

# Geode™ GXm Processor Integrated x86 Solution with MMX Support

### **General Description**

The National Semiconductor<sup>®</sup> Geode<sup>™</sup> GXm processor is an advanced 32-bit x86 compatible processor offering high performance, fully accelerated 2D graphics, a 64-bit synchronous DRAM controller and a PCI bus controller, all on a single chip that is compatible with Intel's MMX technology.


The GXm processor core is a proven design that offers competitive CPU performance. It has integer and floating point execution units that are based on sixth-generation technology. The integer core contains a single, six-stage execution pipeline and offers advanced features such as operand forwarding, branch target buffers, and extensive write buffering. A 16 KB write-back L1 cache is accessed in a unique fashion that eliminates pipeline stalls to fetch operands that hit in the cache.

In addition to the advanced CPU features, the GXm processor integrates a host of functions which are typically implemented with external components. A full-function graphics accelerator provides pixel processing and rendering functions.

A separate on-chip video buffer enables >30 fps MPEG1 video playback when used together with the CS5530 I/O companion chip. Graphics and system memory accesses are supported by a tightly-coupled synchronous DRAM (SDRAM) memory controller. This tightly coupled memory subsystem eliminates the need for an external L2 cache.

The GXm processor includes Virtual System Architecture<sup>®</sup> (VSA<sup>™</sup> technology) enabling XpressGRAPHICS and XpressAUDIO subsystems as well as generic emulation capabilities. Software handler routines for the XpressGRAPHICS and XpressAUDIO subsystems can be included in the BIOS and provide compatible VGA and 16-bit industry standard audio emulation. XpressAUDIO technology eliminates much of the hardware traditionally associated with audio functions.

### Geode™ GXm Processor Internal Block Diagram



National Semiconductor and Virtual System Architecture are registered trademarks of National Semiconductor Corporation. Geode and VSA are trademarks of National Semiconductor Corporation.

For a complete listing of National Semiconductor trademarks, please visit www.national.com/trademarks.

### **Features**

#### **General Features**

- Packaged in:
  - 352-Terminal Ball Grid Array (BGA) or
  - 320-Pin Staggered Pin Grid Array (SPGA)
- 0.35-micron four layer metal CMOS process
- Split rail design (3.3V I/O and 2.9V core)

#### 32-Bit x86 Processor

- Supports the MMX instruction set extension for the acceleration of multimedia applications
- Speeds offered up to 266 MHz
- 16 KB unified L1 cache
- Integrated Floating Point Unit (FPU)
- Re-entrant System Management Mode (SMM) enhanced for VSA

#### **PCI Controller**

- Fixed, rotating, hybrid, or ping-pong arbitration
- Supports up to three PCI bus masters
- Synchronous CPU and PCI bus clock frequency
- Supports concurrency between PCI master and L1 cache

#### **Power Management**

- Designed to support CS5530 power management architecture
- CPU only Suspend or full 3V Suspend supported:
  - Clocks to CPU core stopped for CPU Suspend
  - All on-chip clocks stopped for 3V Suspend
  - Suspend refresh supported for 3V Suspend

### **Virtual Systems Architecture Technology**

- Architecture allows OS independent (software) virtualization of hardware functions
- Provides compatible high performance legacy VGA core functionality

**Note:** GUI (Graphical User Interface) graphics acceleration is pure hardware.

■ Provides 16-bit XpressAUDIO subsystem

### 2D Graphics Accelerator

- Graphics pipeline performance significantly increased over previous generations by pipelining burst reads/writes
- Accelerates BitBLTs, line draw, text
- Supports all 256 raster operations
- Supports transparent BLTs
- Runs at core clock frequency
- Full VGA and VESA mode support
- Special "Driver level" instructions utilize internal scratchpad for enhanced performance

### **Display Controller**

- Video Generator (VG) improves memory efficiency for display refresh with SDRAM
- Supports a separate MPEG1 video buffer and data path to enable video acceleration in the CS5530
- Internal palette RAM for use with the CS5530
- Direct interface to CS5530 for CRT and TFT flat panel support which eliminates need for external RAMDAC
- Hardware frame buffer compressor/decompressor
- Hardware cursor
- Supports up to 1280x1024x8 bpp and 1024x768x16 bpp

### **XpressRAM Subsystem**

- Memory control/interface directly from CPU
- 64-Bit wide memory bus
- Support for:
  - Two 168-pin unbuffered DIMMs
  - Up to 16 open banks simultaneously
  - Single or 16-byte reads (burst length of two)

# **Table of Contents**

1.0	Arch	nitecture Overview	. 8
	1.1	INTEGER UNIT	8
	1.2	FLOATING POINT UNIT	9
	1.3	WRITE-BACK CACHE UNIT	9
	1.4	MEMORY MANAGEMENT UNIT	9
		1.4.1 Internal Bus Interface Unit	9
	1.5	INTEGRATED FUNCTIONS	9
		1.5.1 Graphics Accelerator	9
		1.5.2 Display Controller	
		1.5.3 XpressRAM Memory Subsystem	
		1.5.4 PCI Controller	
	1.6	GEODE GXM/CS5530 SYSTEM DESIGNS	. 11
2.0	Sign	nal Definitions	13
	2.1	PIN ASSIGNMENTS	. 13
	2.2	SIGNAL DESCRIPTIONS	. 24
		2.2.1 System Interface Signals	. 24
		2.2.2 PCI Interface Signals	
		2.2.3 Memory Controller Interface Signals	
		2.2.4 Video Interface Signals	
		2.2.5 Power, Ground, and No Connect Signals	
		2.2.6 Internal Test and Measurement Signals	
	2.3	SUBSYSTEM SIGNAL CONNECTIONS	
	2.4	POWER PLANES	. 36
3.0	Proc	cessor Programming	38
	3.1	CORE PROCESSOR INITIALIZATION	. 38
	3.2	INSTRUCTION SET OVERVIEW	. 39
	3.2	INSTRUCTION SET OVERVIEW	
	3.2		. 39
		3.2.1 Lock Prefix	. 39 . 40 . 40
		3.2.1 Lock Prefix  REGISTER SETS  3.3.1 Application Register Set  3.3.2 System Register Set	. 39 . 40 . 40 . 44
		3.2.1 Lock Prefix  REGISTER SETS  3.3.1 Application Register Set  3.3.2 System Register Set  3.3.3 Model Specific Register Set	. 39 . 40 . 40 . 44 . 59
	3.3	3.2.1 Lock Prefix  REGISTER SETS  3.3.1 Application Register Set  3.3.2 System Register Set  3.3.3 Model Specific Register Set  3.3.4 Time Stamp Counter	. 39 . 40 . 40 . 44 . 59 . 59
		3.2.1 Lock Prefix  REGISTER SETS  3.3.1 Application Register Set  3.3.2 System Register Set  3.3.3 Model Specific Register Set  3.3.4 Time Stamp Counter  ADDRESS SPACES	. 39 . 40 . 40 . 44 . 59 . 59
	3.3	3.2.1 Lock Prefix  REGISTER SETS  3.3.1 Application Register Set  3.3.2 System Register Set  3.3.3 Model Specific Register Set  3.3.4 Time Stamp Counter  ADDRESS SPACES  3.4.1 I/O Address Space	. 39 . 40 . 40 . 59 . 59 . 60
	3.3	3.2.1 Lock Prefix  REGISTER SETS  3.3.1 Application Register Set  3.3.2 System Register Set  3.3.3 Model Specific Register Set  3.3.4 Time Stamp Counter  ADDRESS SPACES  3.4.1 I/O Address Space  3.4.2 Memory Address Space	. 39 . 40 . 44 . 59 . 60 . 60
	3.3 3.4 3.5	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS	. 39 . 40 . 44 . 59 . 60 . 60 . 61
	3.3 3.4 3.5 3.6	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM	. 39 . 40 . 44 . 59 . 60 . 60 . 61
	3.3 3.4 3.5	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 61
	3.3 3.4 3.5 3.6	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 61 . 62
	3.3 3.4 3.5 3.6	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms 3.7.2 Segment Mechanism in Protective Mode	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 61 . 62 . 63
	3.3 3.4 3.5 3.6	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms 3.7.2 Segment Mechanism in Protective Mode 3.7.3 GDTR and LDTR Registers	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 62 . 63 . 66
	3.3 3.4 3.5 3.6	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms 3.7.2 Segment Mechanism in Protective Mode 3.7.3 GDTR and LDTR Registers 3.7.4 Descriptor Bit Structure	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 62 . 62 . 63 . 66 . 67
	3.3 3.4 3.5 3.6 3.7	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms 3.7.2 Segment Mechanism in Protective Mode 3.7.3 GDTR and LDTR Registers 3.7.4 Descriptor Bit Structure 3.7.5 Gate Descriptors	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 62 . 63 . 66 . 67 . 69
	3.3 3.4 3.5 3.6	3.2.1 Lock Prefix REGISTER SETS 3.3.1 Application Register Set 3.3.2 System Register Set 3.3.3 Model Specific Register Set 3.3.4 Time Stamp Counter ADDRESS SPACES 3.4.1 I/O Address Space 3.4.2 Memory Address Space OFFSET, SEGMENT, AND PAGING MECHANISMS OFFSET MECHANISM DESCRIPTORS AND SEGMENT MECHANISMS 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms 3.7.2 Segment Mechanism in Protective Mode 3.7.3 GDTR and LDTR Registers 3.7.4 Descriptor Bit Structure	. 39 . 40 . 44 . 59 . 60 . 60 . 61 . 62 . 63 . 66 . 67 . 69

Table	e of C	ontents	G (Continued)	
	3.10	INTER	RUPTS AND EXCEPTIONS	. 74
		3.10.1	Interrupts	. 74
		3.10.2	Exceptions	. 74
		3.10.3	Interrupt Vectors	. 75
		3.10.4	Interrupt and Exception Priorities	. 76
		3.10.5	Exceptions in Real Mode	. 77
		3.10.6	Error Codes	. 77
	3.11	SYSTE	M MANAGEMENT MODE	. 78
		3.11.1	SMM Enhancements	. 79
		3.11.2	SMM Operation	. 79
		3.11.3	The SMI# Pin	. 80
		3.11.4	SMM Configuration Registers	. 80
		3.11.5	SMM Memory Space Header	. 80
		3.11.6	SMM Instructions	
		3.11.7	SMM Memory Space	
		3.11.8	SMI Generation	
		3.11.9	SMI Service Routine Execution	. 83
	3.12	SHUTE	OOWN AND HALT	. 86
	3.13	PROTE	ECTION	. 86
		3.13.1	Privilege Levels	
		3.13.2	I/O Privilege Levels	. 86
		3.13.3	Privilege Level Transfers	. 87
		3.13.4	Initialization and Transition to Protected Mode	. 87
	3.14	VIRTU	AL 8086 MODE	. 88
		3.14.1	Memory Addressing	. 88
		3.14.2	Protection	
		3.14.3	Interrupt Handling	
		3.14.4	Entering and Leaving Virtual 8086 Mode	
	3.15	FLOAT	ING POINT UNIT OPERATIONS	. 89
		3.15.1	FPU (Floating Point Unit) Register Set	
		3.15.2	FPU Tag Word Register	
		3.15.3	FPU Status Register	
		3.15.4	FPU Mode Control Register	. 89
4.0	Integ	grated F	Functions	91
	4.1	INTEGI	RATED FUNCTIONS PROGRAMMING INTERFACE	. 92
		4.1.1	Graphics Control Register	. 92
		4.1.2	Control Registers	. 94
		4.1.3	Graphics Memory	. 94
		4.1.4	L1 Cache Controller	. 95
		4.1.5	Display Driver Instructions	. 98
		4.1.6	CPU_READ/CPU_WRITE Instructions	. 99
	4.2	INTERI	NAL BUS INTERFACE UNIT	100
		4.2.1	FPU Error Support	100
		4.2.2	A20M Support	100
		4.2.3	SMI Generation	100
		4.2.4	640 KB to 1 MB Region	
		4.2.5	Internal Bus Interface Unit Registers	101

Table	ble of Contents (Continued)				
	4.3	MEMOR	RY CONTROLLER		
		4.3.1	Memory Array Configuration		
		4.3.2	Memory Organizations		
		4.3.3	SDRAM Commands		
		4.3.4	Memory Controller Register Description		
		4.3.5	Address Translation		
		4.3.6	Memory Cycles		
		4.3.7	SDRAM Interface Clocking		
	4.4		IICS PIPELINE		
		4.4.1	BitBLT/Vector Engine		
		4.4.2	Master/Slave Registers		
		4.4.3	Pattern Generation		
		4.4.4	Source Expansion		
		4.4.5	Raster Operations		
		4.4.6	Graphics Pipeline Register Descriptions		
	4.5		AY CONTROLLER		
		4.5.1	Display FIFO		
		4.5.2	Compression Technology		
		4.5.3	Motion Video Acceleration Support		
		4.5.4	Hardware Cursor		
		4.5.5	Display Timing Generator		
		4.5.6	Dither and Frame-Rate Modulation		
		4.5.7	Display Modes		
		4.5.8	Graphics Memory Map		
		4.5.9	Display Controller Registers		
		4.5.10	Memory Organization Registers		
		4.5.11	Timing Registers		
		4.5.12	Cursor Position Registers		
		4.5.13	Color Registers		
		4.5.14	Palette Access Registers		
		4.5.15	CS5530 Display Controller Interface		
	4.6	PCI CO	NTROLLER		
		4.6.1	X-Bus PCI Slave		
		4.6.2	X-Bus PCI Master		
		4.6.3	PCI Arbiter		
		4.6.4	Generating Configuration Cycles		
		4.6.5	Generating Special Cycles		
		4.6.6	PCI Configuration Space Control Registers		
		4.6.7	PCI Configuration Space Registers		
		4.6.8	PCI Cycles		
5.0	Virtu	ıal Subs	system Architecture 165		
	5.1		AL VGA		
		5.1.1	Traditional VGA Hardware		
	5.2	• • • • • • • • • • • • • • • • • • • •	IRTUAL VGA		
	0.2	5.2.1	Datapath Elements		
		5.2.2	Video Refresh		
		5.2.3	GXm VGA Hardware		
		5.2.4	VGA Video BIOS		
		5.2.5	Virtual VGA Register Descriptions		
			-		

Table	e of C	Continued)
6.0	Pow 6.1 6.2 6.3 6.4 6.5	rer Management       174         APM SUPPORT       174         CPU SUSPEND COMMAND REGISTERS       174         SUSPEND MODULATION       174         3-VOLT SUSPEND MODE       174         SUSPEND MODE AND BUS CYCLES       175         6.5.1 Initiating Suspend with SUSP#       175         6.5.2 Initiating Suspend with HALT       176         6.5.3 Responding to a PCI Access During Suspend Mode       177         6.5.4 Stopping the Input Clock       178         GXM PROCESSOR SERIAL BUS       179         6.6.1 Serial Packet Transmission       179         POWER MANAGEMENT REGISTERS       179
7.0	7.1 7.2 7.3 7.4 7.5 7.6	Etrical Specifications.       182         PART NUMBERS       182         ELECTRICAL CONNECTIONS       182         7.2.1 Power/Ground Connections and Decoupling       182         7.2.2 Power Sequencing the Core and I/O Voltages       182         7.2.3 NC-Designated Pins       182         7.2.4 Pull-Up and Pull-Down Resistors       182         7.2.5 Unused Input Pins       182         ABSOLUTE MAXIMUM RATINGS       183         OPERATING CONDITIONS       184         DC CHARACTERISTICS       185         AC CHARACTERISTICS       186
8.0	8.1 8.2	kage Specifications195THERMAL CHARACTERISTICS1958.1.1 Heatsink Considerations196MECHANICAL PACKAGE OUTLINES198
9.0	9.1 9.2 9.3 9.4	ruction Set.       201         GENERAL INSTRUCTION SET FORMAT       202         9.1.1 Prefix (Optional)       203         9.1.2 Opcode       203         9.1.3 mod and r/m Byte (Memory Addressing)       205         9.1.4 reg Field       206         9.1.5 s-i-b Byte (Scale, Indexing, Base)       207         CPUID INSTRUCTION       208         9.2.1 Standard CPUID Levels       208         9.2.2 Extended CPUID Levels       210         PROCESSOR CORE INSTRUCTION SET       212         FPU INSTRUCTION SET       224
	9.5 9.6	MMX INSTRUCTION SET

Table	Table of Contents (Continued)				
Appen	ndix	A Support Documentation	36		
A	A.1	ORDER INFORMATION	36		
A	A.2	DATA BOOK REVISION HISTORY	36		

### 1.0 Architecture Overview

The National Semiconductor Geode GXm processor is an x86-compatible 32-bit microprocessor. The decoupled load/store unit (within the memory management unit) allows multiple instructions in a single clock cycle. Other features include single-cycle execution, single-cycle instruction decode, 16 KB write-back cache, and clock rates up to 266 MHz. These features are made possible by the use of advanced-process technologies and superpipelining.

The GXm processor has low power consumption at all clock frequencies. Where additional power savings are required, designers can make use of Suspend mode, Stop Clock capability, and System Management Mode (SMM).

The GXm processor is divided into major functional blocks (as shown in Figure 1-1):

- Integer Unit
- Floating Point Unit (FPU)
- Write-Back Cache Unit
- · Memory Management Unit (MMU)
- Internal Bus Interface Unit
- · Integrated Functions

Instructions are executed in the integer unit and in the floating point unit. The cache unit stores the most recently used data and instructions and provides fast access to this information for the integer and floating point units.

#### 1.1 INTEGER UNIT

The integer unit consists of:

- Instruction Buffer
- Instruction Fetch
- Instruction Decoder and Execution

The superpipelined integer unit fetches, decodes, and executes x86 instructions through the use of a six-stage integer pipeline.

The instruction fetch pipeline stage generates, from the on-chip cache, a continuous high-speed instruction stream for use by the processor. Up to 128 bits of code are read during a single clock cycle.

Branch prediction logic within the prefetch unit generates a predicted target address for unconditional or conditional branch instructions. When a branch instruction is detected, the instruction fetch stage starts loading instructions at the predicted address within a single clock cycle. Up to 48 bytes of code are queued prior to the instruction decode stage.

The instruction decode stage evaluates the code stream provided by the instruction fetch stage and determines the number of bytes in each instruction and the instruction type. Instructions are processed and decoded at a maximum rate of one instruction per clock.

The address calculation function is super-pipelined and contains two stages, AC1 and AC2. If the instruction refers to a memory operand, AC1 calculates a linear memory address for the instruction.

The AC2 stage performs any required memory management functions, cache accesses, and register file accesses. If a floating point instruction is detected by AC2, the instruction is sent to the floating point unit for processing.

The execution stage, under control of microcode, executes instructions using the operands provided by the address calculation stage.

Write-back, the last stage of the integer unit, updates the register file within the integer unit or writes to the load/store unit within the memory management unit.




Figure 1-1. Internal Block Diagram

#### 1.2 FLOATING POINT UNIT

The FPU (Floating Point Unit) interfaces to the integer unit and the cache unit through a 64-bit bus. The FPU is x87-instruction-set compatible and adheres to the IEEE-754 standard. Because almost all applications that contain FPU instructions also contain integer instructions, the GXm processor's FPU achieves high performance by completing integer and FPU operations in parallel.

FPU instructions are dispatched to the pipeline within the integer unit. The address calculation stage of the pipeline checks for memory management exceptions and accesses memory operands for use by the FPU. Once the instructions and operands have been provided to the FPU, the FPU completes instruction execution independently of the integer unit.

### 1.3 WRITE-BACK CACHE UNIT

The 16 KB write-back unified cache is a data/instruction cache and is configured as four-way set associative. The cache stores up to 16 KB of code and data in 1024 cache lines.

The GXm processor provides the ability to allocate a portion of the L1 cache as a scratchpad, which is used to accelerate the Virtual Systems Architecture algorithms as well as for some graphics operations.

#### 1.4 MEMORY MANAGEMENT UNIT

The memory management unit (MMU) translates the linear address supplied by the integer unit into a physical address to be used by the cache unit and the internal bus interface unit. Memory management procedures are x86-compatible, adhering to standard paging mechanisms.

The MMU also contains a load/store unit that is responsible for scheduling cache and external memory accesses. The load/store unit incorporates two performance-enhancing features:

- Load-store reordering that gives priority to memory reads required by the integer unit over writes to external memory.
- Memory-read bypassing that eliminates unnecessary memory reads by using valid data from the execution unit.

#### 1.4.1 Internal Bus Interface Unit

The internal bus interface unit provides a bridge from the GXm processor to the integrated system functions (i.e., memory subsystem, display controller, graphics pipeline) and the PCI bus interface.

When external memory access is required, the physical address is calculated by the memory management unit and then passed to the internal bus interface unit, which translates the cycle to an X-Bus cycle (the X-Bus is a National Semiconductor proprietary internal bus which provides a common interface for all of the system modules). The X-Bus memory cycle now is arbitrated between

other pending X-Bus memory requests to the SDRAM controller before completing.

In addition, the internal bus interface unit provides configuration control for up to 20 different regions within system memory with separate controls for read access, write access, cacheability, and PCI access.

#### 1.5 INTEGRATED FUNCTIONS

The GXm processor integrates the following functions traditionally implemented using external devices:

- · High-performance 2D graphics accelerator
- Separate CRT and TFT data paths from the display controller
- · SDRAM memory controller
- · PCI bridge

The processor has also been enhanced to support National Semiconductor's proprietary Virtual System Architecture (VSA) implementation.

The GXm processor implements a Unified Memory Architecture (UMA). By using National Semiconductor's Display Compression Technology (DCT), the performance degradation inherent in traditional UMA systems is eliminated.

#### 1.5.1 Graphics Accelerator

The graphics accelerator is a full-featured GUI (Graphical User Interface) accelerator. The graphics pipeline implements a bitBLT engine for frame buffer bitBLTs and rectangular fills. Additional instructions in the integer unit may be processed, as the bitBLT engine assists the CPU in the bitBLT operations that take place between system memory and the frame buffer. This combination of hardware and software is used by the display driver to provide very fast transfers in both directions between system memory and the frame buffer. The bitBLT engine also draws randomly-oriented vectors, and scanlines for polygon fill. All of the pipeline operations described in the following list can be applied to any bitBLT operation.

- Pattern Memory. Render with 8x8 dither, 8x8 monochrome, or 8x1 color pattern.
- Color Expansion. Expand monochrome bitmaps to full-depth 8- or 16-bit colors.
- Transparency. Suppresses drawing of background pixels for transparent text.
- Raster Operations. Boolean operation combines source, destination, and pattern bitmaps.

#### 1.5.2 Display Controller

The display port is a direct interface to the CS5530 which drives a TFT flat panel display, LCD panel, or a CRT display.

The display controller (video generator) retrieves image data from the frame buffer region of memory, performs a color-look-up if required, inserts the cursor overlay into the pixel stream, generates display timing, and formats the pixel data for output to a variety of display devices. The display controller contains Display Compression Technology (DCT) that allows the GXm processor to refresh the display from a compressed copy of the frame buffer. DCT typically decreases the screen-refresh bandwidth requirement by a factor of 15 to 20, further minimizing bandwidth contention.

#### 1.5.3 XpressRAM Memory Subsystem

The memory controller drives a 64-bit SDRAM port directly. The SDRAM memory array contains both the main system memory and the graphics frame buffer. Up to four module banks of SDRAM are supported. Each module bank will have two or four component banks depending on the memory size and organization. The maximum configuration is four module banks with four component banks providing a total of 16 open banks. The maximum memory size is 1 GB.

The memory controller handles multiple requests for memory data from the GXm processor, the graphics accelerator and the display controller. The memory controller contains extensive buffering logic that helps minimize contention for memory bandwidth between graphics and CPU requests. The memory controller cooperates with the internal bus controller to determine the cacheability of all memory references.

#### 1.5.4 PCI Controller

The GXm processor incorporates a full-function PCI interface module that includes the PCI arbiter. All accesses to external I/O devices are sent over the PCI bus, although most memory accesses are serviced by the SDRAM controller. The Internal Bus Interface Unit contains address mapping logic that determines if memory accesses are targeted for the SDRAM or for the PCI bus.

#### 1.6 GEODE GXM/CS5530 SYSTEM DESIGNS

The GXm Integrated Subsystem with MMX support consists of two chips, the GXm Processor and the CS5530 I/O companion. The subsystem provides high performance using 32-bit x86 processing. The two chips integrate video, audio and memory interface functions normally performed by external hardware.

As described in separate manuals, the CS5530 enables the full features of the GXm processor with MMX support. These features include full VGA and VESA video, 16-bit stereo sound, IDE interface, ISA interface, SMM power

management, and AT compatibility logic. In addition, the newer CS5530 provides an Ultra DMA/33 interface, MPEG2 assist, and AC97 Version 2.0 compliant audio.

Figure 1-2 shows a basic block system diagram (refer to Figure 2-4 on page 34 for detailed subsystem interconnection signals). It includes the National Semiconductor CS9210 Dual-Scan Flat Panel Display Controller for designs that need to interface to a DSTN panel (instead of TFT panel).




Figure 1-2. Geode™ GXm/CS5530 System Block Diagram

The CS9210 converts the digital RGB output of the CS5530 I/O companion chip to the digital output suitable for driving a dual-scan color STN (DSTN) flat panel LCD. It connects to the digital RGB output of a GXm processor or 55x0 and drives the graphics data onto a dual-scan flat

panel LCD. It can drive all standard dual-scan color STN flat panels up to 1024x768 resolution. Figure 1-3 shows an example of a CS9210 interface in a typical GXm Integrated Subsystem.




Figure 1-3. CS9210 Interface System Diagram

### 2.0 Signal Definitions

This section describes the external interface of the Geode GXm processor. Figure 2-1 shows the signals organized by their functional interface groups (internal test and electrical pins are not shown).

#### 2.1 PIN ASSIGNMENTS

The tables in this section use several common abbreviations. Table 2-1 lists the mnemonics and their meanings.

Figure 2-2 on page 14 shows the pin assignment for the 352 BGA with Tables 2-2 and 2-3 listing the pin assignments sorted by pin number and alphabetically by signal name, respectively.

Figure 2-3 on page 19 shows the pin assignment for the 320 SPGA with Tables 2-4 and 2-5 listing the pin assignments sorted by pin number and alphabetically by signal name, respectively.

In Section 2.2 "Signal Descriptions" starting on Page 24 a description of each signal is provided within its associated functional group.

Following the signal descriptions, information regarding subsystem signal connections and split power planes and decoupling is provided.

Table 2-1. Pin Type Definitions

Mnemonic	Definition
I	Standard input pin.
I/O	Bidirectional pin.
0	Totem-pole output.
OD	Open-drain output structure that allows multiple devices to share the pin in a wired-OR configuration
PU	Pull-up resistor
PD	Pull-down resistor
s/t/s	Sustained tri-state, an active-low tri-state signal owned and driven by one and only one agent at a time. The agent that drives an s/t/s pin low must drive it high for at least one clock before letting it float. A new agent cannot start driving an s/t/s signal any sooner than one clock after the previous owner lets it float. A pull-up resistor is required to sustain the inactive state until another agent drives it, and must be provided by the central resource.
VCC (PWR)	Power pin.
VSS (GND)	Ground pin
#	The "#" symbol at the end of a signal name indicates that the active, or asserted state occurs when the signal is at a low voltage level. When "#" is not present after the signal name, the signal is asserted when at a high voltage level.





Figure 2-1. Functional Block Diagram



● = GND terminal

= PWR terminal (VCC2 = VCC\_CORE; VCC3 = VCC\_IO)

Figure 2-2. 352 BGA Pin Assignment Diagram

For order information refer to Section A.1 "Order Information" on page 236.

Table 2-2. 352 BGA Pin Assignments - Sorted by Pin Number

		Idoic	Z-Z. 33Z DO	7 1 <u>III 7</u> 8	significates -	_00	i ica i	y Pin Numbe	<sup>71</sup>	
Pin No.	Signal Name	Pin No.	Signal Name	Pin No.	Signal Name		Pin No.	Signal Name	Pin No.	Signal Name
A1	VSS	B23	MD1	D19	VSS		K1	VCC2	T1	PIXEL7
A2	VSS	B24	MD33	D20	VCC3		K2	VCC2	T2	PIXEL8
А3	AD27	B25	VSS	D21	VSS		K3	VCC2	Т3	PIXEL9
A4	AD24	B26	VSS	D22	MD0		K4	VCC2	T4	VSS
A5	AD21	C1	AD29	D23	VSS		K23	VCC2	T23	VSS
A6	AD16	C2	AD31	D24	MD4		K24	VCC2	T24	DQM0
A7	VCC2	C3	AD30	D25	MD36		K25	VCC2	T25	DQM4
A8	FRAME#	C4	AD26	D26	TDN		K26	VCC2	T26	DQM1
A9	DEVSEL#	C5	AD23	E1	GNT2#		L1	CLKMODE1	U1	VCC3
A10	VCC3	C6	AD19	E2	SUSPA#		L2	FP_HSYNC	U2	VCC3
A11	PERR#	C7	VCC2	E3	REQ0#		L3	SERIALP	U3	VCC3
A12	AD15	C8	AD17	E4	AD20		L4	VSS	U4	VCC3
A13	VSS	C9	IRDY#	E23	MD6		L23	VSS	U23	VCC3
A14	AD11		VCC3	E24	TDP		L24	MD11	U24	VCC3
A15	C/BE0#		STOP#	E25	MD5		L25	MD43	U25	
A16	AD6		SERR#	E26	MD37		L26	MD12	U26	
A17	VCC2		C/BE1#	F1			M1	CLKMODE2		PIXEL10
A18	<del> </del>		AD13	F2			M2	VID VAL		PIXEL11
	AD2		AD10	F3			M3	CLKMODE0		PIXEL12
A20			AD8	F4	+	-	M4	VSS		VSS
A21	AD0	C17		F23	1	-	M23	VSS	V23	
A22	AD1		AD5	F24				MD44		DQM5
A23			SMI#	F25				MD13	V25	
A24			VCC3	F26				MD45		CS0#
A25		C21		G1			N1	VSS		PIXEL13
	VSS		IRQ13	G2				PIXEL1	W2	
B1	VSS		MD32	G2 G3	1		N3	PIXEL0		PIXEL14
B2			MD34	G3 G4	+	-	N4	VSS	W4	
B3			MD3	G23			N23	VSS	W23	
	AD25		MD35	G23 G24	1		N23	MD14		RASA#
	AD23 AD22		GNT0#	G24 G25	1					-
B5	AD22 AD18	D1	TDI	-	VCC3			MD46 MD15		RASB# MA0
				-	1			_		
	VCC2		REQ2#	l ——	TMS			VID_CLK		VCC2
	C/BE2#		VSS C/DE2#		SUSP#			PIXEL3		VCC2
	TRDY#		C/BE3#	· ·	REQ1#			PIXEL2		VCC2
	VCC3		VSS	· -	VSS			VSS		VCC2
	LOCK#		VCC2	-	VSS			VSS		VCC2
	PAR		VSS	-	MD8			MD47		VCC2
	AD14		VSS	l	MD40			CASA#		VCC2
	AD12		VCC3	l ——	MD9			SYSCLK		VCC2
	AD9		VSS		FP_VSYNC			PIXEL4		PIXEL15
	AD7		VSS	l ——	TCLK			PIXEL5		PIXEL16
	VCC2		VSS	-	RESET			PIXEL6		CRT_VSYNC
B18	INTR		VSS		VSS			VSS		VSS
	AD3		VSS	l ——	VSS				AA23	
	VCC3		VSS	-	MD41			WEB#	AA24	
	TEST1		VCC2		MD10			WEA#	AA25	1
B22	TEST3	D18	VSS	J26	MD42		R26	CASB#	AA26	MA3

Table 2-2. 352 BGA Pin Assignments - Sorted by Pin Number (Continued)

Pin No.	Signal Name
AB1	DCLK
AB2	PIXEL17
AB3	VID_DATA6
AB4	VID_DATA7
AB23	MA4
AB24	MA5
AB25	MA6
AB26	MA7
AC1	PCLK
AC2	FLT#
AC3	VID_DATA4
AC4	VSS
AC5	VOLDET
AC6	VSS
AC7	VCC2
AC8	VSS
AC9	VSS
AC10	VCC3
AC11	VSS
AC12	VSS
AC13	VSS
AC14	VSS
AC15	VSS

C Z-Z.	332 DGA FII
Pin No.	Signal Name
AC16	VSS
AC17	VCC2
AC18	VSS
AC19	VSS
AC20	VCC3
AC21	VSS
AC22	DQM6
AC23	VSS
AC24	MA8
AC25	MA9
AC26	MA10
AD1	VID_RDY
AD2	VID_DATA5
AD3	VID_DATA3
AD4	VID_DATA0
AD5	ENA_DISP
AD6	MD63
AD7	VCC2
AD8	MD62
AD9	MD29
AD10	VCC3
AD11	MD59
AD12	MD26

Pin No.	Signal Name
AD13	MD56
AD14	MD55
AD15	MD22
AD16	CKEB
AD17	VCC2
AD18	MD51
AD19	MD18
AD20	VCC3
AD21	MD48
AD22	DQM3
AD23	CS1#
AD24	MA11
AD25	BA0
AD26	BA1
AE1	VSS
AE2	VSS
AE3	VID_DATA2
AE4	SDCLK3
AE5	SDCLK1
AE6	RW_CLK
AE7	VCC2
AE8	SDCLK_IN
AE9	MD61

Pin	
No.	Signal Name
AE10	VCC3
AE11	MD28
AE12	MD58
AE13	MD25
AE14	MD24
AE15	MD54
AE16	MD21
AE17	VCC2
AE18	MD20
AE19	MD50
AE20	VCC3
AE21	MD17
AE22	DQM7
AE23	CS3#
AE24	MA12
AE25	VSS
AE26	VSS
AF1	VSS
AF2	VSS
AF3	VID_DATA1
AF4	SDCLK0
AF5	SDCLK2
AF6	MD31

Pin No.	Signal Name
AF7	VCC2
AF8	SDCLK_OUT
AF9	MD30
AF10	VCC3
AF11	MD60
AF12	MD27
AF13	MD57
AF14	VSS
AF15	MD23
AF16	MD53
AF17	VCC2
AF18	MD52
AF19	MD19
AF20	VCC3
AF21	MD49
AF22	MD16
AF23	DQM2
AF24	CKEA
AF25	VSS
AF26	VSS

Table 2-3. 352 BGA Pin Assignments - Sorted Alphabetically by Signal Name

	Tabl	e 2-3. 3
Signal Name	Туре	Pin No.
AD0	I/O	A21
AD1	I/O	A22
AD2	I/O	A19
AD3	I/O	B19
AD4	I/O	A18
AD5	I/O	C18
AD6	I/O	A16
AD7	I/O	B16
AD8	I/O	C16
AD9	I/O	B15
AD10	I/O	C15
AD11	I/O	A14
AD12	I/O	B14
AD13	I/O	C14
AD14	I/O	B13
AD15	I/O	A12
AD16	I/O	A6
AD17	I/O	C8
AD18	I/O	В6
AD19	I/O	C6
AD20	I/O	E4
AD21	I/O	A5
AD22	I/O	B5
AD23	I/O	C5
AD24	I/O	A4
AD25	I/O	B4
AD26	I/O	C4
AD27	I/O	A3
AD28	I/O	B3
AD29	I/O	C1
AD30	I/O	C3
AD31	I/O	C2
BA0	0	AD25
BA1	0	AD26
CASA#	0	P25
CASB#	0	R26
C/BE0#	I/O	A15
C/BE1#	I/O	C13
C/BE2#	I/O	B8
C/BE3#	I/O	D5
CKEA	0	AF24
CKEB	0	AD16
CLKMODE0	ı	M3
CLKMODE1	i	L1
CLKMODE2	i	M1
	0	W2
CRT_HSYNC CRT_VSYNC	0	AA3
CS0#	0	V26
CS0# CS1#	0	
CS1# CS2#		AD23 V25
	0	
CS3#	0	AE23
DEVSEL#	<del>                                     </del>	AB1
DEVSEL#	s/t/s	A9 (PU)

BGA Pin	Assig	nments
Signal Name	Туре	Pin No.
DQM0	0	T24
DQM1	0	T26
DQM2	0	AF23
DQM3	0	AD22
DQM4	0	T25
DQM5	0	V24
DQM6	0	AC22
DQM7	0	AE22
ENA_DISP	0	AD5
FLT#	I	AC2
FP_HSYNC	0	L2
FP_VSYNC	0	J1
FRAME#	s/t/s	A8 (PU)
GNT0#	0	D1
GNT1#	0	F2
GNT2#	0	E1
INTR	I	B18
IRDY#	s/t/s	C9 (PU)
IRQ13	0	C22
LOCK#	s/t/s	B11 (PU)
MA0	0	W26
MA1	0	AA24
MA2	0	AA25
MA3	0	AA26
MA4	0	AB23
MA5	0	AB24
MA6	0	AB25
MA7	0	AB26
MA8	0	AC24
MA9	0	AC25
MA10	0	AC26
MA11	0	AD24
MA12	0	AE24
MD0	I/O	D22
MD1	I/O	B23
MD2	I/O	A24
MD3	I/O	C25
MD4	I/O	D24
MD5	I/O	E25
MD6	I/O	E23
MD7	I/O	F25
MD8	I/O	H24
MD9	I/O	H26
MD10	I/O	J25
MD11	I/O	L24
MD12	I/O	L26
MD13	I/O	M25
MD14	I/O	N24
MD15	I/O	N26
MD16	I/O	AF22
MD17	I/O	AE21
MD18	I/O	AD19
MD19	I/O	AF19

Sorted Alp	habet	ically by
Signal Name	Туре	Pin No.
MD20	I/O	AE18
MD21	I/O	AE16
MD22	I/O	AD15
MD23	I/O	AF15
MD24	I/O	AE14
MD25	I/O	AE13
MD26	I/O	AD12
MD27	I/O	AF12
MD28	I/O	AE11
MD29	I/O	AD9
MD30	I/O	AF9
MD31	I/O	AF6
MD32	I/O	C23
		B24
MD33	1/0	
MD34	1/0	C24
MD35	1/0	C26
MD36	1/0	D25
MD37	I/O	E26
MD38	I/O	F24
MD39	I/O	F26
MD40	I/O	H25
MD41	I/O	J24
MD42	I/O	J26
MD43	I/O	L25
MD44	I/O	M24
MD45	I/O	M26
MD46	I/O	N25
MD47	I/O	P24
MD48	I/O	AD21
MD49	I/O	AF21
MD50	I/O	AE19
MD51	I/O	AD18
MD52	I/O	AF18
MD53	I/O	AF16
MD54	I/O	AE15
MD55	I/O	AD14
MD56	I/O	AD13
MD57	I/O	AF13
MD58	I/O	AE12
MD59	I/O	AD11
MD60	I/O	AF11
MD61	I/O	AE9
MD61	I/O	AD8
MD62 MD63	1/0	AD6
PAR	1/0	B12
PCLK		
	0	AC1
PERR#	s/t/s	A11 (PU)
PIXEL0	0	N3
PIXEL1	0	N2
PIXEL2	0	P3
PIXEL3	0	P2
PIXEL4	0	R1
PIXEL5	0	R2

Signal Name	Туре	Pin No.
PIXEL6	0	R3
PIXEL7	0	T1
PIXEL8	0	T2
PIXEL9	0	Т3
PIXEL10	0	V1
PIXEL11	0	V2
PIXEL12	0	V3
PIXEL13	0	W1
PIXEL14	0	W3
PIXEL15	0	AA1
PIXEL16	0	AA2
PIXEL17	0	AB2
RASA#	0	W24
RASB#	0	W25
REQ0#	ı	E3 (PU)
REQ1#	i	H3 (PU)
REQ2#	<u>'</u>	D3 (PU)
RESET	ı	J3
	0	
RW_CLK		AE6
SDCLK_IN	1	AE8
SDCLK_OUT	0	AF8
SDCLK0	0	AF4
SDCLK1	0	AE5
SDCLK2	0	AF5
SDCLK3	0	AE4
SERIALP	0	L3
SERR#	OD	C12 (PU)
SMI#	!	C19
STOP#	s/t/s	C11 (PU)
SUSP#	1	H2 (PU)
SUSPA#	0	E2
SYSCLK	I	P26
TCLK	I	J2 (PU)
TDI	1	D2 (PU)
TDN	0	D26
TDO	0	F1
TDP	0	E24
TEST	I	F3 (PD)
TEST0	0	C21
TEST1	0	B21
TEST2	0	A23
TEST3	0	B22
TMS	ı	H1 (PU)
TRDY#	s/t/s	B9 (PU)
VCC2	PWR	A7
VCC2	PWR	A17
VCC2	PWR	В7
VCC2	PWR	B17
VCC2	PWR	C7
VCC2	PWR	C17
VCC2	PWR	D7
VCC2	PWR	D17
VCC2	PWR	K1
1002	1 4417	13.1

Table 2-3. 352 BGA Pin Assignments - Sorted Alphabetically by Signal Name (Continued)


Signal Name         Type         Pin No.           VCC2         PWR         K2           VCC2         PWR         K3           VCC2         PWR         K4           VCC2         PWR         K24           VCC2         PWR         K25           VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y3           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y25           VCC2         PWR         Y25           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC2         PWR         AF17           VCC3	<u> </u>	abic 2	J. JJZ
VCC2         PWR         K3           VCC2         PWR         K4           VCC2         PWR         K23           VCC2         PWR         K24           VCC2         PWR         K25           VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y24           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR	Signal Name	Туре	Pin No.
VCC2         PWR         K4           VCC2         PWR         K23           VCC2         PWR         K24           VCC2         PWR         K25           VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y23           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         B20           VCC3         PWR	VCC2	PWR	K2
VCC2         PWR         K23           VCC2         PWR         K24           VCC2         PWR         K25           VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         AC7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         B20           VCC3         PWR	VCC2	PWR	K3
VCC2         PWR         K24           VCC2         PWR         K25           VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC2         PWR         AF10           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR	VCC2	PWR	K4
VCC2         PWR         K25           VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF1           VCC2         PWR         AF1           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B10           VCC3         PWR         C20           VCC3         PWR	VCC2	PWR	K23
VCC2         PWR         K26           VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y23           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR	VCC2	PWR	K24
VCC2         PWR         Y1           VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         B20           VCC3         PWR         D10           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR	VCC2	PWR	K25
VCC2         PWR         Y2           VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR	VCC2	PWR	K26
VCC2         PWR         Y3           VCC2         PWR         Y4           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AD7           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF1           VCC3         PWR         A10           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR	VCC2	PWR	Y1
VCC2         PWR         Y4           VCC2         PWR         Y23           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G2	VCC2	PWR	Y2
VCC2         PWR         Y23           VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AF17           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G2	VCC2	PWR	Y3
VCC2         PWR         Y24           VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD17           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B10           VCC3         PWR         C20           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	Y4
VCC2         PWR         Y25           VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	Y23
VCC2         PWR         Y26           VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF7           VCC2         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	Y24
VCC2         PWR         AC7           VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	Y25
VCC2         PWR         AC17           VCC2         PWR         AD7           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	Y26
VCC2         PWR         AD7           VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G2	VCC2	PWR	AC7
VCC2         PWR         AD17           VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	AC17
VCC2         PWR         AE7           VCC2         PWR         AE17           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	AD7
VCC2         PWR         AE17           VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G2	VCC2	PWR	AD17
VCC2         PWR         AF7           VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	AE7
VCC2         PWR         AF17           VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	AE17
VCC3         PWR         A10           VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	AF7
VCC3         PWR         A20           VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC2	PWR	AF17
VCC3         PWR         B10           VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	A10
VCC3         PWR         B20           VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	A20
VCC3         PWR         C10           VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	B10
VCC3         PWR         C20           VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	B20
VCC3         PWR         D10           VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	C10
VCC3         PWR         D20           VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	C20
VCC3         PWR         G1           VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	D10
VCC3         PWR         G2           VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	D20
VCC3         PWR         G3           VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	G1
VCC3         PWR         G4           VCC3         PWR         G23	VCC3	PWR	G2
VCC3 PWR G23	VCC3	PWR	G3
	VCC3	PWR	G4
VCC3 PWR G24	VCC3	PWR	G23
	VCC3	PWR	G24

Signal Name	Туре	Pin No.
VCC3	PWR	G25
VCC3	PWR	G26
VCC3	PWR	U1
VCC3	PWR	U2
VCC3	PWR	U3
VCC3	PWR	U4
VCC3	PWR	U23
VCC3	PWR	U24
VCC3	PWR	U25
VCC3	PWR	U26
VCC3	PWR	AC10
VCC3	PWR	AC20
VCC3	PWR	AD10
VCC3	PWR	AD20
VCC3	PWR	AE10
VCC3	PWR	AE20
VCC3	PWR	AF10
VCC3	PWR	AF20
VID_CLK	0	P1
VID_DATA0	0	AD4
VID_DATA1	0	AF3
VID_DATA2	0	AE3
VID_DATA3	0	AD3
VID_DATA4	0	AC3
VID_DATA5	0	AD2
VID_DATA6	0	AB3
VID_DATA7	0	AB4
VID_RDY	I	AD1
VID_VAL	0	M2
VOLDET	0	AC5
VSS	GND	A1
VSS	GND	A2
VSS	GND	A13
VSS	GND	A25
VSS	GND	A26
VSS	GND	B1
VSS	GND	B2

	,,	0.9
Signal Name	Туре	Pin No.
VSS	GND	B25
VSS	GND	B26
VSS	GND	D4
VSS	GND	D6
VSS	GND	D8
VSS	GND	D9
VSS	GND	D11
VSS	GND	D12
VSS	GND	D13
VSS	GND	D14
VSS	GND	D15
VSS	GND	D16
VSS	GND	D18
VSS	GND	D19
VSS	GND	D21
VSS	GND	D23
VSS	GND	F4
VSS	GND	F23
VSS	GND	H4
VSS	GND	H23
VSS	GND	J4
VSS	GND	J23
VSS	GND	L4
VSS	GND	L23
VSS	GND	M4
VSS	GND	M23
VSS	GND	N1
VSS	GND	N4
VSS	GND	N23
VSS	GND	P4
VSS	GND	P23
VSS	GND	R4
VSS	GND	R23
VSS	GND	T4
VSS	GND	T23
VSS	GND	V4
VSS	GND	V23

Signal Name	Туре	Pin No.
VSS	GND	W4
VSS	GND	W23
VSS	GND	AA4
VSS	GND	AA23
VSS	GND	AC4
VSS	GND	AC6
VSS	GND	AC8
VSS	GND	AC9
VSS	GND	AC11
VSS	GND	AC12
VSS	GND	AC13
VSS	GND	AC14
VSS	GND	AC15
VSS	GND	AC16
VSS	GND	AC18
VSS	GND	AC19
VSS	GND	AC21
VSS	GND	AC23
VSS	GND	AE1
VSS	GND	AE2
VSS	GND	AE25
VSS	GND	AE26
VSS	GND	AF1
VSS	GND	AF2
VSS	GND	AF14
VSS	GND	AF25
VSS	GND	AF26
WEA#	0	R25
WEB#	0	R24

Note: PU/PD indicates pin is internally connected to a 20-kohm pull-up/down resistor.



Note: Signal names have been abbreviated in this figure due to space constraints.

- = Denotes GND terminal
- = Denotes PWR terminal (VCC2 = VCC\_CORE; VCC3 = VCC\_IO)

Figure 2-3. 320 SPGA Pin Assignment Diagram

For order information refer to Section A.1 "Order Information" on page 236.

Table 2-4. 320 SPGA Pin Assignments - Sorted by Pin Number										
Pin No.	Signal Name	Pin No.	Signal Name	Pin No.	Signal Name		Pin No.	Signal Name	Pin No.	Signal Name
А3	VCC3	C25	AD4	G′	VSS		R34	MD44	AB2	PIXEL12
A5	AD25	C27	AD0	G	CLKMODE2		R36	MD12	AB4	PIXEL13
A7	VSS	C29	VCC2	G	VSS		S1	CLKMODE0	AB34	RASB#
A9	VCC2	C31	IRQ13	G33	3 VSS		S3	VID_VAL	AB36	RASA#
A11	AD16	C33	MD1	G35	MD37	1	S5	PIXEL0	AC1	VCC2
A13	VCC3		MD34	G37	vss	1	S33	MD14		VCC2
A15	STOP#	C37	VCC3	H2	GNT2#	1	S35	MD13	AC5	VCC2
A17		D2	AD30	H	SUSPA#	1	S37	MD45	AC33	VCC2
A19	VSS		AD29	H34	MD6	1	T2	PIXEL1		VCC2
A21	AD11	D6	AD24	H36	6 MD38	1	T4	PIXEL2		VCC2
A23	AD8	D8	AD22	J	TDO	1	T34	MD15	AD2	CRT_HSYNC
	VCC3		AD20	J	3 VSS	1	T36	MD46		DCLK
A27	AD2	-	AD17	J	TEST			VSS	AD34	MA2
A29	VCC2	-	IRDY#	J33	VCC2			VCC3	AD36	MAO
A31			PERR#	-	5 VSS	1		VSS		PIXEL14
A33		-	AD14	J37		1		VSS		VSS
A35			AD12	-	2 REQ1#	1		VCC3		VCC2
A37			AD7		GNT1#	1		VSS		VCC2
B2			INTR	-	MD39			PIXEL3	AE35	
	AD27		TEST1	-	6 MD8	-		VID_CLK	AE37	
	C/BE3#		TEST3		VCC2	1		SYSCLK	-	PIXEL15
	AD21		MD0	L3		1		MD47		PIXEL16
	AD19		MD32	L!		1		PIXEL6	AF34	
	C/BE2#		MD3		VCC2	1		PIXEL5	AF36	
B14			MD35	L35	+	1		PIXEL4		VSS
	LOCK#	-	REQ0#	L37		1		WEA#		PIXEL17
	C/BE1#		REQ2#	-	RESET	-		WEB#		VSS
	AD13		AD28	-	SUSP#	-		CASA#	AG33	
		E7		-	MD40	-		NC	AG35	
	AD6		VCC2	-	6 MD9	-		PIXEL9	AG37	
	AD3		VCC2		VCC3	-		DQM0		CRT_VSYNC
	SMI#		VSS		3 TMS	1		CASB#		VID_DATA6
	AD1		DEVSEL#		S VSS	1		PIXEL8		MA10
	TEST2	-	AD15	-	VSS VSS	1		VSS	AH34	
	MD33		VSS	-	5 MD41	1		PIXEL7	AH36	
	MD2		C/BE0#		VCC3	1		DQM1		PCLK
	VCC3	-	AD5	-	P FP_VSYNC	1		VSS		FTL#
	AD31		VSS	-	TCLK	1		DQM4		VID_DATA5
	AD26		VCC2	-	MD10	1		NC		VSS VSS
	AD23	-	VCC2		6 MD42	1		PIXEL10		VCC2
	VCC2		VSS		SERIALP	-		CS2#		MD31
	AD18	-	MD4		S VSS	1		DQM5		VSS
	FRAME#	-	MD36		NC	1		VCC3		MD60
	VSS		TDN	-	B MD11	$\frac{1}{2}$		PIXEL11		MD57
	PAR		GNT0#		VSS	$\frac{1}{2}$		VSS		VSS
			TDI		+	-				
	VCC3				MD43	-	AA33			MD22
U21	AD10 VSS	F34	MD5 TDP		CLKMODE1 FP_HSYNC	4		VCC3		MD52 VSS

Table 2-4. 320 SPGA Pin Assignments - Sorted by Pin Number (Continued)

Pin No.	Signal Name
AJ27	VCC2
AJ29	VCC2
AJ31	VSS
AJ33	BA1
AJ35	MA9
AJ37	MA7
AK2	VID_RDY
AK4	VSS
AK6	VID_DATA0
AK8	SDCLK0
AK10	SDCLK2
AK12	SDCLK_IN
AK14	MD29
AK16	MD27
AK18	MD56
AK20	MD55
AK22	MD21

Pin No.	Signal Name
AK24	MD20
AK26	MD50
AK28	MD16
AK30	DQM3
AK32	CS3#
AK34	VSS
AK36	BA0
AL1	VCC2
AL3	VID_DATA4
AL5	VID_DATA2
AL7	SDCLK1
AL9	VCC2
AL11	RW_CLK
AL13	SDCLK_OUT
AL15	VSS
AL17	MD58
AL19	VCC3

Pin No.	Signal Name
AL21	MD23
AL23	VSS
AL25	MD19
AL27	MD49
AL29	VCC2
AL31	DQM6
AL33	CKEA
AL35	MA11
AL37	VCC3
AM2	VID_DATA7
AM4	VID_DATA3
AM6	ENA_DISP
AM8	SDCLK3
AM10	MD63
AM12	MD30
AM14	MD61
AM16	MD59

Pin No.	Signal Name
AM18	MD25
AM20	MD24
AM22	MD53
AM24	MD51
AM26	MD18
AM28	MD48
AM30	DQM7
AM32	DQM2
AM34	MA12
AM36	VOLDET
AN1	VSS
AN3	VCC2
AN5	VID_DATA1
AN7	VSS
AN9	VCC2
AN11	MD62
AN13	VCC3

Pin No.	Signal Name
AN15	MD28
AN17	MD26
AN19	VSS
AN21	MD54
AN23	CKEB
AN25	VCC3
AN27	MD17
AN29	VCC2
AN31	VSS
AN33	CS1#
AN35	VCC3
AN37	VSS

Table 2-5. 320 SPGA Pin Assignments - Sorted Alphabetically by Signal Name

	Table	e 2-5. 32
Signal Name	Туре	Pin. No.
AD0	I/O	C27
AD1	I/O	B30
AD2	I/O	A27
AD3	I/O	B26
AD4	I/O	C25
AD5	I/O	E23
AD6	I/O	B24
AD7	I/O	D22
AD8	I/O	A23
AD9	I/O	B22
AD10	I/O	C21
AD11	I/O	A21
AD12	I/O	D20
AD13	I/O	B20
AD14	I/O	D18
AD15	I/O	E17
AD16	I/O	A11
AD17	I/O	D12
AD18	I/O	C11
AD19	I/O	B10
AD20	I/O	D10
AD21	I/O	B8
AD21	I/O	D8
AD23	I/O	C7
AD23 AD24	1/0	D6
	1/0	A5
AD25	1	C5
AD27	1/0	B4
AD27	1/0	
AD28	1/0	E5
AD29	1/0	D4
AD30	1/0	D2
AD31	1/0	C3
BA0	0	AK36
BA1	0	AJ33
CASA#	0	W37
CASB#	0	X36
C/BE0#	I/O	E21
C/BE1#	I/O	B18
C/BE2#	I/O	B12
C/BE3#	I/O	B6
CKEA	0	AL33
CKEB	0	AN23
CLKMODE0	I	S1
CLKMODE1	I	R2
CLKMODE2	I	G3
CRT_HSYNC	0	AD2
CRT_VSYNC	0	AH2
CS0#	0	AA35
CS1#	0	AN33
CS2#	0	Z34
CS3#	0	AK32
DCLK	I	AD4
DEVSEL#	s/t/s	E15 (PU)

SPGA Pin	Assig	nments
Signal Name	Туре	Pin. No.
DQM0	0	X34
DQM1	0	Y33
DQM2	0	AM32
DQM3	0	AK30
DQM4	0	Y37
DQM5	0	Z36
DQM6	0	AL31
DQM7	0	AM30
ENA_DISP	0	AM6
FLT#	I	AJ3
FP_HSYNC	0	R4
FP_VSYNC	0	P2
FRAME#	s/t/s	C13 (PU)
GNT0#	0	F2
GNT1#	0	K4
GNT2#	0	H2
INTR	ı	D24
IRDY#	s/t/s	D14 (PU)
IRQ13	0	C31
LOCK#	s/t/s	B16 (PU)
MA0	0	AD36
MA1	0	AE37
MA2	0	AD34
MA3	0	AF36
MA4	0	AF34
MA5	0	AG35
MA6	0	AH36
MA7	0	AJ37
MA8	0	AH34
MA9	0	AJ35
MA10	0	AH32
MA11	0	AL35
MA12	0	AM34
MD0	1/0	_
		D30
MD1	1/0	C33
MD2	1/0	B36
MD3	1/0	D34
MD4	1/0	E33
MD5	1/0	F34
MD6	1/0	H34
MD7	1/0	J37
MD8	1/0	K36
MD9	1/0	M36
MD10	1/0	P34
MD11	1/0	Q33
MD12	I/O	R36
MD13	I/O	S35
MD14	I/O	S33
MD15	I/O	T34
MD16	I/O	AK28
MD17	I/O	AN27
MD18	I/O	AM26
MD19	I/O	AL25

Sorted Alp	habe	tically b
Signal Name	Туре	Pin. No.
MD20	I/O	AK24
MD21	I/O	AK22
MD22	I/O	AJ21
MD23	I/O	AL21
MD24	I/O	AM20
MD25	I/O	AM18
MD26	I/O	AN17
MD27	I/O	AK16
MD28	I/O	AN15
MD29	I/O	AK14
MD30	I/O	AM12
MD31	I/O	AJ11
MD32	I/O	D32
MD32	I/O	B34
MD34	1/0	C35
MD35	1/0	D36
MD36	I/O	E35
MD37	I/O	G35
MD38	I/O	H36
MD39	I/O	K34
MD40	I/O	M34
MD41	I/O	N35
MD42	I/O	P36
MD43	I/O	Q37
MD44	I/O	R34
MD45	I/O	S37
MD46	I/O	T36
MD47	I/O	V36
MD48	I/O	AM28
MD49	I/O	AL27
MD50	I/O	AK26
MD51	I/O	AM24
MD52	I/O	AJ23
MD53	I/O	AM22
MD54	I/O	AN21
MD55	I/O	AK20
MD56	I/O	AK18
MD57	I/O	AJ17
MD58	I/O	AL17
MD59	I/O	AM16
MD60	I/O	AJ15
MD61		AM14
	1/0	
MD62	1/0	AN11
MD63	I/O	AM10
NC		Q5
NC		X2
NC	110	Z2
PAR	I/O	C17
PCLK	0	AJ1
PERR#	s/t/s	D16 (PU)
PIXEL0	0	S5
PIXEL1	0	T2
PIXEL2	0	T4

PIXEL3         O         V2           PIXEL4         O         W5           PIXEL6         O         W1           PIXEL7         O         Y5           PIXEL8         O         Y1           PIXEL9         O         X4           PIXEL10         O         AA3           PIXEL11         O         AA3           PIXEL12         O         AB2           PIXEL13         O         AE1           PIXEL14         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK2         O         AK10           SDCLK3         O         AK8           SDCLK3         O         AK1           SDCLK3	Signal Name	Туре	Pin. No.
PIXEL5         O         W3           PIXEL6         O         W1           PIXEL7         O         Y5           PIXEL8         O         Y1           PIXEL9         O         X4           PIXEL10         O         Z4           PIXEL11         O         AB3           PIXEL12         O         AB4           PIXEL13         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           RESET         I         M2           RW_CLK         O         AL1           SDCLK_IOUT         O         AL13           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SDCLK3         O         AM8           SERR#         OD         A17 (PU)           SUSP#	PIXEL3	0	V2
PIXEL6         O         W1           PIXEL7         O         Y5           PIXEL8         O         Y1           PIXEL9         O         X4           PIXEL10         O         AA3           PIXEL11         O         AA3           PIXEL12         O         AB4           PIXEL13         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL1           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL3           SDCLK3         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SUSP#	PIXEL4	0	W5
PIXEL7         O         Y5           PIXEL8         O         Y1           PIXEL9         O         X4           PIXEL10         O         Z4           PIXEL11         O         AA3           PIXEL12         O         AB2           PIXEL13         O         AB4           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           RESC1#         I         K2 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK, OUT         O         AL3           SDCLK, OUT         O         AL7           SDCLK3         O         AM8           SERIALP         O         Q1           SDCLK3         O         AM8           SERIALP         O         Q1           SSM#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP# <td>PIXEL5</td> <td>0</td> <td>W3</td>	PIXEL5	0	W3
PIXEL8         O         Y1           PIXEL9         O         X4           PIXEL10         O         Z4           PIXEL11         O         AA3           PIXEL12         O         AB2           PIXEL13         O         AB4           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL3           SDCLK_OUT         O         AK8           SDCLK3         O         AM8           SERIALP         O         Q1           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         M4 (PU)           SUSP#<	PIXEL6	0	W1
PIXEL9         O         X4           PIXEL10         O         Z4           PIXEL11         O         AA3           PIXEL12         O         AB2           PIXEL13         O         AB4           PIXEL14         O         AF2           PIXEL15         O         AF2           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK,IN         I         AK12           SDCLKO         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUS	PIXEL7	0	Y5
PIXEL10         O         Z4           PIXEL11         O         AA3           PIXEL12         O         AB2           PIXEL13         O         AB4           PIXEL14         O         AF2           PIXEL15         O         AF4           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)	PIXEL8	0	Y1
PIXEL11         O         AA3           PIXEL12         O         AB2           PIXEL13         O         AB4           PIXEL14         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASA#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4	PIXEL9	0	X4
PIXEL12         O         AB2           PIXEL13         O         AB4           PIXEL14         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL13           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4	PIXEL10	0	Z4
PIXEL13         O         AB4           PIXEL14         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL3           SDCLKO         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCL	PIXEL11	0	AA3
PIXEL14         O         AE1           PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK, IN         I         AK12           SDCLK, OUT         O         AL3           SDCLKO         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         Y34           TCLK         I         P4 (PU) <t< td=""><td>PIXEL12</td><td>0</td><td>AB2</td></t<>	PIXEL12	0	AB2
PIXEL15         O         AF2           PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK,IN         I         AK12           SDCLKO         O         AK8           SDCLKO         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         S/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         Y4 (PU)	PIXEL13	0	AB4
PIXEL16         O         AF4           PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL3           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)	PIXEL14	0	AE1
PIXEL17         O         AG3           RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL7           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)	PIXEL15	0	AF2
RASA#         O         AB36           RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         E3 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL7           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         P4 (PU)           TDN         O         E37           TDO         O         J1           <	PIXEL16	0	AF4
RASB#         O         AB34           REQ0#         I         E1 (PU)           REQ1#         I         E3 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL13           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1	PIXEL17	0	AG3
REQ0#         I         E1 (PU)           REQ1#         I         K2 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLKO         O         AL3           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SER#         OD         A17 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDN         O         E37           TDO         O         J1           TDN         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3	RASA#	0	AB36
REQ1#         I         K2 (PU)           REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLKO         O         AL3           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP##         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDN         O         E37           TDO         O         J1           TDN         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3	RASB#	0	AB34
REQ2#         I         E3 (PU)           RESET         I         M2           RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2	REQ0#	ı	E1 (PU)
RESET I M2  RW_CLK O AL11  SDCLK_IN I AK12  SDCLK_OUT O AL13  SDCLK0 O AK8  SDCLK1 O AK10  SDCLK2 O AK10  SDCLK3 O AM8  SERIALP O Q1  SERR# OD A17 (PU)  SMI# I B28  STOP# S/t/s A15 (PU)  SUSP# I M4 (PU)  SUSP# I W4 (PU)  SUSPA# O H4  SYSCLK I Y34  TCLK I P4 (PU)  TDI I F4 (PU)  TDI I F4 (PU)  TDN O E37  TDO O J1  TDP O F36  TEST I J5 (PD)  TESTO O A33  TEST1 O D26  TEST2 O B32  TEST3 O D28  TMS I N3 (PU)  TRDY# S/t/s B14 (PU)  VCC2 PWR A9  VCC2 PWR A29  VCC2 PWR C29  VCC2 PWR C29  VCC2 PWR C29  VCC2 PWR C29	REQ1#	ı	K2 (PU)
RW_CLK         O         AL11           SDCLK_IN         I         AK12           SDCLK_OUT         O         AL13           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSP##         I         M4 (PU)           SUSP##         I         P4 (PU)           TD         I         F4 (PU)           TDN         O         E37           TDN         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26	REQ2#	ı	E3 (PU)
SDCLK_IN         I         AK12           SDCLK_OUT         O         AL13           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#	RESET	ı	M2
SDCLK_OUT         O         AL13           SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2	RW_CLK	0	AL11
SDCLK0         O         AK8           SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDN         O         E37           TDO         O         J1           TDN         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2 <t< td=""><td>SDCLK_IN</td><td>ı</td><td>AK12</td></t<>	SDCLK_IN	ı	AK12
SDCLK1         O         AL7           SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2         <	SDCLK_OUT	0	AL13
SDCLK2         O         AK10           SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2         PWR         C9           VCC2 <t< td=""><td>SDCLK0</td><td>0</td><td>AK8</td></t<>	SDCLK0	0	AK8
SDCLK3         O         AM8           SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	SDCLK1	0	AL7
SERIALP         O         Q1           SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	SDCLK2	0	AK10
SERR#         OD         A17 (PU)           SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	SDCLK3	0	AM8
SMI#         I         B28           STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	SERIALP	0	Q1
STOP#         s/t/s         A15 (PU)           SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         E9	SERR#	OD	A17 (PU)
SUSP#         I         M4 (PU)           SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	SMI#	I	B28
SUSPA#         O         H4           SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	STOP#	s/t/s	A15 (PU)
SYSCLK         I         V34           TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	SUSP#	I	M4 (PU)
TCLK         I         P4 (PU)           TDI         I         F4 (PU)           TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	SUSPA#	0	H4
TDI I F4 (PU) TDN O E37 TDO O J1 TDP O F36 TEST I J5 (PD) TEST0 O A33 TEST1 O D26 TEST2 O B32 TEST3 O D28 TMS I N3 (PU) TRDY# s/t/s B14 (PU) VCC2 PWR A9 VCC2 PWR A29 VCC2 PWR C9 VCC2 PWR C9 VCC2 PWR C9 VCC2 PWR E9	SYSCLK	ı	V34
TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	TCLK	ı	P4 (PU)
TDN         O         E37           TDO         O         J1           TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C9           VCC2         PWR         E9	TDI	ı	F4 (PU)
TDP         O         F36           TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TDN	0	
TEST         I         J5 (PD)           TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TDO	0	J1
TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TDP	0	F36
TEST0         O         A33           TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TEST	ı	J5 (PD)
TEST1         O         D26           TEST2         O         B32           TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TEST0	0	
TEST3         O         D28           TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TEST1	0	D26
TMS         I         N3 (PU)           TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TEST2	0	B32
TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TEST3	0	D28
TRDY#         s/t/s         B14 (PU)           VCC2         PWR         A9           VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TMS	I	N3 (PU)
VCC2         PWR         A29           VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	TRDY#	s/t/s	
VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	VCC2	PWR	A9
VCC2         PWR         C9           VCC2         PWR         C29           VCC2         PWR         E9	VCC2	PWR	A29
VCC2 PWR E9	VCC2		C9
VCC2 PWR E9			
VCC2 PWR E11	VCC2	PWR	E9
	VCC2		

Table 2-5. 320 SPGA Pin Assignments - Sorted Alphabetically by Signal Name (Continued)

	Table 2	2-5. 320
Signal Name	Туре	Pin. No.
VCC2	PWR	E27
VCC2	PWR	E29
VCC2	PWR	J33
VCC2	PWR	L1
VCC2	PWR	L3
VCC2	PWR	L5
VCC2	PWR	L33
VCC2	PWR	L35
VCC2	PWR	L37
VCC2	PWR	AC1
VCC2	PWR	AC3
VCC2	PWR	AC5
VCC2	PWR	AC33
VCC2	PWR	AC35
VCC2	PWR	AC37
VCC2	PWR	AE5
VCC2	PWR	AE33
VCC2	PWR	AJ9
VCC2	PWR	AJ27
VCC2	PWR	AJ29
VCC2	PWR	AL1
VCC2	PWR	AL9
VCC2	PWR	AL29
VCC2	PWR	AN3
VCC2	PWR	AN9
VCC2	PWR	AN29
VCC3	PWR	A3
VCC3	PWR	A13
VCC3	PWR	A25

Signal Name	Туре	Pin. No.	
VCC3	PWR	A35	
VCC3	PWR	C1	
VCC3	PWR	C19	
VCC3	PWR	C37	
VCC3	PWR	N1	
VCC3	PWR	N37	
VCC3	PWR	U3	
VCC3	PWR	U35	
VCC3	PWR	AA1	
VCC3	PWR	AA37	
VCC3	PWR	AL19	
VCC3	PWR	AL37	
VCC3	PWR	AN13	
VCC3	PWR	AN25	
VCC3	PWR	AN35	
VID_CLK	0	V4	
VID_DATA0	0	AK6	
VID_DATA1	0	AN5	
VID_DATA2	0	AL5	
VID_DATA3	0	AM4	
VID_DATA4	0	AL3	
VID_DATA5	0	AJ5	
VID_DATA6	0	AH4	
VID_DATA7	0	AM2	
VID_RDY	I	AK2	
VID_VAL	0	S3	
VOLDET	0	AM36	
VSS	GND	A7	
VSS	GND	A19	

Signal Name	Туре	Pin. No.
VSS	GND	A31
VSS	GND	A37
VSS	GND	B2
VSS	GND	C15
VSS	GND	C23
VSS	GND	E7
VSS	GND	E13
VSS	GND	E19
VSS	GND	E25
VSS	GND	E31
VSS	GND	G1
VSS	GND	G5
VSS	GND	G33
VSS	GND	G37
VSS	GND	J3
VSS	GND	J35
VSS	GND	N5
VSS	GND	N33
VSS	GND	Q3
VSS	GND	Q35
VSS	GND	U1
VSS	GND	U5
VSS	GND	U33
VSS	GND	U37
VSS	GND	Y3
VSS	GND	Y35
VSS	GND	AA5
VSS	GND	AA33
VSS	GND	AE3

Signal Name	Туре	Pin. No.
VSS	GND	AE35
VSS	GND	AG1
VSS	GND	AG5
VSS	GND	AG33
VSS	GND	AG37
VSS	GND	AJ7
VSS	GND	AJ13
VSS	GND	AJ19
VSS	GND	AJ25
VSS	GND	AJ31
VSS	GND	AK4
VSS	GND	AK34
VSS	GND	AL15
VSS	GND	AL23
VSS	GND	AN1
VSS	GND	AN7
VSS	GND	AN19
VSS	GND	AN31
VSS	GND	AN37
WEA#	0	W33
WEB#	0	W35

Note: PU/PD indicates pin is internally connected to a 20-kohm pull-up/ down resistor

## 2.2 SIGNAL DESCRIPTIONS

## 2.2.1 System Interface Signals

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
SYSCLK	P26	V34	I	System Clock
				System Clock runs synchronously with the PCI bus. The internal clock of the GXm processor is generated by an internal PLL which multiplies the SYSCLK input and can run up to eight times faster. The SYSCLK to core clock multiplier is configured using the CLKMOD[2:0] inputs.
				The SYSCLK input is a fixed frequency which can only be stopped or varied when the GXm processor is in a full 3V Suspend. (Section 6.4 "3-Volt Suspend Mode" on page 174 for details regarding this mode.)
CLKMODE[2:0]	M1, L1,	G3, R2,	I	Clock Mode
	M3	S1		These signals are used to set the core clock multiplier. The PCI clock "SYSCLK" is multiplied by the value programmed by CLK-MODE[2:0] to generate the GXm processor's core clock. CLKMODE2 is valid only for GXm processor revision 4.0 and up. The value read from DIR1 (Device ID Register 1, refer to page 51) affects the definition of the CLKMODE pins.
				If DIR1 = 30h-33h then CLKMODE[1:0]: 00 = SYSCLK multiplied by 4 (Test mode only) 01 = SYSCLK multiplied by 6 10 = SYSCLK multiplied by 7 11 = SYSCLK multiplied by 5
				If DIR1 = 34h-4Fh then CLKMODE[1:0]:  00 = SYSCLK multiplied by 4 (Test mode only)  01 = SYSCLK multiplied by 6  10 = SYSCLK multiplied by 7  11 = SYSCLK multiplied by 8
				If DIR1 > or = 50h then CLKMODE[2:0]:  000 = SYSCLK multiplied by 4 (Test mode only)  001 = SYSCLK multiplied by 10  010 = SYSCLK multiplied by 9  011 = SYSCLK multiplied by 5  100 = SYSCLK multiplied by 4  101 = SYSCLK multiplied by 6  110 = SYSCLK multiplied by 7  111 = SYSCLK multiplied by 8
RESET	J3	M2	I	Reset
				RESET aborts all operations in progress and places the GXm processor into a reset state. RESET forces the CPU and peripheral functions to begin executing at a known state. All data in the on-chip cache is invalidated.
				RESET is an asynchronous input but must meet specified setup and hold times to guarantee recognition at a particular clock edge. This input is typically generated during the Power-On-Reset sequence.
				<b>Note:</b> Warm Reset does not require an input on the GXm processor since the function is virtualized using SMM.

## 2.2.1 System Interface Signals (Continued)

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
INTR	B18	D24	I	(Maskable) Interrupt Request
				INTR is a level-sensitive input that causes the GXm processor to Suspend execution of the current instruction stream and begin execution of an interrupt service routine. The INTR input can be masked through the Flags Register IF bit. (See Table 3-4 on page 43 for bit definitions.)
IRQ13	C22	C31	0	Interrupt Request Level 13
				IRQ13 is asserted if an on-chip floating point error occurs.
				When a floating point error occurs, the GXm processor asserts the IRQ13 pin. The floating point interrupt handler then performs an OUT instruction to I/O address F0h or F1h. The GXm processor accepts either of these cycles and clears the IRQ13 pin.
				Refer to Section 3.4.1 "I/O Address Space" on page 60 for further information on IN/OUT instructions.
SMI#	C19	B28	- 1	System Management Interrupt
				SMI# is a level-sensitive interrupt. SMI# puts the GXm processor into System Management Mode (SMM).
SUSP#	H2	M4	I	Suspend Request
	(PU)	(PU)		This signal is used to request that the GXm processor enter Suspend mode. After recognition of an active SUSP# input, the processor completes execution of the current instruction, any pending decoded instructions and associated bus cycles. SUSP# is ignored following RESET# and is enabled by setting the SUSP bit in CCR2. (See Table 16 on page 44 for CCR2 bit definitions.)
				Since the GXm processor includes system logic functions as well as the CPU core, there are special modes designed to support the different power management states associated with APM, ACPI, and portable designs. The part can be configured to stop only the CPU core clocks, or all clocks. When all clocks are stopped, the external clock can also be stopped. (See Section 6.0 "Power Management" on page 174 for more details regarding power management states.)
				This pin is internally connected to a 20-kohm pull-up resistor. SUSP# is pulled up when not active.
SUSPA#	E2	H4	0	Suspend Acknowledge
				Suspend Acknowledge indicates that the GXm processor has entered low-power Suspend mode as a result of SUSP# assertion or execution of a HALT instruction. SUSPA# is enabled by setting the SUSP bit in CCR2. (See Table 16 on page 44 for CCR2 bit definitions.)
				The SYSCLK input may be stopped after SUSPA# has been asserted to further reduce power consumption if the system is configured for 3V Suspend mode. (Section 6.4 "3-Volt Suspend Mode" on page 174 for details regarding this mode.)
SERIALP	L3	Q1	0	Serial Packet
				Serial Packet is the single wire serial-transmission signal to the CS5530 chip. The clock used for this interface is the PCI clock (SYSCLK). This interface carries packets of miscellaneous information to the chipset to be used by the VSA software handlers.

## 2.2.2 PCI Interface Signals

Signal Name	BGA Pin No.	SPGA Pin No	Туре	Description
AD[31:0]	Refer to Table 2-3	Refer to Table 2-5	I/O	Multiplexed Address and Data  Addresses and data are multiplexed on the same PCI pins. A bus transaction consists of an address phase in the cycle in which FRAME# is asserted followed by one or more data phases. During the address phase, AD[31:0] contain a physical 32-bit address. For I/O, this is a byte address, for configuration and memory it is a DWORD address. During data phases, AD[7:0] contain the least significant byte (LSB) and AD[31:24] contain the most significant byte (MSB). Write data is stable and valid when IRDY# is asserted and read data is stable and valid when TRDY# is asserted. Data is transferred during those SYSCLKS where both IRDY# and TRDY# are asserted.
C/BE[3:0]#	D5, B8, C13, A15	B6, B12, B18, E21	I/O	Multiplexed Command and Byte Enables  Bus command and byte enables are multiplexed on the same PCI pins. During the address phase of a transaction when FRAME# is active, C/BE[3:0]# define the bus command. During the data phase C/BE[3:0]# are used as byte enables. The byte enables are valid for the entire data phase and determine which byte lanes carry meaningful data. C/BE0# applies to byte 0 (LSB) and C/BE3# applies to byte 3 (MSB).  The command encoding and types are listed below.  0000 = Interrupt Acknowledge 0001 = Special Cycle 0010 = I/O Read 0011 = I/O Write 0100 = Reserved 0110 = Memory Read 0111 = Memory Write 1000 = Reserved 1001 = Reserved 1011 = Configuration Read 1011 = Configuration Write 1100 = Memory Read Multiple 1101 = Dual Address Cycle (Reserved) 1110 = Memory Read Line 1111 = Memory Write and Invalidate
PAR	B12	C17	I/O	Parity Parity generation is required by all PCI agents: the master drives PAR for address and write-data phases, the target drives PAR for read-data phases. Parity is even across AD[31:0] and C/BE[3:0]#.  For address phases, PAR is stable and valid one SYSCLK after the address phase. It has the same timing as AD[31:0] but delayed by one SYSCLK.  For data phases, PAR is stable and valid one SYSCLK after either IRDY# is asserted on a write transaction or after TRDY# is asserted on a read transaction. Once PAR is valid, it remains valid until one SYSCLK after the completion of the data phase. (Also see PERR#.)

## 2.2.2 PCI Interface Signals (Continued)

Signal Name	BGA Pin No.	SPGA Pin No	Туре	Description
FRAME#	A8 (PU)	C13 (PU)	s/t/s	Frame  Cycle Frame is driven by the current master to indicate the beginning and duration of an access. FRAME# is asserted to indicate a bus transaction is beginning. While FRAME# is asserted, data transfers continue. When FRAME# is deasserted,
				the transaction is in the final data phase.  This pin is internally connected to a 20-kohm pull-up resistor.
IRDY#	C9 (PU)	D14 (PU)	s/t/s	Initiator Ready Initiator Ready is asserted to indicate that the bus master is able to complete the current data phase of the transaction. IRDY# is used in conjunction with TRDY#. A data phase is completed on any SYSCLK in which both IRDY# and TRDY# are sampled asserted. During a write, IRDY# indicates valid data is present on AD[31:0]. During a read, it indicates the master is prepared to accept data. Wait cycles are inserted until both IRDY# and TRDY# are asserted together.
				This pin is internally connected to a 20-kohm pull-up resistor.
TRDY#	B9 (PU)	B14 (PU)	s/t/s	Target Ready  TRDY# is asserted to indicate that the target agent is able to complete the current data phase of the transaction. TRDY# is used in conjunction with IRDY#. A data phase is complete on any SYSCLK in which both TRDY# and IRDY# are sampled asserted. During a read, TRDY# indicates that valid data is present on AD[31:0]. During a write, it indicates the target is prepared to accept data. Wait cycles are inserted until both IRDY# and TRDY# are asserted together.  This pin is internally connected to a 20-kohm pull-up resistor.
STOP#	C11 (PU)	A15 (PU)	s/t/s	Target Stop  STOP# is asserted to indicate that the current target is requesting the master to stop the current transaction. This signal is used with DEVSEL# to indicate retry, disconnect or target abort. If STOP# is sampled active while a master, FRAME# will be deasserted and the cycle stopped within three SYSCLK cycles. As an input, STOP# can be asserted in the following cases. 1) If a PCI master tries to access memory that has been locked by another master. This condition is detected if FRAME# and LOCK# are asserted during an address phase. 2) STOP# will also be asserted if the PCI write buffers are full or if a previously buffered cycle has not completed. 3) Finally, STOP# can be asserted on read cycles that cross cache line boundaries. This is conditional based upon the programming of bit 1 in PCI Control Function 2 Register. (See Table 4-37 on page 156 for programming details.)

## 2.2.2 PCI Interface Signals (Continued)

Signal Name	BGA Pin No.	SPGA Pin No	Туре	Description
LOCK#	B11 (PU)	B16 (PU)	s/t/s	Lock Operation  LOCK# indicates an atomic operation that may require multiple transactions to complete. When LOCK# is asserted, nonexclusive transactions may proceed to an address that is not currently locked (at least 16 bytes must be locked). A grant to start a transaction on PCI does not guarantee control of LOCK#. Control of LOCK# is obtained under it own protocol in conjunction with GNT#. It is possible for different agents to use PCI while a single master retains ownership of LOCK#. The arbiter can implement a complete system lock. In this mode, if LOCK# is active, no other master can gain access to the system until the LOCK# is deasserted.  This pin is internally connected to a 20-kohm pull-up resistor.
DEVSEL#	A9 (PU)	E15 (PU)	s/t/s	Device Select  DEVSEL# indicates that the driving device has decoded its address as the target of the current access. As an input, DEVSEL# indicates whether any device on the bus has been
				selected. DEVSEL# will also be driven by any agent that has the ability to accept cycles on a subtractive decode basis. As a master, if no DEVSEL# is detected within and up to the subtractive decode clock, a master abort cycle will result expect for special cycles which do not expect a DEVSEL# returned.
				This pin is internally connected to a 20-kohm pull-up resistor.
PERR#	A11 (PU)	D16 (PU)	s/t/s	Parity Error  PERR# is used for reporting of data parity errors during all PCI transactions except a Special Cycle. The PERR# line is driven two SYSCLKs after the data in which the error was detected. This is one SYSCLK after the PAR that is attached to the data. The minimum duration of PERR# is one SYSCLK for each data phase in which a data parity error is detected. PERR# must be driven high for one SYSCLK before being in TRI-STATE mode. A target asserts PERR# on write cycles if it has claimed the cycle with DEVSEL#. The master asserts PERR# on read cycles.
0500"	040	0.47	0.0	This pin is internally connected to a 20-kohm pull-up resistor.
SERR#	C12 (PU)	A17 (PU)	OD	System Error  System Error may be asserted by any agent for reporting errors other than PCI parity. The intent is to have the PCI central agent assert NMI to the processor. When the Parity Enable bit is set in the Memory Controller Configuration register, SERR# will be asserted upon detecting a parity error on read operations from DRAM.
REQ[2:0]#	D3,	E3,	I	Request Lines
H3, E3 (PU)		E3 E1		Request indicates to the arbiter that an agent desires use of the bus. Each master has its own REQ# line. REQ# priorities are based on the arbitration scheme chosen.
				Each of these pins are internally connected to a 20-kohm pull-up resistor.

## 2.2.2 PCI Interface Signals (Continued)

Signal Name	BGA Pin No.	SPGA Pin No	Туре	Description
GNT[2:0]#	E1, F2, D1	H2, K4, F2	0	Grant Lines Grant indicates to the requesting master that it has been granted access to the bus. Each master has its own GNT# line. GNT# can be pulled away at any time a higher REQ# is received or if the master does not begin a cycle within a minimum period of time (16 SYSCLKs).

### 2.2.3 Memory Controller Interface Signals

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
tem board		C DIMM co	nnectors. I	wo types of memory configurations: SDRAM modules on the sys- Refer to Section 4.3 "Memory Controller" on page 103 for detailed
MD[63:0]	Refer to Table 2-3	Refer to Table 2-5	I/O	Memory Data Bus The data bus lines driven to/from system memory.
MA[12:0]	Refer to Table 2-3	Refer to Table 2-5	0	Memory Address Bus  The multiplexed row/column address lines driven to the system memory.  Supports 256 Mbit SDRAM.
BA[1:0]	AD26, AD25	AJ33, AK36	0	Bank Address Bits  These bits are used to select the component bank within the SDRAM.
CS[3:0]#	AE23, V25, AD23, V26	AK32, Z34, AN33, AA35	0	Chip Selects  The chip selects are used to select the module bank within the system memory. Each chip select corresponds to a specific module bank.  If CS# is high, the bank(s) do not respond to RAS#, CAS#, WE# until the bank is selected again.
RASA#, RASB#	W24, W25	AB36, AB34	0	Row Address Strobe  RAS#, CAS#, WE# and CKE are encoded to support the different SDRAM commands. RASA# is used with CS[1:0]#. RASB# is used with CS[3:2]#.
CASA#, CASB#	P25, R26	W37, X36	0	Column Address Strobe  RAS#, CAS#, WE# and CKE are encoded to support the different SDRAM commands. CASA# is used with CS[1:0]#. CASB# is used with CS[3:2]#.
WEA#, WEB#	R25, R24	W33, W35	0	Write Enable  RAS#, CAS#, WE# and CKE are encoded to support the different SDRAM commands. WEA# is used with CS[1:0]#. WEB# is used with CS[3:2]#.

## 2.2.3 Memory Controller Interface Signals (Continued)

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
DQM[7:0]	Refer	Refer	0	Data Mask Control Bits
	to Table 2-3	to Table 2-5		During memory read cycles, these outputs control whether the SDRAM output buffers are driven on the MD bus or not. All DQM signals are asserted during read cycles.
				During memory write cycles, these outputs control whether or not MD data will be written into the SDRAM.
				DQM[7:0] connect directly to the DQM7-0 pins of each connector.
CKEA,	AF24,	AL33,	0	Clock Enable
CKEB	AD16	AN23		For normal operation CKE is held high. CKE goes low during Suspend.
SDCLK[3:0]	AE4,	AM8,	0	SDRAM Clocks
	AF5, AE5, AF4	AK10, AL7, AK8		The SDRAM samples all the control, address, and data using these clocks.
SDCLK_IN	AE8	AK12	I	SDRAM Clock Input
				The GXm processor samples the memory read data on this clock. Works in conjunction with the SDCLK_OUT signal.
SDCLK_OUT	AF8	AL13	0	SDRAM Clock Output
				This output is routed back to SDCLK_IN. The board designer should vary the length of the board trace to control skew between SDCLK_IN and SDCLK.

## 2.2.4 Video Interface Signals

Signal Name	BGA Pin No	SPGA Pin No	Туре	Description
PCLK	AC1	AJ1	0	Pixel Port Clock
				Pixel Port Clock represents the pixel dotclock or a 2x multiple of the dotclock for some 16-bit-per-pixel modes. It determines the data transfer rate from the GXm processor to the CS5530.
VID_CLK	P1	V4	0	Video Clock
				Video Clock represents the video port clock to the CS5530. This pin is only used if the Video Port is enabled.
DCLK	AB1	AD4	I	DOT Clock
				The DCLK input is driven from the CS5530 and represents the pixel dot clock. In some cases, such as when displaying 16 BPP data with an eight-bit-graphics pixel port, this clock will actually be a 2x multiple of the dotclock.
CRT_HSYNC	W2	AD2	0	CRT Horizontal Sync
				CRT Horizontal Sync establishes the line rate and horizontal retrace interval for an attached CRT. The polarity is programmable and depends on the display mode.

## 2.2.4 Video Interface Signals (Continued)

Signal Name	BGA Pin No	SPGA Pin No	Туре	Description
CRT_VSYNC	AA3	AH2	0	CRT Vertical Sync
				CRT Vertical Sync establishes the screen refresh rate and vertical retrace interval for an attached CRT. The polarity is programmable and depends on the display mode.
FP_HSYNC	L2	R4	0	Flat Panel Horizontal Sync
				Flat Panel Horizontal Sync establishes the line rate and horizontal retrace interval for a TFT display. Polarity is programmable and depends on the display mode.
				This signal is an input to the CS5530. The CS5530 re-drives this signal to the flat panel.
				If no flat panel is used in the system, this signal does not need to be connected.
FP_VSYNC	J1	P2	0	Flat Panel Vertical Sync
				Flat Panel Vertical Sync establishes the screen refresh rate and vertical retrace interval for a TFT display. Polarity is programmable and depends on the display mode.
				This signal is an input to the CS5530. The CS5530 re-drives this signal to the flat panel.
				If no flat panel is used in the system, this signal does not need to be connected.
ENA_DISP	AD5	AM6	0	Display Enable
				Display Enable indicates the active display portion of a scan line to the CS5530.
				In a CS5530-based system, this signal is required to be connected even if there is no TFT panel in the system.
VID_RDY	AD1	AK2	I	Video Ready
				This input signal indicates that the video FIFO in the CS5530 is ready to receive more data.
VID_VAL	M2	S3	0	Video Valid
				VID_VAL qualifies valid video data to the CS5530.
VID_DATA[7:0] R	Refer	Refer	0	Video Data Bus
	to	to Table 2-5		When the Video Port is enabled, this bus drives Video (Y-U-V) data synchronous to the VID_CLK output.
PIXEL[17:0]	Refer	Refer	0	Graphics Pixel Data Bus
	to Table 2-3	to Table 2-5		This bus drives graphics pixel data synchronous to the PCLK output.

### 2.2.5 Power, Ground, and No Connect Signals

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
VOLDET	AC5	AM36	0	Voltage Detect
				In early schematic revisions this pin was identified as VOLDET. However, in the production version this pin is a "no connect" and should be left disconnected.
VSS	Refer to Table 2-3 (Total of 71)	Refer to Table 2-5 (Total of 50)	GND	Ground Connection
VCC2	Refer to Table 2-3 (Total of 32)	Refer to Table 2-5 (Total of 32)	PWR	2.9V (nominal) Core Power Connection
VCC3	Refer to Table 2-3 (Total of 32)	Refer to Table 2-5 (Total of 18)	PWR	3.3V (nominal) I/O Power Connection
NC		Q5, X2,		No Connection
		Z2		A line designated as NC should be left disconnected.

### 2.2.6 Internal Test and Measurement Signals

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
FLT#	AC2	AJ3	1	Float
				Float Outputs force the GXm processor to float all outputs in the high-impedance state and to enter a power-down state.
RW_CLK	AE6	AL11	0	Raw Clock
				This output is the GXm processor clock. This debug signal can be used to verify clock operation.
TEST[3:0]	B22,	D28,	0	SDRAM Test Outputs
	A23, B21,	B32, D26.		These outputs are used for internal debug only.
	C21	A33		
TCLK	J2	P4 (PU)	I	Test Clock
	(PU)			JTAG test clock.
				This pin is internally connected to a 20-kohm pull-up resistor.
TDI	D2	F4	I	Test Data Input
(PU)	(PU)		JTAG serial test-data input.	
				This pin is internally connected to a 20-kohm pull-up resistor.
TDO	F1	J1	0	Test Data Output
				JTAG serial test-data output.


## 2.2.6 Internal Test and Measurement Signals

Signal Name	BGA Pin No.	SPGA Pin No.	Туре	Description
TMS	H1	N3	I	Test Mode Select
	(PU)	(PU)		JTAG test-mode select.
				This pin is internally connected to a 20-kohm pull-up resistor.
TEST	F3	J5	I	Test
	(PD)	(PD)		Test-mode input.
				This pin is internally connected to a 20-kohm pull-down resistor.
TDP	E24	F36	0	Thermal Diode Positive
				TDP is the positive terminal of the thermal diode on the die. The diode is used to do thermal characterization of the device in a system. This signal works in conjunction with TDN.
TDN	D26	E37	0	Thermal Diode Negative
				TDN is the negative terminal of the thermal diode on the die. The diode is used to do thermal characterization of the device in a system. This signal works in conjunction with TDP.

#### 2.3 SUBSYSTEM SIGNAL CONNECTIONS

As previously stated, the GXm Integrated Subsystem with MMX support consists of two chips: the GXm Processor and the CS5530 I/O companion. Figure 2-4 shows the

signal connections between the processor and the I/O companion chip.



Note: Refer to Figure 2-5 for interconnection of these lines.

Figure 2-4. Subsystem Signal Connections




Figure 2-5. PIXEL Signal Connections

#### 2.4 POWER PLANES

Figure 2-6 shows layout recommendations for splitting the power plane between VCC2 (core: 2.9V) and VCC3 (I/O: 3.3V) volts in the BGA package.

The illustration assumes there is one power plane, and no components on the back of the board

Figure 2-7 shows layout recommendations for splitting the power plane between VCC2 (core: 2.9V) and VCC3 (I/O: 3.3V) volts for the GXm in the SPGA package.




Figure 2-6. BGA Recommended Split Power Plane and Decoupling




Figure 2-7. SPGA Recommended Split Power Plane and Decoupling

## 3.0 Processor Programming

This section describes the internal operations of the Geode GXm processor from a programmer's point of view. It includes a description of the traditional "core" processing and FPU operations. The integrated function registers are described at the end of this chapter.

The primary register sets within the processor core include:

- Application Register Set
- System Register Set
- · Model Specific Register Set
- · Floating Point Unit Register Set.

The initialization of the major registers within in core are shown in Table 3-1.

The integrated function sets are located in main memory space and include:

- Internal Bus Interface Unit Register Set
- Graphics Pipeline Register Set
- · Display Controller Register Set
- · Memory Controller Register Set
- · Power Management Register Set

#### 3.1 CORE PROCESSOR INITIALIZATION

The GXm processor is initialized when the RESET signal is asserted. The processor is placed in real mode and the registers listed in Table 3-1 are set to their initialized values. RESET invalidates and disables the CPU cache, and turns off paging. When RESET is asserted, the CPU terminates all local bus activity and all internal execution. During the entire time that RESET is asserted, the internal pipeline is flushed and no instruction execution or bus activity occurs.

Approximately 150 to 250 external clock cycles after RESET is deasserted, the processor begins executing instructions at the top of physical memory (address location FFFFFF0h). The actual time depends on the clock scaling in use. Also, an additional 2<sup>20</sup> clock cycles are needed when self-test is requested.

Typically, an intersegment jump is placed at FFFFFF0h. This instruction will force the processor to begin execution in the lowest 1 MB of address space.

The following table, Table 3-1, lists the core registers and illustrates how they are initialized.

Table 3-1. Initialized Core Register Controls

Register	Register Name	Initialized Contents	Comments
EAX	Accumulator	xxxxxxxxh	0000000h indicates self-test passed.
EBX	Base	xxxxxxxxh	
ECX	Count	xxxxxxxxh	
EDX	Data	xxxx 04 [DIR0]h	DIR0 = Device ID
EBP	Base Pointer	xxxxxxxxh	
ESI	Source Index	xxxxxxxxh	
EDI	Destination Index	xxxxxxxxh	
ESP	Stack Pointer	xxxxxxxxh	
EFLAGS	Extended FLAGS	00000002h	See Table 3-4 on page 43 for bit definitions.
EIP	Instruction Pointer	0000FFF0h	
ES	Extra Segment	0000h	Base address set to 00000000h. Limit set to FFFFh.
CS	Code Segment	F000h	Base address set to FFFF0000h. Limit set to FFFFh.
SS	Stack Segment	0000h	Base address set to 00000000h. Limit set to FFFFh.
DS	Data Segment	0000h	Base address set to 00000000h. Limit set to FFFFh.
FS	Extra Segment	0000h	Base address set to 00000000h. Limit set to FFFFh.
GS	Extra Segment	0000h	Base address set to 00000000h. Limit set to FFFFh.
IDTR	Interrupt Descriptor Table Register	Base = 0, Limit = 3FFh	
GDTR	Global Descriptor Table Register	xxxx xxxxh	
LDTR	Local Descriptor Table Register	xxxxh	
TR	Task Register	xxxxh	
CR0	Machine Status Word	60000010h	See Table 3-7 on page 49 for bit definitions.
CR2	Control Register 2	xxxxxxxxh	See Table 3-7 on page 49 for bit definitions.
CR3	Control Register 3	xxxxxxxxh	See Table 3-7 on page 49 for bit definitions.
CR4	Control Register 4	00000000h	See Table 3-7 on page 49 for bit definitions.
CCR1	Configuration Control 1	00h	See Table 3-11 on page 49 for bit definitions.
CCR2	Configuration Control 2	00h	See Table 3-11 on page 49 for bit definitions.
CCR3	Configuration Control 3	00h	See Table 3-11 on page 49 for bit definitions.
CCR7	Configuration Control 7	00h	See Table 3-11 on page 50 for bit definitions.
SMAR0	SMM Address 0	00h	See Table 3-11 on page 51 for bit definitions.

Table 3-1. Initialized Core Register Controls (Continued)

Register	Register Name	Initialized Contents	Comments
SMAR1	SMM Address 1	00h	See Table 3-11 on page 50 for bit definitions.
SMAR2	SMM Address 2 / SMAR Size	00h	See Table 3-11 on page 50 for bit definitions.
DIR0	Device Identification 0	4xh	Device ID and reads back initial CPU clock-speed setting. See Table 3-11 on page 51 for bit definitions.
DIR1	Device Identification 1	xxh	Stepping and Revision ID (RO). See Table 3-11 on page 51 for bit definitions.
DR7	Debug Register 7	00000400h	See Table 3-13 on page 53 for bit definitions.

**Note:** x = Undefined value

#### 3.2 INSTRUCTION SET OVERVIEW

The GXm processor instruction set can be divided into nine types of operations:

- Arithmetic
- Bit Manipulation
- Shift/Rotate
- String Manipulation
- Control Transfer
- Data Transfer
- Floating Point
- High-Level Language Support
- · Operating System Support

GXm processor instructions operate on as few as zero operands and as many as three operands. An NOP instruction (no operation) is an example of a zero-operand instruction. Two-operand instructions allow the specification of an explicit source and destination pair as part of the instruction. These two-operand instructions can be divided into ten groups according to operand types:

- Register to Register
- · Register to Memory
- · Memory to Register
- Memory to Memory
- Register to I/O
- I/O to Register
- · Memory to I/O
- I/O to Memory
- · Immediate Data to Register
- · Immediate Data to Memory

An operand can be held in the instruction itself (as in the case of an immediate operand), in one of the processor's registers or I/O ports, or in memory. An immediate operand is fetched as part of the opcode for the instruction.

Operand lengths of 8, 16, 32 or 48 bits are supported as well as 64 or 80 bits associated with floating-point instructions. Operand lengths of 8 or 32 bits are generally used when executing code written for 386- or 486-class (32-bit code) processors. Operand lengths of 8 or 16 bits are generally used when executing existing 8086 or 80286 code (16-bit code). The default length of an operand can be overridden by placing one or more instruction prefixes in front of the opcode. For example, the use of prefixes allows a 32-bit operand to be used with 16-bit code or a 16-bit operand to be used with 32-bit code.

Section 9.1 "General Instruction Set Format" on page 202 contains the clock count table that lists each instruction in the CPU instruction set. Included in the table are the associated opcodes, execution clock counts, and effects on the EFLAGS register.

#### 3.2.1 Lock Prefix

The LOCK prefix may be placed before certain instructions that read, modify, then write back to memory. The PCI will not be granted access in the middle of locked instructions. The LOCK prefix can be used with the following instructions only when the result is a write operation to memory.

- Bit Test Instructions (BTS, BTR, BTC)
- Exchange Instructions (XADD, XCHG, CMPXCHG)
- One-Operand Arithmetic and Logical Instructions (DEC, INC, NEG, NOT)
- Two-Operand Arithmetic and Logical Instructions (ADC, ADD, AND, OR, SBB, SUB, XOR).

An invalid opcode exception is generated if the LOCK prefix is used with any other instruction or with one of the instructions above when no write operation to memory occurs (for example, when the destination is a register).

#### 3.3 REGISTER SETS

The accessible registers in the processor are grouped into three sets:

- The Application Register Set contains the registers frequently used by application programmers. Table 3-2 shows the general purpose, segment, the instruction pointer and the EFLAGS Registers.
- The System Register Set contains the registers typically reserved for operating-systems programmers: control, system address, debug, configuration, and test registers.
- 3) The Model Specific Register (MSR) Set is used to monitor the performance of the processor or a specific component within the processor. The model specific register set has one 64-bit register called the Time Stamp Counter.

Each of these register sets are discussed in detail in the subsections that follow. Additional registers to support integrated GXm processor subsystems are described in Section 4.1 "Integrated Functions Programming Interface" on page 92.

### 3.3.1 Application Register Set

The Application Register Set consists of the registers most often used by the applications programmer. These registers are generally accessible, although some bits in the EFLAGS register are protected.

The **General Purpose Register** contents are frequently modified by instructions and typically contain arithmetic and logical instruction operands.

In real mode, **Segment Registers** contain the base address for each segment. In protected mode, the segment registers contain segment selectors. The segment selectors provide indexing for tables (located in memory) that contain the base address for each segment, as well as other memory addressing information.

The **Instruction Pointer Register** points to the next instruction that the processor will execute. This register is automatically incremented by the processor as execution progresses.

The **EFLAGS Register** contains control bits used to reflect the status of previously executed instructions. This register also contains control bits that affect the operation of some instructions.

### 3.3.1.1 General Purpose Registers

The General Purpose Registers are divided into four data registers, two pointer registers, and two index registers as shown in Table 3-2.

The **Data Registers** are used by the applications programmer to manipulate data structures and to hold the results of logical and arithmetic operations. Different portions of general data registers can be addressed by using different names.

An "E" prefix identifies the complete 32-bit register. An "X" suffix without the "E" prefix identifies the lower 16 bits of the register.

The lower two bytes of a data register are addressed with an "H" suffix (identifies the upper byte) or an "L" suffix (identifies the lower byte). These \_L and \_H portions of the data registers act as independent registers. For example, if the AH register is written to by an instruction, the AL register bits remain unchanged.

The **Pointer and Index Registers** are listed below.

SI or ESI Source Index
DI or EDI Destination Index
SP or ESP Stack Pointer
BP or EBP Base Pointer

These registers can be addressed as 16- or 32-bit registers, with the "E" prefix indicating 32 bits. The pointer and index registers can be used as general purpose registers; however, some instructions use a fixed assignment of these registers. For example, repeated string operations always use ESI as the source pointer, EDI as the destination pointer, and ECX as a counter. The instructions that use fixed registers include multiply and divide, I/O access, string operations, stack operations, loop, variable shift and rotate, and translate instructions.

The GXm processor implements a stack using the ESP register. This stack is accessed during the PUSH and POP instructions, procedure calls, procedure returns, interrupts, exceptions, and interrupt/exception returns. The GXm processor automatically adjusts the value of the ESP during operations that result from these instructions.

The EBP register may be used to refer to data passed on the stack during procedure calls. Local data may also be placed on the stack and accessed with BP. This register provides a mechanism to access tack data in high-level languages.

## **Table 3-2. Application Register Set**

1   30   29   28   27   26   25   24   23   22   21   20   19   18   17   16   15   14   13   12   11   10   9   8   7   6   5   4   3   2   1   0   0   0   0   0   0   0   0   0									abi	<del>-</del> 3	-2. /	746	,,,,,	ition r	veg	ister .	Jei										
AX	31 30	29	28	27 2	6 25	24	23 2	2 21	20	19	18	17	16	15 14	13	12 11	10	9	8	7	6	5	4	3	2	1	0
AH	Gener	ral Pui	rpos	e Reg	gisters	s																					
EAX (Extended A Register)  BX BH BH BL  EBX (Extended B Register)  CX CH CH CL  ECX (Extended C Register)  DX DH DL  EDX (Extended D Register)  SI (Source Index)  ESI (Extended Source Index)  ESI (Extended Destination Index)  EDI (Extended Destination Index)  EDI (Extended Base Pointer)  EBP (Extended Base Pointer)  ESP (Extended Stack Pointer)																			A.	Χ							
BX   BL																AH							Α	L_			
BH   BL     EBX (Extended B Register)   CX   CH   CL   CH   CL   CH   CL   CH   CD   CD   CH   CD   CD   CD   CD		EAX (Ext											ende	d A Re	giste	r)											
EBX (Extended B Register)  CX CH CL  ECX (Extended C Register)  DX DH DL  EDX (Extended D Register)  SI (Source Index)  ESI (Extended Source Index)  DI (Destination Index)  EDI (Extended Destination Index)  EDI (Extended Base Pointer)  EBP (Extended Base Pointer)  ESP (Extended Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  ES (E Data Segment)  FS (F Data Segment)  SETUCTION Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)																			B	X							
CX												<i>-</i>	!										В	<u>L</u>			
CH											EBX	(Ext	ende	d B Re	giste	r)				· · ·							
ECX (Extended C Register)													•			CH			C.	X							
DX   DH											FCX	(Fyt	ende	d C Re	niste												
DH   DL											LOX	(LX	Criac	u o rec	gioto	,ı,			D	X							
SI (Source Index)   ESI (Extended Source Index)   DI (Destination Index)   EDI (Extended Destination Index)   BP (Base Pointer)   EBP (Extended Base Pointer)   SP (Stack Pointer)   ESP (Extended Stack Pointer)													•			DH							D	L			
ESI (Extended Source Index)  DI (Destination Index)  EDI (Extended Destination Index)  BP (Base Pointer)  EBP (Extended Base Pointer)  SP (Stack Pointer)  ESP (Extended Stack Pointer)  ESP (Extended Stack Pointer)  CS (Code Segment)  SS (Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  ES (E Data Segment)  FS (F Data Segment)  astruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)											EDX	(Ext	ende	d D Re	giste	er)											
EDI (Extended Destination Index)  EDI (Extended Destination Index)  BP (Base Pointer)  EBP (Extended Base Pointer)  SP (Stack Pointer)  ESP (Extended Stack Pointer)  egment (Selector) Registers  CS (Code Segment)  SS (Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  FS (F Data Segment)  GS (G Data Segment)  astruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)																		SI (S	Sourc	ce In	ndex)	)					
EDI (Extended Destination Index)  BP (Base Pointer)  EBP (Extended Base Pointer)  SP (Stack Pointer)  ESP (Extended Stack Pointer)  egment (Selector) Registers  CS (Code Segment)  SS (Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  FS (F Data Segment)  GS (G Data Segment)  astruction Pointer and EFLAGS Registers										E	SI (E	xter	nded	Source	Inde	ex)											
BP (Base Pointer)  EBP (Extended Base Pointer)  SP (Stack Pointer)  ESP (Extended Stack Pointer)  egment (Selector) Registers  CS (Code Segment)  SS (Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  FS (F Data Segment)  GS (G Data Segment)  astruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)																	DI	(De	stina	tion	Inde	ex)					
EBP (Extended Base Pointer)  SP (Stack Pointer)  ESP (Extended Stack Pointer)  egment (Selector) Registers  CS (Code Segment)  SS (Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  FS (F Data Segment)  GS (G Data Segment)  struction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)										ED	I (Ext	tend	ed D	estinatio	on In	idex)											
SP (Stack Pointer)  ESP (Extended Stack Pointer)  egment (Selector) Registers  CS (Code Segment) SS (Stack Segment) DS (D Data Segment) ES (E Data Segment) FS (F Data Segment) GS (G Data Segment)  estruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)										_	.DD //																
ESP (Extended Stack Pointer)  egment (Selector) Registers  CS (Code Segment) SS (Stack Segment) DS (D Data Segment) ES (E Data Segment) FS (F Data Segment) GS (G Data Segment) Struction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)											:BP (I	Exte	naec	Base F	oint	er)		2D /	Stack	, Do	intor	٠١					
CS (Code Segment) SS (Stack Segment) DS (D Data Segment) ES (E Data Segment) FS (F Data Segment) GS (G Data Segment) Struction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)										F	SP (I	Exte	nded	Stack F	Point	ter)		эг (·	State	\ FU	iiiiei	)					
CS (Code Segment) SS (Stack Segment) DS (D Data Segment) ES (E Data Segment) FS (F Data Segment) GS (G Data Segment)  astruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)	Seam	ent (S	elec	tor) R	Regist	ers					(-			- Ctabit i	-	,											
SS (Stack Segment)  DS (D Data Segment)  ES (E Data Segment)  FS (F Data Segment)  GS (G Data Segment)  astruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)	- Cog	o (o	0.00	,	.09.01												C	s (C	ode:	Sen	ımer	nt)					
DS (D Data Segment) ES (E Data Segment) FS (F Data Segment) GS (G Data Segment)  Instruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)													-									-					
ES (E Data Segment) FS (F Data Segment) GS (G Data Segment)  Instruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)																											
FS (F Data Segment) GS (G Data Segment)  astruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)													ŀ														
estruction Pointer and EFLAGS Registers  EIP (Extended Instruction Pointer)											İ																
EIP (Extended Instruction Pointer)													•				GS	S (G	Data	Se	gme	nt)					
	Instru	ction	Poir	nter a	nd EF	LAG	S Reg	isters	3		_										_	_			_		
ESP (Extended FLAGS Register)										EIP	(Ext	ende	d In	struction	n Poi	inter)											
										ES	P (Ex	ktend	ded F	LAGS	Regi	ster)											

#### 3.3.1.2 **Segment Registers**

The 16-bit segment registers, part of the main memory addressing mechanism, are described in Section 3.5 "Offset, Segment, and Paging Mechanisms" on page 61. The six segment registers are:

CS Code Segment

DS Data Segment SS

Stack Segment

ES Extra Segment

FS Additional Data Segment

Additional Data Segment GS

The segment registers are used to select segments in main memory. A segment acts as private memory for different elements of a program such as code space, data space, and stack space.

There are two segment mechanisms, one for real and virtual 8086 operating modes and one for protective mode. Initialization and transition to protective mode is described in Section 3.13.4 "Initialization and Transition to Protected Mode" on page 87. The segment mechanisms are described in Section 3.7 "Descriptors and Segment Mechanisms" on page 62.

The active segment register is selected according to the rules listed in Table 3-3 and the type of instruction being currently processed. In general, the DS register selector is used for data references. Stack references use the SS register, and instruction fetches use the CS register. While some of these selections may be overridden, instruction fetches, stack operations, and the destination write operation of string operations cannot be overridden. Special segment-override instruction prefixes allow the use of alternate segment registers. These segment registers include the ES, FS, and GS registers.

## 3.3.1.3 Instruction Pointer Register

The Instruction Pointer (EIP) Register contains the offset into the current code segment of the next instruction to be executed. The register is normally incremented by the length of the current instruction with each instruction execution unless it is implicitly modified through an interrupt, exception, or an instruction that changes the sequential execution flow (for example JMP and CALL).

Table 3-3 illustrates the code segment selection rules.

Table 3-3. Segment Register Selection Rules

Type of Memory Reference	Implied (Default) Segment	Segment-Override Prefix
Code Fetch	CS	None
Destination of PUSH, PUSHF, INT, CALL, PUSHA instructions	SS	None
Source of POP, POPA, POPF, IRET, RET instructions	SS	None
Destination of STOS, MOVS, REP STOS, REP MOVS instructions	ES	None
Other data references with effective address using base registers of: EAX, EBX, ECX, EDX, ESI, EDI, EBP, ESP	DS	CS, ES, FS, GS, SS
	SS	CS, DS, ES, FS, GS

## 3.3.1.4 EFLAGS Register

The EFLAGS Register contains status information and controls certain operations on the GXm processor. The lower 16 bits of this register are referred to as the

EFLAGS register that is used when executing 8086 or 80286 code. Table 3-4 gives the bit formats for the EFLAGS Register

Table 3-4. EFLAGS Register

Bit	Name	Flag Type	Description
31:22	RSVD		Reserved: Set to 0.
21	ID	System	<b>Identification Bit</b> : The ability to set and clear this bit indicates that the CPUID instruction is supported. The ID can be modified only if the CPUID bit in CCR4 (Index E8h[7]) is set.
20:19	RSVD		Reserved: Set to 0.
18	AC	System	Alignment Check Enable: In conjunction with the AM flag (bit 18) in CR0, the AC flag determines whether or not misaligned accesses to memory cause a fault. If AC is set, alignment faults are enabled.
17	VM	System	Virtual 8086 Mode: If set while in protected mode, the processor switches to virtual 8086 operation handling segment loads as the 8086 does, but generating exception 13 faults on privileged opcodes. The VM bit can be set by the IRET instruction (if current privilege level is 0) or by task switches at any privilege level.
16	RF	Debug	<b>Resume Flag</b> : Used in conjunction with debug register breakpoints. RF is checked at instruction boundaries before breakpoint exception processing. If set, any debug fault is ignored on the next instruction.
15	RSVD		Reserved: Set to 0.
14	NT	System	<b>Nested Task</b> : While executing in protected mode, NT indicates that the execution of the current task is nested within another task.
13:12	IOPL	System	I/O Privilege Level: While executing in protected mode, IOPL indicates the maximum current privilege level (CPL) permitted to execute I/O instructions without generating an exception 13 fault or consulting the I/O permission bit map. IOPL also indicates the maximum CPL allowing alteration of the IF bit when new values are popped into the EFLAGS register.
11	OF	Arithmetic	<b>Overflow Flag</b> : Set if the operation resulted in a carry or borrow into the sign bit of the result but did not result in a carry or borrow out of the high-order bit. Also set if the operation resulted in a carry or borrow out of the high-order bit but did not result in a carry or borrow into the sign bit of the result.
10	DF	Control	<b>Direction Flag</b> : When cleared, DF causes string instructions to auto-increment (default) the appropriate index registers (ESI and/or EDI). Setting DF causes auto-decrement of the index registers to occur.
9	IF	System	Interrupt Enable Flag: When set, maskable interrupts (INTR input pin) are acknowledged and serviced by the CPU.
8	TF	Debug	<b>Trap Enable Flag</b> : Once set, a single-step interrupt occurs after the next instruction completes execution. TF is cleared by the single-step interrupt.
7	SF	Arithmetic	Sign Flag: Set equal to high-order bit of result (0 indicates positive, 1 indicates negative).
6	ZF	Arithmetic	Zero Flag: Set if result is zero; cleared otherwise.
5	RSVD		Reserved: Set to 0.
4	AF	Arithmetic	<b>Auxiliary Carry Flag</b> : Set when a carry out of (addition) or borrow into (subtraction) bit position 3 of the result occurs; cleared otherwise.
3	RSVD		Reserved: Set to 0.
2	PF	Arithmetic	<b>Parity Flag</b> : Set when the low-order 8 bits of the result contain an even number of ones; otherwise PF is cleared.
1	RSVD		Reserved: Set to 1.
0	CF	Arithmetic	<b>Carry Flag</b> : Set when a carry out of (addition) or borrow into (subtraction) the most significant bit of the result occurs; cleared otherwise.

### 3.3.2 System Register Set

The system register set, shown in Table 3-5, consists of registers not generally used by application programmers. These registers are typically employed by system level programmers who generate operating systems and memory management programs. Associated with the system register set are certain tables and segments which are listed in Table 3-5.

The **Control Registers** control certain aspects of the GXm processor such as paging, coprocessor functions, and segment protection.

The **Descriptor Tables** hold descriptors that manage memory segments and tables, interrupts and task switching. The tables are defined by corresponding registers.

The two Task State Segments Tables defined by TSS register are used to save and load the computer state when switching tasks.

The **Configuration Registers** are used to define the GXm CPU setup including cache management.

The ID registers allow BIOS and other software to identify the specific CPU and stepping. System Management Mode (SMM) control information is stored in the SMM registers.

The **Debug Registers** provide debugging facilities for the GXm processor and enable the use of data access breakpoints and code execution breakpoints.

The **Test Registers** provide a mechanism to test the contents of both the on-chip 16 KB cache and the Translation Lookaside Buffer (TLB). The TLB is used as a cache for the tables that are used in to translate linear addresses to physical addresses while paging is enabled.

Table 3-5 lists the system register sets along with their size and function.

Table 3-5. System Register Set

Group	Name	Function	Width (Bits)
Control Registers	CR0	System Control Register	32
	CR2	Page Fault Linear Address Register	32
	CR3	Page Directory Base Register	32
	CR4	Time Stamp Counter	32
Descriptor	GDT	General Descriptor Table	32
Tables	IDT	Interrupt Descriptor Table	32
	LDT	Local Descriptor Table	16
Descriptor	GDTR	GDT Register	32
Table	IDTR	IDT Register	32
Registers	LDTR	LDT Register	16
Task State Segment and	TSS	Task State Segment Tables	16
Registers	TR	TSS Register Setup	16
Configuration Registers	CCRn	Configuration Control Registers	8
ID Registers	DIRn	Device Identification Registers	8
SMM Registers	SMARn	SMM Address Region Registers	8
	SMHRn	SMM Header Addresses	8
Performance Registers	PCR0	Performance Control Register	8
Debug Registers	DR0	Linear Breakpoint Address 0	32
	DR1	Linear Breakpoint Address 1	32
	DR2	Linear Breakpoint Address 2	32
	DR3	Linear Breakpoint Address 3	32
	DR6	Breakpoint Status	32
	DR7	Breakpoint Control	32
Test	TR3	Cache Test	32
Registers	TR4	Cache Test	32
	TR5	Cache Test	32
	TR6	TLB Test Control	32
	TR7	TLB Test Status	32

### 3.3.2.1 Control Registers

A map of the Control Registers (CR0, CR2, CR3, and CR4) is shown in Table 3-6 and the bit definitions are given in Table 3-7. (These registers should not be confused with the CRRn registers.) The CR0 register contains system control bits which configure operating modes and indicate

the general state of the CPU. The lower 16 bits of CR0 are referred to as the Machine Status Word (MSW).

When operating in real mode, any program can read and write the control registers. In protected mode, however, only privilege level 0 (most-privileged) programs can read and write these registers.

## Table 3-6. Control Registers Map

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
CR	4 Re	egis	ter									(	Cont	trol	Reç	gister	4 (F	R/W)													
				RSVD																T S C	RS	VD									
CR	CR3 Register Control Register 3 (R/W)																														
					PDBR (Page Directory Base Register)  RSVD  0 0 RSVD																										
CR	2 R	egis	ter	Control Register 2 (R/W)																											
												PFL	A (P	age	Fau	ult Lin	ear	Addı	ress	5)											
CR	1 Re	egis	ter									(	Cont	trol	Reç	gister	1 (F	R/W)													
															R	SVD															
CR	0 Re	egis	ter									(	Cont	trol	Reç	gister	0 (F	R/W)													
P G	C D	N W					RS	SVD					A M	R S V D	W P					RS	SVD					N E	R S V D	T S	E M	M P	P E
													Ma	achi	ne S	tatu	ıs W	ord	(MS	W)											

### Table 3-7. CR4-CR0 Bit Definitions

Bit	Name	Description						
CR4 Re	gister	Control Register 4 (R/W)						
31:3	RSVD	Reserved: Set to 0 (always returns 0 when read).						
2	TSC	Fime Stamp Counter Instruction:  f = 1 RDTSC instruction enabled for CPL = 0 only; reset state.  f = 0 RDTSC instruction enabled for all CPL states.						
1:0	RSVD	Reserved: Set to 0 (always returns 0 when read).						
CR3 Re	gister	Control Register 3 (R/W)						
31:12	PDBR	Page Directory Base Register: Identifies page directory base address on a 4 KB page boundary.						
11:0	RSVD	Reserved: Set to 0.						
CR2 Re	gister	Control Register 2 (R/W)						
31:0	PFLA	Page Fault Linear Address: With paging enabled and after a page fault, PFLA contains the linear address of the address that caused the page fault.						
CR1 Re	gister	Control Register 1 (R/W)						
31:0	RSVD	Reserved						
CR0 Reg	gister	Control Register 0 (R/W)						
31 PG		<b>Paging Enable Bit</b> : If PG = 1 and protected mode is enabled (PE = 1), paging is enabled. After changing the state of PG, software must execute an unconditional branch instruction (e.g., JMP, CALL) to have the change take effect.						

Table 3-7. CR4-CR0 Bit Definitions (Continued)

Bit	Name	Description
30	CD	<b>Cache Disable</b> : If CD = 1, no further cache line fills occur. However, data already present in the cache continues to be used if the requested address hits in the cache. Writes continue to update the cache and cache invalidations due to inquiry cycles occur normally. The cache must also be invalidated with a WBINVD instruction to completely disable any cache activity.
29	NW	Not Write-Through: If NW = 1, the on-chip cache operates in write-back mode. In write-back mode, writes are issued to the external bus only for a cache miss, a line replacement of a modified line, execution of a locked instruction, or a line eviction as the result of a flush cycle. If NW = 0, the on-chip cache operates in write-through mode. In write-through mode, all writes (including cache hits) are issued to the external bus. This bit cannot be changed if LOCK_NW = 1 in CCR2.
18	AM	Alignment Check Mask: If AM = 1, the AC bit in the EFLAGS register is unmasked and allowed to enable alignment check faults. Setting AM = 0 prevents AC faults from occurring.
16	WP	Write Protect: Protects read-only pages from supervisor write access. WP = 0 allows a read-only page to be written from privilege level 0-2. WP = 1 forces a fault on a write to a read-only page from any privilege level.
5	NE	<b>Numerics Exception</b> : NE = 1 to allow FPU exceptions to be handled by interrupt 16. NE = 0 if FPU exceptions are to be handled by external interrupts.
4	RSVD	Reserved: Do not attempt to modify, always 1.
3	TS	<b>Task Switched</b> : Set whenever a task switch operation is performed. Execution of a floating point instruction with TS = 1 causes a DNA fault. If MP = 1 and TS = 1, a WAIT instruction also causes a DNA fault.
2	EM	Emulate Processor Extension: If EM = 1, all floating point instructions cause a DNA fault 7.
1	MP	<b>Monitor Processor Extension</b> : If MP = 1 and TS = 1, a WAIT instruction causes Device Not Available (DNA) fault 7. The TS bit is set to 1 on task switches by the CPU. Floating point instructions are not affected by the state of the MP bit. The MP bit should be set to one during normal operations.
0	PE	<b>Protected Mode Enable</b> : Enables the segment based protection mechanism. If PE = 1, protected mode is enabled. If PE = 0, the CPU operates in real mode and addresses are formed as in an 8086-style CPU. Refer to Section 3.13 "Protection" on page 86.

Table 3-8. Effects of Various Combinations of EM, TS, and MP Bits

	CR0[3:1]		Instruction Type					
TS	EM	MP	WAIT	ESC				
0	0	0	Execute	Execute				
0	0	1	Execute	Execute				
1	0	0	Execute	Fault 7				
1	0	1	Fault 7	Fault 7				
0	1	0	Execute	Fault 7				
0	1	1	Execute	Fault 7				
1	1	0	Execute	Fault 7				
1	1	1	Fault 7	Fault 7				

### 3.3.2.2 Configuration Registers

The configuration registers listed in Table 3-9 are CPU registers and are selected by register index numbers. The registers are accessed through I/O memory locations 22h and 23h. Registers are selected for access by writing an index number to I/O Port 22h using an OUT instruction prior to transferring data through I/O Port 23h.

Each data transfer through I/O Port 23h must be preceded by a register index selection through I/O Port 22h; otherwise, subsequent I/O Port 23h operations are directed offchip and produce external I/O cycles.

If MAPEN, bit 4 of CCR3 (Index C3h[4]) = 0, external I/O cycles occur if the register index number is outside the range C0h-CFh, FEh, and FFh. The MAPEN bit should remain 0 during normal operation to allow system registers located at I/O Port 22h to be accessed.

**Table 3-9. Configuration Register Summary** 

Index	Туре	Name	Access Controlled By*	Default Value	Reference (Bit Formats)
C1h	R/W	CCR1 — Configuration Control 1	SMI_LOCK	00h	Table 3-11 on page 49
C2h	R/W	CCR2 — Configuration Control 2		00h	Table 3-11 on page 49
C3h	R/W	CCR3 — Configuration Control 3	SMI_LOCK	00h	Table 3-11 on page 49
E8h	R/W	CCR4 — Configuration Control 4	MAPEN	85h	Table 3-11 on page 50
EBh	R/W	CCR7 — Configuration Control 7		00h	Table 3-11 on page 50
20h	R/W	PCR — Performance Control	MAPEN	07h	Table 3-11 on page 50
B0h	R/W	SMHR0 — SMM Header Address 0	MAPEN	xxh	Table 3-11 on page 50
B1h	R/W	SMHR1 — SMM Header Address 1	MAPEN	xxh	Table 3-11 on page 50
B2h	R/W	SMHR2 — SMM Header Address 2	MAPEN	xxh	Table 3-11 on page 50
B3h	R/W	SMHR3 — SMM Header Address 3	MAPEN	xxh	Table 3-11 on page 50
B8h	R/W	GCR — Graphics Control Register	MAPEN	00h	Table 4-1 on page 92
B9h		VGACTL — VGA Control Register		00h	Table 5-5 on page 173
BAh- BDh		VGAM0 — VGA Mask Register		00h	Table 5-5 on page 173
CDh	R/W	SMAR0 — SMM Address 0	SMI_LOCK	00h	Table 3-11 on page 51
CEh	R/W	SMAR1 — SMM Address 1	SMI_LOCK	00h	Table 3-11 on page 51
CFh	R/W	SMAR2 — SMM Address 2	SMI_LOCK	00h	Table 3-11 on page 51
FEh	RO	DIR0 — Device ID 0		4xh	Table 3-11 on page 51
FFh	RO	DIR1 — Device ID 1		xxh	Table 3-11 on page 51

Note: \*MAPEN = Index C3h[4] (CCR3) and SMI\_LOCK = Index C3h[0] (CCR3).

## Table 3-10. Configuration Register Map

Table 5-16. Comiguration Register map													
Register (Index)	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0					
Control Registe	ers												
CCR1 (C1h)			RSVD			SMAC	USE_SMI	RSVD					
CCR2 (C2h)	USE_SUSP	RS	VD	WT1	SUSP_HLT	LOCK_NW	VD						
CCR3 (C3h)	LSS_34	LSS_23	LSS_12	MAPEN	RS	VD	NMI_EN	SMI_LOCK					
CCR4 (E8h)	CPUID	SMI_NEST	RSVD	DTE_EN	MEM_BYP	IORT2	IORT1	IORT0					
CCR7 (EBh)			RSVD			NMI	RSVD	EMMX					
PCR (20h)	LSSER				RSVD								
Device ID Registers													
DIR0 (FEh)	DID3	DID2	DID1	DID0	RSVD	CLKMODE1	RSVD	CLMODE0					
DIR1 (FFh)	SID3	SID2	SID1	SID0	RID3	RID2	RID1	RID0					
SMM Base Hea	SMM Base Header Address Registers												
SMAR0 (CDh)	A31	A30	A29	A28	A27	A26	A25	A24					
SMAR1 (CEh)	A23	A22	A21	A20	A19	A18	A17	A16					
SMAR2 (CFh)	A15	A14	A13	A12	SIZE3	SIZE2	SIZE1	SIZE0					
SMHR0 (B0h)	A7	A6	A5	A4	А3	A2	A1	A0					
SMHR1 (B1h)	A15	A14	A13	A12	A11	A10	A9	A8					
SMHR2 (B2h)	A23	A22	A21	A20	A19	A18	A17	A16					
SMHR3 (B3h)	A31	A30	A29	A28	A27	A26	A26	A24					
Graphics/VGA	Related Regis	sters											
GCR (B8h)		RS	VD		Scratch	oad Size	Base Add	ress Code					
VGACTL (B9h)	RSVD  Enable SMI for VGA memory B8000h to BFFFFh B7FFFh AFFFFh												
VGAM0 (BAh)	VGA Mask Register Bits [7:0]												
VGAM1 (BBh)			,	VGA Mask Reg	gister Bits [15:8	]							
VGAM2 (BCh)			\	/GA Mask Reg	ister Bits [23:16	6]							
VGAM3 (BDh)	VGA Mask Register Bits [31:24]												

**Table 3-11. Configuration Registers** 

Bit	Name	Description
Index C1h		CCR1 — Configuration Control Register 1 (R/W) Default Value = 00
7:3	RSVD	Reserved: Set to 0.
2:1	SMAC	System Management Memory Access:
		If = 00: SMM is disabled.
		If = 01: SMI# pin is active to enter SMM. SMINT instruction is inactive.
		If = 10: SMM is disabled. If = 11: SMINT instruction is active to enter SMM. SMI# pin is inactive.
		<b>Note:</b> SMI_LOCK (CCR3[0]) must = 0, or the CPU must be in SMI mode, to write this bit.
0	RSVD	Reserved: Set to 0.
Note: Bits	1 and 2 are cleared	to zero at reset.
Index C2h		CCR2 — Configuration Control Register 2 (R/W) Default Value = 00
7	USE_SUSP	Enable Suspend Pins:
,	002_0001	If = 1: SUSP# input and SUSPA# output are enabled.
		If = 0: SUSP# input is ignored.
6	RSVD	Reserved: This is a test bit that must be set to 0.
5	RSVD	Reserved: Set to 0.
4	WT1	Write-Through Region 1:
		If = 1: Forces all writes to the address region between 640 KB to 1 MB that hit in the on-chip cache
		to be issued on the external bus.
3	SUSP_HLT	Suspend on HALT:
		If = 1: CPU enters suspend mode following execution of a HALT instruction.
2	LOCK_NW	Lock NW Bit:
		If = 1: Prohibits changing the state of the NW bit (CR0[29]) (refer to Table 3-7 on page 45). Set to 1 after setting NW.
1:0	RSVD	Reserved: Set to 0.
Note: All b	oits are cleared to zer	ro at reset.
Index C3h		CCR3 — Configuration Control Register 3 (R/W) Default Value = 00
7	LSS_34	Load/Store Serialize 3 GB to 4 GB:
		If = 1: Strong R/W ordering imposed in address range C0000000h to FFFFFFFh:
6	LSS_23	Load/Store Serialize 2 GB to 3 GB:
U	L00_20	
	L30_23	If = 1: Strong R/W ordering imposed in address range 80000000h to BFFFFFFh:
5	LSS_12	Load/Store Serialize 1 GB to 2 GB:
5	LSS_12	
	_	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:
5	LSS_12	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.
5	LSS_12	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are
5	LSS_12	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.
5	LSS_12	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are not configuration.
5	LSS_12 MAPEN	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are no accessible.
5	LSS_12 MAPEN	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are no accessible.  Enable Suspend in SMM Mode:
5	LSS_12 MAPEN	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are not accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.
5 4	LSS_12  MAPEN  SUSP_SMM_EN	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are no accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.  1 = SUSP# recognized in SMM mode.
5 4 3	LSS_12  MAPEN  SUSP_SMM_EN  RSVD	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are no accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.  1 = SUSP# recognized in SMM mode.  Reserved: Set to 0.  NMI Enable:  If = 1: NMI is enabled during SMM.
5 4 3	LSS_12  MAPEN  SUSP_SMM_EN  RSVD	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are not accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.  1 = SUSP# recognized in SMM mode.  Reserved: Set to 0.  NMI Enable:  If = 1: NMI is enabled during SMM.  If = 0: NMI is not recognized during SMM.
5 4 3 2 1	LSS_12  MAPEN  SUSP_SMM_EN  RSVD  NMI_EN	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are not accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.  1 = SUSP# recognized in SMM mode.  Reserved: Set to 0.  NMI Enable:  If = 1: NMI is enabled during SMM.  If = 0: NMI is not recognized during SMM.  Note: SMI_LOCK (CCR3[0]) must = 0 or the CPU must be in SMI mode to write to this bit.
5 4 3	LSS_12  MAPEN  SUSP_SMM_EN  RSVD	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are not accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.  1 = SUSP# recognized in SMM mode.  Reserved: Set to 0.  NMI Enable:  If = 1: NMI is enabled during SMM.  If = 0: NMI is not recognized during SMM.  Note: SMI_LOCK (CCR3[0]) must = 0 or the CPU must be in SMI mode to write to this bit.  SMM Register Lock:
5 4 3 2 1	LSS_12  MAPEN  SUSP_SMM_EN  RSVD  NMI_EN	Load/Store Serialize 1 GB to 2 GB:  If = 1: Strong R/W ordering imposed in address range 40000000h to 7FFFFFFh  Map Enable:  If = 1: All configuration registers are accessible. All accesses to Port 22h are trapped.  If = 0: Only configuration registers Index C1h through CFh, FEh, FFh (CCRn, SMAR, DIRn) are accessible. Other configuration registers (including PCR, SMHRn, GCR, VGACTL, VGAM0) are not accessible.  Enable Suspend in SMM Mode:  0 = SUSP# ignored in SMM mode.  1 = SUSP# recognized in SMM mode.  Reserved: Set to 0.  NMI Enable:  If = 1: NMI is enabled during SMM.  If = 0: NMI is not recognized during SMM.  Note: SMI_LOCK (CCR3[0]) must = 0 or the CPU must be in SMI mode to write to this bit.

**Table 3-11. Configuration Registers (Continued)** 

Bit	Name	Description	
Index E8h		CCR4 — Configuration Control Register 4 (R/W)	Default Value = 85h
7	CPUID	Enable CPUID Instruction:	
		If = 1: The ID bit in the EFLAGS register to be modified and execution occurs as documented in Table 9-2 on page 202.	of the CPUID instruction
		If = 0: The ID bit can not be modified and execution of the CPUID instruopcode exception.	uction causes an invalid
6	SMI NEST	SMI Nest:	
Ü	<u>.</u> <u>.</u>	If = 1: SMI interrupts can occur during SMM mode. SMI handlers can op to allow higher-priority SMI interrupts while handling the current event	otionally set SMI_NEST high
5	FPU_FAST_EN	FPU Fast Mode Enable:	
		If = 0: Disable FPU Fast Mode	
		If = 1: Enable FPU Fast Mode.	
4	DTE_EN	Directory Table Entry Cache:	
	_	If = 1: Enables directory table entry to be cached.	
		Cleared to 0 at reset.	
3	MEM_BYP	Memory Read Bypassing:	
	_	If = 1: Enables memory read bypassing.	
		Cleared to 0 at reset.	
2:0	IORT(2:0)	I/O Recovery Time: Specifies the minimum number of bus clocks betw	reen I/O accesses:
	(=)	000 = No clock delay 100 = 16-clock delay	
		,	y (default value after reset)
		010 = 4-clock delay 110 = 64-clock delay	
		011 = 8-clock delay 111 = 128-clock delay	ay
		Cleared to 0 at reset.	
Note: MAF	PEN (CCR3[4]) must	= 1 to read or write to this register.	
Index EBh		CCR7 — Configuration Control Register 7 (R/W)	Default Value = 00h
7:3	RSVD	Reserved: Set to 0.	
2	NMI	Generate NMI:	
		0 = Do nothing	
		1 = Generate NMI	
		In order to generate multiple NMIs, this bit must be set to zero between	each setting of 1.
1	RSVD	Reserved: Set to 0.	
0	EMMX	Extended MMX Instructions Enable:	
		If = 1: extended MMX instructions are enabled	
Index 20h		PCR — Performance Control Register (R/W)	Default Value = 07h
7	LSSER	Load/Store Serialize Enable (Reorder Disable): LSSER should be seemapped I/O devices operating outside of the address range 640K to 1M memory accesses above 1 GB, refer to CCR3[7:5] (LSS_34, LSS_23,	I will operate correctly. For
		If = 1: All memory read and write operations will occur in execution ordernabled, reordering disabled).	er (load/store serializing
		If = 0: Memory reads and write can be reordered for optimum performa disabled, reordering enabled).	nce (load/store serializing
		Memory accesses in the address range 640K to 1M will always be issued	ed in execution order.
6	RSVD	Reserved: Set to 0.	
5	RSVD	Reserved: This is a test bit that must be set to 0.	
4:0	RSVD	Reserved: Set to 0.	
Note: MAI	PEN (CCR3[4]) must	= 1 to read or write to this register.	

Table 3-11. Configuration Registers (Continued)

Bit	Name	Description			
Index	SMHR Bits	SMM Header Address B	its [A31:0]: SMHR add	lress bits [31:0] cont	tain the physical base addres
B3h	A[31:24]	for the SMM header space			
B2h	A[23:16]	Refer to Section 3.11.4 "S	SMM Configuration Reg	isters" on page 80 f	or more information.
B1h	A[15:12]				
B0h	A[7:0]				
		st = 1 to read or write to this	<u> </u>		
Index CDh	, CEh, CFh		dress Region/Size Reg		Default Value = 0
Index	SMAR Bits	SMM Address Region B the SMM region.	its [A31:A12]: SMAR a	address bits [31:12]	contain the base address for
CDh	A[31:24]	Bits [31:24] correspond w	ith Index CDh		
CEh	A[23:16]	Bits [23:16] correspond w			
CFh[7:4]	A[15:12]	Bits [15:12] correspond w			
				•	s SMAR[15:12] and size cod
		bits SIZE[3:0]. During acc			
		Refer to Section 3.11.4 "S	MM Configuration Reg	isters" on page 80 fo	or more information.
CFh[3:0]	SIZE[3:0]		hold SIZE[3:0]. Index (	CFh allows simultane	e SMM region. During acces eous access to SMAR addre
		0000 = SMM Disabled	0100 = 32 KB	1000 = 512 KB	1100 = 8 MB
		0001 = 4 KB	0101 = 64 KB	1001 = 1 MB	1101 = 16 MB
		0010 = 8 KB	0110 = 128 KB	1010 = 2 MB	1110 = 32 MB
		0011 = 16 KB	0111 = 256 KB	1011 = 4 MB	1111 = 4 KB (same as
		0001)			
Note: SMI	_LOCK (CCR3[0])	must = 0, or the CPU must b	e in SMI mode, to write	these registers/bits	
			·		
Index FEh		DIR0 — Device	Identification Registe	r 0 (RO)	Default Value = 4
Index FEh 7:4	DID[3:0]	DIR0 — Device  Device ID (Read Only):	Identification Registe		Default Value = 4
		Device ID (Read Only): I	Identification Registe dentifies device as GXr nly) — Identifies the co	n processor.	Default Value = 4 he CLKMODE[2:0] pins (see
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0]	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only)	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only)	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0101 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0010 = SYSCLK multiplie  0101 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0101 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0111 = SYSCLK multiplie  0111 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the coeff.  h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5	n processor. re multiplier set by t	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only)	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 10	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0011 = SYSCLK multiplie  0011 = SYSCLK multiplie  0011 = SYSCLK multiplie	Identification Registe dentifies device as GXr Inly) — Identifies the co 21)  h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5  h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0010 = SYSCLK multiplie  0010 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0010 = SYSCLK multiplie  0100 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5 d by 5 h or greater then MUL d by 4 (Test mode only) d by 10 d by 4 (Test mode only) d by 6 d by 9	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0111 = SYSCLK multiplie  0112 = SYSCLK multiplie  0113 = SYSCLK multiplie  0114 = SYSCLK multiplie  0115 = SYSCLK multiplie  0116 = SYSCLK multiplie  0117 = SYSCLK multiplie  0118 = SYSCLK multiplie  0119 = SYSCLK multiplie  0119 = SYSCLK multiplie  0119 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 6 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5 d by 9 d by 9 d by 5	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 8 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5 d by 9 d by 9 d by 5 d by 7	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0111 = SYSCLK multiplie  0112 = SYSCLK multiplie  0113 = SYSCLK multiplie  0114 = SYSCLK multiplie  0115 = SYSCLK multiplie  0116 = SYSCLK multiplie  0117 = SYSCLK multiplie  0118 = SYSCLK multiplie  0119 = SYSCLK multiplie  0119 = SYSCLK multiplie  0119 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 8 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5 d by 9 d by 9 d by 5 d by 7	n processor. re multiplier set by t :	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  Signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 8 d by 7 d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 4 (Test mode only) d by 5 d by 9 d by 9 d by 5 d by 7	n processor. re multiplier set by t : .T[3:0]:	
7:4	DID[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  Signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0001 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0110 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie	Identification Registe dentifies device as GXr nly) — Identifies the co 21) h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 8 d by 7 d by 5 h or greater then MUL d by 4 (Test mode only) d by 6 d by 9 d by 5 d by 9 d by 5 d by 7 d by 8 d by 9 d by 5 d by 9 d by 5 d by 7 d by 8	n processor. re multiplier set by t : .T[3:0]:	he CLKMODE[2:0] pins (see
7:4 3:0	DID[3:0] MULT[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  Signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0111 = SYSCLK multiplie  1xxx = Reserved  If DIR1 (Index FFh) is 50  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0010 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  0112 = SYSCLK multiplie  0113 = SYSCLK multiplie  014 = SYSCLK multiplie  015 = SYSCLK multiplie  016 = SYSCLK multiplie  017 = SYSCLK multiplie  018 = SYSCLK multiplie  019 = SYSCLK multiplie  010 =	Identification Register dentifies device as GXr Inly) — Identifies the co 21)  h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 8 d by 7 d by 5  h or greater then MUL d by 4 (Test mode only) d by 6 d by 9 d by 5 d by 9 d by 5 d by 7 d by 8  Identification Register vision (Read Only) — processor revision 1.0	n processor. re multiplier set by t : .T[3:0]: .T[3:0]: .DIR1 indicates devi	he CLKMODE[2:0] pins (see
7:4 3:0	DID[3:0] MULT[3:0]	Device ID (Read Only): I  Core Multiplier (Read Only): I  Signal descriptions page 2  If DIR1 (Index FFh) is 30  0000 = SYSCLK multiplie  0010 = SYSCLK multiplie  0011 = SYSCLK multiplie  0100 = SYSCLK multiplie  0101 = SYSCLK multiplie  0101 = SYSCLK multiplie  0110 = SYSCLK multiplie  0111 = SYSCLK multiplie  111 = SYSCLK multiplie  111 = SYSCLK multiplie  112 = SYSCLK multiplie  113 = SYSCLK multiplie  114 = SYSCLK multiplie  115 = SYSCLK multiplie  116 = SYSCLK multiplie  117 = SYSCLK multiplie  118 = SYSCLK multiplie  119 = SYSCLK multiplie  110 = SYSCLK multiplie  111 = SYSCLK multiplie  112 = SYSCLK multiplie  113 = SYSCLK multiplie  114 = SYSCLK multiplie  115 = SYSCLK multiplie  116 = SYSCLK multiplie  117 = SYSCLK multiplie  117 = SYSCLK multiplie  118 = SYSCLK multiplie  119 = SYSCLK multiplie  119 = SYSCLK multiplie  110 =	Identification Register dentifies device as GXr Inly) — Identifies the co 21)  h-4Fh then MULT[3:0] d by 4 (Test mode only) d by 6 d by 4 (Test mode only) d by 8 d by 7 d by 5  h or greater then MUL d by 4 (Test mode only) d by 6 d by 9 d by 5 d by 9 d by 5 d by 7 d by 8  Identification Register vision (Read Only) — processor revision 1.0 processor revision 2.4	n processor. re multiplier set by t : .T[3:0]: .T[3:0]: .DIR1 indicates devi - 2.3 - 3.x	he CLKMODE[2:0] pins (see

### 3.3.2.3 Debug Registers

Six debug registers (DR0-DR3, DR6 and DR7) support debugging on the GXm processor. Memory addresses loaded in the debug registers, referred to as "breakpoints," generate a debug exception when a memory access of the specified type occurs to the specified address. A breakpoint can be specified for a particular kind of memory access such as a read or write operation. Code and data breakpoints can also be set allowing debug exceptions to occur whenever a given data access (read or write operation) or code access (execute) occurs. The size of the debug target can be set to 1, 2, or 4 bytes. The debug registers are accessed through MOV instructions that can be executed only at privilege level 0 (real mode is always privilege level 0).

The Debug Address Registers (DR0-DR3) each contain the linear address for one of four possible breakpoints. Each breakpoint is further specified by bits in the Debug Control Register (DR7). For each breakpoint address in DR0-DR3, there are corresponding fields L, R/W, and LEN in DR7 that specify the type of memory access associated with the breakpoint.

The R/W field can be used to specify instruction execution as well as data access breakpoints. Instruction execution breakpoints are always taken before execution of the instruction that matches the breakpoint. The Debug Registers are mapped in Table 3-12

Table 3-12. Debug Registers

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
DR	7 Re	gist	er								ı	Debi	ug C	ont	rol F	Regi	ster	7 (R	(W)												
LEN3 R/W3 LEN2 R/W2 LEN1 R/W1 LEN0 R/W0 0 0 G D											0	0	1	0	0	G 3	L 3	G 2	L 2	G 1	L 1	G 0	LO								
DR	DR6 Register Debug Status Register 6 (RO)																														
0	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0															В0															
DR	DR3 Register' Debug Address Register 3 (R/W))																														
												В	reak	poin	t 3 L	inea	ar Ac	ddres	ss												
DR	2 Re	gist	er								0	ebu	ıg A	ddre	ess	Regi	ster	2 (F	R/W)												
												В	reak	poin	t 2 L	inea	ar Ac	ddres	ss												
DR	1 Re	gist	er								0	ebu	ıg A	ddre	ess	Regi	ster	1 (F	R/W)												
												В	reak	poin	t 1 L	inea	ar Ac	ddres	ss												
DR	0 Re	gist	er								0	ebu	ıg A	ddre	ess	Regi	ster	0 (F	R/W)												
	Breakpoint 0 Linear Address																														
Not	e: /	All bi	ts m	arke	ed as	s 0 o	r 1 a	re re	eserv	ved	and	shou	ıld n	ot be	e mo	difie	ed.														

The Debug Status Register (DR6) reflects conditions that were in effect at the time the debug exception occurred. The contents of the DR6 register are not automatically cleared by the processor after a debug exception occurs, and therefore should be cleared by software at the appropriate time. Table 3-13 lists the field definitions for the DR6 and DR7 registers.

Code execution breakpoints may also be generated by placing the breakpoint instruction (INT3) at the location where control is to be regained. The single-step feature may be enabled by setting the TF flag (bit 8) in the EFLAGS register. This causes the processor to perform a debug exception after the execution of every instruction. Debug Registers 6 and 7 are shown in Table 3-13.

Table 3-13. DR7 and DR6 Bit Definitions

Field(s)	Number of Bits	Description
DR7 Register		Debug Control Register 7 (R/W)
R/Wn	2	Applies to the DRn breakpoint address register:  00 = Break on instruction execution only  01 = Break on data write operations only  10 = Not used  11 = Break on data reads or write operations.
LENn	2	Applies to the DRn breakpoint address register:  00 = One-byte length  01 = Two-byte length  10 = Not used  11 = Four-byte length.
Gn	1	If = 1: breakpoint in DRn is globally enabled for all tasks and is not cleared by the processor as the result of a task switch.
Ln	1	If = 1: breakpoint in DRn is locally enabled for the current task and is cleared by the processor as the result of a task switch.
GD	1	Global disable of debug register access. GD bit is cleared whenever a debug exception occurs.
DR6 Register		Debug Status Register 6 (RO)
Bn	1	Bn is set by the processor if the conditions described by DRn, R/Wn, and LENn occurred when the debug exception occurred, even if the breakpoint is not enabled via the Gn or Ln bits.
ВТ	1	BT is set by the processor before entering the debug handler if a task switch has occurred to a task with the T bit in the TSS set.
BS	1	BS is set by the processor if the debug exception was triggered by the single-step execution mode (TF flag, bit 8, in EFLAGS set).
<b>Note:</b> n = 0, 1,	2, and 3	·

### 3.3.2.4 Test Registers

The five test registers are used in testing the processor's Translation Lookaside Buffer (TLB) and on-chip cache. TR6 and TR7 are used for TLB testing, and TR3-TR5 are used for cache testing. Table 3-14 is a register map for the Test Registers with their bit definitions given in Tables 3-15 and 3-17.

### **TLB Test Registers**

The processor's TLB is a 32-entry, four-way set associative memory. Each TLB entry consists of a 24-bit tag and 20-bit data. The 24-bit tag represents the high-order 20 bits of the linear address, a valid bit, and three attribute bits. The 20-bit data portion represents the upper 20 bits of the physical address that corresponds to the linear address.

The TLB Test Data Register (TR7) contains the upper 20 bits of the physical address (TLB data field), three LRU bits and a control bit. During TLB write operations, the physical address in TR7 is written into the TLB entry selected by the contents of TR6. During TLB lookup operations, the TLB data selected by the contents of TR6 is loaded into TR7. Table 3-15 lists the bit definitions for TR7 and TR6.

The TLB Test Control Register (TR6) contains a command bit, the upper 20 bits of a linear address, a valid bit and the attribute bits used in the test operation. The contents of TR6 are used to create the 24-bit TLB tag during both write and read (TLB lookup) test operations. The command bit defines whether the test operation is a read or a write.

### Table 3-14. TLB Test Registers

																		_													
31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
TR	TR7 Register TLB Test Data Register (R/W)																														
	Physical Address												0	0	TL	B L	RU	0	0	PL	RI	ĒΡ	0	0							
TR	TR6 Register TLB Test Control Register (R/W)																														
	Linear Address											٧	D	D#	U	U#	R	R#	0	0	0	0	С								

Table 3-15. TR7-TR6 Bit Definitions

Bit	Name	Description										
TR7 Regis	ter	TLB Test Data Register (R/W)										
31:12	Physical Address	Physical Address:  TLB lookup: Data field from the TLB.  TLB write: Data field written into the TLB.										
11:10	RSVD	Reserved: Set to 0.										
9:7	TLB LRU	LRU Bits:  TLB lookup: LRU bits associated with the TLB entry the TLB write: Ignored.	pefore the TLB lookup.									
4	PL	PL Bit:  TLB lookup: If PL = 1, read hit occurred. If PL = 0, read miss occurred.  TLB write: If PL = 1, REP field is used to select the set. If PL = 0, the pseudo-LRU replacement algorithm is used to select the set.										
3:2	REP	Set Selection:  TLB lookup: If PL = 1, this field indicates the set in which the tag was found. If PL = 0, undefined data.  TLB write: If PL = 1, this field selects one of the four sets for replacement. If PL = 0, ignored.										
1:0	RSVD	Reserved: Set to 0.										
TR6 Regis	ter	TLB Test Control Register (R/M	V)									
31:12	Linear Address	Linear Address:  TLB lookup: The TLB is interrogated per this address. If one and only one match occurs in the TLB, the rest of the fields in TR6 and TR7 are updated per the matching TLB entry.  TLB write: A TLB entry is allocated to this linear address.										
11	V	Valid Bit:  TLB write: If V = 1, the TLB entry contains valid data.										
10:9 8:7 6:5	D, D# U, U# R, R#	Dirty Attribute Bit and its Complement (D, D#) User/Supervisor Attribute Bit and its Complement Read/Write Attribute Bit and its Complement (R, F	` ' '									
		Effect on TLB Lookup  00 = Do not match 01 = Match if D, U, or R bit is a 0 10 = Match if D, U, or R bit is a 1 11 = Match if D, U, or R bit is either a 1 or 0	Effect on TLB Write Undefined Clear the bit Set the bit Undefined									
4:1	RSVD	Reserved: Set to 0.										
0	С	Command Bit:  If C = 1: TLB lookup.  If C = 0: TLB write.										

### **Cache Test Registers**


The processor's 16 KB on-chip cache is a four-way set associative memory that is configured as write-back cache. Each cache set contains 256 entries. Each entry consists of a 20-bit tag address, a 16-byte data field, a valid bit, and four dirty bits.

The 20-bit tag represents the high-order 20 bits of the physical address. The 16-byte data represents the 16 bytes of data currently in memory at the physical address represented by the tag. The valid bit indicates whether the data bytes in the cache actually contain valid data. The four dirty bits indicate if the data bytes in the cache have been modified internally without updating external memory (write-back configuration). Each dirty bit indicates the

status for one double-word (4 bytes) within the 16-byte data field.

For each line in the cache, there are three LRU bits that indicate which of the four sets was most recently accessed. A line is selected using bits [11:4] of the physical address. Figure 3-1 illustrates the CPU cache architecture.

The CPU contains three test registers (TR5-TR3) that allow testing of its internal cache. Bit definitions for the cache test registers are shown in Table 3-17. Using a 16-byte cache fill buffer and a 16-byte cache flush buffer, cache reads and writes may be performed.



= Cache Entry (153 bits)
Tag Address (20 bits)
Data (128 bits)
Valid Status (1 bit)
Dirty Status (4 bits)

Figure 3-1. CPU Cache Architecture

### Table 3-16. Cache Test Registers

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
TR!	5 Re	gist	er (I	R/W)	)																										
	RSVD												Line Selection Set/ Control DWORD Bits																		
TR4	R4 Register (R/W)																														
	Cache Tag Address											0	Valid	LF	RU B	Bits		Dirty	y Bit	S	0	0	0								
TR	TR3 Register (R/W)																														
														(	Cacl	ne D	ata														

## Table 3-17. TR5-TR3 Bit Definitions

Bit	Name	Description
TR5 Regis	ster (R/W)	
11:4	Line Selection	Line Selection:
		Physical address bits 11-4 used to select one of 256 lines.
3:2	Set/DWORD	Set/DWord Selection:
		Cache read: Selects which of the four sets in the cache is used as the source for data transferred to the cache flush buffer.
		Cache write: Selects which of the four sets in the cache is used as the destination for data transferred from the cache fill buffer.
		Flush buffer read: Selects which of the four Dword in the flush buffer is used during a TR3 read.
		Fill buffer write: Selects which of the four Dword in the fill buffer is written during a TR3 write.
1:0	Control Bits	Control Bits:
		If = 00: flush read or fill buffer write.
		If = 01: cache write.
		If = 10: cache read. If = 11: cache flush.
TR4 Regis	ster (R/W)	II - 11. Oddro noon.
31:12	Upper Tag	Upper Tag Address:
01.12	Address	Cache read: Upper 20 bits of tag address of the selected entry.
		Cache write: Data written into the upper 20 bits of the tag address of the selected entry.
10	Valid Bit	Valid Bit:
		Cache read: Valid bit for the selected entry.
		Cache write: Data written into the valid bit for the selected entry.
9:7	LRU Bits	LRU Bits:
		Cache read: The LRU bits for the selected line.
		xx1 = Set 0 or Set 1 most recently accessed.
		xx0 = Set 2 or Set 3 most recently accessed.
		x1x = Most recent access to Set 0 or Set 1 was to Set 0.
		x0x = Most recent access to Set 0 or Set 1 was to Set 1.
		1xx = Most recent access to Set 2 or Set 3 was to Set 2.  0xx = Most recent access to Set 2 or Set 3 was to Set 3.
		Cache write: Ignored.
6:3	Dirty Bits	Dirty Bits:
		Cache read: The dirty bits for the selected entry (one bit per DWord).
		Cache write: Data written into the dirty bits for the selected entry.
2:0	RSVD	Reserved: Set to 0.
TR3 Regis		
31:0	Cache Data	Cache Data:
		Flush buffer read: Data accessed from the cache flush buffer.
		Fill buffer write: Data to be written into the cache fill buffer.

There are five types of test operations that can be executed:

- Flush buffer read
- Fill buffer write
- Cache write
- Cache read
- · Cache flush

These operations are described in detail in Table 3-18. To fill a cache line with data, the fill buffer must be written four

times. Once the fill buffer holds a complete cache line of data (16 bytes), a cache write operation transfers the data from the fill buffer to the cache.

To read the contents of a cache line, a cache read operation transfers the data in the selected cache line to the flush buffer. Once the flush buffer is loaded, the programmer accesses the contents of the flush buffer by executing four flush buffer read operations.

**Table 3-18. Cache Test Operations** 

<b>Test Operation</b>	Code Sequence	Action Taken
Flush Buffer Read	MOV TR5, 0h	Set DWORD = 0, control = 00 = flush buffer read.
	MOV dest,TR3	Flush buffer (31:0)> dest.
	MOV TR5, 4h	Set DWORD = 1, control = 00 = flush buffer read.
	MOV dest,TR3	Flush buffer (63:32)> dest.
	MOV TR5, 8h	Set DWORD = 2, control = 00 = flush buffer read.
	MOV dest,TR3	Flush buffer (95:64)> dest.
	MOV TR5, Ch	Set DWORD = 3, control = 00 = flush buffer read.
	MOV dest,TR3	Flush buffer (127:96)> dest.
Fill Buffer Write	MOV TR5, 0h	Set DWORD = 0, control = 00 = fill buffer write.
	MOV TR3, cache_data	Cache_data> fill buffer (31:0).
	MOV TR5, 4h	Set DWORD = 1, control = 00 = fill buffer write.
	MOV TR3, cache_data	Cache_data> fill buffer (63:32).
	MOV TR5, 8h	Set DWORD = 2, control = 00 = fill buffer write.
	MOV TR3, cache_data	Cache_data> fill buffer (95:64).
	MOV TR5, Ch	Set DWORD = 3, control = 00 = fill buffer write.
	MOV TR3, cache_data	Cache_data> fill buffer (127:96).
Cache Write	MOV TR4, cache_tag	Cache_tag> tag address, valid and dirty bits.
	MOV TR5, line+set+control=01	Fill buffer (127:0)> cache line (127:0).
Cache Read	MOV TR5, line+set+control=10	Cache line (127:0)> flush buffer (127:0).
	MOV dest, TR4	Cache line tag address, valid/LRU/dirty bits> dest.
Cache Flush	MOV TR5, 3h	Control = 11 = cache flush, all cache valid bits = 0.

#### 3.3.3 Model Specific Register Set

The Model Specific Register (MSR) Set is used to monitor the performance of the processor or a specific component within the processor.

A MSR can be read using the RDMSR instruction, opcode 0F32h. During a MSR read, the contents of the particular MSR, specified by the ECX Register, is loaded into the EDX:EAX Registers.

A MSR can be written using the WRMSR instruction, opcode 0F30h. During a MSR write, the contents of EX:EAX are loaded into the MSR specified in the ECX Register.

The RDMSR and WRMSR instructions are privileged instructions.

The GXm processor contains one 64-bit Model Specific Register (MSR10) the Time Stamp Counter (TSC).

#### 3.3.4 Time Stamp Counter

The processor contains a model specific register (MSR) called the Time Stamp Counter (TSC). The TSC, (MSR[10]), is a 64-bit counter that counts the internal CPU clock cycles since the last reset. The TSC uses a continuous CPU core clock and will continue to count clock cycles even when the processor is in suspend or shutdown mode.

The TSC is read using a RDMSR instruction, opcode 0F 32h, with the ECX register set to 10h. During a TSC read, the contents of the TSC is loaded into the EDX:EAX registers.

The TSC is written to using a WRMSR instruction, opcode 0F 30h with the ECX register set to 10h. During a TSC write, the contents of EX:EAX are loaded into the TSC.

The RDMSR and WRMSR instructions are privileged instructions.

In addition, the TSC can be read using the RDTSC instruction, opcode 0F 31h. The RDTSC instruction loads the contents of the TSC into EDX:EAX. The use of the RDTSC instruction is restricted by the TSC flag (bit 2) in the CR4 register (refer to Tables 3-6 and 3-7 on pages 45 and 45 for CR4 register information). When the TSC bit = 0, the RDTSC instruction can be executed at any privilege level. When the TSC bit = 1, the RDTSC instruction can only be executed at privilege level 0.

#### 3.4 ADDRESS SPACES

The GXm processor can directly address either memory or I/O space. Figure 3-2 illustrates the range of addresses available for memory address space and I/O address space. For the CPU, the addresses for physical memory range between 00000000h and FFFFFFFF (4 GBytes). The accessible I/O addresses space ranges between 00000000h and 0000FFFh (64 KB). The CPU does not use coprocessor communication space in upper I/O space between 800000F8h and 800000FFh as do the 386-style CPUs. The I/O locations 22h and 23h are used for GXm processor configuration register access.

#### 3.4.1 I/O Address Space

The CPU I/O address space is accessed using IN and OUT instructions to addresses referred to as "ports." The accessible I/O address space is 64 KB and can be accessed as 8-bit, 16-bit or 32-bit ports.

The GXm processor configuration registers reside within the I/O address space at port addresses 22h and 23h and are accessed using the standard IN and OUT instructions.

The configuration registers are modified by writing the index of the configuration register to port 22h, and then transferring the data through port 23h. Accesses to the on-chip configuration registers do not generate external I/O cycles. However, each operation on port 23h must be preceded by a write to port 22h with a valid index value. Otherwise, subsequent port 23h operations will communicate through the I/O port to produce external I/O cycles without modifying the on-chip configuration registers. Write operations to port 22h outside of the CPU index range (C0h-CFh and FEh-FFh) result in external I/O cycles and do not affect the on-chip configuration registers. Reading port 22h generates external I/O cycles.

I/O accesses to port address range 3B0h through 3DFh can be trapped to SMI by the CPU if this option is enabled in the BC\_XMAP\_1 register (see SMIB, SMIC, and SMID bits in Table 4-10 on page 101). Figure 3-2 illustrates the I/O address space.

#### 3.4.2 Memory Address Space

The processor directly addresses up to 4 GB of physical memory even though the memory controller addresses only 1 GB of DRAM. Memory address space is accessed as bytes, words (16 bits) or DWORDs (32 bits). Words and DWORDs are stored in consecutive memory bytes with the low-order byte located in the lowest address. The physical address of a word or DWORD is the byte address of the low-order byte.

The processor allows memory to be addressed using nine different addressing modes. These addressing modes are used to calculate an offset address, often referred to as an effective address. Depending on the operating mode of the CPU, the offset is then combined, using memory management mechanisms, into a physical address that is applied to the physical memory devices.

Memory management mechanisms consist of segmentation and paging. Segmentation allows each program to use several independent, protected address spaces. Paging translates a logical address into a physical address using translation lookup tables. Virtual memory is often implemented using paging. Either or both of these mechanisms can be used for management of the GXm processor memory address space.




Figure 3-2. Memory and I/O Address Spaces

### 3.5 OFFSET, SEGMENT, AND PAGING MECHANISMS

The mapping of address space into a sequence of memory locations (often cached) is performed by the offset, segment and paging mechanisms.

In general, the offset, segment and paging mechanisms work in tandem as shown below:

instruction offset *⇒* offset mechanism *⇒* offset address offset address *⇒* segment mechanism *⇒* linear address linear address *⇒*paging mechanism *⇒*physical page.

As will be explained, the actual operations depend on several factors such as the current operating mode and if paging is enabled. Note: the paging mechanism uses part of the linear address as an offset on the physical page.

### 3.6 OFFSET MECHANISM

In all operating modes, the offset mechanism computes an offset (effective) address by adding together up to three values: a base, an index and a displacement. The base, if present, is the value in one of eight general registers at the time of the execution of the instruction. The index, like the base, is a value that is contained in one of the general registers (except the ESP register) when the instruction is executed. The index differs from the base in that the index is first multiplied by a scale factor of 1, 2, 4 or 8 before the summation is made. The third component added to the memory address calculation is the displacement that is a value supplied as part of the instruction. Figure 3-3 illustrates the calculation of the offset address.

Nine valid combinations of the base, index, scale factor and displacement can be used with the CPU instruction set. These combinations are listed in Table 3-19 on page 61. The base and index both refer to contents of a register as indicated by [Base] and [Index].

In real mode operation, the CPU only addresses the lowest 1 MB of memory and the offset contains 16-bits. In protective mode the offset contains 32 bits. Initialization and transition to protective mode is described in Section 3.13.4 "Initialization and Transition to Protected Mode" on page 87.




Figure 3-3. Offset Address Calculation

Table 3-19. Memory Addressing Modes

Addressing Mode	Base	Index	Scale Factor (SF)	Displacement (DP)	Offset Address (OA) Calculation
Direct				х	OA = DP
Register Indirect	х				OA = [BASE]
Based	х			х	OA = [BASE] + DP
Index		х		х	OA = [INDEX] + DP
Scaled Index		х	х	х	OA = ([INDEX] * SF) + DP
Based Index	х	х			OA = [BASE] + [INDEX]
Based Scaled Index	х	х	х		OA = [BASE] + ([INDEX] * SF)
Based Index with Displacement	х	х		х	OA = [BASE] + [INDEX] + DP
Based Scaled Index with Displacement	х	Х	х	х	OA = [BASE] + ([INDEX] * SF) + DP

#### 3.7 DESCRIPTORS AND SEGMENT MECHANISMS

Memory is divided into contiguous regions called "segments." The segments allow the partitioning of individual elements of a program. Each segment provides a zero address-based private memory for such elements as code, data and stack space.

The segment mechanisms select a segment in memory. Memory is divided into an arbitrary number of segments, each containing usually much less than the 2<sup>32</sup> byte (4 GByte) maximum.

There are two segment mechanisms, one for Real and Virtual 8086 Operating Modes, and one for Protective Mode.

# 3.7.1 Real and Virtual 8086 Mode Segment Mechanisms

### **Real Mode Segment Mechanism**

In real mode operation, the CPU addresses only the lowest 1 MB of memory. In this mode a selector located in one of the segment registers is used to locate a segment. To calculate a physical memory address, the 16-bit segment base address located in the selected segment register is multiplied by 16 and then a 16-bit offset address is added. The resulting 20-bit address is then extended with twelve zeros in the upper address bits to crate 32-bit physical address.

The value of the selector (the INDEX field) is multiplied by 16 to produce a base address (Figure 3-4.) The base address is summed with the instruction offset value to produce a physical address.

### Virtual 8086 Mode Segment Mechanism

In Virtual 8086 mode the operation is performed as in real mode except that a paging mechanism is added. When paging is enabled, the paging mechanism translates the linear address into a physical address using cached look-up tables (refer to Section 3.9 "Paging Mechanism" on page 72).




Figure 3-4. Real Mode Address Calculation

#### 3.7.2 Segment Mechanism in Protective Mode

The segment mechanism in protective mode is more complex. Basically as in Real and Virtual 8086 modes the offset address is added to the segment base address to produce a linear address (Figure 3-5). However, the calculation of the segment base address is based on the contents of descriptor tables.

Again, if paging is enabled the linear address is further processed by the paging mechanism.

A more detailed look at the segment mechanisms for real, virtual 8086 and protective modes is illustrated in Figure 3-6. In protective mode, the segment selector is cached. This is illustrated in Figure 3-7 on page 65.

### 3.7.2.1 Segment Selectors

The segment registers are used to store segment selectors. In protective mode, the segment selectors are

divided in to three fields: the RPL, TI and INDEX fields as shown in Figure 3-6.

The segments are assigned permission levels to prevent application program errors from disrupting operating programs. The Requested Privilege Level (RPL) determines the Effective Privilege Level of an instruction. RPL = 0 indicates the most privileged level, and RPL = 3 indicates the least privileged level. Refer to Section 3.13 "Protection" on page 86.

Descriptor tables hold descriptors that allow management of segments and tables in address space while in protective mode. The Table Indicator Bit (TI) in the selector selects either the General Descriptor Table (GDT) or one Local Descriptor Tables (LDT) tables. If TI = 0, GDT is selected; if TI =1, LDT is selected. The 13-bit INDEX field in the segment selector is used to index a GDT or LDT table.






Figure 3-5. Protected Mode Address Calculation



#### Real and Virtual 8086 Modes



**Protective Mode** 

Figure 3-6. Selector Mechanisms

## **Processor Programming (Continued)** Selector Load Instruction Segment Register Selected By Decoded Instruction Selector INDEX In Segment RPL Segment Register Caching Cached Segment and Descriptor Segment Descriptor TI = 0Cached Global Descriptor Selector Segment Table Used If Base Available Address

Figure 3-7. Selector Mechanism Caching

Segment Descriptor

Local Descriptor Table TI = 1

#### 3.7.3 GDTR and LDTR Registers

The GDT, and LDT descriptor tables are defined by the Global Descriptor Table Register (GDTR) and the Local Descriptor Table Register (LDTR) respectively. Some texts refer to these registers as GDT, and LDT descriptors.

The following instructions are used in conjunction with the GDT and LDT registers:

- · LGDT Load memory to GDTR
- LLDT Load memory to LDTR
- · SGDT Store GDTR to memory
- · SLDT Store LDTR to memory

The GDTR is set up in REAL mode using the LGDT instruction. This is possible as the LGDT instruction is one of two instructions that directly load a linear address (instead of a segment relative address) in protective mode. (The other instruction is the Load Interrupt Descriptor Table [LIDT]).

As shown in Table 3-20, the GDT registers contain a BASE ADDRESS field and a LIMIT field that define the GDT tables. (The IDTR is described in Section 3.7.3.2 "Task, Gate and Interrupt Descriptors" on page 67.)

Also shown in Table 3-20, the LDTR is only two bytes wide as it contains only a SELECTOR field. The contents of the SELECTOR field point to a descriptor in the GDT.

#### 3.7.3.1 Segment Descriptors

There are several types of descriptors. A segment descriptor defines the base address, limit and attributes of a memory segment.

The GDT or LDT can hold several types of descriptors. In particular, the segment descriptors are stored in either of two registers, the GDT, or the LDT as shown in Table 3-20). Either of these tables can store as many as 8,192 (2<sup>13</sup>) eight-byte selectors taking as much as 64 KB of memory.

The first descriptor in the GDT (location 0) is not used by the CPU and is referred to as the "null descriptor."

## **Types of Segment Descriptors**

The type of memory segments are defined by corresponding types of segment descriptors:

- Code Segment Descriptors
- Data Segment Descriptors
- · Stack Segment Descriptors
- · LDT Segment Descriptors

#### Table 3-20. GDTR, LDTR and IDTR Registers

	-					_										
47	16	15 14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
GDT Register GI	obal Descriptor	Table	Reg	ister	,											
BASE	BASE LIMIT															
DT Register Interrupt Descriptor Table Register																
BASE								LIN	⁄IIT							
LDT Register Lo	ocal Descriptor	Table	Regi	ster												
	SELECTOR															

#### 3.7.3.2 Task, Gate and Interrupt Descriptors

Besides segment descriptors there are descriptors used in task switching, switching between tasks with different priority and those used to control interrupt functions:

- Task State Segment Table Descriptors
- Gate Table Descriptors
- · Interrupt Descriptors.

All descriptors have some things in common. They are all eight bytes in length and have three fields (BASE, LIMIT and TYPE). The BASE field defines the starting location for the table or segment. The LIMIT field defines the size and the TYPE field depends on the type of descriptor. One of the main functions of the TYPE field is to define the access rights to the associated segment or table.

### **Interrupt Descriptor Table**

The Interrupt Descriptor Table is an array of 256 8-byte (4-byte for real mode) interrupt descriptors, each of which is used to point to an interrupt service routine. Every interrupt that may occur in the system must have an associated entry in the IDT. The contents of the IDTR are completely visible to the programmer through the use of the SIDT instruction.

The IDT descriptor table is defined by the Interrupt Descriptor Table Register (IDTR). Some texts refer to this register as an IDT descriptor.

The following instructions are used in conjunction with the IDTR registers:

- · LIDT Load memory to IDTR
- · SIDT Store IDTR to memory

The IDTR is set up in REAL mode using the LIDT instruction. This is possible as the LIDT instructions is only one of two instructions that directly load a linear address (instead of a segment relative address) in protective mode.

As previously shown in Table 3-20, the IDTR contains a BASE ADDRESS field and a LIMIT field that define the IDT tables.

### 3.7.4 Descriptor Bit Structure

The bit structure for application and system descriptors is shown in Table 3-21. The explanation of the TYPE field is shown in Table 3-23 on page 68.

### Table 3-21. Application and System Segment Descriptors

31	31	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Me	mor	y Of	fset	+4																											
		BA	\SE	[31:2	24]			G	D	0	A V L	LII	MIT[	19:1	6]	Р	DF	PL	S		TY	PE				BA	\SE[	[23:1	6]		
Ме	mor	y Of	fset	+0																											
						В	ASE	[15:	0]													L	IMIT	[15:0	0]						

#### Table 3-22. Application and System Segment Descriptors Bit Definitions

Bit	Memory Offset	Name	Description
31:24	+4	BASE	Segment Base Address: Three fields which collectively define the base location for the segment in
7:0	+4		4 GB physical address space.
31:16	+0		
19:16	+4	LIMIT	Segment Limit: Two fields that define the size of the segment based on the Segment Limit
15:0	+0		Granularity Bit.
			If G = 1: Limit value interpreted in units of 4 KB.  If G = 0: Limit value is interpreted in bytes.
23	+4	G	Segment Limit Granularity Bit: Defines LIMIT multiplier.
			If G = 1: Limit value interpreted in units of 4 KB. Segment size ranges from 1 byte to 1 MB.  If G = 0: Limit value is interpreted in bytes. Segment size ranges from 4 KB to 4 GB.
22	+4	D	Default Length for Operands and Effective Addresses:
			If D = 1: Code segment = 32-bit length for operands and effective addresses
			If D = 0: Code segment = 16-bit length for operands and effective addresses
			If D = 1: Data segment = Pushes, calls and pop instructions use 32-bit ESP register
			If D = 0: Data segment = Stack operations use 16-bit SP register
20	+4	AVL	Segment Available: This field is available for use by system software.

Table 3-22. Application and System Segment Descriptors Bit Definitions (Continued)

Bit	Memory Offset	Name	Description
15	+4	Р	Segment Present:
			If = 1: Segment is memory segment allocated.
			If = 0: The BASE and LIMIT fields become available for use by the system. Also, If = 0, a segment- not-present exception generated when selector for the descriptor is loaded into a segment register allowing virtual memory management.
14:13	+4	DPL	Descriptor Privilege Level:
			If = 00: Highest privilege level If = 11: Low privilege level
12	+4	S	Descriptor Type:
			If = 1: Code or data segment If = 0: System segment
11:8	+4	TYPE	Segment Type: Refer to Table 3-23 on page 68 for TYPE bit definitions.  Bit 11 = Executable  Bit 10 = Conforming if bit 12 = 1  Bit 10 = Expand Down if bit 12 = 0  Bit 9 = Readable, if Bit 12 = 1  Bit 9 = Writable, if Bit 12 = 0  Bit 8 = Accessed

Table 3-23. Application and System Segment Descriptors TYPE Bit Definitions

I -	YPE [11:8]	System Segment and Gate Types Bit 12 = 0	Application Segment Types Bit 12 = 1							
Num	SEWA	TYPE	PE (Data Segments)							
0	0000	Reserved	Data	Read-Only						
1	0001	Available 16-Bit TSS	Data	Read-Only, accessed						
2	0010	LDT	Data	Read/Write						
3	0011	Busy 16-Bit TSS	Data	Read/Write accessed						
4	0100	16-Bit Call Gate	Data	Read-Only, expand down						
5	0101	Task Gate	Data	Read-Only, expand down, accessed						
6	0110	16-Bit Interrupt Gate	pt Gate Data Read/Write, expand down							
7	0111	16-Bit Trap Gate	Data	Read/Write, expand down, accessed						
Num	SCRA	TYPE	(Code Se	egments)						
8	1000	Reserved	Code	Execute-Only						
9	1001	Available 32-Bit TSS	Code	Execute-Only, accessed						
Α	1010	Reserved	Code	Execute/Read						
В	1011	Busy 32-Bit TSS	Code	Execute/Read, accessed						
С	1100	32-Bit Call Gate	Code	Execute/Read, conforming						
D	1101	Reserved	Code	Execute/Read, conforming, accessed						
E	1110	32-Bit Interrupt Gate	Code	Execute/Read-Only, conforming						
F	1111	32-Bit Trap Gate	Code	Execute/Read-Only, conforming accessed						
	S = Co	de Segment (not Data Segment)  E = Expand Down  W = Write Enable	essed Iforming Code Segment Id Enable							

#### 3.7.5 Gate Descriptors

Four kinds of gate descriptors are used to provide protection during control transfers: call gates, trap gates, interrupt gates and task gates. (For more information on protection refer to Section 3.13 "Protection" on page 86.)

**Call Gate Descriptor (CGD).** Call gates are used to define legal entry points to a procedure with a higher privilege level. The call gates are used by CALL and JUMP instructions in much the same manner as code segment descriptors. When the CPU decodes an instruction and sees it refers to a call gate descriptor in the GDT table or a LDT table, the call gate is used to point to another descriptor in the table that defines the destination code segment.

The following privilege levels are tested during the transfer through the call gate:

- CPL = Current Privilege Level
- RPL = Segment Selector Field
- DPL = Descriptor Privilege Level in the call gate descriptor.
- DPL = Descriptor Privilege Level in the destination code segment.

The maximum value of the CPL and RPL must be equal or less than the gate DPL. For a JMP instruction the destination DPL equals the CPL. For a CALL instruction the destination DPL is less or equals the CPL.

Conforming Code Segments. Transfer to a procedure with a higher privilege level can also be accomplished by bypassing the use of call gates, if the requested procedure is to be executed in a conforming code segment. Conforming code segments have the C bit set in the TYPE field in their descriptor.

The bit structure and definitions for gate descriptors are shown in Tables 3-24 and Table 3-25 on page 69.

## **Table 3-24. Gate Descriptors**

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Ме	mor	y Of	fset	+4																											
						OF	FSE	T[31	:16]							Р	DI	PL	0		TY	PE		0	0	0	F	ARA	ME	ΓER:	S
Ме	mor	y Of	fset	+0																											
					;	SELI	ECT	OR[	15:0]	]												OF	FSE	T[1	5:0]						

## Table 3-25. Gate Descriptors Bit Definitions

Bit	Memory Offset	Name	Description	
31:16	+4	OFFSET	Offset: Offset used during a call gate to	o calculate the branch target.
15:0	+0			
31:16	+0	SELECTOR	Segment Selector	
15	+4	Р	Segment Present	
14:13	+4	DPL	Descriptor Privilege Level	
11:8	+4	TYPE	Segment Type:	
			0100 = 16-bit call gate 0101 = Task gate 0110 = 16-bit interrupt gate 0111 = 16-bit trap gate	1100 = 32-bit call gate 1110 = 32-bit interrupt gate 1111 = 32-bit trap gate
4:0	+4	PARAMETERS	<b>Parameters</b> : Number of parameters to dure's stack.	copy from the caller's stack to the called proce-

#### 3.8 MULTITASKING AND TASK STATE SEGMENTS

The CPU enables rapid task switching using JMP and CALL instructions that refer to Task State Segments (TSS). During a switch, the complete task state of the current task is stored in its TSS, and the task state of the requested task is loaded from its TSS. The TSSs are defined through special segment descriptors and gates.

The **Task Register (TR)** holds 16-bit descriptors that contain the base address and segment limit for each task state segment. The TR is loaded and stored via the LTR and STR instructions, respectively. The TR can only be accessed only during protected mode and can be loaded when the privilege level is 0 (most privileged). When the TR is loaded, the TR selector field indexes a TSS descriptor that must reside in the Global Descriptor Table (GDT).

Only the 16-bit selector of a TSS descriptor in the TR is accessible. The BASE, TSS LIMT and ACCESS RIGHT fields are program invisible.

During task switching, the processor saves the current CPU state in the TSS before starting a new task. The TSS can be either a 386/486-type 32-bit TSS (see Table 3-26) or a 286-type 16-bit TSS (see Table 3-27 on page 71).

**Task Gate Descriptors**. A task gate descriptor provides controlled access to the descriptor for a task switch. The DPL of the task gate is used to control access. The selector's RPL and the CPL of the procedure must be a higher level (numerically less) than the DPL of the descriptor. The RPL in the task gate is not used.

The I/O Map Base Address field in the 32-bit TSS points to an I/O permission bit map that often follows the TSS at location +68h.

16 15 0 0 Т I/O Map Base Address 0 0 0 0 +64h Selector for Task's LDT +60h GS +5Ch FS +58h DS +54h SS +50h CS +4Ch ES +48h EDI +44h ESI +40h EBP +3Ch **ESP** +38h **EBX** +34h EDX +30h ECX +2Ch EAX +28h **EFLAGS** +24h EIP +20h CR3 +1Ch SS for CPL = 2+18h ESP for CPL = 2+14h 0 0 0 SS for CPL = 1 +10h ESP for CPL = 1 +Ch 0 0 0 0 0 SS for CPL = 0+8h ESP for CPL = 0+4h 0 0 0 0 0 0 0 0 0 0 0 0 Back Link (Old TSS Selector) +0h

Table 3-26. 32-Bit Task State Segment (TSS) Table

Note: 0 = Reserved

Table 3-27. 16-Bit Task State Segment (TSS) Table

15	0
Selector for Task's LDT	
DS	
SS	
CS	
ES	
DI	
SI	
ВР	
SP	
BX	
DX	
CX	
AX	
EFLAGS	
IP	
SS for Privilege Level 0	
SP for Privilege Level 1	
SS for Privilege Level 1	
SP for Privilege Level 1	
SS for Privilege Level 0	
SP for Privilege Level 0	
Back Link (Old TSS Selector)	

#### 3.9 PAGING MECHANISM

The paging mechanism translates a linear address to its corresponding physical address. If the required page is not currently present in RAM, an exception is generated. When the operating system services the exception, the required page can be loaded into memory and the instruction restarted. Pages are either 4 KB or 1 MB in size. The CPU defaults to 4 KB pages that are aligned to 4 KB boundaries.

A page is addressed by using two levels of tables as illustrated in Figure 3-8. Bits[31:22] of the 32-bit linear address, the Directory Table Index (DTI) are used to

locate an entry in the page directory table. The page directory table acts as a 32-bit master index to up to 1 K individual second-level page tables. The selected entry in the page directory table, referred to as the directory table entry (DTE), identifies the starting address of the second-level page table. The page directory table itself is a page and is, therefore, aligned to a 4 KB boundary. The physical address of the current page directory table is stored in the CR3 control register, also referred to as the Page Directory Base Register (PDBR).




Figure 3-8. Paging Mechanism

Bits [21:12] of the 32-bit linear address, referred to as the Page Table Index (PTI), locate a 32-bit entry in the second-level page table. This Page Table Entry (PTE) contains the base address of the desired page frame. The second-level page table addresses up to 1K individual page frames. A second-level page table is 4 KB in size and is itself a page. Bits [11:0] of the 32-bit linear address, the Page Frame Offset (PFO), locate the desired physical data within the page frame.

Since the page directory table can point to 1 K page tables, and each page table can point to 1 K page frames, a total of 1 M page frames can be implemented. Since each page frame contains 4 KB, up to 4 GB of virtual memory can be addressed by the CPU with a single page directory table.

Along with the base address of the page table or the page frame, each directory table entry or page table entry contains attribute bits and a present bit as illustrated in Table 3-28.

If the present bit (P) is set in the DTE, the page table is present and the appropriate page table entry is read. If P = 1 in the corresponding PTE (indicating that the page is in memory), the accessed and dirty bits are updated, if necessary, and the operand is fetched. Both accessed bits are set (DTE and PTE), if necessary, to indicate that the table and the page have been used to translate a linear address. The dirty bit (D) is set before the first write is made to a page.

The present bits must be set to validate the remaining bits in the DTE and PTE. If either of the present bits are not set, a page fault is generated when the DTE or PTE is accessed. If P=0, the remaining DTE/PTE bits are available for use by the operating system. For example, the operating system can use these bits to record where on the hard disk the pages are located. A page fault is also generated if the memory reference violates the page protection attributes.

#### **Translation Look-Aside Buffer**

The translation look-aside buffer (TLB) is a cache for the paging mechanism and replaces the two-level page table lookup procedure for TLB hits. The TLB is a four-way set associative 32-entry page table cache that automatically keeps the most commonly used page table entries in the processor. The 32-entry TLB, coupled with a 4 K page size, results in coverage of 128 KB of memory addresses.

The TLB must be flushed when entries in the page tables are changed. The TLB is flushed whenever the CR3 register is loaded. An individual entry in the TLB can be flushed using the INVLPG instruction.

#### **DTE Cache**

The DTE cache caches the two most recent DTEs so that future TLB misses only require a single page table read to calculate the physical address. The DTE cache is disabled following reset and can be enabled by setting the DTE\_EN bit in CCR4[4] (Index E8h).

Table 3-28. Directory Table Entry (DTE) and Page Table Entry (PTE)

Bit	Name	Description
31:12	BASE ADDRESS	Base Address: Specifies the base address of the page or page table.
11:9	AVAILABLE	Available: Undefined and Available to the Programmer
8:7	RSVD	Reserved: Unavailable to programmer
6	D	Dirty Bit:  PTE format — If = 1: Indicates that a write access has occurred to the page.  DTE format — Reserved.
5	А	Accessed Flag: If set, indicates that a read access or write access has occurred to the page.
4:3	RSVD	Reserved: Set to 0.
2	U/S	User/Supervisor Attribute:  If = 1: Page is accessible by User at privilege level 3.  If = 0: Page is accessible by Supervisor only when CPL ≤ 2.
1	W/R	Write/Read Attribute:  If = 1: Page is writable.  If = 0: Page is read only.
0	Р	Present Flag:  If = 1: The page is present in RAM and the remaining DTE/PTE bits are validated  If = 0: The page is not present in RAM and the remaining DTE/PTE bits are available for use by the programmer.

#### 3.10 INTERRUPTS AND EXCEPTIONS

The processing of either an interrupt or an exception changes the normal sequential flow of a program by transferring program control to a selected service routine. Except for SMM interrupts, the location of the selected service routine is determined by one of the interrupt vectors stored in the interrupt descriptor table.

True interrupts are hardware interrupts and are generated by signal sources external to the processor. All exceptions (including so-called software interrupts) are produced internally by the processor.

#### 3.10.1 Interrupts

External events can interrupt normal program execution by using one of the three interrupt pins on the GXm processor:

- Non-maskable Interrupt (NMI pin)
- Maskable Interrupt (INTR pin)
- SMM Interrupt (SMI# pin)

For most interrupts, program transfer to the interrupt routine occurs after the current instruction has been completed. When the execution returns to the original program, it begins immediately following the interrupted instruction.

The **NMI** interrupt cannot be masked by software and always uses interrupt vector 2 to locate its service routine. Since the interrupt vector is fixed and is supplied internally, no interrupt acknowledge bus cycles are performed. This interrupt is normally reserved for unusual situations such as parity errors and has priority over INTR interrupts.

Once NMI processing has started, no additional NMIs are processed until an IRET instruction is executed, typically at the end of the NMI service routine. If NMI is re-asserted before execution of the IRET instruction, one and only one NMI rising edge is stored and then processed after execution of the next IRET.

During the NMI service routine, maskable interrupts may be enabled. If an unmasked INTR occurs during the NMI service routine, the INTR is serviced and execution returns to the NMI service routine following the next IRET. If a HALT instruction is executed within the NMI service routine, the CPU restarts execution only in response to RESET, an unmasked INTR or a System Management Mode (SMM) interrupt. NMI does not restart CPU execution under this condition.

The **INTR** interrupt is unmasked when the Interrupt Enable Flag (IF, bit 9) in the EFLAGS register is set to 1. Except for string operations, INTR interrupts are acknowledged between instructions. Long string operations have interrupt windows between memory moves that allow INTR interrupts to be acknowledged.

When an INTR interrupt occurs, the processor performs an interrupt-acknowledge bus cycle. During this cycle, the CPU reads an 8-bit vector that is supplied by an external interrupt controller. This vector selects which of the 256 possible interrupt handlers will be executed in response to the interrupt.

The **SMM** interrupt has higher priority than either INTR or NMI. After SMI# is asserted, program execution is passed to an SMI service routine that runs in SMM address space reserved for this purpose. The remainder of this section does not apply to the SMM interrupts. SMM interrupts are described in greater detail later in this section.

### 3.10.2 Exceptions

Exceptions are generated by an interrupt instruction or a program error. Exceptions are classified as traps, faults or aborts depending on the mechanism used to report them and the restartability of the instruction which first caused the exception.

A **Trap exception** is reported immediately following the instruction that generated the trap exception. Trap exceptions are generated by execution of a software interrupt instruction (INTO, INT3, INTn, BOUND), by a single-step operation or by a data breakpoint.

Software interrupts can be used to simulate hardware interrupts. For example, an INTn instruction causes the processor to execute the interrupt service routine pointed to by the nth vector in the interrupt table. Execution of the interrupt service routine occurs regardless of the state of the IF flag (bit 9) in the EFLAGS register.

The one byte INT3, or breakpoint interrupt (vector 3), is a particular case of the INTn instruction. By inserting this one byte instruction in a program, the user can set breakpoints in the code that can be used during debug.

Single-step operation is enabled by setting the TF bit (bit 8) in the EFLAGS register. When TF is set, the CPU generates a debug exception (vector 1) after the execution of every instruction. Data breakpoints also generate a debug exception and are specified by loading the debug registers (DR0-DR7) with the appropriate values.

A **Fault exception** is reported before completion of the instruction that generated the exception. By reporting the fault before instruction completion, the processor is left in a state that allows the instruction to be restarted and the effects of the faulting instruction to be nullified. Fault exceptions include divide-by-zero errors, invalid opcodes, page faults and coprocessor errors. Debug exceptions (vector 1) are also handled as faults (except for data breakpoints and single-step operations). After execution of the fault service routine, the instruction pointer points to the instruction that caused the fault.

An **Abort exception** is a type of fault exception that is severe enough that the CPU cannot restart the program at the faulting instruction. The double fault (vector 8) is the only abort exception that occurs on the processor.

#### 3.10.3 Interrupt Vectors

When the processor services an interrupt or exception, the current program's instruction pointer and flags are pushed onto the stack to allow resumption of execution of the interrupted program. In protected mode, the processor also saves an error code for some exceptions. Program control is then transferred to the interrupt handler (also called the interrupt service routine). Upon execution of an IRET at the end of the service routine, program execution resumes at the instruction pointer address saved on the stack when the interrupt was serviced.

### 3.10.3.1 Interrupt Vector Assignments

Each interrupt (except SMI#) and exception is assigned one of 256 interrupt vector numbers as shown in Table 3-29. The first 32 interrupt vector assignments are defined or reserved. INT instructions acting as software interrupts may use any of interrupt vectors, 0 through 255.

The non-maskable hardware interrupt (NMI) is assigned vector 2. Illegal opcodes including faulty FPU instructions will cause an illegal opcode exception, interrupt vector 6. NMI interrupts are enabled by setting bit 2 of the CCR7 register (Index EBh[2] = 1, see Table 3-11 on page 49 for register format).

In response to a maskable hardware interrupt (INTR), the processor issues interrupt acknowledge bus cycles used to read the vector number from external hardware. These vectors should be in the range 32 to 255 as vectors 0 to 31 are predefined. In PCs, vectors 8 through 15 are used.

#### 3.10.3.2 Interrupt Descriptor Table

The interrupt vector number is used by the processor to locate an entry in the interrupt descriptor table (IDT). In real mode, each IDT entry consists of a four-byte far pointer to the beginning of the corresponding interrupt service routine. In protected mode, each IDT entry is an 8-byte descriptor. The Interrupt Descriptor Table Register (IDTR) specifies the beginning address and limit of the IDT. Following reset, the IDTR contains a base address of 0h with a limit of 3FFh.

The IDT can be located anywhere in physical memory as determined by the IDTR. The IDT may contain different types of descriptors: interrupt gates, trap gates and task gates. Interrupt gates are used primarily to enter a hardware interrupt handler. Trap gates are generally used to enter an exception handler or software interrupt handler. If an interrupt gate is used, the Interrupt Enable Flag (IF) in the EFLAGS register is cleared before the interrupt handler is entered. Task gates are used to make the transition to a new task.

Table 3-29. Interrupt Vector Assignments

1 Debu	Function e error g exception nterrupt	Exception Type Fault Trap/Fault*
1 Debu 2 NMI i	g exception nterrupt	
2 NMI i	nterrupt	Trap/Fault*
	•	
3 Breal	rnoint	
	фонт	Trap
4 Interr	upt on overflow	Trap
5 BOU	ND range exceeded	Fault
6 Invali	d opcode	Fault
7 Device	e not available	Fault
8 Doub	le fault	Abort
9 Rese	rved	
10 Invali	d TSS	Fault
11 Segn	nent not present	Fault
12 Stack	fault	Fault
13 Gene	ral protection fault	Trap/Fault
14 Page	fault	Fault
15 Rese	rved	
16 FPU	error	Fault
17 Align	ment check exception	Fault
18:31 Rese	rved	
32:55 Mask	able hardware interrupts	Trap
0:255 Progr	ammed interrupt	Trap

Note: \*Data breakpoints and single steps are traps. All other debug exceptions are faults.

#### 3.10.4 Interrupt and Exception Priorities

As the CPU executes instructions, it follows a consistent policy for prioritizing exceptions and hardware interrupts. The priorities for competing interrupts and exceptions are listed in Table 3-30. SMM interrupts always take precedence. Debug traps for the previous instruction and next instructions are handled as the next priority. When NMI and maskable INTR interrupts are both detected at the same instruction boundary, the GXm processor services the NMI interrupt first.

The CPU checks for exceptions in parallel with instruction decoding and execution. Several exceptions can result from a single instruction. However, only one exception is

generated upon each attempt to execute the instruction. Each exception service routine should make the appropriate corrections to the instruction and then restart the instruction. In this way, exceptions can be serviced until the instruction executes properly.

The CPU supports instruction restart after all faults, except when an instruction causes a task switch to a task whose task state segment (TSS) is partially not present. A TSS can be partially not present if the TSS is not page aligned and one of the pages where the TSS resides is not currently in memory.

Table 3-30. Interrupt and Exception Priorities

Priority	Description	Notes
0	Warm Reset.	Caused by the assertion of WM_RST.
1	SMM hardware interrupt.	SMM interrupts are caused by SMI# asserted and always have highest priority.
2	Debug traps and faults from previous instruction.	Includes single-step trap and data breakpoints specified in the debug registers.
3	Debug traps for next instruction.	Includes instruction execution breakpoints specified in the debug registers.
4	Non-maskable hardware interrupt.	Caused by NMI asserted.
5	Maskable hardware interrupt.	Caused by INTR asserted and IF = 1.
6	Faults resulting from fetching the next instruction.	Includes segment not present, general protection fault and page fault.
7	Faults resulting from instruction decoding.	Includes illegal opcode, instruction too long, or privilege violation.
8	WAIT instruction and TS = 1 and MP = 1.	Device not available exception generated.
9	ESC instruction and EM = 1 or TS = 1.	Device not available exception generated.
10	Floating point error exception.	Caused by unmasked floating point exception with NE = 1.
11	Segmentation faults (for each memory reference required by the instruction) that prevent transferring the entire memory operand.	Includes segment not present, stack fault, and general protection fault.
12	Page Faults that prevent transferring the entire memory operand.	
13	Alignment check fault.	

### 3.10.5 Exceptions in Real Mode

Many of the exceptions described in Table 3-29 on page 75 are not applicable in real mode. Exceptions 10, 11, and 14 do not occur in real mode. Other exceptions have slightly different meanings in real mode as listed in Table 3-31.

Table 3-31. Exception Changes in Real Mode

Vector Number	Protected Mode Function	Real Mode Function
8	Double fault.	Interrupt table limit overrun.
10	Invalid TSS.	Does not occur.
11	Segment not present.	Does not occur.
12	Stack fault.	SS segment limit overrun.
13	General protection fault.	CS, DS, ES, FS, GS segment limit overrun. In protected mode, an error is pushed. In real mode, no error is pushed.
14	Page fault.	Does not occur.

### 3.10.6 Error Codes

When operating in protected mode, the following exceptions generate a 16-bit error code:

- Double Fault
- Alignment Check
- Invalid TSS
- Segment Not Present
- Stack Fault
- General Protection Fault
- Page Fault

The error code format and bit definitions are shown in Table 3-32. Bits [15:3] (selector index) are not meaningful if the error code was generated as the result of a page fault. The error code is always zero for double faults and alignment check exceptions.

#### Table 3-32. Error Codes

15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
					Sel	ector In	dex						S2	S1	S0

#### Table 3-33. Error Code Bit Definitions

Fault Type	Selector Index (Bits 15:3)	S2 (Bit 2)	S1 (Bit 1)	S0 (Bit 0)
Page Fault	Reserved.	Fault caused by:  0 = Not present page  1 = Page-level protection violation	Fault occurred during: 0 = Read access 1 = Write access	Fault occurred during 0 = Supervisor access 1 = User access.
IDT Fault	Index of faulty IDT selector.	Reserved	1	If = 1, exception occurred while trying to invoke exception or hardware interrupt handler.
Segment Fault	Index of faulty selector.	TI bit of faulty selector	0	If =1, exception occurred while trying to invoke exception or hardware interrupt handler.

#### 3.11 SYSTEM MANAGEMENT MODE

System Management Mode (SMM) is usually employed for system power management or software-transparent emulation of I/O peripherals. SMM mode is entered through a hardware signal "System Management Interrupt" (SMI# pin) that has a higher priority than any other interrupt, including NMI. An SMM interrupt can also be triggered from software using an SMINT instruction. Following an SMM interrupt, portions of the CPU state are automatically saved, SMM mode is entered, and program execution begins at the base of SMM address space (Figure 3-9).

The GXm processor extends System Management Mode (SMM) to support the virtualization of many devices, including VGA video. The SMM mechanism can be triggered not only by I/O activity, but by access to selected memory regions. For example, SMM interrupts are generated when VGA addresses are accessed. As will be described, other SMM enhancements have reduced SMM overhead and improved virtualization-software performance




Figure 3-9. System Management Memory Address Space

#### 3.11.1 SMM Enhancements

Eight SMM instructions have been added to the x86 instruction set that permit initiating SMM through software and saving and restoring the total CPU state when in SMM.

The SMM header now:

- · Stores 32-bits memory addresses.
- · Stores 32-bit memory data.
- · Differentiates memory and I/O accesses.
- Indicates if an SMM interrupt was generated by access to a VGA region.

The SMM service code is now cacheable. An SMAR register specifies the SMM region code base and limit. An SMHR register specifies the physical address for the SMM header. The SMI\_NEST bit enables the nesting of SMM interrupts.

#### 3.11.2 SMM Operation

SMM execution flow is summarized in Figure 3-10. Entering SMM requires the assertion of the SMI# pin for at least two SYSCLK periods or execution of the SMINT instruction. For the SMI# signal or SMINT instruction to be recognized, configuration register bits must be set as shown in Table 3-34. (The configuration registers are discussed in detail in Section 3.3.2.2 "Configuration Registers" on page 47.)

After triggering an SMM through the SMI# pin or a SMINT instruction, selected CPU state information is automatically saved in the SMM memory space header located at the top of SMM memory space. After saving the header, the CPU enters real mode and begins executing the SMM service routine starting at the SMM memory region base address.

The SMM service routine is user definable and may contain system or power management software. If the power management software forces the CPU to power down or if the SMM service routine modifies more registers than are automatically saved, the complete CPU state information should be saved.

Table 3-34. SMI# and SMINT Recognition Requirements

Register Bits	SMI#	SMINT
USE_SMI, CCR1[1] (Index C1h)	1	1
SMAC, CCR1[2] (Index C1h)	0	1
SIZE[3:0], SMAR3[3:0] (Index CFh)	>0	>0




Figure 3-10. SMM Execution Flow

#### 3.11.3 The SMI# Pin

External chipsets can generate an SMI based on numerous asynchronous events, including power management timers, I/O address trapping, external devices, audio FIFO events, and others. Since SMI# is edge sensitive, the chipset must generate an edge for each of the events above, requiring arbitration and storage of multiple SMM events. These functions are provided by the CS5530 I/O companion device. The processor generates an SMI when the external pin changes from high-to-low or when an RSM occurs if SMI# has not remained low since the initiation of the previous SMI.

### 3.11.4 SMM Configuration Registers

The SMAR register specifies the base location of SMM code region and its size limit. This SMAR register is identical to many of the National Semconductor processors.

A new configuration control register called SMHR has been added to specify the 32-bit physical address of the SMM header. The SMHR address must be 32-bit aligned as the bottom two bits are ignored by the microcode. Hardware will detect write operations to SMHR, and signal the microcode to recompute the header address. Access to these registers is enabled by MAPEN (Index C3h[4]).

The SMAR register writes to the SMM header when the SMAR register is changed. For this reason, changes to the SMAR register should be completed prior to setting up the SMM header. The configuration registers bit formats are detailed in Table 3-11 on page 49.

#### 3.11.5 SMM Memory Space Header

Tables 3-35 and show the SMM header. A memory address field has been added to the end (offset -40h) of the header for the GXm processor. Memory data will be stored overlapping the I/O data, since these events cannot occur simultaneously. The I/O address is valid for both IN and OUT instructions, and I/O data is valid only for OUT. The memory address is valid for read and write operations, and memory data is valid only for write operations.

With every SMI interrupt or SMINT instruction, selected CPU state information is automatically saved in the SMM memory space header located at the top of SMM address space. The header contains CPU state information that is modified when servicing an SMM interrupt. Included in this information are two pointers. The current IP points to the instruction executing when the SMI was detected, but it is valid only for an internal I/O SMI.

The Next IP points to the instruction that will be executed after exiting SMM. The contents of Debug Register 7 (DR7), the Extended FLAGS Register (EFLAGS), and Control Register 0 (CR0) are also saved. If SMM has been entered due to an I/O trap for a REP INSx or REP OUTSx instruction, the Current IP and Next IP fields contain the same addresses. In addition, the I and P fields contain valid information.

If entry into SMM is the result of an I/O trap, it is useful for the programmer to know the port address, data size and data value associated with that I/O operation. This information is also saved in the header and is valid only if SMI# is asserted during an I/O bus cycle. The I/O trap information is not restored within the CPU when executing a RSM instruction.

Table 3-35. SMM Memory Space Header

																	-															
Mem. Offset	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
-4h																DF	٦7															
–8h																EFL	AGS	3														
–Ch																CF	₹0															
-10h															C	Curre	ent II	Р														
-14h		Next IP																														
–18h								RS	VD														С	S Se	elect	tor						
-1Ch														CS	De	scrip	otor	[63:	32]													
-20h														CS	S De	escri	ptor	[31	:0]							<u> </u>						
-24h								RS	VD										F	RSVI	)			Ν	٧	Х	М	Η	S	Р	Ι	С
–28h							I/O	Dat	a Si	ze												I/	O A	ddre	ess	[15:0	0]					
–2Ch												I/	′O о	r Me	emo	ry D	ata	[31:	1) [0	Vote	)											
-30h														Re	esto	red I	ESI	or E	DI													
-32h		Memory Address [31:0]																														
Note: 0	Chec	k th	е М	bit a	at of	fset	24h	to c	lete	min	e if t	the o	data	is r	nem	ory	or I/	О.								te: Check the M bit at offset 24h to determine if the data is memory or I/O.						

Table 3-36. SMM Memory Space Header Description

Name	Description	Size
DR7	Debug Register 7: The contents of Debug Register 7.	4 Bytes
EFLAGS	Extended FLAGS Register: The contents of Extended FLAGS Register.	4 Bytes
CR0	Control Register 0: The contents of Control Register 0.	4 Bytes
Current IP	<b>Current Instruction Pointer:</b> The address of the instruction executed prior to servicing SMM interrupt.	4 Bytes
Next IP	<b>Next Instruction Pointer:</b> The address of the next instruction that will be executed after exiting SMM.	4 Bytes
CS Selector	Code Segment Selector: Code segment register selector for the current code segment.	2 Bytes
CS Descriptor	Code Segment Descriptor: Encoded descriptor bits for the current code segment.	8 Bytes
N	Nested SMI Status: Flag that determines whether an SMI occurred during SMM (i.e., nested)	1 Bit
V	SoftVGA SMI Status: SMI was generated by an access to VGA region.	1 Bit
X	External SMI Status:  If = 1: SMI generated by external SMI# pin  If = 0: SMI internally generated by Internal Bus Interface Unit.	1 Bit
M	Memory or I/O Access: 0 = I/O access; 1 = Memory access.	1 Bit
Н	Halt Status: Indicates that the processor was in a halt or shutdown prior to servicing the SMM interrupt.	1 Bit
S	Software SMM Entry Indicator:  If = 1: Current SMM is the result of an SMINT instruction.  If = 0: Current SMM is not the result of an SMINT instruction.	1 Bit
Р	REP INSx/OUTSx Indicator:	1 Bit
	If = 1: Current instruction has a REP prefix. If = 0: Current instruction does not have a REP prefix.	
I	IN, INSx, OUT, or OUTSx Indicator:  If = 1: Current instruction performed is an I/O WRITE.  If = 0: Current instruction performed is an I/O READ.	1 Bit
С	CS Writable: Code Segment Writable  If = 1: CS is writable  If = 0: CS is not writable	1 Bit
I/O Data Size	Indicates size of data for the trapped I/O cycle:  01h = byte  03h = word  0Fh = DWORD	2 Bytes
I/O Address	Processor port used for the trapped I/O cycle.	2 Bytes
I/O or Memory Data	Data associated with the trapped I/O or memory cycleS.	4 Bytes
Restored ESI or EDI	<b>Restored ESI or EDI Value:</b> Used when it is necessary to repeat a REP OUTSx or REP INSx instruction when one of the I/O cycles caused an SMI# trap.	4 Bytes
Memory Address	Physical address of the operation that caused the SMI.	4 Bytes

Note: INSx = INS, INSB, INSW or INSD instruction.
OUTSx = OUTS, OUTSB, OUTSW and OUTSD instruction.

#### 3.11.6 SMM Instructions

The GXm processor core automatically saves the minimal amount of CPU state information when entering an SMM cycle that allows fast SMM service-routine entry and exit. After entering the SMM service routine, the MOV, SVDC, SVLDT and SVTS instructions can be used to save the complete CPU state information. If the SMM service routine modifies more state information than is automatically saved or if it forces the CPU to power down, the complete CPU state information must be saved. Since the CPU is a static device, its internal state is retained when the input clock is stopped. Therefore, an entire CPU-state save is not necessary before stopping the input clock.

The SMM instructions, listed in Table 3-37, can be executed only if all the conditions listed below are met.

- 1) USE\_SMI = 1.
- 2) SMAR SIZE > 0.
- 3) Current Privilege level = 0.
- SMAC bit is high or the CPU is in an SMI service routine.

If any one of the conditions above is not met and an attempt is made to execute an SVDC, RSDC, SVLDT, RSLDT, SVTS, RSTS, or RSM instruction, an invalid opcode exception is generated. The SMM instructions can be executed outside of defined SMM space provided the conditions above are met.

The SMINT instruction can be used by software to enter SMM. The SMINT instruction can only be used outside an SMM routine if all the conditions listed below are true.

- 1) USE\_SMI = 1
- 2) SMAR size > 0
- 3) Current Privilege Level = 0
- 4) SMAC = 1

If SMI# is asserted to the CPU during a software SMI, the hardware SMI# is serviced after the software SMI has been exited by execution of the RSM instruction.

All the SMM instructions (except RSM and SMINT) save or restore 80 bits of data, allowing the saved values to include the hidden portion of the register contents.

Table 3-37. SMM Instruction Set

Instruction	Opcode	Format	Description
SVDC	0F 78h [mod sreg3 r/m]	SVDC mem80, sreg3	Save Segment Register and Descriptor
			Saves reg (DS, ES, FS, GS, or SS) to mem80.
RSDC	0F 79h [mod sreg3 r/m]	RSDC sreg3, mem80	Restore Segment Register and Descriptor
			Restores reg (DS, ES, FS, GS, or SS) from mem80. Use RSM to restore CS.
			Note: Processing "RSDC CS, Mem80" will produce an exception.
SVLDT	0F 7Ah [mod 000 r/m]	SVLDT mem80	Save LDTR and Descriptor
			Saves Local Descriptor Table (LDTR) to mem80.
RSLDT	0F 7Bh [mod 000 r/m]	RSLDT mem80	Restore LDTR and Descriptor
			Restores Local Descriptor Table (LDTR) from mem80.
SVTS	0F 7Ch [mod 000 r/m]	SVTS mem80	Save TSR and Descriptor
			Saves Task State Register (TSR) to mem80.
RSTS	0F 7Dh [mod 000 r/m]	RSTS mem80	Restore TSR and Descriptor
			Restores Task State Register (TSR) from mem80.
SMINT	0F 38h	SMINT	Software SMM Entry
			CPU enters SMM. CPU state information is saved in SMM memory space header and execution begins at SMM base address.
RSM	0F AAh	RSM	Resume Normal Mode
			Exits SMM. The CPU state is restored using the SMM memory space header and execution resumes at interrupted point.

**Note:** smem80 = 80-bit memory location.

#### 3.11.7 SMM Memory Space

SMM memory space is defined by specifying the base address and size of the SMM memory space in the SMAR register. The base address must be a multiple of the SMM memory space size. For example, a 32 KB SMM memory space must be located at a 32 KB address boundary. The memory space size can range from 4 KB to 32 MB. Execution of the interrupt begins at the base of the SMM memory space.

SMM memory space accesses are always cacheable, which allows SMM routines to run faster.

#### 3.11.8 SMI Generation

Virtualization software depends on processor-specific hardware to generate SMI interrupts for each memory or I/O access to the device being implemented. The GXm processor implements SMI generation for VGA accesses. Memory write operations in regions A0000h to AFFFFh, B0000h to B7FFFh, and B8000h to BFFFFh generate an SMI.

Memory reads are not trapped by the GXm processor. The GXm processor traps I/O addresses for VGA in the following regions: 3B0h to 3BFh, 3C0h to 3CFh, and 3D0h to 3DFh. Memory-write trapping is performed during instruction decode in the processor core. I/O read and write trapping is implemented in the Internal Bus Interface Unit of the GXm processor.

The SMI-generation hardware requires two additional configuration registers to control and mask SMI interrupts in the VGA memory space: VGACTL and VGAM. The VGACTL register has a control bit for each address range shown above. The VGAM register has 32 bits that can selectively disable 2 KB regions within the VGA memory. The VGAM applies only to the A0000h-to-AFFFFh region. If this region is not enabled in VGA\_CTL, then the contents of VGAM is ignored. The purpose of VGAM is to prevent SMI from occurring when non-displayed VGA memory is accessed. This is an enhancement which improves performance for double-buffered applications. The format of each register is shown in Chapter 4 of this document.

#### 3.11.9 SMI Service Routine Execution

Upon entry into SMM, after the SMM header has been saved, the CR0, EFLAGS, and DR7 registers are set to their reset values. The Code Segment (CS) register is loaded with the base, as defined by the SMAR register, and a limit of 4 GBytes. The SMI service routine then begins execution at the SMM base address in real mode.

The programmer must save the value of any registers that may be changed by the SMI service routine. For data accesses immediately after entering the SMI service routine, the programmer must use CS as a segment override. I/O port access is possible during the routine but care must be taken to save registers modified by the I/O instructions. Before using a segment register, the register and the register's descriptor cache contents should be saved using the SVDC instruction.

Hardware interrupts, INTRs and NMIs, may be serviced during an SMI service routine. If interrupts are to be serviced while executing in the SMM memory space, the SMM memory space must be within the address range of 0 to 1 MB to guarantee proper return to the SMI service routine after handling the interrupt.

INTRs are automatically disabled when entering SMM since the IF flag (EFLAGS register, bit 9) is set to its reset value. Once in SMM, the INTR can be enabled by setting the IF flag. An NMI event in SMM can be enabled by setting NMI\_EN high in the CCR3 register (Index C3h[1]). If NMI is not enabled while in SMM, the CPU latches one NMI event and services the interrupt after NMI has been enabled or after exiting SMM through the RSM instruction. The processor is always in real mode in SMM, but it may exit to either real or protected mode depending on its state when SMM was initiated. The IDT (Interrupt Descriptor Table) indicates which state it will exit to.

Within the SMI service routine, protected mode may be entered and exited as required, and real or protected mode device drivers may be called.

To exit the SMI service routine, a Resume (RSM) instruction, rather than an IRET, is executed. The RSM instruction causes the GXm processor core to restore the CPU state using the SMM header information and resume execution at the interrupted point. If the full CPU state was saved by the programmer, the stored values should be reloaded before executing the RSM instruction using the MOV, RSDC, RSLDT and RSTS instructions.

#### 3.11.9.1 SMI Nesting

The SMI mechanism supports nesting of SMI interrupts through the SMI handler, the SMI\_NEST bit in CCR4[6] (Index E8h), and the Nested SMI Status bit (bit N in the SMM header, see Table on page 80). Nesting is an important capability in allowing high-priority events, such as audio virtualization, to interrupt lower-priority SMI code for VGA virtualization or power management. SMI\_NEST controls whether SMI interrupts can occur during SMM. SMI handlers can optionally set SMI\_NEST high to allow higher-priority SMI interrupts while handling the current event.

The SMI handler is responsible for managing the SMI header data for nested SMI interrupts. The SMI header must be saved before SMI\_NEST is set high, and SMI\_NEST must be cleared and its header information restored before an RSM instruction is executed.

The Nested SMI Status bit has been added to the SMM header to show whether the current SMI is nested. The processor sets Nested SMI Status high if the processor was in SMM when the SMI was taken. The processor uses Nested SMI Status on exit to determine whether the processor should stay in SMM.

When SMI nesting is disabled, the processor holds off external SMI interrupts until the currently executing SMM code exits. When SMI nesting is enabled, the processor can proceed with the SMI. The SMI handler will guarantee

that no internal SMIs are generated in SMM, so the processor ignores such events. If the internal and external SMI signals are received simultaneously, then the internal SMI is given priority to avoid losing the event.

The state diagram of the SMI\_NEST and Nested SMI Status bits are shown in Figure 3-11 with each state explained next.

- A. When the processor is outside of SMM, Nested SMI Status is always clear and SMI\_NEST is set high.
- B. The first-level SMI interrupt is received by the processor. The microcode clears SMI\_NEST, sets Nested SMI Status high and saves the previous value of Nested SMI Status (0) in the SMI header.
- C. The first-level SMI handler saves the header and sets SMI\_NEST high to re-enable SMI interrupts from SMM.
- D. A second-level (nested) SMI interrupt is received by the processor. This SMI is taken even though the processor is in SMM because the SMI\_NEST bit is

- set high. The microcode clears SMI\_NEST, sets Nested SMI Status high and saves the previous value of Nested SMI Status (1) in the SMI header.
- E. The second-level SMI handler saves the header and sets SMI\_NEST to re-enable SMI interrupts within SMM. Another level of nesting could occur during this period.
- F. The second-level SMI handler clears SMI\_NEST to disable SMI interrupts, then restores its SMI header.
- G. The second-level SMI handler executes an RSM. The microcode sets SMI\_NEST, and restores the Nested SMI Status (1) based on the SMI header.
- H. The first-level SMI handler clears SMI\_NEST to disable SMI interrupts, then restores its SMI header.
- I. The first-level SMI handler executes an RSM. The microcode sets SMI\_NEST high and restores the Nested SMI Status (0) based on the SMI header.

When the processor is outside of SMM, Nested SMI Status is always clear and SMI\_NEST is set high.




Figure 3-11. SMI Nesting State Machine

# 3.11.9.2 CPU States Related to SMM and Suspend Mode

The state diagram shown in Figure 3-12 illustrates the various CPU states associated with SMM and Suspend mode. While in the SMI service routine, the GXm processor core can enter Suspend mode either by (1) executing a halt (HLT) instruction or (2) by asserting the SUSP# input.

During SMM operations and while in SUSP#-initiated Suspend mode, an occurrence of either NMI or INTR is

latched. (In order for INTR to be latched, the IF flag, EFLAGS register bit 9, must be set.) The INTR or NMI is serviced after exiting Suspend mode.

If Suspend mode is entered through a HLT instruction from the operating system or application software, the reception of an SMI# interrupt causes the CPU to exit Suspend mode and enter SMM. If Suspend mode is entered through the hardware (SUSP# = 0) while the operating system or application software is active, the CPU latches one occurrence of INTR, NMI, and SMI#.




Figure 3-12. SMM and Suspend Mode State Diagram

#### 3.12 SHUTDOWN AND HALT

The Halt Instruction (HLT) stops program execution and generates a special Halt bus cycle. The GXm processor core then drives out a special Stop Grant bus cycle and enters a low-power Suspend mode if the SUSP\_HLT bit in CCR2 (Index C2h[3]) is set. SMI#, NMI, INTR with interrupts enabled (IF bit in EFLAGS = 1), or RESET forces the CPU out of the halt state. If the halt state is interrupted, the saved code segment and instruction pointer specify the instruction following the HLT.

Shutdown occurs when a severe error is detected that prevents further processing. The most common severe error is the triple fault, a fault event while handling a double fault. Setting the IDT or the GDT limit to zero will cause a triple fault.

An NMI input or a reset can bring the processor out of shutdown. An NMI will work if the IDT limit is large enough, at least 000Fh, to contain the NMI interrupt vector and if the stack has enough room. The stack must be large enough to contain the vector and flag information (the stack pointer must be greater than 0005h).

### 3.13 PROTECTION

Segment protection and page protection are safeguards built into the GXm processor's protected-mode architecture that deny unauthorized or incorrect access to selected memory addresses. These safeguards allow multitasking programs to be isolated from each other and from the operating system. This section concentrates on segment protection.

Selectors and descriptors are the key elements in the segment protection mechanism. The segment base address, size, and privilege level are established by a segment descriptor. Privilege levels control the use of privileged instructions, I/O instructions and access to segments and segment descriptors. Selectors are used to locate segment descriptors.

Segment accesses are divided into two basic types, those involving code segments (e.g., control transfers) and those involving data accesses. The ability of a task to access a segment depends on the:

- · segment type
- instruction requesting access
- type of descriptor used to define the segment
- · associated privilege levels (described next)

Data stored in a segment can be accessed only by code executing at the same or a more privileged level. A code segment or procedure can only be called by a task executing at the same or a less privileged level.

#### 3.13.1 Privilege Levels

The values for privilege levels range between 0 and 3. Level 0 is the highest privilege level (most privileged), and level 3 is the lowest privilege level (least privileged). The privilege level in real mode is zero.

The **Descriptor Privilege Level** (DPL) is the privilege level defined for a segment in the segment descriptor. The DPL field specifies the minimum privilege level needed to access the memory segment pointed to by the descriptor.

The **Current Privilege Level** (CPL) is defined as the current task's privilege level. The CPL of an executing task is stored in the hidden portion of the code segment register and essentially is the DPL for the current code segment.

The Requested Privilege Level (RPL) specifies a selector's privilege level. RPL is used to distinguish between the privilege level of a routine actually accessing memory (the CPL), and the privilege level of the original requester (the RPL) of the memory access. If the level requested by RPL is less than the CPL, the RPL level is accepted and the Effective Privilege Level (EPL) is changed to the RPL value. If the level requested by RPL is greater than CPL, the CPL overrides the requested RPL and EPL becomes the CPL value.

The lesser of the RPL and CPL is called the Effective Privilege Level (EPL). Therefore, if RPL = 0 in a segment selector, the EPL is always determined by the CPL. If RPL = 3, the EPL is always 3 regardless of the CPL.

For a memory access to succeed, the EPL must be at least as privileged as the Descriptor Privilege Level (EPL  $\leq$  DPL). If the EPL is less privileged than the DPL (EPL > DPL), a general protection fault is generated. For example, if a segment has a DPL = 2, an instruction accessing the segment only succeeds if executed with an EPL  $\leq$  2.

#### 3.13.2 I/O Privilege Levels

The I/O Privilege Level (IOPL) allows the operating system executing at CPL = 0 to define the least privileged level at which IOPL-sensitive instructions can unconditionally be used. The IOPL-sensitive instructions include CLI, IN, OUT, INS, OUTS, REP INS, REP OUTS, and STI. Modification of the IF bit in the EFLAGS register is also sensitive to the I/O privilege level.

The IOPL is stored in the EFLAGS register (bits [31:12]). An I/O permission bit map is available as defined by the 32-bit Task State Segment (TSS). Since each task can have its TSS, access to individual I/O ports can be granted through separate I/O permission bit maps.

If CPL  $\leq$  IOPL, IOPL-sensitive operations can be performed. If CPL > IOPL, a general protection fault is generated if the current task is associated with a 16-bit TSS. If the current task is associated with a 32-bit TSS and CPL > IOPL, the CPU consults the I/O permission bitmap in the TSS to determine on a port-by-port basis whether or not I/O instructions (IN, OUT, INS, OUTS, REP INS, REP OUTS) are permitted. The remaining IOPL-sensitive operations generate a general protection fault.

#### 3.13.3 Privilege Level Transfers

A task's CPL can be changed only through intersegment control transfers using gates or task switches to a code segment with a different privilege level. Control transfers result from exception and interrupt servicing and from execution of the CALL, JMP, INT, IRET and RET instructions.

There are five types of control transfers that are summarized in Table 3-38. Control transfers can be made only when the operation causing the control transfer references the correct descriptor type. Any violation of these descriptor usage rules causes a general protection fault.

Any control transfer that changes the CPL within a task results in a change of stack. The initial values for the stack segment (SS) and stack pointer (ESP) for privilege levels 0, 1, and 2 are stored in the TSS. During a JMP or CALL control transfer, the SS and ESP are loaded with the new stack pointer and the previous stack pointer is saved on the new stack. When returning to the original privilege level, the RET or IRET instruction restores the SS and ESP of the less-privileged stack.

#### 3.13.3.1 Gates

Gate descriptors described in Section 3.7.5 "Gate Descriptors" on page 69, provide protection for privilege transfers among executable segments. Gates are used to transition to routines of the same or a more privileged level. Call gates, interrupt gates and trap gates are used for privilege transfers within a task. Task gates are used to transfer between tasks.

Gates conform to the standard rules of privilege. In other words, gates can be accessed by a task if the effective privilege level (EPL) is the same or more privileged than the gate descriptor's privilege level (DPL).

#### 3.13.4 Initialization and Transition to Protected Mode

The GXm processor core switches to real mode immediately after RESET. While operating in real mode, the system tables and registers should be initialized. The GDTR and IDTR must point to a valid GDT and IDT, respectively. The size of the IDT should be at least 256 bytes, and the GDT must contain descriptors that describe the initial code and data segments.

The processor can be placed in protected mode by setting the PE bit (CR0 register bit 0). After enabling protected mode, the CS register should be loaded and the instruction decode queue should be flushed by executing an intersegment JMP. Finally, all data segment registers should be initialized with appropriate selector values.

Table 3-38. Descriptor Types Used for Control Transfer

Type of Control Transfer	Operation Types	Descriptor Referenced	Descriptor Table
Intersegment within the same privilege level.	JMP, CALL, RET, IRET*	Code Segment	GDT or LDT
Intersegment to the same or a more	CALL	Gate Call	GDT or LDT
privileged level. Interrupt within task (could change CPL level).	Interrupt Instruction, Exception, External Interrupt	Trap or Interrupt Gate	IDT
Intersegment to a less privileged level (changes task CPL).	RET, IRET*	Code Segment	GDT or LDT
Task Switch via TSS	CALL, JMP	Task State Segment	GDT
Task Switch via Task Gate	CALL, JMP	Task Gate	GDT or LDT
	IRET**, Interrupt Instruction, Exception, External Interrupt	Task Gate	IDT

Note: \*NT = 0 (Nested Task bit in EFLAGS, bit 14)

\*\*NT =1 (Nested Task bit in EFLAGS, bit 14)

#### **3.14 VIRTUAL 8086 MODE**

Both real mode and virtual 8086 (V86) modes are supported by the GXm processor, allowing execution of 8086 application programs and 8086 operating systems. V86 mode allows the execution of 8086-type applications, yet still permits use of the paging and protection mechanisms. V86 tasks run at privilege level 3. Before entry, all segment limits must be set to FFFFh (64K) as in real mode.

### 3.14.1 Memory Addressing

While in V86 mode, segment registers are used in an identical fashion to real mode. The contents of the Segment register are multiplied by 16 and added to the offset to form the Segment Base Linear Address. The GXm processor permits the operating system to select which programs use the V86 address mechanism and which programs use protected mode addressing for each task.

The GXm processor also permits the use of paging when operating in V86 mode. Using paging, the 1 MB address space of the V86 task can be mapped to any region in the 4 GB linear address space.

The paging hardware allows multiple V86 tasks to run concurrently, and provides protection and operating system isolation. The paging hardware must be enabled to run multiple V86 tasks or to relocate the address space of a V86 task to physical address space other than 0.

### 3.14.2 Protection

All V86 tasks operate with the least amount of privilege (level 3) and are subject to all CPU protected mode protection checks. As a result, any attempt to execute a privileged instruction within a V86 task results in a general protection fault.

In V86 mode, a slightly different set of instructions are sensitive to the I/O privilege level (IOPL) than in protected mode. These instructions are: CLI, INT n, IRET, POPF, PUSHF, and STI. The INT3, INTO and BOUND variations of the INT instruction are not IOPL sensitive.

### 3.14.3 Interrupt Handling

To fully support the emulation of an 8086-type machine, interrupts in V86 mode are handled as follows. When an interrupt or exception is serviced in V86 mode, program execution transfers to the interrupt service routine at privilege level 0 (i.e., transition from V86 to protected mode occurs). The VM bit in the EFLAGS register (bit 17) is cleared. The protected mode interrupt service routine then determines if the interrupt came from a protected mode or V86 application by examining the VM bit in the EFLAGS image stored on the stack. The interrupt service routine may then choose to allow the 8086 operating system to handle the interrupt or may emulate the function of the interrupt handler. Following completion of the interrupt service routine, an IRET instruction restores the EFLAGS register (restores VM = 1) and segment selectors and control returns to the interrupted V86 task.

### 3.14.4 Entering and Leaving Virtual 8086 Mode

V86 mode is entered from protected mode by either executing an IRET instruction at CPL = 0 or by task switching. If an IRET is used, the stack must contain an EFLAGS image with VM = 1. If a task switch is used, the TSS must contain an EFLAGS image containing a 1 in the VM bit position. The POPF instruction cannot be used to enter V86 mode since the state of the VM bit is not affected. V86 mode can only be exited as the result of an interrupt or exception. The transition out must use a 32-bit trap or interrupt gate that must point to a non-conforming privilege level 0 segment (DPL = 0), or a 32-bit TSS. These restrictions are required to permit the trap handler to IRET back to the V86 program.

#### 3.15 FLOATING POINT UNIT OPERATIONS

The FPU is x87-instruction-set compatible and adheres to the IEEE-754 standard. Because most applications that contain FPU instructions intermix with integer instructions, the GXm processor's FPU achieves high performance by completing integer and FPU operations in parallel.

#### 3.15.1 FPU (Floating Point Unit) Register Set

In addition to the registers described to this point, the FPU within the CPU provides the user eight data registers accessed in a stack-like manner, a control register, and a status register. The CPU also provides a data register tag word that improves context switching and stack performance by maintaining empty/non-empty status for each of the eight data registers. In addition, registers contain pointers to (a) the memory location containing the current instruction word and (b) the memory location containing the operand associated with the current instruction word (if any).

### 3.15.2 FPU Tag Word Register

The CPU maintains a tag word register that is divided into eight tag word fields. These fields assume one of four values depending on the contents of their associated data registers: Valid (00), Zero (01), Special (10), and Empty (11). Note: Denormal, Infinity, QNaN, SNaN and unsupported formats are tagged as "Special." Tag values are maintained transparently by the CPU and are only available to the programmer indirectly through the FSTENV and FSAVE instructions. The tag word with tag fields for each associated physical register, tag(n), is shown in Table 3-39 on page 90.

### 3.15.3 FPU Status Register

The FPU communicates status information and operation results to the CPU through the status register. The fields in the FPU status register are detailed in Table 3-39 on page 90. These fields include information related to exception status, operation execution status, register status, operand class, and comparison results. This register is continuously accessible to the CPU regardless of the state of the Control or Execution Units.

#### 3.15.4 FPU Mode Control Register

The FPU Mode Control Register (MCR) shown in Table 3-39 on page 90 is used by the GXm processor to specify the operating mode of the FPU. The MCR register fields include information related to the rounding mode selected, the amount of precision to be used in the calculations, and the exception conditions which should be reported to the GXm processor using traps. The user controls precision, rounding, and exception reporting by setting or clearing appropriate bits in the MCR.

Table 3-39. FPU Registers

		Table 3-39. FPU Registers
Bit	Name	Description
FPU Tag V	Vord Register	(R/W) (Note)
15:14	TAG7	<b>TAG7:</b> 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
13:12	TAG6	<b>TAG6:</b> 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
11:10	TAG5	<b>TAG5:</b> 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
9:8	TAG4	<b>TAG4:</b> 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
7:6	TAG3	<b>TAG3:</b> 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
5:4	TAG2	<b>TAG2:</b> 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
3:2	TAG1	<b>TAG1</b> : 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
1:0	TAG0	<b>TAG0</b> : 00 = Valid; 01 = Zero; 10 = Special; 11 = Empty.
FPU Statu	s Register (R/V	W) (Note)
15	В	Copy of ES bit (bit 7 this register)
14	C3	Condition code bit 3
13:11	S	<b>Top-of-Stack:</b> Register number that points to the current TOS.
10:8	C[2:0]	Condition code bits [2:0]
7	ES	Error indicator: Set to 1 if unmasked exception detected.
6	SF	Stack Full: FPU Status Register: or invalid register operation bit.
5	Р	Precision error exception bit
4	U	Underflow error exception bit
3	0	Overflow error exception bit
2	Z	Divide-by-zero exception bit
1	D	Denormalized-operand error exception bit
0	I	Invalid operation exception bit
FPU Mode	Control Regis	ster (R/W) (Note)
15:12	RSVD	Reserved: Set to 0.
11:10	RC	Rounding Control Bits:  00 = Round to nearest or even  01 = Round towards minus infinity  10 = Round towards plus infinity  11 = Truncate
9:8	PC	Precision Control Bits:  00 = 24-bit mantissa  01 = Reserved  10 = 53-bit mantissa  11 = 64-bit mantissa
7:6	RSVD	Reserved: Set to 0.
5	Р	Precision error exception bit
4	U	FPU Mode Control Register
3	0	Overflow error exception bit
2	Z	Divide-by-zero exception bit
1	D	Denormalized-operand error exception bit
0	I	Invalid-operation exception bit
Note: R/W	only through t	he environment at store and restore commands.

# 4.0 Integrated Functions

The Geode GXm processor integrates a memory controller, graphics pipeline and display controller in a Unified Memory Architecture (UMA). UMA simplifies system designs and significantly reduces overall system costs associated with high chip count, small footprint notebook designs. Performance degradation in traditional UMA systems is reduced through the use of National Semiconductor's Display Compression Technology (DCT).

Figure 4-1 shows the major functional blocks of the GXm processor and how the internal bus interface unit operates as the interface between the processor's core units and the integrated functions.

This section details how the integrated functions and internal bus interface unit operate and their respective registers.




Figure 4-1. Internal Block Diagram

#### 4.1 INTEGRATED FUNCTIONS PROGRAMMING INTERFACE

The GXm processor performs mapping for the dedicated cache, graphics pipeline, display controller, memory controller, and graphics memory, including the frame buffer. It maps these to high memory addresses or GXm processor memory space. The base address for these is controlled by the Graphics Configuration Register (GCR, Index B8h), which specifies address bits [31:30] in physical memory.

Figure 4-2 on page 93 shows the address map for the GXm processor. When accessing the GXm processor memory space, address bits [29:24] must be zero. This allows the GXm processor a linear address space with a total of 16 MB. Address bit 23 divides this space into 8 MB for control (bit 23 = 0) and 8 MB for graphics memory (bit 23 = 1). In control space, bits [22:16] are not decoded, so the programmer should set them to zero. Address bit 15 divides the remaining 64 KB address space into scratch-pad RAM and PCI access (bit 15 = 0) and control registers (bit 15 = 1).

Device drivers must be responsible for performing physical-to-virtual memory-address translation, including allo-

cation of selectors that point to the GXm processor. The processor may be accessed in protected mode by creating a selector with the physical address shown in Table 4-1, and a limit of 16 MB. A selector with a 64 KB limit is large enough to access all of the GXm processor's registers and scratchpad RAM.

### 4.1.1 Graphics Control Register

The GXm processor incorporates graphics functions that require registers to implement and control them. Most of these registers are memory mapped and physically located in the logical units they control. The mapping of these units is controlled by this configuration register. The Graphics Control Register (GCR, Index B8h) is I/O-mapped because it must be accessed before memory mapping can be enabled. Refer to Section 3.3.2.2 "Configuration Registers" on page 47 for information on how to access this register.

Table 4-1. GCR Register

Bit	Name	Description	
Index B8h		GCR Register (R/W) Default Value = 00h	
7:4	RSVD	Reserved: Set to 0.	
3:2	SP	Scratchpad Size: Specifies the size of the scratchpad cache.  00 = 0 KB  01 = 2 KB  10 = 3 KB  11 = 4 KB	
1:0	GX	GXm Base Address: Specifies the physical address for the base (GX_BASE) of the scratchpad RAM, the graphics memory (frame buffer, compression buffer, etc.) and the other memory mapped registers.  00 = Scratchpad RAM, Graphics Subsystem, and memory-mapped configuration registers are disabled.  01 = Scratchpad RAM and control registers start at GX_BASE = 40000000h.  10 = Scratchpad RAM and control registers start at GX_BASE = 80000000h.  11 = Scratchpad RAM and control registers start at GX_BASE = C0000000h.	




Figure 4-2. Geode™ GXm Processor Memory Space

#### 4.1.2 Control Registers

The control registers for the GXm processor use 32 KB of the memory map, starting at GX\_BASE+8000h (see Figure 4-2 on page 93). This area is divided into internal bus interface unit, graphics pipeline, display controller, memory controller, and power management sections:

- The internal bus interface unit maps 100h locations starting at GX\_BASE+8000h.
- The graphics pipeline maps 200h locations starting at GX BASE+8100h.
- The display controller maps 100h locations starting at GX BASE+8300h.
- The memory controller maps 100h locations starting at GX\_BASE+8400h
- GX\_BASE+8500h-8FFFh is dedicated to power management registers for the serial packet transmission control, the user-defined power management address space, Suspend Refresh, and SMI status for Suspend/Resume.

The register descriptions are contained in the individual subsections of this chapter. Accesses to undefined registers in the GXm processor control register space will not cause a hardware error.

#### 4.1.3 Graphics Memory

The GXm processor's graphics memory is mapped into 8 MB starting at GX\_BASE+80000h. This area includes the frame buffer memory and storage for internal display controller state. The frame buffer is a linear map whose size depends on the current resolution setup in the memory controller. Frame buffer scan lines are not contiguous in many resolutions, so software that renders to the frame buffer must use a skip count to advance between scan lines. The display controller uses the graphics memory that lies between scan lines for internal state. For this reason, accessing graphics memory between the end of a scan line and the start of another can cause display problems. The skip count for all supported resolutions is shown in Table 4-2.

Graphics memory is allocated from system DRAM by the system BIOS. The graphics memory size is programmed by setting the graphics memory base address in the memory controller. Display drivers communicate with system BIOS about resolution changes, to ensure that the correct amount of graphics memory is allocated. When a graphics resolution change requires an increased amount of graphics memory, the system must be rebooted! The reason for this restriction is that no mechanism exists to recover system DRAM from the operating system without rebooting.

**Table 4-2. Display Resolution Skip Counts** 

Screen Resolution	Pixel Depth	Skip Count
640x480	8 bits	1024
640x480	16 bits	2048
800x600	8 bits	1024
800x600	16 bits	2048
1024x768	8 bits	1024
1024x768	16 bits	2048

### 4.1.4 L1 Cache Controller

The GXm processor contains an on-board 16 KB unified data/instruction L1 cache. It operates in write-back mode. Since the memory controller is also on-board, the L1 cache requires no external logic to maintain coherency. All DMA cycles automatically snoop the L1 cache. For improved graphics performance, part of the L1 cache operates as a scratchpad RAM to be used by the graphics pipeline as a BLT Buffer.

The CD bit (Cache Disable, bit 30) in CR0 globally controls the operating mode of the L1 cache. LCD and LWT, Local Cache Disable and Local Write-through bits in the Translation Lookaside Buffer, control the mode on a page-by-page basis. Additionally, memory configuration control can specify certain memory regions as non-cacheable.

If the cache is disabled, no further cache line fills occur. However, data already present in the cache continues to be used. For the cache to be completely disabled, the cache must be invalidated with a WBINVD instruction after the cache has been disabled.

Write-back caching improves performance by relieving congestion on slower external buses. With four dirty bits, the cache marks dirty locations on a double-word basis. This further reduces the number of double-word bus write

operations needed during a replacement or flush operation.

The GXm processor will cache SMM regions. This speeds up system management overhead to allow for hardware emulation such as VGA.

The cache of the GXm processor provides the ability to redefine 2 KB, 3 KB, or 4 KB of the L1 cache to be scratchpad memory. The scratchpad area is memory mapped to the upper memory region defined by the GCR register (Index B8h). The valid bits for the scratchpad RAM will always be true and the scratchpad RAM locations will never be flushed to memory. The scratchpad RAM serves as a general purpose high speed RAM and as a BLT buffer for the graphics pipeline. Incrementing BLT buffer address registers have been added to enable the graphics pipeline to access this memory as a BLT buffer. A 16-byte line buffer dedicated to the graphics pipeline accesses has been added to minimize graphics interference with normal CPU operation.

Table 4-3 summarizes the registers contained in the L1 cache. These registers do not have default values and must be initialized before use. Table 4-4 on page 96 gives the register/bit formats.

Table 4-3. L1 Cache BitBLT Register Summary

Mnemonic Name	Function	
L1_BB0_BASE L1 Cache BitBLT 0 Base Address	Contains the address offset to the first byte of BLT Buffer 0 in the scratch-pad memory.	
L1_BB0_POINTER L1 Cache BitBLT 0 Pointer	Contains the address offset to the current line of BLT Buffer 0 in the scratchpad memory.	
L1_BB1_BASE L1 Cache BitBLT 1 Base Address	Contains the offset to the first byte of BLT Buffer 1 in the scratchpad memory.	
L1_BB1_POINTER L1 Cache BitBLT 1 Pointer	Contains the address offset to the current line of BLT Buffer 1 in the scratchpad memory.	
Nets: For information on accessing these registers refer to Section 4.4.6 "CDLL DEAD/CDLL WIDIT Instructions"		

**Note:** For information on accessing these registers, refer to Section 4.1.6 "CPU\_READ/CPU\_WRITE Instructions" on page 99.

# Table 4-4. L1 Cache BitBLT Registers

Bit	Name	Description	
		L1_BB0_BASE Register (R/W)	Default Value = None
15:12	RSVD	Reserved: Set to 0.	
11:4	INDEX	BitBLT 0 Base Index: The index to the starting line of BLT Buffer 0.	
3:0	BYTE	BitBLT 0 Starting Byte: Determines which byte of the starting line is the	peginning of BLT Buffer 0.
		L1_BB0_POINTER Register (R/W)	Default Value = None
15:12	RSVD	Reserved: Set to 0.	
11:4	INDEX	BitBLT 0 Pointer Index: The index to the current line of BLT Buffer 0.	
3:0	RSVD	Reserved: Set to 0.	
		L1_BB1_Base Register (R/W)	Default Value = None
15:12	RSVD	Reserved: Set to 0.	
11:4	INDEX	BitBLT 1 Base Index: The index to the starting line of BLT Buffer 1.	
3:0	BYTE	BitBLT 1 Starting Byte: Determines which byte of the starting line is the l	peginning of BLT Buffer 1.
		L1_BB1_POINTER Register (R/W)	Default Value = None
15:12	RSVD	Reserved: Set to 0.	
	INDEV	BitBLT 1 Pointer Index: The index to the current line of BLT Buffer 1.	
11:4	INDEX	BREET TO GIRLET MICEX. THE MICEX TO THE CUITER THE OF BET BUILD TO	

#### 4.1.4.1 Scratchpad Memory

The scratchpad RAM is a dedicated high-speed memory cache that contains BLT buffers, SMM header, and a scratchpad area for display drivers. It provides both L1 cache performance and a dedicated resource that cannot be thrown out by other system activity. The configuration of the scratchpad is based on graphics resolution and is described in Table 4-5.

The scratchpad memory is part of the on-chip L1 cache memory. The memory size is controlled by bits in the GCR register (Index B8h). The scratchpad memory can be disabled, or sized to 2 KB, 3 KB, or 4 KB. The remaining L1 cache size is 16 KB minus the scratchpad size, and all of the scratchpad area is subtracted from a single way.

The scratchpad memory is used by display drivers and virtualization software. Because this resource must be tightly controlled to avoid conflicts, application software and third-party drivers should avoid accesses to the scratchpad area.

The display driver creates and manages two BLT buffers from within the scratchpad area. These BLT buffers are used to transfer source data from system memory into the frame buffer, or for destination data from system memory or the frame buffer. The graphics pipeline accesses the BLT buffers for many common operations, including Bit-BLT transfers, output primitives, and raster text. Display drivers also use a small portion of the scratchpad as an extended register file, since scratchpad read and write accesses are very fast compared to normal memory operations.

The virtualization software uses the scratchpad area to store critical SMM information, including the SMI header and SMM system state. No SMM code currently resides in the scratchpad area, although this is an option for future products.

When the BLT buffer pointer is used (refer to Table 4-8 on page 99) addresses outside the scratchpad range will wrap around back into the scratchpad RAM. Table 4-5 shows the allocation of scratchpad memory for the 2 KB and 3 KB configurations of the scratchpad. The 2 KB configuration uses GX\_BASE+0800h to GX\_BASE+1000h. The 3 KB configuration uses GX\_BASE+0400h to GX\_BASE+1000h. These configurations are fixed by the system BIOS during boot and cannot be changed without rebooting the system.

**Table 4-5. Scratchpad Organization** 

2 KB Configura	tion	3 KB Configura		
Offset	Size	Offset	Size	Description
GX_BASE + 0EE0h	288 bytes	GX_BASE + 0EE0h	288 bytes	SMM scratchpad
GX_BASE + 0E60h	128 bytes	GX_BASE + 0E60h	128 bytes	Driver scratchpad
GX_BASE + 0B30h	816 bytes	GX_BASE + 0930h	1328 bytes	BLT Buffer 0
GX_BASE + 0800h	816 bytes	GX_BASE + 0400h	1328 bytes	BLT Buffer 1

### 4.1.5 Display Driver Instructions

The GXm processor has four instructions to access processor core registers. Table 4-6 shows these instructions.

Adding CPU instructions does not create a compatibility problem for applications that may depend on receiving illegal opcode traps. The solution is to make these instructions generate an illegal opcode trap unless a compatibility bit is explicitly set. The GXm processor uses the scratchpad size field (bits [3:2] in GCR, Index B8h) to

enable or disable all of the graphics instructions. If the scratchpad size bits are zero, meaning that none of the cache is defined as scratchpad, then hardware will assume that the graphics controller is not being used and the graphics instructions will be disabled. Any other scratchpad size will enable all of the new instructions. Note that the base address of the memory map in the GCR register can still be set up to allow access to the memory controller registers.

**Table 4-6. Display Driver Instructions** 

Syntax	Opcode	Description
BB0_RESET	0F3A	Reset the BLT Buffer 0 pointer to the base.
BB1_RESET	0F3B	Reset the BLT Buffer 1 pointer to the base.
CPU_WRITE	0F3C	Write data to CPU internal register.
CPU_READ	0F3D	Read data from CPU internal register.

### 4.1.6 CPU\_READ/CPU\_WRITE Instructions

The GXm processor has several internal registers that control the BLT buffer and power management circuitry in the dedicated cache subsystem. To avoid adding additional instructions to read and write these registers, the GXm processor has a general mechanism to access internal CPU registers with reasonable performance. The GXm processor has two special instructions to read and write CPU registers: CPU\_READ and CPU\_WRITE. Both instructions fetch a 32-bit register address from *EBX* as shown in Table 4-7 and Table 4-8. CPU\_WRITE uses *EAX* for the source data, and CPU\_READ uses *EAX* as the

destination. Both instructions always transfer 32 bits of data.

These instructions work by initiating a special I/O transaction where the high address bit is set. This provides a very large address space for internal CPU registers.

The BLT buffer base registers define the starting physical addresses of the BLT buffers located within the dedicated L1 cache. The dedicated cache can be configured for up to 4 KB, so 12 address bits are required for each base address.

Table 4-7. CPU-Access Instructions

Syntax	Opcode	Registers	Length
CPU_WRITE	0F3Ch	EBX = 32-bit address, EAX = Source	2 bytes
CPU_READ	0F3Dh	EBX = 32-bit address, EAX = Destination	2 bytes

Table 4-8. Address Map for CPU-Access Registers

Register	EBX Address	Description
L1_BB0_BASE	FFFFF0Ch	BLT Buffer 0 base address (see Table 4-4 on page 96).
L1_BB1_BASE	FFFFFF1Ch	BLT Buffer 1 base address (see Table 4-4 on page 96).
L1_BB0_POINTER	FFFFFF2Ch	BLT Buffer 0 pointer address (see Table 4-4 on page 96).
L1_BB1_POINTER	FFFFF3Ch	BLT Buffer 1 pointer address (see Table 4-4 on page 96).
PM_BASE	FFFFF6Ch	Power management base address (see Table 6-3 on page 181).
PM_MASK	FFFFFF7Ch	Power management address mask (see Table 6-3 on page 181).

#### 4.2 INTERNAL BUS INTERFACE UNIT

The Geode GXm processor's internal bus interface unit provides control and interface functions to the internal C-Bus (processor core, FPU, graphics pipeline, and L1 cache) and X-Bus (PCI controller, display controller, memory controller, and graphics accelerator) paths, provides control for several sections of memory, and plays an important part in the virtual VGA function.

The internal bus interface unit performs, without loss of compatibility, the functions that previously required the external pins IGNNE# and A20M#.

The internal bus interface unit provides configuration control for up to 20 different regions within system memory. It provides 19 configurable memory regions in the address space between 640 KB and 1 MB, with separate control for read access, write access, cacheability, and PCI access.

The memory configuration control includes a top-of-memory register and hardware support for VGA emulation plus, the capability to program 20 regions of the memory map for different ROM configurations, and to locate memory-mapped I/O.

### 4.2.1 FPU Error Support

The FERR# (floating point error) and IGNNE# (ignore numeric error) pins of the 486 microprocessor have been replaced with an IRQ13 (interrupt request 13) pin. In DOS systems, FPU errors are reported by the external vector 13. This mode of operation is specified by clearing the NE bit (bit 5) in the CR0 register. If the NE bit is active, the IRQ13 output of the GXm processor is always driven inactive. If the NE bit is cleared, the GXm processor drives IRQ13 active when the ES bit (bit 7) in the FPU Status Register is set high. Software must respond to this interrupt with an OUT instruction of an 8-bit operand to F0h or F1h. When the OUT cycle occurs, the IRQ13 pin is driven inactive and the FPU starts ignoring numeric errors. When the ES bit is cleared, the FPU resumes monitoring numeric errors.

### 4.2.2 A20M Support

The GXm processor provides an A20M bit in the BC\_XMAP\_1 Register (GX\_BASE+ 8004h[21]) to replace the A20M# pin on the 486 microprocessor. When the A20M bit is set high, all non-SMI accesses will have address bit 20 forced to zero. External hardware must do an SMI trap on I/O locations that toggle the A20M# pin. The SMI software can then change the A20M bit as desired.

This maintains compatibility with software that depends on wrapping the address at bit 20.

### 4.2.3 SMI Generation

The internal bus interface unit can generate SMI interrupts whenever an I/O cycle in the VGA address range is 3B0h-3BFh and 3C0h-3CFh. An I/O cycle to 3D0h-3DFh can be trapped. In case an external VGA card is present, the Internal Bus Interface Unit default values will not generate an interrupt on VGA accesses. (Refer to Section 5.2.3.1 "SMI Generation" on page 168 for instructions on how to configure the registers to generate the SMI interrupt.)

### 4.2.4 640 KB to 1 MB Region

There are 19 configurable memory regions located between 640 KB and 1 MB. Three of the regions are A0000h-AFFFFh, B0000h-B7FFFh, and B8000h-BFFFFh. The area between C0000h and FFFFFh is divided into 16 KB segments to form the remaining 16 regions. Each of these regions has four control bits to allow any combination of read-access, write-access, cache, and PCI-access capabilities (Table 4-11 on page 102).

In addition, each of the three regions defined in the A0000h-BFFFh area of memory has a VGA control bit that can cause the graphics pipeline to handle accesses to that section of memory (see Table 5-3 on page 170).

### 4.2.5 Internal Bus Interface Unit Registers

The Internal Bus Interface Unit maps 100h locations starting at GX\_BASE+8000h. Refer to Section 4.1.2 "Control Registers" on page 94 for instructions on accessing these registers.

Table 4-9 summarizes the four 32-bit registers contained in the Internal Bus Interface Unit and Table 4-10 gives the register/bit formats.

Table 4-9. Internal Bus Interface Unit Register Summary

GX_BASE+ Memory Offset	Туре	Name/Function	Default Value
8000h-8003h	R/W	BC_DRAM_TOP	3FFFFFFFh
		Top of DRAM: Contains the highest available address of system memory not including the memory that is set aside for graphics memory, which corresponds to 1 GByte of memory. The largest possible value for the register is 3FFFFFFFh.	
8004h-8007h	R/W	BC_XMAP_1	00000000h
		Memory X-Bus Map Register 1 (A and B Region Control: Contains the region control of the A and B regions and the SMI controls required for VGA emulation. PCI access to internal registers and the A20M function are also controlled by this register.	
8008h-800Bh	R/W	BC_XMAP_2	00000000h
		Memory X-Bus Map Register 2 (C and D Region Control): Contains region control fields for eight regions in the address range C0h through DCh.	
800Ch-800Fh	R/W	BC_XMAP_3	00000000h
		Memory X-Bus Map Register 3 (E and F Region Control): Contains the region control fields for memory regions in the address range E0h through FCh.	

Table 4-10. Internal Bus Interface Unit Registers

Bit	Name	Description	
GX_BASE+8000h-8003h		BC_DRAM_TOP Register (R/W)	Default Value = 3FFFFFFFh
31:30	RSVD	Reserved: Set to 0.	
29:17	TOP OF DRAM	Top of DRAM: Maximum value is FFFh.	
16:0	1FFFF	Granularity: Must be set to 1FFFFh (128 KB).	
GX_BASE	+8004h-8007h	BC_XMAP_1 Register (R/W)	Default Value = 00000000h
31:29	RSVD	Reserved: Set to 0.	
28	GEB8	<b>Graphics Enable for B8 Region:</b> Allow memory R/W operations for address range B8000h-BFFFFh b directed to the graphics pipeline: 0 = Disable; 1 = Enable.  (Used for VGA emulation.)	
27:24	B8	<b>B8 Region:</b> Region control field for address range B8000h-BFFF	Fh.
		Note: Refer to Table 4-11 for decode.	
23	RSVD	Reserved: Set to 0.	
22	PRAE	<b>PCI Register Access Enable:</b> Allow PCI Slave to access internal registers on the X-Bus: 0 = Disable; 1 = Enable.	
21	A20M	Address Bit 20 Mask: Address bit 20 is always forced to a zero except for SMI accesses: 0 = Disable; 1 = Enable.	
20	GEB0	<b>Graphics Enable for B0 Region:</b> Allow memory R/W operations for address range B0000h-B7FFFh directed to the graphics pipeline: 0 = Disable; 1 = Enable.  (Used for VGA emulation.)	
19:16	В0	<b>B0 Region:</b> Region control field for address range B0000h-B7FF <b>Note:</b> Refer to Table 4-11 for decode.	Fh.
15	SMID	<b>SMID:</b> All I/O accesses for address range 3D0h-3DFh generate an SMI: 0 = Disable; 1 = Enable. (Used for VGA virtualization.)	
14	SMIC	SMIC: All I/O accesses for address range 3C0h-3CFh generate an SMI: 0 = Disable; 1 = Enable. (Used for VGA virtualization.)	
13	SMIB	SMIB: All I/O accesses for address range 3B0h-3BFh generate a (Used for VGA virtualization.)	an SMI: 0 = Disable; 1 = Enable

Table 4-10. Internal Bus Interface Unit Registers (Continued)

Bit	Name	Description	
12:8	RSVD	Reserved: Set to 0.	
7	XPD	X-Bus Pipeline Disable: When cleared, the address for the next cycle Bus before the completion of the data phase of the current cycle.	can be driven on the internal X-
6	GNWS	X-Bus Graphics Pipe No Wait State: Data driven on X-Bus from graph 0 = 1 full clock before X_DSX is asserted 1 = On the same clock in which X_RDY is asserted	hics pipeline:
5	XNWS	X-Bus No Wait State: Data driven on X-Bus from Internal Bus Interface 0 = 1 full clock before X_DSX is asserted 1 = On the same clock in which X_RDY is asserted	e Unit:
4	GEA	<b>Graphics Enable for A Region:</b> Memory R/W operations for address r directed to the graphics pipeline: 0 = Disable; 1 = Enable. (Used for VGA emulation.)	ange A0000h-AFFFFh are
3:0	A0	A0 Region: Region control field for address range A0000h-AFFFFh.	
		Note: Refer to Table 4-11 for decode.	
GX_BASE	+8008h-800Bh	BC_XMAP_2 Register (R/W)	Default Value = 00000000h
31:28	DC	DC Region: Region control field for address range DC000h to DFFFFh	l.
27:24	D8	D8 Region: Region control field for address range D8000h to DBFFFh.	
23:20	D4	D4 Region: Region control field for address range D4000h to D7FFFh.	
19:16	D0	<b>D0 Region:</b> Region control field for address range D0000h to D3FFFh.	
15:12	CC	CC Region: Region control field for address range CC000h to CFFFh	
11:8	C8	C8 Region: Region control field for address range C8000h to CBFFF.	
7:4	C4	C4 Region: Region control field for address range C4000h to C7FFFh.	
3:0	C0	C0 Region: Region control field for address range C0000h to C3FFFh.	
Note: Ref	er to Table 4-11 f	or decode.	
GX_BASE	+800Ch-800Fh	BC_XMAP_3 Register (R/W)	Default Value = 00000000h
31:28	FC	FC Region: Region control field for address range FC000h to FFFFFh.	
27:24	F8	F8 Region: Region control field for address range F8000h to FBFFFh.	
23:20	F4	<b>F4 Region:</b> Region control field for address range F4000h to F7FFFh.	
19:16	F0	<b>F0 Region:</b> Region control field for address range F0000h to F3FFFh.	
15:12	EC	EC Region: Region control field for address range EC000h to EFFFFh.	
11:8	E8	E8 Region: Region control field for address range E8000h to EBFFFh.	
7:4	E4	<b>E4 Region:</b> Region control field for address range E4000h to E7FFFh.	
3:0	E0	<b>E0 Region:</b> Region control field for address range E0000h to E3FFFh.	
Nata Dat	er to Table 4-11 f	or decode	
Note: Ref	el lo lable 4-11 l	or accode.	

Table 4-11. Region-Control-Field Bit Definitions

Bit Position	Function
3	<b>PCI Accessible:</b> The PCI slave can access this memory if this bit is set high and if the appropriate Read or Write Enable bit is also set high.
2	Cache Enable: Caching this region of memory is inhibited if this bit is cleared.
1	<b>Write Enable:</b> Write operations to this region of memory are allowed if this bit is set high. If this bit is cleared, then write operations in this region are directed to the PCI master.
0	<b>Read Enable:</b> Read operations to this region of memory are allowed if this bit is set high. If this bit is cleared then read operations in this region are directed to the PCI master.

Note: If Cache Enable = 1 and Write Enable = 1, the Write Enable determination occurs after the data has passed the cache. Since the cache does write update, write data will change the cache if the address is cached. If a read then occurs to that address, the data will come from the written data that is in the cache even though the address is not writable. If this must be avoided then do not make the region cacheable.

#### 4.3 MEMORY CONTROLLER

The memory controller operates with the Processor Interface (X-Bus), Display Controller Interface, Graphics Pipeline Interface, and the SDRAM Interface.

The GXm processor supports LVTTL (low voltage TTL) technology. LVTTL technology allows the SDRAM interface of the memory controller to run at frequencies up to 100 MHz.

The SDRAM clock is a function of the core clock. The SDRAM bus can be run at speeds that range between 66

MHz and 100 MHz. The core clock can be divided down from two to five in half clock increments to generate the SDRAM clock. SDRAM frequencies between 79 MHz and 100 MHz are only supported for certain types of closed systems and strict design rules must be adhered to. For further details, please contact your local National Semiconductor technical support representative.

A basic block diagram of the memory controller is shown in Figure 4-3.




Figure 4-3. Memory Controller Block Diagram

### 4.3.1 Memory Array Configuration

The memory controller supports up to two 64-bit, 168-pin unbuffered SDRAM modules (DIMM). Each DIMM receives a unique set of RAS, CAS, WE, and CKE lines. Each DIMM can have one or two 64-bit DIMM banks. Each DIMM bank is selected by a unique chip select (CS). There are four chip select signals to choose between a total of four DIMM banks. Each DIMM bank also receives a unique SDCLK. Each DIMM bank can have two or four

component banks. Component bank selection is done through the bank address (BA) lines.

For example, 16 Mb SDRAMS have two component banks and 64 Mb SDRAMs have two or four component banks. For single DIMM bank modules, the memory controller can support two DIMMS with a maximum of eight component banks. For dual DIMM bank modules, the memory controller can support two DIMMs with a maximum of 16 component banks. Up to 16 banks can be open at the same time.




Figure 4-4. Memory Array Configuration

### 4.3.2 Memory Organizations

The memory controller supports JEDEC standard synchronous DRAMs in 16 Mb and 64 Mb configurations. Supported configurations are shown in Table 4-12.

Table 4-12. Synchronous DRAM Configurations

Depth	Organization	Row Address	Column Address	Bank Address	Total # of Address bits
1	1 Mx16	A10-A0	A7-A0	BA0	20
2	2 Mx8	A10-A0	A8-A0	BA0	21
	2 Mx32	A10-A0	A7-A0	BA1-BA0	21
	2 Mx32	A10-A0	A8-A0	BA0	21
	2 Mx32	A11-A0	A6-A0	BA1-BA0	21
	2 Mx32	A12-A0	A6-A0	BA0	21
4	4 Mx4	A10-A0	A9-A0	BA0	22
	4 Mx16	A11-A0	A7-A0	BA1-BA0	22
	4 Mx16	A12-A0	A7-A0	BA0	22
	4 Mx16	A10-A0	A9-A0	BA0	22
8	8 Mx8	A11-A0	A8-A0	BA1-BA0	23
	8 Mx8	A12-A0	A8-A0	BA0	23
	8 Mx32	A11-A0	A8-A0	BA1-BA0	23
	8 Mx32	A12-A0	A7-A0	BA1-BA0	23
16	16 Mx4	A11-A0	A9-A0	BA1-BA0	24
	16 Mx4	A12-A0	A9-A0	BA0	24
	16 Mx16	A12-A0	A8-A0	BA1-BA0	24
	16 Mx16	A11-A0	A9-A0	BA1-BA0	24
32	32 Mx8	A12-A0	A9-A0	BA1-BA0	25
64	64 Mx4	A12-A0	A9-A0,A11	BA1-BA0	26

### 4.3.3 SDRAM Commands

This subsection discusses the SDRAM commands supported by the memory controller. Table 4-13 summarizes these commands followed by detailed operational information regarding each command.

Table 4-13. Basic Command Truth Table

Name	Command	cs	RAS	CAS	WE
MRS	Mode Register Set	L	L	L	L
PRE	Bank Precharge	L	L	Н	L
ACT	Bank activate/row- address entry	L	L	Н	Η
WRT	Column address entry/Write operation	L	Н	L	L
READ	Column address entry/Read operation	L	Н	L	Н
DESL	Control input inhibit/ No operation	Н	Х	Х	Х
REFR*	CBR Refresh or Auto Refresh	L	L	L	Н

Note: \*This command is CBR (CAS-before-RAS) refresh when CKE is high and self refresh when CKE is low.

MRS — The Mode Register command defines the specific mode of operation of the SDRAM. This definition includes the selection of burst length, burst type, and CAS latency. CAS latency is the delay, in clock cycles, between the registration of a read command and the availability of the first piece of output data.

The burst length is programmed by address bits MA[2:0], the burst type by address bit MA3 and the CAS latency by address bits MA[6:4].

The memory controller only supports a burst length of two and burst type of interleave.

The field value on MA[12:0] and BA[1:0] during the MRS cycle are as shown in Table 4-14.

**PRE** — The precharge command is used to deactivate the open row in a particular bank or the open row in both component banks. Address pin MA10 determines whether one or both banks are to be precharged. In the case where only one component bank is to be precharged, BA[1:0] selects which bank. Once a bank has been precharged, it is in the Idle state and must be activated prior to any read or write commands.

Table 4-14. Address Line Programming during MRS Cycles

BA[1:0]	MA[12:7]	MA[6:4]	MA3	MA2	MA1	MA0
00	000000	CAS Latency: 000 = Reserved 010 = 2 CLK 100 = 4 CLK 110 = 6 CLK 001 = 1 CLK 011 = 3 CLK 101 = 5 CLK 111 = 7 CLK	1	0	0	1

**ACT** — The activate command is used to open a row in a particular bank for a subsequent access. The value on the BA lines selects the bank, and the address on the MA lines selects the row. This row remains open for accesses until a precharge command is issued to that bank. A precharge command must be issued before opening a different row in the same bank.

**READ** — The read command is used to initiate a burst read access to an active row. The value on the BA lines select the component bank, and the address provided by the MA lines select the starting column location. The memory controller does not perform auto precharge during read operations. Valid data-out from the starting column address is available following the CAS latency after the read command. The DQM signals are asserted low during read operations.

WRT — The write command is used to initiate a burst write access to an active row. The value on the BA liens select the component bank, and the address provided by the MA lines select the starting column location. The memory controller does not perform auto precharge during write operations. This leaves the page open for subsequent accesses. Data appearing on the MD lines is written to the DQM logic level appearing coincident with the data. If the DQM signal is registered low, the corresponding data will be written to memory. If the DQM is driven high, the corresponding data will be ignored, and a write will not be executed to that location.

REF — Auto refresh is used during normal operation and is analogous to the CAS-before-RAS (CBR) refresh in conventional DRAMs.During auto refresh the address bits are "don't care". The memory controller precharges all banks prior to an auto refresh cycle. Auto refresh cycles are issued approximately 15 µs apart.

The self refresh command is used to retain data in the SDRAMs even when the rest of the system is powered down. The self refresh command is similar to an auto refresh command except CKE is disabled (low). The memory controller issues a self refresh command during 3V Suspend mode when all the internal clocks are stopped.

#### 4.3.3.1 SDRAM Initialization Sequence

After the clocks have started and stabilized, the memory controller SDRAM initialization sequence begins:

- 1) Precharge all component banks
- 2) Perform eight refresh cycles
- 3) Perform an MRS cycle
- 4) Perform eight refresh cycles

This sequence is compatible with the majority of SDRAMs available from the various vendors.

### 4.3.4 Memory Controller Register Description

The Memory Controller maps 100h locations starting at GX\_BASE+8400h. Refer to Section 4.1.2 "Control Registers" on page 94 for instructions on accessing these registers.

Table 4-15 summarizes the 32-bit registers contained in the memory controller. Table 4-16 gives detailed register/bit formats.

Table 4-15. Memory Controller Register Summary

GX_BASE+ Memory Offset	Туре	Name/Function	Default Value
8400h-8403h	R/W	MC_MEM_CNTRL1	248C0040h
		Memory Controller Control Register 1: Memory controller configuration information e.g., refresh interval, SDCLK ratio, etc.	
8404h-8407h	R/W	MC_MEM_CNTRL2	00000801h
		Memory Controller Control Register 2: Memory controller configuration information to control SDCLK.	
8408h-840Bh	R/W	MC_BANK_CFG	41104110h
		Memory Controller Bank Configuration: Contains the configuration information for the each of the two DIMMs in the memory array. BIOS programs this register during boot by running an autosizing routine on the memory.	
840Ch-840Fh	R/W	MC_SYNC_TIM1	2A733225h
		Memory Controller Synchronous Timing Register 1: SDRAM memory timing information - This register controls the memory timing of all four banks of DRAM. BIOS programs this register based on the processor frequency and the SDCLK divide ratio.	
8414h-8417h	R/W	MC_GBASE_ADD	00000000h
		Memory Controller Graphics Base Address Register: This register sets the graphics memory base address, which is programmable on 512 KB boundaries. The display controller and the graphics pipeline generate a 20-bit DWORD offset that is added to the graphics memory base address to form the physical memory address. Typically, the graphics memory region is located at the top of physical memory.	
8418h-841Bh	R/W	MC_DR_ADD	00000000h
		Memory Controller Dirty RAM Address Register: This register is used to set the Dirty RAM address index for processor diagnostic access. This register should be initialized before accessing the MC_DR_ACC register	
841Ch-841Fh	R/W	MC_DR_ACC	0000000xh
		Memory Controller Dirty RAM Access Register: This register is used to access the Dirty RAM. A read/write to this register will access the Dirty RAM at the address specified in the MC_DR_ADD register.	

**Table 4-16. Memory Controller Registers** 

Bit	Name	Description	
GX_BASE+ 8400h-8403h		MC_MEM_CNTRL1 (R/W)	Default Value = 248C0040h
31:29	MDHDCTL	MD High Drive Control: Controls the high drive and slew rate of the m 000 = Tristate 001 = Smallest drive strength 010 -110 = Represents gradual drive strength increase 111 = Highest drive strength	emory data bus (MD[63:0]):
28:26	MABAHDCTL	MA/BA High Drive Control: Controls the high drive and slew rate of the ing the memory bank address bus (MA[12:0] and BA[1:0]):  000 = Tristate 001 = Smallest drive strength 010 -110 = Represents gradual drive strength increase 111 = Highest drive strength	e memory address bus includ-

Table 4-16. Memory Controller Registers (Continued)

Bit	Name	Description
25:23	MEMHDCTL	Control High Drive/Slew Control: Controls the high drive and slew rate of the memory control signals (CASA#, CASB#, RASA#, RASB#, CKEA, CKEB, WEA#, WEA#, DQM[7:0], and CS[3:0]#):
		000 = Tristate
		001 = Smallest drive strength 010 -110 = Represents gradual drive strength increase
		111 = Highest drive strength
22	RSVD	Reserved: Set to 0.
21	RSVD	Reserved: Must be set to 0. Wait state on the X-Bus x_data during read cycles - for debug only.
20:18	SDCLKRATE	SDRAM Clock Ratio: Selects SDRAM clock ratio:
		$000 = Reserved   100 = \div 3.5$
		$     \begin{array}{r}       001 = \div 2 \\       010 = \div 2.5     \end{array} $ $     \begin{array}{r}       101 = \div 4 \\       110 = \div 4.5     \end{array} $
		$0.010 = \div 2.5$ $0.011 = \div 3$ (Default) $0.011 = \div 5$
		Ratio does not take effect until the SDCLKSTRT bit (bit 17 of this register) transitions from 0 to 1.
17	SDCLKSTRT	Start SDCLK: Start operating SDCLK using the new ratio and shift value (selected in bits [20:18] of
	OBOLINOTHI	this register): 0 = Clear; 1 = Enable.
		This bit should be cleared every time before a one is written to it in order to start SDCLK or to change the shift value.
16:8	RFSHRATE	<b>Refresh Interval:</b> This field determines the number of processor core clocks multiplied by 64 between refresh cycles to the DRAM. By default, the refresh interval is 00h. This implies that refresh is turned off by default.
7:6	RFSHSTAG	Refresh Staggering: This field determines number of clocks between REF commands to different banks during refresh cycles:
		00 = 0 SDRAM clocks 10 = 2 SDRAM clocks
		01 = 1 SDRAM clocks (Default)  11 = 4 SDRAM clocks  Staggering in used to help reduce power spikes during refresh. When only DIMMO is installed and it
		Staggering is used to help reduce power spikes during refresh. When only DIMM0 is installed and it has only one DIMM bank, then this field must be set to 00.
5	2CLKADDR	<b>Two Clock Address Setup:</b> Assert memory address for one extra clock before CS# is asserted: 0 = Disable; 1 = Enable.
		This can be used to compensate for address setup at high frequencies.
4	RFSHTST	<b>Test Refresh:</b> This bit, when set high, generates a refresh request. This bit is only used for testing purposes.
3	XBUSARB	<b>X-Bus Round Robin:</b> When enabled, processor requests are arbitrated at the same priority level than graphics pipeline requests and non-critical display controller requests. When disabled, processor requests are arbitrated at a higher priority level. High priority display controller requests always have the highest arbitration priority: 0 = Enable; 1 = Disable.
2	VGAWRP	VGA Wrap Enable: Allow memory wrapping into the VGA memory address space from A0000h to BFFFFh: 0 = Disable; 1 = Enable.
1	RSVD	Reserved: Set to 0.
0	SDRAMPRG	<b>Program SDRAM:</b> When this bit is set the memory controller will program the SDRAM MRS register using LTMODE in MC_SYNC_TIM1.
		This bit should be cleared every time before a one is written to it in order to program the SDRAM.
GX_BASE	+8404h-8407h	MC_MEM_CNTRL2 (R/W) Default Value = 00000801h
31:18	RSVD	Reserved: Set to 0.
17:16	SDCLKRISE	SDCLK Rising Delay: Controls the delay between the core clock and the rising edge of SDCLK during all modes. (Set by BIOS.)
15:14	SDCLKFALL	SDCLK Falling Delay: Controls the delay between the core clock and the falling edge of SDCLK during 2.5 and 3.5 clock modes. (Set by BIOS.)
13:11	SDCLKHDCTL	SDCLK High Drive/Slew Control: Controls the high drive and slew rate of SDCLK[3:0] and SDCLK_OUT.
		000 = Highest drive strength. (No braking applied in the pads)
		001 = Smallest drive strength
		010 -110 = Represent gradual drive strength increase 111 = Highest drive strength
10	SDCLKOMSK	Mask SDCLK_OUT: 0 = Not masked; 1 = Mask.
	1	- · · · · · · · · · · · · · · · · · · ·

Table 4-16. Memory Controller Registers (Continued)

Bit	Name	Description					
9	SDCLK3MSK	Mask SDCLK3: 0 = Not masked; 1 = Mask.					
8	SDCLK2MSK	Mask SDCLK2: 0 = Not masked; 1 = Mask					
7	SDCLK1MSK	Mask SDCLK1: 0 = Not masked; 1 = Mask.					
6	SDCLK0MSK	Mask SDCLK0: 0 = Not masked; 1 = Mask					
5:3	SHFTSDCLK	Shift SDCLK: This function allows shifting SDCLK to meet SDRAM setup and hold time requirements. The shift function will not take effect until the SDCLKSTRT bit (bit 17 of MC_MEM_CNTRL1) transitions from 0 to 1:  000 = No shift					
2	RSVD	Reserved: Set to 0.					
1	RD	<b>Read Data Phase:</b> Selects if read data is latched one or two core clock after the rising edge of SDCLK: 0 = 1 core clock; 1 = 2 core clocks.					
0	FSTRDMSK	Fast Read Mask: Do not allow core reads to bypass the request FIFO: 0 = Disable; 1 = Enable.					
GX_BASE-	⊦8408h-840Bh	MC_BANK_CFG (R/W) Default Value = 41104110h					
31	RSVD	Reserved: Set to 0.					
30	DIMM1_ MOD_BNK	<b>DIMM1 Module Banks:</b> Selects the number of module banks per DIMM for DIMM1:  0 = 1 Module bank  1 = 2 Module banks					
29	RSVD	Reserved: Set to 0.					
28	DIMM1_ COMP_BNK	<b>DIMM1 Component Banks:</b> Selects the number of component banks per module bank for DIMM1:  0 = 2 Component banks  1 = 4 Component banks					
27	RSVD	Reserved: Set to 0.					
26:24	DIMM1_SZ	DIMM1 Size: Selects the size of DIMM1:         000 = 4 MB       010 = 16 MB       100 = 64 MB       110 = 256 MB         001 = 8 MB       011 = 32 MB       101 = 128 MB       111 = 512 MB					
23	RSVD	Reserved: Set to 0.					
22:20	DIMM1_PG_SZ	DIMM1 Page Size: Selects the page size of DIMM1:  000 = 1 KB					
19:15	RSVD	Reserved: Set to 0.					
14	DIMM0_ MOD_BNK	<b>DIMM0 Module Banks:</b> Selects number of module banks per DIMM for DIMM0:  0 = 1 Module bank  1 = 2 Module banks					
13	RSVD	Reserved: Set to 0.					
12	DIMM0_ COMP_BNK	<b>DIMM0 Component Banks:</b> Selects the number of component banks per module bank for DIMM0: 0 = 2 Component banks 1 = 4 Component banks					
11	RSVD	Reserved: Set to 0.					
10:8	DIMM0_SZ	DIMM0 Size: Selects the size of DIMM1:         000 = 4 MB       010 = 16 MB       100 = 64 MB       110 = 256 MB         001 = 8 MB       011 = 32 MB       101 = 128 MB       111 = 512 MB					
7	RSVD	001 = 8 MB					
6:4	DIMM0_PG_SZ	DIMM0 Page Size: Selects the page size of DIMM0:					
0.4	DIIVIIVIO_FG_GC	000 = 1 KB					
	50: 75	When DIMM0 is not installed, program all other DIMM0 fields to 0.					
3:0	RSVD	Reserved: Set to 0.					

Table 4-16. Memory Controller Registers (Continued)

Bit	Name	Description							
GX_BASE+	840Ch-840Fh		MC_SYNC_TI	Default Value = 2A733225h					
31	RSVD	Reserved: Set to	0.						
30:28	LTMODE	command and the	CAS Latency (LTMODE): CAS latency is the delay, in clock cycles, between the registration of a read command and the availability of the first piece of output data (BIOS interrogates EEPROM across the I <sup>2</sup> C interface to determine this value):						
		000 = Reserved 001 = 1 CLK	010 = 2 CLK 011 = 3 CLK	100 = 4 CLK 101 = 5 CLK	110 = 6 CLK 111 = 7 CLK				
				AMPRG (bit 0 of MC ot currently supported	_MEM_CNTRL1) transitions from 0 to 1. d.				
27:24	RC	REF to REF/ACT REF/ACT commar		(tRC): Minimum num	ber of SDRAM clock between REF and				
		0000 = Reserved 0001 = 2 CLK 0010 = 3 CLK 0011 = 4 CLK	0100 = 5 CLK 0101 = 6 CLK 0110 = 7 CLK 0111 = 8 CLK	1000 = 9 CLK 1001 = 10 CLK 1010 = 11 CLK 1011 = 12 CLK	1100 = 13 CLK 1101 = 14 CLK 1110 = 15 CLK 1111 = 16 CLK				
23:20	RAS	ACT to PRE Com commands:	mand Period (tRA	S): Minimum number	of SDRAM clocks between ACT and PRE				
		0000 = Reserved 0001 = 2 CLK 0010 = 3 CLK 0011 = 4 CLK	0100 = 5 CLK 0101 = 6 CLK 0110 = 7 CLK 0111 = 8 CLK	1000 = 9 CLK 1001 = 10 CLK 1010 = 11 CLK 1011 = 12 CLK	1100 = 13 CLK 1101 = 14 CLK 1110 = 15 CLK 1111 = 16 CLK				
19	RSVD	Reserved: Set to	0.						
18:16	RP	PRE to ACT Com commands:  000 = Reserved	` .		of SDRAM clocks between PRE and ACT				
		001 = 1 CLK	010 = 2 CLK 011 = 3 CLK	100 = 4 CLK 101 = 5 CLK	110 = 6 CLK 111 = 7 CLK				
15	RSVD	Reserved: Set to							
14:12	RCD	and READ/WRT c	ommands:		num number of SDRAM clock between AC				
		000 = Reserved 001 = 1 CLK	010 = 2 CLK 011 = 3 CLK	100 = 4 CLK 101 = 5 CLK	110 = 6 CLK 111 = 7 CLK				
11	RSVD	Reserved: Set to							
10:8	RRD	ACT command to ler does not perfor	two different compo m back-to-back Act	onent banks within the civate commands to the	umber of SDRAM clocks between ACT and e same module bank. The memory control wo different component banks without a d should be set to 001.				
7	RSVD	Reserved: Set to	0.						
6:4	DPL		ommand period (tl		per of SDRAM clocks from the time the last				
		000 = Reserved 001 = 1 CLK	010 = 2 CLK 011 = 3 CLK	100 = 4 CLK 101 = 5 CLK	110 = 6 CLK 111 = 7 CLK				
3:0	RSVD	Reserved: Set to	or leave unchang	ed.					
GX_BASE+	8414h-8417h		MC_GBASE_A	ADD (R/W)	Default Value = 000000000				
31:18	RSVD	Reserved: Set to	0.						
17	TE	Test Enable TEST 0 = TEST[3:0] are 1 = TEST[3:0] pins	•	test information					
16	TECTL	Test Enable Shar 0 = RASB#, CASB	ed Control Pins: #, CKEB, WEB# ar		information				
	SEL	Salact: This field i	s used for debug pu	rnoses only					
15:12	SEL	Ocicot. This field i	s asca for acoug po	i poddo orny.					

**Table 4-16. Memory Controller Registers (Continued)** 

Bit	Name	Description				
10:0	GBADD	<b>Graphics Base Address:</b> This field indicates the graphics memory base address, which is programmable on 512 KB boundaries. This field corresponds to address bits [29:19].				
		Note that BC_DRAM_TOP must be set to a value lower than the	e Graphics Base Address.			
GX_BASE	+8418h-841Bh	MC_DR_ADD (R/W)	Default Value = 00000000h			
31:10	RSVD	Reserved: Set to 0.				
9:0	DRADD	<b>Dirty RAM Address:</b> This field is the address index that is used MC_DR_ACC register. This field does not auto increment.	d to access the Dirty RAM with the			
GX_BASE	+841Ch-841Fh	MC_DR_ACC (R/W)	Default Value = 0000000xh			
31:2	RSVD	Reserved: Set to 0.				
1	D	Dirty Bit: This bit is read/write accessible.				
0	V	Valid Bit: This bit is read/write accessible.				

#### 4.3.5 Address Translation

The memory controller supports two address translations depending on the method used to interleave pages.

#### 4.3.5.1 High Order Interleaving

High Order Interleaving (HOI) uses the most significant address bits to select which bank the page is located in. This has the effect of allowing any mixture of DIMM types. However, it spreads the pages over wide address ranges. For example, two 8 MB DIMMs contain a total of four component pages. Two pages are together in one DIMM separated from the other two pages by 8 MB.

### 4.3.5.2 Low Order Interleaving

Low Order Interleaving (LOI) uses the least significant bits after the page bits to select which bank the page is located in. This requires that memory is a power of 2, that the number of banks is a power of 2, and that the page sizes are the same. In other words, the DIMMs have to be of the same type. However, LOI does give a good benefit by providing a moving page throughout memory. Using the same example as above, two banks would be on one DIMM and the next two banks would be on the second DIMM, but they would be linear in address space. For an eight bank system that has 1 KB address (8 KB data) pages, there would be an effective moving page of 64 KB of data.

# 4.3.5.3 Physical Address to DRAM Address Conversion

Auto LOI is in effect whenever the two DIMMs have the same number of DIMM banks, component banks, module sizes and page sizes.

Tables 4-17 and Table 4-18 on page 113 give Auto LOI address conversion examples when two DIMMs of the same size are used in a system. Table 4-17 shows a one DIMM bank conversion example, while Table 4-18 shows a two DIMM bank example.

Table 4-19 and Table 4-20 on page 114 give Non-Auto LOI address conversion examples when either one or two DIMMs of different sizes are used in a system. Table 4-19 shows a one DIMM bank address conversion example, while Table 4-20 shows a two DIMM bank example. The addresses are computed on a per DIMM basis.

Since the DRAM interface is 64 bits wide, the lower three bits of the physical address get mapped onto the DQM[7:0] lines. Thus, the address conversion tables (Tables 4-17 through 4-20) show the physical address starting from A3.

Table 4-17. Auto LOI -- 2 DIMMs, Same Size, 1 DIMM Bank

	1 K Pag	je Size	2 K Pa	ge Size	4 K Pa	ge Size	1 K
	Row	Col	Row	Col	Row	Col	Ro
Address		2	Compon	ent Bank	s	•	
MA12	A24		A25		A26		A2:
MA11	A23		A24		A25		A24
MA10	A22		A23		A24		A23
MA9	A21		A22		A23		A22
MA8	A20		A21		A22	A11	A2
MA7	A19		A20	A10	A21	A10	A20
MA6	A18	A9	A19	A9	A20	A9	A19
MA5	A17	A8	A18	A8	A19	A8	A18
MA4	A16	A7	A17	A7	A18	A7	A1
MA3	A15	A6	A16	A6	A17	A6	A10
MA2	A14	A5	A15	A5	A16	A5	A1:
MA1	A13	A4	A14	A4	A15	A4	A14
MA0	A12	А3	A13	А3	A14	А3	A1:
CS0#/CS1#	A1	1	A	12	Α	13	
CS2#/CS#3		-	-	-	-		
BA0/BA1	A1	0	A	11	А	12	A

1 K Page Size		2 K Pa	ge Size	4 Page Size		
Row	Col	Row	Col	Row	Col	
	4	Compon	ent Bank	s		
A25		A26		A27		
A24		A25		A26		
A23		A24		A25		
A22	A9	A23		A24		
A21	A8	A22		A23	A11	
A20	A7	A21	A10	A22	A10	
A19	A6	A20	A9	A21	A9	
A18	A5	A19	A8	A20	A8	
A17	A4	A18	A7	A19	A7	
A16	А3	A17	A6	A18	A6	
A15	A8	A16	A5	A17	A5	
A14	A7	A15	A4	A16	A4	
A13	A6	A14	А3	A15	А3	
A.	A12		13	A14		
_	-					
A11	/A10	A12	/A11	A13	/A12	

Table 4-18. Auto LOI -- 2 DIMMs, Same Size, 2 DIMM Banks

	1 K Page Size		2 K Page Size		4 K Page Size		
	Row	Col	Row	Col	Row	Col	
Address		2	Compone	ent Bank	 S		
MA12	A25		A26		A27		
MA11	A24		A25		A26		
MA10	A23		A24		A25		
MA9	A22		A23		A24		
MA8	A21		A22		A23	A11	
MA7	A20		A21	A10	A22	A10	
MA6	A19	A9	A20	A9	A21	A9	
MA5	A18	A8	A19	A8	A20	A8	
MA4	A17	A7	A18	A7	A19	A7	
MA3	A16	A6	A17	A6	A18	A6	
MA2	A15	A5	A16	A5	A17	A5	
MA1	A14	A4	A15	A4	A16	A4	
MA0	A13	А3	A14	А3	A15	А3	
CS0#/CS1#	A12		A13		Α	A14	
CS2#/CS3#	A11		A12		A13		
BA0/BA1	A1	0	A <sup>2</sup>	11	A	12	

1 K Page Size		2 Pag	je Size	4 K Pa	4 K Page Size				
Row	Col	Row	Col	Row	Col				
	4 Component Banks								
A26		A27		A28					
A25		A26		A27					
A24		A25		A26					
A23		A24		A25					
A22		A23		A24	A11				
A21		A22	A10	A23	A10				
A20	A9	A21	A9	A22	A9				
A19	A8	A20	A8	A21	A8				
A18	A7	A19	A7	A20	A7				
A17	A6	A18	A6	A19	A6				
A16	A5	A17	A5	A18	A5				
A15	A4	A16	A4	A17	A4				
A14	А3	A15	А3	A16	А3				
А	13	А	14	А	A15				
А	12	A13		A14					
A11	/A10	A12	/A11	A13	A13/A12				

Table 4-19. Non-Auto LOI -- 1 or 2 DIMMs, Different Sizes, 1 DIMM Bank

	1 K Page Size		2 K Pa	2 K Page Size		4 K Page Size	
	Row	Col	Row	Col	Row	Col	
Address		2	Compone	ent Bank	s		
MA12	A23		A24		A25		
MA11	A22		A23		A24		
MA10	A21		A22		A23		
MA9	A20		A21		A22		
MA8	A19		A20		A21	A11	
MA7	A18		A19	A10	A20	A10	
MA6	A17	A9	A18	A9	A19	A9	
MA5	A16	A8	A17	A8	A18	A8	
MA4	A15	A7	A16	A7	A17	A7	
MA3	A14	A6	A15	A6	A16	A6	
MA2	A13	A5	A14	A5	A15	A5	
MA1	A12	A4	A13	A4	A14	A4	
MA0	A11	А3	A12	А3	A13	А3	
CS0#/CS1#		-			-		
CS2#/CS3#							
BA0/BA1	A1	0	A <sup>2</sup>	11	A	12	

1 K Page Size		2 K Pa	ge Size	4 K Page Size					
Row	Col	Row	Col	Row	Col				
	4 Component Banks								
A24		A25		A26					
A23		A24		A25					
A22		A23		A24					
A21		A22		A23					
A20		A21		A22	A11				
A19		A20	A10	A21	A10				
A18	A9	A19	A9	A20	A9				
A17	A8	A18	A8	A19	A8				
A16	A7	A17	A7	A18	A7				
A15	A6	A16	A6	A17	A6				
A14	A5	A15	A5	A16	A5				
A13	A4	A14	A4	A15	A4				
A12	А3	A13	А3	A14 A3					
-			-						
_	-								
A11	/A10	A12	/A11	A13	/A12				

Table 4-20. Non-Auto LOI -- 1 or 2 DIMMs, Different Sizes, 2 DIMM Banks

	1 K Page Size		2 K Page Size		4 K Page Size	
	Row	Col	Row	Col	Row	Col
Address		2	Compone	ent Bank	S	
MA12	A24		A25		A26	
MA11	A23		A24		A25	
MA10	A22		A23		A24	
MA9	A21		A22		A23	
MA8	A20		A21		A22	A11
MA7	A19		A20	A10	A21	A10
MA6	A18	A9	A19	A9	A20	A9
MA5	A17	A8	A18	A8	A19	A8
MA4	A16	A7	A17	A7	A18	A7
MA3	A15	A6	A16	A6	A17	A6
MA2	A14	A5	A15	A5	A16	A5
MA1	A13	A4	A14	A4	A15	A4
MA0	A12	А3	A13	A3	A14	А3
CS0#/CS1#	A1	1	A12		A13	
CS2#/CS3#						
BA0/BA1	A1	0	A <sup>2</sup>	11	А	12

1 K Pag	ge Size	2 K Pa	ge Size	4 K Pa	4 K Page Size		
Row	Col	Row	Col	Row	Col		
	4	Compon	ent Bank	(S			
A25		A26		A27			
A24		A25		A26			
A23		A24		A25			
A22		A23		A24			
A21		A22		A23	A11		
A20		A21	A10	A22	A10		
A19	A9	A20	A9	A21	A9		
A18	A8	A19	A8	A20	A8		
A17	A7	A18	A7	A19	A7		
A16	A6	A17	A6	A18	A6		
A15	A5	A16	A5	A17	A5		
A14	A4	A15	A4	A16	A4		
A13	А3	A14	А3	A15	A3		
A <sup>2</sup>	12	A13		A14			
A11	/A10	A12	/A11	A13	/A12		

## 4.3.6 Memory Cycles

Figures 4-5 through Figure 4-8 on page 117 illustrate various memory cycles that the memory controller supports. The following subsections describe some of the supported cycles.

### **SDRAM Read Cycle**

Figure 4-5 shows a SDRAM read cycle. The figure assumes that a previous ACT command has presented the row address for the read operation. Note that the burst length for the READ command is always two.




Figure 4-5. Basic Read Cycle with a CAS Latency of Two

## **SDRAM Write Cycle**

Figure 4-6 shows a SDRAM write cycle. The burst length for the WRT command is 2.




Figure 4-6. Basic Write Cycle

### **SDRAM Refresh Cycle**

Figure 4-7 shows a SDRAM auto refresh cycle. The memory controller always precedes the refresh cycle with a PRE command to all banks.

## **Page Miss**

Figure 4-8 shows a Read/WRT command after a page miss cycle. In order to program the new row address, a PRE command must be issued followed by an ACT command.




Figure 4-7. Auto Refresh Cycle




Figure 4-8. Read/WRT Command to a New Row Address

## 4.3.7 SDRAM Interface Clocking

The GXm processor drives the SDCLK to the SDRAMs; one for each DIMM bank. All the control, data, and address signals driven by the memory controller are sampled by the SDRAM at the rising edge of SDCLK. SDCLK-OUT is a reference signal used to generate SDCLKIN. Read data is sampled by the memory controller at the rising edge of SDCLKIN.

The delay for SDCLKIN must be designed so that it lags the SDCLKs at the DRAM by approximately 2ns. The delay should also include the SDCLK transmission line delay. The SDCLK traces on the board need to be laid out so there is no skew between each of the four sinks. These guidelines allow the memory interface to be closer to the DRAM specifications. They improve performance by running the SDCLK up to frequencies of 100 MHz and a CAS latency of two.





Figure 4-9. SDCLKIN Clocking

The SDRAM interface timings are programmable. The SHFTSDCLK bits in the MC\_MEM\_CNTRL2 register can be used to change the relationship between SDCLK and the control/address/data signals. To meet setup and hold time requirements for SDRAM across different board layouts, the SHFTSDCLK bits are used. SHFTSDCLK bit values are selected based upon the SDRAM signals loads and the core frequency (refer to Table 7-10 on page 190).

Figure 4-10 shows an example of how the SHFTSDCLK bits setting affects SDCLK. The PCI clock is the input clock to the GXm processor. The core clock is the internal processor clock that is multiplied up. The memory control-

ler runs off this processor clock. The memory clock is generated by dividing down the processor clock. SDCLK is generated from the memory clock. In the example diagram, the processor clock is running 6X times the PCI clock and the memory clock is running in divide by 3 mode.

The SDRAM control, address, and data signals are driven off edge "x" of the memory clock to be setup before edge "y". With no shift applied, the control signals could end up being latched on edge "x". A shift value of two or three could be used so that SDCLK at the SDRAM is centered around when the control signals change.



Note: The first SDCLK shows how SDCLK operates with the SHFTSDCLK bits = 000, no shift.

The second SDCLK shows how SDCLK operates with the SHFTSDCLK bits = 001, shift 0.5 core clock.

(See MC\_MEMCNTRL2 bits [5:3], Table 4-16 on page 108, for remaining decode values.)

Figure 4-10. Effects of SHFTSDCLK Programming Bits Example

### 4.4 GRAPHICS PIPELINE

The graphics pipeline of the GXm processor includes a BitBLT/vector engine which has been optimized for Microsoft Windows. The hardware supports pattern generation, source expansion, pattern/source transparency, and 256 ternary raster operations. The block diagram of the graphics pipeline is shown in Figure 4-11.

### 4.4.1 BitBLT/Vector Engine

BLTs are initiated by writing to the GP\_BLT\_MODE register, which specifies the type of source data (none, frame buffer, or BLT buffer), the type of the destination data (none, frame buffer, or BLT buffer), and a source expansion flag.




Figure 4-11. Graphics Pipeline Block Diagram

The BLT buffers in the dedicated cache temporarily store source and destination data, typically on a scan line basis. The hardware automatically loads frame-buffer data (source or destination) into the BLT buffers for each scan line. The software is responsible for making sure that this does not overflow the memory allocated for the BLT buffers. When the source data is a bitmap, the data is loaded directly into the BLT buffer before starting the BLT.

Vectors are initiated by writing to the GP\_VECTOR\_MODE register (GX\_BASE+8204h), which specifies the direction of the vector and a "read destination data" flag. If the flag is set, the hardware will read destination data along the vector and store it temporarily in BLT Buffer 0.

#### 4.4.2 Master/Slave Registers

When starting a BitBLT or vector operation, the graphics pipeline registers are latched from the master registers to the slave registers. A second BitBLT or vector operation can then be loaded into the master registers while the first operation is rendered. If a second BLT is pending in the master registers, any write operations to the graphics

pipeline registers will corrupt the values of the pending BLT. Software must prevent this from happening by checking the "BLT Pending" bit in the GP\_BLT\_STATUS register (GX\_BASE+820Ch[2].

Most of the graphics pipeline registers are latched directly from the master registers to the slave registers when starting a new BitBLT or vector operation. Some registers, however, use the updated slave values if the master registers have not been written, which allows software to render successive primitives without loading some of the registers as outlined in Table 4-21.

#### 4.4.3 Pattern Generation

The graphics pipeline contains hardware support for 8x8 monochrome patterns (expanded to two colors), 8x8 dither patterns (expanded to four colors), and 8x1 color patterns. The pattern hardware, however, does not maintain a pattern origin, so the pattern data must be justified before it is loaded into the GXm processor's registers. For solid primitives, the pattern hardware is disabled and the pattern color is always sourced from the GP\_PAT\_COLOR\_0 register (GX\_BASE+8110h).

Table 4-21. Graphics Pipeline Registers

Master	Function
GP_DST_XCOOR	Next X position along vector.
	Master register if written, otherwise: Unchanged slave if BLT, source mode = bitmap. Slave + width if BLT, source mode = text glyph
GP_DST_YCOOR	Next Y position along vector.
	Master register if written, otherwise: Slave +/- height if BLT, source mode = bitmap. Unchanged slave if BLT, source mode = text glyph.
GP_INIT_ERROR  Master register if written, otherwise: Initial error for the next pixel along the vector.	
GP_SRC_YCOOR	Master register if written, otherwise: Slave +/- height if BLT, source mode = bitmap.

#### 4.4.3.1 Monochrome Patterns

Monochrome patterns are selected by setting the pattern mode to 01b in the GP\_RASTER\_MODE register (GX\_BASE+ 8200h). Those pixels corresponding to a clear bit (0) in the pattern are rendered using the color specified in the GP\_PAT\_COLOR\_0 register, and those pixels corresponding to a set bit (1) in the pattern are rendered using the color specified in the GP\_PAT\_COLOR\_1 register (GX\_BASE+8112h).

If the pattern transparency bit is set high in the GP\_RASTER\_MODE register, those pixels corresponding to a clear bit in the pattern data are not drawn.

Monochrome patterns use bits [63:0] of the pattern data. Bits [7:0] correspond to the first row of the pattern, and bit 7 corresponds to the leftmost pixel on the screen. This is illustrated in Figure 4-12.




Figure 4-12. Example of Monochrome Patterns

#### 4.4.3.2 Dither Patterns

Dither patterns are selected by setting the pattern mode to 10 b in the GP\_RASTER\_MODE register (Table 4-25 on page 125). Two bits of pattern data are used for each pixel, allowing color expansion to four colors. The colors are specified in the GP\_PAT\_COLOR\_0 through GP\_PAT\_COLOR\_3 registers (Table 4-25 on page 125).

Dither patterns use all 128 bits of pattern data. Bits [15:0] correspond to the first row of the pattern (the lower byte contains the LSB of the pattern color and the upper byte contains the MSB of the pattern color). This is illustrated in Figure 4-13.




Figure 4-13. Example of Dither Patterns

#### 4.4.3.3 Color Patterns

Color patterns are selected by setting the pattern mode to 11 b in the GP\_RASTER\_MODE register. Bits [63:0] are used to hold a row of pattern data for an 8-BPP pattern, with bits [7:0] corresponding to the leftmost pixel of the row. Likewise, bits [127:0] are used for a 16-BPP color pattern, with bits [15:0] corresponding to the leftmost pixel of the row.

To support an 8x8 color pattern, software must load the pattern data for each row.

#### 4.4.4 Source Expansion

The graphics pipeline contains hardware support for color expansion of source data (primarily used for text). Those pixels corresponding to a clear bit (0) in the source data are rendered using the color specified in the GP\_SRC\_COLOR\_0 register (GX\_BASE+810Ch), and those pixels corresponding to a set bit (1) in the source data are rendered using the color specified in the GP\_SRC\_COLOR\_1 register (GX\_BASE+810Eh).

If the source transparency bit is set in the GP\_RASTER\_MODE register, those pixels corresponding to a clear bit (0) in the source data are not drawn.

#### 4.4.5 Raster Operations

The GP\_RASTER\_MODE register specifies how the pattern data, source data (color-expanded if necessary), and destination data are combined to produce the output from the graphics pipeline. The definition of the ROP valu matches that of the Microsoft API. This allows Windows display drivers to load the raster operation directly into hardware. Table 4-22 illustrates this definition. Some common raster operations are described in Table 4-23.

Table 4-22. GP RASTER MODE Bit Patterns

Pattern (bit)	Source (bit)	Destination (bit)	Output (bit)
0	0	0	ROP[0]
0	0	1	ROP[1]
0	1	0	ROP[2]
0	1	1	ROP[3]
1	0	0	ROP[4]
1	0	1	ROP[5]
1	1	0	ROP[6]
1	1	1	ROP[7]

**Table 4-23. Common Raster Operations** 

ROP	Description
F0h	Output = Pattern
CCh	Output = source
5Ah	Output = Pattern XOR destination
66h	Output = Source XOR destination
55h	Output = ~Destination

## 4.4.6 Graphics Pipeline Register Descriptions

The graphics pipeline maps 200h locations starting at GX\_BASE+8100h. Refer to Section 4.1.2 "Control Registers" on page 94 for instructions on accessing these registers.

Table 4-24 summarizes the graphics pipeline registers and Table 4-25 on page 125 gives detailed register/bit formats

Table 4-24. Graphics Pipeline Configuration Register Summary

GX_BASE+ Memory Offset Type Name / Function		Default Value	
8100h-8103h	R/W	GP_DST/START_Y/XCOOR  Destination/Starting Y and X Coordinates Register — In BLT mode this register specifies the destination Y and X positions for a BLT operation. In Vector mode it specifies the starting Y and X positions in a vector.	00000000h
8104-8107h	R/W	GP_WIDTH/HEIGHT and GP_VECTOR_LENGTH/INIT_ERROR	00000000h
8104-810711	IX/VV	Width/Height or Vector Length/Initial Error Register — In BLT mode this register specifies the BLT width and height in pixels. In Vector mode it specifies the vector initial error and pixel length.	000000011
8108h-810Bh	R/W	GP_SRC_X/YCOOR and GP_AXIAL/DIAG_ERROR Source X/Y Coordinate Axial/Diagonal Error Register — In BLT mode this register specifies the BLT X and Y source. In Vector mode it specifies the axial and diagonal error for rendering a vector.	00000000h
810Ch-810Fh	R/W	GP_SRC_COLOR_0 and GP_SCR_COLOR_1 Source Color Register — Determines the colors used when expanding monochrome source data in either the 8-BPP mode or the 16-BPP mode.	00000000h
8110h-8113h	R/W	GP_PAT_COLOR_0 and GP_PAT_COLOR_1 Graphics Pipeline Pattern Color 0 and 1 Registers — These two registers determine the colors used when expanding pattern data.	00000000h
8114h-8117h	R/W	GP_PAT_COLOR_2 and GP_PAT_COLOR_3 Graphics Pipeline Pattern Color 2 and 3 Registers — These two registers determine the colors used when expanding pattern data.	00000000h
8120h-8123h	R/W	GP_PAT_DATA 0 through 3	00000000h
8124h-8127h	R/W	Graphics Pipeline Pattern Data Registers 0 through 3 — Together these registers	00000000h
8128h-812Bh	R/W	contain 128 bits of pattern data.	00000000h
812Ch-812Fh	R/W	GP_PAT_DATA_0 corresponds to bits [31:0] of the pattern data.  GP_PAT_DATA_1 corresponds to bits [63:32] of the pattern data.  GP_PAT_DATA_2 corresponds to bits [95:64] of the pattern data.  GP_PAT_DATA_3 corresponds to bits [127:96] of the pattern data.	00000000h
8140h-8143h (Note)	R/W	GP_VGA_WRITE Graphics Pipeline VGA Write Patch Control Register — Controls the VGA memory write path in the graphics pipeline.	xxxxxxxxh
8144h-8147h (Note)	R/W	GP_VGA_READ Graphics Pipeline VGA Read Patch Control Register — Controls the VGA memory read path in the graphics pipeline.	00000000h
8200h-8203h	R/W	GP_RASTER_MODE  Graphics Pipeline Raster Mode Register — This register controls the manipulation of the pixel data through the graphics pipeline. Refer to Section 4.4.5 "Raster Operations" on page 123.	
8204h-8207h	R/W	GP_VECTOR_MODE  Graphics Pipeline Vector Mode Register — Writing to this register initiates the rendering of a vector.	00000000h

**Note:** The registers at GX\_BASE+8140, 8144h, 8210h, and 8217h are located in the area designated for the graphics pipeline but are used for VGA emulation purposes. Refer to Table 5-5 on page 173 for these register's bit formats.

Table 4-24. Graphics Pipeline Configuration Register Summary (Continued)

GX_BASE+ Memory Offset	Туре	Name / Function	Default Value
820Ch-820Fh	R/W	GP_BLT_STATUS	00000000h
		Graphics Pipeline BLT Status Register — Contains configuration and status information for the BLT engine. The status bits are contained in the lower byte of the register.	
8210h-8213h	R/W	GP_VGA_BASE	xxxxxxxxh
(Note)		Graphics Pipeline VGA Memory Base Address Register — Specifies the offset of the VGA memory, starting from the base of graphics memory.	
8214h-8217h	R/W	GP_VGA_LATCH	xxxxxxxxh
(Note)		Graphics Pipeline VGA Display Latch Register — Provides a memory mapped way to read or write the VGA display latch.	

**Note:** The registers at GX\_BASE+8140, 8144h, 8210h, and 8217h are located in the area designated for the graphics pipeline but are used for VGA emulation purposes. Refer to Table 5-5 on page 173 for these register's bit formats.

**Table 4-25. Graphics Pipeline Configuration Registers** 

	1	Table 4-25. Graphics Pipeline Configuration Regis	
Bit	Name	Description	
GX_BAS	SE+8100h-810	GP_DST/START_X/YCOOR Register (R/W)	Default Value = 00000000h
31:16	DESTINATIO	N/STARTING Y POSITION (SIGNED):	
	BLT Mode —	Specifies the destination Y position for a BLT operation.	
	Vector Mode	<ul> <li>Specifies the starting Y position in a vector.</li> </ul>	
15:0	DESTINATIO	N/STARTING X POSITION (SIGNED):	
		Specifies the destination X position for a BLT operation.	
	Vector Mode	Specifies the starting X position in a vector.	
GX_BAS	SE+8104h-810	7h GP_WIDTH/HEIGHT and GP_VECTOR_LENGTH/INIT_ERROR Register (R/W)	Default Value = 000000001
31:16	PIXEL_WIDT	H or VECTOR_LENGTH (UNSIGNED):	
	BLT Mode —	Specifies the width, in pixels, of a BLT operation. No pixels are rendered to	for a width of zero.
		<ul> <li>— Bits [31:30] are reserved in this mode allowing this 14-bit field to specify dered for a length of zero. This field is limited to 14 bits due to a lack of properties.</li> </ul>	•
15:0	PIXEL_HEIG	HT or VECTOR_INITIAL_ERROR (UNSIGNED):	
	BLT Mode —	Specifies the height, in pixels, of a BLT operation. No pixels are rendered	for a height of zero.
	Vector Mode	Specifies the initial error for rendering a vector.	
GX_BAS	SE+8108h-810	Bh GP_SCR_X/YCOOR and GP_AXIAL/DIAG_ERROR Register (R	R/W) Default Value = 000000001
31:16	SRC_X_POS	or VECTOR_AXIAL_ERROR (SIGNED):	
	BLT Modo		
	BLI Wode —	Specifies the source X position for a BLT operation.	
		Specifies the source X position for a BLT operation.  — Specifies the axial error for rendering a vector.	
15:0	Vector Mode	·	
15:0	Vector Mode SRC_Y_POS	— Specifies the axial error for rendering a vector.	
15:0	Vector Mode SRC_Y_POS Source Y Pos	— Specifies the axial error for rendering a vector.  s or VECTOR_DIAG_ERROR (SIGNED):	
	Vector Mode SRC_Y_POS Source Y Pos	— Specifies the axial error for rendering a vector.  5 or VECTOR_DIAG_ERROR (SIGNED):  sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.	Default Value = 00000000
GX_BAS	Vector Mode  SRC_Y_POS  Source Y Pos  Vector Mode  SE+810Ch-810	— Specifies the axial error for rendering a vector.  5 or VECTOR_DIAG_ERROR (SIGNED):  sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.	Default Value = 000000000
GX_BAS	Vector Mode  SRC_Y_POS  Source Y Pos  Vector Mode  SE+810Ch-810	— Specifies the axial error for rendering a vector.  Sor VECTOR_DIAG_ERROR (SIGNED): Sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.  Fh	Default Value = 00000000
GX_BAS 8-BPP N	Vector Mode SRC_Y_POS Source Y Pos Vector Mode SE+810Ch-810 lode GP_SRC_CC	— Specifies the axial error for rendering a vector.  Sor VECTOR_DIAG_ERROR (SIGNED): Sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.  Fh	
GX_BAS 8-BPP M 31:24	Vector Mode SRC_Y_POS Source Y Pos Vector Mode SE+810Ch-810 Iode GP_SRC_CC 8-BPP Color	— Specifies the axial error for rendering a vector.  For VECTOR_DIAG_ERROR (SIGNED): Sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.  Fh	
<b>GX_BAS 8-BPP N</b> 31:24 23:16	Vector Mode SRC_Y_POS Source Y Pos Vector Mode SE+810Ch-810 dode GP_SRC_CC 8-BPP Color data. GP_SRC_CC	— Specifies the axial error for rendering a vector.  For VECTOR_DIAG_ERROR (SIGNED): Sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.  Fh	_COLOR_0 when rendering 8-BPF
GX_BAS 8-BPP N 31:24 23:16 15:8 7:0	Vector Mode SRC_Y_POS Source Y Pos Vector Mode SE+810Ch-810 Iode GP_SRC_CC 8-BPP Color data. GP_SRC_CC 8-BPP Color data.	— Specifies the axial error for rendering a vector.  Sor VECTOR_DIAG_ERROR (SIGNED): Sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.  Fh	_COLOR_0 when rendering 8-BPF
GX_BAS 8-BPP M 31:24 23:16 15:8	Vector Mode SRC_Y_POS Source Y Pos Vector Mode SE+810Ch-810 Iode GP_SRC_CC 8-BPP Color data. GP_SRC_CC 8-BPP Color data. Mode	— Specifies the axial error for rendering a vector.  Sor VECTOR_DIAG_ERROR (SIGNED): Sition (Signed) — Specifies the source Y position for a BLT operation.  — Specifies the diagonal error for rendering a vector.  Fh	_COLOR_0 when rendering 8-BPF

## **Table 4-25. Graphics Pipeline Configuration Registers (Continued)**

Bit	Name	Description	
8- G	BPP mode or the	eline Source Color Register specifies the colors used when expande 16-BPP mode. Those pixels corresponding to clear bits (0) in R_0 and those pixels corresponding to set bits (1) in the source R_1.	the source data are rendered using
GX_BAS	E+8110h-8113	h GP_PAT_COLOR_A Register (R/W)	Default Value = 00000000h
8-BPP M	lode		
31:24	GP_PAT_COL	OR_0:	
23:16	8-BPP Color I data.	ndex — The color index must be duplicated in the upper byte of	GP_PAT_COLOR_0 when rendering 8-BPP
15:8	GP_PAT_COI		
7:0	8-BPP Color I data.	ndex — The color index must be duplicated in the upper byte of	GP_PAT_COLOR_1 when rendering 8-BPP
16-BPP I	Mode		
31:16		.OR_0: 16-BPP Color (RGB)	
15:0	GP_PAT_COL	.OR_1: 16-BPP Color (RGB)	
Note: Th	ne Graphics Pip	eline Pattern Color A and B Registers specify the colors used w	vhen expanding pattern data.
GX_BAS	E+8114h-8117	h GP_PAT_COLOR_B Register (R/W)	Default Value = 00000000h
8-BPP M	lode		
31:24	GP_PAT_COL	.OR_2:	
23:16	8-BPP Color I data.	ndex — The color index must be duplicated in the upper byte of	GP_PAT_COLOR_2 when rendering 8-BPP
15:8	GP_PAT_COI	_	
7:0	8-BPP Color I data.	ndex — The color index must be duplicated in the upper byte of	GP_PAT_COLOR_3 when rendering 8-BPP
16-BPP I	Mode		
31:16	GP_PAT_COI	.OR_2: 16-BPP Color (RGB)	
15:0		.OR_3: 16-BPP Color (RGB)	
		eline Pattern Color A and B Registers specify the colors used w	vhen expanding pattern data.
GX_BAS	E+8120h-8123		Default Value = 00000000h
31:0		ata Register 0: The Graphics Pipeline Pattern Data Registers (GP_PAT_DATA_0 register corresponds to bits [31:0] of the patt	
GX_BAS	E+8124h-8127	h GP_PAT_DATA_1 Register (R/W)	Default Value = 00000000h
31:0		ata Register 1: The Graphics Pipeline Pattern Data Registers (GP_PAT_DATA_1 register corresponds to bits [63:32] of the pa	
GX_BAS	E+8128h-812E	h GP_PAT_DATA_2 Register (R/W)	Default Value = 00000000h
31:0		ata Register 2: The Graphics Pipeline Pattern Data Registers (GP_PAT_DATA_2 register corresponds to bits [95:64] of the pa	
GX_BAS	E+812Ch-812F	h GP_PAT_DATA_3 Register (R/W)	Default Value = 00000000h
31:0		ata Register 3: The Graphics Pipeline Pattern Data Registers 0 GP_PAT_DATA_3 register corresponds to bits [127:96] of the p	
GX_BAS	E+8140h-8143	h GP_VGA_WRITE Register (R/W)	Default Value = xxxxxxxxxh
	•	GX_BASE+82140h and 8144h are located in the area designals. Refer to Table 5-5 on page 173 for these register's bit formats	9 1 1 1
GX BAS	E+8144h-8147	h GP_VGA_READ Register (R/W)	Default Value = 00000000h
Note that	the registers a	GX_BASE+82140h and 8144h are located in the area designals. Refer to Table 5-5 on page 173 for these register's bit formats	ated for the graphics pipeline but are used for

**Table 4-25. Graphics Pipeline Configuration Registers (Continued)** 

Bit	Name	Description					
GX_BAS	E+8200h-820	3h GP_RASTER_MODE Register (R/W)	Default Value = 00000000h				
31:13	RSVD	Reserved: Set to 0.					
12	ТВ	<b>Transparent BLIT:</b> When set, this bit enables transparent BLIT. The sou color key and if it matches, that pixel will not be drawn. The color key va destination data. The raster operation must be set to C6h, and the patter mode to work properly.	lue is stored in the BLIT buffer as				
11	ST	<b>Source Transparency:</b> Enables transparency for monochrome source data. Those pixels corresponding to clear bits in the source data are not drawn.					
10	PT	Pattern Transparency: Enables transparency for monochrome pattern clear bits in the pattern data are not drawn.	data. Those pixels corresponding to				
9:8	PM	Pattern Mode: Specifies the format of the pattern data.					
		00 = Indicates a solid pattern. The pattern data is always sourced from t	the GP_PAT_COLOR_0 register.				
		01 = Indicates a monochrome pattern. The pattern data is sourced from GP_PAT_COLOR_1 registers.	the GP_PAT_COLOR_0 and				
		10 = Indicates a dither pattern. All four pattern color registers are used.					
		11 =Indicates a color pattern. The pattern data is sourced directly from t	the pattern data registers.				
7:0	ROP	Raster Operation: Specifies the raster operation for pattern, source, an	nd destination data.				
GX_BAS	E+8204h-820	7h GP_VECTOR_MODE Register (R/W)	Default Value = 00000000h				
31:4	RSVD	Reserved: Set to 0.					
3	DEST	Read Destination Data: Indicates that frame-buffer destination data is	required.				
2	DMIN	Minor Direction: Indicates a positive minor axis step.					
1	DMAJ	Major Direction: Indicates a positive major axis step.					
0	YMAJ	Major Direction: Indicates a Y Major vector.					
GX_BAS	E+8208h-820	Bh GP_BLT_MODE Register (R/W)	Default Value = 00000000h				
31:9	RSVD	Reserved: Set to 0.					
8	Υ	Reverse Y Direction: Indicates a negative increment for the Y position. tion of screen to screen BLTs to prevent data corruption in overlapping v					
7:6	SM	Source Mode: Specifies the format of the source data.					
		00 = Source is a color bitmap.					
		01 = Source is a monochrome bitmap (use source color expansion).					
		10 = Unused.					
		11 = Source is a text glyph (use source color expansion). This differs fro X position is adjusted by the width of the BLT and the Y position remains	•				
5	RSVD	Reserved: Set to 0.					
4:2	RD	Destination Data: Specifies the destination data location.					
		000 = No destination data is required. The destination data into the raste	er operation unit is all ones.				
		010 = Read destination data from BLT Buffer 0.					
		011 = Read destination data from BLT Buffer 1.					
		100 = Read destination data from the frame buffer (store temporarily in	BLT Buffer 0).				
		101 = Read destination data from the frame buffer (store temporarily in	BLT Buffer 1).				
1:0	RS	Source Data: Specifies the source data location.					
		00 = No source data is required. The source data into the raster operation					
		01 = Read source data from the frame buffer (temporarily stored in BLT	Buffer 0).				
		10 = Read source data from BLT Buffer 0.					
		11 = Read source data from BLT Buffer 1.					

## Table 4-25. Graphics Pipeline Configuration Registers (Continued)

Bit	Name	Description				
GX_BAS	E+820Ch-820	Fh GP_BLT_STATUS Register (R/W) Default Value = 00000000h				
31:10	RSVD	Reserved: Set to 0.				
9	W	Screen Width: Selects a frame-buffer width of 2048 bytes (default is 1024 bytes).				
8	М	16-BPP Mode: Selects a pixel data format of 16 BPP (default is 8 BPP).				
7:3	RSVD	Reserved: Set to 0.				
2	BP (RO)	BLT Pending (Read Only): Indicates that a BLT operation is pending in the master registers.				
		The "BLT Pending" bit must be clear before loading any of the graphics pipeline registers. Loading registers when this bit is set high will destroy the values for the pending BLT.				
1	PB (RO)	Pipeline Busy (Read Only): Indicates that the graphics pipeline is processing data.				
		The "Pipeline Busy" bit differs from the "BLT Busy" bit in that the former only indicates that the graphics pipeline is processing data. The "BLT Busy" bit also indicates that the memory controller has not yet processed all of the requests for the current operation.				
		The "Pipeline Busy" bit must be clear before loading a BLT buffer if the previous BLT operation used the same BLT buffer.				
0	BB (RO)	BLT Busy (Read Only): Indicates that a BLT / vector operation is in progress.				
		The "BLT Busy" bit must be clear before accessing the frame buffer directly.				

### GX\_BASE+8210h-8213h

#### GP\_VGA\_BASE (R/W)

Default Value = xxxxxxxxh

Note that the registers at GX\_BASE+8210h and 8214h are located in the area designated for the graphics pipeline but are used for VGA emulation purposes. Refer to Table 5-5 on page 173 for these register's bit formats.

#### GX\_BASE+8214h-8217h

### GP\_VGA\_LATCH Register (R/W)

Default Value = xxxxxxxxh

Note that the registers at GX\_BASE+8210h and 8214h are located in the area designated for the graphics pipeline but are used for VGA emulation purposes. Refer to Table 5-5 on page 173 for these register's bit formats.

### 4.5 DISPLAY CONTROLLER

The GXm processor incorporates a display controller that retrieves display data from the memory controller and formats it for output on a variety of display devices. The GXm processor can directly connect to an active matrix TFT LCD flat panel or to an external RAMDAC for CRT display or both. The display controller includes a display FIFO, compression/decompression (CODEC) hardware, hard-

ware cursor, a 256-entry-by-18-bit palette RAM (plus three extension colors), display timing generator, dither and frame-rate-modulation circuitry for TFT panels, and flexible output formatting logic. A diagram of the display controller subsystem is shown in Figure 4-14.




Figure 4-14. Display Controller Block Diagram

#### 4.5.1 Display FIFO

The display controller contains a large (64x64 bit) FIFO for queuing up display data from the memory controller as it is required for output to the screen. The memory controller must arbitrate between the display controller requests and other requests for memory access from the microprocessor core, L1 cache controller, and the graphics pipeline.

Since display data is required in real time, this data is the highest priority in the system. Without efficient memory management, system performance would suffer dramatically due to the constant display-refresh requests from the display controller. The large size of the display FIFO is desirable so that the FIFO may primarily be loaded during times when there is no other request pending to the DRAM controller and so that the memory controller can stay in page mode for a long period of time when servicing the display FIFO. When a priority request from the cache or graphics pipeline occurs, if the display FIFO has enough data queued up, the DRAM controller can immediately service the request without concern that the display FIFO will underflow. If the display FIFO is below a programmable threshold, a high-priority request will be sent to the DRAM controller, which will take precedence over any other requests that are pending.

The display FIFO is 64 bits wide to accommodate highspeed burst read operations from the DRAM controller at maximum memory bandwidth. In addition to the normal pixel data stream, the display FIFO also queues up cursor patterns.

#### 4.5.2 Compression Technology

To reduce the system memory contention caused by the display refresh, the display controller contains compression and decompression logic for compressing the frame buffer image in real time as it is sent to the display. It combines this compressed display buffer into the extra offscreen memory within the graphics memory aperture. Coherency of the compressed display buffer is maintained by use of dirty and valid bits for each line. The dirty and valid RAM is contained on-chip for maximum efficiency. Whenever a line has been validly compressed, it will be retrieved from the compressed display buffer for all future accesses until the line becomes dirty again. Dirty lines will be retrieved from the normal uncompressed frame buffer.

The compression logic has the ability to insert a programmable number of "static" frames, during which time dirty bits are ignored and the valid bits are read to determine whether a line should be retrieved from the frame buffer or compressed display buffer. The less frequently the dirty bits are sampled, the more frequently lines will be retrieved from the compressed display buffer. This allows a programmable screen image update rate (as opposed to refresh rate). Generally, an update rate of 30 frames per second is adequate for displaying most types of data, including real-time video. However, if a flat panel display is used that has a slow response time, such as 100 ms, the image need not be updated faster than ten frames per second, since the panel could not display changes beyond that rate.

The compression algorithm used in the GXm processor commonly achieves compression ratios between 10:1 and 20:1, depending on the nature of the display data. This high level of compression provides higher system performance by reducing typical latency for normal system memory access, higher graphics performance by increasing available drawing bandwidth to the DRAM array, and much lower power consumption by significantly reducing the number of off-chip DRAM accesses required for refreshing the display. These advantages become even more pronounced as display resolution, color depth, and refresh rate are increased and as the size of the installed DRAM increases.

As uncompressed lines are fed to the display, they will be compressed and stored in an on-chip compressed line buffer (64x32 bits). Lines will not be written back to the compressed display buffer in the DRAM unless a valid compression has resulted, so there is no penalty for pathological frame buffer images where the compression algorithm breaks down.

### 4.5.3 Motion Video Acceleration Support

The display controller of the GXm processor supports the CS5530 and future I/O companion chips' hardware motion video acceleration by reading the off-screen video buffer and serializing the video data onto the RAMDAC port. The display controller supplies video data to the I/O companion chips in either interleaved YUV4:2:2 format or RGB5:6:5 format. The I/O companion chips can then scale and filter the data, apply color space conversion to YUV data, and mix the video data with graphics data also supplied by the display controller.

#### 4.5.4 Hardware Cursor

The display controller contains hardware cursor logic to allow overlay of the cursor image onto the pixel data stream. Overhead for updating this image on the screen is kept to a minimum by requiring that only the X and Y position be changed. This eliminates "submarining" effects commonly associated with software cursors. The cursor, 32x32 pixels with two bits per pixel, is loaded into offscreen memory within the graphics memory aperture. The two-bit code selects color 0, color 1, transparent, or background-color inversion for each pixel in the cursor (see Table 4-31 on page 144. The two cursor colors will be stored as extensions to the normal 256-entry palette at locations 100h and 101h. These palette extensions will be used when driving a flat panel or a RAMDAC operating in 16 BPP (bits per pixel) mode. For 8 BPP operation using an external RAMDAC, the DC\_CURSOR\_COLOR register (GX\_BASE+8360h) should be programmed to set the indices for the cursor colors. To avoid corruption of the cursor colors by an application program that modifies the external palette, care should be taken to program the cursor color indices to one of the static color indices. Since Microsoft Windows typically uses only black and white cursor colors and these are static colors, this kind of problem should rarely occur.

### 4.5.5 Display Timing Generator

The display controller features a fully programmable timing generator for generating all timing control signals for the display. The timing control signals include horizontal and vertical sync and blank signals in addition to timing for active and overscan regions of the display. The timing generator is similar in function to the CRTC of the original VGA, although programming is more straightforward. Programming of the timing registers will generally happen via a BIOS INT10 call during a mode set. When programming the timing registers directly, extreme care should be taken to ensure that all timing is compatible with the display device.

The timing generator supports overscan to maintain full backward compatibility with the VGA. This feature is supported primarily for CRT display devices since flat panel displays have fixed resolutions and do not provide for overscan. However, the GXm processor supports a mechanism to center the display when a display mode is selected having a lower resolution than the panel resolution. The border region is effectively stretched to fill the remainder of the screen. The border color is at palette extension 104h. For 8 BPP operation with an external RAMDAC, the DC\_BORDER\_COLOR register (GX\_BASE+8368h) should also be programmed.

#### 4.5.6 Dither and Frame-Rate Modulation

The display controller supports 2x2 dither and two-level frame-rate modulation (FRM) to increase the apparent number of colors displayed on 9-bit or 12-bit TFT panels. Dither and FRM are individually programmable. With dithering and FRM enabled, 185,193 colors are possible on a 9-bit TFT panel, and 226,981 colors are possible on a 12-bit TFT panel.

#### 4.5.7 Display Modes

The GXm processor supports 640x480, 800x600, and 1024x768 display resolutions at both 8 and 16 bits per pixel. In addition, 1280x1024 resolution is supported at 8 bits per pixel only. Two 16-bit display formats are supported: RGB 5-6-5 and RGB 5-5-5. All CRT modes use VESA-compatible timing. Table 4-26 on page 132 gives the supported CRT display modes.

Table 4-26. TFT Panel Display Modes

Resolution	Simultaneous Colors	Refresh Rate (Hz)	DOTCLK Rate (MHz)	PCLK (MHz)	Panel Type	Maximum Displayed Colors (Note 1)
640x480	8 BPP	60	25.175	25.175	9-bit	57 <sup>3</sup> = 185,193
(Note 2)	256 colors out of a palette of 256				12-bit	$61^3 = 226,981$
	paiotto di 200				18-bit	4 <sup>3</sup> = 262,144
	16 BPP	60	25.175	25.175	9-bit	29x57x29 = 47,937
	64 K colors 5-6-5				12-bit	31x61x31 = 58,621
	3-0-3				18-bit	32x64x32 = 65,535
800x600	8 BPP	60	40.0	40.0	9-bit	$57^3 = 185,193$
(Note 2)	256 colors out of a palette of 256				12-bit	$61^3 = 226,981$
	parette of 200				18-bit	$64^3 = 262,144$
	16 BPP 64 K Colors 5-6-5	60	40.0	40.0	9-bit	29x57x29 = 47,937
					12-bit	31x61x31 = 58,621
					18-bit	32x64x32 = 65,535
1024x768	8 BPP 256 colors out of a palette of 256	60	65	32.5	9-bit/18-I/F	57 <sup>3</sup> = 185,193
	16 BPP 64 K colors 5-6-5	60	65	32.5	9-bit/18-I/F	29x57x29 = 47,937

Notes: 1) 9-bit and 12-bit panels use FRM and dither to increase displayed colors. (See Section 4.5.6 "Dither and Frame-Rate Modulation" on page 131.)

2) All 640x480 and 800x600 modes can be run in simultaneous display with CRT.

Table 4-27. TFT Panel Data Bus Formats

Panel Data	18-Bit	12-Bit TFT	9	9-Bit TFT		
Bus Bit	TFT		640x480	102	4x768	
17	R5	R5	R5	R5	Even	
16	R4	R4	R4	R4	]	
15	R3	R3	R3	R3		
14	R2	R2		R5	Odd	
13	R1			R4		
12	R0			R3		
11	G5	G5	G5	G5	Even	
10	G4	G4	G4	G4	]	
9	G3	G3	G3	G3	]	
8	G2	G2		G5	Odd	
7	G1			G4	]	
6	G0			G3		
5	B5	B5	B5	B5	Even	
4	B4	B4	B4	B4	]	
3	B3	В3	B3	B3	1	
2	B2	B2		B5	Odd	
1	B1			B4	1	
0	B0			В3		

Table 4-28. CRT Display Modes

Resolution	Simultaneous Colors	Refresh Rate (Hz)	DOTCLK Rate (MHz)	PCLK (MHz)	Graphics Port Width (Bits)
640x480	8 BPP	60	25.175	25.175	8
	256 colors out of a palette of 256	72	31.5	31.5	8
	palette of 200	75	31.5	31.5	8
	16 BPP	60	25.175	50.35	8
	64 K colors RGB 5-6-5			25.175	16
	NOD 3-0-3	72	31.5	63.0	8
				31.5	16
		75	31.5	63.0	8
				31.5	16
800x600	8 BPP	60	40.0	40.0	8
	256 colors out of a palette of 256	72	50.0	50.0	8
		75	49.5	49.5	8
	16 BPP 64 K colors RGB 5-6-5	60	40.0	80.0	8
				40.0	16
		72	50.0	100	8
				50.0	16
		75	49.5	99	8
				49.5	16
1024x768	8 BPP	60	65.0	65.0	8
	256 colors out of a palette of 256	70	75.0	75.0	8
	palette of 200	75	78.5	78.5	8
	16 BPP	60	65.0	65.0	16
	64 K colors RGB 5-6-5	70	75.0	75.0	16
	1.00 0-0-0	75	78.5	78.5	16
1280x1024	8 BPP	60	108.0	108.0	8
	256 colors out of a palette of 256			54.0	16
	paiotic of 200	75	135.0	67.5	16

#### 4.5.8 Graphics Memory Map

The GXm processor supports a maximum of 4 MB of graphics memory and will map it to an address space (see Figure 4-2 on page 93) higher than the maximum amount of installed RAM. The graphics memory aperture physically resides at the top of the installed system RAM. The start address and size of the graphics memory aperture are programmable on 128 KB boundaries. Typically, the system BIOS sets the size and start address of the graphics memory aperture during the boot process based on the amount of installed RAM, user defined CMOS settings, and display resolution. The graphics pipeline and display controller address the graphics memory with a 20bit offset (address bits [21:2]) and four byte enables into the graphics memory aperture. The graphics memory stores several buffers that are used to generate the display: the frame buffer, compressed display buffer, VGA memory, and cursor pattern(s). Any remaining off-screen memory within the graphics aperture may be used by the display driver as desired or not at all.

#### 4.5.8.1 DC Memory Organization Registers

The display controller contains a number of registers that allow full programmability of the graphics memory organization. This includes starting offsets for each of the buffer regions described above, line delta parameters for the frame buffer and compression buffer, as well as compressed line-buffer size information. The starting offsets

for the various buffers are programmable for a high degree of flexibility in memory organization.

# 4.5.8.2 Frame Buffer and Compression Buffer Organization

The GXm processor supports primary display modes 640x480, 800x600, and 1024x768 at both 8 BPP and 16 BPP, and 1280x1024 at 8 BPP. Pixels will be packed into DWORDs as shown in Figure 4-15.

In order to simplify address calculations by the rendering hardware, the frame buffer is organized in an XY fashion where the offset is simply a concatenation of the X and Y pixel addresses. All 8 BPP display modes with the exception of 1280x1024 resolution will use a 1024-byte line delta between the starting offsets of adjacent lines. All 16 BPP display modes and 1280x1024x8 BPP display modes will use a 2048-byte line delta between the starting offsets of adjacent lines. If there is room, the space between the end of a line and the start of the next line will be filled with the compressed display data for that line, thus allowing efficient memory utilization. For 1024x768 display modes, the frame-buffer line size is the same as the line delta, so no room is left for the compressed display data between lines. In this case, the compressed display buffer begins at the end of the frame buffer region and is linearly mapped.




Figure 4-15. Pixel Arrangement Within a DWORD

### 4.5.8.3 VGA Display Support

The graphics pipeline contains full hardware support for the VGA front end. The VGA data is stored in a 256 KB buffer located in graphics memory. The main task for Soft-VGA is converting the data in the VGA buffer to an 8 BPP frame buffer that can be displayed by the GXm processor's hardware.

For some modes, the display controller can display the VGA data directly and the data conversion is not necessary. This includes standard VGA mode 13h and the variations of that mode used in several games; the display controller can also directly display VGA planar graphics modes D, E, F, 10, 11, and 12. Likewise, the hardware can directly display all of the higher-resolution VESA modes. Since the frame buffer data is written directly to memory instead of travelling across an external bus, the GXm processor outperforms typical VGA cards for these modes.

The display controller, however, does not directly support text modes. SoftVGA must then convert the characters and attributes in the VGA buffer to an 8 BPP frame buffer the hardware uses for display refresh. See Section 4 "Virtual Subsystem Architecture" for SoftVGA details.

### 4.5.8.4 Cursor Pattern Memory Organization

The cursor overlay patterns are loaded to independent memory locations, usually mapped above the frame buffer and compressed display buffer (off-screen). The cursor buffer must start on a 16-byte aligned boundary. It is linearly mapped, and is always 256 bytes in size. If there is enough room (256 bytes) after the compression-buffer line but before the next frame-buffer line starts, the cursor pattern may be loaded into this area to make efficient use of the graphics memory.

Each pattern is a 32x32-pixel array of 2-bit codes. The codes are a combination of AND mask and XOR mask for a particular pixel. Each line of an overlay pattern is stored as two DWORDs, with each DWORD containing the AND masks for 16 pixels in the upper word and the XOR masks for 16 pixels in the lower word. DWORDs are arranged with the leftmost pixel block being least significant and the rightmost pixel block being most significant. Pixels within words are arranged with the leftmost pixels being most significant and the rightmost pixels being least significant.

Multiple cursor patterns may be loaded into the off-screen memory. An application may simply change the cursor start offset to select a new cursor pattern. The new cursor pattern will be used at the start of the next frame scan.

#### 4.5.9 Display Controller Registers

The Display Controller maps 100h locations starting at GX\_BASE+8300h. Refer to Section 4.1.2 "Control Registers" on page 94 for instructions on accessing these registers.

The Display Controller Registers are divided into six categories:

- · Configuration and Status Registers
- · Memory Organization Registers
- Timing Registers
- · Cursor and Line Compare Registers
- Color Registers
- · Palette and RAM Diagnostic Registers

Table 4-29 summarizes these registers and locations and the following subsections give detailed register/bit formats.

Table 4-29. Display Controller Register Summary

GX_BASE+ Memory Offset	Туре	Name/Function	Default Value
Configuration ar	nd Status	Registers	
8300h-8303h	R/W	DC_UNLOCK	00000000h
		Display Controller Unlock — This register is provided to lock the most critical memory-mapped display controller registers to prevent unwanted modification (write operations). Read operations are always allowed.	
8304h-8307h	R/W	DC_GENERAL_CFG	00000000h
		Display Controller General Configuration — General control bits for the display controller.	
8308h-830Bh	R/W	DC_TIMING_CFG	xx000000h
		Display Controller Timing Configuration — Status and control bits for various display timing functions.	
830Ch-830Fh	R/W	DC_OUTPUT_CFG	xx000000h
		Display Controller Output Configuration — Status and control bits for pixel output formatting functions.	
Memory Organiz	ation Re	gisters	
8310h-8313h	R/W	DC_FB_ST_OFFSET	xxxxxxxxh
		Display Controller Frame Buffer Start Address — Specifies offset at which the frame buffer starts.	

Table 4-29. Display Controller Register Summary (Continued)

GX_BASE+ Memory Offset			Default Value
8314h-8317h	R/W	DC_CB_ST_OFFSET	xxxxxxxxh
		Display Controller Compression Buffer Start Address — Specifies offset at which the compressed display buffer starts.	
8318h-831Bh	R/W	DC_CURS_ST_OFFSET	
		Display Controller Cursor Buffer Start Address — Specifies offset at which the cursor memory buffer starts.	
831Ch-831Fh		Reserved	00000000h
8320h-8323h	R/W	DC_VID_ST_OFFSET  Display Controller Video Start Address — Specifies offset at which the video buffer starts.	xxxxxxxxh
8324h-8327h	R/W	DC_LINE_DELTA Display Controller Line Delta — Stores line delta for the graphics display buffers.	xxxxxxxxh
8328h-832Bh	R/W	DC_BUF_SIZE  Display Controller Buffer Size — Specifies the number of bytes to transfer for a line of frame buffer data and the size of the compressed line buffer.	xxxxxxxxh
832Ch-832Fh		Reserved	00000000h
Timing Registers	s		
8330h-8333h	R/W	DC_H_TIMING_1	xxxxxxxxh
		Display Controller Horizontal and Total Timing — Horizontal active and total timing information.	
8334h-8337h	R/W	DC_H_TIMING_2	xxxxxxxxh
		Display Controller CRT Horizontal Blanking Timing — CRT horizontal blank timing information.	
8338h-833Bh	R/W	DC_H_TIMING_3 Display Controller CRT Sync Timing — CRT horizontal sync timing information.	
833Ch-833Fh	R/W	DC_FP_H_TIMING	xxxxxxxxh
		Display Controller Flat Panel Horizontal Sync Timing: Horizontal sync timing information for an attached flat panel display.	
8340h-8343h	40h-8343h R/W <b>DC_V_TIMING_1</b>		xxxxxxxxh
		Display Controller Vertical and Total Timing — Vertical active and total timing information. The parameters pertain to both CRT and flat panel display.	
8344h-8247h	R/W	DC_V_TIMING_2 Display Controller CRT Vertical Blank Timing — Vertical blank timing information.	
8348h-834Bh	R/W	DC_V_TIMING_3 Display Controller CRT Vertical Sync Timing — CRT vertical sync timing information.	
834Ch-834Fh R/W DC_FP_V_TIMING		DC_FP_V_TIMING	xxxxxxxxh
		Display Controller Flat Panel Vertical Sync Timing — Flat panel vertical sync timing information.	
Cursor and Line	Compar	e Registers	
8350h-8353h	R/W	DC_CURSOR_X Display Controller Cursor X Position — X position information of the hardware cursor.	xxxxxxxxh
8354h-8357h	RO	DC_V_LINE_CNT	xxxxxxxxh
		Display Controller Vertical Line Count — This read only register provides the current scanline for the display. It is used by software to time update of the frame buffer to avoid tearing artifacts.	
8358h-835Bh	R/W	DC_CURSOR_Y Display Controller Cursor Y Position — Y position information of the hardware cursor.	xxxxxxxxh
835Ch-835Fh	R/W	DC_SS_LINE_CMP Display Controller Split-Screen Line Compare — Contains the line count at which the lower screen begins in a VGA split-screen mode.	

## Table 4-29. Display Controller Register Summary (Continued)

GX_BASE+ Memory Offset	Туре	Name/Function	
Color Registers			
8360h-8363h	R/W	DC_CURSOR_COLOR	xxxxxxxxh
		Display Controller Cursor Color — Contains the 8-bit indices for the cursor colors.	
8364h-8367h		Reserved	00000000h
8368h-836Bh	R/W	DC_BORDER_COLOR	xxxxxxxxh
		Display Controller Border Color — Contains the 8-bit index for the border or overscan color.	
836Ch-836Fh		Reserved	
Palette and RAM	l Diagnos	stic Registers	
8370h-8373h	R/W	DC_PAL_ADDRESS	xxxxxxxxh
		Display Controller Palette Address — This register should be written with the address (index) location to be used for the next access to the DC_PAL_DATA register.	
3374h-8377h R/W <b>DC_PAL_DATA</b>		xxxxxxxxh	
		Display Controller Palette Data — Contains the data for a palette access cycle.	
8378h-837Bh	R/W	DC_DFIFO_DIAG	xxxxxxxxh
		Display Controller Display FIFO Diagnostic — This register is provided to enable testability of the Display FIFO RAM.	
837Ch-837Fh	R/W	DC_CFIFO_DIAG	xxxxxxxxh
		Display Controller Compression FIFO Diagnostic — This register is provided to enable testability of the Compressed Line Buffer (FIFO) RAM.	

### 4.5.9.1 Configuration and Status Registers

The Configuration and Status Registers group consists of four 32-bit registers located at GX\_BASE+8300h-830Ch. These registers are described below and Table 4-30 gives their bit formats.

- Display Controller Unlock (DC\_UNLOCK)
  - This register is provided to lock the most critical memory-mapped display controller registers to prevent unwanted modification (write operations).
     Read operations are always allowed.
- Display Controller General Configuration (DC\_GENERAL\_CFG)
  - General control bits for the display controller.
- Display Controller Timing Configuration (DC\_TIMING\_CFG)
  - Status and control bits for various display timing functions.
- Display Controller Output Configuration (DC\_OUTPUT\_CFG)
  - Status and control bits for pixel output formatting functions.

Table 4-30. Display Controller Configuration and Status Registers

Bit	Name	Description		
GX_BASE+8300h-8303h		DC_UNLOCK Register (R/W)	Default Value = 00000000h	
31:16	RSVD	Reserved: Set to 0.		
15:0	UNLOCK_ CODE	Unlock Code: This register must be written with the value 4758h in ters. The following registers are protected by the locking mechanism DC_GENERAL_CFG DC_CB_ST_OFFSET, DC_BUF_SIZE, DC_V_TIMING_2 DC_TIMING_CFG, DC_CURS_ST_OFFSET, DC_H_TIMING_1, DC_V_TIMING_3 DC_OUTPUT_CFG, DC_H_TIMNG_2, DC_FP_H_TIMING DC_FB_ST_OFFSET, DC_LINE_DELTA, DC_FP_V_TIMING		
GX_BAS	E+8304h-8307h	DC_GENERAL_CFG (R/W)	Default Value = 00000000h	
31	DDCK	<b>Divide Dot Clock:</b> Divide internal DOTCLK by two relative to PCLF modes utilizing an eight-bit RAMDAC): 0 = Disable; 1 = Enable.	K (pertains only to 16 BPP display	
30	DPCK	<b>Divide Pixel Clock:</b> Divide PCLK by two relative to internal DOTCI pack two pixels together such as 1280x1024 on an external CRT o		
29	VRDY	<b>Video Ready Protocol:</b> 0 = Low speed video port, use with V2.3 at 1 = High speed video port, use with V2.4 and newer.	and older.	
28	VIDE	<b>Video Enable:</b> Motion video port: 0 = Disable; 1 = Enable.		
27	SSLC	Split-screen Line Compare: VGA line compare function: 0 = Disable; 1 = Enable.  When enabled, the internal line counter will be compared to the value programmed in the DC_SS _LINE_CMP register. If it matches, the frame buffer address will be reset to zero. This enables a split screen function.		
26	CH4S	<b>Chain 4 Skip:</b> Allow display controller to read every 4th DWORD fr with the VGA: 0 = Disable; 1 = Enable.	om the frame buffer for compatibility	
25	DIAG	<b>FIFO Diagnostic Mode:</b> This bit allows testability of the on-chip Di Buffer via the diagnostic access registers. A low-to-high transition vers and the Compressed Line Buffer's read pointer. 0 = Normal operations are considered by the compression of the compre	will reset the Display FIFO's R/W point-	
24	LDBL	<b>Line Double:</b> Allow line doubling for emulated VGA modes: 0 = Distribution of the properties of the p	evious line as the data is sent to the dis-	
		should be loaded with half the normal number of lines.	g .2 dood, noneton, me name buner	
23	CKWR	<b>Clock Write:</b> This bit will be output directly to an external clock chip high and low by the software to strobe data into the chip.	·	
00.00	DAO 5010 61	Note that this bit can be used in conjunction with the DACRS[2:0] p		
22:20	DAC_RS[2:0]	<b>RAMDAC Register Selects:</b> This 3-bit field sets the register select next cycle. It is used to allow access to the extended register set of may be used in selecting the frequency for an external clock chip or selections are required, the RAMDAC extended register programmitional select bit must be provided by some other means.	f the RAMDAC. Alternatively, these bits SYNDAC. If more than eight frequency	

Table 4-30. Display Controller Configuration and Status Registers (Continued)

Bit	Name	Description
19 RTPM		Real-Time Performance Monitoring: Allows real-time monitoring of a variety of internal GXm processor signals by multiplexing the signals onto the CLKWR and DACRS[2:0] pins: 0 = Disable (Normal operation); 1 = Enable.
		The CLKWR pin should not be fed to a clock chip or SYNDAC when this mode of operation is used, a different programming scheme should be used for the clock chip using the DACRS[2:0] signals and RAM-DACRD# and RAMDACWR# signals. The selection of output signals is made using bits [27:16] of the DC_BUF_SIZE register. The lower 12 bits of this field will select one of eight outputs for each pin.
18	FDTY	Frame Dirty Mode: Allow entire frame to be flagged as dirty whenever a pixel write occurs to the frame buffer (this is provided for modes that use a linearly mapped frame buffer for which the line delta is not equal to 1024 or 2048 bytes): 0 = Disable; 1 = Enable.
4-7	501/5	When disabled, dirty bits are set according to the Y address of the pixel write.
17	RSVD	Reserved: Set to 0.
16	CMPI	Compressor Insert Mode: Insert one static frame between update frames: 0 = Disable; 1 = Enable.
		An update frame is referred to as a frame in which dirty lines will be allowed to be updated. Conversely, a static frame is referred to as a frame in which dirty lines will not be updated (although the image may not be static, since lines that are not compressed successfully must be retrieved from the uncompressed frame buffer).
15:12	DFIFO HI-PRI END LVL	<b>Display FIFO High Priority End Level:</b> This field specifies the depth of the display FIFO (in 64-bit entries x 4) at which a high-priority request previously issued to the memory controller will end. The value is dependent upon display mode.
		This register should always be non-zero and should be larger than the start level.
11:8	DFIFO HI-PRI START LVL	<b>Display FIFO High Priority Start Level:</b> This field specifies the depth of the display FIFO (in 64-bit entries x 4) at which a high-priority request will be sent to the memory controller to fill up the FIFO. The value is dependent upon display mode.
		This register should always be nonzero and should be less than the high-priority end level.
7:6	DCLK_ MUL	DCLK Multiplier: This 2-bit field specifies the clock multiplier for the input DCLK pin. After the input clock is optionally multiplied, the internal DOTCLK, PCLK, and FPCLK may be divided as necessary.  00 = Forced Low 01 = 1 x DCLK 10 = 2 x DCLK 11 = 4 x DCLK
5	DECE	<b>Decompression Enable:</b> Allow operation of internal decompression hardware: 0 = Disable; 1 = Enable.
4	CMPE	Compression Enable: Allow operation of internal compression hardware: 0 = Disable; 1 = Enable
3	PPC	Pixel Panning Compatibility: This bit has the same function as that found in the VGA.
		Allow pixel alignment to change when crossing a split-screen boundary - it will force the pixel alignment to be 16-byte aligned: 0 = Disable; 1 = Enable.
		If disabled, the previous alignment will be preserved when crossing a split-screen boundary.
2	DVCK	Divide Video Clock: Selects frequency of VID_CLK pin:
		0 = VID_CLK pin frequency is equal to one-half (½) the frequency of the core clock.
		1 = VID_CLK pin frequency is equal to one-fourth (1/4) the frequency of the core clock.
	01:55	Note: Bit 28 (VIDE) must be set to 1 for this bit to be valid.
1	CURE	Cursor Enable: Allow operation of internal hardware cursor: 0 = Disable; 1 = Enable.
0	DFLE	<b>Display FIFO Load Enable:</b> Allow the display FIFO to be loaded from memory: 0 = Disable; 1 = Enable.
		If disabled, no write or read operations will occur to the display FIFO.
		If enabled, a flat panel should be powered down prior to setting this bit low. Similarly, if active, a CRT should be blanked prior to setting this bit low.

Table 4-30. Display Controller Configuration and Status Registers (Continued)

Bit	Name	Description	
GX_BAS	E+8308h-830Bh	DC_TIMING_CFG Register (R/W)	Default Value = xxx00000h
31	VINT (RO)	<b>Vertical Interrupt (Read Only):</b> Is a vertical interrupt pending? 0 = No; This bit is provided to maintain backward compatibility with the VGA. It of 7.	
30	VNA (RO)	<b>Vertical Not Active (Read Only):</b> Is the active part of a vertical scan is or border)? $0 = \text{Yes}$ ; $1 = \text{No}$ .	in progress (i.e. retrace, blanking,
		This bit is provided to maintain backward compatibility with the VGA. It c bit 3.	orresponds to VGA port 3BA/3DA
29	DNA (RO)	<b>Display Not Active (Read Only):</b> Is the active part of a line is being disborder)? $0 = \text{Yes}$ ; $1 = \text{No}$ .	played (i.e. retrace, blanking, or
		This bit is provided to maintain backward compatibility with the VGA. It c bit 0.	orresponds to VGA port 3BA/3DA
28	SENS (RO)	<b>Monitor Sense (Read Only):</b> This bit returns the result of the voltage of from the external RAMDAC. The value will be a low level if one or more of mV level indicating an unloaded line.	
		This bit can be tested repeatedly to determine the loading on the red, gr palette with various values. The BIOS can then determine whether a col attached. If no RAMDAC is attached, the BIOS should assume that a co in color mode. For VGA emulation, read operations to port 3C2 bit 4 are	or, monochrome, or no monitor is lor panel is attached and operate
27	DDCI (RO)	<b>DDC Input (Read Only):</b> This bit returns the value from the DDCIN pin pin 12 of the VGA connector. It is used to provide support for the VESA level DDC1.	
26:20	RSVD	Reserved: Set to 0.	
19:17	PWR_SEQ DELAY	Power Sequence Delay: This 3-bit field sets the delay between edges flogic. The actual delay is this value multiplied by one frame period (typic	ally 16ms).
		Note that a value of zero will result in a delay of only one DOTCLK period	od.
16	BKRT	Blink Rate:  0 = Cursor blinks on every 16 frames for a duration of 8 frames (approxi VGA text characters will blink on every 32 frames for a duration of 16 fra second).	
		1 = Cursor blinks on every 32 frames for a duration of 16 frames (approx VGA text characters blink on every 64 frames for a duration of 32 frames ond).	• • • • • • • • • • • • • • • • • • • •
15	PXDB	<b>Pixel Double:</b> Allow pixel doubling to stretch the displayed image in the $0 = \text{Disable}$ ; $1 = \text{Enable}$ .	horizontal dimension:
		If bit 15 is enabled, timing parameters should be programmed as if no pi frame buffer should be loaded with half the normal pixels per line. Also, DC_BUF_SIZE should be set for the number of bytes to be transferred f displayed.	the FB_LINE_SIZE parameter in
14	INTL	Interlace Scan: Allow interlaced scan mode:	
		0 = Disable (non-interlaced scanning is supported)	
		1 = Enable (If a flat panel is attached, it should be powered down before	,
13	PLNR	VGA Planar Mode: This bit must be set high for all VGA planar display	
12	FCEN	<b>Flat Panel Center:</b> Allows the border and active portions of a scan line panel display via the ENADISP signal. This allows the use of a large bor panel display. 0 = Disable; 1 = Enable.  When disabled, only the normal active portion of the scan line will be qu	rder region for centering the flat
11	FVSP	Flat Panel Vertical Sync Polarity:	
		0 = Causes TFT vertical sync signal to be normally low, generating a high	gh pulse during sync interval.
		1 = Causes TFT vertical sync signal to be normally high, generating a lo	ow pulse during sync interval.
10	FHSP	Flat Panel Horizontal Sync Polarity:	
		$0 = \mathbf{Causes} \ \mathbf{TFT} \ \mathbf{horizontal} \ \mathbf{sync} \ \mathbf{signal} \ \mathbf{to} \ \mathbf{be} \ \mathbf{normally} \ \mathbf{low}, \ \mathbf{generating} \ \mathbf{a}$	
		1 = Causes TFT horizontal sync signal to be normally high, generating a	a low pulse during sync interval.

Table 4-30. Display Controller Configuration and Status Registers (Continued)

Bit	Name	Description		
9	CVSP	CRT Vertical Sync Polarity:		
		0 = Causes CRT VSYNC signal to be normally low, generating a high pulse during the retrace interval.		
		1 = Cause CRT VSYNC signal to be normally high, generating a low pulse during the retrace interval.		
8	CHSP	CRT Horizontal Sync Polarity:		
		0 = Causes CRT HSYNC signal to be normally low, generating a high pulse during the retrace interval.		
		1 = Causes CRT HSYNC signal to be normally high, generating a low pulse during the retrace interval.		
7	BLNK	LNK Blink Enable: Blink circuitry: 0 = Disable; 1 = Enable.		
		If enabled, the hardware cursor will blink as well as any pixels. This is provided to maintain compatibility		
		with VGA text modes. The blink rate is determined by the bit 16 (BKRT).		
6	VIEN	Vertical Interrupt Enable: Generate a vertical interrupt on the occurrence of the next vertical sync pulse		
		0 = Disable, vertical interrupt is cleared;		
		1 = Enable.		
_		This bit is provided to maintain backward compatibility with the VGA.		
5	TGEN	Timing Generator Enable: Allow timing generator to generate the timing control signals for the display.		
		0 = Disable, the Timing Registers may be reprogrammed, and all circuitry operating on the DOTCLK will be reset.		
		1 = Enable, no write operations are permitted to the Timing Registers.		
4	DDCK	DDC Clock: This bit is used to provide the serial clock for reading the DDC data pin. This bit is multiplexed		
4	DDCK	onto the CRTVSYNC pin, but in order for it to have an effect, the VSYE bit must be set low to disable the		
		normal vertical sync. Software should then pulse this bit high and low to clock data into the GXm proces-		
		sor.		
		This feature is provided to allow support for the VESA Display Data Channel standard level DDC1.		
3	BLKE	Blank Enable: Allow generation of the composite blank signal to the display device:		
		0 = Disable; 1 = Enable.		
		When disabled, the BLANK# output will be a static low level. This allows VESA DPMS compliance.		
2	VSYE	Horizontal Sync Enable: Allow generation of the horizontal sync signal to a CRT display device: 0 = Disable; 1 = Enable.		
		When disabled, the HSYNC output will be a static low level. This allows VESA DPMS compliance.		
		Note that this bit only applies to the CRT; the flat panel HSYNC is controlled by the automatic power		
		sequencing logic.		
1	HSYE	Vertical Sync Enable: Allow generation of the vertical sync signal to a CRT display device:		
		0 = Disable; 1 = Enable.		
		When disabled, the VSYNC output will be a static low level. This allows VESA DPMS compliance.		
		Note that this bit only applies to the CRT; the flat panel VSYNC is controlled by the automatic power		
		sequencing logic.		
0	FPPE	Flat Panel Power Enable: On a low-to-high transition this bit will enable the flat panel power-up sequence		
		to begin. This will first turn on VDD to the panel, then start the clocks, syncs, and pixel bus, then turn on the LCD bias voltage, and finally the backlight.		
		On a high-to-low transition, this bit will disable the outputs in the reverse order.		
OV DAG	- 0000L 000F			
	E+830Ch-830Fl			
31:16	RSVD	Reserved: Set to 0.		
15	DIAG	Compressed Line Buffer Diagnostic Mode: This bit will allow testability of the Compressed Line Buffer via the diagnostic access registers. A low-to-high transition will reset the Compressed Line Buffer write		
		pointer. 0 = Disable (Normal operation); 1 = Enable.		
14	CFRW	Compressed Line Buffer Read/Write Select: Enables the read/write address to the Compressed Line		
	<b>3</b>	Buffer for use in diagnostic testing of the RAM.		
		0 = Write address enabled		
		1 = Read address enabled		
13	PDEH	Panel Data Enable High:		
-	· -	0 = The PANEL[17:9] data bus to be driven to a logic low level to effectively blank an attached flat panel		
		display or disable the upper pixel data bus for 16-bit pixel port RAMDACs.		
		1 = If no flat panel is attached, the PANEL[17:9] data bus will be driven with active pixel data. If a flat pane		
		is attached, setting this bit high will have no effect - the upper panel bus will be driven based upon the		
		power sequencing logic.		

Table 4-30. Display Controller Configuration and Status Registers (Continued)

Bit	Name	Description
12	PDEL	Panel Data Enable Low:
		0 = This bit will cause the PANEL[8:0] data bus to be driven to a logic low level to effectively blank an attached flat panel display or disable the lower panel data bus if it is not required.
		1= If no flat panel is attached, the PANEL[8:0] data bus will be driven with active pixel data. If a flat panel is attached, setting this bit high will have no effect – the lower panel bus will be driven based upon the power sequencing logic.
11	PRMP	Palette Re-map:
		0 = The modified codes are sent to the RAMDAC and the external palette should uses the modified mapping.
		1 = Bits [8:1] of the palette output register are routed to the RAMDAC data bus. The GXm processor internal palette RAM may be loaded with 8-bit VGA indices to translate the modified codes stored in display memory so that the RAMDAC data bus will contain the expected indices. The modified codes are used to achieve character blinking in VGA text modes. This mode should be set high set high only for desktop systems with no flat panel attached. It should only be necessary when 8514/A or VESA standard feature con-
		nector support is required.
10	CKSL	Clock Select: Selects output used to clock PANEL[17:0], FPHSYNC, FPVSYNC, and ENADISP output pins.
		1 = PCLK
		0 = FPCLK (based upon the power sequencing logic) This bit should be high when using a 16-bit RAMDAC.
9	FRMS	Frame Rate Modulation Select:
9	FRIVIS	0 = Enables FRM circuitry to change the pattern displayed every frame.
		1 = Enables FRM circuitry to change the pattern displayed every two frames (to allow for slower response
		time liquid crystal materials).
8	3/4ADD	3- or 4-bit Add:
		0 = Enables dither and FRM circuitry to operate on the 3 most significant bits of each color component for 9-bit TFT panels.
		1 = Enables the dither and FRM circuitry to operate on the 4 most significant bits of each color component for 12-bit TFT panels.
7	RSVD	Reserved: Must be set to 0.
6	RSVD	Reserved: Must be set to 0.
5	RSVD	Reserved: Must be set to 0.
4	DITE	<b>Dither Enable:</b> Allow a 2x2 spatial dither on the 3-bit or 4-bit color value. Note that dither will not be supported for 12-bit TFT panels when FRM is enabled. 0 = Disable; 1 = Enable.
3	FRME	<b>Frame-Rate Modulation Enable:</b> Allow FRM to be performed on the 3-bit or 4-bit color value using the next most significant bit after the least significant bit sent to the panel.
		0 = Disable (no FRM performed); 1 = Enable.
2	PCKE	PCLK Enable:
		0 = PCLK is disabled and a low logic level is driven off-chip. Also, the RAMDAC data bus is driven low. 1 = Enable PCLK to be driven off-chip.
		This clock operates the RAMDAC interface.
1	16FMT	16 BPP Format: Selects RGB display mode:
		0 = RGB 5-6-5 mode
		1 = RGB 5-5-5 display mode
		This bit is only significant if 8 BPP is low, indicating 16 BPP mode.
	0000	a ppp //a ppp aday
0	8BPP	8 BPP / 16 BPP Select: 0 = 16-bit per pixel display mode is selected. (Bit 1 of OUTPUT_CONFIG will indicate the format of the 16 bit data.)

### 4.5.10 Memory Organization Registers

The GXm processor utilizes a graphics memory aperture that is up to 4 MB in size. The base address of the graphics memory aperture is stored in the DRAM controller. The graphics memory is made up of the normal uncompressed frame buffer, compressed display buffer, and cursor buffer. Each buffer begins at a programmable offset within the graphics memory aperture.

The various memory buffers are arranged so as to efficiently pack the data within the graphics memory aperture. This requires flexibility in the way that the buffers are arranged when different display modes are in use. The cursor buffer is a linear block so addressing is straightforward. The frame buffer and compressed display buffer are arranged based upon scan lines. Each scan line has a maximum number of valid or active DWORDs and a delta, that when added to the previous line offset, points to the next line. In this way, the buffers may be stored as linear blocks or as logical blocks as may be desired.

The Memory Organization Registers group consists of six 32-bit registers located at GX\_BASE+8310h-8328h. These registers are described below and Table 4-31 gives their bit formats.

- Display Controller Frame Buffer Start Address (DC\_FB\_ST\_OFFSET)
  - Specifies the offset at which the frame buffer starts.
- Display Controller Compression Buffer Start Address (DC\_CB\_ST\_OFFSET)
  - Specifies the offset at which the compressed display buffer starts.
- Display Controller Cursor Buffer Start Address (DC CURS ST OFFSET)
  - Specifies the offset at which the cursor memory buffer starts.
- Display Controller Video Start Address (DC VID\_ST\_OFFSET)
  - Specifies the offset at which the video buffer starts.
- Display Controller Line Delta (DC\_LINE\_DELTA)
  - Stores the line delta for the graphics display buffers.
- Display Controller Buffer Size (DC\_BUF\_SIZE)
  - Specifies the number of bytes to transfer for a line of frame buffer data and the size of the compressed line buffer. (The compressed line buffer will be invalidated if it exceeds the CB\_LINE\_SIZE, bits [15:9].)

Table 4-31. Display Controller Memory Organization Registers

Bit	Name	Description		
GX_BASE+8310h-8313h		DC_FB_ST_OFFSET Register (R/W) Default Value = xxxxxxxx	xh	
31:22	RSVD	Reserved: Set to 0.		
21:0	FB_START _OFFSET	frame buffer. This value may be changed to achieve panning across a virtual desktop or to allow multiple buffering.		
		When this register is programmed to a nonzero value, the compression logic should be disabled. The memory address defined by bits [21:4] will take effect at the start of the next frame scan. The pixel offs defined by bits [3:0] will take effect immediately (in general, it should only change during vertical blanking).	set	
GX_BASE+8314h-8317h		DC_CB_ST_OFFSET Register (R/W) Default Value = xxxxxxxx	xh	
31:22	RSVD	Reserved: Set to 0.		
21:0	CB_START _OFFSET	Compressed Display Buffer Start Offset: This value represents the byte offset of the starting location of the compressed display buffer. Bits [3:0] should always be programmed to zero so that the start offset is aligned to a 16-byte boundary. This value should change only when a new display mode is set due to a change in size of the frame buffer.		

Table 4-31. Display Controller Memory Organization Registers (Continued)

Bit	Name	Description	
GX_BASE	+8318h-831Bh	DC_CUR_ST_OFFSET Register (R/W)	Default Value = xxxxxxxxh
31:22	RSVD	Reserved: Set to 0.	
21:0	CUR_START _OFFSET	Cursor Start Offset: This value represents the byte offset of the start pattern. Bits [1:0] should always be programmed to zero so that the cursor data will be stored as a linear block of data. The active cursor Multiple cursor patterns may be loaded into off-screen memory. The frame. Each cursor pattern will be exactly 256 bytes in size. Note the pattern, the cursor start offset should be set to point to the first disputation, the cursor start offset should be set to point to the first disputation, the cursor start offset should be set to point to the first disputation, the cursor start offset should be set to point to the first disputation, the cursor code for a given pixel is determined by an AND mask and an be stored as two DWORDs, with each DWORD containing the AND word and the XOR masks for 16 pixels in the lower word. DWORDs block of 16 pixels being least significant and the rightmost block be words will be arranged with the leftmost pixels being most significant significant. The 2-bit cursor codes are as follows.  AND XOR Displayed  O Cursor Color 0  O Tursor Color 1  Transparent – Background Pixel  Inverted – Bit-wise Inversion of Background Pixel	e start offset is DWORD aligned. The or will always be 32x32x2 bits in size. It is start offset is loaded at the start of a nat if there is a Y offset for the cursor played line of the cursor pattern. The XOR mask. Each line of a cursor will of masks for 16 pixels in the upper is will be arranged with the leftmost sing most significant. Pixels within and the rightmost pixels being least
GX_BASE	+831Ch-831Fh	Reserved	Default Value = 00000000h
GX_BASE	+8320h-8323h	DC_VID_ST_OFFSET Register (R/W)	Default Value = xxxxxxxxh
31:21	RSVD	Reserved: Set to 0.	
20:0	VID_START _OFFSET	Video Buffer Start Offset Value: This is the value for the Video Bustarting location for Video Buffer. Bits [3:0] should always be progratis aligned to a 16 byte boundary.	•
GX_BASE	+8324h-8327h	DC_LINE_DELTA Register (R/W)	Default Value = xxxxxxxxh
31:22	RSVD	Reserved: Set to 0.	
21:12	CB_LINE_ DELTA	Compressed Display Buffer Line Delta: This value represents not to the starting offset of the previous line, will point to the start of the is used to always maintain a pointer to the starting offset for the coloaded into the display FIFO.	e next compressed line in memory. It
11:10	RSVD	Reserved: Set to 0.	
9:0	FB_LINE_ DELTA	Frame Buffer Line Delta: This value represents number of DWOR offset of the previous line, will point to the start of the next frame bull always maintain a pointer to the starting offset for the frame buffer FIFO.	uffer line in memory. It is used to
GX_BASE	+8328h-832Bh	DC_BUF_SIZE Register (R/W)	Default Value = xxxxxxxxh
31:30	RSVD	Reserved: Set to 0.	
29:16	VID_BUF_ SIZE	<b>Video Buffer Size:</b> These bits set the video buffer size, in 64-byte MB.	segments. The maximum size is 1
15:9	CB_LINE_ SIZE	Compressed Display Buffer Line Size: This value represents the pressed line plus 1. It is used to detect an overflow of the compress larger than 41h or 65Dh since the maximum size of the compresse	sed data FIFO. It should never be
8:0	FB_LINE_ SIZE	Frame Buffer Line Size: This value specifies the number of QWOF each display line from the frame buffer.	RDS (8-byte segments) to transfer for
		If panning is enabled, this value can generally be programmed to the so that enough data is transferred to handle any possible alignmen	
		end of a line will automatically be discarded.	it. Extra pixer data in the fire of at the

#### 4.5.11 Timing Registers

The GXm processor timing registers control the generation of sync, blanking, and active display regions. They provide complete flexibility in interfacing to both CRT and flat panel displays. These registers will generally be programmed by the BIOS from an INT 10h call or by the extended mode driver from a display timing file. Note that the horizontal timing parameters are specified in character clocks, which actually means pixels divided by 8, since all characters are bit mapped. For interlaced display the vertical counter will be incremented twice during each display line, so vertical timing parameters should be programmed with reference to the total frame rather than a single field.

The Timing Registers group consists of six 32-bit registers located at GX\_BASE+8330h-834Ch. These registers are described below and Table 4-32 gives their bit formats.

- Display Controller Horizontal and Total Timing (DC\_H\_TIMING\_1)
  - Contains horizontal active and total timing information.
- Display Controller CRT Horizontal Blanking Timing (DC\_H\_TIMING\_2 Register)
  - Contains CRT horizontal blank timing information.
- Display Controller CRT Sync Timing (DC\_H\_TIMING\_3)

- Contains CRT horizontal sync timing information.
   Note, however, that this register should also be programmed appropriately for flat panel only display since the horizontal sync transition determines when to advance the vertical counter.
- Display Controller Flat Panel Horizontal Sync Timing (DC\_FP\_H\_TIMING)
  - Contains horizontal sync timing information for an attached flat panel display.
- Display Controller Vertical and Total Timing (DC\_V\_TIMING\_1)
  - Contains vertical active and total timing information.
     The parameters pertain to both CRT and flat panel display.
- Display Controller CRT Vertical Blank Timing (DC\_V\_TIMING\_2)
  - Contains vertical blank timing information.
- Display Controller CRT Vertical Sync Timing (DC\_V\_TIMING\_3)
  - Contains CRT vertical sync timing information.
- Display Controller Flat Panel Vertical Sync Timing (DC\_FP\_V\_TIMING)
  - Contains flat panel vertical sync timing information.

Table 4-32. Display Controller Timing Registers

Bit	Name	Description	
GX_BASE	+8330h-8333h	DC_H_TIMING_1 Register (R/W)	Default Value = xxxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:19	H_TOTAL	Horizontal Total: This field represents the total number of chaminus 1. Note that the value is necessarily greater than the H_der pixels and blanked pixels. For flat panels, this value will ne programmed with the pixel count minus 1, although bits [18:16] programmable on 8-pixel boundaries only.	_ACTIVE field because it includes borever change. The field [26:16] may be
18:16	RSVD	Reserved: These bits are readable and writable but have no	effect.
15:11	RSVD	Reserved: Set to 0.	
10:3	H_ACTIVE	Horizontal Active: This field represents the total number of c tion of a scan line minus 1. The field [10:0] may be programmed although bits [2:0] are ignored. The active count is programmed that for flat panels, if this value is less than the panel active hor parameters H_BLANK_START, H_BLANK_END, H_SYNC_STREDUCED by the value of H_ADJUST (or the value of H_PANEL centering.	ed with the pixel count minus 1, able on 8-pixel boundaries only. Note prizontal resolution (H_PANEL), the TART, and H_SYNC_END should be
2:0	RSVD	Reserved: These bits are readable and writable but have no	effect.
Note: Not	e also that for simult	aneous CRT and flat panel display the H_ACTIVE and H_TOTAL	parameters pertain to both.
GX_BASE	+8334h-8337h	DC_H_TIMING_2 Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:19	H_BLK_END	Horizontal Blank End: This field represents the character cloing signal becomes inactive minus 1. The field [26:16] may be minus 1, although bits [18:16] are ignored. The blank end pos boundaries only.	programmed with the pixel count
18:16	RSVD	Reserved: These bits are readable and writable but have no	effect.
15:11	RSVD	Reserved: Set to 0.	

### Table 4-32. Display Controller Timing Registers (Continued)

Bit	Name	Description
10:3	H_BLK_START	Horizontal Blank Start: This field represents the character clock count at which the horizontal blanking signal becomes active minus 1. The field [10:0] may be programmed with the pixel count minus 1, although bits [2:0] are ignored. The blank start position is programmable on 8-pixel boundaries only.
2:0	RSVD	Reserved: These bits are readable and writable but have no effect.

**Note:** A minimum of four character clocks is required for the horizontal blanking portion of a line in order for the timing generator to function correctly.

GX_BASE	+8338h-833Bh	DC_H_TIMING_3 Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:19	H_SYNC_END	Horizontal Sync End: This field represents the character clock sync signal becomes inactive minus 1. The field [26:16] may be minus 1, although bits [18:16] are ignored. The sync end positionaries only.	e programmed with the pixel count
18:16	RSVD	Reserved: These bits are readable and writable but have no e	effect.
15:11	RSVD	Reserved: Set to 0.	
10:3	H_SYNC_START	Horizontal Sync Start: This field represents the character clock count at which the CRT horizont sync signal becomes active minus 1. The field [10:0] may be programmed with the pixel count min 1, although bits [2:0] are ignored. The sync start position is programmable on 8-pixel boundaries only.	
2:0	RSVD	Reserved: These bits are readable and writable but have no e	effect.

**Note:** This register should also be programmed appropriately for flat panel only display since the horizontal sync transition determines when to advance the vertical counter.

GX_BASE-	-833Ch-833Fh	C_FP_H_TIMING Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:16	FP_H_SYNC _END	Flat Panel Horizontal Sync End: This field represents the pixel zontal sync signal becomes inactive minus 1.	count at which the flat panel hori-
15:11	RSVD	Reserved: Set to 0.	
10:0	FP_H_SYNC _START	Flat Panel Horizontal Sync Start: This field represents the pixe zontal sync signal becomes active minus 1.	I count at which the flat panel hori-

**Note:** All values are specified in pixels rather than character clocks to allow precise control over sync position. Note, however, that for flat panels which combine two pixels per panel clock, these values should be odd numbers (even pixel boundary) to guarantee that the sync signal will meet proper setup and hold times.

GX_BASE	+8340h-8343h	DC_V_TIMING_1 Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:16	V_TOTAL	<b>Vertical Total:</b> This field represents the total number of lines for that the value is necessarily greater than the V_ACTIVE field b blanked lines. If the display is interlaced, the total number of line be an even number.	ecause it includes border lines and
15:11	RSVD	Reserved: Set to 0.	
10:0	V_ACTIVE	Vertical Active: This field represents the total number of lines scan minus 1. Note that for flat panels, if this value is less than (V_PANEL), the parameters V_BLANK_START, V_BLANK_EN V_SYNC_END should be reduced by the following value (V_AL V_ADJUST = (V_PANEL - V_ACTIVE) / 2  If the display is interlaced, the number of active lines should be number.	the panel active vertical resolution D, V_SYNC_START, and DJUST) to achieve vertical centering:

Note: All values are specified in lines.

GX_BASE	+8344h-8347h	DC_V_TIMING_2 Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:16	V_BLANK_END	<b>Vertical Blank End:</b> This field represents the line at which the vertical blank in active minus 1. If the display is interlaced, no border is supported to V_TOTAL.	5 5
15:11	RSVD	Reserved: Set to 0.	

### Table 4-32. Display Controller Timing Registers (Continued)

Bit	Name	Description
10:0	V_BLANK_ START	<b>Vertical Blank Start:</b> This field represents the line at which the vertical blanking signal becomes active minus 1. If the display is interlaced, this value should be programmed to V_ACTIVE plus 1.

**Note:** All values are specified in lines. For interlaced display, no border is supported, so blank timing is implied by the total/active timing.

GX_BASE+8348h-834Bh		DC_V_TIMING_3 Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:16	V_SYNC_END	<b>Vertical Sync End:</b> This field represents the line at which the CRT v inactive minus 1.	vertical sync signal becomes
15:11	RSVD	Reserved: Set to 0.	
10:0	V_SYNC_START	Vertical Sync Start: This field represents the line at which the CRT active minus 1. For interlaced display, note that the vertical counter is line and since there are an odd number of lines, the vertical sync pulline for one field and at the end of a line for the subsequent field.	incremented twice during each

Note: All values are specified in lines.

GX_BASE	-834Ch-834Fh	DC_FP_V_TIMING Register (R/W)	Default Value = xxxxxxxxh
31:27	RSVD	Reserved: Set to 0.	
26:16	FP_V_SYNC _END	Flat Panel Vertical Sync End: This field represents the line at wh nal becomes inactive minus 2. Note that the internal flat panel ver panel horizontal sync prior to being output to the panel.	. , , ,
15:11	RSVD	Reserved: Set to 0.	
10:0	FP_VSYNC _START	Flat Panel Vertical Sync Start: This field represents the line at w sync signal becomes active minus 2. Note that the internal flat panel horizontal sync prior to being output to the panel.	
Mata. All.	aluge are enecified i	- Bara	

Note: All values are specified in lines.

#### 4.5.12 Cursor Position Registers

The Cursor Position Registers contain pixel coordinate information for the cursor. These values are not latched by the timing generator until the start of the frame to avoid tearing artifacts when moving the cursor.

The Cursor Position group consists of four 32-bit registers located at GX\_BASE+8350h-835Ch. These registers are described below and Table 4-33 gives their bit formats.

- Display Controller Cursor X Position (DC\_CURSOR\_X)
  - Contains the X position information of the hardware cursor.

- Display Controller Vertical Line Count (DC\_V\_LINE\_CNT)
  - This register is read only. It provides the current scanline for the display. It is used by software to time update of the frame buffer to avoid tearing artifacts.
- Display Controller Cursor Y Position (DC\_CURSOR\_Y)
  - Contains the Y position information of the hardware cursor.
- Display Controller Split-Screen Line Compare (DC\_SS\_LINE\_CMP)
  - Contains the line count at which the lower screen begins in a VGA split-screen mode.

Table 4-33. Display Controller Cursor Position Registers

Bit	Name	Description	
GX_BASE	+8350h-8353h	DC_CURSOR_X Register (R/W)	Default Value = xxxxxxxxx
31:16	RSVD	Reserved: Set to 0.	
15:11	X_OFFSET	X Offset: This field represents the X pixel offset within the 32x32 portion of the cursor is to begin. Normally, this value is set to zero for cursors for which the "hot spot" is not at the left edge of the pathe rightmost pixels of the cursor only as the cursor moves close	to display the entire cursor pattern, bu attern, it may be necessary to display
10:0	CURSOR_X	<b>Cursor X:</b> This field represents the X coordinate of the pixel at w is to be displayed. This value is referenced to the screen origin (Corner of the screen.	
GX_BASE	+8354h-8357h	DC_V_LINE_CNT Register (RO)	Default Value = xxxxxxxxx
31:11	RSVD	Reserved (Read Only)	
10:0	V_LINE_CNT (RO)	Vertical Line Count (Read Only): This value is the current scan	line of the display.
		ster is driven directly off of the DOTCLK, and consequently it is not s register twice and compare the result to ensure that the value is	
GX_BASE	+8358h-835Bh	DC_CURSOR_Y Register (R/W)	Default Value = xxxxxxxx
31:16	RSVD	Reserved: Set to 0.	
15:11	Y_OFFSET	Y Offset: This field represents the Y line offset within the 32x32 oportion of the cursor is to begin. Normally, this value is set to zero for cursors for which the "hot spot" is not at the top edge of the pathe bottommost lines of the cursor only as the cursor moves closs that if this value is nonzero, the CUR_START_OFFSET must be a displayed.	to display the entire cursor pattern, bu attern, it may be necessary to display e to the top edge of the display. <u>Note</u>
10	RSVD	Reserved: Set to 0.	
9:0	CURSOR_Y	<b>Cursor Y:</b> This field represents the Y coordinate of the line at whi to be displayed. This value is referenced to the screen origin (0,0 ner of the screen.	
		This field is alternately used as the line-compare value for a newly This is necessary for VGA programs that change the start offset in	
		this function, the hardware cursor function should be disabled.	, ,
GX_BASE	+835Ch-835Fh		n the middle of a frame. In order to use
<b>GX_BASE</b> 31:11	+835Ch-835Fh RSVD	this function, the hardware cursor function should be disabled.	, ,
	1	this function, the hardware cursor function should be disabled.  DC_SS_LINE_CMP Register (R/W)	n the middle of a frame. In order to use

### 4.5.13 Color Registers

These registers are used in 8 BPP display mode with an external RAMDAC for passing cursor and border color indices to the palette in the RAMDAC. For the flat panel color translation, the cursor and border color data is loaded into palette extensions as described in the Palette Access Registers section.

The Color Registers group consists of two 32-bit registers located at GX\_BASE+8360h-8368h. These registers are described below and Table 4-34 gives their bit formats.

- Display Controller Cursor Color (DC\_CURSOR\_COLOR)
  - Contains the 8-bit indices for the cursor colors.
- Display Controller Border Color (DC\_BORDER\_COLOR)

Contains the 8-bit index for the border or overscan color.

Table 4-34. Display Controller Color Registers

Bit	Name	Description	
GX_BASE+8360h-8363h		DC_CURSOR_COLOR Register (R/W)	Default Value = xxxxxxxxh
31:16	RSVD	Reserved: Set to 0.	
15:8	CURS_CLR_1	<b>Cursor Color 1:</b> This is the 8-bit index to the external palette for a reserved or static color.	the cursor color 1. It should point to
7:0	CURS_CLR_0	Cursor Color 0: This is the 8-bit index to the external palette for a reserved or static color.	the cursor color 0. It should point to
GX_BASE+8364h-8367h			
GX_BASE	+8364h-8367h	Reserved	Default Value = 00000000h
_	+8364h-8367h +8368h-836Bh	Reserved DC_BORDER_COLOR Register (RO)	Default Value = 00000000h  Default Value = xxxxxxxxh
_			
GX_BASE	+8368h-836Bh	DC_BORDER_COLOR Register (RO)	Default Value = xxxxxxxxxh

#### 4.5.14 Palette Access Registers

These registers are used for accessing the internal palette RAM and extensions. In addition to the standard 256 entries for 8 BPP color translation, the GXm processor palette has extensions for cursor colors and overscan (border) color.

The Palette Access Register group consists of four 32-bit registers located at GX\_BASE+8370h-837Ch. These registers are described below and Table 4-35 gives their bit formats.

- Display Controller Palette Address (DC\_PAL\_ADDRESS)
  - This register should be written with the address (index) location to be used for the next access to the DC\_PAL\_DATA register.

- Display Controller Palette Data (DC\_PAL\_DATA)
  - Contains the data for a palette access cycle.
- Display Controller Display FIFO Diagnostic (DC\_DFIFO\_DIAG)
  - This register is provided to enable testability of the Display FIFO RAM.
- Display Controller Compression FIFO Diagnostic (DC\_CFIFO\_DIAG)
  - This register is provided to enable testability of the Compressed Line Buffer (FIFO) RAM.

Table 4-35. Display Controller Palette and RAM Diagnostic Registers

	Table 4-3	35. Display Controller Palette and RAM Diagnost	tic Registers
Bit	Name	Description	
GX_BASE	+8370h-8373h	DC_PAL_ADDRESS Register (R/W)	Default Value = xxxxxxxxh
31:9	RSVD	Reserved: Set to 0.	
8:0	PALETTE_ADDR	Palette Address: This 9-bit field specifies the address to be us DC_PAL_DATA register. Each access to the data register will a address register. If non-sequential access is made to the palett loaded between each non-sequential data block. The address Address Color Oh - FFh Standard Palette Colors 100h Cursor Color 0 101h Cursor Color 1 102h Reserved 103h Reserved 104h Overscan Color 105h - 1FFh Not Valid Note that in general, 18-bit values will be loaded for all color extis active, only the appropriate most significant bits will be used mode is active and an external RAMDAC is used, the cursor in DC_CURSOR_COLOR register. The border index will be obtain register.	utomatically increment the palette te, the address register must be ranges are as follows.  The sensions are as follows.  The sensions are as follows are as follows.  The sensions are as follows are as follows.
GX_BASE	+8374h-8377h	DC_PAL_DATA Register (R/W)	Default Value = xxxxxxxxx
31:18	RSVD	Reserved: Set to 0.	
17:0	PALETTE_DATA	Palette Data: This 18-bit field contains the read or write data for	or a palette access.
effe DC	ct should go unnotice _PAL_ADDRESS reg	the palette RAM occurs, the previous output value will be held for and will provide for sparkle-free update. Prior to a read or write ister should be loaded with the appropriate address. The address of for sequential access, the address register need only be loaded.	e to this register, the s automatically increments after each
GX_BASE	+8378h-837Bh	DC_DFIFO_DIAG Register (R/W)	Default Value = xxxxxxxxx

# Table 4-35. Display Controller Palette and RAM Diagnostic Registers (Continued)

Bit	Name	Description
31:0	DISPLAY FIFO DIAGNOSTIC DATA	Display FIFO Diagnostic Read or Write Data: Before this register is accessed, the DIAG bit in DC_GENERAL_CFG register should be set high and the DFLE bit should be set low. Since, each FIFO entry is 64 bits, an even number of write operations should be performed. Each pair of write operations will cause the FIFO write pointer to increment automatically. After all write operations have been performed, a single read of don't care data should be performed to load data into the output latch. Each subsequent read will contain the appropriate data which was previously written. Each pair of read operations will cause the FIFO read pointer to increment automatically. A pause of at least four core clocks should be allowed between subsequent read operations to allow adequate time for the shift to take place.
GX_BASE	+837Ch-837Fh	DC_CFIFO_DIAG Register (R/W) Default Value = xxxxxxxxxh
31:0	COMPRESSED FIFO DIAGNOS- TIC DATA	Compressed Data FIFO Diagnostic Read or Write Data: Before this register is accessed, the DIAG bit in DC_GENERAL_CFG register should be set high and the DFLE bit should be set low. Also, the DIAG bit in DC_OUTPUT_CFG should be set high and the CFRW bit in DC_OUTPUT_CFG should be set low. After each write, the FIFO write pointer will automatically increment. After all write operations have been performed, the CFRW bit of DC_OUTPUT_CFG should be set high to enable read addresses to the FIFO and a single read of don't care data should be performed to load data into the output latch. Each subsequent read will contain the appropriate data which was previously written. After each read, the FIFO read pointer will automatically increment.

#### 4.5.15 CS5530 Display Controller Interface

As previously stated in Section 1.6 "Geode GXM/CS5530 System Designs" on page 11, the GXm processor interfaces with either the CS5530 I/O companion chip. This section will discuss the specifics on signal connections between the two devices with regards to the display controller.

When the GXm processor is used in a system with the CS5530 I/O companion chip, the need for an external RAMDAC is eliminated. The CS5530 contains the DACs, a video accelerator engine, and the TFT interface.

A GXm processor and CS5530-based system supports both portable and desktop configurations. Figure 4-16 shows the signal connections for both types of systems.





Figure 4-16. Display Controller Signal Connections

#### 4.5.15.1 CS5530 Video Port Data Transfer

VID\_VAL indicates that the GXm processor has placed valid data on VID\_DATA[7:0]. VID\_RDY indicates that the CS5530 is ready to accept the next byte of video data.

VID\_DATA[7:0] is advanced when both VID\_VAL and VID\_RDY are asserted. VID\_RDY is driven one clock early to the GXm processor while VID\_VAL is driven coincident with VID\_DATA[7:0]. A sample interface functional timing diagram is shown in Figure 4-17.



Note: VID\_CLK = CORE\_CLK/2

Figure 4-17. Video Port Data Transfer (CS5530)

#### 4.6 PCI CONTROLLER

The GXm processor includes an integrated PCI controller with the following features.

#### 4.6.1 X-Bus PCI Slave

- 16-byte PCI write buffer
- 16-byte PCI read buffer from X-bus
- · Supports cache line bursting
- Write/Inv line support
- · Pacing of data for read or write operations with X-bus
- No active byte enable transfers supported

#### 4.6.2 X-Bus PCI Master

- 16 byte X-bus to PCI write buffer
- Configuration read/write Support
- Int Acknowledge support
- Lock conversion
- Support fast back-to-back cycles as slave

#### 4.6.3 PCI Arbiter

- Fixed, rotating, hybrid, or ping-pong arbitration (programmable)
- · Support four masters, three on PCI
- Internal REQ for CPU
- Master retry mask counter
- Master dead timer
- · Resource or total system lock support

#### 4.6.4 Generating Configuration Cycles

Configuration space is a physical address space unique to PCI. Configuration Mechanism #1 must be used by software to generate configuration cycles. Two DWORD I/O locations are used in this mechanism. The first DWORD location (CF8h) references a read/write register that is named CONFIG\_ADDRESS. The second DWORD address (CFCh) references a register CONFIG\_DATA. The general method for accessing configuration space is to write а value CONFIG\_ADDRESS that specifies the PCI bus, device on that bus, and configuration register in that device being accessed. A read or write to CONFIG\_DATA will then cause the bridge to translate that CONFIG\_ADDRESS value to the requested configuration cycle on the PCI bus.

#### 4.6.5 Generating Special Cycles

A special cycle is a broadcast message to the PCI bus. Two hardcoded special cycle messages are defined in the command encode: HALT and SHUTDOWN. Software can also generate special cycles by using special cycle generation for configuration mechanism #1 as described in the PCI Specification 3.6.4.1.2 and briefly described here. To initiate a special cycle from software, the host must write a value to CONFIG\_ADDRESS encoded as shown in Table 4-36.

The next value written to CONFIG\_DATA is the encoded special cycle. Type 0 or Type 1 conversion will be based on the Bus Bridge number matching the GXm processor's bus number of 00h.

Table 4-36. Special-Cycle Code to CONFIG ADDRESS

31	30 24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
1	00000	0		Bus	No.	= Br	idge			1	1	1	1	1	1	1	1	0	0	0	0	0	0	Т	Т
CONFIG ENABLE	RSVD			BU	S NI	JMB	ER			DE	VICI	E NU	JMB	ER		NCTI JMBE		RE	GIS	STER	NU	MBE	ΞR	TRA LATI TYI	ION

Note: See Table 4-37 on page 156, bits [1:0] for translation type.

### 4.6.6 PCI Configuration Space Control Registers

There are two registers in this category. CONFIG\_ADDRESS and CONFIG\_DATA.

The CONFIG\_ADDRESS register contains the address information for the next configuration space access to CONFIG\_DATA. Only DWORD accesses are permitted to

this register all others will be forwarded as normal I/O cycles to the PCI bus.

The CONFIG\_DATA register contains the data that is sent or received during a PCI configuration space access.

Table 4-37 gives the bit formats for these two registers.

**Table 4-37. PCI Configuration Registers** 

Bit	Name	Description	
I/O Offset	0CF8h-0CFBh	CONFIG_ADDRESS Register (R/W)	Default Value = 00000000h
31	CFG_EN	Config Enable: Determines when accesses should be translate bus, or treated as a normal I/O operation. This register will be up ations to the CONFIG_ADDRESS. Any other accesses are treat allow I/O devices to use BYTE or WORD registers at the same a bit 31 is set high, subsequent accesses to CONFIG_DATA are the cycles.  1 = Generate configuration cycles 0 = Normal I/O cycles	odated only on full DWORD I/O oper- ted as normal I/O cycles in order to address an remain unaffected. Once
30:24	RSVD	Reserved: Set to 0.	
23:16	BUS	Bus: Specifies a PCI bus number in the hierarchy of 1 to 256 bu	uses.
15:11	DEVICE	<b>Device:</b> Selects a device on a specified bus. A device value of 0 the bus number is also 00h. DEVICE values of 01h to 15h will be the 32 possible devices are supported. A DEVICE value of 0000 of 10101b will map to AD[31].	mapped to AD[31:11], so only 21 of
10:8	FUNCTION	Function: Selects a function in a multi-function device.	
7:2	REGISTER	Register: Chooses a configuration DWORD space register in the	ne selected device.
1:0	π	Translation Type Bits: These bits indicate if the configuration at translation through other bridges to another PCI bus. When an a address and the specified bus number matches the GXm procestype 0 translation takes place.  For a Type 0 translation, the CONFIG_ADDRESS register value PCI bus. Note that bits 10:2 are passed unchanged. The DEVICE.	access occurs to the CONFIG_DATA ssor's bus number (00h), then a ses are translated to AD lines on the CE value is mapped to one of 21 AD
		lines. The translation type bits are set to 00 to indicate a transact When an access occurs to the CONFIG_DATA address and the (Type 1), the GXm processor passes this cycle to the PCI bus b CONFIG_ADDRESS register onto the AD lines during the address the translation type bits AD[1:0] to 01.	specified bus number is not 00h y copying the contents of the
I/O Offset	0CFCh-0CFFh	CONFIG_DATA (R/W)	Default Value = 00000000h
31:0	CONFIG_DATA	Configuration Data Register: Contains the data that is sent or space access. The register accessed is determined by the value ter. The CONFIG_DATA register supports BYTE, WORD, or DW ister, bit 31 of the CONFIG_ADDRESS register must be set to 0 be done. Configuration cycles are performed when bit 31 of the to 1	e in the CONFIG_ADDRESS regis- /ORD accesses. To access this reg- and a full DWORD I/O access must

### 4.6.7 PCI Configuration Space Registers

To access the internal PCI configuration registers of the GXm processor, the Configuration Address Register (CONFIG\_ADDRESS) must be written as a DWORD using the format shown in Table 4-38. Any other size will be interpreted as an I/O write to Port 0CF8h. Also, when entering the Configuration Index, only the six most signifi-

cant bits of the offset are used, and the two least significant bits must be 00b.

Table 4-39 summarizes the registers located within the Configuration Space. The tables that follow, give detailed register/bit formats.

Table 4-38. Format for Accessing the Internal PCI Configuration Registers

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
1			RES	SER\	/ED			0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	O	onfi	gura	tion	Inde	X	0	0

Table 4-39. PCI Configuration Space Register Summary

Index	Туре	Name	Default Value
00h-01h	RO	Vendor Identification	1078h
02h-03h	RO	Device Identification	0001h
04h-05h	R/W	PCI Command	0007h
06h-07h	R/W	Device Status	0280h
08h	RO	Revision Identification	00h
09h-0Bh	RO	Class Code	060000h
0Ch	RO	Cache Line Size	00h
0Dh	R/W	Latency Timer	0Dh
0Eh-3Fh		Reserved	00h
40h	R/W	PCI Control Function 1	00h
41h	R/W	PCI Control Function 2	96h
42h		Reserved	00h
43h	R/W	PCI Arbitration Control 1	80h
44h	R/W	PCI Arbitration Control 2	00h
45h-FFh		Reserved	00h

Table 4-40. PCI Configuration Registers

Bit	Name	Description	
Index 00h-	-01h	Vendor Identification Register (RO)	Default Value = 1078h
31:0	VID (RO)	<b>Vendor Identification Register (Read Only):</b> The combination of this value identifies any PCI device. The Vendor ID is the ID given to national Semicor PCI SIG.	
Index 02h-	-03h	Device Identification Register (RO)	Default Value = 0001h
31:0	DIR (RO)	<b>Device Identification Register (Read Only):</b> This value along with the vend PCI device.	dor ID uniquely identifies any
Index 04h-	-05h	PCI Command Register (R/W)	Default Value = 0007h
15:10	RSVD	Reserved: Set to 0.	
9	FBE	Fast Back-to-Back Enable: As a master, the GXm processor does not sup	port this function.
		This bit returns 0.	
8	SERR	SERR# Enable: This is used as an output enable gate for the SERR# drive	r.
7	WAT	Wait Cycle Control: GXm processor does not do address/ data stepping.	
		This bit is always set to 0.	
6	PE	Parity Error Response:  0 = GXm processor ignores parity errors on the PCI bus.  1 = GXm processor checks for parity errors.	
5	VPS	VGA Palette Snoop: GXm processor does not support this function. This bit is always set to 0.	
4	MS	<b>Memory Write and Invalidate Enable:</b> As a master, the GXm processor do This bit is always set to 0.	es not support this function.
3	SPC	<b>Special Cycles:</b> GXm processor does not respond to special cycles on the This bit is always set to 0.	PCI bus.
2	ВМ	Bus Master:  0 = GXm processor does not perform master cycles on the PCI.  1 = GXm processor can act as a bus master on the PCI.	
1	MS	Memory Space: GXm processor will always respond to memory cycles on This bit is always set to 1.	the PCI.
0	IOS	I/O Space: GXm processor will not respond to I/O accesses from the PCI. This bit is always set to 1.	
Index 06h-	-07h	PCI Device Status Register (RO, R/W Clear)	Default Value = 0280h
15	DPE	Detected Parity Error: When a parity error is detected, this bit is set to 1.	Dolaali Valao - 020011
15	DIL	This bit can be cleared to 0 by writing a 1 to it.	
14	SSE	Signaled System Error: This bit is set whenever SERR# is driven active.	
13	RMA	Received Master Abort: This bit is set whenever a master abort cycle occumulation whenever a PCI cycle is not claimed except for special cycles.  This bit can be cleared to 0 by writing a 1 to it.	irs. A master abort will occur
12	RTA	Received Target Abort: This bit is set whenever a target abort is received master of the cycle.	while the GXm processor is
		This bit can be cleared to 0 by writing a 1 to it.	
11	STA	<b>Signaled Target Abort:</b> This bit is set whenever the GXm processor signal abort is signaled when an address parity occurs for an address that hits in th space.  This bit can be cleared to 0 by writing a 1 to it.	
10:9	DT	Devise Timing:  00 = Fast 01 = Medium 10 = Slow 11 = Reserved The GXm processor performs medium DEVSEL# active for addresses that address space. These two bits are always set to 01.	hit into the GXm processor

Table 4-40. PCI Configuration Registers (Continued)

Bit	Name	Description	
8	DPD	Data Parity Detected: This bit is set when three conditions are met.  1) GXm processor asserted PERR# or observed PERR# asserted; 2) GXm processor is the master for the cycle in which the PERR# occurred.	ed; and
		3) PE (bit 6 of Command Register) is enabled. This bit can be cleared to 0 by writing a 1 to it.	
7	FBS	Fast Back-to-Back Capable: As a target, the processor is capable of acc	centing Fast Back-to-Back
,	1 00	transactions.  This bit is always set to 1.	Septing I ast back-to-back
6:0	RSVD	Reserved: Set to 0.	
Index 08h	11075	Revision Identification Register (RO)	Default Value = 00h
7:0	RID (RO)	Revision ID (Read Only): This register contains the revision number of the	
Index 09h-	` '	Class Code Register (RO)	Default Value = 060000h
23:16	CLASS	Class Code: The class code register is used to identify the generic function	
		GXm processor is classified as a host bridge device (06).	on of the device. The
15:0	RSVD (RO)	Reserved (Read Only)	
Index 0Ch		Cache Line Size Register (RO)	Default Value = 00h
7:0	CACHELINE	Cache Line Size (Read Only): The cache line size register specifies the of 32-bit words. This function is not supported in the GXm processor.	system cacheline size in units
Index 0Dh		Latency Timer Register (R/W)	Default Value = 00h
7:5	RSVD	Reserved: Set to 0.	
		from a slave the does not responded to the master. If the register value is abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle will also stop the c	ounter will reset on each valid ive, then the slave is consid- in with a master abort and flag ever by a slave device that con-
Index 0Eh-	3Fh	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore	ounter will reset on each valid ive, then the slave is consid- on with a master abort and flag ever by a slave device that con-
Index 0Eh- Index 40h	3Fh	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle will also stop the cy	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that conwith a master abort.  Default Value = 00h
	<b>3Fh</b> RSVD	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle will respond to the counter of the c	ounter will reset on each valid ive, then the slave is consid- on with a master abort and flag ever by a slave device that con- with a master abort.
Index 40h	-	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle verserved  Reserved  PCI Control Function 1 Register (R/W)	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that conwith a master abort.  Default Value = 00h
<b>Index 40h</b> 7	RSVD	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that conwith a master abort.  Default Value = 00h  Default Value = 00h
<b>Index 40h</b> 7	RSVD	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle verserved  PCI Control Function 1 Register (R/W)  Reserved: Set to 0.  Single Write Mode: PCI slave supports:  0 = Multiple PCI write cycles  1 = Single cycle write transfers on the PCI bus. The slave will perform a tax	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that conwith a master abort.  Default Value = 00h  Default Value = 00h
7 6	RSVD SW	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle version of t	ounter will reset on each valid ive, then the slave is consident with a master abort and flag ever by a slave device that conwith a master abort.  Default Value = 00h  Default Value = 00h
<b>Index 40h</b> 7	RSVD	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle version of t	ounter will reset on each valid ive, then the slave is consident with a master abort and flag ever by a slave device that conwith a master abort.  Default Value = 00h  Default Value = 00h
7 6	RSVD SW	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle version of t	ounter will reset on each valid rive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h
7 6	RSVD SW	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle version of the countries of the cycle version of the c	ounter will reset on each valid rive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h
7 6	RSVD SW	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle with the cycle of th	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first error with the first error.  The data in the PCI master
7 6	RSVD SW	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle with the cycle of th	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first ers. The data in the PCI master st active indicating the need to
7 6	RSVD SW SR RXBNE	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle of the	ounter will reset on each valid rive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first ers. The data in the PCI master st active indicating the need to buffered data.
7 6 5	RSVD SW SR RXBNE	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle with the cycle of th	ounter will reset on each valid rive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first ers. The data in the PCI master at active indicating the need to confered data.  Enable.  Enable.
7 6 5 4	RSVD SW SR RXBNE	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle with the cycle of th	ounter will reset on each valid rive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first ers. The data in the PCI master at active indicating the need to confered data.  Enable.  Enable.
7 6 5 4	RSVD SW SR RXBNE	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle with the cycle of th	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first ers. The data in the PCI master at active indicating the need to puffered data.  Enable.  Km processor: used.
7 6 5 4	RSVD SW SR RXBNE	abled. Otherwise, Timer represents the 5 MSBs of an 8-bit counter. The c data transfer. If the counter expires before the next TRDY# is received act ered to be incapable of responding, and the master will stop the transactio an SERR# active. This would also keep the master from being retried fore tinues to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries. In these cases, the master will also stop the cycle versions to issue retries.  Reserved  PCI Control Function 1 Register (R/W)  Reserved: Set to 0.  Single Write Mode: PCI slave supports:  0 = Multiple PCI write cycles  1 = Single cycle write transfers on the PCI bus. The slave will perform a tadata transferred.  Single Read Mode: PCI slave supports:  0 = Multiple PCI read cycles.  1 = Single cycle read transfers on the PCI bus. The slave will perform a tadata transferred.  Force Retry when X-Bus Buffers are Not Empty:  0 = PCI slave accepts the PCI cycle with data in the PCI master write buffer write buffers will not be affected or corrupted. The PCI master holds request access the PCI bus.  1 = PCI slave retries cycles if the PCI master X-bus write buffers contain to PCI slave Write Buffer Enable: PCI slave write buffers: 0 = Disable; 1 = PCI Cache Line Read Enable: Read operations from the PCI into the GX 0 = Single cycle unless a read multiple or memory read line command is to 1 = Cause a cache line read to occur.  X-Bus Burst Enable: PCI slave acting as a master performs burst cycles	ounter will reset on each valid ive, then the slave is consider with a master abort and flag ever by a slave device that consider with a master abort.  Default Value = 00h  Default Value = 00h  arget disconnect with the first ers. The data in the PCI master at active indicating the need to puffered data.  Enable.  Km processor: used.

Table 4-40. PCI Configuration Registers (Continued)

Bit	Name	Description
Index 41h		PCI Control Function 2 Register (R/W) Default Value = 96h
7	RSVD	Reserved: Set to 0.
6	RW_CLK	<b>RAW Clock:</b> A debug signal used to view internal clock operation. 0 = Disable; 1 = Enable.
5	PFS	<b>PERR# forces SERR#:</b> PCI master drives an active SERR# anytime it also drives or receives an active PERR#: 0 = Disable; 1 = Enable.
4	XWB	X-Bus to PCI Write Buffer: Enable GXm processor PCI master's X-Bus write buffers (non-locked memory cycles are buffered, I/O cycles and lock cycles are not buffered): 0 = Disable; 1 = Enable.
3:2	SDB	Slave Disconnect Boundary: PCI slave issues a disconnect with data when it crosses line boundary:  00 = 128 bytes 01 = 256 bytes 10 = 512 bytes 11 = 1024 bytes Works in conjunction with bit 1.
1	SDBE	Slave Disconnect Boundary Enable:  0 = PCI slave disconnects on boundaries set by bits [3:2].  1 = PCI disconnects on cache line boundary which is 16 bytes.
0	XWS	<b>X-Bus Wait State Enable:</b> The PCI slave acting as a master on the X-bus will insert wait states on write cycles for data setup time. 0 = Disable; 1 = Enable.
Index 43h		PCI Arbitration Control 1 Register (R/W) Default Value = 80h
7	BG	Bus Grant: 0 = Grants bus regardless of X-bus buffers. 1 = Grants bus only if X-bus buffers are empty.
6	RSVD	Reserved: Set to 1.
5	RME2	<b>REQ2# Retry Mask Enable:</b> Arbiter allows the REQ2# to be masked based on the master retry mask in bits [2:1]: 0 = Disable; 1 = Enable.
4	RME1	<b>REQ1# Retry Mask Enable:</b> Arbiter allows the REQ1# to be masked based on the master retry mask in bits [2:1]: 0 = Disable; 1 = Enable.
3	RME0	<b>REQ0# Retry Mask Enable:</b> Arbiter allows the REQ0# to be masked based on the master retry mask in bits [2:1]: 0 = Disable; 1 = Enable.
2:1	MRM	Master Retry Mask: When a target issues a retry to a master, the arbiter can mask the request from the retried master in order to allow other lower order masters to gain access to the PCI bus:  00 = No retry mask 01 = Mask for 16 PCI clocks 10 = Mask for 32 PCI clocks 11 = Mask for 64 PCI clocks
0	HXR	Hold X-bus on Retries: Arbiter holds the X-Bus X_HOLD for two additional clocks to see if the retried master will request the bus again: 0 = Disable; 1 = Enable (This may prevent retry thrashing in some cases.)

Table 4-40. PCI Configuration Registers (Continued)

Bit	Name	Description
Index 44h		PCI Arbitration Control 2 Register (R/W) Default Value = 00h
7	PP	Ping-Pong: 0 = Arbiter grants the processor bus per the setting of bits [2:0]. 1 = Arbiter grants the processor bus ownership of the PCI bus every other arbitration cycle.
6:4	FAC	Fixed Arbitration Controls: These bits control the priority under fixed arbitration. The priority table is as follows (priority listed highest to lowest):  000 = REQ0#, REQ1#, REQ2#  001 = REQ1#, REQ0#, REQ2#  010 = REQ0#, REQ2#,REQ1#  011 = Reserved  100 = REQ1#, REQ2#, REQ0#  101 = Reserved  110 = REQ2#, REQ0#, REQ0#  111 = REQ2#, REQ0#, REQ0#  111 = REQ2#, REQ0#, REQ1#  Note: The rotation arbitration bits [2:0] must be set to 000 for full fixed arbitration. If rotation bits are not set to 000, then hybrid arbitration will occur. If Ping-Pong is enabled (bit 7 = 1), the processor will have priority every other arbitration. In this mode, the arbiter grants the PCI bus to a master and ignores all other requests. When the master finishes, the processor will be guaranteed access. At this point PCI requests will again be recognized. This will switch arbitration from CPU-to-PCI to CPU-to-PCI, etc.
3	RSVD	Reserved: Set to 0.
45h-FFh		Reserved

### 4.6.8 PCI Cycles

The following sections and diagrams provide the functional relationships for PCI cycles.

#### 4.6.8.1 PCI Read Transaction

A PCI read transaction consists of an address phase and one or more data phases. Data phases may consist of wait cycles and a data transfer. Figure 4-18 illustrates a PCI read transaction. In this example, there are three data phases.

The address phase begins on clock 2 when FRAME# is asserted. During the address phase, AD[31:0] contains a

valid address and C/BE[3:0]# contains a valid bus command. The first data phase begins on clock 3. During the data phase, AD[31:0] contains data and C/BE[3:0]# indicate which byte lanes of AD[31:0] carry valid data. The first data phase completes with zero delay cycles. However, the second phase is delayed one cycle because the target was not ready so it deasserted TRDY# on clock 5. The last data phase is delayed one cycle because the master deasserted IRDY# on clock 7.

For additional information refer to Chapter 3.3.1, Read Transaction, of the PCI Local Bus Specification, Revision 2.1




Figure 4-18. Basic Read Operation

#### 4.6.8.2 PCI Write Transaction

A PCI write transaction is similar to a PCI read transaction, consisting of an address phase and one or more data phases. Since the master provides both address and data, no turnaround cycle is required following the address phase. The data phases work the same for both read and write transactions. Figure 4-19 illustrates a write transaction.

The address phase begins on clock 2 when FRAME# is asserted. The first and second data phases complete without delays. During data phase 3, the target inserts three wait cycles by deasserting TRDY#.

For additional information refer to Chapter 3.3.2, Write Transaction, of the PCI Local Bus Specification, Revision 2.1.




Figure 4-19. Basic Write Operation

#### 4.6.8.3 PCI Arbitration

An agent requests the bus by asserting its REQ#. Based on the arbitration scheme set in the PCI Arbitration Control 2 Register (Index 44h), the GX PCI arbiter will grant the request by asserting GNT#. Figure 4-20 illustrates basic arbitration.

REQ#-a is asserted at clock 1. The PCI GXm processor arbiter grants access to Agent A by asserting GNT#-a on clock 2. Agent A must begin a transaction by asserting FRAME# within 16 clocks, or the GX PCI arbiter will remove GNT#. Also, it is possible for Agent A to lose bus ownership sooner if another agent with higher priority requests the bus. However, in this example, Agent A starts the transaction on clock 3 by asserting FRAME# and completes its transaction. Since Agent A requests another transaction, REQ#-a remains asserted. When FRAME# is asserted on clock 3, the GXm processor's PCI arbiter determines Agent B should go next, asserts GNT#-b and deasserts GNT#-a on clock 4. Agent B requires only a single transaction. It completes the transaction, then deasserts FRAME# and REQ#-b on clock 6.

The GXm processor's PCI arbiter can then grant access to agent A, and does so on clock 7. Note that all buffers must flush before a grant is given to a new agent.

For additional information refer to Chapter 3.4.1, Arbitration Signaling Protocol, of the PCI Local Bus Specification, Revision 2.1.

#### 4.6.8.4 PCI Halt Command

Halt is a broadcast message from the processor indicating it has executed a halt instruction. The PCI Special Cycle command is used to broadcast the message to all agents on the bus segment. During the address phase of the Halt Special cycle, C/BE[3:0]# = 0001 and AD[31:0] are driven to random values. During the data phase, C/BE[3:0]# = 1100 indicating bytes 1 and 0 are valid and AD[15:0] = 0001h.

For additional information, refer to Chapter 3.7.2, Special Cycle, and Appendix A, Special Cycle Messages, of the PCI Local Bus Specification, Revision 2.1.




Figure 4-20. Basic Arbitration

### 5.0 Virtual Subsystem Architecture

This section describes the Virtual Subsystem Architecture<sup>®</sup> (VSA<sup>TM</sup>) as implemented with the Geode GXm processor(s) and VSA enhanced I/O companion device(s). VSA provides a framework to enable software implementation of traditionally hardware-only components. VSA software executes in System Management Mode (SMM), enabling it to execute transparently to the operating system, drivers and applications.

The VSA design is based upon a simple model for replacing hardware components with software. Hardware to be virtualized is merely replaced with simple access detection circuitry which asserts the processor's SMI# (System Management Interrupt) pin when hardware accesses are detected. The current execution stream is immediately preempted, and the processor enters SMM. The SMM system software then saves the processor state, initializes the VSA execution environment, decodes the SMI source and dispatches handler routines which have registered requests to service the decoded SMI source. Once all handler routines have completed, the processor state is restored and normal execution resumes. In this manner, hardware accesses are transparently replaced with the execution of SMM handler software.

Historically, SMM software was used primarily for the single purpose of facilitating active power management for notebook designs. That software's only function was to manage the power up and down of devices to save power. With high performance processors now available, it is feasible to implement, primarily in SMM software, PC capabilities traditionally provided by hardware. In contrast to power management code, this virtualization software generally has strict performance requirements to prevent application performance from being significantly impacted.

Several functions can be virtualized in a GXm processor based design using the VSA environment. The VSA enhanced chipsets provide programmable resources to trap both memory and I/O accesses. However, specific hardware is included to support the virtualization of VGA core compatibility and audio functionality in the system.

The hardware support for VGA emulation resides completely inside the GXm processor. Legacy VGA accesses do not generate off-chip bus cycles. However, the VSA support hardware for

XpressAUDIO resides in the CS5530 I/O companion device and is described in the CS5530 specification.

#### 5.1 VIRTUAL VGA

The GXm processor reduces the burden of PC-legacy hardware by using a balanced mix of hardware and software to provide the same functionality. The graphics pipeline contains full hardware support for the VGA "frontend", the logic that controls read and write operations to the VGA frame buffer (located in graphics memory). For some modes, the hardware can also provide direct display of the data in the VGA buffer. Virtual VGA traps frame buffer accesses only when necessary, but it must trap all VGA I/O accesses to maintain the VGA state and properly program the graphics pipeline and display controller.

VGA functionality with the GXm processor includes the standard VGA modes (VGA, EGA, CGA, and MDA) as well as the higher-resolution VESA modes. The CGA and MDA modes (modes 0 through 7) require that Virtual VGA convert the data in the VGA buffer to a separate 8-BPP frame buffer that the hardware can use for display refresh.

The remaining modes, VGA, EGA, and VESA, can be displayed directly by the hardware, with no data conversion required. For these modes, Virtual VGA outperforms typical VGA cards because the frame buffer data does not travel across an external bus.

Display drivers for popular GUI (graphical user interface) based operating systems are provided by National Semiconductor which enable a full featured 2D hardware accelerator to be used instead of the emulated VGA core.

#### 5.1.1 Traditional VGA Hardware

A VGA card consists of display memory and control registers. The VGA display memory shows up in system memory between addresses A0000h and BFFFFh. It is possible to map this memory to three different ranges within this 128 KB block.

The first range is

- A0000h to B0000h for EGA and VGA modes, the second range is
- B0000h to B7FFFh for MDA modes, and the third range is
  - B8000h to BFFFFh for CGA modes.

The VGA control registers are mapped to the I/O address range from 3B0h to 3DFh. The VGA registers are accessed with an indexing scheme that provides more registers than would normally fit into this range. Some registers are mapped at two locations, one for monochrome, and another for color.

The VGA hardware can be accessed by calling BIOS routines or by directly writing to VGA memory and control registers. DOS always calls BIOS to set up the display mode and render characters. Many other applications access the VGA memory and control registers directly. The VGA card can be set up to a virtually unlimited number of modes. However, many applications use one of the predefined modes specified by the BIOS routine which sets up the display mode. The predefined modes are translated into specific VGA control register setups by the BIOS. The standard modes supported by VGA cards are shown in Table 5-1.

Table 4	5-1	Standard	VGA	Modes

Category	Mode	Text or Graphics	Resolution	Format	Туре
Software	0,1	Text	40x25	Characters	CGA
	2,3	Text	80x25	Characters	CGA
	4,5	Graphics	320x200	2 BPP	CGA
	6	Graphics	640x200	1 BPP	CGA
	7	Text	80x25	Characters	MDA
Hardware	0Dh	Graphics	320x200	4 BPP	EGA
	0Eh	Graphics	640x200	4 BPP	EGA
	0Fh	Graphics	640x350	1 BPP	EGA
	10h	Graphics	640x350	4 BPP	EGA
	11h	Graphics	640x480	1 BPP	VGA
	12h	Graphics	640x480	4 BPP	VGA
	13h	Graphics	320x200	8 BPP	VGA

A VGA is made up of several functional units.

- The frame buffer is 256 KB of memory that provides data for the video display. It is organized as 64 K 32-bit DWORDs.
- The sequencer decomposes word and DWORD CPU accesses into byte operations for the graphics controller. It also controls a number of miscellaneous functions, including reset and some clocking controls.
- The graphics controller provides most of the interface between CPU data and the frame buffer. It allows the programmer to read and write frame buffer data in different formats. Plus provides ROP (raster operation) and masking functions.
- The CRT controller provides video timing signals and address generation for video refresh. It also provides a text cursor.
- The attribute controller contains the video refresh datapath, including text rasterization and palette lookup.
- The general registers provide status information for the programmer as well as control over VGA-host address mapping and clock selection. This is all handled in hardware by the graphics pipeline.

It is important to understand that a VGA is constructed of numerous independent functions. Most of the register fields correspond to controls that were originally built out of discrete logic or were part of a dedicated controller such as the 6845. The notion of a VGA "mode" is a higher-level convention to denote a particular set of values for the registers. Many popular programs do not use standard modes, preferring instead to produce their own VGA setups that are optimal for their purposes.

#### 5.1.1.1 VGA Memory Organization

The VGA memory is organized as 64 K 32-bit DWORDs. This organization is usually presented as four 64 KB "planes". A plane consists of one byte out of every

DWORD. Thus, plane 0 refers to the least significant byte from every one of the 64 K DWORDs. The addressing granularity of this memory is a DWORD, not a byte; that is, consecutive addresses refer to consecutive DWORDs. The only provision for byte-granularity addressing is the four-byte enable signals used for writes. In C parlance,

single\_plane\_byte = (dword\_fb[address] >>
(plane \* 8)) & 0xFF;

When dealing with VGA, it is important to recognize the distinction between host addresses, frame buffer addresses, and the refresh address pipe. A VGA controller contains lots of hardware to translate between these address spaces in different ways, and understanding these translations is critical to understanding the entire device. In standard four-plane graphics modes, a frame-buffer DWORD provides eight 4-bit pixels. The left-most pixel comes from bit 7 of each plane, with plane 3 providing the most significant bit.

pixel[i].bit[j] = dword\_fb[address].bit[j\*8 + (7-i)]

#### 5.1.1.2 VGA Front End

The VGA front end consists of address and data translations between the CPU and the frame buffer. This functionality is contained within the graphics controller and sequencer components. Most of the front end functionality is implemented in the VGA read and write hardware of the GXm processor. An important axiom of the VGA is that the front end and back end are controlled independently. There are no register fields that control the behavior of both pieces. Terms like "VGA odd/even mode" are therefore somewhat misleading; there are two different controls for odd/even functionality in the front end, and two separate controls in the refresh path to cause "sensible" refresh behavior for frame buffer contents written in odd/even mode. Normally, all these fields would be set up together, but they don't have to be. This sort of orthogonal behavior gives rise to the enormous number of possible VGA "modes". The CPU end of the read and write pipes is one byte wide. Word and DWORD accesses from the

CPU to VGA memory are broken down into multiple byte accesses by the sequencer. For example, a word write to A0000h (in a VGA graphics mode) is processed as if it were two-byte write operations to A0000h and A0001h.

#### 5.1.1.3 Address Mapping

When a VGA card sees an address on the host bus, bits [31:15] determine whether the transaction is for the VGA. Depending on the mode, addresses 000AXXXX, 000B{0XXX}XXX, or 000B{1XXX}XXXX can decode into VGA space. If the access is for the VGA, bits [15:0] provide the DWORD address into the frame buffer (however, see odd/even and Chain 4 modes, below). Thus, each byte address on the host bus addresses a DWORD in VGA memory.

On a write transaction, the byte enables are normally driven from the sequencer's MapMask register. The VGA has two other write address mappings that modify this behavior. In odd/even (Chain 2) write mode, bit 0 of the address is used to enable bytes 0 and 2 (if zero) or bytes 1 and 3 (if one). In addition, the address presented to the frame buffer has bit 0 replaced with the PageBit field of the Miscellaneous Output register. Chain 4 write mode is similar; only one of the four byte enables is asserted, based on bits [1:0] of the address, and bits [1:0] of the frame buffer address are set to zero. In each of these modes, the MapMask enables are logically ANDed into the enables that result from the address.

#### 5.2 GXM VIRTUAL VGA

The GXm processor provides VGA compatibility through a mixture of hardware and software. The processor core contains SMI generation hardware for VGA memory write operations. The bus controller contains SMI generation hardware for VGA I/O read and write operations. The graphics pipeline contains hardware to detect and process reads and writes to VGA memory. VGA memory is partitioned from system memory.

### 5.2.1 Datapath Elements

The graphics controller contains several elements that convert between host data and frame buffer data.

The rotator simply rotates the byte written from the host by 0 to 7 bits to the right, based on the RotateCount field of the DataRotate register. It has no effect in the read path.

The display latch is a 32-bit register that is loaded on every read access to the frame buffer. All 32 bits of the frame buffer DWORDs are loaded into the latch.

The **write-mode unit** converts a byte from the host into a 32-bit value. A VGA has four write modes:

- Write Mode 0:
  - Bit n of byte b comes from one of two places, depending on bit b of the EnableSetReset register. If that bit is zero, it comes from bit n of the host data. If that bit is one, it comes from bit b of the SetReset register. This mode allows the programmer to set

some planes from the host data and the others from SetReset.

#### • Write Mode 1:

 All 32 bits come directly out of the display latch; the host data is ignored. This mode is used for screento-screen copies.

#### • Write Mode 2:

 Bit n of byte b comes from bit b of the host data; that is, the four LSBs of the host data are each replicated through a byte of the result. In conjunction with the BitMask register, this mode allows the programmer to directly write a 4-bit color to one or more pixels.

#### • Write Mode 3:

 Bit n of byte b comes from bit b of the SetReset register. The host data is ANDed with the BitMask register to provide the bit mask for the write (see below).

The **read mode unit** converts a 32-bit value from the frame buffer into a byte. A VGA has two read modes:

#### · Read Mode 0:

 One of the four bytes from the frame buffer is returned, based on the value of the ReadMapSelect register. In Chain 4 mode, bits [1:0] of the read address select a plane. In odd/even read mode, bit 0 of the read address replaces bit 0 of ReadMapSelect.

#### · Read Mode 1:

 Bit n of the result is set to 1 if bit n in every byte b matches bit b of the ColorCompare register; otherwise it is set to 0. There is a ColorDon'tCare register that can exclude planes from this comparison. In four-plane graphics modes, this provides a conversion from 4 BPP to 1 BPP.

The ALU is a simple two-operand ROP unit that operates on writes. Its operating modes are COPY, AND, OR, and XOR. The 32-bit inputs are:

- 1) the output of the write-mode unit and
- 2) the display latch (not necessarily the value at the frame buffer address of the write).

An application that wishes to performs ROPs on the source and destination must first byte read the address (to load the latch) and then immediately write a byte to the same address. The ALU has no effect in Write Mode 1.

The bit mask unit does not provide a true bit mask. Instead, it selects between the ALU output and the display latch. The mask is an 8-bit value, and bit n of the mask makes the selection for bit n of all four bytes of the result (a zero selects the latch). No bit masking occurs in Write Mode 1.

The VGA hardware of the GXm processor does not implement Write Mode 1 directly, but it can be indirectly implemented by setting the BitMask to zero and the ALU mode to COPY.

#### 5.2.2 Video Refresh

VGA refresh is controlled by two units: the CRT controller (CRTC) and the attribute controller (ATTR). The CRTC provides refresh addresses and video control; the ATTR provides the refresh datapath, including pixel formatting and internal palette lookup.

The VGA back end contains two basic clocks: the dot clock (or pixel clock) and the character clock. The Clock-Select field of the Miscellaneous Output register selects a "master clock" of either 25 MHz or 28 MHz. This master clock, optionally divided by two, drives the dot clock. The character clock is simply the dot clock divided by eight or nine.

The VGA supports four basic pixel formats. Using text format, the VGA interprets frame buffer values as ASCII characters, foreground/background attributes, and font data. The other three formats are all "graphics modes", known as APA (All Points Addressable) modes. These formats could be called CGA-compatible (odd/even four bits/pixel), EGA-compatible (4-plane four bits/pixel), and VGA-compatible (pixel-per-byte eight bits/pixel). The format is chosen by the ShiftRegister field of the Graphics Controller Mode register.

The refresh address pipe is an integral part of the CRTC, and has many configuration options. Refresh can begin at any frame buffer address. The display width and the frame buffer pitch (scan-line delta) are set separately. Multiple scan lines can be refreshed from the same frame buffer addresses. The LineCompare register causes the refresh address to be reset to zero at a particular scan line, providing support for vertical split-screen.

Within the context of a single scan line, the refresh address increments by one on every character clock. Before being presented to the frame buffer, refresh addresses can be shifted by 0, 1, or 2 bits to the left. These options are often mis-named Byte, Word, and Doubleword modes. Using this shifter, the refresh unit can be programmed to skip one out of two or three out of four DWORDs of refresh data. As an example of the utility of this function, consider Chain 4 mode, described earlier. Pixels written in Chain 4 mode occupy one out of every four DWORDs in the frame buffer. If the refresh path is put into "Doubleword" mode, the refresh will come only from those DWORDs writable in Chain 4. This is how VGA mode 13h works.

In text mode, the ATTR has a lot of work to do. At each character clock, it pulls a DWORD of data out of the frame buffer. In that DWORD, plane 0 contains the ASCII character code, and plane 1 contains an attribute byte. The ATTR uses plane 0 to generate a font lookup address and read another DWORD. In plane 2, this DWORD contains a bit-per-pixel representation of one scan line in the appropriate character glyph. The ATTR transforms these bits into eight pixels, obtaining foreground and background colors from the attribute byte. The CRTC must refresh from the same memory addresses for all scan lines that make up a character row; within that row, the ATTR must

fetch successive scan lines from the glyph table so as to draw proper characters. Graphics modes are somewhat simpler. In CGA-compatible mode, a DWORD provides eight pixels. The first four pixels come from planes 0 and 2; each 4-bit pixel gets bits [3:2] from plane 2, and bits [1:0] from plane 0. The remaining four pixels come from planes 1 and 3. The EGA-compatible mode also gets eight pixels from a DWORD, but each pixel gets one bit from each plane, with plane 3 providing bit 3. Finally, VGA-compatible mode gets four pixels from each DWORD; plane 0 provides the first pixel, plane 1 the next, and so on. The 8 BPP mode uses an option to provide every pixel for two dot clocks, thus allowing the refresh pipe to keep up (it only increments on character clocks) and meaning that the 320-pixel-wide mode 13h really has 640 visible pixels per line. The VGA color model is unusual. The ATTR contains a 16-entry color palette with 6 bits per entry. Except for 8 BPP modes, all VGA configurations drive four bits of pixel data into the palette, which produces a 6-bit result. Based on various control registers, this value is then combined with other register contents to produce an 8-bit index into the DAC. There is a ColorPlaneEnable register to mask bits out of the pixel data before it goes to the palette; this is used to emulate four-color CGA modes by ignoring the top two bits of each pixel. In 8 BPP modes, the palette is bypassed and the pixel data goes directly to the DAC

#### 5.2.3 GXm VGA Hardware

The GXm processor core contains hardware to detect VGA accesses and generate SMI interrupts. The graphics pipeline contains hardware to detect and process reads and writes to VGA memory. The VGA memory on the GXm processor is partitioned from system memory. The GXm processor has the following hardware components to assist the VGA emulation software.

- SMI Generation
- VGA Range Detection
- VGA Sequencer
- VGA Write/Read Path
- VGA Address Generator
- VGA Memory

### 5.2.3.1 SMI Generation

VGA emulation software is notified of VGA memory accesses by an SMI generated in dedicated circuitry in the processor core that detects and traps memory accesses. The SMI generation hardware for VGA memory addresses is in the second stage of instruction decoding on the processor core. This is the earliest stage of instruction decode where virtual addresses have been translated to physical addresses. Trapping after the execution stage is impractical, because memory write buffering will allow subsequent instructions to execute.

The VGA emulation code requires the SMI to be generated immediately when a VGA access occurs. The SMI generation hardware can optionally exclude areas of VGA memory, based on a 32-bit register which has a control bit for each 2 KB region of the VGA memory window. The

control bit determines whether or not an SMI interrupt is generated for the corresponding region. The purpose of this hardware is to allow the VGA emulation software to disable SMI interrupts in VGA memory regions that are not currently displayed.

For direct display modes (8 BPP or 16 BPP) in the display controller, Virtual VGA can operate without SMI generation.

The SMI generation circuit on the GXm processor has configuration registers to control and mask SMI interrupts in the VGA memory space.

#### 5.2.3.2 VGA Memory Addresses

SMI generation can be configured to trap VGA memory accesses in one of the following ranges:

A0000h to AFFFFh (EGA,VGA), B0000h to B7FFFh (MDA), or B8000h to BFFFFh (CGA).

Range selection is accomplished through programmable bits in the VGACTL register (Index B9h). Fine control can be exercised within the range selected to allow off-screen accesses to occur without generating SMIs.

SMI generation can also separately control the following I/O ranges: 3B0h to 3BFh, 3C0h to 3CFh, and 3D0h to

3DFh. The BC\_XMAP\_1 register (GX\_BASE+8004h) in the Internal Bus Interface Unit has an enable/disable bit for each of the address ranges above.

#### 5.2.3.3 VGA Configuration Registers

Table 5-2 summarizes the VGA Configuration Registers. Detailed register/bit formats are given in Table 5-3.

#### 5.2.3.4 VGA Control Register

The VGA control register (VGACTL) provides control for SMI generation through an enable bit for memory address ranges A0000h to BFFFFh. Each bit controls whether or not SMI is generated for accesses to the corresponding address range. The default value of this register is zero so that VGA accesses will not be trapped on systems with an external VGA card.

#### 5.2.3.5 VGA Mask Registers

The VGA Mask register (VGAM) has 32 bits that can selectively mask 2 KB regions within the VGA memory region A0000h to AFFFFh. If none of the three regions is enabled in VGACTL, then the contents of VGAM are ignored. VGAM can be used to prevent the occurrence of SMI when non-displayed VGA memory is accessed. This is an enhancement that improves performance for double-buffered applications only.

Table 5-2. VGA Configuration Registers Summary

Index	Name	Description	Default
B9h	VGACTL	VGA Control Register	00h (SMI generation disabled)
BAh-BDh	VGAM	VGA Mask Register	Don't Care

Table 5-3. VGA Configuration Registers

Bit	Description	
Index B9h	VGACTL Register (R/W)	Default Value = 00h
7:3	Reserved: Set to 0.	
2	SMI generation for VGA memory range B8000h to BFFFFh: 0 = Disable; 1 = Enable	
1	SMI generation for VGA memory range B0000h to B7FFFh: 0 = Disable; 1 = Enable.	
0	SMI generation for VGA memory range A0000h to AFFFFh: 0 = Disable; 1 = Enable	
Index BAh	-BDh VGAM Register (R/W)	Default Value = xxxxxxxxh
31	SMI generation for address range AF800h to AFFFFh: 0 = Disable; 1 = Enable.	
30	SMI generation for address range AF000h to AF7FFh: 0 = Disable; 1 = Enable.	
29	SMI generation for address range AE800h to AEFFFh: 0 = Disable; 1 = Enable.	
28	SMI generation for address range AE000h to AE7FFh: 0 = Disable; 1 = Enable.	
27	SMI generation for address range AD800h to ADFFFh: 0 = Disable; 1 = Enable.	
26	SMI generation for address range AD000h to AD7FFh: 0 = Disable; 1 = Enable.	
25	SMI generation for address range AC800h to ACFFFh: 0 = Disable; 1 = Enable.	
24	SMI generation for address range AC000h to AC7FFh: 0 = Disable; 1 = Enable.	
23	SMI generation for address range AB800h to ABFFFh: 0 = Disable; 1 = Enable.	
22	SMI generation for address range AB000h to AB7FFh: 0 = Disable; 1 = Enable.	
21	SMI generation for address range AA800h to AAFFFh: 0 = Disable; 1 = Enable.	
20	SMI generation for address range AA000h to AA7FFh: 0 = Disable; 1 = Enable.	
19	SMI generation for address range A9800h to A9FFFh: 0 = Disable; 1 = Enable.	
18	SMI generation for address range A9000h to A97FFh: 0 = Disable; 1 = Enable.	
17	SMI generation for address range A8800h to A8FFFh: 0 = Disable; 1 = Enable.	
16	SMI generation for address range A8000h to A87FFh: 0 = Disable; 1 = Enable.	
15	SMI generation for address range A7800h to A7FFFh: 0 = Disable; 1 = Enable.	
14	SMI generation for address range A7000h to A77FFh: 0 = Disable; 1 = Enable.	
13	SMI generation for address range A6800h to A6FFFh: 0 = Disable; 1 = Enable.	
12	SMI generation for address range A6000h to A67FFh: 0 = Disable; 1 = Enable.	
11	SMI generation for address range A5800h to A5FFFh: 0 = Disable; 1 = Enable.	
10	SMI generation for address range A5000h to A57FFh: 0 = Disable; 1 = Enable.	
9	SMI generation for address range A4800h to A4FFFh: 0 = Disable; 1 = Enable.	
8	SMI generation for address range A4000h to A47FFh: 0 = Disable; 1 = Enable.	
7	SMI generation for address range A3800h to A3FFFh: 0 = Disable; 1 = Enable.	
6	SMI generation for address range A3000h to A37FFh: 0 = Disable; 1 = Enable.	
5	SMI generation for address range A2800h to A2FFFh: 0 = Disable; 1 = Enable.	
4	SMI generation for address range A2000h to A27FFh: 0 = Disable; 1 = Enable.	
3	SMI generation for address range A1800h to A1FFFh: 0 = Disable; 1 = Enable.	
2	SMI generation for address range A1000h to A17FFh: 0 = Disable; 1 = Enable.	
1	SMI generation for address range A0800h to A0FFFh: 0 = Disable; 1 = Enable.	
0	SMI generation for address range A0000h to A07FFh: 0 = Disable; 1 = Enable.	

#### 5.2.3.6 VGA Range Detection

The VGA range detection circuit is similar to the SMI generation hardware, however, it resides in the bus controller address mapping unit. The purpose of this hardware is to notify the graphics pipeline when accesses to the VGA memory range A0000h to BFFFFh are detected. The graphics pipeline has VGA read and write path hardware to process VGA memory accesses. The VGA range detection can be configured to trap VGA memory accesses in one or more of the following ranges: A0000h to AFFFFh (EGA,VGA), B0000h to B7FFFh (MDA), or B8000h to BFFFFh (CGA).

#### 5.2.3.7 VGA Sequencer

The VGA sequencer is located at the front end of the graphics pipeline. The purpose of the VGA sequencer is to divide up multiple-byte read and write operations into a sequence of single-byte read and write operations. 16-bit or 32-bit X-bus write operations to VGA memory are divided into 8-bit write operations and sent to the VGA write path. 16-bit or 32-bit X-bus read operations from VGA memory are accumulated from 8-bit read operations over the VGA read path. The sequencer generates the lower two bits of the address.

#### 5.2.3.8 VGA Write/Read Path

The VGA write path implements standard VGA write operations into VGA memory. No SMI is generated for write path operations when the VGA access is not displayed. When the VGA access is displayed, an SMI is generated so that the SMI emulation can update the frame buffer. The VGA write path converts 8-bit write operations from the sequencer into 32-bit VGA memory write operations. The operations performed by the VGA write path include data rotation, raster operation (ALU), bit masking, plane select, plane enable, and write modes.

The VGA read path implements standard VGA read operations from VGA memory. No SMI is needed for read-path operations. The VGA read path converts 32-bit read operations from VGA memory to 8-bit data back to the sequencer. The basic operations performed by the VGA read path include color compare, plane-read select, and read modes.

#### 5.2.3.9 VGA Address Generator

The VGA address generator translates VGA memory addresses up to address where the VGA memory resides on the GXm processor. The VGA address generator requires the address from the VGA access (A0000h to BFFFFh), the base of the VGA memory on the GXm processor, and various control bits. The control bits are necessary because addressing is complicated by odd/even and Chain 4 addressing modes.

#### 5.2.3.10 VGA Memory

The VGA memory requires 256 KB of memory organized as 64 KB by 32 bits. The VGA memory is implemented as part of system memory. The GXm processor partitions system memory into two areas, normal system memory and graphics memory. System memory is mapped to the normal physical address of the DRAM, starting at zero and ending at memory size. Graphics memory is mapped into high physical memory, contiguous to the registers and dedicated cache of the GXm processor. The graphics memory includes the frame buffer, compression buffer, cursor memory, and VGA memory. The VGA memory is mapped on a 256 KB boundary to simplify the address generation.

#### 5.2.4 VGA Video BIOS

The video BIOS supports the VESA BIOS Extensions (VBE) Version 1.2 and 2.0, as well as all standard VGA BIOS calls. It interacts with Virtual VGA through the use of several extended VGA registers. These are virtual registers contained in the VSA code for Virtual VGA. (These registers are defined in a separate document.)

### 5.2.5 Virtual VGA Register Descriptions

This section describes the registers contained in the graphics pipeline used for VGA emulation. The graphics pipeline maps 200h locations starting at GX\_BASE+8100h. Refer to Section 4.1.2 "Control Regis-

ters" on page 94 for instructions on accessing these registers.

The registers are summarized in Table 5-4, followed by detailed bit formats in Table 5-5 on page 173.

Table 5-4. Virtual VGA Register Summary

GX_BASE+ Memory Offset	Туре	Function	Default Value
8210h-8213h	R/W	GP_VGA_BASE VGA Graphics Pipeline VGA Memory Base Address Register — Specifies the offset of the VGA memory, starting from the base of graphics memory.	
8214h-8217h	R/W	GP_VGA_LATCH  Graphics Pipeline VGA Display Latch Register — Provides a memory mapped way to read or write the VGA display latch.	
8140h-8143h	R/W	GP_VGA_WRITE xxxxxxx Graphics Pipeline VGA Write Patch Control Register — Controls the VGA memory write path in the graphics pipeline.	
8144h-8147h	R/W	GP_VGA_READ  Graphics Pipeline VGA Read Patch Control Register — Controls the VGA memory read path in the graphics pipeline.  00000000h	

Table 5-5. Virtual VGA Registers

Bit	Name	Description	
GX_BASE	+8210h-8213h	GP_VGA_BASE (R/W)	Default Value = xxxxxxxxxh
31:14	RSVD	Reserved: Set to 0.	
13:8	VGA_BASE (RO)	Base Address (Read Only): The VGA base address is added specify where VGA memory starts. The VGA base address prowhen mapping VGA accesses into graphics memory. This alloany 64 KB boundary within the 4 MB of graphics memory.	ovides longword address bits 19:14
7:6	RSVD	Reserved: Set to 0.	
5:0	VGA_BASE (WO)	Base Address (Write Only): The VGA base address is added specify where VGA memory starts. The VGA base address prowhen mapping VGA accesses into graphics memory. This alloany 64 KB boundary within the 4 MB of graphics memory.	ovides longword address bits 19:14
GX_BASE	+8214h-8217h	GP_VGA_LATCH Register (R/W)	Default Value = xxxxxxxxxh
31:0	LATCH	<b>Display Latch:</b> Specifies the value in the VGA display latch. V frame-buffer data to be latched in the display latch. VGA write as a source of data for VGA frame-buffer write operations.	
GX_BASE	+8140h-8143h	GP_VGA_WRITE Register (R/W)	Default Value = xxxxxxxxh
31:28	RSVD	Reserved: Set to 0.	
27:24	MAP_MASK	<b>Map Mask:</b> Enables planes 3 through 0 for writing. Combined with chain control to determine the final enables.	
23:21	RSVD	Reserved: Set to 0.	
20	W3	Write Mode 3: Selects write mode 3 by using the bit mask wit	h the rotated data.
19	W2	Write Mode 2: Selects write mode 2 by controlling set/reset.	
18:16	RC	Rotate Count: Controls the eight bit rotator.	
15:12	SRE	Set/Reset Enable: Enables the set/reset value for each plane	
11:8	SR	Set/Reset: Selects 1 or 0 for each plane if enabled.	
7:0	BIT_MASK	Bit Mask: Selects data from the data latches (last read data).	
GX_BASE	+8144h-8147h	GP_VGA_READ Register (R/W)	Default Value = 00000000h
31:18	RSVD	Reserved: Set to 0.	
17:16	RMS	Read Map Select: Selects which plane to read in read mode	0 (Chain 2 and Chain 4 inactive).
15	F15	Force Address Bit 15: Forces address bit 15 to 0.	
14	PC4	Packed Chain 4:— Provides 64 KB of packed pixel addressing when used with Chain 4 mode. This bit causes the VGA addresses to be shifted right by 2 bits.	
13	C4	Chain 4 Mode: Selects Chain 4 mode for both read operations and write operations.	
12	РВ	Page Bit: Becomes LSB of address if COE is set high.	
11	COE	Chain Odd/Even: Selects PB rather than A0 for least-significant VGA address bit.	
10	W2	Write Chain 2 Mode: Selects Chain 2 mode for write operations.	
9	R2	Read Chain 2 Mode: Selects Chain 2 mode for read operations.	
8	RM	Read Mode: Selects between read mode 0 (normal) and read mode 1 (color compare).	
7:4	CCM	Color Compare Mask: Selects planes to include in the color comparison (read mode 1).	
3:0	CC	Color Compare: Specifies value of each plane for color comparison (read mode 1).	

### 6.0 Power Management

The power management resources provided by a combined Geode GXm processor and CS5530-based system have been designed to support a full-featured notebook implementation. The extent to which these resources are employed depends on the application and the discretion of the system designer.

The three greatest power consumers in a notebook system are the display, the hard drive and the CPU. Managing power for the first two is relatively straightforward and is discussed in the Geode CS5530 I/O companion specification. Managing CPU power can be more difficult since detecting inactive (Idle) states by monitoring external activity is imperfect as well as inefficient.

The GXm processor and CS5530 I/O companion chip contain the most advanced power management features for reducing the power consumption of the processor in the system while delivering the highest performance in any mobile processor. The GXm processor supports the following CPU power management features:

- APM Support
- · CPU Suspend Command Registers (CS5530)
- · Suspend Modulation
- 3 Volt Suspend
- · GXm Integrated Processor Serial Bus

#### 6.1 APM SUPPORT

Many notebook computers rely solely on the APM (Advanced Power Management) driver for DOS, Windows 3.1 and Windows 95 operating systems to manage power to the CPU. APM provides several services that enhance the system power management by determining when the CPU is idle. For the CPU, APM is theoretically the best approach but there are some drawbacks.

- APM is an OS-specific driver which may not be available for some operating systems.
- Application support is inconsistent. Some applications in foreground may prevent idle calls.

The components for APM support are:

- Software CPU Suspend control via the CS5530 CPU Suspend Command Register (ACh).
- Software SMI entry via the Software SMI Register (D0h). This allows the APM BIOS to be part of the SMI handler.

#### 6.2 CPU SUSPEND COMMAND REGISTERS

Power management system software can invoke the SUSP#/SUSPA# protocol with the "CPU Suspend Command" and the "Suspend Notebook Command" registers in the CS5530. If the SUSP#/SUSPA# protocol is invoked, all pending SMIs are serviced and SMI# is deasserted. Then SUSP# is asserted by the CS5530 and, subsequently, SUSPA# is returned by the GXm processor. When a condition that ends the "Suspend" state exists, SMI# is re-asserted. At this point, if the PLL in the GXm processor has not been stopped, then SUSP# is deas-

serted. SUSP# is never deasserted until SUSPA# has been sampled active (low).

Note: The SMI# pin is a unidirectional line from the CS5530 to the GXm processor. It is active low. When SMI is initiated from a normal mode, the SMI# pin is asserted low and is held low until the SMI source is cleared. At that time, SMI# is deasserted.

#### 6.3 SUSPEND MODULATION

The hardware provided to support the GXm processor's power management works by assuming that the GXm processor is Idle and reducing power until activity is detected. Most power management schemes in the industry run the system at full speed until a period of inactivity is detected. National Semiconductor's more aggressive approach yields lower power consumption. When activity is detected, the GXm processor is instantly converted to full speed for a programmed duration. This is called Suspend Modulation.

Suspend Modulation acts as backup for cases where APM doesn't correctly detect an Idle condition in the system. As long as it is enabled, it will only become active in the background. The "Suspend Modulation Enable Register" in the CS5530 enables the Suspend Modulation feature.

The "Suspend Modulation ON Count Register" in the CS5530 is an 8-bit counter that represents the number of 32  $\mu s$  intervals that the SUSP# pin will be asserted to the GXm processor. This counter, together with the "Suspend Modulation OFF Count Register" and the IRQ/Video Speedup Registers, performs the Suspend Modulation function for GXm processor's power management. The ratio of the on count to the off count sets up an effective (emulated) clock frequency, allowing the power manager in the system to reduce the GXm processor's power consumption.

### 6.4 3-VOLT SUSPEND MODE

The GXm processor and CS5530 support stopping the processor and system clocks using the 3-Volt Suspend Mode. If configured (refer to the CS5530 specification), the CS5530 asserts the SUSP\_3V pin after the SUSP#/SUSPA# handshake. SUSP\_3V is intended to be connected to the output enable of a clock synthesizer or buffer chip so that the clocks to the GXm processor (SYSCLK), the CS5530 (PCI\_CLK), and other system devices are stopped. The SUSP\_3V pin is asserted on any write to the CS5530's "CPU Suspend Command Register" or "Suspend Notebook Command Register" with bit 0 of the "Clock Stop Control Register" set.

The GXm processor has two low-power Suspend modes. The mode implemented is determined by bit 0 in the PM Clock Stop Control Register. One mode (bit 0 clear) turns off the internal clocks to everything except the internal display and memory controllers, thereby keeping the display active. The second mode, which is lower power, turns off all internal clocks generated from SYSCLK. This mode is

selected by setting bit 0 in the PM Clock Stop Control Register. If you are using DRAMs without self refresh, you must supply a 32 kHz clock to the CLK32KHZ bit to keep the refresh circuitry active when using the lower-power Suspend mode.

While also in 3-Volt Suspend Mode, the CS5530 continues to decrement all of its device timers, and it responds to external SMI interrupts using the 32 kHz clock input (CLK32KHz) pin. Any SMI event, timer or pin, causes the CS5530 to deassert the SUSP\_3V pin, starting the system clocks. The CS5530 holds SUSP# active for a preprogrammed period that varies from 0 to 16 ms, which allows the clocks to settle. After this period expires, the CS5530 deasserts SUSP#. SMI# is held active for the entire period, so that the GXm processor status registers are updated.

The SUSP\_3V pin can be active either high or low. The pin is an input during POR, and is sampled to determine its inactive state. This allows a designer to match the active state of SUSP\_3V to the inactive state for a clock driver output enable with a pull-up or pull-down resistor.

#### 6.5 SUSPEND MODE AND BUS CYCLES

The following subsections describe the bus cycles when the Suspend mode is implemented.

#### 6.5.1 Initiating Suspend with SUSP#

The GXm processor has two low-power Suspend modes. The mode is selected by bit 0 in the PM Clock Stop Control Register. One mode (bit 0 cleared) turns off the internal clocks to everything but the internal Display and Memory Controllers, keeping the display active. A lower-

power mode turns off all internal clocks generated from SYSCLK. This mode is selected by setting bit 0 in the PM Clock Stop Control Register. If the bit is set and DRAMS without self-refresh are used, a 32 KHz clock must be supplied to the CLK32KHZ input to keep the refresh circuit active.

The GXm processor enters the Suspend mode in response to SUSP# input assertion only when certain conditions are met. First, the USE\_SUSP bit must be set in CCR2 (Index C2h[7]). In addition, execution of the current instructions and any pending decoded instructions and associated bus cycles must be completed. SUSP# is sampled on the rising edge of SYSCLK, and must meet specified setup and hold times to be recognized at a particular SYSCLK edge.

When all conditions are met, the SUSPA# output is asserted. The time from assertion of SUSP# to the activation of SUSPA# depends on which instructions were decoded prior to assertion of SUSP#. Normally, once SUSP# has been sampled inactive the SUSPA# output will be deactivated within two clocks. However, the deactivation of SUSPA# may be delayed until the end of an active refresh cycle.

If the CPU is already in a Suspend mode initiated by SUSP#, one occurrence of NMI, INTR and SMI# is stored for execution after Suspend mode is exited. The CPU also allows PCI accesses during a SUSP#-initiated Suspend mode (see Figure 6-1). If the CPU is in the middle of a PCI access when SUSP# is asserted, the assertion of SUSPA# will be delayed until the PCI access is completed.




Figure 6-1. SUSP#-Initiated Suspend Mode

### 6.5.2 Initiating Suspend with HALT

The CPU also enters Suspend mode as a result of executing a HALT instruction if the SUSP\_HALT bit in CCR2 (Index C2h[3]) is set. Suspend mode is then exited upon recognition of an NMI, an unmasked INTR, or an SMI#. Normally SUSPA# is deactivated within six SYSCLKS from the detection of an active interrupt. However, the

deactivation of SUSPA# may be delayed until the end of an active refresh cycle.

The CPU also allows PCI accesses during a HALT-initiated Suspend mode. If the CPU is in the middle of a PCI access when the Halt instruction is executed, the assertion of SUSPA# will be delayed until the PCI access is completed.




Figure 6-2. HALT-Initiated Suspend Mode

# 6.5.3 Responding to a PCI Access During Suspend Mode

The GXm processor can temporarily exit Suspend mode to handle PCI accesses. If an unmasked REQx# is asserted, the GXm processor will deassert SUSPA# and exit the Suspend mode to respond to the PCI access. A PCI access is completed when FRAME# is inactive and TRDY# or STOP# are active. If SUSP# is asserted when

the PCI access is completed, the GXm processor will assert SUSPA# and return to a SUSP#-initiated Suspend mode. If it was a HALT-initiated Suspend mode and no active interrupts have been recognized, the CPU will assert SUSPA# and return to a HALT-initiated Suspend mode.




Figure 6-3. PCI Access During Suspend Mode

### 6.5.4 Stopping the Input Clock

Because the GXm processor is a static device, the input clock (SYSCLK) can be stopped and restarted without any loss of internal CPU data. If DRAMS are used that do not have self-refresh, bit 0 of the PM Clock Stop Control Register must be set to a one and the CLK32KHZ input must be continuously applied to keep the refresh circuitry running. The SYSCLK input can be stopped at either a logic high or logic low state. The required sequence for stopping SYSCLK is to initiate CPU Suspend mode, wait for the assertion of SUSPA# by the processor, and then stop the input clock.

The CPU remains suspended until SYSCLK is restarted and the Suspend mode is exited as described earlier. While SYSCLK is stopped, the processor can no longer sample and respond to any input stimulus including REQx#, NMI, SMI#, INTR, and RESET inputs.

Figure 6-4 illustrates the recommended sequence for stopping the SYSCLK using SUSP# to initiate Suspend mode. SYSCLK may be started prior to or following negation of the SUSP# input. The figure includes the SUSP\_3V pin from the CS5530 which is used to stop the external clocks.




Figure 6-4. Stopping SYSCLK During Suspend Mode

#### 6.6 GXM PROCESSOR SERIAL BUS

The power management logic of the GXm processor provides the CS5530 with information regarding the GXm processor productivity. If the GXm processor is determined to be relatively inactive, the GXm processor power consumption can be greatly reduced by entering the Suspend Modulation mode.

Although the majority of the system power management logic is implemented in the CS5530, a small amount of logic is required within the GXm processor to provide information from the graphics controller that is not externally visible otherwise. The GXm processor implements a simple serial communications mechanism to transmit the CPU status to the CS5530. The GXm processor accumulates CPU events in a 8-bit register, "PM Serial Packet Register" (GX\_BASE+850Ch, see Table 6-1), which is serially transmitted out of the GXm processor every 1 to 10 µs. The transmission frequency is set with the "PM Serial Packet Control Register" (GX\_BASE+8504h, see Table 6-1).

#### 6.6.1 Serial Packet Transmission

The GXm processor transmits the contents of the "PM Serial Packet Register" on the SERIALP output pin to the PSERIAL input pin of the CS5530. The GXm processor holds SERIALP low until the transmission interval counter (GX\_BASE+8504h[4:3]) has elapsed. Once the counter has elapsed, PSERIAL is held high for two SYSCLKs to

indicate the start of packet transmission. The contents of the packet register are then shifted out starting from bit 7 down to bit 0. PSERIAL is held high for one SYSCLK to indicate the end of packet transmission and then remains low until the next transmission interval. After the packet transmission has completed, the packet contents are cleared.

#### 6.7 POWER MANAGEMENT REGISTERS

The GXm processor contains the power management registers for the serial packet transmission control, the user-defined power management address space, Suspend Refresh, and SMI status for Suspend/Resume. These registers are memory mapped (GX\_BASE+8500h8FFFh) in the address space of the GXm processor and are described in the following sections. Refer to Section 4.1.2 "Control Registers" on page 94 for instructions on accessing these registers.

Note, however, the PM\_BASE and PM\_MASK registers are accessed with the CPU\_READ and CPU\_WRITE instructions. Refer to Section 4.1.6 "CPU\_READ/CPU\_WRITE Instructions" on page 99 for more information regarding these instructions.

Table 6-1 summarizes the above mentioned registers. Tables 6-2 and 6-3 starting on page 180 give these register's bit formats.

**Table 6-1. Power Management Register Summary** 

GX_BASE+ Memory Offset	Туре	Name/Function	Default Value
Control and Status	Registers		
8500h-8503h R/W		PM_STAT_SMI	
		PM SMI Status Register — Contains System Management Mode (SMM) status information used by SoftVGA.	
8504h-8507h	R/W	PM_CNTRL_TEN	
		PM Serial Packet Control Register — Sets the serial packet transmission frequency and enables specific CPU events to be recorded in the serial packet.	
8508h-850Bh R/W		PM_CNTRL_CSTP	xxxxxx00h
		PM Clock Stop Control Register — Enables the 3-V Suspend Mode for the GXm processor.	
850Ch-850Fh R/W <b>PM_SER_PA</b>		PM_SER_PACK	xxxxxx00h
		PM Serial Packet Register — Transmits the contents of the serial packet.	
Programmable Add	dress Regi	on Registers	
FFFF FF6Ch	R/W	PM_BASE	00000000h
		PM Base Register — Contains the base address for the programmable memory range decode. This register, in combination with the PM_MASK register, is used to generate a memory range decode which sets bit 1 in the serial transmission packet.	
FFFF FF7Ch	R/W	PM_MASK	00000000h
		PM Mask Register — The address mask for the PM_BASE register	

Table 6-2. Power Management Control and Status Registers

Bit	Name	Description		
GX_BASE	E+8500h-8503h	PM_STAT_SMI Register (R/W)	Default Value = xxxxxx00h	
31:8	RSVD	Reserved — These bits are not used. Do not write to these bits.		
7:3	RSVD	Reserved — Set to 0.		
2	SMI_MEM	SMI VGA Emulation Memory — This bit is set high if a SMI was response to a VGA memory access. An SMI can be generated o regions in the A0000h-to-BFFFFh range as specified in the BC	on a memory access to one of three	
1	SMI_IO	<b>SMI VGA Emulation I/O</b> — This bit is set high if a SMI was generated for VGA emulation in response to an I/O access. An SMI can be generated on a I/O access to one of three regions in the 3B0h-to-3DFh range as specified in the BC_XMAP_1 register.		
0	SMI_PIN	<b>SMI Pin</b> — When set high, this bit indicates that the SMI# input   GXm processor.	pin has been asserted to the	
Note: The	ese bits are "sticky" b	its and can only be cleared with a write of '1' to the respective bit.		
GX_BASE	+8504h-8507h	PM_CNTRL_TEN Register (R/W)	Default Value = xxxxxx00h	
31:8	RSVD	Reserved — These bits are not used. Do not write to these bits.		
7:6	RSVD	Reserved — Set to 0.		
5	X_TEST (WO)	<b>Transmission Test (Write Only)</b> — Setting this bit causes the GXm processor to immediately transmit the current contents of the serial packet. This bit is write only and is used primarily for test. This bit returns 0 on a read.		
4:3	X_FREQ	<b>Transmission Frequency</b> — This field indicates the time between serial packet transmissions. Serial packet transmissions occur at the selected interval only if at least one of the packet bits is set high: 00 = Disable transmitter; 01 = 1 ms; 10 = 5 ms; 11 = 10 ms.		
2	CPU_RD	CPU Activity Read Enable — Setting this bit high enables repormisses that are not a result of an instruction fetch. This bit is a dividingh	•	
1	CPU_EN	CPU Activity Master Enable — Setting this bit high enables rep misses in bit 6 of the serial transmission packet. When enabled, t is reported on any read (assuming the CREN is set high) or write resulted from an instruction fetch.	he CPU Level-1 cache miss activity	
0	VID_EN	Video Event Enable — Setting this bit high enables video decor the serial transmission packet. CPU or graphics-pipeline accesse play-controller-register accesses are also reported.		
GX_BASE	+8508h-850Bh	PM_CNTRL_CSTP Register (R/W)	Default Value = xxxxxx00h	
31:8	RSVD	Reserved — These bits are not used. Do not write to these bits.		
7:1	RSVD	Reserved — Set to 0.		
0	CLK_STP	Clock Stop — This bit configures the GXm processor for Susper Mode:	nd Refresh Mode or 3-Volt Suspend	
		0 = Suspend Refresh Mode. The clocks to the memory and disp 1 = 3-Volt Suspend Mode. All internal clocks are stopped.	lay controller are active.	
and car	d asserts the Suspen to be stopped. If this re	high and the Suspend input pin (SUSP#) is asserted, the GXm produced Acknowledge output pin (SUSPA#). Once SUSPA# is asserted the egister is cleared, the internal memory-controller and display-controller, and the SYSCLK input can not be stopped.	ne GXm processor's SYSCLK input	
GX_BASE	+850Ch-850Fh	PM_SER_PACK Register (R/W)	Default Value = xxxxxx00h	
31:8	RSVD	Reserved — These bits are not used. Do not write to these bits.		
7	VID_IRQ	Video IRQ — This bit indicates the occurrence of a video vertical sync pulse. This bit is set at the same timer that the VINT (Vertical Interrupt) bit is set in the DC_TIMING_CFG register. The VINT bit has a corresponding enable bit (VIEN) in the DC_TIM_CFG register.		
6	CPU_ACT	CPU Activity — This bit indicates the occurrence of a level 1 cac instruction fetch. This bit has a corresponding enable bit in the P		
5:2	RSVD	Reserved — Set to 0.		
1	USR_DEF	Programmable Address Decode — This bit indicates the occur address decode. This bit is set based on the values of the PM_B register. The PM_BASE register can be initialized to any address	BASE register and the PM_MASK	

## Power Management (Continued)

Table 6-2. Power Management Control and Status Registers (Continued)

E	Bit	Name	Description
	0	VID_DEC	<b>Video Decode</b> — This bit indicates that the CPU has accessed either the Display Controller registers or the graphics memory region. This bit has a corresponding enable bit in the PM_CNTRL_TEN.

**Note:** The GXm processor transmits the contents of the serial packet only when a bit in the packet register is set and the interval counter has elapsed. The CS5530 decodes the serial packet after each transmission. Once a bit in the packet is set, it will remain set until the completion of the next packet transmission. Successive events of the same type that occur between packet transmissions are ignored. Multiple unique events between packet transmissions will accumulate in this register.

## Table 6-3. Power Management Programmable Address Region Registers

Bit	Name	Description				
Index FFFFF6Ch		PM_BASE Register (R/W) Default Value = 00000				
31:28	RSVD	Reserved — Set to 0.				
27:2	BASE_ADDR	Base Address — This is the word-aligned base address for pare. The actual address range is determined with this field a				
1:0	RSVD	Reserved — Set to 0.				
Index FFF	FFF7Ch	PM_MASK Register (R/W)	Default Value = 0000000h			
31:28	RSVD	Reserved — Set to 0.				
27:2	ADR_MASK	Address Mask — This field is the address mask for the BAS ter. If a bit in the ADR_MASK field is cleared the corresponding match the processor address. If a bit in the mask field is set BASE_ADDR field always compares. If the processor cycle to RE bits, and all bits in the BADD field match the processor are bit 1 will be set high in the serial transmission packet.	ing bit in the BASE_ADDR field must high, the corresponding bit in the type matches the values of the WE and			
1	WE	Write Enable — Compare memory write cycles with BASE_ 0 = Disable; 1 = Enable.	ADDR and ADR_MASK:			
0	RE	<b>Read Enable</b> — Compare memory read cycles with BASE_0 0 = Disable; 1 = Enable	ADDR and ADR_MASK:			

## 7.0 Electrical Specifications

This section provides information on electrical connections, absolute maximum ratings, required operating conditions, DC characteristics, and AC characteristics for the Geode GXm processor. All voltage values in the Electrical Specifications are with respect to  $V_{\rm SS}$  unless otherwise noted. For detailed information on the PCI bus electrical specification refer to Chapter 4 of the PCI Bus Specification, Revision 2.1.

#### 7.1 PART NUMBERS

The following part numbers designate the various speeds available. For all speeds, the  $V_{CC2}$  voltage is 2.9V nominal and the  $V_{CC3}$  voltage is 3.3V nominal.

**Table 7-1. Part Numbers** 

Core Frequency (MHz)	Temperature (Degree C)	Part Marking
266	70	GXm-266P 2.9V 70C
	85	GXm-266P 2.9V 85C
	70	GXm-266B 2.9V 70C
	85	GXm-266B 2.9V 85C
233	70	GXm-233P 2.9V 70C
	85	GXm-233P 2.9V 85C
	70	GXm-233B 2.9V 70C
	85	GXm-233B 2.9V 85C
200	70	GXm-200P 2.9V 70C
	85	GXm-200P 2.9V 85C
	70	GXm-200B 2.9V 70C
	85	GXm-200B 2.9V 85C
180	70	GXm-180P 2.9V 70C
	85	GXm-180P 2.9V 85C
	70	GXm-180B 2.9V 70C
	85	GXm-180B 2.9V 85C
	BGA Package	

## P = SPGA Package

## 7.2 ELECTRICAL CONNECTIONS

#### 7.2.1 Power/Ground Connections and Decoupling

Testing and operating the GXm processor requires the use of standard high frequency techniques to reduce parasitic effects. These effects can be minimized by filtering the DC power leads with low-inductance decoupling capacitors, using low-impedance wiring, and by utilizing all of the  $V_{\rm CC2}$ ,  $V_{\rm CC3}$ , and VSS pins.

# 7.2.2 Power Sequencing the Core and I/O Voltages

With two voltages connected to the GXm processor, it is important that the voltages come up in the correct order.  $V_{CC2}$  should come up at or before  $V_{CC3}$ . There are no additional timing requirements related to this sequence.

#### 7.2.3 NC-Designated Pins

Pins designated NC (No Connection) should be left disconnected. Connecting an NC pin to a pull-up/-down resistor, or an active signal could cause unexpected results and possible circuit malfunctions.

### 7.2.4 Pull-Up and Pull-Down Resistors

Table 7-2 lists the input pins that are internally connected to a 20-kohm pull-up/-down resistor. When unused, these inputs do not require connection to an external pull-up/-down resistor.

Table 7-2. Pins with 20-kohm Internal Resistor

Signal Name	BGA Ball No.	SPGA Pin No.	PU/PD
SUSP#*	H2	M4	Pull-up
FRAME#	A8	C13	Pull-up
IRDY#	C9	D14	Pull-up
TRDY#	B9	B14	Pull-up
STOP#	C11	A15	Pull-up
LOCK#	B11	B16	Pull-up
DEVSEL#	A9	E15	Pull-up
PERR#	A11	D16	Pull-up
SERR#	C12	A17	Pull-up
REQ[2:0]#	D3, H3, E3	E3, K2, E1	Pull-up
TCLK	J2	P4	Pull-up
TMS	H1	N3	Pull-up
TDI	D2	F4	Pull-up
TEST	F3	J5	Pull-down
Note: *SUSP# is	s pulled up v	vhen not act	ive.

#### **Note:** \*SUSP# is pulled up when not active.

#### 7.2.5 Unused Input Pins

All inputs not used by the system designer and not listed in Table 7-2 should be kept at either ground or  $V_{CC3}.$  To prevent possible spurious operation, connect active-high inputs to ground through a 20-kohm (±10%) pull-down resistor and active-low inputs to  $V_{CC3}$  through a 20-kohm (±10%) pull-up resistor.

## 7.3 ABSOLUTE MAXIMUM RATINGS

Table 7-3 lists absolute maximum ratings for the GXm processor. Stresses beyond the listed ratings may cause permanent damage to the device. Exposure to conditions beyond these limits may (1) reduce device reliability and (2) result in premature failure even when there is no immediately apparent sign of failure. Prolonged exposure to conditions at or near the absolute maximum ratings may also result

in reduced useful life and reliability. These are stress ratings only and do not imply that operation under any conditions other than those listed under Table 7-4 on page 184 is possible.

**Table 7-3. Absolute Maximum Ratings** 

Parameter	Min	Max	Units	Notes
Operating Case Temperature	-65	110	°C	Power Applied
Storage Temperature	<del>-</del> 65	150	°C	No Bias
Supply Voltage		3.2	V	
Voltage On Any Pin	-0.5	6.0	V	
Input Clamp Current, I <sub>IK</sub>	-0.5	10	mA	Power Applied
Output Clamp Current, I <sub>OK</sub>		25	mA	Power Applied

## 7.4 OPERATING CONDITIONS

Table 7-4 lists the operating conditions for the GXm processor.

**Table 7-4. Operating Conditions** 

Symbol	Parameter	Min	Max	Units	Notes
T <sub>C</sub>	Operating Case Temperature	0	70	°C	For Desktop Applications
T <sub>C</sub>	Operating Case Temperature	0	85	°C	For Notebook Applications
V <sub>CC2</sub>	Supply Voltage (2.9V nominal)	2.75	3.05	V	
V <sub>CC3</sub>	Supply Voltage (3.3V nominal)	3.14	3.46	V	
V <sub>IH</sub>	High-Level Input Voltage:				
	All input and I/O pins except SDRAM Interface and SYSCLK	2.0	5.5	V	Note 1
	SDRAM Interface	2.0	V <sub>CC3</sub> +0.5	V	Note 2
	SYSCLK	2.7	5.5	V	Note 1
V <sub>IL</sub>	Low-Level Input Voltage:				
	All except PCI bus and SYSCLK	-0.5	0.8	V	
	PCI bus	-0.5	0.3*V <sub>CC3</sub>	V	
	SYSCLK	-0.5	0.4	V	
I <sub>OH</sub>	High-Level Output Current		-2	mA	$V_O = V_{OH} (Min)$
I <sub>OL</sub>	Low-Level Output Current		5	mA	$V_O = V_{OL} (Max)$

**Notes:** 1) This parameter indicates that these pins are tolerant to the PCI 5 Volt Signaling Environment DC specification.

2) SDRAM Interface Pins: BA[1:0], CAS[A:B]#, CKE[A:B], CS[3:0]#, DQM[7:0], MA[12:0], MD[63:0], RASA#, RASB#, SDCLK\_IN, SDCLK\_OUT, SDCLK[3:0], TEST[3:0], WE[A:B]#

## 7.5 DC CHARACTERISTICS

DC characteristics were measured under the operating conditions listed in Table 7-4 on page 184.

**Table 7-5. DC Characteristics** 

Symbol	Parameter	Min	Max	Units	Notes
V <sub>OL</sub>	Output Low Voltage		0.4	V	I <sub>OL</sub> = 5 mA
V <sub>OH</sub>	Output High Voltage	2.4		V	$I_{OH} = -2 \text{ mA}$
I <sub>I</sub>	Input Leakage Current for all input pins except those with internal PU/PDs		±10	μΑ	0 < V <sub>IN</sub> < V <sub>CC3</sub> , See Table 7-2
I <sub>IH</sub>	Input Leakage Current for all pins with internal PDs.		200	μА	V <sub>IH</sub> = 2.4 V, See Table 7-2
I <sub>IL</sub>	Input Leakage Current for all pins with internal PUs.		-400	μА	V <sub>IL</sub> = 0.35 V, See Table 7-2
I <sub>CC</sub>	Active I <sub>CC</sub> :				
	Core $I_{CC}$ 2 at $f_{CLK}$ = 180 MHz I/O $I_{CC}$ 3 at $f_{CLK}$ = 180 MHz		2.25 0.400	Α	Note 1
	Core $I_{CC}$ 2 at $f_{CLK}$ = 200 MHz I/O $I_{CC}$ 3 at $f_{CLK}$ = 200 MHz		2.55 0.405		
	Core $I_{CC}$ 2 at $f_{CLK}$ = 233 MHz I/O $I_{CC}$ 3 at $f_{CLK}$ = 233M Hz		2.85 0.410		
	Core $I_{CC}$ 2 at $f_{CLK}$ = 266 MHz I/O $I_{CC}$ 3 at $f_{CLK}$ = 266 MHz		3.10 0.415		
I <sub>CCSM</sub>	Suspend Mode I <sub>CC</sub> :				
	Core $I_{CC}^2$ at $f_{CLK} = 180 \text{ MHz}$ I/O $I_{CC}^3$ at $f_{CLK} = 180 \text{ MHz}$		18 8	mA	Notes 1 and 4
	Core $I_{CC}$ 2 at $f_{CLK}$ = 200 MHz I/O $I_{CC}$ 3 at $f_{CLK}$ = 200 MHz		22 9		
	Core $I_{CC}^2$ at $f_{CLK}^2 = 233 \text{ MHz}$ I/O $I_{CC}^3$ at $f_{CLK}^2 = 233 \text{ MHz}$		25 10		
	Core $I_{CC}^2$ at $f_{CLK}^2 = 266 \text{ MHz}$ I/O $I_{CC}^3$ at $f_{CLK}^2 = 266 \text{ MHz}$		28 11		
I <sub>ccss</sub>	Standby I <sub>CC</sub> (Suspend and CLK Stopped):			I.	1
	Core $I_{CC}$ 2 at $f_{CLK}$ = 0 MHz I/O $I_{CC}$ 3 at $f_{CLK}$ = 0 MHz		10 5	mA	Notes 1 and 3
C <sub>IN</sub>	Input Capacitance		16	pF	f = 1 MHz, Note 2
C <sub>OUT</sub>	Output or I/O Capacitance		16	pF	f = 1 MHz, Note 2
C <sub>CLK</sub>	CLK Capacitance		12	pF	f = 1 MHz, Note 2

Notes: 1. fCLK ratings refer to internal clock frequency.

- 2. Not 100% tested.
- 3. All inputs are at 0.2 V or VCC3 0.2 (CMOS levels). All inputs are held static and all outputs are unloaded (static IOUT = 0 mA).
- 4. All inputs are at 0.2 V or VCC3 0.2 (CMOS levels). All inputs except clock are held static and all outputs are unloaded (static IOUT = 0 mA).

## 7.6 AC CHARACTERISTICS


The following tables list the AC characteristics including output delays, input setup requirements, input hold requirements and output float delays. The rising-clockedge reference level  $V_{\rm REF}$  and other reference levels are shown in Table 7-6. Input or output signals must cross these levels during testing.

Input setup and hold times are specified minimums that define the smallest acceptable sampling window for which a synchronous input signal must be stable for correct operation.

All AC tests are at  $V_{CC2}$  = 2.75V to 3.05V (2.9V nominal),  $T_C$  = 0°C to 70°C or 85°,  $C_L$  = 50 pF unless otherwise specified.

Table 7-6. Drive Level and Measurement Points for Switching Characteristics

Symbol	Voltage (V)
V <sub>REF</sub>	1.5
V <sub>IHD</sub>	2.4
V <sub>ILD</sub>	0.4



**Legend:** A = Maximum Output Delay Specification

B = Minimum Output Delay Specification

C = Minimum Input Setup Specification

D = Minimum Input Hold Specification

Figure 7-1. Drive Level and Measurement Points for Switching Characteristics

Table 7-7. Clock Signals

		180 MHz (6x) (Note)		200 MHz (6x) (Note)		233 MHz (7x) (Note)		266 MHz (8x) (Note)			
Symbol	ParameterT	Min	Max	Min	Max	Min	Max	Min	Max	Units	
t1	SYSCLK Period		33.3		30.0		30.0		30.0	ns	
t2	SYSCLK Period Stability		±250		±250		±250		±250	ps	
t3	SYSCLK High Time	10		10		10		10		ns	
t4	SYSCLK Low Time	10		10		10		10		ns	
t5	SYSCLK Fall Time	0.15	2.0	0.15	2.0	0.15	2.0	0.15	2.0	ns	
t6	SYSCLK Rise Time	0.15	2.0	0.15	2.0	0.15	2.0	0.15	2.0	ns	
t7	DCLK Period	7.3		7.3		7.3		7.3		ns	
t8	DCLK Rise/Fall Time		3.0		3.0		3.0		3.0	ns	
t9	SDCLK_OUT, SDCLK[3:0] Period	14.5	19.5	13	17	11	16	10	13	ns	
t10	SDCLK_OUT, SDCLK[3:0] High Time	7.5		6.5		5.5		5		ns	
t11	SDCLK_OUT, SDCLK[3:0] Low Time	7.5		6.5		5.5		5		ns	
t12	SDCLK_OUT, SDCLK[3:0] Fall Time	0.15	2.0	0.15	2.0	0.15	2.0	0.15	2.0	ns	
t13	SDCLK_OUT, SDCLK[3:0] Rise Time	0.15	2.0	0.15	2.0	0.15	2.0	0.15	2.0	ns	

Note: SDCLK timings (t9-t13) assume an SDCLK that is a "divide by 3" from the internal core clock. Hence:

180 MHz (6x) = 60.0 MHz SDCLK 200 MHz (6x) = 66.7 MHz SDCLK 233 MHz (7x) = 77.7 MHz SDCLK 266 MHz (8x) = 88.7 MHz SDCLK




Figure 7-1 SYSCLK Timing and Measurement Points




Figure 7-2. DCLK Timing and Measurement Points




Figure 7-3. SDCLK, SDCLK[3:0] Timing and Measurement Points

Table 7-8. System Signals

Parameter	Min	Max	Unit	Notes
Setup Time for RESET, INTR	5		ns	Note
Hold Time for RESET, INTR	2		ns	Note
Setup Time for SMI#, SUSP#, FLT#	5		ns	
Hold Time for SMI#, SUSP#, FLT#	2		ns	
Valid Delay for IRQ13, SUSPA#	2	15	ns	
Valid Delay for SERIALP	2	15	ns	

**Note:** The system signals may be asynchronous. The setup/hold times are required for determining static behavior.

Table 7-9. PCI Interface Signals

Symbol	Parameter	Min	Max	Unit	Notes
t <sub>VAL1</sub>	Delay Time, SYSCLK to Signal Valid for Bused Signals	2	11	ns	
t <sub>VAL2</sub>	Delay Time, SYSCLK to Signal Valid for GNT#	2	12	ns	Note
t <sub>ON</sub>	Delay Time, Float to Active	2		ns	
t <sub>OFF</sub>	Delay Time, Active to Float		28	ns	
t <sub>SU1</sub>	Input Setup Time for Bused Signals	7		ns	
t <sub>SU2</sub>	Input Setup Time for REQ#	12		ns	Note
t <sub>H</sub>	Input Hold Time to SYSCLK	0		ns	

**Note:** GNT# and REQ# are point-to-point signals. All other PCI interface signals are bused. Refer to Chapter 4 of PCI Local Bus Specification, Revision 2.1, for more detailed information.




Figure 7-4. Output Timing




Figure 7-5. Input Timing

Table 7-10. SDRAM Interface Signals

Symbol	Parameter	Min	Max	Unit
t1	CNTRL* Output Valid from SDCLK[3:0]	Equation Number = -1.5 (see below)	Equation Number = -1.0 (see below)	ns
t2	MA[12:0], BA[1:0] Output Valid from SDCLK[3:0]	Equation Number = -1.7 (see below)	Equation Number = -1.2 (see below)	ns
t3	MD[63:0] Output Valid from SDCLK[3:0]	Equation Number = -1.6 (see below)	Equation Number = -0.3 (see below)	ns
t4	MD[63:0] Read Data in Setup to SDCLKIN	0		ns
t5	MD[63:0] Read Data Hold to SDCLKIN	2.0		ns

\*CNTRL = RASA#, RASB# CASA#, CASB#, WEA#, WEB#, CKEA, CKEB, DQM[7:0], CS[3:0]#. Load = 50pF, Core Vcc = 2.9, I/O Vcc = 3.3V,  $25^{\circ}C$ .

Output Valid Equation: Use Min or Max number in equation: Min# or Max# + (x \* y)

Where:  $x = \text{shift value applied to SHFTSDCLK field and } y = (\text{core clock period}) \div 2$ Note that SHFTSDCLK field = GX\_BASE+8404h[5:3], see page 109.

#### **Equation Example:**

A 200 MHz GXm processor running a 66 MHz SDRAM bus, with a shift value of 2:

t1 Min =  $-1.5 + (2 * (5 \div 2)) = 3.5$  ns t1 Max =  $-1.0 + (2 * (5 \div 2)) = 4.0$  ns




Figure 7-6. Output Valid Timing




Figure 7-7. Setup and Hold Timings - Read Data In

Table 7-11. Video Interface Signals

Symbol	Parameter	Min	Max	Unit
t1	PCLK Period	7.4	40	ns
t2	PCLK High Time	3		ns
t3	PCLK Low Time	3		ns
t4	PIXEL[17:0], CRT_HSYNC, CRT_VSYNC, FP_HSYNC, FP_VSYNC, ENA_DISP Valid Delay from PCLK Rising Edge	2	5	ns
t5	VID_CLK Period	8.5		ns
t6	VID_RDY Setup to VID_CLK Rising Edge	5		ns
t7	VID_RDY Hold to VID_CLK Rising Edge	2		ns
t8	VID_VAL, VID_DATA[7:0] Valid Delay from VID_CLK Rising Edge	2	5	ns
t9	DCLK Period	7.4		ns
t10	DCLK Rise/Fall Time		3	ns
tcyc	DCLK Duty Cycle	40	60	%




Figure 7-8. Graphics Port Timing




Figure 7-9. Video Port Timing




Figure 7-10. DCLK Timing

Table 7-12. JTAG AC Specification

Symbol	Parameter	Min	Max	Unit
	TCK Frequency (MHz)		25	MHz
t1	TCK Period	40		ns
t2	TCK High Time	10		ns
t3	TCK Low Time	10		ns
t4	TCK Rise Time		4	ns
t5	TCK Fall Time		4	ns
t6	TDO Valid Delay	3	25	ns
t7	Non-test Outputs Valid Delay	3	25	ns
t8	TDO Float Delay		30	ns
t9	Non-test Outputs Float Delay		36	ns
t10	TDI, TMS Setup Time	8		ns
t11	Non-test Inputs Setup Time	8		ns
t12	TDI, TMS Hold Time	7		ns
t13	Non-test Inputs Hold Time	7		ns





Figure 7-11. TCK Timing and Measurement Points



## 8.0 Package Specifications

The thermal characteristics and mechanical dimensions for the Geode GXm processor are provided on the following pages.

#### 8.1 THERMAL CHARACTERISTICS

Table 8-1 shows the junction-to-case thermal resistance of the SPGA and BGA package and can be used to calculate the junction (die) temperature under any given circumstance.

Table 8-1. Junction-to-Case Thermal Resistance for SPGA and BGA Packages

Package	θЈС
SPGA	1.7 °C/W
BGA	1.1 °C/W

Note that there is no specification for maximum junction temperature given since the operation of both SPGA and BGA devices are guaranteed to a case temperature range of 0°C to 85°C. As long as the case temperature of the device is maintained within this range, the junction temperature of the die will also be maintained within its allowable operating range. However, the die (junction) temperature under a given operating condition can be calculated by using the following equation:

$$T_J = T_C + (P * \theta_{JC})$$

where:

 $T_J$  = Junction temperature (°C)

T<sub>C</sub> = Case temperature at top center of package (°C)

P = Power dissipation (W)

 $\theta_{JC}$  = Junction-to-case thermal resistance (°C/W)

As stated previously, a maximum junction temperature is not specified since a maximum case temperature is. Therefore, the following equation can be used to calculate the maximum thermal resistance required of the thermal solution for a given maximum ambient temperature:

$$\theta_{CS} + \theta_{SA} = \frac{T_C - T_A}{P}$$

where:

θ<sub>CS</sub> = Max case-to-heatsink thermal resistance (°C/W) allowed for thermal solution.

θ<sub>SA</sub> = Max heatsink-to-ambient thermal resistance (°C/W) allowed for thermal solution.

 $T_A = Max$  ambient temperature (°C)

 $T_C = Max$  case temperature at top center of package (°C)

P = Max power dissipation (W)

If thermal grease is used between the case and heatsink,  $\theta_{CS}$  will reduce to about 0.01 °C/W. Therefore, the above equation can be simplified to:

$$\theta_{CA} = \frac{T_C - T_A}{P}$$

where:

 $\theta_{CA} = \theta_{CS} = \text{Max case-to-ambient thermal resistance}$  (°C/W) allowed for thermal solution.

The calculated  $\theta_{CA}$  value (examples shown in Table 8-2) represents the maximum allowed thermal resistance of the selected cooling solution which is required to maintain the 85°C case temperature for the application in which the device is used.

These examples are given for reference only. The actual value used for Maximum Power (P) and ambient temperature  $(T_A)$  is determined by the system designer based on system configuration, extremes of the operating environment, and whether active thermal management (via Suspend Modulation) of the processor is employed.

## Package Specifications (continued)

Table 8-2. Case-to-Ambient Thermal Resistance Examples @ 85°C

Core Voltage	Core	Maximum	$\theta_{ extsf{CA}}$ for Different Ambient Temperatures (°C/W)				
(V <sub>CC2</sub> )	Frequency	Power	20°C	25°C	30°C	35°C	40°C
2.9V	266 MHz	7.7W	8.44	7.79	7.14	6.49	5.84
(Nominal)	233 MHz	7.1W	9.15	8.45	7.75	7.04	6.34
	200 MHz	6.4W	10.16	9.38	8.59	7.81	7.03
	180 MHz	6.0W	10.83	10.00	9.17	8.33	7.50

#### 8.1.1 Heatsink Considerations

As described previously, Table 8-2 shows the maximum allowed thermal resistance of a heatsink for particular operating environments. The calculated values, defined as  $\theta_{CA}$ , represent the required ability of a particular heatsink to transfer heat generated by the processor from its case into the air, thereby maintaining the case temperature at or below 85°C. Because  $\theta_{CA}$  is a measure of thermal resistivity, it is inversely proportional to the heatsink's ability to dissipate heat or it's thermal conductivity.

**Note:** A "perfect" heatsink would be able to maintain a case temperature equal to that of the ambient air inside the system chassis.

Looking at Table 8-2, it can be seen that as ambient temperature (T<sub>A</sub>) increases,  $\theta_{CA}$  decreases, and that as power consumption of the processor (P) increases,  $\theta_{CA}$  decreases. Thus, the ability of the heatsink to dissipate thermal energy must increase as the processor power increases and as the temperature inside the enclosure increases.

While  $\theta_{\text{CA}}$  is a useful parameter to calculate, heatsinks are not typically specified in terms of a single  $\theta_{CA}$ . This is because the thermal resistivity of a heatsink is not constant across power or temperature. In fact, heatsinks become slightly less efficient as the amount of heat they are trying to dissipate increases. For this reason, heatsinks are typically specified by graphs that plot heat dissipation (in watts) vs. mounting surface (case) temperature rise above ambient (in °C). This method is necessary because ambient and case temperatures fluctuate constantly during normal operation of the system. The system designer must be careful to choose the proper heatsink by matching the required  $\theta_{\text{CA}}$  with the thermal dissipation curve of the device under the entire range of operating conditions in order to make sure that a case temperature of 85°C is never surpassed.

## Package Specifications (continued)

To choose the proper heatsink, the system designer must make sure that the calculated  $\theta_{CA}$  falls above the curve (shaded area). The curve itself defines the minimum temperature rise above ambient that the heatsink can maintain.

See Figure 8-1 as an example of a particular heatsink under consideration.




Figure 8-1. Heatsink Example

### **Example 1**

Assume P (max) = 5W and  $T_A$  (max) = 40°C.

Therefore:

$$\theta_{CA} = \frac{T_C - T_A}{P}$$

$$\theta_{\mathsf{CA}} = \frac{(85 - 40)}{5}$$

$$\theta_{CA} = 9$$

In this case, the heatsink under consideration is more than adequate since at 5W worst case, it can maintain a 40°C case temperature rise above ambient ( $\theta_{CA}=9$ ) when a maximum of 45°C ( $\theta_{CA}=8$ ) is required.

### Example 2

Assume P (max) = 10W and  $T_A$  (max) = 40°C.

Therefore:

$$\theta_{CA} = \frac{T_C - T_A}{P}$$

$$\theta_{\mathsf{CA}} = \frac{(85 - 40)}{9}$$

$$\theta_{CA} = 5$$


In this case, the heatsink under consideration is NOT adequate to maintain the 45°C case temperature rise above ambient for a 9W processor.

For more information on thermal design considerations or heatsink properties, refer to the Product Selection Guide of any leading vendor of Thermal Engineering solutions.

## Package Specifications (continued)

## 8.2 MECHANICAL PACKAGE OUTLINES

Dimensions for the BGA package are shown in Figure 8-2. Figure 8-3 shows the SPGA dimensions. Table 8-3 gives the legend for the symbols used in both package outlines.



	Millin	neters	Inc	hes
Sym	Min	Max	Min	Max
Α	1.45	2.23	0.057	0.088
A1	0.50	0.70	0.020	0.028
A2	0.43	0.83	0.017	0.033
aaa		0.20		0.008
В	0.60	0.90	0.024	0.035
D	34.80	35.20	1.370	1.386
D1	31.55	31.95	1.242	1.258
D2	32.80	35.20	1.291	1.386
E1	1.12	1.42	0.044	0.056
F		0.35		0.014
S1	1.42	1.82	0.056	0.072




Figure 8-2. 352-Terminal BGA Mechanical Package Outline




Figure 8-3. 320-Pin SPGA Mechanical Package Outline

# Package Specifications (Continued)

## Table 8-3. Mechanical Package Outline Legend

Symbol	Meaning
А	Distance from seating plane datum to highest point of body
A1	Solder ball height
A2	Laminate thickness (excluding heat spreader)
aaa	Coplanarity
В	Pin or solder ball diameter
D	Largest overall package outline dimension
D1	Length from outer pin center to outer pin center
D2	Heat spreader outline dimension
E1	BGA: Solder ball pitch SPGA: Linear spacing between true pin position centerlines
E2	Diagonal spacing between true pin position centerlines
F	Flatness
L	Distance from seating plane to tip of pin
S1	Length from outer pin/ball center to edge of laminate

## 9.0 Instruction Set

This section summarizes the Geode GXm processor instruction set and provides detailed information on the instruction encodings. The instruction set is broken into four categories:

- Processor Core Instruction Set listed in Table 9-27 on page 213
- FPU Instruction Set listed in Table 9-29 on page 225
- MMX Instruction Set listed in Table 9-31 on page 230
- National Semiconductor Extended MMX Instruction Set

   listed in Table 9-33 on page 235

These tables provide information on the instruction encoding, and the instruction clock counts for each instruction. The clock count values for these tables are based on the following assumptions

- All clock counts refer to the microprocessor core internal clock frequency. For example, clock doubled GXm processor cores will reference a clock frequency that is twice the bus frequency.
- The instruction has been prefetched, decoded and is ready for execution.
- 3. Bus cycles do not require wait states.

- There are no local bus HOLD requests delaying processor access to the bus.
- No exceptions are detected during instruction execution.
- 6. If an effective address is calculated, it does not use two general register components. One register, scaling and displacement can be used within the clock count shown. However, if the effective address calculation uses two general register components, add one clock to the clock count shown.
- All clock counts assume aligned 32-bit memory/IO operands.
- If instructions access a 32-bit operand on odd addresses, add one clock for read or write and add two clocks for read and write.
- For non-cached memory accesses, add two clocks (clock doubled GXm processor cores) or four clocks (clock tripled GXm processor cores), assuming zero wait state memory accesses.
- Locked cycles are not cacheable. Therefore, using the LOCK prefix with an instruction adds additional clocks as specified in item 9 above.

## 9.1 GENERAL INSTRUCTION SET FORMAT

Depending on the instruction, the GXm processor core instructions follow the general instruction format shown in Table 9-1.

These instructions vary in length and can start at any byte address. An instruction consists of one or more bytes that can include prefix bytes, at least one opcode byte, a mod r/m byte, an s-i-b byte, address displacement, and imme-

diate data. An instruction can be as short as one byte and as long as 15 bytes. If there are more than 15 bytes in the instruction, a general protection fault (error code 0) is generated.

The fields in the general instruction format at the byte level are summarized in Table 9-2 and detailed in the following subsections.

Table 9-1. General Instruction Set Format

		Register and Address Mode Specifier								
		me	od r/m By	/te	s-i-b Byte		s-i-b Byte		Address	Immediate
Prefix (optional)	Opcode	mod	reg	r/m	ss	index	base	Displacement	Data	
0 or More Bytes	1 or 2 Bytes	7:6	5:3	2:0	7:6	5:3	2:0	0, 8, 16, or 32 Bits	0, 8, 16, or 32 Bits	

#### **Table 9-2. Instruction Fields**

Field Name	Description
Prefix (optional)	Prefix Field(s): One or more optional fields that are used to specify segment register override, address and operand size, repeat elements in string instruction, LOCK# assertion.
Opcode	Opcode Field: Identifies instruction operation.
mod	Address Mode Specifier: Used with r/m field to select addressing mode.
reg	General Register Specifier: Uses reg, sreg3 or sreg2 encoding depending on opcode field.
r/m	Address Mode Specifier: Used with mod field to select addressing mode.
SS	Scale factor: Determines scaled-index address mode.
index	Index: Determines general register to be used as index register.
base	Base: Determines general register to be used as base register.
Address Displacement	Displacement: Determines address displacement.
Immediate Data	Immediate Data: Immediate-data operand used by instruction.

#### 9.1.1 Prefix (Optional)

Prefix bytes can be placed in front of any instruction to modify the operation of that instruction. When more than one prefix is used, the order is not important. There are five types of prefixes that can be used:

- Segment Override explicitly specifies which segment register the instruction will use for effective address calculation.
- Address Size switches between 16-bit and 32-bit addressing by selecting the non-default address size.
- Operand Size switches between 16-bit and 32-bit operand size by selecting the non-default operand size.
- Repeat is used with a string instruction to cause the instruction to be repeated for each element of the string.
- Lock is used to assert the hardware LOCK# signal during execution of the instruction.

Table 9-3 lists the encoding for different types of prefix bytes.

## 9.1.2 Opcode

The opcode field specifies the operation to be performed by the instruction. The opcode field is either one or two bytes in length and may be further defined by additional bits in the mod r/m byte. Some operations have more than one opcode, each specifying a different form of the operation. Certain opcodes name instruction groups. For example, opcode 80h names a group of operations that have an immediate operand and a register or memory operand. The reg field may appear in the second opcode byte or in the mod r/m byte.

The opcode may contain w, d, s and eee opcode fields as shown in the Table 9-27 on page 213

**Table 9-3. Instruction Prefix Summary** 

Prefix	Encoding	Description
ES:	26h	Override segment default, use ES for memory operand.
CS:	2Eh	Override segment default, use CS for memory operand.
SS:	36h	Override segment default, use SS for memory operand.
DS:	3Eh	Override segment default, use DS for memory operand.
FS:	64h	Override segment default, use FS for memory operand.
GS:	65h	Override segment default, use GS for memory operand.
Operand Size	66h	Make operand size attribute the inverse of the default.
Address Size	67h	Make address size attribute the inverse of the default.
LOCK	F0h	Assert LOCK# hardware signal.
REPNE	F2h	Repeat the following string instruction.
REP/REPE	F3h	Repeat the following string instruction.

#### 9.1.2.1 w Field (Operand Size)

When used, the 1-bit w field selects the operand size during 16-bit and 32-bit data operations. See Table 9-4.

Table 9-4. w Field Encoding

	Operand Size				
w Field	16-Bit Data Operations	32-Bit Data Operations			
0	8 bits	8 bits			
1	16 bits	32 bits			

## 9.1.2.2 d Field (Operand Direction)

When used, the d field (bit 1) determines which operand is taken as the source operand and which operand is taken as the destination. See Table 9-5.

#### 9.1.2.3 s Field (Immediate Data Field Size)

When used, the s field (bit 1) determines the size of the immediate data field. If the s bit is set, the immediate field of the opcode is 8 bits wide and is sign-extended to match the operand size of the opcode. See Table 9-6.

# 9.1.2.4 eee Field (MOV-Instruction Register Selection)

The eee field (bits [5:3]) is used to select the control, debug and test registers in the MOV instructions. The type of register and base registers selected by the eee field are listed in Table 9-7. The values shown in Table 9-7 are the only valid encodings for the eee bits.

Table 9-5. d Field Encoding

d Field	Direction of Operation	Source Operand	Destination Operand
0	Register-to-Register or Register-to-Memory	reg	mod r/m or mod ss-index- base
1	Register-to-Register or Memory-to-Register	mod r/m or mod ss-index- base	reg

## Table 9-6. s Field Encoding

	Immediate Field Size						
s Field	8-Bit 16-Bit Operand Size		32-Bit Operand Size				
0 (or not present)	8 bits	16 bits	32 bits				
1	8 bits	8 bits (sign-extended)	8 bits (sign-extended)				

#### Table 9-7. eee Field Encoding

eee Field	Register Type	Base Register
000	Control Register	CR0
010	Control Register	CR2
011	Control Register	CR3
100	Control Register	CR4
000	Debug Register	DR0
001	Debug Register	DR1
010	Debug Register	DR2
011	Debug Register	DR3
110	Debug Register	DR6
111	Debug Register	DR7
011	Test Register	TR3
100	Test Register	TR4
101	Test Register	TR5
110	Test Register	TR6
111	Test Register	TR7

## 9.1.3 mod and r/m Byte (Memory Addressing)

The mod and r/m fields within the mod r/m byte, select the type of memory addressing to be used. Some instructions use a fixed addressing mode (e.g., PUSH or POP) and therefore, these fields are not present. Table 9-8 lists the addressing method when 16-bit addressing is used and a mod r/m byte is present. Some mod r/m field encodings are dependent on the w field and are shown in Table 9-8.

Table 9-8. General Registers Selected by mod r/m Fields and w Field

		16-Bit Operation		32- Oper	Bit ation
mod	r/m	w = 0	w = 1	w = 0	w = 1
11	000	AL	AX	AL	EAX
11	001	CL	CX	CL	ECX
11	010	DL	DX	DL	EDX
11	011	BL	BX	BL	EBX
11	100	AH	SP	AH	ESP
11	101	СН	BP	СН	EBP
11	110	DH	SI	DH	ESI
11	111	ВН	DI	ВН	EDI

Table 9-9. mod r/m Field Encoding

mod Field	r/m Field	16-Bit Address Mode with mod r/m Byte	32-Bit Address Mode with mod r/m Byte and No s-i-b Byte Present
00	000	DS:[BX+SI]	DS:[EAX]
00	001	DS:[BX+DI]	DS:[ECX]
00	010	SS:[BP+SI]	DS:[EDX]
00	011	SS:[BP+DI]	DS:[EBX]
00	100	DS:[SI]	s-i-b is present (See Table 9-15)
00	101	DS:[DI]	DS:[d32]
00	110	DS:[d16]	DS:[ESI]
00	111	DS:[BX]	DS:[EDI]
01	000	DS:[BX+SI+d8]	DS:[EAX+d8]
01	001	DS:[BX+DI+d8]	DS:[ECX+d8]
01	010	SS:[BP+SI+d8]	DS:[EDX+d8]
01	011	SS:[BP+DI+d8]	DS:[EBX+d8]
01	100	DS:[SI+d8]	s-i-b is present (See Table 9-15)
01	101	DS:[DI+d8]	SS:[EBP+d8]
01	110	SS:[BP+d8]	DS:[ESI+d8]
01	111	DS:[BX+d8]	DS:[EDI+d8]
10	000	DS:[BX+SI+d16]	DS:[EAX+d32]
10	001	DS:[BX+DI+d16]	DS:[ECX+d32]
10	010	SS:[BP+SI+d16]	DS:[EDX+d32]
10	011	SS:[BP+DI+d16]	DS:[EBX+d32]
10	100	DS:[SI+d16]	s-i-b is present (See Table 9-15)
10	101	DS:[DI+d16]	SS:[EBP+d32]
10	110	SS:[BP+d16]	DS:[ESI+d32]
10	111	DS:[BX+d16]	DS:[EDI+d32]
11	xxx	See Table 9-8.	See Table 9-8

**Note:** Note: d8 refers to 8-bit displacement, and d16 refers to 16-bit displacement.

## 9.1.4 reg Field

The reg field (Table 9-10) determines which general registers are to be used. The selected register is dependent on whether a 16- or 32-bit operation is current and on the status of the w bit.

# 9.1.4.1 sreg2 Field (ES, CS, SS, DS Register Selection)

The sreg2 field (Table 9-11) is a 2-bit field that allows one of the four 286-type segment registers to be specified.

# 9.1.4.2 sreg3 Field (FS and GS Segment Register Selection)

The sreg3 field (Table 9-12) is 3-bit field that is similar to the sreg2 field, but allows use of the FS and GS segment registers.

Table 9-10. General Registers Selected by reg Field

	16-Bit Operation		32-Bit	Operation
reg	w = 0	w = 1	w = 0	w = 1
000	AL	AX	AL	EAX
001	CL	CX	CL	ECX
010	DL	DX	DL	EDX
011	BL	BX	BL	EBX
100	AH	SP	AH	ESP
101	СН	BP	СН	EBP
110	DH	SI	DH	ESI
111	ВН	DI	ВН	EDI

Table 9-11. sreg2 Field Encoding

sreg2 Field	Segment Register Selected
00	ES
01	CS
10	SS
11	DS

Table 9-12. sreg3 Field Encoding

sreg3 Field	Segment Register Selected
000	ES
001	CS
010	SS
011	DS
100	FS
101	GS
110	Undefined
111	Undefined

#### 9.1.5 s-i-b Byte (Scale, Indexing, Base)

The s-i-b fields provide scale factor, indexing and a base field for address selection. The ss, index and base fields are described next.

#### 9.1.5.1 ss Field (Scale Selection)

The ss field (Table 9-13) specifies the scale factor used in the offset mechanism for address calculation. The scale factor multiplies the index value to provide one of the components used to calculate the offset address.

Table 9-13. ss Field Encoding

ss Field	Scale Factor
00	x1
01	x2
01	x4
11	x8

#### 9.1.5.2 index Field (Index Selection)

The index field (Table 9-14) specifies the index register used by the offset mechanism for offset address calculation. When no index register is used (index field = 100), the ss value must be 00 or the effective address is undefined.

Table 9-14. index Field Encoding

Index Field	Index Register
000	EAX
001	ECX
010	EDX
011	EBX
100	none
101	EBP
110	ESI
111	EDI

#### 9.1.5.3 Base Field (s-i-b Present)

In Table 9-9 on page 205, the note "s-i-b present" for certain entries forces the use of the mod and base field as listed in Table 9-15. The first two digits in the first column of Table 9-15 identify the mod bits in the mod r/m byte. The last three digits in the first column of this table identifies the base fields in the s-i-b byte.

Table 9-15. mod base Field Encoding

mod Field within mode/rm Byte (bits 7:6)	base Field within s-i-b Byte (bits 2:0)	32-Bit Address Mode with mod r/m and s-i-b Bytes Present
00	000	DS:[EAX+(scaled index)]
00	001	DS:[ECX+(scaled index)]
00	010	DS:[EDX+(scaled index)]
00	011	DS:[EBX+(scaled index)]
00	100	SS:[ESP+(scaled index)]
00	101	DS:[d32+(scaled index)]
00	110	DS:[ESI+(scaled index)]
00	111	DS:[EDI+(scaled index)]
01	000	DS:[EAX+(scaled index)+d8]
01	001	DS:[ECX+(scaled index)+d8]
01	010	DS:[EDX+(scaled index)+d8]
01	011	DS:[EBX+(scaled index)+d8]
01	100	SS:[ESP+(scaled index)+d8]
01	101	SS:[EBP+(scaled index)+d8]
01	110	DS:[ESI+(scaled index)+d8]
01	111	DS:[EDI+(scaled index)+d8]
10	000	DS:[EAX+(scaled index)+d32]
10	001	DS:[ECX+(scaled index)+d32]
10	010	DS:[EDX+(scaled index)+d32]
10	011	DS:[EBX+(scaled index)+d32]
10	100	SS:[ESP+(scaled index)+d32]
10	101	SS:[EBP+(scaled index)+d32]
10	110	DS:[ESI+(scaled index)+d32]
10	111	DS:[EDI+(scaled index)+d32]

#### 9.2 CPUID INSTRUCTION

The CPUID instruction (opcode 0FA2) allows the software to make processor inquiries as to the vendor, family, model, stepping, features and also provides cache information. The GXm with MMX supports both the standard and National Semiconductor extended CPUID levels.

The presence of the CPUID instruction is indicated by the ability to change the value of the ID Flag, bit 21 in the EFLAGS register.

The CPUID level allows the CPUID instruction to return different information in the EAX, EBX, ECX, and EDX registers. The level is determined by the initialized value of the EAX register before the instruction is executed. A summary of the CPUID levels is shown in Table 9-16.

Table 9-16. CPUID Levels Summary

CPUID Type	Initialized EAX Register	Returned Data in EAX, EBX, ECX, EDX Registers
Standard	00000000h	Maximum standard levels, CPU vendor string
Standard	00000001h	Model, family, type and features
Standard	00000002h	TLB and cache information
Extended	80000000h	Maximum extended levels
Extended	80000001h	Extended model, family, type and features
Extended	80000002h	CPU marketing name string
Extended	80000003h	
Extended	80000004h	
Extended	80000005h	TLB and L1 cache description

#### 9.2.1 Standard CPUID Levels

The standard CPUID levels are part of the standard x86 instruction set.

#### 9.2.1.1 CPUID Instruction with EAX = 00000000h

Standard function 0h (EAX = 0) of the CPUID instruction returns the maximum standard CPUID levels as well as the processor vendor string.

After the instruction is executed, the EAX register contains the maximum standard CPUID levels supported. The maximum standard CPUID level is the highest acceptable value for the EAX register input. This does not include the extended CPUID levels.

The EBX through EDX registers contain the vendor string of the processor as shown in Table 9-17.

Table 9-17. CPUID Data Returned when EAX = 0

Register (Note)	Returned Contents		Description	
EAX		2		Maximum Standard Level
EBX	69 (iryC)	72	7943	Vendor ID String 1
EDX	73 (snlx)	6E	4978	Vendor ID String 2
ECX	64 (daet)	61	6574	Vendor ID String 3

Note: The register column is intentionally out of order.

#### 9.2.1.2 CPUID Instruction with EAX = 00000001h

Standard function 01h (EAX = 1) of the CPUID instruction returns the processor type, family, model, and stepping information of the current processor in the EAX register (see Table 9-18). The EBX and ECX registers are reserved.

Table 9-18. EAX, EBX, ECX CPUID Data Returned when EAX = 1

Register	Returned Contents	Description
EAX[3:0]	xx	Stepping ID
EAX[7:4]	4	Model
EAX[11:8]	5	Family
EAX[15:12]	0	Туре
EAX[31:16]	-	Reserved
EBX	-	Reserved
ECX	-	Reserved

The standard feature flags supported are returned in the EDX register as shown in Table 9-19 on page 209. Each flag refers to a specific feature and indicates if that feature is present on the processor. Some of these features have protection control in CR4. Before using any of these features on the processor, the software should check the corresponding feature flag. Attempting to execute an unavailable feature can cause exceptions and unexpected behavior. For example, software must check bit 4 before attempting to use the Time Stamp Counter instruction.

Table 9-19. EDX CPUID Data Returned when EAX = 1

		T .	
EDX	Returned Contents*	Feature Flag	CR4 Bit
EDX[0]	1	FPU On-Chip	-
EDX[1]	0	Virtual Mode Extension	-
EDX[2]	0	Debug Extensions	-
EDX[3]	0	Page Size Extensions	-
EDX[4]	1	Time Stamp Counter	2
EDX[5]	1	RDMSR / WRMSR Instructions	-
EDX[6]	0	Physical Address Extensions	-
EDX[7]	0	Machine Check Exception	-
EDX[8]	1	CMPXCHG8B Instruction	-
EDX[9]	0	On-Chip APIC Hardware	-
EDX[10]	0	Reserved	-
EDX[11]	0	SYSENTER / SYSEXIT Instructions	-
EDX[12]	0	Memory Type Range Registers	-
EDX[13]	0	Page Global Enable	-
EDX[14]	0	Machine Check Architecture	-
EDX[15]	1	Conditional Move Instructions	-
EDX[16]	0	Page Attribute Table	-
EDX[22:17]	0	Reserved	-
EDX[23]	1	MMX Instructions	-
EDX[24]	0	Fast FPU Save and Restore	-
EDX[31:25]	0	Reserved	-

**Note:** \*0 = Not supported

#### 9.2.1.3 CPUID Instruction with EAX = 00000002h

Standard function 02h (EAX = 02h) of the CPUID instruction returns information that is specific to the National Semiconductor family of processors. Information about the TLB is returned in EAX as shown in Table 9-20. Information about the L1 cache is returned in EDX.

Table 9-20. Standard CPUID with EAX = 00000002h

Register	Returned Contents	Description
EAX	xx xx 70 xxh	TLB is 32 Entry, 4-way set associative, and has 4 KByte Pages
EAX	xx xx xx 01h	The CPUID instruction needs to be executed only once with an input value of 02h to retrieve complete information about the cache and TLB
EBX		Reserved
ECX		Reserved
EDX	xx xx xx 80h	L1 cache is 16 KBytes, 4-way set associated, and has 16 bytes per line.

#### 9.2.2 Extended CPUID Levels

Testing for extended CPUID instruction support can be accomplished by executing a CPUID instruction with the EAX register initialized to 80000000h. If a value greater than or equal to 80000000h is returned to the EAX register by the CPUID instruction, the processor supports extended CPUID levels.

# 9.2.2.1 CPUID Instruction with EAX = 8000000h

Extended function 80000000h (EAX = 80000000h) of the CPUID instruction returns the maximum extended CPUID levels supported by the current processor in EAX (Table 9-21). The EBX, ECX, and EDX registers are currently reserved.

Table 9-21. Maximum Extended CPUID Level

Register	Returned Contents	Description
EAX	80000005h	Maximum Extended CPUID Level (six levels)
EBX	-	Reserved
ECX	-	Reserved
EDX	-	Reserved

# 9.2.2.2 CPUID Instruction with EAX = 8000 0001h

Extended function 80000001h (EAX = 80000001h) of the CPUID instruction returns the processor type, family, model, and stepping information of the current processor in EAX. The EBX and ECX registers are reserved.

The extended feature flags supported are returned in the EDX register as shown in Table 9-23. Each flag refers to a specific feature and indicates if that feature is present on the processor. Some of these features have protection control in CR4. Before using any of these features on the processor, the software should check the corresponding feature flag.

Table 9-22. EAX, EBX, ECX CPUID Data Returned when EAX = 80000001h

Register	Returned Contents	Description
EAX[3:0]	xx	Stepping ID
EAX[7:4]	4	Model
EAX[11:8]	5	Family
EAX[15:12]	0	Processor Type
EAX[31:16]	-	Reserved
EBX	-	Reserved
ECX	-	Reserved

Table 9-23. EDX CPUID Data Returned when EAX = 80000001h

EDX								
EDX[0]	1	FPU On-Chip	-					
EDX[1]	0	Virtual Mode Extension	-					
EDX[2]	0	Debugging Extension	-					
EDX[3]	0	Page Size Extension (4 MB)	-					
EDX[4]	1	Time Stamp Counter	2					
EDX[5]	1	National Semiconductor Model-Specific Registers (via RDMSR / WRMSR Instructions)	1					
EDX[6]	0	Reserved	-					
EDX[7]	0	Machine Check Exception	-					
EDX[8]	1	CMPXCHG8B Instruction	-					
EDX[9]	0	Reserved	-					
EDX[10]	0	Reserved	1					
EDX[11]	0	SYSCALL / SYSRET Instruction	-					
EDX[12]	0	Reserved	-					
EDX[13]	0	Page Global Enable	-					
EDX[14]	0	Reserved	-					
EDX[15]	1	Integer Conditional Move Instruction	-					
EDX[16]	0	FPU Conditional Move Instruction	-					
EDX[22:17]	0	Reserved	-					
EDX[23]	1	MMX	-					
EDX[24]	1	6x86MX Multimedia Extensions	-					

**Note:** 0 = Not supported

# 9.2.2.3 CPUID Instruction with EAX = 80000002h, 80000003h, 80000004h

Extended functions 80000002h through 80000004h (EAX = 80000002h, EAX = 80000003h, EAX = 80000004h) of the CPUID instruction return an ASCII string containing the name of the current processor. These functions eliminate the need to look up the processor name in a lookup table. Software can simply call these functions to obtain the name of the processor. The string may be 48 ASCII characters long, and is returned in little endian format. If the name is shorter than 48 characters long, the remaining bytes will be filled with ASCII NUL character (00h).

Table 9-24. Official CPU Name

80	000002h	80	000003h	80000004h						
EAX	CPU Name 1	EAX	CPU Name 5	EAX	CPU Name 9					
EBX	CPU Name 2	EBX	CPU Name 6	EBX	CPU Name 10					
ECX	CPU Name 3	ECX	CPU Name 7	ECX	CPU Name 11					
EDX	CPU Name 4	EDX	CPU Name 8	EDX	CPU Name 12					

# 9.2.2.4 CPUID Instruction with EAX = 80000005h

Extended function 80000005h (EAX = 80000005h) of the CPUID instruction returns information about the TLB and L1 cache to be looked up in a lookup table. Refer to Table 9-25.

Table 9-25. Standard CPUID with EAX = 80000005h

Register	Returned Contents	Description
EAX		Reserved
EBX	xx xx 70 xxh	TLB is 32 Entry, 4-way set associative, and has 4 KByte Pages
EBX	xx xx xx 01h	The CPUID instruction needs to be executed only once with an input value of 02h to retrieve complete information about the cache and TLB
ECX	xx xx xx 80h	L1 cache is 16 KBytes, 4-way set associated, and has 16 bytes per line.
EDX		Reserved

## 9.3 PROCESSOR CORE INSTRUCTION SET

The instruction set for the GXm processor core is summarized in Table 9-27 on page 213. The table uses several symbols and abbreviations that are described next and listed in Table 9-26.

### **Opcodes**

Opcodes are given as hex values except when they appear within brackets as binary values.

#### **Clock Counts**

The clock counts listed in the instruction set summary table are grouped by operating mode (Real and Protected) and whether there is a register/cache hit or a cache miss. In some cases, more than one clock count is shown in a column for a given instruction, or a variable is used in the clock count.

#### **Flags**

There are nine flags that are affected by the execution of instructions. The flag names have been abbreviated and various conventions used to indicate what effect the instruction has on the particular flag.

Table 9-26. Processor Core Instruction Set
Table Legend

Symbol or Abbreviation	Description										
Opcode											
#	Immediate 8-bit data										
##	Immediate 16-bit data										
###	Full immediate 32-bit data (8, 16, 32 bits)										
+	8-bit signed displacement										
+++	Full signed displacement (16, 32 bits)										
Clock Count											
/	Register operand/memory operand.										
n	Number of times operation is repeated.										
L	Level of the stack frame.										
I	Conditional jump taken   Conditional jump not taken.  (e.g. "4 1" = 4 clocks if jump taken, 1 clock if jump not taken)										
\	CPL ≤ IOPL \ CPL > IOPL (where CPL = Current Privilege Level, IOPL = I/O Privilege Level)										
Flags											
OF	Overflow Flag										
DF	Direction Flag										
IF	Interrupt Enable Flag										
TF	Trap Flag										
SF	Sign Flag										
ZF	Zero Flag										
AF	Auxiliary Flag										
PF	Parity Flag										
CF	Carry Flag										
х	Flag is modified by the instruction.										
-	Flag is not changed by the instruction.										
0	Flag is reset to "0".										
1	Flag is set to "1".										
u	Flag is undefined following execution the instruction.										

Table 9-27. Processor Core Instruction Set Summary

					ı	Flaç	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction	Opcode	O F	D F		T F					C F		Count ache Hit)	No	otes
AAA ASCII Adjust AL after Add	37	u	-	-	-	u	u	Х	u	Х	3	3		
AAD ASCII Adjust AX before Divide	D5 0A	u	-	-	-	Х	Х	u	Х	u	7	7		
AAM ASCII Adjust AX after Multiply	D4 0A	u	-	-	-	Х	Х	u	Х	u	19	19		
AAS ASCII Adjust AL after Subtract	3F	u	-	-	-	u	u	Х	u	Х	3	3		
ADC Add with Carry														
Register to Register	1 [00dw] [11 reg r/m]	х	-	-	-	Х	Х	Х	Х	Х	1	1	b	h
Register to Memory	1 [000w] [mod reg r/m]										1	1		
Memory to Register	1 [001w] [mod reg r/m]										1	1		
Immediate to Register/Memory	8 [00sw] [mod 010 r/m]###										1	1		
Immediate to Accumulator	1 [010w] ###										1	1		
ADD Integer Add	•													
Register to Register	0 [00dw] [11 reg r/m]	х	-	-	-	Х	Х	Х	Х	Х	1	1	b	h
Register to Memory	0 [000w] [mod reg r/m]										1	1	1	
Memory to Register	0 [001w] [mod reg r/m]										1	1	1	
Immediate to Register/Memory	8 [00sw] [mod 000 r/m]###										1	1		
Immediate to Accumulator	0 [010w] ###	1									1	1		
AND Boolean AND	<u> </u>												•	•
Register to Register	2 [00dw] [11 reg r/m]	0	-	-	-	Х	Х	u	Х	0	1	1	b	h
Register to Memory	2 [000w] [mod reg r/m]										1	1		
Memory to Register	2 [001w] [mod reg r/m]										1	1		
Immediate to Register/Memory	8 [00sw] [mod 100 r/m]###										1	1	1	
Immediate to Accumulator	2 [010w] ###										1	1		
ARPL Adjust Requested Privilege Level											I.	L		
From Register/Memory	63 [mod reg r/m]	-	-	-	-	-	х	-	-	-		9	а	h
BB0_Reset Set BLT Buffer 0 Pointer to the Base	0F 3A										2	2		
BB1_Reset Set BLT Buffer 1 Pointer to the Base	0F 3B										2	2		
BOUND Check Array Boundaries	•												•	•
If Out of Range (Int 5)	62 [mod reg r/m]	T-	-	-	-	-	-	-	-	-	8+INT	8+INT	b, e	g,h,j,k,r
If In Range	1										7	7		
BSF Scan Bit Forward	•												•	•
Register, Register/Memory	0F BC [mod reg r/m]	1-	-	-	-	-	Х	-	-	-	4/9+n	4/9+n	b	h
BSR Scan Bit Reverse											ı	I		1
Register, Register/Memory	0F BD [mod reg r/m]	T-	-	-	-	-	Х	-	-	-	4/11+n	4/11+n	b	h
BSWAP Byte Swap	0F C[1 reg]	-	-	-	-	-	-	-	-	-	6	6		
BT Test Bit													•	•
Register/Memory, Immediate	0F BA [mod 100 r/m]#	T-	-	-	_	-	-	_	_	х	1	1	b	h
Register/Memory, Register	0F A3 [mod reg r/m]										1/7	1/7	1	
BTC Test Bit and Complement		-									ı	I		
		_					_		_	х	2	2	b	h
Register/Memory, Immediate	0F BA [mod 111 r/m]#	-	-	-	-	-		-	_	^				
Register/Memory, Immediate  Register/Memory, Register	0F BA [mod 111 r/m]# 0F BB [mod reg r/m]	-	-	-	-	-		-	_	^				
Register/Memory, Register	0F BA [mod 111 r/m]# 0F BB [mod reg r/m]	-	-	_	_	_	_	_	_	^	2/8	2/8		
Register/Memory, Register BTR Test Bit and Reset	0F BB [mod reg r/m]	-    -	_								2/8	2/8		
Register/Memory, Register  BTR Test Bit and Reset  Register/Memory, Immediate	0F BB [mod reg r/m]  0F BA [mod 110 r/m]#	<u> </u> -  -	-		-	-	-	-	-	x	2/8	2/8	b	h
Register/Memory, Register  BTR Test Bit and Reset  Register/Memory, Immediate  Register/Memory, Register	0F BB [mod reg r/m]	-	-	-	- -	- -	-	-	-		2/8	2/8		
Register/Memory, Register  BTR Test Bit and Reset  Register/Memory, Immediate	0F BB [mod reg r/m]  0F BA [mod 110 r/m]#	-  -  -  -	-	- -	- -	- - -	- -	- - -	- -		2/8	2/8		

Table 9-27. Processor Core Instruction Set Summary (Continued)

					ı	Fla	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction			D F				Z F					Count iche Hit)	No	ites
CALL Subroutine Call														
Direct Within Segment	E8 +++	-	-	-	-	-	-	-	-	-	3	3	b	h,j,k,r
Register/Memory Indirect Within Segment	FF [mod 010 r/m]										3/4	3/4		
Direct Intersegment -Call Gate to Same Privilege -Call Gate to Different Privilege No Par's -Call Gate to Different Privilege m Par's -16-bit Task to 16-bit TSS -16-bit Task to 32-bit TSS -16-bit Task to V86 Task -32-bit Task to 16-bit TSS -32-bit Task to V86 Task	9A [unsigned full offset, selector]										9	14 24 45 51+2m 183 189 123 186 192 126		
Indirect Intersegment -Call Gate to Same Privilege -Call Gate to Different Privilege No Par's -Call Gate to Different Privilege m Par's -16-bit Task to 16-bit TSS -16-bit Task to 32-bit TSS -16-bit Task to V86 Task -32-bit Task to 16-bit TSS -32-bit Task to 32-bit TSS -32-bit Task to V86 Task	FF [mod 011 r/m]										11	15 25 46 52+2m 184 190 124 187 193 127		
CBW Convert Byte to Word	98	-	-	-			-			-	3	3		
CDQ Convert Doubleword to Quadword	99	-	-	-	-		-		-	-	2	2		
CLC Clear Carry Flag	F8	-		-	-	-	-	-	-	0	1	1		
CLD Clear Direction Flag	FC	-	0	-	-	-	-	-	-	-	4	4		
CLI Clear Interrupt Flag	FA	-					-	-	-	-	6	6		m
CLTS Clear Task Switched Flag	0F 06	-	-	-	-	-	-	-	-	-	7	7	С	ı
CMC Complement the Carry Flag	F5	-	-	-	-	-	•	-	-	Χ	3	3		
CMOVA/CMOVNBE Move if Above/Not Below or E	:qual													
Register, Register/Memory	0F 47 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVBE/CMOVNA Move if Below or Equal/Not A	bove													
Register, Register/Memory	0F 46 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVAE/CMOVNB/CMOVNC Move if Above or E	qual/Not Below/Not Carry													
Register, Register/Memory	0F 43 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVB/CMOVC/CMOVNAE Move if Below/Carry/	Not Above or Equal													
Register, Register/Memory	0F 42 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVE/CMOVZ Move if Equal/Zero														
Register, Register/Memory	0F 44 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVNE/CMOVNZ Move if Not Equal/Not Zero														
Register, Register/Memory	0F 45 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVG/CMOVNLE Move if Greater/Not Less or E	īqual													
Register, Register/Memory	0F 4F [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVLE/CMOVNG Move if Less or Equal/Not Gre	eater													
Register, Register/Memory	0F 4E [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVL/CMOVNGE Move if Less/Not Greater or E	iqual													
Register, Register/Memory	0F 4C [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVGE/CMOVNL Move if Greater or Equal/Not	Less													
Register, Register/Memory	0F 4D [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVO Move if Overflow														
Register, Register/Memory	0F 40 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVNO Move if No Overflow														
Register, Register/Memory	0F 41 [mod reg r/m]	-	_	-	_	Ξ	-	_	Ξ	_	1	1		r
CMOVP/CMOVPE Move if Parity/Parity Even														
Register, Register/Memory	0F 4A [mod reg r/m]	-	_	_	-	-	-	-	_	-	1	1		r
CMOVNP/CMOVPO Move if Not Parity/Parity Odd														
Sino viti romo vi O iviove ii ivot Failty/Failty Odd														

Table 9-27. Processor Core Instruction Set Summary (Continued)

						Flag	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction	Opcode	O F			T F							Count iche Hit)	No	otes
CMOVS Move if Sign	-										•		l.	
Register, Register/Memory	0F 48 [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		r
CMOVNS Move if Not Sign	•										•	•	l.	
Register, Register/Memory	0F 49 [mod reg r/m]	-	-	-	-	-	-		-	-	1	1		r
CMP Compare Integers														
Register to Register	3 [10dw] [11 reg r/m]	х	-	-	-	Х	Х	Х	Х	Х	1	1	b	h
Register to Memory	3 [101w] [mod reg r/m]										1	1		
Memory to Register	3 [100w] [mod reg r/m]										1	1		
Immediate to Register/Memory	8 [00sw] [mod 111 r/m] ###										1	1		
Immediate to Accumulator	3 [110w] ###										1	1		
CMPS Compare String	A [011w]	х	-	-	-	Х	Х	Х	Х	Х	6	6	b	h
CMPXCHG Compare and Exchange													•	
Register1, Register2	0F B [000w] [11 reg2 reg1]	х	-	-	-	Х	Х	Х	Х	Х	6	6		
Memory, Register	0F B [000w] [mod reg r/m]										6	6		
CMPXCHG8B Compare and Exchange 8 Bytes	0F C7 [mod 001 r/m]	Ŀ	-	-	-	-	-	-	-	-				
CPUID CPU Identification	0F A2	-	-	-	-	-	-	-	-	-	12	12		
CPU_READ Read Special CPU Register	0F 3C										1	1		
CPU_WRITE Write Special CPU Register	0F 3D										1	1		
CWD Convert Word to Doubleword	99	-	-	-	-	-	-	-	-	-	2	2		
CWDE Convert Word to Doubleword Extended	98	-	-	-	-	-		-	-	-	3	3		
DAA Decimal Adjust AL after Add	27	-	-	-	-	Х	Х	Х	Х	Х	2	2		
DAS Decimal Adjust AL after Subtract	2F	-	-	-	-	Х	х	Х	Х	Х	2	2		
DEC Decrement by 1	_											•		
Register/Memory	F [111w] [mod 001 r/m]	х	-	-	-	Х	Х	Х	Х	-	1	1	b	h
Register (short form)	4 [1 reg]										1	1		
DIV Unsigned Divide		•									•	•		
Accumulator by Register/Memory	F [011w] [mod 110 r/m]	-	-	-	-	Х	Х	u	u	-			b,e	e,h
Divisor: Byte											20	20		
Word Doubleword											29 45	29 45		
ENTER Enter New Stack Frame		-												
Level = 0	C8 ##,#	-	-	_	-	_	-	-	-	_	13	13	b	h
Level = 1								-			17	17		
Level (L) > 1											17+2*L	17+2*L		
HLT Halt	F4	+			_		-	-	_		10	10		1
IDIV Integer (Signed) Divide	1 7										10	10		
Accumulator by Register/Memory	F [011w] [mod 111 r/m]	Τ.	_	_	_	¥	х	ш	ш	_		1	b,e	e,h
Divisor: Byte	i [orrw][mod rrr mm]					^	^	u	u		20	20	5,0	0,11
Word Doubleword											29 45	29 45		
IMUL Integer (Signed) Multiply											45	40		
Accumulator by Register/Memory	F [011w] [mod 101 r/m]	х				v	х			Х		1	b	h
Multiplier: Byte	F [OTTW] [IIIOG TOT I/III]	×	-	-	-	X	Х	u	u	X	4	4	D	11
Word											5	5		
Doubleword	OF AF (	-									15	15		
Register with Register/Memory Multiplier: Word	0F AF [mod reg r/m]										5	5		
Doubleword											15	15		
Register/Memory with Immediate to Register2	6 [10s1] [mod reg r/m] ###													
Multiplier: Word Doubleword											6 16	6 16		
IN Input from I/O Port	!	+									10	10		
Fixed Port	E [010w] #	1_	_	_	_	_	_	_	_	_	8	8/22		m
Variable Port	E [110w]	╣.	-	-	•	-	•	•	•	-	8	8/22		111
		-											h	h
INS Input String from I/O Port	6 [110w]	-	-	-	-	-	-	-	-	-	11	11/25	b	h,m

Table 9-27. Processor Core Instruction Set Summary (Continued)

						Flaç	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction	Opcode	O F	D F	I F	T F	S F	Z F	A F	P F	C F		Count ache Hit)	No	otes
INC Increment by 1														
Register/Memory	F [111w] [mod 000 r/m]	х	-	-	-	х	Х	Х	Х	-	1	1	b	h
Register (short form)	4 [0 reg]										1	1		
INT Software Interrupt	•	•									•	•		•
INT i	CD#	-	-	Х	0	-	-	-	-	-	19		b,e	g,j,k,r
Protected Mode: -Interrupt or Trap to Same Privilege -Interrupt or Trap to Different Privilege -16-bit Task to 16-bit TSS by Task Gate -16-bit Task to 32-bit TSS by Task Gate -16-bit Task to 16-bit TSS by Task Gate -16-bit Task to 16-bit TSS by Task Gate -32-bit Task to 32-bit TSS by Task Gate -32-bit Task to V86 by Task Gate -V86 to 16-bit TSS by Task Gate -V86 to 732-bit TSS by Task Gate -V86 to Privilege 0 by Trap Gate/Int Gate												33 55 184 190 124 187 193 127 187 193 64		
INT 3	СС										INT	INT		
INTO	CE													
If OF==0 If OF==1 (INT 4)											4 INT	4 INT		
INVD Invalidate Cache	0F 08	-	-	-	-	-	-	-	-	-	20	20	t	t
INVLPG Invalidate TLB Entry	0F 01 [mod 111 r/m]	-	-	-	-	-	-	-	-	-	15	15		
IRET Interrupt Return														
Real Mode	CF	х	х	Х	х	х	Х	Х	Х	Х	13			g,h,j,k,r
Protected Mode: -Within Task to Same Privilege -Within Task to Different Privilege -16-bit Task to 16-bit Task -16-bit Task to 32-bit TSS -16-bit Task to V86 Task -32-bit Task to 16-bit TSS -32-bit Task to 32-bit TSS -32-bit Task to V86 Task												20 39 169 175 109 172 178 112		
JB/JNAE/JC Jump on Below/Not Above or Equal,	/Carry													
8-bit Displacement	72 +	-	-	-	-	-	-	-	-	-	1	1		r
Full Displacement	0F 82 +++										1	1		
JBE/JNA Jump on Below or Equal/Not Above	•										•	•		•
8-bit Displacement	76 +	-	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 86 +++										1	1		
JCXZ/JECXZ Jump on CX/ECX Zero	E3 +	-	-	-	-	-	-	-	-	-	2	2		r
JE/JZ Jump on Equal/Zero	•										•	•		
8-bit Displacement	74 +	-	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 84 +++										1	1		
JL/JNGE Jump on Less/Not Greater or Equal													I	
8-bit Displacement	7C +	-	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 8C +++										1	1		
JLE/JNG Jump on Less or Equal/Not Greater	1											· · ·	1	l .
8-bit Displacement	7E +	- 1-	_	_	_	_	_	-	-		1	1		r
Full Displacement	0F 8E +++										1	1		
. d., Diopiacomont	15. 52										<u> </u>	L '	L	L

Table 9-27. Processor Core Instruction Set Summary (Continued)

						-1-					Real	Prot'd	Real	Prot'd
		0	. D	_	т	Fla	_	Δ	Р	<u> </u>	Mode	Mode Count	Mode	Mode
Instruction	Opcode	F	F	F	Ė	S F	F	F	F	F		che Hit)	No	otes
JMP Unconditional Jump											1		ı	ı
8-bit Displacement	EB +	_ -	-	-	-	-	-	-	-		1	1	b	h,j,k,r
Full Displacement	E9 +++										1	1		
Register/Memory Indirect Within Segment	FF [mod 100 r/m]										1/3	1/3		
Direct Intersegment -Call Gate Same Privilege Level -16-bit Task to 16-bit TSS -16-bit Task to 32-bit TSS -16-bit Task to V86 Task -32-bit Task to 16-bit TSS -32-bit Task to 32-bit TSS -32-bit Task to V86 Task	EA [unsigned full offset, selector]										8	12 22 186 192 126 189 195 129		
Indirect Intersegment -Call Gate Same Privilege Level -16-bit Task to 16-bit TSS -16-bit Task to 32-bit TSS -16-bit Task to V86 Task -32-bit Task to 16-bit TSS -32-bit Task to 32-bit TSS -32-bit Task to V86 Task	FF [mod 101 r/m]										10	13 23 187 193 127 190 196 130		
JNB/JAE/JNC Jump on Not Below/Above or Equ	<del></del>													
8-bit Displacement	73 +	_ -	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 83 +++										1	1		
JNBE/JA Jump on Not Below or Equal/Above	<b>T</b>										1	,	1	
8-bit Displacement	77 +	_ -	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 87 +++										1	1		
JNE/JNZ Jump on Not Equal/Not Zero														
8-bit Displacement	75 +	_ -	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 85 +++										1	1		
JNL/JGE Jump on Not Less/Greater or Equal														
8-bit Displacement	7D +	_ -	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 8D +++										1	1		
JNLE/JG Jump on Not Less or Equal/Greater														
8-bit Displacement	7F +		-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 8F +++										1	1		
JNO Jump on Not Overflow														
8-bit Displacement	71 +		-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 81 +++										1	1		
JNP/JPO Jump on Not Parity/Parity Odd														
8-bit Displacement	7B +		-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 8B +++										1	1		
JNS Jump on Not Sign														
8-bit Displacement	79 +	_]-	-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 89 +++										1	1		
JO Jump on Overflow														
8-bit Displacement	70 +		-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 80 +++	$\bot$									1	1		
JP/JPE Jump on Parity/Parity Even														
8-bit Displacement	7A +		-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 8A +++										1	1		
JS Jump on Sign														
8-bit Displacement	78 +		-	-	-	-	-	-	-		1	1		r
Full Displacement	0F 88 +++	1									1	1		
LAHF Load AH with Flags	9F	]-	-	-	-	-	-	-	-	-	2	2		
LAR Load Access Rights														
From Register/Memory	0F 02 [mod reg r/m]	]-	-	-	-	-	х	-	-	-		9	а	g,h,j,p
LDS Load Pointer to DS	C5 [mod reg r/m]	-				-					4	9	b	h,i,j

Table 9-27. Processor Core Instruction Set Summary (Continued)

						Flag	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction	Opcode	O F	D F	I F	T F	S F	Z F	A F	P F	C F		Count iche Hit)	No	otes
LEA Load Effective Address	1										•			
No Index Register	8D [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1		
With Index Register											1	1		
LES Load Pointer to ES	C4 [mod reg r/m]	-	-	-	-	-	-	-	-	-	4	9	b	h,i,j
LFS Load Pointer to FS	0F B4 [mod reg r/m]	-	-	-	-	-	-	-	-	-	4	9	b	h,i,j
LGDT Load GDT Register	0F 01 [mod 010 r/m]	-	-	-	-	-	-	-	-	-	10	10	b,c	h,l
LGS Load Pointer to GS	0F B5 [mod reg r/m]	-	-	-	-	-	-	-	-	-	4	9	b	h,i,j
LIDT Load IDT Register	0F 01 [mod 011 r/m]	-	-	-	-	-	-	-	-	-	10	10	b,c	h,l
LLDT Load LDT Register														•
From Register/Memory	0F 00 [mod 010 r/m]	-	-	-	-	-	-	-	-	-		8	а	g,h,j,l
LMSW Load Machine Status Word														
From Register/Memory	0F 01 [mod 110 r/m]	-	-	-	-	-	-	-	-	-	11	11	b,c	h,l
LODS Load String	A [110 w]	-	-	-	-	-	-	-	-	-	3	3	b	h
LSL Load Segment Limit														
From Register/Memory	0F 03 [mod reg r/m]	[-	-	-	-	-	Х	-	-	-		9	а	g,h,j,p
LSS Load Pointer to SS	0F B2 [mod reg r/m]	-	-	-	-	-	-	-	-	-	4	10	а	h,i,j
LTR Load Task Register														
From Register/Memory	0F 00 [mod 011 r/m]	-	-	-	-	-		-	-	-		9	а	g,h,j,l
LEAVE Leave Current Stack Frame	C9	-	-	-	-	-	-	-	-	-	4	4	b	h
LOOP Offset Loop/No Loop	E2 +	-	-	-	-	-	-	-	-	-	2	2		r
LOOPNZ/LOOPNE Offset	E0 +	-	-	-	-	-	-	-	-	-	2	2		r
LOOPZ/LOOPE Offset	E1 +	-	-	-	-	-	-	-	-	-	2	2		r
MOV Move Data														
Register to Register	8 [10dw] [11 reg r/m]	-	-	-	-	-	-	-	-	-	1	1	b	h,i,j
Register to Memory	8 [100w] [mod reg r/m]										1	1		
Register/Memory to Register	8 [101w] [mod reg r/m]										1	1		
Immediate to Register/Memory	C [011w] [mod 000 r/m] ###										1	1		
Immediate to Register (short form)	B [w reg] ###										1	1		
Memory to Accumulator (short form)	A [000w] +++										1	1		
Accumulator to Memory (short form)	A [001w] +++										1	1		
Register/Memory to Segment Register	8E [mod sreg3 r/m]										1	6		
Segment Register to Register/Memory	8C [mod sreg3 r/m]										1	1		
MOV Move to/from Control/Debug/Test Regs														
Register to CR0/CR2/CR3/CR4	0F 22 [11 eee reg]	-	-	-	-	-	-	-	-	-	20/5/5	18/5/6		- 1
CR0/CR2/CR3/CR4 to Register	0F 20 [11 eee reg]										6	6		
Register to DR0-DR3	0F 23 [11 eee reg]										10	10		
DR0-DR3 to Register	0F 21 [11 eee reg]										9	9		
Register to DR6-DR7	0F 23 [11 eee reg]										10	10		
DR6-DR7 to Register	0F 21 [11 eee reg]										9	9		
Register to TR3-5	0F 26 [11 eee reg]										16	16		
TR3-5 to Register	0F 24 [11 eee reg]										8	8		
Register to TR6-TR7	0F 26 [11 eee reg]										11	11		
TR6-TR7 to Register	0F 24 [11 eee reg]										3	3		
MOVS Move String	A [010w]	-	-	-	-	-	-	-	-	-	6	6	b	h
MOVSX Move with Sign Extension	1										1		1	1
Register from Register/Memory	0F B[111w] [mod reg r/m]	-	-	-	-	-	-	-	-	-	1	1	b	h
MOVZX Move with Zero Extension													ı	
Register from Register/Memory	0F B[011w] [mod reg r/m]	-	-	-	_	-	-	-	-	-	1	1	b	h
MUL Unsigned Multiply		_									1			
Accumulator with Register/Memory Multiplier: Byte Word Doubleword	F [011w] [mod 100 r/m]	х	-	-	-	X	Х	u	u	X	4 5 15	4 5 15	b	h

Table 9-27. Processor Core Instruction Set Summary (Continued)

					ı	Flag	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction	Opcode	O F	D F	I F	T F	S F	Z F	A F	P F	C F		Count iche Hit)	No	otes
NEG Negate Integer	F [011w] [mod 011 r/m]	х	-	-	-	Х	Х	Х	Х	Х	1	1	b	h
NOP No Operation	90	-	-	-	-	-	-	-	-	-	1	1		
NOT Boolean Complement	F [011w] [mod 010 r/m]	-	-	-	-	-	-	-	-	-	1	1	b	h
OIO Official Invalid Opcode	0F FF	-	-	Х	0	-	-	-	-	-	1	8-125		
OR Boolean OR												•		
Register to Register	0 [10dw] [11 reg r/m]	0	-	-	-	Х	Х	u	Х	0	1	1	b	h
Register to Memory	0 [100w] [mod reg r/m]										1	1		
Memory to Register	0 [101w] [mod reg r/m]										1	1		
Immediate to Register/Memory	8 [00sw] [mod 001 r/m] ###										1	1		
Immediate to Accumulator	0 [110w] ###										1	1		
OUT Output to Port		-									Į.			
Fixed Port	E [011w] #	-	_	_	_	_	_	_	-	_	14	14/28		m
Variable Port	E [111w]										14	14/28		
OUTS Output String	6 [111w]	+-	_	_	_	_	_	_	_	_	15	15/29	b	h,m
POP Pop Value off Stack	10 [111111]											10/20		,
Register/Memory	8F [mod 000 r/m]	1_	_	_	_	_	_	_	_	_	1/4	1/4	b	h,i,j
Register (short form)	5 [1 reg]	=									1	1	b	11,1,1
Segment Register (ES, SS, DS)	[000 sreg2 111]										1	6		
Segment Register (ES, GS)	0F [10 sreg3 001]										1	6		
0 0 , ,													-	-
POPA Pop All General Registers	61	-			-						9	9	b	h
POPF Pop Stack into FLAGS	9D	Х	Χ	Х	Х	Х	Х	Х	Х	Х	8	8	b	h,n
PREFIX BYTES	T-a										I			
Assert Hardware LOCK Prefix	F0	_ -	-	-	-	-	-	-	-	-				m
Address Size Prefix	67													
Operand Size Prefix	66													
Segment Override Prefix -CS	2E													
-DS	3E													
-ES	26													
-FS -GS	64 65													
-SS	36													
PUSH Push Value onto Stack														
Register/Memory	FF [mod 110 r/m]	-	-	-	-	-	-	-	-	-	1/3	1/3	b	h
Register (short form)	5 [0 reg]										1	1		
Segment Register (ES, CS, SS, DS)	[000 sreg2 110]										1	1		
Segment Register (FS, GS)	0F [10 sreg3 000]										1	1		
Immediate	6 [10s0] ###										1	1		
PUSHA Push All General Registers	60	-	-	-	-	-	-	-	-	-	11	11	b	h
PUSHF Push FLAGS Register	9C		_								2	2	b	h
RCL Rotate Through Carry Left														
RCL Rotate Through Carry Left  Register/Memory by 1	D [000w] [mod 010 r/m]	х	_	_	-	_	_	_	_	х	3	3	b	h
Register/Memory by 1	D [000w] [mod 010 r/m] D [001w] [mod 010 r/m]	_	-							x x	3	3 8	b	h
Register/Memory by 1 Register/Memory by CL	D [001w] [mod 010 r/m]	u	-	-	-	-	-	-	-	х	8	8	b	h
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate		u		-	-	-	-	-	-				b	h
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #	u	-	-	-	-	-	-	-	X X	8	8		
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right Register/Memory by 1	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #  D [000w] [mod 011 r/m]	u u	-	-	-	-	-	-	-	x x	8 8	8 8	b	h
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right Register/Memory by 1 Register/Memory by CL	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #  D [000w] [mod 011 r/m] D [001w] [mod 011 r/m]	u u x u	-	-	-	- - -	- - -	-	- - -	x x x	8 8 4 8	8 8 4 8		
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #  D [000w] [mod 011 r/m] D [001w] [mod 011 r/m] C [000w] [mod 011 r/m] #	u u x u				- - - -	- - - -			x x x x x x	8 8	8 8		
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RDMSR Read Tmodel Specific Register	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #  D [000w] [mod 011 r/m] D [001w] [mod 011 r/m] C [000w] [mod 011 r/m] #  0F 32	u u x u u	- - - -	- - - -	- - - - -	- - - - -	- - - - -	- - - -	- - - - -	x x x x x	8 8 4 8	8 8 4 8		
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #  D [000w] [mod 011 r/m] D [001w] [mod 011 r/m] C [000w] [mod 011 r/m] #	u u x u u	- - - - -		- - - - -				- - - - -	x x x x x	8 8 4 8	8 8 8 8 17+4n\		
Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RCR Rotate Through Carry Right Register/Memory by 1 Register/Memory by CL Register/Memory by Immediate RDMSR Read Tmodel Specific Register RDTSC Read Time Stamp Counter	D [001w] [mod 010 r/m] C [000w] [mod 010 r/m] #  D [000w] [mod 011 r/m] D [001w] [mod 011 r/m] C [000w] [mod 011 r/m] #  0F 32 0F 31	u u x u u	- - - - -	- - - - -	- - - - -	- - - - -	- - - - -	- - - - -		x x x x - -	8 8 4 8 8	8 8 4 8 8	b	h

Table 9-27. Processor Core Instruction Set Summary (Continued)

	lessor core manacin							<u>-</u>	•		Real	Prot'd	Real	Prot'd
						Flag	_				Mode	Mode	Mode	Mode
Instruction	Opcode	O F	D F	I F	T F	S F	Z F	A F	P F	C F		Count ache Hit)	No	otes
REP OUTS Output String	F3 6[111w]	-	-	-	-	-	-	-	-	-	24+4n	24+4n\ 39+4n	b	h,m
REP STOS Store String	F3 A[101w]	-	-	-	-	-	-	-	-	-	9+2n	9+2n	b	h
REPE CMPS Compare String														
Find non-match	F3 A[011w]	Х	-	-	-	Х	Х	Х	Х	х	11+4n	11+4n	b	h
REPE SCAS Scan String														
Find non-AL/AX/EAX	F3 A[111w]	х	-	-	-	Х	Х	Х	Х	х	9+3n	9+3n	b	h
REPNE CMPS Compare String														
Find match	F2 A[011w]	Х	-	-	-	Х	Х	Х	Х	х	11+4n	11+4n	b	h
REPNE SCAS Scan String														
Find AL/AX/EAX	F2 A[111w]	Х	-	-	-	Χ	Χ	Χ	Х	Х	9+3n	9+3n	b	h
RET Return from Subroutine														
Within Segment	C3	_	-	-	-	-	-	-	-	-	3	3	b	g,h,j,k,r
Within Segment Adding Immediate to SP	C2 ##										3	3		
Intersegment	СВ										10	13		
Intersegment Adding Immediate to SP	CA ##										10	13		
Protected Mode: Different Privilege Level -Intersegment												35		
-Intersegment Adding Immediate to SP												35		
ROL Rotate Left														
Register/Memory by 1	D[000w] [mod 000 r/m]	х	-	-	-	-	-	-	-	Х	2	2	b	h
Register/Memory by CL	D[001w] [mod 000 r/m]	u	-	-	-	-	-	-	-	х	2	2		
Register/Memory by Immediate	C[000w] [mod 000 r/m] #	u	-	-	-	-	-	-	-	х	2	2		
ROR Rotate Right														
Register/Memory by 1	D[000w] [mod 001 r/m]	х	-	-	-	-	-	-	-	х	2	2	b	h
Register/Memory by CL	D[001w] [mod 001 r/m]	u	-	-	-	-	-	-	-	Х	2	2		
Register/Memory by Immediate	C[000w] [mod 001 r/m] #	u	-	-	-	-	-	-	-	Х	2	2		
RSDC Restore Segment Register and Descriptor	0F 79 [mod sreg3 r/m]	-	-	-	-	-	-	-	-	-	11	11	S	S
RSLDT Restore LDTR and Descriptor	0F 7B [mod 000 r/m]	-	-	-	-	-	-	-	-	-	11	11	s	S
RSTS Restore TSR and Descriptor	0F 7D [mod 000 r/m]	-	-	-	-	-	-	-	-	-	11	11	S	S
RSM Resume from SMM Mode	0F AA	Х	Χ	Χ	Χ	Χ	Χ	Χ	Χ	Х	57	57	S	S
SAHF Store AH in FLAGS	9E	-	-	-	-	Χ	Χ	Χ	Χ	Х	1	1		
SAL Shift Left Arithmetic														
Register/Memory by 1	D[000w] [mod 100 r/m]	х	-	-	-	Х	Х	u	Х	Х	1	1	b	h
Register/Memory by CL	D[001w] [mod 100 r/m]	u	-	-	-	Х	Х	u	Х	Х	2	2		
Register/Memory by Immediate	C[000w] [mod 100 r/m] #	u	-	-	-	Х	Х	u	Х	Х	1	1		
SAR Shift Right Arithmetic														
Register/Memory by 1	D[000w] [mod 111 r/m]	Х	-	-	-	Χ	Χ	u	Χ	Х	2	2	b	h
Register/Memory by CL	D[001w] [mod 111 r/m]	u	-	-	-	Х	Х	u	Х	Х	2	2		
Register/Memory by Immediate	C[000w] [mod 111 r/m] #	u	-	-	-	Χ	Χ	u	Χ	Х	2	2		
SBB Integer Subtract with Borrow														
Register to Register	1[10dw] [11 reg r/m]	Х	-	-	-	Х	Х	Х	Х	х	1	1	b	h
Register to Memory	1[100w] [mod reg r/m]										1	1		
Memory to Register	1[101w] [mod reg r/m]										1	1		
Immediate to Register/Memory	8[00sw] [mod 011 r/m] ###										1	1		
Immediate to Accumulator (short form)	1[110w] ###										1	1		
SCAS Scan String	A [111w]	Х	Ξ		-	Х	Х	Χ	Х	Х	2	2	b	h
SETB/SETNAE/SETC Set Byte on Below/Not About	ve or Equal/Carry													
To Register/Memory	0F 92 [mod 000 r/m]		_	_	-	_	_	-	_	-	1	1		h
SETBE/SETNA Set Byte on Below or Equal/Not Al	bove													
To Register/Memory	0F 96 [mod 000 r/m]		-	-	-	-	-	-	-	-	1	1		h
SETE/SETZ Set Byte on Equal/Zero									-					

Table 9-27. Processor Core Instruction Set Summary (Continued)

						Fla	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode
Instruction	Opcode	O F					Z F					Count iche Hit)	No	otes
SETL/SETNGE Set Byte on Less/Not Greater or E	qual													
To Register/Memory	0F 9C [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETLE/SETNG Set Byte on Less or Equal/Not Gre	eater													
To Register/Memory	0F 9E [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNB/SETAE/SETNC Set Byte on Not Below/Ab	ove or Equal/Not Carry													
To Register/Memory	0F 93 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNBE/SETA Set Byte on Not Below or Equal/A.	bove													
To Register/Memory	0F 97 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNE/SETNZ Set Byte on Not Equal/Not Zero														•
To Register/Memory	0F 95 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNL/SETGE Set Byte on Not Less/Greater or E	qual													•
To Register/Memory	0F 9D [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNLE/SETG Set Byte on Not Less or Equal/Gre	eater													•
To Register/Memory	0F 9F [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNO Set Byte on Not Overflow	•										•			
To Register/Memory	0F 91 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNP/SETPO Set Byte on Not Parity/Parity Odd	•										•			
To Register/Memory	0F 9B [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETNS Set Byte on Not Sign											1		ı	
To Register/Memory	0F 99 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETO Set Byte on Overflow		-									1		ı	
To Register/Memory	0F 90 [mod 000 r/m]	-	_	-	_	-	-	-	-	-	1	1		h
SETP/SETPE Set Byte on Parity/Parity Even											I	1	<u>l</u>	
To Register/Memory	0F 9A [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SETS Set Byte on Sign											1	1	ı	
To Register/Memory	0F 98 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	1	1		h
SGDT Store GDT Register												•	·	
To Register/Memory	0F 01 [mod 000 r/m]	-	-	-	-	-	-	-	-	-	6	6	b,c	h
SIDT Store IDT Register		-									1			
To Register/Memory	0F 01 [mod 001 r/m]	-	-	-	-	-	-	-	-	-	6	6	b,c	h
SLDT Store LDT Register											I	1		
To Register/Memory	0F 00 [mod 000 r/m]	-	-	-	-	-	-	-	-	-		1	а	h
STR Store Task Register	1										II.	ı		
To Register/Memory	0F 00 [mod 001 r/m]	-	-	-	-	-	-	-	-	-		3	а	h
SMSW Store Machine Status Word	0F 01 [mod 100 r/m]	-	-	-	-	-	-	-	-	-	4	4	b,c	h
STOS Store String	A [101w]	-	-	-	-	-	-	-	-	-	2	2	b	h
SHL Shift Left Logical	,										1		Į.	
Register/Memory by 1	D [000w] [mod 100 r/m]	х	-	-	-	х	Х	u	Х	х	1	1	b	h
Register/Memory by CL	D [001w] [mod 100 r/m]						х				2	2		
Register/Memory by Immediate	C [000w] [mod 100 r/m] #						х				1	1		
SHLD Shift Left Double	1 2000 42 00 000 00040					-	_	_			1		l .	
Register/Memory by Immediate	0F A4 [mod reg r/m] #	u	-	-	-	х	Х	u	Х	х	3	3	b	h
Register/Memory by CL	0F A5 [mod reg r/m]	ŦĨ.				•	•	-		-	6	6		
SHR Shift Right Logical	1 -13 1										1		l .	
Register/Memory by 1	D [000w] [mod 101 r/m]	х	_	-	-	Х	Х	u	Х	х	2	2	b	h
Register/Memory by CL	D [001w] [mod 101 r/m]	_					X				2	2		
Register/Memory by Immediate	C [000w] [mod 101 r/m] #						Х				2	2		
SHRD Shift Right Double	- faceultures to third a												<u> </u>	
Register/Memory by Immediate	0F AC [mod reg r/m] #	lii.	_	_	_	Y	х	11	У	Y	3	3	b	h
Register/Memory by CL	0F AD [mod reg r/m]	⊢"				^	^	u	^	^	6	6		"
. togiston mornory by OL	0F 38									-	84	84	s	S

Table 9-27. Processor Core Instruction Set Summary (Continued)

						Flaç	gs				Real Mode	Prot'd Mode	Real Mode	Prot'd Mode	
Instruction	Opcode				T F							Count iche Hit)	No	otes	
STC Set Carry Flag	F9	-	-	-	-	-	-	-	-	1	1	1			
STD Set Direction Flag	FD	-	1	-	-	-	-	-	-	-	4	4			
STI Set Interrupt Flag	FB	-	-	1	-	-	-	-	-	-	6	6		m	
SUB Integer Subtract	•										•				
Register to Register	2 [10dw] [11 reg r/m]	х	-	-	-	Х	Х	Х	Х	Х	1	1	b	h	
Register to Memory	2 [100w] [mod reg r/m]										1	1			
Memory to Register	2 [101w] [mod reg r/m]										1	1			
Immediate to Register/Memory	8 [00sw] [mod 101 r/m] ###										1	1			
Immediate to Accumulator (short form)	2 [110w] ###										1	1			
SVDC Save Segment Register and Descriptor	0F 78 [mod sreg3 r/m]	-	-	-	-	-	-	-	-	-	20	20	S	S	
SVLDT Save LDTR and Descriptor	0F 7A [mod 000 r/m]	-	-	-	-	-	-	-	-	-	20	20	s	S	
SVTS Save TSR and Descriptor	0F 7C [mod 000 r/m]	-	-	-	-	-	-	-	-	-	21	21	S	s	
TEST Test Bits											•	•			
Register/Memory and Register	8 [010w] [mod reg r/m]	0	-	-	-	х	х	u	х	0	1	1	b	h	
Immediate Data and Register/Memory	F [011w] [mod 000 r/m] ###										1	1			
Immediate Data and Accumulator	A [100w] ###										1	1			
VERR Verify Read Access															
To Register/Memory	0F 00 [mod 100 r/m]	-	-	-	-	-	х	-	-	-		8	а	g,h,j,p	
VERW Verify Write Access															
To Register/Memory	0F 00 [mod 101 r/m]	-	-	-	-	-	Х	-	-	-		8	а	g,h,j,p	
WAIT Wait Until FPU Not Busy	9B	-	-	-	-	-	-	-	-	-	1	1			
WBINVD Write-Back and Invalidate Cache	0F 09	-	-	-	-	-	-	-	-	-	23	23	t	t	
WRMSR Write to Model Specific Register	0F 30	-	-	-	-	-	-	-	-	-					
XADD Exchange and Add															
Register1, Register2	0F C[000w] [11 reg2 reg1]	х	-	-	-	Х	х	Х	Х	х	2	2			
Memory, Register	0F C[000w] [mod reg r/m]										2	2			
XCHG Exchange															
Register/Memory with Register	8[011w] [mod reg r/m]	-	-	-	-	-	-	-	-	-	2	2	b,f	f,h	
Register with Accumulator	9[0 reg]										2	2			
XLAT Translate Byte	D7	-	-	-	-	-	-	-	-	-	5	5		h	
XOR Boolean Exclusive OR															
Register to Register	3 [00dw] [11 reg r/m]	0	-	-	-	Х	Х	u	Х	0	1	1	b	h	
Register to Memory	3 [000w] [mod reg r/m]										1	1			
Memory to Register	3 [001w] [mod reg r/m]										1	1			
Immediate to Register/Memory	8 [00sw] [mod 110 r/m] ###											1	1		
Immediate to Accumulator (short form)	3 [010w] ###										1	1	1		

#### Instruction Notes for Instruction Set Summary

#### Notes a through c apply to Real Address Mode only:

- a. This is a Protected Mode instruction. Attempted execution in Real Mode will result in exception 6 (invalid opcode).
- b. Exception 13 fault (general protection) will occur in Real Mode if an operand reference is made that partially or fully extends beyond the maximum CS, DS, ES, FS, or GS segment limit (FFFFH). Exception 12 fault (stack segment limit violation or not present) will occur in Real Mode if an operand reference is made that partially or fully extends beyond the maximum SS limit.
- This instruction may be executed in Real Mode. In Real Mode, its purpose is primarily to initialize the CPU for Protected Mode.
- d.

# Notes e through g apply to Real Address Mode and Protected Virtual Address Mode:

- e. An exception may occur, depending on the value of the operand
- LOCK# is automatically asserted, regardless of the presence or absence of the LOCK prefix.
- g. LOCK# is asserted during descriptor table accesses.

### Notes h through r apply to Protected Virtual Address Mode only:

- h. Exception 13 fault will occur if the memory operand in CS, DS, ES, FS, or GS cannot be used due to either a segment limit violation or an access rights violation. If a stack limit is violated, an exception 12 occurs.
- For segment load operations, the CPL, RPL, and DPL must agree with the privilege rules to avoid an exception 13 fault. The segment's descriptor must indicate "present" or exception 11 (CS, DS, ES, FS, GS not present). If the SS register is loaded and a stack segment not present is detected, an exception 12 occurs.
- j. All segment descriptor accesses in the GDT or LDT made by this instruction will automatically assert LOCK# to maintain descriptor integrity in multiprocessor systems.

- JMP, CALL, INT, RET, and IRET instructions referring to another code segment will cause an exception 13, if an applicable privilege rule is violated.
- An exception 13 fault occurs if CPL is greater than 0 (0 is the most privileged level).
- m. An exception 13 fault occurs if CPL is greater than IOPL.
- n. The IF bit of the flag register is not updated if CPL is greater than IOPL. The IOPL and VM fields of the flag register are updated only if CPL = 0.
- The PE bit of the MSW (CR0) cannot be reset by this instruction. Use MOV into CRO if desiring to reset the PE bit.
- Any violation of privilege rules as apply to the selector operand does not cause a Protection exception, rather, the zero flag is cleared.
- q. If the coprocessor's memory operand violates a segment limit or segment access rights, an exception 13 fault will occur before the ESC instruction is executed. An exception 12 fault will occur if the stack limit is violated by the operand's starting address.
- The destination of a JMP, CALL, INT, RET, or IRET must be in the defined limit of a code segment or an exception 13 fault will occur.

# Note s applies to National Semiconductor-specific SMM instructions:

s. All memory accesses to SMM space are non-cacheable. An invalid opcode exception 6 occurs unless SMI is enabled and SMAR size > 0, and CPL = 0 and [SMAC is set or if in an SMI handler].

# Note t applies to cache invalidation instruction with the cache operating in write-back mode:

 The total clock count is the clock count shown plus the number of clocks required to write all "modified" cache lines to external memory.

### 9.4 FPU INSTRUCTION SET

The processor core is functionally divided into the FPU, and the integer unit. The FPU processes floating point instructions only and does so in parallel with the integer unit.

For example, when the integer unit detects a floating point instruction without memory operands, after two clock cycles the instruction passes to the FPU for execution. The integer unit continues to execute instructions while the FPU executes the floating point instruction. If another FPU instruction is encountered, the second FPU instruction is placed in the FPU queue. Up to four FPU instructions can be queued. In the event of an FPU exception, while other FPU instructions are queued, the state of the CPU is saved to ensure recovery.

The instruction set for the FPU is summarized in Table 9-29 on page 225. The table uses abbreviations that are described in Table 9-28.

Table 9-28. FPU Instruction Set Table Legend

Abbr.	Description
n	Stack register number
TOS	Top of stack register pointed to by SSS in the status register.
ST(1)	FPU register next to TOS
ST(n)	A specific FPU register, relative to TOS
M.WI	16-bit integer operand from memory
M.SI	32-bit integer operand from memory
M.LI	64-bit integer operand from memory
M.SR	32-bit real operand from memory
M.DR	64-bit real operand from memory
M.XR	80-bit real operand from memory
M.BCD	18-digit BCD integer operand from memory
CC	FPU condition code
Env Regs	Status, Mode Control and Tag Registers, Instruction Pointer and Operand Pointer

Table 9-29. FPU Instruction Set Summary

FPU Instruction	Opcode	Operation	Clock Count	Notes
F2XM1 Function Evaluation 2 <sup>x</sup> -1	D9 F0	TOS < 2 <sup>TOS</sup> -1	92 - 108	2
FABS Floating Absolute Value	D9 E1	TOS <   TOS	2	2
FADD Floating Point Add				
Top of Stack	DC [1100 0 n]	ST(n) < ST(n) + TOS	4 - 9	
80-bit Register	D8 [1100 0 n]	TOS < TOS + ST(n)	4 - 9	
64-bit Real	DC [mod 000 r/m]	TOS < TOS + M.DR	4 - 9	
32-bit Real	D8 [mod 000 r/m]	TOS < TOS + M.SR	4 - 9	
FADDP Floating Point Add, Pop	DE [1100 0 n]	ST(n) < ST(n) + TOS; then pop TOS		
FIADD Floating Point Integer Add			I	
32-bit integer	DA [mod 000 r/m]	TOS < TOS + M.SI	8 - 14	
16-bit integer	DE [mod 000 r/m]	TOS < TOS + M.WI	8 - 14	
FCHS Floating Change Sign	D9 E0	TOS < TOS	2	
FCLEX Clear Exceptions	(9B) DB E2	Wait then Clear Exceptions	5	
FNCLEX Clear Exceptions	DB E2	Clear Exceptions	3	
FCMOVB Floating Point Conditional Move if Below	DA [1100 0 n]	If (CF=1) ST(0) < ST(n)	4	
FCMOVE Floating Point Conditional Move if Equal	DA [1100 1 n]	If (ZF=1) ST(0) < ST(n)	4	
FCMOVBE Floating Point Conditional Move if Below or Equal	DA [1101 0 n]	If (CF=1 or ZF=1) ST(0) < ST(n)	4	
FCMOVU Floating Point Conditional Move if Unordered	DA [1101 1 n]	If (PF=1) ST(0) < ST(n)	4	
FCMOVNB Floating Point Conditional Move if Not Below	DB [1100 0 n]	If (CF=0) ST(0) < ST(n)	4	
FCMOVNE Floating Point Conditional Move if Not Equal	DB [1100 1 n]	If (ZF=0) ST(0) < ST(n)	4	
FCMOVNBE Floating Point Conditional Move if Not Below or Equal	DB [1101 0 n]	If (CF=0 and ZF=0) ST(0) < ST(n)	4	
FCMOVNU Floating Point Conditional Move if Not Unordered	DB [1101 1 n]	If (DF=0) ST(0) < ST(n)	4	
FCOM Floating Point Compare				
80-bit Register	D8 [1101 0 n]	CC set by TOS - ST(n)	4	
64-bit Real	DC [mod 010 r/m]	CC set by TOS - M.DR	4	
32-bit Real	D8 [mod 010 r/m]	CC set by TOS - M.SR	4	
FCOMP Floating Point Compare, Pop				
80-bit Register	D8 [1101 1 n]	CC set by TOS - ST(n); then pop TOS	4	
64-bit Real	DC [mod 011 r/m]	CC set by TOS - M.DR; then pop TOS	4	
32-bit Real	D8 [mod 011 r/m]	CC set by TOS - M.SR; then pop TOS	4	
FCOMPP Floating Point Compare, Pop Two Stack Elements	DE D9	CC set by TOS - ST(1); then pop TOS and ST(1)	4	
FCOMI Floating Point Compare Real and Set EFL	AGS			
80-bit Register	DB [1111 0 n]	EFLAG set by TOS - ST(n)	4	
FCOMIP Floating Point Compare Real and Set El	FLAGS, Pop			
80-bit Register	DF [1111 0 n]	EFLAG set by TOS - ST(n); then pop TOS	4	
FUCOMI Floating Point Unordered Compare Real	and Set EFLAGS			
80-bit Integer	DB [1110 1 n]	EFLAG set by TOS - ST(n)	9 - 10	
FUCOMIP Floating Point Unordered Compare Re	al and Set EFLAGS, Pop		•	
80-bit Integer	DF [1110 1 n]	EFLAG set by TOS - ST(n); then pop TOS	9 - 10	L
FICOM Floating Point Integer Compare				
32-bit integer	DA [mod 010 r/m]	CC set by TOS - M.WI	9 - 10	
16-bit integer	DE [mod 010 r/m]	CC set by TOS - M.SI	9 - 10	
FICOMP Floating Point Integer Compare, Pop		· · · · · ·	1	1
32-bit integer	DA [mod 011 r/m]	CC set by TOS - M.WI; then pop TOS	9 - 10	
16-bit integer	DE [mod 011 r/m	CC set by TOS - M.SI; then pop TOS	9 - 10	$\vdash$

Table 9-29. FPU Instruction Set Summary (Continued)

FPU Instruction	FPU Instruction Opcode Operation				
FCOS Function Evaluation: Cos(x)	D9 FF	TOS < COS(TOS)	92 - 141	1	
FDECSTP Decrement Stack pointer	D9 F6	Decrement top of stack pointer	4		
FDIV Floating Point Divide					
Top of Stack	DC [1111 1 n]	ST(n) < ST(n) / TOS	24 - 34		
80-bit Register	D8 [1111 0 n]	TOS < TOS / ST(n)	24 - 34		
64-bit Real	DC [mod 110 r/m]	TOS < TOS / M.DR	24 - 34		
32-bit Real	D8 [mod 110 r/m]	TOS < TOS / M.SR	24 - 34		
FDIVP Floating Point Divide, Pop	DE [1111 1 n]	ST(n) < ST(n) / TOS; then pop TOS	24 - 34		
FDIVR Floating Point Divide Reversed			•	1	
Top of Stack	DC [1111 0 n]	TOS < ST(n) / TOS	24 - 34		
80-bit Register	D8 [1111 1 n]	ST(n) < TOS / ST(n)	24 - 34		
64-bit Real	DC [mod 111 r/m]	TOS < M.DR / TOS	24 - 34		
32-bit Real	D8 [mod 111 r/m]	TOS < M.SR / TOS	24 - 34		
FDIVRP Floating Point Divide Reversed, Pop	DE [1111 0 n]	ST(n) < TOS / ST(n); then pop TOS	24 - 34		
FIDIV Floating Point Integer Divide	DE [TITT O II]	er(ii) = roe / er(ii), their pop roe	24 04	1	
	DA [mod 110 r/m]	TOS < TOS / M.SI	34 - 38		
32-bit Integer 16-bit Integer	DE [mod 110 r/m]	TOS < TOS / M.WI	34 - 38		
FIDIVR Floating Point Integer Divide Reversed	DE [IIIod 110 I/III]	103 < 103 / W.WI	34 - 30		
	DA [mod 444 r/m]	TOC - MCI/TOC	24 20	1	
32-bit Integer	DA [mod 111 r/m]	TOS < M.SI / TOS	34 - 38	-	
16-bit Integer	DE [mod 111 r/m]	TOS < M.WI / TOS	34 - 38	+	
FFREE Free Floating Point Register	DD [1100 0 n]	TAG(n) < Empty	4	1	
FINCSTP Increment Stack Pointer	D9 F7	Increment top-of-stack pointer	2		
FINIT Initialize FPU	(9B)DB E3	Wait, then initialize	8	-	
FNINIT Initialize FPU	DB E3	Initialize	6		
FLD Load Data to FPU Register	Taranina	T	1		
Top of Stack	D9 [1100 0 n]	Push ST(n) onto stack	2	1	
64-bit Real	DD [mod 000 r/m]	Push M.DR onto stack	2	1	
32-bit Real	D9 [mod 000 r/m]	Push M.SR onto stack	2		
FBLD Load Packed BCD Data to FPU Register	DF [mod 100 r/m]	Push M.BCD onto stack	41 - 45		
FILD Load Integer Data to FPU Register			1		
64-bit Integer	DF [mod 101 r/m]	Push M.LI onto stack	4 - 8		
32-bit Integer	DB [mod 000 r/m]	Push M.SI onto stack	4 - 6		
16-bit Integer	DF [mod 000 r/m]	Push M.WI onto stack	3 - 6		
FLD1 Load Floating Const.= 1.0	D9 E8	Push 1.0 onto stack	4		
FLDCW Load FPU Mode Control Register	D9 [mod 101 r/m]	Ctl Word < Memory	4		
FLDENV Load FPU Environment	D9 [mod 100 r/m]	Env Regs < Memory	30		
<b>FLDL2E</b> Load Floating Const.= Log <sub>2</sub> (e)	D9 EA	Push Log <sub>2</sub> (e) onto stack	4		
<b>FLDL2T</b> Load Floating Const.= Log <sub>2</sub> (10)	D9 E9	Push Log <sub>2</sub> (10) onto stack	4		
FLDLG2 Load Floating Const.= Log <sub>10</sub> (2)	D9 EC	Push Log <sub>10</sub> (2) onto stack	4		
FLDLN2 Load Floating Const.= Ln(2)	D9 ED	Push Log <sub>e</sub> (2) onto stack	4		
FLDPI Load Floating Const.= π	D9 EB	Push $\pi$ onto stack	4		
FLDZ Load Floating Const.= 0.0	D9 EE	Push 0.0 onto stack	4		
FMUL Floating Point Multiply					
Top of Stack	DC [1100 1 n]	ST(n) < ST(n) × TOS	4 - 9		
80-bit Register	D8 [1100 1 n]	TOS < TOS × ST(n)	4 - 9		
64-bit Real	DC [mod 001 r/m]	TOS < TOS × M.DR	4 - 8		
32-bit Real	D8 [mod 001 r/m]	TOS < TOS × M.SR	4 - 6		
FMULP Floating Point Multiply & Pop	DE [1100 1 n]	ST(n) < ST(n) × TOS; then pop TOS	4 - 9		
FIMUL Floating Point Integer Multiply			1	•	
32-bit Integer	DA [mod 001 r/m]	TOS < TOS × M.SI	9 - 11		
31090.	DE [mod 001 r/m]	120 1 10071111101	J ''	1	

Table 9-29. FPU Instruction Set Summary (Continued)

FPU Instruction	Opcode	Operation	Clock Count	Notes
FNOP No Operation	D9 D0	No Operation	2	
FPATAN Function Eval: Tan <sup>-1</sup> (y/x)	D9 F3	ST(1) < ATAN[ST(1) / TOS]; then pop TOS	97 - 161	3
FPREM Floating Point Remainder	D9 F8	TOS < Rem[TOS / ST(1)]	82 - 91	
FPREM1 Floating Point Remainder IEEE	D9 F5	TOS < Rem[TOS / ST(1)]	82 - 91	
FPTAN Function Eval: Tan(x)	D9 F2	TOS < TAN(TOS); then push 1.0 onto stack	117 - 129	1
FRNDINT Round to Integer	D9 FC	TOS < Round(TOS)	10 - 20	
FRSTOR Load FPU Environment and Register	DD [mod 100 r/m]	Restore state	56 - 72	
FSAVE Save FPU Environment and Register	(9B)DD [mod 110 r/m]	Wait, then save state	57 - 67	
FNSAVE Save FPU Environment and Register	DD [mod 110 r/m]	Save state	55 - 65	
FSCALE Floating Multiply by 2 <sup>n</sup>	D9 FD	TOS < TOS × 2 <sup>(ST(1))</sup>	7 - 14	
FSIN Function Evaluation: Sin(x)	D9 FE	TOS < SIN(TOS)	76 - 140	1
FSINCOS Function Eval.: Sin(x)& Cos(x)	D9 FB	temp < TOS; TOS < SIN(temp); then push COS(temp) onto stack	145 - 161	1
FSQRT Floating Point Square Root	D9 FA	TOS < Square Root of TOS	59 - 60	
FST Store FPU Register				
Top of Stack	DD [1101 0 n]	ST(n) < TOS	2	
64-bit Real	DD [mod 010 r/m]	M.DR < TOS	2	
32-bit Real	D9 [mod 010 r/m]	M.SR < TOS	2	
FSTP Store FPU Register, Pop			•	•
Top of Stack	DB [1101 1 n]	ST(n) < TOS; then pop TOS	2	
80-bit Real	DB [mod 111 r/m]	M.XR < TOS; then pop TOS	2	
64-bit Real	DD [mod 011 r/m]	M.DR < TOS; then pop TOS	2	
32-bit Real	D9 [mod 011 r/m]	M.SR < TOS; then pop TOS	2	
FBSTP Store BCD Data, Pop	DF [mod 110 r/m]	M.BCD < TOS; then pop TOS	57 - 63	
FIST Store Integer FPU Register			1	l
32-bit Integer	DB [mod 010 r/m]	M.SI < TOS	8 - 13	
16-bit Integer	DF [mod 010 r/m]	M.WI < TOS	7 - 10	
FISTP Store Integer FPU Register, Pop			<u>'</u>	
64-bit Integer	DF [mod 111 r/m]	M.LI < TOS; then pop TOS	10 - 13	
32-bit Integer	DB [mod 011 r/m]	M.SI < TOS; then pop TOS	8 - 13	
16-bit Integer	DF [mod 011 r/m]	M.WI < TOS; then pop TOS	7 - 10	
FSTCW Store FPU Mode Control Register	(9B)D9 [mod 111 r/m]	Wait Memory < Control Mode Register	5	
FNSTCW Store FPU Mode Control Register	D9 [mod 111 r/m]	Memory < Control Mode Register	3	
FSTENV Store FPU Environment	(9B)D9 [mod 110 r/m]	Wait Memory < Env. Registers	14 - 24	
FNSTENV Store FPU Environment	D9 [mod 110 r/m]	Memory < Env. Registers	12 - 22	
FSTSW Store FPU Status Register	(9B)DD [mod 111 r/m]	Wait Memory < Status Register	6	
FNSTSW Store FPU Status Register	DD [mod 111 r/m]	Memory < Status Register	4	
FSTSW AX Store FPU Status Register to AX	(9B)DF E0	Wait AX < Status Register	4	
FNSTSW AX Store FPU Status Register to AX	DF E0	AX < Status Register	2	
FSUB Floating Point Subtract			<u>'</u>	
Top of Stack	DC [1110 1 n]	ST(n) < ST(n) - TOS	4 - 9	
80-bit Register	D8 [1110 0 n]	TOS < TOS - ST(n	4 - 9	
64-bit Real	DC [mod 100 r/m]	TOS < TOS - M.DR	4 - 9	
32-bit Real	D8 [mod 100 r/m]	TOS < TOS - M.SR	4 - 9	
FSUBP Floating Point Subtract, Pop	DE [1110 1 n]	ST(n) < ST(n) - TOS; then pop TOS	4 - 9	
FSUBR Floating Point Subtract Reverse				•
Top of Stack	DC [1110 0 n]	TOS < ST(n) - TOS	4 - 9	
80-bit Register	D8 [1110 1 n]	ST(n) < TOS - ST(n)	4 - 9	
64-bit Real	DC [mod 101 r/m]	TOS < M.DR - TOS	4 - 9	
32-bit Real	D8 [mod 101 r/m]	TOS < M.SR - TOS	4 - 9	
FSUBRP Floating Point Subtract Reverse, Pop	DE [1110 0 n]	ST(n) < TOS - ST(n); then pop TOS	4 - 9	

Table 9-29. FPU Instruction Set Summary (Continued)

FPU Instruction	Clock Count	Notes		
FISUB Floating Point Integer Subtract				
32-bit Integer	DA [mod 100 r/m]	TOS < TOS - M.SI	14 - 29	
16-bit Integer	DE [mod 100 r/m]	TOS < TOS - M.WI	14 - 27	
FISUBR Floating Point Integer Subtract Revers	se			
32-bit Integer Reversed	DA [mod 101 r/m]	TOS < M.SI - TOS	14 - 29	
16-bit Integer Reversed	DE [mod 101 r/m]	TOS < M.WI - TOS	14 - 27	
FTST Test Top of Stack	D9 E4	CC set by TOS - 0.0	4	
FUCOM Unordered Compare	DD [1110 0 n]	CC set by TOS - ST(n)	4	
FUCOMP Unordered Compare, Pop	DD [1110 1 n]	CC set by TOS - ST(n); then pop TOS	4	
FUCOMPP Unordered Compare, Pop two elements	DA E9	CC set by TOS - ST(I); then pop TOS and ST(1)	4	
FWAIT Wait	9B	Wait for FPU not busy	2	
FXAM Report Class of Operand	D9 E5	CC < Class of TOS	4	
FXCH Exchange Register with TOS	D9 [1100 1 n]	TOS <> ST(n) Exchange	3	
FXTRACT Extract Exponent	D9 F4	temp < TOS; TOS < exponent (temp); then push significant (temp) onto stack	11 - 16	
FLY2X Function Eval. y × Log2(x)	D9 F1	ST(1) < ST(1) × Log <sub>2</sub> (TOS); then pop TOS	145 - 154	
FLY2XP1 Function Eval. y × Log2(x+1)	D9 F9	$ST(1) \leftarrow ST(1) \times Log_2(1+TOS)$ ; then pop TOS	131 - 133	4

#### **FPU Instruction Summary Notes**

All references to TOS and ST(n) refer to stack layout prior to execution.

Values popped off the stack are discarded.

A pop from the stack increments the top of stack pointer.

A push to the stack decrements the top of stack pointer.

#### Notes:

 For FCOS, FSIN, FSINCOS and FPTAN, time shown is for absolute value of TOS < 3p/4. Add 90 clock counts for argument reduction if outside this range.</li>

For FCOS, clock count is 141 if TOS <  $\pi/4$  and clock count is 92 if  $\pi/4$  < TOS >  $\pi/2$ .

For FSIN, clock count is 81 to 82 if absolute value of TOS <  $\pi/4$ .

- 2. For F2XM1, clock count is 92 if absolute value of TOS < 0.5.
- 3. For FPATAN, clock count is 97 if ST(1)/TOS <  $\pi$ /32.
- 4. For FYL2XP1, clock count is 170 if TOS is out of range and regular FYL2X is called.
- The following opcodes are reserved: D9D7, D9E2, D9E7, DDFC, DED8, DEDA, DEDC, DEDD, DEDE, DFFC.

If a reserved opcode is executed, and unpredictable results may occur (exceptions are not generated).

### 9.5 MMX INSTRUCTION SET

The CPU is functionally divided into the FPU unit, and the integer unit. The FPU has been extended to process both MMX instructions and floating point instructions in parallel with the integer unit. Revision 3.1

For example, when the integer unit detects a MMX instruction, the instruction passes to the FPU unit for execution. The integer unit continues to execute instructions while the FPU unit executes the MMX instruction. If another MMX instruction is encountered, the second MMX instruction is placed in the MMX queue. Up to four MMX instructions can be queued.

The MMX instruction set is summarized in Table 9-31 on page 230. The abbreviations used in the table are listed in Table 9-30.

Table 9-30. MMX Instruction Set Table Legend

Abbreviation	Description
<	Result written
[11 mm reg]	Binary or binary groups of digits
mm	One of eight 64-bit MMX registers
reg	A general purpose register
<sat< td=""><td>If required, the resultant data is saturated to remain in the associated data range</td></sat<>	If required, the resultant data is saturated to remain in the associated data range
<move< td=""><td>Source data is moved to result location</td></move<>	Source data is moved to result location
[byte]	Eight 8-bit bytes are processed in parallel
[word]	Four 16-bit word are processed in parallel
[dword]	Two 32-bit double words are processed in parallel
[qword]	One 64-bit quad word is processed
[sign xxx]	The byte, word, double word or quad word most significant bit is a sign bit
mm1, mm2	MMX Register 1, MMX Register 2
mod r/m	Mod and r/m byte encoding (page 6-6 of this manual)
pack	Source data is truncated or saturated to next smaller data size, then concatenated.
packdw	Pack two double words from source and two double words from destination into four words in destination register.
packwb	Pack four words from source and four words from destination into eight bytes in destination register.

Table 9-31. MMX Instruction Set Summary

MMX Instructions	Opcode	Operation and Clock Count (Latency/Throughput)	
EMMS Empty MMX State	0F77	Tag Word < FFFFh (empties the floating point tag word)	1/1
MOVD Move Doubleword	•		
Register to MMX Register	0F6E [11 mm reg]	MMX reg [qword] <move, [dword]<="" extend="" reg="" td="" zero=""><td>1/1</td></move,>	1/1
MMX Register to Register	0F7E [11 mm reg]	reg [qword] <move [low="" dword]<="" mmx="" reg="" td=""><td>5/1</td></move>	5/1
Memory to MMX Register	0F6E [mod mm r/m]	MMX regr[qword] <move, extend="" memory[dword]<="" td="" zero=""><td>1/1</td></move,>	1/1
MMX Register to Memory	0F7E [mod mm r/m]	Memory [dword] <move [low="" dword]<="" mmx="" reg="" td=""><td>1/1</td></move>	1/1
MOVQ Move Quardword			
MMX Register 2 to MMX Register 1	0F6F [11 mm1 mm2]	MMX reg 1 [qword] <move 2="" [qword]<="" mmx="" reg="" td=""><td>1/1</td></move>	1/1
MMX Register 1 to MMX Register 2	0F7F [11 mm1 mm2]	MMX reg 2 [qword] <move 1="" [qword]<="" mmx="" reg="" td=""><td>1/1</td></move>	1/1
Memory to MMX Register	0F6F [mod mm r/m]	MMX reg [qword] <move memory[qword]<="" td=""><td>1/1</td></move>	1/1
MMX Register to Memory	0F7F [mod mm r/m]	Memory [qword] <move [qword]<="" mmx="" reg="" td=""><td>1/1</td></move>	1/1
PACKSSDW Pack Dword with Signed Sa		2 271 2 3	
MMX Register 2 to MMX Register 1	0F6B [11 mm1 mm2]	MMX reg 1 [qword] <packdw, 1<="" 2,="" mmx="" reg="" sat="" signed="" td=""><td>1/1</td></packdw,>	1/1
Memory to MMX Register	0F6B [mod mm r/m]	MMX reg [qword] <packdw, memory,="" mmx="" reg<="" sat="" signed="" td=""><td>1/1</td></packdw,>	1/1
PACKSSWB Pack Word with Signed Satu		311 - 3 1 7 - 3 77, 3	
MMX Register 2 to MMX Register 1	0F63 [11 mm1 mm2]	MMX reg 1 [qword] <packwb, 1<="" 2,="" mmx="" reg="" sat="" signed="" td=""><td>1/1</td></packwb,>	1/1
Memory to MMX Register	0F63 [mod mm r/m]	MMX reg [qword] <packwb, memory,="" mmx="" reg<="" sat="" signed="" td=""><td>1/1</td></packwb,>	1/1
PACKUSWB Pack Word with Unsigned S		-3113 1	
MMX Register 2 to MMX Register 1	0F67 [11 mm1 mm2]	MMX reg 1 [gword] <packwb, 1<="" 2,="" mmx="" reg="" sat="" td="" unsigned=""><td>1/1</td></packwb,>	1/1
Memory to MMX Register	0F67 [mod mm r/m]	MMX reg [qword] <packwb, memory,="" mmx="" reg<="" sat="" td="" unsigned=""><td>1/1</td></packwb,>	1/1
PADDB Packed Add Byte with Wrap-Arou		immix rog (quora) < pasimo, anoignou out montory, minix rog	
MMX Register 2 to MMX Register 1	0FFC [11 mm1 mm2]	MMX reg 1 [byte] < MMX reg 1 [byte] + MMX reg 2 [byte]	1/1
Memory to MMX Register	0FFC [mod mm r/m]	MMX reg[byte] < memory [byte] + MMX reg [byte]	1/1
PADDD Packed Add Dword with Wrap-Ar		Immix regiption to memory [system immix reg [system]	
MMX Register 2 to MMX Register 1	0FFE [11 mm1 mm2]	MMX reg 1 [sign dword] < MMX reg 1 [sign dword] + MMX reg 2 [sign dword]	1/1
Memory to MMX Register	0FFE [mod mm r/m]	MMX reg [sign dword] < memory [sign dword] + MMX reg [sign dword]	1/1
PADDSB Packed Add Signed Byte with S		immix rog (sign andra) to momory (sign andra) timmix rog (sign andra)	
MMX Register 2 to MMX Register 1	0FEC [11 mm1 mm2]	MMX reg 1 [sign byte] <sat +="" 1="" 2="" [sign="" byte]="" byte]<="" mmx="" reg="" td=""><td>1/1</td></sat>	1/1
Memory to Register	0FEC [mod mm r/m]	MMX reg [sign byte] <sat +="" [sign="" byte]="" byte]<="" memory="" mmx="" reg="" td=""><td>1/1</td></sat>	1/1
PADDSW Packed Add Signed Word with		INNIVATOR (Sign byte) C Sate memory (Sign byte) F MinivA Tog (Sign byte)	- 1/ 1
MMX Register 2 to MMX Register 1	0FED [11 mm1 mm2]	MMX reg 1 [sign word] <sat +="" 1="" 2="" [sign="" mmx="" reg="" td="" word]="" word]<=""><td>1/1</td></sat>	1/1
Memory to Register	0FED [mod mm r/m]	MMX reg [sign word] <sat +="" [sign="" memory="" mmx="" reg="" td="" word]="" word]<=""><td>1/1</td></sat>	1/1
PADDUSB Add Unsigned Byte with Satur		www.reg [sign word] \ sat memory [sign word] \ www.reg [sign word]	- 17 1
MMX Register 2 to MMX Register 1	0FDC [11 mm1 mm2]	MMX reg 1 [byte] <sat +="" 1="" 2="" [byte]="" [byte]<="" mmx="" reg="" td=""><td>1/1</td></sat>	1/1
	0FDC [mod mm r/m]	MMX reg [byte] <sat +="" <sat="" [byte]="" [byte]<="" memory="" mmx="" reg="" td=""><td>1/1</td></sat>	1/1
Memory to Register		INNIN TEG [Dyte] <sat +="" [dyte]="" [dyte]<="" innin="" td="" teg="" triefficity=""><td>1/ 1</td></sat>	1/ 1
PADDUSW Add Unsigned Word with Sate MMX Register 2 to MMX Register 1	0FDD [11 mm1 mm2]	MMX reg 1 [word] <sat +="" 1="" 2="" [word]="" [word]<="" mmx="" reg="" td=""><td>1/1</td></sat>	1/1
	0FDD [mod mm r/m]		
Memory to Register		MMX reg [word] <sat +="" [word]="" [word]<="" memory="" mmx="" reg="" td=""><td>1/1</td></sat>	1/1
PADDW Packed Add Word with Wrap-Arc		MMV rag 1 [word] 4 MMV rag 1 [word] 1 MMV rag 2 [word]	1/1
MMX Register 2 to MMX Register 1	0FFD [11 mm1 mm2]	MMX reg 1 [word] < MMX reg 1 [word] + MMX reg 2 [word]	1/1
Memory to MMX Register	0FFD [mod mm r/m]	MMX reg [word] < memory [word] + MMX reg [word]	1/1
PAND Bitwise Logical AND	0EDD [4440]	MANY and formed to be a AND MANY and formed MANY and Officered	4/4
MMX Register 2 to MMX Register 1	0FDB [11 mm1 mm2]	MMX reg 1 [qword] <logic 1="" 2="" [qword],="" [qword]<="" and="" mmx="" reg="" td=""><td>1/1</td></logic>	1/1
Memory to MMX Register	0FDB [mod mm r/m]	MMX reg [qword] <logic [qword],="" [qword]<="" and="" memory="" mmx="" reg="" td=""><td></td></logic>	
PANDN Bitwise Logical AND NOT	OEDE (44 *4 01	MMV and 4 forward a logic AND NOTABLEV 4 forward ABAN - Of D	414
MMX Register 2 to MMX Register 1	0FDF [11 mm1 mm2]	MMX reg 1 [qword] <logic 1="" 2="" [qword],="" [qword]<="" and="" mmx="" not="" reg="" td=""><td>1/1</td></logic>	1/1
Memory to MMX Register	0FDF [mod mm r/m]	MMX reg [qword] <logic [qword],="" [qword]<="" and="" memory="" mmx="" not="" reg="" td=""><td>1/1</td></logic>	1/1
PCMPEQB Packed Byte Compare for Equ	1	Inny 15 1 - 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1/1
MMX Register 2 with MMX Register 1	0F74 [11 mm1 mm2]	MMX reg 1 [byte] <ffh 1="" 2="" [byte]="" [byte]<="" [byte]<00h="" if="" mmx="" not="MMX" reg="" td=""><td>1/1</td></ffh>	1/1

Table 9-31. MMX Instruction Set Summary (Continued)

MMX Instructions	Opcode	Operation and Clock Count (Latency/Throughput)	
PCMPEQD Packed Dword Compare for E	quality		
MMX Register 2 with MMX Register 1	0F76 [11 mm1 mm2]	MMX reg 1 [dword] <ffff 1="" 2<="" [dword]="MMX" ffffh="" if="" mmx="" reg="" td=""><td>1/1</td></ffff>	1/1
		[dword] MMX reg 1 [dword]<0000 0000hif MMX reg 1[dword] NOT = MMX reg 2 [dword]	
Memory with MMX Register	0F76 [mod mm r/m]	MMX reg [dword] <ffff 0000h="" <0000="" [dword]="" [dword]<="" ffffh="" if="" memory[dword]="" mmx="" not="MMX" reg="" td=""><td>1/1</td></ffff>	1/1
PCMPEQW Packed Word Compare for E	quality		
MMX Register 2 with MMX Register 1	0F75 [11 mm1 mm2]	MMX reg 1 [word] <ffffh 1="" 2="" [word]="" [word]<="" [word]<0000h="" if="" mmx="" not="MMX" reg="" td=""><td>1/1</td></ffffh>	1/1
Memory with MMX Register	0F75 [mod mm r/m]	MMX reg [word] <ffffh <0000h="" [word]="" [word]<="" if="" memory[word]="" mmx="" not="MMX" reg="" td=""><td>1/1</td></ffffh>	1/1
PCMPGTB Pack Compare Greater Than	Byte		
MMX Register 2 to MMX Register 1	0F64 [11 mm1 mm2]	MMX reg 1 [byte] <ffh 1="" [byte]="" if="" mmx="" reg=""> MMX reg 2 [byte] MMX reg 1 [byte]&lt;00h if MMX reg 1 [byte] NOT &gt; MMX reg 2 [byte]</ffh>	1/1
Memory with MMX Register	0F64 [mod mm r/m]	MMX reg [byte] <ffh if="" memory[byte]=""> MMX reg [byte] MMX reg [byte] &lt;00h if memory[byte] NOT &gt; MMX reg [byte]</ffh>	1/1
PCMPGTD Pack Compare Greater Than	Dword		
MMX Register 2 to MMX Register 1	0F66 [11 mm1 mm2]	MMX reg 1 [dword] <ffff 1="" [dword]="" ffffh="" if="" mmx="" reg=""> MMX reg 2 [dword] MMX reg 1 [dword]&lt;0000 0000hif MMX reg 1 [dword]NOT &gt; MMX reg 2 [dword]</ffff>	1/1
Memory with MMX Register	0F66 [mod mm r/m]	MMX reg [dword] <ffff ffffh="" if="" memory[dword]=""> MMX reg [dword] MMX reg [dword] &lt;0000 0000h if memory[dword] NOT &gt; MMX reg [dword]</ffff>	1/1
PCMPGTW Pack Compare Greater Than	Word		
MMX Register 2 to MMX Register 1	0F65 [11 mm1 mm2]	MMX reg 1 [word] <fffh 1="" [word]="" if="" mmx="" reg=""> MMX reg 2 [word] MMX reg 1 [word]&lt;0000h if MMX reg 1 [word] NOT &gt; MMX reg 2 [word]</fffh>	1/1
Memory with MMX Register	0F65 [mod mm r/m]	MMX reg [word] <ffffh if="" memory[word]=""> MMX reg [word] MMX reg [word] &lt;0000h if memory[word] NOT &gt; MMX reg [word]</ffffh>	1/1
PMADDWD Packed Multiply and Add			
MMX Register 2 to MMX Register 1	0FF5 [11 mm1 mm2]	MMX reg 1 [dword] <add 1="" 2[sign="" <="" [dword]="" [sign="" mmx="" reg="" td="" word]*mmx="" word]<=""><td>2/1</td></add>	2/1
Memory to MMX Register	0FF5 [mod mm r/m]	MMX reg 1 [dword] <add *="" <="" [dword]="" [sign="" memory="" td="" word]="" word]<=""><td>2/1</td></add>	2/1
PMULHW Packed Multiply High			
MMX Register 2 to MMX Register 1	0FE5 [11 mm1 mm2]	MMX reg 1 [word] <upper *="" 1="" 2="" [sign="" bits="" mmx="" reg="" td="" word]="" word]<=""><td>2/1</td></upper>	2/1
Memory to MMX Register	0FE5 [mod mm r/m]	MMX reg 1 [word] <upper *="" [sign="" bits="" memory="" td="" word]="" word]<=""><td>2/1</td></upper>	2/1
PMULLW Packed Multiply Low			
MMX Register 2 to MMX Register 1	0FD5 [11 mm1 mm2]	MMX reg 1 [word] <lower *="" 1="" 2="" [sign="" bits="" mmx="" reg="" td="" word]="" word]<=""><td>2/1</td></lower>	2/1
Memory to MMX Register	0FD5 [mod mm r/m]	MMX reg 1 [word] <lower *="" [sign="" bits="" memory="" td="" word]="" word]<=""><td>2/1</td></lower>	2/1
POR Bitwise OR			
MMX Register 2 to MMX Register 1	0FEB [11 mm1 mm2]	MMX reg 1 [qword] <logic 1="" 2="" [qword],="" [qword]<="" mmx="" or="" reg="" td=""><td>1/1</td></logic>	1/1
Memory to MMX Register	0FEB [mod mm r/m]	MMX reg [qword] <logic [qword],="" memory[qword]<="" mmx="" or="" reg="" td=""><td>1/1</td></logic>	1/1
PSLLD Packed Shift Left Logical Dword			
MMX Register 1 by MMX Register 2	0FF2 [11 mm1 mm2]	MMX reg 1 [dword] <shift 2="" [dword]<="" by="" in="" left,="" mmx="" reg="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Memory	0FF2 [mod mm r/m]	MMX reg [dword] <shift by="" in="" left,="" memory[dword]<="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Immediate	0F72 [11 110 mm] #	MMX reg [dword] <shift [im="" by="" byte]<="" in="" left,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
PSLLQ Packed Shift Left Logical Qword			
MMX Register 1 by MMX Register 2	0FF3 [11 mm1 mm2]	MMX reg 1 [qword] <shift 2="" [qword]<="" by="" in="" left,="" mmx="" reg="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Memory	0FF3 [mod mm r/m]	MMX reg [qword] <shift [qword]<="" by="" in="" left,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Immediate	0F73 [11 110 mm] #	MMX reg [qword] <shift [im="" by="" byte]<="" in="" left,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
PSLLW Packed Shift Left Logical Word			
MMX Register 1 by MMX Register 2	0FF1 [11 mm1 mm2]	MMX reg 1 [word] <shift 2="" [word]<="" by="" in="" left,="" mmx="" reg="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Memory	0FF1 [mod mm r/m]	MMX reg [word] <shift by="" in="" left,="" memory[word]<="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
- • •		<u> </u>	1/1

Table 9-31. MMX Instruction Set Summary (Continued)

MMX Instructions	Opcode	Operation and Clock Count (Latency/Throughput)	
PSRAD Packed Shift Right Arithmetic Dw			
MMX Register 1 by MMX Register 2	0FE2 [11 mm1 mm2]	MMX reg 1 [dword] <arith 2="" [dword]<="" by="" in="" mmx="" reg="" right,="" shift="" shifting="" td="" zeroes=""><td>1/1</td></arith>	1/1
MMX Register by Memory	0FE2 [mod mm r/m]	MMX reg [dword] <arith by="" in="" memory[dword]<="" right,="" shift="" shifting="" td="" zeroes=""><td>1/1</td></arith>	1/1
MMX Register by Immediate	0F72 [11 100 mm] #	MMX reg [dword] <arith [im="" by="" byte]<="" in="" right,="" shift="" shifting="" td="" zeroes=""><td>1/1</td></arith>	1/1
PSRAW Packed Shift Right Arithmetic Wo	, ,	immy rog [amora] - amaromic right, orinting in 201000 by [im byto]	., .
MMX Register 1 by MMX Register 2	0FE1 [11 mm1 mm2]	MMX reg 1 [word] <arith 2="" [word]<="" by="" in="" mmx="" reg="" right,="" shift="" shifting="" td="" zeroes=""><td>1/1</td></arith>	1/1
MMX Register by Memory	0FE1 [mod mm r/m]	MMX reg [word] <arith by="" in="" memory[word]<="" right,="" shift="" shifting="" td="" zeroes=""><td>1/1</td></arith>	1/1
MMX Register by Immediate	0F71 [11 100 mm] #	MMX reg [word] <arith [im="" by="" byte]<="" in="" right,="" shift="" shifting="" td="" zeroes=""><td>1/1</td></arith>	1/1
PSRLD Packed Shift Right Logical Dword			
MMX Register 1 by MMX Register 2	0FD2 [11 mm1 mm2]	MMX reg 1 [dword] <shift 2="" [dword]<="" by="" in="" mmx="" reg="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Memory	0FD2 [mod mm r/m]	MMX reg [dword] <shift by="" in="" memory[dword]<="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Immediate	0F72 [11 010 mm] #	MMX reg [dword] <shift [im="" by="" byte]<="" in="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
PSRLQ Packed Shift Right Logical Qword			
MMX Register 1 by MMX Register 2	0FD3 [11 mm1 mm2]	MMX reg 1 [qword] <shift 2="" [qword]<="" by="" in="" mmx="" reg="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Memory	0FD3 [mod mm r/m]	MMX reg [qword] <shift by="" in="" memory[qword]<="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Immediate	0F73 [11 010 mm] #	MMX reg [qword] <shift [im="" by="" byte]<="" in="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
PSRLW Packed Shift Right Logical Word			
MMX Register 1 by MMX Register 2	0FD1 [11 mm1 mm2]	MMX reg 1 [word] <shift 2="" [word]<="" by="" in="" mmx="" reg="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Memory	0FD1 [mod mm r/m]	MMX reg [word] <shift by="" in="" memory[word]<="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
MMX Register by Immediate	0F71 [11 010 mm] #	MMX reg [word] <shift by="" imm[word]<="" in="" right,="" shifting="" td="" zeroes=""><td>1/1</td></shift>	1/1
PSUBB Subtract Byte With Wrap-Around			
MMX Register 2 to MMX Register 1	0FF8 [11 mm1 mm2]	MMX reg 1 [byte] < MMX reg 1 [byte] subtract MMX reg 2 [byte]	1/1
Memory to MMX Register	0FF8 [mod mm r/m]	MMX reg [byte] < MMX reg [byte] subtract memory [byte]	1/1
PSUBD Subtract Dword With Wrap-Arour			
MMX Register 2 to MMX Register 1	0FFA [11 mm1 mm2]	MMX reg 1 [dword] < MMX reg 1 [dword] subtract MMX reg 2 [dword]	1/1
Memory to MMX Register	0FFA [mod mm r/m]	MMX reg [dword] < MMX reg [dword] subtract memory [dword]	1/1
PSUBSB Subtract Byte Signed With Satu			
MMX Register 2 to MMX Register 1	0FE8 [11 mm1 mm2]	MMX reg 1 [sign byte] <sat 1="" 2="" [sign="" byte]="" byte]<="" mmx="" reg="" subtract="" td=""><td>1/1</td></sat>	1/1
Memory to MMX Register	0FE8 [mod mm r/m]	MMX reg [sign byte] <sat [sign="" byte]="" byte]<="" memory="" mmx="" reg="" subtract="" td=""><td>1/1</td></sat>	1/1
PSUBSW Subtract Word Signed With Sai	turation		
MMX Register 2 to MMX Register 1	0FE9 [11 mm1 mm2]	MMX reg 1 [sign word] <sat 1="" 2="" [sign="" mmx="" reg="" subtract="" td="" word]="" word]<=""><td>1/1</td></sat>	1/1
Memory to MMX Register	0FE9 [mod mm r/m]	MMX reg [sign word] <sat [sign="" memory="" mmx="" reg="" subtract="" td="" word]="" word]<=""><td>1/1</td></sat>	1/1
PSUBUSB Subtract Byte Unsigned With	Saturation		
MMX Register 2 to MMX Register 1	0FD8 [11 mm1 mm2]	MMX reg 1 [byte] <sat 1="" 2="" [byte]="" [byte]<="" mmx="" reg="" subtract="" td=""><td>1/1</td></sat>	1/1
Memory to MMX Register	0FD8 [11 mm reg]	MMX reg [byte] <sat [byte]="" [byte]<="" memory="" mmx="" reg="" subtract="" td=""><td>1/1</td></sat>	1/1
PSUBUSW Subtract Word Unsigned With	Saturation		
MMX Register 2 to MMX Register 1	0FD9 [11 mm1 mm2]	MMX reg 1 [word] <sat 1="" 2="" [word]="" [word]<="" mmx="" reg="" subtract="" td=""><td>1/1</td></sat>	1/1
Memory to MMX Register	0FD9 [11 mm reg]	MMX reg [word] <sat [word]="" [word]<="" memory="" mmx="" reg="" subtract="" td=""><td>1/1</td></sat>	1/1
PSUBW Subtract Word With Wrap-Aroun	d		
MMX Register 2 to MMX Register 1	0FF9 [11 mm1 mm2]	MMX reg 1 [word] < MMX reg 1 [word] subtract MMX reg 2 [word]	1/1
Memory to MMX Register	0FF9 [mod mm r/m]	MMX reg [word] < MMX reg [word] subtract memory [word]	1/1
PUNPCKHBW Unpack High Packed Byte	, Data to Packed Word	S	
MMX Register 2 to MMX Register 1	0F68 [11 mm1 mm2]	MMX reg 1 [byte] <interleave 1="" 2="" [up="" byte],="" byte]<="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1
Memory to MMX Register	0F68 [11 mm reg]	MMX reg [byte] <interleave [up="" byte],="" byte]<="" memory="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1
PUNPCKHDQ Unpack High Packed Dwo	rd, Data to Qword		
MMX Register 2 to MMX Register 1	0F6A [11 mm1 mm2]	MMX reg 1 [dword] <interleave 1="" 2="" [up="" dword],="" dword]<="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1
Memory to MMX Register	0F6A [11 mm reg]	MMX reg [dword] <interleave [up="" dword],="" dword]<="" memory="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1
PUNPCKHWD Unpack High Packed Wor	d, Data to Packed Dwo	rds	
MMX Register 2 to MMX Register 1	0F69 [11 mm1 mm2]	MMX reg 1 [word] <interleave 1="" 2="" [up="" mmx="" reg="" td="" word],="" word]<=""><td>1/1</td></interleave>	1/1
Memory to MMX Register	0F69 [11 mm reg]	MMX reg [word] <interleave [up="" memory="" mmx="" reg="" td="" word],="" word]<=""><td>1/1</td></interleave>	1/1

### Table 9-31. MMX Instruction Set Summary (Continued)

MMX Instructions	Opcode	Operation and Clock Count (Latency/Throughput)					
PUNPCKLBW Unpack Low Packed Byte, Data to Packed Words							
MMX Register 2 to MMX Register 1	0F60 [11 mm1 mm2]	MMX reg 1 [word] <interleave 1="" 2="" [low="" byte],="" byte]<="" mmx="" reg="" th=""><th>1/1</th></interleave>	1/1				
Memory to MMX Register	0F60 [11 mm reg]	MMX reg [word] <interleave [low="" byte],="" byte]<="" memory="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1				
PUNPCKLDQ Unpack Low Packed Dwo.	rd, Data to Qword						
MMX Register 2 to MMX Register 1	0F62 [11 mm1 mm2]	MMX reg 1 [word] <interleave 1="" 2="" [low="" dword],="" dword]<="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1				
Memory to MMX Register	0F62 [11 mm reg]	MMX reg [word] <interleave [low="" dword],="" dword]<="" memory="" mmx="" reg="" td=""><td>1/1</td></interleave>	1/1				
PUNPCKLWD Unpack Low Packed Work	d, Data to Packed Dwor	ds					
MMX Register 2 to MMX Register 1	0F61 [11 mm1 mm2]	MMX reg 1 [word] <interleave 1="" 2="" [low="" mmx="" reg="" td="" word],="" word]<=""><td>1/1</td></interleave>	1/1				
Memory to MMX Register	0F61 [11 mm reg]	MMX reg [word] <interleave [low="" memory="" mmx="" reg="" td="" word],="" word]<=""><td>1/1</td></interleave>	1/1				
PXOR Bitwise XOR							
MMX Register 2 to MMX Register 1	0FEF [11 mm1 mm2]	MMX reg 1 [qword] <logic 1="" 2="" [qword],="" [qword]<="" exclusive="" mmx="" or="" reg="" td=""><td>1/1</td></logic>	1/1				
Memory to MMX Register	0FEF [11 mm reg]	MMX reg [qword] <logic [qword]<="" exclusive="" memory[qword],="" mmx="" or="" reg="" td=""><td>1/1</td></logic>	1/1				

### 9.6 NATIONAL SEMICONDUCTOR EXTENDED MMX INSTRUCTION SET

National Semiconductor has added instructions to its implementation of the MMX Architecture in order to facilitate writing of multimedia applications. In general, these instructions allow more efficient implementation of multimedia algorithms, or more precision in computation than can be achieved using the basic set of MMX instructions. All of the added instructions follow the SIMD (single instruction, multiple data) format. Many of the instructions add flexibility to the MMX architecture by allowing both source operands of an instruction to be preserved, while the result goes to a separate register that is derived from the input.

Table 9-33 on page 235 summarizes the Extended MMX Instructions. The abbreviations used in the table are listed in Table 9-32.

Configuration control register CCR7(0) at location EBh must be set to allow the execution of the Extended MMX instructions.

Table 9-32. Extend MMX Instruction Set Table Legend

Abbreviation	Description
<	Result written
[11 mm reg]	Binary or binary groups of digits
mm	One of eight 64-bit MMX registers
reg	A general purpose register
<sat< td=""><td>If required, the resultant data is saturated to remain in the associated data range</td></sat<>	If required, the resultant data is saturated to remain in the associated data range
<move< td=""><td>Source data is moved to result location</td></move<>	Source data is moved to result location
[byte]	Eight 8-bit bytes are processed in parallel
[word]	Four 16-bit WORD are processed in parallel
[dword]	Two 32-bit DWORDs are processed in par- allel
[qword]	One 64-bit QWORD is processed
[sign xxx]	The BYTE, WORD, DWORD or QWORD most significant bit is a sign bit
mm1, mm2	MMX Register 1, MMX Register 2
mod r/m	Mod and r/m byte encoding (page 6-6 of this manual)
pack	Source data is truncated or saturated to next smaller data size, then concatenated.
packdw	Pack two DWORDs from source and two DWORDs from destination into four WORDs in destination register.
packwb	Pack four WORDs from source and four WORDs from destination into eight BYTEs in destination register.

Table 9-33. Extended MMX Instruction Set Summary

MMX Instructions	Opcode	Operation and Clock Count	
PADDSIW Packed Add Signed Word with Saturation Using	g Implied Destination		
MMX Register plus MMX Register to Implied Register	0F51 [11 mm1 mm2]	Sum signed packed word from MMX register/memory>	1
Memory plus MMX Register to Implied Register	0F51 [mod mm r/m]	signed packed word in MMX register, saturate, and write result> implied register	1
PAVEB Packed Average Byte			
MMX Register 2 with MMX Register 1	0F50 [11 mm1 mm2]	Average packed byte from the MMX register/memory with	1
Memory with MMX Register	0F50 [mod mm r/m]	packed byte in the MMX register. Result is placed in the MMX register.	1
PDISTIB Packed Distance and Accumulate with Implied R	egister egister		
Memory, MMX Register to Implied Register	0F54 [mod mm r/m]	Find absolute value of difference between packed byte in memory and packed byte in the MMX register. Using unsigned saturation, accumulate with value in implied destination regis- ter.	2
PMACHRIW Packed Multiply and Accumulate with Round	ing		
Memory to MMX Register	0F5E[mod mm r/m]	Multiply the packed word in the MMX register by the packed word in memory. Sum the 32-bit results pairwise. Accumulate the result with the packed signed word in the implied destination register.	2
PMAGW Packed Magnitude			
MMX Register 2 to MMX Register 1	0F52 [11 mm1 mm2]	Set the destination equal> the packed word with the largest	2
Memory to MMX Register	0F52 [mod mm r/m]	magnitude, between the packed word in the MMX register/memory and the MMX register.	2
PMULHRIW Packed Multiply High with Rounding, Implied	Destination		
MMX Register 2 to MMX Register1	0F5D [11 mm1 mm2]	Packed multiply high with rounding and store bits 30 - 15 in	2
Memory to MMX Register	0F5D [mod mm r/m]	implied register.	2
PMULHRW Packed Multiply High with Rounding			
MMX Register 2 to MMX Register 1	0F59 [11 mm1 mm2]	Multiply the signed packed word in the MMX register/memory	2
Memory to MMX Register	0F59 [mod mm r/m]	with the signed packed word in the MMX register. Round with 1/2 bit 15, and store bits 30 - 15 of result in the MMX register.	2
PMVGEZB Packed Conditional Move If Greater Than or E	qual to Zero		
Memory to MMX Register	0F5C [mod mm r/m]	Conditionally move packed byte from memory> packed byte in the MMX register if packed byte in implied MMX register is greater than or equal> zero.	1
PMVLZB Packed Conditional Move If Less Than Zero	i		
Memory to MMX Register	0F5B [mod mm r/m]	Conditionally move packed byte from memory> packed byte in the MMX register if packed byte in implied MMX register is less than zero.	1
PMVNZB Packed Conditional Move If Not Zero	•		
Memory to MMX Register	0F5A [mod mm r/m]	Conditionally move packed byte from memory> packed byte in the MMX register if packed byte in implied MMX register is not zero.	1
PMVZB Packed Conditional Move If Zero			
Memory to MMX Register	0F58 [mod mm r/m]	Conditionally move packed byte from memory> packed byte in the MMX register if packed byte in implied the MMX register is zero.	1
PSUBSIW Packed Subtracted with Saturation Using Implie	ed Destination		
MMX Register 2 to MMX Register 1	0F55 [11 mm1 mm2]	Subtract signed packed word in the MMX register/memory from	1
Memory to MMX Register	0F55 [mod mm r/m]	signed packed word in the MMX register, saturate, and write result> implied register.	1

### Appendix A Support Documentation

### A.1 ORDER INFORMATION

Order Number	Part Marking	Core Frequency (MHz)	Temperature (Degree C)	Package
30070-53	GXm-266P 2.9V 70C	266	70	SPGA
30071-53	GXm-266P 2.9V 85C	266	85	SPGA
30170-53	GXm-266B 2.9V 70C	266	70	BGA
30171-53	GXm-266B 2.9V 85C	266	85	BGA
30050-33	GXm-233P 2.9V 70C	233	70	SPGA
30054-33	GXm-233P 2.9V 85C	233	85	SPGA
30150-33	GXm-233B 2.9V 70C	233	70	BGA
30151-33	GXm-233B 2.9V 85C	233	85	BGA
30040-23	GXm-200P 2.9V 70C	200	70	SPGA
30044-23	GXm-200P 2.9V 85C	200	85	SPGA
30140-23	GXm-200B 2.9V 70C	200	70	BGA
30141-23	GXm-200B 2.9V 85C	200	85	BGA
30030-23	GXm-180P 2.9V 70C	180	70	SPGA
30034-23	GXm-180P 2.9V 85C	180	85	SPGA
30130-23	GXm-180B 2.9V 70C	180	70	BGA
30131-23	GXm-180B 2.9V 85C	180	85	BGA

### A.2 DATA BOOK REVISION HISTORY

This document is a report of the revision/creation process of the data book for the GXm processor. Any revisions

(i.e., additions, deletions, parameter corrections, etc.) are recorded in the tables below.

Table A-1. Revision History

Revision # (PDF Date)	Revisions / Comments
0.0 (2/5/98)	Creation phase
0.1 (2/25/98)	Creation phase continues - added functional description.
0.2 (3/24/98)	Creation phase continues - added 233 MHz parameters.
0.3 (4/22/98)	Creation phase continues - added 266 MHz numbers.
1.0 (8/13/98)	All sections complete - added 300 MHz numbers, added Index.
2.0 (10/29/98)	Major change is new values for 352 BGA Mechanical.
3.0 (9/21/99)	Converted to National Semiconductor format and updated for addendum revision 3.0.
3.1 (4/6/00)	Formatting changes and one change from engineering. See Table A-2 for details.

Table A-2. Edits to Current Revision

Section	Revision
3.0 Processor Programming	Combined bits 1 and 2 of Configuration Control Register 1 in Table 3-11 on page 52.
7.0 Electricals	<ul> <li>All references to Recommended Operating Conditions became Operating Conditions.</li> <li>Table 7-3 on page 183 - Changed supply voltage from 3.6V to 3.2V.</li> </ul>

# Index

Α		CCR7	
Absolute Maximum Ratings	183	Cyrix Extended MMX Instructions Enable	50
AC Characteristics	186	NMI Enabl	50
Accessing	157	CCR7 Configuration Control Register 7 Index EBh	50
Address Spaces	60	Clock Mode Configuration Register Map	24 48
Directory Table Entry (DTE)	73	Control Registers	48
DTE Cache	73	Device ID Registers	48
I/O Address Space	60 60	Graphics/VGA Related Registers	48
Memory Address Space Memory Addressing Modes	61	SMM Base Header Address Registers	48
Offset Mechanism	61	Configuration Register Summary	47
Page Frame Offset (PFO)	73	Conforming Code Segments	69
Page Table Entry (PTE)	73	Control Transfer	87
Paging Mechanism	72	CPU_READ	99
Translation Look-Aside Buffer	74	CPU_READ/WRITE EAX instructions	99
Address Translation	108	EBX instructions	99
Application Register Set	40	CPU_WRITE	99
В		CPUID Instruction	208
BGA Ball Assignments by Ball Number	15	EAX = 0000 0000h	208
BGA Ball Assignments by Pin Name	17	EAX = 0000 0001h	208
BGA Ball Assignments Diagram	14	EAX = 0000 0002h	209
C		EAX = 8000 0000h	210
		EAX = 8000 0001h	210
Cache	05	EAX = 8000 0002h	211
BB0_BASE BB0_POINTER	95 95	EAX = 8000 0003h	211
BB1_BASE	95	EAX = 8000 0004h	211
BB1_POINTER	95	EAX = 8000 0005h CPUID Levels	211 208
GCR register (Index B8h)	95	CPUID Levels, Extended	210
L1 cache	95	CR0 Register	45
scratchpad memory	95	Alignment Check Mask	46
Write-back caching	95	Cache Disable	46
Cache Controller	95	Emulate Processor Extension	46
Cache Disable, bit 30	95	Monitor Processor Extension	46
Cache Test Operations	58	Not Write-Through	46
call gate	69 69	Numerics Exception	46
Current Privilege Level Descriptor Privilege Level	69	Paging Enable Bit	45
Descriptor Privilege Level in Destination	69	Protected Mode Enable Task Switched	46 46
Descriptors Bit Definitions	69	Write Protect	46
Segment Selector Field	69	CR2 Register	45
CCR1		Page Fault Linear Address	45
System Management Memory Access	49	CR3 Register	45
CCR1 Configuration Control Register 1 Index C1h	49	Page Directory Base Register	45
CCR2	40	CR4 Register	45
Enable Suspend Pins Lock NW Bit	49 40	Time Stamp Counter Instruction	45
Suspend on HALT	49 49	D	
Write-Through Region 1	49	DC Characteristics	185
CCR2 Configuration Control Register 2 Index C2h	49	Descriptor Bit Structure	67
CCR3		Descriptor Types	87
Load/Store Serialize 1 GByte to 2 GBytes	49	Descriptors	
Load/Store Serialize 2 GBytes to 3 GBytes	49	Gate	67
Load/Store Serialize 3 GBytes to 4 GBytes	49	gate	69
Map Enable	49	Interrupt	67
NMI Enable	49	Task	67
SMM Register Lock	49	Device Select	28
CCR3 Configuration Control Register 3 Index C3h CCR4	49	DEVSEL DIMM	28 112
Directory Table Entry Cache	50	DIR0	112
Enable CPUID Instruction	50	Device ID	51
I/O Recovery Time	50	DIR0 Device Identification Register 0 Index FEh	51
Memory Read Bypassing	50	DIR1	
SMI Nest	50	Device Identification Revision	51
CCR4 Configuration Control Register 4 Index E8h	50	DIR1 Device Identification Register 1 Index FFh	51

irectory Table Entry	73	ВТ	53
isplay Controller	129—154	DR7 and DR6 Bit Definitions	53
Buffer Organization	135	DR7 Register	53
CODEC hardware	129	GD	53
Compression Logic	130	Gn	53
Compression Technology	130	LENn	53
CRT Display Modes	134	Ln	53
Cursor Pattern Memory	136	R/Wn	53
DC Memory Organization	135	DRAM Address Conversion	112
DC_CURSOR_COLOR Register (BX_BASE	+8360h) 131	E	
Display FIFO	130		
Display Modes	131	EBP register	40
Display Timing	131	EFLAGS Register	43
Dither/Frame-Rate Modulation (FRM)	131	Alignment Check Enable (AM)	43
Graphics Memory Map	135	Auxiliary Carry Flag	43
Hardware Cursor	131	Carry Flag	43
Memory Management	130	CPUID instruction	43
Pixel Arrangement Within a DWORD	135	Direction Flag (DF)	43
RAMDAC	129	I/O Privilege Level (IOPL)	43
TFT LCD flat panel	129	Identification Bit	43
TFT Panel Data Bus Formats	133	Interrupt Enable	43
TFT Panel Display Modes	132	Nested Task (NT)	43
VESA-compatible	131	Resume Flag (RF)	43
VGA Display Support	136	Sign Flag	43
splay Controller Block Diagram	129	Trap Enable Flag	43
splay Controller Registers	136	Virtual 8086 Mode (VM)	43
Configuration and Status Registers	139	EFLAGS register, bit 9	83
DC_BORDER_COLOR (8368h-836Bh)	138	EGA	165
DC_BUF_SIZE (8328h-832Bh)	137	Electrical Connections	182
DC_CB_ST_OFFSET (8314h-8317h)	137	NC-Designated Pins	182
DC_CFIFO_DIAG (837Ch-837Fh)	138	Power/Ground Connections	182
DC_CURS_ST_OFFSET (8318h-831Bh)	137	Pull-Up/Pull-Down Resisters	182
DC_CURSOR_COLOR (83680h-8363h)	138	Unused Input Pins	182
DC_CURSOR_X (8350h-8353h)	137	Electrical Specifications	182
DC_CURSOR_Y (8358h-835Bh)	137	Absolute Maximum Ratings	183
DC_DFIFO_DIAG (8378h-837Bh)	138	AC Characteristics	186
DC_FB_ST_OFFSET (8310h-8313h)	136	Clock Signals	187
DC_FP_H_TIMING (833Ch-833Fh)	137	DC Characteristics Table	185
DC_FP_V_TIMING (834Ch-834Fh)	137	DCLK Timing	192
DC_GENERAL_CFG (8304h-8307h)	136	Graphics Port Timing	191
DC_H_TIMING_1 (8330h-8333h)	137	JTAG AC Specification	193
DC_H_TIMING_2 (8334h-8337h)	137	JTAG Test Timings	194
DC_H_TIMING_3 (8338h-833Bh)	137	Output Valid Timing	190
DC_LINE_DELTA (8324h-8327h)	137	Part Numbers	182
DC_OUTPUT_CFG (830Ch-830Fh)	136	PCI Interface Signals	189
DC_PAL_ADDRESS (8370h-8373h)	138	SDRAM Interface Signals	190
DC_PAL_DATA (8374h-8377h)	138	Setup and Hold Timings	190
DC_SS_LINE_CMP (835Ch-835Fh)	137	SYSCLK Timing	187
DC_TIMING_CFG (8308h-830Bh)	136	System Signals	188
DC_UNLOCK (8300h-8303h)	136	TCK Timing and Measurement Points	193
DC_V_LINE_CNT (8354h-8357h)	137	Video Interface Signals	191
DC_V_TIMING_1 (8340h-8343h)	137	Video Port Timing	192
DC_V_TIMING_2 (8344h-8247h)	137	Exceptions	74
DC_V_TIMING_3 (8348h-834Bh)	137	Abort	75
DC_VID_ST_OFFSET (8320h-8323h)	137	Fault	75
Memory Organization Registers	144	Trap	74
splay Driver		Extended MMX Instruction Set	234
BB0_RESET	98	Extended MMX <sup>TM</sup> Instruction Set	00.
BB1_RESET	98	Configuration Control Rregister	234
CPU_READ	98	Legend	234
CPU_WRITE	98	F	
Scratchpad	98	- Fields - index	207
splay Driver Instructions	98	Fields - mod and r/m	205
R6 Register	53	Fields - sreg3	206
Bn	53	Fields - ss	200
BS	53	floating point error	25

Index (Continued)			
FPU		GP_VGA_LATCH (8214h-8217h)	125
Mode Control Register	89	GP_VGA_LATOTT (821417821711) GP_VGA_READ (8200h-8203h)	124
Register Set	89	GP_VGA_WRITE (8140h-8143h)	124
Status Register	89	Master/Slave Registers	121
Tag Word Register	89	Monochrome Patterns	122
FPU Instruction Set	224	Pattern Generation	121
Summary Notes	228	graphics pipeline	165, 166
FPU Mode Control Register	90	Graphics Pipeline Block Diagram	120
Denormalized-operand error exception bit	90	Н	
Divide-by-zero exception bit Invalid-operation exception bit	90 90	HALT	25
Overflow error exception bit	90	High Order Interleaving	112
Precision Control Bits	90	1	
Precision error exception bit	90	I/O Address Space	60
Rounding Control Bits	90	Initialization	60 38
FPU Operations	89	Initialization, CPU	38
FPU Registers	90	Initiator Ready	00
FPU Status Register	90	IRDY	27
Condition code bit 3	90	TRDY	27
Condition code bits Copy of ES bit	90 90	Instruction Fields	202
Denormalized-operand error exception bit	90	Instruction Set	39
Divide-by-zero exception bit	90	eee Field Encoding	204
Error indicator	90	Index Field	207
Invalid operation exception bit	90	Memory Addressing mod base Field Encoding table	205 207
Overflow error exception bit	90	mod r/m Field Encoding	205
Precision error exception bit	90	Opcode	203
Stack Full	90	prefix bytes	203
Top-of-Stack	90	reg Field	206
Underflow error exception bit FPU Tag Word Register (TAG7:0]	90 90	s-i-b Byte	207
frame buffer	94	s-i-b present	207
	34	sreg2 field	206
G		sreg3	206
Gates	87	ss Field w Field Operand Size	207 203
General Purpose Registers	40	instruction set	203
Global Descriptor Table Register (GDTR)	66	Instruction Set Format Table	202
Grant Lines Graphics Memory (GX_BASE+800000h)	29 94	Instruction Set Formats	201
Graphics Pipeline	120-128	Instruction Set Overview	39
BitBLT/vector engine	120	Instructions	
Color Patterns	123	Bit Test Instructions	39
Diagonal Error Register (108h-810Bh)	124	Exchange Instructions	39
Dither Patterns	122	One-operand Arithmetic and Logical	39
Error Register (8104-8107h)	124	Two-operand Arithmetic and Logical Instuction Prefix Summary	39 203
GP_BLT_MODE	120	Institution Frenk Summary Integrated Functions	203 91
GP_BLT_MODE (8208h-820Bh)	124	Integrated Functions Programming Interface	92
GP_BLT_STATUS (820Ch-820Fh) GP_DST/START_Y/XCOOR (8100h-8103h)	125 124	Interleaving	112
GP_DST_XCOOR	121	Internal Bus Interface	100-102
GP_DST_YCOOR	121	Internal Bus Interface Unit	
GP_INIT_ERROR	121	640KB to 1MB	100
GP_PAT_COLOR_0 register	122	C-Bus	100
GP_PAT_COLOR_1 (GX_BASE+8112h)	122	FPU Error Support	100
GP_PAT_COLOR_A (8110h)	124	Graphics IRQ13	100 100
GP_PAT_COLOR_B (8114h)	124	L1 cache	100
GP_PAT_DATA (8120h-812Fh)	124	Processor Core	100
GP_RASTER_MODE (8200h-8203h) GP_RASTER_MODE (GX_BASE+ 8200h)	124 122	Region Control Field Bit Definitions	102
GP_RASTER_MODE (GA_BASE+ 820011) GP_RASTER_MODE Bit Patterns	123	Registers (GX_BASE+8000h)	101
GP_SRC_COLOR (810Ch-810Fh)	123	SMI Interrupts	100
GP_SRC_COLOR_0 (GX_BASE+810Ch)	123	VGA Access	100
GP_SRC_YCOOR	121	X-Bus	100
GP_VECTOR_MODE (8204h-8207h)	124	Internal Bus Interface Unit Diagram	91
GP_VGA_BASE (8210h-8213h)	125	Internal Bus Interface Unit Registers	

Index (Continued)			
BC_DRAM_TOP (8000h-8003h)	101	SDRAM Interface Clocking	11
BC_XMAP_1 (8004h-8007h)	101	CAS latency	11
BC_XMAP_2 (8008h-800Bh)	101	SDRAM Read Cycle	11:
BC_XMAP_3 (800Ch-800Fh)	101	SDRAM Refresh Cycle	11
nternal Test Signals		SDRAM Write Cycle	11
Ifloat	32	SHFTSDCLK	11
Raw Clock	32	X-Bus	10
SDRAM Test Outputs	32	Memory Controller Interface Signals	
Test	33	Bank Address Bits	2
Test Clock	32	Chip Selects	2
Test Data Input	32	Clock Enable	3
Test Data Output	32	Column Address Strobe	2
Thermal Diode Negative (TDN)	33	Data Mask Control Bits	3
Thermal Diode Positive (TDP)	33	Memory Address Bus	2
nterrupt	00	Row Address Strobe	2
Interrupt and Exception Priorities	76	SDRAM Clocks	3
nterrupt Descriptor Table	75	Write Enable	2
nterrupt Descriptor Table nterrupt Request Level 13	75 25	Memory Controller Register	10
	25 74	,	10
nterrupts		MC_BANK_CFG (8408h-840Bh)	
INTR	74	MC_DR_ACC (841Ch-841Fh)	10
NMI	74	MC_DR_ADD (8418h-8418h)	10
Real Mode Error Codes	77 	MC_GBASE_ADD (8414h-8417h)	10
Real Mode, Exceptions	77	MC_MEM_CNTRL1 (8400h-8403h)	10
SMM	74	MC_MEM_CNTRL2 (8404h-8407h)	10
Vector A	75	MC_SYNC_TIM1 (840Ch-840Fh)	10
· · · · · · · · · · · · · · · · · · ·	4, 76, 83, 85, 86	Memory Data Bus	2
nvalid opcode	39	MMX Instruction Set	22
RET instruction	43	Multiplexed Address	
<u>_</u>		PCI pins	2
	405	Multiplexed Command	
_egacy VGA	165	Configuration Read	2
Local Descriptor Table Register (LDTR)	66	Configuration Write	2
-OCK	28	Dual Address Cycle	2
ock Prefix	39	Memory Read Line	2
_ow Order Interleaving	112	Memory Read Multiple	2
M		Memory Write and Invalidate	2
	407	Special Cycle	2
MediaGX™ Virtual VGA	167	Multiplexed Command and Byte Enables	
Memory Address Space	60	Interrupt Acknowledge	2
Memory Addressing	70	Multitasking	7
Paging Mechanism	72	-	_
Memory Addressing Modes	61	N	
Memory Controller	103—119	NMI 49, 74, 75, 76, 78,	, 83, 85, 8
Auto LOI	112	notebook computers	17
1 DIMM Bank	113	•	
2 DIMM Banks	113	0	
Block Diagram	103	Overflow Flag	4
DRAM Address Conversion	112	Р	
DRAM Configuration	105	-	
Graphics Pipeline	103	Package Outlines	19
Memory Array Configuration	104	Package Specifications	19
Memory Cycles	115	Page Table Entry	7
Memory Organization	105	palette lookup	16
Non-Auto LOI		PCI Arbitration	16
1 DIMM Bank	114	PCI Configuration Registers	
2 DIMM Banks	114	Access Format	15
Page Miss	117	Bus	15
Processor Interface	103	Cache Line Size (0Ch)	15
SDRAM	104	Class Code (09h-0Bh)	15
SDRAM Commands	106	CONFIG ENABLE	15
		CONFIG_DATA 0CFCh-0CFFh	15
ACT	107	Device	15
MRS	106	Device Identification (02h-03h)	15
PRE	106	Device Status (06h-07h)	15
READ	107		15
WRT	107	Latency Timer (0Dh)	
SDRAM Initialization Sequence	107	PCI Arbitration Control 1 (43h) PCI Arbitration Control 2 (44h)	15 15
ODITATIVI IIIII alizationi ocquenoc			

#### Index (Continued) PCI Command (04h-05h) 157 Power, Ground, No Connect Signals PCI Control Function 1 (40h) Ground (VSS) 157 32 PCI Control Function 2 (41h) No Connect (NC) 157 32 Power Connect (VCC2) Register 156 32 Revision Identification (08h) Power Connect (VCC3) 32 157 Voltage Detect(VOLDET) Translation Type Bits 1 32 156 Privilege Level Transfers 87 Vendor Identification (00h-01h) Privilege Levels (CPL, DPL and RPL) 86 157 PCI Configuration Registers 0CF8h-0CFBh Privilege Levels (I/O) 86 156 PCI Controller 155 Processor Core Instruction Set 212 CONFIG ADDRESS 155 **Clock Counts** 212 Configuration Cycles 155 Flags 212 **PCI** Arbiter Legend 212 155 Opcodes Space Control Registers 156 212 Special Cycles 155 Processor Initialization 38 X-Bus PCI Master 155 Programming Interface 38 X-Bus PCI Slave 155 Protected Mode, Initialization and Transition 87 PCI Cycles Protection 86 162 PCI Halt Command 164 Current Privilege Level (CPL) 86 Descriptor Privilege Level (DPL) PCI Interface Signals 86 Frame 27 Requested Privilege Level (RPL) 86 Initiator Ready 27 Protection - V86 Mode 88 Lock Operation 28 Multiplexed Address and Data 26 Register Controls 38 Multiplexed Command and Byte Enables 26 Register Sets 40 Parity 26 Application Parity Error 28 Flags Register 40 Request Lines 28 General Purpose Register 40 Target Ready 27 Instruction Pointer Register 40 Target Stop 27 Segment Registers 40 PCI Local Bus Specification 162 Flags Register 43 **PCI** Read Transactions 162 General Purpose 40 PCI Special Cycle Command 164 Data Registers 40 **PCI Write Transactions** 163 Pointer and Index Registers 40 PCR Performance Control Register Index 20h 50 Instruction Pointer 42 **PERR** 28 Selection Rules 42 Pixel Arrangement Within a DWORD 135 Model Specific Register 40 Pointer and Index Registers System Register Set 40, 44 **ECX Counter** 40 Registers **EDI Destination Pointer** 40 Application Register 40 ESI Source Pointer 40 Model Specific Register 59 **ESP** Register 40 REQ 28 PUSH and POP Instructions 40 RESET 38 Power and Ground Connections and Decoupling 182 ROP (raster operation) 166 Power Management 174 Row Address Strobe 3-Volt Suspend Mode 174 CAS 29 Advanced Power Management (APM) 174 CKE 29 **CPU Suspend Command Registers** 174 RAS 29 Initiating Suspend with HALT 176 **RASA** 29 Initiating Suspend with SUSP 175 **RASB** 29 Processor Serial Bus 179 WE 29 Responding to a PCI Access During Suspend Mode 177 Serial Packet Transmission S Stopping the Input Clock 178 Scratchpad Suspend Mode and Bus Cycles 175 2KB configurations 97 Suspend Modulation 174 3KB configurations 97 **Power Management Registers** 179 SMM information 97 PM\_BASE (FFFF FF6Ch) 179 Scratchpad RAM 97 PM\_CNTRL\_CSTP (8508h-850Bh) 179 **SDRAM Clocks** PM\_CNTRL\_TEN (8504h-8507h) 179 SDCLK IN 30 PM\_MASK (FFFF FF7Ch) 179 SDCLK OUT 30 PM SER PACK (850Ch-850Fh) 179 Segment Register Selection Rules 42 PM\_STAT\_SMI (8500h-8503h) 179 Segment Registers 42 Power Planes 36-37 Serial Packet Power, Ground, No Connect CX5520 25 Ground (VSS) 32

VSA	25	Debug Registers	4
hutdown and Halt	86	Gate Descriptors	69
gnal Definitions	13–23	Task Register	69, 7
gnal Descriptions	24	System Registers	44 <u></u> -5
Cyrix Internal Test and Measurement Signal	s 32	Configuration Registers	4
Memory Controller Interface Signals	29-30	Control Registers	4
PCI Interface Signals	26–29	Debug Registers	5
Power, Ground and No Connect Signals	32	Model Specific Register (MSR)	5
System Interface Signals Video Interface Signals	24—25 30—31	Segment Descriptor Table Registers	6 5
gnals - INTR	30—31 74	Test Registers	5
gnals - NMI	74	T	
gnals - SMM	74	Task Gate Descriptors	70
ZE		Task Register (TR)	7
SMM Region Size Bits	51	Task State Segments	70
tip Counts	94	Thermal Characteristics	19
MAR		TR3 Register	5 <sup>-</sup>
SMM Address Region Bits	51	Cache Data TR4 Register	5 5
MAR SMM Address Region Register Indices CD	n, CEH, CFh	Dirty Bits	5 <sup>-</sup>
MHR		LRU Bits	5
SMM Header Address	51	Upper Tag Address	5
######################################	_	Valid Bit	5
лі пто отполюцию таково птаново доті, дотті, да Лі	, 20 00	TR5 Register	5
Configuration Registers	80	Control Bits	5
Generation	83	Line Selection	5
ЛІ#	74, 75, 78	TR6 Register	5
pin	80	Command Bit	5: 5:
/II# pin	174	Dirty Attribute Bit Linear Address	5: 5:
MM ODLL Otatas	78	Valid Bit	5:
CPU States	85 82	TR7 Register	5
Instructions Memory Space	83	LRU Bits	5
Memory Space Header	80	Physical Address	5
Operation	79	PL Bit	5
SMI Enhancements	79	Set Selection	5
SMI Events	80	Translation Lookaside Buffer	9:
SMI Nested States	84	V	
SMI Nesting	83	V86 Mode	
SMI Service Routine Execution	83	Entering and Leaving	88
SMI# Pin	80	Interrupt Handling	8
Suspend Mode CPU States	85 85	Memory Addressing	88
Suspend Mode CPU States  MM Memory Space Header Description	81	VESA	16
PGA Pin Assignments by Pin Number	20	VGA Address Mapping	16
PGA Pin Assignments by Signal Name	22	MapMask register	16
PGA Pin Assignments Diagram	19	Miscellaneous Output register VGA Configuration Registers	16 <sup>-</sup>
OP	27	VGA Control Register (B9h)	16
bsystem Signal Connections	34-35	VGA Mask Register (BAh-BDh)	16
spend	59, 85, 86	VGA Front End	160
spend Mode	25	VGA function	
stem Error	28	attribute controller	16
NMI stem Interface Signals	28	CRT controller	16
stem Interface Signals Interrupt Request	25	frame buffer	16
Reset	24	general registers	16
Serial Packet	25	graphics controller	160
Suspend Acknowledge	25	sequencer	165 16
Suspend Request	25	VGA Hardware SMI Generation	165, 166 166
System Clock	24	VGA Address Generator	168
System Management Interrupt	25	VGA Address Generator VGA Memory	16
stem Management Interrupt (SMI#)	165	VGA Range Detection	168
rstem Register Set	44	VGA Sequencer	168
rstem Register Sets	50	VGA Write/Read Path	168
Cache Test Registers Configuration Registers	56 47	VGA Memory	17

#### Index (Continued) frame buffer address 166 host address 166 refresh address 166 VGA Memory Addresses 169 VGA Memory Organization 166 VGA Range Detection 171 VGA Sequencer 171 VGA Video BIOS 171 VGA Video Refresh 168 All Points Addressable mode (APA) 168 attribute controller (ATTR) 168 CGA mode 168 Chain 4 mode 168 ClockSelect field 168 ColorPlaneEnable register 168 CRT controller (CRTC) 168 LineCompare register 168 Miscellaneous Output register 168 ShiftRegister field 168 VGA Write/Read Path 171 Video Data Bus VID\_CLK 31 Video Interface Signals **CRT Horizontal Sync** 30 CRT Vertical Sync 31 Display Enable 31 Dotclock 30 Flat Panel Horizontal Sync 31 Flat Panel Vertical Sync 31 Graphics Pixel Data Bus 31 Pixel Port Clock 30 Video Clock 30 Video Data Bus 31 Video Ready 31 Video Valid 31 video refresh 166 Virtual 8086 Mode (V86) 88 Virtual Subsystem Architecture (VSA) 165 Virtual VGA 165 ColorCompare register 167 ColorDon'tCare register 167 **Datapath Elements** 167 read mode unit 167 write-mode unit 167 DataRotate register 167 ReadMapSelect register 167 SetReset register 167 SMI Generation 168 Virtual VGA Register Descriptions 172 VIrtual VGA Registers GP\_VGA\_WRITE (8140h-8143h) 172 Virtual VGA Registers GP\_VGA\_BASE VGA (8210h-8213h) 172 GP\_VGA\_LATCH (8214h-8217h) 172 GP\_VGA\_READ (8144h-8147h) 172 **XpressAUDIO** 165

#### LIFE SUPPORT POLICY

NATIONAL'S PRODUCTS ARE NOT AUTHORIZED FOR USE AS CRITICAL COMPONENTS IN LIFE SUPPORT DEVICES OR SYSTEMS WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE PRESIDENT AND GENERAL COUNSEL OF NATIONAL SEMICONDUCTOR CORPORATION. As used herein:

- Life support devices or systems are devices or systems which, (a) are intended for surgical implant into the body, or (b) support or sustain life, and whose failure to perform when properly used in accordance with instructions for use provided in the labeling, can be reasonably expected to result in a significant injury to the user.
- A critical component is any component of a life support device or system whose failure to perform can be reasonably expected to cause the failure of the life support device or system, or to affect its safety or effectiveness.



# National Semiconductor Corporation

Americas Tel: 1-800-272-9959 Fax: 1-800-737-7018 Email: support@nsc.com

# National Semiconductor Europe

Fax: +49 (0) 180-530 85 86 Email: europe.support@nsc.com Deutsch Tel: +49 (0) 69 9508 6208 English Tel: +44 (0) 870 24 0 2171 Francais Tel: +33 (0) 1 41 91 8790 National Semiconductor Asia Pacific Customer Response Group

Tel: 65-2544466 Fax: 65-2504466

Email: ap.support@nsc.com

National Semiconductor Japan Ltd.

Tel: 81-3-5639-7560 Fax: 81-3-5639-7507

www.national.com



Компания «Океан Электроники» предлагает заключение долгосрочных отношений при поставках импортных электронных компонентов на взаимовыгодных условиях!

### Наши преимущества:

- Поставка оригинальных импортных электронных компонентов напрямую с производств Америки, Европы и Азии, а так же с крупнейших складов мира;
- Широкая линейка поставок активных и пассивных импортных электронных компонентов (более 30 млн. наименований);
- Поставка сложных, дефицитных, либо снятых с производства позиций;
- Оперативные сроки поставки под заказ (от 5 рабочих дней);
- Экспресс доставка в любую точку России;
- Помощь Конструкторского Отдела и консультации квалифицированных инженеров;
- Техническая поддержка проекта, помощь в подборе аналогов, поставка прототипов;
- Поставка электронных компонентов под контролем ВП;
- Система менеджмента качества сертифицирована по Международному стандарту ISO 9001;
- При необходимости вся продукция военного и аэрокосмического назначения проходит испытания и сертификацию в лаборатории (по согласованию с заказчиком);
- Поставка специализированных компонентов военного и аэрокосмического уровня качества (Xilinx, Altera, Analog Devices, Intersil, Interpoint, Microsemi, Actel, Aeroflex, Peregrine, VPT, Syfer, Eurofarad, Texas Instruments, MS Kennedy, Miteq, Cobham, E2V, MA-COM, Hittite, Mini-Circuits, General Dynamics и др.);

Компания «Океан Электроники» является официальным дистрибьютором и эксклюзивным представителем в России одного из крупнейших производителей разъемов военного и аэрокосмического назначения «JONHON», а так же официальным дистрибьютором и эксклюзивным представителем в России производителя высокотехнологичных и надежных решений для передачи СВЧ сигналов «FORSTAR».



**«JONHON»** (основан в 1970 г.)

Разъемы специального, военного и аэрокосмического назначения:

(Применяются в военной, авиационной, аэрокосмической, морской, железнодорожной, горно- и нефтедобывающей отраслях промышленности)

«**FORSTAR**» (основан в 1998 г.)

ВЧ соединители, коаксиальные кабели, кабельные сборки и микроволновые компоненты:

(Применяются в телекоммуникациях гражданского и специального назначения, в средствах связи, РЛС, а так же военной, авиационной и аэрокосмической отраслях промышленности).



Телефон: 8 (812) 309-75-97 (многоканальный)

Факс: 8 (812) 320-03-32

Электронная почта: ocean@oceanchips.ru

Web: http://oceanchips.ru/

Адрес: 198099, г. Санкт-Петербург, ул. Калинина, д. 2, корп. 4, лит. А