

Intel Atom® Processor C3000 Product Family

Datasheet

February 2018

Order Number: 337018-002

Intel technologies' features and benefits depend on system configuration and may require enabled hardware, software or service activation. Learn more at intel.com, or from the OEM or retailer.

No computer system can be absolutely secure.

The products described may contain design defects or errors known as errata which may cause the product to deviate from published specifications. Current characterized errata are available on request.

No license (express or implied, by estoppel or otherwise) to any intellectual property rights is granted by this document.

This document contains information on products, services and/or processes in development. All information provided here is subject to change without notice. Contact your Intel representative to obtain the latest forecast, schedule, specifications and roadmaps.

Intel does not control or audit third-party benchmark data or the web sites referenced in this document. You should visit the referenced web site and confirm whether referenced data are accurate.

Intel, the Intel logo, Pentium, Celeron, Atom, Core, Xeon and others are trademarks of Intel Corporation in the U.S. and/or other countries. *Other names and brands may be claimed as the property of others.

Contact your local Intel sales office or your distributor to obtain the latest specifications and before placing your product order.

Copies of documents which have an order number and are referenced in this document, or other Intel literature, may be obtained by calling 1-800-548-4725, or go to: http://www.intel.com/design/literature.htm

*Other names and brands may be claimed as the property of others.

Copyright © 2018, Intel Corporation. All rights reserved.

Revision History

Date	Revision	Description
February 2018	002US	Below is an overview of broad changes: Chapter 31, "Intel® QuickAssist Technology (Intel® QAT)" • Updated Intel® QuickAssist Reference. **Included Register Chapters from the Intel Atom® Processor C3000 Product Family External Design Specification Volume 4 into this Datasheet.**
January 2018	001US	Initial release.

Contents

Volume 1: Program Overview 105

1 Introduction and Product Offerings **106**
1.1 Overview 106
1.2 SoC Key Features 113
1.2.1 Processor Details 114
1.2.2 Supported Technologies 114
1.2.3 System Memory Support 115
1.2.4 Integrated Clock Generator 116
1.2.5 Intel® QuickAssist Technology (Intel® QAT) 116
1.2.6 Intel® Management Engine (Intel® ME) 117
1.2.7 Innovation Engine (IE) 117
1.2.8 Interface Features 118
1.2.8.1 High Speed I/O Lanes 118
1.2.8.2 LAN Ports 119
1.2.8.3 SMBus Controllers 119
1.2.8.4 Embedded Multi Media Card (eMMC) 119
1.2.8.5 High-Speed Universal Asynchronous Receiver/Transmitter 119
1.2.8.6 Low Pin Count (LPC) 120
1.2.8.7 Serial Peripheral Interface (SPI) 120
1.2.9 Package 120
1.2.10 Testability 120
1.3 Terminology 121
1.4 Related Documents 127

Volume 2: Functional 130

2 Multi-Core Intel Atom® Processors **131**
2.1 Introduction 131
2.2 Features 132
2.2.1 Goldmont New Technologies and ISA Extensions 133
2.2.2 Intel® Virtualization Technology 134
2.2.3 Intel® VT-x Objectives 134
2.2.4 Intel® VT-x Features 135
2.2.5 Security and Cryptography Technologies 136
2.2.5.1 Intel® Advanced Encryption Standard New Instructions (Intel® AES-NI) 136
2.2.5.2 Intel® Secure Hash Algorithm Extensions (Intel® SHA Extensions) 137
2.2.5.3 PCLMULQDQ Instruction 137
2.2.5.4 Digital Random Number Generator 137
2.2.6 Intel® Turbo Boost Technology 138
2.2.6.1 Intel® Turbo Boost Technology Frequency 138
2.2.7 CPUID Instruction 138
2.2.7.1 CPUID Leaf 0 — Basic CPUID Information 140
2.2.7.2 CPUID Leaf 1 — Version and Feature Information 141
2.2.7.3 CPUID Leaf 2 — Cache and TLB Information 146
2.2.7.4 CPUID Leaf 3— Reserved 146
2.2.7.5 CPUID Leaf 4— Deterministic Cache Parameters 147
2.2.7.6 CPUID Leaf 5— MONITOR/MWAIT 149
2.2.7.7 CPUID Leaf 6— Digital Thermometer and Power Management 150
2.2.7.8 CPUID Leaf 7— Extended feature Flags 151
2.2.7.9 CPUID Leaf 8 — Reserved 153
2.2.7.10 CPUID Leaf 9 — Direct Cache Access (DCA) Information 153

2.2.7.11 CPUID Leaf Ah — Architectural Performance Monitoring 153
2.2.7.12 CPUID Leaf Bh — Extended Topology Enumeration 154
2.2.7.13 CPUID Leaf Ch — Reserved 154
2.2.7.14 CPUID Leaf Dh — Intel® Memory Protection Extensions (Intel® MPX), XSAVE Feature 154
2.2.7.15 CPUID Leaf Eh — Reserved 157
2.2.7.16 CPUID Leaf Fh — Platform and Cache Quality of Service (QoS) 157
2.2.7.17 CPUID Leaf 10h — Platform and Cache QoS Enforcement Enumeration 157
2.2.7.18 CPUID Leaf 11h — Reserved 158
2.2.7.19 CPUID Leaf 12h — Reserved 158
2.2.7.20 CPUID Leaf 13h — Reserved 158
2.2.7.21 CPUID Leaf 14h — Intel® Processor Trace (Intel® PT) Enumeration 159
2.2.7.22 CPUID Leaf 15h — Time Stamp Counter (TSC) and Crystal Clock Ratio 160
2.2.7.23 CPUID Leaves 16h through 7FFFFFFFh — Reserved 161
2.2.7.24 CPUID Leaf 80000000h — Maximum EAX Value for CPUID Instruction 161
2.2.7.25 CPUID Leaf 80000001h — Extended Feature Flags 162
2.2.7.26 CPUID Leaves 80000002h, 80000003h, and 80000004h— Intel Processor Brand String 163
2.2.7.27 CPUID Leaf 80000005h — Reserved 163
2.2.7.28 CPUID Leaf 80000006h — Cache Parameters 163
2.2.7.29 CPUID Leaf 80000007h — Advanced Power Management 164
2.2.7.30 CPUID Leaf 80000008h — Virtual/Physical Address Sizes 164

3 System Address Map 165
3.1 Host Root Space—Memory Space 166
3.1.1 Host Memory Space—Regions and Boundaries 166
3.1.2 Host Memory Space—Relocatable Memory-Mapped I/O 169
3.2 Host Root Space—I/O Space 174
3.2.1 Host I/O Space—Fixed I/O Addresses 175
3.2.2 Host I/O Space—Relocatable I/O Addresses 180
3.3 Host Root Space—PCI Configuration Register Space 182
3.3.1 How to Access Registers in PCI Configuration Space 185
3.4 Host Root Space - Host Sideband Register Access 187
3.4.1 Using SBREG_BAR Method 187
3.4.2 Accessing System Agent Sideband Registers 187
3.5 Key Registers Mentioned in this Chapter 188
3.5.1 Key Registers in Host Configuration Space 188
3.5.2 Key Registers in Host Memory Space 190
3.5.3 Key Registers in Host I/O Space 190

4 Strapping and Configuration 191
4.1 SoC Hard (Pin) Straps 193
4.2 SoC Soft Straps 199
4.3 Fuses Pertaining to the Innovation Engine (IE) 260

5 System Agent and Root Complex 261
5.1 Introduction 261
5.2 Features 262
5.3 Root Complex 262
5.4 Register Map 263
5.4.1 Registers in Configuration Space 264

6 Reliability, Availability and Serviceability (RAS) 265
6.1 SoC RAS Overview 265

6.2 Signal Descriptions 265
6.3 Feature Summary 266
6.4 Architectural Overview 267
6.4.1 Error Classification 267
6.4.2 Error Detection and Reporting Mechanisms 268
6.5 Availability Features 269
6.5.1 System Memory 269
6.5.1.1 Single Bit Error Correction 269
6.5.1.2 DRAM Data Scrubbing 269
6.5.1.3 DRAM Data Scrambling 269
6.5.2 PCI Express Root Ports 270
6.6 Machine Check Architecture (MCA) 271
6.6.1 Machine Check MSR Addresses 272
6.6.2 Enhancements to MCA Error Reporting 274
6.6.2.1 Error Cloaking 274
6.6.2.2 Dual Signaling 274
6.6.2.3 Corrected Machine-Check error Interrupt (CMCI) 275
6.7 Advanced Error Reporting (AER) 276
6.7.1 AER and the PCIe Root Ports and RCEC 276
6.8 Intel® Virtualization Technology (Intel® VT) 277
6.9 Error Injection 277
6.10 SoC UnCore and I/O Error Handling 278
6.11 Hardware Error Classification and System Events 279
6.11.1 Correctable Errors 279
6.11.2 Uncorrectable Errors 280
6.11.2.1 Fatal Errors 280
6.11.2.2 Non-Fatal Errors 280
6.11.3 Software Correctable Errors 280
6.12 SoC UnCore and I/O Error Reporting 281
6.12.1 Reporting Error to an External Device 283
6.12.2 PCI Express INTx and MSI 283
6.13 Overview of SoC Error Registers 284
6.13.1 Local Error Registers 285
6.13.2 SoC Global Error Registers 286
6.13.3 First Error and Next Error Log Registers 287
6.13.4 General Local and Global Error-Register Flow 288
6.13.5 Global System Event Reporting 290
6.13.6 Error Counters 292
6.13.6.1 Error Counter Requirements 292
6.14 Error Reporting Flow — PCI Express Devices/Functions 293
6.14.1 Upstream Flow of Error Signal Messages 294
6.14.2 How a PCIe Device Determines Which Error Message to Send 295
6.14.3 PCIe Endpoint Devices Behind Virtual Root Port Error Handling 297
6.14.4 PCI Express Root Ports 298
6.14.4.1 Unsupported Transactions and Unexpected Completions 298
6.14.4.2 Unconnected Ports 298
6.14.5 Internal Errors — SMBus-Host Controller 298
6.14.6 Local Error Registers 299
6.15 Error Reporting Flow — Legacy PCI Devices/Functions 302
6.15.1 Local Error Registers 302
6.16 Error Reporting Flow — Non-PCI devices 304
6.16.1 Local Error Registers 305
6.16.2 Error Injection Control and Registers — Memory Controller 308
6.17 Error Reporting Flow — I/O Fabric 309
6.17.1 Local Error Registers 309

6.18 SoC Error Handling Summary 309
6.19 Register Map 320
6.19.1 Registers in Configuration Space—GLREG 321
6.19.2 Registers in Configuration Space—RCEC 323

7 Clock Architecture 325
7.1 Signal Descriptions 326
7.2 Feature List 328
7.3 Architectural Overview 329
7.3.1 ISCLK 330
7.3.2 Real-Time Clock 330
7.3.3 PMU SUS Clock 330
7.3.4 Flex Clocks 330
7.3.5 SVID Clock 331
7.3.6 SATA Serial GPIO (SGPIO) Clock 331
7.3.7 EMMC Clock 331
7.3.8 DDR Clocks 331
7.3.9 PCI Express Reference Clocks 331
7.3.10 SPI Clock 331
7.3.11 LPC Clocks 331
7.3.12 LAN I2C Clocks 331
7.3.13 LAN MDC Clock 332
7.3.14 LAN NC-SI Clock 332
7.3.15 SMBus Clocks 332
7.3.16 Debug and DFx Clocks 332
7.3.17 Clocks Generated During the S5 Sleep State 332

8 Interrupts and Events 333
8.1 PCI Interrupts and Routing 333
8.1.1 Interrupt Pin Route Overview 335
8.1.2 PIRQx Register Decode Table 337
8.1.3 Edge- and Level-Triggered Mode 337
8.2 Non-Maskable Interrupt (NMI) 338
8.3 System Management Interrupt (SMI) 338
8.4 System Control Interrupt (SCI) 339
8.5 GPIO and PMC General Purpose Event (GPE) 340
8.6 Message Signaled Interrupt (MSI and MSI-X) 343
8.7 I/O APIC Input Mapping 343
8.8 8259 PIC Input Mapping 345
8.9 Device Interrupt-Generating Capabilities 346

9 Memory Controller 347
9.1 Introduction 347
9.2 Signal Descriptions 348
9.3 Feature List 353
9.4 Memory Controller Power Management Features 354
9.4.1 DRAM Running Average Power Limit (RAPL) 354
9.4.2 Dynamic (HW autonomous) Self-refresh DDR4 354
9.4.3 Unsupported Features and Restrictions 355
9.4.4 DDR4 DIMM Types and Population 356
9.4.4.1 DIMM Population Requirements 357
9.5 Memory Controller RAS Features 358
9.5.1 Data Scrambler 358
9.5.2 Patrol Scrub 358
9.5.3 Demand Scrub 358
9.5.4 Asynchronous DRAM Refresh (ADR) 358

10 Flexible I/O Adapter (FIA) Overview....359
10.1 Signal Descriptions....360
10.2 Feature List....360
10.3 Architectural Overview....361
10.4 USB 3.0 as a Debug Port....363
10.5 Lane Configuration....363
10.5.1 Intel® Management Engine and BIOS Roles in Lane Configuration....363
10.5.2 PCI Express Lane Configuration....365
10.5.3 Configuring PCIe Lane to x1 and SATA Ports....366
10.6 Register Map....367
10.6.1 PCI Configuration and Capabilities....368
10.6.2 Sideband Registers....368
11 PCI Express Root Ports (RP)....369
11.1 Signal Descriptions....371
11.2 Feature List....372
11.3 Architectural Overview....374
11.3.1 PCI Bridge Subsystem Identification Capability....375
11.3.2 Message Signaled Interrupt (MSI) Capability....375
11.3.3 Advanced Error Reporting (AER) Capability....375
11.3.4 PCIe Extended Capability and Other Supported Technology....376
11.3.4.1 Access Control Services (ACS) Capability....376
11.3.4.2 Windows Hardware Error Architecture (WHEA)....376
11.3.4.3 Dynamic Link Width....377
11.3.4.4 Alternative Routing-ID Interpretation (ARI)....377
11.4 Physical Layer....378
11.4.1 PCI Express Speed Support....378
11.4.2 Separate Refclk with Independent SSC Architecture (SRIS)....378
11.4.3 Form Factor Support....378
11.4.4 Configuration of the PCI Express Ports and Link Widths....379
11.4.5 Degraded Mode....380
11.4.5.1 Dynamic Lane Reversal....381
11.4.5.2 Lane Polarity Inversion....381
11.5 Transaction Layer....382
11.5.1 Transaction ID....382
11.5.2 Attributes....383
11.5.3 Traffic Class....384
11.5.4 Completer ID....384
11.5.5 Transaction Ordering....385
11.5.6 PCI Express Port Arbitration....385
11.5.7 Request Splitting....385
11.5.8 Read Prefetching Policies....386
11.5.9 Read Completion Combining....386
11.5.10 Write Combining....386
11.6 Interrupt Support....387
11.6.1 Legacy Interrupt Sharing....387
11.7 Power Management....388
11.7.1 Hardware Controlled Active Power Management....388
11.7.2 PCI-PM 1.2 Support....388
11.7.3 Power Management Event Signaling....389
11.7.4 Beacon and WAKE# Signaling....389
11.7.5 Non-D0 State PM Handling....390
11.7.5.1 Non-D0 Behavior for Transmit (Tx) Transactions....390
11.7.5.2 Non-D0 Behavior for Receive (Rx) Transactions....390
11.7.6 BME Clear State Handling....391

11.7.6.1 BME (=0) Clear State Behavior for Transmit (Tx) Transactions 391
11.7.6.2 BME (=0) Clear State Behavior for Receive (Rx) Transactions 391
11.7.6.3 Internal MSI/Error Messages During Non-D0/BME (clear) 391
11.7.6.4 L1 PM Substates 391
11.8 PCI Express RAS Features 392
11.8.1 End-to-End CRC (ECRC) Support 392
11.8.2 Completion Timeout 392
11.8.3 Data Poisoning 392
11.8.4 Role-based Error Reporting 393
11.9 PCI Express Hot-Plug Surprise 394
11.9.1 PCI Express Hot-Plug Interrupts and Events 394
11.9.1.1 Presence Detect 394
11.9.1.2 SCI/SMI Generation 394
11.10 Register Map 395

12 SATA Controller 396
12.1 Signal Descriptions 397
12.2 Feature List 398
12.3 Architectural Overview 398
12.4 AHCI Operation 399
12.4.1 Staggered Spin Up Support 399
12.4.2 Staggered Spin-up Operation in AHCI Mode 399
12.4.3 Interrupts 400
12.4.3.1 Interaction Between INTx# and MSI/MSI-X 400
12.4.4 Power Management 400
12.4.5 Automatic Transition of Partial to Slumber 400
12.4.6 Enclosure Management and Activity LED 400
12.5 Register Map 401
12.5.1 PCI Configuration and Capabilities 402
12.5.2 Memory-Mapped Registers 404
12.5.3 I/O-Mapped Registers 409

13 LAN Controllers 410
13.1 Signal Descriptions 412
13.2 Supported Modes of Operation 415
13.3 Feature List 417
13.4 Programmers Reference Manual 421
13.5 Architectural Overview 421
13.5.1 PCIe Integrated Endpoint 422
13.5.2 Interconnect Interfaces 423
13.6 Basic Operation 424
13.6.1 Transmit (Tx) Data Flow 424
13.6.2 Receive (Rx) Data Flow 425
13.7 Interconnects 426
13.7.1 Setting Up PCI Device Presence and Non-presence 426
13.7.1.1 LAN Controllers Soft Straps 426
13.7.2 Disabling PCI Functions by BIOS 426
13.7.3 LAN Port Interface 427
13.7.4 Reference Clock Input 428
13.7.5 Pin Straps 428
13.8 Shared SPI Flash for Use with LAN0 and LAN1 429
13.8.1 Shared SPI Flash Starter Images 429
13.8.2 Shared SPI Flash Map Related to LAN0 and LAN1 429
13.8.3 Unique MAC Address 429

13.8.4 VLAN Support 430
13.9 MMIO and Software Interface 430
13.10 Host Primary Interface 431
13.10.1 Host Interface Architecture, Transaction and Link Layer Properties 431
13.10.2 PCIe Transaction Layer 432
13.10.2.1 Transaction Types Accepted by the LAN Controllers 432
13.10.2.2 Transaction Types Initiated by the LAN Controllers 434
13.10.2.3 Messages 436
13.10.2.4 Transaction Attributes 436
13.10.2.5 Ordering Rules 437
13.10.3 Error Events and Error Reporting 439
13.10.3.1 General Description 439
13.10.3.2 Error Events 440
13.10.3.3 Completion Timeout Mechanism 441
13.10.3.4 Error Forwarding (TLP Poisoning) 441
13.10.3.5 Completion With Unsuccessful Completion Status 441
13.10.3.6 Blocking on Upper Address 442
13.10.3.7 Proprietary Error Reporting 442
13.11 Management Interfaces 444
13.11.1 SMBus 444
13.11.1.1 Channel Behavior 444
13.11.2 NC-SI Transactions 444
13.11.3 MCTP (over SMBus) 444
13.12 Sideband Interface (NC-SI) 445
13.12.1 Electrical Characteristics 445
13.13 Shared SPI Flash 445
13.13.1 General Overview 445
13.13.2 Shared SPI Flash Protection 446
13.13.3 Shadow RAM 447
13.13.3.1 Shadow RAM Update Flow 448
13.13.4 Shared SPI Flash Clients and Interfaces 449
13.13.5 Memory Mapped Host Interface 450
13.13.6 Shared SPI Flash Access Contention 451
13.13.6.1 Flash Deadlock Avoidance 452
13.13.7 Signature Field 453
13.13.8 VPD Support 453
13.13.8.1 VPD Access Flows 455
13.13.8.2 VPD Area Update Flows 455
13.13.8.3 Shared SPI Flash Update Read, Write, and Erase Sequences 455
13.13.8.4 Software Flow to the Bit Banging Interface 455
13.13.8.5 Erase Flow Using the FLA Register 456
13.13.8.6 Software Access flow to Shadow RAM 456
13.13.8.7 Flash Access Flow via the Memory Mapped Interface 457
13.13.8.8 Software Flash/Shadow RAM Program Flow 457
13.13.8.9 Software Flash Read Flow via the Flash-mode Interface 457
13.13.9 Extended Shared SPI Flash Update Flows 458
13.13.9.1 Flow for Updating Secured Modules 458
13.14 Configurable I/O Pins — Software-Definable Pins (SDPs) 460
13.15 LEDs 462
13.16 Network Management Interface (MDIO or I2C) 464
13.16.1 I^2C or MDIO Selection 464
13.16.2 Recommended Networking Topologies 465
13.16.3 Management Data I/O Interface (MDIO) 467
13.16.3.1 MDIO Timing Relationship to MDC 469
13.16.3.2 IEEE802.3 Clause 22 and Clause 45 Differences 470
13.16.3.3 MDIO Management Frame Structure 470

13.16.3.4 MDIO Direct Access 473
13.16.4 I2C 474
13.16.4.1 Hardware Based I2C Access 474
13.16.4.2 Bit Bang Based I2C Access 475
13.16.4.3 Supported Commands 475
13.17 Network Interface 477
13.17.1 Companion Integrated PHY Register Access 477
13.17.1.1 PHY Register Addressing 477
13.17.1.2 PHY Indirect Read Operation 478
13.17.1.3 PHY Indirect Write Operation 478
13.17.2 Ethernet Flow Control (FC) 479
13.17.2.1 MAC Control Frames and Reception of Flow Control Packets 480
13.17.2.2 PAUSE and MAC Control Frames Forwarding 484
13.17.2.3 Transmitting PAUSE Frames 485
13.17.3 Inter Packet Gap (IPG) Control and Pacing 490
13.18 Physical Functions (PF), Virtual Functions (VF) and ARI (Alternative RID Interpretation) 491
13.19 Register Map 492

14 USB Combo Controller 493
14.1 Signal Descriptions 494
14.2 Feature List 495
14.2.1 USB 3.0 495
14.2.2 USB 2.0 495
14.2.3 xHCI Interface 497
14.3 Architectural Overview 498
14.3.1 xHCI Interface Architecture 501
14.4 xHCI Data Structures 503
14.5 Command Interface 503
14.6 Root Hub Management 504
14.7 Operational Model 504
14.8 Supported Transaction Types 505
14.9 Reset Requirements 505
14.10 USB Power Management – Link States 506
14.11 Error Condition and Handling 507
14.12 Debug Capability (DbC) 507
14.13 Register Map 508
14.13.1 PCI Configuration and Capabilities 509
14.13.2 Memory-Mapped Registers 511

15 Platform Control Cluster (PCC) 522
15.1 Signal Descriptions 523
15.2 Architectural Overview 523
15.2.1 Integrated PCI Devices 523
15.2.2 Integrated PCI Device 31 Functions 524
15.2.3 Legacy Controller Group 524
15.2.3.1 Interrupt Timer Sub System (ITSS) 524

16 Power Management Controller (PMC) 525
16.1 Signal Descriptions 526
16.2 Feature List 528
16.3 Architectural Overview 528
16.4 System Power States 528
16.5 SoC Internal Power Control 528
16.5.1 Internal Power Switching 529
16.6 Total Cost of Ownership (TCO) 530

16.6.1 Detecting a System Lockup 531
16.6.2 Handling an Intruder 531
16.6.3 SMM-to-OS and OS-to-SMM Calls 532
16.7 SMI#/SCI Generation 532
16.7.1 PCI Express* SCI 534
16.8 C States 534
16.9 Dynamic LPC 24-MHz Clock Control 534
16.10 Sleep States 535
16.10.1 Initiating State Changes when in the G0 (S0) Working State 535
16.10.2 Initiating State Changes when in the G3 Mechanical-Off State 537
16.10.3 Returning to the S0 State when in the G2 (S5) Soft-Off State 537
16.10.3.1 LAN Power Management Wakeup 539
16.10.3.2 Other Internal Power Management Events 540
16.10.4 Reset Triggers That Generate a State Change 541
16.11 System Power Supplies, Planes, and Signals 542
16.11.1 Platform Power Plane Control with PMU_SLP_S3_N and PMU_SLP_S45_N 542
16.11.2 COREPWROK SoC Input Signal 542
16.11.3 SUSPWRDNACK SoC Output Signal 542
16.12 Legacy Power Management Theory of Operation 543
16.13 Reset Behavior 543
16.13.1 Reset Request Conditions 544
16.14 Interaction with the Innovative Engine (IE) 546
16.15 Asynchronous DRAM Refresh (ADR) 547
16.15.1 Configuring ADR 548
16.15.1.1 Qualified Internal Events 549
16.15.2 Configuring the Copy-to-Flash Extension 550
16.15.3 NVDIMM Copy-to-Flash 550
16.15.4 ADR Sequence of Events 551
16.15.5 BIOS after Successful ADR 552
16.16 Register Map 553
16.16.1 PCI Configuration and Capabilities 554
16.16.2 Memory-Mapped Registers 554
16.16.3 I/O-Mapped Registers 555
16.16.4 Sideband Registers 556

17 Embedded Multi-Media Card (eMMC) 557
17.1 Signal Descriptions 558
17.2 Feature List 558
17.3 Architectural Overview 558
17.3.1 eMMC Mass Storage Command and Data Flows 558
17.3.2 PCI Mode and ACPI Mode 559
17.4 Address Map 559
17.5 Register Map 560
17.5.1 PCI Configuration and Capabilities 561
17.5.2 Memory-Mapped Registers 562
17.5.3 I/O-Mapped Registers 564

18 High-Speed UART Controller 565
18.1 Signal Descriptions 566
18.2 Feature List 568
18.2.1 UART Features 568
18.2.2 DMA Features 568
18.3 Architectural Overview 569
18.3.1 UART Hiding and Locking 570
18.3.2 Legacy Mode 571

18.3.3 Enhanced Mode 571
18.3.4 UART Function 572
18.3.5 FIFO Interrupt Mode Operation 573
18.3.5.1 Receive Interrupt 573
18.3.5.2 Timeout Interrupt 573
18.3.5.3 Transmit Interrupt 573
18.3.6 FIFO Polled Mode Operation 574
18.3.7 Auto-flow Control Operation 574
18.3.8 Loopback Operation 575
18.3.9 Auto-Baud Detection 575
18.3.10 UART Clocking 576
18.3.11 UART Baud Rate Generation 576
18.3.12 I/O and Memory Base Access Space 577
18.3.13 Interrupt 577
18.3.14 Memory Address MAP 577
18.3.15 DMA 578
18.3.15.1 Channel Arbitration 579
18.3.15.2 Descriptor Arbitration 580
18.3.16 MSI Generation 581
18.4 UART Programming Recommendation 582
18.4.1 Setup Access Space 582
18.4.2 Setup Interrupt 582
18.4.3 Space Enable 582
18.4.4 DMA Programming 582
18.4.5 DMA Descriptor Use/Reuse 583
18.4.6 Programming Optimization 583
18.4.6.1 Optimization Descriptor Programming Activities During DMA 583
18.4.6.2 Optimization Access Time By UART During DMA 583
18.4.6.3 Optimization Interrupt Handling 584
18.5 Register Map 587
18.5.1 PCI Configuration and Capabilities Registers 588
18.5.2 Memory Mapped Registers, BAR1 (Memory Base Address Register, MEMBA) 589
18.5.2.1 UART Memory Mapped Registers 589
18.5.3 DMA Channel Registers 590
18.5.4 I/O Mapped Registers, BAR 0 (I/O Base Address Register, IOBA) 591
18.5.4.1 UART I/O Mapped Registers 591

19 Serial Peripheral Interface (SPI) 592
19.1 Signal Descriptions 593
19.2 Feature List 593
19.3 Architectural Overview 594
19.3.1 Operation Mode 595
19.3.1.1 Descriptor Mode 595
19.3.1.2 Security 596
19.3.1.3 SPI Flash Access 596
19.3.1.4 Flash Component Requirements 597
19.3.2 Flash Regions 598
19.3.2.1 Flash Component Boundary 600
19.3.2.2 Flash Descriptor Region 0 600
19.4 Flash Access 602
19.4.1 Direct Access 602
19.4.1.1 BIOS Direct Read in Descriptor Mode 603
19.4.1.2 Chip Select and Flash Linear Address (FLA) 604
19.4.2 Programmed Register Access 604
19.5 Flash Security and Protection 605

19.5.1 Flash Range Write and Read Protection 605
19.5.2 SMI Based Global Write Protection 606
19.5.3 Flash Security Override Strap 606
19.5.4 Illegal Instructions 606
19.5.5 Error Status Table 607
19.5.6 Region Checks 607
19.6 SMI Generation 608
19.6.1 Synchronous SMI 608
19.6.2 Asynchronous SMI 608
19.7 Hardware vs. Software Sequencing 608
19.7.1 Hardware Sequencing 609
19.7.2 Software Sequencing 610
19.8 Serial Flash Device Compatibility Requirements 612
19.8.1 BIOS SPI Flash Requirements 612
19.9 SPI Flash Interface 613
19.9.1 Single-Input, Dual-Output Fast Read 613
19.9.2 Dual-I/O Fast Read 614
19.9.3 Quad-Output Fast Read 615
19.9.4 Quad-I/O Fast Read 616
19.9.5 JEDEC ID 616
19.10 SPI Support for Trusted Platform Module (TPM) 617
19.10.1 TPM Protocol on SPI 618
19.10.2 TPM Flow Control on SPI 620
19.11 Register Map 622
19.11.1 PCI Configuration and Capabilities 623
19.11.2 Memory Mapped Registers 624

20 Low Pin Count (LPC) Controller 626
20.1 Signal Descriptions 627
20.2 Feature List 628
20.3 Architectural Overview 628
20.3.1 LPC Cycle Types 628
20.3.2 Memory Cycle 628
20.3.3 I/O Cycle 628
20.3.4 DMA Cycle 628
20.3.5 Bus Master Cycle Notes 628
20.3.6 LFRAME# Usage 628
20.3.7 LPC PD# Protocol 629
20.3.8 LPC Interface Decoders 629
20.3.9 SERR# Generation 629
20.3.10 Dynamic LPC Clock Control 629
20.3.10.1 Verifying if Safe to Stop the LPC Clock 629
20.3.10.2 Conditions for Maintaining the LPC Clock 629
20.3.10.3 Conditions for Stopping the LPC Clock 630
20.3.10.4 Conditions for Restarting the LPC Clock 630
20.4 Register Map 631
20.4.1 PCI Configuration and Capabilities 632
20.4.2 Fixed I/O Address Transactions 633
20.4.3 Configurable I/O Address Transactions 635
20.4.4 Memory and BIOS Address Transactions 636
20.4.4.1 BIOS Write Protect and Top Swap Range 637
20.4.4.2 BIOS Boot Decode Claiming Agent 637

21 PIC and I/O APIC Controllers 638
21.1 Signal Descriptions 639
21.2 Programmable Interrupt Controller (PIC) 639

21.2.1 Special Internal Circuitry 639
21.2.2 Generating Interrupts 639
21.2.3 Acknowledging Interrupts 640
21.2.4 Hardware/Software Interrupt Sequence 640
21.2.5 Initialization Command Words (ICWx) 641
21.2.5.1 ICW1 641
21.2.5.2 ICW2 641
21.2.5.3 ICW3 641
21.2.5.4 ICW4 641
21.2.6 Operation Command Words (OCW) 642
21.2.7 Fully-Nested Mode 642
21.2.8 Special Fully-Nested Mode 642
21.2.9 Automatic Rotation Mode (Equal Priority Devices) 642
21.2.10 Specific Rotation Mode (Specific Priority) 643
21.2.11 Poll Mode 643
21.2.12 Edge- and Level-Triggered Mode 643
21.2.13 End of Interrupt (EOI) Operations 644
21.2.13.1 Normal End of Interrupt (EOI) Mode 644
21.2.13.2 Automatic End of Interrupt (AEOI) Mode 644
21.2.14 Masking Interrupts 645
21.2.14.1 Masking on an Individual Interrupt Request 645
21.2.14.2 Special Mask Mode 645
21.3 I/O Advanced Programmable Interrupt Controller (IOxAPIC) 646
21.3.1 Interrupt Redirection Table 646
21.3.2 Accessing the Redirection Table 646
21.3.3 IOxAPIC Interrupts to the Local APICs 647
21.3.4 Interrupt Delivery Modes 649
21.3.5 Determining Safe Message Delivery Time 649
21.3.6 End Of Interrupt (EOI) Register 649
21.4 Register Map 650
21.4.1 PCI Configuration and Capabilities 651
21.4.2 Memory-Mapped Registers 652
21.4.3 I/O-Mapped Registers 653

22 Primary to Side Band (P2SB) Bridge 654
22.1 Signal Descriptions 655
22.2 Feature List 655
22.3 Architectural Overview 655
22.4 Register Map 656
22.4.1 PCI Configuration and Capabilities 657
22.4.2 Memory-Mapped Registers 658

23 Programmable Interval Timer (PIT) 659
23.1 Signal Descriptions 660
23.2 Feature List 660
23.3 Architectural Overview 660
23.3.1 Counter 0, System Timer 661
23.3.2 Counter 2 661
23.4 Counter Mode Definitions 662
23.5 Timer Programming 662
23.5.1 Writing to the Interval Timer 662
23.5.2 Reading from the Interval Timer 663
23.5.2.1 Simple Read 663
23.5.2.2 Counter Latch Command 663
23.5.2.3 Read Back Command 664
23.6 Register Map 665

23.6.1 I/O-Mapped Registers 666

24 Real Time Clock (RTC) 667
24.1 Signal Descriptions 668
24.2 Feature List 669
24.3 Architectural Overview 669
24.4 I/O Registers 670
24.4.1 Alternate-Access Mode 671
24.5 Update Cycles 672
24.6 Interrupts 672
24.7 Lockable RAM Ranges 672
24.8 Month and Year Alarms 672
24.9 Register Map 673
24.9.1 PCI Configuration and Capabilities 674
24.9.2 Memory-Mapped Registers 674
24.9.3 I/O-Mapped Registers 674

25 High Precision Event Timer (HPET) 675
25.1 Signal Descriptions 675
25.2 Feature List 675
25.3 Architectural Overview 676
25.3.1 Timer Accuracy 677
25.3.2 Timer Off-Load 677
25.3.3 Interrupt Mapping 678
25.3.3.1 Mapping Option #1 (Legacy Replacement Option) 678
25.3.3.2 Mapping Option #2 (Standard Option) 679
25.3.3.3 Mapping Option #3 (Processor Message Option) 679
25.3.4 Periodic Versus Non-Periodic Modes 680
25.3.4.1 Non-Periodic (One-Shot) Mode 680
25.3.4.2 Periodic Mode 680
25.3.5 Enabling the Timers 681
25.3.6 Interrupt Levels 681
25.3.7 Handling Interrupts 681
25.3.8 Issues Related to 64-Bit Timers with 32-Bit Processors 681
25.4 Register Map 682
25.4.1 Memory-Mapped Registers 683

26 Customer General-Purpose I/O (GPIO) 685
26.1 GPIO Ball and Signal Names 686
26.2 Pad Description 691
26.3 Signal Configuration Overview 692
26.3.1 Pad Ownership 693
26.3.2 Pad Multiplex Function 694
26.3.3 Pad Internal Pull-up / Pull-down Configure 694
26.3.4 Pad Configuration Logical Control Summary 695
26.3.5 Non-Maskable Interrupt (NMI) 696
26.3.6 System Management Interrupt (SMI) 696
26.3.7 System Control Interrupt (SCI)/General Purpose Event (GPE) 696
26.3.8 GPIO to IOxAPIC 697
26.3.9 Legacy Interrupt Request (IRQ) 697
26.3.10 Pad Level/Edge Sensitive Detect Enable 697
26.4 Registers Lock Down 698
26.5 MMIO Address Access 698

27 System Management Bus (SMBus) Controller - Overview 706
27.1 General Architecture 707
27.2 Feature List 709

28 SMBus Controller - Legacy 711
28.1 Signal Descriptions 712
28.2 General Architecture 713
28.3 Legacy SMBus Controller Operation 714
28.3.1 Supported SMBus Protocols 714
28.3.2 SMBus CRC Generation and Checking 715
28.4 Protocols as an SMBus Master 716
28.4.1 Quick Command 716
28.4.2 Send Byte and Receive Byte Commands 716
28.4.3 Write Byte and Write Word Commands 716
28.4.4 Read Byte and Read Word Commands 717
28.4.5 Process Call Command 717
28.4.6 Block Read and Block Write Commands 718
28.4.7 Block Write-Block Read Process Call Command 719
28.4.8 SMBus Host Notify Command 719
28.5 Protocols and Commands as the ARP Master 720
28.5.1 ARP Enumeration and the Notify ARP Master Command 720
28.6 I^2C Read Command 721
28.7 Bus Arbitration as an SMBus Master 722
28.7.1 SMBCLK Signal Stretching by an SMBus Slave 722
28.7.2 SMBus Timeout 722
28.8 Interrupts and SMI 722
28.9 Optional SMBALERT# Signal 724
28.10 Register Map 725
28.10.1 Registers in the Configuration Space 726
28.10.2 Registers in the Memory Space 727
28.10.3 Registers in the I/O Space 728

29 SMBus Controller - Host 729
29.1 Signal Descriptions 730
29.2 Features 730
29.3 Architectural Overview 731
29.4 Controller Characteristics and Operation 733
29.4.1 SMBus Behavior on PCIe Reset 733
29.4.2 Addressing and Configuration 733
29.4.2.1 ARP Nomenclature 734
29.4.2.2 Unique Device Identifier (UDID) Format 735
29.4.2.3 ARP Slave Behavior 736
29.4.2.4 ARP Master Behavior 743
29.4.2.5 ARP Initialization Flow 746
29.4.3 SMT System Usage Models 748
29.4.4 SMT Security Requirements 748
29.4.5 SMT Timing Modes 748
29.4.6 SMT as Master 749
29.4.6.1 Hardware Buffering for Master Support 749
29.4.6.2 Master Descriptor 750
29.4.6.3 Master Descriptor Usage 754
29.4.6.4 Master Transactions Flow 758
29.4.6.5 Clearing of the Start Bit 761
29.4.6.6 Master Retry Flow 762
29.4.6.7 Write Disabling to DIMM SPD EEPROM Addresses 764
29.4.7 SMT as Target 765
29.4.7.1 Hardware Buffering for Target Support 765
29.4.7.2 Target Descriptor 766
29.4.7.3 Target Transaction Status 770
29.4.7.4 Target Memory Buffer Hardware-Firmware Flow 772

29.4.7.5 Target Flow 775
29.4.8 Dynamic SMT Policy Update 783
29.4.8.1 Master Policy 783
29.4.8.2 Target Policy 783
29.5 Interrupts 785
29.5.1 Master Interrupts 786
29.5.2 Target Interrupts 787
29.5.3 Error Interrupts 788
29.5.4 Interrupt Cause Logging 789
29.6 SMT RAS Architecture 790
29.6.1 Soft Reset (DEVCTL.IFLR and GCTRL.SRST) 790
29.6.2 Target Reset (GCTRL.TRST) 791
29.7 MCTP Over SMBus Packet Header Format 792
29.8 Register Map 794

30 SMBus Controller - Platform Environment Control Interface 795

30.1 Signal Descriptions 796
30.2 PECI over SMBus Features 796
30.3 SMBus Supported Transactions 797
30.4 SMBus Block Read/Write Transaction Formats 798
30.5 SMBus Commands 798
30.6 PECI Over SMBus 799
30.6.1 PECI Message Header in SMBus 799
30.6.1.1 Target Address Field 799
30.6.1.2 Write Length Field 799
30.6.1.3 Read Length Field 799
30.6.1.4 Command Byte 799
30.6.2 PECI Write-Read Protocol 800
30.6.2.1 PECI Proxy Command Format 801
30.6.2.2 PECI Proxy Read Command 802
30.6.3 PECI Proxy Command Handling Procedure 804
30.6.4 PECI Proxy Command Trigger 805
30.6.4.1 Unsupported PECI Command 805
30.6.4.2 Illegally Formatted Command 805
30.7 PECI Proxy Commands 806
30.7.1 Ping() 807
30.7.2 GetDIB() 809
30.7.2.1 PECI Device Info Field 811
30.7.2.2 PECI Revision Number 811
30.7.3 GetTemp() 812
30.7.4 RdPkgConfig() 814
30.7.5 WrPkgConfig() 816
30.7.6 RdIAMSR() 818
30.7.6.1 Processor ID Enumeration 818
30.7.7 RdPCIConfigLocal() 821
30.7.8 WrPCILocalConfig() 824
30.7.9 RdEndPointConfig() 827
30.7.10 WrEndPointConfig() 829
30.7.11 MCA Access via RdEndPointConfig() 831
30.7.12 Endpoints supporting Rd/WrPCILocalConfig 832
30.7.13 Endpoints supporting Rd/WrEndPointConfig 833
30.8 DRAM Thermal Capabilities 834
30.8.1 DRAM Rank Temperature Write (Index = 18) 836
30.8.2 DIMM Temperature Read (Index = 14) 836
30.8.3 DRAM Channel Temperature Read (Index = 22) 837
30.8.4 DRAM Accumulated Energy Read (Index = 4) 837

30.8.5 DRAM Power Info Read (Index = 35/36) 838
30.8.6 DRAM Power Limit Data Read/Write (Index = 34) 839
30.8.7 DRAM Power Limit Performance Status Read 840
30.9 CPU Thermal and Power Optimization Capabilities 841
30.9.1 Package Identifier Read (Index = 0) 848
30.9.1.1 CPU ID Information 848
30.9.1.2 Platform ID 848
30.9.1.3 PCU Device ID 849
30.9.1.4 Maximum Thread ID 849
30.9.1.5 CPU Microcode Update Revision 849
30.9.1.6 MCA Error Source Log 850
30.9.2 Package Power SKU Unit Read (Index = 30) 850
30.9.3 Package Power SKU Read (Index = 28 and 29) 851
30.9.4 Accumulated Run Time Read (Index = 31) 852
30.9.5 Package Temperature Read (Index = 2) 852
30.9.6 Per Core DTS Temperature Read (Index = 9) 852
30.9.7 Temperature Target Read (Index = 16) 853
30.9.8 Package Thermal Status Read / Clear (Index = 20) 853
30.9.9 Thermally Constrained Time Read (Index = 32) 854
30.9.10 Current Limit Read (Index = 17) 854
30.9.11 Accumulated Energy Status Read (Index = 3) 854
30.9.12 Package Power Limits For Multiple Turbo Modes (Index = 26 and 27) 855
30.9.13 Package Power Limit Performance Status Read (Index = 8) 856
30.9.14 Efficient Performance Indicator Read (Index = 6) 856
30.9.15 ACPI P-T Notify Write and Read (Index = 33) 857
30.9.16 Package PL3 (Index = 53) 858
30.9.17 Read Ratio Constraints (Index = 49) 859
30.9.18 Read Ratio Limit 860
30.9.19 Write Ratio Limit 860
30.10 Crash Dump 861
30.10.1 GetCrashDumpCapabilities (Index=51) 861
30.10.2 GetCrashDumpFrame (Index = 52) 862
30.10.3 UnCore and PM Crash Dump Registers 863
30.10.4 Core Crash Dump 866
30.10.4.1 Overview 866
30.10.4.2 PECI Command Structure 866
30.10.4.3 Flow 868
30.10.4.4 Core Crash Details 869
30.11 DTS Temperature Data 871
30.11.1 PECI Device Temp Data 871
30.11.2 Interpretation 871
30.11.3 Temperature Filtering 872
30.11.4 Reserved Values 872

31 Intel® QuickAssist Technology (Intel® QAT) 873

31.1 Signal Descriptions 874
31.2 Features 874
31.3 Usage Model 875
31.3.1 Ring Controller 876
31.3.2 Single-Root I/O Virtualization (SR-IOV) 876
31.3.2.1 I/O Virtualization Models 876
31.3.2.2 Sharing via Virtual Machine Monitor (VMM) 876
31.3.2.3 Direct Assignment of EP with SR-IOV 877
31.3.3 Ring Bundle Mapping 878
31.3.3.1 VF Interrupts 878

31.3.4 PCIe Endpoint (EP) Function 879
31.3.4.1 Transmit Interface (TI) 879
31.3.4.2 Receive Interface (RI) 879
31.3.4.3 PCIe EP Functions 880
31.3.4.4 EP Function Mapping 880
31.3.4.5 EP Mapping of BARs to MMIO 881
31.3.4.6 Alternative Routing-ID Interpretation (ARI) 881
31.3.5 Interrupts 882
31.3.5.1 INTx 882
31.3.5.2 Message Signaled Interrupt (MSI) 882
31.3.5.3 MSI-X 882
31.3.6 EP Errors 883
31.3.6.1 PCIe Error Management 883
31.3.6.2 PCIe Error Reporting Mechanisms 883
31.3.6.3 PCIe Error Handling and Signaling 884
31.3.6.4 PCIe Error Sources 884
31.3.7 Device-Specific Error Management 889
31.3.7.1 Memory Error Poisoning 889
31.3.8 Error Handling with SR-IOV 889
31.4 PCI Configuration Space Map 890

32 SoC Voltage Rails 891
32.1 SoC Voltage (And Related Signals) Descriptions 892

33 Resets and Voltage Sequencing 895
33.1 Signal Descriptions 895
33.2 Architectural Overview 897
33.3 Cold Boot: From G3 To G0.S0 898
33.4 Shutdown: From G0.S0 To G3 900
33.5 Deep Sleep: From G0.S0 To G1.S4 902
33.6 Deep Sleep Wake: From G1.S4 To G0.S0 902
33.7 Soft Off: From G0.S0 To G2.S5 902
33.8 Soft Off Wake: From G2.S5 To G0.S0 902
33.9 Power Failure: From Gx.Sx To G3 902
33.10 Special Considerations for Platform Voltages 902

34 Power Management 903
34.1 Signal Descriptions 903
34.2 Overview 904
34.3 Power Management Features 905
34.3.1 Asynchronous DRAM Refresh (ADR) 905
34.4 Power Wells 906
34.4.1 Core Power Well 906
34.4.2 SUS Power Well 906
34.4.3 RTC Power Well 906
34.5 Supply Voltage Rails 907
34.6 Serial Voltage Identification (sVID) Controller 908
34.6.1 SVID VR Requirements 908
34.6.1.1 sVID Commands 909
34.7 Core Power Management Overview 910
34.8 System Global Power States 911
34.8.1 Idle Power Optimizations 912
34.9 Processor Power States - C-States 913
34.10 Performance States 915
34.10.1 Processor Performance States - P-States 915
34.10.1.1 Frequency/Voltage Scaling 915
34.10.2 Software P-State Requests 915

34.11 Power Management Technologies 916
34.11.1 Intel® Turbo Boost Technology 916
34.11.2 Voltage Regulator Constraints 917
34.11.3 Thermal Design Power Constraints 917
34.11.4 FAST PROCHOT 917
34.11.5 Running Average Power Limiting (RAPL) 918
34.11.6 Always-On Timers (AONT) 918
34.11.7 I/O Device Controller Enable/Disable 918

35 Thermal Management 919
35.1 Signal Descriptions 919
35.2 Feature Summary 920
35.3 Registers with Multiple Access Methods 921
35.4 Thermal Management (TM) 921
35.4.1 Digital Thermal Sensor (DTS) 922
35.4.2 Fan Speed Control (FSC) 923
35.4.3 PROCHOT_N Signal Pin 924
35.4.4 Thermal Throttling 926
35.4.4.1 Throttle Threshold Temperature 926
35.4.4.2 Core Frequency/Voltage Reduction (Intel® Thermal Monitor 2) 927
35.4.4.3 Clock Modulation (Intel® Thermal Monitor 1) 927
35.4.4.4 Software-Controlled Clock Modulation 928
35.4.5 THERMTRIP_N 928
35.4.6 Thermal Status and Interrupts 929
35.4.6.1 Thermal Status and Interrupts — Processor 929
35.4.6.2 Thermal Status and Interrupts — SoC Package 932
35.5 Memory Thermal Management (MTM) 934
35.5.1 Thermal Throttling 934
35.5.1.1 Open Loop Thermal Throttling (OLTT) 934
35.5.1.2 Close Loop Thermal Throttling (CLTT) 935
35.5.1.3 CLTT Throttle Levels 935
35.5.1.4 CLTT Temperature Threshold Values 936
35.5.1.5 Legacy SMBus Used for Accessing Information for CLTT 937
35.5.1.6 PECI SMBus Used for Accessing Information for CLTT 937
35.5.2 MEM_THERMTRIP 938
35.5.3 Thermal Status and Interrupts 938
35.6 Run Average Power Limit (RAPL) 939
35.6.1 RAPL — SoC Package 940
35.6.2 RAPL — DRAM 944
35.7 Inverse Temperature Dependence (ITD) 945
35.8 Platform Voltage Regulator Thermal Alert 945
35.9 Model-Specific Registers (MSR) 946

36 System Management 947
36.1 Signal Descriptions 948
36.2 Intel® ME and Intel Server Platform Services Firmware 949
36.2.1 Key Properties of Intel® ME 949
36.2.2 Intel® ME Requirements 949
36.3 Register Map 950
36.3.1 Host Root Space - Intel® ME HECI1 951
36.3.1.1 PCI Configuration and Capabilities 951
36.3.1.2 Memory-Mapped Registers 953
36.3.1.3 I/O-Mapped Registers 953
36.3.1.4 Sideband Registers 953
36.3.2 Host Root Space - Intel® ME HECI2 954
36.3.2.1 PCI Configuration and Capabilities 954

36.3.2.2 Memory-Mapped Registers 955
36.3.2.3 I/O-Mapped Registers 955
36.3.2.4 Sideband Registers 955
36.3.3 Host Root Space - Intel® ME IDER 956
36.3.3.1 PCI Configuration and Capabilities 956
36.3.3.2 Memory-Mapped Registers 956
36.3.3.3 I/O-Mapped Registers 957
36.3.3.4 Sideband Registers 958
36.3.4 Host Root Space - Intel® ME HECI3 959
36.3.4.1 PCI Configuration and Capabilities 959
36.3.4.2 Memory-Mapped Registers 960
36.3.4.3 I/O-Mapped Registers 960
36.3.4.4 Sideband Registers 960
36.3.5 Host Root Space - Intel® ME KT 961
36.3.5.1 PCI Configuration and Capabilities 961
36.3.5.2 Memory-Mapped Registers 962
36.3.5.3 I/O-Mapped Registers 963
36.3.5.4 Sideband Registers 963

37 Innovation Engine 964
37.1 Feature Summary 966
37.2 Sample IE Usages 967
37.3 Architectural Overview 968
37.4 Inter-Processor Communication (IPC) 971
37.4.1 IE Root Space Devices 971
37.4.1.1 PECI 971
37.4.1.2 SMBus Message Transport (SMT) 971
37.4.1.3 UART 971
37.5 Register Map 972
37.5.1 Host Root Space - IE HECI1 973
37.5.1.1 PCI Configuration and Capabilities 973
37.5.1.2 Memory-Mapped Registers 975
37.5.1.3 I/O-Mapped Registers 975
37.5.1.4 Sideband Registers 975
37.5.2 Host Root Space - IE HECI2 976
37.5.2.1 PCI Configuration and Capabilities 976
37.5.2.2 Memory-Mapped Registers 977
37.5.2.3 I/O-Mapped Registers 977
37.5.2.4 Sideband Registers 977
37.5.3 Host Root Space - IE IDER 978
37.5.3.1 PCI Configuration and Capabilities 978
37.5.3.2 Memory-Mapped Registers 979
37.5.3.3 I/O-Mapped Registers 979
37.5.3.4 Sideband Registers 980
37.5.4 Host Root Space - IE HECI3 981
37.5.4.1 PCI Configuration and Capabilities 981
37.5.4.2 Memory-Mapped Registers 982
37.5.4.3 I/O-Mapped Registers 982
37.5.4.4 Sideband Registers 982
37.5.5 Host Root Space - IE KT 983
37.5.5.1 PCI Configuration and Capabilities 983
37.5.5.2 Memory-Mapped Registers 984
37.5.5.3 I/O-Mapped Registers 984
37.5.5.4 Sideband Registers 984

38 JTAG and Debug Ports 985
38.1 Signal Descriptions 986
38.2 Feature List 987

38.3 Signals after Reset 987
38.4 Intel® Direct Connect Interface (Intel® DCI) 988
38.4.1 Debug Capability (DbC) 988
38.4.2 Intel® DCI-OOB (Out of Band) 988
38.5 Intel® Trace Hub 989
38.6 On-Board Debug Port Connector 989

Volume 3: Electrical, Mechanical, and Thermal 990

39 Signal Pin Names and Signal MUXing 991
39.1 Directory of Signal Names and Pin Names 993
39.1.1 Reserved (RSVD_xxx) Pins 1026
39.2 Directory of Signals that Share the HSIO Pins 1028
39.3 Directory of Voltage Supply and Sense Pin Names 1029
39.4 Directory of Rotation-Detect Pins 1032
39.5 Directory of All Signal and Voltage Pins - Sorted by Pin Number 1033

40 Signal Electrical and Timing Characteristics 1044
40.1 DDR Memory Interface 1044
40.1.1 DDR4 1044
40.1.1.1 Deviations From The DDR4 Standard 1044
40.1.1.2 Supplementary DDR4 Signals Not Covered By The DDR4 Standard 1044
40.2 PCI Express Root Port Interface 1045
40.2.1 Deviations From The PCI Express 3.0 Standard 1045
40.2.2 Supplementary PCI Express Signals Not Covered By The PCI Express 3.0 Standard 1045
40.3 SATA Interface 1046
40.3.1 Deviations From The SATA 3.1 Standard 1046
40.3.2 Supplementary SATA Signals Not Covered By The SATA 3.1 Standard 1046
40.4 USB Interface 1047
40.4.1 Deviations From The USB 3.0 Standard 1047
40.4.2 Supplementary USB Signals Not Covered By The USB 3.0 Standard 1047
40.4.3 USB 2.0 Standard 1047
40.5 SMBus Interface 1048
40.5.1 Deviations From The SMBus 2.0 Standard 1048
40.5.2 Supplementary SMBus Signals Not Covered By The SMBus 2.0 Standard 1048
40.6 LPC Interface 1049
40.6.1 Deviations From The LPC 1.1 Standard 1049
40.6.2 Supplementary LPC Signals Not Covered By The LPC 1.1 Standard 1049
40.7 eMMC Interface 1050
40.7.1 Deviations From The eMMC 5.0 Standard 1050
40.7.2 Supplementary eMMC Signals Not Covered By The eMMC 5.0 Standard 1050
40.8 HSUART Interface 1051
40.8.1 Deviations From Texas Instruments PC16550D Standard 1051
40.8.2 Supplementary HSUART Signals Not Covered By The Texas Instruments PC16550D Standard 1051
40.9 Serial Peripheral Interface (SPI) 1052
40.9.1 Interface Timing Parameters and Waveforms 1052
40.9.2 SPI Electrical Characteristics 1057
40.10 LAN Interface 1058
40.10.1 10GBASE-KR Interface 1058
40.10.1.1 Deviations From The IEEE802.3 10GBASE-KR Standard 1058

40.10.1.2 Supplementary 10GBASE-KR Signals Not Covered By The IEEE802.3 10GBASE-KR Standard 1058
40.10.2 SFI Interface 1058
40.10.2.1 Deviations From The SFF-8431 SFI Standard 1058
40.10.2.2 Supplementary SFI Signals Not Covered By The SFF-8431 SFI Standard 1058
40.10.3 2500BASE-X Interface 1058
40.10.3.1 Deviations From The 2500BASE-X Industry Convention 1058
40.10.3.2 Supplementary 2500BASE-X Signals Not Covered By The 2500BASE-X Industry Convention 1058
40.10.4 1000BASE-KX Interface 1059
40.10.4.1 Deviations From The IEEE802.3 1000BASE-KX Standard 1059
40.10.4.2 Supplementary 1000BASE-KX Signals Not Covered By The IEEE802.3 1000BASE-KX Standard 1059
40.10.5 SGMII Interface 1059
40.10.5.1 Deviations From The Cisco Systems SGMII Industry Standard 1059
40.10.5.2 Supplementary SGMII Signals Not Covered By The Cisco Systems SGMII Industry Standard 1059
40.10.6 Management Data Input/Output (MDIO) 1060
40.10.6.1 Deviations From IEEE 802.3 1060
40.10.6.2 Supplementary MDIO Signals Not Covered By Clause 22 and Clause 45 of IEEE 802.3 1060
40.10.7 Slave ("Target") Network Controller Sideband Interface (NC-SI) 1060
40.10.7.1 Deviations From The NC-SI Standard 1060
40.10.7.2 Supplementary NC-SI Signals Not Covered By The NC-SI Standard 1060
40.11 SoC Serial Voltage Identification (SVID) Interface 1061
40.11.1 SoC SVID Timing Deviates from the VR13.0 Specification 1061
40.11.2 Supplementary Signals Not Covered By The SVID Standard 1061
40.12 SoC JTAG and Debug Interfaces 1061
40.12.1 Deviations From The JTAG Standard 1061
40.12.2 Supplementary Signals Not Covered By The JTAG Standard 1061
40.13 Customer General Purpose I/O (GPIO) Interface 1062
40.13.1 1.05V GPIO (CMOS-LV Buffer Type) Electrical Characteristics 1062
40.13.1.1 Receiver Electrical Characteristics 1062
40.13.1.2 Driver Electrical Characteristics 1063
40.13.2 1.8V GPIO (CMOS-MV Buffer Type) Electrical Characteristics 1064
40.13.2.1 Receiver Electrical Characteristics 1064
40.13.2.2 Driver Electrical Characteristics 1065
40.13.3 3.3V GPIO (CMOS-HV Buffer Type) Electrical Characteristics 1066
40.13.3.1 Receiver Electrical Characteristics 1066
40.13.3.2 Driver Electrical Characteristics 1067
40.14 Miscellaneous Interfaces 1068
40.14.1 Signals of "V Group V1P05" (CMOS-LV Buffer Type) 1068
40.14.2 Signals of "V Group V1P80" (CMOS-MV Buffer Type) 1068
40.14.3 Signals of "V Group V3P30" (CMOS-HV Buffer Type) 1068

41 Operating Conditions and Power Requirements 1069
41.1 Absolute Maximum and Minimum Ratings 1069
41.1.1 Component Storage Conditions Specification 1069
41.1.1.1 Prior to Board-Attach 1069
41.1.1.2 Post Board-Attach 1070
41.2 Normal Operating Conditions 1070
41.2.1 Component Temperature 1070
41.2.2 Supply Voltage and Current Requirements 1071

42 Package Mechanical Overview 1076

Volume 4: Registers 1077

43 Introduction 1078
43.1 Access to Registers in Host Root Space 1078
43.1.1 PCI Configuration Space 1078
43.1.1.1 Unimplemented Devices/Functions and Registers 1078
43.1.2 Memory Space—Relocatable Address 1079
43.1.3 Memory Space—Fixed Address 1079
43.1.4 I/O Space—Relocatable Address 1079
43.1.5 I/O Space—Fixed Address 1079
43.1.6 Sideband Registers 1080
43.1.7 Model-Specific Registers (MSR) 1080
43.2 Register Description Terminology 1080
43.2.1 Default Values 1080
43.2.2 Software Access Attributes 1081
43.2.3 Hexadecimal, Binary and Decimal Numbers 1082

44 System Agent - B0, D0, F0 1083
44.1 Introduction and Index 1083
44.1.1 Host Configuration Space 1084
44.1.2 Host Memory Space—MCHBAR 1085
44.1.3 Host Memory Space—DEFVTDBAR 1096
44.1.4 Host Memory Space—DEFVTDBAR 1097
44.1.5 Sideband Registers 1099
44.2 Registers in Configuration Space 1103
44.2.1 Device ID and Vendor ID Register (DEVICE_ID_VENDOR_ID_0_0_0_PCI)—Offset 0h 1103
44.2.2 PCI Status and PCI Command Register (PCI_STATUS_COMMAND_0_0_0_PCI)—Offset 4h 1103
44.2.3 PCI Revision ID and PCI Class Code Register (REVISION_ID_CLASS_CODE_0_0_0_PCI)—Offset 8h 1104
44.2.4 Master Latency Timer and Header Type Register (MASTER_LATENCY_TIME_0_0_0_PCI)—Offset Ch 1104
44.2.5 PCI Subsystem Vendor ID and PCI Subsystem ID (SVID_SID_0_0_0_PCI)—Offset 2Ch 1105
44.2.6 Capability Register Pointer (CAPPTR_0_0_0_PCI)—Offset 34h 1105
44.2.7 Memory Controller Hub Base Address Register (MCHBAR_LO_0_0_0_PCI)—Offset 48h 1106
44.2.8 Memory Controller Hub Base Address Register (MCHBAR_HI_0_0_0_PCI)—Offset 4Ch 1106
44.2.9 Device Enable Register (DEVEN_0_0_0_PCI)—Offset 54h 1107
44.2.10 PCI Express Enhanced Configuration Range Base Address Low (PCIEXBAR_LO_0_0_0_PCI)—Offset 60h 1108
44.2.11 PCI Express Enhanced Configuration Range Base Address High (PCIEXBAR_HI_0_0_0_PCI)—Offset 64h 1109
44.2.12 Top of Upper Usable DRAM Low (TOUUD_LO_0_0_0_PCI)—Offset A8h 1110
44.2.13 Top of Upper Usable DRAM High (TOUUD_HI_0_0_0_PCI)—Offset ACh 1111
44.2.14 Base of Data Stolen Memory (BDSM_0_0_0_PCI)—Offset B0h 1112
44.2.15 Base of Graphics Stolen Memory (BGSM_0_0_0_PCI)—Offset B4h 1113
44.2.16 Top Segment Memory Base (TSEGMB_0_0_0_PCI)—Offset B8h 1114
44.2.17 Top of Lower Usable DRAM (TOLUD_0_0_0_PCI)—Offset BCh 1115
44.2.18 Scratchpad (SKPD_0_0_0_PCI)—Offset DCh 1115
44.2.19 Capability ID0 Capability Control (CAPID0_CAPCTRL0_0_0_0_PCI)—Offset E0h 1116
44.2.20 Capability ID0 A (CAPID0_A_0_0_0_PCI)—Offset E4h 1117

44.2.21 Capability ID0 B (CAPID0_B_0_0_0_PCI)—Offset E8h 1118
44.2.22 Manufacturer ID Register (MANUFACTURER_ID_0_0_0_PCI)—Offset F4h . 1119
44.3 Registers in Memory Space—MCHBAR 1120
44.3.1 Default VTd Base Address Register (DEFVTDBAR_0_0_0_MCHBAR_C)—Offset 6C80h 1120
44.3.2 Spare BIOS (A_CR_SPARE_BIOS_MCHBAR)—Offset 647Ch 1121
44.3.3 Uncorrectable Error Status Register (A_CR_UNCERRSTS_0_0_0_MCHBAR)—Offset 6588h..... 1122
44.3.4 Uncorrectable Error Mask Register (A_CR_UNCERRMSK_0_0_0_MCHBAR)—Offset 658Ch 1125
44.3.5 Uncorrectable Error Severity Register (A_CR_UNCERRSEV_0_0_0_MCHBAR)—Offset 6590h..... 1127
44.3.6 First Uncorrectable Error Register (A_CR_UNCFERRSTS_0_0_0_MCHBAR)—Offset 6594h 1129
44.3.7 Next Uncorrectable Error Register (A_CR_UNCNERRSTS_0_0_0_MCHBAR)—Offset 6598h..... 1132
44.3.8 Uncorrectable Error Select Register (A_CR_UNCERRCNTSEL_0_0_0_MCHBAR)—Offset 659Ch 1135
44.3.9 Uncorrectable Error Count (A_CR_UNCERRCNT_0_0_0_MCHBAR)—Offset 65A0h 1137
44.3.10 Correctable Error Status Register (A_CR_CORERRSTS_0_0_0_MCHBAR)—Offset 65A4h..... 1138
44.3.11 Correctable Error Mask Register (A_CR_CORERRMSK_0_0_0_MCHBAR)—Offset 65A8h 1141
44.3.12 First Correctable Error Register (A_CR_CORFERRSTS_0_0_0_MCHBAR)—Offset 65ACh 1143
44.3.13 Next Correctable Error Register (A_CR_CORNERRSTS_0_0_0_MCHBAR)—Offset 65B0h..... 1146
44.3.14 Correctable Error Count Select (A_CR_CORERRCNTSEL_0_0_0_MCHBAR)—Offset 65B4h 1149
44.3.15 Correctable Error Count (A_CR_CORERRCNT_0_0_0_MCHBAR)—Offset 65B8h 1151
44.3.16 Slice and Channel Hash (A_CR_SLICE_CHANNEL_HASH_0_0_0_MCHBAR)—Offset 65C0h..... 1152
44.3.17 A_CR_ASYM_MEM_REGION0_0_0_0_MCHBAR—Offset 65D0h 1154
44.3.18 A_CR_ASYM_MEM_REGION1_0_0_0_MCHBAR—Offset 65D4h 1154
44.3.19 B-Unit Miscellaneous Configuration (B_CR_BMISC_0_0_0_MCHBAR)—Offset 6800h..... 1155
44.3.20 Slice 0 Memory Access Count (B_CR_MEM_ACCESS_COUNT_SLICE0)—Offset 6868h 1155
44.3.21 Slice 1 Memory Access Count (B_CR_MEM_ACCESS_COUNT_SLICE1)—Offset 686Ch 1155
44.3.22 IMR0 Base (B_CR_BIMR0BASE_0_0_0_MCHBAR)—Offset 6870h..... 1156
44.3.23 IMR0 Mask (B_CR_BIMR0MASK_0_0_0_MCHBAR)—Offset 6874h..... 1157
44.3.24 IMR0 Control Policy (B_CR_BIMR0CP_0_0_0_MCHBAR)—Offset 6878h 1157
44.3.25 IMR0 Read Access Policy (B_CR_BIMR0RAC_0_0_0_MCHBAR)—Offset 6880h..... 1158
44.3.26 IMR0 Write Access Policy (B_CR_BIMR0WAC_0_0_0_MCHBAR)—Offset 6888h..... 1161
44.3.27 B_CR_BIMR1BASE_0_0_0_MCHBAR—Offset 6890h..... 1164
44.3.28 IMR1 Mask (B_CR_BIMR1MASK_0_0_0_MCHBAR)—Offset 6894h..... 1165
44.3.29 IMR1 Control Policy (B_CR_BIMR1CP_0_0_0_MCHBAR)—Offset 6898h 1165
44.3.30 IMR1 Read Access Policy (B_CR_BIMR1RAC_0_0_0_MCHBAR)—Offset 68A0h 1166
44.3.31 IMR1 Write Access Policy (B_CR_BIMR1WAC_0_0_0_MCHBAR)—Offset 68A8h 1169
44.3.32 Base 0 IMR2 Base (B_CR_BIMR2BASE_0_0_0_MCHBAR)—Offset 68B0h .. 1172

44.3.33 IMR2 Mask (B_CR_BIMR2MASK_0_0_0_MCHBAR)—Offset 68B4h 1173
44.3.34 IMR2 Control Policy (B_CR_BIMR2CP_0_0_0_MCHBAR)—Offset 68B8h.....1173
44.3.35 IMR2 Read Access Policy (B_CR_BIMR2RAC_0_0_0_MCHBAR)—Offset 68C0h 1174
44.3.36 IMR2 Write Access Policy (B_CR_BIMR2WAC_0_0_0_MCHBAR)—Offset 68C8h 1177
44.3.37 IMR3 Base (B_CR_BIMR3BASE_0_0_0_MCHBAR)—Offset 68D0h.....1180
44.3.38 IMR3 Mask (B_CR_BIMR3MASK_0_0_0_MCHBAR)—Offset 68D4h.....1181
44.3.39 IMR3 Control Policy (B_CR_BIMR3CP_0_0_0_MCHBAR)—Offset 68D8h 1181
44.3.40 IMR3 Read Access Policy (B_CR_BIMR3RAC_0_0_0_MCHBAR)—Offset 68E0h 1182
44.3.41 IMR3 Write Access Policy (B_CR_BIMR3WAC_0_0_0_MCHBAR)—Offset 68E8h 1185
44.3.42 IMR4 Base (B_CR_BIMR4BASE_0_0_0_MCHBAR)—Offset 68F0h 1188
44.3.43 IMR4 Mask (B_CR_BIMR4MASK_0_0_0_MCHBAR)—Offset 68F4h 1189
44.3.44 B-Unit IMR4 Control Policy (B_CR_BIMR4CP_0_0_0_MCHBAR)—Offset 68F8h 1189
44.3.45 IMR4 Read Access Policy (B_CR_BIMR4RAC_0_0_0_MCHBAR)—Offset 6900h 1190
44.3.46 IMR4 Write Access Policy (B_CR_BIMR4WAC_0_0_0_MCHBAR)—Offset 6908h 1193
44.3.47 IMR5 Base (B_CR_BIMR5BASE_0_0_0_MCHBAR)—Offset 6910h 1196
44.3.48 IMR5 Mask (B_CR_BIMR5MASK_0_0_0_MCHBAR)—Offset 6914h 1197
44.3.49 IMR5 Control Policy (B_CR_BIMR5CP_0_0_0_MCHBAR)—Offset 6918h.....1197
44.3.50 IMR5 Read Access Policy (B_CR_BIMR5RAC_0_0_0_MCHBAR)—Offset 6920h 1198
44.3.51 IMR5 Write Access Policy (B_CR_BIMR5WAC_0_0_0_MCHBAR)—Offset 6928h 1201
44.3.52 IMR6 Base (B_CR_BIMR6BASE_0_0_0_MCHBAR)—Offset 6930h 1204
44.3.53 IMR6 Mask (B_CR_BIMR6MASK_0_0_0_MCHBAR)—Offset 6934h 1205
44.3.54 IMR6 Control Policy (B_CR_BIMR6CP_0_0_0_MCHBAR)—Offset 6938h.....1205
44.3.55 IMR6 Read Access Policy (B_CR_BIMR6RAC_0_0_0_MCHBAR)—Offset 6940h 1206
44.3.56 IMR6 Write Access Policy (B_CR_BIMR6WAC_0_0_0_MCHBAR)—Offset 6948h 1209
44.3.57 IMR7 Base (B_CR_BIMR7BASE_0_0_0_MCHBAR)—Offset 6950h 1212
44.3.58 IMR7 Mask (B_CR_BIMR7MASK_0_0_0_MCHBAR)—Offset 6954h 1213
44.3.59 IMR7 Control Policy (B_CR_BIMR7CP_0_0_0_MCHBAR)—Offset 6958h.....1213
44.3.60 IMR7 Read Access Policy (B_CR_BIMR7RAC_0_0_0_MCHBAR)—Offset 6960h 1214
44.3.61 IMR7 Write Access Policy (B_CR_BIMR7WAC_0_0_0_MCHBAR)—Offset 6968h 1217
44.3.62 IMR8 Base (B_CR_BIMR8BASE_0_0_0_MCHBAR)—Offset 6970h 1220
44.3.63 IMR8 Mask (B_CR_BIMR8MASK_0_0_0_MCHBAR)—Offset 6974h 1221
44.3.64 IMR8 Control Policy (B_CR_BIMR8CP_0_0_0_MCHBAR)—Offset 6978h.....1221
44.3.65 IMR8 Read Access Policy (B_CR_BIMR8RAC_0_0_0_MCHBAR)—Offset 6980h 1222
44.3.66 IMR8 Write Access Policy (B_CR_BIMR8WAC_0_0_0_MCHBAR)—Offset 6988h 1225
44.3.67 IMR9 Base (B_CR_BIMR9BASE_0_0_0_MCHBAR)—Offset 6990h 1228
44.3.68 IMR9 Mask (B_CR_BIMR9MASK_0_0_0_MCHBAR)—Offset 6994h 1229
44.3.69 IMR9 Control Policy (B_CR_BIMR9CP_0_0_0_MCHBAR)—Offset 6998h.....1229
44.3.70 IMR9 Read Access Policy (B_CR_BIMR9RAC_0_0_0_MCHBAR)—Offset 69A0h 1230
44.3.71 IMR9 Write Access Policy (B_CR_BIMR9WAC_0_0_0_MCHBAR)—Offset 69A8h 1233

44.3.72 IMR10 Base (B_CR_BIMR10BASE_0_0_0_MCHBAR)—Offset 69B0h 1236
44.3.73 B_CR_BIMR10MASK_0_0_0_MCHBAR—Offset 69B4h 1237
44.3.74 IMR10 Control Policy (B_CR_BIMR10CP_0_0_0_MCHBAR)—Offset 69B8h. 1237
44.3.75 IMR10 Read Access Policy (B_CR_BIMR10RAC_0_0_0_MCHBAR)—Offset 69C0h 1238
44.3.76 IMR10 Write Access Policy (B_CR_BIMR10WAC_0_0_0_MCHBAR)—Offset 69C8h 1241
44.3.77 IMR11 Base (B_CR_BIMR11BASE_0_0_0_MCHBAR)—Offset 69D0h 1244
44.3.78 IMR11 Mask (B_CR_BIMR11MASK_0_0_0_MCHBAR)—Offset 69D4h 1245
44.3.79 IMR11 Control Policy (B_CR_BIMR11CP_0_0_0_MCHBAR)—Offset 69D8h 1245
44.3.80 IMR11 Read Access Policy (B_CR_BIMR11RAC_0_0_0_MCHBAR)—Offset 69E0h..... 1246
44.3.81 IMR11 Write Access Policy (B_CR_BIMR11WAC_0_0_0_MCHBAR)—Offset 69E8h..... 1249
44.3.82 IMR12 Base (B_CR_BIMR12BASE_0_0_0_MCHBAR)—Offset 69F0h 1252
44.3.83 IMR12 Mask (B_CR_BIMR12MASK_0_0_0_MCHBAR)—Offset 69F4h 1253
44.3.84 IMR12 Control Policy (B_CR_BIMR12CP_0_0_0_MCHBAR)—Offset 69F8h. 1253
44.3.85 IMR12 Read Access Policy (B_CR_BIMR12RAC_0_0_0_MCHBAR)—Offset 6A00h 1254
44.3.86 IMR12 Write Access Policy (B_CR_BIMR12WAC_0_0_0_MCHBAR)—Offset 6A08h 1257
44.3.87 IMR13 Base (B_CR_BIMR13BASE_0_0_0_MCHBAR)—Offset 6A10h 1260
44.3.88 IMR13 Mask (B_CR_BIMR13MASK_0_0_0_MCHBAR)—Offset 6A14h 1261
44.3.89 IMR13 Control Policy (B_CR_BIMR13CP_0_0_0_MCHBAR)—Offset 6A18h. 1261
44.3.90 IMR13 Read Access Policy (B_CR_BIMR13RAC_0_0_0_MCHBAR)—Offset 6A20h 1262
44.3.91 IMR13 Write Access Policy (B_CR_BIMR13WAC_0_0_0_MCHBAR)—Offset 6A28h 1265
44.3.92 IMR14 Base (B_CR_BIMR14BASE_0_0_0_MCHBAR)—Offset 6A30h 1268
44.3.93 IMR14 Mask (B_CR_BIMR14MASK_0_0_0_MCHBAR)—Offset 6A34h 1269
44.3.94 IMR14 Control Policy (B_CR_BIMR14CP_0_0_0_MCHBAR)—Offset 6A38h. 1269
44.3.95 IMR14 Read Access Policy (B_CR_BIMR14RAC_0_0_0_MCHBAR)—Offset 6A40h 1270
44.3.96 IMR14 Write Access Policy (B_CR_BIMR14WAC_0_0_0_MCHBAR)—Offset 6A48h 1273
44.3.97 IMR15 Base (B_CR_BIMR15BASE_0_0_0_MCHBAR)—Offset 6A50h 1276
44.3.98 IMR15 Mask (B_CR_BIMR15MASK_0_0_0_MCHBAR)—Offset 6A54h 1277
44.3.99 IMR15 Control Policy (B_CR_BIMR15CP_0_0_0_MCHBAR)—Offset 6A58h. 1277
44.3.100 IMR15 Read Access Policy (B_CR_BIMR15RAC_0_0_0_MCHBAR)—Offset 6A60h 1278
44.3.101 IMR15 Write Access Policy (B_CR_BIMR15WAC_0_0_0_MCHBAR)—Offset 6A68h 1281
44.3.102 IMR16 Base (B_CR_BIMR16BASE_0_0_0_MCHBAR)—Offset 6A70h 1284
44.3.103 IMR16 Mask (B_CR_BIMR16MASK_0_0_0_MCHBAR)—Offset 6A74h 1285
44.3.104 IMR16 Control Policy (B_CR_BIMR16CP_0_0_0_MCHBAR)—Offset 6A78h. 1285
44.3.105 IMR16 Read Access Policy (B_CR_BIMR16RAC_0_0_0_MCHBAR)—Offset 6A80h 1286
44.3.106 IMR16 Write Access Policy (B_CR_BIMR16WAC_0_0_0_MCHBAR)—Offset 6A88h 1289
44.3.107 IMR17 Base (B_CR_BIMR17BASE_0_0_0_MCHBAR)—Offset 6A90h 1292
44.3.108 IMR17 Mask (B_CR_BIMR17MASK_0_0_0_MCHBAR)—Offset 6A94h 1293
44.3.109 IMR17 Control Policy (B_CR_BIMR17CP_0_0_0_MCHBAR)—Offset 6A98h. 1293
44.3.110 IMR17 Read Access Policy (B_CR_BIMR17RAC_0_0_0_MCHBAR)—Offset 6AA0h 1294
44.3.111 IMR17 Write Access Policy (B_CR_BIMR17WAC_0_0_0_MCHBAR)—Offset 6AA8h 1297

44.3.112 IMR18 Base (B_CR_BIMR18BASE_0_0_0_MCHBAR)—Offset 6AB0h 1300
44.3.113 IMR18 Mask (B_CR_BIMR18MASK_0_0_0_MCHBAR)—Offset 6AB4h 1301
44.3.114 IMR18 Control Policy (B_CR_BIMR18CP_0_0_0_MCHBAR)—Offset 6AB8h .1301
44.3.115 IMR18 Read Access Policy (B_CR_BIMR18RAC_0_0_0_MCHBAR)—Offset 6AC0h 1302
44.3.116 IMR18 Write Access Policy (B_CR_BIMR18WAC_0_0_0_MCHBAR)—Offset 6AC8h 1305
44.3.117 IMR19 Base (B_CR_BIMR19BASE_0_0_0_MCHBAR)—Offset 6AD0h 1308
44.3.118 IMR19 Mask (B_CR_BIMR19MASK_0_0_0_MCHBAR)—Offset 6AD4h 1309
44.3.119 IMR19 Control Policy (B_CR_BIMR19CP_0_0_0_MCHBAR)—Offset 6AD8h.1309
44.3.120 IMR19 Read Access Policy (B_CR_BIMR19RAC_0_0_0_MCHBAR)—Offset 6AE0h 1310
44.3.121 IMR19 Write Access Policy (B_CR_BIMR19WAC_0_0_0_MCHBAR)—Offset 6AE8h 1313
44.3.122 TPM Selector (B_CR_TPM_SELECTOR_0_0_0_MCHBAR)—Offset 6C24h 1316
44.3.123 Default VTd BAR (B_CR_DEFVTDBAR_0_0_0_MCHBAR)—Offset 6C80h.....1316
44.3.124 B-Unit Arbiter Control BARBCTRL0 (B_CR_BARBCTRL0)—Offset 6D4Ch 1317
44.3.125 B-Unit Arbiter Control BARBCTRL1 (B_CR_BARBCTRL1)—Offset 6D50h 1318
44.3.126 B-Unit Scheduler Control (B_CR_BSCHWT0)—Offset 6D54h 1319
44.3.127 B-Unit Scheduler Control (B_CR_BSCHWT1)—Offset 6D58h 1320
44.3.128 B-Unit Scheduler Control (B_CR_BSCHWT2)—Offset 6D5Ch 1321
44.3.129 B-Unit Scheduler Control (B_CR_BSCHWT3)—Offset 6D60h 1322
44.3.130 B-Unit Flush Control (B_CR_BWFLUSH)—Offset 6D64h.....1323
44.3.131 B-Unit Flush Weights (B_CR_BFLWT)—Offset 6D68h 1323
44.3.132 Weighted Scheduling Control of High Priority ISOC and Other Requests (B_CR_BISOCWT)—Offset 6D6Ch 1324
44.3.133 B-Unit Control (B_CR_BCTRL2)—Offset 6D70h.....1325
44.3.134 Uncorrectable Error Status Register (B_CR_UNCERRSTS_0_0_0_MCHBAR)—Offset 6E04h 1326
44.3.135 Uncorrectable Error Mask Register (B_CR_UNCERRMSK_0_0_0_MCHBAR)—Offset 6E08h.....1329
44.3.136 Uncorrectable Error Severity Register (B_CR_UNCERRSEV_0_0_0_MCHBAR)—Offset 6E0Ch 1331
44.3.137 First Uncorrectable Error Register (B_CR_UNCFERRSTS_0_0_0_MCHBAR)—Offset 6E10h.....1333
44.3.138 Next Uncorrectable Error Register (B_CR_UNCNERRSTS_0_0_0_MCHBAR)—Offset 6E14h 1336
44.3.139 Uncorrectable Error Select Register (B_CR_UNCERRCNTSEL_0_0_0_MCHBAR)—Offset 6E18h 1339
44.3.140 Uncorrectable Error Count (B_CR_UNCERRCNT_0_0_0_MCHBAR)—Offset 6E1Ch 1341
44.3.141 Correctable Error Status Register (B_CR_CORERRSTS_0_0_0_MCHBAR)—Offset 6E20h 1342
44.3.142 Correctable Error Mask Register (B_CR_CORERRMSK_0_0_0_MCHBAR)—Offset 6E24h.....1345
44.3.143 Data Parity Header Log Low (B_CR_DPHDRLOG_LO_0_0_0_MCHBAR)—Offset 6E28h 1347
44.3.144 Data Parity Header Log High (B_CR_DPHDRLOG_HI_0_0_0_MCHBAR)—Offset 6E2Ch 1347
44.3.145 Data Parity Address Log Low (B_CR_DPADDRLOG_LO_0_0_0_MCHBAR)—Offset 6E30h 1347
44.3.146 Data Parity Address Log High (B_CR_DPADDRLOG_HI_0_0_0_MCHBAR)—Offset 6E34h.....1348
44.3.147 D-Unit Error Address Log (B_CR_DERRADDRLOG_LO_0_0_0_MCHBAR)—Offset 6E38h 1348

44.3.148 D-Unit Error Address Log (B_CR_DERRADDRLOG_HI_0_0_0_MCHBAR)—Offset 6E3Ch 1348
44.3.149 Asymmetric Memory Region 0 (B_CR_ASYM_MEM_REGION0_0_0_0_MCHBAR)—Offset 6E40h 1349
44.3.150 Asymmetric Memory Region 1 (B_CR_ASYM_MEM_REGION1_0_0_0_MCHBAR)—Offset 6E44h 1349
44.3.151 B-Unit Machine Check Mode Low (B_CR_BMCMODE_LOW)—Offset 6E48h..... 1350
44.3.152 B-Unit Machine Check Mode High (B_CR_BMCMODE_HIGH)—Offset 6E4Ch 1350
44.3.153 PWR_LIMIT_MISC_0_0_0_MCHBAR (P_CR_PWR_LIMIT_MISC_0_0_0_MCHBAR)—Offset 7014h 1351
44.3.154 CAPABILITY_ID_0_0_0_MCHBAR (P_CR_CAPABILITY_ID_0_0_0_MCHBAR)—Offset 7018h 1351
44.3.155 MC_BIOS_REQ_0_0_0_MCH (P_CR_MC_BIOS_REQ_0_0_0_MCHBAR)—Offset 7020h 1352
44.3.156 MCA_ERROR_SRC_0_0_0_MCHBAR (P_CR_MCA_ERROR_SRC_0_0_0_MCHBAR)—Offset 702Ch 1353
44.3.157 DDR_THERM_THRT_CTRL_0_0_0_MCHBAR (P_CR_DDR_THERM_THRT_CTRL_0_0_0_MCHBAR)—Offset 7030h 1354
44.3.158 PACKAGE_THERM_MARGIN (P_CR_PACKAGE_THERM_MARGIN_0_0_0_MCHBAR)—Offset 703Ch 1355
44.3.159 DDR_RAPL_LIMIT (P_CR_DDR_RAPL_LIMIT_0_0_0_MCHBAR)—Offset 7040h..... 1356
44.3.160 DDR_ENERGY_STATUS (P_CR_DDR_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 7048h 1357
44.3.161 DDR_RAPL_PERF_STATUS (P_CR_DDR_RAPL_PERF_STATUS_0_0_0_MCHBAR)—Offset 704Ch..... 1357
44.3.162 PACKAGE_RAPL_PERF_STATUS (P_CR_PACKAGE_RAPL_PERF_STATUS_0_0_0_MCHBAR)—Offset 7050h.. 1358
44.3.163 PRIMARY_PLANE_TURBO_POWER_POLICY (P_CR_PRIMARY_PLANE_TURBO_PLCY_0_0_0_MCHBAR)—Offset 7054h.. 1358
44.3.164 SECONDARY_PLANE_TURBO_POWER_POLICY (P_CR_SECONDARY_PLANE_TURBO_PLCY_0_0_0_MCHBAR)—Offset 7058h..... 1359
44.3.165 PRIMARY_PLANE_ENERGY_STATUS (P_CR_PRIMARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 705Ch 1359
44.3.166 SECONDARY_PLANE_ENERGY_STATUS (P_CR_SECONDARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 7060h..... 1360
44.3.167 PACKAGE_POWER_SKU_UNIT (P_CR_PACKAGE_POWER_SKU_UNIT_0_0_0_MCHBAR)—Offset 7068h.... 1361
44.3.168 PACKAGE_ENERGY_STATUS (P_CR_PACKAGE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 706Ch 1362
44.3.169 GT_PERF_STATUS (P_CR_GT_PERF_STATUS_0_0_0_MCHBAR)—Offset 7070h..... 1362
44.3.170 TEMPERATURE_TARGET (P_CR_TEMPERATURE_TARGET_0_0_0_MCHBAR)—Offset 7074h 1363
44.3.171 BIOS_RESET_CPL (P_CR_BIOS_RESET_CPL_0_0_0_MCHBAR)—Offset 7078h..... 1364
44.3.172 BIOS_MAILBOX_DATA (P_CR_BIOS_MAILBOX_DATA_0_0_0_MCHBAR)—Offset 7080h 1366
44.3.173 BIOS_MAILBOX_INTERFACE (P_CR_BIOS_MAILBOX_INTERFACE_0_0_0_MCHBAR)—Offset 7084h 1366

44.3.174 CORE_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_CORE_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7088h 1367
44.3.175 GRAPHICS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_GRAPHICS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 708Ch 1368
44.3.176 SYSTEM_AGENT_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_SYSTEM_AGENT_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7090h 1369
44.3.177 FAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_FAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7094h 1369
44.3.178 NEAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_NEAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7098h 1370
44.3.179 PACKAGE_POWER_SKU (P_CR_PACKAGE_POWER_SKU_0_0_0_MCHBAR)—Offset 70A0h.....1371
44.3.180 PACKAGE_RAPL_LIMIT (P_CR_PACKAGE_RAPL_LIMIT_0_0_0_MCHBAR)—Offset 70A8h 1372
44.3.181 IA_PERF_LIMIT_REASONS (P_CR_IA_PERF_LIMIT_REASONS_0_0_0_MCHBAR)—Offset 70B0h 1374
44.3.182 MEMHOT_THERM_STATUS_0_0_0_MCHBAR (P_CR_MEMHOT_THERM_STATUS_0_0_0_MCHBAR)—Offset 70D8h.....1376
44.3.183 MEMHOT_THERM_CONFIG_0_0_0_MCHBAR (P_CR_MEMHOT_THERM_CONFIG_0_0_0_MCHBAR)—Offset 70DCh 1376
44.3.184 MEM_THERM_CTRL_0_0_0_MCHBAR (P_CR_MEM_THERM_CTRL_0_0_0_MCHBAR)—Offset 7200h 1377
44.3.185 MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR (P_CR_MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR)—Offset 7204h.....1378
44.3.186 MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR (P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR)—Offset 7208h....1378
44.3.187 MEM_THERM_STATUS_0_0_0_MCHBAR (P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR)—Offset 720Ch.....1379
44.3.188 MEM_THERM_INTERRUPT_0_0_0_MCHBAR (P_CR_MEM_THERM_INTERRUPT_0_0_0_MCHBAR)—Offset 7210h 1380
44.3.189 MEM_THERM_INT_STATUS_0_0_0_MCHBAR (P_CR_MEM_THERM_INT_STATUS_0_0_0_MCHBAR)—Offset 7214h 1381
44.3.190 MEM_THERM_TEMP_OFST_0_0_0_MCHBAR (P_CR_MEM_THERM_TEMP_OFST_0_0_0_MCHBAR)—Offset 7218h 1383
44.3.191 TELEM_NEAR_MEMORY_ACTIVE_ACCUMULATOR (P_CR_TELEM_NEAR_MEMORY_ACTIVE_0_0_0_MCHBAR)—Offset 70E0h .1384
44.3.192 TELEM_FAR_MEMORY_ACTIVE_ACCUMULATOR (P_CR_TELEM_FAR_MEMORY_ACTIVE_0_0_0_MCHBAR)—Offset 70E8h....1384
44.3.193 TURBO_ACTIVATION_RATIO (P_CR_TURBO_ACTIVATION_RATIO_0_0_0_MCHBAR)—Offset 70F0h 1385
44.3.194 C2C3TT_CFG (P_CR_C2C3TT_CFG_0_0_0_MCHBAR)—Offset 7034h 1385
44.3.195 DTS_CONFIG1_CFG (P_CR_DTS_CONFIG1_CFG_0_0_0_MCHBAR)—Offset 7110h 1386
44.3.196 DTS_CONFIG2_CFG (P_CR_DTS_CONFIG2_CFG_0_0_0_MCHBAR)—Offset 7114h 1386
44.3.197 DTS_CONFIG3_CFG (P_CR_DTS_CONFIG3_CFG_0_0_0_MCHBAR)—Offset 7118h 1387
44.3.198 SOUTH_IO_PORT_STATUS3 (P_CR_SOUTH_IO_PORT_STATUS3_0_0_0_MCHBAR)—Offset 711Ch.....1387
44.3.199 DRAM_BIOS_INFO (P_CR_DRAM_BIOS_INFO_0_0_0_MCHBAR)—Offset 7128h 1388
44.3.200 ADR_COMMAND (P_CR_ADR_COMMAND_0_0_0_MCHBAR)—Offset 712Ch1389

44.3.201 DRAM_POWER_INFO (P_CR_DRAM_POWER_INFO_0_0_0_MCHBAR)—Offset 7130h 1390
44.3.202 PCODE_WRITE_SPARE (P_CR_PCODE_WRITE_SPARE_0_0_0_MCHBAR)—Offset 7138h..... 1390
44.3.203 PACKAGE_TEMPERATURES_0_0_0_MCHBAR (P_CR_PACKAGE_TEMPERATURES_0_0_0_MCHBAR)—Offset 70F4h 1391
44.3.204 MEMSS_FREQUENCY_CAPABILITIES (P_CR_MEMSS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7108h..... 1392
44.3.205 PP1_C0_CORE_CLOCK_0_0_0_MCHBAR (P_CR_PP1_C0_CORE_CLOCK_0_0_0_MCHBAR)—Offset 7160h..... 1392
44.3.206 Core Exists Vector (P_CR_CORE_EXISTS_VECTOR_0_0_0_MCHBAR)—Offset 7164h 1393
44.3.207 Software Core Disable Mask (P_CR_CORE_DISABLE_MASK_0_0_0_MCHBAR)—Offset 7168h..... 1394
44.3.208 PL3_CONTROL_MCHBAR (P_CR_PL3_CONTROL_0_0_0_MCHBAR)—Offset 71F0h..... 1396
44.3.209 CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL1_0_0_0_MCHBAR)—Offset 7220h..... 1398
44.3.210 CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL2_0_0_0_MCHBAR)—Offset 7228h..... 1399
44.3.211 CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL3_0_0_0_MCHBAR)—Offset 7230h..... 1400
44.3.212 CONFIG_TDP_CONTROL (P_CR_CONFIG_TDP_CONTROL_0_0_0_MCHBAR)—Offset 7238h..... 1400
44.3.213 CONFIG_TDP_NOMINAL (P_CR_CONFIG_TDP_NOMINAL_0_0_0_MCHBAR)—Offset 723Ch..... 1401
44.3.214 Graphics Superqueue Active Clocks (P_CR_PP1_ANY_THREAD_ACTIVITY_0_0_0_MCHBAR)—Offset 7244h..... 1402
44.3.215 B-Unit Copy of Default VTd BAR PMEN (B_CR_PMEN_REG_0_0_0_DEFVTDBAR)—Offset 64h 1402
44.3.216 B-Unit Copy of Default VTd BAR PLM Base Register (B_CR_PLMBASE_REG_0_0_0_DEFVTDBAR)—Offset 68h 1403
44.3.217 B-Unit Copy of Default VTd BAR PLM Limit Register (B_CR_PLMLIMIT_REG_0_0_0_DEFVTDBAR)—Offset 6Ch 1404
44.3.218 B-Unit Copy of Default VTd BAR PHM Base Register (B_CR_PHMBASE_REG_0_0_0_DEFVTDBAR)—Offset 70h 1405
44.3.219 B-Unit Copy of Default VTd BAR PHM Limit Register (B_CR_PHMLIMIT_REG_0_0_0_DEFVTDBAR)—Offset 78h 1406
44.4 Registers in Memory Space—DEFVTDBAR..... 1407
44.4.1 Version Register (VER_REG_0_0_0_VTDBAR)—Offset 0h 1407
44.4.2 Capability Register (CAP_REG_0_0_0_VTDBAR)—Offset 8h 1407
44.4.3 Extended Capability Register (ECAP_REG_0_0_0_VTDBAR)—Offset 10h... 1409
44.4.4 Global Command Register (GCMD_REG_0_0_0_VTDBAR)—Offset 18h 1412
44.4.5 Global Status Register (GSTS_REG_0_0_0_VTDBAR)—Offset 1Ch 1413
44.4.6 Root Table Address Register (RTADDR_REG_0_0_0_VTDBAR)—Offset 20h 1414
44.4.7 Context Command Register (CCMD_REG_0_0_0_VTDBAR)—Offset 28h ... 1415
44.4.8 Fault Status Register (FSTS_REG_0_0_0_VTDBAR)—Offset 34h..... 1417
44.4.9 Fault Event Control Register (FECTL_REG_0_0_0_VTDBAR)—Offset 38h .. 1419
44.4.10 Fault Event Data Register (FEDATA_REG_0_0_0_VTDBAR)—Offset 3Ch ... 1420
44.4.11 Fault Event Address Register (FEADDR_REG_0_0_0_VTDBAR)—Offset 40h 1420
44.4.12 Fault Event Upper Address Register (FEUADDR_REG_0_0_0_VTDBAR)—Offset 44h 1420
44.4.13 Advanced Fault Log Register (AFLOG_REG_0_0_0_VTDBAR)—Offset 58h . 1421

44.4.14 Protected Memory Enable Register (PMEN_REG_0_0_0_VTDBAR)—Offset 64h....1422
44.4.15 Protected Low Memory Base Register (PLMBASE_REG_0_0_0_VTDBAR)—Offset 68h....1423
44.4.16 Protected Low-Memory Limit Register (PLMLIMIT_REG_0_0_0_VTDBAR)—Offset 6Ch....1424
44.4.17 Protected High-Memory Base Register (PHMBASE_REG_0_0_0_VTDBAR)—Offset 70h....1425
44.4.18 Protected High-Memory Limit Register (PHMLIMIT_REG_0_0_0_VTDBAR)—Offset 78h....1426
44.4.19 Invalidation Queue Head Register (IQH_REG_0_0_0_VTDBAR)—Offset 80h....1427
44.4.20 Invalidation Queue Tail Register (IQT_REG_0_0_0_VTDBAR)—Offset 88h....1427
44.4.21 Invalidation Queue Address Register (IQA_REG_0_0_0_VTDBAR)—Offset 90h....1428
44.4.22 Invalidation Completion Status Register (ICS_REG_0_0_0_VTDBAR)—Offset 9Ch....1428
44.4.23 Invalidation Event Control Register (IECTL_REG_0_0_0_VTDBAR)—Offset A0h....1429
44.4.24 Invalidation Event Data Register (IEDATA_REG_0_0_0_VTDBAR)—Offset A4h....1430
44.4.25 Invalidation Event Address Register (IEADDR_REG_0_0_0_VTDBAR)—Offset A8h....1430
44.4.26 Invalidation Event Upper Address Register (IEUADDR_REG_0_0_0_VTDBAR)—Offset ACh....1431
44.4.27 Interrupt Remapping Table Address Register (IRTA_REG_0_0_0_VTDBAR)—Offset B8h....1431
44.4.28 Page Request Status Register (PRESTS_REG_0_0_0_VTDBAR)—Offset DCh....1432
44.4.29 Page Request Event Control Register (PRECTL_REG_0_0_0_VTDBAR)—Offset E0h....1433
44.4.30 Page Request Event Data Register (PREDATA_REG_0_0_0_VTDBAR)—Offset E4h....1434
44.4.31 Page Request Event Address Register (PREADDR_REG_0_0_0_VTDBAR)—Offset E8h....1434
44.4.32 Page Request Event Upper Address Register (PREUADDR_REG_0_0_0_VTDBAR)—Offset ECh....1434
44.4.33 Fault Recording Register Low [0] (FRCDL_REG_0_0_0_VTDBAR)—Offset 400h....1435
44.4.34 Fault Recording Register High [0] (FRCDH_REG_0_0_0_VTDBAR)—Offset 408h....1436
44.4.35 Invalidate Address Register (IVA_REG_0_0_0_VTDBAR)—Offset 500h....1438
44.4.36 IOTLB Invalidate Register (IOTLB_REG_0_0_0_VTDBAR)—Offset 508h....1439
44.5 Sideband Registers....1441
44.5.1 UCELOG—Offset 64h....1441
44.5.2 UCEADDR—Offset 68h....1442
44.5.3 SBELOG—Offset 6Ch....1442
44.5.4 SBEADDR—Offset 70h....1443
44.5.5 SBECNT0—Offset 74h....1444
44.5.6 SBECNT1—Offset 78h....1444
44.5.7 SBECNT2—Offset 7Ch....1445
44.5.8 SBECNT3—Offset 80h....1445
44.5.9 SBEACC0—Offset 84h....1445
44.5.10 SBEACC1—Offset 88h....1446
44.5.11 SBEACC2—Offset 8Ch....1446
44.5.12 SBEACC3—Offset 90h....1446

44.5.13 DPATROL_SCRUB_CFG—Offset B0h 1447
44.5.14 UCELOG1—Offset CCh 1447
44.5.15 SBELOG1—Offset D0h 1448
44.5.16 CORRERRTHRSHLD0—Offset 100h 1448
44.5.17 CORRERRTHRSHLD1—Offset 104h 1448
44.5.18 CORRERRTHRSHLD2—Offset 108h 1449
44.5.19 CORRERRTHRSHLD3—Offset 10Ch 1449
44.5.20 LEAKY_BUCKET_CFG0—Offset 110h 1449
44.5.21 LEAKY_BUCKET_CFG1—Offset 114h 1450
44.5.22 LEAKY_BUCKET_CFG2—Offset 118h 1450
44.5.23 LEAKY_BUCKET_CFG3—Offset 11Ch 1450
44.5.24 FERRNERR—Offset 120h 1451
44.5.25 DERRSTS—Offset 124h 1452
44.5.26 DERRMSKSEV—Offset 128h 1453
44.5.27 DERRCNTSEL—Offset 12Ch 1454
44.5.28 DERRCNT—Offset 130h 1454
44.5.29 ERRINJCTL—Offset 134h 1455
44.5.30 ERRINJADDR—Offset 138h 1456
44.5.31 ERRINJAMSK—Offset 13Ch 1456
44.5.32 ERRINJDATA0—Offset 140h 1456
44.5.33 ERRINJDATA1—Offset 144h 1456
44.5.34 DCS—Offset 170h 1457
44.5.35 DECCCTRL—Offset 180h 1458
44.5.36 LEAKY_BUCKET_CNTR_UPPER—Offset 18Ch 1459
44.5.37 DPATROL_SCRUB_TMR—Offset 194h 1459
44.5.38 UCELOG—Offset 64h 1460
44.5.39 UCEADDR—Offset 68h 1460
44.5.40 SBELOG—Offset 6Ch 1461
44.5.41 SBEADDR—Offset 70h 1461
44.5.42 SBECNT0—Offset 74h 1462
44.5.43 SBECNT1—Offset 78h 1462
44.5.44 SBECNT2—Offset 7Ch 1463
44.5.45 SBECNT3—Offset 80h 1463
44.5.46 SBEACC0—Offset 84h 1464
44.5.47 SBEACC1—Offset 88h 1464
44.5.48 SBEACC2—Offset 8Ch 1465
44.5.49 SBEACC3—Offset 90h 1465
44.5.50 DPATROL_SCRUB_CFG—Offset B0h 1466
44.5.51 UCELOG1—Offset CCh 1466
44.5.52 SBELOG1—Offset D0h 1467
44.5.53 CORRERRTHRSHLD0—Offset 100h 1467
44.5.54 CORRERRTHRSHLD1—Offset 104h 1467
44.5.55 CORRERRTHRSHLD2—Offset 108h 1468
44.5.56 CORRERRTHRSHLD3—Offset 10Ch 1468
44.5.57 LEAKY_BUCKET_CFG0—Offset 110h 1468
44.5.58 LEAKY_BUCKET_CFG1—Offset 114h 1469
44.5.59 LEAKY_BUCKET_CFG2—Offset 118h 1469
44.5.60 LEAKY_BUCKET_CFG3—Offset 11Ch 1469
44.5.61 FERRNERR—Offset 120h 1470
44.5.62 DERRSTS—Offset 124h 1471
44.5.63 DERRMSKSEV—Offset 128h 1472
44.5.64 DERRCNTSEL—Offset 12Ch 1473
44.5.65 DERRCNT—Offset 130h 1473
44.5.66 ERRINJCTL—Offset 134h 1474
44.5.67 ERRINJADDR—Offset 138h 1475

44.5.68 ERRINJAMSK—Offset 13Ch 1475
44.5.69 ERRINJDATA0—Offset 140h 1475
44.5.70 ERRINJDATA1—Offset 144h 1475
44.5.71 DCS—Offset 170h 1476
44.5.72 DECCCTRL—Offset 180h 1478
44.5.73 LEAKY_BUCKET_CNTR_UPPER—Offset 18Ch 1479
44.5.74 DPATROL_SCRUB_TMR—Offset 194h 1479
44.5.75 ICLK_DWORD8—Port 99h, Offset 220h 1480

45 Global and Local Error Registers (GLMREG) - B0, D4, F0 1481
45.1 Introduction and Index 1481
45.1.1 Host Configuration Space 1482
45.2 Registers in Configuration Space 1483
45.2.1 GLREG Vendor ID (GLREG_VID)—Offset 0h 1483
45.2.2 GLREG PCI Command (GLREG_PCICMD)—Offset 4h 1484
45.2.3 GLREG PCI Status (GLREG_PCISTS)—Offset 6h 1485
45.2.4 GLREG Class Code (GLREG_CC)—Offset 9h 1486
45.2.5 GLREG Cacheline Size (GLREG_CLS)—Offset Ch 1486
45.2.6 GLREG Subsystem Vendor ID (GLREG_SVID)—Offset 2Ch 1487
45.2.7 GLREG Capabilities Pointer (GLREG_CAPPTR)—Offset 34h 1487
45.2.8 GLREG Interrupt Pin (GLREG_INTP)—Offset 3Dh 1488
45.2.9 GLREG PCI Express Capability List (GLREG_EXPCAPLST)—Offset 40h 1488
45.2.10 GLREG PCI Express Capabilities (GLREG_EXPCAP)—Offset 42h 1489
45.2.11 GLREG Device Control (GLREG_DEVCTL)—Offset 48h 1490
45.2.12 GLREG Device Status (GLREG_DEVSTS)—Offset 4Ah 1491
45.2.13 GLREG Global Correctable Error Status (GLREG_GCOERRSTS)—Offset 200h 1492
45.2.14 GLREG Global Non-Fatal Error Status (GLREG_GNFERRSTS)—Offset 204h 1494
45.2.15 GLREG Global Fatal Error Status (GLREG_GFAERRSTS)—Offset 208h 1496
45.2.16 GLREG Global Error Mask (GLREG_GERRMSK)—Offset 20Ch 1498
45.2.17 GLREG Global Error Timer (GLREG_GTIME)—Offset 228h 1500
45.2.18 GLREG Global Correctable FERR Error Time Stamp (GLREG_GCOFERRTIME)—Offset 230h 1500
45.2.19 GLREG Global Nonfatal FERR Error Time Stamp (GLREG_GNFFERRTIME)—Offset 238h 1501
45.2.20 GLREG Global Fatal FERR Error Time Stamp (GLREG_GFAFERRTIME)—Offset 240h 1501
45.2.21 GLREG Global System Event Status (GLREG_GSYSEVTSTS)—Offset 248h 1502
45.2.22 GLREG Global System Event Mask (GLREG_GSYSEVTMSK)—Offset 24Ch 1502
45.2.23 GLREG Global System Event Map (GLREG_GSYSEVTMAP)—Offset 250h 1503
45.2.24 GLREG Error Pin Control (GLREG_ERRPINCTRL)—Offset 254h 1504
45.2.25 GLREG Error Pin Status (GLREG_ERRPINSTS)—Offset 258h 1504
45.2.26 GLREG Error Pin Data (GLREG_ERRPINDATA)—Offset 25Ch 1505
45.2.27 GLREG Uncorrectable Error Counter (GLREG_LUNCERRCNT)—Offset 294h 1506

46 Root Complex Event Collector - B0, D5, F0 1507
46.1 Introduction and Index 1507
46.1.1 Host Configuration Space 1508
46.2 Registers in Configuration Space 1509
46.2.1 RCEC Vendor ID (RCEC_VID)—Offset 0h 1509
46.2.2 RCEC PCI Command (RCEC_PCICMD)—Offset 4h 1510
46.2.3 RCEC PCI Status (RCEC_PCISTS)—Offset 6h 1511

46.2.4 RCEC Class Code (RCEC_CC)—Offset 9h 1512
46.2.5 RCEC Cacheline Size (RCEC_CLS)—Offset Ch 1512
46.2.6 RCEC Interrupt Pin (RCEC_INTP)—Offset 3Dh 1513
46.2.7 RCEC PCI Express Capability List (RCEC_EXPCAPLST)—Offset 40h 1513
46.2.8 RCEC PCI Express Capabilities (RCEC_EXPCAP)—Offset 42h 1514
46.2.9 RCEC Device Control (RCEC_DEVCTL)—Offset 48h 1515
46.2.10 RCEC Device Status (RCEC_DEVSTS)—Offset 4Ah 1516
46.2.11 RCEC Root Control (RCEC_ROOTCTL)—Offset 5Ch 1517
46.2.12 RCEC Power Management Capabilities (RCEC_PMCAP)—Offset 82h 1518
46.2.13 RCEC Power Management Control / Status (RCEC_PMCSR)—Offset 84h 1518
46.2.14 RCEC MSI Capability List (RCEC_MSICAPLST)—Offset 90h 1519
46.2.15 RCEC MSI Message Control (RCEC_MSICTL)—Offset 92h 1519
46.2.16 RCEC MSI Message Address (RCEC_MSIADDR)—Offset 94h 1520
46.2.17 RCEC MSI Message Data (RCEC_MSIDATA)—Offset 98h 1520
46.2.18 RCEC MSI Mask Bit (RCEC_MSIMSK)—Offset 9Ch 1521
46.2.19 RCEC MSI Pending Bit (RCEC_MSIPENDING)—Offset A0h 1521
46.2.20 RCEC Advanced Error Reporting Extended Capability Header (RCEC_AERCAPHDR)—Offset 100h 1521
46.2.21 RCEC Uncorrectable Error Status (RCEC_ERRUNCSTS)—Offset 104h 1522
46.2.22 RCEC Correctable Error Status (RCEC_ERRCORSTS)—Offset 110h 1523
46.2.23 RCEC Correctable Error Mask (RCEC_ERRCORMSK)—Offset 114h 1524
46.2.24 RCEC Advanced Error Capabilities and Control (RCEC_AERCAPCTL)—Offset 118h 1525
46.2.25 RCEC Header Log (RCEC_AERHDRLOG1)—Offset 11Ch 1525
46.2.26 RCEC Header Log (RCEC_AERHDRLOG2)—Offset 120h 1526
46.2.27 RCEC Header Log (RCEC_AERHDRLOG3)—Offset 124h 1526
46.2.28 RCEC Header Log (RCEC_AERHDRLOG4)—Offset 128h 1526
46.2.29 RCEC Root Error Command (RCEC_ROOTERRCMD)—Offset 12Ch 1527
46.2.30 RCEC Root Error Status (RCEC_ROOTERRSTS)—Offset 130h 1528
46.2.31 RCEC Error Source Identification (RCEC_ERRSRCID)—Offset 134h 1529

47 RP - Intel® QuickAssist Technology - B0, D6/D22/D23, F0 1530
47.1 Introduction and Index 1530
47.1.1 Host Configuration Space 1531
47.2 Registers in Configuration Space 1534
47.2.1 VID—Offset 0h 1534
47.2.2 DID—Offset 2h 1534
47.2.3 PCICMD—Offset 4h 1535
47.2.4 PCISTS—Offset 6h 1536
47.2.5 CCR—Offset 9h 1537
47.2.6 CLS—Offset Ch 1537
47.2.7 IOBASE—Offset 1Ch 1538
47.2.8 IOLIMIT—Offset 1Dh 1538
47.2.9 MEMBASE—Offset 20h 1539
47.2.10 MEMLIMIT—Offset 22h 1540
47.2.11 PFBASE—Offset 24h 1541
47.2.12 PFLIMIT—Offset 26h 1542
47.2.13 PFBASEU—Offset 28h 1542
47.2.14 PFLIMITU—Offset 2Ch 1543
47.2.15 CAPPTR—Offset 34h 1543
47.2.16 INTL—Offset 3Ch 1544
47.2.17 INTP—Offset 3Dh 1544
47.2.18 BCTL—Offset 3Eh 1544
47.2.19 EXPCAPLST—Offset 40h 1546

47.2.20 EXPCAP—Offset 42h 1547
47.2.21 DEVCAP—Offset 44h 1548
47.2.22 DEVCTL—Offset 48h 1549
47.2.23 DEVSTS—Offset 4Ah 1550
47.2.24 LINKCAP—Offset 4Ch 1551
47.2.25 LINKCTL—Offset 50h 1553
47.2.26 LINKSTS—Offset 52h 1554
47.2.27 SLOTSTS—Offset 5Ah 1555
47.2.28 ROOTCTL—Offset 5Ch 1556
47.2.29 ROOTCAP—Offset 5Eh 1557
47.2.30 ROOTSTS—Offset 60h 1557
47.2.31 DEVCAP2—Offset 64h 1558
47.2.32 DEVCTL2—Offset 68h 1560
47.2.33 LINKCAP2—Offset 6Ch 1561
47.2.34 LINKCTL2—Offset 70h 1562
47.2.35 LINKSTS2—Offset 72h 1564
47.2.36 PMCAPLST—Offset 80h 1564
47.2.37 PMCAP—Offset 82h 1565
47.2.38 PMCSR—Offset 84h 1566
47.2.39 PMBSE—Offset 86h 1566
47.2.40 SSCAPLST—Offset 88h 1567
47.2.41 SSVID—Offset 8Ch 1568
47.2.42 SSID—Offset 8Eh 1568
47.2.43 MSICAPLST—Offset 90h 1569
47.2.44 MSICTL—Offset 92h 1569
47.2.45 MSIADDR—Offset 94h 1570
47.2.46 MSIDATA—Offset 98h 1570
47.2.47 MSIMSK—Offset 9Ch 1571
47.2.48 MSIPENDING—Offset A0h 1571
47.2.49 RPPMCSR—Offset A8h 1572
47.2.50 PMCSRS—Offset B0h 1572
47.2.51 SMICSR—Offset C8h 1573
47.2.52 SCICSR—Offset CCh 1573
47.2.53 PBTXNCTL—Offset D8h 1574
47.2.54 PLKCTL—Offset EAh 1574
47.2.55 LTRCSR—Offset ECh 1575
47.2.56 LTRL—Offset F0h 1576
47.2.57 LTROVR—Offset F4h 1577
47.2.58 INTXSWZCTL—Offset F8h 1578
47.2.59 AERCAPCTL—Offset 118h 1579
47.2.60 AERHDRLOG1—Offset 11Ch 1579
47.2.61 AERHDRLOG2—Offset 120h 1580
47.2.62 AERHDRLOG3—Offset 124h 1580
47.2.63 AERHDRLOG4—Offset 128h 1580
47.2.64 ROOTERRCMD—Offset 12Ch 1581
47.2.65 ROOTERRSTS—Offset 130h 1581
47.2.66 ERRSRCID—Offset 134h 1582
47.2.67 ACSCAPHDR—Offset 138h 1582
47.2.68 ACSCAP—Offset 13Ch 1583
47.2.69 ACSCTL—Offset 13Eh 1584
47.2.70 XPTDEF—Offset 2DCh 1585
47.2.71 XPTDEF2—Offset 2E0h 1587
47.2.72 IOSFDEVCLKGCTL—Offset 2E4h 1589
47.2.73 SBDEVCLKGCTL—Offset 2E6h 1589
47.2.74 IDFDEVCLKGCTL—Offset 2E8h 1590

48 PCI Express Root Ports - B0, D(9-12, 14-17), F0 1591
48.1 Introduction and Index 1591
48.1.1 Host Configuration Space 1592
48.1.2 Sideband Registers 1599
48.2 Registers in Configuration Space 1600
48.2.1 VID—Offset 0h 1600
48.2.2 DID—Offset 2h 1600
48.2.3 PCICMD—Offset 4h 1601
48.2.4 PCISTS—Offset 6h 1602
48.2.5 RID—Offset 8h 1603
48.2.6 CCR—Offset 9h 1603
48.2.7 CLS—Offset Ch 1604
48.2.8 PLAT—Offset Dh 1604
48.2.9 HDR—Offset Eh 1604
48.2.10 BIST—Offset Fh 1605
48.2.11 PRIBUS—Offset 18h 1605
48.2.12 SECBUS—Offset 19h 1606
48.2.13 SUBBUS—Offset 1Ah 1606
48.2.14 IOBASE—Offset 1Ch 1607
48.2.15 IOLIMIT—Offset 1Dh 1607
48.2.16 SECSTS—Offset 1Eh 1608
48.2.17 MEMBASE—Offset 20h 1609
48.2.18 MEMLIMIT—Offset 22h 1610
48.2.19 PFBASE—Offset 24h 1611
48.2.20 PFLIMIT—Offset 26h 1612
48.2.21 PFBASEU—Offset 28h 1612
48.2.22 PFLIMITU—Offset 2Ch 1613
48.2.23 CAPPTR—Offset 34h 1613
48.2.24 INTL—Offset 3Ch 1614
48.2.25 INTP—Offset 3Dh 1614
48.2.26 BCTL—Offset 3Eh 1615
48.2.27 EXPCAPLST—Offset 40h 1617
48.2.28 EXPCAP—Offset 42h 1617
48.2.29 DEVCAP—Offset 44h 1618
48.2.30 DEVCTL—Offset 48h 1619
48.2.31 DEVSTS—Offset 4Ah 1620
48.2.32 LINKCAP—Offset 4Ch 1621
48.2.33 LINKCTL—Offset 50h 1623
48.2.34 LINKSTS—Offset 52h 1625
48.2.35 SLOTCAP—Offset 54h 1626
48.2.36 SLOTCTL—Offset 58h 1628
48.2.37 SLOTSTS—Offset 5Ah 1630
48.2.38 ROOTCTL—Offset 5Ch 1632
48.2.39 ROOTCAP—Offset 5Eh 1633
48.2.40 ROOTSTS—Offset 60h 1633
48.2.41 DEVCAP2—Offset 64h 1634
48.2.42 DEVCTL2—Offset 68h 1637
48.2.43 LINKCAP2—Offset 6Ch 1639
48.2.44 LINKCTL2—Offset 70h 1640
48.2.45 LINKSTS2—Offset 72h 1642
48.2.46 PMCAPLST—Offset 80h 1642
48.2.47 PMCAP—Offset 82h 1643
48.2.48 PMCSR—Offset 84h 1644
48.2.49 PMBSE—Offset 86h 1644
48.2.50 SSCAPLST—Offset 88h 1645

48.2.51 SSVID—Offset 8Ch....1646
48.2.52 SSID—Offset 8Eh....1646
48.2.53 MSICAPLST—Offset 90h....1646
48.2.54 MSICTL—Offset 92h....1647
48.2.55 MSIADDR—Offset 94h....1647
48.2.56 MSIDATA—Offset 98h....1648
48.2.57 MSIMSK—Offset 9Ch....1649
48.2.58 MSIPENDING—Offset A0h....1649
48.2.59 RPPMCSR—Offset A8h....1650
48.2.60 PMCSRS—Offset B0h....1652
48.2.61 PPBIFCTL—Offset C0h....1652
48.2.62 SMICSR—Offset C8h....1653
48.2.63 SCICSR—Offset CCh....1654
48.2.64 SSCTL—Offset D0h....1655
48.2.65 EXPPTMBARCTL—Offset D2h....1656
48.2.66 PPD0—Offset D4h....1657
48.2.67 PBTXNCTL—Offset D8h....1659
48.2.68 PBPHYCTL—Offset E0h....1660
48.2.69 PLKCTL—Offset EAh....1660
48.2.70 LTRCSR—Offset ECh....1661
48.2.71 LTRL—Offset F0h....1662
48.2.72 LTROVR—Offset F4h....1663
48.2.73 INTXSWZCTL—Offset F8h....1664
48.2.74 CFGAGTERR—Offset FCh....1665
48.2.75 AERCAPHDR—Offset 100h....1666
48.2.76 ERRUNCSTS—Offset 104h....1667
48.2.77 ERRUNCMSK—Offset 108h....1669
48.2.78 ERRUNCSEV—Offset 10Ch....1671
48.2.79 ERRCORSTS—Offset 110h....1673
48.2.80 ERRCORMSK—Offset 114h....1674
48.2.81 AERCAPCTL—Offset 118h....1675
48.2.82 AERHDRLOG1—Offset 11Ch....1676
48.2.83 AERHDRLOG2—Offset 120h....1676
48.2.84 AERHDRLOG3—Offset 124h....1676
48.2.85 AERHDRLOG4—Offset 128h....1677
48.2.86 ROOTERRCMD—Offset 12Ch....1677
48.2.87 ROOTERRSTS—Offset 130h....1678
48.2.88 ERRSRCID—Offset 134h....1679
48.2.89 ACSCAPHDR—Offset 138h....1679
48.2.90 ACSCAP—Offset 13Ch....1680
48.2.91 ACSCTL—Offset 13Eh....1681
48.2.92 ERRUNCDETMSK—Offset 140h....1682
48.2.93 ERRCORDETMSK—Offset 144h....1683
48.2.94 ROOTERRDETMSK—Offset 148h....1683
48.2.95 MCSTCAPHDR—Offset 150h....1684
48.2.96 MCSTCAP—Offset 154h....1684
48.2.97 MCSTCTL—Offset 156h....1684
48.2.98 MCSTBAR—Offset 158h....1685
48.2.99 MCSTUBAR—Offset 15Ch....1685
48.2.100 MCSTRCV—Offset 160h....1685
48.2.101 MCSTBLKALL—Offset 168h....1686
48.2.102 MCSTOLBAR—Offset 178h....1686
48.2.103 MCSTUOLBAR—Offset 17Ch....1686
48.2.104 EINJCAPHDR—Offset 180h....1687
48.2.105 EINJHDR—Offset 184h....1687

48.2.106 EINJCTL—Offset 188h 1688
48.2.107 SECEXPCAP—Offset 200h 1689
48.2.108 LINKCTL3—Offset 204h 1690
48.2.109 LANEERRSTS—Offset 208h 1691
48.2.110 LANEEQCTL0—Offset 20Ch 1692
48.2.111 LANEEQCTL1—Offset 20Eh 1694
48.2.112 LANEEQCTL2—Offset 210h 1696
48.2.113 LANEEQCTL3—Offset 212h 1698
48.2.114 LANEEQCTL4—Offset 214h 1700
48.2.115 LANEEQCTL5—Offset 216h 1702
48.2.116 LANEEQCTL6—Offset 218h 1704
48.2.117 LANEEQCTL7—Offset 21Ah 1706
48.2.118 XPPMDL0—Offset 280h 1708
48.2.119 XPPMDL1—Offset 284h 1708
48.2.120 XPPMCL0—Offset 288h 1708
48.2.121 XPPMCL1—Offset 28Ch 1708
48.2.122 XPPMDH—Offset 290h 1709
48.2.123 XPPMCH—Offset 292h 1709
48.2.124 XPPMR0—Offset 294h 1710
48.2.125 XPPMR1—Offset 298h 1713
48.2.126 XPPMEVL0—Offset 29Ch 1716
48.2.127 XPPMEVL1—Offset 2A0h 1718
48.2.128 XPPMEVH0—Offset 2A4h 1720
48.2.129 XPPMEVH1—Offset 2A8h 1721
48.2.130 XPPMER0—Offset 2ACh 1722
48.2.131 XPPMER1—Offset 2B0h 1724
48.2.132 XPPMDFXMAT0—Offset 2B4h 1726
48.2.133 XPPMDFXMAT1—Offset 2B8h 1727
48.2.134 XPPMDFXMSK0—Offset 2BCh 1728
48.2.135 XPPMDFXMSK1—Offset 2C0h 1728
48.2.136 XPPERFCON—Offset 2C4h 1729
48.2.137 XPPERFSTAT—Offset 2C8h 1730
48.2.138 XPCDTHROTTLEP—Offset 2D0h 1730
48.2.139 XPCDTHROTTLEN—Offset 2D4h 1731
48.2.140 XPCDTHROTTLEC—Offset 2D8h 1731
48.2.141 IOSFDEVCLKGCTL—Offset 2E4h 1732
48.2.142 SBDEVCLKGCTL—Offset 2E6h 1732
48.2.143 VDHDRCAP—Offset 300h 1733
48.2.144 IBSTHDRCAP—Offset 304h 1733
48.2.145 IBSTENGLKSPDCAP—Offset 310h 1734
48.2.146 IBSTENGLKSPDCTL—Offset 314h 1735
48.2.147 IBSTENGLKTXRXCFG—Offset 31Ch 1736
48.2.148 IBSTERRCRCSTS0—Offset 320h 1736
48.2.149 IBSTERRRCRVSTS0—Offset 324h 1737
48.2.150 IBSTERRCRCSTS1—Offset 328h 1737
48.2.151 IBSTERRRCRVSTS1—Offset 32Ch 1738
48.2.152 IBSTERRCRCSTS2—Offset 330h 1738
48.2.153 IBSTERRRCRVSTS2—Offset 334h 1739
48.2.154 IBSTERRCRCSTS3—Offset 338h 1739
48.2.155 IBSTERRRCRVSTS3—Offset 33Ch 1740
48.2.156 IBSTPHYLCTL0—Offset 344h 1741
48.2.157 IBSTPHYLCTL1—Offset 348h 1742
48.2.158 IBSTPHYLCTL2—Offset 34Ch 1743
48.2.159 IBSTPHYLCTL3—Offset 350h 1744
48.2.160 IBSTTXLCTL—Offset 354h 1745

48.2.161 IBSTTDSTS—Offset 358h 1745
48.2.162 IBSTPLLNSTS0—Offset 36Ch 1746
48.2.163 IBSTPRECFG0—Offset 370h....1747
48.2.164 IBSTPOSTCFG0—Offset 374h....1748
48.2.165 IBSTPLLNSTS1—Offset 378h 1749
48.2.166 IBSTPRECFG1—Offset 37Ch 1750
48.2.167 IBSTPOSTCFG1—Offset 380h....1751
48.2.168 TLPCIECLKGCTL—Offset 8E0h....1751
48.2.169 TLPCIECLKGCCTL—Offset 8E2h....1752
48.2.170 PT0TXNCLKGCTL—Offset 8E4h....1752
48.2.171 PT1TXNCLKGCTL—Offset 8E6h....1753
48.2.172 PT2TXNCLKGCTL—Offset 8E8h....1753
48.2.173 PT3TXNCLKGCTL—Offset 8EAh 1754
48.2.174 XPTDEF2—Offset 8F8h....1755
48.2.175 PMIDLTMR—Offset 948h 1757
48.2.176 LLRBSIZE—Offset 98Ch 1758
48.2.177 FRMERRMSK—Offset 99Ch 1759
48.2.178 FRMERRSTS—Offset 99Eh 1760
48.2.179 LLPCIECLKGCTL—Offset 9E0h....1760
48.2.180 LLPCIECLKGCCTL—Offset 9E2h....1761
48.2.181 PT0LNKCLKGCTL—Offset 9E4h....1761
48.2.182 PT1LNKCLKGCTL—Offset 9E6h....1762
48.2.183 PT2LNKCLKGCTL—Offset 9E8h....1762
48.2.184 PT3LNKCLKGCTL—Offset 9EAh....1763
48.2.185 CFGPCIECLKGCTL—Offset 9ECh 1763
48.2.186 CFGPCIECLKGCCTL—Offset 9EEh 1763
48.2.187 LTSSMSMSTS—Offset A68h....1764
48.2.188 LTSSMLNSTS0—Offset A70h....1765
48.2.189 LTSSMSTATELOG0—Offset A80h 1765
48.2.190 LTSSMSTATELOG1—Offset A84h 1765
48.2.191 LTSSMSTATELOG2—Offset A88h 1766
48.2.192 LTSSMSTATELOGCTL—Offset A8Ch 1766
48.2.193 LTLNERRCTRL—Offset A94h 1766
48.2.194 LTLNERRSTS—Offset A96h 1767
48.2.195 LTLNERRLOG—Offset A98h....1768
48.2.196 UPCFGCSR—Offset AB8h....1769
48.2.197 SOSCTL—Offset AC8h....1770
48.2.198 G3SOSERRSTS—Offset ACCh....1770
48.2.199 PLPCIECLKGCTL—Offset AE0h....1770
48.2.200 PLPCIECLKGCCTL—Offset AE2h....1771
48.2.201 PT0PHYCLKGCTL—Offset AE4h....1771
48.2.202 PT1PHYCLKGCTL—Offset AE6h....1772
48.2.203 PT2PHYCLKGCTL—Offset AE8h....1772
48.2.204 PT3PHYCLKGCTL—Offset AEAh....1773
48.2.205 LTLGCAP—Offset B00h 1773
48.2.206 LTLGCTRL—Offset B04h....1774
48.2.207 LTLGSTART0—Offset B08h 1775
48.2.208 LTLGSTART1—Offset B0Ch 1776
48.2.209 LTLGSTART2—Offset B10h 1777
48.2.210 LTLGSTART3—Offset B14h 1778
48.2.211 LTLGSTP0—Offset B18h 1779
48.2.212 LTLGSTP1—Offset B1Ch....1779
48.2.213 LTLGSTP2—Offset B20h 1780
48.2.214 LTLGSTP3—Offset B24h 1780
48.2.215 LTLGTMEV0—Offset B28h....1781

48.2.216 LTLGTMEV1—Offset B2Ch 1782
48.2.217 LTLGTMEV2—Offset B30h 1783
48.2.218 LTLGTMEV3—Offset B34h 1784
48.2.219 LTLGRDCT—Offset B40h 1784
48.2.220 LTLGRES—Offset B44h 1785
48.2.221 LTLGSMEV0—Offset B48h 1785
48.2.222 LTLGSMEV1—Offset B4Ch 1786
48.2.223 NFTSCOMCLK—Offset B50h 1786
48.2.224 NFTSDSCCLK—Offset B54h 1787
48.2.225 LEKBERR—Offset B58h 1787
48.2.226 EXPBERR0—Offset B5Ch 1787
48.2.227 EXPBERR1—Offset B60h 1788
48.2.228 LEKBPROERR—Offset B64h 1788
48.2.229 SPEEDCTL—Offset B68h 1789
48.2.230 RCVRDETSTS—Offset B6Ch 1791
48.2.231 RCVRERR—Offset B70h 1791
48.2.232 EBERR—Offset B74h 1792
48.2.233 EBERRMSK—Offset B78h 1792
48.2.234 OBEINJCTL—Offset B7Ch 1793
48.2.235 LTSSMERRSTS0—Offset B80h 1795
48.2.236 LTSSMERRSTS1—Offset B84h 1797
48.2.237 EQEVALCTL6—Offset B8Ch 1798
48.2.238 EQEVALCTL7—Offset B90h 1799
48.2.239 EQFARFSLF—Offset B9Ch 1800
48.2.240 FOMINCCTL—Offset BA4h 1801
48.2.241 PHYRECAL—Offset BA8h 1801
48.2.242 PLLSTBYCTL—Offset BACh 1802
48.2.243 PLUTXEQCTL—Offset BB0h 1802
48.2.244 PHYCGIDLEMSK—Offset BB4h 1803
48.2.245 EQEVALCTL4—Offset BB8h 1804
48.2.246 EQEVALCTL5—Offset BBCh 1805
48.2.247 LEKBLNERRCNT0—Offset BC0h 1805
48.2.248 LEKBLNERRCNT1—Offset BC4h 1806
48.2.249 EQEVALCTL—Offset BD0h 1806
48.2.250 EQEVALCTL2—Offset BD4h 1807
48.2.251 EQEVALCTL3—Offset BD8h 1808
48.2.252 EQEVALSTS—Offset BDCh 1809
48.2.253 EQEVALSTS2—Offset BE0h 1811
48.2.254 EQEVALSTS3—Offset BE4h 1812
48.2.255 G3FRAMEERR—Offset BECh 1814
48.3 Sideband Registers - Devices 9-12 1815
48.3.1 PPBIFCTL_PRIV—Offset 10h 1815
48.4 Sideband Registers - Devices 14-17 1816
48.4.1 PPBIFCTL_PRIV—Offset 10h 1816

49 SMBus - Host - B0, D18, F0 1817
49.1 Introduction and Index 1817
49.1.1 Host Configuration Space 1818
49.1.2 Host Memory Space—SMTBAR 1819
49.2 Registers in Configuration Space 1820
49.2.1 VID—Offset 0h 1820
49.2.2 DID—Offset 2h 1820
49.2.3 PCICMD—Offset 4h 1821
49.2.4 PCISTS—Offset 6h 1822
49.2.5 RID—Offset 8h 1823

49.2.6 CCR—Offset 9h 1823
49.2.7 SMTBAR—Offset 10h 1824
49.2.8 SVID—Offset 2Ch 1824
49.2.9 SID—Offset 2Eh 1825
49.2.10 INTL—Offset 3Ch 1825
49.2.11 INTP—Offset 3Dh 1826
49.2.12 EXPCAPLST—Offset 40h 1826
49.2.13 DEVCAP—Offset 44h 1827
49.2.14 DEVCTL—Offset 48h 1829
49.2.15 DEVSTS—Offset 4Ah 1830
49.2.16 PMCAPLST—Offset 80h 1831
49.2.17 MSICAPLST—Offset 8Ch 1831
49.2.18 MSICTL—Offset 8Eh 1832
49.2.19 MSIADDR—Offset 90h 1832
49.2.20 MSIDATA—Offset 98h 1833
49.2.21 MSIMSK—Offset 9Ch 1834
49.2.22 PLKCTL—Offset EAh 1834
49.3 Registers in Memory Space—SMTBAR 1835
49.3.1 GCTRL—Offset 0h 1835
49.3.2 SMTICL—Offset 8h 1836
49.3.3 ERRINTMSK—Offset 10h 1837
49.3.4 ERRAERMSK—Offset 14h 1838
49.3.5 ERRSTS—Offset 18h 1839
49.3.6 ERRINFO—Offset 1Ch 1840
49.3.7 MDBA—Offset 100h 1840
49.3.8 MCTRL—Offset 108h 1841
49.3.9 MSTS—Offset 10Ch 1842
49.3.10 MDS—Offset 110h 1843
49.3.11 RPOLICY—Offset 114h 1844
49.3.12 TBBA—Offset 200h 1846
49.3.13 TCTRL—Offset 208h 1847
49.3.14 TSTS—Offset 20Ch 1848
49.3.15 TBS—Offset 210h 1849
49.3.16 HTHP—Offset 218h 1849
49.3.17 FTTP—Offset 21Ch 1850
49.3.18 TRxCTRL—Offset 220h 1850
49.3.19 TRxSTS—Offset 224h 1851
49.3.20 TACTRL—Offset 228h 1852
49.3.21 TPOLICY—Offset 22Ch 1853
49.3.22 GPBRCTRL—Offset 240h 1855
49.3.23 GPBRDBUF—Offset 244h 1856
49.3.24 SMTARPCTRL—Offset 280h 1857
49.3.25 UDID0—Offset 290h 1858
49.3.26 UUDID0—Offset 298h 1859
49.3.27 UDID1—Offset 2A0h 1860
49.3.28 UUDID1—Offset 2A8h 1861
49.3.29 SPGT—Offset 300h 1862
49.3.30 SPMT—Offset 304h 1863
49.3.31 SPST—Offset 308h 1864
49.3.32 SMBFT—Offset 30Ch 1865
49.3.33 CLTC—Offset 310h 1866
49.3.34 DCLKGT—Offset 380h 1866
49.3.35 SUSCHKB—Offset 384h 1867
49.3.36 DBCTRL—Offset 388h 1868
49.3.37 DBSTS—Offset 38Ch 1869

50 SATA Controllers - B0, D(19, 20), F0 1870
50.1 Introduction and Index 1870
50.1.1 Host Configuration Space 1871
50.1.2 Host Memory Space—MXTBA 1873
50.1.3 Host Memory Space—ABAR 1874
50.2 Registers in Configuration Space 1879
50.2.1 Identifiers (ID)—Offset 0h 1879
50.2.2 Command (CMD)—Offset 4h 1880
50.2.3 Device Status (STS)—Offset 6h 1881
50.2.4 Revision ID (RID)—Offset 8h 1882
50.2.5 Programming Interface (PI)—Offset 9h 1882
50.2.6 Class Code (CC)—Offset Ah 1882
50.2.7 MSI-X Table Base Address (MXTBA)—Offset 10h 1883
50.2.8 SCMDBA—Offset 18h 1884
50.2.9 SCTLBA—Offset 1Ch 1884
50.2.10 AHCI Index Data Pair Base Address (AIDPBA)—Offset 20h 1885
50.2.11 AHCI Base Address (ABAR)—Offset 24h 1886
50.2.12 Capabilities Pointer (CAP)—Offset 34h 1887
50.2.13 Interrupt Information (INTR)—Offset 3Ch 1887
50.2.14 PCI Power Management Capability ID (PID)—Offset 70h 1887
50.2.15 PCI Power Management Capabilities (PC)—Offset 72h 1888
50.2.16 PCI Power Management Control and Status (PMCS)—Offset 74h 1889
50.2.17 Message Signaled Interrupt Identifier (MID)—Offset 80h 1889
50.2.18 Message Signaled Interrupt Message Control (MC)—Offset 82h 1890
50.2.19 Message Signaled Interrupt Message Address (MA)—Offset 84h 1890
50.2.20 Message Signaled Interrupt Message Data (MD)—Offset 88h 1890
50.2.21 Port Mapping Register (MAP)—Offset 90h 1891
50.2.22 Port Control and Status (PCS)—Offset 94h 1893
50.2.23 SATA General Configuration (SATAGC)—Offset 9Ch 1895
50.2.24 SATA Initialization Register Index (SIRI)—Offset A0h 1896
50.2.25 SATA Initialization Register Data (SIRD)—Offset A4h 1896
50.2.26 Serial ATA Capability Register 0 (SATACR0)—Offset A8h 1897
50.2.27 Serial ATA Capability Register 1 (SATACR1)—Offset ACh 1898
50.2.28 FLR Capability ID (FLRCID)—Offset B0h 1898
50.2.29 FLR Control (FLRCTL)—Offset B4h 1899
50.2.30 MSI-X Message Control (MXC)—Offset D2h 1900
50.2.31 MSI-X Table Offset / Table BIR (MXT)—Offset D4h 1900
50.2.32 MSI-X PBA Offset / PBA BIR (MXP)—Offset D8h 1900
50.2.33 BIST FIS Control/Status (BFCS)—Offset E0h 1901
50.2.34 BIST FIS Transmit Data 1 (BFTD1)—Offset E4h 1903
50.2.35 BIST FIS Transmit Data 2 (BFTD2)—Offset E8h 1903
50.2.36 Manufacturing ID (MFID)—Offset F8h 1903
50.3 Registers in Memory Space—MXTBA 1904
50.3.1 MSI-X Table Entries n Message Lower Address (MXTEnMLA) 1904
50.3.2 MSI-X Table Entries n Message Upper Address (MXTEnMUA) 1904
50.3.3 MSI-X Table Entries n Message Data (MXTEnMD) 1905
50.4 Registers in Memory Space—ABAR 1906
50.4.1 HBA Capabilities (GHC_CAP)—Offset 0h 1906
50.4.2 Global HBA Control (GHC)—Offset 4h 1908
50.4.3 Interrupt Status Register (IS)—Offset 8h 1909
50.4.4 Ports Implemented (GHC_PI)—Offset Ch 1910
50.4.5 AHCI Version (VS)—Offset 10h 1911
50.4.6 Enclosure Management Control (EM_CTL)—Offset 20h 1912
50.4.7 HBA Capabilities Extended (GHC_CAP2)—Offset 24h 1914
50.4.8 Vendor Specific (VSP)—Offset A0h 1915

50.4.9 Vendor Specific Capabilities Register (VS_CAP)—Offset A4h 1916
50.4.10 RAID Platform ID (RPID)—Offset C0h 1917
50.4.11 SW Feature Mask (SFM)—Offset C8h 1918
50.4.12 Port [0-7] Command List Base Address (PxCLB0)—Offset 100h 1919
50.4.13 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU0)—Offset 104h 1919
50.4.14 Port [0-7] FIS Base Address (PxFB0)—Offset 108h 1920
50.4.15 Port [0-7] FIS Base Address Upper 32-bits (PxFBU0)—Offset 10Ch 1920
50.4.16 Port [0-7] Interrupt Status (PxIS0)—Offset 110h 1921
50.4.17 Port [0-7] Interrupt Enable (PxIE0)—Offset 114h 1923
50.4.18 Port [0-7] Command (PxCMD0)—Offset 118h 1924
50.4.19 Port [0-7] Serial ATA Status (PxSSTS0)—Offset 128h 1926
50.4.20 Port [0-7] Serial ATA Control (PxSCTL0)—Offset 12Ch 1926
50.4.21 Port [0-7] Serial ATA Error (PxSERR0)—Offset 130h 1927
50.4.22 Port [0-7] Serial ATA Active (PxSACT0)—Offset 134h 1927
50.4.23 Port [0-7] Commands Issued (PxCI0)—Offset 138h 1927
50.4.24 Port [0-7] SNotification (PxSNTF0)—Offset 13Ch 1928
50.4.25 Port [0-7] Command List Base Address (PxCLB1)—Offset 180h 1928
50.4.26 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU1)—Offset 184h 1928
50.4.27 Port [0-7] FIS Base Address (PxFB1)—Offset 188h 1929
50.4.28 Port [0-7] FIS Base Address Upper 32-bits (PxFBU1)—Offset 18Ch 1929
50.4.29 Port [0-7] Interrupt Status (PxIS1)—Offset 190h 1930
50.4.30 Port [0-7] Interrupt Enable (PxIE1)—Offset 194h 1932
50.4.31 Port [0-7] Command (PxCMD1)—Offset 198h 1933
50.4.32 Port [0-7] Serial ATA Status (PxSSTS1)—Offset 1A8h 1935
50.4.33 Port [0-7] Serial ATA Control (PxSCTL1)—Offset 1ACh 1935
50.4.34 Port [0-7] Serial ATA Error (PxSERR1)—Offset 1B0h 1936
50.4.35 Port [0-7] Serial ATA Active (PxSACT1)—Offset 1B4h 1936
50.4.36 Port [0-7] Commands Issued (PxCI1)—Offset 1B8h 1936
50.4.37 Port [0-7] SNotification (PxSNTF1)—Offset 1BCh 1937
50.4.38 Port [0-7] Command List Base Address (PxCLB2)—Offset 200h 1937
50.4.39 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU2)—Offset 204h 1937
50.4.40 Port [0-7] FIS Base Address (PxFB2)—Offset 208h 1938
50.4.41 Port [0-7] FIS Base Address Upper 32-bits (PxFBU2)—Offset 20Ch 1938
50.4.42 Port [0-7] Interrupt Status (PxIS2)—Offset 210h 1939
50.4.43 Port [0-7] Interrupt Enable (PxIE2)—Offset 214h 1941
50.4.44 Port [0-7] Command (PxCMD2)—Offset 218h 1942
50.4.45 Port [0-7] Serial ATA Status (PxSSTS2)—Offset 228h 1944
50.4.46 Port [0-7] Serial ATA Control (PxSCTL2)—Offset 22Ch 1944
50.4.47 Port [0-7] Serial ATA Error (PxSERR2)—Offset 230h 1945
50.4.48 Port [0-7] Serial ATA Active (PxSACT2)—Offset 234h 1945
50.4.49 Port [0-7] Commands Issued (PxCI2)—Offset 238h 1945
50.4.50 Port [0-7] SNotification (PxSNTF2)—Offset 23Ch 1946
50.4.51 Port [0-7] Command List Base Address (PxCLB3)—Offset 280h 1946
50.4.52 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU3)—Offset 284h 1946
50.4.53 Port [0-7] FIS Base Address (PxFB3)—Offset 288h 1947
50.4.54 Port [0-7] FIS Base Address Upper 32-bits (PxFBU3)—Offset 28Ch 1947
50.4.55 Port [0-7] Interrupt Status (PxIS3)—Offset 290h 1948
50.4.56 Port [0-7] Interrupt Enable (PxIE3)—Offset 294h 1950
50.4.57 Port [0-7] Command (PxCMD3)—Offset 298h 1951
50.4.58 Port [0-7] Serial ATA Status (PxSSTS3)—Offset 2A8h 1953
50.4.59 Port [0-7] Serial ATA Control (PxSCTL3)—Offset 2ACh 1953

50.4.60 Port [0-7] Serial ATA Error (PxSERR3)—Offset 2B0h 1954
50.4.61 Port [0-7] Serial ATA Active (PxSACT3)—Offset 2B4h 1954
50.4.62 Port [0-7] Commands Issued (PxCI3)—Offset 2B8h 1954
50.4.63 Port [0-7] SNotification (PxSNTF3)—Offset 2BCh 1955
50.4.64 Port [0-7] Command List Base Address (PxCLB4)—Offset 300h 1955
50.4.65 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU4)—Offset 304h..... 1955
50.4.66 Port [0-7] FIS Base Address (PxFB4)—Offset 308h..... 1956
50.4.67 Port [0-7] FIS Base Address Upper 32-bits (PxFBU4)—Offset 30Ch 1956
50.4.68 Port [0-7] Interrupt Status (PxIS4)—Offset 310h..... 1957
50.4.69 Port [0-7] Interrupt Enable (PxIE4)—Offset 314h..... 1959
50.4.70 Port [0-7] Command (PxCMD4)—Offset 318h..... 1960
50.4.71 Port [0-7] Serial ATA Status (PxSSTS4)—Offset 328h..... 1962
50.4.72 Port [0-7] Serial ATA Control (PxSCTL4)—Offset 32Ch..... 1962
50.4.73 Port [0-7] Serial ATA Error (PxSERR4)—Offset 330h..... 1963
50.4.74 Port [0-7] Serial ATA Active (PxSACT4)—Offset 334h 1963
50.4.75 Port [0-7] Commands Issued (PxCI4)—Offset 338h..... 1963
50.4.76 Port [0-7] SNotification (PxSNTF4)—Offset 33Ch 1964
50.4.77 Port [0-7] Command List Base Address (PxCLB5)—Offset 380h 1964
50.4.78 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU5)—Offset 384h..... 1964
50.4.79 Port [0-7] FIS Base Address (PxFB5)—Offset 388h..... 1965
50.4.80 Port [0-7] FIS Base Address Upper 32-bits (PxFBU5)—Offset 38Ch 1965
50.4.81 Port [0-7] Interrupt Status (PxIS5)—Offset 390h..... 1966
50.4.82 Port [0-7] Interrupt Enable (PxIE5)—Offset 394h..... 1968
50.4.83 Port [0-7] Serial ATA Status (PxSSTS5)—Offset 3A8h..... 1969
50.4.84 Port [0-7] Serial ATA Control (PxSCTL5)—Offset 3ACh..... 1969
50.4.85 Port [0-7] Serial ATA Error (PxSERR5)—Offset 3B0h 1970
50.4.86 Port [0-7] Serial ATA Active (PxSACT5)—Offset 3B4h 1970
50.4.87 Port [0-7] Commands Issued (PxCI5)—Offset 3B8h 1970
50.4.88 Port [0-7] SNotification (PxSNTF5)—Offset 3BCh 1971
50.4.89 Port [0-7] Device Sleep (PxDEVSLP5)—Offset 3C4h 1972
50.4.90 Port [0-7] Command List Base Address (PxCLB6)—Offset 400h 1972
50.4.91 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU6)—Offset 404h..... 1973
50.4.92 Port [0-7] FIS Base Address (PxFB6)—Offset 408h..... 1973
50.4.93 Port [0-7] FIS Base Address Upper 32-bits (PxFBU6)—Offset 40Ch 1973
50.4.94 Port [0-7] Interrupt Status (PxIS6)—Offset 410h..... 1974
50.4.95 Port [0-7] Interrupt Enable (PxIE6)—Offset 414h..... 1976
50.4.96 Port [0-7] Command (PxCMD6)—Offset 418h..... 1977
50.4.97 Port [0-7] Task File Data (PxTFD6)—Offset 420h 1979
50.4.98 Port [0-7] Signature (PxSIG6)—Offset 424h..... 1979
50.4.99 Port [0-7] Serial ATA Status (PxSSTS6)—Offset 428h..... 1980
50.4.100 Port [0-7] Serial ATA Control (PxSCTL6)—Offset 42Ch..... 1980
50.4.101 Port [0-7] Serial ATA Error (PxSERR6)—Offset 430h..... 1981
50.4.102 Port [0-7] Serial ATA Active (PxSACT6)—Offset 434h 1981
50.4.103 Port [0-7] Commands Issued (PxCI6)—Offset 438h..... 1981
50.4.104 Port [0-7] SNotification (PxSNTF6)—Offset 43Ch 1982
50.4.105 Port [0-7] Device Sleep (PxDEVSLP6)—Offset 444h..... 1982
50.4.106 Port [0-7] Command List Base Address (PxCLB7)—Offset 480h 1983
50.4.107 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU7)—Offset 484h..... 1983
50.4.108 Port [0-7] FIS Base Address (PxFB7)—Offset 488h..... 1984
50.4.109 Port [0-7] FIS Base Address Upper 32-bits (PxFBU7)—Offset 48Ch 1984
50.4.110 Port [0-7] Interrupt Status (PxIS7)—Offset 490h..... 1985

50.4.111 Port [0-7] Interrupt Enable (PxIE7)—Offset 494h 1987
50.4.112 Port [0-7] Command (PxCMD7)—Offset 498h 1988
50.4.113 Port [0-7] Task File Data (PxTFD7)—Offset 4A0h 1990
50.4.114 Port [0-7] Signature (PxSIG7)—Offset 4A4h 1990
50.4.115 Port [0-7] Serial ATA Status (PxSSTS7)—Offset 4A8h 1991
50.4.116 Port [0-7] Serial ATA Control (PxSCTL7)—Offset 4ACh 1991
50.4.117 Port [0-7] Serial ATA Error (PxSERR7)—Offset 4B0h 1992
50.4.118 Port [0-7] Serial ATA Active (PxSACT7)—Offset 4B4h 1992
50.4.119 Port [0-7] Commands Issued (PxCI7)—Offset 4B8h 1992
50.4.120 Port [0-7] SNotification (PxSNTF7)—Offset 4BCh 1993
50.4.121 Enclosure Management Message Format (EM_MF)—Offset 580h 1993
50.4.122 Enclosure Management LED (EM_LED)—Offset 584h 1994

51 USB Combo Controller - B0, D21, F0 1995
51.1 Introduction and Index 1995
51.1.1 Host Configuration Space 1996
51.1.2 Host Memory Space—MBAR 1998
51.2 Registers in Configuration Space 2006
51.2.1 Vendor ID (VID)—Offset 0h 2006
51.2.2 Device ID (DID)—Offset 2h 2006
51.2.3 Command (CMD)—Offset 4h 2007
51.2.4 Device Status (STS)—Offset 6h 2008
51.2.5 Revision ID (RID)—Offset 8h 2010
51.2.6 Programming Interface (PI)—Offset 9h 2010
51.2.7 Sub Class Code (SCC)—Offset Ah 2010
51.2.8 Base Class Code (BCC)—Offset Bh 2010
51.2.9 Master Latency Timer (MLT)—Offset Dh 2011
51.2.10 Header Type (HT)—Offset Eh 2011
51.2.11 Memory Base Address (MBAR)—Offset 10h 2012
51.2.12 USB Subsystem Vendor ID (SSVID)—Offset 2Ch 2012
51.2.13 USB Subsystem ID (SSID)—Offset 2Eh 2013
51.2.14 Capabilities Pointer (CAP_PTR)—Offset 34h 2013
51.2.15 Interrupt Line (ILINE)—Offset 3Ch 2013
51.2.16 Interrupt Pin (IPIN)—Offset 3Dh 2014
51.2.17 XHC System Bus Configuration 1 (XHCC1)—Offset 40h 2014
51.2.18 XHC System Bus Configuration 2 (XHCC2)—Offset 44h 2016
51.2.19 Clock Gating (XHCLKGTEN)—Offset 50h 2018
51.2.20 Audio Time Synchronization (AUDSYNC)—Offset 58h 2021
51.2.21 Serial Bus Release Number (SBRN)—Offset 60h 2021
51.2.22 Frame Length Adjustment (FLADJ)—Offset 61h 2022
51.2.23 Best Effort Service Latency (BESL)—Offset 62h 2023
51.2.24 PCI Power Management Capability ID (PM_CID)—Offset 70h 2023
51.2.25 Next Item Pointer #1 (PM_NEXT)—Offset 71h 2023
51.2.26 Power Management Capabilities (PM_CAP)—Offset 72h 2024
51.2.27 Power Management Control/Status (PM_CS)—Offset 74h 2025
51.2.28 Message Signaled Interrupt CID (MSI_CID)—Offset 80h 2026
51.2.29 Next item pointer (MSI_NEXT)—Offset 81h 2026
51.2.30 Message Signaled Interrupt Message Control (MSI_MCTL)—Offset 82h 2027
51.2.31 Message Signaled Interrupt Message Address (MSI_MAD)—Offset 84h 2028
51.2.32 Message Signaled Interrupt Upper Address (MSI_MUAD)—Offset 88h 2028
51.2.33 Message Signaled Interrupt Message Data (MSI_MD)—Offset 8Ch 2028
51.2.34 Device Idle Capability (DEVIDLE)—Offset 90h 2029
51.2.35 Vendor Specific Header (VSHDR)—Offset 94h 2029
51.2.36 SW LTR POINTER (SWLTRPTR)—Offset 98h 2030
51.2.37 Device Idle Pointer Register (DEVIDLEPTR)—Offset 9Ch 2030

51.2.38 Device Idle Power ON Latency (DEVIDLEPOL)—Offset A0h 2031
51.2.39 High Speed Configuration 2 (HSCFG2)—Offset A4h 2032
51.2.40 XHCI USB2 Overcurrent Pin Mapping 1 (U2OCM1)—Offset B0h 2033
51.2.41 XHCI USB3 Overcurrent Pin Mapping 1 (U3OCM1)—Offset D0h 2033
51.2.42 XHCC3—Offset FCh 2034
51.3 Registers in Memory Space—MBAR 2035
51.3.1 Capability Registers Length (CAPLENGTH)—Offset 0h 2035
51.3.2 Host Controller Interface Version Number (HCIVERSION)—Offset 2h 2035
51.3.3 Structural Parameters 1 (HCSPARAMS1)—Offset 4h 2036
51.3.4 Structural Parameters 2 (HCSPARAMS2)—Offset 8h 2036
51.3.5 Structural Parameters 3 (HCSPARAMS3)—Offset Ch 2037
51.3.6 Capability Parameters (HCCPARAMS)—Offset 10h 2038
51.3.7 Doorbell Offset (DBOFF)—Offset 14h 2039
51.3.8 Runtime Register Space Offset (RTSOFF)—Offset 18h 2039
51.3.9 USB Command (USBCMD)—Offset 80h 2040
51.3.10 USB Status (USBSTS)—Offset 84h 2041
51.3.11 Page Size (PAGESIZE)—Offset 88h 2042
51.3.12 Device Notification Control (DNCTRL)—Offset 94h 2042
51.3.13 Command Ring Low (CRCR_LO)—Offset 98h 2043
51.3.14 Command Ring High (CRCR_HI)—Offset 9Ch 2043
51.3.15 Device Context Base Address Array Pointer Low (DCBAAP_LO)—Offset B0h 2044
51.3.16 Device Context Base Address Array Pointer High (DCBAAP_HI)—Offset B4h 2044
51.3.17 Configure (CONFIG)—Offset B8h 2044
51.3.18 Port Status and Control USB2 (PORTSC1)—Offset 480h 2045
51.3.19 Port Power Management Status and Control USB2 (PORTPMSC1)—Offset 484h 2047
51.3.20 Port X Hardware LPM Control Register (PORTHLPMC1)—Offset 48Ch 2048
51.3.21 Port Status and Control USB2 (PORTSC2)—Offset 490h 2049
51.3.22 Port Power Management Status and Control USB2 (PORTPMSC2)—Offset 494h 2051
51.3.23 Port X Hardware LPM Control Register (PORTHLPMC2)—Offset 49Ch 2052
51.3.24 Port Status and Control USB2 (PORTSC3)—Offset 4A0h 2053
51.3.25 Port Power Management Status and Control USB2 (PORTPMSC3)—Offset 4A4h 2055
51.3.26 Port X Hardware LPM Control Register (PORTHLPMC3)—Offset 4ACh 2056
51.3.27 Port Status and Control USB2 (PORTSC4)—Offset 4B0h 2057
51.3.28 Port Power Management Status and Control USB2 (PORTPMSC4)—Offset 4B4h 2059
51.3.29 Port X Hardware LPM Control Register (PORTHLPMC4)—Offset 4BCh 2060
51.3.30 Port Status and Control USB3 (PORTSC5)—Offset 4C0h 2061
51.3.31 Port Power Management Status and Control USB3 (PORTPMSC5)—Offset 4C4h 2064
51.3.32 USB3 Port Link Info (PORTLI5)—Offset 4C8h 2064
51.3.33 Port Status and Control USB3 (PORTSC6)—Offset 4D0h 2065
51.3.34 Port Power Management Status and Control USB3 (PORTPMSC6)—Offset 4D4h 2068
51.3.35 USB3 Port Link Info (PORTLI6)—Offset 4D8h 2068
51.3.36 Port Status and Control USB3 (PORTSC7)—Offset 4E0h 2069
51.3.37 Port Power Management Status and Control USB3 (PORTPMSC7)—Offset 4E4h 2072
51.3.38 USB3 Port Link Info (PORTLI7)—Offset 4E8h 2072
51.3.39 Port Status and Control USB3 (PORTSC8)—Offset 4F0h 2073
51.3.40 Port Power Management Status and Control USB3 (PORTPMSC8)—Offset 4F4h 2076

51.3.41 USB3 Port Link Info (PORTLI8)—Offset 4F8h....2076
51.3.42 Microframe Index (RTMFINDEX)—Offset 2000h....2076
51.3.43 Interrupter 1 Management (IMAN0)—Offset 2020h....2077
51.3.44 Interrupter 1 Moderation (IMOD0)—Offset 2024h....2077
51.3.45 Event Ring Segment Table Size 1 (ERSTSZ0)—Offset 2028h....2077
51.3.46 Event Ring Segment Table Base Address Low 1 (ERSTBA_LO0)—Offset 2030h....2078
51.3.47 Event Ring Segment Table Base Address High 1 (ERSTBA_HI0)—Offset 2034h....2078
51.3.48 Event Ring Dequeue Pointer Low 1 (ERDP_LO0)—Offset 2038h....2079
51.3.49 Event Ring Dequeue Pointer High 1 (ERDP_HI0)—Offset 203Ch....2079
51.3.50 Interrupter 2 Management (IMAN1)—Offset 2040h....2080
51.3.51 Interrupter 2 Moderation (IMOD1)—Offset 2044h....2080
51.3.52 Event Ring Segment Table Size 2 (ERSTSZ1)—Offset 2048h....2080
51.3.53 Event Ring Segment Table Base Address Low 2 (ERSTBA_LO1)—Offset 2050h....2081
51.3.54 Event Ring Segment Table Base Address High 2 (ERSTBA_HI1)—Offset 2054h....2081
51.3.55 Event Ring Dequeue Pointer Low 2 (ERDP_LO1)—Offset 2058h....2081
51.3.56 Event Ring Dequeue Pointer High 2 (ERDP_HI1)—Offset 205Ch....2082
51.3.57 Interrupter 3 Management (IMAN2)—Offset 2060h....2082
51.3.58 Interrupter 3 Moderation (IMOD2)—Offset 2064h....2082
51.3.59 Event Ring Segment Table Size 3 (ERSTSZ2)—Offset 2068h....2083
51.3.60 Event Ring Segment Table Base Address Low 3 (ERSTBA_LO2)—Offset 2070h....2083
51.3.61 Event Ring Segment Table Base Address High 3 (ERSTBA_HI2)—Offset 2074h....2083
51.3.62 Event Ring Dequeue Pointer Low 3 (ERDP_LO2)—Offset 2078h....2084
51.3.63 Event Ring Dequeue Pointer High 3 (ERDP_HI2)—Offset 207Ch....2084
51.3.64 Interrupter 4 Management (IMAN3)—Offset 2080h....2084
51.3.65 Interrupter 4 Moderation (IMOD3)—Offset 2084h....2085
51.3.66 Event Ring Segment Table Size 4 (ERSTSZ3)—Offset 2088h....2085
51.3.67 Event Ring Segment Table Base Address Low 4 (ERSTBA_LO3)—Offset 2090h....2085
51.3.68 Event Ring Segment Table Base Address High 4 (ERSTBA_HI3)—Offset 2094h....2086
51.3.69 Event Ring Dequeue Pointer Low 4 (ERDP_LO3)—Offset 2098h....2086
51.3.70 Event Ring Dequeue Pointer High 4 (ERDP_HI3)—Offset 209Ch....2086
51.3.71 Interrupter 5 Management (IMAN4)—Offset 20A0h....2087
51.3.72 Interrupter 5 Moderation (IMOD4)—Offset 20A4h....2087
51.3.73 Event Ring Segment Table Size 5 (ERSTSZ4)—Offset 20A8h....2087
51.3.74 Event Ring Segment Table Base Address Low 5 (ERSTBA_LO4)—Offset 20B0h....2088
51.3.75 Event Ring Segment Table Base Address High 5 (ERSTBA_HI4)—Offset 20B4h....2088
51.3.76 Event Ring Dequeue Pointer Low 5 (ERDP_LO4)—Offset 20B8h....2088
51.3.77 Event Ring Dequeue Pointer High 5 (ERDP_HI4)—Offset 20BCh....2089
51.3.78 Interrupter 6 Management (IMAN5)—Offset 20C0h....2089
51.3.79 Interrupter 6 Moderation (IMOD5)—Offset 20C4h....2089
51.3.80 Event Ring Segment Table Size 6 (ERSTSZ5)—Offset 20C8h....2090
51.3.81 Event Ring Segment Table Base Address Low 6 (ERSTBA_LO5)—Offset 20D0h....2090
51.3.82 Event Ring Segment Table Base Address High 6 (ERSTBA_HI5)—Offset 20D4h....2090
51.3.83 Event Ring Dequeue Pointer Low 6 (ERDP_LO5)—Offset 20D8h....2091
51.3.84 Event Ring Dequeue Pointer High 6 (ERDP_HI5)—Offset 20DCh....2091

51.3.85 Interrupter 7 Management (IMAN6)—Offset 20E0h 2091
51.3.86 Interrupter 7 Moderation (IMOD6)—Offset 20E4h 2092
51.3.87 Event Ring Segment Table Size 7 (ERSTSZ6)—Offset 20E8h 2092
51.3.88 Event Ring Segment Table Base Address Low 7 (ERSTBA_LO6)—Offset 20F0h 2092
51.3.89 Event Ring Segment Table Base Address High 7 (ERSTBA_HI6)—Offset 20F4h 2093
51.3.90 Event Ring Dequeue Pointer Low 7 (ERDP_LO6)—Offset 20F8h 2093
51.3.91 Event Ring Dequeue Pointer High 7 (ERDP_HI6)—Offset 20FCh 2093
51.3.92 Interrupter 8 Management (IMAN7)—Offset 2100h 2094
51.3.93 Interrupter 8 Moderation (IMOD7)—Offset 2104h 2094
51.3.94 Event Ring Segment Table Size 8 (ERSTSZ7)—Offset 2108h 2094
51.3.95 Event Ring Segment Table Base Address Low 8 (ERSTBA_LO7)—Offset 2110h 2095
51.3.96 Event Ring Segment Table Base Address High 8 (ERSTBA_HI7)—Offset 2114h 2095
51.3.97 Event Ring Dequeue Pointer Low 8 (ERDP_LO7)—Offset 2118h 2095
51.3.98 Event Ring Dequeue Pointer High 8 (ERDP_HI7)—Offset 211Ch 2096
51.3.99 Door Bell 1 (DB0)—Offset 3000h 2096
51.3.100 Door Bell 2 (DB1)—Offset 3004h 2097
51.3.101 Door Bell 3 (DB2)—Offset 3008h 2097
51.3.102 Door Bell 4 (DB3)—Offset 300Ch 2098
51.3.103 Door Bell 5 (DB4)—Offset 3010h 2098
51.3.104 Door Bell 6 (DB5)—Offset 3014h 2099
51.3.105 Door Bell 7 (DB6)—Offset 3018h 2099
51.3.106 Door Bell 8 (DB7)—Offset 301Ch 2100
51.3.107 Door Bell 9 (DB8)—Offset 3020h 2100
51.3.108 Door Bell 10 (DB9)—Offset 3024h 2101
51.3.109 Door Bell 11 (DB10)—Offset 3028h 2101
51.3.110 Door Bell 12 (DB11)—Offset 302Ch 2102
51.3.111 Door Bell 13 (DB12)—Offset 3030h 2102
51.3.112 Door Bell 14 (DB13)—Offset 3034h 2103
51.3.113 Door Bell 15 (DB14)—Offset 3038h 2103
51.3.114 Door Bell 16 (DB15)—Offset 303Ch 2104
51.3.115 Door Bell 17 (DB16)—Offset 3040h 2104
51.3.116 Door Bell 18 (DB17)—Offset 3044h 2105
51.3.117 Door Bell 19 (DB18)—Offset 3048h 2105
51.3.118 Door Bell 20 (DB19)—Offset 304Ch 2106
51.3.119 Door Bell 21 (DB20)—Offset 3050h 2106
51.3.120 Door Bell 22 (DB21)—Offset 3054h 2107
51.3.121 Door Bell 23 (DB22)—Offset 3058h 2107
51.3.122 Door Bell 24 (DB23)—Offset 305Ch 2108
51.3.123 Door Bell 25 (DB24)—Offset 3060h 2108
51.3.124 Door Bell 26 (DB25)—Offset 3064h 2109
51.3.125 Door Bell 27 (DB26)—Offset 3068h 2109
51.3.126 Door Bell 28 (DB27)—Offset 306Ch 2110
51.3.127 Door Bell 29 (DB28)—Offset 3070h 2110
51.3.128 Door Bell 30 (DB29)—Offset 3074h 2111
51.3.129 Door Bell 31 (DB30)—Offset 3078h 2111
51.3.130 Door Bell 32 (DB31)—Offset 307Ch 2112
51.3.131 Door Bell 32 (DB32)—Offset 3080h 2112
51.3.132 XECP_SUPP_USB2_1—Offset 8004h 2113
51.3.133 XECP_SUPP_USB2_2—Offset 8008h 2113
51.3.134 XECP_SUPP_USB3_1—Offset 8024h 2114
51.3.135 XECP_SUPP_USB3_2—Offset 8028h 2114

51.3.136 Host Controller Capability (HOST_CTRL_CAP_REG)—Offset 8070h 2114
51.3.137 Override EP Flow Control (HOST_CLR_MASK_REG)—Offset 8078h 2115
51.3.138 Clear Active IN EP ID Control (HOST_CLR_IN_EP_VALID_REG)—Offset 807Ch 2115
51.3.139 Clear Poll Mask Control (HOST_CLR_PMASK_REG)—Offset 8080h 2116
51.3.140 Host Control Scheduler (HOST_CTRL_SCH_REG)—Offset 8094h 2117
51.3.141 Power Management Control (PMCTRL_REG)—Offset 80A4h 2118
51.3.142 PGCB Control (PGCBCTRL_REG)—Offset 80A8h 2120
51.3.143 D0I3 Control (DOI3CTRL_REG)—Offset 80ACh 2123
51.3.144 HOST_CTRL_MISC_REG—Offset 80B0h 2124
51.3.145 reg_SSPITPE_type (SSPITPE)—Offset 80BCh 2126
51.3.146 AUX Reset Control (AUX_CTRL_REG)—Offset 80C0h 2127
51.3.147 Super Speed Bandwidth Overload (HOST_BW_OV_SS_REG)—Offset 80C4h 2130
51.3.148 High Speed TT Bandwidth Overload (HOST_BW_OV_HS_REG)—Offset 80C8h 2131
51.3.149 Bandwidth Overload Full Low Speed (HOST_BW_OV_FS_LS_REG)—Offset 80CCh.....2131
51.3.150 System Bandwidth Overload (HOST_BW_OV_SYS_REG)—Offset 80D0h....2132
51.3.151 Scheduler Async Delay (HOST_CTRL_SCH_ASYNC_DELAY_REG)—Offset 80D4h 2133
51.3.152 AUX Power Management Control (AUX_CTRL_REG1)—Offset 80E0h 2134
51.3.153 Battery Charge (BATTERY_CHARGE_REG)—Offset 80E4h 2137
51.3.154 SuperSpeed Port Link Control (HOST_CTRL_PORT_LINK_REG)—Offset 80ECh 2138
51.3.155 USB2 Port Link Control 1 (USB2_LINK_MGR_CTRL_REG1)—Offset 80F0h 2140
51.3.156 USB2 Port Link Control 2 (USB2_LINK_MGR_CTRL_REG2)—Offset 80F4h 2142
51.3.157 USB2 Port Link Control 3 (USB2_LINK_MGR_CTRL_REG3)—Offset 80F8h 2142
51.3.158 USB2 Port Link Control 4 (USB2_LINK_MGR_CTRL_REG4)—Offset 80FCh 2143
51.3.159 Bandwidth Overload Burst (HOST_BW_OV_BURST_REG)—Offset 810Ch ...2143
51.3.160 USB Max Bandwidth Control 4 (HOST_CTRL_BW_MAX_REG)—Offset 8128h 2144
51.3.161 Power Scheduler Control-0 (PWR_SCHED_CTRL0)—Offset 8140h 2144
51.3.162 AUX Power Management Control (AUX_CTRL_REG2)—Offset 8154h 2146
51.3.163 USB2 PHY Power Management Control (USB2_PHY_PMC)—Offset 8164h 2148
51.3.164 USB Power Gating Control (USB_PGC)—Offset 8168h 2149
51.3.165 xHCI Aux Clock Control Register (XHCI_AUX_CCR)—Offset 816Ch 2150
51.3.166 USB LPM Parameters (USB_LPM_PARAM)—Offset 8170h 2152
51.3.167 xHC Latency Tolerance Parameters - LTV Control (XLTP_LTV1)—Offset 8174h 2153
51.3.168 xHC Latency Tolerance Parameters LTV Control 2 (XLTP_LTV2)—Offset 8178h 2154
51.3.169 xHC Latency Tolerance Parameters - High Idle Time Control (XLTP_HITC)—Offset 817Ch 2154
51.3.170 xHC Latency Tolerance Parameters - Medium Idle Time Control (XLTP_MITC)—Offset 8180h 2155
51.3.171 xHC Latency Tolerance Parameters Low Idle Time Control (XLTP_LITC)—Offset 8184h 2155
51.3.172 HOST_CTRL_BW_MAX3_REG—Offset 8188h 2156
51.3.173 THRM_HOST_CTRL_REG—Offset 819Ch 2157
51.3.174 THRM_HOST_CTRL_REG2—Offset 81B4h 2158

51.3.175 LFPSONCOUNT_REG—Offset 81B8h 2158
51.3.176 reg_D0i2_CTRL_REG_type (D0i2_CTRL_REG)—Offset 81BCh 2160
51.3.177 reg_D0i2_SCH_ALARM_CTRL_REG_type (D0i2_SCH_ALARM_CTRL_REG)—Offset 81C0h 2162
51.3.178 reg_USB2PMCTRL_REG_type (USB2PMCTRL_REG)—Offset 81C4h 2163
51.3.179 ECC_PARITY_ERROR_LOG_REG—Offset 83F8h 2164
51.3.180 ECC_POISONING_CTRL_REG—Offset 83FCh 2166
51.3.181 USB2_PORT_STATE_REG—Offset 8400h 2167
51.3.182 USB2_PORT_STATE_REG (USB3_PORT_STATE_REG)—Offset 8408h 2167
51.3.183 FUS1_REG—Offset 8410h 2168
51.3.184 FUS2_REG—Offset 8414h 2169
51.3.185 STRAP1_REG—Offset 841Ch 2169
51.3.186 STRAP2_REG—Offset 8420h 2169
51.3.187 STRAP3_REG—Offset 8424h 2170
51.3.188 DFT_REG1—Offset 8430h 2171
51.3.189 DFT_REG2—Offset 8434h 2172
51.3.190 DFT_REG3—Offset 8438h 2173
51.3.191 dft_reg4 (DFT_REG4)—Offset 843Ch 2173
51.3.192 dft_reg5 (DFT_REG5)—Offset 8440h 2174
51.3.193 XECP_CMDM_STS0—Offset 8448h 2175
51.3.194 XECP_CMDM_STS2—Offset 8450h 2177
51.3.195 XECP_CMDM_STS3—Offset 8454h 2177
51.3.196 AUX Power PHY Reset (UPORTS_PON_RST_REG)—Offset 8460h 2177
51.3.197 Latency Tolerance Control 0 (HOST_IF_LAT_TOL_CTRL_REG0)—Offset 8464h 2178
51.3.198 USB Legacy Support Capability (USBLEGSUP)—Offset 846Ch 2179
51.3.199 USB2 Port Disable Override (USB2PDO)—Offset 84F8h 2180
51.3.200 USB3 Port Disable Override (USB3PDO)—Offset 84FCh 2180
51.3.201 Command (CMD_MMIO)—Offset 8604h 2181
51.3.202 Device Status (STS_MMIO)—Offset 8606h 2182
51.3.203 Revision ID (RID_MMIO)—Offset 8608h 2184
51.3.204 Programming Interface (PI_MMIO)—Offset 8609h 2184
51.3.205 Sub Class Code (SCC_MMIO)—Offset 860Ah 2184
51.3.206 Base Class Code (BCC_MMIO)—Offset 860Bh 2185
51.3.207 Master Latency Timer (MLT_MMIO)—Offset 860Dh 2185
51.3.208 Header Type (HT_MMIO)—Offset 860Eh 2185
51.3.209 Memory Base Address (MBAR_MMIO)—Offset 8610h 2186
51.3.210 USB Subsystem Vendor ID (SSVID_MMIO)—Offset 862Ch 2186
51.3.211 USB Subsystem ID (SSID_MMIO)—Offset 862Eh 2187
51.3.212 Capabilities Pointer (CAP_PTR_MMIO)—Offset 8634h 2187
51.3.213 Interrupt Line (ILINE_MMIO)—Offset 863Ch 2187
51.3.214 Interrupt Pin (IPIN_MMIO)—Offset 863Dh 2188
51.3.215 XHC System Bus Configuration 1 (XHCC1_MMIO)—Offset 8640h 2189
51.3.216 XHC System Bus Configuration 2 (XHCC2_MMIO)—Offset 8644h 2191
51.3.217 Clock Gating (XHCLKGTEN_MMIO)—Offset 8650h 2193
51.3.218 Audio Time Synchronization (AUDSYNC_MMIO)—Offset 8658h 2196
51.3.219 Serial Bus Release Number (SBRN_MMIO)—Offset 8660h 2196
51.3.220 Frame Length Adjustment (FLADJ_MMIO)—Offset 8661h 2197
51.3.221 Best Effort Service Latency (BESL_MMIO)—Offset 8662h 2197
51.3.222 PCI Power Management Capability ID (PM_CID_MMIO)—Offset 8670h 2198
51.3.223 Next Item Pointer #1 (PM_NEXT_MMIO)—Offset 8671h 2198
51.3.224 Power Management Capabilities (PM_CAP_MMIO)—Offset 8672h 2199
51.3.225 Power Management Control/Status (PM_CS_MMIO)—Offset 8674h 2200
51.3.226 Message Signaled Interrupt CID (MSI_CID_MMIO)—Offset 8680h 2201
51.3.227 Next item pointer (MSI_NEXT_MMIO)—Offset 8681h 2201

51.3.228 Message Signaled Interrupt Message Control (MSI_MCTL_MMIO)—Offset 8682h 2202
51.3.229 Message Signaled Interrupt Message Address (MSI_MAD_MMIO)—Offset 8684h 2202
51.3.230 Message Signaled Interrupt Upper Address (MSI_MUAD_MMIO)—Offset 8688h 2203
51.3.231 Message Signaled Interrupt Message Data (MSI_MD_MMIO)—Offset 868Ch 2203
51.3.232 Device Idle Capability (DEVIDLE_MMIO)—Offset 8690h 2204
51.3.233 Vendor Specific Header (VSHDR_MMIO)—Offset 8694h 2204
51.3.234 SW LTR POINTER (SWLTRPTR_MMIO)—Offset 8698h 2205
51.3.235 Device Idle Pointer Register (DEVIDLEPTR_MMIO)—Offset 869Ch 2205
51.3.236 Device Idle Power ON Latency (DEVIDLEPOL_MMIO)—Offset 86A0h 2206
51.3.237 High Speed Configuration 2 (HSCFG2_MMIO)—Offset 86A4h 2207
51.3.238 XHCI USB2 Overcurrent Pin Mapping 1 (U2OCM1_MMIO)—Offset 86B0h 2208
51.3.239 XHCI USB3 Overcurrent Pin Mapping 1 (U3OCM1_MMIO)—Offset 86D0h 2208
51.3.240 XHCC3 (XHCC3_MMIO)—Offset 86FCh 2209
51.3.241 Debug Capability ID Register (DCID)—Offset 8700h 2209
51.3.242 Debug Capability Doorbell Register (DCDB)—Offset 8704h 2210
51.3.243 Debug Capability Event Ring Segment Table Size Register (DCERSTSZ)—Offset 8708h 2210
51.3.244 Debug Capability Event Ring Segment Table Base Address Register (DCERSTBA)—Offset 8710h 2211
51.3.245 Debug Capability Event Ring Dequeue Pointer Register (DCERDP)—Offset 8718h 2211
51.3.246 Debug Capability Control Register (DCCTRL)—Offset 8720h 2212
51.3.247 Debug Capability Status Register (DCST)—Offset 8724h 2213
51.3.248 Debug Capability Port Status and Control Register (DCPORTSC)—Offset 8728h 2214
51.3.249 Debug Capability Context Pointer Register (DCCP)—Offset 8730h 2216
51.3.250 Debug Capability Device Descriptor Info Register 1 (DCDDI1)—Offset 8738h 2216
51.3.251 Debug Capability Device Descriptor Info Register 2 (DCDDI2)—Offset 873Ch 2217
51.3.252 Debug Capability Descriptor Parameters (DCDP)—Offset 8740h 2217
51.3.253 Debug Device Control ODMA (DBGDEV_CTRL_ODMA_REG)—Offset 8748h 2218
51.3.254 DBC Control Register 1 (DBCCTL_REG)—Offset 8760h 2220

52 System Management - B0, D24, F(0, 1, 3, 4) 2221

52.1 Introduction and Index 2221
52.1.1 Host Configuration Space—HECI1 (F:0) 2222
52.1.2 Host Configuration Space—HECI2 (F:1) 2224
52.1.3 Host Configuration Space—HECI3 (F:4) 2225
52.1.4 Host Configuration Space—KT (F:3) 2226
52.1.5 Host Configuration Space—IDE (F:2) 2227
52.1.6 Host Memory Space—HECI1_MMIO_MBAR 2228
52.1.7 Host Memory Space—HECI2_MMIO_MBAR 2229
52.1.8 Host Memory Space—HECI3_MMIO_MBAR 2230
52.1.9 Host Memory Space—KT_HOST_MEMBAR 2231
52.1.10 Host Memory Space—Fixed Address 2232
52.1.11 Host I/O Space—KT_HOST_IOBAR 2233
52.1.12 Host I/O Space—IDE_HOST_PCMDIOBAR 2234
52.1.13 Host I/O Space—IDE_HOST_PCTLIOBAR 2235

52.1.14 Host I/O Space—IDE_HOST_BMIOBAR 2236
52.1.15 Sideband Registers 2237
52.2 Registers in Configuration Space—HECI1 2239
52.2.1 Identifiers (HECI1_ID)—Offset 0h 2239
52.2.2 Command (HECI1_CMD)—Offset 4h 2240
52.2.3 Status (HECI1_STS)—Offset 6h 2241
52.2.4 Revision ID and Class Code (HECI1_RID_CC)—Offset 8h 2242
52.2.5 Cache Line Size (HECI1_CLS)—Offset Ch 2242
52.2.6 Master Latency Timer (HECI1_MLT)—Offset Dh 2242
52.2.7 Header Type (HECI1_HTYPE)—Offset Eh 2243
52.2.8 Built In Self-Test (HECI1_BIST)—Offset Fh 2243
52.2.9 HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h 2243
52.2.10 HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h 2244
52.2.11 Sub System Identifiers (HECI1_SS)—Offset 2Ch 2244
52.2.12 Capabilities Pointer (HECI1_CAP)—Offset 34h 2244
52.2.13 Interrupt Information (HECI1_INTR)—Offset 3Ch 2245
52.2.14 Minimum Grant (HECI1_MGNT)—Offset 3Eh 2245
52.2.15 Maximum Latency (HECI1_MLAT)—Offset 3Fh 2245
52.2.16 Host Firmware Status (HECI1_HFS)—Offset 40h 2246
52.2.17 Miscellaneous Shadow (HECI1_MISC_SHDW)—Offset 44h 2248
52.2.18 General Status Shadow 1 (HECI1_GS_SHDW1)—Offset 48h 2249
52.2.19 Host General Status (HECI1_H_GS1)—Offset 4Ch 2250
52.2.20 PCI Power Management Capability ID (HECI1_PID)—Offset 50h 2250
52.2.21 PCI Power Management Capabilities (HECI1_PC)—Offset 52h 2250
52.2.22 PCI Power Management Control and Status (HECI1_PMCS)—Offset 54h 2251
52.2.23 General Status Shadow 2 (HECI1_GS_SHDW2)—Offset 60h 2251
52.2.24 General Status Shadow 3 (HECI1_GS_SHDW3)—Offset 64h 2252
52.2.25 General Status Shadow 4 (HECI1_GS_SHDW4)—Offset 68h 2252
52.2.26 General Status Shadow 5 (HECI1_GS_SHDW5)—Offset 6Ch 2252
52.2.27 Host General Status 2 (HECI1_H_GS2)—Offset 70h 2252
52.2.28 Host General Status 3 (HECI1_H_GS3)—Offset 74h 2253
52.2.29 Message Signaled Interrupt Identifiers (HECI1_MID)—Offset 8Ch 2253
52.2.30 Message Signaled Interrupt Message Control (HECI1_MC)—Offset 8Eh 2253
52.2.31 Message Signaled Interrupt Message Address (HECI1_MA)—Offset 90h 2254
52.2.32 Message Signaled Interrupt Upper Address (HECI1_MUA)—Offset 94h 2254
52.2.33 Message Signaled Interrupt Message Data (HECI1_MD)—Offset 98h 2254
52.2.34 HECI Interrupt Delivery Mode (HECI1_HIDM)—Offset A0h 2255
52.2.35 Host Extend Register Status (HECI1_HERS)—Offset BCh 2255
52.2.36 Host Extend Register DW1. (HECI1_HER1)—Offset C0h 2256
52.2.37 Host Extend Register DW2. (HECI1_HER2)—Offset C4h 2256
52.2.38 Host Extend Register DW3. (HECI1_HER3)—Offset C8h 2256
52.2.39 Host Extend Register DW4. (HECI1_HER4)—Offset CCh 2256
52.2.40 Host Extend Register DW5. (HECI1_HER5)—Offset D0h 2257
52.2.41 Host Extend Register DW6. (HECI1_HER6)—Offset D4h 2257
52.2.42 Host Extend Register DW7. (HECI1_HER7)—Offset D8h 2257
52.2.43 Host Extend Register DW8. (HECI1_HER8)—Offset DCh 2257
52.2.44 Manufacturer's ID (HECI1_MANID)—Offset F8h 2258
52.3 Registers in Configuration Space—HECI2 2259
52.3.1 Identifiers (HECI2_ID)—Offset 0h 2259
52.3.2 Command (HECI2_CMD)—Offset 4h 2259
52.3.3 Status (HECI2_STS)—Offset 6h 2261
52.3.4 Revision ID and Class Code (HECI2_RID_CC)—Offset 8h 2262
52.3.5 Cache Line Size (HECI2_CLS)—Offset Ch 2262
52.3.6 Master Latency Timer (HECI2_MLT)—Offset Dh 2262

52.3.7 Header Type (HECI2_HTYPE)—Offset Eh 2263
52.3.8 Built In Self-Test (HECI2_BIST)—Offset Fh 2263
52.3.9 HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h 2263
52.3.10 HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h 2264
52.3.11 Sub System Identifiers (HECI2_SS)—Offset 2Ch 2264
52.3.12 Capabilities Pointer (HECI2_CAP)—Offset 34h 2264
52.3.13 Interrupt Information (HECI2_INTR)—Offset 3Ch 2265
52.3.14 Minimum Grant (HECI2_MGNT)—Offset 3Eh 2265
52.3.15 Maximum Latency (HECI2_MLAT)—Offset 3Fh 2265
52.3.16 Host Firmware Status (HECI2_HFS)—Offset 40h 2266
52.3.17 General Status Shadow 1 (HECI2_GS_SHDW1)—Offset 48h 2268
52.3.18 Host General Status (HECI2_H_GS1)—Offset 4Ch 2269
52.3.19 PCI Power Management Capability ID (HECI2_PID)—Offset 50h 2269
52.3.20 PCI Power Management Capabilities (HECI2_PC)—Offset 52h 2270
52.3.21 PCI Power Management Control and Status (HECI2_PMCS)—Offset 54h 2271
52.3.22 General Status Shadow 2 (HECI2_GS_SHDW2)—Offset 60h 2271
52.3.23 General Status Shadow 3 (HECI2_GS_SHDW3)—Offset 64h 2272
52.3.24 General Status Shadow 4 (HECI2_GS_SHDW4)—Offset 68h 2272
52.3.25 General Status Shadow 5 (HECI2_GS_SHDW5)—Offset 6Ch 2272
52.3.26 Host General Status 2 (HECI2_H_GS2)—Offset 70h 2272
52.3.27 Host General Status 3 (HECI2_H_GS3)—Offset 74h 2273
52.3.28 Message Signaled Interrupt Identifiers (HECI2_MID)—Offset 8Ch 2273
52.3.29 Message Signaled Interrupt Message Control (HECI2_MC)—Offset 8Eh 2273
52.3.30 Message Signaled Interrupt Message Address (HECI2_MA)—Offset 90h 2274
52.3.31 Message Signaled Interrupt Upper Address (HECI2_MUA)—Offset 94h 2274
52.3.32 Message Signaled Interrupt Message Data (HECI2_MD)—Offset 98h 2274
52.3.33 HECI Interrupt Delivery Mode (HECI2_HIDM)—Offset A0h 2275
52.3.34 Manufacturer's ID (HECI2_MANID)—Offset F8h 2275
52.4 Registers in Configuration Space—HECI3 2276
52.4.1 Identifiers (HECI3_ID)—Offset 0h 2276
52.4.2 Command (HECI3_CMD)—Offset 4h 2277
52.4.3 Status (HECI3_STS)—Offset 6h 2278
52.4.4 Revision ID and Class Code (HECI3_RID_CC)—Offset 8h 2279
52.4.5 Cache Line Size (HECI3_CLS)—Offset Ch 2279
52.4.6 Master Latency Timer (HECI3_MLT)—Offset Dh 2279
52.4.7 Header Type (HECI3_HTYPE)—Offset Eh 2280
52.4.8 Built In Self-Test (HECI3_BIST)—Offset Fh 2280
52.4.9 HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h 2280
52.4.10 HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h 2281
52.4.11 Sub System Identifiers (HECI3_SS)—Offset 2Ch 2281
52.4.12 Capabilities Pointer (HECI3_CAP)—Offset 34h 2281
52.4.13 Interrupt Information (HECI3_INTR)—Offset 3Ch 2282
52.4.14 Minimum Grant (HECI3_MGNT)—Offset 3Eh 2282
52.4.15 Maximum Latency (HECI3_MLAT)—Offset 3Fh 2282
52.4.16 Host Firmware Status (HECI3_HFS)—Offset 40h 2283
52.4.17 General Status Shadow 1 (HECI3_GS_SHDW1)—Offset 48h 2285
52.4.18 Host General Status (HECI3_H_GS1)—Offset 4Ch 2286
52.4.19 PCI Power Management Capability ID (HECI3_PID)—Offset 50h 2286
52.4.20 PCI Power Management Capabilities (HECI3_PC)—Offset 52h 2286
52.4.21 PCI Power Management Control and Status (HECI3_PMCS)—Offset 54h 2287
52.4.22 General Status Shadow 2 (HECI3_GS_SHDW2)—Offset 60h 2287
52.4.23 General Status Shadow 3 (HECI3_GS_SHDW3)—Offset 64h 2288
52.4.24 General Status Shadow 4 (HECI3_GS_SHDW4)—Offset 68h 2288

52.4.25 General Status Shadow 5 (HECI3_GS_SHDW5)—Offset 6Ch 2288
52.4.26 Host General Status 2 (HECI3_H_GS2)—Offset 70h 2288
52.4.27 Host General Status 3 (HECI3_H_GS3)—Offset 74h 2289
52.4.28 Message Signaled Interrupt Identifiers (HECI3_MID)—Offset 8Ch 2289
52.4.29 Message Signaled Interrupt Message Control (HECI3_MC)—Offset 8Eh 2289
52.4.30 Message Signaled Interrupt Message Address (HECI3_MA)—Offset 90h ... 2290
52.4.31 Message Signaled Interrupt Upper Address (HECI3_MUA)—Offset 94h 2290
52.4.32 Message Signaled Interrupt Message Data (HECI3_MD)—Offset 98h..... 2290
52.4.33 HECI Interrupt Delivery Mode (HECI3_HIDM)—Offset A0h..... 2291
52.4.34 Manufacturer's ID (HECI3_MANID)—Offset F8h 2291
52.5 Registers in Configuration Space—KT (Host)..... 2292
52.5.1 Device ID and Vendor ID (KT_HOST_DID_VID)—Offset 0h..... 2292
52.5.2 Status and Command (KT_HOST_STS_CMD)—Offset 4h 2293
52.5.3 Class Code and Revision ID (KT_HOST_CC_RID)—Offset 8h 2295
52.5.4 BIST, Header Type, Latency Timer, and Cache Line Size (KT_HOST_BIST_HTYPE_LT_CLS)—Offset Ch 2295
52.5.5 KT IO BAR (KT_HOST_IOBAR)—Offset 10h 2296
52.5.6 KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h 2296
52.5.7 Cardbus CIS Pointer (KT_HOST_CCP)—Offset 28h 2297
52.5.8 Subsystem ID and Subsystem Vendor ID (KT_HOST_SID_SVID)—Offset 2Ch..... 2297
52.5.9 Expansion ROM Base Address (KT_HOST_XRBAR)—Offset 30h 2297
52.5.10 Capabilities List Pointer (KT_HOST_CAPP)—Offset 34h 2298
52.5.11 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (KT_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch 2298
52.5.12 MSI Message Control, Next Pointer and Capability ID (KT_HOST_MSIMC_MSINP_MSICID)—Offset 40h 2299
52.5.13 MSI Message Address (KT_HOST_MSIMA)—Offset 44h 2299
52.5.14 MSI Message Upper Address (KT_HOST_MSIMUA)—Offset 48h 2300
52.5.15 MSI Message Data (KT_HOST_MSIMD)—Offset 4Ch 2300
52.5.16 Power Management Capabilities, Next Pointer and Capability ID (KT_HOST_PMCAP_PMNP_PMCID)—Offset 50h 2301
52.5.17 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (KT_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h 2302
52.5.18 Process Stepping Information (KT_HOST_PSI)—Offset F8h 2303
52.6 Registers in Configuration Space—IDE (Host) 2304
52.6.1 Device ID and Vendor ID (IDE_HOST_DID_VID)—Offset 0h 2304
52.6.2 Status and Command (IDE_HOST_STS_CMD)—Offset 4h..... 2305
52.6.3 Class Code and Revision ID (IDE_HOST_CC_RID)—Offset 8h 2307
52.6.4 BIST, Header Type, Latency Timer, and Cache Line Size (IDE_HOST_BIST_HTYPE_LT_CLS)—Offset Ch..... 2307
52.6.5 IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h 2308
52.6.6 IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h 2308
52.6.7 IDE Secondary Command Block IO BAR (IDE_HOST_SCMDIOBAR)—Offset 18h 2309
52.6.8 IDE Secondary Control Block IO BAR (IDE_HOST_SCTLIOBAR)—Offset 1Ch 2309
52.6.9 IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h..... 2310
52.6.10 Cardbus CIS Pointer (IDE_HOST_CCP)—Offset 28h 2310
52.6.11 Subsystem ID and Subsystem Vendor ID (IDE_HOST_SID_SVID)—Offset 2Ch 2311
52.6.12 Expansion ROM Base Address (IDE_HOST_XRBAR)—Offset 30h 2311
52.6.13 Capabilities List Pointer (IDE_HOST_CAPP)—Offset 34h 2311

52.6.14 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (IDE_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch 2312
52.6.15 MSI Message Control, Next Pointer and Capability ID (IDE_HOST_MSIMC_MSINP_MSICID)—Offset 40h 2313
52.6.16 MSI Message Address (IDE_HOST_MSIMA)—Offset 44h 2313
52.6.17 MSI Message Upper Address (IDE_HOST_MSIMUA)—Offset 48h 2314
52.6.18 MSI Message Data (IDE_HOST_MSIMD)—Offset 4Ch 2314
52.6.19 Power Management Capabilities, Next Pointer and Capability ID (IDE_HOST_PMCAP_PMNP_PMCID)—Offset 50h 2315
52.6.20 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (IDE_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h 2316
52.6.21 Process Stepping Information (IDE_HOST_PSI)—Offset F8h....2317
52.7 Registers in Memory Space—HECI1_MMIO_MBAR 2318
52.7.1 Host CB Write Window (HECI1_H_CB_WW)—Offset 0h....2318
52.7.2 Host Control and Status Register (HECI1_H_CSR)—Offset 4h....2319
52.7.3 CSE Circular Buffer Read Window (HECI1_CSE_CB_RW)—Offset 8h 2320
52.7.4 CSE Control and Status Register Host Access (HECI1_CSE_CSR_HA)—Offset Ch....2320
52.7.5 D0i3 Control (HECI1_D0I3C)—Offset 800h 2321
52.8 Registers in Memory Space—HECI2_MMIO_MBAR 2322
52.8.1 Host CB Write Window (HECI2_H_CB_WW)—Offset 0h....2322
52.8.2 Host Control and Status Register (HECI2_H_CSR)—Offset 4h....2323
52.8.3 CSE Circular Buffer Read Window (HECI2_CSE_CB_RW)—Offset 8h 2324
52.8.4 CSE Control and Status Register Host Access (HECI2_CSE_CSR_HA)—Offset Ch....2324
52.8.5 D0i3 Control (HECI2_D0I3C)—Offset 800h 2325
52.9 Registers in Memory Space—HECI3_MMIO_MBAR 2326
52.9.1 Host CB Write Window (HECI3_H_CB_WW)—Offset 0h....2326
52.9.2 Host Control and Status Register (HECI3_H_CSR)—Offset 4h....2327
52.9.3 CSE Circular Buffer Read Window (HECI3_CSE_CB_RW)—Offset 8h 2328
52.9.4 CSE Control and Status Register Host Access (HECI3_CSE_CSR_HA)—Offset Ch....2328
52.9.5 D0i3 Control (HECI3_D0I3C)—Offset 800h 2329
52.10 Registers in Memory Space—KT_HOST_MEMBAR 2330
52.10.1 KT Receive Buffer Register (MEM_KTRBR)—Offset 0h....2330
52.10.2 KT Transmitter Holding Register (MEM_KTTHR)—Offset 0h 2330
52.10.3 KT Divisor Latch LSB Register (MEM_KTDLLR)—Offset 0h 2331
52.10.4 KT Interrupt Enable register (MEM_KTIER)—Offset 1h....2331
52.10.5 KT Divisor Latch MSB Register (MEM_KTDLMR)—Offset 1h....2332
52.10.6 KT Interrupt Identification Register (MEM_KTIIR)—Offset 2h....2333
52.10.7 KT FIFO Control register (MEM_KTFCR)—Offset 2h 2334
52.10.8 KT Line Control register (MEM_KTLCR)—Offset 3h 2335
52.10.9 KT Modem Control register (MEM_KTMCR)—Offset 4h 2336
52.10.10 KT Line Status register (MEM_KTLSR)—Offset 5h 2337
52.10.11 KT Modem Status register (MEM_KTMSR)—Offset 6h 2338
52.10.12 KT Scratch register (MEM_KTSCR)—Offset 7h 2338
52.11 Registers in Memory Space—Fixed Address....2339
52.11.1 FTPM Locality State (HOST_LOC_0_LOC_STATE_HROA)—Offset FED40000h 2339
52.11.2 FTPM Locality Reserved (HOST_LOC_0_LOC_RSVD)—Offset FED40004h...2340
52.11.3 FTPM Locality n Control Register (HOST_LOC_0_LOC_CTRL)—Offset FED40008h 2340
52.11.4 FTPM Locality n Status Register Host Read Only Access. (HOST_LOC_0_LOC_STS_HROA)—Offset FED4000Ch 2340

52.11.5 FTPM Locality Config Area Reserved Read Write[0-7] (HOST_LOC_0_RSVD_RW1[0-7])—Offset FED40010h, Count 8, Stride 4h 2341
52.11.6 FTPM Interface ID Host Read Only Access 0 (HOST_LOC_0_INTF_ID_0)—Offset FED40030h 2341
52.11.7 FTPM Interface ID Host Read Only Access 1 (HOST_LOC_0_INTF_ID_1)—Offset FED40034h 2341
52.11.8 FTPM Locality Config Area Reserved Read Write[0-1] (HOST_LOC_0_RSVD_RW2[0-1])—Offset FED40038h, Count 2, Stride 4h 2342
52.11.9 Control Area Request (HOST_LOC_0_CA_REQUEST)—Offset FED40040h . 2342
52.11.10 Control Area Status (HOST_LOC_0_CA_STATUS)—Offset FED40044h 2342
52.11.11 Control Area Cancel (HOST_LOC_0_CA_CANCEL)—Offset FED40048h 2343
52.11.12 Control Area Start (HOST_LOC_0_CA_START)—Offset FED4004Ch 2343
52.11.13 Control Area Interrupt Reserved Part 1 (HOST_LOC_0_CA_INT_RSVD1)—Offset FED40050h 2343
52.11.14 Control Area Interrupt Reserved Part 2 (HOST_LOC_0_CA_INT_RSVD2)—Offset FED40054h 2344
52.11.15 Control Area Command Size (HOST_LOC_0_CA_CMD_SZ)—Offset FED40058h 2344
52.11.16 Control Area Command Part 1 (HOST_LOC_0_CA_CMD1)—Offset FED4005Ch 2344
52.11.17 Control Area Command Part 2 (HOST_LOC_0_CA_CMD2)—Offset FED40060h 2345
52.11.18 Control Area Response Size (HOST_LOC_0_CA_RSP_SZ)—Offset FED40064h 2345
52.11.19 Control Area Response Part 1 (HOST_LOC_0_CA_RSP1)—Offset FED40068h 2345
52.11.20 Control Area Response Part 2 (HOST_LOC_0_CA_RSP2)—Offset FED4006Ch 2346
52.11.21 FTPM Reserved Read Write[0-3] (HOST_LOC_0_RSVD_RW3[0-3])—Offset FED40070h, Count 4, Stride 4h 2346
52.11.22 FTPM Command and Response Buffer[0-991] (HOST_LOC_0_FTPM_CRB[0-991])—Offset FED40080h, Count 992, Stride 4h 2346
52.12 Registers in I/O Space—KT_HOST_IOBAR 2347
52.12.1 KT Receive Buffer Register (IO_KTRBR)—Offset 0h 2347
52.12.2 KT Transmitter Holding Register (IO_KTTHR)—Offset 0h 2347
52.12.3 KT Divisor Latch LSB Register (IO_KTDLLR)—Offset 0h 2348
52.12.4 KT Interrupt Enable register (IO_KTIER)—Offset 1h 2348
52.12.5 KT Divisor Latch MSB Register (IO_KTDLMR)—Offset 1h 2349
52.12.6 KT Interrupt Identification Register (IO_KTIIR)—Offset 2h 2349
52.12.7 KT FIFO Control register (IO_KTFCR)—Offset 2h 2350
52.12.8 KT Line Control register (IO_KTLCR)—Offset 3h 2351
52.12.9 KT Modem Control register (IO_KTMCR)—Offset 4h 2352
52.12.10 KT Line Status register (IO_KTLSR)—Offset 5h 2353
52.12.11 KT Modem Status register (IO_KTMSR)—Offset 6h 2354
52.12.12 KT Scratch register (IO_KTSCR)—Offset 7h 2355
52.13 Registers in I/O Space—IDE_HOST_PCMDIOBAR 2356
52.13.1 IDE Data Register (IDEDATA)—Offset 0h 2356
52.13.2 IDE Features Register (IDEFR)—Offset 1h 2356
52.13.3 IDE Error Register DEV0 (IDEERD0)—Offset 1h 2357
52.13.4 IDE Error Register DEV1 (IDEERD1)—Offset 1h 2357
52.13.5 IDE Sector Count In Register (IDESCIR)—Offset 2h 2358
52.13.6 IDE Sector Count Out Register DEV0 (IDESCOR0)—Offset 2h 2358
52.13.7 IDE Sector Count Out Register DEV1 (IDESCOR1)—Offset 2h 2358

52.13.8 IDE Sector Number In Register (IDESNIR)—Offset 3h 2359
52.13.9 IDE Sector Number Out Register DEV0 (IDESNOR0)—Offset 3h 2359
52.13.10 IDE Sector Number Out Register DEV1 (IDESNOR1)—Offset 3h 2360
52.13.11 IDE Cylinder Low In Register (IDECLIR)—Offset 4h 2360
52.13.12 IDE Cylinder Low Out Register DEV0 (IDCLOR0)—Offset 4h 2361
52.13.13 IDE Cylinder Low Out Register DEV1 (IDCLOR1)—Offset 4h 2361
52.13.14 IDE Cylinder High In Register (IDECHIR)—Offset 5h 2362
52.13.15 IDE Cylinder High Out Register DEV0 (IDCHOR0)—Offset 5h 2362
52.13.16 IDE Cylinder High Out Register DEV1 (IDCHOR1)—Offset 5h 2363
52.13.17 IDE Drive/Head In Register (IDEDHIR)—Offset 6h 2363
52.13.18 IDE Drive/Head Out Register DEV0 (IDDHOR0)—Offset 6h 2364
52.13.19 IDE Drive/Head Out Register DEV1 (IDDHOR1)—Offset 6h 2364
52.13.20 IDE Command Register (IDECR)—Offset 7h 2365
52.13.21 IDE Status Register DEV0 (IDESR0)—Offset 7h 2366
52.13.22 IDE Status Register DEV1 (IDESR1)—Offset 7h 2367
52.14 Registers in I/O Space—IDE_HOST_PCTLIOBAR 2368
52.14.1 IDE Device Control Register (IDDCR)—Offset 2h 2368
52.14.2 IDE Alternate Status Register (IDASR)—Offset 2h 2368
52.15 Registers in I/O Space—IDE_HOST_BMIOBAR 2369
52.15.1 IDE Primary Bus Master Command Register (IDEPBMCR)—Offset 0h 2369
52.15.2 IDE Primary Bus Master Device Specific 0 Register (IDEPBMDS0R)—Offset 1h 2370
52.15.3 IDE Primary Bus Master Status Register (IDEPBMSR)—Offset 2h 2371
52.15.4 IDE Primary Bus Master Device Specific 1 Register (IDEPBMDS1R)—Offset 3h 2373
52.15.5 IDE Primary Bus Master Descriptor Table Pointer Register Byte 0 (IDEPBMDTPR0)—Offset 4h 2373
52.15.6 IDE Primary Bus Master Descriptor Table Pointer Register Byte 1 (IDEPBMDTPR1)—Offset 5h 2373
52.15.7 IDE Primary Bus Master Descriptor Table Pointer Register Byte 2 (IDEPBMDTPR2)—Offset 6h 2374
52.15.8 IDE Primary Bus Master Descriptor Table Pointer Register Byte 3 (IDEPBMDTPR3)—Offset 7h 2374
52.15.9 IDE Secondary Bus Master Command Register (IDESBMCR)—Offset 8h 2375
52.15.10 IDE Secondary Bus Master Device Specific 0 Register (IDESBMDS0R)—Offset 9h 2375
52.15.11 IDE Secondary Bus Master Status Register (IDESBMSR)—Offset Ah 2376
52.15.12 IDE Secondary Bus Master Device Specific 1 Register (IDESBMDS1R)—Offset Bh 2377
52.15.13 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0 (IDESBMDTPR0)—Offset Ch 2377
52.15.14 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1 (IDESBMDTPR1)—Offset Dh 2378
52.15.15 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2 (IDESBMDTPR2)—Offset Eh 2378
52.15.16 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3 (IDESBMDTPR3)—Offset Fh 2379
52.16 Sideband Registers—KT (Host) 2380
52.16.1 KT Host Interrupt Pin Register (KTHIPINR)—Offset 0h 2380
52.16.2 BIOS KT Host PCI Function Disable Register (BKTHDISR)—Offset 4h 2380
52.17 Sideband Registers—IDE (Host) 2381
52.17.1 IDE Host Interrupt Pin Register (IDEHIPINR)—Offset 0h 2381
52.17.2 BIOS IDE Host PCI Function Disable Register (BIDEHDISR)—Offset 4h 2381

53 HSUART Controller - B0, D26, F(0, 1, 2) 2382
53.1 Introduction and Index 2382
53.1.1 Host Configuration Space 2383
53.1.2 Host Memory Space—MEMBA 2384
53.1.3 Host I/O Space—IOBA 2386
53.2 Registers in Configuration Space 2387
53.2.1 VENDOR_DEVICE_ID—Offset 0h 2387
53.2.2 CMD_STAT_REG—Offset 4h 2388
53.2.3 REV_CLASS_CODE—Offset 8h 2390
53.2.4 CACHE—Offset Ch 2390
53.2.5 IOBA—Offset 10h 2391
53.2.6 MEMBA—Offset 14h 2391
53.2.7 SUBSYSTEM_VENDOR_ID—Offset 2Ch 2392
53.2.8 CAP_PTR—Offset 34h 2392
53.2.9 INTERRUPT—Offset 3Ch 2392
53.2.10 MSIC—Offset 40h 2393
53.2.11 MSIA—Offset 44h 2394
53.2.12 MSID—Offset 48h 2394
53.2.13 PMC—Offset 50h 2395
53.2.14 PMCSR—Offset 54h 2396
53.2.15 DSC—Offset 60h 2397
53.2.16 FUNC_RDCFG_HIDE—Offset 74h 2398
53.3 Registers in Memory Space—MEMBA 2399
53.3.1 RBR_THR_DLL—Offset 0h 2399
53.3.2 IER_DLH—Offset 1h 2399
53.3.3 IIR_FCR—Offset 2h 2400
53.3.4 LCR—Offset 3h 2400
53.3.5 MCR—Offset 4h 2402
53.3.6 LSR—Offset 5h 2404
53.3.7 MSR—Offset 6h 2406
53.3.8 SPR—Offset 7h 2408
53.3.9 UART_FISR—Offset 8h 2408
53.3.10 RFOR—Offset 20h 2408
53.3.11 ABR—Offset 24h 2409
53.3.12 ACR—Offset 28h 2410
53.3.13 PSR—Offset 30h 2410
53.3.14 UCMR—Offset 34h 2410
53.3.15 UCDR—Offset 38h 2411
53.3.16 CH0SR—Offset 80h 2412
53.3.17 CH0CR—Offset 84h 2412
53.3.18 CH0DCR—Offset 88h 2414
53.3.19 CH0BSR—Offset 90h 2415
53.3.20 CH0MTSR—Offset 94h 2415
53.3.21 CH0D0SAR—Offset A0h 2415
53.3.22 CH0D0TSR—Offset A4h 2416
53.3.23 CH0D1SAR—Offset A8h 2416
53.3.24 CH0D1TSR—Offset ACh 2416
53.3.25 CH0D2SAR—Offset B0h 2417
53.3.26 CH0D2TSR—Offset B4h 2417
53.3.27 CH0D3SAR—Offset B8h 2418
53.3.28 CH0D3TSR—Offset BCh 2418
53.3.29 CH1SR—Offset C0h 2419
53.3.30 CH1CR—Offset C4h 2420
53.3.31 CH1DCR—Offset C8h 2421
53.3.32 CH1BSR—Offset D0h 2422

53.3.33 CH1MTSR—Offset D4h 2422
53.3.34 CH1D0SAR—Offset E0h 2422
53.3.35 CH1D0TSR—Offset E4h 2423
53.3.36 CH1D1SAR—Offset E8h 2423
53.3.37 CH1D1TSR—Offset ECh 2423
53.3.38 CH1D2SAR—Offset F0h 2424
53.3.39 CH1D2TSR—Offset F4h 2424
53.3.40 CH1D3SAR—Offset F8h 2425
53.3.41 CH1D3TSR—Offset FCh 2425
53.4 Registers in I/O Space—IOBA 2426
53.4.1 RBR_THR_DLL—Offset 0h 2426
53.4.2 IER_DLH—Offset 1h 2426
53.4.3 IIR_FCR—Offset 2h 2427
53.4.4 LCR—Offset 3h 2428
53.4.5 MCR—Offset 4h 2430
53.4.6 LSR—Offset 5h 2432
53.4.7 MSR—Offset 6h 2434
53.4.8 SPR—Offset 7h 2436

54 Innovation Engine - B0, D27, F(0, 1, 3, 4) 2437
54.1 Introduction and Index 2437
54.1.1 Host Configuration Space—HECI1 (F:0) 2438
54.1.2 Host Configuration Space—HECI2 (F:1) 2440
54.1.3 Host Configuration Space—HECI3 (F:4) 2441
54.1.4 Host Configuration Space—KT (F:3) 2442
54.1.5 Host Configuration Space—IDE (F:2) 2443
54.1.6 Host Memory Space—HECI1_MMIO_MBAR 2444
54.1.7 Host Memory Space—HECI2_MMIO_MBAR 2445
54.1.8 Host Memory Space—HECI3_MMIO_MBAR 2446
54.1.9 Host Memory Space—KT_HOST_MEMBAR 2447
54.1.10 Host Memory Space—Fixed Address 2448
54.1.11 Host I/O Space—KT_HOST_IOBAR 2449
54.1.12 Host I/O Space—IDE_HOST_PCMDIOBAR 2450
54.1.13 Host I/O Space—IDE_HOST_PCTLIOBAR 2451
54.1.14 Host I/O Space—IDE_HOST_BMIOBAR 2452
54.1.15 Sideband Registers 2453
54.2 Registers in Configuration Space—HECI1 2454
54.2.1 Identifiers (HECI1_ID)—Offset 0h 2454
54.2.2 Command (HECI1_CMD)—Offset 4h 2455
54.2.3 Status (HECI1_STS)—Offset 6h 2456
54.2.4 Revision ID and Class Code (HECI1_RID_CC)—Offset 8h 2457
54.2.5 Cache Line Size (HECI1_CLS)—Offset Ch 2457
54.2.6 Master Latency Timer (HECI1_MLT)—Offset Dh 2457
54.2.7 Header Type (HECI1_HTYPE)—Offset Eh 2458
54.2.8 Built In Self-Test (HECI1_BIST)—Offset Fh 2458
54.2.9 HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h 2458
54.2.10 HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h 2459
54.2.11 Sub System Identifiers (HECI1_SS)—Offset 2Ch 2459
54.2.12 Capabilities Pointer (HECI1_CAP)—Offset 34h 2459
54.2.13 Interrupt Information (HECI1_INTR)—Offset 3Ch 2460
54.2.14 Minimum Grant (HECI1_MGNT)—Offset 3Eh 2460
54.2.15 Maximum Latency (HECI1_MLAT)—Offset 3Fh 2460
54.2.16 Host Firmware Status (HECI1_HFS)—Offset 40h 2461
54.2.17 Miscellaneous Shadow (HECI1_MISC_SHDW)—Offset 44h 2463
54.2.18 General Status Shadow 1 (HECI1_GS_SHDW1)—Offset 48h 2464

54.2.19 Host General Status (HECI1_H_GS1)—Offset 4Ch 2465
54.2.20 PCI Power Management Capability ID (HECI1_PID)—Offset 50h 2465
54.2.21 PCI Power Management Capabilities (HECI1_PC)—Offset 52h 2465
54.2.22 PCI Power Management Control and Status (HECI1_PMCS)—Offset 54h 2466
54.2.23 General Status Shadow 2 (HECI1_GS_SHDW2)—Offset 60h 2466
54.2.24 General Status Shadow 3 (HECI1_GS_SHDW3)—Offset 64h 2467
54.2.25 General Status Shadow 4 (HECI1_GS_SHDW4)—Offset 68h 2467
54.2.26 General Status Shadow 5 (HECI1_GS_SHDW5)—Offset 6Ch 2467
54.2.27 Host General Status 2 (HECI1_H_GS2)—Offset 70h 2467
54.2.28 Host General Status 3 (HECI1_H_GS3)—Offset 74h 2468
54.2.29 Message Signaled Interrupt Identifiers (HECI1_MID)—Offset 8Ch 2468
54.2.30 Message Signaled Interrupt Message Control (HECI1_MC)—Offset 8Eh 2468
54.2.31 Message Signaled Interrupt Message Address (HECI1_MA)—Offset 90h 2469
54.2.32 Message Signaled Interrupt Upper Address (HECI1_MUA)—Offset 94h 2469
54.2.33 Message Signaled Interrupt Message Data (HECI1_MD)—Offset 98h 2469
54.2.34 HECI Interrupt Delivery Mode (HECI1_HIDM)—Offset A0h 2470
54.2.35 Host Extend Register Status (HECI1_HERS)—Offset BCh 2470
54.2.36 Host Extend Register DW1. (HECI1_HER1)—Offset C0h 2471
54.2.37 Host Extend Register DW2. (HECI1_HER2)—Offset C4h 2471
54.2.38 Host Extend Register DW3. (HECI1_HER3)—Offset C8h 2471
54.2.39 Host Extend Register DW4. (HECI1_HER4)—Offset CCh 2471
54.2.40 Host Extend Register DW5. (HECI1_HER5)—Offset D0h 2472
54.2.41 Host Extend Register DW6. (HECI1_HER6)—Offset D4h 2472
54.2.42 Host Extend Register DW7. (HECI1_HER7)—Offset D8h 2472
54.2.43 Host Extend Register DW8. (HECI1_HER8)—Offset DCh 2472
54.2.44 Manufacturer's ID (HECI1_MANID)—Offset F8h 2473
54.3 Registers in Configuration Space—HECI2 2474
54.3.1 Identifiers (HECI2_ID)—Offset 0h 2474
54.3.2 Command (HECI2_CMD)—Offset 4h 2475
54.3.3 Status (HECI2_STS)—Offset 6h 2476
54.3.4 Revision ID and Class Code (HECI2_RID_CC)—Offset 8h 2477
54.3.5 Cache Line Size (HECI2_CLS)—Offset Ch 2477
54.3.6 Master Latency Timer (HECI2_MLT)—Offset Dh 2477
54.3.7 Header Type (HECI2_HTYPE)—Offset Eh 2478
54.3.8 Built In Self-Test (HECI2_BIST)—Offset Fh 2478
54.3.9 HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h 2478
54.3.10 HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h 2479
54.3.11 Sub System Identifiers (HECI2_SS)—Offset 2Ch 2479
54.3.12 Capabilities Pointer (HECI2_CAP)—Offset 34h 2479
54.3.13 Interrupt Information (HECI2_INTR)—Offset 3Ch 2480
54.3.14 Minimum Grant (HECI2_MGNT)—Offset 3Eh 2480
54.3.15 Maximum Latency (HECI2_MLAT)—Offset 3Fh 2480
54.3.16 Host Firmware Status (HECI2_HFS)—Offset 40h 2481
54.3.17 General Status Shadow 1 (HECI2_GS_SHDW1)—Offset 48h 2483
54.3.18 Host General Status (HECI2_H_GS1)—Offset 4Ch 2484
54.3.19 PCI Power Management Capability ID (HECI2_PID)—Offset 50h 2484
54.3.20 PCI Power Management Capabilities (HECI2_PC)—Offset 52h 2485
54.3.21 PCI Power Management Control and Status (HECI2_PMCS)—Offset 54h 2486
54.3.22 General Status Shadow 2 (HECI2_GS_SHDW2)—Offset 60h 2486
54.3.23 General Status Shadow 3 (HECI2_GS_SHDW3)—Offset 64h 2487
54.3.24 General Status Shadow 4 (HECI2_GS_SHDW4)—Offset 68h 2487
54.3.25 General Status Shadow 5 (HECI2_GS_SHDW5)—Offset 6Ch 2487
54.3.26 Host General Status 2 (HECI2_H_GS2)—Offset 70h 2487

54.3.27 Host General Status 3 (HECI2_H_GS3)—Offset 74h 2488
54.3.28 Message Signaled Interrupt Identifiers (HECI2_MID)—Offset 8Ch 2488
54.3.29 Message Signaled Interrupt Message Control (HECI2_MC)—Offset 8Eh 2488
54.3.30 Message Signaled Interrupt Message Address (HECI2_MA)—Offset 90h 2489
54.3.31 Message Signaled Interrupt Upper Address (HECI2_MUA)—Offset 94h 2489
54.3.32 Message Signaled Interrupt Message Data (HECI2_MD)—Offset 98h 2489
54.3.33 HECI Interrupt Delivery Mode (HECI2_HIDM)—Offset A0h 2490
54.3.34 Manufacturer's ID (HECI2_MANID)—Offset F8h 2490
54.4 Registers in Configuration Space—HECI3 2491
54.4.1 Identifiers (HECI3_ID)—Offset 0h 2491
54.4.2 Command (HECI3_CMD)—Offset 4h 2492
54.4.3 Status (HECI3_STS)—Offset 6h 2493
54.4.4 Revision ID and Class Code (HECI3_RID_CC)—Offset 8h 2494
54.4.5 Cache Line Size (HECI3_CLS)—Offset Ch 2494
54.4.6 Master Latency Timer (HECI3_MLT)—Offset Dh 2494
54.4.7 Header Type (HECI3_HTYPE)—Offset Eh 2495
54.4.8 Built In Self-Test (HECI3_BIST)—Offset Fh 2495
54.4.9 HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h 2495
54.4.10 HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h 2496
54.4.11 Sub System Identifiers (HECI3_SS)—Offset 2Ch 2496
54.4.12 Capabilities Pointer (HECI3_CAP)—Offset 34h 2496
54.4.13 Interrupt Information (HECI3_INTR)—Offset 3Ch 2497
54.4.14 Minimum Grant (HECI3_MGNT)—Offset 3Eh 2497
54.4.15 Maximum Latency (HECI3_MLAT)—Offset 3Fh 2497
54.4.16 Host Firmware Status (HECI3_HFS)—Offset 40h 2498
54.4.17 General Status Shadow 1 (HECI3_GS_SHDW1)—Offset 48h 2500
54.4.18 Host General Status (HECI3_H_GS1)—Offset 4Ch 2501
54.4.19 PCI Power Management Capability ID (HECI3_PID)—Offset 50h 2501
54.4.20 PCI Power Management Capabilities (HECI3_PC)—Offset 52h 2502
54.4.21 PCI Power Management Control and Status (HECI3_PMCS)—Offset 54h 2503
54.4.22 General Status Shadow 2 (HECI3_GS_SHDW2)—Offset 60h 2503
54.4.23 General Status Shadow 3 (HECI3_GS_SHDW3)—Offset 64h 2504
54.4.24 General Status Shadow 4 (HECI3_GS_SHDW4)—Offset 68h 2504
54.4.25 General Status Shadow 5 (HECI3_GS_SHDW5)—Offset 6Ch 2504
54.4.26 Host General Status 2 (HECI3_H_GS2)—Offset 70h 2504
54.4.27 Host General Status 3 (HECI3_H_GS3)—Offset 74h 2505
54.4.28 Message Signaled Interrupt Identifiers (HECI3_MID)—Offset 8Ch 2505
54.4.29 Message Signaled Interrupt Message Control (HECI3_MC)—Offset 8Eh 2505
54.4.30 Message Signaled Interrupt Message Address (HECI3_MA)—Offset 90h 2506
54.4.31 Message Signaled Interrupt Upper Address (HECI3_MUA)—Offset 94h 2506
54.4.32 Message Signaled Interrupt Message Data (HECI3_MD)—Offset 98h 2506
54.4.33 HECI Interrupt Delivery Mode (HECI3_HIDM)—Offset A0h 2507
54.4.34 Manufacturer's ID (HECI3_MANID)—Offset F8h 2507
54.5 Registers in Configuration Space—KT (Host) 2508
54.5.1 Device ID and Vendor ID (KT_HOST_DID_VID)—Offset 0h 2508
54.5.2 Status and Command (KT_HOST_STS_CMD)—Offset 4h 2509
54.5.3 Class Code and Revision ID (KT_HOST_CC_RID)—Offset 8h 2511
54.5.4 BIST, Header Type, Latency Timer, and Cache Line Size (KT_HOST_BIST_HTYPE_LT_CLS)—Offset Ch 2512
54.5.5 KT IO BAR (KT_HOST_IOBAR)—Offset 10h 2512
54.5.6 KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h 2513
54.5.7 Cardbus CIS Pointer (KT_HOST_CCP)—Offset 28h 2513
54.5.8 Subsystem ID and Subsystem Vendor ID (KT_HOST_SID_SVID)—Offset 2Ch 2514

54.5.9 Expansion ROM Base Address (KT_HOST_XRBAR)—Offset 30h 2514
54.5.10 Capabilities List Pointer (KT_HOST_CAPP)—Offset 34h 2514
54.5.11 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (KT_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch 2515
54.5.12 MSI Message Control, Next Pointer and Capability ID (KT_HOST_MSIMC_MSINP_MSICID)—Offset 40h 2516
54.5.13 MSI Message Address (KT_HOST_MSIMA)—Offset 44h 2516
54.5.14 MSI Message Upper Address (KT_HOST_MSIMUA)—Offset 48h 2517
54.5.15 MSI Message Data (KT_HOST_MSIMD)—Offset 4Ch 2517
54.5.16 Power Management Capabilities, Next Pointer and Capability ID (KT_HOST_PMCAP_PMNP_PMCID)—Offset 50h 2518
54.5.17 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (KT_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h 2519
54.5.18 Process Stepping Information (KT_HOST_PSI)—Offset F8h 2520
54.6 Registers in Configuration Space—IDE (Host) 2521
54.6.1 Device ID and Vendor ID (IDE_HOST_DID_VID)—Offset 0h 2521
54.6.2 Status and Command (IDE_HOST_STS_CMD)—Offset 4h..... 2522
54.6.3 Class Code and Revision ID (IDE_HOST_CC_RID)—Offset 8h 2524
54.6.4 BIST, Header Type, Latency Timer, and Cache Line Size (IDE_HOST_BIST_HTYPE_LT_CLS)—Offset Ch..... 2525
54.6.5 IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h 2525
54.6.6 IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h 2526
54.6.7 IDE Secondary Command Block IO BAR (IDE_HOST_SCMDIOBAR)—Offset 18h 2526
54.6.8 IDE Secondary Control Block IO BAR (IDE_HOST_SCTLIOBAR)—Offset 1Ch 2526
54.6.9 IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h..... 2527
54.6.10 Cardbus CIS Pointer (IDE_HOST_CCP)—Offset 28h 2527
54.6.11 Subsystem ID and Subsystem Vendor ID (IDE_HOST_SID_SVID)—Offset 2Ch 2527
54.6.12 Expansion ROM Base Address (IDE_HOST_XRBAR)—Offset 30h 2528
54.6.13 Capabilities List Pointer (IDE_HOST_CAPP)—Offset 34h 2528
54.6.14 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (IDE_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch..... 2529
54.6.15 MSI Message Control, Next Pointer and Capability ID (IDE_HOST_MSIMC_MSINP_MSICID)—Offset 40h..... 2530
54.6.16 MSI Message Address (IDE_HOST_MSIMA)—Offset 44h..... 2530
54.6.17 MSI Message Upper Address (IDE_HOST_MSIMUA)—Offset 48h..... 2531
54.6.18 MSI Message Data (IDE_HOST_MSIMD)—Offset 4Ch..... 2531
54.6.19 Power Management Capabilities, Next Pointer and Capability ID (IDE_HOST_PMCAP_PMNP_PMCID)—Offset 50h..... 2532
54.6.20 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (IDE_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h..... 2533
54.6.21 Process Stepping Information (IDE_HOST_PSI)—Offset F8h 2534
54.7 Registers in Memory Space—HECI1_MMIO_MBAR 2535
54.7.1 Host CB Write Window (HECI1_H_CB_WW)—Offset 0h 2535
54.7.2 Host Control and Status Register (HECI1_H_CSR)—Offset 4h 2536
54.7.3 CSE Circular Buffer Read Window (HECI1_CSE_CB_RW)—Offset 8h 2537
54.7.4 CSE Control and Status Register Host Access (HECI1_CSE_CSR_HA)—Offset Ch 2537
54.7.5 D0i3 Control (HECI1_D0I3C)—Offset 800h..... 2538
54.8 Registers in Memory Space—HECI2_MMIO_MBAR 2539

54.8.1 Host CB Write Window (HECI2_H_CB_WW)—Offset 0h 2539
54.8.2 Host Control and Status Register (HECI2_H_CSR)—Offset 4h 2540
54.8.3 CSE Circular Buffer Read Window (HECI2_CSE_CB_RW)—Offset 8h 2541
54.8.4 CSE Control and Status Register Host Access (HECI2_CSE_CSR_HA)—Offset Ch 2541
54.8.5 D0i3 Control (HECI2_D0I3C)—Offset 800h 2542
54.9 Registers in Memory Space—HECI3_MMIO_MBAR 2543
54.9.1 Host CB Write Window (HECI3_H_CB_WW)—Offset 0h 2543
54.9.2 Host Control and Status Register (HECI3_H_CSR)—Offset 4h 2544
54.9.3 CSE Circular Buffer Read Window (HECI3_CSE_CB_RW)—Offset 8h 2545
54.9.4 CSE Control and Status Register Host Access (HECI3_CSE_CSR_HA)—Offset Ch 2545
54.9.5 D0i3 Control (HECI3_D0I3C)—Offset 800h 2546
54.10 Registers in Memory Space—KT_HOST_MEMBAR 2547
54.10.1 KT Receive Buffer Register (MEM_KTRBR)—Offset 0h 2547
54.10.2 KT Transmitter Holding Register (MEM_KTTHR)—Offset 0h 2547
54.10.3 KT Divisor Latch LSB Register (MEM_KTDLLR)—Offset 0h 2547
54.10.4 KT Interrupt Enable register (MEM_KTIER)—Offset 1h 2548
54.10.5 KT Divisor Latch MSB Register (MEM_KTDLMR)—Offset 1h 2548
54.10.6 KT Interrupt Identification Register (MEM_KTIIR)—Offset 2h 2549
54.10.7 KT FIFO Control register (MEM_KTFCR)—Offset 2h 2550
54.10.8 KT Line Control register (MEM_KTLCR)—Offset 3h 2551
54.10.9 KT Modem Control register (MEM_KTMCR)—Offset 4h 2552
54.10.10 KT Line Status register (MEM_KTLSR)—Offset 5h 2553
54.10.11 KT Modem Status register (MEM_KTMSR)—Offset 6h 2554
54.10.12 KT Scratch register (MEM_KTSCR)—Offset 7h 2554
54.11 Registers in Memory Space—Fixed Address 2555
54.11.1 FTPM Locality State (HOST_LOC_0_LOC_STATE_HROA)—Offset FED40000h 2555
54.11.2 FTPM Locality Reserved (HOST_LOC_0_LOC_RSVD)—Offset FED40004h 2555
54.11.3 FTPM Locality n Control Register (HOST_LOC_0_LOC_CTRL)—Offset FED40008h 2556
54.11.4 FTPM Locality n Status Register Host Read Only Access. (HOST_LOC_0_LOC_STS_HROA)—Offset FED4000Ch 2556
54.11.5 FTPM Locality Config Area Reserved Read Write[0-7] (HOST_LOC_0_RSVD_RW1[0-7])—Offset FED40010h, Count 8, Stride 4h 2556
54.11.6 FTPM Interface ID Host Read Only Access 0 (HOST_LOC_0_INTF_ID_0)—Offset FED40030h 2557
54.11.7 FTPM Interface ID Host Read Only Access 1 (HOST_LOC_0_INTF_ID_1)—Offset FED40034h 2557
54.11.8 FTPM Locality Config Area Reserved Read Write[0-1] (HOST_LOC_0_RSVD_RW2[0-1])—Offset FED40038h, Count 2, Stride 4h 2557
54.11.9 Control Area Request (HOST_LOC_0_CA_REQUEST)—Offset FED40040h 2558
54.11.10 Control Area Status (HOST_LOC_0_CA_STATUS)—Offset FED40044h 2558
54.11.11 Control Area Cancel (HOST_LOC_0_CA_CANCEL)—Offset FED40048h 2558
54.11.12 Control Area Start (HOST_LOC_0_CA_START)—Offset FED4004Ch 2559
54.11.13 Control Area Interrupt Reserved Part 1 (HOST_LOC_0_CA_INT_RSVD1)—Offset FED40050h 2559
54.11.14 Control Area Interrupt Reserved Part 2 (HOST_LOC_0_CA_INT_RSVD2)—Offset FED40054h 2559
54.11.15 Control Area Command Size (HOST_LOC_0_CA_CMD_SZ)—Offset FED40058h 2560
54.11.16 Control Area Command Part 1 (HOST_LOC_0_CA_CMD1)—Offset FED4005Ch 2560

54.11.17 Control Area Command Part 2 (HOST_LOC_0_CA_CMD2)—Offset FED40060h 2560
54.11.18 Control Area Response Size (HOST_LOC_0_CA_RSP_SZ)—Offset FED40064h 2560
54.11.19 Control Area Response Part 1 (HOST_LOC_0_CA_RSP1)—Offset FED40068h 2561
54.11.20 Control Area Response Part 2 (HOST_LOC_0_CA_RSP2)—Offset FED4006Ch 2561
54.11.21 FTPM Reserved Read Write[0-3] (HOST_LOC_0_RSVD_RW3[0-3])—Offset FED40070h, Count 4, Stride 4h 2561
54.11.22 FTPM Command and Response Buffer[0-991] (HOST_LOC_0_FTPM_CRB[0-991])—Offset FED40080h, Count 992, Stride 4h 2561
54.12 Registers in I/O Space—KT_HOST_IOBAR 2562
54.12.1 KT Receive Buffer Register (IO_KTRBR)—Offset 0h 2562
54.12.2 KT Transmitter Holding Register (IO_KTTHR)—Offset 0h 2562
54.12.3 KT Divisor Latch LSB Register (IO_KTDLLR)—Offset 0h 2563
54.12.4 KT Interrupt Enable register (IO_KTIER)—Offset 1h 2563
54.12.5 KT Divisor Latch MSB Register (IO_KTDLMR)—Offset 1h 2564
54.12.6 KT Interrupt Identification Register (IO_KTIIR)—Offset 2h 2564
54.12.7 KT FIFO Control register (IO_KTFCR)—Offset 2h 2565
54.12.8 KT Line Control register (IO_KTLCR)—Offset 3h 2566
54.12.9 KT Modem Control register (IO_KTMCR)—Offset 4h 2567
54.12.10 KT Line Status register (IO_KTLSR)—Offset 5h 2568
54.12.11 KT Modem Status register (IO_KTMSR)—Offset 6h 2569
54.12.12 KT Scratch register (IO_KTSCR)—Offset 7h 2569
54.13 Registers in I/O Space—IDE_HOST_PCMDIOBAR 2570
54.13.1 IDE Data Register (IDEDATA)—Offset 0h 2570
54.13.2 IDE Features Register (IDEFR)—Offset 1h 2570
54.13.3 IDE Error Register DEV0 (IDEERD0)—Offset 1h 2571
54.13.4 IDE Error Register DEV1 (IDEERD1)—Offset 1h 2571
54.13.5 IDE Sector Count In Register (IDESCIR)—Offset 2h 2572
54.13.6 IDE Sector Count Out Register DEV0 (IDESCOR0)—Offset 2h 2572
54.13.7 IDE Sector Count Out Register DEV1 (IDESCOR1)—Offset 2h 2572
54.13.8 IDE Sector Number In Register (IDESNIR)—Offset 3h 2573
54.13.9 IDE Sector Number Out Register DEV0 (IDESNOR0)—Offset 3h 2573
54.13.10 IDE Sector Number Out Register DEV1 (IDESNOR1)—Offset 3h 2573
54.13.11 IDE Cylinder Low In Register (IDECLIR)—Offset 4h 2574
54.13.12 IDE Cylinder Low Out Register DEV0 (IDCLOR0)—Offset 4h 2574
54.13.13 IDE Cylinder Low Out Register DEV1 (IDCLOR1)—Offset 4h 2575
54.13.14 IDE Cylinder High In Register (IDECHIR)—Offset 5h 2575
54.13.15 IDE Cylinder High Out Register DEV0 (IDCHOR0)—Offset 5h 2576
54.13.16 IDE Cylinder High Out Register DEV1 (IDCHOR1)—Offset 5h 2576
54.13.17 IDE Drive/Head In Register (IDEDHIR)—Offset 6h 2577
54.13.18 IDE Drive/Head Out Register DEV0 (IDDHOR0)—Offset 6h 2577
54.13.19 IDE Drive/Head Out Register DEV1 (IDDHOR1)—Offset 6h 2578
54.13.20 IDE Command Register (IDECR)—Offset 7h 2578
54.13.21 IDE Status Register DEV0 (IDESR0)—Offset 7h 2579
54.13.22 IDE Status Register DEV1 (IDESR1)—Offset 7h 2580
54.14 Registers in I/O Space—IDE_HOST_PCTLIOBAR 2581
54.14.1 IDE Device Control Register (IDDCR)—Offset 2h 2581
54.14.2 IDE Alternate Status Register (IDASR)—Offset 2h 2581
54.15 Registers in I/O Space—IDE_HOST_BMIOBAR 2582
54.15.1 IDE Primary Bus Master Command Register (IDEPBMCR)—Offset 0h 2582

54.15.2 IDE Primary Bus Master Device Specific 0 Register (IDEPBMDS0R)—Offset 1h 2583
54.15.3 IDE Primary Bus Master Status Register (IDEPBMSR)—Offset 2h 2584
54.15.4 IDE Primary Bus Master Device Specific 1 Register (IDEPBMDS1R)—Offset 3h 2586
54.15.5 IDE Primary Bus Master Descriptor Table Pointer Register Byte 0 (IDEPBMDTPR0)—Offset 4h 2586
54.15.6 IDE Primary Bus Master Descriptor Table Pointer Register Byte 1 (IDEPBMDTPR1)—Offset 5h 2586
54.15.7 IDE Primary Bus Master Descriptor Table Pointer Register Byte 2 (IDEPBMDTPR2)—Offset 6h 2587
54.15.8 IDE Primary Bus Master Descriptor Table Pointer Register Byte 3 (IDEPBMDTPR3)—Offset 7h 2587
54.15.9 IDE Secondary Bus Master Command Register (IDESBMCR)—Offset 8h 2588
54.15.10 IDE Secondary Bus Master Device Specific 0 Register (IDESBMDS0R)—Offset 9h 2588
54.15.11 IDE Secondary Bus Master Status Register (IDESBMSR)—Offset Ah 2589
54.15.12 IDE Secondary Bus Master Device Specific 1 Register (IDESBMDS1R)—Offset Bh 2590
54.15.13 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0 (IDESBMDTPR0)—Offset Ch 2590
54.15.14 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1 (IDESBMDTPR1)—Offset Dh 2591
54.15.15 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2 (IDESBMDTPR2)—Offset Eh 2591
54.15.16 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3 (IDESBMDTPR3)—Offset Fh 2592
54.16 Sideband Registers—KT (Host) 2593
54.16.1 KT Host Interrupt Pin Register (KTHIPINR)—Offset 0h 2593
54.16.2 BIOS KT Host PCI Function Disable Register (BKTHDISR)—Offset 4h 2593
54.17 Sideband Registers—IDE (Host) 2594
54.17.1 IDE Host Interrupt Pin Register (IDEHIPINR)—Offset 0h 2594
54.17.2 BIOS IDE Host PCI Function Disable Register (BIDEHDISR)—Offset 4h 2594

55 eMMC Controller - B0, D28, F0 2595
55.1 Introduction and Index 2595
55.1.1 Host Memory Space—BAR or BAR1 2596
55.2 Registers in Memory Space—BAR or BAR1 2599
55.2.1 SDMA System Address Register/Argument2 Register (SDMASYSADDR)—Offset 0h 2599
55.2.2 BlockSize Register (BLOCKSIZE)—Offset 4h 2599
55.2.3 BlockCount Register (BLOCKCOUNT)—Offset 6h 2599
55.2.4 Argument1 Register (ARGUMENT1)—Offset 8h 2600
55.2.5 TransferMode Register (TRANSFERMODE)—Offset Ch 2600
55.2.6 Command Register (COMMAND)—Offset Eh 2600
55.2.7 Response Register (RESPONSE1)—Offset 10h 2601
55.2.8 Response Register (RESPONSE2)—Offset 14h 2602
55.2.9 Response Register (RESPONSE3)—Offset 16h 2602
55.2.10 Response Register (RESPONSE4)—Offset 18h 2602
55.2.11 Response Register (RESPONSE5)—Offset 1Ah 2602
55.2.12 Response Register (RESPONSE6)—Offset 1Ch 2603
55.2.13 Response Register (RESPONSE7)—Offset 1Eh 2603
55.2.14 Buffer DataPort Register (DATAPORT)—Offset 20h 2603
55.2.15 PresentState Register (PRESENTSTATE)—Offset 24h 2604

55.2.16 HostControl1 Register (HOSTCONTROL1)—Offset 28h 2606
55.2.17 PowerControl Register (POWERCONTROL)—Offset 29h 2607
55.2.18 BlockGapControl Register (BLOCKGAPCONTROL)—Offset 2Ah 2607
55.2.19 Wakeup Control Register (WAKEUPCONTROL)—Offset 2Bh 2608
55.2.20 Clock Control Register (CLOCKCONTROL)—Offset 2Ch 2609
55.2.21 Timeout Control Register (TIMEOUTCONTROL)—Offset 2Eh 2610
55.2.22 Software Reset Register (SOFTWARERESET)—Offset 2Fh 2610
55.2.23 Normal Interrupt Status Register (NORMALINTRSTS)—Offset 30h 2611
55.2.24 ErrorInterruptStatus Register (ERRORINTRSTS)—Offset 32h 2612
55.2.25 Normal Interrupt Status Enable Register (NORMALINTRSTSENA)—Offset 34h 2613
55.2.26 Error Interrupt Status Enable Register (ERRORINTRSTSENA)—Offset 36h 2614
55.2.27 Normal Interrupt Signal Enable Register (NORMALINTRSIGENA)—Offset 38h 2615
55.2.28 Error Interrupt Signal Enable Register (ERRORINTRSIGENA)—Offset 3Ah 2616
55.2.29 Auto CMD12 Error Status Register (AUTOCMDERRSTS)—Offset 3Ch 2617
55.2.30 Host Control2 Register (HOSTCONTROL2)—Offset 3Eh 2618
55.2.31 Capabilities Register (CAPABILITIES)—Offset 40h 2619
55.2.32 Maximum Current Capabilities Register (MAXCURRENTCAP)—Offset 48h .. 2621
55.2.33 Force Event REGISTER for AUTO CMD Error Status (FORCEEVENTFORAUTOCMDERRORSTATUS)—Offset 50h 2621
55.2.34 Force Event Register for Error Interrupt Status (FORCEEVENTFORERRINTSTS)—Offset 52h 2622
55.2.35 ADMA Error Status Register (ADMAERRSTS)—Offset 54h 2623
55.2.36 ADMA System Address Register0&1 (ADMASYSADDR01)—Offset 58h 2623
55.2.37 ADMA System Address Register1 (ADMASYSADDR2)—Offset 5Ch 2623
55.2.38 ADMA System Address Register1 (ADMASYSADDR3)—Offset 5Eh 2624
55.2.39 Preset Value Register for Initialization (PRESETVALUE0)—Offset 60h 2624
55.2.40 Preset Value Register for Default Speed (PRESETVALUE1)—Offset 62h 2625
55.2.41 Preset Value Register for High Speed (PRESETVALUE2)—Offset 64h 2625
55.2.42 Preset Value Register for SDR12 (PRESETVALUE3)—Offset 66h 2626
55.2.43 Preset Value Register for SDR25 (PRESETVALUE4)—Offset 68h 2626
55.2.44 Preset Value Register for SDR50 (PRESETVALUE5)—Offset 6Ah 2627
55.2.45 Preset Value Register for SDR104 (PRESETVALUE6)—Offset 6Ch 2627
55.2.46 Preset Value Register for DDR50 (PRESETVALUE7)—Offset 6Eh 2628
55.2.47 Boot Timeout Control Register (BOOTTIMEOUTCNT)—Offset 70h 2628
55.2.48 Preset Value Register for DDR50 (PRESETVALUE8)—Offset 74h 2629
55.2.49 Slot Interrupt Status Register (SLOTINTRSTS)—Offset FCh 2629
55.2.50 Host Controller Version Register (HOSTCONTROLLERVER)—Offset FEh 2629
55.2.51 Software Latency Tolerance Reporting (SW_LTR_VAL)—Offset 804h 2630
55.2.52 Auto Latency Tolerance Reporting (AUTO_LTR_VAL)—Offset 808h 2630
55.2.53 Capabilities Bypass Control Register (CAP_BYPS)—Offset 810h 2631
55.2.54 eMMC Capabilities Bypass Register1 (CAP_BYPS_REG1)—Offset 814h 2632
55.2.55 eMMC Capabilities Bypass Register2 (CAP_BYPS_REG2)—Offset 818h 2634
55.2.56 D0i3 Control Register (REG_D0i3)—Offset 81Ch 2635
55.2.57 Front End Module Tx Command Path Delay Register (Tx_CMD_DLY)—Offset 820h 2635
55.2.58 Front End Module Tx Data Path Delay Register1 (Tx_DATA_DLY_1)—Offset 824h 2636
55.2.59 Front End Module Tx Data Path Delay Register2 (Tx_DATA_DLY_2)—Offset 828h 2637
55.2.60 Front End Module Rx Data Path Delay Register1 (Rx_CMD_DATA_DLY_1)—Offset 82Ch 2638

55.2.61 Front End Module Rx Strobe Path Delay Register (Rx_STROBE_CTRL_PATH)—Offset 830h 2639
55.2.62 Front End Module Rx Data Path Delay Register2 (Rx_CMD_DATA_DLY_2)—Offset 834h 2640
55.2.63 Master DLL Software Control Register (MASTER_DLL)—Offset 838h 2641
55.2.64 Auto Tuning Value (AUTO_TUNING)—Offset 840h....2641
55.2.65 Root Space Select (eMMC_ROOT_SPACE)—Offset 900h....2642

56 LPC Controller - B0, D31, F0 2643
56.1 Introduction and Index 2643
56.1.1 Host Configuration Space....2644
56.2 Registers in Configuration Space 2645
56.2.1 I/O Decode Ranges (IOD)—Offset 80h....2645
56.2.2 I/O Enables (IOE)—Offset 82h....2646
56.2.3 LPC Generic I/O Range #1 (LGIR1)—Offset 84h....2647
56.2.4 LPC Generic I/O Range #2 (LGIR2)—Offset 88h....2648
56.2.5 LPC Generic I/O Range #3 (LGIR3)—Offset 8Ch....2649
56.2.6 LPC Generic I/O Range #4 (LGIR4)—Offset 90h....2650
56.2.7 USB Legacy Keyboard/Mouse Control (ULKMC)—Offset 94h....2651
56.2.8 LPC Generic Memory Range (LGMR)—Offset 98h....2653
56.2.9 FWH ID Select #1 (FS1)—Offset D0h....2653
56.2.10 FWH ID Select #2 (FS2)—Offset D4h....2654
56.2.11 BIOS Decode Enable (BDE)—Offset D8h....2655
56.2.12 BIOS Control (BC)—Offset DCh....2657
56.2.13 PCI Clock Control (PCCTL)—Offset E0h....2659

57 Primary to Side Band Bridge - B0, D31, F1 2660
57.1 Introduction and Index 2660
57.1.1 Host Configuration Space....2661
57.2 Registers in Configuration Space 2663
57.2.1 PCI Identifier (PCIID)—Offset 0h....2663
57.2.2 PCI Command (PCICMD)—Offset 4h....2664
57.2.3 PCI Status (PCISTS)—Offset 6h....2665
57.2.4 Revision ID (PCIRID)—Offset 8h....2665
57.2.5 Class Code (PCICC)—Offset 9h....2666
57.2.6 PCI Master Latency Timer (PCIMLT)—Offset Dh....2666
57.2.7 PCI Header Type (PCIHTYPE)—Offset Eh....2666
57.2.8 Sideband Register Access BAR (SBREG_BAR)—Offset 10h....2667
57.2.9 Sideband Register BAR High DWORD (SBREG_BARH)—Offset 14h....2667
57.2.10 PCI Subsystem Identifiers (PCIHSS)—Offset 2Ch....2668
57.2.11 VLW Bus:Device:Function (VBDF)—Offset 50h....2668
57.2.12 ERROR Bus:Device:Function (EBDF)—Offset 52h....2669
57.2.13 Routing Configuration (RCFG)—Offset 54h....2670
57.2.14 High Performance Event Timer Configuration (HPTC)—Offset 60h....2670
57.2.15 IOxAPIC Configuration (IOAC)—Offset 64h....2671
57.2.16 IOxAPIC Bus:Device:Function (IBDF)—Offset 6Ch....2671
57.2.17 HPET Bus:Device:Function (HBDF)—Offset 70h....2672
57.2.18 Sideband Register posted 0 (SBREGPOSTED0)—Offset 80h....2672
57.2.19 Sideband Register posted 1 (SBREGPOSTED1)—Offset 84h....2672
57.2.20 Sideband Register posted 2 (SBREGPOSTED2)—Offset 88h....2673
57.2.21 Sideband Register posted 3 (SBREGPOSTED3)—Offset 8Ch....2673
57.2.22 Sideband Register posted 4 (SBREGPOSTED4)—Offset 90h....2673
57.2.23 Sideband Register posted 5 (SBREGPOSTED5)—Offset 94h....2673
57.2.24 Sideband Register posted 6 (SBREGPOSTED6)—Offset 98h....2674
57.2.25 Sideband Register posted 7 (SBREGPOSTED7)—Offset 9Ch....2674
57.2.26 Display Bus:Device:Function (DISPBDF)—Offset A0h....2674

57.2.27 ICC Register Offsets (ICCOS)—Offset A4h 2675
57.2.28 Endpoint Mask 0 (EPMASK0)—Offset B0h 2675
57.2.29 Endpoint Mask 1 (EPMASK1)—Offset B4h 2675
57.2.30 Endpoint Mask 2 (EPMASK2)—Offset B8h 2676
57.2.31 Endpoint Mask 3 (EPMASK3)—Offset BCh 2676
57.2.32 Endpoint Mask 4 (EPMASK4)—Offset C0h 2676
57.2.33 Endpoint Mask 5 (EPMASK5)—Offset C4h 2676
57.2.34 Endpoint Mask 6 (EPMASK6)—Offset C8h 2677
57.2.35 Endpoint Mask 7 (EPMASK7)—Offset CCh 2677
57.2.36 SBI Address (SBIADDR)—Offset D0h 2677
57.2.37 SBI Data (SBIDATA)—Offset D4h 2678
57.2.38 SBI Status (SBISTAT)—Offset D8h 2678
57.2.39 SBI Routing Identification (SBIRID)—Offset DAh 2679
57.2.40 SBI Extended Address (SBIEXTADDR)—Offset DCh 2679
57.2.41 P2SB Control (P2SBC)—Offset E0h 2680
57.2.42 Unsupported Request Error Status (URES)—Offset F0h 2681
57.2.43 Unsupported Request Error Control (UREC)—Offset F4h 2681
57.2.44 Manufacturer's ID (MANID)—Offset F8h 2682

58 Power Management Controller - B0, D31, F2 2683
58.1 Introduction and Index 2683
58.1.1 Host Configuration Space 2684
58.1.2 Host Memory Space—PWRMBASE 2685
58.1.3 Host I/O Space—ABASE 2686
58.1.4 Host I/O Space—Fixed Address 2687
58.1.5 Sideband Registers 2688
58.2 Registers in Configuration Space 2689
58.2.1 PCI Identifier (PCIID)—Offset 0h 2689
58.2.2 ACPI Base Address (ABASE)—Offset 40h 2689
58.2.3 ACPI Control (ACTL)—Offset 44h 2690
58.2.4 General PM Configuration A (GEN_PMCON_A)—Offset A0h 2691
58.2.5 General PM Configuration B (GEN_PMCON_B)—Offset A4h 2693
58.2.6 Extended Test Mode Register 3 (ETR3)—Offset ACh 2695
58.3 Registers in Memory Space—PWRMBASE 2696
58.3.1 Wake Alarm Device Timer: AC (WADT_AC)—Offset 0h 2696
58.3.2 Wake Alarm Device Timer: DC (WADT_DC)—Offset 4h 2697
58.3.3 Wake Alarm Device Expired Timer: AC (WADT_EXP_AC)—Offset 8h 2698
58.3.4 Wake Alarm Device Expired Timer: DC (WADT_EXP_DC)—Offset Ch 2698
58.3.5 Power and Reset Status (PRSTS)—Offset 10h 2699
58.3.6 Power Management Configuration Reg 1 (PM_CFG)—Offset 18h 2700
58.3.7 PCH Power Management Status (PCH_PM_STS)—Offset 1Ch 2704
58.3.8 PCH Power Management Status (PCH_PM_STS2)—Offset 24h 2705
58.3.9 ADR Enable (ADR_EN)—Offset F0h 2707
58.3.10 System Time Capture Trigger (SYSTIMCT)—Offset F8h 2709
58.3.11 ACPI Timer Control (ACPI_TMR_CTL)—Offset FCh 2709
58.3.12 GPIO Configuration (GPIO_CFG)—Offset 120h 2710
58.3.13 Global Reset Causes (GBLRST_CAUSE0)—Offset 124h 2711
58.3.14 Global Reset Causes (GBLRST_CAUSE1)—Offset 128h 2713
58.3.15 Host Partition Reset Causes (HPR_CAUSE0)—Offset 12Ch 2714
58.3.16 modPHY Power Management Configuration Reg 1 (MODPHY_PM_CFG1)—Offset 200h 2715
58.3.17 modPHY Power Management Configuration Reg 2 (MODPHY_PM_CFG2)—Offset 204h 2716
58.3.18 modPHY Power Management Configuration Reg 3 (MODPHY_PM_CFG3)—Offset 208h 2718

58.3.19 modPHY Power Management Configuration Reg 4 (MODPHY_PM_CFG4)—Offset 20Ch 2719
58.3.20 IE_STS (IE_STS)—Offset 3F0h 2720
58.3.21 ME_STS (ME_STS)—Offset 3F4h 2722
58.3.22 Static PG Related Function Disable Register 1 (ST_PG_FDIS_PMC_1)—Offset 620h 2723
58.3.23 Non-Static PG Related Function Disable Register 1 (NST_PG_FDIS_1)—Offset 628h 2724
58.3.24 Non-Static PG Fuse Disable Read 1 Register (N_STPG_FUSE_SS_DIS_RD_1)—Offset 640h 2724
58.3.25 Static PG Fuse and Soft Strap Disable Read Register 2 (STPG_FUSE_SS_DIS_RD_2)—Offset 644h 2725
58.4 Registers in I/O Space—ABASE 2726
58.4.1 Power Management 1 Enables and Status (PM1_EN_STS)—Offset 0h 2726
58.4.2 Power Management 1 Control —Offset 4h 2728
58.4.3 Power Management 1 Timer (PM1_TMR)—Offset 8h 2729
58.4.4 SMI Control and Enable (SMI_EN)—Offset 30h 2730
58.4.5 SMI Status Register (SMI_STS)—Offset 34h 2732
58.4.6 General Purpose Event Control (GPE_CTRL)—Offset 40h 2735
58.4.7 Device Trap Status Register (DEVTRAP_STS)—Offset 44h 2736
58.4.8 PM2a Control Block (PM2A_CNT_BLK)—Offset 50h 2737
58.4.9 Over-Clocking WDT Control (OC_WDT_CTL)—Offset 54h 2737
58.4.10 General Purpose Event 0 Status [31:0] (GPE0_STS_31_0)—Offset 80h 2738
58.4.11 General Purpose Event 0 Status [63:32] (GPE0_STS_63_32)—Offset 84h 2739
58.4.12 General Purpose Event 0 Status [95:64] (GPE0_STS_95_64)—Offset 88h 2739
58.4.13 General Purpose Event 0 Status [127:96] (GPE0_STS_127_96)—Offset 8Ch 2740
58.4.14 General Purpose Event 0 Enable [31:0] (GPE0_EN_31_0)—Offset 90h 2742
58.4.15 General Purpose Event 0 Enable [63:32] (GPE0_EN_63_32)—Offset 94h 2742
58.4.16 General Purpose Event 0 Enable [95:64] (GPE0_EN_95_64)—Offset 98h 2742
58.4.17 General Purpose Event 0 Enable [127:96] (GPE0_EN_127_96)—Offset 9Ch 2743
58.5 Registers in I/O Space—Fixed Addresses 2745
58.5.1 Reset Control Register (RST_CNT) 2745
58.6 Sideband Registers 2746
58.6.1 Advanced Power Management Status and Control Port (APM_STS_CNT)—Offset B0h 2746
58.6.2 Misc SB Reg0 (MISC_SBR0)—Offset B4h 2746

59 SMBus - Legacy - B0, D31, F4 2748
59.1 Introduction and Index 2748
59.1.1 Registers in Configuration Space 2749
59.1.2 Registers in Memory Space—SMBMBAR 2750
59.1.3 Registers in I/O Space—SBA 2751
59.1.4 Registers in I/O Space—TCOBASE 2752
59.1.5 Sideband Registers—Host SMBus Private Configuration 2753
59.1.6 Sideband Registers—CLTT SMBus Configuration Control 2754
59.2 Registers in Configuration Space 2755
59.2.1 Vendor ID (VID)—Offset 0h 2755
59.2.2 Device ID (DID)—Offset 2h 2755
59.2.3 Command (CMD)—Offset 4h 2756

59.2.4 Device Status (DS)—Offset 6h 2757
59.2.5 Revision ID (RID)—Offset 8h 2758
59.2.6 Programming Interface (PI)—Offset 9h 2758
59.2.7 Sub Class Code (SCC)—Offset Ah 2758
59.2.8 Base Class Code (BCC)—Offset Bh 2758
59.2.9 SMBus Memory Base Address_31_0 (SMBMBAR_31_0)—Offset 10h 2759
59.2.10 SMBus Memory Base Address_63_32 (SMBMBAR_63_32)—Offset 14h 2759
59.2.11 SMB Base Address (SBA)—Offset 20h 2760
59.2.12 SVID—Offset 2Ch 2760
59.2.13 SID—Offset 2Eh 2760
59.2.14 Interrupt Line (INTLN)—Offset 3Ch 2761
59.2.15 Interrupt Pin (INTPN)—Offset 3Dh 2761
59.2.16 Host Configuration (HCFG)—Offset 40h 2762
59.2.17 TCO Base Address (TCOBASE)—Offset 50h 2763
59.2.18 TCO Control (TCOCTL)—Offset 54h 2763
59.2.19 Host_Timing (HTIM)—Offset 64h 2764
59.2.20 Manufacturer's ID (MANID)—Offset F8h 2765
59.3 Registers in Memory Space—SMBMBAR 2766
59.3.1 Host Status Register Address (HSTS)—Offset 0h 2766
59.3.2 Host Control Register (HCTL)—Offset 2h 2767
59.3.3 Host Command Register (HCMD)—Offset 3h 2769
59.3.4 Transmit Slave Address Register (TSA)—Offset 4h 2769
59.3.5 Data 0 Register (HD0)—Offset 5h 2769
59.3.6 Data 1 Register (HD1)—Offset 6h 2770
59.3.7 Host Block Data (HBD)—Offset 7h 2770
59.3.8 Packet Error Check Data Register (PEC)—Offset 8h 2771
59.3.9 Receive Slave Address Register (RSA)—Offset 9h 2771
59.3.10 Slave Data Register (SD)—Offset Ah 2772
59.3.11 Auxiliary Status (AUXS)—Offset Ch 2773
59.3.12 Auxiliary Control (AUXC)—Offset Dh 2774
59.3.13 SMLINK_PIN_CTL Register (SMLC)—Offset Eh 2775
59.3.14 SMBUS_PIN_CTL Register (SMBC)—Offset Fh 2776
59.3.15 Slave Status Register (SSTS)—Offset 10h 2777
59.3.16 Slave Command Register (SCMD)—Offset 11h 2778
59.3.17 Notify Device Address Register (NDA)—Offset 14h 2779
59.3.18 Notify Data Low Byte Register (NDLB)—Offset 16h 2779
59.3.19 Notify Data High Byte Register (NDHB)—Offset 17h 2779
59.4 Registers in I/O Space—SBA 2780
59.4.1 Host Status Register Address (HSTS)—Offset 0h 2780
59.4.2 Host Control Register (HCTL)—Offset 2h 2781
59.4.3 Host Command Register (HCMD)—Offset 3h 2783
59.4.4 Transmit Slave Address Register (TSA)—Offset 4h 2783
59.4.5 Data 0 Register (HD0)—Offset 5h 2783
59.4.6 Data 1 Register (HD1)—Offset 6h 2784
59.4.7 Host Block Data (HBD)—Offset 7h 2784
59.4.8 Packet Error Check Data Register (PEC)—Offset 8h 2785
59.4.9 Receive Slave Address Register (RSA)—Offset 9h 2785
59.4.10 Slave Data Register (SD)—Offset Ah 2786
59.4.11 Auxiliary Status (AUXS)—Offset Ch 2787
59.4.12 Auxiliary Control (AUXC)—Offset Dh 2788
59.4.13 SMLINK_PIN_CTL Register (SMLC)—Offset Eh 2789
59.4.14 SMBUS_PIN_CTL Register (SMBC)—Offset Fh 2790
59.4.15 Slave Status Register (SSTS)—Offset 10h 2791
59.4.16 Slave Command Register (SCMD)—Offset 11h 2792
59.4.17 Notify Device Address Register (NDA)—Offset 14h 2793

59.4.18 Notify Data Low Byte Register (NDLB)—Offset 16h 2793
59.4.19 Notify Data High Byte Register (NDHB)—Offset 17h 2793
59.5 Registers in I/O Space—TCOBASE 2794
59.5.1 TCO_RLD Register (TRLD)—Offset 0h 2794
59.5.2 TCO_DAT_IN Register (TDI)—Offset 2h 2794
59.5.3 TCO_DAT_OUT Register (TDO)—Offset 3h 2795
59.5.4 TCO1_STS Register (TSTS1)—Offset 4h 2795
59.5.5 TCO2_STS Register (TSTS2)—Offset 6h 2797
59.5.6 TCO1_CNT Register (TCTL1)—Offset 8h 2798
59.5.7 TCO2_CNT Register (TCTL2)—Offset Ah 2799
59.5.8 LEGACY_ELIM Register (LE)—Offset 10h 2800
59.5.9 TCO_TMR Register (TTMR)—Offset 12h 2800
59.6 Sideband Registers—Host SMBus Private Configuration 2801
59.6.1 TCO Configuration (TCOCFG)—Offset 0h 2801
59.6.2 General Control (GC)—Offset Ch 2802
59.6.3 Power Control Enable (PCE)—Offset 10h 2803
59.7 Sideband Registers—CLTT SMBus Configuration Control 2804
59.7.1 CLTT Status (CLTT_STS)—Offset 0h 2804
59.7.2 Ch0 Dimm0 Cfg Status (C0D0CFGSTS)—Offset 10h 2805
59.7.3 Ch0 Dimm1 Cfg Status (C0D1CFGSTS)—Offset 14h 2805
59.7.4 Ch0 Dimm2 Cfg Status (C0D2CFGSTS)—Offset 18h 2806
59.7.5 Ch0 Dimm3 Cfg Status (C0D3CFGSTS)—Offset 1Ch 2806
59.7.6 Ch1 Dimm0 Cfg Status (C1D0CFGSTS)—Offset 20h 2807
59.7.7 Ch1 Dimm1 Cfg Status (C1D1CFGSTS)—Offset 24h 2807
59.7.8 Ch1 Dimm2 Cfg Status (C1D2CFGSTS)—Offset 28h 2808
59.7.9 Ch1 Dimm3 Cfg Status (C1D3CFGSTS)—Offset 2Ch 2808
59.7.10 Ch0 Dimm Temp Status (C0TEMPSTS0)—Offset 30h 2809
59.7.11 Ch0 Dimm Temp Status (C0TEMPSTS1)—Offset 34h 2809
59.7.12 Ch1 Dimm Temp Status (C1TEMPSTS0)—Offset 38h 2809
59.7.13 Ch1 Dimm Temp Status (C1TEMPSTS1)—Offset 3Ch 2810
59.7.14 Host Configuration (HCFG)—Offset 40h 2810

60 SPI Controller - B0, D31, F5 2811
60.1 Introduction and Index 2811
60.1.1 Host Configuration Space 2812
60.1.2 Host Memory Space—BIOS_SPI_BAR0 2813
60.2 Registers in Configuration Space 2815
60.2.1 Device ID and Vendor ID (BIOS_SPI_DID_VID)—Offset 0h 2815
60.2.2 Status and Command (BIOS_SPI_STS_CMD)—Offset 4h 2816
60.2.3 Revision ID (BIOS_SPI_CC_RID)—Offset 8h 2818
60.2.4 BIST, Header Type, Latency Timer, Cache Line Size (BIOS_SPI_BIST_HTYPE_LT_CLS)—Offset Ch 2818
60.2.5 SPI BAR0 MMIO (BIOS_SPI_BAR0)—Offset 10h 2819
60.2.6 Cardbus CIS Pointer (BIOS_SPI_CCP)—Offset 28h 2819
60.2.7 Subsystem and Vendor ID (BIOS_SPI_SID_SVID)—Offset 2Ch 2819
60.2.8 Expansion ROM Base Address (BIOS_SPI_XRBAR)—Offset 30h 2820
60.2.9 Capabilities List Pointer (BIOS_SPI_CAPP)—Offset 34h 2820
60.2.10 SPI Unsupported Request Status (BIOS_SPI_UR_STS_CTL)—Offset D0h 2820
60.2.11 BIOS Decode Enable (BIOS_SPI_BDE)—Offset D8h 2821
60.2.12 BIOS Control (BIOS_SPI_BC)—Offset DCh 2823
60.3 Registers in Memory Space—BIOS_SPI_BAR0 2825
60.3.1 SPI BIOS MMIO PRI (BIOS_BFPREG)—Offset 0h 2825
60.3.2 Hardware Sequencing Flash Status and Control (BIOS_HSFSTS_CTL)—Offset 4h 2826
60.3.3 Flash Address (BIOS_FADDR)—Offset 8h 2828

60.3.4 Discrete Lock Bits (BIOS_DLOCK)—Offset Ch 2829
60.3.5 Flash Data 0 (BIOS_FDATA0)—Offset 10h..... 2830
60.3.6 Flash Data 1 (BIOS_FDATA1)—Offset 14h..... 2830
60.3.7 Flash Data 2 (BIOS_FDATA2)—Offset 18h..... 2830
60.3.8 Flash Data 3 (BIOS_FDATA3)—Offset 1Ch 2831
60.3.9 Flash Data 4 (BIOS_FDATA4)—Offset 20h..... 2831
60.3.10 Flash Data 5 (BIOS_FDATA5)—Offset 24h..... 2831
60.3.11 Flash Data 6 (BIOS_FDATA6)—Offset 28h..... 2832
60.3.12 Flash Data 7 (BIOS_FDATA7)—Offset 2Ch 2832
60.3.13 Flash Data 8 (BIOS_FDATA8)—Offset 30h..... 2832
60.3.14 Flash Data 9 (BIOS_FDATA9)—Offset 34h..... 2833
60.3.15 Flash Data 10 (BIOS_FDATA10)—Offset 38h 2833
60.3.16 Flash Data 11 (BIOS_FDATA11)—Offset 3Ch 2833
60.3.17 Flash Data 12 (BIOS_FDATA12)—Offset 40h 2834
60.3.18 Flash Data 13 (BIOS_FDATA13)—Offset 44h 2834
60.3.19 Flash Data 14 (BIOS_FDATA14)—Offset 48h 2834
60.3.20 Flash Data 15 (BIOS_FDATA15)—Offset 4Ch 2834
60.3.21 Flash Region Access Permissions (BIOS_FRACC)—Offset 50h..... 2835
60.3.22 Flash Region 0 (BIOS_FREG0)—Offset 54h 2836
60.3.23 Flash Region 1 (BIOS_FREG1)—Offset 58h 2836
60.3.24 Flash Region 2 (BIOS_FREG2)—Offset 5Ch 2837
60.3.25 Flash Region 3 (BIOS_FREG3)—Offset 60h 2837
60.3.26 Flash Region 4 (BIOS_FREG4)—Offset 64h 2838
60.3.27 Flash Region 5 (BIOS_FREG5)—Offset 68h 2838
60.3.28 Flash Region 6 (BIOS_FREG6)—Offset 6Ch 2839
60.3.29 Flash Region 7 (BIOS_FREG7)—Offset 70h 2839
60.3.30 Flash Region 8 (BIOS_FREG8)—Offset 74h 2840
60.3.31 Flash Region 9 (BIOS_FREG9)—Offset 78h 2840
60.3.32 Flash Region 10 (BIOS_FREG10)—Offset 7Ch..... 2841
60.3.33 Flash Region 11 (BIOS_FREG11)—Offset 80h 2841
60.3.34 Flash Protected Range 0 (BIOS_FPR0)—Offset 84h 2842
60.3.35 Flash Protected Range 1 (BIOS_FPR1)—Offset 88h 2843
60.3.36 Flash Protected Range 2 (BIOS_FPR2)—Offset 8Ch 2844
60.3.37 Flash Protected Range 3 (BIOS_FPR3)—Offset 90h 2845
60.3.38 Flash Protected Range 4 (BIOS_FPR4)—Offset 94h 2846
60.3.39 Global Protected Range 0 (BIOS_GPR0)—Offset 98h 2847
60.3.40 Software Sequencing Flash Status and Control (BIOS_SSFSTS_CTL)—Offset A0h 2848
60.3.41 Prefix Opcode and Opcode Type Configuration (BIOS_PREOP_OPTYPE)—Offset A4h 2850
60.3.42 Opcode Menu0 Configuration (BIOS_OPMENU0)—Offset A8h 2851
60.3.43 Opcode Menu1 Configuration (BIOS_OPMENU1)—Offset ACh 2852
60.3.44 Secondary Flash Region Access Permissions (BIOS_SFRACC)—Offset B0h 2852
60.3.45 Flash Descriptor Observability Control (BIOS_FDOC)—Offset B4h..... 2853
60.3.46 Flash Descriptor Observability Data (BIOS_FDOD)—Offset B8h 2854
60.3.47 Additional Flash Control (BIOS_AFC)—Offset C0h..... 2854
60.3.48 Vendor Specific Component Capabilities for Component 0 (BIOS_SFDP0_VSCC0)—Offset C4h..... 2855
60.3.49 Vendor Specific Component Capabilities for Component 1 (BIOS_SFDP1_VSCC1)—Offset C8h..... 2858
60.3.50 Parameter Table Index (BIOS_PTINX)—Offset CCh 2860
60.3.51 Parameter Table Data (BIOS_PTDATA)—Offset D0h 2861
60.3.52 SPI Bus Requester Status (BIOS_SBRS)—Offset D4h 2862
60.3.53 Flash Region 12 (BIOS_FREG12)—Offset E0h 2863

60.3.54 Flash Region 13 (BIOS_FREG13)—Offset E4h....2863
60.3.55 Flash Region 14 (BIOS_FREG14)—Offset E8h....2864
60.3.56 Flash Region 15 (BIOS_FREG15)—Offset ECh....2864
60.3.57 Set Strap Msg Lock (SSML)—Offset F0h....2865
60.3.58 Set Strap Msg Control (SSMC)—Offset F4h....2865
60.3.59 Set Strap Msg Data (SSMD)—Offset F8h....2866
60.3.60 RPMC SFDP Table (BIOS_RPMC0_D0)—Offset 108h....2866
60.3.61 RPMC SFDP Table (BIOS_RPMC1_D0)—Offset 10Ch....2867
60.3.62 RPMC SFDP Table (BIOS_RPMC0_D1)—Offset 110h....2867
60.3.63 RPMC SFDP Table (BIOS_RPMC1_D1)—Offset 114h....2867
60.3.64 BIOS Master Read Access Permissions (BIOS_BM_RAP)—Offset 118h....2868
60.3.65 BIOS Master Write Access Permissions (BIOS_BM_WAP)—Offset 11Ch....2868
60.3.66 IE Flash Protected Range 0 (BIOS_IE_PR0)—Offset 1B0h....2869
60.3.67 IE Flash Protected Range 1 (BIOS_IE_PR1)—Offset 1B4h....2870
60.3.68 IE Flash Protected Range 2 (BIOS_IE_PR2)—Offset 1B8h....2871
60.3.69 IE Flash Protected Range 3 (BIOS_IE_PR3)—Offset 1BCh....2872
60.3.70 IE Flash Protected Range 4 (BIOS_IE_PR4)—Offset 1C0h....2873

61 Programmable Interval Timer - Legacy....2874
61.1 Introduction and Index....2874
61.1.1 Host I/O Space—Fixed Address....2874
61.2 Registers in I/O Space—Fixed Addresses....2875
61.2.1 Counter 0 - Interval Timer Status Byte Format Register (C0_ITSBFR)—Offset 40h....2876
61.2.2 Counter 2 - Interval Timer Status Byte Format Register (C2_ITSBFR)—Offset 42h....2877
61.2.3 Timer Control Word Register (TCW)—Offset 43h....2878
61.2.4 Counter 2 - Counter Access Ports Register (C2_CAPR)—Offset 42h....2879
61.2.5 Read Back Command (RBC)—Offset 43h....2880
61.2.6 Counter Latch Command (CLC)—Offset 43h....2881
61.2.7 NMI Status and Control (NMI_STS_CNT)—Offset 61h....2882

62 Real Time Clock - Legacy....2883
62.1 Introduction and Index....2883
62.1.1 Host I/O Space—Fixed Address....2884
62.1.2 Host I/O Space—RTC Standard Static RAM Bank (Indexed Data)....2885
62.1.3 Host I/O Space—RTC Extended Static RAM Bank (Indexed Data)....2886
62.1.4 Sideband Registers....2887
62.2 Registers in I/O Space—Fixed Addresses....2888
62.2.1 NMI Enable (and Real Time Clock Index) (NMI_EN)—Port 70h....2888
62.2.2 Real Time Clock Data—Port 71h....2889
62.2.3 Real Time Clock Index to Extended RAM—Port 72h....2889
62.2.4 Real Time Clock Data—Port 73h....2889
62.3 Registers in Host I/O Space—RTC Standard Static RAM Bank (Indexed Data)....2890
62.3.1 Seconds (Sec)—Index 0h....2890
62.3.2 Seconds Alarm (Sec_Alarm)—Index 1h....2890
62.3.3 Minutes—Index 2h....2890
62.3.4 Minutes Alarm (Minutes_Alarm)—Index 3h....2891
62.3.5 Hours—Index 4h....2891
62.3.6 Hours Alarm (Hours_Alarm)—Index 5h....2891
62.3.7 Day of Week (Day_of_Week)—Index 6h....2892
62.3.8 Day of Month (Day_of_Month)—Index 7h....2892
62.3.9 Month—Index 8h....2892
62.3.10 Year—Index 9h....2893
62.3.11 Register A (Register_A)—Index Ah....2894
62.3.12 Register B - General Configuration (Register_B)—Index Bh....2895

62.3.13 Register C - Flag Register (Register_C)—Index Ch 2897
62.3.14 Register D - Flag Register (Register_D)—Index Dh 2898
62.3.15 User RAM—Index Eh through 7Fh 2898
62.4 Registers in Host I/O Space—RTC Extended Static RAM Bank (Indexed Data) 2899
62.4.1 User RAM—Index 0h through 7Fh 2899
62.5 Sideband Registers 2900
62.5.1 RTC Configuration (RC)—Offset 3400h 2900
62.5.2 Backed Up Control (BUC)—Offset 3414h 2901
62.5.3 RTC Update In Progress SMI Control (UIPSMI)—Offset 3F04h 2902
62.5.4 RTC Dynamic Clock Gating Control (RTCDCG)—Offset 3418h 2903

63 High Precision Event Timer - Legacy 2904
63.1 Introduction and Index 2904
63.1.1 Host Memory Space—Fixed Address 2905
63.2 Registers in Memory Space—Fixed Addresses 2906
63.2.1 General Config Register (GEN_CFG)—Offset 10h 2906
63.2.2 General Interrupt Status Register (GEN_INT_STS)—Offset 20h 2907

64 PIC and I/O APIC Controllers 2908
64.1 Introduction and Index 2908
64.1.1 Host Configuration Space 2909
64.1.2 Host Memory Space—Fixed Address 2910
64.1.3 Host I/O Space—Fixed Address 2912
64.2 Registers in Configuration Space 2913
64.2.1 IOxAPIC Configuration (IOAC)—Offset 64h 2913
64.3 Registers in Memory Space—Fixed Addresses 2914
64.3.1 Index Register (IDX)—FEC0_0000h 2914
64.3.2 Window Register (WDW)—FEC0_0010h 2914
64.3.3 IOxAPIC Interrupt Messages for Local APIC—FEE0_0000h 2914
64.4 Registers Accessed through IOxAPIC IDX and WDW 2916
64.4.1 Version (VS)—Offset 1h 2917
64.4.2 Redirection Table Entry 0 (RTE0)—Offset 10h 2918
64.4.3 Redirection Table Entry 1 (RTE1)—Offset 12h 2920
64.4.4 Redirection Table Entry 2 (RTE2)—Offset 14h 2922
64.4.5 Redirection Table Entry 118 (RTE118)—Offset FCh 2924
64.4.6 Redirection Table Entry 119 (RTE119)—Offset FEh 2926
64.5 Registers in I/O Space—Fixed Addresses 2928
64.5.1 Master Initialization Command Word 1 (MICW1)—I/O Port 20h 2928
64.5.2 Master Initialization Command Word 2 (MICW2)—I/O Port 21h 2929
64.5.3 Master Initialization Command Word 3 (MICW3)—I/O Port 21h 2929
64.5.4 Master Initialization Command Word 4 (MICW4)—I/O Port 21h 2930
64.5.5 Master Operational Control Word 1 (MOCW1)—I/O Port 21h 2930
64.5.6 Master Operational Control Word 2 (MOCW2)—I/O Port 20h 2931
64.5.7 Master Operational Control Word 3 (MOCW3)—I/O Port 20h 2932
64.5.8 Slave Initialization Command Word 1 (SICW1)—I/O Port A0h 2933
64.5.9 Slave Initialization Command Word 2 (SICW2)—I/O Port A1h 2934
64.5.10 Slave Initialization Command Word 3 (SICW3)—I/O Port A1h 2934
64.5.11 Slave Initialization Command Word 4 (SICW4)—I/O Port A1h 2935
64.5.12 Slave Operational Control Word 1 (SOCW1)—I/O Port A1h 2935
64.5.13 Slave Operational Control Word 2 (SOCW2)—I/O Port A0h 2936
64.5.14 Slave Operational Control Word 3 (SOCW3)—I/O Port A0h 2937
64.5.15 Master Edge/Level Control (ELCR1)—I/O Port 4D0h 2938
64.5.16 Slave Edge/Level Control (ELCR2)—I/O Port 4D1h 2938

65 Customer General-Purpose I/O Controller 2939

65.1 Introduction and Index 2939
65.1.1 Sideband Registers—Configurable I/O Signals 2940
65.2 Sideband Registers, Part 1 of 2—Sideband Port 0xC2 2953
65.2.1 Pad Base Address (PADBAR)—Offset Ch 2953
65.2.2 Miscellaneous Configuration (MISCCFG)—Offset 10h 2954
65.2.3 Pad Ownership (PAD_OWN_NORTH_ALL_0)—Offset 20h 2955
65.2.4 Pad Ownership (PAD_OWN_NORTH_ALL_1)—Offset 24h 2957
65.2.5 Pad Ownership (PAD_OWN_NORTH_ALL_2)—Offset 28h 2959
65.2.6 Pad Ownership (PAD_OWN_NORTH_ALL_3)—Offset 2Ch 2961
65.2.7 Pad Ownership (PAD_OWN_NORTH_ALL_4)—Offset 30h 2963
65.2.8 Pad Ownership (PAD_OWN_NORTH_ALL_5)—Offset 34h 2965
65.2.9 Pad Configuration Lock (PADCFGLOCK_NORTH_ALL_0)—Offset 90h 2966
65.2.10 Pad Configuration Lock (PADCFGLOCKTX_NORTH_ALL_0)—Offset 94h 2968
65.2.11 Pad Configuration Lock (PADCFGLOCK_NORTH_ALL_1)—Offset 98h 2970
65.2.12 Pad Configuration Lock (PADCFGLOCKTX_NORTH_ALL_1)—Offset 9Ch 2971
65.2.13 Host Software Pad Ownership (HOSTSW_OWN_NORTH_ALL_0)—Offset C0h 2972
65.2.14 Host Software Pad Ownership (HOSTSW_OWN_NORTH_ALL_1)—Offset C4h 2974
65.2.15 GPI Interrupt Status (GPI_IS_NORTH_ALL_0)—Offset 100h 2975
65.2.16 GPI Interrupt Status (GPI_IS_NORTH_ALL_1)—Offset 104h 2977
65.2.17 GPI Interrupt Enable (GPI_IE_NORTH_ALL_0)—Offset 120h 2978
65.2.18 GPI Interrupt Enable (GPI_IE_NORTH_ALL_1)—Offset 124h 2980
65.2.19 Reserved[0-5] (RSVD6[0-5])—Offset 128h, Count 6, Stride 4h 2981
65.2.20 GPI General Purpose Events Status (GPI_GPE_STS_NORTH_ALL_0)—Offset 140h 2981
65.2.21 GPI General Purpose Events Status (GPI_GPE_STS_NORTH_ALL_1)—Offset 144h 2983
65.2.22 GPI General Purpose Events Enable (GPI_GPE_EN_NORTH_ALL_0)—Offset 160h 2984
65.2.23 GPI General Purpose Events Enable (GPI_GPE_EN_NORTH_ALL_1)—Offset 164h 2986
65.2.24 SMI Status (GPI_SMI_STS_NORTH_ALL_0)—Offset 180h 2987
65.2.25 SMI Status (GPI_SMI_STS_NORTH_ALL_1)—Offset 184h 2989
65.2.26 SMI Enable (GPI_SMI_EN_NORTH_ALL_0)—Offset 1A0h 2990
65.2.27 SMI Enable (GPI_SMI_EN_NORTH_ALL_1)—Offset 1A4h 2992
65.2.28 NMI Status (GPI_NMI_STS_NORTH_ALL_0)—Offset 1C0h 2993
65.2.29 NMI Status (GPI_NMI_STS_NORTH_ALL_1)—Offset 1C4h 2995
65.2.30 NMI Enable (GPI_NMI_EN_NORTH_ALL_0)—Offset 1E0h 2996
65.2.31 NMI Enable (GPI_NMI_EN_NORTH_ALL_1)—Offset 1E4h 2998
65.2.32 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP0)—Offset 400h 2999
65.2.33 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP0)—Offset 404h 3002
65.2.34 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP0)—Offset 408h 3003
65.2.35 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP0)—Offset 40Ch 3006
65.2.36 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP1)—Offset 410h 3007
65.2.37 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP1)—Offset 414h 3010
65.2.38 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP1)—Offset 418h 3011
65.2.39 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP1)—Offset 41Ch 3014
65.2.40 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP2)—Offset 420h 3015
65.2.41 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP2)—Offset 424h 3018
65.2.42 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP2)—Offset 428h 3019
65.2.43 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP2)—Offset 42Ch 3022
65.2.44 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP3)—Offset 430h 3023
65.2.45 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP3)—Offset 434h 3026
65.2.46 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP3)—Offset 438h 3027

65.2.47 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP3)—Offset 43Ch 3030
65.2.48 Pad Configuration DW0 (PAD_CFG_DW0_GBE2_LED0)—Offset 440h 3031
65.2.49 Pad Configuration DW1 (PAD_CFG_DW1_GBE2_LED0)—Offset 444h 3034
65.2.50 Pad Configuration DW0 (PAD_CFG_DW0_GBE2_LED1)—Offset 448h 3035
65.2.51 Pad Configuration DW1 (PAD_CFG_DW1_GBE2_LED1)—Offset 44Ch 3038
65.2.52 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_I2C_CLK)—Offset 450h... 3039
65.2.53 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_I2C_CLK)—Offset 454h... 3042
65.2.54 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_I2C_DATA)—Offset 458h 3043
65.2.55 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_I2C_DATA)—Offset 45Ch 3046
65.2.56 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_I2C_CLK)—Offset 460h... 3047
65.2.57 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_I2C_CLK)—Offset 464h... 3050
65.2.58 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_I2C_DATA)—Offset 468h 3051
65.2.59 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_I2C_DATA)—Offset 46Ch 3054
65.2.60 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_RXD0)—Offset 470h 3055
65.2.61 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_RXD0)—Offset 474h 3058
65.2.62 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_CLK_IN)—Offset 478h..... 3059
65.2.63 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_CLK_IN)—Offset 47Ch 3062
65.2.64 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_RXD1)—Offset 480h 3063
65.2.65 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_RXD1)—Offset 484h 3066
65.2.66 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_CRS_DV)—Offset 488h.... 3067
65.2.67 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_CRS_DV)—Offset 48Ch ... 3070
65.2.68 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_ARB_IN)—Offset 490h 3071
65.2.69 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_ARB_IN)—Offset 494h 3074
65.2.70 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TX_EN)—Offset 498h..... 3075
65.2.71 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TX_EN)—Offset 49Ch..... 3078
65.2.72 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TXD0)—Offset 4A0h 3079
65.2.73 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TXD0)—Offset 4A4h 3082
65.2.74 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TXD1)—Offset 4A8h 3083
65.2.75 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TXD1)—Offset 4ACh 3086
65.2.76 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_ARB_OUT)—Offset 4B0h.. 3087
65.2.77 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_ARB_OUT)—Offset 4B4h.. 3090
65.2.78 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_LED0)—Offset 4B8h 3091
65.2.79 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_LED0)—Offset 4BCh 3094
65.2.80 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_LED1)—Offset 4C0h 3095
65.2.81 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_LED1)—Offset 4C4h 3098
65.2.82 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_LED0)—Offset 4C8h 3099
65.2.83 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_LED0)—Offset 4CCh 3102
65.2.84 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_LED1)—Offset 4D0h 3103
65.2.85 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_LED1)—Offset 4D4h 3106
65.2.86 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_0)—Offset 4D8h..... 3107
65.2.87 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_0)—Offset 4DCh..... 3110
65.2.88 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ0_N)—Offset 4E0h 3111
65.2.89 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ0_N)—Offset 4E4h 3114
65.2.90 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ1_N)—Offset 4E8h 3115
65.2.91 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ1_N)—Offset 4ECh 3118
65.2.92 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ2_N)—Offset 4F0h3119
65.2.93 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ2_N)—Offset 4F4h3122
65.2.94 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ3_N)—Offset 4F8h3123
65.2.95 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ3_N)—Offset 4FCh 3126

65.2.96 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ4_N)—Offset 500h 3127
65.2.97 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ4_N)—Offset 504h 3130
65.2.98 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_1)—Offset 508h....3131
65.2.99 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_1)—Offset 50Ch....3134
65.2.100 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_2)—Offset 510h....3135
65.2.101 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_2)—Offset 514h....3138
65.2.102 Pad Configuration DW0 (PAD_CFG_DW0_SVID_ALERT_N)—Offset 518h ...3139
65.2.103 Pad Configuration DW1 (PAD_CFG_DW1_SVID_ALERT_N)—Offset 51Ch ...3142
65.2.104 Pad Configuration DW0 (PAD_CFG_DW0_SVID_DATA)—Offset 520h 3143
65.2.105 Pad Configuration DW1 (PAD_CFG_DW1_SVID_DATA)—Offset 524h 3146
65.2.106 Pad Configuration DW0 (PAD_CFG_DW0_SVID_CLK)—Offset 528h 3147
65.2.107 Pad Configuration DW1 (PAD_CFG_DW1_SVID_CLK)—Offset 52Ch 3150
65.2.108 Pad Configuration DW0 (PAD_CFG_DW0_THERMTRIP_N)—Offset 530h 3151
65.2.109 Pad Configuration DW1 (PAD_CFG_DW1_THERMTRIP_N)—Offset 534h 3154
65.2.110 Pad Configuration DW0 (PAD_CFG_DW0_PROCHOT_N)—Offset 538h 3155
65.2.111 Pad Configuration DW1 (PAD_CFG_DW1_PROCHOT_N)—Offset 53Ch....3158
65.2.112 Pad Configuration DW0 (PAD_CFG_DW0_MEMHOT_N)—Offset 540h 3159
65.2.113 Pad Configuration DW1 (PAD_CFG_DW1_MEMHOT_N)—Offset 544h 3162
65.3 Sideband Registers, Part 2 of 2—Sideband Port 0xC5 3163
65.3.1 Pad Base Address (PADBAR)—Offset 0Ch 3163
65.3.2 Miscellaneous Configuration (MISCCFG)—Offset 10h 3164
65.3.3 Pad Ownership (PAD_OWN_SOUTH_DFX_0)—Offset 20h 3165
65.3.4 Pad Ownership (PAD_OWN_SOUTH_DFX_1)—Offset 24h 3167
65.3.5 Pad Ownership (PAD_OWN_SOUTH_DFX_2)—Offset 28h 3169
65.3.6 Pad Ownership (PAD_OWN_SOUTH_GROUP0_0)—Offset 2Ch....3170
65.3.7 Pad Ownership (PAD_OWN_SOUTH_GROUP0_1)—Offset 30h 3172
65.3.8 Pad Ownership (PAD_OWN_SOUTH_GROUP0_2)—Offset 34h 3174
65.3.9 Pad Ownership (PAD_OWN_SOUTH_GROUP0_3)—Offset 38h 3176
65.3.10 Pad Ownership (PAD_OWN_SOUTH_GROUP0_4)—Offset 3Ch....3178
65.3.11 Pad Ownership (PAD_OWN_SOUTH_GROUP0_5)—Offset 40h 3180
65.3.12 Pad Ownership (PAD_OWN_SOUTH_GROUP0_6)—Offset 44h 3182
65.3.13 Pad Ownership (PAD_OWN_SOUTH_GROUP1_0)—Offset 48h 3183
65.3.14 Pad Ownership (PAD_OWN_SOUTH_GROUP1_1)—Offset 4Ch....3185
65.3.15 Pad Ownership (PAD_OWN_SOUTH_GROUP1_2)—Offset 50h 3187
65.3.16 Pad Ownership (PAD_OWN_SOUTH_GROUP1_3)—Offset 54h 3189
65.3.17 Pad Ownership (PAD_OWN_SOUTH_GROUP1_4)—Offset 58h 3191
65.3.18 Pad Ownership (PAD_OWN_SOUTH_GROUP1_5)—Offset 5Ch....3193
65.3.19 Pad Configuration Lock (PADCFGLOCK_SOUTH_DFX_0)—Offset 90h 3194
65.3.20 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_DFX_0)—Offset 94h....3196
65.3.21 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP0_0)—Offset 98h ..3198
65.3.22 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP0_0)—Offset 9Ch 3200
65.3.23 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP0_1)—Offset A0h ..3202
65.3.24 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP0_1)—Offset A4h....3204
65.3.25 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP1_0)—Offset A8h ..3206
65.3.26 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP1_0)—Offset ACh 3208
65.3.27 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP1_1)—Offset B0h ..3210
65.3.28 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP1_1)—Offset B4h 3211
65.3.29 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_DFX_0)—Offset C0h 3212

65.3.30 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP0_0)—Offset C4h 3214
65.3.31 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP0_1)—Offset C8h 3216
65.3.32 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP1_0)—Offset CCh 3218
65.3.33 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP1_1)—Offset D0h 3220
65.3.34 GPI Interrupt Status (GPI_IS_SOUTH_DFX_0)—Offset 100h..... 3221
65.3.35 GPI Interrupt Status (GPI_IS_SOUTH_GROUP0_0)—Offset 104h..... 3223
65.3.36 GPI Interrupt Status (GPI_IS_SOUTH_GROUP0_1)—Offset 108h..... 3225
65.3.37 GPI Interrupt Status (GPI_IS_SOUTH_GROUP1_0)—Offset 10Ch 3227
65.3.38 GPI Interrupt Status (GPI_IS_SOUTH_GROUP1_1)—Offset 110h..... 3229
65.3.39 GPI Interrupt Enable (GPI_IE_SOUTH_DFX_0)—Offset 120h 3230
65.3.40 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP0_0)—Offset 124h 3232
65.3.41 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP0_1)—Offset 128h 3234
65.3.42 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP1_0)—Offset 12Ch 3236
65.3.43 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP1_1)—Offset 130h 3238
65.3.44 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_DFX_0)—Offset 140h 3239
65.3.45 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP0_0)—Offset 144h 3241
65.3.46 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP0_1)—Offset 148h 3243
65.3.47 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP1_0)—Offset 14Ch 3245
65.3.48 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP1_1)—Offset 150h 3247
65.3.49 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_DFX_0)—Offset 160h..... 3248
65.3.50 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP0_0)—Offset 164h..... 3250
65.3.51 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP0_1)—Offset 168h..... 3252
65.3.52 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP1_0)—Offset 16Ch..... 3254
65.3.53 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP1_1)—Offset 170h..... 3256
65.3.54 SMI Status (GPI_SMI_STS_SOUTH_GROUP0_0)—Offset 184h 3257
65.3.55 SMI Status (GPI_SMI_STS_SOUTH_GROUP0_1)—Offset 188h 3259
65.3.56 SMI Status (GPI_SMI_STS_SOUTH_GROUP1_0)—Offset 18Ch 3261
65.3.57 SMI Status (GPI_SMI_STS_SOUTH_GROUP1_1)—Offset 190h 3263
65.3.58 SMI Enable (GPI_SMI_EN_SOUTH_GROUP0_0)—Offset 1A4h 3264
65.3.59 SMI Enable (GPI_SMI_EN_SOUTH_GROUP0_1)—Offset 1A8h 3266
65.3.60 SMI Enable (GPI_SMI_EN_SOUTH_GROUP1_0)—Offset 1ACh 3268
65.3.61 SMI Enable (GPI_SMI_EN_SOUTH_GROUP1_1)—Offset 1B0h 3270
65.3.62 NMI Status (GPI_NMI_STS_SOUTH_GROUP0_0)—Offset 1C4h..... 3271
65.3.63 NMI Status (GPI_NMI_STS_SOUTH_GROUP0_1)—Offset 1C8h..... 3273
65.3.64 NMI Status (GPI_NMI_STS_SOUTH_GROUP1_0)—Offset 1CCh 3275
65.3.65 NMI Status (GPI_NMI_STS_SOUTH_GROUP1_1)—Offset 1D0h 3277
65.3.66 NMI Enable (GPI_NMI_EN_SOUTH_GROUP0_0)—Offset 1E4h 3278
65.3.67 NMI Enable (GPI_NMI_EN_SOUTH_GROUP0_1)—Offset 1E8h 3280
65.3.68 NMI Enable (GPI_NMI_EN_SOUTH_GROUP1_0)—Offset 1ECh..... 3282
65.3.69 NMI Enable (GPI_NMI_EN_SOUTH_GROUP1_1)—Offset 1F0h 3284
65.3.70 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT_CLK0)—Offset 400h 3285
65.3.71 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT_CLK0)—Offset 404h 3288

65.3.72 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT_CLK1)—Offset 408h.3289
65.3.73 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT_CLK1)—Offset 40Ch.3292
65.3.74 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT0)—Offset 410h.....3293
65.3.75 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT0)—Offset 414h.....3296
65.3.76 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT1)—Offset 418h.....3297
65.3.77 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT1)—Offset 41Ch.....3300
65.3.78 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT2)—Offset 420h.....3301
65.3.79 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT2)—Offset 424h.....3304
65.3.80 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT3)—Offset 428h.....3305
65.3.81 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT3)—Offset 42Ch.....3308
65.3.82 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT4)—Offset 430h.....3309
65.3.83 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT4)—Offset 434h.....3312
65.3.84 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT5)—Offset 438h.....3313
65.3.85 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT5)—Offset 43Ch.....3316
65.3.86 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT6)—Offset 440h.....3317
65.3.87 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT6)—Offset 444h.....3320
65.3.88 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT7)—Offset 448h.....3321
65.3.89 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT7)—Offset 44Ch.....3324
65.3.90 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT8)—Offset 450h.....3325
65.3.91 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT8)—Offset 454h.....3328
65.3.92 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT9)—Offset 458h.....3329
65.3.93 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT9)—Offset 45Ch.....3332
65.3.94 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT10)—Offset 460h 3333
65.3.95 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT10)—Offset 464h 3336
65.3.96 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT11)—Offset 468h 3337
65.3.97 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT11)—Offset 46Ch 3340
65.3.98 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT12)—Offset 470h 3341
65.3.99 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT12)—Offset 474h 3344
65.3.100 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT13)—Offset 478h 3345
65.3.101 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT13)—Offset 47Ch 3348
65.3.102 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT14)—Offset 480h 3349
65.3.103 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT14)—Offset 484h 3352
65.3.104 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT15)—Offset 488h 3353
65.3.105 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT15)—Offset 48Ch 3356
65.3.106 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_12)—Offset 490h 3357
65.3.107 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_12)—Offset 494h 3360
65.3.108 Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_ALRT_N)—Offset 498h.....3361
65.3.109 Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_ALRT_N)—Offset 49Ch.....3364
65.3.110 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ5_N)—Offset 4A0h.....3365
65.3.111 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ5_N)—Offset 4A4h.....3368
65.3.112 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ6_N)—Offset 4A8h.....3369
65.3.113 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ6_N)—Offset 4ACh.....3372
65.3.114 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ7_N)—Offset 4B0h.....3373
65.3.115 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ7_N)—Offset 4B4h.....3376
65.3.116 Pad Configuration DW0 (PAD_CFG_DW0_UART0_RXD)—Offset 4B8h 3377
65.3.117 Pad Configuration DW1 (PAD_CFG_DW1_UART0_RXD)—Offset 4BCh 3380
65.3.118 Pad Configuration DW0 (PAD_CFG_DW0_UART0_TXD)—Offset 4C0h 3381

65.3.119 Pad Configuration DW1 (PAD_CFG_DW1_UART0_TXD)—Offset 4C4h 3384
65.3.120 Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_CLK)—Offset 4C8h . 3385
65.3.121 Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_CLK)—Offset 4CCh . 3388
65.3.122 Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_DATA)—Offset 4D0h 3389
65.3.123 Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_DATA)—Offset 4D4h 3392
65.3.124 Pad Configuration DW0 (PAD_CFG_DW0_ERROR2_N)—Offset 4D8h 3393
65.3.125 Pad Configuration DW1 (PAD_CFG_DW1_ERROR2_N)—Offset 4DCh 3396
65.3.126 Pad Configuration DW0 (PAD_CFG_DW0_ERROR1_N)—Offset 4E0h..... 3397
65.3.127 Pad Configuration DW1 (PAD_CFG_DW1_ERROR1_N)—Offset 4E4h..... 3400
65.3.128 Pad Configuration DW0 (PAD_CFG_DW0_ERROR0_N)—Offset 4E8h..... 3401
65.3.129 Pad Configuration DW1 (PAD_CFG_DW1_ERROR0_N)—Offset 4ECh 3404
65.3.130 Pad Configuration DW0 (PAD_CFG_DW0_IERR_N)—Offset 4F0h 3405
65.3.131 Pad Configuration DW1 (PAD_CFG_DW1_IERR_N)—Offset 4F4h 3408
65.3.132 Pad Configuration DW0 (PAD_CFG_DW0_MCERR_N)—Offset 4F8h 3409
65.3.133 Pad Configuration DW1 (PAD_CFG_DW1_MCERR_N)—Offset 4FCh 3412
65.3.134 Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_CLK)—Offset 500h.. 3413
65.3.135 Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_CLK)—Offset 504h.. 3416
65.3.136 Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_DATA)—Offset 508h 3417
65.3.137 Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_DATA)—Offset 50Ch 3420
65.3.138 Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_ALRT_N)—Offset 510h 3421
65.3.139 Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_ALRT_N)—Offset 514h 3424
65.3.140 Pad Configuration DW0 (PAD_CFG_DW0_SMB1_HOST_DATA)—Offset 518h 3425
65.3.141 Pad Configuration DW1 (PAD_CFG_DW1_SMB1_HOST_DATA)—Offset 51Ch 3428
65.3.142 Pad Configuration DW0 (PAD_CFG_DW0_SMB1_HOST_CLK)—Offset 520h 3429
65.3.143 Pad Configuration DW1 (PAD_CFG_DW1_SMB1_HOST_CLK)—Offset 524h 3432
65.3.144 Pad Configuration DW0 (PAD_CFG_DW0_SMB2_PECI_DATA)—Offset 528h 3433
65.3.145 Pad Configuration DW1 (PAD_CFG_DW1_SMB2_PECI_DATA)—Offset 52Ch 3436
65.3.146 Pad Configuration DW0 (PAD_CFG_DW0_SMB2_PECI_CLK)—Offset 530h. 3437
65.3.147 Pad Configuration DW1 (PAD_CFG_DW1_SMB2_PECI_CLK)—Offset 534h. 3440
65.3.148 Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_DATA)—Offset 538h 3441
65.3.149 Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_DATA)—Offset 53Ch 3444
65.3.150 Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_CLK)—Offset 540h 3445
65.3.151 Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_CLK)—Offset 544h 3448
65.3.152 Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_ALRT_N)—Offset 548h 3449
65.3.153 Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_ALRT_N)—Offset 54Ch 3452
65.3.154 Pad Configuration DW0 (PAD_CFG_DW0_USB_OC0_N)—Offset 550h..... 3453
65.3.155 Pad Configuration DW1 (PAD_CFG_DW1_USB_OC0_N)—Offset 554h..... 3456
65.3.156 Pad Configuration DW0 (PAD_CFG_DW0_FLEX_CLK_SE0)—Offset 558h... 3457
65.3.157 Pad Configuration DW1 (PAD_CFG_DW1_FLEX_CLK_SE0)—Offset 55Ch... 3460
65.3.158 Pad Configuration DW0 (PAD_CFG_DW0_FLEX_CLK_SE1)—Offset 560h... 3461
65.3.159 Pad Configuration DW1 (PAD_CFG_DW1_FLEX_CLK_SE1)—Offset 564h... 3464
65.3.160 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_4)—Offset 568h 3465

65.3.161 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_4)—Offset 56Ch.....3468
65.3.162 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_5)—Offset 570h.....3469
65.3.163 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_5)—Offset 574h.....3472
65.3.164 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_6)—Offset 578h.....3473
65.3.165 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_6)—Offset 57Ch.....3476
65.3.166 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_7)—Offset 580h.....3477
65.3.167 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_7)—Offset 584h.....3480
65.3.168 Pad Configuration DW0 (PAD_CFG_DW0_SATA0_LED_N)—Offset 588h 3481
65.3.169 Pad Configuration DW1 (PAD_CFG_DW1_SATA0_LED_N)—Offset 58Ch 3484
65.3.170 Pad Configuration DW0 (PAD_CFG_DW0_SATA1_LED_N)—Offset 590h 3485
65.3.171 Pad Configuration DW1 (PAD_CFG_DW1_SATA1_LED_N)—Offset 594h 3488
65.3.172 Pad Configuration DW0 (PAD_CFG_DW0_SATA_PDETECT0)—Offset 598h.3489
65.3.173 Pad Configuration DW1 (PAD_CFG_DW1_SATA_PDETECT0)—Offset 59Ch.3492
65.3.174 Pad Configuration DW0 (PAD_CFG_DW0_SATA_PDETECT1)—Offset 5A0h.3493
65.3.175 Pad Configuration DW1 (PAD_CFG_DW1)—Offset 5A4h.....3496
65.3.176 Pad Configuration DW0 (PAD_CFG_DW0_SATA0_SDOUT)—Offset 5A8h ...3497
65.3.177 Pad Configuration DW1 (PAD_CFG_DW1_SATA0_SDOUT)—Offset 5ACh ...3500
65.3.178 Pad Configuration DW0 (PAD_CFG_DW0_SATA1_SDOUT)—Offset 5B0h ...3501
65.3.179 Pad Configuration DW1 (PAD_CFG_DW1_SATA1_SDOUT)—Offset 5B4h ...3504
65.3.180 Pad Configuration DW0 (PAD_CFG_DW0_UART1_RXD)—Offset 5B8h 3505
65.3.181 Pad Configuration DW1 (PAD_CFG_DW1_UART1_RXD)—Offset 5BCh 3508
65.3.182 Pad Configuration DW0 (PAD_CFG_DW0_UART1_TXD)—Offset 5C0h 3509
65.3.183 Pad Configuration DW1 (PAD_CFG_DW1_UART1_TXD)—Offset 5C4h 3512
65.3.184 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_8)—Offset 5C8h.....3513
65.3.185 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_8)—Offset 5CCh 3516
65.3.186 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_9)—Offset 5D0h 3517
65.3.187 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_9)—Offset 5D4h 3520
65.3.188 Pad Configuration DW0 (PAD_CFG_DW0_TCK)—Offset 5D8h 3521
65.3.189 Pad Configuration DW1 (PAD_CFG_DW1_TCK)—Offset 5DCh 3524
65.3.190 Pad Configuration DW0 (PAD_CFG_DW0_TRST_N)—Offset 5E0h 3525
65.3.191 Pad Configuration DW1 (PAD_CFG_DW1_TRST_N)—Offset 5E4h 3528
65.3.192 Pad Configuration DW0 (PAD_CFG_DW0_TMS)—Offset 5E8h 3529
65.3.193 Pad Configuration DW1 (PAD_CFG_DW1_TMS)—Offset 5ECh 3532
65.3.194 Pad Configuration DW0 (PAD_CFG_DW0_TDI)—Offset 5F0h 3533
65.3.195 Pad Configuration DW1 (PAD_CFG_DW1_TDI)—Offset 5F4h 3536
65.3.196 Pad Configuration DW0 (PAD_CFG_DW0_TDO)—Offset 5F8h 3537
65.3.197 Pad Configuration DW1 (PAD_CFG_DW1_TDO)—Offset 5FCh 3540
65.3.198 Pad Configuration DW0 (PAD_CFG_DW0_CX_PRDY_N)—Offset 600h.....3541
65.3.199 Pad Configuration DW1 (PAD_CFG_DW1_CX_PRDY_N)—Offset 604h.....3544
65.3.200 Pad Configuration DW0 (PAD_CFG_DW0_CX_PREQ_N)—Offset 608h 3545
65.3.201 Pad Configuration DW1 (PAD_CFG_DW1_CX_PREQ_N)—Offset 60Ch 3548
65.3.202 Pad Configuration DW0 (PAD_CFG_DW0_CTBTRIGINOUT)—Offset 610h...3549
65.3.203 Pad Configuration DW1 (PAD_CFG_DW1_CTBTRIGINOUT)—Offset 614h...3552
65.3.204 Pad Configuration DW0 (PAD_CFG_DW0_CTBTRIGOUT)—Offset 618h 3553
65.3.205 Pad Configuration DW1 (PAD_CFG_DW1_CTBTRIGOUT)—Offset 61Ch 3556
65.3.206 Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE2)—Offset 620h 3557
65.3.207 Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE2)—Offset 624h 3560
65.3.208 Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE3)—Offset 628h 3561
65.3.209 Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE3)—Offset 62Ch 3564
65.3.210 Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE4)—Offset 630h 3565
65.3.211 Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE4)—Offset 634h 3568
65.3.212 Pad Configuration DW0 (PAD_CFG_DW0_SUSPWRDNACK)—Offset 638h ..3569
65.3.213 Pad Configuration DW1 (PAD_CFG_DW1_SUSPWRDNACK)—Offset 63Ch ..3572
65.3.214 Pad Configuration DW0 (PAD_CFG_DW0_PMU_SUSCLK)—Offset 640h 3573
65.3.215 Pad Configuration DW1 (PAD_CFG_DW1_PMU_SUSCLK)—Offset 644h 3576

65.3.216 Pad Configuration DW0 (PAD_CFG_DW0_ADR_TRIGGER)—Offset 648h ... 3577
65.3.217 Pad Configuration DW1 (PAD_CFG_DW1_ADR_TRIGGER)—Offset 64Ch ... 3580
65.3.218 Pad Configuration DW0 (PAD_CFG_DW0_PMU_SLP_S45_N)—Offset 650h 3581
65.3.219 Pad Configuration DW1 (PAD_CFG_DW1_PMU_SLP_S45_N)—Offset 654h 3584
65.3.220 Pad Configuration DW0 (PAD_CFG_DW0_PMU_SLP_S3_N)—Offset 658h.. 3585
65.3.221 Pad Configuration DW1 (PAD_CFG_DW1_PMU_SLP_S3_N)—Offset 65Ch.. 3588
65.3.222 Pad Configuration DW0 (PAD_CFG_DW0_PMU_WAKE_N)—Offset 660h.... 3589
65.3.223 Pad Configuration DW1 (PAD_CFG_DW1_PMU_WAKE_N)—Offset 664h.... 3592
65.3.224 Pad Configuration DW0 (PAD_CFG_DW0_PMU_PWRBTN_N)—Offset 668h 3593
65.3.225 Pad Configuration DW1 (PAD_CFG_DW1_PMU_PWRBTN_N)—Offset 66Ch 3596
65.3.226 Pad Configuration DW0 (PAD_CFG_DW0_PMU_RESETBUTTON_N)—Offset 670h 3597
65.3.227 Pad Configuration DW1 (PAD_CFG_DW1_PMU_RESETBUTTON_N)—Offset 674h 3600
65.3.228 Pad Configuration DW0 (PAD_CFG_DW0_PMU_PLTRST_N)—Offset 678h.. 3601
65.3.229 Pad Configuration DW1 (PAD_CFG_DW1_PMU_PLTRST_N)—Offset 67Ch.. 3604
65.3.230 Pad Configuration DW0 (PAD_CFG_DW0_SUS_STAT_N)—Offset 680h 3605
65.3.231 Pad Configuration DW1 (PAD_CFG_DW1_SUS_STAT_N)—Offset 684h 3608
65.3.232 Pad Configuration DW0 (PAD_CFG_DW0_SLP_S0IX_N)—Offset 688h 3609
65.3.233 Pad Configuration DW1 (PAD_CFG_DW1_SLP_S0IX_N)—Offset 68Ch 3612
65.3.234 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CS0_N)—Offset 690h 3613
65.3.235 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CS0_N)—Offset 694h 3616
65.3.236 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CS1_N)—Offset 698h 3617
65.3.237 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CS1_N)—Offset 69Ch..... 3620
65.3.238 Pad Configuration DW0 (PAD_CFG_DW0_SPI_MOSI_IO0)—Offset 6A0h... 3621
65.3.239 Pad Configuration DW1 (PAD_CFG_DW1_SPI_MOSI_IO0)—Offset 6A4h... 3624
65.3.240 Pad Configuration DW0 (PAD_CFG_DW0_SPI_MISO_IO1)—Offset 6A8h... 3625
65.3.241 Pad Configuration DW1 (PAD_CFG_DW1_SPI_MISO_IO1)—Offset 6ACh... 3628
65.3.242 Pad Configuration DW0 (PAD_CFG_DW0_SPI_IO2)—Offset 6B0h 3629
65.3.243 Pad Configuration DW1 (PAD_CFG_DW1_SPI_IO2)—Offset 6B4h 3632
65.3.244 Pad Configuration DW0 (PAD_CFG_DW0_SPI_IO3)—Offset 6B8h 3633
65.3.245 Pad Configuration DW1 (PAD_CFG_DW1_SPI_IO3)—Offset 6BCh 3636
65.3.246 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CLK)—Offset 6C0h..... 3637
65.3.247 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CLK)—Offset 6C4h..... 3640
65.3.248 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CLK_LOOPBK)—Offset 6C8h 3641
65.3.249 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CLK_LOOPBK)—Offset 6CCh 3644
65.3.250 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO0)—Offset 6D0h 3645
65.3.251 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO0)—Offset 6D4h 3648
65.3.252 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO1)—Offset 6D8h 3649
65.3.253 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO1)—Offset 6DCh 3652
65.3.254 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO2)—Offset 6E0h 3653
65.3.255 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO2)—Offset 6E4h 3656
65.3.256 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO3)—Offset 6E8h 3657
65.3.257 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO3)—Offset 6ECh 3660
65.3.258 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CS0_N)—Offset 6F0h 3661
65.3.259 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CS0_N)—Offset 6F4h 3664
65.3.260 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CLK)—Offset 6F8h 3665
65.3.261 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CLK)—Offset 6FCh 3668
65.3.262 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_RST_N)—Offset 700h 3669
65.3.263 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_RST_N)—Offset 704h 3672
65.3.264 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_ALRT0_N)—Offset 708h... 3673
65.3.265 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_ALRT0_N)—Offset 70Ch... 3676
65.3.266 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_10)—Offset 710h 3677

65.3.267 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_10)—Offset 714h 3680
65.3.268 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_11)—Offset 718h 3681
65.3.269 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_11)—Offset 71Ch 3684
65.3.270 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CLK_LOOPBK)—Offset 720h 3685
65.3.271 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CLK_LOOPBK)—Offset 724h 3688
65.3.272 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_CMD)—Offset 728h 3689
65.3.273 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_CMD)—Offset 72Ch 3692
65.3.274 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_STROBE)—Offset 730h ...3693
65.3.275 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_STROBE)—Offset 734h ...3696
65.3.276 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_CLK)—Offset 738h 3697
65.3.277 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_CLK)—Offset 73Ch 3700
65.3.278 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D0)—Offset 740h 3701
65.3.279 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D0)—Offset 744h 3704
65.3.280 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D1)—Offset 748h 3705
65.3.281 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D1)—Offset 74Ch 3708
65.3.282 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D2)—Offset 750h 3709
65.3.283 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D2)—Offset 754h 3712
65.3.284 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D3)—Offset 758h 3713
65.3.285 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D3)—Offset 75Ch 3716
65.3.286 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D4)—Offset 760h 3717
65.3.287 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D4)—Offset 764h 3720
65.3.288 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D5)—Offset 768h 3721
65.3.289 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D5)—Offset 76Ch 3724
65.3.290 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D6)—Offset 770h 3725
65.3.291 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D6)—Offset 774h 3728
65.3.292 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D7)—Offset 778h 3729
65.3.293 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D7)—Offset 77Ch 3732
65.3.294 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_3)—Offset 780h.....3733
65.3.295 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_3)—Offset 784h.....3736

66 SMBus - PECI 3737
66.1 Introduction and Index 3737

67 Interrupt Steering and Control..... 3738
67.1 Introduction and Index 3738
67.1.1 Sideband Registers 3739
67.2 Sideband Registers.....3741
67.2.1 PIRQA Routing Control (PARC)—Offset 3100h 3741
67.2.2 PIRQB Routing Control (PBRC)—Offset 3101h 3742
67.2.3 PIRQC Routing Control (PCRC)—Offset 3102h 3743
67.2.4 PIRQD Routing Control (PDRC)—Offset 3103h.....3744
67.2.5 PIRQE Routing Control (PERC)—Offset 3104h 3745
67.2.6 PIRQF Routing Control (PFRC)—Offset 3105h.....3746
67.2.7 PIRQG Routing Control (PGRC)—Offset 3106h.....3747
67.2.8 PIRQH Routing Control (PHRC)—Offset 3107h.....3748
67.2.9 Message Decoder Control (MSGDC)—Offset 3120h 3749
67.2.10 PCI Interrupt Route 0 (PIR0)—Offset 3140h 3750
67.2.11 PCI Interrupt Route 1 (PIR1)—Offset 3142h 3751
67.2.12 PCI Interrupt Route 2 (PIR2)—Offset 3144h 3752
67.2.13 PCI Interrupt Route 3 (PIR3)—Offset 3146h 3753
67.2.14 PCI Interrupt Route 4 (PIR4)—Offset 3148h 3754
67.2.15 PCI Interrupt Route 5 (PIR5)—Offset 314Ah 3755
67.2.16 PCI Interrupt Route 6 (PIR6)—Offset 314Ch 3756
67.2.17 PCI Interrupt Route 7 (PIR7)—Offset 314Eh 3757

67.2.18 PCI Interrupt Route 8 (PIR8)—Offset 3150h 3758
67.2.19 PCI Interrupt Route 9 (PIR9)—Offset 3152h 3759
67.2.20 PCI Interrupt Route 10 (PIR10)—Offset 3154h 3760
67.2.21 PCI Interrupt Route 11 (PIR11)—Offset 3156h 3761
67.2.22 PCI Interrupt Route 12 (PIR12)—Offset 3158h 3762
67.2.23 General Interrupt Control (GIC)—Offset 31FCh 3763
67.2.24 Interrupt Polarity Control 0 (IPC0)—Offset 3200h 3765
67.2.25 Interrupt Polarity Control 1 (IPC1)—Offset 3204h 3765
67.2.26 Interrupt Polarity Control 2 (IPC2)—Offset 3208h 3765
67.2.27 Interrupt Polarity Control 3 (IPC3)—Offset 320Ch 3766
67.2.28 Interrupt Blocking Control (IBC)—Offset 3220h 3766
67.2.29 Interrupt Edge-Trigger Extension 0 (IETE0)—Offset 3230h 3766
67.2.30 Interrupt Edge-Trigger Extension 1 (IETE1)—Offset 3234h 3767
67.2.31 Interrupt Edge-Trigger Extension 2 (IETE2)—Offset 3238h 3767
67.2.32 Interrupt Edge-Trigger Extension 3 (IETE3)—Offset 323Ch 3767
67.2.33 ITSS Power Reduction Control (ITSSPRC)—Offset 3300h 3768
67.2.34 SIDE Clock Timing (SIDECT)—Offset 3304h 3769
67.2.35 IPCI Clock Timing (IPCICT)—Offset 3306h 3770
67.2.36 PGCB Clock Timing (PGCBCT)—Offset 3308h 3770
67.2.37 Uncorrectable Error Mask (UEM)—Offset 3320h 3771
67.2.38 Uncorrectable Error Severity (UEV)—Offset 3324h 3772
67.2.39 Correctable Error Mask (CEM)—Offset 3328h 3773
67.2.40 NMI Control (NMI)—Offset 3330h 3774
67.2.41 Master Message Control (MMC)—Offset 3334h 3775
67.2.42 Master Message Status (MMSTS)—Offset 3336h 3775
67.2.43 HPET Offload Scale Value (HOFFVAL)—Offset 3400h 3776

68 PHY - High-Speed I/O 3777
68.1 Introduction and Index 3777
68.1.1 Sideband Registers 3778
68.2 Sideband Registers 3788
68.2.1 PCS_DWORD10 (pcs_dword10)—Offset 28h 3788
68.2.2 TX_DWORD5 (tx_dword5)—Offset 94h 3789
68.2.3 TX_DWORD6 (tx_dword6)—Offset 98h 3790
68.2.4 TX_DWORD7 (tx_dword7)—Offset 9Ch 3791
68.2.5 TX_DWORD19 (tx_dword19)—Offset CCh 3792
68.2.6 RX_DWORD20 (rx_dword20)—Offset 150h 3792
68.2.7 RX_DWORD21 (rx_dword21)—Offset 154h 3793
68.2.8 RX_DWORD25 (rx_dword25)—Offset 164h 3794
68.2.9 RX_DWORD26 (rx_dword26)—Offset 168h 3794

69 Model-Specific Registers (MSR) 3795
69.1 Introduction and Index 3795
69.2 Model Specific Registers (MSRs) 3801
69.2.1 (006h) IA32_MONITOR_FILTER_SIZE 3801
69.2.2 (017h) IA32_PLATFORM_ID 3802
69.2.3 (01Bh) IA32_APIC_BASE 3802
69.2.4 (02Eh) MSR_PIC_MSG_CONTROL 3803
69.2.5 (033h) MSR_MEMORY_CONTROL 3803
69.2.6 (034h) MSR_SMI_COUNT 3803
69.2.7 (035h) CORE_THREAD_COUNT 3804
69.2.8 (039h) MSR_THREAD_ID 3804
69.2.9 (03Bh) IA32_TSC_ADJUST 3804
69.2.10 (04Eh) MSR_PPIN_CTL 3805
69.2.11 (04Fh) MSR_PPIN 3805
69.2.12 (052h) SMM_MCA_CONTROL 3805

69.2.13 (079h) IA32_BIOS_UPDT_TRIG 3806
69.2.14 (07Ah) MSR_SGX_FEATURE_ACTIVATION 3806
69.2.15 (08Bh) IA32_BIOS_SIGN_ID 3806
69.2.16 (09Bh) IA32_SMM_MONITOR_CTL 3806
69.2.17 (09Eh) IA32_SMBASE....3807
69.2.18 (0C1h) IA32_PMC0 3807
69.2.19 (0C2h) IA32_PMC1 3807
69.2.20 (0C3h) IA32_PMC2 3807
69.2.21 (0C4h) IA32_PMC3 3807
69.2.22 (0CEh) MSR_PLATFORM_INFO 3808
69.2.23 (0E2h) MSR_PKG_CST_CONFIG_CONTROL....3810
69.2.24 (0E4h) MSR_PMG_IO_CAPTURE_BASE....3811
69.2.25 (0E7h) IA32_MPERF 3811
69.2.26 (0E8h) IA32_APERF 3811
69.2.27 (0FEh) IA32_MTRRCAP 3812
69.2.28 (120h) POWER_MISC 3812
69.2.29 (121h) EMULATE_PM_TMR 3813
69.2.30 (139h) INITIAL_BOOT_BLOCK_COMPLETE....3813
69.2.31 (13Ch) FEATURE_CONFIG 3813
69.2.32 (140h) FEATURE_ENABLES 3814
69.2.33 (15Ch) PERMEM_CONFIG_INFO 3814
69.2.34 (15Dh) PERMEM_CTRLR_INDEX 3814
69.2.35 (15Eh) PERMEM_CTRLR_ID 3814
69.2.36 (174h) IA32_SYSENTER_CS 3815
69.2.37 (175h) IA32_SYSENTER_ESP....3815
69.2.38 (176h) IA32_SYSENTER_EIP 3815
69.2.39 (179h) IA32_MCG_CAP....3816
69.2.40 (17Ah) IA32_MCG_STATUS 3816
69.2.41 (17Dh) MSR_SMM_MCA_CAP....3817
69.2.42 (17Fh) MSR_ERROR_CONTROL 3817
69.2.43 (186h) IA32_PERFEVTSEL0 3818
69.2.44 (187h) IA32_PERFEVTSEL1 3818
69.2.45 (188h) IA32_PERFEVTSEL2 3818
69.2.46 (189h) IA32_PERFEVTSEL3 3819
69.2.47 (198h) IA32_PERF_STATUS 3819
69.2.48 (199h) IA32_PERF_CTL 3819
69.2.49 (19Ah) IA32_CLOCK_MODULATION....3820
69.2.50 (19Bh) IA32_THERM_INTERRUPT....3820
69.2.51 (19Ch) IA32_THERM_STATUS 3821
69.2.52 (19Dh) MSR_THERM2_CTL....3822
69.2.53 (1A0h) IA32_MISC_ENABLE 3823
69.2.54 (1A1h) PACKAGE_THERM_MARGINBD....3824
69.2.55 (1A2h) MSR_TEMPERATURE_TARGET 3824
69.2.56 (1A4h) MSR_MISC_FEATURE_CONTROL....3824
69.2.57 (1A6h) MSR_OFFCORE_RSP_0....3825
69.2.58 (1A7h) MSR_OFFCORE_RSP_1....3825
69.2.59 (1A8h) THREAD_SW_DEFEATURE 3825
69.2.60 (1AAh) MSR_MISC_PWR_MGMT....3825
69.2.61 (1ADh) MSR_TURBO_RATIO_LIMIT 3826
69.2.62 (1AEh) MSR_TURBO_RATIO_LIMIT1 3826
69.2.63 (1B0h) IA32_ENERGY_PERF_BIAS....3826
69.2.64 (1B1h) IA32_PACKAGE_THERM_STATUS....3827
69.2.65 (1B2h) IA32_PACKAGE_THERM_INTERRUPT 3828
69.2.66 (1C6h) DEBUG_RESOURCE_STATUS....3828
69.2.67 (1C8h) MSR_LBR_SELECT 3829

69.2.68 (1C9h) MSR_LASTBRANCH_TOS 3829
69.2.69 (1D9h) IA32_DEBUGCTL 3830
69.2.70 (1E3h) DEBUG_ERR_INJ_CTL 3830
69.2.71 (1E4h) DEBUG_ERR_INJ_CTL2 3831
69.2.72 (1E6h) PIC_DEBUG_MODES 3832
69.2.73 (1F0h) VLW_CAPABILITY 3834
69.2.74 (1FCh) MSR_POWER_CTL 3835
69.2.75 (281h) IA32_MC1_CTL2 (L2 Cache) 3836
69.2.76 (282h) IA32_MC2_CTL2 (FEC) 3836
69.2.77 (283h) IA32_MC3_CTL2 (MEC) 3836
69.2.78 (284h) IA32_MC4_CTL2 (SA) 3836
69.2.79 (285h) IA32_MC5_CTL2 (PMU) 3837
69.2.80 (286h) IA32_MC6_CTL2 (SA) 3837
69.2.81 (287h) IA32_MC7_CTL2 (MEM 0) 3837
69.2.82 (288h) IA32_MC8_CTL2 (MEM 1) 3838
69.2.83 (2E0h) NO_EVICT_MODE 3838
69.2.84 (2FFh) IA32_MTRR_DEF_TYPE 3838
69.2.85 (300h) MSR_SGXOWNER0 3839
69.2.86 (301h) MSR_SGXOWNER1 3839
69.2.87 (309h) IA32_FIXED_CTR0 3839
69.2.88 (30Ah) IA32_FIXED_CTR1 3839
69.2.89 (30Bh) IA32_FIXED_CTR2 3839
69.2.90 (345h) IA32_PERF_CAPABILITIES 3840
69.2.91 (38Dh) IA32_FIXED_CTR_CTRL 3840
69.2.92 (38Eh) IA32_PERF_GLOBAL_STATUS 3841
69.2.93 (38Fh) IA32_PERF_GLOBAL_CTRL 3842
69.2.94 (390h) IA32_PERF_GLOBAL_STATUS_RESET 3843
69.2.95 (391h) IA32_PERF_GLOBAL_STATUS_SET 3844
69.2.96 (392h) IA32_PERF_GLOBAL_INUSE 3844
69.2.97 (3F1h) IA32_PEBS_ENABLE 3845
69.2.98 (3F8h) MSR_PKG_C3_RESIDENCY 3845
69.2.99 (3F9h) MSR_PKG_C6_RESIDENCY 3845
69.2.100 (3FCh) MSR_CORE_C3_RESIDENCY 3845
69.2.101 (3FDh) MSR_CORE_C6_RESIDENCY 3846
69.2.102 (3FEh) MSR_CORE_C7_RESIDENCY 3846
69.2.103 (400h) IA32_MC0_CTL (BIU) 3846
69.2.104 (401h) IA32_MC0_STATUS 3847
69.2.105 (402h) IA32_MC0_ADDR (BIU) 3848
69.2.106 (404h) IA32_MC1_CTL (L2 Cache) 3848
69.2.107 (405h) IA32_MC1_STATUS (L2 Cache) 3849
69.2.108 (406h) IA32_MC1_ADDR (L2 Cache) 3851
69.2.109 (408h) IA32_MC2_CTL (FEC) 3851
69.2.110 (409h) IA32_MC2_STATUS (FEC) 3852
69.2.111 (40Ah) IA32_MC2_ADDR (FEC) 3854
69.2.112 (40Ch) IA32_MC3_CTL (MEC) 3854
69.2.113 (40Dh) IA32_MC3_STATUS (MEC) 3855
69.2.114 (40Eh) IA32_MC3_ADDR (MEC) 3855
69.2.115 (410h) IA32_MC4_CTL (SA) 3856
69.2.116 (411h) IA32_MC4_STATUS (SA) 3858
69.2.117 (412h) IA32_MC4_ADDR (SA) 3860
69.2.118 (413h) IA32_MC4_MISC (SA) 3860
69.2.119 (414h) IA32_MC5_CTL (PMU) 3861
69.2.120 (415h) IA32_MC5_STATUS (PMU) 3863
69.2.121 (416h) IA32_MC5_ADDR (PMU) 3864
69.2.122 (417h) IA32_MC5_MISC (PMU) 3864

69.2.123 (418h) IA32_MC6_CTL (SA) 3865
69.2.124 (419h) IA32_MC6_STATUS (SA) 3867
69.2.125 (41Ah) IA32_MC6_ADDR (SA) 3867
69.2.126 (41Ch) IA32_MC7_CTL (MEM 0)....3868
69.2.127 (41Dh) IA32_MC7_STATUS (MEM 0) 3870
69.2.128 (41Fh) IA32_MC7_MISC (MEM 0)....3871
69.2.129 (420h) IA32_MC8_CTL (MEM 1)....3872
69.2.130 (421h) IA32_MC8_STATUS (MEM 1)....3874
69.2.131 (423h) IA32_MC8_MISC (MEM 1)....3874
69.2.132 (4C1h) IA32_A_PMC0....3874
69.2.133 (4C2h) IA32_A_PMC1....3875
69.2.134 (4C3h) IA32_A_PMC2....3875
69.2.135 (4C4h) IA32_A_PMC3....3875
69.2.136 (4E0h) MSR_SMM_FEATURE_CONTROL....3875
69.2.137 (4E2h) MSR_SMM_DELAYED....3876
69.2.138 (4E3h) MSR_SMM_BLOCKED 3876
69.2.139 (500h) IA32_SGX_SVN_STATUS 3876
69.2.140 (503h) MSR_SGX_DEBUG_MODE 3877
69.2.141 (560h) IA32_RTIT_OUTPUT_BASE....3877
69.2.142 (561h) IA32_RTIT_OUTPUT_MASK_PTRS 3877
69.2.143 (570h) IA32_RTIT_CTL....3878
69.2.144 (571h) ARR_CR_RTIT_STATUSIA32_RTIT_STATUS....3878
69.2.145 (572h) IA32_RTIT_CR3_MATCH....3878
69.2.146 (580h) IA32_RTIT_ADDR0_A....3878
69.2.147 (581h) IA32_RTIT_ADDR0_B....3879
69.2.148 (582h) IA32_RTIT_ADDR1_A....3879
69.2.149 (583h) IA32_RTIT_ADDR1_B....3879
69.2.150 (600h) IA32_DS_AREA 3879
69.2.151 (601h) MSR_VR_CURRENT_CONFIG 3880
69.2.152 (603h) MSR_VR_MISC_CONFIG 3880
69.2.153 (606h) MSR_RAPL_POWER_UNIT 3881
69.2.154 (610h) MSR_PKG_POWER_LIMIT 3882
69.2.155 (614h) MSR_PKG_POWER_INFO 3884
69.2.156 (615h) PPL3_CONTROL....3884
69.2.157 (618h) MSR_DRAM_POWER_LIMIT....3885
69.2.158 (61Ch) MSR_DRAM_POWER_INFO....3886
69.2.159 (633h) MSR_PKGC_IRTL3 3887
69.2.160 (634h) MSR_PKGC_IRTL4 3887
69.2.161 (635h) MSR_PKGC_IRTL5 3888
69.2.162 (639h) MSR_PP0_ENERGY_STATUS....3888
69.2.163 (641h) MSR_PP1_ENERGY_STATUS....3889
69.2.164 (64Ch) MSR_TURBO_ACTIVATION_RATIO 3889
69.2.165 (64Fh) MSR_CORE_PERF_LIMIT_REASONS....3890
69.2.166 (80Fh) IA32_X2APIC_SIVR....3891
69.2.167 (828h) IA32_X2APIC_ESR....3891
69.2.168 (82Fh) IA32_X2APIC_LVT_CMCI 3892
69.2.169 (830h) IA32_X2APIC_ICR 3893
69.2.170 (832h) IA32_X2APIC_LVT_TIMER....3894
69.2.171 (833h) IA32_X2APIC_LVT_THERMAL 3895
69.2.172 (834h) IA32_X2APIC_LVT_PMI 3895
69.2.173 (835h) IA32_X2APIC_LVT_LINT0 3896
69.2.174 (836h) IA32_X2APIC_LVT_LINT1 3897
69.2.175 (837h) IA32_X2APIC_LVT_ERROR....3897
69.2.176 (838h) IA32_X2APIC_INIT_COUNT....3898
69.2.177 (839h) IA32_X2APIC_CUR_COUNT....3898

69.2.178 (83Eh) IA32_X2APIC_DIV_CONF 3898
69.2.179 (83Fh) IA32_X2APIC_SELF_IPI 3898
69.2.180 (C80h) IA32_DEBUG_FEATURE 3899
69.2.181 (C8Fh) IA32_PQR_ASSOC 3899
69.2.182 (D10h) IA32_L2_QOS_MASK_0 3899
69.2.183 (D11h) IA32_L2_QOS_MASK_1 3900
69.2.184 (D12h) IA32_L2_QOS_MASK_2 3900
69.2.185 (D13h) IA32_L2_QOS_MASK_3 3900
69.2.186 (D90h) IA32_BNDCFGS 3901
69.2.187 (DA0h) IA32_XSS 3901
69.2.188 (C0000080h) IA32_EFER 3901
69.2.189 (C0000081h) IA32_STAR 3902
69.2.190 (C0000082h) IA32_LSTAR 3902
69.2.191 (C0000083h) IA32_CSTAR 3902
69.2.192 (C0000084h) IA32_FMASK 3902
69.2.193 (C0000100h) IA32_FS_BASE 3903
69.2.194 (C0000101h) IA32_GS_BASE 3903
69.2.195 (C0000102h) IA32_KERNEL_GS_BASE 3903
69.2.196 (C0000103h) IA32_TSC_AUX 3903

Figures

1-1 High-Level Block Diagram 113
2-1 What is Covered in This Chapter 131
2-2 Version Information Returned by CPUID in EAX 139
3-1 Host Root Space - PCI Device Map 182
3-2 DWORD Format of CONFIG_ADDRESS at I/O Address CF8h 185
4-1 Strap Loading Flow 192
4-2 Hard Strap Functionality 194
4-3 IE Fuses 260
5-1 What is Covered in This Chapter 261
5-2 Register Map 263
6-1 SoC Machine Check MSRs — Global Control and Bank Registers 271
6-2 SoC Core, Module, and Package Machine Check Registers 273
6-3 Intel Atom® Processor C3000 Product Family Error Reporting 278
6-4 Error Handling Architecture 281
6-5 MCERR and IERR Handling 283
6-6 Local and Global Error Register Structure 284
6-7 Global Error Registers and System Event Reporting 290
6-8 PCIe Error Signaling and Logging 294
6-9 Error Signaling and Logging for PCIe Root Complex Integrated Endpoints 297
6-10 Error Signaling and Logging for Non-PCI Devices 305
6-11 Register Map 320
7-1 What is Covered in This Chapter 325
7-2 SoC Clock Architecture 329
8-1 PIRQ Routing Control Overview 336
8-2 General Purpose Event (GPE) Register Model 340
9-1 What is Covered in This Chapter 347
10-1 What is Covered in This Chapter 359
10-2 FIA and HSIO Structure 362
10-3 Intel® ME-BIOS/UEFI Interactions in a System with Intel® SPS Firmware 364
10-4 PCIe x1 Lane and SATA Example 366
10-5 Register Map 367
11-1 What is Covered in This Chapter 369
11-2 PCIe Bifurcation and Physical Ports 380
11-3 Register Map 395
12-1 What is Covered in This Chapter 396
12-2 Register Map 401
13-1 What is Covered in This Chapter 410
13-2 System Architecture and Interface 421
13-3 Error Reporting Mechanism 439
13-4 Shared SPI Flash Shadow RAM 447
13-5 10GBASE-T Implementation 465
13-6 10G Backplane Implementation Using KR to Backplane (Switch) 465
13-7 SFP+ Implementation 466
13-8 1G BASE-T Implementation 467
13-9 Basic PHY/MAC Connectivity 468
13-10 MDIO Timing Source by the MAC 469
13-11 MDIO Timing Sourced by the PHY 469
13-12 Behavior of MDIO During TA Field of a Read Transaction 472
13-13 802.3X Link Flow Control (PAUSE) 481
13-14 Register Map 492
14-1 What is Covered in This Chapter 493
14-2 USB 3.0 Cable 496
14-3 Universal Serial Bus, Revision 3.0 System Block Diagram 498

14-4 USB 3.0 eXtensible Host Controller 500
14-5 General Architecture of the eXtensible Host Controller Interface 501
14-6 Register Map 508
15-1 What is Covered in This Chapter 522
16-1 What is Covered in This Chapter 525
16-2 Register Map 553
17-1 What is Covered in This Chapter 557
17-2 Register Map 560
18-1 What is Covered in This Chapter 565
18-2 UART MUXed Signals 567
18-3 UART Core Block Diagram Overview 569
18-4 UART Data Transfer Flow 572
18-5 7-bit Character Encoding 572
18-6 DMA Block Diagram 578
18-7 Logical Representation of Channel Arbitration 579
18-8 Logical Representation of Descriptor Arbitration 580
18-9 Register Map 587
19-1 What is Covered in This Chapter 592
19-2 Connection to the SPI Devices 594
19-3 Flash Regions 599
19-4 Organize Flash Region Single Flash vs. Dual-Flash Components 599
19-5 Flash Descriptor Sections 600
19-6 Dual-Output-Fast-Read Timing 613
19-7 Dual-I/O-Fast-Read Timing 614
19-8 Quad Output Fast Read Timing 615
19-9 Quad-I/O-Fast-Read Timing 616
19-10 Register Map 622
20-1 What is Covered in This Chapter 626
20-2 LPC_CLKRUN_N Timings 630
20-3 Register Map 631
21-1 What is Covered in This Chapter 638
21-2 Master and Slave PIC 639
21-3 MSI-Like IOxAPIC Interrupt Message for the Local APICs 647
21-4 Register Map 650
22-1 What is Covered in This Chapter 654
22-2 Register Map 656
23-1 What is Covered in This Chapter 659
23-2 Programmable Interval Timer (PIT) Implementation 660
23-3 Register Map 665
24-1 What is Covered in This Chapter 667
24-2 Register Map 673
25-1 What is Covered in This Chapter 675
25-2 HPET Counter and Timers 676
25-3 Register Map 682
26-1 What is Covered in This Chapter 685
26-2 Custom GPIO Circuit Definition 691
26-3 GPIO Logic Overview Diagram 695
27-1 Arrangement of SMBus in SoC 708
28-1 What is Covered in This Chapter 711
28-2 Register Map 725
29-1 What is Covered in This Chapter 729
29-2 ARP-Capable (Slave) Device Behavior Flow Diagram 736
29-3 ARP Master Behavior Flow Diagram 743
29-4 Master Descriptor Ring Buffer 750
29-5 Master Descriptor Format 750

29-6 Hardware-Firmware Flow Diagram—DMA Mode 760
29-7 Target Ring Buffer 766
29-8 Target Header Format 766
29-9 High-Level Target Flow 775
29-10 Host Notify Target Flow 777
29-11 SMBus ARP Target Flow 778
29-12 General Purpose Block Read with PEC Target Flow 780
29-13 SMBus/I^2C Target Flow 782
29-14 Target Dynamic Policy Update 784
29-15 MCTP Over SMBus Packet Format 792
29-16 Register Map 794
30-1 What is Covered in This Chapter 795
30-2 SMBus Protocol 797
30-3 SMBus Block Write Command 798
30-4 SMBus Block Read Command 798
30-5 PECI Message Header in the SMBus Packet 799
30-6 PECI Write-Read Protocol 800
30-7 PECI Device Info Field Definition 811
30-8 PCI Configuration Address Format 821
30-9 Channel Index and DIMM Index Parameter Word 835
30-10 Write DRAM Rank Temperature Data Dword 836
30-11 Read DIMM Temperature Data Dword 836
30-12 Read DRAM Channel Temperature Data Dword 837
30-13 Read DRAM Accumulated Energy Data Dword 837
30-14 Read DRAM Power Info Data Dword 838
30-15 DRAM Power Limit Data 839
30-16 DRAM Power Limit Performance Data 840
30-17 CPU ID Data 848
30-18 Platform ID Data 848
30-19 PCU Device ID Data 849
30-20 Maximum Thread ID Data 849
30-21 Processor Microcode Revision 849
30-22 Package Power SKU Unit Data 850
30-23 Package Power SKU Data 851
30-24 Package Temperature Read Data 852
30-25 Temperature Target Read 853
30-26 Package Thermal Status Read/Clear 853
30-27 Current Limit Read Data 854
30-28 Accumulated Energy Read Data 854
30-29 Package Turbo Power Limit Data 855
30-30 Package Power Limit Performance Data 856
30-31 Efficient Performance Indicator Data 856
30-32 ACPI P-T Notify Data 857
30-33 PL2 and PL3 858
30-34 PL3 Register Definition 858
30-35 Read Ratio Constraints Parameter 859
30-36 Read Ratio Constraints Return Value 859
30-37 Read Ratio Limit 860
30-38 Write Ratio Limit 860
30-39 Crash Dump Capabilities Details 861
30-40 Crash Dump Capabilities (Parameter0 = 0x1) 861
30-41 Request Parameters 862
30-42 Response Data for Requested Frame 862
30-43 PECI Device Temp [15:0] Format - Temperature Sensor Data 871
31-1 What is Covered in This Chapter 873

31-2 Intel® QAT Usage Block Diagram 875
31-3 Direct I/O Assignment Model with IOV Support 877
31-4 EP Functional Description Block Diagram 879
31-5 Register Map 890
33-1 ACPI Cold Boot Sequence 898
33-2 Non-ACPI Cold Boot Sequence 899
33-3 ACPI Shutdown Sequence 900
33-4 Non-ACPI Shutdown Sequence 901
34-1 What is Covered in This Chapter 903
34-2 Global System Power States and Transitions 911
34-3 Processor Power States 913
35-1 TM1 Use of Processor Clock Duty Cycle Modulation 927
35-2 CLTT SMBus Connection to DIMMs 937
36-1 What is Covered in This Chapter 947
36-2 Register Map 950
37-1 What is Covered in This Chapter 964
37-2 Intel Atom® Processor C3000 Product Family Embedded Sub-System 966
37-3 Sample IE Usages 967
37-4 Register Map 972
38-1 What is Covered in This Chapter 985
39-1 Ball Quadrant Map 992
40-1 SPI Timing Diagram 1053
40-2 Dual-Output Fast Read Timing with 24-bit Addressing 1054
40-3 Dual I/O Fast Read Timing with 24-bit Addressing 1055
40-4 Quad Output Fast Read Timing with 24-bit Addressing 1056
40-5 Quad I/O Fast Read Timing with 24-bit Addressing 1057
40-6 1.05V GPIO Receiver Timing 1062
40-7 1.05V GPIO Driver Timing 1063
40-8 1.8V GPIO Receiver Timing 1064
40-9 3.3V GPIO Driver Timing 1067
42-1 SoC Package Drawing 1076

Tables

1-1 Features by product SKU - Server and Cloud Storage SKUs 0 through 4 107
1-2 Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10 109
1-3 Features by Product SKU - Extended Temperature SKUs 11 through 14 111
1-4 Terminology 121
1-5 Reference Documents 127
2-1 CPUID Leaf 0h 140
2-2 CPUID Leaf 1h, Output EAX and EBX 141
2-3 CPUID Leaf 1h, Output ECX 142
2-4 CPUID Leaf 1h, Output EDX 144
2-5 CPUID Leaf 2h 146
2-6 CPUID Leaf 4h 147
2-7 CPUID Leaf 5h 149
2-8 CPUID Leaf 6h 150
2-9 CPUID Leaf 7h 151
2-10 CPUID Leaf Ah 153
2-11 CPUID Leaf Bh 154
2-12 CPUID Leaf Dh 155
2-13 CPUID Leaf 10h 157
2-14 CPUID Leaf 14h 159
2-15 Basic CPUID Leaf 15h 160
2-16 Extended CPUID Leaf 80000000h 161
2-17 Extended CPUID Leaf 80000001h 162
2-18 Extended CPUID Leaves 80000002h, 80000003h, and 80000004h 163
2-19 Extended CPUID Leaf 80000006h 163
2-20 Extended CPUID Leaf 80000007h 164
2-21 Extended CPUID Leaf 80000008h 164
3-1 Host Memory Space Address Map 166
3-2 Relocatable MMIO in Host Memory Space 169
3-3 Host Fixed I/O Address Space 176
3-4 Host Relocatable I/O Address Space 180
3-5 Host PCI Bus, Device, Function Numbers and Device IDs 183
3-6 Configuration Registers Used to Configure Host Memory Space 188
3-7 Relocatable Host Memory-Mapped Aperture to Access Certain System Agent Registers 190
3-8 Fixed-Address Host I/O-Mapped Registers to Access Configuration Space 190
4-1 SoC Hard Straps/Pin Straps and Descriptions 195
4-2 Boot interface Hard Strap/ Pin Strap Configurations 198
4-3 Flash Descriptor Soft Straps 201
5-1 References 261
5-2 Registers in Host Configuration Space 264
6-1 Signal Names and Descriptions 265
6-2 References 266
6-3 SoC Machine Check MSR Addresses 272
6-4 MSR_SMM_MCA_CONTROL (MSR 52h) — Enhanced MCA Control 274
6-5 Local Error Register General Descriptions 285
6-6 List of SoC Global Error Registers 286
6-7 Local Error Registers — PCI Express Root Ports 299
6-8 Local Error Registers — PCI Express RCEC and RCiEP Functions 300
6-9 Local Error Registers — PCI Express Functions Attached to Virtual Root Ports 301
6-10 Local Error Registers — SATA, USB, LPC and SMBus-Legacy 303
6-11 Local Error Registers — SPI and HSUART 303
6-12 Local Error Registers — A-Unit and B-Unit 306
6-13 Local Error Registers — D-Units 307

6-14 Local Error Registers — Integrated Error Handler (IEH) 309
6-15 Summary of Default Error Logging and Responses 310
6-16 Registers in Host Configuration Space 321
6-17 Registers in Host Configuration Space 323
7-1 Signal Names and Descriptions 326
8-1 PIRQ Routing Control Information For INT[A-D] Messages 333
8-2 PIRQA through PIRQH Routing Register IRQ Decode 337
8-3 Routing of SCI to the I/O APIC 339
8-4 GPE0_DW Group Mapping 341
8-5 Access to the ACPI General Purpose Event Registers 342
8-6 I/O APIC Input Mapping 343
8-7 8259 PIC Input Mapping 345
8-8 Device Interrupt / Event Sources 346
9-1 References 347
9-2 Signal Names and Descriptions 348
9-3 DIMM Configurations, Two DIMM Socket per Channel 357
10-1 Signal Names and Descriptions 360
10-2 Bifurcation Control for PCIe RP Clusters 0 and 1 365
10-3 Configuration and Capabilities Register Map 368
10-4 Sideband Registers 368
11-1 References 370
11-2 Signal Names and Descriptions 371
11-3 PCI Express Features 372
11-4 PCI Express Transaction ID Handling 382
11-5 PCI Express Attribute Handling 383
11-6 PCI Express CompleterID Handling 384
11-7 Transaction Ordering on PCIe Block 385
11-8 Bridge Mapping for Interrupt Virtual Wires 387
12-1 References 396
12-2 Signal Names and Descriptions 397
12-3 SATA Controller Operations Summary 399
12-4 Interaction Between INTx# and MSI 400
12-5 Configuration and Capabilities Registers 402
12-6 Memory Mapped Registers 404
12-7 I/O Mapped Registers 409
13-1 References 411
13-2 Signal Names and Descriptions 412
13-3 Supported System Configurations 416
13-4 Network Features 417
13-5 Host Interface Features 417
13-6 Miscellaneous Features 418
13-7 LAN Functions Features 418
13-8 LAN Performance Features 419
13-9 Virtualization Features 420
13-10 Manageability Features 420
13-11 PCI and PCIe Capabilities Supported 422
13-12 Base Address Registers 423
13-13 Tx Data Flow 424
13-14 Rx Data Flow 425
13-15 Link Modes 427
13-16 Transaction Types Accepted by the Transaction Layer 432
13-17 Transaction Types Initiated by the Transaction Layer 434
13-18 Supported Message in the LAN Controllers (as a Receiver) 436
13-19 Response and Reporting of PCIe Error Events 440
13-20 PCIe Errors Reported to Device Software 443

13-21 Clients and Access Types to the Shared SPI Flash 449
13-22 Small Resource Structure 453
13-23 Large Resource Structure 453
13-24 VPD Structure 454
13-25 SPI Flash Module Encoding 459
13-26 GPI to SDP Bit Mappings 461
13-27 SDP Settings 461
13-28 LED Control Source (MODE) Mapping 463
13-29 MDC Frequency as Function of Link Speed and MDC Speed Bit 469
13-30 Clause 22 Basic MDIO Frame Format 470
13-31 Clause 45 Indirect Addressing MDIO Frame Format 471
13-32 Direct I^2C Interface Control 475
13-33 I^2C Read Transaction - Dummy Write 475
13-34 I^2C Read Transaction - Word Read 475
13-35 I^2C Read Transaction - Dummy Write 475
13-36 I^2C Read Transaction - Byte Read 475
13-37 I^2C Write Transaction - Word Write 476
13-38 I^2C Write Transaction - Byte Write 476
13-39 PHY Access Registers 477
13-40 PHY Registers' Addressing 477
13-41 MAC Control Frame Format 480
13-42 802.3X Packet Format 480
13-43 Transfer of PAUSE Packet to Host (DPF Bit) 484
13-44 LAN Controllers Delay Values (DV) Used For FCRTH 487
13-45 LAN Controllers FCRTL 488
13-46 Some Recommended Rx Packet Buffer Settings 489
13-47 Pacing Speeds at 10 GbE Link Speed 490
14-1 References 493
14-2 Signal Names and Descriptions 494
14-3 Transaction Type Supported by USB Block 505
14-4 Reset Signal Information 505
14-5 USB 2.0 Link States and Power Actions 506
14-6 USB 3.0 Link States and Power Actions 507
14-7 Configuration and Capabilities Register Map 509
14-8 Relocatable Memory-Mapped Registers 511
15-1 Platform Control Cluster (PCC) 523
16-1 Signal Names and Descriptions 526
16-2 SoC Circuitry Powered-On During the G2 (S5) Global Power State 529
16-3 SoC Circuitry Powered-On During the G3 Global Power State 529
16-4 Causes of SMI and SCI 533
16-5 Power Management Wake Events 537
16-6 Power Management Event Enables 541
16-7 Causes of Host Reset and Global Reset 544
16-8 Configuration and Capabilities Register Map 554
16-9 Relocatable Memory-Mapped Registers 554
16-10 Relocatable I/O-Mapped Registers - Power Management Controller (PMC) 555
16-11 Fixed-Address I/O-Mapped Registers 555
16-12 Relocatable I/O-Mapped Registers - Legacy SMBus Controller 556
16-13 Sideband Registers - Power Management Control (PMC) 556
16-14 Sideband Registers - Legacy SMBus (for TCO) 556
17-1 References 557
17-2 Signal Names and Descriptions 558
17-3 Configuration and Capabilities Register Map 561
17-4 Memory-Mapped Registers 562
18-1 References 565

18-2 Signal Names and Descriptions 566
18-3 Legacy COM I/O Ports 570
18-4 Supported Baud Rates 576
18-5 Interrupt Enabling 577
18-6 UART Memory Space 577
18-7 Interrupt Enabling 582
18-8 PCI Configuration Registers (HSUART_REGS_PCI) 588
18-9 UART and DMA Memory Space 589
18-10 UART Memory Mapped Registers 589
18-11 DMA Channel Memory Mapped Registers 590
18-12 UART I/O Mapped Registers 591
19-1 References 592
19-2 Signal Names and Descriptions 593
19-3 Flash Regions 598
19-4 Flash Protection Mechanism Summary 605
19-5 Programmed Access Error Status 607
19-6 Hardware Sequencing Opcodes 609
19-7 Address and Data Transfer for TPM 619
19-8 Configuration and Capabilities Register Map 623
19-9 BIOS Flash Program Register Address Map 624
20-1 References 626
20-2 Signal Names and Descriptions 627
20-3 LPC_CLKRUN_N Timings 630
20-4 LPC Register Map - Configuration and Capabilities Register Map 632
20-5 LPC Claimable Fixed I/O Range as Target on Primary Interface 633
20-6 LPC Claimable Configurable I/O Range as Target on Primary Interface 635
20-7 LPC Claimable Memory Mapped Range as Target on Primary Interface 636
20-8 LPC Claimable Configurable I/O Range as Target on Primary Interface 637
20-9 BIOS Boot Decode Claiming Agent 637
21-1 Interrupt Status Registers 639
21-2 Content of Interrupt Vector Byte 640
21-3 IOxAPIC Interrupt Message Address 648
21-4 IOxAPIC Interrupt Message Data 648
21-5 Configuration and Capabilities Register Map 651
21-6 IOxAPIC Register Access Window in Host Memory Space 652
21-7 IOxAPIC Registers 652
21-8 IOxAPIC Interrupt Messages for Local APICs in Host Memory Space 652
21-9 8259 (PIC) Registers in Host I/O Space 653
22-1 Configuration and Capabilities Register Map 657
22-2 Relocatable Memory-Mapped Registers 658
23-1 Counter Operating Modes 662
23-2 Fixed-Address I/O-Mapped Registers 666
24-1 Signal Names and Descriptions 668
24-2 RTC Standard and Extended Static RAM Banks 670
24-3 Relocatable Memory-Mapped Registers 674
24-4 Fixed-Address I/O-Mapped Registers 674
25-1 References 675
25-2 Legacy Replacement Routing 678
25-3 Fixed-Address Memory-Mapped Registers 683
26-1 GPIO Ball and Pad Name 686
26-2 Pin Name Descriptions 693
26-3 Input Signal Configuration 695
26-4 Output Signal Configuration 695
26-5 GPIO Pad Configuration Description 698
26-6 PMC pci_cfg.PWRMBASE 704

26-7 PMC pci_cfg.ABASE 705
27-1 References 706
28-1 References 711
28-2 Signal Names 712
28-3 Supported SMBus ARP, SMBus, and I2C Protocols 715
28-4 I2C Block Read 721
28-5 Enable for SMBALERT# (SMB_LEG_ALRT_N) 723
28-6 Enables for Legacy SMBus Controller Events 723
28-7 Enables for a Received Notify ARP Master Command 723
28-8 Registers in the Configuration Space 726
28-9 Registers in the Memory Space 727
28-10 Registers in the I/O Space 728
29-1 References 729
29-2 Signal Names 730
29-3 List of Supported SMBus ARP, SMBus, and I2C Protocols 732
29-4 ARP Nomenclature 734
29-5 Device Decodes of AV and AR Flags 734
29-6 UDID Format 735
29-7 ARP Slave Operations 737
29-8 Hardware Decoding of ARP, SMBus, and I2C Target Transactions 740
29-9 Hardware/Firmware Response to SMBus and ARP Protocols 741
29-10 ARP Master Operation 744
29-11 ARP Initialization Flow 746
29-12 SMT Timing Mode Maximum Clock Frequency Ranges 748
29-13 Master Descriptor Field Descriptions 751
29-14 SMBus Transaction Encodings 754
29-15 I2C Commands 757
29-16 DIMM SPD EEPROM Write-Disable Mechanism 764
29-17 Target Header Descriptor 767
29-18 Valid Target Descriptor MTYPE and TTYPE Combinations 769
29-19 Target Header Encodings (TSTS) Per Transaction Type (TTYPE) 770
29-20 Target Transaction Behavior Due to SUSCHKB.IRWST 776
29-21 Summary of SMT Interrupt Enables and Sources 785
29-22 Error MSI Scheduling 788
29-23 Interrupt Cause Information 789
29-24 SMT Soft Reset Exceptions 790
29-25 SMT Function Level Reset Exceptions 791
29-26 MCTP Over SMBus Packet Format 793
30-1 References 795
30-2 Signal Names 796
30-3 SMBus Write Commands 798
30-4 SMBus Read Command 798
30-5 PECI Proxy Command Protocol Format 801
30-6 PECI Proxy Read 802
30-7 Supported PECI Commands 806
30-8 Ping - PECI Proxy Block Write 807
30-9 Ping - PECI Proxy Block Read 808
30-10 GetDIB() PECI Proxy Block Write 809
30-11 GetDIB() PECI Proxy Block Read 810
30-12 PECI Revision Number Definition 811
30-13 GetTemp() PECI Proxy Block Write 812
30-14 GetTemp() PECI Proxy Block Read 813
30-15 RdPkgConfig() PECI Proxy Block Write 814
30-16 RdPkgConfig() PECI Proxy Block Read 815
30-17 WrPkgConfig() PECI Proxy Block Write 816

30-18 WrPkgConfig() PECI Proxy Block Read 817
30-19 RdIAMSR() PECI Proxy Block Write 819
30-20 RdIAMSR() PECI Proxy Block Read 820
30-21 RdPCIConfigLocal() PECI Proxy Block Write 822
30-22 RdPCIConfigLocal() PECI Proxy Block Read 823
30-23 WrPCILocalConfig() PECI Proxy Block Write 824
30-24 WrPCILocalConfig() PECI Proxy Block Read 826
30-25 RdEndPointConfig() PECI Proxy Block Write 827
30-26 RdEndPointConfig() PECI Proxy Block Read 828
30-27 WrEndPointConfig() PECI Proxy Block Write 829
30-28 WrEndPointConfig() PECI Proxy Block Read 830
30-29 MCA Access via RdEndPointConfig() 831
30-30 Endpoints Supporting Rd/WrPCIConfigLocal 832
30-31 Endpoints Supporting Rd/WrEndPointConfig 833
30-32 Summary of DRAM Thermal and Power Optimization Services 834
30-33 Channel Index and DIMM Index 835
30-34 Summary of CPU Thermal and Power Optimization Services 841
30-35 Power Control Register Unit Calculations 850
30-36 Response Data for Requested Items 863
30-37 RdPkgConfig() PECI Proxy Block Write 866
30-38 RdPkgConfig() PECI Proxy Block Read 867
30-39 Core Crash Details 869
30-40 Error Codes 872
31-1 Ring Assignment to Intel® QAT Virtual Functions 878
31-2 PCIe Commands Supported by RI 880
31-3 PCIe EP Function Mapping 880
31-4 EP Mapping of BARs to MMIOs 881
31-5 Bus, Device and Function Interpretation 881
31-6 PCIe Error Sources 884
31-7 Device-Specific Errors 889
32-1 Signal Descriptions 893
33-1 References 895
33-2 Signal Names and Descriptions 895
33-3 SoC Required Power Supplies 896
33-4 SoC Power Supply for each Supported Power State 896
33-5 Supported ACPI Transitions And Definitions 897
34-1 sVID Controller Signals 903
34-2 References 904
34-3 SoC Voltage Rails 907
34-4 sVID Commands 909
34-5 ACPI Power States 911
34-6 ACPI Power State Transitions for the SoC 912
34-7 Core C-States 914
34-8 Package C-States 914
34-9 ACPI P-State Mappings 915
34-10 I/O Power Management Summary 918
35-1 Signal Names and Descriptions 919
35-2 MSR_POWER_CTL (MSR 1FCh) 924
35-3 PROCHOT_N Signal Direction and Function 925
35-4 MSR Registers 946
36-1 Signal Names and Descriptions 948
36-2 Configuration and Capabilities Register Map 951
36-3 Relocatable Memory-Mapped Registers 953
36-4 Configuration and Capabilities Register Map 954
36-5 Relocatable Memory-Mapped Registers 955

36-6 Configuration and Capabilities Register Map 956
36-7 Relocatable I/O-Mapped Registers 957
36-8 Configuration and Capabilities Register Map 959
36-9 Relocatable Memory-Mapped Registers 960
36-10 Configuration and Capabilities Register Map 961
36-11 Relocatable Memory-Mapped Registers 962
36-12 Relocatable I/O-Mapped Registers 963
37-1 Signal Names and Descriptions 965
37-2 Configuration and Capabilities Register Map 973
37-3 Relocatable Memory-Mapped Registers 975
37-4 Configuration and Capabilities Register Map 976
37-5 Relocatable Memory-Mapped Registers 977
37-6 Configuration and Capabilities Register Map 978
37-7 Relocatable I/O-Mapped Registers 979
37-8 Configuration and Capabilities Register Map 981
37-9 Relocatable Memory-Mapped Registers 982
37-10 Configuration and Capabilities Register Map 983
37-11 Relocatable Memory-Mapped Registers 984
37-12 Relocatable I/O-Mapped Registers 984
38-1 References 985
38-2 Signal Names and Descriptions 986
39-1 Signal Pin Name Directory - Sorted by Name 995
39-2 Treatment of Reserved Pins 1026
39-3 Signals that Share the Twenty HSIO Lanes 1028
39-4 Voltage Pins Sorted by Platform VR and SoC Voltage Group 1029
39-5 Package Rotation (ROT) Pins 1032
39-6 Directory of Signal and Voltage Pins - Sorted by Pin Number 1033
40-1 SPI (17.14MHz) Signal Timing Specifications 1052
40-2 SPI (30MHz) Signal Timing Specifications 1052
40-3 SPI (48MHz) Signal Timing Specifications 1053
40-4 CS# Setup and CS# Hold 1054
40-5 1.05V GPIO Receiver DC Characteristics 1062
40-6 1.05V GPIO Receiver AC Characteristics 1062
40-7 1.05V GPIO Driver DC Characteristics 1063
40-8 1.05V GPIO Driver AC Characteristics 1063
40-9 1.8V GPIO Receiver DC Characteristics 1064
40-10 1.8V GPIO Receiver AC Characteristics 1064
40-11 1.8V GPIO Driver DC Characteristics 1065
40-12 1.8V GPIO Driver AC Characteristics 1065
40-13 1.8V GPIO Driver Timing 1065
40-14 3.3V GPIO Receiver DC Characteristics 1066
40-15 3.3V GPIO Receiver AC Characteristics 1066
40-16 3.3V GPIO Receiver Timing 1066
40-17 3.3V GPIO Driver DC Characteristics 1067
40-18 3.3V GPIO Driver AC Characteristics 1067
41-1 Storage Condition Ratings - Prior to Board-Attach 1069
41-2 Component Temperature Range 1070
41-3 Voltage Supply Requirements Under Normal Operating Conditions 1072
41-4 SoC VCC Load Line 1073
41-5 Supply Current Required - Server and Cloud Storage SKUs 0, 1, and 2 (See Table 1-1) 1074
41-6 Supply Current Required - Network & Enterprise Storage SKUs 3, 4, 5, 6, and 7 (See Table 1-2) and eTEMP SKUs 11 and 12 (See Table 1-3) 1074

41-7 Supply Current Required - Network & Enterprise Storage SKUs 8 and 9 (See Table 1-2) 1075
41-8 Supply Current Required - Network & Enterprise Storage SKU 10 (See Table 1-2) and eTEMP SKU 13 and 14 (See Table 1-3) 1075
43-1 Register Attributes Definitions 1081
44-1 Summary of PCI Configuration Registers—0/0/0 1084
44-2 Summary of Memory Mapped I/O Registers for C-Unit—MCHBAR 1085
44-3 Summary of Memory Mapped I/O Registers for A-Unit—MCHBAR 1086
44-4 Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR 1087
44-5 Summary of Memory Mapped I/O Registers for P-Unit—MCHBAR 1093
44-6 Summary of Memory Mapped I/O Registers—DEFVTDBAR 1096
44-7 Summary of Memory Mapped I/O Registers—DEFVTDBAR 1097
44-8 Summary of Sideband Registers—0x10 (Memory Controller 0) 1099
44-9 Summary of Sideband Registers—0x12 (Memory Controller 1) 1101
44-10 Summary of Sideband Registers—0x99 1102
45-1 Summary of PCI Configuration Registers—0/4/0 1482
46-1 Summary of PCI Configuration Registers—0/5/0 1508
47-1 Summary of PCI Configuration Registers—0/6/0, 0/22/0, and 0/23/0 1531
48-1 Summary of PCI Configuration Registers—0/9-12, 14-17/0 1592
48-2 Summary of Sideband Registers—0xB4 (Devices 9-12) 1599
48-3 Summary of Sideband Registers—0xB3 (Devices 14-17) 1599
49-1 Summary of PCI Configuration Registers—0/18/0 1818
49-2 Summary of Memory Mapped I/O Registers—SMTBAR 1819
50-1 Summary of PCI Configuration Registers—0/19 (or 20)/0 1871
50-2 Summary of Memory Mapped I/O Registers—MXTBA 1873
50-3 Summary of Memory Mapped I/O Registers—ABAR 1874
51-1 Summary of PCI Configuration Registers—0/21/0 1996
51-2 Summary of Memory Mapped I/O Registers—MBAR 1998
52-1 Summary of PCI Configuration Registers—0/24/0 2222
52-2 Summary of PCI Configuration Registers—0/24/1 2224
52-3 Summary of PCI Configuration Registers—0/24/4 2225
52-4 Summary of PCI Configuration Registers—0/24/3 2226
52-5 Summary of PCI Configuration Registers—0/24/2 2227
52-6 Summary of Memory Mapped I/O Registers—HECI1_MMIO_MBAR 2228
52-7 Summary of Memory Mapped I/O Registers—HECI2_MMIO_MBAR 2229
52-8 Summary of Memory Mapped I/O Registers—HECI3_MMIO_MBAR 2230
52-9 Summary of Memory Mapped I/O Registers—KT_HOST_MEMBAR 2231
52-10 Summary of Memory Mapped I/O Registers—Fixed Addresses 2232
52-11 Summary of I/O Registers—KT_HOST_IOBAR 2233
52-12 Summary of I/O Registers—IDE_HOST_PCMDIOBAR 2234
52-13 Summary of I/O Registers—IDE_HOST_PCTLIOBAR 2235
52-14 Summary of I/O Registers—IDE_HOST_BMIOBAR 2236
52-15 Summary of Sideband Registers for KT (Host)—0xe4 2237
52-16 Summary of Sideband Registers for IDE (Host)—0xe4 2238
53-1 Summary of PCI Configuration Registers—0/26/0,1,2 2383
53-2 Summary of Memory Mapped I/O Registers—MEMBA 2384
53-3 Summary of I/O Registers—IOBA 2386
54-1 Summary of PCI Configuration Registers HECI1—0/27/0 2438
54-2 Summary of PCI Configuration Registers HECI2—0/27/1 2440
54-3 Summary of PCI Configuration Registers HECI3—0/27/4 2441
54-4 Summary of PCI Configuration Registers KT (Host)—0/27/3 2442
54-5 Summary of PCI Configuration Registers—0/27/2 2443
54-6 Summary of Memory Mapped I/O Registers—HECI1_MMIO_MBAR 2444
54-7 Summary of Memory Mapped I/O Registers—HECI2_MMIO_MBAR 2445
54-8 Summary of Memory Mapped I/O Registers—HECI3_MMIO_MBAR 2446

54-9 Summary of Memory Mapped I/O Registers—KT_HOST_MEMBAR 2447
54-10 Summary of Memory Mapped I/O Registers—Fix Addresses 2448
54-11 Summary of I/O Registers—KT_HOST_IOBAR 2449
54-12 Summary of I/O Registers—IDE_HOST_PCMDIOBAR....2450
54-13 Summary of I/O Registers—IDE_HOST_PCTLIOBAR....2451
54-14 Summary of I/O Registers—IDE_HOST_BMIOBAR....2452
54-15 Summary of Sideband Registers for KT (Host)—0xf4....2453
54-16 Summary of Sideband Registers IDE (Host)—0xf4....2453
55-1 Summary of Memory Mapped I/O Registers—BAR or BAR1 2596
56-1 Summary of PCI Configuration Registers—0/31/0....2644
56-2 Summary of Sideband Registers—0xD2....2644
57-1 Summary of PCI Configuration Registers—0/31/1....2661
58-1 Summary of PCI Configuration Registers—0/31/2....2684
58-2 Summary of Memory Mapped I/O Registers—PWRMBASE 2685
58-3 Summary of I/O Registers—ABASE....2686
58-4 Summary of I/O Registers—Fixed Addresses....2687
58-5 Summary of Sideband Registers—0x82....2688
59-1 Summary of PCI Configuration Registers—0/31/4....2749
59-2 Summary of Memory Mapped I/O Registers—SMBMBAR 2750
59-3 Summary of I/O Registers—SBA 2751
59-4 Summary of I/O Registers—TCOBASE....2752
59-5 Summary of Sideband Registers—0xCF....2753
59-6 Summary of Sideband Registers—0xCC....2754
60-1 Summary of PCI Configuration Registers—0/31/5....2812
60-2 Summary of Memory Mapped I/O Registers—BIOS_SPI_BAR0....2813
60-3 Summary of Sideband Registers—0x93....2814
61-1 Summary of I/O Registers—Fixed I/O Ports 2875
62-1 Summary of I/O Registers—Fixed Address....2884
62-2 Summary of RTC Standard Static RAM Bank — Indexed Data....2885
62-3 Summary of RTC Extended Static RAM Bank — Indexed Data....2886
62-4 Summary of Sideband Registers—0xD1....2887
63-1 Summary of Memory Mapped I/O Registers—0xFED00000....2905
64-1 Summary of PCI Configuration Registers—0/31/1....2909
64-2 IOxAPIC Interrupt Message Address 2910
64-3 Summary of Memory-Mapped Registers—Fixed Addresses 2910
64-4 Summary of IOxAPIC Index/Window-Accessed Registers 2911
64-5 Summary of I/O Registers—Fixed Location 2912
65-1 Summary of Sideband Registers, Part 1 of 2—Sideband Port 0xC2....2940
65-2 Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5....2944
67-1 Summary of Sideband Registers—0xD0....3739
68-1 Summary of Sideband Registers (Lane 0 of 19) — 0xBA....3778
68-2 Summary of Sideband Registers (Lane 1 of 19) — 0xBA....3778
68-3 Summary of Sideband Registers (Lane 2 of 19) — 0xBA....3779
68-4 Summary of Sideband Registers (Lane 3 of 19) — 0xBA....3779
68-5 Summary of Sideband Registers (Lane 4 of 19) — 0xBA....3780
68-6 Summary of Sideband Registers (Lane 5 of 19) — 0xBA....3780
68-7 Summary of Sideband Registers (Lane 6 of 19) — 0xBA....3781
68-8 Summary of Sideband Registers (Lane 7 of 19) — 0xBA....3781
68-9 Summary of Sideband Registers (Lane 8 of 19) — 0xBA....3782
68-10 Summary of Sideband Registers (Lane 9 of 19) — 0xBA....3782
68-11 Summary of Sideband Registers (Lane 10 of 19) — 0xBA....3783
68-12 Summary of Sideband Registers (Lane 11 of 19) — 0xBA....3783
68-13 Summary of Sideband Registers (Lane 12 of 19) — 0xBA....3784
68-14 Summary of Sideband Registers (Lane 13 of 19) — 0xBA....3784
68-15 Summary of Sideband Registers (Lane 14 of 19) — 0xBA....3785

68-16 Summary of Sideband Registers (Lane 15 of 19) — 0xBA..... 3785
68-17 Summary of Sideband Registers (Lane 16 of 19) — 0xBB..... 3786
68-18 Summary of Sideband Registers (Lane 17 of 19) — 0xBB..... 3786
68-19 Summary of Sideband Registers (Lane 18 of 19) — 0xBB..... 3787
68-20 Summary of Sideband Registers (Lane 19 of 19) — 0xBB..... 3787
69-1 Model Specific Register (MSR) Index 3796

§ §

Volume 1: Program Overview

1 Introduction and Product Offerings

Note: This document contains preliminary information and is highly subject to change.

1.1 Overview

The Intel Atom® Processor C3000 Product Family is the next generation System-On-Chip (SoC) built on the latest Intel 14-nanometer process technology. This highly-integrated SoC contains two to 16 next generation 64-bit Intel Atom® processor cores depending on the product SKU. The SoCs were created to address the growing needs for the emerging markets like Microserver, Cloud Storage and growing Communication Infrastructure market segments.

Note: Throughout this document, the Intel Atom® Processor C3000 Product Family SoC will be referred to as simply SoC.

Network and Enterprise Storage SKUs are targeted for long life supply and extended communications reliability. Four Extended Temperature SKUs provide operation over an extended temperature range.

The parameter T_{CASE} is mentioned in this chapter and is the temperature of the SoC package measured at the geometric center of the topside of the Integrated Heat Spreader (IHS).

Note: The product SKUs, feature lists, and values in the following tables are preliminary based on current expectations and are subject to change without notice:

- Table 1-1, “Features by product SKU - Server and Cloud Storage SKUs 0 through 4”,
- Table 1-2, “Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10”,
- Table 1-3, “Features by Product SKU - Extended Temperature SKUs 11 through 14”

Table 1-1. Features by product SKU - Server and Cloud Storage SKUs 0 through 4 (Sheet 1 of 2)

Features	C3955 SKU 0	C3950 SKU 1	C3850 SKU 2	C3830 SKU 3	C3750 SKU 4
Number of 64-bit Intel Atom® Microarchitecture Goldmont Cores	16		12		8
Number of threads per Core	1				
Processor base frequency (GHz)	2.1	1.7	2.1	1.9	2.2
Intel® Turbo Boost Technology	Enabled	Enabled	Enabled	Enabled	Enabled
P0n Turbo frequency @ 70 °C (GHz)	2.4	2.2	2.4	2.3	2.4
Total SoC L2 Cache (MB)	16		12		16
L2 Cache for each Core (MB)	2 (shared by two cores)				2 (dedicated)
Maximum number of memory channels available	2				
Maximum DDR4 (1.2V) memory data rate supported (MT/s)	2400			2133	2400
Number of High-Speed I/O (HSIO) Lanes shared between PCIe*, SATA, and USB 3.0	20			12	
HSIO Lane Numbers (0 through 19) available	Lanes 0-19			Any 12 Lanes from Lanes 0-19	
Maximum number of PCI Express* (8.0 / 5.0 / 2.5 GT/s) Lanes	16 via HSIO Lanes			12 via HSIO Lanes	
Maximum number of SATA (6.0 / 3.0 / 1.5 Gbps) Lanes	16 via HSIO Lanes			12 via HSIO Lanes	
Maximum number of sets of USB 3.0 signals SSTX+/SSTX- SSRX+/SSRX-	4 via HSIO Lanes				
Number of sets of USB 2.0 signals (DATA+/DATA-)	4				

Table 1-1. Features by product SKU - Server and Cloud Storage SKUs 0 through 4 (Sheet 2 of 2)

Features	C3955 SKU 0	C3950 SKU 1	C3850 SKU 2	C3830 SKU 3	C3750 SKU 4
LAN Controller 0 (Gb/s) [1]	10 2.5 1				
LAN Controller 1 (Gb/s) [1]	10 2.5 1	1	not available		
Intel® Management Engine (Intel® ME)	Yes	Yes			
Innovation Engine (IE)	Yes	Yes			
Intel® QuickAssist Technology (Intel® QAT)	No				
Intel® QAT Speed (MHz)	n/a				
Intel® QAT Speed	n/a				
Intel® QAT Cryptographic Functions	n/a				
Relative temperature offset ($T_{CONTROL}$) from the Thermal Monitor Trip Temperature at which fans will be engaged (°C)	15				

Notes:
1. Each LAN controller must run the same LEK. See Chapter 13, "LAN Controllers" for details.

Table 1-2. Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10 (Sheet 1 of 2)

Features	C3958 SKU 5	C3858 SKU 6	C3758 SKU 7	C3558 SKU 8	C3538 SKU 9	C3338 SKU 10
Number of 64-bit Intel Atom® Microarchitecture Goldmont Cores	16	12	8	4		2
Number of threads per Core	1					
Processor base frequency (GHz)	2	2	2.2	2.2	2.1	1.5
Intel® Turbo Boost Technology	No					Yes
P0n Turbo frequency @ 70°C (GHz)	N/A					2.2
Total SoC L2 Cache (MB)	16	12	16	8		4
L2 Cache for each Core (MB)	2 (shared by two cores)		2 (dedicated)			
Maximum number of memory channels available	2					1 [3]
Maximum DDR4 (1.2V) memory data rate supported (MT/s)	2400			2133		1866
Number of High-Speed I/O (HSIO) Lanes shared between PCIe*, SATA, and USB 3.0	20			12		10 [1]
HSIO Lane Numbers (0 through 19) available	Lanes 0-19			Any 12 Lanes from Lanes 0-19		Any 10 Lanes from Lanes 0-19
Maximum number of PCI Express* (8.0 / 5.0 / 2.5 GT/s) Lanes	16 via HSIO Lanes			12 via HSIO Lanes		10 via HSIO Lanes
Maximum number of SATA (6.0 / 3.0 / 1.5 Gbps) Lanes	16 via HSIO Lanes			12 via HSIO Lanes		10 via HSIO Lanes
Maximum number of sets of USB 3.0 signals SSTX+/SSTX- SSRX+/SSRX-	4 via HSIO Lanes					
Number of sets of USB 2.0 signals (DATA+/DATA-)	4					

Table 1-2. Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10 (Sheet 2 of 2)

Features	C3958 SKU 5	C3858 SKU 6	C3758 SKU 7	C3558 SKU 8	C3538 SKU 9	C3338 SKU 10
LAN Controller 0 (Gb/s) [2]	10 2.5 1					2.5 1
LAN Controller 1 (Gb/s) [2]	10 2.5 1			2.5 1		
Intel® Management Engine (Intel® ME)	Yes					
Innovation Engine (IE)	Yes					
Intel® QuickAssist Technology (Intel® QAT)	Yes					No
Intel® QAT Speed	High	High	Medium	Low	Low	n/a
Intel® QAT Cryptographic Functions	Yes				No	n/a
Intel® QAT Compression/ Decompression	Yes					n/a
Relative temperature offset ($T_{CONTROL}$) from the Thermal Monitor Trip Temperature at which fans will be engaged (°C)	20					

Notes:
1. This product SKU has 10 total available HSIO Lanes. To meet the specified TDP, four of the 10 HSIO Lanes must be disabled with Soft Straps or BIOS. If more than six HSIO Lanes are enabled, the TDP will increase with a thermal resistance between the processor's case and the ambient air. An adequate thermal solution must be designed if more than 6 lanes are used.
2. Each LAN controller must run the same LEK. See Chapter 13, "LAN Controllers" for details.
3. Only one memory channel may be used with this SKU. It can be memory channel 0 or memory channel 1.

Table 1-3. Features by Product SKU - Extended Temperature SKUs 11 through 14 (Sheet 1 of 2)

Features	C3808 SKU 11	C3708 SKU 12	C3508 SKU 13	C3308 SKU 14
Number of 64-bit Intel Atom® Microarchitecture Goldmont Cores	12	8	4	2
Number of threads per Core	1			
Processor base frequency (GHz)	2	1.7	1.6	1.6
Intel® Turbo Boost Technology	No			Yes
P0n Turbo frequency @ 70°C (GHz)	N/A			2.1
Total SoC L2 Cache (MB)	12	16	8	4
L2 Cache for each Core (MB)	2 (shared by two cores)	2 (dedicated)		
Maximum number of memory channels available	2			1 [2]
Maximum DDR4 (1.2V) memory data rate supported (MT/s)	2133		1866	
Number of High-Speed I/O (HSIO) Lanes shared between PCIe*, SATA, and USB 3.0	20		8	6
HSIO Lane Numbers (0 through 19) available	Lanes 0-19		Any 8 Lanes from Lanes 0-19	Any 6 Lanes from Lanes 0-19
Maximum number of PCI Express* (8.0 / 5.0 / 2.5 GT/s) Lanes	16 via HSIO Lanes		8 via HSIO Lanes	6 via HSIO Lanes
Maximum number of SATA (6.0 / 3.0 / 1.5 Gbps) Lanes	16 via HSIO Lanes		8 via HSIO Lanes	6 via HSIO Lanes
Maximum number of sets of USB 3.0 signals SSTX+/SSTX- SSRX+/SSRX-	4 via HSIO Lanes			
Number of sets of USB 2.0 signals (DATA+/DATA-)	4			

Table 1-3. Features by Product SKU - Extended Temperature SKUs 11 through 14 (Sheet 2 of 2)

Features	C3808 SKU 11	C3708 SKU 12	C3508 SKU 13	C3308 SKU 14
LAN Controller 0 (Gb/s) [1]	10 2.5 1		2.5 1	
LAN Controller 1 (Gb/s) [1]	10 2.5 1		2.5 1	
Intel® Management Engine (Intel® ME)	Yes		Yes	
Innovation Engine (IE)	Yes		Yes	
Intel® QuickAssist Technology (Intel® QAT)	Yes			
Intel® QAT Speed	High	Medium	Low	
Intel® QAT Cryptographic Functions	Yes			
Intel® QAT Compression/ Decompression	Yes			
Relative temperature offset ($T_{CONTROL}$) from the Thermal Monitor Trip Temperature at which fans will be engaged (°C)	20			

Notes:
1. Each LAN controller must run the same LEK. See Chapter 13, "LAN Controllers" for details.
2. Only one memory channel may be used with this SKU. It can be memory channel 0 or memory channel 1.

1.2 SoC Key Features

This section describes the features offered in the SoC.

Figure 1-1. High-Level Block Diagram



1.2.1 Processor Details

The SoC has up to sixteen 64-bit Intel Atom® processor cores:

- Each core has an L1 (first-level) cache consisting of:
  - 24-KB data, parity protected.
  - 32-KB instruction, parity protected.
- L2 (second-level) instruction/data cache, ECC protected:
  - SoC with 2, 4 or 8 cores have a 2-MB L2 cache per core.
  - SoC with 12 or 16 cores share a 2-MB L2 cache per 2 cores.

1.2.2 Supported Technologies

- Intel® Virtualization Technology (Intel® VT) for Intel® 64 and IA-32 Intel® Architecture (Intel® VT-x).
- Intel® Virtualization Technology (Intel® VT-x) for Directed I/O (Intel® VT-d).
- Advanced Encryption Standard New Instructions (AES-NI).
- Secure Hash Algorithm New Instruction (SHA-NI).
- Intel® 64 Architecture.
- Intel® Streaming SIMD Extensions 4.1 (Intel® SSE4.1).
- Intel® Streaming SIMD Extensions 4.2 (Intel® SSE4.2).
- Execute Disable Bit.
- Intel® Turbo Boost Technology.
- Enhanced Intel SpeedStep® Technology.

1.2.3 System Memory Support

- Up to two 32/40 bit [1] or 64/72 bit wide memory channels. Up to two DIMMs per channel.
- Single-rank or dual-rank per DIMM module.
- ECC [4] and non-ECC support.
- DDR4 (1.2V):
  - 1600, 1866 [2], 2133, and 2400 MT/s.
  - x8 or x16 width for unbuffered memory (UDIMM, SO-DIMM and memory down).
  - x4 or x8 width devices for RDIMM
  - Minimum memory is:
    32 bit [1] wide memory channel: 1GB (4 Gb, 1 rank, x16 width)
    64-bit wide memory channel: 2GB (4 Gb, 1 rank, x16 width).
  - Maximum memory single channel is 128 GB (16 Gb, x4 width, 4 ranks, 64-bit).
  - Both memory channels maximum is 256 GB (128GB with two 64-bit channels).
- SoC memory population rules:
  - Both channels must be 32 bit [1] or 64 bits wide
  - At least 1 memory channel must be populated.
    Either channel 0 or channel 1 maybe disabled.
  - Both channels require either unbuffered memory (UDIMM, SO-DIMM or memory down), or registered memory (RDIMM and/or NVRDIMM). Technology mixing is not supported.
  - Rank mixing is allowed but can result in a speed bin loss.
  - Each populated channel must be x4 or x8 or x16 only (no width mixing within a channel) 4 Gb, 8 Gb, and 16 Gb technology device mixing between channels is allowed (i.e., Channel 0 can be x4 while Channel 1 is x8).

Notes:

1. A0 and A1 step silicon only support 64/72-bit wide memory channels.
2. The silicon design supports 1866 MT/s but is not validated on Intel platforms. Customers are responsible for validation.
3. With a standard DIMM and NVDIMM in the same channel, the NVDIMM must be in the second slot or be the same size or smaller than the standard DIMM.
4. The ECC SDRAM device must be of the same type and width as the SDRAM devices used for the data bits. This limitation is driven by the DDR4 spec.
   - It is NOT alright to use x16 SDRAM devices for data and a x8 device for ECC.
   - It is NOT alright to use x8 SDRAM devices for data and a x4 device for ECC.
5. Memory based on 16 Gb dual rank technology (including maximum memory configuration of 256GB) is supported by silicon but not validated on Intel platforms.

1.2.4 Integrated Clock Generator

The integrated clock generator requires two external crystals (32.768-kHz and 25-MHz) and eliminates the need for an external clock chip.

- Generates all required internal clocks.
- Two flex clock outputs for platform use.
- Five PCIe output clocks.
- Optional Spread-Spectrum Clocking support.

1.2.5 Intel® QuickAssist Technology (Intel® QAT)

Intel® QuickAssist Technology is only available on Network and Enterprise Storage SKUs and provides hardware acceleration for:

Symmetric cryptographic functions:

- Cipher operations.
- Hash/authenticate operation.
- Cipher-hash combined operation.

Public key functions:

- RSA operation, encryption/decryption and digital signature generation/verification.
- Modular exponentiation for Diffie-Hellman (DH).
- DSA parameter generation and digital signature generation/verification.
- Key derivation operation.
- Elliptic curve cryptography: ECDSA and ECDH.

Compression/Decompression:

- Deflate.

1.2.6 Intel® Management Engine (Intel® ME)

The Intel® ME provides the services that are released and documented in Intel® Server Platform Services Firmware (SPS 4.0) release.

1.2.7 Innovation Engine (IE)

The Innovation Engine (IE) is a complete, embedded, Intel Architecture system intended for Intel customers (system builders) to create innovative or differentiating firmware of their choosing. The IE is available on all SoC product SKUs bit is not required for normal system operation.

The IE is based on Intel® Quark™ technology:

- 32-bit Intel Architecture processor core
- Suite of connections to a number of platform resources

For security, the IE software is cryptographically bound to the owner, the system builder, using a digital-signing technique.

For the IE, the system builder can install an embedded operating system, drivers and application they develop on their own, or purchase them from a third-party vendor. Intel does not provide operating systems, drivers or applications for the IE.

The IE usage is only limited by its technical capabilities. Sample uses include using the IE as a replacement for a low-end Baseboard Management Controller (BMC), or offloading fast-loop sensor monitoring from the BMC.

1.2.8 Interface Features

1.2.8.1 High Speed I/O Lanes

Depending on the SoC product SKU, there are up to 20 High-Speed I/O (HSIO) lanes that are shared between the PCI Express*, Serial ATA (SATA) and Universal Serial Bus (USB) 3.0 ports. See the Chapter 10, "Flexible I/O Adapter (FIA) Overview" for more information on the sharing. The maximum number of available lanes is shown in Table 1-1 on page 107, Table 1-2 on page 109, and Table 1-3 on page 111.

1.2.8.1.1 PCIe Root Port Clusters

- Up to two PCIe Root Port Clusters 0 and 1.
- Fully-compliant to the *PCI Express Base Specification Revision 3.0*.
- Each 1x8 PCIe Root Port Cluster maybe bifurcated by BIOS to:
  - 1x8
  - 2x4
  - 2x2 and 1x4
  - 4x2
  - 4x1
- Minimum Root Port width is 1-lane.
- Maximum Root Port width is 8-lanes with degrades to x4, x2 or x1.
- Lane Reversal supported.
- Polarity Inversion supported.
- No support for peer-to-peer transfers between PCIe Root Ports.

1.2.8.1.2 Serial ATA (SATA)

The SATA ports are 3.1 or 2.0 capable:

- Up to 16 SATA ports:
  - Implemented with up to two controllers.
  - Up to eight ports per controller.
  - One SGPIO per controller.
- No support for IDE mode.

1.2.8.1.3 Universal Serial Bus (USB)

There is a single combo USB 3.0 and USB 2.0 controller with support for:

- Up to four USB 3.0 compliant ports.
- USB 2.0 ports have dedicated SoC I/O pins.
- USB 3.0 ports share HSIO lanes as described above.

1.2.8.2 LAN Ports

Depending on the SoC product SKU, there is either one or two, dual-port, Enterprise-Class, LAN controllers. The controllers support 10GbE or 2500BASE-X depending on the product SKU.

- Based on Intel® Ethernet Controller X55x
- 10GbE LAN ports support SFI, KR, 2500BASE-X, SGMII and 1000BASE-KX
- 2500BASE-X LAN ports support 2500BASE-X, SGMII and 1000BASE-KX
- SGMII is supported for Full Duplex 10Mb, 100Mb and 1Gb
- No support for Half Duplex at 10Mb, 100Mb, 1Gb, 2.5Gb or 10Gb
- Management Interface via NC-SI or SMBus

1.2.8.3 SMBus Controllers

Note: There are seven sets of SMBus pins. And so a maximum of seven SMBus controllers may be configured to be active.

The SoC has the following 10 SMBus controllers:

- Legacy and Host SMBus controllers used by the IA cores
- PECI over SMBus controller
- LAN Management SMBus controller for BMC use
- Three Management Engine SMBus controllers
- Three Innovation Engine SMBus controllers

1.2.8.4 Embedded Multi Media Card (eMMC)

The Embedded Multi-Media Controller (eMMC) is a high speed Flash memory controller that provides low cost, small form factor storage.

- Support for eMMC v5.0
- Eight-bit interface maximum frequency of 200 MHz for transfer rates up to 400 MB/s

1.2.8.5 High-Speed Universal Asynchronous Receiver/Transmitter

Note: At most, three of the SoC four High Speed Universal Asynchronous Receiver/Transmitter (HSUART) controllers can be active. One set of the SoC HSUART pins is configurable to be either the Host Root HSUART or else the Innovation Engine (IE) HSUART.

There are 4 HSUART each supporting Clear-To-Send (CTS) and Request-To-Send (RTS) depending on MUXing. Three (3) of the HSUARTs are in the IA Host space and 1 is in the Innovation Engine Root space.

- Baud rate from 300 bps to 3.6864 Mbps

1.2.8.6 Low Pin Count (LPC)

- LPC
  - Interface is described in the *Intel® Low Pin Count (LPC) Interface Specification*
  - Support for Security Device Trusted Platform Module (TPM)

1.2.8.7 Serial Peripheral Interface (SPI)

- Supports up to two SPI NOR Flash devices and a SPI NOR TPM device
- Supports 17 MHz, 30 MHz, and 48 MHz SPI Devices
- Supports Serial Flash Discovery Parameters (SFDP)
- Supports Quad I/O Fast Read, Quad Output Fast Read, Dual IO Fast Read

1.2.9 Package

The SoC is available in one package size:

- A 34 x 28 mm 1310-ball FCBGA package (FCBGA15)
- Integrated Heat Spreader (IHS)
- 0.65 mm minimum outer pin pitch, maintaining 0.7mm pitch for breakout direction to keep 0.7 mm pitch board routing rules.

1.2.10 Testability

- Includes boundary-scan for board and system level testability.

1.3 Terminology

Table 1-4. Terminology (Sheet 1 of 6)

Term	Description
1000BASE-KX	1000BASE-KX is the IEEE 802.3ap electrical specification for transmission of 1 Gb/s Ethernet over the backplane.
2500BASE-X	Refer to 2.5 GbE in this table. Note this is not an IEEE Standard.
1000BASE-T	1000BASE-T is the specification for 1 Gb/s Ethernet over category 5e twisted pair cables as defined in IEEE 802.3 clause 40.
2.5 GbE	The 2.5-GbE link mode is a special enhanced-speed mode of the 1000BASE-X link mode. This mode should not be confused with third-party solutions being offered in the marketplace today. Contact your local Intel representative for further information on the scope of this feature.
ACPI	Advanced Configuration and Power Interface
ADR	Asynchronous DRAM Refresh
AEN	Asynchronous Event Notification
AFE	Analog Front End
Aggressor	A network that transmits a coupled signal to another network.
AH	IP Authentication Header - An IPsec header providing authentication capabilities defined in RFC 4302.
Anti-Etch	Any plane-split, void, or cutout in a VCC or GND plane is referred to as an anti-etch.
ARP	Address Resolution Protocol
ASF	Alert Standard Format
b/w	Bandwidth
BER	Bit Error Rate
BGA	Ball Grid Array
BIOS	Basic Input/Output System. BIOS is the same as what is called UEFI IA Firmware in this document. Both terms are used and refer to the same thing.
BIST FIS	Built-In Self-Test Frame Information Structure
BMC	Baseboard Management Controller (often used interchangeably with MC)
BT	Bit Time
Bus Agent	A component which represents a load on a bus.
CDV	Cell Delay Variation
CMC	Common Mode Choke
CMCI	Corrected Machine Check error Interrupt
CMP	Chip-Level Multi Processing (CMP)
CRC	Cyclic Redundancy Check
CSR	Configuration and Status Register
DCA	Direct Cache Access
DDR3	Third generation Double Data Rate SDRAM memory technology that is the successor to DDR2 SDRAM.
DDR4	Forth generation Double Data Rate SDRAM memory technology that is the successor to DDR3 SDRAM.
DFT	Design for Testability
DMA	Direct Memory Access
DMTF	Distributed Management Task Force standard body
DP	Display Port

Table 1-4. Terminology (Sheet 2 of 6)

Term	Description
DQ	Descriptor Queue
DUT	Device Under Test
DW	Double Word (4 bytes)
ECC	Error Correction Code
EEE	Energy Efficient Ethernet - IEEE 802.3az standard
EEPROM	Electrically Erasable Programmable Memory. A non-volatile memory directly accessible from the host.
EHCI	Enhanced Host Controller Interface
EMI	Electromagnetic Interference
Enhanced Intel SpeedStep® Technology	Allows the operating system to reduce power consumption when performance is not needed.
EOP	End of Packet
EPT	Extended Page Tables
ESD	Electrostatic Discharge
Execute Disable Bit	The Execute Disable bit allows memory to be marked as executable or non-executable, when combined with a supporting operating system. If code attempts to run in non-executable memory the processor raises an error to the operating system. This feature prevents some classes of viruses or worms that exploit buffer overrun vulnerabilities and improves the overall system security. See the Intel® 64 and IA-32 architectures software developer manuals for more detailed information.
FC	Flow Control
FCS	Frame Check Sequence
Firmware (FW)	Embedded code on the LAN controller that implements the NC-SI protocol and pass-through functionality.
Flight Time	A term in the timing equation that includes the signal propagation delay, any effects the system has on the driver TCO, plus any adjustments to the signal at the receiver needed to guarantee the receiver setup time. More precisely, flight time is defined as the following: • The time difference between a signal at the input pin of a receiving agent crossing the switching voltage (adjusted to meet the receiver manufacturer conditions required for AC timing specifications; i.e., ringback, etc.) and the output pin of the driving agent crossing the switching voltage when the driver is driving a test load used to specify the driver AC timings. Maximum and Minimum Flight Time – Flight time variations are caused by many different parameters. The more obvious causes include the board dielectric constant variation, changes in load condition, crosstalk, power noise, variation in termination resistance, and differences in I/O buffer performance as a function of temperature, voltage, and manufacturing process. Some less obvious causes include effects of Simultaneous Switching Output (SSO) and packaging effects. Maximum flight time is the largest acceptable flight time a network experiences under all conditions. Minimum flight time is the smallest acceptable flight time a network experiences under all conditions.
FS	Full-speed. Refers to USB.
Host Interface	RAM on the LAN controller shared between the firmware and the host, and used to pass commands from the host to the firmware and responses from the firmware to the host.
HPC	High Performance Computing
HS	High-speed. Refers to USB.
IIO	The Integrated I/O Controller. An I/O controller that is integrated in the processor die.
IOMMU	Input/Output Memory Management Unit
iMC	The Integrated Memory Controller. A Memory Controller that is integrated in the processor die.
IE	Innovation Engine
Intel® 64 Technology	64-bit memory extensions to the IA-32 architecture. Further details on the Intel 64 architecture and the programming model are found at: http://developer.intel.com/technology/intel64/.
Intel® ME	Intel® Management Engine

Table 1-4. Terminology (Sheet 3 of 6)

Term	Description
IPC	Inter-Processor Communication
IPDC	Internet Portal Data Center
IPI	Inter-Processor Interrupt
IPG	Inter-Packet Gap
IPMI	Intelligent Platform Management Interface specification
Intel® QuickAssist Technology	Intel® QuickAssist Technology consists of a family of interrelated Intel and industry-standard technologies that simplify the use and deployment of accelerators on the Intel platforms.
Intel® Virtualization Technology (Intel® VT)	Processor virtualization which when used in conjunction with the Virtual Machine Monitor software enables multiple, robust independent software environments inside a single platform.
Integrated Heat Spreader (IHS)	A component of the processor package used to enhance the thermal performance of the package. Component thermal solutions interface with the processor at the IHS surface.
ISA	Instruction Set Architecture
ISI	The effect of a previous signal (or transition) on the interconnect delay. For example, when a signal is transmitted down a line and the reflections due to the transition have not completely dissipated, the following data transition launched onto the bus is affected. Interconnect Symbolic Interference (ISI) is dependent upon frequency, time delay of the line, and the reflection coefficient at the driver and receiver. ISI impacts both timing and signal integrity.
Jitter	Any timing variation of a transition edge or edges from the defined Unit Interval (UI).
LAN (Auxiliary Power-Up)	If connecting the LAN controller to a power source (occurs even before system power-up).
Land	The contact point of the SoC FCBGA package.
LCD	Name for the external LAN Connected Device, sometimes also called a PHY device. The LCD name distinguishes between the whole device and the PHY portion within the LCD.
LCI	LAN Connect Interface
LLC	Last Level Cache
LLDP	Link Layer Discovery Protocol defined in IEEE 802.1AB and used by IEEE 802.3az (EEE) for system wake time negotiation.
LOM	LAN on Motherboard
LPC	Low Pin Count
LPI	Low-Power Idle is the low-power state of Ethernet link as defined in IEEE 802.3az.
LRU	Least Recently Used. A term used in conjunction with cache hierarchy.
LS	Low-speed. Refers to USB.
LSO	Large Send Offload
LTR	Latency Tolerance Reporting (PCI Express* (PCIe*) protocol)
LVR	Linear Voltage Regulator
M0	Intel® Management Engine (Intel® ME) power state where all HW power planes are activated. Host power state is S0.
M3	Intel® Management Engine (Intel® ME) power state where all HW power planes are activated, however the host power state is different than S0 (some host power planes are not activated). Host PCI-E* interface are unavailable to the host SW. Main memory is not available for Intel® Management Engine use.
MAC	Media Access Control
MC	Management Controller
MCA	Machine Check Abort
MCTP	DMTF Management Component Transport Protocol (MCTP) specification. A transport protocol to allow communication between a management controller and controlled device over various transports.
MDIO	Management Data Input/Output Interface over MDC/MDIO lines

Table 1-4. Terminology (Sheet 4 of 6)

Term	Description
ME	See Intel® Management Engine (Intel® ME)
MIFS/MIPG	Minimum Inter-Frame Spacing/Minimum Inter-Packet Gap
MLC	Mid-Level Cache
MMC	Multi-Node Management Controller
MMW	Maximum Memory Window
MPS	Maximum Payload Size in PCIe specification
MSS	Maximum Segment Size. Largest amount of data, in a packet (without headers) that can be transmitted. Specified in bytes.
MTU	Maximum Transmit Unit. Largest packet size (headers and data) that can be transmitted. Specified in bytes.
NC	Network Controller
NC-SI	Network Controller Sideband Interface DMTF Specification
Network	The trace of a Printed Circuit Board (PCB) that completes an electrical connection between two or more components.
NIC	Network Interface Controller
NVDIMM	Nonvolatile DIMM is a DIMM technology that will save its DRAM content to flash on power loss and allow recover of the data on the next system boot.
OOB	Out of Band
Overshoot	The maximum voltage observed for a signal at the device pad, measured with respect to V_{CC}.
Pad	The electrical contact point of a semiconductor die to the package substrate. A pad is only observable in simulations.
PCI, PCIe*	Peripheral Component Interconnect (Express). In this document, this interconnect refers to the PCI logical layer used by the SoC I/O fabric protocol.
PCI Express*	PCI Express
Pcode	Power Management Unit Micro-code
PCS	Physical Coding Sub layer
PEC	Packet Error Code
PECI	Platform Environmental Control Interface
PHY	Physical Layer Device
Pin	The contact point of a component package to the traces on a substrate, such as the motherboard. Signal quality and timings are measured at the pin.
PLC	Platform LAN Connect
PMA	Physical Medium Attachment
PMC	Power Management Controller
PMD	Physical Medium Dependent
PMU	Power Management Unit
Power-Good	Power-Good, or PWRGOOD (an active high signal) indicates that all the system power supplies and clocks are stable. PWRGOOD does go active a predetermined time after system voltages are stable and does go inactive as soon as any of these voltages fail their specifications.
Processor	The 64-bit, single-core or multi-core component (package)
Processor Core	The term Processor Core refers to the silicon die itself which contains multiple execution cores. Each execution core has an instruction cache, data cache, and shares its 1-MB L2 cache with a sibling execution core.
PXE	Preboot Execution Environment
Rank	A unit of DRAM corresponding 4 to 16 devices in parallel, ignoring ECC. These devices are usually, but not always, mounted on a DIMM Raw Card.

Table 1-4. Terminology (Sheet 5 of 6)

Term	Description
Ringback	The voltage to which a signal changes after reaching its maximum absolute value. Ringback is caused by reflections, driver oscillations, or other transmission line phenomena.
RP	Root Port
RTC	Real Time Clock
SA	System Agent
SATA	Serial ATA
SDP	Software Defined Pins
SerDes	Serializer/Deserializer: A transceiver that converts parallel data to serial data and vice-versa.
SFD	Start Frame Delimiter
SFI	SerDes Frame Interface
SFP	Small Form-factor Pluggable
SFP+	enhanced Small Form-factor Pluggable
SGMII	Serialized Gigabit Media Independent Interface ***Note:*** SoC SGMII is supported for Full Duplex 10mb, 100mb and 1Gb only (No Half Duplex support).
SIMD	Single Instruction Multiple Data
SMBus	System Management Bus. A two-wire interface through which simple system and power management related devices communicate with the rest of the system. A bus carrying various manageability components, including the LAN controller, BIOS, sensors, and remote-control devices. SMBus is based on the operational principles of the I^2C two-wire serial bus from Philips Semiconductor.
So-DIMM	Small outline Dual In-line Memory Module
SPD	Serial Presence Detect
SPI	Serial Peripheral Interface
SSE	Intel® Streaming SIMD Extensions (Intel® SSE)
SSO	Simultaneous Switching Output (SSO) effects are differences in electrical timing parameters and degradation in signal quality caused by multiple signal outputs simultaneously switching voltage levels in the opposite direction from a single signal or in the same direction. These are called odd mode and even mode switching, respectively. This simultaneous switching of multiple outputs creates higher current swings that may cause additional propagation delay (“push-out”) or a decrease in propagation delay (“pull-in”). These SSO effects may impact the setup and/or hold times and are not always taken into account by simulations. System timing budgets include margin for SSO effects.
STR	Suspend To RAM
Stub	The branch from the bus trunk terminating at the pad of an agent.
SVR	Switched Voltage Regulator
TAC	Thermal Averaging Constant
TCO	Total Cost of Ownership (TCO) System Management
TDP	Thermal Design Power
TDR	Time Domain Reflectometry
TLB	Translation Lookaside Buffer
TLP	Transaction Layer Packet in the PCI Express specification
Trunk	The main connection, excluding interconnect branches, from one end-agent pad to the other end-agent pad.
TSO	Transmit Segmentation Offload. A mode in which a large TCP/UDP I/O is handed to the device which the device then segments into L2 packets according to the requested MSS.
TSOD	Temperature Sensor On DIMM

Table 1-4. Terminology (Sheet 6 of 6)

Term	Description
UDIMM	Unbuffered Dual In-line Memory Module
UEFI IA Firmware	This is another term used for BIOS. Both terms are used and refer to the same thing.
UHCI	Universal Host Controller Interface
Undershoot	The minimum voltage extending below V_{SS} observed for a signal at the device pad.
Unit Interval (UI)	Binary signaling convention that is measure of time representing the transmission of a single data bit in a serial data stream. One bit is sent for every forwarded clock edge, whether it be a rising edge or a falling edge. If a number of edges are collected at instances t1, t2, tn,...., tk, then the UI at instance "n" is defined as the following: UI n = t n - t n-1.
USB	Universal Serial Bus
VCC	Processor core-power supply
Vcc_core	The core-power rail for the processor.
Victim	A network that receives a coupled crosstalk signal from another network is called the victim network.
VLAN	Virtual LAN
VPD	Vital Product Data (PCI protocol)
VRD	The Voltage Regulator Down (a down on the board solution) for the processor. The VRD is a DC-DC converter module that supplies the required voltage and current to a single processor.
VSS	Processor ground
Intel® VT-d	Intel® Virtualization Technology (Intel® VT-x) for Directed I/O (Intel® VT-d)
Intel® VT-x	Intel® Virtualization Technology (Intel® VT) for Intel® 64 and IA-32 Intel® Architecture (Intel® VT-x)
x1	Refers to a link or port with one physical lane.
x2	Refers to a link or port with two physical lanes.
x4	Refers to a link or port with four physical lanes.
x8	Refers to a link or port with eight physical lanes.
XDP	eXtended Debug Port

1.4 Related Documents

Refer to the following documents for additional information and guidance in developing platform boards using the SoC.

Table 1-5. Reference Documents (Sheet 1 of 3)

Document	Document Number / Location
Intel® 64 and IA-32 Architectures Software Developer's Manual	325462

Table 1-5. Reference Documents (Sheet 2 of 3)

Document	Document Number / Location
Intel® Low Pin Count (LPC) Interface Specification	251289
PCI Express Base Specification Revision 3.0	https://pcisig.com/specifications
PCI Local Bus Specification, Revision 3.0	https://pcisig.com/specifications
PCI Express Card Electromechanical Specification, Revision 3.0	https://pcisig.com/specifications
PCI Express Mini Card Electromechanical Specification, Revision 2.0	https://pcisig.com/specifications
PCI-to-PCI Bridge Architecture Specification, Revision 1.2	https://pcisig.com/specifications
PCI Bus Power Management Interface Specification, Revision 1.2	https://pcisig.com/specifications
Universal Serial Bus 3.0 Specification, Revision 1.0	http://www.usb.org/developers/docs/
Universal Serial Bus Specification, Revision 2.0	http://www.usb.org/developers/docs/usb20_docs/
eXtensible Host Controller Interface for Universal Serial Bus (xHCI), Revision 1.1	https://www.intel.com/content/www/us/en/io/universal-serial-bus/extensible-host-controler-interface-usb-xhci.html
Enhanced Host Controller Interface Specification for Universal Serial Bus, Revision 1.0	https://www.intel.com/content/www/us/en/io/universal-serial-bus/ehci-specification-for-usb.html
System Management Bus (SMBus) Specification, Version 3.0	http://smbus.org/specs/SMBus_3_0_20141220.pdf
Alert Standard Format (ASF) Specification, Version 2.0	https://www.dmtf.org/sites/default/files/standards/documents/DSP0136.pdf
Management Component Transport Protocol (MCTP) Base Specification, Version 1.1.0	https://www.dmtf.org/sites/default/files/standards/documents/DSP0236_1.1.0.pdf
Intel® QuickAssist Technology API Programmer's Guide	https://01.org/sites/default/files/page/330684-001us_api_pg.pdf
Advanced Configuration and Power Interface Specification Version 5.0, Errata A	http://uefi.org/specifications
SPD Annex L, Serial Presence Detect (SPD) for DDR4 SDRAM Modules	https://www.jedec.org/ *JDEC Standard Number* 21-C
PCI-SIG SR-IOV Primer: An Introduction to SR-IOV Technology*	https://www.intel.com/content/dam/doc/application-note/pci-sig-sr-iov-primer-sr-iov-technology-paper.pdf
Embedded Multi-Media Card (eMMC), Electrical Standard	https://www.jedec.org/document_search?search_api_views_fulltext=jesd84-b51

Table 1-5. Reference Documents (Sheet 3 of 3)

Document	Document Number / Location
PC16550D Universal Asynchronous Receiver/Transmitter With FIFOs (Rev. C)	http://www.ti.com/lit/ds/symlink/pc16550d.pdf
Serial Flash Discoverable Parameters (SFDP), JEDEC Specification JESD216B	https://www.jedec.org/standards-documents/docs/jesd216b
IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a	https://www.intel.com/content/dam/www/public/us/en/documents/technical-specifications/software-developers-hpet-spec-1-0a.pdf

Note: For release dates or latest revisions and documentation numbers, contact the appropriate Intel field representative.

§ §

Volume 2: Functional

February 2018
Order Number: 337018-002

2 Multi-Core Intel Atom® Processors

Warning: This document contains preliminary information and is highly subject to change.

2.1 Introduction

The SoC is a highly-integrated System-on-Chip (SoC). The SoC core is a 3-way superscalar, out-of-order, IA core. It is designed using the cutting edge 14 nm process. The SoC core provides roughly 40% Instructions-Per-Cycle (IPC) increase over the previous Intel Atom® processor core.

Also see Table 1-5, "Reference Documents" for newest version of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

The SoC supports a variety of SKUs: up to 16 cores (with SKUs containing 2, 4, 8, 12 or 16 cores). Refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The cores and the rest of the SoC are shown in a general block diagram in Figure 2-1. Most of the chapters in this document refer to this diagram to convey the portion of the SoC pertaining to the chapter.

Figure 2-1. What is Covered in This Chapter



2.2 Features

The main architectural features are:

- Intel® Xeon® series processor Instruction Set Architecture (ISA) compatibility
- Intel® Virtualization Technology (Intel® VT-x, Intel® VT-d):
  - Intel® VT-x for Intel® IA-32 Architecture
  - Intel® VT and Intel® VT-d for Directed I/O
- Each core supports 1 hardware thread
- Each core has an L1 cache consisting of:
  - 24-KB data, parity protected
  - 32-KB instruction, parity protected
- L2 (second-level) instruction/data cache, ECC protected:
  - SoC with 2, 4 or 8 cores have 2-MB L2 per core
  - SoC with 12 or 16 cores share a 2-MB L2 per 2 cores
- 3-wide Out-of-Order (OOO) scheduler
- Improved instruction fetch and decode functions
- Improved branch prediction
- Improvements to TLB and caching hierarchy
- Hybrid OOO scheduling and OOO cache miss processing
- Per core power gating support
- Intel® Streaming SIMD Extensions 4.1 and 4.2 (SSE4.1 and SSE4.2)
- Intel® 64 bit architecture
- Support for IA-32 instruction set
- Support for Intel® Advanced Encryption Standard New Instructions (Intel® AES-NI)
- Secure Hash Algorithm New Instruction (SHA-NI)
- Support for rd_rand and rd_seed instructions
- Intel® Turbo Boost Technology (SKU dependent)
- Supported CPU Power States (C-States): C0, C1, C1e, and C6.

2.2.1 Goldmont New Technologies and ISA Extensions

Goldmont is the codename for the next generation 64-bit Intel® Atom™ processor cores in the SoC.

- EPT - Extended Page Tables (hardware virtualization of page tables).
- Hybrid Out-of Order (OOO) scheduling and OOO cache miss processing.
- Intel® Secure Hash Algorithm Extensions - instruction extensions that target the acceleration of the Secure Hash Algorithm (SHA).
- DRNG - Digital Random Number Generator Instructions:
  - RDRAND
  - RDSEED
- SMM Range Register - Full SMM range protection.
- Energy Efficient Turbo - Improved performance headroom.
- SMM external call trap execute disable - Security feature detects SMM code accesses outside SMRR and causes a machine check.
- APIC Virtualization; x2 APIC - Better APIC handling in Intel® VT mode.
- Pause Loop Exiting - Better spin-lock handling in Intel® VT mode.
- VMCS shadowing - Better performance of VMREAD,VMWRTE under nested virtual machine scenarios.
- CPUID Faulting - Better CPUID handling in VT mode.
- RTIT 2.0 - Improvements to make RTIT architectural.
- Memory Protection Extensions (MPX) + XSAVE - Security technology to detect buffer overflow attacks.
- "Light" Machine Check Abort (MCA) - Corrected Machine Check error Interrupt (CMCI), additional parity.
- Cache QOS - L2 cache partitioning for better real-time performance.
- Parity on IDI (Intra-Die Interconnect).
- 40-bit memory address (1,024 GB).

2.2.2 Intel® Virtualization Technology

Intel® Virtualization Technology (Intel® VT) makes a single system appear as multiple independent systems to the software. This allows multiple, independent operating systems to run simultaneously on a single system. Intel VT comprises technology components to support virtualization of platforms based on Intel® architecture microprocessors and chipsets. Intel® Virtualization Technology for IA-32, Intel® 64 and Intel® Architecture (Intel® VT-x) added hardware support in the processor to improve the virtualization performance and robustness. Intel® VT-x specifications and functional descriptions are included in the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

The first revision of this technology (Intel® VT-x) added hardware support in the processor to improve the virtualization performance and robustness. The latest revisions of this specification (Intel® VT-d), now called "Intel Virtualization Technology for Directed I/O, v1.3" adds direct chipset hardware hooks to improve I/O performance and robustness through DMA remapping. The SoC incorporates the Input/Output Memory Management Unit (IOMMU) (Intel® VT-d) block inside the System Agent to facilitate the translation.

2.2.3 Intel® VT-x Objectives

- Intel® Xeon® series processor Instruction Set Architecture (ISA) compatibility
- Robust - Virtual Machine Monitors (VMMs) no longer need to use paravirtualization or binary translation. This means that they run off-the-shelf operating systems and applications without any special steps.
- Enhanced - Intel® VT enables VMMs to run 64-bit guest operating systems on IA x86 processors.
- More Reliable - Due to the hardware support, VMMs are now smaller, less complex, and more efficient. This improves reliability and availability and reduces the potential for software conflicts.
- More Secure - Use of hardware transitions in the VMM strengthens the isolation of VMs and further prevents corruption of one VM from affecting others on the same system. Intel VT-x provides hardware acceleration for virtualization of IA platforms. VMMs use Intel VT-x features to provide improved reliable virtualized platform.

2.2.4 Intel® VT-x Features

- Extended Page Tables (EPT):
  - An EPT is hardware-assisted page table physical memory virtualization
  - EPT supports guest VM execution in unpaged protected / real address mode
  - EPT eliminates VM exits from guest OS to the VMM for shadow page-table Maintenance
- Virtual Processor IDs (VPID):
  - The ability to use an assigned VM Virtual Processor ID to tag processor core
- Hardware structures (such as TLBs) allowing a logic processor to cache information (such as TLBs) for multiple-linear address spaces:
  - This avoids flushes on VM transitions to give a lower-cost VM transition time
- Overall reduction in virtualization overhead
- Guest Preemption Timer:
  - A mechanism for a VMM to preempt the execution of a guest OS VM after an amount of time specified by the VMM. The VMM sets a timer value before entering a guest.
  - The feature aids VMM developers in flexibility and Quality of Service (QoS) guarantees flexibility in guest VM scheduling and building QoS schemes.
- Descriptor-Table Exiting:
  - Descriptor-table exiting allows a VMM to protect a guest OS from internal (malicious software based) attack by preventing relocation of key system data structures like Interrupt Descriptor Table (IDT), Global Descriptor Table (GDT)
- Local Descriptor Table (LDT), and Task Segment Selector (TSS):
  - A VMM using this feature intercepts (by a VM exit) attempts to relocate these data structures and prevent them from being tampered by malicious software
- VM Functions:
  - A VM function is an operation provided by the processor that is invoked using the VMFUNC instruction from guest VM without a VM exit
  - A VM function to perform EPTP switching is supported and allows guest VM to load a new value for the EPT pointer, thereby establishing a different EPT

2.2.5 Security and Cryptography Technologies

2.2.5.1 Intel® Advanced Encryption Standard New Instructions (Intel® AES-NI)

The processor supports Advanced Encryption Standard New Instructions (Intel®AES-NI) that are a set of Single Instruction Multiple Data (SIMD) instructions that enable fast and secure data encryption and decryption based on the Advanced Encryption Standard (AES). Intel® AES-NI are valuable for a wide range of cryptographic applications, for example:

- applications that perform bulk encryption/decryption
- authentication, random number generation
- authenticated encryption

AES is broadly accepted as the standard for both government and industry applications, and is widely deployed in various protocols. Intel® AES-NI consists of six Intel® SSE instructions.

Four instructions facilitate high performance AES encryption and decryption:

- AESENC
- AESENCLAST
- AESDEC
- AESDELAST

The other two, support the AES key expansion procedure.

- AESIMC
- AESKEYGENASSIST

Together, these instructions provide a full hardware AES support, offering security, high performance, and a great deal of flexibility.

2.2.5.2 Intel® Secure Hash Algorithm Extensions (Intel® SHA Extensions)

The Secure Hash Algorithm (SHA) is one of the most commonly employed cryptographic algorithms. Primary usages of SHA include data integrity, message authentication, digital signatures, and data de-duplication. As the pervasive use of security solutions continues to grow, SHA can be seen in more applications now than ever. The Intel® SHA Extensions are designed to improve the performance of these compute-intensive algorithms on Intel® architecture-based processors.

The Intel® SHA Extensions are a family of seven instructions based on the Intel® Streaming SIMD Extensions (Intel® SSE) that are used together to accelerate the performance of processing SHA-1 and SHA-256 on Intel architecture-based processors.

- **SHA1RNDS4**—Perform Four Rounds of SHA1 Operation
- **SHA1NEXTE**—Calculate SHA1 State Variable E after Four Rounds
- **SHA1MSG1**—Perform an Intermediate Calculation for the Next Four SHA1 Message Dwords
- **SHA1MSG2**—Perform a Final Calculation for the Next Four SHA1 Message Dwords
- **SHA256RNDS2**—Perform Two Rounds of SHA256 Operation
- **SHA256MSG1**—Perform an Intermediate Calculation for the Next Four SHA256 Message Dwords
- **SHA256MSG2**—Perform a Final Calculation for the Next Four SHA256 Message Dwords

A processor supports Intel® SHA Extensions if CPUID.(EAX=07H, ECX=0):EBX.SHA [bit 29] = 1. The Intel® SHA Extensions require only Intel® XMM™ Technology state support on operating systems, similar to SSE2 instructions.

Details of the seven instructions are in a PDF file *Intel® Architecture Instruction Set Extensions Programming Reference* available here: https://software.intel.com/en-us/isa-extensions.

2.2.5.3 PCLMULQDQ Instruction

The processor supports the carry-less multiplication instruction, PCLMULQDQ. PCLMULQDQ is a Single Instruction Multiple Data (SIMD) instruction that computes:

- The 128-bit carry-less multiplication of two 64-bit operands without generating Propagating carries

Carry-less multiplication is an essential processing component of several cryptographic systems and standards. Accelerating carry-less multiplication significantly contributes to achieving high-speed secure computing and communication.

2.2.5.4 Digital Random Number Generator

The processor introduces a software visible digital random number generation mechanism supported by a high-quality entropy source. This capability is available to programmers through the RDRAND and RDSEED instructions. The instruction is described as RDRAND—Read Random Number in Volume 2 of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

Some uses of the RDRAND instruction include cryptographic key generation as used in a variety of applications including communication, digital signatures, secure storage, etc.

2.2.6 Intel® Turbo Boost Technology

Intel® Turbo Boost Technology is available on some of the SoC product SKUs. Refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

Intel® Turbo Boost Technology is a feature that allows the processor to opportunistically and automatically run faster than its rated operating core and/or render clock frequency when there is sufficient power headroom, and the product is within specified temperature and current limits.

The Intel® Turbo Boost Technology feature increases performance of both multi-threaded and single-threaded workloads. The processor supports a turbo mode where the processor uses the thermal capacity associated with the package and core current being drawn to determine the higher core frequencies/power levels resulting in exceeding the SoCs TDP power for short durations.

For the processor to operate with maximum performance, the turbo feature needs to be properly enabled by the BIOS and the platform must have the correct implementation of SVID IMON. Since the turbo feature is configurable and dependent on many platform design limits outside of the processor control, the maximum performance cannot be guaranteed.

Turbo mode availability is independent of the number of active cores; however, the turbo mode frequency is dynamic and dependent on the instantaneous application power load, the number of active cores, user configurable settings, operating environment, and system design.

2.2.6.1 Intel® Turbo Boost Technology Frequency

The processor-rated frequency assumes that all execution cores are active and are at the sustained Thermal Design Power (TDP). However, under a typical operation not all cores are active or executing a high-power workload. Most applications are consuming less than the TDP at the rated frequency. Intel Turbo Boost Technology takes advantage of the available TDP headroom and active cores are able to increase their operating frequency. To determine the highest performance frequency amongst active cores, the processor takes the following into consideration to recalculate turbo frequency during runtime:

- Number of cores operating in the C0 state
- Estimated core current consumption
- Estimated package prior and present power consumption
- Package temperature

Any of these factors affect the maximum frequency for a given workload. If the power, current, or thermal limit is reached, the processor automatically reduces the frequency to stay within its TDP limit. Turbo processor frequencies are only active if the operating system is requesting the P0 state Section 34.10, "Performance States".

2.2.7 CPUID Instruction

The CPU Identification (CPUID) instruction returns processor identification and feature information to the EAX, EBX, ECX, and EDX registers, as determined by input entered in EAX (and in some cases, ECX as well).

Details of the instruction can be found in the Instruction Set Reference portion of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

When CPUID executes with EAX set to 01h, the SoC version information is returned in EAX. See Figure 2-2, "Version Information Returned by CPUID in EAX".

Figure 2-2. Version Information Returned by CPUID in EAX



Note: Once the SoC product is launched, the *Intel® 64 and IA-32 Architectures Software Developer's Manual* will refer to the SoC as having "DisplayFamily_DisplayModel" as 06_5FH.

Leaves 0 through 15h provides Basic CPUID Information.

Leaves 80000000h through 80000008h provide Extended CPUID Information.

Table 2-1, "CPUID Leaf 0h" through Table 2-21, "Extended CPUID Leaf 80000008h" contain descriptions of the leaves and sub-leaves.

2.2.7.1 CPUID Leaf 0 — Basic CPUID Information

Table 2-1. CPUID Leaf 0h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
0	n/a	EAX	[31:0]	Maximum CPUID input value in EAX that is recognized by the SoC for its Basic CPUID Information.	Normally 0x15. *See bit 22 (BOOT_NT4) of MSR 1A0h, IA32_MISC_ENABLE.*	Leaf 15h is the final leaf for SoC Basic CPUID Features
		EBX	[31:0]	Intel identification, ASCII encoded "uneG"	0x756E6547	"Genu"
		ECX	[31:0]	Intel identification, ASCII encoded "letn"	0x6C65746E	"ntel"
		EDX	[31:0]	Intel identification, ASCII encoded "Ieni"	0x49656E69	"ineI"

2.2.7.2 CPUID Leaf 1 — Version and Feature Information

Table 2-2. CPUID Leaf 1h, Output EAX and EBX

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
1	n/a	EAX	[3:0]	Stepping ID	Varies by product release	A0 Stepping = 0 A1 Stepping = 0 B0 Stepping = 1
			[7:4]	Model	0xF	0xF
			[11:8]	Family ID	6	6
			[13:12]	Processor Type	0	Original OEM Processor
			[15:14]	(Reserved)	0	
			[19:16]	Extended Model ID	5	5
			[27:20]	Extended Family ID	0	
		EBX	[7:0]	Brand Index	0	Brand String Method used rather than Brand Index Method
			[15:8]	CLFLUSH line size	8	64 bytes
			[23:16]	Maximum number of addressable IDs for logical processors in this package	0x20	32 IDs Max
			[31:24]	APIC ID assigned during power up	Varies	

Table 2-3. CPUID Leaf 1h, Output ECX (Sheet 1 of 2)

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
1	n/a	ECX	0	**SSE3** - Intel® Streaming SIMD Extensions 3 (Intel® SSE3)	1	Supported
			1	**PCLMULDQ** - PCLMULDQ instruction	1	Supported
			2	**DTES64** - 64-bit DS Area	1	Supported
			3	**MONITOR/MWAIT** feature supported	Varies	Depends on value of bit 18 in IA_MISC_ENABLE (MSR 1A0h)
			4	**DS_CPL** - CPL Qualified Debug Store	1	Supported
			5	**VMX** - Virtual Machine Extensions	1	Supported
			6	**SMX** - Safer Mode Extensions	0	Not Supported
			7	**EIST** - Intel Enhanced SpeedStep® Technology	1	Supported
			8	**TM2** - Intel® Thermal Monitor 2	1	Supported
			9	**SSSE3** - Supplemental Streaming SIMD Extensions 3	1	Supported
			10	**CNXT-ID** - L1 Context ID	0	Not Supported
			11	**Privacy MSR**	1	Supported
			12	**FMA** - **Intel®** Fast Memory Access (**Intel®** FMA) extensions using YMM state	0	Not Supported
			13	**CMPXCHG16B/CX16** - Compare and Exchange Bytes features	1	Supported
			14	**xTPR Update Control** - Allow changing bit 23 of IA32_MISC_ENABLE (MSR 1A0h)	1	Supported
			15	**PDCM** - PerfMon and Debug Capability, altering IA32_PERF_CAPABILITIES (MSR 345h)	1	Supported
			16	(Reserved)	0	
			17	**PCID** - Process-Context Identifiers	0	Not Supported
			18	**DCA** - Ability to prefetch data from memory-mapped device	0	Not Supported
			19	**SSE4.1** - Intel® Streaming SIMD Extensions 4.1	1	Supported
			20	**SSE4.2** - Intel® Streaming SIMD Extensions 4.2	1	Supported
			21	**x2APIC** - Extended Interrupt Mode	1	Supported
			22	**MOVBE** - MOVBE instruction	1	Supported
			23	**POPCNT** - POPCNT instruction	1	Supported
			24	**TSC-Deadline**	1	Supported
			25	**AESNI** - AESNI instruction	1	Supported
			26	**XSAVE** - XSAVE/XRSTOR extended states, XSETBV/XGETBV instructions, and XCRO	1	Supported

Table 2-3. CPUID Leaf 1h, Output ECX (Sheet 2 of 2)

1	n/a	ECX	27	**OSXSAVE** - A value of 1 indicates the OS has set CR4.OSXSAVE	Varies	
			28	**AVX** - AVX instruction extensions.	0	Not Supported
			29	**F16C/IVBNI** - 16-bit floating-point conversion instructions	0	Not Supported
			30	**RDRAND** - RDRAND instruction	1	Supported
			31	(Reserved)	0	

Table 2-4. CPUID Leaf 1h, Output EDX (Sheet 1 of 2)

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
1	n/a	EDX	0	**FPU** - Floating Point Unit on Chip	1	Supported
			1	**VME** - Virtual 8086 Mode Enhancements	1	Supported
			2	**DE** - Debugging Extensions	1	Supported
			3	**PSE** - Page Size Extension	1	Supported
			4	**TSC** - Time Stamp Counter	1	Supported
			5	**MSR** - Model Specific Registers RDMSR & WRMSR Instructions	1	Supported
			6	**PAE** - Physical Address Extension	1	Supported
			7	**MCE** - Machine Check Exception	1	Supported
			8	**CX8** - CMPXCHG8B Instruction	1	Supported
			9	**APIC** - APIC On-Chip	Varies	1 if bit 11 of IA32_APIC_BASE (MSR 1Bh) is set
			10	(Reserved)	0	
			11	**SEP** - SYSTENTER & SYSEXIT Instructions	1	Supported
			12	**MTRR** - Memory Type Range Registers	1	Supported
			13	**PGE** - Page Global Bit	1	Supported
			14	**MCA** - Machine Check Architecture	1	Supported
			15	**CMOV** - Conditional Move Instruction	1	Supported
			16	**PAT** - Page Attribute Table	1	Supported
			17	**PSE-36** - 36-bit Page Size Extension	1	Supported. Physical addresses may be up to 39 bits
			18	**PSN** - Processor Serial Number	0	Not Supported
			19	**CLFSH** - CLFLUSH Instruction	1	Supported
			20	(Reserved)	0	
			21	**DS** - Debug Store	1	Supported
			22	**ACPI** - Software Controlled Clock Facilities	1	Supported
			23	**MMX** - Intel MMX™ technology	1	Supported

Table 2-4. CPUID Leaf 1h, Output EDX (Sheet 2 of 2)

1	n/a	EDX	24	**FXSR** - FXSAVE and FXRSTOR Instructions	1	Supported
			25	**SSE** - Intel® Streaming SIMD Extensions	1	Supported
			26	**SSE2** - Intel® Streaming SIMD Extensions 2	1	Supported
			27	**SS** - Self Snoop	1	Supported
			28	**HTT** - Max APIC IDs reserved field is Valid. See CPUID, Leaf 1, EBX[23:16]	1	Supported
			29	**TM** - Intel® Thermal Monitor	1	Supported
			30	(Reserved)	0	
			31	**PBE** - Pending Break-Enable	1	Supported

2.2.7.3 CPUID Leaf 2 — Cache and TLB Information

Table 2-5. CPUID Leaf 2h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
2	n/a	EAX	[7:0]	Loop value - Number of times CPUID leaf 2 must be executed to retrieve complete information about caches and TLBs.	0x01	One time
			[15:8]	Micro Translation Lookaside Buffer (uTLB) Descriptor	0xA0	4K pages, fully associative, 32 entries
			[23:16]	Data Translation Lookaside Buffer (DTLB) Descriptor	0x64	4K pages, 4-way, 512 entries
			[30:24]	Instruction Translation Lookaside Buffer (ITLB) Descriptor	0x61	4K pages, fully associative, 48 entries
			[31]	Valid bit	0	Bits [30:0] are valid
		EBX	[7:0]	Large-Page DTLB Descriptor	0xC2	2M and 4M pages, 4-way, 16 entries
			[15:8]	General	0xFF	CPUID leaf 2 does not report cache descriptor information. Use CPUID leaf 4 instead
			[31:16]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.4 CPUID Leaf 3— Reserved

The 96-bit processor serial number is not supported. For CPUID with EAX = 3, the results in EAX, EBX, ECX and EDS are reserved and zeros are returned.

2.2.7.5 CPUID Leaf 4— Deterministic Cache Parameters

CPUID leaf 4 has three sub-leaves.

Table 2-6. CPUID Leaf 4h (Sheet 1 of 2)

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
4	0	EAX	[4:0]	Cache Type	0x1	Data Cache
			[7:5]	Cache Level	0x1	Level 1 (L1)
			8	Self Initializing Cache?	1	Yes
			9	Fully Associative?	0	No
			[13:10]	(Reserved)	0	
			[25:14]	Max number of addressable IDs for logical processors sharing this cache	0	Max number is 1
			[31:26]	Max number of addressable IDs for processor cores in the SoC physical package (minus 1)	0xF	Max number is 16
		EBX	[11:0]	System Coherency Line Size (minus 1)	0x3F	64
			[21:12]	Physical Line Partitions	0	1 partition
			[31:22]	Ways (minus 1)	5	6 Ways
		ECX	[31:0]	Sets (minus 1)	0x3F	64 Sets
		EDX	0	Write-back Invalidate/Invalidate	1	WBINVD/INVD is not guaranteed to act upon lower level caches of non-originating threads sharing this cache.
			1	Cache Inclusiveness	0	Cache is not inclusive of lower cache levels
			2	Complex Cache Indexing	1	Complex Cache Indexing supported
			[31:3]	(Reserved)	0	
	1	EAX	[4:0]	Cache Type	0x2	Instruction Cache
			[7:5]	Cache Level	0x1	Level 1 (L1)
			8	Self Initializing Cache?	1	Yes
			9	Fully Associative?	0	No
			[13:10]	(Reserved)	0	
			[25:14]	Max number of addressable IDs for logical processors sharing this cache	0	Max number is 1
			[31:26]	Max number of addressable IDs for processor cores in the SoC physical package (minus 1)	0xF	Max number is 16
		EBX	[11:0]	System Coherency Line Size (minus 1)	0x3F	64
			[21:12]	Physical Line Partitions	0	1 partition
			[31:22]	Ways (minus 1)	7	8 Ways
		ECX	[31:0]	Sets (minus 1)	0x3F	64 Sets

Table 2-6. CPUID Leaf 4h (Sheet 2 of 2)

4	1	EDX	0	Write-back Invalidate/Invalidate	1	WBINVD/INVD is not guaranteed to act upon lower level caches of non-originating threads sharing this cache.
			1	Cache Inclusiveness	0	Cache is not inclusive of lower cache levels
			2	Complex Cache Indexing	1	Complex Cache Indexing supported
			[31:3]	(Reserved)	0	
	2	EAX	[4:0]	Cache Type	0x3	Unified Cache
			[7:5]	Cache Level	0x2	Level 2 (L2)
			8	Self Initializing Cache?	1	Yes
			9	Fully Associative?	0	No
			[13:10]	(Reserved)	0	
			[25:14]	Maximum number of addressable IDs for logical processors sharing this cache (minus 1)	0x3	Max number is 4
			[31:26]	Maximum number of addressable IDs for processor cores in the SoC physical package (minus 1)	0xF	Max number is 16
		EBX	[11:0]	System Coherency Line Size (minus 1)	0x3F	64
			[21:12]	Physical Line Partitions	0	1 partition
			[31:22]	Ways	0xF	16 Ways
		ECX	[31:0]	Sets (minus 1)	0x7FF	2048 Sets
		EDX	0	Write-back Invalidate/Invalidate	1	WBINVD/INVD is not guaranteed to act upon lower level caches of non-originating threads sharing this cache.
			1	Cache Inclusiveness	0	Cache is not inclusive of lower cache levels
			2	Complex Cache Indexing	0	Direct mapped cache
			[31:3]	(Reserved)	0	
	3+	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.6 CPUID Leaf 5— MONITOR/MWAIT

Except for EDX[31:0], values shown in Table 2-7, "CPUID Leaf 5h" are valid only when MONITOR/MWAIT instructions are enabled.

Table 2-7. CPUID Leaf 5h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
5	n/a	EAX	[15:0]	Smallest monitor-line size in bytes	0x40 this can vary depending on filter size	64 bytes or the filter size, whichever is smaller
			[31:16]	(Reserved)	0	
		EBX	[15:0]	Largest monitor-line size in bytes	0x40 this can vary depending on filter size	64 bytes or the filter size, whichever is smaller
			[31:16]	(Reserved)	0	
		ECX	0	Enumeration of MONITOR-WAIT extensions	1	Supported
			1	Supports treating interrupts as break-event for MWAIT, even when interrupts disabled	1	Supported
			[31:2]	(Reserved)	0	
		EDX	[3:0]	Number of MWAIT C0 sub-states supported	0	0
			[7:4]	Number of MWAIT C1 sub-states supported	2	2
			[11:8]	Number of MWAIT C2 sub-states supported	0	0
			[15:12]	Number of MWAIT C3 sub-states supported	2	2
			[19:16]	Number of MWAIT C4 sub-states supported	4	4
			[23:20]	Number of MWAIT C5 sub-states supported	2	2
			[27:24]	Number of MWAIT C6 sub-states supported	0	0
			[31:28]	Number of MWAIT C7 sub-states supported	0	0

2.2.7.7 CPUID Leaf 6— Digital Thermometer and Power Management

Table 2-8. CPUID Leaf 6h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
6	n/a	EAX	0	Digital Thermal Sensor (DTS) support	1	Supported
			1	Intel® Turbo Boost Technology	0 or 1	Support varies by product SKU. BIOS can also disable this technology
			2	**ARAT -** APIC-Timer-always-running feature	1	Supported
			3	(Reserved)	0	
			4	**PLN** - Power limit notification controls support	0	Not Supported
			5	**ECMD** - Clock modulation duty cycle extension support	0	Not Supported
			6	**PTM** - Package thermal management support	0	Not Supported
			[31:7]	(Reserved)	0	
		EBX	[3:0]	Number of Interrupt Thresholds in Digital Thermal Sensor (DTS)	2	2 thresholds
			[31:4]	(Reserved)	0	
		ECX	0	Hardware Coordination Feedback Capability	1	Supported. IA32_MPERF (MSR E7h) and IA32_APERF (MSR E8h) are present
			[2:1]	(Reserved)	0	
			3	Performance-Energy BIAS Preference support	0	Not Supported IA32_ENERGY_PERFORMANCE_BIAS (MSR 1B0h) is not available
			[31:4]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.8 CPUID Leaf 7— Extended feature Flags

The output shown in Table 2-9, "CPUID Leaf 7h" depends on the ECX input value.

Table 2-9. CPUID Leaf 7h (Sheet 1 of 2)

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
7	0	EAX	[31:0]	Maximum supported sub-leaf for CPUID leaf 7	0	Only sub-leaf 0
		EBX	0	**FSGSBASE** - Support for RDFSBASE/RDGSBASE/WRFSBASE /WRGSBASE	1	Supported
			1	Support for IA32_TSC_ADJUST (MSR 3Bh)	1	Supported
			2	**SGX** - Support for Secure Enclaves (SE) and Intel® Software Guard Extensions (Intel® SGX)	0	Not Supported
			3	**BMI1** - Bit Manipulation Set 1	0	Not Supported
			4	**HLE**	0	Not Supported
			5	**AVX2** - Intel® Advanced Vector Extensions 2 (Intel® AVX2)	0	Not Supported
			6	(Reserved)	0	
			7	**SMEP** - Supervisor-Mode Execution Prevention	1	Supported
			8	**BMI2** - Bit Manipulation Set 2	0	Not Supported
			9	**ERMS** - Support for Enhanced REP MOV/STOSB	1	Supported
			10	**INVPCID** - Support for INVPCID instruction	0	Not Supported
			11	**RTM** - HLE+/RTM	0	Not Supported
			12	Support for Platform Quality of Service Monitoring (PQM) capability	0	Not Supported
			13	FPU CS and FPU DS Deprecation	1	The processor depreciates FPU CS and FPU DS values and these fields are 0000h
			14	Intel® Memory Protection Extensions (Intel® MPX)	1	Supported
			15	Support for Platform Quality of Service Enforcement (PQE)	1	Supported
			16	**AVX512F** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512) Foundation instructions)	0	Not Supported
			17	**AVX512DQ** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			18	**RDSEED** - Read Random SEED instruction	1	Supported
			19	(Reserved)	0	
			20	**SMAP** - Supervisory Mode Access Protection and the LAC/STAC instructions	1	Supported

Table 2-9. CPUID Leaf 7h (Sheet 2 of 2)

7	0	EBX	21	**AVX512IFMA** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			22	**PCOMMIT** - Persistent Commit instruction	0	Not Supported
			23	**CLFLUSHOPT** - Flush a Cache Line Optimized instruction	1	Supported
			24	(Reserved)	0	
			25	Intel® Processor Trace (Intel® PT)	1	Supported
			26	**AVX512PF** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			27	**AVX512ER** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			28	**AVX512CD** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			29	**SHA** - Intel® Secure Hash Algorithm Extensions (Intel® SHA Extensions)	1	Supported
			30	**AVX512BW** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			31	**AVX512VL** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
		ECX	0	**PREFETCHWT1** - PREFETCHWT1 instruction	0	Not Supported
			1	**AVX512VBMI** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Not Supported
			[31:2]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
7	1+	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.9 CPUID Leaf 8 — Reserved

CPUID leaf 8 is not supported and is reserved. Zeros are returned.

2.2.7.10 CPUID Leaf 9 — Direct Cache Access (DCA) Information

CPUID leaf 9 is not supported and is reserved. Zeros are returned.

2.2.7.11 CPUID Leaf Ah — Architectural Performance Monitoring

Table 2-10. CPUID Leaf Ah

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
A	n/a	EAX	[7:0]	Version ID of architectural performance monitoring	4	Version 4
			[15:8]	Number of general-purpose, performance monitoring counters per logical processor	4	4 counters
			[23:16]	Bit width of general-purpose, performance monitoring counter	0x30	48 bits
			[31:24]	Length of EBX bit vector to enumerate architectural events	7	7
		EBX	0	Core Cycle event unavailable	0	Core Cycle event is available
			1	Instruction Retired event unavailable	0	Instruction Retired event is available
			2	Reference Cycles event unavailable	0	Reference Cycles event is available
			3	Last-level cache (L2 Cache) reference event unavailable	0	Last-level cache (L2 Cache) reference event is available
			4	Last-level cache (L2 Cache) misses event unavailable	0	Last-level cache (L2 Cache) misses event is available
			5	Branch instruction retired event unavailable	0	Branch instruction retired event is available
			6	Branch mispredict retired event unavailable	0	Branch mispredict retired event is available
		ECX	[31:0]	(Reserved)	0	
		EDX	[4:0]	Number of fixed-function performance counters (if Version ID > 1)	3	3 counters
			[12:5]	Bit width of fixed-function performance counters (if Version ID > 1)	0x30	48 bits
			[31:13]	(Reserved)	0	

2.2.7.12 CPUID Leaf Bh — Extended Topology Enumeration

CPUID leaf Bh has two sub-leaves.

Table 2-11. CPUID Leaf Bh

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
B	0	EAX	[4:0]	Number of bits to shift right on x2APIC ID (EDX[31:0]) to get a unique topology ID of the next level type	1	Shift right 1 bit
			[31:5]	(Reserved)	0	
		EBX	[15:0]	Number of logical processors at this level type. The number reflects configuration as shipped by Intel	1	1 logical processor
			[31:16]	(Reserved)	0	
		ECX	[7:0]	Level Number - Same value as ECX input	0	Level 0
			[15:8]	Level Type	1	SMT level
			[31:16]	(Reserved)	0	
		EDX	[31:0]	x2APIC ID the current logical processor	Varies	
	1	EAX	[4:0]	Number of bits to shift right on x2APIC ID (EDX[31:0]) to get a unique topology ID of the next level type	5	Shift right 5 bits
			[31:5]	(Reserved)	0	
		EBX	[15:0]	Number of logical processors at this level type. The number reflects configuration as shipped by Intel	2, 4, 8, 0xB, or 0x10	2, 4, 8, 12, or 16 depending on product SKU
			[31:16]	(Reserved)	0	
		ECX	[7:0]	Level Number - Same value as ECX input	1	Level 1
			[15:8]	Level Type	2	Core level
			[31:16]	(Reserved)	-	0
		EDX	[31:0]	x2APIC ID the current logical processor	Varies	
	2+	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	Original ECX	2+	
		EDX	[31:0]	(Reserved)	0	

2.2.7.13 CPUID Leaf Ch — Reserved

CPUID leaf Ch is not supported and is reserved. Zeros are returned.

2.2.7.14 CPUID Leaf Dh — Intel® Memory Protection Extensions (Intel® MPX), XSAVE Feature

CPUID leaf Dh has six sub-leaves (0 through 4, and 8) and is shown in Table 2-12, "CPUID Leaf Dh". The other sub-leaves are reserved.

Table 2-12. CPUID Leaf Dh (Sheet 1 of 2)

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
D	0	EAX	0	**X87 State** - Legacy Floating Point (x87/MMX)	1	Legacy FP state can be managed by XSAVE
			1	**SSE State** - Intel® Streaming SIMD Extensions (Intel® SSE)	1	Intel® SSE state can be managed by XSAVE
			2	**AVX State** - Advanced Vector Extensions (Intel® AVX)	0	Intel® AVX state cannot be managed by XSAVE
			3	**BNDREGS State** - Intel® Memory Protection Extensions (Intel® MPX) BNDREGS	1	Intel® MPX Bound Registers (BNDREGS) can be managed by XSAVE
			4	**BNDCSR State** - Intel® Memory Protection Extensions (Intel® MPX) BNDCSR	1	Intel® MPX Bound Control and Status Register (BNDCSR) can be managed by XSAVE
			[7:5]	**AVX-512 State** - Intel® Advanced Vector Extensions 512 (Intel® AVX-512)	0	Intel® AVX-512 not supported and cannot can be managed by XSAVE
			8	**PT State** - Intel® Processor Trace (Intel® PT), used for IA32_XSS (MSR DA0h)	0	Intel® PT MSRs state cannot can be managed by XSAVE
			9	**PKRU State** - Protection-key feature's register PKRU	0	PKRU state cannot can be managed by XSAVE
			[31:10]	(Reserved)	0	
		EBX	[31:0]	Maximum size required for features enabled in XCR0	0x240	576 bytes
		ECX	[31:0]	Max size required by all processor supported features	0x440	1088 bytes
		EDX	[31:0]	(Reserved)	0	
	1	EAX	0	Availability of XSAVEOPT	1	Available
			1	Support of XSAVEC and compact extensions of legacy XSTROR	1	Supported
			2	Support of XGETBV Leaf 1	1	Supported
			3	Support of XSAVES and XRSTORS instructions, and IA32_XSS (MSR DA0h)	1	Supported
			[31:4]	(Reserved)	0	
		EBX	[31:0]	Maximum size required for features enabled in XCR0 | IA32_XSS (MSR DA0h)	0x240	576 bytes
		ECX	[7:0]	(Reserved)	0	
			8	**PT State** - Intel® Processor Trace (Intel® PT)	1	Corresponding bit in IA32_XSS (MSR DA0h) can be set
			[31:9]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

Table 2-12. CPUID Leaf Dh (Sheet 2 of 2)

D	2	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
	3	EAX	[31:0]	Intel® Memory Protection Extensions (Intel® MPX) - Size of feature state-save area	0x40	64 bytes
		EBX	[31:0]	Intel® MPX - Offset of feature state-save area	0x3C0	960 bytes
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
	4	EAX	[31:0]	Intel® MPX - Size of feature state-save area	0x40	64 bytes
		EBX	[31:0]	Intel® MPX - Offset of feature state-save area	0x400	1024 bytes
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
	8	EAX	[31:0]	Intel® Processor Trace (Intel® PT) - Size of Intel® PT state-save area	0x80	128 bytes
		EBX	[31:0]	(Reserved)	0	
		ECX	0	Intel® PT - Supervisor State	1	Intel® PT is supported in IA32_XSS (MSR DA0h)
			[31:1]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
	All other values of ECX	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.15 CPUID Leaf Eh — Reserved

CPUID leaf Eh is not supported and is reserved. Zeros are returned.

2.2.7.16 CPUID Leaf Fh — Platform and Cache Quality of Service (QoS)

CPUID leaf Fh, Platform QoS Monitoring Enumeration and Cache QoS Monitoring Capability, is not supported and is reserved. Zeros are returned.

2.2.7.17 CPUID Leaf 10h — Platform and Cache QoS Enforcement Enumeration

CPUID leaf 10h contains three sub-leaves and is show in Table 2-13, "CPUID Leaf 10h".

Table 2-13. CPUID Leaf 10h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
10	0	EAX	[31:0]	(Reserved)	0	
		EBX	0	(Reserved)	0	
			1	L3 Cache	0	SoC has no L3 Cache
			2	L2 Cache	1	Supports L2 Cache QoS Enforcement
			[31:3]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
	1	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	
	2	EAX	[4:0]	Length of Masks (minus 1)	7	8
			[31:5]	(Reserved)	0	
		EBX	[31:0]	Bitmask	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[15:0]	Highest COS number supported for this ResID (minus 1)	3	4 is highest number
			[31:16]	(Reserved)	0	
	3+	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.18 CPUID Leaf 11h — Reserved

CPUID leaf 11h is not supported and is reserved. Zeros are returned.

2.2.7.19 CPUID Leaf 12h — Reserved

CPUID leaf 12h is not supported and is reserved. Zeros are returned.

2.2.7.20 CPUID Leaf 13h — Reserved

CPUID leaf 13h is not supported and is reserved. Zeros are returned.

2.2.7.21 CPUID Leaf 14h — Intel® Processor Trace (Intel® PT) Enumeration

CPUID leaf 14h has two sub-leaves and is shown in Table 2-14, "CPUID Leaf 14h".

Table 2-14. CPUID Leaf 14h (Sheet 1 of 2)

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
14	0	EAX	[31:0]	Maximum valid sub-leaf	1	Only sub-leaves 0 and 1 are valid
		EBX	0	CR3 Filtering Support	1	IA32_RTIT_CTL (MSR 570h) can be set to 1, and that IA32_RTIT_CR3_MATCH (MSR 572h) can be accessed
			1	Support for Cycle-Accurate Mode and Configurable PSB	1	Supported
			2	Support for IP filtering, TraceStop filtering, and MTC timing packet	1	Supported
			3	Support for Processor Trace MSRs preserved across warm reset	1	Supported
			[31:4]	(Reserved)	0	
		ECX	0	Support of ToPA Output scheme	1	Supported. Tracing can be enabled with the ToPA bit of IA32_RTIT_CTL (MSR 570h)
			1	ToPA Tables Support Multiple Output Regions	1	Supported
			2	Support of Single-Range Output scheme	1	Supported
			3	Support of output to Trace Transport subsystem	0	Not Supported
			[30:2]	(Reserved)	0	
			31	Support of IP payloads contain LIP	1	Generated packets which contain IP payloads contain LIP values, which include the CS base component
		EDX	[31:0]	(Reserved)	0	
	1	EAX	[1:0]	Number of configurable Address Ranges for filtering supported	2	2 ranges
			[15:2]	(Reserved)	0	
			[31:16]	Bitmap of supported MTC Period encodings	0x249	0x249
		EBX	[15:0]	Bitmap of supported Cycle Threshold Value encodings	0xFFFF	0xFFFF
			[31:16]	Bitmap of supported configurable PSB Frequency encodings	0x003F	0x003F
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

Table 2-14. CPUID Leaf 14h (Sheet 2 of 2)

14	2+	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.22 CPUID Leaf 15h — Time Stamp Counter (TSC) and Crystal Clock Ratio

CPUID leaf 15h is the last Basic CPUID leaf.

Table 2-15. Basic CPUID Leaf 15h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
15	n/a	EAX	[31:0]	Denominator of TSC/crystal clock ratio	3	3
		EBX	[31:0]	Numerator of TSC/crystal clock ratio	0xC0	192
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.23 CPUID Leaves 16h through 7FFFFFFFh — Reserved

CPUID leaves 16h through 7FFFFFFFh are not supported and are reserved. Each of these leaves produces the same EAX, EBX, ECX, and EDS values as leaf 15h.

CPUID leaves greater than 80000000h are also reserved and produce the same EAX, EBX, ECX, and EDS values as leaf 15h.

2.2.7.24 CPUID Leaf 80000000h — Maximum EAX Value for CPUID Instruction

Table 2-16. Extended CPUID Leaf 80000000h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
80000000	n/a	EAX	[31:0]	Maximum input value in EAX for Extended Function CPUID information	0x80000008	0x80000008 is the maximum value
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

2.2.7.25 CPUID Leaf 80000001h — Extended Feature Flags

Table 2-17. Extended CPUID Leaf 80000001h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
80000001	n/a	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	0	Availability of LAHF and SAHF instructions in 64-bit mode	1	Available
			5	Availability of LZCNT instruction	0	Not Available
			[7:1]	(Reserved)	0	
			8	Availability of PREFETCHW instruction	1	Available
			[31:9]	(Reserved)	0	
		EDX	[10:0]	(Reserved)	0	
			11	Availability of SYSCALL and SYSTRET instructions in 64-bit mode	1	Available
			[19:12]	(Reserved)	0	
			20	Availability of the Execute Disable Bit	Varies	1 indicates Available. Will be 1 whenever the NX_DISABLE bit of IA32_CR_MISC_ENABLES (MSR 1A0h) = 0
			[25:21]	(Reserved)	0	
			26	1GB Pages	1	Enabled
			27	RDTSCP/IA32_TSC_AUX	1	1
			28	(Reserved)	0	
			29	Availability of Intel® 64 Architecture	1	Available
			[31:30]	(Reserved)	0	

2.2.7.26 CPUID Leaves 80000002h, 80000003h, and 80000004h— Intel Processor Brand String

Table 2-18. Extended CPUID Leaves 80000002h, 80000003h, and 80000004h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
80000002	n/a	EAX	[31:0]	Processor Brand String	65746E49	
		EBX	[31:0]		2952286C	
		ECX	[31:0]		6F744120	
		EDX	[31:0]		4D54286D	
80000003	n/a	EAX	[31:0]		50432029	
		EBX	[31:0]		33432055	
		ECX	[31:0]		20383538	
		EDX	[31:0]		2E322040	
80000004	n/a	EAX	[31:0]		48473030	
		EBX	[31:0]		7A	
		ECX	[31:0]		0	
		EDX	[31:0]		0	

2.2.7.27 CPUID Leaf 80000005h — Reserved

CPUID leaf 80000005h is not supported and is reserved. Zeros are returned.

2.2.7.28 CPUID Leaf 80000006h — Cache Parameters

Table 2-19. Extended CPUID Leaf 80000006h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
80000006	n/a	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[7:0]	Cache Line Size	0x40	64
			[15:12]	Associativity field	0x8	8
			[31:16]	Cache size in 1k units	0x800	2048 1k units (2MB)
		EDX	[31:0]	(Reserved)	0	

2.2.7.29 CPUID Leaf 80000007h — Advanced Power Management

Table 2-20. Extended CPUID Leaf 80000007h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
80000007	n/a	EAX	[31:0]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[7:0]	(Reserved)	0	
			8	Always Running TSC	1	Available
			[31:9]	(Reserved)	0	

2.2.7.30 CPUID Leaf 80000008h — Virtual/Physical Address Sizes

Table 2-21. Extended CPUID Leaf 80000008h

Leaf [EAX] (Hex)	Sub-leaf [ECX] (Hex)	CPUID Results	Bits	Meaning	Returned Value	What Value Indicates
80000008	n/a	EAX	[7:0]	Number of Physical Address Bits	0x27	39 bits
			[15:8]	Number of Linear Address Bits	0x30	48 bits
			[31:16]	(Reserved)	0	
		EBX	[31:0]	(Reserved)	0	
		ECX	[31:0]	(Reserved)	0	
		EDX	[31:0]	(Reserved)	0	

§ §

3 System Address Map

In addition to the Intel Atom® cores, the SoC contains two other units, the Innovation Engine (IE) and Intel® Management Engine (ME), that execute the Intel® architecture instruction set. Each has its own Memory Space, I/O Space and PCI domain. This document refers to these three units as:

- Host Root Space - Associated with the Intel Atom® cores
- IE Root Space - Associated with the IE instruction-execution unit
- Intel® ME Root Space - Associated with the Intel® ME instruction-execution unit

This Chapter describes the Host Root Space, which includes the Configuration Space, Memory Space, and I/O Space of the SoC. Information is provided to show Memory Address Space configuration and how to access Sideband Registers and Configuration Space.

Model-Specific Registers (MSRs) are accessed by executing Read MSR (RDMSR) and Write MSR (WRMSR) instructions. CPU Identification Registers are accessed via CPUID instruction.

3.1 Host Root Space—Memory Space

The Memory Space address map for the Host Root Space is shown in Table 3-1, "Host Memory Space Address Map". The Memory-Mapped I/O (MMIO) that is relocatable in Host Memory Space is shown in Table 3-2, "Relocatable MMIO in Host Memory Space".

The SoC implements 40 address bits providing 1,024 GB of addressable Host Root Memory Space for use by the CPU and devices. This is the address space accessible by memory reads and writes. These addresses are generated by the processor and also by integrated and external I/O devices. The target of the read and write transactions can be system memory or integrated memory and external I/O devices. For PCI compliance the devices and SoC internal circuitry provide a full 64-bit address space. Even so, addresses greater than 1,024 GB (40 address bits) never address a physical resource in the SoC, and are always terminated with an error.

Note: The ultimate subtractive-decode agent in Host Root Space is the Primary-to-Sideband Bridge (P2SB) and not the Low Pin Count (LPC) controller. Any transaction reaching the P2SB which does not match a valid mapped region is terminated. Such transactions are either dropped for Posted Requests or result in an Unsupported Request (UR) for Non-Posted Requests.

3.1.1 Host Memory Space—Regions and Boundaries

Table 3-1. Host Memory Space Address Map (Sheet 1 of 3)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
DOS DRAM (0 to 1 MB)			
DRAM [640 KB]	0000_0000	0009_FFFF	DOS_DRAM
VGA (A Segment and B Segment) [128 KB]	000A_0000	000B_FFFF	A and B segments' VGA region of memory must be configured before first access and may target one and only one of these: • PCIe Root Port which has VGAE (bit 3) of its Bridge Control Register (BCTL) is set. • Legacy Block • DRAM in SBFT mode when ABSEGINDRAM (bit 2) of the B_CR_BMISC_0_0_0_MCHBAR register is set. ***Note:*** The SoC does not support SMM in the A and B segments of memory (the VGA region).
DRAM (C Segment and D Segment) [128 KB]	000C_0000	000D_FFFF	The SoC does not support ISA Expansion region. This area always maps to system DRAM. Access is from the CPU only, no inbound access support—an inbound access will be aborted.
Extended System BIOS (E Segment) [64 KB]	000E_0000	000E_FFFF	Reads and Writes to E segment are to DRAM. ***Note:*** The SoC does not support reading from the BIOS boot interface via the E segment. Access from CPU only, no inbound access support.

Table 3-1. Host Memory Space Address Map (Sheet 2 of 3)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
System BIOS (Upper) (F segment) [64 KB]	000F_0000	000F_FFFF	Reads and Writes to F segment are to DRAM. ***Note:*** The SoC does not support reading from the BIOS boot interface via the F segment. Access from CPU only, no inbound access support.
Lower DRAM Window (1 MB to TOLUD minus 1)			
DRAM [1 MB]	00F0_0000	0100_0000	The SoC does not support ISA hole. This range is always mapped to DRAM.
TSEG	B-unit System Management Mode Memory Base (TSEGMB_0_0_0_PCI)	BGSM_0_0_0_PCI minus 1	TSEG is locked by BIOS by setting the appropriate levels in TSEGMB_0_0_0_PCI and BGSM_0_0_0_PCI.
BGSM	B-unit Graphics Stolen Memory Base (BGSM_0_0_0_PCI)	TOLUD minus 1	For the SoC, the BGSM_0_0_0_PCI range is not applicable. Even so, BGSM_0_0_0_PCI must be programmed since it affects TSEG.
Low MMIO (TOLUD to 4 GB)			
ABORT	FEB0_0000	FEBF_FFFF	CRAB Abort page region
IOxAPIC	FEC0_0000	FEC0_0040	IOxAPIC space. Within FECx_x000 to FECx_x040, BIOS configures the window using APIC Range Select (IOAC.ASEL) and APIC Enable (IOAC.AEN). The IOAC register is in the P2SB Bridge device. ***Note:*** Intel only validates the range FEC0_0000 to FEC0_0040.
HPET	FED0_0000	FED0_03FF	High performance event timer. Although FED0_0000 through FED0_33FF are configurable, only FED0_0000 through FED0_03FF is expected.
TPM	FED4_0000	FED4_0FFF	TPM1.2 range
xHCI DbC	FED6_0000	FED6_0FFF	The OS must be informed that this address range is reserved. No other MMIO must overlap range.
Local APIC	FEE0_0000	FEEF_FFFF	APIC space used to send MSIs to the CPU and INTR ACKs to legacy block.
BIOS4 - Feature space for LPC	FF00_0000	FF0F_FFFF	BDE.0
	FF10_0000	FF1F_FFFF	BDE.1
	FF20_0000	FF2F_FFFF	BDE.2
	FF30_0000	FF3F_FFFF	BDE.3
BIOS4 - Data space for SPI and LPC	FF40_0000	FF4F_FFFF	BDE.0
	FF50_0000	FF5F_FFFF	BDE.1
	FF60_0000	FF6F_FFFF	BDE.2
	FF70_0000	FF7F_FFFF	BDE.3

Table 3-1. Host Memory Space Address Map (Sheet 3 of 3)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
Low MMIO (TOLUD to 4 GB) (continued)			
BIOS3 - Feature space for LPC	FF80_0000	FF87_FFFF	BDE.8
	FF88_0000	FF8F_FFFF	BDE.9
	FF90_0000	FF97_FFFF	BDE.10
	FF98_0000	FF9F_FFFF	BDE.11
	FFA0_0000	FFA7_FFFF	BDE.12
	FFA8_0000	FFAF_FFFF	BDE.13
	FFB0_0000	FFB7_FFFF	BDE.14
BIOS3 - Feature space for LPC	FFB8_0000	FFBF_FFFF	BDE.15; always enabled
BIOS3 - Data space for SPI and LPC	FFC0_0000	FFC7_FFFF	BDE.8
	FFC8_0000	FFCF_FFFF	BDE.9
	FFD0_0000	FFD7_FFFF	BDE.10
	FFD8_0000	FFDF_FFFF	BDE.11
	FFE0_0000	FFE7_FFFF	BDE.12
	FFE8_0000	FFEF_FFFF	BDE.13
	FFF0_0000	FFF7_FFFF	BDE.14
BIOS2 - Data space for SPI and LPC	FFF8_0000	FFFB_FFFF	BDE.15; always enabled
BIOS - Data space for SPI and LPC	FFFC_0000	FFFF_FFFF	This BIOS region is enabled by default and can not be disabled. Reset boot vector is FFFF_FFF0.
ECAM Base Address	PCIEXBAR_LO_0_0_0_PCI and PCIEXBAR_HI_0_0_0_PCI	PCIEXBAR plus 256 MB in 32-bit address space	PCI Express Enhanced Configuration Access Mechanism (ECAM) location. PCI and PCIe Configuration Space accessible as memory-mapped accesses.
Protected Memory (Low) for VT-d	PLMBASE_VTDBAR	PLMLIMIT_VTDBAR	Area of protected memory located <4GB for VT-d.
4 GB to TOUUD-1 -- High DRAM Window			
High DRAM	1_0000_0000	TOUUD-1	High Main Memory. Top of Upper Usable DRAM.
TOUUD to 1024 GB -- High MMIO			
High MMIO	TOUUD	1024 GB	High MMIO for 64-bit MMIO
Protected Memory (High) for VT-d	PHMBASE_VTDBAR	PHMLIMIT_VTDBAR	Area of protected memory located >4GB for VT-d.

3.1.2 Host Memory Space—Relocatable Memory-Mapped I/O

Table 3-2, "Relocatable MMIO in Host Memory Space" lists the Memory-Mapped I/O that is relocatable in Host Memory Space. The I/O listed as being in 32-bit address space can be configured within the "Low MMIO" region shown in Table 3-1, "Host Memory Space Address Map". The I/O listed as being in 64-bit address space can be configured within the "High MMIO or Low MMIO" region of the same table.

Table 3-2. Relocatable MMIO in Host Memory Space (Sheet 1 of 5)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
Dedicated Integrated Root Port for Intel® QuickAssist Technology	D6:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D6:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
Intel® QuickAssist Technology	Bus x:D0:F0 PSECRAMUBAR PSECRAMLBAR	512 KB in 64-bit address space	Intel® QuickAssist Technology, PF Memory Base Address Register
PCI Express RP[0] *Root Port Cluster 0, Root Port 0*	D9:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D9:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D9:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
PCI Express RP[1] *Root Port Cluster 0, Root Port 1*	D10:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D10:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D10:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
PCI Express RP[2] *Root Port Cluster 0, Root Port 2*	D11:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D11:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D11:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.

Table 3-2. Relocatable MMIO in Host Memory Space (Sheet 2 of 5)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
PCI Express RP[3] *Root Port Cluster 0, Root Port 3*	D12:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D12:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D12:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
PCI Express RP[4] *Root Port Cluster 1, Root Port 0*	D14:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D14:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D14:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
PCI Express RP[5] *Root Port Cluster 1, Root Port 1*	D15:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D15:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D15:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
PCI Express RP[6] *Root Port Cluster 1, Root Port 2*	D16:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D16:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D16:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.

Table 3-2. Relocatable MMIO in Host Memory Space (Sheet 3 of 5)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
PCI Express RP[7] *Root Port Cluster 1, Root Port 3*	D17:F0 EXPPTMBAR (BAR1,BAR0)	128 KB in 64-bit address space	As defined by the Base Address Register 0 (BAR0) and Base Address Register 1 (BAR1) in the Function Configuration Space.
	D17:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D17:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
SMBus 2.0 Controller - Host	D18:F0 SMTBAR (BAR1,BAR0)	1 KB in 64-bit address space	SMBus 2.0 Controller (Host)
SATA Controller 0	D19:F0 ABAR (BAR5)	2 KB in 32-bit address space	AHCI Base Address for SATA 3.1 Controller 0
SATA Controller 1	D20:F0 ABAR (BAR5)	2 KB in 32-bit address space	AHCI Base Address for SATA 3.1 Controller 1
USB Combo Controller	D21:F0 MBAR (BAR1,BAR0)	64 KB in 64-bit address space	USB3/USB2 combo controller
Dedicated Integrated Root Port for LAN Controller 0	D22:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D22:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.
LAN Controller 0	Bus y:D0:Fn (BAR1, BAR0)	128 KB in 64-bit address space	LAN port controller, independent per function
	Bus y:D0:Fn BAR2	32B in 64-bit address space	LAN port controller, independent per function
	Bus y:D0:Fn (BAR5, BAR4)	16 KB in 64-bit address space	LAN port MSI-X, independent per function
Dedicated Integrated Root Port for LAN Controller 1	D23:F0 MEMBASE MEMLIMIT	variable length in 32-bit address space	As defined by the Memory Base register and Memory Limit register in the Function Configuration Space.
	D23:F0 PFBASEU PFBASE and PFLIMITU PFLIMIT	variable length in 64-bit address space	As defined by the Prefetchable Memory Base register (Upper and Lower) and Prefetchable Memory Limit register (Upper and Lower) in the Function Configuration Space. The two Upper registers are for 64-bit addressing.

Table 3-2. Relocatable MMIO in Host Memory Space (Sheet 4 of 5)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
LAN Controller 1	Bus z:D0:Fn (BAR1, BAR0)	128 KB in 64-bit address space	LAN port controller, independent per function
	Bus z:D0:Fn BAR2	32B in 64-bit address space	LAN port controller, independent per function
	Bus z:D0:Fn (BAR5, BAR4)	16 KB in 64-bit address space	LAN port MSI-X, independent per function
Intel® ME HECI 1	D24:F0 HECI1_MMIO_MBAR	4 KB in 64-bit address space	
Intel® ME HECI 2	D24:F1 HECI2_MMIO_MBAR	4 KB in 64-bit address space	
Intel® ME KT	D24:F3 KT_HOST_MEMBAR	4 KB in 32-bit address space	Intel® ME Keyboard and Text (KT) Redirection
Intel® ME HECI 3	D24:F4 HECI3_MMIO_MBAR	4 KB in 64-bit address space	
HS-UART Controller 0	D26:F0 MEMBA	256 Bytes in 32-bit address space	HS-UART
HS-UART Controller 1	D26:F1 MEMBA	256 Bytes in 32-bit address space	HS-UART
HS-UART Controller 2	D26:F2 MEMBA	256 Bytes in 32-bit address space	HS-UART
IE HECI 1	D27:F0 HECI1_MMIO_MBAR	4 KB in 64-bit address space	
IE HECI 2	D27:F1 HECI2_MMIO_MBAR	4 KB in 64-bit address space	
IE KT	D27:F3 KT_HOST_MEMBAR	4 KB in 32-bit address space	IE Keyboard and Text (KT) Redirection
IE HECI 3	D27:F4 HECI1_MMIO_MBAR	4 KB in 64-bit address space	
eMMC	D28:F0 BAR_HIGH, BAR	4 KB in 64-bit address space	
LPC	D31:F0 LGMR	64 KB in 32-bit address space	LPC memory space
Proxy (P2SB)	D31:F1 SBREG_BAR	16 MB in 64-bit address space	P2SB register aperture

Table 3-2. Relocatable MMIO in Host Memory Space (Sheet 5 of 5)

Memory Address Range Name [Size]	Start Address or Base Address (Hexadecimal)	End Address or Range (Hexadecimal)	Dependency/Comments
PMC	D31:F2 PBASE	512 B in 32-bit address space	PMC memory space
SMBus 2.0 Controller - Legacy	D31:F4 SMBMBAR	256B in 64-bit space as configured in PSF address space	SMBus 2.0 Controller (Legacy). Used for SPD interface to memory modules.
SPI Controller	D31:F5 BIOS_SPI_BAR0	4KB in 32-bit address space	SPI memory space

3.2 Host Root Space—I/O Space

The SoC implements 64 kilobytes plus three (65,539 decimal) bytes of I/O Space addressing. For I/O instructions that access the highest-addressed ports (FFFDh - FFFFh), there are situations where the three bytes beyond the 64-KB boundary are accessed. There are no resources for these highest-addressed three bytes.

For example, a four-byte read of I/O address FFFEh results in reading two data bytes within the 64-KB boundary and two data bytes beyond the 64-KB boundary. The latter two data bytes have no resources and must be ignored.

The location of the I/O Port register being written to, or read from, via an I/O instruction (IN, INS, OUT, OUTS) is calculated by the SoC. The register can be physically located within the SoC, LPC device, SPI device, or on a PCI Express* device connected to one of the integrated Root Ports.

The primary subtractive-decode agent in Host Root Space is the Primary-to-Sideband Bridge (P2SB) and not the Low Pin Count (LPC) controller. Any transaction reaching the P2SB which does not match a valid mapped region is terminated. Such transactions are either dropped for Posted Requests or result in an Unsupported Request (UR) for Non-Posted Requests.

Warning: Each SoC PCIe* integrated Root Port can be configured by the Operating System (OS) and BIOS to claim a portion of I/O space addresses. When an I/O instruction accesses an I/O Port within this claimed portion, the transaction is routed to the devices on the particular Root Port. The OS and BIOS must ensure that the integrated PCIe Root Ports' claimed portions of I/O space are configured to not overlap the addresses of the I/O Port registers, mostly legacy device registers, located within the SoC.

The fixed-address I/O Port registers are in Table 3-3, "Host Fixed I/O Address Space".

The relocatable (BARs) I/O Port registers are in Table 3-4, "Host Relocatable I/O Address Space".

3.2.1 Host I/O Space—Fixed I/O Addresses

See Table 3-3, "Host Fixed I/O Address Space". The SoC calculates the physical location of an I/O Port register based on a number of conditions. The fixed-address ranges are either positively decoded in the System Agent or subtractively routed to the Primary to Sideband Bridge (P2SB).

In Table 3-3, "Host Fixed I/O Address Space":

- For address ranges listed as having NEG (negative) address decode, an I/O instruction is routed to the device listed in the table. This happens only if there is no enabled device with a BAR that instead captures the I/O address. If there is no BAR that captures the transaction, then the target device of the NEG decode must be enabled.
  - If the target device of the NEG decode is disabled, transactions to the address range are terminated.
- When an address range is listed as having a POS (positive) address decode and the address range is enabled, the I/O transaction is routed to a relocatable BAR. See Table 3-4, "Host Relocatable I/O Address Space". The target device responding to the I/O address can be integrated within or downstream of one of the PCIe Root Ports if the address is within the Root Port's I/O Base and Limit registers.
  - If the target device is disabled, transactions to the address range are terminated.
  - If the POS address range is disabled, the transaction is routed to the LPC controller.
- For address ranges listed as having Fabric address decode, the destination of the I/O transaction is determined by registers and configuration settings of the SoC. Falling into this category are COM1/COM2 I/O address which can be assigned to HSUART and the VGA Enabled (BCTL.VGAE=1) of the Root Ports. Here, if a positive decode of the I/O address is made, the I/O transaction is routed to the appropriate destination.

Table 3-3. Host Fixed I/O Address Space (Sheet 1 of 4)

Address (hex)	Address Decode	Targets	Register Control
00 - 1F	NEG	Transaction is terminated	
20 - 21	NEG	8259 PIC	
24 - 25	NEG	8259 PIC	
28 - 29	NEG	8259 PIC	
2C - 2D	NEG	8259 PIC	
2E - 2F	NEG	LPC	
30 - 31	NEG	8259 PIC	
34 - 35	NEG	8259 PIC	
38 - 39	NEG	8259 PIC	
3C - 3D	NEG	8259 PIC	
40	NEG	8254 Timer	
41	NEG	Transaction is terminated	
42 - 43	NEG	8254 Timer	
4E - 4F	NEG	LPC	
50	NEG	8254 Timer	
51	NEG	Transaction is terminated	
52 - 53	NEG	8254 Timer	
60	NEG	PS/2 Legacy Keyboard/Mouse	
61	NEG	NMI Controller	
62	NEG	LPC	
63	NEG	NMI Controller	
64	NEG	PS/2 Legacy Keyboard/Mouse	
65	NEG	NMI Controller	
66	NEG	LPC	
67	NEG	NMI Controller	
70	NEG	CPU Interface, RTC, Power Management Controller	
71	NEG	RTC, Power Management Controller	
72 - 73	NEG	RTC, Power Management Controller	
74	NEG	RTC, Power Management Controller	
75	NEG	RTC, Power Management Controller	
76 - 77	NEG	RTC, Power Management Controller	
80	POS	LPC or PCIe Root Port	RCFG.RPRID = 1
81 - 83	NEG	Transaction is terminated	
84 - 86	POS	LPC or PCIe Root Port	RCFG.RPRID = 1
87	NEG	Transaction is terminated	
88	POS	LPC or PCIe Root Port	RCFG.RPRID = 1
89 - 8B	NEG	Transaction is terminated	
8C - 8E	POS	LPC or PCIe Root Port	RCFG.RPRID = 1

Table 3-3. Host Fixed I/O Address Space (Sheet 2 of 4)

Address (hex)	Address Decode	Targets	Register Control
8F	NEG	Transaction is terminated	
90	NEG	LPC	
91	NEG	Transaction is terminated	
92	NEG	P2SB->ITSS (CPU I/F)	
93	NEG	Transaction is terminated	
94 - 96	NEG	LPC	
97	NEG	Transaction is terminated	
98	NEG	LPC	
99 - 9B	NEG	Transaction is terminated	
9C - 9E	NEG	LPC	
9F	NEG	Transaction is terminated	
A0 - A1	NEG	8259 PIC	
A4 - A5	NEG	8259 PIC	
A8 - A9	NEG	8259 PIC	
AC - AD	NEG	8259 PIC	
B0 - B1	NEG	8259 PIC	
B2 - B3	NEG	Power Management - SMI	
B4 - B5	NEG	8259 PIC	
B8 - B9	NEG	8259 PIC	
BC - BD	NEG	8259 PIC	
C0 - DF	NEG	Transaction is terminated	
E0 - FF	NEG	Transaction is terminated	
170 - 177	NEG	Transaction is terminated	
1F0 - 1F7	NEG	Transaction is terminated	
200 - 207	POS	LPC	LPC: IOE.LGE = 1
208 - 20F	POS	LPC	LPC: IOE.HGE = 1
220 - 227	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB
228 - 22F	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB
238 - 23F	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB
278 - 27F	POS	LPC	LPC: IOD.HGE = 1

Table 3-3. Host Fixed I/O Address Space (Sheet 3 of 4)

Address (hex)	Address Decode	Targets	Register Control
2E8 - 2EF	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB ***Note:*** If register is programmed to send to LPC then HSUART will not receive these requests even if programmed to 2E8
	Fabric	HSUART COM4 if programmed by BIOS and locked	
2F8 - 2FF	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB ***Note:*** If register is programmed to send to LPC then HSUART will not receive these requests even if programmed to 2F8
	Fabric	HSUART COM2 if programmed by BIOS and locked	
338 - 33F	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB
370 - 375	POS	LPC	LPC: IOD.FDD IOE.FDE
376	NEG	Transaction is Terminated	
377	POS	LPC	LPC: IOD.FDD IOE.FDE
378 - 37F	POS	LPC	LPC: IOD.LTP IOE.PPE
3B0 - 3B8	Fabric	Routed to the PCIe bridge when BCTL.VGAE is set	
3BC - 3BE	POS	LPC	LPC: IOD.LTP IOE.PPE
3C0 - 3DF	Fabric	Routed to the PCIe bridge when BCTL.VGAE is set	

Table 3-3. Host Fixed I/O Address Space (Sheet 4 of 4)

Address (hex)	Address Decode	Targets	Register Control
3E8 - 3EF	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB ***Note:*** If register is programmed to send to LPC then HSUART will not receive these requests even if programmed to 2E8
	Fabric	HSUART COM3 if programmed by BIOS and locked	
3F0 - 3F5	POS	LPC	LPC: IOD.FDD IOE.FDE
3F6	NEG	Transaction is Terminated	
3F7 - 3F7	POS	LPC	LPC: IOD.FDD IOE.FDE
3F8 - 3FF	POS	LPC	LPC: IOE.CAE IOD.CA or IOE.CBE IOD.CB ***Note:*** If register is programmed to send to LPC then HSUART will not receive these requests even if programmed to 2E8
	Fabric	HSUART COM1 if programmed by BIOS and locked	
4D0 - 4D1 ITSS (Interrupt)	POS	8259 PIC	n/a
678 - 67F	POS	LPC	LPC: IOD.LTP IOE.PPE
778 - 77F	POS	LPC	LPC: IOD.LTP IOE.PPE
7BC - 7BE	POS	LPC	LPC: IOD.LTP IOE.PPE
CF8 *Dword (32-bit) access only*	POS	Access to Configuration Registers	
CF9	POS	Software-Generated Reset	n/a
CFC *Dword (32-bit) access only*	POS	Access to Configuration Registers	

3.2.2 Host I/O Space—Relocatable I/O Addresses

Table 3-4. Host Relocatable I/O Address Space (Sheet 1 of 2)

Device	Base Address (decimal)	Size	Comment
PCI Express Root Port Cluster 0			
Port 0 (RP0)	B0:D9:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port 1 (RP1)	B0:D10:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port 2 (RP2)	B0:D11:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port 3 (RP3)	B0:D12:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
PCI Express Root Port Cluster 1			
Port 0 (RP4)	B0:D14:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port 1 (RP5)	B0:D15:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port 2 (RP6)	B0:D16:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port 3 (RP7)	B0:D17:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
SATA Controller 0			
SATA 0	B0:D19:F0:PCMDBA (BAR0)	8 Bytes	SATA Controller 0 (AHCI base)
	B0:D19:F0:PCTLBA (BAR1)	4 Bytes	SATA Controller 0 (AHCI base)
	B0:D19:F0:SCMDBA (BAR2)	8 Bytes	SATA Controller 0 (AHCI base)
	B0:D19:F0:SCTLBA (BAR3)	4 Bytes	SATA Controller 0 (AHCI base)
	B0:D19:F0:LBAR (BAR4)	32 Bytes	SATA Controller 0 (AHCI base)
SATA Controller 1			
SATA 1	B0:D20:F0:PCMDBA (BAR0)	8 Bytes	SATA Controller 1 (AHCI base)
	B0:D20:F0:PCTLBA (BAR1)	4 Bytes	SATA Controller 1 (AHCI base)
	B0:D20:F0:SCMDBA (BAR2)	8 Bytes	SATA Controller 1 (AHCI base)
	B0:D20:F0:SCTLBA (BAR3)	4 Bytes	SATA Controller 1 (AHCI base)
	B0:D20:F0:LBAR (BAR4)	32 Bytes	SATA Controller 1 (AHCI base)
Dedicated PCI Express Root Ports for LAN0 and LAN1			
Port for LAN0	B0:D22:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
Port for LAN1	B0:D23:F0:IOBASE	Up to IOLIMIT	PCIe Legacy I/O Access
LAN Controllers via Dedicated Root Ports (If in I/O Mode)			
LAN 0	By:D0:Fn:BAR2	32 Bytes	Each Primary Function. Bus number assigned during Enumeration
LAN 1	Bz:D0:Fn:BAR2	32 Bytes	

Table 3-4. Host Relocatable I/O Address Space (Sheet 2 of 2)

Device	Base Address (decimal)	Size	Comment
Intel® ME - IDE Redirector (IDER)			
Intel® ME - IDE Redirector	B0:D24:F2 IDE_HOST_PCMDIOBAR	8 Bytes	IDE Primary Command Block
	B0:D24:F2 IDE_HOST_PCTLIOBAR	4 Bytes	IDE Primary Control Block
	B0:D24:F2 IDE_HOST_SCMDIOBAR	8 Bytes	IDE Secondary Command Block (SoC hardware emulates a permanently disabled secondary IDE device).
	B0:D24:F2 IDE_HOST_SCTLIOBAR	4 Bytes	IDE Secondary Control Block (SoC hardware emulates a permanently disabled secondary IDE device).
	B0:D24:F2 IDE_HOST_BMIOBAR	16 Bytes	IDE Bus Master Block
Intel® ME - Keyboard Text (KT)			
Intel® ME - KT	B0:D24:F3: KT_HOST_IOBAR	8 Bytes	Intel® ME - Keyboard Text
High-Speed UART Controllers (In Legacy Mode)			
UART 0	B0:D26:F0:IOBA	8 Bytes	HSUART
UART 1	B0:D26:F1:IOBA	8 Bytes	HSUART
UART 2	B0:D26:F2:IOBA	8 Bytes	HSUART
Innovation Engine (IE) - IDE Redirector			
IE - IDE Redirector	B0:D27:F2 IDE_HOST_PCMDIOBAR	8 Bytes	IDE Primary Command Block
	B0:D27:F2 IDE_HOST_PCTLIOBAR	4 Bytes	IDE Primary Control Block
	B0:D27:F2 IDE_HOST_SCMDIOBAR	8 Bytes	IDE Secondary Command Block (SoC hardware emulates a permanently disabled secondary IDE device).
	B0:D27:F2 IDE_HOST_SCTLIOBAR	4 Bytes	IIDE Secondary Control Block (SoC hardware emulates a permanently disabled secondary IDE device).
	B0:D27:F2 IDE_HOST_BMIOBAR	16 Bytes	IDE Bus Master Block
Innovation Engine (IE) - Keyboard Text (KT)			
IE - KT	B0:D27:F3: KT_HOST_IOBAR	8 Bytes	IE - Keyboard Text
LPC Relocatable Generic I/O Space Regions			
LPC	B0:D31:F0:LGIR1	256 Bytes	LPC Generic I/O Range #1
	B0:D31:F0:LGIR2	256 Bytes	LPC Generic I/O Range #2
	B0:D31:F0:LGIR3	256 Bytes	LPC Generic I/O Range #3
	B0:D31:F0:LGIR4	256 Bytes	LPC Generic I/O Range #4

3.3 Host Root Space—PCI Configuration Register Space

Figure 3-1, "Host Root Space - PCI Device Map" shows the PCI map for the Host Root Space. All PCI devices and functions are shown in Table 3-5, "Host PCI Bus, Device, Function Numbers and Device IDs".

Figure 3-1. Host Root Space - PCI Device Map



Table 3-5. Host PCI Bus, Device, Function Numbers and Device IDs (Sheet 1 of 2)

Bus	Device (dec)	Function	Device ID	Description	Comment
0	0	0	0x1980 through 0x199F	System Agent	
0	4	0	0x19A1	GLREG Registers	
0	5	0	0x19A2	Root Complex Event Collector (RCEC)	
0	6	0	0x19A3	Dedicated Root Port for Intel® QAT Device	
0	9	0	0x19A4	PCI Express Cluster 0, Port 0 (RP0)	
0	10	0	0x19A5	PCI Express Cluster 0, Port 1 (RP1)	
0	11	0	0x19A6	PCI Express Cluster 0, Port 2 (RP2)	
0	12	0	0x19A7	PCI Express Cluster 0, Port 3 (RP3)	
0	14	0	0x19A8	PCI Express Cluster 1, Port 0 (RP4)	
0	15	0	0x19A9	PCI Express Cluster 1, Port 1 (RP5)	
0	16	0	0x19AA	PCI Express Cluster 1, Port 2 (RP6)	
0	17	0	0x19AB	PCI Express Cluster 1, Port 3 (RP7)	
0	18	0	0x19AC	SMBus Controller - Host	
0	19	0	0x19B0 through 0x19B7, 0x19BE, 0x19BF	SATA Controller 0	Device IDs 0x19B1 through 0x19B7, 0x19BE, 0x19BF are to be used if the device supports multiple configurations.
0	20	0	0x19C0 through 0x19C7, 0x19CE, 0x19CF	SATA Controller 1	Device IDs 0x19C1 through 0x19C7, 0x19CE, 0x19CF are to be used if the device supports multiple configurations.
0	21	0	0x19D0	USB 2.0/3.0 Combo Controller	
0	22	0	0x19D1	Dedicated Root Port for LAN Controller 0	
0	23	0	0x19D2	Dedicated Root Port for LAN Controller 1	
0	24	0	0x19D3	Intel® ME - HECI 1	
0	24	1	0x19D4	Intel® ME - HECI 2	
0	24	3	0x19D5	Intel® ME - Keyboard and Text (KT) Redirection	
0	24	4	0x19D6	Intel® ME - HECI 3	
0	26	0, 1 and 2	0x19D8	High-Speed UART Controllers	
0	27	0	0x19E5	IE - HECI 1	
0	27	1	0x19E6	IE - HECI 2	
0	27	3	0x19E8	IE - Keyboard and Text (KT) Redirection	
0	27	4	0x19E9	IE - HECI 3	
0	28	0	0x19DB	eMMC	
0	31	0	0x19DC	LPC	
0	31	1	0x19DD	P2SB	

Table 3-5. Host PCI Bus, Device, Function Numbers and Device IDs (Sheet 2 of 2)

Bus	Device (dec)	Function	Device ID	Description	Comment
0	31	2	0x19DE	PMC	
0	31	4	0x19DF	SMBus Controller - Legacy	
0	31	5	0x19E0	SPI Controller	
0	31	7	0x19E1	Intel® Trace Hub	Details are not provided in this document.
x	0	PF: 0 VF: 0 through 15	0x19E2 0x19E2	Intel® QAT - attached to a dedicated Root Port	x = Bus Number assigned during enumeration. PF = Primary Function number VF = Virtual Function numbers
y	0	PF: 0 VF: 0 through 63 PF: 1 VF: 0 through 63	*see comment*	LAN Controller 0 *attached to a dedicated Root Port*	y, z = Bus Number assigned during enumeration. PF = Primary Function number VF = Virtual Function numbers Device ID: See Table 13-15, "Link Modes"
z	0	PF: 0 VF: 0 through 63 PF: 1 VF: 0 through 63	*see comment*	LAN Controller 1 *attached to a dedicated Root Port*	

3.3.1 How to Access Registers in PCI Configuration Space

Access to the PCI configuration space registers is performed through one of two Configuration Access Methods (CAMs):

- I/O indexed - PCI compatible Configuration Access Mechanism (CAM)
- Memory mapped - PCI Express Enhanced Configuration Access Mechanism (ECAM)

CAM provides access to the first 256 bytes of the configuration registers for each of the 65,536 possible Functions in a system. It involves performing a DWORD I/O instruction to I/O address CF8h (CONFIG_ADDRESS) followed by another DWORD I/O instruction to I/O address CFCh (CONFIG_DATA). Bit 31 of CF8h must be set to a 1 for a Configuration Request cycle to be generated. CAM is described in the "Software Generation of Configuration Transactions" section of the *PCI Express Base Specification Revision 3.0*.

Figure 3-2, "DWORD Format of CONFIG_ADDRESS at I/O Address CF8h" shows the format of the DWORD for CF8h.

Figure 3-2. DWORD Format of CONFIG_ADDRESS at I/O Address CF8h



ECAM was introduced with PCI Express* and extends each function's configuration space to 4,096 bytes. The exact implementation details are product specific, and a general description of the ECAM is provided in the "PCI Express Enhanced Configuration Access" section of *PCI Express Base Specification Revision 3.0*.

The SoC implements ECAM through the Host Root Memory Space. There is a 256-MB relocatable region of memory addresses that provides access to all 4,096 bytes of configuration space for all 65,536 possible functions. This region can be located on a 256-MB memory address boundary within the first 4 GB addresses of Host Memory Space. See Table 3-1, "Host Memory Space Address Map". A 32-bit base memory address is defined by the PCIEXBAR_LO_0_0_0_PCI and PCIEXBAR_HI_0_0_0_PCI registers which are located in Configuration Space at offsets 60h and 64h or Bus 0, Device 0, Function 0.

ECAM utilizes a flat memory-mapped address space to access device configuration registers. This address space is reported by the system firmware to the OS. When using ECAM, in order to maintain compatibility with the PCI configuration addressing mechanisms, system software must access the extended configuration space using 32-bit data operations (32-bit aligned) only. These 32-bit operations include byte enables allowing only appropriate bytes within the DWORD to be accessed. Locked transactions to the PCI Express memory-mapped configuration address space are not supported. All changes made using either the CAM or the ECAM are equivalent.

To access Configuration Space via the ECAM:

1. Use the CAM to enable the ECAM by writing 1 to bit 0 of PCIEXBAR_LO_0_0_0_PCI.
2. Use the CAM to write an appropriate ECAM base address into PCIEXBAR (PCIEXBAR_LO_0_0_0_PCI and PCIEXBAR_HI_0_0_0_PCI).
3. Calculate the memory-mapped address of the Configuration Register to be accessed:
   Memory Address =
   PCIEXBAR +
   Bus Number * 1 MB +
   Device Number * 32 KB +
   Function Number * 4 KB +
   Configuration Register Offset
4. Use a memory write or memory read cycle to the calculated memory-mapped address to write or read the PCI Configuration Register.

If the PCI Bus Number is zero, the SoC generates a Type 0 Configuration Request cycle. If the PCI Bus Number is non-zero, the SoC generates a Type 1 Configuration Request cycle.

3.4 Host Root Space - Host Sideband Register Access

3.4.1 Using SBREG_BAR Method

The SBREG_BAR access method is safe for SoC product SKUs that have multiple threads. It is the required method for accessing the Host Sideband registers.

The SoC provides access to its Host Sideband registers through a relocatable, 16-MB area of Host Memory Space. The base address is the 64-bit SBREG_BAR (SBREG_BAR, SBREG_BARH) register located in P2SB Bridge's Host Configuration Space B:0, D:31, F:1, offset 10h and 14h. The access mechanism allows direct mapping to 16 bits of byte-addressable register space for each of the integrated Host Sideband registers.

All accesses to the SBREG_BAR region of Host Memory Space are DWord-aligned DWords.

- Writes larger than one DWord are completed normally, but the write data beyond the first DWord is discarded.
- Reads larger than one DWord result in a Unsupported Request (UR) response.
- Byte enables within the DWord are honored normally, enabling accesses of less than one DWord.

3.4.2 Accessing System Agent Sideband Registers

BIOS needs to access the B_CR_BMISC_0_0_0_MCHBAR (BMISC) Sideband register of the SoC System Agent in order to set certain access boundaries of Host Memory Space.

To access this and other special System Agent registers, the SoC provides a secure, Memory-Mapped I/O (MMIO) aperture at the 64 bit memory address defined by MCHBAR_LO_0_0_0_PCI and MCHBAR_HI_0_0_0_PCI to expose certain, internal registers of the System Agent. The MCHBAR base address registers are defined in Host Configuration Space at Bus 0, Device 0, Function 0, offset 48h and 4Ch. Not all System Agent Registers are accessible in this aperture.

3.5 Key Registers Mentioned in this Chapter

The registers used to configure the system Host Memory-Space map are listed here. This information is provided primarily for BIOS developers.

3.5.1 Key Registers in Host Configuration Space

The registers listed in Table 3-6, "Configuration Registers Used to Configure Host Memory Space" are accessed using the CAM method described previously. Once the PCIEXBAR is set using CAM, these registers are also accessible using ECAM.

Table 3-6. Configuration Registers Used to Configure Host Memory Space (Sheet 1 of 2)

PCI Bus, Device, Function (decimal)	Offset (hex)	Register Short Name	Description
SoC System Agent Registers[1]			
B0,D0,F0	48	MCHBAR_LO_0_0_0_PCI	Memory Controller Hub Base Address Register (MCHBAR). Used for accessing certain Host Sideband Registers
	4C	MCHBAR_HI_0_0_0_PCI	
	54	DEVEN_0_0_0_PCI	Used to enable/hide SoC resources
	60	PCIEXBAR_LO_0_0_0_PCI	PCI Express Enhanced Configuration Access Mechanism (ECAM) location
	64	PCIEXBAR_HI_0_0_0_PCI	
	A8	TOUUD_LO_0_0_0_PCI	Top of Upper Usable DRAM TOUUD
	AC	TOUUD_HI_0_0_0_PCI	
	B0	BDSM_0_0_0_PCI	Base address of the Data Stolen Memory (DSM)
	B4	BGSM_0_0_0_PCI	Base address of the Graphics Stolen Memory (GSM)
	B8	TSEGMB_0_0_0_PCI	Base address of TSEG DRAM memory
	BC	TOLUD_0_0_0_PCI	Top of Lower Usable DRAM (TOLUD) range and start of the Lower MMIO Address range
SPI Controller[2]			
B0,D31,F5	D8	BIOS_SPI_BDE	BIOS Decode Enable (BDE) register when BIOS is resident on SPI.
LPC Controller[3]			
B0,D31,F0	84	LGIR1	LPC Generic I/O Range #1
	88	LGIR2	LPC Generic I/O Range #2
	8C	LGIR3	LPC Generic I/O Range #3
	90	LGIR4	LPC Generic I/O Range #4
	D8	BDE	BIOS Decode Enable (BDE) register when BIOS is resident on the LPC bus.

Table 3-6. Configuration Registers Used to Configure Host Memory Space (Sheet 2 of 2)

PCI Bus, Device, Function (decimal)	Offset (hex)	Register Short Name	Description
Primary to Side Band (P2SB) Bridge and Integrated Error Handler (IEH)			
B0,D31,F1	10	SBREG_BAR	Lower DWORD of the base address for Host Sideband register access.
	14	SBREG_BARH	Upper DWORD of the base address for Host Sideband register access.
	54	RCFG	Routing Configuration
	64	IOAC	IOxAPIC Configuration
PCI Express Integrated Root Port Cluster 0			
B0,D9,F0	3E	BCTL	Bridge Control Register - Root Port 0
B0,D10,F0	3E	BCTL	Bridge Control Register - Root Port 1
B0,D11,F0	3E	BCTL	Bridge Control Register - Root Port 2
B0,D12,F0	3E	BCTL	Bridge Control Register - Root Port 3
PCI Express Integrated Root Port Cluster 1			
B0,D14,F0	3E	BCTL	Bridge Control Register - Root Port 4
B0,D15,F0	3E	BCTL	Bridge Control Register - Root Port 5
B0,D16,F0	3E	BCTL	Bridge Control Register - Root Port 6
B0,D17,F0	3E	BCTL	Bridge Control Register - Root Port 7

1. The System Agent automatically shadows these accesses to certain other SoC registers. These registers must not be accessed by BIOS via sideband.
2. The sampled Boot BIOS Strap (BBS) hard strap determines whether the BIOS Decode Enable is taken from the SPI Controller function B0,D31,F5 or from the LPC function B0,D31,F0.
3. The sampled LPC Decode Select hard strap determines whether the B0,D31,F0 BIOS Decode Enable belongs to the LPC Controller.

3.5.2 Key Registers in Host Memory Space

Table 3-7. Relocatable Host Memory-Mapped Aperture to Access Certain System Agent Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Description
MCHBAR_LO_0_0_0_PCI, MCHBAR_HI_0_0_0_PCI	6800	B_CR_BMISC_0_0_0_MCHBAR	Miscellaneous Configuration Register. BIOS must use MCHBAR to program BMISC.
	6C80	B_CR_DEFVTDBAR_0_0_0_MCHBAR	Default VTd Base Address

3.5.3 Key Registers in Host I/O Space

Table 3-8. Fixed-Address Host I/O-Mapped Registers to Access Configuration Space

I/O Address (hexadecimal)	Register Short Name	Description
CF8	CONFIG_ADDRESS	DWORD containing the Configuration Register address. See Figure 3-2, "DWORD Format of CONFIG_ADDRESS at I/O Address CF8h".
CFC	CONFIG_DATA	DWORD containing the Configuration Register data.

§ §

4 Strapping and Configuration

This chapter describes how to configure the SoC through the use of hard and soft straps and provides descriptions on what the different strapping options do. This chapter will cover two kinds of strapping configurations: hard straps or pin straps and soft straps. This chapter will also briefly address in-field programmable fuses pertaining to the Innovation Engine (IE) for more information please refer to Chapter 37, "Innovation Engine."

Strapping is needed to enable, disable, or alter default configurations in the SoC. This chapter will provide the descriptions of these strapping signals, their functionality and the configurations they support. For Soft Straps, please refer to Section 4.2, "SoC Soft Straps" in this chapter.

For this SoC, hard straps are the earliest form of user-defined configuration available in the SoC boot sequence. Hard straps are connected to a physical ball or pin depending on the SoC's package and thus are typically very few in number. Some hard straps, will drive a separate function such as a GPIO from the same SoC ball or pin after the hard strap sampling period, which ends 400 ns after the deassertion of the signal RSMRST_N. If hard straps are not set properly, a user is likely to see unexpected complications while trying to boot the SoC. This includes the possibility of no code being fetched from the boot flash memory device since hard straps are responsible for configuring which boot interface will be used by the SoC. It is recommended that customers take precautions and allow themselves the flexibility to easily configure hard straps in their designs through the use of jumpers or other means when first starting a design and are still performing their design validation with the SoC. This allows customers to easily reconfigure hard straps and avoid potentially strenuous reworks to their design. A customer can choose to remove these jumpers or other means for the production version of their design to save on BOM cost. Please refer to Section 4.1, "SoC Hard (Pin) Straps" of this chapter for more information on configuring hard straps.

Soft straps are the second earliest form of user-defined configuration available in the SoC boot sequence and unlike hard straps they are numerous. This SoC has over 2000 soft strap bits which live in the descriptor region of the boot flash memory device. Some soft straps rely on one soft strap bit to configure one setting in the SoC, other soft straps require four or more soft strap bits to configure one setting in the SoC. This chapter will refer to a soft strap as a single or multiple soft strap bits that are required to configure one SoC setting and are listed in Table 4-3, "Flash Descriptor Soft Straps." To be able to load the soft straps into the SoC, it is necessary to read them from the boot flash memory device connected to the SoC which will trigger transactions between the SoC and the device where the soft straps are stored at. i.e. if using a SPI flash memory device to store the soft straps, the user should be able to see and monitor the SPI transactions happening between the SoC and the SPI flash memory device when the SoC is reading the soft straps from the SPI device. Soft straps are required for many of the SoC controllers to come out of reset and as such it is necessary that soft straps are fetched by the SoC in order to continue with the SoC boot sequence. If no soft straps are found by the SoC, the SoC will stop its power on sequence before the signal PMU_SLP_S45_N deasserts. Soft Straps are fetched before the reset vector fetches the first BIOS instruction.

Figure 4-1, "Strap Loading Flow" shows that the strap loading flow starts with the deassertion of the reset signal RSMRST_N, after which the hard straps are sampled followed by the soft straps. The SoC requires that the platform SUSCLK is stable before soft straps are fetched from the boot flash memory device attached to the SoC through the SPI interface. Additionally, the SoC needs to finish reading soft straps before PMU_SLP_S45_N deasserts or the SoC will not progress further in its power on sequence. After PMU_PLTRST_N deasserts, the board follows the boot sequencing flow to the BIOS.

Figure 4-1. Strap Loading Flow



Notes:

1. Hard straps are responsible for configuring which boot interface will be used by the SoC and hence where the SoC will try to read the soft straps from. Please refer to table Table 4-2, "Boot interface Hard Strap/ Pin Strap Configurations" for more information.
2. Platform SUSCLK must be stable before SPI transactions are initiated.
3. Soft Straps live in the descriptor region of the boot memory flash device that can reside over the SPI interface. The SoC needs to finish reading soft straps before the signal PMU_SLP_S45_N deasserts or the SoC will not progress further in its power on sequence.

4.1 SoC Hard (Pin) Straps

Hard straps are configuration signals connected to a physical ball or pin in the SoC depending on the SoC packaging, hence sometimes hard straps are also called pin straps. Since hard straps are connected to a single ball or pin, each hard strap configures a different SoC setting and can only have one of two values: 0 (low) or 1 (high). In order to configure the SoC hard strap to a 1 (high), a pull up is required. In order to configure the SoC hard strap to a 0 (low), a pull down is required. To configure a hard strap pull up (PU) or pull down (PD), a customer can choose to use the SoC internal hard strap default PU/PD or they can force the hard strap with an external PU/PD implemented on the platform.

When configuring hard straps with the SoC internal PU/PD, there is no need to connect the hard strap ball or pin to any termination on the board, it can be left floating. However, there is no way to configure the SoC internal hard strap from a PU to a PD or vice-versa, so the hard strap default will always be either a PU or a PD. See Table 4-1, "SoC Hard Straps/Pin Straps and Descriptions" to check the internal SoC hard strap default PU/PD. When a customer does not require the hard strap setting associated with the default internal SoC PU/PD, an external PU resistor tied to a voltage rail or a PD resistor tied to ground is required to be used on the platform.

When configuring hard straps with an external PU/PD implemented on the board, the internal SoC PU/PD has to be forced to a new state by the external PU/PD. It is recommended that customers take precautions and allow themselves the flexibility to easily configure hard straps in their designs though the use of jumpers or other means when first starting a design and are still performing their design validation with the SoC. This allows to easily reconfigure hard straps and avoid potentially strenuous reworks to the design. These jumpers or other means can be removed for the production version of the design to save on BOM cost.

Each of the hard strap pins is briefly configured as an SoC input during system power on and its state is sampled during the hard strap sampling period which ends 400 ns after the deassertion of the resume reset signal RSMRST_N; the state of the SoC pin or ball is subsequently latched by the SoC hardware. The platform SUSCLK does not need to be stable for hard straps to be sampled.

After the hard strap sampling period, the internal SoC PU/PD associated with the hard straps are removed and if the SoC pin or ball is also a GPIO, then the SoC will drive the GPIO as the alternate function. The GPIO pin should not be driven by an external device during the hard strap sampling period. Customer should take precautions to ensure this does not happen during the SoC power on sequence. If an external PU/PD was used on the hard strap and the pin is used as a GPIO after the hard strap sampling period, then the external PU/PD on the platform will also affect the GPIO signal. For more information on the hard strap pins refer to Table 4-1, "SoC Hard Straps/Pin Straps and Descriptions" for alternate functions refer to Section 39.1, "Directory of Signal Names and Pin Names". For an illustration see Figure 4-2, "Hard Strap Functionality".

Hard straps are responsible for configuring which boot interface will be used by the SoC to read soft straps and fetch BIOS code from. If hard straps are set incorrectly, soft straps will not be fetched and the SoC will not boot. Please refer to Table 4-2, "Boot interface Hard Strap/ Pin Strap Configurations" for more information.

Figure 4-2. Hard Strap Functionality



Note: It is important to ensure that pin straps are always connected to the correct voltage rail when pulled up. Most hard straps are tied to the V3P30 rail Voltage Group, with the exception of "Top Swap Override" Hard Strap which is in GPIO[3] Pin and should be tied to V1P8 Voltage Rail. Also the if the GPIO pin is connected to an external device, that external device should not drive the hard strap for at least the duration of the hard strap sampling period.

In Table 4-1, "SoC Hard Straps/Pin Straps and Descriptions", hard strap pins default to inputs on power up. Their hard strap value is sampled within 400 ns of the rising edge (0 -> 1) of the active-low resume reset signal RSMRST_N. Most hard straps are tied to the V3P30 rail Voltage Group, with the exception of "Top Swap Override" Hard Strap which is tied to pin GPIO[3] and should be tied to V1P8 Voltage Rail.

Table 4-1. SoC Hard Straps/Pin Straps and Descriptions (Sheet 1 of 3)

Hard Strap	Pin Name	SoC Ball Location	Internal PU/PD[1]	Description
Boot BIOS Strap (BBS)	ERROR_N[1]	BR58	20K PD	This Hard Strap tells the SoC from which interface the BIOS code will be fetched • 0 = SPI • 1 = LPC ***Note:*** Please see table Table 4-2, "Boot interface Hard Strap/ Pin Strap Configurations" for information on how to set the Boot BIOS Strap (BBS), LPC Decode Select hard straps properly.
LPC Decode Select	ERROR_N[0]	BL52	20K PD	This Hard Strap tells the SoC to use the LPC interface. • 0 = Low Pin Count (LPC) • 1 = Reserved ***Note:*** The system board must supply a 3.3V voltage to the VCC_LPC_ESPI_3P3_1P8 rail in order for the interface to work. Connecting to the 1.8V rail is not supported. ***Note:*** Please see table Table 4-2, "Boot interface Hard Strap/ Pin Strap Configurations" for information on how to set the Boot BIOS Strap (BBS), LPC Decode Select hard straps properly.
Reserved for Intel	MCERR_N	BN52	20K PD	This Hard Strap must always be set to 0. Either through internal PD or an external PD.
Flash Security Override	IERR_N	BW50	20K PD	• 0 = Flash descriptor security locked (default). The security measures defined in the Flash Descriptor will be in effect. • 1 = Flash descriptor security unlocked ***Notes:*** 1. The internal pull-down is disabled after PLTRST_N deasserts. 2. Asserting Flash Security Override Hard Strap high on the rising edge of PWROK will also halt Intel ME after SoC bring up and disable runtime Intel ME features. This is a debug mode and must not be asserted after manufacturing/debug. 3. This signal is in the Suspend well (V3P30). 4. This hard strap might be named MFG_MODE_STRAP on other IA products.
No TCO Reboot Enable	GPIO[12]	BN56	20K PD	This Hard Strap tells the SoC to enable/disable the Total Cost of Ownership (TCO) watch dog timer (WDT) system reboot feature after the second WDT timeout. • 0 = Default State (the system will reboot after second WDT timeout) • 1 = Stop the TCO watchdog timer from rebooting the system after the second timeout. ***Note:*** More information on TCO see Section 16.6, "Total Cost of Ownership (TCO)".

Table 4-1. SoC Hard Straps/Pin Straps and Descriptions (Sheet 2 of 3)

Hard Strap	Pin Name	SoC Ball Location	Internal PU/PD[1]	Description
Top Swap Override	GPIO[3]	BN44	20K PD	• 0 = Top-swap feature is disabled. • 1 = Top-swap feature is enabled. ***Note:*** For more information on Top-Swap override see Section 56.2.12, "BIOS Control (BC)—Offset DCh" on page 2657.
Forces ME into Recovery Mode	ME_RCVR_N	BE44	20K PU	This signal can be configured via the FITc tool to be on 147 GPIO pins or not available. The default is pin GPIO148. This signal has an internal 20K pull-up to voltage 1.05V with a jumper option to a 1K pull-down resistor on platform. • 0 = Recovery mode • 1 = Normal operating mode for Intel ME. The default for production systems must be normal operating mode. ***Note:*** This signal will immediately put the ME in recovery mode when driven low. By default, driving the signal high will put the ME back in operational mode. A FITc configuration setting can be used to configure the system for legacy mode where operational mode will not be entered until the next reset.
Reserved for Intel	RSVD_BY58	BY58	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	ERROR_N[2]	CA50	20K PD	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	LAN0_PORT0_SDP[3]	BA69	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	LAN0_PORT1_SDP[3]	W58	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	GPIO[0]	BF70	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	GPIO[1]	BK69	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	GPIO[2]	BK71	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.

Table 4-1. SoC Hard Straps/Pin Straps and Descriptions (Sheet 3 of 3)

Hard Strap	Pin Name	SoC Ball Location	Internal PU/PD[1]	Description
Reserved for Intel	SATA0_SDOUT	BU57	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	SMB_LAN_ALRT_N	BN66	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	SUS_STAT_N	BV58	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	FLEX_CLK_SE[0]	BG48	20K PD	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	FLEX_CLK_SE[1]	CA48	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	UART0_TXD	CA52	20K PD	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.
Reserved for Intel	UART1_TXD	BN59	20K PU	This signal has to be sampled in its default "Internal PU/PD" state. Platform cannot drive this signal until > 400ns after RSMRST_N de-asserts.

Notes:
1. The internal PU/PD is only applied during the hard strap sampling period.
2. Strap sampling period is 400 ns after the deassertion of the RSMRST_N signal.

In order for the SoC to properly fetch BIOS code from the flash storage device over the SPI interface the hard strap Reserved for Intel (MCERR_N) has to be tied low (0) even if the LPC Decode Select (ERROR_N[0]) hard strap is tied low (0) which selects the LPC interface.

Please refer to Table 4-2, "Boot interface Hard Strap/ Pin Strap Configurations" for guidance on configuring the SoC boot interface and where the SoC will fetch BIOS code from. Failure to follow the hard strap configurations in the table below may cause the SoC to not come out of reset.

Table 4-2. Boot interface Hard Strap/ Pin Strap Configurations

		Hard Straps	
Boot interface	**LPC Enabled**	**Boot BIOS Strap (ERROR_N[1]) Internal 20K PD**	**LPC Decode Select (ERROR_N[0]) Internal 20K PD**
SPI	**LPC**	0	0
LPC	**LPC**	1	0

4.2 SoC Soft Straps

Soft straps are used to set and configure various features and configurations. Soft strap information is stored within the flash descriptor (region 0) of the Serial Peripheral Interface (SPI) firmware image (which resides on the SPI interface) and removes the need to use pull-up/pull-down resistors to hard strap most SoC features. At boot, the SPI controller reads the soft strap content from the SPI Flash and then distributes it to the various SoC controllers.

Soft Straps are configured utilizing the Intel FITc tool that is provided in the latest Intel® Server Platform Services Firmware Release for Harrisonville Microserver Platforms kit. It is recommended to use the latest version of the tool since that every time the kit is updated, so is the FITc tool.

The SoC provides the ability to use any of the 20 high speed I/O (HSIO) lanes as long as the number of HSIO lanes enabled is lesser than or equal to the number of HSIO lanes allowed on the SKU via fuses. For more information on how this flow works, see Figure 10-3, "Intel® ME-BIOS/UEFI Interactions in a System with Intel® SPS Firmware". HSIO lanes are configured via soft straps and allow the user to select the SoC controller that the HSIO lane will be connected to. If the HSIO lane is configured to either PCIe Gen 3/ SATA Gen 3/ USB3.0 then the HSIO lane will count as being used. However, if it is desired to disable a particular HSIO lane so that the HSIO lane will not count toward the maximum HSIO lane limit imposed by the SKU, then the soft strap configuration setting of "0x2; HSIO Lane not used" must be programed into the HSIO Lane Assignment soft straps. In addition to configuring the SoC FIA via the HSIO Lane Assignment soft straps to select the number of HSIO lanes used and the SoC controllers they connect to, it is also necessary to configure the individual SoC controllers via soft straps to ensure proper SoC behavior. Please follow the following guidance:

- For each HSIO lane assigned to a SATA controller in the HSIO Lane Assignment soft strap section, configure the respective SATA controller to receive the HSIO lane via the HSIO Lane Configuration from SATA Controller section.
- For each HSIO lane assigned to a PCIe root port cluster in the HSIO Lane Assignment soft strap section, configure the respective PCIe root port cluster to support the desired PCIe configuration by configuring settings such as enabling PCIe root ports in the PCIe Bifurcation and Settings section. Once a PCIe root port is disabled via soft strap, it cannot be enabled via BIOS or registers, soft straps take priority.
- For each SoC HSIO controller being used, make sure that it is enabled via the soft straps found in the SoC Feature Disable. Once an SoC controller is disabled via soft strap, it cannot be turned back on unless the soft strap region is updated in the descriptor region of the boot memory flash device and an A/C power cycle is performed on the system.

Some of the SoC soft straps can also be configured without the need to flash the boot flash memory device with a new soft strap configuration in the descriptor region. Instead BIOS is able to request the ME over a HECI message that certain soft straps be reconfigured after a global reset when booting the SoC. For information on how this flow works, please see Figure 10-3, "Intel® ME-BIOS/UEFI Interactions in a System with Intel® SPS Firmware." The soft straps that are able to be dynamically updated by this feature are limited to the following:

- FIA Mux configuration - HSIO Lane Assignment soft straps
- HSIO lane configuration for SATA controllers - HSIO Lane Configuration from SATA Controller soft straps
- PCIe root port cluster configuration (PCIe Bifurcation and Settings) - PCIe* Root Port Cluster [0-1] - "Root Port [0-7] Enable" soft straps
- PCIe root port cluster configuration (PCIe Bifurcation and Settings) - PCIe* Root Port Cluster [0-1] - "Root Port [0-7] x1 Slot Width" soft straps

Note: If no soft straps are found by the SoC, the SoC will stop its power on sequence before PMU_SLP_S45_N deasserts. Soft Straps are fetched before the reset vector fetches the first BIOS instruction.

The Flash Descriptor Soft Straps Table 4-3, "Flash Descriptor Soft Straps" are grouped by SoC features rather than the numerical order of soft straps in the descriptor region of the SPI Flash image.

Table 4-3. Flash Descriptor Soft Straps (Sheet 1 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Power Delivery						
1	+ 4h	15	DRAM VDDQ Voltage Rail - SVID Support	0x0; SVID for VDDQ Disabled 0x1; SVID for VDDQ Enabled	0x1	Tells the SoC if the VDDQ voltage rail supports Serial Voltage Identification (SVID) via SVID_CLK, SVID_DATA and SVID_ALERT pins. If SVID is disabled then the VDDQ rail is static.
2	+ 8h	0	LAN Controller 0 - Powered in S5 Enable	0x0; Not powered in S5 WoL not supported 0x1; Powered in S5 WoL possible	0x1	Tells the SoC that LAN Controller 0 is powered in S5 power state which allows Wake on LAN (WoL) support. **Note:** Setting this strap to "0x0; Not powered in S5; WoL not supported" will cause LAN Controller 0 and 1 to not support WoL regardless of the "LAN Controller 1 Powered in S5 Enable" soft strap setting.
3	+ Ch	0	LAN Controller 1 - Powered in S5 Enable	0x0; Not powered in S5 WoL not supported 0x1; Powered in S5 WoL possible	0x1	Tells the SoC that LAN Controller 1 is powered in S5 power state which allows Wake on LAN support **Note:** LAN Controller 0 Powered in S5 must be set to "Powered in S5; WoL possible" for LAN Controller 1 to function in S5

Table 4-3. Flash Descriptor Soft Straps (Sheet 2 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Power Sequence and Reset - PMC Knobs and Settings						
4	+ 10h	9:8	t573 Timing: COREPWROK to PMU_PLTRST_N Delay	0x0; 100 ms (default) 0x1; 50 ms 0x2; 5 ms 0x3; 1 ms	0x0	Tell the SoC to control timing t573 which is the minimum timing from the assertion of COREPWROK and the de-assertion of the PMU_PLTRST_N signal **Note:** The default setting of 100ms is chosen to be conservative, but the typical preferred setting is expected to be 1ms.
6	+ 18h	11:8	IE FW Launch Time - Out Multiplier	0x0; 8 sec 0x1; 16 sec 0x2; 24 sec 0x3; 32 sec 0x4; 40 sec 0x5; 48 sec 0x6; 56 sec 0x7; 64 sec 0x8; 72 sec 0x9; 80 sec 0xA; 88 sec 0xB; 96 sec 0xC; 104 sec 0xD; 112 sec 0xE; 120 sec 0xF; 128 sec	0x0	Tells the SoC the watch dog timer time before assuming the IE FW is hung on boot and the system needs to be reset. **Note:** Soft Strap "SS6 bit [17] - IE FW Host Boot Preparation Enable" has to be enabled for this strap to have any effect.
6	+ 18h	16	AG3E Boot Select	0x0; System will boot to S0. 0x1; System wait for wake event (S4/S5).	0x1	Tells the SoC to return the system to S0 or S4/S5 power states after power is applied for the first time. Refer to Section 16.10.2, "Initiating State Changes when in the G3 Mechanical-Off State" for additional information about G3 transitions to the S0 and S5 states. **Note:** If the system lost power in S4, then it will return to an S4-like state. In the S5 state, power button or any enabled wake events that were preserved through the power failure are valid wake events and will return the system to S0. See Chapter 16, "Initiating State Changes when in the G3 Mechanical-Off State".
6	+ 18h	17	IE FW Host Boot Preparation Enable	0x0; Do not wait for IE FW 0x1; Wait for IE FW	0x0	Tells the SoC to wait / do not wait for positive indication from IE FW before proceeding with Host boot.
6	+ 18h	29	PMU_RESETBUTTON_N De-bounce	0x0; 16-ms de-bounce 0x1; No de-bounce	0x0	Tells the SoC to de-bounce the PMU_RESETBUTTON_N pin for 16-ms.

Table 4-3. Flash Descriptor Soft Straps (Sheet 3 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
SoC Feature Disable						
5	+ 14h	0	LAN Controller 0 Disable	0x0; LAN Ctrl 0 Enabled 0x1; LAN Ctrl 0 Disabled	0x0	Tells the SoC to disable LAN Controller 0. **Note:** Setting this strap to "LAN Controller 0 Disabled" will cause LAN Controller 1 not to function.
5	+ 14h	1	LAN Controller 1 Disable	0x0; LAN Ctrl 1 Enabled 0x1; LAN Ctrl 1 Disabled	0x0	Tells the SoC to disable LAN Controller 1. **Note**: LAN Controller 0 Disable strap must be set to "LAN Ctrl 0 Enabled" for LAN Controller 1 to function.
5	+ 14h	2	SATA Controller 0 Disable	0x0; SATA Ctrl 0 Enabled 0x1; SATA Ctrl 0 Disabled	0x0	Tells the SoC to disable SATA Controller 0. **Note:** Disabling SATA Controller 0 has no effect on SATA Controller 1 functionality. If set to "SATA Ctrl 0 Disabled" set the soft straps "HSIO Lane 4-11 Select" to a setting that is NOT the "SATA" setting. Also set soft straps "SATA Controller 0 - Assign HSIO Lane 4-11 to Port 0-7" to setting "0x1 - HSIO Lane Not assigned to SATA Controller 0" If the SoC SATA is used then one of the following soft straps must also be set to enabled: SS 5 bit [4] PCIe Root Port Cluster 0 Disable OR SS 5 bit [5] PCIe Root Port Cluster 1 Disable OR SS 5 bit [7] USB Combo Controller Disable AND the requirements in this SATA NOTE must be met.
5	+ 14h	3	SATA Controller 1 Disable	0x0; SATA Ctrl 1 Enabled 0x1; SATA Ctrl 1 Disabled	0x0	Tells the SoC to disable SATA Controller 1. **Note:** Disabling SATA Controller 1 has no effect on SATA Controller 0 functionality. If set to "SATA Ctrl 0 Disabled" set the soft straps "HSIO Lane 12-19 Select" to a setting that is NOT the "SATA" setting. Also set soft straps "SATA Controller 1 - Assign HSIO Lane 12-19 to Port 0-7" to setting "0x1 - HSIO Lane Not assigned to SATA Controller 1" If the SoC SATA is used then one of the following soft straps must also be set to enabled: SS 5 bit [4] PCIe Root Port Cluster 0 Disable OR SS 5 bit [5] PCIe Root Port Cluster 1 Disable OR SS 5 bit [7] USB Combo Controller Disable AND the requirements in this SATA NOTE must be met.

Table 4-3. Flash Descriptor Soft Straps (Sheet 4 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
5	+ 14h	4	PCIe Root Port Cluster 0 Disable	0x0; PCIe Root Port Cluster 0 Enabled 0x1; PCIe Root Port Cluster 0 Disabled	0x0	Tells the SoC to disable PCIe Root Port Cluster 0. **Note:** Disabling PCIe Root Port Cluster 0 has no effect on PCIe Root Port Cluster 1 functionality. If set to "PCIe Root Port Cluster 0 Disabled" set the soft straps "HSIO Lane 4-7 Select" to a setting that is NOT the "PCIe" setting. HSIO Lanes 0-3 will be unusable and should be set to setting "0x2 - HSIO Lane not used" in the soft straps "HSIO Lane 0-3 Select".
5	+ 14h	5	PCIe Root Port Cluster 1 Disable	0x0; PCIe Root Port Cluster 1 Enabled 0x1; PCIe Root Port Cluster 1 Disabled	0x0	Tells the SoC to disable PCIe Root Port Cluster 1. **Note:** Disabling PCIe Root Port Cluster 1 has no effect on PCIe Root Port Cluster 0 functionality. If set to "PCIe Root Port Cluster 1 Disabled" set the soft straps "HSIO Lane 8-15 Select" to a setting that is NOT the "PCIe" setting.
5	+ 14h	6	Intel® QuickAssist Technology Disable	0x0; Intel® QAT Enabled 0x1; Intel® QAT Disabled	0x0	Tells the SoC to disable the Intel® QuickAssist Technology. **Note:** This strap has no effect if your SKU does not support Intel® QuickAssist Technology.
5	+ 14h	7	USB Combo Controller Disable	0x0; USB Combo Controller Enabled 0x1; USB Combo Controller Disabled	0x0	Tells the SoC to disable the USB Combo Controller (USB 2.0 + USB 3.0). **Note:** If set to "USB Combo Controller Disabled" set the soft straps "HSIO Lane 16-19 Select" to a setting that is NOT the "USB 3.0" setting.
5	+ 14h	8	eMMC Controller Disable	0x0; eMMC Enabled 0x1; eMMC Disabled	0x0	Tells the SoC to disable the eMMC (Embedded Multi-Media Card) Controller.
5	+ 14h	17	LAN Controller 0 - Port 1 Disable	0x0; LAN Controller 0 Port 1 Enabled 0x1; LAN Controller 0 Port 1 Disabled	0x0	Tells the SoC to disable Port 1 of LAN Controller 0. **Note**: This assumes that the "LAN Controller 0 Disable" soft strap is set to "LAN Ctrl 0 Enabled".
5	+ 14h	19	LAN Controller 1 - Port 1 Disable	0x0; LAN Controller 1 Port 1 Enabled 0x1; LAN Controller 1 Port 1 Disabled	0x0	Tells the SoC to disable Port 1 of LAN Controller 1. **Note:** Enabling LAN Controller 1 assumes LAN controller 1 is enabled in your SKU and the "LAN Controller 0/1 Disable" soft straps is set to "LAN Ctrl 0/1 Enabled".

Table 4-3. Flash Descriptor Soft Straps (Sheet 5 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
SoC Boot DDR Frequency						
7	+ 1Ch	7:4	SoC Boot DDR Frequency	0x0; Use SoC Fuse Value 0x9; 1866 0xA; 2133 0xB; 2400 **Note:** All other combinations are Reserved	0x0	Limits the speed of the SoC memory controlled during boot. This can be used to avoid SPD reset during MRC training.
BMC and BMC-less Mode Error logging						
5	+ 14h	20	SMB TCO Watch Dog Timer Disable	0x0 -BMC-less Mode: TCO WDT is enabled and any WDT timeout would be escalated to a global reset. If SS7 bit 1 is set to enable, then the error causing the WDT timeout would be logged in SUS_SCRATCH_1 register bit 0. 0x1 -BMC Mode: Prevents TCO WDT from escalating to a global reset due to errors in internal SoC IPs. This allows the BMC to be able to collect error data before global reset. Errors can be fetched from the integrated error handler (IEH).	0x0	Tells the SoC to disable the SMB TCO Watch Dog Timer. **Note:** This SMB TCO WDT is internal to PMC and is intended to be used in conjunction with SS7 bit [1] - "BMC and BMC-less Mode SUS_SCRATCH_1 bit[0] Error logging Enable" soft strap to help capture data should a crash happen under system configurations with or without BMC.
7	+ 1Ch	1	BMC and BMC-less Mode SUS_SCRATCH_1 bit[0] Error logging Enable	0x0 - SUS_SCRATCH_1 bit[0] Error logging Disabled. 0x1 -SUS_SCRATCH_1 bit[0] Error logging Enable.	0x0	When this bit is set, periodically check the status of the IEH and the RCC to check for errors that are impeding a warm reset. If errors are found, then log them into SUS_SCRATCH_1 bit[0].

Table 4-3. Flash Descriptor Soft Straps (Sheet 6 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
High-Speed I/O (HSIO) Configuration						
HSIO Lane Assignment						
21	+ 54h	19:18	HSIO Lane 0 Select	0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [0] and HSIO_TX_D [0] pins are PCIe or not used.
21	+ 54h	21:20	HSIO Lane 1 Select	0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [1] and HSIO_TX_D [1] pins are PCIe or not used.
21	+ 54h	23:22	HSIO Lane 2 Select	0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [2] and HSIO_TX_D [2] pins are PCIe or not used.
21	+ 54h	25:24	HSIO Lane 3 Select	0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [3] and HSIO_TX_D [3] pins are PCIe or not used.
19	+ 4Ch	9:8	HSIO Lane 4 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [4] and HSIO_TX_D [4] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 4 to Port 0" to match this selection.
19	+ 4Ch	11:10	HSIO Lane 5 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [5] and HSIO_TX_D [5] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 5 to Port 1" to match this selection.
19	+ 4Ch	13:12	HSIO Lane 6 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [6] and HSIO_TX_D [6] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 6 to Port 2" to match this selection.
20	+ 50h	1:0	HSIO Lane 7 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [7] and HSIO_TX_D [7] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 7 to Port 3" to match this selection.
20	+ 50h	3:2	HSIO Lane 8 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane is not Used	Board Dependent	Tells the SoC to select if HSIO_RX_D [8] and HSIO_TX_D [8] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 8 to Port 4" to match this selection.

Table 4-3. Flash Descriptor Soft Straps (Sheet 7 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
20	+ 50h	5:4	HSIO Lane 9 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [9] and HSIO_TX_D [9] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 9 to Port 5" to match this selection.
20	+ 50h	7:6	HSIO Lane 10 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [10] and HSIO_TX_D [10] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 10 to Port 6" to match this selection.
20	+ 50h	9:8	HSIO Lane 11 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [11] and HSIO_TX_D [11] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 0 - Assign HSIO Lane 11 to Port 7" to match this selection.
20	+ 50h	11:10	HSIO Lane 12 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [12] and HSIO_TX_D [12] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 12 to Port 0" to match this selection.
20	+ 50h	13:12	HSIO Lane 13 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [13] and HSIO_TX_D [13] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 13 to Port 1" to match this selection.
20	+ 50h	15:14	HSIO Lane 14 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [14] and HSIO_TX_D [14] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 14 to Port 2" to match this selection.
21	+ 54h	17:16	HSIO Lane 15 Select	0x0; SATA 0x1; PCIe 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [15] and HSIO_TX_D [15] pins are SATA, PCIe or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 15 to Port 3" to match this selection.

Table 4-3. Flash Descriptor Soft Straps (Sheet 8 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
20	+ 50h	25:24	HSIO Lane 16 Select	0x0; USB 3.0 0x1; SATA 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [16] and HSIO_TX_D [16] pins are SATA or USB 3.0 or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 16 to Port 4" to match this selection.
20	+ 50h	27:26	HSIO Lane 17 Select	0x0; USB 3.0 0x1; SATA 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [17] and HSIO_TX_D [17] pins are SATA or USB 3.0 or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 17 to Port 5" to match this selection.
20	+ 50h	29:28	HSIO Lane 18 Select	0x0; USB 3.0 0x1; SATA 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [18] and HSIO_TX_D [18] pins are SATA or USB 3.0 or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 18 to Port 6" to match this selection.
20	+ 50h	31:30	HSIO Lane 19 Select	0x0; USB 3.0 0x1; SATA 0x2; HSIO Lane not used	Board Dependent	Tells the SoC to select if HSIO_RX_D [19] and HSIO_TX_D [19] pins are SATA or USB 3.0 or not used. **Note:** Set soft strap "SATA Controller 1 - Assign HSIO Lane 19 to Port 7" to match this selection.

Table 4-3. Flash Descriptor Soft Straps (Sheet 9 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
HSIO Lane Configuration from SATA Controller						
26	+ 68h	1:0	SATA Controller 0 - Assign HSIO Lane 4 to Port 0	0x0; HSIO Lane 4 Statically assigned to SATA Controller 0 Port 0 0x1; HSIO Lane 4 Not assigned to SATA Controller 0 Port 0	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [4] and HSIO_TX_D [4] pins are assigned to Port 0 **Note:** Set the "HSIO Lane 4 Select" soft strap to match this selection
26	+ 68h	3:2	SATA Controller 0 - Assign HSIO Lane 5 to Port 1	0x0; HSIO Lane 5 Statically assigned to SATA Controller 0 Port 1 0x1; HSIO Lane 5 Not assigned to SATA Controller 0 Port 1	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [5] and HSIO_TX_D [5] pins are assigned to Port 1 **Note:** Set the "HSIO Lane 5 Select" soft strap to match this selection
26	+ 68h	5:4	SATA Controller 0 - Assign HSIO Lane 6 to Port 2	0x0; HSIO Lane 6 Statically assigned to SATA Controller 0 Port 2 0x1; HSIO Lane 6 Not assigned to SATA Controller 0 Port 2	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [6] and HSIO_TX_D [6] pins are assigned to Port 2 **Note:** Set the "HSIO Lane 6 Select" soft strap to match this selection
26	+ 68h	7:6	SATA Controller 0 - Assign HSIO Lane 7 to Port 3	0x0; HSIO Lane 7 Statically assigned to SATA Controller 0 Port 3 0x1; HSIO Lane 7 Not assigned to SATA Controller 0 Port 3	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [7] and HSIO_TX_D [7] pins are assigned to Port 3 **Note:** Set the "HSIO Lane 7 Select" soft strap to match this selection
26	+ 68h	9:8	SATA Controller 0 - Assign HSIO Lane 8 to Port 4	0x0; HSIO Lane 8 Statically assigned to SATA Controller 0 Port 4 0x1; HSIO Lane 8 Not assigned to SATA Controller 0 Port 4	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [8] and HSIO_TX_D [8] pins are assigned to Port 4 **Note:** Set the "HSIO Lane 8 Select" soft strap to match this selection
26	+ 68h	11:10	SATA Controller 0 - Assign HSIO Lane 9 to Port 5	0x0; HSIO Lane 9 Statically assigned to SATA Controller 0 Port 5 0x1; HSIO Lane 9 Not assigned to SATA Controller 0 Port 5	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [9] and HSIO_TX_D [9] pins are assigned to Port 5 **Note:** Set the "HSIO Lane 9 Select" soft strap to match this selection
26	+ 68h	13:12	SATA Controller 0 - Assign HSIO Lane 10 to Port 6	0x0; HSIO Lane 10 Statically assigned to SATA Controller 0 Port 6 0x1; HSIO Lane 10 Not assigned to SATA Controller 0 Port 6	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [10] and HSIO_TX_D [10] pins are assigned to Port 6 **Note:** Set the "HSIO Lane 10 Select" soft strap to match this selection
26	+ 68h	15:14	SATA Controller 0 - Assign HSIO Lane 11 to Port 7	0x0; HSIO Lane 11 Statically assigned to SATA Controller 0 Port 7 0x1; HSIO Lane 11 Not assigned to SATA Controller 0 Port 7	Board Dependent	Tells the SoC SATA Controller 0 if HSIO_RX_D [11] and HSIO_TX_D [11] pins are assigned to Port 7 **Note:** Set the "HSIO Lane 11 Select" soft strap to match this selection
27	+ 6Ch	1:0	SATA Controller 1 - Assign HSIO Lane 12 to Port 0	0x0; HSIO Lane 12 Statically assigned to SATA Controller 1 Port 0 0x1; HSIO Lane 12 Not assigned to SATA Controller 1 Port 0	Board Dependent	Tells the SoC's SATA Controller 1 if HSIO_RX_D [12] and HSIO_TX_D [12] pins are assigned to Port 0 **Note:** Set the "HSIO Lane 12 Select" soft strap to match this selection

Table 4-3. Flash Descriptor Soft Straps (Sheet 10 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
27	+ 6Ch	3:2	SATA Controller 1 - Assign HSIO Lane 13 to Port 1	0x0; HSIO Lane 13 Statically assigned to SATA Controller 1 Port 1 0x1; HSIO Lane 13 Not assigned to SATA Controller 1 Port 1	Board Dependent	Tells the SoC's SATA Controller 1 if HSIO_RX_D [13] and HSIO_TX_D [13] pins are assigned to Port 1 **Note:** Set the "HSIO Lane 13 Select" soft strap to match this selection
27	+ 6Ch	5:4	SATA Controller 1 - Assign HSIO Lane 14 to Port 2	0x0; HSIO Lane 14 Statically assigned to SATA Controller 1 Port 2 0x1; HSIO Lane 14 Not assigned to SATA Controller 1 Port 2	Board Dependent	Tells the SoC SATA Controller 1 if HSIO_RX_D [14] and HSIO_TX_D [14] pins are assigned to Port 2 **Note:** Set the "HSIO Lane 14 Select" soft strap to match this selection
27	+ 6Ch	7:6	SATA Controller 1 - Assign HSIO Lane 15 to Port 3	0x0; HSIO Lane 15 Statically assigned to SATA Controller 1 Port 3 0x1; HSIO Lane 15 Not assigned to SATA Controller 1 Port 3	Board Dependent	Tells the SoC SATA Controller 1 if HSIO_RX_D [15] and HSIO_TX_D [15] pins are assigned to Port 3 **Note:** Set the "HSIO Lane 15 Select" soft strap to match this selection
27	+ 6Ch	9:8	SATA Controller 1 - Assign HSIO Lane 16 to Port 4	0x0; HSIO Lane 16 Statically assigned to SATA Controller 1 Port 4 0x1; HSIO Lane 16 Not assigned to SATA Controller 1 Port 4	Board Dependent	Tells the SoC SATA Controller 1 if HSIO_RX_D [16] and HSIO_TX_D [16] pins are assigned to Port 4 **Note:** Set the "HSIO Lane 16 Select" soft strap to match this selection
27	+ 6Ch	11:10	SATA Controller 1 - Assign HSIO Lane 17 to Port 5	0x0; HSIO Lane 17 Statically assigned to SATA Controller 1 Port 5 0x1; HSIO Lane 17 Not assigned to SATA Controller 1 Port 5	Board Dependent	Tells the SoC SATA Controller 1 if HSIO_RX_D [17] and HSIO_TX_D [17] pins are assigned to Port 5 **Note:** Set the "HSIO Lane 17 Select" soft strap to match this selection
27	+ 6Ch	13:12	SATA Controller 1 - Assign HSIO Lane 18 to Port 6	0x0; HSIO Lane 18 Statically assigned to SATA Controller 1 Port 6 0x1; HSIO Lane 18 Not assigned to SATA Controller 1 Port 6	Board Dependent	Tells the SoC SATA Controller 1 if HSIO_RX_D [18] and HSIO_TX_D [18] pins are assigned to Port 6 **Note:** Set the "HSIO Lane 18 Select" soft strap to match this selection
27	+ 6Ch	15:14	SATA Controller 1 - Assign HSIO Lane 19 to Port 7	0x0; HSIO Lane 19 Statically assigned to SATA Controller 1 Port 7 0x1; HSIO Lane 19 Not assigned to SATA Controller 1 Port 7	Board Dependent	Tells the SoC SATA Controller 1 if HSIO_RX_D [19] and HSIO_TX_D [19] pins are assigned to Port 7 **Note:** Set the "HSIO Lane 19 Select" soft strap to match this selection

Table 4-3. Flash Descriptor Soft Straps (Sheet 11 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
PCIe Bifurcation and Settings						
PCIe Root Port Cluster 0						
PCIe RP Cluster 0 - RP Enable						
24	+ 60h	0	PCIe Root Port Cluster 0 - Root Port 0 Enable	0x0; RP0 Disabled 0x1; RP0 Enabled	0x1	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Root Port 0 ***Note:*** If Root port is set to "0x0 - RP0 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.
24	+ 60h	1	PCIe Root Port Cluster 0 - Root Port 1 Enable	0x0; RP1 Disabled 0x1; RP1 Enabled	0x1	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Root Port 1 ***Note:*** If Root port is set to "0x0 - RP1 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.
24	+ 60h	2	PCIe Root Port Cluster 0 - Root Port 2 Enable	0x0; RP2 Disabled 0x1; RP2 Enabled	0x1	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Root Port 2 ***Note:*** If Root port is set to "0x0 - RP2 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.
24	+ 60h	3	PCIe Root Port Cluster 0 - Root Port 3 Enable	0x0; RP3 Disabled 0x1; RP3 Enabled	0x1	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Root Port 3 ***Note:*** If Root port is set to "0x0 - RP3 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.

Table 4-3. Flash Descriptor Soft Straps (Sheet 12 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
						PCIe RP Cluster 0 - RP x1 Link Width Enable
24	+ 60h	27:24	PCIe Root Port Cluster 0 - Root Port 0 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 0 Disable" and "PCIe Root Port Cluster 0 - Root Port 0 Enable" are set to Enable, tell the SoC to set RP 0 link width to x1. **Note:** If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.
24	+ 60h	31:28	PCIe Root Port Cluster 0 - Root Port 1 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 0 Disable" and "PCIe Root Port Cluster 0 - Root Port 1 Enable" are set to Enable, tell the SoC to set RP 1 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.
25	+ 64h	3:0	PCIe Root Port Cluster 0 - Root Port 2 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 0 Disable" and "PCIe Root Port Cluster 0 - Root Port 2 Enable" are set to Enable, tell the SoC to set RP 2 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.
25	+ 64h	7:4	PCIe Root Port Cluster 0 - Root Port 3 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 0 Disable" and "PCIe Root Port Cluster 0 - Root Port 3 Enable" are set to Enable, tell the SoC to set RP 3 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.

Table 4-3. Flash Descriptor Soft Straps (Sheet 13 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
						PCIe RP Cluster 0 - SRIS Enable
25	+ 64h	25	PCIe Root Port Cluster 0 - Root Port 0 SRIS Enable	0x0; RP 0 SRIS Disabled 0x1; RP 0 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 0. SRIS is supported at Gen 1, and 2. **Note:** Refer to the SOSCTL.SRISEN register.
25	+ 64h	26	PCIe Root Port Cluster 0 - Root Port 1 SRIS Enable	0x0; RP 1 SRIS Disabled 0x1; RP 1 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 1. SRIS is supported at Gen 1, and 2. **Note:** Refer to the SOSCTL.SRISEN register.
25	+ 64h	27	PCIe Root Port Cluster 0 - Root Port 2 SRIS Enable	0x0; RP 2 SRIS Disabled 0x1; RP 2 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 2. SRIS is supported at Gen 1, 2and 2 **Note:** Refer to the SOSCTL.SRISEN register.
25	+ 64h	28	PCIe Root Port Cluster 0 - Root Port 3 SRIS Enable	0x0; RP 3 SRIS Disabled 0x1; RP 3 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 0 Disable" is set to "PCIe Root Port Cluster 0 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 3. SRIS is supported at Gen 1, and 2 **Note:** Refer to the SOSCTL.SRISEN register.

Table 4-3. Flash Descriptor Soft Straps (Sheet 14 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
PCIe Root Port Cluster 1						
PCIe RP Cluster 1 - RP Enable						
22	+ 58h	0	PCIe Root Port Cluster 1 - Root Port 4 Enable	**0x0;** RP4 Disabled **0x1;** RP4 Enabled	0x1	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Root Port 4. ***Note:*** If Root port is set to "0x0 - RP4 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.
22	+ 58h	1	PCIe Root Port Cluster 1 - Root Port 5 Enable	**0x0**; RP5 Disabled **0x1**; RP5 Enabled	0x1	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Root Port 5 ***Note:*** If Root port is set to "0x0 - RP5 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.
22	+ 58h	2	PCIe Root Port Cluster 1 - Root Port 6 Enable	**0x0;** RP6 Disabled **0x1;** RP6 Enabled	0x1	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Root Port 6 ***Note:*** If Root port is set to "0x0 - RP6 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.
22	+ 58h	3	PCIe Root Port Cluster 1 - Root Port 7 Enable	**0x0;** RP7 Disabled **0x1;** RP7 Enabled	0x1	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Root Port 7 ***Note:*** If Root port is set to "0x0 - RP7 Disabled" then BIOS will not be able to turn it back on. Soft Straps have priority. Bifurcation control register BIFCTL0[2:0] configuration should take into account any disabled root ports via soft straps.

Table 4-3. Flash Descriptor Soft Straps (Sheet 15 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
						PCIe RP Cluster 1 - RP x1 Link Width Enable
22	+ 58h	27:24	PCIe Root Port Cluster 1 - Root Port 4 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 1 Disable" and "PCIe Root Port Cluster 1 - Root Port 4 Enable" are set to Enable, tell the SoC to set RP 4 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.
22	+ 58h	31:28	PCIe Root Port Cluster 1 - Root Port 5 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 1 Disable" and "PCIe Root Port Cluster 1 - Root Port 5 Enable" are set to Enable, tell the SoC to set RP 5 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.
23	+ 5Ch	3:0	PCIe Root Port Cluster 1 - Root Port 6 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 1 Disable" and "PCIe Root Port Cluster 1 - Root Port 6 Enable" are set to Enable, tell the SoC to set RP 6 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.
23	+ 5Ch	7:4	PCIe Root Port Cluster 1 - Root Port 7 x1 Link Width Enable	0x0; RP Link Width set by BICTRL register 0xF; x1	0x0	If soft straps "PCIe Root Port Cluster 1 Disable" and "PCIe Root Port Cluster 1 - Root Port 7 Enable" are set to Enable, tell the SoC to set RP 7 link width to x1. **Notes:** - If setting this soft strap to the "x1" configuration and desiring to use the other HSIO lane for the SATA controller, make sure to set the respective HSIO and SATA controller soft straps accordingly.

Table 4-3. Flash Descriptor Soft Straps (Sheet 16 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
						PCIe RP Cluster 1 - SRIS Enable
23	+ 5Ch	25	PCIe Root Port Cluster 1 - Root Port 4 SRIS Enable	**0x0;** RP 4 SRIS Disabled **0x1;** RP 4 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 4. SRIS is supported at Gen 1, and 2. **Note:** Refer to the SOSCTL.SRISEN register.
23	+ 5Ch	26	PCIe Root Port Cluster 1 - Root Port 5 SRIS Enable	**0x0;** RP 5 SRIS Disabled **0x1;** RP 5 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 5. SRIS is supported at Gen 1, and 2. **Note:** Refer to the SOSCTL.SRISEN register.
23	+ 5Ch	27	PCIe Root Port Cluster 1 - Root Port 6 SRIS Enable	**0x0;** RP 6 SRIS Disabled **0x1;** RP 6 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 6. SRIS is supported at Gen 1, and 2. **Note:** Refer to the SOSCTL.SRISEN register.
23	+ 5Ch	28	PCIe Root Port Cluster 1 - Root Port 7 SRIS Enable	**0x0;** RP 7 SRIS Disabled **0x1;** RP 7 SRIS Enabled	0x0	If soft strap "PCIe Root Port Cluster 1 Disable" is set to "PCIe Root Port Cluster 1 Enabled" tell the SoC to enable Separate Reference Clocks with Independent Spread Spectrum Clocking (SRIS) for Root Port 7. SRIS is supported at Gen 1, and 2. **Note:** Refer to the SOSCTL.SRISEN register.

Table 4-3. Flash Descriptor Soft Straps (Sheet 17 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
External Clocks						
5	+ 14h	21	HSIO Spread Spectrum Clocking Disable	0x0: Enable HSIO Spread Spectrum Clocking 0x1: Disable HSIO Spread Spectrum Clocking	0x0	Tells the SoC if HSIO Spread Spectrum Clock (SSC) will be disabled from the time the clock is first output by the SoC for PCIe, SATA, and XHCI. ***Note:*** Should BIOS configure this setting, disabling the HSIO SSC will not take effect until after memory training during BIOS execution.
15	+ 3Ch	2	DDR Spread Spectrum Clock (SSC) Modulator Disable	0x0; DDR SSC Disabled 0x1; DDR SSC Enabled	0x1	Tells the SoC if DDR Spread Spectrum Clock (SSC) modulator will be disabled.
CLK_OUT_D 0 Configuration						
15	+ 3Ch	8	Force CLK_OUT_D 0	0x0; CLK_OUT_D 0 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps (CLK_OUT_D 0 ; PCIE_CLKREQ_N[x]). 0x1; Output Clock to CLK_OUT_D 0 at all times regardless of clkreq setting.	Board Dependent	Tells the SoC to output 100 MHz Clock to CLK_OUT_DP[0] and CLK_OUT_DN[0] ***Note:*** There is no option to disable CLK_OUT_D 0. Instead we can prevent a clock from being sent by setting this soft strap to option: "0x0; CLK_OUT_D 0 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps" as well as setting all the CLK_OUT_D 0 - PCIE_CLKREQ_N[0-7] soft straps to: "0x0; Clock will not respond to PCIE_CLKREQ_N[x] pin."
15	+ 3Ch	16	CLK_OUT_D 0 - PCIE_CLKREQ_N[0]	0x0; Clock will not respond to PCIE_CLKREQ_N[0] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[0] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[0] pin.
15	+ 3Ch	17	CLK_OUT_D 0 - PCIE_CLKREQ_N[1]	0x0; Clock will not respond to PCIE_CLKREQ_N[1] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[1] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[1]
15	+ 3Ch	18	CLK_OUT_D 0 - PCIE_CLKREQ_N[2]	0x0; Clock will not respond to PCIE_CLKREQ_N[2] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[2] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[2]

Table 4-3. Flash Descriptor Soft Straps (Sheet 18 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
15	+ 3Ch	19	CLK_OUT_D 0 - PCIE_CLKREQ_N[3]	0x0; Clock will not respond to PCIE_CLKREQ_N[3] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[3] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[3]
15	+ 3Ch	20	CLK_OUT_D 0 - PCIE_CLKREQ_N[4]	0x0; Clock will not respond to PCIE_CLKREQ_N[4] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[4] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[4]
15	+ 3Ch	21	CLK_OUT_D 0 - PCIE_CLKREQ_N[5]	0x0; Clock will not respond to PCIE_CLKREQ_N[5] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[5] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[5]
15	+ 3Ch	22	CLK_OUT_D 0 - PCIE_CLKREQ_N[6]	0x0; Clock will not respond to PCIE_CLKREQ_N[6] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[6] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[6]
15	+ 3Ch	23	CLK_OUT_D 0 - PCIE_CLKREQ_N[7]	0x0; Clock will not respond to PCIE_CLKREQ_N[7] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[7] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 0" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[0] and CLK_OUT_DN[0] will respond to PCIE_CLKREQ_N[7]
CLK_OUT_D 1 Configuration						
15	+ 3Ch	9	Force CLK_OUT_D 1	0x0; CLK_OUT_D 1 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps (CLK_OUT_D 1 ; PCIE_CLKREQ_N[x]). 0x1; Output Clock to CLK_OUT_D 1 at all times regardless of clkreq setting.	Board Dependent	Tells the SoC to output 100 MHz Clock to CLK_OUT_DP[1] and CLK_OUT_DN[1] ***Note:*** There is no option to disable CLK_OUT_D 1. Instead we can prevent a clock from being sent by setting this soft strap to option: "0x0; CLK_OUT_D 1 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps" as well as setting all the CLK_OUT_D 1 - PCIE_CLKREQ_N[0-7] soft straps to: "0x0; Clock will not respond to PCIE_CLKREQ_N[x] pin."
15	+ 3Ch	24	CLK_OUT_D 1 - PCIE_CLKREQ_N[0]	0x0; Clock will not respond to PCIE_CLKREQ_N[0] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[0] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[0] pin.
15	+ 3Ch	25	CLK_OUT_D 1 - PCIE_CLKREQ_N[1]	0x0; Clock will not respond to PCIE_CLKREQ_N[1] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[1] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[1]

Table 4-3. Flash Descriptor Soft Straps (Sheet 19 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
15	+ 3Ch	26	CLK_OUT_D 1 - PCIE_CLKREQ_N[2]	0x0; Clock will not respond to PCIE_CLKREQ_N[2] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[2] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[2]
15	+ 3Ch	27	CLK_OUT_D 1 - PCIE_CLKREQ_N[3]	0x0; Clock will not respond to PCIE_CLKREQ_N[3] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[3] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[3]
15	+ 3Ch	28	CLK_OUT_D 1 - PCIE_CLKREQ_N[4]	0x0; Clock will not respond to PCIE_CLKREQ_N[4] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[4] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[4]
15	+ 3Ch	29	CLK_OUT_D 1 - PCIE_CLKREQ_N[5]	0x0; Clock will not respond to PCIE_CLKREQ_N[5] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[5] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[5]
15	+ 3Ch	30	CLK_OUT_D 1 - PCIE_CLKREQ_N[6]	0x0; Clock will not respond to PCIE_CLKREQ_N[6] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[6] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[6]
15	+ 3Ch	31	CLK_OUT_D 1 - PCIE_CLKREQ_N[7]	0x0; Clock will not respond to PCIE_CLKREQ_N[7] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[7] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 1" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[1] and CLK_OUT_DN[1] will respond to PCIE_CLKREQ_N[7]
CLK_OUT_D 2 Configuration						
15	+ 3Ch	10	Force CLK_OUT_D 2	0x0; CLK_OUT_D 2 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps (CLK_OUT_D 2 ; PCIE_CLKREQ_N[x]). 0x1; Output Clock to CLK_OUT_D 2 at all times regardless of clkreq setting.	Board Dependent	Tells the SoC to output 100 MHz Clock to CLK_OUT_DP[2] and CLK_OUT_DN[2] ***Note:*** There is no option to disable CLK_OUT_D 2. Instead we can prevent a clock from being sent by setting this soft strap to option: "0x0; CLK_OUT_D 2 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps" as well as setting all the CLK_OUT_D 2 - PCIE_CLKREQ_N[0-7] soft straps to: "0x0; Clock will not respond to PCIE_CLKREQ_N[x] pin."
16	+ 40h	0	CLK_OUT_D 2 - PCIE_CLKREQ_N[0]	0x0; Clock will not respond to PCIE_CLKREQ_N[0] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[0] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[0] pin.

Table 4-3. Flash Descriptor Soft Straps (Sheet 20 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
16	+ 40h	1	CLK_OUT_D 2 - PCIE_CLKREQ_N[1]	0x0; Clock will not respond to PCIE_CLKREQ_N[1] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[1] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[1]
16	+ 40h	2	CLK_OUT_D 2 - PCIE_CLKREQ_N[2]	0x0; Clock will not respond to PCIE_CLKREQ_N[2] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[2] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[2]
16	+ 40h	3	CLK_OUT_D 2 - PCIE_CLKREQ_N[3]	0x0; Clock will not respond to PCIE_CLKREQ_N[3] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[3] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[3]
16	+ 40h	4	CLK_OUT_D 2 - PCIE_CLKREQ_N[4]	0x0; Clock will not respond to PCIE_CLKREQ_N[4] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[4] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[4]
16	+ 40h	5	CLK_OUT_D 2 - PCIE_CLKREQ_N[5]	0x0; Clock will not respond to PCIE_CLKREQ_N[5] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[5] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[5]
16	+ 40h	6	CLK_OUT_D 2 - PCIE_CLKREQ_N[6]	0x0; Clock will not respond to PCIE_CLKREQ_N[6] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[6] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[6]
16	+ 40h	7	CLK_OUT_D 2 - PCIE_CLKREQ_N[7]	0x0; Clock will not respond to PCIE_CLKREQ_N[7] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[7] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 2" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[2] and CLK_OUT_DN[2] will respond to PCIE_CLKREQ_N[7]
CLK_OUT_D 3 Configuration						
15	+ 3Ch	11	Force CLK_OUT_D 3	0x0; CLK_OUT_D 3 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps (CLK_OUT_D 3 ; PCIE_CLKREQ_N[x]). 0x1; Output Clock to CLK_OUT_D 3 at all times regardless of clkreq setting.	Board Dependent	Tells the SoC to output 100 MHz Clock to CLK_OUT_DP[3] and CLK_OUT_DN[3] ***Note:*** There is no option to disable CLK_OUT_D 3. Instead we can prevent a clock from being sent by setting this soft strap to option: "0x0; CLK_OUT_D 3 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps" as well as setting all the CLK_OUT_D 3 - PCIE_CLKREQ_N[0-7] soft straps to: "0x0; Clock will not respond to PCIE_CLKREQ_N[x] pin."

Table 4-3. Flash Descriptor Soft Straps (Sheet 21 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
16	+ 40h	8	CLK_OUT_D 3 - PCIE_CLKREQ_N[0]	0x0; Clock will not respond to PCIE_CLKREQ_N[0] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[0] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[0] pin.
16	+ 40h	9	CLK_OUT_D 3 - PCIE_CLKREQ_N[1]	0x0; Clock will not respond to PCIE_CLKREQ_N[1] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[1] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[1]
16	+ 40h	10	CLK_OUT_D 3 - PCIE_CLKREQ_N[2]	0x0; Clock will not respond to PCIE_CLKREQ_N[2] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[2] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[2]
16	+ 40h	11	CLK_OUT_D 3 - PCIE_CLKREQ_N[3]	0x0; Clock will not respond to PCIE_CLKREQ_N[3] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[3] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[3]
16	+ 40h	12	CLK_OUT_D 3 - PCIE_CLKREQ_N[4]	0x0; Clock will not respond to PCIE_CLKREQ_N[4] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[4] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[4]
16	+ 40h	13	CLK_OUT_D 3 - PCIE_CLKREQ_N[5]	0x0; Clock will not respond to PCIE_CLKREQ_N[5] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[5] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[5]
16	+ 40h	14	CLK_OUT_D 3 - PCIE_CLKREQ_N[6]	0x0; Clock will not respond to PCIE_CLKREQ_N[6] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[6] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[6]
16	+ 40h	15	CLK_OUT_D 3 - PCIE_CLKREQ_N[7]	0x0; Clock will not respond to PCIE_CLKREQ_N[7] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[7] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 3" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[3] and CLK_OUT_DN[3] will respond to PCIE_CLKREQ_N[7]

Table 4-3. Flash Descriptor Soft Straps (Sheet 22 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
CLK_OUT_D 4 Configuration						
15	+ 3Ch	12	Force CLK_OUT_D 4	0x0; CLK_OUT_D 4 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps (CLK_OUT_D 4 ; PCIE_CLKREQ_N[x]). 0x1; Output Clock to CLK_OUT_D 4 at all times regardless of clkreq setting.	Board Dependent	Tells the SoC to output 100 MHz Clock to CLK_OUT_DP[4] and CLK_OUT_DN[4] ***Note:*** There is no option to disable CLK_OUT_D 4. Instead we can prevent a clock from being sent by setting this soft strap to option: "0x0; CLK_OUT_D 4 will respond to PCIE_CLKREQ_N[x] pins configured through soft straps" as well as setting all the CLK_OUT_D 4 - PCIE_CLKREQ_N[0-7] soft straps to: "0x0; Clock will not respond to PCIE_CLKREQ_N[x] pin."
16	+ 40h	16	CLK_OUT_D 4 - PCIE_CLKREQ_N[0]	0x0; Clock will not respond to PCIE_CLKREQ_N[0] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[0] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[0] pin.
16	+ 40h	17	CLK_OUT_D 4 - PCIE_CLKREQ_N[1]	0x0; Clock will not respond to PCIE_CLKREQ_N[1] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[1] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[1]
16	+ 40h	18	CLK_OUT_D 4 - PCIE_CLKREQ_N[2]	0x0; Clock will not respond to PCIE_CLKREQ_N[2] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[2] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[2]
16	+ 40h	19	CLK_OUT_D 4 - PCIE_CLKREQ_N[3]	0x0; Clock will not respond to PCIE_CLKREQ_N[3] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[3] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[3]
16	+ 40h	20	CLK_OUT_D 4 - PCIE_CLKREQ_N[4]	0x0; Clock will not respond to PCIE_CLKREQ_N[4] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[4] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[4]
16	+ 40h	21	CLK_OUT_D 4 - PCIE_CLKREQ_N[5]	0x0; Clock will not respond to PCIE_CLKREQ_N[5] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[5] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[5]
16	+ 40h	22	CLK_OUT_D 4 - PCIE_CLKREQ_N[6]	0x0; Clock will not respond to PCIE_CLKREQ_N[6] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[6] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[6]

Table 4-3. Flash Descriptor Soft Straps (Sheet 23 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
16	+ 40h	23	CLK_OUT_D 4 - PCIE_CLKREQ_N[7]	0x0; Clock will not respond to PCIE_CLKREQ_N[7] pin. 0x1; Clock will respond to PCIE_CLKREQ_N[7] pin.	Board Dependent	If soft strap "Force CLK_OUT_D 4" is set to respond to PCIE_CLKREQ_N[x]" then tell the SoC if CLK_OUT_DP[4] and CLK_OUT_DN[4] will respond to PCIE_CLKREQ_N[7]
Flex Clocks Configuration						
16	+ 40h	29:24	FLEX_CLK_SE[0] - Frequency	0x04; 50 MHz 0x06; 33.3 MHz 0x08; 25 MHz 0x22; 48 MHz	0x22	Tells the SoC what frequency to output from FLEX_CLK_SE[0].
16	+ 40h	30	FLEX_CLK_SE[0] - Isolation Enable	0x1; Wait to drive the clocks to ground until after DDR Domains are powered on 0x0; Drive clocks by default (shortly after RSMRST_N)	0x0	This soft strap can help prevent driving a clock into an unpowered domain.
17	+ 44h	5:0	FLEX_CLK_SE[1] - Frequency	0x04; 50 MHz 0x06; 33.3 MHz 0x08; 25 MHz 0x22; 48 MHz	0x22	Tells the SoC what frequency to output from FLEX_CLK_SE[1].
17	+ 44h	6	FLEX_CLK_SE[1] - Isolation Enable	0x1; Wait to drive the clocks to ground until after DDR Domains are powered on 0x0; Drive clocks by default (shortly after RSMRST_N)	0x0	Isolates FlexIO Clock 1 when host_powergood_rst_b is active to prevent driving clock into an unpowered domain.

Table 4-3. Flash Descriptor Soft Straps (Sheet 24 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
SPI						
9	+ 24h	0	SPI - Dual Output Fast Read Enable (DORE)	0x0; Dual Output Read is disabled 0x1; Dual Output Read is enabled	0x1	Tells the SoC SPI controller if Dual Output Fast Read (DORE) instructions are supported. This will only take effect if the SPI flash device connected to the SPI controller also supports DORE in its SFDP table and has the Dual Output bit and the Fast Read Support bit enabled in the FLCOMP register inside the SPI flash descriptor region. ***Note:*** Only one soft strap between DORE/DIORE/QORE/QIORE SPI modes can be enabled at a time. i.e. if DORE is enabled via soft strap, then DIORE/QORE/QIORE soft straps must be set to disabled via soft strap.
9	+ 24h	1	SPI - Dual I/O Fast Read Enable (DIORE)	0x0; Dual I/O Read is disabled 0x1; Dual I/O Read is enabled	0x1	Tells the SoC SPI controller if Dual I/O Fast Read (DIORE) instructions are supported. This will only take effect if the SPI flash device connected to the SPI controller also supports DIORE in its SFDP table and has the Dual Output bit and the Fast Read Support bit enabled in the FLCOMP register inside the SPI flash descriptor region. ***Note:*** Only one soft strap between DORE/DIORE/QORE/QIORE SPI modes can be enabled at a time. i.e. if DORE is enabled via soft strap, then DIORE/QORE/QIORE soft straps must be set to disabled via soft strap.
9	+ 24h	2	SPI - Quad Output Fast Read Enable (QORE)	0x0; Quad Output Read is disabled 0x1; Quad Output Read is enabled	0x1	Tells the SoC SPI controller if Quad Output Fast Read (QORE) instructions are supported. This will only take effect if the SPI flash device connected to the SPI controller also supports QORE in its SFDP table and has the Dual Output bit and the Fast Read Support bit enabled in the FLCOMP register inside the SPI flash descriptor region. ***Note:*** Only one soft strap between DORE/DIORE/QORE/QIORE SPI modes can be enabled at a time. i.e. if DORE is enabled via soft strap, then DIORE/QORE/QIORE soft straps must be set to disabled via soft strap.

Table 4-3. Flash Descriptor Soft Straps (Sheet 25 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
9	+ 24h	3	SPI - Quad I/O Fast Read Enable (QIORE)	0x0; Quad I/O Read is disabled 0x1; Quad I/O Read is enabled	0x1	Tells the SoC SPI controller if Quad I/O Fast Read (QIORE) instructions are supported. This will only take effect if the SPI flash device connected to the SPI controller also supports QIORE in its SFDP table and has the Dual Output bit and the Fast Read Support bit enabled in the FLCOMP register inside the SPI flash descriptor region. ***Note:*** Only one soft strap between DORE/DIORE/QORE/QIORE SPI modes can be enabled at a time. i.e. if DORE is enabled via soft strap, then DIORE/QORE/QIORE soft straps must be set to disabled via soft strap.
9	+ 24h	6:4	SPI - Boot Block Size	0x0; 64KB; Invert A16 if Top Swap is enabled 0x1; 128KB; Invert A17 if Top Swap is enabled 0x2; 256KB; Invert A18 if Top Swap is enabled 0x3; 512KB; Invert A19 if Top Swap is enabled 0x4; 1MB; Invert A20 if Top Swap is enabled	0x0	Tells the SoC if the size of the Top Swap boot block when booting from the SPI interface. **Note**: If boot interface is LPC, this strap has not effect and the Boot block size is 64 KB
9	+ 24h	8	SPI - Enable Delay before write busy poll	0x1; SPI controller may delay the start of issuing read_status to poll for flash device busy after a write operation (enabled) 0x0; SPI controller must start polling immediately after issuing the write command (disabled)	0x0	Tells the SoC if SPI delay before write busy poll is enabled
9	+ 24h	9	SPI - Enable Delay before erase busy poll	0x1; SPI controller may delay the start of issuing read_status to poll for flash device busy after an erase operation (enabled) 0x0; SPI controller must start polling immediately after issuing the erase command. (disabled)	0x0	Tells the SoC if SPI delay before erase busy poll is enabled
9	+ 24h	10	SPI - Enable Delay before RPMC busy poll	0x1; SPI controller may delay the start of polling for flash device busy after an RPMC operation (enabled) 0x0; SPI controller must start polling immediately after issuing any RPMC command. (disabled)	0x0	Tells the SoC if SPI delay before RPMC busy poll is enabled

Table 4-3. Flash Descriptor Soft Straps (Sheet 26 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
9	+ 24h	11	SPI - Enable device 0 deep power down	0x1; flash controller implements enter/exit deep power down to this device if it discovers capability via SFDP (enabled) 0x0; flash controller does not implement enter/exit deep power down for this device (disabled)	0x0	Tells the SoC to implement SPI device 0 (Flash) deep power down
9	+ 24h	12	SPI - Enable device 1 deep power down	0x1; flash controller implements enter/exit deep power down to this device if it discovers capability via SFDP (enabled) 0x0; flash controller does not implement enter/exit deep power down for this device (disabled)	0x0	Tells the SoC to implement SPI device 1 (Flash) deep power down
9	+ 24h	13	SPI - Host Software Sequencing Enable	0x0 - Host SW sequencing is disabled. Default to HW sequencing. 0x1 - Host SW sequencing is enabled along with HW sequencing.	0x0	Tells the SoC that SPI SW sequencing is supported in addition to HW sequencing. This soft strap takes precedence over BIOS_DLOCK.SSEQLOCKDN and BIOS_HSFSTS_CTL.FLOCKDN registers. Should it be set to 0x0, these registers become RO and cannot enable SPI SW sequencing. ***Note:*** SPI SW Sequencing is intended as a backup to HW sequencing.
9	+ 24h	27:25	SPI - Resume Hold off Delay (tRHD)	0x0; 0us 0x1; 2us 0x2; 4us 0x3; 6us 0x4; 8us 0x5; 10us 0x6; 12us 0x7; 14us	0x4	Tells the SoC to specify the time after the completion of a pri_op before the flash controller sends the resume instruction. If a new pri_op is eligible to be issued prior to the end of this delay time then the pri_op is issued and the timer is re-initialized to tRHD.
9	+ 24h	31:30	SPI - Resume to suspend Timing	0x0; 128 us 0x1; 256 us 0x2; 512 us 0x3; no ceiling, use the SFDP values	0x3	Tells the SoC the maximum value for the write and erase resume to suspend intervals
10	+ 28h	10:8	SPI - TPM Clock Frequency	0x2; 48 MHz 0x4; 30 MHz 0x6; 17 MHz	0x6	Tells the SoC what clock frequency to use when talking to TPM on SPI ***Note:*** To control the speed of the instructions between the SoC SPI controller and the SPI flash memory boot device connected to it, configure the FLCOMP register inside the SPI flash descriptor region.

Table 4-3. Flash Descriptor Soft Straps (Sheet 27 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
10	+ 28h	14	SPI - Ignore Fixed FLMSTR Permission	0x0; FLMSTR fixed permission to regions is enabled 0x1; FLMSTR fixed permission to regions may be disabled	0x0	Tells the SoC to ignore Fixed FLMSTR Permission settings that are set in the FLMSTR registers inside the descriptor region of the SPI flash memory boot device connected to the SoC to force the SPI controller to ignore each Master's default permission to its own region(s). This affects FLMSTR default permissions and a software master's capability to extend permission to its region(s).
11	+ 2Ch	31:0	SPI - Global Protected Range default (GPRD)	Value: Hex	0x00000000	Tells the SoC to set the default value of the GPR0 register in the SPI Flash Controller as a security feature. This soft strap value is intended to be configured by customer.

Table 4-3. Flash Descriptor Soft Straps (Sheet 28 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
PECI						
0	+ 0h	6:0	PECI - Target Write Address	Value: Hex	0x4C	The SoC reads this strap and programs the ADDR0 field of the Target Address Control Register (TACTRL) located at sideband Port CEh, offset 228h.
1	+ 4h	26:20	PECI - Target Read Address	Value: Hex	0x4B	The SoC reads this strap and programs the GPTRADR field of the General Control Register (GPBRCTRL) located at sideband Port CEh, offset 240h
Top Swap Override						
30	+ 78h	1	Protected Range Top Swap Override Enable	0x0; PRR_TS_OVR is Read Only (disabled) 0x1; Allows PRR_TS_OVR register to be Read/Write. (enabled)	0x0	Tells the SoC if Protected Range Top Swap Override is enabled by setting the permission to register **PRR_TS_OVR** to Read/Write or Read Only.
TPM over SPI or LPC						
30	+ 78h	0	TPM Over SPI or LPC Select	0x0 - TPM on LPC 0x1 -TPM on SPI	0x0	Tells the SoC to enable TPM on SPI or LPC interfaces. The Intel Manageability Engine (ME) consumes this soft strap.

Table 4-3. Flash Descriptor Soft Straps (Sheet 29 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Intel® Management Engine (Intel® ME)						
14	+ 38h	1	ME ROM - Intel® Trace Hub Soft Enable	0x0; Tracing is disabled 0x1; Tracing is enabled	0x0	This soft strap enables Intel Trace Hub-based tracing in ME ROM. **Note:** In order to use Intel Trace Hub over USB3.0, SS14 bit[17] - "ME - Intel® Direct Connect Interface Enabled" must be set to 0x1 - Enabled.
14	+ 38h	17	ME - Intel® Direct Connect Interface Enabled	0x0; Intel® DCI Disabled 0x1; Intel® DCI Enabled	0x0	Tells the SoC to enable Intel® Direct Connect Interface (Intel® DCI). **Note:** This is required to enable debugging over USB3.0 interface. This soft strap is also required for Intel Trace Hub to work over USB3.0 For more information on Intel DCI. See EDS Chapter 38.4
14	+ 38h	21	ME - Intel® Trace Hub - Emergency Mode	0x0; ROM Tracing Emergency mode disabled 0x1; ROM Tracing Emergency mode enabled	0x0	Tells the SoC to enable ROM Tracing in the base platform ME image. This is for DEBUG ONLY should not be set for production environment **Note:** Enabling this soft strap will increase the ME loading time due to ME outputting Debug traces and thus increase overall system boot time.
Intel® ME SMBus Management Transport 0 - SMT 0 Configuration						
31	+ 7Ch	8	ME SMBus Management Transport 1 - SMT 0 SMBus Enable	0x0; SMT disabled 0x1; SMT enabled	0x1	Tells the SoC that SMT0 is enabled and connected to the SMBus. Disabled means that the device is not connected to the SMBus Pins.
35	+ 8Ch	17:16	ME SMBus Management Transport (SMT) 0 - SMBus Clock	0x1; Standard (100 KHz) 0x2; Fast Mode (400 KHz) 0x3; Fast Mode Plus (1 MHz)	0x1	Tells the SoC the speed the physical bus must operate at. **Note:** It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed.
33	+ 84h	8	ME SMBus Management Transport (SMT) 0 - Host SMBus Address Enable	0x0; Host SMBus Target Address disabled 0x1; Host SMBus Target Address enabled	0x0	Tells the SoC SMT controller that it is the SMBus segment owner and any device sending a request to Address 10h should be claimed by the SMT controller. When set, enables HW to accept write cycles targeting address 10h and enables target logic to ACK Host SMBus address (10h) on the SMBus. **Note:** This bit must be set to "1" when HW is configured to support MCTP and chipset is the SMBus Segment Owner.

Table 4-3. Flash Descriptor Soft Straps (Sheet 30 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
31	+ 7Ch	16	ME SMBus Management Transport (SMT) 0 - General Purpose (GP) Target Address Enable	0x0; GP Target Address is Disabled 0x1; GP Target Address is Enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. (Address Enable Bit) **Note:** The 'Enable' for this address is programmed through this soft strap. HW does not take any action based on the value of this soft strap. It is simply provided to FW for reading.
31	+ 7Ch	23:17	ME SMBus Management Transport (SMT) 0 - General Purpose (GP) Target Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. **Note:** This address has to be configured so that it does not conflict with other devices on the SMBus network.
32	+ 80h	16	ME SMBus Management Transport (SMT) 0 - I^2C Address Enable	0x0; I^2C Target Address disabled 0x1; I^2C Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave over I^2C (Address Enable Bit)
31	+ 7Ch	30:24	ME SMBus Management Transport (SMT) 0 - I^2C Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave over I^2C. **Notes:** I^2C address of the SMT logic for support of I^2C target. All I^2C protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.I2C_EN register is set. -This address has to be configured so that it does not conflict with other devices on the SMBus network.
32	+ 80h	24	ME SMBus Management Transport (SMT) 0 - Alert Sending Device (ASD) Address Enable	0x0; ASD Target Address disabled 0x1; ASD Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. (Address Enable Bit)
32	+ 80h	6:0	ME SMBus Management Transport (SMT) 0 - Alert Sending Device (ASD) Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network. -SMBus address of the SMT logic for support of ASF protocol. All ASF protocol transactions targeting this address will be ACKed by the HW if the TPOLICY.ASD_EN register is set.

Table 4-3. Flash Descriptor Soft Straps (Sheet 31 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
33	+ 84h	0	ME SMBus Management Transport (SMT) 0 - MCTP Address Enable	0x0; MCTP Target Address disabled 0x1; MCTP Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. (Address Enable Bit)
32	+ 80h	14:8	ME SMBus Management Transport (SMT) 0 - MCTP Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. **Note:** MCTP address of the SMT logic. All MCTP protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.MCTP_EN register is set.
33	+ 84h	31:16	ME SMBus Management Transport (SMT) 0 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
34	+ 88h	15:0	ME SMBus Management Transport (SMT) 0 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.
34	+ 88h	31:16	ME SMBus Management Transport (SMT) 0 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
35	+ 8Ch	15:0	ME SMBus Management Transport (SMT) 0 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 32 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Intel® ME SMBus Management Transport 1 - SMT 1 Configuration						
36	+ 90h	8	ME SMBus Management Transport (SMT) 1 - SMT 1 SMBus Enable	0x0; SMT disabled 0x1; SMT enabled	0x1	Tells the SoC that SMT1 is enabled and connected to the SMBus. Disabled means that the device is not connected to the SMBus Pins.
40	+ A0h	17:16	ME SMBus Management Transport (SMT) 1 - SMBus Clock	0x1; Standard (100 KHz) 0x2; Fast Mode (400 KHz) 0x3; Fast Mode Plus (1 MHz)	0x1	Tells the SoC the speed the physical bus must operate at. **Note:** It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed.
38	+ 98h	8	ME SMBus Management Transport (SMT) 1 - Host SMBus Address Enable	0x0; Host SMBus Target Address disabled 0x1; Host SMBus Target Address enabled	0x0	Tells the SoC SMT controller that it is the SMBus segment owner and any device sending a request to Address 10h should be claimed by the SMT controller. When set, enables HW to accept write cycles targeting address 10h and enables target logic to ACK Host SMBus address (10h) on the SMBus. **Note:** This bit must be set to "1" when HW is configured to support MCTP and chipset is the SMBus Segment Owner.
36	+ 90h	16	ME SMBus Management Transport (SMT) 1 - General Purpose (GP) Target Address Enable	0x0; GP Target Address is Disabled 0x1; GP Target Address is Enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. (Address Enable Bit) **Note:** The 'Enable' for this address is programmed through this soft strap. HW does not take any action based on the value of this soft strap. It is simply provided to FW for reading.
36	+ 90h	23:17	ME SMBus Management Transport (SMT) 1 - General Purpose (GP) Target Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. **Note:** This address has to be configured so that it does not conflict with other devices on the SMBus network.
37	+ 94h	16	ME SMBus Management Transport (SMT) 1 - I^2C Address Enable	0x0; I^2C Target Address disabled 0x1; I^2C Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave over I^2C (Address Enable Bit).

Table 4-3. Flash Descriptor Soft Straps (Sheet 33 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
36	+ 90h	30:24	ME SMBus Management Transport (SMT) 1 - I^2C Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave over I^2C. **Notes:** I^2C address of the SMT logic for support of I^2C target. All I^2C protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.I2C_EN register is set. -This address has to be configured so that it does not conflict with other devices on the SMBus network.
37	+ 94h	24	ME SMBus Management Transport (SMT) 1 - Alert Sending Device (ASD) Address Enable	0x0; ASD Target Address disabled 0x1; ASD Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. (Address Enable Bit)
37	+ 94h	6:0	ME SMBus Management Transport (SMT) 1 - Alert Sending Device (ASD) Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network. -SMBus address of the SMT logic for support of ASF protocol. All ASF protocol transactions targeting this address will be ACKed by the HW if the TPOLICY.ASD_EN register is set.
38	+ 98h	0	ME SMBus Management Transport (SMT) 1 - MCTP Address Enable	0x0; MCTP Target Address disabled 0x1; MCTP Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. (Address Enable Bit)
37	+ 94h	14:8	ME SMBus Management Transport (SMT) 1 - MCTP Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. **Note:** MCTP address of the SMT logic. All MCTP protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.MCTP_EN register is set.
38	+ 98h	31:16	ME SMBus Management Transport (SMT) 1 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 34 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
39	+ 9Ch	15:0	ME SMBus Management Transport (SMT) 1 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.
39	+ 9Ch	31:16	ME SMBus Management Transport (SMT) 1 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
40	+ A0h	15:0	ME SMBus Management Transport (SMT) 1 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 35 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Intel® ME SMBus Management Transport 2 - SMT 2 Configuration						
41	+ A4h	8	ME SMBus Management Transport (SMT) 2 - SMT 2 SMBus Enable	0x0; SMT disabled 0x1; SMT enabled	0x1	Tells the SoC that SMT2 is enabled and connected to the SMBus. Disabled means that the device is not connected to the SMBus Pins.
45	+ B4h	17:16	ME SMBus Management Transport (SMT) 2 - SMBus Clock	0x1; Standard (100 KHz) 0x2; Fast Mode (400 KHz) 0x3; Fast Mode Plus (1 MHz)	0x1	Tells the SoC the speed the physical bus must operate at. **Note:** It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed.
43	+ ACh	8	ME SMBus Management Transport (SMT) 2 - Host SMBus Address Enable	0x0; Host SMBus Target Address disabled 0x1; Host SMBus Target Address enabled	0x0	Tells the SoC SMT controller that it is the SMBus segment owner and any device sending a request to Address 10h should be claimed by the SMT controller. When set, enables HW to accept write cycles targeting address 10h and enables target logic to ACK Host SMBus address (10h) on the SMBus. **Note:** This bit must be set to "1" when HW is configured to support MCTP and chipset is the SMBus Segment Owner.
41	+ A4h	16	ME SMBus Management Transport (SMT) 2 - General Purpose (GP) Target Address Enable	0x0; GP Target Address is Disabled 0x1; GP Target Address is Enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. (Address Enable Bit) **Note:** The 'Enable' for this address is programmed through this soft strap. HW does not take any action based on the value of this soft strap. It is simply provided to FW for reading.
41	+ A4h	23:17	ME SMBus Management Transport (SMT) 2 - General Purpose (GP) Target Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network.
42	+ A8h	16	ME SMBus Management Transport (SMT) 2 - I^2C Address Enable	0x0; I^2C Target Address disabled 0x1; I^2C Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave over I^2C (Address Enable Bit)

Table 4-3. Flash Descriptor Soft Straps (Sheet 36 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
41	+ A4h	30:24	ME SMBus Management Transport (SMT) 2 - I^2C Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave over I^2C. **Notes:** - address of the SMT logic for support of I^2C target. All I^2C protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.I2C_EN register is set. -This address has to be configured so that it does not conflict with other devices on the SMBus network.
42	+ A8h	24	ME SMBus Management Transport (SMT) 2 - Alert Sending Device (ASD) Address Enable	0x0; ASD Target Address disabled 0x1; ASD Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. (Address Enable Bit)
42	+ A8h	6:0	ME SMBus Management Transport (SMT) 2 - Alert Sending Device (ASD) Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network. -SMBus address of the SMT logic for support of ASF protocol. All ASF protocol transactions targeting this address will be ACKed by the HW if the TPOLICY.ASD_EN register is set.
43	+ ACh	0	ME SMBus Management Transport (SMT) 2 - MCTP Address Enable	0x0; MCTP Target Address disabled 0x1; MCTP Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. (Address Enable Bit)
42	+ A8h	14:8	ME SMBus Management Transport (SMT) 2 - MCTP Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. **Note:** MCTP address of the SMT logic. All MCTP protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.MCTP_EN register is set.
43	+ ACh	31:16	ME SMBus Management Transport (SMT) 2 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 37 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
44	+ B0h	15:0	ME SMBus Management Transport (SMT) 2 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.
44	+ B0h	31:16	ME SMBus Management Transport (SMT) 2 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
45	+ B4h	15:0	ME SMBus Management Transport (SMT) 2 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 38 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Innovation Engine (IE)						
47	+ BCh	13	IE Disable	0x0; IE is enabled 0x1; IE is disabled	0x0	Tells the SoC to Disable the Innovation Engine (IE)
47	+ BCh	14	IE ROM - SMT Log Enable	0x0; ROM log to SMT Disabled 0x1; ROM log to SMT Enabled	0x0	Tells the SoC to Enable the IE ROM log to SMT0 **Note:** IE will run if IE Verified Boot is enabled even if this SS disables the IE.
IE SMBus Management Transport 0 - SMT 0 Configuration						
48	+ C0h	8	IE SMBus Management Transport (SMT) 0 - SMT 0 SMBus Enable	0x0; SMT0 disabled 0x1; SMT0 enabled	0x1	Tells the SoC that SMT0 is enabled and connected to the SMBus. Disabled means that the device is not connected to the SMBus Pins.
52	+ D0h	17:16	IE SMBus Management Transport (SMT) 0 - SMBus Clock	0x1; Standard (100 KHz) 0x2; Fast Mode (400 KHz) 0x3; Fast Mode Plus (1 MHz)	0x1	Tells the SoC the speed the physical bus must operate at. **Note:** It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed.
50	+ C8h	8	IE SMBus Management Transport (SMT) 0 - Host SMBus Address Enable	0x0; Host SMBus Target Address disabled 0x1; Host SMBus Target Address enabled	0x0	Tells the SoC SMT controller that it is the SMBus segment owner and any device sending a request to Address 10h should be claimed by the SMT controller. When set, enables HW to accept write cycles targeting address 10h and enables target logic to ACK Host SMBus address (10h) on the SMBus. **Note:** This bit must be set to "1" when HW is configured to support MCTP and chipset is the SMBus Segment Owner.
48	+ C0h	16	IE SMBus Management Transport (SMT) 0 - General Purpose (GP) Target Address Enable	0x0; GP Target Address is Disabled 0x1; GP Target Address is Enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. (Address Enable Bit) **Note:** The 'Enable' for this address is programmed through this soft strap. HW does not take any action based on the value of this soft strap. It is simply provided to FW for reading.
48	+ C0h	23:17	IE SMBus Management Transport (SMT) 0 - General Purpose (GP) Target Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. **Note:** This address has to be configured so that it does not conflict with other devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 39 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
49	+ C4h	16	IE SMBus Management Transport (SMT) 0 - I^2C Address Enable	0x0; I^2C Target Address disabled 0x1; I^2C Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave over I^2C (Address Enable Bit)
48	+ C0h	30:24	IE SMBus Management Transport (SMT) 0 - I^2C Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave over I^2C. **Notes:** -I^2C address of the SMT logic for support of I^2C target. All I^2C protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.I2C_EN register is set. -This address has to be configured so that it does not conflict with other devices on the SMBus network.
49	+ C4h	24	IE SMBus Management Transport (SMT) 0 - Alert Sending Device (ASD) Address Enable	0x0; ASD Target Address disabled 0x1; ASD Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. (Address Enable Bit)
49	+ C4h	6:0	IE SMBus Management Transport (SMT) 0 - Alert Sending Device (ASD) Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network. -SMBus address of the SMT logic for support of ASF protocol. All ASF protocol transactions targeting this address will be ACKed by the HW if the TPOLICY.ASD_EN register is set.
50	+ C8h	0	IE SMBus Management Transport (SMT) 0 - MCTP Address Enable	0x0; MCTP Target Address disabled 0x1; MCTP Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. (Address Enable Bit)
49	+ C4h	14:8	IE SMBus Management Transport (SMT) 0 - MCTP Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. **Note:** MCTP address of the SMT logic. All MCTP protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.MCTP_EN register is set.

Table 4-3. Flash Descriptor Soft Straps (Sheet 40 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
50	+ C8h	31:16	IE SMBus Management Transport (SMT) 0 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
51	+ CCh	15:0	IE SMBus Management Transport (SMT) 0 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the ASF UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.
51	+ CCh	31:16	IE SMBus Management Transport (SMT) 0 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
52	+ D0h	15:0	IE SMBus Management Transport (SMT) 0 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Note:** To be configured in conjunction with the MCTP UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 41 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
IE SMBus Management Transport 1 - SMT 1 Configuration						
53	+ D4h	8	IE SMBus Management Transport (SMT) 1 - SMT 1 SMBus Enable	0x0; SMT1 disabled 0x1; SMT1 enabled	0x1	Tells the SoC that SMT1 is enabled and connected to the SMBus. Disabled means that the device is not connected to the SMBus Pins.
57	+ E4h	17:16	IE SMBus Management Transport (SMT) 1 - SMBus Clock	0x1; Standard (100 KHz) 0x2; Fast Mode (400 KHz) 0x3; Fast Mode Plus (1 MHz)	0x1	Tells the SoC the speed the physical bus must operate at. **Note:** It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed.
55	+ DCh	8	IE SMBus Management Transport (SMT) 1 - Host SMBus Address Enable	0x0; Host SMBus Target Address disabled 0x1; Host SMBus Target Address enabled	0x0	Tells the SoC SMT controller that it is the SMBus segment owner and any device sending a request to Address 10h should be claimed by the SMT controller. When set, enables HW to accept write cycles targeting address 10h and enables target logic to ACK Host SMBus address (10h) on the SMBus. **Note:** This bit must be set to **"1"** when HW is configured to support MCTP and chipset is the SMBus Segment Owner.
53	+ D4h	16	IE SMBus Management Transport (SMT) 1 - General Purpose (GP) Target Address Enable	0x0; GP Target Address is Disabled 0x1; GP Target Address is Enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. (Address Enable Bit) **Note:** The 'Enable' for this address is programmed through this soft strap. HW does not take any action based on the value of this soft strap. It is simply provided to FW for reading.
53	+ D4h	23:17	IE SMBus Management Transport (SMT) 1 - GP Target Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. **Note:** This address has to be configured so that it does not conflict with other devices on the SMBus network.
54	+ D8h	16	IE SMBus Management Transport (SMT) 1 - I^2C Address Enable	0x0; I^2C Target Address disabled 0x1; I^2C Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave over I^2C (Address Enable Bit)

Table 4-3. Flash Descriptor Soft Straps (Sheet 42 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
53	+ D4h	30:24	IE SMBus Management Transport (SMT) 1 - I^2C Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave over I^2C. **Notes:** -I^2C address of the SMT logic for support of I^2C target. All I^2C protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.I2C_EN register is set. -This address has to be configured so that it does not conflict with other devices on the SMBus network.
54	+ D8h	24	IE SMBus Management Transport (SMT) 1 - Alert Sending Device (ASD) AddressEnable	0x0; ASD Target Address disabled 0x1; ASD Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. (Address Enable Bit)
54	+ D8h	6:0	IE SMBus Management Transport (SMT) 1 - Alert Sending Device (ASD) Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network. -SMBus address of the SMT logic for support of ASF protocol. All ASF protocol transactions targeting this address will be ACKed by the HW if the TPOLICY.ASD_EN register is set.
55	+ DCh	0	IE SMBus Management Transport (SMT) 1 - MCTP Address Enable	0x0; MCTP Target Address disabled 0x1; MCTP Target Address enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. (Address Enable Bit)
54	+ D8h	14:8	IE SMBus Management Transport (SMT) 1 - MCTP Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. **Note:** MCTP address of the SMT logic. All MCTP protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.MCTP_EN register is set.
55	+ DCh	31:16	IE SMBus Management Transport (SMT) 1 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Notes:** -To be configured in conjunction with the ASF UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 43 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
56	+ E0h	15:0	IE SMBus Management Transport (SMT) 1 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Notes:** -To be configured in conjunction with the ASF UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.
56	+ E0h	31:16	IE SMBus Management Transport (SMT) 1 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Notes:** -To be configured in conjunction with the MCTP UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
57	+ E4h	15:0	IE SMBus Management Transport (SMT) 1 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Notes:** -To be configured in conjunction with the MCTP UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 44 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
IE SMBus Management Transport 2 - SMT 2 Configuration						
58	+ E8h	8	IE SMBus Management Transport (SMT) 2 - SMT 2 SMBus Enable	0x0; SMT2 disabled 0x1; SMT2 enabled	0x1	Tells the SoC that SMT2 is enabled and connected to the SMBus. Disabled means that the device is not connected to the SMBus Pins.
62	+ F8h	17:16	IE SMBus Management Transport (SMT) 2 - SMBus Clock	0x1; Standard (100 KHz) 0x2; Fast Mode (400 KHz) 0x3; Fast Mode Plus (1 MHz)	0x1	Tells the SoC the speed the physical bus must operate at. **Note:** It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed.
60	+ F0h	8	IE SMBus Management Transport (SMT) 2 - Host SMBus Address Enable	0x0; Host SMBus Target Address disabled 0x1; Host SMBus Target Address enabled	0x00	Tells the SoC SMT controller that it is the SMBus segment owner and any device sending a request to Address 10h should be claimed by the SMT controller. When set, enables HW to accept write cycles targeting address 10h and enables target logic to ACK Host SMBus address (10h) on the SMBus. **Note:** This bit must be set to "1" when HW is configured to support MCTP and chipset is the SMBus Segment Owner.
58	+ E8h	16	IE SMBus Management Transport (SMT) 2 - General Purpose (GP) Target Address Enable	0x0; GP Target Address is Disabled 0x1; GP Target Address is Enabled	0x0	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. (Address Enable Bit) **Note:** The 'Enable' for this address is programmed through this soft strap. HW does not take any action based on the value of this soft strap. It is simply provided to FW for reading.
58	+ E8h	23:17	IE SMBus Management Transport (SMT) 2 - General Purpose (GP) Target Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate with externally initiated Block Read commands. **Note:** This address has to be configured so that it does not conflict with other devices on the SMBus network.
59	+ ECh	16	IE SMBus Management Transport (SMT) 2 - I^2C Address Enable	0x0; I^2C Target Address disabled 0x1; I^2C Target Address enabled	0x00	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave over I^2C (Address Enable Bit)

Table 4-3. Flash Descriptor Soft Straps (Sheet 45 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
58	+ E8h	30:24	IE SMBus Management Transport (SMT) 2 - I^2C Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave over I^2C. **Notes:** -I^2C address of the SMT logic for support of I^2C target. All I^2C protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.I2C_EN register is set. -This address has to be configured so that it does not conflict with other devices on the SMBus network.
59	+ ECh	24	IE SMBus Management Transport (SMT) 2 - Alert Sending Device (ASD) AddressEnable	0x0; ASD Target Address disabled 0x1; ASD Target Address enabled	0x00	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. (Address Enable Bit)
59	+ ECh	6:0	IE SMBus Management Transport (SMT) 2 - Alert Sending Device (ASD) Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using ASD protocol. **Notes:** -This address has to be configured so that it does not conflict with other devices on the SMBus network. -SMBus address of the SMT logic for support of ASF protocol. All ASF protocol transactions targeting this address will be ACKed by the HW if the TPOLICY.ASD_EN register is set.
60	+ F0h	0	IE SMBus Management Transport (SMT) 2 - MCTP Address Enable	0x0; MCTP Target Address disabled 0x1; MCTP Target Address enabled	0x00	Tells the SoC to enable the target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. (Address Enable Bit)
59	+ ECh	14:8	IE SMBus Management Transport (SMT) 2 - MCTP Address	Value: Hex	0x00	Tells the SoC the 7-bit configurable target slave address of the SMT Controller so that it can communicate as a slave using MCTP protocol. **Note:** MCTP address of the SMT logic. All MCTP protocol transactions targeting this address will be ACKd by the HW if the TPOLICY.MCTP_EN register is set.
60	+ F0h	31:16	IE SMBus Management Transport (SMT) 2 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Notes:** -To be configured in conjunction with the ASF UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 46 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
61	+ F4h	15:0	IE SMBus Management Transport (SMT) 2 - Alert Standard Format (ASF) Unique Device Identifier (UDID) B118 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the ASF UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Notes:** -To be configured in conjunction with the ASF UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.
61	+ F4h	31:16	IE SMBus Management Transport (SMT) 2 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Vendor ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Vendor ID: Enter a 16 bit subsystem Vendor ID **Notes:** -To be configured in conjunction with the MCTP UDID Subsystem Device ID Soft Strap -The master uses this to query devices on the SMBus network.
62	+ F8h	15:0	IE SMBus Management Transport (SMT) 2 - MCTP Unique Device Identifier (UDID) B1512 (Subsystem Device ID)	Value: Hex	0x0000	Tells the SoC the MCTP UDID Subsystem Device ID: Enter a 16 bit subsystem Device ID **Notes:** -To be configured in conjunction with the MCTP UDID Subsystem Vendor ID Soft Strap -The master uses this to query devices on the SMBus network.

Table 4-3. Flash Descriptor Soft Straps (Sheet 47 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
Reserved						
0	+ 0h	31:7	RESERVED	N/A	0x0000	Reserved
1	+ 4h	0	RESERVED	N/A	0x1	Reserved
1	+ 4h	4:1	RESERVED	N/A	0x0	Reserved
1	+ 4h	5	RESERVED	N/A	0x1	Reserved
1	+ 4h	9:6	RESERVED	N/A	0x1	Reserved
1	+ 4h	10	RESERVED	N/A	0x1	Reserved
1	+ 4h	14:11	RESERVED	N/A	0x3	Reserved
1	+ 4h	19:16	RESERVED	N/A	0x2	Reserved
1	+ 4h	30:27	RESERVED	N/A	0x00	Reserved
1	+ 4h	31	RESERVED	N/A	0x0	Reserved
2	+ 8h	31:1	RESERVED	N/A	0x00000000	Reserved
3	+ Ch	31:1	RESERVED	N/A	0x00000000	Reserved
4	+ 10h	0	RESERVED	N/A	0x0	Reserved
4	+ 10h	1	RESERVED	N/A	0x1	Reserved
4	+ 10h	2	RESERVED	N/A	0x0	Reserved
4	+ 10h	3	RESERVED	N/A	0x0	Reserved
4	+ 10h	4	RESERVED	N/A	0x1	Reserved
4	+ 10h	5	RESERVED	N/A	0x0	Reserved
4	+ 10h	6	RESERVED	N/A	0x1	Reserved
4	+ 10h	7	RESERVED	N/A	0x1	Reserved
4	+ 10h	11:10	RESERVED	N/A	0x0	Reserved
4	+ 10h	12	RESERVED	N/A	0x0	Reserved
4	+ 10h	13	RESERVED	N/A	0x0	Reserved
4	+ 10h	14	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 48 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
4	+ 10h	15	RESERVED	N/A	0x1	Reserved
4	+ 10h	18:16	RESERVED	N/A	0x0	Reserved
4	+ 10h	19	RESERVED	N/A	0x0	Reserved
4	+ 10h	20	RESERVED	N/A	0x0	Reserved
4	+ 10h	22:21	RESERVED	N/A	0x0	Reserved
4	+ 10h	23	RESERVED	N/A	0x1	Reserved
4	+ 10h	24	RESERVED	N/A	0x0	Reserved
4	+ 10h	25	RESERVED	N/A	0x1	Reserved
4	+ 10h	26	RESERVED	N/A	0x0	Reserved
4	+ 10h	27	RESERVED	N/A	0x0	Reserved
4	+ 10h	28	RESERVED	N/A	0x0	Reserved
4	+ 10h	29	RESERVED	N/A	0x0	Reserved
4	+ 10h	30	RESERVED	N/A	0x0	Reserved
4	+ 10h	31	RESERVED	N/A	0x1	Reserved
5	+ 14h	9	RESERVED	N/A	0x0	Reserved
5	+ 14h	10	RESERVED	N/A	0x0	Reserved
5	+ 14h	11	RESERVED	N/A	0x0	Reserved
5	+ 14h	12	RESERVED	N/A	0x0	Reserved
5	+ 14h	13	RESERVED	N/A	0x0	Reserved
5	+ 14h	14	RESERVED	N/A	0x0	Reserved
5	+ 14h	15	RESERVED	N/A	0x0	Reserved
5	+ 14h	16	RESERVED	N/A	0x0	Reserved
5	+ 14h	18	RESERVED	N/A	0x0	Reserved
5	+ 14h	31:21	RESERVED	N/A	0x000	Reserved
6	+ 18h	3:0	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 49 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
6	+ 18h	7:4	RESERVED	N/A	0x0	Reserved
6	+ 18h	15:12	RESERVED	N/A	0x0	Reserved
6	+ 18h	23:18	RESERVED	N/A	0x00	Reserved
6	+ 18h	24	RESERVED	N/A	0x0	Reserved
6	+ 18h	25	RESERVED	N/A	0x0	Reserved
6	+ 18h	26	RESERVED	N/A	0x0	Reserved
6	+ 18h	27	RESERVED	N/A	0x0	Reserved
6	+ 18h	28	RESERVED	N/A	0x0	Reserved
6	+ 18h	30	RESERVED	N/A	0x0	Reserved
6	+ 18h	31	RESERVED	N/A	0x0	Reserved
7	+ 1Ch	0	RESERVED	N/A	0x0	Reserved
7	+ 1Ch	3:2	RESERVED	N/A	0x0	Reserved
7	+ 1Ch	31:8	RESERVED	N/A	0x000000 00	Reserved
8	+ 20h	15:0	RESERVED	N/A	0x0000	Reserved
8	+ 20h	23:16	RESERVED	N/A	0x77	Reserved
8	+ 20h	31:24	RESERVED	N/A	0x78	Reserved
9	+ 24h	7	RESERVED	N/A	0x0	Reserved
9	+ 24h	14	RESERVED	N/A	0x0	Reserved
9	+ 24h	15	RESERVED	N/A	0x0	Reserved
9	+ 24h	16	RESERVED	N/A	0x0	Reserved
9	+ 24h	19:17	RESERVED	N/A	0x0	Reserved
9	+ 24h	22:20	RESERVED	N/A	0x0	Reserved
9	+ 24h	23	RESERVED	N/A	0x0	Reserved
9	+ 24h	24	RESERVED	N/A	0x0	Reserved
9	+ 24h	28	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 50 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
9	+ 24h	29	RESERVED	N/A	0x0	Reserved
10	+ 28h	3:0	RESERVED	N/A	0x5	Reserved
10	+ 28h	6:4	RESERVED	N/A	0x0	Reserved
10	+ 28h	7	RESERVED	N/A	0x0	Reserved
10	+ 28h	13:11	RESERVED	N/A	0x00	Reserved
10	+ 28h	15	RESERVED	N/A	0x0	Reserved
10	+ 28h	23:16	RESERVED	N/A	0x00	Reserved
10	+ 28h	31:24	RESERVED	N/A	0x00	Reserved
12	+ 30h	0	RESERVED	N/A	0x0	Reserved
12	+ 30h	1	RESERVED	N/A	0x0	Reserved
12	+ 30h	2	RESERVED	N/A	0x0	Reserved
12	+ 30h	5:3	RESERVED	N/A	0x0	Reserved
12	+ 30h	7:6	RESERVED	N/A	0x0	Reserved
12	+ 30h	8	RESERVED	N/A	0x0	Reserved
12	+ 30h	9	RESERVED	N/A	0x1	Reserved
12	+ 30h	11:10	RESERVED	N/A	0x0	Reserved
12	+ 30h	12	RESERVED	N/A	0x0	Reserved
12	+ 30h	15:13	RESERVED	N/A	0x0	Reserved
12	+ 30h	18:16	RESERVED	N/A	0x0	Reserved
12	+ 30h	20:19	RESERVED	N/A	0x0	Reserved
12	+ 30h	21	RESERVED	N/A	0x0	Reserved
12	+ 30h	22	RESERVED	N/A	0x1	Reserved
12	+ 30h	23	RESERVED	N/A	0x0	Reserved
12	+ 30h	24	RESERVED	N/A	0x0	Reserved
12	+ 30h	25	RESERVED	N/A	0x1	Reserved
12	+ 30h	28:26	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 51 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
12	+ 30h	31:29	RESERVED	N/A	0x0	Reserved
13	+ 34h	0	RESERVED	N/A	0x0	Reserved
13	+ 34h	1	RESERVED	N/A	0x0	Reserved
13	+ 34h	7:2	RESERVED	N/A	0x00	Reserved
13	+ 34h	8	RESERVED	N/A	0x0	Reserved
13	+ 34h	11:9	RESERVED	N/A	0x0	Reserved
13	+ 34h	14:12	RESERVED	N/A	0x0	Reserved
13	+ 34h	15	RESERVED	N/A	0x0	Reserved
13	+ 34h	18:16	RESERVED	N/A	0x0	Reserved
13	+ 34h	19	RESERVED	N/A	0x0	Reserved
13	+ 34h	21:20	RESERVED	N/A	0x1	Reserved
13	+ 34h	22	RESERVED	N/A	0x0	Reserved
13	+ 34h	23	RESERVED	N/A	0x0	Reserved
13	+ 34h	26:24	RESERVED	N/A	0x0	Reserved
13	+ 34h	31:27	RESERVED	N/A	0x00	Reserved
14	+ 38h	0	RESERVED	N/A	0x0000	Reserved
14	+ 38h	20:18	RESERVED	N/A	0x0	Reserved
14	+ 38h	31:22	RESERVED	N/A	0x000	Reserved
15	+ 3Ch	0	RESERVED	N/A	0x1	Reserved
15	+ 3Ch	1	RESERVED	N/A	0x0	Reserved
15	+ 3Ch	7:3	RESERVED	N/A	0x00	Reserved
15	+ 3Ch	15:13	RESERVED	N/A	0x0	Reserved
16	+ 40h	31	RESERVED	N/A	0x0	Reserved
17	+ 44h	31:7	RESERVED	N/A	0x0000000	Reserved
18	+ 48h	31:0	RESERVED	N/A	0x0000000 00	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 52 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
19	+ 4Ch	1:0	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	2	RESERVED	N/A	0x1	Reserved
19	+ 4Ch	5:3	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	6	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	7	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	15:14	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	16	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	17	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	18	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	19	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	20	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	21	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	23:22	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	24	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	25	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	26	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	27	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	28	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	29	RESERVED	N/A	0x0	Reserved
19	+ 4Ch	31:30	RESERVED	N/A	0x0	Reserved
20	+ 50h	17:16	RESERVED	N/A	0x0	Reserved
20	+ 50h	19:18	RESERVED	N/A	0x0	Reserved
20	+ 50h	21:20	RESERVED	N/A	0x0	Reserved
20	+ 50h	23:22	RESERVED	N/A	0x0	Reserved
21	+ 54h	0	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 53 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
21	+ 54h	1	RESERVED	N/A	0x0	Reserved
21	+ 54h	2	RESERVED	N/A	0x0	Reserved
21	+ 54h	3	RESERVED	N/A	0x0	Reserved
21	+ 54h	4	RESERVED	N/A	0x0	Reserved
21	+ 54h	5	RESERVED	N/A	0x0	Reserved
21	+ 54h	6	RESERVED	N/A	0x0	Reserved
21	+ 54h	7	RESERVED	N/A	0x0	Reserved
21	+ 54h	8	RESERVED	N/A	0x0	Reserved
21	+ 54h	9	RESERVED	N/A	0x0	Reserved
21	+ 54h	10	RESERVED	N/A	0x0	Reserved
21	+ 54h	11	RESERVED	N/A	0x0	Reserved
21	+ 54h	12	RESERVED	N/A	0x0	Reserved
21	+ 54h	13	RESERVED	N/A	0x0	Reserved
21	+ 54h	14	RESERVED	N/A	0x0	Reserved
21	+ 54h	15	RESERVED	N/A	0x0	Reserved
21	+ 54h	31:26	RESERVED	N/A	0x0	Reserved
22	+ 58h	6:4	RESERVED	N/A	0x0	Reserved
22	+ 58h	9:7	RESERVED	N/A	0x0	Reserved
22	+ 58h	12:10	RESERVED	N/A	0x0	Reserved
22	+ 58h	15:13	RESERVED	N/A	0x0	Reserved
22	+ 58h	17:16	RESERVED	N/A	0x2	Reserved
22	+ 58h	19:18	RESERVED	N/A	0x2	Reserved
22	+ 58h	21:20	RESERVED	N/A	0x2	Reserved
22	+ 58h	23:22	RESERVED	N/A	0x2	Reserved
23	+ 5Ch	9:8	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 54 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
23	+ 5Ch	10	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	11	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	12	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	13	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	14	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	15	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	16	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	17	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	18	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	19	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	20	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	21	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	22	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	23	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	24	RESERVED	N/A	0x0	Reserved
23	+ 5Ch	31:29	RESERVED	N/A	0x0	Reserved
24	+ 60h	6:4	RESERVED	N/A	0x0	Reserved
24	+ 60h	9:7	RESERVED	N/A	0x0	Reserved
24	+ 60h	12:10	RESERVED	N/A	0x0	Reserved
24	+ 60h	15:13	RESERVED	N/A	0x0	Reserved
24	+ 60h	17:16	RESERVED	N/A	0x2	Reserved
24	+ 60h	19:18	RESERVED	N/A	0x2	Reserved
24	+ 60h	21:20	RESERVED	N/A	0x2	Reserved
24	+ 60h	23:22	RESERVED	N/A	0x2	Reserved
25	+ 64h	9:8	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 55 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
25	+ 64h	10	RESERVED	N/A	0x0	Reserved
25	+ 64h	11	RESERVED	N/A	0x0	Reserved
25	+ 64h	12	RESERVED	N/A	0x0	Reserved
25	+ 64h	13	RESERVED	N/A	0x0	Reserved
25	+ 64h	14	RESERVED	N/A	0x0	Reserved
25	+ 64h	15	RESERVED	N/A	0x0	Reserved
25	+ 64h	16	RESERVED	N/A	0x0	Reserved
25	+ 64h	17	RESERVED	N/A	0x0	Reserved
25	+ 64h	18	RESERVED	N/A	0x0	Reserved
25	+ 64h	19	RESERVED	N/A	0x0	Reserved
25	+ 64h	20	RESERVED	N/A	0x0	Reserved
25	+ 64h	21	RESERVED	N/A	0x0	Reserved
25	+ 64h	22	RESERVED	N/A	0x0	Reserved
25	+ 64h	23	RESERVED	N/A	0x0	Reserved
25	+ 64h	24	RESERVED	N/A	0x0	Reserved
25	+ 64h	31:29	RESERVED	N/A	0x0	Reserved
26	+ 68h	16	RESERVED	N/A	0x0	Reserved
26	+ 68h	17	RESERVED	N/A	0x0	Reserved
26	+ 68h	18	RESERVED	N/A	0x0	Reserved
26	+ 68h	19	RESERVED	N/A	0x0	Reserved
26	+ 68h	20	RESERVED	N/A	0x0	Reserved
26	+ 68h	21	RESERVED	N/A	0x0	Reserved
26	+ 68h	22	RESERVED	N/A	0x0	Reserved
26	+ 68h	23	RESERVED	N/A	0x0	Reserved
26	+ 68h	31:24	RESERVED	N/A	0x00	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 56 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
27	+ 6Ch	16	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	17	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	18	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	19	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	20	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	21	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	22	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	23	RESERVED	N/A	0x0	Reserved
27	+ 6Ch	31:24	RESERVED	N/A	0x00	Reserved
28	+ 70h	0	RESERVED	N/A	0x0	Reserved
28	+ 70h	1	RESERVED	N/A	0x0	Reserved
28	+ 70h	2	RESERVED	N/A	0x0	Reserved
28	+ 70h	3	RESERVED	N/A	0x0	Reserved
28	+ 70h	31:4	RESERVED	N/A	0x0000000	Reserved
29	+ 74h	0	RESERVED	N/A	0x0	Reserved
29	+ 74h	1	RESERVED	N/A	0x0	Reserved
29	+ 74h	2	RESERVED	N/A	0x0	Reserved
29	+ 74h	3	RESERVED	N/A	0x0	Reserved
29	+ 74h	31:4	RESERVED	N/A	0x0000000	Reserved
30	+ 78h	31:2	RESERVED	N/A	0x0000000	Reserved
31	+ 7Ch	0	RESERVED	N/A	0x0	Reserved
31	+ 7Ch	7:1	RESERVED	N/A	0x00	Reserved
31	+ 7Ch	15:9	RESERVED	N/A	0x00	Reserved
31	+ 7Ch	31	RESERVED	N/A	0x0	Reserved
32	+ 80h	7	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 57 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
32	+ 80h	15	RESERVED	N/A	0x0	Reserved
32	+ 80h	23:17	RESERVED	N/A	0x00	Reserved
32	+ 80h	31:25	RESERVED	N/A	0x00	Reserved
33	+ 84h	7:1	RESERVED	N/A	0x00	Reserved
33	+ 84h	15:9	RESERVED	N/A	0x00	Reserved
35	+ 8Ch	31:18	RESERVED	N/A	0x0000	Reserved
36	+ 90h	0	RESERVED	N/A	0x0	Reserved
36	+ 90h	7:1	RESERVED	N/A	0x00	Reserved
36	+ 90h	15:9	RESERVED	N/A	0x00	Reserved
36	+ 90h	31	RESERVED	N/A	0x0	Reserved
37	+ 94h	7	RESERVED	N/A	0x0	Reserved
37	+ 94h	15	RESERVED	N/A	0x0	Reserved
37	+ 94h	23:17	RESERVED	N/A	0x00	Reserved
37	+ 94h	31:25	RESERVED	N/A	0x00	Reserved
38	+ 98h	7:1	RESERVED	N/A	0x00	Reserved
38	+ 98h	15:9	RESERVED	N/A	0x00	Reserved
40	+ A0h	31:18	RESERVED	N/A	0x0000	Reserved
41	+ A4h	0	RESERVED	N/A	0x0	Reserved
41	+ A4h	7:1	RESERVED	N/A	0x0000	Reserved
41	+ A4h	15:9	RESERVED	N/A	0x0000	Reserved
41	+ A4h	31	RESERVED	N/A	0x0	Reserved
42	+ A8h	7	RESERVED	N/A	0x0	Reserved
42	+ A8h	15	RESERVED	N/A	0x0	Reserved
42	+ A8h	23:17	RESERVED	N/A	0x00	Reserved
42	+ A8h	31:25	RESERVED	N/A	0x00	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 58 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
43	+ ACh	7:1	RESERVED	N/A	0x00	Reserved
43	+ ACh	15:9	RESERVED	N/A	0x00	Reserved
45	+ B4h	31:18	RESERVED	N/A	0x0000	Reserved
46	+ B8h	31:0	RESERVED	N/A	0x00000000	Reserved
47	+ BCh	0	RESERVED	N/A	0x0	Reserved
47	+ BCh	1	RESERVED	N/A	0x0	Reserved
47	+ BCh	12:2	RESERVED	N/A	0x000	Reserved
47	+ BCh	31:15	RESERVED	N/A	0x00000	Reserved
48	+ C0h	0	RESERVED	N/A	0x0	Reserved
48	+ C0h	7:1	RESERVED	N/A	0x00	Reserved
48	+ C0h	15:9	RESERVED	N/A	0x00	Reserved
48	+ C0h	31	RESERVED	N/A	0x0	Reserved
49	+ C4h	7	RESERVED	N/A	0x0	Reserved
49	+ C4h	15	RESERVED	N/A	0x0	Reserved
49	+ C4h	23:17	RESERVED	N/A	0x00	Reserved
49	+ C4h	31:25	RESERVED	N/A	0x00	Reserved
50	+ C8h	7:1	RESERVED	N/A	0x00	Reserved
50	+ C8h	15:9	RESERVED	N/A	0x00	Reserved
52	+ D0h	31:18	RESERVED	N/A	0x0000	Reserved
53	+ D4h	0	RESERVED	N/A	0x0	Reserved
53	+ D4h	7:1	RESERVED	N/A	0x00	Reserved
53	+ D4h	15:9	RESERVED	N/A	0x00	Reserved
53	+ D4h	31	RESERVED	N/A	0x0	Reserved
54	+ D8h	7	RESERVED	N/A	0x0	Reserved
54	+ D8h	15	RESERVED	N/A	0x0	Reserved

Table 4-3. Flash Descriptor Soft Straps (Sheet 59 of 59)

FITC SoC SS #	FPSBA + Offset	Bits	Soft Strap Name	Soft Strap Value List	Default Value	Description
54	+ D8h	23:17	RESERVED	N/A	0x00	Reserved
54	+ D8h	31:25	RESERVED	N/A	0x00	Reserved
55	+ DCh	7:1	RESERVED	N/A	0x00	Reserved
55	+ DCh	15:9	RESERVED	N/A	0x00	Reserved
57	+ E4h	31:18	RESERVED	N/A	0x0000	Reserved
58	+ E8h	0	RESERVED	N/A	0x0	Reserved
58	+ E8h	7:1	RESERVED	N/A	0x00	Reserved
58	+ E8h	15:9	RESERVED	N/A	0x00	Reserved
58	+ E8h	31	RESERVED	N/A	0x0	Reserved
59	+ ECh	7	RESERVED	N/A	0x0	Reserved
59	+ ECh	15	RESERVED	N/A	0x00	Reserved
59	+ ECh	23:17	RESERVED	N/A	0x00	Reserved
59	+ ECh	31:25	RESERVED	N/A	0x00	Reserved
60	+ F0h	7:1	RESERVED	N/A	0x00	Reserved
60	+ F0h	15:9	RESERVED	N/A	0x00	Reserved
62	+ F8h	31:18	RESERVED	N/A	0x0000	Reserved

4.3 Fuses Pertaining to the Innovation Engine (IE)

Note: **Intel recommends that customers perform the IE manufacturing lock step described below, even if not using the Innovation Engine, to eliminate any in field security risk.**

There is a set of fuses pertaining to the Innovation Engine (IE) that must be configured with an Intel in-field fuse programming tool. See Figure 4-3, "IE Fuses." These fuses have to be programmed as a security measure to set the hash of the public cryptographic key by the OEM in order for them to use the IE. After the hash of the public key is set, the tool will complete an IE manufacturing lock process flow to finalize the IE. For more information, refer to Chapter 37, "Innovation Engine."

Figure 4-3. IE Fuses



§ §

5 System Agent and Root Complex

5.1 Introduction

The SoC contains a System Agent block that provides the main interface with the processor cores and the other integrated elements. The I/O Fabric provides the connections to the PCI Express* Root Ports and the integrated I/O devices.

The system agent and memory fabric includes the coherence engine for handling all the coherent transactions, data-path to merge coherent and non-coherent traffic, write combining buffers to merge both coherent and non-coherent partial writes and provide the single point of global observation for all transactions. The coherent and memory fabric interfaces to I/O devices through a standard I/O Fabric root complex.

Figure 5-1. What is Covered in This Chapter



Table 5-1. References

Reference	Revision	Date	Document Title
PCI Express*	3.1	March 4, 2009	*PCI Express Base Specification Revision 3.0*
Software Developer's Manual (SDM)	-	-	*Intel® 64 and IA-32 Architectures Software Developer's Manual*

5.2 Features

- 40-bit physical, 48-bit linear memory-space addressing
- 20 programmable isolated memory regions (IMR)
- Patrol scrub engine performs a DDR memory scrub to fix correctable memory errors in the background
- Support for xAPIC interrupt architecture:
  - Legacy interrupts (SMI#, INIT#, INTR#, NMI) from IO agents
- Support for x2APIC:
  - In x2APIC mode, APIC registers are accessed through Model Specific Register (MSR) interfaces.
- PCI Express Advanced Error Reporting (AER) support
- MSI signaling
- INTx signaling
- Internal command and data path parity coverage
- Internal RAM parity coverage

5.3 Root Complex

The Host Root Complex, also called the Primary Scalable Fabric (PSF), implements the bus 0 interconnect of a PCI Express* Root Complex. The root complex contains the internal Root Complex Event Collector (RCEC) which is a sub-agent of the Primary to Side Band Bridge (P2SB). The Root Complex is also where the Global and Local Error control and reporting are located as well as most of the SoC Reliability, Availability, and Serviceability (RAS) capabilities. See Chapter 6, “Reliability, Availability and Serviceability (RAS)”.

There is a PCI hierarchy for the Host/IA cores, a hierarchy for Innovation Engine (IE), and one for the Intel® Management Engine (Intel® ME).

5.4 Register Map

Figure 5-2 shows the associated registers from a system software viewpoint.

Figure 5-2. Register Map



5.4.1 Registers in Configuration Space

Table 5-2. Registers in Host Configuration Space

Configuration Space of B0:D0:F0 (hex)	Register Short Name	Description
0	DEVICE_ID_VENDOR_ID_0_0_0_PCI	Device ID and Vendor ID Register
4	PCI_STATUS_COMMAND_0_0_0_PCI	PCI Status and PCI Command Register
8	REVISION_ID_CLASS_CODE_0_0_0_PCI	PCI Revision ID and PCI Class Code Register
C	MASTER_LATENCY_TIME_0_0_0_PCI	Master Latency Timer and Header Type Register
2C	SVID_SID_0_0_0_PCI	PCI Subsystem Vendor ID and PCI Subsystem ID
34	CAPPTR_0_0_0_PCI	Capability Register Pointer
48	MCHBAR_LO_0_0_0_PCI	Memory Controller Hub Base Address Register
4C	MCHBAR_HI_0_0_0_PCI	Memory Controller Hub Base Address Register
60	PCIEXBAR_LO_0_0_0_PCI	PCI Express Enhanced Configuration Range Base Address Low
64	PCIEXBAR_HI_0_0_0_PCI	PCI Express Enhanced Configuration Range Base Address High
A8	TOUUD_LO_0_0_0_PCI	Top of Upper Usable DRAM Low
AC	TOUUD_HI_0_0_0_PCI	Top of Upper Usable DRAM High
BC	TOLUD_0_0_0_PCI	Top of Lower Usable DRAM
E0	CAPID0_CAPCTRL0_0_0_0_PCI	Capability ID0 Capability Control
E4	CAPID0_A_0_0_0_PCI	Capability ID0 A

§ §

6 Reliability, Availability and Serviceability (RAS)

6.1 SoC RAS Overview

This chapter describes the features provided by the SoC for the development of high RAS (Reliability, Availability, Serviceability) systems. RAS refers to three main features associated with system's robustness. These features are summarized as follows:

- **Reliability:** Refers to how often errors occur in the system, and whether the system can recover from an error condition.
- **Availability:** Refers to how flexible the system resources can be allocated or redistributed for the system utilizations and system recovery from errors.
- **Serviceability:** Refers to how well the system reports and handles events related to errors.

The SoC is designed to approach the RAS capabilities of Intel® Xeon® processors designed for servers.

6.2 Signal Descriptions

The signal descriptions pertaining to this chapter are shown in Table 6-1, "Signal Names and Descriptions". For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 26, "Customer General-Purpose I/O (GPIO)". The Direction/Type column of Table 6-1, "Signal Names and Descriptions" is interpreted as follows:

- O = Output signal. The SoC has driver circuit.

Table 6-1. Signal Names and Descriptions

Signal Name	Direction	Shared	Description
ERROR_N[0] ERROR_N[1] ERROR_N[2]	O	Yes	**Error:** These active-low signals indicate to the external circuitry the severity of a detected error: • ERROR_N[0] - Correctable Error • ERROR_N[1] - Non-Fatal Error • ERROR_N[2] - Fatal Error While the SoC active-low output signal PMU_PLTRST_N is asserted, these signals are not valid and must be ignored by the platform board circuitry.
IERR_N	O	Yes	**Internal Error:** This active-low signal indicates to the external circuitry that the SoC has detected an error. While the SoC active-low output signal PMU_PLTRST_N is asserted, this signal is not valid and must be ignored by the platform board circuitry.
MCERR_N	O	Yes	**Machine-Check Error:** This active-low signal indicates to the external circuitry that the SoC has detected a Machine Check error. While the SoC active-low output signal PMU_PLTRST_N is asserted, this signal is not valid and must be ignored by the platform board circuitry.

Table 6-2. References

Reference	Revision	Date	Document Title
Software Developer's Manual	-	-	*Intel® 64 and IA-32 Architectures Software Developer's Manual*
PCI Express* Specification	3.0	Nov. 10, 2010	*PCI Express Base Specification Revision 3.0*
ACPI Specification	5.0a	Nov. 13, 2013	*Advanced Configuration and Power Interface Specification Version 5.0, Errata A*

6.3 Feature Summary

- Machine Check Architecture (MCA) implemented which provides MCA Bank registers for Core, L2 Cache, System Agent, Memory Controller, and Power-Management Unit.
  - Error Cloaking and Dual Signaling (MSR 52h) to optionally hide errors from the operating system
  - Corrected Machine-Check error Interrupt (CMCI) that eliminates polling by generating a local interrupt based on programmable threshold values for accumulated MCA corrected errors
- Parity-protected internal data paths of the System Agent circuitry and the interface between the System Agent and the processor cores/L2-cache.
- Parity-protected command and data for the internal I/O system fabric. Parity errors are logged
- Memory Controllers supports ECC, data scrambling, patrol scrubbing and demand scrubbing
- Advanced Error Reporting (AER) supported which provides OS-level error recovery form system errors and also system debug:
  - PCI Express* Root Ports
  - Root Complex Integrated Endpoints: SMBus-Host function; Global/Local Integrated Error Handler (IEH) function
  - Integrated LAN Controllers
  - Integrated Intel® QuickAssist Technology (Intel® QAT) Controller
  - PCI Express* Root Ports (but not the Virtual Root Ports)
- Virtual partitioning with:
  - Enhanced Intel® Virtualization Technology (Intel® VT) for IA-32, Intel® 64 and Intel® Architecture (Intel® VT-x)
  - Intel® Virtualization Technology (Intel® VT) for Directed I/O (Intel® VT-d)
- Error Injection for validation of system error-handling software

6.4 Architectural Overview

This RAS chapter provides information related to the SoC error detection and error reporting mechanisms. The SoC provides Machine Check Architecture to detect and report hardware errors in the CPU cores, L2 Cache, system memory, and the SoC System Agent. The SoC also provides a set of Global Error Registers that are based on a number of Local Error Registers to detect and report SoC-internal hardware errors as well as hardware errors detected by the integrated I/O devices. A number of these I/O devices also support Advanced Error Reporting (AER) which is an optional PCI Express* Extended Capability.

In some cases, these mechanisms are configured to generate interrupts or system events.

Some SoC internal controllers provide ways of maintaining high levels of system availability when hardware errors are detected. Error-correcting logic, transaction retries, and degraded operation are examples.

6.4.1 Error Classification

The ACPI and PCIe* specifications classify errors. This classification separates hardware errors that result in degraded performance from those that result in functional failures:

- Correctable Errors
- Uncorrectable Errors

Uncorrectable hardware errors can be further classified as:

  — Non-Fatal Error

  — Fatal Error

In many cases, just the terms Correctable, Non-Fatal and Fatal are used to classify hardware errors.

6.4.2 Error Detection and Reporting Mechanisms

Machine Check Errors are defined for the SoC. See Section 6.6, "Machine Check Architecture (MCA)". They are accessible to software via Model Specific Registers (MSRs). Errors in the CPU cores, L2 cache, and System Agent are reported as Machine Check Error MSRs.

Besides SoC errors reported through the Machine Check Architecture (MCA), local device errors are detected, logged and reported by the SoC through Global Error registers. These registers are accessible to software via Host Root Configuration Space and Host Root Memory Space. System Agent and peripheral I/O device errors are reported in this manner. There are five types of local devices:

- PCIe Root Ports.
- PCIe Endpoints behind the Virtual Root Ports
- PCIe Root Complex Integrated Endpoints
- Legacy PCI devices
- Non-PCI devices

The manner in which each of the five local device types deals with local errors are explained in Section 6.13, "Overview of SoC Error Registers". There is a set of Global Error registers that summarize the Local Error registers and can be configured to generate an SMI or NMI.

In addition to providing software access to error registers, the SoC provides output signal pins to notify external hardware circuitry that an error has been detected. The severity of the error is also provided on signal pins. Descriptions for all five of these output signal pins are in Table 6-1, "Signal Names and Descriptions". External circuitry can use the SoC SMBus-PECI interface to read various internal registers containing error information.

6.5 Availability Features

6.5.1 System Memory

The SoC Memory Controllers support Single-Bit Error Correction using ECC. The controllers also provide Data Scrambling, Patrol Scrubbing and Demand Scrubbing.

6.5.1.1 Single Bit Error Correction

The memory controllers support ECC. Single-bit errors are corrected and Correctable Errors reported and logged.

6.5.1.2 DRAM Data Scrubbing

Data scrubbing features require the use of Error Correction Codes (ECC) in the system memory design.

Demand Scrubbing writes correct data back to memory for any read request that returns with a correctable data error. The DEMAND_SCRUB_ENABLE field (bit 3) of the B-Unit Control (B_CR_BCTRL2) register enables Demand Scrubbing when set to 1. The B_CR_BCTRL2 register is located in Host Root Memory Space at MCHBAR plus offset 6D70h.

Patrol Scrubbing ensures that data with a Correctable Error does not remain in DRAM long enough to stand a significant chance of further corruption and become an Uncorrectable Error. If enabled, the Patrol Scrubbing generates memory requests at a programmed interval. If a correctable error is detected by a scrubbing request, Demand Scrubbing is used to correct the error. The PAT_SCRUB_ENABLE field (bit 31) of the Patrol Scrub Configuration (DPATROL_SCRUB_CFG) register enables Patrol Scrubbing when set to 1. The DPATROL_SCRUB_CFG register is located in Host Root Memory Space at SBREG_BAR plus offset 10_00B0h. For Memory Controller 1, the DCS register is located at SBREG_BAR, offset 12_00B0h. Various registers first need to be setup by BIOS in order to deploy Patrol Scrubbing.

See Section 6.16, “Error Reporting Flow — Non-PCI devices” for SoC error reporting during scrubbing.

6.5.1.3 DRAM Data Scrambling

As an option, the SoC Memory Controllers provide DRAM Data Scrambling which is a technique to reduce noise on the internal power-supply rails and improve signal integrity. Across the 72 Data/ECC bits of the DQ/ECC bus, it drives very close to 50% ones and 50% zeros in every cycle. This eliminates the worst-case situation where all bits of the bus would simultaneously drive high or drive low.

Data Scrambling is available for both ECC and non-ECC memory platform designs.

Form Memory Controller 0, the SCRAMBLE_ENABLE field (bit 23) of the DRAM Control and Status (DCS) register, when set to 1, the data lanes (DDR0_DQ[63:0]) and the ECC lanes (DDR0_ECC[7:0]) will be scrambled, otherwise no scrambling will occur. The DCS register is located in Host Root Memory Space at SBREG_BAR plus offset 10_0170h. For Memory Controller 1, the DCS register is located at SBREG_BAR, offset 12_0170h.

6.5.2 PCI Express Root Ports

The *PCI Express Base Specification*, Revision 3.0 defines a standard set of error-reporting mechanisms. The SoC supports them all including Error Poisoning and Advanced Error Reporting (AER). The error reporting mechanism and the error registers are described in Section 6.12, "SoC UnCore and I/O Error Reporting".

Besides error detection, logging and reporting, the SoC PCI Express Root Ports support:

- Data Link Layer 32-bit CRC (LCRC) and Retry Management — see sub-section 3.5 "Data Integrity" of the Data Link Layer section in the *PCI Express Base Specification*, Revision 3.0.
- Transaction Layer end-to-end 32-bit CRC (ECRC) — see sub-section 2.7 "Data Integrity" of the Transaction Layer section in the *PCI Express Base Specification*, Revision 3.0.
  - — Supported by the PCIe Root Ports but not on the three Virtual Root Ports.
- Link Retraining and Dynamic Link Width Reduction upon link failure.
  - — Supported by the PCIe Root Ports but does not apply to the three Virtual Root Ports.

When PCIe Link Retraining fails, the SoC PCIe interface provides a mechanism to recover from the failed link. The PCIe link is capable of operating in different link widths. The SoC supports PCIe Root Port operation in x8, x4, and x2. In case of a persistent link failure, the PCIe link can fall back to a smaller link width, as small as x1, in attempt to recover from the error. As an example, a PCIe x8 link can fall back to a x4 link. If necessary, it can be further reduced to a x2 link, and then to X1 link. This mechanism enables continuation of system operation in case of PCIe link failures. Additional information can be found in Section 11.4.5, "Degraded Mode".

6.6 Machine Check Architecture (MCA)

Machine Check Architecture is a mechanism for detecting and reporting hardware (machine) errors in the CPU and UnCore. For the SoC, MCA is not used to report I/O-based errors.

This section provides the necessary details for the operating software to handle Machine Check Exceptions (MCE). Some operating systems hook the Machine Check Architecture (MCA) exception vector (18h) to allow system-crash analysis. Like some other Intel processors, the SoC has been enhanced to allow the machine state to be preserved across the assertion of the Platform Reset. The BIOS does not modify the MCA registers following the assertion of Platform Reset. This allows the operating system to enhance the exception handler by having this information available following a reboot after an error has occurred. Only upon the assertion (the signal transition from low to high) of the COREPWROK input signal (indicating POWERGOOD, power-on) is the machine-check architecture state re-initialized.

All MCA state information is accessible via the Model-Specific Register (MSR) accesses using the Read MSR (RDMSR) and Write MSR (WRMSR) instructions. RDMSR and WRMSR are described in Volume 2, Chapter 4 of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*. The machine-check architecture is described in Volume 3, Chapter 15, of the same manual.

Intel® architecture defines two classifications of MCA MSRs:

1. Machine Check Global Control and Status registers.
2. Machine Check Error-Reporting Bank registers.

The SoC does not implement the IA32_MCG_CTL and IA32_MCG_EXT_CTL Global Control and Status MSRs. See Figure 6-1, "SoC Machine Check MSRs — Global Control and Bank Registers".

Figure 6-1. SoC Machine Check MSRs — Global Control and Bank Registers



6.6.1 Machine Check MSR Addresses

The machine check MSRs are accessed via the RDMSR and WRMSR processor instructions.

Table 6-3 lists the MSR addresses and Figure 6-2, "SoC Core, Module, and Package Machine Check Registers" shows the core, module, and SoC package with respect to each Machine Check register.

Table 6-3. SoC Machine Check MSR Addresses

Register Type	Function	Register	Register Address
MC Bank 0	Module - Bus Interface Unit (BIU)	IA32_MC0_STATUS IA32_MC0_ADDR	401h 402h
MC Bank 1	Module - L2 Cache	IA32_MC1_STATUS IA32_MC1_ADDR	405h 406h
MC Bank 2	Core - Fetch Execution Cluster (FEC)	IA32_MC2_STATUS IA32_MC2_ADDR	409h 40Ah
MC Bank 3	Core - Memory Execution Cluster (MEC)	IA32_MC3_CTL IA32_MC3_STATUS IA32_MC3_ADDR	40Ch 40Dh 40Eh
MC Bank 4	SoC System Agent	IA32_MC4_STATUS IA32_MC4_ADDR IA32_MC4_MISC	411h 412h 413h
MC Bank 5	SoC Power Management Unit (PMU)	IA32_MC5_STATUS IA32_MC5_ADDR IA32_MC5_MISC	415h 416h 417h
MC Bank 6	SoC System Agent	IA32_MC6_STATUS IA32_MC6_ADDR	419h 41Ah
MC Bank 7	Memory Channel 0	IA32_MC7_STATUS IA32_MC7_MISC	41Dh 41Fh
MC Bank 8	Memory Channel 1	IA32_MC8_STATUS IA32_MC8_MISC	421h 423h

Figure 6-2. SoC Core, Module, and Package Machine Check Registers



6.6.2 Enhancements to MCA Error Reporting

The SoC provides support of Error Cloaking and Dual Signaling (MSR 52h) to optionally hide errors from the operating system. Corrected Machine-Check error Interrupt (CMCI) enhancement is also supported.

6.6.2.1 Error Cloaking

The Error Cloaking feature allows BIOS to hide Correctable Errors from the Operating System (OS). The Model-Specific Register (MSR) MSR_SMM_MCA_CONTROL (MSR 52h) contains a control bit to mask corrected errors during non-System-Management-Mode (non-SMM) accesses.

Non-SMM reads to MCi_STATUS registers will return 0 instead of the actual status value if, MCi_STATUS RDMSR reports a VALID CORRECTED error (VAL=1,UC=0) and CERR_RD_STATUS_IN_SMM_ONLY (in MSR0x52) is set. See Table 6-4, "MSR_SMM_MCA_CONTROL (MSR 52h) — Enhanced MCA Control".

6.6.2.2 Dual Signaling

The Dual Signaling feature allows SMM firmware to handle, and possibly clear-out, errors before the Operating System sees them.

In the MCA flow, if PEND_SMI_ON_MCA bit is set in MSR 52h, the SoC creates a pending System Management Interrupt (SMI) on the core. This flow relies on the MCA broadcast (and consistent opt-in and subsequent pending of SMI) to get the SMI pending on all threads. See Table 6-4, "MSR_SMM_MCA_CONTROL (MSR 52h) — Enhanced MCA Control".

Table 6-4. MSR_SMM_MCA_CONTROL (MSR 52h) — Enhanced MCA Control

Bit	Register Field	Access Type	Description
31:10	Reserved	-	Reserved
9	PEND_SMI_ON_MCA	RW	Pend SMI on MCA
8:1		-	Reserved
0	CERR_RD_STATUS_IN_SMM_ONLY	RW	When set to 1, Valid (VAL=1), Correctable Error (UC=0) CPU MCA Status can only be read when the CPU is in System Management Mode (SMM). Otherwise read 0 if VAL=1 and UC=0. This bit is package-scope and mapped by microcode to an UnCore SCP.

6.6.2.3 Corrected Machine-Check error Interrupt (CMCI)

CMCI is an architectural enhancement to the MCA. It provides capabilities beyond those of threshold-based error reporting. With threshold-based error reporting, software is limited to use periodic polling to query the status of hardware corrected Machine-Check errors.

CMCI provides a signaling mechanism to deliver a local interrupt based on threshold values that software can program in bits [14:0] of the Machine-Check Bank IA32_MCi_CTL2 MSRs.

CMCI is disabled by default. The MCG_CMCI_P bit of the IA32_MCG_CAP Global Machine Check register, when set, indicates that the SoC has the CMCI capability. Bit 30 of each IA32_MCi_CTL2 register must be checked to see whether the particular Machine-Check Bank has the CMCI-signaling capability. CMCI is not affected by the CR4.MCE bit, and it is not affected by the IA32_MCi_CTL MSRs. The L2 Cache, SoC internal fabric, and Memory Controller Machine-Check Banks support CMCI signaling.

Corrected Machine-Check Errors detected in the UnCore portion of the SoC (see Figure 6-2, "SoC Core, Module, and Package Machine Check Registers") generate a CMCI to all processor cores of the SoC. There is no provision for one processor to signal a CMCI to other processor within a system.

The processor's APIC Local Vector Table (LVT) has a LVT CMCI register that specifies interrupt Delivery Mode (NMI, SMI, etc.) and Vector when an overflow condition of corrected machine check error count reaching a threshold value occurred in a machine check bank supporting CMCI.

6.7 Advanced Error Reporting (AER)

6.7.1 AER and the PCIe Root Ports and RCEC

Advanced Error Reporting (AER) is supported on these integrated devices:

- PCI Express* Root Ports.
- Root Complex Integrated Endpoints:
  - — SMBus-Host function
  - — Host Bridge (Global/Local Error function)
- Integrated LAN Controllers
- Integrated Intel® QuickAssist Technology (Intel® QAT) Controller

The RCEC and the PCIe Root Ports with the AER capability not only generate system errors (Correctable, Non-Fatal, and Fatal) from received, or internally-generated, error Messages, each can generate an interrupt for each of the three error categories.

The RCEC_ROOTERRCMD register (ROOTERRCMD for each of the eight Root Ports and three Virtual Root Ports) in Host Root Configuration Space provides an enable/disable for each of the three error categories.

For both Root Ports and Root Complex Event Collectors, in order for a received error Message or an internally generated error Message to generate an interrupt enabled by this register, the error Message must be enabled for "transmission" by the Root Port or Root Complex Event Collector.

The interrupt generated to the host is either an INTx message or an MSI/MSI-X interrupt, depending which type of interrupt-reporting mechanism is enabled for the RCEC or Root Port.

The RCEC_ROOTERRSTS register (ROOTERRSTS for the Root Ports) reports status of error Messages (ERR_COR, ERR_NONFATAL, and ERR_FATAL) received by the RCEC (or Root Port), and of errors detected by the RCEC/Root Port itself (which are treated conceptually as if the RCEC/Root Port had sent an error Message to itself). The RCEC provide this only for the two Root Complex Integrated Endpoints is serves — the SMBus-Host function and the Global/Local Integrated Error Handler function.

When an error is received by the RCEC or Root Port, the respective first error bit is Set and the Requester ID is logged in the RCEC_ERRSRCID (ERRSRCID for Root Ports) register.

For additional details, see Section 7.10 "Advanced Error Reporting Capability" of the *PCI Express Base Specification Revision 3.0*.

6.8 Intel® Virtualization Technology (Intel® VT)

The SoC provides hardware support for isolating & restricting device accesses to the owner of the partition managing the device. Virtual partitioning is provided as:

- Enhanced Intel® Virtualization Technology (Intel® VT) for IA-32, Intel® 64 and Intel® Architecture (Intel® VT-x)
- Intel® Virtualization Technology (Intel® VT) for Directed I/O (Intel® VT-d)

See Section 2.2.2, "Intel® Virtualization Technology".

6.9 Error Injection

Error injection can be used to validate system error-handling software. The SoC supports:

- Writable Machine Check Architecture (MCA) banks.
- Out-of band access to the MCA registers
- The PCI Express Root Ports support the Windows Hardware Error Architecture (WHEA) capability. The dedicated Virtual Root Ports for the Intel® QuickAssist Technology and LAN Controllers do not have the WHEA capability.
- Each of the two DRAM memory controllers has error injection on write/read data paths including address/source match. See Section 6.16.2, "Error Injection Control and Registers — Memory Controller".

6.10 SoC UnCore and I/O Error Handling

Figure 6-3, "Intel Atom® Processor C3000 Product Family Error Reporting" shows high level error handling scheme. The SoC receives PCIe error messages from downstream devices. The SoC logs these errors and other internal device errors. More details are provided in the following sections.

Figure 6-3. Intel Atom® Processor C3000 Product Family Error Reporting



6.11 Hardware Error Classification and System Events

In the SoC, hardware errors are classified as two types:

- Correctable Errors
- Uncorrectable Errors

This classification separates hardware errors that result in degraded performance from those that result in functional failures.

Uncorrectable hardware errors can be further classified as:

- Non-Fatal Error
- Fatal Error

Classifying hardware errors in this way provides the platform with ways to map a hardware error to a suitable handling mechanism. Each severity can trigger a System Event according to the GLREG Global System Event Map (GLREG_GSYSEVTMAP) register located in Host Root Configuration Space at B0;D5;F0, offset 250h. The System Event choices are either generate a Non-Maskable Interrupt (NMI), a System Management Interrupt (SMI), or generate no System Event.

The GLREG_GSYSEVTMAP register provides software the flexibility to map an Uncorrectable Error to the suitable error severity. For example, a platform design may choose to map an Uncorrectable DRAM ECC Error as a Non-Fatal Error while another platform design may require mapping the same error as a Fatal Error.

The software/firmware can choose to alter the default mapping after power-on.

6.11.1 Correctable Errors

At power-on, the GLREG_GSYSEVTMAP register is default-set to map Correctable Errors to an SMI System Event.

Hardware correctable errors include those error conditions where the system recovers without any loss of information. The hardware corrects these errors, and no software intervention is required. For example, a link CRC error which is corrected by the data link level retry is considered a correctable error.

- An error is corrected by the hardware without software intervention. System operation is degraded, but its functionality is not compromised
- A correctable error is logged and reported in a implementation specific manner:
  - Upon the immediate detection of the correctable error
  - Upon the accumulation of errors reaching to a threshold

6.11.2 Uncorrectable Errors

At power-on, the GLREG_GSYSEVTMAP register is default-set to map Non-Fatal Uncorrectable Correctable Errors to an SMI System Event.

An uncorrected error is a hardware error condition that cannot be corrected by the hardware or by the firmware. Uncorrected errors are either fatal or non-fatal.

6.11.2.1 Fatal Errors

A fatal hardware error is an uncorrected or uncontained error condition that is determined to be unrecoverable by the hardware. When a fatal uncorrected error occurs, the system is restarted to prevent propagation of the error.

6.11.2.2 Non-Fatal Errors

A non-fatal hardware error is an uncorrected error condition from which the Operating System or firmware can attempt recovery by trying to correct the error. These are also referred to as correctable or recoverable errors.

Isolating non-fatal from fatal errors provides system management software the opportunity to recover from the error without reset and disturbing other transactions in progress. Devices not associated with the transaction in error are not impacted by the error. An example of recoverable error is an ECC uncorrectable error that affects only the data portion of a transaction:

- The error is not corrected by the hardware and requires software intervention for correction
- The error is not corrected. Data integrity is compromised, but system operation is not compromised
- This error requires immediate logging and reporting of the error to the CPU

6.11.3 Software Correctable Errors

Software correctable errors are considered as a recoverable error. These errors include those error conditions where the system recovers without any loss of information. Software intervention is required to correct these errors:

- This error requires immediate logging and reporting of the error to the CPU
- The firmware or other system software layers take corrective actions

Data integrity is not compromised with such errors.

6.12 SoC UnCore and I/O Error Reporting

The SoC logs and reports the detected errors via "system event" generations. In the context of error reporting, a system event is an event that notifies the system of the error. Two types of system events can be generated -- an NMI or SMI to the SoC, or an ERROR_N[2:0] pins indication to the platform. The SoC responds to a system event (NMI or SMI) and takes the appropriate action to handle the error. An external agent such as BMC may monitor ERROR_N[2:0] pins to determine the health of SoC and interrupt the SoC. In some severe error cases, if the SoC is no longer responding to system events resulting from an error(s), the ERROR_N[2:0], IERR_N, and MCERR_N pins provide a way to notify an external agent of the error. The external agent can then perform a reset to recover the Denverton SoC functionality.

The Figure 6-4 illustrates internal and external error reporting. The SoC receives PCIe error messages from downstream devices. The SoC logs these errors and other internal errors.

Figure 6-4. Error Handling Architecture



The SoC detects errors from the PCIe* links and the SoC internal device errors. The errors are first logged and mapped to an error severity, and then mapped to a system event(s) for error reporting.

SoC error-reporting features are summarized below. Details are in the following sections:

- Detects and logs PCIe links and SoC internal device errors
- First error/next error detection and logging for correctable/uncorrectable local errors
- Allows flexible mapping of local uncorrectable errors to fatal or non-fatal error classes
- First/next error detection and logging for correctable, non-fatal, and fatal global errors
- Flexible error reporting using multiple reporting mechanisms
- Supports PCIe error reporting mechanism based on the Root Complex Event Collector (RCEC)

The SoC provides direct mapping of system errors to NMI or SMI. The System Error (SERR) mechanism is not used to do this.

6.12.1 Reporting Error to an External Device

Detected errors can be forwarded to an external device (e.g., a BMC) using the SoC ERROR_N[2:0] signal pins.

The SoC escalates machine check errors (MCERR_B) and unrecoverable internal errors (IERR) to the external BMC and to the CPU cores for handling non-maskable and other fatal errors in the system. See Figure 6-5. The MCERR_N and IERR_N signals are broadcast to the CPU and to the external platform.

Figure 6-5. MCERR and IERR Handling



The MCERR_N signal signifies a catastrophic internal error, a condition which requires immediate attention or possibly shutdown. When this error occurs, the processor core may not be able to execute reliably through the INT18 handler. The following are some possible cases of such catastrophic errors:

- Retirement watchdog time-out from the core
- Internal error detected by the SoC power management circuitry

The MCERR_N signal signifies a machine check error occurred and that SoC Machine Check Architecture registers, accessible through the MSRRD and MSRWR instructions, may have additional information concerning the error.

Note: Board designs must not consider IERR_N and MCERR_N valid until after the PMU_PLTRST_N (Platform Reset) signal is deasserted by the SoC. When the SoC is powered-up or a cold boot, the IERR_N and MCERR_N signals may be unstable and falsely signal an internal error or machine check error before the platform reset is deasserted by the SoC.

6.12.2 PCI Express INTx and MSI

PCIe INTx and MSI are supported via PCIe standard error reporting. The SoC forwards MSI generated from downstream PCIe devices to the CPU. Also, PCIe Root ports and RCEC in the SoC generate Intx/MSI interrupts for error reporting if enabled. See PCIe specification for details on PCIe standard and advanced error reporting capability.

6.13 Overview of SoC Error Registers

The SoC contains sets of error registers to support error reporting. These error registers are assumed to be sticky unless specified otherwise. Sticky means the values of the registers are retained even after a hard reset — they can only be cleared by software or by power-on reset.

There are two levels of hierarchy for the SoC error registers:

- Local Error Registers
- Global Error Registers

See Figure 6-6, "Local and Global Error Register Structure". The Local Error Registers are associated with the local, integrated devices. The Global Error Registers collect the errors reported by the Local Error Registers and map them to system events and/or to SoC output signal pins.

Note: The PSF, IEH, P2SB, A, B, C, and D Units are physical functions within the SoC. They are part of the internal fabric that handles I/O transactions to/from the CPU cores and the system memory subsystem. This document does not provide details of these internal functions other than errors they detect and report.

Figure 6-6. Local and Global Error Register Structure



6.13.1 Local Error Registers

Table 6-5, "Local Error Register General Descriptions" provides a general description of the SoC Local Error registers. Not all SoC error-detecting mechanisms implement all of these registers. Some have additional Local Error registers not listed here.

Table 6-5. Local Error Register General Descriptions

Local Error Register Name	Local Error Register Description
Uncorrectable Errors	
Uncorrectable Error Status (not AER)	When a specific Uncorrectable Error associated with an SoC local interface occurs, its corresponding bit in this error status register is set. Each error can be individually masked by the Uncorrectable Error Mask register. A masked error bit is not set for any subsequent detected error and is not recorded or reported in the Uncorrectable Header Log register and does not update the Uncorrectable FERR/NERR registers.
Uncorrectable Error Mask (not AER)	
Uncorrectable Error Status (AER)	The Uncorrectable Error Status register reports error status of individual correctable error sources on a PCI Express device Function. Software may clear an error status by writing a 1 to the respective error bit. When the respective bit is set in the Uncorrectable Error Mask, the error is set in the Uncorrectable Error Status register, but it is not reported to the PCI Express Root Complex via a PCI Express Error Signaling Message, and the Header Log and First Error Pointer registers are unmodified.
Uncorrectable Error Mask (AER)	
Uncorrectable Error Severity	Controls whether an individual error is reported as a Non-Fatal (register = 0) or Fatal (register = 1) error.
First Uncorrectable Error	The First Uncorrectable Error Register (FERR) logs the first occurrence of an error, while the Next Uncorrectable Error Register (NERR) logs the subsequent occurrence of the errors. The Uncorrectable FERR and NERR do not log errors that are masked. The Uncorrectable FERR log remains valid and unchanged from the first error detection until the clearing of the corresponding Uncorrectable FERR error bit in the Uncorrectable Error Status Register by software.
Next Uncorrectable Error	
Uncorrectable Header Log (not AER)	Logs the header of the first Uncorrectable Error associated with the particular local interface.
Correctable Errors	
Correctable Error Status (not AER)	When a specific Correctable Error associated with an SoC local interface occurs, its corresponding bit in this error status register is set. Each error can be individually masked by the Correctable Error Mask register. A masked error bit is not set for any subsequent detected error and is not recorded or reported in the Uncorrectable Header Log register and does not update the Correctable FERR/NERR registers.
Correctable Error Mask (not AER)	
Correctable Error Status (AER)	The Correctable Error Status register reports error status of individual correctable error sources on a PCI Express device Function. Software may clear an error status by writing a 1 to the respective error bit. When the respective bit is set in the Correctable Error Mask, the error is set in the Correctable Error Status register, but it is not reported to the PCI Express Root Complex via a PCI Express Error Signaling Message, and the Header Log and First Error Pointer registers are unmodified.
Correctable Error Mask (AER)	
First Correctable Error	The First Correctable Error Register (FERR) logs the first occurrence of an error, while the Next Correctable Error Register (NERR) logs the subsequent occurrence of the errors. The Correctable FERR and NERR do not log errors that are masked. The Correctable FERR log remains valid and unchanged from the first error detection until the clearing of the corresponding Correctable FERR error bit in the Correctable Error Status Register by software.
Next Correctable Error	
Correctable Header Log (not AER)	Logs the header of the first Correctable Error associated with the particular local interface.
AER Specific	
Advanced Error Capabilities and Control (AER)	Identifies AER capabilities and the bit position of the first error reported in the (AER) Uncorrectable Error Status register.
Advanced Error Header Log (AER)	Header (four DWords) of the Transaction-Level Packet (TLP) associated with the error.

6.13.2 SoC Global Error Registers

The SoC provides Global Error Registers and circuitry. The Global Error Registers are not defined in any industry specification. The provide a quick way for software to start searching for the error that caused the system error-reporting event.

Table 6-6. List of SoC Global Error Registers

Host Root Configuration Space B0:D4:F0 Offset (hex)	Global Error Register	Register Name
200	GLREG_GCOERRSTS	Global Correctable Error Status
204	GLREG_GNFERRSTS	Global Non-Fatal Error Status
208	GLREG_GFAERRSTS	Global Fatal Error Status
20C	GLREG_GERRMSK	Global Error Mask
228	GLREG_GTIME	Global Error Timer
230	GLREG_GCOFERRTIME	Global Correctable FERR Error Time Stamp
238	GLREG_GNFFERRTIME	Global Nonfatal FERR Error Time Stamp
240	GLREG_GFAFERRTIME	Global Fatal FERR Error Time Stamp
248	GLREG_GSYSEVTSTS	Global System Event Status
24C	GLREG_GSYSEVTMSK	Global System Event Mask
250	GLREG_GSYSEVTMAP	Global System Event Map
254	GLREG_ERRPINCTRL	Error Pin Control
258	GLREG_ERRPINSTS	Error Pin Status
25C	GLREG_ERRPINDATA	Error Pin Data

6.13.3 First Error and Next Error Log Registers

This section pertains to both Local Error logging and Global Error logging. The error-log registers names contain FERR (First Error) and NERR (Next Error). First Errors and Next Errors are captured at both the local level (correctable and uncorrectable) and Global level (correctable, non-fatal and fatal). PCI Express specifies its own error-logging mechanism which is not be described here and can be found in the *PCI Express Base Specification Revision 3.0*.

For Global Error logging, the SoC categorizes a detected error based on the error severity:

- Fatal Error
- Non-Fatal Error
- Correctable Error

Each category includes two sets of error logging:

- First Error register (FERR)
- Next Error register (NERR)

The FERR register stores the information associated with the first detected error, while NERR stores the information associated with the subsequent detected errors after the first error. Both FERR and NERR log the error status in the same format. They indicate errors that can be detected by the SoC with one bit assigned to each type of error. The first error event is indicated by setting the corresponding bit in the FERR status register; a subsequent error is indicated by setting the corresponding bit in the NERR register. In addition, the local FERR registers logs the header of the erroneous cycle. Both First Error and Next Error trigger system events.

Once the First Error and the Next Error have been indicated and logged, the log registers for that error remain valid until either

The first error bit is clear in the associated error status register, or

A reset after loss of power.

Software clears an error bit by writing 1 to the corresponding bit position in the error status register.

The SoC uses this procedure tor updating the FERR and NERR registers and error logs:

1. First Error event is indicated by setting the corresponding bit in the FERR status register, a subsequent error is indicated by setting the corresponding bit in the NERR status register.
2. If the same error occurs before the FERR status register bit is cleared, it is not logged in the NERR status register.
3. In the case of simultaneous multiple errors with same severity, any two errors may be logged in FERR and NERR registers.
4. Updates to error status and error log registers appear atomic to the software.
5. Once the information of the first error is logged in the FERR log register, the logging of FERR log registers is disabled until the corresponding FERR error status is cleared by the software.
6. Error status registers, Error Mask registers and Error Log registers are cleared by the power-on reset only. The contents of Error Log registers are preserved across a reset (while power-good is sensed).

6.13.4 General Local and Global Error-Register Flow

1. Upon a detection of a Local error, the corresponding Local error status is set if the error is unmasked. Otherwise the error bit is not set and the error is not propagated upstream towards the SoC Root Complex.
2. The Local uncorrectable error is mapped to its associated error severity defined by the Uncorrectable Error Severity register. Setting of the Local Error Status register bit causes the logging of the error. Fatal and Non-fatal errors are logged in the Local Uncorrectable FERR and NERR registers, while correctable errors are logged in the Local Correctable FERR and NERR registers. PCI Express errors are logged according to the PCI Express specification.
3. The local FERR and NERR logging events are forwarded to the Global FERR and NERR registers. The report of Local FERR/NERR sets the corresponding Global Error Status bit if the particular global error is unmasked. Otherwise the global error bit is not set and the error is propagated. As mentioned in Section 6.13.3, "First Error and Next Error Log Registers", the Global FERR logs the first occurrence of local FERR event in the SoC while the Global NERR logs the subsequent local NERR event.
4. Correctable error is logged in the Global Correctable FERR/NERR registers, Non-Fatal is logged in the Global Non-Fatal FERR/NERR registers, and Fatal error is logged in the Global Fatal FERR/NERR registers.
5. The Global Error Status register reports the error with its associated error severity to the Global System Event Status (GLREG_GSYSEVTSTS) register. The system event status is generated if the system event reporting is unmasked for the error severity in the Global System Event Mask (GLREG_GSYSEVTMSK) register. Otherwise the bit is not set and the error is not reported.
6. Setting of the system event bit triggers a system event generation according the mapping defined in the Global System Event Map (GLREG_GSYSEVTMAP) register. The associated system event is generated for the error severity and the error indication dispatched to the CPU/BMC (interrupt for CPU or Error Pin for BMC).
7. The global log and local log registers provide the information to identify the source of the error. Software can read the log registers and clear the global and local error status bits.
8. Since the error status bits are edge triggered, a 0-to-1 transition is required to set the bit again. While the error status bit (local, global, or system event) is set to 1, all incoming error reporting to the respective error status register is ignored (no 0-to-1 transition).
    a. When a write occurs to clear the Local Error Status bit, the local error register circuitry re-evaluates the "OR" output of its error bits and reports it to the Global Error register. However, if the Global Error Status bit is already set, then the report is ignored.
    b. When write occurs to clear error status bit, the Global Error register circuitry re-evaluates the "OR output" of its error bits and reports it to the Global System Event Status (GLREG_GSYSEVTSTS) register. However, if the system event status bit is already set, then the report is not generated.
    c. Software can optionally mask or unmask the system event generation (interrupt or error pin) for an error severity in the Global System Event Mask (GLREG_GSYSEVTMSK) register while clearing the Local and Global error registers.

9. Software has the following options for clearing error status registers:
   a. Read the Global and Local Error Log registers to identify the source of the error. Clear local error bits. This does not cause the generation of an interrupt with the global bit still set. Then clear the global error bit and write to the local error register again with all 0s. Writing 0s to the local status does not clear any status bits, but will cause the re-evaluation of the error status bits. An error is reported if there are any uncleared local error bits.
   b. Read the Global and Local Error Log registers to identify the source of the error and mask the error reporting for the error severity. Clear the system event and global error status bits. This causes the setting of the system event status bit if there are other global bits still set. Then clear the local error status bits. This causes the setting of the Global Error Status bit if there are other local error bits still set. Then unmask the system event to cause the SoC to report the error.
10. The FERR register logs the information of the first error detected by the associated error status register (Local or Global). The FERR log remains unchanged until all bits in the respective error status register are cleared by the software. When all error bits are cleared, FERR logging is re-enabled.

6.13.5 Global System Event Reporting

Provided that the Global System Event Mask (GLREG_GSYSEVTMSK) register is not set to prevent the generation of system events, the Global System Event Map (GLREG_GSYSEVTMAP) register determines which system event is generated to the CPU for a given Global Error severity. See Figure 6-7, "Global Error Registers and System Event Reporting".

Figure 6-7. Global Error Registers and System Event Reporting



Each severity (Fatal, Non-Fatal, Correctable) is programmable to generate either an NMI, SMI or not generate a system event. The default settings are:

- Fatal Error - Generate an NMI
- Non-Fatal Error - Generate an SMI
- Correctable Error - Generate an SMI

The Global System Event can also be generated to the platform board through the SoC output signal pins which are shown in Table 6-1, "Signal Names and Descriptions".

- ERROR_N[2] - Fatal Error
- ERROR_N[1] - Non-Fatal Error
- ERROR_N[0] - Correctable Error

The programmable Error Pin Control (GLREG_ERRPINCTRL) register determines how these error pins function. Each pin can also be disabled by this register. The signal pin can be configured to assert when a Global Error of its associated severity is set in the Global System Event Status (GLREG_GSYSEVTSTS) register. It can also be configured to operate as a programmed-controlled signal similar to a general-purpose I/O signal.

The Error Pin Data (GLREG_ERRPINDATA) register provides the data value when the error pin is configured as a program-controlled output signal. The assertion and deassertion of each of the three ERROR_N pins can be programmed. The particular error-pin signal follows the value programmed here. This mechanism only functions when 2-bit Error Enable field of the Error Pin Control (GLREG_ERRPINCTRL) register is set to 01 for the particular Error Pin Data bit.

ERROR_N[1] and ERROR_N[0] are default set to operate in this program-controlled mode. ERROR_N[0] is default-set to assert the pin's signal when a Fatal error is set in the Global System Event Status (GLREG_GSYSEVTSTS) register.

6.13.6 Error Counters

The Error Counters allow the system management controller to monitor the component's health by periodically reporting the Correctable Error Count. The error RAS structure already provides a First Error status and a Second Error status. Because the response time of system management is on the order of milliseconds, it is not possible to read and clear the error logs in time to detect short bursts of errors across the component. Over a long period of time the software uses these values to monitor the rate of change in error occurrences. This helps identify potential component degradations, especially with respect to the system memory interface.

6.13.6.1 Error Counter Requirements

A register with one-hot encoding selects the error types that participate in error counting. It is unlikely that more than one error will occur within a cluster at a given time. Therefore, it is not necessary to count more than one occurrence in one clock cycle. The selection register ORs together all of the selected error types to form a single count enable. This means that only one increment of the counter occurs for one or all types selected. Register attributes are set to write-1-to-clear.

Each of these clusters has a set of error counter/control registers.

- The IEH device (B0:D4:F0) contains a seven-bit Error Counter (ERRCNT[6:0]) in the Uncorrectable Error Counter (GLREG_LUNCERRCNT) register located in Host Root Configuration Space, offset 294h.
  - GLREG_LUNCERRCNT bit 7 (ERR_OVF) is an overflow bit. All eight bits of the register are sticky with a write logic 1 to clear.
- Each of the two D-Units of the SoC System Agent contains an eight-bit Error Counter (UNCCNT[7:0]) field in its Uncorrectable Error Counter (DERRCNT) register located in Host Root Memory Space at SBREG_BAR plus offset 10_0130h (D-Unit 0) and 12_0130h (D-Unit 1).
  - UNCCNT bit 7 is an overflow bit. All eight bits of the UNCCNT field of the register are sticky with a write logic 1 to clear.
- The B-Unit of the System Agent contains a 15-bit Error Counter (ERR_CNT[14:0]) in the Uncorrectable Error Count (B_CR_UNCERRCNT_0_0_0_MCHBAR) register located in Host Root Memory Space at MCHBAR plus offset 6E1Ch.
  - B_CR_UNCERRCNT_0_0_0_MCHBAR register bit 15 (OVERFLOW) is an overflow bit. Bits [15:0] bits of the register are sticky with a write logic 1 to clear.
- The A-Unit of the System Agent contains a 15-bit Error Counter (ERR_CNT[14:0]) in the Uncorrectable Error Count (A_CR_UNCERRCNT_0_0_0_MCHBAR) register located in Host Root Memory Space at MCHBAR plus offset 65A0h.
  - A_CR_UNCERRCNT_0_0_0_MCHBAR register bit 15 (OVERFLOW) is an overflow bit. Bits [15:0] bits of the register are sticky with a write logic 1 to clear.
- The A-Unit of the System Agent contains a 15-bit Error Counter (ERR_CNT[14:0]) in the Correctable Error Count (A_CR_CORERRCNT_0_0_0_MCHBAR) register located in Host Root Memory Space at MCHBAR plus offset 65B8h.
  - A_CR_CORERRCNT_0_0_0_MCHBAR register bit 15 (OVERFLOW) is an overflow bit. Bits [15:0] bits of the register are sticky with a write logic 1 to clear.

6.14 Error Reporting Flow — PCI Express Devices/Functions

- PCIe Root Ports 0 through 7
- Virtual PCIe Root Ports 0 through 2
- PCIe Endpoints behind the Virtual Root Ports
  - — Intel® QuickAssist Technology agent
  - — LAN Controller 0 and 1
- PCIe Root Complex Integrated Endpoints via RCEC
  - — SMBus - Host Controller
  - — Integrated Error Handler (IEH) agent

The PCI Express* architecture provides three complementary mechanisms which allow the agent detecting an error to alert the system or another device that an error has occurred. The three mechanisms are:

- Through the Completion Status of a transaction
- In-band Error-Signaling Messages
- Error Forwarding (also known as data poisoning)

Section 6.2.7 “Error Listing and Rules” of the *PCI Express Base Specification Revision 3.0* lists the actions that an error-detecting agent is expected to take to report and log an error using the above mechanisms. Section 2.2.8.3 “Error Signaling Messages” of the same specification defines the Error Signaling Messages that are used to signal errors that occur on specific PCI Express transactions and errors that are not necessarily associated with a particular transaction. These Messages are initiated by the agent that detected the error. The three Error Signaling Messages are:

- ERR_COR - The device/function detected a Correctable Error.
- ERR_NONFATAL - The device/function detected a Non-Fatal Error.
- ERR_FATAL - The device/function detected a Fatal Error.

6.14.1 Upstream Flow of Error Signal Messages

The upstream flow of the agents' Error Signal Messages to the SoC Global Error Registers is shown in Figure 6-8, "PCIe Error Signaling and Logging". PCI Express endpoint devices attached to the SoC Root Ports send these to the Root Ports where they are channeled along with the Root Port internal errors to the SoC Global Error Registers.

Figure 6-8. PCIe Error Signaling and Logging



6.14.2 How a PCIe Device Determines Which Error Message to Send

Section 6.2 "Error Signaling and Logging" of the *PCI Express Base Specification Revision 3.0* describes the PCIe In-band Error-Signaling Messages. It also provides a flowchart showing how the PCIe device/function determines which error Message, if any, to send to the SoC Root Complex.

All of the flow diagrams provided above show how the Advanced Error Reporting Capability (AER), an optional PCI Express Extended Capability, affects the flow. All of the PCI Express Devices/Functions mentioned in this sub-section have the AER Capability.

Besides the AER Capability, each PCIe device/function has a Device Status register that is part of its PCI Express Capability structure and contains indications of detected errors. Each PCIe device/function also has a Device Control Register that is part of its PCI Express Capability structure. This register contains bits that, in conjunction with other bits, provides software the capability to mask (prevent) the ERR_COR, ERR_NONFATAL, and ERR_FATAL error signaling messages from being transmitted towards the Root Complex.

If an individual error is masked when it is detected, its error status bit is still affected, but no error reporting Message is sent to the Root Complex, and the Header Log and First Error Pointer registers are unmodified. See Section 6.2.3.2.2 "Masking Individual Errors" and the flowchart in Section 6.2.5. "Sequence of Device Error Signaling and Logging Operations" in the *PCI Express Base Specification Revision 3.0*.

The Root Complex internally translates these error indications into platform-level events. This includes setting a possible NMI or SMI (interrupt), and ERROR_N[2:0] output signal pins.

Since they are part of the SoC Root Complex, the Root Ports, Virtual Root Ports, and RCEC interface directly to the SoC Global Registers rather than use the PCIe Error-Signaling Messages mentioned above. Each determines the error severity based on what is programmed in its PCIe Root Control (ROOTCTL) register and, as an option, sends the error to the SoC Global Registers.

As a PCIe Root Complex Integrated Endpoint (RCiE), the SMBus-Host Controller (B0:D18:F0) uses the SoC Root Complex Event Collector (RCEC) to pass errors to the Global Error logic and registers. As part of its AER Capability structure, the RCECs Root Error Status (RCEC_ROOTERRSTS) register and the Error Source Identification (RCEC_ERRSRCID) register that are used to capture the SMBus-Host Controller errors. They are located in Host Root Configuration Space at B0:D5:F0, offsets 130h and 134h respectively. For this to all happen the error signaling messages must be sent to the RCEC and not blocked by the SMBus-Host's Device Control Register that is part of its PCI Express Capability structure. RCEC also has the AER Root Error Command register (RCEC_ROOTERRCMD) at offset 12Ch that can be used to prevent error signaling messages from going to the Root Complex and the Global Error logic and registers.

Also as an RCiE, the SoC Integrated Error Handler (IEH) agent (B0:D4:F0) accumulates internal fabric hardware errors, all considered uncorrectable errors, and report them to the RCEC to pass-on to the Global Error logic/registers and generate an NMI or SMI, and optionally assert the SoC ERROR_N[2:0] output signal pins. This is done through Uncorrectable Internal Error (UIE), bit 22 of the RCEC Uncorrectable Error Status (RCEC_ERRUNCSTS) register located in Host Root Configuration Space at B0:D5:F0, offset 104h.

According to the *PCI Express Base Specification Revision 3.0*, the only method of recovering from an Uncorrectable Internal Error is reset or hardware replacement.

Like RCEC for the SMBus-Host mentioned above, each of the SoC PCIe Root Ports and Virtual Root Ports, as part of its AER Capability structure, has a Root Error Status (ROOTERRSTS) register and an Error Source Identification (ERRSRCID) register to capture errors signaled to them and the transaction Requester ID. Each also has a Root Error Command (ROOTERRCMD) that can be used to prevent error-signaling messages from propagating to the Root Complex and the Global Error logic and registers.

Note: SoC Machine Check events do not occur from hardware errors detected by PCIe agents.

6.14.3 PCIe Endpoint Devices Behind Virtual Root Port Error Handling

The integrated Intel® QuickAssist Technology controller and the integrated LAN Controllers are PCI Express endpoint devices. Each is attached to a dedicated "Virtual" Root Port (VRP). Each has Local Error Registers and an Error Signaling Message flow to the SoC Global Error Registers that is shown in Figure 6-9, "Error Signaling and Logging for PCIe Root Complex Integrated Endpoints."

Figure 6-9. Error Signaling and Logging for PCIe Root Complex Integrated Endpoints



These PCIe endpoint devices support AER registers for logging and reporting internal fabric and device specific errors. Device-specific errors are logged into Local Error registers and reported using Uncorrectable Internal Error Status (Bit 22) of ERRUNCSTS register and Corrected Internal Status (Bit 14) of the ERRUNCSTS register.

6.14.4 PCI Express Root Ports

While PCIe Root Port error reporting is described in the *PCI Express Base Specification Revision 3.0*, the following paragraphs highlight important aspects of PCIe Root port error reporting mechanism.

6.14.4.1 Unsupported Transactions and Unexpected Completions

If a SoC Root Port receives a legal PCIe-defined packet that is not included in PCIe supported transactions, the SoC treats that packet as an unsupported transaction and follows the PCIe rules for handling Unsupported Requests (UR). If the Root Port receives a Completion with a Requester ID set as the Root Port's Requester ID and there is no matching request outstanding, then this is considered an Unexpected Completion (UC). Also, the SoC Root Ports detects malformed packets from the PCI Express interface and reports them as errors per the PCI Express specification.

If a SoC Root Port receives a Type 0 Intel Vendor-Defined message that terminates at the SoC Root Complex and does not recognize it as a valid Intel-supported message, the message is handled by the SoC as an Unsupported Request (UR) with the appropriate error escalation defined in The PCI Express specification. For Type 1 Vendor-Defined messages which terminate at the Root Complex, the SoC simply discards the message with no further action.

6.14.4.2 Unconnected Ports

If a CPU transaction targets a PCIe link that is not connected to any device or the link is down (DL_Down status is received by the Root Port), the SoC treats this as a Master Abort situation. This is required for PCI bus scans to non-existent devices to go through without creating any other side effects. If the transaction is non-posted, The SoC returns all F's. Note that accesses by CPU to the Root Port registers corresponding to an unconnected PCIe interface does not generate an error.

6.14.5 Internal Errors — SMBus-Host Controller

The SMBus-Host Controller report its internal errors in the SMBus-Host Error Status (ERRSTS) register located in Host Root Memory Space located at SMTBAR, offset 18h.

The ERRAERMSK register located at SMTBAR, offset 14h, can be programmed to prevent individual SMBus-Host internal errors (ERRSTS) from also setting the Uncorrectable Internal Error (UIE) status, bit 22 of the SMBus-Host's AER Uncorrectable Error Status (ERRUNCSTS) register located in Host Root Configuration Space at B0:D18:F0, offset 104h. Whether or not the UIE error is signaled to the RCEC and Global Error logic depends on the setting of Uncorrectable Internal Error Mask (UIEM), bit 22 of the SMBus-Host's AER ERRUNCMSK register located at offset 108h.

6.14.6 Local Error Registers

The following tables list the registers associated with the error control, status, and reporting flow for the PCIe devices/functions of the SoC:

- Table 6-7, "Local Error Registers — PCI Express Root Ports"
- Table 6-8, "Local Error Registers — PCI Express RCEC and RCiEP Functions"
- Table 6-9, "Local Error Registers — PCI Express Functions Attached to Virtual Root Ports"

Register details are in the register chapters of this document. Also, reference the *PCI Express Base Specification Revision 3.0* for error register architectural details.

Table 6-7. Local Error Registers — PCI Express Root Ports

Location in Host Root Configuration Space	PCIe RP0 - RP7	Virtual PCIe RP0 - RP2	Register Name
PCI Header Type 1	PCICMD	PCICMD	Command
	PCISTS	PCISTS	Status
	SECSTS	SECSTS	Secondary status
	BCTL	BCTL	Bridge Control
PCIe Capability	DEVCTL	DEVCTL	Device Control
	DEVSTS	DEVSTS	Device Status
	ROOTCTL	ROOTCTL	Root Control
AER Capability	ERRUNCSTS	ERRUNCSTS	Uncorrectable Error Status
	ERRCORSTS	ERRCORSTS	Correctable Error Status
	AERCAPCTL	AERCAPCTL	AER Capabilities & Control
	AERHDRLOG1	AERHDRLOG1	Header Log (one entry)
	AERHDRLOG2	AERHDRLOG2	
	AERHDRLOG3	AERHDRLOG3	
	AERHDRLOG4	AERHDRLOG4	
	ROOTERRCMD	ROOTERRCMD	Root Error Command
	ROOTERRSTS	ROOTERRSTS	Root Error Status
	ERRSRCID	ERRSRCID	Error Source Identification

Table 6-8. Local Error Registers — PCI Express RCEC and RCiEP Functions

Location in Host Root Configuration Space	RCEC	SMBus-Host	Integrated Error Handler	Register Name
PCI Header Type 0	RCEC_PCICMD	PCICMD	GLREG_PCICMD	Command
	RCEC_PCISTS	PCISTS	GLREG_PCISTS	Status
PCIe Capability	RCEC_DEVCTL	DEVCTL	GLREG_DEVCTL	Device Control
	RCEC_DEVSTS	DEVSTS	RCEC_DEVSTS	Device Status
	RCEC_ROOTCTL			Root Control
AER Capability	RCEC_ERRUNCSTS	AERCAPHDR		Uncorrectable Error Status
	RCEC_ERRCORSTS	ERRUNCSEV		Correctable Error Status
	RCEC_ERRCORMSK	ERRCORSTS		Correctable Error Mask
	RCEC_AERCAPCTL	ERRCORMSK		AER Capabilities & Control
	RCEC_AERHDRLOG1	AERCAPCTL		Header Log (one entry)
	RCEC_AERHDRLOG2	AERHDRLOG1		
	RCEC_AERHDRLOG3	AERHDRLOG2		
	RCEC_AERHDRLOG4	AERHDRLOG3		
	RCEC_ROOTERRCMD	AERHDRLOG4		Root Error Command
	RCEC_ROOTERRSTS			Root Error Status
	RCEC_ERRSRCID			Error Source Identification

Table 6-9. Local Error Registers — PCI Express Functions Attached to Virtual Root Ports

Location in Host Root Configuration Space	LAN Primary Function and Virtual Functions	Intel® QuickAssist Technology Primary Function	Intel® QuickAssist Technology Virtual Functions	Register Name
PCI Header Type 0	CMD_STAT_REG	PPCICMD	PCICMD	Command
		PPCISTS	PCISTS	Status
PCIe Capability	DCTL_DSTS	PPDCNTL	DEVCTL	Device Control
		PPDSTAT	DEVSTS	Device Status
AER Capability	UEV	PPAERUCSEV	ERRUNCSEV	Uncorrectable Error Severity
	CES	PPAERCS	ERRCORSTS	Correctable Error Status
	CEM	PPAERCM	ERRCORMSK	Correctable Error Mask
	AECC	PPAERCAPCTL	AERCAPCTL	AER Capabilities & Control
	HL_DW1	PPAERHDRLOG1	AERHDRLOG1	Header Log (one entry)
	HL_DW2	PPAERHDRLOG2	AERHDRLOG2	
	HL_DW3	PPAERHDRLOG3	AERHDRLOG3	
	HL_DW4	PPAERHDRLOG4	AERHDRLOG4	

6.15 Error Reporting Flow — Legacy PCI Devices/Functions

- SATA0 and SATA1 Controllers
- USB Combo Controller
- LPC Controller
- SMBus - Legacy Controller
- SPI Controller
- HSUART Controller
- Intel® Trace Hub

Section 2.2.5 "Error Reporting Pins" of the *PCI Local Bus Specification, Revision 3.0*, defines the Parity Error (PERR#) and System Error (SERR#) error-reporting signal pins. According to the specification, these error signals can be enabled/disabled in the PCI Command register. PERR# is only used for the reporting of data parity errors during all PCI transactions except a Special Cycle. SERR# is for reporting address parity errors, data parity errors on the Special Cycle command, or any other system error where the result will be catastrophic. According to the specification, when an agent issues the SERR#, a non-maskable interrupt (NMI) is generated.

While there are no SoC signal pins involved, the integrated PCI devices/functions of the SoC use a similar way to report transaction errors to the SoC Root Complex, which internally translates error indications to platform-level events. An SERR# is considered an Uncorrectable, Fatal Error by the SoC. The SoC has no equivalent to PCI Parity Error PERR# signal because there is no true, physical PCI bus within the SoC. Even so, the SoC internal I/O fabric does detect and report internal parity errors to the SoC RCEC.

The Command (offset 4) and Status (offset 6) registers in device's Host Root Configuration Space play a role in how the device reports errors and the transaction errors that are detected. See Section 3.7.4 "Error Reporting" of the *PCI Local Bus Specification, Revision 3.0* for additional details.

Besides using its PCI Status register to report SERR# errors, the SATA Controllers report Fatal Errors in the General Configuration (SATAGC) register located at offset 9Ch of the SATA Configuration Space.

Besides a PCI Status register, the USB Combo Controller reports Fatal Errors in the USB Status (USBSTS) register located in Host Root Memory Space at MBAR plus offset 84h.

The LPC, SMBus - Legacy, SPI, and HSUART Controllers can each report a detected Uncorrectable Fatal Error through its PCI Device Status Register (STS) located at offset 6h for the function in Host Root Configuration Space. The Local Error Registers for the Intel® Trace Hub are not documented in this document.

The Error Status of each of the legacy PCI devices is represented in the SoC Global Error Register.

Errors detected by the SoC Legacy PCI devices are routed to the SoC Global Error logic/registers and can generate an NMI or SMI, and optionally assert the SoC ERROR_N[2:0] output signal pins. Machine Check events do not occur from these types of hardware errors.

6.15.1 Local Error Registers

Table 6-10, "Local Error Registers — SATA, USB, LPC and SMBus-Legacy" and Table 6-11, "Local Error Registers — SPI and HSUART" list the registers associated with the error control, status, and reporting flow for the PCIe devices/functions of the SoC.

Table 6-10. Local Error Registers — SATA, USB, LPC and SMBus-Legacy

Location in Host Root Configuration Space	SATA	USB Combo	LPC	SMBus-Legacy	Register Name
PCI Header Type 0	CMD	CMD	CMD	CMD	Command
	STS	STS	STS	DS	Status
Device-Specific	SATAGC	XHCC1			n/a
		XHCC3			n/a
		USBSTS			n/a

Table 6-11. Local Error Registers — SPI and HSUART

Location in Host Root Configuration Space	SPI	HSUART	Register Name
PCI Header Type 0	BIOS_SPI_STS_CMD	CMD_STAT_REG	Command
			Status
Device-Specific	BIOS_SPI_UR_STS_CTL	DSC	n/a

6.16 Error Reporting Flow — Non-PCI devices

These internal devices do not use the PCI or PCIe error-reporting mechanisms. These devices are part of the SoC UnCore (System Agent) and power control circuitry.

- System Agent - A Unit
- System Agent - B Unit
- System Agent - D Unit 0
- System Agent - D Unit 1
- SoC Power Management Unit (PMU)

The A, B, and two D Units of the SoC System Agent, also referred to as the "UnCore," protect the internal data interfaces with parity. Temporarily-stored data are protected with byte parity. The UnCore reports internal hardware errors by generating Machine Check Errors (MCERR) to the CPUs (MC Banks 6, 4, 7, and 8 respectively). The MCERR can also be routed to the MCERR_N output signal pin of the SoC. See Figure 6-5, "MCERR and IERR Handling." System Agent detected errors can also be routed directly to the SoC Global Error logic and logged in the SoC Global Error registers. See Figure 6-6, "Local and Global Error Register Structure."

The SoC Power Management Unit (PMU) detects Internal Errors (IERR) and can generate Machine Check events (MC Bank 5) to the CPUs. The IERR can also be routed to the IERR_N output signal pin of the SoC. See Figure 6-5, "MCERR and IERR Handling."

The D Units 0 and 1 detect and correct single-bit ECC (Correctable) errors. These can generate CMCI. See Section 6.6.2.3, "Corrected Machine-Check error Interrupt (CMCI)."

The SoC detects and logs Correctable Errors and Uncorrectable Errors encountered during DRAM memory Patrol Scrubbing and Demand Scrubbing. These can generate a Machine Check event and MCERR_N output signal. As an option, these errors can also be routed to the Uncorrectable (Double Bit) Read Error, bit 1 (UCE), and the Correctable (Single Bit) Read Error, bit 0 (SBE), of the DRAM Error Status (DERRSTS) register. The DERRSTS register is located in Host Root Memory Space at SBREG_BAR plus offset 10_0124h. For Memory Controller 1, the DERRSTS register is located at SBREG_BAR, offset 12_0124h. From there they can be routed to the SoC Global Error logic/registers and generate an NMI or SMI, and optionally assert the SoC ERROR_N[2:0] output signal pins.

PMU hardware errors also can generate Machine Check events and generate the IERR_N and MCERR_N signal pins. However, the PMU errors are not reported directly to the Global Error logic/registers. Instead they are reported by the Integrated Error Handler (IEH) through the GLREG (B0:D4:F0). This is similar to the flow used by the SoC I/O fabric. See Section 6.17, "Error Reporting Flow — I/O Fabric."

6.16.1 Local Error Registers

Both Correctable Errors and Uncorrectable Errors are reported and logged at the local level. See Figure 6-10, "Error Signaling and Logging for Non-PCI Devices."

The Uncorrectable Error Severity Register further categorizes the error as a Fatal Error or Non-Fatal Error. Error reporting can be masked. The First Error and Next Error are logged for each unit and a selectable error counter register is available.

The Local Error registers are listed in Table 6-12, "Local Error Registers — A-Unit and B-Unit" and Table 6-13, "Local Error Registers — D-Units."

Figure 6-10. Error Signaling and Logging for Non-PCI Devices



The local errors of the A-Unit, B-Unit, and the two D-Units are units are accumulated and directed to bits of the SoC Global Error Registers as shown in Figure 6-6, "Local and Global Error Register Structure."

The A-Unit and B-Unit Local Error registers and logs are located in Host Root Memory Space as offset addresses from MCHBAR:

- A-Unit: Offset 6588h through 65B8h
- B-Unit: Offset 6E04h through 6E3Ch

Table 6-12. Local Error Registers — A-Unit and B-Unit

A-Unit	B-Unit	Register Name
A_CR_UNCERRSTS_0_0_0_MCHBAR	B_CR_UNCERRSTS_0_0_0_MCHBAR	Uncorrectable Error Status Register
A_CR_UNCERRMSK_0_0_0_MCHBAR	B_CR_UNCERRMSK_0_0_0_MCHBAR	Uncorrectable Error Mask Register
A_CR_UNCERRSEV_0_0_0_MCHBAR	B_CR_UNCERRSEV_0_0_0_MCHBAR	Uncorrectable Error Severity Register
A_CR_UNCFERRSTS_0_0_0_MCHBAR	B_CR_UNCFERRSTS_0_0_0_MCHBAR	First Uncorrectable Error Register
A_CR_UNCNERRSTS_0_0_0_MCHBAR	B_CR_UNCNERRSTS_0_0_0_MCHBAR	Next Uncorrectable Error Register
A_CR_UNCERRCNTSEL_0_0_0_MCHBAR	B_CR_UNCERRCNTSEL_0_0_0_MCHBAR	Uncorrectable Error Select Register
A_CR_UNCERRCNT_0_0_0_MCHBAR	B_CR_UNCERRCNT_0_0_0_MCHBAR	Uncorrectable Error Count
A_CR_CORERRSTS_0_0_0_MCHBAR	B_CR_CORERRSTS_0_0_0_MCHBAR	Correctable Error Status Register
A_CR_CORERRMSK_0_0_0_MCHBAR	B_CR_CORERRMSK_0_0_0_MCHBAR	Correctable Error Mask Register
A_CR_CORFERRSTS_0_0_0_MCHBAR		First Correctable Error Register
A_CR_CORNERRSTS_0_0_0_MCHBAR		Next Correctable Error Register
A_CR_CORERRCNTSEL_0_0_0_MCHBAR		Correctable Error Count Select
A_CR_CORERRCNT_0_0_0_MCHBAR		Correctable Error Count
	B_CR_DPHDRLOG_LO_0_0_0_MCHBAR	Data Parity Header Log
	B_CR_DPHDRLOG_HI_0_0_0_MCHBAR	
	B_CR_DPADDRLOG_LO_0_0_0_MCHBAR	Data Parity Address Log
	B_CR_DPADDRLOG_HI_0_0_0_MCHBAR	
	B_CR_DERRADDRLOG_LO_0_0_0_MCHBAR	Error Address Log
	B_CR_DERRADDRLOG_HI_0_0_0_MCHBAR	
A_CR_PARITY_CTL_0_0_0_MCHBAR	B_CR_PARITY_CTL_0_0_0_MCHBAR	Parity and Error Injection Control
A_CR_IOMMU_PARITYINJ		Parity Error Injection

The D-Units report single-bit errors and double-bit errors that occur during reads of system memory. SoC internal buffer errors and DDR interface command and address parity errors are also reported. Memory errors are reported when Demand Scrub and Patrol Scrub are performed. D-Unit0 is Memory Controller 0 and D-Unit1 is Memory Controller 1. The Local Error registers are listed in Table 6-13, "Local Error Registers — D-Units."

The D-Unit Local Error registers are located in Host Root Memory Space as offset addresses from SBREGBAR:

- D-Unit0: Offset 10_0120h through 10_0130h
- D-Unit1: Offset 12_0120h through 12_0130h

The D-Unit Local Error logs and counters are located in Host Root Memory Space as offset addresses from SBREGBAR:

- D-Unit0: Offset 10_0064h through 10_0090h
- D-Unit1: Offset 12_0064h through 12_0090h

Table 6-13. Local Error Registers — D-Units

D-Unit 0	D-Unit 1	Register Name
UCELOG	UCELOG	Uncorrectable Error Log
UCEADDR	UCEADDR	Uncorrectable Error Address
SBELOG	SBELOG	Correctable (Single Bit) Error Log
SBEADDR	SBEADDR	Correctable Error Address
SBECNT0	SBECNT0	SBE Count for Rank 0
SBECNT1	SBECNT1	SBE Count for Rank 1
SBECNT2	SBECNT2	SBE Count for Rank 2
SBECNT3	SBECNT3	SBE Count for Rank 3
SBEACC0	SBEACC0	SBE Accumulator for Rank 0
SBEACC1	SBEACC1	SBE Accumulator for Rank 1
SBEACC2	SBEACC2	SBE Accumulator for Rank 2
SBEACC3	SBEACC3	SBE Accumulator for Rank 3
FERRNERR	FERRNERR	First Error and Next Error Register
DERRSTS	DERRSTS	Error Status Register
DERRMSKSEV	DERRMSKSEV	Error Mask and Severity
DERRCNTSEL	DERRCNTSEL	Uncorrectable Error Count Select
DERRCNT	DERRCNT	Uncorrectable Error Count
ERRINJCTL	ERRINJCTL	Error Injection Control
ERRINJADDR	ERRINJADDR	Error Injection Address
ERRINJAMSK	ERRINJAMSK	Error Injection Address Mask
ERRINJDATA0	ERRINJDATA0	Error Injection Data 0
ERRINJDATA1	ERRINJDATA1	Error Injection Data 1

6.16.2 Error Injection Control and Registers — Memory Controller

The SoC provide an error-injection mechanism for the D-Unit. The control, address, mask and data for this mechanism is located in Host Root Memory Space as offset addresses from SBREGBAR:

- D-Unit0: Offset 10_0134h through 10_0144h
- D-Unit1: Offset 12_0134h through 12_0144h

The error-injection registers are listed in Table 6-13, "Local Error Registers — D-Units."

6.17 Error Reporting Flow — I/O Fabric

The internal I/O fabric is parity protected. Both the command and data paths of the internal I/O fabric are end-to-end parity protected. The System Agent checks the I/O fabric parity on the command when a command is received from an I/O agent. If a command parity error is detected the packet is dropped and an error is reported. In addition, the System Agent does not accept new requests from the faulty I/O agent.

When an I/O agent receives a request from the System Agent, the I/O agent checks for both command and data parity. If a command parity error is detected, the agent drops the request and logs the error.

For Root Ports, if a data parity error is detected from a request from the System Agent, the Root Port forwards the error (also known as data poisoning) by setting the set the EP bit in the Transaction-Level Packet (TLP) of the request and forwards the request downstream over the PCI Express link. The Root Port also sets bit 15, Detected Parity Error (DPE), of its Primary Status Register (offset 6h) and sets bit 12, Poisoned TLP Status, of its Uncorrectable Error Status Register that is part of the AER capability structure. The Root Port indicates this non-fatal event to the Root Complex by sending a ERR_COR message with bit 13, Advisory Non-Fatal Error Status, of its AER Correctable Error Status Register.

6.17.1 Local Error Registers

The I/O fabric Local Errors are reported by the Integrated Error Handler (IEH) through the GLREG (B0:D4:F0) device-specific registers in Host Root Configuration Space starting at offset 280h. All I/O fabric errors are Uncorrectable Errors. See Table 6-14, "Local Error Registers — Integrated Error Handler (IEH)." All of these Uncorrectable Errors are also reported to the RCEC (B0:D5:F0) using Uncorrectable Internal Error (UIE) status (Bit 22) of the RCEC_ERRUNCSTS register.

Table 6-14. Local Error Registers — Integrated Error Handler (IEH)

Location in Host Root Configuration Space	GLREG	Register Name
Device-Specific	GLREG_LERRUNCSTS	Uncorrectable Error Status
	GLREG_LERRUNCMSK	Uncorrectable Error Mask
	GLREG_LFERRUNCSTS	Uncorrectable First Error Status
	GLREG_LNERRUNCSTS	Uncorrectable Next Error Status
	GLREG_LUNCERRCNTSEL	Uncorrectable Error Counter Selection
	GLREG_LUNCERRCNT	Uncorrectable Error Counter
	GLREG_LFERRHDRLOG1	Header Log (one entry)
	GLREG_LFERRHDRLOG2	
	GLREG_LFERRHDRLOG3	
	GLREG_LFERRHDRLOG4	

6.18 SoC Error Handling Summary

Table 6-15, "Summary of Default Error Logging and Responses" summarizes many of the SoC-detected hardware errors, their error severity, and the Local and Global Error registers used to report and log them.

Table 6-15. Summary of Default Error Logging and Responses (Sheet 1 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
Integrated Error Handler Errors				
A0	IEH Detected Configuration Register Parity Error	Uncorrectable (Fatal)	The SoC detects and logs the error.	FERR/NERR is logged in IEH and Global Fatal Error Log registers: GLREG_LERRUNCSTS GLREG_LFERRUNCSTS GLREG_LNERRUNCSTS GLREG_LFERRHDRLOG GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME Header is logged.
A1	Configuration agent detected Fabric Command Parity Error		Internal I/O Bus Command Parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A2	Configuration Agent Fabric Data Parity Error		SoC detects and logs the error.	
A3	Configuration agent detected negatively decoded transaction Error		SoC detects and logs the error.	
A4	Internal Fabric detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A5	Internal Fabric detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A6	Internal Fabric detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A7	Internal Fabric detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A8	Internal Fabric detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A9	Internal Fabric detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	
A10	Internal Fabric Intel® ME detected Command Parity Error		Internal fabric command parity errors are detected at the output of the upstream and downstream queues when a request is granted. Further arbiter grants are inhibited.	

Table 6-15. Summary of Default Error Logging and Responses (Sheet 2 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
B-Unit Errors				
B0	Read data correctable ECC error	Correctable	Read data is corrected and written back to memory	FERR/NERR is logged in Bunit and Global Fatal Error Log Registers: BCORERRSTS BCORFERRSTS BCORNERRSTS GLREG_GCOERRSTS GLREG_GCOFERRSTS GLREG_GCONERRSTS GLREG_GCOFERRTIME These are also logged in Bunit MCA bank registers.
B1	Unexpected Completion	Uncorrectable (Fatal)	SoC detects and logs the error.	FERR/NERR is logged in Bunit and Global Fatal Error Log Registers: BUNCERRSTS BUNCFERRSTS BUNCNERRSTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME These are also logged in Bunit MCA bank registers.
B2	BRAM Write Data Parity Error			
B3	Memory Controller to SSA Data Parity Error			
B4	Source Address Decoder (SAD) Error			
B5	Ucode/xucode Errors			
B6	Read data uncorrectable ECC Error		Read data is sent with bad parity to the B-Unit.	
B8	Protected Memory region space violated Error		Protected memory violation	

Table 6-15. Summary of Default Error Logging and Responses (Sheet 3 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
LAN Controllers Errors				
C0	Advisory Non-fatal Error (ANFE)	Correctable		Error is logged in GbE Local and Global Correctable Error Log registers: CES GCORERRSTS GCORFERRSTS GCORNERRSTS GCORFERRTIME
C1	Bad TLP Error (PTLPE)	Uncorrectable (Non-Fatal)	ERR_Non-fatal sent to root complex. Header is logged. A poisoned completion is ignored and the request can be retried after timeout. If enabled, the error is reported.	Error is logged in GbE Local and Global Non-fatal Error Log Registers: UES GNERRST GNFERRST GNNERRST GNFERRTIME
C2	Completion Timeout Error (CTE)		Error severity is non-fatal (default case): Send error message If advisory Retry the request once and send advisory error message on each failure. If fails, send uncorrectable error message. Error severity is defined as fatal: Send uncorrectable error message	
C3	Completer Abort Error (CAE)		ERR_Non-fatal sent to root complex. Header is logged. Send completion with CA.	
C4	Unexpected Completion Error (UCE)		ERR_Non-fatal sent to root complex. Header is logged. Discard TLP.	
C5	Unsupported Request Error (URE)		ERR_Non-fatal sent to root complex. Header is logged. Send completion with UR.	
C6	Malformed TLP Error (MTLPE)	Uncorrectable (Fatal)	ERR_Fatal sent to root complex. Header is logged. Drop the packet and free FC credits.	Error is logged in GbE Local and Global Fatal Error Log Registers: UES GFERRST GFFERRST GFNERRST GFFERRTIME

Table 6-15. Summary of Default Error Logging and Responses (Sheet 4 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
Memory Controller Errors				
D0	Patrol Scrub/Demand scrub correctable ECC Error	Correctable	Read data is corrected and written back to memory	FERR/NERR is logged in Dunit and Global Fatal Error Log Registers: DERRSTS DFERRNERR SBELOG UCELOG GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME These are also logged in Dunit MCA bank registers.
D1	Write Data Buffer read parity Error	Uncorrectable (Fatal)		
D2	Patrol scrub uncorrectable ECC Error		Read data is sent with bad parity to the B-Unit.	
D3	Demand read uncorrectable ECC Error		Read data is sent with bad parity to the B-Unit.	
D4	DDR4 Add/Cmd parity Error			

Table 6-15. Summary of Default Error Logging and Responses (Sheet 5 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
PCIe* Root Port Errors				
E0	Receiver Error (RE)	Correctable	Respond per *PCI-E Specification*	Log error per PCI Express* AER requirements for these correctable errors/message. If the PCIe correctable error is forwarded to the Global Error registers, the error is logged in Global Correctable Log registers: GCOERRST GCOFERRST GCONERRST GLREG_GCOFERRTIME
E1	Bad TLP Error (BTLPE)			
E2	Bad DLLP Error (BDLLPE)			
E3	Replay Number Rollover Error (RNRE)			
E4	Replay Timer Time-out Error (RTTE)			
E5	Header Log Overflow Error (HLOE)			
E6	Received ERR_COR Message from Downstream Device			
E7	Poisoned TLP Error (PTLPE)	Uncorrectable (Non-Fatal)	SoC logs the error.	Log error per PCI Express AER requirements for the corresponding error/message. If the PCIe uncorrectable error is forwarded to the Global Error registers, the error is logged in Global Non-Fatal Log registers: GNFERRST GNFFERRST GNFNERRST GNFFERRTIME
E8	Completion Time-out Error (CTE)			
E9	Completer Abort Error (CAE)			
E10	Unexpected Completion Error (UCE)		Respond Per *PCI-E Specification*	
E11	Unsupported Request Error (URE)		SoC logs the error.	
E12	ACS Violation Error (ACSE)			
E13	MC Blocked TLP Error (MCE)			
E14	Atomic Egress Blocked Error (AEBE)			
E15	Received ERR_NONFATAL Message from Downstream Device		Respond per *PCI-E Specification*	
E16	Data Link Protocol Error (DLPE)	Uncorrectable (Fatal)	Respond per *PCI-E Specification*	Log error per PCI Express AER requirements for the corresponding error/message. If the PCIe uncorrectable error is forwarded to the Global Error registers, the error is logged in Global Fatal Log registers: GFAERRST GFAFERRST GFANERRST GLREG_GFAFERRTIME
E17	Surprise Link Down Error (SLDE)			
E18	Flow Control Error (FCE)			
E19	Receiver Overflow Error (ROE)			
E20	Malformed TLP Error (MTLPE)			
E21	Uncorrectable Internal Error (UIE)			
E22	Received ERR_FATAL Message from Downstream Device			

Table 6-15. Summary of Default Error Logging and Responses (Sheet 6 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
SMBus Errors				
F0	Retry Error (RETRYERR): An error due to SMT master transaction exceeding (non-collision) retry count as specified in RPOLICY.RETRY	Uncorrectable (Fatal)	The SoC detects and logs the error.	FERR/NERR is logged in the Global Fatal Error Log registers: SMT_ERRUNCSTS SMT_FERRUNCSTS SMT_NERRUNCSTS SMT_FERRHDRLOG GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME

Table 6-15. Summary of Default Error Logging and Responses (Sheet 7 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
Intel® QAT Errors				
G0	Advisory Non-fatal Error (ANFE)	Correctable	ERR_COR sent to root complex	Error is logged in Intel® QAT Local and Global Correctable Error Log Registers: PPAERCS/VPAERCS GCORERRST GCORFERRST GCORNERRST GCORFERRTIME
G1	Corrected Internal Error (CIE)			
G2	Poisoned TLP Error (PTLPE)	Uncorrectable (Non-fatal)	Poisoned completions: ERR_COR Posted Write: ERR_NONFATAL NP Write: ERR_NONFATAL; Completion returned with UR	Error is logged in Intel® QAT Local and Global Non-fatal Error Log Registers: PPAERUCS/VPAERUCS PPAERHDRLOG/VPAERHDRLOG GNERRST GNFERRST GNNERRST GNFERRTIME
G3	Completion Timeout Error (CTE)		ERR_COR sent to root complex	
G4	Completer Abort Error (CAE)		P: request: ERR_NONFATAL NP request: ERR_COR; return completion with CA status	
G5	Unexpected Completion Error (UCE)		ERR_COR; completion is dropped	
G6	Unsupported Request Error (URE)		P: ERR_NONFATAL NP: ERR_COR; return completion with UR status	
G7	Malformed TLP Error (MTLPE)	Uncorrectable (Fatal)	ERR_NONFATAL (if sev = 0) ERR_FATAL (if sev = 1); When a malformed packet is detected, the packet is dropped and the error is logged.	Error is logged in Intel® QAT Local and Global Fatal Error Log Registers: PPAERUCS/VPAERUCS PPAERHDRLOG/VPAERHDRLOG GFERRST GFFERRST GFNERRST GFFERRTIME
G8	Uncorrectable Internal Error (UIE)		ERR_NONFATAL (if sev = 0) ERR_FATAL (if sev = 1)	
SATA Errors				
H0	When a set event occurs to configuration bits SATAGC.URD=1, during SATAGC.URRE=1 and CMD.SEE=1 for controller 1.	Uncorrectable (Fatal)	Treat as UR and initiate DO_SERR	Error is logged in PCISTS and Global Fatal Error Log registers: PCISTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME
H1	When a set event occurs to configuration bits STS.DPE=1 during CMD.PEE=1 and CMD.SEE=1 for controller 1.		For MMR/CFG access, no update on destination & UR for NP req. Error logged and Do_SERR initiated. For SATA data downstream, poison CRC but no error logging or reporting	
H2	When a set event occurs to configuration bits STS.STA=1 during CMD.SEE=1 for controller 1.		Initiate DO_SERR.	

Table 6-15. Summary of Default Error Logging and Responses (Sheet 8 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
USB Errors				
J0	Received downstream completion with unsupported request status	Uncorrectable (Fatal)	Set PCI space STS.RMA, and; Set MMIO space USBSTS.HSE. Note that USBSTS.HSE = 1, and USBCMD.HSEE = 1 will trigger Out-Of-Band error indication from Fresco IP, and SoC I/O fabric Gasket will set STS.SSE and send SERR if XHCC1.RMTASERR = 1 and CMD.SERR = 1. Drop cycles (return credits) and signal unsuccessful completion.	Error is logged in PCISTS and Global Fatal Error Log registers: PCISTS, USBSTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME
J1	Received downstream completion with completer abort status		Set PCI space STS.RTA, and; Set MMIO space USBSTS.HSE. Note that USBSTS.HSE = 1, and USBCMD.HSEE = 1 will trigger Out-Of-Band error indication from Fresco IP, and SoC I/O fabric Gasket will set STS.SSE and send SERR if XHCC1.RMTASERR = 1 and CMD.SERR = 1. Drop cycles (return credits) and signal unsuccessful completion.	
J2	Received downstream memory cycles when PMCS.DS = D3.			
J3	Received downstream memory cycles when CMD.MSE = 0.			
J4	Received downstream memory cycles which is out of range due to recent memory space/limit change.			
J5	Received downstream memory cycles crossing QW aligned address boundary.			
J6	Received downstream request with error poisoned.			
J7	Received downstream completion with error poisoned.			
J8	Internal fabric Data parity error		The SoC detects and logs the error.	
J9	Internal fabric command parity error		The SoC detects and logs the error.	

Table 6-15. Summary of Default Error Logging and Responses (Sheet 9 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
LPC Errors				
K0	LPC Sync Error	Uncorrectable (Fatal)	SoC detects and logs the error.	Error is logged in PCISTS and Global Fatal Error Log registers: PCISTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME
HSUART Errors				
L0	HSUART error	Uncorrectable (Fatal)	The SoC detects and logs the error. Do_Serr initiated.	Error is logged in PCISTS and Global Fatal Error Log Registers: PCISTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME

Table 6-15. Summary of Default Error Logging and Responses (Sheet 10 of 10)

ID	Error	Error Type (Default Severity)	Transaction Response	Default Error Logging[1]
VT-d Errors				
I6	Tag Array Parity Error during Context Cache Lookup	Correctable	A tag array parity error was detected in the VT-d caches.	Error is logged in Aunit Local and Global Correctable Error Log Registers: GCORERRST GCORFERRST GCORNERRST GCORFERRTIME
I7	Tag Array Parity Error during L2 Lookup			
I8	Tag Array Parity Error during L3 Lookup			
I9	Tag Array Parity Error during L4 Lookup			
I10	IOTLB Tag Array Parity Error			
I11	Data Parity Error during Context Cache Lookup	Uncorrectable (Fatal)	A parity error was detected in the VT-d caches.	FERR/NERR is logged in Aunit and Global Fatal Error Log Registers: AUNCERRSTS AUNCFERRSTS AUNCNERRSTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME
I12	Data Parity Error during L2 Lookup			
I13	Data Parity Error during L3 Lookup			
I14	Data Parity Error during L4 Lookup			
I15	IOTLB Data Parity Error			
B8	Protected Memory region space violated Error	Uncorrectable (Fatal)	Protected memory violation	FERR/NERR is logged in Bunit and Global Fatal Error Log Registers: BUNCERRSTS BUNCFERRSTS BUNCNERRSTS GLREG_GFAERRSTS GLREG_GFAFERRSTS GLREG_GFANERRSTS GLREG_GFAFERRTIME
M0	VT-d faults	Uncorrectable (Non-Fatal)	Log error per VT-d spec in Fault Record.	VTDBAR.FRCD

1. This column notes the logging registers used assuming the error severity default remains. The error severity dictates the actual logging registers used upon detecting an error.

6.19 Register Map

Figure 6-11, "Register Map" shows the associated Global and Local Error Registers (GLREG) and the Root Complex Event Collector (RCEC) from a system software perspective.

Figure 6-11. Register Map



6.19.1 Registers in Configuration Space—GLREG

Table 6-16. Registers in Host Configuration Space (Sheet 1 of 2)

Configuration Space of B0:D4:F0 (hex)	Register Short Name	Description
0	GLREG_VID	GLREG Vendor ID
2	GLREG_DID	GLREG Device ID
4	GLREG_PCICMD	GLREG PCI Command
6	GLREG_PCISTS	GLREG PCI Status
8	GLREG_RID	GLREG Revision ID
9	GLREG_CC	GLREG Class Code
C	GLREG_CLS	GLREG Cacheline Size
16	GLREG_HDR	GLREG Header Type
2C	GLREG_SVID	GLREG Subsystem Vendor ID
2E	GLREG_SID	GLREG Subsystem ID
34	GLREG_CAPPTR	GLREG Capabilities Pointer
3C	GLREG_INTL	GLREG Interrupt Line
3D	GLREG_INTP	GLREG Interrupt Pin
40	GLREG_EXPCAPLST	GLREG PCI Express Capability List
42	GLREG_EXPCAP	GLREG PCI Express Capabilities
44	GLREG_DEVCAP	GLREG Device Capabilities
48	GLREG_DEVCTL	GLREG Device Control
4A	GLREG_DEVSTS	GLREG Device Status
200	GLREG_GCOERRSTS	GLREG Global Correctable Error Status
204	GLREG_GNFERRSTS	GLREG Global Non-Fatal Error Status
208	GLREG_GFAERRSTS	GLREG Global Fatal Error Status
20C	GLREG_GERRMSK	GLREG Global Error Mask
210	GLREG_GCOFERRSTS	GLREG Correctable FERR Status
214	GLREG_GCONERRSTS	GLREG Global Correctable NERR Status
218	GLREG_GNFFERRSTS	GLREG Global Non-Fatal FERR Status
21C	GLREG_GNFNERRSTS	GLREG Global Nonfatal NERR Status
220	GLREG_GFAFERRSTS	GLREG Global Fatal FERR Status
224	GLREG_GFANERRSTS	GLREG Global Fatal NERR Status
228	GLREG_GTIME	GLREG Global Error Timer
230	GLREG_GCOFERRTIME	GLREG Global Correctable FERR Error Time Stamp
238	GLREG_GNFFERRTIME	GLREG Global Nonfatal FERR Error Time Stamp
240	GLREG_GFAFERRTIME	GLREG Global Fatal FERR Error Time Stamp
248	GLREG_GSYSEVTSTS	GLREG Global System Event Status
24C	GLREG_GSYSEVTMSK	GLREG Global System Event Mask
250	GLREG_GSYSEVTMAP	GLREG Global System Event Map
254	GLREG_ERRPINCTRL	GLREG Error Pin Control

Table 6-16. Registers in Host Configuration Space (Sheet 2 of 2)

Configuration Space of B0:D4:F0 (hex)	Register Short Name	Description
258	GLREG_ERRPINSTS	GLREG Error Pin Status
25C	GLREG_ERRPINDATA	GLREG Error Pin Data
280	GLREG_LERRUNCSTS	GLREG Uncorrectable Error Status
284	GLREG_LERRUNCMSK	GLREG Uncorrectable Error Mask
288	GLREG_LFERRUNCSTS	GLREG Uncorrectable First Error Status
28C	GLREG_LNERRUNCSTS	GLREG Uncorrectable Next Error Status
290	GLREG_LUNCERRCNTSEL	GLREG Uncorrectable Error Counter Selection
294	GLREG_LUNCERRCNT	GLREG Uncorrectable Error Counter
298	GLREG_LFERRHDRLOG1	GLREG Header Log
29C	GLREG_LFERRHDRLOG2	GLREG Header Log
2A0	GLREG_LFERRHDRLOG3	GLREG Header Log
2A4	GLREG_LFERRHDRLOG4	GLREG Header Log

6.19.2 Registers in Configuration Space—RCEC

Table 6-17. Registers in Host Configuration Space (Sheet 1 of 2)

Configuration Space of B0:D5:F0 (hex)	Register Short Name	Description
0	RCEC_VID	RCEC Vendor ID
2	RCEC_DID	RCEC Device ID
4	RCEC_PCICMD	RCEC PCI Command
6	RCEC_PCISTS	RCEC PCI Status
8	RCEC_RID	RCEC Revision ID
9	RCEC_CC	RCEC Class Code
C	RCEC_CLS	RCEC Cacheline Size
E	RCEC_HDR	RCEC Header Type
2C	RCEC_SVID	RCEC Subsystem Vendor ID
2E	RCEC_SID	RCEC Subsystem ID
34	RCEC_CAPPTR	RCEC Capabilities Pointer
3C	RCEC_INTL	RCEC Interrupt Line
3D	RCEC_INTP	RCEC Interrupt Pin
40	RCEC_EXPCAPLST	RCEC PCI Express Capability List
42	RCEC_EXPCAP	RCEC PCI Express Capabilities
44	RCEC_DEVCAP	RCEC Device Capabilities
48	RCEC_DEVCTL	RCEC Device Control
4A	RCEC_DEVSTS	RCEC Device Status
5C	RCEC_ROOTCTL	RCEC Root Control
5E	RCEC_ROOTCAP	RCEC Root Capabilities
60	RCEC_ROOTSTS	RCEC Root Status
80	RCEC_PMCAPLST	RCEC Power Management Capability List
82	RCEC_PMCAP	RCEC Power Management Capabilities
84	RCEC_PMCSR	RCEC Power Management Control / Status
90	RCEC_MSICAPLST	RCEC MSI Capability List
92	RCEC_MSICTL	RCEC MSI Message Control
94	RCEC_MSIADDR	RCEC MSI Message Address
98	RCEC_MSIDATA	RCEC MSI Message Data
9C	RCEC_MSIMSK	RCEC MSI Mask Bit
A0	RCEC_MSIPENDING	RCEC MSI Pending Bit
100	RCEC_AERCAPHDR	RCEC Advanced Error Reporting Extended Capability Header
104	RCEC_ERRUNCSTS	RCEC Uncorrectable Error Status
108	RCEC_ERRUNCMSK	RCEC Uncorrectable Error Mask
10C	RCEC_ERRUNCSEV	RCEC Uncorrectable Error Severity
110	RCEC_ERRCORSTS	RCEC Correctable Error Status

Table 6-17. Registers in Host Configuration Space (Sheet 2 of 2)

Configuration Space of B0:D5:F0 (hex)	Register Short Name	Description
114	RCEC_ERRCORMSK	RCEC Correctable Error Mask
118	RCEC_AERCAPCTL	RCEC Advanced Error Capabilities and Control
11C	RCEC_AERHDRLOG1	RCEC Header Log
120	RCEC_AERHDRLOG2	RCEC Header Log
124	RCEC_AERHDRLOG3	RCEC Header Log
128	RCEC_AERHDRLOG4	RCEC Header Log
12C	RCEC_ROOTERRCMD	RCEC Root Error Command
130	RCEC_ROOTERRSTS	RCEC Root Error Status
134	RCEC_ERRSRCID	RCEC Error Source Identification
150	RCEC_RCECEPACAPHDR	RCEC Root Complex Event Collector Endpoint Association Extended Capability Header
154	RCEC_ABMRCIEP	RCEC Association Bitmap for Root Complex Integrated Endpoints

§ §

7 Clock Architecture

The SoC requires one external 25-MHz crystal and one external 32.768-kHz crystal for internal clock generation. Some internal clocks can be configured by Soft Straps and by registers accessible to UEFI IA Firmware (BIOS).

Figure 7-1. What is Covered in This Chapter



7.1 Signal Descriptions

The signal descriptions are shown in Table 7-1. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. The Direction/Type column of Table 7-1 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.
- Differential = Differential signal pair. Two pins: Positive; Negative.

Table 7-1. Signal Names and Descriptions (Sheet 1 of 2)

Signal Names	Direction	Shared	Description
CLK_X1_PAD	I	No	**Clock Crystal - 25 MHz**. The SoC uses the crystal for its internal oscillators and PLLs to generate internal clocks of various speeds which are controlled and distributed throughout the SoC.
CLK_X2_PAD	O	No	
ICLKRCOMP	I,O	No	**ISCLK RCOMP:** Compensation resistor for the CLK_OUT_DP[4:0], CLK_OUT_DN[4:0] differential output signals. The resistor is used by the internal ISCLK circuitry to calibrate the PCIe reference-clock driver impedance to comply with the PCIe specification for REFCLK. To achieve 50-Ω driver/trace impedance, ICLKRCOMP must be connected to a 200-Ω resistor to VSS on the platform board. To achieve a 42.5- Ω driver impedance/trace, a 169-Ω resistor must be used.
RTC_X1_PAD RTC_X2_PAD	I,O	No	**Clock Crystal - 32.768 KHz**: The SoC uses the crystal for its internal Real-Time Clock (RTC) oscillator. The clock is used internally and drives the PMU_SUSCLK output signal.
BVCCRTC_EXTPAD	I,O	No	**External Pad for RTC Power Well:** Must be connected to an external 0.1-µF capacitor on the platform board.
FLEX_CLK_SE[1:0]	O	Yes	**Flex Clock.** These single-ended output signals are general-purpose clocks that can be used by the platform board.
PMU_SUSCLK	O	Yes	Chapter 16, "Power Management Controller (PMC)"
SVID_CLK	O-OD	Yes	Chapter 34, "Power Management"
SATA0_SCLK SATA1_SCLK	O-OD	Yes	Chapter 12, "SATA Controller"
EMMC_CLK	I,O	Yes	Chapter 17, "Embedded Multi-Media Card (eMMC)"
DDR0_CLK_DP[3:0] DDR0_CLK_DN[3:0] DDR1_CLK_DP[3:0] DDR1_CLK_DN[3:0]	O, Differential	No	Chapter 9, "Memory Controller"
CLK_OUT_DP[4:0] CLK_OUT_DN[4:0]	O, Differential	No	Chapter 11, "PCI Express Root Ports (RP)"
LPC_CLKOUT[1:0]	O	Yes	Chapter 20, "Low Pin Count (LPC) Controller"
SMB_LAN_CLK	I,O-OD	Yes	Chapter 13, "LAN Controllers"
LAN0_PORT0_I2C_CLK LAN0_PORT1_I2C_CLK LAN1_PORT0_I2C_CLK LAN1_PORT1_I2C_CLK	I,O-OD	Yes	Chapter 13, "LAN Controllers"
LAN_MDC	O	Yes	Chapter 13, "LAN Controllers"
NCSI_CLK_IN	I	Yes	Chapter 13, "LAN Controllers"
SPI_CLK	I,O	Yes	Chapter 19, "Serial Peripheral Interface (SPI)"
SMB_LEG_CLK	I,O-OD	Yes	Chapter 28, "SMBus Controller - Legacy"
SMB_HOST_CLK	I,O-OD	Yes	Chapter 29, "SMBus Controller - Host"

Table 7-1. Signal Names and Descriptions (Sheet 2 of 2)

Signal Names	Direction	Shared	Description
SMB_PECI_CLK	I,O-OD	Yes	Chapter 30, "SMBus Controller - Platform Environment Control Interface"
SMB_ME_SMT0_CLK	I,O-OD	Yes	Chapter 36, "System Management"
SMB_ME_SMT1_CLK		Yes	
SMB_ME_SMT2_CLK		Yes	
SMB_IE_SMT0_CLK	I,O-OD	Yes	Chapter 37, "Innovation Engine"
SMB_IE_SMT1_CLK		Yes	
SMB_IE_SMT2_CLK		Yes	
TCK	I	No	Chapter 38, "JTAG and Debug Ports"
DFX_PORT_CLK[1:0]	O	Yes	Chapter 38, "JTAG and Debug Ports"

7.2 Feature List

- SoC requires only two crystals to generate the necessary reference clocks.
- Two Flex Clock output signals that are configurable for platform board use.
- Spread-Spectrum Clocking (SSC) and Non-Spread-Spectrum clocking (NSSC) available.
- Five PCI Express output reference clocks provided and can be used without additional buffer circuits.

7.3 Architectural Overview

The SoC clock architecture is shown in Figure 7-2.

Figure 7-2. SoC Clock Architecture



7.3.1 ISCLK

The external 25-MHz crystal serves as the reference for the internal block of clocks called the Internal System Clock (ISCLK). The reference is routed to a number of internal Phase-Locked Loop (PLL) circuits which are then distributed to the CPU cores, internal circuitry and devices.

For external-interface clocks generated by the SoC, both Spread-Spectrum Clocking (SSC) and Non-SSC (NSSC) are supported.

There are two customer-configurable clock features:

- **Spread Spectrum Controls:** This is expected to be enabled by UEFI IA Firmware via an Integrated Clock Control HECI command to Intel® ME.
- **Flex I/O Clock Speed:** The setting is programmable via a soft strap that is applied during reset. Software can read the resultant settings of the two Flex Clocks' speeds by reading bits [5:0] and [13:8] of the ICLK_DWORD8 register in Host Root Memory Space.

7.3.2 Real-Time Clock

The external 32.768-kHz crystal serves as the reference for the integrated Real Time Clock (RTC). It also provides the clock used by circuitry and devices when the SoC is in Suspend Mode (SUS Mode).

Note: All platform board designs must provide this crystal even if the RTC is not needed or SUS Mode is not implemented.

7.3.3 PMU SUS Clock

The SoC provides the PMU_SUSCLK output signal pin that is based on the 32.768-KHz RTC clock. This signal can be used by the platform board.

7.3.4 Flex Clocks

FLEX_CLK_SE[1:0] are two, single-ended, output signals available to the SoC customer as general-purpose clocks that can be used by the platform board. The customer uses Soft Straps (Chapter 4, "Strapping and Configuration") to enable and select one of the supported frequencies for each Flex Clock. The supported frequencies for each Flex Clock are:

- 25 MHZ
- 33 MHz
- 48 MHz
- 50 MHz

7.3.5 SVID Clock

The available clock frequencies for the SVID Clock:

- 16.7 MHZ
- 20 MHZ
- 25 MHz (default)

7.3.6 SATA Serial GPIO (SGPIO) Clock

The clock frequency for the SATA Serial Clocks is 32 KHz.

7.3.7 EMMC Clock

The SoC EMMC clock is 200 MHz.

7.3.8 DDR Clocks

The available clock frequencies for the DDR4 differential clock output signals are product-SKU dependent. The entire list follows:

- 933 MHz (1866 MHz SDRAMs)
- 1067 MHz (2133 MHz SDRAMs)
- 1200 MHz (2400 MHz SDRAMs)

7.3.9 PCI Express Reference Clocks

The clock frequency for the PCI Express* reference clocks is 100 MHz.

7.3.10 SPI Clock

The available clock frequencies for the SPI Clock:

- 17 MHz (default)
- 30 MHz
- 48 MHz

7.3.11 LPC Clocks

The SoC LPC clock is 24 MHz.

7.3.12 LAN I2C Clocks

The available clock frequencies for each of the LAN I2C Clocks are:

- 100 kHz
- 400 kHz
- 1 MHz

7.3.13 LAN MDC Clock

The available clock frequencies for the LAN MDIO management interface clock are:

- 240 kHz (available only with 1 Gb/s Link Speed)
- 2.4 MHz

7.3.14 LAN NC-SI Clock

NCSI_CLK_IN is designed to be driven by the 50-MHz NC-SI generated by the platform board.

7.3.15 SMBus Clocks

The available clock frequencies for each of the SMBus controllers of the SoC are:

- 100 kHz
- 400 kHz
- 1 MHz

7.3.16 Debug and DFx Clocks

- The SoC TCK clock input signal can be 100 MHz maximum
- The SoC DFX_PORT_CLK[1:0] clocks are 667 MHz.

7.3.17 Clocks Generated During the S5 Sleep State

The internal clocks for the USB 3.0 PHY (integrated in the HSIO circuitry), USB Combo Controller, and LAN Controllers are generated even during the S5 Sleep State.

§ §

8 Interrupts and Events

Global interrupt handling is described in this chapter. The types of interrupts are described as well as the routing and mapping of these interrupts to the integrated I/O Advanced Programmable Interrupt Controller (APIC) and 8259 Programmable Interrupt Controller (PIC).

8.1 PCI Interrupts and Routing

The SoC does not provide external INTA# through INTD# PCI interrupt signal pins. The PCI Express* integrated endpoints and the PCIe* interrupt messages internally produce the equivalent of these four interrupt signals for the device. Since the SoC Interrupt and Timer Sub-System (ITSS) implements only 13 registers, some PCI Interrupt Route (PIR) registers must be shared by multiple devices.

To support sharing a PIR register among multiple interrupt sources, the ITSS tracks the interrupt assertion and deassertion separately for each source. An interrupt asserts with the first assertion message and remains asserted until the last deassertion message.

PCI Device numbers 0-4, 7-8, 13, and 28-29 are currently unused by the SoC. PCI Device 0, Device 4, Device 25 and Devices 28-29 do not issue INT[A-D] interrupt message. See following Table 8-1 for details.

Table 8-1. PIRQ Routing Control Information For INT[A-D] Messages (Sheet 1 of 2)

PCI Device	PCI Interrupt Route Register: PIR[12:0]												
Device 0-4	does not send legacy interrupts												
Device 5 Fn0: RCEC				**3**									
Device 6 Fn0: VRP2 (for Intel® QAT)					**4**								
Device 7 Device 8	are unused												
Device 9 Fn0: PCIe RP[0]								**7**					
Device 10 Fn0: PCIe RP[1]								**7**					
Device 11 Fn0: PCIe RP[2]								**7**					
Device 12 Fn0: PCIe RP[3]								**7**					
Device 13	is unused												
Device 14 Fn0: PCIe RP[4]									**8**				
Device 15 Fn0: PCIe RP[5]									**8**				
Device 16 Fn0: PCIe RP[6]									**8**				
Device 17 Fn0: PCIe RP[7]									**8**				

Table 8-1. PIRQ Routing Control Information For INT[A-D] Messages (Sheet 2 of 2)

PCI Device	PCI Interrupt Route Register: PIR[12:0]												
Device 18 Fn0: SMBus - Host											**10**		
Device 19 Fn0: SATA0							**6**						
Device 20 Fn0: SATA1												**11**	
Device 21 Fn0: USB Combo										**9**			
Device 22 Fn0: VRP0 (for LAN Ctrl0)		**1**											
Device 23 Fn0: VRP1 (for LAN Ctrl1)			**2**										
Device 24 Fn0: ME.HECI1 Fn1: ME.HECI2 Fn2: ME.PTIO-IDER Fn3: ME.PTIO-KT Fn4: ME.HECI3						**5**							
Device 25	does not send legacy interrupts												
Device 26 Fn0: HSUART0 Fn1: HSUART1 Fn2: HSUART2											**10**		
Device 27 Fn0: IE.HECI1 Fn1: IE.HECI2 Fn2: IE.PTIO-IDER Fn3: IE.PTIO-KT Fn4: IE.HECI3													**12**
Device 28 Fn0: eMMC											**10**		
Device 29	are unused												
Device 30													
Device 31 Fn0: LPC Fn1: P2SB Fn4: SMBus - Legacy Fn7: Intel® Trace Hub	**0**												

8.1.1 Interrupt Pin Route Overview

There are 13, 16-bit PCI interrupt routing registers. These 13 registers, named PCI Interrupt Route (PIR) 0-12, are located in memory space and sideband port PCI Interrupt Route 0 (PIR0)—Offset 3140h through PCI Interrupt Route 12 (PIR12)—Offset 3158h. Each 16-bit register has four 3-bit fields:

- Interrupt A Pin Route (IAR): INTA# mapping to one of PIRQA# through PIRQH# (0h through 7h)
- Interrupt B Pin Route (IBR): INTB# mapping to one of PIRQA# through PIRQH# (0h through 7h)
- Interrupt C Pin Route (ICR): INTC# mapping to one of PIRQA# through PIRQH# (0h through 7h)
- Interrupt D Pin Route (IDR): INTD# mapping to one of PIRQA# through PIRQH# (0h through 7h)

The field values 8h through Fh are invalid.

Note: Each of the eight PIRQx# can represent the interrupt of more than one device and up to four for each device.

PIRQA# through PIRQH# are enabled for routing to 8259 and steered to IRQ0-15; similar steering is done for IOxAPIC to IRQ16-23. Information about programming the 8259 Program Interrupt Controller (PIC) and I/O APIC Controller in Chapter 21, "PIC and I/O APIC Controllers".

The PIRQx is routed to the 8259 PIC mode provided that PIRQx Routing Control Register (PxRC) bit 7 Interrupt Routing Enable (REN) is programmed to 0. When REN is programmed as 1, the particular PIRQx is routed to the APIC mode.

Figure 8-1. PIRQ Routing Control Overview



Note: PIRQx#s are active-low interrupt sources. They are internally inverted before being sent to the PIC. Therefore, the interrupt level reference to the signals at the internal interface of the 8259's, the term "high" indicates "active".

8.1.2 PIRQx Register Decode Table

There are eight, 8-bit routing control registers called PIRQx Routing Control (PxRC), one for each PIRQA through PIRQH. Each of the eight interrupts are routed to one of 11 IRQ inputs of the integrated 8259 PIC according to PxRC bit 3:0 IRQ Routing (IR) field.

PIRQx Routing Control Register (PxRC) bit 7 Interrupt Routing Enable (REN) must be set to 0, the corresponding PIRQ is routed to the legacy 8259 mode. Otherwise, the PIRQ is routed to I/OxAPIC mode.

Table 8-2. PIRQA through PIRQH Routing Register IRQ Decode

PIRQx Register, IR field 3:0	PIRQx Routing to 8259 PIC
0000	Reserved
0001	Reserved
0010	Reserved
0011	IRQ3 of the 8259 PIC
0100	IRQ4 of the 8259 PIC
0101	IRQ5 of the 8259 PIC
0110	IRQ6 of the 8259 PIC
0111	IRQ7 of the 8259 PIC
1000	Reserved
1001	IRQ9 of the 8259 PIC
1010	IRQ10 of the 8259 PIC
1011	IRQ11 of the 8259 PIC
1100	IRQ12 of the 8259 PIC
1101	Reserved
1110	IRQ14 of the 8259 PIC
1111	IRQ15 of the 8259 PIC

8.1.3 Edge- and Level-Triggered Mode

There are two edge/level triggered Control Register ELCR1 (Master) and ELCR2 (Slave) to control edge and level triggered mode selection per interrupt input.

If an ELCR bit is “0”, an interrupt request will be recognized by a low to high transition on the corresponding IRQ input. The IRQ input can remain high without generating another interrupt. If an ELCR bit is “1”, an interrupt request will be recognized by a high level on the corresponding IRQ input and there is no need for an edge detection. The interrupt request must be removed before the End of Interrupt (EOI) command is issued to prevent a second interrupt from occurring.

In both the edge and level triggered modes, the IRQ interrupt (called a spurious interrupt) must remain active until after the falling edge of the first internal INTA#. If the IRQ input goes inactive before this time, a default IRQ7 vector will be returned.

PIRQA# through PIRQH# are defined as level-sensitive interrupts. When routed to a specified IRQ line, the software must change the corresponding ELCR1 or ELCR2 register of the 8259 to a level-sensitive mode.

8.2 Non-Maskable Interrupt (NMI)

NMI is generated internally by serious system events, memory parity errors, some System Errors (SERR), and PCI Express fatal errors.

The NMI is reset by the software by setting the corresponding NMI source enable/disable bit in the NMI Status and Control (NMI_STS_CNT) register.

The 8-bit NMI_STS_CNT register is located in the I/O space at 61h. For the individual GPIO NMI status, enable and routing bit definitions, please see Chapter 26, "Customer General-Purpose I/O (GPIO)".

The NMI is broadcast to all cores in the SoC. Sleeping cores are first awakened. NMI Enable (NMI_EN) register is located in the I/O space at 70h.

The SoC provides interrupt mapping to generate the NMI for various SoC and system events. There is an NMI Control Register (NMI) to indicate current NMI status if any source is asserted. The register NMI is located as a Sideband register accessible in Host Memory Space at offset D0_3330h from the SBREG_BAR base address.

Note: ITSS may escalate other interrupts to NMI. ITSS also may demote NMI to SMI.

8.3 System Management Interrupt (SMI)

The SMI indicates any of several system-level conditions. Examples are:

- Thermal-sensor events
- Throttling activation
- System management RAM access
- Chassis open
- System power button pressed
- System Management Bus (SMBus) events
- Power Management Events (PME)
- PCI Express Hot-Plug* events
- Real Time Clock (RTC) alarm activation
- Various system-state-related activities

An SMI causes the system to enter System Management Mode (SMM). SMM is an operating mode in which all normal execution, including the operating system, is suspended, and special, separate software, usually firmware or a hardware-assisted debugger, is executed in high-privilege mode. The SMI is broadcast to all cores in the SoC. Sleeping cores are first awakened.

SMI Enable register is located in I/O space at 0x30h to enable SMI from different configurable source; SMI Status register is located in I/O space at 0x34h to show SMI status from different configurable source. For the individual GPIO SMI status, enable and routing bit definitions, please see Chapter 26, "Customer General-Purpose I/O (GPIO)".

8.4 System Control Interrupt (SCI)

SCI is a special type of hardware power-management interrupt that is handled directly by the OS, and is not handled by a device driver. It is closely tied to the ACPI model. The operating system uses the SCI interrupt to process ACPI events signaled by GPEs, whether the system is asleep or awake when the event occurs. If the system is in an S0 state, SCI can be caused; if the system is in the S5 state, SCI event will also wake the system.

If not using the I/O APIC for the SCI, the SCI must be routed to IRQ9-IRQ11 of the 8259 PIC. When routed to the 8259 PIC, the SCI is not sharable with the Serial Interrupt (SERIRQ) for that PIC input, but it is shareable with the PIRQA through PIRQH interrupts.

If using an I/O APIC, the SCI is mapped to the I/O APIC interrupt or to an SMI. Mapping SCI events to SMI can be used when a legacy OS is in use. The SCI Enable (SCI_EN) bit of the Power Management 1 Control (PM1_CNT) register controls whether the event is routed as an SCI or an SMI. The PM1_CNT register is located in the I/O space at PCI_Config_ABASE offset 4h.

The SCI routing to the I/O APIC is controlled by the 3-bit SCI IRQ Select (SCIS) field of the ACPI Control (ACTL) register located in the memory space at Bus 0, Device 31, Function 2 offset address 0x44h.

Also, if using the I/O APIC for SCI, the SCI can be mapped to IRQ20-IRQ23 of the I/O APIC, and can be shared with other interrupts. Here the SCI must be programmed for active-low reception. The SCI can also be mapped to IRQ9, IRQ10, of IRQ11 where it must be programmed for active-high reception.

Table 8-3. Routing of SCI to the I/O APIC

ACTL.SCIS	SCI IRQ Select in 8259	SCI IRQ Select in I/O APIC
000	IRQ9	IRQ9
001	IRQ10	IRQ10
010	IRQ11	IRQ11
011		Reserved
100		IRQ20
101		IRQ21
110		IRQ22
111		IRQ23

Note: Power Management Controller (PMC) may escalate SCI to SMI; otherwise SCI is delivered to ITSS as IRQx for handling.

8.5 GPIO and PMC General Purpose Event (GPE)

Some of the Customer GPIOs can be configured as SoC input-pin signals that can generate an ACPI General Purpose Event (GPE). The SoC Power Management Controller (PMC) can also generate ACPI GPE status. Each SoC GPE status can be enabled to generate a System Control Interrupt (SCI) or a System Management Interrupt (SMI). The GPE register model is shown in Figure 8-2. Notice that the Enable bit does not prevent the Status bit from setting when the event occurs.

Figure 8-2. General Purpose Event (GPE) Register Model



The GPIO controller has seven Dwords of GPE status and enable bits of which two Dwords originate from the GPIO North Community and five Dwords from the GPIO South Community.

Even though there are seven Dwords of GPIO GPE Status and seven Dwords of GPIO GPE Enable groups shown in Table 8-4, only three groups are exposed by the PMC. So BIOS must choose which three groups from the seven to use and make only these three GPE groups visible to software. These three GPIO groups are mapped to 96 sets of status/enable GPE0 register bits grouped as GPE0_DW0, GPE0_DW1 and GPE0_DW2.

The GPIO GPE Status and Enable groups are marked with group number in silicon. GPIO Miscellaneous Configuration Register (MISCCFG) located at

SBREG_BAR offset 0xC50010h and 0xC20010h bit 8-19 shows the default value is group 0, 1, and 2 mapping to GPE0_DW0, GPE0_DW1 and GPE0_DW2. By programming MISCCFG bit 8-19, different group can be assigned to GPE0_DW0, GPE0_DW1 and GPE0_DW2.

Table 8-4. GPE0_DW Group Mapping

0	GPI_GPE_STS_NORTH_ALL_0	0	GPI_GPE_EN_NORTH_ALL_0
1	GPI_GPE_STS_NORTH_ALL_1	1	GPI_GPE_EN_NORTH_ALL_1
2	GPI_GPE_STS_SOUTH_DFX_0	2	GPI_GPE_EN_SOUTH_DFX_0
3	GPI_GPE_STS_SOUTH_GROUP0_0	3	GPI_GPE_EN_SOUTH_GROUP0_0
4	GPI_GPE_STS_SOUTH_GROUP0_1	4	GPI_GPE_EN_SOUTH_GROUP0_1
5	GPI_GPE_STS_SOUTH_GROUP1_0	5	GPI_GPE_EN_SOUTH_GROUP1_0
6	GPI_GPE_STS_SOUTH_GROUP1_1	6	GPI_GPE_EN_SOUTH_GROUP1_1
7	Reserved	7	Reserved

GPE Group Name	Three GPIO GPE Status Group and Three GPIO Enable Group Mapped to GPE Group		
GPE0_DW0	0	GPI_GPE_STS_NORTH_ALL_0	GPE_GPE_EN_NORTH_ALL_0
GPE0_DW1	1	GPI_GPE_STS_SOUTH_ALL_1	GPI_GPE_EN_SOUTH_ALL_1
GPE0_DW2	2	GPI_GPE_STS_SOUTH_DFX_0	GPI_GPE_EN_SOUTH_DFX_0

The SoC Power Management Controller (PMC) has its own set of GPE0 status/enable Dwords (GPE0_DW3). See Chapter 16, "Power Management Controller (PMC)".

The SoC PMC is a proxy for the GPIO GPE0 Enable and Status registers. When accessed from Host I/O Space, software writes/reads all of the GPE0 registers directly to/from the PMC. See Table 8-5 on page 342. The GPE0 registers are described in Chapter 58, "Power Management Controller - B0, D31, F2".

When applicable the SoC PMC forwards these writes/reads to GPIO controller based on the mapping path from PMC to GPIO. The GPIO mapping path is configured by the SoC in the two GPIO Sideband registers, offset 10h of Sideband Ports C2h and C5h. These Sideband Ports are accessible in Host Memory Space using SBREG_BAR.

Table 8-5. Access to the ACPI General Purpose Event Registers

Host I/O Space PCU B0:D31:F2 ABASE+Offset (hex)	ACPI General Purpose Event 0 (GPE0)		Customer GPIO Group
80	Status [31:0]	GPE0_DW0	GPI_GPE_STS_NORTH_ALL_0
90	Enable [31:0]		GPE_GPE_EN_NORTH_ALL_0
84	Status [63:32]	GPE0_DW1	GPI_GPE_STS_NORTH_ALL_1
94	Enable [63:32]		GPI_GPE_EN_NORTH_ALL_1
88	Status [95:64]	GPE0_DW2	GPI_GPE_STS_SOUTH_DFX_0
98	Enable [95:64]		GPI_GPE_EN_SOUTH_DFX_0
8C	Status [127:96]	GPE0_DW3	Reserved
9C	Enable [127:96]		

The programming steps to map the GPIOs to the GPE0 DWords are as follows:

- Program GPIO Miscellaneous Configuration Register (MISCCFG) located at SBREG_BAR offset 0xC50010h and 0xC20010h bit 8-19 to assign a specific GPIO Group to the ACPI GPE0.
  - Program a specific GPIO Group to GPE0[31:0] as GPE0_DW0
  - Program a specific GPIO Group to GPE0[63:32] as GPE0_DW1
  - Program a specific GPIO Group to GPE0[95:64] as GPE0_DW2
- Program PMC GPIO Configuration Register (GPIO_CFG) at PCI_CFG_PWRMBASE offset 120h to assign a specific GPIO register to the ACPI GPE0.
  - Program a specific GPIO Group to GPE0[31:0] as GPE0_DW0
  - Program a specific GPIO Group to GPE0[63:32] as GPE0_DW1
  - Program a specific GPIO Group to GPE0[95:64] as GPE0_DW2
- Enable 96 GPE available to PMC by writing to PMC. PMC forwards the writes to the GPIO based on the mapping in first step.
  - Program GPE0_EN_31_0 at I/O space 0x90h
  - Program GPE0_EN_63_32 at I/O space 0x94h
  - Program GPE0_EN_95_64 at I/O space 0x98h
- Check GPE0 status by reading from PMC. PMC forwards the reads to the GPIO based on mapping in first step.
  - Read GPE0_STS_31_0 at I/O space 0x80h
  - Read GPE0_STS_63_32 at I/O space 0x84h
  - Read GPE0_STS_95-64 at I/O space 0x88h

For individual GPIO GPE event enable and status detail, please refer to Chapter 26, "Customer General-Purpose I/O (GPIO)".

8.6 Message Signaled Interrupt (MSI and MSI-X)

Message Signaled Interrupt (MSI) is an optional feature that enables a device function to request service by using PCI Dword memory write transaction. MSI-X defines a separate optional extension to the basic MSI functionality. During device configuration, each capable PCI function is allocated one or more vectors and the memory-mapped location to write the interrupt messages. Compared to MSI, MSI-X supports a larger number of vectors function, the ability for the OS to program independent address and data values for each vector. Each function in the PCIe Endpoint (EP) supports the MSI capability. MSI-X is supported only for the physical function.

Once an MSI has been generated using MSI-X, its characteristics are similar to an MSI what was generated using an MSI capability record. However, MSI-X supports per-vector masking that is optional for MSI. MSI-X also supports a Function Mask bit. When MSI-X enabled, EP generates an interrupt using a PCIe posted memory write transaction. The address and data of the transaction are determined by the system and programmed in the PCI MSI-X table entry.

8.7 I/O APIC Input Mapping

The SoC has an integrated I/O APIC which supports 0-119 APIC interrupts. Each interrupt has its own unique vector assigned by the software. The interrupt vectors are mapped as shown in Table 8-6.

Table 8-6. I/O APIC Input Mapping (Sheet 1 of 2)

I/O APIC Input	Interrupts Routed to This I/O APIC Input	Note
IRQ0	Cascaded from Master 8259	
IRQ1	Option for SERIRQ (1) or other configurable source including internal ACPI devices, GPIO	5, 6
IRQ2	8254 Counter 0, HPET Timer 0	1, 2, 3
IRQ3	Option for SERIRQ (3) or other configurable source including internal ACPI devices, GPIO	5, 6
IRQ4	Option for SERIRQ (4) or other configurable source including internal ACPI devices, GPIO	5, 6
IRQ5	Option for SERIRQ (5) or other configurable source including internal ACPI devices, GPIO	5, 6
IRQ6	Option for SERIRQ (6) or other configurable source including internal ACPI devices, GPIO	5, 6
IRQ7	Option for SERIRQ (7) or other configurable source including internal ACPI devices, GPIO	5, 6
IRQ8	HPET Timer 1 (Legacy mode if GEN_CFG.LEG_RT_CNF is set), RTC (if GEN_CFG.LEG_RT_CNF is not set)	1, 2, 3
IRQ9	Option for SERIRQ (9) or other configurable source including internal ACPI devices, SCI, GPIO	5, 6
IRQ10	Option for SERIRQ (10) or other configurable source including internal ACPI device, SCI, GPIO	5, 6
IRQ11	Option for SERIRQ (11) or other configurable source including internal ACPI devices, SCI, GPIO or HPET Timer 2	4
IRQ12	Option for SERIRQ (12) or other configurable source including internal ACPI devices and GPIO or HPET Timer 3	5, 6
IRQ13	Option for SERIRQ (13) or other configurable source including internal ACPI devices and GPIO	5, 6
IRQ14	Option for SERIRQ (14) or other configurable source including internal ACPI devices and GPIO	5, 6

Table 8-6. I/O APIC Input Mapping (Sheet 2 of 2)

I/O APIC Input	Interrupts Routed to This I/O APIC Input	Note
IRQ15	Option for SERIRQ (15) or other configurable source including internal ACPI devices and GPIO	5, 6
IRQ16	PIRQA, or other configurable source including internal ACPI devices and GPIO	5
IRQ17	PIRQB, or other configurable source including internal ACPI devices and GPIO	5
IRQ18	PIRQC, or other configurable source including internal ACPI devices and GPIO	5
IRQ19	PIRQD, or other configurable source including internal ACPI devices and GPIO	5
IRQ20	PIRQE, or other configurable source including internal ACPI device, GPIO, SCI, and HPET	5
IRQ21	PIRQF, or other configurable source including internal ACPI devices, GPIO, SCI, and HPET	5
IRQ22	PIRQG, or other configurable source including internal ACPI devices, GPIO, SCI, and HPET	5
IRQ23	PIRQH, or other configurable source including internal ACPI devices and SCI, or GPIO	5
IRQ24:IRQ 118	Other configurable source including internal ACPI devices and GPIO	5
IRQ119	GPIO	5

Notes:
1. General Configuration Register (GEN_CFG) located at the memory space address FED0_0010h has bit 1 as is the Legacy Rout Enable (LEG_RT_CNF).
2. When LEG_RT_CNF is set, the HPET Timer 0 Config and Capabilities (TMR0_CNF_CAP) register and Timer 1 Configuration and Capabilities (TMR1_CNF_CAP) register and TIMER1_INT_ROUT_CNF bits have no impact for timers 0 and 1. TIMER0_CNF_CAP and TIMER1_CNF_CAP are located at the memory-space addresses FED0_0100h and FED0_0120h, respectively.
3. When LEG_RT_CNF is cleared, each of the three HPET timers has its own routing control. The interrupts can be routed to various interrupts in the I/O APIC. See detail in TMRx_CNF_CAP registers.
4. HPET Timer 2 is routed to the APIC as per the routing in the HPET T2C register located at the memory-space addresses FED0_0140h.
5. When programming the polarity of internal interrupt sources on the APIC, interrupts 0 through 15 receives active -high internal interrupt sources; interrupt 16 through 23 receive active-low internal interrupt sources; interrupts 24 through 119 receive active -high internal interrupt sources.
6. SERIRQ is MUXed with GPIO [11] for assertion by external devices. Interrupt SERIRQ is not exposed if the signal is configured as GPIO.

The I/O APIC has a Redirection Table (RT) with an entry for each interrupt source. Each RT entry is individually programmed for trigger mode (edge or level), vector number, and destination processor(s). The interrupt is reported to the appropriate local APIC(s).

For more information about the I/O APIC, see Chapter 21, "PIC and I/O APIC Controllers."

8.8 8259 PIC Input Mapping

The interrupts that can be routed to the input of the integrated 8259 PIC are shown in Table 8-7. The 8259 PIC registers are described in Chapter 21, "PIC and I/O APIC Controllers."

Table 8-7. 8259 PIC Input Mapping

I/O PIC Input	Master or Slave 8259 PIC Input	Interrupts Routed to This PIC Input	Note
IRQ0	Master IRQ0	HPET Timer 0 (Legacy mode if GGEN_CFG.LEG_RT_CNF is set) 8254 Timer 0 (if GGEN_CFG.LEG_RT_CNF is not set)	1
IRQ1	Master IRQ1	Option for SERIRQ (1) or other configurable source including SMB/eMMC	1, 6
IRQ2	Master IRQ2	Cascade from Slave 8259	1, 2
IRQ3	Master IRQ3	Option for SERIRQ (3) or other configurable source including PIRQx and internal ACPI devices	1, 3, 4, 6
IRQ4	Master IRQ4	Option for SERIRQ (4) or other configurable source including PIRQx and internal ACPI devices	1, 3, 4, 6
IRQ5	Master IRQ5	Option for SERIRQ (5) or other configurable source including PIRQx and internal ACPI devices	1, 3, 4, 6
IRQ6	Master IRQ6	Option for SERIRQ (6) or other configurable source including PIRQx and internal ACPI devices	1, 3, 4, 6
IRQ7	Master IRQ7	Option for SERIRQ (7) or other configurable source including PIRQx and internal ACPI devices	1, 3, 4, 6
IRQ8	Slave IRQ0	HPET Timer 1 (Legacy mode if GEN_CFG.LEG_RT_CNF is set) RTC (if GEN_CFG.LEG_RT_CNF is not set)	1
IRQ9	Slave IRQ1	Option for SERIRQ (9) or other configurable source including PIRQx and internal ACPI devices, SCI	1, 3, 4, 6
IRQ10	Slave IRQ2	Option for SERIRQ (10) or other configurable source including PIRQx and internal ACPI device, SCI	1, 3, 4, 5
IRQ11	Slave IRQ3	Option for SERIRQ (11) or other configurable source including PIRQx and internal ACPI devices, SCI, or HPET Timer 2	1, 3, 4, 5, 6
IRQ12	Slave IRQ4	Option for SERIRQ (12) or other configurable source including PIRQx and internal ACPI devices, or HPET Timer 3	1, 3, 4, 6
IRQ13	Slave IRQ5	Option for SERIRQ (13) or other configurable source including internal ACPI devices	1, 6
IRQ14	Slave IRQ6	Option for SERIRQ (14) or other configurable source including PIRQx, GPIO and internal ACPI devices	1, 3, 4, 6
IRQ15	Slave IRQ7	Option for SERIRQ (15) or other configurable source including PIRQx, GPIO and internal ACPI devices	1, 3, 4, 6

Notes:
1. Interrupts can individually be programmed to be edge or level, except for IRQ0, IRQ1, IRQ2, IRQ8, which are always default to edge.
2. The slave 8259 controller is cascaded onto the master 8259 controller through the master controller interrupt input IRQ2.
3. If an interrupt is used for PCI IRQA - IRQH, SCI, it should not be used for ISA-style interrupts (vis SERIRQ).
4. PCI interrupts are mapped to IRQ3, 4, 5, 6, 7, 9, 10, 11, 12, 14, or 15. It can be programmed by PIRQx Routing Control Register at 0xD0003100h -3107h.
5. If IRQ11/IRQ12 used for HPET#2/HPET#3, software should ensure IRQ11 is not shared with any other devices to guarantee the proper operation of HPET#2/HPET#3. The hardware does not prevent sharing of IRQ11/IRQ12.
6. SERIRQ is MUXed with GPIO [11] for assertion by external devices. Interrupt SERIRQ is not exposed if the signal is configured as GPIO.

8.9 Device Interrupt-Generating Capabilities

Integrated devices that generate interrupts are shown in Table 8-8.
Interrupt-generating details of each is located in its individual functional chapter.

Table 8-8. Device Interrupt / Event Sources

Agent	IRQ to ITSS	INTx to ITSS	MSI to CPU	NMI to ITSS	SCI to PMC
ME.HECI[1-3] IE.HECI[1-3]	-	INT[A-D]	YES	YES, from HECI1 only	YES
ME PTIO KT and IDER IE PTIO KT and IDER	-	INT[A-D]	YES	-	-
eMMC	IRQ[1-31]	-	-	-	YES
GPIO	YES	-	-	YES	YES
HSUART		INT[A-D]	YES	-	-
RCEC		INT[A-D]	YES	-	-
GLREG	-	-	-	YES	YES
IOMMU	-	-	YES	-	-
HPET in ITSS	IRQ8	-	-	-	-
ITSS	YES	-	-	YES	YES
LAN	-	INT[A-D]	YES	-	-
LPC	IRQ[0-15]	INT[A-D]	-	YES	YES
Intel® QAT	-	INT[A]	YES	-	-
Intel® Trace Hub	-	INT[A-D]	YES	-	-
PCIe Root Port	-	INT[A-D]	YES	-	YES
PMC	YES	-	-	-	YES
RTC	IRQ8	-	-	-	YES
SATA	-	INT[A-D]	YES	-	-
SMBus Host	-	INT[A]	YES	-	-
SMBus Legacy	NO	INT[A-D]	-	NO	YES
SPI	-	-	-	-	YES
VRP[0-2]	-	INT[A-D]	YES	-	-
USB Combo	-	INT[A]	YES	-	-

§ §

9 Memory Controller

9.1 Introduction

The Memory Controller is a dual channel DDR4 Memory Controller. The SoC supports a 40 or a 72 bit wide DDR4 interface per channel, 32 or 64 bits of data and 4 or 8 bits of ECC, and it does support both ECC and non-ECC DIMMs.

Figure 9-1. What is Covered in This Chapter



Table 9-1. References

Reference	Revision	Date	Document Title
JESD79-4	-	July 2012	JEDEC DDR4 SDRAM Specification

9.2 Signal Descriptions

The signal descriptions are shown in Table 8-3. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 511. The Direction/Type column of Table 8-3 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.
  Differential = Differential signal pair. Two pins: Positive; Negative.

Note: The SoC memory signal pins have SoC-internal termination designed to conform to the DDR4 (JESD79-4) standard. The DDR0_ALERT_N_PAR_ERR_N and DDR1_ALERT_N_PAR_ERR_N SoC input pins do not have any SoC-internal termination. Here the signal termination for each of these signals must be provided by the board design.

Table 9-2. Signal Names and Descriptions (Sheet 1 of 5)

Signal Name	Direction	Shared	Description
Memory Channel 0			
DDR0_DQ[63:0]	I,O	No	**Data Lines:** Bi-directional 64-bit data bus, driven on writes, received on reads. ***Note:*** In 32-bit mode, the lower 32 bits must be used.
DDR0_ECC[7:0]	I,O	No	**ECC Data Lines:** Bi-directional ECC data extending the data bus, driven on writes, received on reads. ***Notes:*** 1. If ECC is used 32 and 64 bit data width requires 8 bits of ECC. 2. The ECC SDRAM device must be of the same type and width as the SDRAM devices used for the data bits.
DDR0_DQS_DN[17:0] DDR0_DQS_DP[17:0]	I,O, Differential	No	**Data Strobes:** During writes, driven by Cell Delay Variation (CDV) offset so as to be centered in the data phase. During reads, driven by memory devices edge aligned with data. The following list matches the data strobe in the data group. DQS_DP/DN[7]: DQ[63:56] DQS_DP/DN[6]: DQ[55:48] DQS_DP/DN[5]: DQ[47:40] DQS_DP/DN[4]: DQ[39:32] DQS_DP/DN[3]: DQ[31:24] DQS_DP/DN[2]: DQ[23:16] DQS_DP/DN[1]: DQ[15:8] DQS_DP/DN[0]: DQ[7:0] If ECC is supported then DQS_DP/DN[8]: ECC[7:0]. For x4 devices, strobe is divided to be high nibble strobe and low nibble strobe. ***Note:*** In 32-bit mode, the lower DQ must be used.
DDR0_MA[13:0]	O	No	**Multiplexed Address:** Provides multiplexed row and column address to memory. Provides the row address for Active commands and the column address and Auto Precharge bit for Read/Write commands to select one location out of the memory array in the respective bank. A10 is sampled during a Precharge command to determine whether the Precharge applies to one bank (A10 LOW) or all banks (A10 HIGH). If only one bank is to be precharged, the bank is selected by BA0 - BA2. The address outputs also provide the op-code during MRS or EMRS commands.

Table 9-2. Signal Names and Descriptions (Sheet 2 of 5)

Signal Name	Direction	Shared	Description
DDR0_MA14_WE_N	O	No	**DDR0_WE_N:** When DDR0_ACT_N_MA[15] signal is high, otherwise DDR0_MA[14].
DDR0_MA15_CAS_N	O	No	**DDR0_CAS_N:** When DDR0_ACT_N_MA[15] signal is high, otherwise DDR0_MA[15].
DDR0_MA16_RAS_N	O	No	**DDR0_RAS_N:** When DDR0_ACT_N_MA[15] signal is high, otherwise DDR0_MA[16].
DDR0_MA17	O	No	**Address Lines:** Provide the row address for ACTIVATE commands and column address for Read/Write commands. This address line is only defined for the x4 configuration.
DDR0_ACT_N_MA[15]	O	No	**Activation Command ACT_N:** Defines the Activation command being entered along with CS_N.
DDR0_CLK_DN[3:0] DDR0_CLK_DP[3:0]	O, Differential	No	**Differential DDR Clock:** All address and control input signals are sampled on the crossing of the positive edge of CK_P and negative edge of CK_N. Output (read) data is referenced to the crossings of CK_P and CK_N (both directions of crossing).
Memory Channel 0 (continued)			
DDR0_CKE[3:0]	O	No	**Clock Enable:** (active high) CKE is used for power control of the DRAM devices. CKE HIGH activates and CKE LOW deactivates DRAM device internal clock signals and device input buffers and output drivers. These are output signals from the SoC.
DDR0_CS_N[3:0]	O	No	**Chip Select:** (active low) These signals determine whether a command is valid in a given cycle for the devices connected to it. All commands are masked when CS_N is registered HIGH. CS_N provides for external rank selection on systems with multiple ranks. CS_N is considered part of the command code.
DDR0_C0	O	No	**Chip ID:** Not supported by the SoC. Board designs shall treat this pin as a No-Connect (NC).
DDR0_BA[1:0]	O	No	**Bank Address:** Defines the bank which is the destination for the current Activate, read, write or precharge command.
DDR0_BG0_BA[2]	O	No	Bank group address.
DDR0_BG1_MA[14]	O	No	Bank group address.
DDR0_ODT[3:0]	O	No	**On-Die Termination Enable:** (active high) ODT (registered HIGH) enables termination resistance internal to the DDR device SDRAM. When the ODT feature is enabled, it is dynamically enabled for the receiver of the data. The SoC does this internally for read data returning from the DRAM devices. For write data to the DRAM devices, the DDR0_ODT[] pins are asserted to enable ODT w/in the DRAM devices themselves. Because ODT consumes power, when the feature is enabled, it is controlled dynamically by the SoC. ODT impacts the DQ and DQS.
DDR0_PAR	O	No	Command and address parity
DDR0_ALERT_N_PAR_ERR_N	I	No	**Alert:** Command and address parity error flag or write data CRC error flag (Note the SoC does not support CRC). There is no SoC-internal termination to this input signal. This SoC input is the receiver of the active-low DDR4 "ALERT_n" signal bus which is possibly driven by more than one system source. Board-level termination is required.

Table 9-2. Signal Names and Descriptions (Sheet 3 of 5)

Signal Name	Direction	Shared	Description
Memory Channel 1			
DDR1_DQ[63:0]	I,O	No	**Data Lines:** Bi-directional 64-bit data bus, driven on writes, received on reads. ***Note:*** In 32-bit mode, the lower 32 bits must be used.
DDR1_ECC[7:0]	I,O	No	**ECC Data Lines:** Bi-directional ECC data extending the data bus, driven on writes, received on reads. ***Notes:*** 1. If ECC is used 32 and 64 bit data width requires 8 bits of ECC. 2. The ECC SDRAM device must be of the same type and width as the SDRAM devices used for the data bits.
DDR1_DQS_DP[17:0] DDR1_DQS_DN[17:0]	I,O, Differential	No	**Data Strobes:** During writes, driven by Cell Delay Variation (CDV) offset so as to be centered in the data phase. During reads, driven by memory devices edge aligned with data. The following list matches the data strobe in the data group. DQS_DP/DN[7]: DQ[63:56] DQS_DP/DN[6]: DQ[55:48] DQS_DP/DN[5]: DQ[47:40] DQS_DP/DN[4]: DQ[39:32] DQS_DP/DN[3]: DQ[31:24] DQS_DP/DN[2]: DQ[23:16] DQS_DP/DN[1]: DQ[15:8] DQS_DP/DN[0]: DQ[7:0] If ECC is supported then DQS_DP/DN[8]: ECC[7:0]. DDR4 supports differential strobes only. For x4 devices, strobe is divided to be high nibble strobe and low nibble strobe. ***Note:*** In 32-bit mode, the lower DQ must be used.
DDR1_MA[13:0]	O	No	**Multiplexed Address:** Provides multiplexed row and column address to memory. Provides the row address for Active commands and the column address and Auto Precharge bit for Read/Write commands to select one location out of the memory array in the respective bank. A10 is sampled during a Precharge command to determine whether the Precharge applies to one bank (A10 LOW) or all banks (A10 HIGH). If only one bank is to be precharged, the bank is selected by BA0 - BA2. The address inputs also provide the op-code during MRS or EMRS commands.
DDR1_MA14_WE_N	O	No	**DDR1_WE_N:** When DDR1_ACT_N_MA[15] signal is high, otherwise DDR1_MA[14]
DDR1_MA15_CAS_N	O	No	**DDR1_CAS_N:** When DDR1_ACT_N_MA[15] signal is high, otherwise DDR1_MA[15]
DDR1_MA16_RAS_N	O	No	**DDR1_CAS_N:** When DDR1_ACT_N_MA[15] signal is high, otherwise DDR1_MA[15]
DDR1_MA17	O	No	**Address Lines:** Provide the row address for ACTIVATE commands and column address for Read/Write commands. This address line is only defined for the x4 configuration.
DDR1_ACT_N_MA[15]	O	No	**Activation Command Input:** ACT_N defines the Activation command being entered along with CS_N
DDR1_CLK_DP[3:0] DDR1_CLK_DN[3:0]	O, Differential	No	**Differential DDR Clock:** All address and control input signals are sampled on the crossing of the positive edge of CK_P and negative edge of CK_N. Output (read) data is referenced to the crossings of CK_P and CK_N (both directions of crossing).

Table 9-2. Signal Names and Descriptions (Sheet 4 of 5)

Signal Name	Direction	Shared	Description
DDR1_CKE[3:0]	O	No	**Clock Enable:** (active high) CKE is used for power control of the DRAM devices. CKE HIGH activates and CKE LOW deactivates DRAM device internal clock signals and device input buffers and output drivers. These are output signals from the SoC.

Table 9-2. Signal Names and Descriptions (Sheet 5 of 5)

Signal Name	Direction	Shared	Description
Memory Channel 1 (continued)			
DDR1_CS_N[3:0]	O	No	**Chip Select:** (active low) These signals determine whether a command is valid in a given cycle for the devices connected to it. All commands are masked when CS_N is registered HIGH. CS_N provides for external rank selection on systems with multiple ranks. CS_N is considered part of the command code.
DDR1_C0	O	No	**Chip ID:** Not supported by the SoC. Board designs shall treat this pin as a No-Connect (NC).
DDR1_BA[0:1]	O	No	**Bank Address:** Defines the bank which is the destination for the current Activate, read, write or precharge command.
DDR1_BG0_BA[2]	O	No	Bank group address.
DDR1_BG1_MA[14]	O	No	Bank group address.
DDR1_ODT[3:0]	O	No	**On-Die Termination Enable:** (active high). ODT (registered HIGH) enables termination resistance internal to the DDR device SDRAM. When the ODT feature is enabled, it is dynamically enabled for the receiver of the data. The SoC does this internally for read data returning from the DRAM devices. For write data to the DRAM devices, the DDR1_ODT[] pins are asserted to enable ODT w/in the DRAM devices themselves. Because ODT consumes power, when the feature is enabled, it is controlled dynamically by the SoC. ODT impacts the DQ and DQS. The ODT pin will be ignored by the DDR devices if the EMR(1) is programmed to disable ODT. One pin per rank.
DDR1_PAR	O	No	Command and address parity.
DDR1_ALERT_N_PAR_ERR_N	I	No	**Alert:** Command and address parity error flag or write data CRC error flag (Note the SoC does not support CRC). There is no SoC-internal termination to this input signal. This SoC input is the receiver of the active-low DDR4 "ALERT_n" signal bus which is possibly driven by more than one system source. Board-level termination is required.
Signals Common to Both Memory Channels			
DDR01_DRAMRST_N	O	No	**DRAM Reset:** Active low Reset to the DDR DIMMs of both Memory Controllers.
DDR01_COMP	O	No	The platform board must provide a 1% resistor from this pin to VSS: • 392 Ω for DDR4
ADR_TRIGGER	I,O-OD	Yes	**Asynchronous DRAM Self-Refresh (ADR) Trigger:** Chapter 16, "Power Management Controller (PMC)"
ADR_COMPLETE	I,O	Yes	**Asynchronous DRAM Self-Refresh (ADR) Complete:** Chapter 16, "Power Management Controller (PMC)"

9.3 Feature List

- Up to two 32/40 bit [1] or 64/72 bit wide memory channels. Up to two DIMMs per channel
- Single-rank or dual-rank per DIMM module
- ECC [3] and non-ECC support
- DDR4 Low Voltage version operating at 1.2V
  - 1600, 1866 [2], 2133, and 2400 MT/s
  - x8 and x16 width for unbuffered memory (UDIMM, SO-DIMM & memory down)
  - x4 and x8 width devices for RDIMM
  - 4 Gb, 8 Gb, and 16 Gb technology devices
  - Minimum memory is:
    32 bit [1] wide memory channel: 1GB (4 Gb, 1 rank, x16 width)
    64 bit wide memory channel: 2GB (4 Gb, 1 rank, x16 width)
  - Maximum memory single channel is 128GB (16 Gb, x4n width, 4 ranks, 64 bit)
  - Both memory channels maximum is 256GB (128GB with two 64 bit channels)
- SoC memory population rules:
  - Both channels must be 32 bit [1] or 64 bits wide
  - At least 1 memory channel must be populated and enabled.
    Either channel 0 or channel 1 may be disabled
  - Both channels require either unbuffered memory (UDIMM, SO-DIMM or memory down), or registered memory (RDIMM and/or NVRDIMM). Technology mixing is not supported.
  - Rank mixing is allowed but can result in a speed bin loss.

To calculate the capacity of a DIMM, the type of DRAMs used must be understood. The width of the DRAM should be used to find the number of DRAMs needed to make up the data bus. The capacity per rank can then be calculated by multiplying the number of DRAMs by the size of the DRAM, and further divided by eight to convert bits into bytes. The total DIMM capacity is finally calculated by multiplying the rank capacity and the number of ranks on the DIMM.

Notes:
1. A0 and A1 step silicon only support 64/72-bit wide memory channels.
2. The silicon design supports 1866 MT/s but is not validated on Intel platforms. Customers are responsible for validation.
3. The ECC SDRAM device must be of the say type and width as the SDRAM devices used for the data bits. This limitation is driven by the DDR4 spec.
   - It is NOT alright to use x16 SDRAM devices for data and a x8 device for ECC.
   - It is NOT alright to use x8 SDRAM devices for data and a x4 device for ECC.
4. Memory based on 16 Gb dual rank technology (including maximum memory configuration of 256GB) is supported by silicon but not validated on Intel platforms.

9.4 Memory Controller Power Management Features

9.4.1 DRAM Running Average Power Limit (RAPL)

DRAM Running Average Power Limiting (RAPL) allows power limiting for the memory connected to the SoC.

DRAM RAPL provides a way to set power limits on your memory power consumption. This will allow the SoC to dynamically limit max average power, to match its expected power budget. DRAM RAPL Domain only includes the memory connected directly to the SoC. Implementing RAPL across multiple SoC must be implemented in a multi-node management RAPL solution. DRAM RAPL provides a way to set short term and longer term averaging windows for power limits for the SoC DRAM Memory.

9.4.2 Dynamic (HW autonomous) Self-refresh DDR4

The Self-Refresh command can be used to retain data in the DDR4 DRAM, even if the rest of the system is powered down. When in the Self-Refresh mode, the DDR4 SDRAM retains data without external clocking.The DDR4 DRAM device has a built-in timer to accommodate Self-Refresh operation. The Self-Refresh-Entry (SRE) Command is defined by having CS_n, RAS_n/A16, CAS_n/A15, and CKE held low with WE_n/A14 and ACT_n high at the rising edge of the clock.

Before issuing the Self-Refresh-Entry command, the DDR4 DRAM must be idle with all bank precharge state with tRP satisfied. 'Idlestate' is defined as all banks are closed (tRP, tDAL, etc. satisfied), no data bursts are in progress, CKE is high, and all timings from previous operations are satisfied (tMRD, tMOD, tRFC, tZQinit, tZQoper, tZQCS, etc.). Deselect command must be registered on last positive clock edge before issuing Self Refresh Entry command. Once the Self Refresh Entry command is registered, Deselect command must also be registered at the next positive clock edge. Once the Self-Refresh Entry command is registered, CKE must be held low to keep the device in Self-Refresh mode. DRAM automatically disables ODT termination and set Hi-Z as termination state regardless of ODT pin and RTT_PARK set when it enters in Self-Refresh mode.

Upon exiting Self-Refresh, DRAM automatically enables ODT termination and set RTT_PARK asynchronously during tXSDLL when RTT_PARK is enabled. During normal operation (DLL on) the DLL is automatically disabled upon entering Self-Refresh and is automatically enabled (including a DLL-Reset) upon exiting Self-Refresh.

When the DDR4 SDRAM has entered Self-Refresh mode, all of the external control signals, except CKE and RESET_n, are "don't care." For proper Self-Refresh operation, all power supply and reference pins (VDD, VDDQ, VSS, VSSQ, VPP, and VRefCA) must be at valid levels. DRAM internal VrefDQ generator circuitry may remain ON or turned OFF depending on DRAM design. If DRAM internal VrefDQ circuitry is turned OFF in self refresh, when DRAM exits from self refresh state, it ensures that VrefDQ generator circuitry is powered up and stable within tXS period. First Write operation or first Write Leveling Activity may not occur earlier than tXS after exit from Self Refresh. The DRAM initiates a minimum of one Refresh command internally within tCKE period once it enters Self-Refresh mode.

The clock is internally disabled during Self-Refresh Operation to save power. The minimum time that the DDR4 SDRAM must remain in Self-Refresh mode is tCKESR. The user may change the external clock frequency or halt the external clock tCKSRE after Self- Refresh entry is registered, however, the clock tCKESR must be restarted and stable before the device can exit Self-Refresh operation.

Note: Package C6 (PC6) only helps to save power when DDR dynamic self-refresh feature is on.

9.4.3 Unsupported Features and Restrictions

- DDR3 and DDR3L DRAM technology is not support on this product.
- Technology to minimize DDR pass-gate charge migration issues.
- DDR4 data bus widths other than 32/40 bits or 64/72 bits are not supported.
- 2-Gb Device Density (or lower).
- Dual Channel: Both channels do not have to be populated identically
  - Same voltage.
  - ECC versus non-ECC DIMMs; DIMMs must all be ECC or non-ECC; no mixing allowed.
  - DIMMs must be all either UDIMMs, RDIMMs or NVRDIMM. No DIMM type mixing is permitted.
  - Frequency – BIOS will set the overall Memory frequency to the lowest frequency that is detected during SPD discovery across both channels and all populated DIMMs.
- Partial Self Refresh is not supported.
- Memory mirroring is not supported.
- Memory lockstep is not supported.
- Memory sparing is not supported.
- Memory Hot-Swap is not supported.
- Suspend to Memory (S3) is not supported.
- Single Device Data Correction (SDDC) is not supported.

Note:

1. SPD setting impacts memory initialization during the system boot up. Please refer to the *SPD Annex L, Serial Presence Detect (SPD) for DDR4 SDRAM Modules* for details.

9.4.4 DDR4 DIMM Types and Population

Registered (RDIMM), unbuffered (UDIMM), or small-outline (SODIMM) ECC modules are supported. ECC RDIMMs and UDIMMs are supported. Single rank ("1R") and dual rank ("2R") DIMMs can be used.

Note: Contact your Intel representative for the Harrisonville Platform Snapshot document which contains the most up to date supported memory information.

9.4.4.1 DIMM Population Requirements

Either channel may be populated or both. There are no DIMM matching requirements between channels. Both channels, however, must run at the same interface frequency. Each channel may run at different DIMM timings (RAS latency, CAS latency, and so forth).

The platform does not support mixing of DIMM types. Sockets are populated with all RDIMMs, all UDIMMs, or all SODIMMs. All DIMMs must be DDR4 DIMMs.

DIMMs with different timing parameters can be installed on different slots within the same channel, but only timings that support the slowest DIMM will be applied, i.e., the faster DIMM in a channel will run at the lower speed.

No mixing of x4 and x8 RDIMMs is allowed within a channel. It is allowed when in different channels. Mixing of single rank (SR) and dual rank (DR) DIMMs is allowed but there may be a speed bin loss.

Each populated channel must be x4 or x8 or x16 only (no width mixing within a channel).

These are summarized in Table 9-3.

Regardless of RAS mode, the requirements for DIMM populating within a System and a channel provided in the System/Channel Level DIMM Population Requirements sections in the Product Design Guide must be met at all times.

Table 9-3. DIMM Configurations, Two DIMM Socket per Channel

Style	1N/2N	DIMM1	DIMM0
RDIMM	1N	empty [1]	SRx4, SRx8, DRx4, DRx8
	1N	SRx4	SRx4
	1N	SRx8	SRx8
	1N	DRx4	DRx4
	1N	DRx8	DRx8
UDIMM	2N	empty	SRx8, DRx8
	2N	SRx8	SRx8
	2N	DRx8	DRx8
SODIMM	2N	empty	SRx8, SRx16, DRx8
	2N	SRx8	SRx8
	2N	SRx16	SRx16
	2N	DRx8	DRx8

Notes:
1. For designs using the T-topology in a two socket configuration with only one DIMM slot being populated it is recommended to populate DIMM0 first, although either DIMM0 or DIMM1 may be populated but DIMM1 only population is not fully validated by Intel. For daisy chain designs customers need to populate the further connector to decrease the risk of reflections that impacts signal integrity.

9.5 Memory Controller RAS Features

9.5.1 Data Scrambler

Data scrambling is a general technique to reduce supply noise and improve signal integrity by XORing data and ECC with a pseudo random sequence. The pseudo random sequence has two important effects relative to power delivery. Across the 72 data/ECC bits of the bus, it drives very close to 50% "1's" and 50% "0's" in every cycle. This eliminates the previous worst case where all bits of the bus would simultaneously drive high or low.

9.5.2 Patrol Scrub

Patrol Scrubbing is a process that allows the SoC to correct correctable memory errors detected on a memory module and send the correction to the requester (the original source). When this item is set to Enabled, the SoC will analyze one cache line every 16K cycles, if there is no delay caused by internal processing. By using this method, roughly 64 GB of memory connected to the SoC will be scrubbed every 24 hours. This option can be enabled or disabled.

Note: The above feature requires ECC to be enabled.

9.5.3 Demand Scrub

Demand Scrubbing is a process that allows the SoC to correct correctable memory errors found on a memory module. When the SoC or I/O issues a demand-read command, and the read data from memory turns out to be a correctable error, the error is corrected and sent to the requester (the original source). Memory is updated as well. This option can be enabled or disabled.

Note: The above feature requires ECC to be enabled.

9.5.4 Asynchronous DRAM Refresh (ADR)

Asynchronous DRAM Refresh is a SoC feature that preserves context data to NVRDIMMs before data loss can occur in the event of an unexpected power loss. Once all inflight data is flushed including CPU cached data, the DRAMs must be placed into a self-refresh state before platform power is lost. Details about ADR are in Section 16.15, "Asynchronous DRAM Refresh (ADR)" on page 547.

§ §

10 Flexible I/O Adapter (FIA) Overview

The High Speed I/O (HSIO) lanes are configured by the SoC customer. The product SKU determines how many lanes of PCI Express* Root Ports, SATA ports, and USB 3.0 ports are available. The arrangement of the available lanes is up to the customer. BIOS, via the Intel® Management Engine (Intel® ME), along with Soft Straps and the bifurcation settings of the PCIe* Root Port clusters, configure the lanes.

Figure 10-1. What is Covered in This Chapter



10.1 Signal Descriptions

The signal descriptions are shown in Table 10-1. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a GPIO signal see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. The Direction/Type column of Table 10-1 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- Differential = Differential signal pair. Two pins: Positive; Negative.

Note: The HSIO transmit and receive differential pairs for each lane have SoC-internal termination designed to conform to the PCIe*, SATA, or USB 3.0 industry specification for which the lane is configured.

Table 10-1. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
HSIO_RX_DP[19:0] HSIO_RX_DN[19:0]	I, Differential	Yes	**High-Speed I/O Lane Read Data** - These 20 sets of differential receivers are configured by the customer as PCI Express Root Ports, SATA Ports, and/or USB 3.0 Ports.
HSIO_TX_DP[19:0] HSIO_TX_DN[19:0]	O, Differential	Yes	**High-Speed I/O Lane Write Data** - These 20 sets of differential drivers are configured by the customer as PCI Express Root Ports, SATA Ports, and/or USB 3.0 Ports.
HSIO_COMPREF_DP HSIO_COMPREF_DN	O, Differential	No	**High-Speed** I/O **Common Lane Compensation Pins** - The platform board must provide a 100 Ω, 1% resistor connected from the DP pin to the DN pin.
HSHV_IRCOMP	I,O	No	**HSHV_IRCOMP** - Special compensation resistor to support 3.3V shared by all of the High-Speed I/O Lane interfaces. The platform board must provide a 100-Ω, 1% resistor connected from this pin to VSS.

10.2 Feature List

- Customer-configurable high-speed lane patterns
- Controlled by BIOS, Soft Straps, Intel® ME, and the PCIe bifurcation settings

10.3 Architectural Overview

The Flexible I/O Adapter (FIA) is the mechanism that enables the customer to configure the High Speed I/O (HSIO) lanes to fit a particular system need.

Three controller types are involved to determine HSIO usage:

- PCI Express Root Ports
- SATA
- USB 3.0

See Figure 10-2, "FIA and HSIO Structure".

The FIA provides a high degree of configuration flexibility without increasing pin count by allowing a single PHY lane to be statically mapped to different controllers. This provides great flexibility to platform board designers as the number of PCIe, SATA and USB 3.0 ports and their mapping to SoC pin-out can be configured differently for different platforms.

The FIA supports shared clock-control logic that allows the integrated controllers to share a single master clock. The FIA also contributes to dynamic PHY power gating by managing the PHY common-lanes power gating, allowing power gating only when all the controllers permit. This further reduces the idle power of the PHY. The PHY data lanes power gating is managed by the respective controllers.

Figure 10-2. FIA and HSIO Structure



Note: The structures for PCIe RP bifurcation control BIFCTL0 = 001 and 010 are not shown here but are valid configurations. Most use cases are satisfied by what is shown in the figure.

10.4 USB 3.0 as a Debug Port

Depending on the product SKU, lanes 19:16 are set to be either SATA or USB 3.0. See Figure 10-2 on page 362. For the debug Intel® Direct Connect Interface (Intel® DCI) to work correctly, the Intel® ME programs the Intel® DCI registers to indicate which lanes are SATA and which are USB 3.0 for the particular SoC product SKU. See Chapter 38, "JTAG and Debug Ports" for Intel® DCI and the SoC JTAG port.

10.5 Lane Configuration

All product SKUs are shipped with all controllers enabled for the PCI Express Root Ports, SATA, and USB 3.0 interfaces. The product SKUs are shown in Section 1.1, "Overview." Each product SKU has a limit to the number of HSIO lanes that a customer can use, but this limitation does not specify which physical lanes can and cannot be used. The customer defines the Soft Strap settings (see Chapter 4, "Strapping and Configuration") to connect the I/O lanes of the PCIe Root Port, SATA and USB 3.0 controllers to individual HSIO lanes. Section 10-2, "FIA and HSIO Structure" shows the relationship of the controllers with the HSIO lane numbers. The Soft Straps must define controller connections to no more than the maximum number of HSIO lanes allowed for the particular product SKU. In addition, the PCI Express lane patterns are determined by the values programmed in the PCIe Bifurcation Control Registers described in Section 10.5.2, "PCI Express Lane Configuration."

If the SoC determines that there are more HSIO lanes connected by Soft Straps than allowed by the product SKU, the SoC will configure the HSIO lanes as only four USB 3.0 lanes. In this case, BIOS is still initiated but the system will have only the four USB 3.0 lanes active at the HSIO pins.

10.5.1 Intel® Management Engine and BIOS Roles in Lane Configuration

FIA lane configuration and management are part of the Intel® Server Platform Services (SPS) firmware.

The specification includes a flow diagram for systems with Intel® SPS firmware where the BIOS and Intel® ME determine the lane-assignment validity and confirm that the assignments are within the SoC product SKU definition. This flow is summarized in Figure 10-3, "Intel® ME-BIOS/UEFI Interactions in a System with Intel® SPS Firmware" and addresses three customer use cases:

- The resulting system has a unique integrated firmware image (IFWI) and product-SKU combination for each of the system's boards. This combination is custom-programmed in the SPI device during board manufacturing. Here the SoC Soft Straps provide the HSIO lane assignments.
- A single IFWI for a particular board design is programmed to the SPI device during board manufacturing. The board is designed to accommodate one of a number of SoC product SKUs. Here the SoC Soft Straps in the single IFWI provide the HSIO lane assignments and, if required, the BIOS/UEFI overrides the initial HSIO lane assignments based on the product SKU used on the board.
- A single IFWI for a particular board design is programmed to the SPI Flash memory at manufacturing similar to above, but the desired HSIO assignments cannot be determined until the board is plugged into the chassis and power applied. Here the BIOS/UEFI determines which system I/O cards/controllers are system-connected to the board and attempts to configure the HSIO lanes.

Figure 10-3. Intel® ME-BIOS/UEFI Interactions in a System with Intel® SPS Firmware



10.5.2 PCI Express Lane Configuration

In addition to lane disabling/enabling, the PCI Express lane patterns are determined by the values programmed in the three-bit Bifurcation Control 0 (BIFCTL0) field of the PCIe Port Bifurcation Control Register (PPBIFCTL_PRIV) registers. There is one physical PPBIFCTL_PRIV register for PCI Express Root Port (RP) Cluster 0 and one for RP Cluster 1. Each of the two 8-lane PCI Express RP Clusters has a PPBIFCTL_PRIV register. Bifurcation of the eight lanes is shown in Table 10-2. The effects of the three unshaded BIFCTL0 decodes are shown in Figure 10-2, "FIA and HSIO Structure." BIFCTL0 = 001 and 010, not shown in the figure, are also valid decodes.

Table 10-2. Bifurcation Control for PCIe RP Clusters 0 and 1

BIFCTL0 [2:0]	Port 0	Port 1	Port 2	Port 3
000	X2	X2	X2	X2
001	X4		X2	X2
010	X2	X2	X4	
011	X4		X4	
100	x8			
101	**Reserved**			
110				
111				

There are two access mechanisms for each of the two PCIe Port Bifurcation Control registers. When accessed as a Sideband Register, it is a Read-Write register where the value in BIFCTL0 can be locked once it is set. It can also be accessed through Configuration Space where it is a Read-Only register. The PCIe Port Bifurcation Control registers is called:

- PPBIFCTL_PRIV when accessed as a Sideband Register
- PPBIFCTL when accessed via Configuration Space

As a Sideband Register, PPBIFCTL_PRIV for PCIe RP Cluster 0 is at Sideband Port B4h offset 10h and at Port B3h offset 10 for RP Cluster 1. These Sideband Registers are accessed in Host Memory-Mapped Space using SBREG_BAR, offsets B4_0010h and B3_0010h respectively.

In Configuration Space, PPBIFCTL is a Device-Specific Register located at offset C0h from B0,D9,F0 for PCIe RP Cluster 0 and is aliased in Configuration Space at F0 for Devices 10, 11, and 12. It represents the lane arrangement of RP0, RP1, RP2, and RP3. PCIe RP Cluster 1 has its PPBIFCTL located at offset C0h in Configuration Space at B0,D14,F0 and is aliased in Configuration Space at F0 for Devices 15, 16, and 17. It represents the lane arrangement of RP4, RP5, RP6, and RP7.

10.5.3 Configuring PCIe Lane to x1 and SATA Ports

The FIA is flexible in its lane assignments and efficient. A PCIe Root Port that results as a x2 from the bifurcation setting, can give up its higher-numbered lane so that the HSIO lane can be configured to a SATA port. Soft Straps settings allow this PCIe x1 Root Port configuration. Figure 10-4 shows an example of this PCIe-SATA arrangement of lanes. The RP Enable and RP Width Soft Strap values shown in the example are for Root Ports 0, 1, 2, and 3 for PCIe Cluster 0 and for Root Ports 4, 5, 6, and Cluster 1.

Figure 10-4. PCIe x1 Lane and SATA Example



10.6 Register Map

Figure 10-5 shows the associated registers from a system software viewpoint.

Figure 10-5. Register Map



10.6.1 PCI Configuration and Capabilities

Table 10-3. Configuration and Capabilities Register Map

Offset in Configuration Space of RP0 through RP7 (hex)	Register Short Name	Description
C0	PPBIFCTL	PCIe Port Bifurcation Control Register

10.6.2 Sideband Registers

Table 10-4. Sideband Registers

Memory-Mapped Base Address Register (BAR)	Offset from BAR (hex)	Register Short Name	Register Long Name
PCI Express Root Port Cluster 0 (RP0, RP1, RP2, RP3)			
SBREG_BAR	B4_0010	PPBIFCTL_PRIV	PCIe Port Bifurcation Control Register
PCI Express Root Port Cluster 1 (RP4, RP5, RP6, RP7)			
SBREG_BAR	B3_0010	PPBIFCTL_PRIV	PCIe Port Bifurcation Control Register

§ §

11 PCI Express Root Ports (RP)

The SoC supports up to 16 PCI Express* lanes that comply with the PCI Express Base Specification Revision 3.0. The maximum data rate is 8.0 GT/s. The 16 lanes can be configured to a maximum of eight, independent PCIe* Root Ports (RP). The eight RPs are grouped in to two clusters, four RPs per cluster:

- Cluster 0 - RP0, RP1, RP2, RP3 are assigned Device Numbers 9, 10, 11, 12 decimal
- Cluster 1 - RP4, RP5, RP6, RP7 are assigned Device Numbers 14, 15, 16, 17

The number of available lanes and Root Ports depend on the product SKU.

Twelve of the 16 PCIe lanes share their SoC signal pins with the integrated SATA0 and SATA1 controllers. Each of the 12 shared lanes must be configured as either PCIe or SATA through Soft Straps and BIOS. See Chapter 10, "Flexible I/O Adapter (FIA) Overview." The Root Ports can be configured to support a diverse set of lane assignments.

Figure 11-1. What is Covered in This Chapter



Table 11-1. References

Reference	Revision	Date	Document Title
PCI Express	3.0	Nov. 10, 2010	*PCI Express Base Specification Revision 3.0*
PCI	3.0	Feb. 3, 2004	PCI Local Bus Specification, Revision 3.0
PCIe CEM	3.0	July 21, 2013	*PCI Express Card Electromechanical Specification, Revision 3.0*
PCI Mini CEM	2.0	April 21, 2012	*PCI Express Mini Card Electromechanical Specification, Revision 2.0*
PCI-PCI Bridge	1.2	June 9, 2003	*PCI-to-PCI Bridge Architecture Specification, Revision 1.2*
PCI Power Management	1.2	March 3, 2004	*PCI Bus Power Management Interface Specification, Revision 1.2*

11.1 Signal Descriptions

The signal descriptions are shown in Table 11-2, "Signal Names and Descriptions." For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names." Also, see Table 39-3, "Signals that Share the Twenty HSIO Lanes." The Direction/Type column of Table 11-2, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.
- Differential = Differential signal pair. Two pins: Positive; Negative.

Table 11-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
PCI Express RP Cluster 0 - SoC Root Ports 0, 1, 2, and 3			
PCIE0_RP0_RP3_TX_DP[7:0] PCIE0_RP0_RP3_TX_DN[7:0]	O, Differential	Yes	**Transmit (Tx):** These differential output signals are internal to the SoC. The actual signal pins are determined by the FIA configuration.
PCIE0_RP0_RP3_RX_DP[7:0] PCIE0_RP0_RP3_RX_DN[7:0]	I, Differential	Yes	**Receive (Rx):** These differential input signals are internal to the SoC. The actual signal pins are determined by the FIA configuration.
PCIE_CLKREQ_N[3:0]	I,O-OD	Yes	**Reference Clock Control:** These active-low signals are used for reference clock control. See CLKREQ# signal in the PCIe Mini CEM specification.
PCI Express RP Cluster 1 - SoC Root Ports 4, 5, 6, and 7			
PCIE1_RP4_RP7_TX_DP[7:0] PCIE1_RP4_RP7_TX_DN[7:0]	O, Differential	Yes	**Transmit (Tx):** These differential output signals are internal to the SoC. The actual signal pins are determined by the FIA configuration.
PCIE1_RP4_RP7_RX_DP[7:0] PCIE1_RP4_RP7_RX_DN[7:0]	I, Differential	Yes	**Receive (Rx):** These differential input signals are internal to the SoC. The actual signal pins are determined by the FIA configuration.
PCIE_CLKREQ_N[7:4]	I,O-OD	Yes	**Reference Clock Control:** These active-low signals are used for reference clock control. See CLKREQ# signal in the PCIe Mini CEM specification.
Common to All Root Ports			
CLK_OUT_DP[4:0] CLK_OUT_DN[4:0]	O, Differential	No	**Differential Reference Clock:** These differential output signals can be used to provide a PCIe interface clock to external PCIe devices. These five sets of output signals enable the platform board design to have five PCIe devices without requiring a clock-buffer component. ***Note:*** While there are eight PCIE_CLKREQ_N signal pins, there are only five Differential Reference Clock pins provided. Clock buffering may be needed on some platform board designs.

11.2 Feature List

The following table lists PCI Express Root Port (RP) supported features:

Table 11-3. PCI Express Features (Sheet 1 of 2)

Feature	Root Port (RP)
Alternate Routing-ID Interpretation (ARI)	Supported
Link Speed	Gen3[1] (8 GT/s), Gen2 (5 GT/s), Gen1 (2.5 GT/s)
Port Configuration	2 RP of x8 each (16 lanes)
Maximum Payload Size	256 bytes (default). 128 bytes also supported.
Lane reversal	Inferred during Link training rather than strapped
PME logging with interrupt for WAKE support	Supported
NP request Splitting	Supported on 64/128/256 bytes boundary
Posted Transaction Splitting	Supported on 64 byte boundary
PLL Shutdown/Standby	Supported
PCI Express Card Hot-Plug* In-band Hot Plug	Supported
Full Hot-Plug (PCIe Cards + SHPC)	Supported
Routing of AtomicOps	Not supported
Revise ASPM	Supported
Latency Tolerance Reporting (LTR)	Not Supported
Project Specific Messages	Supported
Dynamic Link Width	Supported (as Slave, Controlled by CSR when port is Master)
Completion Combining	Supported
Windows Hardware Error Architecture (WHEA)	Supported
Completion Time Out (CTO)	Supported
End-to-End CRC (ECRC)	Supported
Stop and Scream (S&S)	Supported
Enhanced Downstream Port Containment (eDPC)	Not supported
Enhanced Live Error Recovery (eLER)	Not supported
Single Root I/O virtualization (SR-IOV)	Supported
Swizzle In-bound INTx into INTA	Supported
Separate Refclk Independent SSC Architecture (SRIS)	Supported
Continuous Time Linear Equalizers (CTLE)	Supported
Initial FoM Search Algorithm/Modified F0M Search Algorithm for WMP	Supported
Squelch Dynamic Enable	Supported
Resizable BAR	Not Supported
Optimized Buffer Flush/Fill Mechanism with WAKE# (OBFF)	Not Supported
Thermal Throttle	Not Supported
SATA Over PCIe	Not Supported
Programmable Device Idle Duration	Not Supported

Table 11-3. PCI Express Features (Sheet 2 of 2)

Feature	Root Port (RP)
Address Translation Services (ATS)	Not Supported
TLP Processing Hints (TLP)	Not Supported
Dynamic Power Allocation (DPA) Capability	Not Supported

1. SKU dependent.

11.3 Architectural Overview

The SoC supports two sets of PCIe* Root Port (RP) clusters. Each cluster consists of four Root Ports. Each cluster can be configured to provide up to eight lanes. RP[3:0] are assigned Device Numbers 12, 11, 10, and 9 while RP[7:4] are assigned 17, 16, 15, and 14. Each can operate at speeds up to 8.0 GT/s.

The internal bus of these root ports is Bus 0 and consists of secondary PCIe buses of specific link width. BIOS and/or OS can assign any logical bus number to the secondary PCIe ports.

Each of the eight RP controllers has three regions in Configuration Space. The contents of these regions and their offset values are:

1. Standard PCI Header:
   — Type 1 = PCI-to-PCI bridge
2. PCI Device Dependent Region:
   — PCI Express Capability
   — PCI Power Management Capability
   — SVID/SID Capability
   — Message Signaled Interrupts (MSI) Capability
   — Various implementation-specific and Intel-reserved registers
3. PCI Express Extended Configuration Space:
   — Advanced Error Reporting (AER) Capability
   — Access Control Services (ACS) Capability
   — Windows* Hardware Error Architecture (WHEA) Capability
   — Latency Tolerance Reporting (LTR) Capability
   — L1 Power Management Substates Capability

Note: The Multicast and Secondary PCI Express Extended Capabilities are not supported.

The PCIe Architecture also includes:

- PCIe Transaction Layer Registers
  — Performance Monitor
  — Local Event Triggers
  — Error Injection
  — Debug Registers
  — Test and High-Volume Manufacturing Registers
- PCIe Link Layer Registers
- PCIe Physical (PHY) Layer Registers

The vendor-specific extended capabilities in Configuration Space are primarily for Intel debug and testing purposes.

Note: The SoC does not support peer-to-peer transactions between RPs.

11.3.1 PCI Bridge Subsystem Identification Capability

The PCI Bridge Subsystem Vendor ID (Intel® Corporation) and additional identification information are read by the software.

11.3.2 Message Signaled Interrupt (MSI) Capability

Supported by the root ports:

- Per-vector masking capable (PVM)

Not Supported by the root ports:

- Address 64-Bit Capable - The root ports are not capable of generating a 64-bit message address
- Multiple Message Capable - No, only one message is supported

Supported by the root ports when enabled by the software [Default]:

- MSI Enable (MSIE) - When set, MSI is enabled and traditional interrupt pins are not used to generate interrupts. Default is 0 (not set)
- Trigger Mode (TM) - Either Edge-Triggered or Level-Triggered. Default is Edge-Triggered
- Level- or edge-triggered messages are always treated as assert messages. For level-triggered interrupts, the Level bit reflects the interrupt input state if TM (above) specifies the level-triggered mode as follows:
  - 0: Deassert messages
  - 1: Assert messages

11.3.3 Advanced Error Reporting (AER) Capability

PCI Express* defines two error reporting paradigms:

- Baseline capability
- Advanced Error Reporting (AER) capability

The baseline error reporting capabilities are required of all PCI Express devices and define the minimum error reporting requirements. The root ports provide the optional Advanced Error Reporting Capability which is defined for more robust error reporting and is implemented with a specific PCI Express Capability structure. PCIe* baseline error handling does not support severity programming.

The Advanced Error Reporting Capability provides each of the root ports the Uncorrectable Error Severity register which allows each uncorrectable error to be programmed to fatal or non-fatal. Uncorrectable errors are not recoverable using defined PCI Express mechanisms. However, the SoC considers a particular error fatal to a link or device or possibly considers that error non-fatal. The Uncorrectable Error Severity register (ERRUNCSEV) default value is re-programmed if the device driver or platform software requires more robust error handling.

11.3.4 PCIe Extended Capability and Other Supported Technology

11.3.4.1 Access Control Services (ACS) Capability

ACS prevents various forms of silent data corruption by preventing PCI Express Requests from being incorrectly routed to a peer Endpoint below a switch. ACS is also used to validate that every request transaction between two downstream components is allowed. Also, ACS allows some robustness checks by checking for the ReqID from a function to be a valid ReqID at a coarse granularity. When ACS is enabled, the PCIe Root Port does loopback memory transactions (reads and writes) to the same port if the address map check matched.

11.3.4.2 Windows Hardware Error Architecture (WHEA)

WHEA is an error-injection methodology that allows the software stack to test how it handles an error. WHEA is a Windows* hardware-enabling specification that requests one correctable and one uncorrectable error to be injected in the SoC.

WHEA is implemented in the PCIe Root Ports controllers as a vendor-specific error-injection capability structure, defined for software recognition in Configuration Space. The Intel-defined Vendor Specific ID is 3h.

It is a programmatic way to inject a correctable and an uncorrectable error. Two bits are provided to allow software to inject correctable and uncorrectable errors. Errors are injected when software sets one of the bits. Software must clear the error injection bit before setting again to generate another error. The bit will not be cleared by the hardware.

This will cause normal error logging and interrupt trigger. The error handler code is expected to be invoked. Error injection software should not preclude the invocation of the error handler. The appropriate status registers are set so that the operating system handler can go through its flows.

As a security feature, a write-once bit is provided to disable the error injection mechanism. BIOS sets this bit in every boot to prevent a denial-of-service (DOS) attack. BIOS keeps this disable bit clear only when error injection is being tested.

The error-injection mechanism does not require dependency on any external component.

The selected correctable error is the Receiver Error. The uncorrectable error is the Completion Timeout Error. Neither of these have header logs associated with them.

11.3.4.3 Dynamic Link Width

The capability allows either end of a link to initiate a dynamic link width change by going through Recovery and Configuration back to L0. This can be used by devices to adjust the link width based on dynamically changing bandwidth requirements. The UPCFGCSR register, located at offset AB8h in the Root Port's Configuration Space, allows the device to advertise up configure capability in the TS2 training set, so the other end can dynamically adjust the link width as needed.

11.3.4.4 Alternative Routing-ID Interpretation (ARI)

ARI enables next generation I/O implementations to support an increased number of concurrent users of an Endpoint, while providing the same level of isolation and controls found in existing implementations. While ARI obviously benefits the virtualized operating environments where each Requester ID can be uniquely assigned to a guest OS, ARI also benefits non-virtualized environments where (due to increased process improvements) a large number of I/O Functions can be integrated into a single Endpoint.

Routing IDs, Requester IDs, and Completer IDs are 16-bit identifiers traditionally composed of three fields:

- an 8-bit Bus Number
- a 5-bit Device Number
- a 3-bit Function Number

With ARI, the 16-bit field is interpreted as two fields instead of three:

- an 8-bit Bus Number
- an 8-bit Function Number

The Device Number field is eliminated.

This new interpretation enables an ARI Device to support up to 256 Functions. ARI is controlled by a new set of capability and control register bits defined in the PCIe registers.

11.4 Physical Layer

11.4.1 PCI Express Speed Support

The PCI Express (PCIe) physical layer implements high-speed, low-voltage differential signaling that is described in detail in the PCI Local Bus Specification, Revision 3.0. The integrated root ports support 2.5 GT/s, 5 GT/s and 8 GT/s (SKU dependent) PCI Express speeds. The Root Port controllers negotiate the speed using the in-band signaling mechanism, Link Initialization and Training, of the specification.

The PCI Express Root Ports use 8b/10b encoding when the data rate is 2.5 GT/s or 5 GT/s. For data rates greater than or equal to 8 GT/s, the encoding mechanism used is a link-wide physical layer packeting along with a per-lane encoding scheme that uses 2-bits of sync header with a payload of 128 bits.

11.4.2 Separate Refclk with Independent SSC Architecture (SRIS)

SRIS can be utilized to enable a PCI Express application involving an inexpensive cabling solution such as for PCIe-attached Solid-State Storage Devices (SSD) with a new cabling form factor that supports non-common clock mode with Spread-Spectrum Clocking (SSC) architecture. The reference clock is not needed to be delivered through cable. However, the new clock mode requires both sides of a link to tolerate a much higher ppm tolerance of 5600 ppm compared to the PCIe Base Specification defined as 600 ppm. For more details, please refer to PCI-SIG Engineering Change Notice (ECN) "Separate Refclk Independent SSC Architecture (SRIS)."

- The SoC has Soft Straps to enable SRIS on each of the eight Root Ports. See Table 4-3, "Flash Descriptor Soft Straps."
- The SoC Root Ports only support Separate Refclk with no SSC (SRNS) and do not support SRIS for 8-GT/s speeds. Both SRIS and SRNS are supported for PCIe 2.5-GT/s and 5-GT/s speeds.

11.4.3 Form Factor Support

The PCIe controllers support card-edge-connector and Server I/O Module (SIOM) form-factors. Form-factor-specific differences that exist for Hot-Plug* and power management are captured in their individual sections elsewhere in this chapter.

The root ports have enough buffering to provide full performance using up to a 20-inch trace of FR4 with two connectors. They do not provide any additional buffering for cable/repeater latencies and are not able to achieve full bandwidth on PCI Express using these topologies. But functionally, they are able to support cables.

11.4.4 Configuration of the PCI Express Ports and Link Widths

While there are up to two, eight-lane (Maximum Link Width = 8) PCI Express Root Port clusters, each can be configured to provide one, two, three or four Root Ports. Each of the two controllers has a PCI Express Port Bifurcation Control (PPBIFCTL_PRIV) register that determines the number of Root Port Links per controller and the number of Lanes per Link. The SoC also provides flexibility in the number of High-Speed I/O interface signals that can be made available on the SoC. Details of the PCI Express Root Port and Lane-configuration possibilities are explained in Section 10.5.2, "PCI Express Lane Configuration" of the Flexible I/O Adapter (FIA) chapter of this document.

The PPD0.ILINKTRN0 bit, located in Host Configuration Space for each of the eight possible Root Ports, controls the PCIe Express port Link Training for the associated port. A value of '1' initiates Link Training. After writing this bit to a '1', software can poll the Data Link Layer Link Active (DLLLA) bit in the LINKSTS register, which is also located in Host Configuration Space for each Root Port. Polling this bit allows software to determine if a port is up and running. Root ports do not automatically initiate Link Training after reset unless the default value of '0' of the ILINKTRN0 bit is changed to a '1'. A write of '0' to a default register-setting has no effect.

A Capability Lock (CL) bit is provided for each PPD0 register and each PPBIFCTL_PRIV register. A write of '1' locks-down the associated register for security purposes. Refer to the register-description chapters of this document for details.

There is a dedicated Soft Strap for port enable on a per-port basis to enable/disable the port. When certain PCI Express lanes within a port are disabled, via Soft Straps or through the Host Configuration-Space Registers, then the Link-Training and Status State Machine (LTSSM) associated with those lanes must be put in the "disabled" state (which disables receiver detect sequence on those lanes). In addition, strap of slot width, per port basis, can be utilized for constraining the port operation at a particular width. This is instant and the behavior is an undefined post, allowing the link to train. The SoC Soft Straps are described in Chapter 4, "Strapping and Configuration."

11.4.5 Degraded Mode

Degraded-Mode Link Widths a PCI Express negotiation behavior supported by the SoC and is automatically attempted every time the PCI Express link is trained. To maximize performance, the SoC first attempts Degraded Mode of a higher Link Width before trying any of the lower-Link-Width Degraded Modes. The x1 is the smallest Link Width supported by the SoC in the PCIe Degraded Mode operation. Link-Width degradation is always be anchored to a slot edge.

Lane-degradation remapping occurs in the Physical Layer. The Link Layer and Transaction Layer are transparent to the Link-Width change.

See Figure 11-2, "PCIe Bifurcation and Physical Ports."

Figure 11-2. PCIe Bifurcation and Physical Ports



11.4.5.1 Dynamic Lane Reversal

Lane Reversal is a Link negotiation behavior that creates a condition where if a Link fails to train, the Link is then forced to train again with its Lanes re-ordered in the opposite order. For an 8x situation with a Link wired as Lanes 0 through 7, Lane Reversal tries the training again with the Link physically wired as Lanes 7 through 0. See Figure 11-2, "PCIe Bifurcation and Physical Ports."

If a Link encounters a "bad Lane" during its initial training, the Link then chooses a "subset" of Lanes. It does this either on the reversed order, anchored to physical Lane N-1, or on the non-reversed order, anchored to physical Lane 0.

If the device connected to the Root Port does not support Lane Reversal, Link training may fail (no possible Lane-0 match).

This Lane Reversal negotiation is only enabled when the Link falls back to the Detect State from the Configuration.Lanenum.Wait or Configuration.Lanenum.Accept state prior to when the Physical Layer reports Physical LinkUp = 1b. Once the link reaches the Configuration.Complete substate, the Lane Reversal negotiation is turned off.

11.4.5.2 Lane Polarity Inversion

Lane Polarity Inversion is a Link negotiation behavior that is supported by the SoC. Polarity inversion allows the board designer to connect the D+ and D- lines to the Rx- and Rx+ pins of the chip respectively.

11.5 Transaction Layer

PCI Local Bus Specification, Revision 3.0 defines a field in the header called the Transaction Descriptor. This descriptor comprises three sub-fields:

- Transaction ID
- Attributes
- Traffic Class

11.5.1 Transaction ID

The Transaction ID uniquely identifies every transaction outstanding on the PCI Express interface. The Transaction ID comprises four sub-fields described in Table 11-4, "PCI Express Transaction ID Handling."

Table 11-4, "PCI Express Transaction ID Handling" provides details on how this field in the PCI Express header is populated by the SoC on the requests it issues on PCI Express (requests issued by core) and the completions it sends back on PCI Express.

Note: The SoC does not support Peer-to-Peer transactions between PCIe Root Ports.

Table 11-4. PCI Express Transaction ID Handling

Field	Definition	SoC as Requester	SoC as Completer
Bus Number	Specifies the Bus Number on which the Requester resides.	The SoC fills this field with its internal Bus Number that the PCI Express cluster resides on.	This field from the request is preserved and copied into the completion.
Device Number	Specifies the Device Number of the Requester.	The SoC fills this field with the Device Number that the root port owns.	
Function Number	Specifies the Function Number of the Requester.	The SoC fills this field with the Function Number that the root port owns.	
Tag	Identifies a unique identifier for every transaction that requires a Completion. Since the PCI Express ordering rules allow read requests to pass other read requests, this field reorders separate completions if they return from the target out-of-order.	• NP Tx: The SoC fills this field with a value such that every pending request carries a unique Tag. • NP Tag[7:5]=Note that bits 7:5 can be non-zero only when 8-bit tag usage is enabled. Otherwise, the SoC always zeros out 7:5. • NP Tag[4:0]=Any algorithm that guarantees uniqueness across all pending NP requests from the port. • P Tx: No uniqueness guaranteed. Forward from source port to destination for p2p posteds.	

11.5.2 Attributes

The Attributes field is used to provide additional information that allows modification of the default-handling of Transactions. Attributes are hints that allow for optimizations in the handling of traffic. PCI Express supports two attributes:

Table 11-5. PCI Express Attribute Handling

Attribute	Definition	PCIe SIP as Requester	PCIe SIP as Completer
Relaxed Ordering	Allows the system to relax some of the standard PCI ordering rules.	This bit is not applicable and set to zero for transactions that the PCIe SIP generates on PCIe on behalf of a request.	The PCIe SIP preserves this field from the request and copies it into the completion.
Snoop Not Respond	This attribute is set when an I/O device controls coherency through software mechanisms. This attribute is an optimization design to preserve processor snoop bandwidth		

For relaxed ordering, PCIe ports implements Downstream CPL relaxed ordering. For the cases where the No-Snoop attribute is set in the inbound TLP, it should be passed to the upstream block or root port and the request should be treated as non-coherent in the UnCore.

The PCI express ports support the “No Snoop Attribute” but there is no isochronous support.

11.5.3 Traffic Class

The SoC does not support any PCI Express Virtual Channels (VC) except for the default channel VC0. There is no Traffic Class (TC)-to-VC mapping capability structure. However, as per the PCI Express Base Specification, a completer must accept requests with a TC label other than TC0, and must preserve the TC label.

The SoC accepts inbound transactions with zero/non-zero TC, but it treats the non-zero TC as mapped to VC0 for inbound requests destined for memory. For completions heading upstream, the Root Port copies the TC value received into the completion packet. If the SoC receives a non-zero TC for any I/O or Configuration transaction, it is treated as a malformed TLP and the error-logged appropriately.

11.5.4 Completer ID

The CompleterID field is used in PCI Express completion packets to identify the completer of the transaction. The CompleterID comprises three sub-fields which are populated on a completion sent back on PCI Express, as described in Table below.

Table 11-6. PCI Express CompleterID Handling

Field	Definition	PCIe RP as Completer
Bus Number	Specifies the bus number om which the completer resides on.	PCIe RP fills this field with its internal Bus Number on which the port resides.
Device Number	Specifies the device number of the completer.	PCIe RP fills this field with its Internal Device Number.
Function Number	Specifies the function number of the completer.	PCIe RP fills this field with its Internal Function Number.

11.5.5 Transaction Ordering

Table 11-7 lists the combined set of ordering rules in the PCIe inbound paths of the root port.

Table 11-7. Transaction Ordering on PCIe Block

Row Pass Column	Message or Posted Wr (PR)	Rd or Configure Write or I/O Req (NPR)	Rd Completion	I/O or Configure Write Completion
Message or Posted Wr (PR)	No	Yes	Yes	Yes
Rd or Configure Write or I/O Req (NPR)	No	No	Yes[1]	Yes
Rd Completion	No	Yes	No	No
I/O or Configure Write Completion	No	Yes	No	No

1. When a completion is stalled, a subsequent read can be allowed to pass it.

11.5.6 PCI Express Port Arbitration

The SoC provides a normal, weighted (based on port width), round-robin method of arbitration amongst the eligible sources.

11.5.7 Request Splitting

The Transaction Layer Packet (TLP) Maximum Payload size is defined as 256 bytes for the PCI Express* Root Ports.

Each SoC Root Port splits Non-Posted Requests greater than 256 bytes at the 256-byte address boundary. This maximum-byte size of 256 is without regard to the target address. The expectation is, that for better performance, the target agent will provide the maximum payload-size completions. The Root Port implements completion tracking to assure that multiple completions for a greater-than 256-byte read are sent to the requester in addressed order.

Posted Requests in the Root Port have a length of up to the defined Maximum Payload Size of 256 bytes and are handled as normal TLPs.

11.5.8 Read Prefetching Policies

The Root Ports do not perform any outbound-read prefetching. They also do not perform any autonomous, speculative Prefetch on their inbound interfaces.

11.5.9 Read Completion Combining

The PCI Local Bus Specification, Revision 3.0 allows a single request to be satisfied with multiple "sub-completions" as long as the sub-completions return in linearly-increasing address order. Therefore, since the Root Ports must split requests into cacheline quantities before issuing them to the coherent interface, the Root Ports often complete a large request in cacheline-sized sub-completions.

As a performance optimization, the Root Port implements an opportunistic read-completion combining algorithm. When the downstream PCI Express* interface is busy (for example, with another transaction) and multiple cachelines have returned before completion on PCI Express is possible, the PCI Express interface combines the cacheline sub-completions into larger quantities up to defined Maximum Payload size.

11.5.10 Write Combining

The Root Ports do not support any outbound write combining.

Potentially, inbound memory writes to the system DDR SDRAM could be combining in the Root Port Write of the coherent interface.

11.6 Interrupt Support

The PCIe Root Port supports both Message Signaled Interrupt (MSI) and in-band legacy interrupt mechanisms. The PCIe Root Port can generate an in-band legacy interrupt request on PCI Express for boot devices and for systems that do not support MSI.

11.6.1 Legacy Interrupt Sharing

PCI Express provides interrupt messages that emulate the legacy wired mechanism.

This feature allows I/O devices to signal PCI-style interrupts using a pair of ASSERT and DEASSERT messages. This message pairing preserves the level-sensitive semantics of the PCI interrupts on PCI Express.

The four virtual wire interrupts (INTA–INTD) correspond to the four interrupt wires defined in the PCI Local Bus Specification, Revision 3.0. The switch routes its interrupts messages from the downstream ports to the upstream ports interrupts as shown in Table below.

Table 11-8. Bridge Mapping for Interrupt Virtual Wires

Device #	Interrupt Message on Port	Interrupt Message on the Upstream Port
0, 4, 8, 12, 16, 20, 24, 28	INTA#	INTA#
	INTB#	INTB#
	INTC#	INTC#
	INTD#	INTD#
1, 5, 9, 13, 17, 21, 25, 29	INTA#	INTB#
	INTB#	INTC#
	INTC#	INTD#
	INTD#	INTA#
2, 6, 10, 14, 18, 22, 26, 30	INTA#	INTC#
	INTB#	INTD#
	INTC#	INTA#
	INTD#	INTB#
3, 7, 11, 15, 19, 23, 27, 31	INTA#	INTD#
	INTB#	INTA#
	INTC#	INTB#
	INTD#	INTC#

The switch tracks the INTx messages from each port independently and presents a collapsed INTx message on the upstream port. For example, each INTx message from the downstream ports are ORed together and presented upstream as a single INTx message. The switch uses its upstream port primary bus number and device number in the Requester ID field for the PCI Express INTx messages. As stated in the PCI Local Bus Specification, Revision 3.0, the function number is reserved for interrupt messages and is always 0.

11.7 Power Management

11.7.1 Hardware Controlled Active Power Management

PCI Express Base Specification defines a HW-initiated power management of the PCIe link called the active state power management (ASPM). Under hardware control, the link can be put into a low-power L0s state or an even lower power L1 link state. Latency to recover from L0s back to L0 (active link state) is smaller than that of recovery from L1 to L0. The PCIe Root Port supports both ASPM link states L0s and L1. ASPM is totally traffic dependent and is not initiated by software. But the software could either enable or disable the active state management via the PCIe Express capability structure.

11.7.2 PCI-PM 1.2 Support

The PCI Express Root Port supports PCI Express link states required to implement PCI_PM 1.2 compatible device states (D0, $D3_{HOT}$, $D3_{COLD}$). These states correspond to PCI Express link states L0, L1, and L3. When all the root ports and the IOxAPIC are programmed to $D3_{HOT}$ state, the upstream link of the switch automatically transitions to the link state L1. The switch also supports the PME_Turn_Off/PME_TO_Ack handshake protocol to enter the $D3_{COLD}$/L3 device/link states.

Each function (upstream port, downstream ports, and IOxAPIC) behaves as follows when in the $D3_{HOT}$ state:

- The function responds to Configuration cycles on UpStream PCIe ports
- The function does not respond to Memory Cycles on UpStream PCIe ports except for completions
- The function does not respond to I/O cycles on UpStream PCIe ports except for completions
- The function does not initiate UpStream PCIe port transactions
- The function does not reset its registers when programmed from D0 to $D3_{HOT}$

Note: When a downstream port is in the $D3_{HOT}$ state, a Hot-Plug event on that port must generate a PME event since the port is unable to generate an interrupt. Software needs to setup the Hot-Plug to generate a wake event instead of interrupts when the port is in $D3_{HOT}$ state.

11.7.3 Power Management Event Signaling

PCIe Root Port supports Active State Power Management (ASPM) transitions into L0s and L1 state. L0p state is not supported by the SoC.

Also, the PCIe Root Port supports the D0 and D3hot power management states per PCI Express port and also supports a wake event from these states on a PCI Express Hot-Plug event. In D3hot, the root port will master abort all configuration transactions targeting the PCI Express link.

PME signaling in PCI-Express accomplishes two distinct functions:

- Firstly, it provides a signaling mechanism for devices requiring service to propagate a wake-up request to the power management controller.
- Secondly, it provides a messaging mechanism for devices requesting a power state change to pass their unique location within the PCI Express hierarchy to the power management controller.

The combination of these two functions provides great flexibility and controllability for the power manager.

11.7.4 Beacon and WAKE# Signaling

At the link level, the PCI Local Bus Specification, Revision 3.0 describes two optional mechanisms used by components to request the reapplication of main power (transition to the fully-operative L0 state) when in the low-power L2 Link state:

- Beacon (using in-band signaling):
  - — Not supported by the Root Ports.
- WAKE# (using sideband signaling):
  - — Supported by the Root Ports through the signal pin WAKE_B.

11.7.5 Non-D0 State PM Handling

The Non-D0 and Bus Master Enable (BME) state requirements are as follows:

11.7.5.1 Non-D0 Behavior for Transmit (Tx) Transactions

- Memory and I/O requests are treated as Unsupported Request (UR) completions
- Memory or I/O requests that require response get a UR response (internally generated)
- Type0 Cfg requests proceed normally for Downstream Port (of an Upstream Component)
- Type0 Cfg requests are treated as URs (completion w/ UR response) for Upstream Port (of an Downstream Component)
- Type1 Cfg are treated as URs (completion w/ UR response)
- Messages and completions are unaffected by device states

11.7.5.2 Non-D0 Behavior for Receive (Rx) Transactions

- Memory and I/O requests are treated as URs
- Memory or I/O requests that require response get an UR response (internally generated)
- Type0 Cfg request is treated as URs (completion w/ UR response) for Downstream Port (of an Upstream Component)
- Type0 Cfg request proceeds normally for Upstream Port (of an Downstream Component)
- Type1 Cfg is treated as URs (completion w/ UR response)
- Messages and completions are unaffected by device states

When the Upstream port is programmed to the non-D0 state, it should initiate its Upstream PCIe link to the transition to PCI-PM L1 state when all conditions are met.

The transition of a PCIe of a Virtual Bridge (such as a root port) from D3hot state to D0 because of a powerstate command will not cause an internal soft reset and this is indicated by setting the No_Soft_Reset bit3 (RO) of PMCSR register.

11.7.6 BME Clear State Handling

In BME (=1) set state, all transactions are treated as normal.

11.7.6.1 BME (=0) Clear State Behavior for Transmit (Tx) Transactions

- Downstream Port (of an Upstream Component)
  - All transmit transactions are treated as normal and behavior is unaffected by BME bit state
- Upstream Port (Downstream Component)
  - Memory, I/O requests are treated as URs
  - Configuration, Messages and completions are treated as normal and behavior is unaffected by BME bit state
  - All requests that require response get an UR response (internally generated)

11.7.6.2 BME (=0) Clear State Behavior for Receive (Rx) Transactions

- Downstream Port (of an Upstream Component)
  - Memory, I/O requests are treated as URs
  - Configuration, Messages and completions are treated as normal and behavior is unaffected by BME bit state
  - All requests that require response get an UR response (internally generated)
- Upstream Port (of an Downstream Component)
  - All transmit transactions are treated as normal and behavior is unaffected by BME bit state

11.7.6.3 Internal MSI/Error Messages During Non-D0/BME (clear)

- MSIs generated internally are blocked when in non-D0 and BME (clear).
- MSIs generated internally in non-D0 with BME = 1 (for example, a completion timeout or an MSI due to PME event) should be allowed to propagate but after the port is reinitialized back to D0. There should be no loss of interrupts.
- MSIs received at the root port or in the switch port from external sources should be blocked (UR) when non-D0.
  Assumption: PCI configuration software should place the downstream component in non-D0 first and then the upstream components. There should be no MSI writes received at the upstream component under these conditions and if any spurious MSIs do arrive, they will be master aborted.
- INTx, VLW and ERR messages should not be blocked.

11.7.6.4 L1 PM Substates

PCIe supports the optional PM L1 Substates including L1.1 and L1.2,where L1.1 is hardware autonomous without Software intervention and L1.2 may require Software not to access device for longer period, which allow for dramatically lower idle power, including near complete removal of power for high speed circuits. The L1 PM Substates are applicable in both the ASPM and PCI-PM L1 Link states and the entrance and depth is constrained by aggregated PCIe LTR.

11.8 PCI Express RAS Features

The PCI Local Bus Specification, Revision 3.0 supports PCI Express Advanced Error Reporting (AER) capability.

11.8.1 End-to-End CRC (ECRC) Support

PCIe End to End CRC (ECRC) is the CRC field generated by a device and is appended to the TLP to protect the data through layers of switches and bridges.

For inbound traffics, PCIe Root Ports support ECRC checking and will strip the ECRC if no error is detected. The corresponding TLP will be dropped and logged UC if an error is detected. ECRC error severity should be set to non-fatal in the Uncorrectable Error Severity Register during initialization.

For outbound traffic, PCIe Root Ports will generate ECRC based on AER Capabilities and Control Register (AERCAPCTL), and insert ECRC to the packet prior to forwarding to the PCIe link. Refer to PCI Local Bus Specification, Revision 3.0 for more details of ECRC generation rules.

11.8.2 Completion Timeout

For all non-posted requests that the PCIe Root Port issues, the PCIe maintains a timer that times the max completion time for that request.

The PCIe Root Port follows the timeout mechanism as defined in the PCI Express Base Specification. The spec provides a way for the OS to select a coarse range for the timeout value. The PCIe root port chooses a final value of the timeout within each coarse range. The timeout value is programmable from 50 ms all the way up to 64s.

Refer to Chapter 6, "Reliability, Availability and Serviceability (RAS)" for details of responses returned by the PCIe Root port to various interfaces on a completion timeout event. AER-required error logging and escalation happen as well.

11.8.3 Data Poisoning

The PCI Express Root Ports support forwarding poisoned information between the coherent interface and the PCIe link, and vice-versa. Also, forwarding poisoned data between peer PCIe ports is supported. The PCIe has a mode where poisoned data is never sent out on PCI Express, in other words, any packet with poisoned data is dropped internally in the root port and an error escalation done.

11.8.4 Role-based Error Reporting

The PCIe Root Port supports the new role-based error reporting that is specified in the PCI Local Bus Specification, Revision 3.0.

When the PCIe Root Port times out or receives a UR/CA response on a request outstanding on PCI Express, it does not attempt recovery in hardware. The UR/CA received does not cause any error escalation via AER mechanism and causes error escalation only via the IO module-specific mechanism. The PCIe Root Port would forward those to the ultimate destination. Also, the PCIe Root Port would treat the completion timeout condition as a normal non-fatal error condition (and not as an advisory condition).

The PCIe Root Port also treats an unexpected completion it receives from PCI Express port as an advisory non-fatal error if the severity of it is set to non-fatal. If the severity is set to fatal, then unexpected completions are NOT treated as advisory but as fatal.

When the PCIe Root Port detects a UR/CA condition on a non-posted request it received from PCIe link, it treats the error as advisory error if the severity of UR/CA is set to non-fatal, and send a UR/CA completion back to the device. Note that a UR/CA condition detected on a posted request that the PCIe Root Port received from the PCIe link is treated as normal non-fatal error with the appropriate escalation/logging.

11.9 PCI Express Hot-Plug Surprise

PCIe Root Port Hot-Plug slot capability is supported mainly through software stacks by setting Hot-Plug related CSRs for handling Hot-Plug events such as in-band presence detect. It does not utilize any mechanical or electromechanical features such as MRL/sensor/EM interlock/ Attention button, etc.

The Hot-Plug Surprise slot capability involves a device that is inserted into or removed from a running system without prior notification to the system. It is not an orderly operation and could cause undesirable effects to the running system. The general expectation from hardware and software is to avoid Hot-Plug error event propagating into a catastrophic system event.

In general, all outstanding Non-posted request should synthesize a Master Abort to avoid completion timeout and suppress catastrophic AER storm whenever applicable. En-queued inbound traffic at the port upstream to the device must complete normally in the event of a Surprise Removal. PME_Turn_Off handshake and VDM should be terminated appropriately plus discarding all other posted & completion requests.

The Hot-Plug Surprise event is limited to the link transitions back to L0, in other words, software may need to wake up periodically during low power states accordingly. To handle the L1 inband Hot-Plug Surprise case, the link will not be allowed to train until the SLOTSTS.PDCS has been cleared by software to avoid hot-add interrupt from being merged with the hot-removal interrupt.

11.9.1 PCI Express Hot-Plug Interrupts and Events

11.9.1.1 Presence Detect

When a module is plugged in and power is supplied, the physical layer will detect the presence of the device, and the downstream port sets SLOTSTS.PDS and SLOTSTS.PDCS. If SLOTCTL.PDCIE and SLOTCTL.HPIE are both set, the downstream port will also generate an interrupt. When a module is removed through physical layer detection, the downstream port clears SLOTSTS.PDS and sets SLOTSTS.PDCS. If SLOTCTL.PDCIE and SLOTCTL.HPIE are both set then the downstream port will also generate an interrupt. The interrupt is generated on an edge-event. For example, if SLOTSTS.PDCS is already set, a change in SLOTSTS.PDS will not generate a new interrupt. Only SLOTSTS.PDCS going from `0 to `1 will cause an interrupt to be generated.

11.9.1.2 SCI/SMI Generation

When a module is plugged in and power is supplied, the physical layer will detect the presence of the device, and the downstream port sets SLOTSTS.PDS and SLOTSTS.PDCS. If SLOTCTL.PDCIE and SLOTCTL.HPIE are both set, the downstream port will also generate an interrupt. Similarly, PCIe Root Port could generate SCI/SMI based on PM_PME message received from downstream PCIe devices.

11.10 Register Map

Figure 11-3, "Register Map" shows the associated registers from a system software viewpoint.

Figure 11-3. Register Map



§ §

12 SATA Controller

The SoC has two independent integrated SATA 3.1 host controllers (SKU dependent). Each controller supports DMA operation on up to eight ports and supports data transfer rates of up to 6 Gbps (600 MBps). Legacy data transfer rates of 3 Gbps and 1.5 Gbps are supported as well. Serial General Purpose Input Output (SGPIO) support is added in this generation and support is per the SFF 8485 specification.

Note: Legacy and Native IDE are not supported in this generation.

Figure 12-1. What is Covered in This Chapter



Table 12-1. References

Reference	Revision	Date	Document Title
Serial ATA	3.1	July 2011	*Serial ATA Specification, Revision 3.1*
Serial ATA	3.0	June 2009	*Serial ATA Specification, Revision 3.0*
AHCI Specification	1.3.1	June 2008	*Serial ATA Advanced Host Controller Interface (AHCI) Specification, Rev 1.3.1*
SFF-8485	0.7	Feb. 1, 2006	*SFF-8485 Specification for Serial GPIO (SGPIO) Bus*, Revision 0.7

12.1 Signal Descriptions

The signal descriptions are shown in Table 12-2. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. Also, see Table 39-3, "Signals that Share the Twenty HSIO Lanes" on page 1028. The Direction/Type column of Table 12-2 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.
- Differential = Differential signal pair. Two pins: Positive; Negative.

Table 12-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
SATA Controller 0			
SATA0_TX_DP[7:0] SATA0_TX_DN[7:0]	O, Differential	Yes	SATA0 Transmitter: These differential output signals are internal to the SoC. They are at the SATA0 controller interface with the FIA circuitry.
SATA0_RX_DP[7:0] SATA0_RX_DN[7:0]	I, Differential	Yes	SATA0 Receiver: These differential input signals are internal to the SoC. They are at the SATA0 controller interface with the FIA circuitry.
SATA0_SLD	O-OD	Yes	SATA0 SGPIO Load: This is the SGPIO SLoad signal. During power-up and reset, this pin is 1 (high impedance). When using the SGPIO bus but purposely not exchanging a bit stream, the SoC sets SLoad to 0. This lets the target know that the initiator (the SoC) is still present and has not been removed.
SATA0_SCLK	O-OD	Yes	SATA0 SGPIO Clock: This is the 32-kHz SGPIO SClock signal. During power-up and reset, this pin is 1 (high impedance). When using the SGPIO bus but purposely not exchanging a bit stream, the SoC sets SClock to 0.
SATA0_SDOUT	O-OD	Yes	SATA0 SGPIO Data Out: This is the SGPIO SDataOut signal. During power-up and reset, this pin is 1 (high impedance).
SATA0_LED_N	O-OD	Yes	Open drain output pin driven during SATA command activity. It is to be connected to external circuitry that can provide the current to drive platform LED. When active, the LED is on. When inactive, the LED is off. An external pull-up resistor is required.
SATA_PDETECT[1:0]	I	Yes	Mechanical Presence Detect: This input signal is called Mechanical Presence Switch in the AHCI Specification: • SATA_PDETECT[0] - SATA Controller 0, Port 0 (FIA/HSIO Lane 4) • SATA_PDETECT[1] - SATA Controller 0, Port 1 (FIA/HSIO Lane 5)
SATA Controller 1			
SATA1_TX_DP[7:0] SATA1_TX_DN[7:0]	O, Differential	Yes	SATA1 Transmitter: These differential output signals are internal to the SoC. They are at the SATA1 controller interface with the FIA circuitry.
SATA1_RX_DP[7:0] SATA1_RX_DN[7:0]	I, Differential	Yes	SATA1 Receiver: These differential input signals are internal to the SoC. They are at the SATA1 controller interface with the FIA circuitry.
SATA1_SLD	O-OD	Yes	SATA1 SGPIO Load: This is the SGPIO SLoad signal. During power-up and reset, this pin is 1 (high impedance). When using the SGPIO bus but purposely not exchanging a bit stream, the SoC sets SLoad to 0. This lets the target know that the initiator (the SoC) is still present and has not been removed.
SATA1_SCLK	O-OD	Yes	SATA1 SGPIO Clock: This is the 32-kHz SGPIO SClock signal. During power-up and reset, this pin is 1 (high impedance). When using the SGPIO bus but purposely not exchanging a bit stream, the SoC sets SClock to 0.
SATA1_SDOUT	O-OD	Yes	SATA1 SGPIO Data Out: This is the SGPIO SDataOut signal. During power-up and reset, this pin is 1 (high impedance).
SATA1_LED_N	O-OD	Yes	Open drain output pin driven during SATA command activity. It is to be connected to external circuitry that can provide the current to drive platform LED. When active, the LED is on. When inactive, the LED is off. An external pull-up resistor is required.

12.2 Feature List

- Complies to SATA specification rev 3.1
- Complies AHCI specification rev 1.3.1
- Supports Native Command Queuing. Up to 32 commands can be queued
- Supports Staggered Spin-up
- Supports Aggressive Link Power Management
- Activity LED support via SGPIO
- Enclosure Management support
- Supports Command based Port Multiplier
- Supports Hot-Plug operation
- Supports MSI and MSI-X interrupts.

12.3 Architectural Overview

There are two independent SATA controllers. Both controllers support up to SATA Gen3 (SKU dependent) traffic speeds of 6 Gbps and are backward compatible to Gen2 and Gen1 speeds. Software mode is supported; this mode requires specific OS device driver support. IDE support is not available. The SoC enables SGPIO support, this is to enable and manage target device LED control. Enclosure management support is also available. SoC also has two dedicated pins for LED activity. SATA0_LED_N and SATA1_LED_N can be employed if a single drive is populated on SATA controller 0 and 1.

Each SATA controller has the following PCI capabilities:

- PCI Power Management Interface Capability
- Message Signaled Interrupts (MSI) Capability
- Extended MSI (MSI-X) Capability
- Serial ATA Capability

Note: The SATA controller configuration registers have default values that do not include the MSI-X Capability in the Capabilities List. BIOS must alter the Capabilities List links to include the MSI-X Capability which is located at offset D0h of each controller Configuration Space.

Note: If your design uses the SoC SATA then one of the following has to be met:

1. HSIO lane 16, 17, 18 or 19 must be assigned to the xHCI controller and the xHCI controller must be enabled and visible as a PCI device.

   OR

2. A PCIe Root Port Cluster must be enabled and visible as a PCI device. There is no requirement to assign any HSIO lanes to the PCIe Root Port.

12.4 AHCI Operation

Each controller supports up to 8 ports and each port can support up to 32 commands. A total of 256 commands can be pending at an instance per controller, a total 512 commands across controllers.

For AHCI operation details, refer to the *Serial ATA Advanced Host Controller Interface (AHCI) Specification, Rev 1.3.1*.

12.4.1 Staggered Spin Up Support

A staggered spin up feature enables a controller to individually spin up attached devices. This mechanism is useful to avoid having a power supply, needing to apply power to all the devices, while handling maximum current draw from all devices at the same time. In order for a system to support staggered spin up, the SATA controller, BIOS and device driver must all support staggered spin up.

Staggered spin-up is controlled by software via sequencing of COMRESET signaling. The table below summarizes the operations of SATA controller in AHCI mode. Refer to the *Serial ATA Advanced Host Controller Interface (AHCI) Specification, Rev 1.3.1* for more details on AHCI staggered spin up.

Table 12-3. SATA Controller Operations Summary

PCS.PxE	CAP.SSS	PxCMD.SUD	Result
0	X	X	No COMRESET and no spin up
1	X	X	COMRESET and spin up
0	X	X	No COMRESET and no spin up
1	0	0	This is not a valid combination. When CAP.SSS is 0, PxCMD.SUD must be 1
1	0	1	COMRESET and spin up
1	1	0	No COMRESET and no spin up
1	1	1	COMRESET and spin up

12.4.2 Staggered Spin-up Operation in AHCI Mode

Device Driver/BIOS to perform following actions

1. Programming ABAR.
2. Configure controller in AHCI mode by setting AHCI GHC.AE bit.
3. Set AHCI CAP.SSS to indicate staggered spin up support.
4. Set PCS.PxE bits.
5. Set PxCMD.SUD bits, this will result in COMRESET to be issued to the all the enabled ports.

12.4.3 Interrupts

12.4.3.1 Interaction Between INTx# and MSI/MSI-X

When MSI is enabled via MMC.MSIE=1, INTx# interrupt is disabled regardless of the setting of the PCI CMD.ID bit. The state of the CMD.ID bit does not affect MSI and MSI-X generation. This is shown the table below.

Table 12-4. Interaction Between INTx# and MSI

CMD.ID	MMC.MSIE/MXC.MXE	INTX# Assertion	MSI/MSI-X Generation
0	0	Yes	No
0	1	No	Yes
1	0	No	No
1	1	No	Yes

12.4.4 Power Management

The SATA Host Controller supports the PCI specification and the SATA PCI specification defined power states. See section 8 of the *Serial ATA Advanced Host Controller Interface (AHCI) Specification, Rev 1.3.1*. This controller also implements specific power management like clock and power gating.

Once BIOS enables the clock gating during the boot process, this is fully hardware autonomous and requires no software intervention.

12.4.5 Automatic Transition of Partial to Slumber

This feature is supported per the AHCI specification.

12.4.6 Enclosure Management and Activity LED

The Enclosure management is supported per the *Serial ATA Advanced Host Controller Interface (AHCI) Specification, Rev 1.3.1*. LED support is per the SFF 8485 specification.

The SAF-TE, SES-2 and SGPIO message formats are defined in the corresponding specifications.

Note: When SGPIO is enabled it will always send 8 ports worth of messages.

12.5 Register Map

Figure 12-2 shows the associated registers from a system software viewpoint.

Figure 12-2. Register Map



12.5.1 PCI Configuration and Capabilities

Table 12-5. Configuration and Capabilities Registers (Sheet 1 of 2)

CFG Address	Default	Instance Name	Name
0x0	1C02_8086h	ID	Identifiers
0x4	0000h	CMD	Command
0x6	02B0h	STS	Device Status
0x8	00h	RID	Revision ID
0x9	01h	PI	Programming Interface
0xA	0106h	CC	Class Code
0xC	00h	CLS	Cache Line Size
0xD	00h	MLT	Master Latency Timer
0xE	00h	HTYPE	Header Type
0x10	0000_0000h	MXTBA	MSI-X Table Base Address
0x14	0000_0000h	MXPBA	MXP Base Address
0x20	0000_0001h	AIDPBA	AHCI Index Data Pair Base Address
0x24	0000_0000h	ABAR	AHCI Base Address
0x2C	0000_0000h	SS	Sub System Identifiers
0x34	80h	CAP	Capabilities Pointer
0x3C	0100h	INTR	Interrupt Information
0x70	A801h	PID	PCI Power Management Capability ID
0x72	4003h	PC	PCI Power Management Capabilities
0x74	0008h	PMCS	PCI Power Management Control and Status
0x80	7005h	MID	Message Signaled Interrupt Identifier
0x82	0000h	MC	Message Signaled Interrupt Message Control
0x84	0000_0000h	MA	Message Signaled Interrupt Message Address
0x88	0000h	MD	Message Signaled Interrupt Message Data
0x90	0000_0000h	MAP	Port Mapping Register
0x94	0000_0000h	PCS	Port Control and Status
0x9C	0000_0000h	SATAGC	SATA General Configuration
0xA0	00h	SIRI	SATA Initialization Register Index
0xA4	0000_0000h	SIRD	SATA Initialization Register Data
0xA8	0010_0012h	SATACR0	Serial ATA Capability Register 0
0xAC	0000_0048h	SATACR1	Serial ATA Capability Register 1
0xB0	0013h	FLRCID	FLR Capability ID

Table 12-5. Configuration and Capabilities Registers (Sheet 2 of 2)

0xB2	0306h	FLRCAP	FLR Capability Length and Version
0xB4	0000h	FLRCTL	FLR Control
0xC0	0000_0000h	SP	Scratch Pad
0xD0	0011h	MXID	MSI-X Identifiers
0xD2	0000h	MXC	MSI-X Message Control
0xD4	0000_0000h	MXT	MSI-X Table Offset / Table BIR
0xD8	0000_0000h	MXP	MSI-X PBA Offset / PBA BIR
0xE0	0000_0000h	BFCS	BIST FIS Control/Status
0xE4	0000_0000h	BFTD1	BIST FIS Transmit Data 1
0xE8	0000_0000h	BFTD2	BIST FIS Transmit Data 2
0xF8	0800_0FB1h	MFID	Manufacturing ID

12.5.2 Memory-Mapped Registers

Table 12-6. Memory Mapped Registers (Sheet 1 of 5)

MEM Address	Default	Instance Name	Name
MEM BaseAddress: ABAR			
0x0	FF36_FF07h	GHC_CAP	HBA Capabilities
0x4	8000_0000h	GHC	Global HBA Control
0x8	0000_0000h	IS	Interrupt Status Register
0xC	0000_0000h	GHC_PI	Ports Implemented
0x10	0001_0300h	VS	AHCI Version
0x1C	0160_0002h	EM_LOC	Enclosure Management Location
0x20	0701_0000h	EM_CTL	Enclosure Management Control
0x24	0000_003Ch	GHC_CAP2	HBA Capabilities Extended
0xA0	0000_0048h	VSP	Vendor Specific
0xA4	0010_02DEh	VS_CAP	Vendor Specific Capabilities Register
0xC0	0031_1C02h	RPID	RAID Platform ID
0xC4	0000h	PFB	Premium Feature Block
0xC8	003Fh	SFM	SW Feature Mask
0x100	0000_0000h	PxCLB0	Port [0-7] Command List Base Address
0x104	0000_0000h	PxCLBU0	Port [0-7] Command List Base Address Upper 32-bits
0x108	0000_0000h	PxFB0	Port [0-7] FIS Base Address
0x10C	0000_0000h	PxFBU0	Port [0-7] FIS Base Address Upper 32-bits
0x110	0000_0000h	PxIS0	Port [0-7] Interrupt Status
0x114	0000_0000h	PxIE0	Port [0-7] Interrupt Enable
0x118	0000_0004h	PxCMD0	Port [0-7] Command
0x120	0000_007Fh	PxTFD0	Port [0-7] Task File Data
0x124	FFFF_FFFFh	PxSIG0	Port [0-7] Signature
0x128	0000_0000h	PxSSTS0	Port [0-7] Serial ATA Status
0x12C	0000_0000h	PxSCTL0	Port [0-7] Serial ATA Control
0x130	0000_0000h	PxSERR0	Port [0-7] Serial ATA Error
0x134	0000_0000h	PxSACT0	Port [0-7] Serial ATA Active
0x138	0000_0000h	PxCI0	Port [0-7] Commands Issued
0x13C	0000_0000h	PxSNTF0	Port [0-7] SNotification
0x144	1E02_2852h	PxDEVSLP0	Port [0-7] Device Sleep
0x180	0000_0000h	PxCLB1	Port [0-7] Command List Base Address

Table 12-6. Memory Mapped Registers (Sheet 2 of 5)

0x184	0000_0000h	PxCLBU1	Port [0-7] Command List Base Address Upper 32-bits
0x188	0000_0000h	PxFB1	Port [0-7] FIS Base Address
0x18C	0000_0000h	PxFBU1	Port [0-7] FIS Base Address Upper 32-bits
0x190	0000_0000h	PxIS1	Port [0-7] Interrupt Status
0x194	0000_0000h	PxIE1	Port [0-7] Interrupt Enable
0x198	0000_0004h	PxCMD1	Port [0-7] Command
0x1A0	0000_007Fh	PxTFD1	Port [0-7] Task File Data
0x1A4	FFFF_FFFFh	PxSIG1	Port [0-7] Signature
0x1A8	0000_0000h	PxSSTS1	Port [0-7] Serial ATA Status
0x1AC	0000_0000h	PxSCTL1	Port [0-7] Serial ATA Control
0x1B0	0000_0000h	PxSERR1	Port [0-7] Serial ATA Error
0x1B4	0000_0000h	PxSACT1	Port [0-7] Serial ATA Active
0x1B8	0000_0000h	PxCI1	Port [0-7] Commands Issued
0x1BC	0000_0000h	PxSNTF1	Port [0-7] SNotification
0x1C4	1E02_2852h	PxDEVSLP1	Port [0-7] Device Sleep
0x200	0000_0000h	PxCLB2	Port [0-7] Command List Base Address
0x204	0000_0000h	PxCLBU2	Port [0-7] Command List Base Address Upper 32-bits
0x208	0000_0000h	PxFB2	Port [0-7] FIS Base Address
0x20C	0000_0000h	PxFBU2	Port [0-7] FIS Base Address Upper 32-bits
0x210	0000_0000h	PxIS2	Port [0-7] Interrupt Status
0x214	0000_0000h	PxIE2	Port [0-7] Interrupt Enable
0x218	0000_0004h	PxCMD2	Port [0-7] Command
0x220	0000_007Fh	PxTFD2	Port [0-7] Task File Data
0x224	FFFF_FFFFh	PxSIG2	Port [0-7] Signature
0x228	0000_0000h	PxSSTS2	Port [0-7] Serial ATA Status
0x22C	0000_0000h	PxSCTL2	Port [0-7] Serial ATA Control
0x230	0000_0000h	PxSERR2	Port [0-7] Serial ATA Error
0x234	0000_0000h	PxSACT2	Port [0-7] Serial ATA Active
0x238	0000_0000h	PxCI2	Port [0-7] Commands Issued
0x23C	0000_0000h	PxSNTF2	Port [0-7] SNotification
0x244	1E02_2852h	PxDEVSLP2	Port [0-7] Device Sleep
0x280	0000_0000h	PxCLB3	Port [0-7] Command List Base Address
0x284	0000_0000h	PxCLBU3	Port [0-7] Command List Base Address Upper 32-bits

Table 12-6. Memory Mapped Registers (Sheet 3 of 5)

0x288	0000_0000h	PxFB3	Port [0-7] FIS Base Address
0x28C	0000_0000h	PxFBU3	Port [0-7] FIS Base Address Upper 32-bits
0x290	0000_0000h	PxIS3	Port [0-7] Interrupt Status
0x294	0000_0000h	PxIE3	Port [0-7] Interrupt Enable
0x298	0000_0004h	PxCMD3	Port [0-7] Command
0x2A0	0000_007Fh	PxTFD3	Port [0-7] Task File Data
0x2A4	FFFF_FFFFh	PxSIG3	Port [0-7] Signature
0x2A8	0000_0000h	PxSSTS3	Port [0-7] Serial ATA Status
0x2AC	0000_0000h	PxSCTL3	Port [0-7] Serial ATA Control
0x2B0	0000_0000h	PxSERR3	Port [0-7] Serial ATA Error
0x2B4	0000_0000h	PxSACT3	Port [0-7] Serial ATA Active
0x2B8	0000_0000h	PxCI3	Port [0-7] Commands Issued
0x2BC	0000_0000h	PxSNTF3	Port [0-7] SNotification
0x2C4	1E02_2852h	PxDEVSLP3	Port [0-7] Device Sleep
0x300	0000_0000h	PxCLB4	Port [0-7] Command List Base Address
0x304	0000_0000h	PxCLBU4	Port [0-7] Command List Base Address Upper 32-bits
0x308	0000_0000h	PxFB4	Port [0-7] FIS Base Address
0x30C	0000_0000h	PxFBU4	Port [0-7] FIS Base Address Upper 32-bits
0x310	0000_0000h	PxIS4	Port [0-7] Interrupt Status
0x314	0000_0000h	PxIE4	Port [0-7] Interrupt Enable
0x318	0000_0004h	PxCMD4	Port [0-7] Command
0x320	0000_007Fh	PxTFD4	Port [0-7] Task File Data
0x324	FFFF_FFFFh	PxSIG4	Port [0-7] Signature
0x328	0000_0000h	PxSSTS4	Port [0-7] Serial ATA Status
0x32C	0000_0000h	PxSCTL4	Port [0-7] Serial ATA Control
0x330	0000_0000h	PxSERR4	Port [0-7] Serial ATA Error
0x334	0000_0000h	PxSACT4	Port [0-7] Serial ATA Active
0x338	0000_0000h	PxCI4	Port [0-7] Commands Issued
0x33C	0000_0000h	PxSNTF4	Port [0-7] SNotification
0x344	1E02_2852h	PxDEVSLP4	Port [0-7] Device Sleep
0x380	0000_0000h	PxCLB5	Port [0-7] Command List Base Address
0x384	0000_0000h	PxCLBU5	Port [0-7] Command List Base Address Upper 32-bits
0x388	0000_0000h	PxFB5	Port [0-7] FIS Base Address

Table 12-6. Memory Mapped Registers (Sheet 4 of 5)

0x38C	0000_0000h	PxFBU5	Port [0-7] FIS Base Address Upper 32-bits
0x390	0000_0000h	PxIS5	Port [0-7] Interrupt Status
0x394	0000_0000h	PxIE5	Port [0-7] Interrupt Enable
0x398	0000_0004h	PxCMD5	Port [0-7] Command
0x3A0	0000_007Fh	PxTFD5	Port [0-7] Task File Data
0x3A4	FFFF_FFFFh	PxSIG5	Port [0-7] Signature
0x3A8	0000_0000h	PxSSTS5	Port [0-7] Serial ATA Status
0x3AC	0000_0000h	PxSCTL5	Port [0-7] Serial ATA Control
0x3B0	0000_0000h	PxSERR5	Port [0-7] Serial ATA Error
0x3B4	0000_0000h	PxSACT5	Port [0-7] Serial ATA Active
0x3B8	0000_0000h	PxCI5	Port [0-7] Commands Issued
0x3BC	0000_0000h	PxSNTF5	Port [0-7] SNotification
0x3C4	1E02_2852h	PxDEVSLP5	Port [0-7] Device Sleep
0x400	0000_0000h	PxCLB6	Port [0-7] Command List Base Address
0x404	0000_0000h	PxCLBU6	Port [0-7] Command List Base Address Upper 32-bits
0x408	0000_0000h	PxFB6	Port [0-7] FIS Base Address
0x40C	0000_0000h	PxFBU6	Port [0-7] FIS Base Address Upper 32-bits
0x410	0000_0000h	PxIS6	Port [0-7] Interrupt Status
0x414	0000_0000h	PxIE6	Port [0-7] Interrupt Enable
0x418	0000_0004h	PxCMD6	Port [0-7] Command
0x420	0000_007Fh	PxTFD6	Port [0-7] Task File Data
0x424	FFFF_FFFFh	PxSIG6	Port [0-7] Signature
0x428	0000_0000h	PxSSTS6	Port [0-7] Serial ATA Status
0x42C	0000_0000h	PxSCTL6	Port [0-7] Serial ATA Control
0x430	0000_0000h	PxSERR6	Port [0-7] Serial ATA Error
0x434	0000_0000h	PxSACT6	Port [0-7] Serial ATA Active
0x438	0000_0000h	PxCI6	Port [0-7] Commands Issued
0x43C	0000_0000h	PxSNTF6	Port [0-7] SNotification
0x444	1E02_2852h	PxDEVSLP6	Port [0-7] Device Sleep
0x480	0000_0000h	PxCLB7	Port [0-7] Command List Base Address
0x484	0000_0000h	PxCLBU7	Port [0-7] Command List Base Address Upper 32-bits
0x488	0000_0000h	PxFB7	Port [0-7] FIS Base Address
0x48C	0000_0000h	PxFBU7	Port [0-7] FIS Base Address Upper 32-bits

Table 12-6. Memory Mapped Registers (Sheet 5 of 5)

0x490	0000_0000h	PxIS7	Port [0-7] Interrupt Status
0x494	0000_0000h	PxIE7	Port [0-7] Interrupt Enable
0x498	0000_0004h	PxCMD7	Port [0-7] Command
0x4A0	0000_007Fh	PxTFD7	Port [0-7] Task File Data
0x4A4	FFFF_FFFFh	PxSIG7	Port [0-7] Signature
0x4A8	0000_0000h	PxSSTS7	Port [0-7] Serial ATA Status
0x4AC	0000_0000h	PxSCTL7	Port [0-7] Serial ATA Control
0x4B0	0000_0000h	PxSERR7	Port [0-7] Serial ATA Error
0x4B4	0000_0000h	PxSACT7	Port [0-7] Serial ATA Active
0x4B8	0000_0000h	PxCI7	Port [0-7] Commands Issued
0x4BC	0000_0000h	PxSNTF7	Port [0-7] SNotification
0x4C4	1E02_2852h	PxDEVSLP7	Port [0-7] Device Sleep
0x580	0000_0000h	EM_MF	Enclosure Management Message Format
0x584	0000_0000h	EM_LED	Enclosure Management LED
MEM BaseAddress: MXTBA			
0x0	0000_0000h	MXTEnMLA	MSI-X Table Entries 0 Message Lower Address
0x4	0000_0000h	MXTEnMUA	MSI-X Table Entries 0 Message Upper Address
0x8	0000_0000h	MXTEnMD	MSI-X Table Entries 0 Message Data
0xC	0000_0001h	MXTEnVC	MSI-X Table Entries 0 Vector Control
MEM BaseAddress: MXPBA			
0x0	0000_0000h	MXPQW0_DW0	MSI-X Pending Bit Array QW 0
0x4	0000_0000h	MXPQW0_DW1	MSI-X Pending Bit Array QW 1

12.5.3 I/O-Mapped Registers

Table 12-7. I/O Mapped Registers

IO Address	Default	Instance Name	Name
IO BaseAddress: AIDPBA			
0x10	0000_0000h	INDEX	AHCI Index Register
0x14	0000_0000h	DATA	AHCI Data Register

§ §

13 LAN Controllers

There are two SoC LAN controllers (LAN0 and LAN1) with two ports each, providing a total of four ports. Each port contains an independent LAN Media Access Control (MAC) that supports a XGMII-like interface link to an internal PHY (see Figure 13-1).

The internal MAC/PHY combine to support 1GbE (KX and SGMII), 2.5GbE and 10GbE operation through various modes of operation.

Refer to Section 13.2, "Supported Modes of Operation" on page 415 for all supported modes of Ethernet for use with internal PHYs (native support) and external PHYs.

Figure 13-1. What is Covered in This Chapter



Table 13-1. References

Reference	Revision	Date	Document Title
DMTF	1.0	May 2009	*DMTF Network Controller Sideband Interface (NC-SI) Specification)*
IEEE			*IEEE 1149.6 standard for Boundary Scan* (MDI pins excluded)
IEEE			*IEEE 802.3-2012*, Clauses 70 through 74.
IEEE		2001	*IEEE standard 1149.1*, 2001 Edition (JTAG). Institute of Electrical and Electronics Engineers (IEEE).
IEEE			*IEEE standard 802*.1Q for VLAN
IEEE		September 2004	*IEEE 1588*, International Standard, Precision clock synchronization protocol for networked measurement and control systems (1588V1/1588V2)
IEEE		January 19, 2006	*IEEE P802.1AE/D5.1*, Media Access Control (MAC) Security
IEEE			*IEEE 802.3-2012*, Clause 78
IETF			*IETF IPv4 Specification*, (RFC 791)
IETF			*IETF IPv6 Specification*, (RFC 2460)
IETF			*IETF TCP Specification*, (RFC 793)
IETF			*IETF UDP Specification*, (RFC 768)
IETF			*IETF ARP Specification*, (RFC 826)
PCI-SIG			*PCI Express Base Specification*, Revision 3.0
PCI-SIG	1.2	March 2004	*PCI Bus Power Management Interface Specification*, Revision 1.2
PCI-SIG	2.0		PICMG 3.1
PCI-SIG	1.1	September 8, 2009	*PCI Single Root I/O Virtualization and Sharing Specification*
SMBus	2.0	August 2000	*System Management Bus (SMBus) Specification*, SBS Implementers Forum

13.1 Signal Descriptions

The signal descriptions are shown in Table 13-2, "Signal Names and Descriptions". For additional signal information, including whether a signal is assigned to a shared-function pin or can be used as a Customer GPIO signal see Section 39.1, "Directory of Signal Names and Pin Names". The Direction/Type column of Table 13-2, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.
- Differential = Differential signal pair. Two pins: Positive; Negative.

Table 13-2. Signal Names and Descriptions (Sheet 1 of 3)

Signal Names	Direction	Shared	Description
LAN Ports 0 and 1 - LAN Controller 0			
LAN0_PORT0_I2C_CLK	I,O-OD	Yes	**I^2C Clock:** The 2-wire management interface Clock used to access the management registers of an external optical module of port n. One clock pulse is generated for each data bit transferred.
LAN0_PORT0_I2C_DATA	I,O-OD	Yes	**I^2C Data:** The Data of the 2-wire management interface used to access the management registers of an external optical module of port n. Stable during the clock high period (unless it is a start or stop condition).
LAN0_PORT0_LED[3:0]	O-OD	Yes	**LED Drivers:** Four LED drivers for this LAN Port.
LAN0_PORT0_SDP[3:0]	I,O	Yes	**Software Defined Pins:** Four general-purpose SDPs for this LAN Port, can be used to support IEEE1588 auxiliary devices or input for external interrupts.
LAN0_PORT0_RX_DP LAN0_PORT0_RX_DN	I, Differential	No	**PHY Differential Input:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G and SFI.
LAN0_PORT0_TX_DP LAN0_PORT0_TX_DN	O, Differential	No	**PHY Differential Output:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G and SFI.
LAN0_PORT1_I2C_CLK	I,O-OD	Yes	**I^2C Clock:** The 2-wire management interface Clock used to access the management registers of an external optical module of port n. One clock pulse is generated for each data bit transferred.
LAN0_PORT1_I2C_DATA	I,O-OD	Yes	**I^2C Data:** The Data of the 2-wire management interface used to access the management registers of an external optical module of port n. Stable during the high period of the clock (unless it is a start or stop condition).
LAN0_PORT1_LED[1:0]	O-OD	Yes	**LED Drivers:** Two LED drivers for this LAN Port.
LAN0_PORT1_SDP[3:0]	I,O	Yes	**Software Defined Pins:** Four general-purpose SDPs for this LAN Port. Can be used to support IEEE1588 auxiliary devices or input for external interrupts.
LAN0_PORT1_RX_DP LAN0_PORT1_RX_DN	I	No	**PHY Differential Input:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G,100 Mb/s full duplex, 10 Mb/s full duplex, and SFI.
LAN0_PORT1_TX_DP LAN0_PORT1_TX_DN	O	No	**PHY Differential Output:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G,100 Mb/s full duplex, 10 Mb/s full duplex, and SFI.
LAN0_RBIAS	I,O	No	**Bias Resistor:** External resistor bias input. The platform board must provide a 1000 Ω, 0.10% resistor connected from this pin to VCCKR0LCPLL_LV. Intel recommends shielding the trace to this pin.

Table 13-2. Signal Names and Descriptions (Sheet 2 of 3)

Signal Names	Direction	Shared	Description
LAN Ports 0 and 1 - LAN Controller 1			
LAN1_PORT0_I2C_CLK	I,O-OD	Yes	**I²C Clock:** The Clock of the 2-wire management interface used to access the management registers of an external optical module of port n. One clock pulse is generated for each data bit transferred.
LAN1_PORT0_I2C_DATA	I,O-OD	Yes	**I²C Data:** The Data of the 2-wire management interface used to access the management registers of an external optical module of port n. Stable during the high period of the clock (unless it is a start or stop condition).
LAN1_PORT0_LED[1:0]	O-OD	Yes	**LED Drivers:** Two LED drivers for this LAN Port.
LAN1_PORT0_SDP[1:0]	I,O	Yes	**Software Defined Pins:** Two general-purpose SDPs for this LAN Port. Can be used to support IEEE1588 auxiliary devices or input for external interrupts.
LAN1_PORT0_RX_DP LAN1_PORT0_RX_DN	I, Differential	No	**PHY Differential Input:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G and SFI.
LAN1_PORT0_TX_DP LAN1_PORT0_TX_DN	O, Differential	No	**PHY Differential Output:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G and SFI.
LAN1_PORT1_I2C_CLK	I,O-OD	Yes	**I²C Clock:** The Clock of the 2-wire management interface used to access the management registers of an external optical module of port n. One clock pulse is generated for each data bit transferred.
LAN1_PORT1_I2C_DATA	I,O-OD	Yes	**I²C Data:** 2-wire management interface data used to access the management registers of an external optical module of port n. Stable during high period of clock (unless it is a start or stop condition).
LAN1_PORT1_LED[1:0]	O-OD	Yes	**LED Drivers:** Two LED drivers for this LAN Port.
LAN1_PORT1_SDP[1:0]	I,O	Yes	**Software Defined Pins:** Two general-purpose SDPs for this LAN Port, can be used to support IEEE1588 auxiliary devices or input for external interrupts.
LAN1_PORT1_RX_DP LAN1_PORT1_RX_DN	I, Differential	No	**PHY Differential Input:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G and SFI.
LAN1_PORT1_TX_DP LAN1_PORT1_TX_DN	O, Differential	No	**PHY Differential Output:** This lane is used in 10GBASE-KR, 1000BASE-KX, 2.5G and SFI.
LAN1_RBIAS	I,O	No	**Bias Resistor:** External resistor bias input. The platform board must provide a 1000 Ω, 0.10% resistor connected from this pin to VCCKR1LCPLL_LV. Intel recommends shielding the trace to this pin.
Signals Common to LAN Controllers 0 and 1			
LAN_MDC	O	Yes	**Management Clock:** Clock output for accessing the external PHYs management registers.
LAN_MDIO	I,O-OD	Yes	**Management Data:** Bi-directional signal for serial data transfers between MAC and the external PHY.
SMB_LAN_DATA	I,O-OD	Yes	**SMBus Data:** Stable during the high period of the clock (unless it is a start or stop condition).
SMB_LAN_CLK	I,O-OD	Yes	**SMBus Clock:** One clock pulse is generated per data bit transferred.
SMB_LAN_ALRT_N	I,O-OD	Yes	**SMBus Alert:** Acts as an interrupt pin of a slave device on the SMBus.
NCSI_ARB_IN	I	Yes	**NC-SI Arbitration In:** Along with NCSI_ARB_OUT, this signal provides hardware-based arbitration when multiple Network Controllers are used. The SoC provides an internal 20-kΩ pull-down resistor.
NCSI_ARB_OUT	O	Yes	**NC-SI Arbitration Out:** Along with NCSI_ARB_IN, this signal provides hardware-based arbitration when multiple Network Controllers are used.

Table 13-2. Signal Names and Descriptions (Sheet 3 of 3)

Signal Names	Direction	Shared	Description
Signals Common to LAN Controllers 0 and 1 (continued)			
NCSI_CLK_IN	I	Yes	**NC-SI Reference Clock Input:** Synchronous clock reference for receive, transmit, and control interface. It is a 50 MHz clock ±100 ppm. The SoC provides an internal 20-kΩ pull-up resistor.
NCSI_CRS_DV	O-Tri	Yes	**Carrier Sense/Receive Data Valid:** Tri-state output signal to the MC. Indicates that the data transmitted from the SoC to the MC is valid. If this signal is used, the platform board must provide a pull-up resistor when the output signal is in the high-impedance state.
NCSI_RXD[1:0]	O-Tri	Yes	**MC Receive Data:** Tri-state output data signals from the SoC LAN controllers to the MC. The SoC provides an internal 20-kΩ pull-up resistor for each output signal.
NCSI_TX_EN	I	Yes	**MC Transmit Enable:** Indicates received data from the MC is valid.
NCSI_TXD[1:0]	I	Yes	**MC Transmit Data:** Data signals from the MC to the SoC LAN controllers.

Note: The SoC LAN controllers only have one SMBus and one NC-SI bus associated with all LAN ports. Both the SMBus and NC-SI can be used simultaneously by the platform board design provided that both sets of signals are configured.

13.2 Supported Modes of Operation

The SoC LAN controllers support speeds of 2.5 GbE[1], 1 GbE, and 10 GbE, as well as 10/100 Mb/s in only full-duplex mode.

There are two SoC LAN controllers (LAN0 and LAN1) with two ports each, providing a total of four ports.

LAN Controller 0 will be enabled for product SKU that only has two ports.

For product SKU with LAN controller 0 and LAN controller 1 if SOC Ethernet is used LAN controller 0 must be enabled.

For each port, there are options to use internal PHYs supporting:

- 10GBASE-KR
- SFI
- 1000BASE-KX
- 2500BASE-X

There are also options to connect to external PHYs via:

- 10GBASE-KR
- 1000BASE-KX
- SGMII is supported for Full Duplex 10 Mb/s, 100 Mb/s and 1 GbE

Each integrated I/O interface block provides the following physical interfaces and electrical modes:

- 10GbE PHY supports:
  - 10GBASE-KR for backplane applications (IEEE802.3 clause 72)
  - 10GBASE-KR FEC (IEEE 802.3 Clause 74)
  - 1000BASE-KX for backplane applications (IEEE802.3 clause 70)
  - Auto-negotiation for backplane Ethernet (IEEE 802.3 Clause 73)
  - SFI compatible interface to: SFP+[2] (SFF8431)
  - KR to 10GBASE-T PHY (Intel® X557-AT2/AT4 LAN PHY)

Note: No support for BASE-T SFP modules.

Note: No support for half duplex at 10 Mb/s, 100 Mb/s, 1 GbE, 2.5 GbE or 10 GbE.

Note: LAN port topologies must be the same for each respective LAN, for example, Ports 0 and 1 of LAN0 must be the same Ethernet mode. However, LAN 0 and LAN 1 can support different topologies as long as care is given to the trace layout. Due to the cross-talk requirements, there is no mixing of DAC (Direct-Attached-Cable) and Optical modules on ports 0 and 1 of the same LAN when using an SFI (native) design.

1. Auto-negotiation is not supported in 2.5 GbE. Auto-negotiate is supported in all other modes.
2. Some system designs might require adding a InPhi* CS4227(dual port)/CS4223 (quad port) re-timer PHY between the SoC and the SFP+ module see Table 13-3, "Supported System Configurations".

Table 13-3, "Supported System Configurations" lists all the supported system configurations, operating modes, and link partners for the LAN controllers. Selecting the desired PHY and system configuration is determined at power on through the use of the shared SPI Flash configuration.

Table 13-3. Supported System Configurations

Connection	Speed	Electrical Interface	Third Party PHYs/Switches[4]
Backplane	1 GbE	1000BASE-KX	Intel® FM4000/FM5000/FM6000 Ethernet switches Broadcom* BCM5684x-series switches
Backplane	10 GbE	10GBASE-KR	Intel FM5000/FM6000 Ethernet switches Broadcom* BCM5684x-series switches
Backplane	2.5 GbE	2500BASE-X [1]	Intel FM4000/FM5000/FM6000 Ethernet switches Broadcom* BCM5684x-series switches
10BASE-T 100BASE-TX 1000BASE-T	10 Mb/s 100 Mb/s 1 GbE	SGMII (no half duplex support)	Marvell* 88E1514/88E1512 [5] Marvell 88E1543
10GBASE-T [7]	10 GbE	KR	Intel® X557-AT2/AT4 10 GbE PHY
1000BASE-T [7]	1 GbE	KX	Intel® X557-AT2/AT4 10 GbE PHY
SFP+ [7]	10 GbE	SFI	Native SFI support
SFP+ [7]	10 GbE	KR [3]	Inphi CS4227 (2 port) [6] Inphi CS4223 (4 port) [6]

Notes:
1. 2500BASE-X is not an IEEE standard. The SoC supports 2.5G rate only.
2. No support for half duplex.
3. Inphi devices required for long reach support in KR mode.
4. XFP+ devices are not supported and should not be used as they may impact the reliability of the LAN port.
5. The 88E1512 and 88E1514 only supports two MDIO addresses (0 or 1) therefore a maximum of 2 of these PHY devices can be used with each SoC.
6. CS422X devices include integrated Rx CAPS. DO NOT include 100nF for Rx traces close to the devices.
7. Supported only in 10G capable LAN controller SKU.

13.3 Feature List

Table 13-4. Network Features

Feature	SoC LAN Controllers	82599
Compliant with the 1 Gb/s Ethernet/802.3 (KX) Specification	Y	Y
Compliant with the 10 Gb/s 802.3 (KR) specification	Y	Y
Support of 10GBASE-KR FEC	Y	Y
Full-Duplex Operation at all Supported Speeds	Y	N
802.3az Energy Efficient Ethernet (EEE) Support	N	N
Support Jumbo Frames of up to 15.5 KB	Y [1]	Y [1]
MDIO Interface Clause 45	Y	N
Flow Control Support: Send/Receive Pause Frames and Receive FIFO Thresholds	Y	Y
Statistics for Management and RMON	Y	Y
802.1q VLAN Support	Y	Y
Double VLAN	Y	Y

1. The SoC LAN controllers support full-size 15.5 KB jumbo packets while in a basic mode of operation. When virtualization is enabled, or OS2BMC is enabled, then the SoC LAN controllers supports 9.5 KB jumbo packets. Packets to/from the MC longer than 2 KB are filtered out.

Table 13-5. Host Interface Features

Feature	SoC LAN Controllers	82599
Integrated I/O	Y	N
64-bit Address Support for Systems Using More Than 4 GB of Physical Memory	Y	Y
Outstanding Requests for Tx Data Buffers	16	16
Outstanding Requests for Tx Descriptors	8	8
Outstanding Requests for Rx Descriptors	8	8
Credits for P-H/P-D/NP-H/NP-D (shared for the two ports)	4/255/4/255 [1]	16/16/4/4
Credits for C-H/C-D (shared for the two ports)	4/255	N
Max Payload Size Supported	64 - 512 bytes	512 bytes
Max Request Size Supported	64B	2 KB
Vital Product Data (VPD)	Y	Y
End to End CRC (ECRC)	N/A	Y
Latency Tolerance Reporting (LTR)	N	N
ID-Based Ordering (IDO)	Y	N
Access Control Services (ACS)	Y	N
PCIe Functions Off through BIOS Control While LAN Ports Are On	Y	N

1. Each data credit accounts for 16 bytes.

Table 13-6. Miscellaneous Features

Feature	SoC LAN Controllers	82599
Serial Flash Interface	N [1]	Y
Configurable LED Operation for Software or OEM Customization of LED Displays	Y	Y
Shared SPI Flash Space for Private Configuration	Y	Y
Device Disable Capability	Y	Y
Watchdog Timer	Y	Y
Time Sync (IEEE 1588 v2)	Y	Y

1. Serial Flash interface is available at the SoC level and is shared among all the integrated devices.

Table 13-7. LAN Functions Features

Feature	SoC LAN Controllers	82599
Programmable Host Memory Receive Buffers	Y	Y
Descriptor Ring Management Hardware for Transmit and Receive	Y	Y
ACPI Register Set and Power Down Functionality Supporting D0 and D3 States	Y	Y
Software-Controlled Global Reset Bit (Resets Everything Except the Configuration Registers)	Y	Y
Software-Definable Pins (SDP) (per port)	2 [1]	8
SDP Pins Can Be Configured as General Purpose Interrupts	Y	Y
Wake on LAN (WoL)	Y	Y
IPv6 Wake-up Filters	Y	Y
Configurable (through shared SPI Flash update) Wake-up Flexible Filters	Y	Y
Default Configuration by shared SPI Flash update for all LEDs for Pre-Driver Functionality	Y	Y
LAN Function Disable Capability	Y	Y
Programmable Memory Transmit Buffers	160 KB / port	160 KB / port
Programmable Memory Receive Buffers	384 KB / port	512 KB / port

1. Available number is dependent on I/O MUXing and selected functionality.

Table 13-8. LAN Performance Features

Feature	SoC LAN Controllers	82599
TCP/UDP Segmentation Offload	256 KB in all modes	256 KB in all modes
TSO Interleaving for Reduced Latency	Y	Y
TCP Receive Side Coalescing (RSC)	32 flows / port	32 flows / port
Rate Limit VM Tx Traffic per TC (i.e. per TxQ)	Y	N
IPv6 Support for IP/TCP and IP/UDP Receive Checksum Offload	Y	Y
Fragmented UDP Checksum Offload for Packet Reassembly	Y	Y
Message Signaled Interrupts (MSI)	Y	Y
Message Signaled Interrupts (MSI-X)	Y	Y
Interrupt Throttling Control to Limit Maximum Interrupt Rate and Improve CPU Use	Y	Y
Rx Packet Split Header	Y	Y
Multiple Rx Queues (RSS)	Y (multiple modes)	Y (multiple modes)
Flexible RSS	N	N
Flow Director Filters: up to 32 KB Flows by Hash Filters or up to 8 KB Perfect Match Filters	Y	Y
Number of Rx Queues (per port)	128	128
Number of Tx Queues (per port)	128	128
TCP Timer Interrupts Relax Ordering	Y Y	Y Y
DMA Coalescing	Y	N

Table 13-9. Virtualization Features

Feature	SoC LAN Controllers	82599
Support for Virtual Machine Device Queues (VMDq1 and Next Generation VMDq)	64	64
L2 Ethernet MAC Address Filters (Unicast and Multicast)	128	128
L2 VLAN Filters	64	64
PCI-SIG SR IOV	Y	Y
Multicast and Broadcast Packet Replication	Y	Y
Packet Mirroring	Y	Y
Packet Loopback	Y	Y
Traffic Shaping	Y	Y
Anti Spoof	MAC, VLAN, Ethertype	N
Forwarding Modes	MAC, VLAN E-tag	N
VEB Support	Y	N

Table 13-10. Manageability Features

Feature	SoC LAN Controllers	82599
Advanced Pass Through-compatible Management Packet Transmit/Receive Support	Y	Y
SMBus Interface to an External MC	Y	Y
New Management Protocol Standards Support (NC-SI) Interface to an External MC	Y	Y
L2 Address Filters	4	4
VLAN L2 Filters	8	8
Flex L3 Port Filters	16	16
Flexible TCO Filters	1	4
L3 Address Filters (IPv4)	4	4
L3 Address Filters (IPv6)	4	4
Host-Based Application-to-BMC Network Communication Patch (OS2BMC)	Y	N
Flexible MAC Address	Y	N
MC Inventory of LOM Device Information	Y	N
iSCSI Boot Configuration Parameters via MC	Y	N
MC Monitoring	Y	N
NC-SI to MC	Y	N
NC-SI Arbitration	Y	N
NC-SI Package ID Via SDP Pins	Y	N
NC-SI Flow Control	Y	N
MCTP over SMBus (pass through and control)	Y	N

13.4 Programmers Reference Manual

Much of the programming-related information and register descriptions for the SoC LAN controllers are in a separate document.

The descriptions of the MMIO registers and MSI-X registers located in memory space, the registers in I/O space, and the contents of the Shared NVM are described in the PRM. The SoC LAN controller registers located in PCI configuration space are provided in both the PRM and this document.

13.5 Architectural Overview

The SoC LAN controllers are a derivative of Intel® Ethernet Controller 82599 and largely supports most feature sets of this document.

Figure 13-2. System Architecture and Interface



Note: 10GbE PHY shown in Figure 13-2, "System Architecture and Interface" are internal to the SoC package.

13.5.1 PCIe Integrated Endpoint

From a systems view, the SoC LAN controllers are a PCIe* integrated endpoint consisting of two devices with two functions. Two independent controllers (LAN0 and LAN1), are connected to PCI Root Port with separate device and function numbers. LAN0 is connected to RP (D:22 F:0) 22 decimal while LAN1 is connected to RP (D:23 F:0) 23 decimal. Both ports on each controller are addressable by function 0 and 1.

SoC LAN controllers are highly configurable. Device IDs for each of the four functions are assigned, and its capabilities are enabled/disabled by data contained in the shared SPI Flash device. Configurable PCI and PCIe capabilities, and their offsets from the start of each capability location in PCI configuration space are listed in Table 13-11, "PCI and PCIe Capabilities Supported".

The LAN controllers are not connected through a standard PCIe bus. Though the LAN controllers appear as PCIe endpoints, and reports Gen1 speed and x1 width, the internal connection is not standard, and has much higher performance.

Table 13-11. PCI and PCIe Capabilities Supported

Offset in Configuration Space (hexadecimal)	Type of Capability	Capability
40	PCI	PCI Power Management Interface (PMI)
50	PCI	Message Signaled Interrupts (MSI)
70	PCI	Message Signaled Interrupts, extended (MSI-X)
A0	PCI	PCI Express Capability
E0	PCI	Vital Product Data (VPD)
100	PCI Express Extended	Advanced Error Reporting (AER)
140	PCI Express Extended	Device Serial Number
1B0	PCI Express Extended	Access Control Services (ACS)

Note: The dummy function device ID that is available on some Intel LAN components is not supported by the SoC.

Each of the four functions has six Base Address Registers (BARs) that are assigned address values during PCI bus enumeration. See Table 13-12, "Base Address Registers".

Table 13-12. Base Address Registers

Offset in Configuration Space (hexadecimal)	32-bit Register Name	Capability	Data Bytes Accessible in Given Space
10	BASE_ADDR_0	64-bit BAR for Memory Space for Memory-Mapped I/O (MMIOs)	128 K
14	BASE_ADDR_1		
18	BASE_ADDR_2	32-bit BAR for I/O Space	32
1C	BASE_ADDR_3	Reserved	
20	BASE_ADDR_4	64-bit BAR for Memory Space for Message Signaled Interrupts, extended (MSI-X)	16 K
24	BASE_ADDR_5		

There are two device-specific registers located in configuration space for each function. They provide one of the two possible methods for accessing the SoC LAN controller internal command and status registers. This first method uses PCI configuration space of each of the four functions:

- 0x98 - IOADDR (32 bits)
- 0x9C - IODATA (32 bits)

The other method uses the system I/O space. Once the BASE_ADDR_2 BAR is enumerated for a particular function, it can be used to access the IOADDR and IODATA registers:

- BASE_ADDR_2 (I/O base address) plus 0 - IOADDR (32 bits)
- BASE_ADDR_2 (I/O base address) plus 4 - IODATA (32 bits)

Note: There are many configuration options that affect the parameter assignments and operation of the SoC LAN controllers. This document only provides an overview and does not show all possibilities available to the SoC customer.

13.5.2 Interconnect Interfaces

The following interconnect interfaces are described in Section 13.7, "Interconnects":

- LED
- Software-Defined Pins (SDP)
- Shared SPI Flash
- MDIO
- I^2C
- SMBus
- NC-SI
- Memory-mapped I/O (MMIO)

13.6 Basic Operation

13.6.1 Transmit (Tx) Data Flow

Tx data flow provides a high-level description of all data/control transformation steps needed for sending Ethernet packets over the wire.

Table 13-13. Tx Data Flow

Step	Description
1	The host creates a descriptor ring and configures one of the LAN controllers transmit queues with the address location, length, head, and tail pointers of the ring (one of 128 available Tx queues).
2	The host is requested by the TCP/IP stack to transmit a packet, it gets the packet data within one or more data buffers.
3	The host initializes the descriptor(s) that point to the data buffer(s) and have additional control parameters that describes the needed hardware functionality. The host places that descriptor in the correct location at the appropriate Tx ring.
4	The host updates the appropriate Queue Tail Pointer (TDT).
5	The LAN controllers DMA senses a change of a specific TDT and as a result sends a PCIe request, over the primary integrated I/O interface bus, to fetch the descriptor(s) from host memory.
6	The descriptor(s) content is received in a PCIe read completion, over the primary integrated I/O interface bus, and is written to the appropriate location in the descriptor queue.
7	The DMA fetches the next descriptor and processes its content. As a result, the DMA sends PCIe requests, over the primary integrated I/O interface bus, to fetch the packet data from system memory.
8	The packet data is being received from PCIe completions, over the primary integrated I/O interface bus, and passes through the transmit DMA that performs all programmed data manipulations (various CPU offloading tasks as checksum offload, TSO offload, etc.) on the packet data on the fly.
9	While the packet is passing through the DMA, it is stored into the transmit FIFO. After the entire packet is stored in the transmit FIFO, it is then forwarded to transmit switch module.
10	The transmit switch arbitrates between host and management packets and eventually forwards the packet to the MAC
11	The MAC appends the L2 CRC to the packet and delivers the packet to the integrated PHY.
12	The PHY performs the PCS encoding, scrambling and the other manipulations required to deliver the packet over the physical interface at the selected speed.
13	When all the PCIe completions for a given packet are complete, the DMA updates the appropriate descriptor(s).
14	The descriptors are written back to host memory, over the primary integrated I/O interface bus, using PCIe posted writes. The head pointer is updated in host memory as well.
15	An interrupt is generated to notify the host driver that the specific packet has been read to the LAN controllers and the driver can then release the buffer(s).

13.6.2 Receive (Rx) Data Flow

Rx data flow provides a high-level description of all data/control transformation steps needed for receiving Ethernet packets.

Table 13-14. Rx Data Flow

Step	Description
1	The host creates a descriptor ring and configures one of the LAN controllers receive queues with the address location, length, head, and tail pointers of the ring (one of 128 available Rx queues).
2	The host initializes descriptor(s) that point to empty data buffer(s). The host places these descriptor(s) in the correct location at the appropriate Rx ring.
3	The host updates the appropriate Queue Tail Pointer (RDT).
4	A packet enters the PHY through the physical interface.
5	The PHY performs the required manipulations on the incoming signal de-scrambling, PCS decoding, etc.
6	The PHY delivers the packet to the Rx MAC.
7	The MAC forwards the packet to the Rx filter.
8	If the packet matches the pre-programmed criteria of the Rx filtering, it is forwarded to an Rx FIFO.
9	The receive DMA fetches the next descriptor from the appropriate host memory ring to be used for the next received packet.
10	After the entire packet is placed into an Rx FIFO, the receive DMA posts the packet data to the location indicated by the descriptor through the primary integrated I/O interface bus. If the packet size is greater than the buffer size, more descriptor(s) are fetched and their buffers are used for the received packet.
11	When the packet is placed into host memory, the receive DMA updates all the descriptor(s) that were used by the packet data.
12	The receive DMA writes back the descriptor content along with status bits that indicate the packet information including what offloads were done on that packet.
13	The LAN controllers initiates an interrupt to the host to indicate that a new received packet is ready in host memory.
14	The host reads the packet data and sends it to the TCP/IP stack for further processing. The host releases the associated buffer(s) and descriptor(s) once they are no longer in use.

13.7 Interconnects

13.7.1 Setting Up PCI Device Presence and Non-presence

PCI device and function presence or non-presence must be established before PCI enumeration and before the LAN controllers are released from PCI reset. Soft straps for the LAN controllers are provided for this purpose.

13.7.1.1 LAN Controllers Soft Straps

There are six soft straps that affect the four LAN ports. By default, all LAN ports and PCI functions of a particular product SKU are enabled. The six soft straps related to Ethernet ports/functions are:

1. LAN Controller 0 – Power in S5 enable.
2. LAN Controller 1 – Power in S5 enable.
3. LAN Controller 0 – Disable.
4. LAN Controller 1 – Disable.
5. LAN Controller 0, Port 1 Disable.
6. LAN Controller 1, Port 1 Disable.

Note: LAN0 Port 0 and LAN1 Port 0 cannot be disabled.

The definition of these soft straps can be found in Table 4-3, "Flash Descriptor Soft Straps". These soft strap settings are defined in the flash descriptor (region 0) of the SPI.

13.7.2 Disabling PCI Functions by BIOS

The BIOS can disable the LAN controller PCI functions. The memory mapped Function Disable (FUNC_DIS) register of the Power Management Controller (PMC) portion of the Platform Control Cluster (PCC) contains four bits to disable for PCI functions in LAN0 (ports 0 and 1) and LAN1 (ports 0 and 1).

Note: LAN port 0 must be enabled if a LAN controller is enabled.

13.7.3 LAN Port Interface

The LAN ports, each with its own MAC and set of transmit and receive queues, performs all of the functions required for transmission, reception, and collision handling called out in the standards.

The default link mode is set via the 2-bit *Link Mode* field (bits [5:4]) of the Initialization Control 3 word, located at 16-bit word offset 0x24 of the particular LAN-port base address of the shared SPI Flash. The link modes are listed in Table 13-15, "Link Modes".

Table 13-15. Link Modes

Link Mode	Device ID	Branding String
Default (10Gbps SKU)	0x1306	Intel® Ethernet Connection X553
Default (1Gbps SKU)	0x1307	Intel® Ethernet Connection X553
VF (Hyper-V)	0x15B4	Intel® X553 Virtual Function
KR/KX to Backplane	0x15C2 [1]	Intel® Ethernet Connection X553 Backplane
KX (2.5GbE)	0x15C3 [2], 0x15C2 [1]	Intel® Ethernet Connection X553 Backplane
SFI (Native) [3]	0x15C4	Intel® Ethernet Connection X553 10 GbE SFP+
VF	0x15C5	Intel® X553 Virtual Function
SGMII Backplane	0x15C6 [1], 0x15C7 [2]	Intel® Ethernet Connection X553 1GbE
SGMII	0x15E4 [1], 0x15E5 [2]	Intel® Ethernet Connection X553 1GbE
KR/KX to 10GBASE-T, 1GBASE-T (X557) [3]	0x15C8	Intel® Ethernet Connection X553 10GBASE-T
KR to SFP+ (InPhi) [3]	0x15CE	Intel® Ethernet Connection X553 10 GbE SFP+

Notes:
1. This device ID represents a 10G LAN controller SKU for the particular link mode.
2. This device ID represents a non-10G LAN controller SKU for the particular link mode.
3. Supported only on 10G capable LAN controller SKU.

LAN port features:

- Device power management and power states
- DMA coalescing
- Broadcast Wake Up
- IPv4/IPv6 packet-detect support
- Magic Packet detection and operation
- Packet pattern flexible filters

13.7.4 Reference Clock Input

The LAN controllers require a differential, non spread-spectrum reference clock for most of its MAC operation. The source of the clock is the 25-MHz crystal attached to pins CLK_X1_PAD and CLK_X2_PAD of the SoC. See Chapter 7, "Clock Architecture". Routing of this clock signal from the 25-MHz crystal to pins is critical and the Product Design Guide should be followed very carefully.

13.7.5 Pin Straps

There are no pin straps associated with the integrated LAN controllers in this SoC generation.

13.8 Shared SPI Flash for Use with LAN0 and LAN1

Unlike previous SoC generations, there is not a dedicated external NVM device that stores the Ethernet configuration parameters. LAN0 and LAN1 use two sections of the shared system SPI Flash to configure parameters for all LAN ports and PCI functions including MAC addresses, LED behaviors, receive packet filters for manageability, wake-up capability, etc.

The contents of the shared SPI Flash are always addressed as 16-bit words. When an offset value is shown, it is always in terms of 16-bit words.

Some of the shared SPI Flash 16-bit words are used to specify hardware parameters that affect all four LAN interfaces such as those affecting circuit behavior. Other words are associated with a specific LAN port. Both LAN0 and LAN1 interfaces access the shared SPI Flash to obtain their respective configuration settings.

13.8.1 Shared SPI Flash Starter Images

Intel provides a number of NVM flash images for LAN functionality that SoC customers can use with their designs. Please refer to the NVM flash image documentation with the images regarding the descriptions and use of these NVM images. These files are considered starter images and to some extent can be altered for a customer particular usage. Intel provides tools for customers to program images to the system for various operating systems. Contact your local Intel sales representative for details. If Intel needs to provide updates to customers, it provides the necessary software tools to do this.

13.8.2 Shared SPI Flash Map Related to LAN0 and LAN1

The shared SPI Flash related to LAN0 and LAN1 is divided into five major regions and a number of sub-regions as listed in Section 4.0 of the “Programmer’s Reference Manual” show a list of words of customer interest. Shared SPI Flash words defined for exclusive use by Intel are not listed.

13.8.3 Unique MAC Address

The SoC customer assigns their own unique six-byte MAC address for each LAN port. The shared SPI Flash has three 16-bit word locations defined for each of the four LAN ports. The six-byte MAC address is programmed to the shared SPI Flash as shown in this example, where the desired MAC address for LAN port 2 is 00-A0-C9-00-00-03:

- Word 0xC0 = 0xA000
- Word 0xC1 = 0x00C9
- Word 0xC2 = 0x0300

13.8.4 VLAN Support

Two basic types of VLANs are supported:

- Tagged VLANs are based on the IEEE 802.1Q specification. Each packet has a 4-byte tag added to the packet header. The switch must support IEEE 802.1Q tagging and be properly configured. Check the switch documentation for the correct switch configuration.
- Untagged or port-based VLANs are statically configured on the switch and are transparent to connected devices.

13.9 MMIO and Software Interface

The MMIO register descriptions for each of the PCI functions of the LAN controllers are not described in this document.

13.10 Host Primary Interface

The LAN controllers communicate with the host CPUs and host memories over an internal fabric.

13.10.1 Host Interface Architecture, Transaction and Link Layer Properties

- All PCI functions are native PCIe functions
- Credit-based flow control
- Packet sizes/formats:
  - Maximum upstream (write) payload size of 512 bytes
    Configurable sizes are: 128 bytes through 512 bytes
  - Maximum downstream (read) payload size of 2 KB
    Configurable sizes are: 128 bytes through 2 KB
- Reset/initialization:
  - Credit negotiation performed by hardware
- Transaction layer mechanisms
  - 64-bit memory address spaces
  - Removal of I/O BAR (optional)
  - Relaxed ordering
  - Flow control update time out mechanism
  - ID-based ordering (IDO)
  - Function-Level Reset (FLR)
  - Reliability
  - Advanced Error Reporting (AER)
- Power management
  - Wake capability
  - Latency Tolerance Reporting (LTR)
- The LAN controllers support the following extended capabilities:
  - Device serial number
  - Alternative Routing-ID Interpretation (ARI)
  - Single Root I/O Virtualization (SR-IOV)
  - Access Control Services (ACS)
- Software configuration mechanism:
  - Uses PCI configuration and bus enumeration model
  - PCIe-specific configuration registers mapped via PCI extended capability mechanism

13.10.2 PCIe Transaction Layer

13.10.2.1 Transaction Types Accepted by the LAN Controllers

Table 13-16, "Transaction Types Accepted by the Transaction Layer" lists the transactions accepted by the device and their attributes.

Table 13-16. Transaction Types Accepted by the Transaction Layer

Transaction Type	Tx Layer Reaction	Hardware Should Keep Data From Original Packet
Configuration Read Request	CPLH + CPLD	Requester ID, TAG, attribute
Configuration Write Request	CPLH	Requester ID, TAG, attribute
Memory Read Request	CPLH + CPLD	Requester ID, TAG, attribute
Memory Write Request	-	-
I/O Read Request	CPLH + CPLD	Requester ID, TAG, attribute
I/O Write Request	CPLH	Requester ID, TAG, attribute
Read Completions	-	-
Message	-	-

13.10.2.1.1 Size of Target Accesses

Memory Accesses

Rules for accesses to the CSR space (both memory BAR and MSI-X BAR):

- Write accesses
  - Zero-length writes have no internal impact (nothing written, no effect such as clear-by-write). The transaction is treated as a successful operation (no error event).
- CSR writes are 32-bit or 64-bit only. Larger or partial CSR writes are handled as completer abort - data is dropped and an error is generated per PCIe rules read accesses
  - Partial reads with at least one byte disabled are handled as a full read. Any side effect of the full read (such as clear by read) is also applicable to partial reads. The completion on PCIe follows the specification rules regarding the number of bytes reported in the completion.
  - Zero-length reads generate a completion, but the register is not accessed and undefined data is returned.
  - CSR reads are 32-bit or 64-bit only. Larger CSR read requests are handled as completer abort - the completion includes a CA status and an error is generated per PCIe rules.
  - Some 64-bit reads are handled atomically (such as not interleaved with any other requests). This applies mainly to reading counters, where all 64 bits need to be read simultaneously. Such registers are explicitly marked in their description.

Rules for accessing the shared SPI Flash space in the memory BAR:

- Write accesses
  - Writes to the shared SPI Flash are 16-bit wide only
  - Any larger write accesses are handled as completer abort - data is dropped and an error is generated per PCIe rules
- Read accesses
  - Reads to shared SPI Flash are 16-bit wide
  - Partial reads with at least one byte disabled are handled internally as a full read. That is, any side effect of the full read (such as clear by read) is also applicable to partial reads. The completion on PCIe follows the specification rules regarding the number of bytes reported in the completion.
  - Larger CSR read requests are handled as completer abort; the completion includes a CA status and an error is generated per PCIe rules

I/O Accesses

Rules for accesses to the I/O BAR:

- Write accesses
  - Write accesses are 32-bit wide
  - Zero-length writes have no internal impact (nothing written, no effect such as clear-by-write). The transaction is treated as a successful operation (no error event).
  - Other accesses (partial writes, larger writes) are handled as completer abort - data is dropped and an error is generated per PCIe rules
- Read accesses
  - Reads to the I/O BAR are 32-bit wide
  - Partial reads with at least one byte disabled are handled internally as a full read. That is, any side effect of the full read (such as clear by read) is also applicable to partial reads. The completion on PCIe follows the specification rules regarding the number of bytes reported in the completion.
  - Larger CSR read requests are handled as completer abort - the completion includes a CA status and an error is generated per PCIe rules

13.10.2.1.2 Support for Dynamic Changes

The LAN controllers capture the bus number and device number per each configuration write request. However, a dynamic change of the bus number or device number is not supported. Rather, the PCIe link should be quiescent prior to such a change, including reception of all completion for previous requests.

13.10.2.2 Transaction Types Initiated by the LAN Controllers

Table 13-17. Transaction Types Initiated by the Transaction Layer

Transaction Type	Payload Size	Tx Layer Reaction
Configuration Read Request Completion	Dword	CPLH + CPLD
Configuration Write Request Completion	-	CPLH
I/O Read Request Completion	Dword	CPLH + CPLD
I/O Write Request Completion	-	CPLH
Read Request Completion	Dword/Qword	CPLH + CPLD
Memory Read Request	-	NPH
Memory Write Request	<= MAX_PAYLOAD_SIZE	PH + PD
Message	64 bytes	PH

Configuration values:

- Max Payload Size - The value of the Max_Payload_Size Supported field in the Device Capabilities register is loaded from the shared SPI Flash.
  - Hardware default is 512 bytes.
  - System software then programs the actual value into the Max_Payload_Size field of the Device Control register.

    Non-ARI mode: If not all functions are programmed with the same value, the max payload size used for all functions is the minimum value programmed among all functions.

    ARI mode: Max_Payload_Size is determined solely by the setting in Function 0
- Max_Read_Request_Size - The SoC LAN controllers support read requests of up to 2 KB.
  - The actual maximum size of a read request is defined as the minimum (2 KB, Max_Read_Request_Size field in the Device Control register).

The number of outstanding memory read requests is bounded by the following:

- The total number of outstanding requests is not more than 32 requests. These are shared by all sources for memory reads.

13.10.2.2.1 Data Alignment

Requests must never specify an address/length combination that causes a memory space access to cross a 4 KB boundary. The LAN controllers therefore break requests into 4 KB-aligned requests (if needed). This does not place any requirement on software. However, if software allocates a buffer across a 4 KB boundary, hardware issues multiple requests for the buffer. Software should consider aligning buffers to a 4 KB boundary in cases where it improves performance. The maximum size of a read request is defined as the minimum (2 KB bytes, Max_Read_Request_Size).

The general rules for packet alignment are as follows. Note that these apply to all LAN controller requests (read/write):

- The length of a single request does not exceed the PCIe limit of MAX_PAYLOAD_SIZE(512B) for write and MAX_READ_REQ (2KB) for read.
- The length of a single request does not exceed the LAN controller internal limitations.
- A single request does not span across different memory pages as noted by the 4 KB boundary alignment previously mentioned.

If a request can be sent as a single packet and still meet the general rules for packet alignment, then it is not broken at the cache line boundary but rather sent as a single packet. However, if any of the three general rules require that the request is broken into two or more packets, then the request is broken at the cache line boundary.

For requests with data payload, if the payload size is larger than (MAX_PAYLOAD_SIZE - CACHELINE_SIZE), then the request is broken into multiple TLPs starting at the first cache line boundary following the (MAX_PAYLOAD_SIZE - CACHELINE_SIZE) bytes. For example, if MAX_PAYLOAD_SIZE = 256 bytes and CACHELINE_SIZE = 64 bytes, a 1 KB request starting at address 0x...10 is broken into TLPs such that the first TLP contains 240bytes of payload (since 240 bytes + 0x10 = 256 bytes is on cache line boundary).

The system cache line size is controlled by the *PCI_CNF2.CACHELINE_SIZE* bit, loaded from the shared SPI Flash update.

Note: The Cache Line Size register in the PCI configuration space is not related to the *PCI_CNF2.CACHELINE_SIZE* and is solely for software use.

13.10.2.3 Messages

13.10.2.3.1 Received Messages

Message packets are special packets that carry a message code. The upstream device transmits special messages to the LAN controllers by using this mechanism. The transaction layer decodes the message code and responds to the message accordingly.

Table 13-18. Supported Message in the LAN Controllers (as a Receiver)

Message Code [7:0]	Routing	Message	LAN Controller Later Response
0x40, 0x41, 0x43, 0x44, 0x45, 0x47, 0x48	100b	Ignored messages (used to be hot-plug messages)	Silently drop.
0x50	100b	Slot power limit support (has one Dword data)	Silently drop.
0x7E	000b, 010b, 011b, 100b	Vendor defined type 0	Drop and handle as an Unsupported request
0x7F	100b	Vendor defined type 1	Silently drop.
0x7F	010b, 011b, 000b	Vendor defined type 1	Silently drop.
0x00	011b	Unlock	Silently drop.

13.10.2.3.2 Transmitted Messages

The transaction layer is also responsible for transmitting specific messages to report internal/external events (such as interrupts and PMEs).

13.10.2.4 Transaction Attributes

13.10.2.4.1 Traffic Class (TC) and Virtual Channels (VC)

The LAN controllers only supports TC = 0b and VC = 0b (default).

13.10.2.5 Ordering Rules

The LAN controllers meet the PCIe ordering rules by following the PCI simple device model:

1. Deadlock Avoidance – The LAN controllers meets the PCIe ordering rules that prevent deadlocks:
   a. Posted writes overtake stalled read requests. This applies to both target and master directions. For example, if master read requests are stalled due to lack of credits, master posted writes are allowed to proceed. On the target side, it is acceptable to timeout on stalled read requests in order to allow later posted writes to proceed.
   b. Target posted writes overtake stalled target configuration writes.
   c. Completions overtake stalled read requests. This applies to both target and master directions. For example, if master read requests are stalled due to lack of credits, completions generated by the LAN controllers are allowed to proceed.
2. Descriptor/Data Ordering — The LAN controllers ensure that a Rx descriptor is written back on PCIe only after the data that the descriptor relates to is written to the PCIe link.
3. MSI and MSI-X Ordering Rules — System software might change the MSI or MSI-X tables during run-time. Software expects that interrupt messages issued after the table has been updated are using the updated contents of the tables.
   a. Since software doesn't know when the tables are actually updated in the LAN controllers, a common scheme is to issue a read request to the MSI or MSI-X table (a PCI configuration read for MSI and a memory read for MSI-X). Software expects that any message issued following the completion of the read request, is using the updated contents of the tables.
   b. Once an MSI or MSI-X message is issued using the updated contents of the interrupt tables, any consecutive MSI or MSI-X message does not use the contents of the tables prior to the change.
4. The LAN controllers meet the rules relating to independence between target and master accesses:
   a. The acceptance of a target posted request does not depend upon the transmission of any TLP.
   b. The acceptance of a target non-posted request does not depend upon the transmission of a non-posted request.
   c. Accepting a completion does not depend upon the transmission of any TLP.

13.10.2.5.1 Relaxed Ordering

The LAN controllers take advantage of the relaxed ordering rules in PCIe. By setting the relaxed ordering bit in the packet header, the LAN controllers enable the system to optimize performance in the following cases:

1. Relaxed ordering for descriptor and data reads — When the LAN controller masters a read transaction, its split completion has no ordering relationship with the writes from the CPUs (same direction). It should be allowed to bypass the writes from the CPUs.
2. Relaxed ordering for receiving data writes — When the LAN controllers master receive data writes, it also enables them to bypass each other in the path to system memory because software does not process this data until their associated descriptor writes are done.
3. The LAN controllers cannot relax ordering for receive descriptor writes or an MSI write.

Relaxed ordering is enabled in the LAN controllers by clearing the *CTRL_EXT.RO_DIS* bit. Relaxed ordering is further controlled through the *Enable Relaxed Ordering* bit in the PCIe Device Control register.

13.10.2.5.2 ID-based Ordering (IDO)

IDO was introduced in the PCIe rev. 2.1 specification. When enabled, The LAN controllers set IDO in all applicable TLPs defined in the PCIe specification.

This capability enables a supporting root complex to relax ordering rules for TLPs sent by different requesters.

IDO is enabled when all of the following conditions are met:

- The shared SPI Flash update *PCI_CAPSUP.IDO* Enable bit is set
- The PCIe *IDO Request Enable* bit (for requests) or the *IDO Completion Enable* bit (for completions) in Device Control 2 register is set

13.10.3 Error Events and Error Reporting

13.10.3.1 General Description

PCIe defines three error reporting paradigms: the baseline capability, the Advanced Error Reporting (AER) capability, and a proprietary mechanism. The baseline error reporting capabilities are required of all PCIe devices and define the minimum error reporting requirements. The AER capability is defined for more robust error reporting and is implemented with a specific PCIe capability structure. Both mechanisms are supported by the LAN controllers. The proprietary error reporting mechanism used for error is better handled by the software device driver using internal CSRs.

The *SERR# Enable* and the *Parity Error* bits from the Legacy Command register also take part in the error reporting and logging mechanism.

In a multi-function device, PCIe errors that are not related to any specific function within the device are logged in the corresponding status and logging registers of all functions in that device. Figure 13-3, "Error Reporting Mechanism" shows, in detail, the flow of error reporting in the LAN controllers.

Figure 13-3. Error Reporting Mechanism



13.10.3.2 Error Events

Table 13-19, "Response and Reporting of PCIe Error Events" lists the error events identified by the LAN controller and the response in terms of logging, reporting, and actions taken. Refer to the *PCI Express Base Specification Revision 3.0* for the effect on the PCI Status register.

Table 13-19. Response and Reporting of PCIe Error Events

Error Name	Error Events	Default Severity	Action
TLP Errors			
Poisoned TLP Received	• TLP With Error Forwarding (EP = 1b) • Data Parity	Uncorrectable ERR_NONFATAL Log Header	If completion TLP: Error is non-fatal (default case) • Send error message if advisory • Retry the request once and send advisory error message on each failure • If fails, send uncorrectable error message Error is defined as fatal • Send uncorrectable error message
Unsupported Request (UR)	• Receipt of TLP with unsupported Request Type • Receipt of an Unsupported Vendor Defined Type 0 Message • Invalid Message Code • Wrong Function Number • Received TLP Outside BAR Address Range • Receipt of a Request TLP during D3hot, other than Configuration and Message requests	Uncorrectable ERR_NONFATAL Log header	Send Completion With UR
Completion Timeout	Completion Timeout Timer Expired	Uncorrectable ERR_NONFATAL	Error is non-fatal (default case) • Send error message if advisory • Error is defined as fatal • Send uncorrectable error message
Completer Abort	Received Target Access With illegal data size per Section 13.10.2.1.1, "Size of Target Accesses"	Uncorrectable. ERR_NONFATAL Log header	Send completion with CA
Unexpected Completion	Received Completion Without a Request For It (Tag, ID, etc.)	Uncorrectable ERR_NONFATAL Log Header	Discard TLP
Malformed TLP (MP)	• Data Payload Exceed Max_Payload_Size Received • TD field value does not correspond with the observed size • PM Messages That Don't Use TC0 • Usage of Unsupported VC • Target request crosses a 4KB boundary	Uncorrectable ERR_FATAL Log Header	Drop the Packet, Free FC Credits
Completion with Unsuccessful Completion Status		No Action (already done by originator of completion)	Free FC Credits
Command Parity	Parity error is detected on the command	Uncorrectable ERR FATAL	

13.10.3.3 Completion Timeout Mechanism

- The LAN controllers support completion time out as defined in the PCIe specification.
- The LAN controllers control the following aspects of completion time out:
- Disabling or enabling completion timeout
  - The PCIe *Completion Timeout Disable Supported* bit in the Device Capabilities 2 register is hard wired to 1b to indicate that disabling completion timeout is supported
  - The PCIe *Completion Timeout Disable* bit in Device Control 2 register controls whether completion timeout is enabled
- A programmable range of timeout values
  - The LAN controllers support all four ranges as programmed in the *Completion Time out Ranges Supported* field of the Device Capabilities 2 register. The actual completion time out value is written in the *Completion Time out Value* field of Device Control 2 register.

The following sequence takes place when completion timeout is detected:

- The appropriate message is sent on PCIe as listed in Table 13-19, "Response and Reporting of PCIe Error Events"
- The affected queue or client takes action based on the nature of the original request.
- An interrupt is issued to the respective PF.

13.10.3.4 Error Forwarding (TLP Poisoning)

If a TLP is received with an error-forwarding trailer, the packet is dropped and is not delivered to its destination, the LAN controller then reacts as listed in Table 13-19.

The following sequence takes place when a poisoned TLP is received:

- The appropriate message is sent on PCIe as listed in Table 13-19, "Response and Reporting of PCIe Error Events".
- An interrupt is issued.
- If the TLP is a completion, a completion time out follows at some later time. Processing continues as described in Section 13.10.2.3, "Messages".

System logic is expected to trigger a system-level interrupt to signal the operating system of the problem. Operating systems can then stop the process associated with the transaction, re-allocate memory to a different area instead of the faulty area, etc.

13.10.3.5 Completion With Unsuccessful Completion Status

A completion arriving with an unsuccessful completion status (either UR or CA) is dropped and not delivered to its destination. A completion time out follows at some later time. Processing continues as described in Section 13.10.2.3, "Messages".

13.10.3.6 Blocking on Upper Address

The PCI_UPADD register blocks master accesses from being sent out on PCIe if the TLP address exceeds some upper limit. Bits [31:1] correspond to bits [63:33] in the PCIe address space, respectively.

When a bit is set in GLPCI_UPADD[31:1], any transaction, in which the corresponding bit in its address is set, is blocked and not sent over PCIe. If all register bits are cleared, there is no effect (such as no TLPs are blocked by this mechanism).

The PCI_UPADD register is loaded from the shared SPI Flash update with a value allowing all addresses to pass. The software device driver should override this value with a system dependent value.

Processing a blocked transaction:

  — Write transaction:

  — The transaction is dropped.

  — Set the Exceeded upper address limit (write requests) event in the PCIe errors register (see Section 13.10.3.7).

  — An interrupt is issued as described in Section 13.10.3.7.

- Read transaction:

  — The transaction is dropped.

  — Set the Exceeded upper address limit (read requests) event in the PCIe errors register (see Section 13.10.3.7).

  — The originating internal client is notified.

  — The affected queue or client takes action based on the nature of the original request. An interrupt is issued to the respective PF.

13.10.3.7 Proprietary Error Reporting

The PCIe specification defines how to report errors to system software. There are, however, error events that the software device driver should be aware of or that the software device driver is in better position to handle and recover from. This section describes the mechanism to report PCIe related errors to software device drivers.

Several CSRs are dedicated to this functionality, with a separate bit allocated per error type (see Table 13-20):

- The PCIe Errors Reported register (PCI_PCIERR - RO) indicates which errors are reported using this mechanism. It is shared by all PFs. It is loaded from the shared SPI Flash update. All non-reserved errors are enabled.
- The PCIe Interrupt Cause register (PCI_ICAUSE - RW1C) indicates pending errors for errors set in the PCIe Errors Reported register. It is dedicated per PF.
- The PCIe Interrupt Enable register (PCI_IENA - RW) determines if an interrupt should be issued to the respective PCI function on an error event. It is dedicated per PF.

Reporting an error to the PF driver involves the following steps:

- The Auto-Negotiate (AN) controllers check if the respective bit is set in the PCIe Errors Reported register. If cleared, done. Else, continue.
- The respective bit is set in the PCIe Interrupt Cause register.
- If the respective bit is set in the PCIe Interrupt Enable register, an interrupt is issued to the PCI function. The PCI_EXCEPTION cause is used (see the EICR register described in the PRM).



Table 13-20. PCIe Errors Reported to Device Software

Error Event	Index	Description and Comments	Function Association
Exceeded upper address limit (read requests)	00	See Section 13.10.3.6, "Blocking on Upper Address"	Sent to PF
Exceeded upper address limit (write requests)	01	See Section 13.10.3.6, "Blocking on Upper Address"	Sent to PF
Reserved	02	Reserved entries	N/A
Poisoned TLP received	03	See Section 13.10.3.4, "Error Forwarding (TLP Poisoning)"	Sent to PF
Reserved	04-05	Reserved entries	N/A
Unsupported Request - Request Type	07	Request causes an Unsupported Request due to receipt of TLP with unsupported Request Type	Sent to PF
Unsupported Request - Vendor Message	08	Request causes an Unsupported Request due to receipt of an Unsupported Vendor Defined Type 0 Message	Sent to PF unless r[2:0] = *Broadcast from Root Complex,* in which case sent to all PFs
Reserved	09	Reserved entries	N/A
Unsupported Request - Function Number	10	Request causes an Unsupported Request due to receipt of a not-supported Function Number	Sent to all PFs
Reserved	12 - 11	Reserved entries	N/A
Completer abort - target size	13	Received Target Access with illegal data size per Section 13.10.2.1.1, "Size of Target Accesses" (CA)	Sent to PF
Reserved	14 - 31	Reserved entries	N/A

13.11 Management Interfaces

The LAN controllers contain three possible interfaces to an external BMC.

- SMBus
- NC-SI (over RMII)
- MCTP (over SMBus)

LAN0 and LAN1 can support SMBus and NCSI independently. This is done through configuration in the shared NVM section for LAN0 and LAN1. Sideband management is typically off by default.

13.11.1 SMBus

SMBus is an optional interface for pass-through and/or configuration traffic between an external BMC and the LAN controllers. The SMBus channel behavior and the commands used to configure or read status from the LAN controllers are described in the PRM.

The LAN controllers also enable reporting and controlling the device using the MCTP protocol over SMBus. The MCTP interface is used by the BMC to control the port and for pass-through traffic. All network ports are mapped to a single MCTP endpoint on SMBus.

13.11.1.1 Channel Behavior

The SMBus specification defines a maximum frequency of 100 KHz. However, when acting as a slave, the LAN controllers can receive transactions with a clock running at up to 1 MHz. When acting as a master, they can toggle the clock at 100 KHz, 400 KHz or 1 MHz. The speed used is set by the *SMBus Connection Speed* field in the SMBus Notification Time out and Flags shared SPI Flash word as described in the PRM.

13.11.2 NC-SI Transactions

The NC-SI link supports both pass-through traffic between the BMC and the LAN controller LAN functions, as well as configuration traffic between the BMC and the SoC LAN controller internal units as defined in the NC-SI protocol.

13.11.3 MCTP (over SMBus)

The LAN controllers support MCTP protocol for management. MCTP runs over the SMBus. The LAN controller also implements MCTP over NC-SI for command and pass-through traffic.

13.12 Sideband Interface (NC-SI)

The NC-SI interface in the LAN controllers is a connection to an external MC. It operates as a single interface with an external BMC, where all traffic between the LAN controllers and the BMC flow through the interface.

The LAN controller NC-SI interface meets the NC-SI version 1.0.0 specification as a PHY-side device.

13.12.1 Electrical Characteristics

The LAN controllers comply with the electrical characteristics defined in the NC-SI specification.

13.13 Shared SPI Flash

13.13.1 General Overview

Enablement, configuration and addressing are configured in the sections of the system shared SPI Flash specific to LAN0 and LAN1. All management interfaces related to LAN0 and LAN1 are disabled by default and they must be enabled via the shared SPI Flash.

The LAN controllers (LAN0 and LAN1) use sections of the system shared SPI Flash specific to LAN0 and LAN1 to enable, configure and personalize each port. The shared SPI Flash section is divided into a few general regions:

- Hardware Accessed — Loaded by the LAN controller hardware after power up, PCI reset deassertion, D3 to D0 transition, or software reset. Different hardware sections in the shared SPI Flash are loaded at different events.
- Firmware Area — Includes firmware code and structures used by the firmware for management configuration in its different modes.
- Software Accessed — This region is used by software entities such as LAN drivers, option ROM software and tools, PCIe bus drivers, VPD software, etc.

13.13.2 Shared SPI Flash Protection

The contents of several shared SPI Flash update modules must be protected via authentication.

The shared SPI Flash protection method implemented in the LAN controllers rely on an authenticate on update concept. It means that protected modules are not authenticated after initialization, but prior to committing a module update operation only. Shared SPI Flash protection is guaranteed by an inductive authentication chain, that assumes an initial secured shared SPI Flash image, and requires that any shared SPI Flash update must be secure as well. This method mandates the following limitations and restricting working assumptions:

1. An initial good image is loaded into the shared SPI Flash at the manufacturing site, which is assumed to be safe.
   a. It assumes customers (OEM and end-user) know the source of the installed components, the supply chain producing these components is not compromised during manufacturing, and that the SoC is physically protected from modification after deployment.
   b. The possibility exists that unauthorized firmware might be loaded into the shared SPI Flash via physical modification post manufacturing, as well as through supply chain vulnerabilities. However, firmware updates via programmatic (software) methods are enhanced to require authentication prior to updating shared SPI Flash settings. Furthermore, host software can independently detect whether the firmware image has an invalid digital signature.
2. In a normal operating mode, shared SPI Flash write accesses are controlled by the device (firmware) and cannot be directly performed by the host. Memory mapped shared SPI Flash access remains available for shared SPI Flash read accesses only. For simplicity and flexibility reasons, shared SPI Flash write accesses from the host can be initiated via *S*oftware Host Interface commands, VPD write interface, or via a BMC command, which are all handled by firmware. All other direct access write modes are blocked by hardware when the shared SPI Flash is protected.

13.13.3 Shadow RAM

The first eight 4 KB sectors of the LAN controller shared SPI Flash are allocated to create two 16 KB sections (section 0 and section 1), for the configuration content. At least one of these two sections must be valid at any given time; otherwise, the SoC LAN controllers are set based on its hardware default. Following a Power On Reset, the LAN controllers copy the valid section of the shared SPI Flash device into an internal shadow RAM. Any further read accesses by software or firmware to the lower 16 KB addresses of the shared SPI Flash (not through a Flash BAR) are directed to the internal shadow RAM. Modifications made to the shadow RAM contents are copied by the LAN controllers to the other 16 KB section of the shared SPI Flash, circularly flipping the valid section between sections 0 and 1 in the shared SPI Flash. This mechanism provides the following advantages:

1. A seamless backward-compatible interface for software/firmware to access the first 16 KB of the shared SPI Flash as if an external EEPROM device was connected. This interface is referred as EEPROM-mode access to the shared SPI Flash.

Note: Write access to the physical shared SPI Flash is only available in blank Flash/ non-secure modes.

2. A way to protect the image-update procedure from power down events by establishing a double-image policy. See Section 13.13.8.9, "Software Flash Read Flow via the Flash-mode Interface" for a description of the double-image policy. It relies on having pointers to shared SPI Flash modules stored in the shared SPI Flash section mirrored in the internal shadow RAM.
3. A way to ensure hardware auto-load during a PCIe reset event can be completed within PCIe timing constraints (100 ms), even if the shared SPI Flash is busy performing an erase operation initiated prior to that reset event.

Figure 13-4 shows the shadow RAM mapping and interface.

Figure 13-4. Shared SPI Flash Shadow RAM



13.13.3.1 Shadow RAM Update Flow

1. Following a write access by the software device driver to update the shadow RAM, the data should be updated in the shared SPI Flash as well. The LAN controllers update the shared SPI Flash from the shadow RAM when software explicitly requests an update using the Shadow RAM Dump Host Interface command. To reduce shared SPI Flash update operations, software is expected to request a dump only once its last shadow RAM write access completes. The LAN controllers then copy the contents of the shadow RAM to the non-valid configuration section and makes it the valid one.
2. The software device driver should wait for the command completion to make sure the flow succeeded. Software should be aware that programming the shared SPI Flash might require a long time since the shared SPI Flash update sequence is handled by firmware. The sector erase command by itself can last hundreds of milliseconds. The regular timeout of the host interface commands should also be sufficient to cover this command also.

13.13.4 Shared SPI Flash Clients and Interfaces

There are different software clients that can access the shared SPI flash sections related to LAN0 and LAN1: driver, tools, BIOS, VPD, etc. Table 13-21, "Clients and Access Types to the Shared SPI Flash" lists the different shared SPI Flash access methods.

Table 13-21. Clients and Access Types to the Shared SPI Flash

Client	Shared SPI Flash Access Method (Data Width)	Shared SPI Flash Access Target	Logical Byte Address Range	Shared SPI Flash Access Interface	Protection and Enforcement
Host Software	Memory BAR (parallel 32-bit)	Flash	0x000000 - 0xFFFFFF	Memory mapped 32-bit read/write via BARs.	Write access is limited to a single byte and is allowed only if hardware protection is disabled. (FLA.LOCKED = 0b).
Host Software	FLA bit banging (serial 1-bit)	Flash	0x000000 - 0xFFFFFF	Software accesses to shared SPI Flash by toggling the SPI pins.	FLA interface access is available only if hardware protection is disabled (FLA.LOCKED = 0b).
Host Software	Host interface Shadow RAM Read/Write command	Shadow RAM	0x000000 - 0x003FFF	Access to shadow RAM through the Shadow RAM Read/Write command	Requires a valid firmware image. Write protection is enforced by firmware.
Host Software	Host interface Shared SPI Flash read command	Flash	0x000000 - 0xFFFFFF	Software read from the shared SPI Flash via Flash Read command.	Requires a valid firmware image.
Host Software	Host interface shared SPI Flash write command/shared SPI Flash sector erase command	Flash	0x008000 - 0xFFFFFF	Software writes and sector erase.	Requires a valid firmware image. Writes and erases to protected areas are dropped when firmware protection is enabled.
Host Software	VPD access (parallel 32-bit)	Shadow RAM	0x000000 - 0x0003FF	VPD Address and Data registers.	Write accesses are enabled to the R/W area of the VPD. If the VPD structure is not valid, the entire 1024 bytes area becomes RO to VPD accesses.

13.13.5 Memory Mapped Host Interface

The shared SPI Flash is accessed by the LAN controllers each time the host CPU performs a read operation to a memory location mapped to the shared SPI Flash address space, or upon boot via accesses to the space indicated by the Base Address register. Accesses to the shared SPI Flash is based on a direct decode of CPU accesses to a memory window defined in the Memory CSR + Flash Base Address register (PCIe Control register at offset 0x10).

The LAN controllers control accesses to the Flash when it decodes a valid access. Attempts to out of range read access, the PCIe expansion/option ROM module (according to shared SPI Flash size field in Shared SPI Flash Control Word 1) would return a value of 0xDEADBEEF. Attempts to memory-mapped write accesses to the shared SPI Flash when protection is enabled or via expansion ROM BAR are ignored.

13.13.6 Shared SPI Flash Access Contention

Shared SPI Flash accesses initiated through different LAN functions might occur concurrently. The LAN controllers do not synchronize between entities accessing the shared SPI Flash, so a contention caused from one entity reading and another modifying the same location is possible.

To avoid such contention between software LANs or between software and firmware accesses, these entities are required to make use of the semaphore registers. Any read or write access to the shared SPI Flash made by software/firmware must be preceded by acquiring ownership over the shared SPI Flash. This is also useful to avoid the time out of a PCIe transaction made to a memory-mapped shared SPI Flash address while the shared SPI Flash is busy performing a sector erase operation.

However, two software entities cannot use this semaphore mechanism: BIOS access through expansion ROM and VPD software.

- Since VPD software accesses only the VPD module, which is located in the configuration section of the shared SPI Flash, VPD accesses are always performed against the shadow RAM. Firmware must take shared SPI Flash ownership before dumping the VPD changes to the shared SPI Flash. The Shadow RAM dump sequence is described in Section 13.13.3.1, "Shadow RAM Update Flow".
- No contention can occur between the BIOS access through expansion ROM and other software entities (including VPD) as it accesses the shared SPI Flash while the operating system is down.
- Contentions between BIOS and firmware can however happen if a system reboot occurs while the MC is accessing the shared SPI Flash.
  - If a system reboot is caused by a user pressing the standby button, it is required to route the wake-up signal from the standby button to the MC and not to the chipset. The MC issues a system reboot signal to the chipset only after the shared SPI Flash write access completes. Firmware is responsible to respond with a busy error code to MC NC-SI commands while other shared SPI Flash update writes are in progress.

If a system reboot is issued by a local user on the host, there is no technical way to prevent shared SPI Flash access contentions between the BIOS and the MC.

Caution: It is the user responsibility when remotely accessing the shared SPI Flash via the MC, to make sure another user is not currently initiating a local host reboot.

Note: Other MAC auto-load events are performed from the internal shadow RAM and do not compete with memory mapped accesses to the shared SPI Flash device.

Note: Software and firmware should avoid holding shared SPI Flash ownership (via the dedicated semaphore bit) for more than 500 ms.

13.13.6.1 Flash Deadlock Avoidance

The Flash is a shared resource among the following clients:

1. Hardware auto-load of shadow RAM (at power up); the LAN controller.
2. LAN port 0 and LAN port 1 software accesses.
3. Manageability/firmware accesses.
4. Software tools.

All clients can access the shared SPI Flash using parallel access. Hardware implements the actual access to the shared SPI Flash. Hardware arbitrates among the different clients and schedules these accesses, avoiding starvation of any client.

However, in the LAN controllers, the software and firmware clients can access the shared SPI Flash using bit banging. In this case, there is a request/grant mechanism that locks the shared SPI Flash to the exclusive use of one client. If one client is stuck without releasing the lock, the other clients can no longer access the shared SPI Flash. To avoid this deadlock, the LAN controllers implement a time-out mechanism, which revokes the grant from a client that doesn't toggle the shared SPI Flash bit-bang interface (*FLA.FL_SCK* bit) for more than two seconds. If any client fails to release the shared SPI Flash interface, hardware clears its grant, enabling the other clients to use the interface.

The deadlock timeout mechanism is enabled by the *Deadlock Timeout Enable* bit in the Control Word 2 in the shared SPI Flash.

13.13.7 Signature Field

The only way the LAN controllers can tell if a shared SPI Flash is programmed, is by trying to read the shared SPI Flash. The LAN controllers first read the Control word at word address 0x0 and 0x2000. They then check the signature value at bits 7 and 6 in both addresses.

If bit 7 is 0b and bit 6 is 1b in (at least) one of the two addresses, it considers the shared SPI Flash to be present and valid. It then reads the additional shared SPI Flash words from that section and programs its internal registers based on the values read. Otherwise, it ignores the values read from that location and does not read additional words.

If the signature bits are valid at both addresses, the LAN controllers assume that the first section is the valid one.

13.13.8 VPD Support

The shared SPI Flash image can contain an area for VPD. This area is managed by the OEM vendor and does not influence the behavior of hardware. Word 0x2F of the shared SPI Flash image contains a pointer to the VPD area in the shared SPI Flash. A value of 0xFFFF means VPD is not supported and the *PCI_CAPCTRL.VPD_EN* bit should be cleared in the PCI shared SPI Flash section (described in the PRM), to prevent the VPD capability from appearing in the configuration space.

The maximum area size is 1024 bytes but can be smaller. The VPD block is built from a list of resources. A resource can be either large or small. The structure of these resources are listed in Table 13-22, "Small Resource Structure" and Table 13-23, "Large Resource Structure".

Table 13-22. Small Resource Structure

Offset	0	1 — n
Content	Tag = 0xxx,xyyyb (Type = Small(0), Item Name = xxxx, length = yy bytes)	Data

Table 13-23. Large Resource Structure

Offset	0	1 — 2	3 — n
Content	Tag = 1xxx,xxxxb (Type = Large(1), Item Name = xxxxxxxx)	Length	Data

The LAN controllers parse the VPD structure during the auto-load process following PCIe reset in order to detect the read only and read/write area boundaries. The LAN controllers assume the following VPD fields with the limitations listed.

Table 13-24. VPD Structure

Tag	Length (bytes)	Data	Resource Description
0x82	Length of identifier string	Identifier	Identifier string.
0x90	Length of RO area	RO data	VPD-R list containing one or more VPD keywords.
0x91	Length of RW area	RW data	VPD-W list containing one or more VPD keywords. This part is optional.
0x78	N/A	N/A	End tag.

VPD structure limitations:

- The structure must start with a Tag = 0x82. If the LAN controllers do not detect a value of 0x82 in the first byte of the VPD area or the structure does not follow the description of the VPD structure, they assume the area is not programmed and the entire 1024 bytes area is read only.
- The RO area and RW area are both optional and can appear in any order. A single area is supported per tag type. Refer to Appendix I in the PCI 3.0 specification for details of the different tags.
- If a VPD-W tag is found, the area defined by its size is writable via the VPD structure.
- The structure must end with a Tag = 0x78. The tag must be word aligned.
- The VPD area can be accessed through the PCIe configuration space VPD capability structure listed in the VPD structure. Write accesses to a read-only area or any access to an offset outside of the VPD area via this structure are ignored.
- VPD area must be mapped in the first 16 KB section of the shared SPI Flash mapped to the shadow RAM.
- VPD software does not check the semaphores before attempting to access the shared SPI Flash via dedicated VPD registers. Even if the shared SPI Flash is owned by another entity, VPD software read access to the VPD area in the shared SPI Flash might complete immediately since it is first performed against the shadow RAM. However, VPD software write access might not complete immediately since the VPD changes are committed to the shared SPI Flash device at the LAN controller initiative, once the other entity releases shared SPI Flash ownership, which can take up to several seconds.

13.13.8.1 VPD Access Flows

13.13.8.1.1 First VPD Area Programming

The VPD capability is exposed in the PCIe configuration space only if the *PCI_CAPCTRL.VPD_EN* bit is set, regardless to any other sanity check that is performed on the VPD area contents.

The VPD content and pointer can be written on a blank shared SPI Flash without any limitation, such as for any other shared SPI Flash module when in the blank shared SPI Flash programming mode. After protection is enabled, if *VPD Write Enable* bit in shared SPI Flash control word 1 is cleared, only the RW area of the VPD is writable and only via the VPD interface.

13.13.8.2 VPD Area Update Flows

1. The host initiates a VPD write by programming the offset and data fields of the VPD capability register set and then setting the capability's *Flag* bit. (bit 15 in VPD Address Register - 0xE2).
2. Firmware checks that the VPD write is allowed - it checks that the write offset falls within the VPD-RW area. If writing is not allowed, firmware clears the VPD flag in the configuration space to notify the host VPD software that the transaction completed. It then exits the flow.
3. Firmware indicates VPD access completion by clearing the VPD flag in the configuration space.

13.13.8.3 Shared SPI Flash Update Read, Write, and Erase Sequences

Refer to for the flow required to update secure shared SPI Flash modules.

Any software flow described in this section must be preceded by taking shared SPI Flash ownership via semaphores.

13.13.8.4 Software Flow to the Bit Banging Interface

To directly access the Flash when Flash is blank or not protected, software should follow these steps:

1. Write a 1b to the *Flash Request* bit (*FLA.FL_REQ*).
2. Poll the *Flash Grant* bit (*FLA.FL_GNT*) until it becomes 1b. It remains 0b as long as there are other accesses to the shared SPI Flash.
3. Write or read the shared SPI Flash using the direct access to the 4-wire interface as defined in the FLA register. The exact protocol used depends on the shared SPI Flash placed on the board.
4. Write a 0b to the *Flash Request* bit (*FLA.FL_REQ*).
5. Following a write or erase instruction, software should clear the *Request* bit only after it has checked that the cycles were completed by the shared SPI Flash. This can be checked by reading the *BUSY* bit in the shared SPI Flash device STATUS register. Refer to shared SPI Flash data sheet for the opcode to be used for reading the Status register.

Note: The bit banging interface is blocked during normal operation (protection enabled). Software should use the *FLSW* mode. Firmware can use this interface at all times.

13.13.8.5 Erase Flow Using the FLA Register

To directly erase a sector in the shared SPI Flash when the shared SPI Flash is blank or not protected, software should follow these steps:

1. Take ownership of shared SPI Flash update semaphore.
2. Set the *Flash Address* (*FLA.FL_ADDR*) to the index of the 4 KB sector to erase and *Sector Erase* bit (*FLA.FL_SER*) bit.
3. Read the FLA register until *Flash Busy* bit (*FLA.FL_BUSY*) is cleared.
4. Release ownership of shared SPI Flash update semaphore.

To directly erase the entire shared SPI Flash update when shared SPI Flash update is blank or not protected, software should follow these steps:

1. Take ownership of shared SPI Flash update semaphore.
2. Set *Device Erase* bit (*FLA.FL_DER*) bit.
3. Read the FLA register until *Flash Busy* bit (*FLA.FL_BUSY*) is cleared.
4. Release ownership of shared SPI Flash semaphore.

13.13.8.6 Software Access flow to Shadow RAM

13.13.8.6.1 Read Interface

Software can read from the shadow RAM using the following flow:

1. Send a Shadow RAM Read Host Interface command (described in the PRM) with the address and length to read.
2. Wait for the command to complete
3. Read the data from the response buffer.

13.13.8.6.2 Write Interface

Software can write to the shadow RAM using the following flow:

1. Send a Shadow RAM Write host Interface command (described in the PRM) with the address, length and data to write.
2. Wait for the command to complete

13.13.8.7 Flash Access Flow via the Memory Mapped Interface

13.13.8.7.1 Read Access

Software can always use the Flash BAR for read accesses.

Note: Software should take semaphore ownership before executing the flow.

13.13.8.7.2 Write Access

When the shared SPI Flash is blank or protection is disabled, software might initiate a write cycles via the Flash BAR as follows:

1. Take semaphore ownership before executing the flow.
2. Write the data byte to the shared SPI Flash through the Flash BAR.
3. Poll the *FL_BUSY* flag in the FLA register until cleared.
4. Repeat steps 2 and 3 to write additional bytes.
5. Release shared SPI Flash semaphore ownership.

As a response, hardware executes the following steps for each write access:

1. Set the *FL_BUSY* bit in the *FLA* register.
2. Initiate autonomous write enable instruction.
3. Initiate the program instruction right after the enable instruction.
4. Poll the Flash status until programming completes.
5. Clear the *FL_BUSY* bit in the *FLA* register.

Note: Software must erase the sector prior to programming it.

13.13.8.8 Software Flash/Shadow RAM Program Flow

Software must take semaphore ownership before executing the flow.

Software can write to non-write protected areas of the shared SPI Flash using the following flow:

1. Send a Flash Write Host Interface command (described in the PRM) with the address, length and data to write.
2. Wait for the command to complete.

13.13.8.9 Software Flash Read Flow via the Flash-mode Interface

Software must take semaphore ownership before executing the flow.

Software can read from the Flash using the following flow:

1. Send a Flash Read host Interface command (described in the PRM) with the address and length of the data to read.
2. Wait for the command to complete.
3. Read the data from the completion of the command.

13.13.9 Extended Shared SPI Flash Update Flows

13.13.9.1 Flow for Updating Secured Modules

This section describes the flow to use to update the firmware image.

In order to protect the shared SPI Flash update procedure from power-down events, a double image policy is used for each of the updated modules. The software flow to update a module is as follows:

1. Take ownership over the shared SPI Flash update via the semaphore bits. See PRM.
   a. If *SW_FW_SYNC.NVM_Update_Started* bit is read as clear, then set this bit together with setting the shared SPI Flash semaphore bit. It is used to notify other entities that a long shared SPI Flash update process that might take up to several minutes has started. During this time, other entities cannot perform a write access to the firmware module, but reading this module in between update write bursts is allowed using the shared SPI Flash memory mapping.
   b. Otherwise, release the shared SPI Flash semaphore ownership and restart the update process later on.
2. Read the pointer to the free provisioning area (shared SPI Flash word 0x40). Check that the free provisioning area size read from shared SPI Flash word 0x41 is greater or equal to the size of the new firmware image to be loaded in the shared SPI Flash.
   a. If not, release the shared SPI Flash semaphore ownership, clear the *SW_FW_SYNC.NVM_Update_Started* bit and exit the flow.
3. Initiate sector erase instructions (Section 13.13.8.3) to the entire free space provisioning segment.
   a. In order to guaranty shared SPI Flash semaphore ownership time does not exceed the one second timeout, it is recommended to perform at this step no more than four 4 KB sector erase operations at once in a burst, releasing semaphore ownership for 10 ms in between. This way, other entities can insert shared SPI Flash read accesses in between bursts without waiting for the entire update process completion, which might take minutes.
4. Write the new firmware/option ROM to the free provisioning area via Flash-mode access (Section 13.13.8.9)
   a. Same as step 3a, it is recommended to write at this step no more than four 4 KB sectors at once in a burst, releasing semaphore ownership for 10 ms in between.
5. Send a shared SPI Flash module update module ID of the section to update.The encoding of the modules is:

Table 13-25. SPI Flash Module Encoding

Module	ID	Reference
Firmware code	0x1	
Reserved	0x2	
Reserved	0x3	
Reserved	0x4	
Reserved	0x5	
Reserved	0x6:0xFD	
Reserved	0xFE	
Reserved (full shadow RAM)	0xFF	

6. Release the shared SPI Flash semaphore and clear the *SW_FW_SYNC.NVM_Update_Started* bit.
   a. Software must avoid taking the shared SPI Flash semaphore again until the firmware command has completed. Any attempt to write the shared SPI Flash until then is not performed by the device.
7. Firmware swaps between the free provisioning area pointer (word 0x40) and the firmware code module pointer, Network boot module pointer or the PHY pointer located at the shadow RAM word address 0x3A/0x5/0x4, respectively. Firmware dumps the shadow RAM into the shared SPI Flash.
8. Software waits for the command to complete.
   a. If the update process failed due to a security check failure or a shared SPI Flash write fault, an Authentication Error (0x80) or Data Error (0x6), respectively is returned. Software must then exit the flow, prior to attempting another update.

13.14 Configurable I/O Pins — Software-Definable Pins (SDPs)

The LAN controller has two software definable pins (SDP pins) per port that can be used for miscellaneous hardware or software-controllable purposes. Unless specified otherwise, these pins and their function are bound to a specific LAN device. The use, direction, and values of SDP pins are controlled and accessed by the Extended SDP Control (ESDP) register. To avoid signal contention, following power up, all SDP pins are defined as input pins.

Note: LAN0 has 4 SDP per port (total 8) and LAN1 has 2 SDP per port (total 4).

For the LAN controllers, the primary uses for the SDPs are:

- MOD_ABS connection pin for use in SFI supported designs where optics are used (SDP0 only)
- IEEE 1588 support
- Custom driver designs that require the use of an SDP for a desired use
- Creation of extended bus like I2C for LAN1 (created by MUXing pins)

Some SDP pins have specific functionality:

- The default direction of the SDP pins is loaded from the SDP Control word in the shared SPI Flash.
- The SDP pins can also be configured for use as External Interrupt Sources (GPI). To act as GPI pins, the desired pins must be configured as inputs and enabled by the GPIE register. The LAN controller can apply an inversion to the Rx data path via a programmable register. When detected, a corresponding GPI interrupt is indicated in the EICR register.

Note: An SDP configured as output can also generate interrupts, but this is not a recommended configuration.The bit mappings are listed in the following table for clarity.

Table 13-26. GPI to SDP Bit Mappings

SDP Pin To Be Used As GPI	ESDP Field Settings		Resulting EICR Bit (GPI)
	Directionality	Enable as GPI interrupt	
3	SDP3_IODIR	SDP3_GPIEN	28
2	SDP2_IODIR	SDP2_GPIEN	27
1	SDP1_IODIR	SDP1_GPIEN	26
0	SDIP_IODIR	SDP0_GPIEN	25

- The lowest SDP pins (SDP0_0) of port 0 can be used to encode the NC-SI package ID of the LAN controller. This ability is enabled by setting bit 15 in NC-SI Configuration 2 word (offset 0x07) of the shared SPI Flash. The 3-bit package ID is encoded as follows: Package ID = {0, SDP0_0, 0}.

When the SDP pins are used as IEEE1588 auxiliary signals they can generate an interrupt on any transition (rising or falling edge).

All SDP pins can be allocated to hardware functions. See more details on IEEE1588 auxiliary functionality in the PRM while I/O pin functionalities are programmed by the TimeSync Auxiliary Control (TSAUXC) register.

If mapping of these SDP pins to a specific hardware function is not required then the pins can be used as general purpose software defined I/Os. For any of the function-specific usages, the SDP I/O pins should be set to native mode by software setting of the SDPxxx_NATIVE bits in the ESDP register. Native mode in those SDP I/O pins, defines the pin functionality at inactive state (reset or power down) while behavior at active state is controlled by the software. The hardware functionality of these SDP I/O pins differ mainly by the active behavior controlled by software.

The following table lists the setup required to achieve each of the possible SDP configurations.

Table 13-27. SDP Settings

SDP	Usage	Shared SPI Flash Setting	ESDP		
			SDPx_NATIVE	SDPx_IODIR	SDP1_Function
0	SDP	N/A	0b	Input/Output	N/A
	MOD_ABS for SFI	bit 15 in NC-SI Configuration 2 shared SPI Flash word	0b	Input	
	1588 functionality as defined by the TSSDP register	N/A	1b	Input/Output	
1	SDP.	N/A	0b	Input/Output	
	XXXXXX	bit 2 in PCIe Control 3 word	N/A	Input	
	1588 functionality as defined by the TSSDP register	N/A	1b	Input/Output	0b

13.15 LEDs

The LAN controller implementation has two devices (LAN0 and LAN1) that provide two ports per device. LAN0 Port 0 has four and the other three ports have two output drivers intended for driving external LED circuits. Each of the LED outputs can be individually configured to select the particular event, state, or activity, indication on that output. In addition, each LED can be individually configured for output polarity as well as for blinking versus non-blinking (steady-state) indication.

The configuration for LED outputs is specified via the LEDCTL register. Furthermore, the hardware-default configuration for all LED outputs can be specified via shared SPI Flash fields thereby supporting LED displays configurable to a particular OEM preference.

Each of the LEDs can be configured to use one of a variety of sources for output indication. For more information on the MODE bits refer to the LEDCTL register description in the PRM.

The *IVRT* bits enable the LED source to be inverted before being output or observed by the blink-control logic. LED outputs are assumed to normally be connected to the negative side (cathode) of an external LED.

The *BLINK* bits control whether the LED should be blinked (on for 200 ms, then off for 200 ms) while the LED source is asserted. The blink control can be especially useful for ensuring that certain events, such as ACTIVITY indication, cause LED transitions, which are sufficiently visible by a human eye.

Note: The LINK/ACTIVITY mode ignores the BLINK value. The LED behavior in this mode is:

- Off if there is no LINK
- On if there is LINK and no ACTIVITY
- Blinks if there is LINK and ACTIVITY

The following mapping is used to specify the LED control source (MODE) for each LED output:

Table 13-28. LED Control Source (MODE) Mapping

Mode	Selected Mode	Source Indication
0000b	LINK_UP	Asserted or blinking according to the LEDx_BLINK setting when any speed link is established and maintained.
0001b	LINK_10G	Asserted or blinking according to the LEDx_BLINK setting when a 10 Gb/s link is established and maintained.
0010b	MAC_ACTIVITY	Active when link is established and packets are being transmitted or received. In this mode, the LEDx_BLINK must be set.
0011b	FILTER_ACTIVITY	Active when link is established and packets are being transmitted or received that passed MAC filtering. In this mode, the LEDx_BLINK must be set.
0100b	LINK/ACTIVITY	Asserted steady when link is established and there is no transmit or receive activity. Blinking when there is link and receive or transmit activity.
0101b	LINK_1G[1]	Asserted or blinking according to the LEDx_BLINK setting when a 1 Gb/s link is established and maintained.
0110b	Reserved[2]	Reserved.
0111b	LINK_2_5G	Asserted or blinking according to the LEDx_BLINK setting when a 2.5 Gb/s link is established and maintained.
1000b	Reserved	Reserved
1110b	LED_ON	Always asserted or blinking according to the LEDx_BLINK setting.
1111b	LED_OFF	Always deasserted.

Notes:
1. 10/100Mb operation will take same LED operation as 1G where applicable.
2. Undefined values are reserved.

13.16 Network Management Interface (MDIO or I^2C)

The LAN controllers support MDIO (Section 13.5.2, "Interconnect Interfaces") and/or I^2C (Section 13.5.2, "Interconnect Interfaces") interfaces, for control plane connection between the MAC (master side) and external PHY devices. The management interface enables both MAC and software access to the PHY for monitoring and controlling of the PHYs functionality and configurations. The LAN controllers are compliant with the IEEE Std 802.3 Clause 45 in LAN and 1 GbE operation. The LAN controllers also support IEEE Std 802.3 Clause 22 frame formats and register address space for accessing legacy PHY registers.

There are various connectivity options to external PHYs some use MDIO, such as Base-T PHYs, others might use I^2C, like SFP+ modules while in some special scenarios both might be needed such as when a device does not natively support SFI and requires the system designer to use both an external PHY for SFI translation, and an external SFP+ module. In such scenarios, the LAN controllers might need to use the MDIO to manage the external PHY and the I^2C to manage the external SFP+ module.

Make sure you select external devices that have been tested by Intel and that are supported in our native driver and tools. If an external device is selected that is not supported natively, it will be the customer's responsibility to change the driver, maintain updates to end users, and perform validation functions related to this added interface.

The list of supported devices can be found in Table 13-3, "Supported System Configurations".

13.16.1 I^2C or MDIO Selection

Since the LAN controller supports both MDC/MDIO and I^2C management interfaces, the final board and device setup must be communicated to the software device driver via a shared SPI Flash loaded configuration.

The following settings are provided in the NW Management Interface Select register for the software device driver to read. Based on these settings, the software device driver is able to understand if there is a companion device connected through either of the port's management interfaces. After power on, the software device driver reads the identity of the device connected through the interface and learns the physical topology.

Figure 13-5, "10GBASE-T Implementation" through Figure 13-8, "1G BASE-T Implementation" show the possible connectivity options.

13.16.2 Recommended Networking Topologies

The following diagrams show various recommended options for LAN controllers support. Each of these implementations are described in detail in Table 13-3, "Supported System Configurations".

Figure 13-5. 10GBASE-T Implementation



This implementation uses a 10GBASE-T PHY to enable four ports of 10GBASE-T via the KR support found in the LAN controller LAN0 and LAN1. MDIO/MDC is used to configure the PHY at initialization for KR mode. Refer to the list of supported external PHYs in Table 13-3, "Supported System Configurations".

Figure 13-6. 10G Backplane Implementation Using KR to Backplane (Switch)



Note: Shown is LAN0 Ports 0 and 1 connected to the backplane. Similar connections would be made if LAN1 connectivity was desired.

This implementation uses the KR support found in the LAN controller LAN0 and LAN1 (all 4 ports) for connection to a supported backplane partner. Refer to the list of supported switches in Table 13-3, "Supported System Configurations".

Figure 13-7. SFP+ Implementation



This implementation uses native SFI found in the LAN controller LAN0 and LAN1 for connection to a supported SFP+ optical modules. MOD_ABS (module absence) is provided via SDP support. I^2C connectivity is needed to ensure supported optical modules are populated.

13.16.3 Management Data I/O Interface (MDIO)

Figure 13-8. 1G BASE-T Implementation



The LAN controllers support the MDIO interface for a control plane connection between the MAC (master side) and PHY devices. The MDIO interface enables both MAC and software access to the PHY for monitoring and controlling of the PHYs functionality and configurations. The LAN controllers are compliant with the IEEE802.3 clause 45 in both 10 GbE and 1 GbE operation. The LAN controllers also support IEEE 802.3 clause 22 frame formats and register address space for accessing legacy PHY registers. Note that these pins are shared with the LED pins and at a given time only one of them is functional based on an shared SPI Flash configuration.

Note: The MDIO interface uses LVTTL signaling as defined in Clause 22 of the IEEE802.3 standard. To access PHYs that support clause 45 1.2V electrical interface, level translators might be needed on board. The MDIO/MDC connection is not required for KX connectivity.

Figure 13-9 shows the basic connectivity between the PHY and MAC.

Note: The MAUI is defined as Medium Attachment Unit Interface.

Figure 13-9. Basic PHY/MAC Connectivity



The MDIO interface is a simple 2-wire serial interface between the MAC and PHY and is used to access Control and Status registers inside the PHY. The interface is implemented using two LVTTL I/O signals:

1. MDC — MDIO-interface clock signal driven by an external MAC (STA) device.
2. MDIO — Read/write data between an external MAC and PHY

13.16.3.1 MDIO Timing Relationship to MDC

The MDC clock toggles during a read/write operation at a frequency of 2.4 MHz or 240 KHz depending on the link speed and register bit HLREG0.MDCSPD as listed in Table 13-29, "MDC Frequency as Function of Link Speed and MDC Speed Bit".

Table 13-29. MDC Frequency as Function of Link Speed and MDC Speed Bit

Link Speed	MDCSPD=1b	MDCSPD=0b
10 Gb/s	Reserved	2.4 MHz
1 Gb/s	2.4 MHz	240 KHz

MDIO is a bidirectional signal that can be sourced by the Station Management Entity (STA) or the PHY. When the STA sources the MDIO signal, the STA must provide a minimum of 10 ns of setup time and a minimum of 10 ns of hold time referenced to the rising edge of MDC, as shown in Figure 13-10, "MDIO Timing Source by the MAC" (measured at the MII connector).

Figure 13-10. MDIO Timing Source by the MAC



When the MDIO signal is sourced by the PHY, it is sampled by the MAC (STA) synchronously with respect to the rising edge of MDC. The clock to output delay from the PHY, as measured at the MII connector, must be a minimum of 0 ns, and a maximum of 300 ns, as shown in Figure 13-11, "MDIO Timing Sourced by the PHY".

Figure 13-11. MDIO Timing Sourced by the PHY



13.16.3.2 IEEE802.3 Clause 22 and Clause 45 Differences

IEEE802.3 clause 45 provides the ability to access additional device registers while still retaining logical compatibility with interface defined in Clause 22. Clause 22 specifies the MDIO frame format and uses an ST code of 01 to access registers. In clause 45, additional registers are added to the address space by defining MDIO frames that use a ST code of 00.

Clause 45 (MDIO interface) major concepts:

- Preserve management frame structure defined in IEEE 802.3 Clause 22.
- Define mechanism to address more registers than specified in IEEE802.3 Clause 22.
- Define ST and OP codes to identify and control the extended access functions.

13.16.3.3 MDIO Management Frame Structure

The MDIO interface frame structure defined in IEEE802.3 clause 22 and Clause 45 are compatible so that the two systems supporting different formats can co-exist on the same MDIO bus. The SoC LAN controllers support both frame structures to enable interfacing PHYs that support either protocol.

The basic frame format as defined in IEEE802.3 clause 22 can optionally be used for accessing legacy PHY registers is listed in Table 13-30, "Clause 22 Basic MDIO Frame Format".

Table 13-30. Clause 22 Basic MDIO Frame Format

Function	Management Frame Fields							
Frame	Pre	ST	OP	PRTAD	REGAD	TA	Data	Idle
Read	1...1	01	10	PPPPP	RRRRR	Z0	DDDDDDDDDDDDDDDD	Z
Write	1...1	01	01	PPPPP	RRRRR	10	DDDDDDDDDDDDDDDD	Z

The MDIO interface defined in clause 45 uses indirect addressing to create an extended address space enabling access to a large number of registers within each MDIO Managed Device (MMD). The MDIO management frame format is listed in Table 13-31, "Clause 45 Indirect Addressing MDIO Frame Format".

Table 13-31. Clause 45 Indirect Addressing MDIO Frame Format

Function	Management Frame Fields							
Frame	Pre	ST	OP	PRTAD	DEVAD	TA	Address / Data	Idle
Address	1...1	00	00	PPPPP	EEEEE	10	AAAAAAAAAAAAAAAA	Z
Write	1...1	00	01	PPPPP	EEEEE	10	DDDDDDDDDDDDDDDD	Z
Read	1...1	00	11	PPPPP	EEEEE	Z0	DDDDDDDDDDDDDDDD	Z
Post-Read Increment Address	1...1	00	10	PPPPP	EEEEE	Z0	DDDDDDDDDDDDDDDD	Z

To support clause 45 indirect addressing each MMD (PHY — MDIO managed device) implements a 16-bit address register that stores the address of the register to be accessed by data transaction frames. The address register must be overwritten by address frames. At power up or device reset, the contents of the address register are undefined. Write, read, and post-read-increment-address frames must access the register whose address is stored in the address register. Write and read frames must not modify the contents of the address register. Upon receiving a post-read-increment-address frame and having completed the read operation, the MMD increments the Address register by one (up to a value of 0xFFFF). Each MMD supported implements a separate address register, so that the MMDs address registers operate independently of one another.

Idle Condition (IDLE) — The IDLE condition on MDIO is a high-impedance state. All three state drivers must be disabled and the PHYs pull-up resistor pulls the MDIO line to a logic one.

Preamble (PRE) — At the beginning of each transaction, the station management entity must send a sequence of 32 contiguous consecutive one bits on MDIO with 32 corresponding cycles on MDC to provide the PHY with a pattern that it can use to establish synchronization. A PHY must observe a sequence of 32 contiguous consecutive one bits on MDIO with 32 corresponding cycles on MDC before it responds to any transaction.

Start of Frame (ST) — The ST is indicated by:

- <00> pattern for clause 45 compatible frames for indirect access cycles.
- <01> pattern for clause 22 compatible frames for direct access cycles.

These patterns ensure a transition from the default value of one on the MDIO signal, and identifies the start of frame.

Operation Code (OP) — The *OP* field indicates the type of transaction being performed by the frame.

For Clause 45 compatible frames:

- A <00> pattern indicates that the frame payload contains the address of the register to access.
- A <01> pattern indicates that the frame payload contains data to be written to the register whose address was provided in the previous address frame.
- A <11> pattern indicates that the frame is an indirect read operation.
- A <10> pattern indicates that the frame is an indirect post-read-increment-address operation.

For Clause 22 compatible frames:

- A <10> pattern indicates a direct read transaction from a register.
- A <01> pattern indicates a direct write transaction to a register.

Port Address (PRTAD) — The PRTAD is five bits, allowing 32 unique PHY port addresses. The first *PRTAD* bit to be transmitted and received is the MSB of the address. A station management entity must have prior knowledge of the appropriate port address for each port to which it is attached, whether connected to a single port or to multiple ports.

Device Address (DEVAD) — The DEVAD is five bits, allowing 32 unique MMDs per port. The first *DEVAD* bit transmitted and received is the MSB of the address. This field is relevant only in clause 45 compatible frames (ST=<00>).

Register Address (REGAD) — The REGAD is five bits, allowing 32 individual registers to be addressed within each PHY. The first *REGAD* bit transmitted and received is the MSB of the address. This field is relevant only in clause 22 compatible frames (ST=<01>).

Turnaround (TA) — The TA time is a 2-bit time spacing between the *DEVAD* field and the *Data* field of a management frame. This is to avoid contention during a read transaction. For a read or post-read-increment-address transaction, both the STA and the PHY must remain in a high-impedance state for the first bit time of the TA. The PHY must drive a zero bit during the second bit time of the TA of a read or post-read-increment-address transaction. During a write or address transaction, the STA must drive a one bit for the first bit time of the TA and a zero bit for the second bit time of the TA. Figure 13-12, "Behavior of MDIO During TA Field of a Read Transaction" shows the behavior of the MDIO signal during the *TA* field of a read transaction.

Figure 13-12.Behavior of MDIO During TA Field of a Read Transaction



- Clause 45 compatible frames have 16-bit address/data fields. For an auto-negotiation address cycle, it contains the address of the register to be accessed on the next cycle. For the data cycle of a write frame, the field contains the data to be written to the register. For a read or post-read-increment-address frame, the field contains the contents of the register. The first bit transmitted and received must be bit 15.
- Clause 22 compatible frames have 16-bit data fields. The first data bit transmitted and received must be bit 15 of the register being addressed.

13.16.3.4 MDIO Direct Access

The MDI is accessed through registers MSCA and MSRWD. A single management frame is sent by setting bit MSCA.MDICMD to 1b after programming the appropriate fields in the MSCA and MSRWD registers. The MSCA.MDICMD bit is auto cleared after the read or write transaction completes. To execute clause 22 format write operations, the following steps should be done:

1. Data to be written is programmed in field MSRWD.MDIWRDATA.
2. Register MSCA is initialized with the appropriate control information (start, code, etc.) with bit MSCA.MDICMD set to 1b.
3. Wait for bit MSCA.MDICMD to reset to 0b when indicating that the transaction on the MDIO interface is complete.

The steps for clause 22 format read operations are identical to the write operation except that the data in field MSRWD.MDIWRDATA is ignored and the data read from the external device is stored in register field MSRWD.MDIRDDATA bits. Clause 45 format read/write operations must be performed in two steps. The address portion of the pair of frames is sent by setting register field MSCA.MDIADD to the desired address, field MSCA.STCODE to 00b (start code that identifies clause 45 format), and register field MSCA.OPCODE to 00b (clause 45 address register write operation). A second data frame must be sent after the address frame completes. This second frame executes the write or read operation to the address specified in the PHY address register.

13.16.4 I²C

The LAN controllers support 2-wire management interface (I^2C) for connectivity to external SFP+ modules. Optical and direct attached copper PHYs use 2-wire management interface (I^2C) as described in SFF8431 (SFP+) or SFF8636 (Direct attach Cu).

Note: Some external PHYs also support an I^2C management interface instead of MDIO. It is up to the board designer to choose which interface to use. See Section 13.16.1, "I^2C or MDIO Selection".

The I^2C interface operates via the I2CCMD and I2CPARAMS register set. Since this register set can be used by either software or firmware in alternation, its ownership must be acquired/released via the semaphore ownership taking/release flows described in the PRM.

The I^2C interface can be used in two methods, a hardware based access, where the device initiates a transaction following a software device driver request via the I2CCMD register or a software controlled bit banging using the I2CPARAMS register.

13.16.4.1 Hardware Based I^2C Access

The following flows should be used to access an I^2C register.

As part of device initialization, or anytime before the actual access, the following parameters should be set:

- *I2CPARAMS.PHYADD* - the address of the device to access.
- *I2CPARAMS.ACCESS_WIDTH* - the width of the data to read or write (byte or word).

To execute a write access, the following steps should be done:

1. Check that register is ready: Poll the *I2CCMD.R* bit until it is read as 1b.
2. Command - The I2CCMD register is initialized with the appropriate PHY register address in the *REGADD* field, the data to write in the *DATA* field and the operation (write) to the *OP* field (0b).
   a. If an interrupt is required, set the *I2CCMD.I* field
3. Check that command is done: Poll *I2CCMD.R* bit until it is read as 1b.
   a. Check that no error is indicated in the *I2CCMD.E* field.

To execute a read access, the following steps should be done:

1. Check that the register is ready: Poll *I2CCMD.R* bit until it is read as 1b.
2. Command - The I2CCMD register is initialized with the appropriate PHY register address in the *REGADD* field, and the operation (read) to the *OP* field (1b).
   a. If an interrupt is required, set the *I2CCMD.I* field
3. Check that command is done: Poll *I2CCMD.R* bit until it is read as 1b.
   a. Check that no error is indicated in the *I2CCMD.E* field.
4. Read the data returned from the *I2CCMD.DATA* field. If a byte access is done (*I2CPARAMS.ACCESS_WIDTH* = 0b), only *DATA[7:0]* is valid.

13.16.4.2 Bit Bang Based I²C Access

In this mode, the software device driver controls the I²C interface directly using the I2CPARAMS register according to the following table:

Table 13-32. Direct I²C Interface Control

Pad	Field Controlling The Output Value	Field Reflecting The Input Value	Field Controlling The Output Enable Value[1]
I2C clock	CLK_OUT	CLK_IN	CLK_OE_N
I2C data	DATA_OUT	DATA_IN	DATA_OE_N

1. 0b = Pad is output. 1b = Pad is input.

13.16.4.3 Supported Commands

The gray columns that follow denote cycles driven by the I²C device. White columns denote cycles driven by the SoC LAN controllers.

When a word Read command (*I2CPARAMS.ACCESS_WIDTH* = 1b, *I2CCMD.OP* =1b) is given, the following sequence is done by the SoC LAN controllers:

Table 13-33. I²C Read Transaction - Dummy Write

1	7	1	1	8	1
S	Device Address	Wr	A	Register Address	A
	From *I2CCMD.PHYADD*	0	0	From *I2CCMD.REGADD*	0

Table 13-34. I²C Read Transaction - Word Read

1	7	1	1	8	1	8	1	1
S	Device Address	Rd	A	Data	A	Data	A	P
	From *I2CPARAMS.PHYADD*	1	0	Stored in *I2CCMD.DATA[7:0]*	0	Stored in *I2CCMD.DATA[15:8]*	0	

When a byte read command (*I2CPARAMS.ACCESS_WIDTH* = 0b, *I2CCMD.OP* =1b) is given the following sequence is done by the SoC LAN controllers:

Table 13-35. I²C Read Transaction - Dummy Write

1	7	1	1	8	1
S	Device Address	Wr	A	Register Address	A
	From *I2CPARAMS.PHYADD*	0	0	From *I2CCMD.REGADD*	0

Table 13-36. I²C Read Transaction - Byte Read

1	7	1	1	8	1
S	Device Address	Rd	A	Data	A
	From *I2CPARAMS.PHYADD*	1	0	Stored in *I2CCMD.DATA[7:0]*	0

When a word Write command (*I2CPARAMS.ACCESS_WIDTH* = 1b, *I2CCMD.OP* =0b) is given the following sequence is done by the LAN controllers:

Table 13-37. I²C Write Transaction - Word Write

1	7	1	8	1	1	8	1	8	1	1
S	Device Address	Wr	Register Address	A	P	Data	A	Data	A	P
	From *I2CPARAMS.PHYADD*	0	From *I2CCMD.REGADD*	0		From in *I2CCMD.DATA[7:0]*	0	From in *I2CCMD.DATA[15:8]*	0	

When a byte write command (*I2CPARAMS.ACCESS_WIDTH* = 0b, *I2CCMD.OP* =0b) is given the following sequence is done by the SoC LAN controllers:

Table 13-38. I²C Write Transaction - Byte Write

1	7	1	8	1	1	8	1
S	Device Address	Wr	Register Address	A	P	Data	A
	From *I2CPARAMS.PHYADD*	0	From *I2CCMD.REGADD*	0		From in *I2CCMD.DATA[7:0]*	0

13.17 Network Interface

There are two LAN controllers (LAN0 and LAN1) with two ports each, providing a total of four ports. Each port contains an independent LAN Media Access Control (MAC) that supports a XGMII-like interface link to an internal PHY (see Figure 13-1, "What is Covered in This Chapter").

The internal MAC/PHY combine to support 1GbE (KX and SGMII), 2.5GbE and 10GbE operation through various modes of operation.

Refer to Section 13.2, "Supported Modes of Operation" for all supported modes of Ethernet for use with internal PHYs (native support) and external PHYs.

13.17.1 Companion Integrated PHY Register Access

The LAN controllers provide a set of registers, per port, to enable register access to the software device driver and firmware. The access is an indirect access. For example, the software agent writes the address and data into the pair of registers listed in Table 13-39, "PHY Access Registers" and then the LAN controllers translate this into an internal operation to the relevant PHY sub-section.

Table 13-39. PHY Access Registers

Register	Description
PHY Indirect Control	This register is used for: • Configuring the address to access. • Report a status at the end of the operation.
PHY Indirect Data	• When software writes the data to this register the write operation is triggered. • When software reads from this register the read operation is triggered.

13.17.1.1 PHY Register Addressing

The PHY registers are addressed using a 16-bit address. Further, the companion integrated PHY is a dual-port block and has its registers divided to three partitions.

Table 13-40. PHY Registers' Addressing

Partition	Address Decoding	Description
Common Registers	[15:14] - 11 [13:0] - register address	Holds global registers with information that is not per port.
Port-0 Registers	[15:14] - 01 [13:0] - register address	Holds port-0 configuration and status registers.
Port-1 Register	[15:14] - 10 [13:0] - register address	Holds port-1 configuration and status registers.

When software or firmware is programming the PHY Indirect Control register with a port register address, it must be aware of the physical port it needs to access and set bits [15:14] of the address accordingly.

In order to identify the port number, software should read the *LAN_ID* field in the LAN controller Device Status register (0x00000008).

13.17.1.2 PHY Indirect Read Operation

1. The software agent checks that the PHY *Indirect Control[Busy]*=0b.
2. The software agent writes the following fields:
   a. PHY Select — These are the three MSBs of the address used to select the PHY sub-section.
   b. Addr[15:0] — internal address of register to access.
3. Software performs a read operation from the PHY Indirect Data register (this triggers the read operation).
4. The LAN controllers issue a read message to the PHY.
5. The LAN controllers send a read completion to software. Software might read the PHY *Indirect Control RESP STAT* field as this indicates the status of the operation.

13.17.1.3 PHY Indirect Write Operation

1. The software agent checks that the PHY *Indirect Control[Busy]*=0b.
2. The software agent writes the following fields:
   a. PHY Select - these are the three MSBs of the address used to select the PHY sub-section.
   b. Addr[15:0] - Internal address of register to access.
3. The software agent writes the data into the PHY Indirect Data register.
4. The LAN controllers issue a write message.
5. The software agent polls the PHY *Indirect Control[Busy]* field until it is = 0b again.

13.17.2 Ethernet Flow Control (FC)

The LAN controllers support flow control as defined in 802.3x, as well as the specific operation of asymmetrical flow control defined by 802.3z.

Note: The LAN controllers can either be configured to receive regular FC packets or PFC packets. The LAN controllers do not support receiving both types of packets simultaneously.

FC is implemented to reduce receive buffer overflows, which result in the dropping of received packets. FC also allows for local controlling of network congestion levels. This can be accomplished by sending an indication to a transmitting station of a nearly full receive buffer condition at a receiving station.

The implementation of asymmetric FC allows for one link partner to send FC packets while being allowed to ignore their reception. For example, not required to respond to PAUSE frames.

The following registers are defined for implementing FC using index[0] of each register:

- MAC Flow Control Register (MFLCN) — Enables FC and passing of control packets to the host.
- Flow Control Configuration (FCCFG) — Determines mode for Tx FC (No FC vs. link-based vs. priority-based). Note that if Tx FC is enabled then Tx CRC by hardware should be enabled as well (*HLREG0.TXCRCEN* = 1b).
- Flow Control Source Address Low, High (RAL[0], RAH[0]).
- Flow Control Destination Address Low, High (*FCAMACL, FCAMACH)* — 6-byte FC multicast address.
- Priority Flow Control Type Opcode (PFCTOP) — Contains the type and OpCode values for PFC.
- Flow Control Receive Threshold Low (FCRTL[7:0]) — A set of 13-bit low watermarks indicating receive buffer emptiness. A single watermark is used in link FC mode.
- Flow Control Transmit Timer Value (FCTTV[3:0]) — A set of 16-bit timer values to include in transmitted PAUSE frame. A single timer is used in link FC mode.
- Flow Control Refresh Threshold Value (FCRTV) — 16-bit PAUSE refresh threshold value (in legacy FC FCRTV[0] must be smaller than FCTTV[0]).

13.17.2.1 MAC Control Frames and Reception of Flow Control Packets

13.17.2.1.1 MAC Control Frame — Other than FC

The IEEE specification reserved the Ethertype value of 0x8808 for MAC control frames, which are listed in Table 13-41, "MAC Control Frame Format".

Table 13-41. MAC Control Frame Format

DA	The *Destination Address* field can be an individual or multicast (including broadcast) address. Permitted values for the *Destination Address* field can be specified separately for a specific control OpCode such as FC packets.
SA	Port Ethernet MAC Address (six bytes).
Type	0x8808 (two bytes).
Opcode	The MAC control OpCode indicates the MAC control function.
Parameters	The MAC control *Parameters* field must contain MAC control OpCode-specific parameters. This field can contain none, one, or more parameters up to a maximum of minFrameSize = 20 bytes.
Reserved field = 0x00	The *Reserved* field is used when the MAC control parameters do not fill the fixed length MAC control frame.
CRC	Four bytes.

13.17.2.1.2 Structure of 802.3X FC Packets

802.3X FC packets are defined by the following three fields (see Table 13-42, "802.3X Packet Format"):

1. A match on the six-byte multicast address for MAC control frames or a match to the station address of the device (Receive Address register 0). The 802.3x standard defines the MAC control frame multicast address as 01-80-C2-00-00-01.
2. A match on the *Type* field. The *Type* field in the FC packet is compared against an IEEE reserved value of 0x8808.
3. A match of the MAC control Opcode field has a value of 0x0001.

Frame-based FC differentiates XOFF from XON based on the value of the PAUSE Timer field. Non-zero values constitute XOFF frames while a value of zero constitutes an XON frame. Values in the *Timer* field are in units of pause quanta (such as slot time). A pause quanta lasts 64 byte times, which is converted into an absolute time duration according to the line speed.

Note: XON frame signals the cancellation of the pause from that was initiated by an XOFF frame. Pause for zero pause quanta.

Table 13-42. 802.3X Packet Format

DA	01_80_C2_00_00_01 (6 bytes).
SA	Port Ethernet MAC Address (6 bytes).
Type	0x8808 (two bytes).
Opcode	0x0001 (two bytes).
Time	XXXX (two bytes).
Pad	42 bytes.
CRC	Four bytes.

13.17.2.1.3 Priority Flow Control

Support is provided for multiple TCs assigning different priorities and bandwidth per TC. Link-level Flow Control (PAUSE) stops all the TCs. Priority Flow Control (PFC), known as Class Based Flow Control or CBFC, allows more granular Flow Control on the Ethernet link in a DCB environment as opposed to the PAUSE mechanism defined in 802.3X.

PFC is implemented to prevent the possibility of receive packet buffers overflow. Receive packet buffers overflow results in the dropping of received packets for a specific TC. Implement PFC by sending a timer indication to the transmitting station TC (XOFF) of a nearly full receive buffer condition at the LAN controllers. At this point the transmitter stops transmitting packets for that TC until the XOFF timer expires or a XON message is received for the stopped TC.

Similarly, once the LAN controllers receive a priority-based XOFF it stops transmitting packets for that specific TC until the XOFF timer expires or XON packet for that TC is received.

Figure 13-13.802.3X Link Flow Control (PAUSE)



13.17.2.1.4 Operation and Rules

The LAN controllers operate in either link FC or in PFC mode. Note that enabling both modes concurrently is not allowed:

- Link FC is enabled by the *RFCE* bit in the MFLCN register.
- PFC is enabled per UP by the corresponding *RPFCE* bit in the MFLCN register, and globally by *MFLCN.RPFCM* bit.

Note: Link FC capability must be negotiated between link partners via the auto-negotiation process. The PFC capability is negotiated via some higher level protocol and the resolution is usually provided to the software device driver by the DCB management agent. It is the software device driver responsibility to reconfigure the link FC settings (including RFCE and PRFCE) after the auto-negotiation process was resolved.

Note: Receiving a link FC frame while in PFC mode might be ignored or might pause TCs in an unpredictable manner. Receiving a PFC frame while in link FC mode is ignored. Flow control events that are ignored do not increment any flow control statistics counters.

Once the receiver has validated the reception of an XOFF, or PAUSE frame, the device performs the following:

- Increments the appropriate statistics register(s).
- Initialize the pause timer based on the packet's PAUSE *Timer* field (overwriting any current timer value).
  - For PFC, this is done per TC. If several UPs are associated with a TC, then the device sets the timer to the maximum value among all enabled *Timer* fields associated with the TC.
- Disable packet transmission or schedule the disabling of transmission after the current packet completes.
  - For PFC, this is done per paused TC.
  - Tx manageability traffic is bound to a specific TC as defined in the MNGTXMAP register, and is thus paused when its TC is paused.

Resumption of transmission can occur under the following conditions:

- Expiration of the PAUSE timer.
  - For PFC, this is done per TC.
- Receiving an XON frame (a frame with its PAUSE timer set to 0b).
  - For PFC, this is done per TC.

Both conditions clear the relevant TXOFF status bits in the Transmit Flow Control Status (TFCS) register and transmission can resume. Hardware records the number of received XON frames.

13.17.2.1.5 Timing Considerations

When operating at LAN line speed, the LAN controllers must not begin to transmit a (new) frame more than 74 pause quanta after receiving a valid Link XOFF frame, as measured at the wires (a pause quantum is 512 bit times).

When operating at 1 GbE line speed, the LAN controllers must not begin to transmit a (new) frame more than two pause quanta after receiving a valid Link XOFF frame, as measured at the wires.

The 802.1Qbb draft 2.3, proposes that the tolerated response time for priority XOFF frames are the same as Link XOFF frames with extra budget of 19360 bit times if MACSec is used, or of two pause quanta otherwise. This extra budget is aimed to compensate the fact that decision to stop new transmissions from a specific TC must be taken earlier in the transmit data path than for the link flow control case.

13.17.2.2 PAUSE and MAC Control Frames Forwarding

Two bits in the Receive Control register control transfer of PAUSE and MAC control frames to the host. These bits are *Discard PAUSE Frames* (*DPF*) and *Pass MAC Control Frames* (*PMCF*). Note also that any packet must pass the L2 filters as well.

- The *DPF* bit controls the transfer of PAUSE packets to the host. The same policy applies to both link FC and PFC packets as listed in Table 13-43, "Transfer of PAUSE Packet to Host (DPF Bit)". Note that any packet must pass the L2 filters as well.
- The Pass MAC Control Frames (PMCF) bit controls the transfer of non-PAUSE packets to the host. Note that when link FC frames are not enabled (RFCE = 0b) then link FC frames are considered as MAC control frames for this case. Similarly, when PFC frames are not enabled (RPFCM = 0b) then PFC frames are considered as MAC control frames as well.

Note: When virtualization is enabled, forwarded control packets are queued according to the regular switching procedure.

Table 13-43. Transfer of PAUSE Packet to Host (DPF Bit)

RFCE	RPFCM	DPF	Link FC Handling	PFC Handling
0b	0b	X	Treat as MAC control (according to *PMCF* setting).	Treat as MAC control (according to *PMCF* setting).
1b	0b	0b	Accept.	Treat as MAC control (according to *PMCF* setting).
1b	0b	1b	Reject.	Treat as MAC control (according to *PMCF* setting).
0b	1b	0b	Treat as MAC control (according to *PMCF* setting).	Accept.
0b	1b	1b	Treat as MAC control (according to *PMCF* setting).	Reject.
1b	1b	X	Unsupported setting.	Unsupported setting.

13.17.2.3 Transmitting PAUSE Frames

The LAN controllers generate PAUSE packets to ensure there is enough space in its receive packet buffers to avoid packet drop. The LAN controllers monitor the fullness of its receive FIFOs and compares it with the contents of a programmable threshold. When the threshold is reached, the LAN controllers send a PAUSE frame. The LAN controllers support both link FC and PFC — but not both concurrently. When DCB is enabled, it only sends PFC, and when DCB is disabled, it only sends link FC.

Note: Similar to receiving flow control packets previously mentioned, software can enable FC transmission by setting the *FCCFG.TFCE* field only after it is negotiated between the link partners (possibly by auto-negotiation).

13.17.2.3.1 Priority Flow Control (PFC)

The LAN controllers operate in either a link 802.3X compliant mode or in a PFC mode, but not in both at the same time.

The same watermarks mechanism is used for PFC and for 802.3X FC to determine when to send XOFF and XON packets. When PFC is used in the receive path, priority PAUSE packets are sent instead of 802.3X PAUSE packets. The format of priority PAUSE packets is described in Operation and Rules.

Specific considerations for generating PFC packets:

- When a PFC packet is sent, the packet sets all the UPs that are associated with the relevant TC (UP-to-TC association in receive is defined in RTRUP2TC register).

13.17.2.3.2 Operation and Rules

The *TFCE* field in the Flow Control Configuration (FCCFG) register enables transmission of PAUSE packets as well as selects between the link FC mode and the PFC mode.

The content of the Flow Control Receive Threshold High (FCRTH) register determines at what point the LAN controllers transmit the first PAUSE frame. The LAN controllers monitor the fullness of the receive FIFO and compares it with the contents of FCRTH. When the threshold is reached, the LAN controllers send a PAUSE frame with its pause time field equal to FCTTV.

At this time, the LAN controllers start counting an internal shadow counter (reflecting the pause time-out counter at the partner end). When the counter reaches the value indicated in FCRTV register, then, if the PAUSE condition is still valid (meaning that the buffer fullness is still above the low watermark), an XOFF message is sent again.

Once the receive buffer fullness reaches the low water mark, the LAN controllers send an XON message (a PAUSE frame with a timer value of zero). Software enables this capability with the XONE field of the FCRTL.

The LAN controllers send a PAUSE frame if it has previously sent one and the FIFO overflows. This is intended to minimize the amount of packets dropped if the first PAUSE frame did not reach its target.

13.17.2.3.3 Flow Control High Threshold — FCRTH

The LAN controllers send a PAUSE frame when the Rx packet buffer is full above the high threshold. The threshold should be large enough to overcome the worst case latency from the time that crossing the threshold is sensed until packets are not received from the link partner.

Referring to Annex O of IEEE802.1Qbb rev 2.3, worst case latency depends on three parameters:

1. Maximum frame size over the TC for which FCRTH is computed. It is referred as MaxFrame(TC).
2. Maximum frame size over the link (all TCs altogether). It is referred as MaxFrame(link).
3. Whether or not MACsec is enabled or disabled over the link.

Two values are envisaged for MaxFrame:

- 1.5 KB (Ethernet - jumbo disabled)
- 9.5 KB (jumbo enabled)

Worst case latency, which is referred as Standard Delay Value (Std DV), is given by:

Std DV = MaxFrame(TC) + MaxFrame(link) + PFC Frame + 2 x Cable Delay + 2 x Interface Delay + Higher Layer Delay + (MACSec enabled = yes) x Sec Y Transmit Delay

Std DV (bit time units) = MaxFrame(TC) + MaxFrame(link) + 672 + 2 x 5,556 + 2 x (25,600 + 8,192 + 2 x 2,048) + 6,144 + (MACSec enabled = yes) x (MaxFrame(link) + 3,200)

MaxFrame(TC) term and MaxFrame(link) term included in Sec Y Transmit Delay correspond to worst case scenarios issued by the link partner. All other terms in Std DV formula must take in account worst case incoming traffic pattern which would lead to worst case buffer utilization as per the internal architecture of Rx packet buffers in the LAN controllers.

Internal architecture of the Rx packet buffer has the following restrictions:

1. Any packet starts at 32 byte aligned address.
2. Any packet has an internal status of 32 bytes. As a result, the Rx packet buffer is used at worst conditions when the Rx packet includes 65 bytes that are posted to the host memory. Assuming that the CRC bytes are not posted to host memory then in the worst case the Rx packet buffer can be filled at 1.44 higher rate than the wire speed (69-byte packet including CRC + 8-byte preamble + 12-byte back-to-back IFS consumes 4 x 32 bytes = 128 bytes on the Rx packet buffer).
3. An additional packet from the concerned traffic class may be inserted into the Rx packet buffer due to the internal loopback switch just before it is decided to issue XOFF to the link partner.

FCRTH must be set to the size of the Rx packet buffer allocated to the TC minus the controller DV.

Table 13-44. LAN Controllers Delay Values (DV) Used For FCRTH

9.5 KB Jumbo Enabled	LAN Controllers DV
No	24 KB
No	25 KB
Yes	50 KB
Yes	35 KB
No	27 KB
No	27 KB
Yes	60 KB
Yes	45 KB

Note: 9.5 KB jumbo enabled/disabled is a global setting per port which concerns all TCs.

13.17.2.3.4 FC Low Threshold — FCRTL

The low threshold value is aimed to protect against wasted available host bandwidth. There is some latency from the time that the low threshold is crossed until the XON frame is sent and packets are received from the link partner. The low threshold must be set high enough so that the Rx packet buffer does not get empty before any new entire packets are received from the link partner. When considering data movement from the Rx packet buffer to host memory, then large packets represent the worst. Assuming the host bandwidth is about the bandwidth on the wire (when dual ports are active at a given time), and assuming a PCIe round trip is required to get the receive descriptors, we get the following formula for FCRTL:

FCRTL = 2 x MaxFrame(TC) + PCIe round trip delay

PCIe round trip delay is assumed to be ~1 μs and it must cover for worst case incoming traffic pattern (buffer utilization by 1.44 than wire rate):

FCRTL (bit time units) = 2 x MaxFrame(TC) + 1.44 x 10,000

Setting the FCRTL to lower values than expressed by the previous equation is permitted. It might simply result with potential sub-optimal use of the PCIe bus once bandwidth is available.

Table 13-45. LAN Controllers FCRTL

9.5 KB Jumbo Enabled	LAN Controllers DV
No	5 KB
No	7 KB
Yes	21 KB
Yes	7 KB

13.17.2.3.5 Packet Buffer Size

When FC is enabled, the total size of a TC packet buffer must be large enough for the Low and high thresholds. In order to avoid constant transmission of XOFF and XON frames it is recommended to add some space for hysteresis type of behavior. The difference between the two thresholds is recommended to be at least one frame size (when 9.5 KB jumbo frames are expected over the TC) and larger than a few frames in other cases (4.5 KB for instance). If the available Rx buffer is large enough, it is recommended to increase as much as possible the hysteresis budget. If the available Rx buffer is not large enough it might be required to cut both the low threshold as well as the hysteresis budget.

- For a PFC-enabled TC:
  - FCRTH = FCRTL + hysteresis budget = FCRTL + Max (MaxFrame(TC), 4.5 x 1024 B)
  - Rx packet buffer size = FCRTH + the LAN controller DV (see Section 13.17.2.3.3, "Flow Control High Threshold — FCRTH")
- For a best effort TC:
  - Rx packet buffer size = FCRTL, as the same considerations than described in Section 13.17.2.3.4, "FC Low Threshold — FCRTL" play here to avoid bubbles over PCIe

The total Rx packet buffer size available to a port for all its supported TCs is either 384 KB, 320 KB, or 256 KB, depending on the size allocated to the Flow Director table, 0 KB, 64 KB, or 128 KB, respectively.

The following table assumes four PFC-enabled TCs are defined over the port, of which two are allocated for loss less traffic types like iSCSI, etc. The table lists the recommended settings for the supported combinations. When less than 4 PFC-enabled TCs are defined, and/or when less than 8 TCs are defined, it is recommended to refer to the setting rules described in this section, in Section 13.17.2.3.3, "Flow Control High Threshold — FCRTH", and in Section 13.17.2.3.4, "FC Low Threshold — FCRTL". Note that reducing the number of TCs of a port to what is really needed, helps increasing the port throughput.

Table 13-46. Some Recommended Rx Packet Buffer Settings

Flow Director Table Size	9.5 KB Jumbo Enabled	Packet Buffer Size of Any of the 4 Best Effort TCs	Packet Buffer Size of Any of The Other 2 PFC-enabled TCs
No	No	33 KB	61 KB FCRTL = 6 KB FCRTH = 37 KB
No	Yes	27 KB	86 KB FCRTL = 21 KB FCRTH = 36 KB
No	No	32 KB	63 KB FCRTL = 6 KB FCRTH = 36 KB
No	Yes	22 KB	91 KB FCRTL = 21 KB FCRTH = 31 KB
64 KB	No	25 KB	53 KB FCRTL = 6 KB FCRTH = 29 KB
64 KB	Yes	19 KB	78 KB FCRTL = 20 KB FCRTH = 28 KB
64 KB	No	24 KB	55 KB FCRTL = 6 KB FCRTH = 28 KB
64 KB	Yes	14 KB	83 KB FCRTL = 18 KB FCRTH = 23 KB
128 KB	No	17 KB	45 KB FCRTL = 6 KB FCRTH = 21 KB
128 KB	No	16 KB	47 KB FCRTL = 6 KB FCRTH = 20 KB

Note: In some of the previous cases, it has been necessary to get compromised on the rules for hysteresis and FCRTL in order to fit the size available for Rx packet buffer.

Note: In some other cases, after having applied all the rules there was an exceeding available Rx packet buffer left that has been used to extend the hysteresis budgets.

Note: In all cases, FCRTH rule has been applied as is, since compromising on it is not allowed and extending it provides no performance benefits.

13.17.3 Inter Packet Gap (IPG) Control and Pacing

The LAN controllers support transmission pacing by extending the IPG (the gap between consecutive packets). The pacing mode enables the average data rate to be slowed in systems that cannot support the full link rate (10 GbE or 1 GbE). As listed in Table 13-47, "Pacing Speeds at 10 GbE Link Speed", the pacing modes work by stretching the IPG in proportion to the data sent. In this case the data sent is measured from the end of preamble to the last byte of the packet. No allowance is made for the preamble or default IPG when using pacing mode.

Example 13-1.

Consider a 64-byte frame. To achieve a 1 GbE data rate when link rate is LAN and packet length is 64 bytes (16 Dwords), add an additional IPG of 144 Dwords (nine times the packet size to reach 1 GbE). When added to the default IPG gives an IPG of 147 Dwords.

Example 13-2.

Consider a 65-byte frame. To achieve a 1 GbE data rate when link rate is LAN and packet length is 65 bytes (17 Dwords when rounded up) add an additional IPG of 153 Dwords (nine times the packet duration in Dwords). When added to the default IPG gives an IPG of 156 Dwords. Note that in this case, where the packet length counted in Dwords is not an integer, count any fraction of a Dword as an entire Dword for computing the additional IPG.

Table 13-47, "Pacing Speeds at 10 GbE Link Speed" lists the pacing configurations supported by the SoC LAN controller at link rates of 10 GbE. When operating at lower link speeds the pacing speed is proportional to the link speed.

Table 13-47. Pacing Speeds at 10 GbE Link Speed

Pacing Speeds (Gb/s)	Delay Inserted into IPG	Register Value
10 (10 GbE)	None	0000b
9.294196 (WAN)	1 byte for 13 transmitted	1111b
9.0	1 Dword for 9 transmitted	1001b
8.0	1 Dword for 4 transmitted	1000b
7.0	3 Dwords for 7 transmitted	0111b
6.0	2 Dwords for 3 transmitted	0110b
5.0	1 Dwords for 1 transmitted	0101b
4.0	3 Dwords for 2 transmitted	0100b
3.0	7 Dwords for 3 transmitted	0011b
2.0	4 Dwords for 1 transmitted	0010b
1.0	9 Dwords for 1 transmitted	0001b
10	None	Default

Note: Pacing is configured in the *PACE* field of the Pause and Pace (PAP) register.

13.18 Physical Functions (PF), Virtual Functions (VF) and ARI (Alternative RID Interpretation)

ATS and ARI are required to support PF and VF. Both ATS and ARI are required in order for PCIe configuration space to be able to address higher than 7 VFs PCIe configurations traditionally configures PF and VFs using 16 bits. ATS and ARI allow more (higher) than 7 functions to be addressed.

The number of VFs, in addition to the PFs, are indicated in the system shared SPI Flash section for the LAN controllers LAN0 and LAN1. A function in the shared SPI Flash image known as I/O Virtualization (IOV) is also need to be enabled. These newly created VF shows up in PCIe configuration space as base/device/function.

In short, to enable hardware based Single Root I/O Virtualization (SR-IOV) and benefit from use of VFs and the built-in Virtual Ethernet Bridge (VEB), you must have:

1. Ensure that ATS/ARI are supported in your version of BIOS.
2. Enable SR-IOV in your BIOS.
3. Use an OS that supports virtualization.
4. Enable IOV in the NVM section and indicated the # of VMs desired to create.

For further information regarding SR-IOV, refer to the published SR-IOV Primer titled *PCI-SIG* SR-IOV Primer: An Introduction to SR-IOV Technology*.

13.19 Register Map

The software-accessible registers are outlined in Table 13-12, "Base Address Registers" and are depicted here.
Figure 13-14, "Register Map" shows the associated registers from a system viewpoint.

Figure 13-14.Register Map



§ §

14 USB Combo Controller

This chapter describes the Universal Serial Bus (USB) Combo Controller. It provides USB 2.0 and USB 3.0 ports.

Figure 14-1. What is Covered in This Chapter



Table 14-1. References

Document Title	Document ID / Location
Universal Serial Bus 3.0 Specification, Revision 1.0	http://www.usb.org/developers/docs/
Universal Serial Bus Specification, Revision 2.0	http://www.usb.org/developers/docs/usb20_docs/
eXtensible Host Controller Interface for Universal Serial Bus (xHCI), Revision 1.1	https://www.intel.com/content/www/us/en/io/universal-serial-bus/extensible-host-controler-interface-usb-xhci.html
Enhanced Host Controller Interface Specification for Universal Serial Bus, Revision 1.0	https://www.intel.com/content/www/us/en/io/universal-serial-bus/ehci-specification-for-usb.html

14.1 Signal Descriptions

The signal descriptions are shown in Table 14-2. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. Also see Table 39-3.The Direction column of Table 39-3 on page 1028 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- Differential = Differential signal pair. Two pins: Positive; Negative.

Table 14-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
USB3_TX_DP[3:0] USB3_TX_DN[3:0]	O, Differential	Yes	**USB 3.0 Transmit Data:** Differential output signals from the USB Combo Controller to the FIA/PHY.
USB3_RX_DP[3:0] USB3_RX_DN[3:0]	I, Differential	Yes	**USB 3.0 Receive Data:** Differential input signals to the USB Combo Controller from the FIA/PHY.
USB2_DP[3:0] USB2_DN[3:0]	I,O, Differential	No	**USB 2.0 Transceiver Data:** Differential bi-directional signal pins.
USB_OC_N	I	No	**USB Over Current.** Active low input signal from the platform board that alerts the SoC that a VBUS over-current condition exists.
USB2_COMP	I	No	**Compensation:** The platform board must provide a 113 Ω, 1% resistor connected from this pin to VSS.

14.2 Feature List

The SoC supports up to four USB 3.0 compliant ports depending on product SKU.

The SoC provides these ports through a USB 3/USB 2 Combo Controller which is an integrated PCI Express* function, Bus 0, Device 21 (decimal), Function 0.

All ports operate in Host Mode. The USB 2.0 operation supports USB 1.X devices and a Rate Matching Hub (RMH) is provided for USB 1.1 devices.

The controller contains one eXtensible Host Controller Interface (xHCI) with software, which complies to the *eXtensible Host Controller Interface for Universal Serial Bus (xHCI), Revision 1.1*.

Note: For a USB 3.0-compliant port design, one set of the controller USB 3.0 signals and one set of the USB 2.0 signals must be routed to the same port connector. Thus for USB 3.0 specification compliance, the USB Combo Controller (xHCI) can only support four devices.

Note: USB On-The-Go (OTG) not supported.

14.2.1 USB 3.0

The USB 3.0 Super Speed data interface is dual-simplex, four-wire differential signals (2-TX and 2-RX) which are separate from the USB 2.0 signals and supports simultaneous bi-directional (full Duplex) data flows. The interface supports a bit rate of 5 Gbps with a maximum data throughput of less than 4 Gbps due to usage of an 8b/10b symbol encoding scheme and additional protocol overhead.

14.2.2 USB 2.0

The USB 2.0 data interface is half-duplex two-wire differential signals, which support unidirectional data flow with negotiated directional bus transitions. The USB 2.0 supports bit rates of:

- Low-speed (1.5 Mbps)
- Full-speed (12 Mbps)
- High-speed (480 Mbps)

For additional information refer to the *Universal Serial Bus Specification, Revision 2.0*.

Figure 14-2. USB 3.0 Cable



14.2.3 xHCI Interface

The USB 3.0 xHCI Host Controller (xHCI) supports the following features:

- Compliant with the specification for USB 1.x, 2.0 (1.5 Mbps, 12 Mbps, 480 Mbps) and USB 3.0 Super Speed (5 Gbps). Supports all USB transactions (bulk, isochronous, interrupt, control).
- USB ports support up to 32 slots and 96 end-points
- Supports xHCI software host controller interface
- Supports wakeup from suspend states S1-S5 and remote-suspend wakeup
- Per port USB disable
- Support prefetch-based pause feature
- Support of USB suspend mode including PLL turn off in S0/Sx
- Capability to use reduced Frame List Sizes
- 64-bit data and 36-bit address
- Downstream 1DW memory read and writes, upstream memory read and writes
- Intel® Direct Connect Interface (Intel® DCI) customer visible debug port
- Intel® Direct Connect Interface (Intel® DCI) over DbC
- Intel® Direct Connect Interface (Intel® DCI) over Intel® DCI OOB (Out of Band)
- xHCI Debug Capability
- EP Type based Port Lock Capability
- The following USB capabilities are not supported:
  - Port Disable Override capability
  - USB-R Capability

14.3 Architectural Overview

The following section is adopted from *eXtensible Host Controller Interface for Universal Serial Bus (xHCI), Revision 1.1*.

Table 14-3, "Universal Serial Bus, Revision 3.0 System Block Diagram" shows a conceptual block diagram of the building block layers in a USB host system that work in concert to support USB 3.0

Figure 14-3. Universal Serial Bus, Revision 3.0 System Block Diagram



The component layers are:

- **Application Software.** This software uses the services provided by one or more USB devices. Application software interfaces with USB devices through standardized interfaces provided by the Class Drivers.
- **Class Driver Software.** This software executes on the host PC corresponding to a particular "class" of USB device (Mass Storage, Human Interface, Audio, etc.). Class Driver software is typically part of the operating system or provided with the USB device.
- **USB Driver (USBD).** The USBD is a system software Bus Driver that abstracts the details of the particular Host Controller Driver for a particular operating system. The generic USB interface presented to the system by USBD is referred to as the *USB Driver Interface* or the **USBDI**.
- **eXtensible Host Controller Driver (xHCD).** xHCD provides the software layer between the Host Controller hardware and the USBD. The details of the host controller driver depend on the host controller hardware register interface definition.
- **eXtensible Host Controller (xHC).** The host controller is the specific hardware implementation of the host controller architecture. There is one host controller specification for the USB 3.0 host controller, which enables support for Low-, Full-, High- and SuperSpeed devices. The interface presented by the xHC to the system is referred to as the *eXtensible Host Controller Interface* or the **xHCI**.
- **USB Device.** This is a hardware device that expands the bus topology (hub) or performs a useful end-user function. Interactions with USB devices flow from the applications through the software and hardware layers to the USB devices.

A key feature of the USB architecture is the **Device Framework** that it presents. The Device Framework defines the interface between a USB device and a Class Driver, which is independent of the particular host controller interface that a system employs to communicate with the USB. This interface consists of a Default Pipe, and zero or more additional class defined Pipes. The Default Pipe (also referred to as the *Default Control Endpoint*) is used to enumerate and manage a USB device. It can also be used to provide access to application specific features of the device. The class defined Pipes provide specialized Quality-of-Service requirements to perform device class specific functions.

The Device Framework allows the USB architecture to separate the details of the "Bus" interface from that of the application specific ("Device") interface, resulting in a split driver model (xHCD/Class Driver). Note that in this context, Device Class refers to the portion of a USB device that performs some useful end user application specific function (e.g. Mass Storage, Audio, Human Interface, etc.).

The USB bus driver (USBD) provides a standard method of interfacing to the transport mechanisms (USB Framework) defined by the USB architecture (Isoch, Interrupt, Control, and Bulk Pipes) and the Device Class driver is where all the application specific knowledge resides. A Class Driver will also include any "value add" that a vendor may provide. As long as the USB Framework presented through the USBDI remains unchanged, the USB Class Drivers do not have to change because the USB bus driver does (e.g. to support the xHCI).

Working groups in the USB-IF have defined several standard USB Device Classes (Mass Storage, Audio, etc.). A USB device vendor may choose to define a proprietary Device Class for their product or utilize part or all of an appropriate USB-IF defined Device Class. The USB-IF defined Device Classes provide a baseline set of features, for their respective class. Several USB Device Classes are supported natively by today's Operating Systems.

Native OS support for Device Classes allows a compliant device to provide a user with basic functionality if the vendor Device Class drivers are not available, however a vendor can define their own Class Driver to add value. Many commodity USB device vendors (mice, keyboard, etc.) take advantage of those provided by OS vendors and don't bother to offer their own Class Drivers. If a vendor offers a USB device that does not fall under one of the standard USB defined Device Classes supported by an OS then they shall offer their own Class Driver.

The xHCI is used for all communications to devices connected through the Root Hub ports of the USB 3.0 host controller.

The xHCI architecture allows the USB 3.0 host controller to provide USB functionality for all speed devices without requiring, as in previous generations, companion controllers along with the associated software support for their respective drivers. The enhanced features of the xHCI architecture are key to delivering this simplified operating environment.

Note that the Figure below does not imply a particular xHC implementation, however the functional partitioning that it illustrates is useful for this discussion. The Host Interface Logic manages the Registers and DMA associated with the xHC.

Figure 14-4. USB 3.0 eXtensible Host Controller



The xHC always manages the respective speed USB devices connected to its Root Hub ports. Depending on the implementation, the resources of a USB bus instance (bandwidth, device addressability, etc.) may be presented on each root hub port, shared across multiple root hub ports, or a combination of allocations.

This specification defines the registers and interfaces for the eXtensible Host Controller Interface.

14.3.1 xHCI Interface Architecture

The xHCI interface defines three interface spaces (refer to in the Figure below):

- **Host Configuration Space.** Every xHC implementation shall include a means of identifying and enumerating the host controller by system software. This specification provides a PCI example of the Host Configuration Space, which is referred to as **PCI Config Space**. The PCI Config Space definition provides a working example of configuration space use for system xHC enumeration and resource (interrupt, power, virtualization, etc.) management.
- **MMIO Space.** The Register Space represents the hardware registers presented by the xHC to system software that reside in the Memory Address Space. The Register Space provides for the implementation-specific parameters defined in the xHCI normal and Extended Capabilities registers, the Operational and Runtime control and status registers, and the Doorbell Array used to flag accesses to individual USB devices. This space, normally referred to as I/O space, is implemented as Memory-Mapped I/O (**MMIO**) space.
- **Host Memory.** This space is defined by the control data structures (Device Context Base Address Array, Device Contexts, Transfer Rings, etc.) and data buffers that are allocated and managed by the xHC Driver to enable the endpoint traffic of individual devices. This space is allocated in the Kernel and User areas of the Memory Address Space.

Figure 14-5. General Architecture of the eXtensible Host Controller Interface



The xHCI provides support for two categories of USB transfer types: asynchronous and periodic. Isochronous and Interrupt transfers are Periodic transfer types. Asynchronous transfer types include Control and Bulk. Figure 3 illustrates that the xHCI provides a homogeneous mechanism (Transfer Rings) for each category of transfer type.

The USB Base Address Register (BAR) in the PCI Config Space points to the base address of the xHC register interface. The xHC register interface consists of 4 major components: Capability Registers, Operational Registers, Runtime Registers, and the Doorbell Array. The Operational and Capability Registers are concatenated in MMIO space. The Runtime Registers are actually just an extension of the Operational Registers. Their partitioning allows the xHC to better support virtualization, by allowing the Runtime Registers to reside on a separate page boundary. A xHCI Capabilities Pointer mechanism (similar to that defined by PCI) is presented in the Capability Registers to point to new or optional capabilities of an xHC implementation.

The ***Capability Registers*** specify read-only limits, restrictions and capabilities of the host controller implementation. These values are used as parameters to the host controller driver.

The ***Runtime*** and ***Operational Registers*** specify host controller configuration and runtime modifiable state, and are used by system software to control and monitor the operational state of the host controller. These registers are partitioned as a function of those that are heavily accessed during runtime and those that are accessed only at initialization time or only lightly during runtime to better support virtualization of the xHCI.

The ***xHCI Extended Capabilities*** specify optional features of an xHC implementation, as well as providing the ability to add new capabilities to implementations after the publication of this specification.

The ***Doorbell Array*** is an array of up to 256 Doorbell Registers, which supports up to 255 USB devices or hubs. Each ***Doorbell Register*** provides system software with a mechanism for notifying the xHC if it has Slot or Endpoint related work to perform. A *DB Target* field in the Doorbell Register is written with a value that identifies the reason for **"ringing"** the doorbell. Doorbell Register 0 is allocated to the Host Controller for Command Ring management.

The term ***Device Slot*** is used as a generic reference to a set of xHCI data structures associated with an individual USB device. Each device is represented by an entry in the *Device Context Base Address Array*, a register in the *Doorbell Array* register, and a device's *Device Context*. The term ***Slot ID*** refers to the index used to identify a specific *Device Slot*. For example the value of *Slot ID* will be used as an index to identify a specific entry in the *Device Context Base Address Array*.

The ***Device Context Base Address Array*** supports up to 255 USB devices or hubs, where each element in the array is a pointer to a *Device Context* data structure.

The **Command Ring** is used by software to pass device and host controller related commands to the xHC. The *Command Ring* shall be treated as read-only by the xHC. Refer to section 4.9.3 for a discussion of Command Ring Management.

The **Event Ring** is used by the xHC to pass command completion and asynchronous events to software. The *Event Ring* shall be treated as read-only by system software. Refer to section 4.9.4 for a discussion of Event Ring Management.

A ***Transfer Ring*** is used by software to schedule work items for a single USB Endpoint. A Transfer Ring is organized as a circular queue of ***Transfer Descriptor*** (TD) data structures, where each *Transfer Descriptor* defines one or more Data Buffers that will be moved to or from the USB. *Transfer Rings* are treated as read-only by the xHC. Refer to section 4.9.2 for a discussion of Transfer Ring Management.

All three types of rings support the ability for system software to grow or shrink them while they are active. Special TDs written to the Transfer and Command rings allow software to change their size, however since the Event Ring is read-only to software, the **Event Ring Segment Table** is provided so that software may modify its size.

14.4 xHCI Data Structures

The xHC is expected to run in virtual memory environments where the size of a contiguous block of physical memory will be limited by the Page size of the system. The data structures that the xHC uses to manage devices and endpoints are designed to accommodate this limitation, by either keeping the data structure under 4K Bytes (the minimum Page size supported), or providing mechanisms to link non-contiguous blocks of physical memory to form larger, logically contiguous data structures, e.g. circular queues of data structures that point to the data buffers used for transferring USB data to or from the host. The data buffers referenced by these data structures may be byte aligned and reference from 1 to 64K bytes of contiguous physical data.

Please refer to the xHCI Specification for further information.

14.5 Command Interface

To manage the xHC and the devices attached to it, the xHC provides an independent Command Ring interface. A work item on a Command Ring is called a *Command Descriptor* (CD). Command Ring operation is very similar to that of Transfer Rings, software issues a command to the xHC by placing a CD on the Command Ring then rings the Host Controller doorbell. The size of the Command Ring can be modified using the same Link TRB mechanism that Transfer Rings use. All commands result in a *Command Completion Event* being placed on the Event Ring, which reports the completion status of the command. Commands are executed by the xHC in the order that they are placed on the Command Ring. System software may add CDs to the Command Ring while it is running, however the execution of CDs should be stopped if software wants to delete or reorder (i.e. raise the priority of) scheduled CDs. Special Command Ring controls allow commands to be stopped or aborted.

Please refer to the *Enhanced Host Controller Interface Specification for Universal Serial Bus, Revision 1.0* for further information.

14.6 Root Hub Management

The host controller of a USB bus is required to implement Root Hub functionality. The Operational Register space contains port registers that provide the hardware status and control needed to manage each port within the USB Specification. An xHC Root Hub may provide USB 2.0 and USB 3.0 Root hub ports to support Low-, Full-, or High-Speed as well as SuperSpeed devices. The host controller traverses the Transfer Rings and encounters work items that result in the host controller executing USB transactions. These transactions are routed to the Root Hub port associated with the attached downstream USB device. The port registers provide system software with the control and status information required to manipulate the port in accordance with the USB Specification. The supported features include: detecting device connects, disconnects, performing device resets, manipulating port power and managing port power management capabilities. System software should provide an abstraction to the USB system software stack that allows the Root Hub ports to be manipulated by the system as if they were ports on an external hub.

14.7 Operational Model

Please refer to the xHCI Specification Chapter 4 “Operational Model” for information related to the eXtensible Host Controller Interface (xHCI) hardware and eXtensible Host Controller Driver (xHCD) (generally referred to as system software).

The chapter includes significant operational feature of the eXtensible Host Controller (xHC) and operational model requirements for the xHC hardware.

14.8 Supported Transaction Types

The controller is discovered as bus 0, device 21, function 0.

Table 14-3, "Transaction Type Supported by USB Block" shows the transaction types supported by the USB block:

Table 14-3. Transaction Type Supported by USB Block

Transaction Type	Upstream	Downstream
Memory Read (32/64 bits)	Yes	Yes
Memory Write (32/64 bits)	Yes	Yes
I/O Read	No	No
I/O Write	No	No
Configuration Read0	No	Yes
Configuration Write0	No	Yes
Configuration Read1	No	No
Configuration Write1	No	No
Message	No	No
MessageD	No	No
Completion	Yes	Yes
CompletionD	Yes	Yes

14.9 Reset Requirements

Table 14-4, "Reset Signal Information" shows the reset signal information used in the USB Controller.

Table 14-4. Reset Signal Information

Reset Signal	Power Well	Assertion	Description
AON Power Good Based Reset	SUS	Async Power Good Removal	Power Good based reset to be used for isolation
Reset	SUS	Async SoC Controlled conditions	Internally synchronous to SUS clock, after AON power is stable and reset sequence is complete.
VNN Power Good Based Reset	VNN/CORE	Async Power Good Removal	Power Good based reset to be used for isolation
SBI Reset	VNN/CORE	Async Fabric Reset	Internally Synchronous to Side Clock.
Fabric Reset	VNN/CORE	Async Host Partition Reset	Internally Synchronous to backbone clock.

14.10 USB Power Management – Link States

Table 14-5, "USB 2.0 Link States and Power Actions" explains the USB 2.0 link states and power actions. Each deeper link state includes actions from prior/shallower link states unless explicitly stated otherwise. So details are not repeated in each deeper link state.

Table 14-5. USB 2.0 Link States and Power Actions

Link State	Entry	Exit	Core Action	PHY Action
USB2				
U0 Idle	All scheduled transactions completed for BI. Minimum time left before next BI.	Start of new BI (early indication used to wake PLL).	Fabric Clock allowed to be trunkgated if other ports do not need it. Fabric PLL allowed to be shut down if no other port needs it. All RFpower gating.	x and Rx current sources and Bias circuits are actively managed. Tx shut down if Receiving. Rx shut down if Transmitting.
U2	L1 is enabled. Device on root port supports L1. Device on root port accepts L1 entry required.	Host DB ring. Device initiates exit from L1. Optional timer based wake for non-compliant devices.	Update LTR. Clock gate USB2 link clock at port level. Shut down USB2 PLL if all ports are in L1 or deeper. Indicate "suspend" to PHY.	Shut down HS clocks. Power gate core portion of PHY.
U3	SW places port in U3.	SW places port in U0.	Update LTR to "no requirement". Allow D3 based actions (implicit). Indicate L1 "suspend" to PHY.	Power gate core portion of PHY.
Disconnected			Update LTR to "no requirement". Allow D3 based actions (implicit). Indicate L1 "suspend" to PHY.	Power gate core portion of PHY.

Table 14-6, "USB 3.0 Link States and Power Actions" explains the USB 3.0 link states and power actions. Each deeper link state includes actions from prior/shallower link states unless explicitly stated otherwise. So details are not repeated in each deeper link state.

Table 14-6. USB 3.0 Link States and Power Actions

Link State	Entry	Exit	Core Action	PHY Action
USB3				
U0			Update LTR based on received BELT messages	
U0 Idle	All scheduled transactions completed for BI. Minimum time left before next BI.	Start of new BI (early indication used to wake PLL).	Fabric Clock allowed to be trunkgated if other ports do not need it. Fabric PLL allowed to be shut down if no other port needs it. All RFpower gating.	None.
U1	U1 idle time expires.	DB ring or Periodic transaction scheduled. Device initiated exit. U2 timer expires.	Link clocks gated at port level. PIPE state = PS1.	Tx OFF. Rx OFF. Maintain common mode.
U2	U2 idle timer expires.	DB ring or Periodic transaction scheduled. Device initiated exit.	Link clocks gated at port level. PIPE state = PS3. Indicate USB 3.0 link PLL can be shut off. Indicate Morhy port can be power gated. Aux clock gated at the partition level. Requires: Timer tick for RxDetect timers.	PLL off. Tx, Rx off. Common mode off. Power gate core well.
U3	SW initiated.	SW initiated.	Allow D3 actions similar to U2.	Similar to U2.
RxDetect.	NA	NA	PIPE state = PS3 (after first RxDetect). Similar to U3.	Similar to U3.

14.11 Error Condition and Handling

The USB 3.0 port Error handling is as per USB3 and xHCI Specifications.

14.12 Debug Capability (DbC)

The USB Debug Capability (DbC) is provided by the SoC USB eXtensible Host Controller (xHC). DbC is an optional USB functionality that enables low-level system debug over USB. The xHC Interface (xHCI) debugging capability provides a means of connecting two systems where one system is a Debug Host and the other a Debug Target (System Under Test). See the section on DbC in the *eXtensible Host Controller Interface for Universal Serial Bus (xHCI), Revision 1.1*. Also see Section 38.4.1, "Debug Capability (DbC)" on page 988, in this document.

14.13 Register Map

Figure 14-6 shows the associated registers from a system software viewpoint.

Figure 14-6. Register Map



14.13.1 PCI Configuration and Capabilities

Table 14-7. Configuration and Capabilities Register Map (Sheet 1 of 2)

Offset from Configuration Space of B0:D21:F0 (hex)	Register Short Name	Description
Standard Type 0 PCI Configuration Registers		
0	VID	Vendor ID
2	DID	Device ID
4	CMD	Command
6	STS	Device Status
8	RID	Revision ID
9	PI	Programming Interface
A	SCC	Sub Class Code
B	BCC	Base Class Code
D	MLT	Master Latency Timer
E	HT	Header Type
10	MBAR	Memory Base Address
2C	SSVID	USB Subsystem Vendor ID
2E	SSID	USB Subsystem ID
34	CAP_PTR	Capabilities Pointer
3C	ILINE	Interrupt Line
3D	IPIN	Interrupt Pin
PCI Power Management Capability		
70	PM_CID	PCI Power Management Capability ID
71	PM_NEXT	Next Item Pointer #1
72	PM_CAP	Power Management Capabilities
74	PM_CS	Power Management Control/Status
Message Signaled Interrupt Capability		
80	MSI_CID	Message Signaled Interrupt CID
81	MSI_NEXT	Next item pointer
82	MSI_MCTL	Message Signaled Interrupt Message Control
84	MSI_MAD	Message Signaled Interrupt Message Address
88	MSI_MUAD	Message Signaled Interrupt Upper Address
8C	MSI_MD	Message Signaled Interrupt Message Data

Table 14-7. Configuration and Capabilities Register Map (Sheet 2 of 2)

Offset from Configuration Space of B0:D21:F0 (hex)	Register Short Name	Description
Device-Specific PCI Configuration Registers		
40	XHCC1	XHC System Bus Configuration 1
44	XHCC2	XHC System Bus Configuration 2
50	XHCLKGTEN	Clock Gatings
58	AUDSYNC	Audio Time Synchronization
60	SBRN	Serial Bus Release Number
61	FLADJ	Frame Length Adjustment
62	BESL	Best Effort Service Latency
90	DEVIDLE	Device Idle Capability
94	VSHDR	Vendor Specific Header
98	SWLTRPTR	SW LTR POINTER
9C	DEVIDLEPTR	Device Idle Pointer Register
A0	DEVIDLEPOL	Device Idle Power ON Latency
A4	HSCFG2	High Speed Configuration 2
B0	U2OCM1	XHCI USB2 Overcurrent Pin Mapping 1
D0	U3OCM1	XHCI USB3 Overcurrent Pin Mapping 1
FC	XHCC3	XHCC3

14.13.2 Memory-Mapped Registers

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 1 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
eXtensible Host Controller (xHCI) Capability Registers			
MBAR	0	CAPLENGTH	Capability Registers Length
MBAR	2	HCIVERSION	Host Controller Interface Version Number
MBAR	4	HCSPARAMS1	Structural Parameters 1
MBAR	8	HCSPARAMS2	Structural Parameters 2
MBAR	C	HCSPARAMS3	Structural Parameters 3
MBAR	10	HCCPARAMS	Capability Parameters
MBAR	14	DBOFF	Doorbell Offset
MBAR	18	RTSOFF	Runtime Register Space Offset
xHCI Operational Registers			
MBAR	80	USBCMD	USB Command
MBAR	84	USBSTS	USB Status
MBAR	88	PAGESIZE	Page Size
MBAR	94	DNCTRL	Device Notification Control
MBAR	98	CRCR_LO	Command Ring Low
MBAR	9C	CRCR_HI	Command Ring High
MBAR	B0	DCBAAP_LO	Device Context Base Address Array Pointer Low
MBAR	B4	DCBAAP_HI	Device Context Base Address Array Pointer High
MBAR	B8	CONFIG	Configure

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 2 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
xHCI USB Port Registers			
MBAR	480	PORTSC1	Port Status and Control USB2
MBAR	484	PORTPMSC1	Port Power Management Status and Control USB2
MBAR	48C	PORTHLPMC1	Port X Hardware LPM Control Register
MBAR	490	PORTSC2	Port Status and Control USB2
MBAR	494	PORTPMSC2	Port Power Management Status and Control USB2
MBAR	49C	PORTHLPMC2	Port X Hardware LPM Control Register
MBAR	4A0	PORTSC3	Port Status and Control USB2
MBAR	4A4	PORTPMSC3	Port Power Management Status and Control USB2
MBAR	4AC	PORTHLPMC3	Port X Hardware LPM Control Register
MBAR	4B0	PORTSC4	Port Status and Control USB2
MBAR	4B4	PORTPMSC4	Port Power Management Status and Control USB2
MBAR	4BC	PORTHLPMC4	Port X Hardware LPM Control Register
MBAR	4C0	PORTSC5	Port Status and Control USB3
MBAR	4C4	PORTPMSC5	Port Power Management Status and Control USB3
MBAR	4C8	PORTLI5	USB3 Port Link Info
MBAR	4D0	PORTSC6	Port Status and Control USB3
MBAR	4D4	PORTPMSC6	Port Power Management Status and Control USB3
MBAR	4D8	PORTLI6	USB3 Port Link Info
MBAR	4E0	PORTSC7	Port Status and Control USB3
MBAR	4E4	PORTPMSC7	Port Power Management Status and Control USB3
MBAR	4E8	PORTLI7	USB3 Port Link Info
MBAR	4F0	PORTSC8	Port Status and Control USB3
MBAR	4F4	PORTPMSC8	Port Power Management Status and Control USB3
MBAR	4F8	PORTLI8	USB3 Port Link Info

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 3 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
Host Controller Runtime Registers			
MBAR	2000	RTMFINDEX	Microframe Index
MBAR	2020	IMAN0	Interrupter 1 Management
MBAR	2024	IMOD0	Interrupter 1 Moderation
MBAR	2028	ERSTSZ0	Event Ring Segment Table Size 1
MBAR	2030	ERSTBA_LO0	Event Ring Segment Table Base Address Low 1
MBAR	2034	ERSTBA_HI0	Event Ring Segment Table Base Address High 1
MBAR	2038	ERDP_LO0	Event Ring Dequeue Pointer Low 1
MBAR	203C	ERDP_HI0	Event Ring Dequeue Pointer High 1
MBAR	2040	IMAN1	Interrupter 2 Management
MBAR	2044	IMOD1	Interrupter 2 Moderation
MBAR	2048	ERSTSZ1	Event Ring Segment Table Size 2
MBAR	2050	ERSTBA_LO1	Event Ring Segment Table Base Address Low 2
MBAR	2054	ERSTBA_HI1	Event Ring Segment Table Base Address High 2
MBAR	2058	ERDP_LO1	Event Ring Dequeue Pointer Low 2
MBAR	205C	ERDP_HI1	Event Ring Dequeue Pointer High 2
MBAR	2060	IMAN2	Interrupter 3 Management
MBAR	2064	IMOD2	Interrupter 3 Moderation
MBAR	2068	ERSTSZ2	Event Ring Segment Table Size 3
MBAR	2070	ERSTBA_LO2	Event Ring Segment Table Base Address Low 3
MBAR	2074	ERSTBA_HI2	Event Ring Segment Table Base Address High 3
MBAR	2078	ERDP_LO2	Event Ring Dequeue Pointer Low 3
MBAR	207C	ERDP_HI2	Event Ring Dequeue Pointer High 3
MBAR	2080	IMAN3	Interrupter 4 Management
MBAR	2084	IMOD3	Interrupter 4 Moderation
MBAR	2088	ERSTSZ3	Event Ring Segment Table Size 4
MBAR	2090	ERSTBA_LO3	Event Ring Segment Table Base Address Low 4
MBAR	2094	ERSTBA_HI3	Event Ring Segment Table Base Address High 4
MBAR	2098	ERDP_LO3	Event Ring Dequeue Pointer Low 4
MBAR	209C	ERDP_HI3	Event Ring Dequeue Pointer High 4
MBAR	20A0	IMAN4	Interrupter 5 Management
MBAR	20A4	IMOD4	Interrupter 5 Moderation
MBAR	20A8	ERSTSZ4	Event Ring Segment Table Size 5

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 4 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
Host Controller Runtime Registers (continued)			
MBAR	20B0	ERSTBA_LO4	Event Ring Segment Table Base Address Low 5
MBAR	20B4	ERSTBA_HI4	Event Ring Segment Table Base Address High 5
MBAR	20B8	ERDP_LO4	Event Ring Dequeue Pointer Low 5
MBAR	20BC	ERDP_HI4	Event Ring Dequeue Pointer High 5
MBAR	20C0	IMAN5	Interrupter 6 Management
MBAR	20C4	IMOD5	Interrupter 6 Moderation
MBAR	20C8	ERSTSZ5	Event Ring Segment Table Size 6
MBAR	20D0	ERSTBA_LO5	Event Ring Segment Table Base Address Low 6
MBAR	20D4	ERSTBA_HI5	Event Ring Segment Table Base Address High 6
MBAR	20D8	ERDP_LO5	Event Ring Dequeue Pointer Low 6
MBAR	20DC	ERDP_HI5	Event Ring Dequeue Pointer High 6
MBAR	20E0	IMAN6	Interrupter 7 Management
MBAR	20E4	IMOD6	Interrupter 7 Moderation
MBAR	20E8	ERSTSZ6	Event Ring Segment Table Size 7
MBAR	20F0	ERSTBA_LO6	Event Ring Segment Table Base Address Low 7
MBAR	20F4	ERSTBA_HI6	Event Ring Segment Table Base Address High 7
MBAR	20F8	ERDP_LO6	Event Ring Dequeue Pointer Low 7
MBAR	20FC	ERDP_HI6	Event Ring Dequeue Pointer High 7
MBAR	2100	IMAN7	Interrupter 8 Management
MBAR	2104	IMOD7	Interrupter 8 Moderation
MBAR	2108	ERSTSZ7	Event Ring Segment Table Size 8
MBAR	2110	ERSTBA_LO7	Event Ring Segment Table Base Address Low 8
MBAR	2114	ERSTBA_HI7	Event Ring Segment Table Base Address High 8
MBAR	2118	ERDP_LO7	Event Ring Dequeue Pointer Low 8
MBAR	211C	ERDP_HI7	Event Ring Dequeue Pointer High 8

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 5 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
Doorbell Registers			
MBAR	3000	DB0	Door Bell 1
MBAR	3004	DB1	Door Bell 2
MBAR	3008	DB2	Door Bell 3
MBAR	300C	DB3	Door Bell 4
MBAR	3010	DB4	Door Bell 5
MBAR	3014	DB5	Door Bell 6
MBAR	3018	DB6	Door Bell 7
MBAR	301C	DB7	Door Bell 8
MBAR	3020	DB8	Door Bell 9
MBAR	3024	DB9	Door Bell 10
MBAR	3028	DB10	Door Bell 11
MBAR	302C	DB11	Door Bell 12
MBAR	3030	DB12	Door Bell 13
MBAR	3034	DB13	Door Bell 14
MBAR	3038	DB14	Door Bell 15
MBAR	303C	DB15	Door Bell 16
MBAR	3040	DB16	Door Bell 17
MBAR	3044	DB17	Door Bell 18
MBAR	3048	DB18	Door Bell 19
MBAR	304C	DB19	Door Bell 20
MBAR	3050	DB20	Door Bell 21
MBAR	3054	DB21	Door Bell 22
MBAR	3058	DB22	Door Bell 23
MBAR	305C	DB23	Door Bell 24
MBAR	3060	DB24	Door Bell 25
MBAR	3064	DB25	Door Bell 26
MBAR	3068	DB26	Door Bell 27
MBAR	306C	DB27	Door Bell 28
MBAR	3070	DB28	Door Bell 29
MBAR	3074	DB29	Door Bell 30
MBAR	3078	DB30	Door Bell 31
MBAR	307C	DB31	Door Bell 32
MBAR	3080	DB32	Door Bell 32

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 6 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
xHCI Extended Capability Pointer Registers			
MBAR	8000	XECP_SUPP_USB2_0	XECP_SUPP_USB2_0
MBAR	8004	XECP_SUPP_USB2_1	XECP_SUPP_USB2_1
MBAR	8008	XECP_SUPP_USB2_2	XECP_SUPP_USB2_2
MBAR	8010	XECP_SUPP_USB2_3	XECP_SUPP_USB2_3 (Full Speed)
MBAR	8014	XECP_SUPP_USB2_4	XECP_SUPP_USB2_4 (Low Speed)
MBAR	8018	XECP_SUPP_USB2_5	XECP_SUPP_USB2_5 (High Speed)
MBAR	8020	XECP_SUPP_USB3_0	XECP_SUPP_USB3_0
MBAR	8024	XECP_SUPP_USB3_1	XECP_SUPP_USB3_1
MBAR	8028	XECP_SUPP_USB3_2	XECP_SUPP_USB3_2
MBAR	8030	XECP_SUPP_USB3_3	XECP_SUPP_USB3_3
MBAR	8034	XECP_SUPP_USB3_4	XECP_SUPP_USB3_4
MBAR	8038	XECP_SUPP_USB3_5	XECP_SUPP_USB3_5
MBAR	803C	XECP_SUPP_USB3_6	XECP_SUPP_USB3_6
MBAR	8040	XECP_SUPP_USB3_7	XECP_SUPP_USB3_7
MBAR	8044	XECP_SUPP_USB3_8	XECP_SUPP_USB3_8
MBAR	8048	XECP_SUPP_USB3_9	XECP_SUPP_USB3_9
xHCI Extended Capability Pointer Registers			
MBAR	8070	HOST_CTRL_CAP_REG	Host Controller Capability
MBAR	8078	HOST_CLR_MASK_REG	Override EP Flow Control
MBAR	807C	HOST_CLR_IN_EP_VALID_REG	Clear Active IN EP ID Control
MBAR	8080	HOST_CLR_PMASK_REG	Clear Poll Mask Control
MBAR	8094	HOST_CTRL_SCH_REG	Host Control Scheduler
MBAR	80A0	HOST_CTRL_PORT_CTRL	Global Port Control
MBAR	80A4	PMCTRL_REG	Power Management Control
MBAR	80A8	PGCBCTRL_REG	PGCB Control
MBAR	80AC	DOI3CTRL_REG	D0I3 Control
MBAR	80B0	HOST_CTRL_MISC_REG	HOST_CTRL_MISC_REG
MBAR	80B4	HOST_CTRL_MISC_REG2	HOST_CTRL_MISC_REG2
MBAR	80B8	SSPE_REG	SSPE_REG
MBAR	80BC	SSPITPE	
MBAR	80C0	AUX_CTRL_REG	AUX Reset Control
MBAR	80C4	HOST_BW_OV_SS_REG	Super Speed Bandwidth Overload
MBAR	80C8	HOST_BW_OV_HS_REG	High Speed TT Bandwidth Overload
MBAR	80CC	HOST_BW_OV_FS_LS_REG	Bandwidth Overload Full Low Speed
MBAR	80D0	HOST_BW_OV_SYS_REG	System Bandwidth Overload
MBAR	80D4	HOST_CTRL_SCH_ASYNC_DELAY_REG	Scheduler Async Delay
MBAR	80E0	AUX_CTRL_REG1	AUX Power Management Control

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 7 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
xHCI Extended Capability Pointer Registers (continued)			
MBAR	80E4	BATTERY_CHARGE_REG	Battery Charge
MBAR	80E8	HOST_CTRL_WATERMARK_REG	Port Watermark
MBAR	80EC	HOST_CTRL_PORT_LINK_REG	SuperSpeed Port Link Control
MBAR	80F0	USB2_LINK_MGR_CTRL_REG1	USB2 Port Link Control 1
MBAR	80F4	USB2_LINK_MGR_CTRL_REG2	USB2 Port Link Control 2
MBAR	80F8	USB2_LINK_MGR_CTRL_REG3	USB2 Port Link Control 3
MBAR	80FC	USB2_LINK_MGR_CTRL_REG4	USB2 Port Link Control 4
MBAR	8100	HOST_CTRL_BW_CTRL_REG	Bandwidth Calc Control
MBAR	8108	HOST_IF_CTRL_REG	Host Interface Control
MBAR	810C	HOST_BW_OV_BURST_REG	Bandwidth Overload Burst
MBAR	8128	HOST_CTRL_BW_MAX_REG	USB Max Bandwidth Control 4
MBAR	8130	LINESTATE_DEBUG_REG	USB2 Linestate Debug
MBAR	8134	USB2_PROTOCOL_GAP_TIMER_REG	USB2 Protocol Gap Timer
MBAR	813C	USB2_PROTOCOL_BTO_TIMER_REG	USB2 Protocol Bus Timeout Timer
MBAR	8140	PWR_SCHED_CTRL0	Power Scheduler Control-0
MBAR	8144	PWR_SCHED_CTRL2	Power Scheduler Control-2
MBAR	8154	AUX_CTRL_REG2	AUX Power Management Control
MBAR	8164	USB2_PHY_PMC	USB2 PHY Power Management Control
MBAR	8168	USB_PGC	USB Power Gating Control
MBAR	816C	XHCI_AUX_CCR	xHCI Aux Clock Control Register
MBAR	8170	USB_LPM_PARAM	USB LPM Parameters
MBAR	8174	XLTP_LTV1	xHC Latency Tolerance Parameters - LTV Control
MBAR	8178	XLTP_LTV2	xHC Latency Tolerance Parameters LTV Control 2
MBAR	817C	XLTP_HITC	xHC Latency Tolerance Parameters - High Idle Time Control
MBAR	8180	XLTP_MITC	xHC Latency Tolerance Parameters - Medium Idle Time Control
MBAR	8184	XLTP_LITC	xHC Latency Tolerance Parameters Low Idle Time Control
MBAR	8188	HOST_CTRL_BW_MAX3_REG	HOST_CTRL_BW_MAX3_REG
MBAR	8198	PDDIS_REG	PDDIS_REG
MBAR	819C	THRM_HOST_CTRL_REG	THRM_HOST_CTRL_REG
MBAR	81A0	LFPS_PM_CTRL_REG	LFPS_PM_CTRL_REG
MBAR	81A4	U2PDM	U2PDM
MBAR	81A8	U2PCM	U2PCM
MBAR	81AC	U3PDM	U3PDM
MBAR	81B0	U3PCM	U3PCM

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 8 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
xHCI Extended Capability Pointer Registers (continued)			
MBAR	81B4	THRM_HOST_CTRL_REG2	THRM_HOST_CTRL_REG2
MBAR	81B8	LFPSONCOUNT_REG	LFPSONCOUNT_REG
MBAR	81BC	D0i2_CTRL_REG	
MBAR	81C0	D0i2_SCH_ALARM_CTRL_REG	
MBAR	81C4	USB2PMCTRL_REG	
MBAR	83F8	ECC_PARITY_ERROR_LOG_REG	ECC_PARITY_ERROR_LOG_REG
MBAR	83FC	ECC_POISONING_CTRL_REG	ECC_POISONING_CTRL_REG
MBAR	8400	USB2_PORT_STATE_REG	USB2_PORT_STATE_REG
MBAR	8408	USB3_PORT_STATE_REG	USB2_PORT_STATE_REG
MBAR	8410	FUS1_REG	FUS1_REG
MBAR	8414	FUS2_REG	FUS2_REG
MBAR	8418	FUS3_REG	FUS3_REG
MBAR	841C	STRAP1_REG	STRAP1_REG
MBAR	8420	STRAP2_REG	STRAP2_REG
MBAR	8424	STRAP3_REG	STRAP3_REG
MBAR	8430	DFT_REG1	DFT_REG1
MBAR	8434	DFT_REG2	DFT_REG2
MBAR	8438	DFT_REG3	DFT_REG3
MBAR	843C	DFT_REG4	dft_reg4
MBAR	8440	DFT_REG5	dft_reg5
MBAR	8448	XECP_CMDM_STS0	XECP_CMDM_STS0
MBAR	844C	XECP_CMDM_STS1	XECP_CMDM_STS1
MBAR	8450	XECP_CMDM_STS2	XECP_CMDM_STS2
MBAR	8454	XECP_CMDM_STS3	XECP_CMDM_STS3
MBAR	8458	XECP_CMDM_STS4	XECP_CMDM_STS4
MBAR	845C	XECP_CMDM_STS5	XECP_CMDM_STS5
MBAR	8460	UPORTS_PON_RST_REG	AUX Power PHY Reset
MBAR	8464	HOST_IF_LAT_TOL_CTRL_REG0	Latency Tolerance Control 0

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 9 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
USB Legacy Support Capability Registers			
MBAR	846C	USBLEGSUP	USB Legacy Support Capability
MBAR	8470	USBLEGCTLSTS	USB Legacy Support Control Status
USB Port Disable Override Capability Registers			
MBAR	84F4	PDO_CAPABILITY	Port Disable Override capability register
MBAR	84F8	USB2PDO	USB2 Port Disable Override
MBAR	84FC	USB3PDO	USB3 Port Disable Override
Hardware State Capability Registers			
MBAR	8500	HW_STATE_CAPABILITY	HW state capability register
MBAR	8504	HW_STATE_REG1	HW state register 1
MBAR	8508	HW_STATE_REG2	HW state register 2
MBAR	850C	HW_STATE_REG3	HW state register 3
MBAR	8510	HW_STATE_REG4	HW state register 4

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 10 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
Configuration Mirror Capability Registers			
MBAR	8600	CONFIG_MIRROR_CAPABILITY	CONFIG mirror capability register
MBAR	8604	CMD_MMIO	Command
MBAR	8606	STS_MMIO	Device Status
MBAR	8608	RID_MMIO	Revision ID
MBAR	8609	PI_MMIO	Programming Interface
MBAR	860A	SCC_MMIO	Sub Class Code
MBAR	860B	BCC_MMIO	Base Class Code
MBAR	860D	MLT_MMIO	Master Latency Timer
MBAR	860E	HT_MMIO	Header Type
MBAR	8610	MBAR_MMIO	Memory Base Address
MBAR	862E	SSID_MMIO	USB Subsystem ID
MBAR	8634	CAP_PTR_MMIO	Capabilities Pointer
MBAR	863C	ILINE_MMIO	Interrupt Line
MBAR	863D	IPIN_MMIO	Interrupt Pin
MBAR	8640	XHCC1_MMIO	XHC System Bus Configuration 1
MBAR	8644	XHCC2_MMIO	XHC System Bus Configuration 2
MBAR	8650	XHCLKGTEN_MMIO	Clock Gating
MBAR	8658	AUDSYNC_MMIO	Audio Time Synchronization
MBAR	8660	SBRN_MMIO	Serial Bus Release Number
MBAR	8661	FLADJ_MMIO	Frame Length Adjustment
MBAR	8662	BESL_MMIO	Best Effort Service Latency
MBAR	8670	PM_CID_MMIO	PCI Power Management Capability ID
MBAR	8671	PM_NEXT_MMIO	Next Item Pointer #1
MBAR	8672	PM_CAP_MMIO	Power Management Capabilities
MBAR	8674	PM_CS_MMIO	Power Management Control/Status
MBAR	8680	MSI_CID_MMIO	Message Signaled Interrupt CID
MBAR	8681	MSI_NEXT_MMIO	Next item pointer
MBAR	8682	MSI_MCTL_MMIO	Message Signaled Interrupt Message Control
MBAR	8684	MSI_MAD_MMIO	Message Signaled Interrupt Message Address
MBAR	8688	MSI_MUAD_MMIO	Message Signaled Interrupt Upper Address
MBAR	868C	MSI_MD_MMIO	Message Signaled Interrupt Message Data
MBAR	8690	DEVIDLE_MMIO	Device Idle Capability
MBAR	8694	VSHDR_MMIO	Vendor Specific Header
MBAR	8698	SWLTRPTR_MMIO	SW LTR POINTER
MBAR	869C	DEVIDLEPTR_MMIO	Device Idle Pointer Register

Table 14-8. Relocatable Memory-Mapped Registers (Sheet 11 of 11)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
Configuration Mirror Capability Registers (continued)			
MBAR	86A0	DEVIDLEPOL_MMIO	Device Idle Power ON Latency
MBAR	86A4	HSCFG2_MMIO	High Speed Configuration 2
MBAR	86B0	U2OCM1_MMIO	XHCI USB2 Overcurrent Pin Mapping 1
MBAR	86D0	U3OCM1_MMIO	XHCI USB3 Overcurrent Pin Mapping 1
MBAR	86FC	XHCC3_MMIO	XHCC3
Debug Capability Registers			
MBAR	8700	DCID	Debug Capability ID Register
MBAR	8704	DCDB	Debug Capability Doorbell Register
MBAR	8708	DCERSTSZ	Debug Capability Event Ring Segment Table Size Register
MBAR	8710	DCERSTBA	Debug Capability Event Ring Segment Table Base Address Register
MBAR	8718	DCERDP	Debug Capability Event Ring Dequeue Pointer Register
MBAR	8720	DCCTRL	Debug Capability Control Register
MBAR	8724	DCST	Debug Capability Status Register
MBAR	8728	DCPORTSC	Debug Capability Port Status and Control Register
MBAR	8730	DCCP	Debug Capability Context Pointer Register
MBAR	8738	DCDDI1	Debug Capability Device Descriptor Info Register 1
MBAR	873C	DCDDI2	Debug Capability Device Descriptor Info Register 2
MBAR	8740	DCDP	Debug Capability Descriptor Parameters
MBAR	8748	DBGDEV_CTRL_ODMA_REG	Debug Device Control ODMA
MBAR	8760	DBCCTL_REG	DBC Control Register 1

§ §

15 Platform Control Cluster (PCC)

This chapter describes the Platform Control Cluster (PCC).

Figure 15-1. What is Covered in This Chapter



15.1 Signal Descriptions

The signal pins and signal names associated with this chapter are described in the chapter of each PCC device.

15.2 Architectural Overview

The Platform Control Cluster (PCC) consists of the devices and controllers shown in Table 15-1. Details are in the Chapters shown in the table.

Table 15-1. Platform Control Cluster (PCC)

Device/Controller	Chapter
Integrated PCI devices	
SMBus - Host	See Chapter 29, "SMBus Controller - Host" for details.
Embedded Multimedia Card (eMMC)	See Chapter 17, "Embedded Multi-Media Card (eMMC)" for details.
High-Speed UART (HSUART)	See Chapter 18, "High-Speed UART Controller" for details.
Device 31 Functions	
LPC	See Chapter 20, "Low Pin Count (LPC) Controller" for details.
Serial Peripheral Interface (SPI)	See Chapter 19, "Serial Peripheral Interface (SPI)" for details.
Power Management Controller (PMC)	See Chapter 16, "Power Management Controller (PMC)" for details.
SMBus - Legacy	See Chapter 28, "SMBus Controller - Legacy" for details.
Primary to Sideband Bridge (P2SB)	See Chapter 22, "Primary to Side Band (P2SB) Bridge" for details.
Legacy controllers	
Customer GPIO	See Chapter 26, "Customer General-Purpose I/O (GPIO)" for details.
Real Time Clock (RTC)	See Chapter 24, "Real Time Clock (RTC)" for details.
8245 Programmable Interrupt Timer (PIT)	See Chapter 23, "Programmable Interval Timer (PIT)" for details.
High Performance Event Timer (HPET)	See Chapter 25, "High Precision Event Timer (HPET)" for details.
8259 Programmable Interrupt Controller (PIC)	See Chapter 21, "PIC and I/O APIC Controllers" for details.
IOxAPIC	See Chapter 21, "PIC and I/O APIC Controllers" for details.

15.2.1 Integrated PCI Devices

The PCC contains three integrated PCI devices which are accessible in Host Root Space:

- Device 18 (decimal), Function 0 - SMBus (Host) controller
- Device 26 (decimal), Functions 0, 1, and 2 - High-Speed UART (HSUART) controller
- Device 28 (decimal), Function 0 - Embedded Multimedia Card (eMMC) controller

Table 15-1 on page 523 provides a list of chapters for each controller.

15.2.2 Integrated PCI Device 31 Functions

Accessible in Host Root Space, the integrated, PCI Device 31 (decimal), has five PCI Functions:

- Function 0:
  - Low Pin Count (LPC) controller if the "Reserved for Intel" tied to pin (MCERR_N) SoC Hard Strap pin is 0.
- Function 1 - Primary to Sideband Bridge (P2SB) controller.
- Function 2 - Power Management Controller (PMC).
- Function 3 - SMBus (Legacy) controller.
- Function 4 - Serial Peripheral Interface (SPI) controller.

Table 15-1 on page 523 provides a list of chapters for each controller.

15.2.3 Legacy Controller Group

The Legacy group of controllers are the Customer General-Purpose I/O (GPIO) controller, Real-Time Clock, and the group of controllers that comprise the Interrupt Timer Sub System (ITSS). Table 15-1 on page 523 provides a list of chapters for each controller. The following section summarizes the ITSS group.

15.2.3.1 Interrupt Timer Sub System (ITSS)

The ITSS is a portion of the SoC internal circuitry consisting of the HPET, 8254 PIT, 8259 PIC, IOxAPIC and CPU interface components. It also provides the SoC interrupt routing control for the Host Root Space. The ITSS has its own clock and reset-control circuitry.

The Innovation Engine (IE) has a sideband connection to the ITSS components.

§ §

16 Power Management Controller (PMC)

This chapter describes the Power Management Controller (PMC) of the SoC.

Figure 16-1. What is Covered in This Chapter



16.1 Signal Descriptions

The signal descriptions are shown in Table 16-1, "Signal Names and Descriptions". For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing". The Direction/Type column of Table 16-1, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 16-1. Signal Names and Descriptions (Sheet 1 of 2)

Signal Names	Direction	Shared	Description
ADR_TRIGGER	I,O-OD	Yes	**Asynchronous DRAM Refresh (ADR) Trigger:** This active-high input is driven by the platform board circuitry to start the SoC ADR flow of events. As an active-high, open-drain output, the SoC can also drive this signal high to trigger ADR when an enabled, internal ADR event occurs. The SoC drives this signal pin high as long as the internal, ADR-triggered event is valid. The platform board must connect a pull-down resistor to this pin. ***Note:*** The platform board must refrain from actively driving this signal before power loss (external qualified event) has happened. The internal SoC circuitry also drives this pin active when it detects and handles an internal qualified event.
ADR_COMPLETE	I,O	Yes	**Asynchronous DRAM Refresh (ADR) Complete:** This active-high output indicates that the SoC has completed the ADR flow of events. When power is invalid or removed from the SoC, this output signal is invalid. ***Note:*** Even though this signal pin is labeled as an input-output (I/O), the platform must use it as an output-only pin and must not drive it.
CPU_RESET_N	O	Yes	**CPU Reset:** This active-low output can be used by the platform board or debug tools to indicate that the SoC is in a reset state.
PMU_PLTRST_N	O	Yes	**Platform Reset:** This active-low signal is asynchronously driven by the SoC and can be used as the platform board's main reset. This signal can be used by the PCI Express interface as the Fundamental Reset signal (PERST#) as defined in the PCIe base specification.
PMU_PWRBTN_N	I	Yes	**Power Button:** This active-low signal is debounced (16 ms) by the SoC. It generates an SMI or SCI to request the system to go to a sleep state. If already in sleep state, it causes a Wake Event. When the signal is held asserted for 5.1 seconds or longer while the SoC is in the G0 or G1 state, a power-button override is generated. This causes an unconditional transition to the G2 soft-off state and is useful when the system is in a hung working state.
PMU_RESETBUTTON_N	I	Yes	**Reset Button:** This edge-triggered, active-low, input signal indicates that the system reset button is depressed. The SoC debounces this input signal and does nothing unless the signal is asserted for at least 16 ms, at which time the PMC begins reset-sequence actions. When this edge-triggered signal is asserted beyond the 16-ms period, no additional reset actions are taken (only one reset produced per asserted edge). ***Note:*** There is a SoC Soft Strap that can be set to either enable this 16-ms debounce period or disable the internal debounce circuitry on this pin. See Chapter 4, "Strapping and Configuration".

Table 16-1. Signal Names and Descriptions (Sheet 2 of 2)

Signal Names	Direction	Shared	Description
PMU_SLP_S3_N	O	Yes	**Sleep State 3:** This active-low signal indicates that the SoC is transitioning from S0 to S4 or S5, or transitioning back up to S0, and that the platform board can shut down power not needed in this state by the SoC and the rest of the system.
PMU_SLP_S45_N	O	Yes	**Sleep State 4 or 5:** This active-low signal indicates that the SoC has entered and is in either the Suspend-to-Disk (S4) or Soft-Off (S5) Sleep State and that the platform board can shut down power not needed in these states by the SoC and the rest of the system.
PMU_SUSCLK	O	Yes	**Suspend Mode Clock:** Output of the RTC circuit (32.768 kHz) that can be used by the platform board. The output has a duty cycle as low as 30% or as high as 70%.
PMU_WAKE_N	I	Yes	**Wake:** This active-low signal is the destination of the PCIe sideband WAKE# signals. All device WAKE# signals are open-drain output signals and are connected together as described in the PCIe base specification.
SUS_STAT_N	O	Yes	**Suspend Status:** This active-low signal indicates that the SoC will be entering a low power state soon. This can be monitored by devices with memory that need to switch from normal refresh to suspend refresh mode. It can also be used by other peripherals as an indication that they should isolate their outputs that may be going to powered-off state.
SUSPWRDNACK	O	Yes	**Suspend Power-Down Acknowledge:** This active-high signal is asserted by the SoC when it does not require its Suspend (SUS) power well to be powered.
COREPWROK	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
INTRUDER_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
RSMRST_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
RTEST_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
SRTCRST_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
THERMTRIP_N	O-OD	Yes	See Chapter 35, "Thermal Management" for details.

16.2 Feature List

- ACPI and general Power Management control
- Circuitry to lower the Total Cost of Ownership (TCO) of the system
- Interacts with the SoC Innovation Engine (IE)
- Interacts with the SoC Intel® Management Engine (Intel® ME)
- Asynchronous DRAM Refresh (ADR)

16.3 Architectural Overview

The SoC Power Management Controller (PMC) is circuitry that provides the power management interface to the SoC signal pins. These are listed in Table 16-1, "Signal Names and Descriptions". The controller is an internal micro-controller which is not directly accessible to the SoC customer.

The PMC appears as a PCI Bus 0, Device 31 (decimal), Function 2 to software.

A number of SoC power-control and status registers are located in relocatable Host Root I/O Space starting at the ACPI Base Address (ABASE). These I/O Space registers must be enabled by setting the ACPI Enable (EN), bit 7 of the ACPI Control (ACTL) register at offset 44h of the PMC Configuration Space.

There are also a number of PMC registers located in relocatable Host Root Memory Space starting at the PM Base Address (PWRMBASE). These Memory-Mapped registers must be enabled by setting the PWRM Enable (PWRM_EN), bit 8 of the ACPI Control (ACTL) register at offset 44h of the PMC Configuration Space.

Bits [2:0] of the aforementioned ACPI Control (ACTL) register specify to which IRQ the System Control Interrupt (SCI) is routed internal to the SoC. The default is IRQ9 and other options are programmable.

The PMC performs the software-generated reset when the Host software writes a value of 06h or 0Eh to the Reset Control (RST_CNT) Register located at address CF9h in I/O Space.

The Total Cost of Ownership (TCO) registers are accessible and are located in the SMBus-Legacy Controller that appears as a PCI Bus 0, Device 31 (decimal), Function 4 to software.

16.4 System Power States

See Section 34.8, "System Global Power States" on page 911.

16.5 SoC Internal Power Control

The required supply voltages for the SoC operation for each Global Power State are shown in Chapter 34, "Supply Voltage Rails". The PMC platform board must provide the SoC voltages, but the PMC circuitry controls the internal silicon voltage rails for its Power Wells, turning internal circuitry on and off as needed. Whether a platform board turns its voltage regulators on and off is up to the system designer, but the regulators must provide power during the power states shown in Chapter 34, "Supply Voltage Rails".

16.5.1 Internal Power Switching

The SoC internal circuitry required for a particular product SKU is fully powered-on during the ACPI G0 (S0) state. The internal SoC circuitry that is only powered-on during the G0 (S0) working state is in the Core Power Well. See Section 34.4.1, "Core Power Well" on page 906. Some internal functions of a product SKU can be programmed to be powered off.

When the system is in the G2 (S5) Soft Off state, the PMC turns off power to some of the internal circuitry. The internal circuitry that is powered-on during G0 (S0) and during the G2 (S5) state is in the SUS Power Well. See Section 34.4.2, "SUS Power Well" on page 906. Sometimes this is referred to as "Always On" circuitry. The integrated circuitry that is powered-on during G2 (S5) is shown Table 16-2, "SoC Circuitry Powered-On During the G2 (S5) Global Power State".

Table 16-2. SoC Circuitry Powered-On During the G2 (S5) Global Power State

SoC Internal Module	Circuitry Powered On	Power Usage
Power Management	All	Required for SoC state changes
USB Combo Controller	USB 2.0 PHY and portion of the USB controller	Required for debug interface and Wakeup
High-Speed IO (HSIO)	All (PCI Express, SATA, USB 3.0)	Required for Wakeup
LAN	PHY	Required for Wakeup (if enabled)
Customer General Purpose I/O (GPIO)	All	Required for Wakeup and operation in the G2 (S5) state
Intel® Management Engine	All	
Innovation Engine	All	
Intel® Trace Hub	All	

When all power supplied to the SoC is removed, the system is in the G3 Mechanical Off state. If the system design includes a functioning RTC battery, a number of SoC registers draw power from the battery and retain their information during the Mechanical-Off state. These registers are also powered-on during the G0 (S0) and G2 (S5) states and are in the SoC RTC Power Well. See Section 34.4.3, "RTC Power Well" on page 906. The integrated circuitry that is powered-on during G3 is shown Table 16-3, "SoC Circuitry Powered-On During the G3 Global Power State".

Table 16-3. SoC Circuitry Powered-On During the G3 Global Power State

SoC Internal Module	Circuitry Powered On	Power Usage
SoC RTC Circuitry	RTC Registers, 32.768 kHz clock, SRAM, time and calendar	Retain register and time information during G3
Power Management	Registers preserved by a functioning RTC battery	Saving system information when system power is off
Intel® Management Engine	Registers preserved by a functioning RTC battery	Saving system information when system power is off

16.6 Total Cost of Ownership (TCO)

The TCO system management functions are designed to allow the system to diagnose failing subsystems. The intent of this logic is that some of the system management functionality can be provided without the aid of an external micro-controller or a Baseboard Management Controller (BMC).

While the TCO circuitry and registers are located in the SoC SMBus-Legacy controller, the SoC does not provide SMBus connectivity to the TCO mechanism. The SoC does allow Operating System (OS) software to access the TCO registers. TCO provides various functions to make a system easier to manage and to lower the total cost of ownership of the system. TCO features supported by the SoC:

- First TCO Watchdog Timer timeout can generate SMI# after a programmable time
  - The programmable 10-bit timer is decremented approximately every 0.6 seconds and allows timeouts ranging from 1.2 seconds to 613.8 seconds. The timeout value is programmable in the TCO_TMR Register (TTMR).
  - OS software can periodically reload the SoC timer using the TCO_RLD Register (TRLD). The first TCO Watchdog Timer timeout causes an SMI# allowing SMM-based recovery from OS lockup.
- Second hard-coded TCO Watchdog Timer timeout to generate a system reboot by the SoC asserting the active low PMU_PLTRST_N signal
  - This second timer is used only after the first TCO Watchdog Timer timeout occurs.
  - The SMI# handler must reload the first timer within 2.4 seconds after it times out to prevent the second timer from causing a system reboot. A timeout here assumes to be from a CPU or hardware error and reason to generate a system reset and reboot.
  - Option to prevent the system from rebooting after the second timeout via the "No TCO Reboot Enable" Hard Pin Strap. See Table 4-1, "SoC Hard Straps/Pin Straps and Descriptions".
- Capability for the SMM handler to generate a TCO interrupt to the OS
- Capability for OS to generate an SMI# to alert the TCO code in the SMM handler
- Processor Present detection
  - Detects if the processor fails to fetch the first instruction after reset.
- Report various errors detected by the circuitry
  - Can generate an SMI# or TCO interrupt (SERR, SMI, SCI).
- Intruder-Detect input (INTRUDER_N):
  - Can generate a TCO interrupt or SMI# when the system cover is removed.
  - The IRQ interrupt routed per register
  - The INTRUDER_N input signal is allowed to go active in any power state, including G3.
- Illegal BIOS accesses through SPI Flash is tracked and enabled in local registers in SPI Flash.
- Detection of bad BIOS Flash programming:
  - Detects if data on first read is FFh (an indication that the BIOS flash device is not programmed).

16.6.1 Detecting a System Lockup

When the processor is reset, it is expected to fetch its first instruction. If the processor fails to fetch the first instruction after reset, the TCO Watchdog Timer times out twice and the SoC asserts the Platform Reset (PMU_PLTRST_N) SoC output signal.

The Platform Reset and subsequent re-boot does not occur if the "No TCO Reboot" SoC Hard Pin Strap is active when sampled when the Resume Reset RSMRST_N signal deasserts. See Table 4-1, "SoC Hard Straps/Pin Straps and Descriptions".

During every boot, BIOS must read the SECOND_TO_STS bit in the TCO2_STS Register (TSTS2) to see if this is normal boot or a reboot due to the timeout. This bit is only cleared by writing a 1 to this bit or by assertion of the active low RSMRST_N SoC input signal pin by the platform board. The BIOS may also check the OS_POLICY bits of the TCO2_CNT Register (TCTL2) to see if it should try another boot or shutdown.

16.6.2 Handling an Intruder

The SoC has an active-low input signal, INTRUDER_N, that can be wired to a switch that is activated by the system's case being open. The activation of this signal can be used to cause an SMI# and to send an interrupt to the Intel® Management Engine (Intel® ME). INTRUDER_N may go active in any power state.

This SoC input has a two RTC-clock de-bounce delay. If the INTRUDER_N signal is driven active (low), and after the de-bounce delay, the Soc sets the Intruder Detect (INTRD_DET) bit of the TCO2_STS Register (TSTS2). The INTRD_SEL bits in the TCO2_CNT Register (TCTL2) can be programmed to enable the SoC to cause:

- an interrupt as selected by the TCO IRQ Select (IS) bits of the TCO Configuration (TCOCFG) register, or
- an SMI#, or
- neither (default).

The BIOS or interrupt handler can then cause a transition to the S5 state by writing to the SLP_TYP and SLP_EN bit fields of the Power Management 1 Control (PM1_CNT) register.

If the INTRUDER_N signal goes inactive some point after the INTRD_DET bit is written as a 1, then the INTRD_DET bit will go to a 0 when INTRUDER_N input signal goes inactive.

The INTRUDER_N signal pin is not shared nor can it be assigned as a Customer GPIO. Even so, software can directly read the status of the INTRUDER_N signal (high or low) by clearing and then reading the INTRD_DET bit. This allows the INTRUDER_N signal pin to be used as a SoC general-purpose input (GPI) if the intruder function is not required.

Note: Refer to the register description shown for INTRD_DET for additional details about how software interfaces with this bit and the 65-µs recovery time involved. The bit is slightly different than a classic sticky bit, since most sticky bits remain active indefinitely when the signal goes active and immediately go inactive when a 1 is written to the bit.

16.6.3 SMM-to-OS and OS-to-SMM Calls

Two eight-bit data registers are provided by the SoC for interaction between an SMI handler and OS-related code.

1. The SMI handler can generate an interrupt to the OS by writing to the TCO_DAT_OUT register. Doing this sets the TCO_INT_STS bit in the TCO1_STS (TSTS1) register. It also causes an interrupt as selected by the TCO IRQ Select (IS) bits of the TCO Configuration (TCOCFG) register. The interrupt is cleared by writing a 1 to the TCO_INT_STS bit.
2. The OS (or driver) can generate an SMI# by writing to the TCO_DAT_IN Register. Doing this sets the OS_TCO_SMI bit in the TCO1_STS Register (TSTS1). The SMI# is cleared by writing a 1 to the OS_TCO_SMI bit.

Reads to the TCO_DAT_IN (TDI) and TCO_DAT_OUT (TDO) registers do not cause an SMI# or interrupt.

Writing a 1 to the NMI_NOW bit of the TCO1_CNT (TCTL1) register allows for an immediate NMI.

16.7 SMI#/SCI Generation

The SoC does not have an System Management Interrupt (SMI)# signal pin. Upon any enabled SMI event taking place while the End of SMI (EOS) bit of the SMI Control and Enable (SMI_EN) is set, the SoC clears the EOS bit and asserts an SMI internal signal to the processor. This causes the CPU to enter System Management Mode (SMM). The PMC takes no further action on behalf of active SMI events until the Host software sets the EOS bit again. At that point, if any SMI events are still active, the PMC sends another SMI internal signal to the processor.

The SoC must have SMI fully enabled when the SoC is enabled to trap cycles. If SMI is not enabled in conjunction with the trap enabling, then hardware behavior is undefined.

The System Control Interrupt (SCI) is a level-mode interrupt that is typically handled by an ACPI-aware operating system. The SCI IRQ Select (SCIS) bits of the ACPI Control (ACTL) register specify the IRQ to which the SCI is mapped.

In non-APIC systems (which is the default), the SCIS bits must be set to route the SCI IRQ to one of the 8259 interrupts IRQ9, IRQ10, or IRQ11. The integrated 8259 interrupt controller must be programmed to level mode for that interrupt. Here the selected IRQ cannot be shared with the SoC LPC Serialized Interrupt (LPC_SERIRQ pin) stream, but it can be shared with other PCI interrupts.

In systems using the APIC, the SCIS bits can routed the SCI to the 8259 interrupts IRQ9, IRQ10, IRQ11, and if APIC Mode is enabled, IRQ20, IRQ21, IRQ22, or IRQ23. The interrupt polarity changes depending on whether it is on an interrupt shareable with a PIRQ or not. The interrupt remains asserted until all SCI sources are removed.

For additional information see Section 8.4, “System Control Interrupt (SCI)” on page 339. Table 16-4, “Causes of SMI and SCI” shows which events can cause an SMI and SCI. The SCI_EN bit of the Power Management 1 Control (PM1_CNT) register and the GBL_SMI_EN bit of the GPE0_EN_127_96 register determine whether the interrupt is routed as an SCI (SCI_EN=1) or SMI (SCI_EN = 0 AND GBL_SMI_EN = 1).

Table 16-4. Causes of SMI and SCI (Sheet 1 of 2)

Cause	SCI	SMI	Additional Enables (Note 1)	Where Reported
PME_B0 *Internal PME-Capable Agents*	Yes	Yes	PME_B0_EN=1	PME_B0_STS
PCI Express* PME Messages *Each Root Port has two SCI enable bits in their SCICSR register in Host Configuration Space*	Yes	No	PCI_EXP_EN=1	PCI_EXP_STS
PCI Express* PME Messages *Each Root Port has two SMI enable bits in its SMICSR register in Host Configuration Space*	No	Yes	None	PCI_EXP_SMI_STS
Power Button Press	Yes	Yes	PWRBTN_EN=1	PWRBTN_STS
Power Button Override (Note 2)	Yes	No	None	PRBTNOR_STS
RTC Alarm	Yes	Yes	RTC_EN=1	RTC_STS
ACPI Timer overflow (2.34 seconds)	Yes	Yes	TMROF_EN=1	TMROF_STS
Any GPIO enabled for SCI/SMI (Note 3)	Yes	Yes		
TCO SCI Logic	Yes	No	TCOSCI_EN=1	TCOSCI_STS
TCO SMI Logic	No	Yes	TCO_EN=1	TCO_STS
TCO SMI – TCO TIMEROUT	No	Yes	None	TIMEOUT
TCO SMI – NMI occurred *and NMIs mapped to SMI*	No	Yes	NMI2SMI_EN=1	NMI2SMI_STS
TCO SMI – Write attempted to BIOS	No	Yes	BIOSWE=1	BIOSWR_STS
BIOS_RLS bit of the SMI_EN register is written to 1 by BIOS (Note 4)	Yes	No	GBL_EN=1	GBL_STS
GBL_RLS written to	No	Yes	BIOS_EN=1	BIOS_STS
Write to B2h register	No	Yes	APMC_EN = 1	APM_STS
Periodic timer expires	No	Yes	PERIODIC_EN=1	PERIODIC_STS
64 ms timer expires	No	Yes	SWSMI_TMR_EN=1	SWSMI_TMR_STS
Monitor Status	No	Yes	None	MONITOR_STS
Enhanced USB Legacy Support Event	No	Yes	LEGACY_USB2_EN = 1	LEGACY_USB2_STS
PMC instructed to generate an SCI	No	Yes	MCSMI_EN	MCSMI_STS
LPC SMI is trapped if trapping is enabled *for legacy USB keyboard emulation*	No	Yes	LEGACY_USB_EN	LEGACY_USB_SMI_EN
Serialized IRQ SMI reported	No	Yes	None	SERIRQ_SMI_STS
SPI Command Completed	No	Yes	None	SPI_STS
SPI Flash Controller asserted SMI	No	Yes	None	SPI_SMI_STS
Device monitors match address in its range	No	Yes	None	DEVTRAP_STS
SMBus Host Controller	No	Yes	SMB_SMI_EN *Host Controller Enabled*	SMBus Host Status Register
SMBus Slave SMI message	No	Yes	None	SMBUS_SMI_STS
SMBus SMBALERT# signal active	No	Yes	None	SMBUS_SMI_STS
SMBus Host Notify message received	No	Yes	HOST_NOTIFY_INTREN	SMBUS_SMI_STS HOST_NOTIFY_STS
SLP_EN bit written to 1	No	Yes	SMI_ON_SLP	SMI_ON_SLP_EN_STS
Software Generated GPE	Yes	Yes	SWGPE_EN=1	SWGPE_STS
Intel® Management Engine causes SCI	Yes	No	ME_SCI_EN=1	ME_SCI_STS

Table 16-4. Causes of SMI and SCI (Sheet 2 of 2)

Cause	SCI	SMI	Additional Enables (Note 1)	Where Reported
Intel® Management Engine causes SMI	No	Yes	ME_SMI_EN=1	ME_SMI_STS
Innovation Engine causes SCI	Yes	No	IE_SCI_EN=1	IE_SCI_STS
Innovation Engine causes SMI	No	Yes	IE_SMI_EN=1	IE_SMI_STS
RTC update-in-progress	No	Yes	If enabled in the I/O Trap Register Space	RTC_UIP_SMI_STS
USB3 (xHCI) SMI Event	No	Yes	XHCI_SMI_EN=1	XHCI_SMI_STS
Wake Alarm Device Timer	Yes	Yes	WADT_EN	WADT_STS
Internal Interrupt Error Handler (IEH) circuitry	No	Yes	IEH_SMI_EN	IEH_SMI_STS

Notes:
1. The SCI_EN bit of the PM1_CNT register must be 1 to enable SCI. When SCI_EN is 0 AND GBL_SMI_EN = 1, SMI is enabled except for when an SCI is generated when the BIOS_RLS bit of the SMI_EN register is written to a 1 by BIOS.
2. When a power button override first occurs, the system transitions immediately to S5. The SCI will only occur after the next wake to S0 if the residual PWRBTNOR_STS status bit of the PM1_EN_STS register is not cleared prior to setting SCI_EN.
3. Refer to Chapter 26, "Customer General-Purpose I/O (GPIO)" for specific Customer GPIOs enabled for SCIs and/or SMIs.
4. GBL_STS being set will cause an SCI, even if the SCI_EN bit of the PM1_CNT register is not set. Software and BIOS must take great care not to set the BIOS_RLS bit of the SMI_EN register (which causes GBL_STS to be set) if the SCI handler is not in place.

16.7.1 PCI Express* SCI

PCI Express ports and the processor have the ability to cause a Power Management Event (PME) using messages. When a PME message is received, the SoC sets the PCI Express Status (PCI_EXP_STS) bit of the GPE0_STS_127_96 register. If the SCI Enable (SCI_EN) bit of the Power Management 1 Control (PM1_CNT) register and the PCI Express Enable (PCI_EXP_EN) bit of the GPE0_EN_127_96 register are also set, the SoC generates cause an SCI.

16.8 C States

The SoC processor power management circuitry, rather than the PMC, controls the C States. See Section 34.9, "Processor Power States - C-States" on page 913.

16.9 Dynamic LPC 24-MHz Clock Control

See Section 20.3.10, "Dynamic LPC Clock Control" on page 629.

16.10 Sleep States

For an overview of the Global Power States and the associated Sleep States see Section 34.8, "System Global Power States" on page 911. Power-supply cycling requirements associated with state changes are described in Chapter 33, "Resets and Voltage Sequencing".

16.10.1 Initiating State Changes when in the G0 (S0) Working State

These initiate a Global Power State change:

- In the G0 (S0) Working State, the Operating System Power Management (OSPM) software initiates the state change by following these steps:
  a. Mask interrupts
  b. Turn-off all bus-master enable bits
  c. Enabling the appropriate wake events that will trigger the exit from the selected state
  d. Set the desired sleep type in the three-bit Sleep Type (SLP_TYP) field of the Power Management 1 Control (PM1_CNT) register located in Host I/O Space at ABASE plus offset 4h. The SLP_TYP bits are in the RTC power well and are retained during G3 if the system has a functioning RTC battery.
  e. Set the Sleep Enable (SLP_EN) bit of the PM1_CNT register

  The hardware then attempts to gracefully put the system into the sleep state designated by SLP_TYP. Once in the sleep state, whenever one of the wake events enabled in "step c" occurs, the hardware transitions the system back to the G0 (S0) Working State which requires rebooting the system.
  The G3 Mechanical Off Global Power State cannot be entered by any operating-software mechanism. If the platform power is removed while in the G2 (S5) state, the G3 state is entered.
- In the G0 (S0) Working State, the user initiates the state change:
  a. The user presses the system Power button for less than 5.1 seconds. The SoC provides the active-low PMU_PWRBTN_N input signal pin to sense the position of the system Power button.
  b. The SoC then generates a power-management event using either a System Management Interrupt (SMI) or System Control Interrupt (SCI), to request the system's power-button driver to go to a sleep state.
  c. The OSPM sequence described in the bullet above this one is then followed. This is a controlled transition that allows OSPM to bring the system down in an orderly fashion by unloading applications, closing files, etc.
- In the G0 (S0) Working State, a Power Button Override is initiated by the user by pressing the system's Power button (active-low PMU_PWRBTN_N input signal pin) for more than 5.1 seconds in order to turn-off a hung system. This causes an unconditional, less graceful transition to the G2 (S5) Soft-Off State. Here the SoC first transitions directly to the early-boot phase and then transitions to the S5 Soft-Off state. Subsequent situations that can trigger a Warm Reset or Cold Reset are ignored.
  — The Intel® Management Engine and Innovation Engine firmware each has a mechanism to turn off a hung system similar to the Power-Button Override by writing bits in their power-management control registers. Subsequent situations that can trigger a Warm Reset or Cold Reset are ignored.

- In the G0 (S0) Working State, the SoC detects a Catastrophic Thermal Trip situation that may damage the SoC component. See Chapter 35, "THERMTRIP_N". The SoC asserts the THERMTRIP_N output signal pin. Except for the V3P30 voltage group, all SoC rails must shut down immediately. Just like a Power Button Override, Catastrophic Thermal Trip causes an unconditional, less graceful transition to the G2 (S5) Soft-Off State. Subsequent situations that can trigger a Warm Reset or Cold Reset are ignored.
  - If all platform power-supply sources to the SoC are shutdown at this point, and the platform doesn't have a working coin-cell battery, the SoC is incapable of retaining the cause of the global reset or straight-to-S5 during the subsequent reboot.
- If a reset button is part of the platform board design, and the user presses the button, it causes the PMU_RESETBUTTON_N SoC input signal pin to go active after a 16-ms de-bounce period). The SoC asserts the active low PMU_PLTRST_N output signal pin, and enters, or remains in, the G0 (S0) Working State.
  - If I/O Port CF9h (RST_CNT) register bit 3=0 in Host I/O Space, a Warm Reset occurs where no power cycles occur, and the SoC performs a system boot.
  - If I/O Port CF9h bit 3=1 in Host I/O Space, a Cold Reset occurs where the Core Power Well is cycled, and the SoC performs a system boot.
- Whenever a write of 06h is performed to I/O Port CF9h (RST_CNT) register, the SoC reacts as if the user pushed the system reset button. The SoC asserts the active low PMU_PLTRST_N output signal pin, and enters, or remains in, the G0 (S0) Working State.
  - If I/O Port CF9h bit 3=0 in Host I/O Space, a Warm Reset occurs where no power cycles occur, and the SoC performs a system boot.
  - If I/O Port CF9h bit 3=1 in Host I/O Space, a Cold Reset occurs where the Core Power Well is cycled, and the SoC performs a system boot.
- Whenever the system is shutdown to G2 (S5) or G3 by integrated manageability functions like Alert Standard Format (ASF).
- Whenever the TCO Watchdog Timer timeout occurs a second time within the SoC. If directed by the hard pin strap "No TCO Reboot Enable," the SoC asserts the active low PMU_PLTRST_N output signal pin, enters (or remains in) the G0 (S0) Working State. There is no power cycle involved and the destination is the G0 (S0) Working State. This is considered a "Warm Reset" and performs a system reboot. See Table 4-1, "SoC Hard Straps/Pin Straps and Descriptions".
- Whenever SoC hardware detects internal errors and is enabled to generated some type of reset. The types of reset and what happens is shown in Table 16-7, "Causes of Host Reset and Global Reset".

16.10.2 Initiating State Changes when in the G3 Mechanical-Off State

- When the SoC is in the G3 Mechanical Off state and the main system power is turned on, the platform board cycles-on the voltages it supplies to the SoC while systematically de-asserting the active-low RTEST_N, SRTCRST_N, and RSMRST_N input signals of the SoC. This initiates what is called a Cold Boot sequence and is shown in Figure 33-1, "ACPI Cold Boot Sequence". The SoC is put in the G2 (S5) Soft-Off state.
  - The SoC has circuitry to determine if this is the first time the system leaves the G3 Mechanical Off state. For this first-boot situation, the SoC uses the "AG3E Boot Select" Soft-Strap setting (see Chapter 4, "SoC Soft Straps") to determine whether to immediately transition to the G0 (S0) Working state and perform a "Cold Boot" or whether to wait in the G2 (S5) Soft-Off state for the power button or some other enabled wake event to transition to the G0 (S0) Working state.
  - During the first-boot sequence, the SoC retains the "AG3E Boot Select" Soft-Strap value in the AFTERG3_EN (AG3E) bit of the General PM Configuration B (GEN_PMCON_B) register for subsequent boot cycles. It retains the AG3E value until the SoC RTC power well loses power. BIOS can alter the AG3E register bit for subsequent boot cycles so that they behave differently than the first boot. If the AG3E bit is still set when the SoC transitions out of the G3 state, it not considered the first-boot situation. The retained value of AG3E is used instead of the "AG3E Boot Select" Soft Strap.

16.10.3 Returning to the S0 State when in the G2 (S5) Soft-Off State

The S5 Soft-Off sleep state is exited based on wake events. Before S5 was entered via the SLP_EN bit setting, software enabled the appropriate wake events in the Power Management 1 Enables and Status (PM1_EN_STS) register. When an enabled wake event occurs in S5, it forces the system to a full-on G2 (S0) Working state. Some non-critical subsystems, like rotational hard drives, might still be shut off and have to be brought back on using some other system-design mechanism.

Upon exit from the S5 Soft-Off state, the WAK_STS bit is set by the SoC. This bit is not affected by hard resets caused by a write to the Host I/O Port CF9h (RST_CNT) register, and is reset by writing a one to this bit, or by an internal power-good reset. The PM1_EN_STS register contains the wake event that caused the exit from the S5 state.

The possible causes of wake events (and their restrictions) are shown in Table 16-5 on page 537.

Table 16-5. Power Management Wake Events (Sheet 1 of 2)

Cause of the Wake Event	How the Wake Event is Enabled	Wake Event Status Reported	Besides Wake from S5, can also Wake from Reset Types
RTC Alarm	RTC Alarm Enable (RTC_EN)	RTC Status (RTC_STS)	-
PMU_PWRBTN_N pin is active (Power Button)	Always enabled as a Wake Event. If an interrupt is desired, the Power Button Enable (PWRBTN_EN) bit must be set.	Power Button Status (PWRBTN_STS)	Notes 1, 2, 3
Any GPIO signal pin that is configured and enabled for triggering a Wake Event	GPI General Purpose Events Enable (GPI_GPE_EN_*signal pin name)* See Chapter 8, "GPIO and PMC General Purpose Event (GPE)".	GPI General Purpose Events Status (GPI_GPE_STS_*signal pin name)* See Chapter 8, "GPIO and PMC General Purpose Event (GPE)".	-

Table 16-5. Power Management Wake Events (Sheet 2 of 2)

Cause of the Wake Event	How the Wake Event is Enabled	Wake Event Status Reported	Besides Wake from S5, can also Wake from Reset Types
Integrated LAN Controllers	See Section 16.10.3.1, "LAN Power Management Wakeup" on page 539.	See Section 16.10.3.1, "LAN Power Management Wakeup" on page 539.	Notes 1, 2, 3
Power Management Event (PME) from SoC integrated devices (PME_B0_STS)	See Section 16.10.3.2, "Other Internal Power Management Events" on page 540.	See Section 16.10.3.2, "Other Internal Power Management Events" on page 540.	-
PMU_WAKE_N pin is active (PCI Express WAKE# signal)	PCI Express Wake Disable (PCIEXP_WAKE_DIS) is not set. Modification of this bit has no impact on the value of the PCIEXP_WAKE_STS bit.	PCI Express Wake Status (PCIEXP_WAKE_STS)	-
SMB_LEG_ALRT_N pin is active (SMBus SMBALERT# Signal)	GPI General Purpose Events Enable (GPI_GPE_EN_SMB0_LEG_ALRT_N)	GPI General Purpose Events Status (GPI_GPE_STS_SMB0_LEG_ALRT_N)	-
Intel® Management Engine (Intel® ME) Non-Maskable Wake	Always enabled as a wake event.	ME_HOST_WAKE_STS (ME_HOST_WAKE_STS)	Notes 1, 2, 3
Innovation Engine (IE) Non-Maskable Wake	Always enabled as a wake event.	IE Host Wake Status (IE_HOST_WAKE_STS)	Notes 1, 2, 3
Wake Alarm Device	Wake Alarm Device Timer Enable (WADT_EN)	Wake Alarm Device Timer Status (WADT_STS)	-

Notes:
1. Reset Type: The SoC transitions straight to the S5 Soft-Off state (not a gradual shutdown). Here the SoC first transitions to the beginning of the early-boot sequences and then transitions to the S5 Soft-Off state.
2. Reset Type: Host Reset with Power Down and the Host stays there when initiated by the Intel® ME.
3. Reset Type: Host Reset with Power Down and the Host stays there when initiated by the Innovation Engine.

16.10.3.1 LAN Power Management Wakeup

The integrated LAN controllers' advanced power management wakeup, or APM wakeup, was previously known as Wake on LAN (WoL). At power up, each SoC LAN controller reads the APM Enable bit from the LAN region of the SoC SPI Flash into the APM Enable (APME) bits of a controller register. This bit controls the enabling of LAN APM Wakeup. When APM Wakeup is enabled, the SoC LAN controller checks all incoming packets for Magic Packets. Each LAN controller can be configured to detect the APM Wakeup on one, both, or none if its two LAN ports. The LAN device driver has the ability to alter the APME bit after power up.

When all of its wakeup enables are in place the LAN controller sends a SoC-internal "enable" signal to the PMC. When the LAN controller detects a wake-up situation, it notifies the PMC through a SoC-internal "wakeup" signal. Before each time the PMC needs to transition from the G0 (S0) Working state to another sleep state, it senses the internal LAN enable signal to keep the LAN port powered-on during the new sleep state if LAN APM Wakeup is enabled. If for some reason the LAN controller is already powered-off during the G0 (S0) Working state, the internal enable signal has no effect on the LAN controller's power state.

If "WoL after SUS power loss" is configured in the LAN region of the SPI Flash, BIOS can use the WoL Enable Override (WOL_EN_OVRD) bit of the General PM Configuration B (GEN_PMCON_B) register to enable Wake-On-LAN regardless of the policies selected through the operating system. This bit is maintained in the RTC power well, therefore permitting WoL following a surprise power failure even in cases in which the system may have been running in S0 without the PME Enables set.

16.10.3.2 Other Internal Power Management Events

The SoC combines the LAN advanced power management enable and wakeup internal signals with the other SoC integrated PCI devices' power-management event enable and wakeup internal signals. The Power Management Event Bus 0 Status (PME_B0_STS) bit of the General Purpose Event 0 Status [127:96] (GPE0_STS_127_96) register is set to one by the SoC when any SoC-internal device with PCI Power Management capabilities on Host PCI Bus 0 asserts the equivalent of the PCI PME# signal. Additionally, if the PME_B0_EN bit of the GPE0_EN_127_96 register and SCI_EN bit in the PM1_CNT register are set, then the setting of the PME_B0_STS bit generates an SCI (or an SMI if SCI_EN is not set).

A Power Management Event (PME) from PM-enabled and powered-on SoC-internal devices that can set the PME_B0_STS bit are:

- Integrated LAN controllers (see Section 16.10.3.1, "LAN Power Management Wakeup" on page 539)
- Integrated SATA Controllers
- Integrated USB 2.0 Controllers
- Integrated USB 3.0 Controllers
- Intel® Management Engine (Intel® ME) Maskable Host Wake bit
- Innovation Engine (IE) Maskable Host Wake bit

If the PME_B0_EN bit is set, and the system is in the S3 or S4 state, or the S5 state due to SLP_TYP and SLP_EN, then the setting of the PME_B0_STS bit generates a wake event. If the system is in an S5 state due to power button override, then the PME_B0_STS bit does not cause a wake event or an SCI. PME_B0_STS is cleared by a software write of '1.'

Note: The S3 state for the SoC is not validated by Intel.

The truth table for situations when an integrated-device wakeup event is enable is shown in Table 16-6, "Power Management Event Enables". In the table:

— "Yes" indicated that the PME is enabled. Device power remains on during the S0-to-Sx transition.

— "No" indicates that the PME is not enabled. The power is turned off by the SoC to the affected devices during the S0-to-Sx transition. Exceptions to this are the Intel® ME and the IE in that they may stay powered-on (active) but the Sx PME wake might be disabled.

Table 16-6. Power Management Event Enables

PME_B0_EN bit	PME_B0_S5_DIS bit	Internal Wakeup Enable signal from LAN	Wakeup and provide wake event status in S4?	Wakeup and provide wake event status in S5?
0	0	0	No	No
0	1	0	No	No
0	X	1	No	Yes, LAN only
1	0	1	Yes, all PME B0 sources including LAN	Yes, all PME B0 sources including LAN
1	1	1	Yes, all PME B0 sources including LAN	Yes, LAN only
1	0	0	Yes, all PME B0 sources including LAN	Yes, all PME B0 sources including LAN
1	1	0	Yes, all PME B0 sources including LAN	No

16.10.4 Reset Triggers That Generate a State Change

Certain hardware situations generate a reset request to the PMC that can trigger the change of the Global Power State of the SoC. The SoC behavior after a reset trigger depends on the situation that generated the reset request.

See Section 16.13, "Reset Behavior" on page 543.

16.11 System Power Supplies, Planes, and Signals

All SoC power-control signal pins are described in Table 16-1, "Signal Names and Descriptions". The following is additional information about those signal pins that can be used for system power-supply control.

16.11.1 Platform Power Plane Control with PMU_SLP_S3_N and PMU_SLP_S45_N

When asserted, the active-low PMU_SLP_S3_N SoC output signal can be used to cut power to the system's VCC, VCCRAM, and VCCREF SoC power-supply pins. This same signal can be used to cut the termination voltage VTT to the DDR DIMMs. VTT is only delivered by the system to the DIMMs and not to the SoC.

When asserted, the active-low PMU_SLP_S45_N SoC output signal can be used to cut power to the system's VDDQ SoC power-supply pins. This is allowed because the SoC does not support the S3 sleep state.

Both of these pins can be configured as Customer GPIOs if not used in the system design.

16.11.2 COREPWROK SoC Input Signal

When asserted, the active-high COREPWROK signal is an indication to the SoC that the platform board Voltage Regulators (VRs) that supply the SoC Core Power Well rails have been stable for at least 10 ms. COREPWROK can be driven asynchronously. When COREPWROK is de-asserted, the SoC asynchronously asserts the active-low PMU_PLTRST_N signal. COREPWROK must not glitch, even if RSMRST_N is active (low)

The SoC output signal PMU_PLTRST_N de-asserts after the SoC input signal COREPWROK is asserted. Platforms which include a PCI Express* device may use the signal PMU_PLTRST_N to generate the PCI Express* signal PERST#. If the signal PMU_PLTRST_N is used to generate the PCI Express* signal PERST#, then the platform should not assert COREPWROK until at least 100ms after all the PCI Express power supplies and clocks have become stable and valid, as mandated within the PCIe Express* PCI Express* Card Electromechanical Specification.

16.11.3 SUSPWRDNACK SoC Output Signal

Suspend Power-Down Acknowledge (SUSPWRDNACK) is an active-high output signal that is asserted by the SoC when it does not require its Suspend (SUS) power well to be powered.

This pin can be configured as a Customer GPIO if not used in the system design.

16.12 Legacy Power Management Theory of Operation

Instead of relying on Advanced Configuration and Power Interface (ACPI) software, legacy power management uses BIOS and various hardware mechanisms. The scheme relies on the concept of detecting when individual subsystems are idle, detecting when the whole system is idle, and detecting when accesses are attempted to idle subsystems.

However, the operating system is assumed to be at least Advanced Power Management (APM) enabled. Without legacy APM calls, there is no quick way for the SoC to know when the system is idle (e.g., idle between keystrokes). The SoC does not support burst modes.

16.13 Reset Behavior

The SoC is divided into three reset partitions:

- Host Partition - The SoC hardware not including the Intel® Management Engine and the Innovation Engine.
- Intel® Management Engine Partition - Just the Intel® Management Engine portion of the SoC.
- Innovation Engine Partition - Just the Innovation Engine portion of the SoC.

The SoC can perform two main types of reset:

- Host Reset - Just the Host Partition hardware is reset. If a Host Reset is triggered and the PMC times out before receiving an internal acknowledge message from the processor, a Global Reset with power-cycle occurs.
- Global Reset - All three of the SoC partitions are reset and a power cycle is performed. During a Global Reset, all SoC functionality is reset except for information backed-up by the RTC Power Well or the SUS (Primary and DSW) Power Well. Also not reset are configuration information, and functional logic for controlling and reporting the reset. The Host, Intel® Management Engine, and Innovation Engine all power back up after the power cycle period.

16.13.1 Reset Request Conditions

Table 16-7, "Causes of Host Reset and Global Reset" shows the situations when the PMC is requested to perform a type of partition reset, possible power down/up cycle, or instead change (not gracefully) the Host sleep state to the G2 (S5) Soft-Off state and stay there until an enabled Wake Event occurs to return to the G0 (S0) Working state.

The latter is called "Straight to S5" and all SoC functionality is reset except for information backed-up by the RTC Power Well or the SUS Power Well. The terms "Primary" and "DSW" are used in the EDS register descriptions instead of "SUS." Also not reset are configuration information, and functional logic for controlling and reporting the reset. While Table 16-7, "Causes of Host Reset and Global Reset" shows Host Reset and Global Reset triggers, there are some situations where only the Intel® Management Engine Partition or Innovation Engine Partition is reset by the PMC.

Table 16-7. Causes of Host Reset and Global Reset (Sheet 1 of 3)

Reset Request and Condition	Host Reset Without Power Cycle (Note 1)	Host Reset With Power Cycle (Note 2)	Global Reset With Power Cycle (Note 3)	Straight to S5 and Host Stays in S5
From power management state-change software				
The CPU is reset when going to the G2 (S5) Soft-Off state. SoC functionality that needs to remain operational or retain status during the Host S5 sleep state does not get reset in this case	-	Yes see Note 4	see Note 5	-
From SoC input signal pins				
PMU_RESETBUTTON_N asserted and CF9h (RST_CNT Register) Bit 3 = 0	Yes	-	see Note 5	-
PMU_RESETBUTTON_N asserted and CF9h (RST_CNT Register) Bit 3 = 1	-	Yes	see Note 5	-
ADR_TRIGGER input signal is asserted when enabled to trigger a Global Reset. If the ADR flow is externally triggered, Global Reset will not be triggered.	-	-	Yes	-
Power Button (PMU_PWRBTN_N) 5.1-second override causes transition to S5 and reset asserts	-	-	-	Yes
From software reset (I/O Port CF9h)				
Write of 06h to CF9h (RST_CNT Register) when CF9h Global Reset (CF9GR) bit = 0 in the ETR3 register of the PMC	Yes	-	see Note 5	-
Write of 0Eh to CF9h (RST_CNT Register) when the SPD Reset (SPD_BIOS_RESET) bit = 1 in the PCH_PM_STS register	-	Yes see Note 6		-
Write of 0Eh to CF9h (RST_CNT Register) when CF9h Global Reset (CF9GR) bit = 0 in the ETR3 register of the PMC	-	Yes	see Note 5	-
Write of 0Eh to CF9h (RST_CNT Register) when CF9h Global Reset (CF9GR) bit = 1 in the ETR3 register of the PMC	-	-	Yes	-
From power failure and thermal alerts				
Power Failure: COREPWROK signal goes inactive in S0	-	-	Yes	-
Processor Thermal Trip (THERMTRIP_N) causes transition to S5 and reset asserts	-	-	-	Yes
SoC internal thermal sensors signals a catastrophic temperature condition	-	-	-	Yes

Table 16-7. Causes of Host Reset and Global Reset (Sheet 2 of 3)

Reset Request and Condition	Host Reset Without Power Cycle (Note 1)	Host Reset With Power Cycle (Note 2)	Global Reset With Power Cycle (Note 3)	Straight to S5 and Host Stays in S5
From detected hardware errors and interface time-out situations				
Total Cost of Ownership (TCO) Watchdog Timer reaches zero two times	Yes	-	see Note 5	-
Host Partition Reset Entry Timeout (see Note 7)	-	-	Yes	-
PMC hardware detects an uncorrectable parity error on a data read from one of its SUS (Primary) Power Well registers	-	-	Yes	-
Power Management Watchdog Timer	-	-	-	Yes
PMC hardware detects that the system has been running too long without Intel® Management Engine firmware acknowledgment	-	-	-	Yes
From shutdown cycles requested by the processor				
Special shutdown cycle from processor causes CF9h-like PMU_PLTRST_N when CF9h Global Reset (CF9GR) bit = 0 in the ETR3 register of the PMC and CF9h (RST_CNT Register) Bit 3 = 0	Yes	-	see Note 5	-
Special shutdown cycle from processor causes CF9h-like PMU_PLTRST_N when CF9h Global Reset (CF9GR) bit = 0 in the ETR3 register of the PMC and CF9h (RST_CNT Register) Bit 3 = 1	-	Yes	see Note 5	-
Special shutdown cycle from processor causes CF9h-like PMU_PLTRST_N when CF9h Global Reset (CF9GR) bit = 1 in the ETR3 register of the PMC	-	-	Yes	-
From the Intel® Management Engine				
Intel® Management Engine-Triggered Host Reset without Power-Cycle	Yes	-	see Note 5	-
Intel® Management Engine-Triggered Host Reset with Power-Cycle	-	Yes	see Note 5	-
Intel® Management Engine-Triggered Host Reset with power down (host stays there)	-	Yes see Note 4	see Note 5	-
Intel® Management Engine promotes a Host Partition Reset to a Global Reset	-	-	Yes	-
Intel® Management Engine-Triggered Global Reset	-	-	Yes	-
Intel® Management Engine detects an unexpected Minute IA (MIA) error	-	-	-	Yes see Note 8
Intel® Management Engine detects an unexpected Minute IA (MIA) shutdown error	-	-	-	Yes see Note 8
Intel® Management Engine Hardware Uncorrectable Error	-	-	-	Yes see Note 8
Intel® Management Engine Watchdog Timer Timeout	-	-	-	Yes see Note 8
Intel® Management Engine-Triggered Power Button Override	-	-	-	Yes
From the Innovation Engine				
Innovation Engine-Triggered Host Reset without Power-Cycle	Yes	-	see Note 5	-
Innovation Engine-Triggered Host Reset with Power-Cycle	-	Yes	see Note 5	-
Innovation Engine-Triggered Host Reset with power down (host stays there)	-	Yes see Note 4	see Note 5	-
Innovation Engine-Triggered Global Reset	-	-	Yes	-

Table 16-7. Causes of Host Reset and Global Reset (Sheet 3 of 3)

Reset Request and Condition	Host Reset Without Power Cycle (Note 1)	Host Reset With Power Cycle (Note 2)	Global Reset With Power Cycle (Note 3)	Straight to S5 and Host Stays in S5
Innovation Engine detects an unexpected Minute IA (MIA) error	-	-	-	Yes see Note 9
Innovation Engine detects an unexpected Minute IA (MIA) shutdown error	-	-	-	Yes see Note 9
Innovation Engine Hardware Uncorrectable Error	-	-	-	Yes see Note 9
Innovation Engine Watchdog Timer Timeout	-	-	-	Yes see Note 9
Innovation Engine-Triggered Power Button Override	-	-	-	Yes

Notes:
1. The SoC drops this type of reset request if received while the system is in the G2 (S5) Soft Off state.
2. The SoC does not drop this type of reset request if received while system is in a "software-entered" G2 (S5) Soft Off state. Here the SoC does perform the Host Reset with Power Cycle.
3. The SoC does not warn the processor. The Global Reset occurs without delay.
4. The PMC waits for an enabled Wake Event to occur before completing the Host Reset with Power Cycle.
5. If the PMC detects a problem while executing the Host Reset, the PMC promotes this request to be a Global Reset with Power Cycle.
6. SoC internal clocks are made ready for DIMM Serial Presence Detect (SPD) discovery.
7. Host Partition Reset Entry Timeout is automatically initiated if the hardware detects that the Platform Reset (PMU_PLTRST_N) sequence has not occurred within 5.1 seconds of being started.
8. Only the Intel® Management Engine is reset and not the Host or Innovation Engine
9. Only the Innovation Engine is reset and not the Host or Intel® Management Engine

16.14 Interaction with the Innovative Engine (IE)

The IE provides the fan control FAN_PWM[3:0] and FAN_TACH[3:0] signals that are listed in Chapter 37, "Innovation Engine".

A number of IE error conditions are reported internally to the PMC so that the PMC can take the appropriate action, typically a Global Reset. See Table 16-7, "Causes of Host Reset and Global Reset".

The IE and PMC also interact with the following:

- Power Up
- Power Down
- IE power control
- Expiration of the IE-based Anti-Theft Watchdog Timer

16.15 Asynchronous DRAM Refresh (ADR)

The ADR feature of the SoC provides a mechanism to enable preservation of key data in battery-backed DDR system memory, in the event of AC power-supply failure. For all processor cores of the product SKU, the SoC ADR sequence forces an L1 cache flush of "dirty write" data to the battery-backed, or supercapacitor-backed, DDR system memory DIMMs and then places DIMMs in the battery/supercapacitor-backed Self-Refresh Mode defined by JEDEC. Dirty writes located in the SoC internal memory data buffers are also flushed. For ADR to be successful, the platform board must sustain valid power levels to the SoC for a minimum of 50 µs once the SoC initiates and enters the ADR sequence.

As a configurable option, the SoC can also flush dirty-write data from the L2 caches to the battery-backed system-memory DIMMs. This adds a certain time to the process and the platform board must sustain valid power to the SoC during this period, too.

The SoC ADR_TRIGGER input signal is the early-warning alert asserted by the platform and system power supply indicating that AC power has been lost and that the platform voltage rails will soon be dropping. Before the platform-board circuitry asserts RSMRST_N or deasserts COREPWROK, the ADR_TRIGGER signal must be asserted and trigger the ADR flow of the SoC.

Typically, proper fencing protocol before ADR triggers is not needed if both L1 and L2 caches are flushed. This may not be true if the platform design contains external DMA subsystems or if multiple SoC nodes mirror data using an external Non-Transparent Bridge (NTB). The discussion of such fencing techniques is beyond the scope of this document.

Note: An SoC internal register bit is used to convey to BIOS that a successful ADR sequence occurred before the most-recent loss of power or Global Reset. For the ADR feature to function properly, a battery is required to keep the RTC power well powered when in the G3 state.

16.15.1 Configuring ADR

To provide imminent power loss as a condition to initiate ADR, BIOS ensures that the SoC pin-function MUXing is configured so that the SoC provides the ADR_TRIGGER and ADR_COMPLETE signal pins for communication with the platform board circuitry. By default, these signal pins are Customer GPIO output signals GPIO[81] and GPIO[0] respectively.

Note: The SoC ensures that the ADR_COMPLETE output signal is glitch-free, even during the SUS-Well power ramp.

The SoC ADR mechanism is configured and controlled by the 32-bit ADR Enable (ADR_EN) register. The register is one of the PMC Memory Mapped Registers located in Host Memory Space at the address specified by the Power Management Base (PWRMBASE) register, plus offset F0h. The PWRMBASE register is located in Configuration Space at Bus 0, Device 31 (decimal), Function 2, offset 48h.

Note: The PWRM Enable (PWRM_EN) bit must be set to enable the decode of the memory-mapped address range pointed by PWRMBASE. PWRM_EN is located in the 32-bit ACPI Control (ACTL) register which is located in Configuration Space at Bus 0, Device 31 (decimal), Function 2, offset 44h.

The ADR feature is enabled/disabled by the ADR Feature Enable (ADR_FEAT_EN) bit (bit 0) of the ADR_EN register. When the feature is enabled, the ADR_TRIGGER signal pin, indicating an impending power loss detected by the board, is used to start the ADR process. Any of a number of "Qualified Internal Events" can also start the ADR process provided they are enabled in the ADR_EN register.

Bit 29 of the ADR_EN register enables/disables whether a Global Reset is generated after the SoC internal-data flushing completes.

BIOS must indicate whether the L2 Cache is to be flushed or not flushed during the ADR process. BIOS does this by programming the L2_FLUSH bit (bit 0) of the P_CR_ADR_COMMAND_0_0_0_MCHBAR Register located in Host Root Memory Space at MCHBAR, offset 712Ch. MCHBAR is defined by the two 32-bit registers MCHBAR_LO_0_0_0_PCI and MCHBAR_HI_0_0_0_PCI located at offsets 48h and 4Ch in configuration space for the System Agent (Bus 0, Device 0, Function 0).

- L2_FLUSH bit = 0: The SoC does not flush L2 Cache during the ADR flow.
- L2_FLUSH bit = 1: The SoC flushes L2 Cache on all processor modules as part of the ADR flow when it is initiated by the ADR_TRIGGER signal pin.

16.15.1.1 Qualified Internal Events

There are a number of SoC-internal qualified events that can be enabled in the ADR_EN register to trigger the ADR sequence and generate a Global Reset after the internal cache-flush sequence completes. These are not associated with the Qualified External Event where the assertion of the ADR_TRIGGER signal pin by the platform board triggers the ADR sequence. The Qualified Internal Events include:

- Power Button Override
- Intel® ME-Initiated Power Button Override
- IE-Initiated Power Button Override
- SoC PMC Firmware Watchdog Timer
- Intel® ME Firmware Watchdog Timer
- IE Firmware Watchdog Timer
- SoC PMC Firmware-Initiated Global Reset
- Intel® ME-Initiated Global Reset
- IE-Initiated Global Reset
- SoC PMC SUS RAM Parity Error
- SYS_PWROK Failure
- Intel® ME Uncorrectable Error
- IE Uncorrectable Error

16.15.2 Configuring the Copy-to-Flash Extension

The Copy-to-Flash (C2F) extension to the ADR sequence is a special platform-level and BIOS sequence. It can extend the system's sequence of events when the SoC ADR sequence is triggered by the platform (ADR_TRIGGER signal for imminent power loss).

In some system designs, the information retained in the system memory after the ADR sequence (valid SDRAM power and SDRAMs in Self-Refresh Mode) is considered volatile. Such system designs require all or some of the system memory to also be written to persistent system memory such as a Solid-State Device (SSD).

To do this, the system platform needs to restore system power for a period of time, usually with some kind of backup power source or supercapacitor for the system, and have the SoC firmware/software write information to the persistent memory subsystem. Also, the platform may require special, on-board registers that are attached to the configured SoC Customer GPIO input signal pins, that later can be read by BIOS to determine a C2F situation.

Normally, when ADR_COMPLETE is asserted by the platform, the ADR sequence is not followed by a Global Reset. To facilitate C2F, the SoC can be configured to trigger a Global Reset once ADR_COMPLETE is asserted. To do so, these conditions must be met:

- ADR_GPIO_RST_EN bit of the ADR_EN register = 1, and
- ADR_FEAT_EN bit of the ADR_EN register = 1, and
- The product SKU supports the ADR feature, and
- The SoC internal ADR sequence has completed.

16.15.3 NVDIMM Copy-to-Flash

If NVDIMM is used for DRAM system memory by the platform design, the NVDIMMs integrated save-to-flash and restore-from-flash operations can be used once ADR_COMPLETE is asserted after an ADR sequence. NVDIMM has a SAVE# input pin, or a SAVE Serial Presence Detect (SPD) command via its SMBus interface, to instruct it to save its DRAM information (now in Self-Refresh Mode and powered by a resident supercapacitor) to its Flash memory. They also have a pin or SPD command to for the platform or BIOS to perform a RESTORE once the system returns to normal operation.

Note: At the time of publication of this document, there is no industry standard for NVDIMMs and for their SAVE and RESTORE pins and/or SPD commands. NVDIMM products typically follow the RDIMM JEDEC standards which has two reserved DIMM pins and reserved SPD registers. Platform designers and BIOS developers need to refer to NVDIMM technical information from NVDIMM manufactures for implementation details.

16.15.4 ADR Sequence of Events

1. BIOS has previously configured the SoC and has made necessary adjustments to the ADR_EN register and then sets the ADR_FEAT_EN bit. The ADR mechanism is armed and waiting.
2. The ADR_TRIGGER signal is asserted by the platform board indicating an imminent power failure has been detected or one of the enabled Qualified Internal Events (within the SoC) occurs. While the Global Reset triggers are captured in the GBLRST_CAUSE0 and GBLRST_CAUSE1 memory-mapped registers, the ADR sequence starts only if the particular trigger is enabled in the ADR_EN register.

Note: The active-high ADR_TRIGGER SoC pin is an open-drain output signal as well as an input signal. Not only can the board drive this signal pin, the SoC drives this pin high when one of the enabled Qualified Internal Events occurs. As long as the ADR-triggered event is valid, the ADR_TRIGGER remains asserted (logic high) by the SoC.

Warning: To indicate the deasserted state, the platform (and SoC) must float (High-Z state) the ADR_TRIGGER signal pin. The platform must have a pull-down resistor tied to this pin. The platform board must only drive this pin to logic 1, when it intends to assert ADR_TRIGGER. It must never drive this pin to a logic 0. The SoC drives this pin to a logic 1 only when one of the enabled, Qualified Internal Events occur. Otherwise the SoC floats (Hi-Z) this pin. The SoC never drives it to a logic 0.

3. The SoC closes all access paths to memory space.
4. All cores are put to sleep and L1 cache flushes are performed.
5. Internal data buffers holding dirty memory-write information are flushed.
6. Once all cores are idle, DRAM throttling is disabled.
7. If the SoC is configured to also flush the L2 caches during ADR, dirty writes in L2 cache are cleaned (written to DRAM). This could take some time to perform.
8. The SoC System Agent circuitry is made idle.
9. The SoC puts the SDRAM components in Self-Refresh Mode.
   - It is the platform's responsibility to maintain SDRAM/DIMM power and maintain the SDRAM components' Clock Enable input signals during Self-Refresh mode.
   - When the SDRAM is on an NVDIMM product, a supercapacitor, that is part of the NVDIMM product, powers the SDRAM while in Self-Refresh Mode.

Note: In order to continue the ADR sequence, the SoC internal timer for ADR completion must not have expired at this point. Ending the sequence at this point indicates that there was not enough time or power-level to complete the ADR sequence or that an internal error that prevented completion of the sequence. Nothing happens and the G3 state (mechanical off) is entered when power is finally lost.

10. The SoC sets ADR_RST_STS, bit 16 of the PCH Power Management Status (PCH_PM_STS) register located in memory space at PWRMBASE, offset 1Ch.
    — The ADR_RST_STS register bit is powered by the SoC RTC Power Well. The SoC must be provided power for the RTC well (VCCRTC_3P3_G3, pin AU48) for this register bit to be preserved during the G3 State (Mechanical Off).
11. The SoC asserts the ADR_COMPLETE output signal pin.
12. Depending on the information in the ADR_EN register, the SoC does one of the following:

- Initiates a Global Reset with an automatic power-up to the S0 state and start of BIOS execution. The platform-defined Copy-to-Flash extension relies on this reset and BIOS entry.
  — Before the SoC starts the power-up, it waits in the S5 state for about five seconds. No wake event is needed to exit S5.
  — Internal SoC registers are reset except for the RTC power-well registers and registers and functional logic in other SoC power wells needed to report this Global Reset.
- Transitions directly to the S5 State and waits for some kind of wake event.
  — The SoC output signal pins PMU_SLP_S3_N and PMU_SLP_S45_N are asserted.
  — Internal SoC registers are reset except for the RTC power-well registers and registers and functional logic in other SoC power wells needed to report this status.
  — Once the SoC asserts the ADR_COMPLETE output signal pin, and the "AG3E Boot Select" Soft Strap = 1 (see Section 4.2, "SoC Soft Straps" on page 199), the platform needs to drive the PMU_PWRBTN_N or PMU_WAKE_N SoC input signal, or configure and drive a wake-supported Customer GPIO (see Chapter 26, "Customer General-Purpose I/O (GPIO)") input to wake-up the SoC from the S5 state.
- Once awakened, the SoC powers-up and enters the S0 state where BIOS begins instruction execution.
  — If the "AG3E Boot Select" Soft Strap = 0, the SoC does not wait for a wake-up event to proceed. Here the SoC enters the S0 state and BIOS commences. For Soft Strap details, see Chapter 4, "Strapping and Configuration".

16.15.5 BIOS after Successful ADR

BIOS uses the ADR_RST_STS, bit 16 of the PCH Power Management Status (PCH_PM_STS) register to determine that a successful ADR sequence occurred before BIOS initiated. It also uses the SoC registers of the Customer GPIO input signals provided by the platform to signify a successful Copy-to-Flash (C2F). The BIOS sequences for ADR and C2F are not discussed in this document.

16.16 Register Map

Figure 16-2, "Register Map" shows the associated registers from a system software viewpoint.

Figure 16-2. Register Map



16.16.1 PCI Configuration and Capabilities

Table 16-8. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D31:F2 (hex)	Register Short Name	Description
00	PCIID	PCI Identifier
04	PCISTS_PCICMD	Device Status & Command
08	PCICC_PCIRID	Class Code & Revision ID
0C	PCIHTYPE_PCIMLT	Header Type and Master Latency Timer
10	PM_DATA_BAR	32-bit Power Management Data Base Address Register
2C	PCISID	Subsystem Identifiers
40	ABASE	ACPI Base Address
44	ACTL	ACPI Control
48	PWRMBASE	PM Base Address
A0	GEN_PMCON_A	General PM Configuration A
A4	GEN_PMCON_B	General PM Configuration B
A8	BM_CX_CNF	BM_BREAK_EN and Cx State Configuration Register
AC	ETR3	Extended Test Mode Register 3
B0	PMC_THROT_1	PMC Throttling 1
C0	MDAP	Maximum DMA Alignment Period
F8	MANID	Manufacturer ID

16.16.2 Memory-Mapped Registers

Table 16-9. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
PWRMBASE	1C	PCH_PM_STS	PCH Power Management Status
PWRMBASE	F0	ADR_EN	ADR Enable
PWRMBASE	124	GBLRST_CAUSE0	Global Reset Causes
PWRMBASE	128	GBLRST_CAUSE1	Global Reset Causes
MCHBAR_LO_0_0_0_PCI MCHBAR_HI_0_0_0_PCI	712h	P_CR_ADR_COMMAND_0_0_0_MCHBAR	ADR Command

The PMC device/function has no Fixed-Address Memory-Mapped Registers.

16.16.3 I/O-Mapped Registers

Table 16-10. Relocatable I/O-Mapped Registers - Power Management Controller (PMC)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
ACPI Base Address (ABASE)			
ABASE	00	PM1_EN_STS	Power Management 1 Enables and Status
ABASE	04	PM1_CNT	Power Management 1 Control
ABASE	08	PM1_TMR	Power Management 1 Timer
ABASE	30	SMI_EN	SMI Control and Enable
ABASE	34	SMI_STS	SMI Status Register
ABASE	40	GPE_CTRL	General Purpose Event Control
ABASE	44	DEVTRAP_STS	Device Trap Status Register
ABASE	50	PM2A_CNT_BLK	PM2a Control Block
ABASE	54	OC_WDT_CTL	Over-Clocking WDT Control
ABASE	80	GPE0_STS_31_0	General Purpose Event 0 Status [31:0]
ABASE	84	GPE0_STS_63_32	General Purpose Event 0 Status [63:32]
ABASE	88	GPE0_STS_95_64	General Purpose Event 0 Status [95:64]
ABASE	8C	GPE0_STS_127_96	General Purpose Event 0 Status [127:96]
ABASE	90	GPE0_EN_31_0	General Purpose Event 0 Enable [31:0]
ABASE	94	GPE0_EN_63_32	General Purpose Event 0 Enable [63:32]
ABASE	98	GPE0_EN_95_64	General Purpose Event 0 Enable [95:64]
ABASE	9C	GPE0_EN_127_96	General Purpose Event 0 Enable [127:96]

Table 16-11. Fixed-Address I/O-Mapped Registers

I/O Address (hex)	Register Short Name	Register Long Name
CF9	RST_CNT	Reset Control Register

Table 16-12. Relocatable I/O-Mapped Registers - Legacy SMBus Controller

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
TCOBASE	00	TRLD	TCO_RLD Register
TCOBASE	02	TDI	TCO_DAT_IN Register
TCOBASE	03	TDO	TCO_DAT_OUT Register
TCOBASE	04	TSTS1	TCO1_STS Register
TCOBASE	06	TSTS2	TCO2_STS Register
TCOBASE	08	TCTL1	TCO1_CNT Register
TCOBASE	0A	TCTL2	TCO2_CNT Register
TCOBASE	0C	TMSG	TCO_MESSAGE1 and TCO_MESSAGE2
TCOBASE	0E	TWDS	TCO_WDSTATUS Register
TCOBASE	0F	RSV_1	Reserved_1
TCOBASE	10	LE	LEGACY_ELIM Register
TCOBASE	11	RSV_2	Reserved_2
TCOBASE	12	TTMR	TCO_TMR Register
TCOBASE	14	RSV_3	Reserved_3
TCOBASE	1C	RSV_4	Reserved_4

16.16.4 Sideband Registers

Table 16-13. Sideband Registers - Power Management Control (PMC)

Sideband Port (hex)	Offset (hex)	Register Short Name	Register Long Name
82	82_00B0	APM_STS_CNT	Advanced Power Management Status and Control Port
	82_00B4	MISC_SBR0	Misc SB Reg0
	82_00B8	MISC_SBR1	Misc SB Reg1
	82_00BC	MISC_SBR2	Misc SB Reg2

Table 16-14. Sideband Registers - Legacy SMBus (for TCO)

Sideband Port (hex)	Offset (hex)	Register Short Name	Register Long Name
CF	CF_0000	TCOCFG	TCO Configuration

§ §

17 Embedded Multi-Media Card (eMMC)

The Embedded Multi-Media Controller (eMMC) is a high-speed Flash memory controller. The controller presents itself to the host as Bus 0, Device 28, and Function 0 during PCI bus enumeration process. This controller handles eMMC protocol at transmission, packing data, adding cyclic redundancy check (CRC), start/end bit, and checks for transaction format correctness.

Figure 17-1. What is Covered in This Chapter



Table 17-1. References

Reference	Revision	Date	Document Title
eMMC Spec	5.0	Oct 2013	*Embedded Multi-Media Card (eMMC), Electrical Standard*

17.1 Signal Descriptions

The signal descriptions are shown in Table 17-2. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing". The Direction column of Table 17-2 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit

Table 17-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
EMMC_CLK	I,O	Yes	**Clock**
EMMC_CMD	I,O	Yes	**Command:** The platform requires a 20k Ohm pull-up resistor, tied to 1.8V for this signal.
EMMC_D[7:0]	I,O	Yes	**Data:** The platform requires a 20k Ohm pull-up resistor, tied to 1.8V for these signals.
EMMC_IRCOMP	I,O	No	**RCOMP for the eMMC interface**: The platform board must provide a 200 Ω, 1% resistor connected from this pin to VSS.
EMMC_STROBE	I	Yes	**Strobe for Rx Data**

17.2 Feature List

- Supports eMMC 5.0 and eMMC 4.5.
- 8-bit interface, maximum frequency of 200 MHz (data transfer rates of 400 MB/sec).
- Supports interrupt coalescing.
- Supports both DMA and non-DMA mode operation.
- Supports data transfers in 1-, 4- and 8-bit mode.
- Supports cyclic redundancy check CRC7 for command and CRC16 for data integrity.
- eMMC interface can be a boot interface to boot an Operating System.

17.3 Architectural Overview

There are two supported modes of operation, PCI and ACPI modes. Upon controller power-on this controller exposes itself as a PCI-compliant device to the host space. For details on how to configure this device as a ACPI device, see Section 17.4, "Address Map" on page 559.

17.3.1 eMMC Mass Storage Command and Data Flows

Host software is to manage data transfer to and from controller to the host memory.

Following steps describe data flows to and from the controller.

1. Host prepares the controller for data transfer by writing DMA descriptor(s) in the host memory.
2. Host write the controller registers to initiate the descriptor chain.
3. Controller moves data from the host memory to the device card.
4. Controller DMA notifies the IOxAPIC after the DMA is done.
5. IOxAPIC forwards the interrupt the host as MSI.

17.3.2 PCI Mode and ACPI Mode

The eMMC can be configured to work in either PCI Mode or ACPI Mode. The configuration is done via a write to the IOSF2OCP Sideband register. By default the eMMC is set to PCI Mode. To change the eMMC to ACPI Mode, it first needs to be enumerated and assigned a BAR. Once this is done, it is possible to configure the device to be an ACPI device (ACPI Mode). Its address shall be the configured BAR address.

17.4 Address Map

From the host point of view, the eMMC device has a 4KB BAR address space. The 4KB is divided into two regions

1. The device internal registers – a 2KB address space which maps the device internal registers.
2. Extended Configuration Registers – a 2KB address space which maps all the extended configuration.

17.5 Register Map

Figure 17-2 shows the associated registers from a system software viewpoint.

Figure 17-2. Register Map



17.5.1 PCI Configuration and Capabilities

Table 17-3. Configuration and Capabilities Register Map

Address	Default	Instance Name	Name
0x0	19DB_8086h	DEVVENDID	Device ID and Vendor ID Register
0x4	0010_0000h	STATUSCOMMAND	Status and Command
0x8	0805_0100h	REVCLASSCODE	Revision ID and Class Code
0xC	0080_0000h	CLLATHEADERBIST	Cache Line Latency Header and BIST
0x10	0000_0004h	BAR	Base Address Register
0x14	0000_0000h	BAR_HIGH	Base Address Register High
0x18	0000_0004h	BAR1	Base Address Register1
0x1C	0000_0000h	BAR1_HIGH	Base Address Register1 High
0x2C	0000_0000h	SUBSYSTEMID	Subsystem Vendor and Subsystem ID
0x30	0000_0000h	EXPANSION_ROM_BASEADDR	EXPANSION ROM Base Address
0x34	0000_0080h	CAPABILITYPTR	Capabilities Register
0x3C	0000_0000h	INTERRUPTREG	Interrupt Register
0x80	0003_9001h	POWERCAPID	Power Management Capability ID
0x84	0000_0008h	PMECTRLSTATUS	Power Management Control Status
0x90	F014_0009h	PCIDEVIDLE_CAP_RECORD	PCI Device Idle Capability Record
0x94	0140_0010h	DEVID_VEND_SPECIFIC_REG	DEVID Vendor Specific Reg
0x98	0000_8041h	D0I3_CONTROL_SW_LTR_MMIO_REG	SW LTR Update MMIO Location Register
0x9C	0000_81C1h	DEVICE_IDLE_POINTER_REG	Device IDLE Pointer Register
0xA0	0029_0800h	D0I3_MAX_POW_LAT_PG_CONFIG	Device PG Config
0xB0	0000_0000h	GEN_REGRW1	General Purpose Read Write Register1
0xB4	0000_0000h	GEN_REGRW2	General Purpose Read Write Register2
0xB8	0000_0000h	GEN_REGRW3	General Purpose Read Write Register3
0xBC	0000_0000h	GEN_REGRW4	General Purpose Read Write Register4
0xC0	0000_0000h	GEN_INPUT_REG	General Purpose Input Register
0xF8	0000_000Fh	MANID	Manufacturers ID

17.5.2 Memory-Mapped Registers

Table 17-4. Memory-Mapped Registers (Sheet 1 of 2)

Address	Default	Instance Name	Register Long Name
0x0	0000_0000h	SDMASYSADDR	SDMA System Address Register/Argument2 Register
0x4	0000h	BLOCKSIZE	BlockSize Register
0x6	0000h	BLOCKCOUNT	BlockCount Register
0x8	0000_0000h	ARGUMENT1	Argument1 Register
0xC	0000h	TRANSFERMODE	TransferMode Register
0xE	0000h	COMMAND	Command Register
0x10	0000_0000h	RESPONSE1	Response Register
0x14	0000h	RESPONSE2	Response Register
0x16	0000h	RESPONSE3	Response Register
0x18	0000h	RESPONSE4	Response Register
0x1A	0000h	RESPONSE5	Response Register
0x1C	0000h	RESPONSE6	Response Register
0x1E	0000h	RESPONSE7	Response Register
0x20	0000_0000h	DATAPORT	Buffer DataPort Register
0x24	0000_0000h	PRESENTSTATE	PresentState Register
0x28	00h	HOSTCONTROL1	HostControl1 Register
0x29	00h	POWERCONTROL	PowerControl Register
0x2A	80h	BLOCKGAPCONTROL	BlockGapControl Register
0x2B	00h	WAKEUPCONTROL	Wakeup Control Register
0x2C	0000h	CLOCKCONTROL	Clock Control Register
0x2E	00h	TIMEOUTCONTROL	Timeout Control Register
0x2F	00h	SOFTWARERESET	Software Reset Register
0x30	0000h	NORMALINTRSTS	Normal Interrupt Status Register
0x32	0000h	ERRORINTRSTS	ErrorInterruptStatus_Register
0x34	0000h	NORMALINTRSTSENA	Normal Interrupt Status Enable Register
0x36	0000h	ERRORINTRSTSENA	Error Interrupt Status Enable Register
0x38	0000h	NORMALINTRSIGENA	Normal Interrupt Signal Enable Register
0x3A	0000h	ERRORINTRSIGENA	Error Interrupt Signal Enable Register
0x3C	0000h	AUTOCMDERRSTS	Auto CMD12 Error Status Register
0x3E	0000h	HOSTCONTROL2	Host Control2 Register
0x40	0000_0000_0000_0000h	CAPABILITIES	Capabilities Register
0x48	0000_0000_0000_0000h	MAXCURRENTCAP	Maximum Current Capabilities Register
0x50	0000h	FORCEEVENTFORAUTOCMDERRORSTATUS	Force Event REGISTER for AUTO CMD Error Status
0x52	0000h	FORCEEVENTFORERRINTSTS	Force Event Register for Error Interrupt Status
0x54	00h	ADMAERRSTS	ADMA Error Status Register
0x58	0000_0000h	ADMASYSADDR01	ADMA System Address Register0&1
0x5C	0000h	ADMASYSADDR2	ADMA System Address Register1

Table 17-4. Memory-Mapped Registers (Sheet 2 of 2)

0x5E	0000h	ADMASYSADDR3	ADMA System Address Register1
0x60	0003h	PRESETVALUE0	Preset Value Register for Initialization
0x62	0003h	PRESETVALUE1	Preset Value Register for Default Speed
0x64	0003h	PRESETVALUE2	Preset Value Register for High Speed
0x66	0003h	PRESETVALUE3	Preset Value Register for SDR12
0x68	0002h	PRESETVALUE4	Preset Value Register for SDR25
0x6A	0001h	PRESETVALUE5	Preset Value Register for SDR50
0x6C	0000h	PRESETVALUE6	Preset Value Register for SDR104
0x6E	0002h	PRESETVALUE7	Preset Value Register for DDR50
0x70	0000_0000h	BOOTTIMEOUTCNT	Boot Timeout Control Register
0x74	0000h	PRESETVALUE8	Preset Value Register for DDR50
0xFC	0000h	SLOTINTRSTS	Slot Interrupt Status Register
0xFE	1002h	HOSTCONTROLLERVER	Host Controller Version Register

17.5.3 I/O-Mapped Registers

There are no I/O mapped registers.

§ §

18 High-Speed UART Controller

The SoC contains four[1] integrated High-Speed Universal Asynchronous Receiver/Transmitter (HSUART) serial ports. Each UART port signal may be shared and MUXed with other functional blocks (i.e., GPIO, SMBus, etc.).

Figure 18-1. What is Covered in This Chapter



Table 18-1. References

Reference	Revision	Date	Document Title
PC16550D UART Specification	Rev C	May 2015	*PC16550D Universal Asynchronous Receiver/Transmitter With FIFOs (Rev. C)*

1. At most, three of the SoC four High Speed Universal Asynchronous Receiver/Transmitter (HSUART) controllers can be active. One set of the SoC HSUART pins is configurable to be either the Host Root HSUART or else the Innovation Engine (IE) HSUART.

18.1 Signal Descriptions

The signal descriptions are shown in Table 18-2. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. The Direction/Type column of Table 18-2 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.

Table 18-2. Signal Names and Descriptions

Signal Names	Direction	Description
UART 0		
UART0_RXD	I	**UART0 Receive Data:** Active-high input
UART0_TXD	O	**UART0 Transmit Data:** Active-high output
UART0_CTS	I	**UART0 Clear to Send:** Active-high input
UART0_RTS	O	**UART0 Request to Send:** Active-high output
UART 1		
UART1_RXD	I	**UART1 Receive Data:** Active-high input
UART1_TXD	O	**UART1 Transmit Data:** Active-high output
UART1_CTS	I	**UART1 Clear to Send:** Active-high input
UART1_RTS	O	**UART1 Request to Send:** Active-high output
UART 2		
UART2_RXD	I	**UART2 Receive Data:** Active-high input
UART2_TXD	O	**UART2 Transmit Data:** Active-high output
UART2_CTS	I	**UART2 Clear to Send:** Active-high input
UART2_RTS	O	**UART2 Request to Send:** Active-high output
UART Innovation Engine[1]		
UART_IE_RXD	I	**UART_IE Receive Data:** Active-high input
UART_IE_TXD	O	**UART_IE Transmit Data:** Active-high output
UART_IE_CTS	I	**UART_IE Clear to Send:** Active-high input
UART_IE_RTS	O	**UART_IE Request to Send:** Active-high output

1. All Innovation Engine (IE) related material described in this section can be reference to Chapter 37, "Innovation Engine".

Figure 18-2. UART MUXed Signals



18.2 Feature List

18.2.1 UART Features

- 16550 and 16750 compliant UART controllers
- 64-byte FIFO for each receiver and transmitter
- Programmable interrupt trigger levels for FIFOs
- Baud generation based on programmable multipliers and divisors
- Supports programmable baud rates from 300 bps to 3.6864 Mbps
- Data rate can be programmed using the multiplier and divisor of the direct digital synthesizer.
- Auto-baud rate detection capability
- Flow control by hardware (HW) or software (SW)
- Configurable data format
- Data bits: 5, 6, 7, or 8 bits
- Even, odd, or no parity generation
- 1, 1.5, 2 stop bits
- False start-bit detection
- Line break generation/detection
- Prioritized interrupt
- Supports DMA and non-DMA mode for data access
- Complete status report capabilities

18.2.2 DMA Features

- Supports 32-bit data and addressing
- Dedicated TX and RX channel for each UART
- Each DMA channel has four descriptors
- Configurable interrupt generation for DMA operation
- Support for timeout
- Supports a single outstanding request at a time
- Uses round robin arbitration among active channels
- Support to generate non-DW aligned memory requests

18.3 Architectural Overview

The UART operates per the 16550 component specifications with optional DMA support. The UART can operate in legacy or enhanced mode. The first eight bytes of the 16550 register are set in addition to other registers for the enhanced UART mode.

Figure 18-3. UART Core Block Diagram Overview



18.3.1 UART Hiding and Locking

The 3 IA Host space UART devices are implemented as PCI devices that are discovered by PCI enumeration. The system BIOS always preforms PCI enumeration and the OS may re-enumerate the bus. This can cause the UART devices to move between BIOS and OS.

If your system does not use any or all of the UARTs the BIOS can hide them before preforming the PCI enumeration. The BIOS does this by writing to each UART PCI configuration space register FUNC_RDCFG_HIDE. UART devices must be hidden from UART 3, then UART 2, and lastly UART 1.

If your system requires the UART to be at a legacy COM 1, 2, 3 or 4 address then before PCI enumeration BIOS can assign the legacy I/O address and MMIO address space (if DMA is required). BIOS must also enabled the I/O address decoding by writing bit 0 of CMD_STAT_REG to 1'b1 and if used the MMIO address decoding by writing bit 1 to 1'b1. Then BIOS would hide the UART via PCI configuration space register FUNC_RDCFG_HIDE. In addition BIOS must setup the SoC to route the COM address to the UART and not to the LPC interface. See Table 3-3, “Host Fixed I/O Address Space” on page 176 for the COM address assigned on what additional registers need to be programmed.

If any of the UART devices are left as PCI enumerable (not hidden or put at a legacy COM address) they must be from low to high UART 1, then UART 2 then UART3.

Table 18-3. Legacy COM I/O Ports

COM Port	I/O Ports
COM1	3F8h – 3FFh
COM2	2F8h – 2FFh
COM3	3E8h – 3EFh
COM4	2E8h – 2EFh

18.3.2 Legacy Mode

In the legacy mode, the UART operates per the 16550 component specifications. The UART requests the eight bytes of I/O and 256 bytes of memory space using the corresponding PCI BAR0 (I/O Base Address Register, IOBA) and BAR1 (Memory Base Address Register, MEMBA). MEMBA is only required if your system uses the DMA feature.

The UART TX and RX FIFO depth can be configured to 64 bytes as opposed to only 16 bytes supported by 16550. This UART does not support DMA in legacy mode and does not comply with the DMA signaling mechanism outlined in the 16550 specifications.

18.3.3 Enhanced Mode

In the enhanced mode, the enhanced register set is available in addition to the legacy mode Command/Status Registers. The UART requests 256 bytes of the memory space per function using BAR1. In the enhanced mode, the memory space is required to be enabled. The UART supports the following additional features in the enhanced mode:

- Programmable UART base frequency using a clock multiplier and divisor
- FIFO size up to 64 bytes
- Baud rates higher than 115.2 kbps (see Table 18-4)
- Auto-baud detection capability
- Auto-flow mode
- DMA capability

18.3.4 UART Function

The UART transmits and receives data in bit frames. Each data frame is between 7 and 12 bits long, depending on the size of data programmed, whether parity is enabled or disabled, and the number of stop bits. The frame begins with a start bit that is represented by a high-to-low transition. Next, 5 to 8 bits of data are transmitted, beginning with the least significant bit. An optional parity bit follows, if enabled. The data frame ends with 1, 1.5, or 2 stop bits (as programmed), represented by 1 or 2 successive bit periods of a logic one.

Figure 18-4. UART Data Transfer Flow



The UART serial bit frames are encoded, where a 1 is represented by a line transition, and a 0 is represented by no line transition. Figure 18-5 shows the coded full 7-bit character 1100110 with no parity and 2 stop bits. The LSB of a byte is transmitted first.

Figure 18-5. 7-bit Character Encoding



Out of reset, the UART transceiver is enabled with the default register configuration. The UART transceiver can be disabled by clearing the UART Unit Enable (UUE) bit of the Auto-Baud Control register. When UUE is set, the receiver looks for the start bit of a frame and the transmitter sends data if data is available in the Transmit FIFO or Transmit Holding register. Disabling the transceiver with the UUE bit does not clear the data in the receive/transmit FIFO. Re-enabling the UART will continue transmission/reception with the original data.

Each UART has a transmit FIFO and a receive FIFO and each can store 64 characters of data. There are two separate methods for moving data into and out of the FIFOs: interrupts and polling. The UART also supports the full and half-auto flow control mode for transmission and receive. The UART baud rate can be configured or it also can support the auto-baud rate detection feature. Key UART modes and features are discussed in subsequent sections.

18.3.5 FIFO Interrupt Mode Operation

18.3.5.1 Receive Interrupt

When the receive FIFO (FCR [TRFIFOE] = 1) and the receiver interrupt (IER [RDA] = 1) are enabled, the following receiver interrupts can occur:

- The receive data available interrupt is asserted when the FIFO has reached its programmed trigger level. The interrupt is cleared when the FIFO drops below the programmed trigger level.
- The IIR [IID] receive data available indication also occurs when the FIFO trigger level is reached, and like the interrupt, the bits are cleared when the FIFO drops below the trigger level.
- The Data Ready bit (LSR [DR]) is set to 1 as soon as a character is transferred from the Shift register to the receive FIFO. This bit is reset to 0 when the FIFO is empty.

18.3.5.2 Timeout Interrupt

When the receive FIFO and receiver interrupt are enabled, a character timeout interrupt (IIR [TOD]) will occur to signal the presence of trailing bytes. The interrupt is cleared and the timer is reset when a character is read from the receiver FIFO. If a timeout interrupt has not occurred, then the timeout timer is reset after a new character is received or after the processor reads the receiver FIFO. Character timeout will occur when all the following conditions are true:

- At least one character is in the FIFO.
- A character has not been received for the amount of time it takes to receive four or more characters at the current baud rate.
- The FIFO has not been read for the amount of time it takes to receive four or more characters at the current baud rate.

18.3.5.3 Transmit Interrupt

A character has not been received for the amount of time it takes to receive four or more characters at the current baud rate.

The FIFO has not been read for the amount of time it takes to receive four or more characters at the current baud rate.

When the transmit FIFO (FCR [TRFIFOE] = 1) and the transmitter interrupt (IER [TDRQ] = 1) are enabled, the following receiver interrupts can occur:

- When FCR [TIL] = 0, the transmit data request interrupt occurs whenever the transmit FIFO is empty. The interrupt is cleared as soon as the Transmit Holding register is written or the IIR is read.
- When FCR [TIL] = 1, the transmit data request interrupt occurs when the transmit FIFO is empty or the FIFO level reaches the half empty mark from more than half full. The interrupt is cleared as soon as the Transmit Holding register is written or the IIR is read.

Users could cause the UART transmit FIFO to overflow if too many characters are written. FIFO underflow does not cause an error as the UART will wait for the transmit FIFO to be serviced.

18.3.6 FIFO Polled Mode Operation

With the FIFOs enabled (FCR [TRFIFOE] = 1), clearing IER puts the serial port in the FIFO polled operation mode. Because the receiver and the transmitter are controlled separately, either one or both can be in the polled operation mode. In this mode, software checks the receiver and transmitter status via the Line Status Register (LSR). The processor polls the following bits for receive and transmit data service.

Receive Data Service

Poll the data ready (LSR [DR]) bit that is set when 1 or more bytes remain in the receive FIFO or Receive Buffer Register (RBR).

Transmit Data Service

Poll the transmit data request LSR [TDRQ] bit that is set when the transmit FIFO or Transmit Holding Register (THR) is empty.

Poll the transmitter empty LSR [TEMT] bit that is set when the transmitter is empty.

18.3.7 Auto-flow Control Operation

Auto-flow control uses the Clear-to-Send (CTS) and Request-to-Send (RTS) signals to automatically control the flow of data between the UART and the external serial device. When auto-flow is enabled, the remote device is not allowed to send data unless the UART asserts RTS low. If the UART de-asserts RTS while the remote device is sending data, the remote device is allowed to send one additional byte after RTS is de-asserted. An overflow could occur if the remote device violates this rule. Likewise, the UART is not allowed to transmit data unless the remote device asserts CTS low. This feature increases system efficiency and eliminates the possibility of a receive FIFO overflow error due to long interrupt latency.

The auto-flow mode can be used in two ways: full auto-flow, automating both CTS and RTS; and half auto-flow, automating only CTS. Full auto-flow is enabled by writing a 1 to bits Modem Control Register (MCR) - MCR [AFE][1] and MCR [RTS] of the MCR. Auto-CTS-only mode is enabled by writing a 1 to MCR [AFE] and a 0 to MCR [RTS] of the MCR register.

The auto-flow mode can only be used in conjunction with the FIFO mode. During the auto flow mode, the modem interrupt should not be enabled.

The following are descriptions of RTS and CTS in both modes.

RTS (UART Output)

In full auto-flow mode, RTS is asserted when the UART FIFO is ready to receive data from the remote transmitter. This occurs when the amount of data in the receive FIFO is below the programmable threshold value. When the amount of data in the receive FIFO reaches the programmable threshold, RTS is de-asserted. It will be asserted once again when enough bytes are removed from the FIFO to lower the data level below the threshold.

CTS (UART Input)

In full or half auto-flow mode, CTS is asserted by the remote receiver when the receiver is ready to receive data from the UART. The UART transmitter checks CTS before reading the next byte from the FIFO and will not read the byte until CTS is low. If CTS goes high while the transfer of a byte is in progress or about to transfer a byte, the transmitter will complete the transmission of this byte.

1. Auto Flow Enable (AFE).

18.3.8 Loopback Operation

The loopback mode is on when MCR [LOOP] is set. During the loopback mode, the following will occur:

- The UART serial out TXD is set to an idle state. The UART serial input RXD is internally disconnected. The internal TX line is looped back into the internal RX line.
- The modem inputs are internally disconnected and modem outputs are connected to the disconnected inputs. The modem outputs are set to the idle state.

In the loopback mode, data that is transmitted is immediately received. This feature allows checking of the transmit and receive data paths of the UART.

In the loopback mode, receive and transmit interrupts are fully functional if enabled. The modem interrupts are also functional if enabled, but the sources of interrupt are the lower 4 bits of the MCR.

Note: Full auto-flow and loopback mode can be enabled simultaneously for efficient diagnostic testing. Half auto-flow and loopback mode should not be enabled simultaneously.

18.3.9 Auto-Baud Detection

Each UART supports auto-baud rate detection. This feature is only available in enhanced mode. When enabled, the UART counts the number of reference clock cycles within the receive start-bit pulse. The frequency of the reference clock is set when the UART clock gen is initialized. The default UART clock is 1.8432 MHz. The number of UART clock pulses in the start bit is written into the Auto-Baud Count Register (ACR) and is used to determine the baud rate. When the ACR is written, an auto-baud lock interrupt is generated (if enabled), and the UART can automatically program the Divisor Latch registers with the appropriate baud rate. If preferred, the processor can read the Auto-Baud Count register and use this information to program the Divisor Latch registers with a baud rate calculated by the processor. After the baud rate has been programmed, the host is responsible to verify that the predetermined characters (usually AT or at) are being received correctly.

If the UART is allowed to program the Divisor Latch registers in the auto-baud mode, users can choose between two methods for auto-baud calculation: table-based and formula-based. The method is selected via bit Auto-baud Table (ABT) of the Auto-Baud Control Register (ABR). When the formula-based method is used, the baud rate, based on the number of UART clock pulses in the start bit, can be programmed by the UART. This method works well for higher baud rates, but could possibly fail below 28.8 Kbps because of the fine resolution of the clock measuring the duration of the start bit, especially when the duration of the start bit is not exactly equal to the nominal due to the use of slow level translators. The actual baud rate may differ by more than one percent of its target.

Once the baud rate is detected the first time, the auto-baud circuitry will disarm itself by clearing bit ABE of the Auto-Baud Control Register (ABR). The Auto-Baud Enable (ABE) bit must be written as 1 by software to rearm the circuitry.

For the auto-baud rate detection circuit to work correctly, the first data bit transmitted after the start bit must be logic 1. If logic 0 is transmitted instead, the auto-baud circuit will count the 0 as part of the start bit, resulting in an incorrect baud rate being programmed into the Divisor Latch Low (DLL) and Divisor Latch High (DLH registers. The input signal with a baud rate less than 150 bps will result in undefined behavior of the auto-baud detection circuitry.

18.3.10 UART Clocking

The UART clock is derived from internal SoC clock system.

FUART = 44236800 Hz

18.3.11 UART Baud Rate Generation

The baud rates are generated from the UART base frequency (FUART) by programming the Divisor Latch Access Bit (DLAB) from Line Control Register (LCR.DLAB) and Pre-Scalar (PSR) registers.

FBAUD = FUART / (PSR/ DLAB)

To get the supported baud rates as mentioned in table below, use FUART = 44236800 Hz.

Table 18-4. Supported Baud Rates

FUART (Hz)	PSR	LCR.DLAB	FBAUD (bps)
44236800	0C	0001h	3686400
44236800	10C	0003h	921600
44236800	10C	0006h	460800
44236800	10C	0009h	307200
44236800	10C	000Ch	230400
44236800	10C	000Fh	184320
44236800	10C	0012h	153600
44236800	10C	0018h	115200
44236800	10C	0030h	57600
44236800	10C	0048h	38400
44236800	10C	0090h	19200
44236800	10C	0120h	9600
44236800	10C	0180h	7200
44236800	10C	0240h	4800
44236800	10C	0300h	3600
44236800	10C	0480h	2400
44236800	10C	0600h	1800
44236800	10C	0900h	1200
44236800	10C	1200h	600
44236800	10C	2400h	300

18.3.12 I/O and Memory Base Access Space

The UART supports 8 bytes of I/O space and 256 bytes of memory space to access registers of the UART. The lower 8 bytes are compliant to the 16550 UART. While addresses beyond 8 bytes give access to more advance features which include an auto-baud lock mechanism, DMA channel access, and higher baud rates.

Configure BAR0 (I/O Base Address Register, IOBA) by placing the device anywhere in the 16-bit I/O address space.

Configure BAR1 (Memory Base Address Register, MEMBA) by placing the device anywhere in the 32-bit memory address space.

18.3.13 Interrupt

The UART supports MSI messages to communicate interrupts.

In the event the MSIMC[MSIE] is set to 1, it is mandatory to configure the MSI address and MSI data properly in order to identify the MSI interrupt from this device.

Table 18-5. Interrupt Enabling

	CMD[ID] = 0	CMD[ID] = 1
MSIMC[MSIE] = 1	MSI sent via primary Interface	No interrupt to host

18.3.14 Memory Address MAP

The memory map is split between the UART Memory Mapped registers Table 18-10 and the DMA channel registers Table 18-11. The UART registers are mapped to the first 128 bytes in the memory map. Each DMA channel takes the next 64 bytes. The total memory requirement for a single function is shown in Table 18-6.

Table 18-6. UART Memory Space

Block	Memory Size	Base Address	Description
UART[n]	128 bytes per function	0x00	UART memory space requirement
DMA Channel[0]	64 bytes for read channel	0x80	DMA memory space read requirement
DMA Channel[1]	64 bytes for write channel	0xC0	DMA memory space write requirement

18.3.15 DMA

The UART provides optional support for direct memory access transactions that isolate the CPU from the need to deliver large chunks of data to or from the main memory to the UART FIFOs.

Figure 18-6. DMA Block Diagram



Each UART has a dedicated read and write channel that will handle read and writes to the host memory. DMA channels have around robin arbiter that arbitrates the requests from all the channels.

Each channel has four descriptor sets. Each has its own Start Address Register (SAR) and Transfer Size Register (TSR). The channel logic chases each descriptor on a round robin manner, i.e., once descriptor 0 is completely done, it moves to descriptor 1, and once descriptor 3 is done it goes back to descriptor 0.

Each descriptor that is active and selected for chasing, delivers the start address and the transfer size. The channel logic decides the actual transfer size, based on the availability of data/space in the buffer and based on the minimal/maximal transfer size programmed to that channel. The descriptor is described as following:

- Start address + actual transfer size -> start address
- Transfer size - actual transfer size -> transfer size
- The design ensures that actual transfer size <= transfer size.

Once the descriptor transfer size reaches 0, the descriptor is considered to be completed and the channel logic can move to chasing the next descriptor.

18.3.15.1 Channel Arbitration

DMA channel arbitration has the following key functionality:

- Round robin arbitration scheme is used.
- The arbiter scans all the channels and whenever a channel has a valid request, the arbiter will send the request to the host interface if it is ready.
- Once the current request is done, the arbiter moves to the next channel, even if the current channel wishes to perform another transfer.

Figure 18-7. Logical Representation of Channel Arbitration



18.3.15.2 Descriptor Arbitration

The descriptor arbitration within each DMA channel has following key functionality:

- Round Robin progresses 0 -> 1 -> 2 -> 3 -> 0 and so on.

On reset, the current descriptor points to descriptor 0. Descriptor arbitration is a function of the descriptor active, descriptor request size, and descriptor timeout for the corresponding descriptor. The descriptor select logic advances from one descriptor to the next once the transfer size on the current selected descriptor is down to 0 or a timeout condition is encountered during these events, the descriptor active bit will be cleared which results in an invalid descriptor.

When all descriptors are invalid, the current descriptor will immediately point to descriptor 0. The descriptor select logic starts with the first programmed valid descriptor. The current descriptor status is logged into the Channel Status register.

Any descriptor with a non-zero request size but an inactive descriptor active bit will not place the request to the channel arbiter.

Figure 18-8. Logical Representation of Descriptor Arbitration



18.3.16 MSI Generation

The UART has the capability to generate an MSI whenever the interrupt event happens within the UART or DMA units. The host needs to program the PCI MSI configuration registers to enable the MSI generation. The host needs to read the Capabilities Pointer (CP) PCI configuration register which points to the MSI Capability ID (MSICID) register. Then, the host needs to program the MSI Message Control (MSIMC) register, MSI Message Address (MSIMA) register, and MSI Message DATA (MSIMD) register to enable MSI generation for the UART. An MSI will be sent upstream as a posted write request to the address in MSIMA with the data value in MSIMD.

Once an MSI is enabled, legacy interrupt over sideband will be disabled. A single MSI is sent upstream whenever any of the interrupt is asserted. In the event of MSI software needs to read the relevant registers from all the three interrupt sources: UART, DMA read channel, and DMA write channel.

18.4 UART Programming Recommendation

This section is provided as recommendation steps for configuration sequencing for the UART programming.

18.4.1 Setup Access Space

The UART supports 8 bytes of the I/O space and 256 bytes of the MEM space to access registers of the UART. The lower 8 bytes are compliant to the 16550 UART. While addresses beyond 8 bytes give access to more advances features which includes the auto baud lock mechanism, DMA channel access, and higher baud rates.

Configure BAR0 (I/O Base Address Register, IOBA) by placing the device anywhere in the 16-bit I/O address space.

Configure BAR1 (Memory Base Address Register, MEMBA) by placing the device anywhere in the 32-bit memory address space.

18.4.2 Setup Interrupt

The UART supports MSI messages to communicate interrupts.

In the event that MSIMC[MSIE] is set to 1, it is mandatory to configure the MSI address and MSI data properly in order to identify an MSI interrupt from this device.

Table 18-7. Interrupt Enabling

	CMD[ID] = 0	CMD[ID] = 1
MSIMC[MSIE] = 1	MSI sent via primary interface	No interrupt to host

18.4.3 Space Enable

Once configuration of the PCI space is done, the host should enable the required space (Memory or I/O). Also, the host should allow the device to initiate a transaction as a master.

To enable memory space CMD[MSE] =1'b1 (1st bit, binary, set to 1)

To enable I/O space CMD[IOSE] = 1'b1

To enable device as a master CMD[BME] = 1'b1

18.4.4 DMA Programming

Even though the DMA channel number is fixed (i.e., Channel 0 is for DMA Rx and Channel 1 is for DMA Tx), it is mandatory to program CHnCR with the appropriate channel direction value. Note that "CHn" from register name represented to DMA Channel 0 and DMA Channel 1 for this chapter.

The UART has FIFO that holds 64 bytes in each direction (UART Tx and UART Rx). the same number must be configured to the Buffer Size register Channel n=channel number Status Register (CHnBSR).

The host has to enable the FIFO mode of the UART when needed to operate with DMA (FCR[TRIFIFOE]).

18.4.5 DMA Descriptor Use/Reuse

In the case when the DMA is enabled, every DMA channel supports four descriptors. Descriptor evaluation happens sequentially from 0 to 3 and then rolls over to 0 again.

It is important to know which descriptor to be evaluated first. Intel recommends to program the descriptor in a sequence rather than randomly.

Once the DMA indicates it is done with the transfer, the host must program the following registers in order for the DMA engine to chase the descriptors again. Failure in the sequence of this program may result in the DMA engine not working when the same descriptor is used again.

1. Deactivate the channel before modifying any descriptor values Channel n=channel number Control Register (CHnCR).
2. Disable all the descriptors (CHnDCR).
3. Program each descriptors of the respective channel with the appropriate value of SAR and TSR (CHnD0/1/2/3SAR, CHnD0/1/2/3TSR).
4. Change the minimum transfer size if required (CHnMOTSR).
5. Activate the channel (CHnCR).
6. Enable the required descriptors with the appropriate interrupt enable bits (CHnDCR).

18.4.6 Programming Optimization

18.4.6.1 Optimization Descriptor Programming Activities During DMA

Program TSR of each descriptor with a sufficient high value.

In the case of the DMA Rx, the host knows how many characters are required to be transferred. Therefore, it should use the full capacity of the TSR and SAR combination to transfer enough data at the UART Tx signals.

In the case of the DMA Tx, the host does not have the knowledge how much data is going to be received, but still the host can enable the timeout interrupt CHnDCR[27:24] for each descriptor. Also, program the fairly large value in TSR to minimize the descriptor programming cycles.

Note: The descriptors are still active when the DMA timeout happens, but the DMA done is not set. The DMA timeout acts as just a notification to the host that nothing is being received in last four character cycles. Also, the DMA engine empties the buffer towards the host with the appropriate address and length.

18.4.6.2 Optimization Access Time By UART During DMA

Channel minimum transfer size (CHnMTSR) instructs the DMA engine when to initiate a request towards the internal interface to the read/write data from the host memory. That means a smaller value shall initiate more requests with less payload size, and a higher value shall initiate less requests with a higher payload size.

This value must not increase the buffer size value in order to prevent overflow (in the case of DMA Tx) or deadlock (in the case of DMA Rx). For SoC I/O fabric UART, the maximum value that can be programmed is 64, and the minimum value that can be programmed is 1.

Intel recommends to program this register with value = 60 on the safe side and to optimize the Dword boundary access.

18.4.6.3 Optimization Interrupt Handling

The UART has two sources of interrupt and shares a common interrupt notification source to communicate an interrupt to the host. If an interrupting condition from the source is not cleared, a subsequent interrupt shall not be communicated. So it is very important to clear the interrupt source upon receipt by the host.

18.4.6.3.1 DMA Interrupt Handling

This section contains interrupt sources which can occur only when the UART is running in the DMA mode.

Descriptor Done Interrupt

When the DMA engine transfers the configured amount of characters (configured via TSR), the DMA engine asserts this interrupt to notify the host to reprogram the respective descriptor. In order to avoid more interrupts from this source, the host may chose to enable this interrupt only for the upper descriptor. For example, if three descriptors are programmed, counting from 0 -> 1 ->2, enable a done interrupt only for descriptor 2. This will skip an interrupt to the host when descriptor 0 and descriptor 1 are completed.

The cost that the host needs to pay is to keep track of which descriptors were programmed before.

This interrupt gets cleared upon reading the DMA interrupt status register.

Descriptor Timeout Interrupt

This interrupt acts as more of a notification of any action for the host. A timeout interrupt can never happen for the DMA Rx channel (Channel 0). Upon character timeout, the HSUART interrupts the host and then activates DMA Tx to flush the trailing bytes from the buffer.

This interrupt gets cleared upon reading the DMA interrupt status register.

18.4.6.3.2 UART Interrupt Handling

This section contains interrupt sources from the UART. The 16550 has the following five types of interrupts.

Receive Data Available Interrupt

This interrupt notifies the host that at least a configured number of characters are present in the buffer. The lower the number, the more frequent interrupts can be expected.

The threshold for this interrupt can be controlled through the FCR[ITL] value.

Note: In the DMA mode, this interrupt acts as a notification only. The DMA engine takes care of transferring the data to the host memory when the Rx buffer gets up to a minimum transfer size.

Programming this interrupt in the DMA mode may block any further interrupt communicated by the DMA or UART source if this interrupt is on. For instance, if FCR[ITL] is programmed to a value 00, upon every SoC I/O fabric transfer, which empties the Rx buffer, this interrupt gets de-asserted, and upon receiving the first character interrupt gets asserted.

Intel recommends to disable this interrupt when running with the DMA mode.

Transmit Data Request Interrupt

This interrupt notifies the host about availability for more characters in the transmit FIFO. The threshold for this interrupt can be controlled with the FCR[TIL] bit value.

Note: In the DMA mode, this interrupt acts as a notification only. The DMA engine takes care of transferring data from the host to the Tx buffer when a configured number of bytes are empty in the buffer.

Intel recommends to disable this interrupt while operating in the DMA mode.

Receiver Line Status Interrupt

This interrupt notifies the host that either error has been noticed in the UART reception or a break character is received. This interrupt notification is important for the host in order to receive error free characters.

Upon detection of line status interrupt, further decoding can be done by reading LSR.

Intel recommends to enable this interrupt.

Modem Interrupt

This interrupt notifies the host about modem-related information and updates.

If running with a modem signal, Intel recommends to enable an interrupt.

Receiver Timeout Interrupt

This interrupt only occurs in the FIFO mode.

If operating in the DMA mode, this interrupt acts as a notification only. The DMA engine takes care of transferring the trailing bytes to the host memory upon detection of a timeout.

If operating in the DMA mode, Intel recommends to disable this interrupt.

If operating in the FIFO mode but not in the DMA mode, Intel recommends to enable this interrupt.

Additional Interrupt

This set of interrupts are introduced in addition to the 16550 recommended interrupts from the UART module.

Auto Baud Lock Interrupt

When the auto baud lock feature (ABR[ABE]) and auto baud lock interrupt (ABR[ABLIE]) are enabled, upon getting locked on a receiving character, this interrupt gets generated.

This interrupt gets cleared when reading IIR.

Intel recommends to enable this interrupt when operating with the auto baud lock feature. Also, Intel recommends not to transfer data unless the auto baud lock is achieved in the auto baud lock mode to ensure transfer integrity.

Enabling the auto baud lock interrupt when the auto baud lock feature is not enabled does not generate any interrupt to the host from the auto baud lock source.

18.5 Register Map

Figure 18-9 shows the associated registers from a system software viewpoint.

Figure 18-9. Register Map



18.5.1 PCI Configuration and Capabilities Registers

The UART PCI configuration registers:

- UART 0 = PCI Bus 0; Device 26 (decimal); Function 0
- UART 1 = PCI Bus 0; Device 26 (decimal); Function 1
- UART 2 = PCI Bus 0; Device 26 (decimal); Function 2

Table 18-8. PCI Configuration Registers (HSUART_REGS_PCI)

Offset from Configuration Space of B0:D26:Fn (n=0,1,2) (Decimal)	Register Name	Description
00h	VENDOR_DEVICE_ID	Vendor and Device ID Register
04h	CMD_STAT_REG	Command and Status Register
08h	REV_CLASS_CODE	Revision ID and Class Code Register
09h	CACHE	Header Type Register
10h	IOBA	I/O Base Address Register
14h	MEMBA	Memory Base Address Register
2Ch	SUBSYSTEM_VENDOR_ID	Subsystem Vendor ID Register
34h	CAP_PTR	Capability Pointer Register
3Ch	INTERRUPT	Interrupt Line Register
40h	MSIC	MSI Capability Register
44h	MSIA	MSI Message Address Register
48h	MSID	MSI Message Data Register
50h	PMC	Power Management Capability Register
54h	PMCSR	Power Management Control and Status Register
60h	DSC	Device Specific Control and Status Register
74h	FUNC_RDCFG_HIDE	Function-Hide Register

18.5.2 Memory Mapped Registers, BAR1 (Memory Base Address Register, MEMBA)

The memory map is split between the UART and DMA channel registers.

The UART registers are mapped to the first 128 bytes in the memory map. If the DMA is included in the design, each channel takes the next 64 bytes. The total memory requirement for a single function is shown in Table 18-9.

Table 18-9. UART and DMA Memory Space

Block	Memory Size	Description
UART	128 bytes per function	UART memory space requirement
DMA	128 bytes per function	DMA memory space requirement • 64-bytes for the read channel • 64-bytes for the write channel

18.5.2.1 UART Memory Mapped Registers

The UART is software compatible with 16650 and 16750 UART specifications. The first 8 bytes of the UART Command/Status Registers are a single byte register. These registers are DW wide.

Note: Software must not assume the existence of any Command/Status Registers which are not explicitly documented here.

Table 18-10. UART Memory Mapped Registers

Offset from MEM Base Address MEMBA (FFFFFF00h)	LCR.DLAB	Access	Register Name	Description
00h	0	RO	RBR	Receive Buffer Register
00h	0	WO	THR	Transmit Holding Register
00h	1	RW	DLL	Divisor Latch Low Byte Register
01h	1	RW	DLH	Divisor Latch High Byte Register
01h	0	RW	IER	Interrupt Enable Register
02h	X	RO	IIR	Interrupt Identification Register
02h	X	WO	FCR	FIFO Control Register
03h	X	RW	LCR	Line Control Register
04h	X	RW	MCR	Modem Control Register
05h	X	RO/RC	LSR	Line Status Register
06h	X	RO/RC	MSR	Modem Status Register
07h	X	RW	SPR	Scratch Pad Register
08h	X	RO	UART_FISR	UART Functional Interrupt Status Register
20h	X	RO	RFOR	Receiver FIFO Occupancy Register
24h	X	RW	ABR	Auto-baud Control Register
28h	X	RO	ACR	Auto-baud Count Register
30h	X	RW	PSR	Pre-Scalar Register
34h	X	RW	UCMR	UART Clock Gen Multiplier Register
38h	X	RW	UCDR	UART Clock Gen Divisor Register

18.5.3 DMA Channel Registers

Table 18-11. DMA Channel Memory Mapped Registers

Offset from MEM Base Address MEMBA (FFFFFF00h)	Access	Register Name	Description
80h	RO	CH0SR	Channel Status Register
84h	WO	CH0CR	Channel Control Register
88h	WO	CH0DCR	Channel Descriptor Control Register
90h	WO	CH0BSR	Channel Buffer Size Register
94h	RO	CH0MTSR	Channel Minimum Transfer Size Register
A0h	WO	CH0D0SAR	Channel Descriptor 0 Start Address Register
A4h	WO	CH0D0TSR	Channel Descriptor 0 Transfer Size Register
A8h	WO	CH0D1SAR	Channel Descriptor 1 Start Address Register
ACh	WO	CH0D1TSR	Channel Descriptor 1 Transfer Size Register
B0h	WO	CH0D2SAR	Channel Descriptor 2 Start Address Register
B4h	WO	CH0D2TSR	Channel Descriptor 2 Transfer Size Register
B8h	WO	CH0D3SAR	Channel Descriptor 3 Start Address Register
BCh	WO	CH0D3TSR	Channel Descriptor 3 Transfer Size Register
C0h	RO	CH1SR	Channel Status Register
C4h	WO	CH1CR	Channel Control Register
C8h	WO	CH1DCR	Channel Descriptor Control Register
D0h	WO	CH1BSR	Channel Buffer Size Register
D4h	RO	CH1MTSR	Channel Minimum Transfer Size Register
E0h	WO	CH1D0SAR	Channel Descriptor 0 Start Address Register
E4h	WO	CH1D0TSR	Channel Descriptor 0 Transfer Size Register
E8h	WO	CH1D1SAR	Channel Descriptor 1 Start Address Register
ECh	WO	CH1D1TSR	Channel Descriptor 1 Transfer Size Register
F0h	WO	CH1D2SAR	Channel Descriptor 2 Start Address Register
F4h	WO	CH1D2TSR	Channel Descriptor 2 Transfer Size Register
F8h	WO	CH1D3SAR	Channel Descriptor 3 Start Address Register
FCh	WO	CH1D3TSR	Channel Descriptor 3 Transfer Size Register

18.5.4 I/O Mapped Registers, BAR 0 (I/O Base Address Register, IOBA)

18.5.4.1 UART I/O Mapped Registers

The following UART registers are located in the I/O address space.

Table 18-12. UART I/O Mapped Registers

Offset from I/O Base Address IOBA (FFFFFFF8h)	LCR.DLAB	Access	Register Name	Description
00h	0	RO	RBR_THR_DLL	Receive Buffer Register (RBR)
00h	0	WO	RBR_THR_DLL	Transmit Holding Register (THR)
00h	1	RW	RBR_THR_DLL	Divisor Latch Low Byte Register (DLL)
01h	1	RW	IER_DLH	Divisor Latch High Byte Register (DLH)
01h	0	RW	IER_DLH	Interrupt Enable Register (IER)
02h	X	RO	IIR_FCR	Interrupt Identification Register (IIR)
02h	X	WO	IIR_FCR	FIFO Control Register (FCR)
03h	X	RW	LCR	Line Control Register
04h	X	RW	MCR	Modem Control Register
05h	X	RO	LSR	Line Status Register
06h	X	RO	MSR	Modem Status Register
07h	X	RW	SPR	Scratch Pad Register

§ §

19 Serial Peripheral Interface (SPI)

The SoC implements a Serial Peripheral Interface (SPI) controller as the interface to the SPI Flash image storage. The SPI controller supports a maximum of two SPI NOR Flash devices and supports frequencies of 17 MHz (default), 30 MHz, and 48 MHz. The SPI controller also supports one discrete TPM device.

The SoC SPI NOR Flash controller allows the Flash component(s) to be shared by various masters including BIOS, Intel® ME, LAN Controllers (GbE), and Innovation Engine (IE). The Flash controller is accessed from either the host, IE, or Intel® ME root space. The GbE accesses to Flash (for both the controller and software driver) are via the GbE controller MMIO space.

Related reference material:

- LAN Controller (GbE) related material described in this section can be reference to Chapter 13, "LAN Controllers".
- Intel® ME related material described in this section can be reference to Chapter 36, "System Management".
- For Innovation Engine (IE) related material described in this chapter, see Chapter 37, "Innovation Engine", see Table 1-5, "Reference Documents" on page 127.

Figure 19-1. What is Covered in This Chapter



Table 19-1. References

Reference	Revision	Date	Document Title
SFDP 1.0, JESD216	--	May 2014	*Serial Flash Discoverable Parameters (SFDP), JEDEC Specification JESD216B*

19.1 Signal Descriptions

The signal descriptions are shown in Table 19-2 For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. The Direction column of Table 19-2 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.

Table 19-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
SPI_CLK	O	Yes	**SPI Clock:** The SPI clock signal during idle the bus owner will drive the clock signal low.
SPI_MOSI_IO[0]	I,O	Yes	**SPI Master OUT Slave IN:** Data output pin.
SPI_MISO_IO[1]	I,O	Yes	**SPI Master IN Slave OUT:** Data input pin.
SPI_IO[3:2]	I,O	Yes	**Extended SPI** I/O**:** to 4-bit data.
SPI_CS_N[0]	O	Yes	**SPI Chip Select 0:** Used as the SPI bus request signal for the Flash device.
SPI_CS_N[1]	O	Yes	**SPI Chip Select 1:** Used as the SPI bus request signal for the Flash device.
SPI_TPM_CS_N	O	Yes	**SPI Trusted Platform Module (TPM) Chip Select:** Used as the TPM dedicated request signal. ***Note:*** The "TPM Over SPI or LPC Select" Soft Strap much be set to SPI to use TPM on the SPI interface.
Boot BIOS Strap	I	Yes	See Chapter 4, "Strapping and Configuration."
LPC Select	I	Yes	See Chapter 4, "Strapping and Configuration."
Flash Security Override	I	Yes	See Chapter 4, "Strapping and Configuration."
Top Swap Override	I	Yes	See Chapter 4, "Strapping and Configuration."

19.2 Feature List

- Support for up to two SPI Flash devices
- The maximum size of each Flash device supported is determined by the SFDP-discovered addressing capability of each device.
  - Each component can be up to 16 MB (32 MB total addressable) using 3-byte addressing.
  - Each component can be up to 64 MB (128 MB total addressable) using 4-byte addressing
- Different size SPI Flash devices may be used on each chip select.
- Both SPI Flash devices must be from the same vendor and family.
- Supports five configurable protecting ranges.
- SoC soft-strap information is supported.
- 3.3V SPI I/O buffer VCC.
- Supports the SPI fast read instruction and frequencies 17 MHz (default), 30 MHz, and 48 MHz.
- Support for SPI attached TPM with one TPM chip select (SPI_TPM_CS_N).
- Supports up to quad mode.

19.3 Architectural Overview

Communication on the SPI bus is done with a master–slave protocol. See Figure 19-2 for the master-slave connection of the SPI devices. The Slave Output (SO) data is implemented through a tri-state bus.

The SPI Flash controller allows the Flash component(s) to be shared by various masters including the BIOS, Intel® ME, Innovation Engine (IE), and LAN Controllers. The Flash controller is accessed from either the host or Intel® ME or IE root space.

Figure 19-2. Connection to the SPI Devices



The chip select 0 (the SPI_CS_N[0] pin) Flash device must have a valid descriptor for SoC to boot.

19.3.1 Operation Mode

The SPI controller must operate in the descriptor mode with optional security access restrictions.

19.3.1.1 Descriptor Mode

The descriptor mode is required to enable many features:

- Supports Flash that is divided into regions and accessible by multiple masters.
  a. Regions are allowed to extend across multiple Flash components.
  b. Regions are aligned to 4K blocks/sectors.
- The soft strap region provides the ability to use Flash NVM as an alternative to hardware pull-up/pull-down resistors for the SoC.
- The Flash descriptor contains the Flash upper map.
  a. This is used by software to define Flash vendor specific capabilities.
- The top 256B of the Flash descriptor is reserved for use by the OEM.

19.3.1.2 Security

- Descriptor-based region restriction: Hardware enforced security restricting master accesses to different regions.
  a. Flash descriptor region settings define separate read/write access to each region per master.
  b. Flash security override SoC hard (pin) strap to remove all descriptor-based security (does not affect register-based protected ranges).
  c. Masters can grant other masters read/write access to their region.
- Protected range registers
  a. Five sets of lockable protected range registers that can restrict program register accesses.
  b. Can span multiple regions.
  c. Separate read and write protection.
- SMI write protection for the BIOS
  a. If enabled, will cause an SMI if a program register access occurs when enabled. The primary purpose of this requirement is to support SMI-based BIOS update utilities.
- Illegal instruction protection for instructions such as chip erase.
- Lockable software sequencing opcodes, disabled by default.

19.3.1.3 SPI Flash Access

- Direct read access
- Program register access
  a. Hardware sequencing: Sequencing uses hardware (HW) to provide the basic instructions of read, write, and erase.
  b. Software sequencing: Allows software (SW) to use only a legal opcode.
- Support for the boot BIOS on the SPI.
  a. SoC hard (pin) straps (BBS) determine the BIOS boot location.
- Pre-fetching/caching to improve performance
  a. Separate 64B pre-fetch/cache for the host.

19.3.1.4 Flash Component Requirements

- Serial Flash Discoverable Parameter (SFDP) support.
  Refer to *Serial Flash Discoverable Parameters (SFDP), JEDEC Specification JESD216B*

Notes:
1. SPI controller does not support legacy non-SFDP devices. SFDP support and an SFDP table are required for flash components.
2. SPI controller collects SFDP information for each chip select (CS0 and CS1) and will use the highest supported features for each chip select. CS0 and CS1 do not have to use the same modes.

- Supports two SPI Flash components using two separate chip select pins, SPI_CS_N[0] and SPI_CS_N[1].
- The Flash controller hardware allows selection of either 64k or 4k erase opcodes if the devices advertise these opcodes via SFDP.
- The maximum size of Flash supported is determined by the SFDP-discovered addressing capability of each device. Each component can be up to 16 MB (32 MB total addressable) using 3-byte addressing. Each component can be up to 64 MB (128 MB total addressable) using 4-byte addressing.
- 3.3V SPI I/O buffer VCC
- Supports frequencies 17 MHz (default), 30 MHz, and 48 MHz (48 MHz support requires components that meet 66 MHz timing).
- Supports the SPI fast read instruction.
- Supports the SPI dual output and dual I/O fast read instruction.
- Supports the SPI quad output and quad I/O fast read.
- Uses the standardized Flash instruction set.
- Supports Flash sizes which are not 2^N (where N is an integer), also known as non-power of 2, with the following restrictions:
  a. The Flash regions must be programmed to the actual size of the Flash component(s).
  b. If using two Flash components, the first Flash component (the one with the Flash descriptor) must be of size 2^N. The second Flash component can be a non-power of 2 size. If using only one Flash component, it can be of non-power of 2 size.
  c. The value programmed in the Flash descriptor component density must be set to the next power of 2 value larger than the non-power of 2 size.

Note:

If the SoC is configured to support "Flash dual output and dual I/O fast read" and/or the "quad output and quad I/O fast read" **and** The SPI flash device advertises via *Serial Flash Discoverable Parameters* (SFDP) the "dual output and dual I/O fast read instruction" and/or the "quad output and quad I/O fast read instruction".

Then: In addition to SFDP, the SPI flash device must also **enable** these SFDP advertised dual mode and/or quad mode at the SPI flash device power on. Check with your SPI flash vendor to determine if a specific device supports this requirement.

Else: The SoC will not boot

SoC	Dual (DORE/DIORE)		Quad (QORE/QIORE)	
Flash SFDP	Yes		Yes	
SPI Flash Enabled at power on	No	Yes	No	Yes
Boot	No	Yes	No	Yes

19.3.2 Flash Regions

The Flash is divided into regions. The following regions are assigned the following content.

Table 19-3. Flash Regions

Region	Name
0	**Descriptor**
1	**BIOS**
2	**Intel® ME**
3	Reserved
4	**Platform Data Region**
5	Reserved
6	Reserved
7	Reserved
8	Reserved
9	Reserved
10	**Innovation Engine (IE)**
11	**LAN Controller 0**
12	**LAN Controller 1**
13	Reserved
14	Reserved
15	Reserved

The regions have the following characteristics:

- Region 0, 1 (SPI boot only), and 2 are required to bring up the SoC. Other regions may be optional to include in the Flash, and depends on how the feature is used.
- Region 0 must be located in the first sector of component 0 and SPI_CS_N[0] and all other regions can be organized in any order.
- Region boundaries must be aligned to erasable sector boundaries, with a minimum granularity of 4 KB.
- Regions can extend across multiple components.

Figure 19-3. Flash Regions



Figure 19-4. Organize Flash Region Single Flash vs. Dual-Flash Components



19.3.2.1 Flash Component Boundary

Flash regions are allowed to cross the component boundary, except for the LAN controller region.

19.3.2.2 Flash Descriptor Region 0

The bottom sector of Flash component 0 contains the Flash Descriptor. The maximum size of the Flash Descriptor is 4K, even if the flash device's sector size is larger than 4K. (The hardware is not required to perform any checks to enforce this -- it's simply a descriptor programming error to configure it any other way.).

The information stored in the Flash descriptor is only written during the board-level manufacturing process. Intel requires the read/write permissions be set to read only when the system containing the SoC leaves the manufacturing floor.

The Flash descriptor is made up of the sections indicated in Figure 19-3.

Figure 19-5. Flash Descriptor Sections



- The **Reserved** sections are reserved.
- The **Signature** section selects the descriptor mode and verifies if the Flash is programmed and functioning. This signature is used to identify if the Flash is valid. The Flash signature is located at offset 10h.
- The **Descriptor Map** section defines the logical structure of the Flash in addition to the number of components used.
- The **Component** section has information about the SPI Flash in the system including:
  - Density of each component
  - Illegal instructions (such as chip erase)
  - Frequencies for read, fast read, and write/erase instructions
- The **Region** section points to the four other regions and the size of each region.
- The **Master** region contains the security settings for the Flash, grants read/write permissions for each region, and identifies each master by a requester ID.
- The **Soft Straps** section contains parameter bits that are used to configure the SoC features and/or behaviors.
- 1 KB is used for **Public Key** storage. The key programmed by the OEM.
- The **VSCC Table** section holds the JEDEC ID and the Vendor Specific Component Capabilities (VSCC) information of the entire SPI Flash supported by the NVM image.
- The **Descriptor Upper Map** section determines the length and base address of the **VSCC Table** section.
- The **OEM Section** is 256-bytes reserved at the top of the Flash descriptor for use by an OEM. The information stored by the OEM can only be written during the manufacturing process as the Flash descriptor read/write permissions must be set to read only when the computer leaves the manufacturing floor. The SoC Flash controller does not read this information. Security permissions in the Flash descriptor should be set to provide read access to both the SoC and for the Intel® ME so they read the OEM section and other Flash descriptor runtime as needed.

Note: It is the user's responsibility to allocate sufficient space in each descriptor region to hold the requested amount of data. Hardware does not check for overlaps in the descriptor map.

19.4 Flash Access

The two types of Flash accesses are:

- Direct access
- Program register access

19.4.1 Direct Access

- The SoC cores, Intel® ME, and IE are the only agents that can do direct read access. Access is limited to reading from their primary region.
- The SPI controller does not support direct writes to Flash, no master can do a direct write to the SPI Flash. Write accesses must take place through the Programmed Register interface.
- Direct write is supported to the SPI TPM when it is enabled.

19.4.1.1 BIOS Direct Read in Descriptor Mode

The SPI Flash controller only maps host direct reads to Flash. BIOS can issue Programmed Register accesses independent of the Boot BIOS Strap allowing BIOS to use the SPI Flash as NVM storage concurrently with LPC.

At Boot, BIOS can access the SPI Flash controller by doing a direct read to the 16MB address range just below 4GB, FF00_0000h to FFFF_FFFFh. BIOS can reduce the size of the 16MB of address space by writing to the BIOS Decode Enable (BDE) register. Independent of the settings of the BIOS Decode Enable Offset, the SPI Controller will not claim any direct reads that exceed the size of the active BIOS region. That is, the BIOS Decode Enable can reduce the memory space that is accessible via a direct read, but it cannot be used to address Flash exceeding the size of the active BIOS region.

When the SPI Flash controller sees a read request from the SoC Core to the BIOS Decode region it will claim the transaction. The read request will be a DW aligned address. The SPI Flash controller calculates the Flash Linear Address (FLA) from the BIOS address by subtracting the difference between the BIOS upper range (FFFF_FFFC) and the actual BIOS address, from the Flash Region Limit:

FLA[26:0] <= (Flash_Regionn_Limit[26:12] & "FFCh") - (FFFF_FFFCh - bios_address[31:2] & "00b") where n=1 if primary BIOS is enabled.

If the BIOS access is to the Legacy F segment (F0000h - FFFFFh) or Legacy E segment (E0000h - EFFFFh) which ranges must be aliased to just below 4GB, the SPI controller will calculate the FLA using the following arithmetic[1]:

FLA[26:0] <= (Flash_Regionn_Limit[26:12] & "FFCh") - (FFFF_FFFCh - "FFF" & bios_address[19:2] & "00b") where n=1 if primary BIOS is enabled.

The Flash Linear Address must be converted to a Flash Physical Address by the SPI Flash Controller prior to issuing on the SPI interface.

If the Top Swap (TS) bit is set when booting from SPI Flash, the SPI Controller will invert one of A16, A17, A18, A19 or A20 (note that LPC TS is only A16) depending on the value of the SPI - Boot Block Size soft strap. The inversion only occurs for the top most memory block, i.e. when all bits above the inverted bit are '1'. The inverted address is then used in the equation above to determine the Flash Linear Address. The Top Swap functionality does not apply to accesses generated to the holes below 1MB. The SPI Controller performs the address bit inversion on only the Direct Memory Read access method.

1. Intel is not validating legacy support.

19.4.1.2 Chip Select and Flash Linear Address (FLA)

The controller manages two chip select pins SPI_CS_N[0] and SPI_CS_N[1].

The 27-bit Flash Linear Addresses (FLA[26:0]) either calculated from the direct read address or as programmed in the Flash Linear Address program register must be converted into a 26 bit Flash Physical Address (FPA[25:0]) prior to being issued on the SPI pins according to the following algorithm.

The size of the Flash component is always taken from density field in the SFDP table. FLCOMP.C0DEN is no longer used by the SPI Controller.

If FLA <= Sizeof(Flash Component 0) then

FPA[25:0] = FLA[25:0];

Chip Select = 0

Else

FPA[25:0] = FLA[26:0] - Sizeof(Component 0)

Chip Select = 1

When a 3-byte address is issued the controller sends FPA[23:0] and truncates FPA[25:24].

19.4.2 Programmed Register Access

- Any master attempts to read or write the SPI programmed registers and SoC internal initiator logic check does not match that of the Primary Region master, an Unsupported Request will be returned.
- Program register access uses hardware or software sequencing. Section 19.10, “SPI Support for Trusted Platform Module (TPM)” on page 617.
- For programmed register accesses, the SPI controller implemented hardware security to ensure that the master never issues a read, write, or erase request to any region that it does not have proper access to by comparing the programmed FLA with the base and limit of each of the regions and verifying that master as read or write access to the specified address. Attempted access to addresses which do not fall within any defined region shall cause the access permission check to fail.
- Any attempt to access a region without proper access permissions will prevent the cycle from running and will cause the Flash Cycle Error (HSFSTS_CTL.FCERR) register error bit to be set.

19.5 Flash Security and Protection

The controller provides additional Flash protection mechanisms beyond the access restrictions defined in the Flash descriptor:

- Range write protection
- Intel® ME write protected range
- IE write protected range
- SMI-based global write protection (BIOS writes/erases to the BIOS regions)

The mechanisms are conceptually ORed together such that if any of the mechanisms indicate that the access should be blocked, then it is blocked.

The SoC provides these protections in hardware. It is critical that the hardware must not allow malicious software to modify the address or opcode pointers after determining that a cycle is allowed to run such that the actual cycle that runs on SPI should have been blocked.

If the command associated with an atomic cycle sequence is blocked according to the SoC configuration, the SPI controller must not run any of the sequence.

A blocked command will appear to software to finish, except that the FCERR status bit is set in this case.

Table 19-4. Flash Protection Mechanism Summary

Mechanism	Accesses Blocked[1]	Range Specific	Reset- Override or SMI-Override
BIOS Range Write Protection	Reads/Writes by Host	Yes	Reset Override
Intel® ME Write Protected Range	Writes by any Master	Yes	Reset Override
Intel® ME Protected Range	Reads/Writes by ME	Yes	Reset Override
IE Protected Range	Reads/Writes by IE	Yes	Reset Override
SMI Write Protect	Writes by Host	Applies to both BIOS regions	SMI Override

1. "Writes" implies both writes and erases

19.5.1 Flash Range Write and Read Protection

The SPI controller provides a method for blocking writes and reads to specific ranges in the SPI Flash when the protected ranges are enabled. This is achieved by checking the read or write cycle type and the address of the requested command against the base and limit fields of a read or write protected range. The protected range applies to all master-initiated Flash accesses except the BIOS. Therefore, those register protections do not apply to hardware-initiated descriptor reads. The BIOS protected range registers only apply to BIOS accesses, the IE protected range registers only apply to IE accesses, etc.

The range specified in the Flash Range registers are allowed to span any addresses, independent of whether that master has read or write access to the region(s) in, or partially in, the protected address range.

Note: Once software has locked down the BIOS or Host Protected Range registers, this mechanism remains in place until the next partition reset.

19.5.2 SMI Based Global Write Protection

The SPI controller blocks BIOS writes to the BIOS regions of the SPI Flash when the Write Protect Disable bit is cleared (i.e., protected). For software sequencing, this is achieved by checking the opcode type information (which can be locked down by the initial boot BIOS) of the requested command. Hardware sequencing write protection is triggered when attempting to issue a write or erase command.

The BIOS Write Protect bit does not apply to any other masters that have the write access permission to the BIOS regions. Host CPU accesses to the regions are not protected by the BIOS Write Protect bit. A blocked write may also generate an SMI. See Section 19.10, "SPI Support for Trusted Platform Module (TPM)" on page 617.

19.5.3 Flash Security Override Strap

The Flash descriptor security override strap is an SoC hard (pin) strap. The purpose of the SoC hard (pin) strap is to override all descriptor-based protections, including region definitions and master region permissions. It does not override register-based or software- programmable protections. It is typically used when an OEM wants to re-write a Flash image during manufacturing or board refurbishment. The effects of the override are limited to the following:

- The master region read access and master region write access permissions that were loaded from the Flash descriptor master section will be overridden giving every master read and write permissions to the entire Flash component(s) including areas outside the defined regions.
- The address checks to ensure that a linear address falls within the total size of the Flash components are not performed.
- No RequesterID security checks are performed

Note: The software programmable Protected Range registers, e.g., host PR0-PR4, GPR0, and IE PR0-PR4, are not affected by the Flash descriptor security override strap.

- The region boundaries for direct reads are still enforced.
- The Flash controller determines the size of the Flash devices from SFDP, not the descriptor. Therefore, cycles may be sent to SPI_CS_N[0] or SPI_CS_N[1] independent of the security override strap.

Note: Any access that exceeds the size of the device attached to SPI_CS_N[0] is sent to SPI_CS_N[1], independent of whether a Flash device is connected to SPI_CS_N[1].

- The SoC hard (pin) strap does not change the behavior of the BC.WPD register.

The Flash descriptor security override SoC hard (pin) strap resides in the resume power well. When the strap is enabled, security override will be performed by the Flash controller even though core power well may be down.

19.5.4 Illegal Instructions

Any attempt to execute an illegal instruction will prevent the cycle from running and will cause the FCERR register error bit to be set.

19.5.5 Error Status Table

Table 19-5 summarizes the status bits that are set under different error scenarios. The "cycle in progress" and "scenario" columns refer to the same master, i.e. it's only an error if Master A performs the scenario while Master A has a cycle in progress.

Table 19-5. Programmed Access Error Status

Cycle in Progress	Scenario	HW Seq FCERR	HW Seq DONE	SW Seq FCERR	SW Seq DONE
Hardware Sequence	Writes to HSFSTS_CTL byte_address 6h	1	N/A	N/A	N/A
	Writes to HSFLCTL.07h	1	N/A	N/A	N/A
	Writes to SSFLCTL.A1h (with SCGO =1)	N/A	N/A	1	
	Writes to SSFLCTL.A1h (with SCGO =0)	N/A	N/A	1	0
	Writes to SSFLCTL.A2h	N/A	N/A	1	0
	Writes to SSFLCTL.A3h	N/A	N/A	1	0
	Writes to FADDR or FDATAx	1	N/A	N/A	N/A
Software Sequence	Writes to HSFLCTL.06h (with FGO =1)	1	1	N/A	N/A
	Writes to HSFLCTL.06h (with FGO = 0)	1	0	N/A	N/A
	Writes to HSFLCTL.07h	1	0	N/A	N/A
	Writes to SSFLCTL.A1h	N/A	N/A	1	N/A
	Writes to SSFLCTL.A2h	N/A	N/A	1	N/A
	Writes to SSFLCTL.A3h	N/A	N/A	1	N/A
	Writes to SSFLCTL.A3h	N/A	N/A	1	N/A
	Writes to FADDR or FDATAx	N/A	N/A	1	N/A

19.5.6 Region Checks

Reads and writes are not allowed to cross 4k address boundaries in Flash. This implies they are not allowed to cross devices.

Region definitions must be contiguous, i.e., no unallocated Flash addresses between any two regions. Unallocated Flash addresses between the highest region limit and the end of Flash are allowed. It is a descriptor programming error to define a region that extends beyond the total size of Flash.

19.6 SMI Generation

19.6.1 Synchronous SMI

The SPI controller sends synchronous SMI assert/de-assert message pairs when the Write Protect Disable bit is written from 0 to 1 while the Lock Enable bit is set. Both bits are in the BIOS Control register in host root space PCI header. The SPI controller waits for the smi_ack message before sending the completion for the non-posted write which set the bit. The SPI controller sends the de-assert synchronous SMI message when software clears the SPI_SYNC_SS bit.

19.6.2 Asynchronous SMI

The SPI controller sends asynchronous SMI assert/de-assert message pairs when configured to generate an SMI for the hardware and software sequencing Flash cycle done. The SMI for Flash cycle done is enabled via HSFSTS_CTL.FSMIE for hardware sequencing and SSFSTS_CTL.SME for software sequencing. The BIOS Control(BC).SE_BWP bit does not control SMI for Flash cycle done. If the SMI is enabled, assert SMI is sent when the Flash cycle done transitions from 0 to 1. If the SMI is enabled, de-assert SMI is sent when the Flash cycle done transitions from 1 to 0 or when the SMI enable becomes false.

BIOS writes/erases may be blocked. When ASE_BWP = 1, such a blocked write or erase attempt by the host to the BIOS region(s) will cause an asynchronous SMI even if the transaction would also be blocked due to multiple causes. De-assert SMI is sent when the Flash cycle done transitions from 1 to 0 or when ASE_BWP becomes false.

19.7 Hardware vs. Software Sequencing

Hardware and software sequencing are the two methods used to communicate with the Flash via the programming registers.

Hardware sequencing is the safer method for communication with the flash. Since the SPI controller uses SFDP to determine the capabilities of each attached SPI flash, hardware sequencing will only use those supported capabilities. Software sequencing on the other hand might use capabilities that the SPI flash doesn’t support causing unpredictable result. Software sequencing is by default disabled in the SoC. To enable it please use SS9 bit [13] SPI - Host Software Sequencing Enable.

19.7.1 Hardware Sequencing

Hardware sequencing has a predefined list of opcodes with only the erase opcode being programmable. This mode is only available if the descriptor is present and valid.

Table 19-6 contains a list of commands and the associated opcodes that an SPI-based serial Flash device must support to be compatible with hardware sequencing.

Table 19-6. Hardware Sequencing Opcodes

Instruction Op-Code	Description
03h	Read data
05h	Read status
0Bh	Fast read
06h	Write enable
04h	Reserved
02h	Write data/program data
50h	Enable the Write Status register.
01h	Write Status register
3Bh/Discoverable	Dual output fast read Discoverable opcodes are obtained from each component SFDP table.
Discoverable	Dual I/O fast read
Discoverable	Quad output fast read
Discoverable	Quad I/O fast read
Discoverable	4k erase. Uses the value from SFDP (if available) or else the value from the VSSC.EO register. Industry standard is 20h.
Discoverable	64k erase. Industry standard is D8h.
Discoverable	RPMC Op1. Not supported via hardware sequencing in SPT. Industry standard is 9Bh.
Discoverable	RPMC Op2. Uses fast read timing with 8 wait states. Not supported via hardware sequencing in SPT. Industry standard is 96h.
5Ah	Read SFDP. Uses fast read timing with 8 wait states.
9Fh	Read JEDEC ID.
B7h	Enable 32-bit addressing mode.

If there is a Hardware Sequencing Cycle In Progress and an attempt is made to program any of the control, address, or data register the cycle is blocked and the FCERR bit is set.

If hardware sequencing allows selection of the Write Status opcode, then the Flash controller will insert a Write Enable (06h) opcode prior to issuing the Write Status. The two operations will be issued as an atomic sequence.

19.7.2 Software Sequencing

Any required command not supported by Hardware Sequencing must be programmed by the software in the Software Sequencing Control, Flash Address, Flash Data, and Opcode Configuration registers. The software must issue either a read ID or read JEDEC ID, or a combination of the two to determine what Flash component is attached. Based on the read ID, the software determines the appropriate opcode instruction sets to set in the program registers and at what SPI frequency to run the command.

The software must program the Flash linear address for all commands, even for those commands that do not require an address such as the read ID or read status. This is because the SPI controller uses the address to determine which chip select to use.

The opcode type and data byte count fields determine how many clocks to run before deasserting the chip enable. The Flash data is always shifted in for the number of bytes specified, and the Flash data out is always shifted out for the number of data bytes specified.

A status bit indicates when the cycle has completed on the SPI port allowing the host to know when read results are checked and/or when to initiate a new command.

The controller also provides the atomic cycle sequence for performing erases and writes to the SPI Flash. When this bit is 1 (and the Go bit is written to 1), a sequence of cycles is performed on the SPI interface without allowing other SPI devices to arbitrate and interleave cycles to the Flash device. In this case, the specified cycle is preceded by the Prefix command (8-bit programmable opcode) and followed by repeated reads to the Status register (opcode 05h) until bit 0 indicates the cycle has completed. The hardware does not attempt to check that the programmed cycle is a write or erase.

If a programmed access is initiated (Cycle Go written to 1) while the SPI controller is already busy with a direct memory read, then the SPI host hardware holds the new programmed access pending until the preceding SPI access completes.

Once the SPI controller has committed to running a programmed access, subsequent writes to the programmed cycle registers that occur before it has completed do not modify the original transaction and result in the assertion of the FCERR bit. The software never purposely behaves in this way and relies on this behavior. However, the FCERR bit provides basic error reporting in this situation. Writes to the following registers cause the FCERR bit assertion in this situation:

- Software Sequencing Control register
- Software Sequencing Address register
- SPI Data register

With the exception of illegal opcodes, the SPI controller does not police which opcodes are valid to be used in software sequencing. For example, if the software programs a dual-output-fast-read opcode, then the dual-output-fast-read cycle is issued, independent of whether the Dual-output Fast Read Enable bit was set in the component descriptor section. However, disabled opcodes for dual and quad reads will be run on the SPI pins as single-input, single-output commands, and will therefore return incorrect data to the requester and cause bus contention when the Flash device drives multiple pins of the SPI bus. Similarly, SPI controller does not use the device capabilities discovered via SFDP to alter any command programmed by software.

SW sequencing registers: HSFSTS_CTL, SSFSTS_CTL, PREOP_OPTYPE, OPMENU, FADDR, and FDATA. See Table 19-9, "BIOS Flash Program Register Address Map" on page 624.

- HSFSTS has the FLOCKDN bit which locks (prevents writing) most SW Sequencing opcode registers. Trusted firmware (BIOS or ME code) configures these registers, then sets FLOCKDN prior to handing control to operating system software.
- SSFSTS indicates when a transaction has completed and provides error status for the transaction. Software must write-to-clear the FCERR and Cycle Done Status bits prior to starting a transaction. Software polls this register, waiting for Cycle Done Status, before accessing read data or setting up a new transaction.
- SSFCTL contains all configuration data for a transaction, e.g., number of data bytes, which opcode(s), whether an atomic sequence of opcodes, and SPI_CLK frequency. Software sets the register SPI Cycle Go bit to initiate a transaction.
- PREOP is programmed with two Write Enable opcodes used by Flash devices. The selected PREOP opcode is sent to Flash prior to the selected OPMENU opcode when the atomic cycle sequence flag is set in the SSFCTL register. Flash devices require the Write Enable opcode be sent prior to Write and Erase instructions. Some devices also require Write Enable prior to a Write Status Register opcode. OPTYPE identifies whether each opcode in OPMENU is a read or a write cycle and whether an address must be sent following the opcode. For example, a Read Status opcode is a read instruction with no address, a Read SFDP opcode is a read instruction with an address, and a Write Status Register opcode is a write instruction with no address. Software must ensure that OPTYPE is programmed correctly for each opcode in OPMENU - hardware cannot detect or correct mismatches.
- OPMENU is programmed with the opcodes that are available for SW sequencing operations. Opcodes typically set in this register include Read SFDP (5Ah), Read JEDEC ID (9Fh), and Write Status Register (01h). Programming "read flash array" type instructions (e.g. Fast Read, Read Dual I/O, Read Quad I/O) is typically not required because the Flash controller will automatically select the most efficient read opcode when either HW Sequencing or direct reads are used.
- FADDR is programmed with the Flash Linear Address for the SW sequenced operation. FADDR must be programmed for every SW sequenced transaction because the Flash controller uses the address to determine which chip select to activate when running the transaction on the SPI bus.
- FDATA is programmed with data to be written to Flash. The Flash controller stores data read from Flash in FDATA.

Example: Read 16 bytes of SFDP from component 1 using SW sequencing

- Verify that HSFSTS.FLOCKDN=0, i.e. the SW sequencing registers are unlocked
- Write to SSFSTS to clear FCERR and Cycle Done Status
- Program OPTYPE 0 to "address required; read cycle type"
- Program OPMENU 0 to 5Ah
- PREOP is not required prior to Read SFDP; no need to touch this register
- Program FADDR to component 1, address offset zero. The size of the Flash component is always taken from density field in the SFDP table. FLCOMP.C0DEN is no longer used by the SPI Controller.
- Program SSFCTL to select opcode and start transaction. SSFCTL fields: SCF=100b, SME=0, DS=1, DBC=0xF, COP=0, SPOP=don't care, ACS=0, SCGO=1
- Poll SSFSTS, waiting for SCIP=0 to show completed SW Sequenced transaction
- Check error status in SSFSTS.FCERR
- Read 16 bytes from FDATA[3:0]

19.8 Serial Flash Device Compatibility Requirements

A variety of serial Flash devices exist in the market. For a serial Flash device to be compatible with the SPI bus, it must meet the minimum requirements.

19.8.1 BIOS SPI Flash Requirements

The SPI Flash device must meet the following minimum requirements when used explicitly for the system BIOS storage. Refer to Section 19.3.1.4, "Flash Component Requirements" on page 597.

- The erase size has at least one of the following: 64 Kbytes, or 4 Kbytes.
- The device must support multiple writes to a page without requiring a preceding erase cycle (refer to Section 19.5.1, "Flash Range Write and Read Protection" on page 605).
- The Serial Flash device must ignore the upper address bits such that an address of FF_FFFFh aliases to the top of the Flash memory for 3-byte addressing support.
- SPI compatible mode 0 support (the clock phase is 0 and data is latched on the rising edge of the clock).
- If the device receives a command that is not supported or incomplete (less than 8 bits), the device must complete the cycle gracefully without any impact on the Flash content.
- An Erase command (page, sector, block, chip, etc.) must set all bits inside the designated area (page, sector, block, chip, etc.) to 1 (Fh).
- Status register bit 0 must be set to 1 when a write, erase, or write to a status register is in progress and cleared to 0 when a write or erase is NOT in progress.
- Devices requiring the Write Enable command must automatically clear the write enable latch at the end of data program instructions.
- Byte write must be supported. The flexibility to perform a write between 1 byte to 64 bytes is recommended.

19.9 SPI Flash Interface

Communication on the SPI bus is done with a Master - Slave protocol. Typical bus topologies call for a single SPI Master with a single SPI Slave. The basic SPI interface consists of a four wire interface: clock (CLK), master data out (Master Out Slave In (MOSI)), master data in (Master In Slave Out (MISO)) and active low chip selects (CS0#).

The SoC SPI Flash controller supports 3 chip selects, SPI_CS_N[0], SPI_CS_N[1], and SPI_TPM_CS_N. The SPI_TPM_CS_N is dedicated to support TPM on SPI. The Flash controller supports up to 4 I/O pins, i.e. SPI_MOSI_IO[0], SPI_MISO_IO[1], SPI_IO[2] and SPI_IO[3] to comprehend the support for the Dual I/O and Quad I/O operation. The Flash controller does not support use of two or four wires for the opcode phase of a Flash transaction, e.g. 2-2-2 or 4-4-4 mode reads.

19.9.1 Single-Input, Dual-Output Fast Read

The SPI controller supports the functionality of a single-input, dual-output fast read: opcode 3Bh. This instruction has the same timing (including a dummy byte) and the same frequencies as the fast read instruction, with the difference that the read data from the Flash is presented on both the MISO and MOSI pins. During a dual-read instruction, the odd data bits are on the MISO pin and the even data bits are on the MOSI pin.

Note: When the dual-output-fast-read support is enabled the fast-read support must be enabled as well.

Note: The Micronix* SPI Flash uses a different opcode for dual-fast read and requires during the address phase the address bits are sent on both MOSI and MISO. The SoC does not support this implementation of the protocol.

Note: When in the 32-bit addressing mode, the address bits in the waveform in Figure 19-6 will be extended to 32 bits (i.e., 4 bytes) instead of 24 bits.

Figure 19-6. Dual-Output-Fast-Read Timing



19.9.2 Dual-I/O Fast Read

Besides having the read data be presented on both the MOSI and MISO pins, dual-I/O fast read allows the address bits to be sent on both MOSI and MISO as well. Odd address bits are on the MISO pin and the even address bits are on the MOSI pin. The dummy byte is also on both the MOSI and MISO pins.

Note: When in the 32-bit addressing mode, the address bits in the waveform in Figure 19-7 will be extended to 32 bits (i.e. 4 bytes) instead of 24 bits.

Figure 19-7. Dual-I/O-Fast-Read Timing



19.9.3 Quad-Output Fast Read

Quad-output fast read allows the read data from the Flash be presented on the MOSI, MISO, SPI_IO2, and SPI_IO3 pins, at the rate of 4 data bits per clock.

Note: When in the 32-bit addressing mode, the address bits in the waveform in Figure 19-8 will be extended to 32 bits (i.e. 4 bytes) instead of 24 bits.

Figure 19-8. Quad Output Fast Read Timing



19.9.4 Quad-I/O Fast Read

Quad-I/O fast read allows the address, the dummy byte and the read data be presented on the MOSI, MISO, SPI_IO2 and SPI_IO3 pins, thus achieving 4 bits per clock during both the address and data phases.

When in the 32-bit addressing mode, the address bits in the waveform in Figure 19-9 will be extended to 32 bits (i.e. 4 bytes) instead of 24 bits.

Figure 19-9. Quad-I/O-Fast-Read Timing



19.9.5 JEDEC ID

Since each serial Flash device may have unique capabilities and commands, the JEDEC ID is the necessary mechanism for identifying the device so the uniqueness of the device is comprehended by the controller (master). The JEDEC ID uses the opcode 9Fh and a specified implementation and usage model. This JEDEC standard manufacturer and device ID read method is defined in Standard JESD21-C, PRN03-NV.

Note: Once software has locked down the BIOS or Host Protected Range registers, this mechanism remains in place until the next partition reset.

19.10 SPI Support for Trusted Platform Module (TPM)

The SoC supports one discrete TPM device with SPI_TPM_CS_N. The SPI controller decodes the TPM read/write directly. There is no register programming model for the TPM.

The requirements for the support are:

- The platform must have no more than 1 TPM. Therefore, the SoC must route all TPM transactions either to LPC or SPI depending on the configuration bits. Some platforms may be without TPM.
- A chip select for the SPI TPM (SPI_TPM_CS_N)
  - When the soft strap sets the TPM on SPI, the TPM chip select must only assert on the decode of TPM transactions.
  - TPM chip select cannot assert based on any programmed registers or other SW mechanism.
- The SPI controller supports accesses to the SPI TPM at whatever frequency the SPI bus has been configured.
- The TPM requires the support for the interrupt routing. However, the TPM interrupt pin is routed to the SoC. Thus, the TPM interrupt is completely independent from the SPI controller.
- The SPI controller is configurable to prevent TPM access when the descriptor is invalid (or no Flash is attached). This is a security requirement for the SoC. When configured to prevent TPM access when the descriptor is invalid, the Flash controller behaves as if the TPM on the SPI does not exist on the system.

19.10.1 TPM Protocol on SPI

Though the SPI controller supports 26-bit addressing on SPI, only 24-address bits are sent to the TPM. The FEh byte is dropped. For example, an incoming address of FED4_4024h would be sent on the SPI as D4_4024h.

Access to the SPI TPM is always with single-address input and single output at the single data rate. Dual-output, dual-I/O, quad-output and quad-I/O operations are not supported on SPI_TPM_CS_N with the TPM.

The following rules apply for the data transfer:

- Data is shifted Most Significant Bit (MSB) first, Least Significant Byte (LSB) first.
- The address and command are shifted MSB first for the entire field.
  - The 24-bit address shifts A23 first, then A22, A21..., A0.
- Master and slave both drive data on the falling edge of the clock.
- The TPM accesses always get a 24-bit address that is the offset from FE00_0000h.
  - Asserting the SPI_TPM_CS_N is an indication that the SoC did a full decode and the cycle is in the FED4_xxxxh range.
- Only SPI mode 0 is supported (CPHA = 0, CPOL = 0).

It is legal to transmit any number of bytes from 1 to 64. Zero length reads or writes are not allowed. If the transfer is less than 4B, then the corresponding bits would be left out. For instance, on a 2B write the last transfer on MOSI would be Data[8] (LSB of MSB).

There is no status byte for the transfer. If the write to the TPM failed, the TPM would not honor what was received, and SW/driver will understand the SW command did not succeed and perform the appropriate recovery mechanisms. If the read fails, then the SoC would return all FFs for the data, which would signal a failure to the driver.

Table 19-7. Address and Data Transfer for TPM

Bit Transfer Order on MISO/MOSI	BYTE on MISO/MOSI	Usage	Notes
	67 for 64B transaction 11 for 8B transaction	Reserved	
57-63 – last bits on wire	7	Data[30:24]	
56		Data[31]	MSB of fourth LSB
49-55	6	Data[22:16]	
48		Data[23]	MSB of third LSB
41-47	5	Data[14:8]	
40		Data[15]	MSB of second LSB
33-39	4	Data[6:0]	
32		Data[7]	MSB of LSB
Optional flow control can be done in this window. This is the only place in the bit transfer where flow control can be done.			
31	3	Addr[0]	LSB of address
9-30	1-3	Addr[22] down to Addr[1]	
8	1	Addr[23]	MSB of address
2-7	0	Bits [5:0] Size of transfer where bit [5] of this field is the third bit transferred on the wire, and bit [0] is the eighth bit on the wire. This field is a 0s-based count of the bytes. Any byte count from 1 to 64 is legal.	Bit [5:0] decode 11_1111 = 64 bytes (For 63 down to 6 bytes) 00_0100 = 5 bytes 00_0011 = 4 bytes 00_0010 = 3 bytes 00_0001 = 2 bytes 00_0000 = 1 byte
1		bit [6]. Reserved	
0-first bit on wire		Byte0, bit [7]. Read/Write	1 = read 0 = write

19.10.2 TPM Flow Control on SPI

Note: This description uses idealized, zero-delay timing for illustrative purposes.

For the TPM operation, it involves HW generating transactions directly to the TPM with minimum or no SW involvement. As such, there needs to be a simple flow control mechanism on SPI since HW can't poll busy bits or use other SW mechanisms. Therefore the following flow control is allowed by the TPM.

SPI protocol doesn't have a defined flow control mechanism. Thus a new flow control mechanism is being created for the TPM on SPI.

The flow control is on a transaction basis and not on a byte basis. For example, a read or write to the data register can be at most 4B in length today, moving to 8B or 64B in the future. The TPM will accept the write data when it has the full size of buffer available to be written (1-64B), or provide the read data when it has the full amount of data (1-64B) ready to deliver, again based on the size of the transaction. The overhead of allowing flow control between each byte is too high with almost no benefit.

Since the specification allows for larger sizes of transactions in the future, the SoC will have limited, if any, HW checking on accesses to the TPM address space. If the SoC receives transaction for any size from 1B to 64B that doesn't cross a 64B boundary, it must issue that transaction on SPI as received. The SoC must accept all transactions of any length on any address boundary to FED4_0000h to FED4_4FFFh, as long as they don't cross a 64B boundary.

The TPM transaction on SPI consists of 1B of command, 3B of address, followed by write data from the SoC or read data from the TPM. The TPM may insert wait states after the 4B of command and address have been received.

The mechanism to insert wait states is as follows. For a read to the TPM, the command and address are driven on MOSI and the TPM responds with data on MISO. With no wait states, the TPM would drive data on the next falling clock edge after the falling clock edge that the SoC drove the last address bit. The flow control mechanism added for the TPM is that the SoC will monitor the MISO pin in the same clock window that A[0] (the last address bit) is valid.

The TPM receives the address, where address bit[2] is captured a clock and a half before it has to drive the flow control bit. For reads, the registers are on a 4B (or 8B) boundary, so that bit[2] of the address should be sufficient to determine if the register is available or not to be read. Then bit[1] and [0] are only used to steer the correct bytes to the bus, but shouldn't be needed to determine flow control.

Note: Having byte-based flow control allows the transaction layer to handle the retransmit of the data. This allows for faster clock speeds. It also keeps all transfers on a byte basis and not having a few bits in between. It provides plenty of time for the TPM to decode the address and determine if it is ready to receive the data or not. This allows faster SPI clocking to speed up the transfers.

There is no further flow control allowed. Once the data starts coming from the TPM, it must provide the entire transactions worth of data, which can be from 1 to 64 bytes. In this example, if the SoC had latched a '1' on the 5th rising clock, then it would start latching in data starting on the 6th rising edge, which is the normal behavior without wait states. The TPM may insert any number of wait states that it needs.

If the TPM intends to drive wait states, it should drive MISO low when it detects CS# asserted. Once the TPM determines the address and whether it can accept or return the data, it drives MISO high for one clock in the wait state window.

Note: The wait state is defined as '0' on MISO, so that if there is no TPM present at all, then the design has a weak pull-up on MISO. Having a pull-up means that the SPI controller sees a '1', which indicates no wait states, and will latch in FFh on the read. This follows standard master abort behavior of FFh for read data and matches the behavior when the TPM was on LPC.

For writes, the mechanism is similar. The SoC will latch the value of MISO on the 5th rising edge. This is the same edge that the last address bit is latched by the slave. In other words, the slave drives MISO to '0' in the same clock that the master drives the last bit of the address. The master samples MISO every 8 clocks after that and will only continue when it samples a '1' during this bit position. If MISO is '0' to request a wait state, then the data during that byte is not valid and the TPM must drop the data. If there is a wait state, the master will drive invalid data over and over until the slave stops requesting wait states. The SoC will sample MISO on the last data bit of the byte (multiples of 8 clocks after the first wait state window). Again, the TPM must hold MISO as '0' for 8 clocks each time it requests a wait state. If MISO is '1', this indicates the TPM is ready for the entire write, and the SoC will drive the 1st and subsequent data bytes on the following clocks. If MISO is still '0', the SoC will continue sending invalid data until it receives a '1' on MISO in the wait state window. Note that the flow control only applies to the first byte and not between each byte. Once the data starts transmitting, the entire write data will be sent with no further flow control. An example for a 2B write that has 2 wait states would be, drive command and address for 4 bytes, then invalid data byte, invalid data byte, valid data byte 0, valid data byte 1.

19.11 Register Map

The SPI controller is a standalone PCI device in the host root space at bus 0, device 31 (decimal), and function 5. The registers listed in Figure 19-10 are described in detail.

Figure 19-10.Register Map



19.11.1 PCI Configuration and Capabilities

The SPI controller also has fixed mappings, independent of the PCI configuration header, in the ranges:

- 4G - 16M to 4G -- direct reads to the BIOS regions. This depends on the boot interface. These could go to LPC.
- Legacy E -- Reads and Writes to E segment are to DRAM only not the BIOS regions
- Legacy F -- Reads and Writes to F segment are to DRAM only not the BIOS regions
- 0xFED4_xxxx -- TPM direct reads and writes if the TPM over the SPI is enabled.
- The registers marked no in the SPI supported column behave as Read Only (RO) and return zero.

Table 19-8. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D31:F5 (decimal)	Register Short Name	Description	SPI Supported
0x0	BIOS_SPI_DID_VID	Device ID and Vendor ID	Yes
0x4	BIOS_SPI_STS_CMD	Status and Command	Yes
0x8	BIOS_SPI_CC_RID	Revision ID	Yes
0xC	BIOS_SPI_BIST_HTYPE_LT_CLS	BIST, Header Type, Latency Timer, Cache Line Size	No
0x10	BIOS_SPI_BAR0	SPI BAR0 MMIO	Yes
0x28	BIOS_SPI_CCP	Cardbus CIS Pointer	No
0x2C	BIOS_SPI_SID_SVID	Subsystem and Vendor ID	No
0x30	BIOS_SPI_XRBAR	Expansion ROM Base Address	No
0x34	BIOS_SPI_CAPP	Capabilities List Pointer	No
0xD0	BIOS_SPI_UR_STS_CTL	SPI Unsupported Request Status	Yes
0xD8	BIOS_SPI_BDE	BIOS Decode Enable	Yes
0xDC	BIOS_SPI_BC	BIOS Control	Yes

19.11.2 Memory Mapped Registers

These registers are mapped in the host root space. The address offsets are relative to BIOS_SPI_BAR0. Reads to unimplemented addresses return 0s.

Table 19-9. BIOS Flash Program Register Address Map (Sheet 1 of 2)

Base Address	MEM Address	Instance Name	Name
BIOS_SPI_BAR0	0x0	BIOS_BFPREG	SPI BIOS MMIO PRI
BIOS_SPI_BAR0	0x4	BIOS_HSFSTS_CTL	Hardware Sequencing Flash Status and Control
BIOS_SPI_BAR0	0x8	BIOS_FADDR	Flash Address
BIOS_SPI_BAR0	0xC	BIOS_DLOCK	Discrete Lock Bits
BIOS_SPI_BAR0	0x10	BIOS_FDATA0	Flash Data 0
BIOS_SPI_BAR0	0x14	BIOS_FDATA1	Flash Data 1
BIOS_SPI_BAR0	0x18	BIOS_FDATA2	Flash Data 2
BIOS_SPI_BAR0	0x1C	BIOS_FDATA3	Flash Data 3
BIOS_SPI_BAR0	0x20	BIOS_FDATA4	Flash Data 4
BIOS_SPI_BAR0	0x24	BIOS_FDATA5	Flash Data 5
BIOS_SPI_BAR0	0x28	BIOS_FDATA6	Flash Data 6
BIOS_SPI_BAR0	0x2C	BIOS_FDATA7	Flash Data 7
BIOS_SPI_BAR0	0x30	BIOS_FDATA8	Flash Data 8
BIOS_SPI_BAR0	0x34	BIOS_FDATA9	Flash Data 9
BIOS_SPI_BAR0	0x38	BIOS_FDATA10	Flash Data 10
BIOS_SPI_BAR0	0x3C	BIOS_FDATA11	Flash Data 11
BIOS_SPI_BAR0	0x40	BIOS_FDATA12	Flash Data 12
BIOS_SPI_BAR0	0x44	BIOS_FDATA13	Flash Data 13
BIOS_SPI_BAR0	0x48	BIOS_FDATA14	Flash Data 14
BIOS_SPI_BAR0	0x4C	BIOS_FDATA15	Flash Data 15
BIOS_SPI_BAR0	0x50	BIOS_FRACC	Flash Region Access Permissions
BIOS_SPI_BAR0	0x54	BIOS_FREG0	Flash Region 0
BIOS_SPI_BAR0	0x58	BIOS_FREG1	Flash Region 1
BIOS_SPI_BAR0	0x5C	BIOS_FREG2	Flash Region 2
BIOS_SPI_BAR0	0x60	BIOS_FREG3	Flash Region 3
BIOS_SPI_BAR0	0x64	BIOS_FREG4	Flash Region 4
BIOS_SPI_BAR0	0x68	BIOS_FREG5	Flash Region 5
BIOS_SPI_BAR0	0x6C	BIOS_FREG6	Flash Region 6
BIOS_SPI_BAR0	0x70	BIOS_FREG7	Flash Region 7
BIOS_SPI_BAR0	0x74	BIOS_FREG8	Flash Region 8
BIOS_SPI_BAR0	0x78	BIOS_FREG9	Flash Region 9
BIOS_SPI_BAR0	0x7C	BIOS_FREG10	Flash Region 10
BIOS_SPI_BAR0	0x80	BIOS_FREG11	Flash Region 11
BIOS_SPI_BAR0	0x84	BIOS_FPR0	Flash Protected Range 0
BIOS_SPI_BAR0	0x88	BIOS_FPR1	Flash Protected Range 1
BIOS_SPI_BAR0	0x8C	BIOS_FPR2	Flash Protected Range 2

Table 19-9. BIOS Flash Program Register Address Map (Sheet 2 of 2)

Base Address	MEM Address	Instance Name	Name
BIOS_SPI_BAR0	0x90	BIOS_FPR3	Flash Protected Range 3
BIOS_SPI_BAR0	0x94	BIOS_FPR4	Flash Protected Range 4
BIOS_SPI_BAR0	0x98	BIOS_GPR0	Global Protected Range 0
BIOS_SPI_BAR0	0xA0	BIOS_SSFSTS_CTL	Software Sequencing Flash Status and Control
BIOS_SPI_BAR0	0xA4	BIOS_PREOP_OPTYPE	Prefix Opcode and Opcode Type Configuration
BIOS_SPI_BAR0	0xA8	BIOS_OPMENU0	Opcode Menu0 Configuration
BIOS_SPI_BAR0	0xAC	BIOS_OPMENU1	Opcode Menu1 Configuration
BIOS_SPI_BAR0	0xB4	BIOS_FDOC	Flash Descriptor Observability Control
BIOS_SPI_BAR0	0xB8	BIOS_FDOD	Flash Descriptor Observability Data
BIOS_SPI_BAR0	0xC0	BIOS_AFC	Additional Flash Control
BIOS_SPI_BAR0	0xC4	BIOS_SFDP0_VSCC0	Vendor Specific Component Capabilities for Component 0
BIOS_SPI_BAR0	0xC8	BIOS_SFDP1_VSCC1	Vendor Specific Component Capabilities for Component 1
BIOS_SPI_BAR0	0xCC	BIOS_PTINX	Parameter Table Index
BIOS_SPI_BAR0	0xD0	BIOS_PTDATA	Parameter Table Data
BIOS_SPI_BAR0	0xD4	BIOS_SBRS	SPI Bus Requester Status
BIOS_SPI_BAR0	0xE0	BIOS_FREG12	Flash Region 12
BIOS_SPI_BAR0	0xE4	BIOS_FREG13	Flash Region 13
BIOS_SPI_BAR0	0xE8	BIOS_FREG14	Flash Region 14
BIOS_SPI_BAR0	0xEC	BIOS_FREG15	Flash Region 15
BIOS_SPI_BAR0	0x108	BIOS_RPMC0_D0	RPMC SFDP Table. Mapping the registers into MMIO space allows the option of BIOS discovering RPMC in systems. No RPMC registers are used by SPI controller.
BIOS_SPI_BAR0	0x10C	BIOS_RPMC1_D0	RPMC SFDP Table. Mapping the registers into MMIO space allows the option of BIOS discovering RPMC in systems. No RPMC registers are used by SPI controller.
BIOS_SPI_BAR0	0x110	BIOS_RPMC0_D1	RPMC SFDP Table. Mapping the registers into MMIO space allows the option of BIOS discovering RPMC in systems. No RPMC registers are used by SPI controller.
BIOS_SPI_BAR0	0x114	BIOS_RPMC1_D1	RPMC SFDP Table. Mapping the registers into MMIO space allows the option of BIOS discovering RPMC in systems. No RPMC registers are used by SPI controller.
BIOS_SPI_BAR0	0x118	BIOS_BM_RAP	BIOS Master Read Access Permissions
BIOS_SPI_BAR0	0x11C	BIOS_BM_WAP	BIOS Master Write Access Permissions
BIOS_SPI_BAR0	0x1B0	BIOS_IE_PR0	IE Flash Protected Range 0
BIOS_SPI_BAR0	0x1B4	BIOS_IE_PR1	IE Flash Protected Range 1
BIOS_SPI_BAR0	0x1B8	BIOS_IE_PR2	IE Flash Protected Range 2
BIOS_SPI_BAR0	0x1BC	BIOS_IE_PR3	IE Flash Protected Range 3
BIOS_SPI_BAR0	0x1C0	BIOS_IE_PR4	IE Flash Protected Range 4

§ §

20 Low Pin Count (LPC) Controller

The LPC serves as a PCI-to-Industry Standard Architecture (ISA) bridge to devices connected to the LPC interface pins. The bridge is discovered by the software at bus 0, device 31 (decimal), function 0 in the configuration address space. This bridge also accommodates a number of integrated legacy peripherals, most of which were originally designed for the ISA.

Note: 3.3V must be supplied to VCC_LPC_ESPI_3P3_1P8.

Figure 20-1. What is Covered in This Chapter



Table 20-1. References

Reference	Revision	Date	Document Title
LPC Specification	1.1	August 2002	*Intel® Low Pin Count (LPC) Interface Specification*
PCI Specification	3.0	February 2004	*PCI Local Bus Specification, Revision 3.0*

20.1 Signal Descriptions

The signal descriptions are shown in Table 20-2. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. The Direction/Type column of Table 20-2 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-Tri = Tri-state Output. SoC output circuit uses a three-state driver.

Table 20-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
LPC_AD[3:0]	I,O-Tri	Yes	Multiplexed command, address, and data
LPC_FRAME_N	O	Yes	**Frame:** Indicates start of a new cycle and termination of a broken cycle. The SoC provides an internal 20-kΩ Pull-Up (PU) resistor on this signal pin.
LPC_CLKOUT[1:0]	O	Yes	**Clock:** Same 24-MHz clock for LPC bus interface. The SoC provides an internal 20-kΩ Pull-Down (PD) resistor on each of these signal pins.
LPC_CLKRUN_N	I,O-Tri	Yes	**Clock Run:** As an input, this active-low signal is generated by LPC peripherals that need the LPC_CLKOUT for a period of time beyond the four clocks guaranteed at the end of a transfer cycle. The SoC, as the central resource that generates the LPC_CLKOUT, monitors the LPC_CLKRUN_N signal to regulate its frequency for low-power operation. As an output, the SoC provides a sustained tri-state signal. When the SoC drives the LPC_CLKRUN_N signal low (asserted), it indicates the LPC_CLKOUT is operating at its normal frequency. When driven high (de-asserted), the SoC indicates a stopped or very-slow clock frequency. The platform board must provide a Pull-Up (PU) resistor to sustain a logic-high voltage when the SoC and attached LPC peripherals float this tri-state bus.
LPC_SERIRQ	I,O-Tri	Yes	**Serialized IRQ:** SERIRQ is an active-low sustained tri-state bus, synchronized with the LPC_CLKOUT signal. As the Serialized Interrupt Host Controller, the SoC drives this pin low for a periods of time, high for a periods of time, and other times floats this pin. The external agents attached to this pin provide the interrupt IRQ and I/O Check indications through low and high signaling, and float this line when they do not own the bus cycle. Electrically, LPC_SERIRQ conforms with the sustained tri-state parameters defined in the PCI Local Bus Specification, Revision 3.0. The platform board must provide a Pull-Up (PU) resistor to sustain a logic-high voltage when the SoC and attached agents float this tri-state bus.
ESPI_IRCOMP	I,O	No	**ESPI_IRCOMP:** Special compensation resistor to support 3.3V. The platform board must provide a 100 Ω, 1% resistor connected from this pin to VSS.
Boot BIOS Strap	I	Yes	See Chapter 4, "Strapping and Configuration."
LPC Decode Select	I	Yes	See Chapter 4, "Strapping and Configuration."
VCC_LPC_ESPI_3P3_1P8	I (Voltage)	n/a	The platform must supply V3P30 to this voltage-supply pin. The SoC voltage-supply pins are listed in Section 39.3, "Directory of Voltage Supply and Sense Pin Names" on page 1029. Also see Chapter 4, "Strapping and Configuration".

20.2 Feature List

LPC controller implements a *Intel® Low Pin Count (LPC) Interface Specification*.

20.3 Architectural Overview

The LPC controller implements a *Intel® Low Pin Count (LPC) Interface Specification*. The LPC bus is operating at a clock frequency of 24 MHz. The LPC interface is used for connection of various legacy components.

20.3.1 LPC Cycle Types

The LPC controller implements all of the cycle types described in the *Intel® Low Pin Count (LPC) Interface Specification*.

There is no support for DMA or bus mastering from the LPC.

20.3.2 Memory Cycle

The LPC provides a generic memory range for decoding memory cycles and forwarding as standard LPC memory cycles on the LPC bus. The generic memory decode range is 64 KB in size, locatable anywhere within the 4 GB memory space. The range is configured by the BIOS during POST to provide the memory resources needed. The BIOS will advertise the range to the operating system (OS) as reserved memory to avoid any resource conflict.

For cycles targeting firmware, firmware memory cycles are used. Only 8-bit transfers are performed. If a larger transfer appears on the backbone, the LPC controller will break it into multiple 8-bit transfers until the request is satisfied.

If the cycle is not claimed by any peripheral (and subsequently aborted), the LPC controller will return a value of all 1s to the SoC core. This is to maintain compatibility with ISA memory cycles where pull-up resistors would keep the bus high if no device responds.

20.3.3 I/O Cycle

All I/O cycles will be performed as 8-bit transfers per the LPC specification. If a larger size is attempted, the LPC controller will perform multiple 8-bit transfers until the request is satisfied.

20.3.4 DMA Cycle

DMA is not supported.

20.3.5 Bus Master Cycle Notes

Bus mastering to the LPC is not supported.

20.3.6 LFRAME# Usage

The controller follows the usage of LFRAME# as defined in the *Intel® Low Pin Count (LPC) Interface Specification*.

20.3.7 LPC PD# Protocol

This signal is provided to the LPC peripherals using the SoC output signal SUS_STAT_N. After driving SUS_STAT_N low (active), the SoC drives LPC_FRAME_N (LFRAME#) low, and tri-states or drives low the LPC_AD[3:0] bus.

Note: *Intel® Low Pin Count (LPC) Interface Specification* defines LPCPD# protocol where at least 30µs is from LPCPD# assertion to LRESET# assertion. This specification explicitly states the protocol only applies to entry or exit of low-power states which does not include asynchronous reset events. The SoC asserts both SUS_STAT_N (LPCPD#) and PMU_PLTRST_N (LRESET#) at the same time during a global reset.

20.3.8 LPC Interface Decoders

In order to allow I/O and memory mapped cycles to go to the LPC interface, the LPC controller includes several decoders. The decoders are located at offset 80h - 9Fh in the device configuration space.

20.3.9 SERR# Generation

When the LPC receives an error SYNC on the LPC bus, an internal SERR# will be generated. This occurs only if SERR reporting is enabled for the LPC.

20.3.10 Dynamic LPC Clock Control

This LPC clock control is achieved through the LPC_CLKRUN_N signal. If an LPC device needs the 24 MHz LPC clock, then it can assert.

20.3.10.1 Verifying if Safe to Stop the LPC Clock

With a lack of LPC activity, the SoC is able to shut off the LPC clocks to conserve power. LPC activity is defined as any activity that would require the LPC clock to be running.

Any of the following conditions will indicate that it is *not* safe to stop the LPC clock:

- Cycles on the LPC (as a target)
- Cycles of any internal device that would need to go on the LPC bus (as a target)
- SERIRQ activity (as a target and master)

Behavioral description:

1. When there is a lack of activity (as defined above) for t90 clocks, the SoC will drive the LPC_CLKRUN_N signal high t91 later.
2. One clock later, the SoC will tri-state the LPC_CLKRUN_N signal.

20.3.10.2 Conditions for Maintaining the LPC Clock

LPC devices that wish to maintain the LPC clock running will observe the LPC_CLKRUN_N signal high, and then must drive it low within t92 clocks.

Behavioral description:

1. When the SoC has driven the LPC_CLKRUN_N signal high, it will then check to see if it is driven low (externally).
2. After observing the LPC_CLKRUN_N signal low for 1 clock, the SoC will then start driving the signal low.
3. If an internal device needs the LPC bus, then the SoC will drive LPC_CLKRUN_N the clock signal active.

20.3.10.3 Conditions for Stopping the LPC Clock

If no device drives LPC_CLKRUN_N low once it has been high for t93 clocks, the SoC will stop the LPC clocks.

20.3.10.4 Conditions for Restarting the LPC Clock

Behavioral description:

1. If a peripheral asserts the LPC_CLKRUN_N signal, the SoC will restart the clock.
2. The SoC will drive LPC_CLKRUN_N low 1 clock after the first rise edge of the LPC clock. The peripheral likewise must continue to drive LPC_CLKRUN_N low until the second rising edge of the LPC clock is detected.
3. If an internal source requests the clock to be restarted, the SoC will assert LPC_CLKRUN_N.

Figure 20-2. LPC_CLKRUN_N Timings



Table 20-3. LPC_CLKRUN_N Timings

Symbol	Minimum	Maximum	Units	Description
t90	29	30	LPC CLK	No activity to idle detect
t91	1	1	LPC CLK	Idle detect to LPC_CLKRUN_N high
t92	2	3	LPC CLK	LPC_CLKRUN_N high to LPC_CLKRUN_N (no stop) [if low from external source] ***Note:*** The maximum can be 5 if LPC_CLKRUN_N low (no stop) due to an internal source
t93	6		LPC CLK	LPC_CLKRUN_N high (stop)
t94	1		LPC CLK	LPC_CLKRUN_N low (restart)

Note: Timing t94 only applies to external devices asserting LPC_CLKRUN_N. If an internal source is active and requests for LPC CLK to be restarted, the SoC will assert LPC_CLKRUN_N. This is because clock synchronization is not required.

20.4 Register Map

Figure 20-3 shows the associated registers from a system software viewpoint.

Figure 20-3. Register Map



20.4.1 PCI Configuration and Capabilities

Table 20-4. LPC Register Map - Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D31F:F0 (hexadecimal)	Register Short Name	Description
00	ID	Identifiers
04	CMD	Command
06	STS	Device Status
08	RID	Revision ID
09	CC	Class Code
0D	PLT	Primary Latency Timer
0E	HTYPE	Header Type
2C	SS	Subsystem Identifiers
34	CAPP	Capability List Pointer
64	SCNT	Serial IRQ Control
80	IOD	I/O Decode Ranges
82	IOE	I/O Enables
84	LGIR1	LPC Generic I/O Range #1
88	LGIR2	LPC Generic I/O Range #2
8C	LGIR3	LPC I/O Range #3
90	LGIR4	LPC I/O Range #4
94	ULKMC	USB Legacy Keyboard/Mouse Control
98	LGMR	LPC Generic Memory Range
9C	RSVD	Reserved
D0	FS1	FWH ID Select #1
D4	FS2	FWH ID Select #2
D8	BDE	BIOS Decode Enable
DC	BC	BIOS Control
E0	PCCTL	PCI Clock Control

20.4.2 Fixed I/O Address Transactions

This subsection lists the claimable fixed I/O addresses by the LPC controller on the primary interface.

Table 20-5. LPC Claimable Fixed I/O Range as Target on Primary Interface (Sheet 1 of 2)

<table>
<tr><th>#</th><th>Address Decode Range</th><th>Allocatable Size (bytes)</th><th>Enable B0:D31:F0 + Offset</th><th>Description</th></tr>
<tr><td>1</td><td>200h – 207h</td><td>8</td><td>0x82h[9]</td><td>Gameport High</td></tr>
<tr><td>2</td><td>208h – 20Fh</td><td>8</td><td>0x82h[8]</td><td>Gameport Low</td></tr>
<tr><td>3</td><td>B0:D31:F0+0x80h[12]
<table><tr><th>Bits</th><th>Decode Range</th></tr><tr><td>0</td><td>3F0h - 3F5h, 3F7h (primary)</td></tr><tr><td>1</td><td>370h - 375h, 377h (secondary)</td></tr></table>2 ranges in 64k I/O space</td><td>8</td><td>0x82h[3]</td><td>Floppy Disk Drive Port</td></tr>
<tr><td>4</td><td>B0:D31:F0+0x80h[9:8]
<table><tr><th>Bits</th><th>Decode Range</th></tr><tr><td>00</td><td>378h - 37Fh and 778h - 77Fh</td></tr><tr><td>01</td><td>278h - 27Fh (port 279h is read only) and 678h - 67Fh</td></tr><tr><td>10</td><td>3BCh - 3BEh and 7BCh - 7BEh</td></tr><tr><td>11</td><td>Reserved</td></tr></table>3 ranges in 64k I/O space</td><td>8</td><td>0x82h[2]</td><td>LPC Parallel Port</td></tr>
<tr><td>5</td><td>B0:D31:F0+0x80h[6:4]
<table><tr><th>Bits</th><th>Decode Range</th></tr><tr><td>000</td><td>3F8h - 3FFh (COM 1)</td></tr><tr><td>001</td><td>2F8h - 2FFh (COM 2)</td></tr><tr><td>010</td><td>220h - 227h</td></tr><tr><td>011</td><td>228h - 22Fh</td></tr><tr><td>100</td><td>238h - 23Fh</td></tr><tr><td>101</td><td>2E8h - 2EFh (COM 4)</td></tr><tr><td>110</td><td>338h - 33Fh</td></tr><tr><td>111</td><td>3E8h - 3EFh (COM 3)</td></tr></table>8 ranges in 64k I/O space</td><td>8</td><td>0x82h[1]</td><td>ComB Port</td></tr>
</table>

Table 20-5. LPC Claimable Fixed I/O Range as Target on Primary Interface (Sheet 2 of 2)

<table>
<tr><th>#</th><th>Address Decode Range</th><th>Allocatable Size (bytes)</th><th>Enable B0:D31:F0 + Offset</th><th>Description</th></tr>
<tr><td>6</td><td>B0:D31:F0+0x80h[2:0]
<table><tr><th>Bits</th><th>Decode Range</th></tr><tr><td>000</td><td>3F8h - 3FFh (COM 1)</td></tr><tr><td>001</td><td>2F8h - 2FFh (COM 2)</td></tr><tr><td>010</td><td>220h - 227h</td></tr><tr><td>011</td><td>228h - 22Fh</td></tr><tr><td>100</td><td>238h - 23Fh</td></tr><tr><td>101</td><td>2E8h - 2EFh (COM 4)</td></tr><tr><td>110</td><td>338h - 33Fh</td></tr><tr><td>111</td><td>3E8h - 3EFh (COM 3)</td></tr></table>8 ranges in 64k I/O space</td><td>8</td><td>0x82h[0]</td><td>ComA Port</td></tr>
</table>

20.4.3 Configurable I/O Address Transactions

This subsection lists the claimable configurable I/O addresses by the LPC controller on the primary interface.

Table 20-6. LPC Claimable Configurable I/O Range as Target on Primary Interface

#	Address Decode Range	Allocatable Size (bytes)	Enable B0:D31:F0 + Offset	Description
1	4 to 256 bytes I/O block size anywhere in the 64k I/O space	4 – 256	0x84h[0]	LPC Generic I/O Range #1
2			0x88h[0]	LPC Generic I/O Range #2
3			0x8Ch[0]	LPC Generic I/O Range #3
4			0x90h[0]	LPC Generic I/O Range #4

20.4.4 Memory and BIOS Address Transactions

This subsection lists the claimable memory and BIOS addresses by the LPC controller on the primary interface.

Table 20-7. LPC Claimable Memory Mapped Range as Target on Primary Interface

#	Address Decode Range	Allocatable Size (bytes)	Enable B0:D31:F0 + Offset	Claiming Agent	Description
1	64 KB memory block anywhere in the 4 GB memory space	64 KB	0x98h[0]	LPC or Serial Peripheral Interface (SPI) primary. The source decode to determine the claiming agent using the BBS and LPC SoC hard (pin) straps. {BBS, LPC decode} 00 → SPI 01 → SPI 10 → LPC[1]	LPC Generic Memory Range
2[1]	000E_0000h – 000E_FFFFh	64 KB	0xD8h[6]		BIOS Legacy E segment
3[1]	000F_0000h – 000F_FFFFh	64 KB	0xD8h[7]		BIOS Legacy F segment
4	FFC0_0000h – FFC7_FFFFh	512 KB	0xD8h[8]		BIOS C0-C7 Data space
5	FF80_0000h – FF87_FFFFh	512 KB	0xD8h[8]		BIOS C0-C7 Feature space
6	FFC8_0000h – FFCF_FFFFh	512 KB	0xD8h[9]		BIOS C8-CF Data space
7	FF88_0000h – FF8F_FFFFh	512 KB	0xD8h[9]		BIOS C8-CF Feature space
8	FFD0_0000h – FFD7_FFFFh	512 KB	0xD8h[10]		BIOS D0-D7 Data space
9	FF90_0000h – FF97_FFFFh	512 KB	0xD8h[10]		BIOS D0-D7 Feature space
10	FFD8_0000h – FFDF_FFFFh	512 KB	0xD8h[11]		BIOS D8-DF Data space
11	FF98_0000h – FF9F_FFFFh	512 KB	0xD8h[11]		BIOS D8-DF Feature space
12	FFE0_0000h – FFE7_FFFFh	512 KB	0xD8h[12]		BIOS E0-E7 Data space
13	FFA0_0000h – FFA7_FFFFh	512 KB	0xD8h[12]		BIOS E0-E7 Feature space
14	FFE8_0000h – FFEF_FFFFh	512 KB	0xD8h[13]		BIOS E8-EF Data space
15	FFA8_0000h – FFAF_FFFFh	512 KB	0xD8h[13]		BIOS E8-EF Feature space
16	FFF0_0000h – FFF7_FFFFh	512 KB	0xD8h[14]		BIOS F0-F7 Data space
17	FFB0_0000h – FFB7_FFFFh	512 KB	0xD8h[14]		BIOS F0-F7 Feature space
18	FFF8_0000h – FFFF_FFFFh	512 KB	Always enabled		BIOS F8-FF Data space. Swappable using Top Swap soft strap.
19	FFB8_0000h – FFBF_FFFFh	512 KB	Always enabled		BIOS F8-FF Feature space. Not Swappable using Top Swap soft strap. Chapter 4, "Strapping and Configuration"
20	FF70_0000h – FF7F_FFFFh	1 MB	0xD8h[3]		BIOS 70-7F Data space
21	FF30_0000h – FF3F_FFFFh	1 MB	0xD8h[3]		BIOS 70-7F Feature space
22	FF60_0000h – FF6F_FFFFh	1 MB	0xD8h[2]		BIOS 60-6F Data space
23	FF20_0000h – FF2F_FFFFh	1 MB	0xD8h[2]		BIOS 60-6F Feature space
24	FF50_0000h – FF5F_FFFFh	1 MB	0xD8h[1]		BIOS 50-5F Data space
25	FF10_0000h – FF1F_FFFFh	1 MB	0xD8h[1]	LPC or SPI primary. The source decode to determine the claiming agent using the boot BIOS and LPC SoC hard (pin) straps.	BIOS 50-5F Feature space
26	FF40_0000h – FF4F_FFFFh	1 MB	0xD8h[0]		BIOS 40-4F Data space
27	FF00_0000h – FF0F_FFFFh	1 MB	0xD8h[0]		BIOS 40-4F Feature space

1. Intel is not validating legacy support.

20.4.4.1 BIOS Write Protect and Top Swap Range

Table 20-8, "LPC Claimable Configurable I/O Range as Target on Primary Interface" lists the BIOS Decode Address range that are subjected to the Write Protect Disable, Enable InSMM.STS (EISS) and Top Swap configuration.

Table 20-8. LPC Claimable Configurable I/O Range as Target on Primary Interface

BIOS Decode Address Range	WPD	EISS	Writes	Top Swap
All ranges: Feature Space	X	X	Allowed	No
Other BIOS decode ranges (Data Space) & Legacy E/F Segments	0	X	Blocked	Only apply to EF8 (FFF80000h - FFFFFFFFh)
	1	0	Allowed	
Note: Intel is not validating legacy support.	1	1	Allowed if InSMM.STS = 1	

20.4.4.2 BIOS Boot Decode Claiming Agent

Table 20-9, "BIOS Boot Decode Claiming Agent" lists the claiming agents for the BIOS cycles to access the Boot codes and the respective BIOS Decode Range Register location. The Boot BIOS Pin Strap goes out to 2 locations, namely SPI and LPC. The BBS register for these registers are programmable to override the SoC hard (pin) strap value. BIOS needs to ensure that the BBS values on both locations (SPI and LPC) are set the same (match).

Table 20-9. BIOS Boot Decode Claiming Agent

Pin BR58 Boot BIOS Strap (BBS)	Pin BL52 LPC Decode Select	BIOS Boot Location	BIOS Boot Decode Range Register Location
0	0	SPI	SPI PCI Configuration Register. Program SPI PCI-configuration (D31:F5) BIOS Decode Range Configuration Registers. SPI uses its own BIOS Decode Range to determine the BIOS Boot Location
0	1	SPI	
1	0	LPC	LPC PCI Configuration Register. Program LPC PCI-configuration (D31:F0) BIOS Decode Range Configuration Registers. LPC uses its own BIOS Decode Range to determine the BIOS Boot Location.

§ §

21 PIC and I/O APIC Controllers

This chapter describes the Programmable Interrupt Controller (PIC). The design is based on the legacy 8259 PIC device. This chapter also describes the I/O Advanced Programmable Interrupt Controller (IOxAPIC).

Figure 21-1. What is Covered in This Chapter



21.1 Signal Descriptions

There are no signal pins or signal names associated with this chapter.

21.2 Programmable Interrupt Controller (PIC)

The design is based on the legacy 8259 PIC device. The slave controller is cascaded onto the master controller through master controller interrupt input 2. This means there are 15 possible Interrupt Requests (IRQ) routed internally to the SoC PIC, see Figure 21-2. The interrupt routing is described in Chapter 8, "Interrupts and Events".

Figure 21-2. Master and Slave PIC



21.2.1 Special Internal Circuitry

Interrupts can be individually-programmed to be edge-triggered or level-sensitive, except for IRQ0, IRQ1, IRQ2 and IRQ8 which always default to edge-triggered.

Active-low interrupt sources, such as the PIRQ#, are internally inverted before being sent to the PIC. In the following descriptions of the 8259, the interrupt levels are in reference to the signals at the internal interface of the 8259, after the required inversions have occurred. Therefore, the term "high" indicates "active", which means "low" on an originating PIRQ#.

21.2.2 Generating Interrupts

The PIC interrupt sequence involves 3 bits, from the IRR, ISR, and IMR, for each interrupt level. These bits are used to determine the interrupt vector returned and the status of any other pending interrupts. Table 21-1 defines the IRR, ISR, and IMR.

Table 21-1. Interrupt Status Registers

Bit	Description
IRR	**Interrupt Request Register:** This bit is set on a low-to-high transition of the interrupt line in the edge mode and by an active high level in the level mode. This bit is set whether or not the interrupt is masked. However, a masked interrupt will not generate the internal INTR signal.
ISR	**Interrupt Service Register:** This bit is set, and the corresponding IRR bit cleared, when an interrupt acknowledge cycle is seen, and the vector returned is for that interrupt.
IMR	**Interrupt Mask Register:** This bit determines whether an interrupt is masked. Masked interrupts do not generate the internal INTR signal.

21.2.3 Acknowledging Interrupts

The processor generates an interrupt acknowledge cycle that is translated into a interrupt acknowledge cycle to the SoC. The PIC translates this command into two internal INTA# pulses expected by the 8259 controllers. The PIC uses the first internal INTA# pulse to freeze the state of the interrupts for priority resolution. On the second INTA# pulse, the master or slave sends the interrupt vector to the processor with the acknowledged interrupt code. This code is based on the five Interrupt Vector Base Address (IVBA) bits of the Master/Slave Initialization Command Word 2 (MICW2 or SICW2), combined with the three Interrupt Request Level (IRL) bits of the MICW2 or SICW2 which represent the interrupt within that controller.

Table 21-2 applies to the Master 8259 controller and to the Slave 8259 controller.

Table 21-2. Content of Interrupt Vector Byte

Master, Slave Interrupt to be serviced by the Interrupt Acknowledge cycle	Master/Slave ICW2 Bits [7:3] generated by the controller	Master/Slave ICW2 Bits [2:0] generated by the controller
IRQ7,15	Interrupt Vector Base Address (IVBA) in the Interrupt Vector Table for the interrupt routine	111
IRQ6,14		110
IRQ5,13		101
IRQ4,12		100
IRQ3,11		011
IRQ2,10		010
IRQ1,9		001
IRQ0,8		000

21.2.4 Hardware/Software Interrupt Sequence

1. One or more of the Interrupt Request lines (IRQ) are raised high in the edge mode or seen high in the level mode, setting the corresponding IRR bit.
2. The PIC sends the internal INTR signal to the processor if an asserted interrupt is not masked.
3. The processor acknowledges the INTR and responds with an internal interrupt acknowledge cycle.
4. When observing the special cycle, the SoC converts it into the two cycles that the internal 8259 pair need to responds. Each cycle appears as an interrupt acknowledge pulse on the internal INTA# signal of the cascaded interrupt controllers.
5. When receiving the first internally-generated INTA# pulse, the highest priority ISR bit is set and the corresponding IRR bit is reset. On the trailing edge of the first pulse, a slave identification code is broadcast by the master to the slave on a private, internal 3-bit wide bus. The slave controller uses these bits to determine if it must respond with an interrupt vector during the second, internal INTA# pulse.
6. When receiving the second internally generated INTA# pulse, the PIC returns the interrupt vector. If no interrupt request is present because the request was too short in duration, the PIC indicates a spurious interrupt by returning interrupt vector 7 from the master controller.
7. This completes the interrupt cycle. In Automatic End of Interrupt (AEOI) mode, the ISR bit is reset at the end of the second INTA# pulse. Otherwise, the ISR bit remains set until an appropriate EOI command is issued at the end of the interrupt subroutine.

21.2.5 Initialization Command Words (ICWx)

Before an operation begins, each 8259 must be initialized. In the SoC, this is a four-byte sequence. The four Initialization Command Words (ICW) are referred by their acronyms: ICW1, ICW2, ICW3, and ICW4.

The base address for each 8259 initialization command word is a fixed location in Host I/O Space address 20h for the master controller and address A0h for the slave controller.

21.2.5.1 ICW1

A write to the master or slave controller base address with data bit 4 equal to 1 is interpreted as a write to ICW1. Upon sensing this write, the PIC expects three more byte writes to 21h for the master controller or A1h for the slave controller to complete the ICW sequence.

A write to ICW1 starts the initialization sequence during which the following automatically occurs:

1. Following initialization, an Interrupt Request (IRQ) input must make a low-to-high transition to generate an interrupt.
2. The Interrupt Mask Register is cleared.
3. IRQ7 input is assigned priority 7.
4. The slave mode address is set to 7.
5. Special mask mode is cleared, and the status read is set to IRR.

21.2.5.2 ICW2

The second write in the sequence (ICW2) is programmed to provide bits [7:3] of the interrupt vector that are released during an interrupt acknowledge. A different base is selected for each interrupt controller. See Table 21-2, “Content of Interrupt Vector Byte” on page 640.

21.2.5.3 ICW3

The third write in the sequence (ICW3) has a different meaning for each controller.

- For the master controller, ICW3 indicates which of the master’s IRQ input lines cascades the IRQ[15:8] of the slave controller. Within the SoC, IRQ2 is used. Therefore, the Cascaded Controller Connection (CCC) indication, bit 2 of the MICW3 is set to a 1 and the other bits are set to 0s.
- For the slave controller, ICW3 is the slave identification code used during an interrupt acknowledge cycle. On interrupt acknowledge cycles, the master controller broadcasts a code to the slave controller if the cascaded interrupt won arbitration on the master controller. The slave controller compares this identification code to the value stored in its ICW3, and if it matches, the slave controller assumes responsibility for broadcasting the interrupt vector.

21.2.5.4 ICW4

The final write in the sequence (ICW4) must be programmed for the master controller and for the slave controller. At least the Microprocessor Mode (MM) indication, bit 0 of the ICW4, must be set to a 1 to indicate the controllers are operating in an Intel® architecture system.

21.2.6 Operation Command Words (OCW)

These command words reprogram the interrupt controller to operate in various interrupt modes:

- OCW1 masks and unmasks the interrupt lines.
- OCW2 controls the rotation of interrupt priorities when in rotating priority mode and controls the EOI function.
- OCW3 sets up the ISR/IRR reads, enables/disables the Special Mask Mode (SMM), and enables/disables the polled interrupt mode.

21.2.7 Fully-Nested Mode

In this mode, interrupt requests are ordered in priority from 0 through 7, with 0 being the highest. When an interrupt is acknowledged, the highest priority request is determined and its vector placed on the bus. Additionally, the ISR for the interrupt is set. This ISR bit remains set until: the processor issues an End of Interrupt (EOI) command immediately before returning from the service routine or if in Automatic End of Interrupt (AEOI) mode, on the trailing edge of the second, internal INTA# signal. While the ISR bit is set, all further interrupts of the same or lower priority are inhibited, while higher levels generate another interrupt. Interrupt priorities are changed in the rotating priority mode.

21.2.8 Special Fully-Nested Mode

This mode is used in the case of a system where cascading is used, and the priority has to be conserved within each slave. In this case, the special fully-nested mode is programmed to the master controller. This mode is similar to the fully-nested mode with the following exceptions:

- When an interrupt request from a certain slave is in service, this slave is not locked out from the master priority logic, and further interrupt requests from higher priority interrupts within the slave are recognized by the master and initiate the interrupts to the processor. In the normal-nested mode, a slave is masked out when its request is in service.
- When exiting the interrupt service routine, the software has to check whether the interrupt serviced was the only one from that slave. This is done by sending a Non-specific EOI command to the slave and then reading its ISR. If it is 0, a non-specific EOI is also sent to the master.

21.2.9 Automatic Rotation Mode (Equal Priority Devices)

In some applications, there are a number of interrupting devices of equal priority. The automatic rotation mode provides for a sequential eight-way rotation. In this mode, a device receives the lowest priority after being serviced. In the worst case, a device requesting an interrupt has to wait until each of the seven other devices are serviced at most once.

Two ways to accomplish automatic rotation using the three-bit Rotate and EOI Codes (REOI) bits [7:5] of the OCW2 are:

101 = Rotation on the Non-Specific EOI command
100 = Rotation in the Automatic EOI mode

21.2.10 Specific Rotation Mode (Specific Priority)

The software changes the interrupt priorities by programming the bottom priority. For example, if IRQ5 is programmed as the bottom-priority device, then IRQ6 is the highest-priority device. This is accomplished by using the three-bit Rotate and EOI Codes (REOI) field, bits [7:5] of the OCW2:

110 = Set Priority command

along with the three-bit Interrupt Level Select (L2, L1, L0) (ILSLT) field, bits [2:0] of the OCW2 to indicate the binary priority level code of the bottom priority device.

In this mode, the internal status is updated by the software control during OCW2. However, it is independent of the EOI command. Priority changes are executed during an EOI command by using REOI set to:

111 = Rotate on Specific EOI command

along with the three-bit ILSLT to indicate the binary priority level code of the bottom priority device.

21.2.11 Poll Mode

The poll mode conserves space in the interrupt vector table. Multiple interrupts that are serviced by one interrupt service routine do not need separate vectors if the service routine uses the Poll command. The poll mode is also used to expand the number of interrupts. The polling interrupt service routine calls the appropriate service routine instead of providing the interrupt vectors in the vector table. In this mode, the internal INTR output signal is not used and the processor internal interrupt enable flip-flop is reset, disabling its interrupt input. Service to the devices is achieved by the software using a Poll command.

The Poll command is issued by setting the Poll Mode Command (PMC), bit 2 of the OCW3. The PIC treats its next Host I/O Read as an interrupt acknowledge, sets the appropriate ISR bit if there is a request, and reads the priority level. Interrupts are frozen from the OCW3 write to the Host I/O Read. The byte returned during the Host I/O Read contains a 1 in bit 7 if there is an interrupt, and the binary code of the highest-priority level is indicated by bits [2:0].

21.2.12 Edge- and Level-Triggered Mode

In Industry Standard Architecture (ISA) systems, this mode is programmed using the Level-Triggered Interrupt Mode (LITM), bit 3 of the ICW1, which sets level or edge for the entire controller. In the SoC, this bit is disabled and a register for edge- and level-triggered mode selection is provided per interrupt input. These make up the Master Edge/Level Control (ELCR1) and Slave Edge/Level Control (ELCR2) registers.

If the ELCR bit is 0, an interrupt request is recognized by a low-to-high transition on the corresponding IRQ input. The IRQ input remains high without generating another interrupt. If the ELCR bit is 1, an interrupt request is recognized by a high level on the corresponding IRQ input, and an edge detection is not needed. The interrupt request must be removed before the EOI command is issued to prevent a second interrupt from occurring.

In both the edge- and level-triggered modes, the IRQ inputs must remain active until after the falling edge of the first internal INTA# signal. If the IRQ input goes inactive before this time, a default IRQ7 vector is returned indicating a spurious interrupt.

21.2.13 End of Interrupt (EOI) Operations

An EOI occurs in one of two fashions:

- Normal EOI - by a command word write issued to the PIC before returning from a service routine, the EOI command
- Automatic EOI - when the Automatic End of Interrupt (AEOI), bit 1 of ICW4, is set to 1.

21.2.13.1 Normal End of Interrupt (EOI) Mode

In normal EOI mode, the software writes an EOI command before leaving the interrupt service routine to mark the interrupt as completed. The two forms of EOI commands are: Specific and Non-Specific.

When a Non-Specific EOI command is issued, the PIC clears the highest ISR bit of those that are set to 1. A Non-Specific EOI is the normal mode of operation of the PIC within the SoC, as the interrupt being serviced currently is the interrupt entered with the interrupt acknowledge. When the PIC is operated in the modes that preserve the fully-nested structure, the software determines which ISR bit to clear by issuing a specific EOI.

An ISR bit that is masked is not cleared by a non-specific EOI if the PIC is in the special mask mode. An EOI command must be issued for both the master and slave controller.

21.2.13.2 Automatic End of Interrupt (AEOI) Mode

In this mode, the PIC automatically performs a Non-Specific EOI operation at the trailing edge of the last interrupt acknowledge pulse. From a system standpoint, this mode is used only when a nested multi-level interrupt structure is not required within a single PIC. The AEOI mode is only used in the master controller and not the slave controller.

Note: Both the master and slave PICs have an AEOI bit in MICW4 and SICW4 respectively. Only the AEOI bit of MICW4 is set by the software. The AEOI bit of SICW4 is not set by the software.

21.2.14 Masking Interrupts

21.2.14.1 Masking on an Individual Interrupt Request

Each interrupt request is masked individually by the Interrupt Mask Register (IMR). This register is programmed through OCW1. Each bit in the IMR masks one interrupt channel. Masking IRQ2 on the master controller masks all requests for service from the slave controller.

21.2.14.2 Special Mask Mode

Some applications may require an interrupt service routine to dynamically alter the system priority structure during its execution under software control. For example, the routine may wish to inhibit lower priority requests for a portion of its execution but enable some of them for another portion.

The Special Mask Mode enables all interrupts not masked by a bit set in the Mask Register. Normally, when an interrupt service routine acknowledges an interrupt without issuing an EOI to clear the ISR bit, the interrupt controller inhibits all lower priority requests. In the special mask mode, any interrupts are selectively enabled by loading the mask register with the appropriate pattern.

The Special Mask Mode is set when the Enable Special Mask Mode (ESMM), bit 5 of OCW3, and the Special Mask Mode (SMM), bit 6 of OCW3, are programmed to 1. Special Mask Mode is cleared when ESMM = 1 and SMM = 0. The SMM bit has no meaning when ESSM is 0.

21.3 I/O Advanced Programmable Interrupt Controller (IOxAPIC)

- Up to 120 interrupt requests (IRQ0 through IRQ119). Default-set to 24.
- Edge- or level-trigger mode per interrupt
- Active-low or -high polarity per interrupt
- Uses an MSI-like memory write cycle to send interrupts for local (processor) APICs
- Established APIC programming model

21.3.1 Interrupt Redirection Table

The interrupt Redirection Table of the SoC IOxAPIC provides 120 64-bit I/O Interrupt Redirection Table Entry (RTE) registers. Each RTE register is dedicated to one of the 120 internal, Interrupt Request (IRQ) input signals. For information about interrupts routed to the IOxAPIC see Chapter 8, "Interrupts and Events".

The information in each RTE is used to translate the interrupt manifestation on the corresponding IOxAPIC Interrupt Request input signal into a message to the local APICs.

The Maximum Redirection Entries (MRE) is default-set to indicate 24 (decimal) interrupts, IRQ[23:0]. BIOS can change this maximum number through the Read-Write-Once (RWO), eight-bit MRE field of the Version (VS) register. MRE contains the RTE number (0 being the lowest entry) of the highest entry in the Redirection Table.

BIOS must write to the MRE field after the SoC asserts the active-low PMU_PLTRST_N platform reset signal pin in order to lock-down the RWO value. This allows BIOS to utilize some of the entries for its own purpose and thus advertising fewer IOxAPIC Redirection Entries to OS. BIOS may program the eight-bit MRE field with a value up to 78h (maximum of 120 RTE registers).

Unlike IRQ pins of the 8259, the notion of interrupt priority is completely unrelated to the position of the physical interrupt input signal on the IOxAPIC. Instead, the software determines the vector (and therefore the priority) for each corresponding interrupt input signal. For each interrupt signal, the operating system also specifies the signal polarity (low active or high active), whether the interrupt is signaled as edges or levels, as well as the destination and delivery mode of the interrupt.

The information in the Redirection Table translates the corresponding interrupt pin information into an inter-APIC message.

21.3.2 Accessing the Redirection Table

A 32-bit Identification (ID) register, 32-bit Version (VS) register, and 120 64-bit RTE registers are accessible in Host Memory Space through an Index (IDX) - Window (WDW) mechanism. The mechanism itself can be relocated within Host Memory Space. See Table 21-6, "IOxAPIC Register Access Window in Host Memory Space" on page 652 and Table 21-7, "IOxAPIC Registers" on page 652.

When accessing the indexed registers, accesses must be done as 32-bit Double-Words or else unspecified behavior results. Software must not attempt to write to reserved registers. Some reserved registers may return non-zero values when read.

21.3.3 IOxAPIC Interrupts to the Local APICs

The VT-d architecture extension requires Interrupt Messages to go through the similar Address Remapping as any other memory requests. This is to allow domain isolation for interrupts such that a device assigned in one domain is not allowed to generate interrupts to another domain.

The Address Remapping for VT-d is based on the Bus:Device:Function field associated with the requests. Hence, it is required for the internal IOxAPIC to initiate the Interrupt Messages using a unique Bus:Device:Function.

The SoC Primary-to-Sideband (P2SB) Bridge PCI device (B:0, D:31, F:1) provides this VT-d capability and issues the MSI-like, IOxAPIC Interrupt Message to the processor local APICs on behalf of the IOxAPIC as an upstream 32-bit Memory Write-Cycle Transaction. The P2SB Bridge B/D/F is used in the Requester ID when the IOxAPIC initiates sending Interrupt Messages to the CPU. The Host Memory-Space address and data values are derived from the Relocation table Entry (RTE) for the interrupt and follow the format shown in Figure 21-3 on page 647.

Figure 21-3. MSI-Like IOxAPIC Interrupt Message for the Local APICs



The P2SB Bridge B/D/F is also used as the Completer ID in response to reads targeting the IOxAPICs Memory-Mapped I/O (MMIO) registers. See Section 21.3.2, "Accessing the Redirection Table" on page 646.

Note: While the P2SB Bridge is the designated PCI device to act on behalf of the IOxAPIC Interrupt Message Writes and Reads of its MMIO registers, there is a register that determines the B/D/F values for the IOxAPIC's surrogate PCI device. The register is the IOxAPIC Bus:Device:Function (IBDF) and is located in Host Configuration Space of the P2SB Bridge, offset 6Ch. The default for IBDF is B:0, D:31, F:0 (LPC) and must be changed to B:0, D:31, F:1 (P2SB Bridge).

The Host Memory Space address of the IOxAPIC Interrupt Message is formed as shown in Table 21-3. The data is shown in Table 21-4.

Table 21-3. IOxAPIC Interrupt Message Address

Address Bit	Short Description	Description
31:20	FEEh	Hardwired as FEEh
19:12	Destination ID	Destination ID of the local APIC - from DID field of the interrupt RTE
11:4	Extended Destination ID	Extended destination ID of the local APIC - from EDID field of the interrupt RTE
3	Redirection Hint	Redirection Hint - '1' If the DLM field = "Lowest Priority" (001) for the interrupt RTE. Otherwise '0'
2	Destination Mode	Used by the Local APIC to determine whether it is the destination of the Interrupt Message
1:0	00	Hardwired as 00 - Interrupt Message data is written as a Double Word (32 bits)

Table 21-4. IOxAPIC Interrupt Message Data

Data Bit	Short Description	Description
31:16	0000h	Hardwired as 0000h
15	Trigger Mode	From TM field of the RTE - '0' indicates the interrupt is edge sensitive. '1' indicates the interrupt is level sensitive.
14	Delivery Status	Is always '1' indicating an "Assert Message" cycle
13:12	00	Hardwired as 00
11	Destination Mode	From DSM field of the RTE - Used by the Local APIC to determine whether it is the destination of the message
10:8	Delivery Mode	From DLM field of the RTE - How the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode. The supported modes are described in Section 21.3.4, "Interrupt Delivery Modes" on page 649.
7:0	Vector	From VCT field of the RTE - Interrupt Vector for this interrupt. Values range between 10h and Feh

21.3.4 Interrupt Delivery Modes

The IOxAPIC supports these Interrupt Delivery Modes (DLM) to the local APICs:

- 000 = Fixed. Deliver the signal on the INTR (internal) signal of all processor cores listed in the Destination field of the RTE. The Trigger Mode field of the RTE can be edge or level.
- 001 = Lowest Priority. Deliver the signal on the INTR (internal) signal of the processor core that is executing at the lowest priority among all the processors listed in the specified Destination field of the RTE. Trigger Mode can be edge or level.
- 111 = ExtINT. Deliver the signal to the INTR signal of all processor cores listed in the Destination field as an interrupt that originated in the 8259 interrupt controller. The INTA cycle that corresponds to this ExtINT delivery is routed to the 8259 controller which is expected to supply the vector. Requires the interrupt to be programmed as edge triggered.

The IOxAPIC does not support the NMI, INIT, or SMI Delivery Modes. However, the SoC does send the Delivery Mode (DLM) value programmed in the Redirection Table as part of the Interrupt Message.

Note: Software is required to take precaution as the SoC does not internally route the NMI/INIT/SMI events to the IOxAPIC, nor attempting to resolve any dependency with the NMI/INIT/SMI delivery as described above even though the DLM field is programmed as such. If needed, this must be addressed outside of the SoC.

21.3.5 Determining Safe Message Delivery Time

When the IOxAPIC sends an Interrupt Message, it first ensures that all buffers that may contain main-memory-directed posted writes from legacy devices have been flushed to the point that when the interrupt is delivered to the CPU, any write data that needs to be processed by the Interrupt Service Software is available in the memory complex. When the legacy-device buffers are empty, the IOxAPIC delivers the interrupt that initiated the flush.

21.3.6 End Of Interrupt (EOI) Register

The 32-bit IOxAPIC EOI register is in Host Memory Space at address FEC0_0040h. The SoC P2SB Bridge PCI device (B:0, D:31, F:1) acts on the IOxAPIC's behalf. When a Host memory Write is issued to the 32-bit EOI register, the P2SB Bridge I/O checks the lower 8 bits written to this register and compares them with the Vector (VCT) field for each of the Redirection Table Entries (RTE 0 through RTE 119) in the Redirection Table.

When a match is found, the P2SB Bridge informs the IOxAPIC to clear the Remote IRR (RIRR) bit for that entry. If multiple entries have the same vector, each of those entries has its RIRR bit cleared.

21.4 Register Map

Figure 21-4 on page 650 shows the associated registers from a system software viewpoint.

Figure 21-4. Register Map



21.4.1 PCI Configuration and Capabilities

Table 21-5. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D31:F1 (hex)	Register Short Name	Description
64	IOAC	IOxAPIC Configuration
6C	IBDF	IOxAPIC Bus:Device:Function

21.4.2 Memory-Mapped Registers

The registers listed in Table 21-7 are described in detail in Chapter 64, "PIC and I/O APIC Controllers".

The IOxAPIC Configuration (IOAC) register is located in Host Configuration Space Bus 0, Device 31 (decimal), Function 1, offset 0x64. When Address Enable (AE) is set in IOAC bit 8, IOAC bits 7:0 define bits 19:12 of the Host Memory Space address used to access the IOxAPIC memory-mapped registers.

Table 21-6 shows the resulting memory addresses when bit 8 of the IOAC register is zero, the default register setting. The default setting of IOAC enables compatibility with the default setting of prior Intel products.

Table 21-6. IOxAPIC Register Access Window in Host Memory Space

Memory Address (hex)	Register Short Name	Register Long Name
FEC0_0000	IDX	Index Register
FEC0_0010	WDW	Window Register
FEC0_0040	EOI	EOI Register

Table 21-7 shows the IOxAPIC register accessed through the Window (WDW) Register for a given Index (IDX) register value. The register is indexed as 32-bit data entries as explained in Section 21.3.2, "Accessing the Redirection Table" on page 646.

Table 21-7. IOxAPIC Registers

Index Register Value (hex)	Information Accessed in the Window Register Short Name	Information Accessed in the Window Register Long Name
00	ID	Identification Register
01	VS	Version
02 through 0E	Reserved	Reserved
10 through FE	RTE0 through RTE119 (decimal)	Redirection Table Entry 0 through 119

Table 21-8 shows the IOxAPIC Interrupt Message locations in Host Memory Space.

Table 21-8. IOxAPIC Interrupt Messages for Local APICs in Host Memory Space

Memory Address (hex)	Register Short Name	Register Long Name
FEE0_0000 FEE0_0004 FEE0_0008 through FEEF_FFFC	-	IOxAPIC Interrupt Messages for processor Local APICs

21.4.3 I/O-Mapped Registers

Table 21-9. 8259 (PIC) Registers in Host I/O Space

I/O Port (hex)	Alias I/O Ports (hex)	Register Short Name	Register Name and Function
20	24h, 28h, 2Ch, 30h, 34h, 38h, 3Ch	MICW1	Master Initialization Command Word 1
		MOCW2	Master Operational Control Word 2
		MOCW3	Master Operational Control Word 3
21	25h, 29h, 2Dh, 31h, 35h, 39h, 3Dh	MICW2	Master Initialization Command Word 2
		MICW3	Master Initialization Command Word 3
		MICW4	Master Initialization Command Word 4
		MOCW1	Master Operational Control Word 1
A0	A4h, A8h, ACh, B0h, B4h, B8h, BCh	SICW1	Slave Initialization Command Word 1
		SOCW2	Slave Operational Control Word 2
		SOCW3	Slave Operational Control Word 3
A1	A5h, A9h, ADh, B1h, B5h, B9h, BDh	SICW2	Slave Initialization Command Word 2
		SICW3	Slave Initialization Command Word 3
		SICW4	Slave Initialization Command Word 4
		SOCW1	Slave Operational Control Word 1
4D0	-	ELCR1	Master Edge/Level Control
4D1	-	ELCR2	Slave Edge/Level Control

§ §

22 Primary to Side Band (P2SB) Bridge

This chapter describes software access to the SoC Sideband registers.

Figure 22-1. What is Covered in This Chapter



22.1 Signal Descriptions

There are no signal pins or signal names associated with this chapter.

22.2 Feature List

- SoC Sideband Registers are accessed through Memory Space
- SBREG_BAR points to the 16-MB area in 64-bit-addressable memory

22.3 Architectural Overview

The Sideband Register access mechanism is configured at Bus 0, Device 31 (decimal), Function 1 of Configuration Space. Its PCI class designation is that of an unspecified other memory controller. SBREG_BAR and SBREG_BARH form the 64-bit memory Base Address Register (BAR) which points to a non-prefetchable, 16-MB region of memory-mapped space.

Warning: All accesses to the SBREG_BAR region are DWORD aligned DWORDS. Writes larger than one DWORD are completed normally, but the write data beyond the first DWORD is discarded. Reads larger than one DWORD result in a Unsupported Request (UR) response. Byte enables within the DWORD are honored normally, enabling accesses of less than one DWORD.

The Sideband Register map is not provided in this chapter. Other chapters that refer to Sideband Registers provide the appropriate memory-mapped locations to access.

22.4 Register Map

Figure 22-2 shows the associated registers from a system software viewpoint.

Figure 22-2. Register Map



22.4.1 PCI Configuration and Capabilities

Table 22-1. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D31:F1 (hex)	Register Short Name	Description
Standard Type 0 PCI Configuration Registers		
0	PCIID	PCI Identifier
4	PCICMD	PCI Command
6	PCISTS	PCI Status
8	PCIRID	Revision ID
9	PCICC	Class Code
D	PCIMLT	PCI Master Latency Timer
E	PCIHTYPE	PCI Header Type
10	SBREG_BAR	Sideband Register Access BAR
14	SBREG_BARH	Sideband Register BAR High DWORD
2C	PCIHSS	PCI Subsystem Identifiers
Device-Specific PCI Configuration Registers		
50	VBDF	VLW Bus:Device:Function
52	EBDF	ERROR Bus:Device:Function
54	RCFG	Routing Configuration
60	HPTC	High Performance Event Timer Configuration
64	IOAC	IOxAPIC Configuration
6C	IBDF	IOxAPIC Bus:Device:Function
E0	P2SBC	P2SB Control
F0	URES	Unsupported Request Error Status
F4	UREC	Unsupported Request Error Control
F8	MANID	Manufacturer’s ID

22.4.2 Memory-Mapped Registers

The registers listed in Table 22-2 that rely on customer access to the SoC are described in various chapters of this document.

Table 22-2. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register
SBREG_BAR SBREG_BARH	0000	First accessible Sideband Register
	0004	Second accessible Sideband Register
	0008	Third accessible Sideband Register
	through	
	FFFC	Last accessible Sideband Register

§ §

23 Programmable Interval Timer (PIT)

This chapter describes the Programmable Interval Timer (PIT). The design is based on the legacy 8254 PIT device.

Figure 23-1. What is Covered in This Chapter



23.1 Signal Descriptions

There are no signal pins or signal names associated with this chapter.

23.2 Feature List

- Legacy 8254 PIT functions.

23.3 Architectural Overview

The SoC contains two counters that have fixed uses. All registers and functions associated with the 8254 timers are in the Core power well. The 8254 unit is clocked by a 1.193-MHz clock derived from 25-MHz internal ISCLK clock. Figure 23-2 shows how the 8254 PIT is implemented in the SoC.

Figure 23-2. Programmable Interval Timer (PIT) Implementation



23.3.1 Counter 0, System Timer

Counter 0 functions as the system timer by controlling the state of IRQ0 and is typically programmed for Mode 3 operation. See Table 23-1, “Counter Operating Modes” on page 662. The counter produces a square wave with a period equal to the product of the counter period (838 ns) and the initial count value. The counter loads the initial count value 1 counter period after software writes the count value to the counter I/O address. The counter initially asserts IRQ0 and decrements the count value by two each counter period. The counter negates IRQ0 when the count value reaches 0. It then reloads the initial count value and again decrements the initial count value by two each counter period. The counter then asserts IRQ0 when the count value reaches 0, reloads the initial count value, and repeats the cycle, alternately asserting and negating IRQ0.

23.3.2 Counter 2

Counter 2 was used in the original IBM PC to drive a speaker pin. The SoC does not have a dedicated speaker pin. The counter must be enabled by a write to TIM_CNT2_EN, bit 0 of the NMI_STS_CNT register at I/O Port 061h.

23.4 Counter Mode Definitions

Table 23-1 lists the six operating modes for the interval counters.

Table 23-1. Counter Operating Modes

Mode	Function	Description
0	Out signal on end of count (=0)	Output is 0. When count goes to 0, output goes to 1 and stays at 1 until counter is reprogrammed.
1	Hardware retriggerable one-shot	Output is 0. When count goes to 0, output goes to 1 for one clock time.
2	Rate generator (divide by n counter)	Output is 1. Goes to 0 for 1 clock time, then back to 1 and counter is reloaded.
3	Square wave output	Output is 1. Output goes to 0 when counter rolls over, and counter is reloaded. Output goes to 1 when counter rolls over, and counter is reloaded, and so on
4	Software triggered strobe	Output is 1. Output goes to 0 when count expires for one clock time.
5	Hardware triggered strobe	Output is 1. Output goes to 0 when count expires for one clock time.

23.5 Timer Programming

23.5.1 Writing to the Interval Timer

The counter/timers are programmed in the following fashion:

1. Write a control word to select a counter.
2. Write an initial count for that counter.
3. Load least and/or most significant bytes (as required by Control Word Bits 5, 4) of the 16-bit counter.
4. Repeat with other counters.

Only two conventions need to be observed when programming the counters.

1. For each counter, control word must be written before the initial count is written.
2. Initial count must follow the count format specified in the control word (least significant byte only, most significant byte only, or least significant byte, and then most significant byte).

A new initial count may be written to a counter at any time without affecting the counter's programmed mode. Counting is affected as described in the mode definitions. The new count must follow the programmed count format.

If a counter is programmed to read/write two-byte counts, the following precaution applies – a program must not transfer control between writing the first and second byte to another routine which also writes into that same counter. Otherwise, the counter will be loaded with an incorrect count.

The Timer Control Word (TCW) Register at I/O Port 43h controls the operation of all three counters. Several commands are available:

- Control Word Command. Specifies which counter to read or write, the operating mode, and the count format (binary or BCD). See Section 23.5.2.1, “Simple Read” on page 663.
- Counter Latch Command. Latches the current count so that it can be read by the system. The countdown process continues. See Section 23.5.2.2, “Counter Latch Command” on page 663.
- Read Back Command. Reads the count value, programmed mode, the current state of the OUT pins, and the state of the Null Count Flag of the selected counter. See Section 23.5.2.3, “Read Back Command” on page 664.

23.5.2 Reading from the Interval Timer

It is often desirable to read the value of a counter without disturbing the count in progress. There are three methods for reading the counters—a simple read operation, counter Latch command, and the Read-Back command. Each is explained below.

With the simple read and counter latch command methods, the count must be read according to the programmed format; specifically, if the counter is programmed for two byte counts, two bytes must be read. The two bytes do not have to be read one right after the other. Read, write, or programming operations for other counters may be inserted between them.

23.5.2.1 Simple Read

The first method is to perform a simple read operation. The counter is selected through C0_CAPR at I/O Port 40h (Counter 0) or C2_CAPR at I/O Port 42h (Counter 2).

Note: Performing a direct read from the counter does not return a determinate value, because the counting process is asynchronous to read operations. However, in the case of Counter 2, the count can be stopped by writing to the TIM_CNT2_EN bit, bit 0 of the NMI_STS_CNT register at I/O Port 061h.

23.5.2.2 Counter Latch Command

The Counter Latch command (CLC), written to I/O Port 43h, latches the count of a specific counter at the time the command is received. This command is used to ensure that the count read from the counter is accurate, particularly when reading a two-byte count. The count value is then read from each counter's Count register as was programmed by the Control register.

The count is held in the latch until it is read or the counter is reprogrammed. The count is then unlatched. This allows reading the contents of the counters on the fly without affecting counting in progress. Multiple Counter Latch Commands may be used to latch more than one counter. Counter Latch commands do not affect the programmed mode of the counter in any way.

If a Counter is latched and then, some time later, latched again before the count is read, the second Counter Latch command is ignored. The count read is the count at the time the first Counter Latch command was issued.

23.5.2.3 Read Back Command

The Read Back command (RBC), written to I/O Port 43h, latches the count value, programmed mode, and current states of the OUT pin and Null Count flag of the selected counter or counters. The value of the counter and its status may then be read by I/O access to the counter address.

The Read Back command may be used to latch multiple counter outputs at one time. This single command is functionally equivalent to several counter latch commands, one for each counter latched. Each counter's latched count is held until it is read or reprogrammed. Once read, a counter is unlatched. The other counters remain latched until they are read. If multiple count Read Back commands are issued to the same counter without reading the count, all but the first are ignored.

The Read Back command may additionally be used to latch status information of selected counters. The status of a counter is accessed by a read from that counter's I/O Port address. If multiple counter status latch operations are performed without reading the status, all but the first are ignored.

Both count and status of the selected counters may be latched simultaneously. This is functionally the same as issuing two consecutive, separate Read Back commands. If multiple count and/or status Read Back commands are issued to the same counters without any intervening reads, all but the first are ignored.

If both count and status of a counter are latched, the first read operation from that counter returns the latched status, regardless of which was latched first. The next one or two reads, depending on whether the counter is programmed for one or two type counts, returns the latched count. Subsequent reads return unlatched count.

23.6 Register Map

Figure 23-3 on page 665 shows the associated registers from a system software viewpoint.

Figure 23-3. Register Map



23.6.1 I/O-Mapped Registers

Table 23-2. Fixed-Address I/O-Mapped Registers

I/O Address and (Alias)	I/O Port Name	Access	Register Short Name	Register Long Name
0x40 (0x50)	Port 40h	RO	C0_ITSBFR	Counter 0 - Interval Timer Status Byte Format Register
0x41 (0x51)	*Reserved*		*Reserved*	*Reserved*
0x42 (0x52)	Port 42h	RO	C2_ITSBFR	Counter 2 - Interval Timer Status Byte Format Register
0x43 (0x53)	Port 43h	WO	TCW	[1]Timer Control Word Register
0x40 (0x50)	Port 40h	RW	C0_CAPR	Counter 0 - Counter Access Ports Register
0x42 (0x52)	Port 42h	RW	C2_CAPR	Counter 2 - Counter Access Ports Register
0x43 (0x53)	Port 43h	WO	RBC	[2]Read Back Command
0x43 (0x53)	Port 43h	WO	CLC	[3]Counter Latch Command
0x61	Port 61	RW	NMI_STS_CNT	NMI Status and Control

1. When data bits 7:6 are 00 or 10. The setting 01 is reserved. Also, data bits 5:4 must be 01, 10, or 11.
2. When data bits 7:6 are 11.
3. When data bits 7:6 are 00 or 10. The setting 01 is reserved. Also, data bits 5:4 must be 00.

§ §

24 Real Time Clock (RTC)

This chapter describes the SoC Real Time Clock (RTC).

Figure 24-1. What is Covered in This Chapter



24.1 Signal Descriptions

The signal descriptions are shown in Table 24-1. The signals associated with the RTC circuitry are shown as well as signal that reside in the SoC RTC power well. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing". The Direction/Type column of Table 24-1 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.

Table 24-1. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
RTC_X1_PAD	I,O	No	**Crystal Input 1:** This signal is connected to the 32.768 KHz crystal (Max 50K ESR). If using an external oscillator, the RTCX1 Vih must be within the range of 0.8V to 1.5V (1.5V max).
RTC_X2_PAD	I,O	No	**Crystal Input 2:** This signal is connected to the 32.768 KHz crystal (Max 50K ESR). If using an external oscillator, RTCX2 should be left floating.
BVCCRTC_EXTPAD	I,O	No	**Internal VRM Filter:** Connect filter capacitor between this signal and ground.
COREPWROK	I	No	**Core Power OK:** When asserted, this active-high input signal indicates that all of the platform board Voltage Regulators (VRs) supplying the SoC core power rails have been stable for at least 10 ms. COREPWROK can be driven asynchronously. When COREPWROK is de-asserted, the SoC asynchronously asserts the active-low PMU_PLTRST_N signal.
INTRUDER_N	I	No	**Intruder Detect:** This signal can be used to disable the system if the box is detected open.
RSMRST_N	I	No	**Resume (SUS Power Well) Reset**: When asserted by the platform board, this active-low input signal resets the SoC SUS Power Well. An external RC circuit is required to guarantee that the SUS well power (VNN, 1.05V, 1.8V, and 3.3V) is valid for a minimum time prior to RSMRST_N signal going high (See Figure 33-1).
RTEST_N	I	No	**RTC Battery Test:** An external RC circuit creates a time delay for the signal such that it will go high (de-assert) sometime after the battery voltage is valid. If the battery is missing/weak, this signal appears low (asserted) at boot just after the suspend power rail (V3P3) is up since it will not have time to meet Vih when V3P3A is high. Upon booting, BIOS should recognize that RTCRCT# was asserted and clear CMOS RAM. ***Note:*** Unless CMOS is being cleared (only to be done in the G3 power state) or the battery is low, the signal input must always be high when all other RTC power planes are on.
SRTCRST_N	I	No	**RTC Reset:** An external RC circuit creates a time delay for the signal such that it will go high (de-assert) sometime after the battery voltage is valid. When asserted, this signal resets all register bits in the RTC well. ***Notes:*** 1. Unless registers are being cleared (only to be done in the G3 power state), the signal input must always be high when all other RTC power planes are on. 2. In the case where the RTC battery is dead or missing on the platform, the signal should go high (de-asserted) before the RSMRST_N signal goes high (de-asserted).

24.2 Feature List

- Maintaining power on VCCRTC_3P3_G3 (pin AU48) to the RTC when in the G3 state (e.g., coin-cell battery implementation) is optional.
- Legacy RTC features.

24.3 Architectural Overview

The Real Time Clock (RTC) module provides a battery backed-up date and time keeping device with two banks of static RAM with 128 bytes each, although the first bank has 114 bytes for general-purpose usage.

Three interrupt features are available:

- Time-of-day alarm with once-a-second to once-a-month range
- Periodic rates of 122 µs to 500 ms
- End-of-update cycle notification

Seconds, minutes, hours, days, day of week, month, and year are counted. Daylight savings compensation is optional. The hour is represented in twelve or twenty-four hour format and data can be represented in binary-coded decimal BCD or binary format.

The design is meant to be functionally compatible with the Motorola MS146818B. The time keeping comes from a 32.768 kHz oscillating source, which is divided to achieve an update every second. The RTC clock is not subject to any internal clock gating.

The lower 14 bytes of the lower static RAM block have very specific functions. The first ten are for time and date information. The next four (0Ah to 0Dh) are registers, which configure and report RTC functions.

The time and calendar data should match the data mode (BCD or binary) and hour mode (12 or 24 hour) as selected in register B. The programmer MUST make sure that data stored in these registers within the reasonable values ranges and represents a possible date and time. The exception to these ranges is to store a value of C0 - FF in the Alarm bytes to indicate a “don’t care” situation.

All Alarm conditions must match in order to trigger an Alarm Flag, which also triggers an Alarm Interrupt if enabled. The SET bit in register B should be 1 while programming these locations to avoid clashes with update cycles.

Access to time and date information is done through the static RAM locations. If a static-RAM read from the ten time and date bytes is attempted during an update cycle, the value read will not necessarily represent the true contents of those locations. Any static-RAM writes under the same conditions will be ignored.

Note: The leap year determination that adds a 29th day to the month of February does not take into account the end-of-the-century exceptions. The logic simply assumes that all years divisible by four are leap years. According to the Royal Observatory Greenwich, years that are divisible by 100 are typically not leap years. In every fourth century (years divisible by 400, like 2000), the 100-year-exception is over-ridden and a leap-year occurs. Note that the year 2100 will be the first time in which the current RTC implementation would incorrectly calculate the leap-year.

Note: The term RSMRST_N used within this chapter includes both the CF9h (in I/O Space) software-generated hardware reset and the RSMRST_N signal pin.

24.4 I/O Registers

The RTC internal registers and its static RAM are organized as two banks of 128 bytes each, called the Standard Bank and the Extended Bank:

- The first 14 bytes of the Standard Bank contain the RTC time and date information along with four registers: A; B; C; D. These four registers are used for configuration of the RTC but not physically exist in the static RAM.
- The Extended Bank, also called the "upper 128-byte bank," contains a full 128 bytes of battery-backed static RAM, and is accessible even when the RTC module is disabled via the RTC configuration register.

Table 24-2. RTC Standard and Extended Static RAM Banks

Index (hex)	Register Short Name	Register Long Name
Standard Bank		
00	Sec	Seconds
01	Sec_Alarm	Seconds Alarm
02	Minutes	Minutes
03	Minutes_Alarm	Minutes Alarm
04	Hours	Hours
05	Hours_Alarm	Hours Alarm
06	Day_of_Week	Day of Week
07	Day_of_Month	Day of Month
08	Month	Month
09	Year	Year
0A	Register_A	Register A
0B	Register_B	Register B - General Configuration
0C	Register_C	Register C - Flag Register
0D	Register_D	Register D - Flag Register
0E - 7F	114 Bytes of User RAM	
Extended Bank		
00 - 7F	128 Bytes of User RAM	

The two banks are accessible using an index mechanism. All data movement between the host CPU and the Real-Time Clock is done through registers mapped to Host Root I/O Space. The I/O register map appears below in Table 24-4, "Fixed-Address I/O-Mapped Registers".

The simplest way of reading the RTC registers is to:

- Use register pair located at I/O locations 74h and 75h to access the Standard Bank.
- Use register pair located at I/O locations 72h and 73h to access the Extended Bank.

24.4.1 Alternate-Access Mode

The NMI Enable bit located at I/O Port location 70h, bit 7, is best accessed ONLY when the chipset is put into Alternate-Access Mode. This guarantees successful read and write cycles regardless of the settings of the other registers. Alternate-Access Mode is enabled by setting Alternate Access Mode Enable (AME), bit 17 of the 32-bit General Interrupt Control (GIC) register in relocatable Memory Space at offset D0_31FCh from SBREG_BAR. When AME is set, read-only registers can be written, and write-only registers can be read.

24.5 Update Cycles

An Update Cycle occurs once a second if the SET bit of register B is not asserted and the divide chain is properly configured. During this procedure:

- the stored time and date will be incremented
- overflow will be checked
- a matching alarm condition will be checked
- the time and date will be rewritten to the static RAM locations.

The Update Cycle starts at least 488 µs after the UIP bit of register A is asserted. The entire cycle takes no more than 1984 µs to complete. The time and date static RAM locations (0-9) are disconnected from the external access bus during this time.

To avoid update and data corruption conditions, external static RAM access to these locations can safely occur upon the detection of either of two conditions:

- When an updated-ended interrupt is detected, almost 999 ms is available to read and write the valid time and date data.
- If the UIP bit of Register A is detected to be low, there is at least 488 µs before the update cycle begins.

Warning: The overflow conditions for leap years and daylight savings adjustments are based on more than one date or time item. To ensure proper operation when adjusting the time, the new time and data values should be set at least two seconds before one of these conditions (leap year, daylight savings time adjustments) occurs.

24.6 Interrupts

The real-time clock interrupt is internally routed to the I/O APIC or the 8259. It is mapped to interrupt vector 8. This interrupt is not shared with any other interrupt. IRQ8# from the Serialized Interrupt (SERIRQ) stream is ignored. However, the High Performance Event Timers (HPET) can also be mapped to IRQ8#. In this latter case, the RTC interrupt is blocked.

24.7 Lockable RAM Ranges

The RTCs battery-backed static RAM supports an 8-byte range (index 38h through 3Fh) for the Standard Bank and also one for the Extended Bank which can be locked via the RTC Configuration (RC) register. If the locking bit is set, the corresponding range in the static RAM bank will not be readable or writable. A write cycle to those locations has no effect. A read cycle to those locations will not return the location's actual value (the value is undefined).

Once a range is locked, the range can be unlocked only by a hard reset, which will invoke the UEFI IA Firmware and allow it to re-lock the static RAM range.

24.8 Month and Year Alarms

These functions are not implemented in the SoC.

24.9 Register Map

Table 24-2 shows how the RTC registers map to Host Root Space.

Figure 24-2. Register Map



24.9.1 PCI Configuration and Capabilities

There are no RTC registers in Host Root Configuration Space.

24.9.2 Memory-Mapped Registers

Table 24-3. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
SBREG_BAR	D0_31FC	GIC	General Interrupt Control
SBREG_BAR	D1_3400	RC	RTC Configuration
SBREG_BAR	D1_3414	BUC	Backed Up Control
SBREG_BAR	D1_3F04	UIPSMI	RTC Update In Progress SMI Control
SBREG_BAR	D1_3418	RTCDCG	RTC Dynamic Clock Gating Control

24.9.3 I/O-Mapped Registers

Table 24-4. Fixed-Address I/O-Mapped Registers

I/O Locations (hex)	When Upper 128 Byte Enable (UE)[1] = 0	Function
70h and 74h	Also alias to 72h and 76h	Real-Time Clock (Standard RAM) Index Register ***Note:*** Writes to 72h, 74h, and 76h do not affect the NMI Enable bit (bit 7 of 70h)
71h and 75h	Also alias to 73h and 77h	Real-Time Clock (Standard RAM) Target Register
72h and 76h		Extended RAM Index Register (if enabled)
73h and 77h		Extended RAM Target Register (if enabled)

1. The Upper 128 Byte Enable (UE) register is bit 2 of the RTC Configuration (RC) register located in Host Root Memory Space at SBREG_BAR, offset D1_3400h.

§ §

25 High Precision Event Timer (HPET)

This chapter describes the High Precision Event Timer (HPET). One HPET Timer Block is provided which consists of a single counter that feeds eight comparators called Timer 0 through Timer 7. It is based on the *IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a*.

Figure 25-1. What is Covered in This Chapter



Table 25-1. References

Reference	Revision	Date	Document Title
Intel HPET Specification	1.0a	October 2004	*IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a*

25.1 Signal Descriptions

There are no signal pins or signal names associated with this chapter.

25.2 Feature List

- The Time to Next Timer Event (TNTE) is conveyed internally from the HPET to the SoC Power Management Controller (PMC).
- HPET uses all 64-bit data as it allows two DW (QW) Register Write Access and Read Access.
- The HPET circuitry uses an internally-generated 24-MHz clock.

25.3 Architectural Overview

This function provides a set of timers that can be used by the operating system. The timers are defined such that the operating system may assign specific timers to be used directly by specific applications. Each timer can be configured to cause a separate interrupt.

The SoC provides eight timers. The timers are implemented as a single counter, and each timer has its own comparator and value register. The counter increases monotonically. Each individual timer can generate an interrupt when the value in its value register matches the value in the main counter. See Figure 25-2.

Timer 0 supports Periodic Interrupts.

Figure 25-2. HPET Counter and Timers



The registers associated with these timers are mapped to a range of fixed addresses in Host Root memory space. The UEFI IA Firmware (also known as BIOS) reports to the operating system the location of the register space via ACPI. The hardware can support an assignable decode space; however, UEFI IA Firmware sets this space to start at memory address 0xFED0_0000 prior to handing it over to the operating system. It is not expected that the operating system will move the location of these timers once it is set by UEFI IA Firmware.

25.3.1 Timer Accuracy

The timers are accurate over any 1-ms period to within 0.05% of the time specified in the timer resolution fields.

Within any 100-microsecond period, the timer reports a time that is up to two ticks too early or too late. Each tick is less than or equal to 100 ns; this represents an error of less than 0.2%.

The timer is monotonic. It does not return the same value on two consecutive reads unless the counter has rolled over and reached the same value.

The HPET main counter uses an internally-generated 24-MHz clock that is generated from the SoC 25-MHz crystal (ISCLK). The accuracy of the main counter is as accurate as the 25-MHz crystal that is used in the system. The HPET main counter increments in femtoseconds (10^{-15} seconds). The internal 24-MHz clock has a period of 41,666,667 femtoseconds.

Note: Since the SoC does not support the processor C11 power state, the 32-kHz RTC clock is not used by the HPET circuitry.

25.3.2 Timer Off-Load

The HPET Timer Off-Load feature is not available with the SoC.

25.3.3 Interrupt Mapping

The interrupts associated with the various timers have several interrupt-mapping options.

Software should mask interrupts prior to clearing the LEG_RT_CNF bit. When reprogramming the HPET interrupt routing scheme, the LEG_RT_CNF bit of the General Configuration (GEN_CFG) Register, a spurious interrupt may occur. This is because the other source of the interrupt (the SoC 8254 Timer) may be asserted.

25.3.3.1 Mapping Option #1 (Legacy Replacement Option)

In this case, the Legacy Replacement Rout (LEG_RT_CNF) bit of the General Configuration (GEN_CFG) Register is set. This forces the mapping found in Table 25-2.

Table 25-2. Legacy Replacement Routing

Timer	8259 Mapping	APIC Mapping	Comment
0	IRQ0	IRQ2	In this case, the 8254 Timer will not cause any interrupts
1	IRQ8	IRQ8	In this case, the RTC will not cause any interrupts.
2 and 3	Per IRQ Routing Field.	Per IRQ Routing Field	
4, 5, 6, 7	not available	not available	

Note: The Legacy Option does not preclude delivery of IRQ0/IRQ8 using processor interrupts messages.

25.3.3.2 Mapping Option #2 (Standard Option)

In this case, the Legacy Replacement Rout (LEG_RT_CNF) bit of the of the General Configuration (GEN_CFG) Register is 0. Each timer has its own routing control. The interrupts can be routed to various interrupts of the 8259 PIC or IOxAPIC. A capabilities field indicates which interrupts are valid options for routing. If a timer is set for edge-triggered mode, the timers should not be shared with any legacy interrupts.

For the SoC, the only supported interrupt values are as follows:

- Timer 0 and 1: IRQ20, 21, 22, and 23 (I/O APIC only).
- Timer 2: IRQ11 (8259 or I/O APIC) and IRQ20, 21, 22, and 23 (I/O APIC only).
- Timer 3: IRQ12 (8259 or I/O APIC) and IRQ 20, 21, 22, and 23 (I/O APIC only).

Note: Interrupts from Timers 4, 5, 6, and 7 can only be delivered using processor message interrupts.

25.3.3.3 Mapping Option #3 (Processor Message Option)

Here the interrupts are mapped directly to processor messages, also called FSB Interrupt Messages, without going to the 8259 PIC or IOxAPIC. To use this mode, the interrupt must be configured to edge-triggered mode. The TIMERn_FSB_EN_CNF bit of the Timer n Configuration and Capabilities (TMR0_CNF_CAP for example) Register must be set to enable this mode.

Software configures where the 32-bit message is written within memory-mapped space. Each of the eight timers has a 64-bit "Timer n FSB Interrupt Rout Register" (TMR0_FSB_INT_ROUT for example) for the 32-bit message address and the 32-bit message data.

Note: The processor message interrupt delivery option has HIGHER priority and is mutually exclusive to the standard interrupt delivery option. Thus, if the TIMERn_FSB_EN_CNF bit is set, the interrupts will be delivered directly to the processor, rather than by means of the APIC or 8259 PIC.

The processor message interrupt delivery can be used even when the legacy mapping is used.

25.3.4 Periodic Versus Non-Periodic Modes

25.3.4.1 Non-Periodic (One-Shot) Mode

This mode change can be thought of as creating a one-shot timer.

Timer 0 is configurable to 32- (default) or 64-bit mode, whereas Timers 1 through timer 7 only support 32-bit mode. All of the timers support Non-Periodic Mode. For details of this mode, see Section 2.3.9.2.1 of the *IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a*.

Warning: Software must be careful when programming the comparator registers. If the value written to the register is not sufficiently far in the future, then the counter may pass the value before it reaches the register and the interrupt will be missed. The UEFI IA Firmware should pass a data structure to the operating system to indicate that the operating system should not attempt to program the periodic timer to a rate faster than 5 microseconds.

25.3.4.2 Periodic Mode

Timer 0 is the only timer that supports Periodic Mode. For details of this mode, see Section 2.3.9.2.2 of the *IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a*.

If the software resets the main counter, the value in the comparator's value register needs to reset as well. This can be done by setting TIMER0_VAL_SET_CNF, bit 6 of the Timer 0 Configuration and Capabilities (TMR0_CNF_CAP) Register. Again, to avoid race conditions, this should be done with the main counter halted. The following usage model is expected:

1. Software clears the ENABLE_CNF, bit 0 of the General Configuration (GEN_CFG) Register, to prevent any interrupts.
2. Software Clears the main counter by writing a value of 00h to it.
3. Software sets the TIMER0_VAL_SET_CNF bit.
4. Software writes the new value in the TIMER0_COMPARATOR_VAL register.
5. Software sets the ENABLE_CNF bit to enable interrupts.

The Timer 0 Comparator Value register cannot be programmed reliably by a single 64-bit write in a 32-bit environment, except if only the periodic rate is being changed during run-time. If the actual Timer 0 Comparator Value needs to be reinitialized, then the following software solution will always work, regardless of the environment:

1. Set TIMER0_VAL_SET_CNF bit.
2. Set the lower 32 bits of the Timer0 Comparator Value register.
3. Set TIMER0_VAL_SET_CNF bit.
4. Set the upper 32 bits of the Timer0 Comparator Value register.

25.3.5 Enabling the Timers

The UEFI IA Firmware or operating system Plug and Play (PnP) code should route the interrupts. This includes the Legacy Replacement Rout bit, Interrupt Rout bit (for each timer), and interrupt type (to select the edge or level type for each timer).

The Device Driver code should do the following for an available timer:

1. Set the Overall Enable bit (ENABLE_CNF), bit 0 of the General Configuration (GEN_CFG) Register.

If Timer 0 is being set up, program the Timer 0 Type field, bit 3 of the Timer 0 Configuration and Capabilities (TMR0_CNF_CAP) Register, to either Periodic Mode or Non-Periodic Mode.

2. Set the interrupt enable.
3. Set the comparator value.

25.3.6 Interrupt Levels

Interrupts directed to the internal 8259 PIC are active high. See Chapter 21, "PIC and I/O APIC Controllers" for information regarding the programming the polarity of 8259 PIC for detecting internal interrupts.

If the interrupts are mapped to the 8259 or I/O APIC and set for level-triggered mode, they can be shared with legacy interrupts. They may be shared although it is unlikely for the operating system to attempt to do this.

If more than one timer is configured to share the same IRQ using the TIMERn_INT_ROUT_CNF fields of the Timer n Configuration and Capabilities (TMR0_CNF_CAP for example) Register, then the software must configure the timers to level- triggered mode. Edge-triggered interrupts cannot be shared.

25.3.7 Handling Interrupts

Section 2.4.6 of the *IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a* describes handling interrupts.

25.3.8 Issues Related to 64-Bit Timers with 32-Bit Processors

Section 2.4.7 of the *IA-PC HPET (High Precision Event Timers) Specification Revision 1.0a* describes issues related to 64-Bit timers with 32-Bit processors.

25.4 Register Map

Figure 25-3 shows the associated registers from a system software viewpoint.

Figure 25-3. Register Map



25.4.1 Memory-Mapped Registers

Note: The base memory address for the HPET registers is determined by the High Performance Event Timer Configuration (HPTC) register in configuration space at offset 60h of the P2SB Bridge (Bus 0, Device 31, Function 1). See Figure 25-3. Even though UEFI IA Firmware can configure the HPET timers to be located at one of four locations in memory space, only the location starting with 0xFED0_0000 is validated by Intel. The other three memory locations are not documented in this document.

Table 25-3. Fixed-Address Memory-Mapped Registers (Sheet 1 of 2)

Fixed Address in Memory Space	64-bit Register Short Name	64-bit Register Long Name
0xFED00000	GEN_CAP_ID	General Capabilities and ID Register
0xFED00008	*Reserved*	*Reserved*
0xFED00010	GEN_CFG	General Configuration Register
0xFED00018	*Reserved*	*Reserved*
0xFED00020	GEN_INT_STS	General Interrupt Status Register
0xFED00028 through 0xFED000E8	*Reserved*	*Reserved*
0xFED000F0	MAIN_CNTR	Main Counter Value
0xFED000F8	*Reserved*	*Reserved*
0xFED00100	TMR0_CNF_CAP	Timer 0 Configuration and Capabilities
0xFED00108	TMR0_CMP_VAL	Timer 0 Comparator Value
0xFED00110	TMR0_FSB_INT_ROUT	Timer 0 FSB Interrupt Rout Register
0xFED00118	*Reserved*	*Reserved*
0xFED00120	TMR1_CNF_CAP	Timer 1 Configuration and Capabilities
0xFED00128	TMR1_CMP_VAL	Timer 1 Comparator Value
0xFED00130	TMR1_FSB_INT_ROUT	Timer 1 FSB Interrupt Rout Register
0xFED00138	*Reserved*	*Reserved*
0xFED00140	TMR2_CNF_CAP	Timer 2 Configuration and Capabilities
0xFED00148	TMR2_CMP_VAL	Timer 2 Comparator Value
0xFED00150	TMR2_FSB_INT_ROUT	Timer 2 FSB Interrupt Rout Register
0xFED00158	*Reserved*	*Reserved*
0xFED00160	TMR3_CNF_CAP	Timer 3 Configuration and Capabilities
0xFED00168	TMR3_CMP_VAL	Timer 3 Comparator Value
0xFED00170	TMR3_FSB_INT_ROUT	Timer 3 FSB Interrupt Rout Register
0xFED00178	*Reserved*	*Reserved*
0xFED00180	TMR4_CNF_CAP	Timer 4 Configuration and Capabilities
0xFED00188	TMR4_CMP_VAL	Timer 4 Comparator Value
0xFED00190	TMR4_FSB_INT_ROUT	Timer 4 FSB Interrupt Rout Register
0xFED00198	*Reserved*	*Reserved*
0xFED001A0	TMR5_CNF_CAP	Timer 5 Configuration and Capabilities
0xFED001A8	TMR5_CMP_VAL	Timer 5 Comparator Value
0xFED001B0	TMR5_FSB_INT_ROUT	Timer 5 FSB Interrupt Rout Register
0xFED001B8	*Reserved*	*Reserved*

Table 25-3. Fixed-Address Memory-Mapped Registers (Sheet 2 of 2)

Fixed Address in Memory Space	64-bit Register Short Name	64-bit Register Long Name
0xFED001C0	TMR6_CNF_CAP	Timer 6 Configuration and Capabilities
0xFED001C8	TMR6_CMP_VAL	Timer 6 Comparator Value
0xFED001D0	TMR6_FSB_INT_ROUT	Timer 6 FSB Interrupt Rout Register
0xFED001D8	*Reserved*	*Reserved*
0xFED001E0	TMR7_CNF_CAP	Timer 7 Configuration and Capabilities
0xFED001E8	TMR7_CMP_VAL	Timer 7 Comparator Value
0xFED001F0	TMR7_FSB_INT_ROUT	Timer 7 FSB Interrupt Rout Register
0xFED001F8 through 0xFED003F8	*Reserved*	*Reserved*

§ §

26 Customer General-Purpose I/O (GPIO)

A number of SoC signal pins have shared, native functions. These signals are called Configurable Flexible I/O (CFIO) signals. If the default setting is not needed for the customer board design, one of the other shared, native signals can be configured for the pin. The silicon pad connected to each CFIO signal pin contains a signal selector (also called MUX) that can be programmed. Of the SoC CFIO signal pins, the SoC provides 147 General-Purpose I/O (GPIO) signals that can be used by the SoC customer. These special CFIO signals are called Customer GPIOs. For example, the GPIO125 default function mode is eMMC clock. See details in Table 39-1, "Signal Pin Name Directory - Sorted by Name" on page 995.

- GPIO registers are accessible by the Host or IE through their MMIO space, using the P2SB (Primary to Sideband Bridge) (B:0 D:31 F:1) SBREG contents as the base address.
- NMI and SMI are capable only on selected GPIOs.
- SCI (GPE) and IOxAPIC interrupt are capable on all GPIOs.
- The Intel® ME assigns ownership of individual GPIO pads. The Intel® ME assigns ownership of individual GPIO pads to the HOST or IE or Intel® ME.
- Legacy I/O space control of GPIOs is not supported

Figure 26-1. What is Covered in This Chapter



26.1 GPIO Ball and Signal Names

The term "pad" is used in the register descriptions of the SoC. The pad is located on the SoC silicon. The signal is wired to a pin (a.k.a., ball) on the product package. The SoC pad control registers refer to the silicon pads, but in essence they apply to the signal at the pin. This chapter uses "pad" and "pin" interchangeably.

Table 26-1, "GPIO Ball and Pad Name" shows GPIO ball mapping to the signal names. The table is an extension to Table 39-1, "Signal Pin Name Directory - Sorted by Name" on page 995.

Table 26-1. GPIO Ball and Pad Name (Sheet 1 of 5)

Number	Ball/Pin	Ball/Pin Name	Notes
0	BF70	GPIO[0]	
1	BK69	GPIO[1]	
2	BK71	GPIO[2]	
3	BN44	GPIO[3]	
4	BH50	GPIO[4]	
5	BL48	GPIO[5]	
6	BE52	GPIO[6]	
7	BH46	GPIO[7]	
8	BY55	GPIO[8]	
9	CA54	GPIO[9]	
10	CA63	ESPI_CS_N[1]	
11	BY62	ESPI_ALRT_N[1]	
12	BN56	GPIO[12]	
13	BN66	SMB_LAN_ALRT_N	
14	AV66	LAN0_PORT0_SDP[0]	
15	AY66	LAN0_PORT1_SDP[0]	
16	BA71	LAN0_PORT0_SDP[1]	
17	BB72	LAN0_PORT1_SDP[1]	
18	AC59	LAN0_PORT0_SDP[2]	
19	AU65	LAN0_PORT1_SDP[2]	
20	BA69	LAN0_PORT0_SDP[3]	
21	W58	LAN0_PORT1_SDP[3]	
22	AY70	LAN1_PORT0_LED[0]	
23	AY72	LAN1_PORT0_LED[1]	
24	AV59	LAN0_PORT0_I2C_CLK	
25	AV56	LAN0_PORT0_I2C_DATA	
26	BB66	LAN0_PORT1_I2C_CLK	
27	BC69	LAN0_PORT1_I2C_DATA	
28	AY59	NCSI_RXD[0]	
29	AY63	NCSI_CLK_IN	
30	BD72	NCSI_RXD[1]	
31	BD65	NCSI_CRS_DV	

Table 26-1. GPIO Ball and Pad Name (Sheet 2 of 5)

Number	Ball/Pin	Ball/Pin Name	Notes
32	AU58	NCSI_ARB_IN	
33	BD70	NCSI_TX_EN	
34	BE66	NCSI_TXD[0]	
35	AL56	NCSI_TXD[1]	
36	AV63	NCSI_ARB_OUT	
37	BE69	LAN0_PORT0_LED[0]	
38	BF72	LAN0_PORT0_LED[1]	
39	BA65	LAN0_PORT1_LED[0]	
40	BG66	LAN0_PORT1_LED[1]	
41	AP56	PCIE_CLKREQ_N[0]	
42	BA58	PCIE_CLKREQ_N[1]	
43	BH71	PCIE_CLKREQ_N[2]	
44	BJ66	PCIE_CLKREQ_N[3]	
45	BD61	PCIE_CLKREQ_N[4]	
46	n/a	n/a	
47	BA54	SVID_ALERT_N	SVID Pads
48	BE56	SVID_DATA	
49	BE59	SVID_CLK	
50	BA61	THERMTRIP_N	TM Pads
51	BM71	PROCHOT_N	
52	BL70	MEMHOT_N	
53	AY56	DFX_PORT_CLK[0]	DFX Set2 Pads
54	BB70	DFX_PORT_CLK[1]	
55	BN68	DFX_PORT[0]	
56	BN70	DFX_PORT[1]	
57	BE63	DFX_PORT[2]	
58	BP69	DFX_PORT[3]	
59	BW68	DFX_PORT[4]	
60	BH69	DFX_PORT[5]	
61	BG63	DFX_PORT[6]	
62	BT69	DFX_PORT[7]	
63	BW67	DFX_PORT[8]	
64	BD58	ESPI_IO[0]	
65	BR67	ESPI_IO[1]	
66	BV64	ESPI_IO[2]	
67	BH65	ESPI_IO[3]	
68	BJ72	ESPI_CS_N[0]	
69	BY64	ESPI_CLK	
70	BV66	ESPI_RST_N	
71	BK61	ESPI_ALRT_N[0]	

Table 26-1. GPIO Ball and Pad Name (Sheet 3 of 5)

Number	Ball/Pin	Ball/Pin Name	Notes
72	BG65	SPI_CS_N[0]	
73	BL66	SPI_CS_N[1]	
74	BU63	SPI_MOSI_IO[0]	
75	BV62	SPI_MOSI_IO[1]	
76	BH61	SPI_IO[2]	
77	BW61	SPI_IO[3]	
78	CA61	SPI_CLK	
79	BH58	SUSPWRDNACK	
80	BG59	PMU_SUSCLK	
81	BV60	ADR_TRIGGER	
82	BW59	PMU_SLP_S45_N	
83	BK65	PMU_SLP_S3_N	
84	BR61	PMU_WAKE_N	
85	CA59	PMU_PWRBTN_N	
86	BL59	PMU_RESETBUTTON_N	
87	BL63	PMU_PLTRST_N	
88	BV58	SUS_STAT_N	
89	BY58	RSVD_BY58	
90	BR65	SATA0_LED_N	
91	BV55	SATA1_LED_N	
92	CA57	SATA_PDETECT[0]	
93	BN63	SATA_PDETECT[1]	
94	BU57	SATA0_SDOUT	
95	BW54	SATA1_SDOUT	
96	BV53	UART1_RXD	
97	BN59	UART1_TXD	
98	BW52	PCIE_CLKREQ_N[5]	
99	BV51	PCIE_CLKREQ_N[6]	
100	BK58	PCIE_CLKREQ_N[7]	
101	BL56	UART0_RXD	
102	CA52	UART0_TXD	
103	BH54	SMB_LAN_CLK	
104	BK54	SMB_LAN_DATA	
105	CA50	ERROR_N[2]	
106	BR58	ERROR_N[1]	
107	BL52	ERROR_N[0]	
108	BW50	IERR_N	
109	BN52	MCERR_N	
110	BY51	SMB_LEG_CLK	
111	BV49	SMB_LEG_DATA	

Table 26-1. GPIO Ball and Pad Name (Sheet 4 of 5)

Number	Ball/Pin	Ball/Pin Name	Notes
112	BW48	SMB_LEG_ALRT_N	
113	BK50	SMB_HOST_DATA	
114	BR50	SMB_HOST_CLK	
115	BY49	SMB_PECI_DATA	
116	BR54	SMB_PECI_CLK	
117	BV47	SMB_ME_SMT0_DATA	
118	BR46	SMB_ME_SMT0_CLK	
119	BG52	SMB_ME_SMT0_ALRT_N	
120	BD54	USB_OC_N	
121	BG48	FLEX_CLK_SE[0]	
122	CA48	FLEX_CLK_SE[1]	
123	BN48	EMMC_CMD	
124	BL44	EMMC_STROBE	
125	BK46	EMMC_CLK	
126	BW45	EMMC_D[0]	
127	BV44	EMMC_D[1]	
128	BY44	EMMC_D[2]	
129	CA45	EMMC_D[3]	
130	BU43	EMMC_D[4]	
131	CA43	EMMC_D[5]	
132	BY42	EMMC_D[6]	
133	BV42	EMMC_D[7]	
134	AY52	DFX_PORT[9]	DFX Set2 Pads
135	BR42	DFX_PORT[10]	
136	BK42	DFX_PORT[11]	
137	BW41	DFX_PORT[12]	
138	BE48	DFX_PORT[13]	
139	CA41	DFX_PORT[14]	
140	BV40	DFX_PORT[15]	

Table 26-1. GPIO Ball and Pad Name (Sheet 5 of 5)

Number	Ball/Pin	Ball/Pin Name	Notes
141	N/A	N/A	DFX Set1 Pads
142	N/A	N/A	
143	N/A	N/A	
144	N/A	N/A	
145	N/A	N/A	
146	BY38	CX_PRDY_N	
147	BH42	CX_PREQ_N	
148	BE44	CTBTRIGINOUT	
149	CA39	CTBTRIGOUT	
150	BM38	GPIO[150]	
151	BW37	GPIO[151]	
152	CA37	GPIO[152]	

Note: There are four types of 1.05V pads:
- DFX Set1 pads
- DFX Set2 pads
- SVID pads
- Thermal Management (TM) pads

The 1.05V pads have different buffer impedance ranges.

26.2 Pad Description

When the signal function is a native function signal (not a GPIO function) the signal is set by the SoC at reset time to be default values. Later on, once BIOS starts, the BIOS can keep all the defaults or alter settings, and then lock all of the configuration registers to be RO (Read Only).

When the signal function is a GPIO mode, the shared-signal pad circuitry contains specific, internal controls including individual pin signal multiplexing, pull-up/pull-down values, pin states and output buffer type (e.g., open drain). See Figure 26-2 for internal pad circuitry. Not all GPIO modes support the pull-up, pull-down options (R1 and R2) shown in Figure 26-2.

See the PAD_CFG_DW1 register configuration options for each GPIO for details of what is supported.

Some of the shared pads are also hard pin straps and have additional pull-up/pull-down circuitry. See Section 4.1, "SoC Hard (Pin) Straps" on page 193.

Figure 26-2. Custom GPIO Circuit Definition



Note: The internal pull-up resistor option is not supported for 1.8V GPIOs. The internal pull-down resistor option is not supported for 3.3V GPIOs.

The interface power source (VCC) for each pad is fixed and can be one of the three voltage levels (1.05V, 1.8V, or 3.3V).

26.3 Signal Configuration Overview

Other than the signal pins mentioned in Chapter 10, "Flexible I/O Adapter (FIA) Overview", the SoC contains signal pins that are shared by more than one native function. They can also be programmed to be Customer GPIO signals.

All 152 of these pins power-up in the high-impedance state and remain in that state until the internal reset for the pin circuitry deasserts. The pins are reset to the default state during a Warm Reset or a Cold Reset (See Chapter 33, "Resets and Voltage Sequencing"). The shared-signal pins that default as output signals are designed to be glitch-free during power-up and reset. For shared-signal pins that by default are Customer GPIO input pins, an external pull-up or pull-down resistor must be used to keep the SoC receiver from triggering an interrupt or event during the internal reset and when the reset is de-asserted.

In many cases, the customer platform design requires an SoC native signal that shares a pin with other SoC native signals. If the desired signal has a Function number that is not the one designated as "Default" in the "Pin States" column of Table 39-1, "Signal Pin Name Directory - Sorted by Name" on page 995, the Pad Mode [2:0] bit field of the pin Pad Configuration DW0 control register (PAD_CFG_DW0) can be programmed to alter the Function number to the desired signal.

If none of the shared SoC native signals are needed by the platform, the customer can set the PAD_CFG_DW0 to Function = 0 (Pad Mode [2:0] = 000), which is always a "Customer GPIO" function.

For pins, the PAD_CFG_DW0 control register and the Pad Configuration DW1 control register (PAD_CFG_DW1), contain bit fields that are customer programmable; used to create the desired signal driver, receiver, and internal pull-up or pull-down termination. Some Customer GPIOs generate interrupts and trigger events.

26.3.1 Pad Ownership

The Pad Ownership registers designate whether the Host, Intel® ME, or IE has control of the pad. The Pad Ownership Register (PAD_OWN) uses a two bit code to indicate the ownership of pad.

00 = Host GPIO Mode
01 = Intel® ME GPIO Mode
10 = Reserved
11 = IE GPIO Mode

When a Customer GPIO is programmed to generate an interrupt to the PIC or IOxAPIC, the GPIO Host Mode is also set to either Host GPIO ACPI Mode or GPIO Driver Mode. This is indicated by the Host Software Pad Ownership (HOSTSW_OWN) Register 1-bit code.

0 = GPIO ACPI Mode
1 = GPIO Driver Mode

Note:

1. All detail description about the Pad in this chapter is focused on Host GPIO Mode.
2. When the Pad is set as ME GPIO Mode, Intel® ME owns the Pad and controls the Pad. No customization is doable from the customer point of view.
3. When the Pad is set as IE GPIO Mode, the IE owns the Pad.

The BIOS default code does not allow all GPIOs to be reassigned to an IE. Most pins have a native function that prevents assignment to IE as a true GPIO. Please see Table 26-2 for details.

Table 26-2. Pin Name Descriptions

Pin Name	Usage Description
GPIO[3]	No native functions assigned; pure GPIO only
GPIO[5], GPIO[6], GPIO[7]	Native functions all belong to IE; IE can tradeoff internal features vs pure GPIO
SMB4_CSME0_DATA, SMB4_CSME0_CLK	Native functions shared by IE and ME; can tradeoff their relative features vs pure GPIO
PCIE_CLKREQ0_N, PCIE_CLKREQ1_N, PCIE_CLKREQ2_N, PCIE_CLKREQ3_N	Native functions shared with PCIe CLKREQ—can allocate some for IE GPIO if platform doesn't require so many CLKREQ
GPIO[10], GPIO[11]	Available
GPIO[12]	Available if not using TPM
GPIO[0], GPIO[1], GPIO[2], GPIO[4], GPIO[8], GPIO[9]	Can be GPIO by IE by turning off the features

Note: For ME recovery mode, SPS FW is able to use any SoC GPIO pin to configure Recover_Jumper mode by using Intel SPS Flash Image Tool (spsFITc.exe). For guidance of configuration, please refer to Tools for Intel Server Platform Service Firmware 4.0 User Guide in SPS release package.

26.3.2 Pad Multiplex Function

The Pad is set as GPIO mode (GPIO ACPI Mode / GPIO Driver Mode) or native function mode, through the Pad Configuration DW0 (PAD_CFG_DW0) register bit [12:10] (Pad Mode).

- 000 = GPIO Controller controls the Pad
- 001 = Native Function 1
- 010 = Native Function 2
- 011 = Native Function 3
- 100 = Native Function 4
- ...through
- 111 = Native Function 7

When the PAD is dedicated GPIO only, the PAD_CFG-DW0 bit [12:10] is all 000.

When the Pad Mode (PMode) is 0, the GPIO controller has the ability to control the RX/TX Disable and RX/TX State through the PAD_CFG_DW0 register bit [9:8] (GPIO RX/TX Disable) and bit[1:0] (GPIO RX/TX State). The pad is either an input or an output signal with different configurations.

When the PMode is not equal to 0, the corresponding GPIO works as the native function mode. The default value of the Pad Mode (PMode) field, also called the signal function value, is assigned when the SoC is reset.

26.3.3 Pad Internal Pull-up / Pull-down Configure

The pad has internal weak pull up/down termination which is controlled by register PAD_CFG_DW1 bit [13:10] (TERM). It is expected software/FW/BIOS shall program the termination settings appropriately. Some common sequences are:

1. Termination settings must be programmed before changing a pad from output to input to avoid the pad state “floating” momentarily.
2. If a given pad is configured as an output, termination must be enabled until the TXDATA is driven properly, to avoid pad state “floating”. This means the TX enable configuration has to be enabled in order to enable the TX buffer before termination is released.

26.3.4 Pad Configuration Logical Control Summary

The pad is configured as an input signal or an output signal, including an open drain output signal. When the signal is set as a Customer GPIO function Table 26-3 through Table 26-5 show how to configure the signal to be input or output.

Figure 26-3. GPIO Logic Overview Diagram



Table 26-3. Input Signal Configuration

Pad	GPIORXDIS	GPIOTXDIS	TERM	GPIORXSTATE	GPIOTXSTATE
0	0	1	0000	0	X
1	0	1	0000	1	X

Table 26-4. Output Signal Configuration

Pad	GPIORXDIS	GPIOTXDIS	TERM	GPIORXSTATE	GPIOTXSTATE
0*	1	0	0000	0	0
1*	1	0	0000	0	1
Hi-Z*	1	1	0000	0	0
Hi-Z	1	0	0000	0	0
0	1	1	0010/0100	0	0
1	1	1	1010/1100	0	0
* Open Drain Output Signal Configuration.					

26.3.5 Non-Maskable Interrupt (NMI)

When a Customer GPIO is customer-configured to be an input, an NMI can be generated by following programming steps:

1. Set Host Ownership - PAD_OWN[1:0] = '00'.
2. Set GPIO ACPI Mode - HOSTSW_OWN = '0'.
3. Set GPIO Input Mode – PAD_CFG_DW0 [12:10] = '000'.
4. NMI Routing enabling - PAD_CFG_DW0 bit [17] (GPIRoutNMI) = '1'.
5. GPI NMI Enable - GPI_NMI_EN = '1'.
6. GPI NMI Status - GPI_NMI_STS= '1'.

Note: Some GPIO signals do not support NMI. Please see detail in Table 26-5, "GPIO Pad Configuration Description".

26.3.6 System Management Interrupt (SMI)

When a Customer GPIO is customer-configured to be an input, an SMI can be generated by following programming steps:

1. Set Host Ownership - PAD_OWN[1:0]= '00'.
2. Set GPIO ACPI Mode - HOSTSW_OWN = '0'.
3. Set GPIO Input Mode – PAD_CFG_DW0 [12:10] = '000'.
4. SMI Routing enabling - PAD_CFG_DW0 bit [18] (GPIRoutSMI) = '1'.
5. GPI SMI Enable - GPI_SMI_EN = '1'.
6. GPI SMI Status - GPI_SMI_STS= '1'.

Note: Some GPIO signals do not support SMI. Please see detail in Table 26-5, "GPIO Pad Configuration Description".

26.3.7 System Control Interrupt (SCI)/General Purpose Event (GPE)

When a Customer GPIO is customer-configured to be an input, an SCI can be generated by following programming steps:

1. Set Host Ownership - PAD_OWN[1:0]= '00'.
2. Set GPIO ACPI Mode - HOSTSW_OWN = '0'.
3. Set GPIO Input Mode – PAD_CFG_DW0 [12:10] = '000'.
4. SCI/GPE Routing enabling - PAD_CFG_ DW0 bit [19] (GPIRoutSCI) = '1'.
5. GPI General Purpose Events Enable - GPI_GPE_EN = '1'.
6. GPI General Purpose Events Status - GPI_GPE_STS = '1'.

26.3.8 GPIO to IOxAPIC

When a Customer GPIO is customer-configured to be an input, a GPIO can directly send an interrupt to the IOxAPIC by following programming steps:

1. Set Host Ownership - PAD_OWN[1:0]= '00'.
2. Set GPIO ACPI Mode - HOSTSW_OWN = '0'.
3. Set GPIO Input Mode – PAD_CFG_DW0 [12:10] = '000'.
4. IOxAPIC Routing enabling - PAD_CFG_DW0 bit [20] (GPIRoutIOxAPIC) = '1'.
5. Specific IRQ Line Enable - PAD_CFG_DW1 bits [6:0] Interrupt Select (IntSel) = '0-119'.

Note: Each GPIO signal has a fixed Interrupt line. Please see detail in Table 27-8.

26.3.9 Legacy Interrupt Request (IRQ)

When a Customer GPIO is customer-configured to be an input, a Legacy IRQ can be generated by following programming steps:

1. Set Host Ownership - PAD_OWN[1:0]= '00'.
2. Set GPIO Driver Mode - HOSTSW_OWN = '1'.
3. Set GPIO Input Mode – PAD_CFG_DW0 [12:10] = '000'.
4. Miscellaneous Configuration Register - MISCCFG bit [3] (GPIO_DRIVER_IRQ_ROUTE) = '0' (IRQ14) or '1' (IRQ15).
5. GPI Interrupt Enable - GPI_INT_EN = '1'.
6. GPI Interrupt Status - GPI_INT_STS= '1'.

26.3.10 Pad Level/Edge Sensitive Detect Enable

The interrupt or wake triggering event for the input Customer GPIO are delivered to the GPIO controller as either Edge detected or Level detected by following program steps:

1. Set Host Ownership - PAD_OWN[1:0]= '00'.
2. Set GPIO Mode based on interrupt type.
3. Set GPIO Input Mode – PAD_CFG_DW0 [12:10] = '000'.
4. Select the polarity inversion stage - PAD_CFG_DW0 bit [23] (RXINV)
5. Enable RX Level/Edge configuration - PAD_CFG_DW0 two bits [26:25] (RXEVCFG).

The default uses Edge detection logic with no inversion.

26.4 Registers Lock Down

The intended use for the pad Configuration Lock (PADCFGLOCK), is for BIOS to lock down the registers related to the pad configuration. This is one-bit-per-pad to unlock/lock certain pad specific fields. After locking, the specific fields become Read-Only. BIOS can unlock PADCFGLOCK by sending opcode 0x13 to the individual GPIO community.

When PADCFGLOCK is written from "1" to "0" (unlock), a synchronous SMI# is generated when enabled. When the unlock is enabled, it cannot be disabled until PMU_PLRTST_N happens. This ensures that only the SMM code changes the register field settings after they are locked.

This configuration is meaningful and affects only the pad owned by the host - PAD_OWN[1:0]= '00'.

26.5 MMIO Address Access

All GPIO registers must be accessed through the Memory Mapped I/O (MMIO) space with the address offsets to SBREG_BAR (B:0 D:31 F:1).

The pad Control Register and Group Register field names identify the specific GPIO by its Pin Name as shown in Table 39-1, "Signal Pin Name Directory - Sorted by Name" on page 995. The Pin Name is used as the suffix of the register name. For example, the register PAD_CFG_DW0_GPIO_0 and the bit PAD_OWN_GPIO_0 for the pin named "*_GPIO_0" has part of the register name.

Note: The register name with the suffix shown in Table 26-5 is used by BIOS/FW for code development/register programming. Some register names have a different suffix name than the name of the pin. These are noted in Table 26-5.

Table 26-5. GPIO Pad Configuration Description (Sheet 1 of 5)

GPIO	Suffix of Pad Register Name	Pad Configuration DW0 Offset (hex)	Pad Configuration DW1 Offset (hex)	SMI/NMI Capability	IOxAPIC Interrupt INTSEL (hex)	Comment
14	*_GBE0_SDP0	C2_0400	C2_0404		18	1
15	*_GBE1_SDP0	C2_0408	C2_040C		19	1
16	*_GBE0_SDP1	C2_0410	C2_0414		1A	1
17	*_GBE1_SDP1	C2_0418	C2_041C		1B	1
18	*_GBE0_SDP2	C2_0420	C2_0424		1C	1, 2
19	*_GBE1_SDP2	C2_0428	C2_042C		1D	1
20	*_GBE0_SDP3	C2_0430	C2_0434		1E	1, 2
21	*_GBE1_SDP3	C2_0438	C2_043C		1F	1, 2
22	*_GBE2_LED0	C2_0440	C2_0444		20	1
23	*_GBE2_LED1	C2_0448	C2_044C		21	1
24	*_GBE0_I2C_CLK	C2_0450	C2_0454		22	1
25	*_GBE0_I2C_DATA	C2_0458	C2_045C		23	1, 2
26	*_GBE1_I2C_CLK	C2_0460	C2_0464		24	1
27	*_GBE1_I2C_DATA	C2_0468	C2_046C		25	1, 2
28	*_NCSI_RXD0	C2_0470	C2_0474		26	

1. The Ball/Pin Name is not same as the suffix of the pad's register name.
2. Until RSMRST_N de-asserts these signals are indeterminate.

Table 26-5. GPIO Pad Configuration Description (Sheet 2 of 5)

GPIO	Suffix of Pad Register Name	Pad Configuration DW0 Offset (hex)	Pad Configuration DW1 Offset (hex)	SMI/NMI Capability	IOxAPIC Interrupt INTSEL (hex)	Comment
29	*_NCSI_CLK_IN	C2_0478	C2_047C		27	
30	*_NCSI_RXD1	C2_0480	C2_0484		28	
31	*_NCSI_CRS_DV	C2_0488	C2_048C		29	
32	*_NCSI_ARB_IN	C2_0490	C2_0494		2A	2
33	*_NCSI_TX_EN	C2_0498	C2_049C		2B	
34	*_NCSI_TXD0	C2_04A0	C2_04A4		2C	2
35	*_NCSI_TXD1	C2_04A8	C2_04AC		2D	
36	*_NCSI_ARB_OUT	C2_04B0	C2_04B4		2E	2
37	*_GBE0_LED0	C2_04B8	C2_04BC		2F	1
38	*_GBE0_LED1	C2_04C0	C2_04C4		30	1
39	*_GBE1_LED0	C2_04C8	C2_04CC		31	1
40	*_GBE1_LED1	C2_04D0	C2_04D4		32	1
0	*_GPIO_0	C2_04D8	C2_04DC	Yes	33	
41	*_PCIE_CLKREQ0_N	C2_04E0	C2_04E4		34	2
42	*_PCIE_CLKREQ1_N	C2_04E8	C2_04EC		35	
43	*_PCIE_CLKREQ2_N	C2_04F0	C2_04F4		36	
44	*_PCIE_CLKREQ3_N	C2_04F8	C2_04FC		37	
45	*_PCIE_CLKREQ4_N	C2_0500	C2_0504		38	2
1	*_GPIO_1	C2_0508	C2_050C	Yes	39	2
2	*_GPIO_2	C2_0510	C2_0514	Yes	3A	2
47	*_SVID_ALERT_N	C2_0518	C2_051C		3B	
48	*_SVID_DATA	C2_0520	C2_0524		3C	
49	*_SVID_CLK	C2_0528	C2_052C		3D	
50	*_THERMTRIP_N	C2_0530	C2_0534		3E	
51	*_PROCHOT_N	C2_0538	C2_053C		3F	
52	*_MEMHOT_N	C2_0540	C2_0544		40	
53	*_DFX_PORT_CLK0	C5_0400	C5_0404		41	
54	*_DFX_PORT_CLK1	C5_0408	C5_040C		42	
55	*_DFX_PORT0	C5_0410	C5_0414		43	
56	*_DFX_PORT1	C5_0418	C5_041C		44	
57	*_DFX_PORT2	C5_0420	C5_0424		45	
58	*_DFX_PORT3	C5_0428	C5_042C		46	
59	*_DFX_PORT4	C5_0430	C5_0434		47	
60	*_DFX_PORT5	C5_0438	C5_043C		48	
61	*_DFX_PORT6	C5_0440	C5_0444		49	
62	*_DFX_PORT7	C5_0448	C5_044C		4A	
63	*_DFX_PORT8	C5_0450	C5_0454		4B	

1. The Ball/Pin Name is not same as the suffix of the pad's register name.
2. Until RSMRST_N de-asserts these signals are indeterminate.

Table 26-5. GPIO Pad Configuration Description (Sheet 3 of 5)

GPIO	Suffix of Pad Register Name	Pad Configuration DW0 Offset (hex)	Pad Configuration DW1 Offset (hex)	SMI/NMI Capability	IOxAPIC Interrupt INTSEL (hex)	Comment
134	*_DFX_PORT9	C5_0458	C5_045C		4C	
135	*_DFX_PORT10	C5_0460	C5_0464		4D	
136	*_DFX_PORT11	C5_0468	C5_046C		4E	
137	*_DFX_PORT12	C5_0470	C5_0474		4F	
138	*_DFX_PORT13	C5_0478	C5_047C		50	
139	*_DFX_PORT14	C5_0480	C5_0484		51	
140	*_DFX_PORT15	C5_0488	C5_048C		52	
12	*_GPIO_12	C5_0490	C5_0494	Yes	53	
13	*_SMB5_GBE_ALRT_N	C5_0498	C5_049C	Yes	54	1
98	*_PCIE_CLKREQ5_N	C5_04A0	C5_04A4	Yes	55	
99	*_PCIE_CLKREQ6_N	C5_04A8	C5_04AC		56	
100	*_PCIE_CLKREQ7_N	C5_04B0	C5_04B4		57	2
101	*_UART0_RXD	C5_04B8	C5_04BC	Yes	58	2
102	*_UART0_TXD	C5_04C0	C5_04C4	Yes	59	2
103	*_SMB5_GBE_CLK	C5_04C8	C5_04CC	Yes	5A	1, 2
104	*_SMB5_GBE_DATA	C5_04D0	C5_04D4		5B	1
105	*_ERROR2_N	C5_04D8	C5_04DC		5C	2
106	*_ERROR1_N	C5_04E0	C5_04E4		5D	2
107	*_ERROR0_N	C5_04E8	C5_04EC		5E	2
108	*_IERR_N	C5_04F0	C5_04F4		5F	
109	*_MCERR_N	C5_04F8	C5_04FC		60	2
110	*_SMB0_LEG_CLK	C5_0500	C5_0504		61	
111	*_SMB0_LEG_DATA	C5_0508	C5_050C		62	
112	*_SMB0_LEG_ALRT_N	C5_0510	C5_0514		63	
113	*_SMB1_HOST_DATA	C5_0518	C5_051C		64	2
114	*_SMB1_HOST_CLK	C5_0520	C5_0524		65	
115	*_SMB2_PECI_DATA	C5_0528	C5_052C		66	2
116	*_SMB2_PECI_CLK	C5_0530	C5_0534		67	
117	*_SMB4_CSME0_DATA	C5_0538	C5_053C		68	
118	*_SMB4_CSME0_CLK	C5_0540	C5_0544		69	
119	*_SMB4_CSME0_ALRT_N	C5_0548	C5_054C		6A	
120	*_USB_OC0_N	C5_0550	C5_0554		6B	2
121	*_FLEX_CLK_SE0	C5_0558	C5_055C	Yes	6C	
122	*_FLEX_CLK_SE1	C5_0560	C5_0564	Yes	6D	2
4	*_GPIO_4	C5_0568	C5_056C		6E	
5	*_GPIO_5	C5_0570	C5_0574		6F	
6	*_GPIO_6	C5_0578	C5_057C		70	

1. The Ball/Pin Name is not same as the suffix of the pad's register name.
2. Until RSMRST_N de-asserts these signals are indeterminate.

Table 26-5. GPIO Pad Configuration Description (Sheet 4 of 5)

GPIO	Suffix of Pad Register Name	Pad Configuration DW0 Offset (hex)	Pad Configuration DW1 Offset (hex)	SMI/NMI Capability	IOxAPIC Interrupt INTSEL (hex)	Comment
7	*_GPIO_7	C5_0580	C5_0584		71	
90	*_SATA0_LED_N	C5_0588	C5_058C	Yes	72	
91	*_SATA1_LED_N	C5_0590	C5_0594	Yes	73	
92	*_SATA_PDETECT0	C5_0598	C5_059C	Yes	74	
93	*_SATA_PDETECT1	C5_05A0	C5_05A4	Yes	75	
94	*_SATA0_SDOUT	C5_05A8	C5_05AC	Yes	76	
95	*_SATA1_SDOUT	C5_05B0	C5_05B4	Yes	18	
96	*_UART1_RXD	C5_05B8	C5_05BC	Yes	19	
97	*_UART1_TXD	C5_05C0	C5_05C4	Yes	1A	2
8	*_GPIO_8	C5_05C8	C5_05CC	Yes	1B	
9	*_GPIO_9	C5_05D0	C5_05D4	Yes	1C	2
146	*_CX_PRDY_N	C5_0600	C5_0604		22	
147	*_CX_PREQ_N	C5_0608	C5_060C		23	
148	*_CTBTRIGINOUT	C5_0610	C5_0614		24	
149	*_CTBTRIGOUT	C5_0618	C5_061C		25	
150	*_DFX_SPARE2	C5_0620	C5_0624		26	1
151	*_DFX_SPARE3	C5_0628	C5_062C		27	1
152	*_DFX_SPARE4	C5_0630	C5_0634		28	1
79	*_SUSPWRDNACK	C5_0638	C5_063C		29	
80	*_PMU_SUSCLK	C5_0640	C5_0644		2A	
81	*_ADR_TRIGGER	C5_0648	C5_064C	Yes	2B	
82	*_PMU_SLP_S45	C5_0650	C5_0654		2C	
83	*_PMU_SLP_S3	C5_0658	C5_065C		2D	
84	*_PMU_WAKE_N	C5_0660	C5_0664		2E	2
85	*_PMU_PWRBTN_N	C5_0668	C5_066C		2F	2
86	*_PMU_RESETBUTTON_N	C5_0670	C5_0674		30	2
87	*_PMU_PLTRST_N	C5_0678	C5_067C		31	2
88	*_SUS_STAT_N	C5_0680	C5_0684		32	
89	*_SLP_S0IX_N	C5_0688	C5_068C		33	1
72	*_SPI_CS0_N	C5_0690	C5_0694		34	
73	*_SPI_CS1_N	C5_0698	C5_069C		35	
74	*_SPI_MOSI_IO0	C5_06A0	C5_06A4		36	
75	*_SPI_MOSI_IO1	C5_06A8	C5_06AC		37	
76	*_SPI_IO2	C5_06B0	C5_06B4		38	2
77	*_SPI_IO3	C5_06B8	C5_06BC		39	2
78	*_SPI_CLK	C5_06C0	C5_06C4		3A	2
64	*_ESPI_IO0	C5_06D0	C5_06D4		3C	

1. The Ball/Pin Name is not same as the suffix of the pad's register name.
2. Until RSMRST_N de-asserts these signals are indeterminate.

Table 26-5. GPIO Pad Configuration Description (Sheet 5 of 5)

GPIO	Suffix of Pad Register Name	Pad Configuration DW0 Offset (hex)	Pad Configuration DW1 Offset (hex)	SMI/NMI Capability	IOxAPIC Interrupt INTSEL (hex)	Comment
65	*_ESPI_IO1	C5_06D8	C5_06DC		3D	
66	*_ESPI_IO2	C5_06E0	C5_06E4		3E	
67	*_ESPI_IO3	C5_06E8	C5_06EC		3F	
68	*_ESPI_CS0_N	C5_06F0	C5_06F4		40	
69	*_ESPI_CLK	C5_06F8	C5_06FC		41	
70	*_ESPI_RST_N	C5_0700	C5_0704		42	
71	*_ESPI_ALRT0_N	C5_0708	C5_070C	Yes	43	
10	*_GPIO_10	C5_0710	C5_0714	Yes	44	
11	*_GPIO_11	C5_0718	C5_071C	Yes	45	
123	*_EMMC_CMD	C5_0728	C5_072C	Yes	47	
124	*_EMMC_STROBE	C5_0730	C5_0734	Yes	48	
125	*_EMMC_CLK	C5_0738	C5_073C	Yes	49	
126	*_EMMC_D0	C5_0740	C5_0744	Yes	4A	
127	*_EMMC_D1	C5_0748	C5_074C	Yes	4B	
128	*_EMMC_D2	C5_0750	C5_0754	Yes	4C	
129	*_EMMC_D3	C5_0758	C5_075C	Yes	4D	
130	*_EMMC_D4	C5_0760	C5_0764	Yes	4E	
131	*_EMMC_D5	C5_0768	C5_076C	Yes	4F	
132	*_EMMC_D6	C5_0770	C5_0774	Yes	50	
133	*_EMMC_D7	C5_0778	C5_077C	Yes	51	
3	*_GPIO_3	C5_0780	C5_0784	Yes	52	

1. The Ball/Pin Name is not same as the suffix of the pad's register name.
2. Until RSMRST_N de-asserts these signals are indeterminate.

For GPIO registers access, there are two ways. One way is using P2SB to access GPIO registers. Another way is to reach GPIO by PMC through Sideband.

The GPIO controllers have 7 Dwords of GPE status and enable registers (NORTH_ALL_1/0 and SOURTH_DFX/GROUP0/1). But PMC exposes only 3 Dwords to SW. So BIOS must choose which 3 of the 7 to make visible.

Programming steps:

1. BIOS programs GPIO_CFG.GPE0_DW0, GPE0_DW1, GPE0_DW2 with the 3 GPIO groups to make visible. There are now 96 GPE available:
   - GPE[31:0] → GPIO selected by GPE0_DW0
   - GPE[63:32] → GPIO selected by GPE0_DW1
   - GPE[95:64] → GPIO selected by GPE0_DW2

2. BIOS enables GPE within the 96 available by writing to PMC. PMC forwards the writes to the GPIO based on mapping in 1)
   - Program GPE0_EN_31_0 → GPIO selected by GPE0_DW0
   - Program GPE0_EN_63_32 → GPIO selected by GPE0_DW1
   - Program GPE0_EN_95_64 → GPIO selected by GPE0_DW2

3. BIOS checks GPE status within the 96 available by reading from PMC. PMC forwards the reads to the GPIO based on mapping in 1)
   - Read I/O 0x80 → GPIO selected by GPE0_DW0
   - Read I/O 0x84 → GPIO selected by GPE0_DW1
   - Read I/O 0x88 → GPIO selected by GPE0_DW2

Table 26-6. PMC pci_cfg.PWRMBASE

<table>
<tr><th>MEM Address</th><th>Register</th><th>Field</th><th></th></tr>
<tr><td>0x120</td><td>GPIO_CFG</td><td>GPE0_DWG</td><td>Assigns a specific GPIO register to ABASE.0x80 and ABASE.0x90
<table>
<tr><th>Value</th><th>0x80 maps to this GPIO register</th><th>0x90 maps to this GPIO register</th></tr>
<tr><td>0</td><td>GPI_GPE_STS_NORTH_ALL_0</td><td>GPI_GPE_EN_NORTH_ALL_0</td></tr>
<tr><td>1</td><td>GPI_GPE_STS_NORTH_ALL_1</td><td>GPI_GPE_EN_NORTH_ALL_1</td></tr>
<tr><td>2</td><td>GPI_GPE_STS_SOUTH_DFX_0</td><td>GPI_GPE_EN_SOUTH_DFX_0</td></tr>
<tr><td>3</td><td>GPI_GPE_STS_SOUTH_GROUP0_0</td><td>GPI_GPE_EN_SOUTH_GROUP0_0</td></tr>
<tr><td>4</td><td>GPI_GPE_STS_SOUTH_GROUP0_1</td><td>GPI_GPE_EN_SOUTH_GROUP0_1</td></tr>
<tr><td>5</td><td>GPI_GPE_STS_SOUTH_GROUP1_0</td><td>GPI_GPE_EN_SOUTH_GROUP1_0</td></tr>
<tr><td>6</td><td>GPI_GPE_STS_SOUTH_GROUP1_1</td><td>GPI_GPE_EN_SOUTH_GROUP1_1</td></tr>
<tr><td>7</td><td>Reserved</td><td>Reserved</td></tr>
</table></td></tr>
<tr><td></td><td></td><td>GPE0_DW1</td><td>Assigns a specific GPIO register to ABASE.0x84 and ABASE.0x94
<table>
<tr><th>Value</th><th>0x84 maps to this GPIO register</th><th>0x94 maps to this GPIO register</th></tr>
<tr><td>0</td><td>GPI_GPE_STS_NORTH_ALL_0</td><td>GPI_GPE_EN_NORTH_ALL_0</td></tr>
<tr><td>1</td><td>GPI_GPE_STS_NORTH_ALL_1</td><td>GPI_GPE_EN_NORTH_ALL_1</td></tr>
<tr><td>2</td><td>GPI_GPE_STS_SOUTH_DFX_0</td><td>GPI_GPE_EN_SOUTH_DFX_0</td></tr>
<tr><td>3</td><td>GPI_GPE_STS_SOUTH_GROUP0_0</td><td>GPI_GPE_EN_SOUTH_GROUP0_0</td></tr>
<tr><td>4</td><td>GPI_GPE_STS_SOUTH_GROUP0_1</td><td>GPI_GPE_EN_SOUTH_GROUP0_1</td></tr>
<tr><td>5</td><td>GPI_GPE_STS_SOUTH_GROUP1_0</td><td>GPI_GPE_EN_SOUTH_GROUP1_0</td></tr>
<tr><td>6</td><td>GPI_GPE_STS_SOUTH_GROUP1_1</td><td>GPI_GPE_EN_SOUTH_GROUP1_1</td></tr>
<tr><td>7</td><td>Reserved</td><td>Reserved</td></tr>
</table></td></tr>
<tr><td></td><td></td><td>GPE0_DW2</td><td>Assigns a specific GPIO register to ABASE.0x88 and ABASE.0x98
<table>
<tr><th>Value</th><th>0x88 maps to this GPIO register</th><th>0x98 maps to this GPIO register</th></tr>
<tr><td>0</td><td>GPI_GPE_STS_NORTH_ALL_0</td><td>GPI_GPE_EN_NORTH_ALL_0</td></tr>
<tr><td>1</td><td>GPI_GPE_STS_NORTH_ALL_1</td><td>GPI_GPE_EN_NORTH_ALL_1</td></tr>
<tr><td>2</td><td>GPI_GPE_STS_SOUTH_DFX_0</td><td>GPI_GPE_EN_SOUTH_DFX_0</td></tr>
<tr><td>3</td><td>GPI_GPE_STS_SOUTH_GROUP0_0</td><td>GPI_GPE_EN_SOUTH_GROUP0_0</td></tr>
<tr><td>4</td><td>GPI_GPE_STS_SOUTH_GROUP0_1</td><td>GPI_GPE_EN_SOUTH_GROUP0_1</td></tr>
<tr><td>5</td><td>GPI_GPE_STS_SOUTH_GROUP1_0</td><td>GPI_GPE_EN_SOUTH_GROUP1_0</td></tr>
<tr><td>6</td><td>GPI_GPE_STS_SOUTH_GROUP1_1</td><td>GPI_GPE_EN_SOUTH_GROUP1_1</td></tr>
<tr><td>7</td><td>Reserved</td><td>Reserved</td></tr>
</table></td></tr>
</table>

Table 26-7. PMC pci_cfg.ABASE

IO Address	Register	
0x80	GPE0_STS_31_0	R/W is redirected to GPE STATUS register per mapping in GPIO_CFG.GPE0_DW0
0x84	GPE0_STS_63_32	R/W is redirected to GPE STATUS register per mapping in GPIO_CFG.GPE0_DW1
0x88	GPE0_STS_95_64	R/W is redirected to GPE STATUS register per mapping in GPIO_CFG.GPE0_DW2
0x8C	GPE0_STS_127_96	STATUS of special GPE events defined by PMC; this register physically lives in PMC
0x90	GPE0_EN_31_0	R/W is redirected to GPE ENABLE register per mapping in GPIO_CFG.GPE0_DW0
0x94	GPE0_EN_63_32	R/W is redirected to GPE ENABLE register per mapping in GPIO_CFG.GPE0_DW1
0x98	GPE0_EN_95_64	R/W is redirected to GPE ENABLE register per mapping in GPIO_CFG.GPE0_DW2
0x9C	GPE0_EN_127_96	ENABLE of special GPE events defined by PMC; this register physically lives in PMC

§ §

27 System Management Bus (SMBus) Controller - Overview

The SoC provides multiple System Management Bus (SMBus) 2.0 controllers. The interfaces comply to *System Management Bus (SMBus) Specification, Version 3.0*. The controllers provide a mechanism for various system components [SoC, Baseboard Management Controller (BMC), etc.] to communicate with each other and with the entire system. The SoC is also capable of operating in a mode that communicates with I^2C*-compatible devices.

Note: There are only seven sets of SMBus pins so a maximum of seven SMBus controllers maybe active.

The SoC includes the following SMBus controllers:

- Legacy SMBus (wire ORed with CLTT SMBus):
  - IA cores use the master/slave legacy interface to communicate with managed devices in the system.
  - The BIOS uses this interface to detect and configure memory devices.
- Host SMBus:
  - IA cores use this master/slave interface to enable the SoC to send/receive out-of-band messages over the SMBus to peripherals. The controller operation is DMA-based and utilizes descriptors to initiate transactions on the bus.
- Platform Environment Control Interface (PECI) SMBus:
  - A slave only interface which enables external management devices (BMC) to obtain system information like thermal data through PECI commands encapsulated within SMBus packets to the SoC.
- Three Intel® Management Engine (Intel® ME) SMBuses:
  - The Intel® ME SMBus Message Transport (SMT) controllers are configured as a master or slave for internal agents inside the SoC to communicate to the external management devices [BMC/External Circuitry (EC)] over SMBus.
  - The silicon-enabling firmware and Intel® Node Manager (Intel® NM) of the Intel® Server Platform Services (SPS) firmware defines the SMT interface configuration and connection.
- LAN SMBus:
  - This master/slave sideband interface provides a mechanism for the network management traffic to be routed to and from a management controller (BMC). The SMBus in each LAN controller is wire-ANDed in silicon.
- Three Innovation Engine (IE) SMBuses:
  - IE uses master/slave interfaces to communicate with devices in the system.

Table 27-1. References

Document Title	Document ID / Location
System Management Bus (SMBus) Specification, Version 3.0	http://smbus.org/specs/SMBus_3_0_20141220.pdf

27.1 General Architecture

At its network layer, the *System Management Bus (SMBus) Specification, Version 3.0* refers to three types of devices:

- **Slave Device** - A device that is receiving or responding to a command.
- **Master** - A device that issues commands, generates the clocks, and terminates the transfer.
- **Host** - A specialized master that provides the main interface to the system CPU. A host must be a master-slave and must support the SMBus host notify protocol. At most, one host exists in a system.

Figure 27-1 shows the overall SMBus arrangement in the SoC, M = Master, S = Slave.

Figure 27-1. Arrangement of SMBus in SoC



Note: If software running on the IA uses the legacy SMBus (SMBus master), then there are multiple masters active. When multiple master are active on the same bus, software using the legacy SMBus controller must check for Bus Error (BERR) in the Status register (HSTS) to determine if a bus collision has occurred, and retry the transaction if needed.

27.2 Feature List

The following are key features of the various controllers:

- Legacy SMBus:
  - Serial interface providing a mechanism for the processor to initiate communications with the SMBus peripherals
  - Access initiated through registers in Host Root Memory Space and Host Root I/O Space.
  - The Memory Reference Code (MRC) uses this bus to detect and configure the DIMMs
  - Closed loop thermal throttling (CLTT) which requires the controller to act as a bus master to monitor DIMM temperature (Refer Chapter 35, "Thermal Management")
  - Chapter 28, "SMBus Controller - Legacy"
- Host SMBus:
  - Operates as an SMBus master or slave
  - Supports Address Resolution Protocol (ARP) in master or slave mode
  - Access initiated through the descriptors
  - OS controlled to communicate with any platform device
  - Packet Error Checking (PEC) is enabled for SMBus transactions
  - Chapter 29, "SMBus Controller - Host"
- PECI SMBus:
  - Supports external BMC
  - Operates in slave mode only
  - Supports one command at a time
  - Chapter 30, "SMBus Controller - Platform Environment Control Interface"
- Intel® ME SMBuses:
  - Sends Out-Of-Band (OOB) manageability messages to managed devices or management controllers
  - SMT controllers operate with full master and slave interfaces
  - Supports Management Component Transport Protocol (MCTP) and Alert Standard Format (ASF) usage models
  - Interrupt generation capability for SMBAlert# signaling received from External SMBus device
  - Chapter 36, "System Management"

- LAN SMBus:
  - Pass-through and/or configuration traffic between an external Manageability Controller (MC) and Integrated Ethernet LAN ports
  - Operates as master or slave
  - Supports MCTP over SMBus
  - Supports ARP
  - Interface pins MUXed with the Network Controller Sideband Interface (NC-SI).
  - Chapter 13, “LAN Controllers”
- IE SMBuses:
  - BMC offload engine to access PECI services
  - Operates as master or slave
  - Chapter 37, “Innovation Engine”

§ §

28 SMBus Controller - Legacy

The SMBus controller described in this chapter is located in the Platform Control Cluster (PCC) of the SoC. In SoC diagrams, it is labeled Legacy SMBus.

The controller provides a mechanism for the processor to initiate communications with SMBus peripherals (slaves). The SoC is also capable of operating in a mode that communicates with I^2C-compatible devices.

The SoC performs SMBus messages with Packet Error Checking (PEC) enabled or disabled. The actual PEC calculation and checking are performed in either the hardware or the software.

The SMBus Address Resolution Protocol (ARP) is supported by using the existing SMBus controller commands through the software. The controller can be the designated SMBus ARP Master.

This SMBus interface is shared with the Closed Loop Temperature Throttling (CLTT) circuitry to allow the CLTT to access the thermal information, if available, through the system memory DIMMs' Temperature Sensor On DIMM (TSOD) circuitry. See Section 35.5.1.5, "Legacy SMBus Used for Accessing Information for CLTT."

Figure 28-1. What is Covered in This Chapter



Table 28-1. References

Document Title	Document ID / Location
System Management Bus (SMBus) Specification, Version 3.0	http://smbus.org/specs/SMBus_3_0_20141220.pdf

28.1 Signal Descriptions

The signal descriptions are shown in Table 28-2, "Signal Names." For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals, see Section 39.1, "Directory of Signal Names and Pin Names." The Direction/Type column of Table 28-2, "Signal Names" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 28-2. Signal Names

Signal Name	Direction	Shared	Description
SMB_LEG_CLK	I, O-OD	Yes	**SMBus Clock (SMBCLK)**
SMB_LEG_DATA	I, O-OD	Yes	**SMBus Data (SMBDAT)**
SMB_LEG_ALRT_N	I, O-OD	Yes	**SMBus Alert (SMBALERT#):** This signal wakes the system or generates a System Management Interrupt (SMI).

The optional SMBus 2.0 signal, SMBSUS#, is not supported.

28.2 General Architecture

From a software driver perspective, the Legacy SMBus controller described in this chapter exists as a PCI device on Bus 0, Device 31 (decimal), Function 4 of configuration space. Its logic is controlled by the SoC RTC Clock. The controller's I/O registers are relocatable. The I/O base address registers are:

- SBA - SoC Host I/O Space
- SMBMBAR - SoC Host Memory Space

The registers and offsets are the same for SBA access and SMBAR access.

Key capabilities supported and not supported by the SoC Legacy SMBus controller:

- It is not supported as an SMBus Slave except when it is acting as the SMBus ARP Master. It functions as an SMBus Master as defined in the *System Management Bus (SMBus) Specification, Version 3.0*.
- Acting as the SMBus Host is not supported.

  As defined by the *System Management Bus (SMBus) Specification, Version 3.0*, an SMBus Host is a specialized SMBus Master that provides the main interface to the system's CPU. An SMBus Host must be an SMBus Master-Slave and must support the SMBus Host Notify protocol. There may be at most one SMBus Host in a system.
- Can be designated as the SMBus Address Resolution Protocol (ARP) Master.

  A system design usually defines the SMBus Host (defined above) to be the SMBus ARP Master but under some circumstances another SMBus Master, like the SoC Legacy SMBus controller, may be given the role by system software. There can only be one active SMBus ARP Master at any time.
- Functions as an SMBus version 2.0 Master or ARP Master device when the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register is 0.
- Functions as an I^2C Master when the I2CEN bit is 1. Not all protocols are supported when I2CEN is 1. The protocol descriptions in this chapter describe what is supported. When the I2CEN bit is set, the SoC never uses its 32-byte buffer for any block commands.
  - The SoC supports an I^2C Read command which is independent of the setting of the I2CEN bit.

28.3 Legacy SMBus Controller Operation

In order to initiate an SMBus operation as an SMBus Master, software sets up the registers of the SoC Legacy SMBus controller with a Slave Address (to which the operation is directed), a command to issue to the addressed Slave, and for write protocols, data to be sent to the Slave and an optional Packet Error Checking (PEC) bits. For read protocols, there is a designated SoC register for the data received from the Slave. The following registers are involved:

- Transmit Slave Address Register (TSA) - TSA bit field 7:1 is the seven-bit Slave address to be used of the targeted SMBus Slave. TSA bit 0 is 0 for write (to Slave) and 1 for read (from Slave). Transactions with TSA[7:0] values of 1010_xxx0 are blocked if the SPD Write Disable (SPDWD) bit = 1 in the Host Configuration (HCFG) register in Configuration Space. SPDWD prevents writing into the DIMM's SPD EEPROM.
- Host Command Register (HCMD) - Contains the eight-bit information to use as the transaction's SMBus command field. "Host" has nothing to do with the term "SMBus Host" mentioned earlier.
- Data 0 Register (HD0), Data 1 Register (HD1), and Host Block Data (HBD) - Used for the data transfer cycles of the particular protocol transaction.

Software then initiates the hardware operation by writing to the Start bit of the Host Control (HCTL) register. While the hardware executes the HCMD command, it sets the Host Busy (HBSY) bit of the Host Status Register Address (HSTS).

When completed, the hardware generates an interrupt or SMI to notify the software to access the HSTS register to view the status and error bits. If the command completed successfully, the Interrupt (INTR) bit of the HSTS register is set. Software must not alter the TSA, HCMD, HD0, HD1 and HBDregisters, until the INTR bit is set.

If the Slave device does not respond with an SMBus Acknowledge (ACK), or holds the SMBus Clock (SMB_LEG_CLK SoC signal pin) lower than the allowed timeout (25 ms which is 800 RTC clock cycles) the transaction times out. Here the hardware discards the cycle and the Device Error (DEVERR) bit is set. If the software sets the Kill (KILL) bit of the Host Control (HCTL) register is set by software while the command is running, the transaction stops and the Failed (FAIL) bit of the HSTS register is set.

The SoC Legacy SMBus controller uses PIRQB# as its interrupt pin. However, the system can alternatively be setup to generate an internal SMI# instead of an IRQ interrupt, by setting the SMB_SMI_EN (SSEN) bit of the HCFG register. More is said about this in Section 28.8, "Interrupts and SMI." Also see Section 8.1.1, "Interrupt Pin Route Overview" for PIRQB# routing. The SoC SMI is described in Section 8.3, "System Management Interrupt (SMI)."

28.3.1 Supported SMBus Protocols

The Legacy SMBus controller supports the SMBus protocols and I^2C transactions shown in Table 28-3, "Supported SMBus ARP, SMBus, and I^2C Protocols." For details of the bus cycles for each protocol, see the *System Management Bus (SMBus) Specification, Version 3.0*.

Table 28-3. Supported SMBus ARP, SMBus, and I²C Protocols

Protocol	Supported	
SMBus ARP Commands	**Sent as ARP Master**	**Received as ARP Slave**
Prepare to ARP	Yes, by Software Driver	Cannot be an SMBus slave
Reset Device *General and directed*		
Get UDID *General and directed*		
Assign Address		
SMBus ARP Commands	**Sent as ARP Slave**	**Received as ARP Master**
Notify ARP Master	Cannot be an SMBus slave	Yes
SMBus Commands	**Sent as Master**	**Received as Slave**
Quick Command	Yes	Cannot be an SMBus slave
Send Byte	Yes	
Receive Byte	Yes	
Write Byte/Word	Yes	
Read Byte/Word	Yes	
Process Call	Yes	
Block Write	Yes	
Block Read	Yes	
Block Write-Block Read Process Call	Yes	
SMBus Host Notify	Yes	
I²C Commands	**Sent as Master**	**Received as Slave**
Master-TX writes to Slave-RX (MTx-to-SRx) *No direction change*	Yes	Cannot be an I²C slave
Master-RX reads Slave-TX (STx-to-MRx)	Yes	
Combined format, write-then-read *direction change after initial write*	No	
Combined format, read-then-write *direction change after initial read*	No	

28.3.2 SMBus CRC Generation and Checking

If the Automatically Append CRC (AAC) bit of the Auxiliary Control (AUXC) register is set, the SoC automatically calculates and drives the Cyclic Redundancy Check (CRC) at the end of the transmitted packet for write cycles and checks the CRC for read cycles. It does not transmit the contents of the Packet Error Check Data (PEC) PEC register for a CRC. The PEC Enable (PEC_EN) bit of the Host Control Register (HCTL) must not be set if the AAC bit is set, or else unspecified behavior results.

If the read cycle results in a CRC error, the Device Error (DERR) bit of the Host Status Register Address (HSTS) and the CRC Error (CRCE) bit of the Auxiliary Status (AUXS) register are set.

28.4 Protocols as an SMBus Master

Software sets up registers and instructs the SoC Legacy SMBus Controller to issue various protocols and commands. Programming details are presented here.

When the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register is 1, the SoC Legacy SMBus Controller is enabled to communicate with I^2C devices. This is also called I^2C mode and changes the formatting of some commands. When I2CEN is 0, behavior is for SMBus as defined in the *System Management Bus (SMBus) Specification, Version 3.0*. The command descriptions below mention the I2CEN bit and how it affects the transaction.

28.4.1 Quick Command

When the Legacy SMBus Controller is programmed to issue a Quick Command, the Transmit Slave Address (TSA) register is sent. The PEC byte is never appended to the quick protocol. The software forces the PEC Enable (PEC_EN) bit of the Host Control Register (HCTL) to 0 when performing the Quick Command. Software must force the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register to 0 when running this command. See Section 5.5.1 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

28.4.2 Send Byte and Receive Byte Commands

For the Send Byte command, the Transmit Slave Address (TSA) and Host Command (HCMD) registers are sent. For the Receive Byte command, the Transmit Slave Address (TSA) register is sent. The data received is stored in the Data 0 (HD0) register. Software must force the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register to bit to 0 when running this command.

The Receive Byte is similar to a Send Byte, the only difference is the direction of data transfer. See Sections 5.5.2 and 5.5.3 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

28.4.3 Write Byte and Write Word Commands

The first byte of a Write Byte/Word access is the command code. The next 1 or 2 bytes are the data to be written. When programmed for a Write Byte/Word command, the Transmit Slave Address (TSA), Host Command (HCMD), and Data 0 (HD0) registers are sent. In addition, the Data 1 (HD1) register is sent on a Write Word command. Software must force the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register to 0 when running this command. See Section 5.5.4 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

28.4.4 Read Byte and Read Word Commands

Reading data is slightly more complicated than writing data. First the SoC must write a command to the slave device. Then it must follow that command with a repeated start condition to denote a read from that device address. The slave then returns 1 or 2 bytes of data. Software must force the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register to 0 when running this command.

When programmed for the Read Byte/Word command, the Transmit Slave Address (TSA) and Host Command (HCMD) registers are sent. Data is received into the Data 0 (HD0) on the read byte, and the Data 0 (HD0) and Data 1 (HD1) registers on the read word. See Section 5.5.5 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

28.4.5 Process Call Command

The Process Call is so named because a command sends data and waits for the slave to return a value dependent on that data. The protocol is a Write Word followed by a Read Word, but without a second command or stop condition.

When programmed for the Process Call command, the SoC transmits the Transmit Slave Address (TSA), Host Command (HCMD), Data 0 (HD0) and Data 1 (HD1) registers. Data received from the device is stored in the Data 0 (HD0) and Data 1 (HD1) registers.

The Process Call command produces undefined results when both the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register and the PEC Enable (PEC_EN) bit of the Host Control (HCTL) register are set. Software must force either the IC2EN bit to 0 or both the PCE_EN and the Automatically Append CRC (AAC) bits of the Auxiliary Control (AUXC) register to 0 when running this command. See Section 5.5.6 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

Note: For the Process Call command, the RW bit of the TSA register must to be programmed to 0 (indicating Write).

Note: If the I2CEN bit is set, the protocol sequence changes slightly. The command code (bits [18:11] in the bit sequence) is not sent, and as a result, the targeted Slave device does not Acknowledge (bit 19 in the sequence).

28.4.6 Block Read and Block Write Commands

The SoC contains a 32-byte buffer for read and write data which is enabled by setting the Enable 32-byte Buffer (E32B) bit of the Auxiliary Control (AUXC) register. If E32B is 0, single-byte buffering is used. This 32-byte buffer is filled with write data before transmission and filled with read data on reception. In the SoC, the interrupt is generated only after a transmission or reception of 32 bytes, or when the entire byte count has been transmitted/received.

Note: If the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register is set, the SoC never uses the 32-byte buffer for any Block commands.

The byte count field is transmitted but ignored by the SoC as the software ends the transfer after all bytes it cares about have been sent or received.

For a Block Write, software must force either the IC2EN bit to 0 or both the PCE_EN and the Automatically Append CRC (AAC) bits of the Auxiliary Control (AUXC) register to 0 when running this command.

The Block Write begins with issuing a Slave Address and a Write indication. After the command code, the SoC issues a byte count describing how many more bytes follow in the message. If the Slave device has 20 bytes to send, the first byte is the number 20 (14h), followed by 20 bytes of data. The byte count is not 0. A Block Read or Write is allowed to transfer a maximum of 32-data bytes.

When programmed for a Block Write command, the Transmit Slave Address (TSA), Host Command (HCMD) and Data 0 (HD0) registers are sent. Data is then sent from the Host Block Data (HBD) register; the total data sent being the value stored in the Data 0 (HD0) register. On Block Read commands, the first byte received is stored in the Data 0 (HD0) register, and the remaining bytes are stored in the Host Block Data (HBD) register. See Section 5.5.7 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

Note: For a Block Write, if the I2CEN bit is set, the format of the command changes slightly. The SoC still sends the number of bytes (on writes) or receives the number of bytes (on reads) indicated in the Data 0 (HD0) register. However, it does not send the contents of the Data 0 (HD0) register as part of the message. Also, the Block Write protocol sequence changes slightly. The byte count (bits [27:20] in the bit sequence) is not sent, and as a result, the Slave device does not Acknowledge (bit 28 in the sequence).

28.4.7 Block Write-Block Read Process Call Command

The Block Write-Block Read Process Call command is a two-part message.

The call begins with a Slave Address and a Write indication. After the command code, the host issues a write byte count (M) that describes how many more bytes are written in the first part of the message. If a master has six bytes to send, the byte count field has the value six (0000_0110), followed by the six bytes of data. The write byte count (M) cannot be 0.

The second part of the message is a block of read data beginning with a repeated start condition followed by the slave address and a read bit. The next byte is the read byte count (N), which differs from the write byte count (M). The read byte count (N) cannot be 0.

The combined data payload must not exceed 32 bytes. The byte-length restrictions of this process call are summarized as follows:

- M ≥ 1 byte
- N ≥ 1 byte
- M + N ≤ 32 bytes

The read byte count does not include the Packet Error Checking (PEC) byte. The PEC is computed on the total message beginning with the first slave address and using the normal PEC computational rules. Intel recommends that a PEC byte be used with the Block Write-Block Read Process Call command. The software must read the Host Command (HCMD) register to reset the 32-byte buffer pointer before reading the Host Block Data (HBD) register.

Note: No STOP condition is before the repeated START condition, and that a NACK signifies the end of the read transfer.

Note: The Enable 32-byte Buffer (E32B) bit of the Auxiliary Control (AUXC) register must be set when using this protocol.

See Section 5.5.8 of the *System Management Bus (SMBus) Specification, Version 3.0* for the format of the protocol.

28.4.8 SMBus Host Notify Command

See Section 5.5.9 SMBus Host Notify Protocol of the *System Management Bus (SMBus) Specification, Version 3.0*.

The SoC Legacy SMBus Controller uses this protocol to communicate with the SMBus Host which has its Slave address defined as 0001_000.

28.5 Protocols and Commands as the ARP Master

The SoC Legacy SMBus controller and associated software driver can act as the SMBus ARP Master. Details of the role of the Address Resolution Protocol (ARP) Master are in Section 5.6.3 ARP Commands of the *System Management Bus (SMBus) Specification, Version 3.0*.

The ARP Master operation is supported via software that uses the existing Legacy SMBus controller commands in the Host Controller Command (HCMD) register in I/O Space and also in Memory Space. When acting as the ARP Master, bits [6:0] of the Receive Slave Address (RSA) register must be programmed to 0001_000.

The supported ARP commands are shown in Table 28-3, "Supported SMBus ARP, SMBus, and I^2C Protocols." The recommended software-driver flow is shown in Figure 29-3, "ARP Master Behavior Flow Diagram." This diagram is taken from the *System Management Bus (SMBus) Specification, Version 3.0*.

28.5.1 ARP Enumeration and the Notify ARP Master Command

Any SMBus Master, including the Legacy SMBus Controller, can be delegated to perform ARP enumeration. Enumeration is the process that assigns Slave Addresses to the ARP-Capable Slave devices on the SMBus. Enumeration begins with a Master issuing the Prepare to ARP command as described in Section 5.6.3.2 Prepare to ARP of the *System Management Bus (SMBus) Specification, Version 3.0*. The controller performs a write to Slave Address 1100_001 which is the SMBus Device Default Address.

If it is the SMBus ARP Master (there can only be one on an SMBus interface), the SoC Legacy SMBus Controller is also responsible for responding to the Notify ARP Master directed to the Slave Address 0001_000 which is the Slave Address that can also be assigned to the SMBus Host.

If the Legacy SMBus Controller is not the ARP Master, because the SoC controller cannot act as an SMBus Slave, it has no Slave Address that can be assigned by the ARP Master and requires no ARP enumeration.

28.6 I²C Read Command

This command allows the SoC to perform Block Reads from certain I²C devices, such as serial EEPROMs. The SMBus Block Read supports the 7-bit addressing mode only. However, this does not allow access to devices using the I²C combined format that has data bytes after the address. Typically these data bytes correspond to an offset (address) within the serial memory chips.

Note: This command is supported independent of the setting of the I2C_EN (I2CEN) bit of the Host Configuration (HCFG) register. The I²C Read command with the PEC Enable (PEC_EN) bit set of the Host Control (HCTL) register produces undefined results. Undefined results also occurs when the The I²C Read command is started and the Append CRC (AAC) bits of the Auxiliary Control (AUXC) register is set.

For an I²C Read command, the RW bit of the TSA register RW must to be programmed to 1 (indicating Read). The format that is used for the command is shown in Table 28-4, "I²C Block Read."

Table 28-4. I²C Block Read

Bit	Description
1	START indication driven by the SoC Legacy SMBus Controller
8:2	Slave Address – 7 bits
9	Write
10	Acknowledge (ACK) from the Slave device
18:11	Send Data 1 (HD1) register
19	ACK from the Slave device
20	Repeated START indication
27:21	Slave Address – 7 bits
28	Read
29	ACK from the Slave device
37:30	Data byte 1 from slave – 8 bits
38	ACK from the Slave device
46:39	Data byte 2 from the Slave device– 8 bits
47	ACK from the Slave device
–	Data bytes from the Slave device and associated ACKs[1]
–	Data byte N from the Slave device – 8 bits
–	NOT Acknowledge (NACK)
–	STOP indication driven by the SoC.

1. The SoC continues reading data from the I²C Slave device until the NACK is received.

28.7 Bus Arbitration as an SMBus Master

See Section 4.3.2 Arbitration of the *System Management Bus (SMBus) Specification, Version 3.0*.

As an SMBus Master, if the SoC Legacy SMBus Controller starts to initiate a transaction on the bus and loses arbitration, the SoC sets the Bus Error (BERR) of the Host Status Register Address (HSTS) and, if enabled, generates an interrupt or SMI. The processor restarts the transaction.

When the controller wins arbitration, it drives the SMBCLK (the SoC SMB_LEG_CLK signal pin) during the transaction. The minimum frequency of the clock is 10 kHz and the maximum is 100 kHz. The SMBDAT (the SoC SMB_LEG_DATA signal pin) is driven or sensed by the SoC during the transaction defined by the protocol. The SoC also ensures minimum time between SMBus transactions it initiates.

28.7.1 SMBCLK Signal Stretching by an SMBus Slave

See Section 4.3.3 Clock low Extending of the *System Management Bus (SMBus) Specification, Version 3.0*.

The Slave device of the transaction may be slower than the Legacy SMBus Controller and may need additional time to respond to the controller. Slower Slave devices are allowed to stretch the low portion of the SMBCLK signal by driving it low (along with the Master) during the transfer of one message up to the maximum limits described in the AC specifications of the *System Management Bus (SMBus) Specification, Version 3.0*. The Slave device must not extend the SMBCLK too long and must maintain an SMBCLK period of no more than 100 µs (minimum SMBCLK frequency of 10 kHz). There are some exceptions to this and are mentioned in the SMBus specification.

28.7.2 SMBus Timeout

See Section 3.1.1.2 Timeouts of the *System Management Bus (SMBus) Specification, Version 3.0*.

If an error is in the transaction, such that an SMBus Slave device does not signal an Acknowledge (ACK) to the Legacy SMBus Controller, or holds the SMBCLK low (stretching) longer than the allowed timeout duration, the transaction times out. The SoC discards the cycle and sets the Device Error (DERR) bit of the Host Status Register Address (HSTS). The minimum timeout duration is 25 ms (800 RTC clock periods). The time-out counter inside the SoC starts after the first bit of data is transferred. The 25-ms time-out counter does not count when the Byte Done Status bit (BYTE_DONE_STS) of the Host Status Register Address (HSTS) is set.

28.8 Interrupts and SMI

The SMBus controller uses PIRQB# as its interrupt pin. However, the system is alternatively set up to generate a System Management Interrupt (SMI) instead of an interrupt, by setting the SMB_SMI_EN (SSEN) bit of the Host Configuration (HCFG) Register.

The following tables specify how the various enable bits in the SMBus function control the generation of the interrupt, host SMI, and wake internal signals:

- Table 28-5, “Enable for SMBALERT# (SMB_LEG_ALRT_N)”
- Table 28-6, “Enables for Legacy SMBus Controller Events”
- Table 28-7, “Enables for a Received Notify ARP Master Command”

The rows in the tables are additive, which means that if more than one row is true for a particular scenario then the results for all of the activated rows occur.

Table 28-5. Enable for SMBALERT# (SMB_LEG_ALRT_N)

Event	INTREN (INTREN) bit of the Host Control (HCTL) Register	SMB_SMI_EN (SSEN) bit of the Host Configuration (HCFG) Register	SMBALERT_DIS (SMB_D) bit of the Slave Command (SCMD) Register	Result
SMBALERT# (SMB_LEG_ALRT_N) asserted low *Always reported in SMBALERT bit of the Host Status Register Address (HSTS)*	X	X	X	Wake Event generated to PMC via the SMB_WAK_STS bit of the General Purpose Event 0 Status [127:96] (GPE0_STS_127_96) register of the SoC PMC. *Depends on Intel® Management Engine settings*
	X	1	0	Besides the Wake Event, an SMI is generated by the Legacy SMBus Controller via the SMBALERT_STS of the Host Status Register Address (HSTS) register. Also, when in the S0 state, this also sets SMBUS_SMI_STS bit of the SMI Status (SMI_STS) register of the SoC PMC.
	1	0	0	IRQ Interrupt generated

Table 28-6. Enables for Legacy SMBus Controller Events

Event	INTREN (INTREN) bit of the Host Control (HCTL) Register	SMB_SMI_EN (SSEN) bit of the Host Configuration (HCFG) Register	Result
Any combination of FAIL, BERR, DERR, and INTR bits of the Host Status Register Address (HSTS) provided they are individually enabled to generate and interrupt.	0	X	None
	1	0	IRQ interrupt generated
	1	1	SMI generated to the PMC when in S0 state via the LEGACY_USB2_STS bit of the SMI Status (SMI_STS) register of the SoC PMC.

Table 28-7. Enables for a Received Notify ARP Master Command

HOST_NOTIFY_INTREN (HNI) bit of the Slave Command (SCMD) Register	SMB_SMI_EN (SSEN) bit of the Host Configuration (HCFG) Register	HOST_NOTIFY_WKEN (HNW) bit of the Slave Command (SCMD) Register	Result
0	X	0	None
X	X	1	Wake Event generated to PMC via the SMB_WAK_STS bit of the General Purpose Event 0 Status [127:96] (GPE0_STS_127_96) register. *Depends on Intel® Management Engine settings*
1	0	X	IRQ interrupt generated
1	1	X	SMI generated to the PMC when in S0 state via the SMBUS_SMI_STS bit of the SMI Status (SMI_STS) register of the SoC PMC.

28.9 Optional SMBALERT# Signal

The optional SMBALERT# signal is multiplexed with Customer GPIO[112]. If not blocked by the SMBALERT_DIS (SMB_D) bit of the Slave Command (SCMD) register, the SoC generates an interrupt or an SMI when SMBALERT# is asserted by an SMBus Slave device. This signal is a wake event from the system S4 or S5 (soft off) power state. See Table 28-5, "Enable for SMBALERT# (SMB_LEG_ALRT_N)." The SMBUSALERT# signal is described in the Appendix A – Optional SMBus Signals section of the *System Management Bus (SMBus) Specification, Version 3.0*.

The interrupt is meant to alert software to setup the Legacy SMBus controller to issue a message over the SMBus with the slave address set to the Alert Response Address (0001_000). This message accesses all SMBUSALERT# devices on the bus. There could be more than one Slave device asserting the SMB_LEG_ALRT_N signal. The controller observes the returned Slave-device address(es) and performs device-address arbitration as defined in the *System Management Bus (SMBus) Specification, Version 3.0* to determine which SMBus Slave device shall be attributed to the alert.

28.10 Register Map

Figure 28-2, "Register Map" shows the associated registers from a system software viewpoint. The TCO Registers are used by the SoC Power Management Controller. See Chapter 16, "Power Management Controller (PMC)."

Figure 28-2. Register Map



28.10.1 Registers in the Configuration Space

Table 28-8. Registers in the Configuration Space

Offset	Name	Description
0h	VID	Vendor ID
2h	DID	Device ID
4h	CMD	Command
6h	DS	Device Status
8h	RID	Revision ID
9h	PI	Programming Interface
Ah	SCC	Sub Class Code
Bh	BCC	Base Class Code
10h	SMBMBAR_31_0	SMBus Memory Base Address_31_0
14h	SMBMBAR_63_32	SMBus Memory Base Address_63_32
20h	SBA	SMB Base Address
2Ch	SVID	Subsystem Vendor ID
2Eh	SID	Subsystem ID
3Ch	INTLN	Interrupt Line
3Dh	INTPN	Interrupt Pin
40h	HCFG	Host Configuration
50h	TCOBASE	TCO Base Address
54h	TCOCTL	TCO Control
F8h	MANID	Manufacturer's ID

28.10.2 Registers in the Memory Space

Table 28-9. Registers in the Memory Space

Offset	Name	Description
0h	HSTS	Host Status Register Address
2h	HCTL	Host Control Register
3h	HCMD	Host Command Register
4h	TSA	Transmit Slave Address Register
5h	HD0	Data 0 Register
6h	HD1	Data 1 Register
7h	HBD	Host Block Data
8h	PEC	Packet Error Check Data Register
9h	RSA	Receive Slave Address Register
Ah	SD	Slave Data Register
Ch	AUXS	Auxiliary Status
Dh	AUXC	Auxiliary Control
Eh	SMLC	SMLINK_PIN_CTL Register
Fh	SMBC	SMBUS_PIN_CTL Register
10h	SSTS	Slave Status Register
11h	SCMD	Slave Command Register
14h	NDA	Notify Device Address Register
16h	NDLB	Notify Data Low Byte Register
17h	NDHB	Notify Data High Byte Register

28.10.3 Registers in the I/O Space

Table 28-10. Registers in the I/O Space

Offset	Name	Description
0h	HSTS	Host Status Register Address
2h	HCTL	Host Control Register
3h	HCMD	Host Command Register
4h	TSA	Transmit Slave Address Register
5h	HD0	Data 0 Register
6h	HD1	Data 1 Register
7h	HBD	Host Block Data
8h	PEC	Packet Error Check Data Register
9h	RSA	Receive Slave Address Register
Ah	SD	Slave Data Register
Ch	AUXS	Auxiliary Status
Dh	AUXC	Auxiliary Control
Eh	SMLC	SMLINK_PIN_CTL Register
Fh	SMBC	SMBUS_PIN_CTL Register
10h	SSTS	Slave Status Register
11h	SCMD	Slave Command Register
14h	NDA	Notify Device Address Register
16h	NDLB	Notify Data Low Byte Register
17h	NDHB	Notify Data High Byte Register

§ §

29 SMBus Controller - Host

The SMBus Message Transport (SMT) controller provides a mechanism whereby the SoC sends and receives out-of-band manageability messages over the SMBus to managed devices or to management controllers. This allows it to participate in manageability services with Intel and third-party devices like embedded controllers, sensors, and other devices through the SMBus interface.

Figure 29-1. What is Covered in This Chapter



Table 29-1. References

Document Title	Document ID / Location
System Management Bus (SMBus) Specification, Version 3.0	http://smbus.org/specs/SMBus_3_0_20141220.pdf
Alert Standard Format (ASF) Specification, Version 2.0	https://www.dmtf.org/sites/default/files/standards/documents/DSP0136.pdf
Management Component Transport Protocol (MCTP) Base Specification, Version 1.1.0	https://www.dmtf.org/sites/default/files/standards/documents/DSP0236_1.1.0.pdf

29.1 Signal Descriptions

The signal descriptions are shown in Table 29-2. For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a customer GPIO signals, see Section 39.1, "Directory of Signal Names and Pin Names" on page 993. The Direction/Type column of Table 29-2 is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 29-2. Signal Names

Signal Name	Direction Type	Shared	Description
SMB_HOST_CLK	I, O-OD	Yes	SMBus Clock (SMBCLK)
SMB_HOST_DATA	I, O-OD	Yes	SMBus Data (SMBDAT)

The optional SMBus 2.0 signals, SMBALERT# and SMBSUS#, are not supported on this controller interface.

29.2 Features

- Operates as an SMBus master or slave.
- Supports ARP in the master or slave mode.
- Packet Error Code (PEC) is enabled for SMBus transactions.
- Compatible with certain I^2C master (all commands except read-then-write) and slave (only MTx-to-SRx) modes.
- Status and errors are communicated by polling or interrupts.
- Supports INTx or Message Signaled Interrupt (MSI).

29.3 Architectural Overview

The SMBus Message Transport (SMT) controller has three regions in the configuration space. These are discovered by software in the configuration space as bus 0, device 18 (decimal), function (0). The address offsets and capability IDs of the contents of these regions are:

1. PCI Standard Header
   - Type 0
2. PCI Capabilities List
   - 40h: PCI Express* - Capability ID = 10h
   - 80h: PCI Power Management - Capability ID = 01h
   - 8Ch: Message Signaled Interrupts (MSI) - Capability ID = 05h
   - Various implementation-specific and Intel-reserved registers
3. PCI Express Extended Capabilities List
   - 100h: Advanced Error Reporting (AER) - Extended Capability ID = 0001h

The SMT controller operation is DMA-based in which descriptors and data are exchanged between the SoC hardware and the firmware through system memory. This DMA mode is available for the SMT acting both as the master and target.

As transport layer functionality, SMT transfers messages between the devices on the SMBus segment (to which it is physically connected) and the SoC firmware. The SMT hardware is physically located within the SoC and resides within its PCIe* space. In the PCIe hierarchy, SMT is bus 0, device 18 (decimal), function 0.

Table 29-3 summarizes which SMBus ARP, SMBus, and I2C protocols are supported by the SMT controller.

Table 29-3. List of Supported SMBus ARP, SMBus, and I2C Protocols

Protocol	Supported	
SMBus ARP Commands	**Sent as ARP Master**	**Received as ARP Slave**
Prepare to ARP	Yes	
Reset Device *General and directed*		
Get UDID *General and directed*		
Assign Address		
SMBus ARP Commands	**Sent as ARP Slave**	**Received as ARP Master**
Notify ARP Master	Yes	
SMBus Commands	**Sent as Master**	**Received as Slave**
Quick Command	Yes	Yes
Send Byte	Yes	Yes
Receive Byte	Yes	No
Write Byte/Word	Yes	Yes
Read Byte/Word	Yes	No
Process Call	Yes	No
Block Write	Yes	Yes
Block Read	Yes	Yes
Block Write-Block Read Process Call	Yes	No
SMBus Host Notify	Yes	Yes
I2C Commands	**Sent as Master**	**Received as Slave**
Master-TX writes slave-RX (MTx-to-SRx) *No direction change*	Yes	Yes
Master-RX reads slave-TX (STx-to-MRx)	Yes	No
Combined format, write-then-read *direction change after initial write*	Yes	No
Combined format, read-then-write *direction change after initial read*	No	No

29.4 Controller Characteristics and Operation

29.4.1 SMBus Behavior on PCIe Reset

When power is applied to an SMBus device, it performs default initialization of the internal state as specified in the *System Management Bus (SMBus) Specification, Version 3.0*. The SMBus device interface logic is not affected by PERST#. This normally allows the SMBus to support communications when the PCIe interface cannot.

29.4.2 Addressing and Configuration

An Address Resolution Protocol (ARP) is defined in the *System Management Bus (SMBus) Specification, Version 3.0* as assigning slave addresses to the SMBus devices. It is required that systems that connect the SMBus to PCIe slots implement the ARP for assignment of SMBus slave addresses to the SMBus interface devices on the PCIe add-in cards. The system must execute the ARP on a logical SMBus whenever any PCIe device in an individual slot associated with the logical SMBus exits the $D3_{COLD}$ state. Before executing the ARP, the system must ensure that all ARP-capable SMBus interface devices are returned to their default address state.

29.4.2.1 ARP Nomenclature

The following are some definitions pertaining to SMBus ARP.

Table 29-4. ARP Nomenclature

Term	Definition
Address Resolution Protocol (ARP)	A protocol by which SMBus devices with assignable addresses on the bus are enumerated and assigned non-conflicting slave addresses.
Address Resolved (AR) Flag	A flag bit or state internal to the SoC that indicates whether or not the device slave address has been resolved by the ARP master.
Address Valid (AV) Flag	A flag bit or state internal to the SoC that indicates whether or not the device slave address is valid. This bit must be non-volatile for devices that support the persistent slave address.
ARP Master	The SMBus master executes the ARP and assigns addresses to the ARP-capable slave devices. The SMBus host usually is the ARP master, but under some circumstances another SMBus master assumes the role. Only one active ARP master exists at any time.
Persistent Slave Address (PSA)	An assigned slave address that is retained through the loss of device power.
SMBus Device Default Address	The address of all the ARP-capable slave devices must respond to. After a slave address has been assigned, a device must still respond to commands at the SMBus device default address for ARP management. This address is fixed at 1100 001.
SMBus Host	A specialized SMBus master that provides the main interface to the system CPU. It must be a master-slave and must support the SMBus host notify protocol. At most, one host is in a system.
Unique Device Identifier (UDID)	A 128-bit value that a device uses during the ARP process to uniquely identify itself.

Table 29-5. Device Decodes of AV and AR Flags

Address Valid (AV)	Address Resolved (AR)	Meaning
Cleared	Cleared	The device does not have a valid slave address and participates in the ARP process. This is the POR state for a device that does not support the Persistent Slave Address (PSA) or if it does it has not previously been assigned a slave address.
Cleared	Set	ILLEGAL STATE
Set	Cleared	The device has a valid slave address but still must participate in the ARP process.
Set	Set	The device has a valid slave address that has been resolved by the ARP master. The device does not respond to the Get UDID (general) command. However, it subsequently receives an Assign Address command and changed its slave address accordingly.

29.4.2.2 Unique Device Identifier (UDID) Format

The UDID is a 128-bit value that a device uses during the ARP process to uniquely identify itself.

Table 29-6. UDID Format

Size	Field	Comments
8 bits Most Significant Bit (MSB)	Device Capabilities	Includes the selection of a fixed or dynamic ARP address
8 bits	Version/Revision	
16 bits	Vendor ID	
16 bits	Device ID	
16 bits	Interface	
16 bits	Subsystem Vendor ID	
16 bits	Subsystem Device ID	
32 bits Least Significant Bit (LSB)	Vendor Specific ID	Includes bits to uniquely identify each device UDIDs

The vendor-specific field provides a unique ID for functionally equivalent devices. This field is for devices that otherwise return identical UDIDs for the purpose of the address assignment. A unique ID in this field is required since this device supports an assigned slave address. For a pre-assigned unique ID, at least 24 bits must be unique; however, the full 32 bits is recommended. Uniqueness is important to guarantee that two like devices are identified discretely.

The Vendor Specific ID (VSID) fields of the UDID0 Data Register (UDID0) and the UDID1 Data Register (UDID1) are located in the SMT controller MMIO.

29.4.2.3 ARP Slave Behavior

Figure 29-2. ARP-Capable (Slave) Device Behavior Flow Diagram



With reference to Table 29-7 the ARP slave operates as follows (steps which are shaded are the responsibility of the firmware alone or of the firmware to trigger the hardware).

Table 29-7. ARP Slave Operations (Sheet 1 of 3)

Step		Description
0.	Perform ARP slave initialization.	• [FW[1]] See Section 29.4.2.5, "ARP Initialization Flow" on page 746
1.	After exiting the power-on-reset state, a device that supports PSA goes to step 2 to verify if its slave address is valid. If the device does not support PSA, proceed to step 5.	• [FW] SoC does not support PSA; jump past PSA-related steps to step 5.
2.	A device supporting PSA must check its address valid flag which is non-volatile. If that flag is set then it has previously received an assigned slave address; proceed to step 4. If the address valid flag is cleared then proceed to step 3.	• N/A
3.	Although the device supports PSA the value is currently invalid. The device must clear the address resolved flag to indicate that it has not had its slave address assigned. Proceed to step 6.	• N/A
4.	The device has a valid PSA so it assumes that slave address for now. However, this address has not been resolved by the ARP master so the device must clear its address resolved flag. Proceed to step 6.	• N/A
5.	The device does not support PSA so it must clear its address valid and address resolved flags. Proceed to step 6.	• [FW] De-assert SMTARPCTRL.AV*n*. • [FW] De-assert SMTARPCTRL.AR*n*.
6.	If supported, the device masters the SMBus and sends the Notify ARP Master command. This informs the ARP master that a new device is present. Proceed to step 7.	• [FW] Determine if supported; check SMTARPCTRL.NOTIFYENB. • [FW and HW[2]] Initiate master transaction (see Section 29.4.6.4, "Master Transactions Flow" on page 758).
7.	The device waits for an SMBus packet.	• [FW and HW] Wait
8.	Upon receipt of an SMBus packet the device must first check the received slave address against the SMBus device default address. If a match is present, then proceed to step 12, otherwise proceed to step 9.	• [HW] Match the default address. • [HW] ACK the transaction if received slave address matches device default address.
9.	The received address is not the SMBus device default address so the packet is potentially addressed to one of the device core functions. The device must check its Address Valid bits to determine whether or not to respond. If any of the Address Valid bits are set then proceed to step 10, otherwise return to step 7 and wait for another SMBus packet.	• [HW] Check if any SMTARPCTRL.AV*n* are asserted.
10.	Since the device has a valid slave address it must compare the received slave address to its internal slave address. If a match is present, then proceed to step 11, otherwise return to step 7 and wait for another SMBus packet.	• [HW] Match any of the internal slave addresses. • [HW] ACK the transaction if received slave address matches **any** target address **and** that target Address Valid bit (SMTARPCTRL.AV*n*) is asserted.
11.	The device has received a packet addressed to a core function so it acknowledges the packet and processes it accordingly. Proceed to step 7 and wait for another SMBus packet.	• [FW and HW] Initiate target transaction (see Section 29.4.7.4, "Target Memory Buffer Hardware-Firmware Flow" on page 772).
12.	The device detected a packet addressed to the SMBus Device default address. Check the command field to determine if this is the Prepare To ARP command. If so, then proceed to step 13, otherwise proceed to step 14.	• [FW] Inspects command field and determines how to proceed.
13.	Upon receipt of the Prepare To ARP command the device must acknowledge the packet and make sure its address resolved flag is clear to participate in the ARP process. Proceed to step 7 and wait for another SMBus packet.	• [FW] De-assert SMTARPCTRL.AR*n*.
14.	The device checks the command field to verify if the Reset Device command was issued. If so, then proceed to step 15, otherwise proceed to step 16.	• [FW] Inspects command field and determines how to proceed.

Table 29-7. ARP Slave Operations (Sheet 2 of 3)

Step		Description
15.	Upon receipt of the Reset Device command the device must acknowledge the packet and make sure its address valid (if non-PSA) and address resolved flags are cleared. This allows the ARP master to re-assign all device addresses without cycling power. Proceed to step 7 and wait for another SMBus packet.	• [FW] De-assert SMTARPCTRL.AV*n*. • [FW] De-assert SMTARPCTRL.AR*n*.
16.	The device checks the command field to verify if the Assign Address command was issued. If so, then proceed to step 17, otherwise proceed to step 19.	• [FW] Inspects the command field and determines how to proceed.
17.	Upon receipt of the Assign Address command the device must compare its UDID to the one it is receiving. If any byte does not match then it must not acknowledge that byte or subsequent ones. If all bytes in the UDID compare then proceed to step 18, otherwise return to step 7 and wait for another SMBus packet.	• [HW] Check the command field **only if** received slave address matches device default address. • [HW] If the Assign Address command, then verify each byte of received UDID against all SMT UDIDs. • [HW] NACK the transaction if received UDID fails to match any SMT UDID. ***Note:*** All ARP protocols are directed only to the device default address. ***Note:*** SMT must respond to this command even if its SMTARPCTRL.AR flag is set (i.e., ARP master overwrites a valid and resolved target address). ***Note:*** This also implies the hardware cannot detect an ARP-pending flag to selectively monitor the command field for Assign Address command. ***Note:*** If UDID is NACKed, the hardware is not required to notify the firmware.
18.	Since the UDID matched, the device must assume the received slave address and update its PSA, if supported. The device must set its address valid and address resolved flags; this indicates it no longer responds to the Get UDID command unless it receives the Prepare To ARP or Reset Device commands or is power cycled. Proceed to step 7 and wait for another SMBus packet.	• [FW] Assign the received slave address to the matched UDID. • [FW] Assert SMTARPCTRL.AV*n*. • [FW] Assert SMTARPCTRL.AR*n*.
19.	The device checks the command field to verify if the Get UDID command was issued. If so, then proceed to step 21, otherwise proceed to step 20.	• [HW] Inspects the command field and determines how to proceed.
20.	The device is receiving a directed command. Directed commands must be acknowledged only by slaves with a valid address. If the address is not valid then ignore the packet and return to step 7 and wait for another SMBus packet. If the address is valid then proceed to step 26.	• [HW] Inspects the address valid flag.
21.	Upon receipt of the Get UDID command, the device must check its address resolved flag to determine whether or not it participates in the ARP process. If set then its address has already been resolved by the ARP master so the device proceeds to step 7 to wait for another SMBus packet. If the AR flag is cleared then the device proceeds to step 22.	• [HW] Inspects the address resolved flag and determines how to proceed.
22.	The device returns its UDID and monitors the SMBus data line for collisions. If a collision is detected at any time the device must stop transmitting and proceed to step 7 and wait for another SMBus packet. If no collisions were detected then proceed to step 23.	• [HW] UDID is returned as read data to master.
23.	The device must now check its address valid flag to determine what value to return for the device slave address field. If the AV flag is set then proceed to step 24, otherwise proceed to step 25.	• [HW] Inspects the address valid flag and determines how to proceed.
24.	The current slave address is valid so the device returns this for the device slave address field (with bit 0 set) and monitors the SMBus data line for collisions (i.e., another device driving a 0 when this device is driving a 1). Proceed to step 7 and wait for another SMBus packet.	• [HW] UDID and current slave address are returned as read data to master (as per generic block-read payload).
25.	The current slave address is invalid so the device returns a value of 0xFF and monitors the SMBus data line for collisions. If the ARP master receives the 0xFF value it knows that the device requires address assignment. Proceed to step 7 and wait for another SMBus packet.	• [HW] UDID and 0xFF address are returned as read data to master (as per generic block-read payload).

Table 29-7. ARP Slave Operations (Sheet 3 of 3)

Step		Description
26.	Is this a directed Reset Device command? If so then proceed to step 15. Otherwise proceed to step 27.	• [FW] Inspects the command field and determines how to proceed.
27.	Is this the Get UDID (directed) command? If so then proceed to step 29. Return the UDID information. If not, then proceed to step 28.	• [HW] Inspects the command field and determines how to proceed.
28.	The device has not received a valid command so it must handle the illegal command in accordance with SMBus rules for error handling. Proceed to step 7 and wait for another SMBus packet.	• [FW] Perform error handling.
29.	Return the UDID information and current slave address, then proceed to step 7 and wait for another SMBus packet.	• [HW] UDID and current slave address are returned as read data to master (as per generic block-read payload).

1. FW means Firmware.
2. HW means Hardware.

Table 29-8 identifies the hardware pattern-matching which is required to decode ARP and ordinary SMBus protocols. The UDID matching applies only to the assign address protocol.

Since ARP protocols are typically writes to the ARP slave by the ARP host, the R/W# bit (LSB) of the first byte is usually 0; however, the general and directed forms of Get UDID require the ARP slave to return its UDID to the ARP host, such that the LSB of the first byte after the repeated start is 1. During either Get UDID protocol, the hardware matching must detect the repeated start and subsequently match a slave address of C3h.

Likewise, most ordinary SMBus protocols begin with a write to the slave/target by the master. However, since certain protocols begin with a read to the slave, the hardware matching treats the LSB of the first byte as a (don't care). For those protocols which require the slave to return data to the master, the LSB of the first byte after the repeated start is 1. Therefore, the hardware matching must detect the repeated start and subsequently match a slave address with an appended 1 LSB.

Table 29-8. Hardware Decoding of ARP, SMBus, and I²C Target Transactions

Byte 1 Slave Address[1]	Byte 2 ARP Command	Bytes 4-19 UDID	Hardware-Decoded Protocol
ARP protocols applicable to all SMT UDIDs			
C2h	01h	N/A	Prepare to ARP
C2h	02h	N/A	Reset Device (general)
C2h	03h	N/A	Get UDID (general)
C3h[2]	N/A	N/A	Get UDID (general) —after repeated start
ARP protocols specific to only matched UDID (128 bits)			
C2h	04h	Matches an SMT UDID	Assign Address
ARP protocols specific to only matched slave address (7 bits)			
C2h	{target address, 1}	N/A	Get UDID (directed)
C3h[2]	N/A	N/A	Get UDID (directed) —after repeated start
C2h	{target address, 0}	N/A	Reset Device (directed)
10h	C2h	N/A	Notify ARP master
10h	!= C2h[3]	N/A	SMBus Host Notify
Ordinary SMBus (and I²C) protocol specific to only matched slave address (7 bits)			
{slave address, x}	N/A	N/A	Ordinary SMBus transaction. LSB = x to be protocol agnostic • Quick Command • Send Byte • Write Byte/Word • Block Write • Block Read
{slave address, **1**}[2]	N/A	N/A	Ordinary SMBus transaction. LSB = 1 —after repeated start • Block Read

1. Hardware checking of LSB during start address cycle is controlled by SUSCHKB.IRWST. (Applies to SMBus target addresses, C2h, and 10h.) See also Section 29.4.7.5, "Target Flow" on page 775 and Table 29-20, "Target Transaction Behavior Due to SUSCHKB.IRWST" on page 776 for more implications to the firmware and the hardware regarding IRWST.
2. Hardware checking of LSB during repeated-start address cycle is controlled by SUSCHKB.IRWRST. (Applies to SMBus target addresses and C2h.)
3. For a transaction directed to 10h if the command byte is not C2h then the transaction is SMBus host notify and the command code format is {initiator slave address, 0}.

Certain SMBus protocols are disallowed in the target mode since they violate the hardware-firmware descriptor mechanism. First, the descriptor is passed to the firmware only after the transaction stop; this architecture does not permit the firmware to return a payload within the same transaction. Second, waiting for a descriptor from the firmware requires the hardware to perform excessive SMBus clock-stretching.

Table 29-9 captures the responses of the hardware/firmware under the various combinations of ARP protocol, address and UDID fields, and ARP status flags. The states mentioned refer to Table 29-9.

Table 29-9. Hardware/Firmware Response to SMBus and ARP Protocols

Received ARP Protocol	AV Flag	AR Flag	ARP States (1-8,...)	SoC Hardware and Firmware Response
Ordinary SMBus protocol				
Ordinary SMBus protocol	T	N/A	9, 10, 11	Normal hardware-firmware flow
SMBus block-read	T	N/A	9, 10, 11	The hardware returns the specified number of bytes from the hardware buffers.
ARP protocol				
Prepare to ARP	N/A	N/A	12, 13	Normal hardware-firmware flow
Reset Device (general)	N/A	N/A	12, 14, 15	Normal hardware-firmware flow
Assign Address	N/A	N/A	12, 14, 16, 17, 18	Normal hardware-firmware flow
Get UDID (general)	N/A	T	12, 14, 16, 19, 21	The hardware does NACK the ARP command byte to indicate it has a valid assigned slave address (ARP is complete).
Get UDID (general)	T	F	12, 14, 16, 19, 21, 22, 23, 24	The hardware returns its UDID and corresponding slave address.
Get UDID (general)	F	F	12, 14, 16, 19, 21, 22, 23, 25	The hardware returns its UDID and 0xFF for its address.
Reset Device (directed)	T	N/A	12, 14, 15, 19, 20, 26, 15	Normal hardware-firmware flow
Get UDID (directed)	T	N/A	12, 14, 16, 19, 20, 26, 27, 29	The hardware returns its UDID and corresponding slave address.
None of the above ARP protocols	N/A	N/A	12, 14, 16, 19, 20, 26, 27, 28	Normal hardware-firmware flow (error handling situation)

The hardware will ACK all valid transactions above. An exception is when processing the assign address protocol, if the received UDID does not match any internal UDID the hardware begins NACKing after the first unmatched byte. Another exception is that if the address resolved flag is asserted and a Get UDID (general) command is received, the command byte is NACKed. Finally, a PEC failure causes a transaction to be NACKed.

In both directed protocols, Get UDID (directed) and reset device (directed), the second byte, or ARP command byte, consists of the target slave address with an appended 0 or 1 to denote a reset device or Get UDID protocol, respectively. Therefore, the hardware uses address bits [7:1] for address comparison and LSB bit 0 to determine the protocol.

Since the SMT supports multiple UDIDs, during the ARP process it participates in the Get UDID (general) and assign address protocols once for each UDID such that each UDID has a slave address which is resolved by the ARP master.

For GPBR and all both Get UDID flavors, the transaction is descriptor-only with no target data written to memory, and the descriptor is managed by the hardware.

Note: The firmware implements a time-out mechanism such that if the SoC issues the Notify ARP Master command and the ARP master does not respond within a particular time period, then the SoC re-issues the Notify ARP Master command. It is implemented to comply with the *System Management Bus (SMBus) Specification, Version 3.0* for bus timing.

29.4.2.4 ARP Master Behavior

Figure 29-3. ARP Master Behavior Flow Diagram



The ARP master must always execute the ARP when it enters the working state and anytime it receives an SMBus status change indication (due to device addition or removal). The process begins with the ARP master issuing the Prepare To ARP command. In all cases the ARP master must be able to resolve addresses when it receives the Notify ARP Master command.

Since SMBus devices join the system without a corresponding system reset (i.e., a hot-plug event), the ARP master optionally chooses to issue the Get UDID (general) command at least once every 10 seconds to discover newly added devices that require address resolution but which do not support the Notify ARP Master command. No device whose AR flag is set responds to this command. However, a newly added device enters the system with a power-up reset, which resets its AR flag; it responds to a Get UDID (general) command with its UDID. The host chooses to assign such a newly added device a non-conflicting address or chooses to re-ARP the entire bus.

Until the ARP process is complete, the ARP master must not wait more than 2 seconds before issuing a Get UDID (general) command after issuing the previous Get UDID (general) command. This restriction is important to allow another SMBus master to determine when it is safe to do an enumeration of the bus.

Table 29-10. ARP Master Operation (Sheet 1 of 2)

Step		Description
0.	Perform ARP master initialization.	• [FW] See Section 29.4.2.5, "ARP Initialization Flow" on page 746.
1.	Upon starting, the ARP master initializes its used address pool. Initially this consists of the slave addresses of fixed-address SMBus devices known to the ARP master and reserved addresses (as defined in *SMBus 2.0 Specification*).	• [FW]
2.	Send the Prepare To ARP command.	• [FW]
3.	Check for an acknowledgment for all bytes in the previous packet. If any bytes were not acknowledged then the ARP master assumes that no ARP-capable devices are present and therefore consider the ARP process complete; proceed to step 4. If all bytes were acknowledged then go to step 6.	• [FW]
4.	The ARP master found no response to the Prepare To ARP command so it assumes that no ARP-capable devices are present in the system at this time. The ARP master periodically re-issues the Prepare To ARP command to discover any ARP-capable devices added. Proceed to step 5.	• [FW]
5.	Wait for an SMBus packet. If a packet is received proceed to step 15.	• [FW]
6.	Send the Get UDID command.	• [FW]
7.	Check for an acknowledgment for the first three bytes and verify that the byte count value received is 0x11. If not, then the ARP master assumes that an ARP-capable device(s) is no longer present and therefore consider the ARP process complete; proceed to step 4. Otherwise proceed to step 8.	• [HW and FW] HW verifies the byte count before sending descriptor to FW.
8.	Check the value of the device slave address received. If 0xFF then proceed to step 11 since this device does not possess a valid slave address. Otherwise proceed to step 9.	• [FW]
9.	Determine if this device has a fixed slave address. If bits 127 and 126 of the UDID are 00b then it has a fixed address, so proceed to step 12. Otherwise proceed to step 10.	• [FW]
10.	The device possesses a valid slave address. However, the ARP master must check this address against the used address pool to ensure that no other device has already been assigned the same address. If the received device slave address is found in the used address pool then proceed to step 11. If not, then the device keeps its current slave address but needs acknowledgment from the ARP master; proceed to step 12.	• [FW]

Table 29-10. ARP Master Operation (Sheet 2 of 2)

Step		Description
11.	Select a slave address that is not in the used address pool and proceed to step 12.	• [FW]
12.	Send the Assign Address command with the UDID returned by the device in the Get UDID command packet.	• [FW]
13.	Check for acknowledgment of all bytes in the Assign Address command packet. If any byte was not acknowledged then the ARP master assumes the device is no longer present; proceed to step 6 to determine if more devices require address resolution. If all bytes were acknowledged then the ARP master assumes that the device has accepted the address assignment; proceed to step 14.	• [HW and FW] HW monitors slave ACK before sending descriptor to FW.
14.	The device now has a valid slave address. The ARP master must add this address to the used address pool. Proceed to step 6 to determine if more devices require address resolution.	• [FW]
15.	The ARP master checks if the received packet was the Notify ARP Master command. If so, then it must execute the ARP to resolve the address for the newly added device(s); proceed to step 6. If not, then proceed to step 16.	• [FW]
16.	The ARP master received a non-ARP related packet. Process it accordingly and proceed to step 5.	• [FW]

These steps cover the case when the ARP master has exited a reset state. Since ARP supports hot-plug, the master must be prepared to execute the ARP at any time; step 15 covers the case when a device issues the Notify ARP Master command. If during the ARP process, a previously detected device is now not discovered, then the slave address associated with that device is removed from the used address pool.

The diagram does not consider bus time-out mechanisms or retries. These are implemented to comply with SMBus timing requirements.

29.4.2.5 ARP Initialization Flow

The firmware initializes the SoC for ARP protocols before any SMBus traffic. Because the SMT master behavior applies to both master-transmitter (e.g., ARP host issuing a prepare to ARP) and slave-transmitter (e.g., ARP slave issuing a host notify), and SMT target behavior applies to both master-receiver (e.g., ARP host receiving a host notify) and slave-receiver (e.g., ARP slave receiving a prepare to ARP), many ARP initialization steps are common to host and slave devices.

The exception is UDID assignment. This pertains only to ARP slaves.

Table 29-11. ARP Initialization Flow (Sheet 1 of 2)

Initialization Flow for an ARP Slave	Initialization Flow for the ARP Host
Configure the SoC bootstrap configuration information programmed fields. • Preset UDID fields are loaded from the SoC bootstrap configuration information. • Also, the SoC bootstrap configuration information is loaded to configure the unique UDID field (VSID)—the hardware permutes the SoC bootstrap configuration information to program multiple UDIDs as necessary. ***Example:*** To support two functions each with two UDIDs, combine three hard-coded LSBs with a sufficient number of SoC bootstrap configuration information bits (n) to distinguish all SoC devices. **Bit Fields:** VSID = [31:32-*n*] [32-*n*-1:3] [2:1] [0] VSID = SoC bootstrap configuration information bits static-bits function UDID Fn0/UDID0 = {SoC bootstrap configuration information bits}{static bits}{00}{0} Fn0/UDID1 = {SoC bootstrap configuration information bits}{static bits}{00}{1} ... Fn1/UDID1 = {SoC bootstrap configuration information bits}{static bits}{01}{1} The SoC bootstrap configuration information bits are shared by all functions and UDIDs. • Preset other fields based on the SoC bootstrap configuration information: GPBRCTRL.GPTRADR, SPGT.SPD, TPOLICY.ADDR0_EN, TPOLICY.ADDR1_EN, and TPOLICY.Host_SMBADDR_EN.	Configure the SoC bootstrap configuration information programmed fields. • N/A • N/A • Preset other fields based on the SoC bootstrap configuration information: GPBRCTRL.GPTRADR, SPGT.SPD, TPOLICY.ADDR0_EN, TPOLICY.ADDR1_EN, and TPOLICY.Host_SMBADDR_EN.
Program SMBus address to any fixed-address target. • Program TACTRL.ADDR0 if required based on UDID0.DEVCAP field. • Program TACTRL.ADDR1 if required based on UDID1.DEVCAP field.	
Verify transaction status flags (no invalid state flags). • Verify all 0s in fields TSTS.IP and MSTS.IP. • Likewise, verify numerous error-status registers.	
Program descriptor base address and buffer entries. • Program MDBA and MDS. • Program TBBA and TBS. • Program SMTICL.	
Program head and/or tail pointers. • Program MCTRL.FMHP and MSTS.HMTP. • Program HTHP.HTBHP and FTTP.FTBTP.	

Table 29-11. ARP Initialization Flow (Sheet 2 of 2)

Initialization Flow for an ARP Slave	Initialization Flow for the ARP Host
Enable (unmask) interrupts from the hardware due to certain conditions. • Assert/de-assert ERRINTMSK, ERRAERMSK, TCTRL.TIE, MCTRL.MEIE.	
Configure policies. • Program RPOLICY.TBRCLKCNT, RPOLICY.COLRTRY, RPOLICY.TBRBCLK, RPOLICY.RETRY.	
Configure GPBR • Set GPBRCTRL.EN. • Assert/de-assert GPBRCTRL.PECEN. • Assert/de-assert GPBRCTRL.HWCLRDIS. • Program GPBRCTRL.BC. • Program GPBRCTRL.CMD. • Program GPBRCTRL.GPTRADR.	

29.4.3 SMT System Usage Models

The SMT architecture takes into account various usage models as envisioned on the SoC-based platforms. The focus of the architecture is to keep the hardware overhead low for supporting the various usage models and protocols:

- SMBus ARP mastering or ARP target
- Embedded Controller (EC) on the SMBus communicating with the SoC

29.4.4 SMT Security Requirements

The SMT has no security requirements.

29.4.5 SMT Timing Modes

The SMT currently supports three different timing modes: standard (up to 100 kHz), fast-mode (up to 400 kHz), and fast-mode plus (up to 1 MHz). The timing requirements for fast-mode and fast-mode plus are found in the I^2C industry specification.

The following section covers design targets for the various timing modes in various operating conditions. The SMT controller does not contain dynamic timing adjustment to account for varying bus loads or pull-up resistor selections, thus SMT is designed and have default settings to meet the specification in the worst-case scenarios. This comes at the cost of not having optimal frequency for any given timing mode in nominal conditions.

Note: Devices also stretch the clock low thus reducing the frequency. These timing estimates are assuming the device is not further impacting the timings.

Table 29-12. SMT Timing Mode Maximum Clock Frequency Ranges

Mode	Maximum Clock Frequency Range
Standard	90-100 kHz*
Fast Mode	350-400 kHz*
Fast Mode Plus	750-1000 kHz*

*Timing assumes the platform design is within the specification for maximum rise time allowed requiring appropriate Rpullup value selection for the given capacitive load on the bus.

29.4.6 SMT as Master

The SMT as the initiator provides the hardware for the internal agents inside the SoC to send/receive data across the SMBus. Due to the various usage models that SMT supports, the hardware support exists for initiating reads/writes from/to external devices on the SMBus. The SMT has the hardware capability to transport them over the physical SMBus and report the status back to the firmware.

Note: The firmware must ensure the data in the transmit data buffers is arranged in the order that it wants to send on the bus, i.e., data pointed to by the Tx data pointer are sent first on the SMBus, then the next byte, etc.

With respect to the receive buffer, data are written to memory as-is received from the physical SMBus, i.e., the first byte received is placed in the lowest address, then the next byte, etc.

29.4.6.1 Hardware Buffering for Master Support

The hardware implements a 240-byte buffer which it uses to queue transactions (both master-transmitter and master-receiver) as a descriptor-based master. Though the hardware supports a maximum read/write of 240 bytes, the firmware driver restricts the payloads to <=32B to compliance SMBUS spec. Please see Section 29.4.6.3.2, “PEC-Enabled SMBus Transactions” for details.

The storage queues are not shared between the master and the target. Both logical sides function independently without dependency on each other.

Note: Although SMT theoretically supports master-initiated write and read cycles of arbitrary length, the practical expectation is that the transaction size does not exceed 32B with Intel firmware driver.

Note: When SMT as master sends I2C write or read, the hardware can support a maximum payload 240 bytes with custom external driver.

29.4.6.2 Master Descriptor

The master descriptor is a ring buffer of individual descriptors set up by the firmware as shown in Figure 29-4. The descriptor ring buffer is pointed to by the base (MDBA) and the size is indicated by the MD Size register (MDS). See register definitions for details. Individual descriptors have a 64-bit pointer into the data buffer with an expected transmit and/or receive length programmed in the control field of the descriptors.

The hardware updates the status WB field in Figure 29-4 and Figure 29-5. See Table 29-13, "Master Descriptor Field Descriptions" for detailed descriptions. The remaining three Dwords are updated by the firmware.

The firmware always leads and points by the FWmHeadPtr (MCTRL.FMHP). The hardware always points by the HWmTailPtr (MSTS.HMTP).

Figure 29-4. Master Descriptor Ring Buffer



Figure 29-5. Master Descriptor Format



Table 29-13. Master Descriptor Field Descriptions (Sheet 1 of 3)

Dword #	Bit #	Field	Description
0	31	SOE	**Stop On Error**: This bit is set to 1 to direct the hardware that if a descriptor-based master cycle results in an unsuccessful transaction on SMBus, the hardware must clear the Start/Stop bit (MCTRL.SS) and stop the engine. If this bit is clear if the hardware encounters an error while sending a transaction on SMBus, it sets the Master Error Status bit (MSTS.MEIS) and continues to process the next descriptor in the queue.
0	30	INT	**Interrupt**: This bit is set to 1 to direct the hardware that it must generate an MSI to the firmware when it has completed the requested transaction successfully. This interrupt is generated only after the status Dword of the descriptor is written back to memory. Interrupts due to unsuccessful transactions on the SMBus are not affected by this bit. If this bit is clear and the transaction is successful on the SMBus, no interrupt is generated; however, the firmware polls the MSTS.MIS bit. ***Note:*** When using legacy interrupts, this bit has no effect; a legacy interrupt is always generated even if not requested by the master descriptor (firmware).
0	29	I^2C	I^2C **Enable:** This bit is set to 1 to indicate the hardware must perform the transaction using I^2C protocol.
0	28	PEC	**Packet Error Code**: This bit is set to 1 to indicate the hardware must append CRC (or PEC) as the master of the requested transaction if it is a write or check received CRC (PEC) of the requested transaction if it is a read. PEC is calculated over the entire message (including address and read/write bits) and supplied by the device which puts out the last-data byte of the message.
0	27	FAIR	**Fair**: This bit is set to 1 to indicate if the hardware is able to successfully win arbitration on the bus and master the transaction, it must set its internal fairness flag. This allows a mechanism for fairness on the SMBus per *MCTP Specification*.
0	26	BLK	**Block**: Set to 1 by the firmware to indicate the hardware must perform a block transaction on the bus. The hardware determines one of three block transactions based on the following fields {BLK, C/WRL and R/W}. 100: Perform an SMBus block write. 111: Perform an SMBus block read. 101: Perform an SMBus block process call. Others: Reserved
0	25	Reserved	Reserved
0	24	C/WRL	**Command/Write Length**: Set to 1 by the firmware when it has overloaded the write length field with the command code of the SMBus transaction.
0	23:16	RDLNTH	**Read Length**: Indicates the number of bytes the hardware receives from the target, and writes to the receive data buffer one-based counting, i.e., the value 0h means 0 bytes of receive data and the value Ah means 10 bytes of receive data. The maximum read length currently supported by the hardware is 240 bytes due to its internal buffer size.
0	15:8	WRLNTH	**Write Length**: Indicates the number of bytes the hardware transmits as a master (except the first address byte, byte count, and any subsequent address bytes for reads) one-based counting, i.e., the value 0h means 0 bytes of transmit data and the value Ah means 10 bytes of transmit data. The maximum write length supported by the hardware is 240 bytes including address due to the size of its internal buffer. The byte count for the SMBus transactions is calculated by the hardware based on the write length field. Example: If WRLNTH = 8, the hardware calculates byte count = 7 and sends on the SMBus. The WRLNTH field itself contains command code and 7 bytes of data. When the C/WRL flag is set, this field contains the command code of the SMBus transaction.

Table 29-13. Master Descriptor Field Descriptions (Sheet 2 of 3)

Dword #	Bit #	Field	Description
0	7:1	TGTADDR	**Target Address**: 7-bit address field indicating the target SMBus/I^2C address. ***Note:*** See Section 29.4.6.7, "Write Disabling to DIMM SPD EEPROM Addresses" on page 764 for restrictions on writes to certain addresses.
0	0	RW	**Read/Write**: Set to 1 to indicate a read request. Cleared to 0 to indicate a write request. Combinations of this bit and the WRLNTH, RDLNTH, and C/WRL fields are decoded by the hardware to distinguish between various types of SMBus cycles and I^2C cycles. ***Note:*** For SMBus Process Call commands, this bit must always be cleared to 0. ***Note:*** See Section 29.4.6.7, "Write Disabling to DIMM SPD EEPROM Addresses" on page 764 for restrictions on writes to certain addresses.
1	31:24	TxBytes	**Transmitted Bytes**: The hardware updates this field to indicate how many bytes transmitted by it were ACKed by the target. This field provides the firmware the ability to reconstruct which particular byte was NACKed by the target. This count is one-based and includes all the bytes sent by the hardware which are ACKed by the target including the address. Value of 0 means address phase NACKed or collision on the address phase.
1	23:16	RXBytes	**Received Bytes**: The hardware indicates how many bytes of received data it is writing to memory (into the data buffer). The count is one-based, i.e., the value 0h means 0 bytes of data. The hardware limitation is for a 240-bytes data buffer implying that for a maximum SMBus legal block read of 32 bytes with the PEC, it forwards to memory the 240 bytes of data; the byte count received. ***Note:*** PEC is not forwarded to the firmware, since the firmware explicitly enables/disables PEC per master transaction. The hardware returns the PEC check in the CRC field, which the firmware inspects.
1	15	Reserved	Reserved
1	14:12	COLRTRY	**Collision Retry**: The hardware indicates the number of collisions on the last attempt before retiring the descriptor.
1	11:8	RETRY	**Retry Count**: The hardware indicates the count with the number of retries attempted before retiring the descriptor.
1	7	LPR	**Large Packet Received**: The hardware sets this bit to indicate that more data was sent by the target than expected by the firmware and exceeds the allocated receive data space (TRxCTRL.MRxB). The hardware must DMA the data to the buffer in memory in the space allocated, dropping the extra bytes.
1	6	COL	**Collisions**: Set to 1 by the hardware to indicate that failure was due to number of collisions exceeding the collision retry count (RPOLICY.COLRTRY).
1	5	CLTO	**Clock Low Time Out**: Set to 1 by the hardware to indicate unexpected time-out seen on the bus during the course of the request. This bit being set indicates that SMB clock signal was held low by the external device for the count as programmed in CNT.
1	4	CRC	**CRC Error:** Set to 1 by the hardware to indicate CRC error[1] on the request. For read requests with PEC, the hardware sets this bit if the PEC received from the target does not match the PEC calculated by the hardware. For write requests with PEC, the hardware sets this bit if the target NACKs the PEC byte.
1	3	NAK	**NACK Received:** Set to 1 by the hardware to indicate unexpected NACK asserted by the target.
1	2:0	Reserved	Reserved
1	0	SCS	**Success**: Set to 1 by the hardware to indicate that the cycle was transferred successfully. Zero indicates that some error was encountered and other bits in the status indicate the error.

Table 29-13. Master Descriptor Field Descriptions (Sheet 3 of 3)

Dword #	Bit #	Field	Description
2	31:0	DPTR	**Data Pointer:** Byte-aligned pointer to the starting location of the data buffer. The hardware reads from memory and transmits exactly as many bytes as is indicated by the WRLNTH field. This does not include the address fields of the message (i.e., start address/repeated start address) and byte count if any. The hardware is expected to write to memory exactly as many bytes as is indicated by the RDLNTH field (unless an error condition exists and the target fails to provide the expected number of bytes, in which case the appropriate error bits are set).
3	63:32	DPTR	

1. The *System Management Bus (SMBus) Specification, Version 3.0* is vague about the condition of the CRC error when the master is initiating a READ and the target provides the CRC. Irrespective of the fact that the CRC is correct or incorrect, the master must NACK the cycle and assert STOP. The SMT hardware informs the firmware of the incorrectness of the received CRC and leaves it up to the firmware for further action. See the *System Management Bus (SMBus) Specification, Version 3.0*.

29.4.6.3 Master Descriptor Usage

Descriptors are used for SMT transactions the are initiated by the firmware. The hardware decodes the I^2C, PEC, WRLNTH, and RDLNTH fields to differentiate between the types of SMBus transactions (see Section 29.4.6.3.1, "SMBus Protocol Transfers" on page 754) and I^2C transactions (see Section 29.4.6.3.3, "I^2C Protocol Transfers" on page 757).

The master transaction flow is defined in Section 29.4.6.4, "Master Transactions Flow" on page 758.

The master retry flow is defined in Section 29.4.6.6, "Master Retry Flow" on page 762.

29.4.6.3.1 SMBus Protocol Transfers

Table 29-14 illustrates how the hardware uses the control information in the descriptor.

Note:

1. The firmware must ensure that the I^2C bit is 0 when initiating SMBus transactions.
2. Target address and R/W# indication is taken from the descriptor.
3. PEC-enabled write transactions proceed in the same manner except that the hardware appends PEC after the last data phase.
4. PEC-enabled read transactions instruct the hardware to check CRC and report the status to the firmware.

Note: See Section 29.4.6.7, "Write Disabling to DIMM SPD EEPROM Addresses" on page 764 for restrictions on writes to certain addresses.

Table 29-14. SMBus Transaction Encodings (Sheet 1 of 2)

SMBus Command	BLK	C/WRL	WRLNTH	RDLNTH	RW (0=W; 1=R)	DPTR (Points to TX Data)	DPTR (Points to RX Data)
Quick Command	0	0	0	0	Read/ Write	X	X
Send Byte	0	1	Command	0	0	X	X
Receive Byte	0	0	0	1	1	X	Valid and points to a buffer where the received byte is placed.
Write Byte	0	0	2	0	0	Valid and points to 2 bytes (command and 1-data byte).	X
Write Word	0	0	3	0	0	Valid and points to 3 bytes (command and 2-data bytes).	X
Read Byte	0	1	Command	1	1	X	Valid and points to a buffer where the received byte is placed.
Read Word	0	1	Command	2	1	X	Valid and points to a buffer where the received 2 bytes are placed.
Process Call	0	0	3	2	0	Valid and points to 3 bytes (command and 2-data bytes).	Valid and points to a buffer where the received 2 bytes are placed.

Table 29-14. SMBus Transaction Encodings (Sheet 2 of 2)

SMBus Command	BLK	C/WRL	WRLNTH	RDLNTH	RW (0=W; 1=R)	DPTR (Points to TX Data)	DPTR (Points to RX Data)
Block Write (1 byte)	1	0	2	0	0	Valid and points to 2 bytes (command and 1-data byte); the byte count is calculated by the hardware.	X
Block Write (2 bytes)	1	0	3	0	0	Valid and points to 3 bytes (command and 2-data bytes); the byte count is calculated by the hardware.	X
Block Write (3 bytes or more)	1	0	4 or more[1]	0	0	Valid and points to at least 4 bytes (command and 3-data bytes); the byte count is calculated by the hardware.	X
Block Read (1 byte)	1	1	Command	2	1	X	Valid and points to a buffer where the received 2 bytes are placed (byte count, data byte 1).
Block Read (2 bytes or more)		1	Command	3 or more[2]	1	X	Valid and points to a buffer where at least the received 3 bytes are placed (byte count, data byte 1, etc.).
Block Write-Block Read Process Call[3] (write 1 byte, read N)	1	0	2	N[4]+1	1	Valid and points to 2 bytes (command and 1-data byte); the byte count is calculated by the hardware.	Valid and points to a buffer where at least the received (N+1) bytes are placed (byte count, N data bytes).
Block Write-Block Read Process Call (write 2 bytes, read N)	1	0	3	N+1	1	Valid and points to 3 bytes (command and 2-data bytes); the byte count is calculated by the hardware.	Valid and points to a buffer where at least the received (N+1) bytes are placed (byte count, N data bytes).
Block Write-Block Read Process Call (write >2 bytes, read N)	1	0	4 or more	N+1	1	Valid and points to at least 4 bytes (command and 3-data bytes); the byte count is calculated by the hardware.	Valid and points to a buffer where at least the received (N+1) bytes are placed (byte count, N data bytes).

1. Per the *System Management Bus (SMBus) Specification, Version 3.0*, having a block write of exactly 3 bytes can occur. However, a block write of 3 bytes and a write word have identical signaling on the bus.
2. Per the *System Management Bus (SMBus) Specification, Version 3.0*, having a block read of exactly 2 bytes can occur. However, a block read of 1 data byte (address, command, byte count = 1, followed by 1 data byte) and a read word from the target (address, command, DataByte1, DataByte2) have identical signaling on the bus.
3. The sum of the data bytes in the write and read phases must not exceed 32 bytes per the *System Management Bus (SMBus) Specification, Version 3.0*.
4. N must be greater than 1.

29.4.6.3.2 PEC-Enabled SMBus Transactions

For writes going out from the SMT to the SMBus, the PEC is calculated by the hardware and appended. For reads, the PEC byte is received from the target and verified by the hardware (incorrectness notification is provided to the firmware by the status bits). The PEC byte is not sent to the buffer.

Note: Firmware-specific:

1. If the firmware wants to send a large amount of data (more than 32 data bytes without counting command byte and byte count) to a target using the SMBus 2.0 protocol and indicates to the hardware to send data using block write protocol, the firmware is responsible to break the data into multiple packets and set up individual descriptors for each packet.
2. The firmware honors all SMBus 2.0 rules for transactions of write, read, transcribe of the total data transfer on the SMBus being not more than 32 bytes (including BlockWr-BlockRd process call).
3. The firmware sets the PEC bit when initiating a PEC-accompanied read from a target so that the hardware verifies and reports PEC accuracy, or when initiating a PEC-accompanied write transaction so that the hardware automatically appends the PEC byte.
4. The firmware must clear the I^2C bit when initiating the SMBus transactions.
5. Because a single pointer is used, for SMBus transactions which both transmit and receive data (i.e., process call and block write-block read process call), the received data overwrites the transmitted data. Before beginning the transaction, the firmware must copy the transmit data if the transmit data are preserved after the transaction.

29.4.6.3.3 I²C Protocol Transfers

For I²C transactions, Table 29-15 illustrates how the hardware uses the control information in the descriptor. The following are the I²C support limitations:

1. Support is limited to 7-bit addressing mode only.
2. Write-read combined format is supported with SMT as a master.
3. As a target, the hardware supports only writes initiated by an external master.
4. When the SMT sends/receives I2C write/read, Hardware supports payloads any size up to 240B.

Table 29-15. I²C Commands

I²C Command	C/WRL	WRLNTH	RDLNTH	RW (0=W; 1=R)	DPTR (points to TX data)	DPTR (points to RX data)
I²C Writes (MTx-to-SRx)	1	Command (1 byte of write data)	0	0	X	X
I²C Writes (MTx-to-SRx)	0	2 or more	0	0	Points to the transmit buffer containing at least 2 bytes of write data.	X
I²C Reads (STx-to-MRx)	0	0	1 or more	1	X	Points to the receive buffer where the receive data are placed.
I²C Combined Format (write followed by read)	1	Command (1 byte of write data)	1 or more	0	X	Points to the receive buffer where the receive data are placed.
I²C Combined Format (write followed by read)	0	2 or more	1 or more	0	Points to the transmit buffer containing at least 2 bytes of write data	Points to the receive buffer where the receive data are placed.

Notes:
1. This table assumes the target address is programmed in the descriptor and is not part of the WRLNTH field.
2. The I²C bit must be set for all I²C transactions.
3. PEC is not supported for any I²C transaction.
4. The BLK bit must be 0 for all I²C transactions.

29.4.6.4 Master Transactions Flow

All master transactions on the physical SMBus pins use descriptors. The high-level flow typically is:

1. The firmware sets the data structures in memory.
2. The firmware programs the descriptors and the associated hardware.
3. The firmware sets the Start bit to initiate the transactions.
4. The hardware processes the descriptor, first setting the InProgress bit, and completes the transaction.
5. The hardware writes data back to memory (if any).
6. The hardware writes back the status to memory for the processed descriptor.
7. If no more descriptors are processed, the hardware clears the InProgress bit.

29.4.6.4.1 Firmware Assumptions

The assumption is an SMT firmware driver exists that understands the SMT hardware register interface and the usage for sending and receiving SMBus messages.

29.4.6.4.2 Initialization

1. The firmware allocates a 64B aligned buffer in memory to be used as the master descriptor ring buffer. Each descriptor is 16B long.
2. The firmware then programs up the MD Base Address (MDBA) register with the lower memory address of the descriptor ring buffer, and MD Size (MDS) register containing the number of descriptors in the ring.
3. The firmware initializes the FWmHeadPtr (MCTRL.FMHP) and HWmTailPtr (MSTS.HMTP) by writing all 0 into it.
4. The firmware also programs interrupts as needed.

Note: The firmware schedules a master transaction in the descriptor ring buffer if the buffer is not full. The descriptor ring buffer is full if (FWmHeadPtr == HWmTailPtr - 1). The –1 subtraction here needs to account for buffer utilization of N-1 for an N-deep buffer.

29.4.6.4.3 Hardware-Firmware Flow

When the firmware driver has to initiate a transaction on the SMBus, and the descriptor ring buffer is not full, the following steps are performed:

1. The firmware programs a 16B descriptor with the attributes of the transaction in memory.
2. The firmware increments the FWmHeadPtr register.
3. The firmware then sets the Start bit (MCTRL.SS) in the hardware.
4. The hardware continuously checks if a descriptor needs to be processed by checking (FWmHeadPtr != HWmTailPtr):
   a. Buffer empty condition: MSTS.HMTP = MCTRL.FMHP
   b. Buffer full: MCTRL.FMHP = MSTS.HMTP-1 or MCTRL.FMHP-MSTS.HMTP = MDS
   c. Buffer wrap condition: When MSTS.HMTP = MDS, and MCTRL.FMHP has already wrapped around, i.e., >= 00h, the hardware reads the 16B descriptor, processes it and if the criteria to increment the pointer are met, it wraps to 00h.
5. If a descriptor (see Section 29-6, "Hardware-Firmware Flow Diagram—DMA Mode" on page 760) is available, the hardware first sets the InProgress bit (MSTS.IP), and then reads the 16B descriptor from memory by combining (MD Base + HWmTailPtr) from which it:
   a. Decodes the control Dword for transaction type and other attributes.
   b. Loads the write data and read data pointers as required.
   c. For writes, the hardware fetches data from the memory pointed to by the DPTR and transmits on the wire. For reads, the hardware stores the DPTR pointer so it can Direct Memory Access (DMA) the data to that address when data is provided by the target.
6. Once the transaction is completed, the hardware does a status write back to the status WB Dword.
7. The hardware then increments HWmTailPtr and sends the interrupt to the firmware if enabled to do so.
   a. Before issuing the MSI, the hardware denotes the master completion in SMTICL and any error status.
8. The hardware then clears the InProgress bit to indicate it has completed processing of the descriptor.
9. The hardware then checks if the Start bit is set. If so, flow follows from #4, or else from #1.

Figure 29-6. Hardware-Firmware Flow Diagram—DMA Mode



29.4.6.5 Clearing of the Start Bit

Under certain conditions, the hardware clears the Start bit (MCTRL.SS).

The hardware clears this register for the following fatal error scenarios:

- The transaction is unsuccessful on the final retry (if enabled), including collisions.
- The hardware receives unsuccessful completion on the internal SoC I/O fabric.

The hardware clears this register for the following non-fatal scenario:

- Master descriptor Stop-on-Error (SOE) bit was set and the transaction was unsuccessful.

The firmware clears the Start bit when it kills a master transaction:

1. The firmware clears MCTRL.SS.
2. The firmware sets GCTRL.KILL.
3. The firmware polls MSTS.IP; the transaction is killed when the bit is detected as cleared.

29.4.6.6 Master Retry Flow

The hardware contains separate timers and counters to auto-retry unsuccessful SMBus cycles that it masters on the SMBus.

Two counters for time between retries and retries due to collision are on the bus. Any failed cycle due to a collision first exhausts the collision counter before decrementing the retry counter. The time between retries is maintained only between two successive transaction retries and not between two successive retries due to a collision.

The high-level flow in the pseudo code is:

```
//Master Transaction begin

MASTER_FLOW

// All registers are defined in RPOLICY register

RELOAD RETRY

// Collision retries

COLRTRY

// Time between retries

TBR

While (RETRY >= 0) {

    RELOAD TBR

    RELOAD COLRTRY

    Send Cycle on SMBus

    While (SMBus COLLISION & (COLRTRY > 0)) {

        COLRTRY = COLRTRY - 1

        WAIT for SMBus IDLE

        Send Cycle on SMBus

    }

    If (SMBus ACK) {

    // Successful cycle

    Update Status in descriptor and WB to memory

    Send Interrupt if enabled

    GOTO MASTERFLOW and wait for new cycle

        BREAK

    } else if

    // Unsuccessful cycle

    (((RETRY == 0) & SMBus NACK) || SMBus Timeout) {

    Update Status in descriptor and WB to memory
```

```
    Set Master Error and send MSI (if enabled) after updating SMTICL

    Clear DMA Start/Stop Bit

GOTO MASTERFLOW and wait for FW to set Start bit

    BREAK

    } else if (SMBus NACK & (RETRY > 0)){

        RETRY = RETRY - 1

        CNTDOWN TBR

        WAIT for TBR to expire

    }

}
```

29.4.6.7 Write Disabling to DIMM SPD EEPROM Addresses

Although this controller is not intended to participate in the DIMM Serial Presence Detect (SPD), an attacker connects its data and clock lines to the segment which includes the SPD EEPROM and mounts an attack. To prevent this, a write disable (MCTRL.SPDDIS) is introduced. If SPDDIS is deasserted, writes are not restricted; however, if SPDDIS is set then writes to the address range A0h-AEh are blocked and an error is flagged. Writes to addresses outside the range A0h-AEh are not affected by SPDDIS, and reads are never affected.

Table 29-16. DIMM SPD EEPROM Write-Disable Mechanism

Target Address [7:4]	Target Address [0] (Read/Write Operation)	SPD Disable Bit (MCTRL.SPDDIS)	SMBus Behavior
Ah	0 (write)	0 (enabled)	Allow writes to addresses A0-AEh.
Ah	0 (write)	1 (disabled)	Deny writes to addresses A0-AEh and log error (ERRSTS.SPDWE).
Ah	1 (read)	Any	Allow reads to addresses A0-AEh.
!= Ah	Any	Any	Allow writes and reads.

The SPDDIS is read-write-once, and the BIOS Memory Reference Code (MRC) is expected to set this bit when SPD is complete. Since the SMBus (host) controller is not intended for SPD, the BIOS must set its SPDDIS at any time in the boot flow.

29.4.7 SMT as Target

The SMT has a fully-functional target interface for other masters on the SMBus intending to communicate with the SMT. The usage models for this are:

- SMBus ARP mastering or ARP target
- Embedded Controller (EC) on the SMBus communicating with the SoC

The hardware aspect of the target interface is highly generalized. Most transactions are treated as raw data which are pushed to the firmware, where the firmware transacts level activity like protocol detection. Acceleration in hardware is limited to interception of ARP Get UDID and SMBus block-read protocols, which require an immediate return of data to an external master and PEC CRC calculation. The other hardware responsibility is inspection of enough transaction bytes (e.g., target address, command code, UDID) to ascertain the protocol type and to engage the appropriate hardware flow.

29.4.7.1 Hardware Buffering for Target Support

The hardware implements a separate 240-bytes buffer to store the bytes it receives as a target, but when SMT is target to receive SMBus block write/read, the support maximum payload is <=32B.

The hardware also implements a separate 32-byte buffer which provides generic read data to external masters for any reads that they perform. This is a generic usage model in which firmware repeatedly programs the generic read-data buffer register (GPBRDBUF) with data, programs a MMIO offset (GPBRCTRL) with address, command, and byte count of how much data is present in the generic read data buffer, and communicates to the external master the hardware is ready for taking the read (in-band through the SMBus). The external master then launches a block read to the address programmed with the command, and the hardware provides the byte count and data bytes associated with it.

Note: When SMT as slave receives I2C write, the maximum buffer size supported can be 240 bytes with custom I2C driver.

29.4.7.2 Target Descriptor

Unlike the master descriptor, the target descriptor is a ring buffer of data and status, all existing concurrently. This simplified model results in the hardware writing a status of a received cycle immediately followed by the data received in the cycle (if applicable).

See also TRxSTS, which is used for debug.

Figure 29-7. Target Ring Buffer



Figure 29-8. Target Header Format



Table 29-17. Target Header Descriptor (Sheet 1 of 2)

Bit #	Field	Description
31:24	PBC	**Payload Byte Count:** The hardware updates this field to indicate how many bytes of payload data follows after the header in the target buffer. For writes coming in, this data includes the sum total of all bytes ACKed from start to stop. The hardware does then DMA all those bytes to memory. • For error scenarios where the master drives more data than expected or command code does not match, the hardware does DMA all bytes ACKed on the SMBus from start until the first byte NACKed by the hardware (this byte is not sent to memory), and the total number of bytes DMAed to memory is reflected in this field. A value of all zeros in this field means no payload is following the header.
23:22	Reserved	Reserved
21:16	RBC	**Read Byte Count**: For external master-generated reads, this data includes the sum total of bytes provided by the hardware which were successfully transferred over SMBus. For example: for an externally generated block read, the hardware provides byte count, X number of bytes, and PEC (if PEC-enabled transaction). In this case, the RBC field is 1+X+1 (for PEC). ***Note:*** For SMBus block reads, the last byte transferred is NACKed by the external master per definition. This is a data byte or PEC byte supplied by the hardware. The data bytes are not written to memory, only the byte count indicates how many bytes provided by the hardware were successfully transferred over SMBus. This field is all zeros if the transaction was an externally-generated write. The header is written to memory (if enabled to do so) containing the status of the transaction. For error scenarios in reads, the status register in the header provides details of the error, and this field contains incorrect values due to the pipelined nature of the hardware.
15:12	Reserved	Reserved
11:8	MTYPE	**Message Type**: These bits indicate which expected transaction happened on the bus since they are expected in the usage model and some have pre-programmed data provided by the firmware. • 0000: SMBus/I^2C transaction • 0111: Block read to general purpose read data buffer • 1000: SMBus ARP prepare to ARP • 1001: SMBus ARP reset device (general) • 1010: SMBus ARP Get UDID (general) • 1011: SMBus ARP assign address • 1100: SMBus ARP Get UDID (directed) • 1101: SMBus ARP reset device (directed) • 1111: SMBus ARP notify ARP master or SMBus host notify • Others: Reserved ***Note:*** Firmware: The cycle does not progress far enough for the hardware to encode the correct encodings. In this case, the hardware inserts some reserved value.

Table 29-17. Target Header Descriptor (Sheet 2 of 2)

Bit #	Field	Description
7:4	TSTS	**Transaction Status**: This field indicates the overall completion status of the transaction, i.e., success, fail, error condition, etc. Multiple error conditions occur in the same transaction (e.g., the hardware NACKs a byte and instead of an external master signaling stop, it continues to toggle the clock and eventually holds the clock low and causes time-out). The hardware captures the first error condition, i.e., the register reads 0011 for the example listed above. Refer to Table 29-19, "Target Header Encodings (TSTS) Per Transaction Type (TTYPE)" on page 770. • 0000: Success with no errors. • 0001: Speculative PEC error detected (the hardware always presumes PEC-enabled writes received). • 0010: Protocol error, i.e., the external master violated the SMBus protocol. For example, this is asserting STOP in the middle of the byte, or a stopped toggling clock, or doing an illegal repeated start, collision, etc. • 0011: Hardware NACK, i.e., the hardware NACKed one or more bytes as the byte did not match the expected byte of the sequence or exceeded hardware limitations. ***Note:*** This is the hardware overflow and does not comprehend overflow of an individual protocol (e.g., block write, received bytes > indicated byte count). • 0100: External NACK (external master NACKed at least 1 byte supplied by the hardware on an externally generated read). • 0101: Clock-low time-out • 0110: Data-low time-out • Others: Reserved
3:0	TTYPE	**Transaction Type**: This field indicates the type of transaction received by the hardware in terms of the various usage models supported: • 0000: Default SMBus transaction to C2h • 0001: Transaction targeting address (TACTRL.ADDR0) of UDID0 • 0010: Transaction targeting address (TACTRL.ADDR1) of UDID1 • 0100: Host notify transaction targeting 10h • 0101: Generic programmable block read to the programmed address in GPBRCTRL.GPTRADR • Others: Reserved ***Note:*** This definition is consistent with TSTS.TCIP.

Only certain combinations of target descriptor MTYPE and TTYPE are valid. These are summarized in Table 29-18 (shaded cells and all unlisted combinations are invalid). For each valid (MTYPE, TTYPE) pair a reference is included to the detailed hardware flowchart.

Table 29-18. Valid Target Descriptor MTYPE and TTYPE Combinations

		MTYPE			
		ARP-Related **1000** **1001** **1010** **1011** **1100** **1101**	**SMBus/I²C** **0000**	**Notify Host** **1111**	**GPBR** **0111**
TTYPE	0000	Section 29.4.7.5.2	Invalid	Invalid	Invalid
	0001 0010	Invalid	Section 29.4.7.5.6	Invalid	Invalid
	0100	Invalid	Invalid	Section 29.4.7.5.1	Invalid
	0101	Invalid	Invalid	Invalid	Section 29.4.7.5.3

29.4.7.3 Target Transaction Status

Table 29-19 provides a reference of the encodings of the transaction status (TSTS) nibble in the header WB for all valid target cycles (TTYPE).

Table 29-19. Target Header Encodings (TSTS) Per Transaction Type (TTYPE) (Sheet 1 of 2)

TTYPE Cycle Type	TSTS 0000 Success	TSTS 0001 PEC Error	TSTS 0010 Protocol Error	TSTS 0011 Hardware NACK	TSTS 0100 External NACK	TSTS 0101 Clock Low Time Out	TSTS 0110 Data Low Time Out
0101 GP Block Read	No errors	N/A (The hardware transmits the PEC.)	• A collision is detected by the hardware. This happens when the hardware intended to drive NACK and saw an ACK on the bus. • The external master signals stop/restart, and so on in the middle of a byte. • The external master signals a stop on a byte boundary before the byte count expired. • The external master continues driving more clocks even after the hardware has provided all the bytes. • The external master drives ACK instead of NACK on the PEC byte sent by the hardware. • Bits [7:1] of the repeated start address do not match the GPBR address. • Bit 0 of the repeated start address is 0, and the policy is to check for 1.	The command code byte received from the external master does not match the expected value.	The external master NACKs at least one of the bytes provided by the hardware, i.e., Byte Count, Data1, Data2, Data3,..., DataN.	The hardware detects the SMBus clock low time-out anywhere in the middle of the transaction that it is actively servicing.	The hardware detects the SMBus data low time-out anywhere in the middle of the transaction that it is actively servicing.

Table 29-19. Target Header Encodings (TSTS) Per Transaction Type (TTYPE) (Sheet 2 of 2)

TTYPE Cycle Type	TSTS 0000 Success	TSTS 0001 PEC Error	TSTS 0010 Protocol Error	TSTS 0011 Hardware NACK	TSTS 0100 External NACK	TSTS 0101 Clock Low Time Out	TSTS 0110 Data Low Time Out
0001 Cycles to ADDR0/UDID0 or 0010 Cycles to ADDR1/UDID1 or 0000 Cycles to Default Address	No errors	PEC received from the external master did not match the hardware-calculated PEC. ***Note:*** This is a speculative error only since the firmware confirms it was a PEC-enabled SMBus transaction (see Section 29.4.7.5.6).	• A collision is detected by the hardware. This happens when the hardware intended to drive NACK and saw an ACK on the bus. • The external master signals stop/restart, and so on in the middle of a byte. • The external master signals stop on a byte boundary before the byte count expired. • The external master drives more bytes than indicated by the byte count. • The external master generates a start instead of a stop on a byte boundary as a response to the hardware NACK in the previous data phase.	• The hardware NACKs when the external master drives more data than the limit programmed in TRxCTRL.MRxB • The hardware detects the protocol/address violation (see Table 29-8 and Table 29-9).	N/A (The hardware does not provide any bytes.)	The hardware detects the SMBus clock low time-out anywhere in the middle of the transaction that it is actively servicing.	The hardware detects the SMBus data low time-out anywhere in the middle of the transaction that it is actively servicing.
0100 Host Notify *or* Notify ARP Master	No errors	N/A (no PEC)	• A collision detected by the hardware. This happens when the hardware intended to drive NACK and saw an ACK on the bus. • The external master signals stop/restart, and so on in the middle of a byte. • The external master signals a stop on a byte boundary before it sends three data bytes. • The external master drives more than three data bytes after the address phase.	N/A (The hardware does not check any bytes.)	N/A (The hardware does not provide any bytes.)	The hardware detects the SMBus clock low time-out anywhere in the middle of the transaction that it is actively servicing.	The hardware detects the SMBus data low time-out anywhere in the middle of the transaction that it is actively servicing.

Note: All references to the TRxCTRL.MRxb registers must take into account the description of MRxB, i.e., the value is not directly matched since it takes into account some arithmetic based on I^2C/MCTP protocol.

Note: For time-out detection as a target, the hardware must be actively servicing the transaction when the time-out occurs. This means the hardware must have at least ACKed the address phase on the SMBus and must be committed to the transaction based on the settings of the policies in SUSCHKB register.

29.4.7.4 Target Memory Buffer Hardware-Firmware Flow

As described in the target descriptor section, a ring buffer is maintained by the firmware where the hardware sends the notifications to the firmware. The various notifications are:

1. External master initiates a read: notification of a success/failure is sent to the firmware in header. Read data is returned by the hardware (data is pre-programmed by the firmware).
2. External master initiates a write: notification of a success/failure is sent to the firmware in the header. Write data received by the hardware is sent as a payload to the memory.

Note:

1. The target buffer is empty when HWtHeadPtr = FWtTailPtr (HTHP = FTTP).
2. The target buffer is full when (HTHP = FTTP - 4B) or (HTHP - FTTP = TBS).
3. A buffer wrap for HTHP is when HTHP = TBS. When this exists, the hardware writes Dword to memory and then rolls over to 0x0000 unless a buffer full condition exists, i.e., FTTP = 0x0000.
4. The firmware must never increment the FWtTailPtr to a value greater than HWtHeadPtr.
5. If the target ring buffer is N-bytes deep, only N-1 bytes are utilized since the hardware/firmware does not implement a wrap bit.

29.4.7.4.1 Initialization

1. The firmware allocates a buffer in the firmware memory to be used as the target ring buffer as one contiguous space.
2. The firmware then programs up the Target Buffer Base Address (TBBA) register with a 64B-aligned memory address of the ring buffer.
3. The firmware assigns the Target Buffer Size (TBS) register with the actual size of the ring buffer with the maximum limit of 64 KB.
4. The hardware reset initializes HWtHeadPtr and FWtTailPtr to 0.
5. The firmware enables all target addresses as needed, and programs the register-based read data as needed.
6. The firmware also programs interrupts as needed.
7. Finally, the firmware sets the TPOLICY.TGTEN bit to enable the target logic.

29.4.7.4.2 Hardware-Firmware Flow

Once the firmware has completed initialization, the hardware target logic continues to idle until an external SMBus master sends a transaction.

External Master Initiating Writes:

1. Once the hardware receives a write transaction targeting one of its slave addresses, the hardware responds to the address and command phases.
2. Each byte ACKed is eventually DMAed to the memory starting at location Base + HWtHeadPtr + 4B as Dword writes.
3. Once the transaction is completed, the hardware writes the final bytes to memory (PBC field in the header indicates to the firmware how many true bytes are in the payload).
4. Upon completion of the transaction, the hardware writes the header Dword of that transaction into the location pointed to by HWtHeadPtr. This contains all the status information for the transaction. (See Figure 29-9, “High-Level Target Flow” on page 775.)
5. The hardware then updates the HWtHeadPtr to the next free Dword location in the target memory.
6. The hardware then writes interrupt information to the Dwords as pointed to by SMTICL. (See Table 29-20, “Target Transaction Behavior Due to SUSCHKB.IRWST” on page 776.)
   a. The hardware writes the current value of the HWtHeadPtr to TRGT.HTHP and sets TRGT.VALID.
   b. Also, if the transaction terminated abnormally the error condition is written (e.g., to ERR.TRBAF, ERR.TRBF, ERR.CKLTO) and ERR.VALID is set to indicate an error was present.
   c. Finally, if enabled, the hardware then sends MSI to the firmware.

External Master Initiating Reads:

1. Once the hardware receives a read transaction targeting one of its slave addresses, the hardware checks the address, command, and any other bytes sent by the external master and ACK/NACK appropriately.
2. If all the bytes sent by the external initiator are ACKed by the hardware, the hardware provides read data to the initiator. (See Figure 29-9, "High-Level Target Flow" on page 775.)
   a. If the initiator takes all the bytes as expected and terminates the transaction normally, depending on the state of TCTRL.SCHWBP bit, the hardware creates (or does not create) a header Dword and writes to memory at a location pointed by HWtHeadPtr with the BC field updated.
   b. If error conditions are read, the hardware updates the error status registers in the status Dword, creates the header with the appropriate BC field, and writes to memory at a location pointed by HWtHeadPtr.
3. The hardware then updates the HWtHeadPtr to the next free Dword location in the target memory.
4. The hardware then writes interrupt information to the Dwords as pointed to by SMTICL. (See Table 29-20, "Target Transaction Behavior Due to SUSCHKB.IRWST" on page 776.)
   a. The hardware writes the current value of HWtHeadPtr to TRGT.HTHP and sets TRGT.VALID.
   b. Also, if the transaction terminated abnormally, the error condition is written (e.g., to ERR.TRBAF, ERR.TRBF, ERR.CKLTO), and ERR.VALID is set to indicate an error was present.
   c. Finally, if enabled, the hardware then sends an MSI to the firmware.

29.4.7.5 Target Flow

Target flow for the hardware depends on the target address seen on the SMBus. The hardware has deterministic behavior based on the address. A high-level flowchart is shown in Figure 29-9. It does not capture all possibilities of errors, but aims to highlight the sequence of events. Depending on the received address, detailed flowcharts follow in later sections for four protocol categories.

The hardware address matching after an SMBus start condition is subject to SUSCHKB.IRWST; if asserted it causes the hardware to ignore the R/W# bit during matching. This behavior is not shown in the flowchart. It does have implications for how the Quick command, receive byte, and I^2C read are handled.

Figure 29-9. High-Level Target Flow



Table 29-20. Target Transaction Behavior Due to SUSCHKB.IRWST

	Quick Command		Receive Byte	I^2C Read
IRWST	**R/W# Bit = Read**	**R/W# Bit = Write#**	**R/W# Bit = Read**	**R/W# Bit = Read**
0	Transaction is ACKed and then dropped. No descriptor is sent. The hardware incorrectly invalidates a supported command option.	Transaction is ACKed and a descriptor is sent to the ring buffer for the firmware.	Transaction is ACKed and then dropped. No descriptor is sent. The hardware invalidates this unsupported command.	Transaction is ACKed and then dropped. No descriptor is sent. The hardware invalidates this unsupported command.
1	Transaction is ACKed and a descriptor is sent to the ring buffer for the firmware.	Transaction is ACKed and a descriptor is sent to the ring buffer for the firmware.	Transaction is ACKed and a descriptor is sent to the ring buffer for the firmware. The command is aliased and treated by the hardware as a send byte. The firmware must invalidate (drop) this unsupported command by detecting the R/W# bit is set in the descriptor.	Transaction is ACKed and a descriptor is sent to the ring buffer for the firmware. The command is aliased and treated by the hardware as an I^2C write. The firmware must invalidate (drop) this unsupported command by detecting the R/W# bit is set in the descriptor.

Note: Based on the interaction between SUSCHKB.IRWST and certain supported and unsupported commands, the following recommendations are made:

- If a Quick command is unused (or if its usage is restricted to R/W# bit cleared), then IRWST is cleared. The hardware invalidates the unsupported commands receive byte and I^2C read.
- Otherwise, IRWST is set, and the firmware invalidates (drops) both of these unsupported commands.

29.4.7.5.1 Host Notify Target Flow

TTYPE = 0100 and **MTYPE = 1111**

The host notify flow comprehends both the ARP host notification and the ordinary SMBus host notify protocols since they differ only in the content of the second received byte. If the firmware has declared this address to be busy (TPOLICY.HOSTBSY), then the hardware will ACK the address byte but NACK all subsequent bytes.

29.4.7.5.2 SMBus ARP Target Flow

TTYPE = 0000 and **MTYPE = 1000, 1001, 1010, 1011, 1100, 1101**

The ARP target flow comprehends all ARP protocols, including general and directed flavors. The priority shown in the flowchart for decoding the command byte is illustrative only. All ARP-related transactions require PEC processing: for Get UDID, the hardware must calculate and transmit the PEC. In all other protocols the hardware must calculate the PEC and compare that against the received PEC byte.

If the firmware has declared this address to be busy (TPOLICY.C2_BSY), then the hardware will ACK the address byte but NACK all subsequent bytes.

The hardware address matching after an SMBus repeated-start condition is subject to SUSCHKB.IRWRST; if asserted it causes the hardware to ignore the R/W# bit during matching. This behavior is not shown in the flowchart.

Figure 29-10.Host Notify Target Flow



Figure 29-11.SMBus ARP Target Flow



29.4.7.5.3 General-Purpose Block Read Flow

TTYPE = 0101 and **MTYPE = 0111**

SMT provides a mechanism for an external master to read up to 32B of data from the SMT.

The rules are:

- The external master cannot asynchronously launch a read request.
- The address to read from is programmed by the firmware (GPBRCTRL.GPTRADR), and this address must be unique from all other target addresses that SMT supports.
- The external master must read data only as defined by an SMBus 2.0 Block Read command.
- The firmware programs the data into the Data Buffer register (GPBRDBUF) and enables the hardware to support a Read command from the external master (GPBRCTRL.EN).
- The firmware sends a message to the external master requesting it to read the data.

The sequence of events is indicated by the flowchart shown in Figure 29-12.

The hardware matches the received command code against a Firmware-programmed Expected command (GPBRCTRL.CMD). A mismatch causes the transaction to be terminated with a NACK. This matching is required since GPBR is handled entirely in the hardware; the firmware does not participate in validating the address and command.

An appended PEC is optional and is enabled by the firmware (GPBRCTRL.PECEN). Its usage is determined by high-level policy negotiation between the SoC and the external master.

Nominally, the hardware clears its enable bit immediately after ACKing the command byte. This enables a handshake between the hardware and the firmware such that the hardware transmits read data only after being programmed and its trigger set by the firmware. Alternately, the hardware is enabled (GPBRCTRL.HWCLRDIS) to continually respond to read requests from an external master; however, in this mode, determinism is not guaranteed between the firmware programming to and the master reads of the data registers.

The hardware address matching after an SMBus repeated-start condition is subject to SUSCHKB.IRWRST; if asserted it causes the hardware to ignore the R/W# bit during matching. This behavior is not shown in the flowchart.

The generic programmable read data buffer register (GPBRDBUF) loads data into the generic programmable read data buffer. The buffer provides a mechanism of supporting Generic Programmable Reads (GPBR) by an external SMBus master under the firmware initiated flow.

The data buffer is filled by the firmware initiating DW writes to this register. A hidden pointer always points to the next available buffer location—reading and writing to GPBRDBUF cause the pointer to increment automatically.

Note: Because the pointer auto-increments after each read and write, a read of GPBRDBUF does NOT return the most recently written data. Normal usage requires the buffer contents to be cleared before filling it with a new data payload. Therefore, a read (of the next empty location) returns 0s. (See also GPBRCTRL.BUFRST and GPBRCTRL.PTRRST.)

Figure 29-12.General Purpose Block Read with PEC Target Flow



29.4.7.5.4 Normal Usage

Before programming new data into the GPBR buffer, the firmware sets both GPBRCTRL.BUFRST (which resets the buffer contents to 0) and GPBRCTRL.PTRRST (which resets the buffer pointer position). After the hardware has completed the reset, it clears both bits.

29.4.7.5.5 Debug Usage

To enable the firmware to read back (verify) the contents of the GPBR buffer, the firmware sets only GPBRCTRL.PTRRST, which resets the buffer pointer position but leaves the buffer contents intact. Consecutive reads then return the previously written buffer data.

The hardware provides read data payload starting from bits [7:0] of Dword0 of the buffer, then bits [15:8] of Dword0, and so on. All bytes must be programmed in the sequence to be sent out without gaps. The hardware counts the number of bytes indicated in the GPBRCTRL.BC register and starts sending them out sequentially starting at byte 0 of Dword 0 until the byte count is decremented to 0.

29.4.7.5.6 SMBus/I^{2}C Target Flow

TTYPE = 0001, 0010 and **MTYPE = 0000**

SMT supports being a target of certain SMBus and I^{2}C transactions (see Figure 29-13, "SMBus/I^{2}C Target Flow" on page 782), and it acknowledges transactions directed to either of its two target addresses (TACTRL.ADDR0 or TACTRL.ADDR1). The basic flow is depicted in Figure 29-13. In general the target hardware interface is agnostic of command and PEC bytes. The firmware handles these bytes.

Note: It is assumed that block reads to SMT as a target are directed only to the dedicated GPBR address (GPBRCTRL.GPTRADR) and are not considered in this flow.

Write cycles received by the SMT target interface nominally terminate when the external master produces a stop condition. A premature hardware NACK occurs if the interface is busy or overflows. The SMBus Quick command is comprised only of the address byte, with the data encoded entirely within the R/W# bit. All other SMBus and I^{2}C transactions have additional data bytes.

The optional PEC byte is not shown explicitly because the firmware determines the actual presence of PEC. This provides for PEC to be enabled on a per-function, per-address, per-protocol, or even per-transaction basis. The hardware always performs a **speculative** internal PEC calculation, which it then compares to the final received byte. If the received and calculated bytes match, this is a strong indication that the transaction was PEC-enabled, but the firmware has the final authority. Conversely, a mismatch is not proof of a transmission error—it may have been a PEC-less transaction. In this case, the firmware ignores the PEC status flag in the target descriptor TSTS field, which resulted from the hardware invalid speculative of the PEC comparison.

Since some protocols have identical transmission templates it is also the responsibility of the firmware to prevent or resolve apparent aliasing (e.g., aliasing of a send byte with the PEC and a write byte; aliasing of a write byte with the PEC and a write word; aliasing of the SMBus write byte and I^{2}C MTx-to-SRx). It is assumed this is accomplished through negotiation between the firmware and the external master. For instance, the command byte differentiates protocols or certain protocol combinations are excluded.

A special case of aliasing occurs for the SMBus block write. Since the hardware ignores the command byte, it cannot distinguish the block write byte count from an ordinary data byte. Therefore, the hardware captures and pushes all bytes to the firmware for processing, and the hardware is not required to verify the received byte count. In the target mode, the firmware programs a ceiling (TRxCTRL.MRxB) on the write length such that if a transaction overflows the ceiling, then the hardware must NACK any unexpected data bytes. This ceiling must not exceed the buffer size. The hardware NACK flag in the target descriptor TSTS field is set upon a hardware (buffer) overflow, but this flag does not comprehend overflow of an individual protocol (e.g., a block write where received bytes > the indicated byte count).

Note: If a target address receives both I^2C and SMBus protocols, the maximum permitted write length (TRxCTRL.MRxB) must accommodate both. For example, if a target receives an SMBus block write with PEC, the write length must be greater than or equal to 36 bytes (= address + command + byte count + N data bytes + PEC, where N<=32).

If the firmware has declared a matched address to be busy (TPOLICY.ADDR0BSY or TPOLICY.ADDR1BSY), then the hardware will ACK the address byte but NACK all subsequent bytes.

The hardware address matching after any SMBus repeated-start condition is subject to SUSCHKB.IRWRST; if asserted it causes the hardware to ignore the R/W# bit during matching. This behavior is not shown in the flowchart.

Figure 29-13.SMBus/I^2C Target Flow



29.4.8 Dynamic SMT Policy Update

The hardware provides a mechanism for the firmware to change the policies of the hardware and other registers by the firmware without requiring a reset to the system.

29.4.8.1 Master Policy

For updates to the master side of the registers, the firmware already has the control by stopping the hardware DMA engine and halting new master transactions. This ensures that the hardware master side is completely disabled and the firmware chooses to update the policy and registers.

29.4.8.2 Target Policy

Updates to the target policy require a flow, since the hardware asynchronously receives a target cycle.

The hardware maintains a current target policy internally without direct visibility to the firmware. The firmware sees the current policy by reading the TPOLICY register. When TPOLICY.PTUREQ=0, it means the current policy settings are effective in the hardware (assuming the firmware follows flow and did not write to any other register without first setting the PTUREQ bit). To change the policy, the firmware first disables the target completely or selectively disables addresses so while the firmware is extensively updating registers, the hardware NACKs appropriately in the address or command phase as desired. After that is done, the firmware must again update the policy following the same flow to have the final desired policy in effect.

1. The firmware sets the intermediate policy desired by programming the TPOLICY register with TPOLICY.PTUREQ also set.
2. When the hardware reaches the SMBus idle state, it checks if PTUREQ is:
   a. If set, the hardware captures the current setting of the policy in PTUREQ and loads into its internal registers. It also clears the PTUREQ bit once the policy is captured.
   b. If clear, the hardware continues to be in idle until another SMBus start is seen.
3. The hardware continues to act on an intermediate policy resulting in NACK on the address phase or on the command phase of incoming cycles (programmed by the firmware).
4. The firmware polls or reads the PTUREQ register to make sure it is clear before reprogramming the registers, etc.
5. Once the firmware is ready to ungate the hardware, the firmware again follows step #1 in which it sets the new policy.
6. The flow again follows steps 2-4 before the final firmware policy is set and active in the hardware.

A conceptual flow is shown in Figure 29-14.

Figure 29-14.Target Dynamic Policy Update



29.5 Interrupts

The SMT hardware has the following causes of interrupts (if enabled).

1. Master Interrupt - The hardware generates master interrupts for transactions ending successfully or in a failure.
2. Target Interrupt - Generated whenever the hardware writes data and/or the header to memory.
3. Error Interrupt - Generated whenever the hardware detects a bus error or a resources error.

Table 29-21. Summary of SMT Interrupt Enables and Sources

Interrupt Enable/Mask	Interrupt Source	Governed By	Asserted Upon
Master Interrupts			
Master Descriptor INT field	MSTS.MIS		Successful completion of master cycles
MCTRL.MEIE	MSTS.MEIS		Unsuccessful completion of master cycles
Target Interrupts			
TCTRL.TIE	TSTS.TIS	TCTRL.SCHWBP TCTRL.UCHWBP TCTRL.URxTWP	Successful completion of target cycles Unsuccessful completion of target cycles Unsuccessful completion of write to target
Error Interrupts			
ERRINTMSK.CKLTO	ERRSTS.CKLTO		SMBus clock-low time-out
ERRINTMSK.TRBF	ERRSTS.TRBF		Target ring buffer is full.
ERRINTMSK.TRBAF	ERRSTS.TRBAF		Target ring buffer is almost full.
ERRINTMSK.IHIE	ERRSTS.IHIE		Read completion with non-successful status
ERRINTMSK.IMAE	ERRSTS.IMAE		Request is made when PCICMD.BME is clear.
ERRINTMSK.ITE	ERRSTS.ITE		Error in IPI transmit transaction
ERRINTMSK.IRDPE	ERRSTS.IRDPE		Data parity error in IPI receive transaction
ERRINTMSK.IRE	ERRSTS.IRE		Error in IPI receive transaction
ERRINTMSK.SPDWE	ERRSTS.SPDWE	MCTRL.SPDDIS	Write is attempted to SPD address range
ERRINTMSK.CPE	ERRSTS.CPE		CSR parity error

Note: First-error cause information is logged in ERRINFO. Also, error interrupts also support masking of escalation to Advanced Error Reporting (AER); see ERRAERMSK.

Note: ERRINTMSK.IMAE: this bit is assumed to be 1 when MSICTL.MSIE is set. IMAE occurs only if PCICMD.BME is clear, and MSI requires BME to be set.

29.5.1 Master Interrupts

Two causes for a master interrupt are:

1. **Successful** - The Interrupt bit in the descriptor is set to indicate the hardware must generate an interrupt on successful completion of the descriptor. An Interrupt Status Register bit is defined in the MMIO space (MSTS.MIS), which is set every time the hardware retires a descriptor. The enable for this interrupt is defined within each individual descriptor.
2. **Failure** - The descriptor is not successfully completed due to an SMBus error. This interrupt has a Cause Enable (MCTRL.MEIE) and a Cause Status bit (MSTS.MEIS) in the device MMIO space.

Upon completion of descriptor processing, either MSTS.MIS (successful completion) or MSTS.MEIS (unsuccessful completion) must be set by the hardware. This distinction is required so that if the firmware disables MSI (i.e., chooses to operate in the polling mode) by polling both flags, it determines when the descriptor has completed and its completion status.

The master interrupts are sent for the descriptor-based transactions. Therefore, they are serialized and ordered with respect to the descriptor writeback and specifically tied to the descriptor just processed due to the operand requirement.

1. Run the descriptor-based master transaction on the SMBus.
2. Perform the descriptor status WB to memory. (See the status WB field in Figure 29-4, “Master Descriptor Ring Buffer” on page 750, Figure 29-5, “Master Descriptor Format” on page 750, and Table 29-13, “Master Descriptor Field Descriptions” on page 751.)
3. Write 1 to the appropriate Cause Status bit (MCTRL.MEIS or MSTS.MIS).
4. If that appropriate interrupt is enabled (locally and globally), an MSI is sent and the cause status is auto-cleared, else an MSI is not sent and the cause remains set and the firmware is expected to poll the response.

Note: MSTS.MEIS itself merely indicates an unsuccessful completion. The descriptor status WB field contains full details of transaction and error conditions.

Note: Firmware implementation:

1. If the cause is set for a previous descriptor-based transaction and the firmware enables the global (and local) interrupt enable, the hardware does not send an interrupt for a previously set cause.
2. The firmware is responsible to ensure that if the cause is set, the previous transactions are accounted for before enabling the MSI (globally and locally).

29.5.2 Target Interrupts

Since the target ring buffer is a single buffer in the memory, the interrupts sent on behalf of the target are simplified to be sent every time the hardware writes data and/or the header to the memory (depending on if target interrupts are enabled and if global MSIen is set).

The conditions which result in a status header being written are further governed by these policies:

- TCTRL.SCHWBP: upon successful completion of target cycles
- TCTRL.UCHWBP: upon unsuccessful completion of target cycles
- TCTRL.URxTWP: upon unsuccessful completion of writes to the target

This simplified model is used since the hardware supports multiple logical devices and transactions of each type are pushed to memory by the hardware in a sequential manner. The firmware then has to parse each header to determine what each transaction is before the firmware takes the appropriate action.

A single Target Interrupt Enable bit is maintained in the MMIO space (TCTRL.TIE) which gates the sending of this interrupt. An Associated Status bit (TSTS.TIS) is also maintained in the hardware.

Similar to master interrupts, target interrupts are also serialized and ordered. The decision to send an MSI is made after the hardware has written back the header for the received transaction to the memory ring buffer.

1. Receive the target cycle from the SMBus.
2. Perform data and header WB to memory.
3. Write 1 to the appropriate Cause Status bit (TSTS.TIS).

If TCTRL.TIE is enabled (locally and globally), an MSI is sent and the cause status is auto cleared else an MSI is not sent and the cause remains set.

Note: Firmware implementation:

1. If the cause is set for a previous target transaction written to memory and the firmware enables the global (and local) interrupt enable, the hardware does not send an interrupt for a previously set cause.
2. The firmware is responsible to ensure that if the cause is set, the previous transactions are accounted for before enabling an MSI (globally and locally).

29.5.3 Error Interrupts

The hardware tracks the following conditions for errors:

1. SMBus clock-low time-out: status is set when the hardware observes the SMBus clock is asserted low for more than the value programmed by the firmware.
2. SMBus data-low time-out: status is set when the hardware observes the SMBus data is asserted low for more than the value programmed by the firmware.
3. Target ring buffer almost full: status is set when the hardware detects the target ring buffer has less than 85B free space remaining in the target ring buffer. This check is done after the hardware performs a memory write for data/header.
4. Target ring buffer full: status is set when the hardware in unable to evict its internal buffer/header WB to memory due to lack of space in the target ring buffer. This check is done every time the hardware needs to write to memory.

Table 29-22. Error MSI Scheduling

Event	Global MSIen	Cause Interrupt Enable[1]	Cause Interrupt Status[2]	MSI Action
Cause occurs, but interrupts are not enabled.	0	0	0 -> 1	No MSI sent.
MSI enable is set, cause enable and cause status are previously set.	0 -> 1	1	1	Send MSI.
MSI enable and cause status previously set, cause interrupt enable is set.	1	0 -> 1	1	Send MSI.
Cause Status register gets set, interrupts are enabled.	1	1	0 -> 1	Send MSI.
Cause Status register previously set, interrupts are enabled, new cause occurs.	1	1	1 -> 1	Does not occur if interrupts are enabled. Cause Status is cleared. If the clearing happens on the same clock as the new cause is set, it is the rule in the next row before.
New cause occurs in the same clock as the previous MSI scheduled was sent.	1	1	1 -> 1	Send MSI.
Scheduled MSI was sent.	1	1	1 -> 0	The hardware auto-clears the cause register.
MSI is scheduled to be sent when MSI enable is cleared.	1 -> 0	1	0 -> 1 or 1 -> 1	The hardware schedules the MSI or drops it. Any pending MSIs must be reflected in the MSI Pending register.

1. Cause interrupt mask: see ERRINTMSK and ERRAERMSK.
2. Cause interrupt status: see ERRSTS.

29.5.4 Interrupt Cause Logging

Before sending any MSI, the hardware writes information pertinent to the interrupt cause to a memory location identified by Table 29-23.

As indicated in Table 29-23, the Dwords of SMTICL are divided into three categories. The hardware updates only the relevant Dword depending on the nature of the interrupt: interrupts generated during a master transaction involves updates only to Dword #0, likewise target transactions involve only Dword #1. However, if an error condition is present, the hardware requires also writing to Dword #2 to capture the nature of the error.

The firmware always reads all three Dwords, and upon reading them clears any Dword which has non-zero data. (At a minimum two Dwords must be read—master + error or target + error.)

Table 29-23. Interrupt Cause Information

Dword	Bit	Field	Description
Information from MASTER			
0	31	MSTR.VALID	Master interrupt cause is valid. 1: Denotes master status (MSTS), including the master hardware tail pointer, has been written.
0	30:0	Reserved	
Information from TARGET			
1	31	TRGT.VALID	Target interrupt cause is valid. 1: Denotes the Target Hardware Head Pointer (HTHP) has been written.
1	30:0	Reserved	
Error Information			
2	31	ERR.VALID	Error interrupt cause is valid. 1: Denotes errors status (ERRSTS) has been written.
2	30:0	Reserved	

29.6 SMT RAS Architecture

29.6.1 Soft Reset (DEVCTL.IFLR and GCTRL.SRST)

The SMT supports several types of soft reset including:

- Function-level reset as defined by the *PCI Local Bus Specification*, Revision 3.0 (see DEVCTL.IFLR).
- Soft reset directed to the SMT controller (see GCTRL.SRST).

In each case, the soft reset applies only to the specific SMT function addressed. Asserting a soft reset has these effects:

- An immediate and abrupt reset of the SMT master and target logic (which causes a protocol violation of any pending master or target cycles),
- Clear all the MMIO registers except those register bits denoted as sticky or read-write-once (RW-O) or primary-reset-only (PRST) as listed in Table 29-24, and
- Release the SMBus clock and data lines.

Table 29-24. SMT Soft Reset Exceptions

Register Fields	Comments
Sticky (S)	
AERCAPCTL.FEP	
AERHDRLOG.TLPHDRLOG	
ERRCORMSK.x, x = CIEM, ANFEM	
ERRCORSTS.x, x = CIE, ANFE	
ERRUNCMSK.x, x = UIEM, UREM, MTLPEM, UCEM, CAEM, CTEM, PTLPEM	
ERRUNCSEV.x, x = UIES, URES, MTLPES, UCES, CAES, CTES, PTLPES	
ERRUNCSTS.x, x = UIE, URE, MTLPE, UCE, CAE, CTE, PTLPE	
PMCSR.PMEEN	
RID.RID	
Primary-Reset-Only (PRST), Including Read-Write-Once (RW-O)	
AERCAPHDR.NCO	
CAPPTR.CPTR	
CCR.x, x = BASE, SUB, RLPI	
DEVCAP.FLR	
DEVCAP2.CTRS	
INTP.INTP	
PLKCTL.CL	
PMCSR.NSR	
SID.SID	
SVID.SVID	

Exceptions to function-level resets are listed in Table 29-25.

Table 29-25. SMT Function Level Reset Exceptions

Register Fields	Comments
DEVCTL.x, x = IFLR and MPS	In addition to any RWS, ROS, and RW1CS fields.
IOSFDEVCLKGCTL.x, x = ICGE and ICT	
SBDEVCLKGCTL.x, x = ICGE and ICT	

29.6.2 Target Reset (GCTRL.TRST)

The scope of this reset is limited to the target FSM. Upon assertion, the hardware gracefully terminates any pending transaction at the next byte boundary and builds a descriptor which the firmware rejects.

29.7 MCTP Over SMBus Packet Header Format

This section is informational. The hardware does not inspect or decode any portion of an Management Component Transport Protocol (MCTP) packet.

MCTP messages with SMBus packet headers can encapsulate data from various protocols like ASF, Network, etc. The command code in the packet (byte 1) identifies this packet as MCTP and the firmware takes appropriate action. Refer to the *Management Component Transport Protocol (MCTP) Base Specification, Version 1.1.0* for further details on the protocol.

The following information is contained in the *Management Component Transport Protocol (MCTP) Base Specification, Version 1.1.0* but is reproduced here for completeness.

https://www.dmtf.org/sites/default/files/standards/documents/DSP0236_1.1.0.pdf

Figure 29-15.MCTP Over SMBus Packet Format



Table 29-26. MCTP Over SMBus Packet Format

Byte #	Field	Description
0	Destination Slave Address	For the local SMBus, slave address for the target device. Bit 0 is always 0 since all MCTP messages are writes.
1	Command Code	Command code indicating the MCTP packet. This value is fixed at 0Fh.
2	Length	Length of the block write. Analogous to the byte count field of the SMBus Block write except length is not limited to 32 bytes. This count indicates the number of bytes to follow in the current message without counting the PEC byte.
3	Slave Address	Bits [7:1]: For the local SMBus, the slave address of the message initiator. This initiator is a repeater and cannot be assumed to be the original initiator. Bit 0: Reserved, always 1b.
4	Header Type	Bits [7:4]: Reserved Bits [3:0]: MCTP Version: 1h for all MCTP device compliant to the *Management Component Transport Protocol (MCTP) Base Specification,* Version 1.0.0.
5	Destination Endpoint ID	Unique ID on the system for the destination of the message. This ID reflects the final destination of the message. Reserved Values: 0 = Local bus only. Terminate at the receiver. 1 = Route to the root management controller. 2-7 = Reserved for future definition.
6	Source Endpoint ID	Unique ID on the system for the originator of the message. This ID reflects the true initiator of the message.
7	Message Control	Bit 7: **Start of Message** (SOM): Set to 1 if the packet is the start of message. Bit 6: **End of Message** (EOM): Set to 1 if the packet is the end of message. Combinations of SOM and EOM are used to identify the start, middle, and end of a message that is split across one or more packets. Bits [5:4]: **Sequence Number**: For messages that span multiple packets, this field helps identify lost intermediate packets. Increments on each successive packet. The value of the sequence number for Packet N, is the Packet N-1 Sequence Number + 1 mod 4. Bit 3: **Initiator** (I): Set to 1 if the value of the message tag field was assigned by the source (for requests) or set to 0 if the message tag was assigned by the destination (for responses). Bits [2:0]: **Message Tag** (MT): This field, along with the source endpoint ID, identifies a unique message ID. The message ID must be unique for all outstanding request transactions that require a response and have not yet received the response. For response messages, the message tag sent with the request is returned in the response.
8	Message Header	Begin MCTP message header.
M	Message Data	MCTP defined
N	PEC	Single byte packet error check accompanies all MCTP messages

29.8 Register Map

Figure 29-16 shows the associated registers from a system software viewpoint.

Figure 29-16.Register Map



§ §

30 SMBus Controller - Platform Environment Control Interface

The Platform Environment Control Interface (PECI) was developed to replace I^2C as the methodology of reading CPU temperatures. The PECI specification has evolved overtime to provide a broader management interface to manage the platform. In non-SoC environments, the PECI slave interface is implemented in the CPU complex, while the master interface is in the Platform Control Hub (PCH) and/or Baseboard Management Controller (BMC). The PECI implementation only allows a single master on the bus.

On the SoC platform, the BMC/IE acts as a PECI over SMBus master and the SoC SMBus-for-PECI controller described in this chapter acts as a slave PECI proxy controller. The PECI commands are encapsulated within SMBus packets sent to the SoC. Additional, new PECI commands have been defined for the SoC, specific to its architecture.

Figure 30-1. What is Covered in This Chapter



Table 30-1. References

Document Title	Document ID / Location
System Management Bus (SMBus) Specification, Version 3.0	http://smbus.org/specs/SMBus_3_0_20141220.pdf

30.1 Signal Descriptions

The signal descriptions are shown in Table 30-2, "Signal Names." For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a customer GPIO signals, see Section 39.1, "Directory of Signal Names and Pin Names." The Direction/Type column of Table 30-2, "Signal Names" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.

Table 30-2. Signal Names

Signal Name	Direction Type	Shared	Description
SMB_PECI_CLK	I, O-OD	Yes	SMBus Clock (SMBCLK)
SMB_PECI_DATA	I, O-OD	Yes	SMBus Data (SMBDAT)

The optional SMBus 2.0 signals, SMBALERT# and SMBSUS#, are not supported on this controller interface.

30.2 PECI over SMBus Features

The SMBus supports the external BMC or IE, operates in slave mode only and comprehends the PECI command structure.

The PECI processes one command at time and support for multiple outstanding commands is not supported.

The PECI commands supported by the SoC are in Table 30-7, "Supported PECI Commands."

30.3 SMBus Supported Transactions

In the SoC, the communication between the SMBus controller and the internal PECI bridge utilizes the SMBus block write and block read transactions as defined in the SMBus 2.0 specifications.

The SMBus PECI device is assigned two SMBus Slave Addresses. The two Slave Addresses are assigned default values but can be altered by the customer Soft Straps. See the PECI category in Section 4.2, "SoC Soft Straps."

- 4Bh = Default SMBus Slave Address for all SMBus Read transactions
- 4Ch = Default SMBus Slave Address for all SMBus Write transactions

The SMBus Slave Addresses are located in sideband registers.

- for SMBus Read transactions: GPTRADR[7:0] field of the GPBRCTRL register located at sideband Port CEh, offset 240h
- for SMBus Write transactions: ADDR0[7:1] field of the TACTRL register located at sideband Port CEh, offset 228h

See Figure 30-2, "SMBus Protocol" to interpret the SMBus protocol drawing.

Figure 30-2. SMBus Protocol

S	Start Condition
Sr	Repeated Start Condition
Rd	Read (bit value of 1)
Wr	Write (bit value 0)
X	Shown under a field indicates that field is required To have the value of 'x'
A	Acknowledge (this bit position is 0 for an ACK or 1 for a NACK)
P	Stop Condition
PEC	Packet Error Code
…	Continuation of Protocol
	Master to Slave
	Slave to Master

30.4 SMBus Block Read/Write Transaction Formats

Figure 30-3. SMBus Block Write Command



Figure 30-4. SMBus Block Read Command



30.5 SMBus Commands

Table 30-3. SMBus Write Commands

Operating Mode	Transaction	Slave Address	Command Code	Byte Count (N)	Byte 1	Byte [N:1]
PECI Mode	PECI Proxy Command	0x4C	0x62	0x4...N[1]		
PECI Mode	Reset PECI	0x4C	0x64	0		

1. See Section 30.6.2.1, "PECI Proxy Command Format."

Table 30-4. SMBus Read Command

Operating Mode	Transaction	Slave Address (CMD Phase)	Read Command Code	Slave Address (Data Phase)	Byte Count (N)	Bytes [N:1]
PECI Mode	PECI Proxy Read Command	0x4B	0x40	0x4B	0x01...N[1]	

1. See Section 30.6.2.2, "PECI Proxy Read Command."

30.6 PECI Over SMBus

PECI uses a simple structure of message header and a write-read protocol. All PECI devices have a command field. The following section describes PECI protocol.

30.6.1 PECI Message Header in SMBus

The header conveys to the target device how many bytes the master intends to send and how many it expects to receive back. The first byte of the write data is interpreted as a command to the device and must be present in all messages. The Ping() command is the only exception to this rule. Additional bytes are written to convey sub commands or to send data to the device. A zero value in the read length field means no data is read from the target device. See Figure 30-5, "PECI Message Header in the SMBus Packet" for the PECI message header. In the figure, N bytes are to be written to the target and M bytes are to be read back from the target.

Figure 30-5. PECI Message Header in the SMBus Packet



In the PECI message header, the Address Timing Negotiation (NT) and Message Timing Negotiation (MT) bits are not present. The BMC is responsible to not include these timing bits in the header.

30.6.1.1 Target Address Field

The PECI device address is defined as 0x30 + a socket identifier of 0…7. In the SoC, only a single socket model is supported, thus the PECI target address is always 0x30. Other PECI device addresses are rejected as errors.

30.6.1.2 Write Length Field

The Write Length byte conveys the number of bytes the originator sends the target device. Since all PECI message headers are identical in size, with the exception of Ping(), the Write Length byte only describes the number of command bytes sent. The target address, write length and read length fields are not included in the write length count. The following rules apply for the write length field:

- The maximum value is 0xFF.
- The command byte is included in the length.
- A write length of 0x0 is only for the Ping() command.

30.6.1.3 Read Length Field

The Read Length byte conveys the number of bytes the target device must supply the originator before returning the Frame Check Sequence (FCS) byte calculated over that data. The read length is in the range of 0x00 and 0xFF.

30.6.1.4 Command Byte

All SoC PECI commands except Ping() require a command byte. The command code is positioned as the first data byte, that is, data_byte[0].

30.6.2 PECI Write-Read Protocol

The write-read protocol shown in Figure 30-6, "PECI Write-Read Protocol" is the only protocol defined for messaging between devices on the PECI. The write-read protocol allows an atomic operation that first writes and then reads data between an originator and a target. Format of a write-read message is given in Figure 30-6, "PECI Write-Read Protocol". The read and write Frame Check Sequence (FCS) bytes are not calculated but may be required to have a byte allocated as part of the specific command where described in Section 30.6.2.1, "PECI Proxy Command Format."

Figure 30-6. PECI Write-Read Protocol



Legend:

Master to Slave

Slave to Master

Similar to Figure 30-5, "PECI Message Header in the SMBus Packet," the PECI message header, the Address Timing Negotiation (NT) and Message Timing Negotiation (MT) bits are not present. The BMC is responsible to not include these timing bits in the header.

30.6.2.1 PECI Proxy Command Format

Unlike some Intel Platform Control Hub (PCH) products, the SoC PECI-over-SMBus controller only operates in PECI mode. The SMBus Interface PECI Proxy Command protocol is an encapsulation of PECI specification commands onto the SMBus by the SMBus master. Two new SoC-specific PECI commands are also supported.

The PECI proxy command bytes, encapsulated in bytes [N:2] of the protocol, conform to Figure 30-6, "PECI Write-Read Protocol". The SoC PECI-over-SMBus controller provides a transparent pass-through of the PECI command to the integrated PECI client and does not verify the validity of the command. It is the burden of the BMC or platform board External Circuitry (EC) to provide valid data in the PECI proxy command fields of the incoming packet.

Because the SMBus is used and not the serial PECI electrical interface, it is unnecessary to calculate the Frame Check Sequence (FCS). The SoC design does keep the PECI commands consist with non-SoC Intel products and carry additional bytes that are set to 0x0. These are called out where appropriate. The PECI proxy command format is shown in Table 30-5, "PECI Proxy Command Protocol Format."

Table 30-5. PECI Proxy Command Protocol Format

PECI Proxy Command							
SMBus Default Data			SMBus to PECI Handshake Control Data	PECI Command Data as Described for Each Supported PECI Command in the PECI Specification			
Slave Address	PECI Mode Command Code	Byte Count	Byte 1	Byte 2	Byte 3	Byte 4	Byte [N:5]
0x4C (default)	0x62	0x04...N	Control Byte (Reserved)	PECI Target Address[1] 0x30 = CPU	PECI Write Length[2]	PECI Read Length[3]	Remaining Part of PECI Command[4]

1. Required PECI header byte.
2. Required PECI header byte. Must be set to the proper value as defined by the particular PECI command. If an Assured Write FCS (AW FCS) is needed, the PECI write length value must also include the AW FCS byte.
3. Required PECI Header byte. Must be set to the proper value as defined by the particular PECI command.
4. This field does not exist for the PECI Ping() command. This field is used for write data bytes including a placeholder for an AW FCS byte. Note that the Retry bit shall be set to zero and the command code byte must be one of the codes supported by the SoC.

30.6.2.2 PECI Proxy Read Command

The SMBus Read command uses one SMBus command code (0x40). The SMBus Read command returns PECI command status or PECI response payload data from the executed PECI Proxy command.

Table 30-6, "PECI Proxy Read" shows the structure of PECI response data from a PECI mode read.

Table 30-6. PECI Proxy Read (Sheet 1 of 2)

SMBus Field	Value	Data Source	Description
Slave Address	0x4B	BMC	Slave address for the command phase
Command Code – SMBus Read	0x40	BMC	Command code for SMBus read
Slave Address	0x4B	BMC	Slave address for data phase

Table 30-6. PECI Proxy Read (Sheet 2 of 2)

SMBus Field	Value	Data Source	Description
Byte Count (N)	0x01...N	SoC	N = 0x01 for busy state: • Byte 1 = 0x01 (CMD_BUSY bit set) N = 0x02 for transaction errors • Byte 1 = 0x02 (CMD_ERR bit set) • Byte 2 = Error code N > 2 indicates the request PECI command executed successfully: • Byte 1 = 0x0 • Byte 2 = 0x0 • Byte [N:3] = PECI response data
Byte 1	Control Data		**Status Byte (CMD_STAT):** Bits [7:2] = Reserved Bit 1 = CMD_ERR • This bit is set by the SoC if the PECI proxy interface detects a transaction error. The error code is defined in Byte 2. Bit 0 = CMD_BUSY • This bit is set by the SoC while a PECI command is executing. It is reset by the SoC when the PECI command operation is completed.
Byte 2	Control Data		**Error Code (ERR_CODE):** 0x00 = PECI_ST_OK • PECI command completed successfully 0x01 = PECI_ST_BAD_FORMAT • SMBus PECI message incorrectly formatted 0x09 = PECI_ST_DISABLED • PECI driver disabled 0x3E = PECI_INVALID_SOCKET • Invalid PECI socket number 0xE1 = PECI_ST_TRANS_TIMEOUT_ERROR • PECI transaction time-out (e.g., PECI controller not responding to commands or hangs) 0xFE = PECI_ST_FAILURE • General PECI failure 0xFF = PECI_ST_UNKNOWN • Unknown status **Unsupported Error Codes:** 0x02 = PECI_ST_FCS_REQ_ERROR • Error in PECI request FCS 0x04 = PECI_ST_FCS_RSP_ERROR • Error in PECI response FCS 0x08 = PECI_ST_LINK_ERROR • PECI link error
Byte [N:3]	PECI Response Data		**PECI Response Data:** PECI response data as described for each PECI command in the PECI specification. It contains all data returned by the PECI client that resides between the Write FCS byte and Read FCS byte. These bytes are valid only when the PECI command completes successfully and the CMD_ERR bit in the Status byte (Byte 1; Bit [1]) is cleared.

30.6.3 PECI Proxy Command Handling Procedure

A BMC requests read and write PECI proxy commands over the SMBus that are formatted to conform to the PECI command protocol. The PECI command handler performs the following on receipt of the SMBus packet:

- Validates that the PECI command is valid.
- Either processes the command locally or forwards the command to other SoC internal units for processing.
- Repackages the command into the appropriate format upon command completion.

The BMC retrieves the PECI response data by performing the SMBus block read transactions. The number of data bytes returned from the Block Read command on the SMBus indicates the completion status of the PECI command.

1. If N=1, then only the Status byte is sent with CMB_BUSY bit set (CMD_BUSY=1b).
   Indicates that the PECI command transaction is still in progress.
2. If N=2, then both Status and Error Code bytes are sent with CMD_BUSY bit reset (CMD_BUSY = 0b) and CMD_ERR bit set (CMD_ERR = 1b).
   Indicates that the PECI command resulted in an error. Byte 2 contains the error code.
3. If N>2, then both CMD_BUSY and CMD_ERR will be reset (CMD_BUSY = 0b, CMD_ERR = 0b).
   Indicates that the PECI command completed successfully and the read-back data is valid.

Note: The BMC should only trigger a new PECI command when the previous command is completed. The SoC does not support posted or multiple commands.

Note: If the Reset PECI SMBus command is received, any pending state will be reset. The initiator would be expected to reissue the last command.

30.6.4 PECI Proxy Command Trigger

This process provides the functions performed by the SMBus master (the BMC) and the SoC to trigger and complete a PECI Proxy command.

1. The BMC performs an SMBus block write transaction, formatted with the data associated with the requested PECI proxy command as shown in Table 30-6, "PECI Proxy Read."
2. The SoC sets the CMD_BUSY bit in the Status byte and handles the requested PECI command.
3. After completing the PECI operation, the SoC performs the following functions:
   — Resets the CMD_BUSY bit in the Status byte.
   — Sets the CMD_ERR bit if a PECI transaction error occurred; otherwise, it resets CMD_ERR bit.
   — Sets the ERR_CODE byte with the end of transaction condition.
   — If the PECI transaction completed successfully, stores the PECI response data and transfers it to the BMC on the next Read command.
4. The BMC polls the Status byte until the CMD_BUSY bit is cleared to indicate the completion of the command. If the PECI transaction completed successfully (CMD_ERR = 0), the PECI response data is valid.

30.6.4.1 Unsupported PECI Command

In the case of an unsupported PECI command, the SoC responds with the appropriate error code.

30.6.4.2 Illegally Formatted Command

In the case of an unsupported PECI command, the SoC responds with the appropriate error code.

30.7 PECI Proxy Commands

Table 30-7, "Supported PECI Commands" is a summary of the PECI Proxy commands supported by the SoC. Each is described in this section following the table.

Table 30-7. Supported PECI Commands

Command	In PECI Specification, Rev. 3.1	Supported by SoC	Command Code	Definition
Ping()	Yes	Yes	none	This command detects that PECI functionality exists.
GetDIB()	Yes	Yes	0xF7	This command returns the PECI device-specific information.
GetTemp()	Yes	Yes	0x01	This command returns the processor die information.
RdPkgConfig()	Yes	Yes	0xA1	This command reads the SoC package configuration space.
WrPkgConfig()	Yes	Yes	0xA5	This command writes the SoC package configuration space.
RdIAMSR()	Yes	Yes	0xB1	
WrIAMSR()	Yes	No	-	
RdPCIConfig()	Yes	No	-	
WrPCIConfig()	Yes	No	-	
RdPCIConfigLocal()	Yes	Yes	0xE1	This command reads the SoC PCI space.
WrPCIConfigLocal()	Yes	Yes	0xE5	This command writes the SoC PCI space.
RdEndPointConfig()	No	Yes	0xC1	This command reads the register space over the sideband.
WrEndPointConfig()	No	Yes	0xC5	This command writes the register space over the sideband.

30.7.1 Ping()

Ping() is a required message for all PECI devices. This message is used to enumerate devices or determine if a device has been removed, been powered-off, etc. A Ping() sent to a device address always returns a non-zero write FCS if the device at the targeted address is able to respond.

Table 30-8, "Ping - PECI Proxy Block Write" shows the ping PECI proxy block write format and Table 30-9, "Ping - PECI Proxy Block Read" shows the ping PECI proxy block read format.

Table 30-8. Ping - PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x04		
Byte 1	SMBUS-PECI Handshake Control		0x00		
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		0x00		Ping() command has no command code. • Write Length = 0x00 • Read Length = 0x00
Byte 4	PECI Read Length		0x00		

Table 30-9. Ping - PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBUS Read Command Code	SMBUS Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for PECI client status • Byte 1 = 0x00 If Byte 2 = 0x00 • PECI client active If Byte 2 = 0x02 • PECI client not active
Byte 1	Status Byte		CMD_STAT		See Byte[1] of Table 30-6, "PECI Proxy Read.".
Byte 2	Error Byte		ERR_CODE		If Byte 2 = 0x00 • PECI client active If Byte 2 = 0x02 • PECI client not active. See Byte[2] of Table 30-6, "PECI Proxy Read" for error code definitions.

30.7.2 GetDIB()

The SoC PECI client implementation of GetDIB() includes an 8-byte response and provides information regarding client revision number and the number of supported domains.

Table 30-10, "GetDIB() PECI Proxy Block Write" shows the GetDIB PECI proxy block write format and Table 30-11, "GetDIB() PECI Proxy Block Read" shows the GetDIB PECI proxy block read format.

Table 30-10. GetDIB() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x05		
Byte 1	SMBus-PECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		Socket ID. Always 0x30 for the SoC.
Byte 3	PECI Write Length		0x01		
Byte 4	PECI Read Length		0x08		
Byte 5	GetDIB() Command Code		0xF7		

Table 30-11. GetDIB() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x0A}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for Transaction errors • Byte 1 = 0x02 • Byte 2 = Error Code defined in Table 30-6, "PECI Proxy Read." N = 0xA indicates a successful PECI transaction • Byte 1 = 0x00 • Byte 2= 0x00 • Byte[10:3] = PECI response data
Byte 1	Status Byte		CMD_STAT		See Byte[1] of Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte[2] of Table 30-6, "PECI Proxy Read."
Byte 3	PECI Response Byte 1	PECI Response Data	PECI Device Info		See Section 30.7.2.1, "PECI Device Info Field." Returns the number of domains in addition to Domain#0 as shown below.
Byte 4	PECI Response Byte 2		PECI Device Revision		See Section 30.7.2.2, "PECI Revision Number."
Byte[10:5]	PECI Response Byte [8:3]		Reserved		

30.7.2.1 PECI Device Info Field

Figure 30-7. PECI Device Info Field Definition



30.7.2.2 PECI Revision Number

The revision number returned is 0011_0001b.

Table 30-12. PECI Revision Number Definition



30.7.3 GetTemp()

The GetTemp() command is used to retrieve the temperature from a target PECI address. The temperature is used by the BMC to regulate the temperature on the die. The data is returned as a negative value representing the number of degrees Celsius below the maximum processor Junction Temperature ($T_{J\text{-}MAX}$).

Note: The maximum PECI temperature value of zero corresponds to the processor $T_{J\text{-}MAX}$. This also represents the default temperature at which the processor Thermal Control Circuit (TCC) activates. The actual value that the thermal management system uses as a control set point ($T_{CONTROL}$) is also defined as a negative number below $T_{J\text{-}MAX}$.

See Section 30.11, "DTS Temperature Data" for the data format and error codes. Table 30-13 shows the GetTemp PECI proxy block write format and Table 30-14, "GetTemp() PECI Proxy Block Read" shows the GetTemp PECI proxy block read format.

Table 30-13. GetTemp() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x05		
Byte 1	SMBus-PECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		0x01		
Byte 4	PECI Read Length		0x02		
Byte 5	GetTemp() Command Code		0x01		

Table 30-14. GetTemp() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x04}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for transaction errors • Byte 1 = 0x02 • Byte 2 = Error Code defined in Table 30-6, "PECI Proxy Read." N = 0x4 indicates successful PECI transaction • Byte 1 = 0x00 • Byte 2= 0x00 • Byte [4:3] = PECI response data
Byte 1	Status Byte		CMD_STAT		See Byte[1] of defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		CMD_ERR		See Byte[2] of defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Response Byte 1	PECI Response Data	PECI Device Temp [7:0]		See Section 30.11.1, "PECI Device Temp Data."
Byte 4	PECI Response Byte 2		PECI Device Temp [15:8]		

30.7.4 RdPkgConfig()

The RdPkgConfig() command provides read access to the Package Configuration Space (PCS) within the processor including various power and thermal management functions. Typical PCS read services supported by the processor may include access to temperature data, energy status, run time information, DIMM temperatures and so on.

This command does provide multi-domain support. Table 30-15, "RdPkgConfig() PECI Proxy Block Write" shows the RdPkgConfig PECI proxy block write format and Table 30-16, "RdPkgConfig() PECI Proxy Block Read" shows the RdPkgConfig PECI proxy block read format.

Table 30-15. RdPkgConfig() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x09		
Byte 1	SMBus-PECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		0x05		
Byte 4	PECI Read Length		{0x02, 0x3, 0x5}		
Byte 5	RdPkgConfig() Command Code		0xA1		
Byte 6	Host ID and Retry		0x00		
Byte 7	Index				See Section 30.7.11, "MCA Access via RdEndPointConfig()" and Section 30.9, "CPU Thermal and Power Optimization Capabilities" for the supported capabilities and their index and parameter information.
Byte 8	Parameter LSB				
Byte 9	Parameter MSB				

Table 30-16. RdPkgConfig() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x04, 0x05, 0x07}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for transaction errors • Byte 1 = 0x02 • Byte 2 = Error Code defined in Table 30-6, "PECI Proxy Read." N = {0x4,0x5,0x7} indicates a successful PECI transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte [7:3] = PECI response data N = {0x04, 0x05, 0x07} value is determined by the number of PECI Response Data bytes returned in Byte [7:4] on the SMBus. N Value: • 0x04 = 1 data byte • 0x05 = 2 data bytes • 0x07 = 4 data bytes
Byte 1	Status Byte		CMD_STAT		See Byte [1] of defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte [2] of defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion Code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command
Byte 4	Data 1 (LSB)		Data = 1, 2, or 4 bytes		See Section 30.7.11, "MCA Access via RdEndPointConfig()" and Section 30.9, "CPU Thermal and Power Optimization Capabilities" for the supported capabilities and their returned data structures.
Byte 5	Data 2				
Byte 6	Data 3				
Byte 7	Data 4 (MSB)				

30.7.5 WrPkgConfig()

The WrPkgConfig() command provides write access to the Package Configuration Space (PCS) within the processor including various power and thermal management functions. Typical PCS write services supported by the processor may include power limiting, thermal averaging constant programming, and other write services.

Table 30-17, "WrPkgConfig() PECI Proxy Block Write" shows the WrPkgConfig PECI proxy block write format and Table 30-18, "WrPkgConfig() PECI Proxy Block Read" shows the WrPkgConfig PECI proxy block read format.

Table 30-17. WrPkgConfig() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	{0x0B, 0x0C, 0x0E}		N = {0x0b, 0x0c, 0x0e} value is determined by the number of PECI Write Data bytes transmitted in Byte [13:10] on the SMBus. N Value: • 0x0b = 1 data byte • 0x0c = 2 data bytes • 0x0e = 4 data bytes
Byte 1	SMBus-PECI Handshake Control		0x01		Value = 0x01 • Assured Write (AW) Frame-Check Sequence (FCS) is not required. However, to maintain compatibility included is the AW space for the byte per the PECI specification.
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		{0x07, 0x08, 0x0A}		
Byte 4	PECI Read Length		0x01		
Byte 5	WrPkgConfig() Command Code		0xA5		
Byte 6	Host ID and Retry		0x00		
Byte 7	Index				See Section 30.7.11, "MCA Access via RdEndPointConfig()" and Section 30.9, "CPU Thermal and Power Optimization Capabilities" for the supported capabilities and their index, parameter, and data structure information.
Byte 8	Parameter (LSB)				
Byte 9	Parameter (MSB)				
Byte 10	PECI Data 1 (LSB)				
Byte 11	PECI Data 2				
Byte 12	PECI Data 3				
Byte 13	PECI Data 4 (MSB)				
Byte 14	AW FCS Byte		0x00		Dummy to maintain compatibility with the PECI specification.

Table 30-18. WrPkgConfig() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x03}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for transaction errors • Byte 1 = 0x02 • Byte 2 = Error Code defined in Table 30-6, "PECI Proxy Read". N = {0x03} indicates successful PECI transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte3 = PECI Completion code
Byte 1	Status Byte		CMD_STAT		See Byte [1] of defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte [2] of defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command

30.7.6 RdIAMSR()

The RdIAMSR() PECI command provides read access to Model Specific Registers (MSRs) defined in the processor's Intel® Architecture (IA). MSR definitions can be found in the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

The processor PECI client allows PECI RdIAMSR() access to the registers pertaining to the SoC error banks (machine check banks 0 through 19). The exact number of accessible banks for the SoC may be obtained by reading the IA32_MCG_CAP[7:0]MSR (0x0179). Attempts to read MSRs that are not accessible over PECI or not implemented result in a completion code of 0x90.

PECI access to these registers is expected only when in-band access mechanisms are not available. Valid processor ID values may be obtained by using the enumeration methods described in Section 30.7.6.1, "Processor ID Enumeration." The PECI host must determine the total number of machine check banks and the validity of the MCi_ADDR and MCi_MISC register contents prior to issuing a read to the machine check bank similar to standard machine check architecture enumeration and accesses. The processor machine check banks 4 through 21 reside outside the processor and hence will return the same value independent of the processor ID used to access these banks. PECI accesses to the machine check banks may not be possible in the event of a core hang. A warm reset of the processor may be required to read any sticky machine check banks.

30.7.6.1 Processor ID Enumeration

The 'Processor ID' field that is used to address the IA MSR space refers to a specific logical processor within the CPU. The 'Processor ID' always refers to the same physical location in the processor silicon regardless of configuration. For example, if certain logical processors are disabled by BIOS, the Processor ID mapping will not change. The total number of Processor IDs on a CPU is product-specific. Processor ID does not always refer to the same physical location across processor types and SKUs.

'Processor ID' enumeration involves discovering the logical processors enabled within the CPU package. This can be accomplished by reading the 'Max Thread ID' value through the RdPkgConfig() command (Index 0, Parameter 3) and subsequently querying each of the supported processor threads. Unavailable processor threads will return a completion code of 0x90.

Table 30-19, "RdIAMSR() PECI Proxy Block Write" shows the RdIAMSR PECI proxy block write format.

Table 30-20, "RdIAMSR() PECI Proxy Block Read" shows the RdIAMSR PECI proxy block read format.

Table 30-19. RdIAMSR() PECI Proxy Block Write

SMBUS	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBUS Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x09		
Byte 1	SMBUSPECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		0x05		
Byte 4	PECI Read Length		{0x02, 0x3, 0x5, 0x9}		
Byte 5	RdIAMSR () Command Code		0xB1		
Byte 6	Host ID & Retry		0x00		
Byte 7	Processor ID				See supported Structure sections for details.
Byte 8	MSR Address (LSB)				
Byte 9	MSR Address (MSB)				

Note: The "Processor ID" field used to address the IA MSR space refers to a specific logical processor in the CPU. The Processor ID always refers to the same physical location in the processor silicon regardless of configuration. For example, if certain logical processors are disabled by BIOS, the Processor ID mapping will not change. The total number of Processor IDs on an SoC is product-specific.

Table 30-20. RdIAMSR() PECI Proxy Block Read

SMBUS	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBUS Command	0x4B	BMC	
SMBUS Read Command Code	SMBUS Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x04, 0x05, 0x07, 0x0b}	PECI "Command Controller"	N = 0x01 for Busy state • Byte 1 = 0x01 N = 0x02 for Transaction Errors • Byte 1 = 0x02 • Byte 2 = Error Code defined Table 30-6, "PECI Proxy Read.". N = {0x4,0x5,0x7, 0x0b} indicates successful PECI Transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte[11:3] = PECI Response Data N = {0x04, 0x05, 0x07,0x0b} value is determined by the number of PECI Response Data bytes returned in Byte[11:4] on the SMBus. N Value: • 0x04 = 1 data byte • 0x05 = 2 data bytes • 0x07 = 4 data bytes • 0x0b = 8 data bytes
Byte 1	Status Byte		CMD_STAT		See Byte[1] of Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte[2] of Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion Code decode: 0x40 = Command successful 0x80 = Response time-out 0x90 = Illegal command
Byte 4	Data 1 (LSB)		Data = {1, 2, 4, or 8 bytes)		See later section.
Byte 5	Data 2				
Byte 6	Data 3				
Byte 7	Data 4				
Byte 8	Data 5				
Byte 9	Data 6				
Byte 10	Data 7				
Byte 11	Data 8 (MSB)				

30.7.7 RdPCIConfigLocal()

The RdPCIConfigLocal() command provides sideband read access to the entire PCI configuration space of the SoC. This includes all SoC registers within the PCI configuration space as described in register document.

PECI originators may conduct a device/function enumeration sweep of this space by issuing reads in the same manner that the BIOS would. A response of all 1's may indicate that the device/function/register is unimplemented even with a 'passing' completion code. Alternatively, reads to unimplemented or hidden registers may return a completion code of 0x90 indicating an invalid request. It is also possible that reads to function 0 of non-existent IIO devices issued prior to BIOS POST may return all '0's with a passing completion code. PECI originators can access this space even prior to BIOS enumeration of the system buses. There is no read restriction on accesses to locked registers.

PCI configuration addresses are constructed as shown in Figure 30-8, "PCI Configuration Address Format." Under normal inband procedures, the Bus number would be used to direct a read or write to the proper device. Any request made with a bad Bus number is ignored and the client will respond with all '0's and a 'passing' completion code.

Figure 30-8. PCI Configuration Address Format



Table 30-21, "RdPCIConfigLocal() PECI Proxy Block Write" shows the RdPCIConfigLocal PECI proxy block write format and Table 30-22, "RdPCIConfigLocal() PECI Proxy Block Read" shows the RdPCIConfigLocal PECI proxy block read format. It is not possible to access PCI Express* B0, D0, F0 using the RdPCIConfigLocal command.

Table 30-21. RdPCIConfigLocal() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode Command Code		0x62		
Byte Count	N	Control Data	0x09		
Byte 1	SMBus-PECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		0x05		
Byte 4	PECI Read Length		{0x02,0x3, 0x5}		One byte for the Completion code plus byte count of the desired data return from the accessed configuration-space register: • 0x02 = One byte desired. • 0x03 = One word desired. • 0x05 = One DWord desired.
Byte 5	RdPCIConfigLocal() Command Code		0xe1		
Byte 6	Host ID and Retry		0x00		
Byte 7	PCI Configuration Address Byte 1 (LSB)		24-bit PCI Configuration Address		24-bit PCI configuration address mapping: • Bit [11:0] = Register • Bit [14:12] = Function • Bit [19:15] = Device • Bit [23:20] = Bus
Byte 8	PCI Configuration Address Byte 2				
Byte 9	PCI Configuration Address Byte 3 (MSB)				

Table 30-22. RdPCIConfigLocal() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x04, 0x05, 0x07}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for transaction errors • Byte 1 = 0x02 • Byte 2 = Error code defined in Table 30-6, "PECI Proxy Read." N = {0x4,0x5,0x7} indicates a successful PECI transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte [7:3] = PECI response data N = {0x04, 0x05, 0x07} value is determined by the number of PECI response data bytes returned in Byte [7:4] on the SMBus. N Value: • 0x04 = 1 data byte • 0x05 = 2 data bytes • 0x07 = 4 data bytes
Byte 1	Status Byte		CMD_STAT		See Byte [1] of defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte [2] of defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command
Byte 4	PCI Data 1 (LSB)		Data = 1,2 or 4 bytes		Data returned from the PCI configuration space. Data is either a byte, word, or DWord depending on the PECI read length field of the associated PECI proxy block write.
Byte 5	PCI Data 2				
Byte 6	PCI Data 3				
Byte 7	PCI Data 4 (MSB)				

30.7.8 WrPCILocalConfig()

The WrPCILocalConfig() command provides sideband write access to the PCI configuration space that resides within the processor. PECI originators can access this space even before BIOS enumeration of the system buses. The write accesses to registers that are locked will not take effect but will still return a completion code of 0x40. However, write accesses to registers that are hidden will return a completion code of 0x90.

Table 30-23, "WrPCILocalConfig() PECI Proxy Block Write" shows the WrPCILocalConfig PECI proxy block write format and Table 30-24, "WrPCILocalConfig() PECI Proxy Block Read" shows the WrPCILocalConfig PECI proxy block read format.

Table 30-23. WrPCILocalConfig() PECI Proxy Block Write (Sheet 1 of 2)

SMBUS	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBUS Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	{0x0b, 0x0c, 0x0e}		
Byte 1	SMBUS-PECI Handshake Control		0x01		Value = 0x01 AW FCS required Bridge Controller generates the AW FCS and appends it to the PECI command to the client.
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		{0x07, 0x08, 0x0a}		Refer to later Section.
Byte 4	PECI Read Length		0x01		
Byte 5	WrPCILocalConfig () Command Code		0xe5		
Byte 6	Host ID & Retry		0x00		

Table 30-23. WrPCILocalConfig() PECI Proxy Block Write (Sheet 2 of 2)

SMBUS	Function		Value	Data Source	Comment
Byte 7	PCI Configuration Address Byte 1 (LSB)	PECI Command	24-bit PCI Configuration Address	BMC	PCI Configuration Address Byte[3:1] = 24-Bit PCI Configuration Address Mapping: • Bit[11:0] = Register • Bit[14:12] = Function • Bit[19:15] = Device • Bit[23:20] = Bus See supported Structure sections for details.
Byte 8	PCI Configuration Address Byte 2				
Byte 9	PCI Configuration Address Byte 3 (MSB)				
Byte 10	PECI Data 1 (LSB)		Data = (1, 2, or 4 bytes)		
Byte 11	PECI Data 2				
Byte 12	PECI Data 3				
Byte 13	PECI Data 4 (MSB)				
Byte 14	AW FCS		0x00		PECI Command Controller generates the AW FCS based on the setting of Bit[0] in Byte 1.

Table 30-24. WrPCILocalConfig() PECI Proxy Block Read

SMBUS	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBUS Command	0x4B	BMC	
SMBUS Read Command Code	SMBUS Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x03}	PECI "Command Controller"	N = 0x01 for Busy state • Byte 1 = 0x01 N= 0x02 for Transaction Errors • Byte 1 = 0x02 • Byte 2 =Error Code defined Table 30-6, "PECI Proxy Read.". N={0x03} indicates successful PECI Transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte 3 = PECI Completion Code
Byte 1	Status		CMD_STAT		See Byte[1] of Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte[2] of Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion Code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command

30.7.9 RdEndPointConfig()

The RdEndPointConfig() command provides sideband read access to the PCI configuration space that resides within the processor, as well as the SSA sideband configuration space of each agent. The exact listing of supported devices, functions, and registers is outside the scope of this document. PECI originators can access this space even before BIOS enumeration of the system busses. PECI originators may also conduct a device/function/register enumeration sweep of this space by issuing reads in the same manner that the BIOS would.

Table 30-25, "RdEndPointConfig() PECI Proxy Block Write" shows the RdEndPointConfig PECI proxy block write format and Table 30-26, "RdEndPointConfig() PECI Proxy Block Read" shows the RdEndPointConfig PECI proxy block read format.

Table 30-25. RdEndPointConfig() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x0B		
Byte 1	SMBus-PECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		{0x07}		
Byte 4	PECI Read Length		{0x02, 0x3, 0x5}		
Byte 5	RdEndPointConfig() Command Code		0xC1		Use the same command for both, i.e., RdEndPointConfig is an alias.
Byte 6	Host ID and Retry		0x00		
Byte 7	SoC Sideband Port				Endpoint Address
Byte 8	Port Register Address Byte 1 (LSB)		Any valid register address for the sideband port		Port offset If the addressed sideband port register does not exist, an error is returned.
Byte 9	Port Register Address Byte 2				
Byte 10	Port Register Address Byte 3				
Byte 11	Port Register Address Byte 4 (MSB)				

Table 30-26. RdEndPointConfig() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x1, 0x02, 0x04, 0x05, 0x07}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for transaction errors • Byte 1 = 0x02 • Byte 2 = Error code defined in Table 30-6, "PECI Proxy Read." N = {0x4,0x5,0x7} indicates a successful PECI transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte [7:3] = PECI response data N = {0x04, 0x05, 0x07} value is determined by the number of PECI Response Data bytes returned in Byte [7:4] on the SMBus. N Value: • 0x04 = 1 data byte • 0x05 = 2 data bytes • 0x07 = 4 data bytes
Byte 1	Status Byte		CMD_STAT		See Byte[1] of defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte[2] of defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion Code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command
Byte 4	Data 1 (LSB)		Data = 1, 2, or 4 bytes		
Byte 5	Data 2				
Byte 6	Data 3				
Byte 7	Data 4 (MSB)				

30.7.10 WrEndPointConfig()

The WrEndPointConfig() command provides sideband write access to the PCI configuration space that resides within the processor. PECI originators can access this space even before BIOS enumeration of the system busses. The exact listing of supported devices, functions, and registers for writing is outside the scope of this document. Refer to the appropriate processor specifications for details on registers that are accessible through this command.

Table 30-27, "WrEndPointConfig() PECI Proxy Block Write" shows the RdEndPointConfig PECI proxy block write format and Table 30-28, "WrEndPointConfig() PECI Proxy Block Read" shows the RdEndPointConfig PECI proxy block read format.

Table 30-27. WrEndPointConfig() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode Command Code		0x62		
Byte Count	N	Control Data	{0x0D, 0x0E, 0x10}		
Byte 1	SMBus-PECI Handshake Control		0x01		Always set the value of Byte 1 to 0x01.
Byte 2	PECI Client Address	PECI Command	0x30		
Byte 3	PECI Write Length		{0x09, 0x0A, 0x0C}		
Byte 4	PECI Read Length		0x01		
Byte 5	WrEndPointConfig() Command Code		0xC5		
Byte 6	Host ID & Retry		0x00		
Byte 7	SoC Sideband Port		0x04		
Byte 8	Register Byte 1 (LSB)		Address		
Byte 9	Register Byte 2				
Byte 10	Register Byte 3				
Byte 11	Register Byte 4 (MSB)				
Byte 12	PECI Data 1 (LSB)		Data = 1, 2, or 4 bytes		Sidebaoperation.
Byte 13	PECI Data 2				
Byte 14	PECI Data 3				
Byte 15	PECI Data 4 (MSB)				
Byte 16	AW FCS		0x00		Always set the value of Byte 16 to 0x00.

Table 30-28. WrEndPointConfig() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x03}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for Transaction errors • Byte 1 = 0x02 • Byte 2 = Error code defined in Table 30-6, "PECI Proxy Read." N = {0x03} indicates a successful PECI transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte3 = PECI completion code
Byte 1	Status Byte		CMD_STAT		See Byte[1] defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte[2] defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command

30.7.11 MCA Access via RdEndPointConfig()

An external agent can access the MCA banks over sideband using the RdEndPointConfig() command.

The registers that are accessed are shown in Table 30-29, "MCA Access via RdEndPointConfig()."

Table 30-29. MCA Access via RdEndPointConfig()

Register Type	Location	Register	MSR Address
MC Bank 4	Bunit	IA32_MC4_CTL	410h
		IA32_MC4_STATUS	411h
		IA32_MC4_ADDR	412h
		IA32_MC4_MISC	413h
MC Bank 5	P-Unit (PMU)	IA32_MC5_CTL	414h
		IA32_MC5_STATUS	415h
MC Bank 6	Aunit	IA32_MC6_CTL	418h
		IA32_MC6_STATUS	419h
		IA32_MC6_ADDR	41Ah
MC Bank 7	Dunit0	IA32_MC7_CTL	41Ch
		IA32_MC7_STATUS	41Dh
		IA32_MC7_MISC	41Fh
MC Bank 8	Dunit1	IA32_MC8_CTL	420h
		IA32_MC8_STATUS	421h
		IA32_MC8_MISC	423h

30.7.12 Endpoints supporting Rd/WrPCILocalConfig

The following endpoints can be accessed by the RdPCILocalConfig command.

Table 30-30. Endpoints Supporting Rd/WrPCIConfigLocal

IP Block	PCI B:D:F	CfgRd
VRP2 (for QAT)	B0:D6:F0	x
PCIe RP[0]	B0:D9:F0	X
PCIe RP[1]	B0:D10:F0	X
PCIe RP[2]	B0:D11:F0	X
PCIe RP[3]	B0:D12:F0	X
PCIe RP[4]	B0:D14:F0	X
PCIe RP[5]	B0:D15:F0	X
PCIe RP[6]	B0:D16:F0	X
PCIe RP[7]	B0:D17:F0	X
SATA Ctrl0	B0:D19:F0	X
SATA Ctrl1	B0:D20:F0	X
USB3	B0:D21:F0	X
VRP0 (for LAN Ctrl0)	B0:D22:F0	X
VRP1 (for LAN Ctrl1)	B0:D23:F0	X
HSUART	B0:D26:F{0, 1, 2}	X
LANCtrl0	By:Dx:F{0, 1, 2, …, 63}	X
LANCtrl1	Bz:Dx:F{0, 1, 2, …, 63}	x

30.7.13 Endpoints supporting Rd/WrEndPointConfig

The following endpoints can be accessed by the Rd/WrEndPointConfig command

Table 30-31. Endpoints Supporting Rd/WrEndPointConfig

EndPoint	Port ID (hex)	CfgRd	CfgWr
PUNIT0	46h	x	X
DUNIT_Shared	16h	X	
DUNIT0	10h	X	
DUNIT1	12h	X	
BUNIT0	4Ch	X	
TUNIT0	50h	X	
USB210	A7h	X	
PCIE1.D14	B3h	X	
PCIE1.D15	8Ah	X	
PCIE1.D16	8Bh	X	
PCIE1.D17	8Ch	X	
PCIE0.D9	B4h	X	
PCIE0.D10	8Dh	X	
PCIE0.D11	8Eh	X	
PCIE0.D12	8Fh	X	
SATA0:D19	B5h	X	
SATA1.D20	B6h	X	
KRM0	76h	X	
MAC0	77h	X	
MAC1	78h	X	

30.8 DRAM Thermal Capabilities

Various DRAM component temperature data can be accessed using the RdPkgConfig() and WrPkgConfig() PECI commands addressed to the SoC.

See Section 30.7.4, "RdPkgConfig()" and Section 30.7.5, "WrPkgConfig()" for the format of the commands. The accessible data structures are given in Table 30-32, "Summary of DRAM Thermal and Power Optimization Services" which contains the values of the command index, parameter, and PECI data fields.

Table 30-32. Summary of DRAM Thermal and Power Optimization Services (Sheet 1 of 2)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() Accumulated DRAM Energy Read	04	0xFF	DRAM Energy consumed by the DIMMs	Read the DRAM energy consumed by all the DIMMS in all the channels	DDR_ENERGY_STATUS (CSR), MSR_DRAM_ENERGY_STATUS (MSR 619h)
RdPkgConfig() DIMM Temperature Reading (CLTT only)	14	Channel Index	Absolute temperature in degrees Celsius: [7:0] DIMM#0 [15:8] DIMM#1 [23:16] DIMM#2 [31:24] DIMM#3 For OLTT, will return 0	Read the temperature of each DIMM within a channel	C[0/1]TEMPSTS[0/1]
WrPkgConfig() DRAM Rank Temperature Write	18	Channel Index and DIMM Index	Absolute temperature in degrees Celsius for ranks 0-3	Write the temperature for each rank within a single DIMM	None
RdPkgConfig() DRAM Channel Temperature Read (CLTT only)	22	0x0000	Absolute temperatures in degrees Celsius [7:0] Channel#0 [15:8] Channel#2 [31:16] Reserved For OLTT, will return 0	Read the maximum DRAM channel temperature	None
WrPkgConfig() RdPkgConfig() DRAM Power Limit Data	34	0x0000	DRAM Plane Power Limit Data	Write/Read DRAM Power Limit Data	DDR_RAPL_LIMIT (CSR), MSR_DRAM_POWER_LIMIT (MSR 618h)

Table 30-32. Summary of DRAM Thermal and Power Optimization Services (Sheet 2 of 2)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() DRAM Power Info Read	35	0x0000	Maximum DRAM power settings & maximum time window	Read DRAM power settings info to be used by power limiting entity	DRAM_POWER_INFO[63:32] (CSR) , MSR_DRAM_POWER_INFO[63:32] (MSR 61Ch)
RdPkgConfig() DRAM Power Info Read	36	0x0000	Typical and minimum DRAM power settings	Read DRAM power settings info to be used by power limiting entity	DRAM_POWER_INFO[31:0] (CSR) , MSR_DRAM_POWER_INFO[31:0] (MSR 61Ch)
RdPkgConfig() DRAM Power Limit Performance Status Read	38	0x0000	Accumulated DRAM throttle time	Read sum of all time durations for which each DRAM has been throttled	DDR_RAPL_PERF_STATUS (CSR), MSR_DRAM_PERF_STATUS (MSR 61Bh)

Figure 30-9. Channel Index and DIMM Index Parameter Word



Table 30-33. Channel Index and DIMM Index

Index Encoding	Physical Channel Number	Physical DIMM Number
000	0	0
001	1	1
010	Reserved	Reserved
011	Reserved	Reserved

30.8.1 DRAM Rank Temperature Write (Index = 18)

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." The DRAM rank temperature write allows the PECI host to program the processor with the temperature for all the ranks within a DIMM up to a maximum of four ranks. The programming data structure is defined in Figure 30-10, "Write DRAM Rank Temperature Data Dword."

Figure 30-10.Write DRAM Rank Temperature Data Dword



The DIMM index and channel index are specified through the parameter field as shown in Figure 30-9, "Channel Index and DIMM Index Parameter Word" and Table 30-33, "Channel Index and DIMM Index." This write is relevant to platforms that do not have on-die or on-board DIMM thermal sensors to provide memory temperature information or if the processor does not have direct access to the DIMM thermal sensors. This temperature information is used by the processor in conjunction with the activity-based DRAM temperature estimations. With this SoC product family, while temperature values are accepted on a per-rank basis, the SoC uses the average temperature over a given channel for throttling decisions.

30.8.2 DIMM Temperature Read (Index = 14)

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." This feature allows the PECI host to read the maximum temperature of all the DIMMs within a channel. If CLTT is disabled, the values returned will be 0. The SoC does not support activity-based temperature estimations. The returned data structure is shown in Figure 30-11, "Read DIMM Temperature Data Dword."

Figure 30-11.Read DIMM Temperature Data Dword



30.8.3 DRAM Channel Temperature Read (Index = 22)

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." This feature enables a PECI host read of the maximum temperature of each memory controller channel of the given product SKU. This includes all of the DIMMs within the channel and all the ranks within each of the DIMMs. If CLTT is disabled, the values returned will be 0 See the returned data structure as shown in Figure 30-12, "Read DRAM Channel Temperature Data Dword."

Figure 30-12.Read DRAM Channel Temperature Data Dword



30.8.4 DRAM Accumulated Energy Read (Index = 4)

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." This feature allows the PECI host to read the DRAM energy consumed by all the DIMMs in all the channels or all the DIMMs within just a specified channel. The channel index are specified through the parameter field. Units used are defined as per the Package Power SKU Unit read described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)." The data is tracked by a 32-bit counter that wraps around. The channel index in Figure 30-14, "Read DRAM Power Info Data Dword" is specified as per the index encoding described in Figure 30-25, "Temperature Target Read." While Intel requires reading the accumulated energy data at least once every 16 seconds to ensure functional correctness, a more realistic polling rate recommendation is once every 100 mS for better accuracy. This feature assumes a 200W memory capacity. In general, as the power capability decreases, so will the minimum polling rate requirement.

Figure 30-13.Read DRAM Accumulated Energy Data Dword



30.8.5 DRAM Power Info Read (Index = 35/36)

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." This read returns the minimum, typical and maximum DRAM power settings and the maximum time window over which the power can be sustained for the entire DRAM domain and is inclusive of all the DIMMs within all the memory channels. Any power values specified by the power limiting entity that is outside of the range specified through these settings cannot be guaranteed. Since this data is 64 bits wide, PECI facilitates access to this register by allowing two requests to read the lower 32 bits and upper 32 bits separately. Power and time units for this read are defined as per the Package Power SKU Unit settings described in Section 30.9, "CPU Thermal and Power Optimization Capabilities."

The minimum DRAM power corresponds to a minimum bandwidth setting of the memory interface. It does 'not' correspond to a processor IDLE or memory self-refresh state. The 'time window' in Figure 30-14, "Read DRAM Power Info Data Dword" is representative of the rate at which the SoC Power Management Unit (PMU) samples the DRAM energy consumption information and reactively takes the necessary measures to meet the imposed power limits. Programming too small a time window may not give the PMU enough time to sample energy information and enforce the limit while too large a time window runs the risk of the PMU not being able to monitor and take timely action on energy excursions. While the DRAM power setting in Figure 30-14, "Read DRAM Power Info Data Dword" provides a maximum value for the 'time window' (typically a few seconds), the minimum value may be assumed to be ~100 mS.

The Power Management Controller (PMC) programs the DRAM power settings described in Figure 30-14, "Read DRAM Power Info Data Dword" when DRAM characterization has been completed by the memory reference code (MRC) during boot as indicated by the setting of the MC_BIOS_REQ register. The DRAM power settings will be programmed during boot independent of the 'DRAM Power Limit Enable' bit setting. In general, any tuning of the power settings is done by polling the voltage regulators supplying the DIMMs.

Figure 30-14.Read DRAM Power Info Data Dword



30.8.6 DRAM Power Limit Data Read/Write (Index = 34)

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." This feature allows the PECI host to program the power limit over a specified time or control window for the entire DRAM domain covering all the DIMMs within all the memory channels. Actual values are chosen based on DRAM power consumption characteristics. The units for the DRAM Power Limit and Control Time Window are determined as per the Package Power SKU Unit settings described in Table 30.9.2, "Package Power SKU Unit Read (Index = 30)." The DRAM Power Limit Enable bit should be set to activate this feature. Exact DRAM power limit values are largely determined by platform memory configuration. As such, this feature is disabled by default and there are no defaults associated with the DRAM power limit values. The PECI host may be used to enable and initialize the power limit fields for the purposes of DRAM power budgeting. Alternatively, this can also be accomplished through inband writes to the appropriate registers. Both power limit enabling and initialization of power limit values can be done in the same command cycle. All RAPL parameter values including the power limit value, control time window, and enable bit will have to be specified correctly even if the intent is to change just one parameter value when programming over PECI.

The following conversion formula should be used for encoding or programming the 'Control Time Window' in bits [23:17].

Control Time Window (in seconds) = ([1 + 0.25 * 'x'] * $2^{'y'}$) * 'z' where

'x' = integer value of bits[23:22]

'y' = integer value of bits[21:17]

'z' = Package Power SKU Time Unit[19:16] (see Table 30.9.2, "Package Power SKU Unit Read (Index = 30)" for details on Package Power SKU Unit)

For example, using this formula, a control time value of 0x0A will correspond to a '1-second' time window.

Figure 30-15.DRAM Power Limit Data



From a DRAM power management standpoint, all post-boot DRAM power management activities (also referred to as 'DRAM RAPL' or 'DRAM Running Average Power Limit') should be managed exclusively through a single interface like PECI or alternatively an inband mechanism. If PECI is being used to manage DRAM power budgeting activities, BIOS should lock out all subsequent inband DRAM power limiting accesses by setting bit 31 of the DRAM_POWER_LIMIT MSR or DRAM_PLANE_POWER_LIMIT CSR to '1'.

30.8.7 DRAM Power Limit Performance Status Read

See Table 30-32, "Summary of DRAM Thermal and Power Optimization Services." This feature allows the PECI host to assess the performance impact of the currently active DRAM power limiting modes. The read return data contains the sum of all the time durations for which each of the DIMMs has been operating in a low power state. This information is tracked by a 32-bit counter that wraps around. The unit for time is determined as per the Package Power SKU Unit settings described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)" The DRAM performance data does not account for stalls on the memory interface.

Figure 30-16.DRAM Power Limit Performance Data



In general, for the purposes of DRAM RAPL, the DRAM power management entity should use PECI accesses to DRAM energy and performance status in conjunction with the power limiting feature to budget power between the various memory sub-systems in the server system.

30.9 CPU Thermal and Power Optimization Capabilities

Table 30-34, "Summary of CPU Thermal and Power Optimization Services" provides a summary of the power and thermal optimization capabilities that can be accessed over PECI for this SoC product family. Twenty-three services are shown and each is described in the subsections following the table.

Note: The index field values are referenced as decimal numbers.

Table 30-34, "Summary of CPU Thermal and Power Optimization Services" also shows alternate in-band mechanisms to access similar or equivalent information where applicable for register read and write services.

The BIOS is required to populate CPUID, PlatformID and the CPU microcode update revision.

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 1 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() Package Identifier Read Section 30.9.1, on page 848	00	0x0000	CPU ID Information	Returns processor-specific information including CPU family, model and stepping information.	Execute the CPUID instruction to get the processor signature.
		0x0001	Platform ID	Used to ensure microcode update compatibility with the processor.	IA32_PLATFORM_ID (MSR 17h)
		0x0002	PCU Device ID	Returns the device ID information for the processor PMU.	
		0x0003	Max Thread ID	Returns the maximum thread ID value supported by the processor.	
		0x0004	CPU Microcode Update Revision	Returns the processor microcode and internal power control-unit firmware revision information.	IA32_BIOS_SIGN_ID (MSR 8Bh)
		0x0005	MCA Error Source Log	Returns the MCA error source log.	MCA_ERR_SRC_LOG (CSR)

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 2 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
WrPkgConfig() VR Debug Interface	01	0x0000	[03:00] VR ID. 00h Vcc 01h Vnn 03h VccSram 02h Memory 06h [08:04] VR command. GetReg (0x07) supported. For illegal commands, return ILLEGAL_CMD completion code. [15:09] Reserved. Fail with ILLEGAL_DATA if non-zero. [23:16] VR register address or VID data. [31:24] Reserved. Fail with ILLEGAL_DATA if non-zero.	Read VR Register data through the VR12.x GetReg command. Data is returned in WrPkgConfig() response	
RdPkgConfig() Package Temperature Read Section 30.9.5, "Package Temperature Read (Index = 2)"	02		[15:0] Reserved [22:16] Processor package Temperature relative to PROCHOT	Returns the maximum processor die temperature (average) in PECI format.	P_CR_PACKAGE_THERM_STATUS (CSR)
RdPkgConfig() Accumulated Energy Status Read Section 30.9.11, "Accumulated Energy Status Read (Index = 3)"	03	0x0 = Vcc Energy 0xFF = SoC (Total Pkg Energy)	Accumulated CPU energy	Returns the value of the energy consumed by just the VCC power plane or the entire SoC.	PACKAGE_ENERGY_STATUS (CSR), MSR_PKG_ENERGY_STATUS (MSR 611h)
RdPkgConfig() Efficient Performance Indication (EPI)	06	0x0000	Number of productive processor cycles	Read number of productive cycles for power budgeting purpose	None

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 3 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() Package Power Limit Performance Status Read Section 30.9.13, "Package Power Limit Performance Status Read (Index = 8)"	08	0x00FF: CPU package	Accumulated CPU throttle time	Read the total time for which the processor package was throttled due to power limiting.	PACKAGE_RAPL_PERF_STATUS (CSR), MSR_PKG_PERF_STATUS (MSR 613h)
RdPkgConfig() Per Core DTS Temperature Read Section 30.9.6, "Per Core DTS Temperature Read (Index = 9)"	09	0x0000 *through* 0x0017: Cores 0 *through* 15 **0xfd**: SoC temperature sensor 0 **0xfe**: SoC temperature sensor 1 **0xff**: SoC temperature sensor 2	Per core DTS maximum temperature [15:0] Module MAX temperature (same format as in Package Temperature) [32:16] Reserved	Read the maximum DTS temperature of a particular core or the system agent within the processor die in the relative PECI temperature format.	IA32_THERM_STATUS (MSR 19C)
THERM_MARGIN	10	0x10	N/A	Format S16.7.8 Read the thermal margin to spec (DTS 2.0) Margin offset relative to T-Control.	P_CR_PACKAGE_THERM_MARGIN_0_0_0_MCHBAR (CSR) PACKAGE_THERM_MARGIN (MSR 1A1h)
RdPkgConfig() Socket Power Throttled Duration	11	0x0000	Duration of the SoC operating condition	Returns the duration for which RAPL power limit determined the operating condition	None
WrPkgConfig() Configure Current Limit	15	0x0000	Current Limit	Configure the maximum current to limit the SoC power	MSR_VR_CURRENT_CONFIG (MSR 601h)

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 4 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() Temperature Target Read Section 30.9.7, "Temperature Target Read (Index = 16)"	16	0x0000	[7:0] Reserved [15:8] TCONTROL value which indicates the relative offset from PROCHOT [23:16] PROCHOT temperature where the Thermal Monitor is activated. [27:24] Temperature offset in degrees (C) from the PROCHOT. If offset is set the Thermal Monitor will occur at lower than PROCHOT.	Returns the maximum processor junction temperature, PROCHOT and processor $T_{CONTROL}$.	TEMPERATURE TARGET (CSR), MSR_TEMPERATURE_TARGET (MSR 1A2h)
RdPkgConfig() Current Limit Read Section 30.9.10, "Current Limit Read (Index = 17)"	17	0x00FF	Current Limit	Reads the current limit on the VCC power plane	MSR_VR_CURRENT_CONFIG[31:0] (MSR 601h)
RdPkgConfig() Package Thermal Status	20	0x0000	Thermal Status Register	Read the thermal status register and optionally clear any log bits.The register includes status and log bits for TCC activation, PROCHOT_N assertion & critical temperature	IA32_PACKAGE_THERM_STATUS (MSR 1B1H)
WrPkgConfig() Package Power limits For multiple Turbo Modes Section 30.9.12, "Package Power Limits For Multiple Turbo Modes (Index = 26 and 27)"	26	0x0000	Power Limit 1 Data	Write power limit 1 data in multiple turbo mode.	PACKAGE_RAPL_LIMIT (CSR), MSR_PKG_POWER_LIMIT (MSR 610h)

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 5 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() Package Power Limits For multiple Turbo Modes Section 30.9.12, "Package Power Limits For Multiple Turbo Modes (Index = 26 and 27)"	27	0x0000	Power Limit 2 Data	Read power limit 2 data in multiple turbo mode.	PACKAGE_RAPL_LIMIT (CSR), MSR_PKG_POWER_LIMIT (MSR 610h)
RdPkgConfig() Package Power SKU Read Section 30.9.3, "Package Power SKU Read (Index = 28 and 29)"	28	0x0000	Package Power SKU [31:0]	Returns Thermal Design Power (TDP) and minimum package power for the SoC product SKU.	PACKAGE_POWER_SKU (CSR), MSR_PKG_POWER_INFO (MSR 614h)
RdPkgConfig() Package Power SKU Read Section 30.9.3, "Package Power SKU Read (Index = 28 and 29)"	29	0x0000	Package Power SKU[64:32]	Returns the maximum package power value for the SoC product SKU and the maximum time interval for which it can be sustained.	PACKAGE_POWER_SKU (CSR), MSR_PKG_POWER_INFO (MSR 614h)
RdPkgConfig() Package Power SKU Unit Read Section 30.9.2, "Package Power SKU Unit Read (Index = 30)"	30	0x0000	Time, Energy and Power Units	Read units for power, energy and time used in the power control registers.	PACKAGE_POWER_SKU_UNIT (CSR), MSR_RAPL_POWER_UNIT (MSR 606h)
RdPkgConfig() Total Time Section 30.9.4, "Accumulated Run Time Read (Index = 31)"	31	0x0000	Elapsed time	Returns the total run time in ms. Total accumulated run time reported in IO_TSC_LOW. 31:0 - lower 32 bits of the UNCORE Time Stamp Counter.	IA32_TIME_STAMP_COUNTER (MSR 10h)
		0x00FE	64-bit counter indicating the aggregate of C0 residency count from all cores		
		0x00FF	32 MSBs of 64-bit counter indicating the aggregate of C0 residency count from all cores		

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 6 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
RdPkgConfig() Thermally Constrained Time Read Section 30.9.9, "Thermally Constrained Time Read (Index = 32)"	32	0x0000	Thermally Constrained Time	Read the time for which the processor has been operating in a lowered power state due to internal TCC activation.	None
WrPkgConfig() RdPkgConfig() ACPI P-T Notify Write/Read	33	0x0000	New p-state equivalent of P1 used in conjunction with package power limiting	Notify/Read the processor PCU to determine the p-state that is one state below the turbo frequency as specified through the last ACPI Notify	None
RdPkgConfig() Read Ratio constraints	49		[0:0] fused or resolved - 0h: fused - 1h: resolved [4:1] AVX level - 0h: non- AVX - 1h: AVX - 2h: AVX3 [11:5] core count input (0h - 7Fh).	Input value for core count returns turbo ratio limits for core counts. 4x+1, 4x+2, 4x+3, 4x+4 in bits 0-7, 8-15, 16-23, 24-31 If 4x+y, y = {1,2,3,4} is not a valid core count, returns FFh as the limit.	
WrPkgConfig() RdPkgConfig() Read/Write Ratio Limit	50	0x0000	Ratio Limit	Reads/ Writes Turbo Ratio Limit	

Table 30-34. Summary of CPU Thermal and Power Optimization Services (Sheet 7 of 7)

Service	Index Field (Decimal)	Parameter Field (Word)	PECI Data Field (DWord)	Description	Alternate In-band MSR or CSR Access
PL3	57	0x0000	PECI Configuration of Package PL3 Limit	[14:0] power limit in 2^(POWER_UNIT) watts [15:15] Power limit control enable [16:16] Reserved [23:17] Control Time Windows [30:24] Duty Cycle in percentage. Max value of 100% [31:31] Lock bit. If set, this command is locked out from future writes and all other data in this command is ignored	
GetCrashDumpDetails	51	Get Crash dump details		Get the details of the Crash Dump.	
GetCrashDumpFrame	52	Get Frame		Gets a particular frame in the specified crash dump	

30.9.1 Package Identifier Read (Index = 0)

This feature enables the PECI host to uniquely identify the PECI client processor. The parameter field encodings shown in Table 30-34, "Summary of CPU Thermal and Power Optimization Services" allow the PECI host, typically the BMC, to access the relevant processor information as described below.

30.9.1.1 CPU ID Information

This is data field contains the equivalent information that can be accessed through executing the Intel® architecture CPUID instruction. It contains the processor type, stepping, model, and family ID information as shown in Figure 30-17, "CPU ID Data."

Figure 30-17.CPU ID Data



30.9.1.2 Platform ID

This data field can be used to ensure processor microcode updates are compatible with the processor.

Note: The value of the platform ID or processor flag[2:0] as shown in Figure 30-18, "Platform ID Data" is typically unique to the platform type and processor stepping.

Figure 30-18.Platform ID Data

30.9.1.3 PCU Device ID

This information can be used to uniquely identify the processor power control unit (PCU) device when combined with the Vendor Identification register content and remains constant across all SKUs. Refer to the appropriate register description for the exact processor PCU Device ID value.

Figure 30-19.PCU Device ID Data



30.9.1.4 Maximum Thread ID

This is data field provides the number of supported processor threads.

Note: This value is dependent on the number of cores within the processor as determined by the processor SKU and is independent of whether certain cores or corresponding threads are enabled or disabled. See Figure 30-20, "Maximum Thread ID Data."

Figure 30-20.Maximum Thread ID Data



30.9.1.5 CPU Microcode Update Revision

This data field reflects the revision number for the microcode update and power control unit firmware updates on the processor sample.

Note: The revision data is a unique 32-bit identifier that reflects a combination of specific versions of the processor microcode and power control unit firmware. See Figure 30-21, "Processor Microcode Revision."

Figure 30-21.Processor Microcode Revision



30.9.1.6 MCA Error Source Log

This is data field contains contents of the Machine-Check Architecture (MCA) Error Source Log register. See Figure 30-22, "Package Power SKU Unit Data" for details. The register indicates the value as defined when IERR and/or MCERR are indicated by the SoC.

30.9.2 Package Power SKU Unit Read (Index = 30)

This feature enables the PECI host to read the units of time, energy, and power used in the processor and DRAM power control registers for calculating power and timing parameters. In Figure 30-22, "Package Power SKU Unit Data," the default values are:

- Power unit field [3:0] = 0011b
- Energy unit field [12:8] = 10000b
- Time unit field [19:16] = 1010b

Actual unit values are calculated as shown in Table 30-35, "Power Control Register Unit Calculations."

Figure 30-22. Package Power SKU Unit Data



Table 30-35. Power Control Register Unit Calculations

Unit Field	Value Calculation	Default Value
Time	1s / 2^TIME UNIT	1s / 2^10 = 976 µs
Energy	1J/2^ENERGY UNIT	1J/2^16 = 15.3 µJ
Power	1W/2^POWER UNIT	1W/2^3 = 1/8 W

30.9.3 Package Power SKU Read (Index = 28 and 29)

This read allows the PECI host to access the minimum, Thermal Design Power (TDP) and maximum power settings for the processor package SKU. It also returns the maximum time interval or window over which the power can be sustained. If the power limiting entity specifies a power limit value outside of the range specified through these settings, power regulation cannot be guaranteed. Since this data is 64-bits wide, PECI facilitates access to this register by allowing two requests to read the lower 32 bits and upper 32 bits separately as shown in Figure 30-23, "Package Power SKU Data." Power units for this read are determined as per the package power SKU unit settings described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)."

Figure 30-23.Package Power SKU Data



The package power SKU data is programmed by the SoC internal Power Control Unit (PCU) firmware during boot time based on SKU dependent power-on default values set during SoC manufacturing. The TDP package power specified through bits [14:0] in Figure 30-23, "Package Power SKU Data" is the maximum value of the Power Limit1 field described in Section 30.9.12, "Package Power Limits For Multiple Turbo Modes (Index = 26 and 27)" while the maximum package power in bits [46:32] is the maximum value of the Power Limit2 field which is also described in Section 30.9.12, "Package Power Limits For Multiple Turbo Modes (Index = 26 and 27)."

The minimum package power in bits [30:16] is applicable to both the Power Limit1 and Power Limit2 fields and corresponds to a mode when all the cores are operational and in their lowest frequency mode. Attempts to program the power limit below the minimum power value may not be effective since the BIOS/OS, and not the integrated PCU, controls disabling of cores and core activity.

Maximum time window in bits [54:48] is representative of the maximum rate at which the internal PCU can sample the package energy consumption and reactively take the necessary measures to meet the imposed power limits. Programming too-large of a time window runs the risk of the PCU not being able to monitor and take timely action on package energy excursions. On the other hand, programming too-small of a time window may not give the PCU enough time to sample energy information and enforce the limit. The minimum value of the "time window" can be obtained by reading bits [21:15] of the PWR_LIMIT_MISC_INFO CSR using the PECI RdPCIConfigLocal() command.

30.9.4 Accumulated Run Time Read (Index = 31)

This services provides support for 2 accumulated runtime reads.

- 0x0000: This read returns the total time for which the processor has been executing with a resolution of 1 ms per count. This is tracked by a 32-bit counter that rolls over on reaching the maximum value. This counter activates and starts counting for the first time when the SoC desserts the active-low CPU_RESET_N output signal pin.
- 0x00FE: This read returns the total time for which the processor has been in C0 with a resolution of 1 ms per count. This is tracked by a 32-bit counter that rolls over on reaching the maximum value. This counter activates and starts counting for the first time when the SoC deasserts the active-low CPU_RESET_N output signal pin.

30.9.5 Package Temperature Read (Index = 2)

This read returns the maximum processor die temperature in a 16-bit PECI format. The upper 16 bits of the response data are reserved. See Figure 30-24, "Package Temperature Read Data." The PECI temperature data returned by this read is the instantaneous value and not the average value as is returned by the PECI GetTemp() described in Section 30.6.4, "PECI Proxy Command Trigger."

Figure 30-24.Package Temperature Read Data



30.9.6 Per Core DTS Temperature Read (Index = 9)

This feature enables the PECI host to read the maximum value of the Digital Thermal Sensor (DTS) temperature for any specific core within the processor. Alternatively, this service can be used to read the internal SoC System Agent (SSA) temperature. The temperature is returned in the same data format as described in Section 30.9.5, "Package Temperature Read (Index = 2)." Data is returned in a relative PECI temperature format.

Reads to a parameter value outside the supported range return an error as indicated by a completion code of 0x90. The supported range of parameter values can vary depending on the number of processor cores within the SoC. The temperature data returned through this feature is the instantaneous value and not the average value. It is updated once every 1 ms.

30.9.7 Temperature Target Read (Index = 16)

The temperature target read allows the PECI host to access the maximum processor junction temperature (T_{J-MAX}) in degrees Celsius. This is also the default temperature value at which the processor thermal control circuit activates. The T_{J-MAX} value may vary from processor part to part to reflect manufacturing process variations.

The temperature target read also returns the processor $T_{CONTROL}$ value. The $T_{CONTROL}$ is returned in a standard PECI temperature format and represents the threshold temperature used by the thermal management system for a fan speed control.

See Figure 30-27.

Figure 30-25.Temperature Target Read



30.9.8 Package Thermal Status Read / Clear (Index = 20)

The Thermal Status Read provides information on package level thermal status. Data includes:

- Thermal Control Circuit (TCC) activation
- Bidirectional PROCHOT_N signal assertion
- Critical Temperature

Both status and sticky log bits are managed in this status word. All sticky log bits are set upon a rising edge of the associated status bit and the log bits are cleared only by Thermal Status reads or a processor reset. A read of the Thermal Status word always includes a log bit clear mask that allows the host to clear any or all of the log bits that it is interested in tracking.

A bit set to '0' in the log bit clear mask will result in clearing the associated log bit. If a mask bit is set to '0' and that bit is not a legal mask, a failing completion code will be returned. A bit set to '1' is ignored and results in no change to any sticky log bits. For example, to clear the TCC Activation Log bit and retain all other log bits, the Thermal Status Read should send a mask of 0xFFFFFFFD.

Figure 30-26.Package Thermal Status Read/Clear



30.9.9 Thermally Constrained Time Read (Index = 32)

This feature allows the PECI host to access the total time for which the processor has been operating in a lowered power state due to Thermal Control Circuit (TCC) activation. The returned data includes the time required to ramp back up to the original P-State target after the TCC activation expires. This timer does not include TCC activation as a result of an external assertion of the SoC PROCHOT_N signal pin. This is tracked by a 32-bit counter with a resolution of 1 ms per count that rolls over or wraps around. Concerning the processor PECI clients, the only logic that can be thermally constrained are those which are supplied by VCC.

30.9.10 Current Limit Read (Index = 17)

This read returns the current limit for the processor VCC power plane in 1/8-ampere increments. Actual current limit data is contained only in the lower 13 bits of the response data. The default return value of 0x140 corresponds to a current limit value of 40 amperes. Bit 31 is a lock bit indicating that the IccMax has been locked to the returned value in bits 0-12.See Figure 30-27, "Current Limit Read Data."

Figure 30-27.Current Limit Read Data



30.9.11 Accumulated Energy Status Read (Index = 3)

This service can return the value of the total energy consumed by the entire processor package or just the logic supplied by the VCC power plane as specified through the parameter field in Table 30-34, "Summary of CPU Thermal and Power Optimization Services." This information is tracked by a 32-bit counter that wraps around and continues counting on reaching its limit. See Figure 30-28, "Accumulated Energy Read Data." Energy units for this read are determined as per the package power SKU unit settings described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)."

Figure 30-28.Accumulated Energy Read Data



While Intel requires reading the accumulated energy data at least once every 16 seconds to ensure functional correctness, a more realistic polling rate recommendation is once every 100 ms for better accuracy. In general, as the power capability decreases, so will the minimum polling rate requirement. Intel recommends to tune the polling rate to reduce the potential impact on other power management features.

30.9.12 Package Power Limits For Multiple Turbo Modes (Index = 26 and 27)

This feature allows the PECI host to program two power limit values to support multiple turbo modes. The operating systems and drivers can balance the power budget using these two limits. Two separate PECI requests are available to program the lower and upper 32 bits of the power limit data shown in Figure 30-29, "Package Turbo Power Limit Data."

Figure 30-29.Package Turbo Power Limit Data



The units for the power limit and control time window are determined as per the package power SKU unit settings described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)," while the valid range for the power limit values are determined by the package power SKU settings described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)" and Section 30.9.3, "Package Power SKU Read (Index = 28 and 29)."

Setting the Clamp Mode bits is required to allow the cores to go into power states below what the operating system originally requested. The Power Limit Enable bits should be set to enable the power limiting function. Power limit values, Enable, and Clamp Mode bits can all be set in the same command cycle.

Intel recommends exclusive use of just one entity or interface, PECI for instance, to manage all processor package power limiting and budgeting needs. If PECI is being used to manage package power limiting activities, the BIOS should lock out all subsequent in-band package power limiting accesses by setting bit 31 of the MSR_PKG_POWER_LIMIT (MSR 610h) or TURBO_POWER_LIMIT (SoC sideband Port 04h, offset 7 and 8) register to 1.

Power Limit #1 is intended to limit processor power consumption to any reasonable value below TDP and defaults to TDP. Power Limit #1 values may be impacted by the processor heat sinks and system air flow. Processor Power Limit #2 can be used as appropriate to limit the current drawn by the processor to prevent any external power supply unit issues. Power Limit #2 should always be programmed to a value (typically 20%) higher than Power Limit #1 and has no default value associated with it.

Though this feature is disabled by default and external programming is required to enable, initialize, and control the package power limit values and time windows, the processor package will still turbo to TDP if Power Limit #1 is not enabled or initialized. Control Time Window #1 values may be programmed to be within a range of 100 ms-10 seconds. Control Time Window #2 values should be in the range 40 ns to 10 ms.

The same conversion formula used for the DRAM Power Limiting feature (see Section DRAM Power Limit Data Read/Write) should be applied when programming the 'Control Time Window' in bits [23:17] and [55:49].

30.9.13 Package Power Limit Performance Status Read (Index = 8)

This service allows the PECI host to assess the performance impact of the currently active power limiting modes. The read return data contains the total amount of time for which the entire processor package has been operating in a power state that is lower than what the operating system originally requested. This information is tracked by a 32-bit counter that wraps around. See Figure 30-30, "Package Power Limit Performance Data." The unit for time is determined as per the package power SKU unit settings described in Section 30.9.2, "Package Power SKU Unit Read (Index = 30)."

Figure 30-30.Package Power Limit Performance Data



30.9.14 Efficient Performance Indicator Read (Index = 6)

The Efficient Performance Indicator (EPI) Read provides an indication of the total number of productive cycles. Specifically, these are the cycles when the processor is engaged in any activity to retire instructions and as a result, consuming energy. Any power management entity monitoring this indicator should sample it at least once every 4 seconds to enable detection of wraparounds.

Figure 30-31.Efficient Performance Indicator Data



30.9.15 ACPI P-T Notify Write and Read (Index = 33)

This feature enables the processor turbo capability when used in conjunction with the PECI package RAPL or power limit. When the BMC sets the package power limit to a value below TDP, it also determines a new corresponding turbo frequency and notifies the OS using the 'ACPI Notify' mechanism as supported by the _PPC or performance present capabilities object. The BMC then notifies the processor PCU using the PECI 'ACPI P-T Notify' service by programming a new state that is one p-state below the turbo frequency sent to the OS via the _PPC method.

When the OS requests a p-state higher than what is specified in bits [7:0] of the PECI ACPI P-T Notify data field, the CPU will treat it as request for P0 or turbo. The PCU will use the IA32_ENERGY_PERFORMANCE_BIAS register settings to determine the exact extent of turbo. Any OS p-state request that is equal to or below what is specified in the PECI ACPI P-T Notify will be granted as long as the RAPL power limit does not impose a lower p-state. However, turbo will not be enabled in this instance even if there is headroom between the processor energy consumption and the RAPL power limit.

This feature does not affect the Thermal Monitor behavior of the processor nor is it impacted by the setting of the power limit clamp mode bit.

Figure 30-32.ACPI P-T Notify Data



30.9.16 Package PL3 (Index = 53)

PL3 is a package limit that is defined for the overall SoC in support of a PSU requirement of a strict duty cycle enforcement for points above PL2. This allows the PSU to be designed for application power draw, rather than virus.

Figure 30-33.PL2 and PL3



Figure 30-34.PL3 Register Definition



The defaults values are:

Power Limit: 1.25 TDP
Enable: Always set
Time Window: 8 ms
Duty-Cycle: 25%

30.9.17 Read Ratio Constraints (Index = 49)

Read constraints takes a single parameter that indicates the desired information

Figure 30-35.Read Ratio Constraints Parameter



Bit [0] indicates fused or resolved. 0:fused, 1: resolved.
Bit [4:1] indicate AVX level. 0h: non-AVX, 1h: AVX, 2h: AVX3.
Bits [11:5] indicate core count input x (0h - 7Fh).

The return value is shown in Figure 30-36, "Read Ratio Constraints Return Value."

Figure 30-36.Read Ratio Constraints Return Value



- If 4x + y, y = {1,2,3,4} is not a valid core count, returns ffh as the limit.

30.9.18 Read Ratio Limit

This read returns the ratio limit.

Figure 30-37.Read Ratio Limit



30.9.19 Write Ratio Limit

The ratio limit is defined in the data field.

Figure 30-38.Write Ratio Limit



30.10 Crash Dump

Crash Dump is implemented as a RdPkgConfig Command.

30.10.1 GetCrashDumpCapabilities (Index=51)

This feature returns the details of a crash dump. When parameter#0 is:

0x0 - returns the size info:

Figure 30-39.Crash Dump Capabilities Details



0x1 - returns the number of frames:

Figure 30-40.Crash Dump Capabilities (Parameter0 = 0x1)



30.10.2 GetCrashDumpFrame (Index = 52)

This feature gets a particular frame in the specified crash dump. When requesting the frame, the frame# is passed as a parameter. A maximum of 2^16 frames is only supported, starting at frame '0'.

Figure 30-41.Request Parameters



Figure 30-42.Response Data for Requested Frame



30.10.3 UnCore and PM Crash Dump Registers

The following are the registers visible in crash dump. The purpose of these registers is to enable customers to gather important system information when a crash happens in their system and to provide the information contained in these registers to Intel for analysis.

Table 30-36. Response Data for Requested Items

Type	Source	Register	Size Each (B)	Granularity	Count	Total Size	Offset
HEADER	Block	ART	8	1	1	8	0
HEADER	PUNIT	Crashlog Version	4	1	1	4	8
HEADER	PUNIT	Reason for Record	4	1	1	4	12
HEADER	PUNIT	Punit Patch version	4	1	1	4	16
PADDING							
REG	BUNIT	RESERVED_1	4	1	1	4	32
REG	BUNIT	RESERVED_2	4	1	1	4	36
REG	AUNIT	RESERVED_3	4	1	1	4	40
REG	DUNIT	RESERVED_4	4	1	1	4	44
REG	DUNIT	RESERVED_5	4	1	1	4	48
REG	DUNIT	RESERVED_6	4	PER_DUNIT	2	8	52
REG	DUNIT	RESERVED_7	4	PER_DUNIT	2	8	60
REG	DUNIT	RESERVED_8	4	PER_DUNIT	2	8	68
REG	DUNIT	RESERVED_9	4	PER_DUNIT	2	8	76
REG	DUNIT	RESERVED_10	4	PER_DUNIT	2	8	84
REG	DUNIT	RESERVED_11	4	PER_DUNIT	2	8	92
REG	DUNIT	RESERVED_12	4	PER_DUNIT	2	8	100
REG	DUNIT	RESERVED_13	4	PER_DUNIT	2	8	108
REG	DUNIT	RESERVED_14	4	PER_DUNIT	2	8	116
REG	DUNIT	RESERVED_15	4	PER_DUNIT	2	8	124
REG	SVID	RESERVED_16	4	1	1	4	132
REG	SVID	RESERVED_17	4	1	1	4	136
REG	SVID	RESERVED_18	4	1	1	4	140
REG	SVID	RESERVED_19	4	1	1	4	144
REG	TUNIT	STATUS/RESERVED_20	8	PER_MODULE	8	64	148
REG	PUNIT	RESERVED_21	4	1	1	4	212
REG	PUNIT	P_CR_MEM_THERM_STATUS	4	1	1	4	216
REG	PUNIT	P_CR_MEM_THERM_INT_STATUS	4	1	1	4	220
REG	PUNIT	P_CR_IA_PERF_LIMIT_REASONS	4	1	1	4	224
REG	BUNIT	RESERVED_22	4	1	1	4	228
REG	BUNIT	RESERVED_23	4	1	1	4	232
REG	PECI	RESERVED_24	4	1	1	4	236
REG	PECI	RESERVED_25	4	1	1	4	240
REG	PECI	RESERVED_26	4	1	1	4	244
REG	USB	PORTLI5	4	1	1	4	248

Table 30-36. Response Data for Requested Items

Type	Source	Register	Size Each (B)	Granularity	Count	Total Size	Offset
REG	USB	PORTLI6	4	1	1	4	252
REG	USB	PORTLI7	4	1	1	4	256
REG	USB	PORTLI8	4	1	1	4	260
REG	USB	USB2_PORT_STATE_REG	8	2	2	16	264
REG	USB	USB3_PORT_STATE_REG	8	2	2	16	280
REG	IOMMU	FSTS_REG_0_0_0_VTDBAR	4	1	1	4	296
REG	GBE	RESERVED_27	8	PER_GBE	2	16	300
REG	GBE	RESERVED_28	8	PER_GBE	2	16	316
REG	GBE	RESERVED_29	8	PER_GBE	2	16	332
REG	GBE	RESERVED_30	8	PER_GBE	2	16	348
REG	GBE	LINKS	8	PER_GBE	2	16	364
REG	GBE	RESERVED_31	8	PER_GBE	2	16	380
REG	GBE	RESERVED_32	8	PER_GBE	2	16	396
REG	GBE	RESERVED_33	8	PER_GBE	2	16	412
REG	GBE	RESERVED_34	8	PER_GBE	2	16	428
REG	GBE	RESERVED_35	8	PER_GBE	2	16	444
REG	GBE	RESERVED_36	8	PER_GBE	2	16	460
REG	GBE	RESERVED_37	8	PER_GBE	2	16	476
PADDING						292	
COREPMA	GLM	RESERVED_38	4	PER_MODULE	8	32	768
COREPMA	GLM	RESERVED_39	4	PER_MODULE	8	32	800
COREPMA	GLM	RESERVED_40	4	PER_MODULE	8	32	832
COREPMA	GLM	RESERVED_41	4	PER_MODULE	8	32	864
COREPMA	GLM	RESERVED_42	4	PER_MODULE	8	32	896
COREPMA	GLM	RESERVED_43	4	PER_MODULE	8	32	928
COREPMA	GLM	RESERVED_44	4	PER_MODULE	8	32	960
COREPMA	GLM	RESERVED_45	4	PER_MODULE	8	32	992
PADDING						32	
IOREG	PUNIT	RESERVED_46	4	N/A	0	0	1024
IOREG	PUNIT	RESERVED_47	4	PER_CORE	16	64	1024
IOREG	PUNIT	RESERVED_48	4	PER_MODULE	8	32	1088
IOREG	PUNIT	RESERVED_49	4	N/A	0	0	1120
IOREG	PUNIT	RESERVED_50	4	N/A	0	0	1120
IOREG	PUNIT	RESERVED_51	4	1	1	4	1120
IOREG	PUNIT	RESERVED_52	4	N/A	0	0	1124
IOREG	PUNIT	RESERVED_53	4	PER_CORE	16	64	1124
IOREG	PUNIT	RESERVED_54	4	PER_CORE	16	64	1188
IOREG	PUNIT	RESERVED_55	4	N/A	0	0	1252
IOREG	PUNIT	RESERVED_56	4	N/A	0	0	1252

Table 30-36. Response Data for Requested Items

Type	Source	Register	Size Each (B)	Granularity	Count	Total Size	Offset
IOREG	PUNIT	RESERVED_57	4	1	1	4	1252
IOREG	PUNIT	RESERVED_58	4	N/A	0	0	1256
IOREG	PUNIT	RESERVED_59	4	N/A	0	0	1256

30.10.4 Core Crash Dump

30.10.4.1 Overview

Core crash dump provides the SoC with the ability to dump the core registers (including the SQ) when a 3-strike crash takes place. To provide this capability, RdPkgConfig has been implemented to access the core crash dump.

30.10.4.2 PECI Command Structure

RdPkgCOnfig is used with index 0x51. The parameter field is divided into 2 bytes. Byte0 is always 0x2 and Byte1 is the coreindex.

Table 30-37. RdPkgConfig() PECI Proxy Block Write

SMBus	Function		Value	Data Source	Comment
Slave Address (Write)	Write Address	SMBus Command	0x4C	BMC	
Command Code	PECI Mode command code		0x62		
Byte Count	N	Control Data	0x09		
Byte 1	SMBus-PECI Handshake Control		0x00		Value = 0x00 No AW FCS Required
Byte 2	PECI Client Address	PECI Command	0x30		Socket ID. Always 0x30 for the SoC.
Byte 3	PECI Write Length		0x05		
Byte 4	PECI Read Length		{0x02, 0x3, 0x5}		
Byte 5	RdPkgConfig() Command Code		0xA1		
Byte 6	Host ID and Retry		0x00		
Byte 7	Index		51		See Section 30.7.11, "MCA Access via RdEndPointConfig()" and Section 30.9, "CPU Thermal and Power Optimization Capabilities" for the supported capabilities and their returned data structures.
Byte 8	Parameter LSB		0x2		
Byte 9	Parameter MSB		coreID 0-15		

Table 30-38. RdPkgConfig() PECI Proxy Block Read

SMBus	Function		Value	Data Source	Comment
Slave Address (Command Phase)	Write Address	SMBus Command	0x4B	BMC	
SMBus Read Command Code	SMBus Read Code		0x40		
Slave Address (Data Phase)	Read Address		0x4B		
Byte Count	N	Control Data	{0x01, 0x02, 0x04, 0x05, 0x07}	SoC	N = 0x01 for busy state • Byte 1 = 0x01 N = 0x02 for transaction errors • Byte 1 = 0x02 • Byte 2 = Error Code defined in Table 30-6, "PECI Proxy Read." N = {0x4,0x5,0x7} indicates a successful PECI transaction • Byte 1 = 0x00 • Byte 2 = 0x00 • Byte [7:3] = PECI response data N = {0x04, 0x05, 0x07} value is determined by the number of PECI Response Data bytes returned in Byte [7:4] on the SMBus. N Value: • 0x04 = 1 data byte • 0x05 = 2 data bytes • 0x07 = 4 data bytes
Byte 1	Status Byte		CMD_STAT		See Byte [1] of defined in Table 30-6, "PECI Proxy Read."
Byte 2	Error Byte		ERR_CODE		See Byte [2] of defined in Table 30-6, "PECI Proxy Read."
Byte 3	PECI Transaction Status	PECI Response Data	PECI Completion Code		Completion Code decode: • 0x40 = Command successful • 0x80 = Response time-out • 0x90 = Illegal command
Byte 4	Data 1 (LSB)		Data = 1, 2, or 4 bytes		See Section 30.7.11, "MCA Access via RdEndPointConfig()" and Section 30.9, "CPU Thermal and Power Optimization Capabilities" for the supported capabilities and their returned data structures.
Byte 5	Data 2				
Byte 6	Data 3				
Byte 7	Data 4 (MSB)				

30.10.4.3 Flow


Start
NO
ERR Pins Asserted?
Possible to read an MSR to determine CORE that generated the MCA and set coreid to that core
CoreID = 0x0
RdPkgConfig(0x51,0x2,CoreID)
Check the version
RdPkgConfig(0x51,0x2,CoreID)
Get Length
While(cnt < length)
Coreid++
no
Increment cnt
RdPkgConfig(0x51,0x2,CoreID)
Get Next DWORD
coreID << MAXCORES
yes
no
Reboot SOC

30.10.4.4 Core Crash Details

Table 30-39. Core Crash Details

Field	Category	Size (bytes)
Module0 Regs		
cpu.module0.crashlog_version	Version - 0x10010	4
cpu.module0.payload_size	Bits 31:16 = Core Size; Bits 15:0 = Module Size	4
cpu.scp_cr_who_am_i_info	Only includes bits 14:0	4
cpu.module0.patch_revision	Misc Info	4
cpu.module0.l2_cr_mci_status	Module MCA Regs	8
cpu.module0.bus_cr_mci_status	Module MCA Regs	8
cpu.module0.bus_cr_mci_addr	Module MCA Regs	8
Module0 XQ		
cpu.module0.XQ_0	Header	8
cpu.module0.XQ_1	Header	8
cpu.module0.XQ_2	Header	8
cpu.module0.XQ_3	Header	8
cpu.module0.XQ_4	Header	8
cpu.module0.XQ_5	Header	8
cpu.module0.XQ_6	Header	8
cpu.module0.XQ_7	Header	8
cpu.module0.XQ_8	Header	8
cpu.module0.XQ_9	Header	8
cpu.module0.XQ_10	Header	8
cpu.module0.XQ_11	Header	8
cpu.module0.XQ_12	Header	8
cpu.module0.XQ_13	Header	8
cpu.module0.XQ_14	Header	8
cpu.module0.XQ_15	Header	8
Module 0 Intel Debug Information		
cpu.module0.intel_debug0	Module Debug Info	8
cpu.module0.intel_debug1	Module Debug Info	8
Core0 Header		
cpu.module0.core0.timestamp	Header	8
cpu.module0.core0.crashlog_reason	Header	4
Core0 Arch State		
cpu.module0.core0.thread0.x86_cr_cr0	Arch State	4
cpu.module0.core0.thread0.scp_cr_x86_cr2	Arch State	8
cpu.module0.core0.thread0.x86_cr_cr3	Arch State	8
cpu.module0.core0.thread0.x86_cr_cr4	Arch State	4

Table 30-39. Core Crash Details

cpu.module0.core0.thread0.ia32_cr_efer	Arch State	4
cpu.module0.core0.lip	Arch State	8
cpu.module0.core0.eflags	Arch State	4
cpu.module0.core0.cs_selector	Arch State	2
cpu.module0.core0.ss_selector	Arch State	2
cpu.module0.core0.ds_selector	Arch State	2
cpu.module0.core0.es_selector	Arch State	2
cpu.module0.core0.fs_selector	Arch State	2
cpu.module0.core0.gs_selector	Arch State	2
cpu.module0.core0.rax	GP Regs	8
cpu.module0.core0.rcx	GP Regs	8
cpu.module0.core0.rdx	GP Regs	8
cpu.module0.core0.rbx	GP Regs	8
cpu.module0.core0.rsp	GP Regs	8
cpu.module0.core0.rbp	GP Regs	8
cpu.module0.core0.rsi	GP Regs	8
cpu.module0.core0.rdi	GP Regs	8
cpu.module0.core0.r8	GP Regs	8
cpu.module0.core0.r9	GP Regs	8
cpu.module0.core0.r10	GP Regs	8
cpu.module0.core0.r11	GP Regs	8
cpu.module0.core0.r12	GP Regs	8
cpu.module0.core0.r13	GP Regs	8
cpu.module0.core0.r14	GP Regs	8
cpu.module0.core0.r15	GP Regs	8
Core0 MC Regs		
cpu.module0.core0.ic_cr_mci_status	Core MCA Regs	8
cpu.module0.core0.ic_cr_mci_addr	Core MCA Regs	8
cpu.module0.core0.mec_cr_mci_status	Core MCA Regs	8
cpu.module0.core0.mec_cr_mci_addr	Core MCA Regs	8
Core0 Intel Debug Information		
cpu.module0.core0.intel_debug0	Debug Info	8
cpu.module0.core0.intel_debug1	Debug Info	8

30.11 DTS Temperature Data

30.11.1 PECI Device Temp Data

When accessed using the PECI GetTemp() command, the temperature is formatted in a 16-bit, 2s complement value representing a number of 1/64 °C.

See Figure 30-43, "PECI Device Temp [15:0] Format - Temperature Sensor Data." This format allows temperatures in a range of +/-512 °C to be reported to approximately a 0.016 °C resolution.

Figure 30-43.PECI Device Temp [15:0] Format - Temperature Sensor Data



30.11.2 Interpretation

The resolution of the processor Digital Thermal Sensor (DTS) is approximately 1 °C, which can be confirmed by a performing a Read Model-Specific Register (RDMSR) Intel® architecture instruction to the IA32_THERM_STATUS MSR (19Ch) where it is architecturally defined.

Note: The MSR read will return only bits [13:6] of the PECI temperature sensor data defined in Figure 30-43, "PECI Device Temp [15:0] Format - Temperature Sensor Data." PECI temperatures are sent through a configurable low-pass filter prior to delivery in the GetTemp() response data. The output of this filter produces temperatures at the full 1/64 °C resolution even though the DTS itself is not this accurate.

Temperature readings from the processor are always negative in a 2s complement format, and imply an offset from the processor $T_{J\text{-}MAX}$ (PECI = 0). For example, if the processor $T_{J\text{-}MAX}$ is 100 °C, a PECI thermal reading of -10 implies that the processor is running at approximately 10 °C below $T_{J\text{-}MAX}$ which would be 90 °C. PECI temperature readings are not reliable at temperatures above $T_{J\text{-}MAX}$ since the processor is outside its operating range; therefore, the PECI temperature readings are never positive.

The changes in PECI data counts are approximately linear in relation to changes in temperature in degrees Celsius. A change of 1 in the PECI count represents roughly a temperature change of 1 °C. This linearity is approximate and cannot be guaranteed over the entire range of PECI temperatures, especially as the offset from the maximum PECI temperature (zero) increases.

30.11.3 Temperature Filtering

The processor Digital Thermal Sensor (DTS) provides an improved capability to monitor device hot spots, which inherently leads to more varying temperature readings over short time intervals. Coupled with the fact that typical fan speed controllers may only read temperatures at 4 Hz, the thermal readings need to reflect the thermal trends and not instantaneous readings. Therefore, PECI supports a configurable low-pass temperature filtering function that is expressed by the equation:

$$T_N = (1-\alpha) * T_{N-1} + \alpha * T_{SAMPLE}$$

where T_N and T_{N-1} are the current and previous averaged PECI temperature values respectively, T_{SAMPLE} is the current PECI temperature sample value and the variable "α" = $1/2^X$, where *X* is the Thermal Averaging Constant that is programmable as described in Section 30.9.8, "Package Thermal Status Read / Clear (Index = 20)."

30.11.4 Reserved Values

Several values well out of the operational range are reserved to signal temperature sensor errors. These are shown in Table 30-40, "Error Codes."

Table 30-40. Error Codes

Error Codes	Description
0x8000	General sensor error
0x8001	Reserved
0x8002	Sensor is operational, but has detected a temperature below its operational range.
0x8003	Sensor is operational, but has detected a temperature above its operational range.
0x8004 – 0x81FF	Reserved

§ §

31 Intel® QuickAssist Technology (Intel® QAT)

The integrated Intel® QuickAssist Technology (Intel® QAT) provides acceleration functions that can be used by the IA cores. The acceleration services can be accessed by a standard PCIe* driver. To enhance communication between the IA and the Intel® QAT, the Intel® QAT implements rings via the Ring controller to route messages between them.

Figure 31-1. What is Covered in This Chapter



Applications running on the IA core(s) can make use of the acceleration by calling the Intel® QuickAssist Technology Application Programming Interfaces (APIs). The APIs communicate with the Intel® QuickAssist Technology hardware via PCI configuration space access and assisted rings stored in system memory.

Refer to the *Intel® QuickAssist Technology API Programmer's Guide, incorporated herein by reference, and available at:*

- https://01.org/packet-processing/intel%C2%AE-quickassist-technology-drivers-and-patches.

31.1 Signal Descriptions

There are no signal pins or signal names associated with this chapter.

31.2 Features

This product contains Intel® QuickAssist Technology hardware version 1.7.

- Symmetric cryptographic functions
  - Cipher operation
  - Hash/authenticate operation
  - Cipher-hash combined operation
  - Key derivation operation
- Public key functions
  - RSA operation
  - Diffie-Helman operation
  - Digital signature standard operation
  - Key derivation operation
  - Elliptic curve cryptography: ECDSA and ECDH
- Compression/Decompression
  - Deflate

31.3 Usage Model

Intel® QAT is used by applications running on the IA cores to accelerate and offload processing. Intel® QAT appears to software as a PCIe endpoint and is used as a look-aside co-processor.

Figure 31-2. Intel® QAT Usage Block Diagram



The following steps list a high-level overview of the usage.

1. The application requires Intel® QAT service (e.g., decrypting a packet using AES). It requests service by calling an API with appropriate parameters.
2. The Intel® QAT device driver formats a request message and places it onto ring-in-host memory, then notifies the Intel® QAT.
3. The Intel® QAT reads the request message from the Ring controller.
4. The Intel® QAT carries out the request.
5. When the process is done, write response message to the ring-in-host memory.
6. Interrupt the CPU via a Message Signaled Interrupt (MSI), or a user application can poll for completions.

Note: Refer to the *Intel® QuickAssist Technology API Programmer's Guide* for information on the Intel® QuickAssist Technology APIs available at:

- https://01.org/packet-processing/intel%C2%AE-quickassist-technology-drivers-and-patches.

31.3.1 Ring Controller

The Ring controller provides communication between the IA cores and the Intel® QuickAssist Integrated Accelerator.

- Implements 256 rings for communications between the CPU and the Intel® QAT.
- Organized in 16 bundles of 16 rings each.
- Each bundle supports one interrupt to the endpoint (EP).

31.3.2 Single-Root I/O Virtualization (SR-IOV)

A virtualized platform enables system hardware resources to be shared among multiple guest operating systems (OS). Each guest OS on the virtual platform operates under the assumption that it has complete control of all platform hardware resources. An I/O device that supports I/O virtualization provides the ability for it to be shared simultaneously among multiple guest operating systems.

The Intel® QAT EP implements support for single-root I/O virtualization for function 0 and enables a usage model that allows up to 16 guest operating systems simultaneous access to its resources.

SR-IOV is a PCI-SIG* I/O Virtualization (IOV) specification which in conjunction with system virtualization technologies like VT-d and VT-x, allows multiple guest operating systems running simultaneously within a single platform to natively share PCIe devices.

The SR-IOV capability structure is discovered and configured using the well-defined standard PCI enumeration process.

- Implements an SR-IOV extended capability record.
- One Physical Function (PF): Supports INTx, MSI, and MSI-X.
- 16 Virtual Functions (VF): Supports ARI. Implements MSI only. Does not support INTx messages or MSI-X.
- EP does not support the following optional IOV features:
  - Multi-root IOV
  - VF migration
- Ring access:
  - PF can access all 16 ring bundles.
  - Each VF can access one bundle.

Note: ARI must be enabled to use any Virtual Functions (VF).

31.3.2.1 I/O Virtualization Models

An I/O device such as the Intel® QAT can be shared amongst multiple guest operating systems in a virtual platform using several different hardware, software, and a combination of software and hardware techniques.

31.3.2.2 Sharing via Virtual Machine Monitor (VMM)

The I/O devices in this mode are assigned to the VMM/hypervisor. The VMM will expose a synthetic device to the Virtual Machines (VMs) and could provide a paravirtualized driver that will run in VM. All accesses from the VM using the paravirtualized driver are intercepted by the VMM. The VMM will then use the device driver to access the I/O device on behalf of the VM. In this form of I/O sharing, there is little or no hardware support in the root complex or I/O device for virtualization.

31.3.2.3 Direct Assignment of EP with SR-IOV

The VMM can take advantage of the Intel® QAT EP with SR-IOV support in the hardware and directly assign up to 16 VMs to the 16 VFs as shown in Figure 31-3, "Direct I/O Assignment Model with IOV Support." Each VM can independently access the services of the Intel® QAT.

Configuration and initialization of the Intel® QAT will be through the I/O Virtual Machine (IOVM). All error messages and interrupts not related to the ring status will be directed towards the IOVM (i.e., serviced by the IOVM).

Figure 31-3. Direct I/O Assignment Model with IOV Support



31.3.3 Ring Bundle Mapping

Each VF will be statically allocated one bundle (16 rings). A guest OS that is directly assigned to a VF will have access to only the rings associated with the bundle the VF is assigned to as shown in Table 31-1, "Ring Assignment to Intel® QAT Virtual Functions."

All errors and interrupts generated by the rings will use the Ring ID (RID) associated with that bundle.

Table 31-1. Ring Assignment to Intel® QAT Virtual Functions

Ring	Virtual Function Assignment	Function Number	Ring CSR PCI Offset Begin
Bundle 0	VF1	8	00000h
Bundle 1	VF2	9	01000h
Bundle 2	VF3	10	02000h
Bundle 3	VF4	11	03000h
Bundle 4	VF5	12	04000h
Bundle 5	VF6	13	05000h
Bundle 6	VF7	14	06000h
Bundle 7	VF8	15	07000h
Bundle 8	VF9	16	08000h
Bundle 9	VF10	17	09000h
Bundle 10	VF11	18	0A000h
Bundle 11	VF12	19	0B000h
Bundle 12	VF13	20	0C000h
Bundle 13	VF14	21	0D000h
Bundle 14	VF15	22	0E000h
Bundle 15	VF16	23	0F000h

Notes:
1. The PF can view and access all bundles.
2. Interrupts and memory accesses generated by each of the bundles via ring commands will use the associated bundle's RID.

31.3.3.1 VF Interrupts

Each VF will support only MSI (one vector). A VF supports functional interrupts generated by the Ring controller. INTx is not applicable for VF per the PCI Express* SR-IOV specification.

31.3.4 PCIe Endpoint (EP) Function

The Intel® QAT will show up as a PCIe device to the software running on the IA cores. The Intel® QAT is an Endpoint Device/Function that is integrated in the SoC and connected to a dedicated Root Port.

Figure 31-4, "EP Functional Description Block Diagram" shows the functional description block diagram of the PCIe EP interface.

Figure 31-4. EP Functional Description Block Diagram



31.3.4.1 Transmit Interface (TI)

TI is responsible for converting EP agent commands toward system memory and Outbound (OB) completions into the PCIe transactions. The TI connects to the inbound port of the PCIe root complex.

31.3.4.2 Receive Interface (RI)

The Receive Interface (RI) is responsible for converting OB PCIe commands from the IA cores into the EP agents' commands. Downstream read completions for PCIe commands initiated by the TI are also received by the RI.

31.3.4.3 PCIe EP Functions

RI connects to the OB port of the PCIe root complex. Table 31-2, "PCIe Commands Supported by RI" lists the RI supported PCIe transactions. The EP only supports requests that are aligned on Dword address boundaries.

Table 31-2. PCIe Commands Supported by RI

PCIe* Command	Description	Source	EP Attributes	Comments
MRd32/MRd64	Memory Read	IA reading EP MMIO region, PCIe* extended configuration space	4B	
MWr32/MWr64	Memory Write	IA writing to EP MMIO region, PCIe extended configuration space	4-8B	Note 2
CfgRd0	Type 0 Configuration Read	IA reading EP Configuration register	1-4B	
CfgWr0	Type 0 Configuration Write	Non-Posted IA writing to EP Configuration register	1-4B	Note 2
CmplD	Completion with Data	Read completion with data for a read command initiated by TI	4B-256B	

Notes:
1. Although the EP is capable of handling 8B requests, Intel® QAT does not support any target that supports 8B requests. Therefore, software should not attempt any 8B requests.
2. This is a non-posted transaction. RI will generate a completion without data after the configuration write is completed. The completion will be routed via a RI-TI private bus to the TI. The TI will initiate the PCIe completion packet.
3. The RI will generate an Unsupported Request (UR) completion if it receives any PCIe commands from IA that are not listed in this table.

31.3.4.4 EP Function Mapping

The EP RI implements a single PCIe device with SR-IOV, and Table 31-3, "PCIe EP Function Mapping" shows the mapping of the EP functionality. When SR-IOV is enabled, the RI exposes additional virtual functions.

Table 31-3. PCIe EP Function Mapping

EP	Functional Blocks	PCIe* Function Number	BARs	Interrupt Capability	PCIe Extended/PCI Capabilities
Intel® QuickAssist Technology	Intel® QAT	0	PMISCBAR, PETRINGCSRBAR	MSI, MSI-X with 16 vectors, INTA	MSI, MSI-X, PM, PCIe, AER, SR-IOV, ARI
VF[1:16]		8-23 Note 1	SRIOVBAR0, SRIOVBAR1	MSI only	MSI, PCIe, AER, ARI, ACS

Notes:
1. ARI must be enabled to view function numbers > 7.
2. When ARI is disabled, the bus and device number is captured by the RI on every type 0 configuration write. When ARI is enabled, the device number is implicitly assumed to be 0 and only the bus number is captured by RI on every type 0 configuration write.
3. PPETRINGCSRBAR is used for access to registers that configure and access Ring. PMISCBAR is used for accessing EP and the MSI-X table.

31.3.4.5 EP Mapping of BARs to MMIO

Table 31-4, "EP Mapping of BARs to MMIOs" shows the mapping of the EP MMIO regions to the BARs. See each PCIe function BAR definition for more details.

Table 31-4. EP Mapping of BARs to MMIOs

Function #	BAR Name (Size)	Region Size	Functionality	Comments
0	PMISCBAR (256 KB)	248 KB	EP, Intel® QAT	This region is mapped to the EP and Intel® QAT CSRs.
0		4 KB	EP MMIO CSRs	The EP CSRs are located in the EP.
0		4 KB	MSI-X Tables	The MSI-X tables are located in the EP.
0	PETRINGCSRBAR	256 KB	16 Bundles of Ring CSRs	128 KB for all 16 bundles of CSRs and Intel® QAT CSRs. ***Note:*** This space is allocated for 32 bundles. Only the lower 16 bundles are used and the upper 16 are memory holes in this region.
8-23 (VF[1-16])	SRIOVBAR0	MIN (4 KB, System Page Size) (Note_2)	1 ETR Bundle per VF[x] (RAM)	Each bundle requires 512B, but are mapped in a 4 KB window by default or the system page size.
	SRIOVBAR1	MIN (4 KB, System Page Size) (Note_3)	VF Messaging Registers	There is only one register per VF but is mapped in a 4 KB window by default or the system page size.

Notes:
1. Accesses to the MMIO region that are not implemented within the regions defined in this table will return 0s. Accesses to MMIO regions that are not claimed by any of the BARs will return UR.
2. The SRIOVBAR0 size is dependent on the value programmed in the system.
3. The SRIOVBAR1 size is dependent on the value programmed in the system page size.

31.3.4.6 Alternative Routing-ID Interpretation (ARI)

Receive Interface (RI) provides support for the Alternative Routing-ID Interpretation (ARI). When enabled, ARI allows the PCIe device to implement more than 8 functions.

An ARI device interprets the Routing, Requester, and Completer IDs as having an 8-bit function number instead of the traditional 3-bit function number. An ARI device has its associated device number implied to be 0 rather than specified by an ID field.

Note: ARI must be enabled to use all of the VF Intel® QAT supports.

Table 31-5. Bus, Device and Function Interpretation

ARI Disabled	**Bus Number**	**Device Number**	**Function Number**
	[7:0]	[4:0]	[2:0]
ARI Enabled	**Bus Number**	**Function Number**	
	[7:0]	[7:0]	

RI supports ARI for function 0 when SR-IOV is enabled.

31.3.5 Interrupts

RI is responsible for collating interrupts and errors from the endpoint and taking the appropriate actions based on the PCIe configurations status.

Interrupts from EP can be configured in the RI to be routed to the IA cores. The interrupts can be sent upstream as either an MSI, MSI-X, or by using INTx virtual wire interrupt signaling mechanism (which are messages on PCIe).

31.3.5.1 INTx

PCIe supports devices that need to use the PCI compatible legacy interrupt signaling: INT[A, B, C, D]. Instead of dedicated pins for this functionality, PCIe supports inband virtual wires.

The EP supports the generation of INTx virtual wire interrupt signaling based on internal generated interrupts. The INTx notification is accomplished using PCIe messages.

RI is responsible for collating interrupt sources from the EP agents and generating the transaction that is translated to a PCIe interrupt message to the IA. Upon detecting an interrupt from an internal source, the RI first determines whether to generate an MSI, MSI-X, or INTx message.

31.3.5.2 Message Signaled Interrupt (MSI)

Message Signaled Interrupts (MSI) are an optional feature that enables a device function to request service by writing a system-specified data value to a system-specified address (using a PCI Dword memory write transaction). System software initializes the message address and message data during device configuration. Each function in the EP supports the MSI capability. All the interrupts per function share one vector.

31.3.5.3 MSI-X

MSI-X defines a separate optional extension to the basic MSI functionality. Compared to MSI, MSI-X supports a larger number of vectors per function, the ability for the OS to program independent address and data values for each vector. The address and data values for each vector are specified by a table that resides in the memory space. MSI-X is supported only for the physical function.

Once an MSI has been generated using MSI-X, its characteristics are similar to an MSI that was generated using an MSI capability record. However, MSI-X supports per-vector masking that is optional for MSI. MSI-X also supports a Function Mask bit, which when set, masks all of the vectors associated with a function. Per-vector masking is managed through a Mask and Pending bit pair per the MSI vector or MSI-X table entry. An MSI-X vector is masked when its associated MSI-X Table Entry Mask bit or the MSI-X Function Mask bit is set. While a vector is masked, the function is prohibited from sending the associated message, and the function must set the associated Pending bit whenever the function would otherwise send the message. When software unmasks a vector whose associated Pending bit is set, the function must schedule sending the associated message, and clear the Pending bit as soon as the message has been sent.

When MSI-X is enabled, EP generates an interrupt using a PCIe posted memory write transaction. The address and data of that transaction are determined by the system and programmed in the PCI MSI-X table entry.

31.3.6 EP Errors

There are two classes of errors that the EP will encounter:

- Errors that occur due to PCIe transactions
  - PCIe error management defines the scope of these kinds of errors including how they are reported and handled.
- Other errors not directly related to PCIe transactions
  - This class of errors is reported via interrupts and does not fall under the scope of PCIe error management mechanisms.

31.3.6.1 PCIe Error Management

PCIe error management focuses on errors associated with the PCIe interface and the transactions between the transaction layers of the transmitting and the receiving PCIe ports.

31.3.6.2 PCIe Error Reporting Mechanisms

The PCIe specification provides three mechanisms for reporting errors that occur while servicing PCIe transactions.

1. PCI
   a. This mechanism provides backward compatibility with legacy PCI compatible software and is required per the PCIe specification. Legacy compatible PCI software will use this mechanism and control this feature via the PCI configuration Command register. When this mechanism is enabled, EP will also log error status information in the PCI Configuration Status register.
   b. EP will support the legacy PCI compatible error mechanism.
2. PCIe
   a. This is the baseline PCIe mechanism for software that understands PCIe devices. The mechanism can be enabled via the PCIe Device Control register. Error status is logged in the PCIe Device Status register.
   b. Supported error classifications: unsupported request type, fatal error, non-fatal error, and correctable error
3. PCIe Advanced Error Reporting (AER)
   a. The optional advanced error reporting registers can be implemented by PCIe devices. This mechanism is defined using a PCIe extended capability structure.
   b. All EP Functions will support AER.

31.3.6.3 PCIe Error Handling and Signaling

The EP will classify errors in the following three PCIe specification-defined buckets:

1. Correctable errors: These errors are handled by the Hardware (HW).
2. Uncorrectable errors (non-fatal): These errors are handled by device-specific software.
3. Uncorrectable errors (fatal): These errors are handled by system software.

EP will use three different mechanisms to signal errors that occur when processing PCIe commands.

1. Completion status
2. Error forwarding or data poisoning
3. Error messages

31.3.6.4 PCIe Error Sources

Table 31-6, "PCIe Error Sources" defines the standard PCIe defined error sources. The following sections describe each of the PCIe error types, and describe how the EP handles the PCIe errors.

Table 31-6. PCIe Error Sources

	Type of Error	Reported Using	Comment
TL	ECRC Check	Uncorrectable Non-Fatal Message	
	Malformed TLP	Uncorrectable Fatal Message	RI will perform checks on the PCIe* transactions received from IA.
	Completion Timeout	Uncorrectable Non-Fatal Message	RI will generate these split transaction errors. Completer abort is supported in RI.
	Unsupported Requests	Completion Status	
	Completer Abort (optional)		
	Unexpected Completion	Uncorrectable Non-Fatal Message	
	Data Corruption/Poisoning	PCIe Header	TI will set the EP bit in the header based on the internal bus data error. Writes that terminate in RI get dropped and the status logged. Writes that target an EP function will be sent with a data error and logged in RI.

31.3.6.4.1 Role-Based Error Reporting

In earlier versions of the PCI Express Specification, errors were reported by the agent that detected the error. The *PCI Express Base Specification Revision 3.0* implements a role-based error reporting where the response to the errors is based on the component's role in the transaction. In general, errors detected in non-posted transactions are handled by the initial requester and the completer may optionally send an advisory message to the root complex as an ERR_COR message. Errors in posted transactions are still logged and reported by the target device.

Note: If the severity for the error is programmed to fatal in the PCI Express Uncorrectable Error Severity register, then it is not an advisory non-fatal error and is signaled with an ERR_FATAL message. A fatal severity overrides all other Advisory Error Control bits.

The following errors are considered advisory non-fatal error cases and have different handling depending on the transaction type.

- ECRC check failed
- Unsupported Request (UR)
- Completer Abort (CA)
- Unexpected completion
- Poisoned TLP received
- Completion timeout

31.3.6.4.2 Malformed Packets

The following checks are made to detect malformed TLPs.

- Data payload exceeds the length specified by the value in the Max_Payload_Size field of the Device Control register.

When a malformed packet is detected, the packet is dropped and the error is logged. No flow control information is updated for malformed packets.

31.3.6.4.3 ECRC Check Failed

EP does not calculate for ECRC but will report the ecrc_error signal that it receives. EP reports by sending an ERR_NONFATAL message to the root complex.

31.3.6.4.4 Unsupported Request

Unsupported requests are detected by the address decode and translation logic. A TLP is treated as unsupported in the following cases:

- The TLP fails to match any of the active memory or I/O windows.
- A configuration TLP that targets an invalid function number.
- A receipt of a Vendor_Defined Type 0 message.
- A message request with an undefined or unsupported message code.
- A poisoned I/O or configuration request.
- A receipt of a memory or I/O transaction while in a non-D0 power state.
- A receipt of a Memory Read Lock (MRdLk).

No checks are made for the address plus the length crossing a window boundary.

For posted transactions, this is **not** an advisory error, and an ERR_NONFATAL is sent to the root complex.

For non-posted transactions, this is considered an advisory error. An ERR_COR is sent to the root complex and a completion with UR status is returned to the requester.

Note: If the severity setting in the PCI Express Uncorrectable Error Severity register is fatal, this is not an advisory error, and an ERR_FATAL will be sent to the root complex.

31.3.6.4.5 Completer Abort (CA)

Requests that target abort or master abort on the internal bus are treated as a completer abort.

These requests must have passed the malformed TLP checks as well as the unsupported request checks before they are issued on the internal bus.

For posted transactions, an ERR_NONFATAL is sent to the root complex.

For non-posted transactions, an ERR_COR is sent to the root complex and a completion with CA status is returned to the requester.

Note: If the severity setting in the PCI Express Uncorrectable Error Severity register is fatal this is not an advisory error and an ERR_FATAL will be sent to the root complex.

31.3.6.4.6 Unexpected Completions

Unexpected completions occur when a completion transaction ID does not match a outstanding request. If the Requester ID of the completion matches a valid function, the error will get logged in that function. Otherwise, the error will get logged against all functions.

This is an advisory non-fatal error and an ERR_COR will be sent to the root complex.

Note: If the severity setting in the PCI Express Uncorrectable Error Severity register is fatal, this is not an advisory error and an ERR_FATAL will be sent to the root complex.

31.3.6.4.7 Poisoned TLP Received

Poisoned TLPs can be received for both inbound posted (write/message) and inbound completions. The two TLP types can be handled differently.

Poisoned completions are passed through to the target agent with the error bit set. The error is logged in the corresponding function. This is an advisory error and an ERR_COR will be issued.

Poisoned memory writes that are MMIO-mapped are passed through to the intended target. Depending on the register target, the MMIO-mapped register may get updated with the poisoned data, whereas in some cases the register will not be updated as the byte-enable signals will be disabled. The error is logged in the corresponding function. This is a non-fatal error and an ERR_NONFATAL will be issued.

Writes to configuration registers will not complete to the target. Since configuration writes are non-posted writes, a completion with UR is returned to the host.

Note: If the severity setting in the PCI Express Uncorrectable Error Severity register is fatal, this is not a non-fatal error, and an ERR_FATAL will be sent to the root complex. Auto-recovery is discouraged as the ERR_FATAL message will likely bring down the hierarchy.

31.3.6.4.8 Completion Timeout

When an out-bound, non-posted request results in a completion timeout, the advanced error registers are updated in the corresponding function. This will be treated as an advisory error, and an ERR_COR will be sent to the root complex.

Note: If the severity setting in the PCI Express Uncorrectable Error Severity register is fatal, this is not an advisory error, and an ERR_FATAL will be sent to the root complex. Auto-recovery is discouraged as the ERR_FATAL message will likely bring down the hierarchy.

31.3.6.4.9 Non-Function Specific Errors

The PCI Express Specification lists the following errors as non-function specific:

- Transaction layer errors
  - — ECRC fail
  - — UR, when caused by no function claiming a TLP
  - — Receiver overflow
  - — Flow control protocol error
  - — Malformed TLP
  - — Unexpected completion, when caused by a no function claiming a completion

On the detection of one of these errors, a multi-function device should generate at most one error reporting message of a given severity, where the message must report the Requester ID of a function of the device that is enabled to report that specific type of error. If no function is enabled to send a reporting message, the device does not send a reporting message. If all reporting-enabled functions have the same severity level set for the error, only one error message is sent. If all reporting-enabled functions do not have the same severity level set for the error, one error message for each severity level is sent. Software is responsible for scanning all functions in a multi-function device when it detects one of those errors.

31.3.7 Device-Specific Error Management

EP will report device-specific errors using interrupts—INTx or MSI based on the PCIe configuration settings.

Table 31-7. Device-Specific Errors

Function	Description
Function 0	EP Implements error source and mask registers. When detecting an assertion on an unmasked error, RI will generate either an INTA or MSI.

31.3.7.1 Memory Error Poisoning

The TI also tracks data errors for all transactions that flow through the TI, including accesses to PCIe and CSRs.

31.3.7.1.1 Memory Write Poisoning

For a PCIe memory write (including memory writes triggered by the Ring Controller), the TI pulls data from the EP master. If the internal bus indicates an error, then the TI logs the error, but it does not abort the write transaction. Instead, the TI passes along the data error notification along with the data. On PCIe, the TI will set the EP bit in the header of the packet.

31.3.8 Error Handling with SR-IOV

EP ring-related errors that are associated with a given VF are handled by the given VF itself. For example, the VF would report and log the errors. Each VF supports the legacy PCI (PCI Command and Status registers) and PCIe reporting mechanism (ERR_COR, ERR_NONFATAL, ERR_FATAL messages). The VF also supports PCIe extended capability - AER. Errors that are not directly related to the ring associated with a given VF are handled by the PF. For example, errors such as EP parity errors, etc.

31.4 PCI Configuration Space Map

Figure 31-5, "Register Map" shows the associated PCI configuration space from a system software viewpoint. Refer to the *Intel® QuickAssist Technology API Programmer's Guide* for information on the Intel® QuickAssist Technology APIs to program the Intel® QAT available at:

- https://01.org/packet-processing/intel%C2%AE-quickassist-technology-drivers-and-patches.

The APIs communicate with the Intel® QuickAssist Technology hardware via PCI configuration space access and assisted rings stored in system memory.

Figure 31-5. Register Map



§ §

32 SoC Voltage Rails

This chapter lists and describes all of the power supplies that directly connect to the SoC, as well as signals that directly connect to the SoC and are related to the power supplies.

This chapter does NOT discuss the complete set of platform (the printed wiring board containing the SoC as well as all other associated components) power supplies, those that do not connect to the SoC. A complete platform requires additional voltages, beyond what is directly connected to the SoC.

32.1 SoC Voltage (And Related Signals) Descriptions

The signal descriptions are shown in Table 32-1, "Signal Descriptions." The "Direction" column of Table 32-1, "Signal Descriptions" is interpreted as follows:

- I = Input signal.
- O = Output signal.

The "Voltage Regulator Group" column of Table 32-1, "Signal Descriptions" is used as an aid in categorizing the signal type; implying a particular voltage supply level, class of voltage supply, if the signal is a reference voltage, if the signal is used for Voltage Regulator (VR) sensing (SENSE), Observation (OBS), or a VR return (VSS).

Two signals that are of the same "Voltage Regulator Group" should not necessarily be directly interconnected. While many signals are supplied by the same VR, they may have differing specific filtering and/or isolation requirements. For example, a signal may require a ferrite bead, an inductor, or some other R/C filtering circuit. The Platform Design Guide should be referenced when determining how to interconnect signals for a successful platform design.

For pin numbers and other information for these signals and voltage sources, see Table 39-5, "Package Rotation (ROT) Pins" and Table 39-6, "Directory of Signal and Voltage Pins - Sorted by Pin Number."

Table 32-1. Signal Descriptions (Sheet 1 of 2)

Signal Name	Direction	Voltage Regulator Group	Description
OBS_VCCCPUVIDSI0GT_MOD1	O	OBS	Used to observe the die voltage being delivered to Atom CPU core #0.
OBS_VCCCPUVIDSI0GT_MOD4	O	OBS	Used to observe the die voltage being delivered to Atom CPU core #1.
OBS_VCCBIUVIDSI0GT_MOD1	O	OBS	Used to observe the die voltage being delivered to the BIU.
OBS_VCCRAMCPUSI1GT_ MOD0	O	OBS	Used to observe the die voltage being delivered to the Atom CPU core L2 caches.
SENSE_VCCCPUVIDSI0	O	SENSE	Voltage sense signal that provides feedback to the voltage regulator that supplies the voltage to the Atom CPU cores via the VCCCPU_SVID_S0 set of pins.
SENSE_VSSCPUVIDSI0	O	SENSE	Voltage sense return signal for the voltage sense signal SENSE_VCCCPUVIDSI0 that provides feedback to the voltage regulator that supplies the voltage to the Atom CPU cores via the VCCCPU_SVID_S0 set of pins.
SENSE_VSSRAMCPU_S0	O	SENSE	Voltage sense return signal for the voltage sense signal SENSE_VCCRAMCPU_S0 that provides feedback to the voltage regulator that supplies the voltage to the Atom CPU core L2 caches via the VCCRAM_S0 set of pins.
SENSE_VCCRAMCPU_S0	O	SENSE	Voltage sense signal that provides feedback to the voltage regulator that supplies the voltage to the Atom CPU core L2 caches via the VCCRAM_S0 set of pins.
VCCFHVSIO_1P05	I	V1P05	Power supply for an on-die voltage regulator.
VCCACKDDR_1P05	I	V1P05	Power supply pins for the DDR digital clock.
VCCADDR_1P05	I	V1P05	Power supply pins for the DDR I/O.
VCCAON_HSIO_1P05	I	V1P05	Power supply pins that feeds the logic which controls the LDO/PG within the HSIO PCIe3, SATA 3.1, and USB3 PHYs.
VCCCL_HSIO_1P05	I	V1P05	Power supply pins that power the PLLs within the HSIO PCIe3, SATA 3.1, and USB3 PHYs.
VCCDIGICKSI0_1P05	I	V1P05	Power supply pins for the SoC internal integrated digital clock circuit, requires on-board filtering.
VCCDIGXXXSI0_1P05	I	V1P05	Power supply pins for multiple digital IP block.
VCCFHVSI0_GROUP0_1P05	I	V1P05	Power supply for an on-die voltage regulator.
VCCFHVSI0_GROUP1_1P05	I	V1P05	Power supply for an on-die voltage regulator.
VCCFHVSI0_GROUP2_1P05	I	V1P05	Power supply for an on-die voltage regulator.
VCCKRA_LV	I	V1P05	Power supply pins feeding 10GE IP block.
VCCKRLCPLL	I	V1P05	Power supply pins for the 10GE PLL, requires on-board filtering.
VCCPLLEBB_HSIO_1P05	I	V1P05	Power supply pin that powers T-Line drivers within the HSIO PHYs.
VCCUSB_1P05	I	V1P05	Power supply pins that power the USB2 PHY.
VCCFHVIFPSI0_1P8	I	V1P80	Power supply for an on-die voltage regulator.
VCCPADXXXSI0_1P8	I	V1P80	Power supply pins that power the 1.8V GPIOs.

Table 32-1. Signal Descriptions (Sheet 2 of 2)

Signal Name	Direction	Voltage Regulator Group	Description
VCCUSBSUS_1P8	I	V1P80	Power supply pins that power the 1.8V suspend supply for the USB2 PHY.
VCCFHVIFPSI0_3P3	I	V3P30	Power supply for an on-die voltage regulator.
VCCPADXXXSI0_3P3	I	V3P30	Power supply pins that power the 3.3V GPIOs, and RTC.
VCCUSBSUS_3P3	I	V3P30	Power supply pins that power the 3.3V suspend supply for the USB2 PHY.
VCC_LPC_ESPI_3P3_1P8	I	V3P30	Power supply for the LPC 3.3V.
VCCCPU_SVID_S0	I	VCC	Power supply pins that power the Atom cores, actual voltage is dependent on SoC request to the VR.
VCCRAM_S0	I	VCCRAM	Power supply pins that power the Atom L2 caches, actual voltage is dependent on SoC request to the VR.
VCCKR_HV	I	V1P80	Voltage reference used by the LAN IP block, requires on-board filtering.
VCCREF_SFRXXXSI0_N	I	VCCREF	Voltage reference for the North side Atom core LDOs, requires on-board filtering.
VCCREF_SFRXXXSI0_S	I	VCCREF	Voltage reference for the South side Atom core LDOs, requires on-board filtering.
VCCUSB_1P24	I	VCCREF	Voltage reference for the USB2 SFR LDO.
VCCCKDDR_VDDQ	I	VDDQ	Power supply pins that drive the DDR clock signals to the DDR memory devices, actual voltage is dependent on SoC request to the VR.
VCCDDR_VDDQ	I	VDDQ	Power supply pins that drive the DDR data signals to the DDR memory devices, actual voltage is dependent on SoC request to the VR.
VCCDDRSFR_VDDQ	I	VDDQ	Power supply for the SFR LDO feeding the DDR PLL, requires on-board filtering, actual voltage is dependent on SoC request to the VR.
VNN_SVID	I	VNN	Power supply pins that power portions of several IPs and level shifters within the UnCore, actual voltage is dependent on SoC request to the VR
VCCRTC_3P3_G3	I	VRTC	Battery backed power supply for the RTC IP block.
VSS	O	VSS	SoC common power supply return signal. Check the Platform Design Guide to see if any of the VSS pins have unique routing or isolation requirements.

§ §

33 Resets and Voltage Sequencing

This chapter discusses the requirements for resetting the SoC and the power-up/power-down voltage sequencing requirements for the SoC. This chapter discusses only the requirements of the SoC, not the entire platform (Printed Wiring Board (PWB) containing the SoC and all associated components).

Table 33-1. References

Reference	Revision	Date	Document Title
ACPI Specification	5.0 A	November 2013	*Advanced Configuration and Power Interface Specification Version 5.0, Errata A*

33.1 Signal Descriptions

The signal descriptions are shown in Table 33-2, "Signal Names and Descriptions."

For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing."

The Direction/Type column of Table 33-2, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.

Table 33-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
PMU_PLTRST_N	O	Yes	See Chapter 16, "Power Management Controller (PMC)" for details.
PMU_SLP_S3_N	O	Yes	See Chapter 16, "Power Management Controller (PMC)" for details.
PMU_SLP_S45_N	O	Yes	See Chapter 16, "Power Management Controller (PMC)" for details.
PMU_SUSCLK	O	Yes	See Chapter 16, "Power Management Controller (PMC)" for details.
SUS_STAT_N	O	Yes	See Chapter 16, "Power Management Controller (PMC)" for details.
SUSPWRDNACK	O	Yes	See Chapter 16, "Power Management Controller (PMC)" for details.
COREPWROK	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
RSMRST_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
RTEST_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.
SRTCRST_N	I	No	See Chapter 24, "Real Time Clock (RTC)" for details.

Nine separate power supplies are required to power the SoC. This chapter does not detail how the nine power supplies connect to the SoC, see Chapter 32, "SoC Voltage Rails."

For convenience, Table 33-3, "SoC Required Power Supplies" lists the reference names of the SoC required power supplies, and their nominal voltages:

Table 33-3. SoC Required Power Supplies

PS Name	Nominal Voltage (V)	Comment
VRTC	2.0-3.3	Tied to battery or 3.3V
VCC	0.52-1.24	Dynamic Range (SVID address 00h)
VNN	0.65-1.24	Dynamic Range (SVID address 01h)
VDDQ	1.20	DDR4 (SVID address 02h)
VCCRAM	0.75-1.20	Dynamic Range (SVID address 03h)
VCCREF	1.24	Static (SVID address 015h)
V1P05	1.05	Static (SVID address 015h)
V1P80	1.80	Static (SVID address 015h)
V3P30	3.3	Static (SVID address 015h)

Table 33-4, "SoC Power Supply for each Supported Power State" lists the states of each SoC power supply for each supported power state:

Table 33-4. SoC Power Supply for each Supported Power State

PS Name	G3	S5	S4	S0
VRTC	With Battery: On Without Battery: OFF	ON	ON	ON
VCC	OFF	OFF	OFF	ON
VNN	OFF	ON	ON	ON
VDDQ	OFF	OFF	OFF	ON
VCCRAM	OFF	OFF	OFF	ON
VCCREF	OFF	OFF	OFF	ON
V1P05	OFF	ON	ON	ON
V1P80	OFF	ON	ON	ON
V3P30	OFF	ON	ON	ON

33.2 Architectural Overview

The SoC device configuration and power management complies with the *Advanced Configuration and Power Interface Specification Version 5.0, Errata A*. However, not all the states defined by ACPI are supported.

The supported ACPI Global (G) States are listed below:

- G0
- G1
- G2
- G3

The supported ACPI System (S) States are listed below:

- S0
- S4
- S5

ACPI terms are used in this chapter for the SoC Reset and Voltage Sequencing requirements.

Table 33-5, "Supported ACPI Transitions And Definitions" lists the supported ACPI Power State transitions along with the term used throughout this chapter in describing each event:

Table 33-5. Supported ACPI Transitions And Definitions

ACPI Transition	SoC
From G3 To G0.S0	Cold Boot
From G0.S0 To G3	Shutdown
From G0.S0 To G1.S4	Deep Sleep
From G1.S4 To G0.S0	Deep Sleep Wake
From G0.S0 To G2.S5	Soft Off
From G2.S5 To G0.S0	Soft Off Wake
From Gx.Sx To G3	Power Failure

The sequencing/reset requirements for each ACPI Transition listed in Table 33-5 is detailed in the sections below.

33.3 Cold Boot: From G3 To G0.S0

Figure 33-1, "ACPI Cold Boot Sequence" illustrates the ACPI timing sequence in going from G3 to G0.S0. The arrows in the timing diagram show the sequences that must be followed. In some cases a delay is shown, in other cases, no specific timing delay is given. For cases where no specific timing delay is given, only the sequence is of significance.

The arrows showing the transition of one signal/voltage causing the transition of another signal/voltage occur when the signal/voltage causing the transition reaches its specified valid level. For example, in Figure 33-1, "ACPI Cold Boot Sequence," when V3P30 reaches the level specified as the operating range for V3P30, this is when V1P80 can begin to reach its specified valid level. And for this example, V1P80 must begin ramping within 10ms or less after V3P30 has reached its valid operating range.

Figure 33-2, "Non-ACPI Cold Boot Sequence" is similar to Figure 33-1, "ACPI Cold Boot Sequence," but illustrates the Non-ACPI sequence, where the PMU_SLP_S45_N and PMU_SLP_S3_N signals may be ignored.

Figure 33-1. ACPI Cold Boot Sequence



Notes:

1. After RSMRST_N de-asserts the Hard straps are sampled. PMU_SLP_S45 will not de-assert until PMU_SUSCLK starts and the Soft straps are loaded from flash.
2. Before PMU_SLP_S45_N de-asserts the PMC and Intel® Management Engine are running.
3. TMAX = 10s: RSMRST should not be asserted indefinitely while the uncore supplies are powered. Specifically, a maximum delay of 10s from V1P05 to RSMRST deassertion should be enforced.

Figure 33-2. Non-ACPI Cold Boot Sequence



Notes:
1. After RSMRST_N de-asserts the Hard straps are sampled. PMU_SLP_S45 will not de-assert until PMU_SUSCLK starts and the Soft straps are loaded from flash.
2. Before PMU_SLP_S45_N de-asserts the PMC and Intel® Management Engine are running.
3. TMAX = 10s: RSMRST should not be asserted indefinitely while the uncore supplies are powered. Specifically, a maximum delay of 10s from V1P05 to RSMRST deassertion should be enforced.

Figure 33-1, Figure 33-2, Figure 33-3, and Figure 33-4 show the configuration where there is no battery connected to VRTC, and instead optionally connected only to V3P30. However, if the battery backed option is selected, then VRTC would always be at the battery voltage and ramp up to V3P30 after the V3P30 VR comes up. When the battery backed option is selected, then the battery and V3P30 are both connected to the VRTC pin through diodes.

The signals RTEST_N and SRTCRST_N are normally held high to VRTC through an external RC circuit, causing a delay in the signals becoming inactive sometime after VRTC has ramped. On a typical system, a jumper is used to force these signals active for testing purposes.

Note: In certain user cases, the core power rails (VCC/VCCRAM/VCCREF/VDDQ) do not need to be cycled during cold reset, but COREPWROK must be cycled during cold reset. If this certain user cases is using non-ACPI code boot sequence, SLP_Sx still are signals to be monitored to be de-asserted before COREPWROK asserted.

33.4 Shutdown: From G0.S0 To G3

Figure 33-3, "ACPI Shutdown Sequence" illustrates the ACPI timing sequence in going from G0.S0 to G3. The arrows in the timing diagram show the sequences that must be followed. In some cases a delay is shown, in other cases, no specific timing delay is given. For cases where no specific timing delay is given, only the sequence is of significance.

The arrows showing the transition of one signal/voltage causing the transition of another signal/voltage occur when the signal/voltage causing the transition falls out of its specified valid level. For example, in Figure 33-3, "ACPI Shutdown Sequence," when V1P05 falls below its valid operating level, this is when the timer begins for T_D. Where T_D is defined as the required time delay before VNN can begin ramping down.

Figure 33-4, "Non-ACPI Shutdown Sequence" is similar to Figure 33-3, "ACPI Shutdown Sequence," but illustrates the Non-ACPI sequence, where the PMU_SLP_S45_N and PMU_SLP_S3_N signals may be ignored.

Figure 33-3. ACPI Shutdown Sequence



Figure 33-4. Non-ACPI Shutdown Sequence



33.5 Deep Sleep: From G0.S0 To G1.S4

Going from G0.S0 to G1.S4 is depicted by the sequence shown in Figure 33-3, "ACPI Shutdown Sequence," and stopping after the VDDQ power supply is turned off. There is no way to discern the G1.S4 state from the G2.S5 state from merely observing the SoC signals.

33.6 Deep Sleep Wake: From G1.S4 To G0.S0

Going from G1.S4 to G0.S0 to is depicted by the sequence shown in Figure 33-1, "ACPI Cold Boot Sequence," beginning in the G1.S4 state. There is no way to discern the G1.S4 state from the G2.S5 state from merely observing the SoC signals.

33.7 Soft Off: From G0.S0 To G2.S5

Going from G0.S0 to G2.S5 is depicted by the sequence shown in Figure 33-3, "ACPI Shutdown Sequence," and stopping after the VDDQ power supply is turned off. There is no way to discern the G1.S4 state from the G2.S5 state from merely observing the SoC signals.

33.8 Soft Off Wake: From G2.S5 To G0.S0

Going from G2.S4 to G0.S0 to is depicted by the sequence shown in Figure 33-1, "ACPI Cold Boot Sequence," beginning in the G2.S5 state. There is no way to discern the G1.S4 state from the G2.S5 state from merely observing the SoC signals.

33.9 Power Failure: From Gx.Sx To G3

While the SoC is capable of withstanding uncontrolled shutdowns due to a power failure, designs should adhere to the specified controlled power shutdown sequencing in order to avoid potential shortened component life expectancies. Intel does not specify or validate the number of power failure cycles a component may withstand before expected component life is affected.

In order to ensure that a power failure does not damage the SoC, the RSMRST_N signal must be asserted (must go low - from a 1 to a 0) at least 1µs before the main power supply that is used to derive all the SoC voltage rails falls 5% below its nominal value. With this sequence, initial testing has shown that components which have experienced 2000 uncontrolled shutdowns (power failures) have not experienced any failures or suffered shortened life expectancies.

33.10 Special Considerations for Platform Voltages

Voltages that do not directly connect to the SoC, but power other platform devices which connect to the SoC, must be isolated (to prevent leakage into SoC), until the SoC has powered up. The 5VDC supply which is provided to a USB interface is an example of a voltage that is not required by the SoC.

§ §

34 Power Management

The SoC provides dynamic power management that fits a number of usages like Microserver, Cloud Storage and Communication Infrastructure. As the technology changes and the number of cores per node and per module change, a better approach is required to manage optimal power of the node/module with respect to the power budget.

Figure 34-1. What is Covered in This Chapter



34.1 Signal Descriptions

The signal descriptions are shown in Table 34-1, "sVID Controller Signals." For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a customer GPIO signal, see Chapter 39, "Signal Pin Names and Signal MUXing." The Direction/Type column of Table 34-1, "sVID Controller Signals" is interpreted as follows:

- I = Input signal. The SoC has receiver circuitry.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 34-1. sVID Controller Signals

Signal Name	Direction/ Type	Shared	Description
SVID_DATA	I,O-OD	Yes	**sVID Data:** Used by the SoC to send requests and data to the external Voltage Regulator (VR) and then by the VR to respond.
SVID_CLK	O-OD	Yes	**sVID Clock:** sVID requests driven on SVID_DATA by the SoC use this clock. The VR uses this clock to register-capture the requests. When the VR responds with data on SVID_DATA, the VR uses this SoC-driven clock.
SVID_ALERT_N	I	Yes	**sVID Alert:** Used by the VR to signal to the SoC that the prior request has not reached the requested operating point.

34.2 Overview

The power management control is comprised of a number of Intel proprietary mechanisms. The power management signal interface to the rest of the platform is through the Power Management Controller (PMC) block. This chapter refers to this distributed function as the SoC Power Management Unit (PMU).

To take advantage of all power management capabilities an external, board-level Baseboard Management Controller (BMC) or some other embedded controller, is required to manage the platform power planes, power-on, sleep states, and reset signaling. This chapter refers to the BMC or Embedded Controller (EC). The EC interfaces with the SoC internal fabric to perform its management functions.

The SoC power management is responsible for the following tasks:

- Communicating with the EC and the Intel® Management Engine (Intel® ME)
- Reset sequencing
- Managing processor C-states and P-states
- Managing Sleep-state entry sequences
- Managing DDR4 power management
- Controlling Low Pin Count (LPC) interface clock
- Directing processor thermal management and memory
- Interfacing with the BIOS and the operating system software
- Managing Intel® Turbo Boost Technology, SoC RAPL control, and DRAM RAPL control

Table 34-2. References

Description	Document ID / Location
Advanced Configuration and Power Interface Specification Version 5.0, Errata A	http://uefi.org/specifications

34.3 Power Management Features

The power management features are:

- ACPI system power states supported: G0 (S0), G1 (S4), G2 (S5), G3 (Mechanical Off)
  - S1, S2, S3 are not supported.
- ACPI processor (CPU) C-states: C0, C1, C2, and C3.
- ACPI device states: D0, D3
- ADR (Asynchronous DRAM Refresh)
- Enhanced Intel SpeedStep® Technology
- Clock and Power gating
- Thermal throttling
- Dynamic I/O, memory, and SoC power reductions
- Running Average Power Limiter (RAPL)
- DDR4 SDRAM memory controller and PHY:
  - CKE active power-down (APD) and pre-charge power-down (PPD).
  - Self-Refresh
  - DDR PHY optimization to reduce SoC power.
  - DLL master/slave shut down based on CPU state.

34.3.1 Asynchronous DRAM Refresh (ADR)

ADR provides an early warning to the SoC of an impending reset or power failure so that it can save critical RAID information to the system memory DIMMs that remain powered by a dedicated battery while the reset is in progress.

See Section 16.15, “Asynchronous DRAM Refresh (ADR)” in this document.

34.4 Power Wells

The SoC circuitry is powered by three power wells:

- Core power well
- SUS power well
- RTC power well

34.4.1 Core Power Well

This power group includes all voltage rails and associated power wells that are on only when the system is in the S0 state (system is fully powered-on). The core power well contains the MAIN and cache power rails. These voltage rails are turned off when the system transitions to one of the other low-power system sleep states. See Figure 34-2, "Global System Power States and Transitions" for the ACPI states flow diagram.

34.4.2 SUS Power Well

The register-description chapters of the EDS use the terminology "Primary" and "DSW" for this power well instead of SUS Power Well.

This power group includes voltage rails and associated power wells that are on when the system is in the S0 and S5 states. These voltage rails are turned off when the system transitions from S5 to the G3 (mechanically off) state.

Most of the power management signal pins have their drivers/receivers in the SUS power well.

34.4.3 RTC Power Well

This power group includes all internal voltage rails and associated power wells that are always on, even when the system is in the G3 (mechanical off) state. This group is supplied its 3.3V from the SUS power supply, when the system is in S0 and S5. When the system is in the G3 state, the optional RTC power well is powered from an external battery source, typically a 3.0V lithium-type coin cell.

If a complete power failure (no AC power and no battery back-up supply) occurs, this voltage rail does not provide any power if there is no functioning battery providing its power. In the G3 state (mechanical off), it is permissible for designs not to have an external coin-cell battery if the design does not need to preserve information when the system power is turned off.

34.5 Supply Voltage Rails

The SoC is a highly integrated component where many traditional subsystems are contained on one die.

A total of nine external unique rails need to be supplied. Table 34-3, "SoC Voltage Rails" shows each voltage rail level and a list of internal units associated with the voltage rail.

See Table 33-3, "SoC Required Power Supplies" for voltage values for VCC, VNN,VCCRAM, and VCCREF.

Table 34-3. SoC Voltage Rails

Voltage Rail	VR Rail	SoC Internal Units	S0	S5	RTC
Coin Cell Battery	VRTC	Real Time Clock (RTC)	On	On	On
sVID VCC VR	VCC	CPU Core	On	-	-
sVID VNN VR	VNN	UnCore	On	On	-
P1V05	P1V05	• GPIOSUS signal pins • GbE control and I/O • Power Management Controller (PMC)	On	On	-
VCCRAM	VCCSRAM	• Core L2 Cache	On	-	-
P1V8	V1P8	• GPIO SUS • USB 2.0 SUS • GbE Biasing	On	On	-
VDDQ	VDDQ	DDR I/O	On	-	-
VCCREF			On	-	
V3P3	V3P3	• GPIO SUS-Well High-Voltage signal pins • USB 2.0 SUS signal pins • Thermal Sensor • USB2 I/O	On	On	-

Note: S3 and S4 are part of the state machine and are included in Table 33-4, "SoC Power Supply for each Supported Power State." These states, however, are passed through on the way to S0 or S5.

RTC - In the G3 (mechanically off) state remains on when the RTC battery is present.

34.6 Serial Voltage Identification (sVID) Controller

The three signals provided by the SoC are in Table 34-1, "sVID Controller Signals."

34.6.1 SVID VR Requirements

It is required that the voltage rails for the cores (VCC), L2 SRAM (VCCRAM), and fabric (VNN) support IMON as defined by the Serial VID (SVID) Protocol Specification, Revision 1.7 which covers VR13.0.

The VDDQ VR, if used, must support IMON for DRAM RAPL and DRAM Energy Reporting to function. It is not, however, required for silicon functionality.

Failure to support IMON for the core voltage rails and VDDQ (if the VR is used) may result in one or more of the following:

- System fails to boot
- Power management features fail to work (e.g. RAPL)
- SoC reliability may be compromised
- SoC may show instability at varied temperatures

Note: Voltage control, VCC, VNN, and VCCSRAM, using the SVID feature is required for the silicon to function. Voltage control for VDDQ is supported but not required.

34.6.1.1 sVID Commands

The sVID commands are shown in Table 34-4, "sVID Commands."

Table 34-4. sVID Commands

Command	Command Code	Send Payload	Receive Payload	Description
Not Supported Reserved	00h	(Extended Command)		
SetVID_Fast	01h	VID	n/a	Sets the new VID target. VR Jumps to the new VID target with controlled (up or down) slew rate programmed by the VR. When the VR receives a VID Moving Up command it exits all low-power states to the normal state to ensure the fastest slew to the new voltage. VR sets VR_settled bit and issues alert when VR has reached new VID target.
SetVID_Slow	02h	VID	n/a	Sets the VID target. VR Jumps to new VID target with controlled slew rate (up or down) programmed by the VR. SetVID-Slow is 4x slower than SetVID-fast. When VR receives a VID Moving Up command it exits all low-power states to the normal state to ensure the fastest slew to the new voltage. VR sets VR_settled and issues alert when VR has reached new VID target.
SetVID_Decay	03h	VID	n/a	Sets the VID target. VR jumps to new VID target, but does not control the slew rate, the output voltage decays at a rate proportional to the load current. SetVID_Decay is only used in VID down direction. VR sets VR_settled bit is set, but alert line is not asserted for SetVID-decay.
SetRegADR	05h	VR Register Address	n/a	Sets the address pointer in the data register table. Typically the Next command SetRegDAT is the payload that gets loaded into this address. However, for multiple writes to the same address, only one SetRegADR is needed.
SetRegDAT	06h	VR Register Data	n/a	Writes the contents to the data register that was previously identified by the address pointer with SetRegADR.
GetReg	07h	VR Register Address	VR Register Data	Slave returns the specified register contents as the payload. The majority of the VR monitoring data is accessed through the GetReg command.
Test_Mode	08h			Vendor Defined
Reserved	08h through 1Fh			

34.7 Core Power Management Overview

The SoC supports the hardware C0, C1, C1e, and C6 C-states. C3 is not supported. For C-states deeper than C6, the SoC will be automatically demoted to C6.

All cores in the C0, C1, or C1e C-state operate at the same voltage and frequency. The target frequency is typically the maximum requested frequency for all threads.

The SoC may or may not provide the requested frequency. Many factors can constrain the resolved frequency including but not limited to the following.

- Temperature
- Power constraints
- SKU constraints

The SoC determines a “resolved” frequency based on the OS requests and these constraints. The SoC autonomously manages the voltage based on the resolved frequency and various additional constraints.

The upper and lower bounds of these targets are weighed and prioritized to come up with a final ratio resolution for each core and the sections.

34.8 System Global Power States

Figure 34-2, "Global System Power States and Transitions" shows the system Global Power States as defined by the *Advanced Configuration and Power Interface Specification Version 5.0, Errata A*.

Table 34-5, "ACPI Power States" provides an overview of the power states defined for platforms based on the SoC. For design details on the power states definition and initiation see Chapter 33, "Resets and Voltage Sequencing."

Figure 34-2. Global System Power States and Transitions



Table 34-5. ACPI Power States

State (Global/Sleep/CPU)	APCI Name	Description
G0/S0/C0	Working (Full On)	CPU operating. Individual devices are shut-off to save power.
G0/S0/C1 G0/S0	Working with CPU Power Management	The different CPU operating levels are defined by Cx states.
G2/S5	Soft Off	System context not maintained. All main power is shut off except for the logic required to wake system. A full boot is required when waking.
G3	Mechanical Off	• System context not maintained. • All main power shut off except for the RTC. • No Wake events occur, because the system does not have any power. This state occurs if user removes the batteries, turns off a mechanical switch, or if the system power supply is at a level that is insufficient to power the waking logic. When system power returns, transition depends on the state before entry to G3.

Table 34-6. ACPI Power State Transitions for the SoC

State (Global/Sleep/CPU)	Transition Trigger	Next State
G0/S0/C0	Executing the MWAIT instruction or LVL Rd	G0/S0/Cx
	Sleep Enable (SLP_EN) bit written to 1 by the software in the Power Management 1 Control (PM1_CNT) register	Specified by the 3-bit code Sleep Type (SLP_TYP) field of the PM1_CNT register: • 000 G0/S0 - Working (Full On) • 001 G1/S1 - Not supported by the SoC • 010 Reserved • 011 Reserved • 100 Reserved • 101 G1/S3 - Suspend-To-RAM - Not supported by the SoC • 10 G1/S4 - Suspend-To-Disk S4 • 111 G2/S5 - Soft Off
	Power Button Override	G2/S5
	Mechanical Off/Power Failure	G3
G0/S0/C1 G0/S0/C3	C-State break events including: • CPU Snoop • MSI • Legacy Interrupt • Always-On (AONT) Timer expires	G0/S0/C0
	Power Button Override	G2/S5
	SUS Well Power Failure	G3
G2/S5	Any Enabled Wake Event	G0/S0/C0
	SUS Well Power Failure	G3
G3	Power Returns	Option to go to: • S0/C0 (Reboot) • G2/S5 (Stays off until the power button is pressed or other enabled wake event)
S0/G3/S0	Surprise Power Loss	ADR (Automatic DIMM Refresh) asserts if the appropriate battery back-up design is in place.

34.8.1 Idle Power Optimizations

The SoC does not use the G1/S1 sleep state. Instead, as other recent server processors do, it enters the G1/S1 sleep state is not used. The processor now enters low power states (package C-states) while staying in the S0 state. This method provides low latency wake-ups. Alternatively, the S4 (sleep) or S5 (soft off) may be used to put the system into its lowest idle power states. Note the exit latency between S4 and S5 are OS and platform configurations dependent. In certain cases, S4 latency is not necessarily faster than S5.

34.9 Processor Power States - C-States

There are three types of C-states which are frequently mixed up:

- ACPI C-states
- Core C-states
- Package C-states

ACPI C-states are C0, C1, C2, and C3. These states are mapped to the actual hardware C-states (C0, C1, C1e, C6) through BIOS tables.

When all cores go into certain Core C-states, the SoC has the option to enter a deeper package C-state and take additional power saving actions in the package and/or on the platform.

Note: Linux and the mainline kernel have moved away from ACPI C-states with the intel_idle driver. This driver will be updated to support this SoC at launch.

Figure 34-3 shows the Processor Power States described in the *Advanced Configuration and Power Interface Specification Version 5.0, Errata A*.

The processor Performance States (P-States) are described later in Section 34.10.1, "Processor Performance States - P-States."

Figure 34-3. Processor Power States



Concerning the SoC CMP Module and its interface to the System Agent, the SoC has three types of C-States:

- Core C-States. See Table 34-7, "Core C-States."
- Package C-States. See Table 34-8, "Package C-States."

Table 34-7. Core C-States

HW Core C-State	Typical Mapped ACPI C-State	Description
CC0	C0 | ACPI C0	Active State
CC1	C1 | ACPI C1	Some core clocks gated. L1 Data Cache Snoops are serviced.
CC1e	C1e | N/A	Some core clocks gated. L1 Data Cache Snoops are serviced. Provides a hint to reduce voltage and frequency.
CC6	C6| ACPI C2	Core power gated and clock gated L1 Data cache is flushed

Table 34-8. Package C-States

Core C-State	Package C-State	When Entered
C0	PC0	• Active States • When at least one core is in CC0
C1e	PC1e	• Reduce voltage and frequency for C1e • When no cores are in CC0 or CC1 and at least 1 core is in C1e
CC6	PC2	• All cores in CC6 • Some package actions allowed

34.10 Performance States

This section describes the concept of processor and device performance states. Processor and device performance states (Px states) are power consumption and capability states within the active/executing states, C0 for processors and D0 for devices. Performance states allow the Operating System Power Management (OSPM) to make trade-offs between performance and energy conservation. Processor and device performance states have the greatest impact when the states invoke different device and processor efficiency levels as opposed to a linear scaling of performance and energy consumption. Since performance state transitions occur in the active/executing device states, ensure that performance state transitions do not adversely impact the system.

34.10.1 Processor Performance States - P-States

The SoC supports P-States for every dual-core pair within a module. Based on power performance analysis, the SoC only supports Package Level P-States. The Power Management Unit will select the highest P-state from all requests across all modules and apply that state to all cores.

Note: Hardware Power Management and Hardware P-states are not supported.

34.10.1.1 Frequency/Voltage Scaling

P-state frequency and voltage are resolved at the package level and not by the individual cores or modules.

Table 34-9. ACPI P-State Mappings

P-State	ACPI Meaning	Frequency Mapping
P0	Performance is preferred over power efficiency	Greater-than or equal-to the Maximum Non-Turbo Limit Ratio. This is set based on thermal/electrical limits, platform constraints, and other parameters.
P1	Maximum performance/efficiency is desired	Maximum Non-Turbo Limit Ratio (base frequency)
P2 through PN	Intermediate performance/efficiency is desired	Less-than the Maximum Non-Turbo Limit Ratio, Greater-than the Maximum Efficiency Ratio
PN	Frequency at the minimum voltage	Maximum Efficiency Ratio correlates to minimum operational voltage (LFM_RATIO)

The OS requests a P-State based on application performance needs. A desired P-State is requested via IA32_PERF_CTL (CLOCK_CR_GEYSIII_CONTROL). The SoC supports the Enhanced Intel SpeedStep® Technology.

34.10.2 Software P-State Requests

ACPI enumerates the base frequency at P1 and the maximum turbo frequency at P0. There are multiple ratios/frequencies between these two points. The SoC supports requests to intermediate ratios and will attempt to provide those ratios (under all normal constraints).

34.11 Power Management Technologies

34.11.1 Intel® Turb Boost Technology

Intel® Turbo Boost Technology enables higher performance through the availability of increased core frequency under certain configurations and workloads. Turbo allows processor cores to run faster than the specified operating frequency if the processor is operating below rated power, temperature, and current specification limits of the system. Turbo is engaged with any number of cores or logical processors enabled and active, enabling increased performance of both multi- and single-threaded workloads.

The BIOS may disable turbo features on turbo-enabled SKUs. If Reset = 1, then the SKU does not support turbo and it is disabled. If RESET = 0, then the SKU does support turbo and it is enabled by default. BIOS can set the bit to disable it.

The Operating System (OS) and applications must use CPUID.06H:EAX[1] to detect whether the BIOS has enabled turbo features. If IA32_MISC_ENABLES[38] is set, CPUID.06H:EAX[1] returns 0. Turbo features have been enabled by BIOS.

Because IA32_MISC_ENABLES[38] is defined per-package, CPUID has to read from the UnCore to get MISC_ENABLES[38]. The OS or BIOS manages read-modify-write conflicts cross-core. Setting IA32_MISC_ENABLES[38] on any core causes the SoC to disable turbo operation for ALL cores.

Certain software workloads may not be able to tolerate the non-deterministic aspects of turbo operation. The software temporarily disables turbo operation by setting CLOCK_CR_GEYSIII_CONTROL[32] bit of the IA32_PERF_CTL Model-Specific Register (MSR) [MSR 0199h]. As previously mentioned, disabling turbo on any core causes turbo to be disabled for ALL cores.

Two MSRs (MSRs 0x1AE and 0x1AD) can be used to limit the maximum amount of turbo that is granted based on the number of active cores. At reset these registers are populated based on the SKU limits. Software (either BIS or Ring-O) can reprogram these limits at boot or runtime. Configuring frequencies larger than the SKU limits will be silently clipped.

34.11.2 Voltage Regulator Constraints

For some platforms, the voltage regulator for the shared VCC voltage rail has some maximum current limits. A typical voltage regulator for a platform using the SoC has a Thermal Design Current (Icctdc) specification and a Maximum Current (Iccmax) limit.

Icctdc represents the current which is sustained indefinitely by the voltage regulator (i.e., able to sustain a TDP workload on all processors running at base frequency), whereas the Iccmax is the peak current which the voltage regulator does source without tripping any protective circuitry. Any current greater than Icctdc is only sustained for a short duration. Iccmax is sustained typically for approximately 10 ms.

Such voltage-regulator specifications must be taken into account when configuring the aggressiveness of turbo operation for the device. Turbo operating points are limited based on the number of active cores to keep the current drawn within the Iccmax limit.

See Section 35.2, "Feature Summary" for Thermal Management Features.

34.11.3 Thermal Design Power Constraints

The Thermal Design Power (TDP) represents the power consumed by the device when running a realistic worst-case workload at $T_{J\text{-}MAX}$ temperature. The realistic-worst-case workload is determined based on knowledge of the target application and realistic usage scenarios. The system thermal solution must be designed to dissipate the heat generated during a sustained period of activity with all cores running at TDP at guaranteed maximum frequency.

See Section 35.2, "Feature Summary" for Thermal Management Features.

34.11.4 FAST PROCHOT

Fast PROCHOT provides a mechanism for the platform to trigger a very quick and heavy throttling (decreasing the clock frequency) of the SoC processor cores. This description is an overview of the functionality. For design details for PROCHOT and Fast PROCHOT see Section 35.4, "Thermal Management (TM)."

Fast PROCHOT is typically used by the power supply unit (PSU) to trigger an immediate throttle to protect against unexpected current spikes or thermal conditions. Other customer platform innovation is possible.

Benefits:

- Enables PSU cost reduction without excessive guard banding lowering cost.
- Enables Processor performance without excessive guard banding enhancing performance.

High-Level Flow:

- Via a comparator at the PSU PROCHOT_N is asserted.
- The SoC Power Management Unit (PMU) utilizes the new fast throttle mechanism. Power is reduced quickly via core instruction throttling.

A frequency transition occurs later and is used to provide more power/performance efficient throttling.

34.11.5 Running Average Power Limiting (RAPL)

The SoC contains proprietary power monitors and Running Average Power Limit (RAPL) algorithms that calculate an energy budget and convert the budget into voltage/frequency working points. This section provides an overview of RAPL. For details see Section 35.6, "Run Average Power Limit (RAPL)."

The SoC supports RAPL control through these interfaces:

- MMIO. Recommended usage is BIOS and platform limits.
- MSR. Recommended usage is runtime limits through ring-0 software).
- PECI. Recommended usage is through an external Baseboard Management Controller (BMC) or other platform circuitry via the SoC PECI/SMBus interface.

RAPL is used in mobile devices to conserve battery power, but the SoC is not typically used in applications where battery is the main source of power. The SoC uses RAPL to deal with the SoC Package and DRAM thermal management in the high-density platform environment of Microserver, Storage, and Communication applications. See Section 35.2, "Feature Summary" for Thermal Management Features.

34.11.6 Always-On Timers (AONT)

Always-On Timers run while the SoC is in the S0 state and are used to periodically wake-up the cores from sleeping. They do not run when the SoC transitions out of S0.

34.11.7 I/O Device Controller Enable/Disable

Table 34-10. I/O Power Management Summary

Integrated I/O Device	I/O Feature Not Used by Customer	Nothing Connected to Interface at Boot Time
PCIe* Root Ports	The BIOS disables the circuitry and power on a per-lane basis.	The BIOS disables the circuitry and power on a per-lane basis.
SATA 3.1	The BIOS disables the circuitry and power-on a per-port basis.	Disabled at power-on unless explicitly enabled by the software.
LAN	The BIOS disables the circuitry and power-on a per-port basis.	Ports not WOL-enabled are in P2. Ports with WOL are in P0. If all ports are WOL-disabled, internal clocks off.
USB	The BIOS disables the circuitry and power.	Idle State with internal clocks off.

§ §

35 Thermal Management

The SoC implements configurable forms of thermal management for itself, memory, and the system. The architecture implements various proven methods of maintaining maximum performance while remaining within thermal specifications. Thermal Control Circuit (TCC) mechanisms are used to reduce power consumption when thermal device limits are exceeded, and the system is notified of this condition via interrupts or thermal signaling pins.

35.1 Signal Descriptions

The signal descriptions are shown in Table 35-1, "Signal Names and Descriptions". For additional signal information including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing." The Direction/Type column of Table 35-1, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 35-1. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
MEMHOT_N	I	Yes	**Memory Hot:** Active-low input signal from the platform board indicating memory exceeds temperature limits. When this signal is active, the SoC can perform memory throttling in an attempt to cool the memory devices.
PROCHOT_N	I,O-OD	Yes	**Processor Hot:** Active low. As an input, the platform board External Circuitry (EC) chooses to drive this signal low to reduce SoC current consumption if the EC detects overheating in the board or system. Also as an input, the power supply asserts this signal to trigger the SoC Fast PROCHOT feature in the event of a maximum power excursion. As an output, the signal is asserted if any SoC thermal sensor indicates the component is operating above temperature limits. The platform board must ignore this SoC output signal while PMU_PLTRST_N (active-low SoC output) is asserted. ***Note:*** PROCHOT_N can be configured to be an output or an input signal pin. It cannot be configured to be bi-directional.
THERMTRIP_N	O-OD	Yes	**Catastrophic Thermal Trip:** Active-low, open-drain output signal indicating the SoC has reached an operating temperature that may damage the component. Once THERMTRIP_N is asserted, the platform must remove power by shutting down the power regulators. The platform board must ignore this SoC output signal while PMU_PLTRST_N (active-low SoC output) is asserted. See Section 35.4.5, "THERMTRIP_N" for additional details on THERMTRIP_N. Even though this open-drain output has an internal 20-kΩ pull-up resistor, an external 51-Ω pull-up resistor tied to V1P05 is recommended for open-drain operation.

35.2 Feature Summary

Thermal management features include:

- Up to 13 Digital Thermal Sensors (DTS):
  - Eight sensors, one for each L2 Cache in the processor core area.
  - Five sensors not in the processor core area.
- Thermal Control Circuit (TCC) mechanisms:
  - Configurable PROCHOT_N.
  - Intel® Thermal Monitor 1.
  - Intel® Thermal Monitor 2.
- Catastrophic temperature protection (THERMTRIP_N) and memory temperature protection (MEM_THERMTRIP).
- Two programmable thermal interrupt thresholds per DTS.
- Memory Temperature Management control modes:
  - OLTT - Open Loop Thermal Throttling.
  - CLTT - Closed Loop Thermal Throttling via SMBus-Legacy interface.
  - CLTT Pass-through via SMBus-PECI interface.
- Thermal status/trigger signal pins:
  - MEMHOT_N input-only signal.
  - PROCHOT_N configurable as an input-only signal or as an output-only signal.
  - THERMTRIP_N output-only signal.
- Fan Speed Control (FSC) parameter ($T_{CONTROL}$ and margin to $T_{CONTROL}$)
- Fast PROCHOT_N input signal pin driven by the platform or power supply that triggers a rapid Intel® Thermal Monitor 2 (TM2) throttling response:
  - Available only when PROCHOT_N pin is configured as input-only signal.
- Inverse Temperature Dependence (ITD) function for maintaining processor performance at low temperatures.
- Platform Voltage Regulator Hot Alert to lower voltage needs when a VR is approaching its thermal limits.

35.3 Registers with Multiple Access Methods

Many of the Thermal Management registers mentioned in this chapter are accessible in more than one way. Even so, the type of access used may have unique Read/Write access capabilities. In some cases of access via the PECI SMBus, the temperature values may have a different format or bit length. For details see Chapter 30, "SMBus Controller - Platform Environment Control Interface."

35.4 Thermal Management (TM)

The IA-32 architecture provides mechanisms for monitoring temperature and controlling thermal power. These are presented in sub-section 14.7 of Volume 3 of the *Intel® 64 and IA-32 Architectures Software Developer's Manual* and are listed below along with the section in this document:

- Catastrophic Shutdown detector
  See Section 35.4.5, "THERMTRIP_N."
- Automatic and Adaptive Thermal Monitoring mechanisms
  See Section 35.4.4, "Thermal Throttling."
- Software-Controlled Clock Modulation mechanism
  See Section 35.4.4.4, "Software-Controlled Clock Modulation."
- On-die Digital Thermal Sensor (DTS) and interrupt mechanisms
  See Section 35.4.1, "Digital Thermal Sensor (DTS)."

35.4.1 Digital Thermal Sensor (DTS)

Each of the 13 on-die Digital Thermal Sensor (DTS) reports the temperature of the associated processor core pair or other portions of the SoC circuitry as a temperature relative to the factory-configured Thermal Control Circuit (TCC) Activation Temperature which is also known as DTS_{MAX}.

- There is one DTS for each two-core processor. Here two cores share an L2 cache and a Bus Interface Unit (BIU). Some SoC product SKUs provide only one core processor per L2 cache and BIU and contain one DTS per core processor.
- There are five additional DTSs located in the remaining SoC circuitry.

Each core-related DTS produces a 7-bit temperature value in the TEMPERATURE field of its IA32_THERM_STATUS register (MSR 19Ch). The TEMPERATURE value is reported as a negative offset from the eight-bit REF_TEMP field of the TEMPERATURE_TARGET register. REF_TEMP is the Thermal Monitor Activation Temperature, also called the PROCHOT_N Temperature, TCC Activation Temperature, and DTS_{MAX}. The REF_TEMP value is the maximum temperature at which the silicon is capable of operating.

Example: If TEMPERATURE_TARGET.REF_TEMP indicates 90 °C, a IA32_THERM_STATUS.TEMPERATURE value of 10 decimal implies that this domain is currently operating at 80 °C.

The SoC Package temperature is based on all 13 DTSs and is in the TEMPERATURE field of the IA32_PACKAGE_THERM_STATUS register (MSR 1B1Ch). The TEMPERATURE value is reported as a negative offset from the aforementioned REF_TEMP field of the TEMPERATURE_TARGET register.

The registers associated with DTS configuration and target values are shown here. The core-related and SoC Package Status registers are mentioned in Section 35.5.3, "Thermal Status and Interrupts":

TEMPERATURE_TARGET

MSR_TEMPERATURE_TARGET (MSR 1A2h)
P_CR_TEMPERATURE_TARGET_0_0_0_MCHBAR (MMIO MCHBAR + 7074h)
Temperature Target Read Data (PECI RdPkgConfig(), Index 16)

This 32-bit register contains information about the Fan Speed Control (FSC) target temperature as well as details on the reference temperature for core-pair DTS relative temperature reading. The register contains the TJ_MAX_TCC_OFFSET. It also contains the Read-Only REF_TEMP (also known as DTS_{MAX}) and FAN_TEMP_TARGET_OFFSET (also known as $T_{CONTROL}$) fields which are set at the Intel factory.

DTS_CONFIG3_CFG

P_CR_DTS_CONFIG3_CFG_0_0_0_MCHBAR (MMIO MCHBAR + 7118h)

This 32-bit register contains an offset value to modify $T_{CONTROL}$. This register contains the legacy TCONTROL_OFFSET and OFFSET_PROGRAMMED fields.

35.4.2 Fan Speed Control (FSC)

Note: This chapter deals with software-controlled and BMC-controlled platform fan speed control. While the SoC has the FAN_PWM[3:0] and FAN_TACH[3:0] signal pins, the pins are exclusively controlled by the customer-programmed Innovation Engine (IE) and are not discussed here. See Chapter 37, "Innovation Engine."

While the SoC does not support the DTS 2.0 Fan Speed Control (FSC) feature, it does support the FSC as used on many Intel® Xeon® processor products that are multi-chip packages (MCP) even though the SoC is not an MCP.

The MCP FSC feature reports "Thermal Margin" as the temperature margin relative to the TEMPERATURE_TARGET.FAN_TEMP_TARGET_OFFSET. The FAN_TEMP_TARGET_OFFSET value is also known as $T_{CONTROL}$. It uses the same Thermal Margin access methods as DTS 2.0 FSC, but the underlying calculations are different and the overall algorithm is much simpler.

The Thermal Margin value simply reflects whether or not the SoC is meeting the TEMPERATURE_TARGET.FAN_TEMP_TARGET_OFFSET ($T_{CONTROL}$) specification; negative margin means the platform needs to increase fan speed. At high power levels, Thermal Margin becomes negative because of the thermal load line, but

TEMPERATURE_TARGET.REF_TEMP (DTS_{MAX}) is set at the Intel factory so that the SoC does not throttle when running a TDP workload and meeting the SoC T_{CASE_MAX} specification.

Thermal Margin is calculated as:

PACKAGE_THERM_STATUS.TEMPERATURE
minus the
TEMPERATURE_TARGET.FAN_TEMP_TARGET_OFFSET
where FAN_TEMP_TARGET_OFFSET is a positive value

Software can read the value of Thermal Margin by PECI command or by the THERM_MARGIN field of an MSR or an MMIO register:

PACKAGE_THERM_MARGIN

MSR_PLATFORM_BRV (MSR 1A1h)
P_CR_PACKAGE_THERM_MARGIN_0_0_0_MCHBAR (MMIO MCHBAR + 703Ch)
THERM_MARGIN Read Data (PECI RdPkgConfig(), Index 10)

Bits 15:0 (of the MSR and MMIO) is the THERM_MARGIN: This product does not support DTS 2.0 and margin to the thermal loadline. This register reports margin to the T_CONTROL temperature in 2's compliment format (S16.7.8). Negative margin implies that the temperature is operating above the (static) T_CONTROL temperature, and that thermal controls (fans, etc.) should be attempting to cool the silicon. Positive margin implies that the silicon is operating at a temperature below the T_CONTROL point and that a reduction in cooling may provide better power efficiency. Unlike Intel products that support DTS 2.0, sustained negative margin is expected and acceptable when the SoC is operating with high power consumption.

35.4.3 PROCHOT_N Signal Pin

The SoC PROCHOT_N signal pin can be configured to be an output or an input signal pin. It cannot be configured to be bi-directional. Bits 0, 21, 22 and 23 of the MSR_POWER_CTL register, MSR 1FCh, provide this configuration.

See Table 35-2, "MSR_POWER_CTL (MSR 1FCh)."

Table 35-2. MSR_POWER_CTL (MSR 1FCh)

Bits	Access Type	Default	Description
31:25	-	-	*Reserved*
24	RW	0	**VR_THERM_ALERT_DISABLE**: When set to 1, disables the VR_THERMAL_ALERT signaling.
23	RW	0	**PROCHOT_LOCK**: When set to 1, locks bits 0, 21, 22 and 23 of this MSR. Once set, a reset is required to clear this bit.
22	RW	0	**PROCHOT_RESPONSE**: PROCHOT_N signal pin configurable response enable. 0 = Go to Pn on incoming asserted PROCHOT_N signal. 1 = Go to a state lower than Pn on incoming asserted PROCHOT_N signal. Go to Pm on incoming PROCHOT_N. ***Note:*** PROCHOT_OUTPUT_MODE_DISABLE must be 1 (input-only signal pin) for this bit to function.
21	RW	1	**PROCHOT_OUTPUT_MODE_DISABLE**: PROCHOT_N signal pin output disable. 0 = PROCHOT_N is an output-only signal pin. 1 = PROCHOT_N output is disabled and the PROCHOT_N signal pin is input-only.
20:19	-	-	*Reserved*
18	RW	0	**PWR_PERF_PLTFRM_OVR**: When set to 0 (default), this bit disables access to IA32_ENERGY_PERF_BIAS (MSR 1B0h), causing a GP# fault on access. CPUID.(EAX=6):ECX[3] will read 0.
17:2	-	-	*Reserved*
1	RW	1	**C1E_ENABLE**: Used to enable C1E behavior on every C1 entry (even if MWAIT C1E sub-state bit was not set or when using HLT). When this package-visible bit is set, it causes the CPU to switch to minimum GV point when all cores have entered C1.
0	RO	0	*Reserved*

The PROCHOT_N signal direction and how the SoC reacts are shown in Table 35-3, "PROCHOT_N Signal Direction and Function."

Table 35-3. PROCHOT_N Signal Direction and Function

MSR_POWER_CTL Bit 21 PROCHOT_OUTPUT_MODE_DISABLE	MSR_POWER_CTL Bit 22 PROCHOT_RESPONSE	Resulting PROCHOT_N Signal Pin
0	x	Output-Only Signal
1	0	Input-Only Signal, go to Pn (the default mode)
1	1	Input-Only Signal, go to Pm

- Pn - Use-frequency scaling and voltage scaling to attain PROCHOT relief. Pn is the lowest frequency of operation, also called the Low Frequency Mode (LFM) frequency.
- Pm - Provides more PROCHOT relief than Pn mode does.

The default mode for PROCHOT_N provides the Fast PROCHOT capability. Customers can use the Input-Only, Pm mode to get some additional power savings on PROCHOT, but this will be mostly frequency-only scaling and not voltage scaling.

Generally, Pm provides a small amount of additional PROCHOT relief versus Pn. Even so, the Pm mode can help a bit more on SoC product SKUs that have small dynamic range from throttling.

Fast PROCHOT is enabled when the MSR (1FCh) MSR_POWER_CTL field PROCHOT_OUTPUT_DISABLE (bit 21) is set. When Fast PROCHOT enabled the processor responds to platform requests to operate within the platform power budget, when rapidly exercised by non-ideal workloads. The PROCHOT_N input time response has been improved on the SoC from 3ms to 80us (from PROCHOT_N pin assertion), when FAST PROCHOT is enabled. Additional time is required for the platform to detect a Pmax condition and assert the PROCHOT_N pin (typically around 20 uS). If a rise in power at or above 1.6x TDP for the processor is detected by platform logic, a PROCHOT_N input by the platform or power supply triggers this rapid Intel® Thermal Monitor 2 (TM2) throttling response. Platform logic is required to detect the power level within 20µs and assert PROCHOT_N for this feature usage. It is recommended that PROCHOT_N be configured for input-only mode to take advantage of this reduced response time. The platform is required to use DTS to check for over temperature conditions, when Fast PROCHOT is enabled as the primary means of temperature monitoring for thermal control, as the PROCHOT_N signal output is disabled.

The Output-Only mode can be useful on systems that want to use PROCHOT_N for fan speed control. While this is not the recommended usage model, it can be used on very-low-cost platform designs. PROCHOT_N is asserted by the SoC when a thermal sensor indicates the component is operating above temperature limits.

35.4.4 Thermal Throttling

The SoC has only one thermal-control domain—the processor cores. No uncore throttling is supported. When an over-temperature event occurs based on the Throttle Threshold Temperature (see Section 35.4.4.1, "Throttle Threshold Temperature"), all processor cores are throttled regardless of which of the 13 DTS within the SoC is reporting the over-temperature event.

Note: The SoC does not throttle the processor when DRAM Memory is hot. Memory Thermal Management (see Section 35.5, "Memory Thermal Management (MTM)") is managed independently of Thermal Management.

Two Thermal Throttling mechanisms are implemented to reduce temperature by reducing power consumption in response to temperatures exceeding the Throttle Threshold Temperature:

- Intel® Thermal Monitor 2 (TM2) - Thermal throttling based on voltage and frequency reductions. See Section 35.4.4.2, "Core Frequency/Voltage Reduction (Intel® Thermal Monitor 2)."
- Intel® Thermal Monitor 1 (TM1) - Thermal throttling via core clock modulation using the processor's eHALT feature. See Section 35.4.4.3, "Clock Modulation (Intel® Thermal Monitor 1)."

Note: IA32_MISC_ENABLE (MSR 1A0h), bit 3, is the Automatic Thermal Control Circuit (TCC) Enable. The SoC ignores the setting of this MSR bit, even if it is 0 and the SoC always invokes TM2 and TM1 (automatic TCC).

The SoC invokes TM2 when the SoC package temperature (the highest temperature of the 13 DTSs) has met or has exceeded the Throttle Threshold Temperature defined in the next sub-section.

The SoC only invokes TM1 if TM2 has reached its Maximum Throttle Point of Pm and the SoC is still over temperature.

35.4.4.1 Throttle Threshold Temperature

The Throttle Threshold Temperature is determined from the following equation:

TEMPERATURE_TARGET.REF_TEMP — TEMPERATURE_TARGET.TJ_MAX_TCC_OFFSET

TJ_MAX_TCC_OFFSET can be set by software in 1°C increments. The register default value is 0 offset. If set to 0, the SoC uses an internally-set guardband offset of approximately 0.5°C, making the Throttle Threshold Temperature about 0.5°C below the REF_TEMP value (REF_TEMP is also known as the DTS_{MAX} temperature or the PROCHOT temperature).

35.4.4.2 Core Frequency/Voltage Reduction (Intel® Thermal Monitor 2)

Intel® Thermal Monitor 2 (TM2) refers to thermal throttling based on voltage and frequency. The SoC attempts to lower the temperature by transitioning to a lower operating frequency and lower operating voltage. An internal algorithm attempts to select the highest possible frequency while staying within thermal constraints. If enabled, TM2 is automatically selected as the primary thermal control mechanism and cannot be disabled by the Operating System software.

Since the SoC does not support per-core Px states, all processor core modules of the SoC package throttle together based on the Throttle Threshold Temperature.

When TM2 starts it steps-down the frequency/voltage until the Maximum Efficiency Throttle Point (Pn) is achieved. If the SoC package temperature is still equal-to or above the Throttle Threshold Temperature, it continues to step-down to the Maximum Throttle Point of Pm. If the package temperature is still not below the Throttle Threshold Temperature, TM1 is invoked.

35.4.4.3 Clock Modulation (Intel® Thermal Monitor 1)

Intel® Thermal Monitor 1 (TM1) is activated as a secondary control mechanism when TM2 (see Section 35.4.4.2, "Core Frequency/Voltage Reduction (Intel® Thermal Monitor 2)") is unsuccessful at reducing processor temperatures, and the SoC is still over temperature. TM1 cannot be disabled by the Operating System software.

Figure 35-1. TM1 Use of Processor Clock Duty Cycle Modulation



Figure 14-21. Processor Modulation Through Stop-Clock Mechanism

TM1 works by periodically stopping (gating) the processor clock for a period of time (microseconds), preventing all execution and reducing power. The "duty cycle" of TM1 refers to the percentage of time the clock is running and not gated off.

When TM1 throttling is invoked, the core clock duty-cycle modulation starts stepping down from the clock's maximum "on" duty-cycle ratio until the clock's minimum "on" duty-cycle ratio (1/8) is reached. During pre-throttle, it steps-down the "on" duty cycle 12.5% once every 8 ms. During throttle it does this more often: once every 1 ms.

When TM1 throttling is reduced during throttle the clock "on" duty-cycle ratio goes back to every 8 ms (pre-throttle). If throttling is further reduced, the "on duty-cycle ratio returns to the maximum.

The stop-clock time duration is clock-frequency dependent. Higher frequencies stop the clock for shorter time durations for a given "on" duty-cycle configuration.

35.4.4.4 Software-Controlled Clock Modulation

This mechanism permits Operating Systems (OS) to implement power-management policies that reduce power consumption. This is in addition to the reduction offered by automatic thermal monitoring mechanisms TM2 and TM1.

The SoC supports the "Extension of the software controlled clock modulation" described in sub-section 14.7 of Volume 3 of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

The mechanism is accessible to software through the IA32_CLOCK_MODULATION register (MSR 19Ah).

The register fields are:

— THROTTLE_ACTIVE (bit 4) enables the Software-Controlled Processor Clock Modulation mechanism.

— T_STATE_REQ (bits 3:0), when THROTTLE_ACTIVE is set, this 4-bit field selects the clock modulation duty cycle in 6.25% increments.

For multiple processor cores in a physical package, each processor core can modulate to a programmed duty cycle independently.

This mechanism functions much like the automatic hardware-controlled TM1 mechanism in reducing SoC power consumption.

35.4.5 THERMTRIP_N

The THERMTRIP_N feature provides SoC protection in the event of a catastrophic thermal event, i.e., temperatures are reached which may damage the SoC silicon. The temperature to trigger THERMTRIP_N is set at the factory and is higher than the temperature that invokes TM2 and TM1. The protection is accomplished by reducing SoC power as fast as possible. Dynamic power is largely eliminated by the SoC within microseconds by means of shutting down as many internal clocks as possible.

The SoC asynchronously signals the platform with PMU_SLP_S45_N indicating the SoC has entered the low power S5 state and logs an error in the SoC circuitry in the RTC Power Well.

Note: THERMTRIP is one of the Power Button Override Events. These events cause an unconditional transition to the S5 state and the Power Button Override (PWRBTNOR_STS) bit of the Power Management 1 Enables and Status (PM1_EN_STS) register is set by the SoC and saved by the SoC RTC power well. This bit is not affected by hard resets via CF9h I/O writes and is not reset by the internal POWERGOOD reset. The THERMTRIP indication is preserved through power failures. This bit is still asserted when the global SCI_EN is set to '1' in which case a System Control Interrupt (SCI) will be generated. The BIOS or SCI handler software clears this bit by writing a 1 to it.

The SoC also indicates a THERMTRIP_N event via the active-low THERMTRIP_N output signal pin. When CLTT is enabled for Memory Thermal Management (Section 35.5.1.2, "Close Loop Thermal Throttling (CLTT)"), the MEM_THERMTRIP can be configured to generate the THERMTRIP event.

Overall power to the SoC is eliminated fully once the VRs on the motherboard are shut down within milliseconds. The platform must remove all power (except battery power) to the SoC within 500 ms of a THERMTRIP_N signal assertion. A cold reset is required to recover from a THERMTRIP_N event.

35.4.6 Thermal Status and Interrupts

35.4.6.1 Thermal Status and Interrupts — Processor

The Operating System (OS) can manage both Core processor and SoC package thermal conditions natively without relying on BIOS or other system board components. The SoC can be programmed to generate interrupts for various thermal events. These interrupts are typically handled either by the OS or System Management Mode (SMM) software.

The thermal interrupt Delivery Mode, Interrupt Mask and the Interrupt Vector for this interrupt, can be programmed through the Thermal Monitor Register entry in the local core's APIC Local Vector Table (LVT), or optional modes may be configured that allow the thermal interrupt notification to be routed to a master core for processing. For more information on the APIC LVT Thermal Monitor Register, see Volume 3, Section 10.5 of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

There are two programmable thermal thresholds per core plus two per package. There is no direct mapping to the number of DTS instances, as interrupts are implemented by the SoC power management mechanism, not in the DTS.

The per-core Thermal Status and per-core Thermal Interrupt use the temperature value of the DTS located near the shared L2-cache. This is important to know when accessing the Model-Specific Registers (MSRs).

The SoC Package Thermal Status and Interrupt uses the Maximum Package Temperature value which is defined as the maximum temperature of the 13 SoC DTSes. All DTS sensors are simultaneously monitored for catastrophic thermal conditions. If such a condition occurs, the CPU will perform an immediate shutdown.

THERM_INTERRUPT
IA32_THERM_INTERRUPT (MSR 19Bh)

There are six processor Thermal Interrupts that can be enabled:

- HIGH_TEMP_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon the rising edge of the Thermal Monitor Status of this core as it crosses the Thermal Monitor Activation Temperature to a temperature above it.
- LOW_TEMP_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon the falling edge of the Thermal Monitor Status of this core as it crosses the Thermal Monitor Activation Temperature to a temperature below it.
- PROCHOT_INT_ENABLE - Assertion or de-assertion of PROCHOT_N.
- OUT_OF_SPEC_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon observation that the processor is operating out of its thermal specification. This interrupt is designed as an early warning of thermal runaway in the silicon and shutdown is recommended.
- THRESHOLD_1_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon observation of any rising or falling detection of the core temperature crossing the THRESHOLD_1_REL_TEMP temperature.
- THRESHOLD_2_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon observation of any rising or falling detection of the core temperature crossing the THRESHOLD_2_REL_TEMP temperature.
- THRESHOLD_1_REL_TEMP and THRESHOLD_2_REL_TEMP - Each is a seven-bit value that represents a negative offset from the reference maximum junction temperature defined in TEMPERATURE_TARGET.REF_TEMP. These temperature thresholds are compared against the corresponding Thermal Status Relative Temperature reading for this core.

THERM_STATUS
IA32_THERM_STATUS (MSR 19Ch)
Per-Core DTS Temperature Read Data (PECI RdPkgConfig(), Index 9)

This register is typically used to inspect the thermal status of a specific core as well as to discover the sources of core thermal-interrupt events. There are seven types of processor Thermal Status each with a sticky monitor bit (Log bit) to let software know if a new status bit has been posted. Each status bit is Read-Only.

- POWER_LIMITATION_STATUS - Indicates that the processors are performance limited due to power constraints.
- THERMAL_MONITOR_STATUS - Indicates that any of the Thermal Monitors has tripped and that the SoC processors are currently thermally throttling.
- PROCHOT_STATUS - Indicates PROCHOT is currently asserted.
- OUT_OF_SPEC_STATUS - Indicates that a processor is operating out of its thermal specification.
- THRESHOLD1_STATUS - Indicates that the actual processor temperature is currently higher than or equal to the value set in Thermal Threshold 1.
- THRESHOLD2_STATUS - Indicates that the actual processor temperature is currently higher than or equal to the value set in Thermal Threshold 2.
- TEMPERATURE - Processor DTS temperature (DTS near shared L2 cache) reported as a negative offset in °C from the factory-set TEMPERATURE_TARGET.REF_TEMP.

Note: Because TEMPERATURE and the two temperature threshold values shown above are defined as negative offsets, a higher number means a lower temperature.

Note: The GetTemp() command via the PECI SMBus returns a temperature value which is different than the TEMPERATURE field shown here. See Chapter 30, “GetTemp()” and Chapter 30, “DTS Temperature Data.”

35.4.6.2 Thermal Status and Interrupts — SoC Package

The SoC package thermal status and interrupt are reported the same way the core status and interrupt is reported. See Section 35.4.6.1, "Thermal Status and Interrupts — Processor." The Thermal Monitor Register entry in the core APIC Local Vector Table (LVT) for package-scoped interrupts is identical to entries of core-scoped interrupts. Software is responsible for determining the origin of the interrupt.

PACKAGE_THERM_INTERRUPT
IA32_PACKAGE_THERM_INTERRUPT (MSR 1B2h)

There are seven package-level Thermal Interrupts that can be enabled:

- POWER_INT_ENABLE - When this bit is set a thermal interrupt will be sent upon detection of a rising-edge assertion of the Power Limit Status bit in the IA32_PACKAGE_THERM_STATUS (MSR 1B1h) register.
- HIGH_TEMP_INT_ENABLE - Rising edge of the Thermal Monitor Status of the virtual maximum package temperature.
- LOW_TEMP_INT_ENABLE - Falling edge of the Thermal Monitor Status of the virtual maximum package temperature.
- OUT_OF_SPEC_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon observation that a processor or un-core DTS is operating out of its thermal specification. This interrupt is designed as an early warning of thermal runaway in the silicon and shutdown is recommended.
- PROCHOT_INT_ENABLE - Assertion or de-assertion of PROCHOT_N.
- THRESHOLD_1_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon observation of any rising or falling detection of the SoC package maximum temperature crossing the Threshold 1 temperature.
- THRESHOLD_2_INT_ENABLE - This bit allows software to enable thermal interrupt delivery upon observation of any rising or falling detection of the SoC package maximum temperature crossing the Threshold 2 temperature.

Threshold 1 and Threshold 2 are 7-bit values in IA32_PACKAGE_THERM_INTERRUPT that represent a negative offset from the reference maximum junction temperature defined in MSR_TEMPERATURE_TARGET.REF_TEMP. These temperature thresholds are compared against the corresponding Thermal Status Relative Temperature reading for the "virtual package max temperature." The possible interrupts and associated enable bis are mentioned above.

PACKAGE_THERM_STATUS

IA32_PACKAGE_THERM_STATUS (MSR 1B1h)
Package Thermal Status Data (PECI RdPkgConfig(), Index 20)

There are seven types of package-level Thermal Status, each with a sticky monitor bit (Log bit) to let software know if a new status bit has been posted. Each status bit is Read-Only.

- POWER_LIMITATION_STATUS - Indicates that the processors are performance limited due to power constraints.
- THERMAL_MONITOR_STATUS - Indicates that any of the package Thermal Monitors has tripped and that the package is currently thermally throttling.
- PROCHOT_STATUS - Indicates PROCHOT is currently asserted.
- OUT_OF_SPEC_STATUS - Indicates that a processor is operating out of its thermal specification.
- THRESHOLD1_STATUS - Indicates that the actual package temperature is currently higher than or equal to the value set in Thermal Threshold 1.
- THRESHOLD2_STATUS - Indicates that the actual package temperature is currently higher than or equal to the value set in Thermal Threshold 2.
- TEMPERATURE - Package temperature reported as a negative offset in °C from the factory-set TEMPERATURE_TARGET.REF_TEMP.

Note: Because TEMPERATURE and the two temperature thresholds shown above are defined as negative offsets, a higher number means a lower temperature.

35.5 Memory Thermal Management (MTM)

The SoC can provide thermal management of the DIMM components of the platform board that are connected to the SoC Memory Controllers. After the SoC memory subsystem has been setup by BIOS the BIOS needs to indicate how memory thermals are to be managed by the SoC. The SoC-internal registers written by BIOS at boot time must remain statically configured.

Note: The Memory Thermal Management registers are not accessible as SoC Model-Specific Registers (MSRs).

35.5.1 Thermal Throttling

Three Memory Thermal Management (MTM) methods are available: Open Loop Thermal Throttling (OLTT); Closed Loop Thermal Throttling (CLTT); CLTT Pass-Through. The MTM mode is selected via the P_CR_MEM_THERM_CTRL_0_0_0_MCHBAR register. Memory throttling can be configured to generate an SMI.

There are no Model-Specific Registers (MSRs) associated with MTM.

The SoC does not support the reading of the DRAM device's Mode Register 4 (MR4). Because of this, memory subsystems that do not read the DIMM temperature sensors via Serial Presence Detect (SPD) and the SoC Legacy SMBus, or have the ability to provide the SoC the DIMM temperature via the PECI SMBus, need to use OLTT for Memory Thermal Management.

The SoC has a dedicated Memory Hot input indicator pin, named MEMHOT_N, to allow the platform to indicate when memory thermal throttling is required. It is a fast-responding event to the SoC power-management control, approximately 100 µs. The amount of thermal throttling can be programmed during the setup at boot time.

The SoC response to the MEMHOT_N input signal pin can be enabled and configured in the P_CR_MEMHOT_THERM_CONFIG_0_0_0_MCHBAR register. The three bandwidth throttle levels of P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR are used in the P_CR_MEM_THERM_CTRL_0_0_0_MCHBAR register.

The state of the MEMHOT_N signal pin is provided in the P_CR_MEMHOT_THERM_STATUS_0_0_0_MCHBAR register.

35.5.1.1 Open Loop Thermal Throttling (OLTT)

The OLTT mode provides a fixed level of memory thermal throttle via a bandwidth limit mechanism programmed by BIOS during boot time. The bandwidth throttle level used is programmable in the two-bit OLTT_THROT_LVL field of the P_CR_MEM_THERM_CTRL_0_0_0_MCHBAR register. The throttle level values are the same as the values programmed for CLTT mode and explained in Section 35.5.1.3, "CLTT Throttle Levels." The throttle-level values can be altered at runtime.

The memory bandwidth limits work by limiting the number of memory reads/writes within a given interval. BIOS programs the bandwidth percentage and the SoC converts that bandwidth percentage into the number of reads and writes for a particular interval.

Note: Even though the P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR register is associated with CLTT mode, its three throttling level values are used for OLTT mode and for the MEMHOT_N input signal pin mechanism.

35.5.1.2 Close Loop Thermal Throttling (CLTT)

In CLTT mode the SoC provides three configurable levels of memory bandwidth throttling that are triggered in response to temperature data sent from the DIMMs to the SoC. The SoC can be programmed to use one of two ways to receive this temperature data:

- Normal: DIMM temperature readings are periodically obtained via SPD by the SoC using the Legacy SMBus interface.
- Pass-through: Temperature readings are provided to the SoC from the platform Baseboard Management Controller (BMC) via the SMBus PECI interface.

DIMM temperature data are provided by a “Temperature Sensor On DIMM” (TSOD).

For normal CLTT the temperature readings are provided directly from the Legacy SMBus interface.

For pass-through CLTT the BMC is required to acquire TSOD temperature measurements from the DIMM or obtain DIMM temperature information by some other means or mechanism, and write the measurements to the SoC using PECI commands via the SoC PECI SMBus. The BMC, or other means is expected to update the DIMM temperature values via the PECI SMBus every 5-10 ms.

The SoC supports dynamic CLTT which allows the platform to make run-time updates to MTM configuration values that adjusts the temperature dynamic range in response to memory subsystem environmental changes detected by the platform.

35.5.1.3 CLTT Throttle Levels

In CLTT normal mode the MTM throttle level is based on the threshold crossed by the highest, adjusted DIMM temperature value the SoC receives via SPD over the SoC Legacy SMBus interface. The throttle levels are programmed by BIOS in the P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR register:

00 = no throttle
01 = THRT_MID (default is 0% throttled)
10 = THRT_HI (default is 90% throttled)
11 = THRT_CRIT (default is 99% throttled)

The % values of throttling are interpreted as shown in the following example:

If the value is 25% throttled then 75% of the maximum memory bandwidth will be available.

In CLTT mode, the throttle-level values in the P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR register can be adjusted after BIOS boot time.

The memory bandwidth limits work by limiting the number of memory reads/writes within a given interval. BIOS programs the bandwidth percentage, and the SoC converts that bandwidth percentage into the number of reads and writes for a particular interval.

35.5.1.4 CLTT Temperature Threshold Values

In CLTT mode, there are three programmable temperature threshold values which trigger MTM responses. They are programmed by BIOS. Their names, location in the P_CR_MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR register, default values, and MTM response are:

- TEMP_LO (bit 1), TSOD = 84 °C, Initiate 2x refresh rate and THRT_MID.
- TEMP_MID (bit 10), TSOD= 93 °C, Initiate THRT_HI, continue 2x refresh rate.
- TEMP_HI (bit 11), TSOD = 100 °C, Initiate THRT_CRIT, continue 2x refresh rate, assert MEM_THERMTRIP.

The P_CR_MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR register also contains a three-bit TEMP_THROT_HYST field that provides a programmable, negative-going threshold hysteresis value that is programmable by BIOS.

To account for offsets between DIMM hot-spot temperature and the reported TSOD values, per-DIMM temperature offsets can be programmed in the P_CR_MEM_THERM_TEMP_OFST_0_0_0_MCHBAR register.

Note: It is the responsibility of the platform to ensure that current, accurate temperature data is provided. The SoC Memory Thermal Management algorithms have no mechanism to detect if temperature data is stale or invalid. If TSODs malfunction, it is recommended that the platform utilize the MEMHOT_N input signal pin as a backup mechanism to control DIMM temperature.

The offset temperature values in the P_CR_MEM_THERM_TEMP_OFST_0_0_0_MCHBAR register and the throttle thresholds in the P_CR_MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR register that the SoC uses to create variable MTM throttle thresholds, can be based on system information such as airflow. These registers can be written by the BMC via the PECI WrEndPointConfig() command over the SoC PECI SMBus interface. This PECI command writes the appropriate register located within the SoC sideband registers. See Chapter 30, "WrEndPointConfig()."

35.5.1.5 Legacy SMBus Used for Accessing Information for CLTT

When in CLTT Normal mode, the SoC uses a special internal connection to the Legacy SMBus interface as an SMBus Master to acquire DIMM-related CLTT information from the system DIMMs. See Figure 35-2, "CLTT SMBus Connection to DIMMs."

Figure 35-2. CLTT SMBus Connection to DIMMs



SoC commands to the SMBus slave (one of the installed DIMMs) are initiated through SoC-internal messages to the SoC SMBus interface hardware by the SoC power-management controller. As an SMBus bus master, the CLTT-based SoC SMBus hardware issues the particular transaction on the SMBus. Only a limited set of SMBus transactions are supported for this purpose.

Once the transaction over the SMBus interface has been completed, the SoC SMBus hardware places the data in SoC-internal registers and responds to the SoC power-management controller that the SMBus operation has been completed.

The CLTT SMBus operations do not support the SMBus Alert option (SMB_LEG_ALRT_N signal). The Legacy SMBus controller does support SMBus Alert.

The Temperature Sensor On DIMM (TSOD) information acquired by this SMBus mechanism is available to software and BIOS through the SoC Sideband registers:

- C0TEMPSTS0 - DIMM 0 of Memory Channel 0
- C0TEMPSTS1 - DIMM 1 of Memory Channel 0
- C1TEMPSTS0 - DIMM 0 of Memory Channel 1
- C1TEMPSTS1 - DIMM 1 of Memory Channel 1

35.5.1.6 PECI SMBus Used for Accessing Information for CLTT

When in CLTT Pass-Through mode, the BMC or some other external management agent writes temperature measurements periodically to the SoC using a PECI write command via the SoC PECI SMBus interface. See Chapter 30, "DRAM Rank Temperature Write (Index = 18)" in the PECI SMBus chapter.

35.5.2 MEM_THERMTRIP

Internal to the SoC, MEM_THERMTRIP indicates that a DIMM temperature has exceeded the highest temperature threshold and memory is considered to be in a state of catastrophic thermal failure. The MEM_THERMTRIP state is determined by the Memory Thermal Management (MTM) throttling algorithm but initiates an additional configurable response that can trigger a processor THERMTRIP_N event.

The SoC-generated P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR register bits are used by the SoC to generate and internal MEM_THERMTRIP indication.

If configured to do so, MEM_THERMTRIP can generate the SoC-internal THERMTRIP event indication and assert the SoC THERMTRIP_N signal pin. This is configured by the EN_MEMTRIP field of the P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR register.

35.5.3 Thermal Status and Interrupts

While the SoC does not generate interrupts for Memory Thermal Management events, it does provide various CLTT and customer-configurable status and logs available through the P_CR_MEM_THERM_INT_STATUS_0_0_0_MCHBAR register:

- "CLTT SMBus is hung" status and log
- "CLTT SMBus is reset" status and log
- DIMM temperature is at or above the point to cause SoC memory throttling. Status and log.

Each log is one bit that is set to 1 the first time the particular status is set and remains sticky until cleared via software or by reset.

When in CLTT mode, either in Normal or Pass-Through mode, the SoC provides thermal status and a log for each of the DIMMs of the memory subsystem. These can be read by software in the P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR register. Each DIMM has a two-bit field:

- 00 = Memory temperature < TEMP_LO
- 01 = TEMP_LO ≤ Memory temperature < TEMP_MID
- 10 = TEMP_MID ≤ Memory temperature < TEMP_HI
- 11 = Memory temperature ≥ TEMP_HI (MEM_THERMTRIP condition)

For TEMP_HI, TEMP_MID, and TEMP_LO, see Section 35.5.1.4, "CLTT Temperature Threshold Values."

Each DIMM has a two-bit Thermal Throttle log in the P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR register. The logs are sticky bits set to highest throttle level achieved (same encoding as P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR register fields) when CLTT memory throttling is initiated by the particular DIMM. The logs remain set until cleared when software writes a 1 value to the log field or the SoC is reset. For more information about memory throttle levels, see Section 35.5.1.3, "CLTT Throttle Levels."

35.6 Run Average Power Limit (RAPL)

RAPL provides platform software the ability to monitor, control, and get notifications about SoC power consumption. The SoC provides RAPL for managing platform thermals.

The Thermal Design Power (TDP) specified for the SoC represents the maximum amount of power the platform cooling system required to dissipate in order for the SoC to operate. But it is possible for the processor to consume more than the TDP power for a short period of time without it being thermally significant. The primary use case of RAPL is providing software the ability of setting per-package, hardware-enforced, power limits. In addition, RAPL provides a very accurate power meter capable of supporting core and non-core devices.

The SoC supports two RAPL domains of power rationing:

- SoC Package domain which includes everything on the die
- DRAM domain which includes the directly-attached DRAM

The PKG_POWER_LIMIT and DRAM_POWER_LIMIT registers are used to configure which RAPL domain is to be enabled. Having both SoC Package RAPL and DRAM RAPL combined into a single RAPL limit called Super-Domain RAPL is not supported.

The SoC supports external access to the RAPL domain interfaces three ways:

- Non-architectural Model-Specific Registers (MSRs) using RDMSR and WRMSR instructions
- Memory-Mapped I/O (MMIO) registers in Host Root Space
- By the BMC, or equivalent, through PECI SMBus commands to access the RAPL registers.

The following set of capabilities are supported through the interfaces:

- Power Limit - Specify power limit, time window, and other controls. RAPL provides a way to set short-term and longer-term averaging windows for Power Limits. Platform thermal control software is advised to dynamically update the RAPL Power Limits and the averaging windows to meet SoC system requirements.
- Energy Status -Access the power-metering interface providing energy consumption information.
- Perf Status - Access to information on the performance effects (regression) due to Power Limits. It is defined as a duration metric that measures the Power Limit effect in the respective domain.
- Power Info - Interface providing information on the range of parameters for a given domain.

The SoC provides the Read-Only RAPL_POWER_UNIT register for software to discover the basic units of time, energy and power defined for SoC Package RAPL and DRAM RAPL.

For additional details about RAPL, see Volume 3, Chapter 14 of the *Intel® 64 and IA-32 Architectures Software Developer's Manual*.

35.6.1 RAPL — SoC Package

For SoC Package RAPL, both Power Limit 1 (PL1) and PL2 Power/Time tuples are supported.

PL1 is typically used for long thermal-time constants, defaulting to Thermal Design Power (TDP) Power/Time. PL2 is typically programmed for a shorter Power/Time tuple to manage Dynamic Turbo where power is allowed to exceed TDP for short, thermal time constants, thus allowing burst performance. To mitigate power, the SoC manages internal power-management mechanisms if required to meet the power tuples. Both PL1 and PL2 have their own control systems which operate concurrently.

The SoC also provides what is called “Fast RAPL” which is a special duty-cycle protection to control excursions past PL2 to limit the duty-cycle of power transients greater than PL2. The purpose of this protection is to avoid thermal over-design of the platform Voltage Regulator (VR). The protection allows the guaranteed VR duty-cycle specifications to be greater than PL2 alone would allow. The SoC uses the SVID interface to read the output current of VCC, VNN and VCCRAM VRs to calculate power to provide this special protection. The VR needs to be capable of being sampled at 100-µs intervals for output current as well using its internal A/D converter to provide a 200-µs anti-aliasing filter prior to digital conversion.

The registers associated with SoC Package RAPL are accessible by RDMSR/WRMSR instructions, through Memory-Mapped I/O (MMIO), or using PECI commands via the PECI SMBus interface. In some cases the PECI information has a different format:

RAPL_POWER_UNIT

MSR_RAPL_POWER_UNIT (MSR 606h)
P_CR_PACKAGE_POWER_SKU_UNIT_0_0_0_MCHBAR (MMIO MCHBAR + 7068h)
Package Power SKU Unit Read Data (PECI RdPkgConfig(), Index 30)

This register defines the units for calculating all SoC Package RAPL and DRAM RAPL RAPL power, current, energy, resistance and timing parameters.

PKG_POWER_LIMIT

MSR_PKG_POWER_LIMIT (MSR 610h)
P_CR_PACKAGE_RAPL_LIMIT_0_0_0_MCHBAR (MMIO MCHBAR + 70A8h)
Package Power Limits for Multiple Turbo Modes (PECI WrPkgConfig(), Index 26)
Package Power Limits for Multiple Turbo Modes (PECI RdPkgConfig(), Index 27)

This register allows software to define power limitation for the SoC Package RAPL domain. PL1 and PL2 power limits and associated time windows can be specified. The values are expressed in units defined by the RAPL_POWER_UNIT register.

PKG_ENERGY_STATUS

MSR_PKG_ENERGY_STATUS (MSR 611h)
P_CR_PACKAGE_ENERGY_STATUS_0_0_0_MCHBAR (MMIO MCHBAR + 706Ch)
Accumulated Energy Status Read Data (PECI RdPkgConfig(), Index 03)

This 32-bit Read-Only register contains an accumulated value of the energy consumed by the entire SoC package. The value of this register is updated by the SoC approximately once every 1 ms. The units are proportional to Joules and are defined by the RAPL_POWER_UNIT register. The SoC uses this value for PL1 and PL2 RAPL algorithms.

PKG_PERF_STATUS

MSR_PKG_PERF_STATUS (MSR 613h)
P_CR_PACKAGE_RAPL_PERF_STATUS_0_0_0_MCHBAR (MMIO MCHBAR + 7050h)
Package Power Limit Performance Status Read Data (PECI RdPkgConfig(), Index 08)

Measures the time that any core in the SoC package is performance-throttled below what the Operating System requested and below the core's base frequency because of Power Limits PL1 or PL2. The time value is expressed in units defined by the RAPL_POWER_UNIT register.

PKG_POWER_INFO

MSR_PKG_POWER_INFO (MSR 614h)
P_CR_PACKAGE_POWER_SKU_0_0_0_MCHBAR (MMIO MCHBAR + 70A0h)
Package Power SKU Read Data (PECI RdPkgConfig(), Index 28 and 29)

This register provides the factory-defined limits for the configurable PL1 and PL2 SoC Package Power Limits and Time Windows in the PKG_POWER_LIMIT register. The values are expressed in units defined by the RAPL_POWER_UNIT register.

PP0_ENERGY_STATUS

MSR_PP0_ENERGY_STATUS (MSR 639h)
P_CR_PRIMARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR (MMIO MCHBAR + 705Ch)

This register contains an accumulated value of the energy consumed in the primary power plane across all cores of the SoC. The value is expressed in units defined by the RAPL_POWER_UNIT register. The value of this register is updated approximately once every 1 ms.

PP1_ENERGY_STATUS

MSR_PP1_ENERGY_STATUS (MSR 641h)
P_CR_SECONDARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR (MMIO MCHBAR + 7060h)

This register contains an accumulated value of the energy consumed in the secondary power plane across all cores of the SoC. The value is expressed in units defined by the RAPL_POWER_UNIT register. The value of this register is updated approximately once every 1 ms.

TURBO_ACTIVATION_RATIO

MSR_TURBO_ACTIVATION_RATIO (MSR 64Ch)

P_CR_TURBO_ACTIVATION_RATIO_0_0_0_MCHBAR (MMIO MCHBAR + 70F0h)

ACPI P-T Notify Write Data (PECI WrPkgConfig(), Index 33)
ACPI P-T Notify Read Data (PECI RdPkgConfig(), Index 33)

This register is used by software to configure the Performance State (P-State) at which Turbo activates. Turbo activation starts at clock ratios above the eight-bit Turbo Activation Ratio Threshold (MAX_NON_TURBO_RATIO field) configured in this register. This feature is disabled when the threshold is set to zero.

IA_PERF_LIMIT_REASONS

MSR_IA_PERF_LIMIT_REASONS (MSR 64Fh)

P_CR_IA_PERF_LIMIT_REASONS_0_0_0_MCHBAR (MMIO MCHBAR + 70B0h)

This register reports reasons for performance limitations on the processor cores. Status bits are an instantaneous indication of an active constraint. Log bits indicate that a constraint was enforced since the log bit was last cleared.

CORE_PERF_LIMIT_REASONS

MSR_CORE_PERF_LIMIT_REASONS (MSR 690h)

Indicator of Frequency Clipping in Processor Cores (R/W). Frequency refers to processor core frequency. I see 11 status fields and 11 associated logs.

PL3_CONTROL

Official MSR Name is TBD (MSR 615h)
P_CR_PL3_CONTROL (Sideband Port P47h, offset 4790h)

Control Power Limit 3 (PL3) and Power Limit 4 (PL4) using this register.

This limit control is physically different from the same control in the IA core MSR space.

— PL3 is designed to clamp peak sustained power to levels supported by the battery or input power supply and as such manage lifetime degradation of that power delivery element. With PL3, peak power excursions above the limit are allowed so long as they do not exceed the configured duty cycle constraint in this register.

— PL4 is designed to clamp peak instantaneous power to levels below the max supported by the battery or input power supply. These clamps are implemented a priori and the SoC is guaranteed to constrain itself below the PL4 limit always.

35.6.2 RAPL — DRAM

Note: DRAM RAPL is not supported when Non-Volatile DIMMs (NVDIMMs) are used.

Note: Both Memory Thermal Management (MTM) and RAPL are capable of throttling memory bandwidth. When both MTM and RAPL are in effect, the memory bandwidth limit will be set to the more restrictive limit between MTM and RAPL. When either condition (MTM or RAPL) is removed, the remaining memory bandwidth limit will be invoked until conditions change such that a different limit, or no limit, is required.

DRAM RAPL is a SoC feature that manages the DRAM power budget to a programmable value. The SoC only supports DRAM RAPL Power Level 1 (PL1) Limit Power/Time tuple. RAPL manages the DRAM domain power which comprises the summation of all the DIMMs populated on the two Memory Controller channels: Two DIMMs per channel; Two ranks per DIMM. To keep within the set Power/Window values, the DIMM power consumption is mitigated by the SoC controlling the memory-access bandwidth by using bandwidth throttling.

The registers associated with DRAM RAPL are accessible by either RDMSR/WRMSR instructions, through Memory-Mapped I/O (MMIO), or using PECI commands via the PECI SMBus interface. In some cases the PECI information has a different format:

DRAM_POWER_LIMIT
MSR_DRAM_POWER_LIMIT (MSR 618h)
P_CR_DDR_RAPL_LIMIT_0_0_0_MCHBAR (MMIO MCHBAR + 7040h)
DRAM Power Limit Data (PECI RdPkgConfig()/WrPkgConfig(), Index 34)

This register is written by the platform software and read by the SoC approximately once every 1 ms. It contains the DRAM Power Limit enable, the DRAM Power Limit value, and the Time Window value. The values are expressed in units defined by the RAPL_POWER_UNIT register.

DRAM_ENERGY_STATUS
MSR_DRAM_ENERGY_STATUS (MSR 619h)
P_CR_DDR_ENERGY_STATUS_0_0_0_MCHBAR (MMIO MCHBAR + 7048h)
Accumulated DRAM Energy Read Data (PECI RdPkgConfig(), Index 04)

This 32-bit Read-Only register contains the Joules of energy consumed by all DIMMs. The value of this register is updated by the SoC approximately once every 1 ms. The units are proportional to Joules and are defined by the RAPL_POWER_UNIT register.

DRAM_PERF_STATUS
MSR_DRAM_PERF_STATUS (MSR 61Bh)
P_CR_DDR_RAPL_PERF_STATUS_0_0_0_MCHBAR (MMIO MCHBAR + 704Ch)
DRAM Power Limit Performance Status Read Data (PECI RdPkgConfig(), Index 38)

Memory RAPL performance throttling counter. This counter accumulates time that any channel in the memory controller is bandwidth-throttled due to memory RAPL constraints. The time values are expressed in units defined by the RAPL_POWER_UNIT register.

DRAM_POWER_INFO
MSR_DRAM_POWER_INFO (MSR 61Ch)
P_CR_DRAM_POWER_INFO_0_0_0_MCHBAR (MMIO MCHBAR + 7130h)
DRAM Power Info Read Data (PECI RdPkgConfig(), Index 35 and 36)

Various DRAM RAPL power and time-window information.

35.7 Inverse Temperature Dependence (ITD)

Inverse Temperature Dependence (ITD) is a SoC feature where internal circuitry requests the platform board VRs to increase SoC voltages at cold temperatures to compensate for timing-path slowdown when cold. The ITD feature is provided on all SoC product SKUs for the VCC, VCCSRAM, and VNN voltage groups. The temperature values and voltage offsets are set at the Intel factory.

Note: ITD is also known as Low Temperature Effect Compensation (LTEC).

35.8 Platform Voltage Regulator Thermal Alert

The SoC supports VR_THERMALERT. The SoC polls the SVID status message for the bit that indicates the platform board Voltage Regulator (VR) is approaching its maximum operating temperature. The VR asserts the VR_THERMALERT bit in the SVID message at a VR temperature lower than the one it uses to assert its VR-hot# pin. The pin is used to drive the SoC PROCHOT_N signal pin if PROCHOT_N is configured as a SoC input.

In response to the VR_THERMALERT indication the SoC reduces all cores in Turbo Mode (P0 Performance State) directly to the P1 Performance State, and clamps it there, but does not throttle (lower the SoC voltage and clock-frequency) any further. Cores in lower P-states remain in those states. No interrupt is generated.

Turbo is then disallowed until the VR_THERMALERT condition is removed.

The VR_THERMALERT signaling is disabled when VR_THERM_ALERT_DISABLE, bit 24 of the MSR_POWER_CTL register (MSR 1FCh), is set to 1.

There are three ways software can access the access the VR_THERMALERT status:

PERF_LIMIT_REASONS

MSR_IA_PERF_LIMIT_REASONS (MSR 64Fh)

P_CR_IA_PERF_LIMIT_REASONS_0_0_0_MCHBAR (MMIO MCHBAR + 70B0h)

The fields are:

VR_THERMALERT_STATUS (bit 10) - Read-Only. Clock frequency is limited due to a VR thermal excursion.

VR_THERMALERT_LOG (bit 26) - Logged indication that frequency was clamped due to a VR thermal excursion. This bit is set by the SoC and can be cleared by software.

35.9 Model-Specific Registers (MSR)

Table 35-4. MSR Registers

MSR Address (hex)	Register Name	Register Name (Basic Name)
199	IA32_PERF_CTL	PERF_CTL
19A	IA32_CLOCK_MODULATION	CLOCK_MODULATION
19B	IA32_THERM_INTERRUPT	THERM_INTERRUPT
19C	IA32_THERM_STATUS	THERM_STATUS
1A0	IA32_MISC_ENABLE	MISC_ENABLE
1A1	MSR_PLATFORM_BRV	PLATFORM_BRV
1A2	MSR_TEMPERATURE_TARGET	TEMPERATURE_TARGET
1AA	MSR_MISC_PWR_MGMT	MISC_PWR_MGMT
1B1	IA32_PACKAGE_THERM_STATUS	PACKAGE_THERM_STATUS
1B2	IA32_PACKAGE_THERM_INTERRUPT	PACKAGE_THERM_INTERRUPT
1FC	MSR_POWER_CTL	POWER_CTL
606	MSR_RAPL_POWER_UNIT	RAPL_POWER_UNIT
610	MSR_PKG_POWER_LIMIT	PKG_POWER_LIMIT
611	MSR_PKG_ENERGY_STATUS	PKG_ENERGY_STATUS
613	MSR_PKG_PERF_STATUS	PKG_PERF_STATUS
614	MSR_PKG_POWER_INFO	PKG_POWER_INFO
618	MSR_DRAM_POWER_LIMIT	DRAM_POWER_LIMIT
619	MSR_DRAM_ENERGY_STATUS	DRAM_ENERGY_STATUS
61B	MSR_DRAM_PERF_STATUS	DRAM_PERF_STATUS
61C	MSR_DRAM_POWER_INFO	DRAM_POWER_INFO
64F	MSR_IA_PERF_LIMIT_REASONS	IA_PERF_LIMIT_REASONS

§ §

36 System Management

The Intel® Management Engine (Intel® ME) is a subsystem that provides the system management. The Intel® ME firmware is provided and developed by Intel.

The Innovation Engine (IE) is an optional feature through which SoC customers can create a custom system-management subsystem. See Chapter 37, "Innovation Engine."

Figure 36-1. What is Covered in This Chapter



36.1 Signal Descriptions

The Intel® ME has three SMBus controllers that tie into the SoC SMBus interfaces. The signals for these SMBus controllers are shown in Chapter 27, "System Management Bus (SMBus) Controller - Overview."

For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing." The Direction/Type column of Table 36-1, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 36-1. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
SMB_ME_SMT0_CLK	I,O-OD	Yes	**SMBus Clock:** (SMBCLK) for System Management Transport 0 of the Intel® ME
SMB_ME_SMT0_DATA	I,O-OD	Yes	**SMBus Data:** (SMBDAT) for System Management Transport 0 of the Intel® ME.
SMB_ME_SMT0_ALRT_N	I,O-OD	Yes	**SMBus Alert:** (SMBALERT#) for System Management Transport 0 of the Intel® ME.
SMB_ME_SMT1_CLK	I,O-OD	Yes	**SMBus Clock:** (SMBCLK) for System Management Transport 1 of the Intel® ME.
SMB_ME_SMT1_DATA	I,O-OD	Yes	**SMBus Data:** (SMBDAT) for System Management Transport 1 of the Intel® ME.
SMB_ME_SMT2_CLK	I,O-OD	Yes	**SMBus Clock:** (SMBCLK) for System Management Transport 2 of the Intel® ME.
SMB_ME_SMT2_DATA	I,O-OD	Yes	**SMBus Data:** (SMBDAT) for System Management Transport 2 of the Intel® ME.

36.2 Intel® ME and Intel Server Platform Services Firmware

36.2.1 Key Properties of Intel® ME

- Connectivity:
  - Delivery of advanced I/O functions.
- Security:
  - More secure and isolated execution.
- Modularity and Partitioning:
  - OSV, VMM and SW independence.
- Power:
  - When in S0, the SoC can be configured by BIOS to completely shut down Intel® ME power.
  - The SoC has a power-disable policy that can be set to shut down the Intel® ME and all its contents are lost.
  - Advanced functions in low power S5 operation.
  - OS independent PM and thermal heuristics.

36.2.2 Intel® ME Requirements

The following list of components composes the Intel® ME hardware infrastructure.

- The Intel® ME is the general purpose controller that resides in the SoC. It operates in parallel to, and is resource-isolated from, the host processor.
- The SPI flash device stores Intel Server Platform Services (SPS) FW code that is executed by the Intel® ME for its operations. The SoC controls the flash device through the SPI interface and internal logic.
- The Intel® ME interacts with the SoC BIOS/UEFI to make sure the Flexible I/O Adapter (FIA) and associated High-Speed I/O (HSIO) lanes are properly configured. See Chapter 10, “Flexible I/O Adapter (FIA) Overview.”

36.3 Register Map

The Intel® ME is accessible through the Host Root Space as shown in Figure 36-2, "Register Map."

Figure 36-2. Register Map



36.3.1 Host Root Space - Intel® ME HECI1

36.3.1.1 PCI Configuration and Capabilities

Table 36-2. Configuration and Capabilities Register Map (Sheet 1 of 2)

Offset from Configuration Space of B0:D24:F0 (hex)	Register Short Name	Description
0	HECI1_ID	Identifiers
4	HECI1_CMD	Command
6	HECI1_STS	Status
8	HECI1_RID_CC	Revision ID and Class Code
C	HECI1_CLS	Cache Line Size
D	HECI1_MLT	Master Latency Timer
E	HECI1_HTYPE	Header Type
F	HECI1_BIST	Built In Self-Test
10	HECI1_MMIO_MBAR_LO	HECI MMIO Base Address Low
14	HECI1_MMIO_MBAR_HI	HECI MMIO Base Address High
2C	HECI1_SS	Sub System Identifiers
34	HECI1_CAP	Capabilities Pointer
3C	HECI1_INTR	Interrupt Information
3E	HECI1_MGNT	Minimum Grant
3F	HECI1_MLAT	Maximum Latency
40	HECI1_HFS	Host Firmware Status
44	HECI1_MISC_SHDW	Miscellaneous Shadow
48	HECI1_GS_SHDW1	General Status Shadow 1
4C	HECI1_H_GS1	Host General Status
50	HECI1_PID	PCI Power Management Capability ID
52	HECI1_PC	PCI Power Management Capabilities
54	HECI1_PMCS	PCI Power Management Control and Status
60	HECI1_GS_SHDW2	General Status Shadow 2
64	HECI1_GS_SHDW3	General Status Shadow 3
68	HECI1_GS_SHDW4	General Status Shadow 4
6C	HECI1_GS_SHDW5	General Status Shadow 5
70	HECI1_H_GS2	Host General Status 2
74	HECI1_H_GS3	Host General Status 3
8C	HECI1_MID	Message Signaled Interrupt Identifiers
8E	HECI1_MC	Message Signaled Interrupt Message Control
90	HECI1_MA	Message Signaled Interrupt Message Address
94	HECI1_MUA	Message Signaled Interrupt Upper Address
98	HECI1_MD	Message Signaled Interrupt Message Data
A0	HECI1_HIDM	HECI Interrupt Delivery Mode

Table 36-2. Configuration and Capabilities Register Map (Sheet 2 of 2)

Offset from Configuration Space of B0:D24:F0 (hex)	Register Short Name	Description
BC	HECI1_HERS	Host Extend Register Status
C0	HECI1_HER1	Host Extend Register DW1.
C4	HECI1_HER2	Host Extend Register DW2.
C8	HECI1_HER3	Host Extend Register DW3.
CC	HECI1_HER4	Host Extend Register DW4.
D0	HECI1_HER5	Host Extend Register DW5.
D4	HECI1_HER6	Host Extend Register DW6.
D8	HECI1_HER7	Host Extend Register DW7.
DC	HECI1_HER8	Host Extend Register DW8.
F8	HECI1_MANID	Manufacturer's ID

36.3.1.2 Memory-Mapped Registers

Table 36-3. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
HECI1_MMIO_MBAR (HI,LO)	0	HECI1_H_CB_WW	Host CB Write Window
HECI1_MMIO_MBAR (HI,LO)	4	HECI1_H_CSR	Host Control and Status Register
HECI1_MMIO_MBAR (HI,LO)	8	HECI1_CSE_CB_RW	CSE Circular Buffer Read Window
HECI1_MMIO_MBAR (HI,LO)	C	HECI1_CSE_CSR_HA	CSE Control and Status Register Host Access
HECI1_MMIO_MBAR (HI,LO)	800	HECI1_D0I3C	D0i3 Control

36.3.1.3 I/O-Mapped Registers

This device has no I/O-mapped registers.

36.3.1.4 Sideband Registers

This device has no Sideband Registers.

36.3.2 Host Root Space - Intel® ME HECI2

36.3.2.1 PCI Configuration and Capabilities

Table 36-4. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D24:F1 (hex)	Register Short Name	Description
0	HECI2_ID	Identifiers
4	HECI2_CMD	Command
6	HECI2_STS	Status
8	HECI2_RID_CC	Revision ID and Class Code
C	HECI2_CLS	Cache Line Size
D	HECI2_MLT	Master Latency Timer
E	HECI2_HTYPE	Header Type
F	HECI2_BIST	Built In Self-Test
10	HECI2_MMIO_MBAR_LO	HECI MMIO Base Address Low
14	HECI2_MMIO_MBAR_HI	HECI MMIO Base Address High
2C	HECI2_SS	Sub System Identifiers
34	HECI2_CAP	Capabilities Pointer
3C	HECI2_INTR	Interrupt Information
3E	HECI2_MGNT	Minimum Grant
3F	HECI2_MLAT	Maximum Latency
40	HECI2_HFS	Host Firmware Status
48	HECI2_GS_SHDW1	General Status Shadow 1
4C	HECI2_H_GS1	Host General Status
50	HECI2_PID	PCI Power Management Capability ID
52	HECI2_PC	PCI Power Management Capabilities
54	HECI2_PMCS	PCI Power Management Control and Status
60	HECI2_GS_SHDW2	General Status Shadow 2
64	HECI2_GS_SHDW3	General Status Shadow 3
68	HECI2_GS_SHDW4	General Status Shadow 4
6C	HECI2_GS_SHDW5	General Status Shadow 5
70	HECI2_H_GS2	Host General Status 2
74	HECI2_H_GS3	Host General Status 3
8C	HECI2_MID	Message Signaled Interrupt Identifiers
8E	HECI2_MC	Message Signaled Interrupt Message Control
90	HECI2_MA	Message Signaled Interrupt Message Address
94	HECI2_MUA	Message Signaled Interrupt Upper Address
98	HECI2_MD	Message Signaled Interrupt Message Data
A0	HECI2_HIDM	HECI Interrupt Delivery Mode
F8	HECI2_MANID	Manufacturer's ID

36.3.2.2 Memory-Mapped Registers

Table 36-5. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
HECI2_MMIO_MBAR (HI,LO)	0	HECI2_H_CB_WW	Host CB Write Window
HECI2_MMIO_MBAR (HI,LO)	4	HECI2_H_CSR	Host Control and Status Register
HECI2_MMIO_MBAR (HI,LO)	8	HECI2_CSE_CB_RW	CSE Circular Buffer Read Window
HECI2_MMIO_MBAR (HI,LO)	C	HECI2_CSE_CSR_HA	CSE Control and Status Register Host Access
HECI2_MMIO_MBAR (HI,LO)	800	HECI2_D0I3C	D0i3 Control

36.3.2.3 I/O-Mapped Registers

This device has no I/O-mapped registers.

36.3.2.4 Sideband Registers

This device has no Sideband Registers.

36.3.3 Host Root Space - Intel® ME IDER

36.3.3.1 PCI Configuration and Capabilities

Table 36-6. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D24:F2 (hex)	Register Short Name	Description
0	IDE_HOST_DID_VID	Device ID and Vendor ID
4	IDE_HOST_STS_CMD	Status and Command
8	IDE_HOST_CC_RID	Class Code and Revision ID
C	IDE_HOST_BIST_HTYPE_LT_CLS	BIST, Header Type, Latency Timer, and Cache Line Size
10	IDE_HOST_PCMDIOBAR	IDE Primary Command Block IO BAR
14	IDE_HOST_PCTLIOBAR	IDE Primary Control Block IO BAR
18	IDE_HOST_SCMDIOBAR	IDE Secondary Command Block IO BAR
1C	IDE_HOST_SCTLIOBAR	IDE Secondary Control Block IO BAR
20	IDE_HOST_BMIOBAR	IDE Bus Master Block IO BAR
28	IDE_HOST_CCP	Cardbus CIS Pointer
2C	IDE_HOST_SID_SVID	Subsystem ID and Subsystem Vendor ID
30	IDE_HOST_XRBAR	Expansion ROM Base Address
34	IDE_HOST_CAPP	Capabilities List Pointer
3C	IDE_HOST_MAXL_MING_INTP_INTL	Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line
40	IDE_HOST_MSIMC_MSINP_MSICID	MSI Message Control, Next Pointer and Capability ID
44	IDE_HOST_MSIMA	MSI Message Address
48	IDE_HOST_MSIMUA	MSI Message Upper Address
4C	IDE_HOST_MSIMD	MSI Message Data
50	IDE_HOST_PMCAP_PMNP_PMCID	Power Management Capabilities, Next Pointer and Capability ID
54	IDE_HOST_PMD_PMCSRBSE_PMCSR	Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status
F8	IDE_HOST_PSI	Process Stepping Information

36.3.3.2 Memory-Mapped Registers

This device has no Memory-Mapped registers.

36.3.3.3 I/O-Mapped Registers

Table 36-7. Relocatable I/O-Mapped Registers (Sheet 1 of 2)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name	Note
IDE_HOST_PCMDIOBAR	0	IDEDATA	IDE Data Register	
IDE_HOST_PCMDIOBAR	1	IDEFR	IDE Features Register	Write
IDE_HOST_PCMDIOBAR	1	IDEERD0	IDE Error Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	1	IDEERD1	IDE Error Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	2	IDESCIR	IDE Sector Count In Register	Write
IDE_HOST_PCMDIOBAR	2	IDESCOR0	IDE Sector Count Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	2	IDESCOR1	IDE Sector Count Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	3	IDESNIR	IDE Sector Number In Register	Write
IDE_HOST_PCMDIOBAR	3	IDESNOR0	IDE Sector Number Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	3	IDESNOR1	IDE Sector Number Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	4	IDECLIR	IDE Cylinder Low In Register	Write
IDE_HOST_PCMDIOBAR	4	IDCLOR0	IDE Cylinder Low Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	4	IDCLOR1	IDE Cylinder Low Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	5	IDECHIR	IDE Cylinder High In Register	Write
IDE_HOST_PCMDIOBAR	5	IDCHOR0	IDE Cylinder High Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	5	IDCHOR1	IDE Cylinder High Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	6	IDEDHIR	IDE Drive/Head In Register	Write
IDE_HOST_PCMDIOBAR	6	IDDHOR0	IDE Drive/Head Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	6	IDDHOR1	IDE Drive/Head Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	7	IDECR	IDE Command Register	Write
IDE_HOST_PCMDIOBAR	7	IDESR0	IDE Status Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	7	IDESR1	IDE Status Register DEV1	Read and Dev = 1
IDE_HOST_PCTLIOBAR	2	IDDCR	IDE Device Control Register	Write
IDE_HOST_PCTLIOBAR	2	IDASR	IDE Alternate Status Register	Read
IDE_HOST_SCMDIOBAR	-	-	Not in SRDL files	
IDE_HOST_SCTLIOBAR	-	-	Not in SRDL files	
IDE_HOST_BMIOBAR	0	IDEPBMCR	IDE Primary Bus Master Command Register	
IDE_HOST_BMIOBAR	1	IDEPBMDS0R	IDE Primary Bus Master Device Specific 0 Register	
IDE_HOST_BMIOBAR	2	IDEPBMSR	IDE Primary Bus Master Status Register	
IDE_HOST_BMIOBAR	3	IDEPBMDS1R	IDE Primary Bus Master Device Specific 1 Register	
IDE_HOST_BMIOBAR	4	IDEPBMDTPR0	IDE Primary Bus Master Descriptor Table Pointer Register Byte 0	
IDE_HOST_BMIOBAR	5	IDEPBMDTPR1	IDE Primary Bus Master Descriptor Table Pointer Register Byte 1	
IDE_HOST_BMIOBAR	6	IDEPBMDTPR2	IDE Primary Bus Master Descriptor Table Pointer Register Byte 2	
IDE_HOST_BMIOBAR	7	IDEPBMDTPR3	IDE Primary Bus Master Descriptor Table Pointer Register Byte 3	

Table 36-7. Relocatable I/O-Mapped Registers (Sheet 2 of 2)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name	Note
IDE_HOST_BMIOBAR	8	IDESBMCR	IDE Secondary Bus Master Command Register	
IDE_HOST_BMIOBAR	9	IDESBMDS0R	IDE Secondary Bus Master Device Specific 0 Register	
IDE_HOST_BMIOBAR	A	IDESBMSR	IDE Secondary Bus Master Status Register	
IDE_HOST_BMIOBAR	B	IDESBMDS1R	IDE Secondary Bus Master Device Specific 1 Register	
IDE_HOST_BMIOBAR	C	IDESBMDTPR0	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0	
IDE_HOST_BMIOBAR	D	IDESBMDTPR1	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1	
IDE_HOST_BMIOBAR	E	IDESBMDTPR2	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2	
IDE_HOST_BMIOBAR	F	IDESBMDTPR3	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3	

36.3.3.4 Sideband Registers

This device has no Sideband Registers.

36.3.4 Host Root Space - Intel® ME HECI3

36.3.4.1 PCI Configuration and Capabilities

Table 36-8. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D24:F4 (hex)	Register Short Name	Description
0	HECI3_ID	Identifiers
4	HECI3_CMD	Command
6	HECI3_STS	Status
8	HECI3_RID_CC	Revision ID and Class Code
C	HECI3_CLS	Cache Line Size
D	HECI3_MLT	Master Latency Timer
E	HECI3_HTYPE	Header Type
F	HECI3_BIST	Built In Self-Test
10	HECI3_MMIO_MBAR_LO	HECI MMIO Base Address Low
14	HECI3_MMIO_MBAR_HI	HECI MMIO Base Address High
2C	HECI3_SS	Sub System Identifiers
34	HECI3_CAP	Capabilities Pointer
3C	HECI3_INTR	Interrupt Information
3E	HECI3_MGNT	Minimum Grant
3F	HECI3_MLAT	Maximum Latency
40	HECI3_HFS	Host Firmware Status
48	HECI3_GS_SHDW1	General Status Shadow 1
4C	HECI3_H_GS1	Host General Status
50	HECI3_PID	PCI Power Management Capability ID
52	HECI3_PC	PCI Power Management Capabilities
54	HECI3_PMCS	PCI Power Management Control and Status
60	HECI3_GS_SHDW2	General Status Shadow 2
64	HECI3_GS_SHDW3	General Status Shadow 3
68	HECI3_GS_SHDW4	General Status Shadow 4
6C	HECI3_GS_SHDW5	General Status Shadow 5
70	HECI3_H_GS2	Host General Status 2
74	HECI3_H_GS3	Host General Status 3
8C	HECI3_MID	Message Signaled Interrupt Identifiers
8E	HECI3_MC	Message Signaled Interrupt Message Control
90	HECI3_MA	Message Signaled Interrupt Message Address
94	HECI3_MUA	Message Signaled Interrupt Upper Address
98	HECI3_MD	Message Signaled Interrupt Message Data
A0	HECI3_HIDM	HECI Interrupt Delivery Mode
F8	HECI3_MANID	Manufacturer's ID

36.3.4.2 Memory-Mapped Registers

Table 36-9. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
HECI3_MMIO_MBAR (HI,LO)	0	HECI3_H_CB_WW	Host CB Write Window
HECI3_MMIO_MBAR (HI,LO)	4	HECI3_H_CSR	Host Control and Status Register
HECI3_MMIO_MBAR (HI,LO)	8	HECI3_CSE_CB_RW	CSE Circular Buffer Read Window
HECI3_MMIO_MBAR (HI,LO)	C	HECI3_CSE_CSR_HA	CSE Control and Status Register Host Access
HECI3_MMIO_MBAR (HI,LO)	800	HECI3_D0I3C	D0i3 Control

36.3.4.3 I/O-Mapped Registers

This device has no I/O-mapped registers.

36.3.4.4 Sideband Registers

This device has no Sideband Registers.

36.3.5 Host Root Space - Intel® ME KT

36.3.5.1 PCI Configuration and Capabilities

Table 36-10. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D24:F3 (hex)	Register Short Name	Description
0	KT_HOST_DID_VID	Device ID and Vendor ID
4	KT_HOST_STS_CMD	Status and Command
8	KT_HOST_CC_RID	Class Code and Revision ID
C	KT_HOST_BIST_HTYPE_LT_CLS	BIST, Header Type, Latency Timer, and Cache Line Size
10	KT_HOST_IOBAR	KT IO BAR
14	KT_HOST_MEMBAR	KT Memory BAR
28	KT_HOST_CCP	Cardbus CIS Pointer
2C	KT_HOST_SID_SVID	Subsystem ID and Subsystem Vendor ID
30	KT_HOST_XRBAR	Expansion ROM Base Address
34	KT_HOST_CAPP	Capabilities List Pointer
3C	KT_HOST_MAXL_MING_INTP_INTL	Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line
40	KT_HOST_MSIMC_MSINP_MSICID	MSI Message Control, Next Pointer and Capability ID
44	KT_HOST_MSIMA	MSI Message Address
48	KT_HOST_MSIMUA	MSI Message Upper Address
4C	KT_HOST_MSIMD	MSI Message Data
50	KT_HOST_PMCAP_PMNP_PMCID	Power Management Capabilities, Next Pointer and Capability ID
54	KT_HOST_PMD_PMCSRBSE_PMCSR	Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status
F8	KT_HOST_PSI	Process Stepping Information

36.3.5.2 Memory-Mapped Registers

Table 36-11. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
KT_HOST_MEMBAR	0	MEM_KTRBR	KT Receive Buffer Register
KT_HOST_MEMBAR	0	MEM_KTTHR	KT Transmitter Holding Register
KT_HOST_MEMBAR	0	MEM_KTDLLR	KT Divisor Latch LSB Register
KT_HOST_MEMBAR	1	MEM_KTIER	KT Interrupt Enable register
KT_HOST_MEMBAR	1	MEM_KTDLMR	KT Divisor Latch MSB Register
KT_HOST_MEMBAR	2	MEM_KTIIR	KT Interrupt Identification Register
KT_HOST_MEMBAR	2	MEM_KTFCR	KT FIFO Control register
KT_HOST_MEMBAR	3	MEM_KTLCR	KT Line Control register
KT_HOST_MEMBAR	4	MEM_KTMCR	KT Modem Control register
KT_HOST_MEMBAR	5	MEM_KTLSR	KT Line Status register
KT_HOST_MEMBAR	6	MEM_KTMSR	KT Modem Status register
KT_HOST_MEMBAR	7	MEM_KTSCR	KT Scratch register

36.3.5.3 I/O-Mapped Registers

Table 36-12. Relocatable I/O-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
KT_HOST_IOBAR	0	IO_KTRBR	KT Receive Buffer Register
KT_HOST_IOBAR	0	IO_KTTHR	KT Transmitter Holding Register
KT_HOST_IOBAR	0	IO_KTDLLR	KT Divisor Latch LSB Register
KT_HOST_IOBAR	1	IO_KTIER	KT Interrupt Enable register
KT_HOST_IOBAR	1	IO_KTDLMR	KT Divisor Latch MSB Register
KT_HOST_IOBAR	2	IO_KTIIR	KT Interrupt Identification Register
KT_HOST_IOBAR	2	IO_KTFCR	KT FIFO Control register
KT_HOST_IOBAR	3	IO_KTLCR	KT Line Control register
KT_HOST_IOBAR	4	IO_KTMCR	KT Modem Control register
KT_HOST_IOBAR	5	IO_KTLSR	KT Line Status register
KT_HOST_IOBAR	6	IO_KTMSR	KT Modem Status register
KT_HOST_IOBAR	7	IO_KTSCR	KT Scratch register

36.3.5.4 Sideband Registers

This device has no Sideband Registers.

§ §

37 Innovation Engine

The Innovation Engine (IE) is an optional, complete, embedded engine intended to enable SoC customers to provide their own custom system management. This chapter provides a brief overview of the IE. It is reserved for system-builder code, not for Intel firmware since Intel supplies IE hardware only. IE activation is not required for normal system operation.

Note: Intel recommends that customers perform the IE manufacturing lock step described, even if not using the Innovation Engine, to eliminate any in field security risk.

IE is a completely optional feature, and is disabled by default in the silicon. It can be enabled by system builders and OEMs to run signed firmware created by the system builder or a third party software vendor. IE is not like the Intel® Management Engine (Intel® ME) where Intel provides the HW plus a complete FW solution. Intel only provides IE hardware (along with collateral and tools enabling). If the IE is configured to be enabled, the IE ROM brings up the system in real mode and then hands off to the system builder's firmware to continue.

To use IE, the OEM enables the IE in Soft Straps, in the SPI descriptor region (using the Flash Image Tool).

Customers should be resourced and able to develop their own firmware for the IE, or work with a third party vendor to develop IE firmware solutions.

Note: If the OEM has enabled IE Verified Boot, then the IE will always be started, and the IE Soft Strap Enable/Disable is ignored.

Figure 37-1. What is Covered in This Chapter



The signal descriptions are shown in Table 37-1, "Signal Names and Descriptions." For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Section 39.1, "Directory of Signal Names and Pin Names."

The Direction/Type column of Table 37-1, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 37-1. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
UART_IE_RXD	I		UART_IE Receive Data: Active-high input. See Table 18-2, "Signal Names and Descriptions" on page 566.
UART_IE_TXD	O		UART_IE Transmit Data: Active-high output. See Table 18-2, "Signal Names and Descriptions" on page 566.
UART_IE_CTS	I		UART_IE Clear to Send: Active-high input. See Table 18-2, "Signal Names and Descriptions" on page 566.
UART_IE_RTS	O		UART_IE Request to Send: Active-high output. See Table 18-2, "Signal Names and Descriptions" on page 566.
SMB_IE_SMT0_CLK	I,O-OD	Yes	**SMBus Clock:** (SMBCLK) for System Management Transport 0 of the IE.
SMB_IE_SMT0_DATA	I,O-OD	Yes	**SMBus Data:** (SMBDAT) for System Management Transport 0 of the IE.
SMB_IE_SMT0_ALRT_N	I,O-OD	Yes	**SMBus Alert:** (SMBALERT#) for System Management Transport 0 of the IE.
SMB_IE_SMT1_CLK	I,O-OD	Yes	**SMBus Clock:** (SMBCLK) for System Management Transport 1 of the IE.
SMB_IE_SMT1_DATA	I,O-OD	Yes	**SMBus Data:** (SMBDAT) for System Management Transport 1 of the IE.
SMB_IE_SMT2_CLK	I,O-OD	Yes	**SMBus Clock:** (SMBCLK) for System Management Transport 2 of the IE.
SMB_IE_SMT2_DATA	I,O-OD	Yes	**SMBus Data:** (SMBDAT) for System Management Transport 2 of the IE.
FAN_PWM[3:0]	O-OD	Yes	**Fan Pulse-Width Modulation (PWM):** These open-drain output signals produce a PWM duty cycle that is used for fan-speed control. When controlling a 3-wire-controlled fan, this signal controls a power transistor that, in turn, controls power to the fan. When controlling a 4-wire-controlled fan, this signal is connected to the "Control" signal on the fan. The polarity of this signal is programmable. The fan controller is part of the IE.
FAN_TACH[3:0]	I	Yes	**Fan Tachometer:** This pulsed input signal is used by the IE to measure fan speed. This signal is connected to the "Sense" signal on the fan. This signal is driven by the fan in an open-drain configuration.

37.1 Feature Summary

- IE is an embedded sub-system in the SoC:
  - Includes a small, 32-bit IA core.
- Reserved for system-builder's code, not for Intel firmware:
  - Intel supplies IE hardware only.
  - IE code is cryptographically signed by the system builder using a private key.
  - IE code that doesn't authenticate with the system builder public key will not load.
- IE activation is not required for normal system operation:
  - Completely optional feature.
- Power:
  - When in S0, the SoC can be configured by BIOS to completely shut down the IE power.
  - The SoC has a power-disable policy that can be set to shut down the IE and all its contents are lost.

Figure 37-2. Intel Atom® Processor C3000 Product Family Embedded Sub-System



37.2 Sample IE Usages

- Lightweight Management/BMC-less platforms. IE takes role of BMC and can do lightweight BMC functions including log SEL events, serial over LAN, basic sensor monitoring. Can also do an IPMI 2.0 compliant implementation.
- BMC or BIOS assist – Enterprise segment likes video redirection and higher BMC capabilities. BMC can respond to network packets and present a nice GUI over network, offload tight loop code to IE
- Enhancements to Intel® ME FW – to optimize or customize for specific usages.
- IE Verified Boot – IE code signed by the system builder is authenticated. The system builder code then authenticates the BIOS image.

Figure 37-3. Sample IE Usages



37.3 Architectural Overview

The Innovation Engine (IE) is an integrated SoC subsystem that is based on a custom Intel® Architecture Processor. This subsystem has dedicated general purpose DMA and Crypto accelerator engines. The PCI Express Message Transport subsystem is comprised of I/O devices, based on standard PCI architecture. This subsystem is connected to the rest of the system via internal fabric, if required. This subsystem maintains its own system space and exposes some of its interface to the Host space, as described below.

The IE ROM holds boot code and is responsible for initialization of the IE subsystem. The subsystem authenticates the OEM IE image and initiates the start up process. SPI Flash is used to store OEM IE images.

IE Memory Subsystem – (SRAM and ROM) – completely independent from Host and Intel® ME.

- IE SRAM – 1.4MB available for IE to run FW.
- IE ROM – 128KB of dedicated ROM embedded in silicon (hard-coded, read-only).

The shared SPI Flash – dedicated IE region for customer FW storage (4-8MB). Regions are defined for all masters accessing the shared SPI flash. Those regions can be as big as the overall SPI flash size (so full flexibility). But in most cases, would be a 4-8MB range allocated for IE in typical platforms.

Depending on what application is running, SPI flash could be used for storing additional data, or holding a small image that could be exposed through IE. We also support paging from SPI flash. Code and data can be bigger than on-die SRAM and can page out of SPI flash. This paging would be managed as a kernel function (have to support page fault handling in kernel), plus DMA driver to load a 4K page from SPI flash into SRAM.

The devices exposed by the IE subsystem to the Host Root Space are:

- HECI (1, 2 and 3) – These functions define the mechanism for host software and IE firmware to communicate. This device exposes three PCI functions to the host during PCI bus enumeration. The message format is OEM dependent and communication between host and IE subsystem takes place via circular buffers and control/status registers. This function supports host MSI, SMI and SCI# interrupt generation mechanisms.
- PTIO – This exposes two PCI functions to the host.
  - Keyboard Text (KT) – The Innovation Engine provides a Keyboard Transfer (KT) interface to redirect virtual keyboard input to the host. The interface is visible to the Innovation Engine as a PCI device.
  - IDE-Redirect (IDER) - The IE provides an IDE-redirection mechanism that performs the basic functions. It provides the capability to boot from a remote IDE drive.

Some of Host Root Space devices are also part of IE root space. A partial list of devices parts of the IE root space are:

- HECI devices/clients
  - HECI specification uses term “HECI client” to refer to software endpoints that send and receive messages via HECI.
  - Examples of Host HECI clients are System BIOS module, OS Services & Applications that interface with HECI.
  - FW HECI Clients are IE FW modules that use HECI to communicate with Host Clients.
  - Each endpoint supports many connections established by the clients at the same time as each client is identified by a unique address assigned while establishing the connection. Both host client address and FW client address are contained by the HECI message header to enable dispatch of the message. HECI Protocol doesn't enforce any restrictions on the format of the message data between HECI Clients.

Note: IE HSUART and IE SMT are exclusively IE Root Space devices. They are not discovered or addressable in Host Root Space.

- HSUART - UART primary fabric interface only supports single channel and 32-bit data/addressing. The register space is not mapped into the prefetchable address space, and the primary target interface does not support more than one DWord access per I/O fabric request.

  In the downstream direction, a register access of more than one DWord could result in undefined behavior and will be treated as an unsupported request. Any unsupported downstream Posted request will be dropped and unsupported, Non-Posted request will be completed with the appropriate unsuccessful completion status. The first 2 DWs of each UART CSR are IO as well as memory mapped. The UART I/O fabric is a PCI device and supports configuration read and write requests at the primary target.

  In the upstream direction, the primary interface makes 32-bit memory read and write requests for DMA transfers. UART primary fabric also supports single MSI vector per function which will be sent as a Posted Write request in upstream direction.

  UART only supports 64 bytes I/O fabric Max Payload Size and Max Read Request Size.

  All upstream memory requests will be split at 64byte block boundary. As no read request will cross the 64bytes RCB, the UART I/O fabric accepts only single completions for each upstream memory read request.

- SMBus Message Transport (SMT): There are three SMBus devices in the IE root space. The SMT provides a mechanism to the IE for sending OOB manageability messages to managed devices or management controllers over SMBus.

37.4 Inter-Processor Communication (IPC)

The IE communicates with the Intel® Management Engine using an IPC Interface over the sideband fabric. The IPC Interface is intended for transferring small messages directly between cores. IPC messages from the IE core are routed to the sideband fabric.

37.4.1 IE Root Space Devices

In addition to the devices that are visible to both the Host address space and the IE root space, the following devices are only visible internally to the IE root space.

37.4.1.1 PECI

In-band PECI is restricted to Intel® ME. PECI over SMBus is also supported through an external wire.

37.4.1.2 SMBus Message Transport (SMT)

The SoC provides a number of virtual SMBus interfaces that are visible to the IE Root Space as PCI devices. Externally, these interfaces conform to the I2C specification as physical SMBus devices. The configuration of the SMT interfaces is determined at manufacturing time, and can be configured to the Intel® Management Engine (Intel® ME), or the Innovation Engine. The requirements vary depending on which Intel® ME features are desired by the system builder.

Bus speed can be configured by Soft Straps to run I2C Fast-mode Plus (Fm+) timings (up to 1MHz) if all devices on the segment support the higher speed.

37.4.1.3 UART

The Innovation Engine supports a serial UART for communication between the Innovation Engine and an external interface, such as an OEM Chassis Management Module. Additionally, this interface can be used for debug purposes.

37.5 Register Map

The IE is accessible through the Host Root Space as shown in Figure 37-4, "Register Map."

Figure 37-4. Register Map



37.5.1 Host Root Space - IE HECI1

37.5.1.1 PCI Configuration and Capabilities

Table 37-2. Configuration and Capabilities Register Map (Sheet 1 of 2)

Offset from Configuration Space of B0:D27:F0 (hex)	Register Short Name	Description
0	HECI1_ID	Identifiers
4	HECI1_CMD	Command
6	HECI1_STS	Status
8	HECI1_RID_CC	Revision ID and Class Code
C	HECI1_CLS	Cache Line Size
D	HECI1_MLT	Master Latency Timer
E	HECI1_HTYPE	Header Type
F	HECI1_BIST	Built In Self-Test
10	HECI1_MMIO_MBAR_LO	HECI MMIO Base Address Low
14	HECI1_MMIO_MBAR_HI	HECI MMIO Base Address High
2C	HECI1_SS	Sub System Identifiers
34	HECI1_CAP	Capabilities Pointer
3C	HECI1_INTR	Interrupt Information
3E	HECI1_MGNT	Minimum Grant
3F	HECI1_MLAT	Maximum Latency
40	HECI1_HFS	Host Firmware Status
44	HECI1_MISC_SHDW	Miscellaneous Shadow
48	HECI1_GS_SHDW1	General Status Shadow 1
4C	HECI1_H_GS1	Host General Status
50	HECI1_PID	PCI Power Management Capability ID
52	HECI1_PC	PCI Power Management Capabilities
54	HECI1_PMCS	PCI Power Management Control and Status
60	HECI1_GS_SHDW2	General Status Shadow 2
64	HECI1_GS_SHDW3	General Status Shadow 3
68	HECI1_GS_SHDW4	General Status Shadow 4
6C	HECI1_GS_SHDW5	General Status Shadow 5
70	HECI1_H_GS2	Host General Status 2
74	HECI1_H_GS3	Host General Status 3
8C	HECI1_MID	Message Signaled Interrupt Identifiers
8E	HECI1_MC	Message Signaled Interrupt Message Control
90	HECI1_MA	Message Signaled Interrupt Message Address
94	HECI1_MUA	Message Signaled Interrupt Upper Address
98	HECI1_MD	Message Signaled Interrupt Message Data
A0	HECI1_HIDM	HECI Interrupt Delivery Mode

Table 37-2. Configuration and Capabilities Register Map (Sheet 2 of 2)

Offset from Configuration Space of B0:D27:F0 (hex)	Register Short Name	Description
BC	HECI1_HERS	Host Extend Register Status
C0	HECI1_HER1	Host Extend Register DW1.
C4	HECI1_HER2	Host Extend Register DW2.
C8	HECI1_HER3	Host Extend Register DW3.
CC	HECI1_HER4	Host Extend Register DW4.
D0	HECI1_HER5	Host Extend Register DW5.
D4	HECI1_HER6	Host Extend Register DW6.
D8	HECI1_HER7	Host Extend Register DW7.
DC	HECI1_HER8	Host Extend Register DW8.
F8	HECI1_MANID	Manufacturer's ID

37.5.1.2 Memory-Mapped Registers

Table 37-3. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
HECI1_MMIO_MBAR (HI,LO)	0	HECI1_H_CB_WW	Host CB Write Window
HECI1_MMIO_MBAR (HI,LO)	4	HECI1_H_CSR	Host Control and Status Register
HECI1_MMIO_MBAR (HI,LO)	8	HECI1_CSE_CB_RW	CSE Circular Buffer Read Window
HECI1_MMIO_MBAR (HI,LO)	C	HECI1_CSE_CSR_HA	CSE Control and Status Register Host Access
HECI1_MMIO_MBAR (HI,LO)	800	HECI1_D0I3C	D0i3 Control

37.5.1.3 I/O-Mapped Registers

This device has no I/O-mapped registers.

37.5.1.4 Sideband Registers

This device has no Sideband Registers.

37.5.2 Host Root Space - IE HECI2

37.5.2.1 PCI Configuration and Capabilities

Table 37-4. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D27:F1 (hex)	Register Short Name	Description
0	HECI2_ID	Identifiers
4	HECI2_CMD	Command
6	HECI2_STS	Status
8	HECI2_RID_CC	Revision ID and Class Code
C	HECI2_CLS	Cache Line Size
D	HECI2_MLT	Master Latency Timer
E	HECI2_HTYPE	Header Type
F	HECI2_BIST	Built In Self-Test
10	HECI2_MMIO_MBAR_LO	HECI MMIO Base Address Low
14	HECI2_MMIO_MBAR_HI	HECI MMIO Base Address High
2C	HECI2_SS	Sub System Identifiers
34	HECI2_CAP	Capabilities Pointer
3C	HECI2_INTR	Interrupt Information
3E	HECI2_MGNT	Minimum Grant
3F	HECI2_MLAT	Maximum Latency
40	HECI2_HFS	Host Firmware Status
48	HECI2_GS_SHDW1	General Status Shadow 1
4C	HECI2_H_GS1	Host General Status
50	HECI2_PID	PCI Power Management Capability ID
52	HECI2_PC	PCI Power Management Capabilities
54	HECI2_PMCS	PCI Power Management Control and Status
60	HECI2_GS_SHDW2	General Status Shadow 2
64	HECI2_GS_SHDW3	General Status Shadow 3
68	HECI2_GS_SHDW4	General Status Shadow 4
6C	HECI2_GS_SHDW5	General Status Shadow 5
70	HECI2_H_GS2	Host General Status 2
74	HECI2_H_GS3	Host General Status 3
8C	HECI2_MID	Message Signaled Interrupt Identifiers
8E	HECI2_MC	Message Signaled Interrupt Message Control
90	HECI2_MA	Message Signaled Interrupt Message Address
94	HECI2_MUA	Message Signaled Interrupt Upper Address
98	HECI2_MD	Message Signaled Interrupt Message Data
A0	HECI2_HIDM	HECI Interrupt Delivery Mode
F8	HECI2_MANID	Manufacturer's ID

37.5.2.2 Memory-Mapped Registers

Table 37-5. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
HECI2_MMIO_MBAR (HI,LO)	0	HECI2_H_CB_WW	Host CB Write Window
HECI2_MMIO_MBAR (HI,LO)	4	HECI2_H_CSR	Host Control and Status Register
HECI2_MMIO_MBAR (HI,LO)	8	HECI2_CSE_CB_RW	CSE Circular Buffer Read Window
HECI2_MMIO_MBAR (HI,LO)	C	HECI2_CSE_CSR_HA	CSE Control and Status Register Host Access
HECI2_MMIO_MBAR (HI,LO)	800	HECI2_D0I3C	D0i3 Control

37.5.2.3 I/O-Mapped Registers

This device has no I/O-mapped registers.

37.5.2.4 Sideband Registers

This device has no Sideband Registers.

37.5.3 Host Root Space - IE IDER

37.5.3.1 PCI Configuration and Capabilities

Table 37-6. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D27:F2 (hex)	Register Short Name	Description
0	IDE_HOST_DID_VID	Device ID and Vendor ID
4	IDE_HOST_STS_CMD	Status and Command
8	IDE_HOST_CC_RID	Class Code and Revision ID
C	IDE_HOST_BIST_HTYPE_LT_CLS	BIST, Header Type, Latency Timer, and Cache Line Size
10	IDE_HOST_PCMDIOBAR	IDE Primary Command Block IO BAR
14	IDE_HOST_PCTLIOBAR	IDE Primary Control Block IO BAR
18	IDE_HOST_SCMDIOBAR	IDE Secondary Command Block IO BAR
1C	IDE_HOST_SCTLIOBAR	IDE Secondary Control Block IO BAR
20	IDE_HOST_BMIOBAR	IDE Bus Master Block IO BAR
28	IDE_HOST_CCP	Cardbus CIS Pointer
2C	IDE_HOST_SID_SVID	Subsystem ID and Subsystem Vendor ID
30	IDE_HOST_XRBAR	Expansion ROM Base Address
34	IDE_HOST_CAPP	Capabilities List Pointer
3C	IDE_HOST_MAXL_MING_INTP_INTL	Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line
40	IDE_HOST_MSIMC_MSINP_MSICID	MSI Message Control, Next Pointer and Capability ID
44	IDE_HOST_MSIMA	MSI Message Address
48	IDE_HOST_MSIMUA	MSI Message Upper Address
4C	IDE_HOST_MSIMD	MSI Message Data
50	IDE_HOST_PMCAP_PMNP_PMCID	Power Management Capabilities, Next Pointer and Capability ID
54	IDE_HOST_PMD_PMCSRBSE_PMCSR	Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status
F8	IDE_HOST_PSI	Process Stepping Information

37.5.3.2 Memory-Mapped Registers

This device has no Memory-Mapped registers.

37.5.3.3 I/O-Mapped Registers

Table 37-7. Relocatable I/O-Mapped Registers (Sheet 1 of 2)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name	Note
IDE_HOST_PCMDIOBAR	0	IDEDATA	IDE Data Register	
IDE_HOST_PCMDIOBAR	1	IDEFR	IDE Features Register	Write
IDE_HOST_PCMDIOBAR	1	IDEERD0	IDE Error Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	1	IDEERD1	IDE Error Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	2	IDESCIR	IDE Sector Count In Register	Write
IDE_HOST_PCMDIOBAR	2	IDESCOR0	IDE Sector Count Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	2	IDESCOR1	IDE Sector Count Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	3	IDESNIR	IDE Sector Number In Register	Write
IDE_HOST_PCMDIOBAR	3	IDESNOR0	IDE Sector Number Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	3	IDESNOR1	IDE Sector Number Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	4	IDECLIR	IDE Cylinder Low In Register	Write
IDE_HOST_PCMDIOBAR	4	IDCLOR0	IDE Cylinder Low Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	4	IDCLOR1	IDE Cylinder Low Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	5	IDECHIR	IDE Cylinder High In Register	Write
IDE_HOST_PCMDIOBAR	5	IDCHOR0	IDE Cylinder High Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	5	IDCHOR1	IDE Cylinder High Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	6	IDEDHIR	IDE Drive/Head In Register	Write
IDE_HOST_PCMDIOBAR	6	IDDHOR0	IDE Drive/Head Out Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	6	IDDHOR1	IDE Drive/Head Out Register DEV1	Read and Dev = 1
IDE_HOST_PCMDIOBAR	7	IDECR	IDE Command Register	Write
IDE_HOST_PCMDIOBAR	7	IDESR0	IDE Status Register DEV0	Read and Dev = 0
IDE_HOST_PCMDIOBAR	7	IDESR1	IDE Status Register DEV1	Read and Dev = 1
IDE_HOST_PCTLIOBAR	2	IDDCR	IDE Device Control Register	Write
IDE_HOST_PCTLIOBAR	2	IDASR	IDE Alternate Status Register	Read
IDE_HOST_BMIOBAR	0	IDEPBMCR	IDE Primary Bus Master Command Register	
IDE_HOST_BMIOBAR	1	IDEPBMDS0R	IDE Primary Bus Master Device Specific 0 Register	
IDE_HOST_BMIOBAR	2	IDEPBMSR	IDE Primary Bus Master Status Register	
IDE_HOST_BMIOBAR	3	IDEPBMDS1R	IDE Primary Bus Master Device Specific 1 Register	
IDE_HOST_BMIOBAR	4	IDEPBMDTPR0	IDE Primary Bus Master Descriptor Table Pointer Register Byte 0	
IDE_HOST_BMIOBAR	5	IDEPBMDTPR1	IDE Primary Bus Master Descriptor Table Pointer Register Byte 1	
IDE_HOST_BMIOBAR	6	IDEPBMDTPR2	IDE Primary Bus Master Descriptor Table Pointer Register Byte 2	

Table 37-7. Relocatable I/O-Mapped Registers (Sheet 2 of 2)

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name	Note
IDE_HOST_BMIOBAR	7	IDEPBMDTPR3	IDE Primary Bus Master Descriptor Table Pointer Register Byte 3	
IDE_HOST_BMIOBAR	8	IDESBMCR	IDE Secondary Bus Master Command Register	
IDE_HOST_BMIOBAR	9	IDESBMDS0R	IDE Secondary Bus Master Device Specific 0 Register	
IDE_HOST_BMIOBAR	A	IDESBMSR	IDE Secondary Bus Master Status Register	
IDE_HOST_BMIOBAR	B	IDESBMDS1R	IDE Secondary Bus Master Device Specific 1 Register	
IDE_HOST_BMIOBAR	C	IDESBMDTPR0	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0	
IDE_HOST_BMIOBAR	D	IDESBMDTPR1	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1	
IDE_HOST_BMIOBAR	E	IDESBMDTPR2	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2	
IDE_HOST_BMIOBAR	F	IDESBMDTPR3	IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3	

37.5.3.4 Sideband Registers

This device has no Sideband Registers.

37.5.4 Host Root Space - IE HECI3

37.5.4.1 PCI Configuration and Capabilities

Table 37-8. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D27:F4 (hex)	Register Short Name	Description
0	HECI3_ID	Identifiers
4	HECI3_CMD	Command
6	HECI3_STS	Status
8	HECI3_RID_CC	Revision ID and Class Code
C	HECI3_CLS	Cache Line Size
D	HECI3_MLT	Master Latency Timer
E	HECI3_HTYPE	Header Type
F	HECI3_BIST	Built In Self-Test
10	HECI3_MMIO_MBAR_LO	HECI MMIO Base Address Low
14	HECI3_MMIO_MBAR_HI	HECI MMIO Base Address High
2C	HECI3_SS	Sub System Identifiers
34	HECI3_CAP	Capabilities Pointer
3C	HECI3_INTR	Interrupt Information
3E	HECI3_MGNT	Minimum Grant
3F	HECI3_MLAT	Maximum Latency
40	HECI3_HFS	Host Firmware Status
48	HECI3_GS_SHDW1	General Status Shadow 1
4C	HECI3_H_GS1	Host General Status
50	HECI3_PID	PCI Power Management Capability ID
52	HECI3_PC	PCI Power Management Capabilities
54	HECI3_PMCS	PCI Power Management Control and Status
60	HECI3_GS_SHDW2	General Status Shadow 2
64	HECI3_GS_SHDW3	General Status Shadow 3
68	HECI3_GS_SHDW4	General Status Shadow 4
6C	HECI3_GS_SHDW5	General Status Shadow 5
70	HECI3_H_GS2	Host General Status 2
74	HECI3_H_GS3	Host General Status 3
8C	HECI3_MID	Message Signaled Interrupt Identifiers
8E	HECI3_MC	Message Signaled Interrupt Message Control
90	HECI3_MA	Message Signaled Interrupt Message Address
94	HECI3_MUA	Message Signaled Interrupt Upper Address
98	HECI3_MD	Message Signaled Interrupt Message Data
A0	HECI3_HIDM	HECI Interrupt Delivery Mode
F8	HECI3_MANID	Manufacturer's ID

37.5.4.2 Memory-Mapped Registers

Table 37-9. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
HECI3_MMIO_MBAR (HI,LO)	0	HECI3_H_CB_WW	Host CB Write Window
HECI3_MMIO_MBAR (HI,LO)	4	HECI3_H_CSR	Host Control and Status Register
HECI3_MMIO_MBAR (HI,LO)	8	HECI3_CSE_CB_RW	CSE Circular Buffer Read Window
HECI3_MMIO_MBAR (HI,LO)	C	HECI3_CSE_CSR_HA	CSE Control and Status Register Host Access
HECI3_MMIO_MBAR (HI,LO)	800	HECI3_D0I3C	D0i3 Control

37.5.4.3 I/O-Mapped Registers

This device has no I/O-mapped registers.

37.5.4.4 Sideband Registers

This device has no Sideband Registers.

37.5.5 Host Root Space - IE KT

37.5.5.1 PCI Configuration and Capabilities

Table 37-10. Configuration and Capabilities Register Map

Offset from Configuration Space of B0:D27:F3 (hex)	Register Short Name	Description
0	KT_HOST_DID_VID	Device ID and Vendor ID
4	KT_HOST_STS_CMD	Status and Command
8	KT_HOST_CC_RID	Class Code and Revision ID
C	KT_HOST_BIST_HTYPE_LT_CLS	BIST, Header Type, Latency Timer, and Cache Line Size
10	KT_HOST_IOBAR	KT IO BAR
14	KT_HOST_MEMBAR	KT Memory BAR
28	KT_HOST_CCP	Cardbus CIS Pointer
2C	KT_HOST_SID_SVID	Subsystem ID and Subsystem Vendor ID
30	KT_HOST_XRBAR	Expansion ROM Base Address
34	KT_HOST_CAPP	Capabilities List Pointer
3C	KT_HOST_MAXL_MING_INTP_INTL	Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line
40	KT_HOST_MSIMC_MSINP_MSICID	MSI Message Control, Next Pointer and Capability ID
44	KT_HOST_MSIMA	MSI Message Address
48	KT_HOST_MSIMUA	MSI Message Upper Address
4C	KT_HOST_MSIMD	MSI Message Data
50	KT_HOST_PMCAP_PMNP_PMCID	Power Management Capabilities, Next Pointer and Capability ID
54	KT_HOST_PMD_PMCSRBSE_PMCSR	Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status
F8	KT_HOST_PSI	Process Stepping Information

37.5.5.2 Memory-Mapped Registers

Table 37-11. Relocatable Memory-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
KT_HOST_MEMBAR	0	MEM_KTRBR	KT Receive Buffer Register
KT_HOST_MEMBAR	0	MEM_KTTHR	KT Transmitter Holding Register
KT_HOST_MEMBAR	0	MEM_KTDLLR	KT Divisor Latch LSB Register
KT_HOST_MEMBAR	1	MEM_KTIER	KT Interrupt Enable register
KT_HOST_MEMBAR	1	MEM_KTDLMR	KT Divisor Latch MSB Register
KT_HOST_MEMBAR	2	MEM_KTIIR	KT Interrupt Identification Register
KT_HOST_MEMBAR	2	MEM_KTFCR	KT FIFO Control register
KT_HOST_MEMBAR	3	MEM_KTLCR	KT Line Control register
KT_HOST_MEMBAR	4	MEM_KTMCR	KT Modem Control register
KT_HOST_MEMBAR	5	MEM_KTLSR	KT Line Status register
KT_HOST_MEMBAR	6	MEM_KTMSR	KT Modem Status register
KT_HOST_MEMBAR	7	MEM_KTSCR	KT Scratch register

37.5.5.3 I/O-Mapped Registers

Table 37-12. Relocatable I/O-Mapped Registers

Base Address Register (BAR) Short Name	Offset from BAR (hex)	Register Short Name	Register Long Name
KT_HOST_IOBAR	0	IO_KTRBR	KT Receive Buffer Register
KT_HOST_IOBAR	0	IO_KTTHR	KT Transmitter Holding Register
KT_HOST_IOBAR	0	IO_KTDLLR	KT Divisor Latch LSB Register
KT_HOST_IOBAR	1	IO_KTIER	KT Interrupt Enable register
KT_HOST_IOBAR	1	IO_KTDLMR	KT Divisor Latch MSB Register
KT_HOST_IOBAR	2	IO_KTIIR	KT Interrupt Identification Register
KT_HOST_IOBAR	2	IO_KTFCR	KT FIFO Control register
KT_HOST_IOBAR	3	IO_KTLCR	KT Line Control register
KT_HOST_IOBAR	4	IO_KTMCR	KT Modem Control register
KT_HOST_IOBAR	5	IO_KTLSR	KT Line Status register
KT_HOST_IOBAR	6	IO_KTMSR	KT Modem Status register
KT_HOST_IOBAR	7	IO_KTSCR	KT Scratch register

37.5.5.4 Sideband Registers

This device has no Sideband Registers.

§ §

38 JTAG and Debug Ports

This chapter describes the SoC debug mechanisms available to customers. This includes the Intel® Direct Connect Interface (Intel® DCI) and Joint Test Action Group (JTAG) interface.

Figure 38-1. What is Covered in This Chapter



Table 38-1. References

Reference	Revision	Date	Document Title
IEEE Std 1149.1*-2001	-	June 14, 2001	*IEEE Standard Test Access Port and Boundary-Scan Architecture*, 1149.1-2001
IEEE Std 1149.7*-2009	-	Dec. 9, 2009	*IEEE Standard for Reduced-Pin and Enhanced-Functionality Test Access Port and Boundary-Scan Architecture*, 1149.7-2009
USB xHCI Specification	1.1	Dec. 20, 2013	*eXtensible Host Controller Interface for Universal Serial Bus (xHCI) Specification*, Revision 1.1

38.1 Signal Descriptions

The signal descriptions are shown in Table 38-2, "Signal Names and Descriptions." For additional signal information, including whether a signal is assigned to shared-function pin or can be used as a Customer GPIO signals see Chapter 39, "Signal Pin Names and Signal MUXing." The Direction/Type column of Table 38-2, "Signal Names and Descriptions" is interpreted as follows:

- I = Input signal. The SoC has receiver circuit.
- O = Output signal. The SoC has driver circuit.
- O-OD = Open-Drain Output. SoC output circuit uses an open-drain driver.

Table 38-2. Signal Names and Descriptions

Signal Names	Direction	Shared	Description
CTBTRIGINOUT	I,O	Yes	**CTB Trigger:** Signals for triggering an external logic analyzer based on internal SoC events.
CTBTRIGOUT	O	Yes	
CX_PRDY_N	O-OD	Yes	**Debug Port Signals:** For connection to a MIPI-60 header on the board.
CX_PREQ_N	I	Yes	
DFX_PORT[15:0]	O	Yes	
DFX_PORT_CLK[1:0]	O	Yes	
Test Access Port 0 - for Debug Port MIPI-60 Header on Board			
TCK	I	No	**Test Clock:** For debug-capable platform board, an external 51-Ω +/- 5% resistor tied to VSS is required. Otherwise, no external resistor is required.
TDI	I	No	**Test Data Input:** For debug-capable platform board, an external 51-Ω +/- 5% resistor tied to V1P05 is required. Otherwise, no external resistor is required.
TDO	I,O-OD	No	**Test Data Output:** For debug-capable platform board, an external 51-Ω +/- 5% resistor tied to V1P05 is required. Otherwise, no external resistor is required.
TMS	I	No	**Test Mode Select:** For debug-capable platform board, an external 51-Ω +/- 5% resistor tied to V1P05 is required. Otherwise, no external resistor is required.
TRST_N	I	No	**Test Reset:** For debug-capable platform board, an external resistor within the range of 500-Ω to 1kΩ tied to VSS is required. Otherwise, no external resistor is required.

38.2 Feature List

- Intel® Direct Connect Interface (Intel® DCI)
  - Debug Capability (DbC)
  - Intel® DCI-OOB (Out of Band)
- MIPI Parallel Trace Interface (PTI) capability
- IEEE Test Access Port (TAP)
- Intel® Trace Hub (Intel® TH)

38.3 Signals after Reset

- Following Power-up Reset, Warm Reset, and Cold Reset, all of the signals listed in Table 38-2, "Signal Names and Descriptions" are available at the SoC pins except for:
  - CTBTRIGINOUT
  - CTBTRIGOUT

To make these signals available, software must reconfigure these pins. The pin configuration mechanism is explained in Chapter 26, "Customer General-Purpose I/O (GPIO)."

38.4 Intel® Direct Connect Interface (Intel® DCI)

Intel® DCI provides a USB 3.0 path to debug features that can replace the traditional Test Access Port (TAP) pins and GPIO. Intel® DCI is being developed as an industry standard through the Mobile Industry Processor Interface Alliance (MIPI* Alliance) standards group. USB-hosted Intel® DCI provides TAP Access, Trace Extraction and Trace Capture.

Depending on the product SKU, lanes 19:16 are set to be either SATA or USB 3.0. For lane configurations, see Chapter 10, "Flexible I/O Adapter (FIA) Overview" For Intel® DCI to work correctly, the Intel® ME programs the Intel® DCI registers to indicate which lanes are SATA and which are USB 3.0 for the particular SoC product SKU.

Debug Capability (DbC) and Intel® DCI-OOB (Out of Band) are part of Intel® DCI. Any USB 3.0 lane (port) can be used for DbC or Intel® DCI-OOB. Two lanes are the maximum that can be used, only if they are in different modes (one lane for DbC and one lane for Intel® DCI-OOB) and used at different times. Intel® DCI does not support dual-mode (simultaneous) operation.

Whichever USB 3.0 port receives an external DbC request switches into the DbC mode and that is the only USB 3.0 port allowed to be in DbC mode until the port goes out of DbC mode.

38.4.1 Debug Capability (DbC)

The USB Debug Capability is a hosting transport that a debugger can use to control a platform. It is provided by the SoC USB eXtensible Host Controller (xHC). DbC is an optional USB functionality that enables low-level system debug over USB. The xHC Interface (xHCI) debugging capability provides a means of connecting two systems where one system is a Debug Host and the other a Debug Target (System Under Test).

The Host Memory Space range from 0xFED6_0000 to 0xFED6_0FFF is reserved for traffic targeting the SoC xHCI DbC subsystem. The Operating System must be informed that this address range is reserved. No other Memory-Mapped I/O (MMIO) in Host Memory Space must overlap with this address range. DbC is never a memory target. It always reads data from elsewhere and transfers in/out through the SoC USB 3.0 port.

See the section on DbC in the *eXtensible Host Controller Interface for Universal Serial Bus (xHCI), Revision 1.1*.

38.4.2 Intel® DCI-OOB (Out of Band)

Intel® DCI-OOB (Out of Band) is a hosting transport that a debugger can use to control a platform. Intel® DCI-OOB is supported by the SoC but requires a special USB 3.0 to Intel® DCI-OOB adapter. Intel® DCI-OOB gives the SoC customer the ability to do the same debug capabilities as DbC, but without the restriction of running it while the operating system (OS) is running on the target. It can run at any time, even during reset.

Intel® DCI-OOB has lower bandwidth when compared to DbC and only supports two of three main operations. Intel® DCI-OOB supports TAP control and Trace Streaming from Intel® Trace Hub, but it does not support memory extraction from main memory. Only DbC supports memory extraction from main memory.

38.5 Intel® Trace Hub

While Intel® Direct Connect Interface (Intel® DCI) is for closed chassis debug, the Intel® Trace Hub (Intel® TH) is an integrated PCI device for system tracing debug. It is discovered as Bus 0, Device 31 (decimal), Function 7.

The Intel® TH is an integrated trace analyzer and a set of silicon features allowing the user to perform system-level debug. It provides hardware-software co-debug. Intel is enabling third-party debug-software vendors to use the integrated Intel® TH in their products to unify software and hardware visibility and internal tracing capabilities.

An Intel® TH viewer is bundled with the Intel® System Studio product to allow the user one common viewer for hardware and software co-development.

The Intel® TH allows the user to trigger sources and capture the events into system memory (DRAM). The user can retrieve the events stored in memory for viewing with the software compiler debug tool (ISS) or retrieve the events from system memory through a third-party vendor JTAG tool using industry-standard MIPI (STPv2) interface and the Parallel Trace Interface (PTI).

38.6 On-Board Debug Port Connector

The SoC provides debug-related signals that can be accessed by a 60-pin Mobile Industry Processor Interface (MIPI) connector. MIPI calls this the Parallel Trace Interface (PTI).

§ §

Volume 3: Electrical, Mechanical, and Thermal

February 2018
Order Number: 337018-002

39 Signal Pin Names and Signal MUXing

Warning: The information in this chapter is preliminary and is subject to change.

The SoC pin numbers, signal-pin names, and associated signals are listed in Table 39-1, "Signal Pin Name Directory - Sorted by Name" in alphabetical order by signal-pin name. Some pins shown in the table have multiple uses and are shared by multiple signals.

The voltage supply pins and voltage sense pins are in a separate list, Table 39-4, "Voltage Pins Sorted by Platform VR and SoC Voltage Group."

Table 39-6, "Directory of Signal and Voltage Pins - Sorted by Pin Number" lists all of the SoC pins sorted by pin number.

The Transmit and Receive differential interface signals for the lanes of the integrated PCI Express* Root Ports, SATA controller ports, and USB 3.0 ports share up to 20 High-Speed I/O (HSIO) lanes of the SoC. These are shown in Table 39-3, "Signals that Share the Twenty HSIO Lanes."

See also Chapter 10, "Flexible I/O Adapter (FIA) Overview."

Note: All signal descriptions are in the functional sections of this document. Readers of the electronic version of this document can navigate to the signal descriptions by clicking on the blue-lettered "D" in the Description column of the following tables:

- Table 39-1, "Signal Pin Name Directory - Sorted by Name"
- Table 39-3, "Signals that Share the Twenty HSIO Lanes."

Figure 39-1. Ball Quadrant Map



39.1 Directory of Signal Names and Pin Names

The table headers for Table 39-1, "Signal Pin Name Directory - Sorted by Name":

- Pin - SoC Pin/Ball matrix number
- Pin Name - Signal Name assigned to the SoC Pin/Ball
- Buffer Type - The type of driver/receiver circuitry used by the signals associated with the SoC Pin/Ball.
- V Group - SoC Voltage Group that supplies power to the driver/receiver circuitry.
- Pin States - Shows the possible states of what is connected to the pin:
  - Not Shared: The signal is not shared. None of the pin states listed below apply to the pin.
  - Strap Sampling: Shown if the pin serves as a Hard Strap during the SoC Hard-Strap pin sampling period. The sampling period is described in Section 4.1, "SoC Hard (Pin) Straps."
  - GPIO Mode: Also known as Func 0, is shown if the pin is capable of being programmed to be a Customer GPIO.
  - Default: The default internal signal connection to the pin after reset. In some cases, the pin's default setting is the Customer GPIO for the pin. Also, in some cases, The LAN Controller firmware can alter a signal-pin's default setting just before BIOS starts.
  - Func x: For pins that are shared by multiple signals, the Function number (Func 1, Func 2,..., Func 7) is programmable by BIOS. There can be up to seven different functional signals per shared pin, but in most cases, less than seven are used. The default pin-MUX setting is the pin's signal after a reset and is not necessarily Func 1. In some cases the default is a reset-configured Customer GPIO for the pin.
- Signal Name - The name of the signal internally connected to the pin for the given Pin State.
- Dir - The direction of the signal and whether the signal is an open-drain, tri-state, differential, or analog circuit:
  - I: SoC Input
  - O: SoC Output
  - O-OD: SoC Open-Drain Output
  - O-Tri: SoC Tri-State Output (logic 0, logic 1, and Hi-Z states)
  - Diff: Differential circuit
  - Analog: Not a digital-logic signal. Typically associated with pins for external compensation circuits or pins connected to internal thermal-sensing diodes.
  - SW: The PU/PD is programmed by BIOS. Typically, this is meant for Customer GPIOs.

- Internal PU/PD - Shown where the SoC has an internal Pull-Up (PU) resistor, Pull-Down (PD) resistor, or both, connected to the pin.
  - The Internal PU/PD shown for the default setting (As BIOS Starts state) remains intact even after BIOS alters the Func 1, Func 2, etc. setting.
  - The internal termination can be altered by BIOS which can program a new PU and/or PD for the pin buffer circuitry or remove all internal resistor connections to the pin.
  - For pins designated as Hard Straps, the SoC applies a special PU/PD arrangement that is active only during the strap-sensing period. After this sampling period, the default Internal PU/PD is applied to the pin.
- Signal Descriptions - Readers of the electronic version of this document can navigate to the chapter containing the signal description by clicking on the blue-colored "D" in the Description column of Table 39-1, "Signal Pin Name Directory - Sorted by Name."

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 1 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BV60	ADR_TRIGGER	CMOS-HV	V3P30	Default	GPIO[81]	O	-	D
				Func 0 GPIO	GPIO[81]	SW	SW	D
				Func 1	ADR_TRIGGER	I,O-OD	-	D
AU61	BVCCRTC_EXTPAD	RTC	VRTC	not shared	BVCCRTC_EXTPAD	I,O	-	D
A41	CLK_OUT_DN[0]	ISCLK	V1P05	not shared	CLK_OUT_DN[0]	O, Diff	-	D
A43	CLK_OUT_DN[1]	ISCLK	V1P05	not shared	CLK_OUT_DN[1]	O, Diff	-	D
A45	CLK_OUT_DN[2]	ISCLK	V1P05	not shared	CLK_OUT_DN[2]	O, Diff	-	D
A48	CLK_OUT_DN[3]	ISCLK	V1P05	not shared	CLK_OUT_DN[3]	O, Diff	-	D
A50	CLK_OUT_DN[4]	ISCLK	V1P05	not shared	CLK_OUT_DN[4]	O, Diff	-	D
C41	CLK_OUT_DP[0]	ISCLK	V1P05	not shared	CLK_OUT_DP[0]	O, Diff	-	D
C43	CLK_OUT_DP[1]	ISCLK	V1P05	not shared	CLK_OUT_DP[1]	O, Diff	-	D
C45	CLK_OUT_DP[2]	ISCLK	V1P05	not shared	CLK_OUT_DP[2]	O, Diff	-	D
C48	CLK_OUT_DP[3]	ISCLK	V1P05	not shared	CLK_OUT_DP[3]	O, Diff	-	D
C50	CLK_OUT_DP[4]	ISCLK	V1P05	not shared	CLK_OUT_DP[4]	O, Diff	-	D
C39	CLK_X1_PAD	KR	V1P05	not shared	CLK_X1_PAD	I	-	D
A39	CLK_X2_PAD	KR	V1P05	not shared	CLK_X2_PAD	O	-	D
AG56	COREPWROK	RTC	VRTC	not shared	COREPWROK	I	-	D
BE44	CTBTRIGINOUT	CMOS-LV	V1P05	Default	Reserved	I	20K PU	
				Func 0 GPIO	GPIO[148]	SW	SW	D
				Func 1	Reserved	I	20K PU	
				Func 2	CTBTRIGINOUT	I,O	20K PU	D
				Func 3	CTBTRIGINOUT	I,O	20K PU	
CA39	CTBTRIGOUT	CMOS-LV	V1P05	Default	Reserved	I	-	
				Func 0 GPIO	GPIO[149]	SW	SW	D
				Func 1	Reserved	I	-	
				Func 2	CTBTRIGOUT	O	-	D
				Func 3	Reserved	O	-	
BY38	CX_PRDY_N	CMOS-LV	V1P05	Default	CX_PRDY_N	O-OD	20K PU	D
				Func 0 GPIO	GPIO[146]	SW	SW	D
				Func 1	CX_PRDY_N	O-OD	20K PU	D
BH42	CX_PREQ_N	CMOS-LV	V1P05	Default	CX_PREQ_N	I	20K PU	D
				Func 0 GPIO	GPIO[147]	SW	SW	D
				Func 1	CX_PREQ_N	I	20K PU	D
AV3	DDR0_ACT_N_MA[15]	DDR	VDDQ	not shared	DDR0_ACT_N_MA[15]	O	-	D
AY3	DDR0_ALERT_N_PAR_ERR_N	DDR	VDDQ	not shared	DDR0_ALERT_N_PAR_ERR_N	I	None	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 2 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BV8	DDR0_BA[0]	DDR	VDDQ	not shared	DDR0_BA[0]	O	-	D
BT5	DDR0_BA[1]	DDR	VDDQ	not shared	DDR0_BA[1]	O	-	D
AW4	DDR0_BG0_BA[2]	DDR	VDDQ	not shared	DDR0_BG0_BA[2]	O	-	D
AW2	DDR0_BG1_MA[14]	DDR	VDDQ	not shared	DDR0_BG1_MA[14]	O	-	D
BV14	DDR0_C0	DDR	VDDQ	not shared	DDR0_C0	O	-	D
AT4	DDR0_CKE[0]	DDR	VDDQ	not shared	DDR0_CKE[0]	O	-	D
AP4	DDR0_CKE[1]	DDR	VDDQ	not shared	DDR0_CKE[1]	O	-	D
AT2	DDR0_CKE[2]	DDR	VDDQ	not shared	DDR0_CKE[2]	O	-	D
AR3	DDR0_CKE[3]	DDR	VDDQ	not shared	DDR0_CKE[3]	O	-	D
BM4	DDR0_CLK_DN[0]	DDR	VDDQ	not shared	DDR0_CLK_DN[0]	O, Diff	-	D
BK4	DDR0_CLK_DN[1]	DDR	VDDQ	not shared	DDR0_CLK_DN[1]	O, Diff	-	D
BL3	DDR0_CLK_DN[2]	DDR	VDDQ	not shared	DDR0_CLK_DN[2]	O, Diff	-	D
BH4	DDR0_CLK_DN[3]	DDR	VDDQ	not shared	DDR0_CLK_DN[3]	O, Diff	-	D
BM2	DDR0_CLK_DP[0]	DDR	VDDQ	not shared	DDR0_CLK_DP[0]	O, Diff	-	D
BK2	DDR0_CLK_DP[1]	DDR	VDDQ	not shared	DDR0_CLK_DP[1]	O, Diff	-	D
BL1	DDR0_CLK_DP[2]	DDR	VDDQ	not shared	DDR0_CLK_DP[2]	O, Diff	-	D
BH2	DDR0_CLK_DP[3]	DDR	VDDQ	not shared	DDR0_CLK_DP[3]	O, Diff	-	D
BW5	DDR0_CS_N[0]	DDR	VDDQ	not shared	DDR0_CS_N[0]	O	-	D
BV12	DDR0_CS_N[1]	DDR	VDDQ	not shared	DDR0_CS_N[1]	O	-	D
BV10	DDR0_CS_N[2]	DDR	VDDQ	not shared	DDR0_CS_N[2]	O	-	D
BW15	DDR0_CS_N[3]	DDR	VDDQ	not shared	DDR0_CS_N[3]	O	-	D
B12	DDR0_DQ[0]	DDR	VDDQ	not shared	DDR0_DQ[0]	I,O	-	D
D12	DDR0_DQ[1]	DDR	VDDQ	not shared	DDR0_DQ[1]	I,O	-	D
C9	DDR0_DQ[2]	DDR	VDDQ	not shared	DDR0_DQ[2]	I,O	-	D
E6	DDR0_DQ[3]	DDR	VDDQ	not shared	DDR0_DQ[3]	I,O	-	D
A13	DDR0_DQ[4]	DDR	VDDQ	not shared	DDR0_DQ[4]	I,O	-	D
C13	DDR0_DQ[5]	DDR	VDDQ	not shared	DDR0_DQ[5]	I,O	-	D
D8	DDR0_DQ[6]	DDR	VDDQ	not shared	DDR0_DQ[6]	I,O	-	D
C6	DDR0_DQ[7]	DDR	VDDQ	not shared	DDR0_DQ[7]	I,O	-	D
M2	DDR0_DQ[8]	DDR	VDDQ	not shared	DDR0_DQ[8]	I,O	-	D
M4	DDR0_DQ[9]	DDR	VDDQ	not shared	DDR0_DQ[9]	I,O	-	D
T2	DDR0_DQ[10]	DDR	VDDQ	not shared	DDR0_DQ[10]	I,O	-	D
T4	DDR0_DQ[11]	DDR	VDDQ	not shared	DDR0_DQ[11]	I,O	-	D
L1	DDR0_DQ[12]	DDR	VDDQ	not shared	DDR0_DQ[12]	I,O	-	D
L3	DDR0_DQ[13]	DDR	VDDQ	not shared	DDR0_DQ[13]	I,O	-	D
R1	DDR0_DQ[14]	DDR	VDDQ	not shared	DDR0_DQ[14]	I,O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 3 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
R3	DDR0_DQ[15]	DDR	VDDQ	not shared	DDR0_DQ[15]	I,O	-	D
Y1	DDR0_DQ[16]	DDR	VDDQ	not shared	DDR0_DQ[16]	I,O	-	D
Y3	DDR0_DQ[17]	DDR	VDDQ	not shared	DDR0_DQ[17]	I,O	-	D
AD1	DDR0_DQ[18]	DDR	VDDQ	not shared	DDR0_DQ[18]	I,O	-	D
AD3	DDR0_DQ[19]	DDR	VDDQ	not shared	DDR0_DQ[19]	I,O	-	D
W2	DDR0_DQ[20]	DDR	VDDQ	not shared	DDR0_DQ[20]	I,O	-	D
W4	DDR0_DQ[21]	DDR	VDDQ	not shared	DDR0_DQ[21]	I,O	-	D
AC2	DDR0_DQ[22]	DDR	VDDQ	not shared	DDR0_DQ[22]	I,O	-	D
AC4	DDR0_DQ[23]	DDR	VDDQ	not shared	DDR0_DQ[23]	I,O	-	D
AC11	DDR0_DQ[24]	DDR	VDDQ	not shared	DDR0_DQ[24]	I,O	-	D
AC7	DDR0_DQ[25]	DDR	VDDQ	not shared	DDR0_DQ[25]	I,O	-	D
AJ7	DDR0_DQ[26]	DDR	VDDQ	not shared	DDR0_DQ[26]	I,O	-	D
AJ11	DDR0_DQ[27]	DDR	VDDQ	not shared	DDR0_DQ[27]	I,O	-	D
AA9	DDR0_DQ[28]	DDR	VDDQ	not shared	DDR0_DQ[28]	I,O	-	D
AD9	DDR0_DQ[29]	DDR	VDDQ	not shared	DDR0_DQ[29]	I,O	-	D
AH9	DDR0_DQ[30]	DDR	VDDQ	not shared	DDR0_DQ[30]	I,O	-	D
AG11	DDR0_DQ[31]	DDR	VDDQ	not shared	DDR0_DQ[31]	I,O	-	D
BY19	DDR0_DQ[32]	DDR	VDDQ	not shared	DDR0_DQ[32]	I,O	-	D
BV19	DDR0_DQ[33]	DDR	VDDQ	not shared	DDR0_DQ[33]	I,O	-	D
BY23	DDR0_DQ[34]	DDR	VDDQ	not shared	DDR0_DQ[34]	I,O	-	D
BV23	DDR0_DQ[35]	DDR	VDDQ	not shared	DDR0_DQ[35]	I,O	-	D
CA18	DDR0_DQ[36]	DDR	VDDQ	not shared	DDR0_DQ[36]	I,O	-	D
BW18	DDR0_DQ[37]	DDR	VDDQ	not shared	DDR0_DQ[37]	I,O	-	D
CA22	DDR0_DQ[38]	DDR	VDDQ	not shared	DDR0_DQ[38]	I,O	-	D
BW22	DDR0_DQ[39]	DDR	VDDQ	not shared	DDR0_DQ[39]	I,O	-	D
BG22	DDR0_DQ[40]	DDR	VDDQ	not shared	DDR0_DQ[40]	I,O	-	D
BE22	DDR0_DQ[41]	DDR	VDDQ	not shared	DDR0_DQ[41]	I,O	-	D
BG29	DDR0_DQ[42]	DDR	VDDQ	not shared	DDR0_DQ[42]	I,O	-	D
BE29	DDR0_DQ[43]	DDR	VDDQ	not shared	DDR0_DQ[43]	I,O	-	D
BH20	DDR0_DQ[44]	DDR	VDDQ	not shared	DDR0_DQ[44]	I,O	-	D
BF20	DDR0_DQ[45]	DDR	VDDQ	not shared	DDR0_DQ[45]	I,O	-	D
BH27	DDR0_DQ[46]	DDR	VDDQ	not shared	DDR0_DQ[46]	I,O	-	D
BF27	DDR0_DQ[47]	DDR	VDDQ	not shared	DDR0_DQ[47]	I,O	-	D
CA26	DDR0_DQ[48]	DDR	VDDQ	not shared	DDR0_DQ[48]	I,O	-	D
BW26	DDR0_DQ[49]	DDR	VDDQ	not shared	DDR0_DQ[49]	I,O	-	D
CA30	DDR0_DQ[50]	DDR	VDDQ	not shared	DDR0_DQ[50]	I,O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 4 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BW30	DDR0_DQ[51]	DDR	VDDQ	not shared	DDR0_DQ[51]	I,O	-	D
BY25	DDR0_DQ[52]	DDR	VDDQ	not shared	DDR0_DQ[52]	I,O	-	D
BV25	DDR0_DQ[53]	DDR	VDDQ	not shared	DDR0_DQ[53]	I,O	-	D
BY29	DDR0_DQ[54]	DDR	VDDQ	not shared	DDR0_DQ[54]	I,O	-	D
BV29	DDR0_DQ[55]	DDR	VDDQ	not shared	DDR0_DQ[55]	I,O	-	D
BN22	DDR0_DQ[56]	DDR	VDDQ	not shared	DDR0_DQ[56]	I,O	-	D
BL22	DDR0_DQ[57]	DDR	VDDQ	not shared	DDR0_DQ[57]	I,O	-	D
BN29	DDR0_DQ[58]	DDR	VDDQ	not shared	DDR0_DQ[58]	I,O	-	D
BL29	DDR0_DQ[59]	DDR	VDDQ	not shared	DDR0_DQ[59]	I,O	-	D
BR20	DDR0_DQ[60]	DDR	VDDQ	not shared	DDR0_DQ[60]	I,O	-	D
BM20	DDR0_DQ[61]	DDR	VDDQ	not shared	DDR0_DQ[61]	I,O	-	D
BR27	DDR0_DQ[62]	DDR	VDDQ	not shared	DDR0_DQ[62]	I,O	-	D
BM27	DDR0_DQ[63]	DDR	VDDQ	not shared	DDR0_DQ[63]	I,O	-	D
B10	DDR0_DQS_DN[0]	DDR	VDDQ	not shared	DDR0_DQS_DN[0]	I,O, Diff	-	D
P2	DDR0_DQS_DN[1]	DDR	VDDQ	not shared	DDR0_DQS_DN[1]	I,O, Diff	-	D
AB1	DDR0_DQS_DN[2]	DDR	VDDQ	not shared	DDR0_DQS_DN[2]	I,O, Diff	-	D
AE7	DDR0_DQS_DN[3]	DDR	VDDQ	not shared	DDR0_DQS_DN[3]	I,O, Diff	-	D
BY21	DDR0_DQS_DN[4]	DDR	VDDQ	not shared	DDR0_DQS_DN[4]	I,O, Diff	-	D
BG26	DDR0_DQS_DN[5]	DDR	VDDQ	not shared	DDR0_DQS_DN[5]	I,O, Diff	-	D
CA28	DDR0_DQS_DN[6]	DDR	VDDQ	not shared	DDR0_DQS_DN[6]	I,O, Diff	-	D
BN26	DDR0_DQS_DN[7]	DDR	VDDQ	not shared	DDR0_DQS_DN[7]	I,O, Diff	-	D
AK2	DDR0_DQS_DN[8]	DDR	VDDQ	not shared	DDR0_DQS_DN[8]	I,O, Diff	-	D
C11	DDR0_DQS_DN[9]	DDR	VDDQ	not shared	DDR0_DQS_DN[9]	I,O, Diff	-	D
N3	DDR0_DQS_DN[10]	DDR	VDDQ	not shared	DDR0_DQS_DN[10]	I,O, Diff	-	D
AA4	DDR0_DQS_DN[11]	DDR	VDDQ	not shared	DDR0_DQS_DN[11]	I,O, Diff	-	D
AE11	DDR0_DQS_DN[12]	DDR	VDDQ	not shared	DDR0_DQS_DN[12]	I,O, Diff	-	D
BW20	DDR0_DQS_DN[13]	DDR	VDDQ	not shared	DDR0_DQS_DN[13]	I,O, Diff	-	D
BF24	DDR0_DQS_DN[14]	DDR	VDDQ	not shared	DDR0_DQS_DN[14]	I,O, Diff	-	D
BV27	DDR0_DQS_DN[15]	DDR	VDDQ	not shared	DDR0_DQS_DN[15]	I,O, Diff	-	D
BM24	DDR0_DQS_DN[16]	DDR	VDDQ	not shared	DDR0_DQS_DN[16]	I,O, Diff	-	D
AJ3	DDR0_DQS_DN[17]	DDR	VDDQ	not shared	DDR0_DQS_DN[17]	I,O, Diff	-	D
D10	DDR0_DQS_DP[0]	DDR	VDDQ	not shared	DDR0_DQS_DP[0]	I,O, Diff	-	D
P4	DDR0_DQS_DP[1]	DDR	VDDQ	not shared	DDR0_DQS_DP[1]	I,O, Diff	-	D
AB3	DDR0_DQS_DP[2]	DDR	VDDQ	not shared	DDR0_DQS_DP[2]	I,O, Diff	-	D
AG7	DDR0_DQS_DP[3]	DDR	VDDQ	not shared	DDR0_DQS_DP[3]	I,O, Diff	-	D
BV21	DDR0_DQS_DP[4]	DDR	VDDQ	not shared	DDR0_DQS_DP[4]	I,O, Diff	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 5 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BE26	DDR0_DQS_DP[5]	DDR	VDDQ	not shared	DDR0_DQS_DP[5]	I,O, Diff	-	D
BW28	DDR0_DQS_DP[6]	DDR	VDDQ	not shared	DDR0_DQS_DP[6]	I,O, Diff	-	D
BL26	DDR0_DQS_DP[7]	DDR	VDDQ	not shared	DDR0_DQS_DP[7]	I,O, Diff	-	D
AK4	DDR0_DQS_DP[8]	DDR	VDDQ	not shared	DDR0_DQS_DP[8]	I,O, Diff	-	D
A11	DDR0_DQS_DP[9]	DDR	VDDQ	not shared	DDR0_DQS_DP[9]	I,O, Diff	-	D
N1	DDR0_DQS_DP[10]	DDR	VDDQ	not shared	DDR0_DQS_DP[10]	I,O, Diff	-	D
AA2	DDR0_DQS_DP[11]	DDR	VDDQ	not shared	DDR0_DQS_DP[11]	I,O, Diff	-	D
AF9	DDR0_DQS_DP[12]	DDR	VDDQ	not shared	DDR0_DQS_DP[12]	I,O, Diff	-	D
CA20	DDR0_DQS_DP[13]	DDR	VDDQ	not shared	DDR0_DQS_DP[13]	I,O, Diff	-	D
BH24	DDR0_DQS_DP[14]	DDR	VDDQ	not shared	DDR0_DQS_DP[14]	I,O, Diff	-	D
BY27	DDR0_DQS_DP[15]	DDR	VDDQ	not shared	DDR0_DQS_DP[15]	I,O, Diff	-	D
BR24	DDR0_DQS_DP[16]	DDR	VDDQ	not shared	DDR0_DQS_DP[16]	I,O, Diff	-	D
AJ1	DDR0_DQS_DP[17]	DDR	VDDQ	not shared	DDR0_DQS_DP[17]	I,O, Diff	-	D
AH2	DDR0_ECC[0]	DDR	VDDQ	not shared	DDR0_ECC[0]	I,O	-	D
AH4	DDR0_ECC[1]	DDR	VDDQ	not shared	DDR0_ECC[1]	I,O	-	D
AM2	DDR0_ECC[2]	DDR	VDDQ	not shared	DDR0_ECC[2]	I,O	-	D
AM4	DDR0_ECC[3]	DDR	VDDQ	not shared	DDR0_ECC[3]	I,O	-	D
AF1	DDR0_ECC[4]	DDR	VDDQ	not shared	DDR0_ECC[4]	I,O	-	D
AF3	DDR0_ECC[5]	DDR	VDDQ	not shared	DDR0_ECC[5]	I,O	-	D
AL1	DDR0_ECC[6]	DDR	VDDQ	not shared	DDR0_ECC[6]	I,O	-	D
AL3	DDR0_ECC[7]	DDR	VDDQ	not shared	DDR0_ECC[7]	I,O	-	D
BP4	DDR0_MA[0]	DDR	VDDQ	not shared	DDR0_MA[0]	O	-	D
BF3	DDR0_MA[1]	DDR	VDDQ	not shared	DDR0_MA[1]	O	-	D
BF1	DDR0_MA[2]	DDR	VDDQ	not shared	DDR0_MA[2]	O	-	D
BE2	DDR0_MA[3]	DDR	VDDQ	not shared	DDR0_MA[3]	O	-	D
BE4	DDR0_MA[4]	DDR	VDDQ	not shared	DDR0_MA[4]	O	-	D
BD3	DDR0_MA[5]	DDR	VDDQ	not shared	DDR0_MA[5]	O	-	D
BC2	DDR0_MA[6]	DDR	VDDQ	not shared	DDR0_MA[6]	O	-	D
BB1	DDR0_MA[7]	DDR	VDDQ	not shared	DDR0_MA[7]	O	-	D
BC4	DDR0_MA[8]	DDR	VDDQ	not shared	DDR0_MA[8]	O	-	D
BA2	DDR0_MA[9]	DDR	VDDQ	not shared	DDR0_MA[9]	O	-	D
BU6	DDR0_MA[10]	DDR	VDDQ	not shared	DDR0_MA[10]	O	-	D
BB3	DDR0_MA[11]	DDR	VDDQ	not shared	DDR0_MA[11]	O	-	D
BA4	DDR0_MA[12]	DDR	VDDQ	not shared	DDR0_MA[12]	O	-	D
BW11	DDR0_MA[13]	DDR	VDDQ	not shared	DDR0_MA[13]	O	-	D
BW9	DDR0_MA14_WE_N	DDR	VDDQ	not shared	DDR0_MA14_WE_N	O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 6 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
CA11	DDR0_MA15_CAS_N	DDR	VDDQ	not shared	DDR0_MA15_CAS_N	O	-	D
BW6	DDR0_MA16_RAS_N	DDR	VDDQ	not shared	DDR0_MA16_RAS_N	O	-	D
CA13	DDR0_MA17	DDR	VDDQ	not shared	DDR0_MA17	O	-	D
BY10	DDR0_ODT[0]	DDR	VDDQ	not shared	DDR0_ODT[0]	O	-	D
BY14	DDR0_ODT[1]	DDR	VDDQ	not shared	DDR0_ODT[1]	O	-	D
BW13	DDR0_ODT[2]	DDR	VDDQ	not shared	DDR0_ODT[2]	O	-	D
CA15	DDR0_ODT[3]	DDR	VDDQ	not shared	DDR0_ODT[3]	O	-	D
BN3	DDR0_PAR	DDR	VDDQ	not shared	DDR0_PAR	O	-	D
AD24	DDR01_COMP	DDR	VDDQ	not shared	DDR01_COMP	O	-	D
AP2	DDR01_DRAMRST_N	DDR	VDDQ	not shared	DDR01_DRAMRST_N	O	-	D
H9	DDR1_ACT_N_MA[15]	DDR	VDDQ	not shared	DDR1_ACT_N_MA[15]	O	-	D
M15	DDR1_ALERT_N_PAR_ERR_N	DDR	VDDQ	not shared	DDR1_ALERT_N_PAR_ERR_N	I	None	D
AD20	DDR1_BA[0]	DDR	VDDQ	not shared	DDR1_BA[0]	O	-	D
AA20	DDR1_BA[1]	DDR	VDDQ	not shared	DDR1_BA[1]	O	-	D
G7	DDR1_BG0_BA[2]	DDR	VDDQ	not shared	DDR1_BG0_BA[2]	O	-	D
J5	DDR1_BG1_MA[14]	DDR	VDDQ	not shared	DDR1_BG1_MA[14]	O	-	D
AJ15	DDR1_C0	DDR	VDDQ	not shared	DDR1_C0	O	-	D
K13	DDR1_CKE[0]	DDR	VDDQ	not shared	DDR1_CKE[0]	O	-	D
J15	DDR1_CKE[1]	DDR	VDDQ	not shared	DDR1_CKE[1]	O	-	D
H13	DDR1_CKE[2]	DDR	VDDQ	not shared	DDR1_CKE[2]	O	-	D
G15	DDR1_CKE[3]	DDR	VDDQ	not shared	DDR1_CKE[3]	O	-	D
AC15	DDR1_CLK_DN[0]	DDR	VDDQ	not shared	DDR1_CLK_DN[0]	O, Diff	-	D
Y15	DDR1_CLK_DN[1]	DDR	VDDQ	not shared	DDR1_CLK_DN[1]	O, Diff	-	D
V15	DDR1_CLK_DN[2]	DDR	VDDQ	not shared	DDR1_CLK_DN[2]	O, Diff	-	D
U13	DDR1_CLK_DN[3]	DDR	VDDQ	not shared	DDR1_CLK_DN[3]	O, Diff	-	D
AD17	DDR1_CLK_DP[0]	DDR	VDDQ	not shared	DDR1_CLK_DP[0]	O, Diff	-	D
AA17	DDR1_CLK_DP[1]	DDR	VDDQ	not shared	DDR1_CLK_DP[1]	O, Diff	-	D
W17	DDR1_CLK_DP[2]	DDR	VDDQ	not shared	DDR1_CLK_DP[2]	O, Diff	-	D
T15	DDR1_CLK_DP[3]	DDR	VDDQ	not shared	DDR1_CLK_DP[3]	O, Diff	-	D
AG22	DDR1_CS_N[0]	DDR	VDDQ	not shared	DDR1_CS_N[0]	O	-	D
AV22	DDR1_CS_N[1]	DDR	VDDQ	not shared	DDR1_CS_N[1]	O	-	D
AF17	DDR1_CS_N[2]	DDR	VDDQ	not shared	DDR1_CS_N[2]	O	-	D
AH17	DDR1_CS_N[3]	DDR	VDDQ	not shared	DDR1_CS_N[3]	O	-	D
A34	DDR1_DQ[0]	DDR	VDDQ	not shared	DDR1_DQ[0]	I,O	-	D
C34	DDR1_DQ[1]	DDR	VDDQ	not shared	DDR1_DQ[1]	I,O	-	D
A30	DDR1_DQ[2]	DDR	VDDQ	not shared	DDR1_DQ[2]	I,O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 7 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
C30	DDR1_DQ[3]	DDR	VDDQ	not shared	DDR1_DQ[3]	I,O	-	D
B35	DDR1_DQ[4]	DDR	VDDQ	not shared	DDR1_DQ[4]	I,O	-	D
D35	DDR1_DQ[5]	DDR	VDDQ	not shared	DDR1_DQ[5]	I,O	-	D
B31	DDR1_DQ[6]	DDR	VDDQ	not shared	DDR1_DQ[6]	I,O	-	D
D31	DDR1_DQ[7]	DDR	VDDQ	not shared	DDR1_DQ[7]	I,O	-	D
P26	DDR1_DQ[8]	DDR	VDDQ	not shared	DDR1_DQ[8]	I,O	-	D
T26	DDR1_DQ[9]	DDR	VDDQ	not shared	DDR1_DQ[9]	I,O	-	D
P18	DDR1_DQ[10]	DDR	VDDQ	not shared	DDR1_DQ[10]	I,O	-	D
T18	DDR1_DQ[11]	DDR	VDDQ	not shared	DDR1_DQ[11]	I,O	-	D
R27	DDR1_DQ[12]	DDR	VDDQ	not shared	DDR1_DQ[12]	I,O	-	D
U27	DDR1_DQ[13]	DDR	VDDQ	not shared	DDR1_DQ[13]	I,O	-	D
R20	DDR1_DQ[14]	DDR	VDDQ	not shared	DDR1_DQ[14]	I,O	-	D
U20	DDR1_DQ[15]	DDR	VDDQ	not shared	DDR1_DQ[15]	I,O	-	D
G26	DDR1_DQ[16]	DDR	VDDQ	not shared	DDR1_DQ[16]	I,O	-	D
J26	DDR1_DQ[17]	DDR	VDDQ	not shared	DDR1_DQ[17]	I,O	-	D
G18	DDR1_DQ[18]	DDR	VDDQ	not shared	DDR1_DQ[18]	I,O	-	D
J18	DDR1_DQ[19]	DDR	VDDQ	not shared	DDR1_DQ[19]	I,O	-	D
H27	DDR1_DQ[20]	DDR	VDDQ	not shared	DDR1_DQ[20]	I,O	-	D
K27	DDR1_DQ[21]	DDR	VDDQ	not shared	DDR1_DQ[21]	I,O	-	D
H20	DDR1_DQ[22]	DDR	VDDQ	not shared	DDR1_DQ[22]	I,O	-	D
K20	DDR1_DQ[23]	DDR	VDDQ	not shared	DDR1_DQ[23]	I,O	-	D
B27	DDR1_DQ[24]	DDR	VDDQ	not shared	DDR1_DQ[24]	I,O	-	D
D27	DDR1_DQ[25]	DDR	VDDQ	not shared	DDR1_DQ[25]	I,O	-	D
B23	DDR1_DQ[26]	DDR	VDDQ	not shared	DDR1_DQ[26]	I,O	-	D
D23	DDR1_DQ[27]	DDR	VDDQ	not shared	DDR1_DQ[27]	I,O	-	D
A28	DDR1_DQ[28]	DDR	VDDQ	not shared	DDR1_DQ[28]	I,O	-	D
C28	DDR1_DQ[29]	DDR	VDDQ	not shared	DDR1_DQ[29]	I,O	-	D
A24	DDR1_DQ[30]	DDR	VDDQ	not shared	DDR1_DQ[30]	I,O	-	D
C24	DDR1_DQ[31]	DDR	VDDQ	not shared	DDR1_DQ[31]	I,O	-	D
AP11	DDR1_DQ[32]	DDR	VDDQ	not shared	DDR1_DQ[32]	I,O	-	D
AP7	DDR1_DQ[33]	DDR	VDDQ	not shared	DDR1_DQ[33]	I,O	-	D
AY7	DDR1_DQ[34]	DDR	VDDQ	not shared	DDR1_DQ[34]	I,O	-	D
AY11	DDR1_DQ[35]	DDR	VDDQ	not shared	DDR1_DQ[35]	I,O	-	D
AN9	DDR1_DQ[36]	DDR	VDDQ	not shared	DDR1_DQ[36]	I,O	-	D
AR9	DDR1_DQ[37]	DDR	VDDQ	not shared	DDR1_DQ[37]	I,O	-	D
AW9	DDR1_DQ[38]	DDR	VDDQ	not shared	DDR1_DQ[38]	I,O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 8 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
AV11	DDR1_DQ[39]	DDR	VDDQ	not shared	DDR1_DQ[39]	I,O	-	D
AT15	DDR1_DQ[40]	DDR	VDDQ	not shared	DDR1_DQ[40]	I,O	-	D
AU17	DDR1_DQ[41]	DDR	VDDQ	not shared	DDR1_DQ[41]	I,O	-	D
BD17	DDR1_DQ[42]	DDR	VDDQ	not shared	DDR1_DQ[42]	I,O	-	D
BB15	DDR1_DQ[43]	DDR	VDDQ	not shared	DDR1_DQ[43]	I,O	-	D
AR17	DDR1_DQ[44]	DDR	VDDQ	not shared	DDR1_DQ[44]	I,O	-	D
AP15	DDR1_DQ[45]	DDR	VDDQ	not shared	DDR1_DQ[45]	I,O	-	D
BA17	DDR1_DQ[46]	DDR	VDDQ	not shared	DDR1_DQ[46]	I,O	-	D
AY15	DDR1_DQ[47]	DDR	VDDQ	not shared	DDR1_DQ[47]	I,O	-	D
BJ7	DDR1_DQ[48]	DDR	VDDQ	not shared	DDR1_DQ[48]	I,O	-	D
BH9	DDR1_DQ[49]	DDR	VDDQ	not shared	DDR1_DQ[49]	I,O	-	D
BL11	DDR1_DQ[50]	DDR	VDDQ	not shared	DDR1_DQ[50]	I,O	-	D
BR9	DDR1_DQ[51]	DDR	VDDQ	not shared	DDR1_DQ[51]	I,O	-	D
BF9	DDR1_DQ[52]	DDR	VDDQ	not shared	DDR1_DQ[52]	I,O	-	D
BG7	DDR1_DQ[53]	DDR	VDDQ	not shared	DDR1_DQ[53]	I,O	-	D
BN7	DDR1_DQ[54]	DDR	VDDQ	not shared	DDR1_DQ[54]	I,O	-	D
BM9	DDR1_DQ[55]	DDR	VDDQ	not shared	DDR1_DQ[55]	I,O	-	D
BH17	DDR1_DQ[56]	DDR	VDDQ	not shared	DDR1_DQ[56]	I,O	-	D
BK17	DDR1_DQ[57]	DDR	VDDQ	not shared	DDR1_DQ[57]	I,O	-	D
BM17	DDR1_DQ[58]	DDR	VDDQ	not shared	DDR1_DQ[58]	I,O	-	D
BR17	DDR1_DQ[59]	DDR	VDDQ	not shared	DDR1_DQ[59]	I,O	-	D
BG15	DDR1_DQ[60]	DDR	VDDQ	not shared	DDR1_DQ[60]	I,O	-	D
BH13	DDR1_DQ[61]	DDR	VDDQ	not shared	DDR1_DQ[61]	I,O	-	D
BR13	DDR1_DQ[62]	DDR	VDDQ	not shared	DDR1_DQ[62]	I,O	-	D
BN15	DDR1_DQ[63]	DDR	VDDQ	not shared	DDR1_DQ[63]	I,O	-	D
A32	DDR1_DQS_DN[0]	DDR	VDDQ	not shared	DDR1_DQS_DN[0]	I,O, Diff	-	D
P22	DDR1_DQS_DN[1]	DDR	VDDQ	not shared	DDR1_DQS_DN[1]	I,O, Diff	-	D
G22	DDR1_DQS_DN[2]	DDR	VDDQ	not shared	DDR1_DQS_DN[2]	I,O, Diff	-	D
B25	DDR1_DQS_DN[3]	DDR	VDDQ	not shared	DDR1_DQS_DN[3]	I,O, Diff	-	D
AT7	DDR1_DQS_DN[4]	DDR	VDDQ	not shared	DDR1_DQS_DN[4]	I,O, Diff	-	D
AW17	DDR1_DQS_DN[5]	DDR	VDDQ	not shared	DDR1_DQS_DN[5]	I,O, Diff	-	D
BL7	DDR1_DQS_DN[6]	DDR	VDDQ	not shared	DDR1_DQS_DN[6]	I,O, Diff	-	D
BM13	DDR1_DQS_DN[7]	DDR	VDDQ	not shared	DDR1_DQS_DN[7]	I,O, Diff	-	D
A18	DDR1_DQS_DN[8]	DDR	VDDQ	not shared	DDR1_DQS_DN[8]	I,O, Diff	-	D
D33	DDR1_DQS_DN[9]	DDR	VDDQ	not shared	DDR1_DQS_DN[9]	I,O, Diff	-	D
U24	DDR1_DQS_DN[10]	DDR	VDDQ	not shared	DDR1_DQS_DN[10]	I,O, Diff	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 9 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
K24	DDR1_DQS_DN[11]	DDR	VDDQ	not shared	DDR1_DQS_DN[11]	I,O, Diff	-	D
C26	DDR1_DQS_DN[12]	DDR	VDDQ	not shared	DDR1_DQS_DN[12]	I,O, Diff	-	D
AT11	DDR1_DQS_DN[13]	DDR	VDDQ	not shared	DDR1_DQS_DN[13]	I,O, Diff	-	D
AU13	DDR1_DQS_DN[14]	DDR	VDDQ	not shared	DDR1_DQS_DN[14]	I,O, Diff	-	D
BE11	DDR1_DQS_DN[15]	DDR	VDDQ	not shared	DDR1_DQS_DN[15]	I,O, Diff	-	D
BJ15	DDR1_DQS_DN[16]	DDR	VDDQ	not shared	DDR1_DQS_DN[16]	I,O, Diff	-	D
D19	DDR1_DQS_DN[17]	DDR	VDDQ	not shared	DDR1_DQS_DN[17]	I,O, Diff	-	D
C32	DDR1_DQS_DP[0]	DDR	VDDQ	not shared	DDR1_DQS_DP[0]	I,O, Diff	-	D
T22	DDR1_DQS_DP[1]	DDR	VDDQ	not shared	DDR1_DQS_DP[1]	I,O, Diff	-	D
J22	DDR1_DQS_DP[2]	DDR	VDDQ	not shared	DDR1_DQS_DP[2]	I,O, Diff	-	D
D25	DDR1_DQS_DP[3]	DDR	VDDQ	not shared	DDR1_DQS_DP[3]	I,O, Diff	-	D
AV7	DDR1_DQS_DP[4]	DDR	VDDQ	not shared	DDR1_DQS_DP[4]	I,O, Diff	-	D
AV15	DDR1_DQS_DP[5]	DDR	VDDQ	not shared	DDR1_DQS_DP[5]	I,O, Diff	-	D
BK9	DDR1_DQS_DP[6]	DDR	VDDQ	not shared	DDR1_DQS_DP[6]	I,O, Diff	-	D
BL15	DDR1_DQS_DP[7]	DDR	VDDQ	not shared	DDR1_DQS_DP[7]	I,O, Diff	-	D
C18	DDR1_DQS_DP[8]	DDR	VDDQ	not shared	DDR1_DQS_DP[8]	I,O, Diff	-	D
B33	DDR1_DQS_DP[9]	DDR	VDDQ	not shared	DDR1_DQS_DP[9]	I,O, Diff	-	D
R24	DDR1_DQS_DP[10]	DDR	VDDQ	not shared	DDR1_DQS_DP[10]	I,O, Diff	-	D
H24	DDR1_DQS_DP[11]	DDR	VDDQ	not shared	DDR1_DQS_DP[11]	I,O, Diff	-	D
A26	DDR1_DQS_DP[12]	DDR	VDDQ	not shared	DDR1_DQS_DP[12]	I,O, Diff	-	D
AU9	DDR1_DQS_DP[13]	DDR	VDDQ	not shared	DDR1_DQS_DP[13]	I,O, Diff	-	D
AW13	DDR1_DQS_DP[14]	DDR	VDDQ	not shared	DDR1_DQS_DP[14]	I,O, Diff	-	D
BG11	DDR1_DQS_DP[15]	DDR	VDDQ	not shared	DDR1_DQS_DP[15]	I,O, Diff	-	D
BK13	DDR1_DQS_DP[16]	DDR	VDDQ	not shared	DDR1_DQS_DP[16]	I,O, Diff	-	D
B19	DDR1_DQS_DP[17]	DDR	VDDQ	not shared	DDR1_DQS_DP[17]	I,O, Diff	-	D
A20	DDR1_ECC[0]	DDR	VDDQ	not shared	DDR1_ECC[0]	I,O	-	D
C20	DDR1_ECC[1]	DDR	VDDQ	not shared	DDR1_ECC[1]	I,O	-	D
A15	DDR1_ECC[2]	DDR	VDDQ	not shared	DDR1_ECC[2]	I,O	-	D
C15	DDR1_ECC[3]	DDR	VDDQ	not shared	DDR1_ECC[3]	I,O	-	D
B21	DDR1_ECC[4]	DDR	VDDQ	not shared	DDR1_ECC[4]	I,O	-	D
D21	DDR1_ECC[5]	DDR	VDDQ	not shared	DDR1_ECC[5]	I,O	-	D
B16	DDR1_ECC[6]	DDR	VDDQ	not shared	DDR1_ECC[6]	I,O	-	D
D16	DDR1_ECC[7]	DDR	VDDQ	not shared	DDR1_ECC[7]	I,O	-	D
AE22	DDR1_MA[0]	DDR	VDDQ	not shared	DDR1_MA[0]	O	-	D
U9	DDR1_MA[1]	DDR	VDDQ	not shared	DDR1_MA[1]	O	-	D
T7	DDR1_MA[2]	DDR	VDDQ	not shared	DDR1_MA[2]	O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 10 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
P7	DDR1_MA[3]	DDR	VDDQ	not shared	DDR1_MA[3]	O	-	D
R13	DDR1_MA[4]	DDR	VDDQ	not shared	DDR1_MA[4]	O	-	D
N13	DDR1_MA[5]	DDR	VDDQ	not shared	DDR1_MA[5]	O	-	D
M7	DDR1_MA[6]	DDR	VDDQ	not shared	DDR1_MA[6]	O	-	D
N9	DDR1_MA[7]	DDR	VDDQ	not shared	DDR1_MA[7]	O	-	D
R9	DDR1_MA[8]	DDR	VDDQ	not shared	DDR1_MA[8]	O	-	D
J11	DDR1_MA[9]	DDR	VDDQ	not shared	DDR1_MA[9]	O	-	D
AF20	DDR1_MA[10]	DDR	VDDQ	not shared	DDR1_MA[10]	O	-	D
J7	DDR1_MA[11]	DDR	VDDQ	not shared	DDR1_MA[11]	O	-	D
G11	DDR1_MA[12]	DDR	VDDQ	not shared	DDR1_MA[12]	O	-	D
AW20	DDR1_MA[13]	DDR	VDDQ	not shared	DDR1_MA[13]	O	-	D
AR20	DDR1_MA14_WE_N	DDR	VDDQ	not shared	DDR1_MA14_WE_N	O	-	D
AT22	DDR1_MA15_CAS_N	DDR	VDDQ	not shared	DDR1_MA15_CAS_N	O	-	D
AC22	DDR1_MA16_RAS_N	DDR	VDDQ	not shared	DDR1_MA16_RAS_N	O	-	D
AG15	DDR1_MA17	DDR	VDDQ	not shared	DDR1_MA17	O	-	D
AU20	DDR1_ODT[0]	DDR	VDDQ	not shared	DDR1_ODT[0]	O	-	D
AY22	DDR1_ODT[1]	DDR	VDDQ	not shared	DDR1_ODT[1]	O	-	D
AE15	DDR1_ODT[2]	DDR	VDDQ	not shared	DDR1_ODT[2]	O	-	D
AK17	DDR1_ODT[3]	DDR	VDDQ	not shared	DDR1_ODT[3]	O	-	D
V7	DDR1_PAR	DDR	VDDQ	not shared	DDR1_PAR	O	-	D
BN68	DFX_PORT[0]	CMOS-LV	V1P05	Default	DFX_PORT[0]	O	-	D
				Func 0 GPIO	GPIO[55]	SW	SW	D
				Func 1	DFX_PORT[0]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	I,O	-	
				Func 4	Reserved	I,O	-	
				Func 5	Reserved	O	-	
				Func 6	Reserved	O	-	
BN70	DFX_PORT[1]	CMOS-LV	V1P05	Default	DFX_PORT[1]	O	-	D
				Func 0 GPIO	GPIO[56]	SW	SW	D
				Func 1	DFX_PORT[1]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	I,O	-	
				Func 4	Reserved	I,O	-	
				Func 5	Reserved	O	-	

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 11 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BE63	DFX_PORT[2]	CMOS-LV	V1P05	Default	DFX_PORT[2]	O	-	D
				Func 0 GPIO	GPIO[57]	SW	SW	D
				Func 1	DFX_PORT[2]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	I,O	-	
				Func 4	Reserved	I,O	-	
				Func 5	Reserved	O	-	
BP69	DFX_PORT[3]	CMOS-LV	V1P05	Default	DFX_PORT[3]	O	-	D
				Func 0 GPIO	GPIO[58]	SW	SW	D
				Func 1	DFX_PORT[3]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	I,O	-	
				Func 4	Reserved	I,O	-	
				Func 5	Reserved	O	-	
BW68	DFX_PORT[4]	CMOS-LV	V1P05	Default	DFX_PORT[4]	O	-	D
				Func 0 GPIO	GPIO[59]	SW	SW	D
				Func 1	DFX_PORT[4]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
BH69	DFX_PORT[5]	CMOS-LV	V1P05	Default	DFX_PORT[5]	O	-	D
				Func 0 GPIO	GPIO[60]	SW	SW	D
				Func 1	DFX_PORT[5]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
BG63	DFX_PORT[6]	CMOS-LV	V1P05	Default	DFX_PORT[6]	O	-	D
				Func 0 GPIO	GPIO[61]	SW	SW	D
				Func 1	DFX_PORT[6]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 12 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BT69	DFX_PORT[7]	CMOS-LV	V1P05	Default	DFX_PORT[7]	O	-	D
				Func 0 GPIO	GPIO[62]	SW	SW	D
				Func 1	DFX_PORT[7]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
BW67	DFX_PORT[8]	CMOS-LV	V1P05	Default	DFX_PORT[8]	O	-	D
				Func 0 GPIO	GPIO[63]	SW	SW	D
				Func 1	DFX_PORT[8]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
				Func 6	Reserved	O	-	
AY52	DFX_PORT[9]	CMOS-LV	V1P05	Default	DFX_PORT[9]	O	-	D
				Func 0 GPIO	GPIO[134]	SW	SW	D
				Func 1	DFX_PORT[9]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
				Func 6	Reserved	O	-	
BR42	DFX_PORT[10]	CMOS-LV	V1P05	Default	DFX_PORT[10]	O	-	D
				Func 0 GPIO	GPIO[135]	SW	SW	D
				Func 1	DFX_PORT[10]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
				Func 6	Reserved	O	-	

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 13 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BK42	DFX_PORT[11]	CMOS-LV	V1P05	Default	DFX_PORT[11]	O	-	D
				Func 0 GPIO	GPIO[136]	SW	SW	D
				Func 1	DFX_PORT[11]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 6	Reserved	O	-	
BW41	DFX_PORT[12]	CMOS-LV	V1P05	Default	DFX_PORT[12]	O	-	D
				Func 0 GPIO	GPIO[137]	SW	SW	D
				Func 1	DFX_PORT[12]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
				Func 6	Reserved	O	-	
BE48	DFX_PORT[13]	CMOS-LV	V1P05	Default	DFX_PORT[13]	O	-	D
				Func 0 GPIO	GPIO[138]	SW	SW	D
				Func 1	DFX_PORT[13]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
				Func 6	Reserved	O	-	
CA41	DFX_PORT[14]	CMOS-LV	V1P05	Default	DFX_PORT[14]	O	-	D
				Func 0 GPIO	GPIO[139]	SW	SW	D
				Func 1	DFX_PORT[14]	O	-	D
				Func 2	Reserved	O	-	
				Func 3	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	
BV40	DFX_PORT[15]	CMOS-LV	V1P05	Default	DFX_PORT[15]	O	-	D
				Func 0 GPIO	GPIO[140]	SW	SW	D
				Func 1	DFX_PORT[15]	O	-	D
				Func 2	Reserved	O	-	
				Func 4	Reserved	O	-	
				Func 5	Reserved	O	-	

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 14 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
AY56	DFX_PORT_CLK[0]	CMOS-LV	V1P05	Default	DFX_PORT_CLK[0]	O	-	D
				Func 0 GPIO	GPIO[53]	SW	SW	D
				Func 1	DFX_PORT_CLK[0]	O	-	D
BB70	DFX_PORT_CLK[1]	CMOS-LV	V1P05	Default	DFX_PORT_CLK[1]	O	-	D
				Func 0 GPIO	GPIO[54]	SW	SW	D
				Func 1	DFX_PORT_CLK[1]	O	-	D
				Func 2	Reserved	I	-	
BK46	EMMC_CLK	CMOS-MV	V1P80	Default	GPIO[125]	I	-	D
				Func 0 GPIO	GPIO[125]	SW	SW	D
				Func 1	EMMC_CLK	I,O	-	D
BN48	EMMC_CMD	CMOS-MV	V1P80	Default	GPIO[123]	I	-	D
				Func 0 GPIO	GPIO[123]	SW	SW	D
				Func 1	EMMC_CMD	I,O	-	D
BW45	EMMC_D[0]	CMOS-MV	V1P80	Default	GPIO[126]	I	-	D
				Func 0 GPIO	GPIO[126]	SW	SW	D
				Func 1	EMMC_D[0]	I,O	-	D
BV44	EMMC_D[1]	CMOS-MV	V1P80	Default	GPIO[127]	I	-	D
				Func 0 GPIO	GPIO[127]	SW	SW	D
				Func 1	EMMC_D[1]	I,O	-	D
BY44	EMMC_D[2]	CMOS-MV	V1P80	Default	GPIO[128]	I	-	D
				Func 0 GPIO	GPIO[128]	SW	SW	D
				Func 1	EMMC_D[2]	I,O	-	D
CA45	EMMC_D[3]	CMOS-MV	V1P80	Default	GPIO[129]	I	-	D
				Func 0 GPIO	GPIO[129]	SW	SW	D
				Func 1	EMMC_D[3]	I,O	-	D
BU43	EMMC_D[4]	CMOS-MV	V1P80	Default	GPIO[130]	I	-	D
				Func 0 GPIO	GPIO[130]	SW	SW	D
				Func 1	EMMC_D[4]	I,O	-	D
CA43	EMMC_D[5]	CMOS-MV	V1P80	Default	GPIO[131]	I	-	D
				Func 0 GPIO	GPIO[131]	SW	SW	D
				Func 1	EMMC_D[5]	I,O	-	D
BY42	EMMC_D[6]	CMOS-MV	V1P80	Default	GPIO[132]	I	-	D
				Func 0 GPIO	GPIO[132]	SW	SW	D
				Func 1	EMMC_D[6]	I,O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 15 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BV42	EMMC_D[7]	CMOS-MV	V1P80	Default	GPIO[133]	I	-	D
				Func 0 GPIO	GPIO[133]	SW	SW	D
				Func 1	EMMC_D[7]	I,O	-	D
BE40	EMMC_IRCOMP	Analog	V1P80	not shared	EMMC_IRCOMP	I,O	-	D
BL44	EMMC_STROBE	CMOS-MV	V1P80	Default	GPIO[124]	I	-	D
				Func 0 GPIO	GPIO[124]	SW	SW	D
				Func 1	EMMC_STROBE	I	-	D
BL52	ERROR_N[0]	CMOS-HV	V3P30	Strap Sampling	LPC Decode Select	I	20K PD	D
				Default	ERROR_N[0]	O	-	D
				Func 0 GPIO	GPIO[107]	SW	SW	D
				Func 1	ERROR_N[0]	O	-	D
BR58	ERROR_N[1]	CMOS-HV	V3P30	Strap Sampling	Boot BIOS Strap (BBS)	I	20K PD	D
				Default	ERROR_N[1]	O	-	D
				Func 0 GPIO	GPIO[106]	SW	SW	D
				Func 1	ERROR_N[1]	O	-	D
CA50	ERROR_N[2]	CMOS-HV	V3P30	Strap Sampling	Intel Reserved	I	20K PD	D
				Default	ERROR_N[2]	O	-	D
				Func 0 GPIO	GPIO[105]	SW	SW	D
				Func 1	ERROR_N[2]	O	-	D
BK61	ESPI_ALRT_N[0]	CMOS-HV	V3P30	Default	LPC_CLKRUN_N			
				Func 0 GPIO	GPIO[71]	SW	SW	D
				Func 2	LPC_CLKRUN_N	I,O-Tri	-	D
BY62	ESPI_ALRT_N[1]	CMOS-HV	V3P30	Default	ESPI_ALRT_N[1]	I	-	D
				Func 0 GPIO	GPIO[11]	SW	SW	D
				Func 1	ESPI_ALRT_N[1]	I	-	D
				Func 2	LPC_SERIRQ	I,O-Tri	-	D
BY64	ESPI_CLK	CMOS-HV	V3P30	Default	LPC_CLKOUT[0]			
				Func 0 GPIO	GPIO[69]	SW	SW	D
				Func 2	LPC_CLKOUT[0]	O	20K PD	D
BJ72	ESPI_CS_N[0]	CMOS-HV	V3P30	Default	LPC_FRAME_N			
				Func 0 GPIO	GPIO[68]	SW	SW	D
				Func 2	LPC_FRAME_N	O	20K PU	D
CA63	ESPI_CS_N[1]	CMOS-HV	V3P30	Default	ESPI_CS_N[1]	O-Tri	-	D
				Func 0 GPIO	GPIO[10]	SW	SW	D
				Func 1	ESPI_CS_N[1]	O-Tri	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 16 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BD58	ESPI_IO[0]	CMOS-HV	V3P30	Default	LPC_AD[0]			
				Func 0 GPIO	GPIO[64]	SW	SW	D
				Func 2	LPC_AD[0]	I,O-Tri	20K PU	D
BR67	ESPI_IO[1]	CMOS-HV	V3P30	Default	LPC_AD[1]			
				Func 0 GPIO	GPIO[65]	SW	SW	D
				Func 2	LPC_AD[1]	I,O-Tri	20K PU	D
BV64	ESPI_IO[2]	CMOS-HV	V3P30	Default	LPC_AD[2]			
				Func 0 GPIO	GPIO[66]	SW	SW	D
				Func 2	LPC_AD[2]	I,O-Tri	20K PU	D
BH65	ESPI_IO[3]	CMOS-HV	V3P30	Default	LPC_AD[3]			
				Func 0 GPIO	GPIO[67]	SW	SW	D
				Func 2	LPC_AD[3]	I,O-Tri	20K PU	D
BD50	ESPI_IRCOMP	Analog	V3P30	not shared	ESPI_IRCOMP	I,O	-	D
BV66	ESPI_RST_N	CMOS-HV	V3P30	Default	LPC_CLKOUT[1]			
				Func 0 GPIO	GPIO[70]	SW	SW	D
				Func 2	LPC_CLKOUT[1]	O	20K PD	D
BG48	FLEX_CLK_SE[0]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PD	D
				Default	FLEX_CLK_SE[0]	O	-	D
				Func 0 GPIO	GPIO[121]	SW	SW	D
				Func 1	FLEX_CLK_SE[0]	O	-	D
CA48	FLEX_CLK_SE[1]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[122]	O	-	D
				Func 0 GPIO	GPIO[122]	SW	SW	D
				Func 1	FLEX_CLK_SE[1]	O	-	D
BF70	GPIO[0]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[0]	O	-	D
				Func 0 GPIO	GPIO[0]	SW	SW	D
				Func 1	Reserved	I,O	-	
				Func 2	FAN_TACH[2]	I	-	D
				Func 3	ADR_COMPLETE	I,O	-	D
BK69	GPIO[1]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[1]	O	-	D
				Func 0 GPIO	GPIO[1]	SW	SW	D
				Func 1	LAN_MDC	O	-	D
				Func 2	Reserved	I,O	-	
				Func 3	FAN_TACH[0]	I	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 17 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BK71	GPIO[2]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[2]	O	-	D
				Func 0 GPIO	GPIO[2]	SW	SW	D
				Func 1	LAN_MDIO	I,O-OD	-	D
				Func 2	Reserved	I,O	-	
				Func 3	FAN_TACH[1]	I	-	D
BN44	GPIO[3]	CMOS-MV	V1P80	Strap Sampling	Top Swap Override	I	20K PD	D
				Default	GPIO[3]	O	-	D
				Func 0 GPIO	GPIO[3]	SW	SW	D
				Func 1	Reserved	I,O	-	
BH50	GPIO[4]	CMOS-HV	V3P30	Default	GPIO[4]	O	-	D
				Func 0 GPIO	GPIO[4]	SW	SW	D
				Func 1	Reserved	I,O	-	
				Func 2	FAN_PWM[0]	O-OD	-	D
				Func 3	LAN1_PORT1_LED[1]	O-OD	-	D
BL48	GPIO[5]	CMOS-HV	V3P30	Default	GPIO[5]	I	-	D
				Func 0 GPIO	GPIO[5]	SW	SW	D
				Func 1	SMB_IE_SMT0_CLK	I,O-OD	-	D
BE52	GPIO[6]	CMOS-HV	V3P30	Default	GPIO[6]	I	-	D
				Func 0 GPIO	GPIO[6]	SW	SW	D
				Func 1	SMB_IE_SMT0_DATA	I,O-OD	-	D
BH46	GPIO[7]	CMOS-HV	V3P30	Default	GPIO[7]	I	-	D
				Func 0 GPIO	GPIO[7]	SW	SW	D
				Func 1	SMB_IE_SMT0_ALRT_N	I,O-OD	-	D
BY55	GPIO[8]	CMOS-HV	V3P30	Default	GPIO[8]	I	-	D
				Func 0 GPIO	GPIO[8]	SW	SW	D
				Func 1	Reserved	I,O	-	
				Func 2	FAN_PWM[1]	O-OD	-	D
				Func 3	SMB_ME_SMT1_DATA	I,O-OD	-	D
CA54	GPIO[9]	CMOS-HV	V3P30	Default	GPIO[9]	I	-	D
				Func 0 GPIO	GPIO[9]	SW	SW	D
				Func 1	Reserved	I,O	-	
				Func 2	FAN_PWM[2]	O-OD	-	D
				Func 3	SMB_ME_SMT1_CLK	I,O-OD	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 18 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BN56	GPIO[12]	CMOS-HV	V3P30	Strap Sampling	No TCO Reboot Enable	I	20K PD	D
				Default	GPIO[12]	O	-	D
				Func 0 GPIO	GPIO[12]	SW	SW	D
				Func 1	SPI_TPM_CS_N	I,O	-	D
BM38	GPIO[150]	CMOS-LV	V1P05	Default	GPIO[150]	I	-	D
				Func 0 GPIO	GPIO[150]	SW	SW	D
				Func 1	Reserved	I	-	
BW37	GPIO[151]	CMOS-LV	V1P05	Default	GPIO[151]	I	-	D
				Func 0 GPIO	GPIO[151]	SW	SW	D
				Func 1	Reserved	I	-	
CA37	GPIO[152]	CMOS-LV	V1P05	Default	GPIO[152]	I	-	D
				Func 0 GPIO	GPIO[152]	SW	SW	D
				Func 1	Reserved	I,O-OD	-	
BD42	HSHV_IRCOMP	HSIO	V3P30	not shared	HSHV_IRCOMP	I,O	-	D
AC56	HSIO_COMPREF_DN	HSIO	V1P05	not shared	HSIO_COMPREF_DN	O, Diff	-	D
AD54	HSIO_COMPREF_DP	HSIO	V1P05	not shared	HSIO_COMPREF_DP	O, Diff	-	D
C52	HSIO_RX_DN[0]	HSIO	V1P05	not shared	HSIO_RX_DN[0]	I, Diff	-	D
C54	HSIO_RX_DN[1]	HSIO	V1P05	not shared	HSIO_RX_DN[1]	I, Diff	-	D
C57	HSIO_RX_DN[2]	HSIO	V1P05	not shared	HSIO_RX_DN[2]	I, Diff	-	D
C59	HSIO_RX_DN[3]	HSIO	V1P05	not shared	HSIO_RX_DN[3]	I, Diff	-	D
C61	HSIO_RX_DN[4]	HSIO	V1P05	not shared	HSIO_RX_DN[4]	I, Diff	-	D
C63	HSIO_RX_DN[5]	HSIO	V1P05	not shared	HSIO_RX_DN[5]	I, Diff	-	D
C65	HSIO_RX_DN[6]	HSIO	V1P05	not shared	HSIO_RX_DN[6]	I, Diff	-	D
F69	HSIO_RX_DN[7]	HSIO	V1P05	not shared	HSIO_RX_DN[7]	I, Diff	-	D
H69	HSIO_RX_DN[8]	HSIO	V1P05	not shared	HSIO_RX_DN[8]	I, Diff	-	D
L70	HSIO_RX_DN[9]	HSIO	V1P05	not shared	HSIO_RX_DN[9]	I, Diff	-	D
N70	HSIO_RX_DN[10]	HSIO	V1P05	not shared	HSIO_RX_DN[10]	I, Diff	-	D
R70	HSIO_RX_DN[11]	HSIO	V1P05	not shared	HSIO_RX_DN[11]	I, Diff	-	D
V70	HSIO_RX_DN[12]	HSIO	V1P05	not shared	HSIO_RX_DN[12]	I, Diff	-	D
Y70	HSIO_RX_DN[13]	HSIO	V1P05	not shared	HSIO_RX_DN[13]	I, Diff	-	D
AB70	HSIO_RX_DN[14]	HSIO	V1P05	not shared	HSIO_RX_DN[14]	I, Diff	-	D
AD70	HSIO_RX_DN[15]	HSIO	V1P05	not shared	HSIO_RX_DN[15]	I, Diff	-	D
AF70	HSIO_RX_DN[16]	HSIO	V1P05	not shared	HSIO_RX_DN[16]	I, Diff	-	D
AJ70	HSIO_RX_DN[17]	HSIO	V1P05	not shared	HSIO_RX_DN[17]	I, Diff	-	D
AL70	HSIO_RX_DN[18]	HSIO	V1P05	not shared	HSIO_RX_DN[18]	I, Diff	-	D
AN70	HSIO_RX_DN[19]	HSIO	V1P05	not shared	HSIO_RX_DN[19]	I, Diff	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 19 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
A52	HSIO_RX_DP[0]	HSIO	V1P05	not shared	HSIO_RX_DP[0]	I, Diff	-	D
A54	HSIO_RX_DP[1]	HSIO	V1P05	not shared	HSIO_RX_DP[1]	I, Diff	-	D
A57	HSIO_RX_DP[2]	HSIO	V1P05	not shared	HSIO_RX_DP[2]	I, Diff	-	D
A59	HSIO_RX_DP[3]	HSIO	V1P05	not shared	HSIO_RX_DP[3]	I, Diff	-	D
A61	HSIO_RX_DP[4]	HSIO	V1P05	not shared	HSIO_RX_DP[4]	I, Diff	-	D
A63	HSIO_RX_DP[5]	HSIO	V1P05	not shared	HSIO_RX_DP[5]	I, Diff	-	D
C67	HSIO_RX_DP[6]	HSIO	V1P05	not shared	HSIO_RX_DP[6]	I, Diff	-	D
G67	HSIO_RX_DP[7]	HSIO	V1P05	not shared	HSIO_RX_DP[7]	I, Diff	-	D
J70	HSIO_RX_DP[8]	HSIO	V1P05	not shared	HSIO_RX_DP[8]	I, Diff	-	D
L72	HSIO_RX_DP[9]	HSIO	V1P05	not shared	HSIO_RX_DP[9]	I, Diff	-	D
N72	HSIO_RX_DP[10]	HSIO	V1P05	not shared	HSIO_RX_DP[10]	I, Diff	-	D
R72	HSIO_RX_DP[11]	HSIO	V1P05	not shared	HSIO_RX_DP[11]	I, Diff	-	D
V72	HSIO_RX_DP[12]	HSIO	V1P05	not shared	HSIO_RX_DP[12]	I, Diff	-	D
Y72	HSIO_RX_DP[13]	HSIO	V1P05	not shared	HSIO_RX_DP[13]	I, Diff	-	D
AB72	HSIO_RX_DP[14]	HSIO	V1P05	not shared	HSIO_RX_DP[14]	I, Diff	-	D
AD72	HSIO_RX_DP[15]	HSIO	V1P05	not shared	HSIO_RX_DP[15]	I, Diff	-	D
AF72	HSIO_RX_DP[16]	HSIO	V1P05	not shared	HSIO_RX_DP[16]	I, Diff	-	D
AJ72	HSIO_RX_DP[17]	HSIO	V1P05	not shared	HSIO_RX_DP[17]	I, Diff	-	D
AL72	HSIO_RX_DP[18]	HSIO	V1P05	not shared	HSIO_RX_DP[18]	I, Diff	-	D
AN72	HSIO_RX_DP[19]	HSIO	V1P05	not shared	HSIO_RX_DP[19]	I, Diff	-	D
G48	HSIO_TX_DN[0]	HSIO	V1P05	not shared	HSIO_TX_DN[0]	O, Diff	-	D
K50	HSIO_TX_DN[1]	HSIO	V1P05	not shared	HSIO_TX_DN[1]	O, Diff	-	D
J52	HSIO_TX_DN[2]	HSIO	V1P05	not shared	HSIO_TX_DN[2]	O, Diff	-	D
H54	HSIO_TX_DN[3]	HSIO	V1P05	not shared	HSIO_TX_DN[3]	O, Diff	-	D
G56	HSIO_TX_DN[4]	HSIO	V1P05	not shared	HSIO_TX_DN[4]	O, Diff	-	D
K58	HSIO_TX_DN[5]	HSIO	V1P05	not shared	HSIO_TX_DN[5]	O, Diff	-	D
J59	HSIO_TX_DN[6]	HSIO	V1P05	not shared	HSIO_TX_DN[6]	O, Diff	-	D
H61	HSIO_TX_DN[7]	HSIO	V1P05	not shared	HSIO_TX_DN[7]	O, Diff	-	D
J63	HSIO_TX_DN[8]	HSIO	V1P05	not shared	HSIO_TX_DN[8]	O, Diff	-	D
J66	HSIO_TX_DN[9]	HSIO	V1P05	not shared	HSIO_TX_DN[9]	O, Diff	-	D
M63	HSIO_TX_DN[10]	HSIO	V1P05	not shared	HSIO_TX_DN[10]	O, Diff	-	D
P66	HSIO_TX_DN[11]	HSIO	V1P05	not shared	HSIO_TX_DN[11]	O, Diff	-	D
T63	HSIO_TX_DN[12]	HSIO	V1P05	not shared	HSIO_TX_DN[12]	O, Diff	-	D
V66	HSIO_TX_DN[13]	HSIO	V1P05	not shared	HSIO_TX_DN[13]	O, Diff	-	D
Y63	HSIO_TX_DN[14]	HSIO	V1P05	not shared	HSIO_TX_DN[14]	O, Diff	-	D
AC66	HSIO_TX_DN[15]	HSIO	V1P05	not shared	HSIO_TX_DN[15]	O, Diff	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 20 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
AE63	HSIO_TX_DN[16]	HSIO	V1P05	not shared	HSIO_TX_DN[16]	O, Diff	-	D
AG66	HSIO_TX_DN[17]	HSIO	V1P05	not shared	HSIO_TX_DN[17]	O, Diff	-	D
AJ63	HSIO_TX_DN[18]	HSIO	V1P05	not shared	HSIO_TX_DN[18]	O, Diff	-	D
AL66	HSIO_TX_DN[19]	HSIO	V1P05	not shared	HSIO_TX_DN[19]	O, Diff	-	D
J48	HSIO_TX_DP[0]	HSIO	V1P05	not shared	HSIO_TX_DP[0]	O, Diff	-	D
M48	HSIO_TX_DP[1]	HSIO	V1P05	not shared	HSIO_TX_DP[1]	O, Diff	-	D
M52	HSIO_TX_DP[2]	HSIO	V1P05	not shared	HSIO_TX_DP[2]	O, Diff	-	D
G52	HSIO_TX_DP[3]	HSIO	V1P05	not shared	HSIO_TX_DP[3]	O, Diff	-	D
J56	HSIO_TX_DP[4]	HSIO	V1P05	not shared	HSIO_TX_DP[4]	O, Diff	-	D
M56	HSIO_TX_DP[5]	HSIO	V1P05	not shared	HSIO_TX_DP[5]	O, Diff	-	D
M59	HSIO_TX_DP[6]	HSIO	V1P05	not shared	HSIO_TX_DP[6]	O, Diff	-	D
G59	HSIO_TX_DP[7]	HSIO	V1P05	not shared	HSIO_TX_DP[7]	O, Diff	-	D
G63	HSIO_TX_DP[8]	HSIO	V1P05	not shared	HSIO_TX_DP[8]	O, Diff	-	D
H65	HSIO_TX_DP[9]	HSIO	V1P05	not shared	HSIO_TX_DP[9]	O, Diff	-	D
K65	HSIO_TX_DP[10]	HSIO	V1P05	not shared	HSIO_TX_DP[10]	O, Diff	-	D
N65	HSIO_TX_DP[11]	HSIO	V1P05	not shared	HSIO_TX_DP[11]	O, Diff	-	D
R65	HSIO_TX_DP[12]	HSIO	V1P05	not shared	HSIO_TX_DP[12]	O, Diff	-	D
U65	HSIO_TX_DP[13]	HSIO	V1P05	not shared	HSIO_TX_DP[13]	O, Diff	-	D
W65	HSIO_TX_DP[14]	HSIO	V1P05	not shared	HSIO_TX_DP[14]	O, Diff	-	D
AA65	HSIO_TX_DP[15]	HSIO	V1P05	not shared	HSIO_TX_DP[15]	O, Diff	-	D
AD65	HSIO_TX_DP[16]	HSIO	V1P05	not shared	HSIO_TX_DP[16]	O, Diff	-	D
AF65	HSIO_TX_DP[17]	HSIO	V1P05	not shared	HSIO_TX_DP[17]	O, Diff	-	D
AH65	HSIO_TX_DP[18]	HSIO	V1P05	not shared	HSIO_TX_DP[18]	O, Diff	-	D
AK65	HSIO_TX_DP[19]	HSIO	V1P05	not shared	HSIO_TX_DP[19]	O, Diff	-	D
W54	ICLKRCOMP	ISCLK	V1P05	not shared	ICLKRCOMP	I,O	-	D
BW50	IERR_N	CMOS-HV	V3P30	Strap Sampling	Flash Security Override	I	20K PD	D
				Default	IERR_N	O	-	D
				Func 0 GPIO	GPIO[108]	SW	SW	D
				Func 1	IERR_N	O	-	D
AJ59	INTRUDER_N	RTC	VRTC	not shared	INTRUDER_N	I	-	D
AV59	LAN0_PORT0_I2C_CLK	CMOS-HV	V3P30	Default	LAN0_PORT0_I2C_CLK	I,O-OD	5K PU	D
				Func 0 GPIO	GPIO[24]	SW	SW	D
				Func 1	LAN0_PORT0_I2C_CLK	I,O-OD	5K PU	D
AV56	LAN0_PORT0_I2C_DATA	CMOS-HV	V3P30	Default	LAN0_PORT0_I2C_DATA	I,O-OD	5K PU	D
				Func 0 GPIO	GPIO[25]	SW	SW	D
				Func 1	LAN0_PORT0_I2C_DATA	I,O-OD	5K PU	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 21 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BE69	LAN0_PORT0_LED[0]	CMOS-HV	V3P30	Default	LAN0_PORT0_LED[0]	O-OD	-	D
				Func 0 GPIO	GPIO[37]	SW	SW	D
				Func 1	LAN0_PORT0_LED[0]	O-OD	-	D
BF72	LAN0_PORT0_LED[1]	CMOS-HV	V3P30	Default	LAN0_PORT0_LED[1]	O-OD	-	D
				Func 0 GPIO	GPIO[38]	SW	SW	D
				Func 1	LAN0_PORT0_LED[1]	O-OD	-	D
U42	LAN0_PORT0_RX_DN	KR	V1P05	not shared	LAN0_PORT0_RX_DN	I, Diff	-	D
R42	LAN0_PORT0_RX_DP	KR	V1P05	not shared	LAN0_PORT0_RX_DP	I, Diff	-	D
AV66	LAN0_PORT0_SDP[0]	CMOS-HV	V3P30	Default	GPIO[14]	O	-	D
				Func 0 GPIO	GPIO[14]	SW	SW	D
				Func 1	LAN0_PORT0_SDP[0]	I,O	-	D
BA71	LAN0_PORT0_SDP[1]	CMOS-HV	V3P30	Default	GPIO[16]	O	-	D
				Func 0 GPIO	GPIO[16]	SW	SW	D
				Func 1	LAN0_PORT0_SDP[1]	I,O	-	D
				Func 2	LAN1_PORT0_I2C_CLK	I,O-OD	-	D
AC59	LAN0_PORT0_SDP[2]	CMOS-HV	V3P30	Default	GPIO[18]	O	-	D
				Func 0 GPIO	GPIO[18]	SW	SW	D
				Func 1	LAN0_PORT0_SDP[2]	I,O	-	D
				Func 2	LAN1_PORT0_SDP[0]	I,O	-	D
BA69	LAN0_PORT0_SDP[3]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[20]	O	-	D
				Func 0 GPIO	GPIO[20]	SW	SW	D
				Func 1	LAN0_PORT0_SDP[3]	I,O	-	D
				Func 2	LAN1_PORT1_I2C_CLK	I,O-OD	-	D
				Func 3	LAN1_PORT0_SDP[1]	I,O	-	D
G40	LAN0_PORT0_TX_DN	KR	V1P05	not shared	LAN0_PORT0_TX_DN	O, Diff	-	D
J40	LAN0_PORT0_TX_DP	KR	V1P05	not shared	LAN0_PORT0_TX_DP	O, Diff	-	D
BB66	LAN0_PORT1_I2C_CLK	CMOS-HV	V3P30	Default	LAN0_PORT1_I2C_CLK	I,O-OD	5K PU	D
				Func 0 GPIO	GPIO[26]	SW	SW	D
				Func 1	LAN0_PORT1_I2C_CLK	I,O-OD	5K PU	D
BC69	LAN0_PORT1_I2C_DATA	CMOS-HV	V3P30	Default	LAN0_PORT1_I2C_DATA	I,O-OD	5K PU	D
				Func 0 GPIO	GPIO[27]	SW	SW	D
				Func 1	LAN0_PORT1_I2C_DATA	I,O-OD	5K PU	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 22 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BA65	LAN0_PORT1_LED[0]	CMOS-HV	V3P30	Default	LAN0_PORT1_LED[0]	O-OD	-	D
				Func 0 GPIO	GPIO[39]	SW	SW	D
				Func 1	LAN0_PORT1_LED[0]	O-OD	-	D
				Func 2	LAN0_PORT0_LED[2]	O-OD	-	D
BG66	LAN0_PORT1_LED[1]	CMOS-HV	V3P30	Default	LAN0_PORT1_LED[1]	O-OD	-	D
				Func 0 GPIO	GPIO[40]	SW	SW	D
				Func 1	LAN0_PORT1_LED[1]	O-OD	-	D
				Func 2	LAN0_PORT0_LED[3]	O-OD	-	D
R46	LAN0_PORT1_RX_DN	KR	V1P05	not shared	LAN0_PORT1_RX_DN	I, Diff	-	D
U46	LAN0_PORT1_RX_DP	KR	V1P05	not shared	LAN0_PORT1_RX_DP	I, Diff	-	D
AY66	LAN0_PORT1_SDP[0]	CMOS-HV	V3P30	Default	GPIO[15]	O	-	D
				Func 0 GPIO	GPIO[15]	SW	SW	D
				Func 1	LAN0_PORT1_SDP[0]	I,O	-	D
BB72	LAN0_PORT1_SDP[1]	CMOS-HV	V3P30	Default	GPIO[17]	O	-	D
				Func 0 GPIO	GPIO[17]	SW	SW	D
				Func 1	LAN0_PORT1_SDP[1]	I,O	-	D
				Func 2	LAN1_PORT0_I2C_DATA	I,O-OD	-	D
AU65	LAN0_PORT1_SDP[2]	CMOS-HV	V3P30	Default	GPIO[19]	O	-	D
				Func 0 GPIO	GPIO[19]	SW	SW	D
				Func 1	LAN0_PORT1_SDP[2]	I,O	-	D
				Func 2	LAN1_PORT1_SDP[0]	I,O	-	D
W58	LAN0_PORT1_SDP[3]	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[21]	O	-	D
				Func 0 GPIO	GPIO[21]	SW	SW	D
				Func 1	LAN0_PORT1_SDP[3]	I,O	-	D
				Func 2	LAN1_PORT1_I2C_DATA	I,O-OD	-	D
				Func 3	LAN1_PORT1_SDP[1]	I,O	-	D
G44	LAN0_PORT1_TX_DN	KR	V1P05	not shared	LAN0_PORT1_TX_DN	O, Diff	-	D
J44	LAN0_PORT1_TX_DP	KR	V1P05	not shared	LAN0_PORT1_TX_DP	O, Diff	-	D
AA50	LAN0_RBIAS	KR	V1P05	not shared	LAN0_RBIAS	I,O	-	D
AY70	LAN1_PORT0_LED[0]	CMOS-HV	V3P30	Default	LAN1_PORT0_LED[0]	O-OD	-	D
				Func 0 GPIO	GPIO[22]	SW	SW	D
				Func 1	LAN1_PORT0_LED[0]	O-OD	-	D
AY72	LAN1_PORT0_LED[1]	CMOS-HV	V3P30	Default	LAN1_PORT0_LED[1]	O-OD	-	D
				Func 0 GPIO	GPIO[23]	SW	SW	D
				Func 1	LAN1_PORT0_LED[1]	O-OD	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 23 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
T37	LAN1_PORT0_RX_DN	KR	V1P05	not shared	LAN1_PORT0_RX_DN	I, Diff	-	D
P37	LAN1_PORT0_RX_DP	KR	V1P05	not shared	LAN1_PORT0_RX_DP	I, Diff	-	D
G33	LAN1_PORT0_TX_DN	KR	V1P05	not shared	LAN1_PORT0_TX_DN	O, Diff	-	D
J33	LAN1_PORT0_TX_DP	KR	V1P05	not shared	LAN1_PORT0_TX_DP	O, Diff	-	D
P40	LAN1_PORT1_RX_DN	KR	V1P05	not shared	LAN1_PORT1_RX_DN	I, Diff	-	D
T40	LAN1_PORT1_RX_DP	KR	V1P05	not shared	LAN1_PORT1_RX_DP	I, Diff	-	D
G37	LAN1_PORT1_TX_DN	KR	V1P05	not shared	LAN1_PORT1_TX_DN	O, Diff	-	D
J37	LAN1_PORT1_TX_DP	KR	V1P05	not shared	LAN1_PORT1_TX_DP	O, Diff	-	D
Y39	LAN1_RBIAS	KR	V1P05	not shared	LAN1_RBIAS	I,O	-	D
BN52	MCERR_N	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PD	D
				Default	MCERR_N	O	-	D
				Func 0 GPIO	GPIO[109]	SW	SW	D
				Func 1	MCERR_N	O	-	D
BL70	MEMHOT_N	CMOS-LV	V1P05	Default	MEMHOT_N	I	20K PU	D
				Func 0 GPIO	GPIO[52]	SW	SW	D
				Func 1	MEMHOT_N	I	20K PU	D
AU58	NCSI_ARB_IN	CMOS-HV	V3P30	Default	GPIO[32]	I	20K PD	D
				Func 0 GPIO	GPIO[32]	SW	SW	D
				Func 1	Reserved	I	20K PD	
				Func 2	NCSI_ARB_IN	I	20K PD	D
AV63	NCSI_ARB_OUT	CMOS-HV	V3P30	Default	GPIO[36]	I	-	D
				Func 0 GPIO	GPIO[36]	SW	SW	D
				Func 2	NCSI_ARB_OUT	O	-	D
AY63	NCSI_CLK_IN	CMOS-HV	V3P30	Default	GPIO[29]	I	20K PU	D
				Func 0 GPIO	GPIO[29]	SW	SW	D
				Func 2	NCSI_CLK_IN	I	20K PU	D
BD65	NCSI_CRS_DV	CMOS-HV	V3P30	Default	GPIO[31]	I	-	D
				Func 0 GPIO	GPIO[31]	SW	SW	D
				Func 2	NCSI_CRS_DV	O-Tri	-	D
AY59	NCSI_RXD[0]	CMOS-HV	V3P30	Default	GPIO[28]	I	20K PU	D
				Func 0 GPIO	GPIO[28]	SW	SW	D
				Func 2	NCSI_RXD[0]	O-Tri	20K PU	D
BD72	NCSI_RXD[1]	CMOS-HV	V3P30	Default	GPIO[30]	I	20K PU	D
				Func 0 GPIO	GPIO[30]	SW	SW	D
				Func 2	NCSI_RXD[1]	O-Tri	20K PU	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 24 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BD70	NCSI_TX_EN	CMOS-HV	V3P30	Default	GPIO[33]	I	-	D
				Func 0 GPIO	GPIO[33]	SW	SW	D
				Func 2	NCSI_TX_EN	I	-	D
BE66	NCSI_TXD[0]	CMOS-HV	V3P30	Default	GPIO[34]	I	-	D
				Func 0 GPIO	GPIO[34]	SW	SW	D
				Func 2	NCSI_TXD[0]	I	-	D
AL56	NCSI_TXD[1]	CMOS-HV	V3P30	Default	GPIO[35]	I	-	D
				Func 0 GPIO	GPIO[35]	SW	SW	D
				Func 2	NCSI_TXD[1]	I	-	D
AP56	PCIE_CLKREQ_N[0]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[0]	I,O-OD	-	D
				Func 0 GPIO	GPIO[41]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[0]	I,O-OD	-	D
BA58	PCIE_CLKREQ_N[1]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[1]	I,O-OD	-	D
				Func 0 GPIO	GPIO[42]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[1]	I,O-OD	-	D
BH71	PCIE_CLKREQ_N[2]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[2]	I,O-OD	-	D
				Func 0 GPIO	GPIO[43]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[2]	I,O-OD	-	D
BJ66	PCIE_CLKREQ_N[3]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[3]	I,O-OD	-	D
				Func 0 GPIO	GPIO[44]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[3]	I,O-OD	-	D
BD61	PCIE_CLKREQ_N[4]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[4]	I,O-OD	-	D
				Func 0 GPIO	GPIO[45]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[4]	I,O-OD	-	D
				Func 2	FAN_TACH[3]	I	-	D
BW52	PCIE_CLKREQ_N[5]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[5]	I,O-OD	-	D
				Func 0 GPIO	GPIO[98]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[5]	I,O-OD	-	D
				Func 2	UART2_RTS	O	-	D
				Func 3	UART0_RTS	O	-	D
BV51	PCIE_CLKREQ_N[6]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[6]	I,O-OD	-	D
				Func 0 GPIO	GPIO[99]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[6]	I,O-OD	-	D
				Func 2	UART2_RXD	I	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 25 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BK58	PCIE_CLKREQ_N[7]	CMOS-HV	V3P30	Default	PCIE_CLKREQ_N[7]	I,O-OD	-	D
				Func 0 GPIO	GPIO[100]	SW	SW	D
				Func 1	PCIE_CLKREQ_N[7]	I,O-OD	-	D
				Func 2	UART2_TXD	O	-	D
				Func 3	LAN1_PORT1_LED[0]	O-OD	-	D
BL63	PMU_PLTRST_N	CMOS-HV	V3P30	Default	PMU_PLTRST_N	O	-	D
				Func 0 GPIO	GPIO[87]	SW	SW	D
				Func 1	PMU_PLTRST_N	O	-	D
CA59	PMU_PWRBTN_N	CMOS-HV	V3P30	Default	PMU_PWRBTN_N	I	20K PU	D
				Func 0 GPIO	GPIO[85]	SW	SW	D
				Func 1	PMU_PWRBTN_N	I	20K PU	D
BL59	PMU_RESETBUTTON_N	CMOS-HV	V3P30	Default	PMU_RESETBUTTON_N	I	20K PU	D
				Func 0 GPIO	GPIO[86]	SW	SW	D
				Func 1	PMU_RESETBUTTON_N	I	20K PU	D
BK65	PMU_SLP_S3_N	CMOS-HV	V3P30	Default	PMU_SLP_S3_N	O	-	D
				Func 0 GPIO	GPIO[83]	SW	SW	D
				Func 1	PMU_SLP_S3_N	O	-	D
BW59	PMU_SLP_S45_N	CMOS-HV	V3P30	Default	PMU_SLP_S45_N	O	-	D
				Func 0 GPIO	GPIO[82]	SW	SW	D
				Func 1	PMU_SLP_S45_N	O	-	D
BG59	PMU_SUSCLK	CMOS-HV	V3P30	Default	PMU_SUSCLK	O	-	D
				Func 0 GPIO	GPIO[80]	SW	SW	D
				Func 1	PMU_SUSCLK	O	-	D
BR61	PMU_WAKE_N	CMOS-HV	V3P30	Default	PMU_WAKE_N	I	20K PU	D
				Func 0 GPIO	GPIO[84]	SW	SW	D
				Func 1	PMU_WAKE_N	I	20K PU	D
BM71	PROCHOT_N	CMOS-LV	V1P05	Default	PROCHOT_N	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[51]	SW	SW	D
				Func 1	PROCHOT_N	I,O-OD	20K PU	D
AE59	RSMRST_N	RTC	VRTC	not shared	RSMRST_N	I	-	D
H35	RSVD_H35	n/a	-	not shared	RSVD_H35	O	-	D
H42	RSVD_H42	n/a	-	not shared	RSVD_H42	O	-	D
K35	RSVD_K35	n/a	-	not shared	RSVD_K35	O	-	D
K42	RSVD_K42	n/a	-	not shared	RSVD_K42	O	-	D
P33	RSVD_P33	n/a	-	not shared	RSVD_P33	I,O	-	D
R31	RSVD_R31	n/a	-	not shared	RSVD_R31	O	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 26 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
R50	RSVD_R50	n/a	-	not shared	RSVD_R50	I	-	D
R54	RSVD_R54	n/a	-	not shared	RSVD_R54	O, Diff	-	D
R58	RSVD_R58	n/a	-	not shared	RSVD_R58	O, Diff	-	D
T33	RSVD_T33	n/a	-	not shared	RSVD_T33	I,O	-	D
T56	RSVD_T56	n/a	-	not shared	RSVD_T56	O, Diff	-	D
T59	RSVD_T59	n/a	-	not shared	RSVD_T59	O, Diff	-	D
U31	RSVD_U31	n/a	-	not shared	RSVD_U31	O	-	D
W50	RSVD_W50	n/a	-	not shared	RSVD_W50	I,O	-	D
Y48	RSVD_Y48	n/a	-	not shared	RSVD_Y48	I,O	-	D
AA29	RSVD_AA29	n/a	-	not shared	RSVD_AA29	O	-	D
AD58	RSVD_AD58	n/a	-	not shared	RSVD_AD58	I,O	-	D
AH20	RSVD_AH20	n/a	-	not shared	RSVD_AH20	O, Diff	-	D
AH54	RSVD_AH54	n/a	-	not shared	RSVD_AH54	I	-	D
AJ22	RSVD_AJ22	n/a	-	not shared	RSVD_AJ22	O, Diff	-	D
AK20	RSVD_AK20	n/a	-	not shared	RSVD_AK20	O, Diff	-	D
AL22	RSVD_AL22	n/a	-	not shared	RSVD_AL22	O, Diff	-	D
AL59	RSVD_AL59	n/a	-	not shared	RSVD_AL59	I	-	D
AN20	RSVD_AN20	n/a	-	not shared	RSVD_AN20	O	-	D
AP22	RSVD_AP22	n/a	-	not shared	RSVD_AP22	O	-	D
AW30	RSVD_AW30	n/a	-	not shared	RSVD_AW30	O	-	D
BA24	RSVD_BA24	n/a	-	not shared	RSVD_BA24	I,O	-	D
BA26	RSVD_BA26	n/a	-	not shared	RSVD_BA26	I,O	-	D
BA29	RSVD_BA29	n/a	-	not shared	RSVD_BA29	O	-	D
BB29	RSVD_BB29	n/a	-	not shared	RSVD_BB29	O	-	D
BF38	RSVD_BF38	n/a	-	not shared	RSVD_BF38	O	-	D
BG40	RSVD_BG40	n/a	-	not shared	RSVD_BG40	I	-	D
BH38	RSVD_BH38	n/a	-	not shared	RSVD_BH38	I,O	-	D
BK38	RSVD_BK38	n/a	-	not shared	RSVD_BK38	I,O	-	D
BY58	RSVD_BY58	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	RSVD_BY58	O	-	D
				Func 0 GPIO	GPIO[89]	SW	SW	D
				Func 1	RSVD_BY58	O	-	
AG59	RTC_X1_PAD	Analog	V1P80	not shared	RTC_X1_PAD	I,O	-	D
AH58	RTC_X2_PAD	Analog	V1P80	not shared	RTC_X2_PAD	I,O	-	D
AJ56	RTEST_N	RTC	VRTC	not shared	RTEST_N	I	-	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 27 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
CA57	SATA_PDETECT[0]	CMOS-HV	V3P30	Default	SATA_PDETECT[0]	I	-	D
				Func 0 GPIO	GPIO[92]	SW	SW	D
				Func 1	SATA_PDETECT[0]	I	-	D
				Func 2	SATA0_SLD	O-OD	-	D
BN63	SATA_PDETECT[1]	CMOS-HV	V3P30	Default	SATA_PDETECT[1]	I	-	D
				Func 0 GPIO	GPIO[93]	SW	SW	D
				Func 1	SATA_PDETECT[1]	I	-	D
				Func 2	SATA1_SLD	O-OD	-	D
BR65	SATA0_LED_N	CMOS-HV	V3P30	Default	SATA0_LED_N	O-OD	-	D
				Func 0 GPIO	GPIO[90]	SW	SW	D
				Func 1	SATA0_LED_N	O-OD	-	D
				Func 2	SATA0_SCLK	O-OD	-	D
BU57	SATA0_SDOUT	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[94]	O	-	D
				Func 0 GPIO	GPIO[94]	SW	SW	D
				Func 1	UART1_RTS	O	-	D
				Func 2	SATA0_SDOUT	O-OD	-	D
				Func 3	UART_IE_RTS	O	-	D
BV55	SATA1_LED_N	CMOS-HV	V3P30	Default	SATA1_LED_N	O-OD	-	D
				Func 0 GPIO	GPIO[91]	SW	SW	D
				Func 1	SATA1_LED_N	O-OD	-	D
				Func 2	SATA1_SCLK	O-OD	-	D
BW54	SATA1_SDOUT	CMOS-HV	V3P30	Default	GPIO[95]	O	-	D
				Func 0 GPIO	GPIO[95]	SW	SW	D
				Func 1	UART1_CTS	I	-	D
				Func 2	SATA1_SDOUT	O-OD	-	D
				Func 3	UART_IE_CTS	I	-	D
BR50	SMB_HOST_CLK	CMOS-HV	V3P30	Default	SMB_HOST_CLK	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[114]	SW	SW	D
				Func 1	SMB_HOST_CLK	I,O-OD	20K PU	D
				Func 2	SMB_ME_SMT2_CLK	I,O-OD	20K PU	D
				Func 3	SMB_IE_SMT1_CLK	I,O-OD	20K PU	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 28 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BK50	SMB_HOST_DATA	CMOS-HV	V3P30	Default	SMB_HOST_DATA	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[113]	SW	SW	D
				Func 1	SMB_HOST_DATA	I,O-OD	20K PU	D
				Func 2	SMB_ME_SMT2_DATA	I,O-OD	20K PU	D
				Func 3	SMB_IE_SMT1_DATA	I,O-OD	20K PU	D
BN66	SMB_LAN_ALRT_N	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[13]	O	-	D
				Func 0 GPIO	GPIO[13]	SW	SW	D
				Func 1	UART2_CTS	I	-	D
				Func 2	UART0_CTS	I	-	D
				Func 3	SMB_LAN_ALRT_N	I,O-OD	-	D
BH54	SMB_LAN_CLK	CMOS-HV	V3P30	Default	GPIO[103]	I	20K PU	D
				Func 0 GPIO	GPIO[103]	SW	SW	D
				Func 1	CPU_RESET_N	O	20K PU	D
				Func 2	FAN_PWM[3]	O-OD	20K PU	D
				Func 3	SMB_LAN_CLK	I,O-OD	20K PU	D
BK54	SMB_LAN_DATA	CMOS-HV	V3P30	Default	GPIO[104]	I	20K PU	D
				Func 0 GPIO	GPIO[104]	SW	SW	D
				Func 3	SMB_LAN_DATA	I,O-OD	20K PU	D
BW48	SMB_LEG_ALRT_N	CMOS-HV	V3P30	Default	SMB_LEG_ALRT_N	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[112]	SW	SW	D
				Func 1	SMB_LEG_ALRT_N	I,O-OD	20K PU	D
BY51	SMB_LEG_CLK	CMOS-HV	V3P30	Default	SMB_LEG_CLK	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[110]	SW	SW	D
				Func 1	SMB_LEG_CLK	I,O-OD	20K PU	D
BV49	SMB_LEG_DATA	CMOS-HV	V3P30	Default	SMB_LEG_DATA	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[111]	SW	SW	D
				Func 1	SMB_LEG_DATA	I,O-OD	20K PU	D
BG52	SMB_ME_SMT0_ALRT_N	CMOS-HV	V3P30	Default	SMB_ME_SMT0_ALRT_N	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[119]	SW	SW	D
				Func 1	SMB_ME_SMT0_ALRT_N	I,O-OD	20K PU	D
BR46	SMB_ME_SMT0_CLK	CMOS-HV	V3P30	Default	SMB_ME_SMT0_CLK	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[118]	SW	SW	D
				Func 1	SMB_ME_SMT0_CLK	I,O-OD	20K PU	D
				Func 2	SMB_IE_SMT2_CLK	I,O-OD	20K PU	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 29 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BV47	SMB_ME_SMT0_DATA	CMOS-HV	V3P30	Default	SMB_ME_SMT0_DATA	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[117]	SW	SW	D
				Func 1	SMB_ME_SMT0_DATA	I,O-OD	20K PU	D
				Func 2	SMB_IE_SMT2_DATA	I,O-OD	20K PU	D
BR54	SMB_PECI_CLK	CMOS-HV	V3P30	Default	SMB_PECI_CLK	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[116]	SW	SW	D
				Func 1	SMB_PECI_CLK	I,O-OD	20K PU	D
BY49	SMB_PECI_DATA	CMOS-HV	V3P30	Default	SMB_PECI_DATA	I,O-OD	20K PU	D
				Func 0 GPIO	GPIO[115]	SW	SW	D
				Func 1	SMB_PECI_DATA	I,O-OD	20K PU	D
CA61	SPI_CLK	CMOS-HV	V3P30	Default	SPI_CLK	I,O	20K PU or 20K PD	D
				Func 0 GPIO	GPIO[78]	SW	SW	D
				Func 1	SPI_CLK	I,O	20K PU or 20K PD	D
BG56	SPI_CS_N[0]	CMOS-HV	V3P30	Default	SPI_CS_N[0]	I,O	20K PU	D
				Func 0 GPIO	GPIO[72]	SW	SW	D
				Func 1	SPI_CS_N[0]	I,O	20K PU	D
BL66	SPI_CS_N[1]	CMOS-HV	V3P30	Default	SPI_CS_N[1]	I,O	20K PU	D
				Func 0 GPIO	GPIO[73]	SW	SW	D
				Func 1	SPI_CS_N[1]	I,O	20K PU	D
BH61	SPI_IO[2]	CMOS-HV	V3P30	Default	SPI_IO[2]	I,O	20K PU	D
				Func 0 GPIO	GPIO[76]	SW	SW	D
				Func 1	SPI_IO[2]	I,O	20K PU	D
BW61	SPI_IO[3]	CMOS-HV	V3P30	Default	SPI_IO[3]	I,O	20K PU	D
				Func 0 GPIO	GPIO[77]	SW	SW	D
				Func 1	SPI_IO[3]	I,O	20K PU	D
BV62	SPI_MISO_IO[1]	CMOS-HV	V3P30	Default	SPI_MISO_IO[1]	I,O	20K PU	D
				Func 0 GPIO	GPIO[75]	SW	SW	D
				Func 1	SPI_MISO_IO[1]	I,O	20K PU	D
BU63	SPI_MOSI_IO[0]	CMOS-HV	V3P30	Default	SPI_MOSI_IO[0]	I,O	20K PU or 20K PD	D
				Func 0 GPIO	GPIO[74]	SW	SW	D
				Func 1	SPI_MOSI_IO[0]	I,O	20K PU or 20K PD	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 30 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
Y59	SRTCRST_N	RTC	VRTC	not shared	SRTCRST_N	I	-	D
BV58	SUS_STAT_N	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	SUS_STAT_N	O	-	D
				Func 0 GPIO	GPIO[88]	SW	SW	D
				Func 1	SUS_STAT_N	O	-	D
BH58	SUSPWRDNACK	CMOS-HV	V3P30	Default	SUSPWRDNACK	O	-	D
				Func 0 GPIO	GPIO[79]	SW	SW	D
				Func 1	SUSPWRDNACK	O	-	D
BA54	SVID_ALERT_N	CMOS-LV	V1P05	Default	SVID_ALERT_N	I	-	D
				Func 0 GPIO	GPIO[47]	SW	SW	D
				Func 1	SVID_ALERT_N	I	-	D
BE59	SVID_CLK	CMOS-LV	V1P05	Default	SVID_CLK	O-OD	-	D
				Func 0 GPIO	GPIO[49]	SW	SW	D
				Func 1	SVID_CLK	O-OD	-	D
BE56	SVID_DATA	CMOS-LV	V1P05	Default	SVID_DATA	I,O-OD	-	D
				Func 0 GPIO	GPIO[48]	SW	SW	D
				Func 1	SVID_DATA	I,O-OD	-	D
BN40	TCK	CMOS-LV	V1P05	Default	TCK	I	20K PD	D
				Func 0 GPIO	Cannot be a Customer GPIO	-	-	-
				Func 1	TCK	I	20K PD	D
BG44	TDI	CMOS-LV	V1P05	Default	TDI	I	20K PU	D
				Func 0 GPIO	Cannot be a Customer GPIO	-	-	-
				Func 1	TDI	I	20K PU	D
BV38	TDO	CMOS-LV	V1P05	Default	TDO	I,O-OD	-	D
				Func 0 GPIO	Cannot be a Customer GPIO	-	-	-
				Func 1	TDO	I,O-OD	-	D
BA61	THERMTRIP_N	CMOS-LV	V1P05	Default	THERMTRIP_N	O-OD	20K PU	D
				Func 0 GPIO	GPIO[50]	SW	SW	D
				Func 1	THERMTRIP_N	O-OD	20K PU	D
BW39	TMS	CMOS-LV	V1P05	Default	TMS	I	20K PU	D
				Func 0 GPIO	Cannot be a Customer GPIO	-	-	-
				Func 1	TMS	I	20K PU	D
BL40	TRST_N	CMOS-LV	V1P05	Default	TRST_N	I	20K PU	D
				Func 0 GPIO	Cannot be a Customer GPIO	-	-	-
				Func 1	TRST_N	I	20K PU	D

Table 39-1. Signal Pin Name Directory - Sorted by Name (Sheet 31 of 31)

Pin	Pin Name	Buffer Type	V Group	Pin States	Signal Name	Dir	Internal PU/PD	Description (Link)
BL56	UART0_RXD	CMOS-HV	V3P30	Default	GPIO[101]	I	20K PU	D
				Func 0 GPIO	GPIO[101]	SW	SW	D
				Func 1	UART0_RXD	I	20K PU	D
CA52	UART0_TXD	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PD	D
				Default	GPIO[102]	O	-	D
				Func 0 GPIO	GPIO[102]	SW	SW	D
				Func 1	UART0_TXD	O	-	D
BV53	UART1_RXD	CMOS-HV	V3P30	Default	GPIO[96]	O	20K PU	D
				Func 0 GPIO	GPIO[96]	SW	SW	D
				Func 1	UART1_RXD	I	20K PU	D
				Func 2	UART_IE_RXD	I	20K PU	D
BN59	UART1_TXD	CMOS-HV	V3P30	Strap Sampling	Reserved for Intel	I	20K PU	D
				Default	GPIO[97]	O	-	D
				Func 0 GPIO	GPIO[97]	SW	SW	D
				Func 1	UART1_TXD	O	-	D
				Func 2	UART_IE_TXD	O	-	D
BD54	USB_OC_N	CMOS-HV	V3P30	Default	USB_OC_N	I	20K PU	D
				Func 0 GPIO	GPIO[120]	SW	SW	D
				Func 1	USB_OC_N	I	20K PU	D
AN54	USB2_COMP	USB2	V3P30	not shared	USB2_COMP	I	-	D
AR72	USB2_DN[0]	USB2	V3P30	not shared	USB2_DN[0]	I,O, Diff	-	D
AP63	USB2_DN[1]	USB2	V3P30	not shared	USB2_DN[1]	I,O, Diff	-	D
AV72	USB2_DN[2]	USB2	V3P30	not shared	USB2_DN[2]	I,O, Diff	-	D
AN61	USB2_DN[3]	USB2	V3P30	not shared	USB2_DN[3]	I,O, Diff	-	D
AR70	USB2_DP[0]	USB2	V3P30	not shared	USB2_DP[0]	I,O, Diff	-	D
AR65	USB2_DP[1]	USB2	V3P30	not shared	USB2_DP[1]	I,O, Diff	-	D
AV70	USB2_DP[2]	USB2	V3P30	not shared	USB2_DP[2]	I,O, Diff	-	D
AP59	USB2_DP[3]	USB2	V3P30	not shared	USB2_DP[3]	I,O, Diff	-	D

39.1.1 Reserved (RSVD_xxx) Pins

A number of the SoC pins are reserved for Intel. Table 39-2 lists these pins and provides recommendations for the platform board design.

Table 39-2. Treatment of Reserved Pins (Sheet 1 of 2)

Pin	Pin Name	Dir	Shared-Function Pin?	Voltage Rail	SoC Has Internal Resistor	Board Design Recommendation
H35	RSVD_H35	O	No	n/a	n/a	Make no connection to this pin.
H42	RSVD_H42	O	No	n/a	n/a	Make no connection to this pin.
K35	RSVD_K35	O	No	n/a	n/a	Make no connection to this pin.
K42	RSVD_K42	O	No	n/a	n/a	Make no connection to this pin.
P33	RSVD_P33	I,O	No	n/a	n/a	Make no connection to this pin.
R31	RSVD_R31	O	No	n/a	n/a	Make no connection to this pin.
R50	RSVD_R50	I	No	VSS	No	Use Pull-Down Resistor with a value ranging from 0 to 1 kΩ, ±5%
R54	RSVD_R54	O, Diff	No	n/a	n/a	Make no connection to this pin.
R58	RSVD_R58	O, Diff	No	n/a	n/a	Make no connection to this pin.
T33	RSVD_T33	I,O	No	n/a	n/a	Make no connection to this pin.
T56	RSVD_T56	O, Diff	No	n/a	n/a	Make no connection to this pin.
T59	RSVD_T59	O, Diff	No	n/a	n/a	Make no connection to this pin.
U31	RSVD_U31	O	No	n/a	n/a	Make no connection to this pin.
W50	RSVD_W50	I,O	No	n/a	n/a	Make no connection to this pin.
Y48	RSVD_Y48	I,O	No	n/a	n/a	Make no connection to this pin.
AA29	RSVD_AA29	O	No	n/a	n/a	Make no connection to this pin.
AD58	RSVD_AD58	I,O	No	n/a	n/a	Make no connection to this pin.
AH20	RSVD_AH20	O, Diff	No	n/a	n/a	Make no connection to this pin.
AH54	RSVD_AH54	I	No	VSS	No	Use Pull-Down Resistor with a value ranging from 0 to 1 kΩ, ±5%
AJ22	RSVD_AJ22	O, Diff	No	n/a	n/a	Make no connection to this pin.
AK20	RSVD_AK20	O, Diff	No	n/a	n/a	Make no connection to this pin.
AL22	RSVD_AL22	O, Diff	No	n/a	n/a	Make no connection to this pin.
AL59	RSVD_AL59	I	No	VSS	No	Use Pull-Down Resistor with a value ranging from 0 to 1 kΩ, ±5%
AN20	RSVD_AN20	O	No	n/a	n/a	Make no connection to this pin.
AP22	RSVD_AP22	O	No	n/a	n/a	Make no connection to this pin.
AW30	RSVD_AW30	O	No	n/a	n/a	Make no connection to this pin.
BA24	RSVD_BA24	I,O	No	n/a	n/a	Make no connection to this pin.
BA26	RSVD_BA26	I,O	No	n/a	n/a	Make no connection to this pin.
BA29	RSVD_BA29	O	No	n/a	n/a	Make no connection to this pin.
BB29	RSVD_BB29	O	No	n/a	n/a	Make no connection to this pin.
BF38	RSVD_BF38	O	No	n/a	n/a	Make no connection to this pin.
BG40	RSVD_BG40	I	No	VSS	No	Use Pull-Down Resistor with a value ranging from 0 to 1 kΩ, ±5%



Table 39-2. Treatment of Reserved Pins (Sheet 2 of 2)

Pin	Pin Name	Dir	Shared-Function Pin?	Voltage Rail	SoC Has Internal Resistor	Board Design Recommendation
BH38	RSVD_BH38	I,O	No	n/a	n/a	Make no connection to this pin.
BK38	RSVD_BK38	I,O	No	n/a	n/a	Make no connection to this pin.
BY58	RSVD_BY58	O	Yes	V3P30	No	Can be programmed to be used as Customer GPIO[89] signal pin. If not used as a GPIO, make no connection to this pin.

39.2 Directory of Signals that Share the HSIO Pins

The High-Speed I/O (HSIO) signals listed in Table 39-1, "Signal Pin Name Directory - Sorted by Name" are shared with PCI Express*, SATA, and USB 3.0 signal pins.

Table 39-1, "Signal Pin Name Directory - Sorted by Name" lists these shared signal names.

The individual shared signals are described in the following chapters:

- Chapter 11, "PCI Express Root Ports (RP)"
- Chapter 12, "SATA Controller"
- Chapter 14, "USB Combo Controller"

Readers of the electronic version of this document can navigate to these description chapters by clicking on the blue-colored "D" in the Description column of Table 39-3, "Signals that Share the Twenty HSIO Lanes."

The association of the Signals in Table 39-3, "Signals that Share the Twenty HSIO Lanes" with the 20 HSIO Lanes, the supported shared patterns, and the HSIO configuration control, are described in Chapter 10, "Flexible I/O Adapter (FIA) Overview."

Table 39-3. Signals that Share the Twenty HSIO Lanes

Signal Name	Direction	Link to Signal Description
PCI Express Root Port Cluster 0 (RP0, RP1, RP2, RP3) - 8 Lanes		
PCIE0_RP_3_0_TX_DP[7:0] PCIE0_RP_3_0_TX_DN[7:0]	O, Differential	D
PCIE0_RP_3_0_RX_DP[7:0] PCIE0_RP_3_0_RX_DN[7:0]	I, Differential	D
PCI Express Root Port Cluster 1 (RP4, RP5, RP6, RP7) - 8 Lanes		
PCIE1_RP_7_4_TX_DP[7:0] PCIE1_RP_7_4_TX_DN[7:0]	O, Differential	D
PCIE1_RP_7_4_RX_DP[7:0] PCIE1_RP_7_4_RX_DN[7:0]	I, Differential	D
SATA0 Controller - 8 Lanes		
SATA0_TX_DP[7:0] SATA0_TX_DN[7:0]	O, Differential	D
SATA0_RX_DP[7:0] SATA0_RX_DN[7:0]	I, Differential	D
SATA1 Controller - 8 Lanes		
SATA1_TX_DP[7:0] SATA1_TX_DN[7:0]	O, Differential	D
SATA1_RX_DP[7:0] SATA1_RX_DN[7:0]	I, Differential	D
USB 3.0 Interface of the USB Combo Controller - 4 Lanes		
USB3_TX_DP[3:0] USB3_TX_DN[3:0]	O, Differential	D
USB3_RX_DP[3:0] USB3_RX_DN[3:0]	I, Differential	D

39.3 Directory of Voltage Supply and Sense Pin Names

Special on-board filtering is required.

Table 39-4. Voltage Pins Sorted by Platform VR and SoC Voltage Group (Sheet 1 of 3)

Platform VR	SoC Voltage Group	Pin Number(s)	Power Delivery Notes
Voltage Observe Output Pins	OBS_VCCRAMCPUSI1GT_MOD0	AA37	
	OBS_VCCCPUVIDSI0GT_MOD0	Y36	
	OBS_VCCCPUVIDSI0GT_MOD4	BA36	
	OBS_VCCBIUVIDSI0GT_MOD0	AA36	
Voltage Sense Output Pins	SENSE_VCCRAMCPU_S0	AW36	
	SENSE_VSSRAMCPU_S0	AW37	
	SENSE_VCCCPUVIDSI0	AE37	
	SENSE_VSSCPUVIDSI0	AE39	
V1P05	VCCACKDDR_1P05	AA27, AC27, AE27, AG27, AJ27, AK27, AM27, AP27, AT27, AU27, AW27	
	VCCADDR_1P05	AA26, AC26, AE26, AG26, AJ26, AK26, AM26, AP26, AT26, AU26, AW26	
	VCCAON_HSIO_1P05	AF50, AG52, AH50, AK50, AN50, AP48, AR50, AT48	
	VCCCL_HSIO_1P05	AJ48, AK48	
	VCCFHVSI0_GROUP0_1P05	BD38	
	VCCFHVSI0_GROUP1_1P05	AW39	
	VCCFHVSI0_GROUP2_1P05	AW41	
	VCCFHVSI0_1P05	AU39	
	VCCPLLEBB_HSIO_1P05	AG48	
	VCCKRLCPLL	AA41, AA43, AA45, AA46	1
	VCCKRA_LV	AC39, AC41, AC43, AC45, AC46, AC48, AE41, AE43, AE45, AE46	
	VCCUSB_1P05	AR54, AU54	
	VCCDIGICKSI0_1P05	AG45, AJ45	1
	VCCDIGXXXSI0_1P05	AK45, AM45, AP45, AT45	
V1P80	VCCKR_HV	Y43, Y45	1
	VCCUSBSUS_1P8	AU50, AW50	
	VCCPADXXXSI0_1P8	AW43, BA43	
	VCCFHVIFPSI0_1P8	BA39	
V3P30 (LPC)	VCC_LPC_ESPI_3P3_1P8	BD46	
V3P30	VCCUSBSUS_3P3	AW48, BA48	
	VCCPADXXXSI0_3P3	AW46, BA46	
	VCCFHVIFPSI0_3P3	BA41	
VRTC	VCCRTC_3P3_G3	AU48	
VCC	VCCCPU_SVID_S0	AA32, AA34, AC32, AC34, AE32, AE34, AG32, AG34, AJ32, AJ34, AK32, AK34, AM32, AM34, AP32, AP34, AT32, AT34, AU32, AU34, AW32, AW34, BA32, BA34, BB33, BD35, BE33, BF35, BG33, BH35, BJ33, BK35, BL33, BM35, BN33, BR35, BU32, BU34, BV33, BW32, BW34, BY33, CA32, CA34	

Table 39-4. Voltage Pins Sorted by Platform VR and SoC Voltage Group (Sheet 2 of 3)

Platform VR	SoC Voltage Group	Pin Number(s)	Power Delivery Notes
VCCRAM	VCCRAM_S0	AC30, AC36, AE30, AE36, AG30, AG36, AJ30, AJ36, AK30, AK36, AM30, AM36, AP30, AP36, AT30, AT36, AU30, AU36	
VCCREF	VCCUSB_1P24	AT52, AV52	
	VCCREF_DTS_E	AP29	1, 2
	VCCREF_DTS_W	AU45	1
	VCCREF_SFRXXXSI0_N	AA30	1
	VCCREF_SFRXXXSI0_S	AW29	1
VDDQ	VCCDDR_VDDQ	K9, M11, P11, P15, T11, V11, Y18, AC18, AE18, AG18, AJ18, AL18, AR1, AV1, AY1, BD1, BJ1, BJ3, BY12	
	VCCCKDDR_VDDQ	AR24, AU24	
	VCCDDRSFR_VDDQ	AH24, AK24	1
	VCCDDR_VDDQ_NCTF	BN1, CA9	

Table 39-4. Voltage Pins Sorted by Platform VR and SoC Voltage Group (Sheet 3 of 3)

Platform VR	SoC Voltage Group	Pin Number(s)	Power Delivery Notes
VNN	VNN_SVID	AG39, AJ39, AJ41, AK39, AK41, AM39, AM41, AP39, AP41, AT39, AT41, AU41	
VSS	VSS	A22, A37, B14, B29, B38, B40, B42, B44, B47, B49, B51, B53, B55, B58, B60, B62, B64, C5, C22, C37, C68, D14, D29, D38, D40, D42, D44, D47, D49, D51, D53, D55, D58, D60, D62, D64, D66, E3, E9, E11, E13, E15, E18, E20, E22, E24, E26, E28, E30, E32, E34, E37, E39, E41, E43, E45, E48, E50, E52, E54, E57, E59, E61, E63, E65, E67, E70, F3, F5, F8, F66, F70, G6, G29, G66, H4, H17, H31, H38, H46, H50, H58, J3, J29, J68, K2, K4, K17, K31, K38, K46, K54, K61, K69, K71, L5, L68, M18, M22, M26, M29, M33, M37, M40, M44, M66, M69, M71, N5, N17, N20, N24, N27, N31, N35, N38, N42, N46, N50, N54, N58, N61, N68, P29, P44, P48, P52, P56, P59, P63, P69, P71, R5, R17, R35, R38, R61, R68, T29, T44, T48, T52, T66, T69, T71, U17, U35, U38, U50, U54, U58, U61, V1, V3, V5, V18, V22, V26, V29, V33, V37, V40, V44, V48, V52, V56, V59, V63, V68, W9, W13, W20, W24, W61, W69, W71, Y5, Y7, Y11, Y22, Y26, Y27, Y29, Y30, Y32, Y34, Y37, Y41, Y46, Y52, Y56, Y66, Y68, AA13, AA24, AA39, AA48, AA54, AA58, AA61, AA69, AA71, AB5, AB68, AC29, AC37, AC52, AC63, AC69, AC71, AD5, AD13, AD50, AD61, AD68, AE2, AE4, AE29, AE48, AE52, AE56, AE66, AE69, AE71, AF5, AF13, AF24, AF54, AF58, AF61, AF68, AG29, AG37, AG41, AG43, AG46, AG63, AH13, AH61, AH69, AH71, AJ5, AJ29, AJ37, AJ43, AJ46, AJ52, AJ66, AJ68, AK9, AK13, AK29, AK37, AK43, AK46, AK54, AK58, AK61, AK69, AK71, AL5, AL7, AL11, AL15, AL52, AL63, AL68, AM29, AM37, AM43, AM46, AM48, AM69, AM71, AN1, AN3, AN5, AN13, AN17, AN24, AN58, AN65, AN68, AP18, AP37, AP43, AP46, AP52, AP66, AP69, AP71, AR5, AR13, AR58, AR61, AR68, AT18, AT29, AT37, AT43, AT46, AT56, AT59, AT63, AT66, AT69, AT71, AU29, AU37, AU43, AU46, AV5, AV18, AV68, AW24, AW45, AW54, AW58, AW61, AW65, AW69, AW71, AY5, AY18, AY68, BA9, BA13, BA20, BA27, BA30, BA37, BA45, BA50, BB5, BB7, BB11, BB18, BB22, BB26, BB37, BB40, BB44, BB48, BB52, BB56, BB59, BB63, BB68, BC71, BD5, BD9, BD13, BD20, BD24, BD27, BD31, BD68, BE7, BE15, BE18, BE37, BE71, BF5, BF13, BF17, BF31, BF42, BF46, BF50, BF54, BF58, BF61, BF65, BF68, BG18, BG37, BH31, BJ5, BJ11, BJ18, BJ22, BJ26, BJ29, BJ37, BJ40, BJ44, BJ48, BJ52, BJ56, BJ59, BJ63, BJ68, BJ70, BK20, BK24, BK27, BK31, BL5, BL18, BL37, BL68, BL72, BM31, BM42, BM46, BM50, BM54, BM58, BM61, BM65, BM69, BN5, BN11, BN18, BN37, BR3, BR6, BR31, BR38, BR70, BT8, BT66, BU3, BU9, BU11, BU13, BU15, BU18, BU20, BU22, BU24, BU26, BU28, BU30, BU37, BU39, BU41, BU45, BU48, BU50, BU52, BU54, BU59, BU61, BU65, BU67, BU70, BV16, BV31, BV35, BW24, BW43, BW57, BW63, BW65, BY16, BY31, BY35, BY40, BY47, BY53, BY60, CA24	
	VSS_NCTF	A5, A7, A9, C3, C70, C72, E1, E72, G1, G72, J1, J72, A65, A66, A68, BN72, BR1, BR72, BU1, BU72, BW1, BW3, BW70, BW72, CA5, CA7, CA65, CA66, CA68, CA70	

39.4 Directory of Rotation-Detect Pins

Table 39-5. Package Rotation (ROT) Pins

Pin Name	Pin Number(s)	Description
NC_ROT	A70	**Package Rotation (ROT) Detect**: For Intel use on special validation boards with a socket for the SoC package. NC_ROT has no connection inside the SoC package. VSS_ROT is connected to VSS power plane of the SoC package. For customer board designs, these pins can be left as no-connects or can be tied to VSS on the board.
VSS_ROT	CA3	

39.5 Directory of All Signal and Voltage Pins - Sorted by Pin Number

Note: The information in this chapter is preliminary and is subject to change.

Table 39-6. Directory of Signal and Voltage Pins - Sorted by Pin Number

A5	VSS
A7	VSS
A9	VSS
A11	DDR0_DQS_DP[9]
A13	DDR0_DQ[4]
A15	DDR1_ECC[2]
A18	DDR1_DQS_DN[8]
A20	DDR1_ECC[0]
A22	VSS
A24	DDR1_DQ[30]
A26	DDR1_DQS_DP[12]
A28	DDR1_DQ[28]
A30	DDR1_DQ[2]
A32	DDR1_DQS_DN[0]
A34	DDR1_DQ[0]
A37	VSS
A39	CLK_X2_PAD
A41	CLK_OUT_DN[0]
A43	CLK_OUT_DN[1]
A45	CLK_OUT_DN[2]
A48	CLK_OUT_DN[3]
A50	CLK_OUT_DN[4]
A52	HSIO_RX_DP[0]
A54	HSIO_RX_DP[1]
A57	HSIO_RX_DP[2]
A59	HSIO_RX_DP[3]
A61	HSIO_RX_DP[4]
A63	HSIO_RX_DP[5]
A65	VSS
A66	VSS
A68	VSS
A70	NC_ROT
B10	DDR0_DQS_DN[0]
B12	DDR0_DQ[0]
B14	VSS
B16	DDR1_ECC[6]
B19	DDR1_DQS_DP[17]
B21	DDR1_ECC[4]
B23	DDR1_DQ[26]
B25	DDR1_DQS_DN[3]
B27	DDR1_DQ[24]
B29	VSS
B31	DDR1_DQ[6]
B33	DDR1_DQS_DP[9]
B35	DDR1_DQ[4]
B38	VSS
B40	VSS
B42	VSS
B44	VSS
B47	VSS
B49	VSS
B51	VSS
B53	VSS
B55	VSS
B58	VSS
B60	VSS
B62	VSS
B64	VSS
C3	VSS
C5	VSS
C6	DDR0_DQ[7]
C9	DDR0_DQ[2]
C11	DDR0_DQS_DN[9]
C13	DDR0_DQ[5]
C15	DDR1_ECC[3]
C18	DDR1_DQS_DP[8]
C20	DDR1_ECC[1]
C22	VSS
C24	DDR1_DQ[31]
C26	DDR1_DQS_DN[12]
C28	DDR1_DQ[29]
C30	DDR1_DQ[3]
C32	DDR1_DQS_DP[0]
C34	DDR1_DQ[1]
C37	VSS
C39	CLK_X1_PAD
C41	CLK_OUT_DP[0]
C43	CLK_OUT_DP[1]
C45	CLK_OUT_DP[2]
C48	CLK_OUT_DP[3]
C50	CLK_OUT_DP[4]
C52	HSIO_RX_DN[0]
C54	HSIO_RX_DN[1]
C57	HSIO_RX_DN[2]
C59	HSIO_RX_DN[3]
C61	HSIO_RX_DN[4]
C63	HSIO_RX_DN[5]
C65	HSIO_RX_DN[6]
C67	HSIO_RX_DP[6]
C68	VSS
C70	VSS
C72	VSS
D8	DDR0_DQ[6]
D10	DDR0_DQS_DP[0]
D12	DDR0_DQ[1]
D14	VSS
D16	DDR1_ECC[7]
D19	DDR1_DQS_DN[17]
D21	DDR1_ECC[5]
D23	DDR1_DQ[27]
D25	DDR1_DQS_DP[3]
D27	DDR1_DQ[25]
D29	VSS
D31	DDR1_DQ[7]
D33	DDR1_DQS_DN[9]
D35	DDR1_DQ[5]
D38	VSS
D40	VSS
D42	VSS
D44	VSS
D47	VSS
D49	VSS
D51	VSS
D53	VSS

D55	VSS
D58	VSS
D60	VSS
D62	VSS
D64	VSS
D66	VSS
E1	VSS
E3	VSS
E6	DDR0_DQ[3]
E9	VSS
E11	VSS
E13	VSS
E15	VSS
E18	VSS
E20	VSS
E22	VSS
E24	VSS
E26	VSS
E28	VSS
E30	VSS
E32	VSS
E34	VSS
E37	VSS
E39	VSS
E41	VSS
E43	VSS
E45	VSS
E48	VSS
E50	VSS
E52	VSS
E54	VSS
E57	VSS
E59	VSS
E61	VSS
E63	VSS
E65	VSS
E67	VSS
E70	VSS
E72	VSS
F3	VSS
F5	VSS
F8	VSS
F66	VSS

F69	HSIO_RX_DN[7]
F70	VSS
G1	VSS
G6	VSS
G7	DDR1_BG0_BA[2]
G11	DDR1_MA[12]
G15	DDR1_CKE[3]
G18	DDR1_DQ[18]
G22	DDR1_DQS_DN[2]
G26	DDR1_DQ[16]
G29	VSS
G33	LAN1_PORT0_TX_DN
G37	LAN1_PORT1_TX_DN
G40	LAN0_PORT0_TX_DN
G44	LAN0_PORT1_TX_DN
G48	HSIO_TX_DN[0]
G52	HSIO_TX_DP[3]
G56	HSIO_TX_DN[4]
G59	HSIO_TX_DP[7]
G63	HSIO_TX_DP[8]
G66	VSS
G67	HSIO_RX_DP[7]
G72	VSS
H4	VSS
H9	DDR1_ACT_N_MA[15]
H13	DDR1_CKE[2]
H17	VSS
H20	DDR1_DQ[22]
H24	DDR1_DQS_DP[11]
H27	DDR1_DQ[20]
H31	VSS
H35	RSVD_H35
H38	VSS
H42	RSVD_H42
H46	VSS
H50	VSS
H54	HSIO_TX_DN[3]
H58	VSS
H61	HSIO_TX_DN[7]
H65	HSIO_TX_DP[9]
H69	HSIO_RX_DN[8]
J1	VSS
J3	VSS

J5	DDR1_BG1_MA[14]
J7	DDR1_MA[11]
J11	DDR1_MA[9]
J15	DDR1_CKE[1]
J18	DDR1_DQ[19]
J22	DDR1_DQS_DP[2]
J26	DDR1_DQ[17]
J29	VSS
J33	LAN1_PORT0_TX_DP
J37	LAN1_PORT1_TX_DP
J40	LAN0_PORT0_TX_DP
J44	LAN0_PORT1_TX_DP
J48	HSIO_TX_DP[0]
J52	HSIO_TX_DN[2]
J56	HSIO_TX_DP[4]
J59	HSIO_TX_DN[6]
J63	HSIO_TX_DN[8]
J66	HSIO_TX_DN[9]
J68	VSS
J70	HSIO_RX_DP[8]
J72	VSS
K2	VSS
K4	VSS
K9	VCCDDR_VDDQ
K13	DDR1_CKE[0]
K17	VSS
K20	DDR1_DQ[23]
K24	DDR1_DQS_DN[11]
K27	DDR1_DQ[21]
K31	VSS
K35	RSVD_K35
K38	VSS
K42	RSVD_K42
K46	VSS
K50	HSIO_TX_DN[1]
K54	VSS
K58	HSIO_TX_DN[5]
K61	VSS
K65	HSIO_TX_DP[10]
K69	VSS
K71	VSS
L1	DDR0_DQ[12]
L3	DDR0_DQ[13]

L5	VSS
L68	VSS
L70	HSIO_RX_DN[9]
L72	HSIO_RX_DP[9]
M2	DDR0_DQ[8]
M4	DDR0_DQ[9]
M7	DDR1_MA[6]
M11	VCCDDR_VDDQ
M15	DDR1_ALERT_N_PAR_ERR_N
M18	VSS
M22	VSS
M26	VSS
M29	VSS
M33	VSS
M37	VSS
M40	VSS
M44	VSS
M48	HSIO_TX_DP[1]
M52	HSIO_TX_DP[2]
M56	HSIO_TX_DP[5]
M59	HSIO_TX_DP[6]
M63	HSIO_TX_DN[10]
M66	VSS
M69	VSS
M71	VSS
N1	DDR0_DQS_DP[10]
N3	DDR0_DQS_DN[10]
N5	VSS
N9	DDR1_MA[7]
N13	DDR1_MA[5]
N17	VSS
N20	VSS
N24	VSS
N27	VSS
N31	VSS
N35	VSS
N38	VSS
N42	VSS
N46	VSS
N50	VSS
N54	VSS
N58	VSS

N61	VSS
N65	HSIO_TX_DP[11]
N68	VSS
N70	HSIO_RX_DN[10]
N72	HSIO_RX_DP[10]
P2	DDR0_DQS_DN[1]
P4	DDR0_DQS_DP[1]
P7	DDR1_MA[3]
P11	VCCDDR_VDDQ
P15	VCCDDR_VDDQ
P18	DDR1_DQ[10]
P22	DDR1_DQS_DN[1]
P26	DDR1_DQ[8]
P29	VSS
P33	RSVD_P33
P37	LAN1_PORT0_RX_DP
P40	LAN1_PORT1_RX_DN
P44	VSS
P48	VSS
P52	VSS
P56	VSS
P59	VSS
P63	VSS
P66	HSIO_TX_DN[11]
P69	VSS
P71	VSS
R1	DDR0_DQ[14]
R3	DDR0_DQ[15]
R5	VSS
R9	DDR1_MA[8]
R13	DDR1_MA[4]
R17	VSS
R20	DDR1_DQ[14]
R24	DDR1_DQS_DP[10]
R27	DDR1_DQ[12]
R31	RSVD_R31
R35	VSS
R38	VSS
R42	LAN0_PORT0_RX_DP
R46	LAN0_PORT1_RX_DN
R50	RSVD_R50
R54	RSVD_R54
R58	RSVD_R58

R61	VSS
R65	HSIO_TX_DP[12]
R68	VSS
R70	HSIO_RX_DN[11]
R72	HSIO_RX_DP[11]
T2	DDR0_DQ[10]
T4	DDR0_DQ[11]
T7	DDR1_MA[2]
T11	VCCDDR_VDDQ
T15	DDR1_CLK_DP[3]
T18	DDR1_DQ[11]
T22	DDR1_DQS_DP[1]
T26	DDR1_DQ[9]
T29	VSS
T33	RSVD_T33
T37	LAN1_PORT0_RX_DN
T40	LAN1_PORT1_RX_DP
T44	VSS
T48	VSS
T52	VSS
T56	RSVD_T56
T59	RSVD_T59
T63	HSIO_TX_DN[12]
T66	VSS
T69	VSS
T71	VSS
U9	DDR1_MA[1]
U13	DDR1_CLK_DN[3]
U17	VSS
U20	DDR1_DQ[15]
U24	DDR1_DQS_DN[10]
U27	DDR1_DQ[13]
U31	RSVD_U31
U35	VSS
U38	VSS
U42	LAN0_PORT0_RX_DN
U46	LAN0_PORT1_RX_DP
U50	VSS
U54	VSS
U58	VSS
U61	VSS
U65	HSIO_TX_DP[13]
V1	VSS

V3	VSS
V5	VSS
V7	DDR1_PAR
V11	VCCDDR_VDDQ
V15	DDR1_CLK_DN[2]
V18	VSS
V22	VSS
V26	VSS
V29	VSS
V33	VSS
V37	VSS
V40	VSS
V44	VSS
V48	VSS
V52	VSS
V56	VSS
V59	VSS
V63	VSS
V66	HSIO_TX_DN[13]
V68	VSS
V70	HSIO_RX_DN[12]
V72	HSIO_RX_DP[12]
W2	DDR0_DQ[20]
W4	DDR0_DQ[21]
W9	VSS
W13	VSS
W17	DDR1_CLK_DP[2]
W20	VSS
W24	VSS
W50	RSVD_W50
W54	ICLKRCOMP
W58	LAN0_PORT1_SDP[3]
W61	VSS
W65	HSIO_TX_DP[14]
W69	VSS
W71	VSS
Y1	DDR0_DQ[16]
Y3	DDR0_DQ[17]
Y5	VSS
Y7	VSS
Y11	VSS
Y15	DDR1_CLK_DN[1]
Y18	VCCDDR_VDDQ
Y22	VSS
Y26	VSS
Y27	VSS
Y29	VSS
Y30	VSS
Y32	VSS
Y34	VSS
Y36	OBS_VCCCPUVIDSI0GT_MOD0
Y37	VSS
Y39	LAN1_RBIAS
Y41	VSS
Y43	VCCKR_HV
Y45	VCCKR_HV
Y46	VSS
Y48	RSVD_Y48
Y52	VSS
Y56	VSS
Y59	SRTCRST_N
Y63	HSIO_TX_DN[14]
Y66	VSS
Y68	VSS
Y70	HSIO_RX_DN[13]
Y72	HSIO_RX_DP[13]
AA2	DDR0_DQS_DP[11]
AA4	DDR0_DQS_DN[11]
AA9	DDR0_DQ[28]
AA13	VSS
AA17	DDR1_CLK_DP[1]
AA20	DDR1_BA[1]
AA24	VSS
AA26	VCCADDR_1P05
AA27	VCCACKDDR_1P05
AA29	RSVD_AA29
AA30	VCCREF_SFRXXXSI0_N
AA32	VCCCPU_SVID_S0
AA34	VCCCPU_SVID_S0
AA36	OBS_VCCBIUVIDSI0GT_MOD0
AA37	OBS_VCCRAMCPUSI1GT_MOD0
AA39	VSS
AA41	VCCKRLCPLL
AA43	VCCKRLCPLL
AA45	VCCKRLCPLL
AA46	VCCKRLCPLL
AA48	VSS
AA50	LAN0_RBIAS
AA54	VSS
AA58	VSS
AA61	VSS
AA65	HSIO_TX_DP[15]
AA69	VSS
AA71	VSS
AB1	DDR0_DQS_DN[2]
AB3	DDR0_DQS_DP[2]
AB5	VSS
AB68	VSS
AB70	HSIO_RX_DN[14]
AB72	HSIO_RX_DP[14]
AC2	DDR0_DQ[22]
AC4	DDR0_DQ[23]
AC7	DDR0_DQ[25]
AC11	DDR0_DQ[24]
AC15	DDR1_CLK_DN[0]
AC18	VCCDDR_VDDQ
AC22	DDR1_MA16_RAS_N
AC26	VCCADDR_1P05
AC27	VCCACKDDR_1P05
AC29	VSS
AC30	VCCRAM_S0
AC32	VCCCPU_SVID_S0
AC34	VCCCPU_SVID_S0
AC36	VCCRAM_S0
AC37	VSS
AC39	VCCKRA_LV
AC41	VCCKRA_LV
AC43	VCCKRA_LV
AC45	VCCKRA_LV
AC46	VCCKRA_LV
AC48	VCCKRA_LV
AC52	VSS
AC56	HSIO_COMPREF_DN
AC59	LAN0_PORT0_SDP[2]
AC63	VSS
AC66	HSIO_TX_DN[15]
AC69	VSS

AC71	VSS
AD1	DDR0_DQ[18]
AD3	DDR0_DQ[19]
AD5	VSS
AD9	DDR0_DQ[29]
AD13	VSS
AD17	DDR1_CLK_DP[0]
AD20	DDR1_BA[0]
AD24	DDR01_COMP
AD50	VSS
AD54	HSIO_COMPREF_DP
AD58	RSVD_AD58
AD61	VSS
AD65	HSIO_TX_DP[16]
AD68	VSS
AD70	HSIO_RX_DN[15]
AD72	HSIO_RX_DP[15]
AE2	VSS
AE4	VSS
AE7	DDR0_DQS_DN[3]
AE11	DDR0_DQS_DN[12]
AE15	DDR1_ODT[2]
AE18	VCCDDR_VDDQ
AE22	DDR1_MA[0]
AE26	VCCADDR_1P05
AE27	VCCACKDDR_1P05
AE29	VSS
AE30	VCCRAM_S0
AE32	VCCCPU_SVID_S0
AE34	VCCCPU_SVID_S0
AE36	VCCRAM_S0
AE37	SENSE_VCCCPUVIDSI0
AE39	SENSE_VSSCPUVIDSI0
AE41	VCCKRA_LV
AE43	VCCKRA_LV
AE45	VCCKRA_LV
AE46	VCCKRA_LV
AE48	VSS
AE52	VSS
AE56	VSS
AE59	RSMRST_N
AE63	HSIO_TX_DN[16]
AE66	VSS

AE69	VSS
AE71	VSS
AF1	DDR0_ECC[4]
AF3	DDR0_ECC[5]
AF5	VSS
AF9	DDR0_DQS_DP[12]
AF13	VSS
AF17	DDR1_CS_N[2]
AF20	DDR1_MA[10]
AF24	VSS
AF50	VCCAON_HSIO_1P05
AF54	VSS
AF58	VSS
AF61	VSS
AF65	HSIO_TX_DP[17]
AF68	VSS
AF70	HSIO_RX_DN[16]
AF72	HSIO_RX_DP[16]
AG7	DDR0_DQS_DP[3]
AG11	DDR0_DQ[31]
AG15	DDR1_MA17
AG18	VCCDDR_VDDQ
AG22	DDR1_CS_N[0]
AG26	VCCADDR_1P05
AG27	VCCACKDDR_1P05
AG29	VSS
AG30	VCCRAM_S0
AG32	VCCCPU_SVID_S0
AG34	VCCCPU_SVID_S0
AG36	VCCRAM_S0
AG37	VSS
AG39	VNN_SVID
AG41	VSS
AG43	VSS
AG45	VCCDIGICKSI0_1P05
AG46	VSS
AG48	VCCPLLEBB_HSIO_1P05
AG52	VCCAON_HSIO_1P05
AG56	COREPWROK
AG59	RTC_X1_PAD
AG63	VSS
AG66	HSIO_TX_DN[17]
AH2	DDR0_ECC[0]

AH4	DDR0_ECC[1]
AH9	DDR0_DQ[30]
AH13	VSS
AH17	DDR1_CS_N[3]
AH20	RSVD_AH20
AH24	VCCDDRSFR_VDDQ
AH50	VCCAON_HSIO_1P05
AH54	RSVD_AH54
AH58	RTC_X2_PAD
AH61	VSS
AH65	HSIO_TX_DP[18]
AH69	VSS
AH71	VSS
AJ1	DDR0_DQS_DP[17]
AJ3	DDR0_DQS_DN[17]
AJ5	VSS
AJ7	DDR0_DQ[26]
AJ11	DDR0_DQ[27]
AJ15	DDR1_C0
AJ18	VCCDDR_VDDQ
AJ22	RSVD_AJ22
AJ26	VCCADDR_1P05
AJ27	VCCACKDDR_1P05
AJ29	VSS
AJ30	VCCRAM_S0
AJ32	VCCCPU_SVID_S0
AJ34	VCCCPU_SVID_S0
AJ36	VCCRAM_S0
AJ37	VSS
AJ39	VNN_SVID
AJ41	VNN_SVID
AJ43	VSS
AJ45	VCCDIGICKSI0_1P05
AJ46	VSS
AJ48	VCCCL_HSIO_1P05
AJ52	VSS
AJ56	RTEST_N
AJ59	INTRUDER_N
AJ63	HSIO_TX_DN[18]
AJ66	VSS
AJ68	VSS
AJ70	HSIO_RX_DN[17]
AJ72	HSIO_RX_DP[17]

AK2	DDR0_DQS_DN[8]
AK4	DDR0_DQS_DP[8]
AK9	VSS
AK13	VSS
AK17	DDR1_ODT[3]
AK20	RSVD_AK20
AK24	VCCDDRSFR_VDDQ
AK26	VCCADDR_1P05
AK27	VCCACKDDR_1P05
AK29	VSS
AK30	VCCRAM_S0
AK32	VCCCPU_SVID_S0
AK34	VCCCPU_SVID_S0
AK36	VCCRAM_S0
AK37	VSS
AK39	VNN_SVID
AK41	VNN_SVID
AK43	VSS
AK45	VCCDIGXXXSI0_1P05
AK46	VSS
AK48	VCCCL_HSIO_1P05
AK50	VCCAON_HSIO_1P05
AK54	VSS
AK58	VSS
AK61	VSS
AK65	HSIO_TX_DP[19]
AK69	VSS
AK71	VSS
AL1	DDR0_ECC[6]
AL3	DDR0_ECC[7]
AL5	VSS
AL7	VSS
AL11	VSS
AL15	VSS
AL18	VCCDDR_VDDQ
AL22	RSVD_AL22
AL52	VSS
AL56	NCSI_TXD[1]
AL59	RSVD_AL59
AL63	VSS
AL66	HSIO_TX_DN[19]
AL68	VSS
AL70	HSIO_RX_DN[18]
AL72	HSIO_RX_DP[18]
AM2	DDR0_ECC[2]
AM4	DDR0_ECC[3]
AM26	VCCADDR_1P05
AM27	VCCACKDDR_1P05
AM29	VSS
AM30	VCCRAM_S0
AM32	VCCCPU_SVID_S0
AM34	VCCCPU_SVID_S0
AM36	VCCRAM_S0
AM37	VSS
AM39	VNN_SVID
AM41	VNN_SVID
AM43	VSS
AM45	VCCDIGXXXSI0_1P05
AM46	VSS
AM48	VSS
AM69	VSS
AM71	VSS
AN1	VSS
AN3	VSS
AN5	VSS
AN9	DDR1_DQ[36]
AN13	VSS
AN17	VSS
AN20	RSVD_AN20
AN24	VSS
AN50	VCCAON_HSIO_1P05
AN54	USB2_COMP
AN58	VSS
AN61	USB2_DN[3]
AN65	VSS
AN68	VSS
AN70	HSIO_RX_DN[19]
AN72	HSIO_RX_DP[19]
AP2	DDR01_DRAMRST_N
AP4	DDR0_CKE[1]
AP7	DDR1_DQ[33]
AP11	DDR1_DQ[32]
AP15	DDR1_DQ[45]
AP18	VSS
AP22	RSVD_AP22
AP26	VCCADDR_1P05
AP27	VCCACKDDR_1P05
AP29	VCCREF_DTS_E
AP30	VCCRAM_S0
AP32	VCCCPU_SVID_S0
AP34	VCCCPU_SVID_S0
AP36	VCCRAM_S0
AP37	VSS
AP39	VNN_SVID
AP41	VNN_SVID
AP43	VSS
AP45	VCCDIGXXXSI0_1P05
AP46	VSS
AP48	VCCAON_HSIO_1P05
AP52	VSS
AP56	PCIE_CLKREQ_N[0]
AP59	USB2_DP[3]
AP63	USB2_DN[1]
AP66	VSS
AP69	VSS
AP71	VSS
AR1	VCCDDR_VDDQ
AR3	DDR0_CKE[3]
AR5	VSS
AR9	DDR1_DQ[37]
AR13	VSS
AR17	DDR1_DQ[44]
AR20	DDR1_MA14_WE_N
AR24	VCCCKDDR_VDDQ
AR50	VCCAON_HSIO_1P05
AR54	VCCUSB_1P05
AR58	VSS
AR61	VSS
AR65	USB2_DP[1]
AR68	VSS
AR70	USB2_DP[0]
AR72	USB2_DN[0]
AT2	DDR0_CKE[2]
AT4	DDR0_CKE[0]
AT7	DDR1_DQS_DN[4]
AT11	DDR1_DQS_DN[13]
AT15	DDR1_DQ[40]
AT18	VSS
AT22	DDR1_MA15_CAS_N

AT26	VCCADDR_1P05
AT27	VCCACKDDR_1P05
AT29	VSS
AT30	VCCRAM_S0
AT32	VCCCPU_SVID_S0
AT34	VCCCPU_SVID_S0
AT36	VCCRAM_S0
AT37	VSS
AT39	VNN_SVID
AT41	VNN_SVID
AT43	VSS
AT45	VCCDIGXXXSI0_1P05
AT46	VSS
AT48	VCCAON_HSIO_1P05
AT52	VCCUSB_1P24
AT56	VSS
AT59	VSS
AT63	VSS
AT66	VSS
AT69	VSS
AT71	VSS
AU9	DDR1_DQS_DP[13]
AU13	DDR1_DQS_DN[14]
AU17	DDR1_DQ[41]
AU20	DDR1_ODT[0]
AU24	VCCCKDDR_VDDQ
AU26	VCCADDR_1P05
AU27	VCCACKDDR_1P05
AU29	VSS
AU30	VCCRAM_S0
AU32	VCCCPU_SVID_S0
AU34	VCCCPU_SVID_S0
AU36	VCCRAM_S0
AU37	VSS
AU39	VCCFHVSI0_1P05
AU41	VNN_SVID
AU43	VSS
AU45	VCCREF_DTS_W
AU46	VSS
AU48	VCCRTC_3P3_G3
AU50	VCCUSBSUS_1P8
AU54	VCCUSB_1P05
AU58	NCSI_ARB_IN

AU61	BVCCRTC_EXTPAD
AU65	LAN0_PORT1_SDP[2]
AV1	VCCDDR_VDDQ
AV3	DDR0_ACT_N_MA[15]
AV5	VSS
AV7	DDR1_DQS_DP[4]
AV11	DDR1_DQ[39]
AV15	DDR1_DQS_DP[5]
AV18	VSS
AV22	DDR1_CS_N[1]
AV52	VCCUSB_1P24
AV56	LAN0_PORT0_I2C_DATA
AV59	LAN0_PORT0_I2C_CLK
AV63	NCSI_ARB_OUT
AV66	LAN0_PORT0_SDP[0]
AV68	VSS
AV70	USB2_DP[2]
AV72	USB2_DN[2]
AW2	DDR0_BG1_MA[14]
AW4	DDR0_BG0_BA[2]
AW9	DDR1_DQ[38]
AW13	DDR1_DQS_DP[14]
AW17	DDR1_DQS_DN[5]
AW20	DDR1_MA[13]
AW24	VSS
AW26	VCCADDR_1P05
AW27	VCCACKDDR_1P05
AW29	VCCREF_SFRXXXSI0_S
AW30	RSVD_AW30
AW32	VCCCPU_SVID_S0
AW34	VCCCPU_SVID_S0
AW36	SENSE_VCCRAMCPU_S0
AW37	SENSE_VSSRAMCPU_S0
AW39	VCCFHVSI0_GROUP1_1P05
AW41	VCCFHVSI0_GROUP2_1P05
AW43	VCCPADXXXSI0_1P8
AW45	VSS
AW46	VCCPADXXXSI0_3P3
AW48	VCCUSBSUS_3P3
AW50	VCCUSBSUS_1P8
AW54	VSS
AW58	VSS

AW61	VSS
AW65	VSS
AW69	VSS
AW71	VSS
AY1	VCCDDR_VDDQ
AY3	DDR0_ALERT_N_PAR_ERR_N
AY5	VSS
AY7	DDR1_DQ[34]
AY11	DDR1_DQ[35]
AY15	DDR1_DQ[47]
AY18	VSS
AY22	DDR1_ODT[1]
AY52	DFX_PORT[9]
AY56	DFX_PORT_CLK[0]
AY59	NCSI_RXD[0]
AY63	NCSI_CLK_IN
AY66	LAN0_PORT1_SDP[0]
AY68	VSS
AY70	LAN1_PORT0_LED[0]
AY72	LAN1_PORT0_LED[1]
BA2	DDR0_MA[9]
BA4	DDR0_MA[12]
BA9	VSS
BA13	VSS
BA17	DDR1_DQ[46]
BA20	VSS
BA24	RSVD_BA24
BA26	RSVD_BA26
BA27	VSS
BA29	RSVD_BA29
BA30	VSS
BA32	VCCCPU_SVID_S0
BA34	VCCCPU_SVID_S0
BA36	OBS_VCCCPUVIDSI0GT_MOD4
BA37	VSS
BA39	VCCFHVIFPSI0_1P8
BA41	VCCFHVIFPSI0_3P3
BA43	VCCPADXXXSI0_1P8
BA45	VSS
BA46	VCCPADXXXSI0_3P3
BA48	VCCUSBSUS_3P3
BA50	VSS

BA54	SVID_ALERT_N
BA58	PCIE_CLKREQ_N[1]
BA61	THERMTRIP_N
BA65	LAN0_PORT1_LED[0]
BA69	LAN0_PORT0_SDP[3]
BA71	LAN0_PORT0_SDP[1]
BB1	DDR0_MA[7]
BB3	DDR0_MA[11]
BB5	VSS
BB7	VSS
BB11	VSS
BB15	DDR1_DQ[43]
BB18	VSS
BB22	VSS
BB26	VSS
BB29	RSVD_BB29
BB33	VCCCPU_SVID_S0
BB37	VSS
BB40	VSS
BB44	VSS
BB48	VSS
BB52	VSS
BB56	VSS
BB59	VSS
BB63	VSS
BB66	LAN0_PORT1_I2C_CLK
BB68	VSS
BB70	DFX_PORT_CLK[1]
BB72	LAN0_PORT1_SDP[1]
BC2	DDR0_MA[6]
BC4	DDR0_MA[8]
BC69	LAN0_PORT1_I2C_DATA
BC71	VSS
BD1	VCCDDR_VDDQ
BD3	DDR0_MA[5]
BD5	VSS
BD9	VSS
BD13	VSS
BD17	DDR1_DQ[42]
BD20	VSS
BD24	VSS
BD27	VSS
BD31	VSS
BD35	VCCCPU_SVID_S0
BD38	VCCFHVSI0_GROUP0_1P05
BD42	HSHV_IRCOMP
BD46	VCC_LPC_ESPI_3P3_1P8
BD50	ESPI_IRCOMP
BD54	USB_OC_N
BD58	ESPI_IO[0]
BD61	PCIE_CLKREQ_N[4]
BD65	NCSI_CRS_DV
BD68	VSS
BD70	NCSI_TX_EN
BD72	NCSI_RXD[1]
BE2	DDR0_MA[3]
BE4	DDR0_MA[4]
BE7	VSS
BE11	DDR1_DQS_DN[15]
BE15	VSS
BE18	VSS
BE22	DDR0_DQ[41]
BE26	DDR0_DQS_DP[5]
BE29	DDR0_DQ[43]
BE33	VCCCPU_SVID_S0
BE37	VSS
BE40	EMMC_IRCOMP
BE44	CTBTRIGINOUT
BE48	DFX_PORT[13]
BE52	GPIO[6]
BE56	SVID_DATA
BE59	SVID_CLK
BE63	DFX_PORT[2]
BE66	NCSI_TXD[0]
BE69	LAN0_PORT0_LED[0]
BE71	VSS
BF1	DDR0_MA[2]
BF3	DDR0_MA[1]
BF5	VSS
BF9	DDR1_DQ[52]
BF13	VSS
BF17	VSS
BF20	DDR0_DQ[45]
BF24	DDR0_DQS_DN[14]
BF27	DDR0_DQ[47]
BF31	VSS
BF35	VCCCPU_SVID_S0
BF38	RSVD_BF38
BF42	VSS
BF46	VSS
BF50	VSS
BF54	VSS
BF58	VSS
BF61	VSS
BF65	VSS
BF68	VSS
BF70	GPIO[0]
BF72	LAN0_PORT0_LED[1]
BG7	DDR1_DQ[53]
BG11	DDR1_DQS_DP[15]
BG15	DDR1_DQ[60]
BG18	VSS
BG22	DDR0_DQ[40]
BG26	DDR0_DQS_DN[5]
BG29	DDR0_DQ[42]
BG33	VCCCPU_SVID_S0
BG37	VSS
BG40	RSVD_BG40
BG44	TDI
BG48	FLEX_CLK_SE[0]
BG52	SMB_ME_SMT0_ALRT_N
BG56	SPI_CS_N[0]
BG59	PMU_SUSCLK
BG63	DFX_PORT[6]
BG66	LAN0_PORT1_LED[1]
BH2	DDR0_CLK_DP[3]
BH4	DDR0_CLK_DN[3]
BH9	DDR1_DQ[49]
BH13	DDR1_DQ[61]
BH17	DDR1_DQ[56]
BH20	DDR0_DQ[44]
BH24	DDR0_DQS_DP[14]
BH27	DDR0_DQ[46]
BH31	VSS
BH35	VCCCPU_SVID_S0
BH38	RSVD_BH38
BH42	CX_PREQ_N
BH46	GPIO[7]

BH50	GPIO[4]
BH54	SMB_LAN_CLK
BH58	SUSPWRDNACK
BH61	SPI_IO[2]
BH65	ESPI_IO[3]
BH69	DFX_PORT[5]
BH71	PCIE_CLKREQ_N[2]
BJ1	VCCDDR_VDDQ
BJ3	VCCDDR_VDDQ
BJ5	VSS
BJ7	DDR1_DQ[48]
BJ11	VSS
BJ15	DDR1_DQS_DN[16]
BJ18	VSS
BJ22	VSS
BJ26	VSS
BJ29	VSS
BJ33	VCCCPU_SVID_S0
BJ37	VSS
BJ40	VSS
BJ44	VSS
BJ48	VSS
BJ52	VSS
BJ56	VSS
BJ59	VSS
BJ63	VSS
BJ66	PCIE_CLKREQ_N[3]
BJ68	VSS
BJ70	VSS
BJ72	ESPI_CS_N[0]
BK2	DDR0_CLK_DP[1]
BK4	DDR0_CLK_DN[1]
BK9	DDR1_DQS_DP[6]
BK13	DDR1_DQS_DP[16]
BK17	DDR1_DQ[57]
BK20	VSS
BK24	VSS
BK27	VSS
BK31	VSS
BK35	VCCCPU_SVID_S0
BK38	RSVD_BK38
BK42	DFX_PORT[11]
BK46	EMMC_CLK

BK50	SMB_HOST_DATA
BK54	SMB_LAN_DATA
BK58	PCIE_CLKREQ_N[7]
BK61	ESPI_ALRT_N[0]
BK65	PMU_SLP_S3_N
BK69	GPIO[1]
BK71	GPIO[2]
BL1	DDR0_CLK_DP[2]
BL3	DDR0_CLK_DN[2]
BL5	VSS
BL7	DDR1_DQS_DN[6]
BL11	DDR1_DQ[50]
BL15	DDR1_DQS_DP[7]
BL18	VSS
BL22	DDR0_DQ[57]
BL26	DDR0_DQS_DP[7]
BL29	DDR0_DQ[59]
BL33	VCCCPU_SVID_S0
BL37	VSS
BL40	TRST_N
BL44	EMMC_STROBE
BL48	GPIO[5]
BL52	ERROR_N[0]
BL56	UART0_RXD
BL59	PMU_RESETBUTTON_N
BL63	PMU_PLTRST_N
BL66	SPI_CS_N[1]
BL68	VSS
BL70	MEMHOT_N
BL72	VSS
BM2	DDR0_CLK_DP[0]
BM4	DDR0_CLK_DN[0]
BM9	DDR1_DQ[55]
BM13	DDR1_DQS_DN[7]
BM17	DDR1_DQ[58]
BM20	DDR0_DQ[61]
BM24	DDR0_DQS_DN[16]
BM27	DDR0_DQ[63]
BM31	VSS
BM35	VCCCPU_SVID_S0
BM38	GPIO[150]
BM42	VSS
BM46	VSS

BM50	VSS
BM54	VSS
BM58	VSS
BM61	VSS
BM65	VSS
BM69	VSS
BM71	PROCHOT_N
BN1	VDDQ
BN3	DDR0_PAR
BN5	VSS
BN7	DDR1_DQ[54]
BN11	VSS
BN15	DDR1_DQ[63]
BN18	VSS
BN22	DDR0_DQ[56]
BN26	DDR0_DQS_DN[7]
BN29	DDR0_DQ[58]
BN33	VCCCPU_SVID_S0
BN37	VSS
BN40	TCK
BN44	GPIO[3]
BN48	EMMC_CMD
BN52	MCERR_N
BN56	GPIO[12]
BN59	UART1_TXD
BN63	SATA_PDETECT[1]
BN66	SMB_LAN_ALRT_N
BN68	DFX_PORT[0]
BN70	DFX_PORT[1]
BN72	VSS
BP4	DDR0_MA[0]
BP69	DFX_PORT[3]
BR1	VSS
BR3	VSS
BR6	VSS
BR9	DDR1_DQ[51]
BR13	DDR1_DQ[62]
BR17	DDR1_DQ[59]
BR20	DDR0_DQ[60]
BR24	DDR0_DQS_DP[16]
BR27	DDR0_DQ[62]
BR31	VSS
BR35	VCCCPU_SVID_S0

BR38	VSS
BR42	DFX_PORT[10]
BR46	SMB_ME_SMT0_CLK
BR50	SMB_HOST_CLK
BR54	SMB_PECI_CLK
BR58	ERROR_N[1]
BR61	PMU_WAKE_N
BR65	SATA0_LED_N
BR67	ESPI_IO[1]
BR70	VSS
BR72	VSS
BT5	DDR0_BA[1]
BT8	VSS
BT66	VSS
BT69	DFX_PORT[7]
BU1	VSS
BU3	VSS
BU6	DDR0_MA[10]
BU9	VSS
BU11	VSS
BU13	VSS
BU15	VSS
BU18	VSS
BU20	VSS
BU22	VSS
BU24	VSS
BU26	VSS
BU28	VSS
BU30	VSS
BU32	VCCCPU_SVID_S0
BU34	VCCCPU_SVID_S0
BU37	VSS
BU39	VSS
BU41	VSS
BU43	EMMC_D[4]
BU45	VSS
BU48	VSS
BU50	VSS
BU52	VSS
BU54	VSS
BU57	SATA0_SDOUT
BU59	VSS
BU61	VSS
BU63	SPI_MOSI_IO[0]
BU65	VSS
BU67	VSS
BU70	VSS
BU72	VSS
BV8	DDR0_BA[0]
BV10	DDR0_CS_N[2]
BV12	DDR0_CS_N[1]
BV14	DDR0_C0
BV16	VSS
BV19	DDR0_DQ[33]
BV21	DDR0_DQS_DP[4]
BV23	DDR0_DQ[35]
BV25	DDR0_DQ[53]
BV27	DDR0_DQS_DN[15]
BV29	DDR0_DQ[55]
BV31	VSS
BV33	VCCCPU_SVID_S0
BV35	VSS
BV38	TDO
BV40	DFX_PORT[15]
BV42	EMMC_D[7]
BV44	EMMC_D[1]
BV47	SMB_ME_SMT0_DATA
BV49	SMB_LEG_DATA
BV51	PCIE_CLKREQ_N[6]
BV53	UART1_RXD
BV55	SATA1_LED_N
BV58	SUS_STAT_N
BV60	ADR_TRIGGER
BV62	SPI_MISO_IO[1]
BV64	ESPI_IO[2]
BV66	ESPI_RST_N
BW1	VSS
BW3	VSS
BW5	DDR0_CS_N[0]
BW6	DDR0_MA16_RAS_N
BW9	DDR0_MA14_WE_N
BW11	DDR0_MA[13]
BW13	DDR0_ODT[2]
BW15	DDR0_CS_N[3]
BW18	DDR0_DQ[37]
BW20	DDR0_DQS_DN[13]
BW22	DDR0_DQ[39]
BW24	VSS
BW26	DDR0_DQ[49]
BW28	DDR0_DQS_DP[6]
BW30	DDR0_DQ[51]
BW32	VCCCPU_SVID_S0
BW34	VCCCPU_SVID_S0
BW37	GPIO[151]
BW39	TMS
BW41	DFX_PORT[12]
BW43	VSS
BW45	EMMC_D[0]
BW48	SMB_LEG_ALRT_N
BW50	IERR_N
BW52	PCIE_CLKREQ_N[5]
BW54	SATA1_SDOUT
BW57	VSS
BW59	PMU_SLP_S45_N
BW61	SPI_IO[3]
BW63	VSS
BW65	VSS
BW67	DFX_PORT[8]
BW68	DFX_PORT[4]
BW70	VSS
BW72	VSS
BY10	DDR0_ODT[0]
BY12	VCCDDR_VDDQ
BY14	DDR0_ODT[1]
BY16	VSS
BY19	DDR0_DQ[32]
BY21	DDR0_DQS_DN[4]
BY23	DDR0_DQ[34]
BY25	DDR0_DQ[52]
BY27	DDR0_DQS_DP[15]
BY29	DDR0_DQ[54]
BY31	VSS
BY33	VCCCPU_SVID_S0
BY35	VSS
BY38	CX_PRDY_N
BY40	VSS
BY42	EMMC_D[6]
BY44	EMMC_D[2]
BY47	VSS

BY49	SMB_PECI_DATA
BY51	SMB_LEG_CLK
BY53	VSS
BY55	GPIO[8]
BY58	RSVD_BY58
BY60	VSS
BY62	ESPI_ALRT_N[1]
BY64	ESPI_CLK
CA3	VSS_ROT
CA5	VSS
CA7	VSS
CA9	VDDQ
CA11	DDR0_MA15_CAS_N
CA13	DDR0_MA17
CA15	DDR0_ODT[3]
CA18	DDR0_DQ[36]
CA20	DDR0_DQS_DP[13]
CA22	DDR0_DQ[38]
CA24	VSS
CA26	DDR0_DQ[48]
CA28	DDR0_DQS_DN[6]
CA30	DDR0_DQ[50]
CA32	VCCCPU_SVID_S0
CA34	VCCCPU_SVID_S0
CA37	GPIO[152]
CA39	CTBTRIGOUT
CA41	DFX_PORT[14]
CA43	EMMC_D[5]
CA45	EMMC_D[3]
CA48	FLEX_CLK_SE[1]
CA50	ERROR_N[2]
CA52	UART0_TXD
CA54	GPIO[9]
CA57	SATA_PDETECT[0]
CA59	PMU_PWRBTN_N
CA61	SPI_CLK
CA63	ESPI_CS_N[1]
CA65	VSS
CA66	VSS
CA68	VSS
CA70	VSS

§ §

40 Signal Electrical and Timing Characteristics

This chapter is organized by signal interface. Each sub-chapter contains the interface DC, AC, and signal timing requirements and characteristics. Some of these requirements and characteristics are based on industry and Intel standards. When the SoC interface complies to a standard, the reader is referred to the standard for the requirements and characteristics. SoC exceptions to the standard, if any, are shown as well as any of the standard's optional interface characteristics as implemented by the SoC design.

Most of the information presented here is in Table and Figure form. In some cases, the reader is referred to one of the functional-description chapters where additional interface-related information is available.

40.1 DDR Memory Interface

The SoC supports up to two channels of DDR4, depending on configuration and product SKU.

40.1.1 DDR4

DDR4 SDRAM is the successor to DDR3 SDRAM. It was revealed at the Intel Developer Forum in San Francisco in 2008, samples were announced in early 2011. DDR4 is expected to reach mass market adoption around 2015.

Published in September 2012, the initial JEDEC DDR4 standard has been defined to provide higher performance, with improved reliability and reduced power, thereby representing a significant achievement relative to previous DRAM memory technologies.

The SoC DDR4 interface was designed to the DDR4 (JESD79-4) standard, and is available for free download from the JEDEC website.

The SoC supports DDR4 voltage of 1.2V. The DDR4 standard supports various options, see the Memory Controller Section 9.3, "Feature List" on page 353 of this document for the DDR4 options supported by this SoC.

This SoC was designed to the DDR4 standard, aside from the deviations listed below.

40.1.1.1 Deviations From The DDR4 Standard

While there are no known deviations, DDR4 is very sensitive to board layout, and only the configurations listed in the SoC Platform Design Guide have been simulated and validated by Intel. It is up to the customer to simulate and validate memory configurations not listed within the SoC Platform Design Guide.

40.1.1.2 Supplementary DDR4 Signals Not Covered By The DDR4 Standard

No supplementary signals.

40.2 PCI Express Root Port Interface

The SoC has up to 16 PCI Express 3.0 lanes, depending on configuration and product SKU, see the PCI Express Section 11.2, "Feature List" on page 372 section of this document for the PCI Express options supported by this SoC.

The SoC PCI Express interface was designed to the PCI Express 3.0 Base specification revision 3.0, made available in November 2010. In August 2007, PCI-SIG announced that PCI Express 3.0 would carry a bit rate of 8 gigatransfers per second (GT/s), and that it would be backward compatible with existing PCI Express implementations. New features for the PCI Express 3.0 specification include a number of optimizations for enhanced signaling and data integrity, including transmitter and receiver equalization, PLL improvements, clock data recovery, and channel enhancements for currently supported topologies.

PCI Express 3.0 upgrades the encoding scheme to 128b/130b from the previous 8b/10b encoding, reducing the overhead to approximately 1.54% ((130–128)/130), as opposed to the 20% overhead of PCI Express 2.0. This is achieved by a technique called "scrambling" that applies a known binary polynomial to a data stream in a feedback topology. Because the scrambling polynomial is known, the data can be recovered by running it through a feedback topology using the inverse polynomial. PCI Express 3.0's 8 GT/s bit rate effectively delivers 985 MB/s per lane, practically doubling the lane bandwidth relative to PCI Express 2.0.

On November 18, 2010, the PCI Special Interest Group officially published the finalized PCI Express 3.0 specification to its members to build devices based on this new version of PCI Express.

PCI Express 3.1 was released in 2014, making various tweaks to the published standard.

40.2.1 Deviations From The PCI Express 3.0 Standard

No known deviations.

40.2.2 Supplementary PCI Express Signals Not Covered By The PCI Express 3.0 Standard

No supplementary signals.

40.3 SATA Interface

The SoC has up to 16 SATA 3.1 lanes, depending on configuration and product SKU, see Chapter 12, "SATA Controller" of this document for the SATA options supported by this SoC.

The Serial ATA International Organization presented the draft specification of SATA 6 Gbit/s physical layer in July 2008, and ratified its physical layer specification on August 18, 2008. The SoC SATA interface was designed to this standard.

The full 3.0 standard was released on May 27, 2009. It runs with a native transfer rate of 6.0 Gbit/s, and taking 8b/10b encoding into account, the maximum uncoded transfer rate is 4.8 Gbit/s (600 MB/s). The theoretical burst throughput of SATA 6.0 Gbit/s is double that of SATA 2.0. SATA 3.1 was released July 2011, introducing new features, supporting the same transfer rate as SATA 3.0, both being backward compatible with SATA 2.0.

40.3.1 Deviations From The SATA 3.1 Standard

No known deviations.

40.3.2 Supplementary SATA Signals Not Covered By The SATA 3.1 Standard

No supplementary signals.

40.4 USB Interface

The SoC has up to four USB 3.0 ports, depending on configuration and product SKU, see the USB Section 14.2, "Feature List" on page 495 of this document for the USB options supported by this SoC.

The SoC USB interface was designed to the USB 3.0 standard released in November 2008. The standard defines a new SuperSpeed mode with a signaling speed of 5 Gbit/s and, due to encoding overhead, usable data rate of up to 4 Gbit/s (500 MB/s). A USB 3.0 port is usually colored blue, and is backwards compatible with USB 2.0.

While the SoC does NOT support USB 3.1, the Universal Serial Bus Revision 3.1 Specification was released July, 2013. The USB 3.1 specification introduces a faster transfer mode called "SuperSpeed USB 10 Gbps"; its logo features a SuperSpeed+ (stylized as SUPERSPEED+) caption. The USB 3.1 standard increases the signaling rate to 10 Gbit/s, double that of USB 3.0, and reduces line encoding overhead to just 3% by changing the encoding scheme to 128b/132b.

The USB 3.1 standard is backward compatible with USB 3.0, and USB 3.0 is backward compatible with USB 2.0.

A USB 3.0 port makes use of SuperSpeed PHYs, in addition to USB 2.0 PHYs. The SoC USB controller supports using just the USB 2.0 PHYs, to implement USB 2.0 ports, or combine the USB 2.0 PHYs with the SuperSpeed PHYs to implement a fully compliant USB 3.0 port; up to a total of four USB ports, depending on configuration and product SKU.

40.4.1 Deviations From The USB 3.0 Standard

No known deviations.

40.4.2 Supplementary USB Signals Not Covered By The USB 3.0 Standard

No supplementary signals.

40.4.3 USB 2.0 Standard

Refer to the *Universal Serial Bus Specification, Revision 2.0*.

40.5 SMBus Interface

The SoC has several SMBus controllers, depending on configuration and product SKU, see the SMBus Section 27.2, "Feature List" on page 709 of this document for the SMBus options supported by this SoC.

The SoC SMBus interface is designed to the SMBus 3.0 standard.

40.5.1 Deviations From The SMBus 2.0 Standard

SMBus/I2C Characteristics of the SDA and SCL Bus Do Not Meet Specification with minor deviation:

SMBus/I2C tSU;STA (set-up time for a repeated START condition) and tSU;STO (set-up time for STOP condition) show certain level violation for 100KHz speed, 400KHz speed and 1MHz Speed.

- For 100KHz tsusta min spec 4.7us vs 4.62 measured, 1.59%
- For 100KHz tsusto min spec 4.0us vs 3.96 measured, 0.847%
- For 400KHz tsusta min spec 0.6us vs 0.529 measured, 11.8%
- For 1MHz tsusta min spec 0.26us vs 0.202 measured, 22%
- For 1MHz tsusto min spec 0.26us vs 0.240 measured, 7.58%

SMBus/I2C tHIght (High period of the SCL clock) shows certain level violation for 400KHz speed and 1MHz Speed.

- For 400KHz tHight min spec 0.6us vs 0.59us measured, 0.7%
- For 1MHz tHight min spec 0.26us vs 0.2us measured, 0.847%

40.5.2 Supplementary SMBus Signals Not Covered By The SMBus 2.0 Standard

No supplementary signals.

40.6 LPC Interface

The SoC LPC interface was designed to the LPC Specification 1.1, August 2000, see the LPC Section 20.2, "Feature List" on page 628 of this document for the LPC options supported by this SoC.

40.6.1 Deviations From The LPC 1.1 Standard

No known deviations.

40.6.2 Supplementary LPC Signals Not Covered By The LPC 1.1 Standard

No supplementary signals.

40.7 eMMC Interface

The SoC eMMC interface was designed to the JEDEC Standard Embedded Multi-Media Card (eMMC) Electrical Standard (5.0), JESD84-B50 (Revision of JESD84-B451, June 2012) September 2013, see the eMMC Section 17.2, "Feature List" on page 558 of this document for the eMMC options supported by this SoC.

The eMMC standard specifies the electrical characteristics at the device end, and not the host. The electrical characteristics at the device end are greatly affected by the physical routing between the host and device. See the SoC Platform Design Guide for routing guidelines that meet the eMMC electrical characteristics at the device end of the channel.

40.7.1 Deviations From The eMMC 5.0 Standard

Given the electrical characteristics of our eMMC I/Os, and the SoC routing guidelines provided by the SoC Platform Design Guide for the eMMC signals, smaller overshoot/undershoot excursions than what the eMMC standard allows will be seen at the device end of the channel. This does not mean we deviate from the eMMC standard, rather we more strictly control overshoot/undershoot than is required by the eMMC standard.

40.7.2 Supplementary eMMC Signals Not Covered By The eMMC 5.0 Standard

No supplementary signals.

40.8 HSUART Interface

The SoC HSUARTs are compatible with the Texas Instruments* PC16550D HSUART specification. See the HSUART Section 18.2, "Feature List" on page 568 of this document for the HSUART options supported by this SoC.

40.8.1 Deviations From Texas Instruments PC16550D Standard

The I/Os of the original Texas Instruments PC16550D used 5.0V signaling. The HSUARTs within the SoC deviate from the Texas Instruments PC16550D standard in that the SoC HSUART I/Os are implemented using the 3.3V GPIO buffers, see Section 40.13.3, "3.3V GPIO (CMOS-HV Buffer Type) Electrical Characteristics" on page 1066 for the Electrical Characteristics.

40.8.2 Supplementary HSUART Signals Not Covered By The Texas Instruments PC16550D Standard

No supplementary signals.

40.9 Serial Peripheral Interface (SPI)

See Chapter 19, "Serial Peripheral Interface (SPI)" of this document for the SPI options supported by this SoC.

There is no industry standard for the SPI bus. The electrical and timing characteristics for this interface are described below.

40.9.1 Interface Timing Parameters and Waveforms

Table 40-1, Table 40-2, and Table 40-3 contain the timing specifications for the SPI interface signals.

Table 40-1. SPI (17.14MHz) Signal Timing Specifications

Symbol	Parameter	Min	Typical	Maximum	Unit
t180	Serial Clock Frequency	16.9	-	17.4	MHz
t183	T_{CO} of SPI_MOSI_IO[0] with respect to serial clock falling edge at the host.	-5	-	13	ns
t184	Setup of SPI_MISO_IO[1] with respect to serial clock falling edge at the host.	16	-	-	ns
t185	Hold of SPI_MISO _IO[1] with respect to serial clock falling edge at the host.	0	-	-	ns
t186	Setup of SPI_CS_N[1:0] assertion with respect to serial clock rising at the host.	30	-	-	ns
t187	Hold of SPI_CS_N[1:0] deassertion with respect to serial clock falling at the host.	30	-	-	ns
t188	SPI_CLK High Time	26.37	-	-	ns
t189	SPI_CLK Low Time	26.82	-	-	ns

Table 40-2. SPI (30MHz) Signal Timing Specifications

Symbol	Parameter	Minimum	Typical	Maximum	Unit
t180	Serial Clock Frequency	29.83	-	30.6	MHz
t183	T_{CO} of SPI_MOSI _IO[0] with respect to serial clock falling edge at the host.	-5	-	5	ns
t184	Setup of SPI_MISO_IO[1] with respect to serial clock falling edge at the host.	8	-	-	ns
t185	Hold of SPI_MISO_IO[1] with respect to serial clock falling edge at the host.	0	-	-	ns
t186	Setup of SPI_CS_N[1:0] assertion with respect to serial clock rising at the host.	30	-	-	ns
t187	Hold of SPI_CS_N[1:0] deassertion with respect to serial clock falling at the host.	30	-	-	ns
t188	SPI_CLK High Time	14.88	-	-	ns
t189	SPI_CLK Low Time	15.18	-	-	ns

Table 40-3. SPI (48MHz) Signal Timing Specifications

Symbol	Parameter	Minimum	Typical	Maximum	Unit
t180	Serial Clock Frequency	47	-	49	MHz
t183	T_{CO} of SPI_MOSI_IO[0] with respect to serial clock falling edge at the host.	-3	-	4.5	ns
t184	Setup of SPI_MISO_IO[1] with respect to serial clock falling edge at the host.	5	-	-	ns
t185	Hold of SPI_MISO_IO[1] with respect to serial clock falling edge at the host.	0	-	-	ns
t186	Setup of SPI_CS_N[1:0] assertion with respect to serial clock rising at the host.	30	-	-	ns
t187	Hold of SPI_CS_N[1:0] deassertion with respect to serial clock falling at the host.	30	-	-	ns
t188	SPI_CLK High Time	5	-	-	ns
t189	SPI_CLK Low Time	10.8	-	-	ns

Figure 40-1. SPI Timing Diagram



Table 40-4. CS# Setup and CS# Hold

Parameter	Value	Description
CS# Setup	2.5 ns (min)	SPI_CS# low to SPI_CLK high
CS# Hold	2.5 ns (min)	SPI_CLK low to SPI_CS# low

Figure 40-2. Dual-Output Fast Read Timing with 24-bit Addressing



Figure 40-3. Dual I/O Fast Read Timing with 24-bit Addressing



Figure 40-4. Quad Output Fast Read Timing with 24-bit Addressing



Figure 40-5. Quad I/O Fast Read Timing with 24-bit Addressing



40.9.2 SPI Electrical Characteristics

The I/O buffers used for the SPI interface are the 3.3V GPIO (CMOS-HV Buffer Type) buffers, see Section 40.13.3, "3.3V GPIO (CMOS-HV Buffer Type) Electrical Characteristics" on page 1066 for the Electrical Characteristics.

40.10 LAN Interface

The SoC includes up to two integrated LAN controllers, with up to two LAN ports each, depending on configuration and product SKU. See the LAN Section 13.3, "Feature List" on page 417 of this document for the LAN options supported by this SoC.

Each LAN port is configurable, supporting various electrical interfaces, depending on configuration and product SKU. Each type of supported electrical interface is listed separately in the sections below.

40.10.1 10GBASE-KR Interface

The SoC 10GBASE-KR interface was designed to the IEEE802.3 Standard.

40.10.1.1 Deviations From The IEEE802.3 10GBASE-KR Standard

No known deviations.

40.10.1.2 Supplementary 10GBASE-KR Signals Not Covered By The IEEE802.3 10GBASE-KR Standard

No supplementary signals.

40.10.2 SFI Interface

The SoC SFI interface was designed to the SFF-8431 Revision 4.1 Standard.

40.10.2.1 Deviations From The SFF-8431 SFI Standard

The SoC supports only SFP+ DA (Direct Attach; i.e., passive twin-ax cable assembly) and limiting optical modules. It will not support linear optical modules.

Linear modules are modules which contain a linear receiver, whereas limiting modules contain a limiting receiver.

40.10.2.2 Supplementary SFI Signals Not Covered By The SFF-8431 SFI Standard

No supplementary signals.

40.10.3 2500BASE-X Interface

2500BASE-X is not an IEEE standard, but leverages the electricals from IEEE802.3ae-2002 (XAUI). 2500BASE-X is term used by Broadcom to describe 2.5Gbit/s (3.125GBd) operation.

40.10.3.1 Deviations From The 2500BASE-X Industry Convention

No known deviations.

40.10.3.2 Supplementary 2500BASE-X Signals Not Covered By The 2500BASE-X Industry Convention

No supplementary signals.

40.10.4 1000BASE-KX Interface

The SoC 1000BASE-KX interface was designed to the IEEE802.3 Standard.

40.10.4.1 Deviations From The IEEE802.3 1000BASE-KX Standard

No known deviations.

40.10.4.2 Supplementary 1000BASE-KX Signals Not Covered By The IEEE802.3 1000BASE-KX Standard

No supplementary signals.

40.10.5 SGMII Interface

The SoC SGMII interface was designed to the Cisco Systems* SGMII Industry Standard, Revision 1.7.

40.10.5.1 Deviations From The Cisco Systems SGMII Industry Standard

No known deviations, other than Half Duplex mode is not supported, only Full Duplex mode is supported.

40.10.5.2 Supplementary SGMII Signals Not Covered By The Cisco Systems SGMII Industry Standard

No supplementary signals.

40.10.6 Management Data Input/Output (MDIO)

The MDIO interface is also known as Serial Management Interface (SMI) or Media Independent Interface Management (MIIM). The MDIO interface connects Media Access Control (MAC) devices with Ethernet physical layer (PHY) circuits.

The MDIO interface is defined by Clause 22 of IEEE 802.3, and is augmented by Clause 45.

The SoC MDIO interface supports both Clause 22 and Clause 45. However, the only I/O voltage supported is the 3.3V option.

40.10.6.1 Deviations From IEEE 802.3

Clause 22 and Clause 45 of IEEE 802.3 support multiple voltage options for the I/O buffers. The only I/O voltage option supported by the SoC is 3.3V, and the specific I/O buffers used for the MDIO interface are the 3.3V GPIO (CMOS-HV Buffer Type) buffers, see Section 40.13.3, "3.3V GPIO (CMOS-HV Buffer Type) Electrical Characteristics" on page 1066 for the Electrical Characteristics.

40.10.6.2 Supplementary MDIO Signals Not Covered By Clause 22 and Clause 45 of IEEE 802.3

No supplementary signals.

40.10.7 Slave ("Target") Network Controller Sideband Interface (NC-SI)

The SoC NC-SI Slave interface was designed to the *DMTF Network Controller Sideband Interface (NC-SI) Specification, Document Number: DSP0222, Version 1.0.0.*

40.10.7.1 Deviations From The NC-SI Standard

No known deviations.

40.10.7.2 Supplementary NC-SI Signals Not Covered By The NC-SI Standard

No supplementary signals.

40.11 SoC Serial Voltage Identification (SVID) Interface

It consists of three signals. See Section 34.6, "Serial Voltage Identification (sVID) Controller" on page 908 of this document for the options supported by this SoC.

40.11.1 SoC SVID Timing Deviates from the VR13.0 Specification

The SoC SVID timing deviates from the VR13.0 specification for the following parameters:

- Tco_max_CPU Clock to data delay @bump = 5µs versus the 0.65µs listed in the VR13.0 specification
- Tco_min_CPU Clock to data delay @bump = 1µs versus the -3.6µs listed in the VR13.0 specification
- Tsu_CPU - Setup time of signal VDIO at CPU side = 15µs versus the 1µs listed in the VR13.0 specification.

40.11.2 Supplementary Signals Not Covered By The SVID Standard

No supplementary signals.

40.12 SoC JTAG and Debug Interfaces

The SoC JTAG/Debug interface was designed to the IEEE Std 1149.1 Standard. See Chapter 38, "JTAG and Debug Ports" of this document for the options supported by this SoC.

The IEEE standard for JTAG does not specify the electrical characteristics of the interface signals, only the functional requirements. The intent is to not limit JTAG by the electrical characteristics of any existing device or I/O technology, but to support any device with existing and future I/O technologies. The JTAG specifications include guidance for interconnecting multiple devices using disparate I/O technologies.

As is the case, the I/O technology used to design the SoC JTAG/Debug I/Os are implemented using the 1.05V GPIO buffers, see Section 40.13.1, "1.05V GPIO (CMOS-LV Buffer Type) Electrical Characteristics" on page 1062 for the Electrical Characteristics.

40.12.1 Deviations From The JTAG Standard

No known deviations.

40.12.2 Supplementary Signals Not Covered By The JTAG Standard

No supplementary signals.

40.13 Customer General Purpose I/O (GPIO) Interface

The SoC has several pins that are configurable as GPIO. See the GPIO Section 26.1, "GPIO Ball and Signal Names" on page 686 of this document for the GPIO options supported by this SoC.

GPIO transceivers are Intel custom circuit designs, and do not comply to any public specifications. There are three classes (types) of GPIO transceivers used in this SoC: 1.05V GPIO, 1.8V GPIO, and 3.3V GPIO.

Many SoC signals make use of the same buffers as the GPIO signals. All SoC signals are listed in Table 39-1. SoC signals which are implemented using the GPIO buffers contain either CMOS-LV, CMOS-MV, or CMOS-HV in the column "Buffer Type" of Table 39-1.

The electrical characteristics for each class of GPIO is listed below in separate sections.

40.13.1 1.05V GPIO (CMOS-LV Buffer Type) Electrical Characteristics

40.13.1.1 Receiver Electrical Characteristics

The tables below list the DC and AC Characteristics of the receiver.

Table 40-5. 1.05V GPIO Receiver DC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition	Unit	Notes
Power Supply	V1P05		1.05		N/A	V	+/- 5%
High-Level Input Voltage	Vih	0.65*V1P05			N/A	V	
Low-Level Input Voltage	Vil			0.35*V1P05	N/A	V	
Input Hysteresis	Vhys	50			N/A	mV	
Input Leakage	Lin	-50		50	V1P05/GND	uA	
Input Capacitance	Cin			5	N/A	pF	

Table 40-6. 1.05V GPIO Receiver AC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Unit	Notes
Input Frequency	Fin	N/A		533	MHz	
Input Rise/Fall	Irise/Ifall	N/A		6	ns	

The figure below depicts the receiver timing.

Figure 40-6. 1.05V GPIO Receiver Timing



40.13.1.2 Driver Electrical Characteristics

The tables below list the DC and AC Characteristics of the driver.

Table 40-7. 1.05V GPIO Driver DC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition	Unit	Notes
Power Supply	V1P05		1.05		N/A	V	+/- 5%
Driver Pullup Impedance	Zup	30	50	90	N/A	Ohm	
Driver Pulldown Impedance	Zdn	12	20	28	N/A	Ohm	
High-Level Output Voltage	Voh	V1P05-0.3			-2mA	V	
Low-Level Output Voltage	Vol			0.2	3mA	V	

Table 40-8. 1.05V GPIO Driver AC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition (Cap to GND)	Unit	Notes
Output Frequency	Fout	N/A		533	0.15pF	MHz	
Output Rise / Fall Rate	Orise/Ofall	N/A	N/A	0.2	0.15pF	ns	Output Rise Rate = -(Output Fall Rate)

The figure below depicts the driver timing.

Figure 40-7. 1.05V GPIO Driver Timing



40.13.2 1.8V GPIO (CMOS-MV Buffer Type) Electrical Characteristics

40.13.2.1 Receiver Electrical Characteristics

The tables below list the DC and AC Characteristics of the receiver.

Table 40-9. 1.8V GPIO Receiver DC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition	Unit	Notes
Power Supply	V1P80		1.8		N/A	V	+/- 5%
High-Level Input Voltage	Vih	0.65*V1P80			N/A	V	
Low-Level Input Voltage	Vil			0.35*V1P80	N/A	V	
Input Hysteresis	Vhys	100			N/A	mV	
Input Leakage	Lin	-10		10	V1P80/GND	uA	
Input Capacitance	Cin			5	N/A	pF	

Table 40-10. 1.8V GPIO Receiver AC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Unit	Notes
Input Frequency	Fin	N/A		400	MHz	
Input Rise/Fall	Irise/Ifall	N/A		6	ns	

The figure below depicts the receiver timing.

Figure 40-8. 1.8V GPIO Receiver Timing



40.13.2.2 Driver Electrical Characteristics

The tables below list the DC and AC Characteristics of the driver.

Table 40-11. 1.8V GPIO Driver DC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition	Unit	Notes
Power Supply	V1P80		1.8		N/A	V	+/- 5%
Output Impedance	Zout	40	50	60	N/A	Ohm	
High-Level Output Voltage	Voh	V1P80-0.45			-2mA	V	
Low-Level Output Voltage	Vol			0.45	2mA	V	

Table 40-12. 1.8V GPIO Driver AC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition (Cap to GND)	Unit	Notes
Output Frequency	Fout	N/A		100 200	30pF 15pF	MHz	
Output Rise / Fall Rate	Orise/Ofall	0.4	N/A	0.7	30pF	V /ns	Output Rise Rate = -(Output Fall Rate)

The figure below depicts the driver timing.

Table 40-13. 1.8V GPIO Driver Timing



40.13.3 3.3V GPIO (CMOS-HV Buffer Type) Electrical Characteristics

40.13.3.1 Receiver Electrical Characteristics

The tables below list the DC and AC Characteristics of the receiver.

Table 40-14. 3.3V GPIO Receiver DC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition	Unit	Notes
Power Supply	V3P30		3.3		N/A	V	+/- 5%
High-Level Input Voltage	Vih	0.625*V3P30			N/A	V	
Low-Level Input Voltage	Vil			0.25*V3P30	N/A	V	
Input Hysteresis	Vhys	50			N/A	mV	
Input Leakage	Lin	-10		10	V3P30/GND	uA	
Input Capacitance	Cin			7	N/A	pF	

Table 40-15. 3.3V GPIO Receiver AC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Unit	Notes
Input Frequency	Fin	N/A		208	MHz	
Input Rise/Fall	Irise/Ifall	N/A		6	ns	

The figure below depicts the receiver timing.

Table 40-16. 3.3V GPIO Receiver Timing



40.13.3.2 Driver Electrical Characteristics

The tables below list the DC and AC Characteristics of the driver.

Table 40-17. 3.3V GPIO Driver DC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition	Unit	Notes
Power Supply	V3P30		3.3		N/A	V	+/- 5%
Output Impedance	Zout	40	50	60	N/A	Ohm	
High-Level Output Voltage	Voh	V3P30-0.45			-3mA	V	
Low-Level Output Voltage	Vol			0.45	3mA	V	

Table 40-18. 3.3V GPIO Driver AC Characteristics

Parameter	Symbol	Minimum	Nominal	Maximum	Test Condition (Cap to GND)	Unit	Notes
Output Frequency	Fout	N/A		125 50	15pF 30pF	MHz	
Output Rise / Fall Rate	Orise/Ofall	0.6		1.4	30pF	V /ns	Output Rise Rate = -(Output Fall Rate)

The figure below depicts the driver timing.

Figure 40-9. 3.3V GPIO Driver Timing



40.14 Miscellaneous Interfaces

Miscellaneous signals not included in the sections above, are not defined by any industry standard, and are custom SoC signals defined by Intel. Three different types of Intel custom electrical interfaces were used in implementing these interfaces.

Many SoC signals make use of the same buffers as the GPIO signals. All SoC signals are listed in Table 39-1, "Signal Pin Name Directory - Sorted by Name" on page 995. SoC signals which are implemented using the GPIO buffers contain either CMOS-LV, CMOS-MV, or CMOS-HV in the column "Buffer Type" of Table 39-1.

Chapter 39, "Signal Pin Names and Signal MUXing" lists all of the SoC signals along with their "V Group" (Voltage Group).

See the subsections below for the electrical characteristics of each "V Group".

40.14.1 Signals of "V Group V1P05" (CMOS-LV Buffer Type)

See Section 40.13.1, "1.05V GPIO (CMOS-LV Buffer Type) Electrical Characteristics" on page 1062 for the Electrical Characteristics of signals within this group.

40.14.2 Signals of "V Group V1P80" (CMOS-MV Buffer Type)

See Section 40.13.2, "1.8V GPIO (CMOS-MV Buffer Type) Electrical Characteristics" on page 1064 for the Electrical Characteristics of signals within this group.

40.14.3 Signals of "V Group V3P30" (CMOS-HV Buffer Type)

See Section 40.13.3, "3.3V GPIO (CMOS-HV Buffer Type) Electrical Characteristics" on page 1066 for the Electrical Characteristics of signals within this group.

§ §

41 Operating Conditions and Power Requirements

41.1 Absolute Maximum and Minimum Ratings

For proper functional operation, all processor electrical and thermal requirements must be satisfied. These are shown starting with Section 41.2, "Normal Operating Conditions" on page 1070.

When the device is subjected to conditions outside the functional operation condition limits, but within absolute maximum and minimum ratings, neither functionality nor long-term reliability can be expected. If a device is returned to conditions within functional operation limits after having been subjected to conditions outside these limits, but within the absolute maximum and minimum ratings, the device may be functional, but with its lifetime degraded depending on exposure to conditions exceeding the functional operation condition limits.

At conditions exceeding absolute maximum and minimum ratings, neither functionality nor long-term reliability is expected. Moreover, devices that are subjected to these conditions for any length of time, will either not function or its reliability will be severely degraded when returned to conditions within the functional operating condition limits.

41.1.1 Component Storage Conditions Specification

This section applies to component-level storage prior to board attach. Environmental storage condition limits define temperature and relative humidity to which the device is exposed to while being stored in the applicable Intel shipping media trays, reels, and moisture barrier bags and boxes, and the component is not electrically connected.

41.1.1.1 Prior to Board-Attach

Table 41-1 specifies absolute maximum and minimum storage temperature and humidity limits for given time durations. Failure to adhere to specified limits can result in physical damage to the component. If this is suspected, Intel recommends a visual inspection to determine possible physical damage to the silicon or surface components.

Table 41-1. Storage Condition Ratings - Prior to Board-Attach

Symbol	Parameter	Minimum	Maximum	Unit
$T_{ABSOLUTE\ STORAGE}$	Device storage temperature when exceeded for any length of time.	-25	125	°C
$T_{SUSTAINED\ STORAGE\ TIME\ AND\ TEMPERATURE}$	The minimum/maximum device storage temperature for a sustained period of time.	-5	40	°C
$T_{SHORT\ TERM\ STORAGE}$	The ambient storage temperature and time for up to 72 hours.	-25	85	°C
$RH_{SUSTAINED\ STORAGE}$	The maximum device storage relative humidity for up to 30 months.		60% at 24 °C	

Notes:
1. Specified temperatures are not to exceed values based on data collected. Exceptions for surface mount re-flow are specified by the applicable JEDEC standard. Non-adherence may affect processor reliability.
2. Component product device storage temperature qualification methods may follow JESD22-A119 (low temperature) and JESD22-A103 (high temperature) standards when applicable for volatile memory.
3. Component stress testing is conducted in conformance with JESD22-A104.
4. The JEDEC J-JSTD-020 moisture level rating and associated handling practices apply to all moisture sensitive devices removed from the moisture barrier bag.

41.1.1.2 Post Board-Attach

The storage condition limits for the component once attached to the application board are not specified.

Intel does not conduct component-level certification assessments post board-attach given the multitude of attach methods and board types used by customers.

Provided as general guidance only, board-level Intel-branded products are specified and certified to meet the following temperature and humidity limits:

- Non-Operating Temperature Limit: -40 °C to 70 °C
- Humidity: 50% to 90%, non-condensing with a maximum wet-bulb of 28 °C

41.2 Normal Operating Conditions

41.2.1 Component Temperature

Table 41-2 specifies the normal operating temperature range for product SKUs that feature Commercial Temperature Range and for product SKUs that feature Extended Temperature Range. The list of product SKUs is in Chapter 1, "Introduction and Product Offerings."

All supply voltage requirements, input signal requirements, and output signal characteristics are specified for the normal operating temperature range of the device. The temperature range is specified in terms of the Package Junction Temperature (Tj) which is the temperature of the die active surface. For a platform board and chassis using the device, the design must maintain an operational Tj within the specified range.

Table 41-2. Component Temperature Range

Parameter	Symbol	Minimum	Maximum	Unit	SoC Product SKU Feature
Package Junction Temperature	Tj[1]	0	100	°C	Commercial Temperature
		-40[2]	100	°C	Extended Temperature

1. All SKU thermal values are based on maintaining Tj minimum and maximum. Based on product SKU, the SoC has its DTS_{MAX} value (also called REF_TEMP) set at the Intel factory so that the SoC does not throttle when running a TDP workload and meet the SoC T_{CASE_MAX} specification. DTS_{MAX} is described in Chapter 35, "Thermal Management".
2. While this temperature is lower than the specified minimum $T_{ABSOLUTE\ STORAGE}$ value, the Package Junction Temperature value assumes the part will be powered-on and hence won't stay at the minimum junction temperature for a long time

41.2.2 Supply Voltage and Current Requirements

Table 41-3 specifies the device voltage supply requirements for each of the voltage supply groups. These groups are described in Table 32-1, "Signal Descriptions" on page 893.

For the table below, the following definitions apply:

- **DC VR Error**
  This is the difference between the constant load VR output voltage and the measured output voltage averaged over time (tens of ms).

- **DC Tolerance**
  This is the three sigma of "DC VR Error", over the range of conditions, load and lifetime.

- **VR Ripple**
  This is the variation in the output voltage of a regulator due to the switching/sampling characteristics of the regulator. This ripple can be most easily measured by looking at the supply output under a constant load, across the range of loads. The ripple frequency will be at the bandwidth of the regulator.

- **AC Tolerance**
  The response to transients (Istep divided by di/dt) generated by the SOC or other platform components (e.g., feed-through from the VR input supply, which may have other loads).

- **Total Tolerance** = DC Tolerance + VR Ripple + AC Tolerance

- **AVP Sense Tolerance**
  This is the tolerance of the load line sensing circuitry over the range of conditions, load, and lifetime.

- **Total Tolerance With Load Line** = (IxRll) + DC Tolerance + VR Ripple + AC Tolerance + AVP Sense Tolerance = (IxRll) + Total Tolerance
  Where Rll is the Load Line Resistance.

The measurement points for the SoC VR specifications are at the SoC (the load). If access at the SoC is not practical, the measurements may be taken at the input of the VR sense signals, which is nearly identical to what the SoC receives.

Table 41-3. Voltage Supply Requirements Under Normal Operating Conditions

Group	Parameter		Typical (V)	DC Tolerance	VR Ripple	Total Tolerance
VCC	Dynamic VID voltage for core circuitry (variable, switched internally)	SVID V_{BOOT}	1	± 6mV	N/A	Total Tolerance With Load Line ±50mV See Table 41-4, "SoC VCC Load Line"
		SVID	0.52 - 1.24			
		Nominal	1.15			
VNN	Dynamic VID voltage for un-core circuitry (variable, always-on voltage supply)	SVID V_{BOOT}	1	± 0.5%	N/A	± 6%
		SVID	0.65 - 1.24			
		Nominal	1.05			
VCCRAM	Dynamic VID for internal circuitry (variable, switched internally)	SVID V_{BOOT}	1	± 0.5%	N/A	± 7%
		SVID	0.75 - 1.20			
		Nominal	1.15			
VDDQ	Static VID for internal Standard DDR4 circuitry (static, switched internally). *See Note below table.*	SVID V_{BOOT}	1 or 1.20	± 8mV	N/A	+60mV, -38mV (1.260-1.162 V)
		Nominal	1.20			
VCCREF	VCC reference voltage		1.24	± 2.1%	N/A	± 50mV
V1P05	Device internal circuitry (always-on voltage supply, switched internally)		1.05	± 0.6%	± 3mV VR Ripple for frequencies less than 1MHz	± 25mV
V1P80	Device internal circuitry (always-on voltage supply, switched internally)		1.8	± 2.1%	N/A	± 72mV
V3P30	Device internal circuitry (always-on voltage supply, switched internally)		3.3	± 2%	N/A	± 165mV
VRTC	All power states other than G3 Mechanical-Off state		3.3	± 2%	N/A	± 165mV
VRTC	G3 State: From Real Time Clock (RTC) battery supply		2.0 - 3.0	± 2%	N/A	± 165mV

Note: DDR4 DRAM Activating Power (VPP) supply (2.5 V nominal, 2.375 V min, 2.75 V max) goes to the DIMM component only and not to the SoC.

Table 41-4. SoC VCC Load Line

Vcc Tolerance / Load Line / Power		Units
VCC_{MAX} =	VID (V) – 2.3 mΩ * ICC (A) + 50 mV	V
VCC_{TYP} =	VID (V) – 2.3 mΩ * ICC (A)	
VCC_{MIN} =	VID (V) – 2.3 mΩ * ICC (A) - 50 mV	
PVCC =	ICC (A) * VCC (V)	W
Total Tolerance	±50mV	V

Adequate supply current is required for each device voltage group to ensure proper operation. The current requirements vary by product SKU group. The tables below show the characteristics of the current draw for all the SKUs in each group, over the supply voltage ranges shown in Table 41-3.

ICC_{MAX} represents the worst-case transient current that the SoC draws from a given power supply. Platform board designers typically use this value to keep the board Voltage Regulator (VR) current below the VR Over-Current Protection (OCP) limit.

Thermal Design Current (TDC) represents the worst-case sustained current (DC equivalent) that the SoC draws from a given power supply. Platform board designers use this value for proper VR design including VR thermal design.

$DI/DT_{\mathbf{MAX}}$ represents the worst-case current change rate, with the worst-case current change step of $ICC_{\mathbf{STEP}}$.

These parameters determine the characteristics of each VR design, the copper layout connecting the VRs to the SoC; as well as determining the number, type, location, and size of capacitors for each VR.

Note: The ICC_{TDC} values shown in the Supply Current Required tables below are representative numbers. ICC_{TDC} values vary across parts and operating conditions. Only the ICC_{MAX} values are guaranteed when the SoC product has achieved production release.

For the supported features of each SKU, please refer to Chapter 1, "Introduction and Product Offerings."

Table 41-5. Supply Current Required - Server and Cloud Storage SKUs 0, 1, and 2 (See Table 1-1)

Group	Parameter	ICC_{TDC}	ICC_{MAX} in S0	ICC_{MAX} in S5	ICC_{STEP}	DI/DT_{MAX} [A/µs]
VCC	Dynamic VID voltage for core circuitry	18A	39A	0A	35A	510
VNN	Dynamic VID voltage for un-core circuitry	4.2A	4.5A	2.3A	3.5A	50
VCCRAM	Dynamic VID for internal circuitry	6.5A	8A	0A	3A	10
VDDQ	Static VID for internal Standard DDR4 circuitry	2A	5A	0A	3.5A	18
VCCREF	VCC reference voltage	0.3A	0.3A	0A	0.02	0.1
V1P05	Device internal circuitry	10A	12A	2.3A	5A	20
V1P80	Device internal circuitry	1A	1A	0.3A	0.1A	0.1
V3P30	Device internal circuitry	0.5A	0.5A	0.4A	0.5A	1
VRTC	All power states other than G3 Mechanical-Off state	0.5mA	0.5mA		N/A	N/A
	G3 State: From Real Time Clock (RTC) battery supply	N/A	9.5µA		N/A	N/A

Table 41-6. Supply Current Required - Network & Enterprise Storage SKUs 3, 4, 5, 6, and 7 (See Table 1-2) and eTEMP SKUs 11 and 12 (See Table 1-3)

Group	Parameter	ICC_{TDC}	ICC_{MAX} in S0	ICC_{MAX} in S5	ICC_{STEP}	DI/DT_{MAX} [A/µs]
VCC	Dynamic VID voltage for core circuitry	18A	30A	0A	27A	400
VNN	Dynamic VID voltage for un-core circuitry	6.7A	7A	2.3A	5A	80
VCCRAM	Dynamic VID for internal circuitry	6.5A	8A	0A	3A	10
VDDQ	Static VID for internal Standard DDR4 circuitry	2A	5A	0A	3.5A	18
VCCREF	VCC reference voltage	0.3A	0.3A	0A	0.02A	0.1
V1P05	Device internal circuitry	10A	12A	2.3A	5A	20
V1P80	Device internal circuitry	1A	1A	0.3A	0.1A	0.1
V3P30	Device internal circuitry	0.5A	0.5A	0.4A	0.5A	1
VRTC	All power states other than G3 Mechanical-Off state	0.50mA	0.50mA		N/A	N/A
	G3 State: From Real Time Clock (RTC) battery supply	N/A	9.5µA		N/A	N/A

Table 41-7. Supply Current Required - Network & Enterprise Storage SKUs 8 and 9 (See Table 1-2)

Group	Parameter	ICC_{TDC}	ICC_{MAX} in S0	ICC_{MAX} in S5	ICC_{STEP}	DI/DT_{MAX} [A/µs]
VCC	Dynamic VID voltage for core circuitry	7A	11A	0A	10A	120
VNN	Dynamic VID voltage for un-core circuitry	4.2A	4.5A	2A	3.5A	60
VCCRAM	Dynamic VID for internal circuitry	3A	5A	0A	1.5A	5
VDDQ	Static VID for internal Standard DDR4 circuitry	1A	4A	0A	3.5A	18
VCCREF	VCC reference voltage	0.3A	0.3A	0A	0.02A	0.1
V1P05	Device internal circuitry	8A	10A	2.3A	5A	20
V1P80	Device internal circuitry	1A	1A	0.3A	0.1A	0.1
V3P30	Device internal circuitry	0.5A	0.5A	0.4A	0.5A	1
VRTC	All power states other than G3 Mechanical-Off state	0.50mA	0.50mA		N/A	N/A
	G3 State: From Real Time Clock (RTC) battery supply	N/A	9.5µA		N/A	N/A

Table 41-8. Supply Current Required - Network & Enterprise Storage SKU 10 (See Table 1-2) and eTEMP SKU 13 and 14 (See Table 1-3)

Group	Parameter	ICC_{TDC}	ICC_{MAX} in S0	ICC_{MAX} in S5	ICC_{STEP}	DI/DT_{MAX} [A/µs]
VCC	Dynamic VID voltage for core circuitry	4A	4.5A	0A	4A	60
VNN	Dynamic VID voltage for un-core circuitry	4.2A	4.5A	2A	3.5A	60
VCCRAM	Dynamic VID for internal circuitry	2.5A	3A	0A	1.5A	5
VDDQ	Static VID for internal Standard DDR4 circuitry	1A	4A	0A	3.5A	18
VCCREF	VCC reference voltage	0.3A	0.3A	0A	0.02A	0.1
V1P05	Device internal circuitry	8A	10A	2.3A	5A	20
V1P80	Device internal circuitry	1A	1A	0.3A	0.1A	0.1
V3P30	Device internal circuitry	0.5A	0.5A	0.4A	0.5A	1
VRTC	All power states other than G3 Mechanical-Off state	0.50mA	0.50mA		N/A	N/A
	G3 State: From Real Time Clock (RTC) battery supply	N/A	9.5µA		N/A	N/A

§ §

42 Package Mechanical Overview

The SoC is manufactured as a 34 mm x 28 mm Flip-Chip Ball Grid Array (FBGA15) package and consists of a silicon die mounted face down on an organic substrate populated with 1310 solder balls (the term "pins" is also used in this document) on the bottom side. The balls have a mixed pitch—minimum pitch is 0.65 mm. The package contains an integrated heat spreader that is 30.36 mm x 24.36 mm, 1 mm thick. See Figure 42-1 for a representation of the SoC package.

Figure 42-1. SoC Package Drawing



§ §

Volume 4: Registers

February 2018
Order Number: 337018-002

43 Introduction

This volume documents the registers accessible to software running in the IA Host Space. There is a register chapter for each PCI device/function in the Host Root Space. There are additional chapters for other SoC entities that have software-accessible registers. There is also a chapter for the SoC Model-Specific Registers (MSRs).

Note: Accessing unimplemented registers and/or writing reserved bits may result in undefined behavior on the platform.

43.1 Access to Registers in Host Root Space

The registers shown in this volume are those accessible in the SoC Host Root Configuration, Memory and I/O Spaces.

Details of the registers accessible in the Root Space of the Intel® Management Engine (Intel® ME) are not provided to SoC customers.

43.1.1 PCI Configuration Space

Access to the registers in PCI Configuration Space is performed through one of the two Configuration Access Methods (CAMs):

- I/O-indexed - PCI CAM (only the first 256 bytes of the function Configuration Space)
- Memory-mapped - PCI enhanced CAM (ECAM)

These two methods are explained in Section 3.3.1, "How to Access Registers in PCI Configuration Space" on page 185.

The descriptions for the Configuration Registers show the PCI Bus, Device, and Function numbers as Bbus#:Ddevice#:Ffunction#. An example is B0:D17:F0. All three of the numbers are decimal. The register offset address from the B:D:F: is also shown for each Configuration Register and is a hexadecimal value. The structure of the Configuration Registers are defined in the *PCI Local Bus Specification, Revision 3.0* and *PCI Express Base Specification Revision 3.0*.

Note: Some of the registers in Host Root Configuration Space can be accessed and altered through the SMBus-PECI interface by an external component such as a Baseboard Management Controller (BMC). See Chapter 30, "SMBus Controller - Platform Environment Control Interface".

43.1.1.1 Unimplemented Devices/Functions and Registers

Read accesses in the Configuration Space is to unimplemented PCI functions and so the devices return all ones, emulating a Master Abort response. Note that there is no asynchronous error reporting that happens when a configuration-read transaction Master Aborts.

Write accesses in the Configuration Space is to unimplemented PCI functions and so the devices return a normal response.

Software must not attempt, or rely on, reads or writes to unimplemented registers or register bits. Unimplemented registers return all zeros when read. Writes to unimplemented registers are ignored by the SoC. For configuration writes to these registers (requires a Completion), the Completion is returned with a normal completion status (not Master-Aborted).

43.1.2 Memory Space—Relocatable Address

Access to this kind of register requires a base memory address defined in a Base Address Register (BAR). The register is accessed using an offset address that is added to the memory BAR. Memory-Mapped I/O (MMIO) registers are accessed in this fashion. A list of most of the Memory BARs is in Section 3.1.2, "Host Memory Space—Relocatable Memory-Mapped I/O" on page 169.

The register description for this type of register shows the name of the BAR and a hexadecimal offset value.

43.1.3 Memory Space—Fixed Address

Fixed-address registers in the Host Root Memory Space are accessed by software and the SoC hardware. The register locations are not relocatable and a BAR is not associated with the register access. The Host Root address map of these registers is in Section 3.1.1, "Host Memory Space—Regions and Boundaries" on page 166.

The register description for this type of register shows the memory address as a hexadecimal value.

43.1.4 I/O Space—Relocatable Address

Access to this kind of register requires a base I/O-Space address defined in a Base Address Register (BAR). The register is accessed using an offset address that is added to the I/O BAR. A list of the I/O BARs is in Section 3.2.2, "Host I/O Space—Relocatable I/O Addresses" on page 180.

The register description for this type of register shows the name of the I/O BAR and a hexadecimal offset value.

43.1.5 I/O Space—Fixed Address

Fixed-address registers in Host Root I/O Space (also known as I/O Ports) are accessed by the CPU when software executes the following instructions:

- Read: IN, INS INSB, INSW, and INSD
- Write: OUT, OUTS, OUTSB, OUTSW, and OUTSD

The descriptions of these I/O Port instructions are in the *IA-32 Intel® Architecture Software Developer's Manual*, Volume 2. The SoC Host Root address map of these registers is in Section 3.2.1, "Host I/O Space—Fixed I/O Addresses" on page 175

The register description for this type of register shows the I/O Port address as a hexadecimal value.

43.1.6 Sideband Registers

The SoC has an internal messaging mechanism that is used by the internal circuitry. This mechanism includes registers called Sideband Registers that are accessible to BIOS so it can configure and tune the system before the Operating System is loaded. BIOS accesses these Sideband Registers in the Host Root Memory Space. They are located as an offset address from the memory BAR defined as SBREG_BAR. A few Sideband Registers are accessible to BIOS as offsets from the Memory Controller Hub Base Address Register (MCHBAR). For more information, see Section 3.4, "Host Root Space - Host Sideband Register Access" on page 187.

The register description for this type of register shows the name of the memory BAR (either SBREG_BAR or MCHBAR) and a hexadecimal offset value.

43.1.7 Model-Specific Registers (MSR)

These registers are accessed by the CPU when software executes the following instructions:

- RDMSR - Read MSR
- WRMSR - Write MSR

The descriptions of the RDMSR and WRMSR instructions are in the *IA-32 Intel® Architecture Software Developer's Manual*, Volume 2. The access to the SoC Machine Check Registers is through MSRs. The SoC MSRs are all described in Chapter 69, "Model-Specific Registers (MSR)".

43.2 Register Description Terminology

43.2.1 Default Values

Warning: BIOS must not rely on the register Default values provided in this document, and instead verify these values by first reading them.

Some Default values shown in the register-description tables vary by product SKU and are set to values at the factory that are different than published here. Generally, the Default values are set by hardware when the register or register fields are reset. During power-on situations, the original default values set by hardware may be written to different values before BIOS starts executing instructions. Things like Hard Pin Straps, customer-selected Soft Straps, the SoC power-management controller, the Intel® Management Engine (Intel® ME) and the Innovation Engine (IE) may alter the default values before BIOS starts executing instructions. By the time that the Operating System is loaded, BIOS could have also modified what was the Default value.

43.2.2 Software Access Attributes

Table 43-1 is a comprehensive list of software-access attributes used in the register descriptions.

Table 43-1. Register Attributes Definitions

Attribute	Description
RO	**Read Only:** These bits can only be read by software, writes have no effect. The value of the bits is determined by the hardware only which includes pin strapping, soft straps, and internal microcode.
RW	**Read / Write:** These bits can be read and written by software.
RO/C RO/C/V	**Read Clear Variant:** These bits can be read by software, and the act of reading them automatically clears them. Hardware is responsible for writing these bits, and therefore the / V modifier is implied.
WO/1S	**Write 1 to Set:** Writing a '1' to these bits will set them to '1.' Writing '0' will have no effect. Reading will return indeterminate values.
WO/1C	**Write 1 to Clear:** Writing a '1' to these bits will set them to '0.' Writing '1' will have no effect. Reading will return indeterminate values.
RW/O	**Read / Write Once:** These bits can be read by software. After reset, these bits can only be written by software once, after which the bits becomes "Read Only."
RW/L	**Read / Write Lock:** These bits can be read and written by software. The bits can be made to be "Read Only" via a separate configuration bit or other logic.
RW/1C	**Read / Write 1 to Clear:** These bits can be read and cleared by software. Writing a '1' to a bit clears it, while writing a '0' to a bit has no effect.
RW/0C	**Read / Write 0 to Clear:** These bits can be read and cleared by software. Writing a '0' to a bit clears it while writing a '1' has no effect.
RO/P	**RO Sticky:** These bits can only be read by software, writes have no effect. The value of the bits is determined by the hardware only. These bits are only re-initialized to their default value by a PWRGOOD reset.
RW/1S	**Read, Write 1 to Set:** These bits can be read. Writing a '1' to a given bit will set it to '1.' Writing a 0 to a given bit will have no effect. It is not possible for software to set a bit to '0.' The '1'-to-'0' transition can only be performed by hardware. These registers are implicitly /V modified.
RW/P	**R / W Sticky (Persistent):** These bits can be read and written by software. These bits are only re- initialized to their default value by a PWRGOOD reset.
RW/1C/P	**R / W1C Sticky:** These bits can be read and cleared by software. Writing a '1' to a bit clears it, while writing a '0' to a bit has no effect. These bits are only re-initialized to their default value by a PWRGOOD reset.
RW/O/P	If a register is both sticky (persistent) and "once," then the sticky value applies to both the register value and the "once" characteristic. Only a PWRGOOD reset will reset both the value and the "once" so that the register can be written to again.
RW/V RO/V	These bits may be modified by hardware. Software cannot expect the values to stay unchanged.
RW/V/P RO/V/P	These bits may be modified by hardware and are Sticky. Software cannot expect the values to stay unchanged. These bits are re-initialized to their default values by a PWRGOOD reset.
RW/P/L	If a register is both sticky and locked, then the sticky behavior only applies to the value. The sticky behavior of the lock is determined by the register that controls the lock.
RW/V/P/L	These bits can be read or written by software and may be modified by hardware. Software cannot expect the values to stay unchanged. These bits are re-initialized to their default values by a PWRGOOD reset. If a register is both sticky and locked, then the sticky behavior only applies to the value. The sticky behavior of the lock is determined by the register that controls the lock.
RSV	**Reserved:** These bits are reserved for future expansion and their value must not be modified by software. When writing these bits, software must preserve the value read.
NA	**No Access:** These bits are not accessible from the given source. Writes are dropped and Reads return '0.'

43.2.3 Hexadecimal, Binary and Decimal Numbers

Base 16 numbers are represented by a string of hexadecimal digits followed by the character “h” (for example, F82Eh). A hexadecimal digit is a character from the following set: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, A, B, C, D, E, and F. Hexadecimal numbers can also be shown using an “x” character (for example 0x2A).

Base 2 (binary) numbers are represented by a string of 1s and 0s, sometimes followed by the character “b” (for example, 1010001b). The “b” designation is only used in situations where confusion as to the type of the number might arise.

Base 10 numbers are represented by a string of decimal digits followed by the character “d” (for example, 23d). The “d” designation is only used in situations where confusion as to the type of the number might arise.

§ §

44 System Agent - B0, D0, F0

44.1 Introduction and Index

The host-accessible registers for the System Agent are described here. The legend for the register access codes are described in Chapter 43, "Introduction."

44.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 0 (decimal), Function 0. The offset addresses are listed.

Table 44-1. Summary of PCI Configuration Registers—0/0/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19908086	"Device ID and Vendor ID Register (DEVICE_ID_VENDOR_ID_0_0_0_PCI)—Offset 0h" on page 1103
4	4	00000007	"PCI Status and PCI Command Register (PCI_STATUS_COMMAND_0_0_0_PCI)—Offset 4h" on page 1103
8	4	06000000	"PCI Revision ID and PCI Class Code Register (REVISION_ID_CLASS_CODE_0_0_0_PCI)—Offset 8h" on page 1104
C	4	00800000	"Master Latency Timer and Header Type Register (MASTER_LATENCY_TIME_0_0_0_PCI)—Offset Ch" on page 1104
2C	4	00000000	"PCI Subsystem Vendor ID and PCI Subsystem ID (SVID_SID_0_0_0_PCI)—Offset 2Ch" on page 1105
34	4	000000E0	"Capability Register Pointer (CAPPTR_0_0_0_PCI)—Offset 34h" on page 1105
48	4	00000000	"Memory Controller Hub Base Address Register (MCHBAR_LO_0_0_0_PCI)—Offset 48h" on page 1106
4C	4	00000000	"Memory Controller Hub Base Address Register (MCHBAR_HI_0_0_0_PCI)—Offset 4Ch" on page 1106
54	4	00000033	"Device Enable Register (DEVEN_0_0_0_PCI)—Offset 54h" on page 1107
60	4	00000000	"PCI Express Enhanced Configuration Range Base Address Low (PCIEXBAR_LO_0_0_0_PCI)—Offset 60h" on page 1108
64	4	00000000	"PCI Express Enhanced Configuration Range Base Address High (PCIEXBAR_HI_0_0_0_PCI)—Offset 64h" on page 1109
A8	4	00000000	"Top of Upper Usable DRAM Low (TOUUD_LO_0_0_0_PCI)—Offset A8h" on page 1110
AC	4	00000000	"Top of Upper Usable DRAM High (TOUUD_HI_0_0_0_PCI)—Offset ACh" on page 1111
B0	4	00000000	"Base of Data Stolen Memory (BDSM_0_0_0_PCI)—Offset B0h" on page 1112
B4	4	00000000	"Base of Graphics Stolen Memory (BGSM_0_0_0_PCI)—Offset B4h" on page 1113
B8	4	00100000	"Top Segment Memory Base (TSEGMB_0_0_0_PCI)—Offset B8h" on page 1114
BC	4	00100000	"Top of Lower Usable DRAM (TOLUD_0_0_0_PCI)—Offset BCh" on page 1115
DC	4	00000000	"Scratchpad (SKPD_0_0_0_PCI)—Offset DCh" on page 1115
E0	4	010C0009	"Capability ID0 Capability Control (CAPID0_CAPCTRL0_0_0_0_PCI)—Offset E0h" on page 1116
E4	4	00000000	"Capability ID0 A (CAPID0_A_0_0_0_PCI)—Offset E4h" on page 1117
E8	4	00000000	"Capability ID0 B (CAPID0_B_0_0_0_PCI)—Offset E8h" on page 1118
F4	4	00000000	"Manufacturer ID Register (MANUFACTURER_ID_0_0_0_PCI)—Offset F4h" on page 1119

44.1.2 Host Memory Space—MCHBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 44-2. Summary of Memory Mapped I/O Registers for C-Unit—MCHBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
C-Unit Registers			
6C80	8	0000000000000000	"Default VTd Base Address Register (DEFVTDBAR_0_0_0_MCHBAR_C)—Offset 6C80h" on page 1120

Table 44-3. Summary of Memory Mapped I/O Registers for A-Unit—MCHBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
647C	4	00000000	"Spare BIOS (A_CR_SPARE_BIOS_MCHBAR)—Offset 647Ch" on page 1121
6588	4	00000000	"Uncorrectable Error Status Register (A_CR_UNCERRSTS_0_0_0_MCHBAR)—Offset 6588h" on page 1122
658C	4	FFFFFFFF	"Uncorrectable Error Mask Register (A_CR_UNCERRMSK_0_0_0_MCHBAR)—Offset 658Ch" on page 1125
6590	4	00000000	"Uncorrectable Error Severity Register (A_CR_UNCERRSEV_0_0_0_MCHBAR)—Offset 6590h" on page 1127
6594	4	00000000	"First Uncorrectable Error Register (A_CR_UNCFERRSTS_0_0_0_MCHBAR)—Offset 6594h" on page 1129
6598	4	00000000	"Next Uncorrectable Error Register (A_CR_UNCNERRSTS_0_0_0_MCHBAR)—Offset 6598h" on page 1132
659C	4	00000000	"Uncorrectable Error Select Register (A_CR_UNCERRCNTSEL_0_0_0_MCHBAR)—Offset 659Ch" on page 1135
65A0	4	00000000	"Uncorrectable Error Count (A_CR_UNCERRCNT_0_0_0_MCHBAR)—Offset 65A0h" on page 1137
65A4	4	00000000	"Correctable Error Status Register (A_CR_CORERRSTS_0_0_0_MCHBAR)—Offset 65A4h" on page 1138
65A8	4	FFFFFFFF	"Correctable Error Mask Register (A_CR_CORERRMSK_0_0_0_MCHBAR)—Offset 65A8h" on page 1141
65AC	4	00000000	"First Correctable Error Register (A_CR_CORFERRSTS_0_0_0_MCHBAR)—Offset 65ACh" on page 1143
65B0	4	00000000	"Next Correctable Error Register (A_CR_CORNERRSTS_0_0_0_MCHBAR)—Offset 65B0h" on page 1146
65B4	4	FFFFFFFF	"Correctable Error Count Select (A_CR_CORERRCNTSEL_0_0_0_MCHBAR)—Offset 65B4h" on page 1149
65B8	4	00000000	"Correctable Error Count (A_CR_CORERRCNT_0_0_0_MCHBAR)—Offset 65B8h" on page 1151
65C0	8	0000000000000000	"Slice and Channel Hash (A_CR_SLICE_CHANNEL_HASH_0_0_0_MCHBAR)—Offset 65C0h" on page 1152
65D0	4	00000000	"A_CR_ASYM_MEM_REGION0_0_0_0_MCHBAR—Offset 65D0h" on page 1154
65D4	4	00000000	"A_CR_ASYM_MEM_REGION1_0_0_0_MCHBAR—Offset 65D4h" on page 1154

Table 44-4. Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR (Sheet 1 of 6)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
6800	4	00000007	"B-Unit Miscellaneous Configuration (B_CR_BMISC_0_0_0_MCHBAR)—Offset 6800h" on page 1155
6868	4	00000000	"Slice 0 Memory Access Count (B_CR_MEM_ACCESS_COUNT_SLICE0)—Offset 6868h" on page 1155
686C	4	00000000	"Slice 1 Memory Access Count (B_CR_MEM_ACCESS_COUNT_SLICE1)—Offset 686Ch" on page 1155
6870	4	00000000	"IMR0 Base (B_CR_BIMR0BASE_0_0_0_MCHBAR)—Offset 6870h" on page 1156
6874	4	00000000	"IMR0 Mask (B_CR_BIMR0MASK_0_0_0_MCHBAR)—Offset 6874h" on page 1157
6878	8	00000C0061010202	"IMR0 Control Policy (B_CR_BIMR0CP_0_0_0_MCHBAR)—Offset 6878h" on page 1157
6880	8	0000000000000000	"IMR0 Read Access Policy (B_CR_BIMR0RAC_0_0_0_MCHBAR)—Offset 6880h" on page 1158
6888	8	0000000000000000	"IMR0 Write Access Policy (B_CR_BIMR0WAC_0_0_0_MCHBAR)—Offset 6888h" on page 1161
6890	4	00000000	"B_CR_BIMR1BASE_0_0_0_MCHBAR—Offset 6890h" on page 1164
6894	4	00000000	"IMR1 Mask (B_CR_BIMR1MASK_0_0_0_MCHBAR)—Offset 6894h" on page 1165
6898	8	00000C0061010202	"IMR1 Control Policy (B_CR_BIMR1CP_0_0_0_MCHBAR)—Offset 6898h" on page 1165
68A0	8	0000000000000000	"IMR1 Read Access Policy (B_CR_BIMR1RAC_0_0_0_MCHBAR)—Offset 68A0h" on page 1166
68A8	8	0000000000000000	"IMR1 Write Access Policy (B_CR_BIMR1WAC_0_0_0_MCHBAR)—Offset 68A8h" on page 1169
68B0	4	00000000	"Base 0 IMR2 Base (B_CR_BIMR2BASE_0_0_0_MCHBAR)—Offset 68B0h" on page 1172
68B4	4	00000000	"IMR2 Mask (B_CR_BIMR2MASK_0_0_0_MCHBAR)—Offset 68B4h" on page 1173
68B8	8	00000C0061010202	"IMR2 Control Policy (B_CR_BIMR2CP_0_0_0_MCHBAR)—Offset 68B8h" on page 1173
68C0	8	0000000000000000	"IMR2 Read Access Policy (B_CR_BIMR2RAC_0_0_0_MCHBAR)—Offset 68C0h" on page 1174
68C8	8	0000000000000000	"IMR2 Write Access Policy (B_CR_BIMR2WAC_0_0_0_MCHBAR)—Offset 68C8h" on page 1177
68D0	4	00000000	"IMR3 Base (B_CR_BIMR3BASE_0_0_0_MCHBAR)—Offset 68D0h" on page 1180
68D4	4	00000000	"IMR3 Mask (B_CR_BIMR3MASK_0_0_0_MCHBAR)—Offset 68D4h" on page 1181
68D8	8	00000C0061010202	"IMR3 Control Policy (B_CR_BIMR3CP_0_0_0_MCHBAR)—Offset 68D8h" on page 1181
68E0	8	0000000000000000	"IMR3 Read Access Policy (B_CR_BIMR3RAC_0_0_0_MCHBAR)—Offset 68E0h" on page 1182
68E8	8	0000000000000000	"IMR3 Write Access Policy (B_CR_BIMR3WAC_0_0_0_MCHBAR)—Offset 68E8h" on page 1185
68F0	4	00000000	"IMR4 Base (B_CR_BIMR4BASE_0_0_0_MCHBAR)—Offset 68F0h" on page 1188
68F4	4	00000000	"IMR4 Mask (B_CR_BIMR4MASK_0_0_0_MCHBAR)—Offset 68F4h" on page 1189

Table 44-4. Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR (Sheet 2 of 6)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
68F8	8	00000C0061010202	"B-Unit IMR4 Control Policy (B_CR_BIMR4CP_0_0_0_MCHBAR)—Offset 68F8h" on page 1189
6900	8	0000000000000000	"IMR4 Read Access Policy (B_CR_BIMR4RAC_0_0_0_MCHBAR)—Offset 6900h" on page 1190
6908	8	0000000000000000	"IMR4 Write Access Policy (B_CR_BIMR4WAC_0_0_0_MCHBAR)—Offset 6908h" on page 1193
6910	4	00000000	"IMR5 Base (B_CR_BIMR5BASE_0_0_0_MCHBAR)—Offset 6910h" on page 1196
6914	4	00000000	"IMR5 Mask (B_CR_BIMR5MASK_0_0_0_MCHBAR)—Offset 6914h" on page 1197
6918	8	00000C0061010202	"IMR5 Control Policy (B_CR_BIMR5CP_0_0_0_MCHBAR)—Offset 6918h" on page 1197
6920	8	0000000000000000	"IMR5 Read Access Policy (B_CR_BIMR5RAC_0_0_0_MCHBAR)—Offset 6920h" on page 1198
6928	8	0000000000000000	"IMR5 Write Access Policy (B_CR_BIMR5WAC_0_0_0_MCHBAR)—Offset 6928h" on page 1201
6930	4	00000000	"IMR6 Base (B_CR_BIMR6BASE_0_0_0_MCHBAR)—Offset 6930h" on page 1204
6934	4	00000000	"IMR6 Mask (B_CR_BIMR6MASK_0_0_0_MCHBAR)—Offset 6934h" on page 1205
6938	8	00000C0061010202	"IMR6 Control Policy (B_CR_BIMR6CP_0_0_0_MCHBAR)—Offset 6938h" on page 1205
6940	8	0000000000000000	"IMR6 Read Access Policy (B_CR_BIMR6RAC_0_0_0_MCHBAR)—Offset 6940h" on page 1206
6948	8	0000000000000000	"IMR6 Write Access Policy (B_CR_BIMR6WAC_0_0_0_MCHBAR)—Offset 6948h" on page 1209
6950	4	00000000	"IMR7 Base (B_CR_BIMR7BASE_0_0_0_MCHBAR)—Offset 6950h" on page 1212
6954	4	00000000	"IMR7 Mask (B_CR_BIMR7MASK_0_0_0_MCHBAR)—Offset 6954h" on page 1213
6958	8	00000C0061010202	"IMR7 Control Policy (B_CR_BIMR7CP_0_0_0_MCHBAR)—Offset 6958h" on page 1213
6960	8	0000000000000000	"IMR7 Read Access Policy (B_CR_BIMR7RAC_0_0_0_MCHBAR)—Offset 6960h" on page 1214
6968	8	0000000000000000	"IMR7 Write Access Policy (B_CR_BIMR7WAC_0_0_0_MCHBAR)—Offset 6968h" on page 1217
6970	4	00000000	"IMR8 Base (B_CR_BIMR8BASE_0_0_0_MCHBAR)—Offset 6970h" on page 1220
6974	4	00000000	"IMR8 Mask (B_CR_BIMR8MASK_0_0_0_MCHBAR)—Offset 6974h" on page 1221
6978	8	00000C0061010202	"IMR8 Control Policy (B_CR_BIMR8CP_0_0_0_MCHBAR)—Offset 6978h" on page 1221
6980	8	0000000000000000	"IMR8 Read Access Policy (B_CR_BIMR8RAC_0_0_0_MCHBAR)—Offset 6980h" on page 1222
6988	8	0000000000000000	"IMR8 Write Access Policy (B_CR_BIMR8WAC_0_0_0_MCHBAR)—Offset 6988h" on page 1225
6990	4	00000000	"IMR9 Base (B_CR_BIMR9BASE_0_0_0_MCHBAR)—Offset 6990h" on page 1228
6994	4	00000000	"IMR9 Mask (B_CR_BIMR9MASK_0_0_0_MCHBAR)—Offset 6994h" on page 1229

Table 44-4. Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR (Sheet 3 of 6)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
6998	8	00000C0061010202	"IMR9 Control Policy (B_CR_BIMR9CP_0_0_0_MCHBAR)—Offset 6998h" on page 1229
69A0	8	0000000000000000	"IMR9 Read Access Policy (B_CR_BIMR9RAC_0_0_0_MCHBAR)—Offset 69A0h" on page 1230
69A8	8	0000000000000000	"IMR9 Write Access Policy (B_CR_BIMR9WAC_0_0_0_MCHBAR)—Offset 69A8h" on page 1233
69B0	4	00000000	"IMR10 Base (B_CR_BIMR10BASE_0_0_0_MCHBAR)—Offset 69B0h" on page 1236
69B4	4	00000000	"B_CR_BIMR10MASK_0_0_0_MCHBAR—Offset 69B4h" on page 1237
69B8	8	00000C0061010202	"IMR10 Control Policy (B_CR_BIMR10CP_0_0_0_MCHBAR)—Offset 69B8h" on page 1237
69C0	8	0000000000000000	"IMR10 Read Access Policy (B_CR_BIMR10RAC_0_0_0_MCHBAR)—Offset 69C0h" on page 1238
69C8	8	0000000000000000	"IMR10 Write Access Policy (B_CR_BIMR10WAC_0_0_0_MCHBAR)—Offset 69C8h" on page 1241
69D0	4	00000000	"IMR11 Base (B_CR_BIMR11BASE_0_0_0_MCHBAR)—Offset 69D0h" on page 1244
69D4	4	00000000	"IMR11 Mask (B_CR_BIMR11MASK_0_0_0_MCHBAR)—Offset 69D4h" on page 1245
69D8	8	00000C0061010202	"IMR11 Control Policy (B_CR_BIMR11CP_0_0_0_MCHBAR)—Offset 69D8h" on page 1245
69E0	8	0000000000000000	"IMR11 Read Access Policy (B_CR_BIMR11RAC_0_0_0_MCHBAR)—Offset 69E0h" on page 1246
69E8	8	0000000000000000	"IMR11 Write Access Policy (B_CR_BIMR11WAC_0_0_0_MCHBAR)—Offset 69E8h" on page 1249
69F0	4	00000000	"IMR12 Base (B_CR_BIMR12BASE_0_0_0_MCHBAR)—Offset 69F0h" on page 1252
69F4	4	00000000	"IMR12 Mask (B_CR_BIMR12MASK_0_0_0_MCHBAR)—Offset 69F4h" on page 1253
69F8	8	00000C0061010202	"IMR12 Control Policy (B_CR_BIMR12CP_0_0_0_MCHBAR)—Offset 69F8h" on page 1253
6A00	8	0000000000000000	"IMR12 Read Access Policy (B_CR_BIMR12RAC_0_0_0_MCHBAR)—Offset 6A00h" on page 1254
6A08	8	0000000000000000	"IMR12 Write Access Policy (B_CR_BIMR12WAC_0_0_0_MCHBAR)—Offset 6A08h" on page 1257
6A10	4	00000000	"IMR13 Base (B_CR_BIMR13BASE_0_0_0_MCHBAR)—Offset 6A10h" on page 1260
6A14	4	00000000	"IMR13 Mask (B_CR_BIMR13MASK_0_0_0_MCHBAR)—Offset 6A14h" on page 1261
6A18	8	00000C0061010202	"IMR13 Control Policy (B_CR_BIMR13CP_0_0_0_MCHBAR)—Offset 6A18h" on page 1261
6A20	8	0000000000000000	"IMR13 Read Access Policy (B_CR_BIMR13RAC_0_0_0_MCHBAR)—Offset 6A20h" on page 1262
6A28	8	0000000000000000	"IMR13 Write Access Policy (B_CR_BIMR13WAC_0_0_0_MCHBAR)—Offset 6A28h" on page 1265
6A30	4	00000000	"IMR14 Base (B_CR_BIMR14BASE_0_0_0_MCHBAR)—Offset 6A30h" on page 1268
6A34	4	00000000	"IMR14 Mask (B_CR_BIMR14MASK_0_0_0_MCHBAR)—Offset 6A34h" on page 1269
6A38	8	00000C0061010202	"IMR14 Control Policy (B_CR_BIMR14CP_0_0_0_MCHBAR)—Offset 6A38h" on page 1269

Table 44-4. Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR (Sheet 4 of 6)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
6A40	8	0000000000000000	"IMR14 Read Access Policy (B_CR_BIMR14RAC_0_0_0_MCHBAR)—Offset 6A40h" on page 1270
6A48	8	0000000000000000	"IMR14 Write Access Policy (B_CR_BIMR14WAC_0_0_0_MCHBAR)—Offset 6A48h" on page 1273
6A50	4	00000000	"IMR15 Base (B_CR_BIMR15BASE_0_0_0_MCHBAR)—Offset 6A50h" on page 1276
6A54	4	00000000	"IMR15 Mask (B_CR_BIMR15MASK_0_0_0_MCHBAR)—Offset 6A54h" on page 1277
6A58	8	00000C0061010202	"IMR15 Control Policy (B_CR_BIMR15CP_0_0_0_MCHBAR)—Offset 6A58h" on page 1277
6A60	8	0000000000000000	"IMR15 Read Access Policy (B_CR_BIMR15RAC_0_0_0_MCHBAR)—Offset 6A60h" on page 1278
6A68	8	0000000000000000	"IMR15 Write Access Policy (B_CR_BIMR15WAC_0_0_0_MCHBAR)—Offset 6A68h" on page 1281
6A70	4	00000000	"IMR16 Base (B_CR_BIMR16BASE_0_0_0_MCHBAR)—Offset 6A70h" on page 1284
6A74	4	00000000	"IMR16 Mask (B_CR_BIMR16MASK_0_0_0_MCHBAR)—Offset 6A74h" on page 1285
6A78	8	00000C0061010202	"IMR16 Control Policy (B_CR_BIMR16CP_0_0_0_MCHBAR)—Offset 6A78h" on page 1285
6A80	8	0000000000000000	"IMR16 Read Access Policy (B_CR_BIMR16RAC_0_0_0_MCHBAR)—Offset 6A80h" on page 1286
6A88	8	0000000000000000	"IMR16 Write Access Policy (B_CR_BIMR16WAC_0_0_0_MCHBAR)—Offset 6A88h" on page 1289
6A90	4	00000000	"IMR17 Base (B_CR_BIMR17BASE_0_0_0_MCHBAR)—Offset 6A90h" on page 1292
6A94	4	00000000	"IMR17 Mask (B_CR_BIMR17MASK_0_0_0_MCHBAR)—Offset 6A94h" on page 1293
6A98	8	00000C0061010202	"IMR17 Control Policy (B_CR_BIMR17CP_0_0_0_MCHBAR)—Offset 6A98h" on page 1293
6AA0	8	0000000000000000	"IMR17 Read Access Policy (B_CR_BIMR17RAC_0_0_0_MCHBAR)—Offset 6AA0h" on page 1294
6AA8	8	0000000000000000	"IMR17 Write Access Policy (B_CR_BIMR17WAC_0_0_0_MCHBAR)—Offset 6AA8h" on page 1297
6AB0	4	00000000	"IMR18 Base (B_CR_BIMR18BASE_0_0_0_MCHBAR)—Offset 6AB0h" on page 1300
6AB4	4	00000000	"IMR18 Mask (B_CR_BIMR18MASK_0_0_0_MCHBAR)—Offset 6AB4h" on page 1301
6AB8	8	00000C0061010202	"IMR18 Control Policy (B_CR_BIMR18CP_0_0_0_MCHBAR)—Offset 6AB8h" on page 1301
6AC0	8	0000000000000000	"IMR18 Read Access Policy (B_CR_BIMR18RAC_0_0_0_MCHBAR)—Offset 6AC0h" on page 1302
6AC8	8	0000000000000000	"IMR18 Write Access Policy (B_CR_BIMR18WAC_0_0_0_MCHBAR)—Offset 6AC8h" on page 1305
6AD0	4	00000000	"IMR19 Base (B_CR_BIMR19BASE_0_0_0_MCHBAR)—Offset 6AD0h" on page 1308
6AD4	4	00000000	"IMR19 Mask (B_CR_BIMR19MASK_0_0_0_MCHBAR)—Offset 6AD4h" on page 1309
6AD8	8	00000C0061010202	"IMR19 Control Policy (B_CR_BIMR19CP_0_0_0_MCHBAR)—Offset 6AD8h" on page 1309

Table 44-4. Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR (Sheet 5 of 6)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
6AE0	8	0000000000000000	"IMR19 Read Access Policy (B_CR_BIMR19RAC_0_0_0_MCHBAR)—Offset 6AE0h" on page 1310
6AE8	8	0000000000000000	"IMR19 Write Access Policy (B_CR_BIMR19WAC_0_0_0_MCHBAR)—Offset 6AE8h" on page 1313
6C24	4	00000000	"TPM Selector (B_CR_TPM_SELECTOR_0_0_0_MCHBAR)—Offset 6C24h" on page 1316
6C80	8	0000000000000000	"Default VTd BAR (B_CR_DEFVTDBAR_0_0_0_MCHBAR)—Offset 6C80h" on page 1316
6D4C	4	04040404	"B-Unit Arbiter Control BARBCTRL0 (B_CR_BARBCTRL0)—Offset 6D4Ch" on page 1317
6D50	4	04040404	"B-Unit Arbiter Control BARBCTRL1 (B_CR_BARBCTRL1)—Offset 6D50h" on page 1318
6D54	4	04040404	"B-Unit Scheduler Control (B_CR_BSCHWT0)—Offset 6D54h" on page 1319
6D58	4	04040404	"B-Unit Scheduler Control (B_CR_BSCHWT1)—Offset 6D58h" on page 1320
6D5C	4	04040404	"B-Unit Scheduler Control (B_CR_BSCHWT2)—Offset 6D5Ch" on page 1321
6D60	4	04040404	"B-Unit Scheduler Control (B_CR_BSCHWT3)—Offset 6D60h" on page 1322
6D64	4	FF010000	"B-Unit Flush Control (B_CR_BWFLUSH)—Offset 6D64h" on page 1323
6D68	4	00000404	"B-Unit Flush Weights (B_CR_BFLWT)—Offset 6D68h" on page 1323
6D6C	4	80003F0F	"Weighted Scheduling Control of High Priority ISOC and Other Requests (B_CR_BISOCWT)—Offset 6D6Ch" on page 1324
6D70	4	000F0014	"B-Unit Control (B_CR_BCTRL2)—Offset 6D70h" on page 1325
6E04	4	00000000	"Uncorrectable Error Status Register (B_CR_UNCERRSTS_0_0_0_MCHBAR)—Offset 6E04h" on page 1326
6E08	4	FFFFFFFF	"Uncorrectable Error Mask Register (B_CR_UNCERRMSK_0_0_0_MCHBAR)—Offset 6E08h" on page 1329
6E0C	4	00000000	"Uncorrectable Error Severity Register (B_CR_UNCERRSEV_0_0_0_MCHBAR)—Offset 6E0Ch" on page 1331
6E10	4	00000000	"First Uncorrectable Error Register (B_CR_UNCFERRSTS_0_0_0_MCHBAR)—Offset 6E10h" on page 1333
6E14	4	00000000	"Next Uncorrectable Error Register (B_CR_UNCNERRSTS_0_0_0_MCHBAR)—Offset 6E14h" on page 1336
6E18	4	00000000	"Uncorrectable Error Select Register (B_CR_UNCERRCNTSEL_0_0_0_MCHBAR)—Offset 6E18h" on page 1339
6E1C	4	00000000	"Uncorrectable Error Count (B_CR_UNCERRCNT_0_0_0_MCHBAR)—Offset 6E1Ch" on page 1341
6E20	4	00000000	"Correctable Error Status Register (B_CR_CORERRSTS_0_0_0_MCHBAR)—Offset 6E20h" on page 1342
6E24	4	FFFFFFFF	"Correctable Error Mask Register (B_CR_CORERRMSK_0_0_0_MCHBAR)—Offset 6E24h" on page 1345
6E28	4	00000000	"Data Parity Header Log Low (B_CR_DPHDRLOG_LO_0_0_0_MCHBAR)—Offset 6E28h" on page 1347
6E2C	4	00000000	"Data Parity Header Log High (B_CR_DPHDRLOG_HI_0_0_0_MCHBAR)—Offset 6E2Ch" on page 1347
6E30	4	00000000	"Data Parity Address Log Low (B_CR_DPADDRLOG_LO_0_0_0_MCHBAR)—Offset 6E30h" on page 1347
6E34	4	00000000	"Data Parity Address Log High (B_CR_DPADDRLOG_HI_0_0_0_MCHBAR)—Offset 6E34h" on page 1348
6E38	4	00000000	"D-Unit Error Address Log (B_CR_DERRADDRLOG_LO_0_0_0_MCHBAR)—Offset 6E38h" on page 1348

Table 44-4. Summary of Memory Mapped I/O Registers for B-Unit—MCHBAR (Sheet 6 of 6)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
6E3C	4	00000000	"D-Unit Error Address Log (B_CR_DERRADDRLOG_HI_0_0_0_MCHBAR)—Offset 6E3Ch" on page 1348
6E40	4	00000000	"Asymmetric Memory Region 0 (B_CR_ASYM_MEM_REGION0_0_0_0_MCHBAR)—Offset 6E40h" on page 1349
6E44	4	00000000	"Asymmetric Memory Region 1 (B_CR_ASYM_MEM_REGION1_0_0_0_MCHBAR)—Offset 6E44h" on page 1349
6E48	4	00000001	"B-Unit Machine Check Mode Low (B_CR_BMCMODE_LOW)—Offset 6E48h" on page 1350
6E4C	4	00000000	"B-Unit Machine Check Mode High (B_CR_BMCMODE_HIGH)—Offset 6E4Ch" on page 1350

Table 44-5. Summary of Memory Mapped I/O Registers for P-Unit—MCHBAR (Sheet 1 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
7014	4	00000000	"PWR_LIMIT_MISC_0_0_0_MCHBAR (P_CR_PWR_LIMIT_MISC_0_0_0_MCHBAR)—Offset 7014h" on page 1351
7018	4	00000000	"CAPABILITY_ID_0_0_0_MCHBAR (P_CR_CAPABILITY_ID_0_0_0_MCHBAR)—Offset 7018h" on page 1351
7020	4	00000000	"MC_BIOS_REQ_0_0_0_MCH (P_CR_MC_BIOS_REQ_0_0_0_MCHBAR)—Offset 7020h" on page 1352
702C	4	00000000	"MCA_ERROR_SRC_0_0_0_MCHBAR (P_CR_MCA_ERROR_SRC_0_0_0_MCHBAR)—Offset 702Ch" on page 1353
7030	4	00010000	"DDR_THERM_THRT_CTRL_0_0_0_MCHBAR (P_CR_DDR_THERM_THRT_CTRL_0_0_0_MCHBAR)—Offset 7030h" on page 1354
703C	4	00000000	"PACKAGE_THERM_MARGIN (P_CR_PACKAGE_THERM_MARGIN_0_0_0_MCHBAR)—Offset 703Ch" on page 1355
7040	8	0000000000000000	"DDR_RAPL_LIMIT (P_CR_DDR_RAPL_LIMIT_0_0_0_MCHBAR)—Offset 7040h" on page 1356
7048	4	00000000	"DDR_ENERGY_STATUS (P_CR_DDR_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 7048h" on page 1357
704C	4	000058F0	"DDR_RAPL_PERF_STATUS (P_CR_DDR_RAPL_PERF_STATUS_0_0_0_MCHBAR)—Offset 704Ch" on page 1357
7050	4	00000000	"PACKAGE_RAPL_PERF_STATUS (P_CR_PACKAGE_RAPL_PERF_STATUS_0_0_0_MCHBAR)—Offset 7050h" on page 1358
7054	4	00000000	"PRIMARY_PLANE_TURBO_POWER_POLICY (P_CR_PRIMARY_PLANE_TURBO_PLCY_0_0_0_MCHBAR)—Offset 7054h" on page 1358
7058	4	00000010	"SECONDARY_PLANE_TURBO_POWER_POLICY (P_CR_SECONDARY_PLANE_TURBO_PLCY_0_0_0_MCHBAR)—Offset 7058h" on page 1359
705C	4	00000000	"PRIMARY_PLANE_ENERGY_STATUS (P_CR_PRIMARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 705Ch" on page 1359
7060	4	00000000	"SECONDARY_PLANE_ENERGY_STATUS (P_CR_SECONDARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 7060h" on page 1360
7068	4	330A0E08	"PACKAGE_POWER_SKU_UNIT (P_CR_PACKAGE_POWER_SKU_UNIT_0_0_0_MCHBAR)—Offset 7068h" on page 1361
706C	4	00000000	"PACKAGE_ENERGY_STATUS (P_CR_PACKAGE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 706Ch" on page 1362
7070	4	00000000	"GT_PERF_STATUS (P_CR_GT_PERF_STATUS_0_0_0_MCHBAR)—Offset 7070h" on page 1362
7074	4	005A0000	"TEMPERATURE_TARGET (P_CR_TEMPERATURE_TARGET_0_0_0_MCHBAR)—Offset 7074h" on page 1363
7078	4	00000000	"BIOS_RESET_CPL (P_CR_BIOS_RESET_CPL_0_0_0_MCHBAR)—Offset 7078h" on page 1364
7080	4	00000000	"BIOS_MAILBOX_DATA (P_CR_BIOS_MAILBOX_DATA_0_0_0_MCHBAR)—Offset 7080h" on page 1366
7084	4	00000000	"BIOS_MAILBOX_INTERFACE (P_CR_BIOS_MAILBOX_INTERFACE_0_0_0_MCHBAR)—Offset 7084h" on page 1366

Table 44-5. Summary of Memory Mapped I/O Registers for P-Unit—MCHBAR (Sheet 2 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
7088	4	00000000	"CORE_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_CORE_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7088h" on page 1367
708C	4	00000000	"GRAPHICS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_GRAPHICS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 708Ch" on page 1368
7090	4	00000000	"SYSTEM_AGENT_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_SYSTEM_AGENT_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7090h" on page 1369
7094	4	00000000	"FAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_FAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7094h" on page 1369
7098	4	00000000	"NEAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_NEAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7098h" on page 1370
70A0	8	0012024000600118	"PACKAGE_POWER_SKU (P_CR_PACKAGE_POWER_SKU_0_0_0_MCHBAR)—Offset 70A0h" on page 1371
70A8	8	0000000000000000	"PACKAGE_RAPL_LIMIT (P_CR_PACKAGE_RAPL_LIMIT_0_0_0_MCHBAR)—Offset 70A8h" on page 1372
70B0	4	00000000	"IA_PERF_LIMIT_REASONS (P_CR_IA_PERF_LIMIT_REASONS_0_0_0_MCHBAR)—Offset 70B0h" on page 1374
70D8	4	00000000	"MEMHOT_THERM_STATUS_0_0_0_MCHBAR (P_CR_MEMHOT_THERM_STATUS_0_0_0_MCHBAR)—Offset 70D8h" on page 1376
70DC	4	00000000	"MEMHOT_THERM_CONFIG_0_0_0_MCHBAR (P_CR_MEMHOT_THERM_CONFIG_0_0_0_MCHBAR)—Offset 70DCh" on page 1376
7200	4	00000000	"MEM_THERM_CTRL_0_0_0_MCHBAR (P_CR_MEM_THERM_CTRL_0_0_0_MCHBAR)—Offset 7200h" on page 1377
7204	4	00645D54	"MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR (P_CR_MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR)—Offset 7204h" on page 1378
7208	4	00635A00	"MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR (P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR)—Offset 7208h" on page 1378
720C	4	00000000	"MEM_THERM_STATUS_0_0_0_MCHBAR (P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR)—Offset 720Ch" on page 1379
7210	4	00000000	"MEM_THERM_INTERRUPT_0_0_0_MCHBAR (P_CR_MEM_THERM_INTERRUPT_0_0_0_MCHBAR)—Offset 7210h" on page 1380
7214	4	00000000	"MEM_THERM_INT_STATUS_0_0_0_MCHBAR (P_CR_MEM_THERM_INT_STATUS_0_0_0_MCHBAR)—Offset 7214h" on page 1381
7218	4	00000000	"MEM_THERM_TEMP_OFST_0_0_0_MCHBAR (P_CR_MEM_THERM_TEMP_OFST_0_0_0_MCHBAR)—Offset 7218h" on page 1383
70E0	8	0000000000000000	"TELEM_NEAR_MEMORY_ACTIVE_ACCUMULATOR (P_CR_TELEM_NEAR_MEMORY_ACTIVE_0_0_0_MCHBAR)—Offset 70E0h" on page 1384
70E8	8	0000000000000000	"TELEM_FAR_MEMORY_ACTIVE_ACCUMULATOR (P_CR_TELEM_FAR_MEMORY_ACTIVE_0_0_0_MCHBAR)—Offset 70E8h" on page 1384

Table 44-5. Summary of Memory Mapped I/O Registers for P-Unit—MCHBAR (Sheet 3 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
70F0	4	00000000	"TURBO_ACTIVATION_RATIO (P_CR_TURBO_ACTIVATION_RATIO_0_0_0_MCHBAR)—Offset 70F0h" on page 1385
7034	4	00000032	"C2C3TT_CFG (P_CR_C2C3TT_CFG_0_0_0_MCHBAR)—Offset 7034h" on page 1385
7110	4	00000000	"DTS_CONFIG1_CFG (P_CR_DTS_CONFIG1_CFG_0_0_0_MCHBAR)—Offset 7110h" on page 1386
7114	4	00000000	"DTS_CONFIG2_CFG (P_CR_DTS_CONFIG2_CFG_0_0_0_MCHBAR)—Offset 7114h" on page 1386
7118	4	00000000	"DTS_CONFIG3_CFG (P_CR_DTS_CONFIG3_CFG_0_0_0_MCHBAR)—Offset 7118h" on page 1387
711C	4	00000000	"SOUTH_IO_PORT_STATUS3 (P_CR_SOUTH_IO_PORT_STATUS3_0_0_0_MCHBAR)—Offset 711Ch" on page 1387
7128	4	00000000	"DRAM_BIOS_INFO (P_CR_DRAM_BIOS_INFO_0_0_0_MCHBAR)—Offset 7128h" on page 1388
712C	4	00000000	"ADR_COMMAND (P_CR_ADR_COMMAND_0_0_0_MCHBAR)—Offset 712Ch" on page 1389
7130	8	0028000000000118	"DRAM_POWER_INFO (P_CR_DRAM_POWER_INFO_0_0_0_MCHBAR)—Offset 7130h" on page 1390
7138	4	00000000	"PCODE_WRITE_SPARE (P_CR_PCODE_WRITE_SPARE_0_0_0_MCHBAR)—Offset 7138h" on page 1390
70F4	4	00000000	"PACKAGE_TEMPERATURES_0_0_0_MCHBAR (P_CR_PACKAGE_TEMPERATURES_0_0_0_MCHBAR)—Offset 70F4h" on page 1391
7108	4	00000000	"MEMSS_FREQUENCY_CAPABILITIES (P_CR_MEMSS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7108h" on page 1392
7160	4	00000000	"PP1_C0_CORE_CLOCK_0_0_0_MCHBAR (P_CR_PP1_C0_CORE_CLOCK_0_0_0_MCHBAR)—Offset 7160h" on page 1392
7164	4	00000000	"Core Exists Vector (P_CR_CORE_EXISTS_VECTOR_0_0_0_MCHBAR)—Offset 7164h" on page 1393
7168	4	00000000	"Software Core Disable Mask (P_CR_CORE_DISABLE_MASK_0_0_0_MCHBAR)—Offset 7168h" on page 1394
71F0	8	0000000000000000	"PL3_CONTROL_MCHBAR (P_CR_PL3_CONTROL_0_0_0_MCHBAR)—Offset 71F0h" on page 1396
7220	8	0000000000000000	"CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL1_0_0_0_MCHBAR)—Offset 7220h" on page 1398
7228	8	0000000000000000	"CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL2_0_0_0_MCHBAR)—Offset 7228h" on page 1399
7230	8	0000000000000000	"CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL3_0_0_0_MCHBAR)—Offset 7230h" on page 1400
7238	4	00000000	"CONFIG_TDP_CONTROL (P_CR_CONFIG_TDP_CONTROL_0_0_0_MCHBAR)—Offset 7238h" on page 1400
723C	4	00000000	"CONFIG_TDP_NOMINAL (P_CR_CONFIG_TDP_NOMINAL_0_0_0_MCHBAR)—Offset 723Ch" on page 1401
7244	4	00000000	"Graphics Superqueue Active Clocks (P_CR_PP1_ANY_THREAD_ACTIVITY_0_0_0_MCHBAR)—Offset 7244h" on page 1402

44.1.3 Host Memory Space—DEFVTDBAR

Table 44-6. Summary of Memory Mapped I/O Registers—DEFVTDBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
64	4	00000000	"B-Unit Copy of Default VTd BAR PMEN (B_CR_PMEN_REG_0_0_0_DEFVTDBAR)—Offset 64h" on page 1402
68	4	00000000	"B-Unit Copy of Default VTd BAR PLM Base Register (B_CR_PLMBASE_REG_0_0_0_DEFVTDBAR)—Offset 68h" on page 1403
6C	4	00000000	"B-Unit Copy of Default VTd BAR PLM Limit Register (B_CR_PLMLIMIT_REG_0_0_0_DEFVTDBAR)—Offset 6Ch" on page 1404
70	8	0000000000000000	"B-Unit Copy of Default VTd BAR PHM Base Register (B_CR_PHMBASE_REG_0_0_0_DEFVTDBAR)—Offset 70h" on page 1405
78	8	0000000000000000	"B-Unit Copy of Default VTd BAR PHM Limit Register (B_CR_PHMLIMIT_REG_0_0_0_DEFVTDBAR)—Offset 78h" on page 1406

44.1.4 Host Memory Space—DEFVTDBAR

Table 44-7. Summary of Memory Mapped I/O Registers—DEFVTDBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000010	"Version Register (VER_REG_0_0_0_VTDBAR)—Offset 0h" on page 1407
8	8	00D2008C40660462	"Capability Register (CAP_REG_0_0_0_VTDBAR)—Offset 8h" on page 1407
10	8	0000000000F050DA	"Extended Capability Register (ECAP_REG_0_0_0_VTDBAR)—Offset 10h" on page 1409
18	4	00000000	"Global Command Register (GCMD_REG_0_0_0_VTDBAR)—Offset 18h" on page 1412
1C	4	00000000	"Global Status Register (GSTS_REG_0_0_0_VTDBAR)—Offset 1Ch" on page 1413
20	8	0000000000000000	"Root Table Address Register (RTADDR_REG_0_0_0_VTDBAR)—Offset 20h" on page 1414
28	8	0800000000000000	"Context Command Register (CCMD_REG_0_0_0_VTDBAR)—Offset 28h" on page 1415
34	4	00000000	"Fault Status Register (FSTS_REG_0_0_0_VTDBAR)—Offset 34h" on page 1417
38	4	80000000	"Fault Event Control Register (FECTL_REG_0_0_0_VTDBAR)—Offset 38h" on page 1419
3C	4	00000000	"Fault Event Data Register (FEDATA_REG_0_0_0_VTDBAR)—Offset 3Ch" on page 1420
40	4	00000000	"Fault Event Address Register (FEADDR_REG_0_0_0_VTDBAR)—Offset 40h" on page 1420
44	4	00000000	"Fault Event Upper Address Register (FEUADDR_REG_0_0_0_VTDBAR)—Offset 44h" on page 1420
58	8	0000000000000000	"Advanced Fault Log Register (AFLOG_REG_0_0_0_VTDBAR)—Offset 58h" on page 1421
64	4	00000000	"Protected Memory Enable Register (PMEN_REG_0_0_0_VTDBAR)—Offset 64h" on page 1422
68	4	00000000	"Protected Low Memory Base Register (PLMBASE_REG_0_0_0_VTDBAR)—Offset 68h" on page 1423
6C	4	00000000	"Protected Low-Memory Limit Register (PLMLIMIT_REG_0_0_0_VTDBAR)—Offset 6Ch" on page 1424
70	8	0000000000000000	"Protected High-Memory Base Register (PHMBASE_REG_0_0_0_VTDBAR)—Offset 70h" on page 1425
78	8	0000000000000000	"Protected High-Memory Limit Register (PHMLIMIT_REG_0_0_0_VTDBAR)—Offset 78h" on page 1426
80	8	0000000000000000	"Invalidation Queue Head Register (IQH_REG_0_0_0_VTDBAR)—Offset 80h" on page 1427
88	8	0000000000000000	"Invalidation Queue Tail Register (IQT_REG_0_0_0_VTDBAR)—Offset 88h" on page 1427
90	8	0000000000000000	"Invalidation Queue Address Register (IQA_REG_0_0_0_VTDBAR)—Offset 90h" on page 1428
9C	4	00000000	"Invalidation Completion Status Register (ICS_REG_0_0_0_VTDBAR)—Offset 9Ch" on page 1428
A0	4	80000000	"Invalidation Event Control Register (IECTL_REG_0_0_0_VTDBAR)—Offset A0h" on page 1429
A4	4	00000000	"Invalidation Event Data Register (IEDATA_REG_0_0_0_VTDBAR)—Offset A4h" on page 1430
A8	4	00000000	"Invalidation Event Address Register (IEADDR_REG_0_0_0_VTDBAR)—Offset A8h" on page 1430

Table 44-7. Summary of Memory Mapped I/O Registers—DEFVTDBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
AC	4	00000000	"Invalidation Event Upper Address Register (IEUADDR_REG_0_0_0_VTDBAR)—Offset ACh" on page 1431
B8	8	0000000000000000	"Interrupt Remapping Table Address Register (IRTA_REG_0_0_0_VTDBAR)—Offset B8h" on page 1431
DC	4	00000000	"Page Request Status Register (PRESTS_REG_0_0_0_VTDBAR)—Offset DCh" on page 1432
E0	4	80000000	"Page Request Event Control Register (PRECTL_REG_0_0_0_VTDBAR)—Offset E0h" on page 1433
E4	4	00000000	"Page Request Event Data Register (PREDATA_REG_0_0_0_VTDBAR)—Offset E4h" on page 1434
E8	4	00000000	"Page Request Event Address Register (PREADDR_REG_0_0_0_VTDBAR)—Offset E8h" on page 1434
EC	4	00000000	"Page Request Event Upper Address Register (PREUADDR_REG_0_0_0_VTDBAR)—Offset ECh" on page 1434
400	8	0000000000000000	"Fault Recording Register Low [0] (FRCDL_REG_0_0_0_VTDBAR)—Offset 400h" on page 1435
408	8	0000000000000000	"Fault Recording Register High [0] (FRCDH_REG_0_0_0_VTDBAR)—Offset 408h" on page 1436
500	8	0000000000000000	"Invalidate Address Register (IVA_REG_0_0_0_VTDBAR)—Offset 500h" on page 1438
508	8	0200000000000000	"IOTLB Invalidate Register (IOTLB_REG_0_0_0_VTDBAR)—Offset 508h" on page 1439

44.1.5 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (BAR) DEFVTDBAR. It is located in Host Root Memory Space MCHBAR +offset 6C80h.

See Section 44.3.123, "Default VTd BAR (B_CR_DEFVTDBAR_0_0_0_MCHBAR)—Offset 6C80h" on page 1316. Also see Section 3.4.2, "Accessing System Agent Sideband Registers" on page 187.

The Sideband registers for Memory Controller 0 are shown in Table 44-8. For Memory Controller 1 see Table 44-9.

Table 44-8. Summary of Sideband Registers—0x10 (Memory Controller 0)

Offset from Sideband Port 10h (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
64	10_0064	00000800	"UCELOG—Offset 64h" on page 1441
68	10_0068	00000000	"UCEADDR—Offset 68h" on page 1442
6C	10_006C	00000800	"SBELOG—Offset 6Ch" on page 1442
70	10_0070	00000000	"SBEADDR—Offset 70h" on page 1443
74	10_0074	00000000	"SBECNT0—Offset 74h" on page 1444
78	10_0078	00000000	"SBECNT1—Offset 78h" on page 1444
7C	10_007C	00000000	"SBECNT2—Offset 7Ch" on page 1445
80	10_0080	00000000	"SBECNT3—Offset 80h" on page 1445
84	10_0084	00000000	"SBEACC0—Offset 84h" on page 1445
88	10_0088	00000000	"SBEACC1—Offset 88h" on page 1446
8C	10_008C	00000000	"SBEACC2—Offset 8Ch" on page 1446
90	10_0090	00000000	"SBEACC3—Offset 90h" on page 1446
B0	10_00B0	00000000	"DPATROL_SCRUB_CFG—Offset B0h" on page 1447
CC	10_00CC	00000000	"UCELOG1—Offset CCh" on page 1447
D0	10_00D0	00000000	"SBELOG1—Offset D0h" on page 1448
100	10_0100	00000000	"CORRERRTHRSHLD0—Offset 100h" on page 1448
104	10_0104	00000000	"CORRERRTHRSHLD1—Offset 104h" on page 1448
108	10_0108	00000000	"CORRERRTHRSHLD2—Offset 108h" on page 1449
10C	10_010C	00000000	"CORRERRTHRSHLD3—Offset 10Ch" on page 1449
110	10_0110	00000000	"LEAKY_BUCKET_CFG0—Offset 110h" on page 1449
114	10_0114	00000000	"LEAKY_BUCKET_CFG1—Offset 114h" on page 1450
118	10_0118	00000000	"LEAKY_BUCKET_CFG2—Offset 118h" on page 1450
11C	10_011C	00000000	"LEAKY_BUCKET_CFG3—Offset 11Ch" on page 1450
120	10_0120	00000000	"FERRNERR—Offset 120h" on page 1451
124	10_0124	00000000	"DERRSTS—Offset 124h" on page 1452
128	10_0128	00000000	"DERRMSKSEV—Offset 128h" on page 1453
12C	10_012C	00000000	"DERRCNTSEL—Offset 12Ch" on page 1454
130	10_0130	00000000	"DERRCNTSEL—Offset 12Ch" on page 1454
134	10_0134	00000000	"ERRINJCTL—Offset 134h" on page 1455

Table 44-8. Summary of Sideband Registers—0x10 (Continued) (Memory Controller 0)

Offset from Sideband Port 10h (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
138	10_0138	00000000	"ERRINJADDR—Offset 138h" on page 1456
13C	10_013C	00000000	"ERRINJAMSK—Offset 13Ch" on page 1456
140	10_0140	00000000	"ERRINJDATA0—Offset 140h" on page 1456
144	10_0144	00000000	"ERRINJDATA1—Offset 144h" on page 1456
170	10_0170	00000000	"DCS—Offset 170h" on page 1457
180	10_0180	00000000	"DECCCTRL—Offset 180h" on page 1458
18C	10_018C	00000000	"LEAKY_BUCKET_CNTR_UPPER—Offset 18Ch" on page 1459
194	10_0194	FFFFFFFF	"DPATROL_SCRUB_TMR—Offset 194h" on page 1459

Table 44-9. Summary of Sideband Registers—0x12 (Memory Controller 1)

Offset from Sideband Port 12h (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
64	12_0064	00000800	"UCELOG—Offset 64h" on page 1460
68	12_0068	00000000	"UCEADDR—Offset 68h" on page 1460
6C	12_006C	00000800	"SBELOG—Offset 6Ch" on page 1461
70	12_0070	00000000	"SBEADDR—Offset 70h" on page 1461
74	12_0074	00000000	"SBECNT0—Offset 74h" on page 1462
78	12_0078	00000000	"SBECNT1—Offset 78h" on page 1462
7C	12_007C	00000000	"SBECNT2—Offset 7Ch" on page 1463
80	12_0080	00000000	"SBECNT3—Offset 80h" on page 1463
84	12_0084	00000000	"SBEACC0—Offset 84h" on page 1464
88	12_0088	00000000	"SBEACC1—Offset 88h" on page 1464
8C	12_008C	00000000	"SBEACC2—Offset 8Ch" on page 1465
90	12_0090	00000000	"SBEACC3—Offset 90h" on page 1465
B0	12_00B0	00000000	"DPATROL_SCRUB_CFG—Offset B0h" on page 1466
CC	12_00CC	00000000	"UCELOG1—Offset CCh" on page 1466
D0	12_00D0	00000000	"SBELOG1—Offset D0h" on page 1467
100	12_0100	00000000	"CORRERRTHRSHLD0—Offset 100h" on page 1467
104	12_0104	00000000	"CORRERRTHRSHLD1—Offset 104h" on page 1467
108	12_0108	00000000	"CORRERRTHRSHLD2—Offset 108h" on page 1468
10C	12_010C	00000000	"CORRERRTHRSHLD3—Offset 10Ch" on page 1468
110	12_0110	00000000	"LEAKY_BUCKET_CFG0—Offset 110h" on page 1468
114	12_0114	00000000	"LEAKY_BUCKET_CFG1—Offset 114h" on page 1469
118	12_0118	00000000	"LEAKY_BUCKET_CFG2—Offset 118h" on page 1469
11C	12_011C	00000000	"LEAKY_BUCKET_CFG3—Offset 11Ch" on page 1469
120	12_0120	00000000	"FERRNERR—Offset 120h" on page 1470
124	12_0124	00000000	"DERRSTS—Offset 124h" on page 1471
128	12_0128	00000000	"DERRMSKSEV—Offset 128h" on page 1472
12C	12_012C	00000000	"DERRCNTSEL—Offset 12Ch" on page 1473
130	12_0130	00000000	"DERRCNT—Offset 130h" on page 1473
134	12_0134	00000000	"ERRINJCTL—Offset 134h" on page 1474
138	12_0138	00000000	"ERRINJADDR—Offset 138h" on page 1475
13C	12_013C	00000000	"ERRINJAMSK—Offset 13Ch" on page 1475
140	12_0140	00000000	"ERRINJDATA0—Offset 140h" on page 1475
144	12_0144	00000000	"ERRINJDATA1—Offset 144h" on page 1475
170	12_0170	00000000	"DCS—Offset 170h" on page 1476
180	12_0180	00000000	"DECCCTRL—Offset 180h" on page 1478
18C	12_018C	00000000	"LEAKY_BUCKET_CNTR_UPPER—Offset 18Ch" on page 1479
194	12_0194	FFFFFFFF	"DPATROL_SCRUB_TMR—Offset 194h" on page 1479

Table 44-10. Summary of Sideband Registers—0x99

Offset from Sideband Port 99h (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
220	99_0220	00042222	"ICLK_DWORD8—Port 99h, Offset 220h" on page 1480

44.2 Registers in Configuration Space

44.2.1 Device ID and Vendor ID Register (DEVICE_ID_VENDOR_ID_0_0_0_PCI)—Offset 0h

This register uniquely identifies any PCI device.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 0h

Default: 19908086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x1990 RO	**Device ID (DID):** This field identifies the particular function as allocated by Intel.
15:0	0x8086 RO	**Vendor ID (VENDOR_ID):** This field identifies Intel as the manufacturer of the device.

44.2.2 PCI Status and PCI Command Register (PCI_STATUS_COMMAND_0_0_0_PCI)—Offset 4h

PCI Status is used to record status information for PCI bus related events. PCI Command provides coarse control over a device's ability to generate and respond to PCI cycles.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 4h

Default: 00000007h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x7 RO	**PCI Status and PCI Command (PCI_STATUS_AND_COMMAND):** Allowing this device to respond to I/O space and Memory Space accesses. This device is also allowed to behave as a bus master.

44.2.3 PCI Revision ID and PCI Class Code Register (REVISION_ID_CLASS_CODE_0_0_0_PCI)—Offset 8h

Revision ID contains the revision number of the device. Class Code identifies the basic function of the device.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 8h

Default: 06000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x600 RO	**Class Code 1 (CLASS_CODE1):** This device is a Host Bridge.
15:8	0x0 RO	**Class Code 0 (CLASS_CODE0):** This device is a Host Bridge.
7:0	0x0 RW/V	**Revision ID (REVISION_ID):** Revision ID

44.2.4 Master Latency Timer and Header Type Register (MASTER_LATENCY_TIME_0_0_0_PCI)—Offset Ch

This register defines Latency Timer and layout of the device Configuration Space header.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + Ch

Default: 00800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RESERVED_1):** Reserved.
23:16	0x80 RO	**Header Type (HEADER_TYPE):** This is a multi-function device.
15:8	0x0 RO	**Master Latency Timer (MASTER_LATENCY_TIMER):** This field specifies, in units of PCI bus clocks, the value of the Latency Timer for this PCI bus master.
7:0	0x0 RO	**Reserved (RESERVED_0):** Reserved.

44.2.5 PCI Subsystem Vendor ID and PCI Subsystem ID (SVID_SID_0_0_0_PCI)—Offset 2Ch

This register is used to uniquely identify the subsystem where the PCI device resides.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Subsystem ID (SUBSYSTEM_ID):** PCI Subsystem ID: This field should be programmed during BIOS initialization.
15:0	0x0 RW	**Subsystem Vendor ID (SUBSYSTEM_VENDOR_ID):** PCI Subsystem Vendor ID: This field should be programmed by BIOS during boot-up to indicate the vendor of the system board.

44.2.6 Capability Register Pointer (CAPPTR_0_0_0_PCI)—Offset 34h

This register contains a pointer to the first Capability Register in a linked list.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 34h

Default: 000000E0h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RESERVED_0):** Reserved.
7:0	0xe0 RO	**Base Address of First Capability Register (BASE_ADDR):** This pointer is an 8-bit address to an offset within this device's Configuration Space that holds the first Capability Register (CAPID0_CAPCTRL).

44.2.7 Memory Controller Hub Base Address Register (MCHBAR_LO_0_0_0_PCI)—Offset 48h

This register contains the lower 32bits of the MCHBAR base address.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:15	0x0 RW	**Base Address of MCHBAR (BASE_ADDR):** Defines the base address of MCHBAR. MCHBAR[38:15] is MCHBAR_HI[6:0],MCHBAR_LO[31:15]. If incoming Request Address[38:15] matches MCHBAR[38:15] then the request hits and address in the MCHBAR range.
14:4	0x0 RO	**Reserved:** Reserved
3:1	0x0 RO	**Reserved:** Reserved
0	0x0 RW	**MCHBAR Enable (MCHBAREN):** • 0: MCHBAR is disabled and does not claim any memory • 1: MCHBAR memory mapped accesses are claimed and decoded appropriately

44.2.8 Memory Controller Hub Base Address Register (MCHBAR_HI_0_0_0_PCI)—Offset 4Ch

This register contains the upper 32bits of the MCHBAR base address.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**Reserved (RESERVED_0):** Reserved.
6:0	0x0 RW	**Base Address of MCHBAR (BASE_ADDR):** Defines the base address of the MCHBAR. If incoming Request Address[38:15] matches MCHBAR[38:15], then request hits an address in the MCHBAR range.

44.2.9 Device Enable Register (DEVEN_0_0_0_PCI)—Offset 54h

The DEVEN register allows for enabling/disabling of PCI devices and functions that are within the CPU package.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 54h

Default: 00000033h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved (RESERVED_1):** Reserved.
5	0x1 RW/V	**Device 3 Function 0 Enable (D3F0EN):** • 0: Bus 0 Device 3 Function 0 is disabled and hidden • 1: Bus 0 Device 3 Function 0 is enabled and visible This bit will be set to 0b and remain 0b if Device 3 capability is disabled.
4	0x1 RW/V	**Device 2 Function 0 Enable (D2F0EN):** • 0: Bus 0 Device 2 Function 0 is disabled and hidden • 1: Bus 0 Device 2 Function 0 is enabled and visible This bit will be set to 0b and remain 0b if Device 2 capability is disabled.
3	0x0 RO	**RSVD0:** Reserved
2	0x0 RO	**Reserved (RESERVED_0):** Reserved.
1	0x1 RW/V	**Device 0 Function 1 Enable (D0F1EN):** • 0: Bus 0 Device 0 Function 1 is disabled and hidden • 1: Bus 0 Device 0 Function 1 is enabled and visible This bit will be set to 0b and remain 0b if Device 0/0/1 capability is disabled.
0	0x1 RO	**Device 0 Function 0 Enable (D0F0EN):** Bus 0 Device 0 Function 0 may not be disabled, and is therefore hardwired to 1.

44.2.10 PCI Express Enhanced Configuration Range Base Address Low (PCIEXBAR_LO_0_0_0_PCI)—Offset 60h

This register contains the lower 32bits of the base address of the PCI Express Enhanced Configuration region.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**PCI Express Base Address Register (PCIEXBAR):** PCIEXBAR[38:28] is PCIEXBAR_HI[6:0],PCIEXBAR_LO[31:28]. Describes bits [38:28] of the base address of the contiguous 256MB region for PCI Express Enhanced Configuration region. If bits [38:28] of the request address matches the PCIEXBAR[38:28] then the request targets the PCI Express Enhanced Configuration Space region. **Power Well:** prst
27	0x0 RO	**Address Mask for 128MB region (ADMSK128):** Reserved. **Power Well:** prst
26	0x0 RO	**Address Mask for 64MB region (ADMSK64):** Reserved. **Power Well:** prst
25:3	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
2:1	0x0 RO	**Length of the Region (LENGTH):** Reserved. **Power Well:** prst
0	0x0 RW	**PCIEXBAR Range Enable (PCIEXBAREN):** • 0: The PCIEXBAR range is disabled. Address may target DRAM or MMIO, depending on other address decode rules. • 1: The PCIEXBAR range is enabled. Incoming request address must be compared with PCIEXBAR to determine whether the request targets PCI Express Enhanced Configuration region. **Power Well:** prst

44.2.11 PCI Express Enhanced Configuration Range Base Address High (PCIEXBAR_HI_0_0_0_PCI)—Offset 64h

This register contains the upper 32bits of the base address of the PCI Express Enhanced Configuration region.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
6:0	0x0 RW	**PCI Express Base Address Register (PCIEXBAR_HI):** PCIEXBAR[38:28] is PCIEXBAR_HI[6:0],PCIEXBAR_LO[31:28]. Describes bits [38:28] of the base address of the contiguous 256MB region for PCI Express Enhanced Configuration region. If bits [38:28] of the request address matches the PCIEXBAR[38:28] then the request targets the PCI Express Enhanced Configuration Space region. **Power Well:** prst

44.2.12 Top of Upper Usable DRAM Low (TOUUD_LO_0_0_0_PCI)—Offset A8h

Defines the top of the upper usable DRAM range and start of the upper MMIO address range. Formerly defined in BMBOUND_HI. This register contains the lower 32 bits of TOUUD.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + A8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Top of Upper Usable DRAM (TOUUD):** TOUUD[38:20] is TOUUD_HI[6:0],TOUUD_LO[31:20]. Upper usable DRAM address range ends at the preceding byte. Upper MMIO Range starts at this address and extends up to the maximum system addressable memory range. Bits 38:20 are compared with bits 38:20 of the incoming request address to determine whether the request targets the upper usable DRAM range or upper MMIO range. If Request Address[38:20])=TOUUD[38:20] and any bit in Request Address[38:32] is set, request is determined to target the upper MMIO range. **Power Well:** prst
19:1	0x0 RO	**Reserved (RESERVED_0):** Reserved should return 0s on read. **Power Well:** prst
0	0x0 RW	**TOUUD Register Lock (LOCK_RESERVED):** This bit will lock all writable settings in this register, including itself (client definition). **Power Well:** prst

44.2.13 Top of Upper Usable DRAM High (TOUUD_HI_0_0_0_PCI)—Offset ACh

Defines the top of the upper usable DRAM range and start of the upper MMIO address range. Formerly defined in BMBOUND_HI. This register contains the upper 32 bits of TOUUD.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + ACh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
6:0	0x0 RW	**Top of Upper Usable DRAM (TOUUD_HI):** TOUUD[38:20] is TOUUD_HI[6:0],TOUUD_LO[31:20]. Upper usable DRAM address range ends at the preceding byte. Upper MMIO Range starts at this address and extends up to the maximum system addressable memory range. Bits 38:20 are compared with bits 38:20 of the incoming request address to determine whether the request targets the upper usable DRAM range or upper MMIO range. If Request Address[38:20])=TOUUD[38:20] and any bit in Request Address[38:32] is set, request is determined to target the upper MMIO range. **Power Well:** prst

44.2.14 Base of Data Stolen Memory (BDSM_0_0_0_PCI)—Offset B0h

Defines the Base of the Data Stolen Memory. In addition, the GSM range is defined to end at the preceding byte. See BGSM register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Base of Data Stolen Memory (BDSM):** This register contains the base address of the Data Stolen Memory. The limit for the Data Stolen Memory is TOLUD-1. This range is not decoded by the system agent, but is a sub-region of BGSM decoded by the Integrated Graphics Device. Incoming Request Address[31:20] is compared against BDSM[31:20] and TOLUD[31:20] to determine if the address falls in the range. The comparison check is as follows: BDSM[31:20](=Address[31:20] and Address[31:20](TOLUD[31:20] and Address[38:32]==0. Request SAI is then checked against the allowed SAIs to determine if access is allowed. **Power Well:** prst
19:1	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
0	0x0 RW	**BDSM Register Lock (LOCK):** This bit will lock all writable settings in this register, including itself. **Power Well:** prst

44.2.15 Base of Graphics Stolen Memory (BGSM_0_0_0_PCI)—Offset B4h

Defines the Base of the Graphics Stolen Memory. In addition, the SMM range is defined to end at the preceding byte. See TSEGMB register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + B4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Base of Graphics Stolen Memory (BGSM):** This register contains the base address of the Graphics Stolen Memory. The limit for the Graphics Stolen Memory is TOLUD-1. Incoming Request Address[31:20] is compared against BGSM[31:20] and TOLUD[31:20] to determine if the address falls in the range. **Power Well:** prst
19:1	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
0	0x0 RW	**BGSM Register Lock (LOCK):** This bit will lock all writable settings in this register, including itself. **Power Well:** prst

44.2.16 Top Segment Memory Base (TSEGMB_0_0_0_PCI)—Offset B8h

TSEGMB defines the base of the SMM range, and the BGSM register defines the limit of the SMM range.

Note: In prior SoCs, the base register was defined in SMMRRL register and the limit was defined in the SMMRRH register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + B8h

Default: 00100000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x1 RW	**Base address of Top Segment DRAM Memory (TSEGMB):** BIOS determines the base of TSEG memory, which must be at or below Graphics Base of GTT Stolen Memory BGSM. SMM range starts at this base and ends at BGSM1. Incoming Request Address [31:20] will be compared with TSEGMB[31:20] and BGSM[31:20] to determine if the request targets the SMM range. **Power Well:** prst
19:1	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
0	0x0 RW	**TSEGMB Register Lock (LOCK):** This bit will lock all writable settings in this register, including itself. **Power Well:** prst

44.2.17 Top of Lower Usable DRAM (TOLUD_0_0_0_PCI)—Offset BCh

This register defines the Top of Lower Usable DRAM range and start of the Lower MMIO Address range. Formerly defined in BMBOUND.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + BCh

Default: 00100000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x1 RW	**Top of Lower Usable DRAM (TOLUD):** Defines the top of lower usable DRAM, which ends at the preceding byte. Lower MMIO Address range starts at this address and continues up to the 4GB Address 0xFFFF_FFFF. Bits 31:20 are compared with incoming request Address[31:20] to determine whether the request targets lower usable DRAM range or the lower MMIO range. If Request Address[31:20])=TOLUD[31:20] and Request Address[38:32]==0 then the Request Address falls in the Lower MMIO Address range. **Power Well:** prst
19:1	0x0 RO	**Reserved (RESERVED_0):** Reserved. **Power Well:** prst
0	0x0 RW	**TOLUD register lock (LOCK):** Reserved. **Power Well:** prst

44.2.18 Scratchpad (SKPD_0_0_0_PCI)—Offset DCh

This register holds 32 writable bits with no functionality behind them. It is for the convenience of BIOS and graphics drivers.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + DCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Scratchpad (SKPD):** 1 DWORD of data storage.

44.2.19 Capability ID0 Capability Control (CAPID0_CAPCTRL0_0_0_0_PCI)—Offset E0h

Control bits in this register describe the attributes of CAPID0_A and CAPID0_B capability registers.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + E0h

Default: 010C0009h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RESERVED_0):** Reserved.
27:24	0x1 RO	**Capability ID Version (CAPID_VER):** This field has the value 0001b to identify the first revision of the CAPID register definition.
23:16	0xc RO	**Capability ID0 Structure Length (CAPIDLEN):** This field has the value 0Ch to indicate the structure length 12 bytes. This is the total size of this CAPCTRL and the CAPID0_A and CAPID0_B registers in the following bytes.
15:8	0x0 RO	**Next Capability Register Pointer (NEXT_CAP):** This field is hardwired to 00h, indicating the end of the capabilities linked list.
7:0	0x9 RO	**Capability ID (CAP_ID):** This field has the value 1001b to identify the CAP_ID assigned by the PCI SIG for vendor dependent capability pointers.

44.2.20 Capability ID0 A (CAPID0_A_0_0_0_PCI)—Offset E4h

Control of bits in this register is only required for customer visible SKU differentiation.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + E4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW	**Reserved:** Reserved
23	0x0 RW/Fuse	**VTd Disable (VTDD):** • 0: Enable VTd • 1: Disable VTd
22:16	0x0 RW/Fuse	**Reserved:** Reserved for future capabilities.
15	0x0 RO/V	**Dynamic Power Performance Management (DPPM) Disable:** • 0: DPPM associated memory spaces are accessible. • 1: DPPM associated memory and IO spaces are disabled. DEVEN_0_0_0_PCI field for DPPM cannot be set.
14:0	0x0 RW/Fuse	**Reserved:** Reserved

44.2.21 Capability ID0 B (CAPID0_B_0_0_0_PCI)—Offset E8h

Control of bits in this register is only required for customer visible SKU differentiation.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + E8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Reserved:** Reserved
30	0x0 RW/Fuse	**Reserved:** Reserved
29	0x0 RW/Fuse	**Reserved:** Reserved
28	0x0 RW/Fuse	**Reserved:** Reserved
27	0x0 RW/Fuse	**Reserved:** Reserved
26	0x0 RW/Fuse	**Reserved:** Reserved
25	0x0 RW/Fuse	**Reserved:** Reserved
24	0x0 RO/V	**Shared Virtual Memory Disable (SVMDIS):** • 0: Enable Shared Virtual Memory mode • 1: Disable Shared Virtual Memory mode
23:0	0x0 RW	**Spare bits[23:0] (SPARE23_0):** Reserved for future capabilities.

44.2.22 Manufacturer ID Register (MANUFACTURER_ID_0_0_0_PCI)—Offset F4h

This register describes the manufacturing characteristics of the device.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:0, F:0] + F4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW/V	**Reserved (RESERVED_0):** Reserved.
27:24	0x0 RW/V	**DOT Portion of Process ID (DOT_PORTION_OF_PROCESS_ID):**
23:16	0x0 RW/V	**Process Portion or Process ID (PROCESS_PORTION_OF_PROCESS_ID):**
15:8	0x0 RW/V	**Manufacturing ID (MID):**
7:0	0x0 RW/V	**Manufacturing Stepping ID (MSID):**

44.3 Registers in Memory Space—MCHBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) MCHBAR. It is a 64-bit BAR and is located in Host Root Configuration Space at Bus 0, Device 0, Function 0, offset 48h and 4Ch.

See Section 44.2.7, "Memory Controller Hub Base Address Register (MCHBAR_LO_0_0_0_PCI)—Offset 48h" on page 1106 and Section 44.2.8, "Memory Controller Hub Base Address Register (MCHBAR_HI_0_0_0_PCI)—Offset 4Ch" on page 1106.

44.3.1 Default VTd Base Address Register (DEFVTDBAR_0_0_0_MCHBAR_C)—Offset 6C80h

This is the base address for the Default VT configuration space. There is no physical memory within this 4KB window that can be addressed. The 4KB reserved by this register does not alias to any PCI 2.3 compliant memory mapped space. On reset the DEFVTd configuration space is disabled and must be enabled by writing a 1'b1 to DEFVTBAREN. BIOS programs this register after which the register cannot be altered. BIOS must write DEFVTDBAR and then immediately follow it up with a read to DEFVTDBAR to ensure that all copies of DEFVTDBAR in the system are updated.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6C80h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:40	0x0 RO	**Reserved (RESERVED_1):** Reserved.
39	0x0 RO	**Reserved:** Reserved
38:12	0x0 RW	**Default VTd Base Address Register (DEFVTDBAR):** If DEFVTDBAR is enabled this field corresponds to bits 38:12 of the base address default IOMMU VTd configuration space. BIOS will program this register, resulting in a base address for a 4KB block of contiguous memory address space. This register ensures that a naturally aligned 4KB space is allocated within the first 512GB of addressable memory space. System Software uses this base address to program the default VTd IOMMU register set. If DEFVTDBAR is enabled and incoming Request Address[38:12] matches DEFVTDBAR[38:12], the request targets the Default VTd BAR.
11:2	0x0 RO	**Reserved (RESERVED_0):** Reserved.
1	0x0 RW	**DEFVTDBAR Register Lock (LOCK):** Locks the contents of the register, including itself.
0	0x0 RW/L	**Default VTd Base Address Range Enable (DEFVTDBAREN):** • 0: DEFVTDBAR is disabled and does not claim any memory • 1: DEFVTDBAR memory mapped accesses are claimed and decoded appropriately. This bit will remain 1'b0 if VTd capability is disabled.

44.3.2 Spare BIOS (A_CR_SPARE_BIOS_MCHBAR)—Offset 647Ch

Spare CR in MCHBAR.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 647Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**SPARE RW Bits (SPARE_RW):** Spare RW 32 bits in BIOSWR policy group.

44.3.3 Uncorrectable Error Status Register (A_CR_UNCERRSTS_0_0_0_MCHBAR)—Offset 6588h

Errors that have been seen in A-Unit. The error is only logged if the respective bit in UNCERRMSK is 0.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6588h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RW/1C	**iommu data iotlb parity error (iommu_data_iotlb_par_err):** IOMMU IOTLB data parity error **Power Well:** prst
24	0x0 RW/1C	**iommu data cc parity error (iommu_data_cc_par_err):** IOMMU context cache data parity error **Power Well:** prst
23	0x0 RW/1C	**iommu data l4 parity error (iommu_data_l4_par_err):** IOMMU level 4 page walk data parity error **Power Well:** prst
22	0x0 RW/1C	**iommu data l3 parity error (iommu_data_l3_par_err):** IOMMU level 3 page walk data parity error **Power Well:** prst
21	0x0 RW/1C	**iommu data l2 parity error (iommu_data_l2_par_err):** IOMMU level 2 page walk data parity error **Power Well:** prst
20	0x0 RW/1C	**downstream cmd buffer parity error (downstream_cmd_buffer_par_err):** downstream cmd buffer parity error detected **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
19	0x0 RW/1C	**downstream data buffer parity error (downstream_data_buffer_par_err):** downstream data buffer parity error detected **Power Well:** prst
18	0x0 RW/1C	**upstream cmd buffer parity error (upstream_cmd_buffer_par_err):** upstream cmd buffer parity error detected **Power Well:** prst
17	0x0 RW/1C	**iosf upstream data parity error (iosf_upstream_data_par_err):** iosf upstream data parity error detected **Power Well:** prst
16	0x0 RW/1C	**iosf upstream cmd parity error (iosf_upstream_cmd_par_err):** iosf upstream cmd parity error detected **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RW/1C	**msi rsvd set (msi_rsvd_set):** An MSI was received with reserved bits set **Power Well:** prst
9	0x0 RW/1C	**gpa overflow (gpa_overflow):** A transaction was received with a guest physical address that was too large **Power Well:** prst
8	0x0 RW/1C	**illegal msi (illegal_msi):** A malformed/illegal MSI was received in the upstream direction **Power Well:** prst
7	0x0 RW/1C	**at translated illegal device (at_translated_illegal_device):** A device that is not support to set the AT bit set it to an illegal value **Power Well:** prst
6	0x0 RO	**reserved (undefined5):** Reserved for future use. **Power Well:** prst
5	0x0 RW/1C	**bad sai cmpl (bad_sai_cmpl):** An incorrect/illegal sai was received with an upstream completion transaction. **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW/1C	**received lk cmpl (received_lk_cmpl):** Received a CmplLck completion from iosf. **Power Well:** prst
3	0x0 RW/1C	**bad sai nonposted (bad_sai_nonposted):** An incorrect/illegal sai was received with an upstream non-posted transaction. **Power Well:** prst
2	0x0 RW/1C	**illegal nonposted opcode (illegal_nonposted_opcode):** Illegal/Unsupported non-posted opcode received from iosf. **Power Well:** prst
1	0x0 RW/1C	**bad sai posted (bad_sai_posted):** An incorrect/illegal sai was received with an upstream posted transaction. **Power Well:** prst
0	0x0 RW/1C	**illegal posted opcode (illegal_posted_opcode):** Illegal/Unsupported posted opcode received from iosf. **Power Well:** prst

44.3.4 Uncorrectable Error Mask Register (A_CR_UNCERRMSK_0_0_0_MCHBAR)—Offset 658Ch

Masks whether a reported error is logged and signaled to the IEH.

1- do not log/signal.

0 - log/signal.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 658Ch

Default: FFFFFFFFh

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Reserved**
30	0x1 RO	**Reserved**
29	0x1 RO	**Reserved**
28	0x1 RO	**Reserved**
27	0x1 RO	**Reserved**
26	0x1 RO	**Reserved**
25	0x1 RW	**iommu data iotlb parity error (iommu_data_iotlb_par_err):** IOMMU IOTLB data parity error
24	0x1 RW	**iommu data cc parity error (iommu_data_cc_par_err):** IOMMU context cache data parity error
23	0x1 RW	**iommu data l4 parity error (iommu_data_l4_par_err):** IOMMU level 4 page walk data parity error
22	0x1 RW	**iommu data l3 parity error (iommu_data_l3_par_err):** IOMMU level 3 page walk data parity error
21	0x1 RW	**iommu data l2 parity error (iommu_data_l2_par_err):** IOMMU level 2 page walk data parity error
20	0x1 RW	**downstream cmd buffer parity error (downstream_cmd_buffer_par_err):** downstream cmd buffer parity error detected
19	0x1 RW	**downstream data buffer parity error (downstream_data_buffer_par_err):** downstream data buffer parity error detected
18	0x1 RW	**upstream cmd buffer parity error (upstream_cmd_buffer_par_err):** upstream cmd buffer parity error detected
17	0x1 RW	**iosf upstream data parity error (iosf_upstream_data_par_err):** iosf upstream data parity error detected
16	0x1 RW	**iosf upstream cmd parity error (iosf_upstream_cmd_par_err):** iosf upstream cmd parity error detected
15	0x1 RO	**Reserved**
14	0x1 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
13	0x1 RO	**Reserved**
12	0x1 RO	**Reserved**
11	0x1 RO	**Reserved**
10	0x1 RW	**msi rsvd set (msi_rsvd_set):** An MSI was received with reserved bits set
9	0x1 RW	**gpa overflow (gpa_overflow):** A transaction was received with a guest physical address that was too large
8	0x1 RW	**illegal msi (illegal_msi):** A malformed/illegal MSI was received in the upstream direction
7	0x1 RW	**at translated illegal device (at_translated_illegal_device):** A device that is not support to set the AT bit set it to an illegal value
6	0x1 RO	**Reserved**
5	0x1 RW	**bad sai cmpl (bad_sai_cmpl):** An incorrect/illegal sai was received with an upstream completion transaction.
4	0x1 RW	**received lk cmpl (received_lk_cmpl):** Received a CmplLck completion from iosf.
3	0x1 RW	**bad sai nonposted (bad_sai_nonposted):** An incorrect/illegal sai was received with an upstream non-posted transaction.
2	0x1 RW	**illegal nonposted opcode (illegal_nonposted_opcode):** Illegal/Unsupported non-posted opcode received from iosf.
1	0x1 RW	**bad sai posted (bad_sai_posted):** An incorrect/illegal sai was received with an upstream posted transaction.
0	0x1 RW	**illegal posted opcode (illegal_posted_opcode):** Illegal/Unsupported posted opcode received from iosf.

44.3.5 Uncorrectable Error Severity Register (A_CR_UNCERRSEV_0_0_0_MCHBAR)—Offset 6590h

When set, escalate error as fatal to IEH, otherwise non-fatal.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6590h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved**
30	0x0 RO	**Reserved**
29	0x0 RO	**Reserved**
28	0x0 RO	**Reserved**
27	0x0 RO	**Reserved**
26	0x0 RO	**Reserved**
25	0x0 RW	**iommu data iotlb parity error (iommu_data_iotlb_par_err):** IOMMU IOTLB data parity error
24	0x0 RW	**iommu data cc parity error (iommu_data_cc_par_err):** IOMMU context cache data parity error
23	0x0 RW	**iommu data l4 parity error (iommu_data_l4_par_err):** IOMMU level 4 page walk data parity error
22	0x0 RW	**iommu data l3 parity error (iommu_data_l3_par_err):** IOMMU level 3 page walk data parity error
21	0x0 RW	**iommu data l2 parity error (iommu_data_l2_par_err):** IOMMU level 2 page walk data parity error
20	0x0 RW	**downstream cmd buffer parity error (downstream_cmd_buffer_par_err):** downstream cmd buffer parity error detected
19	0x0 RW	**downstream data buffer parity error (downstream_data_buffer_par_err):** downstream data buffer parity error detected
18	0x0 RW	**upstream cmd buffer parity error (upstream_cmd_buffer_par_err):** upstream cmd buffer parity error detected
17	0x0 RW	**iosf upstream data parity error (iosf_upstream_data_par_err):** iosf upstream data parity error detected
16	0x0 RW	**iosf upstream cmd parity error (iosf_upstream_cmd_par_err):** iosf upstream cmd parity error detected
15	0x0 RO	**Reserved**
14	0x0 RO	**Reserved**
13	0x0 RO	**Reserved**
12	0x0 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
11	0x0 RO	**Reserved**
10	0x0 RW	**msi rsvd set (msi_rsvd_set):** An MSI was received with reserved bits set.
9	0x0 RW	**gpa overflow (gpa_overflow):** A transaction was received with a guest physical address that was too large
8	0x0 RW	**illegal msi (illegal_msi):** A malformed/illegal MSI was received in the upstream direction
7	0x0 RW	**at translated illegal device (at_translated_illegal_device):** A device that is not support to set the AT bit set it to an illegal value
6	0x0 RO	**Reserved**
5	0x0 RW	**bad sai cmpl (bad_sai_cmpl):** An incorrect/illegal sai was received with an upstream completion transaction.
4	0x0 RW	**received lk cmpl (received_lk_cmpl):** Received a CmplLck completion from iosf.
3	0x0 RW	**bad sai nonposted (bad_sai_nonposted):** An incorrect/illegal sai was received with an upstream non-posted transaction.
2	0x0 RW	**illegal nonposted opcode (illegal_nonposted_opcode):** Illegal/Unsupported non-posted opcode received from iosf.
1	0x0 RW	**bad sai posted (bad_sai_posted):** An incorrect/illegal sai was received with an upstream posted transaction.
0	0x0 RW	**illegal posted opcode (illegal_posted_opcode):** Illegal/Unsupported posted opcode received from iosf.

44.3.6 First Uncorrectable Error Register (A_CR_UNCFERRSTS_0_0_0_MCHBAR)—Offset 6594h

First Error Status

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6594h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO/V	**iommu data iotlb parity error (iommu_data_iotlb_par_err):** IOMMU IOTLB data parity error **Power Well:** prst
24	0x0 RO/V	**iommu data cc parity error (iommu_data_cc_par_err):** IOMMU context cache data parity error **Power Well:** prst
23	0x0 RO/V	**iommu data l4 parity error (iommu_data_l4_par_err):** IOMMU level 4 page walk data parity error **Power Well:** prst
22	0x0 RO/V	**iommu data l3 parity error (iommu_data_l3_par_err):** IOMMU level 3 page walk data parity error **Power Well:** prst
21	0x0 RO/V	**iommu data l2 parity error (iommu_data_l2_par_err):** IOMMU level 2 page walk data parity error **Power Well:** prst
20	0x0 RO/V	**downstream cmd buffer parity error (downstream_cmd_buffer_par_err):** downstream cmd buffer parity error detected **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
19	0x0 RO/V	**downstream data buffer parity error (downstream_data_buffer_par_err):** downstream data buffer parity error detected **Power Well:** prst
18	0x0 RO/V	**upstream cmd buffer parity error (upstream_cmd_buffer_par_err):** upstream cmd buffer parity error detected **Power Well:** prst
17	0x0 RO/V	**iosf upstream data parity error (iosf_upstream_data_par_err):** iosf upstream data parity error detected **Power Well:** prst
16	0x0 RO/V	**iosf upstream cmd parity error (iosf_upstream_cmd_par_err):** iosf upstream cmd parity error detected **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO/V	**msi rsvd set (msi_rsvd_set):** An MSI was received with reserved bits set **Power Well:** prst
9	0x0 RO/V	**gpa overflow (gpa_overflow):** A transaction was received with a guest physical address that was too large. **Power Well:** prst
8	0x0 RO/V	**illegal msi (illegal_msi):** A malformed/illegal MSI was received in the upstream direction **Power Well:** prst
7	0x0 RO/V	**at translated illegal device (at_translated_illegal_device):** A device that is not support to set the AT bit set it to an illegal value **Power Well:** prst
6	0x0 RO	**Reserved** **Power Well:** prst
5	0x0 RO/V	**bad sai cmpl (bad_sai_cmpl):** An incorrect/illegal sai was received with an upstream completion transaction. **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RO/V	**received lk cmpl (received_lk_cmpl):** Received a CmplLck completion from iosf. **Power Well:** prst
3	0x0 RO/V	**bad sai nonposted (bad_sai_nonposted):** An incorrect/illegal sai was received with an upstream non-posted transaction. **Power Well:** prst
2	0x0 RO/V	**illegal nonposted opcode (illegal_nonposted_opcode):** Illegal/Unsupported non-posted opcode received from iosf. **Power Well:** prst
1	0x0 RO/V	**bad sai posted (bad_sai_posted):** An incorrect/illegal sai was received with an upstream posted transaction. **Power Well:** prst
0	0x0 RO/V	**illegal posted opcode (illegal_posted_opcode):** Illegal/Unsupported posted opcode received from iosf. **Power Well:** prst

44.3.7 Next Uncorrectable Error Register (A_CR_UNCNERRSTS_0_0_0_MCHBAR)—Offset 6598h

Next Error Status

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6598h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO/V	**iommu data iotlb parity error (iommu_data_iotlb_par_err):** IOMMU IOTLB data parity error **Power Well:** prst
24	0x0 RO/V	**iommu data cc parity error (iommu_data_cc_par_err):** IOMMU context cache data parity error **Power Well:** prst
23	0x0 RO/V	**iommu data l4 parity error (iommu_data_l4_par_err):** IOMMU level 4 page walk data parity error **Power Well:** prst
22	0x0 RO/V	**iommu data l3 parity error (iommu_data_l3_par_err):** IOMMU level 3 page walk data parity error **Power Well:** prst
21	0x0 RO/V	**iommu data l2 parity error (iommu_data_l2_par_err):** IOMMU level 2 page walk data parity error **Power Well:** prst
20	0x0 RO/V	**downstream cmd buffer parity error (downstream_cmd_buffer_par_err):** downstream cmd buffer parity error detected **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
19	0x0 RO/V	**downstream data buffer parity error (downstream_data_buffer_par_err):** Downstream data buffer parity error detected **Power Well:** prst
18	0x0 RO/V	**upstream cmd buffer parity error (upstream_cmd_buffer_par_err):** Upstream cmd buffer parity error detected **Power Well:** prst
17	0x0 RO/V	**iosf upstream data parity error (iosf_upstream_data_par_err):** IOSF upstream data parity error detected **Power Well:** prst
16	0x0 RO/V	**iosf upstream cmd parity error (iosf_upstream_cmd_par_err):** IOSF upstream cmd parity error detected **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO/V	**msi rsvd set (msi_rsvd_set):** An MSI was received with reserved bits set **Power Well:** prst
9	0x0 RO/V	**gpa overflow (gpa_overflow):** A transaction was received with a guest physical address that was too large **Power Well:** prst
8	0x0 RO/V	**illegal msi (illegal_msi):** A malformed/illegal MSI was received in the upstream direction **Power Well:** prst
7	0x0 RO/V	**at translated illegal device (at_translated_illegal_device):** A device that is not support to set the AT bit set it to an illegal value **Power Well:** prst
6	0x0 RO	**Reserved** **Power Well:** prst
5	0x0 RO/V	**bad sai cmpl (bad_sai_cmpl):** An incorrect/illegal sai was received with an upstream completion transaction. **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RO/V	**received lk cmpl (received_lk_cmpl):** Received a CmplLck completion from IOSF. **Power Well:** prst
3	0x0 RO/V	**bad sai nonposted (bad_sai_nonposted):** An incorrect/illegal sai was received with an upstream non-posted transaction. **Power Well:** prst
2	0x0 RO/V	**illegal nonposted opcode (illegal_nonposted_opcode):** Illegal/Unsupported non-posted opcode received from iosf. **Power Well:** prst
1	0x0 RO/V	**bad sai posted (bad_sai_posted):** An incorrect/illegal sai was received with an upstream posted transaction. **Power Well:** prst
0	0x0 RO/V	**illegal posted opcode (illegal_posted_opcode):** Illegal/Unsupported posted opcode received from iosf. **Power Well:** prst

44.3.8 Uncorrectable Error Select Register (A_CR_UNCERRCNTSEL_0_0_0_MCHBAR)—Offset 659Ch

Selects which errors cause the UNCERRCNT register to increment. 0-do not count 1-count.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 659Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved**
30	0x0 RO	**Reserved**
29	0x0 RO	**Reserved**
28	0x0 RO	**Reserved**
27	0x0 RO	**Reserved**
26	0x0 RO	**Reserved**
25	0x0 RW	**iommu data iotlb parity error (iommu_data_iotlb_par_err):** IOMMU IOTLB data parity error
24	0x0 RW	**iommu data cc parity error (iommu_data_cc_par_err):** IOMMU context cache data parity error
23	0x0 RW	**iommu data l4 parity error (iommu_data_l4_par_err):** IOMMU level 4 page walk data parity error
22	0x0 RW	**iommu data l3 parity error (iommu_data_l3_par_err):** IOMMU level 3 page walk data parity error
21	0x0 RW	**iommu data l2 parity error (iommu_data_l2_par_err):** IOMMU level 2 page walk data parity error
20	0x0 RW	**downstream cmd buffer parity error (downstream_cmd_buffer_par_err):** downstream cmd buffer parity error detected
19	0x0 RW	**downstream data buffer parity error (downstream_data_buffer_par_err):** downstream data buffer parity error detected
18	0x0 RW	**upstream cmd buffer parity error (upstream_cmd_buffer_par_err):** upstream cmd buffer parity error detected
17	0x0 RW	**iosf upstream data parity error (iosf_upstream_data_par_err):** iosf upstream data parity error detected
16	0x0 RW	**iosf upstream cmd parity error (iosf_upstream_cmd_par_err):** iosf upstream cmd parity error detected
15	0x0 RO	**Reserved**
14	0x0 RO	**Reserved**
13	0x0 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
12	0x0 RO	**Reserved**
11	0x0 RO	**Reserved**
10	0x0 RW	**msi rsvd set (msi_rsvd_set):** An MSI was received with reserved bits set
9	0x0 RW	**gpa overflow (gpa_overflow):** A transaction was received with a guest physical address that was too large
8	0x0 RW	**illegal msi (illegal_msi):** A malformed/illegal MSI was received in the upstream direction
7	0x0 RW	**at translated illegal device (at_translated_illegal_device):** A device that is not support to set the AT bit set it to an illegal value
6	0x0 RO	**Reserved**
5	0x0 RW	**bad sai cmpl (bad_sai_cmpl):** An incorrect/illegal sai was received with an upstream completion transaction.
4	0x0 RW	**received lk cmpl (received_lk_cmpl):** Received a CmplLck completion from iosf.
3	0x0 RW	**bad sai nonposted (bad_sai_nonposted):** An incorrect/illegal sai was received with an upstream non-posted transaction.
2	0x0 RW	**illegal nonposted opcode (illegal_nonposted_opcode):** Illegal/Unsupported non-posted opcode received from iosf.
1	0x0 RW	**bad sai posted (bad_sai_posted):** An incorrect/illegal sai was received with an upstream posted transaction.
0	0x0 RW	**illegal posted opcode (illegal_posted_opcode):** Illegal/Unsupported posted opcode received from iosf.

44.3.9 Uncorrectable Error Count (A_CR_UNCERRCNT_0_0_0_MCHBAR)—Offset 65A0h

Counts the number of uncorrectable errors that have occurred.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65A0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C	**Overflow (OVERFLOW):** Error count overflow. **Power Well:** prst
14:0	0x0 RW/1C	**Error Count (ERR_CNT):** Uncorrectable error count. **Power Well:** prst

44.3.10 Correctable Error Status Register (A_CR_CORERRSTS_0_0_0_MCHBAR)—Offset 65A4h

Errors that have been seen in A-Unit. This will always log errors irrespective of the CORERRMSK bit setting

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65A4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RO	**Reserved** **Power Well:** prst
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RO	**Reserved** **Power Well:** prst
8	0x0 RO	**Reserved** **Power Well:** prst
7	0x0 RO	**Reserved** **Power Well:** prst
6	0x0 RO	**Reserved** **Power Well:** prst
5	0x0 RO	**Reserved** **Power Well:** prst
4	0x0 RW/1C	**iommu tag iotlb parity error (iommu_tag_iotlb_par_err):** IOMMU iotlb tag parity error detected **Power Well:** prst
3	0x0 RW/1C	**iommu tag cc parity error (iommu_tag_cc_par_err):** IOMMU context cache tag parity error detected **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/1C	**iommu tag l4 parity error (iommu_tag_l4_par_err):** IOMMU l4 cache tag parity error detected **Power Well:** prst
1	0x0 RW/1C	**iommu tag l3 parity error (iommu_tag_l3_par_err):** IOMMU l3 cache tag parity error detected **Power Well:** prst
0	0x0 RW/1C	**iommu tag l2 parity error (iommu_tag_l2_par_err):** IOMMU l2 cache tag parity error detected **Power Well:** prst

44.3.11 Correctable Error Mask Register (A_CR_CORERRMSK_0_0_0_MCHBAR)—Offset 65A8h

Masks where a reported error is signaled to the IEH. 1- do not signal. 0 - signal.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65A8h

Default: FFFFFFFFh

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Reserved**
30	0x1 RO	**Reserved**
29	0x1 RO	**Reserved**
28	0x1 RO	**Reserved**
27	0x1 RO	**Reserved**
26	0x1 RO	**Reserved**
25	0x1 RO	**Reserved**
24	0x1 RO	**Reserved**
23	0x1 RO	**Reserved**
22	0x1 RO	**Reserved**
21	0x1 RO	**Reserved**
20	0x1 RO	**Reserved**
19	0x1 RO	**Reserved**
18	0x1 RO	**Reserved**
17	0x1 RO	**Reserved**
16	0x1 RO	**Reserved**
15	0x1 RO	**Reserved**
14	0x1 RO	**Reserved**
13	0x1 RO	**Reserved**
12	0x1 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
11	0x1 RO	**Reserved**
10	0x1 RO	**Reserved**
9	0x1 RO	**Reserved**
8	0x1 RO	**Reserved**
7	0x1 RO	**Reserved**
6	0x1 RO	**Reserved**
5	0x1 RO	**Reserved**
4	0x1 RW	**iommu tag iotlb parity error (iommu_tag_iotlb_par_err):** IOMMU iotlb tag parity error detected
3	0x1 RW	**iommu tag cc parity error (iommu_tag_cc_par_err):** IOMMU context cache tag parity error detected
2	0x1 RW	**iommu tag l4 parity error (iommu_tag_l4_par_err):** IOMMU l4 cache tag parity error detected
1	0x1 RW	**iommu tag l3 parity error (iommu_tag_l3_par_err):** IOMMU l3 cache tag parity error detected
0	0x1 RW	**iommu tag l2 parity error (iommu_tag_l2_par_err):** IOMMU l2 cache tag parity error detected

44.3.12 First Correctable Error Register (A_CR_CORFERRSTS_0_0_0_MCHBAR)—Offset 65ACh

First Error Status

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65ACh

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst
18	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RO	**Reserved** **Power Well:** prst
8	0x0 RO	**Reserved** **Power Well:** prst
7	0x0 RO	**Reserved** **Power Well:** prst
6	0x0 RO	**Reserved** **Power Well:** prst
5	0x0 RO	**Reserved** **Power Well:** prst
4	0x0 RO/V	**iommu tag iotlb parity error (iommu_tag_iotlb_par_err):** IOMMU iotlb tag parity error detected **Power Well:** prst
3	0x0 RO/V	**iommu tag cc parity error (iommu_tag_cc_par_err):** IOMMU context cache tag parity error detected **Power Well:** prst
2	0x0 RO/V	**iommu tag l4 parity error (iommu_tag_l4_par_err):** IOMMU l4 cache tag parity error detected **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO/V	**iommu tag l3 parity error (iommu_tag_l3_par_err):** IOMMU l3 cache tag parity error detected **Power Well:** prst
0	0x0 RO/V	**iommu tag l2 parity error (iommu_tag_l2_par_err):** IOMMU l2 cache tag parity error detected **Power Well:** prst

44.3.13 Next Correctable Error Register (A_CR_CORNERRSTS_0_0_0_MCHBAR)—Offset 65B0h

Next Error Status

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65B0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst
18	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RO	**Reserved** **Power Well:** prst
8	0x0 RO	**Reserved** **Power Well:** prst
7	0x0 RO	**Reserved** **Power Well:** prst
6	0x0 RO	**Reserved** **Power Well:** prst
5	0x0 RO	**Reserved** **Power Well:** prst
4	0x0 RO/V	**iommu tag iotlb parity error (iommu_tag_iotlb_par_err):** IOMMU iotlb tag parity error detected **Power Well:** prst
3	0x0 RO/V	**iommu tag cc parity error (iommu_tag_cc_par_err):** IOMMU context cache tag parity error detected **Power Well:** prst
2	0x0 RO/V	**iommu tag l4 parity error (iommu_tag_l4_par_err):** IOMMU l4 cache tag parity error detected **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO/V	**iommu tag l3 parity error (iommu_tag_l3_par_err):** IOMMU l3 cache tag parity error detected **Power Well:** prst
0	0x0 RO/V	**iommu tag l2 parity error (iommu_tag_l2_par_err):** IOMMU l2 cache tag parity error detected **Power Well:** prst

44.3.14 Correctable Error Count Select (A_CR_CORERRCNTSEL_0_0_0_MCHBAR)—Offset 65B4h

Selects which errors cause the CORERRCNT register to increment. 0-do not count 1-count.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: FFFFFFFFh

BAR and Offset: [MCHBAR] + 65B4h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Reserved**
30	0x1 RO	**Reserved**
29	0x1 RO	**Reserved**
28	0x1 RO	**Reserved**
27	0x1 RO	**Reserved**
26	0x1 RO	**Reserved**
25	0x1 RO	**Reserved**
24	0x1 RO	**Reserved**
23	0x1 RO	**Reserved**
22	0x1 RO	**Reserved**
21	0x1 RO	**Reserved**
20	0x1 RO	**Reserved**
19	0x1 RO	**Reserved**
18	0x1 RO	**Reserved**
17	0x1 RO	**Reserved**
16	0x1 RO	**Reserved**
15	0x1 RO	**Reserved**
14	0x1 RO	**Reserved**
13	0x1 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
12	0x1 RO	**Reserved**
11	0x1 RO	**Reserved**
10	0x1 RO	**Reserved**
9	0x1 RO	**Reserved**
8	0x1 RO	**Reserved**
7	0x1 RO	**Reserved**
6	0x1 RO	**Reserved**
5	0x1 RO	**Reserved**
4	0x1 RW	**iommu tag iotlb parity error (iommu_tag_iotlb_par_err):** IOMMU iotlb tag parity error detected
3	0x1 RW	**iommu tag cc parity error (iommu_tag_cc_par_err):** IOMMU context cache tag parity error detected
2	0x1 RW	**iommu tag l4 parity error (iommu_tag_l4_par_err):** IOMMU l4 cache tag parity error detected
1	0x1 RW	**iommu tag l3 parity error (iommu_tag_l3_par_err):** IOMMU l3 cache tag parity error detected
0	0x1 RW	**iommu tag l2 parity error (iommu_tag_l2_par_err):** IOMMU l2 cache tag parity error detected

44.3.15 Correctable Error Count (A_CR_CORERRCNT_0_0_0_MCHBAR)—Offset 65B8h

Counts the number of correctable errors that have occurred

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65B8h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C	**Overflow (OVERFLOW):** Error count overflowed. **Power Well:** prst
14:0	0x0 RW/1C	**Error Count (ERR_CNT):** Correctable error count **Power Well:** prst

44.3.16 Slice and Channel Hash (A_CR_SLICE_CHANNEL_HASH_0_0_0_MCHBAR)—Offset 65C0h

A-Unit slice and channel hash function.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 65C0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**Lock (LOCK):** Intended usage is for BIOS to set the LOCK when it updates the CR.
62:52	0x0 RO	**RSVD0:** Reserved
51:38	0x0 RW	**Channel Hash Mask (CH_HASH_MASK):** When both PMI channels in a slice are enabled, this field specifies the Channel Hash Mask to be applied on Addr[19:6] postremap DRAM address of the request to compute which PMI channel a request must be routed to. Relevant only when HVM mode is disabled and only for requests that do not fall under the MOT region. B-Unit will override the programmed value to include the Channel Selector bit See SLICEHASH.INTERLEAVE_MODE field. Note that HVM mode and MOT regions have special hash requirements and hence they do not use the CH_HASH_MASK.
37:33	0x0 RO	**RSVD1:** Reserved
32	0x0 RW	**Channel 1 Disabled (CH_1_DISABLED):** Channel 1 in both slices are disabled no memory address mapped to ch 1. All requests sent to channel 0.
31	0x0 RW	**Spare (SPARE):** No identified usage yet.
30:20	0x0 RO	**RSVD2:** Reserved
19:6	0x0 RW	**Slice Hash Mask (SLICE_HASH_MASK):** When both slices are enabled this field specifies the Slice Hash Mask to be applied on Addr[19:6] physical address of the request to compute which slice a request must be routed to. Relevant only when HVM mode is disabled and only for physical addresses that do not fall under the Asymmetric Memory Region and the MOT region. B-Unit will override the programmed value to include the Slice Selector bit See INTERLEAVE_MODE field. Note that HVM mode non-address IDI requests asymmetric memory region and MOT regions have special hash requirements and hence they do not use the SLICE_HASH_MASK.
5	0x0 RO	**RSVD3:** Reserved
4	0x0 RW	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
3:2	0x0 RW	**Interleave Mode (INTERLEAVE_MODE):** Default interleave mode that specifies how the Slice Selector and Channel Selector bits are to be determined. Relevant only when HVM mode is disabled and only for system memory addresses that do not fall under the MOT region or the Asymmetric memory region in the System Address Map. Legal encodings are 0x0 0x1 and 0x2. An encoding of 0x3 is treated as if it was 0x2. When both slices and all four PMI channels are enabled: • 0h: Default Slice Selector is Addr[10] and Default Channel Selector is Addr[11] • 1h: Default Slice Selector is Addr[11] and Default Channel Selector is Addr[12] • 2h: Default Slice Selector is Addr[12] and Default Channel Selector is Addr[13] When both slices are enabled but only one channel in each slice enabled: • 0h: Default Slice Selector is Addr[10] • 1h: Default Slice Selector is Addr[11] • 2h: Default Slice Selector is Addr[12] When only SLICE0 is enabled and both channels on that slice are enabled: • 0h: Default Channel Selector is Addr[10] • 1h: Default Channel Selector is Addr[11] • 2h: Default Channel Selector is Addr[12] When SLICE0 and only one channel in that slice is enabled this field is not relevant. B-Unit overrides the setting of the SLICE_HASH_MASK to always include the Slice Selector bit. Similarly, B-Unit overrides the setting of the CH_HASH_MASK to always include the Channel Selector bit.
1	0x0 RW	**Reserved**
0	0x0 RW	**Slice 1 Disabled (SLICE_1_DISABLED):** Slice 1 is disabled; no memory address mapped to Slice 1. All request sent to Slice 0.

44.3.17 A_CR_ASYM_MEM_REGION0_0_0_0_MCHBAR—Offset 65D0h

Specification of asymmetric memory region 0 (in slice 0) for the configuration with 2 asymmetric memory regions.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65D0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**SLICE0_ASYM_ENABLE:** Setting this bit to 0 disables asymmetric memory region 0; setting it to 1 enables the region.
30:28	0x0 RO	**RSVD0:** Reserved
27:20	0x0 RW	**SLICE0_ASYM_LIMIT:** Specifies bits [38:31] of the highest address of asymmetric memory region 0 (in slice 0); all the lower bits of the region's highest address are equal to 1.
19:12	0x0 RO	**RSVD1:** Reserved
11:4	0x0 RW	**SLICE0_ASYM_BASE:** Specifies bits [38:31] of the base address of asymmetric memory region 0 (in slice 0); all the lower bits of the region's base address are equal to 0.
3:0	0x0 RO	**RSVD2:** Reserved

44.3.18 A_CR_ASYM_MEM_REGION1_0_0_0_MCHBAR—Offset 65D4h

Specification of asymmetric memory region 1 (in slice 1) for the configuration with 2 asymmetric memory regions.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 65D4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**SLICE1_ASYM_ENABLE:** Setting this bit to 0 disables asymmetric memory region 1; setting it to 1 enables the region.
30:28	0x0 RO	**RSVD0:** Reserved
27:20	0x0 RW	**SLICE1_ASYM_LIMIT:** Specifies bits [38:31] of the highest address of asymmetric memory region 1 (in slice 1); all the lower bits of the region's highest address are equal to 1.
19:12	0x0 RO	**RSVD1:** Reserved
11:4	0x0 RW	**SLICE1_ASYM_BASE:** Specifies bits [38:31] of the base address of asymmetric memory region 1 (in slice 1); all the lower bits of the region's base address are equal to 0.
3:0	0x0 RO	**RSVD2:** Reserved

44.3.19 B-Unit Miscellaneous Configuration (B_CR_BMISC_0_0_0_MCHBAR)—Offset 6800h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000007h

BAR and Offset: [MCHBAR] + 6800h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RESERVED_0):** Reserved.
3	0x0 RW	**Send Boot Vector to DRAM (SEND_BOOT_VECTOR_TO_DRAM):** When set, IA accesses to 0xFFFF_0000 to 0XFFFF_FFFF will be sent to memory, regardless of the Host IO Boundary setting in TOLUD.
2	0x1 RW	**ABSeginDRAM Legacy Video Area (ABSEGINDRAM):** When this bit is set, reads and writes targeting A or Bsegments are routed to DRAM. Asegment corresponds to the memory range 0xA_0000 to 0xA_FFFF. Bsegment corresponds to the memory ranges 0xB_0000 to 0xB_7FFF and 0xB_8000 to 0xB_FFFF.
1	0x1 RW	**Read FSeg from DRAM (READ_FSEG_FROM_DRAM):** Writes and reads targeting Fsegment are routed to DRAM. Fsegment corresponds to the memory range 0xF_0000 to 0xF_FFFF. This bit must be set '1'.
0	0x1 RW	**Read ESeg from DRAM (READ_ESEG_FROM_DRAM):** Writes and reads targeting Esegment are routed to DRAM. Esegment corresponds to the memory range 0xE_0000 to 0xE_FFFF. This bit must be set '1'.

44.3.20 Slice 0 Memory Access Count (B_CR_MEM_ACCESS_COUNT_SLICE0)—Offset 6868h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6868h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Memory Access Count (MEM_ACCESS_COUNT):** Counts the number of PMI transactions that the B-Unit has sent to any PMI channel. Counts both reads and writes. Counter is not saturating and will roll over to zero. It is up to the consumer of the counter to handle roll over cases.

44.3.21 Slice 1 Memory Access Count (B_CR_MEM_ACCESS_COUNT_SLICE1)—Offset 686Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 686Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Memory Access Count (MEM_ACCESS_COUNT):** Counts the number of PMI transactions that the B-Unit has sent to any PMI channel. Counts both reads and writes. Counter is not saturating and will roll over to zero. It is up to the consumer of the counter to handle roll over cases.

44.3.22 IMR0 Base (B_CR_BIMR0BASE_0_0_0_MCHBAR)—Offset 6870h

This register, along with IMR0MASK, IMR0RAC, and IMR0WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR0RAC and IMR0WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6870h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**Reserved (RESERVED_1):** Reserved.
28:0	0x0 RW	**Base 0 IMR0 Base (IMR0_BASE):** Specifies bits 38:10 of the start address of IMR0 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR0MASK[28:0] applied to bits 38:10 of the incoming address, to determine if an access falls within the IMR0 defined region.

44.3.23 IMR0 Mask (B_CR_BIMR0MASK_0_0_0_MCHBAR)—Offset 6874h

This register, along with IMR0BASE, IMR0RAC, and IMR0WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR0RAC and IMR0WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6874h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit WB Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables return to the requester of implicit writeback HITM data from GT. When set to 0, inhibits HITM data from GT from being returned to the requester. HITM data from IA cores may be returned to the requester depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit WB Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requester. When set to 0, inhibits HITM data from IA cores from being returned to the requester. HITM data from GT may be returned to the requester, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**Reserved (RESERVED_0):** Reserved.
28:0	0x0 RW	**Mask 0 IMR0 Mask (IMR0_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR0BASE[28:0] value. A match indicates that the incoming address falls within the IMR0 region.

44.3.24 IMR0 Control Policy (B_CR_BIMR0CP_0_0_0_MCHBAR)—Offset 6878h

This register controls the access policy to the Read Access Policy BIMR0RAC, Write Access Policy BIMR0WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6878h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR0 Control Policy (IMR0_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR0RAC, BIMR0WAC and BIMR0CP registers based on the value from each agent's 6bit SAI field.

44.3.25 IMR0 Read Access Policy (B_CR_BIMR0RAC_0_0_0_MCHBAR)—Offset 6880h

This register, along with IMR0BASE, IMR0MASK and IMR0WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR0. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6880h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR0 Read Access Policy 63 (IMR0_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR0 Read Access Policy 62 (IMR0_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR0 Read Access Policy 61 (IMR0_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR0 Read Access Policy 60 (IMR0_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR0 Read Access Policy 59 (IMR0_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR0 Read Access Policy 58 (IMR0_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR0 Read Access Policy 57 (IMR0_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR0 Read Access Policy 56 (IMR0_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR0 Read Access Policy 55 (IMR0_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR0 Read Access Policy 54 (IMR0_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR0 Read Access Policy 53 (IMR0_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR0 Read Access Policy 52 (IMR0_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR0 Read Access Policy 51 (IMR0_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR0 Read Access Policy 50 (IMR0_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR0 Read Access Policy 49 (IMR0_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR0 Read Access Policy 48 (IMR0_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR0 Read Access Policy 47 (IMR0_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR0 Read Access Policy 46 (IMR0_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR0 Read Access Policy 45 (IMR0_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR0 Read Access Policy 44 (IMR0_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR0 Read Access Policy 43 (IMR0_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR0 Read Access Policy 42 (IMR0_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR0 Read Access Policy 41 (IMR0_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR0 Read Access Policy 40 (IMR0_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR0 Read Access Policy 39 (IMR0_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR0 Read Access Policy 38 (IMR0_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR0 Read Access Policy 37 (IMR0_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR0 Read Access Policy 36 (IMR0_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR0 Read Access Policy 35 (IMR0_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR0 Read Access Policy 34 (IMR0_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR0 Read Access Policy 33 (IMR0_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR0 Read Access Policy 32 (IMR0_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR0 Read Access Policy 31 (IMR0_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR0 Read Access Policy 30 (IMR0_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR0 Read Access Policy 29 (IMR0_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR0 Read Access Policy 28 (IMR0_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR0 Read Access Policy 27 (IMR0_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR0 Read Access Policy 26 (IMR0_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR0 Read Access Policy 25 (IMR0_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR0 Read Access Policy 24 (IMR0_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR0 Read Access Policy 23 (IMR0_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR0 Read Access Policy 22 (IMR0_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR0 Read Access Policy 21 (IMR0_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR0 Read Access Policy 20 (IMR0_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR0 Read Access Policy 19 (IMR0_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR0 Read Access Policy 18 (IMR0_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR0 Read Access Policy 17 (IMR0_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR0 Read Access Policy 16 (IMR0_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR0 Read Access Policy 15 (IMR0_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR0 Read Access Policy 14 (IMR0_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR0 Read Access Policy 13 (IMR0_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR0 Read Access Policy 12 (IMR0_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR0 Read Access Policy 11 (IMR0_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR0 Read Access Policy 10 (IMR0_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR0 Read Access Policy 9 (IMR0_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR0 Read Access Policy 8 (IMR0_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR0 Read Access Policy 7 (IMR0_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR0 Read Access Policy 6 (IMR0_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR0 Read Access Policy 5 (IMR0_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR0 Read Access Policy 4 (IMR0_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR0 Read Access Policy 3 (IMR0_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR0 Read Access Policy 2 (IMR0_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR0 Read Access Policy 1 (IMR0_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR0 Read Access Policy 0 (IMR0_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR0 region, based on each agent's 6bit encoded SAI value.

44.3.26 IMR0 Write Access Policy (B_CR_BIMR0WAC_0_0_0_MCHBAR)—Offset 6888h

This register, along with IMR0BASE, IMR0MASK and IMR0RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR0. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6888h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR0 Write Access Policy 63 (IMR0_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR0 Write Access Policy 62 (IMR0_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR0 Write Access Policy 61 (IMR0_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR0 Write Access Policy 60 (IMR0_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR0 Write Access Policy 59 (IMR0_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR0 Write Access Policy 58 (IMR0_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR0 Write Access Policy 57 (IMR0_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR0 Write Access Policy 56 (IMR0_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR0 Write Access Policy 55 (IMR0_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR0 Write Access Policy 54 (IMR0_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR0 Write Access Policy 53 (IMR0_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR0 Write Access Policy 52 (IMR0_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR0 Write Access Policy 51 (IMR0_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR0 Write Access Policy 50 (IMR0_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR0 Write Access Policy 49 (IMR0_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR0 Write Access Policy 48 (IMR0_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR0 Write Access Policy 47 (IMR0_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR0 Write Access Policy 46 (IMR0_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR0 Write Access Policy 45 (IMR0_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR0 Write Access Policy 44 (IMR0_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR0 Write Access Policy 43 (IMR0_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR0 Write Access Policy 42 (IMR0_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR0 Write Access Policy 41 (IMR0_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR0 Write Access Policy 40 (IMR0_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR0 Write Access Policy 39 (IMR0_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR0 Write Access Policy 38 (IMR0_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR0 Write Access Policy 37 (IMR0_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR0 Write Access Policy 36 (IMR0_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR0 Write Access Policy 35 (IMR0_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR0 Write Access Policy 34 (IMR0_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR0 Write Access Policy 33 (IMR0_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR0 Write Access Policy 32 (IMR0_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR0 Write Access Policy 31 (IMR0_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR0 Write Access Policy 30 (IMR0_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR0 Write Access Policy 29 (IMR0_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR0 Write Access Policy 28 (IMR0_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR0 Write Access Policy 27 (IMR0_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR0 Write Access Policy 26 (IMR0_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR0 Write Access Policy 25 (IMR0_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR0 Write Access Policy 24 (IMR0_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR0 Write Access Policy 23 (IMR0_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR0 Write Access Policy 22 (IMR0_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR0 Write Access Policy 21 (IMR0_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR0 Write Access Policy 20 (IMR0_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR0 Write Access Policy 19 (IMR0_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR0 Write Access Policy 18 (IMR0_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR0 Write Access Policy 17 (IMR0_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR0 Write Access Policy 16 (IMR0_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR0 Write Access Policy 15 (IMR0_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR0 Write Access Policy 14 (IMR0_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR0 Write Access Policy 13 (IMR0_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR0 Write Access Policy 12 (IMR0_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR0 Write Access Policy 11 (IMR0_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR0 Write Access Policy 10 (IMR0_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR0 Write Access Policy 9 (IMR0_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR0 Write Access Policy 8 (IMR0_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR0 Write Access Policy 7 (IMR0_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR0 Write Access Policy 6 (IMR0_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR0 Write Access Policy 5 (IMR0_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR0 Write Access Policy 4 (IMR0_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR0 Write Access Policy 3 (IMR0_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR0 Write Access Policy 2 (IMR0_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR0 Write Access Policy 1 (IMR0_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR0 Write Access Policy 0 (IMR0_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR0 region, based on each agent's 6bit encoded SAI value.

44.3.27 B_CR_BIMR1BASE_0_0_0_MCHBAR—Offset 6890h

This register, along with IMR1MASK, IMR1RAC and IMR1WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR1RAC and IMR1WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6890h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Trace Enable (TR_EN):** Asset Classification AC[0]: Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 1 IMR1 Base (IMR1_BASE):** Specifies bits 38:10 of the start address of IMR1 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR1MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR1 defined region.

44.3.28 IMR1 Mask (B_CR_BIMR1MASK_0_0_0_MCHBAR)—Offset 6894h

This register, along with IMR1BASE, IMR1RAC and IMR1WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR1RAC and IMR1WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6894h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GT Implicit Writeback Enable (GT_IWB_EN):** Asset Classification AC[2]: Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables return to the requestor of implicit writeback HITM data from GT. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 1 IMR1 Mask (IMR1_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR1BASE[28:0] value. A match indicates that the incoming address falls within the IMR1 region.

44.3.29 IMR1 Control Policy (B_CR_BIMR1CP_0_0_0_MCHBAR)—Offset 6898h

This register controls the access policy to the Read Access Policy BIMR1RAC, the Write Access Policy BIMR1WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6898h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR1 Control Policy (IMR1_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR1RAC, BIMR1WAC and BIMR1CP registers, based on the value from each agent's 6bit SAI field.

44.3.30 IMR1 Read Access Policy (B_CR_BIMR1RAC_0_0_0_MCHBAR)—Offset 68A0h

This register, along with IMR1BASE, IMR1MASK and IMR1WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR1. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68A0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR1 Read Access Policy 63 (IMR1_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR1 Read Access Policy 62 (IMR1_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR1 Read Access Policy 61 (IMR1_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR1 Read Access Policy 60 (IMR1_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR1 Read Access Policy 59 (IMR1_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR1 Read Access Policy 58 (IMR1_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR1 Read Access Policy 57 (IMR1_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR1 Read Access Policy 56 (IMR1_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR1 Read Access Policy 55 (IMR1_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR1 Read Access Policy 54 (IMR1_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR1 Read Access Policy 53 (IMR1_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR1 Read Access Policy 52 (IMR1_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR1 Read Access Policy 51 (IMR1_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR1 Read Access Policy 50 (IMR1_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR1 Read Access Policy 49 (IMR1_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR1 Read Access Policy 48 (IMR1_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR1 Read Access Policy 47 (IMR1_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR1 Read Access Policy 46 (IMR1_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR1 Read Access Policy 45 (IMR1_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR1 Read Access Policy 44 (IMR1_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR1 Read Access Policy 43 (IMR1_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR1 Read Access Policy 42 (IMR1_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR1 Read Access Policy 41 (IMR1_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR1 Read Access Policy 40 (IMR1_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR1 Read Access Policy 39 (IMR1_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR1 Read Access Policy 38 (IMR1_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR1 Read Access Policy 37 (IMR1_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR1 Read Access Policy 36 (IMR1_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR1 Read Access Policy 35 (IMR1_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR1 Read Access Policy 34 (IMR1_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR1 Read Access Policy 33 (IMR1_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR1 Read Access Policy 32 (IMR1_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR1 Read Access Policy 31 (IMR1_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR1 Read Access Policy 30 (IMR1_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR1 Read Access Policy 29 (IMR1_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR1 Read Access Policy 28 (IMR1_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR1 Read Access Policy 27 (IMR1_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR1 Read Access Policy 26 (IMR1_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR1 Read Access Policy 25 (IMR1_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR1 Read Access Policy 24 (IMR1_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR1 Read Access Policy 23 (IMR1_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR1 Read Access Policy 22 (IMR1_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR1 Read Access Policy 21 (IMR1_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR1 Read Access Policy 20 (IMR1_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR1 Read Access Policy 19 (IMR1_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR1 Read Access Policy 18 (IMR1_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR1 Read Access Policy 17 (IMR1_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR1 Read Access Policy 16 (IMR1_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR1 Read Access Policy 15 (IMR1_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR1 Read Access Policy 14 (IMR1_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR1 Read Access Policy 13 (IMR1_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR1 Read Access Policy 12 (IMR1_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR1 Read Access Policy 11 (IMR1_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR1 Read Access Policy 10 (IMR1_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR1 Read Access Policy 9 (IMR1_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR1 Read Access Policy 8 (IMR1_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR1 Read Access Policy 7 (IMR1_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR1 Read Access Policy 6 (IMR1_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR1 Read Access Policy 5 (IMR1_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR1 Read Access Policy 4 (IMR1_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR1 Read Access Policy 3 (IMR1_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR1 Read Access Policy 2 (IMR1_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR1 Read Access Policy 1 (IMR1_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR1 Read Access Policy 0 (IMR1_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR1 region, based on each agent's 6bit encoded SAI value.

44.3.31 IMR1 Write Access Policy (B_CR_BIMR1WAC_0_0_0_MCHBAR)—Offset 68A8h

This register, along with IMR1BASE, IMR1MASK and IMR1RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR1. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68A8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR1 Write Access Policy 63 (IMR1_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR1 Write Access Policy 62 (IMR1_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR1 Write Access Policy 61 (IMR1_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR1 Write Access Policy 60 (IMR1_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR1 Write Access Policy 59 (IMR1_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR1 Write Access Policy 58 (IMR1_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR1 Write Access Policy 57 (IMR1_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR1 Write Access Policy 56 (IMR1_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR1 Write Access Policy 55 (IMR1_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR1 Write Access Policy 54 (IMR1_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR1 Write Access Policy 53 (IMR1_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR1 Write Access Policy 52 (IMR1_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR1 Write Access Policy 51 (IMR1_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR1 Write Access Policy 50 (IMR1_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR1 Write Access Policy 49 (IMR1_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR1 Write Access Policy 48 (IMR1_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR1 Write Access Policy 47 (IMR1_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR1 Write Access Policy 46 (IMR1_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR1 Write Access Policy 45 (IMR1_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR1 Write Access Policy 44 (IMR1_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR1 Write Access Policy 43 (IMR1_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR1 Write Access Policy 42 (IMR1_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR1 Write Access Policy 41 (IMR1_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR1 Write Access Policy 40 (IMR1_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR1 Write Access Policy 39 (IMR1_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR1 Write Access Policy 38 (IMR1_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR1 Write Access Policy 37 (IMR1_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR1 Write Access Policy 36 (IMR1_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR1 Write Access Policy 35 (IMR1_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR1 Write Access Policy 34 (IMR1_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR1 Write Access Policy 33 (IMR1_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR1 Write Access Policy 32 (IMR1_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR1 Write Access Policy 31 (IMR1_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR1 Write Access Policy 30 (IMR1_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR1 Write Access Policy 29 (IMR1_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR1 Write Access Policy 28 (IMR1_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR1 Write Access Policy 27 (IMR1_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR1 Write Access Policy 26 (IMR1_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR1 Write Access Policy 25 (IMR1_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR1 Write Access Policy 24 (IMR1_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR1 Write Access Policy 23 (IMR1_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR1 Write Access Policy 22 (IMR1_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR1 Write Access Policy 21 (IMR1_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR1 Write Access Policy 20 (IMR1_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR1 Write Access Policy 19 (IMR1_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR1 Write Access Policy 18 (IMR1_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR1 Write Access Policy 17 (IMR1_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR1 Write Access Policy 16 (IMR1_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR1 Write Access Policy 15 (IMR1_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR1 Write Access Policy 14 (IMR1_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR1 Write Access Policy 13 (IMR1_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR1 Write Access Policy 12 (IMR1_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR1 Write Access Policy 11 (IMR1_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR1 Write Access Policy 10 (IMR1_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR1 Write Access Policy 9 (IMR1_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR1 Write Access Policy 8 (IMR1_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR1 Write Access Policy 7 (IMR1_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR1 Write Access Policy 6 (IMR1_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR1 Write Access Policy 5 (IMR1_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR1 Write Access Policy 4 (IMR1_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR1 Write Access Policy 3 (IMR1_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR1 Write Access Policy 2 (IMR1_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR1 Write Access Policy 1 (IMR1_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR1 Write Access Policy 0 (IMR1_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR1 region, based on each agent's 6bit encoded SAI value.

44.3.32 Base 0 IMR2 Base (B_CR_BIMR2BASE_0_0_0_MCHBAR)—Offset 68B0h

This register, along with IMR2MASK, IMR2RAC and IMR2WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR2RAC and IMR2WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 68B0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR2 Base (IMR2_BASE):** Specifies bits 38:10 of the start address of IMR2 region. IMR region size must be a strict poweroftwo, at least 1KB and naturally aligned to the size. These bits are compared with the result of the IMR2MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR2 defined region.

44.3.33 IMR2 Mask (B_CR_BIMR2MASK_0_0_0_MCHBAR)—Offset 68B4h

This register, along with IMR2BASE, IMR2RAC, and IMR2WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR2RAC and IMR2WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 68B4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestpr depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR2 Mask (IMR2_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR2BASE[28:0] value. A match indicates that the incoming address falls within the IMR2 region.

44.3.34 IMR2 Control Policy (B_CR_BIMR2CP_0_0_0_MCHBAR)—Offset 68B8h

This register controls the access policy to the Read Access Policy BIMR2RAC, Write Access Policy BIMR2WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68B8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR2 Control Policy (IMR2_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR2RAC, BIMR2WAC and BIMR2CP registers, based on the value from each agent's 6bit SAI field.

44.3.35 IMR2 Read Access Policy (B_CR_BIMR2RAC_0_0_0_MCHBAR)—Offset 68C0h

This register, along with IMR2BASE, IMR2MASK and IMR2WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR2. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68C0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR2 Read Access Policy 63 (IMR2_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR2 Read Access Policy 62 (IMR2_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR2 Read Access Policy 61 (IMR2_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR2 Read Access Policy 60 (IMR2_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR2 Read Access Policy 59 (IMR2_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR2 Read Access Policy 58 (IMR2_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR2 Read Access Policy 57 (IMR2_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR2 Read Access Policy 56 (IMR2_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR2 Read Access Policy 55 (IMR2_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR2 Read Access Policy 54 (IMR2_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR2 Read Access Policy 53 (IMR2_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR2 Read Access Policy 52 (IMR2_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR2 Read Access Policy 51 (IMR2_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR2 Read Access Policy 50 (IMR2_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR2 Read Access Policy 49 (IMR2_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR2 Read Access Policy 48 (IMR2_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR2 Read Access Policy 47 (IMR2_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR2 Read Access Policy 46 (IMR2_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR2 Read Access Policy 45 (IMR2_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR2 Read Access Policy 44 (IMR2_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR2 Read Access Policy 43 (IMR2_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR2 Read Access Policy 42 (IMR2_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR2 Read Access Policy 41 (IMR2_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR2 Read Access Policy 40 (IMR2_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR2 Read Access Policy 39 (IMR2_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR2 Read Access Policy 38 (IMR2_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR2 Read Access Policy 37 (IMR2_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR2 Read Access Policy 36 (IMR2_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR2 Read Access Policy 35 (IMR2_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR2 Read Access Policy 34 (IMR2_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR2 Read Access Policy 33 (IMR2_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR2 Read Access Policy 32 (IMR2_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR2 Read Access Policy 31 (IMR2_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR2 Read Access Policy 30 (IMR2_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR2 Read Access Policy 29 (IMR2_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR2 Read Access Policy 28 (IMR2_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR2 Read Access Policy 27 (IMR2_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR2 Read Access Policy 26 (IMR2_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR2 Read Access Policy 25 (IMR2_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR2 Read Access Policy 24 (IMR2_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR2 Read Access Policy 23 (IMR2_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR2 Read Access Policy 22 (IMR2_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR2 Read Access Policy 21 (IMR2_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR2 Read Access Policy 20 (IMR2_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR2 Read Access Policy 19 (IMR2_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR2 Read Access Policy 18 (IMR2_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR2 Read Access Policy 17 (IMR2_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR2 Read Access Policy 16 (IMR2_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR2 Read Access Policy 15 (IMR2_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR2 Read Access Policy 14 (IMR2_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR2 Read Access Policy 13 (IMR2_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR2 Read Access Policy 12 (IMR2_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR2 Read Access Policy 11 (IMR2_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR2 Read Access Policy 10 (IMR2_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR2 Read Access Policy 9 (IMR2_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR2 Read Access Policy 8 (IMR2_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR2 Read Access Policy 7 (IMR2_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR2 Read Access Policy 6 (IMR2_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR2 Read Access Policy 5 (IMR2_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR2 Read Access Policy 4 (IMR2_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR2 Read Access Policy 3 (IMR2_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR2 Read Access Policy 2 (IMR2_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR2 Read Access Policy 1 (IMR2_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR2 Read Access Policy 0 (IMR2_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR2 region, based on each agent's 6bit encoded SAI value.

44.3.36 IMR2 Write Access Policy (B_CR_BIMR2WAC_0_0_0_MCHBAR)—Offset 68C8h

This register, along with IMR2BASE, IMR2MASK and IMR2RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR2. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68C8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR2 Write Access Policy 63 (IMR2_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR2 Write Access Policy 62 (IMR2_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR2 Write Access Policy 61 (IMR2_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR2 Write Access Policy 60 (IMR2_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR2 Write Access Policy 59 (IMR2_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR2 Write Access Policy 58 (IMR2_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR2 Write Access Policy 57 (IMR2_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR2 Write Access Policy 56 (IMR2_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR2 Write Access Policy 55 (IMR2_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR2 Write Access Policy 54 (IMR2_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR2 Write Access Policy 53 (IMR2_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR2 Write Access Policy 52 (IMR2_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR2 Write Access Policy 51 (IMR2_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR2 Write Access Policy 50 (IMR2_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR2 Write Access Policy 49 (IMR2_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR2 Write Access Policy 48 (IMR2_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR2 Write Access Policy 47 (IMR2_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR2 Write Access Policy 46 (IMR2_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR2 Write Access Policy 45 (IMR2_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR2 Write Access Policy 44 (IMR2_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR2 Write Access Policy 43 (IMR2_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR2 Write Access Policy 42 (IMR2_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR2 Write Access Policy 41 (IMR2_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR2 Write Access Policy 40 (IMR2_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR2 Write Access Policy 39 (IMR2_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR2 Write Access Policy 38 (IMR2_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR2 Write Access Policy 37 (IMR2_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR2 Write Access Policy 36 (IMR2_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR2 Write Access Policy 35 (IMR2_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR2 Write Access Policy 34 (IMR2_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR2 Write Access Policy 33 (IMR2_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR2 Write Access Policy 32 (IMR2_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR2 Write Access Policy 31 (IMR2_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR2 Write Access Policy 30 (IMR2_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR2 Write Access Policy 29 (IMR2_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR2 Write Access Policy 28 (IMR2_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR2 Write Access Policy 27 (IMR2_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR2 Write Access Policy 26 (IMR2_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR2 Write Access Policy 25 (IMR2_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR2 Write Access Policy 24 (IMR2_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR2 Write Access Policy 23 (IMR2_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR2 Write Access Policy 22 (IMR2_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR2 Write Access Policy 21 (IMR2_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR2 Write Access Policy 20 (IMR2_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR2 Write Access Policy 19 (IMR2_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR2 Write Access Policy 18 (IMR2_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR2 Write Access Policy 17 (IMR2_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR2 Write Access Policy 16 (IMR2_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR2 Write Access Policy 15 (IMR2_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR2 Write Access Policy 14 (IMR2_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR2 Write Access Policy 13 (IMR2_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR2 Write Access Policy 12 (IMR2_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR2 Write Access Policy 11 (IMR2_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR2 Write Access Policy 10 (IMR2_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR2 Write Access Policy 9 (IMR2_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR2 Write Access Policy 8 (IMR2_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR2 Write Access Policy 7 (IMR2_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR2 Write Access Policy 6 (IMR2_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR2 Write Access Policy 5 (IMR2_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR2 Write Access Policy 4 (IMR2_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR2 Write Access Policy 3 (IMR2_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR2 Write Access Policy 2 (IMR2_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR2 Write Access Policy 1 (IMR2_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR2 Write Access Policy 0 (IMR2_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR2 region, based on each agent's 6bit encoded SAI value.

44.3.37 IMR3 Base (B_CR_BIMR3BASE_0_0_0_MCHBAR)—Offset 68D0h

This register, along with IMR3MASK, IMR3RAC and IMR3WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR3RAC and IMR3WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 68D0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR3 Base (IMR3_BASE):** Specifies bits 38:10 of the start address of IMR3 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR3MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR3 defined region.

44.3.38 IMR3 Mask (B_CR_BIMR3MASK_0_0_0_MCHBAR)—Offset 68D4h

This register, along with IMR3BASE, IMR3RAC and IMR3WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR3RAC and IMR3WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 68D4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR3 Mask (IMR3_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR3BASE[28:0] value. A match indicates that the incoming address falls within the IMR3 region.

44.3.39 IMR3 Control Policy (B_CR_BIMR3CP_0_0_0_MCHBAR)—Offset 68D8h

This register controls the access policy to the Read Access Policy BIMR3RAC, the Write Access Policy BIMR3WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68D8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR3 Control Policy (IMR3_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR3RAC, BIMR3WAC and BIMR3CP registers, based on the value from each agent's 6bit SAI field.

44.3.40 IMR3 Read Access Policy (B_CR_BIMR3RAC_0_0_0_MCHBAR)—Offset 68E0h

This register, along with IMR3BASE, IMR3MASK and IMR3WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR3. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68E0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR3 Read Access Policy 63 (IMR3_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR3 Read Access Policy 62 (IMR3_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR3 Read Access Policy 61 (IMR3_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR3 Read Access Policy 60 (IMR3_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR3 Read Access Policy 59 (IMR3_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR3 Read Access Policy 58 (IMR3_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR3 Read Access Policy 57 (IMR3_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR3 Read Access Policy 56 (IMR3_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR3 Read Access Policy 55 (IMR3_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR3 Read Access Policy 54 (IMR3_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR3 Read Access Policy 53 (IMR3_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR3 Read Access Policy 52 (IMR3_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR3 Read Access Policy 51 (IMR3_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR3 Read Access Policy 50 (IMR3_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR3 Read Access Policy 49 (IMR3_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR3 Read Access Policy 48 (IMR3_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR3 Read Access Policy 47 (IMR3_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR3 Read Access Policy 46 (IMR3_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR3 Read Access Policy 45 (IMR3_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR3 Read Access Policy 44 (IMR3_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR3 Read Access Policy 43 (IMR3_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR3 Read Access Policy 42 (IMR3_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR3 Read Access Policy 41 (IMR3_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR3 Read Access Policy 40 (IMR3_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR3 Read Access Policy 39 (IMR3_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR3 Read Access Policy 38 (IMR3_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR3 Read Access Policy 37 (IMR3_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR3 Read Access Policy 36 (IMR3_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR3 Read Access Policy 35 (IMR3_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR3 Read Access Policy 34 (IMR3_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR3 Read Access Policy 33 (IMR3_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR3 Read Access Policy 32 (IMR3_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR3 Read Access Policy 31 (IMR3_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR3 Read Access Policy 30 (IMR3_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR3 Read Access Policy 29 (IMR3_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR3 Read Access Policy 28 (IMR3_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR3 Read Access Policy 27 (IMR3_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR3 Read Access Policy 26 (IMR3_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR3 Read Access Policy 25 (IMR3_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR3 Read Access Policy 24 (IMR3_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR3 Read Access Policy 23 (IMR3_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR3 Read Access Policy 22 (IMR3_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR3 Read Access Policy 21 (IMR3_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR3 Read Access Policy 20 (IMR3_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR3 Read Access Policy 19 (IMR3_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR3 Read Access Policy 18 (IMR3_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR3 Read Access Policy 17 (IMR3_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR3 Read Access Policy 16 (IMR3_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR3 Read Access Policy 15 (IMR3_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR3 Read Access Policy 14 (IMR3_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR3 Read Access Policy 13 (IMR3_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR3 Read Access Policy 12 (IMR3_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR3 Read Access Policy 11 (IMR3_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR3 Read Access Policy 10 (IMR3_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR3 Read Access Policy 9 (IMR3_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR3 Read Access Policy 8 (IMR3_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR3 Read Access Policy 7 (IMR3_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR3 Read Access Policy 6 (IMR3_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR3 Read Access Policy 5 (IMR3_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR3 Read Access Policy 4 (IMR3_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR3 Read Access Policy 3 (IMR3_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR3 Read Access Policy 2 (IMR3_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR3 Read Access Policy 1 (IMR3_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR3 Read Access Policy 0 (IMR3_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR3 region, based on each agent's 6bit encoded SAI value.

44.3.41 IMR3 Write Access Policy (B_CR_BIMR3WAC_0_0_0_MCHBAR)—Offset 68E8h

This register, along with IMR3BASE, IMR3MASK and IMR3RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR3. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68E8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR3 Write Access Policy 63 (IMR3_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR3 Write Access Policy 62 (IMR3_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR3 Write Access Policy 61 (IMR3_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR3 Write Access Policy 60 (IMR3_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR3 Write Access Policy 59 (IMR3_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR3 Write Access Policy 58 (IMR3_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR3 Write Access Policy 57 (IMR3_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR3 Write Access Policy 56 (IMR3_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR3 Write Access Policy 55 (IMR3_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR3 Write Access Policy 54 (IMR3_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR3 Write Access Policy 53 (IMR3_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR3 Write Access Policy 52 (IMR3_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR3 Write Access Policy 51 (IMR3_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR3 Write Access Policy 50 (IMR3_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR3 Write Access Policy 49 (IMR3_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR3 Write Access Policy 48 (IMR3_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR3 Write Access Policy 47 (IMR3_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR3 Write Access Policy 46 (IMR3_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR3 Write Access Policy 45 (IMR3_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR3 Write Access Policy 44 (IMR3_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR3 Write Access Policy 43 (IMR3_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR3 Write Access Policy 42 (IMR3_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR3 Write Access Policy 41 (IMR3_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR3 Write Access Policy 40 (IMR3_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR3 Write Access Policy 39 (IMR3_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR3 Write Access Policy 38 (IMR3_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR3 Write Access Policy 37 (IMR3_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR3 Write Access Policy 36 (IMR3_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR3 Write Access Policy 35 (IMR3_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR3 Write Access Policy 34 (IMR3_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR3 Write Access Policy 33 (IMR3_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR3 Write Access Policy 32 (IMR3_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR3 Write Access Policy 31 (IMR3_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR3 Write Access Policy 30 (IMR3_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR3 Write Access Policy 29 (IMR3_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR3 Write Access Policy 28 (IMR3_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR3 Write Access Policy 27 (IMR3_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR3 Write Access Policy 26 (IMR3_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR3 Write Access Policy 25 (IMR3_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR3 Write Access Policy 24 (IMR3_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR3 Write Access Policy 23 (IMR3_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR3 Write Access Policy 22 (IMR3_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR3 Write Access Policy 21 (IMR3_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR3 Write Access Policy 20 (IMR3_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR3 Write Access Policy 19 (IMR3_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR3 Write Access Policy 18 (IMR3_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR3 Write Access Policy 17 (IMR3_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR3 Write Access Policy 16 (IMR3_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR3 Write Access Policy 15 (IMR3_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR3 Write Access Policy 14 (IMR3_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR3 Write Access Policy 13 (IMR3_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR3 Write Access Policy 12 (IMR3_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR3 Write Access Policy 11 (IMR3_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR3 Write Access Policy 10 (IMR3_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR3 Write Access Policy 9 (IMR3_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR3 Write Access Policy 8 (IMR3_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR3 Write Access Policy 7 (IMR3_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR3 Write Access Policy 6 (IMR3_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR3 Write Access Policy 5 (IMR3_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR3 Write Access Policy 4 (IMR3_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR3 Write Access Policy 3 (IMR3_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR3 Write Access Policy 2 (IMR3_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR3 Write Access Policy 1 (IMR3_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR3 Write Access Policy 0 (IMR3_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR3 region, based on each agent's 6bit encoded SAI value.

44.3.42 IMR4 Base (B_CR_BIMR4BASE_0_0_0_MCHBAR)—Offset 68F0h

This register, along with IMR4MASK, IMR4RAC and IMR4WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR4RAC and IMR4WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 68F0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR4 Base (IMR4_BASE):** Specifies bits 38:10 of the start address of IMR4 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR4MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR4 defined region.

44.3.43 IMR4 Mask (B_CR_BIMR4MASK_0_0_0_MCHBAR)—Offset 68F4h

This register, along with IMR4BASE, IMR4RAC and IMR4WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR4RAC and IMR4WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 68F4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR4 Mask (IMR4_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR4BASE[28:0] value. A match indicates that the incoming address falls within the IMR4 region.

44.3.44 B-Unit IMR4 Control Policy (B_CR_BIMR4CP_0_0_0_MCHBAR)—Offset 68F8h

This register controls the access policy to the Read Access Policy BIMR4RAC, the Write Access Policy BIMR4WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 68F8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**B-Unit IMR4 Control Policy (IMR4_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR4RAC, BIMR4WAC and BIMR4CP registers, based on the value from each agent's 6bit SAI field.

44.3.45 IMR4 Read Access Policy (B_CR_BIMR4RAC_0_0_0_MCHBAR)—Offset 6900h

This register, along with IMR4BASE, IMR4MASK and IMR4WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR4. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6900h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR4 Read Access Policy 63 (IMR4_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR4 Read Access Policy 62 (IMR4_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR4 Read Access Policy 61 (IMR4_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR4 Read Access Policy 60 (IMR4_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR4 Read Access Policy 59 (IMR4_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR4 Read Access Policy 58 (IMR4_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR4 Read Access Policy 57 (IMR4_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR4 Read Access Policy 56 (IMR4_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR4 Read Access Policy 55 (IMR4_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR4 Read Access Policy 54 (IMR4_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR4 Read Access Policy 53 (IMR4_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR4 Read Access Policy 52 (IMR4_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR4 Read Access Policy 51 (IMR4_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR4 Read Access Policy 50 (IMR4_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR4 Read Access Policy 49 (IMR4_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR4 Read Access Policy 48 (IMR4_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR4 Read Access Policy 47 (IMR4_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR4 Read Access Policy 46 (IMR4_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR4 Read Access Policy 45 (IMR4_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR4 Read Access Policy 44 (IMR4_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR4 Read Access Policy 43 (IMR4_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR4 Read Access Policy 42 (IMR4_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR4 Read Access Policy 41 (IMR4_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR4 Read Access Policy 40 (IMR4_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR4 Read Access Policy 39 (IMR4_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR4 Read Access Policy 38 (IMR4_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR4 Read Access Policy 37 (IMR4_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR4 Read Access Policy 36 (IMR4_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR4 Read Access Policy 35 (IMR4_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR4 Read Access Policy 34 (IMR4_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR4 Read Access Policy 33 (IMR4_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR4 Read Access Policy 32 (IMR4_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR4 Read Access Policy 31 (IMR4_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR4 Read Access Policy 30 (IMR4_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR4 Read Access Policy 29 (IMR4_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR4 Read Access Policy 28 (IMR4_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR4 Read Access Policy 27 (IMR4_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR4 Read Access Policy 26 (IMR4_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR4 Read Access Policy 25 (IMR4_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR4 Read Access Policy 24 (IMR4_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR4 Read Access Policy 23 (IMR4_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR4 Read Access Policy 22 (IMR4_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR4 Read Access Policy 21 (IMR4_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR4 Read Access Policy 20 (IMR4_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR4 Read Access Policy 19 (IMR4_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR4 Read Access Policy 18 (IMR4_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR4 Read Access Policy 17 (IMR4_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR4 Read Access Policy 16 (IMR4_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR4 Read Access Policy 15 (IMR4_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR4 Read Access Policy 14 (IMR4_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR4 Read Access Policy 13 (IMR4_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR4 Read Access Policy 12 (IMR4_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR4 Read Access Policy 11 (IMR4_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR4 Read Access Policy 10 (IMR4_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR4 Read Access Policy 9 (IMR4_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR4 Read Access Policy 8 (IMR4_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR4 Read Access Policy 7 (IMR4_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR4 Read Access Policy 6 (IMR4_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR4 Read Access Policy 5 (IMR4_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR4 Read Access Policy 4 (IMR4_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR4 Read Access Policy 3 (IMR4_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR4 Read Access Policy 2 (IMR4_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR4 Read Access Policy 1 (IMR4_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR4 Read Access Policy 0 (IMR4_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR4 region, based on each agent's 6bit encoded SAI value.

44.3.46 IMR4 Write Access Policy (B_CR_BIMR4WAC_0_0_0_MCHBAR)—Offset 6908h

This register, along with IMR4BASE, IMR4MASK and IMR4RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with a SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR4. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6908h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR4_WRITE_POL_63:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR4_WRITE_POL_62:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR4_WRITE_POL_61:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR4_WRITE_POL_60:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR4_WRITE_POL_59:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR4_WRITE_POL_58:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR4_WRITE_POL_57:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR4_WRITE_POL_56:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR4_WRITE_POL_55:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR4_WRITE_POL_54:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR4_WRITE_POL_53:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR4_WRITE_POL_52:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR4_WRITE_POL_51:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR4_WRITE_POL_50:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR4_WRITE_POL_49:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR4_WRITE_POL_48:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR4_WRITE_POL_47:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR4_WRITE_POL_46:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR4_WRITE_POL_45:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR4_WRITE_POL_44:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR4_WRITE_POL_43:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR4_WRITE_POL_42:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR4_WRITE_POL_41:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR4_WRITE_POL_40:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR4_WRITE_POL_39:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR4_WRITE_POL_38:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR4_WRITE_POL_37:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR4_WRITE_POL_36:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR4_WRITE_POL_35:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR4_WRITE_POL_34:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR4_WRITE_POL_33:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR4_WRITE_POL_32:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR4_WRITE_POL_31:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR4_WRITE_POL_30:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR4_WRITE_POL_29:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR4_WRITE_POL_28:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR4_WRITE_POL_27:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR4_WRITE_POL_26:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR4_WRITE_POL_25:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR4_WRITE_POL_24:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR4_WRITE_POL_23:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR4_WRITE_POL_22:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR4_WRITE_POL_21:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR4_WRITE_POL_20:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR4_WRITE_POL_19:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR4_WRITE_POL_18:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR4_WRITE_POL_17:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR4_WRITE_POL_16:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR4_WRITE_POL_15:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR4_WRITE_POL_14:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR4_WRITE_POL_13:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR4_WRITE_POL_12:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR4_WRITE_POL_11:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR4_WRITE_POL_10:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR4_WRITE_POL_9:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR4_WRITE_POL_8:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR4_WRITE_POL_7:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR4_WRITE_POL_6:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR4_WRITE_POL_5:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR4_WRITE_POL_4:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR4_WRITE_POL_3:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR4_WRITE_POL_2:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR4_WRITE_POL_1:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR4_WRITE_POL_0:** B-Unit IMR4 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR4 region, based on each agent's 6bit encoded SAI value.

44.3.47 IMR5 Base (B_CR_BIMR5BASE_0_0_0_MCHBAR)—Offset 6910h

This register, along with IMR5MASK, IMR5RAC and IMR5WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR5RAC and IMR5WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6910h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR5 Base (IMR5_BASE):** Specifies bits 38:10 of the start address of IMR5 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR5MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR5 defined region.

44.3.48 IMR5 Mask (B_CR_BIMR5MASK_0_0_0_MCHBAR)—Offset 6914h

This register, along with IMR5BASE, IMR5RAC and IMR5WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR5RAC and IMR5WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6914h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR5 Mask (IMR5_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR5BASE[28:0] value. A match indicates that the incoming address falls within the IMR5 region.

44.3.49 IMR5 Control Policy (B_CR_BIMR5CP_0_0_0_MCHBAR)—Offset 6918h

This register controls the access policy to the Read Access Policy BIMR5RAC, the Write Access Policy BIMR5WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6918h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR5 Control Policy (IMR5_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR5RAC, BIMR5WAC and BIMR5CP registers, based on the value from each agent's 6bit SAI field.

44.3.50 IMR5 Read Access Policy (B_CR_BIMR5RAC_0_0_0_MCHBAR)—Offset 6920h

This register, along with IMR5BASE, IMR5MASK and IMR5WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR5. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6920h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR5 Read Access Policy 63 (IMR5_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR5 Read Access Policy 62 (IMR5_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR5 Read Access Policy 61 (IMR5_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR5 Read Access Policy 60 (IMR5_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR5 Read Access Policy 59 (IMR5_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR5 Read Access Policy 58 (IMR5_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR5 Read Access Policy 57 (IMR5_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR5 Read Access Policy 56 (IMR5_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR5 Read Access Policy 55 (IMR5_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR5 Read Access Policy 54 (IMR5_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR5 Read Access Policy 53 (IMR5_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR5 Read Access Policy 52 (IMR5_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR5 Read Access Policy 51 (IMR5_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR5 Read Access Policy 50 (IMR5_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR5 Read Access Policy 49 (IMR5_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR5 Read Access Policy 48 (IMR5_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR5 Read Access Policy 47 (IMR5_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR5 Read Access Policy 46 (IMR5_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR5 Read Access Policy 45 (IMR5_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR5 Read Access Policy 44 (IMR5_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR5 Read Access Policy 43 (IMR5_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR5 Read Access Policy 42 (IMR5_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR5 Read Access Policy 41 (IMR5_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR5 Read Access Policy 40 (IMR5_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR5 Read Access Policy 39 (IMR5_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR5 Read Access Policy 38 (IMR5_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR5 Read Access Policy 37 (IMR5_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR5 Read Access Policy 36 (IMR5_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR5 Read Access Policy 35 (IMR5_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR5 Read Access Policy 34 (IMR5_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR5 Read Access Policy 33 (IMR5_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR5 Read Access Policy 32 (IMR5_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR5 Read Access Policy 31 (IMR5_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR5 Read Access Policy 30 (IMR5_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR5 Read Access Policy 29 (IMR5_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR5 Read Access Policy 28 (IMR5_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR5 Read Access Policy 27 (IMR5_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR5 Read Access Policy 26 (IMR5_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR5 Read Access Policy 25 (IMR5_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR5 Read Access Policy 24 (IMR5_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR5 Read Access Policy 23 (IMR5_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR5 Read Access Policy 22 (IMR5_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR5 Read Access Policy 21 (IMR5_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR5 Read Access Policy 20 (IMR5_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR5 Read Access Policy 19 (IMR5_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR5 Read Access Policy 18 (IMR5_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR5 Read Access Policy 17 (IMR5_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR5 Read Access Policy 16 (IMR5_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR5 Read Access Policy 15 (IMR5_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR5 Read Access Policy 14 (IMR5_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR5 Read Access Policy 13 (IMR5_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR5 Read Access Policy 12 (IMR5_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR5 Read Access Policy 11 (IMR5_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR5 Read Access Policy 10 (IMR5_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR5 Read Access Policy 9 (IMR5_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR5 Read Access Policy 8 (IMR5_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR5 Read Access Policy 7 (IMR5_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR5 Read Access Policy 6 (IMR5_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR5 Read Access Policy 5 (IMR5_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR5 Read Access Policy 4 (IMR5_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR5 Read Access Policy 3 (IMR5_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR5 Read Access Policy 2 (IMR5_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR5 Read Access Policy 1 (IMR5_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR5 Read Access Policy 0 (IMR5_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR5 region, based on each agent's 6bit encoded SAI value.

44.3.51 IMR5 Write Access Policy (B_CR_BIMR5WAC_0_0_0_MCHBAR)—Offset 6928h

This register, along with IMR5BASE, IMR5MASK and IMR5RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR5. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6928h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR5 Write Access Policy 63 (IMR5_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR5 Write Access Policy 62 (IMR5_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR5 Write Access Policy 61 (IMR5_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR5 Write Access Policy 60 (IMR5_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR5 Write Access Policy 59 (IMR5_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR5 Write Access Policy 58 (IMR5_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR5 Write Access Policy 57 (IMR5_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR5 Write Access Policy 56 (IMR5_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR5 Write Access Policy 55 (IMR5_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR5 Write Access Policy 54 (IMR5_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR5 Write Access Policy 53 (IMR5_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR5 Write Access Policy 52 (IMR5_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR5 Write Access Policy 51 (IMR5_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR5 Write Access Policy 50 (IMR5_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR5 Write Access Policy 49 (IMR5_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR5 Write Access Policy 48 (IMR5_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR5 Write Access Policy 47 (IMR5_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR5 Write Access Policy 46 (IMR5_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR5 Write Access Policy 45 (IMR5_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR5 Write Access Policy 44 (IMR5_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR5 Write Access Policy 43 (IMR5_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR5 Write Access Policy 42 (IMR5_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR5 Write Access Policy 41 (IMR5_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR5 Write Access Policy 40 (IMR5_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR5 Write Access Policy 39 (IMR5_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR5 Write Access Policy 38 (IMR5_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR5 Write Access Policy 37 (IMR5_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR5 Write Access Policy 36 (IMR5_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR5 Write Access Policy 35 (IMR5_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR5 Write Access Policy 34 (IMR5_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR5 Write Access Policy 33 (IMR5_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR5 Write Access Policy 32 (IMR5_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR5 Write Access Policy 31 (IMR5_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR5 Write Access Policy 30 (IMR5_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR5 Write Access Policy 29 (IMR5_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR5 Write Access Policy 28 (IMR5_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR5 Write Access Policy 27 (IMR5_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR5 Write Access Policy 26 (IMR5_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR5 Write Access Policy 25 (IMR5_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR5 Write Access Policy 24 (IMR5_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR5 Write Access Policy 23 (IMR5_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR5 Write Access Policy 22 (IMR5_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR5 Write Access Policy 21 (IMR5_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR5 Write Access Policy 20 (IMR5_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR5 Write Access Policy 19 (IMR5_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR5 Write Access Policy 18 (IMR5_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR5 Write Access Policy 17 (IMR5_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR5 Write Access Policy 16 (IMR5_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR5 Write Access Policy 15 (IMR5_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR5 Write Access Policy 14 (IMR5_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR5 Write Access Policy 13 (IMR5_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR5 Write Access Policy 12 (IMR5_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR5 Write Access Policy 11 (IMR5_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR5 Write Access Policy 10 (IMR5_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR5 Write Access Policy 9 (IMR5_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR5 Write Access Policy 8 (IMR5_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR5 Write Access Policy 7 (IMR5_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR5 Write Access Policy 6 (IMR5_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR5 Write Access Policy 5 (IMR5_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR5 Write Access Policy 4 (IMR5_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR5 Write Access Policy 3 (IMR5_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR5 Write Access Policy 2 (IMR5_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR5 Write Access Policy 1 (IMR5_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR5 Write Access Policy 0 (IMR5_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR5 region, based on each agent's 6bit encoded SAI value.

44.3.52 IMR6 Base (B_CR_BIMR6BASE_0_0_0_MCHBAR)—Offset 6930h

This register, along with IMR6MASK, IMR6RAC and IMR6WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR6RAC and IMR6WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6930h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR6 Base (IMR6_BASE):** Specifies bits 38:10 of the start address of IMR6 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR6MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR6 defined region.

44.3.53 IMR6 Mask (B_CR_BIMR6MASK_0_0_0_MCHBAR)—Offset 6934h

This register, along with IMR6BASE, IMR6RAC and IMR6WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR6RAC and IMR6WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6934h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit WB Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit WB Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR6 Mask (IMR6_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR6BASE[28:0] value. A match indicates that the incoming address falls within the IMR6 region.

44.3.54 IMR6 Control Policy (B_CR_BIMR6CP_0_0_0_MCHBAR)—Offset 6938h

This register controls the access policy to the Read Access Policy BIMR6RAC, the Write Access Policy BIMR6WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6938h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR6 Control Policy (IMR6_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR6RAC, BIMR6WAC, BIMR6CP registers, based on the value from each agent's 6bit SAI field.

44.3.55 IMR6 Read Access Policy (B_CR_BIMR6RAC_0_0_0_MCHBAR)—Offset 6940h

This register, along with IMR6BASE, IMR6MASK and IMR6WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR6. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6940h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR6 Read Access Policy 63 (IMR6_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR6 Read Access Policy 62 (IMR6_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR6 Read Access Policy 61 (IMR6_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR6 Read Access Policy 60 (IMR6_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR6 Read Access Policy 59 (IMR6_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR6 Read Access Policy 58 (IMR6_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR6 Read Access Policy 57 (IMR6_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR6 Read Access Policy 56 (IMR6_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR6 Read Access Policy 55 (IMR6_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR6 Read Access Policy 54 (IMR6_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR6 Read Access Policy 53 (IMR6_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR6 Read Access Policy 52 (IMR6_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR6 Read Access Policy 51 (IMR6_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR6 Read Access Policy 50 (IMR6_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR6 Read Access Policy 49 (IMR6_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR6 Read Access Policy 48 (IMR6_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR6 Read Access Policy 47 (IMR6_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR6 Read Access Policy 46 (IMR6_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR6 Read Access Policy 45 (IMR6_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR6 Read Access Policy 44 (IMR6_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR6 Read Access Policy 43 (IMR6_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR6 Read Access Policy 42 (IMR6_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR6 Read Access Policy 41 (IMR6_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR6 Read Access Policy 40 (IMR6_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR6 Read Access Policy 39 (IMR6_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR6 Read Access Policy 38 (IMR6_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR6 Read Access Policy 37 (IMR6_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR6 Read Access Policy 36 (IMR6_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR6 Read Access Policy 35 (IMR6_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR6 Read Access Policy 34 (IMR6_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR6 Read Access Policy 33 (IMR6_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR6 Read Access Policy 32 (IMR6_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR6 Read Access Policy 31 (IMR6_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR6 Read Access Policy 30 (IMR6_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR6 Read Access Policy 29 (IMR6_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR6 Read Access Policy 28 (IMR6_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR6 Read Access Policy 27 (IMR6_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR6 Read Access Policy 26 (IMR6_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR6 Read Access Policy 25 (IMR6_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR6 Read Access Policy 24 (IMR6_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR6 Read Access Policy 23 (IMR6_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR6 Read Access Policy 22 (IMR6_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR6 Read Access Policy 21 (IMR6_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR6 Read Access Policy 20 (IMR6_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR6 Read Access Policy 19 (IMR6_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR6 Read Access Policy 18 (IMR6_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR6 Read Access Policy 17 (IMR6_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR6 Read Access Policy 16 (IMR6_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR6 Read Access Policy 15 (IMR6_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR6 Read Access Policy 14 (IMR6_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR6 Read Access Policy 13 (IMR6_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR6 Read Access Policy 12 (IMR6_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR6 Read Access Policy 11 (IMR6_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR6 Read Access Policy 10 (IMR6_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR6 Read Access Policy 9 (IMR6_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR6 Read Access Policy 8 (IMR6_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR6 Read Access Policy 7 (IMR6_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR6 Read Access Policy 6 (IMR6_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR6 Read Access Policy 5 (IMR6_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR6 Read Access Policy 4 (IMR6_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR6 Read Access Policy 3 (IMR6_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR6 Read Access Policy 2 (IMR6_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR6 Read Access Policy 1 (IMR6_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR6 Read Access Policy 0 (IMR6_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR6 region, based on each agent's 6bit encoded SAI value.

44.3.56 IMR6 Write Access Policy (B_CR_BIMR6WAC_0_0_0_MCHBAR)—Offset 6948h

This register, along with IMR6BASE, IMR6MASK and IMR6RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with a SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR6. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6948h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR6 Write Access Policy 63 (IMR6_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR6 Write Access Policy 62 (IMR6_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR6 Write Access Policy 61 (IMR6_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR6 Write Access Policy 60 (IMR6_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR6 Write Access Policy 59 (IMR6_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR6 Write Access Policy 58 (IMR6_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR6 Write Access Policy 57 (IMR6_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR6 Write Access Policy 56 (IMR6_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR6 Write Access Policy 55 (IMR6_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR6 Write Access Policy 54 (IMR6_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR6 Write Access Policy 53 (IMR6_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR6 Write Access Policy 52 (IMR6_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR6 Write Access Policy 51 (IMR6_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR6 Write Access Policy 50 (IMR6_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR6 Write Access Policy 49 (IMR6_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR6 Write Access Policy 48 (IMR6_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR6 Write Access Policy 47 (IMR6_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR6 Write Access Policy 46 (IMR6_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR6 Write Access Policy 45 (IMR6_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR6 Write Access Policy 44 (IMR6_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR6 Write Access Policy 43 (IMR6_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR6 Write Access Policy 42 (IMR6_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR6 Write Access Policy 41 (IMR6_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR6 Write Access Policy 40 (IMR6_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR6 Write Access Policy 39 (IMR6_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR6 Write Access Policy 38 (IMR6_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR6 Write Access Policy 37 (IMR6_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR6 Write Access Policy 36 (IMR6_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR6 Write Access Policy 35 (IMR6_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR6 Write Access Policy 34 (IMR6_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR6 Write Access Policy 33 (IMR6_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR6 Write Access Policy 32 (IMR6_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR6 Write Access Policy 31 (IMR6_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR6 Write Access Policy 30 (IMR6_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR6 Write Access Policy 29 (IMR6_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR6 Write Access Policy 28 (IMR6_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR6 Write Access Policy 27 (IMR6_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR6 Write Access Policy 26 (IMR6_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR6 Write Access Policy 25 (IMR6_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR6 Write Access Policy 24 (IMR6_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR6 Write Access Policy 23 (IMR6_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR6 Write Access Policy 22 (IMR6_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR6 Write Access Policy 21 (IMR6_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR6 Write Access Policy 20 (IMR6_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR6 Write Access Policy 19 (IMR6_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR6 Write Access Policy 18 (IMR6_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR6 Write Access Policy 17 (IMR6_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR6 Write Access Policy 16 (IMR6_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR6 Write Access Policy 15 (IMR6_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR6 Write Access Policy 14 (IMR6_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR6 Write Access Policy 13 (IMR6_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR6 Write Access Policy 12 (IMR6_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR6 Write Access Policy 11 (IMR6_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR6 Write Access Policy 10 (IMR6_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR6 Write Access Policy 9 (IMR6_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR6 Write Access Policy 8 (IMR6_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR6 Write Access Policy 7 (IMR6_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR6 Write Access Policy 6 (IMR6_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR6 Write Access Policy 5 (IMR6_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR6 Write Access Policy 4 (IMR6_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR6 Write Access Policy 3 (IMR6_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR6 Write Access Policy 2 (IMR6_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR6 Write Access Policy 1 (IMR6_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR6 Write Access Policy 0 (IMR6_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR6 region, based on each agent's 6bit encoded SAI value.

44.3.57 IMR7 Base (B_CR_BIMR7BASE_0_0_0_MCHBAR)—Offset 6950h

This register, along with IMR7MASK, IMR7RAC and IMR7WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR7RAC and IMR7WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6950h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR7 Base (IMR7_BASE):** Specifies bits 38:10 of the start address of IMR7 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR7MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR7 defined region.

44.3.58 IMR7 Mask (B_CR_BIMR7MASK_0_0_0_MCHBAR)—Offset 6954h

This register, along with IMR7BASE, IMR7RAC and IMR7WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR7RAC and IMR7WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6954h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit WB Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit WB Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR7 Mask (IMR7_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR7BASE[28:0] value. A match indicates that the incoming address falls within the IMR7 region.

44.3.59 IMR7 Control Policy (B_CR_BIMR7CP_0_0_0_MCHBAR)—Offset 6958h

This register controls the access policy to the Read Access Policy BIMR7RAC, the Write Access Policy BIMR7WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6958h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR7 Control Policy (IMR7_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR7RAC, BIMR7WAC and BIMR7CP registers, based on the value from each agent's 6bit SAI field.

44.3.60 IMR7 Read Access Policy (B_CR_BIMR7RAC_0_0_0_MCHBAR)—Offset 6960h

This register, along with IMR7BASE, IMR7MASK and IMR7WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR7. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6960h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR7 Read Access Policy 63 (IMR7_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR7 Read Access Policy 62 (IMR7_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR7 Read Access Policy 61 (IMR7_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR7 Read Access Policy 60 (IMR7_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR7 Read Access Policy 59 (IMR7_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR7 Read Access Policy 58 (IMR7_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR7 Read Access Policy 57 (IMR7_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR7 Read Access Policy 56 (IMR7_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR7 Read Access Policy 55 (IMR7_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR7 Read Access Policy 54 (IMR7_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR7 Read Access Policy 53 (IMR7_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR7 Read Access Policy 52 (IMR7_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR7 Read Access Policy 51 (IMR7_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR7 Read Access Policy 50 (IMR7_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR7 Read Access Policy 49 (IMR7_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR7 Read Access Policy 48 (IMR7_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR7 Read Access Policy 47 (IMR7_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR7 Read Access Policy 46 (IMR7_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR7 Read Access Policy 45 (IMR7_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR7 Read Access Policy 44 (IMR7_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR7 Read Access Policy 43 (IMR7_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR7 Read Access Policy 42 (IMR7_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR7 Read Access Policy 41 (IMR7_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR7 Read Access Policy 40 (IMR7_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR7 Read Access Policy 39 (IMR7_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR7 Read Access Policy 38 (IMR7_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR7 Read Access Policy 37 (IMR7_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR7 Read Access Policy 36 (IMR7_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR7 Read Access Policy 35 (IMR7_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR7 Read Access Policy 34 (IMR7_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR7 Read Access Policy 33 (IMR7_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR7 Read Access Policy 32 (IMR7_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR7 Read Access Policy 31 (IMR7_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR7 Read Access Policy 30 (IMR7_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR7 Read Access Policy 29 (IMR7_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR7 Read Access Policy 28 (IMR7_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR7 Read Access Policy 27 (IMR7_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR7 Read Access Policy 26 (IMR7_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR7 Read Access Policy 25 (IMR7_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR7 Read Access Policy 24 (IMR7_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR7 Read Access Policy 23 (IMR7_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR7 Read Access Policy 22 (IMR7_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR7 Read Access Policy 21 (IMR7_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR7 Read Access Policy 20 (IMR7_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR7 Read Access Policy 19 (IMR7_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR7 Read Access Policy 18 (IMR7_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR7 Read Access Policy 17 (IMR7_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR7 Read Access Policy 16 (IMR7_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR7 Read Access Policy 15 (IMR7_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR7 Read Access Policy 14 (IMR7_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR7 Read Access Policy 13 (IMR7_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR7 Read Access Policy 12 (IMR7_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR7 Read Access Policy 11 (IMR7_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR7 Read Access Policy 10 (IMR7_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR7 Read Access Policy 9 (IMR7_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR7 Read Access Policy 8 (IMR7_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR7 Read Access Policy 7 (IMR7_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR7 Read Access Policy 6 (IMR7_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR7 Read Access Policy 5 (IMR7_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR7 Read Access Policy 4 (IMR7_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR7 Read Access Policy 3 (IMR7_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR7 Read Access Policy 2 (IMR7_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR7 Read Access Policy 1 (IMR7_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR7 Read Access Policy 0 (IMR7_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR7 region, based on each agent's 6bit encoded SAI value.

44.3.61 IMR7 Write Access Policy (B_CR_BIMR7WAC_0_0_0_MCHBAR)—Offset 6968h

This register, along with IMR7BASE, IMR7MASK and IMR7RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR7. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6968h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR7 Write Access Policy 63 (IMR7_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR7 Write Access Policy 62 (IMR7_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR7 Write Access Policy 61 (IMR7_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR7 Write Access Policy 60 (IMR7_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR7 Write Access Policy 59 (IMR7_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR7 Write Access Policy 58 (IMR7_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR7 Write Access Policy 57 (IMR7_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR7 Write Access Policy 56 (IMR7_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR7 Write Access Policy 55 (IMR7_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR7 Write Access Policy 54 (IMR7_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR7 Write Access Policy 53 (IMR7_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR7 Write Access Policy 52 (IMR7_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR7 Write Access Policy 51 (IMR7_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR7 Write Access Policy 50 (IMR7_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR7 Write Access Policy 49 (IMR7_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR7 Write Access Policy 48 (IMR7_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR7 Write Access Policy 47 (IMR7_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR7 Write Access Policy 46 (IMR7_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR7 Write Access Policy 45 (IMR7_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR7 Write Access Policy 44 (IMR7_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR7 Write Access Policy 43 (IMR7_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR7 Write Access Policy 42 (IMR7_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR7 Write Access Policy 41 (IMR7_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR7 Write Access Policy 40 (IMR7_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR7 Write Access Policy 39 (IMR7_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR7 Write Access Policy 38 (IMR7_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR7 Write Access Policy 37 (IMR7_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR7 Write Access Policy 36 (IMR7_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR7 Write Access Policy 35 (IMR7_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR7 Write Access Policy 34 (IMR7_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR7 Write Access Policy 33 (IMR7_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR7 Write Access Policy 32 (IMR7_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR7 Write Access Policy 31 (IMR7_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR7 Write Access Policy 30 (IMR7_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR7 Write Access Policy 29 (IMR7_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR7 Write Access Policy 28 (IMR7_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR7 Write Access Policy 27 (IMR7_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR7 Write Access Policy 26 (IMR7_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR7 Write Access Policy 25 (IMR7_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR7 Write Access Policy 24 (IMR7_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR7 Write Access Policy 23 (IMR7_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR7 Write Access Policy 22 (IMR7_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR7 Write Access Policy 21 (IMR7_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR7 Write Access Policy 20 (IMR7_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR7 Write Access Policy 19 (IMR7_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR7 Write Access Policy 18 (IMR7_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR7 Write Access Policy 17 (IMR7_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR7 Write Access Policy 16 (IMR7_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR7 Write Access Policy 15 (IMR7_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR7 Write Access Policy 14 (IMR7_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR7 Write Access Policy 13 (IMR7_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR7 Write Access Policy 12 (IMR7_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR7 Write Access Policy 11 (IMR7_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR7 Write Access Policy 10 (IMR7_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR7 Write Access Policy 9 (IMR7_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR7 Write Access Policy 8 (IMR7_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR7 Write Access Policy 7 (IMR7_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR7 Write Access Policy 6 (IMR7_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR7 Write Access Policy 5 (IMR7_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR7 Write Access Policy 4 (IMR7_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR7 Write Access Policy 3 (IMR7_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR7 Write Access Policy 2 (IMR7_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR7 Write Access Policy 1 (IMR7_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR7 Write Access Policy 0 (IMR7_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR7 region, based on each agent's 6bit encoded SAI value.

44.3.62 IMR8 Base (B_CR_BIMR8BASE_0_0_0_MCHBAR)—Offset 6970h

This register, along with IMR8MASK, IMR8RAC and IMR8WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR8RAC and IMR8WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6970h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR8 Base (IMR8_BASE):** Specifies bits 38:10 of the start address of IMR8 region. IMR region size must be a strict poweroftwo at least 1KB and naturally aligned to the size. These bits are compared with the result of the IMR8MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR8 defined region.

44.3.63 IMR8 Mask (B_CR_BIMR8MASK_0_0_0_MCHBAR)—Offset 6974h

This register, along with IMR8BASE, IMR8RAC and IMR8WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR8RAC and IMR8WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6974h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR8 Mask (IMR8_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR8BASE[28:0] value. A match indicates that the incoming address falls within the IMR8 region.

44.3.64 IMR8 Control Policy (B_CR_BIMR8CP_0_0_0_MCHBAR)—Offset 6978h

This register controls the access policy to the Read Access Policy BIMR8RAC, the Write Access Policy BIMR8WAC, and, self-referentially to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6978h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR8 Control Policy (IMR8_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR8RAC, BIMR8WAC and BIMR8CP registers, based on the value from each agent's 6bit SAI field.

44.3.65 IMR8 Read Access Policy (B_CR_BIMR8RAC_0_0_0_MCHBAR)—Offset 6980h

This register, along with IMR8BASE, IMR8MASK and IMR8WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR8. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6980h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR8 Read Access Policy 63 (IMR8_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR8 Read Access Policy 62 (IMR8_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR8 Read Access Policy 61 (IMR8_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR8 Read Access Policy 60 (IMR8_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR8 Read Access Policy 59 (IMR8_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR8 Read Access Policy 58 (IMR8_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR8 Read Access Policy 57 (IMR8_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR8 Read Access Policy 56 (IMR8_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR8 Read Access Policy 55 (IMR8_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR8 Read Access Policy 54 (IMR8_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR8 Read Access Policy 53 (IMR8_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR8 Read Access Policy 52 (IMR8_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR8 Read Access Policy 51 (IMR8_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR8 Read Access Policy 50 (IMR8_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR8 Read Access Policy 49 (IMR8_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR8 Read Access Policy 48 (IMR8_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR8 Read Access Policy 47 (IMR8_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR8 Read Access Policy 46 (IMR8_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR8 Read Access Policy 45 (IMR8_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR8 Read Access Policy 44 (IMR8_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR8 Read Access Policy 43 (IMR8_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR8 Read Access Policy 42 (IMR8_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR8 Read Access Policy 41 (IMR8_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR8 Read Access Policy 40 (IMR8_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR8 Read Access Policy 39 (IMR8_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR8 Read Access Policy 38 (IMR8_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR8 Read Access Policy 37 (IMR8_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR8 Read Access Policy 36 (IMR8_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR8 Read Access Policy 35 (IMR8_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR8 Read Access Policy 34 (IMR8_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR8 Read Access Policy 33 (IMR8_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR8 Read Access Policy 32 (IMR8_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR8 Read Access Policy 31 (IMR8_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR8 Read Access Policy 30 (IMR8_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR8 Read Access Policy 29 (IMR8_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR8 Read Access Policy 28 (IMR8_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR8 Read Access Policy 27 (IMR8_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR8 Read Access Policy 26 (IMR8_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR8 Read Access Policy 25 (IMR8_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR8 Read Access Policy 24 (IMR8_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR8 Read Access Policy 23 (IMR8_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR8 Read Access Policy 22 (IMR8_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR8 Read Access Policy 21 (IMR8_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR8 Read Access Policy 20 (IMR8_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR8 Read Access Policy 19 (IMR8_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR8 Read Access Policy 18 (IMR8_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR8 Read Access Policy 17 (IMR8_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR8 Read Access Policy 16 (IMR8_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR8 Read Access Policy 15 (IMR8_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR8 Read Access Policy 14 (IMR8_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR8 Read Access Policy 13 (IMR8_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR8 Read Access Policy 12 (IMR8_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR8 Read Access Policy 11 (IMR8_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR8 Read Access Policy 10 (IMR8_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR8 Read Access Policy 9 (IMR8_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR8 Read Access Policy 8 (IMR8_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR8 Read Access Policy 7 (IMR8_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR8 Read Access Policy 6 (IMR8_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR8 Read Access Policy 5 (IMR8_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR8 Read Access Policy 4 (IMR8_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR8 Read Access Policy 3 (IMR8_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR8 Read Access Policy 2 (IMR8_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR8 Read Access Policy 1 (IMR8_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR8 Read Access Policy 0 (IMR8_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR8 region, based on each agent's 6bit encoded SAI value.

44.3.66 IMR8 Write Access Policy (B_CR_BIMR8WAC_0_0_0_MCHBAR)—Offset 6988h

This register, along with IMR8BASE, IMR8MASK and IMR8RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR8. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6988h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR8 Write Access Policy 63 (IMR8_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR8 Write Access Policy 62 (IMR8_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR8 Write Access Policy 61 (IMR8_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR8 Write Access Policy 60 (IMR8_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR8 Write Access Policy 59 (IMR8_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR8 Write Access Policy 58 (IMR8_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR8 Write Access Policy 57 (IMR8_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR8 Write Access Policy 56 (IMR8_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR8 Write Access Policy 55 (IMR8_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR8 Write Access Policy 54 (IMR8_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR8 Write Access Policy 53 (IMR8_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR8 Write Access Policy 52 (IMR8_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR8 Write Access Policy 51 (IMR8_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR8 Write Access Policy 50 (IMR8_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR8 Write Access Policy 49 (IMR8_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR8 Write Access Policy 48 (IMR8_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR8 Write Access Policy 47 (IMR8_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR8 Write Access Policy 46 (IMR8_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR8 Write Access Policy 45 (IMR8_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR8 Write Access Policy 44 (IMR8_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR8 Write Access Policy 43 (IMR8_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR8 Write Access Policy 42 (IMR8_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR8 Write Access Policy 41 (IMR8_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR8 Write Access Policy 40 (IMR8_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR8 Write Access Policy 39 (IMR8_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR8 Write Access Policy 38 (IMR8_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR8 Write Access Policy 37 (IMR8_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR8 Write Access Policy 36 (IMR8_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR8 Write Access Policy 35 (IMR8_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR8 Write Access Policy 34 (IMR8_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR8 Write Access Policy 33 (IMR8_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR8 Write Access Policy 32 (IMR8_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR8 Write Access Policy 31 (IMR8_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR8 Write Access Policy 30 (IMR8_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR8 Write Access Policy 29 (IMR8_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR8 Write Access Policy 28 (IMR8_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR8 Write Access Policy 27 (IMR8_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR8 Write Access Policy 26 (IMR8_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR8 Write Access Policy 25 (IMR8_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR8 Write Access Policy 24 (IMR8_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR8 Write Access Policy 23 (IMR8_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR8 Write Access Policy 22 (IMR8_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR8 Write Access Policy 21 (IMR8_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR8 Write Access Policy 20 (IMR8_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR8 Write Access Policy 19 (IMR8_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR8 Write Access Policy 18 (IMR8_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR8 Write Access Policy 17 (IMR8_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR8 Write Access Policy 16 (IMR8_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR8 Write Access Policy 15 (IMR8_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR8 Write Access Policy 14 (IMR8_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR8 Write Access Policy 13 (IMR8_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR8 Write Access Policy 12 (IMR8_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR8 Write Access Policy 11 (IMR8_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR8 Write Access Policy 10 (IMR8_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR8 Write Access Policy 9 (IMR8_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR8 Write Access Policy 8 (IMR8_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR8 Write Access Policy 7 (IMR8_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR8 Write Access Policy 6 (IMR8_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR8 Write Access Policy 5 (IMR8_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR8 Write Access Policy 4 (IMR8_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR8 Write Access Policy 3 (IMR8_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR8 Write Access Policy 2 (IMR8_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR8 Write Access Policy 1 (IMR8_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR8 Write Access Policy 0 (IMR8_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR8 region, based on each agent's 6bit encoded SAI value.

44.3.67 IMR9 Base (B_CR_BIMR9BASE_0_0_0_MCHBAR)—Offset 6990h

This register, along with IMR9MASK, IMR9RAC and IMR9WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR9RAC and IMR9WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6990h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 1 IMR9 Base (IMR9_BASE):** Specifies bits 38:10 of the start address of IMR9 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR9MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR9 defined region.

44.3.68 IMR9 Mask (B_CR_BIMR9MASK_0_0_0_MCHBAR)—Offset 6994h

This register, along with IMR9BASE, IMR9RAC and IMR9WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR9RAC and IMR9WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6994h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback data HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 1 IMR9 Mask (IMR9_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR9BASE[28:0] value. A match indicates that the incoming address falls within the IMR9 region.

44.3.69 IMR9 Control Policy (B_CR_BIMR9CP_0_0_0_MCHBAR)—Offset 6998h

This register controls the access policy to the Read Access Policy BIMR9RAC, the Write Access Policy BIMR9WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6998h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR9 Control Policy (IMR9_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR9RAC, BIMR9WAC, BIMR9CP registers based on the value from each agent's 6bit SAI field.

44.3.70 IMR9 Read Access Policy (B_CR_BIMR9RAC_0_0_0_MCHBAR)—Offset 69A0h

This register, along with IMR9BASE, IMR9MASK and IMR9WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR9. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69A0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR9 Read Access Policy 63 (IMR9_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR9 Read Access Policy 62 (IMR9_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR9 Read Access Policy 61 (IMR9_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR9 Read Access Policy 60 (IMR9_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR9 Read Access Policy 59 (IMR9_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR9 Read Access Policy 58 (IMR9_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR9 Read Access Policy 57 (IMR9_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR9 Read Access Policy 56 (IMR9_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR9 Read Access Policy 55 (IMR9_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR9 Read Access Policy 54 (IMR9_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR9 Read Access Policy 53 (IMR9_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR9 Read Access Policy 52 (IMR9_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR9 Read Access Policy 51 (IMR9_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR9 Read Access Policy 50 (IMR9_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR9 Read Access Policy 49 (IMR9_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR9 Read Access Policy 48 (IMR9_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR9 Read Access Policy 47 (IMR9_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR9 Read Access Policy 46 (IMR9_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR9 Read Access Policy 45 (IMR9_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR9 Read Access Policy 44 (IMR9_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR9 Read Access Policy 43 (IMR9_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR9 Read Access Policy 42 (IMR9_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR9 Read Access Policy 41 (IMR9_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR9 Read Access Policy 40 (IMR9_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR9 Read Access Policy 39 (IMR9_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR9 Read Access Policy 38 (IMR9_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR9 Read Access Policy 37 (IMR9_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR9 Read Access Policy 36 (IMR9_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR9 Read Access Policy 35 (IMR9_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR9 Read Access Policy 34 (IMR9_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR9 Read Access Policy 33 (IMR9_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR9 Read Access Policy 32 (IMR9_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR9 Read Access Policy 31 (IMR9_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR9 Read Access Policy 30 (IMR9_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR9 Read Access Policy 29 (IMR9_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR9 Read Access Policy 28 (IMR9_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR9 Read Access Policy 27 (IMR9_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR9 Read Access Policy 26 (IMR9_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR9 Read Access Policy 25 (IMR9_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR9 Read Access Policy 24 (IMR9_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR9 Read Access Policy 23 (IMR9_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR9 Read Access Policy 22 (IMR9_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR9 Read Access Policy 21 (IMR9_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR9 Read Access Policy 20 (IMR9_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR9 Read Access Policy 19 (IMR9_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR9 Read Access Policy 18 (IMR9_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR9 Read Access Policy 17 (IMR9_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR9 Read Access Policy 16 (IMR9_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR9 Read Access Policy 15 (IMR9_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR9 Read Access Policy 14 (IMR9_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR9 Read Access Policy 13 (IMR9_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR9 Read Access Policy 12 (IMR9_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR9 Read Access Policy 11 (IMR9_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR9 Read Access Policy 10 (IMR9_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR9 Read Access Policy 9 (IMR9_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR9 Read Access Policy 8 (IMR9_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR9 Read Access Policy 7 (IMR9_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR9 Read Access Policy 6 (IMR9_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR9 Read Access Policy 5 (IMR9_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR9 Read Access Policy 4 (IMR9_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR9 Read Access Policy 3 (IMR9_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR9 Read Access Policy 2 (IMR9_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR9 Read Access Policy 1 (IMR9_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR9 Read Access Policy 0 (IMR9_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR9 region, based on each agent's 6bit encoded SAI value.

44.3.71 IMR9 Write Access Policy (B_CR_BIMR9WAC_0_0_0_MCHBAR)—Offset 69A8h

This register, along with IMR9BASE, IMR9MASK and IMR9RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR9. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69A8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR9 Write Access Policy 63 (IMR9_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR9 Write Access Policy 62 (IMR9_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR9 Write Access Policy 61 (IMR9_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR9 Write Access Policy 60 (IMR9_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR9 Write Access Policy 59 (IMR9_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR9 Write Access Policy 58 (IMR9_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR9 Write Access Policy 57 (IMR9_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR9 Write Access Policy 56 (IMR9_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR9 Write Access Policy 55 (IMR9_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR9 Write Access Policy 54 (IMR9_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR9 Write Access Policy 53 (IMR9_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR9 Write Access Policy 52 (IMR9_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR9 Write Access Policy 51 (IMR9_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR9 Write Access Policy 50 (IMR9_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR9 Write Access Policy 49 (IMR9_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR9 Write Access Policy 48 (IMR9_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR9 Write Access Policy 47 (IMR9_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR9 Write Access Policy 46 (IMR9_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR9 Write Access Policy 45 (IMR9_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR9 Write Access Policy 44 (IMR9_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR9 Write Access Policy 43 (IMR9_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR9 Write Access Policy 42 (IMR9_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR9 Write Access Policy 41 (IMR9_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR9 Write Access Policy 40 (IMR9_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR9 Write Access Policy 39 (IMR9_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR9 Write Access Policy 38 (IMR9_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR9 Write Access Policy 37 (IMR9_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR9 Write Access Policy 36 (IMR9_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR9 Write Access Policy 35 (IMR9_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR9 Write Access Policy 34 (IMR9_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR9 Write Access Policy 33 (IMR9_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR9 Write Access Policy 32 (IMR9_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR9 Write Access Policy 31 (IMR9_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR9 Write Access Policy 30 (IMR9_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR9 Write Access Policy 29 (IMR9_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR9 Write Access Policy 28 (IMR9_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR9 Write Access Policy 27 (IMR9_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR9 Write Access Policy 26 (IMR9_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR9 Write Access Policy 25 (IMR9_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR9 Write Access Policy 24 (IMR9_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR9 Write Access Policy 23 (IMR9_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR9 Write Access Policy 22 (IMR9_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR9 Write Access Policy 21 (IMR9_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR9 Write Access Policy 20 (IMR9_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR9 Write Access Policy 19 (IMR9_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR9 Write Access Policy 18 (IMR9_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR9 Write Access Policy 17 (IMR9_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR9 Write Access Policy 16 (IMR9_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR9 Write Access Policy 15 (IMR9_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR9 Write Access Policy 14 (IMR9_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR9 Write Access Policy 13 (IMR9_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR9 Write Access Policy 12 (IMR9_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR9 Write Access Policy 11 (IMR9_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR9 Write Access Policy 10 (IMR9_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR9 Write Access Policy 9 (IMR9_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR9 Write Access Policy 8 (IMR9_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR9 Write Access Policy 7 (IMR9_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR9 Write Access Policy 6 (IMR9_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR9 Write Access Policy 5 (IMR9_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR9 Write Access Policy 4 (IMR9_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR9 Write Access Policy 3 (IMR9_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR9 Write Access Policy 2 (IMR9_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR9 Write Access Policy 1 (IMR9_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR9 Write Access Policy 0 (IMR9_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR9 region, based on each agent's 6bit encoded SAI value.

44.3.72 IMR10 Base (B_CR_BIMR10BASE_0_0_0_MCHBAR)—Offset 69B0h

This register, along with IMR10MASK, IMR10RAC and IMR10WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR10RAC and IMR10WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 69B0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR10 Base (IMR10_BASE):** Specifies bits 38:10 of the start address of IMR10 region. IMR region size must be a strict poweroftwo at least 1KB and naturally aligned to the size. These bits are compared with the result of the IMR10MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR10 defined region.

44.3.73 B_CR_BIMR10MASK_0_0_0_MCHBAR—Offset 69B4h

This register, along with IMR10BASE, IMR10RAC and IMR10WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR10RAC and IMR10WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 69B4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback data HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR10 Mask (IMR10_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR10BASE[28:0] value. A match indicates that the incoming address falls within the IMR10 region.

44.3.74 IMR10 Control Policy (B_CR_BIMR10CP_0_0_0_MCHBAR)—Offset 69B8h

This register controls the access policy to the Read Access Policy BIMR10RAC, the Write Access Policy BIMR10WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69B8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR10 Control Policy (IMR10_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR10RAC, BIMR10WAC and BIMR10CP, registers based on the value from each agent's 6bit SAI field.

44.3.75 IMR10 Read Access Policy (B_CR_BIMR10RAC_0_0_0_MCHBAR)—Offset 69C0h

This register, along with IMR10BASE, IMR10MASK and IMR10WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR10. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69C0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR10 Read Access Policy 63 (IMR10_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR10 Read Access Policy 62 (IMR10_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR10 Read Access Policy 61 (IMR10_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR10 Read Access Policy 60 (IMR10_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR10 Read Access Policy 59 (IMR10_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR10 Read Access Policy 58 (IMR10_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR10 Read Access Policy 57 (IMR10_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR10 Read Access Policy 56 (IMR10_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR10 Read Access Policy 55 (IMR10_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR10 Read Access Policy 54 (IMR10_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR10 Read Access Policy 53 (IMR10_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR10 Read Access Policy 52 (IMR10_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR10 Read Access Policy 51 (IMR10_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR10 Read Access Policy 50 (IMR10_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR10 Read Access Policy 49 (IMR10_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR10 Read Access Policy 48 (IMR10_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR10 Read Access Policy 47 (IMR10_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR10 Read Access Policy 46 (IMR10_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR10 Read Access Policy 45 (IMR10_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR10 Read Access Policy 44 (IMR10_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR10 Read Access Policy 43 (IMR10_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR10 Read Access Policy 42 (IMR10_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR10 Read Access Policy 41 (IMR10_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR10 Read Access Policy 40 (IMR10_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR10 Read Access Policy 39 (IMR10_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR10 Read Access Policy 38 (IMR10_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR10 Read Access Policy 37 (IMR10_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR10 Read Access Policy 36 (IMR10_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR10 Read Access Policy 35 (IMR10_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR10 Read Access Policy 34 (IMR10_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR10 Read Access Policy 33 (IMR10_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR10 Read Access Policy 32 (IMR10_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR10 Read Access Policy 31 (IMR10_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR10 Read Access Policy 30 (IMR10_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR10 Read Access Policy 29 (IMR10_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR10 Read Access Policy 28 (IMR10_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR10 Read Access Policy 27 (IMR10_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR10 Read Access Policy 26 (IMR10_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR10 Read Access Policy 25 (IMR10_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR10 Read Access Policy 24 (IMR10_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR10 Read Access Policy 23 (IMR10_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR10 Read Access Policy 22 (IMR10_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR10 Read Access Policy 21 (IMR10_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR10 Read Access Policy 20 (IMR10_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR10 Read Access Policy 19 (IMR10_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR10 Read Access Policy 18 (IMR10_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR10 Read Access Policy 17 (IMR10_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR10 Read Access Policy 16 (IMR10_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR10 Read Access Policy 15 (IMR10_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR10 Read Access Policy 14 (IMR10_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR10 Read Access Policy 13 (IMR10_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR10 Read Access Policy 12 (IMR10_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR10 Read Access Policy 11 (IMR10_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR10 Read Access Policy 10 (IMR10_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR10 Read Access Policy 9 (IMR10_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR10 Read Access Policy 8 (IMR10_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR10 Read Access Policy 7 (IMR10_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR10 Read Access Policy 6 (IMR10_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR10 Read Access Policy 5 (IMR10_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR10 Read Access Policy 4 (IMR10_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR10 Read Access Policy 3 (IMR10_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR10 Read Access Policy 2 (IMR10_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR10 Read Access Policy 1 (IMR10_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR10 Read Access Policy 0 (IMR10_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR10 region, based on each agent's 6bit encoded SAI value.

44.3.76 IMR10 Write Access Policy (B_CR_BIMR10WAC_0_0_0_MCHBAR)—Offset 69C8h

This register along with IMR10BASE, IMR10MASK and IMR10RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR10. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69C8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR10 Write Access Policy 63 (IMR10_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR10 Write Access Policy 62 (IMR10_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR10 Write Access Policy 61 (IMR10_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR10 Write Access Policy 60 (IMR10_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR10 Write Access Policy 59 (IMR10_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR10 Write Access Policy 58 (IMR10_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR10 Write Access Policy 57 (IMR10_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR10 Write Access Policy 56 (IMR10_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR10 Write Access Policy 55 (IMR10_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR10 Write Access Policy 54 (IMR10_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR10 Write Access Policy 53 (IMR10_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR10 Write Access Policy 52 (IMR10_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR10 Write Access Policy 51 (IMR10_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR10 Write Access Policy 50 (IMR10_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR10 Write Access Policy 49 (IMR10_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR10 Write Access Policy 48 (IMR10_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR10 Write Access Policy 47 (IMR10_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR10 Write Access Policy 46 (IMR10_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR10 Write Access Policy 45 (IMR10_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR10 Write Access Policy 44 (IMR10_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR10 Write Access Policy 43 (IMR10_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR10 Write Access Policy 42 (IMR10_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR10 Write Access Policy 41 (IMR10_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR10 Write Access Policy 40 (IMR10_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR10 Write Access Policy 39 (IMR10_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR10 Write Access Policy 38 (IMR10_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR10 Write Access Policy 37 (IMR10_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR10 Write Access Policy 36 (IMR10_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR10 Write Access Policy 35 (IMR10_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR10 Write Access Policy 34 (IMR10_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR10 Write Access Policy 33 (IMR10_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR10 Write Access Policy 32 (IMR10_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR10 Write Access Policy 31 (IMR10_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR10 Write Access Policy 30 (IMR10_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR10 Write Access Policy 29 (IMR10_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR10 Write Access Policy 28 (IMR10_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR10 Write Access Policy 27 (IMR10_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR10 Write Access Policy 26 (IMR10_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR10 Write Access Policy 25 (IMR10_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR10 Write Access Policy 24 (IMR10_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR10 Write Access Policy 23 (IMR10_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR10 Write Access Policy 22 (IMR10_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR10 Write Access Policy 21 (IMR10_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR10 Write Access Policy 20 (IMR10_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR10 Write Access Policy 19 (IMR10_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR10 Write Access Policy 18 (IMR10_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR10 Write Access Policy 17 (IMR10_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR10 Write Access Policy 16 (IMR10_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR10 Write Access Policy 15 (IMR10_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR10 Write Access Policy 14 (IMR10_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR10 Write Access Policy 13 (IMR10_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR10 Write Access Policy 12 (IMR10_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR10 Write Access Policy 11 (IMR10_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR10 Write Access Policy 10 (IMR10_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR10 Write Access Policy 9 (IMR10_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR10 Write Access Policy 8 (IMR10_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR10 Write Access Policy 7 (IMR10_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR10 Write Access Policy 6 (IMR10_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR10 Write Access Policy 5 (IMR10_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR10 Write Access Policy 4 (IMR10_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR10 Write Access Policy 3 (IMR10_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR10 Write Access Policy 2 (IMR10_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR10 Write Access Policy 1 (IMR10_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR10 Write Access Policy 0 (IMR10_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR10 region, based on each agent's 6bit encoded SAI value.

44.3.77 IMR11 Base (B_CR_BIMR11BASE_0_0_0_MCHBAR)—Offset 69D0h

This register, along with IMR11MASK, IMR11RAC and IMR11WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR11RAC and IMR11WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 69D0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR11 Base (IMR11_BASE):** Specifies bits 38:10 of the start address of IMR11 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR11MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR11 defined region.

44.3.78 IMR11 Mask (B_CR_BIMR11MASK_0_0_0_MCHBAR)—Offset 69D4h

This register, along with IMR11BASE, IMR11RAC and IMR11WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR11RAC and IMR11WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 69D4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback data HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR11 Mask (IMR11_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR11BASE[28:0] value. A match indicates that the incoming address falls within the IMR11 region.

44.3.79 IMR11 Control Policy (B_CR_BIMR11CP_0_0_0_MCHBAR)—Offset 69D8h

This register controls the access policy to the Read Access Policy BIMR11RAC, the Write Access Policy BIMR11WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69D8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR11 Control Policy (IMR11_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR11RAC, BIMR11WAC and BIMR11CP registers, based on the value from each agent's 6bit SAI field.

44.3.80 IMR11 Read Access Policy (B_CR_BIMR11RAC_0_0_0_MCHBAR)—Offset 69E0h

This register, along with IMR11BASE, IMR11MASK and IMR11WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR11. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69E0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR11 Read Access Policy 63 (IMR11_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR11 Read Access Policy 62 (IMR11_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR11 Read Access Policy 61 (IMR11_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR11 Read Access Policy 60 (IMR11_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR11 Read Access Policy 59 (IMR11_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR11 Read Access Policy 58 (IMR11_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR11 Read Access Policy 57 (IMR11_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR11 Read Access Policy 56 (IMR11_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR11 Read Access Policy 55 (IMR11_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR11 Read Access Policy 54 (IMR11_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR11 Read Access Policy 53 (IMR11_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR11 Read Access Policy 52 (IMR11_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR11 Read Access Policy 51 (IMR11_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR11 Read Access Policy 50 (IMR11_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR11 Read Access Policy 49 (IMR11_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR11 Read Access Policy 48 (IMR11_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR11 Read Access Policy 47 (IMR11_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR11 Read Access Policy 46 (IMR11_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR11 Read Access Policy 45 (IMR11_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR11 Read Access Policy 44 (IMR11_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR11 Read Access Policy 43 (IMR11_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR11 Read Access Policy 42 (IMR11_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR11 Read Access Policy 41 (IMR11_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR11 Read Access Policy 40 (IMR11_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR11 Read Access Policy 39 (IMR11_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR11 Read Access Policy 38 (IMR11_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR11 Read Access Policy 37 (IMR11_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR11 Read Access Policy 36 (IMR11_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR11 Read Access Policy 35 (IMR11_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR11 Read Access Policy 34 (IMR11_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR11 Read Access Policy 33 (IMR11_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR11 Read Access Policy 32 (IMR11_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR11 Read Access Policy 31 (IMR11_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR11 Read Access Policy 30 (IMR11_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR11 Read Access Policy 29 (IMR11_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR11 Read Access Policy 28 (IMR11_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR11 Read Access Policy 27 (IMR11_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR11 Read Access Policy 26 (IMR11_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR11 Read Access Policy 25 (IMR11_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR11 Read Access Policy 24 (IMR11_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR11 Read Access Policy 23 (IMR11_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR11 Read Access Policy 22 (IMR11_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR11 Read Access Policy 21 (IMR11_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR11 Read Access Policy 20 (IMR11_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR11 Read Access Policy 19 (IMR11_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR11 Read Access Policy 18 (IMR11_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR11 Read Access Policy 17 (IMR11_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR11 Read Access Policy 16 (IMR11_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR11 Read Access Policy 15 (IMR11_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR11 Read Access Policy 14 (IMR11_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR11 Read Access Policy 13 (IMR11_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR11 Read Access Policy 12 (IMR11_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR11 Read Access Policy 11 (IMR11_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR11 Read Access Policy 10 (IMR11_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR11 Read Access Policy 9 (IMR11_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR11 Read Access Policy 8 (IMR11_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR11 Read Access Policy 7 (IMR11_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR11 Read Access Policy 6 (IMR11_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR11 Read Access Policy 5 (IMR11_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR11 Read Access Policy 4 (IMR11_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR11 Read Access Policy 3 (IMR11_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR11 Read Access Policy 2 (IMR11_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR11 Read Access Policy 1 (IMR11_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR11 Read Access Policy 0 (IMR11_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR11 region, based on each agent's 6bit encoded SAI value.

44.3.81 IMR11 Write Access Policy (B_CR_BIMR11WAC_0_0_0_MCHBAR)—Offset 69E8h

This register, along with IMR11BASE, IMR11MASK and IMR11RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR11. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69E8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR11 Write Access Policy 63 (IMR11_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR11 Write Access Policy 62 (IMR11_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR11 Write Access Policy 61 (IMR11_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR11 Write Access Policy 60 (IMR11_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR11 Write Access Policy 59 (IMR11_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR11 Write Access Policy 58 (IMR11_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR11 Write Access Policy 57 (IMR11_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR11 Write Access Policy 56 (IMR11_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR11 Write Access Policy 55 (IMR11_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR11 Write Access Policy 54 (IMR11_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR11 Write Access Policy 53 (IMR11_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR11 Write Access Policy 52 (IMR11_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR11 Write Access Policy 51 (IMR11_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR11 Write Access Policy 50 (IMR11_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR11 Write Access Policy 49 (IMR11_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR11 Write Access Policy 48 (IMR11_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR11 Write Access Policy 47 (IMR11_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR11 Write Access Policy 46 (IMR11_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR11 Write Access Policy 45 (IMR11_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR11 Write Access Policy 44 (IMR11_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR11 Write Access Policy 43 (IMR11_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR11 Write Access Policy 42 (IMR11_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR11 Write Access Policy 41 (IMR11_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR11 Write Access Policy 40 (IMR11_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR11 Write Access Policy 39 (IMR11_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR11 Write Access Policy 38 (IMR11_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR11 Write Access Policy 37 (IMR11_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR11 Write Access Policy 36 (IMR11_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR11 Write Access Policy 35 (IMR11_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR11 Write Access Policy 34 (IMR11_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR11 Write Access Policy 33 (IMR11_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR11 Write Access Policy 32 (IMR11_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR11 Write Access Policy 31 (IMR11_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR11 Write Access Policy 30 (IMR11_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR11 Write Access Policy 29 (IMR11_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR11 Write Access Policy 28 (IMR11_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR11 Write Access Policy 27 (IMR11_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR11 Write Access Policy 26 (IMR11_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR11 Write Access Policy 25 (IMR11_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR11 Write Access Policy 24 (IMR11_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR11 Write Access Policy 23 (IMR11_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR11 Write Access Policy 22 (IMR11_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR11 Write Access Policy 21 (IMR11_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR11 Write Access Policy 20 (IMR11_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR11 Write Access Policy 19 (IMR11_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR11 Write Access Policy 18 (IMR11_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR11 Write Access Policy 17 (IMR11_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR11 Write Access Policy 16 (IMR11_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR11 Write Access Policy 15 (IMR11_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR11 Write Access Policy 14 (IMR11_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR11 Write Access Policy 13 (IMR11_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR11 Write Access Policy 12 (IMR11_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR11 Write Access Policy 11 (IMR11_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR11 Write Access Policy 10 (IMR11_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR11 Write Access Policy 9 (IMR11_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR11 Write Access Policy 8 (IMR11_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR11 Write Access Policy 7 (IMR11_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR11 Write Access Policy 6 (IMR11_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR11 Write Access Policy 5 (IMR11_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR11 Write Access Policy 4 (IMR11_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR11 Write Access Policy 3 (IMR11_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR11 Write Access Policy 2 (IMR11_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR11 Write Access Policy 1 (IMR11_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR11 Write Access Policy 0 (IMR11_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR11 region, based on each agent's 6bit encoded SAI value.

44.3.82 IMR12 Base (B_CR_BIMR12BASE_0_0_0_MCHBAR)—Offset 69F0h

This register, along with IMR12MASK, IMR12RAC and IMR12WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR12RAC and IMR12WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 69F0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR12 Base (IMR12_BASE):** Specifies bits 38:10 of the start address of IMR12 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR12MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR12 defined region.

44.3.83 IMR12 Mask (B_CR_BIMR12MASK_0_0_0_MCHBAR)—Offset 69F4h

This register, along with IMR12BASE, IMR12RAC and IMR12WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR12RAC and IMR12WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 69F4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR12 Mask (IMR12_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR12BASE[28:0] value. A match indicates that the incoming address falls within the IMR12 region.

44.3.84 IMR12 Control Policy (B_CR_BIMR12CP_0_0_0_MCHBAR)—Offset 69F8h

This register controls the access policy to the Read Access Policy BIMR12RAC, the Write Access Policy BIMR12WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 69F8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR12 Control Policy (IMR12_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR12RAC, BIMR12WAC and BIMR12CP registers, based on the value from each agent's 6bit SAI field.

44.3.85 IMR12 Read Access Policy (B_CR_BIMR12RAC_0_0_0_MCHBAR)—Offset 6A00h

This register, along with IMR12BASE, IMR12MASK and IMR12WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR12. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A00h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR12 Read Access Policy 63 (IMR12_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR12 Read Access Policy 62 (IMR12_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR12 Read Access Policy 61 (IMR12_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR12 Read Access Policy 60 (IMR12_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR12 Read Access Policy 59 (IMR12_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR12 Read Access Policy 58 (IMR12_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR12 Read Access Policy 57 (IMR12_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR12 Read Access Policy 56 (IMR12_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR12 Read Access Policy 55 (IMR12_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR12 Read Access Policy 54 (IMR12_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR12 Read Access Policy 53 (IMR12_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR12 Read Access Policy 52 (IMR12_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR12 Read Access Policy 51 (IMR12_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR12 Read Access Policy 50 (IMR12_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR12 Read Access Policy 49 (IMR12_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR12 Read Access Policy 48 (IMR12_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR12 Read Access Policy 47 (IMR12_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR12 Read Access Policy 46 (IMR12_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR12 Read Access Policy 45 (IMR12_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR12 Read Access Policy 44 (IMR12_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR12 Read Access Policy 43 (IMR12_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR12 Read Access Policy 42 (IMR12_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR12 Read Access Policy 41 (IMR12_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR12 Read Access Policy 40 (IMR12_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR12 Read Access Policy 39 (IMR12_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR12 Read Access Policy 38 (IMR12_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR12 Read Access Policy 37 (IMR12_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR12 Read Access Policy 36 (IMR12_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR12 Read Access Policy 35 (IMR12_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR12 Read Access Policy 34 (IMR12_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR12 Read Access Policy 33 (IMR12_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR12 Read Access Policy 32 (IMR12_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR12 Read Access Policy 31 (IMR12_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR12 Read Access Policy 30 (IMR12_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR12 Read Access Policy 29 (IMR12_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR12 Read Access Policy 28 (IMR12_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR12 Read Access Policy 27 (IMR12_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR12 Read Access Policy 26 (IMR12_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR12 Read Access Policy 25 (IMR12_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR12 Read Access Policy 24 (IMR12_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR12 Read Access Policy 23 (IMR12_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR12 Read Access Policy 22 (IMR12_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR12 Read Access Policy 21 (IMR12_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR12 Read Access Policy 20 (IMR12_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR12 Read Access Policy 19 (IMR12_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR12 Read Access Policy 18 (IMR12_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR12 Read Access Policy 17 (IMR12_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR12 Read Access Policy 16 (IMR12_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR12 Read Access Policy 15 (IMR12_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR12 Read Access Policy 14 (IMR12_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR12 Read Access Policy 13 (IMR12_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR12 Read Access Policy 12 (IMR12_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR12 Read Access Policy 11 (IMR12_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR12 Read Access Policy 10 (IMR12_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR12 Read Access Policy 9 (IMR12_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR12 Read Access Policy 8 (IMR12_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR12 Read Access Policy 7 (IMR12_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR12 Read Access Policy 6 (IMR12_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR12 Read Access Policy 5 (IMR12_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR12 Read Access Policy 4 (IMR12_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR12 Read Access Policy 3 (IMR12_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR12 Read Access Policy 2 (IMR12_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR12 Read Access Policy 1 (IMR12_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR12 Read Access Policy 0 (IMR12_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR12 region, based on each agent's 6bit encoded SAI value.

44.3.86 IMR12 Write Access Policy (B_CR_BIMR12WAC_0_0_0_MCHBAR)—Offset 6A08h

This register, along with IMR12BASE, IMR12MASK and IMR12RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR12. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A08h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR12 Write Access Policy 63 (IMR12_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR12 Write Access Policy 62 (IMR12_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR12 Write Access Policy 61 (IMR12_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR12 Write Access Policy 60 (IMR12_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR12 Write Access Policy 59 (IMR12_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR12 Write Access Policy 58 (IMR12_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR12 Write Access Policy 57 (IMR12_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR12 Write Access Policy 56 (IMR12_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR12 Write Access Policy 55 (IMR12_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR12 Write Access Policy 54 (IMR12_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR12 Write Access Policy 53 (IMR12_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR12 Write Access Policy 52 (IMR12_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR12 Write Access Policy 51 (IMR12_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR12 Write Access Policy 50 (IMR12_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR12 Write Access Policy 49 (IMR12_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR12 Write Access Policy 48 (IMR12_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR12 Write Access Policy 47 (IMR12_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR12 Write Access Policy 46 (IMR12_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR12 Write Access Policy 45 (IMR12_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR12 Write Access Policy 44 (IMR12_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR12 Write Access Policy 43 (IMR12_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR12 Write Access Policy 42 (IMR12_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR12 Write Access Policy 41 (IMR12_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR12 Write Access Policy 40 (IMR12_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR12 Write Access Policy 39 (IMR12_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR12 Write Access Policy 38 (IMR12_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR12 Write Access Policy 37 (IMR12_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR12 Write Access Policy 36 (IMR12_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR12 Write Access Policy 35 (IMR12_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR12 Write Access Policy 34 (IMR12_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR12 Write Access Policy 33 (IMR12_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR12 Write Access Policy 32 (IMR12_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR12 Write Access Policy 31 (IMR12_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR12 Write Access Policy 30 (IMR12_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR12 Write Access Policy 29 (IMR12_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR12 Write Access Policy 28 (IMR12_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR12 Write Access Policy 27 (IMR12_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR12 Write Access Policy 26 (IMR12_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR12 Write Access Policy 25 (IMR12_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR12 Write Access Policy 24 (IMR12_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR12 Write Access Policy 23 (IMR12_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR12 Write Access Policy 22 (IMR12_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR12 Write Access Policy 21 (IMR12_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR12 Write Access Policy 20 (IMR12_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR12 Write Access Policy 19 (IMR12_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR12 Write Access Policy 18 (IMR12_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR12 Write Access Policy 17 (IMR12_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR12 Write Access Policy 16 (IMR12_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR12 Write Access Policy 15 (IMR12_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR12 Write Access Policy 14 (IMR12_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR12 Write Access Policy 13 (IMR12_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR12 Write Access Policy 12 (IMR12_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR12 Write Access Policy 11 (IMR12_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR12 Write Access Policy 10 (IMR12_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR12 Write Access Policy 9 (IMR12_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR12 Write Access Policy 8 (IMR12_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR12 Write Access Policy 7 (IMR12_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR12 Write Access Policy 6 (IMR12_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR12 Write Access Policy 5 (IMR12_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR12 Write Access Policy 4 (IMR12_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR12 Write Access Policy 3 (IMR12_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR12 Write Access Policy 2 (IMR12_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR12 Write Access Policy 1 (IMR12_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR12 Write Access Policy 0 (IMR12_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR12 region, based on each agent's 6bit encoded SAI value.

44.3.87 IMR13 Base (B_CR_BIMR13BASE_0_0_0_MCHBAR)—Offset 6A10h

This register, along with IMR13MASK, IMR13RAC and IMR13WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR13RAC and IMR13WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A10h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR13 Base (IMR13_BASE):** Specifies bits 38:10 of the start address of IMR13 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR13MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR13 defined region.

44.3.88 IMR13 Mask (B_CR_BIMR13MASK_0_0_0_MCHBAR)—Offset 6A14h

This register, along with IMR13BASE, IMR13RAC and IMR13WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR13RAC and IMR13WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A14h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR13 Mask (IMR13_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR13BASE[28:0] value. A match indicates that the incoming address falls within the IMR13 region.

44.3.89 IMR13 Control Policy (B_CR_BIMR13CP_0_0_0_MCHBAR)—Offset 6A18h

This register controls the access policy to the Read Access Policy BIMR13RAC, the Write Access Policy BIMR13WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A18h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR13 Control Policy (IMR13_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR13RAC, BIMR13WAC and BIMR13CP registers, based on the value from each agent's 6bit SAI field.

44.3.90 IMR13 Read Access Policy (B_CR_BIMR13RAC_0_0_0_MCHBAR)—Offset 6A20h

This register, along with IMR13BASE, IMR13MASK and IMR13WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR13. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A20h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR13 Read Access Policy 63 (IMR13_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR13 Read Access Policy 62 (IMR13_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR13 Read Access Policy 61 (IMR13_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR13 Read Access Policy 60 (IMR13_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR13 Read Access Policy 59 (IMR13_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR13 Read Access Policy 58 (IMR13_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR13 Read Access Policy 57 (IMR13_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR13 Read Access Policy 56 (IMR13_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR13 Read Access Policy 55 (IMR13_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR13 Read Access Policy 54 (IMR13_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR13 Read Access Policy 53 (IMR13_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR13 Read Access Policy 52 (IMR13_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR13 Read Access Policy 51 (IMR13_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR13 Read Access Policy 50 (IMR13_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR13 Read Access Policy 49 (IMR13_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR13 Read Access Policy 48 (IMR13_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR13 Read Access Policy 47 (IMR13_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR13 Read Access Policy 46 (IMR13_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR13 Read Access Policy 45 (IMR13_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR13 Read Access Policy 44 (IMR13_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR13 Read Access Policy 43 (IMR13_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR13 Read Access Policy 42 (IMR13_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR13 Read Access Policy 41 (IMR13_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR13 Read Access Policy 40 (IMR13_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR13 Read Access Policy 39 (IMR13_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR13 Read Access Policy 38 (IMR13_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR13 Read Access Policy 37 (IMR13_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR13 Read Access Policy 36 (IMR13_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR13 Read Access Policy 35 (IMR13_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR13 Read Access Policy 34 (IMR13_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR13 Read Access Policy 33 (IMR13_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR13 Read Access Policy 32 (IMR13_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR13 Read Access Policy 31 (IMR13_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR13 Read Access Policy 30 (IMR13_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR13 Read Access Policy 29 (IMR13_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR13 Read Access Policy 28 (IMR13_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR13 Read Access Policy 27 (IMR13_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR13 Read Access Policy 26 (IMR13_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR13 Read Access Policy 25 (IMR13_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR13 Read Access Policy 24 (IMR13_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR13 Read Access Policy 23 (IMR13_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR13 Read Access Policy 22 (IMR13_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR13 Read Access Policy 21 (IMR13_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR13 Read Access Policy 20 (IMR13_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR13 Read Access Policy 19 (IMR13_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR13 Read Access Policy 18 (IMR13_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR13 Read Access Policy 17 (IMR13_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR13 Read Access Policy 16 (IMR13_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR13 Read Access Policy 15 (IMR13_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR13 Read Access Policy 14 (IMR13_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR13 Read Access Policy 13 (IMR13_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR13 Read Access Policy 12 (IMR13_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR13 Read Access Policy 11 (IMR13_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR13 Read Access Policy 10 (IMR13_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR13 Read Access Policy 9 (IMR13_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR13 Read Access Policy 8 (IMR13_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR13 Read Access Policy 7 (IMR13_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR13 Read Access Policy 6 (IMR13_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR13 Read Access Policy 5 (IMR13_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR13 Read Access Policy 4 (IMR13_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR13 Read Access Policy 3 (IMR13_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR13 Read Access Policy 2 (IMR13_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR13 Read Access Policy 1 (IMR13_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR13 Read Access Policy 0 (IMR13_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR13 region, based on each agent's 6bit encoded SAI value.

44.3.91 IMR13 Write Access Policy (B_CR_BIMR13WAC_0_0_0_MCHBAR)—Offset 6A28h

This register, along with IMR13BASE, IMR13MASK and IMR13RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR13. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A28h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR13 Write Access Policy 63 (IMR13_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR13 Write Access Policy 62 (IMR13_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR13 Write Access Policy 61 (IMR13_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR13 Write Access Policy 60 (IMR13_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR13 Write Access Policy 59 (IMR13_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR13 Write Access Policy 58 (IMR13_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR13 Write Access Policy 57 (IMR13_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR13 Write Access Policy 56 (IMR13_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR13 Write Access Policy 55 (IMR13_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR13 Write Access Policy 54 (IMR13_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR13 Write Access Policy 53 (IMR13_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR13 Write Access Policy 52 (IMR13_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR13 Write Access Policy 51 (IMR13_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR13 Write Access Policy 50 (IMR13_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR13 Write Access Policy 49 (IMR13_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR13 Write Access Policy 48 (IMR13_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR13 Write Access Policy 47 (IMR13_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR13 Write Access Policy 46 (IMR13_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR13 Write Access Policy 45 (IMR13_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR13 Write Access Policy 44 (IMR13_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR13 Write Access Policy 43 (IMR13_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR13 Write Access Policy 42 (IMR13_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR13 Write Access Policy 41 (IMR13_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR13 Write Access Policy 40 (IMR13_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR13 Write Access Policy 39 (IMR13_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR13 Write Access Policy 38 (IMR13_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR13 Write Access Policy 37 (IMR13_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR13 Write Access Policy 36 (IMR13_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR13 Write Access Policy 35 (IMR13_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR13 Write Access Policy 34 (IMR13_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR13 Write Access Policy 33 (IMR13_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR13 Write Access Policy 32 (IMR13_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR13 Write Access Policy 31 (IMR13_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR13 Write Access Policy 30 (IMR13_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR13 Write Access Policy 29 (IMR13_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR13 Write Access Policy 28 (IMR13_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR13 Write Access Policy 27 (IMR13_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR13 Write Access Policy 26 (IMR13_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR13 Write Access Policy 25 (IMR13_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR13 Write Access Policy 24 (IMR13_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR13 Write Access Policy 23 (IMR13_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR13 Write Access Policy 22 (IMR13_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR13 Write Access Policy 21 (IMR13_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR13 Write Access Policy 20 (IMR13_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR13 Write Access Policy 19 (IMR13_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR13 Write Access Policy 18 (IMR13_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR13 Write Access Policy 17 (IMR13_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR13 Write Access Policy 16 (IMR13_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR13 Write Access Policy 15 (IMR13_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR13 Write Access Policy 14 (IMR13_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR13 Write Access Policy 13 (IMR13_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR13 Write Access Policy 12 (IMR13_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR13 Write Access Policy 11 (IMR13_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR13 Write Access Policy 10 (IMR13_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR13 Write Access Policy 9 (IMR13_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR13 Write Access Policy 8 (IMR13_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR13 Write Access Policy 7 (IMR13_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR13 Write Access Policy 6 (IMR13_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR13 Write Access Policy 5 (IMR13_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR13 Write Access Policy 4 (IMR13_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR13 Write Access Policy 3 (IMR13_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR13 Write Access Policy 2 (IMR13_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR13 Write Access Policy 1 (IMR13_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR13 Write Access Policy 0 (IMR13_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR13 region, based on each agent's 6bit encoded SAI value.

44.3.92 IMR14 Base (B_CR_BIMR14BASE_0_0_0_MCHBAR)—Offset 6A30h

This register, along with IMR14MASK, IMR14RAC and IMR14WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR14RAC and IMR14WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A30h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR14 Base (IMR14_BASE):** Specifies bits 38:10 of the start address of IMR14 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR14MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR14 defined region.

44.3.93 IMR14 Mask (B_CR_BIMR14MASK_0_0_0_MCHBAR)—Offset 6A34h

This register, along with IMR14BASE, IMR14RAC and IMR14WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR14RAC and IMR14WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A34h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR14 Mask (IMR14_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR14BASE[28:0] value. A match indicates that the incoming address falls within the IMR14 region.

44.3.94 IMR14 Control Policy (B_CR_BIMR14CP_0_0_0_MCHBAR)—Offset 6A38h

This register controls the access policy to the Read Access Policy BIMR14RAC, the Write Access Policy BIMR14WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A38h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR14 Control Policy (IMR14_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR14RAC, BIMR14WAC and BIMR14CP registers, based on the value from each agent's 6bit SAI field.

44.3.95 IMR14 Read Access Policy (B_CR_BIMR14RAC_0_0_0_MCHBAR)—Offset 6A40h

This register, along with IMR14BASE, IMR14MASK and IMR14WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR14. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A40h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR14 Read Access Policy 63 (IMR14_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR14 Read Access Policy 62 (IMR14_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR14 Read Access Policy 61 (IMR14_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR14 Read Access Policy 60 (IMR14_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR14 Read Access Policy 59 (IMR14_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR14 Read Access Policy 58 (IMR14_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR14 Read Access Policy 57 (IMR14_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR14 Read Access Policy 56 (IMR14_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR14 Read Access Policy 55 (IMR14_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR14 Read Access Policy 54 (IMR14_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR14 Read Access Policy 53 (IMR14_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR14 Read Access Policy 52 (IMR14_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR14 Read Access Policy 51 (IMR14_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR14 Read Access Policy 50 (IMR14_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR14 Read Access Policy 49 (IMR14_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR14 Read Access Policy 48 (IMR14_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR14 Read Access Policy 47 (IMR14_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR14 Read Access Policy 46 (IMR14_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR14 Read Access Policy 45 (IMR14_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR14 Read Access Policy 44 (IMR14_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR14 Read Access Policy 43 (IMR14_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR14 Read Access Policy 42 (IMR14_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR14 Read Access Policy 41 (IMR14_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR14 Read Access Policy 40 (IMR14_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR14 Read Access Policy 39 (IMR14_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR14 Read Access Policy 38 (IMR14_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR14 Read Access Policy 37 (IMR14_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR14 Read Access Policy 36 (IMR14_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR14 Read Access Policy 35 (IMR14_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR14 Read Access Policy 34 (IMR14_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR14 Read Access Policy 33 (IMR14_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR14 Read Access Policy 32 (IMR14_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR14 Read Access Policy 31 (IMR14_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR14 Read Access Policy 30 (IMR14_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR14 Read Access Policy 29 (IMR14_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR14 Read Access Policy 28 (IMR14_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR14 Read Access Policy 27 (IMR14_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR14 Read Access Policy 26 (IMR14_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR14 Read Access Policy 25 (IMR14_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR14 Read Access Policy 24 (IMR14_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR14 Read Access Policy 23 (IMR14_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR14 Read Access Policy 22 (IMR14_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR14 Read Access Policy 21 (IMR14_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR14 Read Access Policy 20 (IMR14_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR14 Read Access Policy 19 (IMR14_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR14 Read Access Policy 18 (IMR14_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR14 Read Access Policy 17 (IMR14_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR14 Read Access Policy 16 (IMR14_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR14 Read Access Policy 15 (IMR14_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR14 Read Access Policy 14 (IMR14_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR14 Read Access Policy 13 (IMR14_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR14 Read Access Policy 12 (IMR14_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR14 Read Access Policy 11 (IMR14_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR14 Read Access Policy 10 (IMR14_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR14 Read Access Policy 9 (IMR14_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR14 Read Access Policy 8 (IMR14_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR14 Read Access Policy 7 (IMR14_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR14 Read Access Policy 6 (IMR14_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR14 Read Access Policy 5 (IMR14_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR14 Read Access Policy 4 (IMR14_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR14 Read Access Policy 3 (IMR14_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR14 Read Access Policy 2 (IMR14_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR14 Read Access Policy 1 (IMR14_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR14 Read Access Policy 0 (IMR14_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR14 region, based on each agent's 6bit encoded SAI value.

44.3.96 IMR14 Write Access Policy (B_CR_BIMR14WAC_0_0_0_MCHBAR)—Offset 6A48h

This register, along with IMR14BASE IMR14MASK and IMR14RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR14. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A48h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR14 Write Access Policy 63 (IMR14_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR14 Write Access Policy 62 (IMR14_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR14 Write Access Policy 61 (IMR14_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR14 Write Access Policy 60 (IMR14_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR14 Write Access Policy 59 (IMR14_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR14 Write Access Policy 58 (IMR14_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR14 Write Access Policy 57 (IMR14_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR14 Write Access Policy 56 (IMR14_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR14 Write Access Policy 55 (IMR14_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR14 Write Access Policy 54 (IMR14_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR14 Write Access Policy 53 (IMR14_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR14 Write Access Policy 52 (IMR14_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR14 Write Access Policy 51 (IMR14_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR14 Write Access Policy 50 (IMR14_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR14 Write Access Policy 49 (IMR14_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR14 Write Access Policy 48 (IMR14_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR14 Write Access Policy 47 (IMR14_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR14 Write Access Policy 46 (IMR14_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR14 Write Access Policy 45 (IMR14_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR14 Write Access Policy 44 (IMR14_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR14 Write Access Policy 43 (IMR14_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR14 Write Access Policy 42 (IMR14_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR14 Write Access Policy 41 (IMR14_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR14 Write Access Policy 40 (IMR14_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR14 Write Access Policy 39 (IMR14_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR14 Write Access Policy 38 (IMR14_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR14 Write Access Policy 37 (IMR14_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR14 Write Access Policy 36 (IMR14_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR14 Write Access Policy 35 (IMR14_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR14 Write Access Policy 34 (IMR14_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR14 Write Access Policy 33 (IMR14_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR14 Write Access Policy 32 (IMR14_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR14 Write Access Policy 31 (IMR14_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR14 Write Access Policy 30 (IMR14_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR14 Write Access Policy 29 (IMR14_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR14 Write Access Policy 28 (IMR14_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR14 Write Access Policy 27 (IMR14_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR14 Write Access Policy 26 (IMR14_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR14 Write Access Policy 25 (IMR14_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR14 Write Access Policy 24 (IMR14_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR14 Write Access Policy 23 (IMR14_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR14 Write Access Policy 22 (IMR14_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR14 Write Access Policy 21 (IMR14_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR14 Write Access Policy 20 (IMR14_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR14 Write Access Policy 19 (IMR14_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR14 Write Access Policy 18 (IMR14_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR14 Write Access Policy 17 (IMR14_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR14 Write Access Policy 16 (IMR14_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR14 Write Access Policy 15 (IMR14_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR14 Write Access Policy 14 (IMR14_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR14 Write Access Policy 13 (IMR14_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR14 Write Access Policy 12 (IMR14_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR14 Write Access Policy 11 (IMR14_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR14 Write Access Policy 10 (IMR14_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR14 Write Access Policy 9 (IMR14_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR14 Write Access Policy 8 (IMR14_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR14 Write Access Policy 7 (IMR14_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR14 Write Access Policy 6 (IMR14_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR14 Write Access Policy 5 (IMR14_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR14 Write Access Policy 4 (IMR14_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR14 Write Access Policy 3 (IMR14_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR14 Write Access Policy 2 (IMR14_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR14 Write Access Policy 1 (IMR14_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR14 Write Access Policy 0 (IMR14_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR14 region, based on each agent's 6bit encoded SAI value.

44.3.97 IMR15 Base (B_CR_BIMR15BASE_0_0_0_MCHBAR)—Offset 6A50h

This register, along with IMR15MASK, IMR15RAC and IMR15WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR15RAC and IMR15WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A50h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR15 Base (IMR15_BASE):** Specifies bits 38:10 of the start address of IMR15 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR15MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR15 defined region.

44.3.98 IMR15 Mask (B_CR_BIMR15MASK_0_0_0_MCHBAR)—Offset 6A54h

This register, along with IMR15BASE, IMR15RAC and IMR15WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR15RAC and IMR15WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A54h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor, depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR15 Mask (IMR15_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR15BASE[28:0] value. A match indicates that the incoming address falls within the IMR15 region.

44.3.99 IMR15 Control Policy (B_CR_BIMR15CP_0_0_0_MCHBAR)—Offset 6A58h

This register controls the access policy to the Read Access Policy BIMR15RAC, the Write Access Policy BIMR15WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A58h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR15 Control Policy (IMR15_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR15RAC, BIMR15WAC and BIMR15CP registers, based on the value from each agent's 6bit SAI field.

44.3.100 IMR15 Read Access Policy (B_CR_BIMR15RAC_0_0_0_MCHBAR)—Offset 6A60h

This register, along with IMR15BASE, IMR15MASK and IMR15WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR15. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A60h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR15 Read Access Policy 63 (IMR15_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR15 Read Access Policy 62 (IMR15_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR15 Read Access Policy 61 (IMR15_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR15 Read Access Policy 60 (IMR15_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR15 Read Access Policy 59 (IMR15_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR15 Read Access Policy 58 (IMR15_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR15 Read Access Policy 57 (IMR15_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR15 Read Access Policy 56 (IMR15_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR15 Read Access Policy 55 (IMR15_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR15 Read Access Policy 54 (IMR15_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR15 Read Access Policy 53 (IMR15_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR15 Read Access Policy 52 (IMR15_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR15 Read Access Policy 51 (IMR15_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR15 Read Access Policy 50 (IMR15_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR15 Read Access Policy 49 (IMR15_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR15 Read Access Policy 48 (IMR15_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR15 Read Access Policy 47 (IMR15_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR15 Read Access Policy 46 (IMR15_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR15 Read Access Policy 45 (IMR15_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR15 Read Access Policy 44 (IMR15_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR15 Read Access Policy 43 (IMR15_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR15 Read Access Policy 42 (IMR15_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR15 Read Access Policy 41 (IMR15_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR15 Read Access Policy 40 (IMR15_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR15 Read Access Policy 39 (IMR15_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR15 Read Access Policy 38 (IMR15_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR15 Read Access Policy 37 (IMR15_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR15 Read Access Policy 36 (IMR15_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR15 Read Access Policy 35 (IMR15_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR15 Read Access Policy 34 (IMR15_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR15 Read Access Policy 33 (IMR15_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR15 Read Access Policy 32 (IMR15_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR15 Read Access Policy 31 (IMR15_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR15 Read Access Policy 30 (IMR15_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR15 Read Access Policy 29 (IMR15_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR15 Read Access Policy 28 (IMR15_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR15 Read Access Policy 27 (IMR15_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR15 Read Access Policy 26 (IMR15_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR15 Read Access Policy 25 (IMR15_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR15 Read Access Policy 24 (IMR15_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR15 Read Access Policy 23 (IMR15_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR15 Read Access Policy 22 (IMR15_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR15 Read Access Policy 21 (IMR15_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR15 Read Access Policy 20 (IMR15_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR15 Read Access Policy 19 (IMR15_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR15 Read Access Policy 18 (IMR15_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR15 Read Access Policy 17 (IMR15_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR15 Read Access Policy 16 (IMR15_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR15 Read Access Policy 15 (IMR15_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR15 Read Access Policy 14 (IMR15_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR15 Read Access Policy 13 (IMR15_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR15 Read Access Policy 12 (IMR15_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR15 Read Access Policy 11 (IMR15_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR15 Read Access Policy 10 (IMR15_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR15 Read Access Policy 9 (IMR15_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR15 Read Access Policy 8 (IMR15_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR15 Read Access Policy 7 (IMR15_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR15 Read Access Policy 6 (IMR15_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR15 Read Access Policy 5 (IMR15_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR15 Read Access Policy 4 (IMR15_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR15 Read Access Policy 3 (IMR15_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR15 Read Access Policy 2 (IMR15_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR15 Read Access Policy 1 (IMR15_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR15 Read Access Policy 0 (IMR15_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR15 region, based on each agent's 6bit encoded SAI value.

44.3.101 IMR15 Write Access Policy (B_CR_BIMR15WAC_0_0_0_MCHBAR)—Offset 6A68h

This register, along with IMR15BASE, IMR15MASK and IMR15RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR15. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A68h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR15 Write Access Policy 63 (IMR15_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR15 Write Access Policy 62 (IMR15_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR15 Write Access Policy 61 (IMR15_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR15 Write Access Policy 60 (IMR15_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR15 Write Access Policy 59 (IMR15_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR15 Write Access Policy 58 (IMR15_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR15 Write Access Policy 57 (IMR15_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR15 Write Access Policy 56 (IMR15_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR15 Write Access Policy 55 (IMR15_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR15 Write Access Policy 54 (IMR15_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR15 Write Access Policy 53 (IMR15_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR15 Write Access Policy 52 (IMR15_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR15 Write Access Policy 51 (IMR15_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR15 Write Access Policy 50 (IMR15_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR15 Write Access Policy 49 (IMR15_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR15 Write Access Policy 48 (IMR15_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR15 Write Access Policy 47 (IMR15_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR15 Write Access Policy 46 (IMR15_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR15 Write Access Policy 45 (IMR15_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR15 Write Access Policy 44 (IMR15_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR15 Write Access Policy 43 (IMR15_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR15 Write Access Policy 42 (IMR15_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR15 Write Access Policy 41 (IMR15_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR15 Write Access Policy 40 (IMR15_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR15 Write Access Policy 39 (IMR15_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR15 Write Access Policy 38 (IMR15_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR15 Write Access Policy 37 (IMR15_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR15 Write Access Policy 36 (IMR15_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR15 Write Access Policy 35 (IMR15_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR15 Write Access Policy 34 (IMR15_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR15 Write Access Policy 33 (IMR15_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR15 Write Access Policy 32 (IMR15_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR15 Write Access Policy 31 (IMR15_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR15 Write Access Policy 30 (IMR15_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR15 Write Access Policy 29 (IMR15_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR15 Write Access Policy 28 (IMR15_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR15 Write Access Policy 27 (IMR15_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR15 Write Access Policy 26 (IMR15_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR15 Write Access Policy 25 (IMR15_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR15 Write Access Policy 24 (IMR15_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR15 Write Access Policy 23 (IMR15_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR15 Write Access Policy 22 (IMR15_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR15 Write Access Policy 21 (IMR15_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR15 Write Access Policy 20 (IMR15_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR15 Write Access Policy 19 (IMR15_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR15 Write Access Policy 18 (IMR15_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR15 Write Access Policy 17 (IMR15_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR15 Write Access Policy 16 (IMR15_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR15 Write Access Policy 15 (IMR15_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR15 Write Access Policy 14 (IMR15_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR15 Write Access Policy 13 (IMR15_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR15 Write Access Policy 12 (IMR15_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR15 Write Access Policy 11 (IMR15_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR15 Write Access Policy 10 (IMR15_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR15 Write Access Policy 9 (IMR15_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR15 Write Access Policy 8 (IMR15_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR15 Write Access Policy 7 (IMR15_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR15 Write Access Policy 6 (IMR15_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR15 Write Access Policy 5 (IMR15_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR15 Write Access Policy 4 (IMR15_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR15 Write Access Policy 3 (IMR15_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR15 Write Access Policy 2 (IMR15_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR15 Write Access Policy 1 (IMR15_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR15 Write Access Policy 0 (IMR15_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR15 region, based on each agent's 6bit encoded SAI value.

44.3.102 IMR16 Base (B_CR_BIMR16BASE_0_0_0_MCHBAR)—Offset 6A70h

This register, along with IMR16MASK, IMR16RAC and IMR16WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR16RAC and IMR16WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A70h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR16 Base (IMR16_BASE):** Specifies bits 38:10 of the start address of IMR16 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR16MASK[28:0] applied to bits 38:10 of the incoming address, to determine if an access falls within the IMR16 defined region.

44.3.103 IMR16 Mask (B_CR_BIMR16MASK_0_0_0_MCHBAR)—Offset 6A74h

This register, along with IMR16BASE, IMR16RAC and IMR16WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR16RAC and IMR16WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A74h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback data HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR16 Mask (IMR16_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR16BASE[28:0] value. A match indicates that the incoming address falls within the IMR16 region.

44.3.104 IMR16 Control Policy (B_CR_BIMR16CP_0_0_0_MCHBAR)—Offset 6A78h

This register controls the access policy to the Read Access Policy BIMR16RAC, the Write Access Policy BIMR16WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A78h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR16 Control Policy (IMR16_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR16RAC, BIMR16WAC and BIMR16CP registers, based on the value from each agent's 6bit SAI field.

44.3.105 IMR16 Read Access Policy (B_CR_BIMR16RAC_0_0_0_MCHBAR)—Offset 6A80h

This register, along with IMR16BASE, IMR16MASK and IMR16WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR16. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A80h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR16 Read Access Policy 63 (IMR16_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR16 Read Access Policy 62 (IMR16_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR16 Read Access Policy 61 (IMR16_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR16 Read Access Policy 60 (IMR16_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR16 Read Access Policy 59 (IMR16_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR16 Read Access Policy 58 (IMR16_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR16 Read Access Policy 57 (IMR16_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR16 Read Access Policy 56 (IMR16_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR16 Read Access Policy 55 (IMR16_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR16 Read Access Policy 54 (IMR16_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR16 Read Access Policy 53 (IMR16_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR16 Read Access Policy 52 (IMR16_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR16 Read Access Policy 51 (IMR16_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR16 Read Access Policy 50 (IMR16_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR16 Read Access Policy 49 (IMR16_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR16 Read Access Policy 48 (IMR16_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR16 Read Access Policy 47 (IMR16_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR16 Read Access Policy 46 (IMR16_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR16 Read Access Policy 45 (IMR16_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR16 Read Access Policy 44 (IMR16_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR16 Read Access Policy 43 (IMR16_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR16 Read Access Policy 42 (IMR16_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR16 Read Access Policy 41 (IMR16_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR16 Read Access Policy 40 (IMR16_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR16 Read Access Policy 39 (IMR16_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR16 Read Access Policy 38 (IMR16_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR16 Read Access Policy 37 (IMR16_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR16 Read Access Policy 36 (IMR16_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR16 Read Access Policy 35 (IMR16_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR16 Read Access Policy 34 (IMR16_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR16 Read Access Policy 33 (IMR16_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR16 Read Access Policy 32 (IMR16_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR16 Read Access Policy 31 (IMR16_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR16 Read Access Policy 30 (IMR16_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR16 Read Access Policy 29 (IMR16_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR16 Read Access Policy 28 (IMR16_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR16 Read Access Policy 27 (IMR16_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR16 Read Access Policy 26 (IMR16_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR16 Read Access Policy 25 (IMR16_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR16 Read Access Policy 24 (IMR16_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR16 Read Access Policy 23 (IMR16_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR16 Read Access Policy 22 (IMR16_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR16 Read Access Policy 21 (IMR16_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR16 Read Access Policy 20 (IMR16_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR16 Read Access Policy 19 (IMR16_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR16 Read Access Policy 18 (IMR16_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR16 Read Access Policy 17 (IMR16_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR16 Read Access Policy 16 (IMR16_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR16 Read Access Policy 15 (IMR16_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR16 Read Access Policy 14 (IMR16_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR16 Read Access Policy 13 (IMR16_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR16 Read Access Policy 12 (IMR16_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR16 Read Access Policy 11 (IMR16_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR16 Read Access Policy 10 (IMR16_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR16 Read Access Policy 9 (IMR16_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR16 Read Access Policy 8 (IMR16_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR16 Read Access Policy 7 (IMR16_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR16 Read Access Policy 6 (IMR16_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR16 Read Access Policy 5 (IMR16_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR16 Read Access Policy 4 (IMR16_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR16 Read Access Policy 3 (IMR16_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR16 Read Access Policy 2 (IMR16_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR16 Read Access Policy 1 (IMR16_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR16 Read Access Policy 0 (IMR16_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR16 region, based on each agent's 6bit encoded SAI value.

44.3.106 IMR16 Write Access Policy (B_CR_BIMR16WAC_0_0_0_MCHBAR)—Offset 6A88h

This register, along with IMR16BASE, IMR16MASK and IMR16RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR16. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A88h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR16 Write Access Policy 63 (IMR16_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR16 Write Access Policy 62 (IMR16_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR16 Write Access Policy 61 (IMR16_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR16 Write Access Policy 60 (IMR16_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR16 Write Access Policy 59 (IMR16_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR16 Write Access Policy 58 (IMR16_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR16 Write Access Policy 57 (IMR16_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR16 Write Access Policy 56 (IMR16_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR16 Write Access Policy 55 (IMR16_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR16 Write Access Policy 54 (IMR16_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR16 Write Access Policy 53 (IMR16_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR16 Write Access Policy 52 (IMR16_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR16 Write Access Policy 51 (IMR16_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR16 Write Access Policy 50 (IMR16_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR16 Write Access Policy 49 (IMR16_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR16 Write Access Policy 48 (IMR16_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR16 Write Access Policy 47 (IMR16_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR16 Write Access Policy 46 (IMR16_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR16 Write Access Policy 45 (IMR16_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR16 Write Access Policy 44 (IMR16_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR16 Write Access Policy 43 (IMR16_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR16 Write Access Policy 42 (IMR16_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR16 Write Access Policy 41 (IMR16_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR16 Write Access Policy 40 (IMR16_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR16 Write Access Policy 39 (IMR16_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR16 Write Access Policy 38 (IMR16_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR16 Write Access Policy 37 (IMR16_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR16 Write Access Policy 36 (IMR16_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR16 Write Access Policy 35 (IMR16_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR16 Write Access Policy 34 (IMR16_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR16 Write Access Policy 33 (IMR16_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR16 Write Access Policy 32 (IMR16_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR16 Write Access Policy 31 (IMR16_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR16 Write Access Policy 30 (IMR16_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR16 Write Access Policy 29 (IMR16_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR16 Write Access Policy 28 (IMR16_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR16 Write Access Policy 27 (IMR16_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR16 Write Access Policy 26 (IMR16_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR16 Write Access Policy 25 (IMR16_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR16 Write Access Policy 24 (IMR16_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR16 Write Access Policy 23 (IMR16_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR16 Write Access Policy 22 (IMR16_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR16 Write Access Policy 21 (IMR16_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR16 Write Access Policy 20 (IMR16_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR16 Write Access Policy 19 (IMR16_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR16 Write Access Policy 18 (IMR16_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR16 Write Access Policy 17 (IMR16_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR16 Write Access Policy 16 (IMR16_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR16 Write Access Policy 15 (IMR16_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR16 Write Access Policy 14 (IMR16_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR16 Write Access Policy 13 (IMR16_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR16 Write Access Policy 12 (IMR16_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR16 Write Access Policy 11 (IMR16_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR16 Write Access Policy 10 (IMR16_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR16 Write Access Policy 9 (IMR16_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR16 Write Access Policy 8 (IMR16_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR16 Write Access Policy 7 (IMR16_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR16 Write Access Policy 6 (IMR16_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR16 Write Access Policy 5 (IMR16_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR16 Write Access Policy 4 (IMR16_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR16 Write Access Policy 3 (IMR16_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR16 Write Access Policy 2 (IMR16_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR16 Write Access Policy 1 (IMR16_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR16 Write Access Policy 0 (IMR16_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR16 region, based on each agent's 6bit encoded SAI value.

44.3.107 IMR17 Base (B_CR_BIMR17BASE_0_0_0_MCHBAR)—Offset 6A90h

This register, along with IMR17MASK, IMR17RAC and IMR17WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR17RAC and IMR17WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A90h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR17BASE (IMR17_BASE):** Specifies bits 38:10 of the start address of IMR17 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR17MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR17 defined region.

44.3.108 IMR17 Mask (B_CR_BIMR17MASK_0_0_0_MCHBAR)—Offset 6A94h

This register, along with IMR17BASE, IMR17RAC and IMR17WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR17RAC and IMR17WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6A94h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor, depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR17 Mask (IMR17_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR17BASE[28:0] value. A match indicates that the incoming address falls within the IMR17 region.

44.3.109 IMR17 Control Policy (B_CR_BIMR17CP_0_0_0_MCHBAR)—Offset 6A98h

This register controls the access policy to the Read Access Policy BIMR17RAC, the Write Access Policy BIMR17WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6A98h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR17 Control Policy (IMR17_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR17RAC, BIMR17WAC and BIMR17CP registers, based on the value from each agent's 6bit SAI field.

44.3.110 IMR17 Read Access Policy (B_CR_BIMR17RAC_0_0_0_MCHBAR)—Offset 6AA0h

This register, along with IMR17BASE, IMR17MASK and IMR17WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR17. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AA0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR17 Read Access Policy 63 (IMR17_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR17 Read Access Policy 62 (IMR17_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR17 Read Access Policy 61 (IMR17_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR17 Read Access Policy 60 (IMR17_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR17 Read Access Policy 59 (IMR17_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR17 Read Access Policy 58 (IMR17_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR17 Read Access Policy 57 (IMR17_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR17 Read Access Policy 56 (IMR17_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR17 Read Access Policy 55 (IMR17_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR17 Read Access Policy 54 (IMR17_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR17 Read Access Policy 53 (IMR17_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR17 Read Access Policy 52 (IMR17_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR17 Read Access Policy 51 (IMR17_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR17 Read Access Policy 50 (IMR17_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR17 Read Access Policy 49 (IMR17_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR17 Read Access Policy 48 (IMR17_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR17 Read Access Policy 47 (IMR17_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR17 Read Access Policy 46 (IMR17_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR17 Read Access Policy 45 (IMR17_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR17 Read Access Policy 44 (IMR17_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR17 Read Access Policy 43 (IMR17_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR17 Read Access Policy 42 (IMR17_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR17 Read Access Policy 41 (IMR17_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR17 Read Access Policy 40 (IMR17_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR17 Read Access Policy 39 (IMR17_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR17 Read Access Policy 38 (IMR17_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR17 Read Access Policy 37 (IMR17_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR17 Read Access Policy 36 (IMR17_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR17 Read Access Policy 35 (IMR17_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR17 Read Access Policy 34 (IMR17_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR17 Read Access Policy 33 (IMR17_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR17 Read Access Policy 32 (IMR17_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR17 Read Access Policy 31 (IMR17_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR17 Read Access Policy 30 (IMR17_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR17 Read Access Policy 29 (IMR17_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR17 Read Access Policy 28 (IMR17_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR17 Read Access Policy 27 (IMR17_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR17 Read Access Policy 26 (IMR17_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR17 Read Access Policy 25 (IMR17_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR17 Read Access Policy 24 (IMR17_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR17 Read Access Policy 23 (IMR17_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR17 Read Access Policy 22 (IMR17_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR17 Read Access Policy 21 (IMR17_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR17 Read Access Policy 20 (IMR17_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR17 Read Access Policy 19 (IMR17_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR17 Read Access Policy 18 (IMR17_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR17 Read Access Policy 17 (IMR17_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR17 Read Access Policy 16 (IMR17_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR17 Read Access Policy 15 (IMR17_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR17 Read Access Policy 14 (IMR17_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR17 Read Access Policy 13 (IMR17_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR17 Read Access Policy 12 (IMR17_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR17 Read Access Policy 11 (IMR17_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR17 Read Access Policy 10 (IMR17_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR17 Read Access Policy 9 (IMR17_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR17 Read Access Policy 8 (IMR17_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR17 Read Access Policy 7 (IMR17_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR17 Read Access Policy 6 (IMR17_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR17 Read Access Policy 5 (IMR17_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR17 Read Access Policy 4 (IMR17_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR17 Read Access Policy 3 (IMR17_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR17 Read Access Policy 2 (IMR17_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR17 Read Access Policy 1 (IMR17_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR17 Read Access Policy 0 (IMR17_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR17 region, based on each agent's 6bit encoded SAI value.

44.3.111 IMR17 Write Access Policy (B_CR_BIMR17WAC_0_0_0_MCHBAR)—Offset 6AA8h

This register, along with IMR17BASE, IMR17MASK and IMR17RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with a SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR17. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AA8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR17 Write Access Policy 63 (IMR17_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR17 Write Access Policy 62 (IMR17_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR17 Write Access Policy 61 (IMR17_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR17 Write Access Policy 60 (IMR17_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR17 Write Access Policy 59 (IMR17_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR17 Write Access Policy 58 (IMR17_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR17 Write Access Policy 57 (IMR17_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR17 Write Access Policy 56 (IMR17_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR17 Write Access Policy 55 (IMR17_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR17 Write Access Policy 54 (IMR17_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR17 Write Access Policy 53 (IMR17_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR17 Write Access Policy 52 (IMR17_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR17 Write Access Policy 51 (IMR17_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR17 Write Access Policy 50 (IMR17_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR17 Write Access Policy 49 (IMR17_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR17 Write Access Policy 48 (IMR17_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR17 Write Access Policy 47 (IMR17_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR17 Write Access Policy 46 (IMR17_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR17 Write Access Policy 45 (IMR17_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR17 Write Access Policy 44 (IMR17_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR17 Write Access Policy 43 (IMR17_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR17 Write Access Policy 42 (IMR17_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR17 Write Access Policy 41 (IMR17_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR17 Write Access Policy 40 (IMR17_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR17 Write Access Policy 39 (IMR17_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR17 Write Access Policy 38 (IMR17_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR17 Write Access Policy 37 (IMR17_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR17 Write Access Policy 36 (IMR17_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR17 Write Access Policy 35 (IMR17_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR17 Write Access Policy 34 (IMR17_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR17 Write Access Policy 33 (IMR17_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR17 Write Access Policy 32 (IMR17_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR17 Write Access Policy 31 (IMR17_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR17 Write Access Policy 30 (IMR17_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR17 Write Access Policy 29 (IMR17_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR17 Write Access Policy 28 (IMR17_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR17 Write Access Policy 27 (IMR17_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR17 Write Access Policy 26 (IMR17_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR17 Write Access Policy 25 (IMR17_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR17 Write Access Policy 24 (IMR17_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR17 Write Access Policy 23 (IMR17_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR17 Write Access Policy 22 (IMR17_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR17 Write Access Policy 21 (IMR17_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR17 Write Access Policy 20 (IMR17_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR17 Write Access Policy 19 (IMR17_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR17 Write Access Policy 18 (IMR17_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR17 Write Access Policy 17 (IMR17_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR17 Write Access Policy 16 (IMR17_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR17 Write Access Policy 15 (IMR17_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR17 Write Access Policy 14 (IMR17_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR17 Write Access Policy 13 (IMR17_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR17 Write Access Policy 12 (IMR17_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR17 Write Access Policy 11 (IMR17_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR17 Write Access Policy 10 (IMR17_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR17 Write Access Policy 9 (IMR17_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR17 Write Access Policy 8 (IMR17_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR17 Write Access Policy 7 (IMR17_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR17 Write Access Policy 6 (IMR17_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR17 Write Access Policy 5 (IMR17_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR17 Write Access Policy 4 (IMR17_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR17 Write Access Policy 3 (IMR17_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR17 Write Access Policy 2 (IMR17_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR17 Write Access Policy 1 (IMR17_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR17 Write Access Policy 0 (IMR17_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR17 region, based on each agent's 6bit encoded SAI value.

44.3.112 IMR18 Base (B_CR_BIMR18BASE_0_0_0_MCHBAR)—Offset 6AB0h

This register, along with IMR18MASK, IMR18RAC and IMR18WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation, if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR18RAC and IMR18WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6AB0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR18 Base (IMR18_BASE):** Specifies bits 38:10 of the start address of IMR18 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR18MASK[28:0] applied to bits 38:10 of the incoming address, to determine if an access falls within the IMR18 defined region.

44.3.113 IMR18 Mask (B_CR_BIMR18MASK_0_0_0_MCHBAR)—Offset 6AB4h

This register, along with IMR18BASE, IMR18RAC and IMR18WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR18RAC and IMR18WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6AB4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback data HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit Writeback Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR18 Mask (IMR18_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR18BASE[28:0] value. A match indicates that the incoming address falls within the IMR18 region.

44.3.114 IMR18 Control Policy (B_CR_BIMR18CP_0_0_0_MCHBAR)—Offset 6AB8h

This register controls the access policy to the Read Access Policy BIMR18RAC, the Write Access Policy BIMR18WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AB8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR18 Control Policy (IMR18_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR18RAC, BIMR18WAC and BIMR18CP registers, based on the value from each agent's 6bit SAI field.

44.3.115 IMR18 Read Access Policy (B_CR_BIMR18RAC_0_0_0_MCHBAR)—Offset 6AC0h

This register, along with IMR18BASE, IMR18MASK and IMR18WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR18. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AC0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR18 Read Access Policy 63 (IMR18_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR18 Read Access Policy 62 (IMR18_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR18 Read Access Policy 61 (IMR18_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR18 Read Access Policy 60 (IMR18_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR18 Read Access Policy 59 (IMR18_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR18 Read Access Policy 58 (IMR18_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR18 Read Access Policy 57 (IMR18_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR18 Read Access Policy 56 (IMR18_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR18 Read Access Policy 55 (IMR18_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR18 Read Access Policy 54 (IMR18_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR18 Read Access Policy 53 (IMR18_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR18 Read Access Policy 52 (IMR18_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR18 Read Access Policy 51 (IMR18_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR18 Read Access Policy 50 (IMR18_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR18 Read Access Policy 49 (IMR18_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR18 Read Access Policy 48 (IMR18_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR18 Read Access Policy 47 (IMR18_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR18 Read Access Policy 46 (IMR18_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR18 Read Access Policy 45 (IMR18_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR18 Read Access Policy 44 (IMR18_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR18 Read Access Policy 43 (IMR18_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR18 Read Access Policy 42 (IMR18_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR18 Read Access Policy 41 (IMR18_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR18 Read Access Policy 40 (IMR18_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR18 Read Access Policy 39 (IMR18_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR18 Read Access Policy 38 (IMR18_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR18 Read Access Policy 37 (IMR18_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR18 Read Access Policy 36 (IMR18_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR18 Read Access Policy 35 (IMR18_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR18 Read Access Policy 34 (IMR18_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR18 Read Access Policy 33 (IMR18_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR18 Read Access Policy 32 (IMR18_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR18 Read Access Policy 31 (IMR18_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR18 Read Access Policy 30 (IMR18_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR18 Read Access Policy 29 (IMR18_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR18 Read Access Policy 28 (IMR18_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR18 Read Access Policy 27 (IMR18_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR18 Read Access Policy 26 (IMR18_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR18 Read Access Policy 25 (IMR18_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR18 Read Access Policy 24 (IMR18_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR18 Read Access Policy 23 (IMR18_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR18 Read Access Policy 22 (IMR18_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR18 Read Access Policy 21 (IMR18_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR18 Read Access Policy 20 (IMR18_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR18 Read Access Policy 19 (IMR18_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR18 Read Access Policy 18 (IMR18_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR18 Read Access Policy 17 (IMR18_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR18 Read Access Policy 16 (IMR18_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR18 Read Access Policy 15 (IMR18_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR18 Read Access Policy 14 (IMR18_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR18 Read Access Policy 13 (IMR18_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR18 Read Access Policy 12 (IMR18_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR18 Read Access Policy 11 (IMR18_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR18 Read Access Policy 10 (IMR18_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR18 Read Access Policy 9 (IMR18_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR18 Read Access Policy 8 (IMR18_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR18 Read Access Policy 7 (IMR18_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR18 Read Access Policy 6 (IMR18_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR18 Read Access Policy 5 (IMR18_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR18 Read Access Policy 4 (IMR18_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR18 Read Access Policy 3 (IMR18_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR18 Read Access Policy 2 (IMR18_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR18 Read Access Policy 1 (IMR18_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR18 Read Access Policy 0 (IMR18_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR18 region, based on each agent's 6bit encoded SAI value.

44.3.116 IMR18 Write Access Policy (B_CR_BIMR18WAC_0_0_0_MCHBAR)—Offset 6AC8h

This register, along with IMR18BASE, IMR18MASK and IMR18RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR18. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AC8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR18_WRITE_POL_63:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR18_WRITE_POL_62:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR18_WRITE_POL_61:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR18_WRITE_POL_60:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR18_WRITE_POL_59:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR18_WRITE_POL_58:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR18_WRITE_POL_57:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR18_WRITE_POL_56:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR18_WRITE_POL_55:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR18_WRITE_POL_54:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR18_WRITE_POL_53:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR18_WRITE_POL_52:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR18_WRITE_POL_51:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR18_WRITE_POL_50:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR18_WRITE_POL_49:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR18_WRITE_POL_48:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR18_WRITE_POL_47:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR18_WRITE_POL_46:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR18_WRITE_POL_45:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR18_WRITE_POL_44:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR18_WRITE_POL_43:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR18_WRITE_POL_42:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR18_WRITE_POL_41:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR18_WRITE_POL_40:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR18_WRITE_POL_39:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR18_WRITE_POL_38:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR18_WRITE_POL_37:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR18_WRITE_POL_36:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR18_WRITE_POL_35:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR18_WRITE_POL_34:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR18_WRITE_POL_33:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR18_WRITE_POL_32:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR18_WRITE_POL_31:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR18_WRITE_POL_30:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR18_WRITE_POL_29:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR18_WRITE_POL_28:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR18_WRITE_POL_27:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR18_WRITE_POL_26:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR18_WRITE_POL_25:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR18_WRITE_POL_24:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR18_WRITE_POL_23:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR18_WRITE_POL_22:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR18_WRITE_POL_21:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR18_WRITE_POL_20:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR18_WRITE_POL_19:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR18_WRITE_POL_18:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR18_WRITE_POL_17:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR18_WRITE_POL_16:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR18_WRITE_POL_15:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR18_WRITE_POL_14:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR18_WRITE_POL_13:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR18_WRITE_POL_12:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR18_WRITE_POL_11:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR18_WRITE_POL_10:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR18_WRITE_POL_9:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR18_WRITE_POL_8:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR18_WRITE_POL_7:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR18_WRITE_POL_6:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR18_WRITE_POL_5:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR18_WRITE_POL_4:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR18_WRITE_POL_3:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR18_WRITE_POL_2:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR18_WRITE_POL_1:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR18_WRITE_POL_0:** B-Unit IMR18 Write Access Policy: Bit vector used to determine which agents are allowed write access to the IMR18 region, based on each agent's 6bit encoded SAI value.

44.3.117 IMR19 Base (B_CR_BIMR19BASE_0_0_0_MCHBAR)—Offset 6AD0h

This register, along with IMR19MASK, IMR19RAC and IMR19WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR19RAC and IMR19WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6AD0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**IMR Enable (IMR_EN):** Enables access checking for the IMR region.
30	0x0 RW	**Asset Classification AC[0]: Trace Enable (TR_EN):** Enables snooping of transactions to the IMR region by tracing agents.
29	0x0 RO	**RESERVED_1:** Reserved
28:0	0x0 RW	**Base 0 IMR19 Base (IMR19_BASE):** Specifies bits 38:10 of the start address of IMR19 region. IMR region size must be a strict poweroftwo, at least 1KB, and naturally aligned to the size. These bits are compared with the result of the IMR19MASK[28:0] applied to bits 38:10 of the incoming address to determine if an access falls within the IMR19 defined region.

44.3.118 IMR19 Mask (B_CR_BIMR19MASK_0_0_0_MCHBAR)—Offset 6AD4h

This register, along with IMR19BASE, IMR19RAC and IMR19WAC, defines an isolated region of memory that can be masked to prohibit certain system agents from accessing memory. When an agent sends a request to the B-Unit, whether snooped or not, an IMR may optionally prevent that transaction from changing the state of memory or from getting correct data in response to the operation if the agent's SAI field does not specify the correct Policy. The IMR's Policy is configured by the IMR19RAC and IMR19WAC registers.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6AD4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Asset Classification AC[2]: GT Implicit Writeback Enable (GT_IWB_EN):** Enables implicit writebacks to protected region from GT caching agent. When set to 1, enables implicit writeback data HITM data from GT to be returned to the requestor. When set to 0, inhibits HITM data from GT from being returned to the requestor. HITM data from IA cores may be returned to the requestor depending on the setting of the IA_IWB_EN bit.
30	0x0 RW	**Asset Classification AC[1]: IA Implicit WB Enable (IA_IWB_EN):** Enables implicit writebacks to protected region from IA caching agent. When set to 1, enables implicit writeback data HITM data from IA cores to be returned to the requestor. When set to 0, inhibits HITM data from IA cores from being returned to the requestor. HITM data from GT may be returned to the requestor depending on the setting of the GT_IWB_EN bit.
29	0x0 RO	**RESERVED_0:** Reserved
28:0	0x0 RW	**Mask 0 IMR19 Mask (IMR19_MASK):** These bits are ANDed with bits 38:10 of the incoming address to determine if the combined result matches the IMR19BASE[28:0] value. A match indicates that the incoming address falls within the IMR19 region.

44.3.119 IMR19 Control Policy (B_CR_BIMR19CP_0_0_0_MCHBAR)—Offset 6AD8h

This register controls the access policy to the Read Access Policy BIMR19RAC, the Write Access Policy BIMR19WAC, and, self-referentially, to itself. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine both read access and write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AD8h

Default: 00000C0061010202h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0xc0061010202 RW	**IMR19 Control Policy (IMR19_CTRL_POL):** Bit vector used to determine which agents are allowed access to the BIMR19RAC, BIMR19WAC, BIMR19CP registers, based on the value from each agent's 6bit SAI field.

44.3.120 IMR19 Read Access Policy (B_CR_BIMR19RAC_0_0_0_MCHBAR)—Offset 6AE0h

This register, along with IMR19BASE, IMR19MASK and IMR19WAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR19. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine read access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AE0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR19 Read Access Policy 63 (IMR19_READ_POL_63):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR19 Read Access Policy 62 (IMR19_READ_POL_62):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR19 Read Access Policy 61 (IMR19_READ_POL_61):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR19 Read Access Policy 60 (IMR19_READ_POL_60):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR19 Read Access Policy 59 (IMR19_READ_POL_59):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR19 Read Access Policy 58 (IMR19_READ_POL_58):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR19 Read Access Policy 57 (IMR19_READ_POL_57):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR19 Read Access Policy 56 (IMR19_READ_POL_56):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR19 Read Access Policy 55 (IMR19_READ_POL_55):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR19 Read Access Policy 54 (IMR19_READ_POL_54):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR19 Read Access Policy 53 (IMR19_READ_POL_53):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR19 Read Access Policy 52 (IMR19_READ_POL_52):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR19 Read Access Policy 51 (IMR19_READ_POL_51):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR19 Read Access Policy 50 (IMR19_READ_POL_50):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR19 Read Access Policy 49 (IMR19_READ_POL_49):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR19 Read Access Policy 48 (IMR19_READ_POL_48):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR19 Read Access Policy 47 (IMR19_READ_POL_47):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR19 Read Access Policy 46 (IMR19_READ_POL_46):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR19 Read Access Policy 45 (IMR19_READ_POL_45):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR19 Read Access Policy 44 (IMR19_READ_POL_44):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR19 Read Access Policy 43 (IMR19_READ_POL_43):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR19 Read Access Policy 42 (IMR19_READ_POL_42):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR19 Read Access Policy 41 (IMR19_READ_POL_41):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR19 Read Access Policy 40 (IMR19_READ_POL_40):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR19 Read Access Policy 39 (IMR19_READ_POL_39):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR19 Read Access Policy 38 (IMR19_READ_POL_38):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR19 Read Access Policy 37 (IMR19_READ_POL_37):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR19 Read Access Policy 36 (IMR19_READ_POL_36):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR19 Read Access Policy 35 (IMR19_READ_POL_35):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR19 Read Access Policy 34 (IMR19_READ_POL_34):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR19 Read Access Policy 33 (IMR19_READ_POL_33):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR19 Read Access Policy 32 (IMR19_READ_POL_32):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR19 Read Access Policy 31 (IMR19_READ_POL_31):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR19 Read Access Policy 30 (IMR19_READ_POL_30):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR19 Read Access Policy 29 (IMR19_READ_POL_29):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR19 Read Access Policy 28 (IMR19_READ_POL_28):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR19 Read Access Policy 27 (IMR19_READ_POL_27):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR19 Read Access Policy 26 (IMR19_READ_POL_26):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR19 Read Access Policy 25 (IMR19_READ_POL_25):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR19 Read Access Policy 24 (IMR19_READ_POL_24):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR19 Read Access Policy 23 (IMR19_READ_POL_23):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR19 Read Access Policy 22 (IMR19_READ_POL_22):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR19 Read Access Policy 21 (IMR19_READ_POL_21):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR19 Read Access Policy 20 (IMR19_READ_POL_20):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR19 Read Access Policy 19 (IMR19_READ_POL_19):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR19 Read Access Policy 18 (IMR19_READ_POL_18):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR19 Read Access Policy 17 (IMR19_READ_POL_17):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR19 Read Access Policy 16 (IMR19_READ_POL_16):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR19 Read Access Policy 15 (IMR19_READ_POL_15):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR19 Read Access Policy 14 (IMR19_READ_POL_14):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR19 Read Access Policy 13 (IMR19_READ_POL_13):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR19 Read Access Policy 12 (IMR19_READ_POL_12):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR19 Read Access Policy 11 (IMR19_READ_POL_11):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR19 Read Access Policy 10 (IMR19_READ_POL_10):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR19 Read Access Policy 9 (IMR19_READ_POL_9):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR19 Read Access Policy 8 (IMR19_READ_POL_8):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR19 Read Access Policy 7 (IMR19_READ_POL_7):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR19 Read Access Policy 6 (IMR19_READ_POL_6):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR19 Read Access Policy 5 (IMR19_READ_POL_5):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR19 Read Access Policy 4 (IMR19_READ_POL_4):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR19 Read Access Policy 3 (IMR19_READ_POL_3):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR19 Read Access Policy 2 (IMR19_READ_POL_2):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR19 Read Access Policy 1 (IMR19_READ_POL_1):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR19 Read Access Policy 0 (IMR19_READ_POL_0):** Bit vector used to determine which agents are allowed read access to the IMR19 region, based on each agent's 6bit encoded SAI value.

44.3.121 IMR19 Write Access Policy (B_CR_BIMR19WAC_0_0_0_MCHBAR)—Offset 6AE8h

This register, along with IMR19BASE, IMR19MASK and IMR19RAC, defines an isolated region of memory that can be masked to prohibit certain agents from accessing memory. It is programmed with an SAI Policy that indicates which agents in the system are allowed to perform read operations to IMR19. The requesting agent's 6bit encoded SAI value is used as an index into this register's bits to determine write access.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6AE8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW	**IMR19 Write Access Policy 63 (IMR19_WRITE_POL_63):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
62	0x0 RO	**IMR19 Write Access Policy 62 (IMR19_WRITE_POL_62):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
61	0x0 RO	**IMR19 Write Access Policy 61 (IMR19_WRITE_POL_61):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
60	0x0 RO	**IMR19 Write Access Policy 60 (IMR19_WRITE_POL_60):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
59	0x0 RO	**IMR19 Write Access Policy 59 (IMR19_WRITE_POL_59):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
58	0x0 RO	**IMR19 Write Access Policy 58 (IMR19_WRITE_POL_58):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
57	0x0 RO	**IMR19 Write Access Policy 57 (IMR19_WRITE_POL_57):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
56	0x0 RW	**IMR19 Write Access Policy 56 (IMR19_WRITE_POL_56):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
55	0x0 RW	**IMR19 Write Access Policy 55 (IMR19_WRITE_POL_55):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
54	0x0 RW	**IMR19 Write Access Policy 54 (IMR19_WRITE_POL_54):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
53	0x0 RO	**IMR19 Write Access Policy 53 (IMR19_WRITE_POL_53):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
52	0x0 RO	**IMR19 Write Access Policy 52 (IMR19_WRITE_POL_52):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
51	0x0 RO	**IMR19 Write Access Policy 51 (IMR19_WRITE_POL_51):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
50	0x0 RW	**IMR19 Write Access Policy 50 (IMR19_WRITE_POL_50):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
49	0x0 RW	**IMR19 Write Access Policy 49 (IMR19_WRITE_POL_49):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
48	0x0 RW	**IMR19 Write Access Policy 48 (IMR19_WRITE_POL_48):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
47	0x0 RO	**IMR19 Write Access Policy 47 (IMR19_WRITE_POL_47):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
46	0x0 RO	**IMR19 Write Access Policy 46 (IMR19_WRITE_POL_46):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
45	0x0 RO	**IMR19 Write Access Policy 45 (IMR19_WRITE_POL_45):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
44	0x0 RW	**IMR19 Write Access Policy 44 (IMR19_WRITE_POL_44):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
43	0x0 RW	**IMR19 Write Access Policy 43 (IMR19_WRITE_POL_43):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
42	0x0 RW	**IMR19 Write Access Policy 42 (IMR19_WRITE_POL_42):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
41	0x0 RW	**IMR19 Write Access Policy 41 (IMR19_WRITE_POL_41):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
40	0x0 RW	**IMR19 Write Access Policy 40 (IMR19_WRITE_POL_40):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
39	0x0 RO	**IMR19 Write Access Policy 39 (IMR19_WRITE_POL_39):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
38	0x0 RW	**IMR19 Write Access Policy 38 (IMR19_WRITE_POL_38):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
37	0x0 RO	**IMR19 Write Access Policy 37 (IMR19_WRITE_POL_37):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
36	0x0 RW	**IMR19 Write Access Policy 36 (IMR19_WRITE_POL_36):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
35	0x0 RO	**IMR19 Write Access Policy 35 (IMR19_WRITE_POL_35):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
34	0x0 RW	**IMR19 Write Access Policy 34 (IMR19_WRITE_POL_34):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
33	0x0 RW	**IMR19 Write Access Policy 33 (IMR19_WRITE_POL_33):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
32	0x0 RW	**IMR19 Write Access Policy 32 (IMR19_WRITE_POL_32):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
31	0x0 RO	**IMR19 Write Access Policy 31 (IMR19_WRITE_POL_31):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
30	0x0 RW	**IMR19 Write Access Policy 30 (IMR19_WRITE_POL_30):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
29	0x0 RW	**IMR19 Write Access Policy 29 (IMR19_WRITE_POL_29):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
28	0x0 RW	**IMR19 Write Access Policy 28 (IMR19_WRITE_POL_28):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
27	0x0 RW	**IMR19 Write Access Policy 27 (IMR19_WRITE_POL_27):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
26	0x0 RW	**IMR19 Write Access Policy 26 (IMR19_WRITE_POL_26):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
25	0x0 RW	**IMR19 Write Access Policy 25 (IMR19_WRITE_POL_25):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
24	0x0 RW	**IMR19 Write Access Policy 24 (IMR19_WRITE_POL_24):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
23	0x0 RO	**IMR19 Write Access Policy 23 (IMR19_WRITE_POL_23):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
22	0x0 RO	**IMR19 Write Access Policy 22 (IMR19_WRITE_POL_22):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.

Bit Range	Default & Access	Field Name (ID): Description
21	0x0 RW	**IMR19 Write Access Policy 21 (IMR19_WRITE_POL_21):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
20	0x0 RO	**IMR19 Write Access Policy 20 (IMR19_WRITE_POL_20):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
19	0x0 RO	**IMR19 Write Access Policy 19 (IMR19_WRITE_POL_19):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
18	0x0 RO	**IMR19 Write Access Policy 18 (IMR19_WRITE_POL_18):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
17	0x0 RW	**IMR19 Write Access Policy 17 (IMR19_WRITE_POL_17):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
16	0x0 RW	**IMR19 Write Access Policy 16 (IMR19_WRITE_POL_16):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
15	0x0 RO	**IMR19 Write Access Policy 15 (IMR19_WRITE_POL_15):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
14	0x0 RO	**IMR19 Write Access Policy 14 (IMR19_WRITE_POL_14):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
13	0x0 RW	**IMR19 Write Access Policy 13 (IMR19_WRITE_POL_13):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
12	0x0 RW	**IMR19 Write Access Policy 12 (IMR19_WRITE_POL_12):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
11	0x0 RO	**IMR19 Write Access Policy 11 (IMR19_WRITE_POL_11):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
10	0x0 RO	**IMR19 Write Access Policy 10 (IMR19_WRITE_POL_10):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
9	0x0 RO	**IMR19 Write Access Policy 9 (IMR19_WRITE_POL_9):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
8	0x0 RW	**IMR19 Write Access Policy 8 (IMR19_WRITE_POL_8):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
7	0x0 RO	**IMR19 Write Access Policy 7 (IMR19_WRITE_POL_7):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
6	0x0 RO	**IMR19 Write Access Policy 6 (IMR19_WRITE_POL_6):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
5	0x0 RW	**IMR19 Write Access Policy 5 (IMR19_WRITE_POL_5):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
4	0x0 RW	**IMR19 Write Access Policy 4 (IMR19_WRITE_POL_4):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
3	0x0 RW	**IMR19 Write Access Policy 3 (IMR19_WRITE_POL_3):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
2	0x0 RW	**IMR19 Write Access Policy 2 (IMR19_WRITE_POL_2):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
1	0x0 RW	**IMR19 Write Access Policy 1 (IMR19_WRITE_POL_1):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.
0	0x0 RW	**IMR19 Write Access Policy 0 (IMR19_WRITE_POL_0):** Bit vector used to determine which agents are allowed write access to the IMR19 region, based on each agent's 6bit encoded SAI value.

44.3.122 TPM Selector (B_CR_TPM_SELECTOR_0_0_0_MCHBAR)—Offset 6C24h

Specifies where the TPM lives in the platform. B-Unit uses this register to source decode for requests whose addresses fall within the fixed address range for the TPM.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6C24h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Reserved (RESERVED_0):** Reserved.
1:0	0x0 RW	**TPM Selector (TPM_SELECTOR):** • 0h: SoC doesn't support - fTPM enabled. Target of TPM accesses is the Intel ME. • 1h: SPI TPM enabled. Target of TPM accesses is SPI. • 2h: LPC TPM enabled. Target of TPM accesses is LPC. • 3h: All TPMs disabled. Target of TPM accesses is the Error Handler.

44.3.123 Default VTd BAR (B_CR_DEFVTDBAR_0_0_0_MCHBAR)—Offset 6C80h

BIOS must write DEFVTDBAR and then immediately follow it up with a read to DEFVTDBAR to ensure that all copies of DEFVTDBAR in the system are updated.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 6C80h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:40	0x0 RO	**Reserved (RESERVED_0):** Reserved.
39	0x0 RO	**Reserved**
38:12	0x0 RW	**Default IOMMU VTd Config Space Base (DEFVTDBAR):** If DEFVTDBAR is enabled, this field corresponds to bits 38:12 of the base address default IOMMU VTd configuration space. BIOS will program this register resulting in a base address for a 4KB block of contiguous memory address space. This register ensures that a naturally aligned 4KB space is allocated within the first 512GB of addressable memory space. System Software uses this base address to program the default VTd IOMMU register set. If DEFVTDBAR is enabled and incoming Request Address[38:12] matches DEFVTDBAR[38:12] the request targets the Default VTd BAR.
11:2	0x0 RO	**Reserved (RESERVED_1):** Reserved.
1	0x0 RW	**Lock Register Content (LOCK):** Locks the contents of the register including itself.
0	0x0 RW/L	**DEFVTDBAR Enable (DEFVTDBAREN):** • 0: DEFVTDBAR is disabled and does not claim any memory • 1: DEFVTDBAR memory mapped accesses are claimed and decoded appropriately. This bit will remain 0 if VTd capability is disabled.

44.3.124 B-Unit Arbiter Control BARBCTRL0 (B_CR_BARBCTRL0)—Offset 6D4Ch

Specifies the weighting for Agents 03 used by the B-Unit's Badmit Arbiter. The value specified in the Agent Weight field is used by the Badmit arbiters weight counters to determine the number of requests from an agent that are allowed to be granted before updating the requester's age register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D4Ch

Default: 04040404h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RESERVED_0):** Reserved.
29:24	0x4 RW	**Agent 3 Weight (AGENT3_WEIGHT):** Arbiter weight for Agent 3.
23:22	0x0 RO	**Reserved (RESERVED_1):** Reserved.
21:16	0x4 RW	**Agent 2 Weight (AGENT2_WEIGHT):** Arbiter weight for Agent 2.
15:14	0x0 RO	**Reserved (RESERVED_2):** Reserved.
13:8	0x4 RW	**Agent 1 Weight (AGENT1_WEIGHT):** Arbiter weight for Agent 1.
7:6	0x0 RO	**Reserved (RESERVED_3):** Reserved.
5:0	0x4 RW	**Agent 0 Weight (AGENT0_WEIGHT):** Arbiter weight for Agent 0.

44.3.125 B-Unit Arbiter Control BARBCTRL1 (B_CR_BARBCTRL1)—Offset 6D50h

Specifies the weighting for Agents 4-7 used by the B-Unit's Badmit Arbiter. The value specified in the Agent Weight field is used by the Badmit arbiter's weight counters to determine the number of requests from an agent that are allowed to be granted before updating the requester's age register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D50h

Default: 04040404h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RESERVED_0):** Reserved.
29:24	0x4 RW	**Agent 7 Weight (AGENT7_WEIGHT):** Arbiter weight for Agent 7.
23:22	0x0 RO	**Reserved (RESERVED_1):** Reserved.
21:16	0x4 RW	**Agent 6 Weight (AGENT6_WEIGHT):** Arbiter weight for Agent 6.
15:14	0x0 RO	**Reserved (RESERVED_2):** Reserved.
13:8	0x4 RW	**Agent 5 Weight (AGENT5_WEIGHT):** Arbiter weight for Agent 5.
7:6	0x0 RO	**Reserved (RESERVED_3):** Reserved.
5:0	0x4 RW	**Agent 4 Weight (AGENT4_WEIGHT):** Arbiter weight for Agent 4.

44.3.126 B-Unit Scheduler Control (B_CR_BSCHWT0)—Offset 6D54h

Specifies the weighting for Agents 0-3 used by the B-Unit Scheduler. The value is used by the B-Unit Scheduler to determine how many requests can be granted for the agent before the agent's requests are masked by the Scheduler Arbiter, to allow other agents' requests to be granted.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D54h

Default: 04040404h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RESERVED_0):** Reserved.
29:24	0x4 RW	**Agent 3 Weight (AGENT3_WEIGHT):** Arbiter weight for Agent 3.
23:22	0x0 RO	**Reserved (RESERVED_1):** Reserved.
21:16	0x4 RW	**Agent 2 Weight (AGENT2_WEIGHT):** Arbiter weight for Agent 2.
15:14	0x0 RO	**Reserved (RESERVED_2):** Reserved.
13:8	0x4 RW	**Agent 1 Weight (AGENT1_WEIGHT):** Arbiter weight for Agent 1.
7:6	0x0 RO	**Reserved (RESERVED_3):** Reserved.
5:0	0x4 RW	**Agent 0 Weight (AGENT0_WEIGHT):** Arbiter weight for Agent 0.

44.3.127 B-Unit Scheduler Control (B_CR_BSCHWT1)—Offset 6D58h

Specifies the weighting for Agents 4-7 used by the B-Unit Scheduler. The value is used by the B-Unit Scheduler to determine how many requests can be granted for the agent before the agent's requests are masked by the Scheduler Arbiter to allow other agents' requests to be granted.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D58h

Default: 04040404h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RESERVED_0):** Reserved.
29:24	0x4 RW	**Agent 7 Weight (AGENT7_WEIGHT):** Arbiter weight for Agent 7.
23:22	0x0 RO	**Reserved (RESERVED_1):** Reserved.
21:16	0x4 RW	**Agent 6 Weight (AGENT6_WEIGHT):** Arbiter weight for Agent 6.
15:14	0x0 RO	**Reserved (RESERVED_2):** Reserved.
13:8	0x4 RW	**Agent 5 Weight (AGENT5_WEIGHT):** Arbiter weight for Agent 5.
7:6	0x0 RO	**Reserved (RESERVED_3):** Reserved.
5:0	0x4 RW	**Agent 4 Weight (AGENT4_WEIGHT):** Arbiter weight for Agent 4.

44.3.128 B-Unit Scheduler Control (B_CR_BSCHWT2)—Offset 6D5Ch

Specifies the weighting for Agents 8-11 used by the B-Unit Scheduler. The value is used by the B-Unit Scheduler to determine how many requests can be granted for the agent before the agent's requests are masked by the Scheduler Arbiter to allow other agents' requests to be granted.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D5Ch

Default: 04040404h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RESERVED_0):** Reserved.
29:24	0x4 RW	**Agent 11 Weight (AGENT11_WEIGHT):** Arbiter weight for Agent 11.
23:22	0x0 RO	**Reserved (RESERVED_1):** Reserved.
21:16	0x4 RW	**Agent 10 Weight (AGENT10_WEIGHT):** Arbiter weight for Agent 10.
15:14	0x0 RO	**Reserved (RESERVED_2):** Reserved.
13:8	0x4 RW	**Agent 9 Weight (AGENT9_WEIGHT):** Arbiter weight for Agent 9.
7:6	0x0 RO	**Reserved (RESERVED_3):** Reserved.
5:0	0x4 RW	**Agent 8 Weight (AGENT8_WEIGHT):** Arbiter weight for Agent 8.

44.3.129 B-Unit Scheduler Control (B_CR_BSCHWT3)—Offset 6D60h

Specifies the weighting for Agents 12-15 used by the B-Unit Scheduler. The value is used by the B-Unit Scheduler to determine how many requests can be granted for the agent before the agent's requests are masked by the Scheduler Arbiter to allow other agents' requests to be granted.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D60h

Default: 04040404h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RESERVED_0):** Reserved.
29:24	0x4 RW	**Agent 15 Weight (AGENT15_WEIGHT):** Arbiter weight for Agent 15.
23:22	0x0 RO	**Reserved (RESERVED_1):** Reserved.
21:16	0x4 RW	**Agent 14 Weight (AGENT14_WEIGHT):** Arbiter weight for Agent 14.
15:14	0x0 RO	**Reserved (RESERVED_2):** Reserved.
13:8	0x4 RW	**Agent 13 Weight (AGENT13_WEIGHT):** Arbiter weight for Agent 13.
7:6	0x0 RO	**Reserved (RESERVED_3):** Reserved.
5:0	0x4 RW	**Agent 12 Weight (AGENT12_WEIGHT):** Arbiter weight for Agent 12.

44.3.130 B-Unit Flush Control (B_CR_BWFLUSH)—Offset 6D64h

Controls the policy used to determine when dirty entries must be flushed to DRAM. When the number of dirty entries is lower than a high watermark dirty_hwm the B-Unit will opportunistically flush data to DRAM after the write flush timeout value. When the number of dirty entries exceeds the high water mark, the B-Unit will initiate a high priority flush and push dirty data to DRAM until the count is once again below the low water mark.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: FF010000h

BAR and Offset: [MCHBAR] + 6D64h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0xff RW	**Flush Threshold (FLUSH_THRESHOLD):** All write commands are blocked at Badmit if the number of write commands in the Flush Pool exceeeds this value.
23:17	0x0 RO	**Reserved (RESERVED_0):** Reserved.
16	0x1 RO/V	**All Entries Flushed (ALL_ENTRIES_FLUSHED):** All dirty entries in the B-Unit, in both slices, have been flushed.
15:8	0x0 RW	**Dirty Low Water Mark (DIRTY_LWM):** Low water mark for dirty entries retained by the B-Unit. B-Unit will immediately attempt to flush any dirty entry, hence setting the low water mark to 0.
7:0	0x0 RW	**Dirty High Water Mark (DIRTY_HWM):** High water mark for dirty entries retained by the B-Unit. B-Unit will immediately attempt to flush any dirty entry, hence setting the low water mark to 0.

44.3.131 B-Unit Flush Weights (B_CR_BFLWT)—Offset 6D68h

Controls B-Unit alternate scheduling of reads and writes to DRAM.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000404h

BAR and Offset: [MCHBAR] + 6D68h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Disable Flush Weights (DISABLE_FLUSH_WEIGHTS):** When set to 1, disables flush weights. Flushing of dirty entries will start when Dirty Limit is HWM, and continue until Dirty Limit is LWM. No reads will be scheduled in between.
30:14	0x0 RO	**Reserved (RESERVED_1):** Reserved.
13:8	0x4 RW	**Write Weights (WRITE_WEIGHTS):** Number of write requests sent to a PMI channel before switching to scheduling read requests, when use of flush weights is not disabled.
7:6	0x0 RO	**Reserved (RESERVED_0):** Reserved.
5:0	0x4 RW	**Read Weights (READ_WEIGHTS):** Number of read requests sent to a PMI channel before switching to scheduling write requests, when use of flush weights is not disabled.

44.3.132 Weighted Scheduling Control of High Priority ISOC and Other Requests (B_CR_BISOCWT)—Offset 6D6Ch

Controls alternate scheduling of High Priority ISOC requests and other requests.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6D6Ch

Default: 80003F0Fh

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**Enable ISOC Requests (ENABLE_ISOC_WEIGHTS):** When set to 1, enables switching from scheduling High Priority ISOC requests to scheduling Best Effort and Low Priority ISOC requests, based on ISOC weights and NONISOC weights.
30:14	0x0 RO	**Reserved (RESERVED_1):** Reserved.
13:8	0x3f RW	**ISOC Request Weights (ISOC_REQUEST_WEIGHTS):** Weight for high priority isochronous requests.
7:6	0x0 RO	**Reserved (RESERVED_0):** Reserved.
5:0	0xf RW	**Non ISOC Request Weights (NON_ISOC_REQUEST_WEIGHTS):** Weight for non-high priority isochronous and best effort requests.

44.3.133 B-Unit Control (B_CR_BCTRL2)—Offset 6D70h

Contains basic control information used by the B-Unit.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000F0014h

BAR and Offset: [MCHBAR] + 6D70h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Enable Read Invalidate Timer (ENABLE_READ_INVALIDATE_TIMER):** When set to 1, enables the BRAM to clear the RD_DONE bit and flush dirty data when a timer expires. Used when parity is not enabled, to force the B-Unit to not indefinitely cache previously read lines, and also to cause a flush of dirty data that has been written to the BRAM entry.
30:25	0x0 RO	**Reserved (RESERVED_2):** Reserved.
24	0x0 RW	**MOT Disable Stall Arbiter on Error (MOT_DISABLE_STALL_ARB_ON_ERR):** If the HH widget gets an error, allow transactions to get arbitrated.
23:16	0xf RW	**BRAM Read Invalidate Time (BRAM_READ_INVALIDATE_TIME):** Timer threshold to clear rd_done bits or flush a BRAM entry, if dirty. The value specified is in multiples of 250ns. For each time interval specified, the read done status of one BRAM entry will be cleared based on a BTAG index which is then incremented to point to the next BRAM entry.
15:8	0x0 RW	**Casual Timer (CASUAL_TIMER):** The number of clock cycles that the B-Unit waits before starting a casual dirty flush. Casual Flush feature will not be enabled by PND2 architecture. Instead, a dirty write will be made eligible for scheduling immediately.
7:5	0x0 RO	**Reserved (RESERVED_1):** Reserved.
4	0x1 RO	**Enable 64B Read (ENABLE_64B_READ):** When set, B-unit will send 64B PMI read requests for transactions requiring read access to DRAM. Must always be set to one, otherwise functional errors may occur. Not applicable to the SoC, because the SoC is always 64 byte memory accesses.
3	0x0 RW	**Demand Scrub Enable (DEMAND_SCRUB_ENABLE):** This mode causes B-Unit to automatically issue a flush to PMI, thus writing correct data back to memory for any read request that returns with a correctable data error.
2	0x1 RW	**Enable Read Done for Write (ENABLE_READ_DONE_FOR_WRITE):** Enable Any writes (IWB or normal writes) to set the read_done bit in bstat, which enables return of data from the BRAM cache instead of Memory.
1	0x0 RW	**Miss Valid Entries (MISS_VALID_ENTRIES):** This mode causes reads to clean valid B-Unit buffer entries to look like misses instead of hits. When this bit is set -- even when all requested bytes are valid and present in the BRAM data buffer -- B-Unit will send read requests over the PMI interface to re-fetch the data from DRAM, instead of returning it from the BRAM.
0	0x0 RW	**Dirty Stall (DIRTY_STALL):** This mode causes reads or writes from any requester interface to dirty valid B-Unit buffer entries to stall on the appropriate requester interface until the entry has been flushed from the B-Unit.

44.3.134 Uncorrectable Error Status Register (B_CR_UNCERRSTS_0_0_0_MCHBAR)—Offset 6E04h

Errors that have been seen in bunit. The error is only logged if the respective bit in UNCERRMSK is 0.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E04h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RO	**Reserved** **Power Well:** prst
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RW/1C	**Dram Read Data Uncorrectable Error (MC_RD_DATA_UNC):** CRC error in dram read data **Power Well:** prst
8	0x0 RW/1C	**Bram Read Parity Error (BRAM_RD_PAR):** BRAM Read parity error **Power Well:** prst
7	0x0 RW/1C	**Bram Write Parity Error (BRAM_WR_PAR):** BRAM Write parity error **Power Well:** prst
6	0x0 RW/1C	**Reserved** **Power Well:** prst
5	0x0 RW/1C	**IA HIT GSM (IA_HIT_GSM):** IA hit to graphics stolen memory **Power Well:** prst
4	0x0 RW/1C	**MMIO CLFLUSH (MMIO_CLFLUSH):** ClFlush to MMIO address space **Power Well:** prst
3	0x0 RW/1C	**MMIO WBMTOIE (MMIO_WBMTOIE):** WBMTo access to MMIO **Power Well:** prst
2	0x0 RW/1C	**MMIO HITM (MMIO_HITM):** MMIO Access HITM **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW/1C	**PII request to MMIO (PII_2_MMIO):** NonIDI access to MMIO address space **Power Well:** prst
0	0x0 RW/1C	**Unsupport IDI Opcode (UNS_IDI_OP):** Unsupport IDI Opcode detected **Power Well:** prst

44.3.135 Uncorrectable Error Mask Register (B_CR_UNCERRMSK_0_0_0_MCHBAR)—Offset 6E08h

Masks whether a reported error is logged and signaled to the IEH. 1- do not log/signal. 0 - log/signal.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E08h

Default: FFFFFFFFh

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Reserved**
30	0x1 RO	**Reserved**
29	0x1 RO	**Reserved**
28	0x1 RO	**Reserved**
27	0x1 RO	**Reserved**
26	0x1 RO	**Reserved**
25	0x1 RO	**Reserved**
24	0x1 RO	**Reserved**
23	0x1 RO	**Reserved**
22	0x1 RO	**Reserved**
21	0x1 RO	**Reserved**
20	0x1 RO	**Reserved**
19	0x1 RO	**Reserved**
18	0x1 RO	**Reserved**
17	0x1 RO	**Reserved**
16	0x1 RO	**Reserved**
15	0x1 RO	**Reserved**
14	0x1 RO	**Reserved**
13	0x1 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
12	0x1 RO	**Reserved**
11	0x1 RO	**Reserved**
10	0x1 RO	**Reserved**
9	0x1 RW	**Dram Read Data Uncorrectable Error (MC_RD_DATA_UNC):** CRC error in dram read data
8	0x1 RW	**Bram Read Parity Error (BRAM_RD_PAR):** BRAM Read parity error
7	0x1 RW	**Bram Write Parity Error (BRAM_WR_PAR):** BRAM Write parity error
6	0x1 RW	**Reserved**
5	0x1 RW	**IA HIT GSM (IA_HIT_GSM):** IA hit to graphics stolen memory
4	0x1 RW	**MMIO CLFLUSH (MMIO_CLFLUSH):** ClFlush to MMIO address space
3	0x1 RW	**MMIO WBMTOIE (MMIO_WBMTOIE):** WBMTo access to MMIO
2	0x1 RW	**MMIO HITM (MMIO_HITM):** MMIO Access HITM
1	0x1 RW	**PII request to MMIO (PII_2_MMIO):** NonIDI access to MMIO address space
0	0x1 RW	**Unsupport IDI Opcode (UNS_IDI_OP):** Unsupport IDI Opcode detected

44.3.136 Uncorrectable Error Severity Register (B_CR_UNCERRSEV_0_0_0_MCHBAR)—Offset 6E0Ch

When set, escalate error as fatal to IEH, otherwise non-fatal.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E0Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved**
30	0x0 RO	**Reserved**
29	0x0 RO	**Reserved**
28	0x0 RO	**Reserved**
27	0x0 RO	**Reserved**
26	0x0 RO	**Reserved**
25	0x0 RO	**Reserved**
24	0x0 RO	**Reserved**
23	0x0 RO	**Reserved**
22	0x0 RO	**Reserved**
21	0x0 RO	**Reserved**
20	0x0 RO	**Reserved**
19	0x0 RO	**Reserved**
18	0x0 RO	**Reserved**
17	0x0 RO	**Reserved**
16	0x0 RO	**Reserved**
15	0x0 RO	**Reserved**
14	0x0 RO	**Reserved**
13	0x0 RO	**Reserved**
12	0x0 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
11	0x0 RO	**Reserved**
10	0x0 RO	**Reserved**
9	0x0 RW	**Dram Read Data Uncorrectable Error (MC_RD_DATA_UNC):** CRC error in dram read data
8	0x0 RW	**Bram Read Parity Error (BRAM_RD_PAR):** BRAM Read parity error
7	0x0 RW	**Bram Write Parity Error (BRAM_WR_PAR):** BRAM Write parity error
6	0x0 RW	**Reserved**
5	0x0 RW	**IA HIT GSM (IA_HIT_GSM):** IA hit to graphics stolen memory
4	0x0 RW	**MMIO CLFLUSH (MMIO_CLFLUSH):** ClFlush to MMIO address space
3	0x0 RW	**MMIO WBMTOIE (MMIO_WBMTOIE):** WBMTo access to MMIO
2	0x0 RW	**MMIO HITM (MMIO_HITM):** MMIO Access HITM
1	0x0 RW	**PII request to MMIO (PII_2_MMIO):** NonIDI access to MMIO address space
0	0x0 RW	**Unsupport IDI Opcode (UNS_IDI_OP):** Unsupport IDI Opcode detected

44.3.137 First Uncorrectable Error Register (B_CR_UNCFERRSTS_0_0_0_MCHBAR)—Offset 6E10h

First Error Status

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E10h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst
18	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RO/V	**Dram Read Data Uncorrectable Error (MC_RD_DATA_UNC):** CRC error in dram read data **Power Well:** prst
8	0x0 RO/V	**Bram Read Parity Error (BRAM_RD_PAR):** BRAM Read parity error **Power Well:** prst
7	0x0 RO/V	**Bram Write Parity Error (BRAM_WR_PAR):** BRAM Write parity error **Power Well:** prst
6	0x0 RO/V	**Reserved** **Power Well:** prst
5	0x0 RO/V	**IA HIT GSM (IA_HIT_GSM):** IA hit to graphics stolen memory **Power Well:** prst
4	0x0 RO/V	**MMIO CLFLUSH (MMIO_CLFLUSH):** ClFlush to MMIO address space **Power Well:** prst
3	0x0 RO/V	**MMIO WBMTOIE (MMIO_WBMTOIE):** WBMTo access to MMIO **Power Well:** prst
2	0x0 RO/V	**MMIO HITM (MMIO_HITM):** MMIO Access HITM **Power Well:** prst
1	0x0 RO/V	**PII request to MMIO (PII_2_MMIO):** NonIDI access to MMIO address space **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RO/V	**Unsupport IDI Opcode (UNS_IDI_OP):** Unsupport IDI Opcode detected **Power Well:** prst

44.3.138 Next Uncorrectable Error Register (B_CR_UNCNERRSTS_0_0_0_MCHBAR)—Offset 6E14h

Next Error Status

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E14h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst
18	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RO/V	**Dram Read Data Uncorrectable Error (MC_RD_DATA_UNC):** CRC error in dram read data **Power Well:** prst
8	0x0 RO/V	**Bram Read Parity Error (BRAM_RD_PAR):** BRAM Read parity error **Power Well:** prst
7	0x0 RO/V	**Bram Write Parity Error (BRAM_WR_PAR):** BRAM Write parity error **Power Well:** prst
6	0x0 RO/V	**Reserved** **Power Well:** prst
5	0x0 RO/V	**IA HIT GSM (IA_HIT_GSM):** IA hit to graphics stolen memory **Power Well:** prst
4	0x0 RO/V	**MMIO CLFLUSH (MMIO_CLFLUSH):** ClFlush to MMIO address space **Power Well:** prst
3	0x0 RO/V	**MMIO WBMTOIE (MMIO_WBMTOIE):** WBMTo access to MMIO **Power Well:** prst
2	0x0 RO/V	**MMIO HITM (MMIO_HITM):** MMIO Access HITM **Power Well:** prst
1	0x0 RO/V	**PII request to MMIO (PII_2_MMIO):** NonIDI access to MMIO address space **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RO/V	**Unsupport IDI Opcode (UNS_IDI_OP):** Unsupport IDI Opcode detected **Power Well:** prst

44.3.139 Uncorrectable Error Select Register (B_CR_UNCERRCNTSEL_0_0_0_MCHBAR)—Offset 6E18h

Selects which errors cause the UNCERRCNT register to increment. 0-do not count 1-count.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E18h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved**
30	0x0 RO	**Reserved**
29	0x0 RO	**Reserved**
28	0x0 RO	**Reserved**
27	0x0 RO	**Reserved**
26	0x0 RO	**Reserved**
25	0x0 RO	**Reserved**
24	0x0 RO	**Reserved**
23	0x0 RO	**Reserved**
22	0x0 RO	**Reserved**
21	0x0 RO	**Reserved**
20	0x0 RO	**Reserved**
19	0x0 RO	**Reserved**
18	0x0 RO	**Reserved**
17	0x0 RO	**Reserved**
16	0x0 RO	**Reserved**
15	0x0 RO	**Reserved**
14	0x0 RO	**Reserved**
13	0x0 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
12	0x0 RO	**Reserved**
11	0x0 RO	**Reserved**
10	0x0 RO	**Reserved**
9	0x0 RW	**Dram Read Data Uncorrectable Error (MC_RD_DATA_UNC):** CRC error in dram read data
8	0x0 RW	**Bram Read Parity Error (BRAM_RD_PAR):** BRAM Read parity error
7	0x0 RW	**Bram Write Parity Error (BRAM_WR_PAR):** BRAM Write parity error
6	0x0 RW	**Reserved**
5	0x0 RW	**IA HIT GSM (IA_HIT_GSM):** IA hit to graphics stolen memory
4	0x0 RW	**MMIO CLFLUSH (MMIO_CLFLUSH):** ClFlush to MMIO address space
3	0x0 RW	**MMIO WBMTOIE (MMIO_WBMTOIE):** WBMTo access to MMIO
2	0x0 RW	**MMIO HITM (MMIO_HITM):** MMIO Access HITM
1	0x0 RW	**PII request to MMIO (PII_2_MMIO):** NonIDI access to MMIO address space
0	0x0 RW	**Unsupport IDI Opcode (UNS_IDI_OP):** Unsupport IDI Opcode detected

44.3.140 Uncorrectable Error Count (B_CR_UNCERRCNT_0_0_0_MCHBAR)—Offset 6E1Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E1Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RESERVED_0):** Reserved.
15	0x0 RW/1C	**Error Count Overflow (OVERFLOW):** Reserved. **Power Well:** prst
14:0	0x0 RW/1C	**Uncorrectable Error Count (ERR_CNT):** Reserved. **Power Well:** prst

44.3.141 Correctable Error Status Register (B_CR_CORERRSTS_0_0_0_MCHBAR)—Offset 6E20h

Errors that have been seen in A-Unit. This will always log errors irrespective of the CORERRMSK bit setting

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E20h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved** **Power Well:** prst
30	0x0 RO	**Reserved** **Power Well:** prst
29	0x0 RO	**Reserved** **Power Well:** prst
28	0x0 RO	**Reserved** **Power Well:** prst
27	0x0 RO	**Reserved** **Power Well:** prst
26	0x0 RO	**Reserved** **Power Well:** prst
25	0x0 RO	**Reserved** **Power Well:** prst
24	0x0 RO	**Reserved** **Power Well:** prst
23	0x0 RO	**Reserved** **Power Well:** prst
22	0x0 RO	**Reserved** **Power Well:** prst
21	0x0 RO	**Reserved** **Power Well:** prst
20	0x0 RO	**Reserved** **Power Well:** prst
19	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RO	**Reserved** **Power Well:** prst
17	0x0 RO	**Reserved** **Power Well:** prst
16	0x0 RO	**Reserved** **Power Well:** prst
15	0x0 RO	**Reserved** **Power Well:** prst
14	0x0 RO	**Reserved** **Power Well:** prst
13	0x0 RO	**Reserved** **Power Well:** prst
12	0x0 RO	**Reserved** **Power Well:** prst
11	0x0 RO	**Reserved** **Power Well:** prst
10	0x0 RO	**Reserved** **Power Well:** prst
9	0x0 RO	**Reserved** **Power Well:** prst
8	0x0 RO	**Reserved** **Power Well:** prst
7	0x0 RO	**Reserved** **Power Well:** prst
6	0x0 RO	**Reserved** **Power Well:** prst
5	0x0 RO	**Reserved** **Power Well:** prst
4	0x0 RO	**Reserved** **Power Well:** prst
3	0x0 RO	**Reserved** **Power Well:** prst
2	0x0 RO	**Reserved** **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**Reserved** **Power Well:** prst
0	0x0 RW/1C	**MC_RD_DATA_COR:** MC_RD_DATA_COR **Power Well:** prst

44.3.142 Correctable Error Mask Register (B_CR_CORERRMSK_0_0_0_MCHBAR)—Offset 6E24h

Masks where a reported error is signaled to the IEH. 1- do not signal. 0 - signal.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 6E24h

Default: FFFFFFFFh

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Reserved**
30	0x1 RO	**Reserved**
29	0x1 RO	**Reserved**
28	0x1 RO	**Reserved**
27	0x1 RO	**Reserved**
26	0x1 RO	**Reserved**
25	0x1 RO	**Reserved**
24	0x1 RO	**Reserved**
23	0x1 RO	**Reserved**
22	0x1 RO	**Reserved**
21	0x1 RO	**Reserved**
20	0x1 RO	**Reserved**
19	0x1 RO	**Reserved**
18	0x1 RO	**Reserved**
17	0x1 RO	**Reserved**
16	0x1 RO	**Reserved**
15	0x1 RO	**Reserved**
14	0x1 RO	**Reserved**
13	0x1 RO	**Reserved**
12	0x1 RO	**Reserved**

Bit Range	Default & Access	Field Name (ID): Description
11	0x1 RO	**Reserved**
10	0x1 RO	**Reserved**
9	0x1 RO	**Reserved**
8	0x1 RO	**Reserved**
7	0x1 RO	**Reserved**
6	0x1 RO	**Reserved**
5	0x1 RO	**Reserved**
4	0x1 RO	**Reserved**
3	0x1 RO	**Reserved**
2	0x1 RO	**Reserved**
1	0x1 RO	**Reserved**
0	0x1 RW	**MC_RD_DATA_COR:** MC_RD_DATA_COR

44.3.143 Data Parity Header Log Low (B_CR_DPHDRLOG_LO_0_0_0_MCHBAR)—Offset 6E28h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E28h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Location of Bad Data Byte (UNCDPLOG):** Reserved. **Power Well:** prst

44.3.144 Data Parity Header Log High (B_CR_DPHDRLOG_HI_0_0_0_MCHBAR)—Offset 6E2Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E2Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Location of Bad Data Byte (UNCDPLOG):** Reserved. **Power Well:** prst

44.3.145 Data Parity Address Log Low (B_CR_DPADDRLOG_LO_0_0_0_MCHBAR)—Offset 6E30h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E30h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Data Parity Address (DPADDR):** Reserved. **Power Well:** prst

44.3.146 Data Parity Address Log High (B_CR_DPADDRLOG_HI_0_0_0_MCHBAR)—Offset 6E34h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E34h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RESERVED_0):** Reserved.
7:0	0x0 RO/V	**Data Parity Address (DPADDR):** Reserved. **Power Well:** prst

44.3.147 D-Unit Error Address Log (B_CR_DERRADDRLOG_LO_0_0_0_MCHBAR)—Offset 6E38h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E38h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Address (ADDR):** D-Unit error address. **Power Well:** prst

44.3.148 D-Unit Error Address Log (B_CR_DERRADDRLOG_HI_0_0_0_MCHBAR)—Offset 6E3Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E3Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RO/V	**Data Parity Address (ADDR):** Reserved. **Power Well:** prst

44.3.149 Asymmetric Memory Region 0 (B_CR_ASYM_MEM_REGION0_0_0_0_MCHBAR)—Offset 6E40h

Specification of asymmetric memory region 0 (in slice 0) for the configuration with 2 asymmetric memory regions.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E40h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Slice 0 Asymmetric Enable (SLICE0_ASYM_ENABLE):** Setting this bit to 0 disables asymmetric memory region 0; setting it to 1 enables the region.
30:28	0x0 RO	**RSVD0:** Reserved
27:20	0x0 RW	**SLICE0_ASYM_LIMIT:** Specifies bits [38:31] of the highest address of asymmetric memory region 0 (in slice 0); all the lower bits of the region's highest address are equal to 1.
19:12	0x0 RO	**RSVD1:** Reserved
11:4	0x0 RW	**Slice 0 Asymmetric Limit (SLICE0_ASYM_BASE):** Specifies bits [38:31] of the base address of asymmetric memory region 0 (in slice 0); all the lower bits of the region's base address are equal to 0.
3:0	0x0 RO	**RSVD2:** Reserved

44.3.150 Asymmetric Memory Region 1 (B_CR_ASYM_MEM_REGION1_0_0_0_MCHBAR)—Offset 6E44h

Specification of asymmetric memory region 1 (in slice 1) for the configuration with 2 asymmetric memory regions.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E44h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Slice 1 Asymmetric Enable (SLICE1_ASYM_ENABLE):** Setting this bit to 0 disables asymmetric memory region 1; setting it to 1 enables the region.
30:28	0x0 RO	**RSVD0:** Reserved
27:20	0x0 RW	**SLICE1_ASYM_LIMIT:** Specifies bits [38:31] of the highest address of asymmetric memory region 1 (in slice 1); all the lower bits of the region's highest address are equal to 1.
19:12	0x0 RO	**RSVD1:** Reserved
11:4	0x0 RW	**Slice 1 Asymmetric Limit (SLICE1_ASYM_BASE):** Specifies bits [38:31] of the base address of asymmetric memory region 1 (in slice 1); all the lower bits of the region's base address are equal to 0.
3:0	0x0 RO	**RSVD2:** Reserved

44.3.151 B-Unit Machine Check Mode Low (B_CR_BMCMODE_LOW)—Offset 6E48h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000001h

BAR and Offset: [MCHBAR] + 6E48h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RESERVED_0):** Reserved.
0	0x1 RW	**Machine Check Signal Mode (MC_SIGNAL_MODE):** When set to 1, B-Unit will not allow any transaction with uncorrectable error or subsequent memory transaction to propagate through to Requester. This will essentially hang CPU and CPU will end up with IERR shutdown. Issue: When set to zero B-Unit will allow transaction with an uncorrectable error to propagate and signal MC event to CPU if enabled in IA32_MC5_CTL. If enabled MC event will be taken by CPU cores at the end of instruction boundary after it detected by ROB **Power Well:** prst

44.3.152 B-Unit Machine Check Mode High (B_CR_BMCMODE_HIGH)—Offset 6E4Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 6E4Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Reserved (RESERVED_0):** Reserved.

44.3.153 PWR_LIMIT_MISC_0_0_0_MCHBAR (P_CR_PWR_LIMIT_MISC_0_0_0_MCHBAR)—Offset 7014h

This register is Read Only. The register is used to report Skt power at Pn - mapped from FUSE_PN_POWER_OF_SKU and Minimal Time window - mapped from FUSE_PBM_MINIMAL_TAU_ALLOWED. Added new register for relaying IA PBM information to the use.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7014h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RO	**Reserved:** Reserved **Power Well:** prst
21:15	0x0 RO/V	**PBM_MINIMAL_TAU_ALLOWED:** Minimal Tau Time window allowed. **Power Well:** prst
14:0	0x0 RO/V	**PN_POWER_OF_SKU:** Package Power of SKU. **Power Well:** prst

44.3.154 CAPABILITY_ID_0_0_0_MCHBAR (P_CR_CAPABILITY_ID_0_0_0_MCHBAR)—Offset 7018h

This register is Read Only. The register is used to report to BIOS certain PM features for this Part.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7018h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Reserved:** Reserved **Power Well:** prst
1:0	0x0 RO/V	**FUSE_THERMAL_PROFILE:** **Power Well:** prst

44.3.155 MC_BIOS_REQ_0_0_0_MCH (P_CR_MC_BIOS_REQ_0_0_0_MCHBAR)—Offset 7020h

This register is defined to support memSS reset flow, handshake between SOC FW (aka Pcode) and BIOS MRC

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7020h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**RUN_BUSY:** This bit indicates that the BIOS request is pending. BIOS sets this bit together with a command in the lower bits of this register.
30:20	0x0 RW	**RSVD0:** Reserved - Future data bits for fastpath action or status indication.
19	0x0 RW	**MEM_INIT_DONE:** BIOS programs this bit after DUNIT and DDRIO configuration is complete.
18:16	0x0 RW	**Reserved**
15	0x0 RW	**CH1_DIMMS:** BIOS writes this value indicates
14	0x0 RW	**CH0_DIMMS:** BIOS writes this value indicates
13	0x0 RW	**CH1_ENABLED:** BIOS writes this value indicates if memory channel 1 has device attached or not. 1'b1 = 1 or 2 DIMMs populated.
12	0x0 RW	**CH0_ENABLED:** BIOS writes this value indicates if memory channel 1 has device attached or not. 1'b1 = 1 or 2 DIMMs populated.
11:7	0x0 RW	**Reserved**
6	0x0 RW	**DDR_TYPE_VOLTAGE:** BIOS set VDDQ Voltage: 0: DDR3 Memory Technology (VDDQ = 1.35V); 1: DDR4 Memory Technology (VDDQ = 1.25V);
5:0	0x0 RO	**RSVD0:** Reserved

44.3.156 MCA_ERROR_SRC_0_0_0_MCHBAR (P_CR_MCA_ERROR_SRC_0_0_0_MCHBAR)—Offset 702Ch

This register logs error source information i.e IERR or MCERR information for Pcode. The error fields are cleared by HW or BIOS.This register is also shadowed in the I/O space.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 702Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/V	**CATERR:** Asserted by HW on IERR or MCERR assertion. **Power Well:** prst
30	0x0 RW/V	**IERR:** Asserted by HW on IERR assertion. **Power Well:** prst
29	0x0 RW/V	**MCERR:** Asserted by HW on MCERR assertion. **Power Well:** prst
28:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RW	**RESERVED:** **Power Well:** prst

44.3.157 DDR_THERM_THRT_CTRL_0_0_0_MCHBAR (P_CR_DDR_THERM_THRT_CTRL_0_0_0_MCHBAR)—Offset 7030h

This register is used to configure thermal throttling policies for both near and far memory.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00010000h

BAR and Offset: [MCHBAR] + 7030h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**RESERVED**
16	0x1 RW/V	**RESERVED**
15:10	0x0 RO	**RESERVED**
9	0x0 RW/V	**MEM_THRT_ENABLE:** When set, memory traffic is throttled if near Wide-IO or far LPDDR memory MR4 value = FM/NM_THERM_THRT_THRESHOLD, respectively. Thermal throttling is achieved by applying memory bandwidth clips in the memory subsystem.
8	0x0 RW/V	**MEM_THRT_CFG:** Configure memory throttling behavior. Policies are defined as follows: • 0 = Thermal throttling policy uses instantaneous MR4 status for FM/ NM_THERM_THRT_THRESHOLD • 1 = Thermal throttling policy uses time filtered MR4 status for FM/NM_THERM_THRT_THRESHOLD. Filtering time constant is configured in the DDR_THERM_INTERRUPT register.
7	0x0 RW/V	**NM_THERM_THRT_ENABLE:** When set, throttling is activated if near Wide I/O memory MR4 value is greater than or equal to NM_THERM_THRT_THRESHOLD
6:4	0x0 RW/V	**NM_THERM_THRT_THRESHOLD:** Configurable threshold of near Wide I/O memory MR4 value greater than or equal to which thermal throttling is activated. • Near Memory MR4 (Threshold = Enable thermal throttling) • Near Memory MR4 (Threshold = Disable thermal throttling)
3	0x0 RW/V	**FM_THERM_THRT_ENABLE:** When enabled throttling is activated if far LPDDR memory MR4 value is greater than or equal to FM_THERM_THRT_THRESHOLD. For the standard LPDDR DRAM that is only capable up to Tcasemax of 85C this bit should be set to enable far LPDDR throttling to keep DRAM within its Tcasemax spec.
2:0	0x0 RW/V	**FM_THERM_THRT_THRESHOLD:** Configurable threshold of far LPDDR memory MR4 value greater than or equal to which thermal throttling is activated. For the standard LPDDR DRAM that is only capable up to Tcasemax of 85C this field should be configured to avoid DRAM to exceed its Tcasemax spec. • Far Memory MR4 (Threshold = Enable thermal throttling) • Far Memory MR4 (Threshold = Disable thermal throttling)

44.3.158 PACKAGE_THERM_MARGIN (P_CR_PACKAGE_THERM_MARGIN_0_0_0_MCHBAR)—Offset 703Ch

Temperature margin in PECI temperature counts from the thermal profile specification. Platform fan control SW is expected to read therm_margin value to control fan or blower speed.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 703Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**RESERVED**
15:0	0x0 RW	**THERM_MARGIN:** Temperature margin in PECI temperature counts from the thermal profile specification. THERM_MARGIN is in 2's complement format (8.8 format where MSB equals 1 Sign bit + 7 bits of integer temperature value and the LSB equals 8 precision bits of temperature value). A value of zero indicates the hottest CPU die temperature is on the thermal profile line. A negative value indicates gap to the thermal profile that platform SW should increase cooling capacity. A sustained negative value should be avoided as it may impact part reliability.

44.3.159 DDR_RAPL_LIMIT (P_CR_DDR_RAPL_LIMIT_0_0_0_MCHBAR)—Offset 7040h

RAPL power limit for DDR domain. This register is written by platform software and read by Pcode once per 1ms. There are actually two instances of this register: one with MSR access and one with MMIO access. There is a separate PECI/PCS command which is also analogous.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 7040h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/L	**LOCKED:** When set this entire register becomes read-only. This bit will typically be set by BIOS during boot.
62:32	0x0 RO	**Reserved:** Reserved
31:24	0x0 RO	**Reserved:** Reserved
23:22	0x0 RW/L	**LIMIT1_TIME_WINDOW_X:** The time window for RAPL is expressed in a format called TAU. TAU is specified in a mantissa+exponent format. This format is common across all RAPL interfaces for TAU. The format is specified with a 7 bit number that looks like: XXYYYYY (2 bits of mantissa followed by 5 exponent) The time window corresponding to this config is calculated as: (1+ XXb / 4) * (2^YYYYYb) The value that results from this math species the time window in units that are defined in PACKAGE_POWER_SKU_UNIT.TIME_UNIT MSR.
21:17	0x0 RW/L	**LIMIT1_TIME_WINDOW_Y:** The Tau Exponent. See TIME_WINDOW_X for more information.
16	0x0 RO	**RESERVED_0:** Reserved
15	0x0 RW/L	**LIMIT1_ENABLE:** Power Limit[0] enable bit for DDR domain.
14:0	0x0 RW/L	**LIMIT1_POWER:** Power Limit[0] for DDR domain. The power units of this field are specified by the PACKAGE_POWER_SKU_UNIT_MSR.PWR_UNIT.

44.3.160 DDR_ENERGY_STATUS (P_CR_DDR_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 7048h

Reports total energy consumed in DRAM. The energy status is reported in units which are defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT. The counter will wrap around and continue counting from zero when it reaches its limit and therefore should be polled sufficiently frequently to avoid aliasing. Typically, software will calculate delta energy and delta time and divide the two to estimate Watts consumed over a time window. The value of this register is updated at approximately every 1ms. This energy status is what is used by DDR RAPL or OLTM control algorithms if the product supports those features.

To calculate Watts: **Watts = delta(energy) / delta(time) / 2^PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT** THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7048h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**JOULES:** Total Joules of energy consumed by all DIMMs. Units are proportional to Joules and are defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT. **Power Well:** prst

44.3.161 DDR_RAPL_PERF_STATUS (P_CR_DDR_RAPL_PERF_STATUS_0_0_0_MCHBAR)—Offset 704Ch

Memory RAPL performance throttling counter. This counter accumulates time that any channel in the memory controller is bandwidth throttled due to memory RAPL constraints. This counter counts total time (in PACKAGE_POWER_SKU_UNIT_MSR.TIME_UNIT units) that any channel is throttled. If two channels are throttled, this counter increments at a 2x rate, so that for 1ms in wall clock time the counter counts 2ms. This counter does not include throttling as a result of thermal management or MEMHOT. This register is updated at approximately 1ms intervals. This counter is normalized to 'seconds' and is not subject to variation of actual DRAM clock speeds. This register is read-only for software via MMIO MSR and PECI/PCS. This register starts counting at zero from reset and continues counting forever and wraparounds may occur, so software should ensure the sample rate is sufficient to avoid aliasing. This is an unsigned value.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 704Ch

Default: 000058F0h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x58f0 RW	**DURATION:** Bandwidth throttle duration counter due to Memory RAPL. Sum across all channels in PACKAGE_POWER_SKU_UNIT_MSR.TIME_UNIT units. This data can serve as a proxy for the potential performance impacts of RAPL on memory accesses. **Power Well:** prst

44.3.162 PACKAGE_RAPL_PERF_STATUS (P_CR_PACKAGE_RAPL_PERF_STATUS_0_0_0_MCHBAR)—Offset 7050h

Counts time that any core in the IA domain is performance throttled below OS request and below the base frequency (P1) because of power limits (PL1 or PL2). Counts in time units defined by PACKAGE_POWER_SKU_UNIT_MSR.TIME_UNIT. If software uses the TURBO_ACTIVATION_RATIO or PECI ACPI P-NOTIFY, the turbo activation ratios described by those features will may elevate the effective OS request (as calculated by this counter) to max turbo. This register starts counting at zero from reset and continues counting forever and wraparounds may occur, so software should ensure the sample rate is sufficient to avoid aliasing. This is an unsigned value.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7050h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**COUNTS:** Time that any core in the IA domain is performance throttled below OS request and below the base frequency (P1) because of power limits (PL1 or PL2). Counts in time units defined by PACKAGE_POWER_SKU_UNIT_MSR.TIME_UNIT **Power Well:** prst

44.3.163 PRIMARY_PLANE_TURBO_POWER_POLICY (P_CR_PRIMARY_PLANE_TURBO_PLCY_0_0_0_MCHBAR)—Offset 7054h

The PRIMARY_PLANE_TURBO_POWER_POLICY and SECONDARY_PLANE_TURBO_POWER_POLICY are used together as hints to balance the power budget between the primary (IA core) and secondary (Graphics) power planes. This biasing is effectively a performance biasing, and it helps Punit firmware assess where software needs performance the most.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7054h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RO	**RESERVED_0:** Reserved
4:0	0x0 RW	**PRIPTP:** Performance priority Level for the IA Core (primary) power plane. A higher number implies a higher priority.

44.3.164 SECONDARY_PLANE_TURBO_POWER_POLICY (P_CR_SECONDARY_PLANE_TURBO_PLCY_0_0_0_MCHBAR)—Offset 7058h

The PRIMARY_PLANE_TURBO_POWER_POLICY and SECONDARY_PLANE_TURBO_POWER_POLICY are used together as hints to balance the power budget between the primary (IA core) and secondary (Graphics) power planes. This biasing is effectively a performance biasing, and it helps Punit firmware assess where software needs performance the most.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7058h

Default: 00000010h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RO	**RESERVED_0:** Reserved
4:0	0x10 RW	**SECPTP:** Performance priority Level for the Graphics (secondary) power plane. A higher number implies a higher priority.

44.3.165 PRIMARY_PLANE_ENERGY_STATUS (P_CR_PRIMARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 705Ch

Reports total energy consumed across all IA cores. The energy status is reported in units which are defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT. The counter will wrap around and continue counting from zero when it reaches its limit and therefore should be polled sufficiently frequently to avoid aliasing. Typically, software will calculate delta energy and delta time and divide the two to estimate Watts consumed over a time window. The value of this register is updated at approximately every 1ms.

To calculate Watts: **Watts = delta(energy) / delta(time) / 2^PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT** THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 705Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**DATA:** Contains an accumulated value of the energy consumed in the primary power plane. To find the energy consumed in a given time window, software should subtract the two energy readings. Software will have to take care of counter wrapping around when it overflows. Units are proportional to Joules exact precision is defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT

44.3.166 SECONDARY_PLANE_ENERGY_STATUS (P_CR_SECONDARY_PLANE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 7060h

Reports total energy consumed across all IA cores. The energy status is reported in units which are defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT. The counter will wrap around and continue counting from zero when it reaches its limit and therefore should be polled sufficiently frequently to avoid aliasing. Typically, software will calculate delta energy and delta time and divide the two to estimate Watts consumed over a time window. The value of this register is updated at approximately every 1ms.

To calculate Watts: **Watts = delta(energy) / delta(time) / 2^PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT** THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7060h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**DATA:** Contains an accumulated value of the energy consumed in the secondary power plane. To find the energy consumed in a given time window, software should subtract the two energy readings. Software will have to take care of counter wrapping around when it overflows. Units are proportional to Joules exact precision is defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT

44.3.167 PACKAGE_POWER_SKU_UNIT (P_CR_PACKAGE_POWER_SKU_UNIT_0_0_0_MCHBAR)—Offset 7068h

Defines units for calculating SKU power, current, energy, resistance and timing parameters.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 330A0E08h

BAR and Offset: [MCHBAR] + 7068h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x3 RW	**RESISTANCE_UNIT:** Used to define the units of resistance for control registers that describe parameters in ohms such as VR_CURRENT_CONFIG. The actual unit value is calculated by 1mohm / 2^RESISTANCE_UNIT. The default value of 3 corresponds to 0.125mohm.
27:24	0x3 RW	**CURRENT_UNIT:** Used to define the units of amps in control registers such as VR_CURRENT_CONFIG. The actual unit value is calculated by 1A / 2^CURRENT_UNIT. The default value of 3 corresponds to 0.125A.
23:20	0x0 RO	**RESERVED_2:** Reserved
19:16	0xa RW	**TIME_UNIT:** Used for to define the time units in registers such as PL1, PL2, PL3 and PL4. The actual unit value is calculated by 1s / 2^TIME_UNIT. The default value of 10 corresponds to 0.977ms.
15:13	0x0 RO	**RESERVED_1:** Reserved
12:8	0xe RW	**ENERGY_UNIT:** Used to define the units of energy reporting registers such as PACKAGE_ENERGY_STATUS. The actual unit value is calculated by 1 J / 2^ENERGY_UNIT. The default value of 14 corresponds to ~61uJ per bit.
7:4	0x0 RO	**RESERVED_0:** Reserved
3:0	0x8 RW	**PWR_UNIT:** Used to define the units of power control registers such as PL1, PL2, PL3 and PL4. The actual unit value is calculated by 1 W / 2^PWR_UNIT. The default value of 8 corresponds to 3.9mW per bit.

44.3.168 PACKAGE_ENERGY_STATUS (P_CR_PACKAGE_ENERGY_STATUS_0_0_0_MCHBAR)—Offset 706Ch

Reports total energy consumed across the entire SOC / Package. The energy status is reported in units which are defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT. The counter will wrap around and continue counting from zero when it reaches its limit and therefore should be polled sufficiently frequently to avoid aliasing. Typically, software will calculate delta energy and delta time and divide the two to estimate Watts consumed over a time window. The value of this register is updated at approximately every 1ms. This energy status is what is used by RAPL PL1, PL2 and PL3 control algorithms.

To calculate Watts: **Watts = delta(energy) / delta(time) / 2^PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT** THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 706Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**DATA:** Contains accumulated energy consumed by the entire CPU. This counter will wrap around and keep counting when the counter overflows. Units are proportional to Joules exact precision is defined by PACKAGE_POWER_SKU_UNIT_MSR.ENERGY_UNIT

44.3.169 GT_PERF_STATUS (P_CR_GT_PERF_STATUS_0_0_0_MCHBAR)—Offset 7070h

Contains the voltage and ratio status for GT. This register is mapped to GT_PERF_STATUS_0_0_0_MCHBAR.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7070h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:26	0x0 RO	**RSVD0:** Reserved
25:17	0x0 RO/V	**RP_STATE_RATIO_SLICE:** Ratio of the current RP-state, in 16.6Mhz 1xclks. When the graphics engine is in RC6, this field is zeroed out. For the SoC the Unslice and Slice run at the same ratio.
16:8	0x0 RO/V	**RP_STATE_RATIO_UNSLICE:** Ratio of the current RP-state, in 16.6Mhz 1xclks. When the graphics engine is in RC6, this field is zeroed out. For the SoC the Unslice and Slice run at the same ratio.
7:0	0x0 RO/V	**RP_STATE_VOLTAGE:** RP-State Voltage GT Target Voltage in U1.7 Volts

44.3.170 TEMPERATURE_TARGET (P_CR_TEMPERATURE_TARGET_0_0_0_MCHBAR)—Offset 7074h

This register contains information about the fan speed control target temperature as well as details on the reference temperature for IA core DTS relative temperature reading.

MSR_Name: TEMPERATURE_TARGET **MSR_Addr**: 0x1A2

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7074h

Default: 005A0000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**RESERVED_1:** Reserved
30:24	0x0 RW	**TJ_MAX_TCC_OFFSET:** This field allows platform software to configure the temperature at which thermal monitor engages to be lower than the manufacturing configured maximum constraint. This field is programmed in 1'C units. E.g., if the default silicon configured maximum temperature is 100'C and this field is configured to 10, then the silicon will engage thermal throttling algorithms at 90'C
23:16	0x5a RO/V	**REF_TEMP:** Tjmax a.k.a. Thermal Monitor activation temperature or Prochot Temperature. This is the maximum junction temperature at which thermal throttling aka thermal monitor is activated. This temperature is the maximum temperature at which the silicon is capable of operating at. All IA core digital thermal sensor readings are reported as a relative negative offset from this reference temperature, such that a read-on of zero implies the cores are running at this temperature.
15:8	0x0 RO/V	**FAN_TEMP_TARGET_OFFSET:** Fan Temperature Target Offset a.k.a. TControl indicates the relative offset from the the Thermal Monitor Trip Temperature at which fans should be engaged.
7:0	0x0 RO	**RESERVED_0:** Reserved

44.3.171 BIOS_RESET_CPL (P_CR_BIOS_RESET_CPL_0_0_0_MCHBAR)—Offset 7078h

This register is used as a means for BIOS to communicate staging to the Punit / Pcode. The exact definition and utility of each bit may differ across products. The general philosophy is that when BIOS is done with stage0, it writes the RST_CPL0 bit and then waits for the PCODE_INIT_DONE0 bit to be set before proceeding to the next step.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7078h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**RESERVED0:** reserved
15	0x0 RO/V	**PCODE_INIT_DONE7:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
14	0x0 RO/V	**PCODE_INIT_DONE6:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
13	0x0 RO/V	**PCODE_INIT_DONE5:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
12	0x0 RO/V	**PCODE_INIT_DONE4:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
11	0x0 RO/V	**PCODE_INIT_DONE3:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
10	0x0 RO/V	**PCODE_INIT_DONE2:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
9	0x0 RO/V	**PCODE_INIT_DONE1:** Pcode sets this bit when it has completed this stage, BIOS must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
8	0x0 RO/V	**PCODE_INIT_DONE:** Pcode has completed its actions in response to Stage0 BIOS Reset complete. Between BIOS Stage0 complete and Pcode Stage0 complete, Pcode will apply all power savings configurations to PCS and will set up C_STATE_LATENCY control MSR settings for IRTL management.
7	0x0 RW	**RST_CPL7:** reset complete
6	0x0 RW	**RST_CPL6:** BIOS sets this bit when it has completed this stage, Pcode must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
5	0x0 RW	**RST_CPL5:** BIOS sets this bit when it has completed this stage, Pcode must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
4	0x0 RW	**RST_CPL4:** BIOS sets this bit when it has completed this stage, Pcode must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
3	0x0 RW	**RST_CPL3:** BIOS sets this bit when it has completed this stage, Pcode must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW	**RST_CPL2:** BIOS sets this bit when it has completed this stage, Pcode must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
1	0x0 RW	**RST_CPL1:** BIOS sets this bit when it has completed this stage, Pcode must wait for this bit to be set before proceeding to the next stage. Stage validity is product-specific and this stage may not be applicable to this product.
0	0x0 RW	**RST_CPL:** Set by BIOS to indicate that all power management configurations as part of reset are complete. This must include Punit patch load done as well as all relevant Punit power management register and mailbox configurations done. Once this bit is set, Punit will allow normal power management to start. Before setting this bit, P-states and C-states support is disabled. BIOS should wait before receiving the Pcode Stage0 reset complete before proceeding with any further steps.

44.3.172 BIOS_MAILBOX_DATA (P_CR_BIOS_MAILBOX_DATA_0_0_0_MCHBAR)—Offset 7080h

Data register for the BIOStoPCODE mailbox. This mailbox is implemented as a means for accessing statistics and implementing BIOS-Pcode handshakes. This register is used in conjunction with BIOS_MAILBOX_INTERFACE.

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7080h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**DATA:** This field contains the data associated with specific commands.

44.3.173 BIOS_MAILBOX_INTERFACE (P_CR_BIOS_MAILBOX_INTERFACE_0_0_0_MCHBAR)—Offset 7084h

Control and Status register for the BIOS to Pcode mailbox. This mailbox is implemented as a means for accessing statistics and implementing BIOS-Pcode handshakes. This register is used in conjunction with BIOS_MAILBOX_DATA.

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7084h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S/V	**RUN_BUSY:** SW may write to the two mailbox registers only when RUN_BUSY is clear(0). Setting RUN_BUSY to 1 will pend a Fast Path event to Pcode. After setting this bit SW will poll this bit until it is cleared. Pcode will clear RUN_BUSY after updating the mailbox registers with the result and error code.
30:29	0x0 RO	**RSVD0:** Reserved
28:8	0x0 RW/V	**ADDRESS:** This field is used to specify an additional parameter to extend the command when needed.
7:0	0x0 RW/V	**COMMAND:** This field contains the SW request command or the Pcode response code depending on the setting of RUN_BUSY.

44.3.174 CORE_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_CORE_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7088h

PUNIT_MMIO: Core Frequency Capabilities This register describes the frequency capabilities of the IA cores. Units are 100MHz multiplied by the ratio. Minimum and maximum ratio fields are initialized by pCode at reset. Last resolved ratio is updated upon changes to the processing system frequency. The efficient ratio is determined by firmware and may be updated dynamically depending on firmware support.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 7088h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**LAST_RESOLVED_FREQ:** Last resolved ratio for the IA cores. Units are 100MHz multiplied by the ratio. This value is updated dynamically whenever the IA core frequency changes.
23:16	0x0 RO/V	**MAX_SUPPORTED_FREQ:** Maximum ratio for the IA cores. Units are 100MHz multiplied by the ratio.
15:8	0x0 RO/V	**EFFICIENT_FREQ:** Firmware-calculated efficient ratio for the IA cores. Units are 100MHz multiplied by the ratio.
7:0	0x0 RO/V	**MIN_SUPPORTED_FREQ:** Minimum supported ratio for the IA cores. Units are 100MHz multiplied by the ratio.

44.3.175 GRAPHICS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_GRAPHICS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 708Ch

PUNIT_MMIO: Graphics Engine Frequency Capabilities This register describes the frequency capabilities of the integrated graphics engine. Units are 50MHz multiplied by the ratio. Minimum and maximum ratio fields are initialized by pCode at reset. Last resolved ratio is updated upon changes to the integrated graphics engine frequency. The efficient ratio is determined by firmware and may be updated dynamically depending on firmware support.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 708Ch

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**LAST_RESOLVED_FREQ:** Last resolved ratio for the integrated graphics engine. Units are 50MHz multiplied by the ratio. This value is updated dynamically whenever the graphics engine frequency changes.
23:16	0x0 RO/V	**MAX_SUPPORTED_FREQ:** Maximum supported ratio for the integrated graphics engine. Units are 50MHz multiplied by the ratio.
15:8	0x0 RO/V	**EFFICIENT_FREQ:** Firmware-calculated efficient ratio for the integrated graphics engine. Units are 50MHz multiplied by the ratio.
7:0	0x0 RO/V	**MIN_SUPPORTED_FREQ:** Minimum supported ratio for the integrated graphics engine. Units are 50MHz multiplied by the ratio.

44.3.176 SYSTEM_AGENT_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_SYSTEM_AGENT_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7090h

PUNIT_MMIO: System Agent Frequency Capabilities This register describes the frequency capabilities of the System Agent. Units are 16.666MHz multiplied by the ratio. Last resolved ratio is updated upon changes to the System Agent frequency.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 7090h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**LAST_RESOLVED_RATIO:** Last resolved System Agent ratio, in units of 16.666MHz.
23:16	0x0 RO/V	**RESERVED_2:** Reserved
15:8	0x0 RO/V	**RESERVED_1:** Reserved
7:0	0x0 RO/V	**RESERVED_0:** Reserved

44.3.177 FAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_FAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7094h

This register reports out the DDR far memory frequency. The actual capabilities of the SOC with respect to DDR frequency is described in the MEMSS_FREQUENCY_CAPABILITIES register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 7094h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**LAST_RESOLVED_RATIO:** This field reports out the DDR far memory frequency in integer multiple. This register reflects what BIOS has programmed as the default DDR frequency
23:16	0x0 RO/V	**RESERVED_2:** Reserved
15:8	0x0 RO/V	**RESERVED_1:** Reserved
7:0	0x0 RO/V	**RESERVED_0:** Reserved

44.3.178 NEAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR (P_CR_NEAR_MEMORY_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7098h

This register reports out the Wide I/O near memory frequency. A value of zero indicates there is no Wide I/O DRAM present. The actual capabilities of the SOC with respect to Wide I/O frequency is described in the MEMSS_FREQUENCY_CAPABILITIES register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 7098h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**LAST_RESOLVED_RATIO:** This field reports out the Wide I/O near memory frequency in integer multiple of 133.33MHz. This register reflects what BIOS has programmed as the default Wide I/O near memory frequency
23:16	0x0 RO/V	**RESERVED_2:** Reserved
15:8	0x0 RO/V	**RESERVED_1:** Reserved
7:0	0x0 RO/V	**RESERVED_0:** Reserved

44.3.179 PACKAGE_POWER_SKU (P_CR_PACKAGE_POWER_SKU_0_0_0_MCHBAR)—Offset 70A0h

This register describes the power SKU of the part and limits on time window and power limit configuration allowed in the RAPL PL1 and PL2 configuration registers.

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0012024000600118h

BAR and Offset: [MCHBAR] + 70A0h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:55	0x0 RO	**RESERVED_3:** Reserved
54:48	0x12 RW	**PKG_MAX_WIN:** The maximal time window allowed to be programmed for RAPL PL1 and PL2 controls for the SKU. Higher values will be clamped to this value. The bits of this field describe parameters for a mathematical equation for time window configuration. This field is split into two sub-fields: • x = bits[6:5] • y = bits[4:0] Time window equation: **time_window = PACKAGE_POWER_SKU_UNIT.TIME_UNIT * ((1+x/4)^y)** **Power Well:** prst
47	0x0 RO	**RESERVED_2:** Reserved
46:32	0x240 RW	**PKG_MAX_PWR:** The maximal package power setting allowed for the SKU. Higher values will be clamped to this value. The maximum setting is typical not guaranteed. The default value for this field is determined by fuses. The units for this value are defined in PACKAGE_POWER_SKU_MSR[PWR_UNIT]. **Power Well:** prst
31	0x0 RO	**RESERVED_1:** Reserved
30:16	0x60 RW	**PKG_MIN_PWR:** The minimal package power setting allowed for the SKU. Lower values may not be achievable by run-time RAPL PL1 and PL2 control algorithms. **Power Well:** prst
15	0x0 RO	**RESERVED_0:** Reserved
14:0	0x118 RW	**PKG_TDP:** The TDP package power setting allowed for the SKU. The units for this value are defined in PACKAGE_POWER_SKU_MSR[PWR_UNIT].

44.3.180 PACKAGE_RAPL_LIMIT (P_CR_PACKAGE_RAPL_LIMIT_0_0_0_MCHBAR)—Offset 70A8h

Package RAPL Power Limit allows a software agent to define power limitation for the package domain. Power limitation is defined in terms of average power usage (Watts) over a time window specified. Two power limits and associated time windows can be specified. These power limits are commonly referred to as PL1 (long time window) and PL2 (short time window). Each power limit provides independent clamping control that would permit the processor cores to go below OS-requested state to meet the power limits. A lock mechanism allow the software agent to enforce power limit settings. Once the lock bit is set, the power limit settings are static and un-modifiable until next RESET.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 70A8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/L	**PKG_PWR_LIM_LOCK:** When set all settings in this register are locked and are treated as Read Only. This lock control is persistent until the next reset. This bit will typically set by BIOS during boot time or resume from Sx.
62:56	0x0 RO	**RESERVED_1:** Reserved
55:49	0x0 RW/L	**PKG_PWR_LIM_2_TIME:** Time window for Power Limit 1 (PL2). This describes the control window of the power limit. This time window is described in an RC time constant format, which means that if 1s is programmed, the power limit constraint really applies at more like 5s. The maximal time window is bounded by PACKAGE_POWER_SKU_MSR.PKG_MAX_WIN. There is no constraint on the minimum programmable time window, however at very short time windows the control algorithms may not be effective. The bits of this field describe parameters for a mathematical equation for time window configuration. This field is split into two sub-fields: • x = bits[6:5] • y = bits[4:0] Time window equation: **time_window = PACKAGE_POWER_SKU_UNIT.TIME_UNIT * ((1+x/4)^y)**
48	0x0 RW/VL	**PKG_CLMP_LIM_2:** Clamp mode control for PL2. • 0 = PL2 power control is prevented from forcing P-states below the base frequency / P1 for any domain in the SOC. • 1 = PL2 power control will take all actions necessary to meet the power target, even if that involves running at clock frequencies below the base frequency / P1 level. In order to ensure proper SOC cooling, it is generally recommended that the clamp mode is always enabled.
47	0x0 RW/VL	**PKG_PWR_LIM_2_EN:** Enable for Power Limit 2 (PL2). Setting this bit activates the power limit and time window defined for PL2.
46:32	0x0 RW/L	**PKG_PWR_LIM_2:** Sets the average power usage limit of the package domain corresponding to the PL2 time window. The power units of this field are specified by the PACKAGE_POWER_SKU_UNIT_MSR.PWR_UNIT. This power limit must be configured by software before it will engage. The PL2 limit is most commonly associated with long time windows (1s and longer), although there are no explicit constraints on what software configures.
31:24	0x0 RO	**RESERVED_0:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
23:17	0x0 RW/L	**PKG_PWR_LIM_1_TIME:** Time window for Power Limit 1 (PL1). This describes the control window of the power limit. This time window is described in an RC time constant format, which means that if 1s is programmed, the power limit constraint really applies at more like 5s. The maximal time window is bounded by PACKAGE_POWER_SKU_MSR.PKG_MAX_WIN. There is no constraint on the minimum programmable time window, however at very short time windows the control algorithms may not be effective. The bits of this field describe parameters for a mathematical equation for time window configuration. This field is split into two sub-fields: • x = bits[6:5] • y = bits[4:0] Time window equation: **time_window = PACKAGE_POWER_SKU_UNIT.TIME_UNIT * ((1+x/4)^y)**
16	0x0 RW/VL	**PKG_CLMP_LIM_1:** Clamp mode control for PL1. • 0 = PL1 power control is prevented from forcing P-states below the base frequency / P1 for any domain in the SOC. • 1 = PL1 power control will take all actions necessary to meet the power target, even if that involves running at clock frequencies below the base frequency / P1 level. In order to ensure proper SOC cooling, it is generally recommended that the clamp mode is always enabled.
15	0x0 RW/VL	**PKG_PWR_LIM_1_EN:** Enable for Power Limit 1 (PL1). Setting this bit activates the power limit and time window defined for PL1.
14:0	0x0 RW/L	**PKG_PWR_LIM_1:** Sets the average power usage limit of the package domain corresponding to the PL1 time window. The power units of this field are specified by the PACKAGE_POWER_SKU_UNIT_MSR.PWR_UNIT. This power limit must be configured by software before it will engage. The PL1 limit is most commonly associated with long time windows (1s and longer), although there are no explicit constraints on what software configures.

44.3.181 IA_PERF_LIMIT_REASONS (P_CR_IA_PERF_LIMIT_REASONS_0_0_0_MCHBAR)—Offset 70B0h

This register reports reasons for performance limitations on the IA cores. Status bits are an instantaneous indication of an active constraint. Log bits indicate that a constraint was enforced since the log bit was last cleared.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 70B0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/0C/V	**QOS_LOG:** Logged indication that frequency was clamped below the software-defined quality-of-service floor. This bit is set by firmware, and is clearable by software.
30	0x0 RW/0C/V	**MAX_EFFICIENCY_FREQ_LOG:** Logged indication that frequency was clamped below the firmware-calculated maximum efficiency frequency. This bit is set by firmware, and is clearable by software.
29	0x0 RW/0C/V	**MCT_LOG:** Logged indication that frequency was clamped due to ratio change transition attenuation. This bit is set by firmware, and is clearable by software.
28	0x0 RW/0C/V	**EDP_LOG:** Logged indication that frequency was clamped due to the package-level Electrical Design Point constraint. This bit is set by firmware, and is clearable by software.
27	0x0 RW/0C/V	**MULTI_CORE_TURBO_LOG:** Logged indication that frequency was clamped due to effective multi-core turbo constraints. This bit is set by firmware, and is clearable by software.
26	0x0 RW/0C/V	**VR_THERMALERT_LOG:** Logged indication that frequency was clamped due to a voltage regulator thermal excursion. This bit is set by firmware, and is clearable by software.
25	0x0 RW/0C/V	**IA_UTILIZATION_LOG:** Logged indication that frequency was clamped due to the autonomous utilization-based P-state control algorithm. This bit is set by firmware, and is clearable by software.
24	0x0 RW/0C/V	**DEV3_LOG:** Logged indication that frequency was clamped due to a Device 3 driver override. This bit is set by firmware, and is clearable by software.
23	0x0 RW/0C/V	**DEV2_LOG:** Logged indication that frequency was clamped due to a Device 2 driver override. This bit is set by firmware, and is clearable by software.
22	0x0 RW/0C/V	**SPARE6_LOG:** Spare log bit. This bit is set by firmware, and is clearable by software.
21	0x0 RW/0C/V	**SPARE5_LOG:** Spare log bit. This bit is set by firmware, and is clearable by software.
20	0x0 RW/0C/V	**SPARE4_LOG:** Spare log bit. This bit is set by firmware, and is clearable by software.
19	0x0 RW/0C/V	**PL2_LOG:** Logged indication that frequency was clamped due to a package-level PL2 excursion. This bit is set by firmware, and is clearable by software.
18	0x0 RW/0C/V	**PL1_LOG:** Logged indication that frequency was clamped due to a package-level PL1 excursion. This bit is set by firmware, and is clearable by software.
17	0x0 RW/0C/V	**THERMAL_LOG:** Logged indication that frequency was clamped due to a thermal excursion. This bit is set by firmware, and is clearable by software.
16	0x0 RW/0C/V	**PROCHOT_LOG:** Logged indication that frequency was clamped due to PROCHOT assertion. This bit is set by firmware, and is clearable by software.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO/V	**QOS_STATUS:** Frequency is limited below the operating system or driver Quality-of-Service floor.
14	0x0 RO/V	**MAX_EFFICIENCY_FREQ_STATUS:** Frequency is limited below the maximum efficiency frequency.
13	0x0 RO/V	**MCT_STATUS:** Frequency is limited due to ratio change transition attenuation (MCT, prevents frequent ratio changes due to core C-state entry/exit).
12	0x0 RO/V	**EDP_STATUS:** Frequency is limited due to a package-level EDP constraint.
11	0x0 RO/V	**MULTI_CORE_TURBO_STATUS:** Frequency is limited due to effective multi-core turbo constraints.
10	0x0 RO/V	**VR_THERMALERT_STATUS:** Frequency is limited due to a VR thermal excursion.
9	0x0 RO/V	**IA_UTILIZATION_STATUS:** Frequency is limited due to autonomous utilization-based P-state control.
8	0x0 RO/V	**DEV3_STATUS:** Frequency is limited due to Dev3 driver override.
7	0x0 RO/V	**DEV2_STATUS:** Frequency is limited due to Dev2 driver override.
6	0x0 RO/V	**SPARE6_STATUS:** Spare status bit.
5	0x0 RO/V	**SPARE5_STATUS:** Spare status bit.
4	0x0 RO/V	**SPARE4_STATUS:** Spare status bit.
3	0x0 RO/V	**PL2_STATUS:** Frequency is limited due to a package-level PL2 excursion.
2	0x0 RO/V	**PL1_STATUS:** Frequency is limited due to a package-level PL1 excursion.
1	0x0 RO/V	**THERMAL_STATUS:** Frequency is limited due to thermal excursion.
0	0x0 RO/V	**PROCHOT_STATUS:** Frequency is limited due to external PROCHOT assertion.

44.3.182 MEMHOT_THERM_STATUS_0_0_0_MCHBAR (P_CR_MEMHOT_THERM_STATUS_0_0_0_MCHBAR)—Offset 70D8h

Memhot indications and logging

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 70D8h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**RESERVED:** Reserved
1	0x0 RW/0C/V	**MEMHOT_LOG:** Set to 1 on MEMHOT_N pin assertion; remains set until cleared via CR write of 1 value or chip reset.
0	0x0 RO/V	**MEMHOT_STATUS:** • 0 = MEMHOT_N pin not asserted • 1 = MEMHOT_N pin is asserted

44.3.183 MEMHOT_THERM_CONFIG_0_0_0_MCHBAR (P_CR_MEMHOT_THERM_CONFIG_0_0_0_MCHBAR)—Offset 70DCh

Configuration data for memhot.

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 70DCh

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**LOCK:** When 1, writes to other MEMHOT_THERM_CONFIG bits are not allowed
30:2	0x0 RO	**RESERVED:** Reserved
1:0	0x0 RW/L	**MEMHOT_THROT_LVL:** • 00 = MEMHOT disabled (no response to pin assertion) • 01 = THRT_MID • 10 = THRT_HI • 11 = THRT_CRIT

44.3.184 MEM_THERM_CTRL_0_0_0_MCHBAR (P_CR_MEM_THERM_CTRL_0_0_0_MCHBAR)—Offset 7200h

Configuration data for OLTT, CLTT, and MEMTRIP

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7200h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:8	0x0 RW	**TEMP_MEMTRIP:** Temperature at which mem trip will be asserted
7:6	0x0 RO	**RSVD1:** Reserved
5	0x0 RO/V	**SMBUSACKD_FLAG:** Set by CLTT SMBus controller when DIMM temperatures are ready to be read. This bit is also used as the valid bit for the DIMM temperatures. Pcode will clear this bit when initiating a new DIMM temperature read request.
4:3	0x0 RW	**OLTT_THROT_LVL:** Throttle level when OLTT is enabled, reuses CLTT throttle levels. • 00 = no throttle • 01 = THRT_MID • 10 = THRT_HI • 11 = THRT_CRIT
2	0x0 RW	**CLTT_MODE:** • 0 = CLTT pass-thru • 1 = CLTT over SMBus (ignore if MTM_MODE = 0)
1	0x0 RW	**MEM_THERM_MGMT_MODE:** Memory thermal mgmt. mode: • 0 = OLTT, • 1 = CLTT
0	0x0 RW	**EN_MEMTRIP:** Mem_thermtrip control. • 0: THERMTRIP is CPU thermal sensor only • 1: THERMTRIP is CPU thermal sensor or mem_thermtrip

44.3.185 MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR (P_CR_MEM_THERM_TEMP_CONFIG_0_0_0_MCHBAR)—Offset 7204h

CLTT temperature thresholds

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7204h

Default: 00645D54h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**RESERVED_0:** Reserved
26:24	0x0 RW	**TEMP_THROT_HYST:** Negative-going threshold hysteresis value. This value is subtracted from the TEMP_* threshold values to determine the point where the asserted status for that threshold will clear as temperature decreases. TEMP_THROT_HYST must be at least 1C less than the minimum delta between adjacent TEMP_* thresholds.
23:16	0x64 RW	**TEMP_HI:** High threshold temperature, 8.8.0ufp. Program so TEMP_HI) TEMP_MID.
15:8	0x5d RW	**TEMP_MID:** Middle threshold temperature, 8.8.0ufp. Program so TEMP_MID (TEMP_HI.
7:0	0x54 RW	**TEMP_LO:** Lower threshold temperature, 8.8.0ufp. Program so TEMP_LO (TEMP_MID.

44.3.186 MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR (P_CR_MEM_THERM_THROT_CONFIG_0_0_0_MCHBAR)—Offset 7208h

CLTT bandwidth throttle levels

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7208h

Default: 00635A00h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED_0:** Reserved
23:16	0x63 RW	**THRT_CRIT:** Throttle level in %BW (= 100, 8.8.0ufp. Default is 99% throttled.
15:8	0x5a RW	**THRT_HI:** Throttle level in %BW (THRT_CRIT, 8.8.0ufp (default is 90% throttled)
7:0	0x0 RW	**THRT_MID:** Throttle level in %BW (THRT_HI , 8.8.0ufp (default is 0% throttled)

44.3.187 MEM_THERM_STATUS_0_0_0_MCHBAR (P_CR_MEM_THERM_STATUS_0_0_0_MCHBAR)—Offset 720Ch

CLTT per-DIMM status/log info

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 720Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RESERVED_3:** Reserved
27:26	0x0 RW/0C/V	**MEM_THERM_THROT_LOG_1_1:** Sticky bits set to highest throttle level achieved (same encoding as MEM_THERM_STATUS bits) when CLTT memory throttling is initiated by channel1, DIMM1; remains set until cleared via CR write of 1 value or chip reset.
25:24	0x0 RO/V	**MEM_THERM_STATUS_1_1:** Status of channel1, DIMM1: 00 = memory temperature (TEMP_LO 01 = TEMP_LO (= mem temp (TEMP_MID 10 = TEMP_MID (= mem temp (TEMP_HI 11 = mem temp)= TEMP_HI
23:20	0x0 RO	**RESERVED_2:** Reserved
19:18	0x0 RW/0C/V	**MEM_THERM_THROT_LOG_1_0:** Sticky bits set to highest throttle level achieved (same encoding as MEM_THERM_STATUS bits) when CLTT memory throttling is initiated by channel1, DIMM0; remains set until cleared via CR write of 1 value or chip reset.
17:16	0x0 RO/V	**MEM_THERM_STATUS_1_0:** Status of channel1, DIMM0: 00 = memory temperature (TEMP_LO 01 = TEMP_LO (= mem temp (TEMP_MID 10 = TEMP_MID (= mem temp (TEMP_HI 11 = mem temp)= TEMP_HI
15:12	0x0 RO	**RESERVED_1:** Reserved
11:10	0x0 RW/0C/V	**MEM_THERM_THROT_LOG_0_1:** Sticky bits set to highest throttle level achieved (same encoding as MEM_THERM_STATUS bits) when CLTT memory throttling is initiated by channel0, DIMM1; remains set until cleared via CR write of 1 value or chip reset.
9:8	0x0 RO/V	**MEM_THERM_STATUS_0_1:** Status of channel0, DIMM1: 00 = memory temperature (TEMP_LO 01 = TEMP_LO (= mem temp (TEMP_MID 10 = TEMP_MID (= mem temp (TEMP_HI 11 = mem temp)= TEMP_HI
7:4	0x0 RO	**RESERVED_0:** Reserved
3:2	0x0 RW/0C/V	**MEM_THERM_THROT_LOG_0_0:** Sticky bits set to highest throttle level achieved (same encoding as MEM_THERM_STATUS bits) when CLTT memory throttling is initiated by channel0, DIMM0; remains set until cleared via CR write of 1 value or chip reset.
1:0	0x0 RO/V	**MEM_THERM_STATUS_0_0:** Status of channel0, DIMM0: 00 = memory temperature (TEMP_LO 01 = TEMP_LO (= mem temp (TEMP_MID 10 = TEMP_MID (= mem temp (TEMP_HI 11 = mem temp)= TEMP_HI

44.3.188 MEM_THERM_INTERRUPT_0_0_0_MCHBAR (P_CR_MEM_THERM_INTERRUPT_0_0_0_MCHBAR)—Offset 7210h

CLTT and customer-configurable interrupt configuration

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7210h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED_1:** Reserved
23	0x0 RW	**RESERVED_2:** Reserved
22:16	0x0 RW	**RESERVED_3:** Reserved
15	0x0 RW	**MEMHOT_SMI_ENABLE:** Enable thermal interrupt generation whenever maximum DIMM_adj_TEMP_x_y value crosses MEM_INT_THRESHOLD1_VALUE
14:8	0x0 RW	**MEM_INT_THRESHOLD1_VALUE:** Configurable memory temperature threshold1 value for thermal interrupt generation, unsigned integer U7.7.0
7:3	0x0 RO	**RESERVED_0:** Reserved
2	0x0 RW	**TEMP_HI_SMI_ENABLE:** Enable interrupt generation whenever maximum DIMM_adj_TEMP_x_y value crosses TEMP_HI
1	0x0 RW	**TEMP_MID_SMI_ENABLE:** Enable interrupt generation whenever maximum DIMM_adj_TEMP_x_y value crosses TEMP_MID
0	0x0 RW	**TEMP_LOW_SMI_ENABLE:** Enable interrupt generation whenever maximum DIMM_adj_TEMP_x_y value crosses TEMP_LO

44.3.189 MEM_THERM_INT_STATUS_0_0_0_MCHBAR (P_CR_MEM_THERM_INT_STATUS_0_0_0_MCHBAR)—Offset 7214h

CLTT and customer-configurable interrupt status and logs

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7214h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/0C/V	**CLTT_SMBUS_HANG_LOG:** Set to 1 the first time CLTT_SMBUS_HANG_STATUS is set and remains sticky until cleared via software or reset.
30	0x0 RO/V	**CLTT_SMBUS_HANG_STATUS:** Indication that the CLTT SMBUS is hung
29	0x0 RW/0C/V	**CLTT_SMBUS_RESET_LOG:** Set to 1 the first time CLTT_SMBUS_RESET_STATUS is set and remains sticky until cleared via software or reset.
28	0x0 RO/V	**CLTT_SMBUS_RESET_STATUS:** Indication that the CLTT SMBUS is reset
27:14	0x0 RO	**RESERVED_0:** Reserved
13	0x0 RW/0C/V	**Reserved**
12	0x0 RO/V	**Reserved**
11	0x0 RW/0C/V	**SOC_MEM_THROTTLE_LOG:** Set to 1 the first time SOC_MEM_THROTTLE_STATUS is set and remains sticky until cleared via software or reset
10	0x0 RO/V	**SOC_MEM_THROTTLE_STATUS:** Temperature is at or above the point to cause SoC memory throttling
9	0x0 RW/0C/V	**RESERVED_LOG:** Reserved
8	0x0 RO/V	**RESERVED_STATUS:** Reserved
7	0x0 RW/0C/V	**MEMHOT_SMI_LOG:** Set to 1 the first time MEM_INT_THRESHOLD1_STATUS is set and remains sticky until cleared via software or reset.
6	0x0 RO/V	**MEMHOT_SMI_STATUS:** Maximum DIMM_adj_TEMP_x_y value is at or above MEM_INT_THRESHOLD1_VALUE
5	0x0 RW/0C/V	**TEMP_HI_SMI_LOG:** Set to 1 the first time TEMP_HI_SMI_STATUS is set and remains sticky until cleared via software or reset.
4	0x0 RO/V	**TEMP_HI_SMI_STATUS:** • 1: MTM is at the TEMP_HI throttle state. • 0: MTM is below the TEMP_HI throttle state.
3	0x0 RW/0C/V	**TEMP_MID_SMI_LOG:** Set to 1 the first time TEMP_MID_SMI_STATUS is set and remains sticky until cleared via software or reset.
2	0x0 RO/V	**TEMP_MID_SMI_STATUS:** • 1: MTM is at the TEMP_MID throttle state. • 0: MTM is below the TEMP_MID throttle state.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW/0C/V	**TEMP_LO_SMI_LOG:** Set to 1 the first time TEMP_LO_SMI_STATUS is set and remains sticky until cleared via software or reset.
0	0x0 RO/V	**TEMP_LO_SMI_STATUS:** • 1: MTM is at or above the TEMP_LO throttle state. • 0: MTM is in the unthrottled state.

44.3.190 MEM_THERM_TEMP_OFST_0_0_0_MCHBAR (P_CR_MEM_THERM_TEMP_OFST_0_0_0_MCHBAR)—Offset 7218h

CLTT per-DIMM temperature offsets

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7218h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RESERVED_3:** Reserved
28:24	0x0 RW	**MEM_TEMP_OFST_DDR_1_1:** 4-bit integer temperature offset value for channel1, DIMM1 TSOD.
23:21	0x0 RO	**RESERVED_2:** Reserved
20:16	0x0 RW	**MEM_TEMP_OFST_DDR_1_0:** 4-bit integer temperature offset value for channel1, DIMM0 TSOD.
15:13	0x0 RO	**RESERVED_1:** Reserved
12:8	0x0 RW	**MEM_TEMP_OFST_DDR_0_1:** 4-bit integer temperature offset value for channel0, DIMM1 TSOD.
7:5	0x0 RO	**RESERVED_0:** Reserved
4:0	0x0 RW	**MEM_TEMP_OFST_DDR_0_0:** 4-bit integer temperature offset value for channel0, DIMM0 TSOD.

44.3.191 TELEM_NEAR_MEMORY_ACTIVE_ACCUMULATOR (P_CR_TELEM_NEAR_MEMORY_ACTIVE_0_0_0_MCHBAR)—Offset 70E0h

This counter measures the total time spent with near memory active, as measured by any rank being in the active or active idle state. The inverse of this counter indicates the total time spent with all near memory in the self-refresh state. This counter counts at the crystal clock frequency divided by 16.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 70E0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0x0 RO/V	**DATA:** This counter measures the total time spent with near memory active, as measured by any rank being in the active or active idle state. The inverse of this counter indicates the total time spent with all near memory in the self-refresh state. This counter counts at the crystal clock frequency divided by 16.

44.3.192 TELEM_FAR_MEMORY_ACTIVE_ACCUMULATOR (P_CR_TELEM_FAR_MEMORY_ACTIVE_0_0_0_MCHBAR)—Offset 70E8h

This counter measures the total time spent with far memory active, as measured by any rank being in the active or active idle state. The inverse of this counter indicates the total time spent with all far memory in the self-refresh state. This counter counts at the crystal clock frequency divided by 16.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 70E8h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0x0 RO/V	**DATA:** This counter measures the total time spent with far memory active, as measured by any rank being in the active or active idle state. The inverse of this counter indicates the total time spent with all far memory in the self-refresh state. This counter counts at the crystal clock frequency divided by 16.

44.3.193 TURBO_ACTIVATION_RATIO (P_CR_TURBO_ACTIVATION_RATIO_0_0_0_MCHBAR)—Offset 70F0h

PUNIT_MSR: Used by software to configure the P-state at which turbo activates. This feature is functionally identical to the ACPI P-state notify supported over PECI (PCS 33). Turbo activation starts at clock ratios above the turbo activation ratio threshold configured in this register.

MSR_Name: TURBO_ACTIVATION_RATIO **MSR_Addr**: 0x64C

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 70F0h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**TURBO_ACTIVATION_RATIO_LOCK:** Write to 1b to lock the setting in this register until next reset
30:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RW/L	**MAX_NON_TURBO_RATIO:** The P-unit will treat any P-state request above this ratio as a request for maximum turbo. Zero is special encoding which disables the feature

44.3.194 C2C3TT_CFG (P_CR_C2C3TT_CFG_0_0_0_MCHBAR)—Offset 7034h

DEPRECATED. This register contains the initial snoop timer (pop-down) value. BIOS can update this value during run-time. Pcode will sample this register at slow loop. If the value has changed since the previous sample and in addition there is no valid Hysteresis parameter (HYS) from a previous PM_DMD or PM_RSP message, then Pcode will configure IMPH_CR_SNP_RELOAD[LIM] with this value. This register is not used by the SoC.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7034h

Default: 00000032h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:0	0x32 RW	**PPDN_INIT:** Value

44.3.195 DTS_CONFIG1_CFG (P_CR_DTS_CONFIG1_CFG_0_0_0_MCHBAR)—Offset 7110h

DEPRECATED. DTS 2.0 is not supported. Location of correction factor F and scale factor C for DTS2.0

bscherka: IVT HSD i1112231 DTS2.0 added this csr isteiner: Moved DTS registers for re-convergence

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7110h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RW/L	**RSVD1:** Reserved
28:16	0x0 RW/L	**C:** Scale factor C May be unlocked for select OEMs
15:13	0x0 RW/L	**RSVD:** reserved
12:0	0x0 RW/L	**F:** Correction Factor F May be unlocked for select OEMs

44.3.196 DTS_CONFIG2_CFG (P_CR_DTS_CONFIG2_CFG_0_0_0_MCHBAR)—Offset 7114h

DEPRECATED. DTS 2.0 is not supported. Location of time constant coefficients for implementation.

bscherka: IVT HSD i1112231 added this csr isteiner: Moved DTS registers for re-convergence

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7114h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RW/L	**RSVD1:** Reserved be4538196 - attached to correct fuse
28:16	0x0 RW/L	**AS:** Time constant coefficient AS May be unlocked for select OEMs
15:13	0x0 RW/L	**RSVD:** reserved
12:0	0x0 RW/L	**AF:** Time constant coefficient AF May be unlocked for select OEMs

44.3.197 DTS_CONFIG3_CFG (P_CR_DTS_CONFIG3_CFG_0_0_0_MCHBAR)—Offset 7118h

Location of Tcontrol_offset for DTS2.0

bscherka: IVT added HSD i1112231 isteiner: Moved DTS registers for re-convergence

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7118h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RSVD0:** Reserved
28	0x0 RW/L	**OFFSET_PROGRAMMED:** Bit that the offset was programmed.
27:8	0x0 RO	**RSVD1:** Reserved
7:0	0x0 RW/L	**TCONTROL_OFFSET:** Offset to modify Tcontrol for DTS2.0

44.3.198 SOUTH_IO_PORT_STATUS3 (P_CR_SOUTH_IO_PORT_STATUS3_0_0_0_MCHBAR)—Offset 711Ch

Power meter data for south IPs

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 711Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:26	0x0 RW	**RSVD:** reserved
25:24	0x0 RW	**GBE_PORTS:** Snapshot of the number of GBE lanes for power meter.
23:16	0x0 RW	**PCIE_LANES:** Snapshot of the number of PCIE lanes for power meter.
15:8	0x0 RW	**SATA_LANES:** Snapshot of the number of SATA lanes for power meter.
7:4	0x0 RW	**USB3_LANES:** Snapshot of the number of USB3 lanes for power meter.
3:0	0x0 RW	**USB2_LANES:** Snapshot of the number of USB2 lanes for power meter.

44.3.199 DRAM_BIOS_INFO (P_CR_DRAM_BIOS_INFO_0_0_0_MCHBAR)—Offset 7128h

This register provides DRAM interface information for initial boot and SPD warm reset. It is populated by Pcode and read by BIOS.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7128h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW	**Reserved:** Reserved
23:16	0x0 RW	**CURRENT_VID_VALUE:** Current voltage of VDDQ SVID Rail.
15:12	0x0 RW	**RSVD1:** Reserved
11	0x0 RW	**SPD_RESET_STATUS:** This field indicates to BIOS that a SPD Warm Reset has already occurred.
10:8	0x0 RW	**DDR_CURRENT_FREQ:** This field indicates the current DDR IO clock frequency.
7:4	0x0 RW	**RSVD2:** Reserved
3	0x0 RW	**Reserved:** Reserved
2:0	0x0 RW	**DDR_MAX_FREQ_LIMIT:** This field indicates to BIOS the Maximum supported DDR frequency for this product. Pcode populates this information from fuses. For the DDR_MAX_Freg_Limit, the value always shows 4 (100b). • 000b = 1600 MHz • 001b = 1833 MHz • 010b = 2133 MHz • 011b = 2400 MHz • 100b = 2666 MHz

44.3.200 ADR_COMMAND (P_CR_ADR_COMMAND_0_0_0_MCHBAR)—Offset 712Ch

This register provides PMC Firmware the ability to trigger an ADR (Asynchronous DRAM Self-Refresh). Fast path event for Pcode to take action and flush context information to DRAMs on imminent power loss.

THIS REGISTER IS DUPLICATED IN THE PCU IO SPACE, XML CHANGES MUST BE MADE IN BOTH PLACES

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 712Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:1	0x0 RW/V	**Reserved:** Reserved
0	0x0 RW/V	**L2_FLUSH:** Flush the L2 cache on all modules as part of the ADR flow.

44.3.201 DRAM_POWER_INFO (P_CR_DRAM_POWER_INFO_0_0_0_MCHBAR)—Offset 7130h

PUNIT_MSR: MSR for DRAM power information **MSR_Name**: DRAM_POWER_INFO
MSR_Addr: 0x61C

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 7130h

Default: 0028000000000118h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/L	**LOCK:** The Spec power allowed for DRAM. The TDP setting is typical (not guaranteed).
62:55	0x0 RO	**RSVD0:** Reserved
54:48	0x28 RW/L	**DRAM_MAX_WIN:** The maximal time window allowed for the DRAM. Higher values will be clamped to this value. x = PKG_MAX_WIN[54:53], y = PKG_MAX_WIN[52:48]. The timing interval window is Floating Point number given by 1.x * power(2,y).
47	0x0 RO	**RSVD1:** Reserved
46:32	0x0 RW/L	**DRAM_MAX_PWR:** The maximal power setting allowed for DRAM. Higher values will be clamped to this value. The maximum setting is typical (not guaranteed).
31	0x0 RO	**RSVD2:** Reserved
30:16	0x0 RW/L	**DRAM_MIN_PWR:** The minimal power setting allowed for DRAM. Lower values will be clamped to this value. The minimum setting is typical (not guaranteed).
15	0x0 RO	**RSVD3:** Reserved
14:0	0x118 RW/L	**DRAM_TDP:** The Spec power allowed for DRAM. The TDP setting is typical (not guaranteed).

44.3.202 PCODE_WRITE_SPARE (P_CR_PCODE_WRITE_SPARE_0_0_0_MCHBAR)—Offset 7138h

Spare register for future use

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7138h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**SPARE_BITS:** spare bits for stepping ID use

44.3.203 PACKAGE_TEMPERATURES_0_0_0_MCHBAR (P_CR_PACKAGE_TEMPERATURES_0_0_0_MCHBAR)—Offset 70F4h

Read-only register used for monitoring thermal status from all domains in the package.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 70F4h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**SA_Temperature:** System agent domain max temperature in degrees C. Reported in a signed, 2's complement format with the LSB representing 1'C resolution (S8.7.0). Raw, unfiltered
23:16	0x0 RO/V	**Reserved:** Reserved
15:8	0x0 RO/V	**Reserved:** Reserved
7:0	0x0 RO/V	**IA_Temperature:** Virtual max temperature of all IA cores in degrees C. Reported in a signed, 2's complement format with the LSB representing 1'C resolution (S8.7.0). Raw, unfiltered

44.3.204 MEMSS_FREQUENCY_CAPABILITIES (P_CR_MEMSS_FREQUENCY_CAPABILITIES_0_0_0_MCHBAR)—Offset 7108h

Describes the minimum and maximum frequency capabilities of LPDDR and WideIO on this particular SOC. If the maximum supported frequency reports a zero for LPDDR or WideIO, it indicates that the respective DRAM technology is not supported on this product.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7108h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RW	**NUM_NM_CH:** Reserved.
29:24	0x0 RW	**WIO_FREQ:** Reserved.
23:18	0x0 RW	**LP4_FREQ_HIGH:** Reserved.
17:12	0x0 RW	**LP4_FREQ_LOW:** Reserved.
11:6	0x0 RW	**LP3_FREQ_HIGH:** Reserved.
5:0	0x0 RW	**LP3_FREQ_LOW:** Reserved.

44.3.205 PP1_C0_CORE_CLOCK_0_0_0_MCHBAR (P_CR_PP1_C0_CORE_CLOCK_0_0_0_MCHBAR)—Offset 7160h

GT RC0 residency counter. Holds the accumulated number of CS clks that GT has been in RC0.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7160h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**DATA:** Accumulated cycles GT has been in RC0.

44.3.206 Core Exists Vector (P_CR_CORE_EXISTS_VECTOR_0_0_0_MCHBAR)—Offset 7164h

Indication of the physical presence of IA cores in this silicon. IA core modules are defined as containing pairs of cores and an associated L2 cache. Module existence can therefore be inferred by OR'ing pairs of COREx_EXISTS in this register. This register does not reflect the impact of any software-based core disabling. It always reflects the capabilities of the silicon.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7164h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW	**CORE15_EXISTS:** A 1 indicates this core is enabled in the SoC.
14	0x0 RW	**CORE14_EXISTS:** A 1 indicates this core is enabled in the SoC.
13	0x0 RW	**CORE13_EXISTS:** A 1 indicates this core is enabled in the SoC.
12	0x0 RW	**CORE12_EXISTS:** A 1 indicates this core is enabled in the SoC.
11	0x0 RW	**CORE11_EXISTS:** A 1 indicates this core is enabled in the SoC.
10	0x0 RW	**CORE10_EXISTS:** A 1 indicates this core is enabled in the SoC.
9	0x0 RW	**CORE9_EXISTS:** A 1 indicates this core is enabled in the SoC.
8	0x0 RW	**CORE8_EXISTS:** A 1 indicates this core is enabled in the SoC.
7	0x0 RW	**CORE7_EXISTS:** A 1 indicates this core is enabled in the SoC.
6	0x0 RW	**CORE6_EXISTS:** A 1 indicates this core is enabled in the SoC.
5	0x0 RW	**CORE5_EXISTS:** A 1 indicates this core is enabled in the SoC.
4	0x0 RW	**CORE4_EXISTS:** A 1 indicates this core is enabled in the SoC.
3	0x0 RW	**CORE3_EXISTS:** A 1 indicates this core is enabled in the SoC.
2	0x0 RW	**CORE2_EXISTS:** A 1 indicates this core is enabled in the SoC.
1	0x0 RW	**CORE1_EXISTS:** A 1 indicates this core is enabled in the SoC.
0	0x0 RW	**CORE0_EXISTS:** A 1 indicates this core is enabled in the SoC.

44.3.207 Software Core Disable Mask (P_CR_CORE_DISABLE_MASK_0_0_0_MCHBAR)—Offset 7168h

Software may disable cores using this interface. The bit definition of this register exactly matches that defined in the CORE_EXISTS_VECTOR register. The flow is as follows:

- Cold boot
- BIOS reads CORE_EXISTS_VECTOR to establish which modules and cores are present
- BIOS writes 1b to the corresponding core that it wishes to **disable**.
- BIOS may disable entire modules by writing 1b to a pair of cores.
- The results of the configuration are maintained in the sustain power well.
- BIOS initiates a cold reset flow at the platform. In a cold reset, the sustain power well maintains power most other rails are power cycled.
- On cold reset exit, launches only the cores requested by BIOS. To software, it will appear as if these cores do not exist.

Software may discover the resolved core exists vector: resolved_core_exists_vector = (!CORE_DISABLE_MASK) and CORE_EXISTS_VECTOR

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7168h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW	**CORE15_DISABLE_MASK:** core15 disable mask **Power Well:** prst
14	0x0 RW	**CORE14_DISABLE_MASK:** core14 disable mask **Power Well:** prst
13	0x0 RW	**CORE13_DISABLE_MASK:** core13 disable mask **Power Well:** prst
12	0x0 RW	**CORE12_DISABLE_MASK:** core12 disable mask **Power Well:** prst
11	0x0 RW	**CORE11_DISABLE_MASK:** core11 disable mask **Power Well:** prst
10	0x0 RW	**CORE10_DISABLE_MASK:** core10 disable mask **Power Well:** prst
9	0x0 RW	**CORE9_DISABLE_MASK:** core9 disable mask **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
8	0x0 RW	**CORE8_DISABLE_MASK:** core8 disable mask **Power Well:** prst
7	0x0 RW	**CORE7_DISABLE_MASK:** core7 disable mask **Power Well:** prst
6	0x0 RW	**CORE6_DISABLE_MASK:** core6 disable mask **Power Well:** prst
5	0x0 RW	**CORE5_DISABLE_MASK:** core5 disable mask **Power Well:** prst
4	0x0 RW	**CORE4_DISABLE_MASK:** core4 disable mask **Power Well:** prst
3	0x0 RW	**CORE3_DISABLE_MASK:** core3 disable mask **Power Well:** prst
2	0x0 RW	**CORE2_DISABLE_MASK:** core2 disable mask **Power Well:** prst
1	0x0 RW	**CORE1_DISABLE_MASK:** core1 disable mask **Power Well:** prst
0	0x0 RW	**CORE0_DISABLE_MASK:** core0 disable mask **Power Well:** prst

44.3.208 PL3_CONTROL_MCHBAR (P_CR_PL3_CONTROL_0_0_0_MCHBAR)—Offset 71F0h

Control Power Limit 3 (PL3) and Power Limit 4 (PL4) using this register. This limit control is physically different from the same control in the IA core MSR space.

- PL3 is designed to clamp peak sustained power to levels supported by the battery or input power supply and as such manage lifetime degradation of that power delivery element. With PL3, peak power excursions above the limit are allowed so long as they do not exceed the configured duty cycle constraint in this register.
- PL4 is designed to clamp peak instantaneous power to levels below the max supported by the battery or input power supply. These clamps are implemented a priori and the SOC is guaranteed to constrain itself below the PL4 limit always.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 71F0h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/L	**LOCK:** Write a 1b to lock this register until next reset. Once locked, no further updates may be written to any bits in the register.
62:48	0x0 RO	**RSVD0:** Reserved
47	0x0 RW/L	**PL4_ENABLE:** • 0 = disabled • 1 = enabled
46:32	0x0 RW/L	**PMAX:** Power Limit 'PL4' or Pmax power limit in the units as described PACAKGE_POWER_SKU_UNIT MSR. The SoC guarantees it will never exceed this power limit even for very short time windows.
31	0x0 RO	**RSVD1:** Reserved
30:24	0x0 RW/L	**DUTY_CYCLE:** Power limit excursion duty cycle control for PL3, describing what percentage of time it is allowed for the SOC to exceed the programmed PL3 power limit. 0% implies excursions are not supported ever and 100% implies excursions are always allowed (effectively disabling the feature). Units are in percentage(%). E.g., to allow for 20% excursion time and 80% PL3 power limit clamp time, program a value of 14h. Values greater than 100 (64h) are clipped to 100%.
23:17	0x0 RW/L	**TIME_WINDOW:** Duration over which duty cycle control will be maintained. The bits of this field describe parameters for a mathematical equation for time window configuration. This time window is strictly adhered to, if the window described is 40ms, then silicon guarantees no excursions to the programmed duty cycle within a rolling 40ms window. This field is split into two sub-fields: • x = bits[6:5] • y = bits[4:0] Time window equation: **time_window = PACKAGE_POWER_SKU_UNIT.TIME_UNIT * ((1+x/4)^y)**
16	0x0 RO	**RSVD2:** Reserved
15	0x0 RW/L	**PL3_ENABLE:** • 0 = disabled • 1 = enabled

Bit Range	Default & Access	Field Name (ID): Description
14:0	0x0 RW/L	**POWER_LIMIT:** Power Limit 3 (PL3) or PAppMax power level. Any SoC power measurement observed above this level is considered as an excursion against the PL3 power limit and duty cycle / time window budget. Units of this power limit are defined by PACKAGE_POWER_SKU_UNIT_MSR.PWR_UNIT.

44.3.209 CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL1_0_0_0_MCHBAR)—Offset 7220h

Config TDP level n. There are 3 instances of this register for 3 different levels.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 7220h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RO	**RSVD0:** Reserved
62:48	0x0 RW	**PKG_MIN_POWER:** Min Power of SKU (units from PKG_POWER_SKU_UNIT)
47	0x0 RO	**RSVD1:** Reserved
46:32	0x0 RW	**PKG_MAX_POWER:** Max Power of SKU
31:24	0x0 RO	**RSVD2:** Reserved
23:16	0x0 RW	**TDP_RATIO:** TDP ratio for this level
15	0x0 RO	**RSVD3:** Reserved
14:0	0x0 RW	**TDP_POWER_VALUE:** TDP power value (Units from PKG_POWER_SKU_UNIT)

44.3.210 CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL2_0_0_0_MCHBAR)—Offset 7228h

Config TDP level n. There are 3 instances of this register for 3 different levels.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [MCHBAR] + 7228h

Default: 0000000000000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RO	**RSVD0:** Reserved
62:48	0x0 RW	**PKG_MIN_POWER:** Min Power of SKU (units from PKG_POWER_SKU_UNIT)
47	0x0 RO	**RSVD1:** Reserved
46:32	0x0 RW	**PKG_MAX_POWER:** Max Power of SKU
31:24	0x0 RO	**RSVD2:** Reserved
23:16	0x0 RW	**TDP_RATIO:** TDP ratio for this level
15	0x0 RO	**RSVD3:** Reserved
14:0	0x0 RW	**TDP_POWER_VALUE:** TDP power value (Units from PKG_POWER_SKU_UNIT)

44.3.211 CONFIG_TDP_LEVEL (P_CR_CONFIG_TDP_LEVEL3_0_0_0_MCHBAR)—Offset 7230h

Config TDP level n. There are 3 instances of this register for 3 different levels.

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [MCHBAR] + 7230h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RO	**RSVD0:** Reserved
62:48	0x0 RW	**PKG_MIN_POWER:** Min Power of SKU (units from PKG_POWER_SKU_UNIT)
47	0x0 RO	**RSVD1:** Reserved
46:32	0x0 RW	**PKG_MAX_POWER:** Max Power of SKU
31:24	0x0 RO	**RSVD2:** Reserved
23:16	0x0 RW	**TDP_RATIO:** TDP ratio for this level
15	0x0 RO	**RSVD3:** Reserved
14:0	0x0 RW	**TDP_POWER_VALUE:** TDP power value (Units from PKG_POWER_SKU_UNIT)

44.3.212 CONFIG_TDP_CONTROL (P_CR_CONFIG_TDP_CONTROL_0_0_0_MCHBAR)—Offset 7238h

Config TDP control

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MCHBAR] + 7238h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**CONFIG_TDP_LOCK:** Lock this register. BIOS should set this after selecting ConfigTDP level
30:2	0x0 RO	**RSVD0:** Reserved
1:0	0x0 RW/L	**CONFIG_TDP_LEVEL:** Used to select which configTDP level is desired

44.3.213 CONFIG_TDP_NOMINAL (P_CR_CONFIG_TDP_NOMINAL_0_0_0_MCHBAR)—Offset 723Ch

Config TDP nominal

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 723Ch

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RW	**TDP_RATIO:** Config TDP ratio

44.3.214 Graphics Superqueue Active Clocks (P_CR_PP1_ANY_THREAD_ACTIVITY_0_0_0_MCHBAR)—Offset 7244h

Graphics Superqueue active residency counter. Counts at ART)) 4.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MCHBAR] + 7244h

Default: 00000000h

MCHBAR Type: PCI Configuration Register (Size: 64 bits)
MCHBAR Reference: [B:0, D:0, F:0] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**SUPERQUEUE_ACTIVE_RESIDENCY:** Graphics Superqueue active residency counter. Counts in 19.2MHz reference clocks.

44.3.215 B-Unit Copy of Default VTd BAR PMEN (B_CR_PMEN_REG_0_0_0_DEFVTDBAR)—Offset 64h

B-Unit copy of the Default VTd BAR PMEN register. Bit 31 is the only bit used for B-Unit.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 64h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: MCHBAR + 6C80)h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/V	**EPM:** This field controls DMA accesses to the protected lowmemory and protected highmemory regions. • 0: Protected memory regions are disabled. • 1: Protected memory regions are enabled.
30:1	0x0 RO	**Reserved (RESERVED_0):** Reserved.
0	0x0 RO	**PRS Unused (PRS):** Unused by the B-Unit. This field indicates the status of protected memory regions: • 0: Protected memory regions are disabled. • 1: Protected memory regions are enabled.

44.3.216 B-Unit Copy of Default VTd BAR PLM Base Register (B_CR_PLMBASE_REG_0_0_0_DEFVTDBAR)—Offset 68h

Register to set up the base address of DMA-protected low-memory region below 4GB. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled. This register is always treated as RO for implementations not supporting protected low memory region (PLMR field reported as Clear in the Capability register). The alignment of the protected low memory region base depends on the number of reserved bits (N:0) of this register. Software may determine N by writing all 1s to this register, and finding the most significant bit position with 0 in the value read back from the register. Bits N:0 of this register are decoded by hardware as all 0s. Software must setup the protected low memory region below 4GB. Section 10.4.18 of the Intel Virtualization Technology for Directed I/O: Spec describes the Protected Low-Memory Limit register and hardware decoding of these registers. Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 68h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: MCHBAR + 6C80)h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW/V	**Protected Low Memory Base (PLMB):** This register specifies the base of the protected low-memory region in system memory.
19:0	0x0 RO	**Reserved (RESERVED_0):** Reserved.

44.3.217 B-Unit Copy of Default VTd BAR PLM Limit Register (B_CR_PLMLIMIT_REG_0_0_0_DEFVTDBAR)—Offset 6Ch

This register sets up the limit address of DMA-protected low-memory region below 4GB. This register must be set up before enabling protected memory through PMEN_REG, and it must not be updated when protected memory regions are enabled. This register is always treated as RO for implementations not supporting protected low memory region (PLMR field reported as Clear in the Capability register). The alignment of the protected low memory region limit depends on the number of reserved bits (N:0) of this register. Software may determine N by writing all 1's to this register, and then finding most significant zero bit position with 0 in the value read back from the register. Bits N:0 of the limit register are decoded by hardware as all 1s.

The Protected low-memory base and limit registers function as follows:

Programming the protected low-memory base and limit registers with the same value in bits 31:(N+1) specifies a protected low-memory region of size 2^(N+1) bytes. Programming the protected low-memory limit register with a value less than the protected low-memory base register disables the protected low-memory region. Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [DEFVTDBAR] + 6Ch

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: MCHBAR + 6C80)h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW/V	**Protected Low Memory Limit (PLML):** This register specifies the last host physical address of the DMAprotected lowmemory region in system memory.
19:0	0x0 RO	**Reserved (RESERVED_0):** Reserved.

44.3.218 B-Unit Copy of Default VTd BAR PHM Base Register (B_CR_PHMBASE_REG_0_0_0_DEFVTDBAR)—Offset 70h

This is the register to set up the base address of the DMA-protected high-memory region. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled. This register is always treated as RO for implementations not supporting protected high memory region (PHMR field reported as Clear in the Capability register). The alignment of the protected high memory region base depends on the number of reserved bits (N:0) of this register. Software may determine N by writing all 1's to this register, and finding most significant zero bit position below host address width (HAW) in the value read back from the register. Bits N:0 of this register are decoded by hardware as all 0s. Software may setup the protected high memory region either above or below 4GB. Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 70h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: MCHBAR + 6C80)h

Bit Range	Default & Access	Field Name (ID): Description
63:39	0x0 RO	**Reserved (RESERVED_1):** Reserved.
38:20	0x0 RW/V	**Protected High Memory Base (PHMB):** This register specifies the base of protected high memory region in system memory. Hardware ignores and does not implement bits 63:HAW, where HAW is the host address width.
19:0	0x0 RO	**Reserved (RESERVED_0):** Reserved.

44.3.219 B-Unit Copy of Default VTd BAR PHM Limit Register (B_CR_PHMLIMIT_REG_0_0_0_DEFVTDBAR)—Offset 78h

Register to set up the limit address of DMA-protected high-memory region. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled. This register is always treated as RO for implementations not supporting protected high memory region (PHMR field reported as Clear in the Capability register). The alignment of the protected high memory region limit depends on the number of reserved bits (N:0) of this register. Software may determine the value of N by writing all ones to this register, and finding most significant zero bit position below host address width (HAW) in the value read back from the register. Bits N:0 of the limit register are decoded by hardware as all ones.

The protected high-memory base and limit registers function as follows:

Programming the protected low-memory base and limit registers with the same value in bits HAW:(N+1) specifies a protected low-memory region of size 2^(N+1) bytes. Programming the protected high-memory limit register with a value less than the protected high-memory base register disables the protected high-memory region. Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 78h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: MCHBAR + 6C80)h

Bit Range	Default & Access	Field Name (ID): Description
63:39	0x0 RO	**Reserved (RESERVED_1):** Reserved.
38:20	0x0 RW/V	**Protected High Memory Limit (PHML):** This register specifies the last host physical address of the DMA protected high memory region in system memory. Hardware ignores and does not implement bits 63:HAW where HAW is the host address width.
19:0	0x0 RO	**Reserved (RESERVED_0):** Reserved.

44.4 Registers in Memory Space—DEFVTDBAR

44.4.1 Version Register (VER_REG_0_0_0_VTDBAR)—Offset 0h

Register to report the architecture version supported. Backward compatibility for the architecture is maintained with new revision numbers, allowing software to load remapping hardware drivers written for prior architecture versions.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 0h

Default: 00000010h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:4	0x1 RO	**Major Version Number (MAJOR):** Indicates supported architecture version.
3:0	0x0 RO	**Minor Version Number (MINOR):** Indicates supported architecture minor version.

44.4.2 Capability Register (CAP_REG_0_0_0_VTDBAR)—Offset 8h

Register to report general remapping hardware capabilities.

Note: These values can change based on defeature bits.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 8h

Default: 00D2008C40660462h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:57	0x0 RO	**Reserved:** Reserved
56	0x0 RO	**First Level 64-KByte Page SupportP (FL1GP):** A value of 1 in this field indicates 1-GByte page size is supported for first-level translation.
55	0x1 RO	**Read Draining (DRD):** • 0 = Hardware does not support draining of DMA read requests. • 1 = Hardware supports draining of DMA read requests.
54	0x1 RO	**Write Draining (DWD):** • 0 = Hardware does not support draining of DMA write requests. • 1 = Hardware supports draining of DMA write requests.
53:48	0x12 RO	**Reserved:** Reserved
47:40	0x0 RO	**Reserved:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
39	0x1 RO	**Reserved:** Reserved
38	0x0 RO	**Reserved:** Reserved
37:34	0x3 RO	**Second Level Large Page Support (SLLPS):** This field indicates the super page sizes supported by hardware. A 3 = 48-bit offset to page frame (1TB)
33:24	0x40 RO	**Reserved:** Reserved
23	0x0 RO	**Reserved:** Reserved
22	0x1 RO	**Reserved:** Reserved
21:16	0x26 RO	**Reserved:** Reserved
15:13	0x0 RO	**Reserved:** Reserved
12:8	0x4 RO	**Reserved:** Reserved
7	0x0 RO	**Caching Mode (CM):** • 0 = Not-present and erroneous entries are not cached in any of the remapping caches. Invalidations are not required for modifications to individual not present or invalid entries. However, any modifications that result in decreasing the effective permissions or partial permission increases require invalidations for them to be effective. • 1 = Not-present and erroneous mappings may be cached in the remapping caches. Any software updates to the remapping structures (including updates to not-present or erroneous entries) require explicit invalidation.
6	0x1 RO	**Protected High-Memory Region (PHMR):** • 0 = Indicates protected high-memory region is not supported. • 1 = Indicates protected high-memory region is supported.
5	0x1 RO	**Protected Low-Memory Region (PLMR):** • 0 = Indicates protected low-memory region is not supported. • 1 = Indicates protected low-memory region is supported.
4	0x0 RO	**Required Write-Buffer Flushing (RWBF):** • 0 = Indicates no write-buffer flushing is needed to ensure changes to memory-resident structures are visible to hardware. • 1 = Indicates software must explicitly flush the write buffers to ensure updates made to memory-resident remapping structures are visible to hardware.
3	0x0 RO	**Advanced Fault Logging (AFL):** • 0 = Indicates advanced fault logging is not supported. Only primary fault logging is supported. • 1 = Indicates advanced fault logging is supported.
2:0	0x2 RO	**Number of Domains Supported (ND):** • 010b = Hardware supports 8-bit domain-ids with support for up to 256 domains.

44.4.3 Extended Capability Register (ECAP_REG_0_0_0_VTDBAR)—Offset 10h

Register to report remapping hardware extended capabilities. Note: These values can change based on defeature bits.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 10h

Default: 0000000000F050DAh

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:40	0x0 RO	**RSVD0:** Reserved
39:35	0x0 RO	**PASID Size Supported (PSS):** This field reports the PASID size supported by the remapping hardware for requests-with-PASID. A value of N in this field indicates hardware supports PASID field of N+1 bits (For example, value of 7 in this field, indicates 8-bit PASIDs are supported). Requests-with-PASID with PASID value beyond the limit specified by this field are treated as error by the remapping hardware. This field is valid only when PASID field is reported as Set.
34	0x0 RO	**Extended Accessed Flag Support (EAFS):** • 0 = Hardware does not support the extended-accessed (EA) bit in first-level paging-structure entries. • 1 = Hardware supports the extended accessed (EA) bit in first-level paging-structure entries. This field is valid only when PASID field is reported as Set.
33	0x0 RO	**No Write Flag Support (NWFS):** • 0 = Hardware ignores the No Write (NW) flag in Device-TLB translation requests, and behaves as if NW is always 0. • 1 = Hardware supports the No Write (NW) flag in Device-TLB translation requests. This field is valid only when Device-TLB support (DT) field is reported as Set.
32	0x0 RO	**PASID-Only Translations (POT):** • 0 = Hardware does not support PASID-only Translation Type in extended-context-entries. • 1 = Hardware supports PASID-only Translation Type in extended-context-entries. This field is valid only when PASID field is reported as Set.
31	0x0 RO	**Supervisor Request Support (SRS):** • 0 = H/W does not support requests-with-PASID seeking supervisor privilege. • 1 = H/W supports requests-with-PASID seeking supervisor privilege. The field is valid only when PASID field is reported as Set.
30	0x0 RO	**Execute Request Support (ERS):** • 0 = H/W does not support requests-with-PASID seeking execute permission. • 1 = H/W supports requests-with-PASID seeking execute permission. This field is valid only when PASID field is reported as Set.
29	0x0 RO	**Page Request Support (PRS):** • 0 = Hardware does not support Page Requests. • 1 = Hardware supports Page Requests This field is valid only when Device-TLB (DT) field is reported as Set.

Bit Range	Default & Access	Field Name (ID): Description
28	0x0 RO	**Process Address Space ID Support (PASID):** • 0 = Hardware does not support requests tagged with Process Address Space IDs. • 1 = Hardware supports requests tagged with Process Address Space IDs.
27	0x0 RO	**Deferred Invalidate Support (DIS):** • 0 = Hardware does not support deferred invalidations of IOTLB and Device-TLB. • 1 = Hardware supports deferred invalidations of IOTLB and Device-TLB. This field is valid only when PASID field is reported as Set.
26	0x0 RO	**Nested Translation Support (NEST):** • 0 = Hardware does not support nested translations. • 1 = Hardware supports nested translations. This field is valid only when PASID field is reported as Set.
25	0x0 RO	**Memory Type Support (MTS):** • 0 = Hardware does not support Memory Type in first-level translation and Extended Memory type in second-level translation. • 1 = Hardware supports Memory Type in first-level translation and Extended Memory type in second-level translation. This field is valid only when PASID and ECS fields are reported as Set. Remapping hardware units with, one or more devices that operate in processor coherency domain, under its scope must report this field as Set.
24	0x0 RO	**Extended Context Support (ECS):** • 0 = Hardware does not support extended-root-entries and extended-context-entries. • 1 = Hardware supports extended-root-entries and extended-context-entries. Implementations reporting PASID or PRS fields as Set, must report this field as Set.
23:20	0xf RO	**Maximum Handle Mask Value (MHMV):** The value in this field indicates the maximum supported value for the Handle Mask (HM) field in the interrupt entry cache invalidation descriptor (iec_inv_dsc). This field is valid only when the IR field in Extended Capability register is reported as Set.
19:18	0x0 RO	**RSVD1:** Reserved
17:8	0x50 RO	**IOTLB Register Offset (IRO):** This field specifies the offset to the IOTLB registers relative to the register base address of this remapping hardware unit. If the register base address is X, and the value reported in this field is Y, the address for the first IOTLB invalidation register is calculated as X+(16*Y).
7	0x1 RO	**Snoop Control (SC):** • 0 = Hardware does not support 1-setting of the SNP field in the page-table entries. • 1 = Hardware supports the 1-setting of the SNP field in the page-table entries.
6	0x1 RO	**Pass Through (PT):** • 0 = Hardware does not support pass-through translation type in context entries and extended-context-entries. • 1 = Hardware supports pass-through translation type in context entries and extended-context-entries. Pass-through translation is specified through Translation-Type (T) field value of 10b in context-entries, or T field value of 010b in extended-context-entries. Hardware implementations supporting PASID must report a value of 1b in this field.
5	0x0 RO	**RSVD2:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
4	0x1 RO	**Extended Interrupt Mode (EIM):** • 0 = On Intel64 platforms, hardware supports only 8-bit APIC-IDs (xAPIC mode). • 1 = On Intel64 platforms, hardware supports 32-bit APIC-IDs (x2APIC mode). This field is valid only on Intel64 platforms reporting Interrupt Remapping support (IR field Set).
3	0x1 RO	**Interrupt Remapping Suport (IR):** • 0 = Hardware does not support interrupt remapping. • 1 = Hardware supports interrupt remapping. Implementations reporting this field as Set must also support Queued Invalidation (QI).
2	0x0 RO	**Device-TLB Support (DT):** • 0 = Hardware does not support device-IOTLBs. • 1 = Hardware supports Device-IOTLBs. Implementations reporting this field as Set must also support Queued Invalidation (QI). Hardware implementations supporting I/O Page Requests (PRS field Set in Extended Capability register) must report a value of 1b in this field.
1	0x1 RO	**Queued Invalidation Support (QI):** • 0 = Hardware does not support queued invalidations. • 1 = Hardware supports queued invalidations.
0	0x0 RO	**Page-Walk Coherency (C):** This field indicates if hardware access to the root, context, extended-context and interrupt-remap tables, and second-level paging structures for requests-without-PASID, are coherent (snooped) or not. • 0 = Indicates hardware accesses to remapping structures are non-coherent. • 1 = Indicates hardware accesses to remapping structures are coherent. Hardware access to advanced fault log, invalidation queue, invalidation semaphore, page-request queue, PASID-table, PASID-state table, and first-level page-tables are always coherent.

44.4.4 Global Command Register (GCMD_REG_0_0_0_VTDBAR)—Offset 18h

Register to control remapping hardware. If multiple control fields in this register need to be modified, software must serialize the modifications through multiple writes to this register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 18h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Translation Enable (TE):** Software writes to this field to request hardware to enable/disable DMA-remapping: • 0 = Disable DMA remapping. • 1 = Enable DMA remapping.
30	0x0 WO	**Set Root Table Pointer (SRTP):** Software sets this field to set/update the root-entry table pointer used by hardware. The root-entry table pointer is specified through the Root-entry Table Address (RTA_REG) register. The Set Root Table Pointer operation must be performed before enabling or re-enabling (after disabling) DMA remapping through the TE field.
29	0x0 RO	**Reserved:** Reserved
28	0x0 RO	**Reserved:** Reserved
27	0x0 RO	**Reserved:** Reserved
26	0x0 RW	**Queued Invalidation Enable (QIE):** This field is valid only for implementations supporting queued invalidations. Software writes to this field to enable or disable queued invalidations. • 0 = Disable queued invalidations. • 1 = Enable use of queued invalidations.
25	0x0 RW	**Interrupt Remapping Enable (IRE):** This field is valid only for implementations supporting interrupt remapping. • 0 = Disable interrupt-remapping hardware. • 1 = Enable interrupt-remapping hardware.
24	0x0 WO	**Set Interrupt Remap Table Pointer (SIRTP):** This field is valid only for implementations supporting interrupt-remapping. Software sets this field to set/update the interrupt remapping table pointer used by hardware. The interrupt remapping table pointer is specified through the Interrupt Remapping Table Address (IRTA_REG) register.
23	0x0 RW	**Compatibility Format Interrupt (CFI):** This field is valid only for Intel64 implementations supporting interrupt-remapping. Software writes to this field to enable or disable Compatibility Format interrupts on Intel64 platforms. The value in this field is effective only when interrupt-remapping is enabled and Extended Interrupt Mode (x2APIC mode) is not enabled. • 0 = Block Compatibility format interrupts. • 1 = Process Compatibility format interrupts as pass-through (bypass interrupt remapping).
22:0	0x0 RO	**RSVD0:** Reserved

44.4.5 Global Status Register (GSTS_REG_0_0_0_VTDBAR)—Offset 1Ch

Register to report general remapping hardware status.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 1Ch

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Reserved:** Reserved
30	0x0 RO/V	**Reserved:** Reserved
29	0x0 RO	**Fault Log Status (FLS):** This field: • Is cleared by hardware when software Sets the SFL field in the Global Command register. • Is Set by hardware when hardware completes the Set Fault Log Pointer operation using the value provided in the Advanced Fault Log register.
28	0x0 RO	**Advanced Fault Logging Status (AFLS):** This field is valid only for implementations supporting advanced fault logging. It indicates the advanced fault logging status: • 0 = Advanced Fault Logging is not enabled. • 1 = Advanced Fault Logging is enabled.
27	0x0 RO	**Write Buffer Flush Status (WBFS):** This field is valid only for implementations requiring write buffer flushing. This field indicates the status of the write buffer flush command.
26	0x0 RO/V	**Queued Invalidation Enable Status (QIES):** This field indicates queued invalidation enable status. • 0 = queued invalidation is not enabled. • 1 = queued invalidation is enabled
25	0x0 RO/V	**Interrupt Remapping Enable Status (IRES):** This field indicates the status of Interrupt-remapping hardware. • 0 = Interrupt-remapping hardware is not enabled. • 1 = Interrupt-remapping hardware is enabled
24	0x0 RO/V	**Interrupt Remapping Pointer Status (IRTPS):** This field indicates the status of the interrupt remapping table pointer in hardware. This field is cleared by hardware when software sets the SIRTP field in the Global Command register.
23	0x0 RO/V	**Compatibility Format Interrupt Status (CFIS):** This field indicates the status of Compatibility format interrupts on Intel64 implementations supporting interrupt-remapping. The value reported in this field is applicable only when interrupt-remapping is enabled and Extended Interrupt Mode (x2APIC mode) is not enabled. • 0 = Compatibility format interrupts are blocked. • 1 = Compatibility format interrupts are processed as pass-through (bypassing interrupt remapping).
22:0	0x0 RO	**RSVD0:** Reserved

44.4.6 Root Table Address Register (RTADDR_REG_0_0_0_VTDBAR)—Offset 20h

Register providing the base address of root-entry table.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 20h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:12	0x0 RW	**Root Table Address (RTA):** This register points to base of page aligned, 4KB-sized root-entry table in system memory.
11	0x0 RW	**Root Table Type (RTT):** This field specifies the type of root-table referenced by the Root Table Address (RTA) field: • 0 = Root Table. • 1 = Extended Root Table
10:0	0x0 RO	**RSVD0:** Reserved

44.4.7 Context Command Register (CCMD_REG_0_0_0_VTDBAR)—Offset 28h

Register to manage context cache. The act of writing the uppermost byte of the CCMD_REG with the ICC field Set causes the hardware to perform the context-cache invalidation.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 28h

Default: 0800000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/V	**Invalidate Context Cache (ICC):** Software requests invalidation of context-cache by setting this field. Software must also set the requested invalidation granularity by programming the CIRG field. Software must read back and check the ICC field is Clear to confirm the invalidation is complete. Software must not update this register when this field is set. Hardware clears the ICC field to indicate the invalidation request is complete. Hardware also indicates the granularity at which the invalidation operation was performed through the CAIG field. Software must submit a context-cache invalidation request through this field only when there are no invalidation requests pending at this remapping hardware unit. Since information from the context-cache may be used by hardware to tag IOTLB entries, software must perform domain-selective (or global) invalidation of IOTLB after the context cache invalidation has completed. Hardware implementations reporting write-buffer flushing requirement (RWBF=1 in Capability register) must implicitly perform a write buffer flush before invalidating the context cache.
62:61	0x0 RW	**Context Invalidation Request Granularity (CIRG):** Software provides the requested invalidation granularity through this field when setting the ICC field: • 00: Reserved. • 01: Global Invalidation request. • 10: Domain-selective invalidation request. The target domain-id must be specified in the DID field. • 11: Device-selective invalidation request. The target source-id(s) must be specified through the SID and FM fields, and the domain-id (that was programmed in the context-entry for these device(s)) must be provided in the DID field. Hardware implementations may process an invalidation request by performing invalidation at a coarser granularity than requested. Hardware indicates completion of the invalidation request by clearing the ICC field. At this time, hardware also indicates the granularity at which the actual invalidation was performed through the CAIG field.
60:59	0x1 RO/V	**Context Actual Invalidation Granularity (CAIG):** Hardware reports the granularity at which an invalidation request was processed through the CAIG field at the time of reporting invalidation completion (by clearing the ICC field). The following are the encodings for this field: • 00: Reserved. • 01: Global Invalidation performed. This could be in response to a global, domain-selective or device-selective invalidation request. • 10: Domain-selective invalidation performed using the domain-id specified by software in the DID field. This could be in response to a domain-selective or device-selective invalidation request. • 11: Device-selective invalidation performed using the source-id and domain-id specified by software in the SID and FM fields. This can only be in response to a device-selective invalidation request.
58:34	0x0 RO	**RSVD0:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
33:32	0x0 RW	**Function Mask (FM):** Software may use the Function Mask to perform device-selective invalidations on behalf of devices supporting PCI Express Phantom Functions. This field specifies which bits of the function number portion (least significant three bits) of the SID field to mask when performing device-selective invalidations. The following encodings are defined for this field: • 00: No bits in the SID field masked. • 01: Mask most significant bit of function number in the SID field. • 10: Mask two most significant bit of function number in the SID field. • 11: Mask all three bits of function number in the SID field. The context-entries corresponding to all the source-ids specified through the FM and SID fields must have to the domain-id specified in the DID field.
31:16	0x0 RW	**Source-ID (SID):** Indicates the source-id of the device whose corresponding context-entry needs to be selectively invalidated. This field along with the FM field must be programmed by software for device-selective invalidation requests.
15:0	0x0 RW	**Domain-ID (DID):** Indicates the id of the domain whose context-entries need to be selectively invalidated. This field must be programmed by software for both domain-selective and device-selective invalidation requests. The Capability register reports the domain-id width supported by hardware. Software must ensure that the value written to this field is within this limit. Hardware may ignore and not implement bits15:N, where N is the supported domain-id width reported in the Capability register.

44.4.8 Fault Status Register (FSTS_REG_0_0_0_VTDBAR)—Offset 34h

Register indicating the various error status.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 34h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:8	0x0 RO	**Fault Record Index (FRI):** This field is valid only when the PPF field is Set. The FRI field indicates the index (from base) of the fault recording register to which the first pending fault was recorded when the PPF field was Set by hardware. The value read from this field is undefined when the PPF field is clear.
7	0x0 RW/1C	**Page Request Overflow (PRO):** Hardware detected a Page Request Overflow error. Hardware implementations not supporting the Page Request Queue implement this bit as RsvdZ. **Power Well:** prst
6	0x0 RO	**Invalidation Time-out Error (ITE):** Hardware detected a Device-IOTLB invalidation completion time-out. At this time, a fault event may be generated based on the programming of the Fault Event Control register. Hardware implementations not supporting device Device-IOTLBs implement this bit as RsvdZ.
5	0x0 RO	**Invalidation Completion Error (ICE):** Hardware received an unexpected or invalid Device-IOTLB invalidation completion. This could be due to either an invalid ITag or invalid source-id in an invalidation completion response. At this time, a fault event may be generated based on the programming of hte Fault Event Control register. Hardware implementations not supporting Device-IOTLBs implement this bit as RsvdZ.
4	0x0 RW/1C	**Invalidation Queue Error (IQE):** Hardware detected an error associated with the invalidation queue. This could be due to either a hardware error while fetching a descriptor from the invalidation queue, or hardware detecting an erroneous or invalid descriptor in the invalidation queue. At this time, a fault event may be generated based on the programming of the Fault Event Control register. Hardware implementations not supporting queued invalidations implement this bit as RsvdZ. **Power Well:** prst
3	0x0 RO	**Advanced Pending Fault (APF):** When this field is Clear, hardware sets this field when the first fault record (at index 0) is written to a fault log. At this time, a fault event is generated based on the programming of the Fault Event Control register. Software writing 1 to this field clears it. Hardware implementations not supporting advanced fault logging implement this bit as RsvdZ.
2	0x0 RO	**Advanced Fault Overflow (AFO):** Hardware sets this field to indicate advanced fault log overflow condition. At this time, a fault event is generated based on the programming of the Fault Event Control register. Software writing 1 to this field clears it. Hardware implementations not supporting advanced fault logging implement this bit as RsvdZ.
1	0x0 RO/V	**Primary Pending Fault (PPF):** This field indicates if there are one or more pending faults logged in the fault recording registers. Hardware computes this field as the logical OR of Fault (F) fields across all the fault recording registers of this remapping hardware unit. • 0 = No pending faults in any of the fault recording registers. • 1 = One or more fault recording registers has pending faults. The FRI field is updated by hardware whenever the PPF field is set by hardware. Also, depending on the programming of Fault Event Control register, a fault event is generated when hardware sets this field. **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RW/1C	**Primary Fault Overflow (PFO):** Hardware sets this field to indicate overflow of fault recording registers. Software writing 1 clears this field. When this field is Set, hardware does not record any new faults until software clears this field. **Power Well:** prst

44.4.9 Fault Event Control Register (FECTL_REG_0_0_0_VTDBAR)—Offset 38h

Register specifying the fault event interrupt message control bits.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 38h

Default: 80000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**Interrupt Mask (IM):** • 0 = No masking of interrupt. When an interrupt condition is detected, hardware issues an interrupt message (using the Fault Event Data and Fault Event Address register values). • 1 = This is the value on reset. Software may mask interrupt message generation by setting this field. Hardware is prohibited from sending the interrupt message when this field is set.
30	0x0 RO/V	**Interrupt Pending (IP):** Hardware sets the IP field whenever it detects an interrupt condition, which is defined as: • When primary fault logging is active, an interrupt condition occurs when hardware records a fault through one of the Fault Recording registers and sets the PPF field in Fault Status register. • When advanced fault logging is active, an interrupt condition occurs when hardware records a fault in the first fault record (at index 0) of the current fault log and sets the APF field in the Fault Status register. • Hardware detected error associated with the Invalidation Queue, setting the IQE field in the Fault Status register. • Hardware detected invalid Device-IOTLB invalidation completion, setting the ICE field in the Fault Status register. • Hardware detected Device-IOTLB invalidation completion time-out, setting the ITE field in the Fault Status register. If any of the status fields in the Fault Status register was already Set at the time of setting any of these fields, it is not treated as a new interrupt condition. The IP field is kept set by hardware while the interrupt message is held pending. The interrupt message could be held pending due to interrupt mask (IM field) being Set or other transient hardware conditions. The IP field is cleared by hardware as soon as the interrupt message pending condition is serviced. This could be due to either: • Hardware issuing the interrupt message due to either change in the transient hardware condition that caused interrupt message to be held pending, or due to software clearing the IM field. • Software servicing all the pending interrupt status fields in the Fault Status register as follows: • When primary fault logging is active, software clearing the Fault (F) field in all the Fault Recording registers with faults, causing the PPF field in Fault Status register to be evaluated as clear. • Software clearing other status fields in the Fault Status register by writing back the value read from the respective fields.
29:0	0x0 RO	**RSVD0:** Reserved

44.4.10 Fault Event Data Register (FEDATA_REG_0_0_0_VTDBAR)—Offset 3Ch

Register specifying the interrupt message data

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 3Ch

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Extended Interrupt Message Data (EIMD):** This field is valid only for implementations supporting 32-bit interrupt data fields. Hardware implementations supporting only 16-bit interrupt data may treat this field as RsvdZ.
15:0	0x0 RW	**Interrupt Message Data (IMD):** Data value in the interrupt request.

44.4.11 Fault Event Address Register (FEADDR_REG_0_0_0_VTDBAR)—Offset 40h

Register specifying the interrupt message address.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 40h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** When fault events are enabled, the contents of this register specify the DWORD-aligned address (bits 31:2) for the interrupt request.
1:0	0x0 RO	**RSVD0:** Reserved

44.4.12 Fault Event Upper Address Register (FEUADDR_REG_0_0_0_VTDBAR)—Offset 44h

Register specifying the interrupt message upper address.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 44h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Hardware implementations supporting Extended Interrupt Mode are required to implement this register. Hardware implementations not supporting Extended Interrupt Mode may treat this field as RsvdZ.

44.4.13 Advanced Fault Log Register (AFLOG_REG_0_0_0_VTDBAR)—Offset 58h

Register to specify the base address of the memory-resident fault-log region. This register is treated as RsvdZ for implementations not supporting advanced translation fault logging (AFL field reported as 0 in the Capability register).

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 58h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:12	0x0 RO	**Fault Log Address (FLA):** This field specifies the base of 4KB aligned fault-log region in system memory. Hardware ignores and does not implement bits 63:HAW, where HAW is the host address width. Software specifies the base address and size of the fault log region through this register, and programs it in hardware through the SFL field in the Global Command register. When implemented, reads of this field return the value that was last programmed to it.
11:9	0x0 RO	**Fault Log Size (FLS):** This field specifies the size of the fault log region pointed by the FLA field. The size of the fault log region is 2X * 4KB, where X is the value programmed in this register. When implemented, reads of this field return the value that was last programmed to it.
8:0	0x0 RO	**RSVD0:** Reserved

44.4.14 Protected Memory Enable Register (PMEN_REG_0_0_0_VTDBAR)—Offset 64h

Register to enable the DMA-protected memory regions setup through the PLMBASE,..PLMLIMT, PHMBASE, PHMLIMIT registers. This register is always treated as RO for implementations not supporting protected memory regions (PLMR and PHMR fields reported as Clear in the Capability register). Protected memory regions may be used by software to securely initialize remapping structures in memory. To avoid impact to legacy BIOS usage of memory, software is recommended to not overlap protected memory regions with any reserved memory regions of the platform reported through the Reserved Memory Region Reporting (RMRR) structures.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 64h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Enable Protected Memory (EPM):** This field controls DMA accesses to the protected low-memory and protected high-memory regions. • 0 = Protected memory regions are disabled. • 1 = Protected memory regions are enabled.DMA requests accessing protected memory regions are handled as follows: When DMA remapping is not enabled, all DMA requests accessing protected memory regions are blocked. When DMA remapping is enabled: DMA requests processed as pass-through (Translation Type value of 10b in Context-Entry) and accessing the protected memory regions are blocked. DMA requests with translated address (AT=10b) and accessing the protected memory regions are blocked. DMA requests that are subject to address remapping, and accessing the protected memory regions may or may not be blocked by hardware. For such requests, software must not depend on hardware protection of the protected memory regions, and instead program the DMA-remapping page-tables to not allow DMA to protected memory regions. Remapping hardware access to the remapping structures are not subject to protected memory region checks. DMA requests blocked due to protected memory region violation are not recorded or reported as remapping faults. Hardware reports the status of the protected memory enable/disable operation through the PRS field in this register. Hardware implementations supporting DMA draining must drain any in-flight translated DMA requests queued within the Root-Complex before indicating the protected memory region as enabled through the PRS field.
30:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RO/V	**Protected Region Status (PRS):** This field indicates the status of protected memory region(s): • 0 = Protected memory region(s) disabled. • 1 = Protected memory region(s) enabled.

44.4.15 Protected Low Memory Base Register (PLMBASE_REG_0_0_0_VTDBAR)—Offset 68h

Register to set up the base address of DMA-protected low-memory region below 4GB. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled. This register is always treated as RO for implementations not supporting protected low memory region (PLMR field reported as Clear in the Capability register). The alignment of the protected low memory region base depends on the number of reserved bits (N:0) of this register. Software may determine N by writing all 1s to this register, and finding the most significant zero bit position with 0 in the value read back from the register. Bits N:0 of this register is decoded by hardware as all 0s...Software must setup the protected low memory region below 4GB. Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 68h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Protected Low-Memory Base (PLMB):** This register specifies the base of protected low-memory region in system memory.
19:0	0x0 RO	**RSVD0:** Reserved

44.4.16 Protected Low-Memory Limit Register (PLMLIMIT_REG_0_0_0_VTDBAR)—Offset 6Ch

Register to set up the limit address of DMA-protected low-memory region below 4GB. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled This register is always treated as RO for implementations not supporting protected low memory region (PLMR field reported as Clear in the Capability register) The alignment of the protected low memory region limit depends on the number of reserved bits (N:0) of this register. Software may determine N by writing all 1s to this register, and finding most significant zero bit position with 0 in the value read back from the register. Bits N:0 of the limit register is decoded by hardware as all 1s The Protected low-memory base and limit registers functions as follows:

- Programming the protected low-memory base and limit registers with the same value in bits 31: (N+1) specifies a protected low-memory region of size 2(N+1) bytes
- Programming the protected low-memory limit register with a value less than the protected low-memory base register disables the protected low-memory region

Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 6Ch

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Protected Low-Memory Limit (PLML):** This register specifies the last host physical address of the DMA-protected low-memory region in system memory.
19:0	0x0 RO	**RSVD0:** Reserved

44.4.17 Protected High-Memory Base Register (PHMBASE_REG_0_0_0_VTDBAR)—Offset 70h

Register to set up the base address of DMA-protected high-memory region. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled This register is always treated as RO for implementations not supporting protected high memory region (PHMR field reported as Clear in the Capability register) The alignment of the protected high memory region base depends on the number of reserved bits (N:0) of this register. Software may determine N by writing all 1s to this register, and finding most significant zero bit position below host address width (HAW) in the value read back from the register. Bits N:0 of this register are decoded by hardware as all 0s Software may setup the protected high memory region either above or below 4GB Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 70h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:39	0x0 RO	**RSVD0:** Reserved
38:20	0x0 RW	**Protected High-Memory Base (PHMB):** This register specifies the base of protected (high) memory region in system memory. Hardware ignores, and does not implement, bits 63:HAW, where HAW is the host address width.
19:0	0x0 RO	**RSVD1:** Reserved

44.4.18 Protected High-Memory Limit Register (PHMLIMIT_REG_0_0_0_VTDBAR)—Offset 78h

Register to set up the limit address of DMA-protected high-memory region. This register must be set up before enabling protected memory through PMEN_REG, and must not be updated when protected memory regions are enabled This register is always treated as RO for implementations not supporting protected high memory region (PHMR field reported as Clear in the Capability register) The alignment of the protected high memory region limit depends on the number of reserved bits (N:0) of this register. Software may determine the value of N by writing all 1s to this register, and finding most significant zero bit position below host address width (HAW) in the value read back from the register. Bits N:0 of the limit register is decoded by hardware as all 1s The protected high-memory base and limit registers functions as follows

- Programming the protected low-memory base and limit registers with the same value in bits HAW:(N+1) specifies a protected low-memory region of size 2(N+1) bytes
- Programming the protected high-memory limit register with a value less than the protected high-memory base register disables the protected high-memory region

Software must not modify this register when protected memory regions are enabled (PRS field Set in PMEN_REG).

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 78h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:39	0x0 RO	**RSVD0:** Reserved
38:20	0x0 RW	**Protected High-Memory Limit (PHML):** This register specifies the last host physical address of the DMA-protected high-memory region in system memory. Hardware ignores and does not implement bits 63:HAW, where HAW is the host address width.
19:0	0x0 RO	**RSVD1:** Reserved

44.4.19 Invalidation Queue Head Register (IQH_REG_0_0_0_VTDBAR)—Offset 80h

Register indicating the invalidation queue head. This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 80h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:19	0x0 RO	**RSVD0:** Reserved
18:4	0x0 RO/V	**Queue Head (QH):** Specifies the offset (128-bit aligned) to the invalidation queue for the command that will be fetched next by hardware. Hardware resets this field to 0 whenever the queued invalidation is disabled (QIES field Clear in the Global Status register).
3:0	0x0 RO	**RSVD1:** Reserved

44.4.20 Invalidation Queue Tail Register (IQT_REG_0_0_0_VTDBAR)—Offset 88h

Register indicating the invalidation tail head. This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 88h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:19	0x0 RO	**RSVD0:** Reserved
18:4	0x0 RW	**Queue Tail (QT):** Specifies the offset (128-bit aligned) to the invalidation queue for the command that will be written next by software.
3:0	0x0 RO	**RSVD1:** Reserved

44.4.21 Invalidation Queue Address Register (IQA_REG_0_0_0_VTDBAR)—Offset 90h

Register to configure the base address and size of the invalidation queue. This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 90h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:39	0x0 RO	**RSVD0:** Reserved
38:12	0x0 RW	**Invalidation Queue Base Address (IQA):** This field points to the base of 4KB aligned invalidation request queue. Hardware ignores and does not implement bits 63:HAW, where HAW is the host address width. Reads of this field return the value that was last programmed to it.
11:3	0x0 RO	**RSVD1:** Reserved
2:0	0x0 RW	**Queue Size (QS):** This field specifies the size of the invalidation request queue. A value of X in this field indicates an invalidation request queue of (2X) 4KB pages. The number of entries in the invalidation queue is 2(X + 8).

44.4.22 Invalidation Completion Status Register (ICS_REG_0_0_0_VTDBAR)—Offset 9Ch

Register to report completion status of invalidation wait descriptor with Interrupt Flag (IF) Set This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + 9Ch

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RW/1C	**Invalidation Wait Descriptor Complete (IWC):** Indicates completion of Invalidation Wait Descriptor with Interrupt Flag (IF) field Set. Hardware implementations not supporting queued invalidations implement this field as RsvdZ. **Power Well:** prst

44.4.23 Invalidation Event Control Register (IECTL_REG_0_0_0_VTDBAR)—Offset A0h

Register specifying the invalidation event interrupt control bits This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + A0h

Default: 80000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**Interrupt Mask (IM):** • 0= No masking of interrupt. When a invalidation event condition is detected, hardware issues an interrupt message (using the Invalidation Event Data and Invalidation Event Address register values) • 1= This is the value on reset. Software may mask interrupt message generation by setting this field. Hardware is prohibited from sending the interrupt message when this field is Set.
30	0x0 RO/V	**Interrupt Pending (IP):** Hardware sets the IP field whenever it detects an interrupt condition. Interrupt condition is defined as: • An Invalidation Wait Descriptor with Interrupt Flag (IF) field Set completed, setting the IWC field in the Invalidation Completion Status register • If the IWC field in the Invalidation Completion Status register was already Set at the time of setting this field, it is not treated as a new interrupt condition The IP field is kept Set by hardware while the interrupt message is held pending. The interrupt message could be held pending due to interrupt mask (IM field) being Set, or due to other transient hardware conditions. The IP field is cleared by hardware as soon as the interrupt message pending condition is serviced. This could be due to either: • 0= Hardware issuing the interrupt message due to either change in the transient hardware condition that caused interrupt message to be held pending or due to software clearing the IM field • 1= Software servicing the IWC field in the Invalidation Completion Status register.
29:0	0x0 RO	**RSVD0:** Reserved

44.4.24 Invalidation Event Data Register (IEDATA_REG_0_0_0_VTDBAR)—Offset A4h

Register specifying the Invalidation Event interrupt message data This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + A4h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Extended Interrupt Message Data (EIMD):** This field is valid only for implementations supporting 32-bit interrupt data fields. Hardware implementations supporting only 16-bit interrupt data treat this field as Rsvd.
15:0	0x0 RW	**Interrupt Message Data (IMD):** Data value in the interrupt request.

44.4.25 Invalidation Event Address Register (IEADDR_REG_0_0_0_VTDBAR)—Offset A8h

Register specifying the Invalidation Event Interrupt message address This register is treated as RsvdZ by implementations reporting Queued Invalidation (QI) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + A8h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** When fault events are enabled, the contents of this register specify the DWORD-aligned address (bits 31:2) for the interrupt request.
1:0	0x0 RO	**RSVD0:** Reserved

44.4.26 Invalidation Event Upper Address Register (IEUADDR_REG_0_0_0_VTDBAR)—Offset ACh

Register specifying the Invalidation Event interrupt message upper address.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + ACh

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Hardware implementations supporting Queued Invalidations and Extended Interrupt Mode are required to implement this register. Hardware implementations not supporting Queued Invalidations or Extended Interrupt Mode may treat this field as RsvdZ.

44.4.27 Interrupt Remapping Table Address Register (IRTA_REG_0_0_0_VTDBAR)—Offset B8h

Register providing the base address of Interrupt remapping table.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + B8h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:12	0x0 RW	**Interrupt Remapping Table Address (IRTA):** This field points to the base of 4KB aligned interrupt remapping table
11	0x0 RW	**Extended Interrupt Mode Enable (EIME):** This field is used by hardware on Intel64 platforms as follows: • 0=xAPIC mode is active. Hardware interprets only low 8-bits of Destination-ID field in the IRTEs. The high 24-bits of the Destination-ID field are treated as reserved • 1= x2APIC mode is active. Hardware interprets all 32-bits of Destination-ID field in the IRTEs
10:4	0x0 RO	**RSVD0:** Reserved
3:0	0x0 RW	**Size (S):** This field specifies the size of the interrupt remapping table. The number of entries in the interrupt remapping table is 2(X+1), where X is the value programmed in this field.

44.4.28 Page Request Status Register (PRESTS_REG_0_0_0_VTDBAR)—Offset DCh

Register to report pending page request in page request queue. This register is treated as RsvdZ by implementations reporting Page Request Support (PRS) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + DCh

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RW/1C	**Pending Page Request (PPR):** Pending Page Request: Indicates pending page requests to be serviced by software in the page request queue. This field is Set by hardware when a streaming page request entry (page_stream_reg_dsc) or a page group request (page_grp_req_dsc) with Last Page in Group (LPG) field Set, is added to the page request queue. **Power Well:** prst

44.4.29 Page Request Event Control Register (PRECTL_REG_0_0_0_VTDBAR)—Offset E0h

Register specifying the page request event interrupt control bits.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + E0h

Default: 80000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**Interrupt Mask (IM):** Interrupt Mask • 0=No masking of interrupt. When a page request event condition is detected, hardware issues an interrupt message • 1=This is the value on reset. Software may mask interrupt message generation by setting this field.
30	0x0 RO/V	**Interrupt Pending (IP):** Interrupt Pending: Hardware sets the IP field whenever it detects an interrupt condition. The IP field is kept Set by hardware while the interrupt message is held pending.
29:0	0x0 RO	**RSVD0:** Reserved

44.4.30 Page Request Event Data Register (PREDATA_REG_0_0_0_VTDBAR)—Offset E4h

Register specifying the Page Request Event interrupt message data. This register is treated as RsvdZ by implementations reporting Page Request Support (PRS) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + E4h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Extended Interrupt Message Data (EIMD):** Extended Interrupt Message Data
15:0	0x0 RW	**Interrupt Message Data (IMD):** Interrupt Message Data: Data value in the interrupt request. Software requirements for programming this register are described in VTd Spec

44.4.31 Page Request Event Address Register (PREADDR_REG_0_0_0_VTDBAR)—Offset E8h

Register specifying the Page Request Event Interrupt message address. This register is treated as RsvdZ by implementations reporting Page Request Support (PRS) as not supported in the Extended Capability register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + E8h

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** Message Address: When fault events are enabled, the contents of this register specify the DWORD-aligned address (bits 31:2) for the interrupt request.
1:0	0x0 RO	**RSVD0:** Reserved

44.4.32 Page Request Event Upper Address Register (PREUADDR_REG_0_0_0_VTDBAR)—Offset ECh

Register specifying the Page Request Event interrupt message upper address.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [DEFVTDBAR] + ECh

Default: 00000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Message Upper Address: This field specifies the upper address (bits.. 63:32) for the page request event interrupt.

44.4.33 Fault Recording Register Low [0] (FRCDL_REG_0_0_0_VTDBAR)—Offset 400h

Register to record fault information when primary fault logging is active. Hardware reports the number and location of fault recording registers through the Capability register. This register is relevant only for primary fault logging This register is sticky and can be cleared only through power good reset or by software clearing the RW1C fields by writing a 1.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 400h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:12	0x0 RO/V	**Fault Info (FI):** When the Fault Reason (FR) field indicates one of the DMA-remapping fault conditions, bits 63:12 of this field contain the page address in the faulted DMA request. Hardware treats bits 63:N as reserved (0), where N is the maximum guest address width (MGAW) supported. When the Fault Reason (FR) field indicates one of the interrupt-remapping fault conditions, bits 63:48 of this field indicate the interrupt_index computed for the faulted interrupt request, and bits 47:12 are cleared. This field is relevant only when the F field is Set. **Power Well:** prst
11:0	0x0 RO	**RSVD0:** Reserved

44.4.34 Fault Recording Register High [0] (FRCDH_REG_0_0_0_VTDBAR)—Offset 408h

Register to record fault information when primary fault logging is active. Hardware reports the number and location of fault recording registers through the Capability register. This register is relevant only for primary fault logging This register is sticky and can be cleared only through power good reset or by software clearing the RW1C fields by writing a 1.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 408h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/1C	**Fault (F):** Hardware sets this field to indicate a fault is logged in this Fault Recording register. The F field is set by hardware after the details of the fault is recorded in other fields. When this field is Set, hardware may collapse additional faults from the same source-id (SID) **Power Well:** prst
62	0x0 RO/V	**Type (T):** Type of the faulted request: • 0=0: Write request • 1=1: Read request or AtomicOp request This field is relevant only when the F field is Set, and when the fault reason (FR) indicates one of the DMA-remapping fault conditions. **Power Well:** prst
61:60	0x0 RO/V	**Address Type (AT):** This field captures the AT field from the faulted DMA request. Hardware implementations not supporting Device-IOTLBs (DI field Clear in Extended Capability register) treat this field as RsvdZ. When supported, this field is valid only when the F field is Set, and when the fault reason (FR) indicates one of the DMA-remapping fault conditions. **Power Well:** prst
59:40	0x0 RO/V	**PASID Value (PN):** PASID value in the faulted request. This field is relevant only when the PP field is set. Hardware implementations not supporting PASID (PASID field Clear in Extended Capability register) implement this field as RsvdZ. **Power Well:** prst
39:32	0x0 RO/V	**Fault Reason (FR):** Reason for the fault This field is relevant only when the F field is set. **Power Well:** prst
31	0x0 RO/V	**PASID Present (PP):** When set, indicates the faulted request has a PASID tag. The value of the PASID field is reported in the PASID Value (PV) field. This field is relevant only when the F field is Set, and when the fault reason (FR) indicates one of the non-recoverable address translation fault conditions. Hardware implementations not supporting PASID (PASID field Clear in Extended Capability register) implement this field as RsvdZ. **Power Well:** prst
30	0x0 RO/V	**Execute Permission Requested (EXE):** When set, indicates Execute permission was requested by the faulted read request. This field is relevant only when the PP field and T field are both Set. Hardware implementations not supporting PASID (PASID field Clear in Extended Capability register) implement this field as RsvdZ. **Power Well:** prst

Bit Range	Default & Access	Field Name (ID): Description
29	0x0 RO/V	**Privilege Mode Requested (PRIV):** When set, indicates Supervisor privilege was requested by the faulted request. This field is relevant only when the PP field is Set. Hardware implementations not supporting PASID (PASID field Clear in Extended Capability register) implement this field as RsvdZ. **Power Well:** prst
28:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RO/V	**Source Identifier (SID):** Requester-id associated with the fault condition. This field is relevant only when the F field is set. **Power Well:** prst

44.4.35 Invalidate Address Register (IVA_REG_0_0_0_VTDBAR)—Offset 500h

Register to provide the DMA address whose corresponding IOTLB entry needs to be invalidated through the corresponding IOTLB Invalidate register. This register is a write-only register.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 500h

Default: 0000000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63:12	0x0 RW	**Address (ADDR):** Software provides the DMA address that needs to be page-selectively invalidated. To make a page-selective invalidation request to hardware, software must first write the appropriate fields in this register, and then issue the appropriate page-selective invalidate command through the IOTLB_REG. Hardware ignores bits 63:N, where N is the maximum guest address width (MGAW) supported. A value returned on a read of this field is undefined.
11:7	0x0 RO	**RSVD0:** Reserved
6	0x0 RW	**Invalidation Hint (IH):** The field provides hint to hardware about preserving or flushing the non-leaf (page-directory) entries that may be cached in hardware: • 0 = Software may have modified both leaf and non-leaf page-table entries corresponding to mappings specified in the ADDR and AM fields. On a page-selective invalidation request, hardware must flush both the cached leaf and non-leaf page-table entries corresponding to the mappings specified by ADDR and AM fields. • 1 = Software has not modified any non-leaf page-table entries corresponding to mappings specified in the ADDR and AM fields. On a page-selective invalidation request, hardware may preserve the cached non-leaf page-table entries corresponding to mappings specified by ADDR and AM fields. A value returned on a read of this field is undefined.
5:0	0x0 RW	**Address Mask (AM):** The value in this field specifies the number of low order bits of the ADDR field that must be masked for the invalidation operation. This field enables software to request invalidation of contiguous mappings for size-aligned regions. For example:..Mask ADDR bits Pages..Value masked invalidated.. 0 None 1.. 1 12 2.. 2 13:12 4.. 3 14:12 8.. 4 15:12 16 When invalidating mappings for super-pages, software must specify the appropriate mask value. For example, when invalidating mapping for a 2MB page, software must specify an address mask value of at least 9...Hardware implementations report the maximum supported mask value through the Capability register.

44.4.36 IOTLB Invalidate Register (IOTLB_REG_0_0_0_VTDBAR)—Offset 508h

Register to invalidate IOTLB. The act of writing the upper byte of the IOTLB_REG with IVT field Set causes the hardware to perform the IOTLB invalidation.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [DEFVTDBAR] + 508h

Default: 0200000000000000h

DEFVTDBAR Type: Memory Mapped I/O Register (Size: 64 bits)
DEFVTDBAR Reference: B_CR_DEFVTDBAR_0_0_0_MCHBAR + 6C80h

Bit Range	Default & Access	Field Name (ID): Description
63	0x0 RW/V	**Invalidate IOTLB (IVT):** Software requests IOTLB invalidation by setting this field. Software must also set the requested invalidation granularity by programming the IIRG field. Hardware clears the IVT field to indicate the invalidation request is complete. Hardware also indicates the granularity at which the invalidation operation was performed through the IAIG field. Software must not submit another invalidation request through this register while the IVT field is Set, nor update the associated Invalidate Address register. Software must not submit IOTLB invalidation requests when there is a context-cache invalidation request pending at this remapping hardware unit. Hardware implementations reporting write-buffer flushing requirement (RWBF=1 in Capability register) must implicitly perform a write buffer flushing before invalidating the IOTLB.
62	0x0 RO	**RSVD0:** Reserved
61:60	0x0 RW	**IOTLB Invalidation Request Granularity (IIRG):** When requesting hardware to invalidate the IOTLB (by setting the IVT field), software writes the requested invalidation granularity through this field. The following are the encodings for the field: • 00 = Reserved • 01 = Global invalidation request • 10 = Domain-selective invalidation request. The target domain-id must be specified in the DID field • 11 = Page-selective invalidation request. The target address, mask and invalidation hint must be specified in the Invalidate Address register, and the domain-id must be provided in the DID field Hardware implementations may process an invalidation request by performing invalidation at a coarser granularity than requested. Hardware indicates completion of the invalidation request by clearing the IVT field. At this time, the granularity at which actual invalidation was performed is reported through the IAIG field.
59	0x0 RO	**RSVD1:** Reserved
58:57	0x1 RO/V	**IOTLB Actual Invalidation Granularity (IAIG):** Hardware reports the granularity at which an invalidation request was processed through this field when reporting invalidation completion (by clearing the IVT field). The following are the encodings for this field • 00 = Reserved. This indicates hardware detected an incorrect invalidation request and ignored the request. Examples of incorrect invalidation requests include detecting an unsupported address mask value in Invalidate Address register for page-selective invalidation requests • 01 = Global Invalidation performed. This could be in response to a global, domain-selective, or page-selective invalidation request • 10 = Domain-selective invalidation performed using the domain-id specified by software in the DID field. This could be in response to a domain-selective or a page-selective invalidation request • 11 = Domain-page-selective invalidation performed using the address, mask and hint specified by software in the Invalidate Address register and domain-id specified in DID field. This can be in response to a page-selective invalidation request.
56:50	0x0 RO	**RSVD2:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
49	0x0 RW	**Drain Reads (DR):** This field is ignored by hardware if the DRD field is reported as clear in the Capability register. When the DRD field is reported as Set in the Capability register, the following encodings are supported for this field: • 0 = Hardware may complete the IOTLB invalidation without draining any translated DMA read requests • 1 = Hardware must drain DMA read requests.
48	0x0 RW	**Drain Writes (DW):** This field is ignored by hardware if the DWD field is reported as Clear in the Capability register. When the DWD field is reported as Set in the Capability register, the following encodings are supported for this field: • 0 = Hardware may complete the IOTLB invalidation without draining DMA write requests • 1 = Hardware must drain relevant translated DMA write requests.
47:32	0x0 RW	**Domain-ID (DID):** Indicates the ID of the domain whose IOTLB entries need to be selectively invalidated. This field must be programmed by software for domain-selective and page-selective invalidation requests. The Capability register reports the domain-id width supported by hardware. Software must ensure that the value written to this field is within this limit. Hardware ignores and not implements bits 47:(32+N), where N is the supported domain-id width reported in the Capability register.
31:0	0x0 RO	**RSVD3:** Reserved

44.5 Sideband Registers

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space using the Sideband Base Address Register (BAR) DEFVTDBAR. It is located in Host Root Memory Space MCHBAR +offset 6C80h.

See Section 44.3.123, "Default VTd BAR (B_CR_DEFVTDBAR_0_0_0_MCHBAR)—Offset 6C80h" on page 1316.

44.5.1 UCELOG—Offset 64h

Uncorrectable Error Log This register captures the log information when the corresponding channel DERRSTS.UCE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.UCE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 64h
Host Memory Space: SBREG_BAR + 0x100000 + 64h

Default: 00000800h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RSV	**Rsvd_UCELOG_1:** Reserved
21:20	0x0 RO/V/P	**UCERNK:** Rank Address: This is the rank address that contained the error
19:16	0x0 RO/V/P	**UCEBNK:** Bank Address: This is the bank address that contained the error. DDR3: UCEBNK[3] will always be 0 UCEBNK[2:0] = BA[2:0] DDR4: UCEBNK[3:2] = BG[1:0] UCEBNK[1:0] = BA[1:0]
15	0x0 RO/V/P	**UCEAP:** Auto Pre-charge was issued on the read that contained the error. This will always be 0 since AP is not supported.
14	0x0 RO/V/P	**UCELAST:** Last Burst: If this bit is set, then the error occurred within that last four DQ bus bursts before a DQ bus turn-around cycle.
13	0x0 RO/V/P	**UCEFIRST:** First Burst: If this bit is set, then the error occurred within the first four DQ bus bursts after a DQ bus turn-around cycle.
12	0x0 RO/V/P	**UCEA5:** Address bit 5: This is A[5] from the original request
11	0x1 RO/V/P	**UCEBL8:** Burst Length 8: 0 = Burst Chop 4, 1 = Burst Length 8. This will always be 1 for DNV.
10:8	0x0 RO/V/P	**UCEBOFF:** Burst Offset: This is the burst number that contained the error. Note that all 8 bursts are always numbered starting from 0. Thus, even when the critical chunk causes the bursts to occur in the logical order of 4,5,6,7,0,1,2,3, UCEBOFF will still number these starting from 0. So, for example, if an error is detected on logical byte 0, it is possible that this may be recorded as byte offset 4 with critical chunk reordering.
7:0	0x0 RO/V/P	**UCESYND:** ECC Syndrome: This is the 8-bit syndrome output of the ECC checker logic. For DNV, this field does not provide useful information and is not reliable.

44.5.2 UCEADDR—Offset 68h

Uncorrectable Error Address This register captures the log information when the corresponding channel DERRSTS.UCE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.UCE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 68h
Host Memory Space: SBREG_BAR + 0x100000 + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**UCEADDR:** Address Log: Captures the PMI address A[35:6] of the UCE error location.

44.5.3 SBELOG—Offset 6Ch

Correctable (Single Bit) Error Log This register captures the log information when the corresponding channel DERRSTS.SBE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.SBE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 6Ch
Host Memory Space: SBREG_BAR + 0x100000 + 6Ch

Default: 00000800h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RSV	**Rsvd_SBELOG_1:** Reserved
21:20	0x0 RO/V/P	**SBERNK:** Rank Address: This is the rank address that contained the error
19:16	0x0 RO/V/P	**SBEBNK:** Bank Address: This is the bank address that contained the error. DDR3: UCEBNK[3] will always be 0 UCEBNK[2:0] = BA[2:0] DDR4: UCEBNK[3:2] = BG[1:0] UCEBNK[1:0] = BA[1:0]
15	0x0 RO/V/P	**Reserved:** Reserved
14	0x0 RO/V/P	**SBELAST:** Last Burst: If this bit is set, then the error occurred within that last four DQ bus bursts before a DQ bus turn-around cycle.
13	0x0 RO/V/P	**SBEFIRST:** First Burst: If this bit is set, then the error occurred within the first four DQ bus bursts after a DQ bus turn-around cycle.
12	0x0 RO/V/P	**SBEA5:** Address bit 5: This is A[5] from the original request. In 32 bit mode this field is undefined.
11	0x1 RO/V/P	**Reserved:** Reserved
10:8	0x0 RO/V/P	**SBEBOFF:** Burst Offset: This is the burst number that contained the error. Note that all 8 bursts are always numbered starting from 0.
7:0	0x0 RO/V/P	**SBESYND:** ECC Syndrome: This is the 8-bit syndrome output of the ECC checker logic

44.5.4 SBEADDR—Offset 70h

Correctable Error Address This register captures the log information when the corresponding channel DERRSTS.SBE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.SBE[1:0] is cleared.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 70h
Host Memory Space: SBREG_BAR + 0x100000 + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**SBEADDR:** Address Log: Captures the PMI address A[35:6] of the SBE error location.

44.5.5 SBECNT0—Offset 74h

SBE Count for Rank 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 74h
Host Memory Space: SBREG_BAR + 0x100000 + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT0_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 0. Any write to this register will clear the counter to 0.

44.5.6 SBECNT1—Offset 78h

SBE Count for Rank 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 78h
Host Memory Space: SBREG_BAR + 0x100000 + 78h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT1_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 1. Any write to this register will clear the counter to 0.

44.5.7 SBECNT2—Offset 7Ch

SBE Count for Rank 2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 7Ch
Host Memory Space: SBREG_BAR + 0x100000 + 7Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT2_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 2. Any write to this register will clear the counter to 0.

44.5.8 SBECNT3—Offset 80h

SBE Count for Rank 3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 80h
Host Memory Space: SBREG_BAR + 0x100000 + 80h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT3_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 3. Any write to this register will clear the counter to 0.

44.5.9 SBEACC0—Offset 84h

SBE Accumulator for Rank0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 84h
Host Memory Space: SBREG_BAR + 0x100000 + 84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC0_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device. This value is cleared by any write to this register.

44.5.10 SBEACC1—Offset 88h

SBE Accumulator for Rank1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 88h
Host Memory Space: SBREG_BAR + 0x100000 + 88h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC1_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device. This value is cleared by any write to this register.

44.5.11 SBEACC2—Offset 8Ch

SBE Accumulator for Rank2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 8Ch
Host Memory Space: SBREG_BAR + 0x100000 + 8Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC2_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device. This value is cleared by any write to this register.

44.5.12 SBEACC3—Offset 90h

SBE Accumulator for Rank3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 90h
Host Memory Space: SBREG_BAR + 0x100000 + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC3_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device. This value is cleared by any write to this register.

44.5.13 DPATROL_SCRUB_CFG—Offset B0h

Patrol Scrub Config Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + B0h
Host Memory Space: SBREG_BAR + 0x100000 + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**PAT_SCRUB_ENABLE:** Bit to enable/disable patrol scrub • 0: Disable patrol scrub • 1: Enable patrol scrub
30	0x0 RW/P	**DIMM1_COL_ADDR_BITS:** Total number of column bits for devices on rank 0 = 10 + DIMM1_COL_ADDR_BITS • 0: DDR4 and DDR3 • 1: Only DDR3
29	0x0 RW/P	**DIMM0_COL_ADDR_BITS:** Total number of column bits for devices on rank 0 = 10 + DIMM0_COL_ADDR_BITS • 0: DDR4 and DDR3 • 1: Only DDR3
28:23	0x0 RW/P	**DIMM1_MAX_ROW_ADDR:** Maximum row address for DIMM1 - bits 17 to 12. Bits 11:0 are assumed to all be 1.
22:17	0x0 RW/P	**DIMM0_MAX_ROW_ADDR:** Maximum row address for DIMM0 - bits 17 to 12. Bits 11:0 are assumed to all be 1.
16	0x0 RW/P	**PATSCRUB_FORCE_WRITEBACK:** When set to 1, force write back of data with no errors. When set to 0, don't write back data that had no errors.
15:0	0x0 RW/P	**MAX_PATSCRUB_DEBIT_CNT:** Maximum number of debit patrol scrub operations. Once the patrol scrub debit counter exceeds this value, patrol scrubs will be issued until the debit counter reaches 0. Set 0 to disable debit mode.

44.5.14 UCELOG1—Offset CCh

This register captures the log information when the corresponding channel DERRSTS.UCE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.UCE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + CCh
Host Memory Space: SBREG_BAR + 0x100000 + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RSV	**RSVD (reg_RSVD):** Reserved
26:18	0x0 RO/V/P	**UCE_COL:** Column address bits above A[5]
17:0	0x0 RO/V/P	**UCE_ROW:** Row bits

44.5.15 SBELOG1—Offset D0h

Single bit error log 1 This register captures the log information when the corresponding channel DERRSTS.SBE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.SBE[1:0] is cleared.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + D0h
Host Memory Space: SBREG_BAR + 0x100000 + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RSV	**RSVD (reg_RSVD):** Reserved
26:18	0x0 RO/V/P	**SBE_COL:** Column bits [11,9:2], in 32 bit mode SBE_COL[0] will always be 0, SBE_COL[1] contains information for SBEBOFF[2]
17:0	0x0 RO/V/P	**SBE_ROW:** Row bits

44.5.16 CORRERRTHRSHLD0—Offset 100h

Correctable Error Threshold for Rank 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 100h
Host Memory Space: SBREG_BAR + 0x100000 + 100h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD0_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 0. When the error accumulation in SBECNT0 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.17 CORRERRTHRSHLD1—Offset 104h

Correctable Error Threshold for Rank 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 104h
Host Memory Space: SBREG_BAR + 0x100000 + 104h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD1_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 1. When the error accumulation in SBECNT1 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.18 CORRERRTHRSHLD2—Offset 108h

Correctable Error Threshold for Rank 2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 108h
Host Memory Space: SBREG_BAR + 0x100000 + 108h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD2_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 2. When the error accumulation in SBECNT2 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.19 CORRERRTHRSHLD3—Offset 10Ch

Correctable Error Threshold for Rank 3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 10Ch
Host Memory Space: SBREG_BAR + 0x100000 + 10Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD3_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 3. When the error accumulation in SBECNT3 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.20 LEAKY_BUCKET_CFG0—Offset 110h

Leaky Bucket Configuration Rank 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 110h
Host Memory Space: SBREG_BAR + 0x100000 + 110h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 0 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 0, CNTR_HI.

44.5.21 LEAKY_BUCKET_CFG1—Offset 114h

Leaky Bucket Configuration Rank 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 114h
Host Memory Space: SBREG_BAR + 0x100000 + 114h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 1 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 1, CNTR_HI.

44.5.22 LEAKY_BUCKET_CFG2—Offset 118h

Leaky Bucket Configuration Rank 2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 118h
Host Memory Space: SBREG_BAR + 0x100000 + 118h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 2 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 2, CNTR_HI.

44.5.23 LEAKY_BUCKET_CFG3—Offset 11Ch

Leaky Bucket Configuration Rank 3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 11Ch
Host Memory Space: SBREG_BAR + 0x100000 + 11Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 3 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 3, CNTR_HI.

44.5.24 FERRNERR—Offset 120h

First Error and Next Error Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 120h
Host Memory Space: SBREG_BAR + 0x100000 + 120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RSV	**Rsvd_FERRNERR_1 (Rsvd_FERRNERR_3):** Reserved
20	0x0 RO/V/P	**FERRUCEPAT:** First Error Uncorrectable Patrol Scrub Read Error Detected: When set, the first error detected was an uncorrectable (multiple bit) error on the patrol scrub read from memory.
19	0x0 RO/V/P	**FERRAPE:** First Error Uncorrectable DDR4 Command Address Parity Error: When set, the first error detected was the assertion of the xxDDR3_0_ALERT_N pin indicating that one or more DRAMs detected a Command/Address parity error.
18	0x0 RO/V/P	**FERRWPE:** First Error Uncorrectable Write Parity Error Detected: When set, the first error detected was an uncorrectable (parity) error on the write data received from the Bunit.
17	0x0 RO/V/P	**FERRUCE:** First Error Uncorrectable Read Error Detected: When set, the first error detected was an uncorrectable (multiple bit) error on the read data from memory.
16	0x0 RO/V/P	**FERRSBE:** First Error Correctable Read Error Detected: When set, the first error detected was a single bit error on the read data from memory and the error was corrected.
15:5	0x0 RSV	**Rsvd_FERRNERR_0 (Rsvd_FERRNERR_1):** Reserved
4	0x0 RO/V/P	**NERRUCEPAT:** Next Error Uncorrectable Patrol Scrub Read Error: When set, the second error detected was an uncorrectable (mutliple bit) error on the patrol scrub read data from memory.
3	0x0 RO/V/P	**NERRAPE:** Next Error Uncorrectable DDR4 Command Address Parity Error: When set, the second error detected was the assertion of the xxDDR3_0_ALERT_N pin indicating that one or more DRAMs detected a Command/Address parity error. Note that this bit can never be set as the same time as FERRAPE
2	0x0 RO/V/P	**NERRWPE:** Next Error Uncorrectable Write Parity Error Detected: When set, the second error detected was an uncorrectable (parity) error on the write data received from the Bunit.
1	0x0 RO/V/P	**NERRUCE:** Next Error Uncorrectable Read Error Detected: When set, the second error detected was an uncorrectable (multiple bit) error on the read data from memory.
0	0x0 RO/V/P	**NERRSBE:** Next Error Correctable Read Error Detected: When set, the second error detected was a single bit error on the read data from memory and the error was corrected.

44.5.25 DERRSTS—Offset 124h

Error Status Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 124h
Host Memory Space: SBREG_BAR + 0x100000 + 124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RSV	**Rsvd_DERRSTS_0 (Rsvd_DERRSTS_1):** Reserved
6	0x0 RW/1C/V/P	**CAP_ERR_STATE:** Channel Command Address Parity Error State. 1 = CAP error seen, error state entered. All PMI reads will be returned with bad parity. 0 = No CAP error seen. Normal PMI operation.
5	0x0 RO/V/P	**ALERT:** Current state of the channel ALERT_N pin, captured here as active high: 1 = Error being driven by at least one DRAM device 0 = No error currently detected by any DRAM device
4	0x0 RW/1C/V/P	**UCEPAT:** Uncorrectable (multiple bit) patrol scrub error: When set, an uncorrectable (multiple bit error was detected on the read data from memory.
3	0x0 RW/1C/V/P	**APE:** Uncorrectable DDR4 Command/Address Parity Error: When set, an uncorrectable DDR4 command/address parity error was detected by one or more of the DRAMs on channel 0.
2	0x0 RW/1C/V/P	**WPE:** Uncorrectable (Parity) Write Error: When set, an uncorrectable (parity) error was detected on the write data received from the Bunit.
1	0x0 RW/1C/V/P	**UCE:** Uncorrectable (Double Bit) Read Error: When set, a double bit error was detected on the read data from memory.
0	0x0 RW/1C/V/P	**SBE:** Correctable (Single Bit) Read Error: When set, a single bit error was detected on the read data from memory and the error was corrected.

44.5.26 DERRMSKSEV—Offset 128h

Error Mask and Severity

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 128h
Host Memory Space: SBREG_BAR + 0x100000 + 128h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RSV	**Rsvd_DERRMSKSEV_2:** Reserved
20	0x0 RW/P	**MSK_UCEPAT:** Uncorrectable patrol scrub error mask: When set, uncorrectable patrol scrub ECC data errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
19	0x0 RW/P	**MSK_APE:** Uncorrectable command/address parity error mask: When set, uncorrectable DDR4 command/address parity errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
18	0x0 RW/P	**MSK_WDBR:** Uncorrectable (parity) write data buffer read error mask: When set, uncorrectable (pairty) write data buffer read errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
17	0x0 RW/P	**MSK_UCE:** Uncorrectable (multiple bit) error mask: When set, uncorrectable (multiple bit) read and patrol scrub errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
16	0x0 RW/P	**MSK_SBE:** Correctable (single bit) error mask: When set, correctable (single bit) read and patrol scrub errors will not be logged in DERRESTS[0] and DO_SERR_SEV messages will not be sent to the IEH.
15:5	0x0 RSV	**Rsvd_DERRMSKSEV_1:** Reserved
4	0x0 RW/P	**SEV_UCEPAT:** Uncorrectable (Multiple Bit) Patrol Scrub Read Error Severity: When set, UCE errors logged in DERRSTS[5] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
3	0x0 RW/P	**SEV_APE:** Uncorrectable DDR4 Command/Address Parity Error Severity: When set, APE errors logged in DERRSTS[3] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
2	0x0 RW/P	**SEV_WDBR:** Uncorrectable (Parity) Write Error Severity: When set, WPE errors logged in DERRSTS[2] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
1	0x0 RW/P	**SEV_UCE:** Uncorrectable (Multiple Bit) Read Error Severity: When set, UCE errors logged in DERRSTS[1] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
0	0x0 RSV	**Rsvd_DERRMSKSEV_0:** Reserved

44.5.27 DERRCNTSEL—Offset 12Ch

Uncorrectable Error Count Select

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 12Ch
Host Memory Space: SBREG_BAR + 0x100000 + 12Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RSV	**Rsvd_DERRCNTSEL_2:** Reserved
4	0x0 RW/P	**SEL_UCEPAT:** Uncorrectable (Multiple Bit) Patrol Scrub Read Error Count Select: When set, UCE errors logged in DERRSTS[1] will be counted in DERRCNT.UNCCNT1.
3	0x0 RW/P	**SEL_APE:** Uncorrectable DDR4 Command/Address Parity Error Count Select: When set, APE0 errors logged in DERRSTS[3] will be counted in DERRCNT.UNCCNT0.
2	0x0 RW/P	**SEL_WPE:** Uncorrectable (Parity) Write Error Count Select: When set, WPE0 errors logged in DERRSTS[2] will be counted in DERRCNT.UNCCNT0.
1	0x0 RW/P	**SEL_UCE:** Uncorrectable (Multiple Bit) Read Error Count Select: When set, UCE0 errors logged in DERRSTS[1] will be counted in DERRCNT.UNCCNT0.
0	0x0 RSV	**Rsvd_DERRCNTSEL_0:** Reserved

44.5.28 DERRCNT—Offset 130h

Uncorrectable Error Count

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 130h
Host Memory Space: SBREG_BAR + 0x100000 + 130h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RSV	**Rsvd_DERRCNT:** Reserved
7:0	0x0 RW/1C/V/P	**UNCCNT:** Uncorrectable Error Count: The count of uncorrectable errors that have occurred since the last time the count was cleared. The count limit is 128 (80h) and the count is cleared by writing ones to all bits (FFh). The type of uncorrectable errors that are counted is determined by the DERRCNTSEL register. Additionally, if two uncorrectable errors occur in the same clock cycle, only one type will be counted, even if multiple types are selected.

44.5.29 ERRINJCTL—Offset 134h

Error Injection Control

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 134h
Host Memory Space: SBREG_BAR + 0x100000 + 134h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/P	**INJECCPAR:** Error Injection ECC/Parity[7:0]: Error injection ECC/parity. Zero bits indicate no injection; one bits indicate that the corresponding read/write ECC or parity bit should be inverted.
23:20	0x0 RSV	**Rsvd_ERRINJCTL_2:** Reserved
19	0x0 RW/P	**INJAMSK4:** Error Injection Address Mask[4]: This is the mask bit for error injection address bit 4; address mask bits 36:5 are located in the ERRINJAMSK register.
18	0x0 RW/P	**INJADDR4:** Error Injection Address[4]: This is error injection address bit 4; address bits 36:5 are located in the ERRINJADDR register.
17	0x0 RW/P	**INJAMSK3:** Error Injection Address Mask[3]: This is the mask bit for error injection address bit 3; address mask bits 36:5 are located in the ERRINJAMSK register.
16	0x0 RW/P	**INJADDR3:** Error Injection Address[3]: This is error injection address bit 3; address bits 35:4 are located in the ERRINJADDR register.
15:14	0x0 RW/P	**INJTRIGSEL:** Error Injection Trigger Selection: 0x = Disable error injection trigger sources 10 = Enable error injection when trigger source 0 (ddr_fsta_trigev[0]) is asserted 11 = Enable error injection when trigger source 1 (ddr_fsta_trigev[1]) is asserted. When setting this field to 1X, the INJEN field should be set to 0 since it will be set automatically when the trigger asserts.
13:12	0x0 RW/P	**INJCAP:** Command address parity injection per dclk half
11:8	0x0 RW/P	**INJSRC:** Error Injection Source[3:0]: The selected requestor source ID match against when selecting the transaction for error injection.
7	0x0 RW/P	**INJPAT:** Inject on patrol scrub request. Address match/mask logic is not used here. Error injection will occur on the next patrol scrub once INJEN is set.
6	0x0 RW/P	**INJREAD:** Error Injection in the Read Data Path: 0 = Disable 1 = Enabled
5	0x0 RW/P	**INJWRITE:** Error Injection in the Write Data Path: 0 = Disable 1 = Enabled
4	0x0 RW/P	**INJECC:** Error Injection in ECC or Parity Path Selection: 0 = Inject in the Data/Parity Path 1 = Inject in the Data/ECC Path
3	0x0 RW/P	**INJSRCEN:** Error Injection Source Enable: When set, the error injection will be performed only for the specified requestor source.
2	0x0 RW/P	**INJADREN:** Error Injection Address Enable: When set, the error injection will be performed only for addresses that match the address specified in the ERRINJADDR and ERRINJAMSK registers.
1	0x0 RW/P	**INJONCE:** Error Injection Once: When set, a single error will be injected after error injection is enabled. Otherwise, error injection will be continuous until disabled. Note that error injection has a minimum temporal granularity of one dunit clock cycle. Thus, if the address match/match bits allow injections on multiple bursts, it is possible to inject up to 4 errors (across the 4 bursts per dunit cycle) even with this bit set. To ensure predictable single error injection INJAMSK3, INJAMSK4 and ERRINJAMSK.INJAMSK[0] must be set to 0.
0	0x0 RW/V/P	**INJEN:** Error Injection Enable: 0 - Error injection is disabled 1 - Error injection is enabled. This bit is self clearing when inject once is selected and the single error injection has been performed. This bit should be set to 0 when INJTRIGSEL is set to 1X. Upon assertion, the trigger will automatically set the INJEN field.

44.5.30 ERRINJADDR—Offset 138h

Error Injection Address

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 138h
Host Memory Space: SBREG_BAR + 0x100000 + 138h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJADDR:** Error Injection PMI Address[36:5]

44.5.31 ERRINJAMSK—Offset 13Ch

Error Injection Address Mask

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 13Ch
Host Memory Space: SBREG_BAR + 0x100000 + 13Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJAMSK:** Error Injection PMI Address Mask[36:5]: For each bit that is 0 in the address mask, the corresponding PMI address bit will be compared against the same bit in ERRINJADDR.

44.5.32 ERRINJDATA0—Offset 140h

Error Injection Data 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 140h
Host Memory Space: SBREG_BAR + 0x100000 + 140h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJDATA0:** Error Injection Data[31:0]: Zero bits indicate no injection; one bits indicate that the corresponding read/write data bit should be inverted.

44.5.33 ERRINJDATA1—Offset 144h

Error Injection Data 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 144h
Host Memory Space: SBREG_BAR + 0x100000 + 144h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJDATA1:** Error Injection Data[63:32]: Zero bits indicate no injection; one bits indicate that the corresponding read/write data bit should be inverted.

44.5.34 DCS—Offset 170h

DRAM Control and Status

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 170h
Host Memory Space: SBREG_BAR + 0x100000 + 170h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RSV	**Rsvd_DCS_5:** Reserved
28	0x0 RW	**Reserved:** Reserved
27:24	0x0 RSV	**Rsvd_DCS_4:** Reserved
23	0x0 RW/V/P	**SCRAMBLE_ENABLE:** Data Scrambler Enable: When set to 1 the data lanes (DDR3_DQ[63:0]) and the ECC lanes (DDR3_DQECC[7:0]) will be scrambled, otherwise no scrambling will occur.
22	0x0 RSV	**Rsvd_DCS_3:** Reserved
21	0x0 RW/P	**MPRMODE:** Mask Chip-Selects for all commands except read commands and MRS commands
20	0x0 RW/P	**Reserved:** Reserved
19:18	0x0 RSV	**Rsvd_DCS_2:** Reserved
17:16	0x0 RW/P	**Reserved:** Reserved
15:13	0x0 RSV	**Rsvd_DCS_1:** Reserved
12	0x0 RW/P	**ODTMODE:** ODT Control Mode: • 0 - Dunit auto controls the ODT pins based on DRAM Write transactions. • 1 - The value of ODTVAL above directly controls the ODT pins.
11:8	0x0 RW/P	**ODTVAL:** ODT Control Value: Each bit of ODTVAL directly controls an ODT pin, when ODTMODE is set to 1. Used only during init flow by BIOS.
7:5	0x0 RSV	**Rsvd_DCS_0:** Reserved
4	0x0 RW/P	**CKEMODE:** CKE Control Mode: • 0 - Dunit auto controls the CKE pins based on Power-Down and Self Refresh entry and exit. • 1 - The value of CKEVAL above directly controls the CKE pins.
3:0	0x0 RW/P	**CKEVAL:** CKE Control Value: Each bit of CKEVAL directly controls a CKE pin, when CKEMODE is set to 1. Used only during init flow by BIOS.

44.5.35 DECCCTRL—Offset 180h

Dunit ECC Control

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 180h
Host Memory Space: SBREG_BAR + 0x100000 + 180h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:26	0x0 RSV	**Rsvd_DECCCTRL_1:** Reserved
25	0x0 RW/P	**RD2CLRACC:** Read to Clear C[1:0]SBEACC Registers: • 0 = C[1:0]SBEACC Registers are cleared when written • 1 = C[1:0]SBEACC Registers are cleared when written or read
24:18	0x0 RSV	**Rsvd_DECCCTRL_0:** Reserved
17	0x0 RW/P	**ENCBGEN:** Enable Generation of ECC Check Bits: • 0 - Disable generation of ECC Check Bits ECC for Bunit is 0 ECC for CPGC is generated by the CPCC • 1 - Enable generation of ECC Check Bits ECC is generated for both the Bunit and the CPGC
16	0x0 RW/P	**ECCOVREN:** ECC Check Bits Override Enable: • 0 - Normal ECC is generated. • 1 - ECC override enabled, the value in ECCOVR will be used for the ECC code.
15:8	0x0 RW/P	**ECCOVR:** ECC Check Bits Override Value: The ECC override code to be used on writes if enabled by ECCOVREN.
7:5	0x0 RW/P	**UCE_FILTER:** Uncorrectable Error Filter: • 000: Normal mode; All 8 byte ECC checks/corrections are performed independently, no anti-aliasing filters are applied. • 011: An uncorrectable error that is detected in any 8 byte ECC check will cause all four parallel 8 byte ECC checks to be treated as uncorrectable errors.
4	0x0 RW/P	**DPAREN:** Data Parity Enable: When set, data path parity is enabled. The write data parity is checked at the point when ECC is generated and read data parity is generated at the point that ECC is checked.
3	0x0 RW/P	**CAPERREN:** Enable Command Address Parity Error Detection: When set, command address parity errors are detected and signaled to the Bunit.
2	0x0 RW/P	**DERREN:** Enable Uncorrectable Error Notification: When set, uncorrectable ECC errors are signaled to the Bunit and patrol scrub.
1	0x0 RW/P	**SERREN:** Enable Correctable Error Notification: When set, correctable ECC errors are signaled to the Bunit and patrol scrub which indicates that the read data needs to be written back to memory. This causes the DRAM cell with the single bit error to be scrubbed.
0	0x0 RW/V/P	**ECCEN:** ECC Enable: When set, single bit error correction and double bit error detection (SEC/DED ECC) is enabled. The ECC is an 8 bit protection code for every 64 bits of data stored in DRAM. ECC is generated on writes and checked on reads, requiring a 72 bit DDR3 data bus width.

44.5.36 LEAKY_BUCKET_CNTR_UPPER—Offset 18Ch

Leaky Bucket Counter Upper

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 18Ch
Host Memory Space: SBREG_BAR + 0x100000 + 18Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/P	**CNTR_UPPER_RANK3:** Rank 3 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK3 + 1)* (LEAKY_BUCKET_CFG3.CNTR_HI + 1) * (LEAKY_BUCKET_CFG3.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.
23:16	0x0 RW/P	**CNTR_UPPER_RANK2:** Rank 2 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK2 + 1)* (LEAKY_BUCKET_CFG2.CNTR_HI + 1) * (LEAKY_BUCKET_CFG2.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.
15:8	0x0 RW/P	**CNTR_UPPER_RANK1:** Rank 1 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK1 + 1)* (LEAKY_BUCKET_CFG1.CNTR_HI + 1) * (LEAKY_BUCKET_CFG1.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.
7:0	0x0 RW/P	**CNTR_UPPER_RANK0:** Rank 0 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK0 + 1)* (LEAKY_BUCKET_CFG0.CNTR_HI + 1) * (LEAKY_BUCKET_CFG0.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.

44.5.37 DPATROL_SCRUB_TMR—Offset 194h

Patrol Scrub Timer Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x10] + 194h
Host Memory Space: SBREG_BAR + 0x100000 + 194h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RW/P	**PATSCRTIMER:** Patrol scrub interval timer in DCLKs (DRAM cmd clk divided by 2). A new patrol scrub is scheduled every time the timer ticks to the value in this register. Any non zero value is valid

44.5.38 UCELOG—Offset 64h

Uncorrectable Error Log This register captures the log information when the corresponding channel DERRSTS.UCE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.UCE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 64h
Host Memory Space: SBREG_BAR + 0x120000 + 64h

Default: 00000800h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RSV	**Rsvd_UCELOG_1:** Reserved
21:20	0x0 RO/V/P	**UCERNK:** Rank Address: This is the rank address that contained the error
19:16	0x0 RO/V/P	**UCEBNK:** Bank Address: This is the bank address that contained the error. DDR3: UCEBNK[3] will always be 0 UCEBNK[2:0] = BA[2:0] DDR4: UCEBNK[3:2] = BG[1:0] UCEBNK[1:0] = BA[1:0]
15	0x0 RO/V/P	**Reserved:** Reserved
14	0x0 RO/V/P	**UCELAST:** Last Burst: If this bit is set, then the error occurred within that last four DQ bus bursts before a DQ bus turn-around cycle.
13	0x0 RO/V/P	**UCEFIRST:** First Burst: If this bit is set, then the error occurred within the first four DQ bus bursts after a DQ bus turn-around cycle.
12	0x0 RO/V/P	**UCEA5:** Address bit 5: This is A[5] from the original request
11	0x1 RO/V/P	**Reserved:** Reserved
10:8	0x0 RO/V/P	**UCEBOFF:** Burst Offset: This is the burst number that contained the error. Note that all 8 bursts are always numbered starting from 0.
7:0	0x0 RO/V/P	**UCESYND:** ECC Syndrome: This is the 8-bit syndrome output of the ECC checker logic. For DNV, this field does not provide useful information and is not reliable.

44.5.39 UCEADDR—Offset 68h

Uncorrectable Error Address This register captures the log information when the corresponding channel DERRSTS.UCE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.UCE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 68h
Host Memory Space: SBREG_BAR + 0x120000 + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**UCEADDR:** Address Log: Captures the PMI address A[35:6] of the UCE error location.

44.5.40 SBELOG—Offset 6Ch

Correctable (Single Bit) Error Log This register captures the log information when the corresponding channel DERRSTS.SBE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.SBE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 6Ch
Host Memory Space: SBREG_BAR + 0x120000 + 6Ch

Default: 00000800h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RSV	**Rsvd_SBELOG_1:** Reserved
21:20	0x0 RO/V/P	**SBERNK:** Rank Address: This is the rank address that contained the error
19:16	0x0 RO/V/P	**SBEBNK:** Bank Address: This is the bank address that contained the error. DDR3: UCEBNK[3] will always be 0 UCEBNK[2:0] = BA[2:0] DDR4: UCEBNK[3:2] = BG[1:0] UCEBNK[1:0] = BA[1:0]
15	0x0 RO/V/P	**Reserved:** Reserved
14	0x0 RO/V/P	**SBELAST:** Last Burst: If this bit is set, then the error occurred within that last four DQ bus bursts before a DQ bus turn-around cycle.
13	0x0 RO/V/P	**SBEFIRST:** First Burst: If this bit is set, then the error occurred within the first four DQ bus bursts after a DQ bus turn-around cycle.
12	0x0 RO/V/P	**SBEA5:** Address bit 5: This is A[5] from the original request. In 32 bit mode this field is undefined.
11	0x1 RO/V/P	**Reserved:** Reserved
10:8	0x0 RO/V/P	**SBEBOFF:** Burst Offset: This is the burst number that contained the error. Note that all 8 bursts are always numbered starting from 0.
7:0	0x0 RO/V/P	**SBESYND:** ECC Syndrome: This is the 8-bit syndrome output of the ECC checker logic

44.5.41 SBEADDR—Offset 70h

Correctable Error Address This register captures the log information when the corresponding channel DERRSTS.SBE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.SBE[1:0] is cleared.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 70h
Host Memory Space: SBREG_BAR + 0x120000 + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**SBEADDR:** Address Log: Captures the PMI address A[35:6] of the SBE error location.

44.5.42 SBECNT0—Offset 74h

SBE Count for Rank 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 74h
Host Memory Space: SBREG_BAR + 0x120000 + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT0_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 0. Any write to this register will clear the counter to 0.

44.5.43 SBECNT1—Offset 78h

SBE Count for Rank 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 78h
Host Memory Space: SBREG_BAR + 0x120000 + 78h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT1_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 1. Any write to this register will clear the counter to 0.

44.5.44 SBECNT2—Offset 7Ch

SBE Count for Rank 2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 7Ch
Host Memory Space: SBREG_BAR + 0x120000 + 7Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT2_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 2. Any write to this register will clear the counter to 0.

44.5.45 SBECNT3—Offset 80h

SBE Count for Rank 3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 80h
Host Memory Space: SBREG_BAR + 0x120000 + 80h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RSV	**Rsvd_SBECNT3_0:** Reserved
16	0x0 RW/C/V/P	**CORRERRORSTATUS:** The per rank status bits are set when a rank's error count equals the threshold. The status bits are what tell the BIOS/BMC what caused SMI/ERR[0] to get triggered. Once the status bits are set, they will remain set until cleared by BIOS and will cause the SMI/ERR[0] to get signaled to the cores.
15:0	0x0 RW/C/V/P	**CNT:** Single Bit Error Count for Rank 3. Any write to this register will clear the counter to 0.

44.5.46 SBEACC0—Offset 84h

SBE Accumulator for Rank0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 84h
Host Memory Space: SBREG_BAR + 0x120000 + 84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC0_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device. This value is cleared by any write to this register.

44.5.47 SBEACC1—Offset 88h

SBE Accumulator for Rank1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 88h
Host Memory Space: SBREG_BAR + 0x120000 + 88h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC1_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device. This value is cleared by any write to this register.

44.5.48 SBEACC2—Offset 8Ch

SBE Accumulator for Rank2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 8Ch
Host Memory Space: SBREG_BAR + 0x120000 + 8Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC2_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device.

44.5.49 SBEACC3—Offset 90h

SBE Accumulator for Rank3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 90h
Host Memory Space: SBREG_BAR + 0x120000 + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RSV	**Rsvd_SBEACC3_0:** Reserved
17:0	0x0 RW/C/V/P	**LANE:** Single Bit Accumulator per Nibble Lane: This allows for identification of the failing x4 or x8 device.

44.5.50 DPATROL_SCRUB_CFG—Offset B0h

Patrol Scrub Config Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + B0h
Host Memory Space: SBREG_BAR + 0x120000 + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**PAT_SCRUB_ENABLE:** Bit to enable/disable patrol scrub 0: Disable patrol scrub 1: Enable patrol scrub
30	0x0 RW/P	**DIMM1_COL_ADDR_BITS:** Total number of column bits for devices on rank 0 = 10 + DIMM1_COL_ADDR_BITS 0: DDR4 and DDR3 1: Only DDR3
29	0x0 RW/P	**DIMM0_COL_ADDR_BITS:** Total number of column bits for devices on rank 0 = 10 + DIMM0_COL_ADDR_BITS 0: DDR4 and DDR3 1: Only DDR3
28:23	0x0 RW/P	**DIMM1_MAX_ROW_ADDR:** Maximum row address for DIMM1 - bits 17 to 12. Bits 11:0 are assumed to all be 1.
22:17	0x0 RW/P	**DIMM0_MAX_ROW_ADDR:** Maximum row address for DIMM0 - bits 17 to 12. Bits 11:0 are assumed to all be 1.
16	0x0 RW/P	**PATSCRUB_FORCE_WRITEBACK:** When set to 1, force write back of data with no errors. When set to 0, don't write back data that had no errors.
15:0	0x0 RW/P	**MAX_PATSCRUB_DEBIT_CNT:** Maximum number of debit patrol scrub operations. Once the patrol scrub debit counter exceeds this value, patrol scrubs will be issued until the debit counter reaches 0. Set 0 to disable debit mode.

44.5.51 UCELOG1—Offset CCh

This register captures the log information when the corresponding channel DERRSTS.UCE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.UCE[1:0] is cleared to 0.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + CCh
Host Memory Space: SBREG_BAR + 0x120000 + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RSV	**RSVD (reg_RSVD):** Reserved
26:18	0x0 RO/V/P	**UCE_COL:** Column address bits above A[5]
17:0	0x0 RO/V/P	**UCE_ROW:** Row bits

44.5.52 SBELOG1—Offset D0h

Single bit error log 1 This register captures the log information when the corresponding channel DERRSTS.SBE[1:0] is set to 1. This register is cleared and capturing of new errors is re-enabled when the corresponding channel DERRSTS.SBE[1:0] is cleared.

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + D0h
Host Memory Space: SBREG_BAR + 0x120000 + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RSV	**RSVD (reg_RSVD):** Reserved
26:18	0x0 RO/V/P	**SBE_COL:** Column bits [11,9:2], in 32 bit mode SBE_COL[0] will always be 0, SBE_COL[1] contains information for SBEBOFF[2]
17:0	0x0 RO/V/P	**SBE_ROW:** Row bits

44.5.53 CORRERRTHRSHLD0—Offset 100h

Correctable Error Threshold for Rank 0

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 100h
Host Memory Space: SBREG_BAR + 0x120000 + 100h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD0_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 0. When the error accumulation in SBECNT0 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.54 CORRERRTHRSHLD1—Offset 104h

Correctable Error Threshold for Rank 1

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 104h
Host Memory Space: SBREG_BAR + 0x120000 + 104h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD1_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 1. When the error accumulation in SBECNT1 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.55 CORRERRTHRSHLD2—Offset 108h

Correctable Error Threshold for Rank 2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 108h
Host Memory Space: SBREG_BAR + 0x120000 + 108h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD2_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 2. When the error accumulation in SBECNT2 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.56 CORRERRTHRSHLD3—Offset 10Ch

Correctable Error Threshold for Rank 3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 10Ch
Host Memory Space: SBREG_BAR + 0x120000 + 10Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**Rsvd_CORRERRTHRSHLD3_0:** Reserved
15:0	0x0 RW/P	**THRSH_RNK:** Correctable error threshold for rank 3. When the error accumulation in SBECNT3 hits this value, then the CORRERRSTATUS is set and a DO_SMI message is sent if the threshold value is greater than 0.

44.5.57 LEAKY_BUCKET_CFG0—Offset 110h

Leaky Bucket Configuration Rank 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 110h
Host Memory Space: SBREG_BAR + 0x120000 + 110h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 0 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 0, CNTR_HI.

44.5.58 LEAKY_BUCKET_CFG1—Offset 114h

Leaky Bucket Configuration Rank 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 114h
Host Memory Space: SBREG_BAR + 0x120000 + 114h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 1 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 1, CNTR_HI.

44.5.59 LEAKY_BUCKET_CFG2—Offset 118h

Leaky Bucket Configuration Rank 2

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 118h
Host Memory Space: SBREG_BAR + 0x120000 + 118h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 2 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 2, CNTR_HI.

44.5.60 LEAKY_BUCKET_CFG3—Offset 11Ch

Leaky Bucket Configuration Rank 3

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 11Ch
Host Memory Space: SBREG_BAR + 0x120000 + 11Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/P	**CNTR_HI:** Specifies the leaky bucket leak rat in CNTR_LO ticks. When the leaky bucket counter counts through CNTR_HI, the correctable error count for rank 3 is decremented by one.
15:0	0x0 RW/P	**CNTR_LO:** Units for this register are 8192 DRAM clocks. When greater than zero, leaky bucket is enabled. This is the unit for the high order counter for rank 3, CNTR_HI.

44.5.61 FERRNERR—Offset 120h

First Error and Next Error Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 120h
Host Memory Space: SBREG_BAR + 0x120000 + 120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RSV	**Rsvd_FERRNERR_1 (Rsvd_FERRNERR_3):** Reserved
20	0x0 RO/V/P	**FERRUCEPAT:** First Error Uncorrectable Patrol Scrub Read Error Detected: When set, the first error detected was an uncorrectable (multiple bit) error on the patrol scrub read from memory.
19	0x0 RO/V/P	**FERRAPE:** First Error Uncorrectable DDR4 Command Address Parity Error: When set, the first error detected was the assertion of the xxDDR3_0_ALERT_N pin indicating that one or more DRAMs detected a Command/Address parity error.
18	0x0 RO/V/P	**FERRWPE:** First Error Uncorrectable Write Parity Error Detected: When set, the first error detected was an uncorrectable (parity) error on the write data received from the Bunit.
17	0x0 RO/V/P	**FERRUCE:** First Error Uncorrectable Read Error Detected: When set, the first error detected was an uncorrectable (multiple bit) error on the read data from memory.
16	0x0 RO/V/P	**FERRSBE:** First Error Correctable Read Error Detected: When set, the first error detected was a single bit error on the read data from memory and the error was corrected.
15:5	0x0 RSV	**Rsvd_FERRNERR_0 (Rsvd_FERRNERR_1):** Reserved
4	0x0 RO/V/P	**NERRUCEPAT:** Next Error Uncorrectable Patrol Scrub Read Error: When set, the second error detected was an uncorrectable (mutliple bit) error on the patrol scrub read data from memory.
3	0x0 RO/V/P	**NERRAPE:** Next Error Uncorrectable DDR4 Command Address Parity Error: When set, the second error detected was the assertion of the xxDDR3_0_ALERT_N pin indicating that one or more DRAMs detected a Command/Address parity error. Note that this bit can never be set as the same time as FERRAPE
2	0x0 RO/V/P	**NERRWPE:** Next Error Uncorrectable Write Parity Error Detected: When set, the second error detected was an uncorrectable (parity) error on the write data received from the Bunit.
1	0x0 RO/V/P	**NERRUCE:** Next Error Uncorrectable Read Error Detected: When set, the second error detected was an uncorrectable (multiple bit) error on the read data from memory.
0	0x0 RO/V/P	**NERRSBE:** Next Error Correctable Read Error Detected: When set, the second error detected was a single bit error on the read data from memory and the error was corrected.

44.5.62 DERRSTS—Offset 124h

Error Status Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 124h
Host Memory Space: SBREG_BAR + 0x120000 + 124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RSV	**Reserved:** Reserved
6	0x0 RW/1C/V/P	**CAP_ERR_STATE:** Channel Command Address Parity Error State. 1 = CAP error seen, error state entered. All PMI reads will be returned with bad parity. 0 = No CAP error seen. Normal PMI operation.
5	0x0 RO/V/P	**ALERT:** Current state of the channel ALERT_N pin, captured here as active high: 1 = Error being driven by at least one DRAM device 0 = No error currently detected by any DRAM device
4	0x0 RW/1C/V/P	**UCEPAT:** Uncorrectable (multiple bit) patrol scrub error: When set, an uncorrectable (multiple bit error was detected on the read data from memory.
3	0x0 RW/1C/V/P	**APE:** Uncorrectable DDR4 Command/Address Parity Error: When set, an uncorrectable DDR4 command/address parity error was detected by one or more of the DRAMs on channel 0.
2	0x0 RW/1C/V/P	**WPE:** Uncorrectable (Parity) Write Error: When set, an uncorrectable (parity) error was detected on the write data received from the Bunit.
1	0x0 RW/1C/V/P	**UCE:** Uncorrectable (Double Bit) Read Error: When set, a double bit error was detected on the read data from memory.
0	0x0 RW/1C/V/P	**SBE:** Correctable (Single Bit) Read Error: When set, a single bit error was detected on the read data from memory and the error was corrected.

44.5.63 DERRMSKSEV—Offset 128h

Error Mask and Severity

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 128h
Host Memory Space: SBREG_BAR + 0x120000 + 128h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RSV	**Rsvd_DERRMSKSEV_2:** Reserved
20	0x0 RW/P	**MSK_UCEPAT:** Uncorrectable patrol scrub error mask: When set, uncorrectable patrol scrub ECC data errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
19	0x0 RW/P	**MSK_APE:** Uncorrectable command/address parity error mask: When set, uncorrectable DDR4 command/address parity errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
18	0x0 RW/P	**MSK_WDBR:** Uncorrectable (parity) write data buffer read error mask: When set, uncorrectable (pairty) write data buffer read errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
17	0x0 RW/P	**MSK_UCE:** Uncorrectable (multiple bit) error mask: When set, uncorrectable (multiple bit) read and patrol scrub errors will not be logged in DERRESTS[0], DO_SERR_SEV messages will not be sent to the IEH, and derrcnt will not count for this error.
16	0x0 RW/P	**MSK_SBE:** Correctable (single bit) error mask: When set, correctable (single bit) read and patrol scrub errors will not be logged in DERRESTS[0] and DO_SERR_SEV messages will not be sent to the IEH.
15:5	0x0 RSV	**Rsvd_DERRMSKSEV_1:** Reserved
4	0x0 RW/P	**SEV_UCEPAT:** Uncorrectable (Multiple Bit) Patrol Scrub Read Error Severity: When set, UCE errors logged in DERRSTS[5] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
3	0x0 RW/P	**SEV_APE:** Uncorrectable DDR4 Command/Address Parity Error Severity: When set, APE errors logged in DERRSTS[3] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
2	0x0 RW/P	**SEV_WDBR:** Uncorrectable (Parity) Write Error Severity: When set, WPE errors logged in DERRSTS[2] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
1	0x0 RW/P	**SEV_UCE:** Uncorrectable (Multiple Bit) Read Error Severity: When set, UCE errors logged in DERRSTS[1] will be escalated to the global error logic as a fatal error; otherwise it will be escalated as a non-fatal error.
0	0x0 RSV	**Rsvd_DERRMSKSEV_0:** Reserved

44.5.64 DERRCNTSEL—Offset 12Ch

Uncorrectable Error Count Select

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 12Ch
Host Memory Space: SBREG_BAR + 0x120000 + 12Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RSV	**Rsvd_DERRCNTSEL_2:** Reserved
4	0x0 RW/P	**SEL_UCEPAT:** Uncorrectable (Multiple Bit) Patrol Scrub Read Error Count Select: When set, UCE errors logged in DERRSTS[1] will be counted in DERRCNT.UNCCNT1.
3	0x0 RW/P	**SEL_APE:** Uncorrectable DDR4 Command/Address Parity Error Count Select: When set, APE0 errors logged in DERRSTS[3] will be counted in DERRCNT.UNCCNT0.
2	0x0 RW/P	**SEL_WPE:** Uncorrectable (Parity) Write Error Count Select: When set, WPE0 errors logged in DERRSTS[2] will be counted in DERRCNT.UNCCNT0.
1	0x0 RW/P	**SEL_UCE:** Uncorrectable (Multiple Bit) Read Error Count Select: When set, UCE0 errors logged in DERRSTS[1] will be counted in DERRCNT.UNCCNT0.
0	0x0 RSV	**Rsvd_DERRCNTSEL_0:** Reserved

44.5.65 DERRCNT—Offset 130h

Uncorrectable Error Count

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 130h
Host Memory Space: SBREG_BAR + 0x120000 + 130h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RSV	**Rsvd_DERRCNT:** Reserved
7:0	0x0 RW/1C/V/P	**UNCCNT:** Uncorrectable Error Count: The count of uncorrectable errors that have occurred since the last time the count was cleared. The count limit is 128 (80h) and the count is cleared by writing ones to all bits (FFh). The type of uncorrectable errors that are counted is determined by the DERRCNTSEL register. Additionally, if two uncorrectable errors occur in the same clock cycle, only one type will be counted, even if multiple types are selected.

44.5.66 ERRINJCTL—Offset 134h

Error Injection Control

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 134h
Host Memory Space: SBREG_BAR + 0x120000 + 134h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/P	**INJECCPAR:** Error Injection ECC/Parity[7:0]: Error injection ECC/parity. Zero bits indicate no injection; one bits indicate that the corresponding read/write ECC or parity bit should be inverted.
23:20	0x0 RSV	**Rsvd_ERRINJCTL_2:** Reserved
19	0x0 RW/P	**INJAMSK4:** Error Injection Address Mask[4]: This is the mask bit for error injection address bit 4; address mask bits 36:5 are located in the ERRINJAMSK register.
18	0x0 RW/P	**INJADDR4:** Error Injection Address[4]: This is error injection address bit 4; address bits 36:5 are located in the ERRINJADDR register.
17	0x0 RW/P	**INJAMSK3:** Error Injection Address Mask[3]: This is the mask bit for error injection address bit 3; address mask bits 36:5 are located in the ERRINJAMSK register.
16	0x0 RW/P	**INJADDR3:** Error Injection Address[3]: This is error injection address bit 3; address bits 35:4 are located in the ERRINJADDR register.
15:14	0x0 RW/P	**INJTRIGSEL:** Error Injection Trigger Selection: 0x = Disable error injection trigger sources 10 = Enable error injection when trigger source 0 (ddr_fsta_trigev[0]) is asserted 11 = Enable error injection when trigger source 1 (ddr_fsta_trigev[1]) is asserted. When setting this field to 1X, the INJEN field should be set to 0 since it will be set automatically when the trigger asserts.
13:12	0x0 RW/P	**INJCAP:** Command address parity injection per dclk half
11:8	0x0 RW/P	**INJSRC:** Error Injection Source[3:0]: The selected requestor source ID match against when selecting the transaction for error injection.
7	0x0 RW/P	**INJPAT:** Inject on patrol scrub request. Address match/mask logic is not used here. Error injection will occur on the next patrol scrub once INJEN is set.
6	0x0 RW/P	**INJREAD:** Error Injection in the Read Data Path: 0 = Disable 1 = Enabled
5	0x0 RW/P	**INJWRITE:** Error Injection in the Write Data Path: 0 = Disable 1 = Enabled
4	0x0 RW/P	**INJECC:** Error Injection in ECC or Parity Path Selection: 0 = Inject in the Data/Parity Path 1 = Inject in the Data/ECC Path
3	0x0 RW/P	**INJSRCEN:** Error Injection Source Enable: When set, the error injection will be performed only for the specified requestor source.
2	0x0 RW/P	**INJADREN:** Error Injection Address Enable: When set, the error injection will be performed only for addresses that match the address specified in the ERRINJADDR and ERRINJAMSK registers.
1	0x0 RW/P	**INJONCE:** Error Injection Once: When set, a single error will be injected after error injection is enabled. Otherwise, error injection will be continuous until disabled. Note that error injection has a minimum temporal granularity of one dunit clock cycle. Thus, if the address match/match bits allow injections on multiple bursts, it is possible to inject up to 4 errors (across the 4 bursts per dunit cycle) even with this bit set. To ensure predictable single error injection INJAMSK3, INJAMSK4 and ERRINJAMSK.INJAMSK[0] must be set to 0.
0	0x0 RW/V/P	**INJEN:** Error Injection Enable: 0 - Error injection is disabled 1 - Error injection is enabled. This bit is self clearing when inject once is selected and the single error injection has been performed. This bit should be set to 0 when INJTRIGSEL is set to 1X. Upon assertion, the trigger will automatically set the INJEN field.

44.5.67 ERRINJADDR—Offset 138h

Error Injection Address

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 138h
Host Memory Space: SBREG_BAR + 0x120000 + 138h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJADDR:** Error Injection PMI Address[36:5]

44.5.68 ERRINJAMSK—Offset 13Ch

Error Injection Address Mask

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 13Ch
Host Memory Space: SBREG_BAR + 0x120000 + 13Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJAMSK:** Error Injection PMI Address Mask[36:5]: For each bit that is 0 in the address mask, the corresponding PMI address bit will be compared against the same bit in ERRINJADDR.

44.5.69 ERRINJDATA0—Offset 140h

Error Injection Data 0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 140h
Host Memory Space: SBREG_BAR + 0x120000 + 140h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJDATA0:** Error Injection Data[31:0]: Zero bits indicate no injection; one bits indicate that the corresponding read/write data bit should be inverted.

44.5.70 ERRINJDATA1—Offset 144h

Error Injection Data 1

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 144h
Host Memory Space: SBREG_BAR + 0x120000 + 144h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**INJDATA1:** Error Injection Data[63:32]: Zero bits indicate no injection; one bits indicate that the corresponding read/write data bit should be inverted.

44.5.71 DCS—Offset 170h

DRAM Control and Status

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 170h
Host Memory Space: SBREG_BAR + 0x120000 + 170h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RSV	**Rsvd_DCS_5:** Reserved
28	0x0 RW	**PMICTL:** PMI Control: • 0: Connect to the Bunit • 1: Connect to CPGC When this field is changed, the Dunit will only switch after all previous transactions from the previous unit have been completed. Since the Dunit is a slave to the PMI interface and it cannot prevent the Bunit or CPGC from sendign transactions, the initiatior of this request will have to make sure that the Bunit/CPGC are configured appropriately. Status of this operation from the Dunit perspective is provided in the PMI STAT register.
27:24	0x0 RSV	**Rsvd_DCS_4:** Reserved
23	0x0 RW/V/P	**SCRAMBLE_ENABLE:** Data Scrambler Enable: When set to 1 the data lanes (DDR3_DQ[63:0]) and the ECC lanes (DDR3_DQECC[7:0]) will be scrambled, otherwise no scrambling will occur.
22	0x0 RSV	**Rsvd_DCS_3:** Reserved
21	0x0 RW/P	**MPRMODE:** Mask Chip-Selects for all commands except read commands and MRS commands
20	0x0 RW/P	**BLKPHASEB:** Block Phase_B Commands: The Dunit runs at half the frequency of the DRAM clock to save power. In order to issue back-to-back commands on every DRAM clock cycles, the Dunit has to schedule two commands per Dunit clock. Therefore, it processes requests thru two separate arbitration paths labeled as Phase_A and Phase_B. Setting this bit to a 1 will disable Phase_B completely, and all memory requests will be processed thru Phase_A arbitration path. With only Phase_A, the DRAM devices will never see back-to-back commands. The best it will see is a command every other DRAM clock cycle. • 0 - No block • 1 - Block
19:18	0x0 RSV	**Rsvd_DCS_2:** Reserved
17:16	0x0 RW/P	**ECCLANESWAP:** ECC Byte Lane Swap: This feature is not supported in 32 bit mode and this field must be set to 0. • 0h - Normal mode • 1h - Swap ECC and Data Byte 0 • 2h - Reserved • 3h - Reserved
15:13	0x0 RSV	**Rsvd_DCS_1:** Reserved
12	0x0 RW/P	**ODTMODE:** ODT Control Mode: • 0 - Dunit auto controls the ODT pins based on DRAM Write transactions. • 1 - The value of ODTVAL above directly controls the ODT pins.
11:8	0x0 RW/P	**ODTVAL:** ODT Control Value: Each bit of ODTVAL directly controls an ODT pin, when ODTMODE is set to 1. Used only during init flow by BIOS.
7:5	0x0 RSV	**Rsvd_DCS_0:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW/P	**CKEMODE:** CKE Control Mode: • 0 - Dunit auto controls the CKE pins based on Power-Down and Self Refresh entry and exit. • 1 - The value of CKEVAL above directly controls the CKE pins.
3:0	0x0 RW/P	**CKEVAL:** CKE Control Value: Each bit of CKEVAL directly controls a CKE pin, when CKEMODE is set to 1. Used only during init flow by BIOS.

44.5.72 DECCCTRL—Offset 180h

Dunit ECC Control

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 180h
Host Memory Space: SBREG_BAR + 0x120000 + 180h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:26	0x0 RSV	**Rsvd_DECCCTRL_1:** Reserved
25	0x0 RW/P	**RD2CLRACC:** Read to Clear C[1:0]SBEACC Registers: • 0 = C[1:0]SBEACC Registers are cleared when written • 1 = C[1:0]SBEACC Registers are cleared when written or read
24:18	0x0 RSV	**Rsvd_DECCCTRL_0:** Reserved
17	0x0 RW/P	**ENCBGEN:** Enable Generation of ECC Check Bits: • 0 - Disable generation of ECC Check Bits • 1 - Enable generation of ECC Check Bits ECC is generated for both the Bunit and the CPGC
16	0x0 RW/P	**ECCOVREN:** ECC Check Bits Override Enable: • 0 - Normal ECC is generated. • 1 - ECC override enabled, the value in ECCOVR will be used for the ECC code.
15:8	0x0 RW/P	**ECCOVR:** ECC Check Bits Override Value: The ECC override code to be used on writes if enabled by ECCOVREN.
7:5	0x0 RW/P	**UCE_FILTER:** Uncorrectable Error Filter: • 000: Normal mode; All 8 byte ECC checks/corrections are performed independently, no anti-aliasing filters are applied. • 011: An uncorrectable error that is detected in any 8 byte ECC check will cause all four parallel 8 byte ECC checks to be treated as uncorrectable errors.
4	0x0 RW/P	**DPAREN:** Data Parity Enable: When set, data path parity is enabled. The write data parity is checked at the point when ECC is generated and read data parity is generated at the point that ECC is checked.
3	0x0 RW/P	**CAPERREN:** Enable Command Address Parity Error Detection: When set, command address parity errors are detected and signalled to the Bunit.
2	0x0 RW/P	**DERREN:** Enable Uncorrectable Error Notification: When set, uncorrectable ECC errors are signalled to the Bunit and patrol scrub.
1	0x0 RW/P	**SERREN:** Enable Correctable Error Notification: When set, correctable ECC errors are signalled to the Bunit and patrol scrub which indicates that the read data needs to be written back to memory. This causes the DRAM cell with the single bit error to be scrubbed.
0	0x0 RW/V/P	**ECCEN:** ECC Enable: When set, single bit error correction and double bit error detection (SEC/DED ECC) is enabled. The ECC is an 8 bit protection code for every 64 bits of data stored in DRAM. ECC is generated on writes and checked on reads, requiring a 72 bit DDR3 data bus width.

44.5.73 LEAKY_BUCKET_CNTR_UPPER—Offset 18Ch

Leaky Bucket Counter Upper

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 18Ch
Host Memory Space: SBREG_BAR + 0x120000 + 18Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/P	**CNTR_UPPER_RANK3:** Rank 3 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK3 + 1)* (LEAKY_BUCKET_CFG3.CNTR_HI + 1) * (LEAKY_BUCKET_CFG3.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.
23:16	0x0 RW/P	**CNTR_UPPER_RANK2:** Rank 2 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK2 + 1)* (LEAKY_BUCKET_CFG2.CNTR_HI + 1) * (LEAKY_BUCKET_CFG2.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.
15:8	0x0 RW/P	**CNTR_UPPER_RANK1:** Rank 1 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK1 + 1)* (LEAKY_BUCKET_CFG1.CNTR_HI + 1) * (LEAKY_BUCKET_CFG1.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.
7:0	0x0 RW/P	**CNTR_UPPER_RANK0:** Rank 0 CNTR_UPPER configuration. Total Leak Rate = (CNTR_UPPER_RANK0 + 1)* (LEAKY_BUCKET_CFG0.CNTR_HI + 1) * (LEAKY_BUCKET_CFG0.CNTR_LO + 1) * 8192 DRAM clocks. Setting CNTR_LO to zero will disable the leaky bucket.

44.5.74 DPATROL_SCRUB_TMR—Offset 194h

Patrol Scrub Timer Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x12] + 194h
Host Memory Space: SBREG_BAR + 0x120000 + 194h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RW/P	**PATSCRTIMER:** Patrol scrub interval timer in DCLKs (DRAM cmd clk divided by 2). A new patrol scrub is scheduled every time the timer ticks to the value in this register. Any non zero value is valid

44.5.75 ICLK_DWORD8—Port 99h, Offset 220h

Flex Clock 0 and Flex Clock 1 Frequency Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x99] + 220h
Host Memory Space: SBREG_BAR + 0x990000 + 220h

Default: 0004_2222h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RSV	**Reserved**
13	0x1 RW/V	**sel_flex_base1:** Selects the frequency of flex_base1: 0=200 MHz for flex1 clock 1=96 MHz for flex1 clock
12	0x0 RSV	**Reserved**
11:8	0x2 RW/V	**flex_ck_div1:** flex clock 1 is flex_base1/flex_ck_div1.
7:6	0x0 RSV	**Reserved**
5	0x1 RW/V	**sel_flex_base0** Selects the frequency of flex_base0: 0=200 MHz for flex1 clock 1=96 MHz for flex1 clock
4	0x0 RSV	**Reserved**
3:0	0x2 RW/V	**flex_ck_div0:** flex clock 0 is flex_base0/flex_ck_div0.

§ §

45 Global and Local Error Registers (GLMREG) - B0, D4, F0

45.1 Introduction and Index

The host-accessible registers for the Global and Local Error Registers (GLMREG) are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

45.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 4 (decimal), Function 0. The offset addresses are listed.

Table 45-1. Summary of PCI Configuration Registers—0/4/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"GLREG Vendor ID (GLREG_VID)—Offset 0h" on page 1483
4	2	0000	"GLREG PCI Command (GLREG_PCICMD)—Offset 4h" on page 1484
6	2	0010	"GLREG PCI Status (GLREG_PCISTS)—Offset 6h" on page 1485
9	3	00060000	"GLREG Class Code (GLREG_CC)—Offset 9h" on page 1486
C	1	00	"GLREG Cacheline Size (GLREG_CLS)—Offset Ch" on page 1486
2C	2	8086	"GLREG Subsystem Vendor ID (GLREG_SVID)—Offset 2Ch" on page 1487
34	1	40	"GLREG Capabilities Pointer (GLREG_CAPPTR)—Offset 34h" on page 1487
3D	3	00	"GLREG Interrupt Pin (GLREG_INTP)—Offset 3Dh" on page 1488
40	2	0010	"GLREG PCI Express Capability List (GLREG_EXPCAPLST)—Offset 40h" on page 1488
42	2	0092	"GLREG PCI Express Capability List (GLREG_EXPCAPLST)—Offset 40h" on page 1488
48	2	0000	"GLREG Device Control (GLREG_DEVCTL)—Offset 48h" on page 1490
4A	1	00	"GLREG Device Status (GLREG_DEVSTS)—Offset 4Ah" on page 1491
200	4	00000000	"GLREG Global Correctable Error Status (GLREG_GCOERRSTS)—Offset 200h" on page 1492
204	4	00000000	"GLREG Global Non-Fatal Error Status (GLREG_GNFERRSTS)—Offset 204h" on page 1494
208	4	00000000	"GLREG Global Fatal Error Status (GLREG_GFAERRSTS)—Offset 208h" on page 1496
20C	4	00000000	"GLREG Global Error Mask (GLREG_GERRMSK)—Offset 20Ch" on page 1498
228	8	0000000000000000	"GLREG Global Error Timer (GLREG_GTIME)—Offset 228h" on page 1500
230	8	0000000000000000	"GLREG Global Correctable FERR Error Time Stamp (GLREG_GCOFERRTIME)—Offset 230h" on page 1500
238	8	0000000000000000	"GLREG Global Nonfatal FERR Error Time Stamp (GLREG_GNFFERRTIME)—Offset 238h" on page 1501
240	8	0000000000000000	"GLREG Global Fatal FERR Error Time Stamp (GLREG_GFAFERRTIME)—Offset 240h" on page 1501
248	4	00000000	"GLREG Global System Event Status (GLREG_GSYSEVTSTS)—Offset 248h" on page 1502
24C	4	00000000	"GLREG Global System Event Mask (GLREG_GSYSEVTMSK)—Offset 24Ch" on page 1502
250	4	00000025	"GLREG Global System Event Map (GLREG_GSYSEVTMAP)—Offset 250h" on page 1503
254	4	00000025	"GLREG Error Pin Control (GLREG_ERRPINCTRL)—Offset 254h" on page 1504
258	4	00000000	"GLREG Error Pin Status (GLREG_ERRPINSTS)—Offset 258h" on page 1504
25C	4	00000000	"GLREG Error Pin Data (GLREG_ERRPINDATA)—Offset 25Ch" on page 1505
294	1	00	"GLREG Uncorrectable Error Counter (GLREG_LUNCERRCNT)—Offset 294h" on page 1506

45.2 Registers in Configuration Space

45.2.1 GLREG Vendor ID (GLREG_VID)—Offset 0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:4, F:0] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**VID:** This field identifies Intel as the manufacturer of the device.

45.2.2 GLREG PCI Command (GLREG_PCICMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:4, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved:** Reserved.
10	0x0 RO	**INTxD:** This bit controls the ability of the PCI-Express Function to generate INTx interrupt message. When set, functions are prevented from asserting INTx interrupt messages. Any INTx emulation interrupts already asserted by the function must be deserted when this bit is set by generating a Deassert_INTx message(s).
9	0x0 RO	**FBE:** Not applicable to PCI-Express. Hardwired to 0.
8	0x0 RO	**SEE:** When set, this bit enables reporting of Non-Fatal and Fatal Errors detected by the Function to the Root Complex. ERR_COR messages are not affected by this bit. Errors are reported when enabled either through this bit or through the PCI Express-specific bits in the Device Control Register (GLREG_DEVCTL).
7	0x0 RO	**WCC:** Not applicable to PCI-Express. Hardwired to 0.
6	0x0 RO	**PERE:** This bit controls the setting of the master data parity error bit in the Status Register (GLREG_PCISTS) in response to a parity error received on the PCI Express interface (poisoned TLP).
5	0x0 RO	**VGA_PSE:** Not applicable to PCI-Express. Hardwired to 0.
4	0x0 RO	**MWIE:** Not applicable to PCI-Express. Hardwired to 0.
3	0x0 RO	**SCE:** Not applicable to PCI-Express. Hardwired to 0.
2	0x0 RO	**BME:** This bit controls the ability of the Function to issue Memory and I/O read or write requests, and the ability of Root or Switch port to forward memory and I/O read or write requests in the upstream direction.
1	0x0 RO	**MSE:** This bit controls the function's response to Memory Space accesses.
0	0x0 RO	**IOSE:** This bit controls the function's response to IO Space accesses.

45.2.3 GLREG PCI Status (GLREG_PCISTS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:4, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**DPE:** This bit is set when a poisoned TLP is received. This bit is set even when the parity error response enable bit (bit[6] of the PCICMD Register (GLREG_PCICMD) is not set.
14	0x0 RO	**SSE:** This bit is set when ERR_FATAL or ERR_NONFATAL messages are sent to the root complex event collector and the SERR enable bit in the PCICMD Register (GLREG_PCICMD) is set.
13	0x0 RO	**RMA:** This bit is set when the requester receives a completion with an UR completion status.
12	0x0 RO	**RTA:** This bit is set when a requester receives a CA completions status.
11	0x0 RO	**STA:** This bit is set when the switch generates a completion packet with Completer Abort (CA) status is generated by its primary side.
10:9	0x0 RO	**Reserved:** Reserved
8	0x0 RO	**MDPD:** This bit is set by a requester if the parity error response enable bit (PERE) in the Command Register (GLREG_PCICMD) is set and either of the following two conditions occur: • Requester receives a completion marked poisoned. • Requester poisons a write requests. If the parity error bit is 0b, this bit is never set.
7	0x0 RO	**Reserved:** Reserved
6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**Reserved:** Reserved
4	0x1 RO	**CAPE:** This bit indicates the presence of an Extended capabilities list items. This bit is hardwired to 1b.
3	0x0 RO	**INTS:** When set, this bit indicates that an INTx emulation interrupt is pending internally in this function.
2:0	0x0 RO	**RSVD1:** Reserved

45.2.4 GLREG Class Code (GLREG_CC)—Offset 9h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 9h

Default: 00060000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x6 RO	**BC:** This function is hardwired to 06h indicating a Host bridge.
15:8	0x0 RO	**SC:** This function is hardwired to 00h, indicating a Host Bridge.
7:0	0x0 RO	**RLPI:** Set to 00h for all non-APIC devices.

45.2.5 GLREG Cacheline Size (GLREG_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:4, F:0] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**CLS:** These bits specify the system cache-line size in units of DWords. This field is implemented by PCI Express devices but has no effect on device behavior.

45.2.6 GLREG Subsystem Vendor ID (GLREG_SVID)—Offset 2Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:4, F:0] + 2Ch

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RW/O	**SVID:** This field identifies Intel as the manufacturer of the device.

45.2.7 GLREG Capabilities Pointer (GLREG_CAPPTR)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:4, F:0] + 34h

Default: 40h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x40 RO	**CPTR:** Contains the offset of the first item in the list of capabilities. (GLREG_EXPCAPLST)

45.2.8 GLREG Interrupt Pin (GLREG_INTP)—Offset 3Dh

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:4, F:0] + 3Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**INTP:** This register tells which interrupt pin the function uses. • 01h: Generate INTA • 02h: Generate INTB • 03h: Generate INTC • 04h: Generate INTD • Others: Reserved • Devices (or device functions) that do not use an interrupt pin must put a 0 in this register. Not applicable since this device does not generate any interrupts on its own.

45.2.9 GLREG PCI Express Capability List (GLREG_EXPCAPLST)—Offset 40h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:4, F:0] + 40h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**NP:** Contains the offset of the next item in the capabilities list. Indicates that this is the last capability in the list.
7:0	0x10 RO	**CAPID:** Identifies the function as PCI Express capable.

45.2.10 GLREG PCI Express Capabilities (GLREG_EXPCAP)—Offset 42h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:4, F:0] + 42h

Default: 0092h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**RSVD0:** Reserved
13:9	0x0 RO	**IMN:** This field indicates the interrupt message number that is generated from the PCI Express port.
8	0x0 RO	**SI:** Indicates the PCI Express link associated with this port is connected to a slot.
7:4	0x9 RO	**DT:** 1001b Root Complex Integrated Endpoint (RCEC).
3:0	0x2 RO	**VN:** These bits indicate the version number of the PCI Express capability structure.

45.2.11 GLREG Device Control (GLREG_DEVCTL)—Offset 48h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:4, F:0] + 48h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RO	**MRRS:** This field sets the maximum Read Requests size for the function as a requester. The Function must not generate read requests with size exceeding the set value. • 000b: 128 bytes maximum Read Request size • 001b: 256 bytes maximum Read Request size • 010b: 512 bytes maximum Read Request size • 011b: 1024 bytes maximum Read Request size • 100b: 2048 bytes maximum Read Request size • 101b: 4096 bytes maximum Read Request size • Others: Reserved Functions that do not generate Read Requests larger than 128B and functions that do not generate Read Requests on their own behalf are permitted to implement this field as Read Only (RO) with a value of 000b.
11	0x0 RO	**ENOSNP:** This bit is permitted to be hardwired to 0b if a function would never set the No Snoop attribute in transactions it initiates.
10	0x0 RO	**AUXPME:** Not supported
9	0x0 RO	**PFE:** Functions that do not implement this capability hardware this bit to 0b.
8	0x0 RO	**ETFE:** Functions that do not implement this capability hardwire this bit to 0b.
7:5	0x0 RW	**MPS:** This field sets maximum TLP payload size for the function. As a receiver, the function must handle TLPs as larger as the set value. As a Transmitter, the function must not generate TLPs exceeding the set value. • 000b: 128 bytes maximum payload size • 001b: 256 bytes maximum payload size • 010b: 512 bytes maximum payload size (Unsupported) • 011b: 1024 bytes maximum payload size (Unsupported) • 100b: 2048 bytes maximum payload size (Unsupported) • 101b: 4096 bytes maximum payload size (Unsupported) • Others: Reserved
4	0x0 RO	**ENRO:** A function is permitted to hardwire this bit to 0b if it never sets the Relaxed ordering attribute in transactions it initiates as a requester.
3	0x0 RO	**URRE:** This bit controls the enabling of ERR_CORR, ERR_NONFATAL or ERR_FATAL messages on PCI Express for reporting Unsupported Request (UR) errors.
2	0x0 RO	**FERE:** Generation of the ERR_FATAL message is disabled.
1	0x0 RO	**NFERE:** Generation of the ERR_NONFATAL message is disabled.
0	0x0 RO	**CERE:** Generation of the ERR_CORR message is disabled.

45.2.12 GLREG Device Status (GLREG_DEVSTS)—Offset 4Ah

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:4, F:0] + 4Ah

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**Reserved:** Reserved
4	0x0 RO	**APD:** Auxiliary Power is not supported.
3	0x0 RO	**URD:** This bit indicates that the device received an Unsupported Request (UR).
2	0x0 RO	**FED:** This bit indicates status of Fatal Errors detected.
1	0x0 RO	**NFED:** This bit indicates status of Non-Fatal Errors detected.
0	0x0 RO	**CED:** This bit indicates status of Correctable Errors detected.

45.2.13 GLREG Global Correctable Error Status (GLREG_GCOERRSTS)—Offset 200h

This register indicates that a Correctable Error is reported to the global error logic. An individual error status bit that is set indicates that a particular local device or RCEC has detected an error.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 200h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/1C/V/P	**Reserved:** Reserved.
23	0x0 RW/1C/V/P	**NPK_CO_STS:** NPK Error Status - Not used by the SoC
22	0x0 RW/1C/V/P	**SPIESPI_CO_STS:** SPIESPI Error Status - Not used by the SoC
21	0x0 RW/1C/V/P	**HSUART_CO_STS:** HSUART Error Status - Not used by the SoC
20	0x0 RW/1C/V/P	**SMBUS_CO_STS:** SMBUS Error Status - Not used by the SoC
19	0x0 RW/1C/V/P	**LPC_CO_STS:** LPC Error Status - Not used by the SoC
18	0x0 RW/1C/V/P	**USB_CO_STS:** USB Error Status - Not used by the SoC
17	0x0 RW/1C/V/P	**SATA1_CO_STS:** SATA1 Error Status - Not used by the SoC
16	0x0 RW/1C/V/P	**SATA0_CO_STS:** SATA0 Error Status - Not used by the SoC
15	0x0 RW/1C/V/P	**VRP2_CO_STS:**
14	0x0 RW/1C/V/P	**VRP1_CO_STS:**
13	0x0 RW/1C/V/P	**VRP0_CO_STS:**
12	0x0 RW/1C/V/P	**PCIeRP7_CO_STS:**
11	0x0 RW/1C/V/P	**PCIeRP6_CO_STS:**
10	0x0 RW/1C/V/P	**PCIeRP5_CO_STS:**
9	0x0 RW/1C/V/P	**PCIeRP4_CO_STS:**
8	0x0 RW/1C/V/P	**PCIeRP3_CO_STS:**
7	0x0 RW/1C/V/P	**PCIeRP2_CO_STS:**
6	0x0 RW/1C/V/P	**PCIeRP1_CO_STS:**

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW/1C/V/P	**PCIeRP0_CO_STS:**
4	0x0 RW/1C/V/P	**Dunit1_CO_STS:**
3	0x0 RW/1C/V/P	**Dunit0_CO_STS:**
2	0x0 RW/1C/V/P	**Bunit_CO_STS:**
1	0x0 RW/1C/V/P	**Aunit_CO_STS:**
0	0x0 RW/1C/V/P	**RCEC_CO_STS:**

45.2.14 GLREG Global Non-Fatal Error Status (GLREG_GNFERRSTS)—Offset 204h

This register indicates that a Non-Fatal Error is reported to the global error logic. An individual error status bit that is set indicates that a particular local device or RCEC has detected an error.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 204h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/1C/V/P	**Reserved:** Reserved.
23	0x0 RW/1C/V/P	**NPK_NF_STS:** NPK Error Status - Not used by the SoC
22	0x0 RW/1C/V/P	**SPIESPI_NF_STS:** SPIESPI Error Status - Not used by the SoC
21	0x0 RW/1C/V/P	**HSUART_NF_STS:** Reserved.
20	0x0 RW/1C/V/P	**SMBUS_NF_STS:** SMBUS Error Status - Not used by the SoC
19	0x0 RW/1C/V/P	**LPC_NF_STS:** LPC Error Status - Not used by the SoC
18	0x0 RW/1C/V/P	**USB_NF_STS:** USB Error Status - Not used by the SoC
17	0x0 RW/1C/V/P	**SATA1_NF_STS:** SATA1 Error Status - Not used by the SoC
16	0x0 RW/1C/V/P	**SATA0_NF_STS:** SATA0 Error Status - Not used by the SoC
15	0x0 RW/1C/V/P	**VRP2_NF_STS:**
14	0x0 RW/1C/V/P	**VRP1_NF_STS:**
13	0x0 RW/1C/V/P	**VRP0_NF_STS:**
12	0x0 RW/1C/V/P	**PCIeRP7_NF_STS:**
11	0x0 RW/1C/V/P	**PCIeRP6_NF_STS:**
10	0x0 RW/1C/V/P	**PCIeRP5_NF_STS:**
9	0x0 RW/1C/V/P	**PCIeRP4_NF_STS:**
8	0x0 RW/1C/V/P	**PCIeRP3_NF_STS:**
7	0x0 RW/1C/V/P	**PCIeRP2_NF_STS:**
6	0x0 RW/1C/V/P	**PCIeRP1_NF_STS:**

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW/1C/V/P	**PCIeRP0_NF_STS:**
4	0x0 RW/1C/V/P	**Dunit1_NF_STS:**
3	0x0 RW/1C/V/P	**Dunit0_NF_STS:**
2	0x0 RW/1C/V/P	**Bunit_NF_STS:**
1	0x0 RW/1C/V/P	**Aunit_NF_STS:**
0	0x0 RW/1C/V/P	**RCEC_NF_STS:**

45.2.15 GLREG Global Fatal Error Status (GLREG_GFAERRSTS)—Offset 208h

This register indicates that a Fatal Error is reported to the global error logic. An individual error status bit that is set indicates that a particular local device or RCEC has detected an error.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 208h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/1C/V/P	**Reserved:** Reserved.
23	0x0 RW/1C/V/P	**NPK_FA_STS:**
22	0x0 RW/1C/V/P	**SPIESPI_FA_STS:**
21	0x0 RW/1C/V/P	**HSUART_FA_STS:**
20	0x0 RW/1C/V/P	**SMBUS_FA_STS:**
19	0x0 RW/1C/V/P	**LPC_FA_STS:**
18	0x0 RW/1C/V/P	**USB_FA_STS:**
17	0x0 RW/1C/V/P	**SATA1_FA_STS:**
16	0x0 RW/1C/V/P	**SATA0_FA_STS:**
15	0x0 RW/1C/V/P	**VRP2_FA_STS:**
14	0x0 RW/1C/V/P	**VRP1_FA_STS:**
13	0x0 RW/1C/V/P	**VRP0_FA_STS:**
12	0x0 RW/1C/V/P	**PCIeRP7_FA_STS:**
11	0x0 RW/1C/V/P	**PCIeRP6_FA_STS:**
10	0x0 RW/1C/V/P	**PCIeRP5_FA_STS:**
9	0x0 RW/1C/V/P	**PCIeRP4_FA_STS:**
8	0x0 RW/1C/V/P	**PCIeRP3_FA_STS:**
7	0x0 RW/1C/V/P	**PCIeRP2_FA_STS:**
6	0x0 RW/1C/V/P	**PCIeRP1_FA_STS:**

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW/1C/V/P	**PCIeRP0_FA_STS:**
4	0x0 RW/1C/V/P	**Dunit1_FA_STS:**
3	0x0 RW/1C/V/P	**Dunit0_FA_STS:**
2	0x0 RW/1C/V/P	**Bunit_FA_STS:**
1	0x0 RW/1C/V/P	**Aunit_FA_STS:**
0	0x0 RW/1C/V/P	**RCEC_FA_STS:**

45.2.16 GLREG Global Error Mask (GLREG_GERRMSK)—Offset 20Ch

This register masks the reporting of errors detected by local devices. An individual error mask bit that is set masks error reporting of the particular local device, software may set or clear the mask bit. This register is sticky and can only be reset by PWRGOOD. Global Error Mask register masks errors reported from the local devices or RCEC to the global register. If the error reporting is masked in this register, all errors from the corresponding local device or RCEC will not set any of the global error status bits.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 20Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/P	**Reserved:** Reserved.
23	0x0 RW/P	**NPK_MSK:** • 1=mask • 0=unmask
22	0x0 RW/P	**SPIESPI_MSK:** • 1=mask • 0=unmask
21	0x0 RW/P	**HSUART_MSK:** • 1=mask • 0=unmask
20	0x0 RW/P	**SMBUS_MSK:** • 1=mask • 0=unmask
19	0x0 RW/P	**LPC_MSK:** • 1=mask • 0=unmask
18	0x0 RW/P	**USB_MSK:** • 1=mask • 0=unmask
17	0x0 RW/P	**SATA1_MSK:** • 1=mask • 0=unmask
16	0x0 RW/P	**SATA0_MSK:** • 1=mask • 0=unmask
15	0x0 RW/P	**VRP2_MSK:** • 1=mask • 0=unmask
14	0x0 RW/P	**VRP1_MSK:** • 1=mask • 0=unmask
13	0x0 RW/P	**VRP0_MSK:** • 1=mask • 0=unmask
12	0x0 RW/P	**PCIeRP7_MSK:** • 1=mask • 0=unmask

Bit Range	Default & Access	Field Name (ID): Description
11	0x0 RW/P	**PCIeRP6_MSK:** • 1=mask • 0=unmask
10	0x0 RW/P	**PCIeRP5_MSK:** • 1=mask • 0=unmask
9	0x0 RW/P	**PCIeRP4_MSK:** • 1=mask • 0=unmask
8	0x0 RW/P	**PCIeRP3_MSK:** • 1=mask • 0=unmask
7	0x0 RW/P	**PCIeRP2_MSK:** • 1=mask • 0=unmask
6	0x0 RW/P	**PCIeRP1_MSK:** • 1=mask • 0=unmask
5	0x0 RW/P	**PCIeRP0_MSK:** • 1=mask • 0=unmask
4	0x0 RW/P	**Dunit1_MSK:** • 1=mask • 0=unmask
3	0x0 RW/P	**Dunit0_MSK:** • 1=mask • 0=unmask
2	0x0 RW/P	**Bunit_MSK:** • 1=mask • 0=unmask
1	0x0 RW/P	**Aunit_MSK:** • 1=mask • 0=unmask
0	0x0 RW/P	**RCEC_MSK:** • 1=mask • 0=unmask

45.2.17 GLREG Global Error Timer (GLREG_GTIME)—Offset 228h

Global Error Timer register is a free running 64-bit counter and will indicate the current value of the 64-bit counter. This counter is reset to 0 by PWRGOOD. Once out of PWRGOOD reset, the counter begins to run.

Type: PCI Configuration Register (Size: 64 bits)

Offset: [B:0, D:4, F:0] + 228h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0x0 RO/V/P	**GTIME_Value:** This is the 64-bit free running counter.

45.2.18 GLREG Global Correctable FERR Error Time Stamp (GLREG_GCOFERRTIME)—Offset 230h

The time stamp register logs the 64-bit free running counter when the first Correctable Error was logged.

Type: PCI Configuration Register (Size: 64 bits)

Offset: [B:0, D:4, F:0] + 230h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0x0 RO/V/P	**G_COFERR_TIME:** The time stamp register logs the 64-bit free running counter when the first Correctable Error was logged.

45.2.19 GLREG Global Nonfatal FERR Error Time Stamp (GLREG_GNFFERRTIME)—Offset 238h

The time stamp register logs the 64-bit free running counter when the first Nonfatal Error was logged.

Type: PCI Configuration Register (Size: 64 bits)

Offset: [B:0, D:4, F:0] + 238h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0x0 RO/V/P	**G_NFFERR_TIME:** The time stamp register logs the 64-bit free running counter when the first Non-Fatal Error was logged.

45.2.20 GLREG Global Fatal FERR Error Time Stamp (GLREG_GFAFERRTIME)—Offset 240h

The time stamp register logs the 64-bit free running counter when the first Fatal Error was logged.

Type: PCI Configuration Register (Size: 64 bits)

Offset: [B:0, D:4, F:0] + 240h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:0	0x0 RO/V/P	**G_FAFERR_TIME:** The time stamp register logs the 64-bit free running counter when the first Fatal Error was logged.

45.2.21 GLREG Global System Event Status (GLREG_GSYSEVTSTS)—Offset 248h

This register indicates the error severity signaled by the global error logic. Setting of an individual error status bit indicates that the corresponding error severity has been detected.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 248h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**Reserved:** Reserved.
2	0x0 RO/V/P	**FA_SYSEV_STS:** A Fatal Error was detected when set
1	0x0 RO/V/P	**NF_SYSEV_STS:** A Nonfatal Error was detected when set
0	0x0 RO/V/P	**CO_SYSEV_STS:** A Correctable Error was detected when set

45.2.22 GLREG Global System Event Mask (GLREG_GSYSEVTMSK)—Offset 24Ch

The System Event Mask register masks the reporting the errors indicated by the system event status register. When set, the error severity does not cause the generation of the system event. When cleared, detection of the error severity generates system event(s) according to System Event Map Register (SYSEVMAP)

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 24Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**Reserved:** Reserved.
2	0x0 RW/P	**FA_SYSEV_M:** Fatal Error System Event Mask • 0 - Unmask system event reporting of the Fatal Error • 1 - Mask system event reporting of the Fatal Error
1	0x0 RW/P	**NF_SYSEV_M:** Nonfatal Error System Event Mask • 0 - Unmask system event reporting of the nonfatal error • 1 - Mask system event reporting of the Nonfatal Error
0	0x0 RW/P	**CO_SYSEV_M:** Correctable Error System Event Mask • 0 - Unmask system event reporting of the Correctable Error • 1 - Mask system event reporting of the Correctable Error

45.2.23 GLREG Global System Event Map (GLREG_GSYSEVTMAP)—Offset 250h

This register maps the error severity detected to one of the system events. When an error is detected, its corresponding error severity determines which system event to generate according to this register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 250h

Default: 00000025h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved:** Reserved.
5:4	0x2 RW/P	**FA_SYSEV_MAP:** • 11: Reserved • 10: Generate NMI • 01: Generate SMI • 00: No system event generation ***Note:*** NMIE.NMI=1 and NSC.SERR#_NMI_enable=1 to generate an NMI.
3:2	0x1 RW/P	**NF_SYSEV_MAP:** • 11: Reserved • 10: Generate NMI • 01: Generate SMI • 00: No system event generation ***Note:*** NMIE.NMI=1 and NSC.SERR#_NMI_enable=1 to generate an NMI.
1:0	0x1 RW/P	**CO_SYSEV_MAP:** • 11: Reserved • 10: Generate NMI • 01: Generate SMI • 00: No system event generation ***Note:*** NMIE.NMI=1 and NSC.SERR#_NMI_enable=1 to generate an NMI.

45.2.24 GLREG Error Pin Control (GLREG_ERRPINCTRL)—Offset 254h

This register provides the option to configure an error pin to either as a special purpose error pin which is asserted based on the detected error severity, or as a general purpose output which is asserted based on the value in the ERRPINDAT. The assertion of the error pins can also be completely disabled by this register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 254h

Default: 00000025h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved:** Reserved.
5:4	0x2 RW/P	**ERR2_ENABLE:** • 11: Reserved. • 10: Assert Error Pin when Fatal Error is set in the system event status reg. • 01: Assert and Deassert Error pin according to Error Pin Data register • 00: Disable Error pin assertion
3:2	0x1 RW/P	**ERR1_ENABLE:** • 11: Reserved. • 10: Assert Error Pin when Non-Fatal Error is set in the system event status reg. • 01: Assert and Deassert Error pin according to Error Pin Data register • 00: Disable Error pin assertion
1:0	0x1 RW/P	**ERR0_ENABLE:** • 11: Reserved. • 10: Assert Error Pin when Correctable Error is set in the system event status reg. • 01: Assert and Deassert Error pin according to Error Pin Data register • 00: Disable Error pin assertion

45.2.25 GLREG Error Pin Status (GLREG_ERRPINSTS)—Offset 258h

This register reflects the state of the error pin assertion. The status bit of the corresponding error pin is set upon the deassertion to assertion transition of the error pin.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 258h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**Reserved:** Reserved.
2	0x0 RW/1C/V/P	**ERR2_STS:** This bit is set upon the transition of deassertion to assertion of the Error pin. Software writes '1' to clear the status.
1	0x0 RW/1C/V/P	**ERR1_STS:** This bit is set upon the transition of deassertion to assertion of the Error pin. Software writes '1' to clear the status.
0	0x0 RW/1C/V/P	**ERR0_STS:** This bit is set upon the transition of deassertion to assertion of the Error pin. Software writes '1' to clear the status.

45.2.26 GLREG Error Pin Data (GLREG_ERRPINDATA)—Offset 25Ch

This register provides the data value when the error pin is configured as a general purpose output.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:4, F:0] + 25Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**Reserved:** Reserved.
2	0x0 RW	**ERR2_PINDATA:** (applies when ERRPINCTL[5:4]=01, otherwise reserved) This bit acts as the general purpose output for the ERR[2] pin. ERR [2] pin value will follow the value programmed in ERR[2] Pin Data register. • 0 - Deassert ERR[2] pin • 1 - Assert ERR[2] pin
1	0x0 RW	**ERR1_PINDATA:** (applies when ERRPINCTL[3:2]=01, otherwise reserved). This bit acts as the general purpose output for the ERR[1] pin. ERR [1] pin value will follow the value programmed in ERR[1] Pin Data register. • 0 - Deassert ERR[1] pin • 1 - Assert ERR[1] pin
0	0x0 RW	**ERR0_PINDATA:** (applies when ERRPINCNTL[1:0]=01, otherwise reserved). This bit acts as the general purpose output for the ERR[0] pin. Error [0] pin value will follow the value programmed in ERR[0] Pin Data register. • 0 - Deassert ERR[0] pin • 1 - Assert ERR[0] pin

45.2.27 GLREG Uncorrectable Error Counter (GLREG_LUNCERRCNT)—Offset 294h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:4, F:0] + 294h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1C/V/P	**ERR_OVF:** • 0: No overflow occurred • 1: Error overflow. The error count may not be valid.
6:0	0x0 RW/1C/V/P	**ERRCNT:** This counter accumulates errors that occur when the associated error type is selected in the FNBERRCNTSEL register. This field is cleared by writing 7Fh. Maximum counter available is 127d (7Fh). ***Note:*** Single bit write clears the corresponding bit.

§ §

46 Root Complex Event Collector - B0, D5, F0

46.1 Introduction and Index

The host-accessible registers for the Root Complex Event Collector (RCEC) are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

46.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 5 (decimal), Function 0. The offset addresses are listed.

Table 46-1. Summary of PCI Configuration Registers—0/5/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"RCEC Vendor ID (RCEC_VID)—Offset 0h" on page 1509
4	2	0000	"RCEC PCI Command (RCEC_PCICMD)—Offset 4h" on page 1510
6	2	0010	"RCEC PCI Status (RCEC_PCISTS)—Offset 6h" on page 1511
9	3	00080700	"RCEC Class Code (RCEC_CC)—Offset 9h" on page 1512
C	2	00	"RCEC Cacheline Size (RCEC_CLS)—Offset Ch" on page 1512
3D	3	01	"RCEC Interrupt Pin (RCEC_INTP)—Offset 3Dh" on page 1513
40	2	8010	"RCEC PCI Express Capability List (RCEC_EXPCAPLST)—Offset 40h" on page 1513
42	2	00A2	"RCEC PCI Express Capability List (RCEC_EXPCAPLST)—Offset 40h" on page 1513
48	2	0000	"RCEC Device Control (RCEC_DEVCTL)—Offset 48h" on page 1515
4A	1	00	"RCEC Device Status (RCEC_DEVSTS)—Offset 4Ah" on page 1516
5C	2	00	"RCEC Root Control (RCEC_ROOTCTL)—Offset 5Ch" on page 1517
82	2	C803	"RCEC Power Management Capabilities (RCEC_PMCAP)—Offset 82h" on page 1518
84	2	0000	"RCEC Power Management Control / Status (RCEC_PMCSR)—Offset 84h" on page 1518
90	2	0005	"RCEC MSI Capability List (RCEC_MSICAPLST)—Offset 90h" on page 1519
92	2	0100	"RCEC MSI Message Control (RCEC_MSICTL)—Offset 92h" on page 1519
94	4	00000000	"RCEC MSI Message Address (RCEC_MSIADDR)—Offset 94h" on page 1520
98	2	0000	"RCEC MSI Message Data (RCEC_MSIDATA)—Offset 98h" on page 1520
9C	4	00000000	"RCEC MSI Mask Bit (RCEC_MSIMSK)—Offset 9Ch" on page 1521
A0	2	0000	"RCEC MSI Pending Bit (RCEC_MSIPENDING)—Offset A0h" on page 1521
100	4	15010001	"RCEC Advanced Error Reporting Extended Capability Header (RCEC_AERCAPHDR)—Offset 100h" on page 1521
104	4	00000000	"RCEC Uncorrectable Error Status (RCEC_ERRUNCSTS)—Offset 104h" on page 1522
110	2	0000	"RCEC Correctable Error Status (RCEC_ERRCORSTS)—Offset 110h" on page 1523
114	2	E000	"RCEC Correctable Error Mask (RCEC_ERRCORMSK)—Offset 114h" on page 1524
118	2	0000	"RCEC Advanced Error Capabilities and Control (RCEC_AERCAPCTL)—Offset 118h" on page 1525
11C	4	00000000	"RCEC Header Log (RCEC_AERHDRLOG1)—Offset 11Ch" on page 1525
120	4	00000000	"RCEC Header Log (RCEC_AERHDRLOG2)—Offset 120h" on page 1526
124	4	00000000	"RCEC Header Log (RCEC_AERHDRLOG3)—Offset 124h" on page 1526
128	4	00000000	"RCEC Header Log (RCEC_AERHDRLOG4)—Offset 128h" on page 1526
12C	1	00	"RCEC Root Error Command (RCEC_ROOTERRCMD)—Offset 12Ch" on page 1527
130	4	00000000	"RCEC Root Error Status (RCEC_ROOTERRSTS)—Offset 130h" on page 1528
134	4	00000000	"RCEC Error Source Identification (RCEC_ERRSRCID)—Offset 134h" on page 1529

46.2 Registers in Configuration Space

46.2.1 RCEC Vendor ID (RCEC_VID)—Offset 0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**VID:** This field identifies Intel as the manufacturer of the device.

46.2.2 RCEC PCI Command (RCEC_PCICMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved:** Reserved.
10	0x0 RW	**INTxD:** This bit controls the ability of the PCI-Express Function to generate INTx interrupt message. When set, functions are prevented from asserting INTx interrupt messages. Any INTx emulation interrupts already asserted by the function must be deserted when this bit is set by generating a Deassert_INTx message(s).
9	0x0 RO	**FBE:** Not applicable to PCI-Express. Hardwired to 0.
8	0x0 RW	**SEE:** (SERR Enable) When set, this bit enables reporting of Non-Fatal and Fatal Errors detected by the Function of the Root Complex. ERR_COR messages are not affected by this bit. Errors are reported when enabled either through this bit or through the PCI Express-specific bits in the Device Control Register (RCEC_DEVCTL).
7	0x0 RO	**WCC:** Not applicable to PCI-Express. Hardwired to 0.
6	0x0 RW	**PERE:** This bit controls the setting of the master data parity error bit in the Status Register (RCEC_PCISTS) in response to a parity error received on the PCI Express interface (poisoned TLP).
5	0x0 RO	**VGA_PSE:** Not applicable to PCI-Express. Hardwired to 0.
4	0x0 RO	**MWIE:** Not applicable to PCI-Express. Hardwired to 0.
3	0x0 RO	**SCE:** Not applicable to PCI-Express. Hardwired to 0.
2	0x0 RW	**BME:** This bit controls the ability of the Function to issue Memory and I/O read or write requests, and the ability of Root or Switch port to forward memory and I/O read or write requests in the upstream direction. MSI interrupts are inband memory writes and are blocked when this bit is 0b.
1	0x0 RO	**MSE:** This bit controls the function's response to Memory Space accesses. When this bit is 0b, the function will handle memory transactions targeting the Function as an Unsupported Request (UR).
0	0x0 RO	**IOSE:** This bit controls the function's response to IO Space accesses. When this bit is 0b, the function will handle memory transactions targeting the Function as an Unsupported Request (UR).

46.2.3 RCEC PCI Status (RCEC_PCISTS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**DPE:** This bit is set when a poisoned TLP is received. This bit is set even when the parity error response enable, bit 6 of the PCICMD Register (RCEC_PCICMD) is not set.
14	0x0 RW/1C/V	**SSE:** This bit is set when ERR_FATAL or ERR_NONFATAL messages are sent to the root complex event collector and the SERR enable bit in the PCICMD Register (RCEC_PCICMD) is set.
13	0x0 RO	**RMA:** This bit is set when the requester receives a completion with an UR completion status.
12	0x0 RO	**RTA:** This bit is set when a requester receives a CA completions status.
11	0x0 RO	**STA:** This bit is set when the switch generates a completion packet with Completer Abort (CA) status is generated by its primary side.
10:9	0x0 RO	**DVT:** These bits have no meaning on PCI Express. Fast decode timing is reported.
8	0x0 RO	**MDPD:** This bit is set by a requester (primary side for type1 configuration header functions) if the parity error response enable bit (PERE) in the Command Register (RCEC_PCICMD) is set and either of the following two conditions occur: • Requester receives a completion marked poisoned. • Requester poisons a write requests. If the parity error bit is 0b, this bit is never set.
7	0x0 RO	**FBC:** This bit has no meaning on PCI Express.
6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**C66:** This bit has no meaning on PCI Express.
4	0x1 RO	**CAPE:** This bit indicates the presence of an Extended capabilities list items.
3	0x0 RO/V	**INTS:** When set, this bit indicates that an INTx emulation interrupt is pending internally in this function.
2:0	0x0 RO	**RSVD1:** Reserved

46.2.4 RCEC Class Code (RCEC_CC)—Offset 9h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 9h

Default: 00080700h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x8 RW/O	**BC:** Root Complex Event Collector
15:8	0x7 RW/O	**SC:** Root Complex Event Collector
7:0	0x0 RW/O	**RLPI:** Reserved.

46.2.5 RCEC Cacheline Size (RCEC_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:5, F:0] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**CLS:** These bits specify the system cache-line size in units of DWords. This field is implemented by PCI Express devices but has no effect on device behavior.

46.2.6 RCEC Interrupt Pin (RCEC_INTP)—Offset 3Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:5, F:0] + 3Dh

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RO	**INTP:** This register tells which interrupt pin the function uses. • 01h: Generate INTA • 02h: Generate INTB • 03h: Generate INTC • 04h: Generate INTD • Others: Reserved Devices (or device functions) that do not use an interrupt pin must put a 0 in this register. As a single function device, this device specifies INTA as its interrupt pin.

46.2.7 RCEC PCI Express Capability List (RCEC_EXPCAPLST)—Offset 40h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 40h

Default: 8010h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x80 RO	**NP:** Contains the offset of the next item in the capabilities list (RCEC_PMCAPLST).
7:0	0x10 RO	**CAPID:** Identifies the function as PCI Express capable.

46.2.8 RCEC PCI Express Capabilities (RCEC_EXPCAP)—Offset 42h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 42h

Default: 00A2h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**RSVD0:** Reserved
13:9	0x0 RO	**IMN:** This field indicates the interrupt message number that is generated from the PCI Express port.
8	0x0 RO	**SI:** Indicates the PCI Express link associated with this port is connected to a slot.
7:4	0xa RO	**DT:** 1010b Root Complex Event Collector
3:0	0x2 RO	**VN:** These bits indicate the version number of the PCI Express capability structure.

46.2.9 RCEC Device Control (RCEC_DEVCTL)—Offset 48h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 48h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RO	**MRRS:** This field sets the maximum Read Requests size for the function as a requester. The Function must not generate read requests with size exceeding the set value. • 000b: 128 bytes maximum Read Request size • 001b: 256 bytes maximum Read Request size • 010b: 512 bytes maximum Read Request size • 011b: 1024 bytes maximum Read Request size • 100b: 2048 bytes maximum Read Request size • 101b: 4096 bytes maximum Read Request size • Others: Reserved Functions that do not generate Read Requests larger than 128B and functions that do not generate Read Requests on their own behalf are permitted to implement this field as Read Only (RO) with a value of 000b.
11	0x0 RO	**Reserved:** Reserved
10	0x0 RO	**AUXPME:** Not supported
9	0x0 RO	**Reserved:** Reserved
8	0x0 RO	**ETFE:** When set, this bit enables a function to use an 8-bit tag field as a Requester.
7:5	0x0 RW	**MPS:** This field sets maximum TLP payload size for the function. As a receiver, the function must handle TLPs as larger as the set value. As a Transmitter, the function must not generate TLPs exceeding the set value. • 000b: 128 bytes maximum payload size • 001b: 256 bytes maximum payload size • 010b: 512 bytes maximum payload size (Unsupported) • 011b: 1024 bytes maximum payload size (Unsupported) • 100b: 2048 bytes maximum payload size (Unsupported) • 101b: 4096 bytes maximum payload size (Unsupported) • Others: Reserved
4	0x0 RO	**ENRO:** When set, the function is permitted to set the relaxed ordering bit in the attribute field of transactions it initiates that do not require strong write ordering.
3	0x0 RW	**URRE:** This bit controls the enabling of ERR_CORR, ERR_NONFATAL or ERR_FATAL messages on PCI Express for reporting Unsupported Request (UR) errors.
2	0x0 RW	**FERE:** When this bit is set, generation of the ERR_FATAL message is enabled.
1	0x0 RW	**NFERE:** When this bit is set, generation of the ERR_NONFATAL message is enabled.
0	0x0 RW	**CERE:** When this bit is set, generation of the ERR_CORR message is enabled.

46.2.10 RCEC Device Status (RCEC_DEVSTS)—Offset 4Ah

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:5, F:0] + 4Ah

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**Reserved:** Reserved
4	0x0 RO	**APD:** Auxiliary Power is not supported.
3	0x0 RW/1C/V	**URD:** This bit indicates that the device received an Unsupported Request (UR). Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control Register.
2	0x0 RW/1C/V	**FED:** This bit indicates status of Fatal Errors detected. Errors are logged in this register regardless of the settings of the Correctable Error mask register.
1	0x0 RW/1C/V	**NFED:** This bit indicates status of Non-Fatal Errors detected.
0	0x0 RW/1C/V	**CED:** This bit indicates status of Correctable Errors detected.

46.2.11 RCEC Root Control (RCEC_ROOTCTL)—Offset 5Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:5, F:0] + 5Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**RSVD0:** Reserved
4	0x0 RO	**CRSSVE:** This bit, when set, enables the Root Port to return Configuration Retry Status (CRS) Completion status to software. • 1: Enable software to received a CRS status. This allows software to make the decision to re-issue the configuration request or move on and re-issue the request at a later time. • 0: Disable software from receiving a CRS response. The PCI-E will wait and re-issue the configuration request until it receives a response other than CRS without notifying software.
3	0x0 RO	**PMEIE:** This field controls the generation of interrupts for PME messages. • 1: Enables interrupt generation upon receipt of a PME message as reflected in the PME Status bit defined in the ROOTSTS register. A PME interrupt is generated if the PMESTATUS register bit is set when this bit is set from a cleared state. • 0: Disables interrupt generation for PME messages.
2	0x0 RW	**SEFEE:** This field controls generation of system errors in the PCI-Express root Complex Event Collector for Fatal Errors. • 1: indicates that a System Error should be generated if a Fatal Error (ERR_FATAL) is reported by any of the devices associated with and including this PCI-Express root complex event collector. • 0: No System Error should be generated on a Fatal Error (ERR_FATAL) reported by any of the devices associated with and including this PCI-Express root complex event collector.
1	0x0 RW	**SENFEE:** This field controls generation of system errors in the PCI-Express root Complex Event Collector for Non-Fatal Errors. • 1: indicates that a System Error should be generated if a Non-Fatal Error (ERR_NONFATAL) is reported by any of the devices associated with and including this PCI-Express root complex event collector. • 0: No System Error should be generated on a Non-Fatal Error (ERR_NONFATAL) reported by any of the devices associated with and including this PCI-Express root complex event collector.
0	0x0 RW	**SECEE:** This field controls generation of system errors in the PCI-Express root Complex Event Collector for Correctable Errors. • 1: indicates that a System Error should be generated if a Correctable Error (ERR_COR) is reported by any of the devices associated with and including this PCI-Express root complex event collector • 0: No System Error should be generated on a Correctable Error (ERR_COR) reported by any of the devices associated with and including this PCI-Express root complex event collector.

46.2.12 RCEC Power Management Capabilities (RCEC_PMCAP)—Offset 82h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 82h

Default: C803h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x19 RO	**PMESUP:** PME assertion is supported when in D3hot. PME assertion from D3cold is not supported.
10	0x0 RO	**D2S:** Not supported
9	0x0 RO	**D1S:** Not supported
8:6	0x0 RO	**AC:** Auxiliary power is not supported.
5	0x0 RO	**DSI:** Device-specific initialization is not required when transitioning to D0 from D3hot state. This bit is zero.
4	0x0 RO	**RSVD0:** Reserved
3	0x0 RO	**PMECLK:** Does not apply to PCI Express. Hard-wired to 0.
2:0	0x3 RO	**VER:** PM implementation is compliant with PCI Bus Power Management Interface Specification, Revision 11 1.2.

46.2.13 RCEC Power Management Control / Status (RCEC_PMCSR)—Offset 84h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 84h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V/P	**PMESTS:** Reserved.
14:13	0x0 RO	**DC:** Not supported
12:9	0x0 RO	**DS:** Not supported
8	0x0 RW/P	**PMEEN:** Gates assertion of the PME message.
7:2	0x0 RO	**RSVD0:** Reserved
1:0	0x0 RW/V	**PS:** This field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the supported values is given below: • 0h - D0 • 3h - D3hot

46.2.14 RCEC MSI Capability List (RCEC_MSICAPLST)—Offset 90h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 90h

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**NP:** Contains the offset of the next item in the capabilities list. A null value is used to indicate that this is the last capability.
7:0	0x5 RO	**CAPID:** Identifies the function as MSI capable.

46.2.15 RCEC MSI Message Control (RCEC_MSICTL)—Offset 92h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 92h

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved
8	0x1 RO	**PVM:** This bit indicates that this device supports MSI per-vector masking.
7	0x0 RO	**AD64C:** When set, this bit indicates that the function is capable of generating a 64-bit message address.
6:4	0x0 RW	**MMEN:** Only one message is supported. These bits are R/W for software compatibility.
3:1	0x0 RO	**MMC:** Only one message is supported.
0	0x0 RW	**MSIE:** When set, MSI is enabled and traditional interrupt pins are not used to generate interrupts.

46.2.16 RCEC MSI Message Address (RCEC_MSIADDR)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address:** Message address specified by the system, always DWORD aligned
1:0	0x0 RO	**Reserved:** Reserved.

46.2.17 RCEC MSI Message Data (RCEC_MSIDATA)—Offset 98h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**TM:** • 0: Edge Triggered • 1: Level Triggered
14	0x0 RW	**LVL:** if TM is 0h, then this field is a don't care. Edge triggered messages are always treated as assert messages. For level triggered interrupts, this bit reflects the state of the interrupt input if TM is 1h, then: • 0: Deassert Messages • 1: Assert Messages
13:12	0x0 RW	**Reserved:** Reserved
11:8	0x0 RW	**DM:** • 0000: Fixed: Trigger Mode can be edge or level. • 0001: Lowest Priority: Trigger Mode can be edge or level. • 0010: SMI/PMI/MCA - Not supported via MSI of root port • 0011: Reserved - Not supported via MSI of root port • 0100: NMI - Not supported via MSI of root port • 0101: INIT - Not supported via MSI of root port • 0110: Reserved • 0111: ExtINT - Not supported via MSI of primary port • 1000 -1111: Reserved
7:0	0x0 RW	**Reserved:** Reserved

46.2.18 RCEC MSI Mask Bit (RCEC_MSIMSK)—Offset 9Ch

The MSI Mask Bit register enables software to disable message sending on a per-vector basis.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RW	**MSKB:** For each Mask bit that is set, the device is prohibited from sending the associated message. Corresponding bits are masked if set to '1'

46.2.19 RCEC MSI Pending Bit (RCEC_MSIPENDING)—Offset A0h

The Mask Pending register enables software to defer message sending on a per-vector basis.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + A0h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RO/V	**PB:** For each Pending bit that is set, the device has a pending associated message. Corresponding bits are pending if set to '1'

46.2.20 RCEC Advanced Error Reporting Extended Capability Header (RCEC_AERCAPHDR)—Offset 100h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 100h

Default: 15010001h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x150 RO	**NCO:** Contains the offset of the next structure in the Extended Capabilities list (RCEC_RCECEPACAPHDR).
19:16	0x1 RO	**CV:** Indicates the version of the Capability structure present.
15:0	0x1 RO	**EXCAPID:** Identifies the function as Advanced Error Reporting (AER) capable.

46.2.21 RCEC Uncorrectable Error Status (RCEC_ERRUNCSTS)—Offset 104h

This register reports the error status of individual Uncorrectable Error sources. An individual error status bit that is set to 1 indicates that a particular error occurred. Software can clear an error status by writing a 1 to the respective bit.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 104h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x0 RW/1C/V/P	**UIE:** This bit is set whenever an IEH Uncorrectable Internal Error as defined in IEH_UNCERRSTS is detected.
21	0x0 RO	**RSVD1:** Reserved
20	0x0 RW/1C/V/P	**URE:** As a receiver, Set whenever an Unsupported Request (negatively-decoded transaction) is detected. The Header is logged.
19	0x0 RO	**RSVD2:** Reserved
18	0x0 RW/1C/V/P	**MalformedTLP:** As a receiver, set whenever a malformed TLP (Length not equal to 000000001b for config requests) is detected. The Header is logged.
17	0x0 RO	**RSVD3:** Reserved
16	0x0 RW/1C/V/P	**UnexpectedCompletion:** As a receiver, set whenever a completion is received that does not match the requestor ID or outstanding Tag. The Header is logged.
15:0	0x0 RO	**RSVD4:** Reserved

46.2.22 RCEC Correctable Error Status (RCEC_ERRCORSTS)—Offset 110h

This register reports the error status of individual Correctable Error sources on a PCI Express device. An individual error status bit set to 1 indicates that a particular error has occurred. Software can clear the error status by writing a 1 to the respective bit.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 110h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**HLOE:** Reserved.
14	0x0 RO	**CIE:** Reserved.
13	0x0 RW/1C/V/P	**ANFE:** Reserved.
12	0x0 RO	**RTTE:** The PCI-E sets this bit when replay timer time-out occurs.
11:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RO	**RNRE:** The PCI-E sets this bit when the replay number rolls over from 11 to 00.
7	0x0 RO	**BDLLPE:** The switch sets this bit on CRC errors on DLLP.
6	0x0 RO	**BTLPE:** The switch sets this bit on CRC errors on TLP.
5:1	0x0 RO	**RSVD1:** Reserved
0	0x0 RO	**RE:** The PCI-E sets this bit when the physical layer detects a receiver error.

46.2.23 RCEC Correctable Error Mask (RCEC_ERRCORMSK)—Offset 114h

This register controls the reporting of individual Correctable Errors via ERR_COR message. A masked error (respective bit set in mask register) is not reported to the host bridge by the switch. There is a mask bit corresponding to every bit in the Correctable Error Status Register.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 114h

Default: E000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x1 RO	**HLOEM:** Reserved.
14	0x1 RO	**CIEM:** Reserved.
13	0x1 RW/P	**ANFEM:** This bit is set by default to enable compatibility with software that does not comprehend Role-Based Error Reporting.
12	0x0 RO	**RTTEM:** Reserved.
11:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RO	**RNREM:** Reserved.
7	0x0 RO	**BDLLPEM:** Reserved.
6	0x0 RO	**BTLPEM:** Reserved.
5:1	0x0 RO	**RSVD1:** Reserved
0	0x0 RO	**REM:** Reserved.

46.2.24 RCEC Advanced Error Capabilities and Control (RCEC_AERCAPCTL)—Offset 118h

This register gives the status and control for ECRC checks and also the pointer to the first Uncorrectable Error that happened.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:5, F:0] + 118h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**MHRE:** When set, this bit enables the function to record more than one error header.
9	0x0 RO	**MHRC:** Supports more than one error header.
8	0x0 RO	**ECE:** Not supported. Hard-wired to 0
7	0x0 RO	**ECC:** Not supported. Hard-wired to 0
6	0x0 RO	**EGE:** Not supported. Hard-wired to 0
5	0x0 RO	**EGC:** Not supported. Hard-wired to 0
4:0	0x0 RO/V/P	**FEP:** This field identifies the bit position of the first error reported in the Uncorrectable Error Status Register. This register re-arms itself (which does not change its current value) as soon as the error status bit indicated by the pointer is cleared by the software by writing a 1 to that status bit.

46.2.25 RCEC Header Log (RCEC_AERHDRLOG1)—Offset 11Ch

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 11Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLPHDRLOG:** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

46.2.26 RCEC Header Log (RCEC_AERHDRLOG2)—Offset 120h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLPHDRLOG:** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

46.2.27 RCEC Header Log (RCEC_AERHDRLOG3)—Offset 124h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLPHDRLOG:** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

46.2.28 RCEC Header Log (RCEC_AERHDRLOG4)—Offset 128h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 128h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLPHDRLOG:** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

46.2.29 RCEC Root Error Command (RCEC_ROOTERRCMD)—Offset 12Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:5, F:0] + 12Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**FERE:** When set, this bit enables the generation of an interrupt when a Fatal Error is reported by any of the functions in the hierarchy associated with this Root Port.
1	0x0 RW	**NFERE:** When set, this bit enables the generation of an interrupt when a Non-Fatal Error is reported by any of the functions in the hierarchy associated with this Root Port.
0	0x0 RW	**CERE:** When set, this bit enables the generation of an interrupt when a Correctable Error is reported by any of the functions in the hierarchy associated with this Root Port.

46.2.30 RCEC Root Error Status (RCEC_ROOTERRSTS)—Offset 130h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 130h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**AEMN:** This register indicates which MSI/MSI-X vector is used for the interrupt message generated in association with any of the status bits of this Capability. For MSI, the value in this register indicates the offset between the base Message Data and the interrupt message that is generated. Hardware is required to update this field so that it is correct if the number of MSI Messages assigned to the Function changes when software writes to the Multiple Message Enable field in the MSI Message Control register. For MSI-X, the value in this register indicates which MSI-X Table entry is used to generate the interrupt message. The entry must be one of the first 32 entries even if the Function implements more than 32 entries. For a given MSI-X implementation, the entry must remain constant. • If both MSI and MSI-X are implemented, they are permitted to use different vectors, though software is permitted to enable only one mechanism at a time. If software enables both MSI and MSI-X at the same time, the value in this register is undefined. • If MSI-X is enabled, the value in this register must indicate the vector for MSI-X. • If MSI is enabled or neither is enabled, the value in this register must indicate the vector for MSI.
26:7	0x0 RO	**RSVD0:** Reserved
6	0x0 RW/1C/V/P	**FEMR:** Set when one or more Fatal Uncorrectable Error Messages have been received.
5	0x0 RW/1C/V/P	**NFEMR:** Set when one or more Non-Fatal Uncorrectable Error Messages have been received.
4	0x0 RW/1C/V/P	**FUF:** Set when the first Uncorrectable Error Message or PCI_error Message received is for a Fatal Error.
3	0x0 RW/1C/V/P	**MEFR:** Set when either a Fatal or a Non-Fatal Error is received and ERR_FATAL/NONFATAL Received is already Set.
2	0x0 RW/1C/V/P	**EFR:** Set when a Fatal or a Non-Fatal Error Message is received and this bit is not already Set.
1	0x0 RW/1C/V/P	**MCER:** Set when a Correctable Error Message is received and ERR_COR Received is already Set.
0	0x0 RW/1C/V/P	**CER:** Set when a Correctable Error Message is received and this bit is not already Set.

46.2.31 RCEC Error Source Identification (RCEC_ERRSRCID)—Offset 134h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:5, F:0] + 134h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO/V/P	**EFSID:** Requester ID of the source when a Fatal or Non-Fatal Error is received and the Fatal Error Message Received (FEMR) or Non-Fatal Error Message Received (NFEMR) bit is not already set.
15:0	0x0 RO/V/P	**ECSID:** Requester ID of the source when a Correctable Error is received and the Correctable Error Received (CER) bit is not already set.

§ §

47 RP - Intel® QuickAssist Technology - B0, D6/D22/D23, F0

47.1 Introduction and Index

The host-accessible registers for the "Virtual Root Port" (vRP) dedicated to the Intel® QuickAssist Technology Controller are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The SoC also contains a vRP (Device 22) dedicated to LAN Controller 0 and another vRP (Device 23) dedicated to LAN Controller 1.

The registers shown in this chapter apply to vRP Device 6 as well as vRP Devices 22 and 23. Register information unique to a device is explained in the register and bit field descriptions.

The legend for the register access codes are described in Chapter 43, "Introduction."

47.1.1 Host Configuration Space

These Virtual Root Port (vRP) registers are discovered in Host Configuration Space starting at:

- Bus 0, Device 6, Function 0 for the vRP of the Intel® QuickAssist Technology Controller
- Bus 0, Device 22 (decimal), Function 0 for the vRP of LAN Controller 0
- Bus 0, Device 23 (decimal), Function 0 for the vRP of LAN Controller 1

Table 47-1. Summary of PCI Configuration Registers—0/6/0, 0/22/0, and 0/23/0 (Sheet 1 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"VID—Offset 0h" on page 1534
2	2	See register	"DID—Offset 2h" on page 1534
4	2	0000	"PCICMD—Offset 4h" on page 1535
6	2	0010	"PCISTS—Offset 6h" on page 1536
9	3	00060400	"CCR—Offset 9h" on page 1537
C	1	00	"CLS—Offset Ch" on page 1537
1C	1	00	"IOBASE—Offset 1Ch" on page 1538
1D	1	00	"IOLIMIT—Offset 1Dh" on page 1538
20	2	0000	"MEMBASE—Offset 20h" on page 1539
22	2	0000	"MEMLIMIT—Offset 22h" on page 1540
24	2	0001	"PFBASE—Offset 24h" on page 1541
26	2	0001	"PFLIMIT—Offset 26h" on page 1542
28	4	00000000	"PFBASEU—Offset 28h" on page 1542
2C	4	00000000	"PFLIMITU—Offset 2Ch" on page 1543
34	1	40	"CAPPTR—Offset 34h" on page 1543
3C	1	00	"INTL—Offset 3Ch" on page 1544
3D	1	01	"INTP—Offset 3Dh" on page 1544
3E	2	0000	"BCTL—Offset 3Eh" on page 1544
40	2	8010	"EXPCAPLST—Offset 40h" on page 1546
42	2	0042	"EXPCAP—Offset 42h" on page 1547
44	4	00008001	"DEVCAP—Offset 44h" on page 1548
48	2	2000	"DEVCTL—Offset 48h" on page 1549
4A	2	0000	"DEVSTS—Offset 4Ah" on page 1550
4C	4	See register	"LINKCAP—Offset 4Ch" on page 1551
50	2	0000	"LINKCTL—Offset 50h" on page 1553
52	2	1011	"LINKSTS—Offset 52h" on page 1554
5A	2	0040	"SLOTSTS—Offset 5Ah" on page 1555
5C	2	0000	"ROOTCTL—Offset 5Ch" on page 1556
5E	2	0001	"ROOTCAP—Offset 5Eh" on page 1557
60	4	00000000	"ROOTSTS—Offset 60h" on page 1557
64	4	00000020	"DEVCAP2—Offset 64h" on page 1558
68	2	0000	"DEVCTL2—Offset 68h" on page 1560

Table 47-1. Summary of PCI Configuration Registers—0/6/0, 0/22/0, and 0/23/0 (Sheet 2 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
6C	4	00000002	"LINKCAP2—Offset 6Ch" on page 1561
70	2	0001	"LINKCTL2—Offset 70h" on page 1562
72	2	0000	"LINKSTS2—Offset 72h" on page 1564
80	2	8801	"PMCAPLST—Offset 80h" on page 1564
82	2	C803	"PMCAPLST—Offset 80h" on page 1564
84	2	0008	"PMCSR—Offset 84h" on page 1566
86	2	00	"PMBSE—Offset 86h" on page 1566
88	2	900D	"SSCAPLST—Offset 88h" on page 1567
8C	2	8086	"SSVID—Offset 8Ch" on page 1568
8E	2	0000	"SSID—Offset 8Eh" on page 1568
90	2	0005	"MSICAPLST—Offset 90h" on page 1569
92	2	0100	"MSICTL—Offset 92h" on page 1569
94	4	00000000	"MSIADDR—Offset 94h" on page 1570
98	4	00000000	"MSIDATA—Offset 98h" on page 1570
9C	4	00000000	"MSIMSK—Offset 9Ch" on page 1571
A0	4	00000000	"MSIPENDING—Offset A0h" on page 1571
A8	4	00000000	"RPPMCSR—Offset A8h" on page 1572
B0	2	0000	"PMCSRS—Offset B0h" on page 1572
C8	4	00000000	"SMICSR—Offset C8h" on page 1573
CC	4	00000000	"SCICSR—Offset CCh" on page 1573
D8	4	00000000	"PBTXNCTL—Offset D8h" on page 1574
EA	2	0000	"PLKCTL—Offset EAh" on page 1574
EC	4	00000000	"LTRCSR—Offset ECh" on page 1575
F0	4	00000000	"LTRL—Offset F0h" on page 1576
F4	4	00000000	"LTROVR—Offset F4h" on page 1577
F8	1	00	"INTXSWZCTL—Offset F8h" on page 1578
118	4	00000000	"AERCAPCTL—Offset 118h" on page 1579
11C	4	00000000	"AERHDRLOG1—Offset 11Ch" on page 1579
120	4	00000000	"AERHDRLOG2—Offset 120h" on page 1580
124	4	00000000	"AERHDRLOG3—Offset 124h" on page 1580
128	4	00000000	"AERHDRLOG4—Offset 128h" on page 1580
12C	4	00000000	"ROOTERRCMD—Offset 12Ch" on page 1581
130	4	00000000	"ROOTERRSTS—Offset 130h" on page 1581
134	4	00000000	"ERRSRCID—Offset 134h" on page 1582
138	4	0001000D	"ACSCAPHDR—Offset 138h" on page 1582
13C	2	005F	"ACSCAPHDR—Offset 138h" on page 1582
13E	2	0000	"ACSCTL—Offset 13Eh" on page 1584
2DC	4	00008000	"XPTDEF—Offset 2DCh" on page 1585
2E0	4	00001D00	"XPTDEF2—Offset 2E0h" on page 1587

Table 47-1. Summary of PCI Configuration Registers—0/6/0, 0/22/0, and 0/23/0 (Sheet 3 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
2E4	2	0010	"IOSFDEVCLKGCTL—Offset 2E4h" on page 1589
2E6	2	8010	"SBDEVCLKGCTL—Offset 2E6h" on page 1589
2E8	2	0010	"IDFDEVCLKGCTL—Offset 2E8h" on page 1590

47.2 Registers in Configuration Space

47.2.1 VID—Offset 0h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 0h
Offset: [B:0, D:22, F:0] + 0h
Offset: [B:0, D:23, F:0] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**Vendor ID (VID):** This field identifies Intel as the manufacturer of the device.

47.2.2 DID—Offset 2h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 2h
Offset: [B:0, D:22, F:0] + 2h
Offset: [B:0, D:23, F:0] + 2h

Default: 19A3h for D6
Default: 19D1h for D22
Default: 19D2h for D23

Bit Range	Default & Access	Field Name (ID): Description
15:0	D6: 0x19A3 D22: 0x19D1 D23: 0x19D2 RO/V	**Device ID (DID):** This field identifies the particular function as allocated by Intel.

47.2.3 PCICMD—Offset 4h

This register controls how the device behaves on the primary interface (PCI Express).

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 4h
Offset: [B:0, D:22, F:0] + 4h
Offset: [B:0, D:23, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RW	**Interrupt Disable (INTxD):** This bit controls the ability of the PCI-Express Function to generate legacy INTx interrupt message. When set, functions are prevented from asserting INTx interrupt messages. Any INTx emulation interrupts already asserted by the function must be deasserted when this bit is set by generating a Deassert_INTx message(s).
9	0x0 RO	**Fast Back-to-back enable (FBE):** Not applicable to PCI-Express. Hardwired to 0.
8	0x0 RW	**SERR# Enable (SEE):** When set, this bit enables reporting of Non-Fatal and Fatal errors detected by the Function of the Root Complex.
7	0x0 RO	**Wait Cycle Control (WCC):** Not applicable to PCI-Express. Hardwired to 0.
6	0x0 RW	**Parity Error Response Enable (PERE):** This bit controls the setting of the master data parity error bit in the Status Register PCI Status Register (PCISTS) in response to a parity error received on the PCI Express interface (either internal queue errors or a poisoned TLP).
5	0x0 RO	**VGA Palette Snoop Enable (VGA_PSE):** Not applicable to PCI-Express. Hardwired to 0.
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not applicable to PCI-Express. Hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not applicable to PCI-Express. Hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** This bit controls the ability of the Function to issue Memory and I/O read or write requests, and the ability of Root or Switch port to forward memory and I/O read or write requests in the upstream direction. When this bit is 0b, memory and I/O requests received at the root port or downstream side of a switch port (secondary side) must be handled as an Unsupported Request (UR). MSI interrupts are inband memory writes and are blocked when this bit is 0b.
1	0x0 RW	**Memory Space Enable (MSE):** • 0 - Respond to all Memory Requests on the primary interface as Unsupported Request Received. Forward all memory requests from the secondary interface to the primary interface. • 1- Enable forwarding of memory transactions to the secondary interface and any internal function.
0	0x0 RW	**I/O Space Enable (IOSE):** • 0 - Respond to all I/O Requests on the primary interface with an Unsupported Request Completion. Forward all I/O transactions from the secondary interface to the primary interface (if supported). • 1 - Enable forwarding of I/O Requests to the secondary interface.

47.2.4 PCISTS—Offset 6h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 6h
Offset: [B:0, D:22, F:0] + 6h
Offset: [B:0, D:23, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**Detected Parity Error (DPE):** This bit is set when a poisoned TLP is received from PCIe or IOSF. This bit is set even when the parity error response enable bit (bit[6] of the PCI Command Register (PCICMD) is not set.
14	0x0 RW/1C/V	**Signaled System Error (SSE):** This bit is set when ERR_FATAL or ERR_NONFATAL messages are sent to the root complex and the SERR enable bit in the PCICMD Register PCI Command Register (PCICMD) is set.
13	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit is set when the requester receives a completion with an UR completion status.
12	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit is set when a requester receives a CA completions status.
11	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit is Set when the port completes a Posted or Non-Posted Request as a Completer Abort error.
10:9	0x0 RO	**DEVSEL# Timing (DVT):** These bits have no meaning on PCI Express.
8	0x0 RW/1C/V	**Master Data Parity Error Detected (MDPD):** This bit is set if the parity error response enable bit (PERE) in the Command Register PCI Command Register (PCICMD) is set and either of the following two conditions occur: • Requester receives a completion marked poisoned. • Requester sends a poisoned request (includes writes and messages). If the parity error bit is 0b, this bit is never set.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** This bit has no meaning on PCI Express.
6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**Reserved:** Reserved
4	0x1 RO	**Capabilities List Enable (CAPE):** This bit indicates the presence of an Extended capabilities list items.
3	0x0 RO/V	**Interrupt Status (INTS):** When set, this bit indicates that an INTx emulation interrupt is pending internally in this function.
2:0	0x0 RO	**RSVD1:** Reserved

47.2.5 CCR—Offset 9h

The CCR register has an attribute of RW-L PRST to allow configuration software to modify and lock the register from further update. Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL').

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] + 9h
Offset: [B:0, D:22, F:0] + 9h
Offset: [B:0, D:23, F:0] + 9h

Default: 00060400h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x6 RW/L	**Base Class (BC):** The value of 06h indicates that this is a bridge device. **Power Well:** PRST
15:8	0x4 RW/L	**Sub-Class (SC):** This 8-bit value indicates that this device is a PCI-to-PCI Bridge. **Power Well:** PRST
7:0	0x0 RW/L	**Register-Level Programming Interface (RLPI):** This bit indicates that this device is standard (non-subtractive) PCI-to-PCI Bridge. **Power Well:** PRST

47.2.6 CLS—Offset Ch

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] + Ch
Offset: [B:0, D:22, F:0] + Ch
Offset: [B:0, D:23, F:0] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Cache Line Size (CLS):** These bits specify the system cache-line size in units of DWords. This field is implemented by PCI Express devices but has no effect on device behavior.

47.2.7 IOBASE—Offset 1Ch

The I/O Base and I/O Limit registers define an address range that is used by the PCI-Express port to determine when to forward I/O transactions from one interface to the other using the following formula: IO_BASE (= A[15:12](=IO_LIMIT Only the upper 4 bits are programmable. For the purpose of address decode, address bits A[11:0] are treated as 0. The bottom of the defined I/O address range will be aligned to a 4KB boundary while the top of the region specified by IO_LIMIT will be one less than a 4 KB multiple.

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] + 1Ch
Offset: [B:0, D:22, F:0] + 1Ch
Offset: [B:0, D:23, F:0] + 1Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW	**I/O Base Address Bits (IOBA):** These bits define the bottom address of an address range to determine when to forward I/O transactions from one interface to another. These bits correspond to address lines[15:12] for 4 KB alignment. Bits[11:0] are assumed to be 000h.
3:0	0x0 RO	**I/O Base Addressing Capability (IOBC):** Each of these bits is hard-wired to 0, indicating support for 16-bit I/O addressing only.

47.2.8 IOLIMIT—Offset 1Dh

The I/O Base and I/O Limit registers define an address range that is used by the PCI-Express bridge to determine when to forward I/O transactions from one interface to the other using the following formula: IO_BASE (= A[15:12] (=IO_LIMIT Only the upper 4 bits are programmable. For the purpose of address decode, address bits A[11:0] of the IO limit register is treated as FFFh.

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] + 1Dh
Offset: [B:0, D:22, F:0] + 1Dh
Offset: [B:0, D:23, F:0] + 1Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW	**I/O Limit Address Bits (IOLA):** These bits define the top address of an address range to determine when to forward I/O transactions from PCI Express to PCI. These bits correspond to address lines[15:12] for 4 KB aligned window. Bits[11:0] are assumed to be FFFh.
3:0	0x0 RO	**I/O Limit Addressing Capability (IOLC):** Each of these bits is hard-wired to 0, indicating support for 16-bit I/O addressing only.

47.2.9 MEMBASE—Offset 20h

The Memory Base and Memory Limit registers define a memory mapped I/O non-prefetchable address range (32-bit addresses) and direct the accesses in this range to the PCI-Express port based on the following formula: MEMORY_BASE (= A[31:20] (= MEMORY_LIMIT The upper 12 bits of both the Memory Base and Memory Limit registers are read/write and corresponds to the upper 12 address bits, AD[31:20], of 32-bit addresses. For the purpose of address decoding, the bridge assumes that the lower 20 address bits, AD[19:0], of the memory base address are zero. Similarly, the bridge assumes that the lower 20 address bits, AD[19:0], of the memory limit address (not implemented in the Memory Limit register) are FFFFFh. Thus, the bottom of the defined memory address range will be aligned to a 1 MB boundary and the top of the defined memory address range will be one less than a 1 MB boundary

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 20h
Offset: [B:0, D:22, F:0] + 20h
Offset: [B:0, D:23, F:0] + 20h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Memory Base (MB):** These bits are compared with bits[31:20] of the incoming address to determine the lower 1 MB-aligned value (inclusive) of the range. The incoming address must be greater than or equal to this value.
3:0	0x0 RO	**RSVD0:** Reserved

47.2.10 MEMLIMIT—Offset 22h

This register controls the processor to PCI-Express non-prefetchable memory access routing based on the following formula as described above: MEMORY_BASE (= A[31:20] The upper 12 bits of the register are read/write and correspond to the upper 12 address bits A[31:20] of the 32 bit address. The bottom 4 bits of this register are read-only and return zeroes when read. This register must be initialized by the configuration software. For the purpose of address decode address bits A[19:0] are assumed to be FFFFFh. Memory range covered by MEMBASE and MEMLIM registers, are used to map non-prefetchable PCIExpress address ranges (typically where control/ status memory-mapped I/O data structures reside) and PFBASE and PFLIMIT are used to map prefetchable address ranges.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:6, F:0] + 22h
Offset: [B:0, D:22, F:0] + 22h
Offset: [B:0, D:23, F:0] + 22h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Memory Limit (ML):** These bits are compared with bits[31:20] of the incoming address to determine the upper limit of the range of memory accesses that will be passed by the port. The incoming address must be less than or equal to this value as described in the formula in 'Memory Base Register' (MEMBASE).
3:0	0x0 RO	**RSVD0:** Reserved

47.2.11 PFBASE—Offset 24h

The Prefetchable Memory Base and Memory Limit registers define a memory mapped I/O prefetchable address range (32-bit addresses) which is used by the PCI-Express bridge to determine when to forward memory transactions based on the following formula: PREFETCH_MEMORY_BASE (= A[31:20] The upper 12 bits of both the Prefetchable Memory Base and Memory Limit registers are read/ write and corresponds to the upper 12 address bits, A[31:20], of 32-bit addresses. For the purpose of address decoding, the bridge assumes that the lower 20 address bits, A[19:0], of the memory base address are zero. Similarly, the bridge assumes that the lower 20 address bits, A[19:0], of the memory limit address (not implemented in the Memory Limit register) are FFFFFh. Thus, the bottom of the defined memory address range will be aligned to a 1 MB boundary and the top of the defined memory address range will be one less than a 1 MB boundary.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 24h
Offset: [B:0, D:22, F:0] + 24h
Offset: [B:0, D:23, F:0] + 24h

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Prefetchable Memory Base (PMB):** These bits are compared with bits[31:20] of the incoming address to determine the lower 1 MB-aligned value (inclusive) of the range. The incoming address must be greater than or equal to this value.
3:0	0x1 RO	**Prefetchable Memory Base Address Capability (PFMCAP):** • 0: 32-bit Prefetchable Memory addressing • 1: 64-bit Prefetchable Memory addressing This field indicates that 64-bit addressing is supported for the limit.

47.2.12 PFLIMIT—Offset 26h

This register controls the processor to PCI-Express prefetchable memory access routing based on the following formula as described above: PREFETCH_MEMORY_BASE (= A[31:20] The upper 12 bits of the register are read/write and correspond to the upper 12 address bits A[31:20] of the 32 bit address. This register must be initialized by the configuration software. For the purpose of address decode address bits A[19:0] are assumed to be FFFFFh.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 26h
Offset: [B:0, D:22, F:0] + 26h
Offset: [B:0, D:23, F:0] + 26h

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Prefetchable Memory Limit (PML):** These bits are compared with bits[31:20] of the incoming address to determine the upper limit of the prefetchable memory range. The incoming address must be less than or equal to this value as described in the formula in 'Prefetchable Memory Limit Register (PFLIMIT).
3:0	0x1 RO	**Prefetchable Memory Limit Address Capability (PMLC):** This field indicates that 64-bit addressing is supported for the limit.

47.2.13 PFBASEU—Offset 28h

The Prefetchable Base Upper 32 Bits and Prefetchable Limit Upper 32 Bits registers are extensions to the Prefetchable Memory Base and Prefetchable Memory Limit registers. If a 64-bit prefetchable memory address range is supported, the Prefetchable Base Upper 32 Bits and Prefetchable Limit Upper 32 Bits registers specify the upper 32-bits, corresponding to A[63:32], of the 64-bit base and limit addresses which specify the prefetchable memory address range. PREFETCH_MEMORY_BASE_UPPER (= A[63:32] PREFETCH_MEMORY_BASE_LIMIT_UPPER

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] + 28h
Offset: [B:0, D:22, F:0] + 28h
Offset: [B:0, D:23, F:0] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Prefetchable Memory Base Upper Portion (PMBU):** Corresponds to A[63:32] of the memory address that maps to the upper base of the prefetchable range of memory accesses that will be passed by the PCI-Express bridge.

47.2.14 PFLIMITU—Offset 2Ch

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] + 2Ch
Offset: [B:0, D:22, F:0] + 2Ch
Offset: [B:0, D:23, F:0] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Prefetchable Memory Limit Upper Portion (PMLU):** Corresponds to A[63:32] of the memory address that maps to the upper limit of the prefetchable range of memory accesses that will be passed by the PCI-Express bridge. The incoming address must be less than or equal to this value as described in the formula in 'Prefetchable Memory Base Upper 32 Bits Register' (PFBASEU).

47.2.15 CAPPTR—Offset 34h

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] + 34h
Offset: [B:0, D:22, F:0] + 34h
Offset: [B:0, D:23, F:0] + 34h

Default: 40h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x40 RO	**Capabilities Pointer (CPTR):** Contains the offset of the first item in the list of capabilities. (EXPCAPLST)

47.2.16 INTL—Offset 3Ch

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] + 3Ch
Offset: [B:0, D:22, F:0] + 3Ch
Offset: [B:0, D:23, F:0] + 3Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Line (INTL):** This register is used to communicate interrupt line routing information.

47.2.17 INTP—Offset 3Dh

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] + 3Dh
Offset: [B:0, D:22, F:0] + 3Dh
Offset: [B:0, D:23, F:0] + 3Dh

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RW/L	**Interrupt Pin (INTP):** This register tells which interrupt pin the function uses. • 01h: Generate INTA • 02h: Generate INTB • 03h: Generate INTC • 04h: Generate INTD • Others: Reserved **Power Well:** PRST

47.2.18 BCTL—Offset 3Eh

This register provides extensions to the PCI Command Register (PCICMD) that are specific to a bridge. The Bridge Control Register provides many of the same controls for the secondary interface that are provided by the Command Register for the primary interface. Some bits affect operation of both interfaces of the bridge.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] + 3Eh
Offset: [B:0, D:22, F:0] + 3Eh
Offset: [B:0, D:23, F:0] + 3Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11	0x0 RO	**Discard Timer SERR# Enable (DTSE):** Not applicable to PCI Express. Hardwired to 0.
10	0x0 RO	**Discard Timer Status (DTS):** Not applicable to PCI Express. Hardwired to 0.
9	0x0 RO	**Secondary Discard Timer (SDT):** Not applicable to PCI Express. Hardwired to 0.

Bit Range	Default & Access	Field Name (ID): Description
8	0x0 RO	**Primary Discard Timer (PDT):** Not applicable to PCI Express. Hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not applicable to PCI Express. Hardwired to 0.
6	0x0 RW	**Secondary Bus Reset (SBR):** Setting this bit triggers a hot reset on the downstream link for the corresponding PCIe Express port and the PCI Express hierarchy domain subordinate to the port. Software must ensure a minimum reset duration of 1us as defined in the PCI Local Bus Specification, Revision 3.0. Hardware will continue to maintain the hot reset state as long as the SBR bit is set. For Root Ports, it is recommended that software assert this field for a minimum of 2 ms to ensure that all downstream links enters hot reset state. A secondary bus reset will not reset any register of a Type 1 configuration space header function.
5	0x0 RO	**Master Abort Mode (MAM):** Not applicable to PCI Express. Hardwired to 0.
4	0x0 RW	**VGA 16-bit Decode (VGA16BD):** This bit enables the bridge to provide 16-bit decoding of VGA I/O address precluding the decoding of VGA alias addresses every 1 KB. This bit requires the VGA enable bit (bit 3 of this register) to be set to 1. • 0: execute 10-bit address decode on VGA I/O accesses • 1: execute 16-bit address decode on VGA I/O accesses
3	0x0 RW	**VGA Enable (VGAE):** This bit modifies the response to VGA-compatible addresses. When set to 1b, the bridge positively decodes and forwards the following transactions from primary side to secondary side regardless of the value of the I/O base and limit registers. The transactions are qualified by the memory enable and I/O enable in the command register. Memory addresses: • 000A 0000h-000B FFFFh I/O addresses: • 3B0h-3BBh and 3C0h-3DFh in first 64 KB of I/O address space (Inclusive of ISA address aliases when IO address bits[15:10] are not decoded)
2	0x0 RW	**ISA Enable (IE):** This bit modifies the response by the bridge to ISA I/O addresses. This field applies only to I/O addresses that are enabled by the I/O base and I/O limit registers and are in the first 64 KB of PCI I/O space. When this bit is set, the bridge blocks all forwarding from primary to secondary of I/O transactions addressing the last 768 bytes in each 1 KB block (offsets 100h to 3FFh). In the opposite direction (secondary to primary), I/O transactions will be forwarded if they address the last 768B in each 1 KB block. • 1: Forward upstream ISA I/O addresses in the address range defined by the I/O Base and I/O Limit registers that are in the firsts 64KB of PCI I/O address space (Top 768B of each 1K block). • 0: Forward downstream all I/O addresses in the address range defined by the I/O Base and I/O Limit registers.
1	0x0 RW	**SERR# Enable (SE):** This bit controls the forwarding of PCI Express ERR_COR, ERR_NONFATAL and ERR_FATAL messages to the primary side. • 1: Enables forwarding of ERR_COR, ERR_NONFATAL, ERR_FATAL messages. • 0: Disables forwarding of ERR_COR, ERR_NONFATAL, ERR_FATAL messages.
0	0x0 RW	**Parity Error Response Enable (PERE):** This bit controls the response to poisoned TLPs in the PCI Express port. • 1: Enables reporting of poisoned TLP errors. • 0: Disables reporting of poisoned TLP errors.

47.2.19 EXPCAPLST—Offset 40h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +40h
Offset: [B:0, D:22, F:0] +40h
Offset: [B:0, D:23, F:0] +40h

Default: 8010h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x80 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list. (PMCAPLST)
7:0	0x10 RO	**Capability ID (CAPID):** Identifies the function as PCI Express capable.

47.2.20 EXPCAP—Offset 42h

This register stores the version number of the capability item and other base information contained in the capability structure.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +42h
Offset: [B:0, D:22, F:0] +42h
Offset: [B:0, D:23, F:0] +42h

Default: 0042h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**RSVD0:** Reserved
13:9	0x0 RO	**Interrupt Message Number (IMN):** This field indicates the interrupt message number that is generated from the PCI Express port.
8	0x0 RO	**Slot Implemented (SI):** Hardwired to 0 for non root ports and non DP.
7:4	0x4 RO	**Device/Port Type (DT):** 4h: Virtual Root Port
3:0	0x2 RO	**Version Number (VN):** These bits indicate the version number of the PCI Express capability structure.

47.2.21 DEVCAP—Offset 44h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +44h
Offset: [B:0, D:22, F:0] +44h
Offset: [B:0, D:23, F:0] +44h

Default: 00008001h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:26	0x0 RO	**Captured Slot Power Limit Scale (CSPLS):** In combination with the Slot Power Limit value (bits[25:18], this field specifies the upper limit of the power supplied by slot. The power limit (in Watts) is calculated by multiplying the value in this field by the value in the Slot Power Limit Value field. This value is set by the Set_Slot_Power_Limit message. Does not apply to root ports or integrated devices or end points or downstream ports or Virtual Root Port/switch port
25:18	0x0 RO	**Captured Slot Power Limit Value (CSPLV):** In combination with the Slot Power Limit Scale value (bits[27:26]), this field specifies the upper limit of the power supplied by slot. The power limit (in Watts) is calculated by multiplying the value in this field by the value in the Slot Power Limit Scale field. This value is set by the Set_Slot_Power_Limit message. Does not apply to root ports or integrated devices or end points or downstream ports or Virtual Root Port/switch ports
17:16	0x0 RO	**RSVD1:** Reserved
15	0x1 RO	**Role-Based Error Reporting (RBER):** The PCIe cluster supports Role-based Error Reporting.
14:12	0x0 RO	**Undefined:** Reserved.
11:9	0x0 RO	**Endpoint L1 Acceptable Latency (EPL1AL):** This field only applies to Endpoint and is hardwired to 0 for other types such as root ports, upstream/downstream ports
8:6	0x0 RO	**Endpoint L0s Acceptable Latency (EPL0AL):** This field only applies to Endpoint and is hardwired to 0 for other types such as root ports, upstream/downstream ports
5	0x0 RO	**Extended Tag Field Supported (ETFG):** • 0: The PCIe supports 5-bit extended tag • 1: The PCIe supports 8-bit extended tag
4:3	0x0 RO	**Phantom Functions Supported (PFS):** This field indicates the number of most significant bits of the function number portion of Requester ID in a TLP that are logically combined with the Tag identifier. The PCIe cluster does not support phantom functions
2:0	0x1 RO/V	**Max Payload size Supported (MPSS):** The PCIe SIP can tolerate upto 512-byte packets as maximum payload for project specific.

47.2.22 DEVCTL—Offset 48h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +48h
Offset: [B:0, D:22, F:0] +48h
Offset: [B:0, D:23, F:0] +48h

Default: 2000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x2 RW	**Max_Read_Request_Size (MRRS):** This field sets the maximum Read Requests size of the function as a requester. • 000b: 128 bytes maximum Read Request size • 001b: 256 bytes maximum Read Request size • 010b: 512 bytes maximum Read Request size • 011b: 1024 bytes maximum Read Request size • 100b: 2048 bytes maximum Read Request size • 101b: 4096 bytes maximum Read Request size • Others: Reserved
11	0x0 RO	**Enable No Snoop (ENOSNP):** If this bit this is set, the function is permitted to set the No Snoop bit in the Requester attributes of transactions it initiates that do not require hardware enforced cache coherency.
10	0x0 RO	**Auxiliary Power PM Enable (AUXPME):** Not supported
9	0x0 RO	**Reserved:** Reserved
8	0x0 RO	**Reserved:** Reserved
7:5	0x0 RW	**Maximum Payload Size (MPS):** This field sets maximum TLP payload size for the function. As a receiver, the function must handle TLPs as large as the set value. As a Transmitter, the function must not generate TLPs exceeding the set value. • 000b: 128 bytes maximum payload size (default) • 001b: 256 bytes maximum payload size • 010b: 512 bytes maximum payload size • 011b: 1024 bytes maximum payload size • 100b: 2048 bytes maximum payload size • 101b: 4096 bytes maximum payload size • Others: Reserved
4	0x0 RO	**Reserved:** Reserved
3	0x0 RW	**Unsupported Request Reporting Enable (URRE):** This bit controls the enabling of ERR_CORR, ERR_NONFATAL or ERR_FATAL messages on PCI Express for reporting 'Unsupported Request' errors.
2	0x0 RW	**Fatal Error Reporting Enable (FERE):** When this bit is set, generation of the ERR_FATAL message is enabled.
1	0x0 RW	**NonFatal Error Reporting Enable (NFERE):** When this bit is set, generation of the ERR_NONFATAL message is enabled.
0	0x0 RW	**Correctable Error Reporting Enable (CERE):** When this bit is set, generation of the ERR_CORR message is enabled.

47.2.23 DEVSTS—Offset 4Ah

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +4Ah
Offset: [B:0, D:22, F:0] +4Ah
Offset: [B:0, D:23, F:0] +4Ah

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO/V	**Transactions Pending (TP):** When set, this bit indicates that the function has issued Non-Posted Requests that have not been completed.
4	0x0 RO	**Auxiliary Power Detected (APD):** Auxiliary Power is not supported.
3	0x0 RW/1C/V	**Unsupported Request Detected (URD):** This bit indicates that this function received an unsupported request from PCI Express link. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
2	0x0 RW/1C/V	**Fatal Error Detected (FED):** This bit indicates that this function has detected a Fatal error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
1	0x0 RW/1C/V	**Non-Fatal Error Detected (NFED):** This bit indicates that this function has detected a Non-Fatal error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
0	0x0 RW/1C/V	**Correctable Error Detected (CED):** This bit indicates that this function has detected a Correctable error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.

47.2.24 LINKCAP—Offset 4Ch

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +4Ch
Offset: [B:0, D:22, F:0] +4Ch
Offset: [B:0, D:23, F:0] +4Ch

Default: 06000C11h for D6
Default: 16000C11h for D22
Default: 17000C11h for D23

Bit Range	Default & Access	Field Name (ID): Description
31:24	D6: 0x6 D22: 0x16 D23: 0x17 RW/L	**Port Number (PN):** This field indicates the PCI Express port number assigned to this link for Virtual Root Port/Switch Port. **Power Well:** PRST
23:22	0x0 RO	**RSVD0:** Reserved
21	0x0 RO	**Link Bandwidth Notification Capability (LBNC):** A value of 1b indicates support for the Link Bandwidth Notification status and interrupt mechanisms.
20	0x0 RO	**Data Link Layer Active Error Reporting Capable (DLLERC):** For Upstream Ports and components that do not support this optional capability, this bit must be hardwired to 0b Used device number to distinguish the vRP and vSP for default values
19	0x0 RO	**Surprise Down Error Reporting Capable (SLDERC):** For Upstream Ports and components that do not support this optional capability, this bit must be hardwired to 0b.
18	0x0 RO	**Clock Power Management Capable (CPMC):** For Downstream Ports, this bit must be hardwired to 0b.
17:15	0x0 RO	**L1 Exit Latency (L1EL):** This field indicates the L1 exit latency for the given PCI-Express Link. It indicates the length of time this port requires to complete transition from L1 to L0. • 000: Less than 1us • 001: 1us to less than 2us • 010: 2us to less than 4us • 011: 4us to less than 8us • 100: 8us to less than 16us • 101: 16us to less than 32us • 110: 32us to less than 64us • 111: More than 64us If L1 is not supported, the value is undefined
14:12	0x0 RO	**L0s Exit Latency (L0sEL):** This field indicates the L0s exit latency for the given PCI-Express Link. It indicates the length of time this port requires to complete transition from L0s to L0. • 000b: Less than 64ns • 001b: 64ns to less than 128ns • 010b: 128ns to less than 256ns • 011b: 256ns to less than 512ns • 100b 512 ns to less than 1us • 101b: 1us to less than 2us • 110b: 2us to less than 4us • 111b: More than 4us If L0s is not supported, the value is undefined

Bit Range	Default & Access	Field Name (ID): Description
11:10	0x3 RO	**ASPM Support (ASPMSUP):** This field indicates the level of ASPM supported on the given PCI Express Link. • 00b: No ASPM Support • 01b: L0s Supported • 10b: L1 Supported • 11b: L0s and L1 Supported
9:4	0x1 RO	**Maximum Link Width (MLW):** This field indicates the maximum link width implemented by the given PCI Express Link. • 00h: Reserved • 01h: x1 • 02h: x2 • 04h: x4 • 08h: x8 • 10h: x16 • 20h: x32 (Unsupported) • Others Reserved
3:0	0x1 RO	**Maximum Link Speed (MLS):** This field indicates the maximum supported link speed(s) of the associated port. • 0001b: 2.5 Gb/s link speed is supported • 0010b: 5.0 Gb/s and 2.5 Gb/s link speed supported • 0011b: 8.0 Gb/s and 5.0 and 2.5 Gb/s link speed supported • Others: Reserved.

47.2.25 LINKCTL—Offset 50h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +50h
Offset: [B:0, D:22, F:0] +50h
Offset: [B:0, D:23, F:0] +50h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11	0x0 RO	**Reserved:** Reserved
10	0x0 RO	**Link Bandwidth Management Interrupt Enable (LBMIE):** When set, this bit enables the generation of an interrupt to indicate that the Link Bandwidth Management Status bit has been set.
9	0x0 RO	**Reserved:** Reserved
8	0x0 RW/L	**Enable Clock Power Management (ECPM):** Applicable only for Upstream Ports and with form factors that support a 'Clock Request' (CLKREQ#) mechanism, this bit operates as follows: • 0b Clock power management is disabled and device must hold CLKREQ# signal low. • 1b When this bit is Set, the device is permitted to use CLKREQ# signal to power manage Link clock according to protocol defined. **Power Well:** PRST
7	0x0 RW	**Extended Synch (ES):** When set, this bit forces extended transmission of 4096 FTS ordered sets in FTS and an extra 1024 TS1 at exit from L1 prior to entering L0.
6	0x0 RW	**Common Clock Configuration (CCCFG):** When set, this bit indicates that this component and the component at the opposite end of this link are operating with distributed common reference clocks. A value of 0b indicates that this component and the component at the opposite end of this link are operating with asynchronous reference clock.
5	0x0 RO	**Retrain Link (RL):** When set, this bit initiates link retraining by directing the physical layer LTSSM to recovery state. For the upstream port or virtual switch port, it is Read-only.
4	0x0 RW	**Link Disable (LD):** This bit is reserved on Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches.
3	0x0 RO	**Read Completion Boundary (RCB):** This bit indicates the RCB value for Root Port, Endpoints and Bridges. • 0b: 64 byte • 1b: 128 byte
2	0x0 RO	**RSVD1:** Reserved
1:0	0x0 RW	**ASPM Control (ASPMCTL):** This field controls the level of ASPM enabled on a given PCI Express Link. • 00b: Disabled • 01b: L0s Entry Enabled • 10b: L1 Entry Enabled • 11b: L0s and L1 Entry Enabled ''L0s Entry Enabled' enables the Transmitter to enter L0s.

47.2.26 LINKSTS—Offset 52h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +52h
Offset: [B:0, D:22, F:0] +52h
Offset: [B:0, D:23, F:0] +52h

Default: 1011h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Link Autonomous Bandwidth Status (LABS):** This bit is set by hardware.
14	0x0 RO	**Link Bandwidth Management Status (LBMS):** This bit is set by hardware. This bit must be set if the Physical Layer reports a non-autonomous speed or width change initiated by the Upstream Port.
13	0x0 RO	**Data Link Layer Link Active (DLLLA):** This bit indicates the status of the Data Link Control and Management Status Machine. It returns a 1b to indicate the DL_Active state, 0b otherwise.
12	0x1 RW/L	**Slot Clock Configuration (SCC):** When to 1b, this bit indicates that the component uses the same physical reference clock that he platform provides on the connector. If the device uses an independent clock irrespective of the presence of a reference on the connector, this bit must be clear. • 1: Indicates same reference clock. • 0: Indicates independent reference clock **Power Well:** PRST
11	0x0 RO	**Link Training (LT):** This bit indicates that the Physical Layer LTSSM is in the Configuration or Recovery state, or a 1b was written to the Retrain Link bit but the Link training has not yet begun. Hardware clears this bit when the LTSSM exits the Configuration/Recovery state.
10	0x0 RO	**Undefined:** Not applicable
9:4	0x1 RO	**Negotiated Link Width (NLW):** This field indicates the negotiated width of the PCI Express link. • 00 0001b: x1 • 00 0010b: X2 • 00 0100b: x4 • 00 1000b: X8 • 00 1100b: X12 not supported • 01 0000b: X16 • 10 0000b: X32 not supported • All other values are reserved. The value in this field is undefined when the link is not up.
3:0	0x1 RO	**Current Link Speed (CLS):** This field indicates the negotiated link speed of the given PCI Express link. • 0001b: 2.5 Gb/s PCI Express Link • 0010b: 5.0 Gb/s PCI Express Link • 0011b: 8.0 Gb/s PCI Express Link • Others: Reserved

47.2.27 SLOTSTS—Offset 5Ah

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +5Ah
Offset: [B:0, D:22, F:0] +5Ah
Offset: [B:0, D:23, F:0] +5Ah

Default: 0040h

Bit Range	Default & Access	Field Name (ID): Description
15:7	0x0 RO	**RSVD0:** Reserved
6	0x1 RO/V	**Presence Detect State (PDS):** This field conveys the Presence Detect status of an adapter in the slot. • 0: Card/Module/Cable slot empty or Cable Slot occupied but not powered • 1: Card/module Present in slot (powered or unpowered) or cable present and powered on the other end.
5:0	0x0 RO	**RSVD1:** Reserved

47.2.28 ROOTCTL—Offset 5Ch

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +5Ch
Offset: [B:0, D:22, F:0] +5Ch
Offset: [B:0, D:23, F:0] +5Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:5	0x0 RO	**RSVD0:** Reserved
4	0x0 RO	**CRS Software Visibility Enable (CRSSVE):** This bit, when set, enables the Root Port to return Configuration Retry Status (CRS) Completion status to software. • 1: Enable software to received a CRS status. This allows software to make the decision to re-issue the configuration request or move on and re-issue the request at a later time. • 0: Disable software from receiving a CRS response. The PCIe will wait and re-issue the configuration request until it receives a response other than CRS without notifying software.
3	0x0 RW	**PME Interrupt Enable (PMEIE):** This field controls the generation of interrupts for PME messages. • 1: Enables interrupt generation upon receipt of a PME message as reflected in the PME Status bit defined in the ROOTSTS register. A PME interrupt is generated if the PMESTATUS register bit defined in Root Status Register (ROOTSTS), is set when this bit is set from a cleared state. 0: Disables interrupt generation for PME messages.
2	0x0 RW	**System Error on Fatal Error Enable (SEFEE):** This field controls generation of system errors in the PCI-Express port hierarchy for fatal errors. • 1: indicates that a System Error should be generated if a fatal error (ERR_FATAL) is reported by any of the devices in the hierarchy associated with and including this PCI-Express port. • 0: No System Error should be generated on a fatal error (ERR_FATAL) reported by any of the devices in the hierarchy.
1	0x0 RW	**System Error on Non-Fatal Error Enable (SENFEE):** This field controls generation of system errors in the PCI-Express port hierarchy for non-fatal errors. • 1: indicates that a System Error should be generated if a non-fatal error (ERR_NONFATAL) is reported by any of the devices in the hierarchy associated with and including this PCI-Express port. • 0: No System Error should be generated on a non-fatal error (ERR_NONFATAL) reported by any of the devices in the hierarchy.
0	0x0 RW	**System Error on Correctable Error Enable (SECEE):** This field controls generation of system errors in the PCI-Express port hierarchy for correctable errors. • 1: indicates that a System Error should be generated if a correctable error (ERR_COR) is reported by any of the devices in the hierarchy associated with and including this PCI-Express port • 0: No System Error should be generated on a correctable error (ERR_COR) reported by any of the devices in the hierarchy associated with and including this PCI-Express port.

47.2.29 ROOTCAP—Offset 5Eh

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +5Eh
Offset: [B:0, D:22, F:0] +5Eh
Offset: [B:0, D:23, F:0] +5Eh

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:1	0x0 RO	**RSVD0:** Reserved
0	0x1 RW/L	**CRS Software Visibility (CRSSV):** This bit, when set, indicates that the Root Port is capable of returning Configuration Retry Status (CRS) on completions to software. Based on Design input, the CRS notification will be implemented in the EIP PCIe macro and hence the default is set to 1. The field attribute is made as RW-O for any specific changes to be installed by BIOS **Power Well:** PRST

47.2.30 ROOTSTS—Offset 60h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +60h
Offset: [B:0, D:22, F:0] +60h
Offset: [B:0, D:23, F:0] +60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**RSVD0:** Reserved
17	0x0 RO/V	**PME Pending (PMEPEND):** This field indicates that another PME is pending when the PME Status bit is set. When the PME Status bit is cleared by software, the pending PME is delivered by hardware by setting the PME Status bit again and updating the Requestor ID appropriately. The PME pending bit is cleared by hardware if no more PMEs are pending. ***Note:*** The root port can handle two outstanding PM_PME messages in its internal queues of the Power Management controller per port. If the downstream device issues more than 2 PM_PME messages successively, it will be dropped.
16	0x0 RW/1C/V	**PME Status (PMESTS):** This field indicates status of a PME that is underway in the PCI-Express port. 1: PME was asserted by a requester as indicated by the PMEREQID field This bit is cleared by software by writing a '1'. Subsequent PMEs are kept pending until the PME Status is cleared.
15:0	0x0 RO/V	**PME Requester ID (PMERID):** This field indicates the PCI requester ID of the last PME requestor.

47.2.31 DEVCAP2—Offset 64h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +64h
Offset: [B:0, D:22, F:0] +64h
Offset: [B:0, D:23, F:0] +64h

Default: 00000020h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:18	0x0 RO	**OBFF Supported (OBFFS):** • 00b: OBFF Not Supported • 01b: OBFF supported using Message signaling only • 10b: OBFF supported using WAKE# signaling only • 11b: OBFF supported using WAKE# and Message signaling Applicable only to Root Ports, Switch Ports, and Endpoints that support this capability. Must be 00b for other function types.
17:14	0x0 RO	**RSVD1:** Reserved
13:12	0x0 RO	**TPH Completer Supported (TPHCS):** Value indicates Completer support for TPH or Extended TPH. • 00b:TPH and Extended TPH Completer not supported • 01b: TPH Completer supported, Extended TPH completer not supported • 10b: Reserved • 11b: Both TPH and Extended TPH Completer supported Applicable only to Root Ports and Endpoints. Must be 00b for other function types.
11	0x0 RW/L	**LTR Mechanism Supported (LTRMS):** This bit when set indicates support for the Latency Tolerance Reporting (LTR) mechanism. **Power Well:** PRST
10	0x0 RO	**No RO-enabled PR-PR Passing (NROEPRPASS):** This bit if set to 1b disables passing permitted by row entry A2b in PCIe ordering table that is associated with the Relaxed Ordering Attribute field being set. This bit applies only for Switches and RCs that support peer-to-peer traffic between ports. The bit only applies to posted requests being forwarded through the switch or RC. It does not apply to traffic originating or terminating with in the switch or RC itself.
9	0x0 RO	**AD128 CAS Completer Supported (AD128ACS):** This bit must be set to 1b if the function supports this optional capability. Applicable to functions with memory space BARs as well as Root Ports. This is not implemented in Virtual Root port
8	0x0 RO	**AD64-bit AtomicOp Completer Supported (AD64ACS):** This bit must be set to 1b if the function supports this optional capability. Applicable to Functions with Memory Space BARs as well as all Root Ports, must be 0b otherwise. Includes FetchAdd, Swap, and CAS AtomicOps. This is not implemented in Virtual Root port
7	0x0 RO	**AD32 bit AtomicOp Completer Supported (AD32ACS):** Applicable to Functions with Memory Space BARs as well as all Root Ports, must be 0b otherwise. Includes FetchAdd, Swap, and CAS AtomicOps. This bit must be set to 1b if the Function supports this optional capability. This is not implemented in Virtual Root port
6	0x0 RW/L	**AtomicOp Routing Supported (ARS):** This bit must be set to 1b if the port supports this optional capability. Applicable only to switch upstream ports, Switch downstream ports, and root ports,. This is not implemented in Virtual Root port. **Power Well:** PRST
5	0x1 RW/L	**ARI Forwarding Supported (ARI):** This bit is set to 1b indicating that the downstream port supports this capability. Applicable only to Switch Downstream Ports and Root Ports, must be 0b for other Function types. This bit must be set to 1b if a Switch Downstream Port or Root Port supports this optional capability. **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RO	**Completion Timeout Disable Support (CTDS):** A value of 1b indicates support for the completion Timeout Disable Mechanism. Support of completion timeout disable is optional for Root Ports. The Completion timeout is not supported for vRP/vSP
3:0	0x0 RO	**Completion Timeout Range Supported (CTRS):** This field indicates device support for the optional Completion Timeout programmability mechanism. This mechanism allows system software to modify the Completion Timeout value. This field is applicable only to Root Ports, Endpoints that issue requests on their own behalf, and PCI Express to PCI/PCI-X Bridges that take ownership of request issues on PCI Express. Four time values ranges are defined: • Range A: 50us to 10ms • Range B: 10ms to 250ms • Range C: 250ms to 4s • Range D: 4s to 64s Bits ares set according to table below to show timeout value ranges supported. • 0000b: Completions Timeout programming not supported -- values is fixed by implementation in the range 50us to 50ms. • 0001b: Range A • 0010b: Range B • 0011b: Range A and B • 0110b: Range B and C • 0111b: Range A, B, and C • 1110b: Range B, C, and D • 1111b: Range A, B, C, and D • All other values are reserved. For all other devices this field is reserved and maybe be hardwired to 0000b. Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL'). CT Ranges are defined for Virtual Root Port / Virtual Switch Port is 0 (unsupported)

47.2.32 DEVCTL2—Offset 68h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +68h
Offset: [B:0, D:22, F:0] +68h
Offset: [B:0, D:23, F:0] +68h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:13	0x0 RO	**OBFF Enable (OBFFE):** Reserved.
12:11	0x0 RO	**RSVD1:** Reserved
10	0x0 RW/V	**LTR Mechanism Enable (LTRME):** When set to 1b, this bit enables Upstream Ports to send LTR messages and Downstream Ports to process LTR Messages. Applicable to Root Ports, Switches, and Endpoints that implement the LTR capability must implement this bit. For Downstream Ports, this bit must be reset to the default value if the Port goes to DL_Down status.
9	0x0 RO	**IDO Completion Enable (IDOCE):** This bit when set to 1b allows the function to set the ID-Based Ordering (IDO) bit of completions it returns. Applicable only to Endpoints including RC integrated Endpoints and Root Ports.
8	0x0 RO	**IDO Request Enable (IDORE):** This bit when set to 1b allows the function to set the ID-Based Ordering (IDO) bit on requests it initiates. Applicable only to Endpoints including RC integrated Endpoints and Root Ports.
7	0x0 RO	**AtomicOp Egress Blocking (AEB):** When this bit is set, AtomicOp requests that target this out going Egress port must be blocked. Applicable and mandatory for switch Upstream Ports, Switch Downstream Ports, and Root Ports that implement AtomicOp routing capability. Otherwise, must be hardwired to 0b. AEB is not supported for Virtual Root port but applicable for Virtual Switch Port if supported.
6	0x0 RO	**AtomicOp Requester Enable (ARE):** Applicable only to Endpoints and Root Ports, must be hardwired to 0b for other Function types.
5	0x0 RW	**ARI Forwarding Enable (ARIE):** When set to 1b, ARI is enabled for the downstream port or root ports. The Downstream Port disables its traditional Device Number field being 0 enforcement when turning a Type 1 Configuration Request into a Type 0 Configuration Request, permitting access to Extended Functions in an ARI Device immediately below the Port. Default value of this bit is 0b.
4	0x0 RO	**Completion Timeout Disable (CTD):** • 1: Disable the completions timeout mechanism for all NP transactions. • 0: Completion timeout is enabled for all NP transactions.
3:0	0x0 RO	**Completion Timeout Value (CTV):** In devices that support completion timeout programmability, this field allows system software to modify the completion timeout range. The following encodings and corresponding timeout ranges are defined based on implementation choice. This field provides finer control based over the ranges chosen by DEVAP2.CTRS. The implementation specific range is shown in brackets • 0000b: 50us to 50ms (16.8ms - 25.2ms based on core clk period) • 0001b: 50us to 100us (65.5us - 99.3us based on core clk period) • 0010b: 1ms to 10ms (4.2ms - 6.3ms based on core clk period) • 0101b: 16ms to 55ms (33.6ms - 50.3ms based on core clk period) • 0110b: 65ms to 210ms (134.2ms - 201.3ms based on core clk period) • 1001b: 260ms to 900ms (536.9ms - 805.3ms based on core clk period) • 1010b: 1s to 3.5s (2.1s - 3.2s based on core clk period) • 1101b: 4s to 13s (8.6s - 12.9s based on core clk period) • 1110b: 17s to 64s (34.4s - 51.5s based on core clk period) • All others are reserved. CTV is not supported in UP, DP and vRP/vSP It is highly recommended that the completion timeout value not be less then 10ms. A small completion timeout value may result in premature completion timeout for slower responding devices.

47.2.33 LINKCAP2—Offset 6Ch

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +6Ch
Offset: [B:0, D:22, F:0] +6Ch
Offset: [B:0, D:23, F:0] +6Ch

Default: 00000002h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22:16	0x0 RW/L	**Lower SKP OS Reception Supported Speeds Vector (LSKPOSRSSV):** If this field is non-zero, it indicates that the Port, when operating at the indicated speed(s) supports SRIS and also supports receiving SKP OS at the rate defined for SRNS while running in SRIS. Bit definitions within this field are: • Bit 0 2.5 GT/s • Bit 1 5.0 GT/s • Bit 2 8.0 GT/s • Bits 6:3 RsvdP Multi-Function devices associated with an Upstream Port must report the same value in this field for all Functions. Behavior is undefined if a bit is Set in this field and the corresponding bit is not Set in the Supported Link Speeds Vector. Currently, design does not support reception of low frequency SOS in L0. **Power Well:** PRST
15:9	0x0 RW/L	**Lower SKP OS Generation Supported Speeds Vector (LSKPOSGSSV):** If this field is non-zero, it indicates that the Port, when operating at the indicated speed(s) supports SRIS and also supports software control of the SKP Ordered Set transmission scheduling rate. Bit definitions within this field are: • Bit 0 2.5 GT/s • Bit 1 5.0 GT/s • Bit 2 8.0 GT/s • Bits 6:3 RsvdP Multi-Function devices associated with an Upstream Port must report the same value in this field for all Functions. Behavior is undefined if a bit is Set in this field and the corresponding bit is not Set in the Supported Link Speeds Vector. **Power Well:** PRST
8	0x0 RW/L	**Crosslink Supported (CLS):** When set to 1b, this bit indicates that the associated Port supports crosslinks When set to 0b on a Port that supports Link speeds of 8.0 GT/s or higher, this bit indicates that the associated Port does not support crosslinks. When set to 0b on a Port that only supports Link speeds of 2.5 GT/s or 5.0 GT/s, this bit provides no information regarding the Port's level of crosslink support. It is recommended that this bit be Set in any Port that supports crosslinks even though doing so is only required for Ports that also support operating at 8.0 GT/s or higher Link speeds. ***Note:*** Software should use this bit when referencing fields whose definition depends on whether or not the Port supports crosslinks. **Power Well:** PRST
7:1	0x1 RO	**Supported Link Speeds Vector (SLNKSPV):** This field indicates the supported Link speed(s) of the associated Port. For each bit, a value of 1b indicates that the corresponding Link speed is supported, otherwise, the Link speed is not supported. Bit definitions are: • bit 1 2.5 GT/s • bit 2 5.0 GT/s • bit 3 8.0 GT/s • Others: Reserved
0	0x0 RO	**RSVD1:** Reserved

47.2.34 LINKCTL2—Offset 70h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +70h
Offset: [B:0, D:22, F:0] +70h
Offset: [B:0, D:23, F:0] +70h

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**Compliance Preset/De-emphasis (CD):** For 8 GT/s and 5 GT/s: This bit sets the transmitter preset level forPolling.Compliance state if the entry occurred due to the Enter Compliance bit being 1b. The Encoding are defined as follows: 8 GT/s Rate: • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. 5 GT/s Rate: • 001b: -3.5dB • 000b: -6 dB • All other are reserved. When the link is operating at 2.5 Gb/s, the setting of this bit has no effect. Components that support only 2.5 GT/s speed are permitted to hardwire this bit to 0b.
11	0x0 RO	**Compliance SOS (CSOS):** When set to 1b, the LTSSM is required to send Skip Ordered Sets periodically in between the (modified) compliance patterns.
10	0x0 RO	**Enter Modified Compliance (EMC):** When set to 1b, the device transmits Modified Compliance Pattern if the LTSSM enters Polling.Compliance substate. This register is intended for debug, compliance testing purposes only. System firmware and software is allowed to modify this register only during debug or compliance testing. In all other cases, the system must ensure that this register is set to the default value.
9:7	0x0 RO	**Transmit Margin (TM):** This field controls the value of the non-de-emphasized voltage level at the transmitter pins. This field is reset to 000b on entry to the LTSSM Polling.Configuration substate. • 000b: Normal operating range • 001b: 800-1200mV for full swing and 400-700mV for half-swing • 010b-110b: TBD • Others: Reserved This register is intended for debug, compliance testing purposes only. System firmware and software is allowed to modify this register only during debug or compliance testing. In all other cases, the system must ensure that this register is set to the default value.
6	0x0 RO	**Selectable De-emphasis (SD):** This bit is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and upstream ports of switches.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RO	**Hardware Autonomous Speed Disable (HASD):** When set, this bit disables hardware from changing the link speed for device specific reasons other than attempting to correct unreliable link operation by reducing link speed for device-specific reasons other than attempting to correct unreliable link operations by reducing link speed. Initial transition to the highest supported common link speed is not blocked by this bit.
4	0x0 RO	**Enter Compliance (EC):** Software is permitted to force a link to enter compliance mode at the speed indicated in the Target Link Speed field by setting this bit to 1b in both components on a link and then initiating a hot reset on the link.
3:0	0x1 RO	**Target Link Speed (TLS):** For downstream ports and root ports, this field sets an upper limit on link operational speed by restricting the values advertised by the Downstream Port in its training sequences. • 0001b: 2.5 Gb/s Target Link Speed • 0010b: 5.0 Gb/s Target Link Speed • 0011b: 8.0 Gb/s Target Link Speed • Others: Reserved The encoding is the binary value of the bit in the Supported Link Speeds Vector (in the Link Capabilities 2 register) that corresponds to the desired target Link speed. All other encodings are reserved If a value is written to this field that does not correspond to a speed included in the Supported Link Speeds field, the result is undefined. The default value of this field is the highest Link speed supported by the component (as reported in the Max Link Speed field of the Link Capabilities register) unless the corresponding platform/form factor requires a different default value. For both Upstream and Downstream Ports, this field is used to set the target compliance mode speed when software is using the Enter Compliance bit to force a Link into compliance mode.

47.2.35 LINKSTS2—Offset 72h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +72h
Offset: [B:0, D:22, F:0] +72h
Offset: [B:0, D:23, F:0] +72h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**Link Equalization Request (LNKEQREQ):** This bit is set by hardware to request the Link equalization process to be performed on the Link.
4	0x0 RO	**Equalization Phase 3 Successful (EQPH3SUCC):** When set to 1b, this bit indicates that Phase 3 of the Transmitter Equalization procedure has successfully completed.
3	0x0 RO	**Equalization Phase 2 Successful (EQPH2SUCC):** When set to 1b, this bit indicates that Phase 2 of the Transmitter Equalization procedure has successfully completed.
2	0x0 RO	**Equalization Phase 1 Successful (EQPH1SUCC):** When set to 1b, this bit indicates that Phase 1 of the Transmitter Equalization procedure has successfully completed.
1	0x0 RO	**Equalization Complete (EQCMPLT):** When set to 1b, this bit indicates that the Transmitter Equalization procedure has successfully completed.
0	0x0 RO	**Current De-emphasis Level (CDL):** When the link is operating at 5 Gb/s speed, this bit reflects the level of de-emphasis. • 1b: -3.5 dB • 0b: -6dB The value in this bit is undefined when the Link is not operating at 25.0 GT/s speed. Components that support only the 2.5 GT/s speed are permitted to hardwire this bit to 0b.

47.2.36 PMCAPLST—Offset 80h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +80h
Offset: [B:0, D:22, F:0] +80h
Offset: [B:0, D:23, F:0] +80h

Default: 8801h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x88 RO	**Next Pointer (NextPointer):** Contains the offset of the next item in the capabilities list. (SSCAPLST)
7:0	0x1 RO	**Capability ID (CapabilityID):** Identifies the function as PCI Power Management capable.

47.2.37 PMCAP—Offset 82h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +82h
Offset: [B:0, D:22, F:0] +82h
Offset: [B:0, D:23, F:0] +82h

Default: C803h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x19 RO	**PME_Support (PMES):** PME assertion is supported when in D3hot/D3cold. Identifies power states in which the PCIe can send an 'Assert_PMEGPE/ Deassert PMEGPE' message. Bits 15, 14 and 11 must be set to '1' for PCIPCI bridge structures representing ports on root complexes. The definition of these bits is taken from the PCI Bus Power Management Interface Specification Revision 1.1. • XXXX1b - Assert_PMEGPE/Deassert PMEGPE can be sent from D0 • XXX1Xb - Assert_PMEGPE/Deassert PMEGPE can be sent from D1 (Not supported by PCI-E) • XX1XXb - Assert_PMEGPE/Deassert PMEGPE can be sent from D2 (Not supported by PCI-E) • X1XXXb - Assert_PMEGPE/Deassert PMEGPE can be sent from D3 hot (Supported by PCI-E) • 1XXXXb - Assert_PMEGPE/Deassert PMEGPE can be sent from D3 cold (Supported by PCI-E) In the EIP PCIe implementation, there is no PME support for D3 cold as the part does not have the capability. For PCIe compliance purposes, bit 15 is set to 1.
10	0x0 RO	**D2 Support (D2S):** Not supported
9	0x0 RO	**D1 Support (D1S):** Not supported
8:6	0x0 RO	**Auxiliary Current (AC):** Auxiliary power is not supported.
5	0x0 RO	**Device Specific Initialization (DSI):** Device-specific initialization is not required when transitioning to D0 from D3hot state. This bit is zero.
4	0x0 RO	**RSVD0:** Reserved
3	0x0 RO	**PME Clock (PMECLK):** Does not apply to PCI Express. Hard-wired to 0.
2:0	0x3 RO	**Version (VER):** The PM implementation in the PCIe cluster is compliant with PCI Bus Power Management Interface Specification, Revision 1.2.

47.2.38 PMCSR—Offset 84h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +84h
Offset: [B:0, D:22, F:0] +84h
Offset: [B:0, D:23, F:0] +84h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V/P	**PME Status (PMESTS):** Reserved.
14:13	0x0 RO	**Data Scale (DC):** Not supported
12:9	0x0 RO	**Data Select (DS):** Not supported
8	0x0 RW/P	**PME Enable (PMEEN):** Gates assertion of the PME message.
7:4	0x0 RO	**RSVD0:** Reserved
3	0x1 RW/L	**No Soft Reset (NSR):** This bit when 1b indicates that a device transitioning from D3hot to D0 does not perform an internal reset. The configuration context is preserved. **Power Well:** PRST
2	0x0 RO	**RSVD1:** Reserved
1:0	0x0 RW/V	**Power State (PS):** This field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the supported values is given below: • 0h - D0 • 3h - D3hot If software attempts to write an unsupported, optional state to this field, the write operation must complete normally, however, the data is discarded and no state change occurs.

47.2.39 PMBSE—Offset 86h

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] +86h
Offset: [B:0, D:22, F:0] +86h
Offset: [B:0, D:23, F:0] +86h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Bus Power/Clock Control Enable (BPCC_EN):** Neither bus or clock control of PCI is supported when in D3hot state. This bit is hard-wired to 0.
6	0x0 RO	**B2/B3# (B23EN):** Not supported. This bit has no meaning since the BPCC_En bit is hard-wired to 0.
5:0	0x0 RO	**RSVD0:** Reserved

47.2.40 SSCAPLST—Offset 88h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +88h
Offset: [B:0, D:22, F:0] +88h
Offset: [B:0, D:23, F:0] +88h

Default: 900Dh

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x90 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list. (MSICAPLST)
7:0	0xd RO	**Capability ID (CAPID):** Identifies the function as Subsystem Identification capable.

47.2.41 SSVID—Offset 8Ch

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +8Ch
Offset: [B:0, D:22, F:0] +8Ch
Offset: [B:0, D:23, F:0] +8Ch

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RW/L	**Subsystem Vendor Identifier (SSVID):** Assigned by PCI-SIG for vendor ID. **Power Well:** PRST

47.2.42 SSID—Offset 8Eh

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +8Eh
Offset: [B:0, D:22, F:0] +8Eh
Offset: [B:0, D:23, F:0] +8Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/L	**Subsystem Identifier (SSID):** Assigned to uniquely identify the subsystem vendor. **Power Well:** PRST

47.2.43 MSICAPLST—Offset 90h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +90h
Offset: [B:0, D:22, F:0] +90h
Offset: [B:0, D:23, F:0] +90h

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list (MSIXCAPLST). A null value is used to indicate that this is the last capability. The Next Pointer is terminated for DP, vRP/vSP, RP and DMI EP in RC.
7:0	0x5 RO	**Capability ID (CAPID):** Identifies the function as MSI capable.

47.2.44 MSICTL—Offset 92h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +92h
Offset: [B:0, D:22, F:0] +92h
Offset: [B:0, D:23, F:0] +92h

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved
8	0x1 RW/L	**Per-vector masking capable (PVM):** This bit indicates that PCI Express ports support MSI per-vector masking. **Power Well:** PRST
7	0x0 RO	**Address 64-Bit Capable (AD64C):** When set, this bit indicates that the function is capable of generating a 64-bit message address.
6:4	0x0 RW	**Multiple Message Enable (MMEN):** Only one message is supported. These bits are R/W for software compatibility.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Only one message is supported.
0	0x0 RW	**MSI Enable (MSIE):** When set, MSI is enabled and traditional interrupt pins are not used to generate interrupts.

47.2.45 MSIADDR—Offset 94h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +94h
Offset: [B:0, D:22, F:0] +94h
Offset: [B:0, D:23, F:0] +94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address:** Message address specified by the system, always DWORD aligned
1:0	0x0 RO	**RSVD0:** Reserved

47.2.46 MSIDATA—Offset 98h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +98h
Offset: [B:0, D:22, F:0] +98h
Offset: [B:0, D:23, F:0] +98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW	**Trigger Mode (TM):** • 0: Edge Triggered • 1: Level Triggered
14	0x0 RW	**Level (LVL):** if TM is 0h, then this field is a don't care. Edge triggered messages are always treated as assert messages. For level triggered interrupts, this bit reflects the state of the interrupt input if TM is 1h, then • 0: Deassert Messages • 1: Assert Messages
13:12	0x0 RW	**Future:** These bits are don't care for an IOxAPIC interrupt message data field specification.
11:8	0x0 RW	**Delivery Mode (DM):** • 0000: Fixed: Trigger Mode can be edge or level. • 0001: Lowest Priority: Trigger Mode can be edge or level. • 0010: SMI/PMI/MCA - Not supported via MSI of root port • 0011: Reserved - Not supported via MSI of root port • 0100: NMI - Not supported via MSI of root port • 0101: INIT - Not supported via MSI of root port • 0110: Reserved • 0111: ExtINT - Not supported via MSI of primary port • 1000 -1111 - Reserved
7:0	0x0 RW	**Interrupt Vector (IV):** The interrupt vector will be modified by the EIP PCIe Gen3 to provide context sensitive interrupt information for different events that require attention from the processor.

47.2.47 MSIMSK—Offset 9Ch

The MSI Mask Bit register enables software to disable message sending on a per-vector basis.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +9Ch
Offset: [B:0, D:22, F:0] +9Ch
Offset: [B:0, D:23, F:0] +9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RW	**Mask Bits (MSKB):** For each Mask bit that is set, the PCI Express port is prohibited from sending the associated message. Corresponding bits are masked if set to '1'

47.2.48 MSIPENDING—Offset A0h

The Mask Pending register enables software to defer message sending on a per-vector basis.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +A0h
Offset: [B:0, D:22, F:0] +A0h
Offset: [B:0, D:23, F:0] +A0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RO/V	**Pending Bits (PB):** For each Pending bit that is set, the PCI Express port has a pending associated message. Corresponding bits are pending if set to '1'

47.2.49 RPPMCSR—Offset A8h

bek_eip_pcie3_regs_usx16.fm bek_eip_pcie3_regs_usx8.fm bek_eip_pcie3_regs_vsp.fm cnx_eip_pcie3_regs_dmix4.fm cnx_eip_pcie3_regs_rp4px4.fm cnx_eip_pcie3_regs_rp4px16.fm cnx_eip_pcie3_regs_ep.fm cnx_eip_pcie3_regs_rldsx16.fm cdf_eip_pcie3_regs_rlusx16.fm dnv_eip_pcie3_regs_rp4px8.fm dnv_eip_pcie3_regs_rp4px16.fm dnv_eip_pcie3_regs_rp4px4.fm dnv_eip_pcie3_regs_vrp.fm

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +A8h
Offset: [B:0, D:22, F:0] +A8h
Offset: [B:0, D:23, F:0] +A8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**RSVD0:** Reserved
3:2	0x0 RW	**PME_TO_ACK Timeout (PME_TO_ACK_TO):** This timer is activated from the time the PME_Turn_Off message is sent to the link. It will be reset once the timer expires or when PME_TO_ACK has been received from the downstream device and link has been put into L2/L3 Ready state. Once the timer expires, the Sx sequence will continue to take the link down. • 00: 1 ms (default) • 01: 10 ms • 10: 1 us (Pre-Si) • 11: Disable
1:0	0x0 RO	**RSVD1:** Reserved

47.2.50 PMCSRS—Offset B0h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +B0h
Offset: [B:0, D:22, F:0] +B0h
Offset: [B:0, D:23, F:0] +B0h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/P	**PME Status (PMESTS):** This field is utilized for Software to restore the PME Status once exit Sx State. Hardware will reflect the value to the associated PMCSR.PMESTS if this bit was written by Software.
14:0	0x0 RO	**RSVD0:** Reserved

47.2.51 SMICSR—Offset C8h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +C8h
Offset: [B:0, D:22, F:0] +C8h
Offset: [B:0, D:23, F:0] +C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**RSVD0:** Reserved
18	0x0 RW/1C/V	**Hot Plug DLLSC SMI Status (HPLSCSMISTS):** This bit is set when rising edge detected as result of both SLOTSTS.DLLSCS and SMICSR.HPSMIE being set. This field will be treated as reserved for vRP.
17	0x0 RW/1C/V	**Hot Plug SMI Status (HPSMISTS):** This bit is set when rising edge detected as result of both SLOTSTS.PDCS and SMICSR.HPSMIE being set. This field will be treated as reserved for vRP.
16	0x0 RW/1C/V	**Power Management SMI Status (PMSMISTS):** This bit is set when rising edge detected as result of both ROOTSTS.PMESTS and SMICSR.PMSMIE being set.
15:2	0x0 RO	**RSVD1:** Reserved
1	0x0 RW	**Hot Plug SMI Enable (HPSMIE):** Enables the Root Port/DSP to generate SMI whenever a Hot Plug event is detected. This field will be treated as reserved for vRP.
0	0x0 RW	**Power Management SMI Enable (PMSMIE):** Enables the Root Port to generate SMI whenever a power management event is detected.

47.2.52 SCICSR—Offset CCh

The Tag field is being used to differentiate between PMSCI (Tag = '001') and HPSCI (Tag = '000') for PMC whenever a single set of Assert/Deassert SCI is sent.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +CCh
Offset: [B:0, D:22, F:0] +CCh
Offset: [B:0, D:23, F:0] +CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**RSVD0:** Reserved
18	0x0 RW/1C/V	**Hot Plug DLLSC SCI Status (HPLSCSCISTS):** This bit is set when rising edge detected as result of both SLOTSTS.DLLSCS and SCICSR.HPSCIE being set. This field will be treated as reserved for vRP.
17	0x0 RW/1C/V	**Hot Plug SCI Status (HPSCISTS):** This bit is set when rising edge detected as result of both SLOTSTS.PDCS and SCICSR.HPSCIE being set. This field will be treated as reserved for vRP.
16	0x0 RW/1C/V	**Power Management SCI Status (PMSCISTS):** This bit is set when rising edge detected as result of both ROOTSTS.PMESTS and SCICSR.PMSCIE being set.
15:2	0x0 RO	**RSVD1:** Reserved
1	0x0 RW	**Hot Plug SCI Enable (HPSCIE):** Enables the Root Port/DSP to generate SCI whenever a Hot Plug event is detected. This field will be treated as reserved for vRP.
0	0x0 RW	**Power Management SCI Enable (PMSCIE):** Enables the Root Port to generate SCI whenever a power management event is detected.

47.2.53 PBTXNCTL—Offset D8h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +D8h
Offset: [B:0, D:22, F:0] +D8h
Offset: [B:0, D:23, F:0] +D8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RW/P	**ECO31:** These register fields are of type 'RWS' and have no associated functionality currently. They are allocated for future use to add defeature capability as the need arise during tapeout/ECO netlist fixes.
17:0	0x0 RW/P	**ECO17:** These register fields are of type 'RWS' and have no associated functionality currently. They are allocated for future use to add defeature capability as the need arise during tapeout/ECO netlist fixes.

47.2.54 PLKCTL—Offset EAh

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +EAh
Offset: [B:0, D:22, F:0] +EAh
Offset: [B:0, D:23, F:0] +EAh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW/L	**Lnk Layer Capability Lock (LLCL):** Lock key bit for all RWS-L bits located in the following CSRs. VCxRCTL XPLDEF XPLDEF2 LLRBERRINJCTL RXPERRINJCTL CRCERRINJCTL CRCERRINJMSK RTRYCTL PACKTHRESH • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
1	0x0 RW/L	**Txn Layer Capability Lock (TLCL):** Lock key bit for all RWS-L bits located in XPEINJ[1:0], XPCDTHROTTLEP,N,C, XPTDEF*, MBAR01CTL EXPPTMBARCTL. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
0	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RWS-L bits (capabilities, next capability pointer, SSID/SVID, slot register, etc) bits for the function. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST

47.2.55 LTRCSR—Offset ECh

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +ECh
Offset: [B:0, D:22, F:0] +ECh
Offset: [B:0, D:23, F:0] +ECh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RW-L bits of LTRCSR and LTROVR register only. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
30:18	0x0 RO	**RSVD0:** Reserved
17	0x0 RW/1C/V	**Invalid LTR Latency Scale Value Received (IVLSVR):** Set to '1' by hardware when an LTR message is received with Not Permitted Latency Scale Value and both the LTR Mechanism Supported bit and the LTR Mechanism Enable bit are set. Cleared to '0' by software writing 1 to this register.
16	0x0 RW/1C/V	**LTR Received (LTRR):** Set to '1' by hardware when an LTR message is received and both the LTR Mechanism Supported bit and LTR Mechanism Enable bit are set. It can be set/cleared by hardware internally, or software by writing 1 to clear it.
15:4	0x0 RO	**RSVD1:** Reserved
3	0x0 RW/P	**LTR Aggregation Mode Disable (LTRAMD):** • Default is 0 to enable LTR aggregation mode. • Set 1 to disable LTR Aggregation Mode.
2	0x0 RW/L	**LTR Override Policy (LTROVRPLCY):** This register bit defines the LTR override behavior when the respective LTR Override Enable bits are set. 0: The LTR Override values will be in effect when the link is up and in D0, until a valid new LTR message is received from the device. 1: The LTR Override values will be in effect when the link is up and in D0. LTR values from the valid new LTR message received from device will be ignored. Note: This register should be programmed prior to enabling LTR override and should not be modified after LTR override has been enabled. **Power Well:** PRST
1	0x0 RW/L	**LTR No-Snoop Override Enable (LTRNSOVREN):** When this bit is set, the latency tolerance values for this port will be overridden to the values programmed in the LTRNSLOVRV, LTRNSLSOVRV and LTRNSROVR fields. The latency values from the LTR messages received from the devices will be ignored. Hardware should treat this bit as dynamic and the transition of this bit from '0' to '1' will cause a new IOSF sideband LTR message to be sent to update PMC if the new aggregated latency values change as a result of this. **Power Well:** PRST
0	0x0 RW/L	**LTR Snoop Override Enable (LTRSOVREN):** When this bit is set, the latency tolerance values for this port will be overridden to the values programmed in the LTRSLOVRV, LTRSLSOVRV and LTRSROVR fields. The latency values from the LTR messages received from the devices will be ignored. Hardware should treat this bit as dynamic and the transition of this bit from '0' to '1' will cause a new IOSF sideband LTR message to be sent to update PMC if the new aggregated latency values change as a result of this. **Power Well:** PRST

47.2.56 LTRL—Offset F0h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +F0h
Offset: [B:0, D:22, F:0] +F0h
Offset: [B:0, D:23, F:0] +F0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO/V	**LTR No-Snoop Latency Field (LTRNSLF):** This field contains the No-Snoop Latency field of the latest received LTR Message. When an LTR message is received and both the LTR Mechanism Supported bit and LTR Mechanism Enable field are set, bytes 12:13 of the PCIe header are stored in this register. This includes the case where the Latency Scale Value contains 'Not Permitted' encoding.
15:0	0x0 RO/V	**LTR Snoop Latency Field (LTRSLF):** This field contains the Snoop Latency field of the latest received LTR Message. When an LTR message is received and both the LTR Mechanism Supported bit and LTR Mechanism Enable field are set, bytes 14:15 of the PCIe header are stored in this register. This includes the case where the Latency Scale Value contains 'Not Permitted' encoding.

47.2.57 LTROVR—Offset F4h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +F4h
Offset: [B:0, D:22, F:0] +F4h
Offset: [B:0, D:23, F:0] +F4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**LTR No-Snoop Requirement Bit Override (LTRNSROVR):** This field contains the No-Snoop Requirement bit override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
30:29	0x0 RO	**RSVD0:** Reserved
28:26	0x0 RW/L	**LTR No-Snoop Latency Scale Override Value (LTRNSLSOVRV):** This field contains the Snoop latency scale override value for this particular PCIe root port. 000: LTRNSLOVRV times 1 ns 001: LTRNSLOVRV times 32 ns 010: LTRNSLOVRV times 1,024 ns 011: LTRNSLOVRV times 32,768 ns 100: LTRNSLOVRV times 1,048,576 ns 101: LTRNSLOVRV times 33,554,432 ns Others: Not Permitted. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
25:16	0x0 RW/L	**LTR No-Snoop Latency Override Value (LTRNSLOVRV):** This field contains the No-Snoop latency override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
15	0x0 RW/L	**LTR Snoop Requirement Bit Override (LTRSROVR):** This field contains the No-Snoop Requirement bit override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
14:13	0x0 RO	**RSVD1:** Reserved
12:10	0x0 RW/L	**LTR Snoop Latency Scale Override Value (LTRSLSOVRV):** This field contains the Snoop latency scale override value for this particular PCIe root port. • 000: LTRSLOVRV times 1 ns • 001: LTRSLOVRV times 32 ns • 010: LTRSLOVRV times 1,024 ns • 011: LTRSLOVRV times 32,768 ns • 100: LTRSLOVRV times 1,048,576 ns • 101: LTRSLOVRV times 33,554,432 ns • Others: Not Permitted. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
9:0	0x0 RW/L	**LTR Snoop Latency Override Value (LTRSLOVRV):** This field contains the Snoop latency override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST

47.2.58 INTXSWZCTL—Offset F8h

This register provides software the ability to swizzle the legacy interrupts (INTx) from each port and remap them to a different interrupt type for purposes of interrupt rebalancing. This swizzling only applies to inbound INTx messages that arrive on the secondary side of the switch or root port. This register does not affect PCI-Express defined INTx re-map based on device # that is required by the PCI-Express base specification. This register should be treated as reserved if not applicable to device/ project specific.

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:6, F:0] +F8h
Offset: [B:0, D:22, F:0] +F8h
Offset: [B:0, D:23, F:0] +F8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**RSVD0:** Reserved
2:0	0x0 RW/L	**INTx Swizzle (INTXSWZ):** The encoding below defines the target INTx type to which the incoming INTx message is mapped to for that port. • 000b:INTA=)INTA, INTB=)INTB, INTC=)INTC, INTD=)INTD • 001b:INTA=)INTB, INTB=)INTC, INTC=)INTD, INTD=)INTA • 010b:INTA=)INTC, INTB=)INTD, INTC=)INTA, INTD=)INTB • 011b:INTA=)INTD, INTB=)INTA, INTC=)INTB, INTD=)INTC • 100b:INTA=)INTA, INTB=)INTA, INTC=)INTA, INTD=)INTA **Power Well:** PRST

47.2.59 AERCAPCTL—Offset 118h

This register gives the status and control for ECRC checks and also the pointer to the first uncorrectable error that happened.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +118h
Offset: [B:0, D:22, F:0] +118h
Offset: [B:0, D:23, F:0] +118h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:13	0x0 RO	**RSVD0:** Reserved
12	0x0 RO	**Completion Timeout Prefix/Header Log Capable (CTPHLC):** If Set, this bit indicates that the Function records the prefix/header of Request TLPs that experience a Completion Timeout error.
11	0x0 RO/V/P	**TLP Prefix Log Present (TLPPLP):** If Set and the First Error Pointer is valid, indicates that the TLP Prefix Log register contains valid information. If Clear or if First Error Pointer is invalid, the TLP Prefix Log register is undefined.
10	0x0 RO	**Multiple Header Recording Enable (MHRE):** When set, this bit enables the function to record more than one error header.
9	0x0 RO	**Multiple Header Recording Capable (MHRC):** Supports more than one error header.
8	0x0 RW/P	**ECRC Check Enable (ECE):** When Set, ECRC checking is enabled. Functions that do not implement the associated mechanism are permitted to hardwire this bit to 0b.
7	0x0 RW/L	**ECRC Check Capable (ECC):** If Set, this bit indicates that the Function is capable of checking ECRC. **Power Well:** PRST
6	0x0 RW/P	**ECRC Generation Enable (EGE):** When Set, ECRC generation is enabled. Functions that do not implement the associated mechanism are permitted to hardwire this bit to 0b. Default value of this bit is 0b.
5	0x0 RW/L	**ECRC Generation Capable (EGC):** If Set, this bit indicates that the Function is capable of generating ECRC. **Power Well:** PRST
4:0	0x0 RO/V/P	**First Error Pointer (FEP):** This field identifies the bit position of the first error reported in the Uncorrectable Error Status Register (xref). This register re-arms itself (which does not change its current value) as soon as the error status bit indicated by the pointer is cleared by the software by writing a 1 to that status bit.

47.2.60 AERHDRLOG1—Offset 11Ch

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +11Ch
Offset: [B:0, D:22, F:0] +11Ch
Offset: [B:0, D:23, F:0] +11Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

47.2.61 AERHDRLOG2—Offset 120h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +120h
Offset: [B:0, D:22, F:0] +120h
Offset: [B:0, D:23, F:0] +120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

47.2.62 AERHDRLOG3—Offset 124h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +124h
Offset: [B:0, D:22, F:0] +124h
Offset: [B:0, D:23, F:0] +124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

47.2.63 AERHDRLOG4—Offset 128h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +128h
Offset: [B:0, D:22, F:0] +128h
Offset: [B:0, D:23, F:0] +128h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

47.2.64 ROOTERRCMD—Offset 12Ch

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +12Ch
Offset: [B:0, D:22, F:0] +12Ch
Offset: [B:0, D:23, F:0] +12Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**Fatal Error Reporting Enable (FERE):** When set, this bit enables the generation of an interrupt when a Fatal error is reported by any of the functions in the hierarchy associated with this Root Port.
1	0x0 RW	**Non-Fatal Error Reporting Enable (NFERE):** When set, this bit enables the generation of an interrupt when a Non-Fatal error is reported by any of the functions in the hierarchy associated with this Root Port.
0	0x0 RW	**Correctable Error Reporting Enable (CERE):** When set, this bit enables the generation of an interrupt when a Correctable error is reported by any of the functions in the hierarchy associated with this Root Port.

47.2.65 ROOTERRSTS—Offset 130h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +130h
Offset: [B:0, D:22, F:0] +130h
Offset: [B:0, D:23, F:0] +130h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO/V	**Advanced Error Interrupt Message Number (AEMN):** This register indicates which MSI/MSI-X vector is used for the interrupt message generated in association with any of the status bits of this Capability. For MSI, the value in this register indicates the offset between the base Message Data and the interrupt message that is generated. Hardware is required to update this field so that it is correct if the number of MSI Messages assigned to the Function changes when software writes to the Multiple Message Enable field in the MSI Message Control register. For MSI-X, the value in this register indicates which MSI-X Table entry is used to generate the interrupt message. The entry must be one of the first 32 entries even if the Function implements more than 32 entries. For a given MSI-X implementation, the entry must remain constant. For remaining fields info, please refer to PCIe Spec. for more details.
26:7	0x0 RO	**RSVD0:** Reserved
6	0x0 RW/1C/V/P	**Fatal Error Message Received (FEMR):** Reserved.
5	0x0 RW/1C/V/P	**Non-Fatal Error message Received (NFEMR):** Reserved.
4	0x0 RW/1C/V/P	**First Uncorrectable Fatal (FUF):** Reserved.
3	0x0 RW/1C/V/P	**Multiple Error Fatal/Non-Fatal Received (MEFR):** Reserved.
2	0x0 RW/1C/V/P	**Error Fatal/Non-Fatal Received (EFR):** Reserved.
1	0x0 RW/1C/V/P	**Multiple Error Correctable Error Received (MCER):** Reserved.
0	0x0 RW/1C/V/P	**Correctable Error Received (CER):** Reserved.

47.2.66 ERRSRCID—Offset 134h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +134h
Offset: [B:0, D:22, F:0] +134h
Offset: [B:0, D:23, F:0] +134h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO/V/P	**Fatal/Non-Fatal Error Source ID (EFSID):** Requester ID of the source when an Fatal or No Fatal Error is received and the Fatal Error Message Received (FEMR) or Non-Fatal Error message Received (NFEMR) bit is not already set.
15:0	0x0 RO/V/P	**Correctable Error Source ID (ECSID):** Requester ID of the source when a correctable error is received and the Correctable Error Received (CER) bit is not already set.

47.2.67 ACSCAPHDR—Offset 138h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +138h
Offset: [B:0, D:22, F:0] +138h
Offset: [B:0, D:23, F:0] +138h

Default: 0001000Dh

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW/L	**Next Capability Offset (NCO):** Contains the offset of the next structure in the Extended Capabilities. Software will need to program this field appropriately for linked capabilities list if default is not supported. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (CV):** Indicates the version of the Capability structure present.
15:0	0xd RO	**Extended Capability ID (ECID):** Identifies the function as Access Control Services capable.

47.2.68 ACSCAP—Offset 13Ch

This register identifies the Access Control Services (ACS) capabilities.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +13Ch
Offset: [B:0, D:22, F:0] +13Ch
Offset: [B:0, D:23, F:0] +13Ch

Default: 005Fh

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Egress Control Vector Size (ECVS):** Indicates the number of bits in the Egress Control Vector. This is set to 00h as ACS P2P Egress Control (ACSP2PEC) bit 5 in this register is 0b.
7	0x0 RO	**RSVD0:** Reserved
6	0x1 RO	**ACS Direct Translated P2P (TACSDTP2P):** Indicates that the component does implement ACS Direct Translated P2P. Required for Root Ports that support Address Translation Services (ATS) and also support peer-to-peer traffic with other Root Ports, required for Switch Downstream Ports,
5	0x0 RO	**ACS P2P Egress Control (EACSP2PEC):** Hardwired to 0. Indicates that the component does not implement ACS P2P Egress Control.
4	0x1 RO	**ACS Upstream Forwarding (UACSUF):** Indicates that the component implements ACS Upstream Forwarding.
3	0x1 RO	**ACS P2P Completion Redirect (CACSP2PRR):** Indicates that the component implements ACS P2P Completion Redirect. This includes Read Completions, AtomicOp Completions, and other Completions, either with or without data.
2	0x1 RO	**ACS P2P Request Redirect (RACSP2PRR):** Indicates that the component implements ACS P2P Request Redirect.
1	0x1 RO	**ACS Translation Blocking (BACSTB):** Indicates that the component implements ACS Translation Blocking.
0	0x1 RO	**ACS Source Validation (VACSSV):** Indicates that the component implements ACS Source Validation.

47.2.69 ACSCTL—Offset 13Eh

This register identifies the Access Control Services (ACS) control bits.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +13Eh
Offset: [B:0, D:22, F:0] +13Eh
Offset: [B:0, D:23, F:0] +13Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:7	0x0 RO	**RSVD0:** Reserved
6	0x0 RW	**ACS Direct Translated P2P Enable (TACSP2PECE):** When Set, overrides the ACS P2P Request Redirect and ACS P2P Egress Control mechanisms with peer-to-peer Memory Requests whose Address Translation (AT) field indicates a Translated address This bit is ignored if ACS Translation Blocking (B) is enabled.
5	0x0 RO	**ACS P2P Egress Control Enable (EACSP2PECE):** This is hardwired to 0b as the component does not implement ACS P2P Egress Control.
4	0x0 RW	**ACS Upstream Forwarding Enable (UACSUFE):** When set, the component forwards upstream any Request or Completion TLPs it receives that were redirected upstream by a component lower in the hierarchy. Note that the U bit only applies to upstream TLPs arriving at a Downstream Port, and whose normal routing targets the same Downstream Port.
3	0x0 RW	**ACS P2P Completion Redirect Enable (CACSP2PCRE):** Determines when the component redirects peer-to-peer Completions upstream, applicable only to Read Completions whose Relaxed Ordering Attribute is clear.
2	0x0 RW	**ACS P2P Request Redirect Enable (RACSP2PRRE):** This bit determines when the component redirects peer-to-peer Requests upstream.
1	0x0 RW	**ACS Translation Blocking Enable (BACSTBE):** When set, the component blocks all upstream Memory Requests whose Address Translation (AT) field is not set to the default value.
0	0x0 RW	**ACS Source Validation Enable (VACSSVE):** When set, the component validates the Bus Number from the Requester ID of upstream Requests against the secondary / subordinate Bus Numbers.

47.2.70 XPTDEF—Offset 2DCh

Lock Key bit is located in the Personality Lock Key Control Register (PLKCTL.TLCL).

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +2DCh
Offset: [B:0, D:22, F:0] +2DCh
Offset: [B:0, D:23, F:0] +2DCh

Default: 00008000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**RSVD0:** Reserved
29	0x0 RW/P/L	**Internal Sideband Error Message Disable (SBEMSGD):** This bit when set to 1b will disable the generation of the internal sideband message, thus losing some of the error logging capability. It is used to avoid deadlocks on internal sideband bus (if one is discovered).
28:27	0x0 RO	**RSVD1:** Reserved
26	0x0 RW/P/L	**Tx Quick Data Credit Return Override (TXQDCRO):** On the IOSF interface, the data for a TLP is required to be sent in back to back clocks after the request is granted. The design is parameterized to either return data credits on each data queue read for the amount of data read, or return all data credits for a TLP when it is granted, assuming that the returned credits cannot be reused before all the data is read out. This bit switches the mode that the data credits are returned. If the design is compiled with the parameter set to return all credits at once, setting this bit will cause each data queue read to return the credits for the amount of data read from the queue (Tx).
25	0x0 RW/P/L	**Rx Quick Data Credit Return Override (RXQDCRO):** On the IOSF interface, the data for a TLP is required to be sent in back to back clocks after the request is granted. The design is parameterized to either return data credits on each data queue read for the amount of data read, or return all data credits for a TLP when it is granted, assuming that the returned credits cannot be reused before all the data is read out. This bit switches the mode that the data credits are returned. If the design is compiled with the parameter set to return all credits at once, setting this bit will cause each data queue read to return the credits for the amount of data read from the queue (Rx).
24	0x0 RO	**RSVD2:** Reserved
23:21	0x0 RW/P/L	**IDF Master Request Throttle Flow (IDFMRTFCCSEL):** This field selects which traffic (flow) class to throttle. Setting this bit causes the IDF Master to only issue a single request at a time (non-pipeline mode) regardless of the fabric advertised credits. These bits are independent of each other. • xx1: Posted • x1x: Non-Posted • 1xx: Completion • 111: Any traffic class. ***Note:*** '111' would limit all traffic (flow) classes to a single credit, i.e. each flow class would have a single request credit without sharing a single credit across all flow classes.
20	0x0 RO	**RSVD3:** Reserved
19:17	0x0 RW/P/L	**IOSF Master Request Throttle Flow Control Class Select (IMRTFCCSEL):** This field selects which flow control class to throttle. Setting this bit causes the IOSF(CPT/PPF/SWF) Master to only issue a single request at a time (non-pipeline mode) regardless advertised credits by fabric. • These bits are independent of each other. • xx1: Posted • x1x: Non-Posted • 1xx: Completion • 111: Any flow control class ***Note:*** '111' would limit all flow classes to a single credit, i.e. each flow class would have a single request credit without sharing a single credit across all flow classes.
16	0x0 RO	**RSVD4:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
15	0x1 RW/P/L	**Disable Inbound Peer to Peer Configuration (DIS_INB_P2PCFG):** This bit is actually a disable of type1 configuration upstream. This bit is used for controlling configuration request accesses through the PCI-Express port (security feature) for Type1 Configuration access upstream direction, Type0 will still get UR'd. • 1: Upstream type1 configuration accesses will be Master Aborted by IP. • 0: Allows Upstream type1 configuration access. This register bit is of type 'write once' and is controlled by BIOS/special initialization firmware and applies only to upstream type1 configuration. The default value is to disable upstream type1 configuration access.
14	0x0 RW/P/L	**Config Type 1 Check Disable (CFGT1CD):** This bit controls the Express Port's type1 configuration check in both direction. This bit applies only if DIS_INB_P2PCFG is clear. Setting this bit bypasses all type1 configuration checks and forwards the type1 configuration instead of UR. This bit does not apply type1 configuration targeting the IP, which follows the proper check. This is not applicable to NTB.
13	0x0 RW/P/L	**MSG Route by ID Disable (MSGRIDCD):** This bit controls the Express Port's message Route by ID check in both direction. Setting this bit bypasses messages route by ID checks and forwards the message instead of UR/Drop. This bit does not apply messages targeting the IP, which follows the proper check. This is not applicable to NTB.
12	0x0 RW/P/L	**Completion Check Disable (CCD):** This bit controls the Express Port's completion check (Requester ID/Transaction ID) in both direction. Setting this bit bypasses all completion checks based and forwards the completion instead of unexpected completion check. This bit does not apply completion targeting the IP, which follows the proper check. This is not applicable to NTB and Root Ports.
11	0x0 RW/P/L	**ISA Check Disable (ISACD):** This bit controls the Express Port's ISA IO region check in both direction. Setting this bit bypasses ISA IO decode checks and forwards access instead of UR. ISA region check (ISACD) is don't care when bit 9 (IOCD) is set. This is not applicable to NTB.
10	0x0 RW/P/L	**VGA Check Disable (VGACD):** This bit controls the Express Port's VGA Memory and IO check in upstream direction only. Setting this bit bypasses upstream VGA Memory and IO decode checks and forwards the VGA access upstream instead of UR. VGA Memory checks are don't care when bit 8 (MCD) is set, while VGA IO check is a don't care when bit 9 (IOCD) is set. This is not applicable to NTB.
9	0x0 RW/P/L	**IO Check Disable (IOCD):** This bit controls the Express Port's IO check in both direction. Setting this bit bypasses all IO decode checks based on base/limit or BAR registers and forwards the IO access. This bit does not apply for any IO region decoded for IP's internal resources. IO txn) 64K will be UR'd when this bit is set. This is not applicable to NTB.
8	0x0 RW/P/L	**Memory Check Disable (MCD):** This bit controls the Express Port's Memory check in both direction. Setting this bit bypasses all memory decode checks based on base/limit or BAR registers and forwards the memory access. This bit does not apply for any memory region decoded for IP's internal resources. This is not applicable to NTB.
7	0x0 RW/P/L	**Reserved ECO 7 (RECO7):** This field is reserved for ECO purpose.
6:5	0x0 RW/P/L	**Store Forward Override (SFO):** These bits are used to override the store forward of TLPs through the transmit queue. One bit enables the override and the other bit selects whether to force store-forwarding on or off. Note that store-forward on is safer in all cases, but impacts latency. If they clock frequencies are known such that store forwarding is not needed, it can be overridden here. • 0x - No override. • 10 - Force store forward disable. • 11 - Force store forward enable.
4:0	0x0 RW/P/L	**Reserved ECO 0 (RECO0):** This field is reserved for ECO purpose.

47.2.71 XPTDEF2—Offset 2E0h

Lock Key bit is located in the Personality Lock Key Control Register (PLKCTL.TLCL).

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:6, F:0] +2E0h
Offset: [B:0, D:22, F:0] +2E0h
Offset: [B:0, D:23, F:0] +2E0h

Default: 00001D00h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**MSI Address Violation Status (MSIAVS):** MSI address violation check status that does not target 0xFEEx_xxxx while MSIAVCD is not being set. This is only valid for RPs usage.
30:19	0x0 RW/P/L	**Reserved ECO (RECO):** This field is reserved for ECO purpose.
18	0x0 RW/P/L	**Hold Retrain during Surprise Removal Disable (HRSRD):** For Surprise Removal, EIP RPs will not allow retrain to occur until the SLOTSTS.PDCS bit has been cleared by software for the removal event. This bit is to disable the above behavior and allow the retrain to occur. This field is only applicable to RPs and should be treated as reserved for other devices.
17	0x0 RW/P/L	**ECRC Malformed Error Precedence Disable (ECRCMFEPD):** This bit changes the error precedence if a TLP has both a ECRC error and is malform. • When this bit is set to 1, the packet will be logged as an ECRC error. • When set to 0, the packet will be logged as a malform TLP, which is compliant to the PCIe spec errata. Only the type of error logged is affected. If the TLP is malform, it will be dropped with no credit return. If there is only an ECRC error detected on a packet, it will be dropped and credits will be returned per PCI-SIG Errata.
16	0x0 RW/P/L	**MSI Address Violation Check Disable (MSIAVCD):** Disable MSI address violation check that does not target 0xFEEx_xxxx. This is only valid for RPs usage.
15	0x0 RW/P/L	**Force Downstream Relaxed Order (FORCERODN):** Forces all downstream completions to follow relaxed ordering rules. This allows downstream completions to pass downstream posted requests. Note that setting this bit breaks the producer consumer model when the data is in the address space below the port and the flag is in the address space outside the port, because the read of the flag will not push the data writes down the port. The belief is that usage model is not used.
14	0x0 RW/P/L	**Downstream Relaxed Order Disable (DNRODIS):** Disables the ability of downstream relaxed ordered completions from passing posted requests in the same direction.
13	0x0 RW/P/L	**Upstream Relaxed Order Disable (UPRODIS):** Disables the ability of upstream relaxed ordered completions from passing posted requests in the same direction.
12	0x1 RW/P/L	**IOSF tdparity check disable (TDPAR_CHK_DIS):** When set this bit disables the data parity check for incoming data into the IOSF Target block. The logic will ignore the data parity bit and will operate as though the parity bit did not exist. No errors will be logged and good DW based parity will be written into the data queue.
11	0x1 RW/P/L	**IOSF tcparity check disable (TCPAR_CHK_DIS):** When set this bit disables the command parity check for incoming commands into the IOSF Target block. The logic will ignore the command parity bit and will operate as though the parity bit did not exist. No errors will be logged and good DW based parity will be written into the header queue.
10	0x1 RW/P/L	**MCTP Message Bus Number Check Enable (MMBNCE):** When set, if the Requester ID bus number of an MCTP message request received on the PCIe link does not fall within the range between SCBN and SBBN, the MCTP message will be silently discarded.
9	0x0 RW/P/L	**Completion credit advertisement enable (CPLCDT_EN):** Endpoints are required to advertise infinite completion credits. Setting this defeature bit breaks that rule and enables the advertisement of non-infinite completion credits and flow control updates for completion credits. This is only valid for project specific

Bit Range	Default & Access	Field Name (ID): Description
8	0x1 RW/P/L	**Enable Virtual Port IDs (EVPID):** • 1: Enables SB Virtual Port ID mode with allocated VPIDs which is associated with ports for all the egress INTx and LTR messages based on project specific. We will assign (N-1) virtual sideband PortID's to associate with the physical PortID which is port 0. The physical one is the same one as being assigned by the router as we have now, and would be used for all non-INTx messages and INTx messages from port 0. However, the VPIDs would be used for INTx messages routing from port(N-1:1), respectively. This allows all INTx from N ports to be forwarded to the ILB accordingly, so ILB can differentiate the source of the INTx message. • 0: Normal operation with single SB Port ID per cluster for INTx delivery. This is only valid for project specific with multi root ports.
7	0x0 RW/P/L	**Enable Receive Completion Ordering (ERCO):** The default ordering is to allow received completions to pass received posted requests to avoid receiver overflow conditions if posted requests cannot be processed. Setting this bit will enable PCI Express ordering for completions, preventing completions from passing posted requests. This is only valid for project specific
6	0x0 RW/P/L	**Enable MSI Generation Override (MSIGENOV):** • 1: Enables Root Port MSI generation override even if PCICMD.BME = 0 for the root port device as required by PCI Express specification. • 0: Normal operation for Root Port behavior. If PCICMD.BME = 0, the root port will not generate a MSI. This is only valid for project specific .
5	0x0 RW/P/L	**Completion Combining Disable (CPLCOMBINE_D):** When a larger read request is split into smaller read requests, the completions for the small requests may be opportunistically combined into larger completions to enable higher bandwidth and link utilization, as long as packet formation rules are not violated. This bit disables the port from combining completions. This is only valid for project specific .
4	0x0 RW/P/L	**Config Retry Disable (CRD):** Setting this bit disables the re-issuing of a configuration request if the request is completed with a configuration retry status (CRS). The completion with CRS will be returned to the requestor.
3	0x0 RW/P/L	**Optional Unexpected Completion Check Disable (UCCHKD):** Setting this bit disables some optional unexpected checks on completions. Specifically, it disables the checking on the byte count and lower address fields.
2	0x0 RW/P/L	**MCTP Disable Bus Check (MCTPDBC):** Setting this bit will disable the Bus 0 check for all MCTP VDM Type1 messages. The check is enabled by default as following: • Upstream - ReqBus =/= 0 • Downstream - TgtBus =/= 0
1	0x0 RW/P/L	**Reserved ECO 1 (RECO1):** This field is reserved for ECO purpose.
0	0x0 RW/P/L	**Global Stop Disable (GBLSTOPD):** When the design detects an uncorrectable internal error, a stop signal in the design asserts, blocking the processing of transactions in both directions in the transaction layer. Setting this bit, disables the stop mechanism, allowing the transactions to proceed as if no error occurred.

47.2.72 IOSFDEVCLKGCTL—Offset 2E4h

It is included for DMI in RC as an extension of Rootport definition.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +2E4h
Offset: [B:0, D:22, F:0] +2E4h
Offset: [B:0, D:23, F:0] +2E4h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block controls the delay before going into IDLE. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

47.2.73 SBDEVCLKGCTL—Offset 2E6h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:6, F:0] +2E6h
Offset: [B:0, D:22, F:0] +2E6h
Offset: [B:0, D:23, F:0] +2E6h

Default: 8010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x1 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

47.2.74 IDFDEVCLKGCTL—Offset 2E8h

The IDF Device Clock Gate control register is defined only for the Virtual Root port/ Switch Port.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:6, F:0] +2E8h
Offset: [B:0, D:22, F:0] +2E8h
Offset: [B:0, D:23, F:0] +2E8h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

§ §

48 PCI Express Root Ports - B0, D(9-12, 14-17), F0

48.1 Introduction and Index

The host-accessible registers for the PCI Express Root Ports are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

48.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device (9-12, 14-17) (decimal), Function 0. The offset addresses are listed.

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 1 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"VID—Offset 0h" on page 1600
2	2	19A4	"DID—Offset 2h" on page 1600
4	2	0000	"PCICMD—Offset 4h" on page 1601
6	2	0010	"PCISTS—Offset 6h" on page 1602
8	1	00	"RID—Offset 8h" on page 1603
9	3	060400	"CCR—Offset 9h" on page 1603
C	1	00	"CLS—Offset Ch" on page 1604
D	1	00	"PLAT—Offset Dh" on page 1604
E	1	01	"HDR—Offset Eh" on page 1604
F	1	00	"BIST—Offset Fh" on page 1605
18	1	00	"PRIBUS—Offset 18h" on page 1605
19	1	00	"SECBUS—Offset 19h" on page 1606
1A	2	00	"SUBBUS—Offset 1Ah" on page 1606
1C	1	00	"IOBASE—Offset 1Ch" on page 1607
1D	1	00	"IOLIMIT—Offset 1Dh" on page 1607
1E	2	0000	"SECSTS—Offset 1Eh" on page 1608
20	2	0000	"MEMBASE—Offset 20h" on page 1609
22	2	0000	"MEMLIMIT—Offset 22h" on page 1610
24	2	0001	"PFBASE—Offset 24h" on page 1611
26	2	0001	"PFLIMIT—Offset 26h" on page 1612
28	4	00000000	"PFBASEU—Offset 28h" on page 1612
2C	4	00000000	"PFLIMITU—Offset 2Ch" on page 1613
34	1	40	"CAPPTR—Offset 34h" on page 1613
3C	1	00	"INTL—Offset 3Ch" on page 1614
3D	1	01	"INTP—Offset 3Dh" on page 1614
3E	2	0000	"BCTL—Offset 3Eh" on page 1615
40	2	8010	"EXPCAPLST—Offset 40h" on page 1617
42	2	0042	"EXPCAPLST—Offset 40h" on page 1617
44	4	00008021	"DEVCAP—Offset 44h" on page 1618
48	2	2000	"DEVCTL—Offset 48h" on page 1619
4A	2	0000	"DEVSTS—Offset 4Ah" on page 1620
4C	4	09794883	"LINKCAP—Offset 4Ch" on page 1621
50	2	0000	"LINKCTL—Offset 50h" on page 1623
52	2	1001	"LINKSTS—Offset 52h" on page 1625
54	4	00000000	"SLOTCAP—Offset 54h" on page 1626
58	2	03C0	"SLOTCTL—Offset 58h" on page 1628

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 2 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
5A	2	0040	"SLOTSTS—Offset 5Ah" on page 1630
5C	2	0000	"ROOTCTL—Offset 5Ch" on page 1632
5E	2	0001	"ROOTCAP—Offset 5Eh" on page 1633
60	4	00000000	"ROOTSTS—Offset 60h" on page 1633
64	4	00000437	"DEVCAP2—Offset 64h" on page 1634
68	2	0000	"DEVCTL2—Offset 68h" on page 1637
6C	4	0000000E	"LINKCAP2—Offset 6Ch" on page 1639
70	2	0003	"LINKCTL2—Offset 70h" on page 1640
72	2	0000	"LINKSTS2—Offset 72h" on page 1642
80	2	8801	"PMCAPLST—Offset 80h" on page 1642
82	2	C803	"PMCAPLST—Offset 80h" on page 1642
84	2	0008	"PMCSR—Offset 84h" on page 1644
86	2	00	"PMBSE—Offset 86h" on page 1644
88	2	900D	"SSCAPLST—Offset 88h" on page 1645
8C	2	8086	"SSVID—Offset 8Ch" on page 1646
8E	2	0000	"SSID—Offset 8Eh" on page 1646
90	2	0005	"MSICAPLST—Offset 90h" on page 1646
92	2	0100	"MSICTL—Offset 92h" on page 1647
94	4	00000000	"MSIADDR—Offset 94h" on page 1647
98	4	00000000	"MSIDATA—Offset 98h" on page 1648
9C	4	00000000	"MSIMSK—Offset 9Ch" on page 1649
A0	4	00000000	"MSIPENDING—Offset A0h" on page 1649
A8	4	00000020	"RPPMCSR—Offset A8h" on page 1650
B0	2	0000	"PMCSRS—Offset B0h" on page 1652
C0	4	00000000	"PPBIFCTL—Offset C0h" on page 1652
C8	4	00000000	"SMICSR—Offset C8h" on page 1653
CC	4	00000000	"SCICSR—Offset CCh" on page 1654
D0	2	0000	"SSCTL—Offset D0h" on page 1655
D2	2	0000	"EXPPTMBARCTL—Offset D2h" on page 1656
D4	4	00000000	"PPD0—Offset D4h" on page 1657
D8	4	00000000	"PBTXNCTL—Offset D8h" on page 1659
E0	4	00000000	"PBPHYCTL—Offset E0h" on page 1660
EA	2	0000	"PLKCTL—Offset EAh" on page 1660
EC	4	00000000	"LTRCSR—Offset ECh" on page 1661
F0	4	00000000	"LTRL—Offset F0h" on page 1662
F4	4	00000000	"LTROVR—Offset F4h" on page 1663
F8	1	00	"INTXSWZCTL—Offset F8h" on page 1664
FC	4	00000000	"CFGAGTERR—Offset FCh" on page 1665
100	4	13810001	"AERCAPHDR—Offset 100h" on page 1666
104	4	00000000	"ERRUNCSTS—Offset 104h" on page 1667

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 3 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
108	4	04400000	"ERRUNCMSK—Offset 108h" on page 1669
10C	4	00462030	"ERRUNCSEV—Offset 10Ch" on page 1671
110	4	00000000	"ERRCORSTS—Offset 110h" on page 1673
114	4	0000E000	"ERRCORMSK—Offset 114h" on page 1674
118	4	00001000	"AERCAPCTL—Offset 118h" on page 1675
11C	4	00000000	"AERHDRLOG1—Offset 11Ch" on page 1676
120	4	00000000	"AERHDRLOG2—Offset 120h" on page 1676
124	4	00000000	"AERHDRLOG3—Offset 124h" on page 1676
128	4	00000000	"AERHDRLOG4—Offset 128h" on page 1677
12C	4	00000000	"ROOTERRCMD—Offset 12Ch" on page 1677
130	4	00000000	"ROOTERRSTS—Offset 130h" on page 1678
134	4	00000000	"ERRSRCID—Offset 134h" on page 1679
138	4	1501000D	"ACSCAPHDR—Offset 138h" on page 1679
13C	2	005F	"ACSCAPHDR—Offset 138h" on page 1679
13E	2	0000	"ACSCTL—Offset 13Eh" on page 1681
140	4	04000000	"ERRUNCDETMSK—Offset 140h" on page 1682
144	4	00000000	"ERRCORDETMSK—Offset 144h" on page 1683
148	4	00000000	"ROOTERRDETMSK—Offset 148h" on page 1683
150	4	18010012	"MCSTCAPHDR—Offset 150h" on page 1684
154	2	000F	"MCSTCAPHDR—Offset 150h" on page 1684
156	2	0000	"MCSTCTL—Offset 156h" on page 1684
158	4	0000000C	"MCSTBAR—Offset 158h" on page 1685
15C	4	00000000	"MCSTUBAR—Offset 15Ch" on page 1685
160	4	00000000	"MCSTRCV—Offset 160h" on page 1685
168	4	00000000	"MCSTBLKALL—Offset 168h" on page 1686
178	4	00000000	"MCSTOLBAR—Offset 178h" on page 1686
17C	4	00000000	"MCSTUOLBAR—Offset 17Ch" on page 1686
180	4	1901000B	"EINJCAPHDR—Offset 180h" on page 1687
184	4	00A00003	"EINJHDR—Offset 184h" on page 1687
188	2	0000	"EINJCTL—Offset 188h" on page 1688
200	4	00010019	"SECEXPCAP—Offset 200h" on page 1689
204	4	00000000	"LINKCTL3—Offset 204h" on page 1690
208	4	00000000	"LANEERRSTS—Offset 208h" on page 1691
20C	2	0000	"LANEEQCTL0—Offset 20Ch" on page 1692
20E	2	0000	"LANEEQCTL1—Offset 20Eh" on page 1694
210	2	0000	"LANEEQCTL2—Offset 210h" on page 1696
212	2	0000	"LANEEQCTL3—Offset 212h" on page 1698
214	2	0000	"LANEEQCTL4—Offset 214h" on page 1700
216	2	0000	"LANEEQCTL5—Offset 216h" on page 1702
218	2	0000	"LANEEQCTL6—Offset 218h" on page 1704

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 4 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
21A	2	0000	"LANEEQCTL7—Offset 21Ah" on page 1706
280	4	00000000	"XPPMDL0—Offset 280h" on page 1708
284	4	00000000	"XPPMDL1—Offset 284h" on page 1708
288	4	FFFFFFFF	"XPPMCL0—Offset 288h" on page 1708
28C	4	FFFFFFFF	"XPPMCL1—Offset 28Ch" on page 1708
290	2	0000	"XPPMDH—Offset 290h" on page 1709
292	2	0F0F	"XPPMCH—Offset 292h" on page 1709
294	4	00000000	"XPPMR0—Offset 294h" on page 1710
298	4	00000000	"XPPMR1—Offset 298h" on page 1713
29C	4	00000000	"XPPMEVL0—Offset 29Ch" on page 1716
2A0	4	00000000	"XPPMEVL1—Offset 2A0h" on page 1718
2A4	4	00000000	"XPPMEVH0—Offset 2A4h" on page 1720
2A8	4	00000000	"XPPMEVH1—Offset 2A8h" on page 1721
2AC	4	00000000	"XPPMER0—Offset 2ACh" on page 1722
2B0	4	00000000	"XPPMER1—Offset 2B0h" on page 1724
2B4	4	00000000	"XPPMDFXMAT0—Offset 2B4h" on page 1726
2B8	4	00000000	"XPPMDFXMAT1—Offset 2B8h" on page 1727
2BC	4	00000000	"XPPMDFXMSK0—Offset 2BCh" on page 1728
2C0	4	00000000	"XPPMDFXMSK1—Offset 2C0h" on page 1728
2C4	4	00000000	"XPPERFCON—Offset 2C4h" on page 1729
2C8	1	00	"XPPERFSTAT—Offset 2C8h" on page 1730
2D0	4	00000000	"XPCDTHROTTLEP—Offset 2D0h" on page 1730
2D4	4	00000000	"XPCDTHROTTLEN—Offset 2D4h" on page 1731
2D8	4	00000000	"XPCDTHROTTLEC—Offset 2D8h" on page 1731
2E4	2	0010	"IOSFDEVCLKGCTL—Offset 2E4h" on page 1732
2E6	2	8010	"SBDEVCLKGCTL—Offset 2E6h" on page 1732
300	4	0001000B	"VDHDRCAP—Offset 300h" on page 1733
304	4	2A800001	"IBSTHDRCAP—Offset 304h" on page 1733
310	4	00000007	"IBSTENGLKSPDCAP—Offset 310h" on page 1734
314	4	00000000	"IBSTENGLKSPDCTL—Offset 314h" on page 1735
31C	4	00000000	"IBSTENGLKTXRXCFG—Offset 31Ch" on page 1736
320	4	00000000	"IBSTERRCRCSTS0—Offset 320h" on page 1736
324	4	00000000	"IBSTERRRCRVSTS0—Offset 324h" on page 1737
328	4	00000000	"IBSTERRCRCSTS1—Offset 328h" on page 1737
32C	4	00000000	"IBSTERRRCRVSTS1—Offset 32Ch" on page 1738
330	4	00000000	"IBSTERRCRCSTS2—Offset 330h" on page 1738
334	4	00000000	"IBSTERRRCRVSTS2—Offset 334h" on page 1739
338	4	00000000	"IBSTERRCRCSTS3—Offset 338h" on page 1739
33C	4	00000000	"IBSTERRRCRVSTS3—Offset 33Ch" on page 1740
344	4	00400000	"IBSTPHYLCTL0—Offset 344h" on page 1741

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 5 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
348	4	00400000	"IBSTPHYLCTL1—Offset 348h" on page 1742
34C	4	00400000	"IBSTPHYLCTL2—Offset 34Ch" on page 1743
350	4	00400000	"IBSTPHYLCTL3—Offset 350h" on page 1744
354	4	00000000	"IBSTTXLCTL—Offset 354h" on page 1745
358	4	00000000	"IBSTTDSTS—Offset 358h" on page 1745
36C	4	00000000	"IBSTPLLNSTS0—Offset 36Ch" on page 1746
370	4	FFFFFFFF	"IBSTPRECFG0—Offset 370h" on page 1747
374	4	FFFFFFFF	"IBSTPOSTCFG0—Offset 374h" on page 1748
378	4	00000000	"IBSTPLLNSTS1—Offset 378h" on page 1749
37C	4	FFFFFFFF	"IBSTPRECFG1—Offset 37Ch" on page 1750
380	4	FFFFFFFF	"IBSTPOSTCFG1—Offset 380h" on page 1751
8E0	2	001F	"TLPCIECLKGCTL—Offset 8E0h" on page 1751
8E2	2	0055	"TLPCIECLKGCCTL—Offset 8E2h" on page 1752
8E4	2	0010	"PT0TXNCLKGCTL—Offset 8E4h" on page 1752
8E6	2	0010	"PT1TXNCLKGCTL—Offset 8E6h" on page 1753
8E8	2	0010	"PT2TXNCLKGCTL—Offset 8E8h" on page 1753
8EA	2	0010	"PT3TXNCLKGCTL—Offset 8EAh" on page 1754
8F8	4	00001D00	"XPTDEF2—Offset 8F8h" on page 1755
948	4	00000306	"PMIDLTMR—Offset 948h" on page 1757
98C	4	00000000	"LLRBSIZE—Offset 98Ch" on page 1758
99C	2	0000	"FRMERRMSK—Offset 99Ch" on page 1759
99E	2	0000	"FRMERRSTS—Offset 99Eh" on page 1760
9E0	2	001F	"LLPCIECLKGCTL—Offset 9E0h" on page 1760
9E2	2	0055	"LLPCIECLKGCCTL—Offset 9E2h" on page 1761
9E4	2	0010	"PT0LNKCLKGCTL—Offset 9E4h" on page 1761
9E6	2	0010	"PT1LNKCLKGCTL—Offset 9E6h" on page 1762
9E8	2	0010	"PT2LNKCLKGCTL—Offset 9E8h" on page 1762
9EA	2	0010	"PT3LNKCLKGCTL—Offset 9EAh" on page 1763
9EC	2	0010	"CFGPCIECLKGCTL—Offset 9ECh" on page 1763
9EE	2	0001	"CFGPCIECLKGCCTL—Offset 9EEh" on page 1763
A68	4	00000000	"LTSSMSMSTS—Offset A68h" on page 1764
A70	4	00000000	"LTSSMLNSTS0—Offset A70h" on page 1765
A80	4	00000000	"LTSSMSTATELOG0—Offset A80h" on page 1765
A84	4	00000000	"LTSSMSTATELOG1—Offset A84h" on page 1765
A88	4	00000000	"LTSSMSTATELOG2—Offset A88h" on page 1766
A8C	4	00000000	"LTSSMSTATELOGCTL—Offset A8Ch" on page 1766
A94	2	0000	"LTLNERRCTRL—Offset A94h" on page 1766
A96	2	0000	"LTLNERRSTS—Offset A96h" on page 1767
A98	4	00000000	"LTLNERRLOG—Offset A98h" on page 1768
AB8	4	00000000	"UPCFGCSR—Offset AB8h" on page 1769

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 6 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
AC8	4	00025A4E	"SOSCTL—Offset AC8h" on page 1770
ACC	4	00000000	"G3SOSERRSTS—Offset ACCh" on page 1770
AE0	2	001F	"PLPCIECLKGCTL—Offset AE0h" on page 1770
AE2	2	0055	"PLPCIECLKGCCTL—Offset AE2h" on page 1771
AE4	2	0010	"PT0PHYCLKGCTL—Offset AE4h" on page 1771
AE6	2	0010	"PT1PHYCLKGCTL—Offset AE6h" on page 1772
AE8	2	0010	"PT2PHYCLKGCTL—Offset AE8h" on page 1772
AEA	2	0010	"PT3PHYCLKGCTL—Offset AEAh" on page 1773
B00	4	36000000	"LTLGCAP—Offset B00h" on page 1773
B04	4	00321000	"LTLGCTRL—Offset B04h" on page 1774
B08	4	00000001	"LTLGSTART0—Offset B08h" on page 1775
B0C	4	00000001	"LTLGSTART1—Offset B0Ch" on page 1776
B10	4	00000001	"LTLGSTART2—Offset B10h" on page 1777
B14	4	00000001	"LTLGSTART3—Offset B14h" on page 1778
B18	4	1E000009	"LTLGSTP0—Offset B18h" on page 1779
B1C	4	1E000009	"LTLGSTP1—Offset B1Ch" on page 1779
B20	4	1E000009	"LTLGSTP2—Offset B20h" on page 1780
B24	4	1E000009	"LTLGSTP3—Offset B24h" on page 1780
B28	4	00000000	"LTLGTMEV0—Offset B28h" on page 1781
B2C	4	00000000	"LTLGTMEV1—Offset B2Ch" on page 1782
B30	4	00000000	"LTLGTMEV2—Offset B30h" on page 1783
B34	4	00000000	"LTLGTMEV3—Offset B34h" on page 1784
B40	4	00000000	"LTLGRDCT—Offset B40h" on page 1784
B44	4	FFFFFFFF	"LTLGRES—Offset B44h" on page 1785
B48	4	00000000	"LTLGSMEV0—Offset B48h" on page 1785
B4C	4	00000000	"LTLGSMEV1—Offset B4Ch" on page 1786
B50	4	00FFFFFF	"NFTSCOMCLK—Offset B50h" on page 1786
B54	4	00FFFFFF	"NFTSDSCCLK—Offset B54h" on page 1787
B58	4	2000FFFF	"LEKBERR—Offset B58h" on page 1787
B5C	4	FFFFFFFF	"EXPBERR0—Offset B5Ch" on page 1787
B60	4	02000007	"EXPBERR1—Offset B60h" on page 1788
B64	4	00000000	"LEKBPROERR—Offset B64h" on page 1788
B68	4	02001821	"SPEEDCTL—Offset B68h" on page 1789
B6C	4	00000000	"RCVRDETSTS—Offset B6Ch" on page 1791
B70	4	00000000	"RCVRERR—Offset B70h" on page 1791
B74	4	00000000	"EBERR—Offset B74h" on page 1792
B78	4	00000000	"EBERRMSK—Offset B78h" on page 1792
B7C	4	00000000	"OBEINJCTL—Offset B7Ch" on page 1793
B80	4	00000000	"LTSSMERRSTS0—Offset B80h" on page 1795
B84	4	00000000	"LTSSMERRSTS1—Offset B84h" on page 1797

Table 48-1. Summary of PCI Configuration Registers—0/9-12, 14-17/0 (Sheet 7 of 7)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
B8C	4	04904623	"EQEVALCTL6—Offset B8Ch" on page 1798
B90	4	000000FF	"EQEVALCTL7—Offset B90h" on page 1799
B9C	4	00000000	"EQFARFSLF—Offset B9Ch" on page 1800
BA4	4	03046820	"FOMINCCTL—Offset BA4h" on page 1801
BA8	4	0000000C	"PHYRECAL—Offset BA8h" on page 1801
BAC	4	00000100	"PLLSTBYCTL—Offset BACh" on page 1802
BB0	4	078A0000	"PLUTXEQCTL—Offset BB0h" on page 1802
BB4	4	00000000	"PHYCGIDLEMSK—Offset BB4h" on page 1803
BB8	4	64320000	"EQEVALCTL4—Offset BB8h" on page 1804
BBC	4	3A87F003	"EQEVALCTL5—Offset BBCh" on page 1805
BC0	4	00000000	"LEKBLNERRCNT0—Offset BC0h" on page 1805
BC4	4	00000000	"LEKBLNERRCNT1—Offset BC4h" on page 1806
BD0	4	00080808	"EQEVALCTL6—Offset B8Ch" on page 1798
BD4	4	0000FF55	"EQEVALCTL2—Offset BD4h" on page 1807
BD8	4	33F30802	"EQEVALCTL3—Offset BD8h" on page 1808
BDC	4	00000000	"EQEVALSTS—Offset BDCh" on page 1809
BE0	4	00000000	"EQEVALSTS2—Offset BE0h" on page 1811
BE4	4	00000000	"EQEVALSTS3—Offset BE4h" on page 1812
BEC	4	00000000	"G3FRAMEERR—Offset BECh" on page 1814

48.1.2 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 48-2. Summary of Sideband Registers—0xB4 (Devices 9-12)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
10	00000000	"PPBIFCTL_PRIV—Offset 10h" on page 1815

Table 48-3. Summary of Sideband Registers—0xB3 (Devices 14-17)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
10	00000000	"PPBIFCTL_PRIV—Offset 10h" on page 1816

48.2 Registers in Configuration Space

48.2.1 VID—Offset 0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**Vendor ID (VID):** This field identifies Intel as the manufacturer of the device.

48.2.2 DID—Offset 2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2h

Default: 19A4h

Bit Range	Default & Access	Field Name (ID): Description
15:0	*See the Field Description for the default value for each Root Port* RO/V	**Device ID (DID):** This field identifies the particular function as allocated by Intel. The default ID values assigned to each Host Root Port: • RP0 = 0x19A4 (PCI Device 9) • RP1 = 0x19A5 (PCI Device 10) • RP2 = 0x19A6 (PCI Device 11) • RP3 = 0x19A7 (PCI Device 12) • RP4 = 0x19A8 (PCI Device 14) • RP5 = 0x19A9 (PCI Device 15) • RP6 = 0x19AA (PCI Device 16) • RP7 = 0x19AB (PCI Device 17)

48.2.3 PCICMD—Offset 4h

This register controls how the device behaves on the primary interface (PCI Express).

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RW	**Interrupt Disable (INTxD):** This bit controls the ability of the PCI-Express Function to generate legacy INTx interrupt message. When set, functions are prevented from asserting INTx interrupt messages. Any INTx emulation interrupts already asserted by the function must be deasserted when this bit is set by generating a Deassert_INTx message(s).
9	0x0 RO	**Fast Back-to-back enable (FBE):** Not applicable to PCI-Express. Hardwired to 0.
8	0x0 RW	**SERR# Enable (SEE):** When set, this bit enables reporting of Non-Fatal and Fatal errors detected by the Function of the Root Complex.
7	0x0 RO	**Wait Cycle Control (WCC):** Not applicable to PCI-Express. Hardwired to 0.
6	0x0 RW	**Parity Error Response Enable (PERE):** This bit controls the setting of the master data parity error bit in the Status Register ('PCI Status Register "PCISTS—Offset 6h" on page 1602) in response to a parity error received on the PCI Express interface (either internal queue errors or a poisoned TLP).
5	0x0 RO	**VGA Palette Snoop Enable (VGA_PSE):** Not applicable to PCI-Express. Hardwired to 0.
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not applicable to PCI-Express. Hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not applicable to PCI-Express. Hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** This bit controls the ability of the Function to issue Memory and I/O read or write requests, and the ability of Root or Switch port to forward memory and I/O read or write requests in the upstream direction. When this bit is 0b, memory and I/O requests received at the root port or downstream side of a switch port (secondary side) must be handled as an Unsupported Request (UR).
1	0x0 RW	**Memory Space Enable (MSE):** • 0 - Respond to all Memory Requests on the primary interface as Unsupported Request Received. • 1 - Enable forwarding of memory transactions to the secondary interface and any internal function.
0	0x0 RW	**I/O Space Enable (IOSE):** • 0 - Respond to all I/O Requests on the primary interface with an Unsupported Request Completion. • 1 - Enable forwarding of I/O Requests to the secondary interface.

48.2.4 PCISTS—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**Detected Parity Error (DPE):** This bit is set when a poisoned TLP is received from PCIe or IOSF. This bit is set even when the parity error response enable bit (bit[6] of the PCICMD Register 'PCI Command Register "PCICMD—Offset 4h" on page 1601) is not set.
14	0x0 RW/1C/V	**Signaled System Error (SSE):** This bit is set when ERR_FATAL or ERR_NONFATAL messages are sent to the root complex and the SERR enable bit in the PCICMD Register ('PCI Command Register "PCICMD—Offset 4h" on page 1601) is set.
13	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit is set when the requester receives a completion with an UR completion status. On Type 1 configuration header functions, the bit is set when a UR completions status is received on the primary side.
12	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit is set when a requester receives a CA completions status. On Type 1 configuration header functions, the bit is set when a 'Completer Abort' is received on the primary side.
11	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit is Set when the port completes a Posted or Non-Posted Request as a Completer Abort error. This applies to a Function with a Type 1 Configuration header when the Completer Abort was generated by its Primary Side.
10:9	0x0 RO	**DEVSEL# Timing (DVT):** These bits have no meaning on PCI Express.
8	0x0 RW/1C/V	**Master Data Parity Error Detected (MDPD):** This bit is set by a requester (primary side for type1 configuration header functions) if the parity error response enable bit (PERE) in the Command Register ('PCI Command Register "PCICMD—Offset 4h" on page 1601) is set and either of the following two conditions occur:
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** This bit has no meaning on PCI Express.
6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**66 MHz Capable (C66):** This bit has no meaning on PCI Express.
4	0x1 RO	**Capabilities List Enable (CAPE):** This bit indicates the presence of an Extended capabilities list items. Offset 34H indicates the offset for the first entry in the linked list of capabilities.
3	0x0 RO/V	**Interrupt Status (INTS):** When set, this bit indicates that an INTx emulation interrupt is pending internally in this function.
2:0	0x0 RO	**RSVD1:** Reserved

48.2.5 RID—Offset 8h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V/P	**Revision ID (RID):** This field specifies the specific revision of this function and should be viewed as a extension to the Device ID.

48.2.6 CCR—Offset 9h

The CCR register has an attribute of RW-L PRST to allow configuration software to modify and lock the register from further update. Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL').

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9h

Default: 060400h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x6 RW/L	**Base Class (BC):** The value of 06h indicates that this is a bridge device. **Power Well:** PRST
15:8	0x4 RW/L	**Sub-Class (SC):** This 8-bit value indicates that this device is a PCI-to-PCI Bridge. **Power Well:** PRST
7:0	0x0 RW/L	**Register-Level Programming Interface (RLPI):** This bit indicates that this device is standard (non-subtractive) PCI-to-PCI Bridge. **Power Well:** PRST

48.2.7 CLS—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Cache Line Size (CLS):** These bits specify the system cache-line size in units of DWords.

48.2.8 PLAT—Offset Dh

This register denotes the maximum time slice for a burst transaction in legacy PCI 2.3 on the primary interface. It does not affect/influence PCI-Express functionality.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Primary Latency Timer (Prim_Lat_timer):** Not applicable to PCI-Express. Hardwired to 00h. This register is typically called as 'latency Timer' for Endpoints in PCI 3.0 specification

48.2.9 HDR—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + Eh

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/L	**Multi-function device (MFD):** The root port, DMI in RC, Virtual Root port/switch port and downstream ports are single function only. **Power Well:** PRST
6:0	0x1 RW/L	**Header Type (HTYPE):** These bits define the layout of addresses 10h through 3Fh in the configuration space. These bits read as 01h to indicate that the register layout conforms to the standard PCI-to-PCI Bridge layout. **Power Well:** PRST

48.2.10 BIST—Offset Fh

This register is used for reporting control and status information of BIST checks within a PCIExpress port. It is not supported in this implementation.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**BIST Tests (BIST_TST):** Not supported. Hardwired to 0h

48.2.11 PRIBUS—Offset 18h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 18h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Primary Bus Number (PBN):** These bits indicate the PCI Express bus number.

48.2.12 SECBUS—Offset 19h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 19h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Secondary Bus Number (SCBN):** These bits indicate the bus number of the PCI device to which the secondary interface is connected.

48.2.13 SUBBUS—Offset 1Ah

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 1Ah

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Subordinate Bus Number (SBBN):** These bits indicate the highest PCI bus number downstream of this bridge.

48.2.14 IOBASE—Offset 1Ch

The I/O Base and I/O Limit registers define an address range that is used by the PCI-Express port to determine when to forward I/O transactions from one interface to the other using the following formula:

IO_BASE (= A[15:12](=IO_LIMIT Only the upper 4 bits are programmable. For the purpose of address decode, address bits A[11:0] are treated as 0.

The bottom of the defined I/O address range will be aligned to a 4KB boundary while the top of the region specified by IO_LIMIT will be one less than a 4 KB multiple.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 1Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW	**I/O Base Address Bits (IOBA):** These bits define the bottom address of an address range to determine when to forward I/O transactions from one interface to another. These bits correspond to address lines[15:12] for 4 KB alignment. Bits[11:0] are assumed to be 000h.
3:0	0x0 RO	**I/O Base Addressing Capability (IOBC):** Each of these bits is hard-wired to 0, indicating support for 16-bit I/O addressing only.

48.2.15 IOLIMIT—Offset 1Dh

The I/O Base and I/O Limit registers define an address range that is used by the PCI-Express bridge to determine when to forward I/O transactions from one interface to the other using the following formula:

IO_BASE (= A[15:12] (=IO_LIMIT Only the upper 4 bits are programmable. For the purpose of address decode, address bits A[11:0] of the IO limit register is treated as FFFh.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 1Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW	**I/O Limit Address Bits (IOLA):** These bits define the top address of an address range to determine when to forward I/O transactions from PCI Express to PCI. These bits correspond to address lines[15:12] for 4 KB aligned window.
3:0	0x0 RO	**I/O Limit Addressing Capability (IOLC):** Each of these bits is hard-wired to 0, indicating support for 16-bit I/O addressing only.

48.2.16 SECSTS—Offset 1Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 1Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**Detected Parity Error (DPE):** This bit is set by the secondary side for a Type 1 Configuration Space header function whenever it receives a Poisoned TLP, regardless of the state in the Parity Error Response Enable (PERE) field of the Bridge Control Register (BCTL).
14	0x0 RW/1C/V	**Received System Error (RSE):** This bit is set by the secondary side for a Type 1 Configuration Space header function whenever it receives an ERR_FATAL or ERR_NONFATAL message.
13	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit is set when the secondary side for Type 1 configuration space header function (for requests initiated by the Type 1 header function itself) receives a completion with Unsupported Requests Completion Status.
12	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit is set when the secondary side for Type 1 Configuration Space Header Function (for Requests initiated by the Type 1 header Function itself) receives a completion with Completer About Completion Status.
11	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit is set when the secondary side for Type 1 configuration space header function (for requests completed by type 1 header functions itself) completes a Posted or Non-posted request as a Completer Abort error.
10:9	0x0 RO	**DEVSEL# Timing (DVT):** Not applicable to PCI Express. Hardwired to 0.
8	0x0 RW/1C/V	**Master Data Parity Error Detected (MDPD):** This bit is set by the secondary side requester if the Parity Error Response Enable (PERE) bit in the Bridge Control Register (BCTL) is set and either of the following conditions occurs: Requester receives completion marked poisoned Requester sends a poisoned request (includes writes and messages) If the PERE bit in the Bridge Control Register (BCTL) is clear, this bit is never set.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not applicable to PCI Express. Hardwired to 0.
6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**66 MHz Capable (C66):** Not applicable to PCI Express. Hardwired to 0.
4:0	0x0 RO	**RSVD1:** Reserved

48.2.17 MEMBASE—Offset 20h

The Memory Base and Memory Limit registers define a memory mapped I/O non-prefetchable address range (32-bit addresses) and direct the accesses in this range to the PCI-Express port based on the following formula:

MEMORY_BASE (= A[31:20] (= MEMORY_LIMIT The upper 12 bits of both the Memory Base and Memory Limit registers are read/write and corresponds to the upper 12 address bits, AD[31:20], of 32-bit addresses.

For the purpose of address decoding, the bridge assumes that the lower 20 address bits, AD[19:0], of the memory base address are zero. Similarly, the bridge assumes that the lower 20 address bits, AD[19:0], of the memory limit address (not implemented in the Memory Limit register) are FFFFFh. Thus, the bottom of the defined memory address range will be aligned to a 1 MB boundary and the top of the defined memory address range will be one less than a 1 MB boundary

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 20h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Memory Base (MB):** These bits are compared with bits[31:20] of the incoming address to determine the lower 1 MB-aligned value (inclusive) of the range.
3:0	0x0 RO	**RSVD0:** Reserved

48.2.18 MEMLIMIT—Offset 22h

This register controls the processor to PCI-Express non-prefetchable memory access routing based on the following formula as described above:

MEMORY_BASE (= A[31:20] (= MEMORY_LIMIT The upper 12 bits of the register are read/write and correspond to the upper 12 address bits A[31:20] of the 32 bit address. The bottom 4 bits of this register are read-only and return zeros when read. This register must be initialized by the configuration software. For the purpose of address decode address bits A[19:0] are assumed to be FFFFFh.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 22h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Memory Limit (ML):** These bits are compared with bits[31:20] of the incoming address to determine the upper limit of the range of memory accesses that will be passed by the port.
3:0	0x0 RO	**RSVD0:** Reserved

48.2.19 PFBASE—Offset 24h

The Prefetchable Memory Base and Memory Limit registers define a memory mapped I/O prefetchable address range (32-bit addresses) which is used by the PCI-Express bridge to determine when to forward memory transactions based on the following formula:

PREFETCH_MEMORY_BASE (= A[31:20] (= PREFETCH_MEMORY_LIMIT The upper 12 bits of both the Prefetchable Memory Base and Memory Limit registers are read/ write and corresponds to the upper 12 address bits, A[31:20], of 32-bit addresses. For the purpose of address decoding, the bridge assumes that the lower 20 address bits, A[19:0], of the memory base address are zero. Similarly, the bridge assumes that the lower 20 address bits, A[19:0], of the memory limit address (not implemented in the Memory Limit register) are FFFFFh.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 24h

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Prefetchable Memory Base (PMB):** These bits are compared with bits[31:20] of the incoming address to determine the lower 1 MB-aligned value (inclusive) of the range. The incoming address must be greater than or equal to this value.
3:0	0x1 RO	**Prefetchable Memory Base Address Capability (PFMCAP):** • 0: 32-bit Prefetchable Memory addressing. • 1: 64-bit Prefetchable Memory addressing. This field indicates that 64-bit addressing is supported for the limit.

48.2.20 PFLIMIT—Offset 26h

This register controls the processor to PCI-Express prefetchable memory access routing based on the following formula as described above:

PREFETCH_MEMORY_BASE (= A[31:20] (= PREFTCH_MEMORY_LIMIT The upper 12 bits of the register are read/write and correspond to the upper 12 address bits A[31:20] of the 32 bit address. This register must be initialized by the configuration software. For the purpose of address decode address bits A[19:0] are assumed to be FFFFFh.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 26h

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RW	**Prefetchable Memory Limit (PML):** These bits are compared with bits[31:20] of the incoming address to determine the upper limit of the prefetchable memory range.
3:0	0x1 RO	**Prefetchable Memory Limit Address Capability (PMLC):** This field indicates that 64-bit addressing is supported for the limit.

48.2.21 PFBASEU—Offset 28h

The Prefetchable Base Upper 32 Bits and Prefetchable Limit Upper 32 Bits registers are extensions to the Prefetchable Memory Base and Prefetchable Memory Limit registers. If a 64-bit prefetchable memory address range is supported, the Prefetchable Base Upper 32 Bits and Prefetchable Limit Upper 32 Bits registers specify the upper 32-bits, corresponding to A[63:32], of the 64-bit base and limit addresses which specify the prefetchable memory address range. PREFETCH_MEMORY_BASE_UPPER (= A[63:32] (= PREFETCH_MEMORY_BASE_LIMIT_UPPER

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Prefetchable Memory Base Upper Portion (PMBU):** Corresponds to A[63:32] of the memory address that maps to the upper base of the prefetchable range of memory accesses that will be passed by the PCI-Express bridge.

48.2.22 PFLIMITU—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Prefetchable Memory Limit Upper Portion (PMLU):** Corresponds to A[63:32] of the memory address that maps to the upper limit of the prefetchable range of memory accesses that will be passed by the PCI-Express bridge.

48.2.23 CAPPTR—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 34h

Default: 40h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x40 RO	**Capabilities Pointer (CPTR):** Contains the offset of the first item in the list of capabilities. (EXPCAPLST)

48.2.24 INTL—Offset 3Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 3Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Line (INTL):** This register is used to communicate interrupt line routing information. The device itself does not use this value, rather it is used by device drivers and operating systems. (compatibility)

48.2.25 INTP—Offset 3Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 3Dh

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RW/L	**Interrupt Pin (INTP):** This register tells which interrupt pin the function uses. • 01h: Generate INTA • 02h: Generate INTB • 03h: Generate INTC • 04h: Generate INTD • Others: Reserved BIOS has the ability to write this register once during boot to setup the correct interrupt for the Function. **Power Well:** PRST

48.2.26 BCTL—Offset 3Eh

This register provides extensions to the Command Register ('PCI Command Register "PCICMD—Offset 4h" on page 1601) that are specific to a bridge. The Bridge Control Register provides many of the same controls for the secondary interface that are provided by the Command Register for the primary interface. Some bits affect operation of both interfaces of the bridge.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 3Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11	0x0 RO	**Discard Timer SERR# Enable (DTSE):** Not applicable to PCI Express. Hardwired to 0.
10	0x0 RO	**Discard Timer Status (DTS):** Not applicable to PCI Express. Hardwired to 0.
9	0x0 RO	**Secondary Discard Timer (SDT):** Not applicable to PCI Express. Hardwired to 0.
8	0x0 RO	**Primary Discard Timer (PDT):** Not applicable to PCI Express. Hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not applicable to PCI Express. Hardwired to 0.
6	0x0 RW	**Secondary Bus Reset (SBR):** Setting this bit triggers a hot reset on the downstream link for the corresponding PCIe Express port and the PCI Express hierarchy domain subordinate to the port. Software must ensure a minimum reset duration of 1us as defined in the PCI Local Bus Specification, Revision 3.0. Hardware will continue to maintain the hot reset state as long as the SBR bit is set. For Root Ports, it is recommended that software assert this field for a minimum of 2 ms to ensure that all downstream links enters hot reset state. A secondary bus reset will not reset any register of a Type 1 configuration space header function.
5	0x0 RO	**Master Abort Mode (MAM):** Not applicable to PCI Express. Hardwired to 0.
4	0x0 RW	**VGA 16-bit Decode (VGA16BD):** This bit enables the bridge to provide 16-bit decoding of VGA I/O address precluding the decoding of VGA alias addresses every 1 KB. This bit requires the VGA enable bit (bit 3 of this register) to be set to 1. • 0: execute 10-bit address decode on VGA I/O accesses • 1: execute 16-bit address decode on VGA I/O accesses
3	0x0 RW	**VGA Enable (VGAE):** This bit modifies the response to VGA-compatible addresses. When set to 1b, the bridge positively decodes and forwards the following transactions from primary side to secondary side regardless of the value of the I/O base and limit registers. The transactions are qualified by the memory enable and I/O enable in the command register. Memory addresses: 000A 0000h-000B FFFFh I/O addresses: 3B0h-3BBh and 3C0h-3DFh in first 64 KB of I/O address space (Inclusive of ISA address aliases when IO address bits[15:10] are not decoded)

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW	**ISA Enable (IE):** This bit modifies the response by the bridge to ISA I/O addresses. This field applies only to I/O addresses that are enabled by the I/O base and I/O limit registers and are in the first 64 KB of PCI I/O space. When this bit is set, the bridge blocks all forwarding from primary to secondary of I/O transactions addressing the last 768 bytes in each 1 KB block (offsets 100h to 3FFh). In the opposite direction (secondary to primary), I/O transactions will be forwarded if they address the last 768B in each 1 KB block. • 1: Forward upstream ISA I/O addresses in the address range defined by the I/O Base and I/O Limit registers that are in the firsts 64KB of PCI I/O address space (Top 768B of each 1K block). • 0: Forward downstream all I/O addresses in the address range defined by the I/O Base and I/O Limit registers.
1	0x0 RW	**SERR# Enable (SE):** This bit controls the forwarding of PCI Express ERR_COR, ERR_NONFATAL and ERR_FATAL messages to the primary side. • 1: Enables forwarding of ERR_COR, ERR_NONFATAL, ERR_FATAL messages. • 0: Disables forwarding of ERR_COR, ERR_NONFATAL, ERR_FATAL messages.
0	0x0 RW	**Parity Error Response Enable (PERE):** This bit controls the response to poisoned TLPs in the PCI Express port. • 1: Enables reporting of poisoned TLP errors. • 0: Disables reporting of poisoned TLP errors.

48.2.27 EXPCAPLST—Offset 40h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 40h

Default: 8010h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x80 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list. (PMCAPLST)
7:0	0x10 RO	**Capability ID (CAPID):** Identifies the function as PCI Express capable.

48.2.28 EXPCAP—Offset 42h

This register stores the version number of the capability item and other base information contained in the capability structure.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 42h

Default: 0042h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**RSVD0:** Reserved
13:9	0x0 RO/V	**Interrupt Message Number (IMN):** This field indicates the interrupt message number that is generated from the PCI Express port. When there is more than one MSI interrupt number, this register is required to contain the offset between the base Message Data and the MSI Message that is generated when the status bits in the slot status register or root port status registers are set. The chipset is required to update this field if the number of MSI messages change. Applies only to Root ports. The PCIe macro assigns the first vector for PM/HP events and so this field is set to 0.
8	0x0 RW/L	**Slot Implemented (SI):** • 1: Indicates the PCI Express link associated with this port is connected to a slot. • 0: Indicates no slot is connected to this port. Applies only to root and downstream ports. ***Note:*** For any devices with hot plug enabled, this bit will be forced to 1 (slot) in BIOS. **Power Well:** PRST
7:4	0x4 RO	**Device/Port Type (DT):** 4h: Root Port of a PCIe Root Complex
3:0	0x2 RO	**Version Number (VN):** These bits indicate the version number of the PCI Express capability structure.

48.2.29 DEVCAP—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 44h

Default: 00008021h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:26	0x0 RO	**Captured Slot Power Limit Scale (CSPLS):** In combination with the Slot Power Limit value (bits[25:18], this field specifies the upper limit of the power supplied by slot. The power limit (in Watts) is calculated by multiplying the value in this field by the value in the Slot Power Limit Value field. This value is set by the Set_Slot_Power_Limit message. Does not apply to root ports or integrated devices or end points or downstream ports or Virtual Root Port/switch port
25:18	0x0 RO	**Captured Slot Power Limit Value (CSPLV):** In combination with the Slot Power Limit Scale value (bits[27:26]), this field specifies the upper limit of the power supplied by slot. The power limit (in Watts) is calculated by multiplying the value in this field by the value in the Slot Power Limit Scale field. This value is set by the Set_Slot_Power_Limit message. Does not apply to root ports or integrated devices or end points or downstream ports or Virtual Root Port/switch ports
17:16	0x0 RO	**RSVD1:** Reserved
15	0x1 RO	**Role-Based Error Reporting (RBER):** The PCIe cluster supports Role-based Error Reporting.
14:12	0x0 RO	**Undefined:** Reserved.
11:9	0x0 RO	**Endpoint L1 Acceptable Latency (EPL1AL):** This field only applies to Endpoint and is hardwired to 0 for other types such as root ports, upstream/downstream ports
8:6	0x0 RO	**Endpoint L0s Acceptable Latency (EPL0AL):** This field only applies to Endpoint and is hardwired to 0 for other types such as root ports, upstream/downstream ports
5	0x1 RW/L	**Extended Tag Field Supported (ETFG):** • 0: The PCIe supports 5-bit extended tag • 1: The PCIe supports 8-bit extended tag **Power Well:** PRST
4:3	0x0 RO	**Phantom Functions Supported (PFS):** This field indicates the number of most significant bits of the function number portion of Requester ID in a TLP that are logically combined with the Tag identifier. The PCIe cluster does not support phantom functions
2:0	0x1 RW/L	**Max Payload size Supported (MPSS):** The PCIe SIP can tolerate up to 512-byte packets as maximum payload for project specific. Defined encodings are: • 000b 128 bytes max payload size • 001b 256 bytes max payload size • 010b 512 bytes max payload size • 011b 1024 bytes max payload size • 100b 2048 bytes max payload size • 101b 4096 bytes max payload size • 110b Reserved • 111b Reserved **Power Well:** PRST

48.2.30 DEVCTL—Offset 48h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 48h

Default: 2000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x2 RW	**Max_Read_Request_Size (MRRS):** This field sets the maximum Read Requests size of the function as a requester. The Function must not generate read requests with size exceeding the set value. • 000b: 128 bytes maximum Read Request size • 001b: 256 bytes maximum Read Request size • 010b: 512 bytes maximum Read Request size • 011b: 1024 bytes maximum Read Request size • 100b: 2048 bytes maximum Read Request size • 101b: 4096 bytes maximum Read Request size • Others: Reserved Functions that do not generate Read Requests larger than 128B and functions that do not generate Read Requests on their own behalf are permitted to implement this field as Read Only (RO) with a value of 000b.
11	0x0 RO	**Enable No Snoop (ENOSNP):** If this bit this is set, the function is permitted to set the No Snoop bit in the Requester attributes of transactions it initiates that do not require hardware enforced cache coherency.
10	0x0 RO	**RSVD:** Reserved
9	0x0 RO	**RSVD:** Reserved
8	0x0 RW	**Extended Tag Field Enable (ETFE):** When set, this bit enables a function to use an 8-bit tag field as a Requester. Functions that do not implement this capability hardwire this bit to 0b.
7:5	0x0 RW	**Maximum Payload Size (MPS):** This field sets maximum TLP payload size for the function. As a receiver, the function must handle TLPs as large as the set value. As a Transmitter, the function must not generate TLPs exceeding the set value. • 000b: 128 bytes maximum payload size (default) • 001b: 256 bytes maximum payload size • 010b: 512 bytes maximum payload size • 011b: 1024 bytes maximum payload size • 100b: 2048 bytes maximum payload size • 101b: 4096 bytes maximum payload size • Others: Reserved
4	0x0 RO	**Enable Relaxed Ordering (ENRO):** When set, the function is permitted to set the relaxed ordering bit in the attribute field of transactions it initiates that do not require strong write ordering.
3	0x0 RW	**Unsupported Request Reporting Enable (URRE):** This bit controls the enabling of ERR_CORR, ERR_NONFATAL or ERR_FATAL messages on PCI Express for reporting 'Unsupported Request' errors.
2	0x0 RW	**Fatal Error Reporting Enable (FERE):** When this bit is set, generation of the ERR_FATAL message is enabled.
1	0x0 RW	**NonFatal Error Reporting Enable (NFERE):** When this bit is set, generation of the ERR_NONFATAL message is enabled.
0	0x0 RW	**Correctable Error Reporting Enable (CERE):** When this bit is set, generation of the ERR_CORR message is enabled.

48.2.31 DEVSTS—Offset 4Ah

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 4Ah

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO/V	**Transactions Pending (TP):** When set, this bit indicates that the function has issued Non-Posted Requests that have not been completed. For Root or Switch port, it applies to Non-Posted Requests the port has issued on its own behalf (Port's Request ID).
4	0x0 RO	**RSVD:** Reserved
3	0x0 RW/1C/V	**Unsupported Request Detected (URD):** This bit indicates that this function received an unsupported request from PCI Express link. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
2	0x0 RW/1C/V	**Fatal Error Detected (FED):** This bit indicates that this function has detected a Fatal error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
1	0x0 RW/1C/V	**Non-Fatal Error Detected (NFED):** This bit indicates that this function has detected a Non-Fatal error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
0	0x0 RW/1C/V	**Correctable Error Detected (CED):** This bit indicates that this function has detected a Correctable error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.

48.2.32 LINKCAP—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 4Ch

Default: 09794883h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x9 RW/V/L	**Port Number (PN):** This field indicates the PCI Express port number assigned to this link. **Power Well:** PRST
23	0x0 RO	**RSVD0:** Reserved
22	0x1 RW/L	**ASPM Optionality Compliance (ASPMOPCMP):** The ASPM Optionality Compliance bit was created as a tool to set clear expectations for hardware and software interaction. This bit is Set to indicate hardware that conforms to the current specification. **Power Well:** PRST
21	0x1 RW/L	**Link Bandwidth Notification Capability (LBNC):** A value of 1b indicates support for the Link Bandwidth Notification status and interrupt mechanisms. **Power Well:** PRST
20	0x1 RW/L	**Data Link Layer Active Error Reporting Capable (DLLERC):** For a Downstream Port, this bit must be hardwired to 1b if the component supports the optional capability of reporting the DL_Active state of the Data Link Control and Management State Machine. **Power Well:** PRST
19	0x1 RW/L	**Surprise Down Error Reporting Capable (SLDERC):** For a Downstream Port, this bit must be Set if the component supports the optional capability of detecting and reporting a Surprise Down error condition. **Power Well:** PRST
18	0x0 RO	**Clock Power Management Capable (CPMC):** A value of 0b indicates the component does not have this capability and that reference clock(s) must not be removed in these Link states.
17:15	0x2 RW/L	**L1 Exit Latency (L1EL):** This field indicates the L1 exit latency for the given PCI-Express Link. It indicates the length of time this port requires to complete transition from L1 to L0. • 000: Less than 1us • 001: 1us to less than 2us • 010: 2us to less than 4us • 011: 4us to less than 8us • 100: 8us to less than 16us • 101: 16us to less than 32us • 110: 32us to less than 64us • 111: More than 64us If L1 is not supported, the value is undefined. **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
14:12	0x4 RW/L	**L0s Exit Latency (L0sEL):** This field indicates the L0s exit latency for the given PCI-Express Link. It indicates the length of time this port requires to complete transition from L0s to L0. • 000b: Less than 64ns • 001b: 64ns to less than 128ns • 010b: 128ns to less than 256ns • 011b: 256ns to less than 512ns • 100b 512 ns to less than 1 us • 101b: 1us to less than 2us • 110b: 2us to less than 4us • 111b: More than 4us If L0s is not supported, the value is undefined. **Power Well:** PRST
11:10	0x2 RW/L	**ASPM Support (ASPMSUP):** This field indicates the level of ASPM supported on the given PCI Express Link. • 00b: No ASPM Support • 01b: L0s Supported • 10b: L1 Supported • 11b: L0s and L1 Supported **Power Well:** PRST
9:4	0x8 RO/V	**Maximum Link Width (MLW):** This field indicates the maximum link width implemented by the given PCI Express Link. • 00h: Reserved • 01h: x1 • 02h: x2 • 04h: x4 • 08h: x8 • 10h: x16 • 20h: x32 (Unsupported) • Others: Reserved
3:0	0x3 RO/V	**Maximum Link Speed (MLS):** This field indicates the supported link speed(s) of the associated port. • 0001b: 2.5 Gb/s link speed is supported • 0010b: 5.0 Gb/s and 2.5 Gb/s link speed supported • 0011b: 8.0 Gb/s and 5.0 and 2.5 Gb/s link speed supported • Others: Reserved.

48.2.33 LINKCTL—Offset 50h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 50h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11	0x0 RW	**Link Autonomous Bandwidth Interrupt Enable (LABIE):** When Set, this bit enables the generation of an interrupt to indicate that the Link Autonomous Bandwidth Status bit has been set. Functions that do not implement the Link Bandwidth Notification Capability must hardwire this bit to 0b.
10	0x0 RW	**Link Bandwidth Management Interrupt Enable (LBMIE):** When set, this bit enables the generation of an interrupt to indicate that the Link Bandwidth Management Status bit has been set. This bit is not applicable and is reserved for Endpoints, PCI Express-to-PCI/PCI-X bridges, and Upstream Ports of Switches.
9	0x0 RW	**Hardware Autonomous Width Disable (HAWD):** Set, this bit disables hardware from changing the Link width for reasons other than attempting to correct unreliable Link operation by reducing Link width. For a Multi-Function device associated with an Upstream Port, the bit in Function 0 is of type RW, and only Function 0 controls the components Link behavior. In all other Functions of that device, this bit is of type RsvdP. Components that do not implement the ability autonomously to change Link width are permitted to hardwire this bit to 0b. Default value of this bit is 0b.
8	0x0 RW/L	**Enable Clock Power Management (ECPM):** Applicable only for Upstream Ports and with form factors that support a 'Clock Request' (CLKREQ#) mechanism, this bit operates as follows: • 0b Clock power management is disabled and device must hold CLKREQ# signal low. • 1b When this bit is Set, the device is permitted to use CLKREQ# signal to power manage Link clock according to protocol defined in appropriate form factor specification. For a non-ARI multi-Function device, power-management-configuration software must only Set this bit if all Functions of the multi-Function device indicate a 1b in the Clock Power Management bit of the Link Capabilities register. The component is permitted to use the CLKREQ# signal to power manage Link clock only if this bit is Set for all Functions. For ARI Devices, Clock Power Management is enabled solely by the setting in Function 0. The settings in the other Functions always return whatever value software programmed for each, but otherwise are ignored by the component. The CLKREQ# signal may also be controlled via the L1 PM Substates mechanism. Such control is not affected by the setting of this bit. Downstream Ports and components that do not support Clock Power Management (as indicated by a 0b value in the Clock Power Management bit of the Link Capabilities register) must hardwire this bit to 0b. Default value of this bit is 0b, unless specified otherwise by the form factor specification. **Power Well:** PRST
7	0x0 RW	**Extended Synch (ES):** When set, this bit forces extended transmission of 4096 FTS ordered sets in FTS and an extra 1024 TS1 at exit from L1 prior to entering L0. This mode provides external devices monitoring the link time to achieve bit and symbol lock before the link enters L0 state and resumes communication. Default value for this bit is 0.
6	0x0 RW	**Common Clock Configuration (CCCFG):** When set, this bit indicates that this component and the component at the opposite end of this link are operating with distributed common reference clocks. A value of 0b indicates that this component and the component at the opposite end of this link are operating with asynchronous reference clock. After changing the value in this bit in both components on a link, software must trigger the link to retrain by writing a 1b to the Retrain Link bit of the Downstream Port.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW/V	**Retrain Link (RL):** When set, this bit initiates link retraining by directing the physical layer LTSSM to recovery state. If the LTSSM is already in recovery or configuration, re-entering Recovery is permitted but not required. Reads of this bit always return 0b. This is used by the downstream ports, Root ports or DMI EP in RC only. For the upstream port or virtual switch port, it is Read-only.
4	0x0 RW	**Link Disable (LD):** This bit disables the Link by directing the LTSSM to the Disabled state when Set, This is used by the downstream ports, Root ports or DMI EP in RC only. For the upstream port or virtual switch port, it is Read-only.
3	0x0 RO	**Read Completion Boundary (RCB):** This bit indicates the RCB value for Root Port, Endpoints and Bridges. • 0b: 64 byte • 1b: 128 byte Configuration software must only set this bit if the Root Port Upstream from the Endpoint or Bridge reports an RCB value of 128 bytes (Root Port only)
2	0x0 RO	**RSVD1:** Reserved
1:0	0x0 RW	**ASPM Control (ASPMCTL):** This field controls the level of ASPM enabled on a given PCI Express Link. • 00b: Disabled • 01b: L0s Entry Enabled • 10b: L1 Entry Enabled • 11b: L0s and L1 Entry Enabled ''L0s Entry Enabled' enables the Transmitter to enter L0s. If L0s is supported, the Receiver must be capable of entering L0s even when the Transmitter is disabled from entering L0s (00b or 10b).

48.2.34 LINKSTS—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 52h

Default: 1001h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**Link Autonomous Bandwidth Status (LABS):** This bit is set by hardware to indicate that the PCIe cluster has autonomously changed link or width, without the port transitioning through DL_Down status, for reason other than to attempt to correct unreliable link operation. This bit must be set if the Physical Layer reports an autonomous speed or width change initiated by the Upstream Port.
14	0x0 RW/1C/V	**Link Bandwidth Management Status (LBMS):** This bit is set by hardware to indicate that either of the following has occurred without the port transitioning through DL_Down status:
13	0x0 RO/V	**Data Link Layer Link Active (DLLLA):** This bit indicates the status of the Data Link Control and Management Status Machine.
12	0x1 RW/L	**Slot Clock Configuration (SCC):** When to 1b, this bit indicates that the component uses the same physical reference clock that he platform provides on the connector. If the device uses an independent clock irrespective of the presence of a reference on the connector, this bit must be clear. • 1: Indicates same reference clock. • 0: Indicates independent reference clock **Power Well:** PRST
11	0x0 RO/V	**Link Training (LT):** This bit indicates that the Physical Layer LTSSM is in the Configuration or Recovery state
10	0x0 RO	**Undefined:** Not applicable
9:4	0x0 RO/V	**Negotiated Link Width (NLW):** This field indicates the negotiated width of the PCI Express link. • 00 0001b: x1 • 00 0010b: x2 • 00 0100b: x4 • 00 1000b: X8 • 00 1100b: x12 not supported • 01 0000b: x16 • 10 0000b: x32 not supported • All other values are reserved. The value in this field is undefined when the link is not up.
3:0	0x1 RO/V	**Current Link Speed (CLS):** This field indicates the negotiated link speed of the given PCI Express link. • 0001b: 2.5 Gb/s PCI Express Link • 0010b: 5.0 Gb/s PCI Express Link • 0011b: 8.0 Gb/s PCI Express Link • Others: Reserved

48.2.35 SLOTCAP—Offset 54h

Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL').

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 54h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RW/L	**Physical Slot Number (PSN):** This field indicates the physical slot number connected to the PCI-Express port. It should be initialized to 0 for ports connected to devices that are either integrated on the system board or integrated within the same silicon such as the switch device or the Root port. **Power Well:** PRST
18	0x0 RW/L	**No Command Completed Support (NCCS):** When Set, this bit indicates that this slot does not generate software notification when an issued command is completed by the Hot-Plug Controller. This bit is only permitted to be Set if the hot-plug capable Port is able to accept writes to all fields of the Slot Control register without delay between successive writes. **Power Well:** PRST
17	0x0 RW/L	**Electromechanical Interlock Present (EMIP):** This bit when set indicates that an Electromechanical Interlock is implemented on the chassis for this slot and that lock is controlled by bit 11 in Slot Control Register. **Power Well:** PRST
16:15	0x0 RW/L	**Slot Power Limit Scale (SPLS):** This field specifies the scale used for the Slot Power Limit Value. Range of Values: • 00: 1.0x • 01: 0.1x • 10: 0.01x • 11: 0.001x This register must be implemented if the Slot Implemented bit is set in EXPCAP. Writes to this register (SLOTCAP) when the Data Link Layer reports DL_Up status, or the link transitions from a non-DL_Up to a DL_Up would cause the Port to send the Set_Slot_Power_Limit Message. **Power Well:** PRST
14:7	0x0 RW/L	**Slot Power Limit Value (SPLV):** This field specifies the upper limit on power supplied by slot in conjunction with the Slot Power Limit Scale value defined previously Power limit (in Watts). i.e Power limit = SPLS x SPLV. This register must be implemented if the Slot Implemented bit is set in EXPCAP. Writes to this register (SLOTCAP) when the Data Link Layer reports DL_Up status, or the link transitions from a non-DL_Up to a DL_Up would cause the Port to send the Set_Slot_Power_Limit Message. **Power Well:** PRST
6	0x0 RW/L	**Hot-plug Capable (HPC):** This field defines hot-plug support capabilities for the PCI-Express port. • 0: indicates that this slot is not capable of supporting Hot-plug operations. • 1: indicates that this slot is capable of supporting Hot-plug operations **Power Well:** PRST
5	0x0 RW/L	**Hot-plug Surprise (HPS):** This field indicates that a device in this slot may be removed from the system without prior notification. • 0: indicates that hot-plug surprise is not supported • 1: indicates that hot-plug surprise is supported **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW/L	**Power Indicator Present (PIP):** This bit indicates that a Power Indicator is implemented on the chassis for this slot. • 0: indicates that Power Indicator is not present • 1: indicates that Power Indicator is present **Power Well:** PRST
3	0x0 RW/L	**Attention Indicator Present (AIP):** This bit indicates that an Attention Indicator is implemented on the chassis for this slot. • 0: indicates that an Attention Indicator is not present • 1: indicates that an Attention Indicator is present **Power Well:** PRST
2	0x0 RW/L	**MRL Sensor Present (MRLSP):** This bit indicates that an MRL Sensor is implemented on the chassis for this slot. • 0: indicates that an MRL Sensor is not present • 1: indicates that an MRL Sensor is present **Power Well:** PRST
1	0x0 RW/L	**Power Controller Present (PCP):** This bit indicates that a Power Controller is implemented on the chassis for this slot. • 0: indicates that a Power Controller is not present • 1: indicates that a Power Controller is present **Power Well:** PRST
0	0x0 RW/L	**Attention Button Present (ABP):** This bit indicates that an Attention Button is implemented on the chassis for this slot. • 0: indicates that an Attention Button is not present • 1: indicates that an Attention Button is present **Power Well:** PRST

48.2.36 SLOTCTL—Offset 58h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 58h

Default: 03C0h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**RSVD0:** Reserved
13	0x0 RW	**Auto Slot Power Limit Disable (ASPLD):** When Set, this disables the automatic sending of a Set_Slot_Power_Limit Message when a Link transitions from a non-DL_Up status to a DL_Up status.
12	0x0 RW	**Data Link Layer State Changed Enable (DLLSCE):** When set to 1, this field enables software notification when Data Link Layer Link Active reporting field is changed.
11	0x0 RW/V	**Electromechanical Interlock Control (EIC):** When software writes either a 1 to this bit, The PCIe port pulses the EMIL pin per PCIExpress Server/Workstation Module Electromechanical Spec Rev 1.0. Write of 0 has no effect. This bit always returns a 0 when read. If electromechanical lock is not implemented, then either a write of 1 or 0 to this register has no effect.
10	0x0 RW	**Power Controller Control (PCC):** This bit indicates the current state of the Power applied to the slot of the PCIExpress port. Reads of this field must reflect the value from the latest write, even if the corresponding hot-plug command is not executed yet at the VPP, unless software issues a write without waiting for the previous command to complete in which case the read value is undefined. • 0: Power On • 1: Power Off
9:8	0x3 RW	**Power Indicator Control (PIC):** If a Power Indicator is implemented, writes to this register set the Power Indicator to the written state. Reads of this field must reflect the value from the latest write, even if the corresponding hot-plug command is not executed yet at the VPP, unless software issues a write without waiting for the previous command to complete in which case the read value is undefined. • 00: Reserved. • 01: On • 10: Blink (The PCIe cluster drives 1.5 Hz square wave for Chassis mounted LEDs in the case of legacy card form factor for PCI-Express devices) • 11: Off When this register is written, the event is signaled via the virtual pins of the switch over a dedicated SMBus port. The switch does not generated the Power_Indicator_On/Off/Blink messages on PCI Express when this field is written to by software.
7:6	0x3 RW	**Attention Indicator Control (AIC):** If an Attention Indicator is implemented, writes to this register sets the Attention Indicator to the written state. Reads of this field reflect the value from the latest write, even if the corresponding hot-plug command is not executed yet at the VPP, unless software issues a write without waiting for the previous command to complete in which case the read value is undefined. • 00: Reserved. • 01: On • 10: Blink (The switch drives 1.5 Hz square wave) • 11: Off When this register is written, the event is signaled via the virtual pins of the switch over a dedicated SMBus port.
5	0x0 RW	**Hot-plug Interrupt Enable (HPIE):** This field enables the generation of Hot-plug interrupts and events in the PCIExpress port. • 0: Disables Hot-plug events and interrupts • 1: Enables Hot-plug events and interrupts
4	0x0 RW	**Command Completed Interrupt Enable (CCIE):** This field enables the generation of Hot-plug interrupts when a command is completed by the Hot-plug controller connected to the PCI-Express port. • 0: Disables hot-plug interrupts on a command completion by a hot-plug Controller • 1: Enables hot-plug interrupts on a command completion by a hot-plug Controller

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW	**Presence Detect Changed Enable (PDCIE):** This bit enables the generation of hot-plug interrupts or wake messages via a presence detect changed event. • 0: Disables generation of hot-plug interrupts or wake messages when a presence detect changed event happens. • 1- Enables generation of hot-plug interrupts or wake messages when a presence detect changed event happens.
2	0x0 RW	**MRL Sensor Changed Enable (MSCIE):** This bit enables the generation of hot-plug interrupts or wake messages via a MRL Sensor changed event. • 0: Disables generation of hot-plug interrupts or wake messages when an MRL Sensor changed event happens. • 1: Enables generation of hot-plug interrupts or wake messages when an MRL Sensor changed event happens.
1	0x0 RW	**Power Fault Detected Enable (PFDIE):** This bit enables the generation of hot-plug interrupts or wake messages via a power fault event. • 0: Disables generation of hot-plug interrupts or wake messages when a power fault event happens. • 1: Enables generation of hot-plug interrupts or wake messages when a power fault event happens.
0	0x0 RW	**Attention Button Pressed Enable (ABPE):** This bit enables the generation of hot-plug interrupts or wake messages via an attention button pressed event. • 0: Disables generation of hot-plug interrupts or wake messages when the attention button is pressed. • 1: Enables generation of hot-plug interrupts or wake messages when the attention button is pressed

48.2.37 SLOTSTS—Offset 5Ah

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 5Ah

Default: 0040h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RW/1C/V	**Data Link Layer State Changed (DLLSCS):** This bit is set (if it is not already set) when the state of the Data Link Layer Link Active bit in the Link Status register has changed. Software must read Data Link Layer Active field to determine the link state before initiating configuration cycles to the hot plugged device.
7	0x0 RO/V	**Electromechanical Interlock Status (ELS):** A read to this register returns the current state of the Electromechanical Interlock (the EMILS pin) which has the defined encodings as: • 0: Electromechanical Interlock Disengaged • 1: Electromechanical Interlock Engaged

6	0x1
	RO/V
		Presence Detect State (PDS): This field conveys the Presence Detect status of an adapter in the slot.
		It reflects the Logical 'OR' of the Physical Layer in-band presence detect mechanism and any out-of-band presence detect mechanism defined for the slot's corresponding form factor.
		• 0: Card/Module/Cable slot empty or Cable Slot occupied but not powered
		• 1: Card/module Present in slot (powered or unpowered) or cable present and powered on the other end.
		This field is set to 1 by the switch following reset for all the ports since it is related to the complement of the EXPCAP.SI bit whose default is 0 implying that the card is connected to the switch on the motherboard.
		Software should ensure that for those standard PCI-Express ports which are hot-plug capable, it sets the EXPCAP.SI field to '1' such that PDS becomes 0.
		Then any subsequent hotplug action will ensure that this field is set. Refer to the algorithm given below:
		if (EXPCAP.SI == FALSE) // always set to 1b and ignore the input from inband/OOB presence detect SLOTSTS.PDS = 1b else //
		if (EXPCAP.SI == TRUE) // Slot Empty = 0, Card Present = 1 SLOTSTS.PDS reflects slot status of side-band SMBUS Presence Detect signal OR Inband Presence Detect Mechanism.

5	0x0 RO/V	**MRL Sensor State (MRLSS):** This bit reports the status of an MRL sensor if it is implemented. • 0: MRL Closed • 1: MRL Open If Hotplug is implemented through VPP, the correct polarity of the external MRL sensor in the motherboard should be translated to map to the encodings as defined in this register field. (Tylersburg issue)
4	0x0 RW/1C/V	**Command Completed (CCS):** This bit is set when the hot-plug controller completes an issued command and is ready to accept a new command. It is subsequently cleared by software after the field has been read and processed. If Command Completed notification is supported, then the No Command Completed Support bit in the Slot Capabilities register should be 0.
3	0x0 RW/1C/V	**Presence Detect Changed (PDCS):** This bit is set when a Presence Detect Changed event is detected. It is subsequently cleared by software after the field has been read and processed. On-board logic per slot must set the VPP signal corresponding to this bit inactive if the FF/system does not support out-of-band presence detect. RPs may hold the re-training to occur until the SLOTSTS.PDCS bit has been cleared by software for the removal event. If the device is configured as a slot in the EXPCAP_.SI bit, this bit will need to be cleared before re-training will occur.
2	0x0 RW/1C/V	**MRL Sensor Changed (MRLSC):** This bit is set when an MRL Sensor Changed event is detected. It is subsequently cleared by software after the field has been read and processed. On-board logic per slot must set the VPP signal corresponding to this bit inactive if the FF/system does not support out-of-band presence detect.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW/1C/V	**Power Fault Detected (PFD):** This bit is set when a power fault event is detected by the power controller. It is subsequently cleared by software after the field has been read and processed. On-board logic per slot must set the VPP signal corresponding to this bit inactive if the FF/system does not support out-of-band presence detect.
0	0x0 RW/1C/V	**Attention Button Pressed (ABP):** This bit is set when the attention button is pressed. It is subsequently cleared by software after the field has been read and processed. On-board logic per slot must set the VPP signal corresponding to this bit inactive if the FF/system does not support out-of-band presence detect. Design should implement this as an edge detection logic in the chipset/platform to recognize a 0 -) 1 transition as a ABP event. Due to the long time frames for human interaction, software could potentially have serviced and cleared this event while the operator is pressing the attention button. For instance, if the user presses the Attention button that lasts for 2ms and the VPP sampling rate is, say 100us and if the Interrupt Service routine (ISR) processes and clears the ABP in 100us, there could be up to 10 (i.e 2000/(100+100)) different interrupts for the same event.Hardware must only generate 1 interrupt for every ABP event by treating it as edge based rather than level based event.

48.2.38 ROOTCTL—Offset 5Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 5Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:5	0x0 RO	**RSVD0:** Reserved
4	0x0 RW	**CRS Software Visibility Enable (CRSSVE):** This bit, when set, enables the Root Port to return Configuration Retry Status (CRS) Completion status to software. • 1: Enable software to received a CRS status. This allows software to make the decision to re-issue the configuration request or move on and re-issue the request at a later time. • 0: Disable software from receiving a CRS response. The PCIe will wait and re-issue the configuration request until it receives a response other than CRS without notifying software. CRS is implemented for general Root ports. (See 'ROOTCAP').
3	0x0 RW	**PME Interrupt Enable (PMEIE):** This field controls the generation of interrupts for PME messages. • 1: Enables interrupt generation upon receipt of a PME message as reflected in the PME Status bit defined in the ROOTSTS register. A PME interrupt is generated if the PMESTATUS register bit defined i 'Root Status Register "ROOTSTS—Offset 60h" on page 1466, is set when this bit is set from a cleared state. • 0: Disables interrupt generation for PME messages.
2	0x0 RW	**System Error on Fatal Error Enable (SEFEE):** This field controls generation of system errors in the PCI-Express port hierarchy for fatal errors. • 1: indicates that a System Error should be generated if a fatal error (ERR_FATAL) is reported by any of the devices in the hierarchy associated with and including this PCI-Express port. • 0: No System Error should be generated on a fatal error (ERR_FATAL) reported by any of the devices in the hierarchy.
1	0x0 RW	**System Error on Non-Fatal Error Enable (SENFEE):** This field controls generation of system errors in the PCI-Express port hierarchy for non-fatal errors. • 1: indicates that a System Error should be generated if a non-fatal error (ERR_NONFATAL) is reported by any of the devices in the hierarchy associated with and including this PCI-Express port. • 0: No System Error should be generated on a non-fatal error (ERR_NONFATAL) reported by any of the devices in the hierarchy.
0	0x0 RW	**System Error on Correctable Error Enable (SECEE):** This field controls generation of system errors in the PCI-Express port hierarchy for correctable errors. • 1: indicates that a System Error should be generated if a correctable error (ERR_COR) is reported by any of the devices in the hierarchy associated with and including this PCI-Express port. • 0: No System Error should be generated on a correctable error (ERR_COR) reported by any of the devices in the hierarchy associated with and including this PCI-Express port.

48.2.39 ROOTCAP—Offset 5Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 5Eh

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:1	0x0 RO	**RSVD0:** Reserved
0	0x1 RW/L	**CRS Software Visibility (CRSSV):** This bit, when set, indicates that the Root Port is capable of returning Configuration Retry Status (CRS) on completions to software. Based on Design input, the CRS notification will be implemented in the EIP PCIe macro and hence the default is set to 1. The field attribute is made as RW-O for any specific changes to be installed by BIOS **Power Well:** PRST

48.2.40 ROOTSTS—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**RSVD0:** Reserved
17	0x0 RO/V	**PME Pending (PMEPEND):** This field indicates that another PME is pending when the PME Status bit is set. When the PME Status bit is cleared by software, the pending PME is delivered by hardware by setting the PME Status bit again and updating the Requestor ID appropriately. The PME pending bit is cleared by hardware if no more PMEs are pending. ***Note:*** The root port can handle two outstanding PM_PME messages in its internal queues of the Power Management controller per port. If the downstream device issues more than 2 PM_PME messages successively, it will be dropped.
16	0x0 RW/1C/V	**PME Status (PMESTS):** This field indicates status of a PME that is underway in the PCI-Express port. 1: PME was asserted by a requester as indicated by the PMEREQID field. This bit is cleared by software by writing a '1'. Subsequent PMEs are kept pending until the PME Status is cleared.
15:0	0x0 RO/V	**PME Requester ID (PMERID):** This field indicates the PCI requester ID of the last PME requestor.

48.2.41 DEVCAP2—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 64h

Default: 00000437h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:22	0x0 RW/L	**Max End-End TLP Prefixes (MAXE2ETLP):** Indicates the maximum number of End-End TLP Prefixes supported by this Function. TLPs received by this Function that contain more End-End TLP Prefixes than are supported must be handled as Malformed TLPs. • 01: 1 End-End TLP Prefix • 10: 2 End-End TLP Prefixes • 11: 3 End-End TLP Prefixes • 00: 4 End-End TLP Prefixes • If End-End TLP Prefix Supported is Clear, this field is Reserved. **Power Well:** PRST
21	0x0 RW/L	**End-End TLP Prefix Supported (E2ETLPS):** Indicates whether End-End TLP Prefix support is offered by a Function. • 0: No Support • 1: Support is provided to receive TLPs containing End-End TLP Prefixes. The EIP does not support E2E TLP prefix and is hardwired to 0. **Power Well:** PRST
20	0x0 RW/L	**Extended Fmt Field Supported (EXFMTFS):** • 0: The Function supports a 2-bit definition of the Fmt field (default) • 1: The Function supports the 3-bit definition of the Fmt field. Must be Set for Functions that support End-End TLP Prefixes. **Power Well:** PRST
19:18	0x0 RW/L	**OBFF Supported (OBFFS):** • 00b: OBFF Not Supported • 01b: OBFF supported using Message signaling only • 10b: OBFF supported using WAKE# signaling only • 11b: OBFF supported using WAKE# and Message signaling Applicable only to Root Ports, Switch Ports, and Endpoints that support this capability. Must be 00b for other function types. **Power Well:** PRST
17:14	0x0 RO	**RSVD1:** Reserved
13:12	0x0 RW/L	**TPH Completer Supported (TPHCS):** Value indicates Completer support for TPH or Extended TPH. • 00b:TPH and Extended TPH Completer not supported • 01b: TPH Completer supported, Extended TPH completer not supported • 10b: Reserved • 11b: Both TPH and Extended TPH Completer supported Applicable only to Root Ports and Endpoints. Must be 00b for other function types. **Power Well:** PRST
11	0x0 RW/L	**LTR Mechanism Supported (LTRMS):** This bit when set indicates support for the Latency Tolerance Reporting (LTR) mechanism. **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW/L	**No RO-enabled PR-PR Passing (NROEPRPASS):** This bit if set to 1b disables passing permitted by row entry A2b in PCIe ordering table that is associated with the Relaxed Ordering Attribute field being set. This bit applies only for Switches and RCs that support peer-to-peer traffic between ports. The bit only applies to posted requests being forwarded through the switch or RC. It does not apply to traffic originating or terminating with in the switch or RC itself. **Power Well:** PRST
9	0x0 RW/L	**AD128 CAS Completer Supported (AD128ACS):** This bit must be set to 1b if the function supports this optional capability. Applicable to functions with memory space BARs as well as Root Ports. **Power Well:** PRST
8	0x0 RW/L	**AD64-bit AtomicOp Completer Supported (AD64ACS):** This bit must be set to 1b if the function supports this optional capability. Applicable to Functions with Memory Space BARs as well as all Root Ports, must be 0b otherwise. Includes FetchAdd, Swap, and CAS AtomicOps. **Power Well:** PRST
7	0x0 RW/L	**AD32 bit AtomicOp Completer Supported (AD32ACS):** Applicable to Functions with Memory Space BARs as well as all Root Ports, must be 0b otherwise. Includes FetchAdd, Swap, and CAS AtomicOps. This bit must be set to 1b if the Function supports this optional capability. This is set to 1 for Rootport implementations in the PCIe EIP. **Power Well:** PRST
6	0x0 RW/L	**AtomicOp Routing Supported (ARS):** This bit must be set to 1b if the port supports this optional capability. Applicable only to switch upstream ports, Switch downstream ports, and root ports. Must be 00b for other function types. **Power Well:** PRST
5	0x1 RW/L	**ARI Forwarding Supported (ARI):** This bit is set to 1b indicating that the downstream port supports this capability. Applicable only to Switch Downstream Ports and Root Ports, must be 0b for other Function types. This bit must be set to 1b if a Switch Downstream Port or Root Port supports this optional capability. **Power Well:** PRST
4	0x1 RW/L	**Completion Timeout Disable Support (CTDS):** A value of 1b indicates support for the completion Timeout Disable Mechanism. Support of completion timeout disable is optional for Root Ports. The PCIe port supports completions timeout disable. **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x7 RW/L	**Completion Timeout Range Supported (CTRS):** This field indicates device support for the optional Completion Timeout programmability mechanism. This mechanism allows system software to modify the Completion Timeout value. This field is applicable only to Root Ports, Endpoints that issue requests on their own behalf, and PCI Express to PCI/PCI-X Bridges that take ownership of request issues on PCI Express. Four time values ranges are defined: • Range A: 50us to 10ms • Range B: 10ms to 250ms • Range C: 250ms to 4s • Range D: 4s to 64s Bits ares set according to table below to show timeout value ranges supported. • 0000b: Completions Timeout programming not supported -- values are fixed by implementation in the range 50us to 50ms. • 0001b: Range A • 0010b: Range B • 0011b: Range A and B • 0110b: Range B and C • 0111b: Range A, B, and C • 1111b: Range A, B, C and D All other values are reserved. • For all other devices this field is reserved and maybe be hardwired to 0000b. **Power Well:** PRST

48.2.42 DEVCTL2—Offset 68h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 68h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**End-End TLP Prefix Blocking (E2ETLPBLK):** Controls whether the routing function is permitted to forward TLPs containing an End-End TLP Prefix. • 0: Forwarding Enabled - Function is permitted to send TLPs with End-End TLP Prefixes. • 1: Forwarding Blocked - Function is not permitted to send TLPs with End-End TLP Prefixes.
14:13	0x0 RW	**OBFF Enable (OBFFE):** • 00b: OBFF Disabled • 01b: OBFF Enabled using Message signaling [Variation A] • 10b: OBFF Enabled using Message signaling [Variation B] • 11b: OBFF Enabled using WAKE# signaling This field is required for all Ports that support the OBFF Capability. For a Multi-Function Device associated with an Upstream Port of a Device that implements OBFF, the field in Function 0 is of type RW, and only Function 0 controls the Component's behavior. In all other Functions of that Device, this field is of type RsvdP.
12:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RW/V	**LTR Mechanism Enable (LTRME):** When set to 1b, this bit enables Upstream Ports to send LTR messages and Downstream Ports to process LTR Messages. Applicable to Root Ports, Switches, and Endpoints that implement the LTR capability must implement this bit. For Downstream Ports, this bit must be reset to the default value if the Port goes to DL_Down status.
9	0x0 RO	**IDO Completion Enable (IDOCE):** This bit when set to 1b allows the function to set the ID-Based Ordering (IDO) bit of completions it returns. Applicable only to Endpoints including RC integrated Endpoints and Root Ports.
8	0x0 RO	**IDO Request Enable (IDORE):** This bit when set to 1b allows the function to set the ID-Based Ordering (IDO) bit on requests it initiates. Applicable only to Endpoints including RC integrated Endpoints and Root Ports.
7	0x0 RW	**AtomicOp Egress Blocking (AEB):** When this bit is set, AtomicOp requests that target this out going Egress port must be blocked. Applicable and mandatory for switch Upstream Ports, Switch Downstream Ports, and Root Ports that implement AtomicOp routing capability. Otherwise, must be hardwired to 0b.
6	0x0 RW	**AtomicOp Requester Enable (ARE):** Applicable only to Endpoints and Root Ports, must be hardwired to 0b for other Function types. The Function is allowed to initiate AtomicOp Requests only if this bit and the Bus Master Enable bit in the Command register are both Set.
5	0x0 RW	**ARI Forwarding Enable (ARIE):** When set to 1b, ARI is enabled for the downstream port or root ports. The Downstream Port disables its traditional Device Number field being 0 enforcement when turning a Type 1 Configuration Request into a Type 0 Configuration Request, permitting access to Extended Functions in an ARI Device immediately below the Port. Default value of this bit is 0b.
4	0x0 RW	**Completion Timeout Disable (CTD):** • 1: Disable the completions timeout mechanism for all NP transactions. • 0: Completion timeout is enabled for all NP transactions.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RW	**Completion Timeout Value (CTV):** In devices that support completion timeout programmability, this field allows system software to modify the completion timeout range. The following encodings and corresponding timeout ranges are defined based on implementation choice. This field provides finer control based over the ranges chosen by DEVAP2.CTRS. The implementation specific range is shown in brackets • 0000b: 50us to 50ms (16.8ms - 25.2ms based on core clk period) • 0001b: 50us to 100us (65.5us - 99.3us based on core clk period) • 0010b: 1ms to 10ms (4.2ms - 6.3ms based on core clk period) • 0101b: 16ms to 55ms (33.6ms - 50.3ms based on core clk period) • 0110b: 65ms to 210ms (134.2ms - 201.3ms based on core clk period) • 1001b: 260ms to 900ms (536.9ms - 805.3ms based on core clk period) • 1010b: 1s to 3.5s (2.1s - 3.2s based on core clk period) • 1101b: 4s to 13s (8.6s - 12.9s based on core clk period) • 1110b: 17s to 64s (34.4s - 51.5s based on core clk period) • All others are reserved. It is highly recommended that the completion timeout value not be less then 10ms. A small completion timeout value may result in premature completion timeout for slower responding devices.

48.2.43 LINKCAP2—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 6Ch

Default: 0000000Eh

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22:16	0x0 RW/L	**Lower SKP OS Reception Supported Speeds Vector (LSKPOSRSSV):** If this field is non-zero, it indicates that the Port, when operating at the indicated speed(s) supports SRIS and also supports receiving SKP OS at the rate defined for SRNS while running in SRIS. Bit definitions within this field are: • Bit 0 2.5 GT/s • Bit 1 5.0 GT/s • Bit 2 8.0 GT/s • Bits 6:3 RsvdP Multi-Function devices associated with an Upstream Port must report the same value in this field for all Functions. Behavior is undefined if a bit is Set in this field and the corresponding bit is not Set in the Supported Link Speeds Vector. Currently, design does not support reception of low frequency SOS in L0. **Power Well:** PRST
15:9	0x0 RW/L	**Lower SKP OS Generation Supported Speeds Vector (LSKPOSGSSV):** If this field is non-zero, it indicates that the Port, when operating at the indicated speed(s) supports SRIS and also supports software control of the SKP Ordered Set transmission scheduling rate. Bit definitions within this field are: • Bit 0 2.5 GT/s • Bit 1 5.0 GT/s • Bit 2 8.0 GT/s • Bits 6:3 RsvdP Multi-Function devices associated with an Upstream Port must report the same value in this field for all Functions. Behavior is undefined if a bit is Set in this field and the corresponding bit is not Set in the Supported Link Speeds Vector. **Power Well:** PRST
8	0x0 RW/L	**Crosslink Supported (CLS):** When set to 1b, this bit indicates that the associated Port supports crosslinks When set to 0b on a Port that supports Link speeds of 8.0 GT/s or higher, this bit indicates that the associated Port does not support crosslinks. When set to 0b on a Port that only supports Link speeds of 2.5 GT/s or 5.0 GT/s, this bit provides no information regarding the Port's level of crosslink support. It is recommended that this bit be Set in any Port that supports crosslinks even though doing so is only required for Ports that also support operating at 8.0 GT/s or higher Link speeds. ***Note:*** Software should use this bit when referencing fields whose definition depends on whether or not the Port supports crosslinks. **Power Well:** PRST
7:1	0x7 RO/V	**Supported Link Speeds Vector (SLNKSPV):** This field indicates the supported Link speed(s) of the associated Port. For each bit, a value of 1b indicates that the corresponding Link speed is supported, otherwise, the Link speed is not supported. Bit definitions are: • Bit 1 2.5 GT/s • Bit 2 5.0 GT/s • Bit 3 8.0 GT/s • Others: Reserved
0	0x0 RO	**RSVD1:** Reserved

48.2.44 LINKCTL2—Offset 70h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 70h

Default: 0003h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RW/P	**Compliance Preset/De-emphasis (CD):** For 8 GT/s and 5 GT/s: This bit sets the transmitter preset level for Polling. Compliance state if the entry occurred due to the Enter Compliance bit being 1b. The Encoding are defined as follows: 8 GT/s Rate: • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. 5 GT/s Rate: • 001b: -3.5dB • 000b: -6 dB • All other are reserved. When the link is operating at 2.5 Gb/s, the setting of this bit has no effect. Components that support only 2.5 GT/s speed are permitted to hardwire this bit to 0b.
11	0x0 RW/P	**Compliance SOS (CSOS):** When set to 1b, the LTSSM is required to send Skip Ordered Sets periodically in between the (modified) compliance patterns.
10	0x0 RW/P	**Enter Modified Compliance (EMC):** When set to 1b, the device transmits Modified Compliance Pattern if the LTSSM enters Polling. Compliance substate. This register is intended for debug, compliance testing purposes only. System firmware and software is allowed to modify this register only during debug or compliance testing. In all other cases, the system must ensure that this register is set to the default value.
9:7	0x0 RW/V/P	**Transmit Margin (TM):** This field controls the value of the non-de-emphasized voltage level at the transmitter pins. This field is reset to 000b on entry to the LTSSM Polling. Configuration substate. • 000b: Normal operating range • 001b: 800-1200mV for full swing and 400-700mV for half-swing • 010b-110b: TBD • Others: Reserved This register is intended for debug, compliance testing purposes only. System firmware and software is allowed to modify this register only during debug or compliance testing. In all other cases, the system must ensure that this register is set to the default value.
6	0x0 RW/L	**Selectable De-emphasis (SD):** Applicable to RootPorts and downstream ports of PCI Express to PCIe bridges. When the link is operating at 5 Gb/s speed, this bit selects the level of de-emphasis for an Downstream Port. Encodings: 1b -3.5 dB 0b -6 dB When the Link is operating at 2.5 GT/s speed, the setting of this bit has no effect. **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW/P	**Hardware Autonomous Speed Disable (HASD):** When set, this bit disables hardware from changing the link speed for device specific reasons other than attempting to correct unreliable link operation by reducing link speed for device-specific reasons other than attempting to correct unreliable link operations by reducing link speed. Initial transition to the highest supported common link speed is not blocked by this bit.
4	0x0 RW/V/P	**Enter Compliance (EC):** Software is permitted to force a link to enter compliance mode at the speed indicated in the Target Link Speed field by setting this bit to 1b in both components on a link and then initiating a hot reset on the link.
3:0	0x3 RW/V/P	**Target Link Speed (TLS):** For downstream ports and root ports, this field sets an upper limit on link operational speed by restricting the values advertised by the Downstream Port in its training sequences. • 0001b: 2.5 Gb/s Target Link Speed • 0010b: 5.0 Gb/s Target Link Speed • 0011b: 8.0 Gb/s Target Link Speed • Others: Reserved. The encoding is the binary value of the bit in the Supported Link Speeds Vector (in the Link Capabilities 2 register) that corresponds to the desired target Link speed. • All other encodings are reserved If a value is written to this field that does not correspond to a speed included in the Supported Link Speeds field, the result is undefined. The default value of this field is the highest Link speed supported by the component (as reported in the Max Link Speed field of the Link Capabilities register) unless the corresponding platform/form factor requires a different default value. For both Upstream and Downstream Ports, this field is used to set the target compliance mode speed when software is using the Enter Compliance bit to force a Link into compliance mode.

48.2.45 LINKSTS2—Offset 72h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 72h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RW/1C/V/P	**Link Equalization Request (LNKEQREQ):** This bit is set by hardware to request the Link equalization process to be performed on the Link.
4	0x0 RO/V/P	**Equalization Phase 3 Successful (EQPH3SUCC):** When set to 1b, this bit indicates that Phase 3 of the Transmitter Equalization procedure has successfully completed.
3	0x0 RO/V/P	**Equalization Phase 2 Successful (EQPH2SUCC):** When set to 1b, this bit indicates that Phase 2 of the Transmitter Equalization procedure has successfully completed.
2	0x0 RO/V/P	**Equalization Phase 1 Successful (EQPH1SUCC):** When set to 1b, this bit indicates that Phase 1 of the Transmitter Equalization procedure has successfully completed.
1	0x0 RO/V/P	**Equalization Complete (EQCMPLT):** When set to 1b, this bit indicates that the Transmitter Equalization procedure has successfully completed.
0	0x0 RO/V	**Current De-emphasis Level (CDL):** When the link is operating at 5 Gb/s speed, this bit reflects the level of de-emphasis. • 1b: -3.5 dB • 0b: -6dB The value in this bit is undefined when the Link is not operating at 5.0 GT/s speed. Components that support only the 2.5 GT/s speed are permitted to hardwire this bit to 0b.

48.2.46 PMCAPLST—Offset 80h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 80h

Default: 8801h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x88 RO	**Next Pointer (NextPointer):** Contains the offset of the next item in the capabilities list. (SSCAPLST)
7:0	0x1 RO	**Capability ID (CapabilityID):** Identifies the function as PCI Power Management capable.

48.2.47 PMCAP—Offset 82h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 82h

Default: C803h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x19 RO	**PME_Support (PMES):** PME assertion is supported when in D3hot/D3cold. Identifies power states in which the PCIe can send an 'Assert_PMEGPE/Deassert PMEGPE' message. Bits 15, 14 and 11 must be set to '1' for PCIPCI bridge structures representing ports on root complexes. The definition of these bits is taken from the PCI Bus Power Management Interface Specification Revision 1.1. • XXXX1b - Assert_PMEGPE/Deassert PMEGPE can be sent from D0 • XXX1Xb - Assert_PMEGPE/Deassert PMEGPE can be sent from D1 (Not supported by PCI-E) • XX1XXb - Assert_PMEGPE/Deassert PMEGPE can be sent from D2 (Not supported by PCI-E) • X1XXXb - Assert_PMEGPE/Deassert PMEGPE can be sent from D3 hot (Supported by PCI-E) • 1XXXXb - Assert_PMEGPE/Deassert PMEGPE can be sent from D3 cold (Supported by PCI-E) In the EIP PCIe implementation, there is no PME support for D3 cold as the part does not have the capability. For PCIe compliance purposes, bit 15 is set to 1.
10	0x0 RO	**D2 Support (D2S):** Not supported
9	0x0 RO	**D1 Support (D1S):** Not supported
8:6	0x0 RO	**Auxiliary Current (AC):** Auxiliary power is not supported.
5	0x0 RO	**Device Specific Initialization (DSI):** Device-specific initialization is not required when transitioning to D0 from D3hot state. This bit is zero.
4	0x0 RO	**RSVD0:** Reserved
3	0x0 RO	**PME Clock (PMECLK):** Does not apply to PCI Express. Hard-wired to 0.
2:0	0x3 RO	**Version (VER):** The PM implementation in the PCIe cluster is compliant with PCI Bus Power Management Interface Specification, Revision 1.2.

48.2.48 PMCSR—Offset 84h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 84h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V/P	**PME Status (PMESTS):** Reserved.
14:13	0x0 RO	**Data Scale (DC):** Not supported
12:9	0x0 RO	**Data Select (DS):** Not supported
8	0x0 RW/P	**PME Enable (PMEEN):** Gates assertion of the PME message.
7:4	0x0 RO	**RSVD0:** Reserved
3	0x1 RW/L	**No Soft Reset (NSR):** This bit when 1b indicates that a device transitioning from D3hot to D0 does not perform an internal reset. The configuration context is preserved. **Power Well:** PRST
2	0x0 RO	**RSVD1:** Reserved
1:0	0x0 RW/V	**Power State (PS):** This field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the supported values is given below: • 0h - D0 • 3h - D3hot If software attempts to write an unsupported, optional state to this field, the write operation must complete normally, however, the data is discarded and no state change occurs.

48.2.49 PMBSE—Offset 86h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 86h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Bus Power/Clock Control Enable (BPCC_EN):** Neither bus or clock control of PCI is supported when in D3hot state. This bit is hard-wired to 0.
6	0x0 RO	**B2/B3# (B23EN):** Not supported. This bit has no meaning since the BPCC_En bit is hard-wired to 0.
5:0	0x0 RO	**RSVD0:** Reserved

48.2.50 SSCAPLST—Offset 88h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 88h

Default: 900Dh

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x90 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list. (MSICAPLST)
7:0	0xd RO	**Capability ID (CAPID):** Identifies the function as Subsystem Identification capable.

48.2.51 SSVID—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8Ch

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RW/L	**Subsystem Vendor Identifier (SSVID):** Assigned by PCI-SIG for vendor ID. **Power Well:** PRST

48.2.52 SSID—Offset 8Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/L	**Subsystem Identifier (SSID):** Assigned to uniquely identify the subsystem vendor. **Power Well:** PRST

48.2.53 MSICAPLST—Offset 90h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 90h

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list (MSIXCAPLST). A null value is used to indicate that this is the last capability. The Next Pointer is terminated for DP, vRP/vSP, RP and DMI EP in RC.
7:0	0x5 RO	**Capability ID (CAPID):** Identifies the function as MSI capable.

48.2.54 MSICTL—Offset 92h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 92h

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved
8	0x1 RW/L	**Per-vector masking capable (PVM):** This bit indicates that PCI Express ports support MSI per-vector masking. **Power Well:** PRST
7	0x0 RO	**Address 64-Bit Capable (AD64C):** When set, this bit indicates that the function is capable of generating a 64-bit message address.
6:4	0x0 RW	**Multiple Message Enable (MMEN):** Only one message is supported. These bits are R/W for software compatibility.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Only one message is supported.
0	0x0 RW	**MSI Enable (MSIE):** When set, MSI is enabled and traditional interrupt pins are not used to generate interrupts.

48.2.55 MSIADDR—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address:** Message address specified by the system, always DWORD aligned
1:0	0x0 RO	**RSVD0:** Reserved

48.2.56 MSIDATA—Offset 98h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW	**Trigger Mode (TM):** • 0: Edge Triggered • 1: Level Triggered
14	0x0 RW	**Level (LVL):** if TM is 0h, then this field is a don't care. Edge triggered messages are always treated as assert messages. For level triggered interrupts, this bit reflects the state of the interrupt input if TM is 1h, then • 0: Deassert Messages • 1: Assert Messages
13:12	0x0 RW	**Future:** These bits are don't care for an IOxAPIC interrupt message data field specification.
11:8	0x0 RW	**Delivery Mode (DM):** • 0000: Fixed: Trigger Mode can be edge or level. • 0001: Lowest Priority: Trigger Mode can be edge or level. • 0010: SMI/PMI/MCA - Not supported via MSI of root port • 0011: Reserved - Not supported via MSI of root port • 0100: NMI - Not supported via MSI of root port • 0101: INIT - Not supported via MSI of root port • 0110: Reserved • 0111: ExtINT - Not supported via MSI of primary port • 1000 -1111 - Reserved
7:0	0x0 RW	**Interrupt Vector (IV):** The interrupt vector will be modified by the EIP PCIe Gen3 to provide context sensitive interrupt information for different events that require attention from the processor. e.g Hot plug, Power Management and RAS error events.

48.2.57 MSIMSK—Offset 9Ch

The MSI Mask Bit register enables software to disable message sending on a per-vector basis.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RW	**Mask Bits (MSKB):** For each Mask bit that is set, the PCI Express port is prohibited from sending the associated message. Corresponding bits are masked if set to '1'

48.2.58 MSIPENDING—Offset A0h

The Mask Pending register enables software to defer message sending on a per-vector basis.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved
0	0x0 RO/V	**Pending Bits (PB):** For each Pending bit that is set, the PCI Express port has a pending associated message. Corresponding bits are pending if set to '1'

48.2.59 RPPMCSR—Offset A8h

bek_eip_pcie3_regs_usx16.fm bek_eip_pcie3_regs_usx8.fm
bek_eip_pcie3_regs_vsp.fm cnx_eip_pcie3_regs_dmix4.fm
cnx_eip_pcie3_regs_rp4px4.fm cnx_eip_pcie3_regs_rp4px16.fm
cnx_eip_pcie3_regs_ep.fm cnx_eip_pcie3_regs_rlusx16.fm
cdf_eip_pcie3_regs_rldsx16.fm dnv_eip_pcie3_regs_rp4px8.fm
dnv_eip_pcie3_regs_rp4px16.fm dnv_eip_pcie3_regs_rp4px4.fm
dnv_eip_pcie3_regs_vrp.fm

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A8h

Default: 00000020h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RO/V	**Mod-PHY Core Well Power Gating Status (MCWPGS):** This field reflects the effective 'Logical OR' state of the mod-PHY data lane 'Core Power Request' from controller to PHY and 'Core Power Ack' from PHY to controller for all the data lanes owned by the port. Software can read this bit to know that the mod-PHY Core Well power gating handshake is completed, before it proceeds to power down the mod-PHY Suspend Well using the RPPGEN.MDLSWPR and RPPGEN.MDLSWPA bits. This bit is intended to be used for RTD3, as part of the flow to power gate the mod-PHY Core Well.
7	0x0 RO/V	**Mod-PHY Data Lane Suspend Well Power Gating Exit Ack (MDLSWPGXA):** This fields reflects the effective 'Logical AND' of mod-PHY Data Lane Suspend Well Power Gating Exit Ack for all the data lanes owned by this port. • A '1b' indicates that at all the Data Lane Suspend Well Power Gating Exit Ack is asserted. • A '0b' indicates that at least one of the Data Lane Suspend Well Power Gating Exit Ack has been de-asserted. This bit is intended to be used for RTD3, as part of the flow to power gate the mod-PHY data lane Suspend Well.
6	0x0 RO/V	**Mod-PHY Data Lane Suspend Well Power Gating Entry Ack (MDLSWPGEA):** This fields reflects the effective 'Logical OR' of mod-PHY Data Lane Suspend Well Power Gating Entry Ack for all the data lanes owned by this port. • A '1b' indicates that at least one of the Data Lane Suspend Well Power Gating Entry Ack is still asserted. • A '0b' indicates that all the Data Lane Suspend Well Power Ack has been de-asserted. This bit is intended to be used for RTD3, as part of the flow to power gate the mod-PHY data lane Suspend Well.
5	0x1 RW	**Mod-PHY Data Lane Suspend Well Power Request (MDLSWPR):** Software can write a '0b' to this field to de-assert 'Suspend Well Power Request' to all the data lanes owned by this port only when MDLSWPGXA is '1b'. Software can write a '1b' to this field to assert Suspend Well Power Request to all the data lanes owned by this port only when MDLSWPGEA is '0b'. This bit is intended to be used for RTD3, as part of the flow to power gate the mod-PHY data lane Suspend Well.
4	0x0 RW	**PME_TO_ACK Timeout Policy (PME_TO_ACK_TOP):** When set, Root Port will trigger an exit if the link is in TXL0s or L1 and PME_TO_ACK timer times out.
3:2	0x0 RW	**PME_TO_ACK Timeout (PME_TO_ACK_TO):** This timer is activated from the time the PME_Turn_Off message is sent to the link. It will be reset once the timer expires or when PME_TO_ACK has been received from the downstream device and link has been put into L2/L3 Ready state. Once the timer expires, the Sx sequence will continue to take the link down. • 00: 1 ms (default) • 01: 10 ms • 10: 1 us (Pre-Si) • 11: Disable

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW/V/P	**L23Rdy to Detect Transition (L23RDY2DT):** When set by software, the LTSSM moves from L2/L3 Ready to Detect state. This bit is cleared by hardware once the LTSSM is in Detect state. The PHY power and clocks needed to enable this transition is brought up in response to this bit being set by software. If the link is not in L2/L3 Ready when this bit is set, the bit is cleared immediately by hardware.
0	0x0 RW/V/P	**L23Rdy Entry Request (L23RDYER):** When set by software, the corresponding Root Port will initiate the sequence to put the link into L2/L3 Ready state. PME_Turn_Off message will be sent and the corresponding PME_TO_Ack response will be returned by the device. Once the link enters L2/L3 Ready, this bit will be cleared by hardware. Alternatively, this bit will be cleared by hardware when PME_Turn_Off timer time-out.

48.2.60 PMCSRS—Offset B0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B0h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/P	**PME Status (PMESTS):** This field is utilized for Software to restore the PME Status once exit Sx State. Hardware will reflect the value to the associated PMCSR.PMESTS if this bit was written by Software.
14:0	0x0 RO	**RSVD0:** Reserved

48.2.61 PPBIFCTL—Offset C0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V/P	**Capability Lock (CL):** Lock key bit for all RW-L bits of PPBIFCTL register only. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b from IOSF-SB, this key bit can not be unlocked. Writing a 0b has no affect on this bit.
30:3	0x0 RO	**RSVD0:** Reserved
2:0	0x0 RO/V/P	**Bifurcation Control 0 (BIFCTL0):** • 111-101: Reserved • 100: x8 • 011: x4x4 • 010: x4x2x2 • 001: x2x2x4 • 000: x2x2x2x2 A write of '1' on the CL will lock this register field down as bifurcation control status information.

48.2.62 SMICSR—Offset C8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**RSVD0:** Reserved
18	0x0 RW/1C/V	**Hot Plug DLLSC SMI Status (HPLSCSMISTS):** This bit is set when rising edge detected as result of both SLOTSTS.DLLSCS and SMICSR.HPSMIE being set.
17	0x0 RW/1C/V	**Hot Plug SMI Status (HPSMISTS):** This bit is set when rising edge detected as result of both SLOTSTS.PDCS and SMICSR.HPSMIE being set.
16	0x0 RW/1C/V	**Power Management SMI Status (PMSMISTS):** This bit is set when rising edge detected as result of both ROOTSTS.PMESTS and SMICSR.PMSMIE being set.
15:2	0x0 RO	**RSVD1:** Reserved
1	0x0 RW	**Hot Plug SMI Enable (HPSMIE):** Enables the Root Port/DSP to generate SMI whenever a Hot Plug event is detected.
0	0x0 RW	**Power Management SMI Enable (PMSMIE):** Enables the Root Port to generate SMI whenever a power management event is detected.

48.2.63 SCICSR—Offset CCh

The Tag field is being used to differentiate between PMSCI (Tag = '001') and HPSCI (Tag = '000') for PMC whenever a single set of Assert/Deassert SCI is sent.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**RSVD0:** Reserved
18	0x0 RW/1C/V	**Hot Plug DLLSC SCI Status (HPLSCSCISTS):** This bit is set when rising edge detected as result of both SLOTSTS.DLLSCS and SCICSR.HPSCIE being set.
17	0x0 RW/1C/V	**Hot Plug SCI Status (HPSCISTS):** This bit is set when rising edge detected as result of both SLOTSTS.PDCS and SCICSR.HPSCIE being set.
16	0x0 RW/1C/V	**Power Management SCI Status (PMSCISTS):** This bit is set when rising edge detected as result of both ROOTSTS.PMESTS and SCICSR.PMSCIE being set.
15:2	0x0 RO	**RSVD1:** Reserved
1	0x0 RW	**Hot Plug SCI Enable (HPSCIE):** Enables the Root Port/DSP to generate SCI whenever a Hot Plug event is detected.
0	0x0 RW	**Power Management SCI Enable (PMSCIE):** Enables the Root Port to generate SCI whenever a power management event is detected.

48.2.64 SSCTL—Offset D0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + D0h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RW/1C/V/P	**Stop and Scream Event Status (SSES):** This bit indicates that a stop and scream event has occurred on the Tx side of the PCI Express port due to a header or data parity error.
7:2	0x0 RO	**RSVD1:** Reserved
1	0x0 RW	**Stop and Scream LTSSM Operation (SSLTOP):** • 0: PCIe will set the affected link to 'link.disabled' state when the stop and scream condition is signaled by the Transaction Layer due to poisoned data. • 1: PCIe will set the affected link to 'link.disabled' state and then provide feedback to the Transaction Layer. The transaction layer will then initiate a link retraining sequence via the LTSSM to bring it back alive. Sometime the PCI Express port will be unable to return to normal operation due to the nature of the error that initiated the stop and scream mechanism. If Software desires to retrain the link when this field is set to 0, it can perform either of the following tasks: Change the LINKCTL.RL register field or Change mode field (SSLTOP) in this register to 1b or Initialize the BCTL.SBR to clear the sub-hierarchy of the PCI-Express port and reset. This SBR method is only applicable to standard PCI-Express ports and not the DMI This field will only return the PCI Express link back to normal operation after a logged Stop and Scream event. Errors such as header/control parity error which utilize the Stop and Scream mechanism will not be controlled by this register field. A platform reset will be required to re-enable the link. **Power Well:** PRST
0	0x0 RW	**Stop and Scream Enable (SSEN):** • 0: Disable Stop and Scream (normal/default operation) • 1: Enables the link to perform Stop and Scream functionality. When this bit is set, if PCIe root port or downstream port encounters a poisoned data traversing the outbound path, the cluster stops the data, sets the link_down condition internally and places the link in disable. Inbound/outbound paths are blocked and all outstanding requests will be master aborted including Memory, I/O and configuration requests. **Power Well:** PRST

48.2.65 EXPPTMBARCTL—Offset D2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + D2h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RW/L	**Disable MBAR mPhy (DMBARMPHY):** When set to a 1b, memory transaction targeting the 64K-128K space of the EXPPTMBAR dedicated for mPhy will be prevented from accessing control registers. Memory read transactions will return 0's. Memory writes will have no effect. **Power Well:** PRST
7:4	0x0 RO	**RSVD1:** Reserved
3	0x0 RW/L	**Disable Forth 4K Page (D4THPAGE):** When set to a 1b, memory transaction targeting the forth 4K page of the EXPPTMBAR will be prevented from accessing control registers. Memory read transactions will return 0's. Memory writes will have no effect. **Power Well:** PRST
2	0x0 RW/L	**Disable Third 4K Page (D3RDPAGE):** When set to a 1b, memory transaction targeting the third 4K page of the EXPPTMBAR will be prevented from accessing control registers. Memory read transactions return 0's. Memory writes will have no effect. **Power Well:** PRST
1	0x0 RW/L	**Disable Second 4K Page (D2NDPAGE):** When set to a 1b, memory transaction targeting the Second 4K page of the EXPPTMBAR will be prevented from accessing control registers. Memory read transactions will return 0's. Memory writes will have no effect. **Power Well:** PRST
0	0x0 RW/L	**Disable First 4K Page (D1STPAGE):** When set to a 1b, memory transaction targeting the first 4K page of the EXPPTMBAR will be prevented from accessing control registers. Memory read transactions will return 0's. Memory writes will have no effect. **Power Well:** PRST

48.2.66 PPD0—Offset D4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + D4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RW-L bits of PPD0 register only. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
30:14	0x0 RO	**RSVD0:** Reserved
13	0x0 RW/V/L	**Configuration Retry Enable (CRE):** This bit controls the ability of the external side of the NTB to respond to transactions (normal, UR, CRS). The PCIe link is expected to be active after training in about 10-100ms from platform reset deassertion. However, the internal controller may take longer to boot, and to initialize its registers. To allow longer boot time, the CRE bit is used to ensure that the Internal side and related functionality is up and operational before allowing transactions from the external side to be processed even though link training could have been completed prior. • 0: External Link handles PCIe transactions (configuration, memory, messages) in the normal fashion during linkup state. • 1: External Link presents Configuration Retry Status (CRS) to the incoming configuration cycle on the external cycle in the linkup state. • All other requests will be URed. The NTB will respond with Configuration Retry Status (CRS) on the PCIe link for configuration cycles until such time when the internal firmware completes initialization of all internal resources. If the external side sends any other request (memory, messages) before this initialization is done, it will be master aborted (UR) on the external side. It is the responsibility of software to adhere to this flow. This bit is reserved in Root Ports, Downstream Port and DMI EP in RC. This bit is not functional.
12:10	0x0 RO	**RSVD1:** Reserved
9:8	0x0 RO	**NTB Port Definition (NPD):** Value indicating the value to be loaded into the DID register (offset 02h). • 00b - RP0 • 01b - 2 NTBs connected back to back • 10b - Reserved • 11b - Reserved (NTB connected to a RP) The default value is determined by soft straps/fuse proxy. (DSP and NTB only)
7:4	0x0 RO	**RSVD2:** Reserved
3	0x0 RW/V	**Initiate Link Training 0 (ILINKTRN0):** This bit controls PCI Express port link training for associated ports. A value of '1' initiates link training on ports 0, 1, 2, and 3. After writing this bit to a a '1', software can poll the Data Link Layer link active bit in the LNKSTS register to determine if a port is up and running. The associated ports will not automatically initiate link training after reset unless soft strap default values have already set this bit to '1'. A write of '0' has no effect. A write of '1' will lock this register bit down and initiate link training. • 0: The associated PCI Express ports have not initiated link training. • 1: The associated PCI Express ports are initiating link training or have trained. The default value is determined by soft straps This will reset on DL_Down events when in NTB mode **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
2:1	0x0 RO	**RSVD3:** Reserved
0	0x0 RW/P	**Clear ILINKTRN0 on Link down (ClrTrnEnOnLnkDn):** when set to 1, a link down event will cause the link train enable field of this register to be cleared and block subsequent training until that train enable is set again. If 0, a link down will not clear the train enable unless a link down causes a reset.

48.2.67 PBTXNCTL—Offset D8h

This register is reserved for the design team. These bits will control implementation specific features in the transaction layer.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + D8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**Disable APIC EOI Message (DEOIM):** This bit when set to 1b will disable downstream forwarding of the End of Interrupt (EOI) message by the Root Ports or DSP. The EOI message is silently dropped.
30	0x0 RW/P	**GPE Enable (GPEE):** • 1b: Enables 'Assert GPE' (Deassert_GPE) messages to be sent from Root Port. • 0b: Disables 'Assert GPE' (Deassert_GPE) messages. This bit has an overriding effect to generate an ACPI HP event over traditional interrupts. This bit only control the ports internally generated Assert, Deassert_GPE messages
29:26	0x0 RW/P	**Virtual Pin Port Number (VPPN):** This field is used to identify the SMBus device and port number of the 9555 SMBus components. [29:27] = SMBus Address [26] = IO Port
25	0x0 RW/P	**Enable Virtual Pin Port (DVPP):** This bit when set to 1b will enable the VPP pins for the given PCI Express port. • 1b: VPP is enable for this PCI Express port. • 0b: VPP is disable for this PCI Express port.
24	0x0 RW/P	**Hot Plug Form Factor (HPFF):** This bit determines the what hot plug form-factor a particular port. • 0: CEM/Cable • 1: SIOM This bit is used to interpret bit 6 in the VPP serial stream for the port as either MRL# (CEM/Cable) or EMILS (SIOM) input.
23:18	0x0 RW/P	**Undefined:** Design Specific Control bits
17	0x0 RW/P	**Select Override Enable (SOE):** This bit when 1b enables the VPP Select Override field to program the 9555 IO pin direction.
16	0x0 RW/P	**Inversion Override Enable (IOE):** This bit when 1b enables the VPP Inversion Override field to program the 9555 IO pin polarity.
15:8	0x0 RW/P	**VPP Select Override (VPPSELOV):** This field is used by the HP SMBus controller to program the 9555 IO pin direction. Each bit corresponds to a pin for the VPP. • 0b: indicates input • 1b: indicates output pin
7:0	0x0 RW/P	**VPP Inversion Override (VPPIOV):** This field is used by the HP SMBus controller to program the 9555 IO pin polarity. Each bit corresponds to a pin for the VPP. • 1b: Invert Polarity. • 0b: Polarity not inverted.

48.2.68 PBPHYCTL—Offset E0h

This register is reserved for the design team. These bits will control implementation specific features in the physical layer.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + E0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/P	**Undefined:** Design Specific Control bits

48.2.69 PLKCTL—Offset EAh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + EAh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW/L	**Lnk Layer Capability Lock (LLCL):** Lock key bit for all RWS-L bits located in the following CSRs. XPLDEF XPLDEF2 LLRBERRINJCTL RXPERRINJCTL CRCERRINJCTL CRCERRINJMSK RTRYCTL PACKTHRESH • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
1	0x0 RW/L	**Txn Layer Capability Lock (TLCL):** Lock key bit for all RWS-L bits located in XPEINJ[1:0], XPCDTHROTTLEP,N,C, XPTDEF*, MBAR01CTL EXPPTMBARCTL. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
0	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RWS-L bits (capabilities, next capability pointer, SSID/SVID, slot register, etc) bits for the function. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST

48.2.70 LTRCSR—Offset ECh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + ECh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RW-L bits of LTRCSR and LTROVR register only. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST
30:18	0x0 RO	**RSVD0:** Reserved
17	0x0 RW/1C/V	**Invalid LTR Latency Scale Value Received (IVLSVR):** Set to '1' by hardware when an LTR message is received with Not Permitted Latency Scale Value and both the LTR Mechanism Supported bit and the LTR Mechanism Enable bit are set. Cleared to '0' by software writing 1 to this register.
16	0x0 RW/1C/V	**LTR Received (LTRR):** Set to '1' by hardware when an LTR message is received and both the LTR Mechanism Supported bit and LTR Mechanism Enable bit are set. It can be set/cleared by hardware internally, or software by writing 1 to clear it.
15:4	0x0 RO	**RSVD1:** Reserved
3	0x0 RW/P	**LTR Aggregation Mode Disable (LTRAMD):** Default is 0 to enable LTR aggregation mode. Set 1 to disable LTR Aggregation Mode.
2	0x0 RW/L	**LTR Override Policy (LTROVRPLCY):** This register bit defines the LTR override behavior when the respective LTR Override Enable bits are set. • 0: The LTR Override values will be in effect when the link is up and in D0, until a valid new LTR message is received from the device. • 1: The LTR Override values will be in effect when the link is up and in D0. LTR values from the valid new LTR message received from device will be ignored. ***Note:*** This register should be programmed prior to enabling LTR override and should not be modified after LTR override has been enabled. **Power Well:** PRST
1	0x0 RW/L	**LTR No-Snoop Override Enable (LTRNSOVREN):** When this bit is set, the latency tolerance values for this port will be overridden to the values programmed in the LTRNSLOVRV, LTRNSLSOVRV and LTRNSROVR fields. The latency values from the LTR messages received from the devices will be ignored. Hardware should treat this bit as dynamic and the transition of this bit from '0' to '1' will cause a new IOSF sideband LTR message to be sent to update PMC if the new aggregated latency values change as a result of this. **Power Well:** PRST
0	0x0 RW/L	**LTR Snoop Override Enable (LTRSOVREN):** When this bit is set, the latency tolerance values for this port will be overridden to the values programmed in the LTRSLOVRV, LTRSLSOVRV and LTRSROVR fields. The latency values from the LTR messages received from the devices will be ignored. Hardware should treat this bit as dynamic and the transition of this bit from '0' to '1' will cause a new IOSF sideband LTR message to be sent to update PMC if the new aggregated latency values change as a result of this. **Power Well:** PRST

48.2.71 LTRL—Offset F0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + F0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO/V	**LTR No-Snoop Latency Field (LTRNSLF):** This field contains the No-Snoop Latency field of the latest received LTR Message. When an LTR message is received and both the LTR Mechanism Supported bit and LTR Mechanism Enable field are set, bytes 12:13 of the PCIe header are stored in this register. This includes the case where the Latency Scale Value contains 'Not Permitted' encoding.
15:0	0x0 RO/V	**LTR Snoop Latency Field (LTRSLF):** This field contains the Snoop Latency field of the latest received LTR Message. When an LTR message is received and both the LTR Mechanism Supported bit and LTR Mechanism Enable field are set, bytes 14:15 of the PCIe header are stored in this register. This includes the case where the Latency Scale Value contains 'Not Permitted' encoding.

48.2.72 LTROVR—Offset F4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + F4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**LTR No-Snoop Requirement Bit Override (LTRNSROVR):** This field contains the No-Snoop Requirement bit override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
30:29	0x0 RO	**RSVD0:** Reserved
28:26	0x0 RW/L	**LTR No-Snoop Latency Scale Override Value (LTRNSLSOVRV):** This field contains the Snoop latency scale override value for this particular PCIe root port. • 000: LTRNSLOVRV times 1 ns • 001: LTRNSLOVRV times 32 ns • 010: LTRNSLOVRV times 1,024 ns • 011: LTRNSLOVRV times 32,768 ns • 100: LTRNSLOVRV times 1,048,576 ns • 101: LTRNSLOVRV times 33,554,432 ns • Others: Not Permitted. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
25:16	0x0 RW/L	**LTR No-Snoop Latency Override Value (LTRNSLOVRV):** This field contains the No-Snoop latency override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
15	0x0 RW/L	**LTR Snoop Requirement Bit Override (LTRSROVR):** This field contains the No-Snoop Requirement bit override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
14:13	0x0 RO	**RSVD1:** Reserved
12:10	0x0 RW/L	**LTR Snoop Latency Scale Override Value (LTRSLSOVRV):** This field contains the Snoop latency scale override value for this particular PCIe root port. • 000: LTRSLOVRV times 1 ns • 001: LTRSLOVRV times 32 ns • 010: LTRSLOVRV times 1,024 ns • 011: LTRSLOVRV times 32,768 ns • 100: LTRSLOVRV times 1,048,576 ns • 101: LTRSLOVRV times 33,554,432 ns • Others: Not Permitted. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST
9:0	0x0 RW/L	**LTR Snoop Latency Override Value (LTRSLOVRV):** This field contains the Snoop latency override value for this particular PCIe root port. This field is Read-Only when LTRCSR.CL is set. **Power Well:** PRST

48.2.73 INTXSWZCTL—Offset F8h

This register provides software the ability to swizzle the legacy interrupts (INTx) from each port and remap them to a different interrupt type for purposes of interrupt rebalancing. This swizzling only applies to inbound INTx messages that arrive on the secondary side of the switch or root port. This register does not affect PCI-Express defined INTx re-map based on device # that is required by the PCI-Express base specification.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + F8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**RSVD0:** Reserved
2:0	0x0 RW/L	**INTx Swizzle (INTXSWZ):** The encoding below defines the target INTx type to which the incoming INTx message is mapped to for that port. • 000b:INTA=)INTA, INTB=)INTB, INTC=)INTC, INTD=)INTD, • 001b:INTA=)INTB, INTB=)INTC, INTC=)INTD, INTD=)INTA, • 010b:INTA=)INTC, INTB=)INTD, INTC=)INTA, INTD=)INTB, • 011b:INTA=)INTD, INTB=)INTA, INTC=)INTB, INTD=)INTC, • 100b:INTA=)INTA, INTB=)INTA, INTC=)INTA, INTD=)INTA, **Power Well:** PRST

48.2.74 CFGAGTERR—Offset FCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + FCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RW/1C/V/P	**Data Parity Error Status (DPES):** Reserved.
9	0x0 RO	**RSVD1:** Reserved
8	0x0 RW/1C/V/P	**Transaction Layer Internal Parity Error Status (TLIPES):** Reserved.
7	0x0 RW/1C/V/P	**Link Layer Internal Parity Error Status (LLIPES):** Reserved.
6	0x0 RW/1C/V/P	**Physical Layer Internal Parity Error Status (PLIPES):** Reserved.
5	0x0 RO	**RSVD2:** Reserved
4	0x0 RW/P	**Data Parity Error Mask (DPEM):** Reserved.
3	0x0 RO	**RSVD3:** Reserved
2	0x0 RW/P	**Transaction Layer Internal Parity Error Mask (TLIPEM):** Reserved.
1	0x0 RW/P	**Link Layer Internal Parity Error Mask (LLIPEM):** Reserved.
0	0x0 RW/P	**Physical Layer Internal Parity Error Mask (PLIPEM):** Reserved.

48.2.75 AERCAPHDR—Offset 100h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 100h

Default: 13810001h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x138 RW/L	**Next Capability Offset (NCO):** Contains the offset of the next structure in the Extended Capabilities list. (ACSCAPHDR). Software will need to program this field appropriately for linked capabilities list if default is not supported. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (CV):** Indicates the version of the Capability structure present.
15:0	0x1 RO	**Extended Capability ID (EXCAPID):** Identifies the function as Advanced Error Reporting capable.

48.2.76 ERRUNCSTS—Offset 104h

This register reports the error status of individual uncorrectable error sources. An individual error status bit that is set to 1 indicates that a particular error occurred. Software can clear an error status by writing a 1 to the respective bit.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 104h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**RSVD0:** Reserved
26	0x0 RW/1C/V/P	**Poisoned TLP Egress Blocked Status (PTLPEBS):** Reserved.
25	0x0 RO	**TLP Prefix Blocked Error Status (TPBES):** Reserved.
24	0x0 RW/1C/V/P	**Atomic Egress Blocked Status (AEBE):** This bit is set whenever an Atomic OP TLP is blocked on any egress port
23	0x0 RW/1C/V/P	**MC Blocked TLP Status (MCE):** This bit is set whenever a Multicast TLP is blocked.
22	0x0 RW/1C/V/P	**Uncorrectable Internal Error Status (UIE):** This bit is set whenever an uncorrectable internal error is detected.
21	0x0 RW/1C/V/P	**ACS Violation Status (ACSE):** This bit is set whenever an ACS violation is detected by the PCI Express port.
20	0x0 RW/1C/V/P	**Unsupported Request Error Status (URE):** This bit is set whenever an unsupported request is detected on PCI Express port
19	0x0 RW/1C/V/P	**ECRC Error Status (ECRCE):** ECRC checking is optional for project specific.
18	0x0 RW/1C/V/P	**Malformed TLP Status (MTLPE):** This bit is set when it receives a malformed TLP. Header logging is performed.
17	0x0 RW/1C/V/P	**Receiver Overflow Status (ROE):** This bit is set when the PCI Express interface unit receive buffers overflow.
16	0x0 RW/1C/V/P	**Unexpected Completion Status (UCE):** This bit is set whenever a completion is received with a requestor ID that does not match side A or side B, or when a completion is received with a matching requestor ID but an unexpected tag field. Header logging is performed.
15	0x0 RW/1C/V/P	**Completer Abort Status (CAE):** The bridge sets this bit and logs the header associated with the request when the configuration unit signals a completer abort.
14	0x0 RW/1C/V/P	**Completion Timeout Status (CTE):** For Switch Ports, this bit is set if the Switch Port issues Non-Posted Requests on its own behalf (vs. only forwarding such as Requests generated by other devices).
13	0x0 RW/1C/V/P	**Flow Control Protocol Error Status (FCE):** This bit is set when a flow control protocol error is detected.
12	0x0 RW/1C/V/P	**Poisoned TLP Received Status (PTLPE):** This bit is set and the bridge logs the header when a poisoned TLP is received from PCI Express.
11:6	0x0 RO	**RSVD1:** Reserved
5	0x0 RW/1C/V/P	**Surprise Down Error Status (SLDE):** This bit is set when a surprise down error is detected. This bit does not apply to the upstream port.
4	0x0 RW/1C/V/P	**Data Link Protocol Error Status (DLPE):** This bit is set when a data link protocol error is detected.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**RSVD2:** Reserved

48.2.77 ERRUNCMSK—Offset 108h

This register controls the reporting of individual uncorrectable errors by device to the host bridge via a PCI Express error message. This register also controls the logging of the header. Refer to the PCI Express specifications for details of how the mask bits function. A masked error (respective bit set in the mask register) is not reported to the host bridge by the switch, nor is the header logged (status bits unaffected by the mask bit). There is a mask bit per bit of the Uncorrectable Error Status Register. The attr. of AER Error Mask bits in VRSP will be changed to be compliant with PCIe Spec.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 108h

Default: 04400000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**RSVD0:** Reserved
26	0x1 RW/P	**Poisoned TLP Egress Blocked Mask (PTLPEBM):** Reserved.
25	0x0 RO	**TLP Prefix Blocked Error Mask (TPBES):** Reserved.
24	0x0 RW/P	**AtomicOp Egress Blocked Mask (AEBEM):** Reserved.
23	0x0 RW/P	**MC Blocked TLP Mask (MCEM):** Reserved.
22	0x1 RW/P	**Uncorrectable Internal Error Mask (UIEM):** Reserved.
21	0x0 RW/P	**ACS Violation Mask (ACSEM):** Reserved.
20	0x0 RW/P	**Unsupported Request Error Mask (UREM):** Reserved.
19	0x0 RW/P	**ECRC Error Mask (ECRCEM):** Reserved.
18	0x0 RW/P	**Malformed TLP Mask (MTLPEM):** Reserved.
17	0x0 RW/P	**Receiver Overflow Mask (ROEM):** Reserved.
16	0x0 RW/P	**Unexpected Completion Mask (UCEM):** Reserved.
15	0x0 RW/P	**Completer Abort Mask (CAEM):** Reserved.
14	0x0 RW/P	**Completion Timeout Mask (CTEM):** Reserved.
13	0x0 RW/P	**Flow Control Protocol Error Mask (FCEM):** Reserved.
12	0x0 RW/P	**Poisoned TLP Received Mask (PTLPEM):** Reserved.
11:6	0x0 RO	**RSVD1:** Reserved
5	0x0 RW/P	**Surprise Down Error Mask (SLDEM):** This bit does not apply to the upstream port or End point

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW/P	**Data Link Protocol Error Mask (DLPEM):** Reserved.
3:0	0x0 RO	**RSVD2:** Reserved

48.2.78 ERRUNCSEV—Offset 10Ch

This register controls whether an individual uncorrectable error is reported as a fatal error. An uncorrectable error is reported as fatal when the corresponding error bit in this register is set. When the bit is cleared, the corresponding error is considered non-fatal. The attr. of AER Error Severity bits in VRSP will be changed to be compliant with PCIe Spec.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 10Ch

Default: 00462030h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**RSVD0:** Reserved
26	0x0 RW/P	**Poisoned TLP Egress Blocked Severity (PTLPEBS):** Reserved.
25	0x0 RO	**TLP Prefix Blocked Error Severity (TPBES):** Reserved.
24	0x0 RW/P	**AtomicOp Egress Blocked Severity (AEBES):** Reserved.
23	0x0 RW/P	**MC Blocked TLP Severity (MCES):** Reserved.
22	0x1 RW/P	**Uncorrectable Internal Error Severity (UIES):** Reserved.
21	0x0 RW/P	**ACS Violation Severity (ACSES):** Reserved.
20	0x0 RW/P	**Unsupported Request Error Severity (URES):** Reserved.
19	0x0 RW/P	**ECRC Error Severity (ECRCES):** Reserved.
18	0x1 RW/P	**Malformed TLP Severity (MTLPES):** Reserved.
17	0x1 RW/P	**Receiver Overflow Error Severity (ROES):** Reserved.
16	0x0 RW/P	**Unexpected Completion Error Severity (UCES):** Reserved.
15	0x0 RW/P	**Completer Abort Error Severity (CAES):** Reserved.
14	0x0 RW/P	**Completion Timeout Error Severity (CTES):** Reserved.
13	0x1 RW/P	**Flow Control Protocol Error Severity (FCES):** Reserved.
12	0x0 RW/P	**Poisoned TLP Received Severity (PTLPES):** Reserved.
11:6	0x0 RO	**RSVD1:** Reserved
5	0x1 RW/P	**Surprise Down Error Severity (SLDES):** This bit does not apply to the upstream port or end point
4	0x1 RW/P	**Data Link Protocol Error Severity (DLPES):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**RSVD2:** Reserved

48.2.79 ERRCORSTS—Offset 110h

This register reports the error status of individual correctable error sources on a PCI Express device. An individual error status bit set to 1 indicates that a particular error has occurred. Software can clear the error status by writing a 1 to the respective bit.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 110h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C/V/P	**Header Log Overflow Error (HLOE):** Reserved.
14	0x0 RW/1C/V/P	**Correctable Internal Error (CIE):** Reserved.
13	0x0 RW/1C/V/P	**Advisory Non-Fatal Error (ANFE):** Reserved.
12	0x0 RW/1C/V/P	**Replay Timer Timeout Error (RTTE):** The PCIe sets this bit when replay timer time-out occurs.
11:9	0x0 RO	**RSVD1:** Reserved
8	0x0 RW/1C/V/P	**Replay Number Rollover Error (RNRE):** The PCIe sets this bit when the replay number rolls over from 11 to 00.
7	0x0 RW/1C/V/P	**Bad DLLP Error (BDLLPE):** The switch sets this bit on CRC errors on DLLP.
6	0x0 RW/1C/V/P	**Bad TLP Error (BTLPE):** The switch sets this bit on CRC errors on TLP.
5:1	0x0 RO	**RSVD2:** Reserved
0	0x0 RW/1C/V/P	**Receiver Error (RE):** The PCIe sets this bit when the physical layer detects a receiver error.

48.2.80 ERRCORMSK—Offset 114h

This register controls the reporting of individual correctable errors via ERR_COR message. A masked error (respective bit set in mask register) is not reported to the host bridge by the switch. There is a mask bit corresponding to every bit in the Correctable Error Status Register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 114h

Default: 0000E000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x1 RW/P	**Header Log Overflow Error Mask (HLOEM):** Reserved.
14	0x1 RW/P	**Correctable Internal Error Mask (CIEM):** Reserved.
13	0x1 RW/P	**Advisory Non-Fatal Error Mask (ANFEM):** Reserved.
12	0x0 RW/P	**Replay Timer Timeout Error Mask (RTTEM):** Reserved.
11:9	0x0 RO	**RSVD1:** Reserved
8	0x0 RW/P	**Replay Number Rollover Error Mask (RNREM):** Reserved.
7	0x0 RW/P	**Bad DLLP Error Mask (BDLLPEM):** Reserved.
6	0x0 RW/P	**Bad TLP Error Mask (BTLPEM):** Reserved.
5:1	0x0 RO	**RSVD2:** Reserved
0	0x0 RW/P	**Receiver Error Mask (REM):** Reserved.

48.2.81 AERCAPCTL—Offset 118h

This register gives the status and control for ECRC checks and also the pointer to the first uncorrectable error that happened.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 118h

Default: 00001000h

Bit Range	Default & Access	Field Name (ID): Description
31:13	0x0 RO	**RSVD0:** Reserved
12	0x1 RW/L	**Completion Timeout Prefix/Header Log Capable (CTPHLC):** If Set, this bit indicates that the Function records the prefix/header of Request TLPs that experience a Completion Timeout error. **Power Well:** PRST
11	0x0 RO/V/P	**TLP Prefix Log Present (TLPPLP):** If Set and the First Error Pointer is valid, indicates that the TLP Prefix Log register contains valid information. If Clear or if First Error Pointer is invalid, the TLP Prefix Log register is undefined.
10	0x0 RO	**Multiple Header Recording Enable (MHRE):** When set, this bit enables the function to record more than one error header.
9	0x0 RO	**Multiple Header Recording Capable (MHRC):** Supports more than one error header.
8	0x0 RW/P	**ECRC Check Enable (ECE):** When Set, ECRC checking is enabled. Functions that do not implement the associated mechanism are permitted to hardwire this bit to 0b.
7	0x0 RW/L	**ECRC Check Capable (ECC):** If Set, this bit indicates that the Function is capable of checking ECRC. **Power Well:** PRST
6	0x0 RW/P	**ECRC Generation Enable (EGE):** When Set, ECRC generation is enabled. Functions that do not implement the associated mechanism are permitted to hardwire this bit to 0b. Default value of this bit is 0b.
5	0x0 RW/L	**ECRC Generation Capable (EGC):** If Set, this bit indicates that the Function is capable of generating ECRC. **Power Well:** PRST
4:0	0x0 RO/V/P	**First Error Pointer (FEP):** This field identifies the bit position of the first error reported in the Uncorrectable Error Status Register (xref). This register re-arms itself (which does not change its current value) as soon as the error status bit indicated by the pointer is cleared by the software by writing a 1 to that status bit.

48.2.82 AERHDRLOG1—Offset 11Ch

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 11Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

48.2.83 AERHDRLOG2—Offset 120h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

48.2.84 AERHDRLOG3—Offset 124h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

48.2.85 AERHDRLOG4—Offset 128h

This register logs the 4 Dwords of the transaction header for PCI Express errors.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 128h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V/P	**TLP Header Log (TLPHDRLOG):** As soon as an error is logged in this register, it remains locked for further error-logging until the software clears the status bit that caused the header log (in other words, until the error pointer is re-armed for logging again).

48.2.86 ROOTERRCMD—Offset 12Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 12Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**Fatal Error Reporting Enable (FERE):** When set, this bit enables the generation of an interrupt when a Fatal error is reported by any of the functions in the hierarchy associated with this Root Port.
1	0x0 RW	**Non-Fatal Error Reporting Enable (NFERE):** When set, this bit enables the generation of an interrupt when a Non-Fatal error is reported by any of the functions in the hierarchy associated with this Root Port.
0	0x0 RW	**Correctable Error Reporting Enable (CERE):** When set, this bit enables the generation of an interrupt when a Correctable error is reported by any of the functions in the hierarchy associated with this Root Port.

48.2.87 ROOTERRSTS—Offset 130h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 130h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO/V	**Advanced Error Interrupt Message Number (AEMN):** This register indicates which MSI/MSI-X vector is used for the interrupt message generated in association with any of the status bits of this Capability. For MSI, the value in this register indicates the offset between the base Message Data and the interrupt message that is generated. Hardware is required to update this field so that it is correct if the number of MSI Messages assigned to the Function changes when software writes to the Multiple Message Enable field in the MSI Message Control register. For MSI-X, the value in this register indicates which MSI-X Table entry is used to generate the interrupt message. The entry must be one of the first 32 entries even if the Function implements more than 32 entries. For a given MSI-X implementation, the entry must remain constant. For remaining fields info, please refer to PCIe Spec. for more details.
26:7	0x0 RO	**RSVD0:** Reserved
6	0x0 RW/1C/V/P	**Fatal Error Message Received (FEMR):** Reserved.
5	0x0 RW/1C/V/P	**Non-Fatal Error message Received (NFEMR):** Reserved.
4	0x0 RW/1C/V/P	**First Uncorrectable Fatal (FUF):** Reserved.
3	0x0 RW/1C/V/P	**Multiple Error Fatal/Non-Fatal Received (MEFR):** Reserved.
2	0x0 RW/1C/V/P	**Error Fatal/Non-Fatal Received (EFR):** Reserved.
1	0x0 RW/1C/V/P	**Multiple Error Correctable Error Received (MCER):** Reserved.
0	0x0 RW/1C/V/P	**Correctable Error Received (CER):** Reserved.

48.2.88 ERRSRCID—Offset 134h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 134h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO/V/P	**Fatal/Non-Fatal Error Source ID (EFSID):** Requester ID of the source when an Fatal or No Fatal Error is received and the Fatal Error Message Received (FEMR) or Non-Fatal Error message Received (NFEMR) bit is not already set.
15:0	0x0 RO/V/P	**Correctable Error Source ID (ECSID):** Requester ID of the source when a correctable error is received and the Correctable Error Received (CER) bit is not already set.

48.2.89 ACSCAPHDR—Offset 138h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 138h

Default: 1501000Dh

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x150 RW/L	**Next Capability Offset (NCO):** Contains the offset of the next structure in the Extended Capabilities. Software will need to program this field appropriately for linked capabilities list if default is not supported. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (CV):** Indicates the version of the Capability structure present.
15:0	0xd RO	**Extended Capability ID (ECID):** Identifies the function as Access Control Services capable.

48.2.90 ACSCAP—Offset 13Ch

This register identifies the Access Control Services (ACS) capabilities.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 13Ch

Default: 005Fh

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Egress Control Vector Size (ECVS):** Indicates the number of bits in the Egress Control Vector. This is set to 00h as ACS P2P Egress Control (ACSP2PEC) bit 5 in this register is 0b.
7	0x0 RO	**RSVD0:** Reserved
6	0x1 RO	**ACS Direct Translated P2P (TACSDTP2P):** Indicates that the component does implement ACS Direct Translated P2P. Required for Root Ports that support Address Translation Services (ATS) and also support peer-to-peer traffic with other Root Ports, required for Switch Downstream Ports,
5	0x0 RO	**ACS P2P Egress Control (EACSP2PEC):** Hardwired to 0. Indicates that the component does not implement ACS P2P Egress Control.
4	0x1 RO	**ACS Upstream Forwarding (UACSUF):** Indicates that the component implements ACS Upstream Forwarding.
3	0x1 RO	**ACS P2P Completion Redirect (CACSP2PRR):** Indicates that the component implements ACS P2P Completion Redirect. This includes Read Completions, AtomicOp Completions, and other Completions, either with or without data.
2	0x1 RO	**ACS P2P Request Redirect (RACSP2PRR):** Indicates that the component implements ACS P2P Request Redirect.
1	0x1 RO	**ACS Translation Blocking (BACSTB):** Indicates that the component implements ACS Translation Blocking.
0	0x1 RO	**ACS Source Validation (VACSSV):** Indicates that the component implements ACS Source Validation.

48.2.91 ACSCTL—Offset 13Eh

This register identifies the Access Control Services (ACS) control bits.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 13Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:7	0x0 RO	**RSVD0:** Reserved
6	0x0 RW	**ACS Direct Translated P2P Enable (TACSP2PECE):** When Set, overrides the ACS P2P Request Redirect and ACS P2P Egress Control mechanisms with peer-to-peer Memory Requests whose Address Translation (AT) field indicates a Translated address. This bit is ignored if ACS Translation Blocking (B) is enabled.
5	0x0 RO	**ACS P2P Egress Control Enable (EACSP2PECE):** This is hardwired to 0b as the component does not implement ACS P2P Egress Control.
4	0x0 RW	**ACS Upstream Forwarding Enable (UACSUFE):** When set, the component forwards upstream any Request or Completion TLPs it receives that were redirected upstream by a component lower in the hierarchy. Note that the U bit only applies to upstream TLPs arriving at a Downstream Port, and whose normal routing targets the same Downstream Port.
3	0x0 RW	**ACS P2P Completion Redirect Enable (CACSP2PCRE):** Determines when the component redirects peer-to-peer Completions upstream, applicable only to Read Completions whose Relaxed Ordering Attribute is clear.
2	0x0 RW	**ACS P2P Request Redirect Enable (RACSP2PRRE):** This bit determines when the component redirects peer-to-peer Requests upstream.
1	0x0 RW	**ACS Translation Blocking Enable (BACSTBE):** When set, the component blocks all upstream Memory Requests whose Address Translation (AT) field is not set to the default value.
0	0x0 RW	**ACS Source Validation Enable (VACSSVE):** When set, the component validates the Bus Number from the Requester ID of upstream Requests against the secondary / subordinate Bus Numbers.

48.2.92 ERRUNCDETMSK—Offset 140h

A value of 1 masks the field and prevents detection as well as logging.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 140h

Default: 04000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**RSVD0:** Reserved
26	0x1 RW/P	**Poisoned TLP Egress Blocked Detect Mask (PTLPEBDM):** Reserved.
25	0x0 RO	**TLP Prefix Blocked Error Detect Mask (TPBEDM):** Reserved.
24	0x0 RW/P	**AtomicOp Egress Blocked Error Detect Mask (AEBEDM):** Reserved.
23	0x0 RW/P	**MC Blocked TLP Error Detect Mask (MCEDM):** Reserved.
22	0x0 RW/P	**Uncorrectable Internal Error Detect Mask (UIEDM):** Reserved.
21	0x0 RW/P	**ACS Violation Error Detect Mask (ACSEDM):** Reserved.
20	0x0 RW/P	**Unsupported Request Error Detect Mask (UREDM):** Reserved.
19	0x0 RW/P	**ECRC Check Error Mask (ECRCEDM):** Supported
18	0x0 RW/P	**Malformed TLP Error Detect Mask (MTLPEDM):** Reserved.
17	0x0 RW/P	**Receiver Overflow Error Detect Mask (ROEDM):** Reserved.
16	0x0 RW/P	**Unexpected Completion Error Detect Mask (UCEDM):** Reserved.
15	0x0 RW/P	**Completer Abort Error Detect Mask (CAEDM):** Reserved.
14	0x0 RW/P	**Completion Timeout Error Detect Mask (CTEDM):** Reserved.
13	0x0 RW/P	**Flow Control Error Detect Mask (FCEDM):** Reserved.
12	0x0 RW/P	**Poisoned TLP Error Detect Mask (PTLPEDM):** Reserved.
11:6	0x0 RO	**RSVD1:** Reserved
5	0x0 RW/P	**Surprise Down Error Detect Mask (SLDEDM):** Reserved.
4	0x0 RW/P	**Data Link Protocol Error Detect Mask (DLPEDM):** Reserved.
3:0	0x0 RO	**RSVD2:** Reserved

48.2.93 ERRCORDETMSK—Offset 144h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 144h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/P	**Header Log Overflow Error Detect Mask (HLOEDM):** Reserved.
14	0x0 RW/P	**Correctable Internal Error Detect Mask (CIEDM):** Reserved.
13	0x0 RW/P	**Advisory Non-Fatal Error Detect Mask (ANFEDM):** Reserved.
12	0x0 RW/P	**Replay Timer Timeout Error Detect Mask (RTTEDM):** Reserved.
11:9	0x0 RO	**RSVD1:** Reserved
8	0x0 RW/P	**Replay Number Rollover Error Detect Mask (RNREDM):** Reserved.
7	0x0 RW/P	**Bad DLLP Error Detect Mask (BDLLPEDM):** Reserved.
6	0x0 RW/P	**Bad TLP Error Detect Mask (BTLPEDM):** Reserved.
5:1	0x0 RO	**RSVD2:** Reserved
0	0x0 RW/P	**Receiver Error Detect Mask (REDM):** Reserved.

48.2.94 ROOTERRDETMSK—Offset 148h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 148h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW/P	**Received Fatal Message Detect Mask (RFMDM):** Reserved.
1	0x0 RW/P	**Received Non-Fatal Message Detect Mask (RNFMDM):** Reserved.
0	0x0 RW/P	**Received Correctable Message Detect Mask (RCEMDM):** Reserved.

48.2.95 MCSTCAPHDR—Offset 150h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 150h

Default: 18010012h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x180 RW/L	**Next Capability Offset (NCO):** Contains the offset of the next structure in the Extended Capabilities. Software will need to program this field appropriately for linked capabilities list if default is not supported. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (CV):** Indicates the version of the Capability structure present.
15:0	0x12 RO	**Extended Capability ID (ECID):** Identifies the function as Multicast Capability.

48.2.96 MCSTCAP—Offset 154h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 154h

Default: 000Fh

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**MC ECRC Regeneration supported (MCERS):** 1: When set, this bit indicates that ECRC regeneration is supported.
14:6	0x0 RO	**RSVD0:** Reserved
5:0	0xf RO	**MC Max Group (MCMG):** This field indicates the maximum number of Multicast Groups that the component supports, encoded as M-1. A value of 00h indicates that one multicast Group is supported.

48.2.97 MCSTCTL—Offset 156h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 156h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**MC Enable (MCEN):** When set, this bit indicates the Multicast Capability is enabled for the component. This is a global field that controls MC for the specific function.
14:6	0x0 RO	**RSVD0:** Reserved
5:0	0x0 RW	**MC Number Group (MCNG):** This field indicates the number of Multicast Groups configured for use, encoded as N-1. A value of 00h indicates that one Multicast Group is configured for use. Behavior is undefined if value exceeds MC Max Group. This parameter indirectly defines the upper limit of the Multicast address range. This field is ignored if MC Enable is Clear.

48.2.98 MCSTBAR—Offset 158h

The MC_Base_Address register contains the MC_Base_Address and the MC_Index_Position for calculating whether a MC hit occurred or not. Refer to the PCI Local Bus Specification, Revision 3.0 for details on how the MC hit/miss and the MC group number is calculated. This register is 4K aligned and hence only the top 20 bits are useable for the base address.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 158h

Default: 0000000Ch

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Lower Address 32-bit (L32ADR):** Reserved.
11:6	0x0 RO	**RSVD0:** Reserved
5:0	0xc RW	**MC Index Position (MCIP):** This field indicates the location of the LSB of the Multicast Group number within the address. Behavior is undefined if this field is less than 12 when MC Enable is set.

48.2.99 MCSTUBAR—Offset 15Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 15Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address 32-bit (U32ADR):** Reserved.

48.2.100 MCSTRCV—Offset 160h

The MC_Receive register provides a bit vector denoting which Multicast groups the Function should accept

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 160h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW	**MC Receive (MCR):** For each bit that is set, this function gets a copy of any Multicast TLPs for the associated Multicast Group. Bits above MC Number Groups are ignored by hardware.

48.2.101 MCSTBLKALL—Offset 168h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 168h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW	**MC Block All (MCBA):** For each bit that is set, this function is blocked from sending TLPs to the associated Multicast Group. Bits above MC Number Groups are ignored by hardware.

48.2.102 MCSTOLBAR—Offset 178h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 178h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**MC Overlay BAR (MCOVRBAR):** Specifies the base address of the window onto which MC TLPs passing through this function will be overlaid. The overlay BAR is 4K aligned. Default is 0.
11:6	0x0 RO	**RSVD0:** Reserved
5:0	0x0 RW	**MC Overlay Size (MCOVRSZ):** If 6 or greater, specifies the size in bytes of the overlay aperture as a power of 2. If less than 6, disables the overlay mechanism. Default is 0.

48.2.103 MCSTUOLBAR—Offset 17Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 17Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**MC Overlay BAR Upper 32 (MCOVRBARU32):** Specifies the base address of the window onto which MC TLPs passing through this function will be overlaid.

48.2.104 EINJCAPHDR—Offset 180h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 180h

Default: 1901000Bh

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x190 RW/L	**Next Capability Offset (NCO):** Contains the offset of the next structure in the Extended Capabilities. Software will need to program this field appropriately for linked capabilities list if default is not supported. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (CV):** Indicates the version of the Capability structure present.
15:0	0xb RO	**Extended Capability ID (ECID):** Vendor Defined Capability

48.2.105 EINJHDR—Offset 184h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 184h

Default: 00A00003h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0xa RO	**VSEC Length (VSECLEN):** This field indicates the number of bytes in the entire VSEC structure, including the PCI Express Extended Capability header, the Vendor-Specific header, and the Vendor-Specific registers.
19:16	0x0 RO	**VSEC Rev (VSECREV):** This field is a vendor-defined version number that indicates the version of the VSEC structure. Software must qualify the Vendor ID and VSEC ID before interpreting this field.
15:0	0x3 RO	**VSEC ID (VSECID):** This field is a vendor-defined ID number that indicates the nature and format of the VSEC structure. Software must qualify the Vendor ID before interpreting this field. 3h is assigned to WHEA Error Injection.

48.2.106 EINJCTL—Offset 188h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 188h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**Inject Completion Timeout Error (INJCTOERR):** When this bit is written from 0 to 1, one and only one error assertion pulse is produced on the error source signal for the given port. This error will appear equivalent to an actual error assertion because this event is OR'd into the existing error reporting structure. To log another error, this bit must be cleared first, before setting again. Leaving this bit in a 1 state does not produce a persistent error condition.
1	0x0 RW	**Inject Receiver Error (INJRCVERR):** When this bit is written from 0 to 1, one and only one error assertion pulse is produced on the error source signal for the given port. This error will appear equivalent to an actual error assertion because this event is OR'd into the existing error reporting structure. To log another error, this bit must be cleared first, before setting again. Leaving this bit in a 1 state does not produce a persistent error condition.
0	0x0 RW/L	**Error Injection Disable (EINJDIS):** This bit disables the usage of the PCIe Error Injection bits for EINJCTL.INJRCVERR, INJCTOERR This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit. **Power Well:** PRST

48.2.107 SECEXPCAP—Offset 200h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 200h

Default: 00010019h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW/L	**Next Capability Offset (NCO):** Contains the offset of the next structure in the Extended Capabilities list. Set to Null. Software will need to program this field appropriately for linked capabilities list if default is not supported. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (CV):** Indicates the version of the Capability structure present.
15:0	0x19 RO	**Extended Capability ID (ECID):** PCI Express Extended Capability ID for the Secondary PCI Express Extended Capability is 0019h

48.2.108 LINKCTL3—Offset 204h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 204h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:9	0x0 RW	**Enable Lower SKP OS Generation Vector (ELSKPOSGV):** When the Link is in L0 and the bit in this field corresponding to the current Link speed is Set, SKP Ordered Sets are scheduled at the rate defined for SRNS, overriding the rate required based on the clock tolerance architecture. See section 4.2.7 for additional requirements. Bit definitions within this field are: Bit 0 2.5 GT/s Bit 1 5.0 GT/s Bit 2 8.0 GT/s Bits 6:3 RsvdP Bits in this field are RW if the corresponding bit in the Lower SKP OS Generation Supported Speeds Vector is Set, otherwise they are permitted to be hardwired to 0. Behavior is undefined if a bit is Set in this field and the corresponding bit in the Lower SKP OS Generation Supported Speeds Vector is not Set. The default value of this field is 000 0000b.
8:2	0x0 RO	**RSVD1:** Reserved
1	0x0 RW	**Link Equalization Request Interrupt Enable (LNKEQREQINTEN):** When Set, this bit enables the generation of interrupt to indicate that the Link Equalization Request bit has been set. This bit is not applicable and is reserved for Endpoints, PCI Express to PCI/PCIX bridges, and Upstream Ports of Switches.
0	0x0 RW/V	**Perform Equalization (PE):** When this register is 1b and a 1b is written to the 'Link Retrain' register with 'Target Link Speed' set to 8 GT/s, the Downstream Port must perform Transmitter Equalization. Software must guarantee that no transactions are pending in the link while the link is in Recovery when this bit is set to 1b. This bit is not applicable and is reserved for Endpoints, PCI Express to PCI/PCIX bridges, and Upstream Ports of Switches.

48.2.109 LANEERRSTS—Offset 208h

The Equalization Control Register consist of control fields required for per lane equalization and the number of entries in this register are sized by Max Link Width

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 208h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7	0x0 RW/1C/V/P	**Lane 7 Error (L7ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
6	0x0 RW/1C/V/P	**Lane 6 Error (L6ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
5	0x0 RW/1C/V/P	**Lane 5 Error (L5ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
4	0x0 RW/1C/V/P	**Lane 4 Error (L4ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
3	0x0 RW/1C/V/P	**Lane 3 Error (L3ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
2	0x0 RW/1C/V/P	**Lane 2 Error (L2ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
1	0x0 RW/1C/V/P	**Lane 1 Error (L1ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.
0	0x0 RW/1C/V/P	**Lane 0 Error (L0ERR):** A value of 1b indicates that a lane based error was detected on the corresponding PCI Express Lane Number.

48.2.110 LANEEQCTL0—Offset 20Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 20Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB 001b: -7 dB • 010b: -8 dB 011b: -9 dB • 100b: -10 dB 101b: -11 dB • 110b: -12 dB 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of • 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.111 LANEEQCTL1—Offset 20Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 20Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.112 LANEEQCTL2—Offset 210h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 210h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.113 LANEEQCTL3—Offset 212h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 212h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.114 LANEEQCTL4—Offset 214h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 214h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.115 LANEEQCTL5—Offset 216h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 216h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.116 LANEEQCTL6—Offset 218h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 218h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.117 LANEEQCTL7—Offset 21Ah

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 21Ah

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW/L	**Upstream Port Receiver Preset Hint (UPRPH):** Preset Hint for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
11:8	0x0 RW/L	**Upstream Port Transmitter Preset (UPTP):** Transmitter Preset for Upstream Port with the following encoding. The Downstream Port must pass on this value in the EQ TS2's. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 dB for de-emphasis, 3.5 dB for preshoot • 1001b: 0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. For a Upstream Port, this field reflects the latest Receiver Preset value requested from the Downstream Port for corresponding Lane. **Power Well:** PRST
7	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
6:4	0x0 RW/L	**Downstream Port Receiver Preset Hint (DPRPH):** Receiver Preset Hint for Downstream Port. The Downstream Port may use this hint for receiver equalization. • 000b: -6 dB • 001b: -7 dB • 010b: -8 dB • 011b: -9 dB • 100b: -10 dB • 101b: -11 dB • 110b: -12 dB • 111b: Reserved This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST
3:0	0x0 RW/L	**Downstream Port Transmitter Preset (DPTP):** Transmitter Preset for an Downstream Port, with the following encoding. • 0000b: -6 dB for de-emphasis, 0 dB for preshoot • 0001b: -3.5 dB for de-emphasis, 0 dB for preshoot • 0010b: -4.5 dB for de-emphasis, 0 dB for preshoot • 0011b: -2.5 dB for de-emphasis, 0 dB for preshoot • 0100b: 0 dB for de-emphasis, 0 dB for preshoot • 0101b: 0 dB for de-emphasis, 2 dB for preshoot • 0110b: 0 dB for de-emphasis, 2.5 dB for preshoot • 0111b: -6 dB for de-emphasis, 3.5 dB for preshoot • 1000b: -3.5 db for de-emphasis, 3.5 dB for preshoot • 1001b:0 dB for de-emphasis, 3.5 dB for preshoot • 1010b: The Transmitter Preset encoding of 1010b corresponds to the maximum Vtx-boost that the Transmitter advertises with FS and LF in both full swing and reduced swing modes with C-1 = 0 and C+1 = FS - (2*LF). • All other encodings are reserved. This field is not applicable and reserved for Endpoints, PCI Express to PCI/PCI-X bridges, and Upstream Ports of Switches. **Power Well:** PRST

48.2.118 XPPMDL0—Offset 280h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 280h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**PM data counter low value (CNTL):** Low order bits [31:0] for PM data counter[1:0].

48.2.119 XPPMDL1—Offset 284h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 284h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**PM data counter low value (CNTL):** Low order bits [31:0] for PM data counter[1:0].

48.2.120 XPPMCL0—Offset 288h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 288h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RW/V	**PM compare low value (CMPL):** Low order bits [31:0] for PM compare register[1:0].

48.2.121 XPPMCL1—Offset 28Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 28Ch

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RW/V	**PM compare low value (CMPL):** Low order bits [31:0] for PM compare register[1:0].

48.2.122 XPPMDH—Offset 290h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 290h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RW/V	**High Nibble PEX Counter1 value (CNTH1):** High order bits [35:32] of the 36-bit PM Data1 register.
7:4	0x0 RO	**RSVD1:** Reserved
3:0	0x0 RW/V	**High Nibble PEX Counter0 value (CNTH0):** High order bits [35:32] of the 36-bit PM Data0 register.

48.2.123 XPPMCH—Offset 292h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 292h

Default: 0F0Fh

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11:8	0xf RW/V	**High Nibble PEX Compare1 value (CMPH1):** High order bits [35:32] of the 36-bit PM Compare1 register.
7:4	0x0 RO	**RSVD1:** Reserved
3:0	0xf RW/V	**High Nibble PEX Compare0 value (CMPH0):** High order bits [35:32] of the 36-bit PM Compare0 register.

48.2.124 XPPMR0—Offset 294h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 294h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Local/Global Event Select (LOCGLOBEVSEL):** This register bit allows for standalone cluster simulation. Normally the global events are used as control signals for the performance monitors. When this bit is set to1, the internal IPTRIG[0-3] signals are selected respectively in place of the external GE[0-3] signals. ***Note:*** It is possible to have one PERFMON use the internal events, while the other PERFMON uses the external events. • 0:Global events are selected • 1:Local events are selected
30	0x0 RW	**Not greater than comparison (NOTGRTCMP):** • 0: PMC will compare a greater than function. When clear the perfmon status will assert when the PMD is greater than the PMC. • 1: PMC will compare with NOT (greater than) function. When set the perfmon status will assert when the PMD is less than or equal to the PMC. CSPEC NOTE: This bit was not in Seaburg.
29	0x0 RW	**Force PMD counter to add zero to input (FRCPMDADDZ):** This feature is used with the queue measurement bus. When this bit is set the value on the queue measurement bus is added to zero so the result in PMD will always reflect the value from the queue measurement bus. • 0: Do not add zero. Normal PerfMon operation. • 1: Add zero with input queue bus.
28	0x0 RW	**Latched Count Enable Select (LATCNTENSEL):** • 0: Normal PM operation. Use CENS as count enable. • 1: Use Latched count enable from queue empty events
27	0x0 RW	**Reset Pulse Enable (RSTPULSEN):** Setting this bit will select a pulsed version of the reset signal source in the reset block. • 0: Normal reset signaling • 1: Select a pulsed reset from the reset signal sources.
26:24	0x0 RO	**RSVD0:** Reserved
23:22	0x0 RW	**DFX Byte Lane Selection for PerfMon (DFXLNSEL):** This bit field is only active when LDES is asserted. These bits select which set of 3 byte lanes from the 72 bit (9 byte lane) local debug bus is active for DFx event counting with the PerfMons. • 00: Local Debug Byte Lanes 0-2 • 01: Local Debug Byte Lanes 3-5 • 10: Local Debug Byte Lanes 6-8 • 11: Reserved
21	0x0 RW	**Local DFT Event Select (LDES):** This selection enables the local debug bus to be selected for event counting. Enabling this selection changes the PMEVL,H register into 24bits of DFx masking and matching. • 0: Disable DFx event monitoring • 1: Enable DFx event monitoring.
20:19	0x0 RW	**Event Group Selection (EGS):** Selects which event register to use for performance monitoring. • 00: Bus events (XPPMEVL,H register) • 01: Resource utilizations (in the XPPMER register) • 10: Queue measurement (in the XPPMER register) • 11: FIFO queue measurements (selects 1h on the queue measurement bus).

Bit Range	Default & Access	Field Name (ID): Description
18:17	0x0 RW	**Count Event Select (CNTEVSEL):** Selects the condition for incrementing the performance monitor counter. • 00: Event source selected by PMEVL,H • 01: Partner event status (max compare or overflow) • 10: All clocks when enabled • 11: Reserved
16	0x0 RW	**Event Polarity Invert (EVPOLINV):** This bit inverts the polarity of the conditioned event signal. • 0: No inversion • 1: Invert the polarity of the conditioned event signal
15:14	0x0 RW	**Count Mode (CNTMD):** This field sets how the events will be counted. • 00: Count clocks for the duration of event signal is active. • 01: Count rising edge events (for active low signals EVPOLINV must be set for correct measurements). • 10: Count clocks continuously after the event was asserted. The latched state of this condition is cleared by PerfMon reset block, PMR.CNTRST bit, or XPPERFCON.GRST. • 11: Enable queue threshold measuring. This mode will reassign the event selection registers from both PerfMons, selects a modified count enable, and enables add/sub operation. Selecting this mode will not allow normal PerfMon operations to occur. To simplify the logic a strict assignment of functions is applied. PM0's event selection registers are assigned to the add (increment) function and PM1's event selection registers are assigned to the subtract (decrement) function. When both PM0 and PM1 events are asserted or when both are not asserted do not add or subtract values from the queue. PM0Ev.....PM1Ev.....PM condition ....0.....0.....Do not add/sub ....1.....0.....Add queue value ....0.....1.....Sub queue value ....1.....1.....Do not add/sub Setting this mode enables the PM event registers as described but it also enables the selection of a empty signal to be used a count enable signal. The count enable is latched high continuously and only cleared with PM global reset or local counter reset. The THRQMSRSTR bit field selects which bit[3] of each nibble in each byte lane that acts as a count enable. Once this event occurs it is latched and queue counting begins. Because this signal is latched a counter reset or PERCON global reset is required to start another measurement. This latched condition is cleared by the PMR.CNTRST bit, or XPPERFCON.GRST.
13:11	0x0 RW	**Counter enable source (CENS):** These bits identify which input enables the counter. Default value disables counting. • 000: Disabled • 001: Local Count Enabled (LCEN). This bit is always a logic 1. • 010: Partner counter's event status (max compare or overflow) • 011: Header MatchOut signal • 100: GE[0], from the Global Debug Event Block • 101: GE[1], from the Global Debug Event Block • 110: GE[2], from the Global Debug Event Block • 111: GE[3], from the Global Debug Event Block ***Note:*** Address/Header MatchOut signal must align with PMEVL,H events for this to be effective. ***Note:*** The GEs used are dependent on bit 31 (LOCGLOBEVSEL). If bit 31 is used, local events will be used instead of global events.

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Reset Event Select (RSTEVSEL):** This bit field will reset the PMD counter. For details regarding usage and pair mode operation see Chapter 21. • 000: No reset condition • 001: Partner's event status: When the partner counter causes an event status condition to be activated, either by a counter overflow or max comparison, then this counter will reset and continue counting. • 010: Partners PME register event: When the partner counter detects a match condition which meets its selected PME register qualifications, then this counter will reset and continue counting. • 011: This PM counter's status output. • 100: GE[0], from the Global Debug Event Block. • 101: GE[1], from the Global Debug Event Block. • 110: GE[2], from the Global Debug Event Block. • 111: GE[3], from the Global Debug Event Block. ***Note:*** The GEs used are dependent on bit 31 (LOCGLOBEVSEL). If bit 31 is used, local events will be used instead of global events.
7:6	0x0 RW	**Compare Mode (CMPMD):** This field defines how the PMC (compare) register is to be used. • 00: compare mode disabled (PMC register not used) sig p = sig s • 01: max compare only: The PMC register value is compared with the counter value. If the counter value is greater then the Compare Status (CMPSTAT) will be set. sig p = sig n • 10: max compare with update of PMC at end of sample: The PMC register value is compared with the counter value, and if the counter value is greater, the PMC register is updated with the counter value. Note: The Compare Status field is not affected in this mode. sig p = sig n • 11: Reserved
5	0x0 RW	**PM Status Signal Output (PMSSIG):** • 0: Level output from status/overflow signals. • 1: Pulsed output from status/overflow signals.
4:3	0x0 RW	**PerfMon Trigger Output (PTO):** This field selects what the signal is communicated to the chip's event logic structure. • 00: No cluster trigger output from PerfMons or header match. • 01: PM Status. • 10: PM Event Detection. • 11: Address Header Match
2	0x0 RW/1C/V	**Compare Status (CMPSTAT):** This status bit captures a count compare event. • 0: no event • 1: count compare - PMD counter greater than PMC register when in compare mode. This bit remains set once an event is reported even though the original condition is no longer valid. Writing a logic '1' clears the bit.
1	0x0 RW/1C/V	**Overflow Status Bit (OVS):** This status bit captures the overflow event from the PMD counter. This bit remains set once an event is reported even though the original condition is no longer valid. Writing a logic '1' clears the bit.
0	0x0 RW	**Counter Reset (CNTRST):** Setting this bit resets the following bit fields. This only applies to the set of registers for this PM block. Setting this bit resets the PMD counter, the associated adder storage register and the count mode state latch (see bits CNTMD) to the default state. It does not change the state of this PMR register, the event selections, or the value in the compare register. Note: This bit must be cleared by software, otherwise the counters remain in reset. There is also a reset bit in the XPPERFCON register which clears all PM registers including the PMR.

48.2.125 XPPMR1—Offset 298h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 298h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Local/Global Event Select (LOCGLOBEVSEL):** This register bit allows for standalone cluster simulation. Normally the global events are used as control signals for the performance monitors. When this bit is set to1, the internal IPTRIG[0-3] signals are selected respectively in place of the external GE[0-3] signals. ***Note:*** It is possible to have one PERFMON use the internal events, while the other PERFMON uses the external events. • 0:Global events are selected • 1:Local events are selected
30	0x0 RW	**Not greater than comparison (NOTGRTCMP):** • 0: PMC will compare a greater than function. When clear the perfmon status will assert when the PMD is greater than the PMC. • 1: PMC will compare with NOT(greater than) function. When set the perfmon status will assert when the PMD is less than or equal to the PMC. CSPEC NOTE: This bit was not in Seaburg.
29	0x0 RW	**Force PMD counter to add zero to input (FRCPMDADDZ):** This feature is used with the queue measurement bus. When this bit is set the value on the queue measurement bus is added to zero so the result in PMD will always reflect the value from the queue measurement bus. • 0: Do not add zero. Normal PerfMon operation. • 1: Add zero with input queue bus.
28	0x0 RW	**Latched Count Enable Select (LATCNTENSEL):** • 0: Normal PM operation. Use CENS as count enable. • 1: Use Latched count enable from queue empty events
27	0x0 RW	**Reset Pulse Enable (RSTPULSEN):** Setting this bit will select a pulsed version of the reset signal source in the reset block. • 0: Normal reset signaling • 1: Select a pulsed reset from the reset signal sources.
26:24	0x0 RO	**RSVD0:** Reserved
23:22	0x0 RW	**DFX Byte Lane Selection for PerfMon (DFXLNSEL):** This bit field is only active when LDES is asserted. These bits select which set of 3 byte lanes from the 72 bit (9 byte lane) local debug bus is active for DFx event counting with the PerfMons. • 00: Local Debug Byte Lanes 0-2 • 01: Local Debug Byte Lanes 3-5 • 10: Local Debug Byte Lanes 6-8 • 11: Reserved
21	0x0 RW	**Local DFT Event Select (LDES):** This selection enables the local debug bus to be selected for event counting. Enabling this selection changes the PMEVL,H register into 24bits of DFx masking and matching. • 0: Disable DFx event monitoring • 1: Enable DFx event monitoring.
20:19	0x0 RW	**Event Group Selection (EGS):** Selects which event register to use for performance monitoring. • 00: Bus events (XPPMEVL,H register) • 01: Resource utilizations (in the XPPMER register) • 10: Queue measurement (in the XPPMER register) • 11: FIFO queue measurements (selects 1h on the queue measurement bus).

Bit Range	Default & Access	Field Name (ID): Description
18:17	0x0 RW	**Count Event Select (CNTEVSEL):** Selects the condition for incrementing the performance monitor counter. • 00: Event source selected by PMEVL,H • 01: Partner event status (max compare or overflow) • 10: All clocks when enabled • 11: Reserved
16	0x0 RW	**Event Polarity Invert (EVPOLINV):** This bit inverts the polarity of the conditioned event signal. • 0: No inversion • 1: Invert the polarity of the conditioned event signal
15:14	0x0 RW	**Count Mode (CNTMD):** This field sets how the events will be counted. • 00: Count clocks for the duration of event signal is active. • 01: Count rising edge events (for active low signals EVPOLINV must be set for correct measurements). • 10: Count clocks continuously after the event was asserted. The latched state of this condition is cleared by PerfMon reset block, PMR.CNTRST bit, or XPPERFCON.GRST. • 11: Enable queue threshold measuring. This mode will reassign the event selection registers from both PerfMons, selects a modified count enable, and enables add/sub operation. Selecting this mode will not allow normal PerfMon operations to occur. To simplify the logic a strict assignment of functions is applied. PM0's event selection registers are assigned to the add (increment) function and PM1's event selection registers are assigned to the subtract (decrement) function. When both PM0 and PM1 events are asserted or when both are not asserted do not add or subtract values from the queue. PM0Ev.....PM1Ev.....PM condition ....0.....0.....Do not add/sub ....1.....0.....Add queue value ....0.....1.....Sub queue value ....1.....1.....Do not add/sub Setting this mode enables the PM event registers as described but it also enables the selection of a empty signal to be used a count enable signal. The count enable is latched high continuously and only cleared with PM global reset or local counter reset. The THRQMSRSTR bit field selects which bit[3] of each nibble in each byte lane that acts as a count enable. Once this event occurs it is latched and queue counting begins. Because this signal is latched a counter reset or PERCON global reset is required to start another measurement. This latched condition is cleared by the PMR.CNTRST bit, or XPPERFCON.GRST.
13:11	0x0 RW	**Counter enable source (CENS):** These bits identify which input enables the counter. Default value disables counting. • 000: Disabled • 001: Local Count Enabled (LCEN). This bit is always a logic 1. • 010: Partner counter's event status (max compare or overflow) • 011: Header MatchOut signal • 100: GE[0], from the Global Debug Event Block • 101: GE[1], from the Global Debug Event Block • 110: GE[2], from the Global Debug Event Block • 111: GE[3], from the Global Debug Event Block ***Note:*** Address/Header MatchOut signal must align with PMEVL,H events for this to be effective. ***Note:*** The GEs used are dependent on bit 31 (LOCGLOBEVSEL). If bit 31 is used, local events will be used instead of global events.

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Reset Event Select (RSTEVSEL):** This bit field will reset the PMD counter. For details regarding usage and pair mode operation see Chapter 21. • 000: No reset condition • 001: Partner's event status: When the partner counter causes an event status condition to be activated, either by a counter overflow or max comparison, then this counter will reset and continue counting. • 010: Partners PME register event: When the partner counter detects a match condition which meets its selected PME register qualifications, then this counter will reset and continue counting. • 011: This PM counter's status output. • 100: GE[0], from the Global Debug Event Block. • 101: GE[1], from the Global Debug Event Block. • 110: GE[2], from the Global Debug Event Block. • 111: GE[3], from the Global Debug Event Block. ***Note:*** The GEs used are dependent on bit 31 (LOCGLOBEVSEL). If bit 31 is used, local events will be used instead of global events.
7:6	0x0 RW	**Compare Mode (CMPMD):** This field defines how the PMC (compare) register is to be used. • 00: compare mode disabled (PMC register not used) sig p = sig s • 01: max compare only: The PMC register value is compared with the counter value. If the counter value is greater then the Compare Status (CMPSTAT) will be set. sig p = sig n • 10: max compare with update of PMC at end of sample: The PMC register value is compared with the counter value, and if the counter value is greater, the PMC register is updated with the counter value. Note, the Compare Status field is not affected in this mode. sig p = sig n • 11: Reserved
5	0x0 RW	**PM Status Signal Output (PMSSIG):** • 0: Level output from status/overflow signals. • 1: Pulsed output from status/overflow signals.
4:3	0x0 RW	**PerfMon Trigger Output (PTO):** This field selects what the signal is communicated to the chip's event logic structure. • 00: No cluster trigger output from PerfMons or header match. • 01: PM Status. • 10: PM Event Detection. • 11: Address Header Match
2	0x0 RW/1C/V	**Compare Status (CMPSTAT):** This status bit captures a count compare event. • 0: no event • 1: count compare - PMD counter greater than PMC register when in compare mode. This bit remains set once an event is reported even though the original condition is no longer valid. Writing a logic '1' clears the bit.
1	0x0 RW/1C/V	**Overflow Status Bit (OVS):** This status bit captures the overflow event from the PMD counter. This bit remains set once an event is reported even though the original condition is no longer valid. Writing a logic '1' clears the bit.
0	0x0 RW	**Counter Reset (CNTRST):** Setting this bit resets the following bit fields. This only applies to the set of registers for this PM block. Setting this bit resets the PMD counter, the associated adder storage register and the count mode state latch (see bits CNTMD) to the default state. It does not change the state of this PMR register, the event selections, or the value in the compare register. ***Note:*** This bit must be cleared by software, otherwise the counters remain in reset. There is also a reset bit in the XPPERFCON register which clears all PM registers including the PMR.

48.2.126 XPPMEVL0—Offset 29Ch

Selections in this register correspond to fields within the PEX packet header. Each field selection is ANDed with all other fields in this register including the XPPMEVH except where noted.

The qualifications for fields in this register are as follows: PMEV Match = ((IO_Cfg_Write_event + IO_Cfg_Read_event _+ Mem_Write_event + Mem_Read_event + Trusted_write_event + Trusted_read_event + General_event) and INOUTBND) + GESEL IO_Cfg_Write_event = (REQCMP[0] and CMPR[1] and RDWR[1] and DATALEN and (TTYP[2] + (TTYP[1] and CFGTYP))) IO_Cfg_Read_event = (REQCMP[0] and CMPR[1] and RDWR[0] and DATALEN and (TTYP[2] + (FMTTYP[1] and CFGTYP))) Mem_Write_event = (REQCMP[0] and CMPR[0] and RDWR[1] and DATALEN and TTYP[3] and LOCK and EXTADDR and SNATTR)

Note: An outbound memory write does not have a snoop attribute as an inbound memory write has. So the user should set SNATTR='11' for outbound memory write transaction event counting. Mem_Read_event = (REQCMP[0] and CMPR[1] and RDWR[0] and DATALEN and ((TTYP[3] and LOCK and EXTADDR and SNATTR) + TTYP[2] + (TTYP[1] and CFGTYP)))

Note: For outbound memory reads there is no concept of issuing a snoop cycle. The user should select SNATTR='11' for either snoop attribute. Msg_event = (TTYP[0] and DND) (INOUTBND[0] and (MatchEq) + (IOBND[1] and (MatchEq)

Note: Setting both bits in INOUTBND is acceptable however the performance data gathered will not be accurate since once one header can be counted at a time.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 29Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RW	**Data or No Data Attribute (DND):** • x1: Request/completion/message packet with data • 1x: Request/completion/message packet without data
29:28	0x0 RW	**Snoop Attribute (SNATTR):** • x1: Snoop required • 1x: No snoop required • 11: Either
27:26	0x0 RW	**Request or Completion Packet Selection (REQCMP):** • x1: Request packet • 1x: Completion packet • 11: Either
25:24	0x0 RW	**Read or Write Selection (RDWR):** • x1: Read • 1x: Write • 11: Either
23:22	0x0 RW	**Completion Required (CMPR):** (Request packet only) • x1: No completion required • 1x: Completion required • 11: Either
21:20	0x0 RW	**Lock Attribute Selection (LOCK):** • x1: No lock • 1x: Lock • 11: Either

Bit Range	Default & Access	Field Name (ID): Description
19:18	0x0 RW	**Extended Addressing Header (EXTADDR):** • x1: 32b addressing • 1x: 64b addressing • 11: Either
17:16	0x0 RW	**Configuration Type (CFGTYP):** (If Config cycle Space selected) • x1: Type 0 • 1x: Type 1 • 11: Either
15:11	0x0 RW	**Transaction Type Encoding (TTYP):** (ORed group) • 1xxxx: Trusted • x1xxx: Memory • xx1xx: IO • xxx1x: Configuration • xxxx1: Messages • 11111: Any transaction type
10:4	0x0 RW	**Data Length (DATLEN):** • 1xxxxxx: (129 to 256 bytes) • x1xxxxx: (65 to 128 bytes) • xx1xxxx: (33 to 64 bytes) • xxx1xxx: (17 to 32 bytes) • xxxx1xx: (9 to 16 bytes) • xxxxx1x: (0 to 8 bytes) • xxxxxx1: 0 bytes, used for a special zero length encoded packets • 1111111: Any Data length
3:0	0x0 RW	**Completion Status (CMPSTAT):** (for Completion Packet) or message encoding (for Request Packet). • 1xxx: Completer abort • x1xx: Configuration request retry status (only used for receive completions) • xx1x: Unsupported request • xxx1: Successful completion • 1111: Any status

48.2.127 XPPMEVL1—Offset 2A0h

Selections in this register correspond to fields within the PEX packet header. Each field selection is ANDed with all other fields in this register including the XPPMEVH except where noted. The qualifications for fields in this register are as follows: PMEV Match = ((IO_Cfg_Write_event + IO_Cfg_Read_event _+ Mem_Write_event + Mem_Read_event + Trusted_write_event + Trusted_read_event + General_event) and INOUTBND) + GESEL IO_Cfg_Write_event = (REQCMP[0] and CMPR[1] and RDWR[1] and DATALEN and (TTYP[2] + (TTYP[1] and CFGTYP))) IO_Cfg_Read_event = (REQCMP[0] and CMPR[1] and RDWR[0] and DATALEN and (TTYP[2] + (FMTTYP[1] and CFGTYP))) Mem_Write_event = (REQCMP[0] and CMPR[0] and RDWR[1] and DATALEN and TTYP[3] and LOCK and EXTADDR and SNATTR)

Note: An outbound memory write does not have a snoop attribute as an inbound memory write has. So the user should set SNATTR='11' for outbound memory write transaction event counting. Mem_Read_event = (REQCMP[0] and CMPR[1] and RDWR[0] and DATALEN and ((TTYP[3] and LOCK and EXTADDR and SNATTR) + TTYP[2] + (TTYP[1] and CFGTYP)))

Note: For outbound memory reads there is no concept of issuing a snoop cycle. The user should select SNATTR='11' for either snoop attribute. Msg_event = (TTYP[0] and DND) (INOUTBND[0] and (MatchEq) + (IOBND[1] and (MatchEq)

Note: Setting both bits in INOUTBND is acceptable however the performance data gathered will not be accurate since once one header can be counted at a time.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2A0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RW	**Data or No Data Attribute (DND):** • x1: Request/completion/message packet with data • 1x: Request/completion/message packet without data
29:28	0x0 RW	**Snoop Attribute (SNATTR):** • x1: Snoop required • 1x: No snoop required • 11: Either
27:26	0x0 RW	**Request or Completion Packet Selection (REQCMP):** • x1: Request packet • 1x: Completion packet • 11: Either
25:24	0x0 RW	**Read or Write Selection (RDWR):** • x1: Read • 1x: Write • 11: Either
23:22	0x0 RW	**Completion Required (CMPR):** (Request packet only) • x1: No completion required • 1x: Completion required • 11: Either
21:20	0x0 RW	**Lock Attribute Selection (LOCK):** • x1: No lock • 1x: Lock • 11: Either

Bit Range	Default & Access	Field Name (ID): Description
19:18	0x0 RW	**Extended Addressing Header (EXTADDR):** • x1: 32b addressing • 1x: 64b addressing • 11: Either
17:16	0x0 RW	**Configuration Type (CFGTYP):** (If Config cycle Space selected) • x1: Type 0 • 1x: Type 1 • 11: Either
15:11	0x0 RW	**Transaction Type Encoding (TTYP):** (ORed group) • 1xxxx: Trusted • x1xxx: Memory • xx1xx: IO • xxx1x: Configuration • xxxx1: Messages • 11111: Any transaction type
10:4	0x0 RW	**Data Length (DATLEN):** • 1xxxxxx: (129 to 256 bytes) • x1xxxxx: (65 to 128 bytes) • xx1xxxx: (33 to 64 bytes) • xxx1xxx: (17 to 32 bytes) • xxxx1xx: (9 to 16 bytes) • xxxxx1x: (0 to 8 bytes) • xxxxxx1: 0 bytes, used for a special zero length encoded packets • 1111111: Any Data length
3:0	0x0 RW	**Completion Status (CMPSTAT):** (for Completion Packet) or message encoding (for Request Packet). • 1xxx: Completer abort • x1xx: Configuration request retry status (only used for receive completions) • xx1x: Unsupported request • xxx1: Successful completion • 1111: Any status

48.2.128 XPPMEVH0—Offset 2A4h

Selections in this register correspond to fields within the PEX packet header. Each field selection is ANDed with all other fields in this register including the XPPMEVL except for the Global Event signals. These signals are OR'ed with any event in the XPPMEVL and enables for debug operations requiring the accumulation of specific debug signals.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2A4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD0:** Reserved
5:2	0x0 RW	**Global Event Selection (GESEL):** Selects which GE[3:0] is used for event counting. This field is OR'd with other fields in this register. The GEs cannot be qualified with other PerfMon signals. If more than 1 GE is selected then the resultant event is the OR between each GE. However, properly counting Global Event based on design, XP PM Response Control Register bit [13:11] CENS must be set to choose GE[3:0] and also bit[18:17] CNTEVSEL must be set to 2'b10. • 1xxx: GE[3] • x1xx: GE[2] • xx1x: GE[1] • xxx1: GE[0]
1:0	0x0 RW	**Receive or Transmit Selection (RXTXSEL):** Selects which path to count transactions. • 1x: Transmit • x1: Receive (from PCI bus) • 11: Either

48.2.129 XPPMEVH1—Offset 2A8h

Selections in this register correspond to fields within the PEX packet header. Each field selection is ANDed with all other fields in this register including the XPPMEVL except for the Global Event signals. These signals are OR'ed with any event in the XPPMEVL and enables for debug operations requiring the accumulation of specific debug signals.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2A8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD0:** Reserved
5:2	0x0 RW	**Global Event Selection (GESEL):** Selects which GE[3:0] is used for event counting. This field is OR'd with other fields in this register. The GEs cannot be qualified with other PerfMon signals. If more than 1 GE is selected then the resultant event is the OR between each GE. However, properly counting Global Event based on design, XP PM Response Control Register bit [13:11] CENS must be set to choose GE[3:0] and also bit[18:17] CNTEVSEL must be set to 2'b10. • 1xxx: GE[3] • x1xx: GE[2] • xx1x: GE[1] • xxx1: GE[0]
1:0	0x0 RW	**Receive or Transmit Selection (RXTXSEL):** Selects which path to count transactions. • 1x: Transmit • x1: Receive (from PCI bus) • 11: Either

48.2.130 XPPMER0—Offset 2ACh

This register is used to select queuing structures for measurement. Use of this event register is mutually exclusive with the XPPMEVL,H registers. The Event Register Select field in the PMR register must select this register for to enable monitoring operations of the queues.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2ACh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Count Uncorrectable Errors (CNTUCERR):** Setting this bit enables the counting of uncorrectable errors by the perfmon counter. Only uncorrectable errors that are not masked by the ERRUNCDETMSK register are counted. Errors are counted on the ports enabled by the XPRSCA field in this register.
23	0x0 RW	**Count Correctable Errors (CNTCERR):** Setting this bit enables the counting of correctable errors by the perfmon counter. Only correctable errors that are not masked by the ERRCORDETMSK register are counted. Errors are counted on the ports enabled by the XPRSCA field in this register.
22	0x0 RW	**Tx L0s state utilization event (TXL0SU):** • 0: No tx_l0s utilization selected • 1: Enable tx_l0s utilization counting
21	0x0 RW	**Rx L0s state utilization event (RXL0SU):** • 0: No rx_l0s utilization selected • 1: Enable rx_l0s utilization counting
20:17	0x0 RW	**XP Resource Assignment (XPRSCA):** This selects which PCI-Express links are being monitored and against with XPPMEVL and XPPMEFH match registers and the queue measure select modes. A logic 1 selects that PCIe link for monitoring. • 1000: Select port 3 for monitoring. • 0100: Select port 2 for monitoring. • 0010: Select port 1 for monitoring. • 0001: Select port 0 for monitoring. If multiple bits are set, each port with a set bit will be counted (ie. you can count the total traffic on all ports).
16:13	0x0 RW	**Link Utilization (LNKUTIL):** Link Utilization field counts clocks that a port is receiving data and checking for receiver errors. It is used to calculate link reliability. If one counter counts receiver errors and another counter counts the cycles the port was checking for receiver error, a bit error rate can be calculated. • 0000: No event selected • 1000: Port 3 of 4, where applicable (DSPs only) • 0100: Port 2 of 4, where applicable (DSPs only) • 0010: Port 1 of 4, where applicable (DSPs only) • 0001: Port 0 of 4 (USP, DSPs, vSP/vRP) If multiple bits are set, each port with a set bit will be counted (ie. you can count the total traffic on all ports) For configs with less then 4 ports, the upper bits corresponding to non-existent ports have no effect
12	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
11:10	0x0 RW	**Queue Measure Select (QMSEL):** • 00: Transaction Bandwidth Measurement. Counts data payload in dwords going in the direction programmed (RxTx, FC, VC, Port) • 01: FIFO Queue Histogram Measurement. Uses the queue depth. (RxTx, FC, VC, Port, Hdr/Data) • 10: Credit Consumed Histogram Measurement. Uses the credit consumed count. (RxTx, FC, VC, Port, Hdr/Data) • 11: Reserved
9	0x0 RW	**Header Data Select (HDSEL):** • 0: Data Queue selected • 1: Header Queue selected
8	0x0 RW	**All VC Select (AVCSEL):** • 0: Not all VC selected • 1: All VC selected This bit will override VCSEL if selected
7:5	0x0 RW	**VC Select (VCSEL):** This field selects which VC to count. Only one VC can be counted at a time.
4:2	0x0 RW	**Flow Control Class Select (FCCSEL):** This field selects which flow class for resource event • xx1: Posted • x1x: Non-Posted • 1xx: Completion
1:0	0x0 RW	**Tx/Rx Select (TXRXSEL):** This field selects a Tx/Rx queue to monitor. Either receiver or transmit direction for measurement. • 1x: Transmit • x1: Receive (from PCIe bus) • 11: Either Transmit or Receive direction

48.2.131 XPPMER1—Offset 2B0h

This register is used to select queuing structures for measurement. Use of this event register is mutually exclusive with the XPPMEVL,H registers. The Event Register Select field in the PMR register must select this register for to enable monitoring operations of the queues.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Count Uncorrectable Errors (CNTUCERR):** Setting this bit enables the counting of uncorrectable errors by the perfmon counter. Only uncorrectable errors that are not masked by the ERRUNCDETMSK register are counted. Errors are counted on the ports enabled by the XPRSCA field in this register.
23	0x0 RW	**Count Correctable Errors (CNTCERR):** Setting this bit enables the counting of correctable errors by the perfmon counter. Only correctable errors that are not masked by the ERRCORDETMSK register are counted. Errors are counted on the ports enabled by the XPRSCA field in this register.
22	0x0 RW	**Tx L0s state utilization event (TXL0SU):** • 0: No tx_l0s utilization selected • 1: Enable tx_l0s utilization counting
21	0x0 RW	**Rx L0s state utilization event (RXL0SU):** • 0: No rx_l0s utilization selected • 1: Enable rx_l0s utilization counting
20:17	0x0 RW	**XP Resource Assignment (XPRSCA):** This selects which PCI-Express links are being monitored and against with XPPMEVL and XPPMEFH match registers and the queue measure select modes. A logic 1 selects that PCIe link for monitoring. • 1000: Select port 3 for monitoring. • 0100: Select port 2 for monitoring. • 0010: Select port 1 for monitoring. • 0001: Select port 0 for monitoring. If multiple bits are set, each port with a set bit will be counted (ie. you can count the total traffic on all ports).
16:13	0x0 RW	**Link Utilization (LNKUTIL):** Link Utilization field counts clocks that a port is receiving data and checking for receiver errors. It is used to calculate link reliability. If one counter counts receiver errors and another counter counts the cycles the port was checking for receiver error, a bit error rate can be calculated. • 0000: No event selected • 1000: Port 3 of 4, where applicable (DSPs only) • 0100: Port 2 of 4, where applicable (DSPs only) • 0010: Port 1 of 4, where applicable (DSPs only) • 0001: Port 0 of 4 (USP, DSPs, vSP/vRP) If multiple bits are set, each port with a set bit will be counted (ie. you can count the total traffic on all ports) For configs with less then 4 ports, the upper bits corresponding to non-existent ports have no effect
12	0x0 RO	**RSVD1:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
11:10	0x0 RW	**Queue Measure Select (QMSEL):** • 00: Transaction Bandwidth Measurement. Counts data payload in dwords going in the direction programmed (RxTx, FC, VC, Port) • 01: FIFO Queue Histogram Measurement. Uses the queue depth. (RxTx, FC, VC, Port, Hdr/Data) • 10: Credit Consumed Histogram Measurement. Uses the credit consumed count. (RxTx, FC, VC, Port, Hdr/Data) • 11: Reserved
9	0x0 RW	**Header Data Select (HDSEL):** • 0: Data Queue selected • 1: Header Queue selected
8	0x0 RW	**All VC Select (AVCSEL):** • 0: Not all VC selected • 1: All VC selected This bit will override VCSEL if selected
7:5	0x0 RW	**VC Select (VCSEL):** This field selects which VC to count. Only one VC can be counted at a time.
4:2	0x0 RW	**Flow Control Class Select (FCCSEL):** This field selects which flow class for resource event • xx1: Posted • x1x: Non-Posted • 1xx: Completion
1:0	0x0 RW	**Tx/Rx Select (TXRXSEL):** This field selects a Tx/Rx queue to monitor. Either receiver or transmit direction for measurement. • 1x: Transmit • x1: Receive (from PCIe bus) • 11: Either Transmit or Receive direction

48.2.132 XPPMDFXMAT0—Offset 2B4h

This register contains bits to enable matching of any event signal on the local debug bus in this cluster. Only 3 byte lanes are possible for PerfMon counting by selecting bits in PMR.DFXLNSEL. This register is active when the PMR.LDES is set.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2B4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:26	0x0 RW	**Divider (DIV):** See Table 3-16, 'Boolean Combination of Debug Signals' on page 109 of Chapter 3, 'DFD Event Logic' of the Seaburg DFT and Debug (DFx) CSPEC
25:24	0x0 RW	**OR Function Locator (ORFLOC):** See Table 3-16, 'Boolean Combination of Debug Signals' on page 109 of Chapter 3, 'DFD Event Logic' of the Seaburg DFT and Debug (DFx) CSPEC ORFLOC.....DIV.....Resultant Boolean Equation 00.....00.....C+B+A 00.....01.....(C+B)+A 00.....10.....C(B+A) 00.....11.....CBA 01.....01.....C+B+A 01.....11.....CB+A 10.....10.....C+B+A 10.....11.....C+BA 11.....11.....C+B+A ***Note:*** Assume that PMR.DFXLNSEL=00 1. Let A = a match on debug lane 0 2. Let B= a match on debug lane 1. 3. Let C= a match on debug lane 2.
23:16	0x0 RW	**DFx Match on Event Signal Lane N+2 (DFXMAT2):** Reserved.
15:8	0x0 RW	**DFx Match on Event Signal Lane N+1 (DFXMAT1):** Reserved.
7:0	0x0 RW	**DFx Match on Event Signal Lane N (DFXMAT0):** Reserved.

48.2.133 XPPMDFXMAT1—Offset 2B8h

This register contains bits to enable matching of any event signal on the local debug bus in this cluster. Only 3 byte lanes are possible for PerfMon counting by selecting bits in PMR.DFXLNSEL. This register is active when the PMR.LDES is set.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2B8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:26	0x0 RW	**Divider (DIV):** See Table 3-16, 'Boolean Combination of Debug Signals' on page 109 of Chapter 3, 'DFD Event Logic' of the Seaburg DFT and Debug (DFx) CSPEC
25:24	0x0 RW	**OR Function Locator (ORFLOC):** See Table 3-16, 'Boolean Combination of Debug Signals' on page 109 of Chapter 3, 'DFD Event Logic' of the Seaburg DFT and Debug (DFx) CSPEC ORFLOC.....DIV.....Resultant Boolean Equation 00.....00.....C+B+A 00.....01.....(C+B)+A 00.....10.....C(B+A) 00.....11.....CBA 01.....01.....C+B+A 01.....11.....CB+A 10.....10.....C+B+A 10.....11.....C+BA 11.....11.....C+B+A ***Note:*** Assume that PMR.DFXLNSEL=00 1. Let A = a match on debug lane 0. 2. Let B= a match on debug lane 1. 3. Let C= a match on debug lane 2.
23:16	0x0 RW	**DFx Match on Event Signal Lane N+2 (DFXMAT2):** Reserved.
15:8	0x0 RW	**DFx Match on Event Signal Lane N+1 (DFXMAT1):** Reserved.
7:0	0x0 RW	**DFx Match on Event Signal Lane N (DFXMAT0):** Reserved.

48.2.134 XPPMDFXMSK0—Offset 2BCh

This register contains bits to enable masking of any event signal on the local debug bus in this cluster. Only 3 byte lanes are possible for PerfMon counting by selecting bits in PMR.DFXLNSEL. This register is active when the PMR.LDES is set.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2BCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x0 RW	**DFx Mask on Event Signal Lane N+2 (DFXMSK2):** Reserved.
15:8	0x0 RW	**DFx Mask on Event Signal Lane N+1 (DFXMSK1):** Reserved.
7:0	0x0 RW	**DFx Mask on Event Signal Lane N (DFXMSK0):** Reserved.

48.2.135 XPPMDFXMSK1—Offset 2C0h

This register contains bits to enable masking of any event signal on the local debug bus in this cluster. Only 3 byte lanes are possible for PerfMon counting by selecting bits in PMR.DFXLNSEL. This register is active when the PMR.LDES is set.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x0 RW	**DFx Mask on Event Signal Lane N+2 (DFXMSK2):** Reserved.
15:8	0x0 RW	**DFx Mask on Event Signal Lane N+1 (DFXMSK1):** Reserved.
7:0	0x0 RW	**DFx Mask on Event Signal Lane N (DFXMSK0):** Reserved.

48.2.136 XPPERFCON—Offset 2C4h

The XPPERFCON register is a local performance monitor control register used to clear all of the counters or to assign which XP (PCIe) device participates in the performance monitoring event. All perfmon blocks will needs this register. We will perform ORing this register and global PERFCON from full chip for backup usage and self contained purpose.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**RSVD0:** Reserved
1	0x0 RW	**Global Count Enable (GCE):** This bit is AND'ed with the PMR.CENS mux enable selection. • 0: Disable all counters. • 1: Enable local selection of CENS.
0	0x0 RW	**Global Reset (GRST):** Setting this bit to a logic 1 will reset the following bit fields in all PerfMon blocks throughout the component. xxxPMDx.CNT xxxPMR.OVS xxxPMR.CMPSTAT xxxPMCx.PMCx registers, and count mode state latch selected by xxxPMR.CNTMD = '01'. Where xxx is the cluster prefix name. ***Note:*** Software must clear this bit after setting it, otherwise the PerfMons remain in a reset state.

48.2.137 XPPERFSTAT—Offset 2C8h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2C8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:2	0x0 RO	**RSVD0:** Reserved
1	0x0 RW/1C/V	**XP cluster PM1 Status (XPPM1STAT):** This bit indicates the status of PM0 from either the compare or overflow status. This is bit is cleared by writing a '1'.
0	0x0 RW/1C/V	**XP cluster PM0 Status (XPPM0STAT):** This bit indicates the status of PM0 from either the compare or overflow status. This is bit is cleared by writing a '1'.

48.2.138 XPCDTHROTTLEP—Offset 2D0h

This register controls the withholding of posted credits for throttling and survivability. For PCIe ports, the receive direction applies to PCIe credits and the transmit direction applies to IOSF credits. For the vSP/RP where both sides are IOSF credits, the receive credits apply to the IDF credits. Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL.TLCL').

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RW/P/L	**Tx Posted Request Data Throttling (TXPRD):** Remove this many credits from the available pool of credits for this type of transaction.
22:16	0x0 RW/P/L	**Tx Posted Request Header Throttling (TXPRH):** Remove this many credits from the available pool of credits for this type of transaction.
15:7	0x0 RW/P/L	**Rx Posted Request Data Throttling (RXPRD):** Remove this many credits from the available pool of credits for this type of transaction.
6:0	0x0 RW/P/L	**Rx Posted Request Header Throttling (RXPRH):** Remove this many credits from the available pool of credits for this type of transaction.

48.2.139 XPCDTHROTTLEN—Offset 2D4h

This register controls the withholding of non-posted credits for throttling and survivability. For PCIe ports, the receive direction applies to PCIe credits and the transmit direction applies to IOSF credits. For the vSP/RP where both sides are IOSF credits, the receive credits apply to the IDF credits. Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL.TLCL').

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2D4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RW/P/L	**Tx Non-Posted Request Data Throttling (TXNPRD):** Remove this many credits from the available pool of credits for this type of transaction.
22:16	0x0 RW/P/L	**Tx Non-Posted Request Header Throttling (TXNPRH):** Remove this many credits from the available pool of credits for this type of transaction.
15:7	0x0 RW/P/L	**Rx Non-Posted Request Data Throttling (RXNPRD):** Remove this many credits from the available pool of credits for this type of transaction.
6:0	0x0 RW/P/L	**Rx Non-Posted Request Header Throttling (RXNPRH):** Remove this many credits from the available pool of credits for this type of transaction.

48.2.140 XPCDTHROTTLEC—Offset 2D8h

This register controls the withholding of completion credits for throttling and survivability. For PCIe ports, the receive direction applies to PCIe credits and the transmit direction applies to IOSF credits. For the vSP/RP where both sides are IOSF credits, the receive credits apply to the IDF credits. Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL.TLCL').

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2D8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RW/P/L	**Tx Completion Data Throttling (TXCPLD):** Remove this many credits from the available pool of credits for this type of transaction.
22:16	0x0 RW/P/L	**Tx Completion Header Throttling (TXCPLH):** Remove this many credits from the available pool of credits for this type of transaction.
15:7	0x0 RW/P/L	**Rx Completion Data Throttling (RXCPLD):** Remove this many credits from the available pool of credits for this type of transaction.
6:0	0x0 RW/P/L	**Rx Completion Header Throttling (RXCPLH):** Remove this many credits from the available pool of credits for this type of transaction.

48.2.141 IOSFDEVCLKGCTL—Offset 2E4h

It is included for DMI EP in RC as an extension of Rootport definition.

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2E4h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block controls the delay before going into IDLE. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.142 SBDEVCLKGCTL—Offset 2E6h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 2E6h

Default: 8010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x1 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.143 VDHDRCAP—Offset 300h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 300h

Default: 0001000Bh

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW/L	**Next Capability Offset (PCIeNextPtr):** Contains the offset of the next item in the capabilities list. **Power Well:** PRST
19:16	0x1 RO	**Capability Version (PCIeCapVersion):** These bits indicate the version number of the PCI Express capability structure.
15:0	0xb RO	**Extended Capability ID (PCIeCapID):** Identifies the function as a Vendor Specific capability.

48.2.144 IBSTHDRCAP—Offset 304h

This register stores the version number of the capability item and other base information contained in the capability structure.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 304h

Default: 2A800001h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x2a8 RO	**Vendor Specific Extended Capability Length (VSECLength):** These bits indicate the length of the PCI Express extended capability structure.
19:16	0x0 RO	**Revision Number (VSECIDRev):** These bits indicate the Revision number of the PCI Express capability structure.
15:0	0x1 RO	**Vendor Specific Extended Capability ID (VSECID):** Reserved.

48.2.145 IBSTENGLKSPDCAP—Offset 310h

REUT-ENG-LSCAPDevice: 7

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 310h

Default: 00000007h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**RSVD0:** Reserved
29	0x0 RO	**Unique Speed (UniqSpd):** Reserved.
28	0x0 RO	**LSCTR is Passive (SpdCtlPassive):** Link speed is set by Link Speed Control (IBISTENGLKSPDCTL) register or it is passive where REUT-ENG-LSCTR (IBISTENGLKSPDCTL) does not control link speed.
27:26	0x0 RO	**RSVD1:** Reserved
25:24	0x0 RO/V	**Number of Test Controllers (NumTestContr):** Need to update with respect to port type.
23:16	0x0 RO	**RSVD2:** Reserved
15:8	0x0 RO	**Link Speed Capability1 (LinkSpeedCap1):** This field indicates the link speed. Valid only if Unique Speed is 1b and # of Test Controllers is) 0. • 00000001b: Gen 1 Speed (2.5 GT/s) • 00000010b: Gen 2 Speed (5 GT/s) • 00000100b: Gen 3 Speed (8 GT/s) • Others: Reserved.
7:0	0x7 RO/V	**Link Speed Capability (LinkSpeedCap):** This field indicates the link speed capabilities of test controller 0 (if Unique Speed = 1b) or all Test Controllers (if Unique Speed = 0). • 00000001b: Gen 1 Speed (2.5 GT/s) • 00000010b: Gen 2 Speed (5 GT/s - Never used) • 00000011b: Gen 1 and Gen 2 Speeds • 00000100b: Gen 3 Speed Only (Unique Speed = 1) • 00000111b: Gen 1, Gen2, and Gen3 Speed • Others: Reserved.

48.2.146 IBSTENGLKSPDCTL—Offset 314h

REUT-ENG-LSCTR

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 314h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/L	**Link 3 Speed Select (Link3SpeedSel):** This field controls the link speed of Link 3 if defined. This field overrides target link speed field defined in PCI Express spec and forces the link to operate at specified speed when programmed to a non-zero value. • 00000000b: Force link speed control off • 00000001b: Gen 1 Speed (2.5 GT/s) • 00000010b: Gen 2 Speed (5 GT/s) • 00000100b: Gen 3 Speed (8 GT/s) • Others: Reserved.
23:16	0x0 RW/L	**Link 2 Speed Select (Link2SpeedSel):** This field controls the link speed of Link 2 if defined. This field overrides target link speed field defined in PCI Express spec and forces the link to operate at specified speed when programmed to a non-zero value. • 00000000b: Force link speed control off • 00000001b: Gen 1 Speed (2.5 GT/s) • 00000010b: Gen 2 Speed (5 GT/s) • 00000100b: Gen 3 Speed (8 GT/s) • Others: Reserved.
15:8	0x0 RW/L	**Link 1 Speed Select (Link1SpeedSel):** This field controls the link speed of Link 1 if defined. This field overrides target link speed field defined in PCI Express spec and forces the link to operate at specified speed when programmed to a non-zero value. • 00000000b: Force link speed control off • 00000001b: Gen 1 Speed (2.5 GT/s) • 00000010b: Gen 2 Speed (5 GT/s) • 00000100b: Gen 3 Speed (8 GT/s) • Others: Reserved.
7:0	0x0 RW/L	**Link 0 Speed Select (Link0SpeedSel):** This field controls the link speed of Link 0. This field overrides target link speed field defined in PCI Express spec and forces the link to operate at specified speed when programmed to a non-zero value. • 00000000b: Force link speed control off • 00000001b: Gen 1 Speed (2.5 GT/s) • 00000010b: Gen 2 Speed (5 GT/s) • 00000100b: Gen 3 Speed (8 GT/s) • Others: Reserved.

48.2.147 IBSTENGLKTXRXCFG—Offset 31Ch

REUT-ENG-LTRCON

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 31Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:26	0x0 RO	**RSVD0:** Reserved
25	0x0 RO	**Link Automatic Configuration (LinkAutoConfiguration):** Link automatic configuration is not supported by this IBIST engine.
24	0x0 RW/P/L	**IBIST Write Disable (ReutDisable):** When set, this bit will prevent software writes to the IBIST engine's PCI Express Extended Capability Register Structure to prevent unwanted usage of the IBIST engine. Once set, the registers are unwritable until next Powergood reset. ***Note:*** At a Minimum, REUT-ENG-LSCTR.LinkSpeedSel, REUT-ENG-LTRCON.LinkControl, REUT-PAT-TEC.StartTest, and REUT-PH-CTR.Initialization Mode are cleared and locked.
23:15	0x0 RO	**RSVD1:** Reserved
14:8	0x0 RO	**Link Control 1 (LinkControl1):** This field is only valid if Unique Speed is a 1b and Number tof test controllers is) 0.
7	0x0 RO	**RSVD2:** Reserved
6:0	0x0 RW/P/L	**Link Control (LinkControl):** This field indicates the number of links under the control of the IBIST Engine. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware. All the odd bits can not be set by SW. Need to become RO-V to reflect LWCTRL register for downstream or Root ports.

48.2.148 IBSTERRCRCSTS0—Offset 320h

REUT-ERR-CED0-3

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 320h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C/V/P	**CRC Error Overflow (CrcECC2Ovrflow):** Reserved.
14:0	0x0 RW/1C/V/P	**CRC Error Counter (CrcECC2ErrCnt):** Reserved.

48.2.149 IBSTERRRCRVSTS0—Offset 324h

REUT-ERR-ECCRCV0-3 IBSTERRRCRVSTS[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 324h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**Recovery Overflow (LinkRecovOverflow):** This bit when 1b, indicates the recovery counter has overflowed.
30:16	0x0 RW/1C/V/P	**Recovery Counter (RecovCnt):** This field indicates the number of times the link(s) LTSSM state machine has entered the recovery state.
15	0x0 RW/1C/V/P	**Receiver Error Overflow (RxErrCntOvrflow):** This bit when 1b, indicates the receive error counter has overflowed.
14:0	0x0 RW/1C/V/P	**Receiver Error Counter (RxErrCnt):** This field indicates the number of times the link(s) has detected an 8b/10b receiver error.

48.2.150 IBSTERRCRCSTS1—Offset 328h

REUT-ERR-CED0-3

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 328h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C/V/P	**CRC Error Overflow (CrcECC2Ovrflow):** Reserved.
14:0	0x0 RW/1C/V/P	**CRC Error Counter (CrcECC2ErrCnt):** Reserved.

48.2.151 IBSTERRRCRVSTS1—Offset 32Ch

REUT-ERR-ECCRCV0-3 IBSTERRRCRVSTS[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 32Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**Recovery Overflow (LinkRecovOverflow):** This bit when 1b, indicates the recovery counter has overflowed.
30:16	0x0 RW/1C/V/P	**Recovery Counter (RecovCnt):** This field indicates the number of times the link(s) LTSSM state machine has entered the recovery state.
15	0x0 RW/1C/V/P	**Receiver Error Overflow (RxErrCntOvrflow):** This bit when 1b, indicates the receive error counter has overflowed.
14:0	0x0 RW/1C/V/P	**Receiver Error Counter (RxErrCnt):** This field indicates the number of times the link(s) has detected an 8b/10b receiver error.

48.2.152 IBSTERRCRCSTS2—Offset 330h

REUT-ERR-CED0-3

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 330h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C/V/P	**CRC Error Overflow (CrcECC2Ovrflow):** Reserved.
14:0	0x0 RW/1C/V/P	**CRC Error Counter (CrcECC2ErrCnt):** Reserved.

48.2.153 IBSTERRRCRVSTS2—Offset 334h

REUT-ERR-ECCRCV0-3 IBSTERRRCRVSTS[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 334h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**Recovery Overflow (LinkRecovOverflow):** This bit when 1b, indicates the recovery counter has overflowed.
30:16	0x0 RW/1C/V/P	**Recovery Counter (RecovCnt):** This field indicates the number of times the link(s) LTSSM state machine has entered the recovery state.
15	0x0 RW/1C/V/P	**Receiver Error Overflow (RxErrCntOvrflow):** This bit when 1b, indicates the receive error counter has overflowed.
14:0	0x0 RW/1C/V/P	**Receiver Error Counter (RxErrCnt):** This field indicates the number of times the link(s) has detected an 8b/10b receiver error.

48.2.154 IBSTERRCRCSTS3—Offset 338h

REUT-ERR-CED0-3

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 338h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/1C/V/P	**CRC Error Overflow (CrcECC2Ovrflow):** Reserved.
14:0	0x0 RW/1C/V/P	**CRC Error Counter (CrcECC2ErrCnt):** Reserved.

48.2.155 IBSTERRRCRVSTS3—Offset 33Ch

REUT-ERR-ECCRCV0-3 IBSTERRRCRVSTS[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 33Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**Recovery Overflow (LinkRecovOverflow):** This bit when 1b, indicates the recovery counter has overflowed.
30:16	0x0 RW/1C/V/P	**Recovery Counter (RecovCnt):** This field indicates the number of times the link(s) LTSSM state machine has entered the recovery state.
15	0x0 RW/1C/V/P	**Receiver Error Overflow (RxErrCntOvrflow):** This bit when 1b, indicates the receive error counter has overflowed.
14:0	0x0 RW/1C/V/P	**Receiver Error Counter (RxErrCnt):** This field indicates the number of times the link(s) has detected an 8b/10b receiver error.

48.2.156 IBSTPHYLCTL0—Offset 344h

REUT-PH-CTR0-3 IBSTPHYLCTL[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 344h

Default: 00400000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x1 RW/P	**Enable Scramble with LFSR (EnableScrambleLFSR):** When set to 1b, this bit enables scrambling by setting the disable scrambling bit in TS1 to 0b. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
21:14	0x0 RO	**RSVD1:** Reserved
13	0x0 RW/P	**Disable Auto-Compliance (DisableAutocompliance):** This bit when set to 1b does not allow the LTSSM state machine to transition from polling to compliance because squelch is enabled. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
12	0x0 RW/P	**Initialization Abort Freeze (InitAbortFreeze):** This bit when set to 1b freezes the LTSSM state machine at whenever a timeout occurs that would have caused the LTSSM state machine to exit to detect state. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
11	0x0 RO	**RSVD2:** Reserved
10:8	0x0 RW/P/L	**Initialization Mode (InitializationMode):** This field indicated the initialization mode of the link. • 000b: Normal Initialization • 001b: Initialization towards Loopback state • 010b: Tester Mode • 011b: Initialization towards Loopback.Compliance Master • 100b: Forced Entry to Compliance Master • 101b: Forced Entry to Compliance Slave • 110b: Initialization towards Compliance Receive • 111b: Reserved. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware. Note: Based on LKCON registers
7:3	0x0 RO	**RSVD3:** Reserved
2	0x0 RO	**Bypass Calibration (BypassCalib):** ***Note:*** This can change based on IO design.
1	0x0 RO	**RSVD4:** Reserved
0	0x0 RW/P	**Physical Layer Reset (PhyLayerReset):** This bit controls the reset assertion to the physical layer. Software is required to both set and clear this bit. ***Note:*** This bit is equivalent to the link disable bit in the link control register. PCIe logic should 'OR' this bit and the link disable bit.

48.2.157 IBSTPHYLCTL1—Offset 348h

REUT-PH-CTR0-3 IBSTPHYLCTL[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 348h

Default: 00400000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x1 RW/P	**Enable Scramble with LFSR (EnableScrambleLFSR):** When set to 1b, this bit enables scrambling by setting the disable scrambling bit in TS1 to 0b. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
21:14	0x0 RO	**RSVD1:** Reserved
13	0x0 RW/P	**Disable Auto-Compliance (DisableAutocompliance):** This bit when set to 1b does not allow the LTSSM state machine to transition from polling to compliance because squelch is enabled. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
12	0x0 RW/P	**Initialization Abort Freeze (InitAbortFreeze):** This bit when set to 1b freezes the LTSSM state machine at whenever a timeout occurs that would have caused the LTSSM state machine to exit to detect state. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
11	0x0 RO	**RSVD2:** Reserved
10:8	0x0 RW/P/L	**Initialization Mode (InitializationMode):** This field indicated the initialization mode of the link. • 000b: Normal Initialization • 001b: Initialization towards Loopback state • 010b: Tester Mode • 011b: Initialization towards Loopback.Compliance Master • 100b: Forced Entry to Compliance Master • 101b: Forced Entry to Compliance Slave • 110b: Initialization towards Compliance Receive • 111b: Reserved. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware. ***Note:*** Based on LKCON registers
7:3	0x0 RO	**RSVD3:** Reserved
2	0x0 RO	**Bypass Calibration (BypassCalib):** ***Note:*** This can change based on IO design.
1	0x0 RO	**RSVD4:** Reserved
0	0x0 RW/P	**Physical Layer Reset (PhyLayerReset):** This bit controls the reset assertion to the physical layer. Software is required to both set and clear this bit. ***Note:*** This bit is equivalent to the link disable bit in the link control register. PCIe logic should 'OR' this bit and the link disable bit.

48.2.158 IBSTPHYLCTL2—Offset 34Ch

REUT-PH-CTR0-3 IBSTPHYLCTL[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 34Ch

Default: 00400000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x1 RW/P	**Enable Scramble with LFSR (EnableScrambleLFSR):** When set to 1b, this bit enables scrambling by setting the disable scrambling bit in TS1 to 0b. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
21:14	0x0 RO	**RSVD1:** Reserved
13	0x0 RW/P	**Disable Auto-Compliance (DisableAutocompliance):** This bit when set to 1b does not allow the LTSSM state machine to transition from polling to compliance because squelch is enabled. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
12	0x0 RW/P	**Initialization Abort Freeze (InitAbortFreeze):** This bit when set to 1b freezes the LTSSM state machine at whenever a timeout occurs that would have caused the LTSSM state machine to exit to detect state. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
11	0x0 RO	**RSVD2:** Reserved
10:8	0x0 RW/P/L	**Initialization Mode (InitializationMode):** This field indicated the initialization mode of the link. • 000b: Normal Initialization • 001b: Initialization towards Loopback state • 010b: Tester Mode • 011b: Initialization towards Loopback.Compliance Master • 100b: Forced Entry to Compliance Master • 101b: Forced Entry to Compliance Slave • 110b: Initialization towards Compliance Receive • 111b: Reserved. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware. ***Note:*** Based on LKCON registers
7:3	0x0 RO	**RSVD3:** Reserved
2	0x0 RO	**Bypass Calibration (BypassCalib):** ***Note:*** This can change based on IO design.
1	0x0 RO	**RSVD4:** Reserved
0	0x0 RW/P	**Physical Layer Reset (PhyLayerReset):** This bit controls the reset assertion to the physical layer. Software is required to both set and clear this bit. ***Note:*** This bit is equivalent to the link disable bit in the link control register. PCIe logic should 'OR' this bit and the link disable bit.

48.2.159 IBSTPHYLCTL3—Offset 350h

REUT-PH-CTR0-3 IBSTPHYLCTL[1-3] are valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 350h

Default: 00400000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x1 RW/P	**Enable Scramble with LFSR (EnableScrambleLFSR):** When set to 1b, this bit enables scrambling by setting the disable scrambling bit in TS1 to 0b. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
21:14	0x0 RO	**RSVD1:** Reserved
13	0x0 RW/P	**Disable Auto-Compliance (DisableAutocompliance):** This bit when set to 1b does not allow the LTSSM state machine to transition from polling to compliance because squelch is enabled. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
12	0x0 RW/P	**Initialization Abort Freeze (InitAbortFreeze):** This bit when set to 1b freezes the LTSSM state machine at whenever a timeout occurs that would have caused the LTSSM state machine to exit to detect state. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware.
11	0x0 RO	**RSVD2:** Reserved
10:8	0x0 RW/P/L	**Initialization Mode (InitializationMode):** This field indicated the initialization mode of the link. • 000b: Normal Initialization • 001b: Initialization towards Loopback state • 010b: Tester Mode • 011b: Initialization towards Loopback.Compliance Master • 100b: Forced Entry to Compliance Master • 101b: Forced Entry to Compliance Slave • 110b: Initialization towards Compliance Receive • 111b: Reserved. This control bit or field requires a link re-initialization though the LTSSM Detect state before any action is taken by hardware. ***Note:*** Based on LKCON registers
7:3	0x0 RO	**RSVD3:** Reserved
2	0x0 RO	**Bypass Calibration (BypassCalib):** ***Note:*** This can change based on IO design.
1	0x0 RO	**RSVD4:** Reserved
0	0x0 RW/P	**Physical Layer Reset (PhyLayerReset):** This bit controls the reset assertion to the physical layer. Software is required to both set and clear this bit. ***Note:*** This bit is equivalent to the link disable bit in the link control register. PCIe logic should 'OR' this bit and the link disable bit.

48.2.160 IBSTTXLCTL—Offset 354h

REUT-PH-TDC

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 354h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/P	**Tx Data Lane Disable (TxDataLaneDisable):** This register field is used to selectively disable Tx lanes of the link. • Bit 0: Lane 0 disable • ... • Bit 15: lane 15 disable. It gates data from the REUT engine on to the lane. Disabled Lanes is not actually dead.

48.2.161 IBSTTDSTS—Offset 358h

REUT-PH-TDS

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 358h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RO/V	**Tx Data Lane Detection Status (TxLaneDetectStat):** This register field indicates that the Tx lanes did not detect a receiver termination upon existing Detect LTSSM state. • Bit 0: Lane 0 disable • ... • Bit 15: lane 15 disable.

48.2.162 IBSTPLLNSTS0—Offset 36Ch

REUT-PH-LSR0-1

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 36Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO/V	**Lane 7 Present State (Lane7PresState):** This field identifies the current state for lane 7 (or lane 15 for IBSTPLLNSTS1).
27:24	0x0 RO/V	**Lane 6 Present State (Lane6PresState):** This field identifies the current state for lane 6 (or lane 14 for IBSTPLLNSTS1).
23:20	0x0 RO/V	**Lane 5 Present State (Lane5PresState):** This field identifies the current state for lane 5 (or lane 13 for IBSTPLLNSTS1).
19:16	0x0 RO/V	**Lane 4 Present State (Lane4PresState):** This field identifies the current state for lane 4 (or lane 12 for IBSTPLLNSTS1).
15:12	0x0 RO/V	**Lane 3 Present State (Lane3PresState):** This field identifies the current state for lane 3 (or lane 11 for IBSTPLLNSTS1).
11:8	0x0 RO/V	**Lane 2 Present State (Lane2PresState):** This field identifies the current state for lane 2 (or lane 10 for IBSTPLLNSTS1).
7:4	0x0 RO/V	**Lane 1 Present State (Lane1PresState):** This field identifies the current state for lane 1 (or lane 9 for IBSTPLLNSTS1).
3:0	0x0 RO/V	**Lane 0 Present State (Lane0PresState):** This field identifies the current state for lane 0 (or lane 8 for IBSTPLLNSTS1).

48.2.163 IBSTPRECFG0—Offset 370h

REUT-PH-PRE0-1

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 370h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RO/V	**Pre Configuration Lane 7 ID (PreConfigLane7ID):** This field identifies the Pre-configuration Link ID for lane 7 (or lane 15 for IBSTPRECFG1).
27:24	0xf RO/V	**Pre Configuration Lane 6 ID (PreConfigLane6ID):** This field identifies the Pre-configuration Link ID for lane 6 (or lane 14 for IBSTPRECFG1).
23:20	0xf RO/V	**Pre Configuration Lane 5 ID (PreConfigLane5ID):** This field identifies the Pre-configuration Link ID for lane 5 (or lane 13 for IBSTPRECFG1).
19:16	0xf RO/V	**Pre Configuration Lane 4 ID (PreConfigLane4ID):** This field identifies the Pre-configuration Link ID for lane 4 (or lane 12 for IBSTPRECFG1).
15:12	0xf RO/V	**Pre Configuration Lane 3 ID (PreConfigLane3ID):** This field identifies the Pre-configuration Link ID for lane 3 (or lane 11 for IBSTPRECFG1).
11:8	0xf RO/V	**Pre Configuration Lane 2 ID (PreConfigLane2ID):** This field identifies the Pre-configuration Link ID for lane 2 (or lane 10 for IBSTPRECFG1).
7:4	0xf RO/V	**Pre Configuration Lane 1 ID (PreConfigLane1ID):** This field identifies the Pre-configuration Link ID for lane 1 (or lane 9for IBSTPRECFG1).
3:0	0xf RO/V	**Pre Configuration Lane 0 ID (PreConfigLane0ID):** This field identifies the Pre-configuration Link ID for lane 0 (or lane 8 for IBSTPRECFG1).

48.2.164 IBSTPOSTCFG0—Offset 374h

REUT-PH-POST0-1

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 374h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RO/V	**Post Configuration Lane 7 ID (PostConfigLane7ID):** This field identifies the Post-configuration Link ID for lane 7 (or lane 15 for IBSTPOSTCFG1).
27:24	0xf RO/V	**Post Configuration Lane 6 ID (PostConfigLane6ID):** This field identifies the Post-configuration Link ID for lane 6 (or lane 14 for IBSTPOSTCFG1).
23:20	0xf RO/V	**Post Configuration Lane 5 ID (PostConfigLane5ID):** This field identifies the Post-configuration Link ID for lane 5 (or lane 13 for IBSTPOSTCFG1).
19:16	0xf RO/V	**Post Configuration Lane 4 ID (PostConfigLane4ID):** This field identifies the Post-configuration Link ID for lane 4 (or lane 12 for IBSTPOSTCFG1).
15:12	0xf RO/V	**Post Configuration Lane 3 ID (PostConfigLane3ID):** This field identifies the Post-configuration Link ID for lane 3 (or lane 11 for IBSTPOSTCFG1).
11:8	0xf RO/V	**Post Configuration Lane 2 ID (PostConfigLane2ID):** This field identifies the Post-configuration Link ID for lane 2 (or lane 10 for IBSTPOSTCFG1).
7:4	0xf RO/V	**Post Configuration Lane 1 ID (PostConfigLane1ID):** This field identifies the Post-configuration Link ID for lane 1 (or lane 9 for IBSTPOSTCFG1).
3:0	0xf RO/V	**Post Configuration Lane 0 ID (PostConfigLane0ID):** This field identifies the Post-configuration Link ID for lane 0 (or lane 8 for IBSTPOSTCFG1).

48.2.165 IBSTPLLNSTS1—Offset 378h

REUT-PH-LSR0-1

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 378h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO/V	**Lane 7 Present State (Lane7PresState):** This field identifies the current state for lane 7 (or lane 15 for IBSTPLLNSTS1).
27:24	0x0 RO/V	**Lane 6 Present State (Lane6PresState):** This field identifies the current state for lane 6 (or lane 14 for IBSTPLLNSTS1).
23:20	0x0 RO/V	**Lane 5 Present State (Lane5PresState):** This field identifies the current state for lane 5 (or lane 13 for IBSTPLLNSTS1).
19:16	0x0 RO/V	**Lane 4 Present State (Lane4PresState):** This field identifies the current state for lane 4 (or lane 12 for IBSTPLLNSTS1).
15:12	0x0 RO/V	**Lane 3 Present State (Lane3PresState):** This field identifies the current state for lane 3 (or lane 11 for IBSTPLLNSTS1).
11:8	0x0 RO/V	**Lane 2 Present State (Lane2PresState):** This field identifies the current state for lane 2 (or lane 10 for IBSTPLLNSTS1).
7:4	0x0 RO/V	**Lane 1 Present State (Lane1PresState):** This field identifies the current state for lane 1 (or lane 9 for IBSTPLLNSTS1).
3:0	0x0 RO/V	**Lane 0 Present State (Lane0PresState):** This field identifies the current state for lane 0 (or lane 8 for IBSTPLLNSTS1).

48.2.166 IBSTPRECFG1—Offset 37Ch

REUT-PH-PRE0-1

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 37Ch

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RO/V	**Pre Configuration Lane 7 ID (PreConfigLane7ID):** This field identifies the Pre-configuration Link ID for lane 7 (or lane 15 for IBSTPRECFG1).
27:24	0xf RO/V	**Pre Configuration Lane 6 ID (PreConfigLane6ID):** This field identifies the Pre-configuration Link ID for lane 6 (or lane 14 for IBSTPRECFG1).
23:20	0xf RO/V	**Pre Configuration Lane 5 ID (PreConfigLane5ID):** This field identifies the Pre-configuration Link ID for lane 5 (or lane 13 for IBSTPRECFG1).
19:16	0xf RO/V	**Pre Configuration Lane 4 ID (PreConfigLane4ID):** This field identifies the Pre-configuration Link ID for lane 4 (or lane 12 for IBSTPRECFG1).
15:12	0xf RO/V	**Pre Configuration Lane 3 ID (PreConfigLane3ID):** This field identifies the Pre-configuration Link ID for lane 3 (or lane 11 for IBSTPRECFG1).
11:8	0xf RO/V	**Pre Configuration Lane 2 ID (PreConfigLane2ID):** This field identifies the Pre-configuration Link ID for lane 2 (or lane 10 for IBSTPRECFG1).
7:4	0xf RO/V	**Pre Configuration Lane 1 ID (PreConfigLane1ID):** This field identifies the Pre-configuration Link ID for lane 1 (or lane 9for IBSTPRECFG1).
3:0	0xf RO/V	**Pre Configuration Lane 0 ID (PreConfigLane0ID):** This field identifies the Pre-configuration Link ID for lane 0 (or lane 8 for IBSTPRECFG1).

48.2.167 IBSTPOSTCFG1—Offset 380h

REUT-PH-POST0-1

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 380h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RO/V	**Post Configuration Lane 7 ID (PostConfigLane7ID):** This field identifies the Post-configuration Link ID for lane 7 (or lane 15 for IBSTPOSTCFG1).
27:24	0xf RO/V	**Post Configuration Lane 6 ID (PostConfigLane6ID):** This field identifies the Post-configuration Link ID for lane 6 (or lane 14 for IBSTPOSTCFG1).
23:20	0xf RO/V	**Post Configuration Lane 5 ID (PostConfigLane5ID):** This field identifies the Post-configuration Link ID for lane 5 (or lane 13 for IBSTPOSTCFG1).
19:16	0xf RO/V	**Post Configuration Lane 4 ID (PostConfigLane4ID):** This field identifies the Post-configuration Link ID for lane 4 (or lane 12 for IBSTPOSTCFG1).
15:12	0xf RO/V	**Post Configuration Lane 3 ID (PostConfigLane3ID):** This field identifies the Post-configuration Link ID for lane 3 (or lane 11 for IBSTPOSTCFG1).
11:8	0xf RO/V	**Post Configuration Lane 2 ID (PostConfigLane2ID):** This field identifies the Post-configuration Link ID for lane 2 (or lane 10 for IBSTPOSTCFG1).
7:4	0xf RO/V	**Post Configuration Lane 1 ID (PostConfigLane1ID):** This field identifies the Post-configuration Link ID for lane 1 (or lane 9 for IBSTPOSTCFG1).
3:0	0xf RO/V	**Post Configuration Lane 0 ID (PostConfigLane0ID):** This field identifies the Post-configuration Link ID for lane 0 (or lane 8 for IBSTPOSTCFG1).

48.2.168 TLPCIECLKGCTL—Offset 8E0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8E0h

Default: 001Fh

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**DIDT Mode (DIDT):** This bit when set to 1b will ensure that all clock gating is staggered by the amount of time determined by the Stagger Timer field in this register. **Power Well:** PRST
14:9	0x0 RO	**RSVD0:** Reserved
8:0	0x1f RW	**Stagger Timer (ST):** This field indicates the number of clocks that the IP block must be wait before the clock can be disable process begins. **Power Well:** PRST

48.2.169 TLPCIECLKGCCTL—Offset 8E2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8E2h

Default: 0055h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7:6	0x1 RW	**Port Grant Count 3 (PGC3):** Reserved. **Power Well:** PRST
5:4	0x1 RW	**Port Grant Count 2 (PGC2):** Reserved. **Power Well:** PRST
3:2	0x1 RW	**Port Grant Count 1 (PGC1):** Reserved. **Power Well:** PRST
1:0	0x1 RW	**Port Grant Count 0 (PGC0):** Reserved. **Power Well:** PRST

48.2.170 PT0TXNCLKGCTL—Offset 8E4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8E4h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.171 PT1TXNCLKGCTL—Offset 8E6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8E6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.172 PT2TXNCLKGCTL—Offset 8E8h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8E8h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.173 PT3TXNCLKGCTL—Offset 8EAh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8EAh

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.174 XPTDEF2—Offset 8F8h

Lock Key bit is located in the Personality Lock Key Control Register ('PLKCTL.TLCL').

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 8F8h

Default: 00001D00h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**MSI Address Violation Status (MSIAVS):** MSI address violation check status that does not target 0xFEEx_xxxx while MSIAVCD is not being set. This is only valid for RPs usage.
30:19	0x0 RW/P/L	**Reserved ECO (RECO):** This field is reserved for ECO purpose.
18	0x0 RW/P/L	**Hold Retrain during Surprise Removal Disable (HRSRD):** For Surprise Removal, EIP RPs will not allow retrain to occur until the SLOTSTS.PDCS bit has been cleared by software for the removal event. This bit is to disable the above behavior and allow the retrain to occur. This field is only applicable to RPs and should be treated as reserved for other devices.
17	0x0 RW/P/L	**ECRC Malformed Error Precedence Disable (ECRCMFEPD):** This bit changes the error precedence if a TLP has both a ECRC error and is malform. • When this bit is set to 1, the packet will be logged as an ECRC error. • When set to 0, the packet will be logged as a malform TLP, which is compliant to the PCIe spec errata. Only the type of error logged is affected. If the TLP is malform, it will be dropped with no credit return. If there is only an ECRC error detected on a packet, it will be dropped and credits will be returned per PCI-SIG Errata.
16	0x0 RW/P/L	**MSI Address Violation Check Disable (MSIAVCD):** Disable MSI address violation check that does not target 0xFEEx_xxxx. This is only valid for RPs usage.
15	0x0 RW/P/L	**Force Downstream Relaxed Order (FORCERODN):** Forces all downstream completions to follow relaxed ordering rules. This allows downstream completions to pass downstream posted requests. Note that setting this bit breaks the producer consumer model when the data is in the address space below the port and the flag is in the address space outside the port, because the read of the flag will not push the data writes down the port. The belief is that usage model is not used.
14	0x0 RW/P/L	**Downstream Relaxed Order Disable (DNRODIS):** Disables the ability of downstream relaxed ordered completions from passing posted requests in the same direction.
13	0x0 RW/P/L	**Upstream Relaxed Order Disable (UPRODIS):** Disables the ability of upstream relaxed ordered completions from passing posted requests in the same direction.
12	0x1 RW/P/L	**IOSF tdparity check disable (TDPAR_CHK_DIS):** When set this bit disables the data parity check for incoming data into the IOSF Target block. The logic will ignore the data parity bit and will operate as though the parity bit did not exist. No errors will be logged and good DW based parity will be written into the data queue.
11	0x1 RW/P/L	**IOSF tcparity check disable (TCPAR_CHK_DIS):** When set this bit disables the command parity check for incoming commands into the IOSF Target block. The logic will ignore the command parity bit and will operate as though the parity bit did not exist. No errors will be logged and good DW based parity will be written into the header queue.
10	0x1 RW/P/L	**MCTP Message Bus Number Check Enable (MMBNCE):** When set, if the Requester ID bus number of an MCTP message request received on the PCIe link does not fall within the range between SCBN and SBBN, the MCTP message will be silently discarded.
9	0x0 RW/P/L	**Completion credit advertisement enable (CPLCDT_EN):** Endpoints are required to advertise infinite completion credits. Setting this defeature bit breaks that rule and enables the advertisement of non-infinite completion credits and flow control updates for completion credits. This is only valid for project specific

Bit Range	Default & Access	Field Name (ID): Description
8	0x1 RW/P/L	**Enable Virtual Port IDs (EVPID):** • 1: Enables SB Virtual Port ID mode with allocated VPIDs which is associated with ports for all the egress INTx and LTR messages based on project specific. We will assign (N-1) virtual sideband PortID's to associate with the physical PortID which is port 0. The physical one is the same one as being assigned by the router as we have now, and would be used for all non-INTx messages and INTx messages from port 0. However, the VPIDs would be used for INTx messages routing from port(N-1:1), respectively. This allows all INTx from N ports to be forwarded to the ILB accordingly, so ILB can differentiate the source of the INTx message. • 0: Normal operation with single SB Port ID per cluster for INTx delivery. This is only valid for project specific with multi root ports.
7	0x0 RW/P/L	**Enable Receive Completion Ordering (ERCO):** The default ordering is to allow received completions to pass received posted requests to avoid receiver overflow conditions if posted requests cannot be processed. Setting this bit will enable PCI Express ordering for completions, preventing completions from passing posted requests. This is only valid for project specific
6	0x0 RW/P/L	**Enable MSI Generation Override (MSIGENOV):** • 1: Enables Root Port MSI generation override even if PCICMD.BME = 0 for the root port device as required by PCI Express specification. • 0: Normal operation for Root Port behavior. If PCICMD.BME = 0, the root port will not generate a MSI. This is only valid for project specific.
5	0x0 RW/P/L	**Completion Combining Disable (CPLCOMBINE_D):** When a larger read request is split into smaller read requests, the completions for the small requests may be opportunistically combined into larger completions to enable higher bandwidth and link utilization, as long as packet formation rules are not violated. This bit disables the port from combining completions. This is only valid for project specific .
4	0x0 RW/P/L	**Config Retry Disable (CRD):** Setting this bit disables the re-issuing of a configuration request if the request is completed with a configuration retry status (CRS). The completion with CRS will be returned to the requestor.
3	0x0 RW/P/L	**Optional Unexpected Completion Check Disable (UCCHKD):** Setting this bit disables some optional unexpected checks on completions. Specifically, it disables the checking on the byte count and lower address fields.
2	0x0 RW/P/L	**MCTP Disable Bus Check (MCTPDBC):** Setting this bit will disable the Bus 0 check for all MCTP VDM Type1 messages. The check is enabled by default as following: • Upstream - ReqBus =/= 0 • Downstream - TgtBus =/= 0
1	0x0 RW/P/L	**MSI-X Single Message Vector (MSIXSMSGV):** This bit when set, causes only a single MSI-X vector to be generated if MSI-X is enabled. This bit affects the default value of the MSI-X Table Size field
0	0x0 RW/P/L	**Global Stop Disable (GBLSTOPD):** When the design detects an uncorrectable internal error, a stop signal in the design asserts, blocking the processing of transactions in both directions in the transaction layer. Setting this bit, disables the stop mechanism, allowing the transactions to proceed as if no error occurred.

48.2.175 PMIDLTMR—Offset 948h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 948h

Default: 00000306h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**ENPMTIMEOUT:** A number of pci-e cards have a particular erratum which causes them to send spurious PM requests. When such spurious behavior happens, the northbridge starts the pm negotiation from its side and results in a system failure. This bit when set enables an exit to recovery if the power management request did not terminate within 64-96us.
30:28	0x0 RW/P	**PMDLLPCNT:** Only useful for upstream devices. Do not take action based on seeing ASPM/PM DLLPs until 'PMDLLPCNT' DLLPs have been observed. When set to 0, a single ASPM/PM DLLP will cause a response. Used to work around broken devices that fail to flush all ASPM/PM DLLPs before entering the low power state and send spurious DLLPs upon return to L0 state.
27:12	0x0 RO	**RSVD0:** Reserved
11:8	0x3 RW/P	**L0s_IDLE_TIMER:** Indicates the amount of idle time in [us], as defined in the PCI-E spec, after which a tx-L0s transition will be initiated. Timers have an accuracy of -1/+0us. A setting of 0 will disable tx-L0s transitions.
7:5	0x0 RO	**RSVD1:** Reserved
4:0	0x6 RW/P	**L1_IDLE_TIMER:** Only used for Downstream devices. Not useful for an RC. Downstream device will initiate ASPM L1 request after the specified number of us of idle time. For RH can be used as a scratch register. A setting of 0 can be used as a non-specd way of disabling ASPM L1.

48.2.176 LLRBSIZE—Offset 98Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 98Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**RSVD0:** Reserved
26:16	0x0 RO/V	**LUT_SIZE:** Number of physical entries in LUT (does not account for RTRYCTL.UNUSABLE_MAP_ENTRIES). Units are 'TLPs'.
15:11	0x0 RO	**RSVD1:** Reserved
10:0	0x0 RO/V	**LLRB_SIZE:** Number of symbol times of data in the LLRB (does not account for RTRYCTL.UNUSABLE_LLRB_ENTRIES). Units are symbol times.

48.2.177 FRMERRMSK—Offset 99Ch

These errors in FRMERRMSK, STS only apply to Gen1/Gen2.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 99Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:10	0x0 RO	**RSVD0:** Reserved
9	0x0 RW/P	**DUMP_IN_DLLP_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
8	0x0 RW/P	**DUMP_IN_TLP_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
7	0x0 RW/P	**ILL_STP_END_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
6	0x0 RW/P	**SDP_FRQ_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
5	0x0 RW/P	**STP_FRQ_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
4	0x0 RW/P	**GAP_SDP_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
3	0x0 RW/P	**GAP_STP_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
2	0x0 RW/P	**IDL_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
1	0x0 RW/P	**PAD_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.
0	0x0 RW/P	**DW1_ERR_MSK:** This bit masks reporting of the corresponding errors in the FRMERRSTS register.

48.2.178 FRMERRSTS—Offset 99Eh

These errors in FRMERRMSK, STS only apply to Gen1/Gen2.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 99Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:10	0x0 RO	**RSVD0:** Reserved
9	0x0 RW/1C/V/P	**DUMP_IN_DLLP_ERR:** Preprocessor block detected error in DLLP framing.
8	0x0 RW/1C/V/P	**DUMP_IN_TLP_ERR:** Preprocessor block detected error in TLP framing.
7	0x0 RW/1C/V/P	**ILL_STP_END_ERR:** STP/SDP/END/EDB seen in illegal lanes.
6	0x0 RW/1C/V/P	**SDP_FRQ_ERR:** SDP seen too frequently in otherwise legal lanes.
5	0x0 RW/1C/V/P	**STP_FRQ_ERR:** STP seen too frequently in otherwise legal lanes.
4	0x0 RW/1C/V/P	**GAP_SDP_ERR:** Framing error: Gap seen between first packet and DLLP.
3	0x0 RW/1C/V/P	**GAP_STP_ERR:** Framing error: Gap seen between first packet and TLP.
2	0x0 RW/1C/V/P	**IDL_ERR:** Framing error: Logic idles not seen where expected.
1	0x0 RW/1C/V/P	**PAD_ERR:** Framing error: PADs not seen where expected.
0	0x0 RW/1C/V/P	**DW1_ERR:** Framing error in 1st DW of a TLP/DLLP.

48.2.179 LLPCIECLKGCTL—Offset 9E0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9E0h

Default: 001Fh

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**DIDT Mode (DIDT):** This bit when set to 1b will ensure that all clock gating is staggered by the amount of time determined by the Stagger Timer field in this register. **Power Well:** PRST
14:9	0x0 RO	**RSVD0:** Reserved
8:0	0x1f RW	**Stagger Timer (ST):** This field indicates the number of clocks that the IP block must be wait before the clock can be disable process begins. **Power Well:** PRST

48.2.180 LLPCIECLKGCCTL—Offset 9E2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9E2h

Default: 0055h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7:6	0x1 RW	**Port Grant Count 3 (PGC3):** Reserved. **Power Well:** PRST
5:4	0x1 RW	**Port Grant Count 2 (PGC2):** Reserved. **Power Well:** PRST
3:2	0x1 RW	**Port Grant Count 1 (PGC1):** Reserved. **Power Well:** PRST
1:0	0x1 RW	**Port Grant Count 0 (PGC0):** Reserved. **Power Well:** PRST

48.2.181 PT0LNKCLKGCTL—Offset 9E4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9E4h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.182 PT1LNKCLKGCTL—Offset 9E6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9E6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.183 PT2LNKCLKGCTL—Offset 9E8h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9E8h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.184 PT3LNKCLKGCTL—Offset 9EAh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9EAh

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.185 CFGPCIECLKGCTL—Offset 9ECh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9ECh

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.186 CFGPCIECLKGCCTL—Offset 9EEh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + 9EEh

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:2	0x0 RO	**RSVD0:** Reserved
1:0	0x1 RW	**Configuration Grant Count (CGC):** Note: The grant count needs to be greater than 0 for the arbitration to function. A grant count of 0 means no resources available and the requester will never be serviced. **Power Well:** PRST

48.2.187 LTSSMSMSTS—Offset A68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO/V	**LTSSMSTATEMAIN:** LTSSM State Main.
27:24	0x0 RO/V	**LTSSMSTATESUB:** LTSSM State Sub State.
23	0x0 RO	**RSVD0:** Reserved
22:20	0x0 RO/V	**LTSSMRXL0SSM:** LTSSM RxL0s SM
19	0x0 RO	**RSVD1:** Reserved
18:16	0x0 RO/V	**LTSSMRECEQSM:** LTSSM Recovery Equalization SM
15:13	0x0 RO	**RSVD2:** Reserved
12:5	0x0 RO/V	**LNKNUM:** Link Number
4:3	0x0 RO/V	**RCVRATESUP:** Received Rate Support.
2	0x0 RO/V	**LNKREVERSED:** Link Reversed
1	0x0 RO/V	**DLACTIVE:** DL_Active
0	0x0 RO/V	**LTSSMLNKUP:** LTSSM Link UP.

48.2.188 LTSSMLNSTS0—Offset A70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO/V	**Rcvr SM Lane 7 (RCVRSMLN7):** Reserved.
27:24	0x0 RO/V	**Rcvr SM Lane 6 (RCVRSMLN6):** Reserved.
23:20	0x0 RO/V	**Rcvr SM Lane 5 (RCVRSMLN5):** Reserved.
19:16	0x0 RO/V	**Rcvr SM Lane 4 (RCVRSMLN4):** Reserved.
15:12	0x0 RO/V	**Rcvr SM Lane 3 (RCVRSMLN3):** Reserved.
11:8	0x0 RO/V	**Rcvr SM Lane 2 (RCVRSMLN2):** Reserved.
7:4	0x0 RO/V	**Rcvr SM Lane 1 (RCVRSMLN1):** Reserved.
3:0	0x0 RO/V	**Rcvr SM Lane 0 (RCVRSMLN0):** Reserved.

48.2.189 LTSSMSTATELOG0—Offset A80h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A80h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**LAST8MAIN:** • [3:0] present ltssm (or last if stopped) (newest state) • [7:4] prior state • [11:8] [15:12] [19:16] [23:20] [27:24] [31:28] oldest state logged

48.2.190 LTSSMSTATELOG1—Offset A84h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**LAST8SUB:** • [3:0] present ltssm (or last if stopped) (newest state) • [7:4] prior state • [11:8] [15:12] [19:16] [23:20] [27:24] [31:28] oldest state logged

48.2.191 LTSSMSTATELOG2—Offset A88h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A88h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**LAST8RXL0S:** • [3:0] present ltssm (or last if stopped) (newest state) • [7:4] prior state • [11:8] [15:12] [19:16] [23:20] [27:24] [31:28] oldest state logged

48.2.192 LTSSMSTATELOGCTL—Offset A8Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A8Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**RSVD0:** Reserved
8:1	0x0 RW/P	**STOP:** Match register to freeze logging [7:4] LTSSM sub state to match [3:0] LTSSM main state to match
0	0x0 RW/P	**START:** 0--)1 transition clears log registers and restarts logging

48.2.193 LTLNERRCTRL—Offset A94h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A94h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7:4	0x0 RW/P	**SEL2:** select what state transition to log in LTLNERRLOG.STS2
3:0	0x0 RW/P	**SEL1:** select what state transition to log in LTLNERRLOG.STS1

48.2.194 LTLNERRSTS—Offset A96h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A96h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:2	0x0 RO	**RSVD0:** Reserved
1	0x0 RW/1C/V/P	**CAPTURED2:** State transition seen and error results captured in LTLNERRLOG.STS2
0	0x0 RW/1C/V/P	**CAPTURED1:** State transition seen and error results captured in LTLNERRLOG.STS1

48.2.195 LTLNERRLOG—Offset A98h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + A98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RO/V/P	**Lane 7 Error for STS2 (L7ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
22	0x0 RO/V/P	**Lane 6 Error for STS2 (L6ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
21	0x0 RO/V/P	**Lane 5 Error for STS2 (L5ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL12
20	0x0 RO/V/P	**Lane 4 Error for STS2 (L4ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
19	0x0 RO/V/P	**Lane 3 Error for STS2 (L3ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
18	0x0 RO/V/P	**Lane 2 Error for STS2 (L2ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
17	0x0 RO/V/P	**Lane 1 Error for STS2 (L1ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
16	0x0 RO/V/P	**Lane 0 Error for STS2 (L0ERRSTS2):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL2
15:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RO/V/P	**Lane 7 Error for STS1 (L7ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
6	0x0 RO/V/P	**Lane 6 Error for STS1 (L6ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
5	0x0 RO/V/P	**Lane 5 Error for STS1 (L5ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
4	0x0 RO/V/P	**Lane 4 Error for STS1 (L4ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
3	0x0 RO/V/P	**Lane 3 Error for STS1 (L3ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
2	0x0 RO/V/P	**Lane 2 Error for STS1 (L2ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
1	0x0 RO/V/P	**Lane 1 Error for STS1 (L1ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1
0	0x0 RO/V/P	**Lane 0 Error for STS1 (L0ERRSTS1):** Per lane vector, 1 indicates bad lane on selected state transition chosen by LTLNERRCTRL.SEL1

48.2.196 UPCFGCSR—Offset AB8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AB8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x0 RO/V	**RCVDUPCFGCAP:** Received up configure support by link partner.
21:16	0x0 RO/V	**ILW:** Initial Link Width (maximum width to up configure to). ILW format is the same as MLW.
15:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/P	**UPCFGCAPEN:** This bit when set to 1 enables advertising dynamic width support in the training sequences. When this bit is set 1 from 0, the link will move through Recovery to Config advertising upconfigure capability. It will also ignore the settings in fields TLW and UPCFGEN at the time the bit is set.
6:1	0x0 RW/P	**TLW:** This is the target link width used when mastering a dynamic width change. If TLW is greater than the initial trained link width when LinkUp goes to 0--)1, then the initial link width is chosen as a cap.
0	0x0 RW/V	**UPCFGEN:** When UPCFGCAPEN is set to 1 and this bit is set to 1, a dynamic width change is initiated if the TLW field is not equal to the current link width (if other end advertises support for it), this bit is cleared by hardware after making one attempt to change width. On error, this bit will be cleared and TLW != NLW. If TLW==NLW and this bit is set, hardware will clear it without entering Recovery/Config.

48.2.197 SOSCTL—Offset AC8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AC8h

Default: 00025A4Eh

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22	0x0 RW/V/P	**SRISEN:** This field should be set prior to link training and may be loaded via fuse or strap. When enabled, the high frequency SOS interval is defined in SRISSOSINT and the low frequency SOS interval is defined in SOSINTERVAL.
21:11	0x4b RW/P	**SRISSOSINT:** SOS interval used in SRIS mode (high frequency interval). Same interval definition as the SOSINTERVAL field.
10:0	0x24e RW/P	**SOSINTERVAL:** Symbol between SOS insertions For 2.5GTs/ and 5GT/s modes = val * 2 For 8GT/s mode = val * 8

48.2.198 G3SOSERRSTS—Offset ACCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + ACCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V/P	**LFSRERR:** 8GT/s SOS block LFSR state mis-compare.
15:0	0x0 RW/1C/V/P	**PARERR:** 8GT/s SOS block parity error.

48.2.199 PLPCIECLKGCTL—Offset AE0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AE0h

Default: 001Fh

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**DIDT Mode (DIDT):** This bit when set to 1b will ensure that all clock gating is staggered by the amount of time determined by the Stagger Timer field in this register. **Power Well:** PRST
14:9	0x0 RO	**RSVD0:** Reserved
8:0	0x1f RW	**Stagger Timer (ST):** This field indicates the number of clocks that the IP block must be wait before the clock can be disable process begins. **Power Well:** PRST

48.2.200 PLPCIECLKGCCTL—Offset AE2h

The grant count needs to be greater than 0 for the arbitration to function. A grant count of 0 means no resources available and the requester will never be serviced.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AE2h

Default: 0055h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7:6	0x1 RW	**Port Grant Count 3 (PGC3):** This field is valid only for multi-port configuration. **Power Well:** PRST
5:4	0x1 RW	**Port Grant Count 2 (PGC2):** This field is valid only for multi-port configuration. **Power Well:** PRST
3:2	0x1 RW	**Port Grant Count 1 (PGC1):** This field is valid only for multi-port configuration. **Power Well:** PRST
1:0	0x1 RW	**Port Grant Count 0 (PGC0):** Reserved. **Power Well:** PRST

48.2.201 PT0PHYCLKGCTL—Offset AE4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AE4h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.202 PT1PHYCLKGCTL—Offset AE6h

This register is valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AE6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.203 PT2PHYCLKGCTL—Offset AE8h

This register is valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AE8h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.204 PT3PHYCLKGCTL—Offset AEAh

This register is valid only for multi-port configuration.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + AEAh

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**Idle Clock Gating Enable (ICGE):** This bit when set enables clock gating to occur when the IP block is idle longer then the Idle Clock Timer. **Power Well:** PRST
14:8	0x0 RO	**RSVD0:** Reserved
7:0	0x10 RW	**Idle Clock Timer (ICT):** This field indicates the number of clocks that the IP block must be idle before the clock disable process begins. 16 (default value) is the minimum number of clocks recommended. **Power Well:** PRST

48.2.205 LTLGCAP—Offset B00h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B00h

Default: 36000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x3600 RO	**BAROFFSET:** Memory bar offset for ram entry 0
15:4	0x0 RO/V	**RAMSIZE:** Number of total ram entries.
3	0x0 RO	**RSVD0:** Reserved
2:0	0x0 RO/V	**NUMSUBLOG:** Number of sub-loggers supported.

48.2.206 LTLGCTRL—Offset B04h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B04h

Default: 00321000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**RSVD0:** Reserved
22:20	0x3 RW/P	**SUBLOG3PT:** Port to assign to sub-logger 3.
19	0x0 RO	**RSVD1:** Reserved
18:16	0x2 RW/P	**SUBLOG2PT:** Port to assign to sub-logger 2.
15	0x0 RO	**RSVD2:** Reserved
14:12	0x1 RW/P	**SUBLOG1PT:** Port to assign to sub-logger 1.
11	0x0 RO	**RSVD3:** Reserved
10:8	0x0 RW/P	**SUBLOG0PT:** Port to assign to sub-logger 0.
7:5	0x0 RO	**RSVD4:** Reserved
4	0x0 RW/V/P	**CLEARALL:** Clear and restart all sub-loggers.
3	0x0 RO	**RSVD5:** Reserved
2:0	0x0 RW/P	**SPLITCTL:** Control of splitting logger if 1 sub log, ignored if 2 sub logs, only bit 0 used [0] = 1, sublog0 owns full ram [0] = 0, sublog0/1 split ram if 4 sub-logs • 1-- = sublog0 owns full ram • 011 = sublog0/2 split ram in half • 001 = sublog0 gets half, sublog2/3 get a quarter each • 010 = sublog0/1 get a quarter each, sublog2 gets half • 000 = sublog0/1/2/3 get a quarter each

48.2.207 LTLGSTART0—Offset B08h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B08h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RW/P	**STARTTRGMSK:** If XSTOPTRGEN = 0, and any bit is set to 1, it will make that corresponding start trigger bit a don't care (always match). If XSTOPTRGEN = 1, bits [19:18] are used and [31:20] reserved. Here is the definition for a and b which is the OR mask to dmona/b. a = bit[18] | dmona b = bit[19] | dmonb
17:4	0x0 RW/P	**STARTTRG:** If XSTOPTRGEN = 0, start trigger value, used in conjunction with the start trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state. If XSTOPTRGEN = 1, bits [6:4] are used, [17:7] reserved. Here is the definition of the external trigger event using the mask and dmona/b values • 000 - trigger (= (!a and !b) • 001 - trigger (= (a and !b) • 010 - trigger (= (!a and b) • 011 - trigger (= (a and b) • 100 - trigger (= (!a | !b) • 101 - trigger (= (a | !b) • 110 - trigger (= (!a | b) • 111 - trigger (= (a | b) a = bit[18] | dmona b = bit[19] | dmonb
3	0x0 RW/P	**STARTTRGEN:** If set, logging starts when the start trigger field and mask match the current LTSSM state/arc
2	0x0 RW/1C/V/P	**STARTTRIGGERED:** If 1, the start trigger event was hit.
1	0x0 RO	**RSVD0:** Reserved
0	0x1 RW/V/P	**START:** Enable logging. 0--)1 transition will clear log data If using the stop trigger, this bit will clear if the stop trigger event occurs. LTLGSTART[3:0] is based on one per sub-logger.

48.2.208 LTLGSTART1—Offset B0Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B0Ch

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RW/P	**STARTTRGMSK:** • If XSTOPTRGEN = 0, and any bit is set to 1, it will make that corresponding start trigger bit a don't care (always match). • If XSTOPTRGEN = 1, bits [19:18] are used and [31:20] reserved. Here is the definition for a and b which is the OR mask to dmona/b. a = bit[18] | dmona b = bit[19] | dmonb
17:4	0x0 RW/P	**STARTTRG:** If XSTOPTRGEN = 0, start trigger value, used in conjunction with the start trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state If XSTOPTRGEN = 1, bits [6:4] are used, [17:7] reserved. Here is the definition of the external trigger event using the mask and dmona/b values • 000 - trigger (= (!a and !b) • 001 - trigger (= (a and !b) • 010 - trigger (= (!a and b) • 011 - trigger (= (a and b) • 100 - trigger (= (!a | !b) • 101 - trigger (= (a | !b) • 110 - trigger (= (!a | b) • 111 - trigger (= (a | b) a = bit[18] | dmona b = bit[19] | dmonb
3	0x0 RW/P	**STARTTRGEN:** If set, logging starts when the start trigger field and mask match the current LTSSM state/arc
2	0x0 RW/1C/V/P	**STARTTRIGGERED:** If 1, the start trigger event was hit.
1	0x0 RO	**RSVD0:** Reserved
0	0x1 RW/V/P	**START:** Enable logging. 0--)1 transition will clear log data If using the stop trigger, this bit will clear if the stop trigger event occurs. LTLGSTART[3:0] is based on one per sub-logger.

48.2.209 LTLGSTART2—Offset B10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B10h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RW/P	**STARTTRGMSK:** • If XSTOPTRGEN = 0, and any bit is set to 1, it will make that corresponding start trigger bit a don't care (always match). • If XSTOPTRGEN = 1, bits [19:18] are used and [31:20] reserved. Here is the definition for a and b which is the OR mask to dmona/b. a = bit[18] | dmona b = bit[19] | dmonb
17:4	0x0 RW/P	**STARTTRG:** If XSTOPTRGEN = 0, start trigger value, used in conjunction with the start trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state If XSTOPTRGEN = 1, bits [6:4] are used, [17:7] reserved. Here is the definition of the external trigger event using the mask and dmona/b values • 000 - trigger (= (!a and !b) • 001 - trigger (= (a and !b) • 010 - trigger (= (!a and b) • 011 - trigger (= (a and b) • 100 - trigger (= (!a | !b) • 101 - trigger (= (a | !b) • 110 - trigger (= (!a | b) • 111 - trigger (= (a | b) a = bit[18] | dmona b = bit[19] | dmonb
3	0x0 RW/P	**STARTTRGEN:** If set, logging starts when the start trigger field and mask match the current LTSSM state/arc
2	0x0 RW/1C/V/P	**STARTTRIGGERED:** If 1, the start trigger event was hit.
1	0x0 RO	**RSVD0:** Reserved
0	0x1 RW/V/P	**START:** Enable logging. 0--)1 transition will clear log data If using the stop trigger, this bit will clear if the stop trigger event occurs. LTLGSTART[3:0] is based on one per sub-logger.

48.2.210 LTLGSTART3—Offset B14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B14h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RW/P	**STARTTRGMSK:** • If XSTOPTRGEN = 0, and any bit is set to 1, it will make that corresponding start trigger bit a don't care (always match). • If XSTOPTRGEN = 1, bits [19:18] are used and [31:20] reserved. Here is the definition for a and b which is the OR mask to dmona/b. a = bit[18] | dmona b = bit[19] | dmonb
17:4	0x0 RW/P	**STARTTRG:** If XSTOPTRGEN = 0, start trigger value, used in conjunction with the start trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state If XSTOPTRGEN = 1, bits [6:4] are used, [17:7] reserved. Here is the definition of the external trigger event using the mask and dmona/b values • 000 - trigger (= (!a and !b) • 001 - trigger (= (a and !b) • 010 - trigger (= (!a and b) • 011 - trigger (= (a and b) • 100 - trigger (= (!a | !b) • 101 - trigger (= (a | !b) • 110 - trigger (= (!a | b) • 111 - trigger (= (a | b) a = bit[18] | dmona b = bit[19] | dmonb
3	0x0 RW/P	**STARTTRGEN:** If set, logging starts when the start trigger field and mask match the current LTSSM state/arc
2	0x0 RW/1C/V/P	**STARTTRIGGERED:** If 1, the start trigger event was hit.
1	0x0 RO	**RSVD0:** Reserved
0	0x1 RW/V/P	**START:** Enable logging. 0--)1 transition will clear log data If using the stop trigger, this bit will clear if the stop trigger event occurs. LTLGSTART[3:0] is based on one per sub-logger.

48.2.211 LTLGSTP0—Offset B18h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B18h

Default: 1E000009h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30	0x0 RW/1C/V/P	**XTRIGGERED:** If 1, external stop trigger event occurred.
29	0x0 RW/P	**XSTOPTRGEN:** Use external trigger event to stop logging, see LTLGCTL.STARTTRG and STARTTRGMSK for configuration details. Enabling this does not disable the state match stop event and it does disable the state match start event (acts as if STARTTRGEN=0).
28:15	0x3c00 RW/P	**STOPTRGMSK:** if any bit is set to 1, it will make that corresponding stopt trigger bit a don't care (always match)
14:1	0x4 RW/P	**STOPTRG:** Stop trigger value, used in conjunction with the stop trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state
0	0x1 RW/P	**STOPTRGEN:** If set, logging stops when the stop trigger field and mask match the current LTSSM state/arc. LTLGSTP[3:0] is based on one per sub-logger.

48.2.212 LTLGSTP1—Offset B1Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B1Ch

Default: 1E000009h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30	0x0 RW/1C/V/P	**XTRIGGERED:** If 1, external stop trigger event occurred.
29	0x0 RW/P	**XSTOPTRGEN:** Use external trigger event to stop logging, see LTLGCTL.STARTTRG and STARTTRGMSK for configuration details. Enabling this does not disable the state match stop event and it does disable the state match start event (acts as if STARTTRGEN=0).
28:15	0x3c00 RW/P	**STOPTRGMSK:** if any bit is set to 1, it will make that corresponding stop trigger bit a don't care (always match)
14:1	0x4 RW/P	**STOPTRG:** Stop trigger value, used in conjunction with the stop trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state
0	0x1 RW/P	**STOPTRGEN:** If set, logging stops when the stop trigger field and mask match the current LTSSM state/arc. LTLGSTP[3:0] is based on one per sub-logger.

48.2.213 LTLGSTP2—Offset B20h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B20h

Default: 1E000009h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30	0x0 RW/1C/V/P	**XTRIGGERED:** If 1, external stop trigger event occurred.
29	0x0 RW/P	**XSTOPTRGEN:** Use external trigger event to stop logging, see LTLGCTL.STARTTRG and STARTTRGMSK for configuration details. Enabling this does not disable the state match stop event and it does disable the state match start event (acts as if STARTTRGEN=0).
28:15	0x3c00 RW/P	**STOPTRGMSK:** if any bit is set to 1, it will make that corresponding stopt trigger bit a don't care (always match)
14:1	0x4 RW/P	**STOPTRG:** Stop trigger value, used in conjunction with the stop trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state
0	0x1 RW/P	**STOPTRGEN:** If set, logging stops when the stop trigger field and mask match the current LTSSM state/arc. LTLGSTP[3:0] is based on one per sub-logger.

48.2.214 LTLGSTP3—Offset B24h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B24h

Default: 1E000009h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30	0x0 RW/1C/V/P	**XTRIGGERED:** If 1, external stop trigger event occurred.
29	0x0 RW/P	**XSTOPTRGEN:** Use external trigger event to stop logging, see LTLGCTL.STARTTRG and STARTTRGMSK for configuration details. Enabling this does not disable the state match stop event and it does disable the state match start event (acts as if STARTTRGEN=0).
28:15	0x3c00 RW/P	**STOPTRGMSK:** if any bit is set to 1, it will make that corresponding stop trigger bit a don't care (always match)
14:1	0x4 RW/P	**STOPTRG:** Stop trigger value, used in conjunction with the stop trigger mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state
0	0x1 RW/P	**STOPTRGEN:** If set, logging stops when the stop trigger field and mask match the current LTSSM state/arc. LTLGSTP[3:0] is based on one per sub-logger.

48.2.215 LTLGTMEV0—Offset B28h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RW/P	**EVLVL:** • 1: Event should be a level signal (high as long as compare condition is true) • 0: Event should be a pulse
22:6	0x0 RW/P	**COUNT:** The time value to compare with. The value is in units defined by the UNIT field.
5:3	0x0 RW/P	**CMP:** • 00 = compare to equal the time value • 01 = compare to greater than the time value • 10 = compare to less than the time value • 11 = reserved
2	0x0 RW/P	**UNIT:** • 1 = 256cc • 0 = 1cc Where cc is 1 pclk period and the user needs to be cognizant of designs that utilize variable (rate based) pclk.
1	0x0 RW/P	**SMEGC:** Select which state matching register to use for the state matching portion. The register must belong to the port set in the start register.
0	0x0 RW/P	**ENABLE:** Enable timer event using port defined in the start register. LTLGMEV[3:0] is based on one per sub-logger.

48.2.216 LTLGTMEV1—Offset B2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RW/P	**EVLVL:** • 1: Event should be a level signal (high as long as compare condition is true) • 0: Event should be a pulse
22:6	0x0 RW/P	**COUNT:** The time value to compare with. The value is in units defined by the UNIT field.
5:3	0x0 RW/P	**CMP:** • 00 = compare to equal the time value • 01 = compare to greater than the time value • 10 = compare to less than the time value • 11 = reserved
2	0x0 RW/P	**UNIT:** • 1 = 256cc • 0 = 1cc Where cc is 1 pclk period and the user needs to be cognizant of designs that utilize variable (rate based) pclk.
1	0x0 RW/P	**SMEGC:** Select which state matching register to use for the state matching portion. The register must belong to the port set in the start register.
0	0x0 RW/P	**ENABLE:** Enable timer event using port defined in the start register. LTLGMEV[3:0] is based on one per sub-logger.

48.2.217 LTLGTMEV2—Offset B30h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RW/P	**EVLVL:** • 1: Event should be a level signal (high as long as compare condition is true) • 0: Event should be a pulse
22:6	0x0 RW/P	**COUNT:** The time value to compare with. The value is in units defined by the UNIT field.
5:3	0x0 RW/P	**CMP:** • 00 = compare to equal the time value • 01 = compare to greater than the time value • 10 = compare to less than the time value • 11 = reserved
2	0x0 RW/P	**UNIT:** • 1 = 256cc • 0 = 1cc Where cc is 1 pclk period and the user needs to be cognizant of designs that utilize variable (rate based) pclk.
1	0x0 RW/P	**SMEGC:** Select which state matching register to use for the state matching portion. The register must belong to the port set in the start register.
0	0x0 RW/P	**ENABLE:** Enable timer event using port defined in the start register. LTLGMEV[3:0] is based on one per sub-logger.

48.2.218 LTLGTMEV3—Offset B34h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B34h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RW/P	**EVLVL:** • 1: Event should be a level signal (high as long as compare condition is true) • 0: Event should be a pulse
22:6	0x0 RW/P	**COUNT:** The time value to compare with. The value is in units defined by the UNIT field.
5:3	0x0 RW/P	**CMP:** • 00 = compare to equal the time value • 01 = compare to greater than the time value • 10 = compare to less than the time value • 11 = reserved
2	0x0 RW/P	**UNIT:** 1 = 256cc 0 = 1cc Where cc is 1 pclk period and the user needs to be cognizant of designs that utilize variable (rate based) pclk.
1	0x0 RW/P	**SMEGC:** Select which state matching register to use for the state matching portion. The register must belong to the port set in the start register.
0	0x0 RW/P	**ENABLE:** Enable timer event using port defined in the start register. LTLGMEV[3:0] is based on one per sub-logger.

48.2.219 LTLGRDCT—Offset B40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**RSVD0:** Reserved
17:16	0x0 RW/P	**LOGSEL:** Select which sub-logger to read.
15	0x0 RW/P	**AUTOINC:** • 1: Every time a read to LTLGRES happens, the read index increment automatically • 0: manual movement of the read index is required
14:6	0x0 RO	**RSVD1:** Reserved
5:0	0x0 RW/V/P	**RDINDEX:** The value in this field will point the LTLGRES register to a particular log entry. 0 is the latest entry 63 is oldest entry

48.2.220 LTLGRES—Offset B44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B44h

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO/V/P	**ENTRY:** [31] Time granularity bit • 1=512ns • 0=2ns Switch between modes is done when [30:14] increments past 1FFFFh [30:14] time unit count see bit 31 for unit definition [13:10] State exit arc • 0=state not exited • 1..15=see state specific map [9:8] RxL0s State [7:4] LTSSM Main state [3:0] LTSSM Sub state

48.2.221 LTLGSMEV0—Offset B48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30:29	0x0 RO	**RSVD0:** Reserved
28:15	0x0 RW/P	**MASK:** if any bit is set to 1, it will make that corresponding trigger bit a don't care (always match)
14:1	0x0 RW/P	**VALUE:** trigger value, used in conjunction with the mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state
0	0x0 RW/P	**ENABLE:** Enable the trigger on match

48.2.222 LTLGSMEV1—Offset B4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V/P	**TRIGGERED:** If 1, the trigger event was hit.
30:29	0x0 RO	**RSVD0:** Reserved
28:15	0x0 RW/P	**MASK:** if any bit is set to 1, it will make that corresponding trigger bit a don't care (always match)
14:1	0x0 RW/P	**VALUE:** trigger value, used in conjunction with the mask [13:10] State exit arc [9:8] RxL0s state [7:4] LTSSM main state [3:0] LTSSM sub state
0	0x0 RW/P	**ENABLE:** Enable the trigger on match

48.2.223 NFTSCOMCLK—Offset B50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B50h

Default: 00FFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0xff RW/P	**GEN3NFTS:** Number of FTS blocks required for RxL0s in common clock mode
15:8	0xff RW/P	**GEN2NFTS:** Number of FTS ordered sets required for RxL0s in common clock mode
7:0	0xff RW/P	**GEN1NFTS:** Number of FTS ordered sets required for RxL0s in common clock mode

48.2.224 NFTSDSCCLK—Offset B54h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B54h

Default: 00FFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0xff RW/P	**GEN3NFTS:** Number of FTS blocks required for RxL0s in non-common clock mode
15:8	0xff RW/P	**GEN2NFTS:** Number of FTS ordered sets required for RxL0s in non-common clock mode
7:0	0xff RW/P	**GEN1NFTS:** Number of FTS ordered sets required for RxL0s in non-common clock mode

48.2.225 LEKBERR—Offset B58h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B58h

Default: 2000FFFFh

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**Enable Leaky Bucket Error Counter (G3LBEEN):** Enable Leaky Bucket Error Counters for gen3, this allows H/W to request re-equalization based on error rate.
30	0x0 RO	**RSVD0:** Reserved
29:25	0x10 RW/P	**Gen3 Leaky Bucket Error Threshold (G3ERRTHRESH):** Leaky Bucket error threshold used for 8GT/s and above. When the error count for a lane passes this threshold, that lane will be flagged as faulty.
24:20	0x0 RW/P	**Leaky Bucket Error Threshold (ERRTHRESH):** Sets the threshold for leaky bucket error handling. When the error count for a lane passes this threshold, that lane will be flagged as faulty.
19:0	0xffff RW/P	**Aggregate error for leaky bucket error handling (AGGRERR):** The error count for the leaky bucket algorithm increments by one when AGGRERR number of errors have been encountered during the specified time period.

48.2.226 EXPBERR0—Offset B5Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B5Ch

Default: FFFFFFFFh

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RW/P	**EXP_BER:** [31:0] Expected BER for leaky bucket error handling [31:0]. Selects the time window that is sampled for aggregate errors.

48.2.227 EXPBERR1—Offset B60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B60h

Default: 02000007h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x2 RW/P	**G3AGGRERR:** Aggregate error for gen3. The error count for the leaky bucket algorithm increments by one when AGGRERR number of errors have been encountered during the specified time period.
23:18	0x0 RO	**RSVD0:** Reserved
17:0	0x7 RW/P	**EXP_BER:** [49:32] Expected BER for leaky bucket error handling [49:32]. Selects the time window that is sampled for aggregate errors.

48.2.228 LEKBPROERR—Offset B64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x0 RW/1C/V/P	**G3ERRLNSTS:** Feature to check status of lane for Gen3. Bit is set when the current error rate exceeds the set error threshold.
15:8	0x0 RO	**RSVD1:** Reserved
7:0	0x0 RW/1C/V/P	**Lane Error Limit Status (ERRLNSTS):** Feature to check status of lane. Bit is set when the current error rate exceeds the set error threshold.

48.2.229 SPEEDCTL—Offset B68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B68h

Default: 02001821h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**RSVD0:** Reserved
29	0x0 RW/V	**LBEG3DIS:** When set to 1, 8GT/s and higher rates are disabled. Hardware or software may set this bit. Hardware will set it when the LBE is enabled to degrade link speed and the LBE threshold is tripped. Software may set or clear at its will. The register is sticky through in-band resets.
28	0x0 RW/V	**LBEG2DIS:** When set to 1, 5GT/s and higher rates are disabled. Hardware or software may set this bit. Hardware will set it when the LBE is enabled to degrade link speed and the LBE threshold is tripped. Software may set or clear at its will. The register is sticky through in-band resets.
27:26	0x0 RO	**RSVD1:** Reserved
25	0x1 RW/P	**LBEG3DEGRADEEN:** Enable LBE to trigger a speed degrade from 8GT/s operation. The 8GT/s mode and higher is disabled until LBEG3DIS is cleared.
24	0x0 RW/P	**LBEG2DEGRADEEN:** Enable LBE to trigger a speed degrade from 5GT/s operation. The 5GT/s mode and higher is disabled until LBEG2DIS is cleared.
23:21	0x0 RO	**RSVD2:** Reserved
20	0x0 RW/V	**RL:** Retrain Link. This bit has the same functionality as the LinkCtrl.Retrain does for downstream ports. It is intended to be used when initiating a software based speed change.
19:16	0x0 RO	**UPTLS:** unused in downstream ports
15:13	0x0 RW/P	**SPDCHGFAILLIM:** Number of failures to train to a particular speed before that speed (and above) is removed from operation. Used in conjunction with LTSSMERRSTS1. A value of 0 disables this feature.
12	0x1 RW/P	**RPTSPDCHANGE:** • 1: Allow speed changes to be logged as a bandwidth change in the LinkStatus register. • 0: Don't report speed changes as a bandwidth change
11	0x1 RW/P	**RPTCFGCHANGE:** • 1: Allow width changes to be logged as a bandwidth change in the LinkStatus register. • 0: Don't report width changes as a bandwidth change
10	0x0 RW/V/P	**DISINITSPDCHNG:** • 1: blocks initial speed change from Gen1-)Gen2/3 after DL_Active asserts • 0: allows an automatic speed change attempt after reaching DL_Active to the highest common speed supported
9	0x0 RW/P	**FORCEGEN3:** • 1: Forces LTSSM to Detect and then trains link at 8GT/s mode • 0: Releases forced speed
8	0x0 RW/P	**FORCEGEN2:** • 1: Forces LTSSM to Detect and then trains link at 5GT/s mode • 0: Releases forced speed
7	0x0 RW/P	**OVRDISGEN3:** Override of disabling gen3

Bit Range	Default & Access	Field Name (ID): Description
6	0x0 RW/P	**OVRDISGEN2:** Override of disabling gen2
5	0x1 RW/P	**MAINTAINTLS:** Aggressively attempt to keep link at LinkCtl2.TLS speed setting. (DSP only)
4	0x0 RW/P	**DISG3POLCFG:** Don't support advertising Gen3 speed in polling.
3	0x0 RW/P	**DISG2POLCFG:** Don't support upper speed G2 in polling
2	0x0 RW/P	**DISG3UNLESSRCVDTS:** Don't support speeds 8GT/s and higher until other device advertises it after a speed change failure or the 200ms timer expires.
1	0x0 RW/P	**DISG2UNLESSRCVDTS:** Don't support speeds 5GT/s and higher until other device advertises it after a speed change failure or 200ms timer expires.
0	0x1 RW/P	**DIRECTEDSPEEDCHNG:** Controls if the highest ever recorded speed supported is used to set the directed speed change internal variable for downstream operation. • 0: two retrain cycles • 1: one retrain cycle (DSP only)

48.2.230 RCVRDETSTS—Offset B6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RO/V/P	**RCVRDETSTS:** The present receiver detect state of each lane in the cluster.

48.2.231 RCVRERR—Offset B70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x0 RW/P	**MASK:** prevent 8b/10b error from given cluster lane from being promoted to PCIE receiver error. Has no effect on RCVRERR.LANE
15:8	0x0 RO	**RSVD1:** Reserved
7:0	0x0 RW/1C/V/P	**LANE:** Indication that a loggable receiver error occurred on a particular lane of the cluster.

48.2.232 EBERR—Offset B74h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x0 RW/1C/V/P	**EB Full per lane (EBFULLERR):** Indication that a loggable receiver error occurred on a particular lane of the cluster.
15:8	0x0 RO	**RSVD1:** Reserved
7:0	0x0 RW/1C/V/P	**EB Empty per lane (EBEMPTYERR):** Indication that a loggable receiver error occurred on a particular lane of the cluster.

48.2.233 EBERRMSK—Offset B78h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B78h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RW/P	**MASK:** Prevent EB error from given cluster lane from being promoted to PCIE receiver error. Has no effect on EBERR.

48.2.234 OBEINJCTL—Offset B7Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B7Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**Response function Done Signal Disable (RESPDONEDIS):** This bit will disable the done signal returned from the response logic. • 0: Use the Done return signal to remove the assertion. • 1: Disable the Done signal from altering the response function assertion.
30:27	0x0 RW/P	**Lane select to inject error on (LNSLCT):** • 0: Lane 0 • 1: Lane1 • ... • 15: Lane 15 Assume N = max number of lanes for the port, then values greater than (N-1) are reserved.
26:25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/P	**Inject Error in Symbols other than STP, END, SDP (OTHRINJ):** • 0: Do not inject error on type Others. • 1: Inject error on type Others when EINJEN is set.
23	0x0 RW/P	**Inject Error in a SDP Symbol (SDPINJ):** • 0: Do not inject error on SDP. • 1: Inject error on SDP when EINJEN is set.
22	0x0 RW/P	**Inject Error in a END Symbol (ENDINJ):** • 0: Do not inject error on END. • 1: Inject error on END when EINJEN is set.
21	0x0 RW/P	**Inject Error in a STP Symbol (STPINJ):** • 0: Do not inject error on STP. • 1: Inject error on STP when EINJEN is set.
20:12	0x0 RO	**RSVD1:** Reserved
11:10	0x0 RW/P	**INJERRTYPE:** This field defines the type of error that is created. In Gen2 • 00: 10b error, invert bit[0] of designated byte after 8b10b encoding • 01: Disparity error on designated byte • 10: 8b error, invert bit[0] of designated byte before 810b encoding • 11: Reserved - no error injected In Gen3 • 00: Invert bit[0] of designated Tx data byte • 01: Invert syncheader[1:0] bits 01(=)10, changes a data block to a control block or vice versa • 10: force syncheader[1:0]=2'b00 (invalid header) • 11: force syncheader[1:0]=2'b11 (invalid header)
9:6	0x0 RW/P	**BLKBYTEOFF:** In gen3, when OTHRINJ is set and the block type matches BLKTYPE, this field defines the Nth byte of block to place error (0 is 1st byte of block).
5	0x0 RW/P	**HDRINJ:** In GEN3, inject an error on the block header that matched block type. The error will be specified by encodings 01-11 of INJERRTYPE.
4	0x0 RW/P	**BLKTYPE:** In GEN3, what block type to either inject a header error on to or qualify the block start with for offset error injection.
3:2	0x0 RO	**RSVD2:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW/P	**Error Injection Function Select (EINJFUNCTSEL):** • 0: Select EINJ0 response function. • 1: Select EINJ1 response function.
0	0x0 RW/P	**Error Injection Enable (EINJEN):** • 0: Disable error injection. • 1: Enable error injection.

48.2.235 LTSSMERRSTS0—Offset B80h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B80h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RW/1C/V/P	**Reserved**
29	0x0 RW/1C/V/P	**EQMEVAL_TO:** Timeout in Phase2 (DSC) or Phase3 (USC) resulting in Rec.Speed
28	0x0 RW/1C/V/P	**EQMEVALCK_TO:** Timeout in Phase2 (DSC) or Phase3 (USC) while locking on to next set of TS, may not result in Rec.Speed
27	0x0 RW/1C/V/P	**EQSEVA_TO:** Timeout in Equalization Phase3 (DSC) or Phase2 (USC) resulting in Rec.Speed
26	0x0 RW/1C/V/P	**EQSEVASYNC_TO:** Timeout in Equalization Phase3 (DSC) or Phase2 (USC) while locking on to next set of TS resulting in Rec.Speed
25	0x0 RW/1C/V/P	**EQPH1_TO:** Timeout in Equalization Phase1
24	0x0 RW/1C/V/P	**EQPH0_TO:** Timeout in Equalization Phase0
23	0x0 RW/1C/V/P	**RECRCVRLCKWIDTH:** Recovery.RcvrLock Timeout Some TS to Config
22	0x0 RW/1C/V/P	**RECRCVRLCKNOTALLTS:** Recovery.RcvrLock Timeout Some TS to Rec.RcvrCfg
21	0x0 RW/1C/V/P	**RXL0SFTS_TO:** RxL0sFTS Timeout
20	0x0 RW/1C/V/P	**UNEXPECTEDEI:** unexpected electrical idle event in L0
19	0x0 RW/1C/V/P	**LBMSTENTRY_TO:** Loopback.Master Entry timeout
18	0x0 RW/1C/V/P	**DISWTEIOS_TO:** Disable.WaitForEIOS timeout
17	0x0 RW/1C/V/P	**RECIDLEDOWN_TO:** Recovery.Idle Timeout link down
16	0x0 RW/1C/V/P	**RECRCVRCFGSPDOWN_TO:** Recovery.RcvrConfigSpeed Timeout link down
15	0x0 RW/1C/V/P	**RECRCVRCFGDOWN_TO:** Recovery.RcvrConfig Timeout link down
14	0x0 RW/1C/V/P	**RECSPDEXITEIEX_TO:** Recovery.SpeedIdleExit Timeout waiting on EI exit
13	0x0 RW/1C/V/P	**RECSPDIDLWTEI_TO:** Recovery.SpeedIdle Timeout waiting on EI
12	0x0 RW/1C/V/P	**RECRCVRLCKBW_TO:** Recovery.RcvrLock Timeout to Recovery.Speed
11	0x0 RW/1C/V/P	**RECRCVRLCKDOWN_TO:** Recovery.RcvrLock Timeout Link Down
10	0x0 RW/1C/V/P	**UPL12RCVEIOS_TO:** Timed out in L12 Entry waiting on received EIOS

Bit Range	Default & Access	Field Name (ID): Description
9	0x0 RW/1C/V/P	**CFGIDLE_TO:** Timed out in Config.Idle
8	0x0 RW/1C/V/P	**CFGCMPLT_TO:** Timed out in Config.Complete
7	0x0 RW/1C/V/P	**CFGLNNUMAC_TO:** Timed out in Config.LaneNumAccept
6	0x0 RW/1C/V/P	**CFGLNNUMWT_TO:** Timed out in Config.LaneNumWait
5	0x0 RW/1C/V/P	**CFGLNKWDAC_TO:** Timed out in Config.LinkWidthAccept
4	0x0 RW/1C/V/P	**CFGLNKWDST_TO:** Timed out in Config.LinkWidthStart
3	0x0 RW/1C/V/P	**POLCFG_NOTS:** Timed out in Polling.Config w/out any TS seen
2	0x0 RW/1C/V/P	**POLACT_NOTS:** Timed out in Polling.Active w/out any TS seen
1	0x0 RW/1C/V/P	**PARTIAL_RCVRDET:** LTSSM detected something, but on 2nd look, no rcvr detected
0	0x0 RW/1C/V/P	**SPEEDCHANGEFAIL:** A speed change attempt failed.

48.2.236 LTSSMERRSTS1—Offset B84h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO/V/P	**LTERR0FERR:** Pointer to the first error logged in LTSSMERRSTS0, value is only valid if a bit is set in LTSSMERRSTS0
26:8	0x0 RW/1C/V/P	**Reserved**
7	0x0 RW/1C/V/P	**G3FAILLIMERR:** Speed changes to 8GT/s have reached the maximum allowed failures, 8GT/s mode is now disabled. See SPEEDCTL.SPDCHGFAILLIM register for more details.
6:4	0x0 RO/V	**G3FAILCTR:** The number of failed attempts to train to 8GT/s without successfully reaching L0 at 8GT/s. This count resets to zero when G3FAILLIMERR is cleared or when L0 is reached at 8GT/s data rate without error.
3	0x0 RW/1C/V/P	**G2FAILLIMERR:** Speed changes to 5GT/s have reached the maximum allowed failures, 5GT/s mode is now disabled. See SPEEDCTL.SPDCHGFAILLIM register for more details.
2:0	0x0 RO/V	**G2FAILCTR:** The number of failed attempts to train to 5GT/s without successfully reaching L0 at 5GT/s. This count resets to zero when G2FAILLIMERR is cleared or when L0 is reached at 5GT/s data rate without error.

48.2.237 EQEVALCTL6—Offset B8Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B8Ch

Default: 04904623h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RSVD0:** Reserved
28	0x0 RW/P	**REQLBMSTRCOEFF:** When intending to master loopback at Gen3 speeds, and entry is from the Config state, this bit can be used to enable the dictation of what far end Tx EQ settings to use. The per lane settings are defined in the GEN3FARTXCOEFF#.D1/2/FTYPE fields. The LNOVRD field is not required to be set. Valid values must also be captured or programmed into the EQFARFSLF register. This mode will not be enabled if loopback is entered from Recovery as it is assumed the values used to reach L0 in that scenario should be used.
27:22	0x12 RW/P	**EIEREENERRCTRMSK:** Number of EIES cycles to wait before counting additional errors after EB/SOS error
21:16	0x10 RW/P	**EIEREENTIME:** Number of EIES cycles to keep EIE reset bit de-asserted after EB/SOS error
15	0x0 RW/V	**LOCBUSFETCHINIT:** Initiate a manual fetch self clears when complete.
14	0x1 RW/P	**LOCBUSFETCHEN:** Enable Local bus fetch of coeff table.
13	0x0 RW/P	**SPDCHGCTLEADPTEN:** Backup to the IOs doing CTLE for speed change to G3. Control will initiate a CTLE adapt after speed changed and Rx EI Exit.
12:10	0x1 RW/P	**LBCTLEADPTWT:** Time before starting CTLE after EI exit detect. • 000 = 512ns • 001 = 1us • 010 = 1.5us • 011 = 2us • 100 = 4us • 101 = 8us • 110 = 12us • 111 = 16us
9	0x1 RW/P	**LBCTLEADPTEN:** Enable CTLE Adaption on entry to Loopback.Master @Gen3.
8:6	0x0 RW/P	**REEQCTLEADPTWT:** Time before starting CTLE after entry to DP.PH1/UP.PH0. • 000 = 512ns • 001 = 1us • 010 = 1.5us • 011 = 2us • 100 = 4us • 101 = 8us • 110 = 12us • 111 = 16us
5	0x1 RW/P	**REEQCTLEADPTEN:** Enable CTLE Adaption on entry to phase1/0 not from speed change w/EQTS2
4:0	0x3 RW/P	**BACKOFFTIME:** Time in EQ before starting CTLE Adapt and then TS lock val(16 =) val[3:0],6'h0, CXLT_TOU_4NS 0-3.84us +0/-4ns val*256ns val)=16 =) val[4:0],5'h0, CXLT_TOU_128NS 0-126.98us +0/-128ns val*4us

48.2.238 EQEVALCTL7—Offset B90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B90h

Default: 000000FFh

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7:0	0xff RW/P	**FOMSTPLIM:** Max FOM value, if FOM)=FOMSTPLIM, exit evaluation.

48.2.239 EQFARFSLF—Offset B9Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + B9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**RSVD0:** Reserved
17	0x0 RO/V	**LFSAME:** All lanes of the port have equal LF
16	0x0 RO/V	**FSSAME:** All lanes of the port have equal FS
15:14	0x0 RO	**RSVD1:** Reserved
13:8	0x0 RW/V/P	**FARLF:** This field shows the current EQ phase1 status of the link partners LF parameter. The value is also used during entry to loopback master from config when requesting the use of coefficients. If the link has not gone through phase1 of EQ, then software will need to manually write a value. Anytime the link goes through phase1, this field is updated with the value advertised by the link partner (discarding any software written value).
7:6	0x0 RO	**RSVD2:** Reserved
5:0	0x0 RW/V/P	**FARFS:** This field shows the current EQ phase1 status of the link partners FS parameter. The value is also used during entry to loopback master from config when requesting the use of coefficients. If the link has not gone through phase1 of EQ, then software will need to manually write a value. Anytime the link goes through phase1, this field is updated with the value advertised by the link partner (discarding any software written value).

48.2.240 FOMINCCTL—Offset BA4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BA4h

Default: 03046820h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x3 RW/P	**SlowTimerThresh:** FOM feedback value threshold to switch to Slow timer from fast
23	0x0 RW/P	**ErrMaskEn:** Enable Error Mask window
22	0x0 RW/P	**Tem_Unit:** Error mask window time unit • 0: 28ns + val* 32ns upto 2044ns (+0/-4ns) • 1: 896ns + val* 1024ns upto 65408ns (+0/-128ns)
21:16	0x4 RW/P	**Tem_Val:** Error mask window time count
15:14	0x1 RW/P	**Tsi_Unit:** Slow Time Unit
13:8	0x28 RW/P	**Tsi_Val:** Slow Time Count Value
7:6	0x0 RW/P	**Tfi_Unit:** Fast Time Unit • 00: 28ns + val* 32ns upto 2044ns (+0/-4ns) • 01: 896ns + val* 1024ns upto 65408ns (+0/-128ns) • 10: 7us + val* 8us upto 504us (+0/-1us) • 11: 48us + val* 64us upto 4.08ms (+0/-16us)
5:0	0x20 RW/P	**Tfi_Val:** Fast Time Count Value

48.2.241 PHYRECAL—Offset BA8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BA8h

Default: 0000000Ch

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**RSVD0:** Reserved
3	0x1 RW/P	**G3RecOnErrEn:** Request recal on Gen3 Recovery due to Error
2	0x1 RW/P	**G2RecOnErrEn:** Request recal on Gen2 Recovery due to Error
1	0x0 RW/P	**G3L1ExitEn:** Request recal on Gen3 L1 exit
0	0x0 RW/P	**G2L1ExitEn:** Request recal on Gen2 L1 exit

48.2.242 PLLSTBYCTL—Offset BACh

This register is only valid for project specific w/ PLLSTBY feature.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BACh

Default: 00000100h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**PLL Standby In Progress Assertion (PSIP):** When PLL standby is enable gives a range of time to all idle to L1 entry. This indicates to the PCI PLL Control block to assert PSIP. Also known as t200. Range : 0 = 70ns 1 = 150ns 2 = 230ns ... 15= 1270ns **Power Well:** PRST
27:24	0x0 RW	**PLL Standby Assertion (PSTBYA):** Time window to allow for synchronization between idle indications and PLL control logic. This window starts after L1 entry and PLL standby Enabled. Also known as t200. Range: 0 = 40ns 1 = 50ns 2 = 60ns ... 15= 190ns **Power Well:** PRST
23:20	0x0 RW	**PLL Standby Min Assertion time (PSMAT):** Minimum time that the PLL Control block can put the PLL in standby. Anytime shorter than the min time can cause indeterminate PLL behavior. Also known as t202. Range: 0 = 150ns 1 = 310ns 2 = 470ns ... 15= 2550ns **Power Well:** PRST
19:9	0x0 RO	**RSVD0:** Reserved
8	0x1 RW	**P2 vs P1/2 for PLL Idle (P2VSP1):** 0 = lane in P1 equal to idle for PLL standby (see PIPECTL for P2 disable) 1 = lane in P2 equal to idle for PLL standby **Power Well:** PRST
7:4	0x0 RO	**RSVD1:** Reserved
3:0	0x0 RW	**PLL Standby Enable (PSE):** A one enables the PLL control block to put PLL1-4 in standby when the port is in L1 and all idle conditions are met. **Power Well:** PRST

48.2.243 PLUTXEQCTL—Offset BB0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BB0h

Default: 078A0000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:22	0x1e RW/V/P	**8GT/s Full Swing (FS):** This field is used for setting 8GT/s full swing coefficient parameter.
21:16	0xa RW/V/P	**8GT/s Low Frequency (LF):** This field is used for setting 8GT/s low frequency coefficient parameter.
15:0	0x0 RO	**RSVD1:** Reserved

48.2.244 PHYCGIDLEMSK—Offset BB4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BB4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RW/P	**PLL_L1IDLE:** Disables placing the PLL in standby during L1.Idle state This field is only valid for project specific w/ PLLSTBY feature.
4	0x0 RW/P	**PLL_L2IDLE:** Disables placing the PLL in standby during L2.Idle state This field is only valid for project specific w/ PLLSTBY feature.
3	0x0 RW/P	**PLL_DISSUCC:** Disables placing the PLL in standby during Disable.Success state This field is only valid for project specific w/ PLLSTBY feature.
2	0x0 RW/P	**Disable L1 Clock Gating (L1IDLE):** Disables clock gating in L1.Idle state
1	0x0 RW/P	**Disable L2 Clock Gating (L2IDLE):** Disables clock gating in L2.Idle state
0	0x0 RW/P	**Disable LTSSM Disable State Clock Gating (DISSUCC):** Disables clock gating in Disable.Success state

48.2.245 EQEVALCTL4—Offset BB8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BB8h

Default: 64320000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**REVERSEEQTS2:** Allows EQTS2s to be sent by upstream port or decoded by downstream port to override the LinkEqCtl.DownStreamPortTxPreset value. For an upstream port, the PREFPRESET1 value will be sent in the EQTS2s it sends to the upstream component. For a downstream port, this will enable it to accept EQTS2s from the upstream port and override the LinkEqCtl.DownstreamTxPreset value.
30:24	0x64 RW/P	**QCHKTMVAL:** Final evaluation loop time. This loop will not ask the IOs to enabled any adaptive eq logic and is used as a quick sanity check of link errors.
23	0x0 RW/P	**QCHKTMUNIT:** 0 = time limit is QCHKTMVAL * 1us, 1 = time limit is QCHKTMVAL * 128us
22:20	0x3 RW/P	**HINTIDXMODE:** Hint mode index lookup FarTxWeight (FTW) = Using TxPreset captured in Phase1, apply mapping from UPHINTMAP0/1 register LocTxWeight (LTW) = Using TxPreset captured in EQTS2s (LaneEqCtl.UPTP), apply mapping from UPHINTMAP0/1 register RxHintWeight (RHW) = Using Rx Hint captured in EQTS2s (LaneEqCtl.UPRPH), apply mapping from UPHINTMAP2 register Register Value: Hint Index Result • 000: (LTW+FTW)/2 • 001: FTW • 010: LTW • 100: RHW • 011: (LTW+FTW)/2 • 101: (RHW+FTW)/2 • 110: (RHW+LTW)/2 • 111: (RHW+LTW+FTW)/3 The resultant index is used in the comparison of UPHISELFOMTBL. UPHISELFOMTBL.MST If the value calculated according to EQEVALCTL4.HINTIDXMODE is less than the programmed value, treat channel as short and use FOM stage1 entries from the FOM Hint Table. UPHISELFOMTBL.MLT If the value calculated according to EQEVALCTL4.HINTIDXMODE is less than the programmed value and greater or equal to MST, treat the channel as medium-short and use UPHIFOMTBLM0-7.MSD1,D2,FT for FOM Stage1 entries. UPHISELFOMTBL.MLT If the value calculated according to EQEVALCTL4.HINTIDXMODE is less than the programmed value and greater or equal to MST, treat the channel as medium-short and use UPHIFOMTBLM0-7.MSD1,D2,FT for FOM Stage1 entries. UPHISELFOMTBL.LT If the value calculated according to EQEVALCTL4.HINTIDXMODE is less than the programmed value and greater or equal to MLT, treat the channel as medium-long and use UPHIFOMTBLM0-7.MLD1,D2,FT for FOM Stage1 entries. If the value calculated according to EQEVALCTL4.HINTIDXMODE is greater or equal to the programmed value, treat the channel as long and use UPHIFOMTBLL0-7.LD1,D2,FT for FOM Stage1 entries.
19	0x0 RW/V/P	**RXHINT7OVR_EN:** When set to 1, the starting coeff to evaluate (phase2 upstream, phase3 downstream) will be derived from Rx Hint Table entry DBXX (7). This overrides the preferred preset mode and the normal Rx Hint table mode.
18	0x0 RW/P	**RXHINTCOEFF_EN:** If this field is set and FOMSEARH_EN=1 and port is an Upstream port, use HINTIDXMODE and UPHISELFOMTBL to select FOM Stage1 points -OR- FOMSEARCH_EN=1 and port is a Downstream port, field is unused (except if EQEVALCTL2.EVALATT==1). -OR- FOMSEARCH_EN=0, use HINTIDXMODE result to index into FOMHINTTBL for single coefficient evaluation.
17	0x1 RW/V/P	**FOMSEARCH_EN:** Figure of Merit search enable.
16:10	0x0 RO	**RSVD0:** Reserved
9:0	0x0 RW/P	**FOMERRTHRESH:** Figure of Merit error threshold

48.2.246 EQEVALCTL5—Offset BBCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BBCh

Default: 3A87F003h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**RSVD0:** Reserved
30:27	0x7 RW/P	**PhSTimerVal:** Slave phase (UP=Phase3, DP=Phase2) timeout. time limit is (val+1)*4ms.
26:23	0x5 RW/P	**PhMTimerVal:** Master phase (UP=Phase2, DP=Phase3) timeout. time limit is (val+1)*4ms.
22:20	0x0 RW/P	**PhaseTODis:** Disable phase 1/2/3 timeouts bit 0 - phase 1 bit 1 - phase 2 bit 3 - phase 3
19:12	0x7f RW/P	**USEPREEVALWAIT:** Time to wait after lock (or lock timeout) before enabling the IOs to evaluate the new tx preset settings. This allows the circuits some extra time to setup their evaluation logic. Time is value*4us.
11:4	0x0 RW/P	**COEFFEVALWAIT:** Time to wait after lock (or lock timeout) before enabling the IOs to evaluate the new coeff settings. This allows the circuits some extra time to setup their evaluation logic. Time is value*4us.
3:0	0x3 RW/P	**LOCKTIME:** Max time to allow block lock on new coeff request. Time is value*4us. When this field is set to 0, it will remain in Lock state until lock is achieved or the primary timer for Phase2/3 expires (thus an EQ failure).

48.2.247 LEKBLNERRCNT0—Offset BC0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BC0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**RSVD0:** Reserved
29:25	0x0 RO/V	**Lane 5 Error Count (ERRCNT5):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.
24:20	0x0 RO/V	**Lane 4 Error Count (ERRCNT4):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.
19:15	0x0 RO/V	**Lane 3 Error Count (ERRCNT3):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.
14:10	0x0 RO/V	**Lane 2 Error Count (ERRCNT2):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.
9:5	0x0 RO/V	**Lane 1 Error Count (ERRCNT1):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.
4:0	0x0 RO/V	**Lane 0 Error Count (ERRCNT0):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.

48.2.248 LEKBLNERRCNT1—Offset BC4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BC4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**RSVD0:** Reserved
9:5	0x0 RO/V	**Lane 7 Error Count (ERRCNT7):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.
4:0	0x0 RO/V	**Lane 6 Error Count (ERRCNT6):** Error count seen on a lane for the current time window. Decrements progressively to 0 if no errors seen over a prolonged time period.

48.2.249 EQEVALCTL—Offset BD0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BD0h

Default: 00080808h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**RSVD0:** Reserved
30	0x0 RW/P	**BYPASSEQ:** Bypass all aspects of Adaptive EQ.
29	0x0 RW/P	**NODLINITBLK:** Don't block the DL state machine from starting DL Init once initial L0 reached.
28	0x0 RW/P	**BYPASSEQTS2:** For a downstream link, this allows entry to Gen3 w/out sending EQTS2 in 8b/10b mode prior to transmitting at 8GT/s.
27:24	0x0 RW/P	**DEFPRESET:** Preset that will be used if 8GT/s entered w/out receiving EQTS2s. preset 0000 is -6dB de-emphasis and 0dB preshoot.
23	0x0 RW/P	**FLIPCOEFFUPDPOL:** Chicken bit to flip what coeff up/down means to core.
22:16	0x8 RW/P	**PREACCTHR:** Pre cursor eval threshold. The threshold used is value*8 for calculation.
15	0x0 RO	**RSVD1:** Reserved
14:8	0x8 RW/P	**MAINACCTHR:** Main cursor eval threshold. The threshold used is value*8 for calculation.
7	0x0 RO	**RSVD2:** Reserved
6:0	0x8 RW/P	**POSTACCTHR:** Post cursor eval threshold. The threshold used is value*8 for calculation.

48.2.250 EQEVALCTL2—Offset BD4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BD4h

Default: 0000FF55h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/P	**BLKUPEQREQ:** When this bit is set to 1, the following two events will NOT set the request eq bit in TS2s during Rec.RcvrCfg following Rec.Equalization. • Equalization engine deems link usable but not optimal (this would normally trigger an immediate eq request in TS2s) • Coeff received in Rec.RcvrLck follow Rec.Eq don't match negotiated coeff during Eq.
30	0x0 RW/P	**BLKUPSPEED:** H/W will not initiate an up step in speed to 8GT/s in order to advertise or re-do equalization
29	0x0 RW/P	**IGNOREQUIESCE:** H/W will ignore quiesce bit received from downstream component
28	0x0 RW/P	**HWQUIESCE:** H/W will require quiescing of the link prior to re-equalization
27	0x0 RW/P	**HWREEQEN:** Allow HW to initiate re-equalization.
26	0x0 RW/P	**EXTEIEOS:** Enable extended EIEOS request during master eval stage (up component phase 3, down component phase 2).
25	0x0 RW/P	**IGNOREMD:** Echo coeff back but don't change them to the IO.
24	0x0 RW/P	**SKIPEVALPH:** Skip execution of the master eval coeff phase (up component phase 3, down component phase 2). For downstream it skips phase2/3 completely per PCIe Spec. For upstream it passes quickly through phase2 doing no real eval.
23	0x0 RW/P	**REEQSPDDEGRADE:** When set, a self detected need to re-equalize will result in a down shift in speed and a disabling of the current rate (8GT/s or higher) and all rates above it.
22:16	0x0 RO	**RSVD0:** Reserved
15:8	0xff RW/V/P	**EVALATT:** Max number of coeff for a lane to eval before quitting eval phase. Value of 0 means no limit. The value is scaled by the link partners advertised FS value (adj_val = roundup(val*(FS+1)/64)). If FS is 63, the spec max, the value would be unaltered, whereas for a FS of 31, the value written to the config register would be halved. One attempt will be made if the programmed value is greater than 0 and the adjusted value would have resulted in a value of 0. Any evaluation attempt following an InvalidRequest indication on the PIPE interface is not counted as an attempt.
7:0	0x55 RW/P	**EVALTIME:** Field defined to do each coeff eval as following. Evaltime[7:6] = unit Evaltime[5:0] = value Unit: • 11=)1ms • 10=)128us • 01=)16u • 00=)1us This field should not be programmed in value of 0 (unit=any, value=0) for devices connected to WM design.

48.2.251 EQEVALCTL3—Offset BD8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BD8h

Default: 33F30802h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x3 RW/P	**REPEATLIM:** Maximum number of times a previously tried coeff can be attempted. A value of 0 means disable the repeat check. Repeats are defined as coeff already seen in the history matrix. Each time a coeff lookup in the history matrix returns a hit and the limit not reached, the history matrix is reset and the repeat counter incremented.
27:24	0x3 RW/P	**INVREQATTLIM:** Maximum number of repeated times the MAC will allow the PIPE-Phy to request an out-of-bounds coeff (MAC responds to each by asserting InvalidRequest) before aborting the equalization evaluation process. The PIPE3 spec gives no bounds, but if after some number of attempts, the PIPE-Phy keeps requesting the same invalid update, it makes no sense to continue. A value of 0 disables this check.
23	0x1 RW/P	**AllowFromMainOnly:** When set to 1, the main cursor is the only cursor pre or post can get a unit from. So if main is at its minimum value, then an addition to post (or pre) can only occur if a subtraction from pre (or post) is also requested. This prevents adjusting the cursor ratio of pre or post in the opposite direction than is desired. When set to 0, a pre/post edit will take a unit from post/pre if the main cursor does not have a unit to give.
22	0x1 RW/P	**OptCursorEdit:** If pre and post cursor movement requests are in opposite directions, service both at once if legally possible. If not set, it will only edit 1 cursor using the priority defined by PreVsPostRR and PreOverPost
21	0x1 RW/P	**PreVsPostRR:** Edits to pre vs post cursor will be done in a fair round robin manner. The PreOverPost field will dictate the first cursor to be modified. If not set, it will follow a strict priority to pre or post based on PreOverPost field.
20	0x1 RW/P	**PreOverPost:** Pre-cursor adjustments will be taken over post-cursor adjustments when set to 1, else post has priority.
19:18	0x0 RO	**RSVD0:** Reserved
17	0x1 RW/P	**UNDERT2REDO:** If block error count under Threshold 2 but equal to or over Threshold 1, request a redo of equalization
16	0x1 RW/P	**OVERT2SPDFAIL:** If block error count measured over Threshold 2, force link to fail down to lower speed
15:8	0x8 RW/P	**ERRTHRESH2:** Block error count limit considered usable, but may spawn a redo of Equalization if enabled. Setting of 0 causes all checks to at least pass the Threshold 2 check.
7:0	0x2 RW/P	**ERRTHRESH1:** Block error count limit considered optimal. Setting of 0 disables block error check.

48.2.252 EQEVALSTS—Offset BDCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BDCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RO/V/P	**Lane 7 at EVAL Loop (LNLOOP7):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
22	0x0 RO/V/P	**Lane 6 at EVAL Loop (LNLOOP6):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
21	0x0 RO/V/P	**Lane 5 at EVAL Loop (LNLOOP5):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
20	0x0 RO/V/P	**Lane 4 at EVAL Loop (LNLOOP4):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
19	0x0 RO/V/P	**Lane 3 at EVAL Loop (LNLOOP3):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
18	0x0 RO/V/P	**Lane 2 at EVAL Loop (LNLOOP2):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
17	0x0 RO/V/P	**Lane 1 at EVAL Loop (LNLOOP1):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
16	0x0 RO/V/P	**Lane 0 at EVAL Loop (LNLOOP0):** FBDIR = Lane hit Loop Limit: Lane evaluation stopped due to repeated coeff (IO tap update resulted in a loop) FOM = Lane in Paused state: PAUSE gets set when lane SM goes to PAUSE
15:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RO/V/P	**Lane 7 at optimal EQ (LNOPT7):** Lane is running at optimal EQ setting
6	0x0 RO/V/P	**Lane 6 at optimal EQ (LNOPT6):** Lane is running at optimal EQ setting
5	0x0 RO/V/P	**Lane 5 at optimal EQ (LNOPT5):** Lane is running at optimal EQ setting
4	0x0 RO/V/P	**Lane 4 at optimal EQ (LNOPT4):** Lane is running at optimal EQ setting
3	0x0 RO/V/P	**Lane 3 at optimal EQ (LNOPT3):** Lane is running at optimal EQ setting

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RO/V/P	**Lane 2 at optimal EQ (LNOPT2):** Lane is running at optimal EQ setting
1	0x0 RO/V/P	**Lane 1 at optimal EQ (LNOPT1):** Lane is running at optimal EQ setting
0	0x0 RO/V/P	**Lane 0 at optimal EQ (LNOPT0):** Lane is running at optimal EQ setting

48.2.253 EQEVALSTS2—Offset BE0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BE0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**RSVD0:** Reserved
8	0x0 RW/1C/V	**REEQSPDDISG3:** When set, hardware has disabled 8GT/s and above data rates due to a need to re-equalize.
7:0	0x0 RO/V/P	**EVALATTS:** Number of eval attempts to get all lanes optimal.

48.2.254 EQEVALSTS3—Offset BE4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BE4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23	0x0 RO/V/P	**Lane 7 at EVAL Rule Violation (LNRULELIM7):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
22	0x0 RO/V/P	**Lane 6 at EVAL Rule Violation (LNRULELIM6):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
21	0x0 RO/V/P	**Lane 5 at EVAL Rule Violation (LNRULELIM5):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
20	0x0 RO/V/P	**Lane 4 at EVAL Rule Violation (LNRULELIM4):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
19	0x0 RO/V/P	**Lane 3 at EVAL Rule Violation (LNRULELIM3):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
18	0x0 RO/V/P	**Lane 2 at EVAL Rule Violation (LNRULELIM2):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
17	0x0 RO/V/P	**Lane 1 at EVAL Rule Violation (LNRULELIM1):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
16	0x0 RO/V/P	**Lane 0 at EVAL Rule Violation (LNRULELIM0):** FBDIR = Hit invalid request too many times: Lane evaluation stopped due to coeff rule boundary (IO tap update would result in rule violation) FOM = Search complete: Complete gets set when lane SM goes to OPTIMAL or NON_OPTIMAL and the full search has completed (so cases of non-optimal w/out complete being set are possible).
15:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RO/V/P	**Lane 7 Met Error Threshold 2 (LNERRTH2MET7):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2
6	0x0 RO/V/P	**Lane 6 Met Error Threshold 2 (LNERRTH2MET6):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2
5	0x0 RO/V/P	**Lane 5 Met Error Threshold 2 (LNERRTH2MET5):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RO/V/P	**Lane 4 Met Error Threshold 2 (LNERRTH2MET4):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2
3	0x0 RO/V/P	**Lane 3 Met Error Threshold 2 (LNERRTH2MET3):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2
2	0x0 RO/V/P	**Lane 2 Met Error Threshold 2 (LNERRTH2MET2):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2
1	0x0 RO/V/P	**Lane 1 Met Error Threshold 2 (LNERRTH2MET1):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2
0	0x0 RO/V/P	**Lane 0 Met Error Threshold 2 (LNERRTH2MET0):** Non-optimal lane met error threshold 2 requirements from EQEVALCTL3.ERRTHRESH2

48.2.255 G3FRAMEERR—Offset BECh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:9-12, 14-17, F:0] + BECh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**RSVD0:** Reserved
30:27	0x0 RO/V/P	**G3FRAMEFERR:** First error pointer to bits 26:0 of this register
26:12	0x0 RO	**RSVD1:** Reserved
11	0x0 RW/1C/V/P	**FCRC:** TLP framing crc error
10	0x0 RW/1C/V/P	**ITKNL0:** Invalid token on lane 0 (may include misplaced legal token)
9	0x0 RW/1C/V/P	**ITKNLI:** Invalid token post logical idle (may include misplaced legal token)
8	0x0 RW/1C/V/P	**ITKNDL:** Invalid token post DLLP (may include misplaced legal token) [as x1, means in DLLP token too]
7	0x0 RW/1C/V/P	**ITKNTL:** Invalid token post TLP (may include misplaced legal token) [as x1/x2, includes bad EDB token]
6	0x0 RW/1C/V/P	**SDSFE:** bad/unexpected data following SDS block
5	0x0 RW/1C/V/P	**BKFE:** block framing error (header mismatch, bad header, etc.)
4	0x0 RW/1C/V/P	**BK1FE:** unexpected type 1 (OS) header
3	0x0 RW/1C/V/P	**EDS:** bad data following EDS (includes EDS not at end of block)
2	0x0 RW/1C/V/P	**STP2:** two TLP start tokens in same symbol time
1	0x0 RW/1C/V/P	**SDP2:** two DLLP start tokens in same symbol time
0	0x0 RW/1C/V/P	**RDOK:** rcvd data ok removed unexpectedly (rcvr. imp. specific)

48.3 Sideband Registers - Devices 9-12

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

48.3.1 PPBIFCTL_PRIV—Offset 10h

Port Configuration Bifurcation Control for MLW (x8) vs Port number

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xB4] + 10h
Host Memory Space: SBREG_BAR + 0xB40000 + 10h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RW-L bits of PPBIFCTL register only. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit.
30:3	0x0 RO	**RSVD0:** Reserved
2:0	0x0 RW/V/L	**Bifurcation Control 0 (BIFCTL0):** • 111-101: Reserved • 100: x8 • 011: x4x4 • 010: x4x2x2 • 001: x2x2x4 • 000: x2x2x2x2 A write of '1' on the CL will lock this register field down as bifurcation control status information.

48.4 Sideband Registers - Devices 14-17

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

48.4.1 PPBIFCTL_PRIV—Offset 10h

Port Configuration Bifurcation Control for MLW (x8) vs Port number

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xB3] + 0h
Host Memory Space: SBREG_BAR + 0xB30000 + 10h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RW-L bits of PPBIFCTL register only. • 1b: Lock • 0b: Unlocked This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no affect on this bit.
30:3	0x0 RO	**RSVD0:** Reserved
2:0	0x0 RW/V/L	**Bifurcation Control 0 (BIFCTL0):** • 111-101: Reserved • 100: x8 • 011: x4x4 • 010: x4x2x2 • 001: x2x2x4 • 000: x2x2x2x2 A write of '1' on the CL will lock this register field down as bifurcation control status information.

§ §

49 SMBus - Host - B0, D18, F0

49.1 Introduction and Index

The host-accessible registers for the SMBus - Host are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

49.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 18 (decimal), Function 0. The offset addresses are listed.

Table 49-1. Summary of PCI Configuration Registers—0/18/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"VID—Offset 0h" on page 1820
2	2	19AC	"DID—Offset 2h" on page 1820
4	2	0000	"PCICMD—Offset 4h" on page 1821
6	2	0010	"PCISTS—Offset 6h" on page 1822
8	1	00	"RID—Offset 8h" on page 1823
9	3	00088000	"CCR—Offset 9h" on page 1823
10	8	0000000000000004	"SMTBAR—Offset 10h" on page 1824
2C	2	8086	"SVID—Offset 2Ch" on page 1824
2E	2	0000	"SID—Offset 2Eh" on page 1825
3C	1	00	"INTL—Offset 3Ch" on page 1825
3D	3	01	"INTP—Offset 3Dh" on page 1826
40	2	8010	"EXPCAPLST—Offset 40h" on page 1826
44	4	10008001	"DEVCAP—Offset 44h" on page 1827
48	2	0000	"DEVCTL—Offset 48h" on page 1829
4A	2	0000	"DEVSTS—Offset 4Ah" on page 1830
80	2	8C01	"PMCAPLST—Offset 80h" on page 1831
8C	2	0005	"MSICAPLST—Offset 8Ch" on page 1831
8E	2	0180	"MSICTL—Offset 8Eh" on page 1832
90	8	0000000000000000	"MSIADDR—Offset 90h" on page 1832
98	4	00000000	"MSIDATA—Offset 98h" on page 1833
9C	4	00000000	"MSIMSK—Offset 9Ch" on page 1834
EA	2	0000	"PLKCTL—Offset EAh" on page 1834

49.1.2 Host Memory Space—SMTBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 49-2. Summary of Memory Mapped I/O Registers—SMTBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"GCTRL—Offset 0h" on page 1835
8	8	0000000000000000	"SMTICL—Offset 8h" on page 1836
10	4	00000000	"ERRINTMSK—Offset 10h" on page 1837
14	4	00000000	"ERRAERMSK—Offset 14h" on page 1838
18	4	00000000	"ERRSTS—Offset 18h" on page 1839
1C	4	00000000	"ERRINFO—Offset 1Ch" on page 1840
100	8	0000000000000000	"MDBA—Offset 100h" on page 1840
108	4	00000000	"MCTRL—Offset 108h" on page 1841
10C	4	00000000	"MSTS—Offset 10Ch" on page 1842
110	4	00000000	"MDS—Offset 110h" on page 1843
114	4	00061020	"RPOLICY—Offset 114h" on page 1844
200	8	0000000000000000	"TBBA—Offset 200h" on page 1846
208	4	00000010	"TCTRL—Offset 208h" on page 1847
20C	4	00000000	"TSTS—Offset 20Ch" on page 1848
210	4	00000000	"TBS—Offset 210h" on page 1849
218	4	00000000	"HTHP—Offset 218h" on page 1849
21C	4	00000000	"FTTP—Offset 21Ch" on page 1850
220	4	00000058	"TRxCTRL—Offset 220h" on page 1850
224	4	00000000	"TRxSTS—Offset 224h" on page 1851
228	4	00000000	"TACTRL—Offset 228h" on page 1852
22C	4	00000000	"TPOLICY—Offset 22Ch" on page 1853
240	4	00000000	"GPBRCTRL—Offset 240h" on page 1855
244	4	00000000	"GPBRDBUF—Offset 244h" on page 1856
280	4	00000000	"SMTARPCTRL—Offset 280h" on page 1857
290	8	8086000000000000	"UDID0—Offset 290h" on page 1858
298	8	8108808600000024	"UUDID0—Offset 298h" on page 1859
2A0	8	8086000000000000	"UDID1—Offset 2A0h" on page 1860
2A8	8	8108808600000024	"UUDID1—Offset 2A8h" on page 1861
300	4	00000005	"SPGT—Offset 300h" on page 1862
304	4	08080000	"SPMT—Offset 304h" on page 1863
308	4	00000000	"SPST—Offset 308h" on page 1864
30C	4	00002024	"SMBFT—Offset 30Ch" on page 1865
310	4	000015E1	"CLTC—Offset 310h" on page 1866
380	4	80000000	"DCLKGT—Offset 380h" on page 1866
384	4	00000011	"SUSCHKB—Offset 384h" on page 1867
388	4	00000003	"DBCTRL—Offset 388h" on page 1868
38C	4	00000300	"DBSTS—Offset 38Ch" on page 1869

49.2 Registers in Configuration Space

49.2.1 VID—Offset 0h

The Vendor ID Register identifies this device as an Intel device and adheres to the definitions in the PCI Local Bus Specification, Revision 3.0.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**Vendor ID (VID):** This is the standard 16-bit value assigned to Intel by PCI-SIG.

49.2.2 DID—Offset 2h

The Device ID Register identifies this device and adheres to the PCI Local Bus Specification, Revision 3.0.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 2h

Default: 19ACh

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x19ac RO/V	**Device ID (DID):** This is the SMT Device identification Number.

49.2.3 PCICMD—Offset 4h

The PCI Command Register follows a subset of the PCI Local Bus Specification, Revision 3.0. This register provides the basic control of the ability of the device to initiate and respond to transactions sent to it and maintains compatibility with PCI configuration space.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RW	**Interrupt Disable (INTxD):** Controls the ability to generate legacy INTx interrupt messages. When set, functions are prevented from asserting INTx interrupt messages.
9	0x0 RO	**Fast Back to Back Enable (FBE):** Hard-wired to 0.
8	0x0 RW	**SERR# Enable (SEE):** This bit indicates whether the device is allowed to signal a PCIe SERR condition. • 0: The device is disabled from generating fatal/non-fatal errors. • 1: The device is enabled to send fatal/non-fatal errors.
7	0x0 RO	**RSVD:** Reserved
6	0x0 RW	**Parity Error Response (PERE):** This bit controls the setting of the master data parity error bit in the Status Register in response to a parity error received on the PCI Express interface (either internal queue errors or a poisoned TLP). • 0: Parity errors are ignored by the device. • 1: The device reports parity errors.
5	0x0 RO	**RSVD:** Reserved
4	0x0 RO	**RSVD:** Reserved
3	0x0 RO	**RSVD:** Reserved
2	0x0 RW	**Bus Master Enable (BME):** Controls the ability of this device to initiate transactions to memory including MMIO. • 0: The function is not allowed to issue any memory requests. • 1: The function is allowed to issue memory requests.
1	0x0 RW	**Memory Space Enable (MSE):** Controls whether the device responds to memory space transactions as located by its memory space BAR. • 0: Disables device's memory BAR to be decoded as a valid target address. • 1: Enables device's memory BAR to be decoded as a valid target address.
0	0x0 RO	**RSVD:** Reserved

49.2.4 PCISTS—Offset 6h

The PCI Status Register follows a subset of the PCI Local Bus Specification, Revision 3.0. This register maintains compatibility with PCI configuration space. Since this register is part of the standard PCI header, there is a PCISTS register per PCI function.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**Detected Parity Error (DPE):** This bit is set when the device receives an uncorrectable data error or Address/Control parity error regardless of the Parity Error Response bit in the "PCICMD—Offset 4h" on page 1821.
14	0x0 RW/1C/V	**SERR# Asserted (SSE):** • 0: No internal device port errors are signaled. • 1: The device reported internal fatal/non-fatal errors.
13	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit is set when device experiences a master abort on a transaction it has mastered on IOSF.
12	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit is set when device accesses to IOSF return a failed completion status.
11	0x0 RW/1C/V	**Signaled Target Abort (STA):** The IPI interface of the SMT will flag a completer abort for requests to its MMIO space that are greater than 8B in length.
10:9	0x0 RO	**RSVD:** Reserved
8	0x0 RW/1C/V	**Master Data Parity Error (MDPD):** This bit is set if the Parity Error Response bit in the PCI Command register set is set and it receives a completion with poisoned data from IOSF.
7	0x0 RO	**RSVD:** Reserved
6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO	**RSVD:** Reserved
4	0x1 RO	**Capabilities List (CAPE):** This bit indicates that this device implements a PCI Capability list.
3	0x0 RO/V	**Interrupt Status (INTS):** When set, this bit indicates that an INTx emulation interrupt is pending internally in this function, it is reset when the internal signal is de-asserted. This bit has meaning only in the legacy interrupt mode. This bit is always 0 when MSI-X has been selected for DMA interrupts.
2:0	0x0 RO	**RSVD1:** Reserved

49.2.5 RID—Offset 8h

Revision ID Register bit definitions adhere to PCI Local Bus Specification, Revision 3.0.

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:18, F:0] + 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V/P	**Revision ID (RID):** This value is initially 0 for the first release and is incremented for subsequent releases in order to identify any changes.

49.2.6 CCR—Offset 9h

Class Code Register bit definitions adhere to PCI Local Bus Specification, Revision 3.0. Auto configuration software reads this register to determine the PCI device function.

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:18, F:0] + 9h

Default: 00088000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x8 RW/O	**Base Class (BASE):** Indicates it is a 'Generic System Peripheral'. **Power Well:** PRST
15:8	0x80 RW/O	**Sub Class (SUB):** Indicates 'Other System Peripheral'. **Power Well:** PRST
7:0	0x0 RO	**RSVD:** Reserved **Power Well:** PRST

49.2.7 SMTBAR—Offset 10h

This base address register marks the memory-mapped registers used for SMBus Management Transport functionality. These registers are listed subsequently.

Type: PCI Configuration Register (Size: 64 bits)

Offset: [B:0, D:18, F:0] + 10h

Default: 0000000000000004h

Bit Range	Default & Access	Field Name (ID): Description
63:10	0x0 RW	**Base Address (MBA):** Base address of SMT control registers.
9:4	0x0 RO	**Memory Size (MS):** Reserved.
3	0x0 RO	**Prefetchable (PFMEM):** This bit is hardwired to 0b to indicate non-prefetchable.
2:1	0x2 RO	**Type (MTYPE):** The SMT MMIO registers should have the ability to be relocated anywhere within 64-bit address space.
0	0x0 RO	**Memory space indicator (MSI):** Hardwired to 0 to indicate that this is a memory space BAR.

49.2.8 SVID—Offset 2Ch

The Subsystem Vendor ID Register bit definitions adhere to PCI Local Bus Specification, Revision 3.0.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 2Ch

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RW/O	**Subsystem Vendor ID (SVID):** This register uniquely identifies the add-in board or subsystem vendor. **Power Well:** PRST

49.2.9 SID—Offset 2Eh

The Subsystem ID Register bit definitions adhere to PCI Local Bus Specification, Revision 3.0.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 2Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/O	**Subsystem ID (SID):** uniquely identifies the add-in board or subsystem. **Power Well:** PRST

49.2.10 INTL—Offset 3Ch

Interrupt Line Register bit definitions adhere to PCI Local Bus Specification, Revision 3.0.

This register identifies interrupt line routing information.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:18, F:0] + 3Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Assigned (INTL):** system-assigned value identifies which system interrupt controller's interrupt request has the device's PCI interrupt request routed to it (as specified in the interrupt pin register). A value of FFH signifies 'no connection' or 'unknown'.

49.2.11 INTP—Offset 3Dh

Interrupt Pin Register bit definitions adhere to PCI Local Bus Specification, Revision 3.0. This register must be programmed before legacy interrupts are enabled.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:18, F:0] + 3Dh

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RW/L	**Interrupt Pin (INTP):** Indicates which INTx assert/deassert legacy interrupt messages are used. • 01h: Generate INTA. • 02h: Generate INTB. • 03h: Generate INTC. • 04h: Generate INTD. • Others: Reserved. **Power Well:** PRST

49.2.12 EXPCAPLST—Offset 40h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 40h

Default: 8010h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x80 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list ("PMCAPLST—Offset 80h").
7:0	0x10 RO	**Capability ID (CAPID):** Identifies the function as PCI Express capable.

49.2.13 DEVCAP—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:18, F:0] + 44h

Default: 10008001h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RSVD0:** Reserved.
28	0x1 RW/O	**Function Level Reset Capability (FLR):** This field when set indicates this function supports function Level Reset mechanism. Lock key bit for DEVCTL.IFLR. • 0b: Lock. • 1b: Unlocked. **Power Well:** PRST
27:26	0x0 RO	**RSVD:** Reserved
25:18	0x0 RO	**RSVD:** Reserved
17:16	0x0 RO	**RSVD1:** Reserved.
15	0x1 RO	**Role-Based Error Reporting (RBER):** The PCIe cluster supports Role-based Error Reporting.
14:12	0x0 RO	**RSVD:** Reserved.
11:9	0x0 RO	**Endpoint L1 Acceptable Latency (EPL1AL):** • 000b Maximum of 1 us • 001b Maximum of 2 us • 010b Maximum of 4 us • 011b Maximum of 8 us • 100b Maximum of 16 us • 101b Maximum of 32 us • 110b Maximum of 64 us • 111b No limit This field does not apply to SMT device. The minimal latency is shown here as default
8:6	0x0 RO	**Endpoint L0s Acceptable Latency (EPL0AL):** • 000b Maximum of 64 ns • 001b Maximum of 128 ns • 010b Maximum of 256 ns • 011b Maximum of 512 ns • 100b Maximum of 1 us • 101b Maximum of 2 us • 110b Maximum of 4 us • 111b No limit This field does not apply to SMT device. The minimal latency is shown here as default
5	0x0 RO	**Extended Tag Field Supported (ETFG):** • 0: The device supports 5-bit extended tag • 1: The device supports 8-bit extended tag Currently, only 5-bit tag is supported and validated for the EP
4:3	0x0 RO	**RSVD:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
2:0	0x1 RO	**Max Payload size Supported (MPSS):** This is an internal device and can send/receive up to 256B packets internally from/to the IOSF fabric.

49.2.14 DEVCTL—Offset 48h

The MPS register field is coded with NFLRST attribute to indicate it is not reset by FLR.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 48h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/V/L	**Initiate Function Level Reset (IFLR):** A write of 1 initiates Function Level Reset. The value read by software from this bit is always 0b. Only applies to end point. This field is locked by the complement of the DEVCAP.FLR LockKey: ~DEVCAP.FLR **Power Well:** NFLRST
14:12	0x0 RO	**Max_Read_Request_Size (MRRS):** This field sets the maximum Read Requests size of the function as a requester on PCIe.
11	0x0 RW	**Enable No Snoop (ENOSNP):** If this bit this is set, the function is permitted to set the No Snoop bit in the Requester attributes of transactions.
10	0x0 RO	**RSVD:** Reserved
9	0x0 RO	**RSVD:** Reserved
8	0x0 RO	**RSVD:** Reserved
7:5	0x0 RW	**Maximum Payload Size (MPS):** This field sets maximum TLP payload size for the function. • 000b: 128 bytes maximum payload size (default) • 001b: 256 bytes maximum payload size • Others: Reserved **Power Well:** NFLRST
4	0x0 RO	**RSVD:** Reserved
3	0x0 RW	**Unsupported Request Reporting Enable (URRE):** This bit controls the enabling of ERR_CORR, ERR_NONFATAL, or ERR_FATAL messages for reporting 'Unsupported Request' errors.
2	0x0 RW	**Fatal Error Reporting Enable (FERE):** When this bit is set, generation of the ERR_FATAL message is enabled.
1	0x0 RW	**NonFatal Error Reporting Enable (NFERE):** When this bit is set, generation of the ERR_NONFATAL message is enabled.
0	0x0 RW	**Correctable Error Reporting Enable (CERE):** When this bit is set, generation of the ERR_CORR message is enabled.

49.2.15 DEVSTS—Offset 4Ah

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 4Ah

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RO/V	**Transactions Pending (TP):** When set, this bit indicates that the device has issued non-posted PCI Express transactions which have not yet completed.
4	0x0 RO	**RSVD:** Reserved
3	0x0 RW/1C/V	**Unsupported Request Detected (URD):** This bit indicates that this function received an unsupported request from PCI Express link. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
2	0x0 RW/1C/V	**Fatal Error Detected (FED):** This bit indicates that the function has detected a Fatal error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
1	0x0 RW/1C/V	**Non-Fatal Error Detected (NFED):** This bit indicates that the function has detected a Non-Fatal error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.
0	0x0 RW/1C/V	**Correctable Error Detected (CED):** This bit indicates that the function has detected a Correctable error. Errors are logged in this register regardless of whether error reporting is enabled or not in the Device Control register.

49.2.16 PMCAPLST—Offset 80h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 80h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list ("MSICAPLST—Offset 8Ch").
7:0	0x1 RO	**Capability ID (CAPID):** Identifies the function as PCI Power Management capable.

49.2.17 MSICAPLST—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NP):** Contains the offset of the next item in the capabilities list.
7:0	0x5 RO	**Capability ID (CAPID):** Identifies the function as MSI capable.

49.2.18 MSICTL—Offset 8Eh

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:18, F:0] + 8Eh

Default: 0180h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved.
8	0x1 RO	**Per-vector masking capable (PVM):** This bit indicates that this device supports MSI per-vector masking.
7	0x1 RO	**Address 64-Bit Capable (AD64C):** When set, this bit indicates that this function is capable of generating a 64-bit message address. • 1: Function is capable of sending 64-bit message address. • 0: Function is not capable of sending 64-bit message address.
6:4	0x0 RW	**Multiple Message Enable (MMEN):** These bits are R/W for software compatibility. SMT supports only one message. • 000b = 1 Message. • Others = Reserved.
3:1	0x0 RO	**Multiple Message Capable (MMC):** SMT supports only one MSI message (power of 2). There is no option of supporting multiple messages.
0	0x0 RW	**MSI Enable (MSIE):** When set, MSI is enabled and traditional interrupt pins are not used to generate interrupts. Software must disable INTx and MSI-X for this device when using MSI.

49.2.19 MSIADDR—Offset 90h

Type: PCI Configuration Register
(Size: 64 bits)

Offset: [B:0, D:18, F:0] + 90h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:2	0x0 RW	**Address (ADDR):** Message address specified by the system, always Dword aligned.
1:0	0x0 RO	**RSVD0:** Reserved.

49.2.20 MSIDATA—Offset 98h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:18, F:0] + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15	0x0 RW	**Trigger Mode (TM):** • 0: Edge Triggered. • 1: Level Triggered.
14	0x0 RW	**Level (LVL):** If TM is 0h, then this field is a don't care. Edge-triggered messages are always treated as assert messages. If TM is 1h, then: • 0: Deassert Messages • 1: Assert Messages. For level-triggered interrupts, this bit reflects the state of the interrupt input.
13:12	0x0 RW	**Future:** These bits are don't care for an IOxAPIC interrupt message data field specification.
11:8	0x0 RW	**Delivery Mode (DM):** • 0000: Fixed: Trigger Mode can be edge or level. • 0001: Lowest Priority: Trigger Mode can be edge or level. • 0010: SMI/PMI/MCA - Not supported via MSI of root port • 0011: Reserved - Not supported via MSI of root port. • 0100: NMI - Not supported via MSI of root port. • 0101: INIT - Not supported via MSI of root port. • 0110: Reserved. • 0111: ExtINT - Not supported via MSI of primary port. • 1000 -1111 - Reserved.
7:0	0x0 RW	**Interrupt Vector (IV):** The interrupt vector (LSB) will be modified by the IIO to provide context-sensitive interrupt information for different events that require attention from the processor. e.g Hot plug, Power Management and RAS error events.

49.2.21 MSIMSK—Offset 9Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:18, F:0] + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**RSVD0:** Reserved.
0	0x0 RW	**Mask Bits (MSKB):** For each Mask bit that is set, the PCI Express port is prohibited from sending the associated message. The SMT supports 1 MSI message. Corresponding bits are masked if set to '1'.

49.2.22 PLKCTL—Offset EAh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:18, F:0] + EAh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:1	0x0 RO	**RSVD0:** Reserved.
0	0x0 RW/L	**Capability Lock (CL):** Lock key bit for all RW-L bits (capabilities, next capability pointer, SSID/SVID, slot register, etc) bits for the function. • 1b: Lock. • 0b: Unlocked. This bit is self-locking. Once this bit is set to a 1b, this key bit can not be unlocked. Writing a 0b has no effect on this bit. **Power Well:** PRST

49.3 Registers in Memory Space—SMTBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) SMTBAR described in Section 49.2.7, "SMTBAR—Offset 10h" on page 1824.

49.3.1 GCTRL—Offset 0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 0h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**RSVD0:** Reserved.
6	0x0 RW/V/P	**SRST (SoftReset):** Set by the FW to asynchronously Reset the SMT Master and Target logic, Clear all the MMIO registers, and Release the SMBus Clock and Data lines.
5:4	0x0 RO	**RSVD1:** Reserved.
3	0x0 RW/V/P	**KILL:** FW sets the bit to cause HW to cause clock low timeout on the SMBus and generate stop after the timeout.
2	0x0 RW/V/P	**Target Reset (TRST):** Set by FW to force HW to idle its internal SMBus clock and data.
1:0	0x0 RO	**RSVD2:** Reserved.

49.3.2 SMTICL—Offset 8h

This address register marks the location of where SMT interrupt cause information is written before an MSI is sent. The two least-significant bits are fixed at 00b so that the memory address is Dword-aligned.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [SMTBAR] + 8h

Default: 0000000000000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:2	0x0 RW	**Base Address (BA):** Base address of SMT interrupt cause.
1:0	0x0 RO	**Memory Size (MS):** Reserved.

49.3.3 ERRINTMSK—Offset 10h

Interrupt masking applies to both MSI and INTx.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 10h

Default: 00000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**RSVD0:** Reserved.
24	0x0 RW/P	**SMBus Clock Low Timeout Error Interrupt Mask (CKLTO):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.CKLTO being set.
23:18	0x0 RO	**RSVD1:** Reserved.
17	0x0 RW/P	**Target Ring Buffer Full Error Interrupt Mask (TRBF):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.TRBF being set.
16	0x0 RW/P	**Target Ring Buffer Almost Full Error Interrupt Mask (TRBAF):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.TRBAF being set.
15:13	0x0 RO	**RSVD2:** Reserved.
12	0x0 RW/P	**IPI Host Interface Error (IHIE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.IHIE being set.
11	0x0 RW/P	**IPI Master Abort Error (IMAE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.IMAE being set. ERRINTMSK.IMAE: this bit is assumed to be '1' when MSICTL.MSIE is set. IMAE will occur only if PCICMD.BME is clear and MSI requires BME to be set.
10	0x0 RO	**IPI Transmit Error Interrupt Mask (ITE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.ITE being set. This error condition is deprecated.
9	0x0 RW/P	**IPI Receive Data Parity Error Interrupt Mask (IRDPE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.IRDPE being set.
8	0x0 RO	**IPI Receive Error Interrupt Mask (IRE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.IRE being set. This error condition is deprecated.
7:2	0x0 RO	**RSVD3:** Reserved.
1	0x0 RW/P	**SPD Write Error Mask (SPDWE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.SPDWE being set.
0	0x0 RW/P	**CSR Parity Error Interrupt Mask (CPE):** FW sets this bit to mask HW from generating an interrupt due to ERRSTS.CPE being set.

49.3.4 ERRAERMSK—Offset 14h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 14h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**RSVD0:** Reserved.
24	0x0 RW/P	**SMBus Clock Low Timeout Error AER Mask (CKLTO):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.CKLTO being set.
23:18	0x0 RO	**RSVD1:** Reserved.
17	0x0 RW/P	**Target Ring Buffer Full Error AER Mask (TRBF):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.TRBF being set.
16	0x0 RW/P	**Target Ring Buffer Almost Full Error AER Mask (TRBAF):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.TRBAF being set.
15:13	0x0 RO	**RSVD2:** Reserved.
12	0x0 RW/P	**IPI Host Interface Error (IHIE):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.IHIE being set.
11	0x0 RW/P	**IPI Master Abort Error (IMAE):** FW sets this bit to mask HW from escalating through AER Correctable Internal Error due to ERRSTS.IMAE being set. This error is escalated as Correctable.
10	0x0 RO	**IPI Transmit Error AER Mask (ITE):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.ITE being set. This error condition is deprecated.
9	0x0 RW/P	**IPI Receive Data Parity Error AER Mask (IRDPE):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.IRDPE being set.
8	0x0 RO	**IPI Receive Error AER Mask (IRE):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.IRE being set. This error condition is deprecated.
7:2	0x0 RO	**RSVD3:** Reserved.
1	0x0 RW/P	**SPD Write Error AER Mask (SPDWE):** FW sets this bit to mask HW from escalating through AER Correctable Internal Error due to ERRSTS.SPDWE being set.
0	0x0 RW/P	**CSR Parity Error AER Mask (CPE):** FW sets this bit to mask HW from escalating through AER Uncorrectable Internal Error due to ERRSTS.CPE being set.

49.3.5 ERRSTS—Offset 18h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 18h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**RSVD0:** Reserved.
24	0x0 RW/1C/V/P	**SMBus Clock Low Timeout Error Status (CKLTO):** This bit is set by HW when SMBus clock is seen low for the time programmed in CLTC.CNT. FW clears this register by writing '1'.
23:18	0x0 RO	**RSVD1:** Reserved.
17	0x0 RW/1C/V/P	**Target Ring Buffer Full Error Status (TRBF):** HW sets this bit when it needs to write data and/or header to memory and does not have enough free space in the ring buffer in memory. Once the ring buffer full status bit is set, HW will silently NACK all incoming target transactions on the command phase to indicate that it is busy. FW clears this register by writing '1'.
16	0x0 RW/1C/V/P	**Target Ring Buffer Almost Full Error Status (TRBAF):** HW sets this bit after it has completed writing data and/or header to memory and checks if there is less than 85B of free space in the ring buffer. FW clears this register by writing '1'.
15:13	0x0 RO	**RSVD2:** Reserved.
12	0x0 RW/1C/V/P	**IPI Host Interface Error (IHIE):** HW sets this bit when a read completion returns with non-successful status. FW clears this register by writing '1'.
11	0x0 RW/1C/V/P	**IPI Master Abort Error (IMAE):** HW sets this bit if a request is made when PCICMD.BME is clear. FW clears this register by writing '1'.
10	0x0 RO	**IPI Transmit Error Status (ITE):** HW sets this bit if an error is detected in any IPI transmit transaction. This error condition is deprecated.
9	0x0 RW/1C/V/P	**IPI Receive Data Parity Error Status (IRDPE):** HW sets this bit if a data parity error is detected in any IPI receive transaction. FW clears this register by writing '1'.
8	0x0 RO	**IPI Receive Error Status (IRE):** HW sets this bit if an error is detected in any IPI receive transaction. This error condition is deprecated.
7:2	0x0 RO	**RSVD3:** Reserved.
1	0x0 RW/1C/V/P	**SPD Write Error Status (SPDWE):** HW sets this bit if a write is attempted to SPD address range (A0h-AEh) and write disable (MCTRL.SPDDIS) has been set. FW clears this register by writing '1'.
0	0x0 RW/1C/V/P	**CSR Parity Error Status (CPE):** HW sets this bit if a parity error is detected in any CSR. FW clears this register by writing '1'.

49.3.6 ERRINFO—Offset 1Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 1Ch

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:13	0x0 RO/V/P	**Second Error Info (SERRINFO):** Scratchpad.
12:8	0x0 RO/V/P	**Second Error Pointer (SERRPTR):** Upon the second occurrence of any error, as included in ERRSTS, HW sets this register to point to the specific bit which was set.
7:5	0x0 RO/V/P	**First Error Info (FERRINFO):** Scratchpad.
4:0	0x0 RO/V/P	**First Error Pointer (FERRPTR):** Upon the first occurrence of any error, as included in ERRSTS, HW sets this register to point to the specific bit which was set.

49.3.7 MDBA—Offset 100h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [SMTBAR] + 100h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:6	0x0 RW	**Master Descriptor Base Address (MDBA):** 64Byte aligned base address of the master descriptor ring buffer in FW memory. HW uses this base to add to MSTS.HMTP to calculate the physical address of the memory location it wants to access. FW must update this register only when MCTRL.SS and MSTS.IP bits are cleared.
5:0	0x0 RO	**RSVD0:** Reserved.

49.3.8 MCTRL—Offset 108h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 108h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved.
23:16	0x0 RW	**Firmware Master Head Pointer (FMHP):** Address offset of the number of descriptors available in the descriptor ring. Updated by FW when it has programmed one or more new descriptors in the master descriptor ring buffer. Always points to the descriptor offset that FW will next write to. FW can increment this register at most to be 'MSTS.HMTP - 1' thus implying that Master Descriptor Ring Buffer can only hold 'MDS - 1' valid descriptors. FW must roll this register to 0 after MDS is reached.
15:5	0x0 RO	**RSVD1:** Reserved.
4	0x0 RW	**Master Error Interrupt Enable (MEIE):** Set by FW to enable HW to generate MSI (if MSICTL.MSIE set) if MSTS.MEIS bit is set.
3	0x0 RW/O/P	**SPD Write Disable (SPDDIS):** This bit must be set to '1' to disable writes to DIMM SPD, which are located in address range A0h-AEh. If set, this address range is unwritable until the next platform reset. Reads are unaffected. This bit is reset only upon platform reset. It should be set by BIOS MRC (Memory Reference Code).
2:1	0x0 RO	**RSVD2:** Reserved.
0	0x0 RW/V	**Start/Stop (SS):** Set by the FW when it has programmed at least one descriptor in the descriptor ring. Cleared by FW when it wants HW to stop processing more descriptors. FW must monitor the MSTS.IP bit which indicates that HW is truly stopped. HW clears this register for the following fatal error scenario, regardless of Stop-on-Error (SOE) bit in the master descriptor: • HW receives unsuccessful completion on internal IOSF. HW clears this register for the following non-fatal scenario: • Master descriptor SOE bit was set and the transaction was unsuccessful for any condition as reported in the Status WB Dword.

49.3.9 MSTS—Offset 10Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 10Ch

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved.
23:16	0x0 RW/V	**Hardware Master Tail Pointer (HMTP):** Descriptor offset in the descriptor ring. Incremented by HW and points to the descriptor that HW is currently processing or will process next. Initialized by FW with the descriptor location where it wants the master to start transaction from (typically 0). This register must only be written by FW when the MCTRL.SS bit is '0' and the MSTS.IP bit is '0'. HW must not increment this pointer in the case that due to the failure of a descriptor-initiated cycle, HW clears the MCTRL.SS bit. HW uses MSTS.HMTP and MCTRL.FMHP to calculate Full and Empty conditions. FW must never initialize this buffer to a value greater than MDS.
15:6	0x0 RO	**RSVD1:** Reserved.
5	0x0 RW/1C/V	**Master Interrupt Status (MIS):** Set by HW to indicate that the descriptor that was being processed was successfully done over SMBus. HW proceeds normally to process the next descriptor if the MCTRL.SS bit is set. HW auto-clears this register if INT bit in the descriptor which it finished processing is set and the associated MSI is sent. If INT bit in descriptor is cleared, FW clears this bit by writing '1'.
4	0x0 RW/1C/V	**Master Error Interrupt Status (MEIS):** Set by HW to indicate that the descriptor that was being processed was not successfully done on SMBus. HW halts the descriptor engine by clearing the MCTRL.SS bit if this bit is set and the SOE bit in the descriptor which was processed was set. HW auto-clears this register if MCTRL.MEIE register is set and the associated Master Error MSI is sent. If MCTRL.MEIE is cleared, FW clears this bit by writing '1'.
3:1	0x0 RO	**RSVD2:** Reserved.
0	0x0 RO/V	**In Progress (IP):** Set by the HW to indicate that its DMA processor is active meaning that it is processing a descriptor. HW will clear this bit after it has finished processing the current descriptor (which is the completion of the descriptor's status write back into memory and Interrupt if enabled is sent). This is to aid the stopping of HW even if there are multiple descriptors to be processed.

49.3.10 MDS—Offset 110h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 110h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved.
7:0	0x0 RW	**Master Descriptor Size (MDS):** Defines the size of the master descriptor ring buffer that is pointed to by MDBA. 0-based number of 16B descriptors. The top of the ring buffer is MDBA+MDS including the last location. A value of '1' represents a total possible capacity of 2 descriptors in the ring, and a value of '255' represents capacity of 256 descriptors in the ring. Used by HW to calculate if it has reached the top of the buffer and must wrap back to 0.

49.3.11 RPOLICY—Offset 114h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00061020h

BAR and Offset: [SMTBAR] + 114h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved.
23:16	0x6 RW	**Time Between Retry Clock Count (TBRCLKCNT):** This register is programmed by the FW to set the retry timer clock count. The reference clock used for this timer count is specified by FW in RPOLICY.TBRBCLK. The combination of the setting in this register and the reference tick used in RPOLICY.TBRBCLK determines how long the HW waits before issuing an automatic retry for master transactions. A value of '0' indicates HW should retry the transaction without any additional delay. ***Note:*** Retry count is not applicable for retries due to collision on SMBus. Those must be retried as soon as SMBus is free. This timer must be reloaded every time HW attempts a retry or a completely new cycle is initiated by FW. ***Note:*** (FW) Since the timer ticks in register RPOLICY.TBRBCLK are free running and not independently generated by HW, there is a possibility of inaccuracy in delay time. This inaccuracy is at most 1 complete duration of the timer tick, e.g. if 1ms tick is chosen the inaccuracy is never greater than 1ms. Hence FW should use its judgment in which timer tick is selected. Recommendation would be to use a faster tick so that the inaccuracy is smaller.
15:14	0x0 RO	**RSVD1:** Reserved.
13:11	0x2 RW	**Collision Retry (COLRTRY):** This field allows the FW to set the number of times master transactions are retried before HW gives up. HW decrements this count after it attempts a master transaction and loses arbitration on SMBus. This timer must be reloaded by HW whenever the RPOLICY.RETRY count is changed (i.e. decremented due to retry or reloaded due to new master cycle initiated). • 000: Reserved. • 001: Retry once (total attempts = 2). • 010: Retry 2 times (total attempts = 3). • 011: Retry 3 times (total attempts = 4). • 100: Retry 4 times (total attempts = 5). • 101: Retry 5 times (total attempts = 6). • 110: Retry 6 times (total attempts = 7). • 111: Retry 7 times (total attempts = 8).
10:8	0x0 RW	**Time Between Retry Base Clock (TBRBCLK):** This register allows the FW to choose the granularity of the timer tick. • 000: 10us. • 001: 100us. • 010: 1ms. • 011: 10ms. • 100: 100ms. • 101: Reserved. • 110: Reserved. • 111: Reserved. The combination of this register and the RPOLICY.TBRCLKCNT register allows the FW to set mean time between retries on SMBus.

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x2 RW	**RETRY:** HW will decode this field to determine the number of times to retry before HW gives up. HW must not decrement this count for cycles that are retried because of collision. HW must reload this count every time it starts a new master cycle. HW must not retry cycles if the cycle was unsuccessful due to a clock-low timeout on the SMBus. • 0000: No retries. • 0001: Retry once (total attempts = 2). • 0010: Retry 2 times (total attempts = 3). • 0011: Retry 3 times (Default: total attempts = 4). • 0100: Retry 4 times (total attempts = 5). • 0110: Retry 5 times (total attempts = 6). • 0111: Retry 6 times (total attempts = 7). • ... • 1111: Retry 15 times (Total attempts = 16).
3:0	0x0 RO	**RSVD2:** Reserved.

49.3.12 TBBA—Offset 200h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [SMTBAR] + 200h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:6	0x0 RW	**Target Buffer Base Address (TBBA):** 64B aligned base address of the target ring buffer. HW uses this base to add to the HTHP to calculate the physical address of the memory location it wants to access. FW must update this register only when target is disabled and TSTS.IP bit is cleared.
5:0	0x0 RO	**RSVD0:** Reserved.

49.3.13 TCTRL—Offset 208h

For definitions and usage of fields PBC (Payload Byte Count), RBC (Read Byte Count), MTYPE (Message Type), TSTS (Transaction Status), and TTYPE (Transaction Type) in the target header, refer to Figure 20-7, 'Target Header Format' on page 863, Table 20-11, 'Target Header Descriptor' on page 864, Table 20-12, 'Valid Target Descriptor MTYPE and TTYPE Combinations' on page 867, and Table 20-13, 'Target Header Encodings (TSTS) Per Transaction Type (TTYPE)' on page 868.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 208h

Default: 00000010h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**RSVD0:** Reserved.
6	0x0 RW	**Un-Successful Received Target Writes Policy (URxTWP):** FW sets this bit to enable the HW to send data and header for unsuccessful write cycles received by the HW as a target. Since HW is responsible only for writing the payload to memory and sending a descriptor to FW, it is FW responsibility to inspect the transaction data to determine protocol type, payload, etc. The following cycles fall under this policy umbrella: • SMBus Host Notify. • ARP Notify. • ARP Master. • ARP Prepare to ARP. • ARP Assign Address. • ARP General Reset Device command. • ARP Directed Reset Device command to TACTRL.ADDR0 or TACTRL.ADDR1. • SMBus Send Byte command to TACTRL.ADDR0 or TACTRL.ADDR1. • SMBus Write Byte/Word command to TACTRL.ADDR0 or TACTRL.ADDR1. • SMBus Block Write command to TACTRL.ADDR0 or TACTRL.ADDR1 I2C. • Master-TX writes Slave-RX to TACTRL.ADDR0 or TACTRL.ADDR1. The header bits will define the transaction size (PBC and RBC), cycle type (MTYPE and TTYPE), and why the cycle was unsuccessful (TSTS!=0000b). When this bit is cleared, HW only sends data and header to FW of cycles which were successful.
5	0x0 RW	**Un-Successful Completion Header WB Policy (UCHWBP):** FW sets this bit to enable the HW to send a header for programmed FW cycles that were unsuccessfully completed as a target. The following cycles fall under this policy umbrella: • SMBus Block Reads to GPBR Address (GPBRCTRL.GPTRADR). • SMBus Quick Command to TACTRL.ADDR0 or TACTRL.ADDR1. • ARP Directed Get UDID command to TACTRL.ADDR0 or TACTRL.ADDR1. • ARP General Get UDID command. The header bits will define the transaction size (PBC and RBC), cycle type (MTYPE and TTYPE), and why the cycle was unsuccessful (TSTS!=0000b). When this bit is cleared, no header writeback is done by HW. If General Get UDID command is received and that UDID Address Resolved (AR) flag is set, HW will NACK the ARP 'command' byte to indicate it has a valid assigned slave address (its ARP is complete), and it should not send any unsuccessful completion header to FW.
4	0x1 RW	**Successful Completion Header WB Policy (SCHWBP):** FW sets this bit to enable the HW to send a header for programmed FW cycles that were successfully completed as target on SMBus. The following cycles fall under this policy umbrella: • SMBus Block Reads to GPBR Address (GPBRCTRL.GPTRADR). • Cycles to ADDR0 or ADDR1 (TACTRL.ADDR0 or TACTRL.ADDR1). • Cycles to Default Address (C2h). • Cycles to SMBus or ARP Host (10h). The header bits will define the transaction size (PBC and RBC), cycle type (MTYPE and TTYPE), and successful completion status (TSTS=0000b). When this bit is cleared, no header writeback is done by HW.

Bit Range	Default & Access	Field Name (ID): Description
3:1	0x0 RO	**RSVD1:** Reserved.
0	0x0 RW	**Target Interrupt Enable (TIE):** FW sets this bit to enable HW to send MSI when it writes header to memory, i.e. when TSTS.TIS is set.

49.3.14 TSTS—Offset 20Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 20Ch

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved.
11:8	0x0 RO/V	**Target Cycle In Progress (TCIP):** This field allows FW to check which logical target address HW is currently servicing as a target. This field is set by HW at the same time as TSTS.IP transitions from 0 to 1. • 0000: Default SMBus transaction to C2h. • 0001: Transaction targeting address (TACTRL.ADDR0) of UDID0. • 0010: Transaction targeting address (TACTRL.ADDR1) of UDID1. • 0100: Host Notify transaction targeting 10h. • 0101: Generic Programmable Block Read to programmed address in GPBRCTRL.GPTRADR. • Others: Reserved. This field is valid only when the TSTS.IP bit is set. This field is consistent with Target Header Descriptor TTYPE field.
7:2	0x0 RO	**RSVD1:** Reserved.
1	0x0 RO/V	**In Progress (IP):** This bit is set by HW when it is processing a target cycle received on SMBus. This is the phase after the HW has ACKed a matching address until Stop is asserted by the external initiator, target buffer is emptied, and interrupt if enabled is sent to FW. This bit is cleared otherwise.
0	0x0 RW/1C/V	**Target Interrupt Status (TIS):** This bit is set by HW after it has written status header in target ring buffer as an indication of interrupt generation. • The conditions which result in a status header being written are governed by these policies: TCTRL.SCHWBP: upon successful completion. • TCTRL.UCHWBP: upon unsuccessful completion. • TCTRL.URxTWP: upon unsuccessful completion of writes to target. If TCTRL.TIE is cleared, FW must write '1' to clear this bit. It TCTRL.TIE register is set and global MSICTL.MSIE is set, HW sends the MSI and auto-clears this bit.

49.3.15 TBS—Offset 210h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 210h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:2	0x0 RW	**Target Buffer Size (TBS):** Defines the size in bytes of the target ring buffer in memory which must be Dword aligned. Bits[1:0] are reserved such that FW always provides HW a buffer in granularity of 4Bytes. • 0x0000: 4B. • 0x0004: 8B. • ... • 0xFFFC: 65536B (~64KB).
1:0	0x0 RO	**RSVD1:** Reserved.

49.3.16 HTHP—Offset 218h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 218h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:2	0x0 RW/V	**Hardware Target Buffer Head Pointer (HTBHP):** Dword offset from the base address within the target ring buffer. Updated by HW to indicate the offset within the ring buffer where the HW is writing payload data/ header or will be writing to next. HW uses HTHP and FTTP and TBS to calculate buffer full, empty, and wrap conditions. FW must never initialize this to a value greater than TBS.TBS or undefined HW behavior may occur.
1:0	0x0 RO	**RSVD1:** Reserved.

49.3.17 FTTP—Offset 21Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 21Ch

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:2	0x0 RW	**Firmware Target Buffer Tail Pointer (FTBTP):** Dword offset from the base address within the target ring buffer. Updated by FW and points to the offset FW is reading from or will read from next. FW must never increment this register beyond the value of the HTHP.HTBHP register.
1:0	0x0 RO	**RSVD1:** Reserved.

49.3.18 TRxCTRL—Offset 220h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000058h

BAR and Offset: [SMTBAR] + 220h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Descriptio
31:8	0x0 RO	**RSVD0:** Reserved.
7:0	0x58 RW	**Max Receive Bytes (MRxB):** This register sets the limit for the maximum number of bytes (address included) that SMT can receive as a target of write transactions. Once this limit is reached, HW must NACK the following received bytes. The encoding is 0's based, i.e. '0' means 1 byte (address only) and '255' means 256 bytes. • 00h: Reserved. • 01h: 2 bytes (address + 1 additional byte). • ... • EFh: 240 bytes (address + 239 additional bytes). • F0h: Reserved. • ... • FFh: Reserved. HW must always track the received number of bytes for I2C transactions to ensure that it never overflows the count programmed in this register. When this count is met, HW must NACK any following received bytes. (It is expected that bounded protocols, like SMBus which announces a byte count, provide protocol-level control to ensure write count is not exceeded. Should HW NACK such an overflowing transaction it is the responsibility of the bus master to recover and retry.) Default is defined for MCTP with 80B MCTP packet payload: (8B) MCTP SMBus Packet Header (includes 4B SMBus medium-specific header and 4B MCTP transport header) (80B) MCTP Packet Payload (1B) SMBus PEC = 89B --) 88d (0's-based encoding).

49.3.19 TRxSTS—Offset 224h

This register is updated by HW for cycles received as a target. HW updates this register with every new target cycle received even during EP well power available. The contents are similar to the target header updates by HW, so refer to the header fields for explanation, unless noted below.

This register is primarily a debug feature. This register is updated based on HW responding to transactions on SMBus. There is no ordering maintained w.r.t. updating this register and header/data write back to memory.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 224h

Default: 00000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**Payload Byte Count (PBC):** HW updates this field to indicate how many bytes were ACKed on SMBus sent by the external master and stored within the target buffer locally. For writes coming in, this data will include the sum total of all bytes ACKed from 'start' to 'stop'. For error scenarios where the master drives more data than expected or command code does not match, HW will update the count with all bytes ACKed on SMBus from 'Start' until the first byte NACKed by HW (this byte is not added to the count).
23:22	0x0 RO	**RSVD0:** Reserved.
21:16	0x0 RO/V	**Read Byte Count (RBC):** This byte count is for externally generated read transactions only. HW updates this field to indicate the sum total of data bytes it successfully provided over SMBus to the external master.
15:12	0x0 RO	**RSVD1:** Reserved.
11:8	0x0 RO/V	**MTYPE:** Check the Target header description.
7:4	0x0 RO/V	**TSTS:** Check the Target header description.
3:0	0x0 RO/V	**TTYPE:** Check the Target header description.

49.3.20 TACTRL—Offset 228h

Each address supported by SMT device must be unique since they all logically reside on the same SMBus segment.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 228h

Default: 00000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:9	0x0 RW	**Address1 (ADDR1):** FW programs this field with an address of the SMT logic.
8	0x0 RO	**RSVD1:** Reserved.
7:1	0x0 RW	**Address0 (ADDR0):** FW programs this field with an address of the SMT logic.
0	0x0 RO	**RSVD2:** Reserved.

49.3.21 TPOLICY—Offset 22Ch

The target addresses referenced above are located in the following registers:

- TACTRL.ADDR0
- TACTRL.ADDR1
- GPBRCTRL.GPTRADR

FW can write to this register to enable/disable functionality pertaining to a target address. FW requests HW to update the new policy by setting TPOLICY.PTUREQ register.

HW waits until all the pending target cycles are over, and copies the contents of this register into internal non-FW-visible register bits. Once it is done, HW clears the TPOLICY.PTUREQ register as confirmation to FW that the new policy is in effect. FW can always read this register and see the current policy that HW is using if the PTUREQ bit is cleared. Any setting or clearing of the policies in this register without setting the PTUREQ bit first must not cause HW to change policies.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 22Ch

Default: 00000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/V/P	**Target Policy Update Request (PTUREQ):** FW sets this bit to indicate to the HW that it wants to update registers/policies in the target interface. The new policy that the FW needs is programmed in the lower word of this register. HW clears this bit when it has updated the new policy. When this bit is cleared the other registers indicate the current policy in effect in HW.
30:11	0x0 RO	**RSVD0:** Reserved.
10	0x0 RW	**C2_BSY:** When set forces HW to ACK only matching C2h address byte and NACK in any subsequent bytes to indicate device is busy.
9	0x0 RW	**Host Busy (HOSTBSY):** When set forces HW to ACK only matching 10h address byte and NACK in any subsequent bytes to indicate device is busy.
8	0x0 RW	**ADDR1 Busy (ADDR1BSY):** When set forces HW to ACK only matching ADDR1 address byte and NACK in any subsequent bytes to indicate device is busy.
7	0x0 RO	**RSVD1:** Reserved.
6	0x0 RW	**ADDR0 Busy (ADDR0BSY):** When set forces HW to ACK only matching ADDR0 address byte and NACK in any subsequent bytes to indicate device is busy.
5	0x0 RO	**RSVD2:** Reserved.
4	0x0 RW/V/P	**Device Address0 Enable (ADDR0_EN):** When set, enables target logic to ACK ADDR0 address on the SMBus. Fuse load.
3	0x0 RW/V/P	**Host SMBus Address Enable (Host_SMBADDR_EN):** When set, enables HW to accept write cycles targeting address 10h. This bit must be set to '1' when SoC is the SMBus Segment Owner. Fuse load.
2	0x0 RW	**Default SMBus Address Enable (DEF_SMBADDR_EN):** When set, enables HW to ACK cycles targeting address C2h, which is the SMBus default address.
1	0x0 RW/V/P	**Device Address1 Enable (ADDR1_EN):** When set, enables target logic to ACK ADDR1 address on the SMBus. Fuse load.

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RW	**Target Enable (TGTEN):** Set to '1' by the FW after it has programmed the base address in the Target Data Ring Buffer and updated target policies. While in default state '0' all bytes will be NACKed on SMBus including the address byte of the enabled addresses. TGTEN applies to all target addresses: ADDR0_EN, ADDR1_EN, Host_SMBADDR_EN, DEF_SMBADDR_EN, and GPBRCTRL.EN.

49.3.22 GPBRCTRL—Offset 240h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 240h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/V/P	**Enable (EN):** This bit is set by FW to enable HW to respond to a block read command to address GPBRCTRL.GPTRADR and command GPBRCTRL.CMD. HW clears this bit after HW ACKs the command code (CMD) on the Block Read command if GPBRCTRL.HWCLRDIS is cleared.
30	0x0 RW	**PEC Enable (PECEN):** This bit is set by FW to indicate that HW must provide PEC at the end of the transaction to the external master.
29	0x0 RW	**HW Clear Disable (HWCLRDIS):** This bit is set by FW to disable the HW from clearing of the GPBRCTRL.EN bit. This functionality allows HW to continuously provide current data in the GPRDx registers to the external master without FW involvement. When this bit is set, HW must start sending data from byte 0 (of the buffer behind GPBRDBUF) when responding to a new Block Read cycle.
28	0x0 RW/V	**GPBR Buffer Contents Reset (BUFRST):** This bit is set by FW to reset (zero) the contents of the GPBR buffer ("GPBRDBUF—Offset 244h"). HW clears this bit after it has reset the GPBR buffer contents.
27	0x0 RW/V	**GPBR Buffer Pointer Reset (PTRRST):** This bit is set by FW to reset the pointer into the GPBR buffer ("GPBRDBUF—Offset 244h"). HW clears this bit after it has reset the GPBR buffer pointer.
26:24	0x0 RO	**RSVD0:** Reserved.
23:16	0x0 RW	**Byte Count (BC):** Byte count indicating how many bytes are programmed in the Generic Read Data buffer ("GPBRDBUF—Offset 244h") by FW. The maximum count is 32B, which is the maximum number of bytes that the buffer can hold. On the block read, after HW matches the address and command, HW sends the contents of this byte on the SMBus and then sends out those many bytes from the Generic Read Data Buffer starting from the LSB of GPBRDBUF0 register, i.e. the byte 0 of GPBRDBUF0.
15:8	0x0 RW	**Command (CMD):** Command byte of the block read command.
7:0	0x0 RW/V/P	**General Purpose Target Read Address (GPTRADR):** Target address of the externally initiated Block Read command cycle. Bit [0] of this register is the 'Enable' for this address. HW does not take any action based on the value of bit [0]. It is simply provided to FW for reading. Fuse load.

49.3.23 GPBRDBUF—Offset 244h

This register is used to load data into the generic programmable read data buffer. The buffer is used to provide a mechanism of supporting generic programmable reads (GPBR) by an external SMBus master under FW initiated flow. The data buffer is filled by FW initiating DW writes to this register. A hidden pointer always points to the next available buffer location reading and writing to GPBRDBUF cause the pointer to increment automatically.

Because the pointer auto-increments after each write, a read of GPBRDBUF will NOT return the most recently written data. Normal usage requires the buffer contents to be cleared prior to filling it with a new data payload, therefore a read (of the next 'empty' location) will return 0s (See also GPBRCTRL.BUFRST and GPBRCTRL.PTRRST).

HW provides read data payload starting from bit [7:0] of Dword0 of the buffer, then bit [15:8] of Dword0, and so on. All bytes must be programmed in the sequence to be sent out without gaps. HW will simply count the number of bytes indicated in the GPBRCTRL.BC register and start sending them out sequentially starting at byte 0 of Dword 0 until the byte count is decremented to 0.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [SMTBAR] + 244h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Data DWORD (GPBRD):** Reserved.

49.3.24 SMTARPCTRL—Offset 280h

The flags AV0 and AR0 refer to UDID0 and its corresponding target address TACTRL.ADDR0. The flags AV1 and AR1 refer to UDID1 and its corresponding target address TACTRL.ADDR1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 280h

Default: 00000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Disable 'Notify ARP Master' (NOTIFYD):** If asserted, the SMT will not issue a 'Notify ARP Master' command. Otherwise, if SMT is not the ARP Host, it is permitted to issue a 'Notify ARP Master' command.
30:7	0x0 RO	**RSVD0:** Reserved.
6	0x0 RW	**Address Resolved (AR1):** If asserted, the device's slave address has been resolved by the ARP Master.
5	0x0 RW	**Address Valid (AV1):** If asserted, the device's slave address is valid.
4	0x0 RW	**UDID1 Enable (UDID1E):** If cleared the SMT will not ACK or respond to ARP transactions directed to UDID1.
3	0x0 RO	**RSVD1:** Reserved
2	0x0 RW	**Address Resolved (AR0):** If asserted, the device's slave address has been resolved by the ARP Master.
1	0x0 RW	**Address Valid (AV0):** If asserted, the device's slave address is valid.
0	0x0 RW	**UDID0 Enable (UDID0E):** If cleared the SMT will not ACK or respond to ARP transactions directed to UDID0.

49.3.25 UDID0—Offset 290h

These bits are programmed by FW and are provided by the HW to external master when it initiates a Directed Get UDID Block Read command (with PEC) to UDID0's SMBus target address.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [SMTBAR] + 290h

Default: 8086000000000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:48	0x8086 RO	**Subsystem Vendor ID (SVID):** Subsystem Vendor ID Indicates that the device subsystem vendor is Intel.
47:32	0x0 RO	**Subsystem Device ID (SDID):** Subsystem Device ID.
31:0	0x0 RW/V/P	**Vendor Specific ID (VSID):** Vendor Specific ID must uniquely identify this device when dynamic, volatile addressing is enabled. At least 24 bits should be provided from fuses to uniquely identify over 16 million the SoC devices (without resorting to other revision fields). Fuse load

49.3.26 UUDID0—Offset 298h

These bits are programmed by FW and are provided by the HW to external master when it initiates a Directed Get UDID Block Read command (with PEC) to UDID0 SMBus target address.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [SMTBAR] + 298h

Default: 8108808600000024h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x81 RW	**Device Capabilities (DEVCAP):** Device Capabilities by default indicate that the device is a dynamic and volatile address device which supports PEC. FW may modify the capability, for instance to behave as a fixed-address device.
55:48	0x8 RO	**Version/Revision (RID):** Version/ Revision indicating UDID version 1 and Revision 0 of the silicon.
47:32	0x8086 RO	**Vendor ID (VID):** Vendor ID indicates that the device vendor is Intel.
31:16	0x0 RO	**Device ID (DID):** Device ID.
15:0	0x24 RW	**Interface (INTF):** Interface field indicates that the device supports SMBus 2.0 and its ASF capabilities bit set.

49.3.27 UDID1—Offset 2A0h

These bits are programmed by FW and are provided by the HW to external master when it initiates a Directed Get UDID Block Read command (with PEC) to UDID1 SMBus target address.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [SMTBAR] + 2A0h

Default: 8086000000000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:48	0x8086 RO	**Subsystem Vendor ID (SVID):** Subsystem Vendor ID Indicates that the device subsystem vendor is Intel.
47:32	0x0 RO	**Subsystem Device ID (SDID):** Subsystem Device ID.
31:0	0x0 RW/V/P	**Vendor Specific ID (VSID):** Vendor Specific ID must uniquely identify this device when dynamic, volatile addressing is enabled. At least 24 bits should be provided from fuses to uniquely identify over 16 million the SoC devices (without resorting to other revision fields). Fuse load

49.3.28 UUDID1—Offset 2A8h

These bits are programmed by FW and are provided by the HW to external master when it initiates a Directed Get UDID Block Read command (with PEC) to UDID1's SMBus target address.

Type: Memory Mapped I/O Register (Size: 64 bits)

BAR and Offset: [SMTBAR] + 2A8h

Default: 8108808600000024h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x81 RW	**Device Capabilities (DEVCAP):** Device Capabilities by default indicate that the device is a dynamic and volatile address device which supports PEC. FW may modify the capability, for instance to behave as a fixed-address device.
55:48	0x8 RO	**Version/Revision (RID):** Version/ Revision indicating UDID version 1 and Revision 0 of the silicon.
47:32	0x8086 RO	**Vendor ID (VID):** Vendor ID indicates that the device vendor is Intel.
31:16	0x0 RO	**Device ID (DID):** Device ID.
15:0	0x24 RW	**Interface (INTF):** Interface field indicates that the device supports SMBus 2.0 and its ASF capabilities bit set.

49.3.29 SPGT—Offset 300h

Setting of these timing parameters by FW, will affect both master and target timing on the physical.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 300h

Default: 00000005h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RW/V/P	**SMBus Speed (SPD):** Value to indicate what speed physical bus must operate. It is up to the system designer to ensure that all devices on the same SMBus segment are capable of operating at the programmed speed. • 00: Standard (80 kHz). • 01: Standard (100 kHz). • 10: Fast Mode (400 kHz). • 11: Fast Mode Plus (1 MHz).
29	0x0 RW	**Speed Lock (SPDLK):** FW sets this register if it overrides the settings of SPGT.SPD register. If this bit is set, HW must not load the SPGT.SPD from the soft strap.
28:20	0x0 RO	**RSVD0:** Reserved.
19:16	0x0 RW	**T-Hold Data (THDDAT):** The value in this field will be added to the Thddat timing parameter as defined in the SMBus 2.0 spec. • 0000: 0 Clocks (0ns). • 0001: 1 Clocks (10ns). • 0010: 2 Clocks (20ns). • ... • 1111: 15 Clocks (150ns).
15:12	0x0 RO	**RSVD1:** Reserved.
11:8	0x0 RW	**T-Setup Data (TSUDAT):** The value in this field will be added to the Tsudat timing parameter as defined in the SMBus 2.0 spec. • 0000: 0 Clocks (0ns). • 0001: 1 Clocks (10ns). • 0010: 2 Clocks (20ns). • ... • 1111: 15 Clocks (150ns).
7:0	0x5 RW	**De-Glitch (DG):** The value in this field defines the minimum de-glitch pulse that the de-glitch logic will reject from the SMBus clock and data lines. • 000000xx: No de-glitch. • 00000100: 4 Clocks (40ns glitch pulse). • 00000101: 5 Clocks (50ns glitch pulse). • ... • 11111111: 255 Clocks (2550ns glitch pulse).

49.3.30 SPMT—Offset 304h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 08080000h

BAR and Offset: [SMTBAR] + 304h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x8 RW	**Time high (Thigh):** The value in this field will be added/subtracted to the Thigh timing parameter as defined in the SMBus 2.0 spec. • 00000000: 0 Clock (0ns). • 00000001: -1 Clock (-10ns). • ... • 00000111: -7 Clocks (-70ns). • 00001000: 0 Clock (0ns). • 00001001: +1 Clock (+10ns). • ... • 11111111: +247 Clocks (+2,470ns). These are offsets that control the range of the nominal Thigh value in the PHY layers.
23:16	0x8 RW	**Time low (Tlow):** The value in this field will be added/subtracted to the Tlow timing parameter as defined in SMBus 2.0 spec. See Thigh field above for encoding.
15:12	0x0 RW	**Thdsta:** The time value in this field will be added/subtracted to the Thdsta timing parameter as defined in SMBus 2.0 spec. • 1111: -7 Clocks (-70ns). • 1110: -6 Clocks (-60ns). • ... • x000: 0 Clock (0ns). • 0001: +1 Clock (+10ns). • ... • 0111: +7 Clocks (+70ns).
11:8	0x0 RW	**Tsusta:** The time value in this field will be added/subtracted to the Tsusta timing parameter as defined in SMBus 2.0 spec. See Thdsta field above.
7:4	0x0 RW	**Tbuf:** The time value in this field will be added/subtracted to the Tbuf timing parameter as defined in SMBus 2.0 spec. See Thdsta field above.
3:0	0x0 RW	**Tsusto:** The time value in this field will be added/subtracted to the Tsusto timing parameter as defined in SMBus 2.0 spec. See Thdsta field above.

49.3.31 SPST—Offset 308h

These values should only be changed when the physical is idle. These timings are based off the 100-MHz PHY clock. A higher-frequency PHY clock will scale the timings accordingly.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 308h

Default: 00000000h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW	**Slave Tlow Extension (Slave_Tlow_Ext):** The time value in this field will be added to the SMBCLK Tlow extension timing parameter on a per bit basis. • 00000000: 0 Clock (0ns). • 00000001: 1 Clock (10ns). • ---- • 11111111: 255 Clocks (2,550ns). These Tlow extensions are only visible when set) Tlow:min as defined in the SMBus 2.0 spec. The slave will attempt to stretch the CLK on every bit, thus slowing down the entire bus segment, regardless of whether it is currently the target addressed by an external master.
23:12	0x0 RO	**RSVD0:** Reserved.
11:8	0x0 RW	**Slave Tsusta (Slave_Tsusta):** The time value in this field will be added/subtracted to the detection of Tsusta timing parameter as defined in SMBus 2.0 spec. • 1111: -7 Clocks (-70ns). • 1110: -6 Clocks (-60ns). • ---- • x000: 0 Clock (0ns). • 0001: +1 Clock (+10ns). • ---- • 0111: +7 Clocks (+70ns). These are offsets that control the range of the nominal Tsusta value detected as a slave the PHY layers.
7:4	0x0 RW	**Slave Tthdsta (Slave_Tthdsta):** The time value in this field will be added/subtracted to the detection of Thdsta timing parameter as defined in SMBus 2.0 spec. See Slave_Tsusta field above.
3:0	0x0 RW	**Slave Ttsusto (Slave_Ttsusto):** The time value in this field will be added/subtracted to the detection of Tsusto timing parameter as defined in SMBus 2.0 spec. See Slave_Tsusta field above.

49.3.32 SMBFT—Offset 30Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00002024h

BAR and Offset: [SMTBAR] + 30Ch

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Fair Flag (FF):** HW sets this bit when it has mastered a cycle by processing a descriptor in which 'FAIR' control bit was set. This flag when set is an internal state for the HW to wait longer before it attempts to master the next cycle on SMBus. The next cycle does not necessarily have to be descriptor-based or have the 'FAIR' bit set in the descriptor if it is descriptor-based. Mastering a cycle is defined as when HW attempts to do a SMBus block write and in the data phase following byte count it sees its own SMBus address (with RW bit = 1) on the SMBus. This is per MCTP spec. HW clears this flag after the expiry of SMBFT.SFIC.
30:16	0x0 RO	**RSVD0:** Reserved.
15:8	0x20 RW	**SMBus Start Delay (SSD):** This count is the number of ticks (in increments of 1us) that HW must count after SMBFT.FF is cleared before it can attempt to master another SMBus cycle. HW must look for transition of SMBFT.FF bit to transition from 1-)0 before it starts counting off this delay time. • 0h: Reserved (see note). • 1h: Reserved (see note). • 2h: 2us. • ... • FFh: 255us. ***Note:*** The base delay for this in each timing mode is defined as T_IDLE_DELAY in MCTP spec. For Standard Mode (100kHz) or lower SMBus operation the minimum is 31us. For Fast Mode (400kHz) the minimum is 16us. For Fast Mode Plus (1MHz) the minimum is 10us (MCTP over SMBus/I2C spec has no definition of timings for Fast Mode Plus). The 1us tick used by the HW to count off this delay is not internally generated in SMBus controller, hence the count could be off by a 1us tick therefore 1us guard band should be added to compensate for this.
7:0	0x24 RW	**SMBus Fair Idle Count (SFIC):** This count represents the minimum SMBus Idle Time (in increments of 1us) that the HW must detect after SMBus Stop is seen before clearing the SMBFT.FF register. • 0h: reserved (see note). • 1h: reserved (see note). • 2h: 2us. • ... • FFh: 255us. ***Note:*** The base delay for Fair Idle Count timings is designed to match the T_IDLE_WINDOW minimum plus T_BUF. For Standard Mode (100kHz) or lower SMBus operation the window is 30-60us to which must be added 4.7us (T_BUF). For Fast Mode (400kHz) the window is 5-20us to which must be added 1.3us (T_BUF). For Fast Mode Plus (1MHz) the window is 3us to which must be added 0.5us (T_BUF) (MCTP over SMBus/I2C spec has no definition of timings for Fast Mode Plus.). The 1us tick used by the HW to count off this delay is not internally generated in SMBus controller, hence the count could be off by a 1us tick therefore 1us guard band should be added to compensate for this.

49.3.33 CLTC—Offset 310h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000015E1h

BAR and Offset: [SMTBAR] + 310h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:4	0x15e RW	**Count (CNT):** FW sets this to the desired count that the HW must count while SMBus clock is low before flagging SMBus Clock Low Timeout. • 0h: Reserved (see note for BCLK). • 1h: Reserved (see note for BCLK). • Others: Count per BCLK. Default value is set to provide 35ms clock low timeout detection (for default 100us BCLK).
3	0x0 RO	**RSVD1:** Reserved.
2:0	0x1 RW	**Base Clock (BCLK):** FW programs this register to set the granularity of the count. The value in this register selects which timer ticks are used to count off the value programmed in CLTC.CNT register. • 000: 10us. • 001: 100us (default). • 010: 1ms. • 011: 10ms. • 100: 100ms. • Others: Reserved. The timer ticks are not internally generated by HW hence the count could be off by 1 timer tick.

49.3.34 DCLKGT—Offset 380h

By default, clock gating is enabled in HW. However in case clock gating has to be disabled in HW, FW can set these register bits to disable clock gating at the individual levels defined below.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 80000000h

BAR and Offset: [SMTBAR] + 380h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**Global Clock Gating Enable (GCGE):** This bit when set enables dynamic clock gating of the transaction, link, and PHY layers. When set, HW enables global clock gating and the other register policies are followed (DCLKGT bits [6:0]). When cleared, HW disables all clock gating and overrides the policies set by DCLKGT bits [6:0].
30:0	0x0 RO	**RSVD0:** Reserved.

49.3.35 SUSCHKB—Offset 384h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000011h

BAR and Offset: [SMTBAR] + 384h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD0:** Reserved.
5	0x0 RW	**NOA Select (NOASEL):** When set allows NOA signals of instance #2 of SMT to be viewed on NOA for debug purposes.
4	0x1 RW	**Auto Slave Clock Low Disable (ASCKLDIS):** When set disables the auto-clock low stretching by the slave.
3	0x0 RW	**25ms Timeout Detection Enable (TODE25):** When set bypasses the FW controlled Clock low timeout detection and reverts back to fixed 25ms Clock low timeout detection.
2	0x0 RO	**RSVD1:** Reserved.
1	0x0 RW	**Ignore R/W bit on Start Address (IRWST):** When set, HW ignores the value of R/W bit on the start address for all of its SMBus target addresses. HW just matches bits [7:1] to ACK the address. If this bit is clear and R/W bit does not match, HW will ACK the address on SMBus, but will NACK all further bytes until stop is seen. There is no FW notification for this transaction. Cycles targeting address C2h and 10h are also applicable to this policy.
0	0x1 RW	**Ignore R/W bit on Repeated Start Address (IRWRST):** When set, HW ignores the value of R/W bit on the repeated start address for an SMBus transaction. HW just matches bits [7:1] on repeated start address. Cycles targeting address C2h are also applicable to this policy.

49.3.36 DBCTRL—Offset 388h

Note: For FW: HW provides the FW a generic ability to bit bang on the SMBUs. It is however the responsibility of the FW that: HW DMA engine is completely stopped and no transactions are pending within HW, HW target interface is disabled, and SMBus is idle prior to bit banging. FW must guarantee all SMBus protocol and timing.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [SMTBAR] + 388h

Default: 00000003h

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Enable (EN):** This register is set by FW when it is bit banging on SMBus. This bit must always be set when FW is bit banging on SMBus. FW must clear this bit when it is done bit banging. It is recommended that FW first set the enable bit before it starts bit banging on the clock and data line.
30:2	0x0 RO	**RSVD0:** Reserved.
1	0x1 RW	**SMBus Clock (SMBCK):** This register provides ability for the FW to bit bang directly on the SMBus Clock pin. When FW writes a '0' to this register, HW will drive the SMBus Clock low.
0	0x1 RW	**SMBus Data (SMBDT):** This register provides ability for the FW to bit bang directly on the SMBus Data pin. When FW writes a '0' to this register, HW will drive the SMBus Data low.

49.3.37 DBSTS—Offset 38Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000300h

BAR and Offset: [SMTBAR] + 38Ch

SMTBAR Type: PCI Configuration Register (Size: 64 bits)
SMTBAR Reference: [B:0, D:18, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**RSVD0:** Reserved.
9	0x1 RO/V	**SMBus Clock (SMBCK):** This register shows the live state of SMBus clock signal as seen by HW from the buffer after HW deglitch and synchronization.
8	0x1 RO/V	**SMBus Data (SMBDT):** This register shows the live state of SMBus data signal as seen by HW from the buffer after HW deglitch and synchronization.
7	0x0 RO/C	**SMBus Clock Change (SMBCKC):** This register when set indicates that there was a 1-)0 or 0-)1 transition on SMBus clock line. This register is cleared by HW on reads by FW.
6	0x0 RO/C	**SMBus Data Change (SMBDC):** This register when set indicates that there was a 1-)0 or 0-)1 transition on SMBus data line. This register is cleared by HW on reads by FW.
5:3	0x0 RO	**RSVD1:** Reserved.
2:0	0x0 RO/V	**Last SMBus State (LSMBS):** This register reflects the last seen state of the SMBus. Since the SMBus state is dynamic, it is advised that FW use its judgment when interpreting this data. • 000: SMBus Idle. • 001: Start Seen. • 010: ACK Seen. • 011: Repeated Start Seen. • 100: Stop Seen. • 101: Reserved. • 110: Reserved. • 111: Reserved

§ §

50 SATA Controllers - B0, D(19, 20), F0

50.1 Introduction and Index

The host-accessible registers for the SATA Controllers are described here.

To determine the number of devices/functions available refer to the following:

- Intel Atom® Processor C3000 Product Family
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

50.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 19 (decimal), Function 0. Another set of configuration registers start at Bus 0, Device 20 (decimal), Function 0. The offset addresses are listed.

Table 50-1. Summary of PCI Configuration Registers—0/19 (or 20)/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	1C028086	"Identifiers (ID)—Offset 0h" on page 1879
4	2	0000	"Command (CMD)—Offset 4h" on page 1880
6	2	02B0	"Device Status (STS)—Offset 6h" on page 1881
8	1	00	"Revision ID (RID)—Offset 8h" on page 1882
9	1	01	"Programming Interface (PI)—Offset 9h" on page 1882
A	2	0106	"Class Code (CC)—Offset Ah" on page 1882
10	4	00000000	"MSI-X Table Base Address (MXTBA)—Offset 10h" on page 1883
18	4	00000001	"SCMDBA—Offset 18h" on page 1884
1C	4	00000001	"SCTLBA—Offset 1Ch" on page 1884
20	4	00000001	"AHCI Index Data Pair Base Address (AIDPBA)—Offset 20h" on page 1885
24	4	00000000	"AHCI Base Address (ABAR)—Offset 24h" on page 1886
34	1	80	"Capabilities Pointer (CAP)—Offset 34h" on page 1887
3C	2	0100	"Interrupt Information (INTR)—Offset 3Ch" on page 1887
70	2	A801	"PCI Power Management Capability ID (PID)—Offset 70h" on page 1887
72	2	4003	"PCI Power Management Capabilities (PC)—Offset 72h" on page 1888
74	2	0008	"PCI Power Management Control and Status (PMCS)—Offset 74h" on page 1889
80	2	7005	"Message Signaled Interrupt Identifier (MID)—Offset 80h" on page 1889
82	2	0000	"Message Signaled Interrupt Message Control (MC)—Offset 82h" on page 1890
84	4	00000000	"Message Signaled Interrupt Message Address (MA)—Offset 84h" on page 1890
88	2	0000	"Message Signaled Interrupt Message Data (MD)—Offset 88h" on page 1890
90	4	00000000	"Port Mapping Register (MAP)—Offset 90h" on page 1891
94	4	00000000	"Port Control and Status (PCS)—Offset 94h" on page 1893
9C	4	00000000	"SATA General Configuration (SATAGC)—Offset 9Ch" on page 1895
A0	1	00	"SATA Initialization Register Index (SIRI)—Offset A0h" on page 1896
A4	4	00000000	"SATA Initialization Register Data (SIRD)—Offset A4h" on page 1896
A8	4	00100012	"Serial ATA Capability Register 0 (SATACR0)—Offset A8h" on page 1897
AC	4	00000048	"Serial ATA Capability Register 1 (SATACR1)—Offset ACh" on page 1898
B0	2	0013	"FLR Capability ID (FLRCID)—Offset B0h" on page 1898
B4	2	0000	"FLR Control (FLRCTL)—Offset B4h" on page 1899
D2	2	0007	"MSI-X Message Control (MXC)—Offset D2h" on page 1900
D4	4	00000000	"MSI-X Table Offset / Table BIR (MXT)—Offset D4h" on page 1900
D8	4	00000000	"MSI-X PBA Offset / PBA BIR (MXP)—Offset D8h" on page 1900
E0	4	00000000	"BIST FIS Control/Status (BFCS)—Offset E0h" on page 1901

Table 50-1. Summary of PCI Configuration Registers—0/19 (or 20)/0 (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
E4	4	00000000	"BIST FIS Transmit Data 1 (BFTD1)—Offset E4h" on page 1903
E8	4	00000000	"BIST FIS Transmit Data 2 (BFTD2)—Offset E8h" on page 1903
F8	4	08000FB1	"Manufacturing ID (MFID)—Offset F8h" on page 1903

50.1.2 Host Memory Space—MXTBA

An index of the registers that are accessible in Host Memory Space is shown here.

Table 50-2. Summary of Memory Mapped I/O Registers—MXTBA

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
4	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
8	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
10	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
14	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
18	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
20	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
24	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
28	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
30	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
34	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
38	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
40	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
44	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
48	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
50	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
54	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
58	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
60	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
64	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
68	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905
70	4	00000000	"MSI-X Table Entries n Message Lower Address (MXTEnMLA)" on page 1904
74	4	00000000	"MSI-X Table Entries n Message Upper Address (MXTEnMUA)" on page 1904
78	4	00000000	"MSI-X Table Entries n Message Data (MXTEnMD)" on page 1905

50.1.3 Host Memory Space—ABAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 50-3. Summary of Memory Mapped I/O Registers—ABAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	FF36FF07	"HBA Capabilities (GHC_CAP)—Offset 0h" on page 1906
4	4	80000000	"HBA Capabilities (GHC_CAP)—Offset 0h" on page 1906
8	4	00000000	"Interrupt Status Register (IS)—Offset 8h" on page 1909
C	4	00000000	"Ports Implemented (GHC_PI)—Offset Ch" on page 1910
10	4	00010300	"AHCI Version (VS)—Offset 10h" on page 1911
20	4	07010000	"Enclosure Management Control (EM_CTL)—Offset 20h" on page 1912
24	4	0000003C	"HBA Capabilities Extended (GHC_CAP2)—Offset 24h" on page 1914
A0	4	00000048	"Vendor Specific (VSP)—Offset A0h" on page 1915
C0	4	00311C02	"RAID Platform ID (RPID)—Offset C0h" on page 1917
C8	2	003F	"SW Feature Mask (SFM)—Offset C8h" on page 1918
100	4	00000000	"Port [0-7] Command List Base Address (PxCLB0)—Offset 100h" on page 1919
104	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU0)—Offset 104h" on page 1919
108	4	00000000	"Port [0-7] FIS Base Address (PxFB0)—Offset 108h" on page 1920
10C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU0)—Offset 10Ch" on page 1920
110	4	00000000	"Port [0-7] Interrupt Status (PxIS0)—Offset 110h" on page 1921
114	4	00000000	"Port [0-7] Interrupt Enable (PxIE0)—Offset 114h" on page 1923
118	4	00000004	"Port [0-7] Command (PxCMD0)—Offset 118h" on page 1924
128	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS0)—Offset 128h" on page 1926
12C	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL0)—Offset 12Ch" on page 1926
130	4	00000000	"Port [0-7] Serial ATA Error (PxSERR0)—Offset 130h" on page 1927
134	4	00000000	"Port [0-7] Serial ATA Active (PxSACT0)—Offset 134h" on page 1927
138	4	00000000	"Port [0-7] Commands Issued (PxCI0)—Offset 138h" on page 1927
13C	4	00000000	"Port [0-7] SNotification (PxSNTF0)—Offset 13Ch" on page 1928
180	4	00000000	"Port [0-7] Command List Base Address (PxCLB1)—Offset 180h" on page 1928
184	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU1)—Offset 184h" on page 1928
188	4	00000000	"Port [0-7] FIS Base Address (PxFB1)—Offset 188h" on page 1929
18C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU1)—Offset 18Ch" on page 1929
190	4	00000000	"Port [0-7] Interrupt Status (PxIS1)—Offset 190h" on page 1930
194	4	00000000	"Port [0-7] Interrupt Enable (PxIE1)—Offset 194h" on page 1932
198	4	00000004	"Port [0-7] Command (PxCMD1)—Offset 198h" on page 1933
1A8	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS1)—Offset 1A8h" on page 1935
1AC	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL1)—Offset 1ACh" on page 1935
1B0	4	00000000	"Port [0-7] Serial ATA Error (PxSERR1)—Offset 1B0h" on page 1936
1B4	4	00000000	"Port [0-7] Serial ATA Active (PxSACT1)—Offset 1B4h" on page 1936
1B8	4	00000000	"Port [0-7] Commands Issued (PxCI1)—Offset 1B8h" on page 1936

Table 50-3. Summary of Memory Mapped I/O Registers—ABAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
1BC	4	00000000	"Port [0-7] SNotification (PxSNTF1)—Offset 1BCh" on page 1937
200	4	00000000	"Port [0-7] Command List Base Address (PxCLB2)—Offset 200h" on page 1937
204	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU2)—Offset 204h" on page 1937
208	4	00000000	"Port [0-7] FIS Base Address (PxFB2)—Offset 208h" on page 1938
20C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU2)—Offset 20Ch" on page 1938
210	4	00000000	"Port [0-7] Interrupt Status (PxIS2)—Offset 210h" on page 1939
214	4	00000000	"Port [0-7] Interrupt Enable (PxIE2)—Offset 214h" on page 1941
218	4	00000004	"Port [0-7] Command (PxCMD2)—Offset 218h" on page 1942
228	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS2)—Offset 228h" on page 1944
22C	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL2)—Offset 22Ch" on page 1944
230	4	00000000	"Port [0-7] Serial ATA Error (PxSERR2)—Offset 230h" on page 1945
234	4	00000000	"Port [0-7] Serial ATA Active (PxSACT2)—Offset 234h" on page 1945
238	4	00000000	"Port [0-7] Commands Issued (PxCI2)—Offset 238h" on page 1945
23C	4	00000000	"Port [0-7] SNotification (PxSNTF2)—Offset 23Ch" on page 1946
280	4	00000000	"Port [0-7] Command List Base Address (PxCLB3)—Offset 280h" on page 1946
284	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU3)—Offset 284h" on page 1946
288	4	00000000	"Port [0-7] FIS Base Address (PxFB3)—Offset 288h" on page 1947

Table 50-3. Summary of Memory Mapped I/O Registers—ABAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
28C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU3)—Offset 28Ch" on page 1947
290	4	00000000	"Port [0-7] Interrupt Status (PxIS3)—Offset 290h" on page 1948
294	4	00000000	"Port [0-7] Interrupt Enable (PxIE3)—Offset 294h" on page 1950
298	4	00000004	"Port [0-7] Command (PxCMD3)—Offset 298h" on page 1951
2A8	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS3)—Offset 2A8h" on page 1953
2AC	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL3)—Offset 2ACh" on page 1953

Table 50-3. Summary of Memory Mapped I/O Registers—ABAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
2B0	4	00000000	"Port [0-7] Serial ATA Error (PxSERR3)—Offset 2B0h" on page 1954
2B4	4	00000000	"Port [0-7] Serial ATA Active (PxSACT3)—Offset 2B4h" on page 1954
2B8	4	00000000	"Port [0-7] Commands Issued (PxCI3)—Offset 2B8h" on page 1954
2BC	4	00000000	"Port [0-7] SNotification (PxSNTF3)—Offset 2BCh" on page 1955
300	4	00000000	"Port [0-7] Command List Base Address (PxCLB4)—Offset 300h" on page 1955
304	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU4)—Offset 304h" on page 1955
308	4	00000000	"Port [0-7] FIS Base Address (PxFB4)—Offset 308h" on page 1956
30C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU4)—Offset 30Ch" on page 1956
310	4	00000000	"Port [0-7] Interrupt Status (PxIS4)—Offset 310h" on page 1957
314	4	00000000	"Port [0-7] Interrupt Enable (PxIE4)—Offset 314h" on page 1959
318	4	00000004	"Port [0-7] Command (PxCMD4)—Offset 318h" on page 1960
328	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS4)—Offset 328h" on page 1962
32C	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL4)—Offset 32Ch" on page 1962
330	4	00000000	"Port [0-7] Serial ATA Error (PxSERR4)—Offset 330h" on page 1963
334	4	00000000	"Port [0-7] Serial ATA Active (PxSACT4)—Offset 334h" on page 1963
338	4	00000000	"Port [0-7] Commands Issued (PxCI4)—Offset 338h" on page 1963
33C	4	00000000	"Port [0-7] SNotification (PxSNTF4)—Offset 33Ch" on page 1964
380	4	00000000	"Port [0-7] Command List Base Address (PxCLB5)—Offset 380h" on page 1964
384	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU5)—Offset 384h" on page 1964
388	4	00000000	"Port [0-7] FIS Base Address (PxFB5)—Offset 388h" on page 1965
38C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU5)—Offset 38Ch" on page 1965
390	4	00000000	"Port [0-7] Interrupt Status (PxIS5)—Offset 390h" on page 1966
394	4	00000000	"Port [0-7] Interrupt Enable (PxIE5)—Offset 394h" on page 1968
3A8	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS5)—Offset 3A8h" on page 1969
3AC	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL5)—Offset 3ACh" on page 1969
3B0	4	00000000	"Port [0-7] Serial ATA Error (PxSERR5)—Offset 3B0h" on page 1970
3B4	4	00000000	"Port [0-7] Serial ATA Active (PxSACT5)—Offset 3B4h" on page 1970
3B8	4	00000000	"Port [0-7] Commands Issued (PxCI5)—Offset 3B8h" on page 1970
3BC	4	00000000	"Port [0-7] SNotification (PxSNTF5)—Offset 3BCh" on page 1971
3C4	4	1E022852	"Port [0-7] Device Sleep (PxDEVSLP5)—Offset 3C4h" on page 1972
400	4	00000000	"Port [0-7] Command List Base Address (PxCLB6)—Offset 400h" on page 1972
404	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU6)—Offset 404h" on page 1973
408	4	00000000	"Port [0-7] FIS Base Address (PxFB6)—Offset 408h" on page 1973
40C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU6)—Offset 40Ch" on page 1973
410	4	00000000	"Port [0-7] Interrupt Status (PxIS6)—Offset 410h" on page 1974
414	4	00000000	"Port [0-7] Interrupt Enable (PxIE6)—Offset 414h" on page 1976
418	4	00000004	"Port [0-7] Command (PxCMD6)—Offset 418h" on page 1977

Table 50-3. Summary of Memory Mapped I/O Registers—ABAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
420	4	0000007F	"Port [0-7] Task File Data (PxTFD6)—Offset 420h" on page 1979
424	4	FFFFFFFF	"Port [0-7] Signature (PxSIG6)—Offset 424h" on page 1979
428	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS6)—Offset 428h" on page 1980
42C	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL6)—Offset 42Ch" on page 1980
430	4	00000000	"Port [0-7] Serial ATA Error (PxSERR6)—Offset 430h" on page 1981
434	4	00000000	"Port [0-7] Serial ATA Active (PxSACT6)—Offset 434h" on page 1981
438	4	00000000	"Port [0-7] Commands Issued (PxCI6)—Offset 438h" on page 1981
43C	4	00000000	"Port [0-7] SNotification (PxSNTF6)—Offset 43Ch" on page 1982
444	4	1E022852	"Port [0-7] Device Sleep (PxDEVSLP6)—Offset 444h" on page 1982
480	4	00000000	"Port [0-7] Command List Base Address (PxCLB7)—Offset 480h" on page 1983
484	4	00000000	"Port [0-7] Command List Base Address Upper 32-bits (PxCLBU7)—Offset 484h" on page 1983
488	4	00000000	"Port [0-7] FIS Base Address (PxFB7)—Offset 488h" on page 1984
48C	4	00000000	"Port [0-7] FIS Base Address Upper 32-bits (PxFBU7)—Offset 48Ch" on page 1984
490	4	00000000	"Port [0-7] Interrupt Status (PxIS7)—Offset 490h" on page 1985
494	4	00000000	"Port [0-7] Interrupt Enable (PxIE7)—Offset 494h" on page 1987
498	4	00000004	"Port [0-7] Command (PxCMD7)—Offset 498h" on page 1988
4A0	4	0000007F	"Port [0-7] Task File Data (PxTFD7)—Offset 4A0h" on page 1990
4A4	4	FFFFFFFF	"Port [0-7] Signature (PxSIG7)—Offset 4A4h" on page 1990
4A8	4	00000000	"Port [0-7] Serial ATA Status (PxSSTS7)—Offset 4A8h" on page 1991
4AC	4	00000000	"Port [0-7] Serial ATA Control (PxSCTL7)—Offset 4ACh" on page 1991
4B0	4	00000000	"Port [0-7] Serial ATA Error (PxSERR7)—Offset 4B0h" on page 1992
4B4	4	00000000	"Port [0-7] Serial ATA Active (PxSACT7)—Offset 4B4h" on page 1992
4B8	4	00000000	"Port [0-7] Commands Issued (PxCI7)—Offset 4B8h" on page 1992
4BC	4	00000000	"Port [0-7] SNotification (PxSNTF7)—Offset 4BCh" on page 1993
580	4	00000000	"Enclosure Management Message Format (EM_MF)—Offset 580h" on page 1993
584	4	00000000	"Enclosure Management LED (EM_LED)—Offset 584h" on page 1994

50.2 Registers in Configuration Space

50.2.1 Identifiers (ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 0h

Default: 1C028086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x1c02 RO	**Device ID (DID):** The specific value is dependent on config bits and fuses.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates the company vendor as Intel.

50.2.2 Command (CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD0:** Reserved.
10	0x0 RW	**Interrupt Disable (ID):** This disables pin-based INTx# interrupts. This bit has no effect on MSI operation. When set, internal INTx# will not be generated. When cleared, internal INTx# are generated if there is an interrupt and MSI is not enabled.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Reserved.
8	0x0 RW	**SERR# Enable (SEE):** When set to 1, the HBA is allowed to generate SERR# on DPD or SATAGC.URD event that is enabled for SERR# generation. When cleared to 0, it is not.
7	0x0 RO	**Wait Cycle Enable (WCC):** Reserved.
6	0x0 RW	**Parity Error Response Enable (PEE):** When set, the SATA Controller will corrupt the outbound DATA FIS CRC if a forwarded data parity error is indicated.
5	0x0 RO	**VGA Palette Snooping Enable (VGA):** Reserved.
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Reserved.
3	0x0 RO	**Special Cycle Enable (SCE):** Reserved.
2	0x0 RW	**Bus Master Enable (BME):** Controls the SATA Controller's ability to act as a master for data transfers. This bit does not impact the generation of completions for split transaction commands.
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the SATA Controller's target memory space (for AHCI).
0	0x0 RW	**I/O Space Enable (IOSE):** Controls access to the SATA Controller's target I/O space.

50.2.3 Device Status (STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 6h

Default: 02B0h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**Detected Parity Error (DPE):** Set when the SATA Controller detects a parity error on its interface.
14	0x0 RW/1C	**Signaled System Error (SSE):** Set when SATA Controller generates an SERR#.
13	0x0 RW/1C	**Received Master-Abort Status (RMA):** Set when the SATA Controller receives a master abort to a cycle it generated.
12	0x0 RW/1C	**Received Target-Abort Status (RTA):** Set when the SATA Controller receives a target abort to a cycle it generated.
11	0x0 RW/1C	**Signaled Target-Abort Status (STA):** This bit must be set by a target device whenever it terminates a transaction with Target-Abort. Devices that will never signal Target-Abort do not need to implement this bit.
10:9	0x1 RO	**DEVSEL# Timing Status (DEVT):** Controls the device select time for the SATA Controller's PCI interface.
8	0x0 RW/1C	**Master Data Parity Error Detected (DPD):** Set when the SATA Controller, as a master, either detects a parity error or sees the parity error line asserted, and the parity error response bit (bit 6 of the command register) is set. This bit can only be set on read completions received from the backbone where there is a parity error.
7	0x1 RO	**Fast Back-to-Back Capable (FBC):** Reserved.
6	0x0 RO	**RSVD0:** Reserved.
5	0x1 RO	**66 MHz Capable (RSV):** Reserved.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list.
3	0x0 RO	**Interrupt Status (IS):** Reflects the state of INTx# messages, IRQ14 or IRQ15. This bit is set when the interrupt is to be asserted. This bit is a 0 after the interrupt is cleared.
2:0	0x0 RO	**RSVD1:** Reserved.

50.2.4 Revision ID (RID)—Offset 8h

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:19 or 20, F:0] + 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Revision ID (RID):** Indicates stepping of the host controller hardware.

50.2.5 Programming Interface (PI)—Offset 9h

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:19 or 20, F:0] + 9h

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RO	**Interface (IF):** If CC.SCC=06h(AHCI mode), it indicates that this is an AHCI HBA that has a major revision of 1 (as specified in the AHCI Version register). If CC.SCC=04h(RAID mode), it indicates that there is no programming interface(IF=00h). Internally, under this condition, the SATA controller is in native mode and its I/O spaces are only accessible through the I/O BARs.

50.2.6 Class Code (CC)—Offset Ah

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + Ah

Default: 0106h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO	**Base Class Code (BCC):** Indicates that this is a mass storage device.
7:0	0x6 RO	**Sub Class Code (SCC):** The value reported in this field is dependent on SATAGC.SMS and various fuses and configuration bits.

50.2.7 MSI-X Table Base Address (MXTBA)—Offset 10h

This BAR is used to allocate 32K, 16K or 8K Memory space for the MSI-X Table. The Memory space size is determined by BIOS by making bit-14 and bit-13 Read-Only '1' or Read-Write '0' based on SATAGC.MSS[1:0].

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 10h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:15	0x0 RW	**Base Address (BA):** Base address of memory space.
14	0x0 RW	**Base Address Bit 14 (BAB14):** When SATAGC.MSS [1:0]=00, this bit is Read Only '0' else it's Read Write '0'.
13	0x0 RW	**Base Address Bit 13 (BAB13):** When SATAGC.MSS [1:0]=00 or 01, this bit is Read Only '0' else it's Read Write '0'.
12:4	0x0 RO	**RSVD0:** Reserved.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not prefetchable.
2:1	0x0 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 32-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for Memory space.

50.2.8 SCMDBA—Offset 18h

BAR2 register define a 8-byte I/O space but this space is not implemented. Accesses to this space will get master abort.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 18h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:3	0x0 RW	**Base Address (BAR):** Base address of the I/O space.
2:1	0x0 RO	**RSVD1:** Reserved.
0	0x1 RO	**Resource Type Indicator (RTE):** Indicates a request for IO space.

50.2.9 SCTLBA—Offset 1Ch

BAR3 register define a 4-byte I/O space but this space is not implemented. Accesses to this space will get master abort.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 1Ch

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:2	0x0 RW	**Base Address (BAR):** Base address of the I/O space.
1	0x0 RO	**RSVD1:** Reserved.
0	0x1 RO	**Resource Type Indicator (RTE):** Indicates a request for IO space.

50.2.10 AHCI Index Data Pair Base Address (AIDPBA)—Offset 20h

This BAR is used to allocate I/O space for the AHCI index/data pair mechanism.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 20h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:5	0x0 RW	**Base Address (BA):** Base address of the I/O space.
4:1	0x0 RO	**RSVD1:** Reserved.
0	0x1 RO	**Resource Type Indicator (RTE):** Indicates a request for IO space.

50.2.11 AHCI Base Address (ABAR)—Offset 24h

This register represents a memory BAR allocating space for the AHCI memory registers.

Note: Bit [31:16] of this register must be programmed to a value greater than 0 to ensure the memory is mapped to an address of 1 Mbyte and greater (i.e. ABAR must be 00010000h or greater). Otherwise, memory cycle targeting the ABAR range may not be accepted.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 24h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RW	**Base Address (BA):** Base address of register memory space.
18	0x0 RW	**Base Address Bit 18 (BAB18):** When SATAGC.ASSEL[2:0] selects an ABAR size bigger than 256K, this bit is Read Only '0' else it's Read Write '0'.
17	0x0 RW	**Base Address Bit 17 (BAB17):** When SATAGC.ASSEL[2:0] selects an ABAR size bigger than 128K, this bit is Read Only '0' else it's Read Write '0'.
16	0x0 RW	**Base Address Bit 16 (BAB16):** When SATAGC.ASSEL[2:0] selects an ABAR size bigger than 64K, this bit is Read Only '0' else it's Read Write '0'.
15	0x0 RW	**Base Address Bit 15 (BAB15):** When SATAGC.ASSEL[2:0] selects an ABAR size bigger than 32K, this bit is Read Only '0' else it's Read Write '0'.
14	0x0 RW	**Base Address Bit 14 (BAB14):** When SATAGC.ASSEL[2:0] selects an ABAR size bigger than 16K, this bit is Read Only '0' else it's Read Write '0'.
13:11	0x0 RW	**Base Address Bit 13-11 (BAB1311):** When SATAGC.ASSEL[2:0] selects an ABAR size bigger than 2K, this bit is Read Only '0' else it's Read Write '0'.
10:4	0x0 RO	**RSVD0:** Reserved.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not prefetchable
2:1	0x0 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 32-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

50.2.12 Capabilities Pointer (CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:19 or 20, F:0] + 34h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x80 RW/L	**Capability Pointer (CP):** Indicates that the first capability pointer offset is offset 80h (the Message Signaled Interrupt capability). The following capability structures are linked by default: • (CAP.CP -) 80h • (MSI) -) D0h • (MSI-X)-) 70h • (PCI Power) -) A8h • (SATA) -) 00h end.

50.2.13 Interrupt Information (INTR)—Offset 3Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RW/O	**Interrupt Pin (IPIN):** This register tells which interrupt pin the device function uses. • A value of 1 corresponds to INTA#. • A value of 2 corresponds to INTB#. • A value of 3 corresponds to INTC#. • A value of 4 corresponds to INTD#. This register is not reset by FLR.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this register. Interrupt Line register is not reset by FLR.

50.2.14 PCI Power Management Capability ID (PID)—Offset 70h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 70h

Default: A801h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0xa8 RW/L	**Next Capability (NEXT):** A8h is location of the Serial ATA Capability structure. The RW/L register attribute allows for flexibility in determining the capability structure available in this PCI function. Refer to SATAGC.REGLOCK description in order to lock the register to become RO. This register is not reset by FLR.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management capability.

50.2.15 PCI Power Management Capabilities (PC)—Offset 72h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 72h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME_Support:** The default value is 01000 which indicates PME# can be generated from the D3HOT state in the SATA controller.
10	0x0 RO	**D2_Support:** The D2 state is not supported.
9	0x0 RO	**D1_Support:** The D1 state is not supported.
8:6	0x0 RO	**Aux_Current:** PME# from D3COLD state is not supported, therefore this field is 000b.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates that no device-specific initialization is required.
4	0x0 RO	**RSVD0:** Reserved
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

50.2.16 PCI Power Management Control and Status (PMCS)—Offset 74h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 74h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**PME Status (PMES):** This bit is set when a PME event is to be requested, and if this bit is set and PMEE is set, a PME# will be generated. This register field is not reset by FLR.
14:9	0x0 RO	**RSVD0:** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, the SATA controller generates PME# from D3HOT on a wake event. Note: Software is advised to clear PMEE together with PMES prior to changing CC.SCC thru SATAGC.SMS. This register field is not reset by FLR.
7:4	0x0 RO	**RSVD1:** Reserved.
3	0x1 RO	**No Soft Reset (NSFRST):** A 1 indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. Configuration context is preserved.
2	0x0 RO	**RSVD2:** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the SATA Controller and to set a new power state. The values are: • 00 = D0 state. • 11 = D3HOT state.

50.2.17 Message Signaled Interrupt Identifier (MID)—Offset 80h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 80h

Default: 7005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x70 RW/L	**Next Pointer (NEXT):** Indicates the next item in the list is the PCI power management pointer.
7:0	0x5 RO	**Capability ID (CID):** Capabilities ID indicates MSI.

50.2.18 Message Signaled Interrupt Message Control (MC)—Offset 82h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 82h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved.
7	0x0 RO	**64 Bit Address Capable (C64):** Capable of generating a 32-bit message only.
6:4	0x0 RO	**Multiple Message Enable (MME):** When this field is cleared to 000 (and MSIE is set), only a single MSI message will be generated for all SATA ports, and bits [15:0] of the message vector will be driven from MD[15:0].
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not supported.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and traditional interrupt pins are not used to generate interrupts.

50.2.19 Message Signaled Interrupt Message Address (MA)—Offset 84h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DWORD aligned.
1:0	0x0 RO	**RSVD0:** Reserved.

50.2.20 Message Signaled Interrupt Message Data (MD)—Offset 88h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + 88h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the lower word of the data bus of the MSI memory write transaction.

50.2.21 Port Mapping Register (MAP)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved.
23	0x0 RW/O	**SATA Port 7 Disable (SPD7):** Similar to SPD0 but for port 7. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. PCIe/SATA muxing for port 7 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 7 physically.
22	0x0 RW/O	**SATA Port 6 Disable (SPD6):** Similar to SPD0 but for port 6. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. PCIe/SATA muxing for port 6 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 6 physically.
21	0x0 RW/O	**SATA Port 5 Disable (SPD5):** Similar to SPD0 but for port 5. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. PCIe/SATA muxing for port 5 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 5 physically.
20	0x0 RW/O	**SATA Port 4 Disable (SPD4):** Similar to SPD0 but for port 4. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. PCIe/SATA muxing for port 4 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 4 physically.
19	0x0 RW/O	**SATA Port 3 Disable (SPD3):** Similar to SPD0 but for port 3. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. • 1. Fuse FFSATA7 (disable port 2 and 3). • 2. Fuse FFSATA8 (disable port 1 and 3). • 3. PCIe/SATA muxing for port 3 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 3 physically.
18	0x0 RW/O	**SATA Port 2 Disable (SPD2):** Similar to SPD0 but for port 2. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. • 1. Fuse FFSATA7 (disable port 2 and 3). • 2. PCIe/SATA muxing for port 3 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 3 physically.
17	0x0 RW/O	**SATA Port 1 Disable (SPD1):** Similar to SPD0 but for port 1. This bit is RO-one if ANY of the fuse/strap/GPIO condition below is true else this bit is RW-zero. • 1. Fuse FFSATA8 (disable port 1 and 3). • 2. PCIe/SATA muxing for port 3 based on fuses, soft straps and GPIO does not select SATA. This bit is only applicable to project(s): that has port 1 physically.
16	0x0 RW/O	**SATA Port 0 Disable (SPD0):** A 1 prevents the SATA port from being enabled via config PCS.PxE. Write of 1 to PCS.PxE has no effect when the corresponding SPD[x] bit is 1. In preventing a port(s) from being enabled, BIOS shall first configure MAP.SPDx. And only then BIOS configures the PCS.PxE. This field is not reset by FLR. This bit is only applicable to project(s): that has port 0 physically.
15:8	0x0 RO	**RSVD1:** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Port Clock Disable (PCD):** When any of these bits is set to 1, the backbone clock driven to the associated port logic is gated and will not toggle. When this bit is cleared to 0, all clocks to the associated port logic will operate normally. Assignment of the bits is: • Bit 7: Port 7, this bit is applicable to projects: that has port 7 physically • Bit 6: Port 6, this bit is only applicable to project(s): that has port 6 physically • Bit 5: Port 5, this bit is only applicable to project(s): that has port 5 physically • Bit 4: Port 4, this bit is only applicable to project(s): that has port 4 physically • Bit 3: Port 3, this bit is only applicable to project(s): that has port 3 physically • Bit 2: Port 2, this bit is only applicable to project(s): that has port 2 physically • Bit 1: Port 1, this bit is only applicable to project(s): that has port 1 physically • Bit 0: Port 0, this bit is only applicable to project(s): That has port 0 physically. If a particular port is not available, software shall set the corresponding bit to 1. Software can also set the corresponding bit(s) to 1 after disabling particular port(s). Software cannot set the PCD[port x]=1 if the corresponding config PCS.PxE=1 or AHCI MMIO GHC.PI[x]=1.

50.2.22 Port Control and Status (PCS)—Offset 94h

By default, the SATA ports are set (by hardware) to the disabled state (e.g. bits[5:0] == '0') as a result of an initial power on reset. When enabled by software, the ports can transition between the on, partial, and slumber states and can detect devices. When disabled, the port is in the off state and cannot detect any devices. This register is not reset by FLR.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved.
23	0x0 RO	**Port 7 Present (P7P):** Same as P0P, except for port 7. This bit is only applicable to project(s): That has port 7 physically.
22	0x0 RO	**Port 6 Present (P6P):** Same as P0P, except for port 6. This bit is only applicable to project(s): That has port 6 physically.
21	0x0 RO	**Port 5 Present (P5P):** Same as P0P, except for port 5. This bit is only applicable to project(s): That has port 5 physically.
20	0x0 RO	**Port 4 Present (P4P):** Same as P0P, except for port 4. This bit is only applicable to project(s): That has port 4 physically.
19	0x0 RO	**Port 3 Present (P3P):** Same as P0P, except for port 3. This bit is only applicable to project(s): That has port 3 physically.
18	0x0 RO	**Port 2 Present (P2P):** Same as P0P, except for port 2. This bit is only applicable to project(s): That has port 2 physically.
17	0x0 RO	**Port 1 Present (P1P):** Same as P0P, except for port 1. This bit is only applicable to project(s): That has port 1 physically.
16	0x0 RO	**Port 0 Present (P0P):** When set, the SATA controller has detected the presence of a device on port 0. It may change at any time. Clearing P0E bit leads to clearing of this bit after implementation delay. ***Note:*** For system software that intends to clear all PCS.PxE bits that are previously 1 to 0 and then to 1 again in two consecutive write cycles, software shall poll on this bit being 0 before setting P0E bit to 1. This bit is only applicable to project(s): That has port 0 physically.
15:8	0x0 RO	**RSVD1:** Reserved.
7	0x0 RW	**Port 7 Enabled (P7E):** When MAP.SPD[7] is 1, this bit is reserved and is read-only 0. Otherwise if none of the above is true, this field is RW and the definition of this bit is the same as P0E, except for port 7. This bit takes precedence over P7CMD.SUD. This bit is only applicable to project(s): That has port 7 physically.
6	0x0 RW	**Port 6 Enabled (P6E):** When MAP.SPD[6] is 1, this bit is reserved and is read-only 0. Otherwise if none of the above is true, this field is RW and the definition of this bit is the same as P0E, except for port 6. This bit takes precedence over P6CMD.SUD. This bit is only applicable to project(s): That has port 6 physically.
5	0x0 RW	**Port 5 Enabled (P5E):** When MAP.SPD[5] is 1, this bit is reserved and is read-only 0. Otherwise if none of the above is true, this field is RW and the definition of this bit is the same as P0E, except for port 5. This bit takes precedence over P5CMD.SUD. This bit is only applicable to project(s): That has port 5 physically.
4	0x0 RW	**Port 4 Enabled (P4E):** When MAP.SPD[4] is 1, this bit is reserved and is read-only 0. Otherwise if none of the above is true, this bit is RW and same as P0E but for port 4 and takes precedence over P4CMD.SUD. This bit is only applicable to project(s): That has port 4 physically.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW	**Port 3 Enabled (P3E):** When MAP.SPD[3] is 1, this bit is reserved and is read-only 0. Otherwise if none of the above is true, this bit is RW and same as P0E but for port 3 and takes precedence over P3CMD.SUD. This bit is only applicable to project(s): That has port 3 physically.
2	0x0 RW	**Port 2 Enabled (P2E):** When MAP.SPD[2] is 1, this bit is reserved and is read-only 0. Otherwise if none of the above is true, this bit is RW and same as P0E but for port 2 and takes precedence over P2CMD.SUD. This bit is only applicable to project(s): That has port 2 physically.
1	0x0 RW	**Port 1 Enabled (P1E):** When MAP.SPD[1] is 1, this bit is reserved and read-only 0. Otherwise if none of the above is true, this bit is RW and same as P0E but for port 1 and takes precedence over P1CMD.SUD. This bit is only applicable to project(s): That has port 1 physically.
0	0x0 RW	**Port 0 Enabled (P0E):** When MAP.SPD[0] is 1, this bit is reserved and read-only 0. When set, the port is enabled. When cleared, the port is disabled. When enabled, the port can transition between the on, partial, and slumber states and can detect devices. When disabled, the port is in the off state and cannot detect any devices. This bit takes precedence over P0CMD.SUD.

50.2.23 SATA General Configuration (SATAGC)—Offset 9Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/O	**Register Lock (REGLOCK):** BIOS can set this bit to 1 to lock the following registers with RW/L attribute: • CAP • CP • MID.NEXT • PIE.NEXT • SATACR0.NEXT. Once locked the register attribute of above list changes from RW/L to RO holding the existing value. This field is not reset by FLR.
30:17	0x0 RO	**RSVD0:** Reserved.
16	0x0 RW	**SATA Mode Select (SMS):** Software (SW) programs these bits to control the mode in which the SATA HBA should operate: • 0b = AHCI mode. • 1b = RAID mode. This register field is not reset by FLR.
15	0x0 RW	**Data Phase Parity Error Enable (DPPEE):** When 1, IOSF data phase parity error handling is enabled. When 0, the data phase parity error handling is disabled.
14:12	0x0 RW	**Write Request_Size Select/Max_Payload_Size (WRRSELMPS):** These two bits select the max write request size that SATA host controller will initiate for DMA write to memory. SATA host controller will internally break up larger write request based on these bits. The request is address-aligned to the selected size. Defined encodings for this field are: • 000b = 128 address aligned bytes max payload size. • 111b = 64 address aligned bytes max payload size. • All other values are reserved for SATA host controller. This field is not reset by FLR.
11	0x0 RW	**Command Parity Error Enable (CPEE):** When 1, command parity error handing is enable. When 0 the command parity error handling is disable
10	0x0 RW	**SATA Controller Function Disable (SCFD):** BIOS program this bit to 1 to disable the SATA Controller function. When 0, SATA Controller function is enabled.
9	0x0 RW	**Unsupported Request Reporting Enable (URRE):** If set to 1 by software, it allows reporting of an Unsupported Request as a system error. If both URRE and PCI configuration SERR# Enable registers are set to a 1, then the agent must set the Signaled System Error bit in the PCI Status register and send a DO_SERR message in IOSF-SB interface.
8	0x0 RW/1C	**Unsupported Request Detected (URD):** Set to 1 by hardware upon detecting an Unsupported Request on IOSF Primary interface that is not considered Advisory Non-Fatal. Cleared to 0 by SW.
7	0x0 RW/O	**Alternate ID Enable (AIE):** When programmed to 0, HW will report the following device id's: 2822h for desktop or 282Ah for mobile. When programmed to a 1, HW will not report these device id's. This field is not reset by FLR.
6	0x0 RW/O	**AIE0 DevID Selection (DEVIDSEL):** This register allows BIOS to select Device ID when AIE=0 and Server Feature (SATA AIE DEVIDSEL) Disable Fuse =0. This field is not reset by FLR.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW/O	**FLR Capability Selection (FLRCSSEL):** This allows the FLR Capability to be bypassed.
4:3	0x0 RW/O	**MXTBA Size Select (MSS):** These 2 bits select the size of the Memory space for the MSI-X Table defined in BAR 0 (Configuration space offset 10h). MSI-X Table Memory space size is: • 32k when MSS[1:0]=00. • 16k when MSS[1:0]=01. • 8k when MSS[1:0]=10. This field is not reset by FLR.
2:0	0x0 RW/O	**ABAR Size Select (ASSEL):** These 3 bits select the size of the Memory space for the ABAR in BAR 5 (Configuration space offset 24h). ABAR Memory space size is: • 2k when ASSEL[2:0]=000. • 16k when ASSEL[2:0]=001. • 32k when ASSEL[2:0]=010. • 64k when ASSEL[2:0]=011. • 128k when ASSEL[2:0]=100. • 256k when ASSEL[2:0]=101. • 512k when ASSEL[2:0]=110. This field is not reset by FLR.

50.2.24 SATA Initialization Register Index (SIRI)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:19 or 20, F:0] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:2	0x0 RW	**Index (IDX):** 6-bit index pointer into the 256-byte space. Data is written into the SIRD register and read from the SIRD register. This points to a DWord register. The byte enables on the SIRD register affect what will be written.
1:0	0x0 RO	**RSVD0:** Reserved.

50.2.25 SATA Initialization Register Data (SIRD)—Offset A4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + A4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Data (DTA):** 32-bit data value that is written to the register pointed to by SIRI, or read from the register pointed to by SIRI.

50.2.26 Serial ATA Capability Register 0 (SATACR0)—Offset A8h

Note that the SATACR0.NEXT is not changed from RO to become RWO because there is an existing method (SATAGC.FLRCSSEL bit) to bypass the FLR Capability structure.

FLR Capability ID.NEXT is already indicating end of capability structure, it does not need to change to be RWO.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + A8h

Default: 00100012h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved.
23:20	0x1 RO	**Major Revision (MAJREV):** Major revision number of the SATA Capability Pointer implemented.
19:16	0x0 RO	**Minor Revision (MINREV):** Minor revision number of the SATA Capability Pointer implemented.
15:8	0x0 RW/L	**Next Capability Pointer (NEXT):** 00h indicating the final item in the Capability List. The RW/L register attribute allows for flexibility in determining the capability structure available in this PCI function.
7:0	0x12 RO	**Capability ID (CAP):** The value of 12h has been assigned by the PCI SIG to designate the SATA Capability pointer.

50.2.27 Serial ATA Capability Register 1 (SATACR1)—Offset ACh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + ACh

Default: 00000048h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved.
15:4	0x4 RO	**BAR Offset (BAROFST):** Indicates the offset into the BAR where the AHCI Index/Data pair are located (in Dword granularity). The Index and Data I/O registers are located at offset 10h within the I/O space defined by LBAR (BAR4). A value of 004h indicates offset 10h. • 000h = 0h offset. • 001h = 4h offset. • 002h = 8h offset. • 003h = Ch offset. • 004h = 10h offset. • ... • FFFh = 3FFFh offset (max 16 KB).
3:0	0x8 RO	**BAR Location (BARLOC):** Indicates the absolute PCI Configuration Register address of the BAR containing the Index/Data pair (in Dword granularity). The Index and Data I/O registers reside within the space defined by LBAR (BAR4) in the SATA controller. A value of 8h indicates offset 20h, which is LBAR (BAR4). • 0000 - 0011b = Reserved • 0100b = 10h =) BAR0 • 0101b = 14h =) BAR1 • 0110b = 18h =) BAR2 • 0111b = 1Ch =) BAR3 • 1000b = 20h =) AIDPBA • 1001b = 24h =) BAR5 • 1010 - 1110b = Reserved • 1111b = Index/Data pair in PCI Configuration space which is not supported.

50.2.28 FLR Capability ID (FLRCID)—Offset B0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + B0h

Default: 0013h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Capability (NEXT):** 00h indicating the final item in the Capability List.
7:0	0x13 RO	**Capability ID (CID):** The value of this field depends on the FLRCSSEL bit: • SATAGC.FLRCSSEL = 0, Capability ID = 13h. • SATAGC.FLRCSSEL = 1, Capability ID = 00h (capability is bypassed).

50.2.29 FLR Control (FLRCTL)—Offset B4h

This register shall be read-only 0 when SATAGC.FLRCSSEL=1.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + B4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**RSVD0:** Reserved.
8	0x0 RO	**Transactions Pending (TXP):** A 1 indicates that the controller has issued Non-Posted request which has not been completed. A 0 indicates that Completions for all non-posted requests have been received by the controller.
7:1	0x0 RO	**RSVD1:** Reserved.
0	0x0 RW	**Initiate FLR (Initiate_FLR):** Used to initiated FLR transition. A write of 1 indicates FLR transition. Since hardware must not respond to any cycles till FLR completion, the value read by software from this bit is 0. Refer to Function Level Reset (FLR) on specifics to SATA.

50.2.30 MSI-X Message Control (MXC)—Offset D2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:19 or 20, F:0] + D2h

Default: 0007h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**MSI-X Enable (MXE):** If set to '1' and the MSI Enable bit in the MSI Message Control register is cleared to '0', the function is permitted to use MSI-X to request service and is prohibited from using its INTx# pin (if implemented). If cleared to '0', the function is prohibited from using MSI-X to request service.
14	0x0 RW	**Function Mask (FM):** If set to '1', all of the vectors associated with the function are masked, regardless of their per vector Mask bit states. If cleared to '0', each vector's Mask bit determines whether the vector is masked or not. Setting or clearing the MSI-X Function Mask bit has no effect on the state of the per vector Mask bits.
13:11	0x0 RO	**RSVD0:** Reserved.
10:0	0x7 RO	**Table Size (TS):** This value indicates the size of the MSI-X Table as the value n, which is encoded as n - 1.

50.2.31 MSI-X Table Offset / Table BIR (MXT)—Offset D4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + D4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**Table Offset (TO):** Used as an offset from the address contained by one of the function's Base Address registers to point to the base of the MSI-X Table. The lower three Table BIR bits are masked off (cleared to 000b) by system software to form a 32-bit Qword-aligned offset.
2:0	0x0 RO	**Table BIR (TBIR):** This field indicates which one of a function's Base Address registers, located beginning at 10h in Configuration Space, is used to map the function's MSI-X Table into system memory. A read-only value of '0' means 10h.

50.2.32 MSI-X PBA Offset / PBA BIR (MXP)—Offset D8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + D8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**PBA Offset (PBAO):** Used as an offset from the address contained by one of the function's Base Address registers to point to the base of the MSI-X PBA. The lower three PBA BIR bits are masked off (cleared to 000b) by software to form a 32-bit Qword-aligned offset.
2:0	0x0 RO	**PBA BIR (PBIR):** This field indicates which one of a function's Base Address registers, located beginning at 10h in Configuration Space, is used to map the function's MSI-X PBA into system memory. A read-only value of '1' means 14h.

50.2.33 BIST FIS Control/Status (BFCS)—Offset E0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + E0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**RSVD0:** Reserved
17	0x0 RW	**Port 7 BIST FIS Initiate (P7BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 7, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 7 physically.
16	0x0 RW	**Port 6 BIST FIS Initiate (P6BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 6, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 6 physically.
15	0x0 RW	**Port 5 BIST FIS Initiate (P5BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 5, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 5 physically.
14	0x0 RW	**Port 4 BIST FIS Initiate (P4BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 4, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 4 physically.
13	0x0 RW	**Port 3 BIST FIS Initiate (P3BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 3, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 3 physically.
12	0x0 RW	**Port 2 BIST FIS Initiate (P2BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 2, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 2 physically.
11	0x0 RW/1C/V	**BIST FIS Successful (BFS):** This bit is set any time a BIST FIS transmitted by the SATA controller receives an R_OK completion status from the device.
10	0x0 RW/1C/V	**BIST FIS Failed (BFF):** This bit is set any time that a BIST FIS transmitted by the SATA controller receives an R_ERR completion status from the device.
9	0x0 RW	**Port 1 BIST FIS Initiate (P1BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 1, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 1 physically.
8	0x0 RW	**Port 0 BIST FIS Initiate (P0BFI):** When a rising edge is detected on this bit, the SATA controller will initiate a BIST FIS to the device on port 0, using the parameters specified in this register and BFTD1 and BFTD2. This bit is only applicable to project(s): That has port 0 physically.
7:2	0x0 RW	**BIST FIS Parameters (BFP):** These bits form the contents of the upper 6 bits of the BIST FIS Pattern Definition in the BIST FIS transmitted by the SATA controller. This field is not port specific - its contents will be used for any BIST FIS initiated on the SATA controller. The specific bit definitions are: • Bit 7 (T) Far End Transmit mode. • Bit 6 (A) Align Bypass mode. • Bit 5 (S) Bypass Scrambling. • Bit 4 (L) Far End Retimed Loopback. • Bit 3 (F) Far End Analog Loopback. • Bit 2 (P) Primitive bit for use with Transmit mode.

Bit Range	Default & Access	Field Name (ID): Description
1:0	0x0 RO	**RSVD1:** Reserved.

50.2.34 BIST FIS Transmit Data 1 (BFTD1)—Offset E4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + E4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Data (DATA):** The data programmed into this register will form the contents of the second DW of any BIST FIS initiated by the SATA controller. This register is not port specific - its contents will be used for BIST FIS initiated on any port. Although the 2nd and 3rd DWs of the BIST FIS are only meaningful when the T bit of the BIST FIS is set to indicate Far-End Transmit mode, this register's contents will be transmitted as the BIST FIS 2nd DW regardless of whether or not the T bit is indicated in the BFCS register.

50.2.35 BIST FIS Transmit Data 2 (BFTD2)—Offset E8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + E8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Data (DATA):** The data programmed into this register will form the contents of the third DW of any BIST FIS initiated by the SATA controller. This register is not port specific - its contents will be used for BIST FIS initiated on any port. Although the 2nd and 3rd DWs of the BIST FIS are only meaningful when the T bit of the BIST FIS is set to indicate Far-End Transmit mode, this register's contents will be transmitted as the BIST FIS 3rd DW regardless of whether or not the T bit is set in the BFCS register.

50.2.36 Manufacturing ID (MFID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:19 or 20, F:0] + F8h

Default: 08000FB1h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved.
27:24	0x8 RO/V	**Dot portion of Process ID (DPID):** Indicates the dot. Process is reflected in bits [7:0]. This 8-bit value is received via the IOSF Sideband SetID message.
23:16	0x0 RO/V	**Stepping Identifier (SID):** This field is incremented for each stepping of the part. ***Note:*** This field can be used by software to differentiate steppings when the Revision ID may not change. This is SIP customer implementation specific and SIP customer provides this 8-bit value via the Sideband SetID message.
15:8	0xf RO/V	**Manufacturer Identifier (MID):** This is SIP customer implementation specific and SIP customer provides this 8-bit value via the Sideband SetID message.
7:0	0xb1 RO/V	**Process/Dot Identifier (PID):** Indicates the Process. Dot is reflected in bits [27:24]. This is SIP customer implementation specific and SIP customer provides this 8-bit value via the Sideband SetID message.

50.3 Registers in Memory Space—MXTBA

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) MXTBA described in Section 50.2.7, "MSI-X Table Base Address (MXTBA)—Offset 10h" on page 1883.

50.3.1 MSI-X Table Entries n Message Lower Address (MXTEnMLA)

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MXTBA] + 0h + n*10h (where n<=7)

MXTBA Type: PCI Configuration Register (Size: 32 bits)
MXTBA Reference: [B:0, D:(19,20), F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**MSI-X message lower address (MXMLA):** Specifies the lower 32-bit of the DWORD-aligned address (Addr[31:02]) of the MSI-X Message.
1:0	0x0 RO	**RSVD0:** Reserved.

50.3.2 MSI-X Table Entries n Message Upper Address (MXTEnMUA)

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MXTBA] + 4h + n*10h (where n<=7)

MXTBA Type: PCI Configuration Register (Size: 32 bits)
MXTBA Reference: [B:0, D:(19,20), F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**MSI-X message upper 32-bit address (MXMUA):** Specifies the lower 32-bit of the DWORD-aligned address (Addr[31:02]) of the MSI-X Message.

50.3.3 MSI-X Table Entries n Message Data (MXTEnMD)

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MXTBA] + 8h + n*10h (where n<=7)

MXTBA Type: PCI Configuration Register (Size: 32 bits)
MXTBA Reference: [B:0, D:(19,20), F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**MSI-X message Data (MXMD):** Specifies the 32-bit Data of the MSI-X Message.

50.4 Registers in Memory Space—ABAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) ABAR described in Section 50.2.11, "AHCI Base Address (ABAR)—Offset 24h" on page 1886.

50.4.1 HBA Capabilities (GHC_CAP)—Offset 0h

This register indicates basic capabilities of the HBA to driver software. The RWO bits in this register are only cleared upon PLTRST#. This register is not reset by FLR.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: FF36FF07h

BAR and Offset: [ABAR] + 0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW/O	**Supports 64-bit Addressing (S64A):** Indicates the S-ATA controller can access 64-bit data structures. The 32-bit upper bits of the port DMA Descriptor, the PRD Base, and each PRD entry are read/write.
30	0x1 RW/O	**Supports Native Command Queuing Acceleration (SCQA):** Indicates the SATA controller supports Serial-ATA Native Command Queuing. The HBA will handle DMA Setup FISes in hardware, including support for auto-activate optimization through the FIS.
29	0x1 RW/O	**Supports SNotification Register (SSNTF):** When set to 1, indicates that the HBA supports the PxSNTF (SNotification) register and its associated functionality. When cleared to 0., the HBA does not support the PxSNTF (SNotification) register and its associated functionality.
28	0x1 RW/O	**Supports Mechanical Presence Switch (SMPS):** When set to 1, the HBA supports mechanical presence switches on its ports for use in hot plug operations. When cleared to 0, this function is not supported. This value is loaded by the BIOS prior to OS initialization.
27	0x1 RW/O	**Supports Staggered Spin-up (SSS):** Indicates whether the S-ATA controller supports staggered spin-up on its ports, for use in balancing power spikes. This value is loaded by platform BIOS prior to OS initialization.
26	0x1 RW/O	**Supports Aggressive Link Power Management (SALP):** Indicates the S-ATA controller supports auto-generating link requests to the partial or slumber states when there are no commands to process. When cleared to 0, software shall treat the PxCMD.ALPE and PxCMD.ASP bits as reserved.
25	0x1 RW/O	**Supports Activity LED (SAL):** Indicates the S-ATA controller supports a single output pin (SATALED#) which indicates activity.
24	0x1 RW/O	**Supports Command List Override (SCLO):** When set to 1, indicates that the HBA supports the PxCMD.CLO bit and it's associated function. When cleared to 0., The HBA is not capable of clearing the BSY and DRQ bits in the Status register in order to issue a software reset if these bits are still set from a previous operation.
23:20	0x3 RW/O	**Interface Speed Support (ISS):** Indicates the maximum speed the S-ATA controller can support on its ports. These encodings match the system software programmable PxSCTL.DET.SPD field. • 0000 = Reserved • 0001 = Gen 1 (1.5 Gbps) • 0010 = Gen 2 (3 Gbps) • 0011 = Gen 3 (6 Gbps) • 0100 - 1111 = Reserved. ***Note:*** If (FFSATA0p0, FFSATA0p1, FFSATA0p2, FFSATA0p3, FFSATA0p4 and FFSATA0p5) is 1, this field is RWO defaulting to 0010 and ignores software write value of 0011. If either FFSATA0p0, FFSATA0p1, FFSATA0p2, FFSATA0p3, FFSATA0p4 or FFSATA0p5 is 0, this field is RWO defaulting to 0011.
19	0x0 RO	**Supports Non-Zero DMA Offsets (SNZO):** Reserved as per AHCI 1.3.

Bit Range	Default & Access	Field Name (ID): Description
18	0x1 RO	**Supports AHCI mode only (SAM):** The SATA controller may optionally support AHCI access mechanism only. A value of 1 indicates that the SATA controller does not implement a legacy, task-file based register interface.
17	0x1 RO	**Supports Port Multiplier (SPM):** The SATA controller may optionally support command-based switching Port Multipliers.
16	0x0 RO	**FIS-based Switching Supported (FBSS):** Not supported.
15	0x1 RO	**PIO Multiple DRQ Block (PMD):** If set to 1, the HBA supports multiple DRQ block data transfers for the PIO command protocol.
14	0x1 RW/O	**Slumber State Capable (SSC):** The SATA controller supports the slumber state.
13	0x1 RW/O	**Partial State Capable (PSC):** The SATA controller supports the partial state.
12:8	0x1f RO	**Number of Command Slots (NCS):** 1Fh indicating support for 32 slots.
7	0x0 RO	**Command Completion Coalescing Supported (CCCS):** When set to 1, indicates that the HBA supports command completion coalescing.
6	0x0 RW/O/V	**Enclosure Management Supported (EMS):** When set to 1, indicates that the HBA supports enclosure management.
5	0x0 RW/O	**Supports External SATA (SXS):** When set to 1, indicates that the HBA has one or more Serial ATA ports that has a signal only connector that is externally accessible.
4:0	0x7 RO/V	**Number of Ports (NP):** 0's based value indicating the maximum number of ports supported.

50.4.2 Global HBA Control (GHC)—Offset 4h

This register controls various global actions of the HBA.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 4h

Default: 80000000h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**AHCI Enable (AE):** When set, indicates that an AHCI driver is loaded and communication to the HBA shall be via AHCI mechanisms.
30:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RO	**Reserved:** Reserved
1	0x0 RW	**Interrupt Enable (IE):** This global bit enables interrupts from the HBA. When cleared (reset default), all interrupt sources from all ports are disabled. When set, interrupts are enabled.
0	0x0 RW/1S	**HBA Reset (HR):** When set by SW, this bit causes an internal reset of the HBA. All state machines that relate to data transfers and native command queuing will return to an idle condition, and all ports will be re-initialized via COMRESET.

50.4.3 Interrupt Status Register (IS)—Offset 8h

This register indicates which of the ports within the controller have an interrupt pending and require service.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 8h

Default: 00000000h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7	0x0 RW/1C/V	**Interrupt Pending Status Port 7 (IPS7):** If set, indicates that port 7 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 7 physically.
6	0x0 RW/1C/V	**Interrupt Pending Status Port 6 (IPS6):** If set, indicates that port 6 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 6 physically.
5	0x0 RW/1C/V	**Interrupt Pending Status Port 5 (IPS5):** If set, indicates that port 5 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 5 physically.
4	0x0 RW/1C/V	**Interrupt Pending Status Port 4 (IPS4):** If set, indicates that port 4 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 4 physically.
3	0x0 RW/1C/V	**Interrupt Pending Status Port 3 (IPS3):** If set, indicates that port 3 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 3 physically.
2	0x0 RW/1C/V	**Interrupt Pending Status Port 2 (IPS2):** If set, indicates that port 2 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 2 physically.
1	0x0 RW/1C/V	**Interrupt Pending Status Port 1 (IPS1):** If set, indicates that port 1 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 1 physically.
0	0x0 RW/1C/V	**Interrupt Pending Status Port 0 (IPS0):** If set, indicates that port 0 has an interrupt pending. Software can use this information to determine which ports require service after an interrupt. This bit is only applicable to project(s): That has port 0 physically.

50.4.4 Ports Implemented (GHC_PI)—Offset Ch

This register indicates which ports are exposed to the HBA. It indicates which ports that the device supports are available for software to use. Any available port may not be implemented. This register is not reset by FLR. There is BIOS programming requirement on the PI register. Please refer to section 7.9.13.1.1 for details.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + Ch

Default: 00000000h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**RSVD0:** Reserved
7	0x0 RW/O/V	**Port 7 Implemented (PI7):** If set, then port 7 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 7 is not available.
6	0x0 RW/O/V	**Port 6 Implemented (PI6):** If set, then port 6 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 6 is not available.
5	0x0 RW/O/V	**Port 5 Implemented (PI5):** If set, then port 5 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 5 is not available.
4	0x0 RW/O/V	**Port 4 Implemented (PI4):** If set, then port 4 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 4 is not available.
3	0x0 RW/O/V	**Port 3 Implemented (PI3):** If set, then port 3 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 3 is not available.
2	0x0 RW/O/V	**Port 2 Implemented (PI2):** If set, then port 2 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 2 is not available.
1	0x0 RW/O/V	**Port 1 Implemented (PI1):** If set, then port 1 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 1 is not available.
0	0x0 RW/O/V	**Port 0 Implemented (PI0):** If set, then port 0 is available for use. If cleared, the port is not available for use. This bit is reserved and is read-only 0 if below condition is true else it's RWO-zero: Refer to CAP.NP where port 0 is not available.

50.4.5 AHCI Version (VS)—Offset 10h

This register indicates the major and minor version of the AHCI specification. It is BCD encoded. The upper two bytes represent the major version number, and the lower two bytes represent the minor version number. Example: Version 3.12 would be represented as 00030102h.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 10h

Default: 00010300h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x1 RO	**Major Version Number (MJR):** Indicates the major version is 1
15:0	0x300 RO	**Minor Version Number (MNR):** Indicates the minor version is 30

50.4.6 Enclosure Management Control (EM_CTL)—Offset 20h

This register is used to control and obtain status for the enclosure management interface. The register includes information on the attributes of the implementation, enclosure management messages supported, the status of the interface, whether any messages are pending, and is used to initiate sending messages. This register is not implemented if enclosure management is not supported (i.e. CAP.EMS = 0).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 20h

Default: 07010000h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27	0x0 RO	**Port Multiplier Support (ATTR_PM):** The HBA does not support enclosure management messages for devices attached via a Port Multiplier. Software should use the Serial ATA enclosure management bridge that is built into many Port Multipliers for enclosure services with these devices. For more information on Serial ATA enclosure management bridges, refer to the Serial ATA II: Extensions to Serial ATA 1.0a revision 1.2 specification.
26	0x1 RW/O	**Activity LED Hardware Driven (ATTR_ALHD):** If set to 1, the HBA drives the activity LED for the LED message type in hardware and does not utilize software settings for this LED. The HBA does not begin transmitting the hardware based activity signal until after software has written CTL.TM=1 after a reset condition.
25	0x1 RO	**Transmit Only (ATTR_XMT):** If set to 1, the HBA only supports transmitting messages and does not support receiving messages. If cleared to 0, the HBA supports transmitting and receiving messages.
24	0x1 RO	**Single Message Buffer (ATTR_SMB):** If set to 1, the HBA has one message buffer that is shared for messages to transmit and messages received. In this case, unsolicited receive messages are not supported and it is software's responsibility to manage access to this buffer. If cleared to 0, there are separate receive and transmit buffers such that unsolicited messages could be supported.
23:20	0x0 RO	**RSVD1:** Reserved
19	0x0 RO	**SGPIO Enclosure Management Messages (SUPP_SGPIO):** If set to 1, the HBA supports the SGPIO register interface message type.
18	0x0 RO	**SES-2 Enclosure Management Messages (SUPP_SES2):** If set to 1, the HBA supports the SES-2 message type.
17	0x0 RO	**SAF-TE Enclosure Management Messages (SUPP_SAFTE):** If set to 1, the HBA supports the SAF-TE message type.
16	0x1 RO	**LED Message Types (SUPP_LED):** If set to 1, the HBA supports the LED message type defined in LED Message Type.
15:10	0x0 RO	**RSVD2:** Reserved
9	0x0 RW/1S	**Reset (RST):** When set to 1 by software, the HBA shall reset all enclosure management message logic and take all appropriate reset actions to ensure messages can be transmitted/received after the reset. After the HBA completes the reset operation, the HBA shall set the value to 0. A write of 0 by software to this field shall have no effect.
8	0x0 RW/1S	**Transmit Message (CTL_TM):** When set to 1 by software, the HBA shall transmit the message contained in the message buffer. When the message is completely sent, the HBA shall clear this bit to 0. A write of 0 to this bit by software shall have no effect. Software shall not change the contents of the message buffer while CTL.TM is set to 1.

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RO	**RSVD3:** Reserved
0	0x0 RO	**Message Received (STS_MR):** Message received is not supported.

50.4.7 HBA Capabilities Extended (GHC_CAP2)—Offset 24h

This register indicates basic capabilities of the HBA to driver software. The RWO bits in this register are only cleared upon PLTRST#. This register is not reset by FLR.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 24h

Default: 0000003Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD0:** Reserved
5	0x1 RW/O	**DEVSLP Entrance from Slumber Only (DESO):** This field specifies that the HBA shall only assert DEVSLP if the interface is in Slumber. When this bit is set to 1, the HBA shall ignore software directed entrance to DEVSLP via PxCMD.ICC unless PxSSTS.IPM = 6h.
4	0x1 RW/O/V	**Supports Aggressive DEVSLP Management (SADM):** When set to 1, the HBA supports hardware assertion of the DEVSLP signal after the idle timeout expires.
3	0x1 RW/O/V	**Supports DEVSLP (SDS):** When set to 1, the HBA supports the DEVSLP feature. When cleared to 0, DEVSLP is not supported.
2	0x1 RW/O/V	**Automatic Partial to Slumber Transitions (APST):** When set to 1, the HBA supports Automatic Partial to Slumber Transitions.
1	0x0 RO	**RSVD1:** Reserved
0	0x0 RO	**Reserved:** Reserved

50.4.8 Vendor Specific (VSP)—Offset A0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000048h

BAR and Offset: [ABAR] + A0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**RSVD0:** Reserved
6	0x1 RO	**Software Feature Mask Supported (SFMS):** Set to 1 if the platform is enabled for premium storage features mask (SFM) as described in VS MMIO space at offset ABAR[RPID.(OFST*4)+4].
5	0x0 RO/V	**Premium Features Supported (PFS):** Set to 1 if the platform is enabled for premium storage features (PFB) as described in VS MMIO space at offset ABAR[RPID.OFST*4]. Set to 0 if the platform is not enabled for premium storage features.
4	0x0 RO/V	**Platform Type (PT):** Set to 1 if mobile platform. Clear (0) if desktop.
3	0x1 RO	**Supports RAID Platform ID Reporting (SRPIR):** If set to 1, then indicates that the RAID Platform ID is reported via ABAR + C0h. Set to 0 if this ID is not reported via MMIO space.
2:0	0x0 RO	**RSVD1:** Reserved

50.4.9 Vendor Specific Capabilities Register (VS_CAP)—Offset A4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 001002DEh

BAR and Offset: [ABAR] + A4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:16	0x10 RW/O	**NVM Remapped Register Offset (NRMO):** Specifies the offset (in 128B unit) within ABAR as to where the PCIe NAND memory BAR register space is remapped. For example, NRMO=1 means ABAR + 128B. This allows the remapped offset to shift between ABAR + 0B, and ABAR + 512KK - 128B, with 128B step. The remapped offset into the AHCI memory space must not overlap with the memory space used for SATA. The remapped offset into the AHCI memory space and the remapped size must not exceed the allocated AHCI memory space of the integrated AHCI controller. Only valid when NRMBE = 1. The reset default of this field is 10h, this places the start of the PCIe NAND memory BAR register space at ABAR + 2K. This field is not reset by FLR.
15:13	0x0 RO	**RSVD1:** Reserved
12:1	0x16f RW/O	**Memory Space Limit. (MSL):** This field specifies the size (in 128B unit) of the remapped memory space for the PCIe NAND device. It is a 0-based field. For example, MSL=1 means 256B. This allows the remapped size to shift between 128B and 512K with the step of 128B.Memory BAR offset from 0 to MSL of the PCIe NAND device are remapped under the integrated AHCI controller memory space. The remapped offset into the AHCI memory space and the value programmed in this field must not exceed the allocated AHCI memory space of the integrated AHCI controller. Only valid when NRMBE = 1. The reset default of this field is 16Fh which specifies the size of the remapped memory space as 34k. This field is not reset by FLR.
0	0x0 RW/O	**PCIe NAND Memory BAR Remapped Enable (NRMBE):** Set to 1 if a PCIe NAND device is present and remapping of its memory BAR register space is enabled. Cleared to 0 if there is no PCIe NAND device present or the remapping of its memory BAR register space is disabled. This bit is not reset by FLR.

50.4.10 RAID Platform ID (RPID)—Offset C0h

This register is used by the Intel Matrix Storage Manager OROM to match the features supported by the OROM with the platform on which the OROM is executing. This prevents the use of an OROM designed for newer chipsets from being use on older chipsets as this could reduce up-sell potential.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + C0h

Default: 00311C02h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x31 RO	**Offset (OFST):** The offset of the Premium Feature Block (PFB) in DWords from the beginning of the ABAR. SFM follows directly after PFB.
15:0	0x1c02 RO/V	**RAID Platform ID (RPID):** Specifies the DID value that has been assigned to the platform. This is the same DID that is reported by the SATA controller when SATAGC.AIE is set to 1 except that the DID is always reported through this register, regardless if the programming of SATAGC.AIE.

50.4.11 SW Feature Mask (SFM)—Offset C8h

The following will be programmed by the BIOS when VS_CAP.SFMS == 1. The feature mask is used by SW to determine which non-premium features shall be supported by SW. These register bits are not reset by FLR since they are programmed by BIOS.

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [ABAR] + C8h

Default: 003Fh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RO	**RSVD0:** Reserved
11:10	0x0 RW/O	**OROM UI Normal Delay. (OROM_UI_Normal_Delay):** Values of these bits specify the delay of the OROM UI Splash Screen in a normal status. • 00 = 2 secs (default and previous value) • 01 = 4 secs • 10 = 6 secs • 11 = 8 secs. If bit 5 == 0, then these values are disregarded.
9	0x0 RW/O	**Smart Response Technology. (Smart_Response_Technology):** If set to '1', then Smart Response Technology is enabled. If cleared to '0', the feature is disabled.
8	0x0 RW/O	**RRT Only on ESATA (IRRT_Only_on_ESATA):** If set to 1, then only RRT volumes can span internal and external SATA ports (e.g. eSATA). If cleared to 0, then any RAID volume can span internal and external SATA ports (e.g. eSATA).
7	0x0 RW/O	**LED Locate (LED_Locate):** If set to 1, then LED/SGPIO hardware is attached and the ping to locate feature is enabled in the OS.
6	0x0 RW/O	**HDDUNLOCK:** If set to 1, then HDD password unlock is enabled in the OS.
5	0x1 RW/O	**OROM UI and BANNER (OROM_UI_and_BANNER):** If set to 1, then the OROM UI is displayed. When cleared to 0, the OROM UI and BANNER are not displayed if all disks and volumes have a normal status.
4	0x1 RW/O	**RRT (IRRT):** If set to 1, then Rapid Recovery Technology is enabled.
3	0x1 RW/O	**R5:** If set to 1, then RAID5 is enabled
2	0x1 RW/O	**R10:** If set to 1, then RAID10 is enabled
1	0x1 RW/O	**R1:** If set to 1, then RAID1 is enabled
0	0x1 RW/O	**R0:** If set to 1, then RAID0 is enabled

50.4.12 Port [0-7] Command List Base Address (PxCLB0)—Offset 100h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 100h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.13 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU0)—Offset 104h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 104h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. ***Note:*** These bits are not reset on a HBA reset.

50.4.14 Port [0-7] FIS Base Address (PxFB0)—Offset 108h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 108h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.15 Port [0-7] FIS Base Address Upper 32-bits (PxFBU0)—Offset 10Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 10Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.16 Port [0-7] Interrupt Status (PxIS0)—Offset 110h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 110h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. Note that this bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.17 Port [0-7] Interrupt Enable (PxIE0)—Offset 114h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 114h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.18 Port [0-7] Command (PxCMD0)—Offset 118h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 118h

Default: 00000004h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleared to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI. When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether the this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0. when CAP.PMS = 0., and read/write when CAP.PMS = 1. Note that this bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RO/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RO/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO/V	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 to a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.19 Port [0-7] Serial ATA Status (PxSSTS0)—Offset 128h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 128h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.20 Port [0-7] Serial ATA Control (PxSCTL0)—Offset 12Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 12Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.21 Port [0-7] Serial ATA Error (PxSERR0)—Offset 130h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 130h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.22 Port [0-7] Serial ATA Active (PxSACT0)—Offset 134h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 134h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.23 Port [0-7] Commands Issued (PxCI0)—Offset 138h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 138h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.24 Port [0-7] SNotification (PxSNTF0)—Offset 13Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 13Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. Note that, while this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.25 Port [0-7] Command List Base Address (PxCLB1)—Offset 180h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 180h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.26 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU1)—Offset 184h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 184h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. ***Note:*** These bits are not reset on a HBA reset.

50.4.27 Port [0-7] FIS Base Address (PxFB1)—Offset 188h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 188h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.28 Port [0-7] FIS Base Address Upper 32-bits (PxFBU1)—Offset 18Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 18Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.29 Port [0-7] Interrupt Status (PxIS1)—Offset 190h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 190h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. Note that this bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.30 Port [0-7] Interrupt Enable (PxIE1)—Offset 194h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 194h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.31 Port [0-7] Command (PxCMD1)—Offset 198h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 198h

Default: 00000004h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleared to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI. When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether the this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0. when CAP.PMS = 0., and read/write when CAP.PMS = 1. Note that this bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RW/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RW/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 to a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.32 Port [0-7] Serial ATA Status (PxSSTS1)—Offset 1A8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 1A8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.33 Port [0-7] Serial ATA Control (PxSCTL1)—Offset 1ACh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 1ACh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.34 Port [0-7] Serial ATA Error (PxSERR1)—Offset 1B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 1B0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.35 Port [0-7] Serial ATA Active (PxSACT1)—Offset 1B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 1B4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.36 Port [0-7] Commands Issued (PxCI1)—Offset 1B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 1B8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.37 Port [0-7] SNotification (PxSNTF1)—Offset 1BCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 1BCh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. Note that, while this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST.

50.4.38 Port [0-7] Command List Base Address (PxCLB2)—Offset 200h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 200h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.39 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU2)—Offset 204h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 204h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. ***Note:*** These bits are not reset on a HBA reset.

50.4.40 Port [0-7] FIS Base Address (PxFB2)—Offset 208h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 208h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.41 Port [0-7] FIS Base Address Upper 32-bits (PxFBU2)—Offset 20Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 20Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.42 Port [0-7] Interrupt Status (PxIS2)—Offset 210h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 210h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. Note that this bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.43 Port [0-7] Interrupt Enable (PxIE2)—Offset 214h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 214h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.44 Port [0-7] Command (PxCMD2)—Offset 218h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000004h

BAR and Offset: [ABAR] + 218h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleard to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI. When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether the this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0. when CAP.PMS = 0., and read/write when CAP.PMS = 1. Note that this bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RO/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RO/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO/V	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 to a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.45 Port [0-7] Serial ATA Status (PxSSTS2)—Offset 228h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 228h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.46 Port [0-7] Serial ATA Control (PxSCTL2)—Offset 22Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 22Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.47 Port [0-7] Serial ATA Error (PxSERR2)—Offset 230h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 230h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.48 Port [0-7] Serial ATA Active (PxSACT2)—Offset 234h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 234h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.49 Port [0-7] Commands Issued (PxCI2)—Offset 238h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 238h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.50 Port [0-7] SNotification (PxSNTF2)—Offset 23Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 23Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. Note that, while this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.51 Port [0-7] Command List Base Address (PxCLB3)—Offset 280h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 280h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.52 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU3)—Offset 284h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 284h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. Note that these bits are not reset on a HBA reset.

50.4.53 Port [0-7] FIS Base Address (PxFB3)—Offset 288h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 288h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.54 Port [0-7] FIS Base Address Upper 32-bits (PxFBU3)—Offset 28Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 28Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.55 Port [0-7] Interrupt Status (PxIS3)—Offset 290h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 290h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** 1=Change in Current Connect Status. 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. ***Note:*** This bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.56 Port [0-7] Interrupt Enable (PxIE3)—Offset 294h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 294h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.57 Port [0-7] Command (PxCMD3)—Offset 298h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [ABAR] + 298h

Default: 00000004h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleared to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI. When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether the this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0. when CAP.PMS = 0., and read/write when CAP.PMS = 1. Note that this bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RO/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RO/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO/V	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 to a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.58 Port [0-7] Serial ATA Status (PxSSTS3)—Offset 2A8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 2A8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.59 Port [0-7] Serial ATA Control (PxSCTL3)—Offset 2ACh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 2ACh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.60 Port [0-7] Serial ATA Error (PxSERR3)—Offset 2B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 2B0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.61 Port [0-7] Serial ATA Active (PxSACT3)—Offset 2B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 2B4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.62 Port [0-7] Commands Issued (PxCI3)—Offset 2B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 2B8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.63 Port [0-7] SNotification (PxSNTF3)—Offset 2BCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 2BCh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. Note that, while this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.64 Port [0-7] Command List Base Address (PxCLB4)—Offset 300h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 300h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. Note that these bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.65 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU4)—Offset 304h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 304h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. ***Note:*** These bits are not reset on a HBA reset.

50.4.66 Port [0-7] FIS Base Address (PxFB4)—Offset 308h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 308h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.67 Port [0-7] FIS Base Address Upper 32-bits (PxFBU4)—Offset 30Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 30Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.68 Port [0-7] Interrupt Status (PxIS4)—Offset 310h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 310h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. ***Note:*** This bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.69 Port [0-7] Interrupt Enable (PxIE4)—Offset 314h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 314h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.70 Port [0-7] Command (PxCMD4)—Offset 318h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000004h

BAR and Offset: [ABAR] + 318h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleard to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI. When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0 when CAP.PMS = 0., and read/write when CAP.PMS = 1. Note that this bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RO/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RO/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO/V	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 to a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.71 Port [0-7] Serial ATA Status (PxSSTS4)—Offset 328h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 328h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.72 Port [0-7] Serial ATA Control (PxSCTL4)—Offset 32Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 32Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.73 Port [0-7] Serial ATA Error (PxSERR4)—Offset 330h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 330h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.74 Port [0-7] Serial ATA Active (PxSACT4)—Offset 334h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 334h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.75 Port [0-7] Commands Issued (PxCI4)—Offset 338h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 338h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.76 Port [0-7] SNotification (PxSNTF4)—Offset 33Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 33Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. Note that, while this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.77 Port [0-7] Command List Base Address (PxCLB5)—Offset 380h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 380h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.78 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU5)—Offset 384h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 384h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. ***Note:*** These bits are not reset on a HBA reset.

50.4.79 Port [0-7] FIS Base Address (PxFB5)—Offset 388h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 388h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.80 Port [0-7] FIS Base Address Upper 32-bits (PxFBU5)—Offset 38Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 38Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.81 Port [0-7] Interrupt Status (PxIS5)—Offset 390h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 390h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. Note that this bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.82 Port [0-7] Interrupt Enable (PxIE5)—Offset 394h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 394h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.83 Port [0-7] Serial ATA Status (PxSSTS5)—Offset 3A8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 3A8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.84 Port [0-7] Serial ATA Control (PxSCTL5)—Offset 3ACh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 3ACh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.85 Port [0-7] Serial ATA Error (PxSERR5)—Offset 3B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 3B0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.86 Port [0-7] Serial ATA Active (PxSACT5)—Offset 3B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 3B4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.87 Port [0-7] Commands Issued (PxCI5)—Offset 3B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 3B8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.88 Port [0-7] SNotification (PxSNTF5)—Offset 3BCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 3BCh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. ***Note:*** While this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.89 Port [0-7] Device Sleep (PxDEVSLP5)—Offset 3C4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 1E022852h

BAR and Offset: [ABAR] + 3C4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RSVD0:** Reserved
28:25	0xf RW/O/V	**DITO Multiplier (DM):** 0's based value that specifies the DITO multiplier that the HBA applies to the specified DITO value, effectively extending the range of DITO from 1ms to 16368ms. A value of 0h indicates a multiplier of 1. A maximum multiplier of 16 may be applied.
24:15	0x4 RW/V	**DEVSLP Idle Timeout (DITO):** This field specifies the amount of the time (in approximate 1ms granularity) that the HBA shall wait before driving the DEVSLP signal.
14:10	0xa RW/V	**DEVSLP Minimum Assertion Time (MDAT):** This field specifies the minimum amount of time (in 1ms granularity) that the HBA must assert the DEVSLP signal before it may be de-asserted. The nominal value is 10ms and the minimum is 1ms depending on device identification information.
9:2	0x14 RW/V	**DEVSLP Exit Timeout (DETO):** This field specifies the maximum duration (in approximate 1ms granularity) from DEVSLP de-assertion until the device is ready to accept OOB. The nominal value is 20ms while the max value is 255ms depending on device identification information.
1	0x1 RW/O	**DEVSLP Present (DSP):** If set to '1', the platform supports DEVSLP on this port. If cleared to '0', the platform does not support DEVSLP on this port.
0	0x0 RW/V	**Aggressive DEVSLP Enable (ADSE):** This bit is read/write for HBAs that support aggressive DEVSLP management (CAP2. SADM = 1).

50.4.90 Port [0-7] Command List Base Address (PxCLB6)—Offset 400h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 400h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.91 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU6)—Offset 404h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 404h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. Note that these bits are not reset on a HBA reset.

50.4.92 Port [0-7] FIS Base Address (PxFB6)—Offset 408h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 408h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.93 Port [0-7] FIS Base Address Upper 32-bits (PxFBU6)—Offset 40Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 40Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.94 Port [0-7] Interrupt Status (PxIS6)—Offset 410h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 410h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. Note that this bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.95 Port [0-7] Interrupt Enable (PxIE6)—Offset 414h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 414h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.96 Port [0-7] Command (PxCMD6)—Offset 418h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000004h

BAR and Offset: [ABAR] + 418h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleared to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI.When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether the this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0. when CAP.PMS = 0., and read/write when CAP.PMS = 1. ***Note:*** This bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RO/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RO/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO/V	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 ot a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.97 Port [0-7] Task File Data (PxTFD6)—Offset 420h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0000007Fh

BAR and Offset: [ABAR] + 420h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:8	0x0 RO/V	**Error (ERR):** Contains the latest copy of the task file error register.
7	0x0 RO/V	**Status Busy (STS_BSY):** Status - Indicates the interface is busy.
6:4	0x7 RO/V	**Status Rsvd0 (STS_RSVD0):** Status - Not Applicable.
3	0x1 RO/V	**Status Drq (STS_DRQ):** Status - Indicates a data transfer is requested.
2:1	0x3 RO/V	**Status Rsvd1 (STS_RSVD1):** Status - Not Applicable.
0	0x1 RO/V	**Status Err (STS_ERR):** Status - Indicates an error during the transfer.

50.4.98 Port [0-7] Signature (PxSIG6)—Offset 424h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: FFFFFFFFh

BAR and Offset: [ABAR] + 424h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO/V	**Signature (SIG):** Contains the signature received from a device on the first D2H Register FIS.

50.4.99 Port [0-7] Serial ATA Status (PxSSTS6)—Offset 428h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 428h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.100 Port [0-7] Serial ATA Control (PxSCTL6)—Offset 42Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 42Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.101 Port [0-7] Serial ATA Error (PxSERR6)—Offset 430h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 430h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.102 Port [0-7] Serial ATA Active (PxSACT6)—Offset 434h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 434h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.103 Port [0-7] Commands Issued (PxCI6)—Offset 438h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 438h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.104 Port [0-7] SNotification (PxSNTF6)—Offset 43Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 43Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. ***Note:*** While this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.105 Port [0-7] Device Sleep (PxDEVSLP6)—Offset 444h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 1E022852h

BAR and Offset: [ABAR] + 444h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RSVD0:** Reserved
28:25	0xf RW/O/V	**DITO Multiplier (DM):** 0's based value that specifies the DITO multiplier that the HBA applies to the specified DITO value, effectively extending the range of DITO from 1ms to 16368ms. A value of 0h indicates a multiplier of 1. A maximum multiplier of 16 may be applied.
24:15	0x4 RW/V	**DEVSLP Idle Timeout (DITO):** This field specifies the amount of the time (in approximate 1ms granularity) that the HBA shall wait before driving the DEVSLP signal. Hardware reloads its port specific DEVSLP timer with this value each time the port transitions out of DEVSLP state.
14:10	0xa RW/V	**DEVSLP Minimum Assertion Time (MDAT):** This field specifies the minimum amount of time (in 1ms granularity) that the HBA must assert the DEVSLP signal before it may be de-asserted. The nominal value is 10ms and the minimum is 1ms depending on device identification information.
9:2	0x14 RW/V	**DEVSLP Exit Timeout (DETO):** This field specifies the maximum duration (in approximate 1ms granularity) from DEVSLP de-assertion until the device is ready to accept OOB. The nominal value is 20ms while the max value is 255ms depending on device identification information.
1	0x1 RW/O	**DEVSLP Present (DSP):** If set to '1', the platform supports DEVSLP on this port. If cleared to '0', the platform does not support DEVSLP on this port.
0	0x0 RW/V	**Aggressive DEVSLP Enable (ADSE):** This bit is read/write for HBAs that support aggressive DEVSLP management (CAP2. SADM = 1).

50.4.106 Port [0-7] Command List Base Address (PxCLB7)—Offset 480h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 480h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RW	**Command List Base Address (CLB):** Indicates the 32-bit base for the command list for this port. This base is used when fetching commands to execute. This address must be 1K aligned as indicated by bits 31:10 being read/write. ***Note:*** These bits are not reset on a HBA reset.
9:0	0x0 RO	**RSVD0:** Reserved

50.4.107 Port [0-7] Command List Base Address Upper 32-bits (PxCLBU7)—Offset 484h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 484h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command List Base Address Upper (CLBU):** Indicates the upper 32-bits for the command list base address for this port. This base is used when fetching commands to execute. ***Note:*** These bits are not reset on a HBA reset.

50.4.108 Port [0-7] FIS Base Address (PxFB7)—Offset 488h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 488h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**FIS Base Address (FB):** Indicates the 32-bit base for received FISes. This address must be 256-byte aligned as indicated by bits 31:08 being read/write. When FIS-based switching is in use, this structure is 4KB in length and the address shall be 4KB aligned. ***Note:*** These bits are not reset on a HBA reset.
7:0	0x0 RO	**RSVD0:** Reserved

50.4.109 Port [0-7] FIS Base Address Upper 32-bits (PxFBU7)—Offset 48Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 48Ch

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FIS Base Address Upper (FBU):** Indicates the upper 32-bits for the received FIS base for this port. ***Note:*** These bits are not reset on a HBA reset.

50.4.110 Port [0-7] Interrupt Status (PxIS7)—Offset 490h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 490h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Status (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW/1C/V	**Task File Error Status (TFES):** This bit is set whenever the status register is updated by the device and the error bit (bit 0 of the Status field in the received FIS) is set.
29	0x0 RW/1C/V	**Host Bus Fatal Error Status (HBFS):** Indicates that the HBA encountered a host bus error that it cannot recover from, such as a bad software pointer. In PCI, such an indication would be a target or master abort.
28	0x0 RW/1C/V	**Host Bus Data Error Status (HBDS):** Indicates that the HBA encountered a data error (uncorrectable ECC / parity) when reading from or writing to system memory.
27	0x0 RW/1C/V	**Interface Fatal Error Status (IFS):** Indicates that the HBA encountered an error on the SATA interface which caused the transfer to stop.
26	0x0 RW/1C/V	**Interface Non-fatal Error Status (INFS):** Indicates that the HBA encountered an error on the SATA interface but was able to continue operation.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW/1C/V	**Overflow Status (OFS):** Indicates that the HBA received more bytes from a device than was specified in the PRD table for the command.
23	0x0 RW/1C/V	**Incorrect Port Multiplier Status (IPMS):** Indicates that the HBA received a FIS from a device whose port multiplier field did not match what was expected. The IPMS bit may be set during enumeration process. It is recommended that IPMS only be used after enumeration is complete on the Port Multiplier.
22	0x0 RO/V	**PhyRdy Change Status (PRCS):** When set to one indicates the internal PhyRdy signal changed state. This bit reflects the state of PxSERR.DIAG.N. This bit is RO and is only cleared when PxSERR.DIAG.N is cleared.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/1C/V	**Device Mechanical Presence Status (DMPS):** When set, indicates that a platform mechanical presence switch has been opened or closed, which may lead to a change in the connection state of the device. This bit is only valid in systems that support mechanical presence switch (CAP.SMPS and PxCMD.MPSP are set).
6	0x0 RO/V	**Port Connect Change Status (PCS):** • 1=Change in Current Connect Status. • 0=No change in Current Connect Status. This bit reflects the state of PxSERR.DIAG.X. This bit is only cleared when PxSERR.DIAG.X is cleared.
5	0x0 RW/1C/V	**Descriptor Processed (DPS):** A PRD with the I. bit set has transferred all of its data.
4	0x0 RO/V	**Unknown FIS Interrupt (UFS):** When set to 1 indicates that an unknown FIS was received and has been copied into system memory. This bit is cleared to 0 by software clearing the PxSERR.DIAG.F bit to 0. Note that this bit does not directly reflect the PxSERR.DIAG.F bit. PxSERR.DIAG.F is set immediately when an unknown FIS is detected, whereas this bit is set when the FIS is posted to memory. Software should wait to act on an unknown FIS until this bit is set to 1 or the two bits may become out of sync.
3	0x0 RW/1C/V	**Set Device Bits Interrupt (SDBS):** A Set Device Bits FIS has been received with the I. bit set and has been copied into system memory.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/1C/V	**DMA Setup FIS Interrupt (DSS):** A DMA Setup FIS has been received with the I. bit set and has been copied into system memory.
1	0x0 RW/1C/V	**PIO Setup FIS Interrupt (PSS):** A PIO Setup FIS has been received with the I. bit set, it has been copied into system memory, and the data related to that FIS has been transferred. This bit shall be set even if the data transfer resulted in an error.
0	0x0 RW/1C/V	**Device to Host Register FIS Interrupt (DHRS):** A D2H register FIS has been received with the I. bit set, and has been copied into system memory.

50.4.111 Port [0-7] Interrupt Enable (PxIE7)—Offset 494h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 494h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Cold Presence Detect Enable (CPDS):** The SATA controller does not support cold presence detect.
30	0x0 RW	**Task File Error Enable (TFEE):** When set, GHC.IE is set, and P0S.TFES is set, the HBA shall generate an interrupt.
29	0x0 RW	**Host Bus Fatal Error Enable (HBFE):** When set, GHC.IE is set, and P0IS.HBFS is set, the HBA shall generate an interrupt.
28	0x0 RW	**Host Bus Data Error Enable (HBDE):** when set, GHC.IE is set, and P0IS.HBDS is set, the HBA shall generate an interrupt.
27	0x0 RW	**Interface Fatal Error Enable (IFE):** When set, GHC.IE is set, and P0IS.IFS is set, the HBA shall generate an interrupt.
26	0x0 RW	**Interface Non-fatal Error Enable (INFE):** When set, GHC.IE is set, and P0IS.INFS is set, the HBA shall generate an interrupt.
25	0x0 RO	**RSVD0:** Reserved
24	0x0 RW	**Overflow Enable (OFE):** When set, and GHC.IE and P0IS.OFS are set, the HBA shall generate an interrupt.
23	0x0 RW	**Incorrect Port Multiplier Enable (IPME):** When set, and GHC.IE and P0IS.IPMS are set, the HBA shall generate an interrupt. BIOS is required to program this field to '0'. The same applies to AHCI driver.
22	0x0 RW	**PhyRdy Change Interrupt Enable (PRCE):** When set, and GHC.IE is set, and PxIS.PRCS is set, the HBA shall generate an interrupt.
21:8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW/V	**Device Mechanical Enable (DMPE):** When set, and P0IS.DMPS is set, the HBA shall generate an interrupt.
6	0x0 RW	**Port Change Interrupt Enable (PCE):** When set, GHC.IE is set, and P0IS.PCS is set, the HBA shall generate an interrupt.
5	0x0 RW	**Descriptor Processed Interrupt Enable (DPE):** When set, GHC.IE is set, and P0IS.DPS is set, the HBA shall generate an interrupt.
4	0x0 RW	**Unknown FIS Interrupt Enable (UFE):** When set, GHC.IE is set, and PxIS.UFS is set to 1, the HBA shall generate an interrupt.
3	0x0 RW	**Set Device Bits FIS Interrupt Enable (SDBE):** When set, GHC.IE is set, and P0IS.SDBS is set, the HBA shall generate an interrupt.
2	0x0 RW	**DMA Setup FIS Interrupt Enable (DSE):** When set, GHC.IE is set, and P0IS.DSS is set, the HBA shall generate an interrupt.
1	0x0 RW	**PIO Setup FIS Interrupt Enable (PSE):** When set, GHC.IE is set, and P0IS.PSS is set, the HBA shall generate an interrupt.
0	0x0 RW	**Device to Host Register FIS Interrupt Enable (DHRE):** When set, GHC.IE is set, and P0IS.DHRS is set, the HBA shall generate an interrupt.

50.4.112 Port [0-7] Command (PxCMD7)—Offset 498h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000004h

BAR and Offset: [ABAR] + 498h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Interface Communication Control (ICC):** This is a four bit field which can be used to control reset and power states of the interface. If the Link layer is currently in the L_IDLE state, writes to this field shall cause the HBA to initiate a transition to the interface power management state requested. If the Link layer is not currently in the L_IDLE state, writes to this field shall have no effect.
27	0x0 RW	**Aggressive Slumber Partial (ASP):** When set to 1, and the ALPE bit is set, the HBA shall aggressively enter the Slumber state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. When cleared, and the ALPE bit is set, the HBA will aggressively enter the Partial state when it clears a bit in the PxCI or PxSACT register and the register values are then PxCI = 0h and PxSACT = 0h. If CAP.SALP is cleard to 0., software shall treat this bit as reserved.
26	0x0 RW	**Aggressive Link Power Management Enable (ALPE):** When set, the HBA will aggressively enter a lower link power state (Partial or Slumber) based upon the setting of the ASP bit. Software shall only set this bit to 1 if CAP.SALP is set to 1. If CAP.SALP is cleared to 0, software shall treat this bit as reserved. BIOS is recommended to program this field to 1.
25	0x0 RW	**Drive LED on ATAPI Enable (DLAE):** When set, the HBA will drive the LED pin active for commands regardless of the state of PxCMD.ATAPI. When cleared, the HBA will only drive the LED pin active for commands if PxCMD.ATAPI is set to 0. This bit is set by software.
24	0x0 RW	**Device is ATAPI (ATAPI):** When set, the connected device is an ATAPI device. This bit is used by the HBA to control whether or not to generate the desktop LED when commands are active.
23	0x0 RW	**Automatic Partial to Slumber Transitions Enabled (APSTE):** When set to 1., the HBA may perform Automatic Partial to Slumber Transitions. When cleared to 0. the port shall not perform Automatic Partial to Slumber Transitions. Software shall only set this bit to 1. if CAP2.APST is set to 1.; if CAP2.APST is cleared to 0. software shall treat this bit as reserved.
22	0x0 RO	**FIS-based Switching Capable Port (FBSCP):** The SATA controller does not support FIS-Based Switching.
21	0x0 RW/O	**External SATA Port (ESP):** When set to 1, indicates that this port is routed externally and will be used with an external SATA device. When set to 1, CAP.SXS must also be set to 1. When cleared (0), indicates that this port is not routed externally and supports internal SATA devices only. If ESP is set to '1', then the port may experience hot plug events.
20	0x0 RO	**Cold Presence Detection (CPD):** The SATA controller does not support cold presence detect.
19	0x0 RW/O	**Mechanical Presence Switch Attached to Port (MPSP):** If set to 1, the platform supports a mechanical presence switch attached to this port. If cleared to 0, the platform does not support a mechanical presence switch attached to this port.
18	0x0 RW/O	**Hot Plug Capable Port (HPCP):** This indicates whether the this port is connected to a device which can be hot plugged. SATA by definition is hot-pluggable, but not all platforms are constructed to allow the device to be removed (it may be screwed into the chassis, for example). This bit can be used by system software to indicate a feature such as eject device to the end-user.
17	0x0 RW/V	**Port Multiplier Attached (PMA):** When set, a Port Multiplier is attached to the HBA for this port. When cleared, a Port Multiplier is not attached to the HBA for this port. This bit is a read only 0. when CAP.PMS = 0., and read/write when CAP.PMS = 1. Note that this bit is set by software; hardware does not auto-detect that a Port Multiplier is attached.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**RSVD0:** Reserved
15	0x0 RO/V	**Command List Running (CR):** When this bit is set it indicates that the command list DMA engine for the port is running.
14	0x0 RO/V	**FIS Receive Running (FR):** When this bit is set it indicates that the FIS Receive DMA engine for the port is running. Note to software: When FR bit stays set, please read the PxIS.PCS and PxSERR.DET.X to service the PCS interrupt accordingly if any
13	0x0 RO/V	**Mechanical Presence Switch State (MPSS):** The MPSS bit reports the state of a mechanical presence switch attached to this port. If CAP.SMPS is set to 1 and the mechanical presence switch is closed then this bit is cleared to 0. If CAP.SMPS is set to 1 and the mechanical presence switch is open then this bit is set to 1. If CAP.SMPS is set to 0 then this bit is cleared to 0. Software should only use this bit if both CAP.SMPS and PxCMD.MPSP are set to 1.
12:8	0x0 RO	**Current Command Slot (CCS):** Indicates the current command slot the HBA is processing. This field is valid when the PxCMD.ST bit is set, and is constantly updated by the HBA. This field can be updated as soon as the HBA recognizes an active command slot, or at some point soon after when it begins processing the command. When PxCMD.ST transitions from a 1 to a 0, the HBA will reset this field to 0. After PxCMD.ST transitions from 0 to 1, the highest priority slot to issue from next is command slot 0. After the first command has been issued, the highest priority slot to issue from next is PxCMD.CCS + 1. For example, after the HBA has issued its first command, if PxCMD.CCS = 0h and PxCI is set to 3h, the next command that will be issued is from command slot 1.
7:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RW	**FIS Receive Enable (FRE):** When set, the HBA may post received FISes into the FIS receive area pointed to by PxFB and PxFBU. When cleared, received FISes are not accepted by the HBA, except for the first D2H register FIS after the initialization sequence.
3	0x0 RW/1S	**Command List Override (CLO):** Setting this bit to 1 causes PxTFD.STS.BSY and PxTFD.STS.DRQ to be cleared to 0. This allows a software reset to be transmitted to the device regardless of whether the BSY and DRQ bits are still set in the PxTFD.STS register. The HBA sets this bit to 0 when PxTFD.STS.BSY and PxTFD.STS.DRQ have been cleared to 0. A write to this register with a value of 0 shall have no effect.
2	0x1 RO	**Power On Device (POD):** The SATA controller does not support cold presence detect.
1	0x0 RW/V	**Spin-Up Device (SUD):** This bit is read/write for HBAs that support staggered spin-up via CAP.SSS. This bit is read only 1. for HBAs that do not support staggered spin-up. On an edge detect from 0. to 1, the HBA shall start a COMRESET initialization sequence to the device. Clearing this bit causes no action on the interface. Clearing this bit to0 does not cause any OOB signal to be sent on the interface. When this bit is cleared to 0. and PxSCTL.DET = 0h, the HBA will enter listen mode.
0	0x0 RW	**Start (ST):** When set, the HBA may process the command list. When cleared, the HBA may not process the command list. Whenever this bit is changed from a 0 to a 1, the HBA starts processing the command list at entry 0. Whenever this bit is changed from a 1 to a 0, the PxCI and PxSACT register is cleared by the HBA upon the HBA putting the controller into an idle state. PxTFD shall be updated also.

50.4.113 Port [0-7] Task File Data (PxTFD7)—Offset 4A0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0000007Fh

BAR and Offset: [ABAR] + 4A0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:8	0x0 RO/V	**Error (ERR):** Contains the latest copy of the task file error register.
7	0x0 RO/V	**Status Busy (STS_BSY):** Status - Indicates the interface is busy.
6:4	0x7 RO/V	**Status Rsvd0 (STS_RSVD0):** Status - Not Applicable.
3	0x1 RO/V	**Status Drq (STS_DRQ):** Status - Indicates a data transfer is requested.
2:1	0x3 RO/V	**Status Rsvd1 (STS_RSVD1):** Status - Not Applicable.
0	0x1 RO/V	**Status Err (STS_ERR):** Status - Indicates an error during the transfer.

50.4.114 Port [0-7] Signature (PxSIG7)—Offset 4A4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: FFFFFFFFh

BAR and Offset: [ABAR] + 4A4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO/V	**Signature (SIG):** Contains the signature received from a device on the first D2H Register FIS.

50.4.115 Port [0-7] Serial ATA Status (PxSSTS7)—Offset 4A8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 4A8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD0:** Reserved
11:8	0x0 RO/V	**Interface Power Management (IPM):** Indicates the current interface state
7:4	0x0 RO/V	**Current Interface Speed (SPD):** Indicates the negotiated interface communication speed.
3:0	0x0 RO/V	**Device Detection (DET):** Indicates the interface device detection and Phy state.

50.4.116 Port [0-7] Serial ATA Control (PxSCTL7)—Offset 4ACh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 4ACh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RSVD0:** Reserved
19:16	0x0 RW	**Port Multiplier Port (PMP):** This field is not used by AHCI.
15:12	0x0 RW	**Select Power Management (SPM):** This field is not used by AHCI.
11:8	0x0 RW	**Interface Power Management Transitions Allowed (IPM):** Indicates which power states the HBA is allowed to transition to. If an interface power management state is not allowed via this register field, the HBA will not initiate that state and the HBA will PMNAKP any request from the device to enter that state.
7:4	0x0 RW	**Speed Allowed (SPD):** Indicates the highest allowable speed of the interface.
3:0	0x0 RW	**Device Detection Initialization (DET):** Controls the HBA.s device detection and interface initialization.

50.4.117 Port [0-7] Serial ATA Error (PxSERR7)—Offset 4B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 4B0h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/1C/V	**Diagnostics (DIAG):** Contains diagnostic error information for use by diagnostic software in validating correct operation or isolating failure modes.
15:0	0x0 RW/1C/V	**Error (ERR):** The ERR field contains error information for use by host software in determining the appropriate response to the error condition. If one or more of bits 11:8 of this register are set, the controller will stop the current transfer.

50.4.118 Port [0-7] Serial ATA Active (PxSACT7)—Offset 4B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 4B4h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Device Status (DS):** System software sets this bit for native command queuing commands prior to setting the PxCI.CI bit in the same command slot entry. This field is cleared via the Set Device Bits FIS.

50.4.119 Port [0-7] Commands Issued (PxCI7)—Offset 4B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 4B8h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1S/V	**Commands Issued (CI):** This field is set by software to indicate to the HBA that a command has been built in system memory for a command slot and may be sent to the device. When the HBA receives a FIS which clears the BSY, ERR, and DRQ bits for the command, it clears the corresponding bit in this register for that command slot. Bits in this field shall only be set to 1 by software when PxCMD.ST is set to 1.

50.4.120 Port [0-7] SNotification (PxSNTF7)—Offset 4BCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 4BCh

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**RSVD0:** Reserved
15:0	0x0 RW/1C/V	**PM Notify (PMN):** This field indicates whether a particular device with the corresponding PM Port number issued a Set Device Bits FIS to the host with the Notification bit set. PM Port 0h sets bit 0. PM Port Fh sets bit 15. Individual bits are cleared by software writing 1's to the corresponding bit positions. ***Note:*** While this field is reset to default on a HBA Reset, it is not reset by COMRESET or SRST

50.4.121 Enclosure Management Message Format (EM_MF)—Offset 580h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 580h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RSVD0:** Reserved
27:24	0x0 RW	**Message Type (MTYPE):** Specifies the type of the message. The message types are: • 0h = LED • 1h = SAF-TE • 2h = SES-2 • 3h = SGPIO (register based interface) • All other values reserved.
23:16	0x0 RW	**Data Size (DSIZE):** Specifies the data size in bytes. If the message (enclosure services command) has a data buffer that is associated with it that is transferred, the size of that data buffer is specified in this field. If there is no separate data buffer, this field shall have a value of '0'. The data directly follows the message in the message buffer. This value should always be '0'.
15:8	0x0 RW	**Message Size (MSIZE):** Specifies the size of the message in bytes. The message size does not include the one Dword header. A value of '0'. is invalid. The message size is always 4 bytes.
7:0	0x0 RO	**RSVD1:** Reserved

50.4.122 Enclosure Management LED (EM_LED)—Offset 584h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABAR] + 584h

ABAR Type: PCI Configuration Register (Size: 32 bits)
ABAR Reference: [B:0, D:(19,20), F:0] + 24h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Value (VAL):** This field describes the state of each LED for a particular location. There are three LEDs that may be supported by the HBA. Each LED has 3 bits of control. LED values are: • 000b - LED shall be off • 001b - LED shall be solid on as perceived by human eye • All other values reserved. The LED bit locations are: • Bits 2:0 - Activity LED (may be driven by hardware) • Bits 5:3 - Vendor Specific LED (e.g. locate) • Bits 8:6 - Vendor Specific LED (e.g. fault) • Bits 15:9 - Reserved. Vendor specific message is: Bit 3:0 - Vendor Specific Pattern; Bit 15:4 - Reserved.
15:8	0x0 RW	**Port Multiplier Information (PM):** Specifies slot specific information related to Port Multiplier. Bits 3:0 specify the Port Multiplier port number for the slot that requires the status update. • If a Port Multiplier is not attached to the device in the affected slot, the Port Multiplier port number shall be '0'. • Bits 7:4 are reserved. SATA does not support LED messages for devices behind a Port Multiplier. This byte should be 0.
7:0	0x0 RW	**HBA Information (HBA):** Specifies slot specific information related to the HBA. • Bits 4:0 - HBA port number for the slot that requires the status update. • Bit 5 - If set to '1', Value is a vendor specific message that applies to the entire enclosure. If cleared to '0', Value applies to the port specified in bits 4:0. • Bits 7:6 - Reserved.

§ §

51 USB Combo Controller - B0, D21, F0

51.1 Introduction and Index

The host-accessible registers for the USB Combo Controller are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

51.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 21 (decimal), Function 0. The offset addresses are listed.

Table 51-1. Summary of PCI Configuration Registers—0/21/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"Vendor ID (VID)—Offset 0h" on page 2006
2	2	19D0	"Device ID (DID)—Offset 2h" on page 2006
4	2	0000	"Command (CMD)—Offset 4h" on page 2007
6	2	0290	"Device Status (STS)—Offset 6h" on page 2008
8	1	00	"Revision ID (RID)—Offset 8h" on page 2010
9	1	30	"Programming Interface (PI)—Offset 9h" on page 2010
A	1	03	"Sub Class Code (SCC)—Offset Ah" on page 2010
B	2	0C	"Base Class Code (BCC)—Offset Bh" on page 2010
D	1	00	"Master Latency Timer (MLT)—Offset Dh" on page 2011
E	2	00	"Header Type (HT)—Offset Eh" on page 2011
10	8	0000000000000004	"Memory Base Address (MBAR)—Offset 10h" on page 2012
2C	2	0000	"USB Subsystem Vendor ID (SSVID)—Offset 2Ch" on page 2012
2E	2	0000	"USB Subsystem ID (SSID)—Offset 2Eh" on page 2013
34	1	70	"Capabilities Pointer (CAP_PTR)—Offset 34h" on page 2013
3C	1	00	"Interrupt Line (ILINE)—Offset 3Ch" on page 2013
3D	3	00	"Interrupt Pin (IPIN)—Offset 3Dh" on page 2014
40	4	000001FD	"XHC System Bus Configuration 1 (XHCC1)—Offset 40h" on page 2014
44	4	0003C000	"XHC System Bus Configuration 2 (XHCC2)—Offset 44h" on page 2016
50	4	00000000	"Clock Gating (XHCLKGTEN)—Offset 50h" on page 2018
58	4	00000000	"Audio Time Synchronization (AUDSYNC)—Offset 58h" on page 2021
60	1	30	"Serial Bus Release Number (SBRN)—Offset 60h" on page 2021
61	1	60	"Frame Length Adjustment (FLADJ)—Offset 61h" on page 2022
62	1	00	"Best Effort Service Latency (BESL)—Offset 62h" on page 2023
70	1	01	"PCI Power Management Capability ID (PM_CID)—Offset 70h" on page 2023
71	1	80	"Next Item Pointer #1 (PM_NEXT)—Offset 71h" on page 2023
72	2	C1C2	"Power Management Capabilities (PM_CAP)—Offset 72h" on page 2024
74	2	0008	"Power Management Control/Status (PM_CS)—Offset 74h" on page 2025
80	1	05	"Message Signaled Interrupt CID (MSI_CID)—Offset 80h" on page 2026
81	1	00	"Next item pointer (MSI_NEXT)—Offset 81h" on page 2026
82	2	0086	"Message Signaled Interrupt Message Control (MSI_MCTL)—Offset 82h" on page 2027
84	4	00000000	"Message Signaled Interrupt Message Address (MSI_MAD)—Offset 84h" on page 2028
88	4	00000000	"Message Signaled Interrupt Upper Address (MSI_MUAD)—Offset 88h" on page 2028
8C	2	0000	"Message Signaled Interrupt Message Data (MSI_MD)—Offset 8Ch" on page 2028
90	4	F0140009	"Device Idle Capability (DEVIDLE)—Offset 90h" on page 2029

Table 51-1. Summary of PCI Configuration Registers—0/21/0 (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
94	4	01400010	"Vendor Specific Header (VSHDR)—Offset 94h" on page 2029
98	4	00000000	"SW LTR POINTER (SWLTRPTR)—Offset 98h" on page 2030
9C	4	00080AC1	"Device Idle Pointer Register (DEVIDLEPTR)—Offset 9Ch" on page 2030
A0	2	0800	"Device Idle Power ON Latency (DEVIDLEPOL)—Offset A0h" on page 2031
A4	4	00002000	"High Speed Configuration 2 (HSCFG2)—Offset A4h" on page 2032
B0	4	00000000	"XHCI USB2 Overcurrent Pin Mapping 1 (U2OCM1)—Offset B0h" on page 2033
D0	4	00000000	"XHCI USB3 Overcurrent Pin Mapping 1 (U3OCM1)—Offset D0h" on page 2033
FC	4	00000002	"XHCC3—Offset FCh" on page 2034

51.1.2 Host Memory Space—MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	80	"Capability Registers Length (CAPLENGTH)—Offset 0h" on page 2035
2	2	0100	"Host Controller Interface Version Number (HCIVERSION)—Offset 2h" on page 2035
4	4	08000820	"Structural Parameters 1 (HCSPARAMS1)—Offset 4h" on page 2036
8	4	94000054	"Structural Parameters 2 (HCSPARAMS2)—Offset 8h" on page 2036
C	4	00040001	"Structural Parameters 3 (HCSPARAMS3)—Offset Ch" on page 2037
10	4	200077C1	"Capability Parameters (HCCPARAMS)—Offset 10h" on page 2038
14	4	00003000	"Doorbell Offset (DBOFF)—Offset 14h" on page 2039
18	4	00002000	"Runtime Register Space Offset (RTSOFF)—Offset 18h" on page 2039
80	4	00000000	"USB Command (USBCMD)—Offset 80h" on page 2040
84	4	00000001	"USB Status (USBSTS)—Offset 84h" on page 2041
88	4	00000001	"Page Size (PAGESIZE)—Offset 88h" on page 2042
94	4	00000000	"Device Notification Control (DNCTRL)—Offset 94h" on page 2042
98	4	00000000	"Command Ring Low (CRCR_LO)—Offset 98h" on page 2043
9C	4	00000000	"Command Ring High (CRCR_HI)—Offset 9Ch" on page 2043
B0	4	00000000	"Device Context Base Address Array Pointer Low (DCBAAP_LO)—Offset B0h" on page 2044
B4	4	00000000	"Device Context Base Address Array Pointer High (DCBAAP_HI)—Offset B4h" on page 2044
B8	4	00000000	"Configure (CONFIG)—Offset B8h" on page 2044
480	4	000002A0	"Port Status and Control USB2 (PORTSC1)—Offset 480h" on page 2045
484	4	00000000	"Port Power Management Status and Control USB2 (PORTPMSC1)—Offset 484h" on page 2047
48C	4	00000000	"Port X Hardware LPM Control Register (PORTHLPMC1)—Offset 48Ch" on page 2048
490	4	000002A0	"Port Status and Control USB2 (PORTSC2)—Offset 490h" on page 2049
494	4	00000000	"Port Power Management Status and Control USB2 (PORTPMSC2)—Offset 494h" on page 2051
49C	4	00000000	"Port X Hardware LPM Control Register (PORTHLPMC2)—Offset 49Ch" on page 2052
4A0	4	000002A0	"Port Status and Control USB2 (PORTSC3)—Offset 4A0h" on page 2053
4A4	4	00000000	"Port Power Management Status and Control USB2 (PORTPMSC3)—Offset 4A4h" on page 2055
4AC	4	00000000	"Port X Hardware LPM Control Register (PORTHLPMC3)—Offset 4ACh" on page 2056
4B0	4	000002A0	"Port Status and Control USB2 (PORTSC4)—Offset 4B0h" on page 2057
4B4	4	00000000	"Port Power Management Status and Control USB2 (PORTPMSC4)—Offset 4B4h" on page 2059
4BC	4	00000000	"Port X Hardware LPM Control Register (PORTHLPMC4)—Offset 4BCh" on page 2060
4C0	4	000002A0	"Port Status and Control USB3 (PORTSC5)—Offset 4C0h" on page 2061

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
4C4	4	00000000	"Port Power Management Status and Control USB3 (PORTPMSC5)—Offset 4C4h" on page 2064
4C8	4	00000000	"USB3 Port Link Info (PORTLI5)—Offset 4C8h" on page 2064
4D0	4	000002A0	"Port Status and Control USB3 (PORTSC6)—Offset 4D0h" on page 2065
4D4	4	00000000	"Port Power Management Status and Control USB3 (PORTPMSC6)—Offset 4D4h" on page 2068
4D8	4	00000000	"USB3 Port Link Info (PORTLI6)—Offset 4D8h" on page 2068
4E0	4	000002A0	"Port Status and Control USB3 (PORTSC7)—Offset 4E0h" on page 2069
4E4	4	00000000	"Port Power Management Status and Control USB3 (PORTPMSC7)—Offset 4E4h" on page 2072
4E8	4	00000000	"USB3 Port Link Info (PORTLI7)—Offset 4E8h" on page 2072
4F0	4	000002A0	"Port Status and Control USB3 (PORTSC8)—Offset 4F0h" on page 2073
4F4	4	00000000	"Port Power Management Status and Control USB3 (PORTPMSC8)—Offset 4F4h" on page 2076
4F8	4	00000000	"USB3 Port Link Info (PORTLI8)—Offset 4F8h" on page 2076
2000	4	00000000	"Microframe Index (RTMFINDEX)—Offset 2000h" on page 2076
2020	4	00000000	"Interrupter 1 Management (IMAN0)—Offset 2020h" on page 2077
2024	4	00000FA0	"Interrupter 1 Moderation (IMOD0)—Offset 2024h" on page 2077
2028	4	00000000	"Event Ring Segment Table Size 1 (ERSTSZ0)—Offset 2028h" on page 2077
2030	4	00000000	"Event Ring Segment Table Base Address Low 1 (ERSTBA_LO0)—Offset 2030h" on page 2078
2034	4	00000000	"Event Ring Segment Table Base Address High 1 (ERSTBA_HI0)—Offset 2034h" on page 2078
2038	4	00000000	"Event Ring Dequeue Pointer Low 1 (ERDP_LO0)—Offset 2038h" on page 2079
203C	4	00000000	"Event Ring Dequeue Pointer High 1 (ERDP_HI0)—Offset 203Ch" on page 2079
2040	4	00000000	"Interrupter 2 Management (IMAN1)—Offset 2040h" on page 2080
2044	4	00000FA0	"Interrupter 2 Moderation (IMOD1)—Offset 2044h" on page 2080
2048	4	00000000	"Event Ring Segment Table Size 2 (ERSTSZ1)—Offset 2048h" on page 2080
2050	4	00000000	"Event Ring Segment Table Base Address Low 2 (ERSTBA_LO1)—Offset 2050h" on page 2081
2054	4	00000000	"Event Ring Segment Table Base Address High 2 (ERSTBA_HI1)—Offset 2054h" on page 2081
2058	4	00000000	"Event Ring Dequeue Pointer Low 2 (ERDP_LO1)—Offset 2058h" on page 2081
205C	4	00000000	"Event Ring Dequeue Pointer High 2 (ERDP_HI1)—Offset 205Ch" on page 2082
2060	4	00000000	"Interrupter 3 Management (IMAN2)—Offset 2060h" on page 2082
2064	4	00000FA0	"Interrupter 3 Moderation (IMOD2)—Offset 2064h" on page 2082
2068	4	00000000	"Event Ring Segment Table Size 3 (ERSTSZ2)—Offset 2068h" on page 2083
2070	4	00000000	"Event Ring Segment Table Base Address Low 3 (ERSTBA_LO2)—Offset 2070h" on page 2083
2074	4	00000000	"Event Ring Segment Table Base Address High 3 (ERSTBA_HI2)—Offset 2074h" on page 2083
2078	4	00000000	"Event Ring Dequeue Pointer Low 3 (ERDP_LO2)—Offset 2078h" on page 2084
207C	4	00000000	"Event Ring Dequeue Pointer High 3 (ERDP_HI2)—Offset 207Ch" on page 2084
2080	4	00000000	"Interrupter 4 Management (IMAN3)—Offset 2080h" on page 2084

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
2084	4	00000FA0	"Interrupter 4 Moderation (IMOD3)—Offset 2084h" on page 2085
2088	4	00000000	"Event Ring Segment Table Size 4 (ERSTSZ3)—Offset 2088h" on page 2085
2090	4	00000000	"Event Ring Segment Table Base Address Low 4 (ERSTBA_LO3)—Offset 2090h" on page 2085
2094	4	00000000	"Event Ring Segment Table Base Address High 4 (ERSTBA_HI3)—Offset 2094h" on page 2086
2098	4	00000000	"Event Ring Dequeue Pointer Low 4 (ERDP_LO3)—Offset 2098h" on page 2086
209C	4	00000000	"Event Ring Dequeue Pointer High 4 (ERDP_HI3)—Offset 209Ch" on page 2086
20A0	4	00000000	"Interrupter 5 Management (IMAN4)—Offset 20A0h" on page 2087
20A4	4	00000FA0	"Interrupter 5 Moderation (IMOD4)—Offset 20A4h" on page 2087
20A8	4	00000000	"Event Ring Segment Table Size 5 (ERSTSZ4)—Offset 20A8h" on page 2087
20B0	4	00000000	"Event Ring Segment Table Base Address Low 5 (ERSTBA_LO4)—Offset 20B0h" on page 2088
20B4	4	00000000	"Event Ring Segment Table Base Address High 5 (ERSTBA_HI4)—Offset 20B4h" on page 2088
20B8	4	00000000	"Event Ring Dequeue Pointer Low 5 (ERDP_LO4)—Offset 20B8h" on page 2088
20BC	4	00000000	"Event Ring Dequeue Pointer High 5 (ERDP_HI4)—Offset 20BCh" on page 2089
20C0	4	00000000	"Interrupter 6 Management (IMAN5)—Offset 20C0h" on page 2089
20C4	4	00000FA0	"Interrupter 6 Moderation (IMOD5)—Offset 20C4h" on page 2089
20C8	4	00000000	"Event Ring Segment Table Size 6 (ERSTSZ5)—Offset 20C8h" on page 2090
20D0	4	00000000	"Event Ring Segment Table Base Address Low 6 (ERSTBA_LO5)—Offset 20D0h" on page 2090
20D4	4	00000000	"Event Ring Segment Table Base Address High 6 (ERSTBA_HI5)—Offset 20D4h" on page 2090
20D8	4	00000000	"Event Ring Dequeue Pointer Low 6 (ERDP_LO5)—Offset 20D8h" on page 2091
20DC	4	00000000	"Event Ring Dequeue Pointer High 6 (ERDP_HI5)—Offset 20DCh" on page 2091
20E0	4	00000000	"Interrupter 7 Management (IMAN6)—Offset 20E0h" on page 2091
20E4	4	00000FA0	"Interrupter 7 Moderation (IMOD6)—Offset 20E4h" on page 2092
20E8	4	00000000	"Event Ring Segment Table Size 7 (ERSTSZ6)—Offset 20E8h" on page 2092
20F0	4	00000000	"Event Ring Segment Table Base Address Low 7 (ERSTBA_LO6)—Offset 20F0h" on page 2092
20F4	4	00000000	"Event Ring Segment Table Base Address High 7 (ERSTBA_HI6)—Offset 20F4h" on page 2093
20F8	4	00000000	"Event Ring Dequeue Pointer Low 7 (ERDP_LO6)—Offset 20F8h" on page 2093
20FC	4	00000000	"Event Ring Dequeue Pointer High 7 (ERDP_HI6)—Offset 20FCh" on page 2093
2100	4	00000000	"Interrupter 8 Management (IMAN7)—Offset 2100h" on page 2094
2104	4	00000FA0	"Interrupter 8 Moderation (IMOD7)—Offset 2104h" on page 2094
2108	4	00000000	"Event Ring Segment Table Size 8 (ERSTSZ7)—Offset 2108h" on page 2094
2110	4	00000000	"Event Ring Segment Table Base Address Low 8 (ERSTBA_LO7)—Offset 2110h" on page 2095
2114	4	00000000	"Event Ring Segment Table Base Address High 8 (ERSTBA_HI7)—Offset 2114h" on page 2095
2118	4	00000000	"Event Ring Dequeue Pointer Low 8 (ERDP_LO7)—Offset 2118h" on page 2095

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
211C	4	00000000	"Event Ring Dequeue Pointer High 8 (ERDP_HI7)—Offset 211Ch" on page 2096
3000	4	00000000	"Door Bell 1 (DB0)—Offset 3000h" on page 2096
3004	4	00000000	"Door Bell 2 (DB1)—Offset 3004h" on page 2097
3008	4	00000000	"Door Bell 3 (DB2)—Offset 3008h" on page 2097
300C	4	00000000	"Door Bell 4 (DB3)—Offset 300Ch" on page 2098
3010	4	00000000	"Door Bell 5 (DB4)—Offset 3010h" on page 2098
3014	4	00000000	"Door Bell 6 (DB5)—Offset 3014h" on page 2099
3018	4	00000000	"Door Bell 7 (DB6)—Offset 3018h" on page 2099
301C	4	00000000	"Door Bell 8 (DB7)—Offset 301Ch" on page 2100
3020	4	00000000	"Door Bell 9 (DB8)—Offset 3020h" on page 2100
3024	4	00000000	"Door Bell 10 (DB9)—Offset 3024h" on page 2101
3028	4	00000000	"Door Bell 11 (DB10)—Offset 3028h" on page 2101
302C	4	00000000	"Door Bell 12 (DB11)—Offset 302Ch" on page 2102
3030	4	00000000	"Door Bell 13 (DB12)—Offset 3030h" on page 2102
3034	4	00000000	"Door Bell 14 (DB13)—Offset 3034h" on page 2103
3038	4	00000000	"Door Bell 15 (DB14)—Offset 3038h" on page 2103
303C	4	00000000	"Door Bell 16 (DB15)—Offset 303Ch" on page 2104
3040	4	00000000	"Door Bell 17 (DB16)—Offset 3040h" on page 2104
3044	4	00000000	"Door Bell 18 (DB17)—Offset 3044h" on page 2105
3048	4	00000000	"Door Bell 19 (DB18)—Offset 3048h" on page 2105
304C	4	00000000	"Door Bell 20 (DB19)—Offset 304Ch" on page 2106
3050	4	00000000	"Door Bell 21 (DB20)—Offset 3050h" on page 2106
3054	4	00000000	"Door Bell 22 (DB21)—Offset 3054h" on page 2107
3058	4	00000000	"Door Bell 23 (DB22)—Offset 3058h" on page 2107
305C	4	00000000	"Door Bell 24 (DB23)—Offset 305Ch" on page 2108
3060	4	00000000	"Door Bell 25 (DB24)—Offset 3060h" on page 2108
3064	4	00000000	"Door Bell 26 (DB25)—Offset 3064h" on page 2109
3068	4	00000000	"Door Bell 27 (DB26)—Offset 3068h" on page 2109
306C	4	00000000	"Door Bell 28 (DB27)—Offset 306Ch" on page 2110
3070	4	00000000	"Door Bell 29 (DB28)—Offset 3070h" on page 2110
3074	4	00000000	"Door Bell 30 (DB29)—Offset 3074h" on page 2111
3078	4	00000000	"Door Bell 31 (DB30)—Offset 3078h" on page 2111
307C	4	00000000	"Door Bell 32 (DB31)—Offset 307Ch" on page 2112
3080	4	00000000	"Door Bell 32 (DB32)—Offset 3080h" on page 2112
8004	4	20425355	"XECP_SUPP_USB2_1—Offset 8004h" on page 2113
8008	4	30190401	"XECP_SUPP_USB2_2—Offset 8008h" on page 2113
8024	4	20425355	"XECP_SUPP_USB3_1—Offset 8024h" on page 2114
8028	4	10000405	"XECP_SUPP_USB3_2—Offset 8028h" on page 2114
8070	4	004DFFC0	"Host Controller Capability (HOST_CTRL_CAP_REG)—Offset 8070h" on page 2114

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
8078	4	00000000	"Override EP Flow Control (HOST_CLR_MASK_REG)—Offset 8078h" on page 2115
807C	4	00000000	"Clear Active IN EP ID Control (HOST_CLR_IN_EP_VALID_REG)—Offset 807Ch" on page 2115
8080	4	00000000	"Clear Poll Mask Control (HOST_CLR_PMASK_REG)—Offset 8080h" on page 2116
8094	4	00008100	"Host Control Scheduler (HOST_CTRL_SCH_REG)—Offset 8094h" on page 2117
80A4	4	002DFF90	"Power Management Control (PMCTRL_REG)—Offset 80A4h" on page 2118
80A8	4	00315555	"PGCB Control (PGCBCTRL_REG)—Offset 80A8h" on page 2120
80AC	4	00000008	"D0I3 Control (DOI3CTRL_REG)—Offset 80ACh" on page 2123
80B0	4	0001037F	"HOST_CTRL_MISC_REG—Offset 80B0h" on page 2124
80BC	4	0000000F	"reg_SSPITPE_type (SSPITPE)—Offset 80BCh" on page 2126
80C0	4	015FC0F0	"AUX Reset Control (AUX_CTRL_REG)—Offset 80C0h" on page 2127
80C4	4	004A4008	"Super Speed Bandwidth Overload (HOST_BW_OV_SS_REG)—Offset 80C4h" on page 2130
80C8	4	0001A01F	"High Speed TT Bandwidth Overload (HOST_BW_OV_HS_REG)—Offset 80C8h" on page 2131
80CC	4	00014080	"Bandwidth Overload Full Low Speed (HOST_BW_OV_FS_LS_REG)—Offset 80CCh" on page 2131
80D0	4	00032010	"System Bandwidth Overload (HOST_BW_OV_SYS_REG)—Offset 80D0h" on page 2132
80D4	4	00000000	"Scheduler Async Delay (HOST_CTRL_SCH_ASYNC_DELAY_REG)—Offset 80D4h" on page 2133
80E0	4	808DBCA0	"AUX Power Management Control (AUX_CTRL_REG1)—Offset 80E0h" on page 2134
80E4	4	00000000	"Battery Charge (BATTERY_CHARGE_REG)—Offset 80E4h" on page 2137
80EC	4	18010000	"SuperSpeed Port Link Control (HOST_CTRL_PORT_LINK_REG)—Offset 80ECh" on page 2138
80F0	4	310803A0	"USB2 Port Link Control 1 (USB2_LINK_MGR_CTRL_REG1)—Offset 80F0h" on page 2140
80F4	4	80C40620	"USB2 Port Link Control 2 (USB2_LINK_MGR_CTRL_REG2)—Offset 80F4h" on page 2142
80F8	4	F865EB6B	"USB2 Port Link Control 3 (USB2_LINK_MGR_CTRL_REG3)—Offset 80F8h" on page 2142
80FC	4	00008003	"USB2 Port Link Control 4 (USB2_LINK_MGR_CTRL_REG4)—Offset 80FCh" on page 2143
810C	4	00008020	"Bandwidth Overload Burst (HOST_BW_OV_BURST_REG)—Offset 810Ch" on page 2143
8128	8	0F42528505647F42	"USB Max Bandwidth Control 4 (HOST_CTRL_BW_MAX_REG)—Offset 8128h" on page 2144
8140	4	0A019132	"Power Scheduler Control-0 (PWR_SCHED_CTRL0)—Offset 8140h" on page 2144
8154	4	81390206	"AUX Power Management Control (AUX_CTRL_REG2)—Offset 8154h" on page 2146
8164	4	000000FC	"USB2 PHY Power Management Control (USB2_PHY_PMC)—Offset 8164h" on page 2148
8168	4	000282EE	"USB Power Gating Control (USB_PGC)—Offset 8168h" on page 2149

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
816C	4	00000400	"xHCI Aux Clock Control Register (XHCI_AUX_CCR)—Offset 816Ch" on page 2150
8170	4	96090032	"USB LPM Parameters (USB_LPM_PARAM)—Offset 8170h" on page 2152
8174	4	0040047D	"xHC Latency Tolerance Parameters - LTV Control (XLTP_LTV1)—Offset 8174h" on page 2153
8178	4	000017FF	"xHC Latency Tolerance Parameters LTV Control 2 (XLTP_LTV2)—Offset 8178h" on page 2154
817C	4	00000000	"xHC Latency Tolerance Parameters - High Idle Time Control (XLTP_HITC)—Offset 817Ch" on page 2154
8180	4	00000000	"xHC Latency Tolerance Parameters - Medium Idle Time Control (XLTP_MITC)—Offset 8180h" on page 2155
8184	4	00000000	"xHC Latency Tolerance Parameters Low Idle Time Control (XLTP_LITC)—Offset 8184h" on page 2155
8188	4	00F42F42	"HOST_CTRL_BW_MAX3_REG—Offset 8188h" on page 2156
819C	4	00000000	"THRM_HOST_CTRL_REG—Offset 819Ch" on page 2157
81B4	4	0000000F	"THRM_HOST_CTRL_REG2—Offset 81B4h" on page 2158
81B8	4	000020C8	"LFPSONCOUNT_REG—Offset 81B8h" on page 2158
81BC	4	084204B0	"reg_D0i2_CTRL_REG_type (D0i2_CTRL_REG)—Offset 81BCh" on page 2160
81C0	4	00000000	"reg_D0i2_SCH_ALARM_CTRL_REG_type (D0i2_SCH_ALARM_CTRL_REG)—Offset 81C0h" on page 2162
81C4	4	00000000	"reg_USB2PMCTRL_REG_type (USB2PMCTRL_REG)—Offset 81C4h" on page 2163
83F8	4	00000000	"ECC_PARITY_ERROR_LOG_REG—Offset 83F8h" on page 2164
83FC	4	00000000	"ECC_POISONING_CTRL_REG—Offset 83FCh" on page 2166
8400	8	0000000000000000	"USB2_PORT_STATE_REG—Offset 8400h" on page 2167
8408	8	0000000000000000	"USB2_PORT_STATE_REG (USB3_PORT_STATE_REG)—Offset 8408h" on page 2167
8410	4	00010000	"FUS1_REG—Offset 8410h" on page 2168
8414	4	00000000	"FUS2_REG—Offset 8414h" on page 2169
841C	4	00000000	"STRAP1_REG—Offset 841Ch" on page 2169
8420	4	00000000	"STRAP2_REG—Offset 8420h" on page 2169
8424	4	00000000	"STRAP3_REG—Offset 8424h" on page 2170
8430	4	00000000	"DFT_REG1—Offset 8430h" on page 2171
8434	4	00000000	"DFT_REG2—Offset 8434h" on page 2172
8438	4	00000000	"DFT_REG3—Offset 8438h" on page 2173
843C	4	00000000	"dft_reg4 (DFT_REG4)—Offset 843Ch" on page 2173
8440	4	00000000	"dft_reg5 (DFT_REG5)—Offset 8440h" on page 2174
8448	4	00000000	"XECP_CMDM_STS0—Offset 8448h" on page 2175
8450	4	00000000	"XECP_CMDM_STS2—Offset 8450h" on page 2177
8454	4	00000000	"XECP_CMDM_STS3—Offset 8454h" on page 2177
8460	4	00000000	"AUX Power PHY Reset (UPORTS_PON_RST_REG)—Offset 8460h" on page 2177
8464	4	000D0000	"Latency Tolerance Control 0 (HOST_IF_LAT_TOL_CTRL_REG0)—Offset 8464h" on page 2178

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
846C	4	00002201	"USB Legacy Support Capability (USBLEGSUP)—Offset 846Ch" on page 2179
84F8	4	00000000	"USB2 Port Disable Override (USB2PDO)—Offset 84F8h" on page 2180
84FC	4	00000000	"USB3 Port Disable Override (USB3PDO)—Offset 84FCh" on page 2180
8604	2	0000	"Command (CMD_MMIO)—Offset 8604h" on page 2181
8606	2	0290	"Device Status (STS_MMIO)—Offset 8606h" on page 2182
8608	1	00	"Revision ID (RID_MMIO)—Offset 8608h" on page 2184
8609	1	30	"Programming Interface (PI_MMIO)—Offset 8609h" on page 2184
860A	1	03	"Sub Class Code (SCC_MMIO)—Offset 860Ah" on page 2184
860B	2	0C	"Base Class Code (BCC_MMIO)—Offset 860Bh" on page 2185
860D	1	00	"Master Latency Timer (MLT_MMIO)—Offset 860Dh" on page 2185
860E	2	00	"Header Type (HT_MMIO)—Offset 860Eh" on page 2185
8610	8	0000000000000004	"Memory Base Address (MBAR_MMIO)—Offset 8610h" on page 2186
862C	2	0000	"USB Subsystem Vendor ID (SSVID_MMIO)—Offset 862Ch" on page 2186
862E	2	0000	"USB Subsystem ID (SSID_MMIO)—Offset 862Eh" on page 2187
8634	1	70	"Capabilities Pointer (CAP_PTR_MMIO)—Offset 8634h" on page 2187
863C	1	00	"Interrupt Line (ILINE_MMIO)—Offset 863Ch" on page 2187
863D	3	00	"Interrupt Pin (IPIN_MMIO)—Offset 863Dh" on page 2188
8640	4	000001FD	"XHC System Bus Configuration 1 (XHCC1_MMIO)—Offset 8640h" on page 2189
8644	4	0003C000	"XHC System Bus Configuration 2 (XHCC2_MMIO)—Offset 8644h" on page 2191
8650	4	00000000	"Clock Gating (XHCLKGTEN_MMIO)—Offset 8650h" on page 2193
8658	4	00000000	"Audio Time Synchronization (AUDSYNC_MMIO)—Offset 8658h" on page 2196
8660	1	30	"Serial Bus Release Number (SBRN_MMIO)—Offset 8660h" on page 2196
8661	1	60	"Frame Length Adjustment (FLADJ_MMIO)—Offset 8661h" on page 2197
8662	1	00	"Best Effort Service Latency (BESL_MMIO)—Offset 8662h" on page 2197
8670	1	01	"PCI Power Management Capability ID (PM_CID_MMIO)—Offset 8670h" on page 2198
8671	1	80	"Next Item Pointer #1 (PM_NEXT_MMIO)—Offset 8671h" on page 2198
8672	2	C1C2	"Power Management Capabilities (PM_CAP_MMIO)—Offset 8672h" on page 2199
8674	2	0008	"Power Management Control/Status (PM_CS_MMIO)—Offset 8674h" on page 2200
8680	1	05	"Message Signaled Interrupt CID (MSI_CID_MMIO)—Offset 8680h" on page 2201
8681	1	00	"Next item pointer (MSI_NEXT_MMIO)—Offset 8681h" on page 2201
8682	2	0086	"Message Signaled Interrupt Message Control (MSI_MCTL_MMIO)—Offset 8682h" on page 2202
8684	4	00000000	"Message Signaled Interrupt Message Address (MSI_MAD_MMIO)—Offset 8684h" on page 2202
8688	4	00000000	"Message Signaled Interrupt Upper Address (MSI_MUAD_MMIO)—Offset 8688h" on page 2203
868C	2	0000	"Message Signaled Interrupt Message Data (MSI_MD_MMIO)—Offset 868Ch" on page 2203

Table 51-2. Summary of Memory Mapped I/O Registers—MBAR (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
8690	4	F0140009	"Device Idle Capability (DEVIDLE_MMIO)—Offset 8690h" on page 2204
8694	4	01400010	"Vendor Specific Header (VSHDR_MMIO)—Offset 8694h" on page 2204
8698	4	00000000	"SW LTR POINTER (SWLTRPTR_MMIO)—Offset 8698h" on page 2205
869C	4	00080AC1	"Device Idle Pointer Register (DEVIDLEPTR_MMIO)—Offset 869Ch" on page 2205
86A0	2	0800	"Device Idle Power ON Latency (DEVIDLEPOL_MMIO)—Offset 86A0h" on page 2206
86A4	4	00002000	"High Speed Configuration 2 (HSCFG2_MMIO)—Offset 86A4h" on page 2207
86B0	4	00000000	"XHCI USB2 Overcurrent Pin Mapping 1 (U2OCM1_MMIO)—Offset 86B0h" on page 2208
86D0	4	00000000	"XHCI USB3 Overcurrent Pin Mapping 1 (U3OCM1_MMIO)—Offset 86D0h" on page 2208
86FC	4	00000002	"XHCC3 (XHCC3_MMIO)—Offset 86FCh" on page 2209
8700	4	0005000A	"Debug Capability ID Register (DCID)—Offset 8700h" on page 2209
8704	4	00000000	"Debug Capability Doorbell Register (DCDB)—Offset 8704h" on page 2210
8708	4	00000000	"Debug Capability Event Ring Segment Table Size Register (DCERSTSZ)—Offset 8708h" on page 2210
8710	8	0000000000000000	"Debug Capability Event Ring Segment Table Base Address Register (DCERSTBA)—Offset 8710h" on page 2211
8718	8	0000000000000000	"Debug Capability Event Ring Dequeue Pointer Register (DCERDP)—Offset 8718h" on page 2211
8720	4	00000000	"Debug Capability Control Register (DCCTRL)—Offset 8720h" on page 2212
8724	4	00000000	"Debug Capability Status Register (DCST)—Offset 8724h" on page 2213
8728	4	00000080	"Debug Capability Port Status and Control Register (DCPORTSC)—Offset 8728h" on page 2214
8730	8	0000000000000000	"Debug Capability Context Pointer Register (DCCP)—Offset 8730h" on page 2216
8738	4	80870000	"Debug Capability Device Descriptor Info Register 1 (DCDDI1)—Offset 8738h" on page 2216
873C	4	00000000	"Debug Capability Device Descriptor Info Register 2 (DCDDI2)—Offset 873Ch" on page 2217
8740	4	000030C3	"Debug Capability Descriptor Parameters (DCDP)—Offset 8740h" on page 2217
8748	4	00000000	"Debug Device Control ODMA (DBGDEV_CTRL_ODMA_REG)—Offset 8748h" on page 2218
8760	4	00000000	"DBC Control Register 1 (DBCCTL_REG)—Offset 8760h" on page 2220

51.2 Registers in Configuration Space

51.2.1 Vendor ID (VID)—Offset 0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**Vendor ID (VID):** Reserved. **Power Well:** Core

51.2.2 Device ID (DID)—Offset 2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 2h

Default: 19D0h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x19d0 RO/V	**Device ID (DID):** **Power Well:** Core

51.2.3 Command (CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
10	0x0 RW	**Interrupt Disable (ID):** When cleared to 0, the function is capable of generating interrupts. When 1, the function can not generate its interrupt to the interrupt controller ***Note:*** The corresponding Interrupt Status bit is not affected by the interrupt enable. **Power Well:** Core
9	0x0 RO	**Fast Back to Back Enable (FBE):** Reserved. **Power Well:** Core
8	0x0 RW	**SERR# Enable (SERR):** When set to 1, the XHC is capable of generating (internally) SERR#. **Power Well:** Core
7	0x0 RO	**Wait Cycle Control (WCC):** Reserved. **Power Well:** Core
6	0x0 RW	**Parity Error Response (PER):** When set to 1, the XHCI Host Controller will check for correct parity (on its internal interface) and halt operation when bad parity is detected during the data phase as recommended by the XHCI specification. ***Note:*** This applies to both requests and completions from the system interface. This bit must be set in order for the parity errors to generate SERR#. **Power Well:** Core
5	0x0 RO	**VGA Palette Snoop (VPS):** Reserved. **Power Well:** Core
4	0x0 RO	**Memory Write Invalidate (MWI):** Reserved. **Power Well:** Core
3	0x0 RO	**Special Cycle Enable (SCE):** Reserved. **Power Well:** Core
2	0x0 RW	**Bus Master Enable (BME):** When set, it allows XHC to act as a bus master. When cleared, it disable XHC from initiating transactions on the system bus. **Power Well:** Core
1	0x0 RW	**Memory Space Enable (MSE):** This bit controls access to the XHC Memory Space registers. If this bit is set, accesses to the XHC registers are enabled. The Base Address register for the XHC should be programmed before this bit is set. **Power Well:** Core
0	0x0 RO	**I/O Space Enable (IOSE):** Reserved as 0. Read-Only. **Power Well:** Core

51.2.4 Device Status (STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 6h

Default: 0290h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**Detected Parity Error (DPE):** This bit is set by the SoC whenever a parity error is seen on the internal interface to the XHC host controller, regardless of the setting of bit 6 or bit 8 in the Command register or any other conditions. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
14	0x0 RW/1C	**Signaled System Error (SSE):** This bit is set by the SoC whenever it signals SERR# (internally). The SERR_EN bit (bit 8 in the Command Register) must be 1 for this bit to be set. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
13	0x0 RW/1C	**Received Master-Abort Status (RMA):** This bit is set when XHC, as a master, receives a master-abort status on a memory access. This is treated as a Host Error and halts the DMA engines. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
12	0x0 RW/1C	**Received Target Abort Status (RTA):** This bit is set when XHC, as a master, receives a target abort status on a memory access. This is treated as a Host Error and halts the DMA engines. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
11	0x0 RW/1C	**Signaled Target-Abort Status (STA):** This bit is used to indicate when the XHC function responds to a cycle with a target abort. **Power Well:** Core
10:9	0x1 RO	**DEVSEL# Timing Status (DEVT):** This 2-bit field defines the timing for DEVSEL# assertion. Read-Only. **Power Well:** Core
8	0x0 RW/1C	**Master Data Parity Error Detected (MDPED):** This bit is set by the SoC whenever a data parity error is detected on a XHC read completion packet on the internal interface to the XHC host controller and bit 6 of the Command register is set to 1. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
7	0x1 RO	**Fast Back-to-Back Capable (FBBC):** Reserved as 1 Read-Only. **Power Well:** Core
6	0x0 RO	**User Definable Features (UDF):** Reserved as 0. Read-Only. **Power Well:** Core
5	0x0 RO	**66 MHz Capable (MC):** Reserved as 0. Read-Only. **Power Well:** Core
4	0x1 RO	**Capabilities List (CL):** Hardwired to 1 indicating that offset 34h contains a valid capabilities pointer. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RO/V	**Interrupt Status (IS):** This read-only bit reflects the state of this function's interrupt at the input of the enable/disable logic. This bit is a 1 when the interrupt is asserted. This bit will be 0 when the interrupt is deasserted. The value reported in this bit is independent of the value in the Interrupt Enable bit. **Power Well:** Core
2:0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

51.2.5 Revision ID (RID)—Offset 8h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Revision ID (RID):** **Power Well:** Core

51.2.6 Programming Interface (PI)—Offset 9h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 9h

Default: 30h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x30 RO	**Programming Interface (PI):** A value of 30h indicates that this USB Host Controller conforms to the XHCI specification. **Power Well:** Core

51.2.7 Sub Class Code (SCC)—Offset Ah

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + Ah

Default: 03h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x3 RO	**Sub Class Code (SCC):** A value of 03h indicates that this is a Universal Serial Bus Host Controller. **Power Well:** Core

51.2.8 Base Class Code (BCC)—Offset Bh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + Bh

Default: 0Ch

Bit Range	Default & Access	Field Name (ID): Description
7:0	0xc RO	**Base Class Code (BCC):** A value of 0Ch indicates that this is a Serial Bus controller. **Power Well:** Core

51.2.9 Master Latency Timer (MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Because the XHC controller is internally implemented with arbitration on an internal interface, it does not need a master latency timer. The bits will be fixed at 0. **Power Well:** Core

51.2.10 Header Type (HT)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Multi-Function Bit (MFB):** Read only indicating single function device. **Power Well:** Core
6:0	0x0 RO	**Configuration layout (CL):** Hardwired to 0 to indicate a standard PCI configuration layout. **Power Well:** Core

51.2.11 Memory Base Address (MBAR)—Offset 10h

Value in this register will be different after the enumeration process.

Type: PCI Configuration Register (Size: 64 bits)

Offset: [B:0, D:21, F:0] + 10h

Default: 0000000000000004h

Bit Range	Default & Access	Field Name (ID): Description
63:16	0x0 RW	**Base Address (BA):** Bits (63:16) correspond to memory address signals (63:16), respectively. This gives 64 KB of relocatable memory space aligned to 64 KB boundaries. **Power Well:** Core
15:4	0x0 RO	**Reserved (RSVD):** Reserved. Read-Only 0, this indicates that this function is requesting an 64KB block of memory. **Power Well:** Core
3	0x0 RO	**Prefetchable:** This bit is hardwired to 0 indicating that this range should not be pre-fetched. **Power Well:** Core
2:1	0x2 RO	**Type:** If this field is hardwired to 00 it indicates that this range can be mapped anywhere within 32-bit address space. If this field is hardwired to 10 it indicates that this range can be mapped anywhere within 64-bit address space. **Power Well:** Core
0	0x0 RO	**Resource Type Indicator (RTE):** This bit is hardwired to 0 indicating that the base address field in this register maps to memory space. **Power Well:** Core

51.2.12 USB Subsystem Vendor ID (SSVID)—Offset 2Ch

This register is modified and maintained by BIOS

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 2Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/L	**USB Subsystem Vendor ID (SSVID):** This register, in combination with the USB Subsystem ID register, enables the operating system to distinguish each subsystem from the others. **Power Well:** Core

51.2.13 USB Subsystem ID (SSID)—Offset 2Eh

This register is modified and maintained by BIOS

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:21, F:0] + 2Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/L	**USB Subsystem ID (SSID):** BIOS sets the value in this register to identify the Subsystem ID. This register, in combination with the Subsystem Vendor ID register, enables the operating system to distinguish each subsystem from other(s). **Power Well:** Core

51.2.14 Capabilities Pointer (CAP_PTR)—Offset 34h

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:21, F:0] + 34h

Default: 70h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x70 RO	**Capabilities Pointer (CAP_PTR):** This register points to the starting offset of the capabilities ranges. **Power Well:** Core

51.2.15 Interrupt Line (ILINE)—Offset 3Ch

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:21, F:0] + 3Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Line (ILINE):** This data is not used by the SoC. It is used as a scratchpad register to communicate to software the interrupt line that the interrupt pin is connected to. **Power Well:** Core

51.2.16 Interrupt Pin (IPIN)—Offset 3Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 3Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/L	**Interrupt pin (IPIN):** Bits 7:0 reflect the Interrupt Pin assigned to the host controller by the platform (and are hardwired). **Power Well:** Core

51.2.17 XHC System Bus Configuration 1 (XHCC1)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 40h

Default: 000001FDh

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/O	**Access Control (ACCTRL):** This bit is used by BIOS to lock/unlock lockable bits. When set to '1' the write access to bits locked by this bit is disabled (locked state). When set to '0', the write access to bit locked by this bit is enabled (unlocked state). Writable once after platform reset. **Power Well:** Core
30:25	0x0 RW	**ECO1:** **Power Well:** Core
24	0x0 RW	**Master/Target Abort SERR (RMTASERR):** When set, it allows the out-of-band error reporting from the xHCI Controller to be reported as SERR# (if SERR# reporting is enabled) and thus set the STS.SSE bit. **Power Well:** Core
23	0x0 RW/C	**Unsupported Request Detected (URD):** Set the HW when xHCI Controller received an unsupported request posted cycle. Cleared by SW when the bit is written with value of '1'. **Power Well:** Core
22	0x0 RW	**Unsupported Request Report Enable (URRE):** When set this bit allows the URD bit to be reported as SERR# (if SERR# reporting is enabled) and thus set the STS.SSE bit. **Power Well:** Core
21:19	0x0 RW	**Inactivity Initiated L1 Enable (IIL1E):** If programmed to non-zero, it allows L1 power managed to be enabled after the time-out period specified. • 000: Disabled • 001: 32 bb_cclk • 010: 64 bb_cclk • 011: 128 bb_cclk • 100: 256 bb_cclk • 101: 512 bb_cclk • 110: 1024 bb_cclk • 111: 131072 bb_cclk **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RW	**XHC Initiated L1 Enable (XHCIL1E):** If set, allow the XHC initiated L1 power management to be enabled. **Power Well:** Core
17	0x0 RW	**D3 Initiated L1 Enable (D3IL1E):** If set, allow PCI device state D3 initiated L1 power management to be enables. This bit can only be set if the XHCI L1 Override P2 chicken bit is set. **Power Well:** Core
16:12	0x0 RW	**Periodic Complete Pre Wake Time (PCPWT):** This allows for platform wake time before the next scheduled periodic transaction. The value programmed in this field represents the # of bytes consumed in the current micro-frame which is required to allow for the periodic complete to de-assert. This allows for a programmable time to cause the periodic complete to de-assert prior to the start of the next micro-frame. Register Format: Bits (16:12) represents the # of bytes remaining with a 256B granularity. Periodic Complete will de-assert if the bytes consumed in the current micro-frame is less **Power Well:** Core
11	0x0 RW	**SW Assisted xHC Idle (SWAXHCI):** This bit being set will indicate xHC idleness (through SW means), which must be a '1' to allow L1 entry, and subsequently allow backbone clock to be gated. This bit is to be set by Intel xHCI driver after checking that the xHCI Controller will stay in idle state for a significant period of time, e.g. all ports disconnected. This bit can be cleared under the following conditions (see SWAXHCI Policy bits in xHC System Bus Configuration 2 register): n SW: SW could write 0 to clear this bit. n HW: HW, under policy control, will clear this bit on an MMIO access to the Host Controller. n HW: HW, under policy control, will clear this bit when HW exits Idle state. **Power Well:** Core
10:8	0x1 RW	**L23 to Host Reset Acknowledge Wait Count (L23HRAWC):** If programmed to non zero, it allows a wait period after the L23 PHY has shutdown before returning host reset acknowledge to PMC. • 000: Disabled • 001: 128 bb_cclk • 010: 256 bb_cclk • 011: 512 bb_cclk • 100: 1024 bb_cclk • 101: 2048 bb_cclk • 110: 4096 bb_cclk • 111: 131072 bb_cclk **Power Well:** Core
7:6	0x3 RW	**Upstream Type Arbiter Grant Count Posted (UTAGCP):** Grant count for IOSF upstream L2 request type arbiter for posted type. **Power Well:** Core
5:4	0x3 RW	**Upstream Type Arbiter Grant Count Non Posted (UDAGCNP):** Grant count for IOSF upstream L2 type arbiter for non-posted type. **Power Well:** Core
3:2	0x3 RW	**Upstream Type Arbiter Grant Count Completion (UDAGCCP) (UDAGCCP):** Grant count for IOSF upstream L2 type arbiter for completion type. **Power Well:** Core
1:0	0x1 RW	**Upstream Device Arbiter Grant Count (UDAGC) (UDAGC):** Grant count for IOSF upstream L1 device arbiter. **Power Well:** Core

51.2.18 XHC System Bus Configuration 2 (XHCC2)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 44h

Default: 0003C000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**OC Configuration Done (OCCFGDONE):** This bit is used by BIOS to prevent spurious switching during OC configuration. It must be set by BIOS after configuration of the OC mapping bits is complete. Once this bit is set, OC mapping shall not be changed by SW. **Power Well:** SUS
30:26	0x0 RW	**ECO1:** **Power Well:** Core
25	0x0 RW	**DMA Request Boundary Crossing Control (DREQBCC):** This bit controls the boundary crossing limit of each Read/Write Request. • 0: 4KB • 1: 64B **Power Well:** Core
24:22	0x0 RW	**IDMA Write Request Size Control (IDMA_WRREQSZCTRL):** Write Request Size Control: This bit controls the maximum size of each Write Request. • 000: 128B • 001: 256B • 011 - 110: Reserved • 111: 64B **Power Well:** Core
21	0x0 RW	**XHC Upstream Read Relaxed Ordering Enable (XHCUPRDROE):** This policy controls the Relaxed Ordering attribute for upstream reads. • 0 - xHC will clear RO for all upstream read requests. • 1 - xHC will set RO for all upstream read requests. **Power Well:** Core
20	0x0 RW	**IOSF Sideband Register Access Disable (IOSFSRAD):** When set, it disables the IOSF sideband interface from accepting any host space register access. **Power Well:** Core
19:14	0xf RW	**Upstream Non-Posted Pre-Allocation (UNPPA):** This field reserves data sizes, in 64 byte chunks, of the downstream completion resource. This value is zero based. 000000 - 111111: Pre-allocate 64 bytes - 4096 bytes If set greater than the default allows over-allocation. If set less than default allows under-allocation. Only allowed to be programmed when BME = 0 and no outstanding downstream completion. **Power Well:** Core
13:12	0x0 RW	**SW Assisted xHC Idle Policy (SWAXHCIP):** Note: Irrespective of the setting of this field, SW write of 0 to SWAXHCI will clear the bit. • 00b (default): xHC HW clears SWAXHCI bit upon: n MMIO access to Host Controller OR n xHC HW exits Idle state • 01b: xHC HW does not autonomously clear SWAXHCI bit. The bit could be cleared only by SW. • 10b: xHC HW clears SWAXHCI upon MMIO acces to Host Controller. xHC HW exit from Idle state will not clear SWAXHCI. • 11b: Reserved **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
11	0x0 RW	**MMIO Read After MMIO Write Delay Disable (RAWDD):** This field controls delay on MMIO Read after MMIO Write. • 0b (Default): Delay MMIO Read after MMIO Write • 1b: Do not delay MMIO Read after MMIO Write Note that this delay applies after the second of the two DW writes in the case where the IOSF Gasket splits a QW write into two single DW writes to the IP. **Power Well:** Core
10	0x0 RW	**MMIO Write After MMIO Write Delay Enable (WAWDE):** This field controls delay on MMIO Write after previous MMIO Write. • 0b (Default): Do not delay MMIO Write after previous MMIO Write • 1b: Delay MMIO Write after previous MMIO Write Note that the delay count does not apply on the second of the two DW writes that are generated by IOSF Gasket when it splits a QW write into two. In other words, the second of the two DW writes could happen without any delay with respect to the first DW write. This choice is being made for ease of ECO. The delay count, in this case, will apply after the second of the two DW writes. **Power Well:** Core
9:8	0x0 RW	**SW Assisted Cx Inhibit (SWACXIHB):** This field controls how the DMI L1 inhibit signal from USB3 to PMC will behave. • 00: Never inhibit Cx • 01: Inhibit Cx when Isochronous Endpoint is active (PPT Behavior) • 10: Inhibit Cx when Periodic Active as defined in 40.4.3.2.1 • 11: Always inhibit Cx **Power Well:** Core
7:6	0x0 RW	**SW Assisted DMI L1 Inhibit (SWADMIL1IHB):** This field controls how the DMI L1 inhibit signal from USB3 to DMI will behave. • 00: Never inhibit DMI L1. • 01: Inhibit DMI L1 when Isochronous Endpoint is active (PPT Behavior). • 10: Inhibit DMI L1 when Priodic Active as defined in 40.4.3.2.1. • 11: Inhibit DMI L1 if XHCC1.SWAXHCI = 0. **Power Well:** Core
5:3	0x0 RW	**L1 Force P2 Clock Gating Wait Count (L1FP2CGWC):** If programmed to non zero, it allows L1 force P2 gating off the clock to be delayed after the time-out period specified. If wake up event is detected before the time-out, pclk remains alive and trigger L1 exit as though CPU host is causing the wake, • 000: Disabled • 001: 128 bb_cclk • 010: 256 bb_cclk • 011: 512 bb_cclk • 100: 1024 bb_cclk • 101: 2048 bb_cclk • 110: 4096 bb_cclk • 111: 131072 bb_cclk **Power Well:** Core
2:0	0x0 RW	**Read Request Size Control (RDREQSZCTRL):** Read Request Size Control: This bit controls the maximum size of each Read Request. • 000: 128B • 001: 256B • 010: 512B • 011 - 110: Reserved • 111: 64B **Power Well:** Core

51.2.19 Clock Gating (XHCLKGTEN)—Offset 50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 50h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**Rsvd2:** Reserved **Power Well:** Core
28	0x0 RW	**Naking USB2.0 EPs for Backbone Clock Gating and PLL Shutdown (NUEFBCGPS):** This field controls whether Naking USB2.0 EPs, once in Naking low priority schedule, should be considered as active for the considerations for backbone clock gating and PLL shutdown or not. • 0: Naking USB2.0 EPs are not considered to be active for Backbone Clock Gating and PLL Shutdown evaluation. • 1: Naking USB2.0 EPs are considered to be active for Backbone clock gating and PLL shutdown evaluation. **Power Well:** Core
27	0x0 RW	**SRAM Power Gate Enable (SRAMPGTEN):** This register enables the SRAM Power Gating when PLL shutdown conditions for all clock domains have been met • 0 - Disallow SRAM Power Gating. • 1 - Allow SRAM Power Gating **Power Well:** Core
26	0x0 RW	**SS Link PLL Shutdown Enable (SSLSE):** This register enables the SS P3 state to be exposed to PXP PLL Shutdown conditions on behalf of all USB SS Ports on top of trunk clock gating. • 0 - P3 state NOT allowed to result in PXP PLL shutdown. • 1- P3 state allowed to result in PXP PLL shutdown **Power Well:** Core
25	0x0 RW	**USB2 PLL Shutdown Enable (USB2PLLSE):** When set, this bit allows USB2 PLL to be shutdown when HS Link trunk clock is gated, and xHC can tolerate PLL spin up time for subsequent clock request. ***Note:*** If USB2 PLL Shutdown Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. **Power Well:** Core
24	0x0 RW	**IOSF Sideband Trunk Clock Gating Enable (IOSFSTCGE):** When set, this bit allows the IOSF sideband clock trunk to be gated when idle conditions are met. **Power Well:** Core
23:20	0x0 RW	**HS Backbone PXP Trunk Clock Gate Enable (HSTCGE):** This register determines the HS Ux state(s) which will be exposed to Backbone PXP trunk gating of core clock. Uy is a state allowed to result in trunk gating when ss_tcg_ux_en(x) is asserted. • (0) ==) U0 or deeper • (1) ==) NA (no support for U1) • (2) ==) U2 (L1) or deeper • (3) ==) U3 (L2) or deeper **Power Well:** Core
19:16	0x0 RW	**SS Backbone PXP Trunk Clock Gate Enable (SSTCGE):** This register determines the SS Ux state(s) which will be exposed to Backbone PXP trunk gating of core clock. Uy is a state allowed to result in trunk gating when ss_tcg_ux_en(x) is asserted. (0) ==) U0 or deeper (1) ==) U1 or deeper (2) ==) U2 or deeper (3) ==) U3 or deeper **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**XHC Ignore_EU3S (XHCIGEU3S):** This register determines if the xHC will use the EU3S as a condition to allow for Frame timer gating. • 0 - xHC may allow frame timer to be gated when EU3S is set and all ports are in the required state. • 1 - xHC may allow frame timer to be gated regardless of EU3S. **Power Well:** Core
14	0x0 RW	**XHC Frame Timer Clock Shutdown Enable (XHCFTCLKSE):** This register determines if the xHC will allow the frame timer clock to be gated. • 0 - xHC will not allow ICC PLL 96MHz output to be shutdown thus keeping the frame timer running. • 1 - xHC will allow ICC PLL 96MHz output to be shutdown under specific conditions. **Power Well:** Core
13	0x0 RW	**XHC Backbone PXP Trunk Clock Gate In Presence of ISOCH EP (XHCBBTCGIPISO):** This register controls the policy on allowing Backbone PXP trunk clock gate in the presence of IDLE ISOCH EP s with active DB. Allows the periodic active to be used in enabling Backbone PXP trunk clock gating of core clock. • 0 Trunk gate of core clock is not allowed when ISOCH EP DB is set and ISOCH EP s are idle. • 1 Allow trunk gate of core clock when ISOCH EP DB is set and ISOCH EP s are idle. **Power Well:** Core
12	0x0 RW	**XHC HS Backbone PXP Trunk Clock Gate U2 non RWE (XHCHSTCGU2NRWE):** This register controls the policy on allowing Backbone PXP trunk gating of core clock when there is at least 1 non Remote Wake Enabled HS Port in U2. • 0 Prevent trunk gate of core clock when a non RWE HS Port is in U2. • 1 Allow trunk gate of core clock when a non RWE HS Port is in U2. **Power Well:** Core
11:10	0x0 RW	**XHC USB2 PLL Shutdown Lx Enable (XHCUSB2PLLSDLE):** This register determines the HS Link state(s) which will be exposed to USB2 PLL Shutdown conditions on behalf of all USB2 HS Ports. Ly is a state allowed to result in USB2 PLL Shutdown when en(x) is asserted. • (0) ==) L1 or deeper • (1) ==) L2 or deeper **Power Well:** Core
9:8	0x0 RW	**HS Backbone PXP PLL Shutdown Ux Enable (HSUXDMIPLLSE):** This register determines the Ux state(s) which will be exposed to PXP PLL Shutdown conditions. PLL Shutdown is allowed in: • 00b Disabled (Link states shall be disabled for DMI PLL shutdown) • 01b U0 or conditions for 10b setting. • 10b U2 or conditions for 11b setting. • 10b U3, Disconnected, Disabled or Powered-Off. **Power Well:** Core
7:5	0x0 RW	**SS Backbone PXP PLL Shutdown Ux Enable (SSPLLSUE):** This register determines the Ux state(s) which will be exposed to DMI PLL Shutdown conditions. PLL Shutdown is allowed in: • 000b Disabled (Link states shall be ignored for DMI PLL shutdown). • 001b U0 or conditions for 010b setting • 010b U1 or conditions for 011b setting • 011b U2 or conditions for 100b setting • 100b U3, Disconnected, Disabled or Powered-Off **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW	**XHC Backbone Local Clock Gating Enable (XHCBLCGE):** When set, this bit allows XHCI Controller IP backbone clock to be locally gated when idle conditions are met. ***Note:*** If XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. **Power Well:** Core
3	0x0 RW	**HS Link Trunk Clock Gating Enable (HSLTCGE):** When set, this bit allows High Speed Link control's 480 MHz and its 48/60 MHz link clock trunk to be gated when idle conditions are met. ***Note:*** If XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. BIOS need to query fuses to see if HW is enabled. **Power Well:** Core
2	0x0 RW	**SS Link Trunk Clock Gating Enable (SSLTCGE):** When set, this bit allows the SuperSpeed Link control's 250 MHz and its divided 125 MHz link clock trunk to ge gated when idle conditions are met. ***Note:*** If XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. BIOS need to query fuses to see if HW is enabled. **Power Well:** Core
1	0x0 RW	**IOSF Backbone Trunk Clock Gating Enable (IOSFBTCGE):** When set, this bit allows the IOSF backbone clock trunk to be gated when idle conditions are met. **Power Well:** Core
0	0x0 RW	**IOSF Gasket Backbone Local Clock Gating Enable (IOSFBLCGE):** When set, this bit allows the IOSF Gasket backbone clock to be locally gated when idle conditions are met. ***Note:*** If XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. BIOS need to query fuses to see if HW is enabled. **Power Well:** Core

51.2.20 Audio Time Synchronization (AUDSYNC)—Offset 58h

This 32 bit register is used for audio stream synchronization across different devices. Global signal sample_now captures a value in AUDSYNC register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 58h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
29:16	0x0 RO/V	**Captured Frame List Current Index/Frame Number (CMFI):** The value in this register is updated in response to sample_now signal. Bits (29:16) reflect state of bits (13:0) of FRINDEX **Power Well:** Core
15:13	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
12:0	0x0 RO/V	**Captured Micro-frame BLIF (CMFB):** The value is updated in response to sample_now signal and provides information about offset within micro-frame. Captured value represents number of 8 high-speed bit time units from start of micro-frame. At the beginning of micro-frame captured value will be 0 and increase to maximum value at the end. Default maximum value is 7499 but it may be changed as result of adjustment done in FLA. **Power Well:** Core

51.2.21 Serial Bus Release Number (SBRN)—Offset 60h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 60h

Default: 30h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x30 RO	**Serial Bus Release Number (SBRN):** A value of 30h indicates that this controller follows USB release 3.0. **Power Well:** SUS

51.2.22 Frame Length Adjustment (FLADJ)—Offset 61h

This feature is used to adjust any offset from the clock source that generates the clock that drives the SOF counter. When a new value is written into these six bits, the length of the frame is adjusted. Its initial programmed value is system dependent based on the accuracy of hardware USB clock and is initialized by system BIOS. This register should only be modified when the HChalted bit in the USBSTS register is a one. Changing value of this register while the host controller is operating yields undefined results.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 61h

Default: 60h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD):** **Power Well:** SUS
6	0x1 RO	**No Frame Length Timing Capability (NO_FRAME_LENGTH_TIMING_CAP):** This flag is set to 1 to indicate that the host controller does not support a programmable Frame Length Timing Value field. **Power Well:** Core
5:0	0x20 RO	**Frame Length Timing Value (FLTV):** SOF micro-frame length) is equal to 59488 + value in this field. The default value is decimal 32 (20h), which gives a SOF cycle time of 60000. Frame Length (number of High Speed bit times) FLADJ Value (decimal) (decimal) • 59488 0 (00h) • 59504 1 (01h) • 59520 2 (02h) • ... • 59984 31 (1Fh) • 60000 32 (20h) • ... • 60480 62 (3Eh) • 60496 63 (3Fh) Each decimal value change to this register corresponds to 16 high-speed bit times. The SOF cycle time (number of SOF counter clock periods to generate a SOF micro-frame length) is equal to 59488 + value in this field. The default value is decimal 32 (20h), which gives a SOF cycle time of 60000. Frame Length (# High Speed bit times) FLADJ Value **Power Well:** SUS

51.2.23 Best Effort Service Latency (BESL)—Offset 62h

Best Effort Service Latency.

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 62h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW/L	**Default Best Effort Service Latency Deep (DBESLD):** Default Best Effort Service Latency (DBESLD) If the value of this field is non-zero, it defines the recommended value for programming the PORTPMSC register BESLD field. This is programmed by BIOS based on platform parameters. **Power Well:** Core
3:0	0x0 RW/L	**Default Best Effort Service Latency (DBESL):** If the value of this field is non-zero, it defines the recommended value for programming the PORTPMSC register BESL field. This is programmed by BIOS based on platform parameters. **Power Well:** Core

51.2.24 PCI Power Management Capability ID (PM_CID)—Offset 70h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 70h

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RO	**PCI Power Management Capability ID (PM_CID):** A value of 01h indicates that this is a PCI Power Management capabilities field. **Power Well:** Core

51.2.25 Next Item Pointer #1 (PM_NEXT)—Offset 71h

This register is modified and maintained by BIOS

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 71h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x80 RW/L	**Next Item Pointer #1 (PM_NEXT):** This register defaults to 80h, which indicates that the next capability registers begin at configuration offset 80h. This register is writable when the Access Control bit is set to '0'. This allows BIOS to effectively hide the next capability registers, if necessary. This register should only be written during system initialization before the plug-and-play software has enabled any master-initiated traffic. Values of: 80h implies next capability is MSI 00h implies that MSI capability is hidden. ***Note:*** This value is never expected to be programmed. **Power Well:** Core

51.2.26 Power Management Capabilities (PM_CAP)—Offset 72h

Normally, this register is read-only to report capabilities to the power management software. In order to report different power management capabilities depending on the system in which the SoC is used, the write access to this register is controlled by the Access Control bit (ACCTRL). The value written to this register does not affect the hardware other than changing the value returned during a read. This register is modified and maintained by BIOS

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 72h

Default: C1C2h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x18 RW/L	**PME_Support:** This 5-bit field indicates the power states in which the function may assert PME#. The SoC XHC does not support the D1 or D2 states. For all other states, the SoC XHC is capable of generating PME#. Software should never need to modify this field. **Power Well:** Core
10	0x0 RW/L	**D2_Support:** The D2 state is not supported. **Power Well:** Core
9	0x0 RW/L	**D1_Support:** The D1 state is not supported. **Power Well:** Core
8:6	0x7 RW/L	**Aux_Current:** The SoC XHC reports 375mA maximum Suspend well current required when in the D3cold state. This value can be written by BIOS when a more accurate value is known. **Power Well:** Core
5	0x0 RW/L	**DSI:** The SoC reports 0, indicating that no device-specific initialization is required. **Power Well:** Core
4	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
3	0x0 RW/L	**PME Clock (PMEClock):** The SoC reports 0, indicating that no PCI clock is required to generate PME#. **Power Well:** Core
2:0	0x2 RW/L	**Version:** The SoC reports 010, indicating that it complies with Revision 1.1 of the PCI Power Management Specification. **Power Well:** Core

51.2.27 Power Management Control/Status (PM_CS)—Offset 74h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 74h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**PME_Status:** This bit is set when the SoC XHC would normally assert the PME# signal independent of the state of the PME_En bit. Writing a 1 to this bit will clear it and cause the internal PME to deassert (if enabled). Writing a 0 has no effect. This bit must be explicitly cleared by the operating system each time the operating system is loaded. **Power Well:** SUS
14:13	0x0 RO	**RSVD:** Reserved **Power Well:** Core
12:9	0x0 RO	**RSVD:** Reserved **Power Well:** Core
8	0x0 RW	**PME_En:** A 1 enables the SoC XHC to generate an internal PME signal when PME_Status is 1. This bit must be explicitly cleared by the operating system each time it is initially loaded. **Power Well:** SUS
7:4	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. **Power Well:** Core
2	0x0 RO	**Reserved (RSVD2):** Reserved. **Power Well:** Core
1:0	0x0 RW	**PowerState:** This 2-bit field is used both to determine the current power state of XHC function and to set a new power state. The definition of the field values are: • 00b - D0 state • 11b - D3hot state **Power Well:** Core

51.2.28 Message Signaled Interrupt CID (MSI_CID)—Offset 80h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 80h

Default: 05h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x5 RO	**Capability ID (CID):** Indicates that this is an MSI capability. **Power Well:** Core

51.2.29 Next item pointer (MSI_NEXT)—Offset 81h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:21, F:0] + 81h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Next Pointer (NEXT):** Indicates that this is the last item on the capability list. **Power Well:** Core

51.2.30 Message Signaled Interrupt Message Control (MSI_MCTL)—Offset 82h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 82h

Default: 0086h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RO	**Per-Vector Masking Capable (PVM):** Specifies whether controller supports MSI per vector masking. Not supported **Power Well:** Core
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages. This device is 64-bit capable. **Power Well:** Core
6:4	0x0 RW	**Multiple Message Enable (MME):** Indicates the number of messages the controller should assert. This device supports multiple message MSI. **Power Well:** Core
3:1	0x3 RO	**Multiple Message Capable (MMC):** Indicates the number of messages the controller wishes to assert. This field must be set by HW to reflect the number of Interrupters supported. Encoding number of Vectors requested (number of Interrupters) • 000 1 • 001 2 • 010 4 • 011 8 • 100 16 • 101 32 • 110-111 Reserved **Power Well:** Core
0	0x0 RW	**MSI Enable (MSIE):** If set to 1, MSI is enabled and the traditional interrupt pins are not used to generate interrupts. If cleared to 0, MSI operation is disabled and the traditional interrupt pins are used. **Power Well:** Core

51.2.31 Message Signaled Interrupt Message Address (MSI_MAD)—Offset 84h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Addr:** Lower DW of system specified message address, always DWORD aligned. **Power Well:** Core
1:0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

51.2.32 Message Signaled Interrupt Upper Address (MSI_MUAD)—Offset 88h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 88h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Addr (UpperAddr):** Upper DW of system specified message address. **Power Well:** Core

51.2.33 Message Signaled Interrupt Message Data (MSI_MD)—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + 8Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data:** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the lower word (PCI AD(15:0)) during the data phase of the MSI memory write transaction. **Power Well:** Core

51.2.34 Device Idle Capability (DEVIDLE)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 90h

Default: F0140009h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RO	**VID:** Reserved. **Power Well:** Core
27:24	0x0 RO	**REV:** Reserved. **Power Well:** Core
23:16	0x14 RO	**Length (LENGTH):** Indicates that this capability is 16 bytes long. **Power Well:** Core
15:8	0x0 RO	**Next Capability Pointer (NCP):** This field contains the offset to the next PCI Capability structure or 000h if no other items exist in the linked list of Capabilities. **Power Well:** Core
7:0	0x9 RO	**Capability ID (CID):** Reserved. **Power Well:** Core

51.2.35 Vendor Specific Header (VSHDR)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 94h

Default: 01400010h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x14 RO	**VSEC Length (VSEC_LENGTH):** This field indicates the number of bytes in the entire VSEC structure, including the PCI Extended Capability header, the Vendor- Specific header, and the Vendor-Specific register **Power Well:** Core
19:16	0x0 RO	**VSEC Rev (VSEC_REV):** This field is a vendor-defined version number that indicates the version of the VSEC structure. Software must qualify the Vendor ID and VSEC ID before interpreting this field. **Power Well:** Core
15:0	0x10 RO	**VSEC ID (VSEC_ID):** This field is a vendor-defined ID number that indicates the nature and format of the VSEC structure. Software must qualify the Vendor ID before interpreting this field. **Power Well:** Core

51.2.36 SW LTR POINTER (SWLTRPTR)—Offset 98h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**SW LTR Update MMIO Offset Location (SW_LTR_UPDT_MMIO_OFFSET):** This register contains the location pointer to the SW LTR register in MMIO space, as an offset from the specified BAR. The value of this register is a don't care, if the Valid bit is not set. **Power Well:** Core
3:1	0x0 RO	**Base Address Register Number (BARNUM):** Contains the 0s based AR Number of the BAR which contains the location of the SW LTR MMIO register. When counting BAR Numbers, all BARs, regardless of size and type, consume one BAR Number. Bar 0 is the 1st BAR. The value of this register is a don't care, if the Valid bit is not set. **Power Well:** Core
0	0x0 RO	**Valid (VALID):** Set to 1 to indicate that the function has implemented a SW LTR register as specified in the DevIdle that can be located using the SWLTRLOC register and BARNUM. Set to 0 to indicate that the function has not implemented a SW LTR register that is compliant to the DevIdle definition. This could be because the function has not implemented SW LTR at all, or has a device specific version of SW LTR. **Power Well:** Core

51.2.37 Device Idle Pointer Register (DEVIDLEPTR)—Offset 9Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + 9Ch

Default: 00080AC1h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x80ac RW/L	**DevIdle MMIO Offset Location (DEVIDLELOC):** This register contains the location pointer to the DevIdle register in MMIO space, as an offset from the specified BAR. The value of this register is a don't care, if the Valid bit is not set. **Power Well:** Core
3:1	0x0 RO	**Base Address Register Number (BARNUM):** Contains the 0s based BAR Number of the BAR which contains the location of the DevIdle MMIO register. When counting BAR Numbers, all BARs, regardless of size and type, consume one BAR Number. Bar 0 is the 1st BAR. The value of this register is a don't care, if the Valid bit is not set. **Power Well:** Core
0	0x1 RW/L	**Valid (VALID):** Set to 1 to indicate that the function has implemented a DevIdle register as specified in the DevIdle that can be located using the DEVIDLELOC register and BARNUM. Set to 0 to indicate that the function has not implemented a DevIdle register that is compliant to the DevIdle definition. This could be because the function has not implemented DevIdle at all, or has a device specific version of DevIdle. **Power Well:** Core

51.2.38 Device Idle Power ON Latency (DEVIDLEPOL)—Offset A0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:21, F:0] + A0h

Default: 0800h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
12:10	0x2 RW/L	**Power On Latency Scale (POLS):** Latency Scale multiplier: • 010: 1us • 011: 32us • All other settings are reserved. The value of this register is multiplied with the Power On Latency Value (POLV) to provide the DevIdle power on exit latency multiplier scale from 1us to 32ms. This register is defined to be RWO (read-write-once) to allow BIOS to set the initial value. This register is undefined if the DevIdle.Valid bit is 0. **Power Well:** Core
9:0	0x0 RW/L	**Power On Latency Value (POLV):** 10-bit value that is multiplied by the Power On Latency Scale. A value of 0 indicates a power on latency of less than 1us. This register is defined to be RWO (read-write-once) to allow BIOS to set the initial value. This register is undefined if the DevIdle.Valid bit is 0. **Power Well:** Core

51.2.39 High Speed Configuration 2 (HSCFG2)—Offset A4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + A4h

Default: 00002000h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
18	0x0 RW	**PORT1_HOST_MODE_OVERRIDE:** When set, this bit causes the Host_Device mux on port 1 to be forced into the Host mode. **Power Well:** Core
17:16	0x0 RW	**eUSB2SEL:** The two bits are associate with USB2 ports 1 - bit 16 and 2 - bit 2 • 0: Port is mapped to USB2 • 1: Port is mapped to eUSB2 **Power Well:** Core
15	0x0 RW	**HS ASYNC Active IN Mask (HSAAIM):** Determines if the Async Active will mask/ignore IN EP s. • 0 HS ASYNC Active will include IN EP s. • 1 HS ASYNC Active will mask/ignore IN EP s. **Power Well:** Core
14	0x0 RW	**HS OUT ASYNC Active Polling EP Mask (HSOAAPEPM):** Determines if the Async Active for OUT HS/FS/LS masks/ignores EP s that are polling/PINGing (HS) due to NAK. • 0 HS OUT ASYNC Active will include EP s that are polling. • 1 HS OUT ASYNC Active will mask/ignore EP s that are polling. **Power Well:** Core
13	0x1 RW	**HS IN ASYNC Active Polling EP Mask (HSIAAPEPM):** Determines if the Async Active for IN HS/FS/LS masks/ignores EP s that are polling due to NAK. • 0 HS IN ASYNC Active will include EP s that are polling. • 1 HS IN ASYNC Active will mask/ignore EP s that are polling. **Power Well:** Core
12:11	0x0 RW	**HS INTR IN Periodic Active Policy Control (HSIIPAPC):** Controls how the HS INTR IN periodic active is used to generate the global periodic active. This will determine how the smallest service interval among active EP s and number of active EP s are used. • 0 HS INTR IN periodic active will be used to generate periodic active if Service Interval Threshold OR Numb of EP Threshold values meet the requirement. • 1 HS INTR IN periodic active will be used to generate periodic active if Service Interval Threshold AND Numb of EP Threshold values meet the requirement. • 2 Always allow HS INTR EP s to be used in the generation of the global Periodic Active indication. • 3 Never allow HS INTR EP s to be used in the generation of the global Periodic Active indication **Power Well:** Core
10:4	0x0 RW	**HS INTR IN Periodic Active Num of EP Threshold (HSIIPANEPT):** Defines the threshold used to determine if Periodic Active may include HS/FS/LS INTR IN EP active indication. **Power Well:** Core
3:0	0x0 RW	**HS INTR IN Periodic Active Service Interval Threshold (HSIIPASIT):** Defines the Service Interval threshold used to determine if Periodic Active will include HS/FS/LS INTR IN EP active indication. **Power Well:** Core

51.2.40 XHCI USB2 Overcurrent Pin Mapping 1 (U2OCM1)—Offset B0h

The RW/L property of this register is controlled by OCCFDONE bit.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Rsvd:** Reserved **Power Well:** SUS
3:0	0x0 RW/L	**OC Mapping (OCM):** Reserved. **Power Well:** SUS

51.2.41 XHCI USB3 Overcurrent Pin Mapping 1 (U3OCM1)—Offset D0h

The RW/L property of this register is controlled by OCCFDONE bit.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Rsvd:** Reserved. **Power Well:** Core
3:0	0x0 RW/L	**OC Mapping (OCM):** Reserved. **Power Well:** SUS

51.2.42 XHCC3—Offset FCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:21, F:0] + FCh

Default: 00000002h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (Rsvd1):** Reserved **Power Well:** SUS
3	0x0 RW	**Error Handling : Disable Command Parity Check (DISABLE_COMMAND_PARITY_CHECK):** When set to 1, XHCI Host Controller disables checking of Command Parity on command received as a target on its IOSF Primary interface **Power Well:** SUS
2	0x0 RW	**Error Handling : Disable Data Parity Check (DISABLE_DATA_PARITY_CHECK):** When set to 1, XHCI Host Controller disables checking of Data Parity on data received as a target on its IOSF Primary interface **Power Well:** SUS
1	0x1 RW	**Error Handling : Enable ECC Error Response (ENABLE_ECC_ERROR_RESPONSE):** When set to 1, XHCI Host Controller will check for ECC on RFs (that support ECC) and halt operation when uncorrectable ECC is detected **Power Well:** SUS
0	0x0 RW/L	**Function Disable (FXN_DISABLE):** When set will disable the xHC from being operational. **Power Well:** SUS

51.3 Registers in Memory Space—MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) MBAR described in Section 51.2.11, "Memory Base Address (MBAR)—Offset 10h" on page 2012.

51.3.1 Capability Registers Length (CAPLENGTH)—Offset 0h

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 80h

BAR and Offset: [MBAR] + 0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x80 RW/L	**Capability Registers Length (CAPLENGTH):** Reserved. **Power Well:** Core

51.3.2 Host Controller Interface Version Number (HCIVERSION)—Offset 2h

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0100h

BAR and Offset: [MBAR] + 2h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x100 RW/L	**Host Controller Interface Version Number (HCIVERSION):** Reserved. **Power Well:** Core

51.3.3 Structural Parameters 1 (HCSPARAMS1)—Offset 4h

This register is modified and maintained by BIOS.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 08000820h

BAR and Offset: [MBAR] + 4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x8 RW/L	**Number of Ports (MaxPorts):** Reserved. **Power Well:** Core
23:19	0x0 RW/L	**Rsvd1:** Reserved. **Power Well:** Core
18:8	0x8 RW/L	**Number of Interrupters (MaxIntrs):** Reserved. **Power Well:** Core
7:0	0x20 RW/L	**Number of Device Slots (MaxSlots):** Reserved. **Power Well:** Core

51.3.4 Structural Parameters 2 (HCSPARAMS2)—Offset 8h

This register is modified and maintained by BIOS.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 94000054h

BAR and Offset: [MBAR] + 8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x12 RW/L	**Max Scratchpad Buffers LO (MaxScratchpadBufs):** Reserved. **Power Well:** Core
26	0x1 RW/L	**Scratchpad Restore (SPR):** Reserved. **Power Well:** Core
25:21	0x0 RW/L	**Max Scratchpad Buffers HI (MaxScratchpadBufs_HI):** Reserved. **Power Well:** Core
20:8	0x0 RW/L	**Rsvd1:** Reserved. **Power Well:** Core
7:4	0x5 RW/L	**Event Ring Segment Table Max (ERSTMax):** Reserved. **Power Well:** Core
3:0	0x4 RW/L	**Isochronous Scheduling Threshold (IST):** Reserved. **Power Well:** Core

51.3.5 Structural Parameters 3 (HCSPARAMS3)—Offset Ch

This register is modified and maintained by BIOS.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00040001h

BAR and Offset: [MBAR] + Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x4 RW/L	**U2 Device Exit Latency (U2DEL):** Reserved. **Power Well:** Core
15:8	0x0 RW/L	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x1 RW/L	**U1 Device Exit Latency (U1DEL):** Reserved. **Power Well:** Core

51.3.6 Capability Parameters (HCCPARAMS)—Offset 10h

This register is modified and maintained by BIOS.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 10h

Default: 200077C1h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x2000 RW/L	**xHCI Extended Capabilities Pointer (xECP):** Reserved. **Power Well:** Core
15:12	0x7 RW/L	**Maximum Primary Stream Array Size (MaxPSASize):** Reserved. **Power Well:** Core
11	0x0 RW/L	**Contiguous Frame ID Capability (CFC):** Reserved. **Power Well:** Core
10	0x1 RW/L	**Stopped EDLTA Capabilty (SEC):** Reserved. **Power Well:** Core
9	0x1 RW/L	**Stopped - Short Packet Capability (SPC):** Reserved. **Power Well:** Core
8	0x1 RW/L	**Parst All Event Data (PAE):** Reserved. **Power Well:** Core
7	0x1 RW/L	**No Secondary SID Support (NSS):** Reserved. **Power Well:** Core
6	0x1 RW/L	**Latency Tolerance Messaging Capability (LTC):** Reserved. **Power Well:** Core
5	0x0 RW/L	**Light HC Reset Capability (LHRC):** Reserved. **Power Well:** Core
4	0x0 RW/L	**Port Indicators (PIND):** Reserved. **Power Well:** Core
3	0x0 RW/L	**Port Power Control (PPC):** Reserved. **Power Well:** Core
2	0x0 RW/L	**Context Size (CSZ):** Reserved. **Power Well:** Core
1	0x0 RW/L	**BW Negotiation Capability (BNC):** Reserved. **Power Well:** Core
0	0x1 RW/L	**64-bit Addressing Capability (AC64):** Reserved. **Power Well:** Core

51.3.7 Doorbell Offset (DBOFF)—Offset 14h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00003000h

BAR and Offset: [MBAR] + 14h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0xc00 RO	**Doorbell Array Offset (DBAO):** Reserved. **Power Well:** Core
1:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.8 Runtime Register Space Offset (RTSOFF)—Offset 18h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00002000h

BAR and Offset: [MBAR] + 18h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x100 RO	**Runtime Register Space Offset (RTRSO):** Reserved. **Power Well:** Core
4:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.9 USB Command (USBCMD)—Offset 80h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 80h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
11	0x0 RW	**Enable U3 MFINDEX Stop (EU3S):** Reserved. **Power Well:** Core
10	0x0 RW	**Enable Wrap Event (EWE):** Reserved. **Power Well:** Core
9	0x0 RW	**Controller Restore State (CRS):** Reserved. **Power Well:** Core
8	0x0 RW	**Controller Save State (CSS):** Reserved. **Power Well:** Core
7	0x0 RW	**Light Host Controller Reset (LHCRST):** Reserved. **Power Well:** Core
6:4	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
3	0x0 RW	**Host System Error Enable (HSEE):** Reserved. **Power Well:** Core
2	0x0 RW	**Interrupter Enable (INTE):** Reserved. **Power Well:** Core
1	0x0 RW	**Host Controller Reset (HCRST):** Reserved. **Power Well:** Core
0	0x0 RW	**Run/Stop (RS):** Reserved. **Power Well:** Core

51.3.10 USB Status (USBSTS)—Offset 84h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000001h

BAR and Offset: [MBAR] + 84h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:13	0x0 RO	**Rsvd3:** Reserved. **Power Well:** Core
12	0x0 RO	**Host Controller Error (HCE):** This bit is not preset in HC, this is deviation from XHCI 1.0 spec. **Power Well:** Core
11	0x0 RO	**Controller Not Ready (CNR):** This is deviation from XHCI 1.0 spec. **Power Well:** Core
10	0x0 RW/C	**Save/Restore Error (SRE):** Reserved. **Power Well:** Core
9	0x0 RO	**Restore State Status (RSS):** Reserved. **Power Well:** Core
8	0x0 RO	**Save State Status (SSS):** Reserved. **Power Well:** Core
7:5	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
4	0x0 RW/C	**Port Change Detect (PCD):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Interrupt (EINT):** Reserved. **Power Well:** Core
2	0x0 RW/C	**Host System Error (HSE):** Reserved. **Power Well:** Core
1	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
0	0x1 RO	**HCHalted (HCH):** Reserved. **Power Well:** Core

51.3.11 Page Size (PAGESIZE)—Offset 88h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000001h

BAR and Offset: [MBAR] + 88h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x1 RO	**Page Size (PAGESIZE):** Reserved. **Power Well:** Core

51.3.12 Device Notification Control (DNCTRL)—Offset 94h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 94h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Notification Enable (N0_N15):** Reserved. **Power Well:** Core

51.3.13 Command Ring Low (CRCR_LO)—Offset 98h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 98h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Command Ring Pointer (CRP):** Reserved. **Power Well:** Core
5:4	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
3	0x0 RO	**Command Ring Running (CRR):** Reserved. **Power Well:** Core
2	0x0 RW/1S	**Command Abort (CA):** Reserved. **Power Well:** Core
1	0x0 RW/1S	**Command Stop (CS):** Reserved. **Power Well:** Core
0	0x0 RW	**Ring Cycle State (RCS):** Reserved. **Power Well:** Core

51.3.14 Command Ring High (CRCR_HI)—Offset 9Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 9Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Command Ring Pointer (CRP):** Reserved. **Power Well:** Core

51.3.15 Device Context Base Address Array Pointer Low (DCBAAP_LO)—Offset B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + B0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Device Context Base Address Array Pointer (DCBAAP):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.16 Device Context Base Address Array Pointer High (DCBAAP_HI)—Offset B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + B4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Device Context Base Address Array Pointer (DCBAAP):** Reserved. **Power Well:** Core

51.3.17 Configure (CONFIG)—Offset B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + B8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**Max Device Slots Enabled (MaxSlotsEn):** Reserved. **Power Well:** Core

51.3.18 Port Status and Control USB2 (PORTSC1)—Offset 480h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 480h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Reserved:** Reserved. **Power Well:** SUS
30	0x0 RW/L	**Device Removable (DR):** Reserved. **Power Well:** Core
29:28	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
27	0x0 RW	**Wake on Over-current Enable (WOE):** ***Note:*** This register is sticky. **Power Well:** SUS
26	0x0 RW	**Wake on Disconnect Enable (WDE):** ***Note:*** This register is sticky. **Power Well:** SUS
25	0x0 RW	**Wake on Connect Enable (WCE):** ***Note:*** This register is sticky. **Power Well:** SUS
24	0x0 RO	**Cold Attach Status (CAS):** Reserved. **Power Well:** SUS
23	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
22	0x0 RW/C	**Port Link State Change (PLC):** ***Note:*** This register is sticky. **Power Well:** SUS
21	0x0 RW/C	**Port Reset Change (PRC):** ***Note:*** This register is sticky. **Power Well:** SUS
20	0x0 RW/C	**Over-current Change (OCC):** ***Note:*** This register is sticky. **Power Well:** SUS
19	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** ***Note:*** This register is sticky. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW/C	**Connect Status Change (CSC):** ***Note:*** This register is sticky. **Power Well:** SUS
16	0x0 RW	**Port Link State Write Strobe (LWS):** Reserved. **Power Well:** SUS
15:14	0x0 RW	**Port Indicator Control (PIC):** ***Note:*** This register is sticky. **Power Well:** SUS
13:10	0x0 RW	**Port Speed (PortSpeed):** ***Note:*** This register is sticky. **Power Well:** SUS
9	0x1 RW	**Port Power (PP):** ***Note:*** This register is sticky. **Power Well:** SUS
8:5	0x5 RW	**Port Link State (PLS):** ***Note:*** This register is sticky. **Power Well:** SUS
4	0x0 RW/1S	**Port Reset (PR):** Reserved. **Power Well:** SUS
3	0x0 RW	**Over-current Active (OCA):** ***Note:*** This register is sticky. **Power Well:** SUS
2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW/C	**Port Enabled Disabled (PED):** ***Note:*** Note: This register is sticky. **Power Well:** SUS
0	0x0 RW	**Current Connect Status (CCS):** ***Note:*** This register is sticky. **Power Well:** SUS

51.3.19 Port Power Management Status and Control USB2 (PORTPMSC1)—Offset 484h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 484h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Port Test Control (PTC):** When this field is '0', the port is not operating in a test mode. (Default) A non-zero value indicates that the port is operating in test mode in indicated by the specific value. A non-zero Port Test Control value is only valid to a port that is in the Disabled state. If the port is not in this state, the xHC shall respond with the Port Test Control field set to Port Test Control Error. The encoding of the Test Mode bits for a USB 2.0 port are: Value Test Mode • 0h - Test mode not enabled • 1h - Test J_STATE • 2h - Test K_STATE • 3h - Test SE0_NAK • 4h - Test Packet • 5h - Test FORCE_ENABLE • 6h-14h - Reserved. • 15 - Port Test Control Error
27:17	0x0 RO	Reserved.
16	0x0 RW	**Hardware LPM Enable (HLE):** • 0 - Disable • 1 - Enable. When this bit is a 1, hardware controlled LPM shall be enabled for this port. Refer to Section 4 of the USB 2.0 LPM Specification for more information.
15:8	0x0 RO	Reserved.
7:4	0x0 RW	**Best Effort Service Latency:** System software sets this field to indicate the recipient device how long the xHCI will driver resume if it initiates an exit from L1.
3	0x0 RW	**Remote Wake Enable (RWE):** The host system sets this flag to enable or disable the device for remote wake from L1. • 0 - disable • 1 - enable The value of this flag will temporarily (while in L1) override the current setting of the Remote Wake feature set by the standard Set/ClearFeature() commands defined in Universal Serial Bus Specification, Revision 2.0, Chapter 9.
2:0	0x0 RW	**L1 Status (L1S):** This field is used by software to determine whether an L1-based suspend request was successful.

51.3.20 Port X Hardware LPM Control Register (PORTHLPMC1)—Offset 48Ch

There are 9 PORTHLPMC registers at offsets 48Ch, 49Ch, 4ACh, 4BCh, 4CCh, 4DCh, 4ECh, 4FCh, 50Ch This register is reset only by platform hardware during cold reset or in response to a Host Controller Reset (HCRST). The definition for the fields depend on the protocol supported. For USB3 this register is reserved and shall be treated by software as RsvdP. For USB2 the definition is given below. Fields contain parameters necessary for xHC to automatically generate an LPM Token to the downstream device.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 48Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
13:10	0x0 RW	**Host Initiated Resume Duration-Deep (HIRDD):** System software sets this field to indicate to the recipient device how long the xHC will drive resume if an exit from L1. The HIRDD value is is encoded as follows: • 0h: 50 us (default) • 1h: 125 us • 2h: 200 us • ... • Fh: 1.175ms The value of 0h is interpreted as 50 us. Each incrementing value adds 75 us to the previous value. **Power Well:** SUS
9:2	0x0 RW	**L1 Timeout (L1_TO):** Timeout value for L1 inactivity timer. This field shall be set to 00h by assertion of PR to '1'. Following are permissible values: • 00h: 128 us (default) • 01h: 256 us • ... • FFh: 65,280us ***Note:*** This register is sticky. **Power Well:** SUS
1:0	0x0 RW	**Host Initiated Resume Duration Mode (HIRDM):** Indicates which HIRD value should be used. Following are permissible values: • 0: Initiate L1 using HIRD only time out (default) • 1: Initiate HIRDDon timeout. If rejected by device, initiate L1 using HIRD • 2: Reserved • 3: Reserved ***Note:*** This register is sticky. **Power Well:** SUS

51.3.21 Port Status and Control USB2 (PORTSC2)—Offset 490h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 490h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Reserved:** Reserved. **Power Well:** SUS
30	0x0 RW/L	**Device Removable (DR):** Reserved. **Power Well:** Core
29:28	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
27	0x0 RW	**Wake on Over-current Enable (WOE):** ***Note:*** This register is sticky. **Power Well:** SUS
26	0x0 RW	**Wake on Disconnect Enable (WDE):** ***Note:*** This register is sticky. **Power Well:** SUS
25	0x0 RW	**Wake on Connect Enable (WCE):** ***Note:*** This register is sticky. **Power Well:** SUS
24	0x0 RO	**Cold Attach Status (CAS):** Reserved. **Power Well:** SUS
23	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
22	0x0 RW/C	**Port Link State Change (PLC):** ***Note:*** This register is sticky. **Power Well:** SUS
21	0x0 RW/C	**Port Reset Change (PRC):** ***Note:*** This register is sticky. **Power Well:** SUS
20	0x0 RW/C	**Over-current Change (OCC):** ***Note:*** This register is sticky. **Power Well:** SUS
19	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** ***Note:*** This register is sticky. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW/C	**Connect Status Change (CSC):** ***Note:*** This register is sticky. **Power Well:** SUS
16	0x0 RW	**Port Link State Write Strobe (LWS):** Reserved. **Power Well:** SUS
15:14	0x0 RW	**Port Indicator Control (PIC):** ***Note:*** This register is sticky. **Power Well:** SUS
13:10	0x0 RW	**Port Speed (PortSpeed):** ***Note:*** This register is sticky. **Power Well:** SUS
9	0x1 RW	**Port Power (PP):** ***Note:*** This register is sticky. **Power Well:** SUS
8:5	0x5 RW	**Port Link State (PLS):** ***Note:*** This register is sticky. **Power Well:** SUS
4	0x0 RW/1S	**Port Reset (PR):** Reserved. **Power Well:** SUS
3	0x0 RW	**Over-current Active (OCA):** ***Note:*** This register is sticky. **Power Well:** SUS
2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW/C	**Port Enabled Disabled (PED):** ***Note:*** This register is sticky. **Power Well:** SUS
0	0x0 RW	**Current Connect Status (CCS):** ***Note:*** This register is sticky. **Power Well:** SUS

51.3.22 Port Power Management Status and Control USB2 (PORTPMSC2)—Offset 494h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 494h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Port Test Control (PTC):** When this field is '0', the port is not operating in a test mode. (Default) A non-zero value indicates that the port is operating in test mode in indicated by the specific value. A non-zero Port Test Control value is only valid to a port that is in the Disabled state. If the port is not in this state, the xHC shall respond with the Port Test Control field set to Port Test Control Error. The encoding of the Test Mode bits for a USB 2.0 port are: Value Test Mode • 0h - Test mode not enabled • 1h - Test J_STATE • 2h - Test K_STATE • 3h - Test SE0_NAK • 4h - Test Packet • 5h - Test FORCE_ENABLE • 6h-14h - Reserved. • 15 - Port Test Control Error
27:17	0x0 RO	Reserved.
16	0x0 RW	**Hardware LPM Enable (HLE):** • 0 - Disable • 1 - Enable. When this bit is a 1, hardware controlled LPM shall be enabled for this port. Refer to Section 4 of the USB 2.0 LPM Specification for more information.
15:8	0x0 RO	Reserved.
7:4	0x0 RW	**Best Effort Service Latency:** System software sets this field to indicate the recipient device how long the xHCI will driver resume if it initiates an exit from L1.
3	0x0 RW	**Remote Wake Enable (RWE):** The host system sets this flag to enable or disable the device for remote wake from L1. • 0 - disable • 1 - enable The value of this flag will temporarily (while in L1) override the current setting of the Remote Wake feature set by the standard Set/ClearFeature() commands defined in Universal Serial Bus Specification, Revision 2.0, Chapter 9.
2:0	0x0 RW	**L1 Status (L1S):** This field is used by software to determine whether an L1-based suspend request was successful.

51.3.23 Port X Hardware LPM Control Register (PORTHLPMC2)—Offset 49Ch

There are 9 PORTHLPMC registers at offsets 48Ch, 49Ch, 4ACh, 4BCh, 4CCh, 4DCh, 4ECh, 4FCh, 50Ch This register is reset only by platform hardware during cold reset or in response to a Host Controller Reset (HCRST). The definition for the fields depend on the protocol supported. For USB3 this register is reserved and shall be treated by software as RsvdP. For USB2 the definition is given below. Fields contain parameters necessary for xHC to automatically generate an LPM Token to the downstream device.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 49Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
13:10	0x0 RW	**Host Initiated Resume Duration-Deep (HIRDD):** System software sets this field to indicate to the recipient device how long the xHC will drive resume if an exit from L1. • The HIRDD value is encoded as follows: • 0h: 50 us (default) • 1h: 125 us • 2h: 200 us • ... • Fh: 1.175ms The value of 0h is interpreted as 50 us. Each incrementing value adds 75 us to the previous value. **Power Well:** SUS
9:2	0x0 RW	**L1 Timeout (L1_TO):** Timeout value for L1 inactivity timer. This field shall be set to 00h by assertion of PR to '1'. Following are permissible values: • 00h: 128 us (default) • 01h: 256 us. • ... • FFh: 65,280us ***Note:*** This register is sticky. **Power Well:** SUS
1:0	0x0 RW	**Host Initiated Resume Duration Mode (HIRDM):** Indicates which HIRD value should be used. Following are permissible values: • 0: Initiate L1 using HIRD only time out (default) • 1: Initiate HIRDDon timeout. If rejected by device, initiate L1 using HIRD • 2: Reserved • 3: Reserved ***Note:*** This register is sticky. **Power Well:** SUS

51.3.24 Port Status and Control USB2 (PORTSC3)—Offset 4A0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 4A0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Reserved:** Reserved. **Power Well:** SUS
30	0x0 RW/L	**Device Removable (DR):** Reserved. **Power Well:** Core
29:28	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
27	0x0 RW	**Wake on Over-current Enable (WOE):** ***Note:*** This register is sticky. **Power Well:** SUS
26	0x0 RW	**Wake on Disconnect Enable (WDE):** ***Note:*** This register is sticky. **Power Well:** SUS
25	0x0 RW	**Wake on Connect Enable (WCE):** ***Note:*** This register is sticky. **Power Well:** SUS
24	0x0 RO	**Cold Attach Status (CAS):** Reserved. **Power Well:** SUS
23	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
22	0x0 RW/C	**Port Link State Change (PLC):** ***Note:*** This register is sticky. **Power Well:** SUS
21	0x0 RW/C	**Port Reset Change (PRC):** ***Note:*** This register is sticky. **Power Well:** SUS
20	0x0 RW/C	**Over-current Change (OCC):** ***Note:*** This register is sticky. **Power Well:** SUS
19	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** ***Note:*** This register is sticky. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW/C	**Connect Status Change (CSC):** ***Note:*** This register is sticky. **Power Well:** SUS
16	0x0 RW	**Port Link State Write Strobe (LWS):** Reserved. **Power Well:** SUS
15:14	0x0 RW	**Port Indicator Control (PIC):** ***Note:*** This register is sticky. **Power Well:** SUS
13:10	0x0 RW	**Port Speed (PortSpeed):** ***Note:*** This register is sticky. **Power Well:** SUS
9	0x1 RW	**Port Power (PP):** ***Note:*** This register is sticky. **Power Well:** SUS
8:5	0x5 RW	**Port Link State (PLS):** ***Note:*** This register is sticky. **Power Well:** SUS
4	0x0 RW/1S	**Port Reset (PR):** Reserved. **Power Well:** SUS
3	0x0 RW	**Over-current Active (OCA):** ***Note:*** This register is sticky. **Power Well:** SUS
2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW/C	**Port Enabled Disabled (PED):** ***Note:*** This register is sticky. **Power Well:** SUS
0	0x0 RW	**Current Connect Status (CCS):** ***Note:*** This register is sticky. **Power Well:** SUS

51.3.25 Port Power Management Status and Control USB2 (PORTPMSC3)—Offset 4A4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4A4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Port Test Control (PTC):** When this field is '0', the port is not operating in a test mode. (Default) A non-zero value indicates that the port is operating in test mode in indicated by the specific value. A non-zero Port Test Control value is only valid to a port that is in the Disabled state. If the port is not in this state, the xHC shall respond with the Port Test Control field set to Port Test Control Error. The encoding of the Test Mode bits for a USB 2.0 port are: Value Test Mode • 0h - Test mode not enabled • 1h - Test J_STATE • 2h - Test K_STATE • 3h - Test SE0_NAK • 4h - Test Packet • 5h - Test FORCE_ENABLE • 6h-14h - Reserved. • 15 - Port Test Control Error
27:17	0x0 RO	Reserved.
16	0x0 RW	**Hardware LPM Enable (HLE):** • 0 - Disable • 1 - Enable. When this bit is a 1, hardware controlled LPM shall be enabled for this port. Refer to Section 4 of the USB 2.0 LPM Specification for more information.
15:8	0x0 RO	Reserved.
7:4	0x0 RW	**Best Effort Service Latency:** System software sets this field to indicate the recipient device how long the xHCI will driver resume if it initiates an exit from L1.
3	0x0 RW	**Remote Wake Enable (RWE):** The host system sets this flag to enable or disable the device for remote wake from L1. • 0 - disable • 1 - enable The value of this flag will temporarily (while in L1) override the current setting of the Remote Wake feature set by the standard Set/ClearFeature() commands defined in Universal Serial Bus Specification, Revision 2.0, Chapter 9.
2:0	0x0 RW	**L1 Status (L1S):** This field is used by software to determine whether an L1-based suspend request was successful.

51.3.26 Port X Hardware LPM Control Register (PORTHLPMC3)—Offset 4ACh

There are 9 PORTHLPMC registers at offsets 48Ch, 49Ch, 4ACh, 4BCh, 4CCh, 4DCh, 4ECh, 4FCh, 50Ch This register is reset only by platform hardware during cold reset or in response to a Host Controller Reset (HCRST). The definition for the fields depend on the protocol supported. For USB3 this register is reserved and shall be treated by software as RsvdP. For USB2 the definition is given below. Fields contain parameters necessary for xHC to automatically generate an LPM Token to the downstream device.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 4ACh

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
13:10	0x0 RW	**Host Initiated Resume Duration-Deep (HIRDD):** System software sets this field to indicate to the recipient device how long the xHC will drive resume if an exit from L1. The HIRDD value is is encoded as follows: • 0h: 50 us (default) • 1h: 125 us • 2h: 200 us • ... • Fh: 1.175ms The value of 0h is interpreted as 50 us. Each incrementing value adds 75 us to the previous value. **Power Well:** SUS
9:2	0x0 RW	**L1 Timeout (L1_TO):** Timeout value for L1 inactivity timer. This field shall be set to 00h by assertion of PR to '1'. Following are permissible values: • 00h: 128 us (default) • 01h: 256 us • ... • FFh: 65,280us ***Note:*** This register is sticky. **Power Well:** SUS
1:0	0x0 RW	**Host Initiated Resume Duration Mode (HIRDM):** Indicates which HIRD value should be used. Following are permissible values: • 0: Initiate L1 using HIRD only time out (default) • 1: Initiate HIRDDon timeout. If rejected by device, initiate L1 using HIRD • 2: Reserved • 3: Reserved ***Note:*** This register is sticky. **Power Well:** SUS

51.3.27 Port Status and Control USB2 (PORTSC4)—Offset 4B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 4B0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Reserved:** Reserved. **Power Well:** SUS
30	0x0 RW/L	**Device Removable (DR):** Reserved. **Power Well:** Core
29:28	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
27	0x0 RW	**Wake on Over-current Enable (WOE):** Note: This register is sticky. **Power Well:** SUS
26	0x0 RW	**Wake on Disconnect Enable (WDE):** Note: This register is sticky. **Power Well:** SUS
25	0x0 RW	**Wake on Connect Enable (WCE):** Note: This register is sticky. **Power Well:** SUS
24	0x0 RO	**Cold Attach Status (CAS):** Reserved. **Power Well:** SUS
23	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
22	0x0 RW/C	**Port Link State Change (PLC):** Note: This register is sticky. **Power Well:** SUS
21	0x0 RW/C	**Port Reset Change (PRC):** Note: This register is sticky. **Power Well:** SUS
20	0x0 RW/C	**Over-current Change (OCC):** Note: This register is sticky. **Power Well:** SUS
19	0x0 RW/C	**Reserved:** Reserved. **Power Well:** SUS
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** Note: This register is sticky. **Power Well:** SUS
17	0x0 RW/C	**Connect Status Change (CSC):** Note: This register is sticky. **Power Well:** SUS
16	0x0 RW	**Port Link State Write Strobe (LWS):** Reserved. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RW	**Port Indicator Control (PIC):** Note: This register is sticky. **Power Well:** SUS
13:10	0x0 RW	**Port Speed (PortSpeed):** Note: This register is sticky. **Power Well:** SUS
9	0x1 RW	**Port Power (PP):** Note: This register is sticky. **Power Well:** SUS
8:5	0x5 RW	**Port Link State (PLS):** Note: This register is sticky. **Power Well:** SUS
4	0x0 RW/1S	**Port Reset (PR):** Reserved. **Power Well:** SUS
3	0x0 RW	**Over-current Active (OCA):** Note: This register is sticky. **Power Well:** SUS
2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW/C	**Port Enabled Disabled (PED):** Note: This register is sticky. **Power Well:** SUS
0	0x0 RW	**Current Connect Status (CCS):** Note: This register is sticky. **Power Well:** SUS

51.3.28 Port Power Management Status and Control USB2 (PORTPMSC4)—Offset 4B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4B4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW	**Port Test Control (PTC):** When this field is '0', the port is not operating in a test mode. (Default) A non-zero value indicates that the port is operating in test mode in indicated by the specific value. A non-zero Port Test Control value is only valid to a port that is in the Disabled state. If the port is not in this state, the xHC shall respond with the Port Test Control field set to Port Test Control Error. The encoding of the Test Mode bits for a USB 2.0 port are: Value Test Mode • 0h - Test mode not enabled • 1h - Test J_STATE • 2h - Test K_STATE • 3h - Test SE0_NAK • 4h - Test Packet • 5h - Test FORCE_ENABLE • 6h-14h - Reserved. • 15 - Port Test Control Error
27:17	0x0 RO	Reserved.
16	0x0 RW	**Hardware LPM Enable (HLE):** • 0 - Disable • 1 - Enable. When this bit is a 1, hardware controlled LPM shall be enabled for this port. Refer to Section 4 of the USB 2.0 LPM Specification for more information.
15:8	0x0 RO	Reserved.
7:4	0x0 RW	**Best Effort Service Latency:** System software sets this field to indicate the recipient device how long the xHCI will driver resume if it initiates an exit from L1.
3	0x0 RW	**Remote Wake Enable (RWE):** The host system sets this flag to enable or disable the device for remote wake from L1. • 0 - disable • 1 - enable The value of this flag will temporarily (while in L1) override the current setting of the Remote Wake feature set by the standard Set/ClearFeature() commands defined in Universal Serial Bus Specification, Revision 2.0, Chapter 9.
2:0	0x0 RW	**L1 Status (L1S):** This field is used by software to determine whether an L1-based suspend request was successful.

51.3.29 Port X Hardware LPM Control Register (PORTHLPMC4)—Offset 4BCh

There are 9 PORTHLPMC registers at offsets 48Ch, 49Ch, 4ACh, 4BCh, 4CCh, 4DCh, 4ECh, 4FCh, 50Ch This register is reset only by platform hardware during cold reset or in response to a Host Controller Reset (HCRST). The definition for the fields depend on the protocol supported. For USB3 this register is reserved and shall be treated by software as RsvdP. For USB2 the definition is given below. Fields contain parameters neccessary for xHC to automatically generate an LPM Token to the downstream device.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 4BCh

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
13:10	0x0 RW	**Host Initiated Resume Duration-Deep (HIRDD):** System software sets this field to indicate to the recipient device how long the xHC will drive resume if an exit from L1. The HIRDD value is is encoded as follows: 0h: 50 us (default) 1h: 125 us 2h: 200 us ... Fh: 1.175ms The value of 0h is interpreted as 50 us. Each incrementing value adds 75 us to the previous value. **Power Well:** SUS
9:2	0x0 RW	**L1 Timeout (L1_TO):** Timeout value for L1 inactivity timer. This field shall be set to 00h by assertion of PR to '1'. Following are permissible values: 00h: 128 us (default) 01h: 256 us. ... FFh: 65,280us Note: This register is sticky. **Power Well:** SUS
1:0	0x0 RW	**Host Initiated Resume Duration Mode (HIRDM):** Indicates which HIRD value should be used. Following are permissible values: 0: Initiate L1 using HIRD only time out (default) 1: Initiate HIRDDon timeout. If rejected by device, initiate L1 using HIRD 2,3: Reserved Note: This register is sticky. **Power Well:** SUS

51.3.30 Port Status and Control USB3 (PORTSC5)—Offset 4C0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 02A0h

BAR and Offset: [MBAR] + 4C0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Warm Port Reset (WPR):** When software sets this bit to be "1", the Warm Reset sequence as defined in the USB3 specification is initiated and the PR flag is set to "1". This flag shall always return "0" when read. This flag only applies to USB3 protocol ports.
30	0x0 RW/L	**Device Removable (DR):** This bit indicates if this port has a removable device. • 0 - Device is removable • 1 - Device is non-removable
29:28	0x0 RO	Reserved.
27	0x0 RW	**Wake on Over-current Enable (WOE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to over-current conditions as system wake-up events.
26	0x0 RW	**Wake on Disconnect Enable (WDE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device disconnects as system wake-up events.
25	0x0 RW	**Wake on Connect Enable (WCE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device connects as system wake-up events.
24	0x0 RO	**Cold Attach Status (CAS):** This bit indicates that far-end terminations were detected in the Disconnected state and the Root Hub Port State Machine was unable to advance to the Enabled state. Software shall clear this bit by writing a 1b to the WPR bit or the xHC shall clear this bit if the CSS bit transitions to 1.
23	0x0 RW/C	**Port Config Error Change (CEC):** This flag indicates that port failed to configure its link partner. • 0= No change. • 1= Port Config Error Detected. Software shall clear this but by writing a "1" to it.
22	0x0 RW/C	**Port Link State Change (PLC):** • 0 - No change • 1 - Link Status Change This flag is set to '1' due to the following Port Link (PLS) transitions:
21	0x0 RW/C	**Port Reset Change (PRC):** This flag is set to '1' due to a '1' to '0' transition of Port Reset (PR). For example, when any reset processing on this port is complete. • 0 - No change • 1 - Reset Complete
20	0x0 RW/C	**Over-current Change (OCC):** The functionality of this bit is not dependent upon the port owner. Software clears this bit by writing a 1 to it. • 0 - No change. (Default) • 1 - There is a change to Overcurrent Active.
19	0x0 RW/C	**Warm Port Reset Change (WRC):** This bit is set when Warm Reset processing on this port completes. • 0 - No change. (Default) • 1 - Warm reset complete

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** • 0 - No change. (Default) • 1 - There is a change to PED bit.
17	0x0 RW/C	**Connect Status Change (CSC):** R?WC. This flag indicates a change has occurred in the port's Current Connect Status (CCS) or Cold Attach Status (CAS) bits. • 0 - No change. (Default) • 1 - There is a change to the CCS or CAS bit. The xHC sets this bit to 1b for all changes to the port device connect status, even if system software has not cleared an existing Connect Status Change. For example, the insertion status changes twice before system software has cleared the change condition root hub hardware will be "setting" an already-set bit (that is, the bit will remain 1b).
16	0x0 RW	**Port Link State Write Strobe (LWS):** • 0 - When 0b, write data in PLS field is ignored. (Default) • 1 - When this bit is set to 1b on a write references to this register, this flag enables writes to the PLS field. Reads to this bit return '0'.
15:14	0x0 RW	**Port Indicator Control (PIC):** Note: This register is sticky.
13:10	0x0 RW	**Port Speed (PortSpeed):** A device attached to this port operates at a speed defined by the following codes: Value Speed • 0001b - full-speed • 0010b - low speed • 0011b - Highspeed • All other values reserved. Refer to the eXtensible Host Controller Interface for Universal Serial Bus Specification for additional details.
9	0x1 RW	**Port Power (PP):** Read-only with a value of 1. This indicates that the port does have power.

Bit Range	Default & Access	Field Name (ID): Description
8:5	0x5 RW	**Port Link State (PLS):** This field is used to power manage the port and reflects its currentlink state. When the port is in the Enabled state, system software may set the link U-state by writing this field. System software may also write this field to force a Disabled to Disconnected state transition of the port. Write Value Description • 0 - The link shall transition to a U0 state from any of the U-states. • 2 - USB 2.0 ports only. The link should transition to the U2 State. • 3 - The link shall transition to a U3 state from any of the U-states. This action selectively suspends the device connected to this port. While the Port LinkState = U3 the hub does not propagate downstream-directed traffic to this port, but the hub will respond to resume signaling from the port. • 5 - USB 3.0 ports only. If the port is in the Disabled state (PLS = Disabled, PP = 1), then the link shall transition to a Rx Detect state and the port shall transition to the Disconnected state, else ignored. • 15 - USB 2.0 ports only. If the port is in the U3 state (PLS = U3), then the link shall remain in the U3 state and the port shall transition to the U3Exit substate, else ignored. • All other values Ignored Read Value Definition • 0 - Link is in the U0 State • 1 - Link is in the U1 State • 2 - Link is in the U2 State • 3 - Link is in the U3 State (Device Suspended) • 4 - Link is in the Disabled State • 5 - Link is in the RxDetect State • 6 - Link is in the Inactive State • 7 - Link is in the Polling State • 8 - Link is in the Recovery State • 9 - Link is in the Hot Reset State • 10 - Link is in the Compliance Mode State • 11 - Link is in the Test Mode State • 12-14 - Reserved • 15 Link is in the Resume State
4	0x0 RW/1S	**Port Reset (PR):** When software writes a 1 to this bit (from a 0), the bus reset sequence as • 1 - port in reset • 0 - port not in reset
3	0x0 RW	**Over-current Active (OCA):** • 0 - This port does not have an overcurrent condition. (Default) • 1 - This port currently has an overcurrent condition. This bit will automatically transition from 1 to 0 when the over current condition is removed. The PCH automatically disables the port when the overcurrent active bit is 1.
2	0x0 RO	Reserved.
1	0x0 RW/C	**Port Enabled Disabled (PED):** Ports can only be enabled by the host controller as a part of the reset and enable. Software cannot enable a port by writing a 1 to this bit. Ports can be disabled by either a fault condition (disconnect even or other fault condition) or by host software. The bit status does not change until the port state actually changes. There may be a delay in disabling or enabling a port due to other host controller and bus events. • 0 - disable • 1 - enable (default)
0	0x0 RW	**Current Connect Status (CCS):** This value reflects the current state of the port and may not correspond directly to the event that caused the Connect Status Change bit (Bit 1) to be set. • 0 - no device is present • 1 - device is present on port.

51.3.31 Port Power Management Status and Control USB3 (PORTPMSC5)—Offset 4C4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4C4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
16	0x0 RW	**Force Link PM Accept (FLA):** Reserved. **Power Well:** SUS
15:8	0x0 RW/S	**U2 Timeout (U2T):** Reserved. **Power Well:** SUS
7:0	0x0 RW/S	**U1 Timeout (U1T):** Reserved. **Power Well:** SUS

51.3.32 USB3 Port Link Info (PORTLI5)—Offset 4C8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4C8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RO	**Link Error Count (LEC):** Reserved. **Power Well:** Core

51.3.33 Port Status and Control USB3 (PORTSC6)—Offset 4D0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 4D0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Warm Port Reset (WPR):** When software sets this bit to be "1", the Warm Reset sequence as defined in the USB3 specification is initiated and the PR flag is set to "1". This flag shall always return "0" when read. This flag only applies to USB3 protocol ports.
30	0x0 RW/L	**Device Removable (DR):** This bit indicates if this port has a removable device. • 0 - Device is removable • 1 - Device is non-removable
29:28	0x0 RO	Reserved.
27	0x0 RW	**Wake on Over-current Enable (WOE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to over-current conditions as system wake-up events.
26	0x0 RW	**Wake on Disconnect Enable (WDE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device disconnects as system wake-up events.
25	0x0 RW	**Wake on Connect Enable (WCE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device connects as system wake-up events.
24	0x0 RO	**Cold Attach Status (CAS):** This bit indicates that far-end terminations were detected in the Disconnected state and the Root Hub Port State Machine was unable to advance to the Enabled state. Software shall clear this bit by writing a 1b to the WPR bit or the xHC shall clear this bit if the CSS bit transitions to 1.
23	0x0 RW/C	**Port Config Error Change (CEC):** This flag indicates that port failed to configure its link partner. • 0= No change. • 1= Port Config Error Detected. Software shall clear this but by writing a "1" to it.
22	0x0 RW/C	**Port Link State Change (PLC):** • 0 - No change • 1 - Link Status Change This flag is set to '1' due to the following Port Link (PLS) transitions:
21	0x0 RW/C	**Port Reset Change (PRC):** This flag is set to '1' due to a '1' to '0' transition of Port Reset (PR). For example, when any reset processing on this port is complete. • 0 - No change • 1 - Reset Complete
20	0x0 RW/C	**Over-current Change (OCC):** The functionality of this bit is not dependent upon the port owner. Software clears this bit by writing a 1 to it. • 0 - No change. (Default) • 1 - There is a change to Overcurrent Active.
19	0x0 RW/C	**Warm Port Reset Change (WRC):** This bit is set when Warm Reset processing on this port completes. • 0 - No change. (Default) • 1 - Warm reset complete

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** • 0 - No change. (Default) • 1 - There is a change to PED bit.
17	0x0 RW/C	**Connect Status Change (CSC):** R?WC. This flag indicates a change has occurred in the port's Current Connect Status (CCS) or Cold Attach Status (CAS) bits. • 0 - No change. (Default) • 1 - There is a change to the CCS or CAS bit. The xHC sets this bit to 1b for all changes to the port device connect status, even if system software has not cleared an existing Connect Status Change. For example, the insertion status changes twice before system software has cleared the change condition root hub hardware will be "setting" an already-set bit (that is, the bit will remain 1b).
16	0x0 RW	**Port Link State Write Strobe (LWS):** • 0 - When 0b, write data in PLS field is ignored. (Default) • 1 - When this bit is set to 1b on a write references to this register, this flag enables writes to the PLS field. Reads to this bit return '0'.
15:14	0x0 RW	**Port Indicator Control (PIC):** Note: This register is sticky.
13:10	0x0 RW	**Port Speed (PortSpeed):** A device attached to this port operates at a speed defined by the following codes: Value Speed • 0001b - full-speed • 0010b - low speed • 0011b - Highspeed • All other values reserved. Refer to the eXtensible Host Controller Interface for Universal Serial Bus Specification for additional details.
9	0x1 RW	**Port Power (PP):** Read-only with a value of 1. This indicates that the port does have power.

Bit Range	Default & Access	Field Name (ID): Description
8:5	0x5 RW	**Port Link State (PLS):** This field is used to power manage the port and reflects its currentlink state. When the port is in the Enabled state, system software may set the link U-state by writing this field. System software may also write this field to force a Disabled to Disconnected state transition of the port. Write Value Description • 0 - The link shall transition to a U0 state from any of the U-states. • 2 - USB 2.0 ports only. The link should transition to the U2 State. • 3 - The link shall transition to a U3 state from any of the U-states. This action selectively suspends the device connected to this port. While the Port LinkState = U3 the hub does not propagate downstream-directed traffic to this port, but the hub will respond to resume signaling from the port. • 5 - USB 3.0 ports only. If the port is in the Disabled state (PLS = Disabled, PP = 1), then the link shall transition to a Rx Detect state and the port shall transition to the Disconnected state, else ignored. • 15 - USB 2.0 ports only. If the port is in the U3 state (PLS = U3), then the link shall remain in the U3 state and the port shall transition to the U3Exit substate, else ignored. • All other values Ignored Read Value Definition • 0 - Link is in the U0 State • 1 - Link is in the U1 State • 2 - Link is in the U2 State • 3 - Link is in the U3 State (Device Suspended) • 4 - Link is in the Disabled State • 5 - Link is in the RxDetect State • 6 - Link is in the Inactive State • 7 - Link is in the Polling State • 8 - Link is in the Recovery State • 9 - Link is in the Hot Reset State • 10 - Link is in the Compliance Mode State • 11 - Link is in the Test Mode State • 12-14 - Reserved • 15 Link is in the Resume State
4	0x0 RW/1S	**Port Reset (PR):** When software writes a 1 to this bit (from a 0), the bus reset sequence as • 1 - port in reset • 0 - port not in reset
3	0x0 RW	**Over-current Active (OCA):** • 0 - This port does not have an overcurrent condition. (Default) • 1 - This port currently has an overcurrent condition. This bit will automatically transition from 1 to 0 when the over current condition is removed. The PCH automatically disables the port when the overcurrent active bit is 1.
2	0x0 RO	Reserved.
1	0x0 RW/C	**Port Enabled Disabled (PED):** Ports can only be enabled by the host controller as a part of the reset and enable. Software cannot enable a port by writing a 1 to this bit. Ports can be disabled by either a fault condition (disconnect even or other fault condition) or by host software. The bit status does not change until the port state actually changes. There may be a delay in disabling or enabling a port due to other host controller and bus events. • 0 - disable • 1 - enable (default)
0	0x0 RW	**Current Connect Status (CCS):** This value reflects the current state of the port and may not correspond directly to the event that caused the Connect Status Change bit (Bit 1) to be set. • 0 - no device is present • 1 - device is present on port.

51.3.34 Port Power Management Status and Control USB3 (PORTPMSC6)—Offset 4D4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4D4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
16	0x0 RW	**Force Link PM Accept (FLA):** Reserved. **Power Well:** SUS
15:8	0x0 RW/S	**U2 Timeout (U2T):** Reserved. **Power Well:** SUS
7:0	0x0 RW/S	**U1 Timeout (U1T):** Reserved. **Power Well:** SUS

51.3.35 USB3 Port Link Info (PORTLI6)—Offset 4D8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4D8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RO	**Link Error Count (LEC):** Reserved. **Power Well:** Core

51.3.36 Port Status and Control USB3 (PORTSC7)—Offset 4E0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 4E0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Warm Port Reset (WPR):** When software sets this bit to be "1", the Warm Reset sequence as defined in the USB3 specification is initiated and the PR flag is set to "1". This flag shall always return "0" when read. This flag only applies to USB3 protocol ports.
30	0x0 RW/L	**Device Removable (DR):** This bit indicates if this port has a removable device. • 0 - Device is removable • 1 - Device is non-removable
29:28	0x0 RO	Reserved.
27	0x0 RW	**Wake on Over-current Enable (WOE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to over-current conditions as system wake-up events.
26	0x0 RW	**Wake on Disconnect Enable (WDE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device disconnects as system wake-up events.
25	0x0 RW	**Wake on Connect Enable (WCE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device connects as system wake-up events.
24	0x0 RO	**Cold Attach Status (CAS):** This bit indicates that far-end terminations were detected in the Disconnected state and the Root Hub Port State Machine was unable to advance to the Enabled state. Software shall clear this bit by writing a 1b to the WPR bit or the xHC shall clear this bit if the CSS bit transitions to 1.
23	0x0 RW/C	**Port Config Error Change (CEC):** This flag indicates that port failed to configure its link partner. • 0= No change. • 1= Port Config Error Detected. Software shall clear this but by writing a "1" to it.
22	0x0 RW/C	**Port Link State Change (PLC):** • 0 - No change • 1 - Link Status Change This flag is set to '1' due to the following Port Link (PLS) transitions:
21	0x0 RW/C	**Port Reset Change (PRC):** This flag is set to '1' due to a '1' to '0' transition of Port Reset (PR). For example, when any reset processing on this port is complete. • 0 - No change • 1 - Reset Complete
20	0x0 RW/C	**Over-current Change (OCC):** The functionality of this bit is not dependent upon the port owner. Software clears this bit by writing a 1 to it. • 0 - No change. (Default) • 1 - There is a change to Overcurrent Active.
19	0x0 RW/C	**Warm Port Reset Change (WRC):** This bit is set when Warm Reset processing on this port completes. • 0 - No change. (Default) • 1 - Warm reset complete

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** • 0 - No change. (Default) • 1 - There is a change to PED bit.
17	0x0 RW/C	**Connect Status Change (CSC):** R?WC. This flag indicates a change has occurred in the port's Current Connect Status (CCS) or Cold Attach Status (CAS) bits. • 0 - No change. (Default) • 1 - There is a change to the CCS or CAS bit. The xHC sets this bit to 1b for all changes to the port device connect status, even if system software has not cleared an existing Connect Status Change. For example, the insertion status changes twice before system software has cleared the change condition root hub hardware will be "setting" an already-set bit (that is, the bit will remain 1b).
16	0x0 RW	**Port Link State Write Strobe (LWS):** • 0 - When 0b, write data in PLS field is ignored. (Default) • 1 - When this bit is set to 1b on a write references to this register, this flag enables writes to the PLS field. Reads to this bit return '0'.
15:14	0x0 RW	**Port Indicator Control (PIC):** Note: This register is sticky.
13:10	0x0 RW	**Port Speed (PortSpeed):** A device attached to this port operates at a speed defined by the following codes: Value Speed • 0001b - full-speed • 0010b - low speed • 0011b - Highspeed • All other values reserved. Refer to the eXtensible Host Controller Interface for Universal Serial Bus Specification for additional details.
9	0x1 RW	**Port Power (PP):** Read-only with a value of 1. This indicates that the port does have power.

Bit Range	Default & Access	Field Name (ID): Description
8:5	0x5 RW	**Port Link State (PLS):** This field is used to power manage the port and reflects its currentlink state. When the port is in the Enabled state, system software may set the link U-state by writing this field. System software may also write this field to force a Disabled to Disconnected state transition of the port. Write Value Description • 0 - The link shall transition to a U0 state from any of the U-states. • 2 - USB 2.0 ports only. The link should transition to the U2 State. • 3 - The link shall transition to a U3 state from any of the U-states. This action selectively suspends the device connected to this port. While the Port LinkState = U3 the hub does not propagate downstream-directed traffic to this port, but the hub will respond to resume signaling from the port. • 5 - USB 3.0 ports only. If the port is in the Disabled state (PLS = Disabled, PP = 1), then the link shall transition to a Rx Detect state and the port shall transition to the Disconnected state, else ignored. • 15 - USB 2.0 ports only. If the port is in the U3 state (PLS = U3), then the link shall remain in the U3 state and the port shall transition to the U3Exit substate, else ignored. • All other values Ignored Read Value Definition • 0 - Link is in the U0 State • 1 - Link is in the U1 State • 2 - Link is in the U2 State • 3 - Link is in the U3 State (Device Suspended) • 4 - Link is in the Disabled State • 5 - Link is in the RxDetect State • 6 - Link is in the Inactive State • 7 - Link is in the Polling State • 8 - Link is in the Recovery State • 9 - Link is in the Hot Reset State • 10 - Link is in the Compliance Mode State • 11 - Link is in the Test Mode State • 12-14 - Reserved • 15 Link is in the Resume State
4	0x0 RW/1S	**Port Reset (PR):** When software writes a 1 to this bit (from a 0), the bus reset sequence as • 1 - port in reset • 0 - port not in reset
3	0x0 RW	**Over-current Active (OCA):** • 0 - This port does not have an overcurrent condition. (Default) • 1 - This port currently has an overcurrent condition. This bit will automatically transition from 1 to 0 when the over current condition is removed. The PCH automatically disables the port when the overcurrent active bit is 1.
2	0x0 RO	Reserved.
1	0x0 RW/C	**Port Enabled Disabled (PED):** Ports can only be enabled by the host controller as a part of the reset and enable. Software cannot enable a port by writing a 1 to this bit. Ports can be disabled by either a fault condition (disconnect even or other fault condition) or by host software. The bit status does not change until the port state actually changes. There may be a delay in disabling or enabling a port due to other host controller and bus events. • 0 - disable • 1 - enable (default)
0	0x0 RW	**Current Connect Status (CCS):** This value reflects the current state of the port and may not correspond directly to the event that caused the Connect Status Change bit (Bit 1) to be set. • 0 - no device is present • 1 - device is present on port.

51.3.37 Port Power Management Status and Control USB3 (PORTPMSC7)—Offset 4E4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4E4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
16	0x0 RW	**Force Link PM Accept (FLA):** Reserved. **Power Well:** SUS
15:8	0x0 RW/S	**U2 Timeout (U2T):** Reserved. **Power Well:** SUS
7:0	0x0 RW/S	**U1 Timeout (U1T):** Reserved. **Power Well:** SUS

51.3.38 USB3 Port Link Info (PORTLI7)—Offset 4E8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4E8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RO	**Link Error Count (LEC):** Reserved. **Power Well:** Core

51.3.39 Port Status and Control USB3 (PORTSC8)—Offset 4F0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000002A0h

BAR and Offset: [MBAR] + 4F0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1S	**Warm Port Reset (WPR):** When software sets this bit to be "1", the Warm Reset sequence as defined in the USB3 specification is initiated and the PR flag is set to "1". This flag shall always return "0" when read. This flag only applies to USB3 protocol ports.
30	0x0 RW/L	**Device Removable (DR):** This bit indicates if this port has a removable device. • 0 - Device is removable • 1 - Device is non-removable
29:28	0x0 RO	Reserved.
27	0x0 RW	**Wake on Over-current Enable (WOE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to over-current conditions as system wake-up events.
26	0x0 RW	**Wake on Disconnect Enable (WDE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device disconnects as system wake-up events.
25	0x0 RW	**Wake on Connect Enable (WCE):** • 0 - Disable. (Default) • 1 - Enable. Writing this but to a 1b enables the port to be sensitive to device connects as system wake-up events.
24	0x0 RO	**Cold Attach Status (CAS):** This bit indicates that far-end terminations were detected in the Disconnected state and the Root Hub Port State Machine was unable to advance to the Enabled state. Software shall clear this bit by writing a 1b to the WPR bit or the xHC shall clear this bit if the CSS bit transitions to 1.
23	0x0 RW/C	**Port Config Error Change (CEC):** This flag indicates that port failed to configure its link partner. • 0= No change. • 1= Port Config Error Detected. Software shall clear this but by writing a "1" to it.
22	0x0 RW/C	**Port Link State Change (PLC):** • 0 - No change • 1 - Link Status Change This flag is set to '1' due to the following Port Link (PLS) transitions:
21	0x0 RW/C	**Port Reset Change (PRC):** This flag is set to '1' due to a '1' to '0' transition of Port Reset (PR). For example, when any reset processing on this port is complete. • 0 - No change • 1 - Reset Complete
20	0x0 RW/C	**Over-current Change (OCC):** The functionality of this bit is not dependent upon the port owner. Software clears this bit by writing a 1 to it. • 0 - No change. (Default) • 1 - There is a change to Overcurrent Active.
19	0x0 RW/C	**Warm Port Reset Change (WRC):** This bit is set when Warm Reset processing on this port completes. • 0 - No change. (Default) • 1 - Warm reset complete

Bit Range	Default & Access	Field Name (ID): Description
18	0x0 RW/C	**Port Enabled Disabled Change (PEC):** • 0 - No change. (Default) • 1 - There is a change to PED bit.
17	0x0 RW/C	**Connect Status Change (CSC):** R?WC. This flag indicates a change has occurred in the port's Current Connect Status (CCS) or Cold Attach Status (CAS) bits. • 0 - No change. (Default) • 1 - There is a change to the CCS or CAS bit. The xHC sets this bit to 1b for all changes to the port device connect status, even if system software has not cleared an existing Connect Status Change. For example, the insertion status changes twice before system software has cleared the change condition root hub hardware will be "setting" an already-set bit (that is, the bit will remain 1b).
16	0x0 RW	**Port Link State Write Strobe (LWS):** • 0 - When 0b, write data in PLS field is ignored. (Default) • 1 - When this bit is set to 1b on a write references to this register, this flag enables writes to the PLS field. Reads to this bit return '0'.
15:14	0x0 RW	**Port Indicator Control (PIC):** Note: This register is sticky.
13:10	0x0 RW	**Port Speed (PortSpeed):** A device attached to this port operates at a speed defined by the following codes: Value Speed • 0001b - full-speed • 0010b - low speed • 0011b - Highspeed • All other values reserved. Refer to the eXtensible Host Controller Interface for Universal Serial Bus Specification for additional details.
9	0x1 RW	**Port Power (PP):** Read-only with a value of 1. This indicates that the port does have power.

Bit Range	Default & Access	Field Name (ID): Description
8:5	0x5 RW	**Port Link State (PLS):** This field is used to power manage the port and reflects its currentlink state. When the port is in the Enabled state, system software may set the link U-state by writing this field. System software may also write this field to force a Disabled to Disconnected state transition of the port. Write Value Description • 0 - The link shall transition to a U0 state from any of the U-states. • 2 - USB 2.0 ports only. The link should transition to the U2 State. • 3 - The link shall transition to a U3 state from any of the U-states. This action selectively suspends the device connected to this port. While the Port LinkState = U3 the hub does not propagate downstream-directed traffic to this port, but the hub will respond to resume signaling from the port. • 5 - USB 3.0 ports only. If the port is in the Disabled state (PLS = Disabled, PP = 1), then the link shall transition to a Rx Detect state and the port shall transition to the Disconnected state, else ignored. • 15 - USB 2.0 ports only. If the port is in the U3 state (PLS = U3), then the link shall remain in the U3 state and the port shall transition to the U3Exit substate, else ignored. • All other values Ignored Read Value Definition • 0 - Link is in the U0 State • 1 - Link is in the U1 State • 2 - Link is in the U2 State • 3 - Link is in the U3 State (Device Suspended) • 4 - Link is in the Disabled State • 5 - Link is in the RxDetect State • 6 - Link is in the Inactive State • 7 - Link is in the Polling State • 8 - Link is in the Recovery State • 9 - Link is in the Hot Reset State • 10 - Link is in the Compliance Mode State • 11 - Link is in the Test Mode State • 12-14 - Reserved • 15 Link is in the Resume State
4	0x0 RW/1S	**Port Reset (PR):** When software writes a 1 to this bit (from a 0), the bus reset sequence as • 1 - port in reset • 0 - port not in reset
3	0x0 RW	**Over-current Active (OCA):** • 0 - This port does not have an overcurrent condition. (Default) • 1 - This port currently has an overcurrent condition. This bit will automatically transition from 1 to 0 when the over current condition is removed. The PCH automatically disables the port when the overcurrent active bit is 1.
2	0x0 RO	Reserved.
1	0x0 RW/C	**Port Enabled Disabled (PED):** Ports can only be enabled by the host controller as a part of the reset and enable. Software cannot enable a port by writing a 1 to this bit. Ports can be disabled by either a fault condition (disconnect even or other fault condition) or by host software. The bit status does not change until the port state actually changes. There may be a delay in disabling or enabling a port due to other host controller and bus events. • 0 - disable • 1 - enable (default)
0	0x0 RW	**Current Connect Status (CCS):** This value reflects the current state of the port and may not correspond directly to the event that caused the Connect Status Change bit (Bit 1) to be set. • 0 - no device is present • 1 - device is present on port.

51.3.40 Port Power Management Status and Control USB3 (PORTPMSC8)—Offset 4F4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4F4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
16	0x0 RW	**Force Link PM Accept (FLA):** Reserved. **Power Well:** SUS
15:8	0x0 RW/S	**U2 Timeout (U2T):** Reserved. **Power Well:** SUS
7:0	0x0 RW/S	**U1 Timeout (U1T):** Reserved. **Power Well:** SUS

51.3.41 USB3 Port Link Info (PORTLI8)—Offset 4F8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 4F8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RO	**Link Error Count (LEC):** Reserved. **Power Well:** Core

51.3.42 Microframe Index (RTMFINDEX)—Offset 2000h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 2000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
13:0	0x0 RO	**Microframe Index (IMAN0):** Reserved. **Power Well:** Core

51.3.43 Interrupter 1 Management (IMAN0)—Offset 2020h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2020h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.44 Interrupter 1 Moderation (IMOD0)—Offset 2024h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2024h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.45 Event Ring Segment Table Size 1 (ERSTSZ0)—Offset 2028h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2028h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.46 Event Ring Segment Table Base Address Low 1 (ERSTBA_LO0)—Offset 2030h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2030h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.47 Event Ring Segment Table Base Address High 1 (ERSTBA_HI0)—Offset 2034h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2034h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.48 Event Ring Dequeue Pointer Low 1 (ERDP_LO0)—Offset 2038h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 2038h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.49 Event Ring Dequeue Pointer High 1 (ERDP_HI0)—Offset 203Ch

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 203Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.50 Interrupter 2 Management (IMAN1)—Offset 2040h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2040h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.51 Interrupter 2 Moderation (IMOD1)—Offset 2044h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2044h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.52 Event Ring Segment Table Size 2 (ERSTSZ1)—Offset 2048h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2048h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.53 Event Ring Segment Table Base Address Low 2 (ERSTBA_LO1)—Offset 2050h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2050h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.54 Event Ring Segment Table Base Address High 2 (ERSTBA_HI1)—Offset 2054h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2054h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.55 Event Ring Dequeue Pointer Low 2 (ERDP_LO1)—Offset 2058h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2058h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.56 Event Ring Dequeue Pointer High 2 (ERDP_HI1)—Offset 205Ch

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 205Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.57 Interrupter 3 Management (IMAN2)—Offset 2060h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2060h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.58 Interrupter 3 Moderation (IMOD2)—Offset 2064h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2064h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.59 Event Ring Segment Table Size 3 (ERSTSZ2)—Offset 2068h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2068h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.60 Event Ring Segment Table Base Address Low 3 (ERSTBA_LO2)—Offset 2070h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2070h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.61 Event Ring Segment Table Base Address High 3 (ERSTBA_HI2)—Offset 2074h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2074h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.62 Event Ring Dequeue Pointer Low 3 (ERDP_LO2)—Offset 2078h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2078h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.63 Event Ring Dequeue Pointer High 3 (ERDP_HI2)—Offset 207Ch

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 207Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.64 Interrupter 4 Management (IMAN3)—Offset 2080h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2080h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.65 Interrupter 4 Moderation (IMOD3)—Offset 2084h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2084h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.66 Event Ring Segment Table Size 4 (ERSTSZ3)—Offset 2088h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2088h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.67 Event Ring Segment Table Base Address Low 4 (ERSTBA_LO3)—Offset 2090h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2090h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.68 Event Ring Segment Table Base Address High 4 (ERSTBA_HI3)—Offset 2094h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 2094h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.69 Event Ring Dequeue Pointer Low 4 (ERDP_LO3)—Offset 2098h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 2098h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.70 Event Ring Dequeue Pointer High 4 (ERDP_HI3)—Offset 209Ch

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 209Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.71 Interrupter 5 Management (IMAN4)—Offset 20A0h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20A0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.72 Interrupter 5 Moderation (IMOD4)—Offset 20A4h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20A4h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.73 Event Ring Segment Table Size 5 (ERSTSZ4)—Offset 20A8h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20A8h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.74 Event Ring Segment Table Base Address Low 5 (ERSTBA_LO4)—Offset 20B0h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20B0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.75 Event Ring Segment Table Base Address High 5 (ERSTBA_HI4)—Offset 20B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20B4h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.76 Event Ring Dequeue Pointer Low 5 (ERDP_LO4)—Offset 20B8h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20B8h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.77 Event Ring Dequeue Pointer High 5 (ERDP_HI4)—Offset 20BCh

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 20BCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.78 Interrupter 6 Management (IMAN5)—Offset 20C0h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 20C0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.79 Interrupter 6 Moderation (IMOD5)—Offset 20C4h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000FA0h

BAR and Offset: [MBAR] + 20C4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.80 Event Ring Segment Table Size 6 (ERSTSZ5)—Offset 20C8h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20C8h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.81 Event Ring Segment Table Base Address Low 6 (ERSTBA_LO5)—Offset 20D0h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20D0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.82 Event Ring Segment Table Base Address High 6 (ERSTBA_HI5)—Offset 20D4h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20D4h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.83 Event Ring Dequeue Pointer Low 6 (ERDP_LO5)—Offset 20D8h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20D8h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.84 Event Ring Dequeue Pointer High 6 (ERDP_HI5)—Offset 20DCh

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20DCh

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.85 Interrupter 7 Management (IMAN6)—Offset 20E0h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20E0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.86 Interrupter 7 Moderation (IMOD6)—Offset 20E4h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20E4h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.87 Event Ring Segment Table Size 7 (ERSTSZ6)—Offset 20E8h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20E8h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.88 Event Ring Segment Table Base Address Low 7 (ERSTBA_LO6)—Offset 20F0h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 20F0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.89 Event Ring Segment Table Base Address High 7 (ERSTBA_HI6)—Offset 20F4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 20F4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.90 Event Ring Dequeue Pointer Low 7 (ERDP_LO6)—Offset 20F8h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 20F8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.91 Event Ring Dequeue Pointer High 7 (ERDP_HI6)—Offset 20FCh

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 20FCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.92 Interrupter 8 Management (IMAN7)—Offset 2100h

There are 8 IMAN registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2100h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
1	0x0 RW	**Interrupt Enable (IE):** Reserved. **Power Well:** Core
0	0x0 RW/C	**Interrupt Pending (IP):** Reserved. **Power Well:** Core

51.3.93 Interrupter 8 Moderation (IMOD7)—Offset 2104h

There are 8 IMOD registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2104h

Default: 00000FA0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Interrupt Moderation Counter (IMODC):** Reserved. **Power Well:** Core
15:0	0xfa0 RW	**Interrupt Moderation Interval (IMODI):** Reserved. **Power Well:** Core

51.3.94 Event Ring Segment Table Size 8 (ERSTSZ7)—Offset 2108h

There are 8 ERSTSZ register. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2108h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** Reserved. **Power Well:** Core

51.3.95 Event Ring Segment Table Base Address Low 8 (ERSTBA_LO7)—Offset 2110h

There are 8 ERSTBA_LO registers x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2110h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBA):** Reserved. **Power Well:** Core
5:0	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core

51.3.96 Event Ring Segment Table Base Address High 8 (ERSTBA_HI7)—Offset 2114h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2114h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Segment Table Base Address (ERSTBA):** Reserved. **Power Well:** Core

51.3.97 Event Ring Dequeue Pointer Low 8 (ERDP_LO7)—Offset 2118h

There are 8 ERDP_LO registers. x = 1, 2, ...,8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 2118h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core
3	0x0 RW/C	**Event Handler Busy (EHB):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** Reserved. **Power Well:** Core

51.3.98 Event Ring Dequeue Pointer High 8 (ERDP_HI7)—Offset 211Ch

There are 8 ERDP_HI registers. x = 1, 2, ..., 8

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 211Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Event Ring Dequeue Pointer (ERDP):** Reserved. **Power Well:** Core

51.3.99 Door Bell 1 (DB0)—Offset 3000h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3000h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.100 Door Bell 2 (DB1)—Offset 3004h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3004h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.101 Door Bell 3 (DB2)—Offset 3008h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3008h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.102 Door Bell 4 (DB3)—Offset 300Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 300Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.103 Door Bell 5 (DB4)—Offset 3010h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3010h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.104 Door Bell 6 (DB5)—Offset 3014h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3014h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.105 Door Bell 7 (DB6)—Offset 3018h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3018h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.106 Door Bell 8 (DB7)—Offset 301Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 301Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.107 Door Bell 9 (DB8)—Offset 3020h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3020h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.108 Door Bell 10 (DB9)—Offset 3024h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3024h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.109 Door Bell 11 (DB10)—Offset 3028h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3028h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.110 Door Bell 12 (DB11)—Offset 302Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 302Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.111 Door Bell 13 (DB12)—Offset 3030h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3030h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.112 Door Bell 14 (DB13)—Offset 3034h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3034h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.113 Door Bell 15 (DB14)—Offset 3038h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3038h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.114 Door Bell 16 (DB15)—Offset 303Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 303Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.115 Door Bell 17 (DB16)—Offset 3040h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3040h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.116 Door Bell 18 (DB17)—Offset 3044h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3044h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.117 Door Bell 19 (DB18)—Offset 3048h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3048h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.118 Door Bell 20 (DB19)—Offset 304Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 304Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.119 Door Bell 21 (DB20)—Offset 3050h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3050h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.120 Door Bell 22 (DB21)—Offset 3054h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3054h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.121 Door Bell 23 (DB22)—Offset 3058h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3058h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.122 Door Bell 24 (DB23)—Offset 305Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 305Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.123 Door Bell 25 (DB24)—Offset 3060h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3060h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.124 Door Bell 26 (DB25)—Offset 3064h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3064h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.125 Door Bell 27 (DB26)—Offset 3068h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3068h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.126 Door Bell 28 (DB27)—Offset 306Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 306Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.127 Door Bell 29 (DB28)—Offset 3070h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3070h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.128 Door Bell 30 (DB29)—Offset 3074h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3074h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.129 Door Bell 31 (DB30)—Offset 3078h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3078h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.130 Door Bell 32 (DB31)—Offset 307Ch

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 307Ch

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.131 Door Bell 32 (DB32)—Offset 3080h

Door Bell registers are an array of 64 registers, with 0 to 32 being used by the XHC and the rest being reserved.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 3080h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**DB Stream ID (DSI):** Reserved. **Power Well:** Core
15:8	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
7:0	0x0 RW	**DB Target (DT):** This field defines the target of the doorbell reference. Doorbell register 0: Dedicated to Command Ring and decodes this field differently than other doorbell registers. **Power Well:** Core

51.3.132 XECP_SUPP_USB2_1—Offset 8004h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 20425355h

BAR and Offset: [MBAR] + 8004h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x20425355 RO	**XECP_SUPP_USB2_1:** Namestring USB **Power Well:** Core

51.3.133 XECP_SUPP_USB2_2—Offset 8008h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 30190401h

BAR and Offset: [MBAR] + 8008h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x3 RO	**Protocol Speed ID Count (PROT_SPD_ID_CNT):** 3 USB 2.0 Speed (High, Full, Low) **Power Well:** Core
27:21	0x0 RO	**Rsvd0:** Reserved. **Power Well:** Core
20	0x1 RW/L	**BESL LPM Capability (BLC):** Bit is set to 1 to indicate that the the ports described by this xHCI Supported Protocol Capability will apply BESL timing to BESL and BESLD fields of the PORTPMSC and PORTHLPMCC registers. **Power Well:** Core
19	0x1 RW/L	**Protocol Defined - Hardware LMP Capability (HLC):** Reserved. **Power Well:** Core
18	0x0 RO	**Protocol Defined - Integrated Hub Implementation (IHI):** Reserved. **Power Well:** Core
17	0x0 RO	**Protocol Defined - High SPeed Only (HSO):** Reserved. **Power Well:** Core
16	0x1 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:8	0x4 RO	**Compatible Port Count (CPC):** Reserved. **Power Well:** Core
7:0	0x1 RO	**Compatible Port Offset (CPO):** Reserved. **Power Well:** Core

51.3.134 XECP_SUPP_USB3_1—Offset 8024h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 20425355h

BAR and Offset: [MBAR] + 8024h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x20425355 RO	**XECP_SUPP_USB2_1:** Namestring USB **Power Well:** Core

51.3.135 XECP_SUPP_USB3_2—Offset 8028h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 10000405h

BAR and Offset: [MBAR] + 8028h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x1 RO	**Protocol Speed ID Count (PROT_SPD_ID_CNT):** 1 USB 3.0 Speed (Supper Speed) **Power Well:** Core
27:16	0x0 RO	**Rsvd0:** Reserved. **Power Well:** Core
15:8	0x4 RO	**Compatible Port Count (CPC):** Reserved. **Power Well:** Core
7:0	0x5 RO	**Compatible Port Offset (CPO):** Reserved. **Power Well:** Core

51.3.136 Host Controller Capability (HOST_CTRL_CAP_REG)—Offset 8070h

This is a register that describe the host controller the extended cap location. It includes the , XECP_HOST_NEXT_CAP_OFFSET and VEND_DEF_HOST_CAP_ID_192. This register is not subject to HW save and restore.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 004DFFC0h

BAR and Offset: [MBAR] + 8070h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
23:16	0x4d RW/L	**Valid Length (VALID_LENGTH):** Indicates the number of valid DWords in the capability, that need to be saved and restored This value needs to be updated as new chicken bit registers are added. 47h -) 818Bh is the last valid byte **Power Well:** Core
15:8	0xff RW/L	**Next Capability Pointer (XECP_HOST_NEXT_CAP_OFFSET):** Reserved. **Power Well:** Core
7:0	0xc0 RW/L	**Supported Protocol ID (VEND_DEF_HOST_CAP_ID):** Reserved. **Power Well:** Core

51.3.137 Override EP Flow Control (HOST_CLR_MASK_REG)—Offset 8078h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8078h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
9:5	0x0 WO	**Slot Number Default Config (SNDC):** 5bits of slot number as a default configuration. It can scale to max of 128 slots **Power Well:** Core
4:1	0x0 WO	**EP Number (EP_NUM):** 4bits of EP number **Power Well:** Core
0	0x0 WO	**Clear Internal Scheduler's Mask (CISM):** This is a register that is used to clear the internal scheduler's mask that is used to stop scheduling a particular EP. Bit0 indicates the direction of the EP **Power Well:** Core

51.3.138 Clear Active IN EP ID Control (HOST_CLR_IN_EP_VALID_REG)—Offset 807Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 807Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Clear Active IN EP ID Control (HOST_CLR_IN_EP_VALID_REG):** This register is used to clear the internal valid IN EP array that TRM stored in order to guarantee one IN EP per port. This register allows software to clear the valid bit of each port IN EP. This field indicates the port number. For a 2port configuration, only bit1:0 are valid. It can scale for the max number of ports that we support. **Power Well:** Core

51.3.139 Clear Poll Mask Control (HOST_CLR_PMASK_REG)—Offset 8080h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8080h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
9:5	0x0 WO	**Slot Number Default Config (SNDC):** 5bits of slot number as a default configuration. It can scale to max of 128 slots **Power Well:** Core
4:1	0x0 WO	**EP Number (EP_NUM):** 4bits of EP number **Power Well:** Core
0	0x0 WO	**Clear Internal Scheduler's Poll Mask (CISPM):** This is a register that is used to clear the internal scheduler's poll mask that is used to indicate whether we need to poll this EP. This is used for USB2. Bit0 indicates the direction of the EP **Power Well:** Core

51.3.140 Host Control Scheduler (HOST_CTRL_SCH_REG)—Offset 8094h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00008100h

BAR and Offset: [MBAR] + 8094h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RW	**Scheduler Host Control Reg Cont (SCHED_HOST_CTRL_CONT):** method of USB2 port periodic done check (off by default) **Power Well:** Core
20:13	0x4 RW	**TTE Host Control (TTE_HOST_CTRL):** (0): disable interrupt complete split limit to 3 microframes (1): disable checking of missed microframes (2): disable split error request w/NULL pointer on speculative INs with data payload and no TRB. (3): disable deferred split error request on speculative IN with data payload and no TRB. (7:4): reserved **Power Well:** Core
12:11	0x0 RW	**Cache Size Control Reg (CACHE_SZ_CTRL):** 0: 64 1: 32 2,3: 16 **Power Well:** Core
10:9	0x0 RW	**Maximum EP Per Slot (MAX_EP_SLOT):** 0: 32 1: 16 2: 8 3: 4 **Power Well:** Core
8	0x1 RW	**Turn on scratch_pad_en (TO_SCRATCH_PAD_EN):** Reserved. **Power Well:** Core
7:0	0x0 RW	**Scheduler Host Control Reg (SCHED_HOST_CTRL):** (0): disable poll delay (1): disable TRM active in EP valid check (2): enable TTE overlap prevention on interrupt IN EPs (at cost of possible service interval slip) (3) enable TTE overlap prevention on interrupt OUT EPs (at cost of possible service interval slip) (5:4) scheduler sort pattern 00 (default) search ISO ahead of interrupt within each service interval 01 - search USB2-ISO, USB3-ISO, USB2-Interrupt, USB3-Interrupt within each service interval 10 - search strictly by interval 11 - search all ISO intervals ahead interrupt intervals and within each interval, USB2 ahead of USB3 (6): disable 1 pack scheduling limit when ISO pending in present microframe (7): enable check to stop scheduling on port that are not connected **Power Well:** Core

51.3.141 Power Management Control (PMCTRL_REG)—Offset 80A4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 002DFF90h

BAR and Offset: [MBAR] + 80A4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Async PME Source Enable (ASYNC_PME_SRC_EN):** This field allows the async PME source to be allowed to generate PME. This is specifically required for SOCs that do not allow for any clock other than RTC to be available during RTD3. **Power Well:** SUS
30	0x0 RW	**Legacy PME Source Enable (LEGACY_PME_SRC_EN):** This field allows the legacy PME source to be used in PME generation. The legacy source in in reference to the source prior to the RTD3 changes. **Power Well:** SUS
29	0x0 RW	**Reset Warn Power Gate Trigger Disable (RESET_WARN_PWR_GATE_TRIGGER_DISABLE):** This field controls the actions taken for due to reset warn. 0 - Reset Warn will trigger a HW autonomous Power Gate 1 - Reset Warn will not trigger a HW autonomous Power Gate **Power Well:** SUS
28	0x0 RW	**CLR_PME_FLAG_PULSE_AUX_CCLK:** Reserved. **Power Well:** SUS
27	0x0 RW	**RESERVED (RSVD):** Reserved. **Power Well:** SUS
26	0x0 RW	**XLFPSCOUNTSRC:** XLFPSCOUNTSRC (Source for LFPS OFF Counter) 0: Central RTC Counter for LFPS detection 1: Local Counter for LFPS detection **Power Well:** SUS
25	0x0 RW	**XELFPSRTC:** XELFPSRTC (Enable LFPS Filtering on RTC) 0: Use Oscillator clock for LFPS Filtering during P3 1: Use RTC Clock for LFPS Filtering during P3 **Power Well:** SUS
24	0x0 RW	**XMPHYSPGDD0I2:** XMPHYSPGDD0I2 (ModPhy Sus Well Power Gate Disable for D0I2) 0 : Modphy sus well power gating enabled 1 : Modphy sus well power gating disabled **Power Well:** SUS
23	0x0 RW	**XMPHYSPGDD0I3:** XMPHYSPGDD0I3 (ModPhy Sus Well Power Gate Disable for D0I3) 0 : Modphy sus well power gating enabled 1 : Modphy sus well power gating disabled **Power Well:** SUS
22	0x0 RW	**XMPHYSPGDRTD3:** XMPHYSPGDRTD3 (ModPhy Sus Well Power Gate Disable for RTD3) 0 : Modphy sus well power gating enabled 1 : Modphy sus well power gating disabled **Power Well:** SUS
21:18	0xb RW	**XD3RTCPTTM:** XD3RTCPTTM (D3 RTC Port Timer Tick Multiplier) This register will be the multiplication factor for determining SSIC Wake Detection Frequency and RXDET based on the XD3RTCPTTC value. If XD3RTCPTTC is 9h and this register is Bh, frequency for RXDET and SSIC H8EXIT detection while MODPHY SUS Power gating is enabled would be 99ms. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**U3 LFPS Periodic Sampling ON Time Control (U3_LFPS_PRDC_SAMPLING_ON_TIME_CTRL):** This field controls the ON time for the LFPS periodic sampling for USB3/SSIC ports. 0 ON time is 2 rtc clocks 1 ON time is 3 rtc clocks Note: This field is ignored if USB3/SSIC PHY SUS Well Power Gating is enabled. **Power Well:** SUS
16	0x1 RW	**AON LFPS Detector Enable Mode (AON_LFPS_DETECTOR_EN_MODE):** 1 - Allow the LFSP Detector in AON to own LFPS detection when the port is in PS3 for U2/U3 - not RxD regardless of port ownership. 0 - Allow the LFPS Detector in AON to own the LFPS detection only when the AON owns the port and in U2/U3 - not RxD **Power Well:** SUS
15:8	0xff RW	**SS U3 LFPS Detection Threshold (SS_U3_LFPS_DETECTION_THRESHOLD):** This field controls the threshold used to determine when a valid U3 Wake is detected through when using the unfiltered LFPS source. The value on this field will reflect the binary count required to have been detected on the counter being clocked by the unfiltered lfps source to result in a valid U3 wake detection. **Power Well:** SUS
7:4	0x9 RW	**SS_U3_LFPS_PRDC_SAMPLING_OFFTIME_CTRL:** This field controls the OFF time for the LFPS periodic sampling for USB3 Ports 0x0 periodic sampling is disabled. 0x1 OFF time is 1ms 0x2 OFF time is 2ms 0xF OFF time is 15ms The ON Time is determined by the amount of time required to reliably determine if there is a valid LFPS and is HW implementation specific. A speed up mode shall be implemented where this field is in units of us. i.e. 0x1 = 1 us OFF time, 0x2 = 2 us OFF time, etc. **Power Well:** SUS
3	0x0 RW	**PS3 LFPS Source Select (PS3_LFPS_SRC_SEL):** 0 LFPS Source is unfiltered 1 LFPS Source is filtered (Rx-Elec-Idle) LFPS Source is Rx-Elec-Idle for any non PS3 state. **Power Well:** SUS
2	0x0 RW	**XHCI Engine Autonomous Power Gate Exit Reset Policy (XHC_AUTO_PWRGATE_EXITRST_POLICY):** Controls when the xHCI engine is brought out of reset due to a power ungate. 0 Engine is brought out of reset when D3 to D0 is triggered. This allows for a quick power up sequence while leaving the virtual PCIe LTSSM in L23 is power ungate is not due to D3 to D0. 1 Engine is brought out of reset along with the rest of the IP. This is required for PMC save/restore flow. **Power Well:** SUS
1	0x0 RW	**USB2 Port Wake Unit Coupling Policy (USB2_PORT_WAKE_COUPLING_POLICY):** Controls the trigger for USB2 Port Wake Units to initiate Port Level Power Off Preparation. 0 RTD3 triggered 1 - Port Triggered when in L1, L2 or Disabled, Disconnected **Power Well:** SUS
0	0x0 RW	**USB3 Port Wake Unit Coupling Policy (USB3_PORT_WAKE_COUPLING_POLICY):** Controls the trigger for USB3 Port Wake Units to initiate Port Level Power Off Preparation. 0 - RTD3 Triggered 1 - Port Triggered when in PS3 due to RxDetect, U3, U2 or Disabled **Power Well:** SUS

51.3.142 PGCB Control (PGCBCTRL_REG)—Offset 80A8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00315555h

BAR and Offset: [MBAR] + 80A8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** SUS
27:25	0x0 RW	**IP_INACCESSIBLE_HYSTERESIS_TIMER:** • 000 =50us • 001 =100us • 010 =150us • 011 =200us • 000 =250us • 001 =300us • 010 =350us • 111 =400us **Power Well:** SUS
24	0x0 RW	**Override_Disable (OVERRIDE_DISABLE):** Reserved. **Power Well:** SUS
23:20	0x3 RW	**CDH Aggregation Minimum Wait Time (CDH_MIN_WAIT_TIME):** This field controls the minimum time that we must wait for resets to propagate before allowing Power Up flow to complete. The Power Up flow requires special handling of clocks, reset and sleep signaling which requires the CDH to monitor reset propagation. This timer allow for flexibility on when we consider all resets propagated. • 0h Disabled • 1h 2 clocks • 2h 4 clocks • 3h 8 clocks • 4h 16 clocks • 5h 32 clocks • 6h 64 clocks • 7h 128 clocks **Power Well:** SUS
19	0x0 RW	**RESERVED (CDH_RST_PROPAGATION_CNTRL):** This bit will indicate the mode of operation for the CDH Reset Propagation Aggregator. It allows for a mode where the aggregation will wait for an indication from each CDH before proceeding OR ignore the CDH indication before proceeding. Regardless of the mode, the aggregator will enforce the CDH Aggregation Mini Wait Time. 0 Aggregate all the CDH indications before triggering the CDH Aggregation Mini Wait Time. Once the Min Wait Time is met a notification to the Power Sequencer/Control will be initiated 1 Trigger the CDH Aggregation Mini Wait Time w/o waiting for CDH indication. Once the Min Wait time is met a notification to the Power Sequencer/Control will be initiated. **Power Well:** SUS
18	0x0 RW	**MMP_PFET_REQ_OVRD:** This bit will disable the MMP PFET request condition for PGCB control. • 1 MMP PFET Request Ignored • 0 Default **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
17:16	0x1 RW	**PGCB Clock Gate Request to PGCB Sleep (PGCB_CLK_GATE_REQ_2_PGCB_SLEEP):** Value representing the minimum number of delay clocks required between the assertion of pgcb_ip_clkgate_b to the deassertion of pgcb_sleep on PG exit. (This is only applicable for IP-Accessible PG with state-retention enabled.) Please see the description of cfg_tsleepact for more details. **Power Well:** SUS
15:14	0x1 RW	**PGCB Sleep Deassertion to PGCB ISM Unlock Req (PGCB_SLEEP_DEASRTN_2_ISM_UNLOCK_REQ):** For IP-Accessible PG (with state retention): Value representing the minimum number of delay clocks required between the deassertion of gcb_sleepto the deassertion of pgcb_ip_*_lock_req_b. For IP-Inaccessible PG (or with state-retention disabled): Value representing the minimum number of delay clocks required between the deassertion of pgcb_sleep to the deassertion of pgcb_isol_en_b. **Power Well:** SUS
13:12	0x1 RW	**PGCB Prim Reset Deassertion to PGCB Next State (PGCB_PRIMRST_DEASRTN_2_NSTATE):** For IP-Accessible PG (with state retention): Value representing the minimum number of delay clocks required between the deassertion of pgcb_sleep to the deassertion of pgcb_ip_*_lock_req_b. For IP-Inaccessible PG (or with state-retention disabled): Value representing the minimum number of delay clocks required between the deassertion of pgcb_sleep to the deassertion of pgcb_isol_en_b. **Power Well:** SUS
11:10	0x1 RW	**PGCB Side Reset Deassertion to PGCB Prim Reset Deassertion (PGCB_SIDERST_DEASRTN_2_PRIMERST_DEASRTN):** Value representing the number of delay clocks required between the deassertion of gcb_force_rst_bto the deassertion of gcb_force_prim_rst_b (This is only applicable for IP-Accessible PG.) Please see the description of cfg_tsleepact for more details. **Power Well:** SUS
9:8	0x1 RW	**PGCB Latch Isolation High to PGCB Clock Ungate Request (PGCB_LATCH_ISO_HI_2_PGCB_CLK_UNGATE_REQ):** Value representing the number of delay clocks required between the assertion of pgcb_isol_latchen to the deassertion of pgcb_ip_clkgate_req_b. Please see the description of cfg_tsleepact for more details. **Power Well:** SUS
7:6	0x1 RW	**PGCB Isolation Deassertion to PGCB Latch Isolation High Count (PGCB_ISO_DEASRTN_2_PGCB_ISO_HI_CNT):** Value representing the minimum number of delay clocks required between the deassertion of pgcb_isol_en_b to the assertion of gcb_isol_latchen. Please see the description of cfg_tsleepact for more details. **Power Well:** SUS
5:4	0x1 RW	**PGCB Reset Assertion to PGCB Power Down Request Count (PGCB_RST_2_PGCB_PWRDOWN_REQCNT):** For IP-Accessible PG (with state retention): Value representing the minimum number of delay clocks required between the assertion of pgcb_force_prim_rst_b and pgcb_force_rst_b to the assertion of pgcb_pmc_pg_req_b. For IP-Inaccessible PG (or with state-retention disabled): Value representing the minimum number of delay clocks required between the assertion of pgcb_force_prim_rst_b and pgcb_force_rst_b to the assertion of pgcb_sleep. Please see the description of cfg_tsleepact for more details. **Power Well:** SUS
3:2	0x1 RW	**PGCB Isolation Assertion to PGCB Reset Assertion Count (PGCB_ISO_ASRTN_2_PGCB_RST_ASRTN_CNT):** Value representing the minimum number of delay clocks required between the assertion of gcb_isol_en_bto the assertion of gcb_force_prim_rst_band gcb_force_rst_b Please see the description of [1:0] for more details. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
1:0	0x1 RW	**PGCB Sleep Assertion to PGCB Isolation Enable Count (PGCB_SLEEP_ASRTN_2_PGCB_ISO_EN_CNT):** For IP-Accessible PG (with state retention): Value representing the minimum number of delay clocks required between the assertion of pgcb_sleep (and the deassertion of pgcb_isol_latchen) to the assertion of pgcb_isol_en_b. For IP-Inaccessible PG (or with state-retention disabled): Value representing the minimum number of delay clocks required between the deassertion of pgcb_isol_latchen to the assertion of pgcb_isol_en_b, as well as the minimum number of delay clocks required between the assertion of pgcb_sleep to the assertion of pgcb_pmc_pg_req_b. Common for all cfg_t* inputs: 0 1 clock 1 2 clocks 0 8 clocks 1 256 clocks For any of the cfg_t* inputs that an IP may feel are a don-care and the IP does not feel they will be useful for post-silicon debug, the recommendation is to tie the input to 201 (2 clocks). Otherwise, the inputs may be tied to another relevant value or connected to a configuration register. ***Note:*** These signals may only change while pgcb_pwrupidle is asserted, if pgcb_pwrupidle is deasserted it should be valid and stable. (It may change the same cycle that ip_pgcb_pg_rdy_req_b asserts.) **Power Well:** SUS

51.3.143 D0I3 Control (DOI3CTRL_REG)—Offset 80ACh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000008h

BAR and Offset: [MBAR] + 80ACh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** SUS
3	0x1 RW/1C	**RestoreRequired (RESTORE_REQUIRED):** When set (by HW), SW must restore state to the IP. The state may have been lost due to a reset or full power lost. SW clears the bit by writing a 1. This bit will be set on initial power up. **Power Well:** SUS
2	0x0 RW	**D0I3:** SW sets this bit to 1 to move the IP into the D0i3 state. Writing this bit to 0 will return the IP to the fully active D0 state (D0i0). **Power Well:** SUS
1:0	0x0 RO	**RESERVED (RSVD1):** Reserved. **Power Well:** SUS

51.3.144 HOST_CTRL_MISC_REG—Offset 80B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0001037Fh

BAR and Offset: [MBAR] + 80B0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**USB2_LTRUPDT_DIS:** Reserved. **Power Well:** Core
30	0x0 RW	**USB2 Line State Debounce During Port Reset Policy (USB2_LINE_STATE_DEBOUNCE_DURING_PORT_RESET_POLICY):** This register controls how the debounce is enforced during the Port Reset phase. 0 do not enable the line state debounce during port reset. 1 enable the line state debounce during port reset. **Power Well:** Core
29	0x0 RW	**TTE PEXE Credit Fix Disable (TTE_PEXE_CREDIT_FIX_DISABLE):** When set, it disables a fix implemented to re-deem PEXE credits when a port is disconnected **Power Well:** Core
28	0x0 RW	**TTE Scheduling policy (TTE_SCHEDULING_POLICY):** This register controls a fix made to prevent over-scheduling by not account for 188B in each uFrame. Setting this bit will disable the fix and allow for over-scheduling. **Power Well:** Core
27	0x0 RW	**USB3 ITP Delta Timer Source Select (USB3_ITP_DELTA_TIMER_SOURCE_SELECT):** This register selects the source for the delta timer tracking used for ITP generation. 0 the source is a 16.666 ns tick generated from a crystal reference clock 1 - the source is a 16.666 ns tick generated from the aux_cclk. This field needs to remain in sync with Frame Timer Source Select to ensure the are both set or both cleared. There is no support for any other combination. **Power Well:** Core
26	0x0 RW	**Frame Timer Source Select (FRAME_TIMER_SOURCE_SELECT):** This register controls the source for the frame timer. 0 the source for the frame timer is a crystal reference clock 1 the source for the frame timer is the aux_cclk. **Power Well:** Core
25	0x0 RW	**uFrame Masking Enable (UFRAME_MASKING_ENABLE):** If set, enables the uFrame tick to be masked due to ports being in U3/NC. This controls a fix made to disable the auto masking of uFrame tick due to port state w/o any pipeline idle condition. When cleared, we rely on gating of frame timer due to proper port state and idleness tracking from the pipeline. **Power Well:** Core
24	0x0 RW	**Late FID Check Disable (LATE_FID_CHECK_DISABLE):** This register disables the Late FID Check performed when starting an ISOCH stream. **Power Well:** Core
23:20	0x0 RW	**RESERVED (RSVD1):** Reserved. **Power Well:** Core
19	0x0 RW	**USB2 Resume Cx Inhibit Disable (USB2_RESUME_CX_INHIBIT_DISABLE):** Controls if USB2 L1 Resume is allowed to contribute to DMA Active which will inhibit Cx state. 0 USB2 L1 Resume is allowed to inhibit Cx via DMA Active 1 USB2 L1 Resume is NOT allowed to inhibit Cx via DMA Active When cleared, Cx will only be inhibited when the DMA traffic for the port begins. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
18:16	0x1 RW	**Extra uFrame (EXTRA_UFRAME):** This register controls the extra number of uFrames added onto the advancing of late FID check. **Power Well:** Core
15:0	0x37f RW	**Valid Isoch Scheduling Range (VALID_ISOCH_SCHEDULING_RANGE):** This register defines the window in miliseconds from the current Frame that will be considered for scheduling in an upcoming Frame. Anything scheduled outside of this window will be considered as late and will trigger the Missed Service Error. **Power Well:** Core

51.3.145 reg_SSPITPE_type (SSPITPE)—Offset 80BCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0000000Fh

BAR and Offset: [MBAR] + 80BCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**RSVD:** Reserved. **Power Well:** Core
3:0	0xf RW	**ITP Transmit Enable (ITP_TRANSMIT_EN):** Width is scaled with USB3 Port Count PortCount=4 **Power Well:** Core

51.3.146 AUX Reset Control (AUX_CTRL_REG)—Offset 80C0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 015FC0F0h

BAR and Offset: [MBAR] + 80C0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Reset USB3 AUX/Main PD Logic (RST_U3_AM_PDL):** A reset that is designed to reset all USB3 port AUX + Main power domain logic. This is a debug function. It is called cold reset. Write 1 to this register will issue a cold reset to USB3 ports. **Power Well:** SUS
30	0x0 RW	**RESERVED (RSVD):** Reserved. **Power Well:** SUS
29	0x0 RW	**Enable PCIe PIPE Reset As PCIe PHY Reset (EN_PPIPE_PPHY_RST):** This bit set to 1 selects the PCIe PIPE reset as a PCIe PHY power on reset. 0 selects the AUX powerup reset as a PCIe PHY powerup reset. **Power Well:** SUS
28	0x0 RW	**Ensure PIPE Powerdown On PERST# (EN_PPWRDN_PERST):** This bit ensures any PERST# being asserted will cause PIPE powerdown state transition to P1. **Power Well:** SUS
27	0x0 RW	**Disable PERST# Main RST (DIS_PERST_MRST):** There is a feature where we only allow PERST# to be treated as a main powerdown reset when it is asserted during the state that is not in D3. This bit disables this feature when it is set to 1. If this bit is set to 1, it means that any PERST# will be treated as a main power domain reset regardless of its Dstate. **Power Well:** SUS
26	0x0 RW	**Disable PCIe PERST# Host Controller (DIS_PERST_HC):** There is a feature where we can disable PCIe PERST# from reset the host controller until power management control module has done its clock switching. This is for a case where PM entered L23 and immediately PERST# asserted. This bit is designed to enable this feature when set to 1. **Power Well:** SUS
25	0x0 RW	**Enable Fast Simulation Reset Mode (EN_FAST_RST):** Enable a fast simulation mode for reset function. This is a feature for GLS **Power Well:** SUS
24	0x1 RW	**Prevent USB3 Link Down Reset (PREV_U3_LDRST):** When set to 1 prevent a reset being generated due to the USB3 port link down condition. **Power Well:** SUS
23	0x0 RW	**Ignore Main Power Up Reset (IGN_MPU_RST):** When set to 1 ignore the main power up reset for USB3 PIPE PHY reset. **Power Well:** SUS
22	0x1 RW	**RESERVED (RSVD_1):** Reserved. **Power Well:** SUS
21	0x0 RW	**Ignore HC Reset USB2 (IGN_HC_RST_U2):** When set to '1' ignore HC reset to reset the USB2 Port logic **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
20	0x1 RW	**Ignore HC Reset USB PHY (IGN_HC_RST_UP_POR):** When set to '1' ignore HC reset to the USB PHY power-on reset **Power Well:** SUS
19	0x1 RW	**Enable PCIe Link-Down Reset (EN_PLD_RST):** Enable a reset due to a PCIe link-down condition. The PCIe link down condition will cause a HC reset liked. If this bit is set 1, the PCIe link down condition will only reset the PCIe core. **Power Well:** SUS
18	0x1 RW	**Enable EEPROM Reload On Power Up (EN_EEP_REL_PU):** When set to '1' enable EEPROM reload on every main power-up **Power Well:** SUS
17	0x1 RW	**Ignore HC Reset PCIe PHY PIPE (IGN_HC_RST_PPP):** When set to '1' ignore HC reset to the PCIe PHY PIPE reset **Power Well:** SUS
16	0x1 RW	**Ignore LTSSM Reset USB PHY PIPE (IGN_LRST_UPP):** When set to '1' ignore the LTSSM of USB link state transition caused reset to USB PHY PIPE reset **Power Well:** SUS
15	0x1 RW	**Ignore Warm Reset USB PHY Power (IGN_WR_UPP):** When set to '1' ignore warm reset the USB PHY power on reset **Power Well:** SUS
14	0x1 RW	**Allow Core PCIe Link Down Reset (ALL_CPLD_RST):** When set to '1' allow PCIe link down to cause a reset to the rest of the core **Power Well:** SUS
13	0x0 RW	**Ignore Hot Reset USB3 (IGN_HR_U3):** When set to '1' ignore hot reset to the USB3 port logic **Power Well:** SUS
12	0x0 RW	**Ignore Warm Reset USB3 (IGN_WR_U3):** When set to '1' ignore warm reset to the USB3 port logic **Power Well:** SUS
11	0x0 RW	**Ignore Main Power Up Reset USB3 (IGN_MPU_RST_U3):** When set to '1' ignore main power up reset to USB3 port logic **Power Well:** SUS
10	0x0 RW	**Ignore Main Power Up Reset USB2 (IGN_MPU_RST_U2):** When set to '1' ignore main power up reset to USB2 port logic **Power Well:** SUS
9	0x0 RW	**Ignore Main Power Up Reset PCIe Core (IGN_MPU_RST_PC):** When set to '1' ignore main power up reset to PCIe core **Power Well:** SUS
8	0x0 RW	**Ignore Main Power Up Reset PCIe PHY (IGN_MPU_RST_PP):** When set to '1' ignore main power up reset to PCIe PHY **Power Well:** SUS
7	0x1 RW	**Ignore HC Reset USB PHY (IGN_HC_RST_UP):** When set to '1' ignore HC reset to the USB PHY **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
6	0x1 RW	**Ignore Warm Reset USB PHY (IGN_WRST_UP):** When set to '1' ignore warm reset to the USB PHY **Power Well:** SUS
5	0x1 RW	**Enable HC Reset Per Port Isolation (EN_HC_RST_PPI):** Enables the HC reset or per port reset isolation function **Power Well:** Core
4	0x1 RW	**Allow Power Off Power Domain Reset (ALL_PO_PDRST):** When set to '1' allow main power off condition to trigger a main power domain reset **Power Well:** SUS
3	0x0 RW	**Ignore Wait For PERST# During Power Show Down (IGN_PERST_PSD):** When set to '1' ignore waiting for PERST# deassertion during main power show down. **Power Well:** SUS
2	0x0 RW	**Ignore Fundamental Reset During AUX Power Up (IGN_FRST_AUX_PU):** When fundamental reset is asserted during AUX power up, if this bit is set, then we will ignore PERST# such that purely wait for timeout to deassert fundamental reset. **Power Well:** SUS
1:0	0x0 RW	**Trigger Fundamental Reset (TRIG_FRST):** Writing to bit(1:0) to value of 2'b11 will cause a fundamental reset **Power Well:** SUS

51.3.147 Super Speed Bandwidth Overload (HOST_BW_OV_SS_REG)—Offset 80C4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 004A4008h

BAR and Offset: [MBAR] + 80C4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
23:12	0x4a4 RW	**Max. TT BW Allowed (MAX_TT_BWA):** **Power Well:** Core
11:0	0x8 RW	**Per Packet Overhead SS BW (PP_OVRH_SSBW):** BW calculation: Overhead per packet for SS BW calculations. **Power Well:** Core

51.3.148 High Speed TT Bandwidth Overload (HOST_BW_OV_HS_REG)—Offset 80C8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0001A01Fh

BAR and Offset: [MBAR] + 80C8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
23:12	0x1a RW	**Per Packet Overhead HS-TT BW (PP_OVRH_HSTTBW):** BW calculation: Overhead per packet for HS-TT BW calculations. **Power Well:** Core
11:0	0x1f RW	**Per Packet Overhead HS BW (PP_OVRH_HSBW):** BW calculation: Overhead per packet for HS BW calculations. **Power Well:** Core

51.3.149 Bandwidth Overload Full Low Speed (HOST_BW_OV_FS_LS_REG)—Offset 80CCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00014080h

BAR and Offset: [MBAR] + 80CCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
23:12	0x14 RW	**Per Packet Overhead FS BW (PP_OVRH_FSBW):** BW calculation: Overhead per packet for FS BW calculations. **Power Well:** Core
11:0	0x80 RW	**Per Packet Overhead LS BW (PP_OVRH_LSBW):** BW calculation: Overhead per packet for LS BW calculations. **Power Well:** Core

51.3.150 System Bandwidth Overload (HOST_BW_OV_SYS_REG)—Offset 80D0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00032010h

BAR and Offset: [MBAR] + 80D0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
23:12	0x32 RW	**Per TT Packet Overhead System BW (PTTP_OVRH_SBW):** BW calculation: Overhead per TT packet for System BW calculations. **Power Well:** Core
11:0	0x10 RW	**Per Packet Overhead System BW (PP_OVRH_SBW):** BW calculation: Overhead per packet for System BW calculations. **Power Well:** Core

51.3.151 Scheduler Async Delay (HOST_CTRL_SCH_ASYNC_DELAY_REG)—Offset 80D4h

Global defaults for inserting delays between packets in the scheduler for async. types.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 80D4h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
19	0x0 RW	**High-Speed Bulk Delay Enable (HS_BD_EN):** Reserved. **Power Well:** Core
18:16	0x0 RW	**High-Speed Bulk Delay Default (HS_BD_DEF):** (0=125us,1=250us,2=500us,3=1ms,...) **Power Well:** Core
15	0x0 RW	**Full-Speed Bulk Delay Enable (FS_BD_EN):** Reserved. **Power Well:** Core
14:12	0x0 RW	**Full-Speed Bulk Delay Default (FS_BD_DEF):** (0=125us,1=250us,2=500us,3=1ms,...) **Power Well:** Core
11	0x0 RW	**High-Speed Control Delay Enable (HS_CD_EN):** Reserved. **Power Well:** Core
10:8	0x0 RW	**High-Speed Control Delay Default (HS_CD_DEF):** (0=125us,1=250us,2=500us,3=1ms,...) **Power Well:** Core
7	0x0 RW	**Full-Speed Control Delay Enable (FS_CD_EN):** Reserved. **Power Well:** Core
6:4	0x0 RW	**Full-Speed Control Default (FS_CD_DEF):** (0=125us,1=250us,2=500us,3=1ms,...) **Power Well:** Core
3	0x0 RW	**Low-Speed Control Delay Enable (LS_CD_EN):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Low-Speed Control Delay Default (LS_CD_DEF):** (0=125us,1=250us,2=500us,3=1ms,...) **Power Well:** Core

51.3.152 AUX Power Management Control (AUX_CTRL_REG1)—Offset 80E0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 808DBCA0h

BAR and Offset: [MBAR] + 80E0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**D3 Hot function enable register (D3_HOT_FXN_EN):** This bit is from pin input which is set 1. But we allow software to alter it if it is needed. 1: D3 hot enabled 0: D3 hot not abled. **Power Well:** SUS
30	0x0 RW	**Allow L1 Core Clock Gating (ALL_L1_CORE_CG):** When set to 1 allows core clock being gated during L1 state. **Power Well:** SUS
29	0x0 RW	**Allow Engine PHY Status Extension (AL_EP_SEXT):** When set to 1 allows the engine to extend PHY status of PCIe PIPE for one more cycle. This is due to the fact that our rate change function has a potential of not being able to sample the phystatus signal. **Power Well:** SUS
28	0x0 RW	**Allow Engine PCIe Rate Change Passing (ALL_EP_RCP):** When set to 1 allows the engine to pass PCIe rate change signal as it is from PCIe core to PCIe PHY. **Power Well:** SUS
27	0x0 RW	**Allow Engine PERST Fundamental Reset (AL_PERST_FRST):** When set to 1 allow engine to treat PERST# as a foundamental reset **Power Well:** SUS
26	0x0 RW	**Overwrite PCIe P2 to P1 (OVR_PCIE_P2_P1):** When set to 1 will overwrite a PCIe powerdown state of P2 to P1. **Power Well:** SUS
25	0x0 RW	**Set Internal SSV 1 (SET_ISSV_1):** When set to 1 set the internal SSV to 1. **Power Well:** SUS
24	0x0 RW	**Clear Internal SSV 0 (CLR_ISSV_0):** When set to 1 clear the internal SSV to 0. **Power Well:** SUS
23	0x1 RW	**Enable save_restore_enable SW Loading (EN_SRE_SW_LD):** This is a bit that enables the save_restore_enable signal being loaded when a software command has set Save bit. This is a debug function. **Power Well:** SUS
22	0x0 RW	**RESERVED (RSVD_1):** Reserved. **Power Well:** SUS
21	0x0 RW	**Force save_restore 1 (FORCE_SR1):** When set to 1, it will force the save_restore flag to 1. This flag is an bit to ensure that we have masked the update during low power state. If software write this bit to 1, it must write it to 0 in order to resume the normal save and restore function. **Power Well:** SUS
20	0x0 RW	**cfg pcie txreg rd (CPTR):** Reserved. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
19	0x1 RW	**cfg iob drivestrength[1] (CIDS1):** Reserved. **Power Well:** SUS
18	0x1 RW	**cfg iob drivestrength[0] (CIDS0):** Reserved. **Power Well:** SUS
17	0x0 RW	**Enable CFG USB P2 (EN_CFG_UP2):** When set to '1' enable cfg usb p2 **Power Well:** SUS
16	0x1 RW	**cfg clk gate dis (CCGD):** Reserved. **Power Well:** SUS
15	0x1 RW	**Enable CFG RXDET P3 (EN_CFG_RDP3):** When set to '1' enable cfg rxdet p3 **Power Well:** SUS
14	0x0 RW	**Enable CFG PIPE Reset (EN_CFG_PIPE_RST):** When set to '1' enable cfg pipe rst **Power Well:** SUS
13	0x1 RW	**Enable Filter TX Idle (EN_FILT_TX_IDLE):** When set to 1 enables a filter function to TX electrical idle signal at PCie PIPE. We have a filter that will set TXelecidle signal of PCIe PIPE to 1 whenever we are in isolation state or power down transition states. **Power Well:** SUS
12	0x1 RW	**Enable Host Engine Generate PME (EN_HE_GEN_PME):** This is a global switch to whether or not eable this host engine to generate PME message. **Power Well:** SUS
11	0x1 RW	**Enable Isolation (EN_ISOL):** When set to '1' enable isolation **Power Well:** SUS
10	0x1 RW	**Enable L1 Caused P2 Overwrite (EN_L1_P2_OVR):** Set 1 to enable a new feature. This new feature is designed to use L1 as a state to identify whether we should do P2 Overwrite or not. We used to use P1 state to identify whether or not to invoke P2 overwrite function. **Power Well:** SUS
9	0x0 RW	**Enable Core Clock Gating (EN_CORE_CG):** When set to '1' enable core clock gating based on low power state entered **Power Well:** SUS
8	0x0 RW	**Enable PHY Status Timeout (EN_PHY_STS_TO):** When set to '1' enable PHY status timeout function which is designed to cover the PCIePHY issue that we may have not able to detect the PHY status toggle. **Power Well:** SUS
7	0x1 RW	**Ignore aux_pm_en PCIe Core (IGN_APE_PC):** When set to '1' ignore the aux_pm_en reg from PCIe core to continue the remote wake/clock switching support **Power Well:** SUS
6	0x0 RW	**Enable P2 Overwrite P1 (EN_P2_OVR_P1):** When set to '1' enable P2 overwrite P1 when PCIe core has indicated the transition from P0 to P1. This is to enable entering the even lower power state. **Power Well:** SUS
5	0x1 RW	**Enable P2 Remote Wake (EN_P2_REM_WAKE):** When set 1 '1' enable the remote wake function by allowing P2 clock/switching and P2 entering **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
4:1	0x0 RW	**Forced PM State (FORCED_PM_STATE):** Reserved. **Power Well:** SUS
0	0x0 RW	**Initiate Force PM State (INIT_FPMS):** When set to '1' force PM state to go to the state indicated in bit 4:1 **Power Well:** SUS

51.3.153 Battery Charge (BATTERY_CHARGE_REG)—Offset 80E4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 80E4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Enable DM_SRC Battery Charge (EN_DS_BC):** 1 - Always enable battery charge DM_SRC if not connected. Don't wait for portable device detect. (spec. ver. 1.2) 0 - Battery charge spec ver. 1.1. **Power Well:** SUS
30:4	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
3	0x0 RW	**Enable Port 3 Battery Charging (EN_P3_BC):** 0 - Battery charging disabled (Physical Port #3) 1 - Battery charging enabled (Physical Port #3) **Power Well:** SUS
2	0x0 RW	**Enable Port 2 Battery Charging (EN_P2_BC):** 0 - Battery charging disabled (Physical Port #2) 1 - Battery charging enabled (Physical Port #2) **Power Well:** SUS
1	0x0 RW	**Enable Port 1 Battery Charging (EN_P1_BC):** 0 - Battery charging disabled (Physical Port #1) 1 - Battery charging enabled (Physical Port #1) **Power Well:** SUS
0	0x0 RW	**Enable Port 0 Battery Charging (EN_P0_BC):** 0 - Battery charging disabled (Physical Port #0) 1 - Battery charging enabled (Physical Port #0) **Power Well:** SUS

51.3.154 SuperSpeed Port Link Control (HOST_CTRL_PORT_LINK_REG)—Offset 80ECh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 18010000h

BAR and Offset: [MBAR] + 80ECh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x3 RW	**Force LTSSM State (FORCE_LTSSM_ST):** LTSSM state to be forced This value is for test purpose only. **Power Well:** Core
26	0x0 RW	**Direct Link LTSSM State (DL_LTSSM_ST):** 0: Normal operation mode 1: Direct link to a specific state specified by bit 31:27 This bit is for test purpose only. It shall be written 0 in normal operation mode. **Power Well:** Core
25	0x0 RW	**Direct Link To U0 (DL_U0):** 0: Normal operation mode 1: Direct link to U0 This bit is for test purpose only. It shall be written 0 in normal operation mode. **Power Well:** Core
24:21	0x0 RW	**Forced Compliance Pattern (FORCED_CMP_PAT):** Compliance pattern to be forced to enter compliance mode This value is for test purpose only. **Power Well:** Core
20	0x0 RW	**Enable Link Error Slave Count (EN_LES_CNT):** 0: Disable link error slave count 1: Enable link error slave count **Power Well:** Core
19:17	0x0 RW	**Debug Mode Select (DEBUG_MD_SEL):** Reserved. **Power Well:** Core
16:15	0x2 RW	**PHY Low Power Latency (PHY_LP_LAT):** This field defines the latency to drive the PHY to enter low power mode 0: 4 cycles 1: 8 cycles 2: 16 cycles 3: 32 cycles **Power Well:** Core
14:12	0x0 RW	**Link Recovery Minimum Time (LR_MIN_TM):** This value defines the minimum time for the link to stay in Recovery.Active other than from U3. The granuity is 128us. **Power Well:** Core
11:9	0x0 RW	**Link Polling Minimum Time (LP_MIN_TM):** This value defines the minimum time for the link to stay in Polling.Active and Recovery.Active from U3. The granuity is 128us. **Power Well:** Core
8	0x0 RW	**Force Link Accept PM Command (FORCE_LA_PMC):** 0: Normal operation mode 1: Force link to accept power management command **Power Well:** Core
7	0x0 RW	**Direct Link Recovery U0 (DL_REC_U0):** 0: Normal operation mode 1: Direct link to Recovery from U0 **Power Well:** Core
6	0x0 RW	**Link Fast Training Mode (LINK_FTM):** 0: Normal operation mode 1: Link fast training mode This bit should be written 0 in normal operation. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**Disable Link Scrambler (DIS_LINK_SCRAM):** 0: Enable link scrambler 1: Disable link scramber **Power Well:** Core
4	0x0 RW	**Direct Link U3 From U0 (DL_U3_U0):** 0: Normal operation mode 1: Direct link to U3 from U0 This bit is for test purpose only. It shall be written 0 in normal operation mode. **Power Well:** Core
3	0x0 RW	**Direct Link U3 From U0 (DL_U2_U0):** 0: Normal operation mode 1: Direct link to U2 from U0 This bit is for test purpose only. It shall be written 0 in normal operation mode. **Power Well:** Core
2	0x0 RW	**Direct Link U3 From U0 (DL_U1_U0):** 0: Normal operation mode 1: Direct link to U1 from U0 This bit is for test purpose only. It shall be written 0 in normal operation mode. **Power Well:** Core
1	0x0 RW	**Enable Link Loopback Master Mode (EN_LINK_LB_MAST):** 0: Disable link loopback master mode 1: Enable link loopback master mode **Power Well:** Core
0	0x0 RW	**Disable Link Compliance Mode (DIS_LINK_CM):** 0: Enable link compliance mode 1: Disable link compliance mode **Power Well:** Core

51.3.155 USB2 Port Link Control 1 (USB2_LINK_MGR_CTRL_REG1)—Offset 80F0h

These set of registers is used to control jey USB set of timers. They are spread over 4 registers each 32 bits wide.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 80F0h

Default: 310803A0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x31 RW	**FS/LS Mode SE0 Disconnect Delay[7:0] (FSLS_SE0_DIS_DEL_7_0):** # of microseconds of SE0 in FS/LS mode to register disconnect had occurred. **Power Well:** SUS
23:21	0x0 RW	**Reserved (RSVD0):** Reserved. **Power Well:** SUS
20	0x0 RW	**L1_EXIT_RECOVERY_MODE:** Mode for extended L1 Exit recovery delay: 0: 12us 1: 50us **Power Well:** SUS
19	0x1 RW	**L1_TO_INCR_MODE:** Mode select for L1 Timeout increments: 0: time out increments are in 125us 1: L1 Timeout increments are in 256us. Refer to USB2 PORTHLPMC.L1 Timeout in XHCI Spec for additional details **Power Well:** SUS
18	0x0 RW	**Reserved (RSVD1):** Reserved. **Power Well:** SUS
17	0x0 RW	**EN_DETECT_NOMINAL_PKT_EOP:** 0: Detect minimal packet EOP. 1: Detect nominal packet EOP. **Power Well:** SUS
16	0x0 RW	**Disable Chirp Response (DIS_CHIRP_RESPONSE):** 0: Normal 1: Force full speed on host ports (disable chirp response) **Power Well:** SUS
15	0x0 RW	**Disable 192 Byte Limit Check (DIS_192B_LIM):** 0: Enforce 192 byte limit on complete-split INs. Treat any packet) 192 as babble case. 1: Disable 192 byte limit check. **Power Well:** SUS
14	0x0 RW	**External Provided FS/LS Disconnect (EXT_FSLS_DIS):** 0: Internal FS/LS Disconnect from linestate(1:0) 1: External provided FS/LS Disconnect from hostdisconnect input **Power Well:** SUS
13:12	0x0 RW	**UTMI Reset Source Select (UTMI_RST_SEL):** Select UTMI Reset Source (FRD UTMI Reset Only) 00: HCReset or Force PHY Reset or internal reset after disconnect/suspend for restart (default) 01,11: UTMI reset = ~UTMI suspendm 10: UTMI reset = ~UTMI suspendm and synchronization to port clk. **Power Well:** SUS
11	0x0 RW	**Disable HS Disconnect Window (DIS_HS_DIS_WIN):** 0: Enable HS Disconnect Window Function 1: Disable HS Disconnect Window Function **Power Well:** SUS
10	0x0 RW	**Disable Port Error Detection (DIS_PERR_DET):** 0: Enable Port Error Detection (default) 1: Disable Port Error Detection **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
9	0x1 RW	**Disable Peek Function for ISO-OUT (DIS_PF_IOUT):** 0: Enable Peek function for ISO-OUT (default) 1: Disable Peek function for ISO-OUT **Power Well:** SUS
8	0x1 RW	**Drive Resume-K FS/LS Serial Interface (DRV_RESK_FSLS_SER):** 0: Drive Resume-K on parallel Interface 1: Drive Resume-K directly on FS/LS Serial Interface (default) **Power Well:** SUS
7	0x1 RW	**Enable USB2 Drop-Ping (EN_U2_DROP_PING):** 0: Disable Drop-Ping Function in USB2 Protocol (default) 1: Enable Drop-Ping Function in USB2 Protocol **Power Well:** SUS
6	0x0 RW	**Enable USB2 Force-Ping (EN_U2_FORCE_PING):** 0: Disable Force-Ping Function in USB2 Protocol (default) 1: Enable Force-Ping Function in USB2 Protocol **Power Well:** SUS
5	0x1 RW	**Enable USB2 Auto-Ping (EN_U2_AUTO_PING):** 0: Disable Auto-Ping Function 1: Enable Auto-Ping Function in USB2 Protocol (default) **Power Well:** SUS
4	0x0 RW	**Disable PHY SuspendM (DIS_PHY_SUSM):** 0: PHY is suspend=U3,U2,disconnect (default) 1: Disable PHY SuspendM in All States **Power Well:** SUS
3	0x0 RW	**UTMI Internal Clock Gate Disable (UTMI_INT_CG_DIS):** 0: Normal operation (internal clock gated in U2,U3,disconnect) 1: UTMI Internal Clock Gate Disable **Power Well:** SUS
2	0x0 RW	**Disable PHY SuspendM in Disconnect State (DIS_PSUSM_DS):** 0: PHY is suspendM=0 in Disconnect State (default) 1: Disable PHY SuspendM in Disconnect State **Power Well:** SUS
1	0x0 RW	**Force PHY Reset (FORCE_PHY_RST):** 0: Normal Operation (default) 1: Force PHY Reset **Power Well:** SUS
0	0x0 RW	**USB2 Accelerated Simulation Timing (U2_ACC_SIM_TIM):** 0: Normal Operation (default - FPGA/ASIC) 1: USB2 Accelerated Simulation Timing (default - simulation) **Power Well:** SUS

51.3.156 USB2 Port Link Control 2 (USB2_LINK_MGR_CTRL_REG2)—Offset 80F4h

These set of registers is used to control jey USB set of timers. They are spread over 4 registers each 32 bits wide.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 80F4h

Default: 80C40620h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**Total Reset Duration[0] (TOT_RST_DUR_0):** # of microseconds for total reset duration **Power Well:** SUS
30:18	0x31 RW	**Chirp-K Duration (CHIRPK_DUR):** # of microseconds of Chirp-K to register that a device is chirping **Power Well:** SUS
17:5	0x31 RW	**K/J Disconnect Connect Delay (KJ_DIS_CON_DEL):** # of microseconds of K/J in disconnected state to register connect has occurred. **Power Well:** SUS
4:0	0x0 RW	**FS/LS Mode SE0 Disconnect Delay[12:8] (FSLS_SE0_DIS_DEL_12_8):** # of microseconds of SE0 in FS/LS mode to register disconnect had occurred. **Power Well:** SUS

51.3.157 USB2 Port Link Control 3 (USB2_LINK_MGR_CTRL_REG3)—Offset 80F8h

These set of registers is used to control jey USB set of timers. They are spread over 4 registers each 32 bits wide.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 80F8h

Default: F865EB6Bh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RW	**U2 Entry Ignore Linestate Changes Duration[3:0] (U2_IGN_LS_DUR_3_0):** # of microseconds after entering U2, linestate changes are ignored as bus settles **Power Well:** SUS
27:15	0x10cb RW	**U3 Entry Ignore Linestate Changes Duration (U3_IGN_LS_DUR):** # of microseconds after entering U3, linestate changes are ignored as bus settles **Power Well:** SUS
14:0	0x6b6b RW	**Total Reset Duration[15:1] (TOT_RST_DUR_15_1):** # of microseconds for total reset duration **Power Well:** SUS

51.3.158 USB2 Port Link Control 4 (USB2_LINK_MGR_CTRL_REG4)—Offset 80FCh

These set of registers is used to control jey USB set of timers. They are spread over 4 registers each 32 bits wide.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00008003h

BAR and Offset: [MBAR] + 80FCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
21:9	0x40 RW	**U2 Detect Remote Wake Delay (U2D_RWAKE_DEL):** #of microseconds after detecting U2 remote wake condition to reflect K **Power Well:** SUS
8:0	0x3 RW	**U2 Entry Ignore Linestate Changes Duration[12:4] (U2_IGN_LS_DUR_12_4):** # of microseconds after entering U2, linestate changes are ignored as bus settles **Power Well:** SUS

51.3.159 Bandwidth Overload Burst (HOST_BW_OV_BURST_REG)—Offset 810Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00008020h

BAR and Offset: [MBAR] + 810Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
23:12	0x8 RW	**Per Burst Overhead System BW (PB_OVRH_SBW):** BW calculation: Overhead per burst for system BW calculations. **Power Well:** Core
11:0	0x20 RW	**Per Burst Overhead System BW (PB_OVRH_SSBW):** BW calculation: Overhead per burst for SS BW calculations. **Power Well:** Core

51.3.160 USB Max Bandwidth Control 4 (HOST_CTRL_BW_MAX_REG)—Offset 8128h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0F42528505647F42h

BAR and Offset: [MBAR] + 8128h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:60	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
59:48	0xf42 RW	**PCIe Max BW Units (PCIE_MAX_BW):** Max. Number of BW units for PCIe (system interface) (denominator in 90% calculation) **Power Well:** Core
47:36	0x528 RW	**TT Max BW Units (TT_MAX_BW):** Max. Number of BW units for TTs. (denominator in 90% calculation) **Power Well:** Core
35:24	0x505 RW	**FS/LS Max BW Units (FSLS_MAX_BW):** Max. Number of BW units for FS/LS ports. (denominator in 90% calculation) **Power Well:** Core
23:12	0x647 RW	**HS Max BW Units (HS_MAX_BW):** Max. Number of BW units for HS ports. (denominator in 80% calculation) **Power Well:** Core
11:0	0xf42 RW	**SS Max BW Units (SS_MAX_BW):** Max. Number of BW units for SS ports. (denominator in 90% calculation) **Power Well:** Core

51.3.161 Power Scheduler Control-0 (PWR_SCHED_CTRL0)—Offset 8140h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0A019132h

BAR and Offset: [MBAR] + 8140h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0xa RW	**Engine Idle Hysteresis (EIH):** This register controls the min. idle span that has to be observed from the engine idle indicators before the power state flags (xhc_*_idle) will indicate a 1. **Power Well:** Core
23:12	0x19 RW	**Backbone PLL Shutdown Advance Wake (BPSAW):** This register controls the time before the next scheduled transaction where the Backbone PLL request will assert. Register Format: Bits [11:7] # of 125us uframes Bits [6:0] # of microseconds (0-124) **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
11:0	0x132 RW	**Backbone PLL Shutdown Min. Idle Duration (BPSMID):** The sum of this register plus the Backbone PLL Shutdown Advance Wake form to a Total Idle time. When the next scheduled periodic transaction is after present time + Total Idle, the Backbone PLL request will de-assert, allowing the PLL to shutdwon. Register Format: Bits [11:7] # of 125us uframes Bits [6:0] # of microseconds (0-124) **Power Well:** Core

51.3.162 AUX Power Management Control (AUX_CTRL_REG2)—Offset 8154h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 81390206h

BAR and Offset: [MBAR] + 8154h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**DIS_L1P2_EXIT_ON_WAKE_EN:** This bit disables the dependency on Wake Enables defined in PORTSC for L1P2 exit when in D0 **Power Well:** SUS
30:28	0x0 RW	**RESERVED0 (RSVD0):** Reserved. **Power Well:** SUS
27:25	0x0 RW	**RESERVED (RSVD):** Reserved. **Power Well:** SUS
24	0x1 RW	**Enable L1 exit notification to SNPS PCIe core (EN_L1_EXIT_NOTIF_PCIE):** This bit enables a L1 exit notification to SNPS PCIe core. There is a case where USB ports have waked up and AUX PM module has started the wakeup process. The AUX PM control state got into a wait for P0 state because it needs to wait until PCie core to signal powerdown state change. Due to the fact that the core is in D3Hot, there is no run_stop bit set such that no internal interrupt will be fired. This causes the LTSSM of PCIe stayed in L1 even though AUX PM has known that it needs an L1 exit. This bit works together with bit21 of this register. 1: enables this feature 0: disables this feature. **Power Well:** SUS
23	0x0 RW	**DISABLE PLC ON DISCONNECT (DIS_PLC_ON_DISCONNECT):** 1: do not assert PLC for disconnection 0: assert PLC for disconnection **Power Well:** SUS
22	0x0 RW	**TREAT_IDLE_AS_TS2_IN_LTSSM_WAIT_4_TS2:** This bit enables a feature in PCie core LTSSM to treat IDLE received as TS2 when LTSSM is in wait for TS2 receive state. This is a function requested from PHY where it is possible to not able to receive TS2 without error. 1: treat Logic IDLE as TS2 received when in some PCIe LTSSM state. 0: disable this feature. **Power Well:** SUS
21	0x1 RW	**Disable p2 overwrite due to the D3HOT where PCIe core enters the L1 (DIS_P2_OVERWRITE_DUE2_D3HOT):** We added a feature where if PCIe core LTSSM enters L1 due to the D3hot, the aux PM control will not start a P2 overwrite function in anticipating for the next L23 enter. 1: disables p2 overwrite due to the D3HOT where PCIe core enters the L1. 0: enables P2 overwrite even if we are in D3Hot. **Power Well:** SUS
20	0x1 RW	**Enable the port to enter U3 automatically when in U1/U2 (ENABLE_AUTO_U3_ENTRY_FROM_U2_U3):** 1: enables the port to enter U3 automatically when in U1/U2 0: disables the port to enter U3 automatically when in U1/U2 **Power Well:** SUS
19	0x1 RW	**No linkdown reset is issue during low power state (DIS_LINKDOWN_RST_DURING_LOW_POWER):** No linkdown reset is issue during low power state **Power Well:** SUS
18	0x0 RW	**EN_EXIT_DEEP_SLEEP_IF_PCIE_IN_P0:** This bit enables a feature in AUX PM module where if PCIe core LTSSM is in P0 for a duration of time, we will exit the deep sleep state. This is for failure control in case. 1: enables this feature 0: disable this feature **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**U2_EXIT_LFPS_TIMER_VALUE:** This bit selects U2 exit LFPS timer value 0: 320ns 400ns in 25MHz domain 1: 240ns 320ns in 25MHz domain **Power Well:** SUS
16	0x1 RW	**EN_EXIT_DEEP_SLEEP_ON_USB_PORT_WAKEUP:** This bit enables a function that AUX PM module exits from the deep sleep state due to the USB ports wakeup level signal. We have added this feature where USB ports will generated a wakeup level signal to wakeup the AUX PM module if it is in deep sleep state and this level signal will be cleared if the change bits are updated by software. 1: enables this function 0: disables this function which means that a wakeup pulse generated from each USB PortSC event will wake up the AUX PM module from deep sleep if the D3 state is programmed. **Power Well:** SUS
15:14	0x0 RW	**P3_ENTRY_TIMEOUT:** This field defines the timeout value to enter P3 mode in U2. 00: 7us 8us 01: 511us 512us 10: disables the timer (0us) 11: disables the timer (0us) **Power Well:** SUS
13	0x0 RW	**Enable U2 P3 Mode (EN_U2_P3):** 0: Disable U2 P3 mode 1: Enable U2 P3 mode **Power Well:** SUS
12:11	0x0 RW	**Fine Debug Mode Select (FINE_DM_SEL):** Reserved. **Power Well:** SUS
10	0x0 RW	**Enable Low Power State Based Core Clock Gating (EN_LP_CORE_CG):** When set to '1' enable core clock gating based on low power state entered **Power Well:** SUS
9	0x1 RW	**Disable USB3 Port Status Changed Event (DIS_U3_PORT_SCE):** 0: Enable USB3 port status change event generation if any change bit is not cleared 1: Disable USB3 port status change event generation if any change bit is not cleared Bit 12 default 0 **Power Well:** SUS
8:4	0x0 RW	**Debug Mode Select Register (DEB_MODE_SEL):** Reserved. **Power Well:** SUS
3	0x0 RW	**Enable Auto Wakeup Non-IDLE (EN_AWAK_NIDLE):** When set to 1 enables the auto wakeup function when engine has identified non IDLE condition. **Power Well:** SUS
2	0x1 RW	**Enable PM Control P1 Exit P2 (EN_PMC_P1_EXIT_P2):** When set 1 enables the PM control module to transition to P1 instead of P0 when exit P2. **Power Well:** SUS
1	0x1 RW	**Enable PCIe PIPE CLK Isolation (EN_PP_CLK_ISOL):** When set to 1 enables the PCIe PIPE CLK to be isolated when main power is removed. **Power Well:** SUS
0	0x0 RW	**Enable P2 Overwrite P1 Allowed Detect (EN_P2OVRP1_ADET):** When set to 1 enables a function that can detect whether or not enable P2 overwrite P1 function. The condition to get to P2 overwrite is when engine is in idle conditions. This means that there is no ISO EP pending. **Power Well:** SUS

51.3.163 USB2 PHY Power Management Control (USB2_PHY_PMC)—Offset 8164h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000000FCh

BAR and Offset: [MBAR] + 8164h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
7	0x1 RW	**EN_CMDM_TXRXB:** Enable Command Manager Active indication for Tx/Rx Bias circuit HS Phy PM Policy **Power Well:** Core
6	0x1 RW	**EN_TTE_TXRXB:** Enable TTE Active indication for Tx/Rx Bias circuit HS Phy PM Policy **Power Well:** Core
5	0x1 RW	**EN_IDMA_TXRXB:** Enable IDMA Active indication for Tx/Rx Bias circuit HS Phy PM Policy **Power Well:** Core
4	0x1 RW	**EN_ODMA_TXRXB:** Enable ODMA Active indication for Tx/Rx Bias circuit HS Phy PM Policy **Power Well:** Core
3	0x1 RW	**EN_TRM_TXRXB:** Enable Transfer Manager Active indication for Tx/Rx Bias circuit HS Phy PM Policy **Power Well:** Core
2	0x1 RW	**EN_SCH_TXRXB:** Enable Scheduler Active indication for Tx/Rx Bias circuit HS Phy PM Policy **Power Well:** Core
1	0x0 RW	**Enable Rx Bias ckt disable (EN_RXB_CD):** When set enables the Rx bias ckt to be disabled when conditions met (as described by the HS phy PM policy bits) **Power Well:** Core
0	0x0 RW	**Enable Tx Bias ckt disable (EN_TXB_CD):** When set enables the Tx bias ckt to be disabled when conditions met (as described by the HS phy PM policy bits) **Power Well:** Core

51.3.164 USB Power Gating Control (USB_PGC)—Offset 8168h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000282EEh

BAR and Offset: [MBAR] + 8168h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x14177 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
0	0x0 RW	**USB SRAM power gating enable (USB_SRAM_PGE):** When set enables power gating on USB ports. Usage of this bit is further qualified with xHCI SRAM Dynamic Power Gating Disable fuse. If the fuse disables dynamic power gating, setting this bit to 1 shall not enable power gating feature. This bit always returns the value that was written to it irrespective of the setting of xHCI SRAM Dynamic Power Gating Disable fuse. **Power Well:** Core

51.3.165 xHCI Aux Clock Control Register (XHCI_AUX_CCR)—Offset 816Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000400h

BAR and Offset: [MBAR] + 816Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**Reserved (RSVD):** Reserved.
19	0x0 RW	**USB3 Partition Engine/Link trunk gating Enable (PARUSB3_ENG_GEN):** When set to 1 enables gating of the SOSC trunk to the XHCI engine and link in the PARUSB3 partition. **Power Well:** SUS
18	0x0 RW	**USB3 Partition Frame Timer trunk gating Enable (PARUSB3_LINK_GEN):** When set to 1 enables gating of the SOSC trunk to the Frame timer in the PARUSB3 partition. **Power Well:** SUS
17	0x0 RW	**USB2 link partition clock gating enable (PARUSB2_CLK_GEN):** When set to 1 enables gating of the SOSC trunk to the USB2 link and Phy logic in the PARUSB2 partition. **Power Well:** SUS
16	0x0 RW	**USB2/USHIP 12.5 MHz partition clock gating enable (USHIP_PCGEN):** When set to 1 enables gating of the 12.5 MHz SOSC trunk to the USB2 and USHIP logic in the PARUSB2 partition. **Power Well:** SUS
15	0x0 RO	**Reserved1 (RSVD1):** Reserved
14	0x0 RW	**USB3 Port Aux/Core clock gating enable (USB3_AC_CGE):** When set, allows the aux_cclk clock into the USB3 port to be gated when conditions are met. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS
13:12	0x0 RW	**Rx Detect Timer when port Aux Clock is Gated (RX_DT_ACG):** This field defines the value of the timer used to perform Rx Detect when port Aux Clock has been gated. 0x0: 100ms 0x1: 12ms Others: Reserved Note: This timer shall use the Fast Training Timer Tick (about 1us tick) for simulation purposes. For Fast Training mode, the above timeouts will become about 11us and about 100us, +/- implementation uncertainty, respectively. **Power Well:** SUS
11:8	0x4 RW	**U2 Residency Before ModPHY Clock Gating (U2R_BM_CG):** Before gating ModPHY Aux clock, Host Controller shall wait for this time in U2. This time is meant to ensure that the attached device has entered U2 as well. 0x0: 1us 0x1: 128us 0x2: 256us 0x3: 512us 0x4: 640us 0x5: 768us 0x6: 896us 0x7: 1024us Others: Reserved Note: This counter shall start counting once pipe has entered PS3 state in response to link in U2. **Power Well:** SUS
7	0x0 RW	**Frame Timer Clock Gating Ports in U2 Enable (FTCGPU2E):** This bit, when set, allows Host Controller to gate the clock to the Frame Timer when ports are in U2. **Power Well:** SUS
6	0x0 RW	**USB2 port clock throttle enable (USB2_PC_TE):** When set, allows the Aux clock into the USB2 ports to be throttled when conditions allow. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**XHCI Engine Aux clock gating enable (XHCI_AC_GE):** When set, allows the aux clock into the XHCI engine to be gated when idle. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS
4	0x0 RW	**XHCI Aux PM block clock gating enable (XHCI_APMB_CGE):** When set, allows the aux clock into the Aux PM block to be gated when idle. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS
3	0x0 RW	**USB3 Aux Clock Trunk Gating Enable (USB3_AC_TGE):** When set, allows Aux Clock Trunk feeding to USB3.0 ports to be gated when port Aux clock is gated at all USB3.0 ports and all USB3.0 modPHY instances. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS
2	0x0 RW	**USB3 Port Aux/Port clock gating enable (USB3_AP_CGE):** When set, allows the aux_pclk clock into the USB3 port to be gated when conditions are met. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS
1	0x0 RW	**ModPHY port Aux clock gating enable in U2 (MPP_AC_GEU2):** When set, allows the aux clock into the ModPhy to be gated when Link is in U2 and pipe has been in PS3 for at least the time defined by U2 Residency Before ModPHY Clock Gating field. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS
0	0x0 RW	**ModPHY port Aux clock gating enable in Disconnected, U3 or Disabled (MPP_AC_GE_DDU3):** When set, allows the aux clock into the ModPHY to be gated when Link is in Disconnected, U3 or Disabled state. Usage of this bit is further qualified with xHC Dynamic Clock Gating Disable fuse. If the fuse disables dynamic clock gating, Aux clock gating will not be enabled either. This bit always returns the value that was written to it irrespective of the setting of xHC Dynamic Clock Gating Disable fuse. **Power Well:** SUS

51.3.166 USB LPM Parameters (USB_LPM_PARAM)—Offset 8170h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 96090032h

BAR and Offset: [MBAR] + 8170h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x258 RW	**USB2_LPM_REG_RSM_U3_DET_NORM:** Reserved. **Power Well:** Core
21:19	0x1 RW	**Min U3 Exit LFPS Duration (MIN_U3E_LFPS_D):** Min U3 Exit LFPS Duration This field defines the minimum duration of LFPS driven by Host Controller upon U3 exit LFPS handshake. Note that theres an uncertainty of +-16us in actual duration driven by the Host Controller. 0b000: 96us 0b001: 160us 0b010: 224us 0b011: 288us 0b100: 352us 0b101: 416us 0b110: 480us 0b111: 544us **Power Well:** SUS
18:16	0x1 RW	**Min U2 Exit LFPS Duration (MIN_U2_ELFPS_D):** Min U2 Exit LFPS Duration This field defines the minimum duration of LFPS driven by Host Controller upon U2 exit LFPS handshake. Note that theres an uncertainty of +-16us in actual duration driven by the Host Controller. 0b000: 96us 0b001: 160us 0b010: 224us 0b011: 288us 0b100: 352us 0b101: 416us 0b110: 480us 0b111: 544us **Power Well:** SUS
15	0x0 RW	**Max PING LFPS Rx Detection (XHCI_MAX_PING_LFPS):** This field defines the maximum timing for PING LFPS. If an incoming LFPS will be considered a PING if it has a timing such that it is less than or equal to the selected value. Otherwise it will be considered for the other types of LFPS. 0b Max PING LFPS timing set to 256 ns (32 link clocks) 1b Max PING LFPS timing set to 320 ns (40 link clocks) **Power Well:** SUSe
14:10	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
9:0	0x32 RW	**xHCI BESL to HIRD Distance (XHCI_BESL_HIRD_DT):** This field defines the gap between BESL and duration of Resume signalling from Host upon Host Initiated Resume from USB2.0 LPM. Default value of this register corresponds to xHCI spec defined 50us value. Value BESL to HIRD Distance 000h 0us 001h 1us 002h 2us 3FFh 1023us **Power Well:** SUS

51.3.167 xHC Latency Tolerance Parameters - LTV Control (XLTP_LTV1)—Offset 8174h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0040047Dh

BAR and Offset: [MBAR] + 8174h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Disable scheduler direct transition from IDLE to NO requirement (DIS_SDT_IDL_NR):** 0: (default) allow scheduler direct transition from IDLE to NO requirement 1: Disable scheduler direct transition from IDLE to NO requirement **Power Well:** Core
30:26	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
25	0x0 RW	**XHCI LTR Transition Policy (XLTRTP):** When '0', LTR messaging state machine transitions from High, Medium, or Low LTR states to Active state upon the Alarm Timer timout and stays in Active until the next service boundary. When '1', the LTR messaging state machine transitions through High ? Med ? Low ? Active states assuming enough latency is available for each transition. **Power Well:** Core
24	0x0 RW	**XHCI LTR Enable (XLTRE):** This bit must be set to enable LTV messaging from XHCI to the PMC. **Power Well:** Core
23:12	0x400 RW	**Periodic Active LTV (PA_LTV):** 23:22 Latency Scale 00b : Reserved 01b : Latency Value to be multiplied by 1024 10b : Latency Value to be multiplied by 32,768 11b : Latency Value to be multiplied by 1,048,576 21:12 Latency Value (ns) Defaults to 0 micro seconds **Power Well:** Core
11:0	0x47d RW	**USB2 Port L0 LTV (USB2_PL0_LTV):** 11:10 Latency Scale 00b : Reserved 01b : Latency Value to be multiplied by 1024 10b : Latency Value to be multiplied by 32,768 11b : Latency Value to be multiplied by 1,048,576 9:0 Latency Value (ns) Defaults to 128 Micro Seconds **Power Well:** Core

51.3.168 xHC Latency Tolerance Parameters LTV Control 2 (XLTP_LTV2)—Offset 8178h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000017FFh

BAR and Offset: [MBAR] + 8178h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:13	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
12:0	0x17ff RW	**LTV Limit (LTV_LMT):** This register defines a maximum LTR value that is allowed to be advertised to the PMC. This is meant to be used as a workaround or mitigation if issues are discovered with the LTR values generated by the XHC using the defined algorithms. If the LTR value of the XHC is larger than the value in this register field, the value in this field is sent to the PMC instead. Default value is the highest possible - 101b 12:10: Latency Multiplier Field 000b - Value times 1 ns 001b - Value times 32 ns 010b - Value times 1,024 ns 011b - Value times 32,768 ns 100b - Value times 1,048,576 ns 101b - Value times 33,554,432 ns 110b-111b - Not Permitted 9:0: Latency Value Default = 3FFh **Power Well:** Core

51.3.169 xHC Latency Tolerance Parameters - High Idle Time Control (XLTP_HITC)—Offset 817Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 817Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
28:16	0x0 RW	**Minimum High Idle Time (MHIT):** LTR value can be indicated. This value must be larger than HIWL 12:7 - Time value in # of 125 Micro Seconds Bus Intervals (0 - 8ms) 6:0 - Fractional BI Time value in Micro Seconds (0 - 124 Micro Seconds) **Power Well:** Core
15:13	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
12:0	0x0 RW	**High Idle Wake Latency (HIWL):** This is the latency to access memory from the High Idle Latency state. This value must be larger than MIWL and LIWL 12:7 - Time value in # of 125 Micro Seconds Bus Intervals (0 - 8ms) 6:0 - Fractional BI Time value in Micro Seconds (0 - 124 Micro Seconds) **Power Well:** Core

51.3.170 xHC Latency Tolerance Parameters - Medium Idle Time Control (XLTP_MITC)—Offset 8180h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8180h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
28:16	0x0 RW	**Minimum Medium Idle Time (MMIT):** LTR value can be indicated. This value must be larger than MIWL 12:7 - Time value in # of 125 Micro Seconds Bus Intervals (0 - 8ms) 6:0 - Fractional BI Time value in Micro Seconds (0 - 124 Micro Seconds) **Power Well:** Core
15:13	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
12:0	0x0 RW	**Medium Idle Wake Latency (MIWL):** This is the latency to access memory from the Medium Idle Latency state. This value must be larger than LIWL 12:7 - Time value in # of 125 Micro Seconds Bus Intervals (0 - 8ms) 6:0 - Fractional BI Time value in Micro Seconds (0 - 124 Micro Seconds) **Power Well:** Core

51.3.171 xHC Latency Tolerance Parameters Low Idle Time Control (XLTP_LITC)—Offset 8184h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8184h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
28:16	0x0 RW	**Minimum Low Idle Time (MLIT):** LTR value can be indicated. This value must be larger than LIWL 12:7 - Time value in # of 125 Micro Seconds Bus Intervals (0 - 8ms) 6:0 - Fractional BI Time value in Micro Seconds (0 - 124 Micro Seconds) **Power Well:** Core
15:13	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
12:0	0x0 RW	**Low Idle Wake Latency (LIWL):** This is the latency to access memory from the Medium Idle Latency state. 12:7 - Time value in # of 125 Micro Seconds Bus Intervals (0 - 8ms) 6:0 - Fractional BI Time value in Micro Seconds (0 - 124 Micro Seconds) **Power Well:** Core

51.3.172 HOST_CTRL_BW_MAX3_REG—Offset 8188h

Added for CHV

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00F42F42h

BAR and Offset: [MBAR] + 8188h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Rsvd:** Reserved. **Power Well:** Core
23:0	0xf42f42 RW	**MAX_OUT_BW_UNITS_FOR_SS_PORTS:** Max. Number of OUT BW units for SS ports - denominator in 90% calculation **Power Well:** Core

51.3.173 THRM_HOST_CTRL_REG—Offset 819Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 819Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RW	**Rsvd:** Reserved. **Power Well:** Core
20	0x0 RW	**SSIC Thermal Throttle Ux Mapping (SSIC_THRM_UX_MAPPING):** Controls if U1 or U2 is forced upon the start of thermal throttle OFF period. 0 Force ports into U2 during Thermal Throttle triggered Ux entry. 1 Force ports into U1 during Thermal Throttle triggered Ux entry. **Power Well:** Core
19:18	0x0 RW	**USB3 Thermal Throttle Ux LGO delay (USB3_THRM_UX_LGO_DELAY):** Controls the delay enforced between LMP for FLPMA and LMP for Ux LGO. After sending LPMA ON , wait for pre-defined number of clocks to initiate LGO_U1/LGO_U2 00: 8 clocks 01: 32 clocks 10: 128 clocks 11: 0 clocks This field does not apply to ports that are not operating in the mode required to issue FLMA ON. **Power Well:** Core
17	0x0 RW	**THRM_THROTTLING_DISABLE:** 0: Thermal throttling is enabled. 1: Thermal throtling is disabled. The host controller ignores the TT control inputs and does not throttle. **Power Well:** Core
16	0x0 RW	**USB3 Thermal Throttle Ux Mapping (USB3_THRM_UX_MAPPING):** Controls if U1 or U2 is forced upon the start of thermal throttle OFF period. 0 Force ports into U2 during Thermal Throttle triggered Ux entry. 1 Force ports into U1 during Thermal Throttle triggered Ux entry. **Power Well:** Core
15	0x0 RW	**THROTTLE_PRIORITY_MODE:** 0: Off period has priority: In this case, when the throttle signal is asserted, the host controller enters the off state on the next uframe boundary, and stays in the off state for the prescribed duration or until the end of the 16 uframe throttle period whichever occurs first. On subsequent throttle periods, the off period occurs first and then the on period. 1: The On period has priority: In this case, when the throttle signal is asserted, the host controller completes the required On period first before entering the off period. If the required number of uFrames has already been executed in a 16 uframe throttle window, the controller enters the off period immediately. **Power Well:** Core
14	0x0 RW	**DISABLE_FORCE_L1_WHEN_THROTTLED:** 0: USB2 port will not force L1 entry on throttled ports. L1 entry will be based on the normal idle timeout 1: USB2 ports will attempt to enter L1 immediately after throttled ports are idle. **Power Well:** Core
13	0x0 RW	**DISABLE_INTERRUPT_THROTTLING:** 0: Interrupt traffic is throttled 1: Interrupt traffic is not throttled **Power Well:** Core
12	0x0 RW	**DISABLE_ISOCHRONOUS_THROTTLING:** 0: Isochronous traffic is throttled 1: Isochronous traffic is not throttled **Power Well:** Core
11:8	0x0 RW	**T1_ACTION:** # bus intervals to be idle for async traffic out of the 16 interval master period; from 0 to 15. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW	**T2_ACTION:** # bus intervals to be idle for async traffic out of the 16 interval master period; from 0 to 15. **Power Well:** Core
3:0	0x0 RW	**T3_ACTION:** # bus intervals to be idle for async traffic out of the 16 interval master period; from 0 to 15. **Power Well:** Core

51.3.174 THRM_HOST_CTRL_REG2—Offset 81B4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0000000Fh

BAR and Offset: [MBAR] + 81B4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Rsvd:** Reserved. **Power Well:** Core
3:0	0xf RW	**Force LPM Accept Enable (FORCE_LPM_ACCEPT_EN):** Per Port Control to allow for enforcement to be based on device detection if certain devices do not support FLPMA. 0: Do not set FLPMA prior to Ux entry due to TT 1: Set FLPMA prior to Ux entry due to TT **Power Well:** Core

51.3.175 LFPSONCOUNT_REG—Offset 81B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000020C8h

BAR and Offset: [MBAR] + 81B8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Rsvd:** Reserved. **Power Well:** SUS
17:16	0x0 RW	**U2P3 LFPS Periodic Sampling Control (XU2P3LPSC):** This field controls the OFF time for the LFPS periodic sampling for SS and SSIC ports in U2P3. If LFPSPM for a port is 1, it will override the OFF time and LFPS receiver will remain OFF permanently. For Fast Sim mode, 500us will be equivalent to 5us. 0x0 Polling Disable. (RXDET Polling will become 100ms.) 0x1 500us OFF Time 0x2 1ms OFF Time 0x3 1.5ms OFF Time **Power Well:** SUS
15:10	0x8 RW	**XLFPSONCNTSSIC:** This time would describe the number of clocks SSIC LFPS will remain ON. SSIC LFPS detection operation may be carried out on using RTC clock or Oscillator clock. The value of this register should be adjusted accordingly. For RTC recommended value is 2. For Oscillator clock, recommended value is 8. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
9:0	0xc8 RW	**XLFPSONCNTSS:** This time would describe the number of clocks LFPS will remain ON. LFPS detection operation may be carried out on using RTC clock or Oscillator clock. The value of this register should be adjusted accordingly. For RTC recommended value is 2. For Oscillator clock, recommended value is 200. **Power Well:** SUS

51.3.176 reg_D0i2_CTRL_REG_type (D0i2_CTRL_REG)—Offset 81BCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 084204B0h

BAR and Offset: [MBAR] + 81BCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
29:26	0x2 RW	**D0i2 Minimum Residency (D0I2_MIN_RESIDENCY):** This field controls the minimum time that we must stay in D0i2 to ensure that the entry sequence has settled before we attempt to exit. 0h Disabled 1h 8 clocks 2h 16 clocks 3h 32 clocks 4h 128 clocks 5h 256 clocks 6h 512 clocks 7h 1024 clocks **Power Well:** SUS
25:22	0x1 RW	**D0i2 Entry Hysteresis Timer (D0I2_ENTRY_HYSTERESIS_TIMER):** This field allows for a hysteresis timer to be implemented specifically for D0i2. This will allow for D0i2 entry to be controlled independently from the timer used for D0i3 and D3. 0h Disabled 1h 8 clocks 2h 16 clocks 3h 32 clocks 4h 64 clocks 5h 128 clocks 6h 256 clocks 7h 512 clocks **Power Well:** SUS
21	0x0 RW	**Active Periodic EP Disable (ACTIVE_PERIODIC_EP_DISABLE):** This field allows the xHC to control how aggressive it enters D0i2 in the presence of active Periodic EPs. Setting this field will allow D0i2 only when there are no active Periodic EPs on the schedule. Either there are no active DB or any active Interrupt EP is flow controlled. **Power Well:** SUS
20:16	0x2 RW	**MSI D0i2 Pre Wake Time (MSID0I2PWT):** This is the latency that is expected to be incurred to exit the D0i2 state. This wake latency is the latency to be added to the tracked D0i2 wake by the MSI module. Example: If while allowing D0i2 there is an MSI generation that will trigger in 250 us from now ,the MSI module will trigger a D0i2 wake up 250 us MSI D0i2 Pre Wake Time. The D0I2WL is to ensure that the act of D0i2 exit does not impact the action(s) required by the alarm(s) that was enabled prior to D0i2. 3:0 250 ns ticks 0h 0 ns 1h 250 ns . 1Fh 3750 ns **Power Well:** SUS
15:4	0x4b RW	**MSI Idle Threshold (MSI_IDLE_THRESHOLD):** This field allows the xHC to control how aggressive it enters D0i2 in the presence of pending MSI. This field is valid only if Pending MSI Disable is 0, allowing D0i2 in the presence of pending MSIs. D0i2 will be prevented if the amount of idle time between Event Ring being idle to the time an MSI will be generated does not exceed this time. Register Format: Bits [11:7] # of 125us uframes Bits [6:0] # of microseconds (0-124) **Power Well:** SUS
3	0x0 RW	**Pending MSI Disable (PENDING_MSI_DISABLE):** This field allows the xHC to disable D0i2 when there are pending MSIs in the event manager. Setting this field will require all IMOD counters to be 0h and all MSIs delivered. Clearing this field will allow for D0i2 power gating while there are 1 or more IMOD counters decrementing which implies that an MSI is pending and will be generated once the corresponding IMOD counter reaches 0h. **Power Well:** SUS
2	0x0 RW	**Frame Timer Run Disable (FRAME_TIMER_RUN_DISABLE):** This field allows the xHC to disable D0i2 when the frame timer is running. Clearing this field will allow D0i2 when the frame timer is required as defined in the XHCI Spec. Setting this field will not allow D0i2 when the frame timer is required and will limit D0i2 for the condition where the frame timer is not required. **Power Well:** SUS
1	0x0 RW	**USB2 L1 Disable (USB2_L1_DISABLE):** This field allows the xHC to disable D0i2 when USB2 ports are in L1. This implies that D0i2 will only be triggered when ports are in L2 or deeper. **Power Well:** SUS

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RW	**USB3 U2 Disable (USB3_U2_DISABLE):** This field allows the xHC to disable D0i2 when USB3 ports are in U2. This implies that D0i2 will only be triggered when ports are in U3 or deeper. **Power Well:** SUS

51.3.177 reg_D0i2_SCH_ALARM_CTRL_REG_type (D0i2_SCH_ALARM_CTRL_REG)—Offset 81C0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 81C0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** SUS
28:16	0x0 RW	**D0i2 Idle Time (D0I2IT):** This is the minimum schedule idle time that must be available before D0i2 can allowed. 12:7 Time value in # of 125s Bus Intervals (0 8ms) 6:0 Fractional BI Time value in s (0 124s) This field controls how much scheduler idle time is required to trigger D0i2. The scheduler idle time is the same idle time that is used by other functions implementing alarm timers such as PLL shutdown, LTR and USB2 L1 override. If there is a need to require other alarm timers to have been set such as LTR has triggered a Low Idle time, then this field needs to be as aggressive as LTR Low Min Idle Time to ensure D0i2 is triggered once the scheduler has detected IDLE in the schedule. This is only to be used as alternate modes of operation or back up modes. **Power Well:** SUS
15:13	0x0 RO	**Reserved (RSVD1):** Reserved. **Power Well:** SUS
12:0	0x0 RW	**D0i2 Wake Latency (D0I2WL):** This is the latency that is expected to be incurred to exit the D0i2 state. This wake latency is the latency to be added to the tracked D0i2 wake by the scheduler. Example: If while allowing D0i2 there is an alarm that will trigger in 250 us from now , the scheduler will allow D0i2 and track this alarm with an adjustment to wake up 250ns D0I2WL) from. The D0I2WL is to ensure that the act of D0i2 exit does not impact the action(s) required by the alarm(s) that was enabled prior to D0i2. 12:7 Time value in # of 125s Bus Intervals (0 8ms) 6:0 Fractional BI Time value in s (0124s) **Power Well:** SUS

51.3.178 reg_USB2PMCTRL_REG_type (USB2PMCTRL_REG)—Offset 81C4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 81C4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** SUS
11	0x0 RW	**USB2 PHY SUS Power Gate PORTSC Block Policy (U2PSPGPSCBP):** This controls the policy for blocking PORTSC Updates while the USB2 PHY SUS Well is power gated. When set, the controller will block any updates to the PORTSC caused by port status change if the USB2 PHY SUS is power gated. 0 Do not **Power Well:** SUS
10:8	0x0 RW	**USB2 PHY SUS Well Power Gate Entry Hysteresis Count (U2PSPGEHC):** This controls the amount of hysteresis time the controller will enforce after detecting the USB2 PHY SUS Power Gate entry condition. 0h 0 clocks 1h 32 clocks 2h 64 clocks 3h 128 clocks 4h 256 clocks 5h 512 clocks 6h 1024 clocks 7h 2048 clocks **Power Well:** SUS
7:4	0x0 RW	**USB2 PHY SUS Power Gate PORTSC Block Policy (U2CLPGLAT):** This field represents the worst case latency for the USB2 Common Lane to enter and exit its power gate state. This fields is required to be compared to a ports HIRD/HIRD value for the ports that have allowed L1 to L2 mapping to determine if the Common Lane can be allowed to power off. If the power gate entry/exit latency is greater than the HIRD/HIRDD then the common lane should not be allowed to power gate as this will result in a L1 exit violation. 0h 100 us 1h 200 us 2h 300 us Eh 1500us Fh 1600 us **Power Well:** SUS
3:2	0x0 RW	**USB2 PHY SUS Well Power Gate Policy (U2PSUSPGP):** This field controls when to enable the USB2 PHY SUS Well Power Gating when the proper conditions are met. 00 USB2 PHY SUS Power Gating is Disabled. 01 USB2 PHY SUS Power Gating is Enabled in Only D0 and D0i2 (Excludes D0i3 and D3) 10 USB2 PHY SUS Power Gating is Eanabled in only in D0, D0i2 and D0i3 (Excludes D3) 11 USB2 PHY SUS Power Gating is Eanabled in D0/D0i2/D0i3/D3 **Power Well:** SUS
1	0x0 RW	**USB2 Common Lane Power Gating Enable During L1 to L2 Mapping for USB2 PHY Power Gating (U2CLPGEL1L2):** This field when set enables the controller to allow for the common lane power gating to be enabled when all ports are exposed as in L2 to the USB2 PHY while at least 1 port has been mapped to L2 from L1. This field alone does not guarantee power gating since the L1 HIRD/HIRDD Value must be compared with the PHYs power gate exit latency (U2CLPGLAT) held in this register to ensure that L1 exit is not violated. 0 USB2 Common Lane Power Gating is disabled when any port has been mapped from L1 to L2. 1 USB2 Common Lane Power Gating is allowed when any port has been mapped to L2 from L1 with the additional condition that the HIRD/HIRDD is greater than the PHYs Power Gate exit latency. **Power Well:** SUS
0	0x0 RW	**USB2 Data Lane L1 to L2 Mapping Enable for USB2 PHY Power Gating (U2DLL1L2ME):** This field when set enables the controller to map an L1 entry directly to L2 to allow the USB2 PHY to trigger its Autonomous Power Gating. The USB2 PHY will trigger PG only when in L2 since it does not fully understand the requirements for L1. 0 USB2 L1 to L2 mapping is disabled for all ports 1 USB2 L1 to L2 mapping is enabled for all ports **Power Well:** SUS

51.3.179 ECC_PARITY_ERROR_LOG_REG—Offset 83F8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 83F8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**COMMAND_PARITY_DETECTED:** Command Parity Error detected on received IOSF transaction **Power Well:** Core
30	0x0 RW/1C	**DATA_PARITY_DETECTED:** Data Parity Error detected on received IOSF transaction **Power Well:** Core
29	0x0 RW/1C	**ERROR_PRESENT_DETECTED:** Error present detected on received IOSF transaction **Power Well:** Core
28:26	0x0 RO	**RSVD:** Reserved **Power Well:** Core
25:21	0x0 RW/1C	**Correctable ECC Error Source RF (CORRECTABLE_ECC_ERROR_SOURCE_RF):** When set indicates the specific RF the ECC Error was detected on. This is used along with the ECC Source, and Port Info to determine the specific RF on which Correctable ECC Error was seen on. USB2 Port RF: 00000: Reserved 00001: Async. TX Payload 00010: Periodic TX Payload 00011: RX Payload 00100: TTE Periodic TX Payload 00101: TTE RX Payload Others: Reserved USB3 Port RF: 00000: Reserved 00001: Async TX Payload 00010: Periodic TX Payload 00011: RX Payload Others: Reserved XHCI Engine RF: 00000: Reserved 00001: TTE Context 00010: TRM Context 00011: XHCI Completion Collect 00100: Debug Device Completion Collect 00101: DBC-EXI Trace Data **Power Well:** Core
20:15	0x0 RW/1C	**CORRECTABLE_ECC_ERROR_SOURCE_PORT:** When set indicates the Port# if the ECC Error was detected on any of the USB2/USB3 Port RFs. This is valid only when bit[1:0] != 00 **Power Well:** Core
14:13	0x0 RW/1C	**CORRECTABLE_ECC_ERROR_SOURCE_LOG:** When an Correctable ECC is detected for an RF, the corresponding bit is set to '1' 11: Detected Uncorrectable ECC Error on USB3 RFs 10 : Detected Uncorrectable ECC Error on USB2 RFs 01: Detected Uncorrectable ECC Error on XHCI Engine RFs 00 : No Error Note: On detection of first Uncorrectable ECC Error HW shall lock the Correctable log registers (Source, Port, RF) until SW clears the ECC Error log or cleared by reset. **Power Well:** Core
12:8	0x0 RW/1C	**UNCORRECTABLE_ECC_ERROR_SOURCE_RF:** When set indicates the specific RF the ECC Error was detected on. This is used along with the ECC Source, and Port Info to determine the specific RF on which uncorrectable ECC Error was seen on. USB2 Port RF: 00000: Reserved 00001: Async. TX Payload 00010: Periodic TX Payload 00011: RX Payload 00100: TTE Periodic TX Payload 00101: TTE RX Payload Others: Reserved USB3 Port RF: 00000: Reserved 00001: Async TX Payload 00010: Periodic TX Payload 00011: RX Payload Others: Reserved XHCI Engine RF: 00000: Reserved 00001: TTE Context 00010: TRM Context 00011: XHCI Completion Collect 00100: Debug Device Completion Collect 00101: DBC-EXI Trace Data **Power Well:** Core
7:2	0x0 RW/1C	**UNCORRECTABLE_ECC_ERROR_SOURCE_PORT:** When set indicates the Port# if the ECC Error was detected on any of the USB2/USB3 Port RFs. This is valid only when bit[1:0] != 00 **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
1:0	0x0 RW/1C	**UNCORRECTABLE_ECC_ERROR_SOURCE_LOG:** When an uncorrectable ECC is detected for an RF, the corresponding bit is set to '1' 11: Detected Uncorrectable ECC Error on USB3 RFs 10 : Detected Uncorrectable ECC Error on USB2 RFs 01: Detected Uncorrectable ECC Error on XHCI Engine RFs 00 : No Error Note: On detection of first Uncorrectable ECC Error HW shall lock the Uncorrectable log registers (Source, Port, RF) until SW clears the ECC Error log or cleared by reset. **Power Well:** Core

51.3.180 ECC_POISONING_CTRL_REG—Offset 83FCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 83FCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RW	**ENGINE_RF_ECC_POISONING_VECTOR:** XHCI Engine RFs ECC Poisoning Inversion bits for the 64b or 128bit based on RF width **Power Well:** Core
22:14	0x0 RW	**USB3_RF_ECC_POISONING_VECTOR:** USB3 RFs ECC Poisoning Inversion bits for the 64b or 128bit based on RF width **Power Well:** Core
13:5	0x0 RW	**USB2_RF_ECC_POISONING_VECTOR:** USB2 RFs ECC Poisoning Inversion bits for the 64b or 128bit based on RF width **Power Well:** Core
4:3	0x0 RO	**RSVD:** Reserved. **Power Well:** Core
2	0x0 RW	**ENGINE_RF_ECC_POISONING_EN:** Enable ECC Poisoning for XHCI Engine related RFs that support ECC **Power Well:** Core
1	0x0 RW	**USB3_RF_ECC_POISONING_EN:** Enable ECC Poisoning for USB3 Port related RFs that support ECC. Setting this bit enables poisoning of USB3 Port related RFs. This applies to all USB3 ports **Power Well:** Core
0	0x0 RW	**USB2_RF_ECC_POISONING_EN:** Enable ECC Poisoning for USB2 Port related RFs that support ECC. Setting this bit enables poisoning of USB2 Port related RFs. This applies to all USB2 ports **Power Well:** Core

51.3.181 USB2_PORT_STATE_REG—Offset 8400h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [MBAR] + 8400h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:4	0x0 RO	**RSVD:** Reserved. **Power Well:** SUS
3:0	0x0 RO	**USB2_PORT_STATE_REG:** Per USB2 Port State Register indicating the following states 0x0 Connected 0x1 Suspended 0x2 Disabled 0x3 Reserved This register is Read Only and will reflect the state of the ports. Status can change at any time and any usage of this information must be done with care and under specific flows where port state change race conditions are properly handled. **Power Well:** SUS

51.3.182 USB2_PORT_STATE_REG (USB3_PORT_STATE_REG)—Offset 8408h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [MBAR] + 8408h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:4	0x0 RO	**RSVD:** Reserved. **Power Well:** SUS
3:0	0x0 RO	**USB3_PORT_STATE_REG:** Per USB3 Port State Register indicating the following states 0x0 Connected 0x1 Suspended 0x2 Disabled 0x3 Reserved This register is Read Only and will reflect the state of the ports. Status can change at any time and any usage of this information must be done with care and under specific flows where port state change race conditions are properly handled. **Power Well:** SUS

51.3.183 FUS1_REG—Offset 8410h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00010000h

BAR and Offset: [MBAR] + 8410h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**RSVD:** Reserved. **Power Well:** Core
20:18	0x0 RO	**DEV_ID:** Provides a fuse over-ride for the lower 3 bits of device ID. **Power Well:** Core
17	0x0 RO	**XHC_DPGDIS:** When asserted, it indicates that the xHCI will not dynamically power gate the controller. **Power Well:** Core
16	0x1 RO	**USBR_DIS:** When asserted, it indicates that xHCI does not support USBr **Power Well:** Core
15	0x0 RO	**XHC_FXN_DIS:** When asserted, it indicates the xHCI is fused to function disabled. **Power Well:** Core
14:10	0x0 RO	**USB2_PORT_COUNT:** 0x0 = MAX USB2 Ports enabled 0x1 = Max USB2 Ports -1 enabled 0x1F = All ports disabled **Power Well:** Core
9:5	0x0 RO	**USB3_PORT_COUNT:** 0x0 = MAX USB3 Ports enabled 0x1 = Max USB3 Ports -1 enabled 0x1F = All ports disabled **Power Well:** Core
4	0x0 RO	**DEBUG_MODE_ENABLE:** 0 = USB debug mode disabled 1 = USB debug mode enabled Not used for LPT. **Power Well:** Core
3	0x0 RO	**XHC_DCGDIS:** 0= USB3 (xHC) dynamic clock gating enabled 1= USB3 (xHC) dynamic clock gating disabled **Power Well:** Core
2	0x0 RO	**REGFILE_DPGDIS:** 0 = USB3 (xHC) dynamic RF power gating enabled 1 = USB3 (xHC) dynamic RF power gating disabled **Power Well:** Core
1	0x0 RO	**USBIO_PMDIS:** 0=USB2 HW LPM and USB3 HW Ux under xHC enabled 1= USB2 HW LPM and USB3 HW Ux under xHC disabled **Power Well:** Core
0	0x0 RO	**USB2_PLL_SHUTDOWN_DIS:** 0= USB2 PLL Shutdown enabled 1= USB2 PLL Shutdown disabled **Power Well:** Core

51.3.184 FUS2_REG—Offset 8414h

This register is NOT subject to HW save and restore.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8414h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**RSVD:** Reserved. **Power Well:** Core
11:0	0x0 RO	**PORT_MAP_FUS1:** 1:0 Port 1 3:2 Port 2 5:4 Port 3 31:30 Port 16 Bit Description: 00: Port assgned to USB3 01: Port assigned to non-XHCI controller 10: Port assigned to Flex IO mapping. Mapping is based on Soft Straps. 11: Reserved. **Power Well:** SUS

51.3.185 STRAP1_REG—Offset 841Ch

This register is NOT subject to HW save and restore.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 841Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD:** Reserved. **Power Well:** Core
5:0	0x0 RO	**FlexIO mapping (FLEX_IO_MAPPING):** Each bit corresponds to the appropriately numbered USB3 port (zero based) Bit 0 = port 1, bit 1 = port 2 etc. 0: Port is owned by XHCI 1: Port is not owned by XHCI **Power Well:** Core

51.3.186 STRAP2_REG—Offset 8420h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8420h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**RSVD:** Reserved. **Power Well:** Core
5:0	0x0 RO	**USB3_SSIC_MODE:** Each bit corresponds to the appropriately numbered USB3 port (zero based) Bit 0 = port 1, bit 1 = port 2 etc. 0: Port is operated in USB3 mode 1: Port is operated in SSIC mode. **Power Well:** Core

51.3.187 STRAP3_REG—Offset 8424h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8424h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**RSVD:** Reserved. **Power Well:** Core
1:0	0x0 RO	**XHCI_PRI_CLK_FREQ_SEL:** Specifies the frequency of the Primary clock (iosf_prim_mux_clk) used by XHCI 00 : 200 MHz (default) 01 : 125 MHz 10 : 250 MHz **Power Well:** SUS

51.3.188 DFT_REG1—Offset 8430h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8430h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**SS/SSIC DFT CRC (SSDFTCRC):** These register bits contain the value of SS DFT CRC **Power Well:** Core
15:12	0x0 RO	**RSVD0:** RSVD0 **Power Well:** Core
11	0x0 RW	**DFTLFPSSEL:** DFTLFPSSEL 0: Rxelecidle is driven from GPIO Pin 1: Rxelecidle is Driven as specified by Super Speed DFT LFPS Mode Select **Power Well:** Core
10	0x0 RW	**Super Speed DFT LFPS Mode Select (SSDFTLMSEL):** This bit selects the Super Speed DFT LFPS mode, and will only take effect when Super Speed HBP mode is enabled. 0b: HBP logic will internally loopback TX LFPS as RX LFPS and AFE RX LFPS path to the controller is disconnected. 1b: RX LFPS path works normally **Power Well:** Core
9:6	0x0 RW	**SS/SSIC DFT CRC Select (SSDFTCRCSEL):** These bits select which Super Speed DFT CRC value is reflected in SSDFTCRC bits. In addition, these bits also select which SuperSpeed DFT CRC MSB value is sent to GPIO monitor pin, i.e. sata3gp_gp37 to aid silicon debug. Live version of selected CRC's MSB will be- sent to GPIO monitor pin, i.e. sata3gp_gp37. 0h (default): No SuperSpeed DFT CRC is selected. 1h: Data Payload CRC 2h: Link Management Packet CRC 3h: Transaction Packet CRC 4h: Isochronous Timestamp Packet CRC 5h: Data Packet Header CRC 6h: Link Command Packet CRC 7h: RRAP Packet CRC 8h: Tx/Rx Cfg CRC Others: Reserved Note : CRC types 7 and 8 are onlyapplicable if Port is SSIC Port **Power Well:** Core
5	0x0 RO	**RSVD1:** RSVD1 **Power Well:** Core
4:0	0x0 RW	**SS/SSIC DFT CRC Port Select (SSICDFTCPS):** One CRC per packet type is shared for all the Super Speed ports. These bits select the Super Speed port for which CRC data will be updated. 000b: (default) No SuperSpeed Port is selected 001b: SS/SSIC Port 0 010b: SS/SSIC Port 1 011b: SS/SSIC Port 2 100b: SS/SSIC Port 3 101b: SS/SSIC PORT4 110b :SS/SSIC Port 5 others : Rsvd **Power Well:** Core

51.3.189 DFT_REG2—Offset 8434h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8434h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**HS/HSIC TX CRC (TXCRC):** These register bits contain the value of TX CRC. This TX CRC is placed right after the 480MHz XCLKQ. **Power Well:** Core
15:11	0x0 RW	**HSIC/UTMI+ DFT Port Select (UTMIDFTPS):** One CRC is shared for all the UTMI+ ports. These bits select the UTMI+ port for which CRC data will be updated and loopback status reflected in UTMILPBKSTS. 0h: (default) No UTMI+ Port is selected 1h: UTMI+ Port 0 2h: UTMI+ Port 1 3h: UTMI+ Port 2 4h: UTMI+ Port 3 5h: UTMI+ Port 4 6h: UTMI+ Port 5 7h: UTMI+ Port 6 8h: UTMI+ Port 7 9h: UTMI+ Port 8 Ah: UTMI+ Port 9 Bh: UTMI+ Port 10 Ch: UTMI+ Port 11 Dh: UTMI+ Port 12 Eh: UTMI+ Port 13 Others: Reserved **Power Well:** Core
10:7	0x0 RW	**Loop Number (UTMILPBKLOOPN_3_0):** Number of repeatable fixed pattern within a packet Note: Connect register bit 3 to counter bit 7, register bit 2 to counter bit 5, register bit 1 to counter bit 3, register bit 0 to counter bit 1. Counter bits 6, 4, 2 and 0 will be tied off to 0. Hence, the programmable loop number shall be: 0000b: 0 loop 0001b: 2 loops 0010b: 8 loops 0011b: 10 loops 1100b: 160 loops 1101b: 162 loops 1110b: 168 loops 1111b: 170 loops (max) +E27 **Power Well:** Core
6:5	0x0 RW	**Operational Mode (UTMIOPMODE_1_0):** Operational Mode in test mode. These signals select between various operational modes: 00b: Normal Operation 01b: Non-Driving 10b: Disable Bit Stuffing and NRZI encoding 11b: Reserved **Power Well:** Core
4	0x0 RW	**Termination Select (UTMITERMSEL):** Termination Select in test mode. This signal selects between the FS and HS terminations: 0b: HS termination enabled 1b: FS termination enabled **Power Well:** Core
3:2	0x0 RW	**Transceiver Select (UTMIXCVRSELECT_1_0):** Transceiver Select in test mode. This signal selects between the LS, FS and HS transceivers: 00b: HS transceiver enabled 01b: FS transceiver enabled 10b: LS transceiver enabled 11b: Reserved **Power Well:** Core
1:0	0x0 RW	**UTMI+ Loopback Status (UTMILPBKSTS):** Loopback Status for port selected by UTMIDFTPS 00b: Reset condition 01b: Comparator has started receiving data and the received data matches with the TX pattern. 10b: Comparator has started receiving data the received data does not match with the TX pattern but there was no assertion of RC error from UTMI. 11b: Comparator has started receiving data and RX ERROR was asserted for at least one clock by UTMI. Note that this does not reflect the status of pattern comparison since RX error from UTMI is unexpected for loopback. **Power Well:** Core

51.3.190 DFT_REG3—Offset 8438h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8438h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Loopback Pattern (UTMILPBKPAT):** 2-byte pattern for loopback Note: This 2-byte pattern will be replicated to the upper 2-byte to form the DW pattern **Power Well:** Core
15:2	0x0 RW	**Loopback Lane Select (UTMILPBKSEL_13_0):** Port is selected if the corresponding bit is selected Note: MSB is for UTMI+ Port13, LSB is for UTMI+ Port0 **Power Well:** Core
1	0x0 RW	**Loopback Pattern (UTMILPBKPATSEL):** Near end loopback pattern generation type: 0b: Fixed pattern 1b: USB2 test packet **Power Well:** Core
0	0x0 RW	**Loopback Type (UTMILPBKTYPE):** Loopback Type in test mode. This signal selects between DNELB and ANELB, and will only take effect if DTUTMILPBKEN is set. 0b: Digital Near-End Loopback (DNELB) 1b: Analog Near-End Loopback (ANELB) Note: Analog Far-End Loopback (AFELB) is not supported **Power Well:** Core

51.3.191 dft_reg4 (DFT_REG4)—Offset 843Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 843Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:11	0x0 RW	**RSVD:** Reserved. **Power Well:** Core
10:0	0x0 RW	**Loopback Pattern (UTMILPBKPATSEL):** Loopback Lane Select (UTMILPBKSEL): Port is selected if the corresponding bit (zero based) is selected Bit 0 = Port 1 Bit 1 = Port 2 Etc. **Power Well:** Core

51.3.192 dft_reg5 (DFT_REG5)—Offset 8440h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8440h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RW/L	**High Speed Bypass Enable (HIGH_SPEED_BYPASS_ENABLE):** 0000 - Disable all HBP 0001 - Enable SS HBP 0010 - Enable HS HBP 0011 - Enable HSIC HBP 0100 - Enable SSIC HBP Others - Reserved **Power Well:** Core
27	0x0 RW	**DFTIDPINSEL (DFTIDPINSEL):** Select Between Device and Host Controller in HBP mode 0h : Device Controller is selected 1h : Host Controller is selected **Power Well:** Core
26	0x0 RW/O	**Lock Bit (LOCK):** This bit is used by BIOS to lock/unlock lockable bits. When set to '1' the write access to HBP Enable is disabled (locked state). When set to '0', the write access to bit locked are enable (unlocked state). Writable once after platform reset. **Power Well:** Core
25	0x0 RW/L	**Loopback Enable (UTMILPBKEN):** Enable loopback test mode. If asserted, loopback test mode is enabled **Power Well:** Core
24:0	0x0 RO	**Rsvd:** Reserved. **Power Well:** Core

51.3.193 XECP_CMDM_STS0—Offset 8448h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8448h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**IDMA_OWNS_CNTX:** Indicates that IDMA module owns the context access currently **Power Well:** Core
30	0x0 RO	**ODMA_OWNS_CNTX:** Indicates that ODMA module owns the context access currently **Power Well:** Core
29	0x0 RO	**TRM_OWNS_CNTX:** Indicates that TRM modules owns the context access currently **Power Well:** Core
28	0x0 RO	**CMD_RING_REQUESTED_CNTX_LOCK:** Indicates that Command Manager has requested a context lock **Power Well:** Core
27	0x0 RO	**CMD_RING_STOP_IN_PROGRESS:** Indicates that Command Ring stop command is in progress **Power Well:** Core
26	0x0 RO	**SCH_UPDATE_CLR_EP_IN_PROGRESS:** Indicates that clearing an EP out of schedule is in progress **Power Well:** Core
25	0x0 RO	**ADDR_DEV_DONE:** Indicates that current address device command is done by ODMA **Power Well:** Core
24	0x0 RO	**ADDR_DEV_IN_PROGRESS:** Indicates that ODMA has an address device command in progress **Power Well:** Core
23	0x0 RO	**EP_STATE_UPDATE_IN_PROGRESS:** Indicates that updating of EP state is in progress **Power Well:** Core
22	0x0 RO	**EP_STATE_IN_PROGRESS_FROM_STOP_DUE_TO_DB:** Indicates that doorbell manager is issuing and EP update due to a doorbell ring on an EP that is in stop state **Power Well:** Core
21	0x0 RO	**EP_STATE_UPDATE_IN_PROGRESS_DUE_TO_EP_ERROR:** Indicates that transfer ring manager is isuing and EP update due to an EP error condition detected **Power Well:** Core
20	0x0 RO	**EP_STATE_UPDATE_IN_PROGRESS_DUE_TO_STALL:** Indicates that transfere ring manager is issuing an EP state update due to stall received **Power Well:** Core
19	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
18	0x0 RO	**STOP in progress (STOP_IN_PROGRESS):** Indicates that a STOP on the Command Ring is in progress **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**commend ring has doorbell pending (CMD_RING_DB_PENDING):** Indicates that the commend ring has doorbell pending **Power Well:** Core
16	0x0 RO	**commend ring running (CMD_RING_RUNNING):** Indicates that the commend ring is running **Power Well:** Core
15:8	0x0 RO	**Command next capability offset (CMD_NEXT_CAP_OFFSET):** Reserved. **Power Well:** Core
7:0	0x0 RO	**Vendor defined capability ID (VID):** Reserved. **Power Well:** Core

51.3.194 XECP_CMDM_STS2—Offset 8450h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8450h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RO	**Rsvd0:** Reserved. **Power Well:** Core
4:0	0x0 RO	**Event Ring Segment Table (ERST):** count low **Power Well:** Core

51.3.195 XECP_CMDM_STS3—Offset 8454h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8454h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Rsvd0:** Reserved. **Power Well:** Core
15:0	0x0 RO	**Event Ring Segment Table (ERST):** count high **Power Well:** Core

51.3.196 AUX Power PHY Reset (UPORTS_PON_RST_REG)—Offset 8460h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8460h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**RESERVED (RSVD):** Reserved. **Power Well:** Core
3:0	0x0 WO	**Allow Software USB PHY RST (ALL_SW_UP_RST):** Allow a USB PHY reset being issued by software. Writing to this register with bit set to 1 will reset the USB PHY that is connected to the port. Bit3:0 indicates the port number of the USB PHY **Power Well:** SUS

51.3.197 Latency Tolerance Control 0 (HOST_IF_LAT_TOL_CTRL_REG0)—Offset 8464h

The Latency Tolerance Control Register is used by SW to control which BELT is returned when this register is read. SW shall write to this register to program a Slot-ID, Port-ID and BELT Select to determine which BELT is selected. When this register is read the selected BELT is returned.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 8464h

Default: 000D0000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 WO	**BELT Select (BELT_SEL):** This field determines what value will be selected to read back from SW when reading this register 0: Returns the SW programmed Latency Tolerance Value 1: Returns the Lowest BELT in the Host 2: Returns the BELT for the requested Slot-ID (Slot Select) 3: Returns the BELT for the requested Port-ID (Port Select) **Power Well:** Core
29:20	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
19:16	0xd WO	**Port Select (PORT_SEL):** Used to select the BELT for a given Port # when the BELT Select is programmed to select the Port-ID (this field is 0 based) **Power Well:** Core
15:12	0x0 RO	**Rsvd:** Reserved. **Power Well:** Core
11:5	0x0 RO	**BELT Value (BELTV):** Value of selected BELT is return in this field **Power Well:** Core
4:0	0x0 RW	**Slot Select (SLOT_SEL):** Reads will return: BELT Value (BELTV) [4:0]: Value of selected BELT is return in this field Writes will control : Slot Select (): Used to select the BELT for a given Slot # when the BELT Select is programmed to select the Slot-ID (this field is zero based) **Power Well:** Core

51.3.198 USB Legacy Support Capability (USBLEGSUP)—Offset 846Ch

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00002201h

BAR and Offset: [MBAR] + 846Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	Reserved.
24	0x0 RW	**HC OS Owned Semaphore (HCOSOS):** Default = '0'. System software sets this bit to request ownership of the xHC. Ownership is obtained when this bit reads as '1' and the HC BIOS Owned Semaphore bit reads as '0'.
23:17	0x0 RO	Reserved.
16	0x0 RW	**HC BIOS Owned Semaphore (HCBIOSOS):** Default = '0'. The BIOS sets this bit to establish ownership of the xHC. System BIOS will set this bit to a '0' in response to a request for ownership of the xHC by system software.
15:8	0x22 RW/S	**Next Capability Pointer (NextCP):** This field indicates the location of the next capability with respect to the effective address of this capacity. Refer to Table 145 for more information on this field.
7:0	0x1 RW/L	**Capability ID (CID):** This field identifies the extended capability. Refer to Table 146 for the value that identifies the capability as Legacy Support. This extended capability requires one additional 32-bit register for control/status information (USBLEGCTLSTS), and this register is located at offset xECP+04h.

51.3.199 USB2 Port Disable Override (USB2PDO)—Offset 84F8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 84F8h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	Reserved.
13:0	0x0 RW/O	**USB2PDO (USB2PDO):** A '1' in a bit position prevents the corresponding USB 2 port from reporting a Device Connection to the xHC. This applies across all USB2 protocol ports • 0 - Allows corresponding USB port to report a device connection to the xHC. • 1 - Prevents the corresponding USB port from reporting a device Connection to the xHC. Port to bit mapping is in one-hot encoding, this is bit 0 controls port 1 and so on. • Bit 0 - USB 2.0 port 0 • ... • Bit N - USB 2.0 port N

51.3.200 USB3 Port Disable Override (USB3PDO)—Offset 84FCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 84FCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	Reserved.
9:0	0x0 RW/O	**USB3 Port Disable Override (USB3PDO):** • 0 - Allows corresponding USB port to report a Device Connection to the xHC. • 1 - Prevents the corresponding USB port from reporting a Device Connection to the xHC. • Bit 0 - USB 3.0 Port 1 • ... • Bit N - USB 3.0 Port N

51.3.201 Command (CMD_MMIO)—Offset 8604h

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [MBAR] + 8604h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
10	0x0 RW	**Interrupt Disable (ID):** When cleared to 0, the function is capable of generating interrupts. When 1, the function can not generate its interrupt to the interrupt controller. Note that the corresponding Interrupt Status bit is not affected by the interrupt enable. **Power Well:** Core
9	0x0 RO	**Fast Back to Back Enable (FBE):** Reserved. **Power Well:** Core
8	0x0 RW	**SERR# Enable (SERR):** When set to 1, the XHC is capable of generating (internally) SERR#. **Power Well:** Core
7	0x0 RO	**Wait Cycle Control (WCC):** Reserved. **Power Well:** Core
6	0x0 RW	**Parity Error Response (PER):** When set to 1, the XHCI Host Controller will check for correct parity (on its internal interface) and halt operation when bad parity is detected during the data phase as recommended by the XHCI specification. Note that this applies to both requests and completions from the system interface. This bit must be set in order for the parity errors to generate SERR#. **Power Well:** Core
5	0x0 RO	**VGA Palette Snoop (VPS):** Reserved. **Power Well:** Core
4	0x0 RO	**Memory Write Invalidate (MWI):** Reserved. **Power Well:** Core
3	0x0 RO	**Special Cycle Enable (SCE):** Reserved. **Power Well:** Core
2	0x0 RW	**Bus Master Enable (BME):** When set, it allows XHC to act as a bus master. When cleared, it disable XHC from initiating transactions on the system bus. **Power Well:** Core
1	0x0 RW	**Memory Space Enable (MSE):** This bit controls access to the XHC Memory Space registers. If this bit is set, accesses to the XHC registers are enabled. The Base Address register for the XHC should be programmed before this bit is set. **Power Well:** Core
0	0x0 RO	**I/O Space Enable (IOSE):** Reserved as 0. Read-Only. **Power Well:** Core

51.3.202 Device Status (STS_MMIO)—Offset 8606h

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0290h

BAR and Offset: [MBAR] + 8606h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**Detected Parity Error (DPE):** This bit is set by the SoC whenever a parity error is seen on the internal interface to the XHC host controller, regardless of the setting of bit 6 or bit 8 in the Command register or any other conditions. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
14	0x0 RW/1C	**Signaled System Error (SSE):** This bit is set by the SoC whenever it signals SERR# (internally). The SERR_EN bit (bit 8 in the Command Register) must be 1 for this bit to be set. **Power Well:** Core
13	0x0 RW/1C	**Received Master-Abort Status (RMA):** This bit is set when XHC, as a master, receives a master-abort status on a memory access. This is treated as a Host Error and halts the DMA engines. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
12	0x0 RW/1C	**Received Target Abort Status (RTA):** This bit is set when XHC, as a master, receives a target abort status on a memory access. This is treated as a Host Error and halts the DMA engines. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
11	0x0 RW/1C	**Signaled Target-Abort Status (STA):** This bit is used to indicate when the XHC function responds to a cycle with a target abort. **Power Well:** Core
10:9	0x1 RO	**DEVSEL# Timing Status (DEVT):** This 2-bit field defines the timing for DEVSEL# assertion. Read-Only. **Power Well:** Core
8	0x0 RW/1C	**Master Data Parity Error Detected (MDPED):** This bit is set by the SoC whenever a data parity error is detected on a XHC read completion packet on the internal interface to the XHC host controller and bit 6 of the Command register is set to 1. Software clears this bit by writing a 1 to this bit location. **Power Well:** Core
7	0x1 RO	**Fast Back-to-Back Capable (FBBC):** Reserved as 1 Read-Only. **Power Well:** Core
6	0x0 RO	**User Definable Features (UDF):** Reserved as 0. Read-Only. **Power Well:** Core
5	0x0 RO	**66 MHz Capable (MC):** Reserved as 0. Read-Only. **Power Well:** Core
4	0x1 RO	**Capabilities List (CL):** Hardwired to 1 indicating that offset 34h contains a valid capabilities pointer. **Power Well:** Core
3	0x0 RO/V	**Interrupt Status (IS):** This read-only bit reflects the state of this function's interrupt at the input of the enable/disable logic. This bit is a 1 when the interrupt is asserted. This bit will be 0 when the interrupt is deasserted. The value reported in this bit is independent of the value in the Interrupt Enable bit. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
2:0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

51.3.203 Revision ID (RID_MMIO)—Offset 8608h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 8608h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Revision ID (RID):** **Power Well:** Core

51.3.204 Programming Interface (PI_MMIO)—Offset 8609h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 30h

BAR and Offset: [MBAR] + 8609h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x30 RO	**Programming Interface (PI):** A value of 30h indicates that this USB Host Controller conforms to the XHCI specification. **Power Well:** Core

51.3.205 Sub Class Code (SCC_MMIO)—Offset 860Ah

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 03h

BAR and Offset: [MBAR] + 860Ah

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x3 RO	**Sub Class Code (SCC):** A value of 03h indicates that this is a Universal Serial Bus Host Controller. **Power Well:** Core

51.3.206 Base Class Code (BCC_MMIO)—Offset 860Bh

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 0Ch

BAR and Offset: [MBAR] + 860Bh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0xc RO	**Base Class Code (BCC):** A value of 0Ch indicates that this is a Serial Bus controller. **Power Well:** Core

51.3.207 Master Latency Timer (MLT_MMIO)—Offset 860Dh

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 860Dh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Because the XHC controller is internally implemented with arbitration on an internal interface, it does not need a master latency timer. The bits will be fixed at 0. **Power Well:** Core

51.3.208 Header Type (HT_MMIO)—Offset 860Eh

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 860Eh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Multi-Function Bit (MFB):** Read only indicating single function device. **Power Well:** Core
6:0	0x0 RO	**Configuration layout (CL):** Hardwired to 0 to indicate a standard PCI configuration layout. **Power Well:** Core

51.3.209 Memory Base Address (MBAR_MMIO)—Offset 8610h

Value in this register will be different after the enumeration process.

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000004h

BAR and Offset: [MBAR] + 8610h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:16	0x0 RW	**Base Address (BA):** Bits (63:16) correspond to memory address signals (63:16), respectively. This gives 64 KB of relocatable memory space aligned to 64 KB boundaries. **Power Well:** Core
15:4	0x0 RO	**Reserved (RSVD):** Reserved. Read-Only 0, this indicates that this function is requesting an 64KB block of memory. **Power Well:** Core
3	0x0 RO	**Prefetchable:** This bit is hardwired to 0 indicating that this range should not be prefetched. **Power Well:** Core
2:1	0x2 RO	**Type:** If this field is hardwired to 00 it indicates that this range can be mapped anywhere within 32-bit address space. If this field is hardwired to 10 it indicates that this range can be mapped anywhere within 64-bit address space. **Power Well:** Core
0	0x0 RO	**Resource Type Indicator (RTE):** This bit is hardwired to 0 indicating that the base address field in this register maps to memory space **Power Well:** Core

51.3.210 USB Subsystem Vendor ID (SSVID_MMIO)—Offset 862Ch

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [MBAR] + 862Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/L	**USB Subsystem Vendor ID (SSVID):** This register, in combination with the USB Subsystem ID register, enables the operating system to distinguish each subsystem from the others. **Power Well:** Core

51.3.211 USB Subsystem ID (SSID_MMIO)—Offset 862Eh

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [MBAR] + 862Eh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/L	**USB Subsystem ID (SSID):** BIOS sets the value in this register to identify the Subsystem ID. This register, in combination with the Subsystem Vendor ID register, enables the operating system to distinguish each subsystem from other(s). **Power Well:** Core

51.3.212 Capabilities Pointer (CAP_PTR_MMIO)—Offset 8634h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 70h

BAR and Offset: [MBAR] + 8634h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x70 RO	**Capabilities Pointer (CAP_PTR):** This register points to the starting offset of the capabilities ranges. **Power Well:** Core

51.3.213 Interrupt Line (ILINE_MMIO)—Offset 863Ch

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 863Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Line (ILINE):** This data is not used by the SoC. It is used as a scratchpad register to communicate to software the interrupt line that the interrupt pin is connected to. **Power Well:** Core

51.3.214 Interrupt Pin (IPIN_MMIO)—Offset 863Dh

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 863Dh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/L	**Interrupt pin (IPIN):** Bits 7:0 reflect the Interrupt Pin assigned to the host controller by the platform (and are hardwired). **Power Well:** Core

51.3.215 XHC System Bus Configuration 1 (XHCC1_MMIO)—Offset 8640h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000001FDh

BAR and Offset: [MBAR] + 8640h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/O	**Access Control (ACCTRL):** This bit is used by BIOS to lock/unlock lockable bits. When set to '1' the write access to bits locked by this bit is disabled (locked state). When set to '0', the write access to bit locked by this bit is enabled (unlocked state). Writable once after platform reset. **Power Well:** Core
30:25	0x0 RW	**ECO1:** **Power Well:** Core
24	0x0 RW	**Master/Target Abort SERR (RMTASERR):** When set, it allows the out-of-band error reporting from the xHCI Controller to be reported as SERR# (if SERR# reporting is enabled) and thus set the STS.SSE bit. **Power Well:** Core
23	0x0 RW/C	**Unsupported Request Detected (URD):** Set the HW when xHCI Controller received an unsupported request posted cycle. Cleared by SW when the bit is written with value of '1'. **Power Well:** Core
22	0x0 RW	**Unsupported Request Report Enable (URRE):** When set this bit allows the URD bit to be reported as SERR# (if SERR# reporting is enabled) and thus set the STS.SSE bit. **Power Well:** Core
21:19	0x0 RW	**Inactivity Initiated L1 Enable (IIL1E):** If programmed to non-zero, it allows L1 power managed to be enabled after the time-out period specified. 000: Disabled 001: 32 bb_cclk 010: 64 bb_cclk 011: 128 bb_cclk 100: 256 bb_cclk 101: 512 bb_cclk 110: 1024 bb_cclk 111: 131072 bb_cclk **Power Well:** Core
18	0x0 RW	**XHC Initiated L1 Enable (XHCIL1E):** If set, allow the XHC initiated L1 power mangement to be enabled. **Power Well:** Core
17	0x0 RW	**D3 Initiated L1 Enable (D3IL1E):** If set, allow PCI device state D3 initiated L1 power managment to be enables. This bit can only be set if the XHCI L1 Override P2 chicken bit is set. **Power Well:** Core
16:12	0x0 RW	**Periodic Complete Pre Wake Time (PCPWT):** signal . This allows for platform wake time before the next scheduled periodic transaction. The value programmed in this field represents the # of bytes consumed in the current micro-frame which is required to allow for the periodic complete to de-assert. This allows for a programmable time to cause the periodic complete to de-assert prior to the start of the next micro-frame. Register Format: Bits (16:12) represnets the # of bytes remaining with a 256B granularity. Periodic Complete will de-assert if the bytes consumed in the current micro-frame is less **Power Well:** Core
11	0x0 RW	**SW Assisted xHC Idle (SWAXHCI):** This bit being set will indicate xHC idleness (through SW means), which must be a '1' to allow L1 entry, and subsequently allow backbone clock to be gated. This bit is to be set by Intel xHCI driver after checking that the xHCI Controller will stay in idle state for a significant period of time, e.g. all ports disconnected. This bit can be cleared under the following conditions (see SWAXHCI Policy bits in xHC System Bus Configuration 2 register): n SW: SW could write 0 to clear this bit. n HW: HW, under policy control, will clear this bit on an MMIO access to the Host Controller. n HW: HW, under policy control, will clear this bit when HW exits Idle state. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x1 RW	**L23 to Host Reset Acknowledge Wait Count (L23HRAWC):** If programmed to non zero, it allows a wait period after the L23 PHY has shutdown before returning host reset acknowledge to PMC. 000: Disabled 001: 128 bb_cclk 010: 256 bb_cclk 011: 512 bb_cclk 100: 1024 bb_cclk 101: 2048 bb_cclk 110: 4096 bb_cclk 111: 131072 bb_cclk **Power Well:** Core
7:6	0x3 RW	**Upstream Type Arbiter Grant Count Posted (UTAGCP):** Grant count for IOSF upstream L2 request type arbiter for posted type **Power Well:** Core
5:4	0x3 RW	**Upstream Type Arbiter Grant Count Non Posted (UDAGCNP):** Grant count for IOSF upstream L2 type arbiter for non-posted type **Power Well:** Core
3:2	0x3 RW	**Upstream Type Arbiter Grant Count Completion (UDAGCCP) (UDAGCCP):** Grant count for IOSF upstream L2 type arbiter for completion type **Power Well:** Core
1:0	0x1 RW	**Upstream Device Arbiter Grant Count (UDAGC) (UDAGC):** Grant count for IOSF upstream L1 device arbiter **Power Well:** Core

51.3.216 XHC System Bus Configuration 2 (XHCC2_MMIO)—Offset 8644h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0003C000h

BAR and Offset: [MBAR] + 8644h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**OC Configuration Done (OCCFGDONE):** This bit is used by BIOS to prevent spurious switching during OC configuration. It must be set by BIOS after configuration of the OC mapping bits is complete. Once this bit is set, OC mapping shall not be changed by SW. **Power Well:** SUS
30:26	0x0 RW	**ECO1:** **Power Well:** Core
25	0x0 RW	**DMA Request Boundary Crossing Control (DREQBCC):** This bit controls the boundary crossing limit of each Read/Write Request. • 0: 4KB • 1: 64B **Power Well:** Core
24:22	0x0 RW	**IDMA Write Request Size Control (IDMA_WRREQSZCTRL):** Write Request Size Control: This bit controls the maximum size of each Write Request. • 000: 128B • 001: 256B • 011 - 110: Reserved • 111: 64B **Power Well:** Core
21	0x0 RW	**XHC Upstream Read Relaxed Ordering Enable (XHCUPRDROE):** This policy controls the Relaxed Ordering attribute for upstream reads. • 0 - xHC will clear RO for all upstream read requests. • 1 - xHC will set RO for all upstream read requests. **Power Well:** Core
20	0x0 RW	**IOSF Sideband Register Access Disable (IOSFSRAD):** When set, it disables the IOSF sideband interface from accepting any host space register access. **Power Well:** Core
19:14	0xf RW	**Upstream Non-Posted Pre-Allocation (UNPPA):** This field reserves data sizes, in 64 byte chunks, of the downstream completion resource. This value is zero based. 000000 - 111111: Pre-allocate 64 bytes - 4096 bytes If set greater than the default allows over-allocation If set less than default allows under-allocation Only allowed to be programmed when BME = 0 and no outstanding downstream completion **Power Well:** Core
13:12	0x0 RW	**SW Assisted xHC Idle Policy (SWAXHCIP):** Note: Irrespective of the setting of this field, SW write of 0 to SWAXHCI will clear the bit. • 00b (default): xHC HW clears SWAXHCI bit upon: n MMIO access to Host Controller OR n xHC HW exits Idle state • 01b: xHC HW does not autonomously clear SWAXHCI bit. The bit could be cleared only by SW. • 10b: xHC HW clears SWAXHCI upon MMIO acces to Host Controller. xHC HW exit from Idle state will not clear SWAXHCI. • 11b: Reserved **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
11	0x0 RW	**MMIO Read After MMIO Write Delay Disable (RAWDD):** This field controls delay on MMIO Read after MMIO Write. • 0b (Default): Delay MMIO Read after MMIO Write • 1b: Do not delay MMIO Read after MMIO Write ***Note:*** This delay applies after the second of the two DW writes in the case where the IOSF Gasket splits a QW write into two single DW writes to the IP. **Power Well:** Core
10	0x0 RW	**MMIO Write After MMIO Write Delay Enable (WAWDE):** This field controls delay on MMIO Write after previous MMIO Write. • 0b (Default): Do not delay MMIO Write after previous MMIO Write • 1b: Delay MMIO Write after previous MMIO Write ***Note:*** The delay count does not apply on the second of the two DW writes that are generated by IOSF Gasket when it splits a QW write into two. In other words, the second of the two DW writes could happen without any delay with respect to the first DW write. This choice is being made for ease of ECO. The delay count, in this case, will apply after the second of the two DW writes. **Power Well:** Core
9:8	0x0 RW	**SW Assisted Cx Inhibit (SWACXIHB):** This field controls how the DMI L1 inhibit signal from USB3 to PMC will behave. • 00: Never inhibit Cx • 01: Inhibit Cx when Isochronous Endpoint is active (PPT Behavior) • 10: Inhibit Cx when Periodic Active as defined in 40.4.3.2.1 • 11: Always inhibit Cx **Power Well:** Core
7:6	0x0 RW	**SW Assisted DMI L1 Inhibit (SWADMIL1IHB):** This field controls how the DMI L1 inhibit signal from USB3 to DMI will behave. • 00: Never inhibit DMI L1. • 01: Inhibit DMI L1 when Isochronous Endpoint is active (PPT Behavior). • 10: Inhibit DMI L1 when Priodic Active as defined in 40.4.3.2.1. • 11: Inhibit DMI L1 if XHCC1.SWAXHCI = 0. **Power Well:** Core
5:3	0x0 RW	**L1 Force P2 Clock Gating Wait Count (L1FP2CGWC):** If programmed to non zero, it allows L1 force P2 gating off the clock to be delayed after the time-out period specified. If wake up event is detected before the time-out, pclk remains alive and trigger L1 exit as though CPU host is causing the wake, • 000: Disabled • 001: 128 bb_cclk • 010: 256 bb_cclk • 011: 512 bb_cclk • 100: 1024 bb_cclk • 101: 2048 bb_cclk • 110: 4096 bb_cclk • 111: 131072 bb_cclk **Power Well:** Core
2:0	0x0 RW	**Read Request Size Control (RDREQSZCTRL):** Read Request Size Control: This bit controls the maximum size of each Read Request. • 000: 128B • 001: 256B • 010: 512B • 011 - 110: Reserved • 111: 64B **Power Well:** Core

51.3.217 Clock Gating (XHCLKGTEN_MMIO)—Offset 8650h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8650h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**Rsvd2:** Reserved **Power Well:** Core
28	0x0 RW	**Naking USB2.0 EPs for Backbone Clock Gating and PLL Shutdown (NUEFBCGPS):** This field controls whether Naking USB2.0 EPs, once in Naking low priority schedule, should be considered as active for the considerations for backbone clock gating and PLL shutdown or not. 0: Naking USB2.0 EPs are not considered to be active for Backbone Clock Gating and PLL Shutdown evaluation. 1: Naking USB2.0 EPs are considered to be active for Backbone clock gating and PLL shutdown evaluation. **Power Well:** Core
27	0x0 RW	**SRAM Power Gate Enable (SRAMPGTEN):** This register enables the SRAM Power Gating when PLL shutdown conditions for all clock domains have been met 0 - Disallow SRAM Power Gating. 1 - Allow SRAM Power Gating **Power Well:** Core
26	0x0 RW	**SS Link PLL Shutdown Enable (SSLSE):** This register enables the SS P3 state to be exposed to PXP PLL Shutdown conditions on behalf of all USB SS Ports ontop of trunk clock gating. 0 - P3 state NOT allowed to result in PXP PLL shutdown. 1- P3 state allowed to result in PXP PLL shutdown **Power Well:** Core
25	0x0 RW	**USB2 PLL Shutdown Enable (USB2PLLSE):** When set, this bit allows USB2 PLL to be shutdown when HS Link trunk clock is gated, and xHC can tolerate PLL spin up time for subsequent clock request. Note: if USB2 PLL Shutdown Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. **Power Well:** Core
24	0x0 RW	**IOSF Sideband Trunk Clock Gating Enable (IOSFSTCGE):** When set, this bit allows the IOSF sideband clock trunk to be gated when idle conditions are met. **Power Well:** Core
23:20	0x0 RW	**HS Backbone PXP Trunk Clock Gate Enable (HSTCGE):** This register determines the HS Ux state(s) which will be exposed to Backbone PXP trunk gating of core clock. Uy is a state allowed to result in trunk gating when ss_tcg_ux_en(x) is asserted. (0) ==) U0 or deeper (1) ==) NA (no support for U1) (2) ==) U2 (L1) or deeper (3) ==) U3 (L2) or deeper **Power Well:** Core
19:16	0x0 RW	**SS Backbone PXP Trunk Clock Gate Enable (SSTCGE):** This register determines the SS Ux state(s) which will be exposed to Backbone PXP trunk gating of core clock. Uy is a state allowed to result in trunk gating when ss_tcg_ux_en(x) is asserted. (0) ==) U0 or deeper (1) ==) U1 or deeper (2) ==) U2 or deeper (3) ==) U3 or deeper **Power Well:** Core
15	0x0 RW	**XHC Ignore_EU3S (XHCIGEU3S):** This register determines if the xHC will use the EU3S as a condition to allow for Frame timer gating. 0 - xHC may allow frame timer to be gated when EU3S is set and all ports are in the required state. 1 - xHC may allow frame timer to be gated regardless of EU3S. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
14	0x0 RW	**XHC Frame Timer Clock Shutdown Enable (XHCFTCLKSE):** This register determines if the xHC will allow the frame timer clock to be gated. 0 - xHC will not allow ICC PLL 96MHz output to be shutdown thus keeping the frame timer running. 1 - xHC will allow ICC PLL 96MHz output to be shutdown under specific conditions. **Power Well:** Core
13	0x0 RW	**XHC Backbone PXP Trunk Clock Gate In Presence of ISOCH EP (XHCBBTCGIPISO):** This register controls the policy on allowing Backbone PXP trunk clock gate in the presence of IDLE ISOCH EP s with active DB. Allows the periodic active to be used in enabling Backbone PXP trunk clock gating of core clock. 0 Trunk gate of core clock is not allowed when ISOCH EP DB is set and ISOCH EP s are idle. 1 Allow trunk gate of core clock when ISOCH EP DB is set and ISOCH EP s are idle. **Power Well:** Core
12	0x0 RW	**XHC HS Backbone PXP Trunk Clock Gate U2 non RWE (XHCHSTCGU2NRWE):** This register controls the policy on allowing Backbone PXP trunk gating of core clock when there is atleast 1 non Remote Wake Enabled HS Port in U2. 0 Prevent trunk gate of core clock when a non RWE HS Port is in U2. 1 Allow trunk gate of core clock when a non RWE HS Port is in U2. **Power Well:** Core
11:10	0x0 RW	**XHC USB2 PLL Shutdown Lx Enable (XHCUSB2PLLSDLE):** This register determines the HS Link state(s) which will be exposed to USB2 PLL Shutdown conditions on behalf of all USB2 HS Ports. Ly is a state allowed to result in USB2 PLL Shutdown when en(x) is asserted. (0) ==) L1 or deeper (1) ==) L2 or deeper **Power Well:** Core
9:8	0x0 RW	**HS Backbone PXP PLL Shutdown Ux Enable (HSUXDMIPLLSE):** This register determines the Ux state(s) which will be exposed to PXP PLL Shutdown conditions. PLL Shutdown is allowed in: 00b Disabled (Link states shall be disabled for DMI PLL shutdown) 01b U0 or conditions for 10b setting. 10b U2 or conditions for 11b setting. 10b U3, Disconnected, Disabled or Powered-Off. **Power Well:** Core
7:5	0x0 RW	**SS Backbone PXP PLL Shutdown Ux Enable (SSPLLSUE):** This register determines the Ux state(s) which will be exposed to DMI PLL Shutdown conditions. PLL Shutdown is allowed in: 000b Disabled (Link states shall be ignored for DMI PLL shutdown). 001b U0 or conditions for 010b setting 010b U1 or conditions for 011b setting 011b U2 or conditions for 100b setting 100b U3, Disconnected, Disabled or Powered-Off **Power Well:** Core
4	0x0 RW	**XHC Backbone Local Clock Gating Enable (XHCBLCGE):** When set, this bit allows XHCI Controller IP backbone clock to be locally gated when idle conditions are met. Note: if XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. **Power Well:** Core
3	0x0 RW	**HS Link Trunk Clock Gating Enable (HSLTCGE):** When set, this bit allows High Speed Link control's 480 MHz and its 48/60 MHz link clock trunk to be gated when idle conditions are met. Note: if XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. BIOS need to query fuses to see if HW is enabled. **Power Well:** Core
2	0x0 RW	**SS Link Trunk Clock Gating Enable (SSLTCGE):** When set, this bit allows the SuperSpeed Link control's 250 MHz and its divided 125 MHz link clock trunk to ge gated when idle conditions are met. Note: if XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. BIOS need to query fuses to see if HW is enabled. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW	**IOSF Backbone Trunk Clock Gating Enable (IOSFBTCGE):** When set, this bit allows the IOSF backbone clock trunk to be gated when idle conditions are met. **Power Well:** Core
0	0x0 RW	**IOSF Gasket Backbone Local Clock Gating Enable (IOSFBLCGE):** When set, this bit allows the IOSF Gasket backbone clock to be locally gated when idle conditions are met. Note: if XHC Dynamic Clock Gating Disable Fuse is '1', hardware will always see '0' as an output from this register. BIOS reading this register should always return the correct value. BIOS need to query fuses to see if HW is enabled. **Power Well:** Core

51.3.218 Audio Time Synchronization (AUDSYNC_MMIO)—Offset 8658h

This 32 bit register is used for audio stream synchronization across different devices. Global signal sample_now captures a value in AUDSYNC register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 8658h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Rsvd2:** Reserved. **Power Well:** Core
29:16	0x0 RO/V	**Captured Frame List Current Index/Frame Number (CMFI):** The value in this register is updated in response to sample_now signal. Bits (29:16) reflect state of bits (13:0) of FRINDEX **Power Well:** Core
15:13	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
12:0	0x0 RO/V	**Captured Micro-frame BLIF (CMFB):** The value is updated in response to sample_now signal and provides information about offset within micro-frame. Captured value represents number of 8 high-speed bit time units from start of micro-frame. At the beginning of micro-frame captured value will be 0 and increase to maximum value at the end. Default maximum value is 7499 but it may be changed as result of adjustment done in FLA. **Power Well:** Core

51.3.219 Serial Bus Release Number (SBRN_MMIO)—Offset 8660h

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [MBAR] + 8660h

Default: 30h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x30 RO	**Serial Bus Release Number (SBRN):** A value of 30h indicates that this controller follows USB release 3.0. **Power Well:** SUS

51.3.220 Frame Length Adjustment (FLADJ_MMIO)—Offset 8661h

This feature is used to adjust any offset from the clock source that generates the clock that drives the SOF counter. When a new value is written into these six bits, the length of the frame is adjusted. Its initial programmed value is system dependent based on the accuracy of hardware USB clock and is initialized by system BIOS. This register should only be modified when the HChalted bit in the USBSTS register is a one. Changing value of this register while the host controller is operating yields undefined results.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 60h

BAR and Offset: [MBAR] + 8661h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD):** . **Power Well:** SUS
6	0x1 RO	**No Frame Length Timing Capability (NO_FRAME_LENGTH_TIMING_CAP):** This flag is set to 1 to indicate that the host controller does not support a programmable Frame Length Timing Value field. **Power Well:** Core
5:0	0x20 RO	**Frame Length Timing Value (FLTV):** SOF micro-frame length) is equal to 59488 + value in this field. The default value is decimal 32 (20h), which gives a SOF cycle time of 60000. Frame Length (number of High Speed bit times) FLADJ Value (decimal) (decimal) 59488 0 (00h) 59504 1 (01h) 59520 2 (02h) ... 59984 31 (1Fh) 60000 32 (20h) ... 60480 62 (3Eh) 60496 63 (3Fh) Each decimal value change to this register corresponds to 16 high-speed bit times. The SOF cycle time (number of SOF counter clock periods to generate a SOF micro-frame length) is equal to 59488 + value in this field. The default value is decimal 32 (20h), which gives a SOF cycle time of 60000. Frame Length (# High Speed bit times) FLADJ Value **Power Well:** SUS

51.3.221 Best Effort Service Latency (BESL_MMIO)—Offset 8662h

Bset Effort Service Latency.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 8662h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RW/L	**Default Best Effort Service Latency Deep (DBESLD):** Default Best Effort Service Latency (DBESLD) If the value of this field is non-zero, it defines the recommended value for programming the PORTPMSC register BESLD field. This is programmed by BIOS based on platform parameters. **Power Well:** Core
3:0	0x0 RW/L	**Default Best Effort Service Latency (DBESL):** If the value of this field is non-zero, it defines the recommended value for programming the PORTPMSC register BESL field. This is programmed by BIOS based on platform parameters. **Power Well:** Core

51.3.222 PCI Power Management Capability ID (PM_CID_MMIO)—Offset 8670h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 01h

BAR and Offset: [MBAR] + 8670h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RO	**PCI Power Management Capability ID (PM_CID):** A value of 01h indicates that this is a PCI Power Management capabilities field. **Power Well:** Core

51.3.223 Next Item Pointer #1 (PM_NEXT_MMIO)—Offset 8671h

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 80h

BAR and Offset: [MBAR] + 8671h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x80 RW/L	**Next Item Pointer #1 (PM_NEXT):** This register defaults to 80h, which indicates that the next capability registers begin at configuration offset 80h. This register is writable when the Access Control bit is set to '0'. This allows BIOS to effectively hide the next capability registers, if necessary. This register should only be written during system initialization before the plug-and-play software has enabled any master-initiated traffic. Values of: 80h implies next capability is MSI 00h implies that MSI capability is hidden. Note: This value is never expected to be programmed. **Power Well:** Core

51.3.224 Power Management Capabilities (PM_CAP_MMIO)—Offset 8672h

Normally, this register is read-only to report capabilities to the power management software. In order to report different power management capabilities depending on the system in which the SoC is used, the write access to this register is controlled by the Access Control bit (ACCTRL). The value written to this register does not affect the hardware other than changing the value returned during a read. This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [MBAR] + 8672h

Default: C1C2h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x18 RW/L	**PME_Support:** This 5-bit field indicates the power states in which the function may assert PME#. The SoC XHC does not support the D1 or D2 states. For all other states, the SoC XHC is capable of generating PME#. Software should never need to modify this field. **Power Well:** Core
10	0x0 RW/L	**D2_Support:** The D2 state is not supported. **Power Well:** Core
9	0x0 RW/L	**D1_Support:** The D1 state is not supported. **Power Well:** Core
8:6	0x7 RW/L	**Aux_Current:** The SoC XHC reports 375mA maximum Suspend well current required when in the D3cold state. This value can be written by BIOS when a more accurate value is known. **Power Well:** Core
5	0x0 RW/L	**DSI:** The SoC reports 0, indicating that no device-specific initialization is required. **Power Well:** Core
4	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
3	0x0 RW/L	**PME Clock (PMEClock):** The SoC reports 0, indicating that no PCI clock is required to generate PME#. **Power Well:** Core
2:0	0x2 RW/L	**Version:** The SoC reports 010, indicating that it complies with Revision 1.1 of the PCI Power Management Specification. **Power Well:** Core

51.3.225 Power Management Control/Status (PM_CS_MMIO)—Offset 8674h

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0008h

BAR and Offset: [MBAR] + 8674h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**PME_Status:** This bit is set when the SoC XHC would normally assert the PME# signal independent of the state of the PME_En bit. Writing a 1 to this bit will clear it and cause the internal PME to deassert (if enabled). Writing a 0 has no effect. This bit must be explicitly cleared by the operating system each time the operating system is loaded. **Power Well:** SUS
14:13	0x0 RO	**Data_Scale:** The SoC hardwires these bits to 00 because it does not support the associated Data register. **Power Well:** Core
12:9	0x0 RO	**Data_Select:** The SoC hardwires these bits to 0000 because it does not support the associated Data register. **Power Well:** Core
8	0x0 RW	**PME_En:** A 1 enables the SoC XHC to generate an internal PME signal when PME_Status is 1. This bit must be explicitly cleared by the operating system each time it is initially loaded. **Power Well:** SUS
7:4	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
3	0x1 RO	**No Soft Reset (NSR):**), this bit indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. Configuration Context is preserved. Upon transition from the D3hot to the D0 Initialized state, no additional operating system intervention is required to preserve Configuration Context beyond writing the PowerState bits. Transition from D3hot to D0 by a system or bus segment reset will return to the device state D0 Uninitialized with only PME context preserved if PME is supported and enabled. **Power Well:** Core
2	0x0 RO	**Reserved (RSVD2):** Reserved. **Power Well:** Core
1:0	0x0 RW	**PowerState:** This 2-bit field is used both to determine the current power state of XHC function and to set a new power state. The definition of the field values are: 00b - D0 state 11b - D3hot state If software attempts to write a value of 10b or 01b in to this field, the write operation must complete normally, however, the data is discarded and no state change occurs. When in the D3hot state, the SoC must not accept accesses to the XHC memory range, but the configuration space must still be accessible. **Power Well:** Core

51.3.226 Message Signaled Interrupt CID (MSI_CID_MMIO)—Offset 8680h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 05h

BAR and Offset: [MBAR] + 8680h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x5 RO	**Capability ID (CID):** Indicates that this is an MSI capability **Power Well:** Core

51.3.227 Next item pointer (MSI_NEXT_MMIO)—Offset 8681h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MBAR] + 8681h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Next Pointer (NEXT):** Indicates that this is the last item on the capability list **Power Well:** Core

51.3.228 Message Signaled Interrupt Message Control (MSI_MCTL_MMIO)—Offset 8682h

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0086h

BAR and Offset: [MBAR] + 8682h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RO	**Per-Vector Masking Capable (PVM):** Specifies whether controller supports MSI per vector masking. Not supported **Power Well:** Core
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages. This device is 64-bit capable. **Power Well:** Core
6:4	0x0 RW	**Multiple Message Enable (MME):** Indicates the number of messages the controller should assert. This device supports multiple message MSI. **Power Well:** Core
3:1	0x3 RO	**Multiple Message Capable (MMC):** Indicates the number of messages the controller wishes to assert. This field must be set by HW to reflect the number of Interrupters supported. Encoding number of Vectors requested (number of Interrupters) 000 1 001 2 010 4 011 8 100 16 101 32 110-111 Reserved **Power Well:** Core
0	0x0 RW	**MSI Enable (MSIE):** If set to 1, MSI is enabled and the traditional interrupt pins are not used to generate interrupts. If cleared to 0, MSI operation is disabled and the traditional interrupt pins are used. **Power Well:** Core

51.3.229 Message Signaled Interrupt Message Address (MSI_MAD_MMIO)—Offset 8684h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8684h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Addr:** Lower DW of system specified message address, always DWORD aligned **Power Well:** Core
1:0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

51.3.230 Message Signaled Interrupt Upper Address (MSI_MUAD_MMIO)—Offset 8688h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8688h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Addr (UpperAddr):** Upper DW of system specified message address. **Power Well:** Core

51.3.231 Message Signaled Interrupt Message Data (MSI_MD_MMIO)—Offset 868Ch

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [MBAR] + 868Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data:** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the lower word (PCI AD(15:0)) during the data phase of the MSI memory write transaction. The Multiple Message Enable field (bits 6-4 of the Message Control register) defines the number of low order message data bits the function is permitted to modify to generate its system software allocated vectors. For example, a Multiple Message Enable encoding of 010 indicates the function has been allocated four vectors and is permitted to modify message data bits 1 and 0 (a function modifies the lower message data bits to generate the allocated number of vectors). If the Multiple Message Enable field is 000, the function is not permitted to modify the message data. **Power Well:** Core

51.3.232 Device Idle Capability (DEVIDLE_MMIO)—Offset 8690h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: F0140009h

BAR and Offset: [MBAR] + 8690h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0xf RO	**VID:** Reserved. **Power Well:** Core
27:24	0x0 RO	**REV:** Reserved. **Power Well:** Core
23:16	0x14 RO	**Length (LENGTH):** Indicates that this capability is 16 bytes long. **Power Well:** Core
15:8	0x0 RO	**Next Capability Pointer (NCP):** This field contains the offset to the next PCI Capability structure or 000h if no other items exist in the linked list of Capabilities. **Power Well:** Core
7:0	0x9 RO	**Capability ID (CID):** Reserved. **Power Well:** Core

51.3.233 Vendor Specific Header (VSHDR_MMIO)—Offset 8694h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 01400010h

BAR and Offset: [MBAR] + 8694h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x14 RO	**VSEC Length (VSEC_LENGTH):** This field indicates the number of bytes in the entire VSEC structure, including the PCI Extended Capability header, the Vendor- Specific header, and the Vendor-Specific register **Power Well:** Core
19:16	0x0 RO	**VSEC Rev (VSEC_REV):** This field is a vendor-defined version number that indicates the version of the VSEC structure. Software must qualify the Vendor ID and VSEC ID before interpreting this field. **Power Well:** Core
15:0	0x10 RO	**VSEC ID (VSEC_ID):** This field is a vendor-defined ID number that indicates the nature and format of the VSEC structure. Software must qualify the Vendor ID before interpreting this field. **Power Well:** Core

51.3.234 SW LTR POINTER (SWLTRPTR_MMIO)—Offset 8698h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8698h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**SW LTR Update MMIO Offset Location (SW_LTR_UPDT_MMIO_OFFSET):** This register contains the location pointer to the SW LTR register in MMIO space, as an offset from the specified BAR. The value of this register is a dont care, if the Valid bit is not set. **Power Well:** Core
3:1	0x0 RO	**Base Address Register Number (BARNUM):** Contains the 0s based AR Number of the BAR which contains the location of the SW LTR MMIO register. When counting BAR Numbers, all BARs, regardless of size and type, consume one BAR Number. Bar 0 is the 1st BAR. The value of this register is a dont care, if the Valid bit is not set. **Power Well:** Core
0	0x0 RO	**Valid (VALID):** Set to 1 to indicate that the function has implemented a SW LTR register as specified in the DevIdle that can be located using the SWLTRLOC register and BARNUM. Set to 0 to indicate that the function has not implemented a SW LTR register that is compliant to the DevIdle definition. This could be because the function has not implemented SW LTR at all, or has a device specific version of SW LTR. **Power Well:** Core

51.3.235 Device Idle Pointer Register (DEVIDLEPTR_MMIO)—Offset 869Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00080AC1h

BAR and Offset: [MBAR] + 869Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x80ac RW/L	**DevIdle MMIO Offset Location (DEVIDLELOC):** This register contains the location pointer to the DevIdle register in MMIO space, as an offset from the specified BAR. The value of this register is a dont care, if the Valid bit is not set. **Power Well:** Core
3:1	0x0 RO	**Base Address Register Number (BARNUM):** Contains the 0s based BAR Number of the BAR which contains the location of the DevIdle MMIO register. When counting BAR Numbers, all BARs, regardless of size and type, consume one BAR Number. Bar 0 is the 1st BAR. The value of this register is a dont care, if the Valid bit is not set. **Power Well:** Core
0	0x1 RW/L	**Valid (VALID):** Set to 1 to indicate that the function has implemented a DevIdle register as specified in the DevIdle that can be located using the DEVIDLELOC register and BARNUM. Set to 0 to indicate that the function has not implemented a DevIdle register that is compliant to the DevIdle definition. This could be because the function has not implemented DevIdle at all, or has a device specific version of DevIdle. **Power Well:** Core

51.3.236 Device Idle Power ON Latency (DEVIDLEPOL_MMIO)—Offset 86A0h

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0800h

BAR and Offset: [MBAR] + 86A0h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
12:10	0x2 RW/L	**Power On Latency Scale (POLS):** Latency Scale multiplier: 010: 1us 011: 32us All other settings are reserved. The value of this register is multiplied with the Power On Latency Value (POLV) to provide the DevIdle power on exit latency multiplier scale from 1us to 32ms. This register is defined to be RWO (read-write-once) to allow BIOS to set the initial value. This register is undefined if the DevIdle.Valid bit is 0. **Power Well:** Core
9:0	0x0 RW/L	**Power On Latency Value (POLV):** 10-bit value that is multiplied by the Power On Latency Scale. A value of 0 indicates a power on latency of less than 1us. This register is defined to be RWO (read-write-once) to allow BIOS to set the initial value. This register is undefined if the DevIdle.Valid bit is 0. **Power Well:** Core

51.3.237 High Speed Configuration 2 (HSCFG2_MMIO)—Offset 86A4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00002000h

BAR and Offset: [MBAR] + 86A4h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Rsvd1:** Reserved. **Power Well:** Core
18	0x0 RW	**PORT1_HOST_MODE_OVERRIDE:** When set, this bit causes the Host_Device mux on port 1 to be forced into the Host mode. **Power Well:** Core
17:16	0x0 RW	**eUSB2SEL:** The two bits are associate with USB2 ports 1 - bit 16 and 2 - bit 2 0: Port is mapped to USB2 1: Port is mapped to eUSB2 **Power Well:** Core
15	0x0 RW	**HS ASYNC Active IN Mask (HSAAIM):** Determines if the Async Active will mask/ignore IN EP s. 0 HS ASYNC Active will include IN EP s. 1 HS ASYNC Active will mask/ignore IN EP s. **Power Well:** Core
14	0x0 RW	**HS OUT ASYNC Active Polling EP Mask (HSOAAPEPM):** Determines if the Async Active for OUT HS/FS/LS masks/ignores EP s that are polling/PINGing (HS) due to NAK. 0 HS OUT ASYNC Active will include EP s that are polling. 1 HS OUT ASYNC Active will mask/ignore EP s that are polling. **Power Well:** Core
13	0x1 RW	**HS IN ASYNC Active Polling EP Mask (HSIAAPEPM):** Determines if the Async Active for IN HS/FS/LS masks/ignores EP s that are polling due to NAK. 0 HS IN ASYNC Active will include EP s that are polling. 1 HS IN ASYNC Active will mask/ignore EP s that are polling. **Power Well:** Core
12:11	0x0 RW	**HS INTR IN Periodic Active Policy Control (HSIIPAPC):** Controls how the HS INTR IN periodic active is used to generate the global periodic active. This will determine how the smallest service interval among active EP s and number of active EP s are used. 0 HS INTR IN periodic active will be used to generate periodic active if Service Interval Threshold OR Numb of EP Threshold values meet the requirement. 1 HS INTR IN periodic active will be used to generate periodic active if Service Interval Threshold AND Numb of EP Threshold values meet the requirement. 2 Always allow HS INTR EP s to be used in the generation of the global Periodic Active indication. 3 Never allow HS INTR EP s to be used in the generation of the global Periodic Active indicaiton **Power Well:** Core
10:4	0x0 RW	**HS INTR IN Periodic Active Num of EP Threshold (HSIIPANEPT):** Defines the threshold used to determine if Periodic Acive may include HS/FS/LS INTR IN EP active indication. If there are more than NumEPThreshold active HS/FS/LS INTR EP s then they may be included as part of the periodic active generation. **Power Well:** Core
3:0	0x0 RW	**HS INTR IN Periodic Active Service Interval Threshold (HSIIPASIT):** Defines the Service Interval threshold used to determine if Periodic Acive will include HS/FS/LS INTR IN EP active indication. If there are any active HS/FS/LS INTR EP s with a service interval less than or equal to this threshold then they may be included as part of the periodic active generation. **Power Well:** Core

51.3.238 XHCI USB2 Overcurrent Pin Mapping 1 (U2OCM1_MMIO)—Offset 86B0h

The RW/L property of this register is controlled by OCCFDONE bit.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 86B0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Rsvd:** Reserved **Power Well:** SUS
3:0	0x0 RW/L	**OC Mapping (OCM):** • 0 - port 0 • 1 - port 1 • 2 - port 2 • 3 - port 3 • Others: Reserved **Power Well:** SUS

51.3.239 XHCI USB3 Overcurrent Pin Mapping 1 (U3OCM1_MMIO)—Offset 86D0h

The RW/L property of this register is controlled by OCCFDONE bit.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 86D0h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Rsvd:** Reserved. **Power Well:** Core
3:0	0x0 RW/L	**OC Mapping (OCM):** • 0 - port 0 • 1 - port 1 • 2 - port 2 • 3 - port 3 • Others: Reserved **Power Well:** SUS

51.3.240 XHCC3 (XHCC3_MMIO)—Offset 86FCh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000002h

BAR and Offset: [MBAR] + 86FCh

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (Rsvd1):** Reserved **Power Well:** SUS
3	0x0 RW	**Error Handling : Disable Command Parity Check (DISABLE_COMMAND_PARITY_CHECK):** When set to 1, XHCI Host Controller disables checking of Command Parity on command received as a target on its IOSF Primary interface **Power Well:** SUS
2	0x0 RW	**Error Handling : Disable Data Parity Check (DISABLE_DATA_PARITY_CHECK):** When set to 1, XHCI Host Controller disables checking of Data Parity on data received as a target on its IOSF Primary interface **Power Well:** SUS
1	0x1 RW	**Error Handling : Enable ECC Error Response (ENABLE_ECC_ERROR_RESPONSE):** When set to 1, XHCI Host Controller will check for ECC on RFs (that support ECC) and halt operation when uncorrectable ECC is detected **Power Well:** SUS
0	0x0 RW/L	**Function Disable (FXN_DISABLE):** When set will disable the xHC from being operational. **Power Well:** SUS

51.3.241 Debug Capability ID Register (DCID)—Offset 8700h

This register is modified and maintained by BIOS

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 0005000Ah

BAR and Offset: [MBAR] + 8700h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
20:16	0x5 RW	**Debug Capability Event Ring Segment Table Max (DCERSTM):** Note: This register is sticky. **Power Well:** Core
15:8	0x0 RW	**Next Capability Pointer (NCP):** Note: This register is sticky. **Power Well:** Core
7:0	0xa RW	**Capability ID (CID):** Note: This register is sticky. **Power Well:** Core

51.3.242 Debug Capability Doorbell Register (DCDB)—Offset 8704h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8704h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:8	0x0 RW	**Doorbell Target (DBTGT):** This field defines the target of the doorbell reference. The table below defines the Debug Capability notification that is generated by ringing the doorbell. Value Definition 0 Data EP 1 OUT Enqueue Pointer Update 1 Data EP 1 IN Enqueue Pointer Update 2:255 Reserved This field returns '0' when read and the value should be treated as undefined by software. **Power Well:** Core
7:0	0x0 RW	**Reserved (RSVD_1):** Reserved. **Power Well:** Core

51.3.243 Debug Capability Event Ring Segment Table Size Register (DCERSTSZ)—Offset 8708h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8708h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RW	**Event Ring Segment Table Size (ERSTS):** This field identifies the number of valid Event Ring Segment Table entries in the Event Ring Segment Table pointed to by the Debug Capability Event Ring Segment Table Base Address register. The maximum value supported by an xHC implementation for this register is defined by the DCERST Max field in the DCID register Software shall initialize this register before setting the Debug Capability Enable field in the DCCTRL register to '1'. **Power Well:** Core

51.3.244 Debug Capability Event Ring Segment Table Base Address Register (DCERSTBA)—Offset 8710h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [MBAR] + 8710h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:4	0x0 RW	**Event Ring Segment Table Base Address Register (ERSTBAR):** This field defines the high order bits of the start address of the Debug Capability Event Ring Segment Table. Software shall initialize this register before setting the Debug Capability Enable field in the DCCTRL register to '1'. **Power Well:** Core
3:0	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core

51.3.245 Debug Capability Event Ring Dequeue Pointer Register (DCERDP)—Offset 8718h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [MBAR] + 8718h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:4	0x0 RW	**Dequeue Pointer (DQP):** This field defines the high order bits of the 64-bit address of the current Debug Capability Event Ring Dequeue Pointer. Software shall initialize this register before setting the Debug Capability Enable field in the DCCTRL register to '1'. **Power Well:** Core
3	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Dequeue ERST Segment Index (DESI):** This field may be used by the xHC to accelerate checking the Event Ring full condition. This field is written with the low order 3 bits of the offset of the ERST entry which defines the Event Ring segment that the Event Ring Dequeue Pointer resides in. **Power Well:** Core

51.3.246 Debug Capability Control Register (DCCTRL)—Offset 8720h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8720h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Debug Capability Enable (DCE):** Reserved. **Power Well:** Core
30:24	0x0 RO	**Device Address (DADDR):** Reserved. **Power Well:** Core
23:16	0x0 RO	**Debug Max Burst Size (DMBS):** LPT-LP USB Debug Device does not support bursting. **Power Well:** Core
15:5	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
4	0x0 RW/C	**DbC Run Change (DRC):** Reserved. **Power Well:** Core
3	0x0 RW/1S	**Halt IN TR (HIT):** Reserved. **Power Well:** Core
2	0x0 RW/1S	**Halt OUT TR (HOT):** Reserved. **Power Well:** Core
1	0x0 RW	**Link Status Event Enable (LSE):** Reserved. **Power Well:** Core
0	0x0 RO	**DbC Run (DCR):** Reserved. **Power Well:** Core

51.3.247 Debug Capability Status Register (DCST)—Offset 8724h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8724h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Debug Port Number (DPNUM):** This field provides the ID of the Root Hub port that the Debug Capability has been automatically attached to. The value is '0' when the Debug Capability is not attached to a Root Hub port. **Power Well:** Core
23:1	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
0	0x0 RO	**Event Ring Not Empty (ERNE):** When '1', this field indicates that the Debug Capability Event Ring has a Transfer Event on it. It is automatically cleared to '0' by the xHC when the Debug Capability Event Ring is empty, i.e. the Debug Capability Enqueue Pointer is equal to the Debug Capability Event Ring Dequeue Pointer register. **Power Well:** Core

51.3.248 Debug Capability Port Status and Control Register (DCPORTSC)—Offset 8728h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000080h

BAR and Offset: [MBAR] + 8728h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
23	0x0 RW/C	**Port Config Error Change (CEC):** This flag indicates that the port failed to configure its link partner. 0 = No change. 1 = Port Config Error detected. Software shall clear this bit by writing a '1' to it. **Power Well:** Core
22	0x0 RW/C	**Port Link Status Change (PLC):** This flag is set to '1' due to the following PLS transitions: U0 -) U3 Suspend signaling detected from Debug Host U3 -) U0 Resume complete Polling -) Disabled Training Error Ux or Recovery -) Inactive Error Software shall clear this bit by writing a '1' to it. This field is '0' if DCE is '0' **Power Well:** Core
21	0x0 RW/C	**Port Reset Change (PRC):** This bit is set when reset processing on this port is complete (i.e. a '1' to '0' transition of PR). '0' = No change. '1' = Reset complete.Software shall clear this bit by writing a '1' to it. This field is '0' if DCE is '0'. **Power Well:** Core
20:18	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
17	0x0 RW/C	**Connect Status Change (CSC):** an already-set bit (i.e., the bit will remain '1'). Software shall clear this bit by writing a '1' to it. This field is '0' if DCE is '0'. **Power Well:** Core
16:14	0x0 RO	**Reserved (RSVD_2):** Reserved. **Power Well:** Core
13:10	0x0 RO	**Port Speed (PSPD):** This field identifies the speed of the port. This field is only relevant when a Debug Host is attached (CCS = '1') in all other cases this field shall indicate Undefined Speed. 0 Undefined Speed 1-15 Protocol Speed ID (PSI) Note: The Debug Capability onlydoes not supports LS, FS, or HS operation. **Power Well:** Core
9	0x0 RO	**Reserved (RSVD_3):** Reserved. **Power Well:** Core
8:5	0x4 RO	**Port Link State (PLS):** This field reflects its current link state. This field is only relevant when a Debug Host is attached (Debug Port Number) '0'). Value Meaning 0 Link is in the U0 State 1 Link is in the U1 State 2 Link is in the U2 State 3 Link is in the U3 State (Device Suspended) 4 Link is in the Disabled State 5 Link is in the RxDetect State 6 Link is in the Inactive State 7 Link is in the Polling State 8 Link is in the Recovery State 9 Link is in the Hot Reset State 15:10 Reserved Note: Transitions between different states are not reflected until the transition is complete. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RO	**Port Reset (PR):** '1' = Port is in Reset. '0' = Port is not in Reset. This bit is set to '1' when the bus reset sequence as defined in the USB Specification is detected on the Root Hub port assigned to the Debug capability. It is cleared when the bus reset sequence is completed by the Debug Host, and the DbC shall transition to the USB Default state. A '0' to '1' transition of this bit shall clear DCPORTSC PED ('0'). This field is '0' if DCE or CCS are '0'. **Power Well:** Core
3:2	0x0 RO	**Reserved (RSVD_4):** Reserved. **Power Well:** Core
1	0x0 RW	**Port Enabled/Disabled (PED):** Default = '0'. '1' = Enabled. '0' = Disabled. This flag shall be set to '1' by a '0' to '1' transition of CCS or a '1' to '0' transition of the PR. When PED transitions from '1' to '0' due to the assertion of PR, the port's link shall transition to the Rx.Detect state. This flag may be used by software to enable or disable the operation of the Root Hub port assigned to the Debug Capability. The Debug Capability Root Hub port operation may be disabled by a fault condition (disconnect event or other fault condition, e.g. a LTSSM Polling substate timeout, tPortConfiguration timeout error, etc.), the assertion of DCPORTSC PR, or by software. 0 = Debug Capability Root Hub port is disabled. 1 = Debug Capability Root Hub port is enabled. When the port is disabled (PED = '0') the port's link shall enter the SS.Disabled state and remain there until PED is reasserted ('1') or DCE is negated ('0'). Note that the Root Hub port is remains mapped to Debug Capability while PED = '0'. While PED = '0' the Debug Capability will appear to be disconnected to the Debug Host. Note, this bit is not affected by PORTSC PR bit transitions. This field is '0' if DCE or CCS are '0'. **Power Well:** Core
0	0x0 RO	**Current Connect Status (CCS):** '1' = A Root Hub port is connected to a Debug Host and assigned to the Debug Capability. '0' = No Debug Host is present. This value reflects the current state of the port, and may not correspond to the value reported by the Connect Status Change (CSC) field in the Port Status Change Event that was generated by a '0' to '1' transition of this bit. This flag is '0' if Debug Capability Enable (DCE) is '0'. **Power Well:** Core

51.3.249 Debug Capability Context Pointer Register (DCCP)—Offset 8730h

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [MBAR] + 8730h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
63:4	0x0 RW	**Debug Capability Context Pointer Register (DCCPR):** This field defines the high order bits of the start address of the Debug Capability Context data structure associated with the Debug Capability. Software shall initialize this register before setting the Debug Capability Enable bit in the Debug Capability Control Register to '1'. **Power Well:** Core
3:0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

51.3.250 Debug Capability Device Descriptor Info Register 1 (DCDDI1)—Offset 8738h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 80870000h

BAR and Offset: [MBAR] + 8738h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x8087 RW	**Vendor ID (VID):** This field is presented by the Debug Device in the USB Device Descriptor idVendor field. **Power Well:** Core
15:8	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
7:0	0x0 RW	**DbC Protocol (DBCPR):** This field is presented by the Debug Device in the USB Interface Descriptor bInterfaceProtocol field. Value Function 0 Debug Target vendor defined. 1 GNU Remote Debug Command Set supported. 2-255 Reserved. **Power Well:** Core

51.3.251 Debug Capability Device Descriptor Info Register 2 (DCDDI2)—Offset 873Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 873Ch

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Device Revision (DREV):** This field is presented by the Debug Device in the USB Device Descriptor bcdDevice field. **Power Well:** Core
15:0	0x0 RW	**Product ID (PID):** This field is presented by the Debug Device in the USB Device Descriptor idProduct field. **Power Well:** Core

51.3.252 Debug Capability Descriptor Parameters (DCDP)—Offset 8740h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000030C3h

BAR and Offset: [MBAR] + 8740h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
23:16	0x0 RW	**Max Power Field (MPF):** This field will be used by USB Debug Device to report maximum power consumption when the device is fully operational. This value is returned by bMaxPower field in response to Configuration Descriptor read from the debug device. Note: bU1DevExitLat and bU2DevExitLat fields returned in BOS Descriptor read will be taken from the corresponding fields from the Host Controller space. **Power Well:** Core
15:8	0x30 RW/S	**NEXT CAPABILITY POINTER (NCP):** Reserved. **Power Well:** Core
7:0	0xc3 RW/S	**Capability ID (CID):** Reserved. **Power Well:** Core

51.3.253 Debug Device Control ODMA (DBGDEV_CTRL_ODMA_REG)—Offset 8748h

This register contains a number of fields that provide a specific level of configurability for the OUT DMA that is part of Debug Device logic. This configurability is above and beyond that defined in the xHCI specification.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MBAR] + 8748h

Default: 00000000h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
18	0x0 RW	**Enable ACK FIFO credit accounting (EN_ACK_FCA):** Setting this field will enable ACK FIFO credit accounting. ODMA will ensure that ample room exists in the ACK FIFO for expected device responses prior to initiating a given DP **Power Well:** Core
17:14	0x0 RW	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
13	0x0 RW	**Enable ACK FIFO ICA mechanisms (EN_ACK_FIFO_ICA):** Setting this field will enable ACK FIFO individual credit accounting mechanisms for Async vs. Periodic Endpoints. ODMA will ensure that ample room exists in the ACK FIFO for expected device responses prior to initiating a given DP **Power Well:** Core
12:9	0x0 RW	**Reserved (RSVD_2):** Reserved. **Power Well:** Core
8	0x0 RW	**Clear ownership of context semaphore (CL_OWN_CS):** Setting this field generates a pulse that clears the ownership of the context semaphore that is shared between the Out DMA Response and Completion Finite State Machines **Power Well:** Core
7	0x0 RW	**Return OD ACK credits (RET_OD_ACK_CR):** Setting this field generates a pulse that implicitly returns all of the Out DMA ACK credits on all ports **Power Well:** Core
6	0x0 RW	**Reserved (RSVD_3):** Reserved. **Power Well:** Core
5	0x0 RW	**Return ODCF SM to idle state (RET_ODCF_SM_IS):** Setting this field generates a pulse that returns the Out DMA Completion Finite State Machine into the IDLE state **Power Well:** Core
4	0x0 RW	**Return ODRF SM to idle state (RET_ODRF_SM_IS):** Setting this field generates a pulse that returns the Out DMA Response Finite State Machine into the IDLE state **Power Well:** Core
3	0x0 RW	**Return ODRDF SM to idle state (RET_ODRDF_SM_IS):** Setting this field generates a pulse that returns the Out DMA Read Finite State Machine into the IDLE state **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
2:0	0x0 RW	**Reserved (RSVD_4):** Reserved. **Power Well:** Core

51.3.254 DBC Control Register 1 (DBCCTL_REG)—Offset 8760h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MBAR] + 8760h

MBAR Type: PCI Configuration Register (Size: 64 bits)
MBAR Reference: [B:0, D:21, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** RSVD **Power Well:** Core
7	0x0 RW	**SW_DCE_SEL:** Reserved. **Power Well:** Core
6:3	0x0 RW	**DISC_RXD_CNT:** Reserved. **Power Well:** Core
2	0x0 RO	**RSVD0:** Reserved
1	0x0 RW	**Force DCE Mode (FORCE_DCE_MODE):** 0: When DCE is set, the DbC switches to Mode 2 1: When DCE is set, the DbC switches to Mode 3 **Power Well:** Core
0	0x0 RW	**Force Disconnect upon DCE (FORCE_DISCONNECT_ON_DCE):** If this bit is set by BIOS, the DbC will temporarily disconnect from the remote host if the DCE is set, and shortly thereafter re-connect. This allows the DbC to switch from Mode1 to Mode2 or Mode 3 operation upon DCE being set. **Power Well:** Core

§ §

52 System Management - B0, D24, F(0, 1, 3, 4)

52.1 Introduction and Index

The host-accessible registers for the System Management are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

52.1.1 Host Configuration Space—HECI1 (F:0)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 24 (decimal), Function 0. The offset addresses are listed.

Table 52-1. Summary of PCI Configuration Registers—0/24/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19D38086	"Identifiers (HECI1_ID)—Offset 0h" on page 2239
4	2	0000	"Command (HECI1_CMD)—Offset 4h" on page 2240
6	2	0010	"Status (HECI1_STS)—Offset 6h" on page 2241
8	4	07800000	"Revision ID and Class Code (HECI1_RID_CC)—Offset 8h" on page 2242
C	1	00	"Cache Line Size (HECI1_CLS)—Offset Ch" on page 2242
D	1	00	"Master Latency Timer (HECI1_MLT)—Offset Dh" on page 2242
E	1	80	"Header Type (HECI1_HTYPE)—Offset Eh" on page 2243
F	1	00	"Built In Self-Test (HECI1_BIST)—Offset Fh" on page 2243
10	4	00000004	"HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h" on page 2243
14	4	00000000	"HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h" on page 2244
2C	4	00000000	"Sub System Identifiers (HECI1_SS)—Offset 2Ch" on page 2244
34	1	50	"Capabilities Pointer (HECI1_CAP)—Offset 34h" on page 2244
3C	2	0100	"Interrupt Information (HECI1_INTR)—Offset 3Ch" on page 2245
3E	1	00	"Minimum Grant (HECI1_MGNT)—Offset 3Eh" on page 2245
3F	1	00	"Maximum Latency (HECI1_MLAT)—Offset 3Fh" on page 2245
40	4	00000000	"Host Firmware Status (HECI1_HFS)—Offset 40h" on page 2246
44	4	80000000	"Miscellaneous Shadow (HECI1_MISC_SHDW)—Offset 44h" on page 2248
48	4	00000000	"General Status Shadow 1 (HECI1_GS_SHDW1)—Offset 48h" on page 2249
4C	4	00000000	"Host General Status (HECI1_H_GS1)—Offset 4Ch" on page 2250
50	2	8C01	"PCI Power Management Capability ID (HECI1_PID)—Offset 50h" on page 2250
52	2	4003	"PCI Power Management Capabilities (HECI1_PC)—Offset 52h" on page 2250
54	2	0008	"PCI Power Management Control and Status (HECI1_PMCS)—Offset 54h" on page 2251
60	4	00000000	"General Status Shadow 2 (HECI1_GS_SHDW2)—Offset 60h" on page 2251
64	4	00000000	"General Status Shadow 3 (HECI1_GS_SHDW3)—Offset 64h" on page 2252
68	4	00000000	"General Status Shadow 4 (HECI1_GS_SHDW4)—Offset 68h" on page 2252
6C	4	00000000	"General Status Shadow 5 (HECI1_GS_SHDW5)—Offset 6Ch" on page 2252
70	4	00000000	"Host General Status 2 (HECI1_H_GS2)—Offset 70h" on page 2252
74	4	00000000	"Host General Status 3 (HECI1_H_GS3)—Offset 74h" on page 2253
8C	2	0005	"Message Signaled Interrupt Identifiers (HECI1_MID)—Offset 8Ch" on page 2253
8E	2	0080	"Message Signaled Interrupt Message Control (HECI1_MC)—Offset 8Eh" on page 2253
90	4	00000000	"Message Signaled Interrupt Message Address (HECI1_MA)—Offset 90h" on page 2254
94	4	00000000	"Message Signaled Interrupt Upper Address (HECI1_MUA)—Offset 94h" on page 2254
98	2	0000	"Message Signaled Interrupt Message Data (HECI1_MD)—Offset 98h" on page 2254
A0	1	00	"HECI Interrupt Delivery Mode (HECI1_HIDM)—Offset A0h" on page 2255
BC	4	40000000	"Host Extend Register Status (HECI1_HERS)—Offset BCh" on page 2255
C0	4	00000000	"Host Extend Register DW1. (HECI1_HER1)—Offset C0h" on page 2256

Table 52-1. Summary of PCI Configuration Registers—0/24/0 (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
C4	4	00000000	"Host Extend Register DW2. (HECI1_HER2)—Offset C4h" on page 2256
C8	4	00000000	"Host Extend Register DW3. (HECI1_HER3)—Offset C8h" on page 2256
CC	4	00000000	"Host Extend Register DW4. (HECI1_HER4)—Offset CCh" on page 2256
D0	4	00000000	"Host Extend Register DW5. (HECI1_HER5)—Offset D0h" on page 2257
D4	4	00000000	"Host Extend Register DW6. (HECI1_HER6)—Offset D4h" on page 2257
D8	4	00000000	"Host Extend Register DW7. (HECI1_HER7)—Offset D8h" on page 2257
DC	4	00000000	"Host Extend Register DW8. (HECI1_HER8)—Offset DCh" on page 2257
F8	4	00000000	"Manufacturer's ID (HECI1_MANID)—Offset F8h" on page 2258

52.1.2 Host Configuration Space—HECI2 (F:1)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 24 (decimal), Function 1. The offset addresses are listed.

Table 52-2. Summary of PCI Configuration Registers—0/24/1

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19D48086	"Identifiers (HECI2_ID)—Offset 0h" on page 2259
4	2	0000	"Command (HECI2_CMD)—Offset 4h" on page 2259
6	2	0010	"Status (HECI2_STS)—Offset 6h" on page 2261
8	4	07800000	"Revision ID and Class Code (HECI2_RID_CC)—Offset 8h" on page 2262
C	1	00	"Cache Line Size (HECI2_CLS)—Offset Ch" on page 2262
D	1	00	"Master Latency Timer (HECI2_MLT)—Offset Dh" on page 2262
E	1	80	"Header Type (HECI2_HTYPE)—Offset Eh" on page 2263
F	1	00	"Built In Self-Test (HECI2_BIST)—Offset Fh" on page 2263
10	4	00000004	"HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h" on page 2263
14	4	00000000	"HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h" on page 2264
2C	4	00000000	"Sub System Identifiers (HECI2_SS)—Offset 2Ch" on page 2264
34	1	50	"Capabilities Pointer (HECI2_CAP)—Offset 34h" on page 2264
3C	2	0100	"Interrupt Information (HECI2_INTR)—Offset 3Ch" on page 2265
3E	1	00	"Minimum Grant (HECI2_MGNT)—Offset 3Eh" on page 2265
3F	1	00	"Maximum Latency (HECI2_MLAT)—Offset 3Fh" on page 2265
40	4	00000000	"Host Firmware Status (HECI2_HFS)—Offset 40h" on page 2266
48	4	00000000	"General Status Shadow 1 (HECI2_GS_SHDW1)—Offset 48h" on page 2268
4C	4	00000000	"Host General Status (HECI2_H_GS1)—Offset 4Ch" on page 2269
50	2	8C01	"PCI Power Management Capability ID (HECI2_PID)—Offset 50h" on page 2269
52	2	4003	"PCI Power Management Capabilities (HECI2_PC)—Offset 52h" on page 2270
54	2	0008	"PCI Power Management Control and Status (HECI2_PMCS)—Offset 54h" on page 2271
60	4	00000000	"General Status Shadow 2 (HECI2_GS_SHDW2)—Offset 60h" on page 2271
64	4	00000000	"General Status Shadow 3 (HECI2_GS_SHDW3)—Offset 64h" on page 2272
68	4	00000000	"General Status Shadow 4 (HECI2_GS_SHDW4)—Offset 68h" on page 2272
6C	4	00000000	"General Status Shadow 5 (HECI2_GS_SHDW5)—Offset 6Ch" on page 2272
70	4	00000000	"Host General Status 2 (HECI2_H_GS2)—Offset 70h" on page 2272
74	4	00000000	"Host General Status 3 (HECI2_H_GS3)—Offset 74h" on page 2273
8C	2	0005	"Message Signaled Interrupt Identifiers (HECI2_MID)—Offset 8Ch" on page 2273
8E	2	0080	"Message Signaled Interrupt Message Control (HECI2_MC)—Offset 8Eh" on page 2273
90	4	00000000	"Message Signaled Interrupt Message Address (HECI2_MA)—Offset 90h" on page 2274
94	4	00000000	"Message Signaled Interrupt Upper Address (HECI2_MUA)—Offset 94h" on page 2274
98	2	0000	"Message Signaled Interrupt Message Data (HECI2_MD)—Offset 98h" on page 2274
A0	1	00	"HECI Interrupt Delivery Mode (HECI2_HIDM)—Offset A0h" on page 2275
F8	4	00000000	"Manufacturer's ID (HECI2_MANID)—Offset F8h" on page 2275

52.1.3 Host Configuration Space—HECI3 (F:4)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 24 (decimal), Function 4. The offset addresses are listed.

Table 52-3. Summary of PCI Configuration Registers—0/24/4

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19D68086	"Identifiers (HECI3_ID)—Offset 0h" on page 2276
4	2	0000	"Command (HECI3_CMD)—Offset 4h" on page 2277
6	2	0010	"Status (HECI3_STS)—Offset 6h" on page 2278
8	4	07800000	"Revision ID and Class Code (HECI3_RID_CC)—Offset 8h" on page 2279
C	1	00	"Cache Line Size (HECI3_CLS)—Offset Ch" on page 2279
D	1	00	"Master Latency Timer (HECI3_MLT)—Offset Dh" on page 2279
E	1	80	"Header Type (HECI3_HTYPE)—Offset Eh" on page 2280
F	1	00	"Built In Self-Test (HECI3_BIST)—Offset Fh" on page 2280
10	4	00000004	"HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h" on page 2280
14	4	00000000	"HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h" on page 2281
2C	4	00000000	"Sub System Identifiers (HECI3_SS)—Offset 2Ch" on page 2281
34	1	50	"Capabilities Pointer (HECI3_CAP)—Offset 34h" on page 2281
3C	2	0100	"Interrupt Information (HECI3_INTR)—Offset 3Ch" on page 2282
3E	1	00	"Minimum Grant (HECI3_MGNT)—Offset 3Eh" on page 2282
3F	1	00	"Maximum Latency (HECI3_MLAT)—Offset 3Fh" on page 2282
40	4	00000000	"Host Firmware Status (HECI3_HFS)—Offset 40h" on page 2283
48	4	00000000	"General Status Shadow 1 (HECI3_GS_SHDW1)—Offset 48h" on page 2285
4C	4	00000000	"Host General Status (HECI3_H_GS1)—Offset 4Ch" on page 2286
50	2	8C01	"PCI Power Management Capability ID (HECI3_PID)—Offset 50h" on page 2286
52	2	4003	"PCI Power Management Capabilities (HECI3_PC)—Offset 52h" on page 2286
54	2	0008	"PCI Power Management Control and Status (HECI3_PMCS)—Offset 54h" on page 2287
60	4	00000000	"General Status Shadow 2 (HECI3_GS_SHDW2)—Offset 60h" on page 2287
64	4	00000000	"General Status Shadow 3 (HECI3_GS_SHDW3)—Offset 64h" on page 2288
68	4	00000000	"General Status Shadow 4 (HECI3_GS_SHDW4)—Offset 68h" on page 2288
6C	4	00000000	"General Status Shadow 5 (HECI3_GS_SHDW5)—Offset 6Ch" on page 2288
70	4	00000000	"Host General Status 2 (HECI3_H_GS2)—Offset 70h" on page 2288
74	4	00000000	"Host General Status 3 (HECI3_H_GS3)—Offset 74h" on page 2289
8C	2	0005	"Message Signaled Interrupt Identifiers (HECI3_MID)—Offset 8Ch" on page 2289
8E	2	0080	"Message Signaled Interrupt Message Control (HECI3_MC)—Offset 8Eh" on page 2289
90	4	00000000	"Message Signaled Interrupt Message Address (HECI3_MA)—Offset 90h" on page 2290
94	4	00000000	"Message Signaled Interrupt Upper Address (HECI3_MUA)—Offset 94h" on page 2290
98	2	0000	"Message Signaled Interrupt Message Data (HECI3_MD)—Offset 98h" on page 2290
A0	1	00	"HECI Interrupt Delivery Mode (HECI3_HIDM)—Offset A0h" on page 2291
F8	4	00000000	"Manufacturer's ID (HECI3_MANID)—Offset F8h" on page 2291

52.1.4 Host Configuration Space—KT (F:3)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 24 (decimal), Function 3. The offset addresses are listed.

Table 52-4. Summary of PCI Configuration Registers—0/24/3

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19D58086	"Device ID and Vendor ID (KT_HOST_DID_VID)—Offset 0h" on page 2292
4	4	00B00000	"Status and Command (KT_HOST_STS_CMD)—Offset 4h" on page 2293
8	4	07000200	"Class Code and Revision ID (KT_HOST_CC_RID)—Offset 8h" on page 2295
C	4	00800000	"BIST, Header Type, Latency Timer, and Cache Line Size (KT_HOST_BIST_HTYPE_LT_CLS)—Offset Ch" on page 2295
10	4	00000001	"KT IO BAR (KT_HOST_IOBAR)—Offset 10h" on page 2296
14	4	00000000	"KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h" on page 2296
28	4	00000000	"Cardbus CIS Pointer (KT_HOST_CCP)—Offset 28h" on page 2297
2C	4	00008086	"Subsystem ID and Subsystem Vendor ID (KT_HOST_SID_SVID)—Offset 2Ch" on page 2297
30	4	00000000	"Expansion ROM Base Address (KT_HOST_XRBAR)—Offset 30h" on page 2297
34	4	00000040	"Capabilities List Pointer (KT_HOST_CAPP)—Offset 34h" on page 2298
3C	4	00000000	"Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (KT_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch" on page 2298
40	4	00805005	"MSI Message Control, Next Pointer and Capability ID (KT_HOST_MSIMC_MSINP_MSICID)—Offset 40h" on page 2299
44	4	00000000	"MSI Message Address (KT_HOST_MSIMA)—Offset 44h" on page 2299
48	4	00000000	"MSI Message Upper Address (KT_HOST_MSIMUA)—Offset 48h" on page 2300
4C	4	00000000	"MSI Message Data (KT_HOST_MSIMD)—Offset 4Ch" on page 2300
50	4	00230001	"Power Management Capabilities, Next Pointer and Capability ID (KT_HOST_PMCAP_PMNP_PMCID)—Offset 50h" on page 2301
54	4	00000008	"Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (KT_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h" on page 2302
F8	4	00000000	"Process Stepping Information (KT_HOST_PSI)—Offset F8h" on page 2303

52.1.5 Host Configuration Space—IDE (F:2)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 24 (decimal), Function 2. The offset addresses are listed.

Table 52-5. Summary of PCI Configuration Registers—0/24/2

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19EA8086	"Device ID and Vendor ID (IDE_HOST_DID_VID)—Offset 0h" on page 2304
4	4	00B00000	"Status and Command (IDE_HOST_STS_CMD)—Offset 4h" on page 2305
8	4	01018500	"Class Code and Revision ID (IDE_HOST_CC_RID)—Offset 8h" on page 2307
C	4	00800000	"BIST, Header Type, Latency Timer, and Cache Line Size (IDE_HOST_BIST_HTYPE_LT_CLS)—Offset Ch" on page 2307
10	4	00000001	"IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h" on page 2308
14	4	00000001	"IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h" on page 2308
18	4	00000001	"IDE Secondary Command Block IO BAR (IDE_HOST_SCMDIOBAR)—Offset 18h" on page 2309
1C	4	00000001	"IDE Secondary Control Block IO BAR (IDE_HOST_SCTLIOBAR)—Offset 1Ch" on page 2309
20	4	00000001	"IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h" on page 2310
28	4	00000000	"Cardbus CIS Pointer (IDE_HOST_CCP)—Offset 28h" on page 2310
2C	4	00008086	"Subsystem ID and Subsystem Vendor ID (IDE_HOST_SID_SVID)—Offset 2Ch" on page 2311
30	4	00000000	"Expansion ROM Base Address (IDE_HOST_XRBAR)—Offset 30h" on page 2311
34	4	00000040	"Capabilities List Pointer (IDE_HOST_CAPP)—Offset 34h" on page 2311
3C	4	00000000	"Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (IDE_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch" on page 2312
40	4	00805005	"MSI Message Control, Next Pointer and Capability ID (IDE_HOST_MSIMC_MSINP_MSICID)—Offset 40h" on page 2313
44	4	00000000	"MSI Message Address (IDE_HOST_MSIMA)—Offset 44h" on page 2313
48	4	00000000	"MSI Message Upper Address (IDE_HOST_MSIMUA)—Offset 48h" on page 2314
4C	4	00000000	"MSI Message Data (IDE_HOST_MSIMD)—Offset 4Ch" on page 2314
50	4	00230001	"Power Management Capabilities, Next Pointer and Capability ID (IDE_HOST_PMCAP_PMNP_PMCID)—Offset 50h" on page 2315
54	4	00000008	"Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (IDE_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h" on page 2316
F8	4	00000000	"Process Stepping Information (IDE_HOST_PSI)—Offset F8h" on page 2317

52.1.6 Host Memory Space—HECI1_MMIO_MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 52-6. Summary of Memory Mapped I/O Registers—HECI1_MMIO_MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Host CB Write Window (HECI1_H_CB_WW)—Offset 0h" on page 2318
4	4	80000000	"Host Control and Status Register (HECI1_H_CSR)—Offset 4h" on page 2319
8	4	FFFFFFFF	"CSE Circular Buffer Read Window (HECI1_CSE_CB_RW)—Offset 8h" on page 2320
C	4	80000000	"CSE Control and Status Register Host Access (HECI1_CSE_CSR_HA)—Offset Ch" on page 2320
800	4	00000000	"D0i3 Control (HECI1_D0I3C)—Offset 800h" on page 2321

52.1.7 Host Memory Space—HECI2_MMIO_MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 52-7. Summary of Memory Mapped I/O Registers—HECI2_MMIO_MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Host CB Write Window (HECI2_H_CB_WW)—Offset 0h" on page 2322
4	4	80000000	"Host Control and Status Register (HECI2_H_CSR)—Offset 4h" on page 2323
8	4	FFFFFFFF	"CSE Circular Buffer Read Window (HECI2_CSE_CB_RW)—Offset 8h" on page 2324
C	4	80000000	"CSE Control and Status Register Host Access (HECI2_CSE_CSR_HA)—Offset Ch" on page 2324
800	4	00000000	"D0i3 Control (HECI2_D0I3C)—Offset 800h" on page 2325

52.1.8 Host Memory Space—HECI3_MMIO_MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 52-8. Summary of Memory Mapped I/O Registers—HECI3_MMIO_MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Host CB Write Window (HECI3_H_CB_WW)—Offset 0h" on page 2326
4	4	80000000	"Host Control and Status Register (HECI3_H_CSR)—Offset 4h" on page 2327
8	4	FFFFFFFF	"CSE Circular Buffer Read Window (HECI3_CSE_CB_RW)—Offset 8h" on page 2328
C	4	80000000	"CSE Control and Status Register Host Access (HECI3_CSE_CSR_HA)—Offset Ch" on page 2328
800	4	00000000	"D0i3 Control (HECI3_D0I3C)—Offset 800h" on page 2329

52.1.9 Host Memory Space—KT_HOST_MEMBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 52-9. Summary of Memory Mapped I/O Registers—KT_HOST_MEMBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"KT Receive Buffer Register (MEM_KTRBR)—Offset 0h" on page 2330
0	1	00	"KT Transmitter Holding Register (MEM_KTTHR)—Offset 0h" on page 2330
0	1	00	"KT Divisor Latch LSB Register (MEM_KTDLLR)—Offset 0h" on page 2331
1	1	00	"KT Interrupt Enable register (MEM_KTIER)—Offset 1h" on page 2331
1	1	00	"KT Divisor Latch MSB Register (MEM_KTDLMR)—Offset 1h" on page 2332
2	1	01	"KT Interrupt Identification Register (MEM_KTIIR)—Offset 2h" on page 2333
2	1	00	"KT FIFO Control register (MEM_KTFCR)—Offset 2h" on page 2334
3	1	03	"KT Line Control register (MEM_KTLCR)—Offset 3h" on page 2335
4	1	00	"KT Modem Control register (MEM_KTMCR)—Offset 4h" on page 2336
5	1	60	"KT Line Status register (MEM_KTLSR)—Offset 5h" on page 2337
6	1	00	"KT Modem Status register (MEM_KTMSR)—Offset 6h" on page 2338
7	1	00	"KT Scratch register (MEM_KTSCR)—Offset 7h" on page 2338

52.1.10 Host Memory Space—Fixed Address

An index of the registers that are accessible in Host Memory Space is shown here.

Table 52-10. Summary of Memory Mapped I/O Registers—Fixed Addresses

Memory Address (hex)	Bytes (decimal)	Default Value (hex)	Register Name (Register Symbol)
FED40000	4	00000000	"FTPM Locality State (HOST_LOC_0_LOC_STATE_HROA)—Offset FED40000h" on page 2339
FED40004	4	00000000	"FTPM Locality Reserved (HOST_LOC_0_LOC_RSVD)—Offset FED40004h" on page 2340
FED40008	4	00000000	"FTPM Locality n Control Register (HOST_LOC_0_LOC_CTRL)—Offset FED40008h" on page 2340
FED4000C	4	00000000	"FTPM Locality n Status Register Host Read Only Access. (HOST_LOC_0_LOC_STS_HROA)—Offset FED4000Ch" on page 2340
FED40010	4	00000000	"FTPM Locality Config Area Reserved Read Write[0-7] (HOST_LOC_0_RSVD_RW1[0-7])—Offset FED40010h, Count 8, Stride 4h" on page 2341
FED40030	4	00000000	"FTPM Interface ID Host Read Only Access 0 (HOST_LOC_0_INTF_ID_0)—Offset FED40030h" on page 2341
FED40034	4	00000000	"FTPM Interface ID Host Read Only Access 1 (HOST_LOC_0_INTF_ID_1)—Offset FED40034h" on page 2341
FED40038	4	00000000	"FTPM Locality Config Area Reserved Read Write[0-1] (HOST_LOC_0_RSVD_RW2[0-1])—Offset FED40038h, Count 2, Stride 4h" on page 2342
FED40040	4	00000000	"Control Area Request (HOST_LOC_0_CA_REQUEST)—Offset FED40040h" on page 2342
FED40044	4	00000000	"Control Area Status (HOST_LOC_0_CA_STATUS)—Offset FED40044h" on page 2342
FED40048	4	00000000	"Control Area Cancel (HOST_LOC_0_CA_CANCEL)—Offset FED40048h" on page 2343
FED4004C	4	00000000	"Control Area Start (HOST_LOC_0_CA_START)—Offset FED4004Ch" on page 2343
FED40050	4	00000000	"Control Area Interrupt Reserved Part 1 (HOST_LOC_0_CA_INT_RSVD1)—Offset FED40050h" on page 2343
FED40054	4	00000000	"Control Area Interrupt Reserved Part 2 (HOST_LOC_0_CA_INT_RSVD2)—Offset FED40054h" on page 2344
FED40058	4	00000000	"Control Area Command Size (HOST_LOC_0_CA_CMD_SZ)—Offset FED40058h" on page 2344
FED4005C	4	00000000	"Control Area Command Part 1 (HOST_LOC_0_CA_CMD1)—Offset FED4005Ch" on page 2344
FED40060	4	00000000	"Control Area Command Part 2 (HOST_LOC_0_CA_CMD2)—Offset FED40060h" on page 2345
FED40064	4	00000000	"Control Area Response Size (HOST_LOC_0_CA_RSP_SZ)—Offset FED40064h" on page 2345
FED40068	4	00000000	"Control Area Response Part 1 (HOST_LOC_0_CA_RSP1)—Offset FED40068h" on page 2345
FED4006C	4	00000000	"Control Area Response Part 2 (HOST_LOC_0_CA_RSP2)—Offset FED4006Ch" on page 2346
FED40070	4 x 4	00000000	"FTPM Reserved Read Write[0-3] (HOST_LOC_0_RSVD_RW3[0-3])—Offset FED40070h, Count 4, Stride 4h" on page 2346
FED40080	4 x 992	00000000	"FTPM Command and Response Buffer[0-991] (HOST_LOC_0_FTPM_CRB[0-991])—Offset FED40080h, Count 992, Stride 4h" on page 2346

52.1.11 Host I/O Space—KT_HOST_IOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 52-11. Summary of I/O Registers—KT_HOST_IOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"KT Receive Buffer Register (IO_KTRBR)—Offset 0h" on page 2347
0	1	00	"KT Transmitter Holding Register (IO_KTTHR)—Offset 0h" on page 2347
0	1	00	"KT Divisor Latch LSB Register (IO_KTDLLR)—Offset 0h" on page 2348
1	1	00	"KT Interrupt Enable register (IO_KTIER)—Offset 1h" on page 2348
1	1	00	"KT Divisor Latch MSB Register (IO_KTDLMR)—Offset 1h" on page 2349
2	1	01	"KT Interrupt Identification Register (IO_KTIIR)—Offset 2h" on page 2349
2	1	00	"KT FIFO Control register (IO_KTFCR)—Offset 2h" on page 2350
3	1	03	"KT Line Control register (IO_KTLCR)—Offset 3h" on page 2351
4	1	00	"KT Modem Control register (IO_KTMCR)—Offset 4h" on page 2352
5	1	60	"KT Line Status register (IO_KTLSR)—Offset 5h" on page 2353
6	1	00	"KT Modem Status register (IO_KTMSR)—Offset 6h" on page 2354
7	1	00	"KT Scratch register (IO_KTSCR)—Offset 7h" on page 2355

52.1.12 Host I/O Space—IDE_HOST_PCMDIOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 52-12. Summary of I/O Registers—IDE_HOST_PCMDIOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	0000	"IDE Data Register (IDEDATA)—Offset 0h" on page 2356
1	1	00	"IDE Features Register (IDEFR)—Offset 1h" on page 2356
1	1	00	"IDE Error Register DEV0 (IDEERD0)—Offset 1h" on page 2357
1	1	00	"IDE Error Register DEV1 (IDEERD1)—Offset 1h" on page 2357
2	1	00	"IDE Sector Count In Register (IDESCIR)—Offset 2h" on page 2358
2	1	00	"IDE Sector Count Out Register DEV0 (IDESCOR0)—Offset 2h" on page 2358
2	1	00	"IDE Sector Count Out Register DEV1 (IDESCOR1)—Offset 2h" on page 2358
3	1	00	"IDE Sector Number In Register (IDESNIR)—Offset 3h" on page 2359
3	1	00	"IDE Sector Number Out Register DEV0 (IDESNOR0)—Offset 3h" on page 2359
3	1	00	"IDE Sector Number Out Register DEV1 (IDESNOR1)—Offset 3h" on page 2360
4	1	00	"IDE Cylinder Low In Register (IDECLIR)—Offset 4h" on page 2360
4	1	00	"IDE Cylinder Low Out Register DEV0 (IDCLOR0)—Offset 4h" on page 2361
4	1	00	"IDE Cylinder Low Out Register DEV1 (IDCLOR1)—Offset 4h" on page 2361
5	1	00	"IDE Cylinder High In Register (IDECHIR)—Offset 5h" on page 2362
5	1	00	"IDE Cylinder High Out Register DEV0 (IDCHOR0)—Offset 5h" on page 2362
5	1	00	"IDE Cylinder High Out Register DEV1 (IDCHOR1)—Offset 5h" on page 2363
6	1	00	"IDE Drive/Head In Register (IDEDHIR)—Offset 6h" on page 2363
6	1	00	"IDE Drive/Head Out Register DEV0 (IDDHOR0)—Offset 6h" on page 2364
6	1	00	"IDE Drive/Head Out Register DEV1 (IDDHOR1)—Offset 6h" on page 2364
7	1	00	"IDE Command Register (IDECR)—Offset 7h" on page 2365
7	1	80	"IDE Status Register DEV0 (IDESR0)—Offset 7h" on page 2366
7	1	80	"IDE Status Register DEV1 (IDESR1)—Offset 7h" on page 2367

52.1.13 Host I/O Space—IDE_HOST_PCTLIOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 52-13. Summary of I/O Registers—IDE_HOST_PCTLIOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
2	1	00	"IDE Device Control Register (IDDCR)—Offset 2h" on page 2368
2	1	00	"IDE Alternate Status Register (IDASR)—Offset 2h" on page 2368

52.1.14 Host I/O Space—IDE_HOST_BMIOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 52-14. Summary of I/O Registers—IDE_HOST_BMIOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"IDE Primary Bus Master Command Register (IDEPBMCR)—Offset 0h" on page 2369
1	1	00	"IDE Primary Bus Master Device Specific 0 Register (IDEPBMDS0R)—Offset 1h" on page 2370
2	1	80	"IDE Primary Bus Master Status Register (IDEPBMSR)—Offset 2h" on page 2371
3	1	00	"IDE Primary Bus Master Device Specific 1 Register (IDEPBMDS1R)—Offset 3h" on page 2373
4	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 0 (IDEPBMDTPR0)—Offset 4h" on page 2373
5	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 1 (IDEPBMDTPR1)—Offset 5h" on page 2373
6	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 2 (IDEPBMDTPR2)—Offset 6h" on page 2374
7	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 3 (IDEPBMDTPR3)—Offset 7h" on page 2374
8	1	00	"IDE Secondary Bus Master Command Register (IDESBMCR)—Offset 8h" on page 2375
9	1	00	"IDE Secondary Bus Master Device Specific 0 Register (IDESBMDS0R)—Offset 9h" on page 2375
A	1	80	"IDE Secondary Bus Master Status Register (IDESBMSR)—Offset Ah" on page 2376
B	1	00	"IDE Secondary Bus Master Device Specific 1 Register (IDESBMDS1R)—Offset Bh" on page 2377
C	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0 (IDESBMDTPR0)—Offset Ch" on page 2377
D	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1 (IDESBMDTPR1)—Offset Dh" on page 2378
E	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2 (IDESBMDTPR2)—Offset Eh" on page 2378
F	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3 (IDESBMDTPR3)—Offset Fh" on page 2379

52.1.15 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 52-15. Summary of Sideband Registers for KT (Host)—0xe4

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
0	00000000	"KT Host Interrupt Pin Register (KTHIPINR)—Offset 0h" on page 2380
4	00000000	"BIOS KT Host PCI Function Disable Register (BKTHDISR)—Offset 4h" on page 2380

Table 52-16. Summary of Sideband Registers for IDE (Host)—0xe4

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
0	00000000	"IDE Host Interrupt Pin Register (IDEHIPINR)—Offset 0h" on page 2381
4	00000000	"BIOS IDE Host PCI Function Disable Register (BIDEHDISR)—Offset 4h" on page 2381

52.2 Registers in Configuration Space—HECI1

52.2.1 Identifiers (HECI1_ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 0h

Default: 19D38086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19d3 RO/V	**Device ID (DID):** Indicates what device number assigned by Intel.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates Intel is the vendor, assigned by the PCI SIG.

52.2.2 Command (HECI1_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD:** Reserved
10	0x0 RW	**Interrupt Disable (ID):** Disables this device from generating PCI line based interrupts. This bit does not have any effect on MSI operation.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not implemented, hardwired to 0.
8	0x0 RO	**SERR# Enable (SEE):** Not implemented, hardwired to 0.
7	0x0 RO	**Wait Cycle Enable (WCC):** Not implemented, hardwired to 0.
6	0x0 RO	**Parity Error Response Enable (PEE):** Not implemented, hardwired to 0.
5	0x0 RO	**VGA Palette Snooping Enable (VAG):** Not implemented, hardwired to 0
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not implemented, hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not implemented, hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the HECI host controller's abiity to act as a system memory master for data transfers. When this bit is cleared, HECI bus master activity stops and any active DMA engines return to an idle condition. This bit is made visible to firmware through the H_PCI_CSR register, and changes to this bit may be configured by the H_PCI_CSR register to generate an MSI to mIA. When this bit is '0', HECI is blocked from generating MSI to the host CPU. ***Note:*** This bit does not block HECI accesses to CSE-UMA
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the HECI host controllers memory mapped register space.
0	0x0 RO	**I/O Space Enable (IOSE):** Not implemented, hardwired to 0.

52.2.3 Status (HECI1_STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Detected Parity Error (DPE):** Not implemented, hardwired to 0.
14	0x0 RO	**Signaled System Error (SSE):** Not implemented, hardwired to 0.
13	0x0 RO	**Received Master-Abort (RMA):** Not implemented, hardwired to 0.
12	0x0 RO	**Received Target Abort (RTA):** Not implemented, hardwired to 0.
11	0x0 RO	**Signaled Target-Abort (STA):** Not implemented, hardwired to 0.
10:9	0x0 RO	**DEVSEL# Timing (DEVT):** These bits are hardwired to 00.
8	0x0 RO	**Master Data Parity Error Detected (DPD):** Not implemented, hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not implemented, hardwired to 0.
6	0x0 RO	**RSVD (RSVD_6_6):** Reserved.
5	0x0 RO	**66 MHz Capable (C66):** Not implemented, hardwired to 0.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list, hardwired to 1.
3	0x0 RO/V	**Interrupt Status (IS):** Reflects the state of the INTx# signal at the input of the enable/disable circuit. This bit is a 1 when the INTx# is asserted. This bit is a 0 after the interrupt is cleared (independent of the state of the Interrupt Disable bit in the command register). ***Note:*** This bit is not set by an MSI.
2:0	0x0 RO	**RSVD (RSVD_2_0):** Reserved

52.2.4 Revision ID and Class Code (HECI1_RID_CC)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 8h

Default: 07800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Indicates the base class code of the HECI host controller device.
23:16	0x80 RO	**Sub Class Code (SCC):** Indicates the sub class code of the HECI host controller device.
15:8	0x0 RO	**Programming Interface (PI):** Indicates the programming interface of the HECI host controller device.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates stepping of the HECI host controller.

52.2.5 Cache Line Size (HECI1_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented, hardwired to 0.

52.2.6 Master Latency Timer (HECI1_MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Not implemented, hardwired to 0.

52.2.7 Header Type (HECI1_HTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + Eh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Multi-Function Device (MFD):** Indicates the HECI host controller is part of a multi- function device.
6:0	0x0 RO	**Header Layout (HL):** Indicates that the HECI host controller uses a target device layout.

52.2.8 Built In Self-Test (HECI1_BIST)—Offset Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**BIST Capable (BC):** Not implemented, hardwired to 0.
6:0	0x0 RO	**RSVD:** Reserved.

52.2.9 HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Base Address Low (BA_LO):** Lower 32 bits of base address of register memory space.
11:4	0x0 RO	**Memory Size (MS):** This field is hardwired to 0 to indicate that HECI device requests 4KB of memory space.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not pre-fetchable.
2:1	0x2 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 64-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

52.2.10 HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address High (BA_HI):** Upper 32 bits of base address of register memory space.

52.2.11 Sub System Identifiers (HECI1_SS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Indicates the sub- system identifier. This field should be programmed by BIOS during boot-up. Once written, this register becomes Read Only.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Indicates the sub-system vendor identifier. This field should be programmed by BIOS during boot- up. Once written, this register becomes Read Only.

52.2.12 Capabilities Pointer (HECI1_CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + 34h

Default: 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x50 RO	**Capability Pointer (CP):** Indicates the first capability pointer offset. It points to the PCI power management capability offset.

52.2.13 Interrupt Information (HECI1_INTR)—Offset 3Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO/V	**Interrupt Pin (IPIN):** This field indicates the virtual interrupt pin the HECI host controller uses. A value of 0x1/0x2/0x3/0x4 indicates that this function implements legacy interrupt on INTA/INTB/INTC/INTD, respectively. When legacy interrupt is not used this register should be set to 0x0.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this field.

52.2.14 Minimum Grant (HECI1_MGNT)—Offset 3Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + 3Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Grant (GNT):** Not implemented, hardwired to 0.

52.2.15 Maximum Latency (HECI1_MLAT)—Offset 3Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + 3Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Latency (LAT):** Not implemented, hardwired to 0.

52.2.16 Host Firmware Status (HECI1_HFS)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**BIOS MSG ACK:** Acknowledge for register based BIOS message in MEI 1 H_GS Register.
27:25	0x0 RO	**BIOS MSG ACK Data:** Message specific data for acknowledged BIOS message.
24:20	0x0 RO	Reserved
19:16	0x0 RO	**Operating Mode:** This field describes the current operating mode of Intel® ME. • 1:0 - Reserved • 2 - Debug Mode • 14:3 - Reserved • 15 - Intel® SPS firmware is running in Intel® ME
15:12	0x0 RO	**Error Code:** If set to nonzero value the Intel® ME firmware has encountered a fatal error and stopped normal operation. • 0 - No Error • 1 - Uncategorized Failure - The Intel® ME firmware has experienced an uncategorized error. Further details of the failure can be found in the Extended Status Data. • 2 - Disabled - Firmware was disabled on this platform. • 3 - Image Failure - The Intel® ME firmware stored in the system flash is not valid.
11	0x0 RO	**Update in Progress:** The bit is set if any type of Intel® ME firmware update is in progress.
10	0x0 RO	**Recovery BUP Load Fault:** This bit is set when firmware is not able to load recovery bring-up from the flash. It means that the recovery section in Intel® ME region on the SPI flash.
9	0x0 RO	**Init Complete:** When this but is not set firmware is still in initialization phase. When firmware has fully entered a stable state, this but is set to 1 and "Current State" field of this register provides the steady state of the Intel® ME subsystem.
8:6	0x0 RO	**Operating State:** This field describes the current operating state of Intel® ME. • 000 - Preboot • 001 - M0 with UMA • 010 - Reserved • 011 - Reserved • 100 - M3 without UMA • 101 - M0 without UMA - normal state for Intel® SPS firmware • 110 - Bring up • 111 - M0 without UMA but with error
5	0x0 RO	**FPT or Factory Defaults Bad:** This bit is set when the firmware discovers a bad checksum of Intel® ME region Flash Partition Table (FPT) or Factory Defaults. When this bit set, it may or may not have the error code shown in bit [15:12]. The system can get this bit clear only by re-flashing the whole Intel® ME region in the SPI Flash.
4	0x0 RO	**Manufacturing Mode:** When this bit is set, the platform is still in manufacturing mode. Host can use this bit to inform user that the platform is NOT READY for production yet. This but is set as long as Intel® ME Region access is not locked for flash masters other than Intel® ME. For shipping machine, this bit MUST be 0.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**Current State:** This field describes the current operation state of the firmware. • 0 - Reset - Intel® ME is in reset state, will exit this state within 1 millisecond • 1 - Initialization - Intel® ME is initializing, will exit this state within 2 seconds • 2 - Recovery - Intel® ME is in recovery mode, check ME1.GMES register to determine cause • 3 - Reserved • 4 - Disabled - Intel® ME functionality has been disabled, it executes idle loop • 5 - Operational - Intel® ME is in normal operational state • 6 - Reserved • 7 - State Transition - Intel® ME sets this state before starting a transition to a new Operating State. It is a temporary state, may appear on transition between Initialization and Operational.

52.2.17 Miscellaneous Shadow (HECI1_MISC_SHDW)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 44h

Default: 80000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Miscellaneous Shadow Valid (MSVLD):** This bit is hardwired to 1 to indicate that this HECI device implements the Miscellaneous Shadow register. This bit can be used by host software that is bus/dev/function number agnostic (such as HECI operating system driver) to discover whether the Miscellaneous Shadow register is implemented or not.
30:17	0x0 RO	**RSVD_30_17:** Reserved.
16	0x0 RO/V	**CSE UMA Size Valid (CUSZV):** This bit indicates that FW has written the CUSZ field. This field reflects the value of CSE CUBA.CUSZV.
15:7	0x0 RO	**Reserved (RSVD_15_7):** Reserved.
6:0	0x0 RO/V	**CSE UMA Size (CUSZ):** These bits reflect firmware's desired size of CSEUMA memory region. It is configured by firmware prior to bring up core power and allowing BIOS to initialize memory. The legal CSEUMA sizes and encodings for this field are: • 0000000b (0MB, no CSEUMA region) • 0000001b (1MB) • 0000010b (2MB) • 0000100b (4MB) • 0001000b (8MB) • 0010000b (16MB) • 0100000b (32MB) • 1000000b (64MB). This field reflects the value of CSE CUBA.CUSZ.

52.2.18 General Status Shadow 1 (HECI1_GS_SHDW1)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**EOP Status:** This bit presents the Intel® ME notion of EOP status. If BIOS encounters this bit set to '1' during POST it signals an error in platform power flow.
30:28	0x0 RO	**Infrastructure Progress Code:** This field identifies the infrastructure progress code: • 0 - ROM - Intel® ME is in ROM phase • 1 - BUP - Intel® ME is in BRINGUP phase • 2 - uKernel - Intel® ME is in Micro Kernel phase • 3 - Policy Module - Intel® ME is in Policy Module phase • 4 - Other Module - Intel® ME is loading modules in M0 or M3 Operating State
27:16	0x0 RO	**Extended Status Data:** These bits provide extended status data for the current state of operating of the firmware. Or, if the firmware is in a fatal error state, these bits provide extended error code information.
15:13	0x0 RO	**Firmware Heartbeat:** This number increments approximately every second if Intel® ME firmware is running.
12	0x0 RO	Intel® ME Target Image Boot Fault • 0 - Target image loaded successfully • 1 - Target image boot failed, switched to backup image or recovery image
11:8	0x0 RO	Reserved
7	0x0 RO	**Warm Reset Request:** If this bit is set, Intel® ME informs BIOS that a warm reset is requested by Intel® ME.
6	0x0 RO	**MFS Failure:** If this bit is set, Intel® ME informs BIOS that Intel® ME File System failure has been detected during recent Intel® ME boot.
5:4	0x0 RO	Reserved

3:1	0x0
	RO
		Recovery Cause: If ME1.HFS.Current State indicates that Intel® ME firmware is running in recovery mode these bits provide the cause of this mode:
		• 0 - Intel® ME recovery jumper asserted
		• 1 - Security strap override jumper asserted
		• 2 - Recovery forced with IPMI command
		• 3 - Invalid flash configuration, either:
		  • flash master access permissions configuration is wrong
		  • VSCC entry is missing or wrong
		  • flash erase block size in Intel® ME region configuration
		• 4 - Intel® ME internal error
		  Intel® ME could not start in operational mode because of some firmware problems.
		• 5..7 - Reserved for future extensions

0	0x0 RO	**BIST in Progress:** If this bit is set Intel® ME Built In Self-Test is in Progress.

52.2.19 Host General Status (HECI1_H_GS1)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status (H_GS1):** General status of Host. This field is not used by hardware.

52.2.20 PCI Power Management Capability ID (HECI1_PID)—Offset 50h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 50h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Capability (NEXT):** Indicates the location of the next capability item in the list. This is the Message Signaled Interrupts capability.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management.

52.2.21 PCI Power Management Capabilities (HECI1_PC)—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 52h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME Support (PSUP):** Indicates the states that can generate PME#. HECI can assert PME# from D3hot only.
10	0x0 RO	**D2 Support (D2S):** The D2 state is not supported for the HECI host controller.
9	0x0 RO	**D _Support (D1S):** The D1 state is not supported for the HECI host controller.
8:6	0x0 RO	**Aux_Current (AUXC):** Reports the maximum Suspend well current required when in the D3COLD state. Value of 0 is reported.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates whether device-specific initialization is required.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

52.2.22 PCI Power Management Control and Status (HECI1_PMCS)—Offset 54h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 54h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**PME Status (PMES):** The PME Status bit in HECI space can be set to '1' by CSE FW performing a write into CSE side register to set PMES. This bit is cleared by host CPU writing a '1' to it. CSE cannot clear this bit. Host CPU writes with value '0' have no effect on this bit.
14:9	0x0 RO	**Reserved (RSVD_14_9):** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, PME_assert and PME_deassert messages are sent over Sideband to PMC based on the PMES bit. When reset these messages may not be sent.
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that when the HECI host controller is transitioning from D3hot to D0 due to power state command, it does not perform and internal reset.
2	0x0 RO	**Reserved (RSVD_2_2):** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the HECI host controller and to set a new power state. The values are: • 00 - D0 state • 11 - D3HOT state. The D1 and D2 states are not supported for this HECI host controller. If software attempts to write an unsupported, optional state to this field, the write operation must complete normally on the bus; however, the data is discarded and no state change occurs. When in the D3HOT state, the HBA's configuration space is available, but the registers memory space is not. Additionally, interrupts are blocked. This field is visible to firmware through the H_PCI_CSR register, and changes to this field may be configured by the H_PCI_CSR register to generate an MSI to mIA.

52.2.23 General Status Shadow 2 (HECI1_GS_SHDW2)—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 2 (GSS2):** This field is host side shadow of CSE General Status 2 (CSE_GS2).

52.2.24 General Status Shadow 3 (HECI1_GS_SHDW3)—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 3 (GSS3):** This field is host side shadow of CSE General Status 3 (CSE_GS3).

52.2.25 General Status Shadow 4 (HECI1_GS_SHDW4)—Offset 68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 4 (GSS4):** This field is host side shadow of CSE General Status 4 (CSE_GS4).

52.2.26 General Status Shadow 5 (HECI1_GS_SHDW5)—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 5 (GSS5):** This field is host side shadow of CSE General Status 5 (CSE_GS5).

52.2.27 Host General Status 2 (HECI1_H_GS2)—Offset 70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 2 (H_GS2):** General status of Host. This field is not used by hardware.

52.2.28 Host General Status 3 (HECI1_H_GS3)—Offset 74h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 3 (H_GS3):** General status of Host. This field is not used by hardware.

52.2.29 Message Signaled Interrupt Identifiers (HECI1_MID)—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NEXT):** Indicates the next item in the list. This can be other capability pointers (such as PCI-X or PCI- Express) or it can be the last item in the list.
7:0	0x5 RO	**Capability ID (CID):** Indicates MSI.

52.2.30 Message Signaled Interrupt Message Control (HECI1_MC)—Offset 8Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 8Eh

Default: 0080h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Reserved (RSVD):** Reserved.
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages.
6:4	0x0 RO	**Multiple Message Enable (MME):** Not implemented, hardwired to 0.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not implemented, hardwired to 0.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and INTx virtual wires are not used to generate interrupts.

52.2.31 Message Signaled Interrupt Message Address (HECI1_MA)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DW aligned.
1:0	0x0 RO	**Reserved (RSVD):** Reserved.

52.2.32 Message Signaled Interrupt Upper Address (HECI1_MUA)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address (UADDR):** Upper 32 bits of the system specified message address. This register is optional and only implemented if MC.C64=1.

52.2.33 Message Signaled Interrupt Message Data (HECI1_MD)—Offset 98h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:0] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the FSB during the data phase of the MSI memory write transaction.

52.2.34 HECI Interrupt Delivery Mode (HECI1_HIDM)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:0] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved.
2	0x0 RW/1S	**HIDM Lock (HIDM_L):** Writing 1 to this bit locks the HIDM field.
1:0	0x0 RW/L	**HECI Interrupt Delivery Mode (HIDM):** These bits control what type of interrupt the HECI will send when CSE FW writes to set the CSE_IG bit. They are interpreted as follows: • 00 - Generate Legacy or MSI interrupt; • 01 - Generate SCI; • 10 - Generate SMI; This field may be locked by writing 1 to HIDM_L bit.

52.2.35 Host Extend Register Status (HECI1_HERS)—Offset BCh

This register is used to communicate the CSE FW measurement status information to host.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + BCh

Default: 40000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Extend Register Valid (ERV):** Set by FW after all FW has been loaded and the measurement data has been stored in HERx registers. If ERA field is SHA-1, the result of the extend operation is in HER:5-1. If ERA field is SHA-256, the result is in HER:8-1.
30	0x1 RO	**Extend Feature Present (EFP):** This bit is hardwired to 1 to allow driver software to easily detect the chipset supports the Extend Registers FW measurement feature.
29:4	0x0 RO	**Reserved (RSVD_29_4):** Reserved.
3:0	0x0 RO/V	**Extend Register Algorithm (ERA):** This field indicates the hash algorithm used in the FW measurement Extend operation. Encodings are: 0x0: SHA-1, 0x2: SHA-256. Other values: reserved. This field is set by FW with the used hash algorithm value when the ERV bit is set to 1. This field is meaningless when the ERV bit is 0. This field does NOT have any defined reset value.

52.2.36 Host Extend Register DW1. (HECI1_HER1)—Offset C0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW1 (ERDW1):** Reserved.

52.2.37 Host Extend Register DW2. (HECI1_HER2)—Offset C4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW2 (ERDW2):** Reserved.

52.2.38 Host Extend Register DW3. (HECI1_HER3)—Offset C8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW3 (ERDW3):** Reserved.

52.2.39 Host Extend Register DW4. (HECI1_HER4)—Offset CCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW4 (ERDW4):** Reserved.

52.2.40 Host Extend Register DW5. (HECI1_HER5)—Offset D0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW5 (ERDW5):** Reserved.

52.2.41 Host Extend Register DW6. (HECI1_HER6)—Offset D4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + D4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW6 (ERDW6):** Reserved.

52.2.42 Host Extend Register DW7. (HECI1_HER7)—Offset D8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + D8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW7 (ERDW7):** Reserved.

52.2.43 Host Extend Register DW8. (HECI1_HER8)—Offset DCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + DCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW8 (ERDW8):** Reserved.

52.2.44 Manufacturer's ID (HECI1_MANID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:0] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD_31_28):** Reserved.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Indicates the dot process.
23:16	0x0 RO/V	**Manufacturing Stepping ID (MSID):** This field is incremented for each stepping of the part. Note that this field can be used by software to differentiate steppings when Revision ID may not change.
15:8	0x0 RO/V	**Manufacturing ID (MID):** Set by Intel.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Indicates the process. The dot portion of the process is reflected in bits [27:24]. Note that this field can be used by software to differentiate steppings when Revision ID may not change.

52.3 Registers in Configuration Space—HECI2

AR Author and Tech Comm: HIDE this sub-chapter if the device has no such registers.

52.3.1 Identifiers (HECI2_ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 0h

Default: 19D48086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19d4 RO/V	**Device ID (DID):** Indicates what device number assigned by Intel.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates Intel is the vendor, assigned by the PCI SIG.

52.3.2 Command (HECI2_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD:** Reserved
10	0x0 RW	**Interrupt Disable (ID):** Disables this device from generating PCI line based interrupts. This bit does not have any effect on MSI operation.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not implemented, hardwired to 0.
8	0x0 RO	**SERR# Enable (SEE):** Not implemented, hardwired to 0.
7	0x0 RO	**Wait Cycle Enable (WCC):** Not implemented, hardwired to 0.
6	0x0 RO	**Parity Error Response Enable (PEE):** Not implemented, hardwired to 0.
5	0x0 RO	**VGA Palette Snooping Enable (VAG):** Not implemented, hardwired to 0
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not implemented, hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not implemented, hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the HECI host controller's ability to act as a system memory master for data transfers. When this bit is cleared, HECI bus master activity stops and any active DMA engines return to an idle condition. This bit is made visible to firmware through the H_PCI_CSR register, and changes to this bit may be configured by the H_PCI_CSR register to generate an MSI to mIA. When this bit is '0', HECI is blocked from generating MSI to the host CPU. Note that this bit does not block HECI accesses to CSE-UMA

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the HECI host controllers memory mapped register space.
0	0x0 RO	**I/O Space Enable (IOSE):** Not implemented, hardwired to 0.

52.3.3 Status (HECI2_STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Detected Parity Error (DPE):** Not implemented, hardwired to 0.
14	0x0 RO	**Signaled System Error (SSE):** Not implemented, hardwired to 0.
13	0x0 RO	**Received Master-Abort (RMA):** Not implemented, hardwired to 0.
12	0x0 RO	**Received Target Abort (RTA):** Not implemented, hardwired to 0.
11	0x0 RO	**Signaled Target-Abort (STA):** Not implemented, hardwired to 0.
10:9	0x0 RO	**DEVSEL# Timing (DEVT):** These bits are hardwired to 00.
8	0x0 RO	**Master Data Pariy Error Detected (DPD):** Not implemented, hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not implemented, hardwired to 0.
6	0x0 RO	**RSVD (RSVD_6_6):** Reserved
5	0x0 RO	**66 MHz Capable (C66):** Not implemented, hardwired to 0.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list, hardwired to 1.
3	0x0 RO/V	**Interrupt Status (IS):** Reflects the state of the INTx# signal at the input of the enable/disable circuit. This bit is a 1 when the INTx# is asserted. This bit is a 0 after the interrupt is cleared (independent of the state of the Interrupt Disable bit in the command register). ***Note:*** This bit is not set by an MSI.
2:0	0x0 RO	**RSVD (RSVD_2_0):** Reserved

52.3.4 Revision ID and Class Code (HECI2_RID_CC)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 8h

Default: 07800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Indicates the base class code of the HECI host controller device.
23:16	0x80 RO	**Sub Class Code (SCC):** Indicates the sub class code of the HECI host controller device.
15:8	0x0 RO	**Programming Interface (PI):** Indicates the programming interface of the HECI host controller device.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates stepping of the HECI host controller.

52.3.5 Cache Line Size (HECI2_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented, hardwired to 0.

52.3.6 Master Latency Timer (HECI2_MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Not implemented, hardwired to 0.

52.3.7 Header Type (HECI2_HTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + Eh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Multi-Function Device (MFD):** Indicates the HECI host controller is part of a multi- function device.
6:0	0x0 RO	**Header Layout (HL):** Indicates that the HECI host controller uses a target device layout.

52.3.8 Built In Self-Test (HECI2_BIST)—Offset Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**BIST Capable (BC):** Not implemented, hardwired to 0.
6:0	0x0 RO	**RSVD:** Reserved

52.3.9 HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Base Address Low (BA_LO):** Lower 32 bits of base address of register memory space.
11:4	0x0 RO	**Memory Size (MS):** This field is hardwired to 0 to indicate that HECI device requests 4KB of memory space.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not pre-fetchable
2:1	0x2 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 64-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

52.3.10 HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address High (BA_HI):** Upper 32 bits of base address of register memory space.

52.3.11 Sub System Identifiers (HECI2_SS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Indicates the sub- system identifier. This field should be programmed by BIOS during boot-up. Once written, this register becomes Read Only.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Indicates the sub-system vendor identifier. This field should be programmed by BIOS during boot- up. Once written, this register becomes Read Only.

52.3.12 Capabilities Pointer (HECI2_CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + 34h

Default: 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x50 RO	**Capability Pointer (CP):** Indicates the first capability pointer offset. It points to the PCI power management capability offset.

52.3.13 Interrupt Information (HECI2_INTR)—Offset 3Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO/V	**Interrupt Pin (IPIN):** This field indicates the virtual interrupt pin the HECI host controller uses. A value of 0x1/0x2/0x3/0x4 indicates that this function implements legacy interrupt on INTA/INTB/INTC/INTD, respectively. When legacy interrupt is not used this register should be set to 0x0.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this field.

52.3.14 Minimum Grant (HECI2_MGNT)—Offset 3Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + 3Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Grant (GNT):** Not implemented, hardwired to 0.

52.3.15 Maximum Latency (HECI2_MLAT)—Offset 3Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + 3Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Latency (LAT):** Not implemented, hardwired to 0.

52.3.16 Host Firmware Status (HECI2_HFS)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**BIOS MSG ACK:** Acknowledge for register based BIOS message in MEI 1 H_GS Register.
27:25	0x0 RO	**BIOS MSG ACK Data:** Message specific data for acknowledged BIOS message.
24:20	0x0 RO	Reserved
19:16	0x0 RO	**Operating Mode:** This field describes the current operating mode of Intel® ME. • 1:0 - Reserved • 2 - Debug Mode • 14:3 - Reserved • 15 - Intel® SPS firmware is running in Intel® ME
15:12	0x0 RO	**Error Code:** If set to nonzero value the Intel® ME firmware has encountered a fatal error and stopped normal operation. • 0 - No Error • 1 - Uncategorized Failure - The Intel® ME firmware has experienced an uncategorized error. Further details of the failure can be found in the Extended Status Data. • 2 - Disabled - Firmware was disabled on this platform. • 3 - Image Failure - The Intel® ME firmware stored in the system flash is not valid.
11	0x0 RO	**Update in Progress:** The bit is set if any type of Intel® ME firmware update is in progress.
10	0x0 RO	**Recovery BUP Load Fault:** This bit is set when firmware is not able to load recovery bring-up from the flash. It means that the recovery section in Intel® ME region on the SPI flash.
9	0x0 RO	**Init Complete:** When this but is not set firmware is still in initialization phase. When firmware has fully entered a stable state, this but is set to 1 and "Current State" field of this register provides the steady state of the Intel® ME subsystem.
8:6	0x0 RO	**Operating State:** This field describes the current operating state of Intel® ME. • 000 - Preboot • 001 - M0 with UMA • 010 - Reserved • 011 - Reserved • 100 - M3 without UMA • 101 - M0 without UMA - normal state for Intel® SPS firmware • 110 - Bring up • 111 - M0 without UMA but with error
5	0x0 RO	**FPT or Factory Defaults Bad:** This bit is set when the firmware discovers a bad checksum of Intel® ME region Flash Partition Table (FPT) or Factory Defaults. When this bit set, it may or may not have the error code shown in bit [15:12]. The system can get this bit clear only by re-flashing the whole Intel® ME region in the SPI Flash.
4	0x0 RO	**Manufacturing Mode:** When this bit is set, the platform is still in manufacturing mode. Host can use this bit to inform user that the platform is NOT READY for production yet. This but is set as long as Intel® ME Region access is not locked for flash masters other than Intel® ME. For shipping machine, this bit MUST be 0.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**Current State:** This field describes the current operation state of the firmware. • 0 - Reset - Intel® ME is in reset state, will exit this state within 1 millisecond • 1 - Initialization - Intel® ME is initializing, will exit this state within 2 seconds • 2 - Recovery - Intel® ME is in recovery mode, check ME1.GMES register to determine cause • 3 - Reserved • 4 - Disabled - Intel® ME functionality has been disabled, it executes idle loop • 5 - Operational - Intel® ME is in normal operational state • 6 - Reserved • 7 - State Transition - Intel® ME sets this state before starting a transition to a new Operating State. It is a temporary state, may appear on transition between Initialization and Operational.

52.3.17 General Status Shadow 1 (HECI2_GS_SHDW1)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**EOP Status:** This bit presents the Intel® ME notion of EOP status. If BIOS encounters this bit set to '1' during POST it signals an error in platform power flow.
30:28	0x0 RO	**Infrastructure Progress Code:** This field identifies the infrastructure progress code: • 0 - ROM - Intel® ME is in ROM phase • 1 - BUP - Intel® ME is in BRINGUP phase • 2 - uKernel - Intel® ME is in Micro Kernel phase • 3 - Policy Module - Intel® ME is in Policy Module phase • 4 - Other Module - Intel® ME is loading modules in M0 or M3 Operating State
27:16	0x0 RO	**Extended Status Data:** These bits provide extended status data for the current state of operating of the firmware. Or, if the firmware is in a fatal error state, these bits provide extended error code information.
15:13	0x0 RO	**Firmware Heartbeat:** This number increments approximately every second if Intel® ME firmware is running.
12	0x0 RO	Intel® ME Target Image Boot Fault • 0 - Target image loaded successfully • 1 - Target image boot failed, switched to backup image or recovery image
11:8	0x0 RO	Reserved
7	0x0 RO	**Warm Reset Request:** If this bit is set, Intel® ME informs BIOS that a warm reset is requested by Intel® ME.
6	0x0 RO	**MFS Failure:** If this bit is set, Intel® ME informs BIOS that Intel® ME File System failure has been detected during recent Intel® ME boot.
5:4	0x0 RO	Reserved

3:1	0x0
	RO
		Recovery Cause: If ME1.HFS.Current State indicates that Intel® ME firmware is running in recovery mode these bits provide the cause of this mode:
		• 0 - Intel® ME recovery jumper asserted
		• 1 - Security strap override jumper asserted
		• 2 - Recovery forced with IPMI command
		• 3 - Invalid flash configuration, either:
		  • flash master access permissions configuration is wrong
		  • VSCC entry is missing or wrong
		  • flash erase block size in Intel® ME region configuration
		• 4 - Intel® ME internal error
		  Intel® ME could not start in operational mode because of some firmware problems.
		• 5..7 - Reserved for future extensions

0	0x0 RO	**BIST in Progress:** If this bit is set Intel® ME Built In Self-Test is in Progress.

52.3.18 Host General Status (HECI2_H_GS1)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status (H_GS1):** General status of Host. This field is not used by hardware.

52.3.19 PCI Power Management Capability ID (HECI2_PID)—Offset 50h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 50h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Capability (NEXT):** Indicates the location of the next capability item in the list. This is the Message Signaled Interrupts capability.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management.

52.3.20 PCI Power Management Capabilities (HECI2_PC)—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 52h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME Support (PSUP):** Indicates the states that can generate PME#. HECI can assert PME# from D3hot only.
10	0x0 RO	**D2 Support (D2S):** The D2 state is not supported for the HECI host controller.
9	0x0 RO	**D _Support (D1S):** The D1 state is not supported for the HECI host controller.
8:6	0x0 RO	**Aux_Current (AUXC):** Reports the maximum Suspend well current required when in the D3COLD state. Value of 0 is reported.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates whether device-specific initialization is required.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

52.3.21 PCI Power Management Control and Status (HECI2_PMCS)—Offset 54h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 54h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**PME Status (PMES):** The PME Status bit in HECI space can be set to '1' by CSE FW performing a write into CSE side register to set PMES. This bit is cleared by host CPU writing a '1' to it. CSE cannot clear this bit. Host CPU writes with value '0' have no effect on this bit.
14:9	0x0 RO	**Reserved (RSVD_14_9):** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, PME_assert and PME_deassert messages are sent over Sideband to PMC based on the PMES bit. When reset these messages may not be sent.
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that when the HECI host controller is transitioning from D3hot to D0 due to power state command, it does not perform and internal reset.
2	0x0 RO	**Reserved (RSVD_2_2):** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the HECI host controller and to set a new power state. The values are: • 00 - D0 state • 11 - D3HOT state. The D1 and D2 states are not supported for this HECI host controller.

52.3.22 General Status Shadow 2 (HECI2_GS_SHDW2)—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 2 (GSS2):** This field is host side shadow of CSE General Status 2 (CSE_GS2).

52.3.23 General Status Shadow 3 (HECI2_GS_SHDW3)—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 3 (GSS3):** This field is host side shadow of CSE General Status 3 (CSE_GS3).

52.3.24 General Status Shadow 4 (HECI2_GS_SHDW4)—Offset 68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 4 (GSS4):** This field is host side shadow of CSE General Status 4 (CSE_GS4).

52.3.25 General Status Shadow 5 (HECI2_GS_SHDW5)—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 5 (GSS5):** This field is host side shadow of CSE General Status 5 (CSE_GS5).

52.3.26 Host General Status 2 (HECI2_H_GS2)—Offset 70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 2 (H_GS2):** General status of Host. This field is not used by hardware.

52.3.27 Host General Status 3 (HECI2_H_GS3)—Offset 74h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 3 (H_GS3):** General status of Host. This field is not used by hardware.

52.3.28 Message Signaled Interrupt Identifiers (HECI2_MID)—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NEXT):** Indicates the next item in the list. This can be other capability pointers (such as PCI-X or PCI- Express) or it can be the last item in the list.
7:0	0x5 RO	**Capability ID (CID):** Indicates MSI.

52.3.29 Message Signaled Interrupt Message Control (HECI2_MC)—Offset 8Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 8Eh

Default: 0080h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Reserved (RSVD):** Reserved.
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages.
6:4	0x0 RO	**Multiple Message Enable (MME):** Not implemented, hardwired to 0.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not implemented, hardwired to 0.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and INTx virtual wires are not used to generate interrupts.

52.3.30 Message Signaled Interrupt Message Address (HECI2_MA)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DW aligned.
1:0	0x0 RO	**Reserved (RSVD):** Reserved.

52.3.31 Message Signaled Interrupt Upper Address (HECI2_MUA)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address (UADDR):** Upper 32 bits of the system specified message address. This register is optional and only implemented if MC.C64=1.

52.3.32 Message Signaled Interrupt Message Data (HECI2_MD)—Offset 98h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:1] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the FSB during the data phase of the MSI memory write transaction.

52.3.33 HECI Interrupt Delivery Mode (HECI2_HIDM)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:1] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved.
2	0x0 RW/1S	**HIDM Lock (HIDM_L):** Writing 1 to this bit locks the HIDM field.
1:0	0x0 RW/L	**HECI Interrupt Delivery Mode (HIDM):** These bits control what type of interrupt the HECI will send when CSE FW writes to set the CSE_IG bit. They are interpreted as follows: • 00 - Generate Legacy or MSI interrupt; • 01 - Generate SCI; • 10 - Generate SMI; This field may be locked by writing 1 to HIDM_L bit.

52.3.34 Manufacturer's ID (HECI2_MANID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:1] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD_31_28):** Reserved.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Indicates the dot process.
23:16	0x0 RO/V	**Manufacturing Stepping ID (MSID):** This field is incremented for each stepping of the part. ***Note:*** This field can be used by software to differentiate steppings when Revision ID may not change.
15:8	0x0 RO/V	**Manufacturing ID (MID):** This field is set by Intel.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Indicates the process. The dot portion of the process is reflected in bits [27:24]. ***Note:*** This field can be used by software to differentiate steppings when Revision ID may not change.

52.4 Registers in Configuration Space—HECI3

52.4.1 Identifiers (HECI3_ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 0h

Default: 19D68086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19d6 RO/V	**Device ID (DID):** Indicates what device number assigned by Intel.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates Intel is the vendor, assigned by the PCI SIG.

52.4.2 Command (HECI3_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD:** Reserved
10	0x0 RW	**Interrupt Disable (ID):** Disables this device from generating PCI line based interrupts. This bit does not have any effect on MSI operation.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not implemented, hardwired to 0.
8	0x0 RO	**SERR# Enable (SEE):** Not implemented, hardwired to 0.
7	0x0 RO	**Wait Cycle Enable (WCC):** Not implemented, hardwired to 0.
6	0x0 RO	**Parity Error Response Enable (PEE):** Not implemented, hardwired to 0.
5	0x0 RO	**VGA Palette Snooping Enable (VAG):** Not implemented, hardwired to 0
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not implemented, hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not implemented, hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the HECI host controller's ability to act as a system memory master for data transfers. When this bit is cleared, HECI bus master activity stops and any active DMA engines return to an idle condition. This bit is made visible to firmware through the H_PCI_CSR register, and changes to this bit may be configured by the H_PCI_CSR register to generate an MSI to mIA. When this bit is '0', HECI is blocked from generating MSI to the host CPU. ***Note:*** This bit does not block HECI accesses to CSE-UMA
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the HECI host controllers memory mapped register space.
0	0x0 RO	**I/O Space Enable (IOSE):** Not implemented, hardwired to 0.

52.4.3 Status (HECI3_STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Detected Parity Error (DPE):** Not implemented, hardwired to 0.
14	0x0 RO	**Signaled System Error (SSE):** Not implemented, hardwired to 0.
13	0x0 RO	**Received Master-Abort (RMA):** Not implemented, hardwired to 0.
12	0x0 RO	**Received Target Abort (RTA):** Not implemented, hardwired to 0.
11	0x0 RO	**Signaled Target-Abort (STA):** Not implemented, hardwired to 0.
10:9	0x0 RO	**DEVSEL# Timing (DEVT):** These bits are hardwired to 00.
8	0x0 RO	**Master Data Parity Error Detected (DPD):** Not implemented, hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not implemented, hardwired to 0.
6	0x0 RO	**RSVD (RSVD_6_6):** Reserved
5	0x0 RO	**66 MHz Capable (C66):** Not implemented, hardwired to 0.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list, hardwired to 1.
3	0x0 RO/V	**Interrupt Status (IS):** Reflects the state of the INTx# signal at the input of the enable/disable circuit. This bit is a 1 when the INTx# is asserted. This bit is a 0 after the interrupt is cleared (independent of the state of the Interrupt Disable bit in the command register). ***Note:*** This bit is not set by an MSI.
2:0	0x0 RO	**RSVD (RSVD_2_0):** Reserved

52.4.4 Revision ID and Class Code (HECI3_RID_CC)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 8h

Default: 07800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Indicates the base class code of the HECI host controller device.
23:16	0x80 RO	**Sub Class Code (SCC):** Indicates the sub class code of the HECI host controller device.
15:8	0x0 RO	**Programming Interface (PI):** Indicates the programming interface of the HECI host controller device.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates stepping of the HECI host controller.

52.4.5 Cache Line Size (HECI3_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented, hardwired to 0.

52.4.6 Master Latency Timer (HECI3_MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Not implemented, hardwired to 0.

52.4.7 Header Type (HECI3_HTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + Eh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Multi-Function Device (MFD):** Indicates the HECI host controller is part of a multi- function device.
6:0	0x0 RO	**Header Layout (HL):** Indicates that the HECI host controller uses a target device layout.

52.4.8 Built In Self-Test (HECI3_BIST)—Offset Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**BIST Capable (BC):** Not implemented, hardwired to 0.
6:0	0x0 RO	**RSVD:** Reserved

52.4.9 HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Base Address Low (BA_LO):** Lower 32 bits of base address of register memory space.
11:4	0x0 RO	**Memory Size (MS):** This field is hardwired to 0 to indicate that HECI device requests 4KB of memory space.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not pre-fetchable
2:1	0x2 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 64-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

52.4.10 HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address High (BA_HI):** Upper 32 bits of base address of register memory space.

52.4.11 Sub System Identifiers (HECI3_SS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Indicates the sub- system identifier. This field should be programmed by BIOS during boot-up. Once written, this register becomes Read Only.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Indicates the sub-system vendor identifier. This field should be programmed by BIOS during boot- up. Once written, this register becomes Read Only.

52.4.12 Capabilities Pointer (HECI3_CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + 34h

Default: 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x50 RO	**Capability Pointer (CP):** Indicates the first capability pointer offset. It points to the PCI power management capability offset.

52.4.13 Interrupt Information (HECI3_INTR)—Offset 3Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO/V	**Interrupt Pin (IPIN):** This field indicates the virtual interrupt pin the HECI host controller uses. A value of 0x1/0x2/0x3/0x4 indicates that this function implements legacy interrupt on INTA/INTB/INTC/INTD, respectively. When legacy interrupt is not used this register should be set to 0x0.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this field.

52.4.14 Minimum Grant (HECI3_MGNT)—Offset 3Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + 3Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Grant (GNT):** Not implemented, hardwired to 0.

52.4.15 Maximum Latency (HECI3_MLAT)—Offset 3Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + 3Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Latency (LAT):** Not implemented, hardwired to 0.

52.4.16 Host Firmware Status (HECI3_HFS)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**BIOS MSG ACK:** Acknowledge for register based BIOS message in MEI 1 H_GS Register.
27:25	0x0 RO	**BIOS MSG ACK Data:** Message specific data for acknowledged BIOS message.
24:20	0x0 RO	Reserved
19:16	0x0 RO	**Operating Mode:** This field describes the current operating mode of Intel® ME. • 1:0 - Reserved • 2 - Debug Mode • 14:3 - Reserved • 15 - Intel® SPS firmware is running in Intel® ME
15:12	0x0 RO	**Error Code:** If set to nonzero value the Intel® ME firmware has encountered a fatal error and stopped normal operation. • 0 - No Error • 1 - Uncategorized Failure - The Intel® ME firmware has experienced an uncategorized error. Further details of the failure can be found in the Extended Status Data. • 2 - Disabled - Firmware was disabled on this platform. • 3 - Image Failure - The Intel® ME firmware stored in the system flash is not valid.
11	0x0 RO	**Update in Progress:** The bit is set if any type of Intel® ME firmware update is in progress.
10	0x0 RO	**Recovery BUP Load Fault:** This bit is set when firmware is not able to load recovery bring-up from the flash. It means that the recovery section in Intel® ME region on the SPI flash.
9	0x0 RO	**Init Complete:** When this but is not set firmware is still in initialization phase. When firmware has fully entered a stable state, this but is set to 1 and "Current State" field of this register provides the steady state of the Intel® ME subsystem.
8:6	0x0 RO	**Operating State:** This field describes the current operating state of Intel® ME. • 000 - Preboot • 001 - M0 with UMA • 010 - Reserved • 011 - Reserved • 100 - M3 without UMA • 101 - M0 without UMA - normal state for Intel® SPS firmware • 110 - Bring up • 111 - M0 without UMA but with error
5	0x0 RO	**FPT or Factory Defaults Bad:** This bit is set when the firmware discovers a bad checksum of Intel® ME region Flash Partition Table (FPT) or Factory Defaults. When this bit set, it may or may not have the error code shown in bit [15:12]. The system can get this bit clear only by re-flashing the whole Intel® ME region in the SPI Flash.
4	0x0 RO	**Manufacturing Mode:** When this bit is set, the platform is still in manufacturing mode. Host can use this bit to inform user that the platform is NOT READY for production yet. This but is set as long as Intel® ME Region access is not locked for flash masters other than Intel® ME. For shipping machine, this bit MUST be 0.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**Current State:** This field describes the current operation state of the firmware. • 0 - Reset - Intel® ME is in reset state, will exit this state within 1 millisecond • 1 - Initialization - Intel® ME is initializing, will exit this state within 2 seconds • 2 - Recovery - Intel® ME is in recovery mode, check ME1.GMES register to determine cause • 3 - Reserved • 4 - Disabled - Intel® ME functionality has been disabled, it executes idle loop • 5 - Operational - Intel® ME is in normal operational state • 6 - Reserved • 7 - State Transition - Intel® ME sets this state before starting a transition to a new Operating State. It is a temporary state, may appear on transition between Initialization and Operational.

52.4.17 General Status Shadow 1 (HECI3_GS_SHDW1)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**EOP Status:** This bit presents the Intel® ME notion of EOP status. If BIOS encounters this bit set to '1' during POST it signals an error in platform power flow.
30:28	0x0 RO	**Infrastructure Progress Code:** This field identifies the infrastructure progress code: • 0 - ROM - Intel® ME is in ROM phase • 1 - BUP - Intel® ME is in BRINGUP phase • 2 - uKernel - Intel® ME is in Micro Kernel phase • 3 - Policy Module - Intel® ME is in Policy Module phase • 4 - Other Module - Intel® ME is loading modules in M0 or M3 Operating State
27:16	0x0 RO	**Extended Status Data:** These bits provide extended status data for the current state of operating of the firmware. Or, if the firmware is in a fatal error state, these bits provide extended error code information.
15:13	0x0 RO	**Firmware Heartbeat:** This number increments approximately every second if Intel® ME firmware is running.
12	0x0 RO	Intel® ME Target Image Boot Fault • 0 - Target image loaded successfully • 1 - Target image boot failed, switched to backup image or recovery image
11:8	0x0 RO	Reserved
7	0x0 RO	**Warm Reset Request:** If this bit is set, Intel® ME informs BIOS that a warm reset is requested by Intel® ME.
6	0x0 RO	**MFS Failure:** If this bit is set, Intel® ME informs BIOS that Intel® ME File System failure has been detected during recent Intel® ME boot.
5:4	0x0 RO	Reserved

3:1	0x0
	RO
		Recovery Cause: If ME1.HFS.Current State indicates that Intel® ME firmware is running in recovery mode these bits provide the cause of this mode:
		• 0 - Intel® ME recovery jumper asserted
		• 1 - Security strap override jumper asserted
		• 2 - Recovery forced with IPMI command
		• 3 - Invalid flash configuration, either:
		  • flash master access permissions configuration is wrong
		  • VSCC entry is missing or wrong
		  • flash erase block size in Intel® ME region configuration
		• 4 - Intel® ME internal error
		  Intel® ME could not start in operational mode because of some firmware problems.
		• 5..7 - Reserved for future extensions

0	0x0 RO	**BIST in Progress:** If this bit is set Intel® ME Built In Self-Test is in Progress.

52.4.18 Host General Status (HECI3_H_GS1)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status (H_GS1):** General status of Host. This field is not used by hardware.

52.4.19 PCI Power Management Capability ID (HECI3_PID)—Offset 50h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 50h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Capability (NEXT):** Indicates the location of the next capability item in the list. This is the Message Signaled Interrupts capability.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management.

52.4.20 PCI Power Management Capabilities (HECI3_PC)—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 52h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME Support (PSUP):** Indicates the states that can generate PME#. HECI can assert PME# from D3hot only.
10	0x0 RO	**D2 Support (D2S):** The D2 state is not supported for the HECI host controller.
9	0x0 RO	**D _Support (D1S):** The D1 state is not supported for the HECI host controller.
8:6	0x0 RO	**Aux_Current (AUXC):** Reports the maximum Suspend well current required when in the D3COLD state. Value of 0 is reported.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates whether device-specific initialization is required.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

52.4.21 PCI Power Management Control and Status (HECI3_PMCS)—Offset 54h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 54h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**PME Status (PMES):** The PME Status bit in HECI space can be set to '1' by CSE FW performing a write into CSE side register to set PMES. This bit is cleared by host CPU writing a '1' to it. CSE cannot clear this bit. Host CPU writes with value '0' have no effect on this bit.
14:9	0x0 RO	**Reserved (RSVD_14_9):** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, PME_assert and PME_deassert messages are sent over Sideband to PMC based on the PMES bit. When reset these messages may not be sent.
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that when the HECI host controller is transitioning from D3hot to D0 due to power state command, it does not perform and internal reset.
2	0x0 RO	**Reserved (RSVD_2_2):** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the HECI host controller and to set a new power state. The values are: • 00 - D0 state • 11 - D3HOT state. The D1 and D2 states are not supported for this HECI host controller.

52.4.22 General Status Shadow 2 (HECI3_GS_SHDW2)—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 2 (GSS2):** This field is host side shadow of CSE General Status 2 (CSE_GS2).

52.4.23 General Status Shadow 3 (HECI3_GS_SHDW3)—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 3 (GSS3):** This field is host side shadow of CSE General Status 3 (CSE_GS3).

52.4.24 General Status Shadow 4 (HECI3_GS_SHDW4)—Offset 68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 4 (GSS4):** This field is host side shadow of CSE General Status 4 (CSE_GS4).

52.4.25 General Status Shadow 5 (HECI3_GS_SHDW5)—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 5 (GSS5):** This field is host side shadow of CSE General Status 5 (CSE_GS5).

52.4.26 Host General Status 2 (HECI3_H_GS2)—Offset 70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 2 (H_GS2):** General status of Host. This field is not used by hardware.

52.4.27 Host General Status 3 (HECI3_H_GS3)—Offset 74h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 3 (H_GS3):** General status of Host. This field is not used by hardware.

52.4.28 Message Signaled Interrupt Identifiers (HECI3_MID)—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NEXT):** Indicates the next item in the list. This can be other capability pointers (such as PCI-X or PCI- Express) or it can be the last item in the list.
7:0	0x5 RO	**Capability ID (CID):** Indicates MSI.

52.4.29 Message Signaled Interrupt Message Control (HECI3_MC)—Offset 8Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 8Eh

Default: 0080h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Reserved (RSVD):** Reserved.
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages.
6:4	0x0 RO	**Multiple Message Enable (MME):** Not implemented, hardwired to 0.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not implemented, hardwired to 0.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and INTx virtual wires are not used to generate interrupts.

52.4.30 Message Signaled Interrupt Message Address (HECI3_MA)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DW aligned.
1:0	0x0 RO	**Reserved (RSVD):** Reserved.

52.4.31 Message Signaled Interrupt Upper Address (HECI3_MUA)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address (UADDR):** Upper 32 bits of the system specified message address. This register is optional and only implemented if MC.C64=1.

52.4.32 Message Signaled Interrupt Message Data (HECI3_MD)—Offset 98h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:24, F:4] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the FSB during the data phase of the MSI memory write transaction.

52.4.33 HECI Interrupt Delivery Mode (HECI3_HIDM)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:24, F:4] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved.
2	0x0 RW/1S	**HIDM Lock (HIDM_L):** Writing 1 to this bit locks the HIDM field.
1:0	0x0 RW/L	**HECI Interrupt Delivery Mode (HIDM):** These bits control what type of interrupt the HECI will send when CSE FW writes to set the CSE_IG bit. They are interpreted as follows: • 00 - Generate Legacy or MSI interrupt; • 01 - Generate SCI; • 10 - Generate SMI; This field may be locked by writing 1 to HIDM_L bit.

52.4.34 Manufacturer's ID (HECI3_MANID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:4] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD_31_28):** Reserved.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Indicates the dot process.
23:16	0x0 RO/V	**Manufacturing Stepping ID (MSID):** This field is incremented for each stepping of the part. ***Note:*** Note that this field can be used by software to differentiate steppings when Revision ID may not change.
15:8	0x0 RO/V	**Manufacturing ID (MID):** This field is set by Intel.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Indicates the process. The dot portion of the process is reflected in bits [27:24]. ***Note:*** This field can be used by software to differentiate steppings when Revision ID may not change. This field is set by a special IOSF SB message (SetIDValue).

52.5 Registers in Configuration Space—KT (Host)

52.5.1 Device ID and Vendor ID (KT_HOST_DID_VID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 0h

Default: 19D58086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19d5 RO/V	**Device ID (DID):** This field identifies the particular device.
15:0	0x8086 RO	**Vendor ID (VID):** This field identifies the manufacturer of the device. Valid vendor identifiers are allocated by the PCI SIG to ensure uniqueness. The value of 0x8086 indicates Intel

52.5.2 Status and Command (KT_HOST_STS_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 4h

Default: 00B00000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Detected Parity Error (DPE):** Not implemented. Hardwired to 0.
30	0x0 RO	**Signaled System Error (SSE):** Not implemented. Hardwired to 0.
29	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit must be set by a master device whenever its transaction (except for Special Cycle) is completed with Unsupported Request Completion Status (a.k.a. Master-Abort). All master devices must implement this bit.
28	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit must be set by a master device whenever its transaction is completed with Completer Abort Completion Status (a.k.a. Target-Abort). All master devices must implement this bit.
27	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit must be set by a target device whenever it completes a Posted or Non-Posted transaction with a Completer Abort (a.k.a. Target-Abort) error. Devices that will never signal Completer Abort (a.k.a. Target-Abort) do not need to implement this bit.
26:25	0x0 RO	**Devsel Timing (DEVT):** These bits encode the timing of DEVSEL#. There are three allowable timings for assertion of DEVSEL# as described below: • 00b: fast • 01b: medium • 10b: slow • 11b: reserved These bits are read-only and must indicate the slowest time that a device asserts DEVSEL# for any bus command except Configuration Read and Configuration Write. Hardwired to 00b.
24	0x0 RO	**Master Data Parity Error (MDPE):** Not implemented. Hardwired to 0.
23	0x1 RO	**Fast Back to Back Capable (FBTBC):** This bit indicates whether or not the target is capable of accepting fast back-to-back transactions when the transactions are not to the same agent. This bit can be set to 1 if the device can accept these transactions and must be set to 0 otherwise. Hardwired to 1.
22	0x0 RO	**Reserved (RSVD3):** Reserved (RSVD)
21	0x1 RO	**66 Mhz Capable (MCAP):** This bit indicates whether or not this device is capable of running at 66 MHz. • A value of 0 indicates 33 MHz. • A value of 1 indicates that the device is 66 MHz capable. Hardwired to 1.
20	0x1 RO	**Capabilities List (CAPL):** This optional read-only bit indicates whether or not this device implements the pointer for a New Capabilities linked list at offset 34h. A value of zero indicates that no New Capabilities linked list is available. A value of one indicates that the value read at offset 34h is a pointer in Configuration Space to a linked list of new capabilities.
19	0x0 RO	**Interrupt Status (INTS):** This read-only bit reflects the state of the interrupt in the device/function. Only when the Interrupt Disable bit in the command register is a 0 and this Interrupt Status bit is a 1, will the device's/function's INTx# signal be asserted. Setting the Interrupt Disable bit to a 1 has no effect on the state of this bit. Read-only and hardwired to 0 for a device that does NOT support pin-based interrupt.
18:16	0x0 RO	**Reserved (RSVD2):**

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD1):**
10	0x0 RW	**Interrupt Disable (INTD):** This bit disables the device/function from asserting INTx#. A value of 0 enables the assertion of its INTx# signal. A value of 1 disables the assertion of its INTx# signal. This bit's state after RST# is 0.
9	0x0 RO	**Fast Back to Back Enable (FBTBEN):** Not implemented. Hardwired to 0.
8	0x0 RO	**System Error Enable (SERREN):** Not implemented. Hardwired to 0.
7	0x0 RO	**Reserved (RSVD0):**
6	0x0 RO	**Parity Error Response (PERRR):** Not implemented. Hardwired to 0.
5	0x0 RO	**VGA Palette Snoop (VGAPS):** Not implemented. Hardwired to 0.
4	0x0 RO	**Memory Write and Invalidate Enable (MWRIEN):** Not implemented. Hardwired to 0.
3	0x0 RO	**Special Cycles (SPCYC):** Not implemented. Hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the ability of a PCI device to issue Memory and I/O Read/Write Requests, and the ability of a PCI bridge to forward Memory and I/O Read/Write Requests in the Upstream direction. When this bit is Set, the PCI device function is allowed to issue Memory or I/O Requests. When this bit is Clear, the PCI device function is not allowed to issue any Memory or I/O Requests. ***Note:*** As MSI/MSI-X interrupt Messages are in-band memory writes, setting the Bus Master Enable bit to 0b disables MSI/MSI-X interrupt Messages as well. Requests other than Memory or I/O Requests are not controlled by this bit. Default value of this bit is 0b. This bit is hardwired to 0b if a PCI device function does not generate Memory or I/O Requests. Default value of this bit is 0b.
1	0x0 RW	**Memory Space Enable (MSE):** Controls a device's response to Memory Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to Memory Space accesses. State after RST# is 0.
0	0x0 RW	**IO Space Enable (IOSE):** Controls a device's response to I/O Space accesses. A value of 0 disables the device response. A value of 1 allows the device to respond to I/O Space accesses. State after RST# is 0.

52.5.3 Class Code and Revision ID (KT_HOST_CC_RID)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 8h

Default: 07000200h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Identifies the Base Class Code of an external 16550-compatible serial controller device driver.
23:16	0x0 RO	**Sub-Class Code (SCC):** Identifies the Sub-Class Code of an external 16550-compatible serial controller device driver.
15:8	0x2 RO	**Programming Interface (PI):** Identifies the Programming Interface of an external 16550-compatible serial controller device driver.
7:0	0x0 RO/V	**Revision ID (RID):** This register specifies a device specific revision identifier. The value is chosen by the vendor. Zero is an acceptable value. This field should be viewed as a vendor defined extension to the Device ID.

52.5.4 BIST, Header Type, Latency Timer, and Cache Line Size (KT_HOST_BIST_HTYPE_LT_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + Ch

Default: 00800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Built In Self Test (BIST):** Not implemented. Hardwired to 0.
23	0x1 RO/V	**Header Type 1 (HTYPE1):** This bit identifies whether or not the device contains multiple functions. • If the bit is 0, then the device is single function. • If the bit is 1, then the device has multiple functions.
22:16	0x0 RO	**Header Type 0 (HTYPE0):** This field identifies the layout of the second part of the predefined header (beginning at byte 10h in Configuration Space). • The encoding 00h specifies the non-bridge Configuration Space Header. • The encoding 01h specifies the PCI-to-PCI bridge Configuration Space Header. • The encoding 02h specifies the CardBus bridge Configuration Space Header. • All other encodings are reserved. Hardwired to 0 to identify the non-bridge Configuration Space Header.
15:8	0x0 RO	**Latency Timer (LT):** Not implemented. Hardwired to 0.
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented. Hardwired to 0.

52.5.5 KT IO BAR (KT_HOST_IOBAR)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 10h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region
2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 8B of IO space
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

52.5.6 KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Memory BAR (MEMBAR):** Software programs this register with the base address of the device's memory region
11:4	0x0 RO	**Memory Size (MEMSIZE):** Hardwired to 0 to indicate 4KB of memory space
3	0x0 RO	**Prefetchable (PREFETCH):** A device can mark a range as prefetchable if there are no side effects on reads, the device returns all bytes on reads regardless of the byte enables. Hardwired to 0 to indicate the device's memory space as non-prefetchable.
2:1	0x0 RO	**Type (TYP):** Hardwired to 0 to indicate that Base register is 32 bits wide and mapping can be done anywhere in the 32-bit Memory Space.
0	0x0 RO	**Memory Space Indicator (MEMSPACE):** Hardwired to 0 to identify a Memory BAR.

52.5.7 Cardbus CIS Pointer (KT_HOST_CCP)—Offset 28h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Cardbus CIS Pointer (CCP):** Not implemented. Hardwired to 0.

52.5.8 Subsystem ID and Subsystem Vendor ID (KT_HOST_SID_SVID)—Offset 2Ch

These registers are used to uniquely identify the add-in card or subsystem where the PCI device resides. They provide a mechanism for add-in card vendors to distinguish their add-in cards from one another even though the add-in cards may have the same PCI controller on them (and, therefore, the same Vendor ID and Device ID).

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 2Ch

Default: 00008086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SID):** Value of this field is vendor-specific. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SID should have its own lock.
15:0	0x8086 RW/O	**Subsystem Vendor ID (SVID):** This field identifies the vendor of the add-in card or subsystem. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SVID should have its own lock.

52.5.9 Expansion ROM Base Address (KT_HOST_XRBAR)—Offset 30h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Expansion ROM Base Address (XRBAR):** Not implemented. Hardwired to 0.

52.5.10 Capabilities List Pointer (KT_HOST_CAPP)—Offset 34h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 34h

Default: 00000040h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):**
7:0	0x40 RO	**Capabilities Pointer (CAPP):** Indicates the pointer for the first entry in the capabilities list which is the MSI Capability.

52.5.11 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (KT_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 3Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Maximum Latency (MAXL):** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Minimum Grant (MING):** Not implemented. Hardwired to 0.
15:8	0x0 RO/V	**Interrupt Pin (INTP):** This register specifies which interrupt pin KT uses in PCI interrupt mode. Value Decoding • 00h The function does NOT use an interrupt pin. • 01h INTA • 02h INTB • 03h INTC • 04h INTD • 05h - FFh Reserved.
7:0	0x0 RW	**Interrupt Line (INTL):** This register is used to communicate interrupt line routing information. POST software will write the routing information into this register as it initializes and configures the system. The value in this register tells which input of the system interrupt controller(s) the device's interrupt pin is connected to. The device itself does not use this value, rather it is used by device drivers and operating systems. Device drivers and operating systems can use this information to determine priority and vector information. Values in this register are system architecture specific.

52.5.12 MSI Message Control, Next Pointer and Capability ID (KT_HOST_MSIMC_MSINP_MSICID)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 40h

Default: 00805005h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**Reserved (RSVD):**
24	0x0 RO	**Per Vector Masking Capable (PVMC):** Not implemented. Hardwired to 0 to indicate the function does NOT support MSI per-vector masking.
23	0x1 RO	**64 bit address capable (XAC):** Hardwired to 1 to indicate the function is capable of sending a 64-bit message address.
22:20	0x0 RW	**Multiple Message Enable (MMEN):** Encoded number of interrupt vectors allocated by SW. This field is RW for software compatibility, but only one interrupt vector is ever sent by the function.
19:17	0x0 RO	**Multiple Message Capable (MMC):** Encoded number of interrupt vectors requested by a device. Hardwired to 0 to indicate one requested interrupt vector.
16	0x0 RW	**MSI Enable (MSIE):** If set, MSI interrupt delivery is enabled whereas pin-based interrupt delivery SHALL be disabled. If cleared, prior to returning the configuration write (that clears this field) completion, the function must send any pending MSI(s).
15:8	0x50 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 50h to point to the PM Capability list
7:0	0x5 RO	**Capability ID (CID):** Hardwired to 05h to indicate the linked list item as the MSI Capability registers

52.5.13 MSI Message Address (KT_HOST_MSIMA)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** 32-bit DW-aligned MSI message address.
1:0	0x0 RO	**Reserved (RSVD):**

52.5.14 MSI Message Upper Address (KT_HOST_MSIMUA)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Upper 32-bit of a 64-bit DW-aligned MSI message address.

52.5.15 MSI Message Data (KT_HOST_MSIMD)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):**
15:0	0x0 RW	**Message Data (MD):** MSI Message Data

52.5.16 Power Management Capabilities, Next Pointer and Capability ID (KT_HOST_PMCAP_PMNP_PMCID)—Offset 50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 50h

Default: 00230001h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**PME Support (PMES):** This 5-bit field indicates the power states in which the function may assert PME#. A value of 0b for any bit indicates that the function is not capable of asserting the PME# signal while in that power state. • bit(27) X XXX1b - PME# can be asserted from D0 • bit(28) X XX1Xb - PME# can be asserted from D1 • bit(29) X X1XXb - PME# can be asserted from D2 • bit(30) X 1XXXb - PME# can be asserted from D3hot • bit(31) 1 XXXXb - PME# can be asserted from D3cold
26	0x0 RO	**D2 Support (D2S):** Hardwired to 0 to indicate that this device does not support D2
25	0x0 RO	**D1 Support (D1S):** Hardwired to 0 to indicate that this device does not support D1
24:22	0x0 RO	**Aux Current (AUXC):** Not implemented. Hardwired to 0.
21	0x1 RO	**Device Specific Initialization (DSI):** indicates whether special initialization of this function is required (beyond the standard PCI configuration header) before the generic class device driver is able to use it. A 1 indicates that the function requires a device specific initialization sequence following transition to the D0 uninitialized state. Hardwired to 1 to indicate Device Specific Initialization is required.
20	0x0 RO	**Reserved (RSVD):**
19	0x0 RO	**PME Clock (PMECLK):** Not implemented. Hardwired to 0.
18:16	0x3 RO	**Version (VER):** Hardwired to value of 011b indicates that this function complies with rev 1.2 of PCI Power Management Interface Spec
15:8	0x0 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 0 to indicate no more linked list item.
7:0	0x1 RO	**Capability ID (CID):** Hardwired to 01h to indicate the linked list item as the PCI Power Management registers

52.5.17 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (KT_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + 54h

Default: 00000008h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Data:** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Control/Status Register Bridge Support Extensions (CSRBSE):** Not implemented. Hardwired to 0.
15	0x0 RO	**PME Status (PMESTS):** This bit is set when the function would normally assert the PME signal independent of the state of the PME_En bit. • Writing a 1 to this bit will clear it and cause the function to stop asserting a PME (if enabled). • Writing a 0 has no effect. If the function supports PME from D3cold, then this bit is sticky and must be explicitly cleared by the operating system each time the operating system is initially loaded. Not implemented. Hardwired to 0.
14:13	0x0 RO	**Data Scale (DS):** Not implemented. Hardwired to 0.
12:9	0x0 RO	**Data Select (DSEL):** Not implemented. Hardwired to 0.
8	0x0 RO	**PME Enable (PMEEN):** A 1 enables the function to assert PME. When 0, PME assertion is disabled. This bit defaults to 0 if the function does not support PME generation from D3cold. If the function supports PME from D3cold then this bit is sticky and must be explicitly cleared by the operating system each time it is initially loaded. Not implemented. Hardwired to 0.
7:4	0x0 RO	**Reserved (RSVD1):**
3	0x1 RO	**No Soft Reset (NSR):** When set to 1, this bit indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. Configuration Context is preserved. Upon transition from the D3hot to the D0 Initialized state, no additional operating system intervention is required to preserve Configuration Context beyond writing the PowerState bits.
2	0x0 RO	**Reserved (RSVD0):**
1:0	0x0 RW	**Power State (PWRST):** This 2-bit field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the field values is given below: • 00b - D0 • 01b - D1 • 10b - D2 • 11b - D3hot If software attempts to write an unsupported, optional state to this field, the write operation must complete normally on the bus; however, the data is discarded and no state change occurs.

52.5.18 Process Stepping Information (KT_HOST_PSI)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:3] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Reserved.
23:16	0x0 RO/V	**Manufacturing Stepping (MSID):** Reserved.
15:8	0x0 RO/V	**Manufacturing ID (MID):** Reserved.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Reserved.

52.6 Registers in Configuration Space—IDE (Host)

AR Author and Tech Comm: HIDE this sub-chapter if the device has no such registers.

52.6.1 Device ID and Vendor ID (IDE_HOST_DID_VID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 0h

Default: 19EA8086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19ea RO/V	**Device ID (DID):** This field identifies the particular device.
15:0	0x8086 RO	**Vendor ID (VID):** This field identifies the manufacturer of the device. Valid vendor identifiers are allocated by the PCI SIG to ensure uniqueness. The value of 0x8086 indicates Intel

52.6.2 Status and Command (IDE_HOST_STS_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 4h

Default: 00B00000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Detected Parity Error (DPE):** Not implemented. Hardwired to 0.
30	0x0 RO	**Signaled System Error (SSE):** Not implemented. Hardwired to 0.
29	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit must be set by a master device whenever its transaction (except for Special Cycle) is completed with Unsupported Request Completion Status (a.k.a. Master-Abort). All master devices must implement this bit.
28	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit must be set by a master device whenever its transaction is completed with Completer Abort Completion Status (a.k.a. Target-Abort). All master devices must implement this bit.
27	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit must be set by a target device whenever it completes a Posted or Non-Posted transaction with a Completer Abort (a.k.a. Target-Abort) error. Devices that will never signal Completer Abort (a.k.a. Target-Abort) do not need to implement this bit.
26:25	0x0 RO	**Devsel Timing (DEVT):** These bits encode the timing of DEVSEL#. There are three allowable timings for assertion of DEVSEL# as described below: • 00b: fast; • 01b: medium; • 10b: slow; • 11b: reserved. These bits are read-only and must indicate the slowest time that a device asserts DEVSEL# for any bus command except Configuration Read and Configuration Write. Hardwired to 00b.
24	0x0 RO	**Master Data Parity Error (MDPE):** Not implemented. Hardwired to 0.
23	0x1 RO	**Fast Back to Back Capable (FBTBC):** This bit indicates whether or not the target is capable of accepting fast back-to-back transactions when the transactions are not to the same agent. This bit can be set to 1 if the device can accept these transactions and must be set to 0 otherwise. Hardwired to 1.
22	0x0 RO	**Reserved (RSVD3):** Reserved (RSVD)
21	0x1 RO	**66 Mhz Capable (MCAP):** This bit indicates whether or not this device is capable of running at 66 MHz. • A value of 0 indicates 33 MHz. • A value of 1 indicates that the device is 66 MHz capable. Hardwired to 1.
20	0x1 RO	**Capabilities List (CAPL):** This optional read-only bit indicates whether or not this device implements the pointer for a New Capabilities linked list at offset 34h. A value of zero indicates that no New Capabilities linked list is available. A value of one indicates that the value read at offset 34h is a pointer in Configuration Space to a linked list of new capabilities.
19	0x0 RO	**Interrupt Status (INTS):** This read-only bit reflects the state of the interrupt in the device/function. Only when the Interrupt Disable bit in the command register is a 0 and this Interrupt Status bit is a 1, will the device's/function's INTx# signal be asserted. Setting the Interrupt Disable bit to a 1 has no effect on the state of this bit. Read-only and hardwired to 0 for a device that does NOT support pin-based interrupt.

Bit Range	Default & Access	Field Name (ID): Description
18:16	0x0 RO	**Reserved (RSVD2):**
15:11	0x0 RO	**Reserved (RSVD1):**
10	0x0 RW	**Interrupt Disable (INTD):** This bit disables the device/function from asserting INTx#. • A value of 0 enables the assertion of its INTx# signal. • A value of 1 disables the assertion of its INTx# signal. This bit's state after RST# is 0.
9	0x0 RO	**Fast Back to Back Enable (FBTBEN):** Not implemented. Hardwired to 0.
8	0x0 RO	**System Error Enable (SERREN):** Not implemented. Hardwired to 0.
7	0x0 RO	**Reserved (RSVD0):**
6	0x0 RO	**Parity Error Response (PERRR):** Not implemented. Hardwired to 0.
5	0x0 RO	**VGA Palette Snoop (VGAPS):** Not implemented. Hardwired to 0.
4	0x0 RO	**Memory Write and Invalidate Enable (MWRIEN):** Not implemented. Hardwired to 0.
3	0x0 RO	**Special Cycles (SPCYC):** Not implemented. Hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the ability of a PCI device to issue Memory and I/O Read/Write Requests, and the ability of a PCI bridge to forward Memory and I/O Read/Write Requests in the Upstream direction. When this bit is Set, the PCI device function is allowed to issue Memory or I/O Requests. When this bit is Clear, the PCI device function is not allowed to issue any Memory or I/O Requests. ***Note:*** As MSI/MSI-X interrupt Messages are in-band memory writes, setting the Bus Master Enable bit to 0b disables MSI/MSI-X interrupt Messages as well. Requests other than Memory or I/O Requests are not controlled by this bit. Default value of this bit is 0b. This bit is hardwired to 0b if a PCI device function does not generate Memory or I/O Requests. Default value of this bit is 0b.
1	0x0 RO	**Memory Space Enable (MSE):** Controls a device's response to Memory Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to Memory Space accesses. State after RST# is 0. Read-only and hardwired to 0 because IDE does NOT support Memory Space accesses.
0	0x0 RW	**IO Space Enable (IOSE):** Controls a device's response to I/O Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to I/O Space accesses. State after RST# is 0.

52.6.3 Class Code and Revision ID (IDE_HOST_CC_RID)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 8h

Default: 01018500h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x1 RO	**Base Class Code (BCC):** Identifies the Base Class Code of an external IDE controller device driver.
23:16	0x1 RO	**Sub-Class Code (SCC):** Identifies the Sub-Class Code of an external IDE controller device driver.
15:8	0x85 RO	**Programming Interface (PI):** Identifies the Programming Interface of an IDE controller device driver.
7:0	0x0 RO/V	**Revision ID (RID):** This register specifies a device specific revision identifier. The value is chosen by the vendor. Zero is an acceptable value. This field should be viewed as a vendor defined extension to the Device ID.

52.6.4 BIST, Header Type, Latency Timer, and Cache Line Size (IDE_HOST_BIST_HTYPE_LT_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + Ch

Default: 00800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Built In Self Test (BIST):** Not implemented. Hardwired to 0.
23	0x1 RO/V	**Header Type 1 (HTYPE1):** This bit identifies whether or not the device contains multiple functions. • If the bit is 0, then the device is single function. • If the bit is 1, then the device has multiple functions.
22:16	0x0 RO	**Header Type 0 (HTYPE0):** This field identifies the layout of the second part of the predefined header (beginning at byte 10h in Configuration Space). • The encoding 00h specifies the non-bridge Configuration Space Header. • The encoding 01h specifies the PCI-to-PCI bridge Configuration Space Header. • The encoding 02h specifies the CardBus bridge Configuration Space Header. • All other encodings are reserved. Hardwired to 0 to identify the non-bridge Configuration Space Header.
15:8	0x0 RO	**Latency Timer (LT):** Not implemented. Hardwired to 0.
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented. Hardwired to 0.

52.6.5 IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 10h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region
2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 8B of IO space
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

52.6.6 IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 14h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

52.6.7 IDE Secondary Command Block IO BAR (IDE_HOST_SCMDIOBAR)—Offset 18h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 18h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region
2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 8B of IO space
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

52.6.8 IDE Secondary Control Block IO BAR (IDE_HOST_SCTLIOBAR)—Offset 1Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 1Ch

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

52.6.9 IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 20h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
3:2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 16B of IO space.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

52.6.10 Cardbus CIS Pointer (IDE_HOST_CCP)—Offset 28h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Cardbus CIS Pointer (CCP):** Not implemented. Hardwired to 0.

52.6.11 Subsystem ID and Subsystem Vendor ID (IDE_HOST_SID_SVID)—Offset 2Ch

These registers are used to uniquely identify the add-in card or subsystem where the PCI device resides. They provide a mechanism for add-in card vendors to distinguish their add-in cards from one another even though the add-in cards may have the same PCI controller on them (and, therefore, the same Vendor ID and Device ID).

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 2Ch

Default: 00008086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SID):** Value of this field is vendor-specific. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SID should have its own lock.
15:0	0x8086 RW/O	**Subsystem Vendor ID (SVID):** This field identifies the vendor of the add-in card or subsystem. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SVID should have its own lock.

52.6.12 Expansion ROM Base Address (IDE_HOST_XRBAR)—Offset 30h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Expansion ROM Base Address (XRBAR):** Not implemented. Hardwired to 0.

52.6.13 Capabilities List Pointer (IDE_HOST_CAPP)—Offset 34h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 34h

Default: 00000040h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):**
7:0	0x40 RO	**Capabilities Pointer (CAPP):** Indicates the pointer for the first entry in the capabilities list which is the MSI Capability.

52.6.14 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (IDE_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 3Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Maximum Latency (MAXL):** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Minimum Grant (MING):** Not implemented. Hardwired to 0.
15:8	0x0 RO/V	**Interrupt Pin (INTP):** This register specifies which interrupt pin IDE uses in PCI interrupt mode. Value Decoding 00h The function does NOT use an interrupt pin. 01h INTA 02h INTB 03h INTC 04h INTD 05h - FFh Reserved. ***Note:*** This field shadows the IDEHIPINR.IPIN field in the PTIO Host private CR space which is configured by BIOS over IOSF SB.
7:0	0x0 RW	**Interrupt Line (INTL):** This register is used to communicate interrupt line routing information. POST software will write the routing information into this register as it initializes and configures the system. The value in this register tells which input of the system interrupt controller(s) the device's interrupt pin is connected to. The device itself does not use this value, rather it is used by device drivers and operating systems. Device drivers and operating systems can use this information to determine priority and vector information. Values in this register are system architecture specific.

52.6.15 MSI Message Control, Next Pointer and Capability ID (IDE_HOST_MSIMC_MSINP_MSICID)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 40h

Default: 00805005h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**Reserved (RSVD):**
24	0x0 RO	**Per Vector Masking Capable (PVMC):** Not implemented. Hardwired to 0 to indicate the function does NOT support MSI per-vector masking.
23	0x1 RO	**64 bit address capable (XAC):** Hardwired to 1 to indicate the function is capable of sending a 64-bit message address.
22:20	0x0 RW	**Multiple Message Enable (MMEN):** Encoded number of interrupt vectors allocated by SW. This field is RW for software compatibility, but only one interrupt vector is ever sent by the function.
19:17	0x0 RO	**Multiple Message Capable (MMC):** Encoded number of interrupt vectors requested by a device. Hardwired to 0 to indicate one requested interrupt vector.
16	0x0 RW	**MSI Enable (MSIE):** If set, MSI interrupt delivery is enabled whereas pin-based interrupt delivery SHALL be disabled. If cleared, prior to returning the configuration write (that clears this field) completion, the function must send any pending MSI(s).
15:8	0x50 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 50h to point to the PM Capability list
7:0	0x5 RO	**Capability ID (CID):** Hardwired to 05h to indicate the linked list item as the MSI Capability registers

52.6.16 MSI Message Address (IDE_HOST_MSIMA)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** 32-bit DW-aligned MSI message address.
1:0	0x0 RO	**Reserved (RSVD):**

52.6.17 MSI Message Upper Address (IDE_HOST_MSIMUA)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Upper 32-bit of a 64-bit DW-aligned MSI message address.

52.6.18 MSI Message Data (IDE_HOST_MSIMD)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):**
15:0	0x0 RW	**Message Data (MD):** MSI Message Data

52.6.19 Power Management Capabilities, Next Pointer and Capability ID (IDE_HOST_PMCAP_PMNP_PMCID)—Offset 50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 50h

Default: 00230001h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**PME Support (PMES):** This 5-bit field indicates the power states in which the function may assert PME#. A value of 0b for any bit indicates that the function is not capable of asserting the PME# signal while in that power state. • bit(27) X XXX1b - PME# can be asserted from D0 • bit(28) X XX1Xb - PME# can be asserted from D1 • bit(29) X X1XXb - PME# can be asserted from D2 • bit(30) X 1XXXb - PME# can be asserted from D3hot • bit(31) 1 XXXXb - PME# can be asserted from D3cold
26	0x0 RO	**D2 Support (D2S):** Hardwired to 0 to indicate that this device does not support D2
25	0x0 RO	**D1 Support (D1S):** Hardwired to 0 to indicate that this device does not support D1
24:22	0x0 RO	**Aux Current (AUXC):** Not implemented. Hardwired to 0.
21	0x1 RO	**Device Specific Initialization (DSI):** indicates whether special initialization of this function is required (beyond the standard PCI configuration header) before the generic class device driver is able to use it. A 1 indicates that the function requires a device specific initialization sequence following transition to the D0 uninitialized state. Hardwired to 1 to indicate Device Specific Initialization is required.
20	0x0 RO	**Reserved (RSVD):**
19	0x0 RO	**PME Clock (PMECLK):** Not implemented. Hardwired to 0.
18:16	0x3 RO	**Version (VER):** Hardwired to value of 011b indicates that this function complies with rev 1.2 of PCI Power Management Interface Spec
15:8	0x0 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 0 to indicate no more linked list item.
7:0	0x1 RO	**Capability ID (CID):** Hardwired to 01h to indicate the linked list item as the PCI Power Management registers

52.6.20 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (IDE_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + 54h

Default: 00000008h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Data:** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Control/Status Register Bridge Support Extensions (CSRBSE):** Not implemented. Hardwired to 0.
15	0x0 RO	**PME Status (PMESTS):** This bit is set when the function would normally assert the PME signal independent of the state of the PME_En bit. • Writing a 1 to this bit will clear it and cause the function to stop asserting a PME (if enabled). • Writing a 0 has no effect. If the function supports PME from D3cold, then this bit is sticky and must be explicitly cleared by the operating system each time the operating system is initially loaded. Not implemented. Hardwired to 0.
14:13	0x0 RO	**Data Scale (DS):** Not implemented. Hardwired to 0.
12:9	0x0 RO	**Data Select (DSEL):** Not implemented. Hardwired to 0.
8	0x0 RO	**PME Enable (PMEEN):** A 1 enables the function to assert PME. When 0, PME assertion is disabled. This bit defaults to 0 if the function does not support PME generation from D3cold. If the function supports PME from D3cold then this bit is sticky and must be explicitly cleared by the operating system each time it is initially loaded. Not implemented. Hardwired to 0.
7:4	0x0 RO	**Reserved (RSVD1):**
3	0x1 RO	**No Soft Reset (NSR):** When set to 1, this bit indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. Configuration Context is preserved. Upon transition from the D3hot to the D0 Initialized state, no additional operating system intervention is required to preserve Configuration Context beyond writing the PowerState bits.
2	0x0 RO	**Reserved (RSVD0):**
1:0	0x0 RW	**Power State (PWRST):** This 2-bit field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the field values is given below: 00b - D0 01b - D1 10b - D2 11b - D3hot If software attempts to write an unsupported, optional state to this field, the write operation must complete normally on the bus; however, the data is discarded and no state change occurs.

52.6.21 Process Stepping Information (IDE_HOST_PSI)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:24, F:2] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Reserved.
23:16	0x0 RO/V	**Manufacturing Stepping (MSID):** Reserved.
15:8	0x0 RO/V	**Manufacturing ID (MID):** Reserved.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Reserved.

52.7 Registers in Memory Space—HECI1_MMIO_MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) HECI1_MMIO_MBAR_LO described in Section 52.2.9, "HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h" on page 2243 and HECI1_MMIO_MBAR_HI described in Section 52.2.10, "HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h" on page 2244.

52.7.1 Host CB Write Window (HECI1_H_CB_WW)—Offset 0h

This register is for host to write into its Circular Buffer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI1_MMIO_MBAR] + 0h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:24, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Host Circular Buffer Write Window Field (H_CB_WWF):** This field is for host to write into its circular buffer. This field is write only, reads will return arbitrary data. Writes to this register will increment the H_CBWP as long as CSE_RDY is 1. When CSE_RDY is 0, writes to this register have no effect and are not delivered to the H_CB, nor is H_CBWP incremented.

52.7.2 Host Control and Status Register (HECI1_H_CSR)—Offset 4h

This register reports status information about the host circular buffer (H_CB) and allows host software to control interrupt generation.

Note to software: reserved bits in this register must be set to 0 whenever this register is written.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + 4h

Default: 80000000h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:24, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**Host Circular Buffer Depth (H_CBD):** This field indicates the maximum number of 32 bit entries available in the host circular buffer (H_CB). Host software uses this field along with the H_CBRP and H_CBWP fields to calculate the number of valid entries in the H_CB to read or number of entries available for write. Programmers note: This field is implemented with a '1-hot' scheme. Only one bit will be set to a '1' at a time. Each bit position represents the value n of a buffer depth of (2^n). For example, when bit# 1 is 1, the buffer depth is 2; when bit#2 is 1, the buffer depth is 4, etc. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**Host CB Write Pointer (H_CBWP):** Points to next location in the H_CB for host to write the data. Software uses this field along with H_CBRP and H_CBD fields to calculate the number of valid entries in the H_CB to read or number of entries available for write.
15:8	0x0 RO/V	**Host CB Read Pointer (H_CBRP):** Points to next location in the H_CB where a valid data is available for embedded controller to read. Software uses this field along with H_CBWR and H_CBD fields to calculate the number of valid entries in the host CB to read or number of entries available for write.
7	0x0 RO	**Reserved (RSVD_7_7):** Reserved.
6	0x0 RW/1C/V	**Host D0I3 Interrupt Status (H_D0I3C_IS):** HW sets this bit to 1 when D0I3C.H_D0I3_IR is set and D0I3C.H_D0I3_CIP transitions from 1 to 0. Host clears this bit to 0 by writing a 1 to this bit position. H_D0I3C_IE has no effect on this bit.
5	0x0 RW	**Host D0I3 Interrupt Enable (H_D0I3C_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_D0I3C_IS is set to 1.
4	0x0 RW	**Host Reset (H_RST):** Setting this bit to 1 will initiate the HECI reset sequence to get the circular buffers into a known good state for host and CSE communication. When this bit transitions from 0 to 1, hardware will clear the H_RDY and CSE_RDY bits.
3	0x0 RW/V	**Host Ready (H_RDY):** This bit indicates that the host is ready to process messages.
2	0x0 RW/V	**Host Interrupt Generate (H_IG):** Once message(s) are written into its CB, the host sets this bit to one for the HW to set the CSE_IS bit in the CSE_CSR and to generate an interrupt message to mIA. HW then clears this bit to 0.
1	0x0 RW/1C/V	**Host Interrupt Status (H_IS):** HW sets this bit to 1 when CSE_IG bit is set to 1. Host clears this bit to 0 by writing a 1 to this bit position. H_IE has no effect on this bit.
0	0x0 RW	**Host Interrupt Enable (H_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_IS is set to 1.

52.7.3 CSE Circular Buffer Read Window (HECI1_CSE_CB_RW)—Offset 8h

This register is for host to read from the CSE Circular Buffer (CSE_CB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + 8h

Default: FFFFFFFFh

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:24, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO	**CSE Circular Buffer Read Window Field (CSE_CB_RWF):** This bit field is for host to read from the CSE Circular Buffer. This field is read only, writes have no effect. Reads to this register will increment the CSE_CBRP as long as CSE_RDY is 1. When CSE_RDY is 0, reads to this register have no effect, all 1s are returned, and CSE_CBRP is not incremented.

52.7.4 CSE Control and Status Register Host Access (HECI1_CSE_CSR_HA)—Offset Ch

This register allows host software to read the CSE Control Status register (CSE_CSR).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + Ch

Default: 80000000h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:24, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**CSE Circular Buffer Depth Host Read Access (CSE_CBD_HRA):** Host read access to CSE_CBD. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**CSE CB Write Pointer Host Read Access (CSE_CBWP_HRA):** Host read only access to CSE_CBWP.
15:8	0x0 RO/V	**CSE CB Read Pointer Host Read Access (CSE_CBRP_HRA):** Host read only access to CSE_CBRP.
7	0x0 RO/V	**NMI Status Host Read Access (NMI_STS_HRA):** Host read access to NMI_STS.
6	0x0 RO	**Reserved (RSVD_6_6):** Reserved.
5	0x0 RO/V	**Pointer Reset Host Read Access (PTR_RST_HRA):** Host read access to PTR_RST.
4	0x0 RO/V	**CSE Reset Host Read Access (CSE_RST_HRA):** Host read access to CSE_RST.
3	0x0 RO/V	**CSE Ready Host Read Access (CSE_RDY_HRA):** Host read access to CSE_RDY.
2	0x0 RO/V	**CSE Interrupt Generate Host Read Access (CSE_IG_HRA):** Host read only access to CSE_IG.
1	0x0 RO/V	**CSE Interrupt Status Host Read Access (CSE_IS_HRA):** Host read only access to CSE_IS.
0	0x0 RO/V	**CSE Interrupt Enable Host Read Access (CSE_IE_HRA):** Host read only access to CSE_IE.

52.7.5 D0i3 Control (HECI1_D0I3C)—Offset 800h

This register allows host to configure the power mode using D0i0/D0i3 support.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + 800h

Default: 00000000h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:24, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3	0x0 RO	**Restore Required (H_D0I3C_RR):** When this bit is set (by HW), SW must restore the state of the IP. This bit is cleared by SW writing a 1. **In CSE this bit is never set so it does not need to be cleared by SW.**
2	0x0 RW	**D0i3 (H_D0I3C_I3):** SW sets this bit to 1 in order to move the IP into the D0i3 state. Clearing this bit will return the IP into the fully active D0 state (D0i0). When this bit changes state, mIA may be interrupted (see H_PCI_CSR.D0I3C_IS register's description)
1	0x0 RW	**Interrupt Request (H_D0I3C_IR):** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this bit on each write to this register. When this bit is set to 1, Command-in-Progress deassertion is captured in H_CSR.H_D0I3_IS. If H_CSR.H_D0I3_IE is 1 as well, host interrupt will be initiated.
0	0x0 RO/V	**Command-in-Progress (H_D0I3C_CIP):** HW sets this bit on a 0-)1 or 1-)0 transition of D0i3 bit (bit [2]). While set, the other bits in this register are not valid and it is illegal for SW to write to any of them. While clear, all other bits in this register are valid and SW may write to them. If Interrupt Request (bit [1]) was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles a particular interrupt is not visible to HW. SW writes to this bit have no effect. This bit is auto-cleared by HW one cycle after it is set.

52.8 Registers in Memory Space—HECI2_MMIO_MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) HECI2_MMIO_MBAR_LO described in Section 52.3.9, "HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h" on page 2263 and HECI2_MMIO_MBAR_HI described in Section 52.3.10, "HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h" on page 2264.

52.8.1 Host CB Write Window (HECI2_H_CB_WW)—Offset 0h

This register is for host to write into its Circular Buffer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI2_MMIO_MBAR] + 0h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:24, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Host Circular Buffer Write Window Field (H_CB_WWF):** This field is for host to write into its circular buffer. This field is write only, reads will return arbitrary data. Writes to this register will increment the H_CBWP as long as CSE_RDY is 1. When CSE_RDY is 0, writes to this register have no effect and are not delivered to the H_CB, nor is H_CBWP incremented.

52.8.2 Host Control and Status Register (HECI2_H_CSR)—Offset 4h

This register reports status information about the host circular buffer (H_CB) and allows host software to control interrupt generation.

Note to software: reserved bits in this register must be set to 0 whenever this register is written.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI2_MMIO_MBAR] + 4h

Default: 80000000h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:24, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**Host Circular Buffer Depth (H_CBD):** This field indicates the maximum number of 32 bit entries available in the host circular buffer (H_CB). Host software uses this field along with the H_CBRP and H_CBWP fields to calculate the number of valid entries in the H_CB to read or number of entries available for write. Programmers note: This field is implemented with a '1-hot' scheme. Only one bit will be set to a '1' at a time. Each bit position represents the value n of a buffer depth of (2^n). For example, when bit# 1 is 1, the buffer depth is 2; when bit#2 is 1, the buffer depth is 4, etc. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**Host CB Write Pointer (H_CBWP):** Points to next location in the H_CB for host to write the data. Software uses this field along with H_CBRP and H_CBD fields to calculate the number of valid entries in the H_CB to read or number of entries available for write.
15:8	0x0 RO/V	**Host CB Read Pointer (H_CBRP):** Points to next location in the H_CB where a valid data is available for embedded controller to read. Software uses this field along with H_CBWR and H_CBD fields to calculate the number of valid entries in the host CB to read or number of entries available for write.
7	0x0 RO	**Reserved (RSVD_7_7):** Reserved.
6	0x0 RW/1C/V	**Host D0I3 Interrupt Status (H_D0I3C_IS):** HW sets this bit to 1 when D0I3C.H_D0I3_IR is set and D0I3C.H_D0I3_CIP transitions from 1 to 0. Host clears this bit to 0 by writing a 1 to this bit position. H_D0I3C_IE has no effect on this bit.
5	0x0 RW	**Host D0I3 Interrupt Enable (H_D0I3C_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_D0I3C_IS is set to 1.
4	0x0 RW	**Host Reset (H_RST):** Setting this bit to 1 will initiate the HECI reset sequence to get the circular buffers into a known good state for host and CSE communication. When this bit transitions from 0 to 1, hardware will clear the H_RDY and CSE_RDY bits.
3	0x0 RW/V	**Host Ready (H_RDY):** This bit indicates that the host is ready to process messages.
2	0x0 RW/V	**Host Interrupt Generate (H_IG):** Once message(s) are written into its CB, the host sets this bit to one for the HW to set the CSE_IS bit in the CSE_CSR and to generate an interrupt message to mIA. HW then clears this bit to 0.
1	0x0 RW/1C/V	**Host Interrupt Status (H_IS):** HW sets this bit to 1 when CSE_IG bit is set to 1. Host clears this bit to 0 by writing a 1 to this bit position. H_IE has no effect on this bit.
0	0x0 RW	**Host Interrupt Enable (H_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_IS is set to 1.

52.8.3 CSE Circular Buffer Read Window (HECI2_CSE_CB_RW)—Offset 8h

This register is for host to read from the CSE Circular Buffer (CSE_CB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI2_MMIO_MBAR] + 8h

Default: FFFFFFFFh

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:24, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO	**CSE Circular Buffer Read Window Field (CSE_CB_RWF):** This bit field is for host to read from the CSE Circular Buffer. This field is read only, writes have no effect. Reads to this register will increment the CSE_CBRP as long as CSE_RDY is 1. When CSE_RDY is 0, reads to this register have no effect, all 1s are returned, and CSE_CBRP is not incremented.

52.8.4 CSE Control and Status Register Host Access (HECI2_CSE_CSR_HA)—Offset Ch

This register allows host software to read the CSE Control Status register (CSE_CSR).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI2_MMIO_MBAR] + Ch

Default: 80000000h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:24, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**CSE Circular Buffer Depth Host Read Access (CSE_CBD_HRA):** Host read access to CSE_CBD. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**CSE CB Write Pointer Host Read Access (CSE_CBWP_HRA):** Host read only access to CSE_CBWP.
15:8	0x0 RO/V	**CSE CB Read Pointer Host Read Access (CSE_CBRP_HRA):** Host read only access to CSE_CBRP.
7	0x0 RO/V	**NMI Status Host Read Access (NMI_STS_HRA):** Host read access to NMI_STS.
6	0x0 RO	**Reserved (RSVD_6_6):** Reserved.
5	0x0 RO/V	**Pointer Reset Host Read Access (PTR_RST_HRA):** Host read access to PTR_RST.
4	0x0 RO/V	**CSE Reset Host Read Access (CSE_RST_HRA):** Host read access to CSE_RST.
3	0x0 RO/V	**CSE Ready Host Read Access (CSE_RDY_HRA):** Host read access to CSE_RDY.
2	0x0 RO/V	**CSE Interrupt Generate Host Read Access (CSE_IG_HRA):** Host read only access to CSE_IG.
1	0x0 RO/V	**CSE Interrupt Status Host Read Access (CSE_IS_HRA):** Host read only access to CSE_IS.
0	0x0 RO/V	**CSE Interrupt Enable Host Read Access (CSE_IE_HRA):** Host read only access to CSE_IE.

52.8.5 D0i3 Control (HECI2_D0I3C)—Offset 800h

This register allows host to configure the power mode using D0i0/D0i3 support.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI2_MMIO_MBAR] + 800h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:24, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3	0x0 RO	**Restore Required (H_D0I3C_RR):** When this bit is set (by HW), SW must restore the state of the IP. This bit is cleared by SW writing a 1. **In CSE this bit is never set so it does not need to be cleared by SW.**
2	0x0 RW	**D0i3 (H_D0I3C_I3):** SW sets this bit to 1 in order to move the IP into the D0i3 state. Clearing this bit will return the IP into the fully active D0 state (D0i0). When this bit changes state, mIA may be interrupted (see H_PCI_CSR.D0I3C_IS register's description)
1	0x0 RW	**Interrupt Request (H_D0I3C_IR):** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this bit on each write to this register. When this bit is set to 1, Command-in-Progress deassertion is captured in H_CSR.H_D0I3_IS. If H_CSR.H_D0I3_IE is 1 as well, host interrupt will be initiated.
0	0x0 RO/V	**Command-in-Progress (H_D0I3C_CIP):** HW sets this bit on a 0-)1 or 1-)0 transition of D0i3 bit (bit [2]). While set, the other bits in this register are not valid and it is illegal for SW to write to any of them. While clear, all other bits in this register are valid and SW may write to them. If Interrupt Request (bit [1]) was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles a particular interrupt is not visible to HW. SW writes to this bit have no effect. This bit is auto-cleared by HW one cycle after it is set.

52.9 Registers in Memory Space—HECI3_MMIO_MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) HECI3_MMIO_MBAR_LO described in Section 52.4.9, "HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h" on page 2280 and HECI3_MMIO_MBAR_HI described in Section 52.4.10, "HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h" on page 2281.

52.9.1 Host CB Write Window (HECI3_H_CB_WW)—Offset 0h

This register is for host to write into its Circular Buffer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI3_MMIO_MBAR] + 0h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:24, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Host Circular Buffer Write Window Field (H_CB_WWF):** This field is for host to write into its circular buffer. This field is write only, reads will return arbitrary data. Writes to this register will increment the H_CBWP as long as CSE_RDY is 1. When CSE_RDY is 0, writes to this register have no effect and are not delivered to the H_CB, nor is H_CBWP incremented.

52.9.2 Host Control and Status Register (HECI3_H_CSR)—Offset 4h

This register reports status information about the host circular buffer (H_CB) and allows host software to control interrupt generation.

Note to software: reserved bits in this register must be set to 0 whenever this register is written.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI3_MMIO_MBAR] + 4h

Default: 80000000h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:24, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**Host Circular Buffer Depth (H_CBD):** This field indicates the maximum number of 32 bit entries available in the host circular buffer (H_CB). Host software uses this field along with the H_CBRP and H_CBWP fields to calculate the number of valid entries in the H_CB to read or number of entries available for write. Programmers note: This field is implemented with a '1-hot' scheme. Only one bit will be set to a '1' at a time. Each bit position represents the value n of a buffer depth of (2^n). For example, when bit# 1 is 1, the buffer depth is 2; when bit#2 is 1, the buffer depth is 4, etc. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**Host CB Write Pointer (H_CBWP):** Points to next location in the H_CB for host to write the data. Software uses this field along with H_CBRP and H_CBD fields to calculate the number of valid entries in the H_CB to read or number of entries available for write.
15:8	0x0 RO/V	**Host CB Read Pointer (H_CBRP):** Points to next location in the H_CB where a valid data is available for embedded controller to read. Software uses this field along with H_CBWR and H_CBD fields to calculate the number of valid entries in the host CB to read or number of entries available for write.
7	0x0 RO	**Reserved (RSVD_7_7):** Reserved.
6	0x0 RW/1C/V	**Host D0I3 Interrupt Status (H_D0I3C_IS):** HW sets this bit to 1 when D0I3C.H_D0I3_IR is set and D0I3C.H_D0I3_CIP transitions from 1 to 0. Host clears this bit to 0 by writing a 1 to this bit position. H_D0I3C_IE has no effect on this bit.
5	0x0 RW	**Host D0I3 Interrupt Enable (H_D0I3C_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_D0I3C_IS is set to 1.
4	0x0 RW	**Host Reset (H_RST):** Setting this bit to 1 will initiate the HECI reset sequence to get the circular buffers into a known good state for host and CSE communication. When this bit transitions from 0 to 1, hardware will clear the H_RDY and CSE_RDY bits.
3	0x0 RW/V	**Host Ready (H_RDY):** This bit indicates that the host is ready to process messages.
2	0x0 RW/V	**Host Interrupt Generate (H_IG):** Once message(s) are written into its CB, the host sets this bit to one for the HW to set the CSE_IS bit in the CSE_CSR and to generate an interrupt message to mIA. HW then clears this bit to 0.
1	0x0 RW/1C/V	**Host Interrupt Status (H_IS):** HW sets this bit to 1 when CSE_IG bit is set to 1. Host clears this bit to 0 by writing a 1 to this bit position. H_IE has no effect on this bit.
0	0x0 RW	**Host Interrupt Enable (H_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_IS is set to 1.

52.9.3 CSE Circular Buffer Read Window (HECI3_CSE_CB_RW)—Offset 8h

This register is for host to read from the CSE Circular Buffer (CSE_CB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI3_MMIO_MBAR] + 8h

Default: FFFFFFFFh

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:24, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO	**CSE Circular Buffer Read Window Field (CSE_CB_RWF):** This bit field is for host to read from the CSE Circular Buffer. This field is read only, writes have no effect. Reads to this register will increment the CSE_CBRP as long as CSE_RDY is 1. When CSE_RDY is 0, reads to this register have no effect, all 1s are returned, and CSE_CBRP is not incremented.

52.9.4 CSE Control and Status Register Host Access (HECI3_CSE_CSR_HA)—Offset Ch

This register allows host software to read the CSE Control Status register (CSE_CSR).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI3_MMIO_MBAR] + Ch

Default: 80000000h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:24, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**CSE Circular Buffer Depth Host Read Access (CSE_CBD_HRA):** Host read access to CSE_CBD. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**CSE CB Write Pointer Host Read Access (CSE_CBWP_HRA):** Host read only access to CSE_CBWP.
15:8	0x0 RO/V	**CSE CB Read Pointer Host Read Access (CSE_CBRP_HRA):** Host read only access to CSE_CBRP.
7	0x0 RO/V	**NMI Status Host Read Access (NMI_STS_HRA):** Host read access to NMI_STS.
6	0x0 RO	**Reserved (RSVD_6_6):** Reserved.
5	0x0 RO/V	**Pointer Reset Host Read Access (PTR_RST_HRA):** Host read access to PTR_RST.
4	0x0 RO/V	**CSE Reset Host Read Access (CSE_RST_HRA):** Host read access to CSE_RST.
3	0x0 RO/V	**CSE Ready Host Read Access (CSE_RDY_HRA):** Host read access to CSE_RDY.
2	0x0 RO/V	**CSE Interrupt Generate Host Read Access (CSE_IG_HRA):** Host read only access to CSE_IG.
1	0x0 RO/V	**CSE Interrupt Status Host Read Access (CSE_IS_HRA):** Host read only access to CSE_IS.
0	0x0 RO/V	**CSE Interrupt Enable Host Read Access (CSE_IE_HRA):** Host read only access to CSE_IE.

52.9.5 D0i3 Control (HECI3_D0I3C)—Offset 800h

This register allows host to configure the power mode using D0i0/D0i3 support.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI3_MMIO_MBAR] + 800h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:24, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3	0x0 RO	**Restore Required (H_D0I3C_RR):** When this bit is set (by HW), SW must restore the state of the IP. This bit is cleared by SW writing a 1. **In CSE this bit is never set so it does not need to be cleared by SW.**
2	0x0 RW	**D0i3 (H_D0I3C_I3):** SW sets this bit to 1 in order to move the IP into the D0i3 state. Clearing this bit will return the IP into the fully active D0 state (D0i0). When this bit changes state, mIA may be interrupted (see H_PCI_CSR.D0I3C_IS register's description)
1	0x0 RW	**Interrupt Request (H_D0I3C_IR):** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this bit on each write to this register. When this bit is set to 1, Command-in-Progress deassertion is captured in H_CSR.H_D0I3_IS. If H_CSR.H_D0I3_IE is 1 as well, host interrupt will be initiated.
0	0x0 RO/V	**Command-in-Progress (H_D0I3C_CIP):** HW sets this bit on a 0-)1 or 1-)0 transition of D0i3 bit (bit [2]). While set, the other bits in this register are not valid and it is illegal for SW to write to any of them. While clear, all other bits in this register are valid and SW may write to them. If Interrupt Request (bit [1]) was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles a particular interrupt is not visible to HW. SW writes to this bit have no effect. This bit is auto-cleared by HW one cycle after it is set.

52.10 Registers in Memory Space—KT_HOST_MEMBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) KT_HOST_MEMBAR described in Section 52.5.6, "KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h" on page 2296.

52.10.1 KT Receive Buffer Register (MEM_KTRBR)—Offset 0h

This register implements the standard Receiver Buffer register in the KT Block. This is read-only. DLAB (i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be read when the receiver data is ready. In FIFO mode, a read from this register will be translated into a read from the RBR FIFO.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 0h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Receiver Buffer Register (RBR):** Implements the Receiver Buffer register of the Serial Interface.

52.10.2 KT Transmitter Holding Register (MEM_KTTHR)—Offset 0h

This register implements the standard Transmitter Holding register in the KT Block. This is write-only. DLAB (i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be written when the Host needs to transmit data. In FIFO mode, a write to this register will be translated into a write to the THR FIFO.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 0h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**Transmitter Holding Register (THR):** Implements the Transmit Data register of the Serial Interface.

52.10.3 KT Divisor Latch LSB Register (MEM_KTDLLR)—Offset 0h

This register implements the standard DLL register in the KT Block. DLAB (i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. this register is supported only for SW compatibility and has no impact on HW performance.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 0h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch LSB (DLL):** Implements the DLL register of the Serial Interface.

52.10.4 KT Interrupt Enable register (MEM_KTIER)—Offset 1h

This register implements the standard Interrupt Enable register in the KT Block. The bits enable specific events to interrupt the Host. See bit specific definition below. DLAB (i.e. KTLCR[7]) shall is 0 in order for this register to be accessed.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 1h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RW	**MSR (IER3):** When set, enables bits in Modem Status register to cause an interrupt to the Host
2	0x0 RW	**LSR (IER2):** When set, enables bits in Receiver Line Status Register to cause an interrupt to the Host
1	0x0 RW	**THR (IER1):** When set, enables an interrupt to the Host when the Transmitter Holding register is empty
0	0x0 RW	**DR (IER0):** When set, enables an interrupt to the Host when the Received Data is available OR Receiver FIFO timeout.

52.10.5 KT Divisor Latch MSB Register (MEM_KTDLMR)—Offset 1h

This register implements the standard DLM register in the KT Block. DLAB (i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. This register is supported only for SW compatibility and has no impact on HW performance.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 1h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch MSB (DLM):** Implements the DLM register of the Serial Interface.

52.10.6 KT Interrupt Identification Register (MEM_KTIIR)—Offset 2h

This register implements the standard Interrupt Identification register in the KT Block. This is read-only. This register is created to provide minimum software overhead during data character transfers. The register prioritizes KT interrupts into 4 levels and records them in the IIRSTS field of this register. The four levels of interrupt conditions in order of priority are: Receiver Line Status; Received Data Ready/Character Timeout Indication; Transmitter Holding Register Empty; MODEM Status. When the Host accesses the IIR, the HW freezes all interrupts and indicates the highest priority pending interrupt to the Host. While this Host access is occurring, the HW records new interrupts, but does not change its current indication until the access is complete. Table in the Host Interrupt Generation section shows the contents.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 2h

Default: 01h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**FIFO Enable (FIEN1):** This field is connected by HW to the FIFO Enable field of the FCR register.
6	0x0 RO/V	**FIFO Enable (FIEN0):** This field is connected by HW to the FIFO Enable field of the FCR register.
5:4	0x0 RO	**Reserved (RSVD):** Hardwired to 0.
3:1	0x0 RO/V	**IIR Status (IIRSTS):** These bits are asserted by the HW according to the source of the interrupt and the priority level. Refer to the section on Host Interrupt Generation for a table of values.
0	0x1 RO/V	**Interrupt Status (INTSTS):** 0: indicates a pending Host interrupt and IIRSTS may be used as a pointer to the appropriate interrupt service routine. It reflects the logical-NOR of all UART interrupts. An individual UART interrupt will be identified as pending when the individual event status is asserted AND its corresponding event interrupt enable is asserted as well. For example, the THR Empty interrupt will be identified as pending when both LSR[THRE] bit is 1 AND IER[IER1] is 1. 1: indicates no pending Host interrupt.

52.10.7 KT FIFO Control register (MEM_KTFCR)—Offset 2h

This register implements the standard FIFO Control register in the KT Block. It is used to configure features pertinent to the FIFO mode of operation. This is write-only.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 2h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 WO	**Receiver Trigger Level (RTL):** Trigger level in bytes for the Receiver FIFO. Once the trigger level number of bytes is reached, an interrupt will be sent to the Host [7:6] RCVR FIFO Trigger Level (bytes) • 00 -- 01 • 01 -- 04 • 10 -- 08 • 11 -- 14
5:4	0x0 WO	**Reserved (RSVD):** Writes to this field shall be dropped.
3	0x0 WO	**RDY Mode (RDYM):** This bit has no effect on HW performance
2	0x0 WO	**XMT FIFO Clear (XFIC):** When the Host writes one to this bit the HW will clear the XMT FIFO. This bit is self-cleared by HW.
1	0x0 WO	**RCV FIFO Clear (RFIC):** When the Host writes one to this bit the HW will clear the RCV FIFO. This bit is self-cleared by HW.
0	0x0 WO	**FIFO Enable (FIE):** When set indicates that the KT interface is working in FIFO node. When this bit value is changed the RCV and XMT FIFO are cleared by HW. This bit must be a 1 when other FCR bits are written to or they will NOT be programmed.

52.10.8 KT Line Control register (MEM_KTLCR)—Offset 3h

This register implements the standard Line Control register in the KT Block. It specifies the format of the asynchronous data communications exchange and sets the DLAB bit. Most bits in this register have no effect on HW and are only used by the FW.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 3h

Default: 03h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Divisor Latch Access Bit (DLAB):** • 1: Allows access to the Divisor Latch Registers and reading of the FIFO Control Register. • 0: Allows access to RBR, THR, IER and IIR registers.
6	0x0 RW	**Break Control (BC):** This bit has no effect on HW
5:4	0x0 RW	**Parity Bit Mode (PBM):** This bit has no effect on HW
3	0x0 RW	**Parity Enable (PE):** This bit has no effect on HW
2	0x0 RW	**Stop Bit Select (SBS):** This bit has no effect on HW
1:0	0x3 RW	**Word Select Byte (WSB):** This bit has no effect on HW.

52.10.9 KT Modem Control register (MEM_KTMCR)—Offset 4h

This register implements the standard Modem Control register in the KT Block. It controls the interface with the modem. Because the FW emulates the modem, the Host communicates with the FW via this register. This register has impact on the HW in the loopback mode.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 4h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved.
4	0x0 RW	**Loop Back Mode (LBM):** When set by Host indicates that the serial port is in loop Back mode. This means that the data that is transmitted by the host should be received. Helps in debug of the interface
3	0x0 RW	**Output 2 (OUT2):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit (7)
2	0x0 RW	**Output 1 (OUT1):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit(6)
1	0x0 RW	**Request to Send Out (RTSO):** This bit has no effect on HW in normal mode. In loopback mode, the value of this bit is written by HW to Modem Status Register bit(4)
0	0x0 RW	**Data Terminal Ready Out (DRTO):** This bit has no effect on HW in normal mode. In loopback mode, the value in this bit is written by HW to Modem Status Register Bit(5)

52.10.10 KT Line Status register (MEM_KTLSR)—Offset 5h

This register implements the standard Line Status register in the KT Block. It provides status information of the data transfer to the Host. Error indication etc are provided by the HW/FW to the host via this register.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 5h

Default: 60h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/C/V	**RCVR FIFO Error (RXFER):** This bit is cleared in non FIFO mode. This bit is connected to UART LSR[BI] bit in FIFO mode.
6	0x1 RO/V	**Transmitter Empty (TEMT):** In non-FIFO mode: this bit will be set to 1 whenever the Transmitter Holding Register (THR) and the Transmitter Shift Register (TSR) are both empty, OR cleared to 0 whenever either THR or TSR contains a data byte. In FIFO mode: this bit will be set to 1 whenever XMIT FIFO and TSR are both empty, OR cleared to 0 whenever either XMIT FIFO or TSR contains a data byte. Implementation note: This bit is connected by HW to THRE bit
5	0x1 RO/V	**Transmitter Holding Register Empty (THRE):** The bit will always be set whenever Host changes UART FCR[FIE] bit. This bit is controlled differently in FIFO vs non-FIFO modes: Non-FIFO mode: This bit will be cleared by HW when Host writes to THR, and set by HW when FW reads from THR. FIFO mode: This bit will be set by HW when XMIT FIFO is empty , and cleared by HW when XMIT FIFO is NOT empty.
4	0x0 RO/C/V	**Break Interrupt (BI):** This bit will be cleared by HW when the UART LSR register is read by Host. This bit will be set by HW in two cases: In FIFO mode, when FW sets the KTRIVR[SBI] bit. In non-FIFO mode, when FW sets the KTRBR[BIA] bit.
3	0x0 RO	**Framing Error (FE):** This bit is NOT implemented and hardwired to 0.
2	0x0 RO	**Parity Error (PE):** This bit is NOT implemented and hardwired to 0.
1	0x0 RO/C/V	**Overrun Error (OE):** HW will clear this bit when Host reads from KTLSR register and this is source of interrupt. HW will set this bit when overrun error is detected. In non-FIFO mode, the character that triggers the overrun error shall overwrite the character in the RBR register. In FIFO mode, the character that triggers the overrun error shall be dropped without corrupting the RCVR FIFO.
0	0x0 RO/V	**Data Ready (DR):** Non-FIFO Mode: this bit will be set by HW when FW writes to RBR and cleared by HW when Host reads from RBR. FIFO Mode: the bit will be set by HW when RCVR FIFO is not empty and cleared by HW when RCVR FIFO is empty.

52.10.11 KT Modem Status register (MEM_KTMSR)—Offset 6h

This register implements the standard Modem Status register in the KT Block. It provides the current state of the control lines from the modem. The modem functionality is emulated by the FW.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 6h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Data Carrier Detect (DCD):** In Loop Back mode this bit is connected by HW to the value of MCR bit 3
6	0x0 RO	**Ring Indicator (RI):** In Loop Back mode this bit is connected by HW to the value of MCR bit 2.
5	0x0 RO	**Data Set Ready (DSR):** In Loop Back mode this bit is connected by HW to the value of MCR bit 0.
4	0x0 RO	**Clear To Send (CTS):** In Loop Back mode this bit is connected by HW to the value of MCR bit 1.
3	0x0 RO/C/V	**Delta Data Carrier Detect (DDCD):** This bit is set when bit 7 is changed. This bit is cleared by HW when the MSR register is being read by the HOST driver.
2	0x0 RO/C/V	**Trailing Edge of Read Detector (TERI):** This bit is set when bit 6 is changed from 1 to 0. This bit is cleared by HW when the MSR register is being read by the Host driver.
1	0x0 RO/C/V	**Delta Data Set Ready (DDSR):** This bit is set when bit 5 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver
0	0x0 RO/C/V	**Delta Clear To Send (DCTS):** This bit is set when bit 4 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver

52.10.12 KT Scratch register (MEM_KTSCR)—Offset 7h

This register implements the standard Scratch register in the KT Block. It allows Host SW programmers to hold temporary data. It has NO effect on HW.

Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 7h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:24, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Scratch Register Data (SCRD):** Reserved.

52.11 Registers in Memory Space—Fixed Address

These registers are accessed in Host Memory Space through fixed memory addresses.

52.11.1 FTPM Locality State (HOST_LOC_0_LOC_STATE_HROA)—Offset FED40000h

Reads by host SW from this register will reflect the value of FTPM_LOC_STATE register in mIA space. This register is aliased to the following addresses in the host address space: FED4_x000, x=0,1,2,3,4. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40000h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO/V	**Reserved (RSVD_31_8):** Opaque to HW. Defined by FW.
7	0x0 RO/V	**Register Valid Status (FTPM_REG_VALID_STS):** Opaque to HW. This bit is used by FW to signal to host SW when this register is valid.
6:5	0x0 RO/V	**Reserved (RSVD_6_5):** Opaque to HW. Defined by FW.
4:2	0x0 RO/V	**Active Locality (FTPM_ACTV_LOC):** The encodings are: • 000 - Locality 0, • 001 - Locality 1, • 010 - Locality 2, • 011 - Locality 3, • 100 - Locality 4, • 101 and 111 - reserved. FW sets these bits to mux in the active locality. Once set, the FTPM HCI will pass cycles from the active host locality to the FTPM shared SRAM. Writes from in-active localities will be dropped and reads will return 0's.
1	0x0 RO/V	**Locality Assigned (FTPM_LOC_ASSIGNED):** A value of 0 indicates to host SW that no locality is assigned, a value of 1 indicates a locality has been assigned.
0	0x0 RO/V	**Establishment (FTPM_ESTABLISHMENT):** Opaque to HW. This bit is set to 0 by FW when HASH_START occurs and set to 1 when the RESET_ESTABLISHMENT bit is set.

52.11.2 FTPM Locality Reserved (HOST_LOC_0_LOC_RSVD)—Offset FED40004h

This register was added in order to support QW reads from Locality State register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40004h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Reserved (FTPM_LOC_RSVD_BITS):** Reserved.

52.11.3 FTPM Locality n Control Register (HOST_LOC_0_LOC_CTRL)—Offset FED40008h

Writes by host SW to this register will update the value of the corresponding LOC_n_CTRL_CSEROA register in mIA space. Writes by host SW to this register may be configured by CSE FW to trigger an MSI/PME to mIA. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40008h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**FTPM Locality n Control Bits (FTPM_LOC_CTRL_BITS):** Reserved.

52.11.4 FTPM Locality n Status Register Host Read Only Access. (HOST_LOC_0_LOC_STS_HROA)—Offset FED4000Ch

Reads by host SW from this register will reflect the value of the corresponding LOC_n_STS register in mIA space. This register is opaque to HW. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4000Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**FTPM Locality n Status Bits (FTPM_LOC_STS_BITS):** Reserved.

52.11.5 FTPM Locality Config Area Reserved Read Write[0-7] (HOST_LOC_0_RSVD_RW1[0-7])—Offset FED40010h, Count 8, Stride 4h

This register represents a DW of RW memory in FTPM EBB which has no defined functionality. This DW is aliased to the same offset for each locality, and even inactive localities can access it.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-7]: [0x0] + FED40010h + [0-7]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Locality Config Area Reserved Read Write DW (RSVD_RW_31_0):** Reserved.

52.11.6 FTPM Interface ID Host Read Only Access 0 (HOST_LOC_0_INTF_ID_0)—Offset FED40030h

This register is opaque to HW. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40030h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**FTPM Interface ID Bits 0 (FTPM_INTF_ID_BITS_0):** These are the 32 LSbits used by FW to inform host SW as to the interface type of the TPM. The exact usage is defined by TCG.

52.11.7 FTPM Interface ID Host Read Only Access 1 (HOST_LOC_0_INTF_ID_1)—Offset FED40034h

This register is opaque to HW. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40034h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**FTPM Interface ID Bits 1 (FTPM_INTF_ID_BITS_1):** These are the 32 MSbits used by FW to inform host SW as to the interface type of the TPM. The exact usage is defined by TCG.

52.11.8 FTPM Locality Config Area Reserved Read Write[0-1] (HOST_LOC_0_RSVD_RW2[0-1])—Offset FED40038h, Count 2, Stride 4h

This register represents a DW of RW memory in FTPM EBB which has no defined functionality. This DW is aliased to the same offset for each locality, and even inactive localities can access it.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-1]: [0x0] + FED40038h + [0-1]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Locality Config Area Reserved Read Write DW (RSVD_RW_31_0):** Reserved.

52.11.9 Control Area Request (HOST_LOC_0_CA_REQUEST)—Offset FED40040h

This register is implemented in flip-flops. This register is implemented in retention flops to maintain state through PG.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40040h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_REQUEST:** Host software sets this field to a CSxE firmware-defined value to indicate a state change request to the fTPM. Any host write to this register shall result in an interrupt to the CSxE firmware, or wakeup the CSxE subsystem when it is in power-gated state.

52.11.10 Control Area Status (HOST_LOC_0_CA_STATUS)—Offset FED40044h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40044h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_STATUS:** Reserved.

52.11.11 Control Area Cancel (HOST_LOC_0_CA_CANCEL)—Offset FED40048h

This register is implemented in flip-flops. This register is implemented in retention flops to maintain state through PG.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40048h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CANCEL:** Host software sets this field to a CSxE firmware-defined value to indicate that a command should be canceled. Any host write to this register shall result in an interrupt to the CSxE firmware, or wakeup the CSxE subsystem when it is in power-gated state.

52.11.12 Control Area Start (HOST_LOC_0_CA_START)—Offset FED4004Ch

This register is implemented in flip-flops. This register is implemented in retention flops to maintain state through PG.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4004Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Control Area Start (HOST_CA_START):** Host software sets this field to a CSxE firmware defined value to indicate that a command is available for processing. The reset value indicates that a command is NOT available for processing. Any host write to this register shall result in an interrupt to the CSE firmware or wakeup the CSE subsystem when it is in power-gated state.

52.11.13 Control Area Interrupt Reserved Part 1 (HOST_LOC_0_CA_INT_RSVD1)—Offset FED40050h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40050h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RSVD_31_0:** Reserved

52.11.14 Control Area Interrupt Reserved Part 2 (HOST_LOC_0_CA_INT_RSVD2)—Offset FED40054h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40054h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RSVD_31_0:** Reserved

52.11.15 Control Area Command Size (HOST_LOC_0_CA_CMD_SZ)—Offset FED40058h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40058h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CMD_SZ:** Reserved.

52.11.16 Control Area Command Part 1 (HOST_LOC_0_CA_CMD1)—Offset FED4005Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4005Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CMD1:** Reserved.

52.11.17 Control Area Command Part 2 (HOST_LOC_0_CA_CMD2)—Offset FED40060h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40060h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CMD2:** Reserved.

52.11.18 Control Area Response Size (HOST_LOC_0_CA_RSP_SZ)—Offset FED40064h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40064h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_RSP_SZ:** Reserved.

52.11.19 Control Area Response Part 1 (HOST_LOC_0_CA_RSP1)—Offset FED40068h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40068h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_RSP1:** Reserved.

52.11.20 Control Area Response Part 2 (HOST_LOC_0_CA_RSP2)—Offset FED4006Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4006Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_RSP2:** Reserved.

52.11.21 FTPM Reserved Read Write[0-3] (HOST_LOC_0_RSVD_RW3[0-3])—Offset FED40070h, Count 4, Stride 4h

This register represents a DW of RW memory in FTPM EBB which has no defined functionality. The access to this DW is allowed only to an active locality.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-3]: [0x0] + FED40070h + [0-3]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Reserved Read Write DW (RSVD_RW_31_0):** Reserved.

52.11.22 FTPM Command and Response Buffer[0-991] (HOST_LOC_0_FTPM_CRB[0-991])—Offset FED40080h, Count 992, Stride 4h

This register represents a DW of RW memory in FTPM CRB (EBB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-991]: [0x0] + FED40080h + [0-991]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Command and Response Buffer DW (HOST_FTPM_CRB_DW):** Reserved.

52.12 Registers in I/O Space—KT_HOST_IOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) KT_HOST_IOBAR described in Section 52.5.5, "KT IO BAR (KT_HOST_IOBAR)—Offset 10h" on page 2296.

52.12.1 KT Receive Buffer Register (IO_KTRBR)—Offset 0h

This register implements the standard Receiver Buffer register in the KT Block. This is read-only. DLAB (i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be read when the receiver data is ready. In FIFO mode, a read from this register will be translated into a read from the RBR FIFO.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 0h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Receiver Buffer Register (RBR):** Implements the Receiver Buffer register of the Serial Interface.

52.12.2 KT Transmitter Holding Register (IO_KTTHR)—Offset 0h

This register implements the standard Transmitter Holding register in the KT Block. This is write-only. DLAB (i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be written when the Host needs to transmit data. In FIFO mode, a write to this register will be translated into a write to the THR FIFO.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 0h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**Transmitter Holding Register (THR):** Implements the Transmit Data register of the Serial Interface.

52.12.3 KT Divisor Latch LSB Register (IO_KTDLLR)—Offset 0h

This register implements the standard DLL register in the KT Block. DLAB (i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. this register is supported only for SW compatibility and has no impact on HW performance.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 0h

Default: 00h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch LSB (DLL):** Implements the DLL register of the Serial Interface.

52.12.4 KT Interrupt Enable register (IO_KTIER)—Offset 1h

This register implements the standard Interrupt Enable register in the KT Block. The bits enable specific events to interrupt the Host. See bit specific definition below. DLAB (i.e. KTLCR[7]) shall is 0 in order for this register to be accessed.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 1h

Default: 00h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RW	**MSR (IER3):** When set, enables bits in Modem Status register to cause an interrupt to the Host
2	0x0 RW	**LSR (IER2):** When set, enables bits in Receiver Line Status Register to cause an interrupt to the Host
1	0x0 RW	**THR (IER1):** When set, enables an interrupt to the Host when the Transmitter Holding register is empty
0	0x0 RW	**DR (IER0):** When set, enables an interrupt to the Host when the Received Data is available OR Receiver FIFO timeout.

52.12.5 KT Divisor Latch MSB Register (IO_KTDLMR)—Offset 1h

This register implements the standard DLM register in the KT Block. DLAB (i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. This register is supported only for SW compatibility and has no impact on HW performance.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 1h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch MSB (DLM):** Implements the DLM register of the Serial Interface.

52.12.6 KT Interrupt Identification Register (IO_KTIIR)—Offset 2h

This register implements the standard Interrupt Identification register in the KT Block. This is read-only. This register is created to provide minimum software overhead during data character transfers. The register prioritizes KT interrupts into 4 levels and records them in the IIRSTS field of this register. The four levels of interrupt conditions in order of priority are: Receiver Line Status; Received Data Ready/Character Timeout Indication; Transmitter Holding Register Empty; MODEM Status. When the Host accesses the IIR, the HW freezes all interrupts and indicates the highest priority pending interrupt to the Host. While this Host access is occurring, the HW records new interrupts, but does not change its current indication until the access is complete. Table in the Host Interrupt Generation section shows the contents.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 01h

BAR and Offset: [KT_HOST_IOBAR] + 2h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**FIFO Enable (FIEN1):** This field is connected by HW to the FIFO Enable field of the FCR register.
6	0x0 RO/V	**FIFO Enable (FIEN0):** This field is connected by HW to the FIFO Enable field of the FCR register.
5:4	0x0 RO	**Reserved (RSVD):** Hardwired to 0.
3:1	0x0 RO/V	**IIR Status (IIRSTS):** These bits are asserted by the HW according to the source of the interrupt and the priority level. Refer to the section on Host Interrupt Generation for a table of values.
0	0x1 RO/V	**Interrupt Status (INTSTS):** 0: indicates a pending Host interrupt and IIRSTS may be used as a pointer to the appropriate interrupt service routine. It reflects the logical-NOR of all UART interrupts. An individual UART interrupt will be identified as pending when the individual event status is asserted AND its corresponding event interrupt enable is asserted as well. For example, the THR Empty interrupt will be identified as pending when both LSR[THRE] bit is 1 AND IER[IER1] is 1. 1: indicates no pending Host interrupt.

52.12.7 KT FIFO Control register (IO_KTFCR)—Offset 2h

This register implements the standard FIFO Control register in the KT Block. It is used to configure features pertinent to the FIFO mode of operation. This is write-only.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 2h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 WO	**Receiver Trigger Level (RTL):** Trigger level in bytes for the Receiver FIFO. Once the trigger level number of bytes is reached, an interrupt will be sent to the Host [7:6] RCVR FIFO Trigger Level (bytes) • 00 -- 01 • 01 -- 04 • 10 -- 08 • 11 -- 14
5:4	0x0 WO	**Reserved (RSVD):** Writes to this field shall be dropped.
3	0x0 WO	**RDY Mode (RDYM):** This bit has no effect on HW performance.
2	0x0 WO	**XMT FIFO Clear (XFIC):** When the Host writes one to this bit the HW will clear the XMT FIFO. This bit is self-cleared by HW.
1	0x0 WO	**RCV FIFO Clear (RFIC):** When the Host writes one to this bit the HW will clear the RCV FIFO. This bit is self-cleared by HW.
0	0x0 WO	**FIFO Enable (FIE):** When set indicates that the KT interface is working in FIFO node. When this bit value is changed the RCV and XMT FIFO are cleared by HW. This bit must be a 1 when other FCR bits are written to or they will NOT be programmed.

52.12.8 KT Line Control register (IO_KTLCR)—Offset 3h

This register implements the standard Line Control register in the KT Block. It specifies the format of the asynchronous data communications exchange and sets the DLAB bit. Most bits in this register have no effect on HW and are only used by the FW.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 03h

BAR and Offset: [KT_HOST_IOBAR] + 3h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Divisor Latch Access Bit (DLAB):** • 1: Allows access to the Divisor Latch Registers and reading of the FIFO Control Register. • 0: Allows access to RBR, THR, IER and IIR registers.
6	0x0 RW	**Break Control (BC):** This bit has no effect on HW.
5:4	0x0 RW	**Parity Bit Mode (PBM):** This bit has no effect on HW.
3	0x0 RW	**Parity Enable (PE):** This bit has no effect on HW.
2	0x0 RW	**Stop Bit Select (SBS):** This bit has no effect on HW.
1:0	0x3 RW	**Word Select Byte (WSB):** This bit has no effect on HW.

52.12.9 KT Modem Control register (IO_KTMCR)—Offset 4h

This register implements the standard Modem Control register in the KT Block. It controls the interface with the modem. Because the FW emulates the modem, the Host communicates with the FW via this register. This register has impact on the HW in the loopback mode.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 4h

Default: 00h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved.
4	0x0 RW	**Loop Back Mode (LBM):** When set by Host indicates that the serial port is in loop Back mode. This means that the data that is transmitted by the host should be received. Helps in debug of the interface
3	0x0 RW	**Output 2 (OUT2):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit (7)
2	0x0 RW	**Output 1 (OUT1):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit(6)
1	0x0 RW	**Request to Send Out (RTSO):** This bit has no effect on HW in normal mode. In loopback mode, the value of this bit is written by HW to Modem Status Register bit(4)
0	0x0 RW	**Data Terminal Ready Out (DRTO):** This bit has no effect on HW in normal mode. In loopback mode, the value in this bit is written by HW to Modem Status Register Bit(5)

52.12.10 KT Line Status register (IO_KTLSR)—Offset 5h

This register implements the standard Line Status register in the KT Block. It provides status information of the data transfer to the Host. Error indication etc are provided by the HW/FW to the host via this register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 5h

Default: 60h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/C/V	**RCVR FIFO Error (RXFER):** This bit is cleared in non FIFO mode. This bit is connected to UART LSR[BI] bit in FIFO mode.
6	0x1 RO/C/V	**Transmitter Empty (TEMT):** In non-FIFO mode: this bit will be set to 1 whenever the Transmitter Holding Register (THR) and the Transmitter Shift Register (TSR) are both empty, OR cleared to 0 whenever either THR or TSR contains a data byte. In FIFO mode: this bit will be set to 1 whenever XMIT FIFO and TSR are both empty, OR cleared to 0 whenever either XMIT FIFO or TSR contains a data byte. Implementation note: This bit is connected by HW to THRE bit.
5	0x1 RO/C/V	**Transmitter Holding Register Empty (THRE):** The bit will always be set whenever Host changes UART FCR[FIE] bit. This bit is controlled differently in FIFO vs non-FIFO modes: Non-FIFO mode: This bit will be cleared by HW when Host writes to THR, and set by HW when FW reads from THR. FIFO mode: This bit will be set by HW when XMIT FIFO is empty, and cleared by HW when XMIT FIFO is NOT empty.
4	0x0 RO/C/V	**Break Interrupt (BI):** This bit will be cleared by HW when the UART LSR register is read by Host. This bit will be set by HW in two cases: In FIFO mode, when FW sets the KTRIVR[SBI] bit. In non-FIFO mode, when FW sets the KTRBR[BIA] bit.
3	0x0 RO	**Framing Error (FE):** This bit is NOT implemented and hardwired to 0.
2	0x0 RO	**Parity Error (PE):** This bit is NOT implemented and hardwired to 0.
1	0x0 RO/C/V	**Overrun Error (OE):** HW will clear this bit when Host reads from KTLSR register and this is source of interrupt. HW will set this bit when overrun error is detected. In non-FIFO mode, the character that triggers the overrun error shall overwrite the character in the RBR register. In FIFO mode, the character that triggers the overrun error shall be dropped without corrupting the RCVR FIFO.
0	0x0 RO/V	**Data Ready (DR):** Non-FIFO Mode: this bit will be set by HW when FW writes to RBR and cleared by HW when Host reads from RBR. FIFO Mode: the bit will be set by HW when RCVR FIFO is not empty and cleared by HW when RCVR FIFO is empty.

52.12.11 KT Modem Status register (IO_KTMSR)—Offset 6h

This register implements the standard Modem Status register in the KT Block. It provides the current state of the control lines from the modem. The modem functionality is emulated by the FW.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 6h

Default: 00h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Data Carrier Detect (DCD):** In Loop Back mode this bit is connected by HW to the value of MCR bit 3
6	0x0 RO	**Ring Indicator (RI):** In Loop Back mode this bit is connected by HW to the value of MCR bit 2.
5	0x0 RO	**Data Set Ready (DSR):** In Loop Back mode this bit is connected by HW to the value of MCR bit 0.
4	0x0 RO	**Clear To Send (CTS):** In Loop Back mode this bit is connected by HW to the value of MCR bit 1.
3	0x0 RO/C/V	**Delta Data Carrier Detect (DDCD):** This bit is set when bit 7 is changed. This bit is cleared by HW when the MSR register is being read by the HOST driver.
2	0x0 RO/C/V	**Trailing Edge of Read Detector (TERI):** This bit is set when bit 6 is changed from 1 to 0. This bit is cleared by HW when the MSR register is being read by the Host driver.
1	0x0 RO/C/V	**Delta Data Set Ready (DDSR):** This bit is set when bit 5 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver.
0	0x0 RO/C/V	**Delta Clear To Send (DCTS):** This bit is set when bit 4 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver.

52.12.12 KT Scratch register (IO_KTSCR)—Offset 7h

This register implements the standard Scratch register in the KT Block. It allows Host SW programmers to hold temporary data. It has NO effect on HW.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 7h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:24, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Scratch Register Data (SCRD):** Reserved.

52.13 Registers in I/O Space—IDE_HOST_PCMDIOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IDE_HOST_PCMDIOBAR described in Section 52.6.5, "IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h" on page 2308.

52.13.1 IDE Data Register (IDEDATA)—Offset 0h

This register serves as the data interface in IDE PIO modes. Unit of access is in WORD. Host writes to this register are converted into writes to the PIO buffer in CSxE memory at monotonically increasing WORD address. Host writes are dropped under any one of the following conditions: (1) PIO modes are disabled. (Cfg. IDEPBPR[EN] defined in CSxE memory space) (2) PIO buffer is full. Host reads from this register are converted into reads from the PIO buffer in CSxE memory at monotonically increasing WORD address. Host reads are dropped under any one of the following conditions: (1) PIO modes are disabled. (Cfg. IDEPBPR[EN] defined in CSxE memory space) (2) PIO buffer is empty.

Reset condition: no connection to any reset signal.

Type: I/O Register
(Size: 16 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 0h

Default: 0000h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/V	**IDE Data Register (IDEDR):** Data interface in IDE PIO modes. Host reads/writes from/to this register are converted into reads/writes from/to the PIO buffer in CSxE memory.

52.13.2 IDE Features Register (IDEFR)—Offset 1h

This register implements the standard Features register in the Primary IDE Command Block. This is write-only. BE[0] shall be deasserted.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 1h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Features Data (IDEFD):** The IDE Features register is command specific and is used to enable and disable interface features.

52.13.3 IDE Error Register DEV0 (IDEERD0)—Offset 1h

This register implements the standard Device 0 Error register in the Primary IDE Command Block. This is read-only. BE[0] shall be deasserted. DEV = 0 (i.e. IDEDHIR[4] = 0).

Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 1h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Error Data (IDEED):** Upon command completion of any command except EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET, the content of this register is valid and contains error status when the ERR bit is set to 1 in the Status register (i.e. IDESR0[ERR] = 1). Following a power-on, a hardware or software reset, or command completion of an EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET command, this register contains a diagnostic code. Bit 2 ABRT (command aborted) is set to 1 to indicate the requested command has been command aborted because the command code or a command parameter is invalid, the command is not supported, a pre-requisite for the command has not been met, or some other error has occurred.

52.13.4 IDE Error Register DEV1 (IDEERD1)—Offset 1h

This register implements the standard Device 1 Error register in the Primary IDE Command Block. This is read-only. BE[0] shall be deasserted. DEV = 1 (i.e. IDEDHIR[4] = 1).

Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 1h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Error Data (IDEED):** Upon command completion of any command except EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET, the content of this register is valid and contains error status when the ERR bit is set to 1 in the Status register (i.e. IDESR0[ERR] = 1). Following a power-on, a hardware or software reset, or command completion of an EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET command, this register contains a diagnostic code. Bit 2 ABRT (command aborted) is set to 1 to indicate the requested command has been command aborted because the command code or a command parameter is invalid, the command is not supported, a pre-requisite for the command has not been met, or some other error has occurred.

52.13.5 IDE Sector Count In Register (IDESCIR)—Offset 2h

This register implements the standard Sector Count In register in the Primary IDE Command Block. All 3 registers (IDESCIR, IDESCOR0, IDESCOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is meaningful for an ATA command while unused for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 2h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Sector Count Data (IDESCD):** The Sector Count register specifies the sector count of the data for which an ATA transfer has been made.

52.13.6 IDE Sector Count Out Register DEV0 (IDESCOR0)—Offset 2h

This register implements the standard Device 0 Sector Count Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA/ATAPI command. This register is called IDE Interrupt Reason Register DEV0 for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 2h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Count Out DEV0 (ISCOD0):** Sector Count Out register for Device 0

52.13.7 IDE Sector Count Out Register DEV1 (IDESCOR1)—Offset 2h

This register implements the standard Device 1 Sector Count Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA/ATAPI command. This register is called IDE Interrupt Reason Register DEV1 for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 2h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Count Out DEV1 (ISCOD1):** Sector Count Out register for Device 1

52.13.8 IDE Sector Number In Register (IDESNIR)—Offset 3h

This register implements the standard Sector Number In register in the Primary IDE Command Block in CHS addressing mode. All 3 registers (IDESNIR, IDESNOR0, IDESNOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is called IDE LBA Low In Register in LBA addressing mode. This register is reserved for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 3h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Sector Number Data (IDESND):** The Sector Number register is set by the host to specify the starting sector number associated with the next ATA command to be executed. Following a qualified ATA command sequence the device will set the register value to the last sector read or written as a result of the previous ATA command.

52.13.9 IDE Sector Number Out Register DEV0 (IDESNOR0)—Offset 3h

This register implements the standard Device 0 Sector Number Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Low Out Register DEV0 in LBA addressing mode. This register is reserved for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 3h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Number Out DEV0 (IDESNO0):** Sector Number Out register for Device 0

52.13.10 IDE Sector Number Out Register DEV1 (IDESNOR1)—Offset 3h

This register implements the standard Device 1 Sector Number Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Low Out Register DEV1 in LBA addressing mode. This register is reserved for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 3h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Number Out DEV1 (IDESNO1):** Sector Number Out register for Device 1

52.13.11 IDE Cylinder Low In Register (IDECLIR)—Offset 4h

This register implements the standard Cylinder Low In register in the Primary IDE Command Block. All 3 registers (IDECLIR, IDCLOR0, IDCLOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is called IDE LBA Mid In Register in LBA addressing mode. This register is called IDE Byte Count Low Limit Register for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 4h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Cylinder Low Data. (IDECLD):** The Cylinder Low register is set by the host to specify the cylinder number low byte. Following an ATA command, the contents of this register is written by the device, identifying the cylinder number low byte.

52.13.12 IDE Cylinder Low Out Register DEV0 (IDCLOR0)—Offset 4h

This register implements the standard Device 0 Cylinder Low Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Mid Out Register DEV0 in LBA addressing mode. This register is called IDE Byte Count Low Register DEV0 for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 4h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder Low Out DEV0. (IDECLO0):** Cylinder Low Out Register for Device 0.

52.13.13 IDE Cylinder Low Out Register DEV1 (IDCLOR1)—Offset 4h

This register implements the standard Device 1 Cylinder Low Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Mid Out Register DEV1 in LBA addressing mode. This register is called IDE Byte Count Low Register DEV1 for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 4h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder Low Out DEV1. (IDECLO1):** Cylinder Low Out Register for Device 1.

52.13.14 IDE Cylinder High In Register (IDECHIR)—Offset 5h

This register implements the standard Cylinder High In register in the Primary IDE Command Block. All 3 registers (IDECHIR, IDCHOR0, IDCHOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is called IDE LBA High In Register in LBA addressing mode. This register is called IDE Byte Count High Limit Register for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 5h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Cylinder High Data (IDECHD):** The Cylinder High register is set by the host to specify the cylinder number high byte. Following an ATA command, the contents of this register is written by the device, identifying the cylinder number high byte.

52.13.15 IDE Cylinder High Out Register DEV0 (IDCHOR0)—Offset 5h

This register implements the standard Device 0 Cylinder High Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA High Out Register DEV0 in LBA addressing mode. This register is called IDE Byte Count High Register DEV0 for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 5h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder High Out DEV0 (IDECHO0):** Cylinder High Out register for Device 0

52.13.16 IDE Cylinder High Out Register DEV1 (IDCHOR1)—Offset 5h

This register implements the standard Device 1 Cylinder High Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA High Out Register DEV1 in LBA addressing mode. This register is called IDE Byte Count High Register DEV1 for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 5h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder High Out DEV1 (IDECHO1):** Cylinder High Out register for Device 1

52.13.17 IDE Drive/Head In Register (IDEDHIR)—Offset 6h

This register implements the standard Drive/Head In register in the Primary IDE Command Block. All 3 registers (IDEDHIR, IDDHOR0, IDDHOR1) will be updated with the same write data when this register is write-accessed. This is write-only. Bit 4 of this register is the DEV (master/slave) bit. This bit is cleared by hardware on IDE software reset (IDDCR[SRST] = 1) in addition to Host reset. This register is called IDE Device In Register in LBA addressing mode or for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 6h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Drive/Head Data (IDEDHD):** The Drive/Head Register is used by the host and the device to select the type of addressing (CHS or LBA), the drive letter, and either bits 3 through 0 of the head number in CHS mode or in LBA mode, bits D3:D0 reflect the logical block number bits LBA27:LBA24.

52.13.18 IDE Drive/Head Out Register DEV0 (IDDHOR0)—Offset 6h

This register implements the standard Device 0 Drive/Head Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE Device Out Register DEV0 in LBA addressing mode or for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 6h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Drive/Head Out DEV0 (IDEDHO0):** Drive/Head Out register of Device 0

52.13.19 IDE Drive/Head Out Register DEV1 (IDDHOR1)—Offset 6h

This register implements the standard Device 1 Drive/Head Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE Device Out Register DEV1 in LBA addressing mode or for an ATAPI command.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 6h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Drive/Head Out DEV1 (IDEDHO1):** Drive/Head Out register of Device 1

52.13.20 IDE Command Register (IDECR)—Offset 7h

This register implements the standard Command register in the Primary IDE Command Block. This is write-only.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 7h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Command Data (IDECD):** The Command register specifies the ATA/ATAPI Command code being issued to the drive by the host. Command processing begins when this register is written. The content of the Command Block registers becomes parameters of the command when this register is written. Writing this register clears any pending interrupt condition. Please refer to the description of the INTM and INTS bits in the IDGCR register in the CSxE memory space for detailed conditions under which interrupt condition shall be cleared.

52.13.21 IDE Status Register DEV0 (IDESR0)—Offset 7h

This register implements the standard Device 0 Status register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA/ATAPI command. Additionally upon completion of the last data phase of a PIO transfer, HW will load this register with value of the SRAFP field in the IDESRAP register in the CSxE memory space. Host read of this register clears Device 0's interrupt. Please refer to the description of the INTM bit in the IDGCR register in the CSxE memory space for detailed conditions under which interrupt condition shall be cleared. The bit description is for ATA mode. Different name in ATAPI mode, if applicable, is cited as well.

Reset condition: CSxE reset with the BSY bit as an exception. Please refer to description of the BSY bit below for a list of BSY bit reset conditions. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 7h

Default: 80h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Busy (BSY):** This bit is set by HW when the IDECR is being written and DEV=0, OR when IDDCR[SRST] bit is asserted by Host, OR host system reset, OR D3 to D0 transition of the IDE function. This bit is cleared by FW write of 0. Please refer to general register description above for special handling for a PIO transfer. When this bit is 1, any other bit in this register is meaningless.
6	0x0 RO/V	**Drive Ready (DRDY):** When set, indicates drive is ready for command. Update of this bit is completely FW-assisted. This bit is also called Device Ready. Please refer to general register description above for special handling for a PIO transfer.
5	0x0 RO/V	**Drive Fault (DF):** When set, indicates Error on the drive. Update of this bit is completely FW-assisted. This bit is called DMA Ready for a DMA ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
4	0x0 RO/V	**Drive Seek Complete (DSC):** When set, indicates Heads are positioned over the desired cylinder. Update of this bit is completely FW-assisted. This bit is called Service for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
3	0x0 RO/V	**Data Request (DRQ):** Set when the drive wants to exchange data with the Host via the data register. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
2	0x0 RO/V	**Corrected Data (CORR):** When set, indicates a correctable read error has occurred. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
1	0x0 RO/V	**Index (IDX):** This bit is set once per rotation of the medium when the index mark passes under the read/write head. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
0	0x0 RO/V	**Error (ERR):** When set, indicates an error occurred in the process of executing the current command. The Error Register of the selected device contains the error information. Update of this bit is completely FW-assisted. This bit is called Check for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.

52.13.22 IDE Status Register DEV1 (IDESR1)—Offset 7h

This register implements the standard Device 1 Status register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA/ATAPI command. Additionally upon completion of the last data phase of a PIO transfer, HW will load this register with value of the SRAFP field in the IDESRAP register in the CSxE memory space. Host read of this register clears Device 1's interrupt. Please refer to the description of the INTM bit in the IDGCR register in the CSxE memory space for detailed conditions under which interrupt condition shall be cleared. The bit description is for ATA mode. Different name in ATAPI mode, if applicable, is cited as well.

Reset condition: CSxE reset with the BSY bit as an exception. Please refer to description of the BSY bit below for a list of BSY bit reset conditions. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 7h

Default: 80h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:24, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Busy (BSY):** This bit is set by HW when the IDECR is being written and DEV=1, OR when IDDCR[SRST] bit is asserted by Host, OR host system reset, OR D3 to D0 transition of the IDE function. This bit is cleared by FW write of 0. Please refer to general register description above for special handling for a PIO transfer. When this bit is 1, any other bit in this register is meaningless.
6	0x0 RO/V	**Drive Ready (DRDY):** When set, indicates drive is ready for command. Update of this bit is completely FW-assisted. This bit is also called Device Ready. Please refer to general register description above for special handling for a PIO transfer.
5	0x0 RO/V	**Drive Fault (DF):** When set, indicates Error on the drive. Update of this bit is completely FW-assisted. This bit is called DMA Ready for a DMA ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
4	0x0 RO/V	**Drive Seek Complete (DSC):** When set, indicates Heads are positioned over the desired cylinder. Update of this bit is completely FW-assisted. This bit is called Service for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
3	0x0 RO/V	**Data Request (DRQ):** Set when the drive wants to exchange data with the Host via the data register. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
2	0x0 RO/V	**Corrected Data (CORR):** When set, indicates a correctable read error has occurred. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
1	0x0 RO/V	**Index (IDX):** This bit is set once per rotation of the medium when the index mark passes under the read/write head. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
0	0x0 RO/V	**Error (ERR):** When set, indicates an error occurred in the process of executing the current command. The Error Register of the selected device contains the error information. Update of this bit is completely FW-assisted. This bit is called Check for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.

52.14 Registers in I/O Space—IDE_HOST_PCTLIOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IDE_HOST_PCTLIOBAR described in described in Section 52.6.6, "IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h" on page 2308.

52.14.1 IDE Device Control Register (IDDCR)—Offset 2h

This register implements the standard Device Control register in the Primary IDE Control Block. This is write-only. BE[0] shall be deasserted.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCTLIOBAR] + 2h

Default: 00h

IDE_HOST_PCTLIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCTLIOBAR Reference: [B:0, D:24, F:2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 WO	**Reserved (RSVD1):** Writable by Host, but NO HW effect due to writes.
2	0x0 WO	**Software Reset (SRST):** • 1: both devices shall perform the software reset protocol. • 0: both devices shall exit software reset.
1	0x0 WO	**Host Interrupt Disable (nIEN):** • 1: disables HW from generating interrupt to the Host. • 0: enables HW to generate interrupt to the Host.
0	0x0 WO	**Reserved (RSVD0):** Writable by Host, but NO HW effect due to writes.

52.14.2 IDE Alternate Status Register (IDASR)—Offset 2h

This register implements the standard Alternate Status register in the Primary IDE Control Block. This is read-only. It shadows the standard Status registers in the Primary IDE Command Block. Read of this register does NOT clear the interrupt status bits in the selected Status register. IDESR0 is shadowed when DEV = 0 (i.e. IDEDHIR[4] = 0). IDESR1 is shadowed when DEV = 1 (i.e. IDEDHIR[4] = 1).

Reset condition: There is no reset associated with this register because it is NOT a physical register.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCTLIOBAR] + 2h

Default: 00h

IDE_HOST_PCTLIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCTLIOBAR Reference: [B:0, D:24, F:2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Alternate Status Register (IDEASR):** Shadows DEV0/DEV1 Status register on Host reads depending on IDEDHIR[4] setting.

52.15 Registers in I/O Space—IDE_HOST_BMIOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IDE_HOST_BMIOBAR described in described in Section 52.6.9, "IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h" on page 2310.

52.15.1 IDE Primary Bus Master Command Register (IDEPBMCR)—Offset 0h

This register implements the standard IDE Primary Bus Master Command register in the IDE Bus Master Block.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 0h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD1):** Not implemented. Hardwired to 0.
3	0x0 RW	**Read or Write Control (RWC):** This bit sets the direction of the bus master transfer. • 0: reads are performed from Host system memory. • 1: writes are performed to Host system memory. This bit shall NOT be changed when the bus master function is active.
2:1	0x0 RO	**Reserved (RSVD0):** Not implemented. Hardwired to 0.
0	0x0 RW/V	**Start/Stop Bus Master (SSBM):** Host starts a bus master operation in the device by setting this bit to 1. The device shall only transfer data between the ATA device and Host memory in the bus master operation. Host stops the bus master operation by clearing this bit to 0. All state information will be lost when 0 is written. Host CANNOT stop and then resume the bus master operation. When Host clears this bit to 0 while the bus master operation is still active, the bus master operation will be aborted and data transferred from the device may be discarded before being written to host memory. In any event the device should terminate any DMA burst in progress compliant with the ATA protocol being used. If the UDMA protocol is being used, there may be a CRC error report. The ATA device may be in an indeterminate state. HW will clear this bit to 0 after the data transfer has been completed, as indicated by satisfaction of either of the following conditions: (1) IDEPBMSR[BMIA] is cleared to 0. OR (2) IDEPBMSR[INT] is set to 1.

52.15.2 IDE Primary Bus Master Device Specific 0 Register (IDEPBMDS0R)—Offset 1h

This register implements the standard IDE Primary Bus Master Device Specific 0 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data.

Reset condition: CSxE reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 1h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Device Specific Data0 (DSD0):** Device Specific

52.15.3 IDE Primary Bus Master Status Register (IDEPBMSR)—Offset 2h

This register implements the standard IDE Primary Bus Master Status register in the IDE Bus Master Block.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + 2h

Default: 80h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Simplex Only (SO):** This bit indicates whether or not both bus master channels (primary and secondary) can be operated at the same time. If the bit is 0, both channels operate independently and can be used at the same time. If the bit is 1, only one channel may be used at a time. Reset condition: CSxE reset. Non-sticky.
6	0x0 RW/V	**Device 1 DMA Capable (D1DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 1 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance. Reset condition: Host reset. Non-sticky.
5	0x0 RW/V	**Device 0 DMA Capable (D0DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 0 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance. Reset condition: Host reset. Non-sticky.
4:3	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
2	0x0 RW/1C/V	**Interrupt (INT):** HW shall set this bit to 1 on rising edge detection of the ATA channels interrupt line (INTRQ). Host SW writes 1 to clear this bit. Host SW can use this bit to determine if an ATA device has asserted its interrupt line (INTRQ) (see ATA standard). When this bit is 1, all data MUST have been transferred to the Hosts system memory. The adapter shall not set this bit to 1 until it has flushed all internal data buffers. NOTE: When INTRQ is deasserted, HW won't clear this bit atomically. When INTRQ is deasserted, this bit shall be cleared as well by Host SW writing 1 to this bit. Reset condition: CSxE reset. Non-sticky.
1	0x0 RW/1C/V	**Error (ER):** FW will set this bit to 1 when the device encounters an error in transferring data to/from Host memory. The exact error condition is bus specific and can be determined in a bus specific manner. Host SW writes 1 to clear this bit. Reset condition: CSxE reset. Non-sticky.

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RO/V	**Bus Master IDE Active (BMIA):** HW shall set this bit when (1) Host sets the IDEPBMCR[SSBM] bit. FW shall clear this bit when (1) The last transfer for a region is performed, where EOT for that region is set in the region descriptor. OR (2) FW detects that Host cleared IDEPBMCR[SSBM] bit as indicated by a value of 1 in proxy bit IDEBMCR[SSBMC] in CSxE root space. Before clearing this bit to 0, FW must satisfy the following conditions in addition: (1) All data transferred from the device during the previous bus master command has been transferred to the Hosts system memory, unless the bus master command was aborted. OR (2) All data has been written to the device. Reset condition: CSxE reset. Non-sticky.

52.15.4 IDE Primary Bus Master Device Specific 1 Register (IDEPBMDS1R)—Offset 3h

This register implements the standard IDE Primary Bus Master Device Specific 1 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data.

Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 3h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Device Specific Data1 (DSD1):** Device Specific Data

52.15.5 IDE Primary Bus Master Descriptor Table Pointer Register Byte 0 (IDEPBMDTPR0)—Offset 4h

This register implements the Byte 0 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 4h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 0 (DTPB0):** Byte 0 of the Descriptor Table pointer. The Descriptor Table shall be DW-aligned. Hence bit[1:0] shall always be 0.

52.15.6 IDE Primary Bus Master Descriptor Table Pointer Register Byte 1 (IDEPBMDTPR1)—Offset 5h

This register implements the Byte 1 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 5h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 1 (DTPB1):** Byte 1 of the Descriptor Table pointer.

52.15.7 IDE Primary Bus Master Descriptor Table Pointer Register Byte 2 (IDEPBMDTPR2)—Offset 6h

This register implements the Byte 2 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + 6h

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 2 (DTPB2):** Byte 2 of the Descriptor Table pointer.

52.15.8 IDE Primary Bus Master Descriptor Table Pointer Register Byte 3 (IDEPBMDTPR3)—Offset 7h

This register implements the Byte 3 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + 7h

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 3 (DTPB3):** Byte 3 of the Descriptor Table pointer.

52.15.9 IDE Secondary Bus Master Command Register (IDESBMCR)—Offset 8h

This register implements the standard IDE Secondary Bus Master Command register in the IDE Bus Master Block. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 8h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD1):** Not implemented. Hardwired to 0.
3	0x0 RW	**Read or Write Control (RWC):** This bit sets the direction of the bus master transfer. • 0: reads are performed from Host system memory. • 1: writes are performed to Host system memory. This bit shall NOT be changed when the bus master function is active.
2:1	0x0 RO	**Reserved (RSVD0):** Not implemented. Hardwired to 0.
0	0x0 RW	**Start/Stop Bus Master (SSBM):** Host starts a bus master operation in the device by setting this bit to 1. The device shall only transfer data between the ATA device and Host memory in the bus master operation. Host stops the bus master operation by clearing this bit to 0. All state information will be lost when 0 is written. Host CANNOT stop and then resume the bus master operation.

52.15.10 IDE Secondary Bus Master Device Specific 0 Register (IDESBMDS0R)—Offset 9h

This register implements the standard IDE Secondary Bus Master Device Specific 0 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 9h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Device Specific Data0 (DSD0):** Device Specific

52.15.11 IDE Secondary Bus Master Status Register (IDESBMSR)—Offset Ah

This register implements the standard IDE Secondary Bus Master Status register in the IDE Bus Master Block. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset with the SO bit as an exception. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Ah

Default: 80h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Simplex Only (SO):** Value indicates whether both Bus Master Channels can be operated at the same time or not. • 0: Both can be operated independently • 1: Only one can be operated at a time. This bit shadows IDEPBMSR[SO]. Reset condition: CSxE reset. Non-sticky.
6	0x0 RW	**Device 1 DMA Capable (D1DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 1 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance.
5	0x0 RW	**Device 0 DMA Capable (D0DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 0 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance.
4:3	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
2	0x0 RO	**Interrupt (INT):** No functionality implemented. Hardwired to 0.
1	0x0 RO	**Error (ER):** Not implemented. Hardwired to 0.
0	0x0 RO	**Bus Master IDE Active (BMIA):** Not implemented. Hardwired to 0.

52.15.12 IDE Secondary Bus Master Device Specific 1 Register (IDESBMDS1R)—Offset Bh

This register implements the standard IDE Secondary Bus Master Device Specific 1 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Bh

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Device Specific Data1 (DSD1):** Device Specific Data

52.15.13 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0 (IDESBMDTPR0)—Offset Ch

This register implements the Byte 0 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Ch

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 0 (DTPB0):** Byte 0 of the Descriptor Table pointer. The Descriptor Table shall be DW-aligned. Hence bit[1:0] shall always be 0.

52.15.14 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1 (IDESBMDTPR1)—Offset Dh

This register implements the Byte 1 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Dh

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 1 (DTPB1):** Byte 1 of the Descriptor Table pointer.

52.15.15 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2 (IDESBMDTPR2)—Offset Eh

This register implements the Byte 2 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Eh

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 2 (DTPB2):** Byte 2 of the Descriptor Table pointer.

52.15.16 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3 (IDESBMDTPR3)—Offset Fh

This register implements the Byte 3 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register.

Reset condition: Host reset. Non-sticky.

Type: I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + Fh

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:24, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 3 (DTPB3):** Byte 3 of the Descriptor Table pointer.

52.16 Sideband Registers—KT (Host)

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

52.16.1 KT Host Interrupt Pin Register (KTHIPINR)—Offset 0h

This register provides for BIOS to specify which interrupt pin KT shall use in the Host root space when generating an interrupt in the PCI legacy mode.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xe4] + 0h
Host Memory Space: SBREG_BAR + 0xe40000 + 0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
7:0	0x0 RW/O	**Interrupt Pin (IPIN):** BIOS writes to this field once to specify which interrupt pin KT shall use. After written once, this register will become read-only. This field shall be shadowed into the Interrupt Pin register in the PCI header of the KT Host PCI function. Value Decoding • 00h The function does NOT use an interrupt pin. • 01h INTA • 02h INTB • 03h INTC • 04h INTD • 05h - FFh Reserved Reset condition: Host side reset. Non-sticky.

52.16.2 BIOS KT Host PCI Function Disable Register (BKTHDISR)—Offset 4h

This register provides for BIOS to enable or disable the KT Host PCI function.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xe4] + 4h
Host Memory Space: SBREG_BAR + 0xe40000 + 4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
0	0x0 RW	**Host PCI Function Disable (HDIS):** BIOS sets this bit to disable the KT Host PCI function. BIOS clears this bit to enable the KT Host PCI function. Reset condition: Host side reset. Non-sticky.

52.17 Sideband Registers—IDE (Host)

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

52.17.1 IDE Host Interrupt Pin Register (IDEHIPINR)—Offset 0h

This register provides for BIOS to specify which interrupt pin IDE shall use in the Host root space when generating an interrupt in the PCI legacy mode.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xe4] + 0h
Host Memory Space: SBREG_BAR + 0xe40000 + 0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
7:0	0x0 RW/O	**Interrupt Pin (IPIN):** BIOS writes to this field once to specify which interrupt pin IDE shall use. After written once, this register will become read-only. This field shall be shadowed into the Interrupt Pin register in the PCI header of the IDE Host PCI function. Value Decoding 00h The function does NOT use an interrupt pin. 01h INTA 02h INTB 03h INTC 04h INTD 05h - FFh Reserved Reset condition: Host side reset. Non-sticky.

52.17.2 BIOS IDE Host PCI Function Disable Register (BIDEHDISR)—Offset 4h

This register provides for BIOS to enable or disable the IDE Host PCI function.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xe4] + 4h
Host Memory Space: SBREG_BAR + 0xe40000 + 4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
0	0x0 RW	**Host PCI Function Disable (HDIS):** BIOS sets this bit to disable the IDE Host PCI function. BIOS clears this bit to enable the IDE Host PCI function. Reset condition: Host side reset. Non-sticky.

§ §

53 HSUART Controller - B0, D26, F(0, 1, 2)

53.1 Introduction and Index

The host-accessible registers for the HSUART Controller are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, “Features by product SKU - Server and Cloud Storage SKUs 0 through 4”
- Table 1-2, “Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10”
- Table 1-3, “Features by Product SKU - Extended Temperature SKUs 11 through 14”.

The legend for the register access codes are described in Chapter 43, “Introduction.”

53.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 26 (decimal), Function (0, 1, 2). The offset addresses are listed.

Table 53-1. Summary of PCI Configuration Registers—0/26/0,1,2

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19D88086	"VENDOR_DEVICE_ID—Offset 0h" on page 2387
4	4	00100000	"CMD_STAT_REG—Offset 4h" on page 2388
8	4	07000200	"REV_CLASS_CODE—Offset 8h" on page 2390
C	4	00800000	"CACHE—Offset Ch" on page 2390
10	4	00000001	"IOBA—Offset 10h" on page 2391
14	4	00000000	"MEMBA—Offset 14h" on page 2391
2C	4	00008086	"SUBSYSTEM_VENDOR_ID—Offset 2Ch" on page 2392
34	4	00000040	"CAP_PTR—Offset 34h" on page 2392
3C	4	000001FF	"INTERRUPT—Offset 3Ch" on page 2392
40	4	00005005	"MSIC—Offset 40h" on page 2393
44	4	00000000	"MSIA—Offset 44h" on page 2394
48	4	00000000	"MSID—Offset 48h" on page 2394
50	4	00030001	"PMC—Offset 50h" on page 2395
54	4	00000008	"PMCSR—Offset 54h" on page 2396
60	4	00000000h	"DSC—Offset 60h" on page 2397
74	4	00000000h	"FUNC_RDCFG_HIDE—Offset 74h" on page 2398

53.1.2 Host Memory Space—MEMBA

An index of the registers that are accessible in Host Memory Space is shown here. There is a set of these registers for each of the three HSUART Functions (F0, F1, and F2).

Table 53-2. Summary of Memory Mapped I/O Registers—MEMBA

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"RBR_THR_DLL—Offset 0h" on page 2399
1	1	00	"IER_DLH—Offset 1h" on page 2399
2	1	00	"IIR_FCR—Offset 2h" on page 2400
3	1	00	"LCR—Offset 3h" on page 2400
4	1	00	"MCR—Offset 4h" on page 2402
5	1	60	"LSR—Offset 5h" on page 2404
6	1	00	"MSR—Offset 6h" on page 2406
7	1	00	"SPR—Offset 7h" on page 2408
8	4	00000000	"UART_FISR—Offset 8h" on page 2408
20	4	00000000	"RFOR—Offset 20h" on page 2408
24	4	00000010	"ABR—Offset 24h" on page 2409
28	4	00000000	"ACR—Offset 28h" on page 2410
30	4	00000010	"PSR—Offset 30h" on page 2410
34	4	000000D8	"UCMR—Offset 34h" on page 2410
38	4	00003D09	"UCDR—Offset 38h" on page 2411
80	4	000F0000	"CH0SR—Offset 80h" on page 2412
84	4	00000000	"CH0CR—Offset 84h" on page 2412
88	4	00008000	"CH0DCR—Offset 88h" on page 2414
90	4	00000000	"CH0BSR—Offset 90h" on page 2415
94	4	00000000	"CH0MTSR—Offset 94h" on page 2415
A0	4	00000000	"CH0D0SAR—Offset A0h" on page 2415
A4	4	00000000	"CH0D0TSR—Offset A4h" on page 2416
A8	4	00000000	"CH0D1SAR—Offset A8h" on page 2416
AC	4	00000000	"CH0D1TSR—Offset ACh" on page 2416
B0	4	00000000	"CH0D2SAR—Offset B0h" on page 2417
B4	4	00000000	"CH0D2TSR—Offset B4h" on page 2417
B8	4	00000000	"CH0D3SAR—Offset B8h" on page 2418
BC	4	00000000	"CH0D3TSR—Offset BCh" on page 2418
C0	4	000F0000	"CH1SR—Offset C0h" on page 2419
C4	4	00000000	"CH1CR—Offset C4h" on page 2420
C8	4	00008000	"CH1DCR—Offset C8h" on page 2421
D0	4	00000000	"CH1BSR—Offset D0h" on page 2422
D4	4	00000000	"CH1MTSR—Offset D4h" on page 2422
E0	4	00000000	"CH1D0SAR—Offset E0h" on page 2422
E4	4	00000000	"CH1D0TSR—Offset E4h" on page 2423

Table 53-2. Summary of Memory Mapped I/O Registers—MEMBA (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
E8	4	00000000	"CH1D1SAR—Offset E8h" on page 2423
EC	4	00000000	"CH1D1TSR—Offset ECh" on page 2423
F0	4	00000000	"CH1D2SAR—Offset F0h" on page 2424
F4	4	00000000	"CH1D2TSR—Offset F4h" on page 2424
F8	4	00000000	"CH1D3SAR—Offset F8h" on page 2425
FC	4	00000000	"CH1D3TSR—Offset FCh" on page 2425

53.1.3 Host I/O Space—IOBA

An index of the registers that are accessible in Host I/O Space is shown here. There is a set of these registers for each of the three HSUART Functions (F0, F1, and F2).

Table 53-3. Summary of I/O Registers—IOBA

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"RBR_THR_DLL—Offset 0h" on page 2426
1	1	00	"IER_DLH—Offset 1h" on page 2426
2	1	00	"IIR_FCR—Offset 2h" on page 2427
3	1	00	"LCR—Offset 3h" on page 2428
4	1	00	"MCR—Offset 4h" on page 2430
5	1	00	"LSR—Offset 5h" on page 2432
6	1	00	"MSR—Offset 6h" on page 2434
7	1	00	"SPR—Offset 7h" on page 2436

53.2 Registers in Configuration Space

53.2.1 VENDOR_DEVICE_ID—Offset 0h

Note: The default value of DEVICE_ID can be overwritten using the setidval sideband message.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 0h

Default: 19D88086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19d8 RO/V	**DEVICE_ID:** Device ID
15:0	0x8086 RO	**VENDOR_ID:** Identifies uniquely Intel products.

53.2.2 CMD_STAT_REG—Offset 4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 4h

Default: 00100000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**STATUS_DETECTED_PARITY_ERROR:** Detected Parity Error. This bit is set when the device receives an uncorrectable data error or parity error regardless of the Parity Error Response bit (CMD_STAT_REG.COMMAND_PARITY_ERROR_RESPONSE_ENABLE).
30	0x0 RW/1C	**STATUS_SIGNALED_SYSTEM_ERROR:** Signaled System Error. Never expected to be asserted. This bit is set when the device has detected an uncorrectable error and reported it via SERR message over sideband. This requires SERR Enable bit to be set in Command register.
29	0x0 RW/1C	**STATUS_RECEIVED_MASTER_ABORT:** Received Master Abort. This bit is set when device receives a Completion transaction with Unsupported Request completion status. No error will be reported.
28	0x0 RW/1C	**STATUS_RECEIVED_TARGET_ABORT:** Received Target Abort. This bit is set when device receives a Completion transaction with Completer Abort completion status. No error will be reported.
27	0x0 RW/1C	**STATUS_SIGNALED_TARGET_ABORT:** Signaled Target Abort. Set by the device when aborting a request that violates the device programming model. When SERR Enable is set SERR message will be send over sideband.
26:25	0x0 RSV	**STATUS_RESERVED_25:** Reserved.
24	0x0 RW/1C	**STATUS_MASTER_DATA_PARITY_ERROR:** Master Data Parity Error. This bit is set if the Parity Error Response bit (CMD_STAT_REG.COMMAND_PARITY_ERROR_RESPONSE_ENABLE) is set and it receives a completion with poisoned data from IOSF.
23:21	0x0 RSV	**STATUS_RESERVED_21:** Reserved.
20	0x1 RO	**STATUS_NEW_CAP:** New Capabilities. Indicates that a device implements extended capabilities. The Controller sets this bit, and implements a capabilities list.
19	0x0 RO/V	**STATUS_INTERRUPT_STATUS:** Interrupt Status. The Interrupt Status field is a RO field that indicates that an interrupt message is pending internally to the device.
18:16	0x0 RSV	**STATUS_RESERVED_16:** Reserved.
15:11	0x0 RSV	**COMMAND_RESERVED_11:** Reserved.
10	0x0 RW	**COMMAND_INTERRUPT_DISABLE:** Interrupt Disable. Controls the ability of a device to generate a legacy interrupt message. When set, the device cannot generate legacy interrupt messages.

Bit Range	Default & Access	Field Name (ID): Description
9	0x0 RSV	**COMMAND_RESERVED_9:** Reserved.
8	0x0 RW	**COMMAND_SERR_ENABLE:** SERR# Enable
7	0x0 RSV	**COMMAND_RESERVED_7:** Reserved.
6	0x0 RW	**COMMAND_PARITY_ERROR_RESPONSE_ENABLE:** Parity Error Response. This bit controls the setting of STATUS_MASTER_DATA_PARITY_ERROR. 0 = Parity errors can be ignored by the device. 1 = Device can report parity errors.
5:3	0x0 RSV	**COMMAND_RESERVED_3:** Reserved.
2	0x0 RW	**COMMAND_BUS_ACCESS_ENABLE:** Must be set to 1 for the device to initiate memory read and write requests as a master. This bit does not affect a device's ability to generate MSI message, Error Message, or completion cycles as a target.
1	0x0 RW	**COMMAND_MEM_ACCESS_ENABLE:** Memory Access Enable
0	0x0 RW	**COMMAND_IO_ACCESS_ENABLE:** When set, IO Space Decoding is enabled and IO transactions targeting the device are accepted.

53.2.3 REV_CLASS_CODE—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 8h

Default: 07000200h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x70002 RO	**CLASS_CODE:** The class code is a RO hard-coded value that identifies its functionality. ***Note:*** This field (Programming Interface, Sub Class Code, Base Class Code) is RO from Primary and RW from Sideband.
7:0	0x0 RO/V	**REVISION_ID:** The default revision ID is 0x0.

53.2.4 CACHE—Offset Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + Ch

Default: 00800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RSV	**BIST:** Reserved.
23:16	0x80 RO	**HEADER_TYPE:** This indicates if a device is single-function or multifunction. If a single function is the only active one then this field has a value of 0x00 to indicate a single-function device. If other functions are enabled then this field has a value of 0x80 to indicate a multi-function device.
15:8	0x0 RSV	**RESERVED_1:** Reserved.
7:0	0x0 RSV	**RESERVED_0:** Reserved.

53.2.5 IOBA—Offset 10h

The Base Address registers (BARs) are used to map register space of the various functions. It has a memory BAR, IO BAR.

The internal registers memories are accessed as direct memory mapped offsets from the Base Address register. Software can access a Dword or 64 bits.

Note: If this is a Dummy function the register is RO as 0.

Type: PCI Configuration Register (Size: 32 bits) **Offset:** [B:0, D:26, F:0] + 10h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**BASE_ADDR:** Reserved.
2:1	0x0 RO	**MEMORY_TYPE:** Hardwired to 0 for 8 byte access.
0	0x1 RO	**MEMORY_IO_SPACE:** Reserved.

53.2.6 MEMBA—Offset 14h

The Base Address registers (BARs) are used to map register space of the various functions.

The internal registers memories are accessed as direct memory mapped offsets from the Base Address register. Software can access a Dword or 64 bits.

Type: PCI Configuration Register (Size: 32 bits) **Offset:** [B:0, D:26, F:0] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**BASE_ADDR:** Reserved.
7:4	0x0 RO	**MEM_SIZE:** Set to 0 to indicate 256 byte memory Space.
3	0x0 RO	**PREFETCHABLE:** Set to 0 to indicate MEMBA is not prefetchable.
2:1	0x0 RO	**MEMORY_TYPE:** Set to 0 to indicate the BAR is located in lower 4G space.
0	0x0 RO	**MEMORY_IO_SPACE:** Reserved.

53.2.7 SUBSYSTEM_VENDOR_ID—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 2Ch

Default: 00008086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O/P	**SUBSYSTEM_ID:** ***Note:*** This field is RO from Sideband and RW/O from Primary.
15:0	0x8086 RW/O/P	**SUBSYSTEM_VENDOR_ID:** ***Note:*** This field is RO from Sideband and RW/O from Primary.

53.2.8 CAP_PTR—Offset 34h

The Capabilities Pointer field is an 8 bit field that provides an offset in the device's PCI configuration space for the location of the first item in the Capabilities Linked List (CLL).

Controller sets this bit and implements a capabilities list to indicate that it supports PCI power management, Message Signaled Interrupts (MSIs), and PCIe extended capabilities. Its value is 0x40, which is the address of the first entry: MSI cap.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 34h

Default: 00000040h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RSV	**RESERVED:** Reserved.
7:0	0x40 RO	**CAP_PTR:**

53.2.9 INTERRUPT—Offset 3Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 3Ch

Default: 000001FFh

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED:** Reserved.
15:8	0x1 RW/P/L	**INTERRUPT_PIN:** A value of 0x1, 0x2, 0x3, or 0x4 indicates that this function implements legacy interrupt on INTA#, INTB#, INTC#, or INTD#, respectively. This bit is locked by PLKCTL.CL.
7:0	0xff RW	**INTERRUPT_LINE:** Read/write register programmed by software to indicate which of the system interrupt request lines this controller's interrupt pin is bound to. See the PCIe definition for more details. Each of the PCIe functions has its own register. ***Note:*** For Dummy functions this register is RO as zero.

53.2.10 MSIC—Offset 40h

MSI Capability Register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 40h

Default: 00005005h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RSV	**RESERVED:** Reserved.
23	0x0 RO	**AD64C:** 64-bit capable. A value of 1 indicates it is capable of generating 64-bit message addresses.
22:20	0x0 RW	**MMEN:** Multiple Message Enable. Indicates it supports a single message per function.
19:17	0x0 RO	**MMC:** Multiple Message Capable. Indicates a single requested message per each function.
16	0x0 RW	**MSI_EN:** If set to 1, equals MSI. In this case, controller generates an MSI for interrupt assertion instead of INTx signaling.
15:8	0x50 RO	**NEXT_POINTER:** Next cap Pointer. This field provides an offset to the next capability item in the capability list. Its value of 0x50 points to the PM capability structure.
7:0	0x5 RO	**CAP_ID:** This field equals 0x05 indicating the linked list item as being the MSI registers.

53.2.11 MSIA—Offset 44h

Written by the system to indicate 32 bits of the address to use for the MSI memory write transaction.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**MSIAddr:** Reserved.
1:0	0x0 RO	**MSI_DW:** Value of 0 indicates memory address is always DW aligned.

53.2.12 MSID—Offset 48h

Written by the system to indicate the lower 16 bits of the data written in the MSI memory write Dword transaction. The upper 16 bits of the transaction are written as 0b.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED:** Reserved.
15:0	0x0 RW	**MSID:**

53.2.13 PMC—Offset 50h

All fields are reset on full power-up. All of the fields except PME_En and PME_Status are reset on exit from D3cold state. If aux power is not supplied, the PME_En and PME_Status fields also reset on exit from D3cold state.

Note: See the detailed description for registers loaded from the EEPROM at initialization time. Behavior of some fields depend on the Power Management bit in EEPROM word 0x0A.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 50h

Default: 00030001h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**PME_SUPPORT:** This 5-bit field indicates the power states in which the function may assert PME#. A value of 0b for any bit indicates that the function is not capable of asserting the PME# signal while in that power state.
26	0x0 RO	**D2_SUPPORT:** Does not support D2 state.
25	0x0 RO	**D1_SUPPORT:** Does not support D1 state.
24:22	0x0 RO	**AUX_CURRENT:** Required current defined in the Data Register.
21	0x0 RO	**DSI:** Controller requires its device driver to be executed following transition to the D0 uninitialized state.
20	0x0 RSV	**RESERVED:** Reserved.
19	0x0 RO	**PME_CLOCK:** Disabled; Hardwired to 0.
18:16	0x3 RO	**VERSION:** Complies with the PCI PM specification, revision 1.2
15:8	0x0 RO	**NEXT_POINTER:** This field provides an offset to the next capability item in the capability list. Value of 0xA0 points to the PCI Express capability.
7:0	0x1 RO	**CAP_ID:** This fields equals 0x01 indicating the linked list item as being the PCI Power Management registers.

53.2.14 PMCSR—Offset 54h

All fields are reset on full power-up. All of the fields except PME_En and PME_Status are reset on exit from D3cold state. If aux power is not supplied, the PME_En and PME_Status fields also reset on exit from D3cold state. Each device function has its own PMCSR register.

Note: See the detailed description for registers loaded from the EEPROM at initialization time. Behavior of some fields depend on the Power Management bit in EEPROM word 0x0A.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 54h

Default: 00000008h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**DATA:** No Data.
23:16	0x0 RSV	**RESERVED16:** Reserved.
15	0x0 RO	**PME_STATUS:**
14:9	0x0 RSV	**RESERVED:** Reserved.
8	0x0 RO	**PME_EN:** Hardwired to 0, indicate not support PME.
7:4	0x0 RSV	**RESERVED4:** Reserved.
3	0x1 RO	**NO_SOFT_RESET:** • When set (1) this bit indicates that when controller transitions from D3hot to D0 because of modifying Power State bits in the PMCSR register, no internal reset is issued and Configuration Context is preserved. Upon transition from the D3hot to the D0 Initialized state, no additional operating system intervention is required to preserve Configuration Context beyond writing the Power State bits. • When clear (0) controller performs an internal reset upon transitioning from D3hot to D0 via software control of the Power State bits in the PMCSR register. Configuration Context is lost when performing the soft reset. Upon transition from the D3hot to the D0 state, full re-initialization sequence is needed to return the device to D0 Initialized. Regardless of this bit, devices that transition from D3hot to D0 by a system or bus segment reset will return to the device state D0 Uninitialized with only PME context preserved if PME is supported and enabled.
2	0x0 RSV	**RESERVED2:** Reserved.
1:0	0x0 RW/V	**POWER_STATE:** This field is used to set and report the power state of a function as follows: • 00b = D0 • 01b = D1 (cycle ignored if written with this value) • 10b = D2 (cycle ignored if written with this value) • 11b = D3 hot

53.2.15 DSC—Offset 60h

Device Specific control and Status Register.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RSV	**RESERVED_3:** Reserved.
19	0x0 RW/1C	**URD:** Unsupported Request Detect: When set, this bit is set when unsupported request is detected.
18:16	0x0 RSV	**RESERVED_2:** Reserved.
15:4	0x0 RSV	**RESERVED_1:** Reserved.
3	0x0 RW	**URRE:** Unsupported Request Reporting Enable: When set, this bit enables the reporting of Non-fatal error.
2:0	0x0 RSV	**RESERVED_0:** Reserved.

53.2.16 FUNC_RDCFG_HIDE—Offset 74h

Function-Hide Register. Hiding is programmable per-function. Since hiding affects reads to FUNC_RDCFG_HIDE itself, this register is not shared in order to avoid read-modify-write errors.

Note: If function 0 is hidden, O/S will not discover function 1 and function 2.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:26, F:0] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RSV	**RESERVED_0:** Reserved.
0	0x0 RW	**HIDE:** HIDE: • 0 - HSUART Not Hidden • 1 - HSUART Hidden

53.3 Registers in Memory Space—MEMBA

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) MEMBA. There is a set of these registers for each of the three HSUART Functions (F0, F1, and F2).

53.3.1 RBR_THR_DLL—Offset 0h

RBR = Receive buffer register THR = Transmit hold register DLL = Divisor Latch low.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MEMBA] + 0h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**RBR_THR_DLL:** When DLAB =0, this 8 bit is used as Received Buffer Register as Read, and is used as Transmit Holding Register as Write. When DLAB is 1, this register is used as DLL (Divisor Latch Low Byte Register).

53.3.2 IER_DLH—Offset 1h

IER = Interrupt Enable Register DLH = Divisor Latch High.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MEMBA] + 1h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**IER_DLH:** When DLAB =0, this 8 bit is used as Interrupt Enable Register. When DLAB =1, this 8 bit is used as DLH (Divisor Latch High Byte Register).

53.3.3 IIR_FCR—Offset 2h

IIR = Interrupt Identification Register FCR = FIFO control register.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MEMBA] + 2h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**IIR_FCR:** When this 8 bit is read, it is serving as Interrupt Identification Registers. When this 8 bit is written, it is serving as FCR (FIFO control register.).

53.3.4 LCR—Offset 3h

Line Control Register.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MEMBA] + 3h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**LCR_DLAB:** Divisor Latch Register Access Bit: The divisor-latch access bit must be set high (logic 1) to access the divisor latches of the baud rate generator during a read or write operation. It must be set low (logic 0) to access the receiver buffer, the Transmit Holding register, or the Interrupt Enable register. This bit does not need to be set when using auto-baud. • 0: Access Transmit Holding register (THR), Receive Buffer register (RBR) and Interrupt Enable register. • 1: Access Divisor Latch registers (DLL and DLH).
6	0x0 RW	**LCR_SB:** Set Break: The set-break control bit transmits a Break condition to the receiving UART. When SB is set to logic 1, the serial output (TXD) is forced to the Spacing (logic 0) state and remains there until SB is set to logic 0. This bit acts only on the TXD pin and has no effect on the transmitter logic. • 0: No effect on TXD output. • 1: Forces TXD output to 0 (space). This feature enables the processor to alert a terminal in a computer communications system. If the following sequence is executed, no erroneous characters will be transmitted because of the break: Load 0x00 in the Transmit Holding register in response to a TDRQ Interrupt. After TDRQ goes high (indicating that 0x00 is being shifted out), set the break bit before the parity or stop bits reach the TXD pin. Wait for the transmitter to be idle (TEMT = 1), and clear the break bit when normal transmission has to be restored. During the Break, the transmitter can be used as a character timer to accurately establish the Break duration. In FIFO mode, wait for the transmitter to be idle (TEMT=1) to set and clear the break bit.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**LCR_STKYP:** Sticky Parity: This bit is the sticky-parity bit, which can be used in multiprocessor communications. • 0: No effect on parity bit. • 1: Forces parity bit to be opposite of EPS bit value. When PEN and STKYP are logic 1, the bit that is transmitted in the parity-bit location (the bit just before the stop bit) is the complement of the EPS bit. If EPS is 0, then the bit at the parity-bit location will be transmitted as a 1. In the receiver, if STKYP and PEN are 1, then the receiver compares the bit that is received in the parity-bit location with the complement of the EPS bit. If the values being compared are not equal, the receiver sets the parity-error bit in LSR, and causes an Error Interrupt if Line-Status Interrupts were enabled. For example, if EPS is 0, the receiver expects the bit received at the parity-bit location to be 1. If it is not, then the parity-error bit is set. By forcing the bit value at the parity-bit location, rather than calculating a parity value, a system with a master transmitter and multiple receivers can identify some transmitted characters as receiver addresses and the rest of the characters as data. If PEN = 0, STKYP is ignored.
4	0x0 RW	**LCR_EPS:** Even Parity Select: EPS is only valid when the parity is enabled (PEN = 1). • 0: Sends and checks for odd parity. • 1: Sends and checks for even parity.
3	0x0 RW	**LCR_PEN:** Parity Enable (PEN): When PEN is logic 1, a parity bit is generated (transmit data) or checked (receive data) between the last data-word bit and stop bit of the serial data. • 0: No parity function. • 1: Allows parity generation and checking.
2	0x0 RW	**LCR_STB:** Stop Bits: This bit specifies the number of stop bits transmitted and received in each serial character. • 0: 1 stop bit. • 1: 2 stop bits; except for 5-bit character, then 1 bits The receiver checks the first stop bit only, regardless of the number of stop bits selected.
1:0	0x0 RW	**LCR_WLS:** Word Length Select: The word length select bits specify the number of data bits (five to eight bits are allowed) in each transmitted or received serial character. • 00: 5-bit character (default). • 01: 6-bit character 10: 7-bit character 11: 8-bit character.

53.3.5 MCR—Offset 4h

Modem Control Register.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [MEMBA] + 4h

Default: 00h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RSV	**MCR_RESERVED:** Reserved.
5	0x0 RW	**MCR_AFE:** MCR-Auto Flow Enable: This is a reserved bit in 16550 spec. • 0: Auto-RTS and Auto-CTS are disabled. • 1: Auto-CTS is enabled. If MCR[RTS] is also set, both Auto-CTS and Auto-RTS is enabled. Auto-RTS is not enabled if AFE is not set regardless of the state of MCR[RTS]. Autoflow automates the flow of data between the UART and the remote device.
4	0x0 RW	**MCR_LOOP:** Modem Control Register-Loop back test mode. This bit provides a local loopback feature for diagnostic testing of the UART. This feature allows the processor to verify the UART transmit and receive data paths. The Transmit, Receive, and Modem Control interrupts are operational in this mode. • 0: Normal UART operation. • 1: Loopback Test mode operation Serial output uart_txd pin is set to logic 1. Serial input uart_rxd pin is disconnected from external input line. The output of the Transmitter Shift register is looped back into the Receiver Shift register. The modem-control inputs (uart_cts, uart_dsr, uart_dcd, and uart_ri) are activated by MCR bits 0-3 instead of the modem-control inputs. A Break signal can also be transferred from the transmitter section to the receiver section in Loopback mode. When LOOP is set to logic 1, the following will occur: The TXD (transmitter output) pin is set to a logic-1 state. The RXD (receiver input) pin is disconnected. The output of the Transmitter Shift register is looped back into the Receiver-Shift register input. The four modem-control inputs (uart_cts, uart_dsr, uart_dcd, and uart_ri) are disconnected from the pins and the modem-control output pins (uart_rts and uart_dtr) are forced to their inactive state. The lower four bits of the Modem Control register (MCR) are connected to the upper four modem status register (MSR) bits. Flow control can be tested; if autoflow is enabled, the MCR[RTS] bit has no effect on the nCTS input as nRTS is asserted by the autoflow logic. • DTR = 1 forces DSR to a 1 • RTS = 1 forces CTS to a 1 • OUT1 = 1 forces RI to a 1 • OUT2= 1 forces DCD to a 1 Coming out of the Loopback Test mode may result in unpredictable activation of the delta bits (bits 3:0) in the Modem Status register (MSR). It is recommended that MSR is read once to clear the delta bits in the MSR.
3	0x0 RW	**MCR_OUT2:** Output2: The function of the auxiliary output OUT2 bit differs depending on the mode of the UART. • 0: uart_dcd UART pin input set low when in Loop-back mode. • 1: uart_dcd UART pin input set high when in Loop-back mode.
2	0x0 RW	**MCR_OUT1:** Modem Control Register-output1: The auxiliary output OUT1 bit is only used in Loopback Test mode. • 0: uart_ri UART pin input set low when in Loop-back mode. • 1: uart_ri UART pin input set high when in Loop-back mode.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW	**MCR_RTS:** When Auto Flow is disabled: MCR[AFE] = 0: • 0: Primary output uart_rts pin is forced to logic 1. • 1: Primary output uart_rts pin is forced to logic 0. When Auto Flow is enabled: MCR[AFE] = 1: • 0: Auto-RTS is disabled. • 1: Auto-RTS is enabled.
0	0x0 RW	**MCR_DTR:** Modem Control Register-Data Terminal Ready. This bit controls the Data Terminal Ready output. • 0: Primary output uart_dtr pin is forced to logic 1. • 1: Primary output uart_dtr pin is forced to logic 0. The uart_dtr output of the UART may be applied to an EIA inverting line driver (such as the DS1488) to obtain the proper polarity input at the succeeding modem or data set.

53.3.6 LSR—Offset 5h

Line Status Register.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 60h

BAR and Offset: [MEMBA] + 5h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**LSR_FIFOE:** Line Status Register - FIFO Error Status: • 0: No character has error inside the Receive FIFO. • 1: At least one character in Receiver FIFO has errors. In non-FIFO mode, this bit is always set to 0. In FIFO mode, FIFOE is set to 1 when there is at least one parity error, framing error, or break indication for any of the characters in the FIFO. A processor read to the Line Status register does not reset this bit. FIFOE is reset when all error bytes have been read from the FIFO. If DMA requests are enabled and FIFOE is set to 1, the Error Interrupt is generated and no Receive DMA request is generated even if the Receive FIFO reaches the trigger level. If DMA requests are not enabled setting FIFOE to 1 does not generate an interrupt.
6	0x1 RO/V	**LSR_TEMT:** Line Status Register - Transmitter Empty: • 0: There is data in the Transmit Shift register, the Transmit Holding register, or the FIFO (in FIFO mode). • 1: All the data in the transmitter has been shifted out.
5	0x1 RO/V	**LSR_TDRQ:** Line Status Register - Transmit data Request: • 0: The UART is NOT ready to receive data for transmission. • 1: The UART is ready to receive data for transmission. The assertion of TDRQ causes the UART to interrupt the processor when the Transmit Data Request Interrupt Enable IER[TIE] is set high, and generates a DMA request to the DMA controller if DMA Request is enabled. TDRQ is set to 1 when the new symbol is copied from Transmit Holding register into the Transmit Shift register. The bit is reset to logic 0 concurrently with the loading of the Transmit Holding register by the processor. In FIFO mode, TDRQ is set to logic 1 when the FIFO is less than half full. It is cleared when the FIFO is more than half full. If more than 64 characters are loaded into the FIFO, the excess characters are lost.
4	0x0 RO/C/V	**LSR_BI:** Line Status Register - Break Interrupt: • 0: No break signal has been received. • 1: Break signal has been received. BI is set to logic 1 when the received data input is held in the Spacing (logic 0) state for longer than a full character transmission time (that is, the total time of start bit + data bits + parity bit + stop bits). The Break Indicator is reset when the processor reads the Line Status register. In FIFO mode, only one Break character (equal to 0x00) is loaded into the FIFO regardless of the length of the Break condition. BI shows the Break condition for the character at the bottom of the FIFO, not the most recent character received.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RO/C/V	**LSR_FE:** Line Status Register - frame error: • 0: No Framing error. • 1: Framing error has occurred. FE indicates that the received character did not have a valid stop bit. FE is set to logic 1 when the bit following the last data bit or parity bit is detected as logic 0 bit (spacing level). If the Line Control register had been set for two stop bits, the receiver does not check for a valid second stop bit. The FE indicator is reset when the processor reads the Line Status register. The UART will resynchronize after a framing error by assuming that the framing error was due to the next start bit. Therefore it samples this start bit twice and then takes in the data. In FIFO mode, FE shows a framing error for the character at the bottom of the FIFO, not for the most recent character received.
2	0x0 RO/C/V	**LSR_PE:** Line Status Register - Parity Enable: • 0: No Parity error. • 1: Parity error has occurred. PE indicates that the received character does not have the correct even or odd parity, as selected by the Even Parity Select bit. The PE is set to logic 1 upon detection of a parity error and is reset to logic 0 when the processor reads the Line Status register. In FIFO mode, PE shows a parity error for the character at the bottom of the FIFO, not the most recent character received.
1	0x0 RO/C/V	**LSR_OE:** Line Status Register - Overflow Error: • 0: No overflow error. Data has not been lost. • 1: Overflow error. Receive data has been lost. In non-FIFO mode, OE indicates that data in the Receiver Buffer register was not read by the processor before the next character was received; the new character is lost. In FIFO mode, OE indicates that all 64 bytes of the FIFO are full and the most recently received byte has been discarded. The OE indicator is set to logic 1 upon detection of an overflow condition and reset when the processor reads the Line Status register.
0	0x0 RO/V	**LSR_DR:** Line Status Register - Data Ready: • 0: No data has been received. • 1: Data is available in RBR or the FIFO. DR is set to logic 1 when a complete incoming character has been received and transferred into the Receiver Buffer register or the FIFO. In non-FIFO mode, DR is reset to 0 when the receive buffer is read. In FIFO mode, DR is reset to logic 0 if the FIFO is empty (last character has been read from RBR) or the RESETRF bit is set in FCR.

53.3.7 MSR—Offset 6h

Modem Status Register.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MEMBA] + 6h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**MSR_DCD:** Modem Status Register - data Carrier Detect: Loopback is disabled, MCR[LOOP] = 0. • 0: Primary input uart_dcd is logic 1. • 1: Primary input uart_dcd is logic 0. Loopback is enabled, MCR[LOOP] = 1. • 0: MCR[OUT2] is logic 0. • 1: MCR[OUT2] is logic 1.
6	0x0 RO/V	**MSR_RI:** Modem Status Register - Ring Indicator: Loopback is disabled, MCR[LOOP] = 0. • 0: Primary input uart_ri is logic 1. • 1: Primary input uart_ri is logic 0. Loopback is enabled, MCR[LOOP] = 1. • 0: MCR[OUT1] is logic 0. • 1: MCR[OUT1] is logic 1.
5	0x0 RO/V	**MSR_DSR:** Modem Status Register - Data Set Ready: Loopback is disabled, MCR[LOOP] = 0. • 0: Primary input uart_dsr is logic 1. • 1: Primary input uart_dsr is logic 0. Loopback is enabled, MCR[LOOP] = 1. • 0: MCR[DTR] is logic 0. • 1: MCR[DTR] is logic 1.
4	0x0 RO/V	**MSR_CTS:** Modem Status Register - Clear to Send: Loopback is disabled, MCR[LOOP] = 0. • 0: Primary input uart_cts is logic 1. • 1: Primary input uart_cts is logic 0. Loopback is enabled, MCR[LOOP] = 1. • 0: MCR[RTS] is logic 0. • 1: MCR[RTS] is logic 1.
3	0x0 RO/C/V	**MSR_DDCR:** Modem Status Register - Delta Data Carrier Ready: • 0: No change in uart_dcr pin since last read of MSR. • 1: uart_dcr pin has changed state. When DDCR is set the modem status interrupt will be generated if enabled in IER.
2	0x0 RO/C/V	**MSR_TERI:** Modem Status Register - Trailing Edge Ring Indicator: • 0: uart_ri pin has not changed from 0 to 1 since last read of MSR. • 1: uart_ri pin has changed from 0 to 1. When TERI is set the modem status interrupt will be generated if enabled in IER.
1	0x0 RO/C/V	**MSR_DDSR:** Modem Status Register - Delta Data Set Ready: • 0: No change in uart_dsr pin since last read of MSR. • 1: uart_dsr pin has changed state. When DDSR is set the modem status interrupt will be generated if enabled in IER.

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RO/V	**MSR_DCTS:** Modem Status Register - Delta Clear to Send: • 0: No change in uart_cts pin since last read of MSR. • 1: uart_cts pin has change state. When DCTS is set the modem status interrupt will be generated if enabled in IER.

53.3.8 SPR—Offset 7h

Scratch Pad Status Register.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [MEMBA] + 7h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**SPR:** Scratch Pad Register (SCRATCH): Writing to this field does not affect the operation of the UART in any way.

53.3.9 UART_FISR—Offset 8h

UART Functional Interrupt Status Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + 8h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RSV	**RESERVED:** Reserved.
2	0x0 RO/V	**DWCIS:** DMA Write Channel Interrupt Status (DWCIS): Set when Functions DMA write channel interrupt line is asserted.
1	0x0 RO/V	**DRCIS:** DMA Read Channel Interrupt Status (DRCIS): Set when Functions DMA read channel interrupt line is asserted.
0	0x0 RO/V	**UIS:** UART Interrupt Status (UIS): Set when Functions UART interrupt line is asserted.

53.3.10 RFOR—Offset 20h

Receiver FIFO Occupancy Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + 20h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RSV	**RESERVED:** Reserved.
6:0	0x0 RO	**RFBC:** Receive FIFO Byte Count (RFBC): Number of bytes (0-64) present in the receive FIFO.

53.3.11 ABR—Offset 24h

Auto BAUD Control Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000010h

BAR and Offset: [MEMBA] + 24h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RSV	**RESERVED:** Reserved.
4	0x1 RW	**UUE:** UART Unit Enable (UUE): • 0: UART transceiver is disabled. • 1: UART transceiver is enabled. Transceiver is also disabled by hardware whenever the function is D3-hot PM state.
3	0x0 RW	**ABT:** Auto-baud Table (ABT): • 0: Formula used to calculate baud rates allowing all possible baud rates. • 1: Standard baud rates to be chosen by UART. When set to 1, UART will round the calculated baud rate to nearest standard baud rate.
2	0x0 RW	**ABUP:** Auto-Baud UART Program (ABUP): • 0: Processor Programs Divisor Latch registers. • 1: UART Programs Divisor Latch registers Setting ABUP allows the UART to automatically program the Divisor Latch registers (DLL and DLH) when the auto-baud circuit has detected the baud rate, regardless of the state of the Divisor-Latch Access bit (LCR[DLAB]). For this to occur, the Auto-Baud Enable (ABE) bit must be set. Clearing this bit allows the processor to read the Auto-Baud Count register (ACR) and determine the baud rate using its own algorithm rather than using the UARTs.
1	0x0 RW	**ABLIE:** Auto-Baud Lock Interrupt Enable (ABLIE): • 0: Auto Baud Lock Interrupt disabled (Source IIR[ABL]). • 1: Auto Baud Lock Interrupt enabled (Source IIR[ABL]). Setting ABLIE enables the IIR[ABL] Interrupt, which occurs when the auto-baud circuit has detected the baud rate and written the value into the Auto-Baud Count register (ACR). The Divisor Latch registers can then be programmed by the processor or auto-baud circuitry as dictated by the state of the ABUP.
0	0x0 RW	**ABE:** Auto-Baud Enable (ABE): • 0: Auto Baud disabled. • 1: Auto Baud enabled. Setting ABE enables the auto-baud circuitry within the UART. The circuitry counts the number of clocks in the start bit and writes this count into the Auto-Baud Count register (ACR). It will then interrupt the processor if the Auto Baud Lock Interrupt Enable (ABLIE) bit is set. It will also automatically program the Divisor Latch registers (DLL and DLH) if the Auto-Baud UART Program (ABUP) bit is set.

53.3.12 ACR—Offset 28h

Auto Baud Count Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + 28h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED:** Reserved.
15:0	0x0 RO/V	**ABC:** Auto-Baud Count (ABC): Auto-baud count is the number of FUART clock cycles within a start bit pulse.

53.3.13 PSR—Offset 30h

Pre-Scaler Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + 30h

Default: 00000010h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED:** Reserved.
15:0	0x10 RW	**PS:** Pre-Scalar (PS): # of samples per character bit.

53.3.14 UCMR—Offset 34h

UART CLOCK GEN Multiplier Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + 34h

Default: 000000D8h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RSV	**RESERVED:** Reserved.
23:0	0xd8 RW	**UCMUL:** UART Clock Gen Multiplier (UCMUL): UART Clock Gen Multiplier to derive the UART transceiver clock.

53.3.15 UCDR—Offset 38h

UART CLOCK GEN Divisor Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + 38h

Default: 00003D09h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RSV	**RESERVED:** Reserved.
23:0	0x3d09 RW	**UCDIV:** UART Clock Gen Divisor (UCDIV): UART Clock Gen Divisor to derive the UART transceiver clock.

53.3.16 CH0SR—Offset 80h

Channel Status Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000F0000h

BAR and Offset: [MEMBA] + 80h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO/V	**CDESC:** Current Descriptor (CDESC): • 00: Descriptor 0 • 01: Descriptor 1 • 10: Descriptor 2 • 11: Descriptor 3 The current descriptor will points to the descriptor to be served at any moment. While none of the descriptor is valid the current descriptor will point to the descriptor 0.
29:20	0x0 RSV	**RESERVED_2:** Reserved 2.
19:16	0xf RO/V	**DESCE:** Descriptor Empty (DESCE): One bit per descriptor, value of 1 indicates the descriptor transfer size is not 0.
15	0x0 RO/C/V	**CHE:** Channel Error (CHE): When set this bit indicates the following error condition. write channel: RX FIFO error status transitioned from 1 to 0. Once read this bit will only get set again when the RX FIFO Error status transition from 1 to 0. Error status is assumed 1 when FIFO contains erroneous data. read channel: The last read request is returned with malformed completion. In this case the UART TX FIFO will not be updated.
14:12	0x0 RSV	**RESERVED_1:** Reserved 1.
11:8	0x0 RO/C/V	**DESCTO:** Descriptor Time Out (DESCTO): One bit per descriptor, value of 1 indicates the descriptor has timed out. This only valid for write channel. In the event of descriptor timeout the available data in the buffer will be written to the memory and channel timeout interrupt will be asserted if enabled through descriptor control register. If the timeout condition will occur at the descriptor done boundary only descriptor done status is updated.
7:4	0x0 RSV	**RESERVED_0:** Reserved 0.
3:0	0x0 RO/C/V	**DESCD:** Descriptor Done (DESCD): One bit per descriptor, value of 1 indicates the descriptor request has been completed.

53.3.17 CH0CR—Offset 84h

Channel Control Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + 84h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RSV	**RESERVED_0:** Reserved 0.
1	0x0 WO	**CHD:** Channel Direction (CHD): • 0: Read Channel (UART TX). • 1: Write Channel (UART RX).
0	0x0 WO	**CHA:** Channel Active (CHA): • 0: Channel is disabled. • 1: Channel is enabled. Whenever channel stops the hardware will clear this bit. Channel can be stopped by HW on descriptor done, timeout or error condition.

53.3.18 CH0DCR—Offset 88h

Channel 0 Descriptor Control Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + 88h

Default: 00008000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RSV	**RESERVED_3:** Reserved 3.
27:24	0x0 RW	**CHTOI:** Channel Time Out Interrupt (CHTOI): One bit per descriptor, value of 1 indicates the channel should generate interrupt once timeout is detected. This is only applicable to write channel.
23	0x0 RW	**CHEI:** Channel Error Interrupt (CHEI): Value of 1 indicates the channel should generate interrupt if the channel error condition has occurred.
22:20	0x0 RSV	**RESERVED_2:** Reserved 2.
19:16	0x0 RW	**CHDI:** Channel Done Interrupt (CHDI): One bit per descriptor, value of 1 indicates the channel should generate interrupt once descriptor is done.
15	0x1 RW	**CHSOE:** Channel Stop on Error (CHSOTO): Value of 1 indicates the channel should stop on error condition while any serving descriptor.
14	0x0 RW	**CHSOTO:** Channel Stop on Timeout (CHSOTO): Value of 1 indicates the channel should stop on timeout condition while any serving descriptor.
13:12	0x0 RSV	**RESERVED_1:** Reserved 1.
11:8	0x0 RW	**CHSOD:** Channel Stop on Done (CHSOD): One bit per descriptor, value of 1 indicates the channel should stop once the descriptor request has been completed.
7:4	0x0 RSV	**RESERVED_0:** Reserved 0.
3:0	0x0 RW/V	**DESCA:** Descriptor Active (DESCA): One bit per descriptor, value of 1 indicates the descriptor is active. Whenever the descriptor is done or timed out the corresponding descriptor active bit will be cleared.

53.3.19 CH0BSR—Offset 90h

Channel Buffer Size.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + 90h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW	**CHBS:** Channel Buffer Size (CHBS): Indicates the size of UART FIFO connected to the channel.

53.3.20 CH0MTSR—Offset 94h

Channel Minimum Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + 94h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW	**CHMTSR:** Channel Minimum Transfer Size (CHMTSR): Indicates the minimum number of bytes required to make the DMA request.

53.3.21 CH0D0SAR—Offset A0h

Channel Descriptor 0 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + A0h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD0SAR:** Channel Descriptor 0 Start Address (CHD0SAR):

53.3.22 CH0D0TSR—Offset A4h

Channel Descriptor 0 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + A4h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD0TS:** Channel Descriptor 0 Transfer Size (CHD0TS):

53.3.23 CH0D1SAR—Offset A8h

Channel Descriptor 1 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + A8h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD1SAR:** Channel Descriptor 1 Start Address (CHD1SAR):

53.3.24 CH0D1TSR—Offset ACh

Channel Descriptor 1 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + ACh

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD1TS:** Channel Descriptor 1 Transfer Size (CHD1TS):

53.3.25 CH0D2SAR—Offset B0h

Channel Descriptor 2 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + B0h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD2SAR:** Channel Descriptor 2 Start Address (CHD2SAR):

53.3.26 CH0D2TSR—Offset B4h

Channel Descriptor 2 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + B4h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD2TS:** Channel Descriptor 2 Transfer Size (CHD2TS):

53.3.27 CH0D3SAR—Offset B8h

Channel Descriptor 3 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + B8h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD3SAR:** Channel Descriptor 3 Start Address (CHD3SAR):

53.3.28 CH0D3TSR—Offset BCh

Channel Descriptor 3 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + BCh

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD3TS:** Channel Descriptor 3 Transfer Size (CHD3TS):

53.3.29 CH1SR—Offset C0h

Channel Status Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000F0000h

BAR and Offset: [MEMBA] + C0h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO/V	**CDESC:** Current Descriptor (CDESC): • 00: Descriptor 0 • 01: Descriptor 1 • 10: Descriptor 2 • 11: Descriptor 3 The current descriptor will points to the descriptor to be served at any moment. While none of the descriptor is valid the current descriptor will point to the descriptor 0.
29:20	0x0 RSV	**RESERVED_2:** Reserved 2.
19:16	0xf RO/V	**DESCE:** Descriptor Empty (DESCE): One bit per descriptor, value of 1 indicates the descriptor transfer size is not 0.
15	0x0 RO/C/V	**CHE:** Channel Error (CHE): When set this bit indicates the following error condition. write channel: RX FIFO error status transitioned from 1 to 0. Once read this bit will only get set again when the RX FIFO Error status transition from 1 to 0. Error status is assumed 1 when FIFO contains erroneous data. read channel: The last read request is returned with malformed completion. In this case the UART TX FIFO will not be updated.
14:12	0x0 RSV	**RESERVED_1:** Reserved 1.
11:8	0x0 RO/C/V	**DESCTO:** Descriptor Time Out (DESCTO): One bit per descriptor, value of 1 indicates the descriptor has timed out. This only valid for write channel. In the event of descriptor timeout the available data in the buffer will be written to the memory and channel timeout interrupt will be asserted if enabled through descriptor control register. If the timeout condition will occur at the descriptor done boundary only descriptor done status is updated.
7:4	0x0 RSV	**RESERVED_0:** Reserved 0.
3:0	0x0 RO/C/V	**DESCD:** Descriptor Done (DESCD): One bit per descriptor, value of 1 indicates the descriptor request has been completed.

53.3.30 CH1CR—Offset C4h

Channel Control Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + C4h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RSV	**RESERVED_0:** Reserved 0.
1	0x0 WO	**CHD:** Channel Direction (CHD): • 0: Read Channel (UART TX). • 1: Write Channel (UART RX).
0	0x0 WO	**CHA:** Channel Active (CHA): • 0: Channel is disabled. • 1: Channel is enabled. Whenever channel stops the hardware will clear this bit. Channel can be stopped by HW on descriptor done, timeout or error condition.

53.3.31 CH1DCR—Offset C8h

Channel 0 Descriptor Control Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00008000h

BAR and Offset: [MEMBA] + C8h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RSV	**RESERVED_3:** Reserved 3.
27:24	0x0 RW	**CHTOI:** Channel Time Out Interrupt (CHTOI): One bit per descriptor, value of 1 indicates the channel should generate interrupt once timeout is detected. This is only applicable to write channel.
23	0x0 RW	**CHEI:** Channel Error Interrupt (CHEI): Value of 1 indicates the channel should generate interrupt if the channel error condition has occurred.
22:20	0x0 RSV	**RESERVED_2:** Reserved 2.
19:16	0x0 RW	**CHDI:** Channel Done Interrupt (CHDI): One bit per descriptor, value of 1 indicates the channel should generate interrupt once descriptor is done.
15	0x1 RW	**CHSOE:** Channel Stop on Error (CHSOTO): Value of 1 indicates the channel should stop on error condition while any serving descriptor.
14	0x0 RW	**CHSOTO:** Channel Stop on Timeout (CHSOTO): Value of 1 indicates the channel should stop on timeout condition while any serving descriptor.
13:12	0x0 RSV	**RESERVED_1:** Reserved 1.
11:8	0x0 RW	**CHSOD:** Channel Stop on Done (CHSOD): One bit per descriptor, value of 1 indicates the channel should stop once the descriptor request has been completed.
7:4	0x0 RSV	**RESERVED_0:** Reserved 0.
3:0	0x0 RW/V	**DESCA:** Descriptor Active (DESCA): One bit per descriptor, value of 1 indicates the descriptor is active. Whenever the descriptor is done or timed out the corresponding descriptor active bit will be cleared.

53.3.32 CH1BSR—Offset D0h

Channel Buffer Size.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + D0h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW	**CHBS:** Channel Buffer Size (CHBS): Indicates the size of UART FIFO connected to the channel.

53.3.33 CH1MTSR—Offset D4h

Channel Minimum Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + D4h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW	**CHMTSR:** Channel Minimum Transfer Size (CHMTSR): Indicates the minimum number of bytes required to make the DMA request.

53.3.34 CH1D0SAR—Offset E0h

Channel Descriptor 0 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + E0h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD0SAR:** Channel Descriptor 0 Start Address (CHD0SAR):

53.3.35 CH1D0TSR—Offset E4h

Channel Descriptor 0 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + E4h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD0TS:** Channel Descriptor 0 Transfer Size (CHD0TS):

53.3.36 CH1D1SAR—Offset E8h

Channel Descriptor 1 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + E8h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD1SAR:** Channel Descriptor 1 Start Address (CHD1SAR):

53.3.37 CH1D1TSR—Offset ECh

Channel Descriptor 1 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + ECh

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD1TS:** Channel Descriptor 1 Transfer Size (CHD1TS):

53.3.38 CH1D2SAR—Offset F0h

Channel Descriptor 2 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + F0h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD2SAR:** Channel Descriptor 2 Start Address (CHD2SAR):

53.3.39 CH1D2TSR—Offset F4h

Channel Descriptor 2 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [MEMBA] + F4h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD2TS:** Channel Descriptor 2 Transfer Size (CHD2TS):

53.3.40 CH1D3SAR—Offset F8h

Channel Descriptor 3 Start Address Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + F8h

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**CHD3SAR:** Channel Descriptor 3 Start Address (CHD3SAR):

53.3.41 CH1D3TSR—Offset FCh

Channel Descriptor 3 Transfer Size Register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [MEMBA] + FCh

Default: 00000000h

MEMBA Type: PCI Configuration Register (Size: 32 bits)
MEMBA Reference: [B:0, D:26, F:0,1,2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RSV	**RESERVED_0:** Reserved 0.
15:0	0x0 RW/V	**CHD3TS:** Channel Descriptor 3 Transfer Size (CHD3TS):

53.4 Registers in I/O Space—IOBA

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IOBA described in Section 53.2.5, "IOBA—Offset 10h" on page 2391. There is a set of these registers for each of the three HSUART Functions (F0, F1, and F2).

53.4.1 RBR_THR_DLL—Offset 0h

RBR = Receive buffer register THR = Transmit hold register DLL = Divisor Latch low.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IOBA] + 0h

Default: 00h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**RBR_THR_DLL:** When DLAB =0, this 8 bit is used as Received Buffer Register as Read, and is used as Transmit Holding Register as Write. When DLAB is 1, this register is used as DLL (Divisor Latch Low Byte Register).

53.4.2 IER_DLH—Offset 1h

IER = Interrupt Enable Register DLH = Divisor Latch High.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IOBA] + 1h

Default: 00h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**IER_DLH:** When DLAB =0, this 8 bit is used as Interrupt Enable Register. When DLAB =1, this 8 bit is used as DLH (Divisor Latch High Byte Register).

53.4.3 IIR_FCR—Offset 2h

IIR = Interrupt Identification Register FCR = FIFO control register.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IOBA] + 2h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**IIR_FCR:** When this 8 bit is read, it is serving as Interrupt Identification Registers. When this 8 bit is written, it is serving as FCR (FIFO control register.).

53.4.4 LCR—Offset 3h

Line Control Register.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IOBA] + 3h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**LCR_DLAB:** Divisor Latch Register Access Bit (DLAB): The divisor-latch access bit must be set high (logic 1) to access the divisor latches of the baud rate generator during a read or write operation. It must be set low (logic 0) to access the receiver buffer, the Transmit Holding register, or the Interrupt Enable register. This bit does not need to be set when using auto-baud. • 0: Access Transmit Holding register (THR), Receive Buffer register (RBR) and Interrupt Enable register. • 1: Access Divisor Latch registers (DLL and DLH)
6	0x0 RW	**LCR_SB:** Set Break (SB): The set-break control bit transmits a Break condition to the receiving UART. When SB is set to logic 1, the serial output (TXD) is forced to the Spacing (logic 0) state and remains there until SB is set to logic 0. This bit acts only on the TXD pin and has no effect on the transmitter logic. • 0: No effect on TXD output. • 1: Forces TXD output to 0 (space). This feature enables the processor to alert a terminal in a computer communications system. If the following sequence is executed, no erroneous characters will be transmitted because of the break: Load 0x00 in the Transmit Holding register in response to a TDRQ Interrupt. After TDRQ goes high (indicating that 0x00 is being shifted out), set the break bit before the parity or stop bits reach the TXD pin. Wait for the transmitter to be idle (TEMT = 1), and clear the break bit when normal transmission has to be restored. During the Break, the transmitter can be used as a character timer to accurately establish the Break duration. In FIFO mode, wait for the transmitter to be idle (TEMT=1) to set and clear the break bit.
5	0x0 RW	**LCR_STKYP:** Sticky Parity (STKYP): This bit is the sticky-parity bit, which can be used in multiprocessor communications. • 0: No effect on parity bit. • 1: Forces parity bit to be opposite of EPS bit value. When PEN and STKYP are logic 1, the bit that is transmitted in the parity-bit location (the bit just before the stop bit) is the complement of the EPS bit. If EPS is 0, then the bit at the parity-bit location will be transmitted as a 1. In the receiver, if STKYP and PEN are 1, then the receiver compares the bit that is received in the parity-bit location with the complement of the EPS bit. If the values being compared are not equal, the receiver sets the parity-error bit in LSR, and causes an Error Interrupt if Line-Status Interrupts were enabled. For example, if EPS is 0, the receiver expects the bit received at the parity-bit location to be 1. If it is not, then the parity-error bit is set. By forcing the bit value at the parity-bit location, rather than calculating a parity value, a system with a master transmitter and multiple receivers can identify some transmitted characters as receiver addresses and the rest of the characters as data. If PEN = 0, STKYP is ignored.
4	0x0 RW	**LCR_EPS:** Even Parity Select (EPS): EPS is only valid when the parity is enabled (PEN = 1). • 0: Sends and checks for odd parity. • 1: Sends and checks for even parity.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW	**LCR_PEN:** Parity Enable (PEN): When PEN is logic 1, a parity bit is generated (transmit data) or checked (receive data) between the last data-word bit and stop bit of the serial data. • 0: No parity function. • 1: Allows parity generation and checking.
2	0x0 RW	**LCR_STB:** Stop Bits (STB): This bit specifies the number of stop bits transmitted and received in each serial character. • 0: 1 stop bit • 1: 2 stop bits; except for 5-bit character, then 1 bits The receiver checks the first stop bit only, regardless of the number of stop bits selected.
1:0	0x0 RW	**LCR_WLS:** Word Length Select (WLS): The word length select bits specify the number of data bits (five to eight bits are allowed) in each transmitted or received serial character. • 00: 5-bit character (default) • 01: 6-bit character • 10: 7-bit character • 11: 8-bit character

53.4.5 MCR—Offset 4h

Modem Control Register.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IOBA] + 4h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RSV	**MCR_RESERVED:** Reserved.
5	0x0 RW	**MCR_AFE:** MCR-Auto Flow Enable (AFE): This is a reserved bit in 16550 spec. • 0: Auto-RTS and Auto-CTS are disabled. • 1: Auto-CTS is enabled. If MCR[RTS] is also set, both Auto-CTS and Auto-RTS is enabled. Auto-RTS is not enabled if AFE is not set regardless of the state of MCR[RTS]. Autoflow automates the flow of data between the UART and the remote device.
4	0x0 RW	**MCR_LOOP:** Modem Control Register-Loop back test mode (LOOP): This bit provides a local loopback feature for diagnostic testing of the UART. This feature allows the processor to verify the UART transmit and receive data paths. The Transmit, Receive, and Modem Control interrupts are operational in this mode. • 0: Normal UART operation. • 1: Loopback Test mode operation. Serial output uart_txd pin is set to logic 1. Serial input uart_rxd pin is disconnected from external input line. The output of the Transmitter Shift register is looped back into the Receiver Shift register. The modem-control inputs (uart_cts, uart_dsr, uart_dcd, and uart_ri) are activated by MCR bits 0-3 instead of the modem-control inputs. A Break signal can also be transferred from the transmitter section to the receiver section in Loopback mode. When LOOP is set to logic 1, the following will occur: The TXD (transmitter output) pin is set to a logic-1 state. The RXD (receiver input) pin is disconnected. The output of the Transmitter Shift register is looped back into the Receiver-Shift register input. The four modem-control inputs (uart_cts, uart_dsr, uart_dcd, and uart_ri) are disconnected from the pins and the modem-control output pins (uart_rts and uart_dtr) are forced to their inactive state. The lower four bits of the Modem Control register (MCR) are connected to the upper four modem status register (MSR) bits. Flow control can be tested; if autoflow is enabled, the MCR[RTS] bit has no effect on the nCTS input as nRTS is asserted by the autoflow logic. • DTR = 1 forces DSR to a 1 • RTS = 1 forces CTS to a 1 • OUT1 = 1 forces RI to a 1 • OUT2= 1 forces DCD to a 1 Coming out of the Loopback Test mode may result in unpredictable activation of the delta bits (bits 3:0) in the Modem Status register (MSR). It is recommended that MSR is read once to clear the delta bits in the MSR.
3	0x0 RW	**MCR_OUT2:** Output2 (OUT2): The function of the auxiliary output OUT2 bit differs depending on the mode of the UART. • 0: uart_dcd UART pin input set low when in Loop-back mode • 1: uart_dcd UART pin input set high when in Loop-back mode.
2	0x0 RW	**MCR_OUT1:** Modem Control Register-output1 (OUT1): The auxiliary output OUT1 bit is only used in Loopback Test mode. • 0: uart_ri UART pin input set low when in Loop-back mode • 1: uart_ri UART pin input set high when in Loop-back mode

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW	**MCR_RTS:** When Auto Flow is disabled MCR[AFE] = 0: • 0: Primary output uart_rts pin is forced to logic 1. • 1: Primary output uart_rts pin is forced to logic 0. When Auto Flow is enabled: MCR[AFE] = 1: • 0: Auto-RTS is disabled. • 1: Auto-RTS is enabled.
0	0x0 RW	**MCR_DTR:** Modem Control Register-Data Terminal Ready (DTR): This bit controls the Data Terminal Ready output. • 0: Primary output uart_dtr pin is forced to logic 1. • 1: Primary output uart_dtr pin is forced to logic 0. The uart_dtr output of the UART may be applied to an EIA inverting line driver (such as the DS1488) to obtain the proper polarity input at the succeeding modem or data set.

53.4.6 LSR—Offset 5h

Line Status Register.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IOBA] + 5h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**LSR_FIFOE:** Line Status Register - FIFO Error Status (FIFOE): • 0: No character has error inside the Receive FIFO. • 1: At least one character in Receiver FIFO has errors. In non-FIFO mode, this bit is always set to 0. In FIFO mode, FIFOE is set to 1 when there is at least one parity error, framing error, or break indication for any of the characters in the FIFO. A processor read to the Line Status register does not reset this bit. FIFOE is reset when all error bytes have been read from the FIFO. If DMA requests are enabled and FIFOE is set to 1, the Error Interrupt is generated and no Receive DMA request is generated even if the Receive FIFO reaches the trigger level. If DMA requests are not enabled setting FIFOE to 1 does not generate an interrupt.
6	0x0 RO/V	**LSR_TEMT:** Line Status Register - Transmitter Empty (TEMT): • 0: There is data in the Transmit Shift register, the Transmit Holding register, or the FIFO (in FIFO mode). • 1: All the data in the transmitter has been shifted out.
5	0x0 RO/V	**LSR_TDRQ:** Line Status Register - Transmit data Request (TDRQ) • 0: The UART is NOT ready to receive data for transmission. • 1: The UART is ready to receive data for transmission. The assertion of TDRQ causes the UART to interrupt the processor when the Transmit Data Request Interrupt Enable IER[TIE] is set high, and generates a DMA request to the DMA controller if DMA Request is enabled. TDRQ is set to 1 when the new symbol is copied from Transmit Holding register into the Transmit Shift register. The bit is reset to logic 0 concurrently with the loading of the Transmit Holding register by the processor. In FIFO mode, TDRQ is set to logic 1 when the FIFO is less than half full. It is cleared when the FIFO is more than half full. If more than 64 characters are loaded into the FIFO, the excess characters are lost.
4	0x0 RO/C/V	**LSR_BI:** Line Status Register - Break Interrupt (BI): • 0: No break signal has been received. • 1: Break signal has been received. BI is set to logic 1 when the received data input is held in the Spacing (logic 0) state for longer than a full character transmission time (that is, the total time of start bit + data bits + parity bit + stop bits). The Break Indicator is reset when the processor reads the Line Status register. In FIFO mode, only one Break character (equal to 0x00) is loaded into the FIFO regardless of the length of the Break condition. BI shows the Break condition for the character at the bottom of the FIFO, not the most recent character received.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RO/C/V	**LSR_FE:** Line Status Register - frame error (FE): • 0: No Framing error. • 1: Framing error has occurred. FE indicates that the received character did not have a valid stop bit. FE is set to logic 1 when the bit following the last data bit or parity bit is detected as logic 0 bit (spacing level). If the Line Control register had been set for two stop bits, the receiver does not check for a valid second stop bit. The FE indicator is reset when the processor reads the Line Status register. The UART will resynchronize after a framing error by assuming that the framing error was due to the next start bit. Therefore it samples this start bit twice and then takes in the data. In FIFO mode, FE shows a framing error for the character at the bottom of the FIFO, not for the most recent character received.
2	0x0 RO/C/V	**LSR_PE:** Line Status Register - Parity Enable (PE): • 0: No Parity error. • 1: Parity error has occurred. PE indicates that the received character does not have the correct even or odd parity, as selected by the Even Parity Select bit. The PE is set to logic 1 upon detection of a parity error and is reset to logic 0 when the processor reads the Line Status register. In FIFO mode, PE shows a parity error for the character at the bottom of the FIFO, not the most recent character received.
1	0x0 RO/C/V	**LSR_OE:** Line Status Register - Overflow Error (OE): • 0: No overflow error. Data has not been lost. • 1: Overflow error. Receive data has been lost. In non-FIFO mode, OE indicates that data in the Receiver Buffer register was not read by the processor before the next character was received; the new character is lost. In FIFO mode, OE indicates that all 64 bytes of the FIFO are full and the most recently received byte has been discarded. The OE indicator is set to logic 1 upon detection of an overflow condition and reset when the processor reads the Line Status register.
0	0x0 RO/V	**LSR_DR:** Line Status Register - Data Ready (DR): • 0: No data has been received. • 1: Data is available in RBR or the FIFO. DR is set to logic 1 when a complete incoming character has been received and transferred into the Receiver Buffer register or the FIFO. In non-FIFO mode, DR is reset to 0 when the receive buffer is read. In FIFO mode, DR is reset to logic 0 if the FIFO is empty (last character has been read from RBR) or the RESETRF bit is set in FCR.

53.4.7 MSR—Offset 6h

Modem Status Register

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IOBA] + 6h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**MSR_DCD:** Modem Status Register - data Carrier Detect (DCD): Loopback is disabled, MCR[LOOP] = 0 • 0: Primary input uart_dcd is logic 1. • 1: Primary input uart_dcd is logic 0. Loopback is enabled, MCR[LOOP] = 1 • 0: MCR[OUT2] is logic 0. • 1: MCR[OUT2] is logic 1.
6	0x0 RO/V	**MSR_RI:** Modem Status Register - Ring Indicator (RI): Loopback is disabled, MCR[LOOP] = 0 • 0: Primary input uart_ri is logic 1. • 1: Primary input uart_ri is logic 0. Loopback is enabled, MCR[LOOP] = 1 • 0: MCR[OUT1] is logic 0. • 1: MCR[OUT1] is logic 1.
5	0x0 RO/V	**MSR_DSR:** Modem Status Register - Data Set Ready (DSR): Loopback is disabled, MCR[LOOP] = 0 • 0: Primary input uart_dsr is logic 1. • 1: Primary input uart_dsr is logic 0. Loopback is enabled, MCR[LOOP] = 1 • 0: MCR[DTR] is logic 0. • 1: MCR[DTR] is logic 1.
4	0x0 RO/V	**MSR_CTS:** Modem Status Register - Clear to Send (CTS): Loopback is disabled, MCR[LOOP] = 0 • 0: Primary input uart_cts is logic 1. • 1: Primary input uart_cts is logic 0. Loopback is enabled, MCR[LOOP] = 1 • 0: MCR[RTS] is logic 0. • 1: MCR[RTS] is logic 1.
3	0x0 RO/C/V	**MSR_DDCR:** Modem Status Register - Delta Data Carrier Ready (DDCR): • 0: No change in uart_dcr pin since last read of MSR • 1: uart_dcr pin has changed state. When DDCR is set the modem status interrupt will be generated if enabled in IER.
2	0x0 RO/C/V	**MSR_TERI:** Modem Status Register - Trailing Edge Ring Indicator (TERI): • 0: uart_ri pin has not changed from 0 to 1 since last read of MSR. • 1: uart_ri pin has changed from 0 to 1. When TERI is set the modem status interrupt will be generated if enabled in IER.
1	0x0 RO/C/V	**MSR_DDSR:** Modem Status Register - Delta Data Set Ready (DDSR): • 0: No change in uart_dsr pin since last read of MSR. • 1: uart_dsr pin has changed state. When DDSR is set the modem status interrupt will be generated if enabled in IER.

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RO/V	**MSR_DCTS:** Modem Status Register - Delta Clear to Send (DCTS): • 0: No change in uart_cts pin since last read of MSR. • 1: uart_cts pin has change state. When DCTS is set the modem status interrupt will be generated if enabled in IER.

53.4.8 SPR—Offset 7h

Scratch Pad Status Register.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IOBA] + 7h

IOBA Type: PCI Configuration Register (Size: 32 bits)
IOBA Reference: [B:0, D:26, F:0,1,2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**SPR:** Scratch Pad Register (SCRATCH): Writing to this field does not affect the operation of the UART in any way.

§ §

54 Innovation Engine - B0, D27, F(0, 1, 3, 4)

54.1 Introduction and Index

The host-accessible registers for the Innovation Engine are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

54.1.1 Host Configuration Space—HECI1 (F:0)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 27 (decimal), Function 0. The offset addresses are listed.

Table 54-1. Summary of PCI Configuration Registers HECI1—0/27/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19E58086	"Identifiers (HECI1_ID)—Offset 0h" on page 2454
4	2	0000	"Command (HECI1_CMD)—Offset 4h" on page 2455
6	2	0010	"Status (HECI1_STS)—Offset 6h" on page 2456
8	4	07800000	"Revision ID and Class Code (HECI1_RID_CC)—Offset 8h" on page 2457
C	1	00	"Cache Line Size (HECI1_CLS)—Offset Ch" on page 2457
D	1	00	"Master Latency Timer (HECI1_MLT)—Offset Dh" on page 2457
E	1	80	"Header Type (HECI1_HTYPE)—Offset Eh" on page 2458
F	1	00	"Built In Self-Test (HECI1_BIST)—Offset Fh" on page 2458
10	4	00000004	"HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h" on page 2458
14	4	00000000	"HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h" on page 2459
2C	4	00000000	"Sub System Identifiers (HECI1_SS)—Offset 2Ch" on page 2459
34	1	50	"Capabilities Pointer (HECI1_CAP)—Offset 34h" on page 2459
3C	2	0100	"Interrupt Information (HECI1_INTR)—Offset 3Ch" on page 2460
3E	1	00	"Minimum Grant (HECI1_MGNT)—Offset 3Eh" on page 2460
3F	1	00	"Maximum Latency (HECI1_MLAT)—Offset 3Fh" on page 2460
40	4	00000000	"Host Firmware Status (HECI1_HFS)—Offset 40h" on page 2461
44	4	80000000	"Miscellaneous Shadow (HECI1_MISC_SHDW)—Offset 44h" on page 2463
48	4	00000000	"General Status Shadow 1 (HECI1_GS_SHDW1)—Offset 48h" on page 2464
4C	4	00000000	"Host General Status (HECI1_H_GS1)—Offset 4Ch" on page 2465
50	2	8C01	"PCI Power Management Capability ID (HECI1_PID)—Offset 50h" on page 2465
52	2	4003	"PCI Power Management Capabilities (HECI1_PC)—Offset 52h" on page 2465
54	2	0008	"PCI Power Management Control and Status (HECI1_PMCS)—Offset 54h" on page 2466
60	4	00000000	"General Status Shadow 2 (HECI1_GS_SHDW2)—Offset 60h" on page 2466
64	4	00000000	"General Status Shadow 3 (HECI1_GS_SHDW3)—Offset 64h" on page 2467
68	4	00000000	"General Status Shadow 4 (HECI1_GS_SHDW4)—Offset 68h" on page 2467
6C	4	00000000	"General Status Shadow 5 (HECI1_GS_SHDW5)—Offset 6Ch" on page 2467
70	4	00000000	"Host General Status 2 (HECI1_H_GS2)—Offset 70h" on page 2467
74	4	00000000	"Host General Status 3 (HECI1_H_GS3)—Offset 74h" on page 2468
8C	2	0005	"Message Signaled Interrupt Identifiers (HECI1_MID)—Offset 8Ch" on page 2468
8E	2	0080	"Message Signaled Interrupt Message Control (HECI1_MC)—Offset 8Eh" on page 2468
90	4	00000000	"Message Signaled Interrupt Message Address (HECI1_MA)—Offset 90h" on page 2469
94	4	00000000	"Message Signaled Interrupt Upper Address (HECI1_MUA)—Offset 94h" on page 2469
98	2	0000	"Message Signaled Interrupt Message Data (HECI1_MD)—Offset 98h" on page 2469
A0	1	00	"HECI Interrupt Delivery Mode (HECI1_HIDM)—Offset A0h" on page 2470
BC	4	40000000	"Host Extend Register Status (HECI1_HERS)—Offset BCh" on page 2470
C0	4	00000000	"Host Extend Register DW1. (HECI1_HER1)—Offset C0h" on page 2471

Table 54-1. Summary of PCI Configuration Registers HECI1—0/27/0 (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
C4	4	00000000	"Host Extend Register DW2. (HECI1_HER2)—Offset C4h" on page 2471
C8	4	00000000	"Host Extend Register DW3. (HECI1_HER3)—Offset C8h" on page 2471
CC	4	00000000	"Host Extend Register DW4. (HECI1_HER4)—Offset CCh" on page 2471
D0	4	00000000	"Host Extend Register DW5. (HECI1_HER5)—Offset D0h" on page 2472
D4	4	00000000	"Host Extend Register DW6. (HECI1_HER6)—Offset D4h" on page 2472
D8	4	00000000	"Host Extend Register DW7. (HECI1_HER7)—Offset D8h" on page 2472
DC	4	00000000	"Host Extend Register DW8. (HECI1_HER8)—Offset DCh" on page 2472
F8	4	00000000	"Manufacturer's ID (HECI1_MANID)—Offset F8h" on page 2473

54.1.2 Host Configuration Space—HECI2 (F:1)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 27 (decimal), Function 1. The offset addresses are listed.

Table 54-2. Summary of PCI Configuration Registers HECI2—0/27/1

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19E68086	"Identifiers (HECI2_ID)—Offset 0h" on page 2474
4	2	0000	"Command (HECI2_CMD)—Offset 4h" on page 2475
6	2	0010	"Status (HECI2_STS)—Offset 6h" on page 2476
8	4	07800000	"Revision ID and Class Code (HECI2_RID_CC)—Offset 8h" on page 2477
C	1	00	"Cache Line Size (HECI2_CLS)—Offset Ch" on page 2477
D	1	00	"Master Latency Timer (HECI2_MLT)—Offset Dh" on page 2477
E	1	80	"Header Type (HECI2_HTYPE)—Offset Eh" on page 2478
F	1	00	"Built In Self-Test (HECI2_BIST)—Offset Fh" on page 2478
10	4	00000004	"HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h" on page 2478
14	4	00000000	"HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h" on page 2479
2C	4	00000000	"Sub System Identifiers (HECI2_SS)—Offset 2Ch" on page 2479
34	1	50	"Capabilities Pointer (HECI2_CAP)—Offset 34h" on page 2479
3C	2	0100	"Interrupt Information (HECI2_INTR)—Offset 3Ch" on page 2480
3E	1	00	"Minimum Grant (HECI2_MGNT)—Offset 3Eh" on page 2480
3F	1	00	"Maximum Latency (HECI2_MLAT)—Offset 3Fh" on page 2480
40	4	00000000	"Host Firmware Status (HECI2_HFS)—Offset 40h" on page 2481
48	4	00000000	"General Status Shadow 1 (HECI2_GS_SHDW1)—Offset 48h" on page 2483
4C	4	00000000	"Host General Status (HECI2_H_GS1)—Offset 4Ch" on page 2484
50	2	8C01	"PCI Power Management Capability ID (HECI2_PID)—Offset 50h" on page 2484
52	2	4003	"PCI Power Management Capabilities (HECI2_PC)—Offset 52h" on page 2485
54	2	0008	"PCI Power Management Control and Status (HECI2_PMCS)—Offset 54h" on page 2486
60	4	00000000	"General Status Shadow 2 (HECI2_GS_SHDW2)—Offset 60h" on page 2486
64	4	00000000	"General Status Shadow 3 (HECI2_GS_SHDW3)—Offset 64h" on page 2487
68	4	00000000	"General Status Shadow 4 (HECI2_GS_SHDW4)—Offset 68h" on page 2487
6C	4	00000000	"General Status Shadow 5 (HECI2_GS_SHDW5)—Offset 6Ch" on page 2487
70	4	00000000	"Host General Status 2 (HECI2_H_GS2)—Offset 70h" on page 2487
74	4	00000000	"Host General Status 3 (HECI2_H_GS3)—Offset 74h" on page 2488
8C	2	0005	"Message Signaled Interrupt Identifiers (HECI2_MID)—Offset 8Ch" on page 2488
8E	2	0080	"Message Signaled Interrupt Message Control (HECI2_MC)—Offset 8Eh" on page 2488
90	4	00000000	"Message Signaled Interrupt Message Address (HECI2_MA)—Offset 90h" on page 2489
94	4	00000000	"Message Signaled Interrupt Upper Address (HECI2_MUA)—Offset 94h" on page 2489
98	2	0000	"Message Signaled Interrupt Message Data (HECI2_MD)—Offset 98h" on page 2489
A0	1	00	"HECI Interrupt Delivery Mode (HECI2_HIDM)—Offset A0h" on page 2490
F8	4	00000000	"Manufacturer's ID (HECI2_MANID)—Offset F8h" on page 2490

54.1.3 Host Configuration Space—HECI3 (F:4)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 27 (decimal), Function 4. The offset addresses are listed.

Table 54-3. Summary of PCI Configuration Registers HECI3—0/27/4

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19E98086	"Identifiers (HECI3_ID)—Offset 0h" on page 2491
4	2	0000	"Command (HECI3_CMD)—Offset 4h" on page 2492
6	2	0010	"Status (HECI3_STS)—Offset 6h" on page 2493
8	4	07800000	"Revision ID and Class Code (HECI3_RID_CC)—Offset 8h" on page 2494
C	1	00	"Cache Line Size (HECI3_CLS)—Offset Ch" on page 2494
D	1	00	"Master Latency Timer (HECI3_MLT)—Offset Dh" on page 2494
E	1	80	"Header Type (HECI3_HTYPE)—Offset Eh" on page 2495
F	1	00	"Built In Self-Test (HECI3_BIST)—Offset Fh" on page 2495
10	4	00000004	"HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h" on page 2495
14	4	00000000	"HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h" on page 2496
2C	4	00000000	"Sub System Identifiers (HECI3_SS)—Offset 2Ch" on page 2496
34	1	50	"Capabilities Pointer (HECI3_CAP)—Offset 34h" on page 2496
3C	2	0100	"Interrupt Information (HECI3_INTR)—Offset 3Ch" on page 2497
3E	1	00	"Minimum Grant (HECI3_MGNT)—Offset 3Eh" on page 2497
3F	1	00	"Maximum Latency (HECI3_MLAT)—Offset 3Fh" on page 2497
40	4	00000000	"Host Firmware Status (HECI3_HFS)—Offset 40h" on page 2498
48	4	00000000	"General Status Shadow 1 (HECI3_GS_SHDW1)—Offset 48h" on page 2500
4C	4	00000000	"Host General Status (HECI3_H_GS1)—Offset 4Ch" on page 2501
50	2	8C01	"PCI Power Management Capability ID (HECI3_PID)—Offset 50h" on page 2501
52	2	4003	"PCI Power Management Capabilities (HECI3_PC)—Offset 52h" on page 2502
54	2	0008	"PCI Power Management Control and Status (HECI3_PMCS)—Offset 54h" on page 2503
60	4	00000000	"General Status Shadow 2 (HECI3_GS_SHDW2)—Offset 60h" on page 2503
64	4	00000000	"General Status Shadow 3 (HECI3_GS_SHDW3)—Offset 64h" on page 2504
68	4	00000000	"General Status Shadow 4 (HECI3_GS_SHDW4)—Offset 68h" on page 2504
6C	4	00000000	"General Status Shadow 5 (HECI3_GS_SHDW5)—Offset 6Ch" on page 2504
70	4	00000000	"Host General Status 2 (HECI3_H_GS2)—Offset 70h" on page 2504
74	4	00000000	"Host General Status 3 (HECI3_H_GS3)—Offset 74h" on page 2505
8C	2	0005	"Message Signaled Interrupt Identifiers (HECI3_MID)—Offset 8Ch" on page 2505
8E	2	0080	"Message Signaled Interrupt Message Control (HECI3_MC)—Offset 8Eh" on page 2505
90	4	00000000	"Message Signaled Interrupt Message Address (HECI3_MA)—Offset 90h" on page 2506
94	4	00000000	"Message Signaled Interrupt Upper Address (HECI3_MUA)—Offset 94h" on page 2506
98	2	0000	"Message Signaled Interrupt Message Data (HECI3_MD)—Offset 98h" on page 2506
A0	1	00	"HECI Interrupt Delivery Mode (HECI3_HIDM)—Offset A0h" on page 2507
F8	4	00000000	"Manufacturer's ID (HECI3_MANID)—Offset F8h" on page 2507

54.1.4 Host Configuration Space—KT (F:3)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 27 (decimal), Function 3. The offset addresses are listed.

Table 54-4. Summary of PCI Configuration Registers KT (Host)—0/27/3

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19E88086	"Device ID and Vendor ID (KT_HOST_DID_VID)—Offset 0h" on page 2508
4	4	00B00000	"Status and Command (KT_HOST_STS_CMD)—Offset 4h" on page 2509
8	4	07000200	"Class Code and Revision ID (KT_HOST_CC_RID)—Offset 8h" on page 2511
C	4	00800000	"BIST, Header Type, Latency Timer, and Cache Line Size (KT_HOST_BIST_HTYPE_LT_CLS)—Offset Ch" on page 2512
10	4	00000001	"KT IO BAR (KT_HOST_IOBAR)—Offset 10h" on page 2512
14	4	00000000	"KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h" on page 2513
28	4	00000000	"Cardbus CIS Pointer (KT_HOST_CCP)—Offset 28h" on page 2513
2C	4	00008086	"Subsystem ID and Subsystem Vendor ID (KT_HOST_SID_SVID)—Offset 2Ch" on page 2514
30	4	00000000	"Expansion ROM Base Address (KT_HOST_XRBAR)—Offset 30h" on page 2514
34	4	00000040	"Capabilities List Pointer (KT_HOST_CAPP)—Offset 34h" on page 2514
3C	4	00000000	"Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (KT_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch" on page 2515
40	4	00805005	"MSI Message Control, Next Pointer and Capability ID (KT_HOST_MSIMC_MSINP_MSICID)—Offset 40h" on page 2516
44	4	00000000	"MSI Message Address (KT_HOST_MSIMA)—Offset 44h" on page 2516
48	4	00000000	"MSI Message Upper Address (KT_HOST_MSIMUA)—Offset 48h" on page 2517
4C	4	00000000	"MSI Message Data (KT_HOST_MSIMD)—Offset 4Ch" on page 2517
50	4	00230001	"Power Management Capabilities, Next Pointer and Capability ID (KT_HOST_PMCAP_PMNP_PMCID)—Offset 50h" on page 2518
54	4	00000008	"Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (KT_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h" on page 2519
F8	4	00000000	"Process Stepping Information (KT_HOST_PSI)—Offset F8h" on page 2520

54.1.5 Host Configuration Space—IDE (F:2)

These registers are discovered in Host Configuration Space starting at Bus 0, Device 27 (decimal), Function 2. The offset addresses are listed.

Table 54-5. Summary of PCI Configuration Registers—0/27/2

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19E78086	"Device ID and Vendor ID (IDE_HOST_DID_VID)—Offset 0h" on page 2521
4	4	00B00000	"Status and Command (IDE_HOST_STS_CMD)—Offset 4h" on page 2522
8	4	01018500	"Class Code and Revision ID (IDE_HOST_CC_RID)—Offset 8h" on page 2524
C	4	00800000	"BIST, Header Type, Latency Timer, and Cache Line Size (IDE_HOST_BIST_HTYPE_LT_CLS)—Offset Ch" on page 2525
10	4	00000001	"IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h" on page 2525
14	4	00000001	"IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h" on page 2526
18	4	00000001	"IDE Secondary Command Block IO BAR (IDE_HOST_SCMDIOBAR)—Offset 18h" on page 2526
1C	4	00000001	"IDE Secondary Control Block IO BAR (IDE_HOST_SCTLIOBAR)—Offset 1Ch" on page 2526
20	4	00000001	"IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h" on page 2527
28	4	00000000	"Cardbus CIS Pointer (IDE_HOST_CCP)—Offset 28h" on page 2527
2C	4	00008086	"Subsystem ID and Subsystem Vendor ID (IDE_HOST_SID_SVID)—Offset 2Ch" on page 2527
30	4	00000000	"Expansion ROM Base Address (IDE_HOST_XRBAR)—Offset 30h" on page 2528
34	4	00000040	"Capabilities List Pointer (IDE_HOST_CAPP)—Offset 34h" on page 2528
3C	4	00000000	"Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (IDE_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch" on page 2529
40	4	00805005	"MSI Message Control, Next Pointer and Capability ID (IDE_HOST_MSIMC_MSINP_MSICID)—Offset 40h" on page 2530
44	4	00000000	"MSI Message Address (IDE_HOST_MSIMA)—Offset 44h" on page 2530
48	4	00000000	"MSI Message Upper Address (IDE_HOST_MSIMUA)—Offset 48h" on page 2531
4C	4	00000000	"MSI Message Data (IDE_HOST_MSIMD)—Offset 4Ch" on page 2531
50	4	00230001	"Power Management Capabilities, Next Pointer and Capability ID (IDE_HOST_PMCAP_PMNP_PMCID)—Offset 50h" on page 2532
54	4	00000008	"Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (IDE_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h" on page 2533
F8	4	00000000	"Process Stepping Information (IDE_HOST_PSI)—Offset F8h" on page 2534

54.1.6 Host Memory Space—HECI1_MMIO_MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 54-6. Summary of Memory Mapped I/O Registers—HECI1_MMIO_MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Host CB Write Window (HECI1_H_CB_WW)—Offset 0h" on page 2535
4	4	80000000	"Host Control and Status Register (HECI1_H_CSR)—Offset 4h" on page 2536
8	4	FFFFFFFF	"CSE Circular Buffer Read Window (HECI1_CSE_CB_RW)—Offset 8h" on page 2537
C	4	80000000	"CSE Control and Status Register Host Access (HECI1_CSE_CSR_HA)—Offset Ch" on page 2537
800	4	00000000	"D0i3 Control (HECI1_D0I3C)—Offset 800h" on page 2538

54.1.7 Host Memory Space—HECI2_MMIO_MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 54-7. Summary of Memory Mapped I/O Registers—HECI2_MMIO_MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Host CB Write Window (HECI2_H_CB_WW)—Offset 0h" on page 2539
4	4	80000000	"Host Control and Status Register (HECI2_H_CSR)—Offset 4h" on page 2540
8	4	FFFFFFFF	"CSE Circular Buffer Read Window (HECI2_CSE_CB_RW)—Offset 8h" on page 2541
C	4	80000000	"CSE Control and Status Register Host Access (HECI2_CSE_CSR_HA)—Offset Ch" on page 2541
800	4	00000000	"D0i3 Control (HECI2_D0I3C)—Offset 800h" on page 2542

54.1.8 Host Memory Space—HECI3_MMIO_MBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 54-8. Summary of Memory Mapped I/O Registers—HECI3_MMIO_MBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Host CB Write Window (HECI3_H_CB_WW)—Offset 0h" on page 2543
4	4	80000000	"Host Control and Status Register (HECI3_H_CSR)—Offset 4h" on page 2544
8	4	FFFFFFFF	"CSE Circular Buffer Read Window (HECI3_CSE_CB_RW)—Offset 8h" on page 2545
C	4	80000000	"CSE Control and Status Register Host Access (HECI3_CSE_CSR_HA)—Offset Ch" on page 2545
800	4	00000000	"D0i3 Control (HECI3_D0I3C)—Offset 800h" on page 2546

54.1.9 Host Memory Space—KT_HOST_MEMBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 54-9. Summary of Memory Mapped I/O Registers—KT_HOST_MEMBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"KT Receive Buffer Register (MEM_KTRBR)—Offset 0h" on page 2547
0	1	00	"KT Transmitter Holding Register (MEM_KTTHR)—Offset 0h" on page 2547
0	1	00	"KT Divisor Latch LSB Register (MEM_KTDLLR)—Offset 0h" on page 2547
1	1	00	"KT Interrupt Enable register (MEM_KTIER)—Offset 1h" on page 2548
1	1	00	"KT Divisor Latch MSB Register (MEM_KTDLMR)—Offset 1h" on page 2548
2	1	01	"KT Interrupt Identification Register (MEM_KTIIR)—Offset 2h" on page 2549
2	1	00	"KT FIFO Control register (MEM_KTFCR)—Offset 2h" on page 2550
3	1	03	"KT Line Control register (MEM_KTLCR)—Offset 3h" on page 2551
4	1	00	"KT Modem Control register (MEM_KTMCR)—Offset 4h" on page 2552
5	1	60	"KT Line Status register (MEM_KTLSR)—Offset 5h" on page 2553
6	1	00	"KT Modem Status register (MEM_KTMSR)—Offset 6h" on page 2554
7	1	00	"KT Scratch register (MEM_KTSCR)—Offset 7h" on page 2554

54.1.10 Host Memory Space—Fixed Address

An index of the registers that are accessible in Host Memory Space is shown here.

Table 54-10. Summary of Memory Mapped I/O Registers—Fix Addresses

Memory Address (hex)	Bytes (decimal)	Default Value (hex)	Register Name (Register Symbol)
FED40000	4	00000000	"FTPM Locality State (HOST_LOC_0_LOC_STATE_HROA)—Offset FED40000h" on page 2555
FED40004	4	00000000	"FTPM Locality Reserved (HOST_LOC_0_LOC_RSVD)—Offset FED40004h" on page 2555
FED40008	4	00000000	"FTPM Locality n Control Register (HOST_LOC_0_LOC_CTRL)—Offset FED40008h" on page 2556
FED4000C	4	00000000	"FTPM Locality n Status Register Host Read Only Access. (HOST_LOC_0_LOC_STS_HROA)—Offset FED4000Ch" on page 2556
FED40010	4	00000000	"FTPM Locality Config Area Reserved Read Write[0-7] (HOST_LOC_0_RSVD_RW1[0-7])—Offset FED40010h, Count 8, Stride 4h" on page 2556
FED40030	4	00000000	"FTPM Interface ID Host Read Only Access 0 (HOST_LOC_0_INTF_ID_0)—Offset FED40030h" on page 2557
FED40034	4	00000000	"FTPM Interface ID Host Read Only Access 1 (HOST_LOC_0_INTF_ID_1)—Offset FED40034h" on page 2557
FED40038	4	00000000	"FTPM Locality Config Area Reserved Read Write[0-1] (HOST_LOC_0_RSVD_RW2[0-1])—Offset FED40038h, Count 2, Stride 4h" on page 2557
FED40040	4	00000000	"Control Area Request (HOST_LOC_0_CA_REQUEST)—Offset FED40040h" on page 2558
FED40044	4	00000000	"Control Area Status (HOST_LOC_0_CA_STATUS)—Offset FED40044h" on page 2558
FED40048	4	00000000	"Control Area Cancel (HOST_LOC_0_CA_CANCEL)—Offset FED40048h" on page 2558
FED4004C	4	00000000	"Control Area Start (HOST_LOC_0_CA_START)—Offset FED4004Ch" on page 2559
FED40050	4	00000000	"Control Area Interrupt Reserved Part 1 (HOST_LOC_0_CA_INT_RSVD1)—Offset FED40050h" on page 2559
FED40054	4	00000000	"Control Area Interrupt Reserved Part 2 (HOST_LOC_0_CA_INT_RSVD2)—Offset FED40054h" on page 2559
FED40058	4	00000000	"Control Area Command Size (HOST_LOC_0_CA_CMD_SZ)—Offset FED40058h" on page 2560
FED4005C	4	00000000	"Control Area Command Part 1 (HOST_LOC_0_CA_CMD1)—Offset FED4005Ch" on page 2560
FED40060	4	00000000	"Control Area Command Part 2 (HOST_LOC_0_CA_CMD2)—Offset FED40060h" on page 2560
FED40064	4	00000000	"Control Area Response Size (HOST_LOC_0_CA_RSP_SZ)—Offset FED40064h" on page 2560
FED40068	4	00000000	"Control Area Response Part 1 (HOST_LOC_0_CA_RSP1)—Offset FED40068h" on page 2561
FED4006C	4	00000000	"Control Area Response Part 2 (HOST_LOC_0_CA_RSP2)—Offset FED4006Ch" on page 2561
FED40070	4 x 4	00000000	"FTPM Reserved Read Write[0-3] (HOST_LOC_0_RSVD_RW3[0-3])—Offset FED40070h, Count 4, Stride 4h" on page 2561
FED40080	4 x 992	00000000	"FTPM Command and Response Buffer[0-991] (HOST_LOC_0_FTPM_CRB[0-991])—Offset FED40080h, Count 992, Stride 4h" on page 2561

54.1.11 Host I/O Space—KT_HOST_IOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 54-11. Summary of I/O Registers—KT_HOST_IOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"KT Receive Buffer Register (IO_KTRBR)—Offset 0h" on page 2562
0	1	00	"KT Transmitter Holding Register (IO_KTTHR)—Offset 0h" on page 2562
0	1	00	"KT Divisor Latch LSB Register (IO_KTDLLR)—Offset 0h" on page 2563
1	1	00	"KT Interrupt Enable register (IO_KTIER)—Offset 1h" on page 2563
1	1	00	"KT Divisor Latch MSB Register (IO_KTDLMR)—Offset 1h" on page 2564
2	1	01	"KT Interrupt Identification Register (IO_KTIIR)—Offset 2h" on page 2564
2	1	00	"KT FIFO Control register (IO_KTFCR)—Offset 2h" on page 2565
3	1	03	"KT Line Control register (IO_KTLCR)—Offset 3h" on page 2566
4	1	00	"KT Modem Control register (IO_KTMCR)—Offset 4h" on page 2567
5	1	60	"KT Line Status register (IO_KTLSR)—Offset 5h" on page 2568
6	1	00	"KT Modem Status register (IO_KTMSR)—Offset 6h" on page 2569
7	1	00	"KT Scratch register (IO_KTSCR)—Offset 7h" on page 2569

54.1.12 Host I/O Space—IDE_HOST_PCMDIOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 54-12. Summary of I/O Registers—IDE_HOST_PCMDIOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	0000	"IDE Data Register (IDEDATA)—Offset 0h" on page 2570
1	1	00	"IDE Features Register (IDEFR)—Offset 1h" on page 2570
1	1	00	"IDE Error Register DEV0 (IDEERD0)—Offset 1h" on page 2571
1	1	00	"IDE Error Register DEV1 (IDEERD1)—Offset 1h" on page 2571
2	1	00	"IDE Sector Count In Register (IDESCIR)—Offset 2h" on page 2572
2	1	00	"IDE Sector Count Out Register DEV0 (IDESCOR0)—Offset 2h" on page 2572
2	1	00	"IDE Sector Count Out Register DEV1 (IDESCOR1)—Offset 2h" on page 2572
3	1	00	"IDE Sector Number In Register (IDESNIR)—Offset 3h" on page 2573
3	1	00	"IDE Sector Number Out Register DEV0 (IDESNOR0)—Offset 3h" on page 2573
3	1	00	"IDE Sector Number Out Register DEV1 (IDESNOR1)—Offset 3h" on page 2573
4	1	00	"IDE Cylinder Low In Register (IDECLIR)—Offset 4h" on page 2574
4	1	00	"IDE Cylinder Low Out Register DEV0 (IDCLOR0)—Offset 4h" on page 2574
4	1	00	"IDE Cylinder Low Out Register DEV1 (IDCLOR1)—Offset 4h" on page 2575
5	1	00	"IDE Cylinder High In Register (IDECHIR)—Offset 5h" on page 2575
5	1	00	"IDE Cylinder High Out Register DEV0 (IDCHOR0)—Offset 5h" on page 2576
5	1	00	"IDE Cylinder High Out Register DEV1 (IDCHOR1)—Offset 5h" on page 2576
6	1	00	"IDE Drive/Head In Register (IDEDHIR)—Offset 6h" on page 2577
6	1	00	"IDE Drive/Head Out Register DEV0 (IDDHOR0)—Offset 6h" on page 2577
6	1	00	"IDE Drive/Head Out Register DEV1 (IDDHOR1)—Offset 6h" on page 2578
7	1	00	"IDE Command Register (IDECR)—Offset 7h" on page 2578
7	1	80	"IDE Status Register DEV0 (IDESR0)—Offset 7h" on page 2579
7	1	80	"IDE Status Register DEV1 (IDESR1)—Offset 7h" on page 2580

54.1.13 Host I/O Space—IDE_HOST_PCTLIOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 54-13. Summary of I/O Registers—IDE_HOST_PCTLIOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
2	1	00	"IDE Device Control Register (IDDCR)—Offset 2h" on page 2581
2	1	00	"IDE Alternate Status Register (IDASR)—Offset 2h" on page 2581

54.1.14 Host I/O Space—IDE_HOST_BMIOBAR

An index of the registers that are accessible in Host I/O Space is shown here.

Table 54-14. Summary of I/O Registers—IDE_HOST_BMIOBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"IDE Primary Bus Master Command Register (IDEPBMCR)—Offset 0h" on page 2582
1	1	00	"IDE Primary Bus Master Device Specific 0 Register (IDEPBMDS0R)—Offset 1h" on page 2583
2	1	80	"IDE Primary Bus Master Status Register (IDEPBMSR)—Offset 2h" on page 2584
3	1	00	"IDE Primary Bus Master Device Specific 1 Register (IDEPBMDS1R)—Offset 3h" on page 2586
4	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 0 (IDEPBMDTPR0)—Offset 4h" on page 2586
5	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 1 (IDEPBMDTPR1)—Offset 5h" on page 2586
6	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 2 (IDEPBMDTPR2)—Offset 6h" on page 2587
7	1	00	"IDE Primary Bus Master Descriptor Table Pointer Register Byte 3 (IDEPBMDTPR3)—Offset 7h" on page 2587
8	1	00	"IDE Secondary Bus Master Command Register (IDESBMCR)—Offset 8h" on page 2588
9	1	00	"IDE Secondary Bus Master Device Specific 0 Register (IDESBMDS0R)—Offset 9h" on page 2588
A	1	80	"IDE Secondary Bus Master Status Register (IDESBMSR)—Offset Ah" on page 2589
B	1	00	"IDE Secondary Bus Master Device Specific 1 Register (IDESBMDS1R)—Offset Bh" on page 2590
C	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0 (IDESBMDTPR0)—Offset Ch" on page 2590
D	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1 (IDESBMDTPR1)—Offset Dh" on page 2591
E	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2 (IDESBMDTPR2)—Offset Eh" on page 2591
F	1	00	"IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3 (IDESBMDTPR3)—Offset Fh" on page 2592

54.1.15 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 54-15. Summary of Sideband Registers for KT (Host)—0xf4

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
0	00000000	"KT Host Interrupt Pin Register (KTHIPINR)—Offset 0h" on page 2593
4	00000000	"BIOS KT Host PCI Function Disable Register (BKTHDISR)—Offset 4h" on page 2593

Table 54-16. Summary of Sideband Registers IDE (Host)—0xf4

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
0	00000000	"IDE Host Interrupt Pin Register (IDEHIPINR)—Offset 0h" on page 2594
4	00000000	"BIOS IDE Host PCI Function Disable Register (BIDEHDISR)—Offset 4h" on page 2594

54.2 Registers in Configuration Space—HECI1

54.2.1 Identifiers (HECI1_ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 0h

Default: 19E58086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19E5 RO/V	**Device ID (DID):** Indicates what device number assigned by Intel.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates that Intel is the vendor, assigned by the PCI SIG.

54.2.2 Command (HECI1_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:0] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD:** Reserved
10	0x0 RW	**Interrupt Disable (ID):** Disables this device from generating PCI line based interrupts. This bit does not have any effect on MSI operations.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not implemented, hardwired to 0.
8	0x0 RO	**SERR# Enable (SEE):** Not implemented, hardwired to 0.
7	0x0 RO	**Wait Cycle Enable (WCC):** Not implemented, hardwired to 0.
6	0x0 RO	**Parity Error Response Enable (PEE):** Not implemented, hardwired to 0.
5	0x0 RO	**VGA Palette Snooping Enable (VAG):** Not implemented, hardwired to 0
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not implemented, hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not implemented, hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the HECI host controller's ability to act as a system memory master for data transfers. When this bit is cleared, HECI bus master activity stops and any active DMA engines return to an idle condition. This bit is made visible to firmware through the H_PCI_CSR register, and changes to this bit may be configured by the H_PCI_CSR register to generate an MSI to mIA. When this bit is '0', HECI is blocked from generating MSI to the host CPU. ***Note:*** This bit does not block HECI accesses to CSE-UMA.
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the HECI host controller’s memory-mapped register space.
0	0x0 RO	**I/O Space Enable (IOSE):** Not implemented, hardwired to 0.

54.2.3 Status (HECI1_STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:0] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Detected Parity Error (DPE):** Not implemented, hardwired to 0.
14	0x0 RO	**Signaled System Error (SSE):** Not implemented, hardwired to 0.
13	0x0 RO	**Received Master-Abort (RMA):** Not implemented, hardwired to 0.
12	0x0 RO	**Received Target Abort (RTA):** Not implemented, hardwired to 0.
11	0x0 RO	**Signaled Target-Abort (STA):** Not implemented, hardwired to 0.
10:9	0x0 RO	**DEVSEL# Timing (DEVT):** These bits are hardwired to 00.
8	0x0 RO	**Master Data Pariy Error Detected (DPD):** Not implemented, hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not implemented, hardwired to 0.
6	0x0 RO	**RSVD (RSVD_6_6):** Reserved
5	0x0 RO	**66 MHz Capable (C66):** Not implemented, hardwired to 0.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list, hardwired to 1.
3	0x0 RO/V	**Interrupt Status (IS):** Reflects the state of the INTx# signal at the input of the enable/disable circuit. • This bit is a 1 when the INTx# is asserted. • This bit is a 0 after the interrupt is cleared (independent of the state of the Interrupt Disable bit in the command register). ***Note:*** This bit is not set by an MSI.
2:0	0x0 RO	**RSVD (RSVD_2_0):** Reserved

54.2.4 Revision ID and Class Code (HECI1_RID_CC)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 8h

Default: 07800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Indicates the base class code of the HECI host controller device.
23:16	0x80 RO	**Sub Class Code (SCC):** Indicates the sub class code of the HECI host controller device.
15:8	0x0 RO	**Programming Interface (PI):** Indicates the programming interface of the HECI host controller device.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates stepping of the HECI host controller.

54.2.5 Cache Line Size (HECI1_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:0] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented, hardwired to 0.

54.2.6 Master Latency Timer (HECI1_MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:0] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Not implemented, hardwired to 0.

54.2.7 Header Type (HECI1_HTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:0] + Eh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Multi-Function Device (MFD):** Indicates the HECI host controller is part of a multi-function device.
6:0	0x0 RO	**Header Layout (HL):** Indicates that the HECI host controller uses a target device layout.

54.2.8 Built In Self-Test (HECI1_BIST)—Offset Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:0] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**BIST Capable (BC):** Not implemented, hardwired to 0.
6:0	0x0 RO	**RSVD:** Reserved

54.2.9 HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Base Address Low (BA_LO):** Lower 32 bits of base address of register memory space.
11:4	0x0 RO	**Memory Size (MS):** This field is hardwired to 0 to indicate that HECI device requests 4KB of memory space.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not pre-fetchable
2:1	0x2 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 64-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

54.2.10 HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address High (BA_HI):** Upper 32 bits of base address of register memory space.

54.2.11 Sub System Identifiers (HECI1_SS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Indicates the sub- system identifier. This field should be programmed by BIOS during boot-up. Once written, this register becomes Read Only.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Indicates the sub-system vendor identifier. This field should be programmed by BIOS during boot- up. Once written, this register becomes Read Only.

54.2.12 Capabilities Pointer (HECI1_CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:0] + 34h

Default: 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x50 RO	**Capability Pointer (CP):** Indicates the first capability pointer offset. It points to the PCI power management capability offset.

54.2.13 Interrupt Information (HECI1_INTR)—Offset 3Ch

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:27, F:0] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO/V	**Interrupt Pin (IPIN):** This field indicates the virtual interrupt pin the HECI host controller uses. A value of 0x1/0x2/0x3/0x4 indicates that this function implements legacy interrupt on INTA/INTB/INTC/INTD, respectively. When legacy interrupt is not used this register should be set to 0x0. Programmed by BIOS over IOSF SB through corresponding Private CR register.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this field.

54.2.14 Minimum Grant (HECI1_MGNT)—Offset 3Eh

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:27, F:0] + 3Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Grant (GNT):** Not implemented, hardwired to 0.

54.2.15 Maximum Latency (HECI1_MLAT)—Offset 3Fh

Type: PCI Configuration Register
(Size: 8 bits)

Offset: [B:0, D:27, F:0] + 3Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Latency (LAT):** Not implemented, hardwired to 0.

54.2.16 Host Firmware Status (HECI1_HFS)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**BIOS MSG ACK:** Acknowledge for register based BIOS message in MEI 1 H_GS Register.
27:25	0x0 RO	**BIOS MSG ACK Data:** Message specific data for acknowledged BIOS message.
24:20	0x0 RO	Reserved
19:16	0x0 RO	**Operating Mode:** This field describes the current operating mode of Intel® ME. • 1:0 - Reserved • 2 - Debug Mode • 14:3 - Reserved • 15 - Intel® SPS firmware is running in Intel® ME
15:12	0x0 RO	**Error Code:** If set to nonzero value the Intel® ME firmware has encountered a fatal error and stopped normal operation. • 0 - No Error • 1 - Uncategorized Failure - The Intel® ME firmware has experienced an uncategorized error. Further details of the failure can be found in the Extended Status Data. • 2 - Disabled - Firmware was disabled on this platform. • 3 - Image Failure - The Intel® ME firmware stored in the system flash is not valid.
11	0x0 RO	**Update in Progress:** The bit is set if any type of Intel® ME firmware update is in progress.
10	0x0 RO	**Recovery BUP Load Fault:** This bit is set when firmware is not able to load recovery bring-up from the flash. It means that the recovery section in Intel® ME region on the SPI flash.
9	0x0 RO	**Init Complete:** When this but is not set firmware is still in initialization phase. When firmware has fully entered a stable state, this but is set to 1 and "Current State" field of this register provides the steady state of the Intel® ME subsystem.
8:6	0x0 RO	**Operating State:** This field describes the current operating state of Intel® ME. • 000 - Preboot • 001 - M0 with UMA • 010 - Reserved • 011 - Reserved • 100 - M3 without UMA • 101 - M0 without UMA - normal state for Intel® SPS firmware • 110 - Bring up • 111 - M0 without UMA but with error
5	0x0 RO	**FPT or Factory Defaults Bad:** This bit is set when the firmware discovers a bad checksum of Intel® ME region Flash Partition Table (FPT) or Factory Defaults. When this bit set, it may or may not have the error code shown in bit [15:12]. The system can get this bit clear only by re-flashing the whole Intel® ME region in the SPI Flash.
4	0x0 RO	**Manufacturing Mode:** When this bit is set, the platform is still in manufacturing mode. Host can use this bit to inform user that the platform is NOT READY for production yet. This but is set as long as Intel® ME Region access is not locked for flash masters other than Intel® ME. For shipping machine, this bit MUST be 0.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**Current State:** This field describes the current operation state of the firmware. • 0 - Reset - Intel® ME is in reset state, will exit this state within 1 millisecond • 1 - Initialization - Intel® ME is initializing, will exit this state within 2 seconds • 2 - Recovery - Intel® ME is in recovery mode, check ME1.GMES register to determine cause • 3 - Reserved • 4 - Disabled - Intel® ME functionality has been disabled, it executes idle loop • 5 - Operational - Intel® ME is in normal operational state • 6 - Reserved • 7 - State Transition - Intel® ME sets this state before starting a transition to a new Operating State. It is a temporary state, may appear on transition between Initialization and Operational.

54.2.17 Miscellaneous Shadow (HECI1_MISC_SHDW)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 44h

Default: 80000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RO	**Miscellaneous Shadow Valid (MSVLD):** This bit is hardwired to 1 to indicate that this HECI device implements the Miscellaneous Shadow register. This bit can be used by host software that is bus/dev/function number agnostic (such as HECI operating system driver) to discover whether the Miscellaneous Shadow register is implemented or not.
30:17	0x0 RO	**RSVD_30_17:** Reserved
16	0x0 RO/V	**CSE UMA Size Valid (CUSZV):** This bit indicates that firmware has written the CUSZ field. This field reflects the value of CSE CUBA.CUSZV.
15:7	0x0 RO	**Reserved (RSVD_15_7):** Reserved.
6:0	0x0 RO/V	**CSE UMA Size (CUSZ):** These bits reflect firmware's desired size of CSEUMA memory region. It is configured by firmware prior to bring up core power and allowing BIOS to initialize memory. The legal CSEUMA sizes and encodings for this field are: • 0000000b (0MB, no CSEUMA region) • 0000001b (1MB) • 0000010b (2MB) • 0000100b (4MB) • 0001000b (8MB) • 0010000b (16MB) • 0100000b (32MB) • 1000000b (64MB) This field reflects the value of CSE CUBA.CUSZ.

54.2.18 General Status Shadow 1 (HECI1_GS_SHDW1)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**EOP Status:** This bit presents the Intel® ME notion of EOP status. If BIOS encounters this bit set to '1' during POST it signals an error in platform power flow.
30:28	0x0 RO	**Infrastructure Progress Code:** This field identifies the infrastructure progress code: • 0 - ROM - Intel® ME is in ROM phase • 1 - BUP - Intel® ME is in BRINGUP phase • 2 - uKernel - Intel® ME is in Micro Kernel phase • 3 - Policy Module - Intel® ME is in Policy Module phase • 4 - Other Module - Intel® ME is loading modules in M0 or M3 Operating State
27:16	0x0 RO	**Extended Status Data:** These bits provide extended status data for the current state of operating of the firmware. Or, if the firmware is in a fatal error state, these bits provide extended error code information.
15:13	0x0 RO	**Firmware Heartbeat:** This number increments approximately every second if Intel® ME firmware is running.
12	0x0 RO	Intel® ME Target Image Boot Fault • 0 - Target image loaded successfully • 1 - Target image boot failed, switched to backup image or recovery image
11:8	0x0 RO	Reserved
7	0x0 RO	**Warm Reset Request:** If this bit is set, Intel® ME informs BIOS that a warm reset is requested by Intel® ME.
6	0x0 RO	**MFS Failure:** If this bit is set, Intel® ME informs BIOS that Intel® ME File System failure has been detected during recent Intel® ME boot.
5:4	0x0 RO	Reserved

3:1	0x0
	RO
		Recovery Cause: If ME1.HFS.Current State indicates that Intel® ME firmware is running in recovery mode these bits provide the cause of this mode:
		• 0 - Intel® ME recovery jumper asserted
		• 1 - Security strap override jumper asserted
		• 2 - Recovery forced with IPMI command
		• 3 - Invalid flash configuration, either:
		  • flash master access permissions configuration is wrong
		  • VSCC entry is missing or wrong
		  • flash erase block size in Intel® ME region configuration
		• 4 - Intel® ME internal error
		  Intel® ME could not start in operational mode because of some firmware problems.
		• 5..7 - Reserved for future extensions

0	0x0 RO	**BIST in Progress:** If this bit is set Intel® ME Built In Self-Test is in Progress.

54.2.19 Host General Status (HECI1_H_GS1)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status (H_GS1):** General status of Host. This field is not used by hardware.

54.2.20 PCI Power Management Capability ID (HECI1_PID)—Offset 50h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:0] + 50h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Capability (NEXT):** Indicates the location of the next capability item in the list. This is the Message Signaled Interrupts capability.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management.

54.2.21 PCI Power Management Capabilities (HECI1_PC)—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:0] + 52h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME Support (PSUP):** Indicates the states that can generate PME#. HECI can assert PME# from D3hot only.
10	0x0 RO	**D2 Support (D2S):** The D2 state is not supported for the HECI host controller.
9	0x0 RO	**D _Support (D1S):** The D1 state is not supported for the HECI host controller.
8:6	0x0 RO	**Aux_Current (AUXC):** Reports the maximum Suspend well current required when in the D3COLD state. Value of 0 is reported.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates whether device-specific initialization is required.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

54.2.22 PCI Power Management Control and Status (HECI1_PMCS)—Offset 54h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:0] + 54h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**PME Status (PMES):** The PME Status bit in HECI space can be set to '1' by CSE FW performing a write into CSE side register to set PMES. This bit is cleared by host CPU writing a '1' to it. CSE cannot clear this bit. Host CPU writes with value '0' have no effect on this bit.
14:9	0x0 RO	**Reserved (RSVD_14_9):** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, PME_assert and PME_deassert messages are sent over the SoC Sideband to the SoC PMC based on the PMES bit. When reset these messages are not sent to the PMC.
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that when the HECI host controller is transitioning from D3hot to D0 due to power state command, it does not perform and internal reset.
2	0x0 RO	**Reserved (RSVD_2_2):** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the HECI host controller and to set a new power state. The values are: • 00 - D0 state • 11 - D3HOT state The D1 and D2 states are not supported for this HECI host controller.

54.2.23 General Status Shadow 2 (HECI1_GS_SHDW2)—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 2 (GSS2):** This field is host side shadow of CSE General Status 2 (CSE_GS2).

54.2.24 General Status Shadow 3 (HECI1_GS_SHDW3)—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 3 (GSS3):** This field is host side shadow of CSE General Status 3 (CSE_GS3).

54.2.25 General Status Shadow 4 (HECI1_GS_SHDW4)—Offset 68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 4 (GSS4):** This field is host side shadow of CSE General Status 4 (CSE_GS4).

54.2.26 General Status Shadow 5 (HECI1_GS_SHDW5)—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 5 (GSS5):** This field is host side shadow of CSE General Status 5 (CSE_GS5).

54.2.27 Host General Status 2 (HECI1_H_GS2)—Offset 70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 2 (H_GS2):** General status of Host. This field is not used by hardware.

54.2.28 Host General Status 3 (HECI1_H_GS3)—Offset 74h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:27, F:0] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 3 (H_GS3):** General status of Host. This field is not used by hardware.

54.2.29 Message Signaled Interrupt Identifiers (HECI1_MID)—Offset 8Ch

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:27, F:0] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NEXT):** Indicates the next item in the list. This can be additional capability pointers or, if zero, indicates that this is the last item in the list.
7:0	0x5 RO	**Capability ID (CID):** Indicates Message Signaled Interrupts (MSI).

54.2.30 Message Signaled Interrupt Message Control (HECI1_MC)—Offset 8Eh

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:27, F:0] + 8Eh

Default: 0080h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Reserved (RSVD):** Reserved.
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages.
6:4	0x0 RO	**Multiple Message Enable (MME):** Not implemented, hardwired to 0.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not implemented, hardwired to 0.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and INTx virtual wires are not used to generate interrupts.

54.2.31 Message Signaled Interrupt Message Address (HECI1_MA)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DW aligned.
1:0	0x0 RO	**Reserved (RSVD):** Reserved.

54.2.32 Message Signaled Interrupt Upper Address (HECI1_MUA)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address (UADDR):** Upper 32 bits of the system specified message address. This register is optional and only implemented if MC.C64=1.

54.2.33 Message Signaled Interrupt Message Data (HECI1_MD)—Offset 98h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:0] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the FSB during the data phase of the MSI memory write transaction.

54.2.34 HECI Interrupt Delivery Mode (HECI1_HIDM)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:0] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved.
2	0x0 RW/1S	**HIDM Lock (HIDM_L):** Writing 1 to this bit locks the HIDM field.
1:0	0x0 RW/L	**HECI Interrupt Delivery Mode (HIDM):** These bits control what type of interrupt the HECI will send when CSE FW writes to set the CSE_IG bit. They are interpreted as follows: • 00 - Generate Legacy or MSI interrupt • 01 - Generate SCI • 10 - Generate SMI This field may be locked by writing 1 to HIDM_L bit.

54.2.35 Host Extend Register Status (HECI1_HERS)—Offset BCh

This register is used to communicate the CSE FW measurement status information to host.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + BCh

Default: 40000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Extend Register Valid (ERV):** Set by FW after all FW has been loaded and the measurement data has been stored in HERx registers. • If ERA field is SHA-1, the result of the extend operation is in HER:5-1. • If ERA field is SHA-256, the result is in HER:8-1.
30	0x1 RO	**Extend Feature Present (EFP):** This bit is hardwired to 1 to allow driver software to easily detect the chipset supports the Extend Registers FW measurement feature.
29:4	0x0 RO	**Reserved (RSVD_29_4):** Reserved.
3:0	0x0 RO/V	**Extend Register Algorithm (ERA):** This field indicates the hash algorithm used in the FW measurement Extend operation. Encodings are: • 0x0: SHA-1 • 0x2: SHA-256 • Other values: reserved. This field is set by FW with the used hash algorithm value when the ERV bit is set to 1. This field is meaningless when the ERV bit is 0. This field does NOT have any defined reset value.

54.2.36 Host Extend Register DW1. (HECI1_HER1)—Offset C0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW1 (ERDW1):** 1st DWORD result of the extend operation. ***Note:*** Note: Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.37 Host Extend Register DW2. (HECI1_HER2)—Offset C4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW2 (ERDW2):** 2nd DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.38 Host Extend Register DW3. (HECI1_HER3)—Offset C8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW3 (ERDW3):** 3rd DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.39 Host Extend Register DW4. (HECI1_HER4)—Offset CCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW4 (ERDW4):** 4th DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.40 Host Extend Register DW5. (HECI1_HER5)—Offset D0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW5 (ERDW5):** 5th DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.41 Host Extend Register DW6. (HECI1_HER6)—Offset D4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + D4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW6 (ERDW6):** 6th DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.42 Host Extend Register DW7. (HECI1_HER7)—Offset D8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + D8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW7 (ERDW7):** 7th DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.43 Host Extend Register DW8. (HECI1_HER8)—Offset DCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + DCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Host Extend Register DW8 (ERDW8):** 8th DWORD result of the extend operation. ***Note:*** Extend Operation is HER[5:1] if using SHA-1. If using SHA-256 then Extend Operation is HER[8:1].

54.2.44 Manufacturer's ID (HECI1_MANID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:0] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD_31_28):** Reserved.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Indicates the dot process.
23:16	0x0 RO/V	**Manufacturing Stepping ID (MSID):** This field is incremented for each stepping of the part. This field can be used by software to differentiate steppings when Revision ID may not change.
15:8	0x0 RO/V	**Manufacturing ID (MID):** This field is set by the SoC.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Indicates the process. The dot portion of the process is reflected in bits [27:24]. This field can be used by software to differentiate steppings when Revision ID may not change.

54.3 Registers in Configuration Space—HECI2

54.3.1 Identifiers (HECI2_ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 0h

Default: 19E68086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19E6 RO/V	**Device ID (DID):** Indicates what device number assigned by Intel.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates that Intel is the vendor, assigned by the PCI SIG.

54.3.2 Command (HECI2_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD:** Reserved
10	0x0 RW	**Interrupt Disable (ID):** Disables this device from generating PCI line based interrupts. This bit does not have any effect on MSI operations.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not implemented, hardwired to 0.
8	0x0 RO	**SERR# Enable (SEE):** Not implemented, hardwired to 0.
7	0x0 RO	**Wait Cycle Enable (WCC):** Not implemented, hardwired to 0.
6	0x0 RO	**Parity Error Response Enable (PEE):** Not implemented, hardwired to 0.
5	0x0 RO	**VGA Palette Snooping Enable (VAG):** Not implemented, hardwired to 0
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not implemented, hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not implemented, hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the HECI host controller's ability to act as a system memory master for data transfers. When this bit is cleared, HECI bus master activity stops and any active DMA engines return to an idle condition. This bit is made visible to firmware through the H_PCI_CSR register, and changes to this bit may be configured by the H_PCI_CSR register to generate an MSI to mIA. When this bit is '0', HECI is blocked from generating MSI to the host CPU. ***Note:*** This bit does not block HECI accesses to CSE-UMA
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the HECI host controllers memory-mapped register space.
0	0x0 RO	**I/O Space Enable (IOSE):** Not implemented, hardwired to 0.

54.3.3 Status (HECI2_STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Detected Parity Error (DPE):** Not implemented, hardwired to 0.
14	0x0 RO	**Signaled System Error (SSE):** Not implemented, hardwired to 0.
13	0x0 RO	**Received Master-Abort (RMA):** Not implemented, hardwired to 0.
12	0x0 RO	**Received Target Abort (RTA):** Not implemented, hardwired to 0.
11	0x0 RO	**Signaled Target-Abort (STA):** Not implemented, hardwired to 0.
10:9	0x0 RO	**DEVSEL# Timing (DEVT):** These bits are hardwired to 00.
8	0x0 RO	**Master Data Pariy Error Detected (DPD):** Not implemented, hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not implemented, hardwired to 0.
6	0x0 RO	**RSVD (RSVD_6_6):** Reserved
5	0x0 RO	**66 MHz Capable (C66):** Not implemented, hardwired to 0.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list, hardwired to 1.
3	0x0 RO/V	**Interrupt Status (IS):** Reflects the state of the INTx# signal at the input of the enable/disable circuit. This bit is a 1 when the INTx# is asserted. This bit is a 0 after the interrupt is cleared (independent of the state of the Interrupt Disable bit in the command register). ***Note:*** This bit is not set by an MSI.
2:0	0x0 RO	**RSVD (RSVD_2_0):** Reserved

54.3.4 Revision ID and Class Code (HECI2_RID_CC)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 8h

Default: 07800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Indicates the base class code of the HECI host controller device.
23:16	0x80 RO	**Sub Class Code (SCC):** Indicates the sub class code of the HECI host controller device.
15:8	0x0 RO	**Programming Interface (PI):** Indicates the programming interface of the HECI host controller device.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates stepping of the HECI host controller.

54.3.5 Cache Line Size (HECI2_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented, hardwired to 0.

54.3.6 Master Latency Timer (HECI2_MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Not implemented, hardwired to 0.

54.3.7 Header Type (HECI2_HTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + Eh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Multi-Function Device (MFD):** Indicates the HECI host controller is part of a multi-function device.
6:0	0x0 RO	**Header Layout (HL):** Indicates that the HECI host controller uses a target device layout.

54.3.8 Built In Self-Test (HECI2_BIST)—Offset Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**BIST Capable (BC):** Not implemented, hardwired to 0.
6:0	0x0 RO	**RSVD:** Reserved

54.3.9 HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Base Address Low (BA_LO):** Lower 32 bits of base address of register memory space.
11:4	0x0 RO	**Memory Size (MS):** This field is hardwired to 0 to indicate that HECI device requests 4KB of memory space.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not pre-fetchable
2:1	0x2 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 64-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

54.3.10 HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address High (BA_HI):** Upper 32 bits of base address of register memory space.

54.3.11 Sub System Identifiers (HECI2_SS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Indicates the sub- system identifier. This field should be programmed by BIOS during boot-up. Once written, this register becomes Read Only.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Indicates the sub-system vendor identifier. This field should be programmed by BIOS during boot- up. Once written, this register becomes Read Only.

54.3.12 Capabilities Pointer (HECI2_CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + 34h

Default: 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x50 RO	**Capability Pointer (CP):** Indicates the first capability pointer offset. It points to the PCI power management capability offset.

54.3.13 Interrupt Information (HECI2_INTR)—Offset 3Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO/V	**Interrupt Pin (IPIN):** This field indicates the virtual interrupt pin the HECI host controller uses. A value of 0x1/0x2/0x3/0x4 indicates that this function implements legacy interrupt on INTA/INTB/INTC/INTD, respectively. When legacy interrupt is not used this register should be set to 0x0.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this field.

54.3.14 Minimum Grant (HECI2_MGNT)—Offset 3Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + 3Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Grant (GNT):** Not implemented, hardwired to 0.

54.3.15 Maximum Latency (HECI2_MLAT)—Offset 3Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + 3Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Latency (LAT):** Not implemented, hardwired to 0.

54.3.16 Host Firmware Status (HECI2_HFS)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**BIOS MSG ACK:** Acknowledge for register based BIOS message in MEI 1 H_GS Register.
27:25	0x0 RO	**BIOS MSG ACK Data:** Message specific data for acknowledged BIOS message.
24:20	0x0 RO	Reserved
19:16	0x0 RO	**Operating Mode:** This field describes the current operating mode of Intel® ME. • 1:0 - Reserved • 2 - Debug Mode • 14:3 - Reserved • 15 - Intel® SPS firmware is running in Intel® ME
15:12	0x0 RO	**Error Code:** If set to nonzero value the Intel® ME firmware has encountered a fatal error and stopped normal operation. • 0 - No Error • 1 - Uncategorized Failure - The Intel® ME firmware has experienced an uncategorized error. Further details of the failure can be found in the Extended Status Data. • 2 - Disabled - Firmware was disabled on this platform. • 3 - Image Failure - The Intel® ME firmware stored in the system flash is not valid.
11	0x0 RO	**Update in Progress:** The bit is set if any type of Intel® ME firmware update is in progress.
10	0x0 RO	**Recovery BUP Load Fault:** This bit is set when firmware is not able to load recovery bring-up from the flash. It means that the recovery section in Intel® ME region on the SPI flash.
9	0x0 RO	**Init Complete:** When this but is not set firmware is still in initialization phase. When firmware has fully entered a stable state, this but is set to 1 and "Current State" field of this register provides the steady state of the Intel® ME subsystem.
8:6	0x0 RO	**Operating State:** This field describes the current operating state of Intel® ME. • 000 - Preboot • 001 - M0 with UMA • 010 - Reserved • 011 - Reserved • 100 - M3 without UMA • 101 - M0 without UMA - normal state for Intel® SPS firmware • 110 - Bring up • 111 - M0 without UMA but with error
5	0x0 RO	**FPT or Factory Defaults Bad:** This bit is set when the firmware discovers a bad checksum of Intel® ME region Flash Partition Table (FPT) or Factory Defaults. When this bit set, it may or may not have the error code shown in bit [15:12]. The system can get this bit clear only by re-flashing the whole Intel® ME region in the SPI Flash.
4	0x0 RO	**Manufacturing Mode:** When this bit is set, the platform is still in manufacturing mode. Host can use this bit to inform user that the platform is NOT READY for production yet. This but is set as long as Intel® ME Region access is not locked for flash masters other than Intel® ME. For shipping machine, this bit MUST be 0.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**Current State:** This field describes the current operation state of the firmware. • 0 - Reset - Intel® ME is in reset state, will exit this state within 1 millisecond • 1 - Initialization - Intel® ME is initializing, will exit this state within 2 seconds • 2 - Recovery - Intel® ME is in recovery mode, check ME1.GMES register to determine cause • 3 - Reserved • 4 - Disabled - Intel® ME functionality has been disabled, it executes idle loop • 5 - Operational - Intel® ME is in normal operational state • 6 - Reserved • 7 - State Transition - Intel® ME sets this state before starting a transition to a new Operating State. It is a temporary state, may appear on transition between Initialization and Operational.

54.3.17 General Status Shadow 1 (HECI2_GS_SHDW1)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**EOP Status:** This bit presents the Intel® ME notion of EOP status. If BIOS encounters this bit set to '1' during POST it signals an error in platform power flow.
30:28	0x0 RO	**Infrastructure Progress Code:** This field identifies the infrastructure progress code: • 0 - ROM - Intel® ME is in ROM phase • 1 - BUP - Intel® ME is in BRINGUP phase • 2 - uKernel - Intel® ME is in Micro Kernel phase • 3 - Policy Module - Intel® ME is in Policy Module phase • 4 - Other Module - Intel® ME is loading modules in M0 or M3 Operating State
27:16	0x0 RO	**Extended Status Data:** These bits provide extended status data for the current state of operating of the firmware. Or, if the firmware is in a fatal error state, these bits provide extended error code information.
15:13	0x0 RO	**Firmware Heartbeat:** This number increments approximately every second if Intel® ME firmware is running.
12	0x0 RO	Intel® ME Target Image Boot Fault • 0 - Target image loaded successfully • 1 - Target image boot failed, switched to backup image or recovery image
11:8	0x0 RO	Reserved
7	0x0 RO	**Warm Reset Request:** If this bit is set, Intel® ME informs BIOS that a warm reset is requested by Intel® ME.
6	0x0 RO	**MFS Failure:** If this bit is set, Intel® ME informs BIOS that Intel® ME File System failure has been detected during recent Intel® ME boot.
5:4	0x0 RO	Reserved

3:1	0x0
	RO
		Recovery Cause: If ME1.HFS.Current State indicates that Intel® ME firmware is running in recovery mode these bits provide the cause of this mode:
		• 0 - Intel® ME recovery jumper asserted
		• 1 - Security strap override jumper asserted
		• 2 - Recovery forced with IPMI command
		• 3 - Invalid flash configuration, either:
		  • flash master access permissions configuration is wrong
		  • VSCC entry is missing or wrong
		  • flash erase block size in Intel® ME region configuration
		• 4 - Intel® ME internal error
		  Intel® ME could not start in operational mode because of some firmware problems.
		• 5..7 - Reserved for future extensions

0	0x0 RO	**BIST in Progress:** If this bit is set Intel® ME Built In Self-Test is in Progress.

54.3.18 Host General Status (HECI2_H_GS1)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status (H_GS1):** General status of Host. This field is not used by hardware.

54.3.19 PCI Power Management Capability ID (HECI2_PID)—Offset 50h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 50h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Capability (NEXT):** Indicates the location of the next capability item in the list. This is the Message Signaled Interrupts capability.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management.

54.3.20 PCI Power Management Capabilities (HECI2_PC)—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 52h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME Support (PSUP):** Indicates the states that can generate PME#. HECI can assert PME# from D3hot only.
10	0x0 RO	**D2 Support (D2S):** The D2 state is not supported for the HECI host controller.
9	0x0 RO	**D _Support (D1S):** The D1 state is not supported for the HECI host controller.
8:6	0x0 RO	**Aux_Current (AUXC):** Reports the maximum Suspend well current required when in the D3COLD state. Value of 0 is reported.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates whether device-specific initialization is required.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

54.3.21 PCI Power Management Control and Status (HECI2_PMCS)—Offset 54h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 54h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**PME Status (PMES):** The PME Status bit in HECI space can be set to '1' by CSE FW performing a write into CSE side register to set PMES. This bit is cleared by host CPU writing a '1' to it. CSE cannot clear this bit. Host CPU writes with value '0' have no effect on this bit.
14:9	0x0 RO	**Reserved (RSVD_14_9):** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, PME_assert and PME_deassert messages are sent over the Soc Sideband to the SoC PMC based on the PMES bit. When reset these messages are not sent to the PMC.
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that when the HECI host controller is transitioning from D3hot to D0 due to power state command, it does not perform and internal reset.
2	0x0 RO	**Reserved (RSVD_2_2):** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the HECI host controller and to set a new power state. The values are: • 00 - D0 state • 11 - D3HOT state The D1 and D2 states are not supported for this HECI host controller.

54.3.22 General Status Shadow 2 (HECI2_GS_SHDW2)—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 2 (GSS2):** This field is host side shadow of CSE General Status 2 (CSE_GS2).

54.3.23 General Status Shadow 3 (HECI2_GS_SHDW3)—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 3 (GSS3):** This field is host side shadow of CSE General Status 3 (CSE_GS3).

54.3.24 General Status Shadow 4 (HECI2_GS_SHDW4)—Offset 68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 4 (GSS4):** This field is host side shadow of CSE General Status 4 (CSE_GS4).

54.3.25 General Status Shadow 5 (HECI2_GS_SHDW5)—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 5 (GSS5):** This field is host side shadow of CSE General Status 5 (CSE_GS5).

54.3.26 Host General Status 2 (HECI2_H_GS2)—Offset 70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 2 (H_GS2):** General status of Host. This field is not used by hardware.

54.3.27 Host General Status 3 (HECI2_H_GS3)—Offset 74h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 3 (H_GS3):** General status of Host. This field is not used by hardware.

54.3.28 Message Signaled Interrupt Identifiers (HECI2_MID)—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NEXT):** Indicates the next item in the list. This can be additional capability pointers or, if zero, indicates that this is the last item in the list.
7:0	0x5 RO	**Capability ID (CID):** Indicates Message Signaled Interrupts (MSI).

54.3.29 Message Signaled Interrupt Message Control (HECI2_MC)—Offset 8Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 8Eh

Default: 0080h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Reserved (RSVD):** Reserved.
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages.
6:4	0x0 RO	**Multiple Message Enable (MME):** Not implemented, hardwired to 0.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not implemented, hardwired to 0.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and INTx virtual wires are not used to generate interrupts.

54.3.30 Message Signaled Interrupt Message Address (HECI2_MA)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DW aligned.
1:0	0x0 RO	**Reserved (RSVD):** Reserved.

54.3.31 Message Signaled Interrupt Upper Address (HECI2_MUA)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address (UADDR):** Upper 32 bits of the system specified message address. This register is optional and only implemented if MC.C64=1.

54.3.32 Message Signaled Interrupt Message Data (HECI2_MD)—Offset 98h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:1] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the FSB during the data phase of the MSI memory write transaction.

54.3.33 HECI Interrupt Delivery Mode (HECI2_HIDM)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:1] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved.
2	0x0 RW/1S	**HIDM Lock (HIDM_L):** Writing 1 to this bit locks the HIDM field.
1:0	0x0 RW/L	**HECI Interrupt Delivery Mode (HIDM):** These bits control what type of interrupt the HECI will send when CSE FW writes to set the CSE_IG bit. They are interpreted as follows: • 00 - Generate Legacy or MSI interrupt • 01 - Generate SCI • 10 - Generate SMI This field may be locked by writing 1 to HIDM_L bit.

54.3.34 Manufacturer's ID (HECI2_MANID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:1] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD_31_28):** Reserved.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Indicates the dot process.
23:16	0x0 RO/V	**Manufacturing Stepping ID (MSID):** This field is incremented for each stepping of the part. ***Note:*** This field can be used by software to differentiate steppings when Revision ID may not change.
15:8	0x0 RO/V	**Manufacturing ID (MID):** This field is set by the SoC.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Indicates the process. The dot portion of the process is reflected in bits [27:24]. This field can be used by software to differentiate steppings when Revision ID may not change.

54.4 Registers in Configuration Space—HECI3

54.4.1 Identifiers (HECI3_ID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 0h

Default: 19E98086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19E9 RO/V	**Device ID (DID):** Indicates what device number assigned by Intel.
15:0	0x8086 RO	**Vendor ID (VID):** 16-bit field which indicates that Intel is the vendor, assigned by the PCI SIG.

54.4.2 Command (HECI3_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD:** Reserved
10	0x0 RW	**Interrupt Disable (ID):** Disables this device from generating PCI line based interrupts. This bit does not have any effect on MSI operations.
9	0x0 RO	**Fast Back-to-Back Enable (FBE):** Not implemented, hardwired to 0.
8	0x0 RO	**SERR# Enable (SEE):** Not implemented, hardwired to 0.
7	0x0 RO	**Wait Cycle Enable (WCC):** Not implemented, hardwired to 0.
6	0x0 RO	**Parity Error Response Enable (PEE):** Not implemented, hardwired to 0.
5	0x0 RO	**VGA Palette Snooping Enable (VAG):** Not implemented, hardwired to 0
4	0x0 RO	**Memory Write and Invalidate Enable (MWIE):** Not implemented, hardwired to 0.
3	0x0 RO	**Special Cycle Enable (SCE):** Not implemented, hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the HECI host controller's ability to act as a system memory master for data transfers. When this bit is cleared, HECI bus master activity stops and any active DMA engines return to an idle condition. This bit is made visible to firmware through the H_PCI_CSR register, and changes to this bit may be configured by the H_PCI_CSR register to generate an MSI to mIA. When this bit is '0', HECI is blocked from generating MSI to the host CPU. ***Note:*** This bit does not block HECI accesses to CSE-UMA
1	0x0 RW	**Memory Space Enable (MSE):** Controls access to the HECI host controllers memory-mapped register space.
0	0x0 RO	**I/O Space Enable (IOSE):** Not implemented, hardwired to 0.

54.4.3 Status (HECI3_STS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 6h

Default: 0010h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Detected Parity Error (DPE):** Not implemented, hardwired to 0.
14	0x0 RO	**Signaled System Error (SSE):** Not implemented, hardwired to 0.
13	0x0 RO	**Received Master-Abort (RMA):** Not implemented, hardwired to 0.
12	0x0 RO	**Received Target Abort (RTA):** Not implemented, hardwired to 0.
11	0x0 RO	**Signaled Target-Abort (STA):** Not implemented, hardwired to 0.
10:9	0x0 RO	**DEVSEL# Timing (DEVT):** These bits are hardwired to 00.
8	0x0 RO	**Master Data Pariy Error Detected (DPD):** Not implemented, hardwired to 0.
7	0x0 RO	**Fast Back-to-Back Capable (FBC):** Not implemented, hardwired to 0.
6	0x0 RO	**RSVD (RSVD_6_6):** Reserved
5	0x0 RO	**66 MHz Capable (C66):** Not implemented, hardwired to 0.
4	0x1 RO	**Capabilities List (CL):** Indicates the presence of a capabilities list, hardwired to 1.
3	0x0 RO/V	**Interrupt Status (IS):** Reflects the state of the INTx# signal at the input of the enable/disable circuit. This bit is a 1 when the INTx# is asserted. This bit is a 0 after the interrupt is cleared (independent of the state of the Interrupt Disable bit in the command register). ***Note:*** This bit is not set by an MSI.
2:0	0x0 RO	**RSVD (RSVD_2_0):** Reserved

54.4.4 Revision ID and Class Code (HECI3_RID_CC)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 8h

Default: 07800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Indicates the base class code of the HECI host controller device.
23:16	0x80 RO	**Sub Class Code (SCC):** Indicates the sub class code of the HECI host controller device.
15:8	0x0 RO	**Programming Interface (PI):** Indicates the programming interface of the HECI host controller device.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates stepping of the HECI host controller.

54.4.5 Cache Line Size (HECI3_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented, hardwired to 0.

54.4.6 Master Latency Timer (HECI3_MLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Master Latency Timer (MLT):** Not implemented, hardwired to 0.

54.4.7 Header Type (HECI3_HTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + Eh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Multi-Function Device (MFD):** Indicates the HECI host controller is part of a multi-function device.
6:0	0x0 RO	**Header Layout (HL):** Indicates that the HECI host controller uses a target device layout.

54.4.8 Built In Self-Test (HECI3_BIST)—Offset Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**BIST Capable (BC):** Not implemented, hardwired to 0.
6:0	0x0 RO	**RSVD:** Reserved

54.4.9 HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Base Address Low (BA_LO):** Lower 32 bits of base address of register memory space.
11:4	0x0 RO	**Memory Size (MS):** This field is hardwired to 0 to indicate that HECI device requests 4KB of memory space.
3	0x0 RO	**Prefetchable (PF):** Indicates that this range is not pre-fetchable.
2:1	0x2 RO	**Type (TP):** Indicates that this range can be mapped anywhere in 64-bit address space.
0	0x0 RO	**Resource Type Indicator (RTE):** Indicates a request for register memory space.

54.4.10 HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address High (BA_HI):** Upper 32 bits of base address of register memory space.

54.4.11 Sub System Identifiers (HECI3_SS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Indicates the sub- system identifier. This field should be programmed by BIOS during boot-up. Once written, this register becomes Read Only.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Indicates the sub-system vendor identifier. This field should be programmed by BIOS during boot- up. Once written, this register becomes Read Only.

54.4.12 Capabilities Pointer (HECI3_CAP)—Offset 34h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + 34h

Default: 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x50 RO	**Capability Pointer (CP):** Indicates the first capability pointer offset. It points to the PCI power management capability offset.

54.4.13 Interrupt Information (HECI3_INTR)—Offset 3Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 3Ch

Default: 0100h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x1 RO/V	**Interrupt Pin (IPIN):** This field indicates the virtual interrupt pin the HECI host controller uses. A value of 0x1/0x2/0x3/0x4 indicates that this function implements legacy interrupt on INTA/INTB/INTC/INTD, respectively. When legacy interrupt is not used this register should be set to 0x0.
7:0	0x0 RW	**Interrupt Line (ILINE):** Software written value to indicate which interrupt line (vector) the interrupt is connected to. No hardware action is taken on this field.

54.4.14 Minimum Grant (HECI3_MGNT)—Offset 3Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + 3Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Grant (GNT):** Not implemented, hardwired to 0.

54.4.15 Maximum Latency (HECI3_MLAT)—Offset 3Fh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + 3Fh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Latency (LAT):** Not implemented, hardwired to 0.

54.4.16 Host Firmware Status (HECI3_HFS)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**BIOS MSG ACK:** Acknowledge for register based BIOS message in MEI 1 H_GS Register.
27:25	0x0 RO	**BIOS MSG ACK Data:** Message specific data for acknowledged BIOS message.
24:20	0x0 RO	Reserved
19:16	0x0 RO	**Operating Mode:** This field describes the current operating mode of Intel® ME. • 1:0 - Reserved • 2 - Debug Mode • 14:3 - Reserved • 15 - Intel® SPS firmware is running in Intel® ME
15:12	0x0 RO	**Error Code:** If set to nonzero value the Intel® ME firmware has encountered a fatal error and stopped normal operation. • 0 - No Error • 1 - Uncategorized Failure - The Intel® ME firmware has experienced an uncategorized error. Further details of the failure can be found in the Extended Status Data. • 2 - Disabled - Firmware was disabled on this platform. • 3 - Image Failure - The Intel® ME firmware stored in the system flash is not valid.
11	0x0 RO	**Update in Progress:** The bit is set if any type of Intel® ME firmware update is in progress.
10	0x0 RO	**Recovery BUP Load Fault:** This bit is set when firmware is not able to load recovery bring-up from the flash. It means that the recovery section in Intel® ME region on the SPI flash.
9	0x0 RO	**Init Complete:** When this but is not set firmware is still in initialization phase. When firmware has fully entered a stable state, this but is set to 1 and "Current State" field of this register provides the steady state of the Intel® ME subsystem.
8:6	0x0 RO	**Operating State:** This field describes the current operating state of Intel® ME. • 000 - Preboot • 001 - M0 with UMA • 010 - Reserved • 011 - Reserved • 100 - M3 without UMA • 101 - M0 without UMA - normal state for Intel® SPS firmware • 110 - Bring up • 111 - M0 without UMA but with error
5	0x0 RO	**FPT or Factory Defaults Bad:** This bit is set when the firmware discovers a bad checksum of Intel® ME region Flash Partition Table (FPT) or Factory Defaults. When this bit set, it may or may not have the error code shown in bit [15:12]. The system can get this bit clear only by re-flashing the whole Intel® ME region in the SPI Flash.
4	0x0 RO	**Manufacturing Mode:** When this bit is set, the platform is still in manufacturing mode. Host can use this bit to inform user that the platform is NOT READY for production yet. This but is set as long as Intel® ME Region access is not locked for flash masters other than Intel® ME. For shipping machine, this bit MUST be 0.

Bit Range	Default & Access	Field Name (ID): Description
3:0	0x0 RO	**Current State:** This field describes the current operation state of the firmware. • 0 - Reset - Intel® ME is in reset state, will exit this state within 1 millisecond • 1 - Initialization - Intel® ME is initializing, will exit this state within 2 seconds • 2 - Recovery - Intel® ME is in recovery mode, check ME1.GMES register to determine cause • 3 - Reserved • 4 - Disabled - Intel® ME functionality has been disabled, it executes idle loop • 5 - Operational - Intel® ME is in normal operational state • 6 - Reserved • 7 - State Transition - Intel® ME sets this state before starting a transition to a new Operating State. It is a temporary state, may appear on transition between Initialization and Operational.

54.4.17 General Status Shadow 1 (HECI3_GS_SHDW1)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**EOP Status:** This bit presents the Intel® ME notion of EOP status. If BIOS encounters this bit set to '1' during POST it signals an error in platform power flow.
30:28	0x0 RO	**Infrastructure Progress Code:** This field identifies the infrastructure progress code: • 0 - ROM - Intel® ME is in ROM phase • 1 - BUP - Intel® ME is in BRINGUP phase • 2 - uKernel - Intel® ME is in Micro Kernel phase • 3 - Policy Module - Intel® ME is in Policy Module phase • 4 - Other Module - Intel® ME is loading modules in M0 or M3 Operating State
27:16	0x0 RO	**Extended Status Data:** These bits provide extended status data for the current state of operating of the firmware. Or, if the firmware is in a fatal error state, these bits provide extended error code information.
15:13	0x0 RO	**Firmware Heartbeat:** This number increments approximately every second if Intel® ME firmware is running.
12	0x0 RO	Intel® ME Target Image Boot Fault • 0 - Target image loaded successfully • 1 - Target image boot failed, switched to backup image or recovery image
11:8	0x0 RO	Reserved
7	0x0 RO	**Warm Reset Request:** If this bit is set, Intel® ME informs BIOS that a warm reset is requested by Intel® ME.
6	0x0 RO	**MFS Failure:** If this bit is set, Intel® ME informs BIOS that Intel® ME File System failure has been detected during recent Intel® ME boot.
5:4	0x0 RO	Reserved

3:1	0x0
	RO
		Recovery Cause: If ME1.HFS.Current State indicates that Intel® ME firmware is running in recovery mode these bits provide the cause of this mode:
		• 0 - Intel® ME recovery jumper asserted
		• 1 - Security strap override jumper asserted
		• 2 - Recovery forced with IPMI command
		• 3 - Invalid flash configuration, either:
		  • flash master access permissions configuration is wrong
		  • VSCC entry is missing or wrong
		  • flash erase block size in Intel® ME region configuration
		• 4 - Intel® ME internal error
		  Intel® ME could not start in operational mode because of some firmware problems.
		• 5..7 - Reserved for future extensions

0	0x0 RO	**BIST in Progress:** If this bit is set Intel® ME Built In Self-Test is in Progress.

54.4.18 Host General Status (HECI3_H_GS1)—Offset 4Ch

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:27, F:4] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status (H_GS1):** General status of Host. This field is not used by hardware.

54.4.19 PCI Power Management Capability ID (HECI3_PID)—Offset 50h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:27, F:4] + 50h

Default: 8C01h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x8c RO	**Next Capability (NEXT):** Indicates the location of the next capability item in the list. This is the Message Signaled Interrupts capability.
7:0	0x1 RO	**Cap ID (CID):** Indicates that this pointer is a PCI power management.

54.4.20 PCI Power Management Capabilities (HECI3_PC)—Offset 52h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 52h

Default: 4003h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x8 RO	**PME Support (PSUP):** Indicates the states that can generate PME#. HECI can assert PME# from D3hot only.
10	0x0 RO	**D2 Support (D2S):** The D2 state is not supported for the HECI host controller.
9	0x0 RO	**D _Support (D1S):** The D1 state is not supported for the HECI host controller.
8:6	0x0 RO	**Aux_Current (AUXC):** Reports the maximum Suspend well current required when in the D3COLD state. Value of 0 is reported.
5	0x0 RO	**Device Specific Initialization (DSI):** Indicates whether device-specific initialization is required.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RO	**PME Clock (PMEC):** Indicates that PCI clock is not required to generate PME#.
2:0	0x3 RO	**Version (VS):** Indicates support for Revision 1.2 of the PCI Power Management Specification.

54.4.21 PCI Power Management Control and Status (HECI3_PMCS)—Offset 54h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 54h

Default: 0008h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**PME Status (PMES):** The PME Status bit in HECI space can be set to '1' by CSE FW performing a write into CSE side register to set PMES. This bit is cleared by host CPU writing a '1' to it. CSE cannot clear this bit. Host CPU writes with value '0' have no effect on this bit.
14:9	0x0 RO	**Reserved (RSVD_14_9):** Reserved.
8	0x0 RW	**PME Enable (PMEE):** When set, PME_assert and PME_deassert messages are sent over the SoC Sideband to the SoC PMC based on the PMES bit. When reset these messages may not be sent.
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x1 RO	**No Soft Reset (NSR):** This bit indicates that when the HECI host controller is transitioning from D3hot to D0 due to power state command, it does not perform and internal reset.
2	0x0 RO	**Reserved (RSVD_2_2):** Reserved.
1:0	0x0 RW	**Power State (PS):** This field is used both to determine the current power state of the HECI host controller and to set a new power state. The values are: • 00 - D0 state • 11 - D3HOT state The D1 and D2 states are not supported for this HECI host controller.

54.4.22 General Status Shadow 2 (HECI3_GS_SHDW2)—Offset 60h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 60h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 2 (GSS2):** This field is host side shadow of CSE General Status 2 (CSE_GS2).

54.4.23 General Status Shadow 3 (HECI3_GS_SHDW3)—Offset 64h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 64h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 3 (GSS3):** This field is host side shadow of CSE General Status 3 (CSE_GS3).

54.4.24 General Status Shadow 4 (HECI3_GS_SHDW4)—Offset 68h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 68h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 4 (GSS4):** This field is host side shadow of CSE General Status 4 (CSE_GS4).

54.4.25 General Status Shadow 5 (HECI3_GS_SHDW5)—Offset 6Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 6Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**General Status Shadow 5 (GSS5):** This field is host side shadow of CSE General Status 5 (CSE_GS5).

54.4.26 Host General Status 2 (HECI3_H_GS2)—Offset 70h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 70h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 2 (H_GS2):** General status of Host. This field is not used by hardware.

54.4.27 Host General Status 3 (HECI3_H_GS3)—Offset 74h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + 74h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Host General Status 3 (H_GS3):** General status of Host. This field is not used by hardware.

54.4.28 Message Signaled Interrupt Identifiers (HECI3_MID)—Offset 8Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 8Ch

Default: 0005h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Next Pointer (NEXT):** Indicates the next item in the list. This can be additional capability pointers or, if zero, indicates that this is the last item in the list.
7:0	0x5 RO	**Capability ID (CID):** Indicates a Message Signaled Interrupt (MSI).

54.4.29 Message Signaled Interrupt Message Control (HECI3_MC)—Offset 8Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:27, F:4] + 8Eh

Default: 0080h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**Reserved (RSVD):** Reserved.
7	0x1 RO	**64 Bit Address Capable (C64):** Specifies whether capable of generating 64-bit messages.
6:4	0x0 RO	**Multiple Message Enable (MME):** Not implemented, hardwired to 0.
3:1	0x0 RO	**Multiple Message Capable (MMC):** Not implemented, hardwired to 0.
0	0x0 RW	**MSI Enable (MSIE):** If set, MSI is enabled and INTx virtual wires are not used to generate interrupts.

54.4.30 Message Signaled Interrupt Message Address (HECI3_MA)—Offset 90h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:27, F:4] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Address (ADDR):** Lower 32 bits of the system specified message address, always DW aligned.
1:0	0x0 RO	**Reserved (RSVD):** Reserved.

54.4.31 Message Signaled Interrupt Upper Address (HECI3_MUA)—Offset 94h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:27, F:4] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Upper Address (UADDR):** Upper 32 bits of the system specified message address. This register is optional and only implemented if MC.C64=1.

54.4.32 Message Signaled Interrupt Message Data (HECI3_MD)—Offset 98h

Type: PCI Configuration Register
(Size: 16 bits)

Offset: [B:0, D:27, F:4] + 98h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**Data (DATA):** This 16-bit field is programmed by system software if MSI is enabled. Its content is driven onto the FSB during the data phase of the MSI memory write transaction.

54.4.33 HECI Interrupt Delivery Mode (HECI3_HIDM)—Offset A0h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:27, F:4] + A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved.
2	0x0 RW/1S	**HIDM Lock (HIDM_L):** Writing 1 to this bit locks the HIDM field.
1:0	0x0 RW/L	**HECI Interrupt Delivery Mode (HIDM):** These bits control what type of interrupt the HECI will send when CSE FW writes to set the CSE_IG bit. They are interpreted as follows: • 00 - Generate Legacy or MSI interrupt • 01 - Generate SCI • 10 - Generate SMI This field may be locked by writing 1 to HIDM_L bit.

54.4.34 Manufacturer's ID (HECI3_MANID)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:4] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD_31_28):** Reserved.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Indicates the dot process.
23:16	0x0 RO/V	**Manufacturing Stepping ID (MSID):** This field is incremented for each stepping of the part. This field can be used by software to differentiate steppings when Revision ID may not change.
15:8	0x0 RO/V	**Manufacturing ID (MID):** This field is set by the SoC.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Indicates the process. The dot portion of the process is reflected in bits [27:24]. This field can be used by software to differentiate steppings when Revision ID may not change.

54.5 Registers in Configuration Space—KT (Host)

54.5.1 Device ID and Vendor ID (KT_HOST_DID_VID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 0h

Default: 19E88086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19E8 RO/V	**Device ID (DID):** This field identifies the particular device.
15:0	0x8086 RO	**Vendor ID (VID):** This field identifies the manufacturer of the device. The value of 0x8086 indicates Intel.

54.5.2 Status and Command (KT_HOST_STS_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 4h

Default: 00B00000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Detected Parity Error (DPE):** Not implemented. Hardwired to 0.
30	0x0 RO	**Signaled System Error (SSE):** Not implemented. Hardwired to 0.
29	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit must be set by a master device whenever its transaction (except for Special Cycle) is completed with Unsupported Request Completion Status (a.k.a. Master-Abort). All master devices must implement this bit.
28	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit must be set by a master device whenever its transaction is completed with Completer Abort Completion Status (a.k.a. Target-Abort). All master devices must implement this bit.
27	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit must be set by a target device whenever it completes a Posted or Non-Posted transaction with a Completer Abort (a.k.a. Target-Abort) error. Devices that will never signal Completer Abort (a.k.a. Target-Abort) do not need to implement this bit.
26:25	0x0 RO	**Devsel Timing (DEVT):** These bits encode the timing of DEVSEL#. There are three allowable timings for assertion of DEVSEL# as described below: • 00b: fast • 01b: medium • 10b: slow • 11b: reserved These bits are read-only and must indicate the slowest time that a device asserts DEVSEL# for any bus command except Configuration Read and Configuration Write. Hardwired to 00b.
24	0x0 RO	**Master Data Parity Error (MDPE):** Not implemented. Hardwired to 0.
23	0x1 RO	**Fast Back to Back Capable (FBTBC):** This bit indicates whether or not the target is capable of accepting fast back-to-back transactions when the transactions are not to the same agent. This bit can be set to 1 if the device can accept these transactions and must be set to 0 otherwise. Hardwired to 1.
22	0x0 RO	**Reserved (RSVD3):** Reserved (RSVD)
21	0x1 RO	**66 Mhz Capable (MCAP):** This bit indicates whether or not this device is capable of running at 66 MHz. A value of 0 indicates 33 MHz. A value of 1 indicates that the device is 66 MHz capable. Hardwired to 1.
20	0x1 RO	**Capabilities List (CAPL):** This optional read-only bit indicates whether or not this device implements the pointer for a New Capabilities linked list at offset 34h. A value of zero indicates that no New Capabilities linked list is available. A value of one indicates that the value read at offset 34h is a pointer in Configuration Space to a linked list of new capabilities.
19	0x0 RO	**Interrupt Status (INTS):** This read-only bit reflects the state of the interrupt in the device/function. Only when the Interrupt Disable bit in the command register is a 0 and this Interrupt Status bit is a 1, will the device's/function's INTx# signal be asserted. Setting the Interrupt Disable bit to a 1 has no effect on the state of this bit. Read-only and hardwired to 0 for a device that does NOT support pin-based interrupt.
18:16	0x0 RO	**Reserved (RSVD2):**

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD1):**
10	0x0 RW	**Interrupt Disable (INTD):** This bit disables the device/function from asserting INTx#. A value of 0 enables the assertion of its INTx# signal. A value of 1 disables the assertion of its INTx# signal. This bit's state after RST# is 0.
9	0x0 RO	**Fast Back to Back Enable (FBTBEN):** Not implemented. Hardwired to 0.
8	0x0 RO	**System Error Enable (SERREN):** Not implemented. Hardwired to 0.
7	0x0 RO	**Reserved (RSVD0):**
6	0x0 RO	**Parity Error Response (PERRR):** Not implemented. Hardwired to 0.
5	0x0 RO	**VGA Palette Snoop (VGAPS):** Not implemented. Hardwired to 0.
4	0x0 RO	**Memory Write and Invalidate Enable (MWRIEN):** Not implemented. Hardwired to 0.
3	0x0 RO	**Special Cycles (SPCYC):** Not implemented. Hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the ability of a PCI device to issue Memory and I/O Read/Write Requests. When this bit is Set, the PCI device function is allowed to issue Memory or I/O Requests. When this bit is Clear, the PCI device function is not allowed to issue any Memory or I/O Requests. ***Note:*** As MSI/MSI-X interrupt Messages are in-band memory writes, setting the Bus Master Enable bit to 0b disables MSI/MSI-X interrupt Messages as well. Requests other than Memory or I/O Requests are not controlled by this bit. Default value of this bit is 0b. This bit is hardwired to 0b if a PCI device function does not generate Memory or I/O Requests.
1	0x0 RW	**Memory Space Enable (MSE):** Controls a device's response to Memory Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to Memory Space accesses. State after RST# is 0.
0	0x0 RW	**IO Space Enable (IOSE):** Controls a device's response to I/O Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to I/O Space accesses. State after RST# is 0.

54.5.3 Class Code and Revision ID (KT_HOST_CC_RID)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 8h

Default: 07000200h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x7 RO	**Base Class Code (BCC):** Identifies the Base Class Code of an external 16550-compatible serial controller device driver.
23:16	0x0 RO	**Sub-Class Code (SCC):** Identifies the Sub-Class Code of an external 16550-compatible serial controller device driver.
15:8	0x2 RO	**Programming Interface (PI):** Identifies the Programming Interface of an external 16550-compatible serial controller device driver.
7:0	0x0 RO/V	**Revision ID (RID):** This register specifies a device specific revision identifier. The value is chosen by the vendor. Zero is an acceptable value. This field should be viewed as a vendor defined extension to the Device ID.

54.5.4 BIST, Header Type, Latency Timer, and Cache Line Size (KT_HOST_BIST_HTYPE_LT_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + Ch

Default: 00800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Built In Self Test (BIST):** Not implemented. Hardwired to 0.
23	0x1 RO/V	**Header Type 1 (HTYPE1):** This bit identifies whether or not the device contains multiple functions. • If the bit is 0, then the device is single function. • If the bit is 1, then the device has multiple functions.
22:16	0x0 RO	**Header Type 0 (HTYPE0):** This field identifies the layout of the second part of the predefined header (beginning at byte 10h in Configuration Space). • The encoding 00h specifies the non-bridge Configuration Space Header. • The encoding 01h specifies the PCI-to-PCI bridge Configuration Space Header. • The encoding 02h specifies the CardBus bridge Configuration Space Header. • All other encodings are reserved. Hardwired to 0 to identify the non-bridge Configuration Space Header.
15:8	0x0 RO	**Latency Timer (LT):** Not implemented. Hardwired to 0.
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented. Hardwired to 0.

54.5.5 KT IO BAR (KT_HOST_IOBAR)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 10h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 8B of IO space.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

54.5.6 KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Memory BAR (MEMBAR):** Software programs this register with the base address of the device's memory region.
11:4	0x0 RO	**Memory Size (MEMSIZE):** Hardwired to 0 to indicate 4KB of memory space.
3	0x0 RO	**Prefetchable (PREFETCH):** A device can mark a range as prefetchable if there are no side effects on reads, the device returns all bytes on reads regardless of the byte enables. Hardwired to 0 to indicate the device's memory space as non-prefetchable.
2:1	0x0 RO	**Type (TYP):** Hardwired to 0 to indicate that Base register is 32 bits wide and mapping can be done anywhere in the 32-bit Memory Space.
0	0x0 RO	**Memory Space Indicator (MEMSPACE):** Hardwired to 0 to identify a Memory BAR.

54.5.7 Cardbus CIS Pointer (KT_HOST_CCP)—Offset 28h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Cardbus CIS Pointer (CCP):** Not implemented. Hardwired to 0.

54.5.8 Subsystem ID and Subsystem Vendor ID (KT_HOST_SID_SVID)—Offset 2Ch

These registers are used to uniquely identify the add-in card or subsystem where the PCI device resides. They provide a mechanism for add-in card vendors to distinguish their add-in cards from one another even though the add-in cards may have the same PCI controller on them (and, therefore, the same Vendor ID and Device ID).

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 2Ch

Default: 00008086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SID):** Value of this field is vendor-specific. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SID should have its own lock.
15:0	0x8086 RW/O	**Subsystem Vendor ID (SVID):** This field identifies the vendor of the add-in card or subsystem. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SVID should have its own lock.

54.5.9 Expansion ROM Base Address (KT_HOST_XRBAR)—Offset 30h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Expansion ROM Base Address (XRBAR):** Not implemented. Hardwired to 0.

54.5.10 Capabilities List Pointer (KT_HOST_CAPP)—Offset 34h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 34h

Default: 00000040h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):**
7:0	0x40 RO	**Capabilities Pointer (CAPP):** Indicates the pointer for the first entry in the capabilities list which is the MSI Capability.

54.5.11 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (KT_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 3Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Maximum Latency (MAXL):** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Minimum Grant (MING):** Not implemented. Hardwired to 0.
15:8	0x0 RO/V	**Interrupt Pin (INTP):** This register specifies which interrupt pin KT uses in PCI interrupt mode. Value Decoding • 00h The function does NOT use an interrupt pin. • 01h INTA • 02h INTB • 03h INTC • 04h INTD • 05h - FFh Reserved. ***Note:*** This field shadows the KTHIPINR.IPIN field in the PTIO Host private CR space which is configured by BIOS over IOSF SB.
7:0	0x0 RW	**Interrupt Line (INTL):** This register is used to communicate interrupt line routing information. POST software will write the routing information into this register as it initializes and configures the system.

54.5.12 MSI Message Control, Next Pointer and Capability ID (KT_HOST_MSIMC_MSINP_MSICID)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 40h

Default: 00805005h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**Reserved (RSVD):**
24	0x0 RO	**Per Vector Masking Capable (PVMC):** Not implemented. Hardwired to 0 to indicate the function does NOT support MSI per-vector masking.
23	0x1 RO	**64 bit address capable (XAC):** Hardwired to 1 to indicate the function is capable of sending a 64-bit message address.
22:20	0x0 RW	**Multiple Message Enable (MMEN):** Encoded number of interrupt vectors allocated by SW. This field is RW for software compatibility, but only one interrupt vector is ever sent by the function.
19:17	0x0 RO	**Multiple Message Capable (MMC):** Encoded number of interrupt vectors requested by a device. Hardwired to 0 to indicate one requested interrupt vector.
16	0x0 RW	**MSI Enable (MSIE):** If set, MSI interrupt delivery is enabled whereas pin-based interrupt delivery SHALL be disabled. If cleared, prior to returning the configuration write (that clears this field) completion, the function must send any pending MSI(s).
15:8	0x50 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 50h to point to the PM Capability list.
7:0	0x5 RO	**Capability ID (CID):** Hardwired to 05h to indicate the linked list item as the MSI Capability registers.

54.5.13 MSI Message Address (KT_HOST_MSIMA)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** 32-bit DW-aligned MSI message address.
1:0	0x0 RO	**Reserved (RSVD):**

54.5.14 MSI Message Upper Address (KT_HOST_MSIMUA)—Offset 48h

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:27, F:3] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Upper 32-bit of a 64-bit DW-aligned MSI message address.

54.5.15 MSI Message Data (KT_HOST_MSIMD)—Offset 4Ch

Type: PCI Configuration Register
(Size: 32 bits)

Offset: [B:0, D:27, F:3] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):**
15:0	0x0 RW	**Message Data (MD):** MSI Message Data

54.5.16 Power Management Capabilities, Next Pointer and Capability ID (KT_HOST_PMCAP_PMNP_PMCID)—Offset 50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 50h

Default: 00230001h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**PME Support (PMES):** This 5-bit field indicates the power states in which the function may assert PME#. A value of 0b for any bit indicates that the function is not capable of asserting the PME# signal while in that power state. • bit(27) X XXX1b - PME# can be asserted from D0 • bit(28) X XX1Xb - PME# can be asserted from D1 • bit(29) X X1XXb - PME# can be asserted from D2 • bit(30) X 1XXXb - PME# can be asserted from D3hot • bit(31) 1 XXXXb - PME# can be asserted from D3cold
26	0x0 RO	**D2 Support (D2S):** Hardwired to 0 to indicate that this device does not support D2.
25	0x0 RO	**D1 Support (D1S):** Hardwired to 0 to indicate that this device does not support D1.
24:22	0x0 RO	**Aux Current (AUXC):** Not implemented. Hardwired to 0.
21	0x1 RO	**Device Specific Initialization (DSI):** indicates whether special initialization of this function is required (beyond the standard PCI configuration header) before the generic class device driver is able to use it. A 1 indicates that the function requires a device specific initialization sequence following transition to the D0 uninitialized state. Hardwired to 1 to indicate Device Specific Initialization is required.
20	0x0 RO	**Reserved (RSVD):**
19	0x0 RO	**PME Clock (PMECLK):** Not implemented. Hardwired to 0.
18:16	0x3 RO	**Version (VER):** Hardwired to value of 011b indicates that this function complies with rev 1.2 of PCI Power Management Interface Spec.
15:8	0x0 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 0 to indicate no more linked list item.
7:0	0x1 RO	**Capability ID (CID):** Hardwired to 01h to indicate the linked list item as the PCI Power Management registers.

54.5.17 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (KT_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + 54h

Default: 00000008h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Data:** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Control/Status Register Bridge Support Extensions (CSRBSE):** Not implemented. Hardwired to 0.
15	0x0 RO	**PME Status (PMESTS):** This bit is set when the function would normally assert the PME signal independent of the state of the PME_En bit. • Writing a 1 to this bit will clear it and cause the function to stop asserting a PME (if enabled). • Writing a 0 has no effect. If the function supports PME from D3cold, then this bit is sticky and must be explicitly cleared by the operating system each time the operating system is initially loaded. Not implemented. Hardwired to 0.
14:13	0x0 RO	**Data Scale (DS):** Not implemented. Hardwired to 0.
12:9	0x0 RO	**Data Select (DSEL):** Not implemented. Hardwired to 0.
8	0x0 RO	**PME Enable (PMEEN):** A 1 enables the function to assert PME. When 0, PME assertion is disabled. This bit defaults to 0 if the function does not support PME generation from D3cold. If the function supports PME from D3cold then this bit is sticky and must be explicitly cleared by the operating system each time it is initially loaded. Not implemented. Hardwired to 0.
7:4	0x0 RO	**Reserved (RSVD1):**
3	0x1 RO	**No Soft Reset (NSR):** When set to 1, this bit indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. Configuration Context is preserved. Upon transition from the D3hot to the D0 Initialized state, no additional operating system intervention is required to preserve Configuration Context beyond writing the PowerState bits.
2	0x0 RO	**Reserved (RSVD0):**
1:0	0x0 RW	**Power State (PWRST):** This 2-bit field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the field values is given below: • 00b - D0 • 01b - D1 • 10b - D2 • 11b - D3hot If software attempts to write an unsupported, optional state to this field, the write operation must complete normally on the bus; however, the data is discarded and no state change occurs.

54.5.18 Process Stepping Information (KT_HOST_PSI)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:3] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Reserved.
23:16	0x0 RO/V	**Manufacturing Stepping (MSID):** Reserved.
15:8	0x0 RO/V	**Manufacturing ID (MID):** Reserved.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Reserved.

54.6 Registers in Configuration Space—IDE (Host)

54.6.1 Device ID and Vendor ID (IDE_HOST_DID_VID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 0h

Default: 19E78086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19e7 RO/V	**Device ID (DID):** This field identifies the particular device. This identifier is allocated by the vendor.
15:0	0x8086 RO	**Vendor ID (VID):** This field identifies the manufacturer of the device. The value of 0x8086 indicates Intel.

54.6.2 Status and Command (IDE_HOST_STS_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 4h

Default: 00B00000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Detected Parity Error (DPE):** Not implemented. Hardwired to 0.
30	0x0 RO	**Signaled System Error (SSE):** Not implemented. Hardwired to 0.
29	0x0 RW/1C/V	**Received Master Abort (RMA):** This bit must be set by a master device whenever its transaction (except for Special Cycle) is completed with Unsupported Request Completion Status (a.k.a. Master-Abort). All master devices must implement this bit.
28	0x0 RW/1C/V	**Received Target Abort (RTA):** This bit must be set by a master device whenever its transaction is completed with Completer Abort Completion Status (a.k.a. Target-Abort). All master devices must implement this bit.
27	0x0 RW/1C/V	**Signaled Target Abort (STA):** This bit must be set by a target device whenever it completes a Posted or Non-Posted transaction with a Completer Abort (a.k.a. Target-Abort) error. Devices that will never signal Completer Abort (a.k.a. Target-Abort) do not need to implement this bit.
26:25	0x0 RO	**Devsel Timing (DEVT):** These bits encode the timing of DEVSEL#. There are three allowable timings for assertion of DEVSEL# as described below: • 00b: fast • 01b: medium • 10b: slow • 11b: reserved These bits are read-only and must indicate the slowest time that a device asserts DEVSEL# for any bus command except Configuration Read and Configuration Write. Hardwired to 00b.
24	0x0 RO	**Master Data Parity Error (MDPE):** Not implemented. Hardwired to 0.
23	0x1 RO	**Fast Back to Back Capable (FBTBC):** This bit indicates whether or not the target is capable of accepting fast back-to-back transactions when the transactions are not to the same agent. This bit can be set to 1 if the device can accept these transactions and must be set to 0 otherwise. Hardwired to 1.
22	0x0 RO	**Reserved (RSVD3):** Reserved (RSVD
21	0x1 RO	**66 Mhz Capable (MCAP):** This bit indicates whether or not this device is capable of running at 66 MHz. • A value of 0 indicates 33 MHz • A value of 1 indicates that the device is 66 MHz capable Hardwired to 1.
20	0x1 RO	**Capabilities List (CAPL):** This optional read-only bit indicates whether or not this device implements the pointer for a New Capabilities linked list at offset 34h. • A value of zero indicates that no New Capabilities linked list is available. • A value of one indicates that the value read at offset 34h is a pointer in Configuration Space to a linked list of new capabilities.
19	0x0 RO	**Interrupt Status (INTS):** This read-only bit reflects the state of the interrupt in the device/function. Only when the Interrupt Disable bit in the command register is a 0 and this Interrupt Status bit is a 1, will the device's/function's INTx# signal be asserted. Setting the Interrupt Disable bit to a 1 has no effect on the state of this bit. Read-only and hardwired to 0 for a device that does NOT support pin-based interrupt.
18:16	0x0 RO	**Reserved (RSVD2):**

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD1):**
10	0x0 RW	**Interrupt Disable (INTD):** This bit disables the device/function from asserting INTx#. • A value of 0 enables the assertion of its INTx# signal • A value of 1 disables the assertion of its INTx# signal This bit's state after RST# is 0.
9	0x0 RO	**Fast Back to Back Enable (FBTBEN):** Not implemented. Hardwired to 0.
8	0x0 RO	**System Error Enable (SERREN):** Not implemented. Hardwired to 0.
7	0x0 RO	**Reserved (RSVD0):**
6	0x0 RO	**Parity Error Response (PERRR):** Not implemented. Hardwired to 0.
5	0x0 RO	**VGA Palette Snoop (VGAPS):** Not implemented. Hardwired to 0.
4	0x0 RO	**Memory Write and Invalidate Enable (MWRIEN):** Not implemented. Hardwired to 0.
3	0x0 RO	**Special Cycles (SPCYC):** Not implemented. Hardwired to 0.
2	0x0 RW	**Bus Master Enable (BME):** Controls the ability of a PCI device to issue Memory and I/O Read/Write Requests. When this bit is Set, the PCI device function is allowed to issue Memory or I/O Requests. When this bit is Clear, the PCI device function is not allowed to issue any Memory or I/O Requests. ***Note:*** As MSI/MSI-X interrupt Messages are in-band memory writes, setting the Bus Master Enable bit to 0b disables MSI/MSI-X interrupt Messages as well. Requests other than Memory or I/O Requests are not controlled by this bit. Default value of this bit is 0b. This bit is hardwired to 0b if a PCI device function does not generate Memory or I/O Requests.
1	0x0 RO	**Memory Space Enable (MSE):** Controls a device's response to Memory Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to Memory Space accesses. State after RST# is 0. Read-only and hardwired to 0 because IDE does NOT support Memory Space accesses.
0	0x0 RW	**IO Space Enable (IOSE):** Controls a device's response to I/O Space accesses. • A value of 0 disables the device response. • A value of 1 allows the device to respond to I/O Space accesses. State after RST# is 0.

54.6.3 Class Code and Revision ID (IDE_HOST_CC_RID)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 8h

Default: 01018500h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x1 RO	**Base Class Code (BCC):** Identifies the Base Class Code of an external IDE controller device driver.
23:16	0x1 RO	**Sub-Class Code (SCC):** Identifies the Sub-Class Code of an external IDE controller device driver.
15:8	0x85 RO	**Programming Interface (PI):** Identifies the Programming Interface of an IDE controller device driver.
7:0	0x0 RO/V	**Revision ID (RID):** This register specifies a device specific revision identifier. The value is chosen by the vendor. Zero is an acceptable value. This field should be viewed as a vendor defined extension to the Device ID.

54.6.4 BIST, Header Type, Latency Timer, and Cache Line Size (IDE_HOST_BIST_HTYPE_LT_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + Ch

Default: 00800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Built In Self Test (BIST):** Not implemented. Hardwired to 0.
23	0x1 RO/V	**Header Type 1 (HTYPE1):** This bit identifies whether or not the device contains multiple functions. • If the bit is 0, then the device is single function • If the bit is 1, then the device has multiple functions
22:16	0x0 RO	**Header Type 0 (HTYPE0):** This field identifies the layout of the second part of the predefined header (beginning at byte 10h in Configuration Space). • The encoding 00h specifies the non-bridge Configuration Space Header. • The encoding 01h specifies the PCI-to-PCI bridge Configuration Space Header. • The encoding 02h specifies the CardBus bridge Configuration Space Header. • All other encodings are reserved. Hardwired to 0 to identify the non-bridge Configuration Space Header.
15:8	0x0 RO	**Latency Timer (LT):** Not implemented. Hardwired to 0.
7:0	0x0 RO	**Cache Line Size (CLS):** Not implemented. Hardwired to 0.

54.6.5 IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 10h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 8B of IO space.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

54.6.6 IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 14h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

54.6.7 IDE Secondary Command Block IO BAR (IDE_HOST_SCMDIOBAR)—Offset 18h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 18h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 8B of IO space.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

54.6.8 IDE Secondary Control Block IO BAR (IDE_HOST_SCTLIOBAR)—Offset 1Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 1Ch

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

54.6.9 IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 20h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RW	**IO BAR (IOBAR):** Software programs this space with the base address of the device's IO region.
3:2	0x0 RO	**IO Size (IOSIZE):** Hardwired to 0 to indicate 16B of IO space.
1	0x0 RO	**Reserved (RSVD):** Hardwired to 0 for an IO BAR.
0	0x1 RO	**IO Space Indicator (IOSPACE):** Hardwired to 1 to identify an IO BAR.

54.6.10 Cardbus CIS Pointer (IDE_HOST_CCP)—Offset 28h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Cardbus CIS Pointer (CCP):** Not implemented. Hardwired to 0.

54.6.11 Subsystem ID and Subsystem Vendor ID (IDE_HOST_SID_SVID)—Offset 2Ch

These registers are used to uniquely identify the add-in card or subsystem where the PCI device resides. They provide a mechanism for add-in card vendors to distinguish their add-in cards from one another even though the add-in cards may have the same PCI controller on them (and, therefore, the same Vendor ID and Device ID).

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 2Ch

Default: 00008086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SID):** Value of this field is vendor-specific. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SID should have its own lock.
15:0	0x8086 RW/O	**Subsystem Vendor ID (SVID):** This field identifies the vendor of the add-in card or subsystem. This is written by BIOS. No hardware action will be taken on this value. Implementation Note: The Write-Once lock must be implemented per field. SVID should have its own lock.

54.6.12 Expansion ROM Base Address (IDE_HOST_XRBAR)—Offset 30h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Expansion ROM Base Address (XRBAR):** Not implemented. Hardwired to 0.

54.6.13 Capabilities List Pointer (IDE_HOST_CAPP)—Offset 34h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 34h

Default: 00000040h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):**
7:0	0x40 RO	**Capabilities Pointer (CAPP):** Indicates the pointer for the first entry in the capabilities list which is the MSI Capability.

54.6.14 Maximum Latency, Minimum Grant, Interrupt Pin and Interrupt Line (IDE_HOST_MAXL_MING_INTP_INTL)—Offset 3Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 3Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Maximum Latency (MAXL):** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Minimum Grant (MING):** Not implemented. Hardwired to 0.
15:8	0x0 RO/V	**Interrupt Pin (INTP):** This register specifies which interrupt pin IDE uses in PCI interrupt mode. Value Decoding • 00h The function does NOT use an interrupt pin. • 01h INTA • 02h INTB • 03h INTC • 04h INTD • 05h - FFh Reserved.
7:0	0x0 RW	**Interrupt Line (INTL):** This register is used to communicate interrupt line routing information. POST software will write the routing information into this register as it initializes and configures the system.

54.6.15 MSI Message Control, Next Pointer and Capability ID (IDE_HOST_MSIMC_MSINP_MSICID)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 40h

Default: 00805005h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**Reserved (RSVD):**
24	0x0 RO	**Per Vector Masking Capable (PVMC):** Not implemented. Hardwired to 0 to indicate the function does NOT support MSI per-vector masking.
23	0x1 RO	**64 bit address capable (XAC):** Hardwired to 1 to indicate the function is capable of sending a 64-bit message address.
22:20	0x0 RW	**Multiple Message Enable (MMEN):** Encoded number of interrupt vectors allocated by SW. This field is RW for software compatibility, but only one interrupt vector is ever sent by the function.
19:17	0x0 RO	**Multiple Message Capable (MMC):** Encoded number of interrupt vectors requested by a device. Hardwired to 0 to indicate one requested interrupt vector.
16	0x0 RW	**MSI Enable (MSIE):** If set, MSI interrupt delivery is enabled whereas pin-based interrupt delivery SHALL be disabled. If cleared, prior to returning the configuration write (that clears this field) completion, the function must send any pending MSI(s).
15:8	0x50 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 50h to point to the PM Capability list.
7:0	0x5 RO	**Capability ID (CID):** Hardwired to 05h to indicate the linked list item as the MSI Capability registers.

54.6.16 MSI Message Address (IDE_HOST_MSIMA)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RW	**Message Address (MA):** 32-bit DW-aligned MSI message address.
1:0	0x0 RO	**Reserved (RSVD):**

54.6.17 MSI Message Upper Address (IDE_HOST_MSIMUA)—Offset 48h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Message Upper Address (MUA):** Upper 32-bit of a 64-bit DW-aligned MSI message address.

54.6.18 MSI Message Data (IDE_HOST_MSIMD)—Offset 4Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):**
15:0	0x0 RW	**Message Data (MD):** MSI Message Data

54.6.19 Power Management Capabilities, Next Pointer and Capability ID (IDE_HOST_PMCAP_PMNP_PMCID)—Offset 50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 50h

Default: 00230001h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**PME Support (PMES):** This 5-bit field indicates the power states in which the function may assert PME#. A value of 0b for any bit indicates that the function is not capable of asserting the PME# signal while in that power state. • bit(27) X XXX1b - PME# can be asserted from D0 • bit(28) X XX1Xb - PME# can be asserted from D1 • bit(29) X X1XXb - PME# can be asserted from D2 • bit(30) X 1XXXb - PME# can be asserted from D3hot • bit(31) 1 XXXXb - PME# can be asserted from D3cold
26	0x0 RO	**D2 Support (D2S):** Hardwired to 0 to indicate that this device does not support D2.
25	0x0 RO	**D1 Support (D1S):** Hardwired to 0 to indicate that this device does not support D1.
24:22	0x0 RO	**Aux Current (AUXC):** Not implemented.Hardwired to 0.
21	0x1 RO	**Device Specific Initialization (DSI):** indicates whether special initialization of this function is required (beyond the standard PCI configuration header) before the generic class device driver is able to use it. A 1 indicates that the function requires a device specific initialization sequence following transition to the D0 uninitialized state. Hardwired to 1 to indicate Device Specific Initialization is required.
20	0x0 RO	**Reserved (RSVD):**
19	0x0 RO	**PME Clock (PMECLK):** Not implemented.Hardwired to 0.
18:16	0x3 RO	**Version (VER):** Hardwired to value of 011b indicates that this function complies with rev 1.2 of PCI Power Management Interface Spec.
15:8	0x0 RO	**Next Item Pointer (NP):** Indicates the pointer for the next entry in the capabilities list. Hardwired to 0 to indicate no more linked list item.
7:0	0x1 RO	**Capability ID (CID):** Hardwired to 01h to indicate the linked list item as the PCI Power Management registers.

54.6.20 Power Management Data, Control/Status Register Bridge Support Extensions, Control and Status (IDE_HOST_PMD_PMCSRBSE_PMCSR)—Offset 54h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + 54h

Default: 00000008h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Data:** Not implemented. Hardwired to 0.
23:16	0x0 RO	**Control/Status Register Bridge Support Extensions (CSRBSE):** Not implemented. Hardwired to 0.
15	0x0 RO	**PME Status (PMESTS):** This bit is set when the function would normally assert the PME signal independent of the state of the PME_En bit. • Writing a 1 to this bit will clear it and cause the function to stop asserting a PME (if enabled). • Writing a 0 has no effect. If the function supports PME from D3cold, then this bit is sticky and must be explicitly cleared by the operating system each time the operating system is initially loaded. Not implemented. Hardwired to 0.
14:13	0x0 RO	**Data Scale (DS):** Not implemented. Hardwired to 0.
12:9	0x0 RO	**Data Select (DSEL):** Not implemented. Hardwired to 0.
8	0x0 RO	**PME Enable (PMEEN):** A 1 enables the function to assert PME. When 0, PME assertion is disabled. This bit defaults to 0 if the function does not support PME generation from D3cold. If the function supports PME from D3cold then this bit is sticky and must be explicitly cleared by the operating system each time it is initially loaded. Not implemented. Hardwired to 0.
7:4	0x0 RO	**Reserved (RSVD1):**
3	0x1 RO	**No Soft Reset (NSR):** When set to 1, this bit indicates that devices transitioning from D3hot to D0 because of PowerState commands do not perform an internal reset. Configuration Context is preserved. Upon transition from the D3hot to the D0 Initialized state, no additional operating system intervention is required to preserve Configuration Context beyond writing the PowerState bits.
2	0x0 RO	**Reserved (RSVD0):**
1:0	0x0 RW	**Power State (PWRST):** This 2-bit field is used both to determine the current power state of a function and to set the function into a new power state. The definition of the field values is given below: • 00b - D0 • 01b - D1 • 10b - D2 • 11b - D3hot If software attempts to write an unsupported, optional state to this field, the write operation must complete normally on the bus; however, the data is discarded and no state change occurs.

54.6.21 Process Stepping Information (IDE_HOST_PSI)—Offset F8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:27, F:2] + F8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
27:24	0x0 RO/V	**Dot Portion of Process ID (DPOP):** Reserved.
23:16	0x0 RO/V	**Manufacturing Stepping (MSID):** Reserved.
15:8	0x0 RO/V	**Manufacturing ID (MID):** Reserved.
7:0	0x0 RO/V	**Process Portion of Process ID (PPOP):** Reserved.

54.7 Registers in Memory Space—HECI1_MMIO_MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) HECI1_MMIO_MBAR_LO described in Section 54.2.9, "HECI MMIO Base Address Low (HECI1_MMIO_MBAR_LO)—Offset 10h" on page 2458 and HECI1_MMIO_MBAR_HI described in Section 54.2.10, "HECI MMIO Base Address High (HECI1_MMIO_MBAR_HI)—Offset 14h" on page 2459.

54.7.1 Host CB Write Window (HECI1_H_CB_WW)—Offset 0h

This register is for host to write into its Circular Buffer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI1_MMIO_MBAR] + 0h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:27, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Host Circular Buffer Write Window Field (H_CB_WWF):** This field is for host to write into its circular buffer. This field is write only, reads will return arbitrary data. Writes to this register will increment the H_CBWP as long as CSE_RDY is 1. When CSE_RDY is 0, writes to this register have no effect and are not delivered to the H_CB, nor is H_CBWP incremented.

54.7.2 Host Control and Status Register (HECI1_H_CSR)—Offset 4h

This register reports status information about the host circular buffer (H_CB) and allows host software to control interrupt generation.

Note to software: reserved bits in this register must be set to 0 whenever this register is written.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + 4h

Default: 80000000h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:27, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**Host Circular Buffer Depth (H_CBD):** This field indicates the maximum number of 32 bit entries available in the host circular buffer (H_CB). Host software uses this field along with the H_CBRP and H_CBWP fields to calculate the number of valid entries in the H_CB to read or number of entries available for write. Programmers note: This field is implemented with a '1-hot' scheme. Only one bit will be set to a '1' at a time. Each bit position represents the value n of a buffer depth of (2^n). For example, when bit# 1 is 1, the buffer depth is 2; when bit#2 is 1, the buffer depth is 4, etc. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**Host CB Write Pointer (H_CBWP):** Points to next location in the H_CB for host to write the data. Software uses this field along with H_CBRP and H_CBD fields to calculate the number of valid entries in the H_CB to read or number of entries available for write.
15:8	0x0 RO/V	**Host CB Read Pointer (H_CBRP):** Points to next location in the H_CB where a valid data is available for embedded controller to read. Software uses this field along with H_CBWR and H_CBD fields to calculate the number of valid entries in the host CB to read or number of entries available for write.
7	0x0 RO	**Reserved (RSVD_7_7):** Reserved.
6	0x0 RW/1C/V	**Host D0I3 Interrupt Status (H_D0I3C_IS):** HW sets this bit to 1 when D0I3C.H_D0I3_IR is set and D0I3C.H_D0I3_CIP transitions from 1 to 0. Host clears this bit to 0 by writing a 1 to this bit position. H_D0I3C_IE has no effect on this bit.
5	0x0 RW	**Host D0I3 Interrupt Enable (H_D0I3C_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_D0I3C_IS is set to 1.
4	0x0 RW	**Host Reset (H_RST):** Setting this bit to 1 will initiate the HECI reset sequence to get the circular buffers into a known good state for host and CSE communication. When this bit transitions from 0 to 1, hardware will clear the H_RDY and CSE_RDY bits.
3	0x0 RW/V	**Host Ready (H_RDY):** This bit indicates that the host is ready to process messages.
2	0x0 RW/V	**Host Interrupt Generate (H_IG):** Once message(s) are written into its CB, the host sets this bit to one for the HW to set the CSE_IS bit in the CSE_CSR and to generate an interrupt message to mIA. HW then clears this bit to 0.
1	0x0 RW/1C/V	**Host Interrupt Status (H_IS):** HW sets this bit to 1 when CSE_IG bit is set to 1. Host clears this bit to 0 by writing a 1 to this bit position. H_IE has no effect on this bit.
0	0x0 RW	**Host Interrupt Enable (H_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_IS is set to 1.

54.7.3 CSE Circular Buffer Read Window (HECI1_CSE_CB_RW)—Offset 8h

This register is for host to read from the CSE Circular Buffer (CSE_CB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + 8h

Default: FFFFFFFFh

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:27, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO	**CSE Circular Buffer Read Window Field (CSE_CB_RWF):** This bit field is for host to read from the CSE Circular Buffer. This field is read only, writes have no effect. Reads to this register will increment the CSE_CBRP as long as CSE_RDY is 1. When CSE_RDY is 0, reads to this register have no effect, all 1s are returned, and CSE_CBRP is not incremented.

54.7.4 CSE Control and Status Register Host Access (HECI1_CSE_CSR_HA)—Offset Ch

This register allows host software to read the CSE Control Status register (CSE_CSR).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + Ch

Default: 80000000h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:27, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**CSE Circular Buffer Depth Host Read Access (CSE_CBD_HRA):** Host read access to CSE_CBD. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**CSE CB Write Pointer Host Read Access (CSE_CBWP_HRA):** Host read only access to CSE_CBWP.
15:8	0x0 RO/V	**CSE CB Read Pointer Host Read Access (CSE_CBRP_HRA):** Host read only access to CSE_CBRP.
7	0x0 RO/V	**NMI Status Host Read Access (NMI_STS_HRA):** Host read access to NMI_STS.
6	0x0 RO	**Reserved (RSVD_6_6):** Reserved.
5	0x0 RO/V	**Pointer Reset Host Read Access (PTR_RST_HRA):** Host read access to PTR_RST.
4	0x0 RO/V	**CSE Reset Host Read Access (CSE_RST_HRA):** Host read access to CSE_RST.
3	0x0 RO/V	**CSE Ready Host Read Access (CSE_RDY_HRA):** Host read access to CSE_RDY.
2	0x0 RO/V	**CSE Interrupt Generate Host Read Access (CSE_IG_HRA):** Host read only access to CSE_IG.
1	0x0 RO/V	**CSE Interrupt Status Host Read Access (CSE_IS_HRA):** Host read only access to CSE_IS.
0	0x0 RO/V	**CSE Interrupt Enable Host Read Access (CSE_IE_HRA):** Host read only access to CSE_IE.

54.7.5 D0i3 Control (HECI1_D0I3C)—Offset 800h

This register allows host to configure the power mode using D0i0/D0i3 support.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI1_MMIO_MBAR] + 800h

Default: 00000000h

HECI1_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI1_MMIO_MBAR Reference: [B:0, D:27, F:0] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3	0x0 RO	**Restore Required (H_D0I3C_RR):** When this bit is set (by HW), SW must restore the state of the IP. This bit is cleared by SW writing a 1. **In CSE this bit is never set so it does not need to be cleared by SW.**
2	0x0 RW	**D0i3 (H_D0I3C_I3):** SW sets this bit to 1 in order to move the IP into the D0i3 state. Clearing this bit will return the IP into the fully active D0 state (D0i0). When this bit changes state, mIA may be interrupted (see H_PCI_CSR.D0I3C_IS register's description)
1	0x0 RW	**Interrupt Request (H_D0I3C_IR):** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this bit on each write to this register. When this bit is set to 1, Command-in-Progress deassertion is captured in H_CSR.H_D0I3_IS. If H_CSR.H_D0I3_IE is 1 as well, host interrupt will be initiated.
0	0x0 RO/V	**Command-in-Progress (H_D0I3C_CIP):** HW sets this bit on a 0-)1 or 1-)0 transition of D0i3 bit (bit [2]). While set, the other bits in this register are not valid and it is illegal for SW to write to any of them. While clear, all other bits in this register are valid and SW may write to them. If Interrupt Request (bit [1]) was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles a particular interrupt is not visible to HW. SW writes to this bit have no effect. This bit is auto-cleared by HW one cycle after it is set.

54.8 Registers in Memory Space—HECI2_MMIO_MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) HECI2_MMIO_MBAR_LO described in Section 54.3.9, "HECI MMIO Base Address Low (HECI2_MMIO_MBAR_LO)—Offset 10h" on page 2478 and HECI2_MMIO_MBAR_HI described in Section 54.3.10, "HECI MMIO Base Address High (HECI2_MMIO_MBAR_HI)—Offset 14h" on page 2479.

54.8.1 Host CB Write Window (HECI2_H_CB_WW)—Offset 0h

This register is for host to write into its Circular Buffer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI2_MMIO_MBAR] + 0h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:27, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Host Circular Buffer Write Window Field (H_CB_WWF):** This field is for host to write into its circular buffer. This field is write only, reads will return arbitrary data. Writes to this register will increment the H_CBWP as long as CSE_RDY is 1. When CSE_RDY is 0, writes to this register have no effect and are not delivered to the H_CB, nor is H_CBWP incremented.

54.8.2 Host Control and Status Register (HECI2_H_CSR)—Offset 4h

This register reports status information about the host circular buffer (H_CB) and allows host software to control interrupt generation.

Note to software: reserved bits in this register must be set to 0 whenever this register is written.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI2_MMIO_MBAR] + 4h

Default: 80000000h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:27, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**Host Circular Buffer Depth (H_CBD):** This field indicates the maximum number of 32 bit entries available in the host circular buffer (H_CB). Host software uses this field along with the H_CBRP and H_CBWP fields to calculate the number of valid entries in the H_CB to read or number of entries available for write. Programmers note: This field is implemented with a '1-hot' scheme. Only one bit will be set to a '1' at a time. Each bit position represents the value n of a buffer depth of (2^n). For example, when bit# 1 is 1, the buffer depth is 2; when bit#2 is 1, the buffer depth is 4, etc. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**Host CB Write Pointer (H_CBWP):** Points to next location in the H_CB for host to write the data. Software uses this field along with H_CBRP and H_CBD fields to calculate the number of valid entries in the H_CB to read or number of entries available for write.
15:8	0x0 RO/V	**Host CB Read Pointer (H_CBRP):** Points to next location in the H_CB where a valid data is available for embedded controller to read. Software uses this field along with H_CBWR and H_CBD fields to calculate the number of valid entries in the host CB to read or number of entries available for write.
7	0x0 RO	**Reserved (RSVD_7_7):** Reserved.
6	0x0 RW/1C/V	**Host D0I3 Interrupt Status (H_D0I3C_IS):** HW sets this bit to 1 when D0I3C.H_D0I3_IR is set and D0I3C.H_D0I3_CIP transitions from 1 to 0. Host clears this bit to 0 by writing a 1 to this bit position. H_D0I3C_IE has no effect on this bit.
5	0x0 RW	**Host D0I3 Interrupt Enable (H_D0I3C_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_D0I3C_IS is set to 1.
4	0x0 RW	**Host Reset (H_RST):** Setting this bit to 1 will initiate the HECI reset sequence to get the circular buffers into a known good state for host and CSE communication. When this bit transitions from 0 to 1, hardware will clear the H_RDY and CSE_RDY bits.
3	0x0 RW/V	**Host Ready (H_RDY):** This bit indicates that the host is ready to process messages.
2	0x0 RW/V	**Host Interrupt Generate (H_IG):** Once message(s) are written into its CB, the host sets this bit to one for the HW to set the CSE_IS bit in the CSE_CSR and to generate an interrupt message to mIA. HW then clears this bit to 0.
1	0x0 RW/1C/V	**Host Interrupt Status (H_IS):** HW sets this bit to 1 when CSE_IG bit is set to 1. Host clears this bit to 0 by writing a 1 to this bit position. H_IE has no effect on this bit.
0	0x0 RW	**Host Interrupt Enable (H_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_IS is set to 1.

54.8.3 CSE Circular Buffer Read Window (HECI2_CSE_CB_RW)—Offset 8h

This register is for host to read from the CSE Circular Buffer (CSE_CB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI2_MMIO_MBAR] + 8h

Default: FFFFFFFFh

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:27, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO	**CSE Circular Buffer Read Window Field (CSE_CB_RWF):** This bit field is for host to read from the CSE Circular Buffer. This field is read only, writes have no effect. Reads to this register will increment the CSE_CBRP as long as CSE_RDY is 1. When CSE_RDY is 0, reads to this register have no effect, all 1s are returned, and CSE_CBRP is not incremented.

54.8.4 CSE Control and Status Register Host Access (HECI2_CSE_CSR_HA)—Offset Ch

This register allows host software to read the CSE Control Status register (CSE_CSR).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI2_MMIO_MBAR] + Ch

Default: 80000000h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:27, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**CSE Circular Buffer Depth Host Read Access (CSE_CBD_HRA):** Host read access to CSE_CBD. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**CSE CB Write Pointer Host Read Access (CSE_CBWP_HRA):** Host read only access to CSE_CBWP.
15:8	0x0 RO/V	**CSE CB Read Pointer Host Read Access (CSE_CBRP_HRA):** Host read only access to CSE_CBRP.
7	0x0 RO/V	**NMI Status Host Read Access (NMI_STS_HRA):** Host read access to NMI_STS.
6	0x0 RO	**Reserved (RSVD_6_6):** Reserved.
5	0x0 RO/V	**Pointer Reset Host Read Access (PTR_RST_HRA):** Host read access to PTR_RST.
4	0x0 RO/V	**CSE Reset Host Read Access (CSE_RST_HRA):** Host read access to CSE_RST.
3	0x0 RO/V	**CSE Ready Host Read Access (CSE_RDY_HRA):** Host read access to CSE_RDY.
2	0x0 RO/V	**CSE Interrupt Generate Host Read Access (CSE_IG_HRA):** Host read only access to CSE_IG.
1	0x0 RO/V	**CSE Interrupt Status Host Read Access (CSE_IS_HRA):** Host read only access to CSE_IS.
0	0x0 RO/V	**CSE Interrupt Enable Host Read Access (CSE_IE_HRA):** Host read only access to CSE_IE.

54.8.5 D0i3 Control (HECI2_D0I3C)—Offset 800h

This register allows host to configure the power mode using D0i0/D0i3 support.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI2_MMIO_MBAR] + 800h

HECI2_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI2_MMIO_MBAR Reference: [B:0, D:27, F:1] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3	0x0 RO	**Restore Required (H_D0I3C_RR):** When this bit is set (by HW), SW must restore the state of the IP. This bit is cleared by SW writing a 1. **In CSE this bit is never set so it does not need to be cleared by SW.**
2	0x0 RW	**D0i3 (H_D0I3C_I3):** SW sets this bit to 1 in order to move the IP into the D0i3 state. Clearing this bit will return the IP into the fully active D0 state (D0i0). When this bit changes state, mIA may be interrupted (see H_PCI_CSR.D0I3C_IS register's description)
1	0x0 RW	**Interrupt Request (H_D0I3C_IR):** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this bit on each write to this register. When this bit is set to 1, Command-in-Progress deassertion is captured in H_CSR.H_D0I3_IS. If H_CSR.H_D0I3_IE is 1 as well, host interrupt will be initiated.
0	0x0 RO/V	**Command-in-Progress (H_D0I3C_CIP):** HW sets this bit on a 0-)1 or 1-)0 transition of D0i3 bit (bit [2]). While set, the other bits in this register are not valid and it is illegal for SW to write to any of them. While clear, all other bits in this register are valid and SW may write to them. If Interrupt Request (bit [1]) was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles a particular interrupt is not visible to HW. SW writes to this bit have no effect. This bit is auto-cleared by HW one cycle after it is set.

54.9 Registers in Memory Space—HECI3_MMIO_MBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) HECI3_MMIO_MBAR_LO described in Section 54.4.9, "HECI MMIO Base Address Low (HECI3_MMIO_MBAR_LO)—Offset 10h" on page 2495 and HECI3_MMIO_MBAR_HI described in Section 54.4.10, "HECI MMIO Base Address High (HECI3_MMIO_MBAR_HI)—Offset 14h" on page 2496.

54.9.1 Host CB Write Window (HECI3_H_CB_WW)—Offset 0h

This register is for host to write into its Circular Buffer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI3_MMIO_MBAR] + 0h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:27, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**Host Circular Buffer Write Window Field (H_CB_WWF):** This field is for host to write into its circular buffer. This field is write only, reads will return arbitrary data. Writes to this register will increment the H_CBWP as long as CSE_RDY is 1. When CSE_RDY is 0, writes to this register have no effect and are not delivered to the H_CB, nor is H_CBWP incremented.

54.9.2 Host Control and Status Register (HECI3_H_CSR)—Offset 4h

This register reports status information about the host circular buffer (H_CB) and allows host software to control interrupt generation.

Note to software: reserved bits in this register must be set to 0 whenever this register is written.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI3_MMIO_MBAR] + 4h

Default: 80000000h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:27, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**Host Circular Buffer Depth (H_CBD):** This field indicates the maximum number of 32 bit entries available in the host circular buffer (H_CB). Host software uses this field along with the H_CBRP and H_CBWP fields to calculate the number of valid entries in the H_CB to read or number of entries available for write. Programmers note: This field is implemented with a '1-hot' scheme. Only one bit will be set to a '1' at a time. Each bit position represents the value n of a buffer depth of (2^n). For example, when bit# 1 is 1, the buffer depth is 2; when bit#2 is 1, the buffer depth is 4, etc. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**Host CB Write Pointer (H_CBWP):** Points to next location in the H_CB for host to write the data. Software uses this field along with H_CBRP and H_CBD fields to calculate the number of valid entries in the H_CB to read or number of entries available for write.
15:8	0x0 RO/V	**Host CB Read Pointer (H_CBRP):** Points to next location in the H_CB where a valid data is available for embedded controller to read. Software uses this field along with H_CBWR and H_CBD fields to calculate the number of valid entries in the host CB to read or number of entries available for write.
7	0x0 RO	**Reserved (RSVD_7_7):** Reserved.
6	0x0 RW/1C/V	**Host D0I3 Interrupt Status (H_D0I3C_IS):** HW sets this bit to 1 when D0I3C.H_D0I3_IR is set and D0I3C.H_D0I3_CIP transitions from 1 to 0. Host clears this bit to 0 by writing a 1 to this bit position. H_D0I3C_IE has no effect on this bit.
5	0x0 RW	**Host D0I3 Interrupt Enable (H_D0I3C_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_D0I3C_IS is set to 1.
4	0x0 RW	**Host Reset (H_RST):** Setting this bit to 1 will initiate the HECI reset sequence to get the circular buffers into a known good state for host and CSE communication. When this bit transitions from 0 to 1, hardware will clear the H_RDY and CSE_RDY bits.
3	0x0 RW/V	**Host Ready (H_RDY):** This bit indicates that the host is ready to process messages.
2	0x0 RW/V	**Host Interrupt Generate (H_IG):** Once message(s) are written into its CB, the host sets this bit to one for the HW to set the CSE_IS bit in the CSE_CSR and to generate an interrupt message to mIA. HW then clears this bit to 0.
1	0x0 RW/1C/V	**Host Interrupt Status (H_IS):** HW sets this bit to 1 when CSE_IG bit is set to 1. Host clears this bit to 0 by writing a 1 to this bit position. H_IE has no effect on this bit.
0	0x0 RW	**Host Interrupt Enable (H_IE):** Host sets this bit to 1 to enable the host interrupt (MSI, INTx, SMI or SCI) to be asserted when H_IS is set to 1.

54.9.3 CSE Circular Buffer Read Window (HECI3_CSE_CB_RW)—Offset 8h

This register is for host to read from the CSE Circular Buffer (CSE_CB).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI3_MMIO_MBAR] + 8h

Default: FFFFFFFFh

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:27, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xffffffff RO	**CSE Circular Buffer Read Window Field (CSE_CB_RWF):** This bit field is for host to read from the CSE Circular Buffer. This field is read only, writes have no effect. Reads to this register will increment the CSE_CBRP as long as CSE_RDY is 1. When CSE_RDY is 0, reads to this register have no effect, all 1s are returned, and CSE_CBRP is not incremented.

54.9.4 CSE Control and Status Register Host Access (HECI3_CSE_CSR_HA)—Offset Ch

This register allows host software to read the CSE Control Status register (CSE_CSR).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [HECI3_MMIO_MBAR] + Ch

Default: 80000000h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:27, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x80 RO	**CSE Circular Buffer Depth Host Read Access (CSE_CBD_HRA):** Host read access to CSE_CBD. **This field is hardwired to represent a depth of 128 entries.**
23:16	0x0 RO/V	**CSE CB Write Pointer Host Read Access (CSE_CBWP_HRA):** Host read only access to CSE_CBWP.
15:8	0x0 RO/V	**CSE CB Read Pointer Host Read Access (CSE_CBRP_HRA):** Host read only access to CSE_CBRP.
7	0x0 RO/V	**NMI Status Host Read Access (NMI_STS_HRA):** Host read access to NMI_STS.
6	0x0 RO	**Reserved (RSVD_6_6):** Reserved.
5	0x0 RO/V	**Pointer Reset Host Read Access (PTR_RST_HRA):** Host read access to PTR_RST.
4	0x0 RO/V	**CSE Reset Host Read Access (CSE_RST_HRA):** Host read access to CSE_RST.
3	0x0 RO/V	**CSE Ready Host Read Access (CSE_RDY_HRA):** Host read access to CSE_RDY.
2	0x0 RO/V	**CSE Interrupt Generate Host Read Access (CSE_IG_HRA):** Host read only access to CSE_IG.
1	0x0 RO/V	**CSE Interrupt Status Host Read Access (CSE_IS_HRA):** Host read only access to CSE_IS.
0	0x0 RO/V	**CSE Interrupt Enable Host Read Access (CSE_IE_HRA):** Host read only access to CSE_IE.

54.9.5 D0i3 Control (HECI3_D0I3C)—Offset 800h

This register allows host to configure the power mode using D0i0/D0i3 support.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [HECI3_MMIO_MBAR] + 800h

HECI3_MMIO_MBAR Type: PCI Configuration Register (Size: 64 bits)
HECI3_MMIO_MBAR Reference: [B:0, D:27, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3	0x0 RO	**Restore Required (H_D0I3C_RR):** When this bit is set (by HW), SW must restore the state of the IP. This bit is cleared by SW writing a 1. **In CSE this bit is never set so it does not need to be cleared by SW.**
2	0x0 RW	**D0i3 (H_D0I3C_I3):** SW sets this bit to 1 in order to move the IP into the D0i3 state. Clearing this bit will return the IP into the fully active D0 state (D0i0). When this bit changes state, mIA may be interrupted (see H_PCI_CSR.D0I3C_IS register's description)
1	0x0 RW	**Interrupt Request (H_D0I3C_IR):** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this bit on each write to this register. When this bit is set to 1, Command-in-Progress deassertion is captured in H_CSR.H_D0I3_IS. If H_CSR.H_D0I3_IE is 1 as well, host interrupt will be initiated.
0	0x0 RO/V	**Command-in-Progress (H_D0I3C_CIP):** HW sets this bit on a 0-)1 or 1-)0 transition of D0i3 bit (bit [2]). While set, the other bits in this register are not valid and it is illegal for SW to write to any of them. While clear, all other bits in this register are valid and SW may write to them. If Interrupt Request (bit [1]) was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles a particular interrupt is not visible to HW. SW writes to this bit have no effect. This bit is auto-cleared by HW one cycle after it is set.

54.10 Registers in Memory Space—KT_HOST_MEMBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) KT_HOST_MEMBAR described in Section 54.5.6, "KT Memory BAR (KT_HOST_MEMBAR)—Offset 14h" on page 2513.

54.10.1 KT Receive Buffer Register (MEM_KTRBR)—Offset 0h

This register implements the standard Receiver Buffer register in the KT Block. This is read-only. DLAB(i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be read when the receiver data is ready. In FIFO mode, a read from this register will be translated into a read from the RBR FIFO. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 0h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Receiver Buffer Register (RBR):** Implements the Receiver Buffer register of the Serial Interface.

54.10.2 KT Transmitter Holding Register (MEM_KTTHR)—Offset 0h

This register implements the standard Transmitter Holding register in the KT Block. This is write-only. DLAB(i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be written when the Host needs to transmit data. In FIFO mode, a write to this register will be translated into a write to the THR FIFO. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 0h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**Transmitter Holding Register (THR):** Implements the Transmit Data register of the Serial Interface.

54.10.3 KT Divisor Latch LSB Register (MEM_KTDLLR)—Offset 0h

This register implements the standard DLL register in the KT Block. DLAB(i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. this register is supported only for SW compatibility and has no impact on HW performance. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 0h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch LSB (DLL):** Implements the DLL register of the Serial Interface.

54.10.4 KT Interrupt Enable register (MEM_KTIER)—Offset 1h

This register implements the standard Interrupt Enable register in the KT Block. The bits enable specific events to interrupt the Host. See bit specific definition below. DLAB(i.e. KTLCR[7]) shall is 0 in order for this register to be accessed. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 1h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RW	**MSR (IER3):** When set, enables bits in Modem Status register to cause an interrupt to the Host
2	0x0 RW	**LSR (IER2):** When set, enables bits in Receiver Line Status Register to cause an interrupt to the Host
1	0x0 RW	**THR (IER1):** When set, enables an interrupt to the Host when the Transmitter Holding register is empty.
0	0x0 RW	**DR (IER0):** When set, enables an interrupt to the Host when the Received Data is available OR Receiver FIFO timeout.

54.10.5 KT Divisor Latch MSB Register (MEM_KTDLMR)—Offset 1h

This register implements the standard DLM register in the KT Block. DLAB(i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. This register is supported only for SW compatibility and has no impact on HW performance. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 1h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch MSB (DLM):** Implements the DLM register of the Serial Interface.

54.10.6 KT Interrupt Identification Register (MEM_KTIIR)—Offset 2h

This register implements the standard Interrupt Identification register in the KT Block. This is read-only. This register is created to provide minimum software overhead during data character transfers. The register prioritizes KT interrupts into 4 levels and records them in the IIRSTS field of this register. The four levels of interrupt conditions in order of priority are: Receiver Line Status; Received Data Ready/Character Timeout Indication; Transmitter Holding Register Empty; MODEM Status. When the Host accesses the IIR, the HW freezes all interrupts and indicates the highest priority pending interrupt to the Host. While this Host access is occurring, the HW records new interrupts, but does not change its current indication until the access is complete. Table in the Host Interrupt Generation section shows the contents. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 2h

Default: 01h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**FIFO Enable (FIEN1):** This field is connected by HW to the FIFO Enable field of the FCR register.
6	0x0 RO/V	**FIFO Enable (FIEN0):** This field is connected by HW to the FIFO Enable field of the FCR register.
5:4	0x0 RO	**Reserved (RSVD):** Hardwired to 0.
3:1	0x0 RO/V	**IIR Status (IIRSTS):** These bits are asserted by the HW according to the source of the interrupt and the priority level. Refer to the section on Host Interrupt Generation for a table of values.
0	0x1 RO/V	**Interrupt Status (INTSTS):** • 0: indicates a pending Host interrupt and IIRSTS may be used as a pointer to the appropriate interrupt service routine. It reflects the logical-NOR of all UART interrupts. An individual UART interrupt will be identified as pending when the individual event status is asserted AND its corresponding event interrupt enable is asserted as well. For example, the THR Empty interrupt will be identified as pending when both LSR[THRE] bit is 1 AND IER[IER1] is 1. • 1: indicates no pending Host interrupt.

54.10.7 KT FIFO Control register (MEM_KTFCR)—Offset 2h

This register implements the standard FIFO Control register in the KT Block. It is used to configure features pertinent to the FIFO mode of operation. This is write-only. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 2h

Default: 00h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 WO	**Receiver Trigger Level (RTL):** Trigger level in bytes for the Receiver FIFO. Once the trigger level number of bytes is reached, an interrupt will be sent to the Host [7:6] RCVR FIFO Trigger Level (bytes) • 00 -- 01 • 01 -- 04 • 10 -- 08 • 11 -- 14
5:4	0x0 WO	**Reserved (RSVD):** Writes to this field shall be dropped.
3	0x0 WO	**RDY Mode (RDYM):** This bit has no effect on HW performance.
2	0x0 WO	**XMT FIFO Clear (XFIC):** When the Host writes one to this bit the HW will clear the XMT FIFO. This bit is self-cleared by HW.
1	0x0 WO	**RCV FIFO Clear (RFIC):** When the Host writes one to this bit the HW will clear the RCV FIFO. This bit is self-cleared by HW.
0	0x0 WO	**FIFO Enable (FIE):** When set indicates that the KT interface is working in FIFO node. When this bit value is changed the RCV and XMT FIFO are cleared by HW. This bit must be a 1 when other FCR bits are written to or they will NOT be programmed.

54.10.8 KT Line Control register (MEM_KTLCR)—Offset 3h

This register implements the standard Line Control register in the KT Block. It specifies the format of the asynchronous data communications exchange and sets the DLAB bit. Most bits in this register have no effect on HW and are only used by the FW. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 3h

Default: 03h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Divisor Latch Access Bit (DLAB):** • 1: Allows access to the Divisor Latch Registers and reading of the FIFO Control Register. • 0: Allows access to RBR, THR, IER and IIR registers.
6	0x0 RW	**Break Control (BC):** This bit has no effect on HW.
5:4	0x0 RW	**Parity Bit Mode (PBM):** This bit has no effect on HW.
3	0x0 RW	**Parity Enable (PE):** This bit has no effect on HW.
2	0x0 RW	**Stop Bit Select (SBS):** This bit has no effect on HW.
1:0	0x3 RW	**Word Select Byte (WSB):** This bit has no effect on HW.

54.10.9 KT Modem Control register (MEM_KTMCR)—Offset 4h

This register implements the standard Modem Control register in the KT Block. It controls the interface with the modem. Because the FW emulates the modem, the Host communicates with the FW via this register. This register has impact on the HW in the loopback mode. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 4h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved.
4	0x0 RW	**Loop Back Mode (LBM):** When set by Host indicates that the serial port is in loop Back mode. This means that the data that is transmitted by the host should be received. Helps in debug of the interface
3	0x0 RW	**Output 2 (OUT2):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit (7).
2	0x0 RW	**Output 1 (OUT1):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit(6).
1	0x0 RW	**Request to Send Out (RTSO):** This bit has no effect on HW in normal mode. In loopback mode, the value of this bit is written by HW to Modem Status Register bit(4).
0	0x0 RW	**Data Terminal Ready Out (DRTO):** This bit has no effect on HW in normal mode. In loopback mode, the value in this bit is written by HW to Modem Status Register Bit(5).

54.10.10 KT Line Status register (MEM_KTLSR)—Offset 5h

This register implements the standard Line Status register in the KT Block. It provides status information of the data transfer to the Host. Error indication etc are provided by the HW/FW to the host via this register. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [KT_HOST_MEMBAR] + 5h

Default: 60h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/C/V	**RCVR FIFO Error (RXFER):** This bit is cleared in non FIFO mode. This bit is connected to UART LSR[BI] bit in FIFO mode.
6	0x1 RO/V	**Transmitter Empty (TEMT):** In non-FIFO mode: This bit will be set to 1 whenever the Transmitter Holding Register (THR) and the Transmitter Shift Register (TSR) are both empty, OR cleared to 0 whenever either THR or TSR contains a data byte. In FIFO mode: This bit will be set to 1 whenever XMIT FIFO and TSR are both empty, OR cleared to 0 whenever either XMIT FIFO or TSR contains a data byte. Implementation note: This bit is connected by HW to THRE bit
5	0x1 RO/V	**Transmitter Holding Register Empty (THRE):** The bit will always be set whenever Host changes UART FCR[FIE] bit. This bit is controlled differently in FIFO vs non-FIFO modes: Non-FIFO mode: This bit will be cleared by HW when Host writes to THR, and set by HW when FW reads from THR. FIFO mode: This bit will be set by HW when XMIT FIFO is empty , and cleared by HW when XMIT FIFO is NOT empty.
4	0x0 RO/C/V	**Break Interrupt (BI):** This bit will be cleared by HW when the UART LSR register is read by Host. This bit will be set by HW in two cases: In FIFO mode, when FW sets the KTRIVR[SBI] bit. In non-FIFO mode, when FW sets the KTRBR[BIA] bit.
3	0x0 RO	**Framing Error (FE):** This bit is NOT implemented and hardwired to 0.
2	0x0 RO	**Parity Error (PE):** This bit is NOT implemented and hardwired to 0.
1	0x0 RO/C/V	**Overrun Error (OE):** HW will clear this bit when Host reads from KTLSR register and this is source of interrupt. HW will set this bit when overrun error is detected. In non-FIFO mode, the character that triggers the overrun error shall overwrite the character in the RBR register. In FIFO mode, the character that triggers the overrun error shall be dropped without corrupting the RCVR FIFO.
0	0x0 RO/V	**Data Ready (DR):** Non-FIFO Mode: This bit will be set by HW when FW writes to RBR and cleared by HW when Host reads from RBR. FIFO Mode: The bit will be set by HW when RCVR FIFO is not empty and cleared by HW when RCVR FIFO is empty.

54.10.11 KT Modem Status register (MEM_KTMSR)—Offset 6h

This register implements the standard Modem Status register in the KT Block. It provides the current state of the control lines from the modem. The modem functionality is emulated by the FW. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 6h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Data Carrier Detect (DCD):** In Loop Back mode this bit is connected by HW to the value of MCR bit 3
6	0x0 RO	**Ring Indicator (RI):** In Loop Back mode this bit is connected by HW to the value of MCR bit 2.
5	0x0 RO	**Data Set Ready (DSR):** In Loop Back mode this bit is connected by HW to the value of MCR bit 0.
4	0x0 RO	**Clear To Send (CTS):** In Loop Back mode this bit is connected by HW to the value of MCR bit 1.
3	0x0 RO/C/V	**Delta Data Carrier Detect (DDCD):** This bit is set when bit 7 is changed. This bit is cleared by HW when the MSR register is being read by the HOST driver.
2	0x0 RO/C/V	**Trailing Edge of Read Detector (TERI):** This bit is set when bit 6 is changed from 1 to 0. This bit is cleared by HW when the MSR register is being read by the Host driver.
1	0x0 RO/C/V	**Delta Data Set Ready (DDSR):** This bit is set when bit 5 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver.
0	0x0 RO/C/V	**Delta Clear To Send (DCTS):** This bit is set when bit 4 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver.

54.10.12 KT Scratch register (MEM_KTSCR)—Offset 7h

This register implements the standard Scratch register in the KT Block. It allows Host SW programmers to hold temporary data. It has NO effect on HW. Reset condition: Host reset. Non-sticky.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_MEMBAR] + 7h

KT_HOST_MEMBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_MEMBAR Reference: [B:0, D:27, F:3] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Scratch Register Data (SCRD):** Reserved.

54.11 Registers in Memory Space—Fixed Address

These registers are accessed in Host Memory Space through fixed memory addresses.

54.11.1 FTPM Locality State (HOST_LOC_0_LOC_STATE_HROA)—Offset FED40000h

Reads by host SW from this register will reflect the value of FTPM_LOC_STATE register in mIA space. This register is aliased to the following addresses in the host address space: FED4_x000, x=0,1,2,3,4. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40000h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO/V	**Reserved (RSVD_31_8):** Opaque to HW. Defined by FW.
7	0x0 RO/V	**Register Valid Status (FTPM_REG_VALID_STS):** Opaque to HW. This bit is used by FW to signal to host SW when this register is valid.
6:5	0x0 RO/V	**Reserved (RSVD_6_5):** Opaque to HW. Defined by FW.
4:2	0x0 RO/V	**Active Locality (FTPM_ACTV_LOC):** The encodings are: • 000 - Locality 0, • 001 - Locality 1, • 010 - Locality 2, • 011 - Locality 3, • 100 - Locality 4, • 101 and 111 - reserved. FW sets these bits to mux in the active locality. Once set, the FTPM HCI will pass cycles from the active host locality to the FTPM shared SRAM. Writes from in-active localities will be dropped and reads will return 0's.
1	0x0 RO/V	**Locality Assigned (FTPM_LOC_ASSIGNED):** A value of 0 indicates to host SW that no locality is assigned, a value of 1 indicates a locality has been assigned.
0	0x0 RO/V	**Establishment (FTPM_ESTABLISHMENT):** Opaque to HW. This bit is set to 0 by FW when HASH_START occurs and set to 1 when the RESET_ESTABLISHMENT bit is set.

54.11.2 FTPM Locality Reserved (HOST_LOC_0_LOC_RSVD)—Offset FED40004h

This register was added in order to support QW reads from Locality State register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40004h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Reserved (FTPM_LOC_RSVD_BITS):** Reserved.

54.11.3 FTPM Locality n Control Register (HOST_LOC_0_LOC_CTRL)—Offset FED40008h

Writes by host SW to this register will update the value of the corresponding LOC_n_CTRL_CSEROA register in mIA space. Writes by host SW to this register may be configured by CSE FW to trigger an MSI/PME to mIA. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40008h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 WO	**FTPM Locality n Control Bits (FTPM_LOC_CTRL_BITS):** Reserved.

54.11.4 FTPM Locality n Status Register Host Read Only Access. (HOST_LOC_0_LOC_STS_HROA)—Offset FED4000Ch

Reads by host SW from this register will reflect the value of the corresponding LOC_n_STS register in mIA space. This register is opaque to HW. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4000Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**FTPM Locality n Status Bits (FTPM_LOC_STS_BITS):** Reserved.

54.11.5 FTPM Locality Config Area Reserved Read Write[0-7] (HOST_LOC_0_RSVD_RW1[0-7])—Offset FED40010h, Count 8, Stride 4h

This register represents a DW of RW memory in FTPM EBB which has no defined functionality. This DW is aliased to the same offset for each locality, and even inactive localities can access it.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-7]: [0x0] + FED40010h + [0-7]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Locality Config Area Reserved Read Write DW (RSVD_RW_31_0):** Reserved.

54.11.6 FTPM Interface ID Host Read Only Access 0 (HOST_LOC_0_INTF_ID_0)—Offset FED40030h

This register is opaque to HW. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40030h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**FTPM Interface ID Bits 0 (FTPM_INTF_ID_BITS_0):** These are the 32 LSbits used by FW to inform host SW as to the interface type of the TPM. The exact usage is defined by TCG.

54.11.7 FTPM Interface ID Host Read Only Access 1 (HOST_LOC_0_INTF_ID_1)—Offset FED40034h

This register is opaque to HW. This register is implemented in flip-flops.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40034h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**FTPM Interface ID Bits 1 (FTPM_INTF_ID_BITS_1):** These are the 32 MSbits used by FW to inform host SW as to the interface type of the TPM. The exact usage is defined by TCG.

54.11.8 FTPM Locality Config Area Reserved Read Write[0-1] (HOST_LOC_0_RSVD_RW2[0-1])—Offset FED40038h, Count 2, Stride 4h

This register represents a DW of RW memory in FTPM EBB which has no defined functionality. This DW is aliased to the same offset for each locality, and even inactive localities can access it.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-1]: [0x0] + FED40038h + [0-1]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Locality Config Area Reserved Read Write DW (RSVD_RW_31_0):** Reserved.

54.11.9 Control Area Request (HOST_LOC_0_CA_REQUEST)—Offset FED40040h

This register is implemented in flip-flops. This register is implemented in retention flops to maintain state through PG.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40040h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_REQUEST:** Host software sets this field to a CSxE firmware-defined value to indicate a state change request to the fTPM. Any host write to this register shall result in an interrupt to the CSxE firmware, or wakeup the CSxE subsystem when it is in power-gated state.

54.11.10 Control Area Status (HOST_LOC_0_CA_STATUS)—Offset FED40044h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40044h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_STATUS:** Reserved.

54.11.11 Control Area Cancel (HOST_LOC_0_CA_CANCEL)—Offset FED40048h

This register is implemented in flip-flops. This register is implemented in retention flops to maintain state through PG.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40048h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CANCEL:** Host software sets this field to a CSxE firmware-defined value to indicate that a command should be canceled. Any host write to this register shall result in an interrupt to the CSxE firmware, or wakeup the CSxE subsystem when it is in power-gated state.

54.11.12 Control Area Start (HOST_LOC_0_CA_START)—Offset FED4004Ch

This register is implemented in flip-flops. This register is implemented in retention flops to maintain state through PG.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4004Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Control Area Start (HOST_CA_START):** Host software sets this field to a CSxE firmware defined value to indicate that a command is available for processing. The reset value indicates that a command is NOT available for processing. Any host write to this register shall result in an interrupt to the CSE firmware or wakeup the CSE subsystem when it is in power-gated state.

54.11.13 Control Area Interrupt Reserved Part 1 (HOST_LOC_0_CA_INT_RSVD1)—Offset FED40050h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40050h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RSVD_31_0:** Reserved.

54.11.14 Control Area Interrupt Reserved Part 2 (HOST_LOC_0_CA_INT_RSVD2)—Offset FED40054h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40054h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RSVD_31_0:** Reserved.

54.11.15 Control Area Command Size (HOST_LOC_0_CA_CMD_SZ)—Offset FED40058h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40058h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CMD_SZ:** Reserved.

54.11.16 Control Area Command Part 1 (HOST_LOC_0_CA_CMD1)—Offset FED4005Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4005Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CMD1:** Reserved.

54.11.17 Control Area Command Part 2 (HOST_LOC_0_CA_CMD2)—Offset FED40060h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40060h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_CMD2:** Reserved.

54.11.18 Control Area Response Size (HOST_LOC_0_CA_RSP_SZ)—Offset FED40064h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40064h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_RSP_SZ:** Reserved.

54.11.19 Control Area Response Part 1 (HOST_LOC_0_CA_RSP1)—Offset FED40068h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED40068h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_RSP1:** Reserved.

54.11.20 Control Area Response Part 2 (HOST_LOC_0_CA_RSP2)—Offset FED4006Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [0x0] + FED4006Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**HOST_CA_RSP2:** Reserved.

54.11.21 FTPM Reserved Read Write[0-3] (HOST_LOC_0_RSVD_RW3[0-3])—Offset FED40070h, Count 4, Stride 4h

This register represents a DW of RW memory in FTPM EBB which has no defined functionality. The access to this DW is allowed only to an active locality.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-3]: [0x0] + FED40070h + [0-3]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Reserved Read Write DW (RSVD_RW_31_0):** Reserved.

54.11.22 FTPM Command and Response Buffer[0-991] (HOST_LOC_0_FTPM_CRB[0-991])—Offset FED40080h, Count 992, Stride 4h

This register represents a DW of RW memory in FTPM CRB (EBB)

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset[0-991]: [0x0] + FED40080h + [0-991]*4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**FTPM Command and Response Buffer DW (HOST_FTPM_CRB_DW):** Reserved.

54.12 Registers in I/O Space—KT_HOST_IOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) KT_HOST_IOBAR described in Section 54.5.5, "KT IO BAR (KT_HOST_IOBAR)—Offset 10h" on page 2512.

54.12.1 KT Receive Buffer Register (IO_KTRBR)—Offset 0h

This register implements the standard Receiver Buffer register in the KT Block. This is read-only. DLAB(i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be read when the receiver data is ready. In FIFO mode, a read from this register will be translated into a read from the RBR FIFO. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 0h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Receiver Buffer Register (RBR):** Implements the Receiver Buffer register of the Serial Interface.

54.12.2 KT Transmitter Holding Register (IO_KTTHR)—Offset 0h

This register implements the standard Transmitter Holding register in the KT Block. This is write-only. DLAB(i.e. KTLCR[7]) shall be 0. In non-FIFO mode, this register will be written when the Host needs to transmit data. In FIFO mode, a write to this register will be translated into a write to the THR FIFO. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 0h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**Transmitter Holding Register (THR):** Implements the Transmit Data register of the Serial Interface.

54.12.3 KT Divisor Latch LSB Register (IO_KTDLLR)—Offset 0h

This register implements the standard DLL register in the KT Block. DLAB(i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. this register is supported only for SW compatibility and has no impact on HW performance. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 0h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch LSB (DLL):** Implements the DLL register of the Serial Interface.

54.12.4 KT Interrupt Enable register (IO_KTIER)—Offset 1h

This register implements the standard Interrupt Enable register in the KT Block. The bits enable specific events to interrupt the Host. See bit specific definition below. DLAB(i.e. KTLCR[7]) shall is 0 in order for this register to be accessed. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 1h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x0 RW	**MSR (IER3):** When set, enables bits in Modem Status register to cause an interrupt to the Host.
2	0x0 RW	**LSR (IER2):** When set, enables bits in Receiver Line Status Register to cause an interrupt to the Host.
1	0x0 RW	**THR (IER1):** When set, enables an interrupt to the Host when the Transmitter Holding register is empty.
0	0x0 RW	**DR (IER0):** When set, enables an interrupt to the Host when the Received Data is available OR Receiver FIFO timeout.

54.12.5 KT Divisor Latch MSB Register (IO_KTDLMR)—Offset 1h

This register implements the standard DLM register in the KT Block. DLAB(i.e. KTLCR[7]) shall be 1 in order for this register to be accessed. This register is supported only for SW compatibility and has no impact on HW performance. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 1h

Default: 00h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Divisor Latch MSB (DLM):** Implements the DLM register of the Serial Interface.

54.12.6 KT Interrupt Identification Register (IO_KTIIR)—Offset 2h

This register implements the standard Interrupt Identification register in the KT Block. This is read-only. This register is created to provide minimum software overhead during data character transfers. The register prioritizes KT interrupts into 4 levels and records them in the IIRSTS field of this register. The four levels of interrupt conditions in order of priority are: Receiver Line Status; Received Data Ready/Character Timeout Indication; Transmitter Holding Register Empty; MODEM Status. When the Host accesses the IIR, the HW freezes all interrupts and indicates the highest priority pending interrupt to the Host. While this Host access is occurring, the HW records new interrupts, but does not change its current indication until the access is complete. Table in the Host Interrupt Generation section shows the contents. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 2h

Default: 01h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**FIFO Enable (FIEN1):** This field is connected by HW to the FIFO Enable field of the FCR register.
6	0x0 RO/V	**FIFO Enable (FIEN0):** This field is connected by HW to the FIFO Enable field of the FCR register.
5:4	0x0 RO	**Reserved (RSVD):** Hardwired to 0.
3:1	0x0 RO/V	**IIR Status (IIRSTS):** These bits are asserted by the HW according to the source of the interrupt and the priority level. Refer to the section on Host Interrupt Generation for a table of values.
0	0x1 RO/V	**Interrupt Status (INTSTS):** • 0: indicates a pending Host interrupt and IIRSTS may be used as a pointer to the appropriate interrupt service routine. It reflects the logical-NOR of all UART interrupts. An individual UART interrupt will be identified as pending when the individual event status is asserted AND its corresponding event interrupt enable is asserted as well. For example, the THR Empty interrupt will be identified as pending when both LSR[THRE] bit is 1 AND IER[IER1] is 1. • 1: indicates no pending Host interrupt.

54.12.7 KT FIFO Control register (IO_KTFCR)—Offset 2h

This register implements the standard FIFO Control register in the KT Block. It is used to configure features pertinent to the FIFO mode of operation. This is write-only. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 2h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 WO	**Receiver Trigger Level (RTL):** Trigger level in bytes for the Receiver FIFO. Once the trigger level number of bytes is reached, an interrupt will be sent to the Host [7:6] RCVR FIFO Trigger Level (bytes) • 00 -- 01 • 01 -- 04 • 10 -- 08 • 11 -- 14
5:4	0x0 WO	**Reserved (RSVD):** Writes to this field shall be dropped.
3	0x0 WO	**RDY Mode (RDYM):** This bit has no effect on HW performance.
2	0x0 WO	**XMT FIFO Clear (XFIC):** When the Host writes one to this bit the HW will clear the XMT FIFO. This bit is self-cleared by HW.
1	0x0 WO	**RCV FIFO Clear (RFIC):** When the Host writes one to this bit the HW will clear the RCV FIFO. This bit is self-cleared by HW.
0	0x0 WO	**FIFO Enable (FIE):** When set indicates that the KT interface is working in FIFO node. When this bit value is changed the RCV and XMT FIFO are cleared by HW. This bit must be a 1 when other FCR bits are written to or they will NOT be programmed.

54.12.8 KT Line Control register (IO_KTLCR)—Offset 3h

This register implements the standard Line Control register in the KT Block. It specifies the format of the asynchronous data communications exchange and sets the DLAB bit. Most bits in this register have no effect on HW and are only used by the FW. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 3h

Default: 03h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Divisor Latch Access Bit (DLAB):** • 1: Allows access to the Divisor Latch Registers and reading of the FIFO Control Register. • 0: Allows access to RBR, THR, IER and IIR registers.
6	0x0 RW	**Break Control (BC):** This bit has no effect on HW.
5:4	0x0 RW	**Parity Bit Mode (PBM):** This bit has no effect on HW.
3	0x0 RW	**Parity Enable (PE):** This bit has no effect on HW.
2	0x0 RW	**Stop Bit Select (SBS):** This bit has no effect on HW.
1:0	0x3 RW	**Word Select Byte (WSB):** This bit has no effect on HW.

54.12.9 KT Modem Control register (IO_KTMCR)—Offset 4h

This register implements the standard Modem Control register in the KT Block. It controls the interface with the modem. Because the FW emulates the modem, the Host communicates with the FW via this register. This register has impact on the HW in the loopback mode. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 4h

Default: 00h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved.
4	0x0 RW	**Loop Back Mode (LBM):** When set by Host indicates that the serial port is in loop Back mode. This means that the data that is transmitted by the host should be received. Helps in debug of the interface.
3	0x0 RW	**Output 2 (OUT2):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit (7).
2	0x0 RW	**Output 1 (OUT1):** This bit has no effect on HW in normal mode. In loop back mode the value of this bit is written by HW to Modem Status Register bit(6).
1	0x0 RW	**Request to Send Out (RTSO):** This bit has no effect on HW in normal mode. In loopback mode, the value of this bit is written by HW to Modem Status Register bit(4).
0	0x0 RW	**Data Terminal Ready Out (DRTO):** This bit has no effect on HW in normal mode. In loopback mode, the value in this bit is written by HW to Modem Status Register Bit(5).

54.12.10 KT Line Status register (IO_KTLSR)—Offset 5h

This register implements the standard Line Status register in the KT Block. It provides status information of the data transfer to the Host. Error indication etc are provided by the HW/FW to the host via this register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [KT_HOST_IOBAR] + 5h

Default: 60h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/C/V	**RCVR FIFO Error (RXFER):** This bit is cleared in non FIFO mode. This bit is connected to UART LSR[BI] bit in FIFO mode.
6	0x1 RO/C/V	**Transmitter Empty (TEMT):** In non-FIFO mode: This bit will be set to 1 whenever the Transmitter Holding Register (THR) and the Transmitter Shift Register (TSR) are both empty, OR cleared to 0 whenever either THR or TSR contains a data byte. In FIFO mode: This bit will be set to 1 whenever XMIT FIFO and TSR are both empty, OR cleared to 0 whenever either XMIT FIFO or TSR contains a data byte. Implementation note: This bit is connected by HW to THRE bit
5	0x1 RO/C/V	**Transmitter Holding Register Empty (THRE):** The bit will always be set whenever Host changes UART FCR[FIE] bit. This bit is controlled differently in FIFO vs non-FIFO modes: Non-FIFO mode: This bit will be cleared by HW when Host writes to THR, and set by HW when FW reads from THR. FIFO mode: This bit will be set by HW when XMIT FIFO is empty , and cleared by HW when XMIT FIFO is NOT empty.
4	0x0 RO/C/V	**Break Interrupt (BI):** This bit will be cleared by HW when the UART LSR register is read by Host. This bit will be set by HW in two cases: In FIFO mode, when FW sets the KTRIVR[SBI] bit. In non-FIFO mode, when FW sets the KTRBR[BIA] bit.
3	0x0 RO	**Framing Error (FE):** This bit is NOT implemented and hardwired to 0.
2	0x0 RO	**Parity Error (PE):** This bit is NOT implemented and hardwired to 0.
1	0x0 RO/C/V	**Overrun Error (OE):** HW will clear this bit when Host reads from KTLSR register and this is source of interrupt. HW will set this bit when overrun error is detected. In non-FIFO mode, the character that triggers the overrun error shall overwrite the character in the RBR register. In FIFO mode, the character that triggers the overrun error shall be dropped without corrupting the RCVR FIFO.
0	0x0 RO/V	**Data Ready (DR):** Non-FIFO Mode: This bit will be set by HW when FW writes to RBR and cleared by HW when Host reads from RBR. FIFO Mode: The bit will be set by HW when RCVR FIFO is not empty and cleared by HW when RCVR FIFO is empty.

54.12.11 KT Modem Status register (IO_KTMSR)—Offset 6h

This register implements the standard Modem Status register in the KT Block. It provides the current state of the control lines from the modem. The modem functionality is emulated by the FW. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 6h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Data Carrier Detect (DCD):** In Loop Back mode this bit is connected by HW to the value of MCR bit 3.
6	0x0 RO	**Ring Indicator (RI):** In Loop Back mode this bit is connected by HW to the value of MCR bit 2.
5	0x0 RO	**Data Set Ready (DSR):** In Loop Back mode this bit is connected by HW to the value of MCR bit 0.
4	0x0 RO	**Clear To Send (CTS):** In Loop Back mode this bit is connected by HW to the value of MCR bit 1.
3	0x0 RO/C/V	**Delta Data Carrier Detect (DDCD):** This bit is set when bit 7 is changed. This bit is cleared by HW when the MSR register is being read by the HOST driver.
2	0x0 RO/C/V	**Trailing Edge of Read Detector (TERI):** This bit is set when bit 6 is changed from 1 to 0. This bit is cleared by HW when the MSR register is being read by the Host driver.
1	0x0 RO/C/V	**Delta Data Set Ready (DDSR):** This bit is set when bit 5 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver.
0	0x0 RO/C/V	**Delta Clear To Send (DCTS):** This bit is set when bit 4 is changed. This bit is cleared by HW when the MSR register is being read by the Host driver.

54.12.12 KT Scratch register (IO_KTSCR)—Offset 7h

This register implements the standard Scratch register in the KT Block. It allows Host SW programmers to hold temporary data. It has NO effect on HW. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [KT_HOST_IOBAR] + 7h

KT_HOST_IOBAR Type: PCI Configuration Register (Size: 32 bits)
KT_HOST_IOBAR Reference: [B:0, D:27, F:3] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Scratch Register Data (SCRD):** Reserved.

54.13 Registers in I/O Space—IDE_HOST_PCMDIOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IDE_HOST_PCMDIOBAR described in Section 54.6.5, "IDE Primary Command Block IO BAR (IDE_HOST_PCMDIOBAR)—Offset 10h" on page 2525.

54.13.1 IDE Data Register (IDEDATA)—Offset 0h

This register serves as the data interface in IDE PIO modes. Unit of access is in WORD. Host writes to this register are converted into writes to the PIO buffer in CSxE memory at monotonically increasing WORD address. Host writes are dropped under any one of the following conditions: (1) PIO modes are disabled. (Cfg. IDEPBPR[EN] defined in CSxE memory space) (2) PIO buffer is full. Host reads from this register are converted into reads from the PIO buffer in CSxE memory at monotonically increasing WORD address. Host reads are dropped under any one of the following conditions: (1) PIO modes are disabled. (Cfg. IDEPBPR[EN] defined in CSxE memory space) (2) PIO buffer is empty. Reset condition: no connection to any reset signal.

Type: I/O Register
(Size: 16 bits)

Default: 0000h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 0h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/V	**IDE Data Register (IDEDR):** Data interface in IDE PIO modes. Host reads/writes from/to this register are converted into reads/writes from/to the PIO buffer in CSxE memory.

54.13.2 IDE Features Register (IDEFR)—Offset 1h

This register implements the standard Features register in the Primary IDE Command Block. This is write-only. BE[0] shall be deasserted. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 1h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Features Data (IDEFD):** The IDE Features register is command specific and is used to enable and disable interface features.

54.13.3 IDE Error Register DEV0 (IDEERD0)—Offset 1h

This register implements the standard Device 0 Error register in the Primary IDE Command Block. This is read-only. BE[0] shall be deasserted. DEV = 0 (i.e. IDEDHIR[4] = 0). Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 1h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Error Data (IDEED):** Upon command completion of any command except EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET, the content of this register is valid and contains error status when the ERR bit is set to 1 in the Status register (i.e. IDESR0[ERR] = 1). Following a power-on, a hardware or software reset, or command completion of an EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET command, this register contains a diagnostic code. Bit 2 ABRT (command aborted) is set to 1 to indicate the requested command has been command aborted because the command code or a command parameter is invalid, the command is not supported, a pre-requisite for the command has not been met, or some other error has occurred.

54.13.4 IDE Error Register DEV1 (IDEERD1)—Offset 1h

This register implements the standard Device 1 Error register in the Primary IDE Command Block. This is read-only. BE[0] shall be deasserted. DEV = 1 (i.e. IDEDHIR[4] = 1). Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 1h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Error Data (IDEED):** Upon command completion of any command except EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET, the content of this register is valid and contains error status when the ERR bit is set to 1 in the Status register (i.e. IDESR0[ERR] = 1). Following a power-on, a hardware or software reset, or command completion of an EXECUTE DEVICE DIAGNOSTIC or DEVICE RESET command, this register contains a diagnostic code. Bit 2 ABRT (command aborted) is set to 1 to indicate the requested command has been command aborted because the command code or a command parameter is invalid, the command is not supported, a pre-requisite for the command has not been met, or some other error has occurred.

54.13.5 IDE Sector Count In Register (IDESCIR)—Offset 2h

This register implements the standard Sector Count In register in the Primary IDE Command Block. All 3 registers (IDESCIR, IDESCOR0, IDESCOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is meaningful for an ATA command while unused for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 2h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Sector Count Data (IDESCD):** The Sector Count register specifies the sector count of the data for which an ATA transfer has been made.

54.13.6 IDE Sector Count Out Register DEV0 (IDESCOR0)—Offset 2h

This register implements the standard Device 0 Sector Count Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA/ATAPI command. This register is called IDE Interrupt Reason Register DEV0 for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 2h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Count Out DEV0 (ISCOD0):** Sector Count Out register for Device 0.

54.13.7 IDE Sector Count Out Register DEV1 (IDESCOR1)—Offset 2h

This register implements the standard Device 1 Sector Count Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA/ATAPI command. This register is called IDE Interrupt Reason Register DEV1 for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 2h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Count Out DEV1 (ISCOD1):** Sector Count Out register for Device 1.

54.13.8 IDE Sector Number In Register (IDESNIR)—Offset 3h

This register implements the standard Sector Number In register in the Primary IDE Command Block in CHS addressing mode. All 3 registers (IDESNIR, IDESNOR0, IDESNOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is called IDE LBA Low In Register in LBA addressing mode. This register is reserved for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 3h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Sector Number Data (IDESND):** The Sector Number register is set by the host to specify the starting sector number associated with the next ATA command to be executed. Following a qualified ATA command sequence the device will set the register value to the last sector read or written as a result of the previous ATA command.

54.13.9 IDE Sector Number Out Register DEV0 (IDESNOR0)—Offset 3h

This register implements the standard Device 0 Sector Number Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Low Out Register DEV0 in LBA addressing mode. This register is reserved for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 3h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Number Out DEV0 (IDESNO0):** Sector Number Out register for Device 0.

54.13.10 IDE Sector Number Out Register DEV1 (IDESNOR1)—Offset 3h

This register implements the standard Device 1 Sector Number Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Low Out Register DEV1 in LBA addressing mode. This register is reserved for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 3h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Sector Number Out DEV1 (IDESNO1):** Sector Number Out register for Device 1.

54.13.11 IDE Cylinder Low In Register (IDECLIR)—Offset 4h

This register implements the standard Cylinder Low In register in the Primary IDE Command Block. All 3 registers (IDECLIR, IDCLOR0, IDCLOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is called IDE LBA Mid In Register in LBA addressing mode. This register is called IDE Byte Count Low Limit Register for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 4h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Cylinder Low Data. (IDECLD):** The Cylinder Low register is set by the host to specify the cylinder number low byte. Following an ATA command, the contents of this register is written by the device, identifying the cylinder number low byte.

54.13.12 IDE Cylinder Low Out Register DEV0 (IDCLOR0)—Offset 4h

This register implements the standard Device 0 Cylinder Low Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Mid Out Register DEV0 in LBA addressing mode. This register is called IDE Byte Count Low Register DEV0 for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 4h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder Low Out DEV0. (IDECLO0):** Cylinder Low Out Register for Device 0.

54.13.13 IDE Cylinder Low Out Register DEV1 (IDCLOR1)—Offset 4h

This register implements the standard Device 1 Cylinder Low Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA Mid Out Register DEV1 in LBA addressing mode. This register is called IDE Byte Count Low Register DEV1 for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 4h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder Low Out DEV1. (IDECLO1):** Cylinder Low Out Register for Device 1.

54.13.14 IDE Cylinder High In Register (IDECHIR)—Offset 5h

This register implements the standard Cylinder High In register in the Primary IDE Command Block. All 3 registers (IDECHIR, IDCHOR0, IDCHOR1) will be updated with the same write data when this register is write-accessed. This is write-only. This register is called IDE LBA High In Register in LBA addressing mode. This register is called IDE Byte Count High Limit Register for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 5h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Cylinder High Data (IDECHD):** The Cylinder High register is set by the host to specify the cylinder number high byte. Following an ATA command, the contents of this register is written by the device, identifying the cylinder number high byte.

54.13.15 IDE Cylinder High Out Register DEV0 (IDCHOR0)—Offset 5h

This register implements the standard Device 0 Cylinder High Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA High Out Register DEV0 in LBA addressing mode. This register is called IDE Byte Count High Register DEV0 for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 5h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder High Out DEV0 (IDECHO0):** Cylinder High Out register for Device 0.

54.13.16 IDE Cylinder High Out Register DEV1 (IDCHOR1)—Offset 5h

This register implements the standard Device 1 Cylinder High Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE LBA High Out Register DEV1 in LBA addressing mode. This register is called IDE Byte Count High Register DEV1 for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 5h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Cylinder High Out DEV1 (IDECHO1):** Cylinder High Out register for Device 1.

54.13.17 IDE Drive/Head In Register (IDEDHIR)—Offset 6h

This register implements the standard Drive/Head In register in the Primary IDE Command Block. All 3 registers (IDEDHIR, IDDHOR0, IDDHOR1) will be updated with the same write data when this register is write-accessed. This is write-only. Bit 4 of this register is the DEV (master/slave) bit. This bit is cleared by hardware on IDE software reset (IDDCR[SRST] = 1) in addition to Host reset. This register is called IDE Device In Register in LBA addressing mode or for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 6h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Drive/Head Data (IDEDHD):** The Drive/Head Register is used by the host and the device to select the type of addressing (CHS or LBA), the drive letter, and either bits 3 through 0 of the head number in CHS mode or in LBA mode, bits D3:D0 reflect the logical block number bits LBA27:LBA24.

54.13.18 IDE Drive/Head Out Register DEV0 (IDDHOR0)—Offset 6h

This register implements the standard Device 0 Drive/Head Out register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE Device Out Register DEV0 in LBA addressing mode or for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 6h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Drive/Head Out DEV0 (IDEDHO0):** Drive/Head Out register of Device 0.

54.13.19 IDE Drive/Head Out Register DEV1 (IDDHOR1)—Offset 6h

This register implements the standard Device 1 Drive/Head Out register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA command. This register is called IDE Device Out Register DEV1 in LBA addressing mode or for an ATAPI command. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 6h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Drive/Head Out DEV1 (IDEDHO1):** Drive/Head Out register of Device 1.

54.13.20 IDE Command Register (IDECR)—Offset 7h

This register implements the standard Command register in the Primary IDE Command Block. This is write-only. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 7h

Default: 00h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 WO	**IDE Command Data (IDECD):** The Command register specifies the ATA/ATAPI Command code being issued to the drive by the host. Command processing begins when this register is written. The content of the Command Block registers becomes parameters of the command when this register is written. Writing this register clears any pending interrupt condition. Please refer to the description of the INTM and INTS bits in the IDGCR register in the CSxE memory space for detailed conditions under which interrupt condition shall be cleared.

54.13.21 IDE Status Register DEV0 (IDESR0)—Offset 7h

This register implements the standard Device 0 Status register in the Primary IDE Command Block. This is read-only. DEV = 0 (i.e. IDEDHIR[4] = 0). CSxE FW writes to this register upon completion of an ATA/ATAPI command. Additionally upon completion of the last data phase of a PIO transfer, HW will load this register with value of the SRAFP field in the IDESRAP register in the CSxE memory space. Host read of this register clears Device 0's interrupt. Please refer to the description of the INTM bit in the IDGCR register in the CSxE memory space for detailed conditions under which interrupt condition shall be cleared. The bit description is for ATA mode. Different name in ATAPI mode, if applicable, is cited as well. Reset condition: CSxE reset with the BSY bit as an exception. Please refer to description of the BSY bit below for a list of BSY bit reset conditions. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 7h

Default: 80h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Busy (BSY):** This bit is set by HW when the IDECR is being written and DEV=0, OR when IDDCR[SRST] bit is asserted by Host, OR host system reset, OR D3 to D0 transition of the IDE function. This bit is cleared by FW write of 0. Please refer to general register description above for special handling for a PIO transfer. When this bit is 1, any other bit in this register is meaningless.
6	0x0 RO/V	**Drive Ready (DRDY):** When set, indicates drive is ready for command. Update of this bit is completely FW-assisted. This bit is also called Device Ready. Please refer to general register description above for special handling for a PIO transfer.
5	0x0 RO/V	**Drive Fault (DF):** When set, indicates Error on the drive. Update of this bit is completely FW-assisted. This bit is called DMA Ready for a DMA ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
4	0x0 RO/V	**Drive Seek Complete (DSC):** When set, indicates Heads are positioned over the desired cylinder. Update of this bit is completely FW-assisted. This bit is called Service for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
3	0x0 RO/V	**Data Request (DRQ):** Set when the drive wants to exchange data with the Host via the data register. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
2	0x0 RO/V	**Corrected Data (CORR):** When set, indicates a correctable read error has occurred. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
1	0x0 RO/V	**Index (IDX):** This bit is set once per rotation of the medium when the index mark passes under the read/write head. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
0	0x0 RO/V	**Error (ERR):** When set, indicates an error occurred in the process of executing the current command. The Error Register of the selected device contains the error information. Update of this bit is completely FW-assisted. This bit is called Check for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.

54.13.22 IDE Status Register DEV1 (IDESR1)—Offset 7h

This register implements the standard Device 1 Status register in the Primary IDE Command Block. This is read-only. DEV = 1 (i.e. IDEDHIR[4] = 1). CSxE FW writes to this register upon completion of an ATA/ATAPI command. Additionally upon completion of the last data phase of a PIO transfer, HW will load this register with value of the SRAFP field in the IDESRAP register in the CSxE memory space. Host read of this register clears Device 1's interrupt. Please refer to the description of the INTM bit in the IDGCR register in the CSxE memory space for detailed conditions under which interrupt condition shall be cleared. The bit description is for ATA mode. Different name in ATAPI mode, if applicable, is cited as well. Reset condition: CSxE reset with the BSY bit as an exception. Please refer to description of the BSY bit below for a list of BSY bit reset conditions. Non-sticky.

Type: I/O Register (Size: 8 bits)

BAR and Offset: [IDE_HOST_PCMDIOBAR] + 7h

Default: 80h

IDE_HOST_PCMDIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCMDIOBAR Reference: [B:0, D:27, F:2] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Busy (BSY):** This bit is set by HW when the IDECR is being written and DEV=1, OR when IDDCR[SRST] bit is asserted by Host, OR host system reset, OR D3 to D0 transition of the IDE function. This bit is cleared by FW write of 0. Please refer to general register description above for special handling for a PIO transfer. When this bit is 1, any other bit in this register is meaningless.
6	0x0 RO/V	**Drive Ready (DRDY):** When set, indicates drive is ready for command. Update of this bit is completely FW-assisted. This bit is also called Device Ready. Please refer to general register description above for special handling for a PIO transfer.
5	0x0 RO/V	**Drive Fault (DF):** When set, indicates Error on the drive. Update of this bit is completely FW-assisted. This bit is called DMA Ready for a DMA ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
4	0x0 RO/V	**Drive Seek Complete (DSC):** When set, indicates Heads are positioned over the desired cylinder. Update of this bit is completely FW-assisted. This bit is called Service for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.
3	0x0 RO/V	**Data Request (DRQ):** Set when the drive wants to exchange data with the Host via the data register. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
2	0x0 RO/V	**Corrected Data (CORR):** When set, indicates a correctable read error has occurred. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
1	0x0 RO/V	**Index (IDX):** This bit is set once per rotation of the medium when the index mark passes under the read/write head. Update of this bit is completely FW-assisted. Please refer to general register description above for special handling for a PIO transfer.
0	0x0 RO/V	**Error (ERR):** When set, indicates an error occurred in the process of executing the current command. The Error Register of the selected device contains the error information. Update of this bit is completely FW-assisted. This bit is called Check for an ATAPI command. Please refer to general register description above for special handling for a PIO transfer.

54.14 Registers in I/O Space—IDE_HOST_PCTLIOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IDE_HOST_PCTLIOBAR described in Section 54.6.6, "IDE Primary Control Block IO BAR (IDE_HOST_PCTLIOBAR)—Offset 14h" on page 2526.

54.14.1 IDE Device Control Register (IDDCR)—Offset 2h

This register implements the standard Device Control register in the Primary IDE Control Block. This is write-only. BE[0] shall be deasserted. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCTLIOBAR] + 2h

IDE_HOST_PCTLIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCTLIOBAR Reference: [B:0, D:27, F:2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 WO	**Reserved (RSVD1):** Writable by Host, but NO HW effect due to writes.
2	0x0 WO	**Software Reset (SRST):** 1: both devices shall perform the software reset protocol. 0: both devices shall exit software reset.
1	0x0 WO	**Host Interrupt Disable (nIEN):** 1: disables HW from generating interrupt to the Host. 0: enables HW to generate interrupt to the Host.
0	0x0 WO	**Reserved (RSVD0):** Writable by Host, but NO HW effect due to writes.

54.14.2 IDE Alternate Status Register (IDASR)—Offset 2h

This register implements the standard Alternate Status register in the Primary IDE Control Block. This is read-only. It shadows the standard Status registers in the Primary IDE Command Block. Read of this register does NOT clear the interrupt status bits in the selected Status register. IDESR0 is shadowed when DEV = 0 (i.e. IDEDHIR[4] = 0). IDESR1 is shadowed when DEV = 1 (i.e. IDEDHIR[4] = 1). Reset condition: There is no reset associated with this register because it is NOT a physical register.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_PCTLIOBAR] + 2h

IDE_HOST_PCTLIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_PCTLIOBAR Reference: [B:0, D:27, F:2] + 14h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**IDE Alternate Status Register (IDEASR):** Shadows DEV0/DEV1 Status register on Host reads depending on IDEDHIR[4] setting.

54.15 Registers in I/O Space—IDE_HOST_BMIOBAR

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) IDE_HOST_BMIOBAR described in Section 54.6.9, "IDE Bus Master Block IO BAR (IDE_HOST_BMIOBAR)—Offset 20h" on page 2527.

54.15.1 IDE Primary Bus Master Command Register (IDEPBMCR)—Offset 0h

This register implements the standard IDE Primary Bus Master Command register in the IDE Bus Master Block. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 0h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD1):** Not implemented. Hardwired to 0.
3	0x0 RW	**Read or Write Control (RWC):** This bit sets the direction of the bus master transfer. • 0: reads are performed from Host system memory. • 1: writes are performed to Host system memory. This bit shall NOT be changed when the bus master function is active.
2:1	0x0 RO	**Reserved (RSVD0):** Not implemented. Hardwired to 0.
0	0x0 RW/V	**Start/Stop Bus Master (SSBM):** Host starts a bus master operation in the device by setting this bit to 1. The device shall only transfer data between the ATA device and Host memory in the bus master operation. Host stops the bus master operation by clearing this bit to 0. All state information will be lost when 0 is written. Host CANNOT stop and then resume the bus master operation. When Host clears this bit to 0 while the bus master operation is still active, the bus master operation will be aborted and data transferred from the device may be discarded before being written to host memory. In any event the device should terminate any DMA burst in progress compliant with the ATA protocol being used. If the UDMA protocol is being used, there may be a CRC error report. The ATA device may be in an indeterminate state. HW will clear this bit to 0 after the data transfer has been completed, as indicated by satisfaction of either of the following conditions: (1) IDEPBMSR[BMIA] is cleared to 0. OR (2) IDEPBMSR[INT] is set to 1.

54.15.2 IDE Primary Bus Master Device Specific 0 Register (IDEPBMDS0R)—Offset 1h

This register implements the standard IDE Primary Bus Master Device Specific 0 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data. Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 1h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Device Specific Data0 (DSD0):** Device Specific.

54.15.3 IDE Primary Bus Master Status Register (IDEPBMSR)—Offset 2h

This register implements the standard IDE Primary Bus Master Status register in the IDE Bus Master Block.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + 2h

Default: 80h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Simplex Only (SO):** This bit indicates whether or not both bus master channels (primary and secondary) can be operated at the same time. • If the bit is 0, both channels operate independently and can be used at the same time. • If the bit is 1, only one channel may be used at a time. Reset condition: CSxE reset. Non-sticky.
6	0x0 RW/V	**Device 1 DMA Capable (D1DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 1 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance. Reset condition: Host reset. Non-sticky.
5	0x0 RW/V	**Device 0 DMA Capable (D0DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 0 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance. Reset condition: Host reset. Non-sticky.
4:3	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
2	0x0 RW/1C/V	**Interrupt (INT):** HW shall set this bit to 1 on rising edge detection of the ATA channels interrupt line (INTRQ). Host SW writes 1 to clear this bit. Host SW can use this bit to determine if an ATA device has asserted its interrupt line (INTRQ) (see ATA standard). When this bit is 1, all data MUST have been transferred to the Hosts system memory. The adapter shall not set this bit to 1 until it has flushed all internal data buffers. NOTE: When INTRQ is deasserted, HW won't clear this bit atomically. When INTRQ is deasserted, this bit shall be cleared as well by Host SW writing 1 to this bit. Reset condition: CSxE reset. Non-sticky.
1	0x0 RW/1C/V	**Error (ER):** FW will set this bit to 1 when the device encounters an error in transferring data to/from Host memory. The exact error condition is bus specific and can be determined in a bus specific manner. Host SW writes 1 to clear this bit. Reset condition: CSxE reset. Non-sticky.

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RO/V	**Bus Master IDE Active (BMIA):** HW shall set this bit when (1) Host sets the IDEPBMCR[SSBM] bit. FW shall clear this bit when (1) The last transfer for a region is performed, where EOT for that region is set in the region descriptor. OR (2) FW detects that Host cleared IDEPBMCR[SSBM] bit as indicated by a value of 1 in proxy bit IDEBMCR[SSBMC] in CSxE root space. Before clearing this bit to 0, FW must satisfy the following conditions in addition: (1) All data transferred from the device during the previous bus master command has been transferred to the Hosts system memory, unless the bus master command was aborted. OR (2) All data has been written to the device. Reset condition: CSxE reset. Non-sticky.

54.15.4 IDE Primary Bus Master Device Specific 1 Register (IDEPBMDS1R)—Offset 3h

This register implements the standard IDE Primary Bus Master Device Specific 1 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data. Reset condition: CSxE reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 3h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Device Specific Data1 (DSD1):** Device Specific Data.

54.15.5 IDE Primary Bus Master Descriptor Table Pointer Register Byte 0 (IDEPBMDTPR0)—Offset 4h

This register implements the Byte 0 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 4h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 0 (DTPB0):** Byte 0 of the Descriptor Table pointer. The Descriptor Table shall be DW-aligned. Hence bit[1:0] shall always be 0.

54.15.6 IDE Primary Bus Master Descriptor Table Pointer Register Byte 1 (IDEPBMDTPR1)—Offset 5h

This register implements the Byte 1 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 5h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 1 (DTPB1):** Byte 1 of the Descriptor Table pointer.

54.15.7 IDE Primary Bus Master Descriptor Table Pointer Register Byte 2 (IDEPBMDTPR2)—Offset 6h

This register implements the Byte 2 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 6h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 2 (DTPB2):** Byte 2 of the Descriptor Table pointer.

54.15.8 IDE Primary Bus Master Descriptor Table Pointer Register Byte 3 (IDEPBMDTPR3)—Offset 7h

This register implements the Byte 3 of the standard IDE Primary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the primary channel. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + 7h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 3 (DTPB3):** Byte 3 of the Descriptor Table pointer.

54.15.9 IDE Secondary Bus Master Command Register (IDESBMCR)—Offset 8h

This register implements the standard IDE Secondary Bus Master Command register in the IDE Bus Master Block. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + 8h

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD1):** Not implemented. Hardwired to 0.
3	0x0 RW	**Read or Write Control (RWC):** This bit sets the direction of the bus master transfer. • 0: reads are performed from Host system memory. • 1: writes are performed to Host system memory. This bit shall NOT be changed when the bus master function is active.
2:1	0x0 RO	**Reserved (RSVD0):** Not implemented. Hardwired to 0.
0	0x0 RW	**Start/Stop Bus Master (SSBM):** Host starts a bus master operation in the device by setting this bit to 1. The device shall only transfer data between the ATA device and Host memory in the bus master operation. Host stops the bus master operation by clearing this bit to 0. All state information will be lost when 0 is written. Host CANNOT stop and then resume the bus master operation.

54.15.10 IDE Secondary Bus Master Device Specific 0 Register (IDESBMDS0R)—Offset 9h

This register implements the standard IDE Secondary Bus Master Device Specific 0 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + 9h

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Device Specific Data0 (DSD0):** Device Specific.

54.15.11 IDE Secondary Bus Master Status Register (IDESBMSR)—Offset Ah

This register implements the standard IDE Secondary Bus Master Status register in the IDE Bus Master Block. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset with the SO bit as an exception. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 80h

BAR and Offset: [IDE_HOST_BMIOBAR] + Ah

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO/V	**Simplex Only (SO):** Value indicates whether both Bus Master Channels can be operated at the same time or not. • 0: Both can be operated independently • 1: Only one can be operated at a time. This bit shadows IDEPBMSR[SO]. Reset condition: CSxE reset. Non-sticky.
6	0x0 RW	**Device 1 DMA Capable (D1DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 1 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance.
5	0x0 RW	**Device 0 DMA Capable (D0DC):** This read/write bit is set by device dependent code (BIOS or host software) to indicate that Device 0 for this channel is capable of DMA transfers, and that the device has been initialized for optimum performance.
4:3	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
2	0x0 RO	**Interrupt (INT):** No functionality implemented. Hardwired to 0.
1	0x0 RO	**Error (ER):** Not implemented. Hardwired to 0.
0	0x0 RO	**Bus Master IDE Active (BMIA):** Not implemented. Hardwired to 0.

54.15.12 IDE Secondary Bus Master Device Specific 1 Register (IDESBMDS1R)—Offset Bh

This register implements the standard IDE Secondary Bus Master Device Specific 1 register in the IDE Bus Master Block. This register is programmed by the Host for any device specific data. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Bh

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Device Specific Data1 (DSD1):** Device Specific Data.

54.15.13 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 0 (IDESBMDTPR0)—Offset Ch

This register implements the Byte 0 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Ch

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 0 (DTPB0):** Byte 0 of the Descriptor Table pointer. The Descriptor Table shall be DW-aligned. Hence bit[1:0] shall always be 0.

54.15.14 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 1 (IDESBMDTPR1)—Offset Dh

This register implements the Byte 1 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + Dh

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 1 (DTPB1):** Byte 1 of the Descriptor Table pointer.

54.15.15 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 2 (IDESBMDTPR2)—Offset Eh

This register implements the Byte 2 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [IDE_HOST_BMIOBAR] + Eh

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 2 (DTPB2):** Byte 2 of the Descriptor Table pointer.

54.15.16 IDE Secondary Bus Master Descriptor Table Pointer Register Byte 3 (IDESBMDTPR3)—Offset Fh

This register implements the Byte 3 of the standard IDE Secondary Bus Master Descriptor Table Pointer register in the IDE Bus Master Block. The descriptor table pointer is used for bus master operation in the secondary channel. Usage notes: The Secondary IDE Channel is permanently disabled. Access attributes are maintained to satisfy test requirement. No bus master functionality is implemented behind the register. Reset condition: Host reset. Non-sticky.

Type: I/O Register
(Size: 8 bits)

BAR and Offset: [IDE_HOST_BMIOBAR] + Fh

Default: 00h

IDE_HOST_BMIOBAR Type: PCI Configuration Register (Size: 32 bits)
IDE_HOST_BMIOBAR Reference: [B:0, D:27, F:2] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Descriptor Table Pointer Byte 3 (DTPB3):** Byte 3 of the Descriptor Table pointer.

54.16 Sideband Registers—KT (Host)

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

54.16.1 KT Host Interrupt Pin Register (KTHIPINR)—Offset 0h

This register provides for BIOS to specify which interrupt pin KT shall use in the Host root space when generating an interrupt in the PCI legacy mode.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xf4] + 0h
Host Memory Space: SBREG_BAR + 0xf40000 + 0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
7:0	0x0 RW/O	**Interrupt Pin (IPIN):** BIOS writes to this field once to specify which interrupt pin KT shall use. After written once, this register will become read-only. This field shall be shadowed into the Interrupt Pin register in the PCI header of the KT Host PCI function. Value Decoding • 00h The function does NOT use an interrupt pin. • 01h INTA • 02h INTB • 03h INTC • 04h INTD • 05h - FFh Reserved Reset condition: Host side reset. Non-sticky.

54.16.2 BIOS KT Host PCI Function Disable Register (BKTHDISR)—Offset 4h

This register provides for BIOS to enable or disable the KT Host PCI function.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xf4] + 4h
Host Memory Space: SBREG_BAR + 0xf40000 + 4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
0	0x0 RW	**Host PCI Function Disable (HDIS):** BIOS sets this bit to disable the KT Host PCI function. BIOS clears this bit to enable the KT Host PCI function. Reset condition: Host side reset. Non-sticky.

54.17 Sideband Registers—IDE (Host)

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

54.17.1 IDE Host Interrupt Pin Register (IDEHIPINR)—Offset 0h

This register provides for BIOS to specify which interrupt pin IDE shall use in the Host root space when generating an interrupt in the PCI legacy mode.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xf4] + 0h
Host Memory Space: SBREG_BAR + 0xf40000 + 0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
7:0	0x0 RW/O	**Interrupt Pin (IPIN):** BIOS writes to this field once to specify which interrupt pin IDE shall use. After written once, this register will become read-only. This field shall be shadowed into the Interrupt Pin register in the PCI header of the IDE Host PCI function. Value Decoding • 00h The function does NOT use an interrupt pin. • 01h INTA • 02h INTB • 03h INTC • 04h INTD • 05h - FFh Reserved Reset condition: Host side reset. Non-sticky.

54.17.2 BIOS IDE Host PCI Function Disable Register (BIDEHDISR)—Offset 4h

This register provides for BIOS to enable or disable the IDE Host PCI function.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xf4] + 4h
Host Memory Space: SBREG_BAR + 0xf40000 + 4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Not implemented. Hardwired to 0.
0	0x0 RW	**Host PCI Function Disable (HDIS):** BIOS sets this bit to disable the IDE Host PCI function. BIOS clears this bit to enable the IDE Host PCI function. Reset condition: Host side reset. Non-sticky.

§ §

55 eMMC Controller - B0, D28, F0

55.1 Introduction and Index

The host-accessible registers for the eMMC Controller are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

55.1.1 Host Memory Space—BAR or BAR1

An index of the registers that are accessible in Host Memory Space is shown here.

Table 55-1. Summary of Memory Mapped I/O Registers—BAR or BAR1 (Sheet 1 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
eMMC Registers			
0	4	00000000	"SDMA System Address Register/Argument2 Register (SDMASYSADDR)—Offset 0h" on page 2599
4	2	0000	"BlockSize Register (BLOCKSIZE)—Offset 4h" on page 2599
6	2	0000	"BlockCount Register (BLOCKCOUNT)—Offset 6h" on page 2599
8	4	00000000	"Argument1 Register (ARGUMENT1)—Offset 8h" on page 2600
C	2	0000	"TransferMode Register (TRANSFERMODE)—Offset Ch" on page 2600
E	2	0000	"Command Register (COMMAND)—Offset Eh" on page 2600
10	4	00000000	"Response Register (RESPONSE1)—Offset 10h" on page 2601
14	2	0000	"Response Register (RESPONSE2)—Offset 14h" on page 2602
16	2	0000	"Response Register (RESPONSE3)—Offset 16h" on page 2602
18	2	0000	"Response Register (RESPONSE4)—Offset 18h" on page 2602
1A	2	0000	"Response Register (RESPONSE5)—Offset 1Ah" on page 2602
1C	2	0000	"Response Register (RESPONSE6)—Offset 1Ch" on page 2603
1E	2	0000	"Response Register (RESPONSE7)—Offset 1Eh" on page 2603
20	4	00000000	"Buffer DataPort Register (DATAPORT)—Offset 20h" on page 2603
24	4	00000000	"PresentState Register (PRESENTSTATE)—Offset 24h" on page 2604
28	1	00	"HostControl1 Register (HOSTCONTROL1)—Offset 28h" on page 2606
29	1	00	"PowerControl Register (POWERCONTROL)—Offset 29h" on page 2607
2A	1	80	"BlockGapControl Register (BLOCKGAPCONTROL)—Offset 2Ah" on page 2607
2B	1	00	"Wakeup Control Register (WAKEUPCONTROL)—Offset 2Bh" on page 2608
2C	2	0000	"Clock Control Register (CLOCKCONTROL)—Offset 2Ch" on page 2609
2E	1	00	"Timeout Control Register (TIMEOUTCONTROL)—Offset 2Eh" on page 2610
2F	1	00	"Software Reset Register (SOFTWARERESET)—Offset 2Fh" on page 2610
30	2	0000	"Normal Interrupt Status Register (NORMALINTRSTS)—Offset 30h" on page 2611
32	2	0000	"ErrorInterruptStatus Register (ERRORINTRSTS)—Offset 32h" on page 2612
34	2	0000	"Normal Interrupt Status Enable Register (NORMALINTRSTSENA)—Offset 34h" on page 2613
36	2	0000	"Error Interrupt Status Enable Register (ERRORINTRSTSENA)—Offset 36h" on page 2614
38	2	0000	"Normal Interrupt Signal Enable Register (NORMALINTRSIGENA)—Offset 38h" on page 2615
3A	2	0000	"Error Interrupt Signal Enable Register (ERRORINTRSIGENA)—Offset 3Ah" on page 2616
3C	2	0000	"Auto CMD12 Error Status Register (AUTOCMDERRSTS)—Offset 3Ch" on page 2617
3E	2	0000	"Host Control2 Register (HOSTCONTROL2)—Offset 3Eh" on page 2618
40	8	80000007F76F64B2	"Capabilities Register (CAPABILITIES)—Offset 40h" on page 2619

Table 55-1. Summary of Memory Mapped I/O Registers—BAR or BAR1 (Sheet 2 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
48	8	0000000000000000	"Maximum Current Capabilities Register (MAXCURRENTCAP)—Offset 48h" on page 2621
50	2	0000	"Force Event REGISTER for AUTO CMD Error Status (FORCEEVENTFORAUTOCMDERRORSTATUS)—Offset 50h" on page 2621
52	2	0000	"Force Event Register for Error Interrupt Status (FORCEEVENTFORERRINTSTS)—Offset 52h" on page 2622
54	1	00	"ADMA Error Status Register (ADMAERRSTS)—Offset 54h" on page 2623
58	4	00000000	"ADMA System Address Register0&1 (ADMASYSADDR01)—Offset 58h" on page 2623
5C	2	0000	"ADMA System Address Register1 (ADMASYSADDR2)—Offset 5Ch" on page 2623
5E	2	0000	"ADMA System Address Register1 (ADMASYSADDR3)—Offset 5Eh" on page 2624
60	2	0003	"Preset Value Register for Initialization (PRESETVALUE0)—Offset 60h" on page 2624
62	2	0003	"Preset Value Register for Default Speed (PRESETVALUE1)—Offset 62h" on page 2625
64	2	0003	"Preset Value Register for High Speed (PRESETVALUE2)—Offset 64h" on page 2625
66	2	0003	"Preset Value Register for SDR12 (PRESETVALUE3)—Offset 66h" on page 2626
68	2	0002	"Preset Value Register for SDR25 (PRESETVALUE4)—Offset 68h" on page 2626
6A	2	0001	"Preset Value Register for SDR50 (PRESETVALUE5)—Offset 6Ah" on page 2627
6C	2	0000	"Preset Value Register for SDR104 (PRESETVALUE6)—Offset 6Ch" on page 2627
6E	2	0002	"Preset Value Register for DDR50 (PRESETVALUE7)—Offset 6Eh" on page 2628
70	4	00000000	"Boot Timeout Control Register (BOOTTIMEOUTCNT)—Offset 70h" on page 2628
74	2	0000	"Preset Value Register for DDR50 (PRESETVALUE8)—Offset 74h" on page 2629
FC	2	0000	"Slot Interrupt Status Register (SLOTINTRSTS)—Offset FCh" on page 2629
FE	2	1002	"Host Controller Version Register (HOSTCONTROLLERVER)—Offset FEh" on page 2629
Extended eMMC Registers (Convergence Layer)			
804	4	00000800	"Software Latency Tolerance Reporting (SW_LTR_VAL)—Offset 804h" on page 2630
808	4	00000800	"Auto Latency Tolerance Reporting (AUTO_LTR_VAL)—Offset 808h" on page 2630
810	4	00000000	"Capabilities Bypass Control Register (CAP_BYPS)—Offset 810h" on page 2631
814	4	3001EF3C	"eMMC Capabilities Bypass Register1 (CAP_BYPS_REG1)—Offset 814h" on page 2632
818	4	04004000	"eMMC Capabilities Bypass Register2 (CAP_BYPS_REG2)—Offset 818h" on page 2634
81C	4	00000008	"D0i3 Control Register (REG_D0i3)—Offset 81Ch" on page 2635
820	4	00000400	"Front End Module Tx Command Path Delay Register (Tx_CMD_DLY)—Offset 820h" on page 2635
824	4	00000A18	"Front End Module Tx Data Path Delay Register1 (Tx_DATA_DLY_1)—Offset 824h" on page 2636
828	4	1C1C1C00	"Front End Module Tx Data Path Delay Register2 (Tx_DATA_DLY_2)—Offset 828h" on page 2637

Table 55-1. Summary of Memory Mapped I/O Registers—BAR or BAR1 (Sheet 3 of 3)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
82C	4	00000000	"Front End Module Rx Data Path Delay Register1 (Rx_CMD_DATA_DLY_1)—Offset 82Ch" on page 2638
830	4	00000000	"Front End Module Rx Strobe Path Delay Register (Rx_STROBE_CTRL_PATH)—Offset 830h" on page 2639
834	4	00000000	"Front End Module Rx Data Path Delay Register2 (Rx_CMD_DATA_DLY_2)—Offset 834h" on page 2640
838	4	00000001	"Master DLL Software Control Register (MASTER_DLL)—Offset 838h" on page 2641
840	4	00000000	"Auto Tuning Value (AUTO_TUNING)—Offset 840h" on page 2641
900	4	00000000	"Root Space Select (eMMC_ROOT_SPACE)—Offset 900h" on page 2642

55.2 Registers in Memory Space—BAR or BAR1

The eMMC operates in either PCI Mode or ACPI Mode. By default all the devices are defined as PCI devices (PCI Mode).

To change a device to an ACPI device (ACPI Mode), it first needs to be enumerated and assigned a BAR. Once this is done, it is possible to configure the device to be an ACPI device. Its address shall be the configured BAR address.

55.2.1 SDMA System Address Register/Argument2 Register (SDMASYSADDR)—Offset 0h

This register contains concatenates reg_sdmasysaddrlo and reg_sdmasysaddrhi

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 0h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**sdma_sysaddress:** Refer to reg_sdmasysaddrlo and reg_sdmasysaddrhi

55.2.2 BlockSize Register (BLOCKSIZE)—Offset 4h

This register is used to configure the number of bytes in a data block

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 4h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**RSVD0:** Reserved
14:12	0x0 RW	**sdma_bufboundary:** This Field specifies DMA Buffer Boundary
11:0	0x0 RW	**xfer_blocksize:** This Field specifies Block Size for Data Transfers

55.2.3 BlockCount Register (BLOCKCOUNT)—Offset 6h

This register is used to configure the number of data blocks

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 6h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**xfer_blockcount:** This Register specifies Block Size for Data Transfers

55.2.4 Argument1 Register (ARGUMENT1)—Offset 8h

This register contains concatenates argument1lo and argument1hi registers to result SD Command Argument

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 8h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**command_argument1:** refer t oreg_argument1lo and reg_argument1hi.

55.2.5 TransferMode Register (TRANSFERMODE)—Offset Ch

This register is used to control the operations of data transfers

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + Ch

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**RSVD0:** Reserved
5	0x0 RW	**xfermode_multiblksel:** This bit enables multiple block data transfers.
4	0x0 RW	**xfermode_dataxferdir:** This bit defines the direction of data transfers.
3:2	0x0 RW	**xfermode_autocmdena:** This field determines use of auto command functions.
1	0x0 RW	**xfermode_blkcntena:** This bit is used to enable the Block count register, which is only relevant for multiple block transfers
0	0x0 RW	**xfermode_dmaenable:** '1' to enable DMA,

55.2.6 Command Register (COMMAND)—Offset Eh

This register is used to program the Command for host controller

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + Eh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**RSVD0:** Reserved
13:8	0x0 RW	**command_cmdindex:** This bit shall be set to the command number (CMD0-63, ACMD0-63).

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RW	**command_cmdtype:** This bit is used for select different command types.
5	0x0 RW	**command_datapresent:** This bit is used to checking whether data present or not.
4	0x0 RW	**command_indexchkena:** This bit is used to enable/disable Command Index checking.
3	0x0 RW	**command_crcchkena:** This bit is used to enable/disable CRC checking.
2	0x0 RO	**RSVD1:** Reserved
1:0	0x0 RW	**command_responsetype:** Response Type Select.

55.2.7 Response Register (RESPONSE1)—Offset 10h

This register is used to store responses from SD Cards (concatinates response0 and response1 registers)

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 10h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.8 Response Register (RESPONSE2)—Offset 14h

This register is used to store responses from SD Cards

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [BAR or BAR1] + 14h

Default: 0000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.9 Response Register (RESPONSE3)—Offset 16h

This register is used to store responses from SD Cards

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [BAR or BAR1] + 16h

Default: 0000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.10 Response Register (RESPONSE4)—Offset 18h

This register is used to store responses from SD Cards

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [BAR or BAR1] + 18h

Default: 0000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.11 Response Register (RESPONSE5)—Offset 1Ah

This register is used to store responses from SD Cards

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [BAR or BAR1] + 1Ah

Default: 0000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.12 Response Register (RESPONSE6)—Offset 1Ch

This register is used to store responses from SD Cards

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 1Ch

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.13 Response Register (RESPONSE7)—Offset 1Eh

This register is used to store responses from SD Cards

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 1Eh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO	**command_response:** R[] refers to a bit range within the response data as transmitted on the SD Bus, REP[] refers to a bit

55.2.14 Buffer DataPort Register (DATAPORT)—Offset 20h

This register is used to access internal buffer

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 20h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**sdhcdmactrl_piobufrddata:** The Host Controller Buffer can be accessed through this 32-bit Data Port Register.

55.2.15 PresentState Register (PRESENTSTATE)—Offset 24h

The Host Driver can get status of the Host Controller from this 32-bit read-only register

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 24h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:29	0x0 RO	**RSVD0:** Reserved
28	0x0 RO	**sdif_dat7in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
27	0x0 RO	**sdif_dat6in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
26	0x0 RO	**sdif_dat5in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
25	0x0 RO	**sdif_dat4in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
24	0x0 RO	**sdif_cmdin_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
23	0x0 RO	**sdif_dat3in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
22	0x0 RO	**sdif_dat2in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
21	0x0 RO	**sdif_dat1in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
20	0x0 RO	**sdif_dat0in_dsync:** This status is used to check DAT line level to recover from errors, and for debugging.
19	0x0 RO	**sdif_wp_dsync:** The Write Protect Switch is supported for memory and combo cards.
18	0x0 RO	**sdif_cd_n_dsync:** This bit reflects the inverse value of the SDCD# pin.
17	0x0 RO	**sdhccarddet_statestable_dsync:** This bit is used for testing.
16	0x0 RO	**sdhccarddet_inserted_dsync:** This bit indicates whether a card has been inserted.
15:12	0x0 RO	**RSVD1:** Reserved
11	0x0 RO	**sdhcdmactrl_piobufrdena:** This status is used for non-DMA read transfers. This read only flag indicates that valid data exists in the host side buffer status.
10	0x0 RO	**sdhcdmactrl_piobufwrena:** This status is used for non-DMA write transfers. This read only flag indicates if space is available for write data.
9	0x0 RO	**sdhcdmactrl_rdxferactive:** This status is used for detecting completion of a read transfer.
8	0x0 RO	**sdhcdmactrl_wrxferactive:** This status indicates a write transfer is active.
7:4	0x0 RO	**RSVD2:** Reserved

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RO	**sdhcsdctrl_retuningreq_dsync:** Host Controller may request Host Driver to execute re-tuning sequence by setting this bit.
2	0x0 RO	**sdhcdmactrl_datalineactive:** This bit indicates whether one of the DAT line on SD bus is in use.
1	0x0 RO	**presentstate_inhibitdat:** This status bit is generated if either the DAT Line Active or the Read transfer Active is set to 1.
0	0x0 RO	**presentstate_inhibitcmd:** If this bit is 0, it indicates the CMD line is not in use and the HC can issue a SD command using the CMD line. This bit is set immediately after the Command register (00Fh) is written. This bit is cleared when the command response is received.

55.2.16 HostControl1 Register (HOSTCONTROL1)—Offset 28h

This register is used to program DMA modes, LED Control, Data Transfer Width, High Speed Enable, Card detect test level and signal selection.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [BAR or BAR1] + 28h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**hostctrl1_cdsigselect:** This bit selects source for card detection.
6	0x0 RW	**hostctrl1_cdtestlevel:** This bit is used for indicating whether card is inserted or not.
5	0x0 RW	**hostctrl1_extdatawidth:** This bit controls 8-bit bus width mode for embedded device.
4:3	0x0 RW	**hostctrl1_dmaselect:** One of supported DMA modes can be selected.
2	0x0 RW	**hostctrl1_highspeedena:** This bit is used for setting speed mode.
1	0x0 RW	**hostctrl1_datawidth:** This bit selects the data width of the HC.
0	0x0 RW	**hostctrl1_ledcontrol:** This bit is used to caution the user not to remove the card while the SD card is being accessed.

55.2.17 PowerControl Register (POWERCONTROL)—Offset 29h

This register is used to program the SD Bus power and voltage level

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [BAR or BAR1] + 29h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**RSVD0:** Reserved
4	0x0 RW	**emmc_hwreset:** Hardware reset signal is generated for eMMC card.
3:1	0x0 RW	**pwrctrl_sdbusvoltage:** By setting these bits, the HD selects the voltage level for the SD card.
0	0x0 RW	**pwrctrl_sdbuspower:** This bit is used detect whether power is on or off.

55.2.18 BlockGapControl Register (BLOCKGAPCONTROL)—Offset 2Ah

This register is used to program the block gap request, read wait control and interrupt at block gap

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 80h

BAR and Offset: [BAR or BAR1] + 2Ah

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**blkgapctrl_bootackena:** To check for the boot acknowledge in boot operation.
6	0x0 RW	**blkgapctrl_altbootmode:** To start boot code access in alternative mode.
5	0x0 RW	**blkgapctrl_bootenable:** To start boot code access. • '0' To stop boot code access • '1' To start boot code access
4	0x0 RW	**blkgapctrl_spimode:** SPI mode enable bit. • '0' SD Mode • '1' SPI Mode
3	0x0 RW	**blkgapctrl_interrupt:** This bit is valid only in 4-bit mode of the SDIO card and selects a sample point in the interrupt cycle.
2	0x0 RW	**blkgapctrl_rdwaitctrl:** The read wait function is optional for SDIO cards.
1	0x0 RW	**blkgapctrl_continue:** This bit is used to restart a transaction which was stopped using the Stop At Block Gap Request.
0	0x0 RW	**blkgapctrl_stopatblkgap:** This bit is used to stop executing a transaction at the next block gap for non- DMA,SDMA and ADMA transfers.

55.2.19 Wakeup Control Register (WAKEUPCONTROL)—Offset 2Bh

This register is used to program the wakeup functionality

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [BAR or BAR1] + 2Bh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**wkupctrl_cardremoval:** This bit enables wakeup event via Card Insertion assertion in the Normal Interrupt Status register.
1	0x0 RW	**wkupctrl_cardinsertion:** This bit enables wakeup event via Card Insertion assertion in the Normal Interrupt Status register.
0	0x0 RW	**wkupctrl_cardinterrupt:** This bit enables wakeup event via Card Interrupt assertion in the Normal Interrupt Status register.

55.2.20 Clock Control Register (CLOCKCONTROL)—Offset 2Ch

This register is used to program the Clock frequency select, generator select, Clock enable, Internal Clock state fields

Type: Memory Mapped I/O Register (Size: 16 bits)

BAR and Offset: [BAR or BAR1] + 2Ch

Default: 0000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**clkctrl_sdclkfreqsel:** This register is used to select the frequency of the SDCLK pin.
7:6	0x0 RW	**clkctrl_sdclkfreqsel_upperbits:** Bit 07-06 is assigned to bit 09-08 of clock divider in SDCLK Frequency Select
5	0x0 RW	**clkctrl_clkgensel:** This bit is used to select the clock generator mode in SDCLK Frequency Select.
4:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**clkctrl_sdclkena:** This bit enables/disables SD Clock. • '0' Disable • '1' Enable
1	0x0 RO	**sdhcclkgen_intclkstable_dsync:** This bit is set to 1 when SD clock is stable after writing to Internal Clock Enable in this register to 1.
0	0x0 RW	**clkctrl_intclkena:** This bit enables setting of internal clock. • '0' Stop • '1' Oscillate

55.2.21 Timeout Control Register (TIMEOUTCONTROL)—Offset 2Eh

The register sets the Data Timeout counter value

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [BAR or BAR1] + 2Eh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**RSVD0:** Reserved
3:0	0x0 RW	**timeout_ctrvalue:** This value determines the interval by which DAT line time-outs are detected.

55.2.22 Software Reset Register (SOFTWARERESET)—Offset 2Fh

This register is used to program the software reset for data, command and for all.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [BAR or BAR1] + 2Fh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RW	**swreset_for_dat:** Only part of data circuit is reset. • '0' Work • '1' Reset
1	0x0 RW	**swreset_for_cmd:** Only part of command circuit is reset. • '0' Work • '1' reset.
0	0x0 RW	**swreset_for_all:** If this bit is set to 1, the SD card shall reset itself and must be re initialized by the HD.

55.2.23 Normal Interrupt Status Register (NORMALINTRSTS)—Offset 30h

This register gives the status of all the interrupts.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 30h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**reg_errorintrsts:** This bit is set If any of the bits in the Error Interrupt Status Register are set.
14	0x0 RW	**normalintrsts_bootcomplete:** This status is set if the boot operation gets terminated.
13	0x0 RW	**normalintrsts_rcvbootack:** This status is set if the boot acknowledge is received from device.
12	0x0 RO	**normalintrsts_retuningevent:** This status is set if Re-Tuning Request in the Present State register changes from 0 to 1.
11	0x0 RO	**normalintrsts_intc:** This status is set if INT_C is enabled and INT_C# pin is in low level. It is cleared by resetting the INT_C interrupt factor.
10	0x0 RO	**normalintrsts_intb:** This status is set if INT_B is enabled and INT_B# pin is in low level. It is cleared by resetting
9	0x0 RO	**normalintrsts_inta:** This status is set if INT_A is enabled and INT_A# pin is in low level. It is cleared by resetting
8	0x0 RO	**normalintrsts_cardintsts:** This status is set to generate Card Interrupt. • '0' No Card Interrupt • '1' Generate Card Interrupt
7	0x0 RW	**normalintrsts_cardremsts:** This status is set if the Card Inserted in the Present State register changes from 1 to 0.
6	0x0 RW	**normalintrsts_cardinssts:** This status is set if the Card Inserted in the Present State register changes from 0 to 1.
5	0x0 RW	**normalintrsts_bufrdready:** This status is set if the Buffer Read Enable changes from 0 to 1.
4	0x0 RW	**normalintrsts_bufwrready:** This status is set if the Buffer Write Enable changes from 0 to 1.
3	0x0 RW	**normalintrsts_dmainterrupt:** This status is set if the HC detects the Host DMA Buffer Boundary in the Block Size register.
2	0x0 RW	**normalintrsts_blkgapevent:** If the Stop At Block Gap Request in the BlockGap Control Register is set, this bit is set.
1	0x0 RW	**normalintrsts_xfercomplete:** This bit is set when a read / write transaction is completed.
0	0x0 RW	**normalintrsts_cmdcomplete:** This bit is set when we get the end bit of the command response.

55.2.24 ErrorInterruptStatus Register (ERRORINTRSTS)—Offset 32h

This register gives the status of the error interrupts.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 32h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**RSVD0:** Reserved
12	0x0 RW	**errorintrsts_hosterror:** Occurs when detecting Host ERROR
11:10	0x0 RO	**RSVD1:** Reserved
9	0x0 RW	**errorintrsts_admaerror:** This bit is set when the Host Controller detects errors during ADMA based data transfer.
8	0x0 RW	**errorintrsts_autocmderror:** This bit is set when detecting that one of the bits D00-D04 in Auto CMD Error Status register has changed from 0 to 1.
7	0x0 RW	**errorintrsts_currlimiterror:** If this bit is 1, it means that the HC is not supplying power to SD card due to some failure. Reading 0 means that the HC is supplying power and no error has occurred.
6	0x0 RW	**errorintrsts_dataendbiterror:** Occurs when detecting 0 at the end bit position of read data which uses the DAT line or the end bit position of the CRC status.
5	0x0 RW	**errorintrsts_datacrcerror:** Occurs when detecting CRC error when transferring read data which uses the DAT line or when detecting the Write CRC Status having a value of other than 010.
4	0x0 RW	**errorintrsts_datatimeouterror:** This status is set if Data Timeout error occurs.
3	0x0 RW	**errorintrsts_cmdindexerror:** Occurs if a Command Index error occurs in the Command Response.
2	0x0 RW	**errorintrsts_cmdendbiterror:** Occurs when detecting that the end bit of a command response is 0.
1	0x0 RW	**errorintrsts_cmdcrcerror:** This bit is set when Command CRC Error is generated. • '0' No Error • '1' CRC Error
0	0x0 RW	**errorintrsts_cmdtimeouterror:** This bit is set if no response is returned within 64 SDCLK cycles from the end bit of the command.

55.2.25 Normal Interrupt Status Enable Register (NORMALINTRSTSENA)—Offset 34h

This register is used to enable the normal interrupt status register fields.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 34h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**normalintrsts_enableregbit15:** The HC shall control error Interrupts using the Error Interrupt Status Enable register.
14	0x0 RW	**normalintrsts_enableregbit14:** This status is set if the boot operation gets terminated.
13	0x0 RW	**normalintrsts_enableregbit13:** This status is set if the boot acknowledge is received from device.
12	0x0 RW	**normalintrsts_enableregbit12:** This status is set if Re-Tuning Request in the Present State register changes from 0 to 1.
11	0x0 RW	**normalintrsts_enableregbit11:** If this bit is set to 0, the Host Controller shall clear the interrupt request to the System.
10	0x0 RW	**normalintrsts_enableregbit10:** If this bit is set to 0, the Host Controller shall clear the interrupt request to the System.
9	0x0 RW	**normalintrsts_enableregbit9:** If this bit is set to 0, the Host Controller shall clear the interrupt request to the System.
8	0x0 RW	**sdhcregset_cardintstsena:** If this bit is set to 0, the HC shall clear Interrupt request to the System. The Card Interrupt detection is stopped when this bit is cleared and restarted when this bit is set to 1.
7	0x0 RW	**sdhcregset_cardremstsena:** This status is set if the Card Inserted in the Present State register changes from 1 to 0.
6	0x0 RW	**sdhcregset_cardinsstsena:** This status is set if the Card Inserted in the Present State register changes from 0 to 1.
5	0x0 RW	**normalintrsts_enableregbit5:** This status is set if the Buffer Read Enable changes from 0 to 1.
4	0x0 RW	**normalintrsts_enableregbit4:** This status is set if the Buffer Write Enable changes from 0 to 1.
3	0x0 RW	**normalintrsts_enableregbit3:** This status is set if the HC detects the Host DMA Buffer Boundary in the Block Size regiser.
2	0x0 RW	**normalintrsts_enableregbit2:** If the Stop At Block Gap Request in the BlockGap Control Register is set, this bit is set.
1	0x0 RW	**normalintrsts_enableregbit1:** This bit is set when a read / write transaction is completed.
0	0x0 RW	**normalintrsts_enableregbit0:** This bit is set when we get the end bit of the command response.

55.2.26 Error Interrupt Status Enable Register (ERRORINTRSTSENA)—Offset 36h

This register is used to enable the Error Interrupt Status register fields

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 36h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**RSVD0:** Reserved
12	0x0 RO	**errorintrsts_enableregbit12:** Occurs when detecting ERROR in m_hresp(dma transaction)
11	0x0 RO	**RSVD1:** Reserved
10	0x0 RW	**errorintrsts_enableregbit10:** This status is set if INT_B is enabled and INT_B# pin is in low level. It is cleared by resetting
9	0x0 RW	**errorintrsts_enableregbit9:** This bit is set when the Host Controller detects errors during ADMA based data transfer.
8	0x0 RW	**errorintrsts_enableregbit8:** This bit is set when detecting that one of the bits D00-D04 in Auto CMD Error Status register has changed from 0 to 1.
7	0x0 RW	**errorintrsts_enableregbit7:** If this bit is 1, it means that the HC is not supplying power to SD card due to some failure. Reading 0 means that the HC is supplying power and no error has occurred.
6	0x0 RW	**errorintrsts_enableregbit6:** Occurs when detecting 0 at the end bit position of read data which uses the DAT line or the end bit position of the CRC status.
5	0x0 RW	**errorintrsts_enableregbit5:** Occurs when detecting CRC error when transferring read data which uses the DAT line or when detecting the Write CRC Status having a value of other than 010.
4	0x0 RW	**errorintrsts_enableregbit4:** This status is set if Data Timeout error occurs.
3	0x0 RW	**errorintrsts_enableregbit3:** Occurs if a Command Index error occurs in the Command Response.
2	0x0 RW	**errorintrsts_enableregbit2:** Occurs when detecting that the end bit of a command response is 0.
1	0x0 RW	**errorintrsts_enableregbit1:** This bit is set when Command CRC Error is generated.
0	0x0 RW	**errorintrsts_enableregbit0:** This bit is set if no response is returned within 64 SDCLK cycles from the end bit of the command.

55.2.27 Normal Interrupt Signal Enable Register (NORMALINTRSIGENA)—Offset 38h

This register is used to enable the Normal Interrupt Signal register.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 38h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**normalintrsts_enableregbit15:** The HD shall control error Interrupts using the Error Interrupt Signal Enable register.
14	0x0 RW	**normalintrsts_enableregbit14:** Boot Terminate Interrupt Signal Enable
13	0x0 RW	**normalintrsts_enableregbit13:** Boot ack rcv Signal Enable
12	0x0 RW	**normalintrsts_enableregbit12:** Re-Tuning Event Signal Enable
11	0x0 RW	**normalintrsts_enableregbit11:** INT_C Signal Enable
10	0x0 RW	**normalintrsts_enableregbit10:** INT_B Signal Enable
9	0x0 RW	**normalintrsts_enableregbit9:** INT_A Signal Enable
8	0x0 RW	**sdhcregset_cardintstsena:** Card Interrupt Signal Enable
7	0x0 RW	**sdhcregset_cardremstsena:** Card Removal Signal Enable
6	0x0 RW	**sdhcregset_cardinsstsena:** Card Insertion Signal Enable
5	0x0 RW	**normalintrsts_enableregbit5:** Buffer Read Ready Signal Enable
4	0x0 RW	**normalintrsts_enableregbit4:** Buffer Write Ready Signal Enable
3	0x0 RW	**normalintrsts_enableregbit3:** DMA Interrupt Signal Enable
2	0x0 RW	**normalintrsts_enableregbit2:** Block Gap Event Signal Enable
1	0x0 RW	**normalintrsts_enableregbit1:** Transfer Complete Signal Enable
0	0x0 RW	**normalintrsts_enableregbit0:** Command Complete Signal Enable

55.2.28 Error Interrupt Signal Enable Register (ERRORINTRSIGENA)—Offset 3Ah

This register is used to enable Error Interrupt Signal register.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 3Ah

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**RSVD0:** Reserved
12	0x0 RO	**errorintrsig_enableregbit12:** Target Response Error Signal Enable
11	0x0 RO	**RSVD1:** Reserved
10	0x0 RW	**errorintrsig_enableregbit10:** Tuning Error Signal Enable
9	0x0 RW	**errorintrsig_enableregbit9:** ADMA Error Signal Enable
8	0x0 RW	**errorintrsig_enableregbit8:** Auto CMD Error Signal Enable
7	0x0 RW	**errorintrsig_enableregbit7:** Current Limit Error Signal Enable
6	0x0 RW	**errorintrsig_enableregbit6:** Data End Bit Error Signal Enable
5	0x0 RW	**errorintrsig_enableregbit5:** Data CRC Error Signal Enable
4	0x0 RW	**errorintrsig_enableregbit4:** Data Timeout Error Signal Enable
3	0x0 RW	**errorintrsig_enableregbit3:** Command Index Error Signal Enable
2	0x0 RW	**errorintrsig_enableregbit2:** Command End Bit Error Signal Enable
1	0x0 RW	**errorintrsig_enableregbit1:** Command CRC Error Signal Enable
0	0x0 RW	**errorintrsig_enableregbit0:** Command Timeout Error Signal Enable

55.2.29 Auto CMD12 Error Status Register (AUTOCMDERRSTS)—Offset 3Ch

This register is used to indicate CMD12 response error of Auto CMD12 and CMD23 response error of Auto CMD 23.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 3Ch

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7	0x0 RO	**autocmderrsts_nexterror:** Setting this bit to 1 means CMD_wo_DAT is not executed due to an Auto CMD12 error(D04- D01) in this register. This bit is set to 0 when Auto CMD Error is generated by Auto CMD23
6:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RO	**autocmderrsts_indexerror:** Occurs if the Command Index error occurs in response to a command.
3	0x0 RO	**autocmderrsts_endbiterror:** Occurs when detecting that the end bit of command response is 0.
2	0x0 RO	**autocmderrsts_crcerror:** Occurs when detecting a CRC error in the command response.
1	0x0 RO	**autocmderrsts_timeouterror:** Occurs if the no response is returned within 64 SDCLK cycles from the end bit of the command.
0	0x0 RO	**autocmderrsts_notexecerror:** Setting this bit to 1 means the HC cannot issue Auto CMD12 to stop memory multiple block transfer due to some error.

55.2.30 Host Control2 Register (HOSTCONTROL2)—Offset 3Eh

This register is used to program UHS Select Mode, UHS Select Mode, Driver Strength Select, Execute Tuning, Sampling Clock Select, Asynchronous Interrupt Enable and Preset value enable.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 3Eh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**hostctrl2_presetvalueenable:** This bit enables the functions defined in the Preset Value registers.
14	0x0 RW	**hostctrl2_asynchintrenable:** This bit can be set to 1 if a card support asynchronous interrupt and Asynchronous Interrupt Support is set to 1 in the Capabilities register.
13:10	0x0 RO	**RSVD0:** Reserved
9	0x0 RW	**hostctrl2_driverstrength_bit2:** This is the programmed Drive Strength output and Bit[2] of the sdhccore_drivestrength value.
8	0x0 RO	**RSVD1:** Reserved
7	0x0 RW	**hostctrl2_samplingclkselect:** This bit is set by tuning procedure when Execute Tuning is cleared.
6	0x0 RW	**hostctrl2_executetuning:** This bit is set to 1 to start tuning procedure and automatically cleared when tuning procedure is completed.
5:4	0x0 RW	**hostctrl2_driverstrength:** Host Controller output driver in 1.8V signaling is selected by this bit.
3	0x0 RW	**hostctrl2_1p8vsignallingena:** This bit controls voltage regulator for I/O cell.
2:0	0x0 RW	**hostctrl2_uhsmodeselect:** This field is used to select one of UHS-I modes and effective when 1.8V Signaling Enable is set to 1.

55.2.31 Capabilities Register (CAPABILITIES)—Offset 40h

This register provides the host driver with information specific to the host controller implementation.

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 80000007F76F64B2h

BAR and Offset: [BAR or BAR1] + 40h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
63	0x1 RO	**corecfg_hs400support:** This field indicates whether HS400 is supported or not.
62:58	0x0 RO	**rsvd0:** Reserved Field
57	0x0 RO	**corecfg_spiblkmode:** This field indicates whether SPI Block Mode is supported or not.
56	0x0 RO	**corecfg_spisupport:** This field indicates whether SPI Mode is supported or not.
55:48	0x0 RO	**corecfg_clockmultiplier:** This field indicates clock multiplier value of programmable clock generator.
47:46	0x0 RO	**corecfg_retuningmodes:** This field defines the re-tuning capability of a Host Controller.
45	0x0 RO	**corecfg_tuningforsdr50:** If this bit is set to 1, this Host Controller requires tuning to operate SDR50.
44	0x0 RO	**rsvd1:** Reserved Field
43:40	0x0 RO	**corecfg_retuningtimercnt:** This field indicates an initial value of the Re-Tuning Timer for Re-Tuning Mode 1 to 3.
39	0x0 RO	**corecfg_type4support:** This bit indicates support of Type 4 Driver.
38	0x0 RO	**corecfg_ddriversupport:** This bit indicates support of Driver Type D for 1.8 Signaling.
37	0x0 RO	**corecfg_cdriversupport:** This bit indicates support of Driver Type C for 1.8 Signaling.
36	0x0 RO	**corecfg_adriversupport:** This bit indicates support of Driver Type A for 1.8 Signaling.
35	0x0 RO	**rsvd2:** Reserved Field
34	0x1 RO	**corecfg_ddr50support:** This bit indicates whether DDR50 is supported.
33	0x1 RO	**corecfg_sdr104support:** This bit indicates whether SDR104 is supported.SDR104 requires tuning.
32	0x1 RO	**corecfg_sdr50support:** This bit indicates whether SDR50 is supported.
31:30	0x3 RO	**corecfg_slottype:** This field indicates usage of a slot by a specific Host System
29	0x1 RO	**corecfg_asynchintrsupport:** Asynchronous Interrupt Support

Bit Range	Default & Access	Field Name (ID): Description
28	0x1 RO	**corecfg_64bitsupport:** This bit indicates whether the HC supports 64bit System Bus
27	0x0 RO	**rsvd3:** Reserved Field
26	0x1 RO	**corecfg_1p8voltsupport:** This bit indicates whether the HC supports 1.8V.
25	0x1 RO	**corecfg_3p0voltsupport:** This bit indicates whether the HC supports 3.0V.
24	0x1 RO	**corecfg_3p3voltsupport:** This bit indicates whether the HC supports 3.3V.
23	0x0 RO	**corecfg_suspressupport:** This bit indicates whether the HC supports Suspend/Resume functionality.
22	0x1 RO	**corecfg_sdmasupport:** This bit indicates whether the HC is capable of using DMA to transfer data between system memory and the HC directly.
21	0x1 RO	**corecfg_highspeedsupport:** This bit indicates whether the HC and the Host System support High Speed mode.
20	0x0 RO	**rsvd4:** Reserved Field
19	0x1 RO	**corecfg_adma2support:** '0'ADMA2 Not Supported
18	0x1 RO	**corecfg_8bitsupport:** This bit indicates whether the Host Controller is capable of using 8-bit bus width mode.
17:16	0x3 RO	**corecfg_maxblklength:** This value indicates the maximum block size that the HD can read and write to the buffer in the HC.
15:8	0x64 RO	**corecfg_baseclkfreq:** 6-bit Base Clock Frequency
7	0x1 RO	**corecfg_timeoutclkunit:** This bit shows the unit of base clock frequency used to detect Data Timeout Error.
6	0x0 RO	**rsvd5:** Reserved Field
5:0	0x32 RO	**corecfg_timeoutclkfreq:** This bit shows the base clock frequency used to detect Data Timeout Error.

55.2.32 Maximum Current Capabilities Register (MAXCURRENTCAP)—Offset 48h

This register indicates maximum current capability for each voltage.

Type: Memory Mapped I/O Register (Size: 64 bits)

Default: 0000000000000000h

BAR and Offset: [BAR or BAR1] + 48h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
63:24	0x0 RO	**RSVD0:** Reserved
23:16	0x0 RO	**corecfg_maxcurrent1p8v:** Maximum Current for 1.8V
15:8	0x0 RO	**corecfg_maxcurrent3p0v:** Maximum Current for 3.0V
7:0	0x0 RO	**corecfg_maxcurrent3p3v:** Maximum Current for 3.3V

55.2.33 Force Event REGISTER for AUTO CMD Error Status (FORCEEVENTFORAUTOCMDERRORSTATUS)—Offset 50h

This register is not physically implemented, rather it is an address where Auto CMD Error Status register can be written.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 50h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7	0x0 RO	**forcecmdnotissuedbyautocmd12err:** Force Event for Command Not Issued by AUTO CMD12 Error
6:5	0x0 RO	**RSVD1:** Reserved
4	0x0 RO	**forceautocmdindexerr:** Force Event for AUTO CMD Index Error
3	0x0 RO	**forceautocmdendbiterr:** Force Event for AUTO CMD End Bit Error
2	0x0 RO	**forceautocmdcrcerr:** Force Event for AUTO CMD Timeout Error
1	0x0 RO	**forceautocmdtimeouterr:** Force Event for AUTO CMD Timeout Error
0	0x0 RO	**forceautocmdnotexec:** Force Event for AUTO CMD12 Not Executed

55.2.34 Force Event Register for Error Interrupt Status (FORCEEVENTFORERRINTSTS)—Offset 52h

This register is not physically implemented, rather it is an address where Error Interrupt Status register can be written.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 52h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**forcetuningerr:** Force Event for Tuning Error
9	0x0 RO	**forceadmaerr:** Force Event for ADMA Error • '0' no interrupt • '1' interrupt generated
8	0x0 RO	**forceautocmderr:** Force Event for Auto CMD Error • '0' no interrupt • '1' interrupt generated
7	0x0 RO	**forcecurrlimerr:** Force Event for Current Limit Error • '0' no interrupt • '1' interrupt generated
6	0x0 RO	**forcedatendbiterr:** Force Event for Data End Bit Error. • '0' no interrupt • '1' interrupt generated
5	0x0 RO	**forcedatcrcerr:** Force Event for Data CRC Error
4	0x0 RO	**forcedattimeouterr:** Force Event for Data Timeout Error • '0' no interrupt • '1' interrupt generated
3	0x0 RO	**forcecmdindexerr:** Force Event for Command Index Error
2	0x0 RO	**forcecmdendbiterr:** Force Event for Command End Bit Error • '0' no interrupt • '1' interrupt generated
1	0x0 RO	**forcecmdcrcerr:** Force Event for Command CRC Error
0	0x0 RO	**forcecmdtimeouterr:** Force Event for CMD Timeout Error • '0' No interrupt • '1' interrupt generated

55.2.35 ADMA Error Status Register (ADMAERRSTS)—Offset 54h

When the ADMA Error interrupt occurs, this register holds the ADMA State in ADMA Error States field and ADMA System Address holds address around the error descriptor.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [BAR or BAR1] + 54h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**RSVD0:** Reserved
2	0x0 RO	**admaerrsts_admalenmismatcherr:** ADMA Length Mismatch Error
1:0	0x0 RO	**admaerrsts_admaerrorstate:** This field indicates the state of ADMA when error is occurred during ADMA data transfer.

55.2.36 ADMA System Address Register0&1 (ADMASYSADDR01)—Offset 58h

This register contains the physical address used for ADMA data transfer.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 58h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**adma_sysaddress0:** This register holds byte address of executing command of the Descriptor table.

55.2.37 ADMA System Address Register1 (ADMASYSADDR2)—Offset 5Ch

This register contains the physical address used for ADMA data transfer.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 5Ch

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**adma_sysaddress2:** This register holds byte address of executing command of the Descriptor table.

55.2.38 ADMA System Address Register1 (ADMASYSADDR3)—Offset 5Eh

This register contains the physical address used for ADMA data transfer.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 5Eh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW	**adma_sysaddress3:** This register holds byte address of executing command of the Descriptor table.

55.2.39 Preset Value Register for Initialization (PRESETVALUE0)—Offset 60h

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0003h

BAR and Offset: [BAR or BAR1] + 60h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x3 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.40 Preset Value Register for Default Speed (PRESETVALUE1)—Offset 62h

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for Default Speed.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0003h

BAR and Offset: [BAR or BAR1] + 62h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x3 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.41 Preset Value Register for High Speed (PRESETVALUE2)—Offset 64h

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for High Speed.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0003h

BAR and Offset: [BAR or BAR1] + 64h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x3 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.42 Preset Value Register for SDR12 (PRESETVALUE3)—Offset 66h

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for SDR12.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0003h

BAR and Offset: [BAR or BAR1] + 66h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x3 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.43 Preset Value Register for SDR25 (PRESETVALUE4)—Offset 68h

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value SDR25.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0002h

BAR and Offset: [BAR or BAR1] + 68h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x2 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.44 Preset Value Register for SDR50 (PRESETVALUE5)—Offset 6Ah

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for SDR50.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0001h

BAR and Offset: [BAR or BAR1] + 6Ah

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x1 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.45 Preset Value Register for SDR104 (PRESETVALUE6)—Offset 6Ch

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for SDR 104.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 6Ch

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x0 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.46 Preset Value Register for DDR50 (PRESETVALUE7)—Offset 6Eh

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for DDR50.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0002h

BAR and Offset: [BAR or BAR1] + 6Eh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x2 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.47 Boot Timeout Control Register (BOOTTIMEOUTCNT)—Offset 70h

This is used to program the boot timeout value counter.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 70h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**boot_timeoutcnt:** This value determines the interval by which DAT line time-outs are detected during boot operation for eMMC4.4 card.

55.2.48 Preset Value Register for DDR50 (PRESETVALUE8)—Offset 74h

This register is used to read the SDCLK Frequency Select Value, Clock Generator Select Value, and Driver Strength Select Value for DDR50.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + 74h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**DriverStrengthSelectValue:** Driver Strength Select Value
13:11	0x0 RO	**RSVD0:** Reserved
10	0x0 RO	**ClockGeneratorSelectValue:** This bit is effective when Host Controller supports programmable clock
9:0	0x0 RO	**SDCLKFrequencySelectValue:** 10-bit preset value to set SDCLK Frequency Select in the Clock Control Register is described by a host system.

55.2.49 Slot Interrupt Status Register (SLOTINTRSTS)—Offset FCh

This register is used to read the interrupt signal for each slot.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [BAR or BAR1] + FCh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RO	**RSVD0:** Reserved
7:0	0x0 RO	**sdhchostif_slotintrsts:** These status bits indicate the logical OR of Interrupt signal and Wakeup signal for each slot.

55.2.50 Host Controller Version Register (HOSTCONTROLLERVER)—Offset FEh

This register is used to read the vendor version number and specification version number.

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 1002h

BAR and Offset: [BAR or BAR1] + FEh

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x10 RO	**SDHC_VENVERNUM:** This status is reserved for the vendor version number.
7:0	0x2 RO	**SpecificationVersionNumber:** This status indicates the Host Controller Spec. Version. The upper and lower 4-bits indicate the version.

55.2.51 Software Latency Tolerance Reporting (SW_LTR_VAL)—Offset 804h

Sets the Software Latency Tolerance Reporting fields.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000800h

BAR and Offset: [BAR or BAR1] + 804h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15	0x0 RW	**Snoop_Requirment:** If the Requirement (bit 15) is clear, that indicates that the device has no LTR requirement for this type of traffic (i.e. it can wait for service indefinitely). If the 10-bit latency value is zero it indicates that the device cannot tolerate any delay and needs the best possible service/response time.
14:13	0x0 RO	**Reserved (RSVD):** Reserved.
12:10	0x2 RW	**Snoop_latency_scale:** Support for codes 010 (1us) or 011 (32us) for Snoop Latency Scale (1us -) 32ms total span) only. Writes to this CSR which don't match those values will be dropped completely, next read will return previous value.
9:0	0x0 RW	**Snoop_value:** 10-bit latency value

55.2.52 Auto Latency Tolerance Reporting (AUTO_LTR_VAL)—Offset 808h

Sets the Auto Latency Tolerance Reporting fields.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000800h

BAR and Offset: [BAR or BAR1] + 808h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15	0x0 RW	**Snoop_Requirment:** If the Requirement (bit 15) is clear, that indicates that the device has no LTR requirement for this type of traffic (i.e. it can wait for service indefinitely). If the 10-bit latency value is zero it indicates that the device cannot tolerate any delay and needs the best possible service/response time.
14:13	0x0 RO	**Reserved_low:** Reserved_low
12:10	0x2 RW	**Snoop_latency_scale:** Support for codes 010 (1us) or 011 (32us) for Snoop Latency Scale (1us -) 32ms total span) only. Writes to this CSR which don't match those values will be dropped completely, next read will return previous value.
9:0	0x0 RW	**Snoop_value:** 10-bit latency value

55.2.53 Capabilities Bypass Control Register (CAP_BYPS)—Offset 810h

Capabilities Bypass Control register.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 810h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Reserved.
7:0	0x0 RW	**Enable_Cap_Bypass:** 8h5A Enable Capabilities Bypass. All other Capabilities Bypass Disable (using default values).

55.2.54 eMMC Capabilities Bypass Register1 (CAP_BYPS_REG1)—Offset 814h

eMMC Capabilities Bypass register 1

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 3001EF3Ch

BAR and Offset: [BAR or BAR1] + 814h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD):** Reserved.
29	0x1 RW	**hs400_support:** • 1: HS400 Mode Supported. • 0: HS400 Mode NOT Supported
28	0x1 RW	**timeout_clock_unit:** • 1b1 - to Select MHz Clock • 1b0 - to Select KHz Clock
27:22	0x200 RW	**timeout_clock_freq:** Timeout clock frequency
21	0x0 RW	**SPI_mode_support:** SPI Mode Support • 1b1 SPI Mode Supported • 1b0 SPI Mode Not Supported
20:17	0x0 RW	**timer_count:** Timer Count for Re-Tuning This is the Timer Count for Re-Tuning Timer for Re-Tuning Mode 1 to 3. Setting to 4b0 disables Re-Tuning Timer
16	0x1 RW	**tuning_for_SDR50:** Use Tuning for SDR50 • 1b1 Use Tuning • 1b0 Don’t use Tuning
15	0x1 RW	**ddr50_support:** • 1: DDR50 Mode Supported. • 0: DDR50 Mode NOT Supported
14	0x1 RW	**sdr104_support:** • 1: SDR104 Mode Supported. • 0: SDR104 Mode NOT Supported
13	0x1 RW	**sdr50_support:** • 1: SDR50 Mode Supported. • 0: SDR50 Mode NOT Supported
12:11	0x1 RW	**Slot_Type:** • 00 - Removable SD Card Slot. • 01 - Embedded Slot for One Device. • 10 - Shared Bus Slot. • 11 - Reserved
10	0x1 RW	**Async_Interrupt_Support:** • 1: Asynchronous Interrupt Supported. • 0: Asynchronous Interrupt NOT Supported
9	0x1 RW	**Sys_Addr_64bit_Support:** • 1 - Core supports 64-bit System Address Bus. • 0 - Core supports only 32-bit System Address Bus
8	0x1 RW	**Voltage_Support_1_8V:** • 1: 1.8V Supported. • 0: 1.8V NOT Supported

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Voltage_Support_3V:** • 1: 3.0V Supported. • 0: 3.0V NOT Supported
6	0x0 RW	**Voltage_Support_3_3V:** • 1: 3.3V Supported. • 0: 3.3V NOT Supported
5	0x1 RW	**Suspend_Resume_Support:** • 1: Suspend/Resume Supported. • 0: Suspend/Resume NOT Supported
4	0x1 RW	**SDMA_Support:** • 1: SDMA mode Supported. • 0: SDMA mode NOT Supported
3	0x1 RW	**High_Speed_Support:** • 1: HIGH_SPEED mode Supported. • 0: HIGH_SPEED mode NOT Supported
2	0x1 RW	**ADMA2_Support:** • 1: ADMA2 mode Supported. • 0: ADMA2 mode NOT Supported
1:0	0x0 RW	**Max_Burst_Length:** Maximum Block Length supported by the Core/Device. • 00: 512 (Bytes). • 01: 1024. • 10: 2048. • 11: Reserved

55.2.55 eMMC Capabilities Bypass Register2 (CAP_BYPS_REG2)—Offset 818h

eMMC Capabilities Bypass register 2

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 04004000h

BAR and Offset: [BAR or BAR1] + 818h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**Reserved (RSVD):** Reserved.
26:21	0x20 RW	**tuning_count_val:** Tuning Count Value Configures the Number of Taps (Phases) of the rxclk_in that is supported. The Tuning State machine uses this information to select one of the Taps (Phases) of the rxclk_in during the Tuning Procedure.
20	0x0 RW	**tuning_dis:** Disable the 1.5x Tuning count when calculating total tuning count. The internal tuning count will be set to the corecfg_Tuningcount when this signal is asserted
19	0x0 RW	**driver_type_4:** Driver Type 4 Support • 1b1 Supported • 1b0 NOT Supported
18	0x0 RW	**driver_type_D:** Driver Type D Support • 1b1 Supported • 1b0 NOT Supported
17	0x0 RW	**driver_type_C:** Driver Type C Support • 1b1 Supported • 1b0 NOT Supported
16	0x0 RW	**driver_type_A:** Driver Type A Support • 1b1 Supported • 1b0 NOT Supported
15	0x0 RO	**Reserved (RSVD):** Reserved.
14	0x1 RW	**support_8_bit_embedded:** 8-bit Support for Embedded Device • 1b1 Supported • 1b0 NOT Supported
13:8	0x0 RO	**Reserved (RSVD):** Reserved.
7:0	0x0 RW	**base_sd_clock:** Base Clock Frequency for SD Clock

55.2.56 D0i3 Control Register (REG_D0i3)—Offset 81Ch

D0i3 Control register

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000008h

BAR and Offset: [BAR or BAR1] + 81Ch

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RO	**Reserved (RSVD):** Reserved.
4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x1 RW/1C	**RestoreRequired:** When set (by HW), SW must restore state to the IP. The state may have been lost due to a reset or full power lost. SW clears the bit by writing a 1. This bit will be set on initial power up.
2	0x0 RW	**D0i3:** SW sets this bit to 1 to move the IP into the D0i3 state. Writing this bit to 0 will return the IP to the fully active D0 state (D0i0).
1	0x0 RO	**Interrupt_Request:** SW sets this bit to 1 to ask for an interrupt to be generated on completion of the command. SW must clear or set this on each write to this register. Not supported in SCS!
0	0x0 RO	**Cmd_In_Progress:** HW sets this bit on a 1-)0 or 0-)1 transition of bit [2]. While set, the other bits in this register are not valid and it is illegal for SW to write to any bit in this register. When clear all the other bits in the register are valid and SW may write to any bit. If Interrupt Request bit [1] was set for the current command, HW may clear this bit before the interrupt has been made visible to SW, since when SW actually handles

55.2.57 Front End Module Tx Command Path Delay Register (Tx_CMD_DLY)—Offset 820h

Front end module Tx Command Path Delay register

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000400h

BAR and Offset: [BAR or BAR1] + 820h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:15	0x0 RO	**Reserved (RSVD):** Reserved.
14:8	0x4 RW	**ddr_mode:** Tx CMD Delay (DDR Mode). 0 39 Select number of active delay elements. Each = 125pSec. 40 127 Reserved
7	0x0 RO	**Reserved (RSVD):** Reserved.
6:0	0x0 RW	**sdr_mode:** Tx CMD Delay (SDR Mode). 0 39 Select number of active delay elements. Each = 125pSec. 40 127 - Reserved

55.2.58 Front End Module Tx Data Path Delay Register1 (Tx_DATA_DLY_1)—Offset 824h

Front end module Tx data Path Delay register 1

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000A18h

BAR and Offset: [BAR or BAR1] + 824h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:15	0x0 RO	**Reserved (RSVD):** Reserved.
14:8	0xa RW	**hs400_mode:** Tx Data Delay (HS400 Mode). • 0-78 - Select number of active delay elements. Each = 125pSec. • 79-127 - Reserved
7	0x0 RO	**Reserved (RSVD):** Reserved.
6:0	0x18 RW	**sdr104_hs200:** Tx Data Delay (SDR104/HS200 Mode) • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved

55.2.59 Front End Module Tx Data Path Delay Register2 (Tx_DATA_DLY_2)—Offset 828h

Front end module Tx data Path Delay register 2

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 1C1C1C00h

BAR and Offset: [BAR or BAR1] + 828h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:24	0x1c RW	**sdr50_mode:** Tx Data Delay (SDR50 Mode) • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved
23	0x0 RO	**Reserved (RSVD):** Reserved.
22:16	0x1c RW	**ddr50_mode:** Tx Data Delay (DDR50 Mode). • 0-78 - Select number of active delay elements. Each = 125pSec. • 79-127 - Reserved
15	0x0 RO	**Reserved (RSVD):** Reserved.
14:8	0x1c RW	**sdr25_hs50_mode:** Tx Data Delay (SDR25/HS50 Mode • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved
7	0x0 RO	**Reserved (RSVD):** Reserved.
6:0	0x0 RW	**sdr12_comp_mode:** Tx Data Delay (SDR12/Compatibility Mode) • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved

55.2.60 Front End Module Rx Data Path Delay Register1 (Rx_CMD_DATA_DLY_1)—Offset 82Ch

Front end module Rx data Path Delay register 1

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BAR or BAR1] + 82Ch

Default: 00000000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:24	0x0 RW	**sdr50_mode:** Rx CMD + Data Delay (SDR50 Mode). • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved
23	0x0 RO	**Reserved (RSVD):** Reserved.
22:16	0x0 RW	**ddr50_mode:** Rx CMD + Data Delay (DDR50 Mode). • 0-78 - Select number of active delay elements. Each = 125pSec. • 79-127 - Reserved
15	0x0 RO	**Reserved (RSVD):** Reserved.
14:8	0x0 RW	**sdr25_hs50:** Rx CMD + Data Delay (SDR25/HS50 Mode) • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved
7	0x0 RO	**Reserved (RSVD):** Reserved.
6:0	0x0 RW	**sdr12_comp:** Rx CMD + Data Delay (SDR12/Compatibility Mode) • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved

55.2.61 Front End Module Rx Strobe Path Delay Register (Rx_STROBE_CTRL_PATH)—Offset 830h

Front end module Rx strobe Path Delay register

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 830h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved (RSVD):** Reserved.
16	0x0 RW	**auto_tuning:** Enable Auto Tuning for HS400 Strobe Path • 0 Auto Tuning Disabled • 1 Auto Tuning Enabled
15	0x0 RO	**Reserved (RSVD):** Reserved.
14:8	0x0 RW	**hs400_mode1:** Rx Strobe Delay DLL 1(HS400 Mode) • 0-39 - Select number of active delay elements. Each = 125pSec • 40-63 - Reserved
7	0x0 RO	**Reserved (RSVD):** Reserved.
6:0	0x0 RW	**hs400_mode2:** Rx Strobe Delay DLL 2(HS400 Mode) • 0-39 - Select number of active delay elements. Each = 125pSec • 40-63 - Reserved

55.2.62 Front End Module Rx Data Path Delay Register2 (Rx_CMD_DATA_DLY_2)—Offset 834h

Front end module Rx data Path Delay register 2

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BAR or BAR1] + 834h

Default: 00000000h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD):** Reserved.
17:16	0x0 RW	**clk_source:** Clock Source for Rx Path • 00 - Rx Clock after Output Buffer • 01 - Rx Clock before Output Buffer • 10 - Automatic Selection based on Working mode (HS 200 before buffer, all others after buffer) • 11 - Reserved
15:14	0x0 RO	**Reserved (RSVD):** Reserved.
13:8	0x0 RW	**path_pll:** Rx Path PLL #3 Delay value For Auto Tuning Mode • 0-39 - Select the required delay, as a multiple of 125pSec. • 40-63 - Reserved
7	0x0 RO	**Reserved (RSVD):** Reserved.
6:0	0x0 RW	**cmd_data_sdr104_hs200:** Rx CMD + Data Delay (SDR104/HS200 Mode) • 0-79 - Select the required delay, as a multiple of 125pSec. • 80-127 - Reserved

55.2.63 Master DLL Software Control Register (MASTER_DLL)—Offset 838h

Master DLL Software control register

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000001h

BAR and Offset: [BAR or BAR1] + 838h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**Reserved (RSVD):** Reserved.
24	0x0 RW	**SW_reset_dll:** SW reset for Master DLL • 0 No SW Reset for Master DLL • 1 Force Reset for Master DLL
23	0x0 RO/V	**DLL_lock:** Master DLL Lock Indication
22:8	0x0 RW	**coarse_code:** Set coarse code to DLL. (only valid when Software control is Enabled)
7:4	0x0 RW	**fine_code:** Set fine code to DLL. (only valid when Software control is Enabled)
3	0x0 RO/V	**less:** Phase Detection Less Indication
2	0x0 RO/V	**more:** Phase Detector More Indication
1	0x0 RW	**Master_DLL_Software_Ctrl:** Master DLL Software Ctrl. • 0 Master DLL Automatic Control (SW Control Disabled). • 1 Master DLL Software Control Enabled
0	0x1 RW	**Ctrl_of_Mst_DLL_Ref_Clk:** Ctrl of Master DLL Ref Clock. • 0 - Clock is Disabled. • 1 - Clock is Enabled

55.2.64 Auto Tuning Value (AUTO_TUNING)—Offset 840h

Auto Tuning Value

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 840h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RO	**Reserved (RSVD):** Reserved.
4:0	0x0 RO/V	**Auto_tuning_val:** Reserved.

55.2.65 Root Space Select (eMMC_ROOT_SPACE)—Offset 900h

Root space select to indicate which root space the IP will output its upstream accesses

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BAR or BAR1] + 900h

BAR or BAR1 Type: PCI Configuration Register (Size: 64 bits)
BAR or BAR1 Reference: [B:0, D:28, F:0] + 10h or 18h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Reserved.
0	0x0 RO	**root_space:** Root Space Select Selects the Root Space in which the IP output its upstream accesses • 0 Root Space 0 • 1 Root Space 1

§ §

56 LPC Controller - B0, D31, F0

56.1 Introduction and Index

The host-accessible registers for the LPC Controller are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

56.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 31 (decimal), Function 0. The offset addresses are listed.

Table 56-1. Summary of PCI Configuration Registers—0/31/0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
80	2	0000	"I/O Decode Ranges (IOD)—Offset 80h" on page 2645
82	2	0000	"I/O Enables (IOE)—Offset 82h" on page 2646
84	4	00000000	"LPC Generic I/O Range #1 (LGIR1)—Offset 84h" on page 2647
88	4	00000000	"LPC Generic I/O Range #2 (LGIR2)—Offset 88h" on page 2648
8C	4	00000000	"LPC Generic I/O Range #3 (LGIR3)—Offset 8Ch" on page 2649
90	4	00000000	"LPC Generic I/O Range #4 (LGIR4)—Offset 90h" on page 2650
94	4	00000000	"USB Legacy Keyboard/Mouse Control (ULKMC)—Offset 94h" on page 2651
98	4	00000000	"LPC Generic Memory Range (LGMR)—Offset 98h" on page 2653
D0	4	00112233	"FWH ID Select #1 (FS1)—Offset D0h" on page 2653
D4	2	4567	"FWH ID Select #2 (FS2)—Offset D4h" on page 2654
D8	2	FFCF	"BIOS Decode Enable (BDE)—Offset D8h" on page 2655
DC	1	20	"BIOS Control (BC)—Offset DCh" on page 2657
E0	4	00000000	"PCI Clock Control (PCCTL)—Offset E0h" on page 2659

56.2 Registers in Configuration Space

56.2.1 I/O Decode Ranges (IOD)—Offset 80h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:0] + 80h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**Reserved (RSVD):** Reserved.
12	0x0 RW	**FDD Range (FDD):** The following table describes which range to decode for the FDD Port: Bits Decode Range • 0 3F0h - 3F5h, 3F7h (Primary). • 1 370h - 375h, 377h (Secondary).
11:10	0x0 RO	**Reserved (RSVD_1):** Reserved.
9:8	0x0 RW	**LPT Range (LPT):** The following table describes which range to decode for the LPT Port: Bits Decode Range • 00 378h - 37Fh and 778h - 77Fh. • 01 278h - 27Fh (port 279h is read only) and 678h - 67Fh. • 10 3BCh - 3BEh and 7BCh - 7BEh. • 11 Reserved.
7	0x0 RO	**Reserved (RSVD_2):** Reserved.
6:4	0x0 RW	**ComB Range (CB):** The following table describes which range to decode for the COMB Port: Bits Decode Range • 000 3F8h - 3FFh (COM 1) • 001 2F8h - 2FFh (COM 2) • 010 220h - 227h • 011 228h - 22Fh • 100 238h - 23Fh • 101 2E8h - 2EFh (COM 4) • 110 338h - 33Fh • 111 3E8h - 3EFh (COM 3)
3	0x0 RO	**Reserved (RSVD_3):** Reserved.
2:0	0x0 RW	**ComA Range (CA):** The following table describes which range to decode for the COMA Port: Bits Decode Range • 000 3F8h - 3FFh (COM 1) • 001 2F8h - 2FFh (COM 2) • 010 220h - 227h • 011 228h - 22Fh • 100 238h - 23Fh • 101 2E8h - 2EFh (COM 4) • 110 338h - 33Fh • 111 3E8h - 3EFh (COM 3)

56.2.2 I/O Enables (IOE)—Offset 82h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:0] + 82h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**Reserved (RSVD):** Reserved.
13	0x0 RW	**Microcontroller Enable #2 (ME2):** Enables decoding of I/O locations 4Eh and 4Fh to LPC.
12	0x0 RW	**SuperI/O Enable (SE):** Enables decoding of I/O locations 2Eh and 2Fh to LPC.
11	0x0 RW	**Microcontroller Enable #1 (ME1):** Enables decoding of I/O locations 62h and 66h to LPC.
10	0x0 RW	**Keyboard Enable (KE):** Enables decoding of the keyboard I/O locations 60h and 64h to LPC.
9	0x0 RW	**High Gameport Enable (HGE):** Enables decoding of the I/O locations 208h to 20Fh to LPC.
8	0x0 RW	**Low Gameport Enable (LGE):** Enables decoding of the I/O locations 200h to 207h to LPC. **Power Well:** Core
7:4	0x0 RO	**Reserved (RSVD_1):** Reserved.
3	0x0 RW	**Floppy Drive Enable (FDE):** Enables decoding of the FDD range to LPC. Range is selected by IOD.FDE
2	0x0 RW	**Parallel Port Enable (PPE):** Enables decoding of the LPT range to LPC. Range is selected by IOD.LPT.
1	0x0 RW	**Com Port B Enable (CBE):** Enables decoding of the COMB range to LPC. Range is selected IOD.CB.
0	0x0 RW	**Com Port A Enable (CAE):** Enables decoding of the COMA range to LPC. Range is selected IOD.CA.

56.2.3 LPC Generic I/O Range #1 (LGIR1)—Offset 84h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + 84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved.
23:18	0x0 RW	**Address [7:2] Mask (Address_7_2_Mask):** A 1 in any bit position indicates that any value in the corresponding address bit in a received cycle will be treated as a match. The corresponding bit in the Address field, below, is ignored. The mask is only provided for the lower 6 bits of the DWord address, allowing for decoding blocks up to 256 bytes in size.
17:16	0x0 RO	**Reserved (RSVD_1):** Reserved.
15:2	0x0 RW	**Address [15:2] (Address_15_2):** DWord-aligned address. ***Note:*** The SoC does not provide decode down to the word or byte level.
1	0x0 RO	**Reserved (RSVD_2):** Reserved.
0	0x0 RW	**LPC Decode Enable (LPC_Decode_Enable):** When this bit is set to 1, then the range specified in this register is enabled for decoding to LPC.

56.2.4 LPC Generic I/O Range #2 (LGIR2)—Offset 88h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + 88h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved.
23:18	0x0 RW	**Address [7:2] Mask (Address_7_2_Mask):** A 1 in any bit position indicates that any value in the corresponding address bit in a received cycle will be treated as a match. The corresponding bit in the Address field, below, is ignored. The mask is only provided for the lower 6 bits of the DWord address, allowing for decoding blocks up to 256 bytes in size.
17:16	0x0 RO	**Reserved (RSVD_1):** Reserved.
15:2	0x0 RW	**Address [15:2] (Address_15_2):** DWord-aligned address. ***Note:*** The SoC does not provide decode down to the word or byte level.
1	0x0 RO	**Reserved (RSVD_2):** Reserved.
0	0x0 RW	**LPC Decode Enable (LPC_Decode_Enable):** When this bit is set to 1, then the range specified in this register is enabled for decoding to LPC.

56.2.5 LPC Generic I/O Range #3 (LGIR3)—Offset 8Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + 8Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved.
23:18	0x0 RW	**Address [7:2] Mask (Address_7_2_Mask):** A 1 in any bit position indicates that any value in the corresponding address bit in a received cycle will be treated as a match. The corresponding bit in the Address field, below, is ignored. The mask is only provided for the lower 6 bits of the DWord address, allowing for decoding blocks up to 256 bytes in size.
17:16	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
15:2	0x0 RW	**Address [15:2] (Address_15_2):** DWord-aligned address. ***Note:*** The SoC does not provide decode down to the word or byte level.
1	0x0 RO	**Reserved (RSVD_2):** Reserved.
0	0x0 RW	**LPC Decode Enable (LPC_Decode_Enable):** When this bit is set to 1, then the range specified in this register is enabled for decoding to LPC.

56.2.6 LPC Generic I/O Range #4 (LGIR4)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved.
23:18	0x0 RW	**Address [7:2] Mask (Address_7_2_Mask):** A 1 in any bit position indicates that any value in the corresponding address bit in a received cycle will be treated as a match. The corresponding bit in the Address field, below, is ignored. The mask is only provided for the lower 6 bits of the DWord address, allowing for decoding blocks up to 256 bytes in size.
17:16	0x0 RO	**Reserved (RSVD_1):** Reserved.
15:2	0x0 RW	**Address [15:2] (Address_15_2):** DWord-aligned address. ***Note:*** The SoC does not provide decode down to the word or byte level.
1	0x0 RO	**Reserved (RSVD_2):** Reserved.
0	0x0 RW	**LPC Decode Enable (LPC_Decode_Enable):** When this bit is set to 1, then the range specified in this register is enabled for decoding to LPC.

56.2.7 USB Legacy Keyboard/Mouse Control (ULKMC)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15	0x0 RW/1C	**SMI Caused by End of Pass-through (SMIBYENDPS):** Indicates if the event occurred. ***Note:*** Even if the corresponding enable bit is not set in the Bit 7, then this bit will still be active. It is up to the SMM code to use the enable bit to determine the exact cause of the SMI#. Writing a 1 to this bit will clear the latch.
14	0x0 RO	**Reserved (RSVD_1):** Reserved.
13	0x0 RW	**Reserved (RSVD_2):** Reserved.
12	0x0 RO	**Reserved (RSVD_3):** Reserved.
11	0x0 RW/1C	**SMI Caused by Port 64 Write (TRAPBY64W):** Indicates if the event occurred. ***Note:*** Even if the corresponding enable bit is not set in the Bit 3, then this bit will still be active. It is up to the SMM code to use the enable bit to determine the exact cause of the SMI#. Writing a 1 to this bit will clear the latch. ***Note:*** The A20Gate Pass-Through Logic allows specific port 64h Writes to complete without setting this bit.
10	0x0 RW/1C	**SMI Caused by Port 64 Read (TRAPBY64R):** Indicates if the event occurred. ***Note:*** Even if the corresponding enable bit is not set in the Bit 2, then this bit will still be active. It is up to the SMM code to use the enable bit to determine the exact cause of the SMI#. Writing a 1 to this bit will clear the latch.
9	0x0 RW/1C	**SMI Caused by Port 60 Write (TRAPBY60W):** Indicates if the event occurred. ***Note:*** Even if the corresponding enable bit is not set in the Bit 1, then this bit will still be active. It is up to the SMM code to use the enable bit to determine the exact cause of the SMI#. Writing a 1 to this bit will clear the latch. ***Note:*** The A20Gate Pass-Through Logic allows specific port 60h Writes to complete without setting this bit.
8	0x0 RW/1C	**SMI Caused by Port 60 Read (TRAPBY60R):** Indicates if the event occurred. ***Note:*** Even if the corresponding enable bit is not set in the Bit 0, then this bit will still be active. It is up to the SMM code to use the enable bit to determine the exact cause of the SMI#. Writing a 1 to this bit will clear the latch.
7	0x0 RW	**SMI at End of Pass-through Enable (SMIATENDPS):** May need to cause SMI at the end of a pass-through. Can occur if an SMI is generated in the middle of a pass through, and needs to be serviced later.
6	0x0 RO	**Pass Through State (PSTATE):** This read-only bit indicates that the state machine is in the middle of an A20GATE pass-through sequence. If software needs to reset this bit, it should set Bit 5 0.
5	0x0 RW	**A20Gate Pass-Through Enable (A20PASSEN):** When enabled, allows A20GATE sequence Pass-Through function (see details below in Section 20.14). When enabled, a specific cycle sequence involving writes to port 60h and port 64h does not result in the setting of the SMI status bits.SMI# will not be generated, even if the various enable bits are set.

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW	**Reserved (RSVD_4):** Reserved.
3	0x0 RW	**SMI on Port 64 Writes Enable (s64WEN):** When set, a 1 in bit 11 will cause an SMI event.
2	0x0 RW	**SMI on Port 64 Reads Enable (s64REN):** When set, a 1 in bit 10 will cause an SMI event.
1	0x0 RW	**SMI on Port 60 Writes Enable (s60WEN):** When set, a 1 in bit 9 will cause an SMI event.
0	0x0 RW	**SMI on Port 60 Reads Enable (s60REN):** When set, a 1 in bit 8 will cause an SMI event.

56.2.8 LPC Generic Memory Range (LGMR)—Offset 98h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Memory Address [31:16] (MA_31_16):** This field specifies a 64KB memory block anywhere in the 4GB memory space that will be decoded to LPC as standard LPC Memory Cycle if enabled.
15:1	0x0 RO	**Reserved (RSVD):** Reserved.
0	0x0 RW	**LPC Memory Range Decode Enable (LMRD_En):** When this bit is set to 1, then the range specified in this register is enabled for decoding to LPC.

56.2.9 FWH ID Select #1 (FS1)—Offset D0h

This register contains the IDSEL fields the LPC Bridge uses for memory cycles going to the FWH.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + D0h

Default: 00112233h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**F8-FF IDSEL (IF8):** IDSEL to use in FWH cycle for range enabled by BDE.EF8.
27:24	0x0 RW	**F0-F7 IDSEL (IF0):** IDSEL to use in FWH cycle for range enabled by BDE.EF0.
23:20	0x1 RW	**E8-EF IDSEL (IE8):** IDSEL to use in FWH cycle for range enabled by BDE.EE8.
19:16	0x1 RW	**E0-E7 IDSEL (IE0):** IDSEL to use in FWH cycle for range enabled by BDE.EE0.
15:12	0x2 RW	**D8-DF IDSEL (ID8):** IDSEL to use in FWH cycle for range enabled by BDE.ED8.
11:8	0x2 RW	**D0-D7 IDSEL (ID0):** IDSEL to use in FWH cycle for range enabled by BDE.ED0.
7:4	0x3 RW	**C8-CF IDSEL (IC8):** IDSEL to use in FWH cycle for range enabled by BDE.EC8.
3:0	0x3 RW	**C0-C7 IDSEL (IC0):** IDSEL to use in FWH cycle for range enabled by BDE.EC0.

56.2.10 FWH ID Select #2 (FS2)—Offset D4h

This register contains the additional IDSEL fields the LPC Bridge uses for memory cycles going to the FWH.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:0] + D4h

Default: 4567h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x4 RW	**70-7F IDSEL (I70):** IDSEL to use in FWH cycle for range enabled by BDE.E70.
11:8	0x5 RW	**60-6F IDSEL (I60):** IDSEL to use in FWH cycle for range enabled by BDE.E60.
7:4	0x6 RW	**50-5F IDSEL (I50):** IDSEL to use in FWH cycle for range enabled by BDE.E50.
3:0	0x7 RW	**40-4F IDSEL (I40):** IDSEL to use in FWH cycle for range enabled by BDE.E40.

56.2.11 BIOS Decode Enable (BDE)—Offset D8h

Note that this register effects the BIOS decode regardless of whether the BIOS is resident on LPC or SPI. The concept of Feature Space does not apply to SPI-based flash. The SoC simply decodes these ranges as memory accesses when enabled for the SPI flash interface.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:0] + D8h

Default: FFCFh

Bit Range	Default & Access	Field Name (ID): Description
15	0x1 RO	**F8-FF Enable (EF8):** Enables decoding of 512K of the following BIOS range: • Data space: FFF80000h - FFFFFFFFh. • Feature space: FFB80000h - FFBFFFFFh.
14	0x1 RW	**F0-F8 Enable (EF0):** Enables decoding of 512K of the following BIOS range: • Data space: FFF00000h - FFF7FFFFh. • Feature space: FFB00000h - FFB7FFFFh.
13	0x1 RW	**E8-EF Enable (EE8):** Enables decoding of 512K of the following BIOS range: • Data space: FFE80000h - FFEFFFFFh. • Feature space: FFA80000h - FFAFFFFFh.
12	0x1 RW	**E0-E8 Enable (EE0):** Enables decoding of 512K of the following BIOS range: • Data space: FFE00000h - FFE7FFFFh. • Feature Space: FFA00000h - FFA7FFFFh.
11	0x1 RW	**D8-DF Enable (ED8):** Enables decoding of 512K of the following BIOS range: • Data space: FFD80000h - FFDFFFFFh. • Feature space: FF980000h - FF9FFFFFh.
10	0x1 RW	**D0-D7 Enable (ED0):** Enables decoding of 512K of the following BIOS range: • Data space: FFD00000h - FFD7FFFFh. • Feature space: FF900000h - FF97FFFFh.
9	0x1 RW	**C8-CF Enable (EC8):** Enables decoding of 512K of the following BIOS range: • Data space: FFC80000h - FFCFFFFFh. • Feature space: FF880000h - FF8FFFFFh.
8	0x1 RW	**C0-C7 Enable (EC0):** Enables decoding of 512K of the following BIOS range: • Data space: FFC00000h - FFC7FFFFh. • Feature space: FF800000h - FF87FFFFh.
7	0x1 RW	**Legacy F Segment Enable (LFE):** This enables the decoding of the legacy 64KB range at F0000h - FFFFFh. ***Note:*** Decode for the BIOS legacy F segment is enabled by the LFE bit only, it is not affected by the GEN_PMCON_1.iA64_EN bit.
6	0x1 RW	**Legacy E Segment Enable (LEE):** This enables the decoding of the legacy 64KB range at E0000h - EFFFFh. ***Note:*** Decode for the BIOS legacy E segment is enabled by the LEE bit only, it is not affected by the GEN_PMCON_1.iA64_EN bit.
5:4	0x0 RO	**Reserved (RSVD):** Reserved.
3	0x1 RW	**70-7F Enable (E70):** Enables decoding of 1MB of the following BIOS range: • Data space: FF700000h - FF7FFFFFh. • Feature space: FF300000h - FF3FFFFFh.
2	0x1 RW	**60-6F Enable (E60):** Enables decoding of 1MB of the following BIOS range: • Data space: FF600000h - FF6FFFFFh. • Feature Space: FF200000h - FF2FFFFFh.

Bit Range	Default & Access	Field Name (ID): Description
1	0x1 RW	**50-5F Enable (E50):** Enables decoding of 1MB of the following BIOS range: • Data space: FF500000h - FF5FFFFFh. • Feature space: FF100000h - FF1FFFFFh.
0	0x1 RW	**40-4F Enable (E40):** Enables decoding of 1MB of the following BIOS range: • Data space: FF400000h - FF4FFFFFh. • Feature space: FF000000h - FF0FFFFFh.

56.2.12 BIOS Control (BC)—Offset DCh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:0] + DCh

Default: 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1L	**BIOS Interface Lock-Down (BILD):** When set, prevents BC.TS and BC.BBS from being changed. This bit can only be written from 0 to 1 once. ***Note:*** BIOS: This bit is not backed up in the RTC well. This bit should also be set in the BUC register in the RTC device to record the last state of this value following a cold reset.
6	0x0 RW/L	**Boot BIOS Strap (BBS):** This field determines the destination of accesses to the BIOS memory range. For the default, Functional Strap section of Signal Description chapter for details. Bits Description • 0 SPI. • 1 LPC. When SPI or LPC is selected, the range that is decoded is further qualified by other configuration bits described in the respective sections. The value in this field can be overwritten by software as long as the BIOS Interface Lock-Down is not set. ***Note:*** Software must not change this bit since the SoC does not support dynamic switching between the SPI and LPC interface it is chosen at boot time by a strap.
5	0x1 RW/L	**Enable InSMM.STS (EISS):** When this bit is set, the BIOS region is not writable until SMM sets the InSMM.STS bit. If this bit [5] is set, then WPD must be a 1 and InSMM.STS must be 1 also. If this bit [5] is clear, then BIOS is writable based only on WPD = 1 and the InSMM.STS is a don't care.
4	0x0 RO	**Top Swap (TS):** When set, the SoC will invert either A16, A17, or A18 for cycles going to the BIOS space (but not the feature space). When cleared, the SoC will not invert A16. If booting from SPI, then the BOOT_BLOCK_SIZE soft strap determines if A16, A17, or A18 should be inverted if Top Swap is enabled. *If the SoC is strapped for to enable Top-Swap Override (GPIO[3] is sampled as height (1) within 400 ns of the rising edge (0 -> 1) of the active-low resume reset signal RSMRST_N), then this bit cannot be cleared by software. The strap jumper should be removed (GPIO[3] set to low(0)) and the system rebooted. BIOS Note: 1. This bit provides a read-only path to view the state of the Top Swap strap. It is backed up and driven from the RTC well. BIOS will need to program the corresponding register in the RTC Controller (in RTC well), which will be reflected in this register. 2. The Register portion of the Top Swap is lockable by the BIOS Interface Lockdown Bit (BC.BILD) but unlockable by SPI Flash Protected Range and Top Swap Override (uCode.PRR_TS_OVR).
3:2	0x0 RW	**SPI Read Configuration (SRC):** This 2-bit field controls two policies related to BIOS reads on the SPI interface: Bit 3- Prefetch Enable Bit 2- Cache Disable Settings are summarized below: Bits 3:2 Description • 00 - No prefetching, but caching enabled. Direct Memory reads load the read buffer cache with valid data, allowing repeated reads to the same range to complete quickly • 01 - No prefetching and no caching. One-to-one correspondence of host BIOS reads to SPI cycles. This value can be used to invalidate the cache. • 10 - Prefetching and Caching enabled. This mode is used for long sequences of short reads to consecutive addresses (i.e. shadowing) • 11 - Illegal. Caching must be enabled when Prefetching is enabled. This eliminates the need for a complex prefetch-flushing mechanism.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW/1L	**Lock Enable (LE):** When set, setting the WP bit will cause SMI. When cleared, setting the WP bit will not cause SMI. Once set, this bit can only be cleared by a PLTRST#. When this bit is set, EISS - bit [5] of this register is locked down.
0	0x0 RW	**Write Protect Disable (WPD):** When set, access to the BIOS space is enabled for both read and write cycles to BIOS. When cleared, only read cycles are permitted to the FWH or SPI flash. When this bit is written from a 0 to a 1 and the LE bit is also set, an SMI# is generated. This ensures that only SMM code can update BIOS.

56.2.13 PCI Clock Control (PCCTL)—Offset E0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:0] + E0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD):** Reserved.
9	0x0 RO/V	**CLKRUN# Buffer Enable Override (CLKRUN_EN_OVR):** When set to '1', SW is in control of the CLKRUN# buffer enable and the value in CLKRUN_EN_VAL will be propagated to the output buffer enable. When this bit is '0', HW will determine the value of the buffer enable.
8	0x0 RO/V	**CLKRUN# Override (CLKRUN_OVR):** When set to '1', SW is in control of the CLKRUN# pin and the value in CLKRUN_VAL will be propagated to the output pin. When this bit is '0', HW will determine the value of the pin.
7	0x0 RO/V	**CLKRUN# Buffer Enable Value (CLKRUN_EN_VAL):** Either HW or SW may own control of the CLKRUN# pin. This bit provides the value to drive on the active low CLKRUN# buffer enable if CLKRUN_EN_OVR is set to '1'.
6	0x0 RO/V	**CLKRUN# Pin Output Value (CLKRUN_VAL):** Either HW or SW may own control of the CLKRUN# pin. This bit provides the value to drive on the pin if CLKRUN_OVR is set to '1'.
5	0x0 RO/V	**Stop PCI# Value (STP_PCI_VAL):** Either Hardware or Software may own control of the internal STP_PCI#. This bit provides the value to drive on the STP_PCI# if STP_PCI_OVR is set to 1. ***Note:*** 1. SW cannot control the STP_PCI# pin while PLTRST# is asserted (the pin will be at its reset default value).
4	0x0 RO/V	**Stop PCI# Override (STP_PCI_OVR):** When set to 1, Firmware is in control of the STP_PCI# and the value in STP_PCI_VAL will be propagated to the internal STP_PCI#. When this bit is '0', HW will determine the value of the pin. ***Note:*** 1. BIOS cannot control the STP_PCI# pin while PLTRST# is asserted (the pin will be at its reset default value).
3:2	0x0 RW	**Reserved (RSVD_1):** Reserved
1	0x0 RW	**Reserved (RSVD_1):** Reserved.
0	0x0 RW	**Clock Run Enable (CLKRUN_EN):** Enables the CLKRUN# logic to stop the PCI clocks. If the SLP_EN bit is set, then the SoC will drive CLKRUN# low. This will keep the PCI and LPC clocks running on the way to the sleeping state. This is required to meet an LPC specification. This does not necessarily mean that the CLKRUN_EN bit is forced low when SLP_EN is set. Even though the CLKRUN# signal will be low when SLP_EN is set, the state of the CLKRUN_EN bit is ignored when SLP_EN bit is set. This gives flexibility in the implementation.

§ §

57 Primary to Side Band Bridge - B0, D31, F1

57.1 Introduction and Index

The host-accessible registers for the Primary to Side Band (P2SB) Bridge are described here.

The legend for the register access codes are described in Chapter 43, “Introduction.”

57.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 31 (decimal), Function 1. The offset addresses are listed.

Table 57-1. Summary of PCI Configuration Registers—0/31/1

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19DD8086	"PCI Identifier (PCIID)—Offset 0h" on page 2663
4	2	0004	"PCI Command (PCICMD)—Offset 4h" on page 2664
6	2	0000	"PCI Status (PCISTS)—Offset 6h" on page 2665
8	1	00	"Revision ID (PCIRID)—Offset 8h" on page 2665
9	4	00058000	"Class Code (PCICC)—Offset 9h" on page 2666
D	1	00	"PCI Master Latency Timer (PCIMLT)—Offset Dh" on page 2666
E	2	00	"PCI Header Type (PCIHTYPE)—Offset Eh" on page 2666
10	4	00000004	"Sideband Register Access BAR (SBREG_BAR)—Offset 10h" on page 2667
14	4	00000000	"Sideband Register BAR High DWORD (SBREG_BARH)—Offset 14h" on page 2667
2C	4	00000000	"PCI Subsystem Identifiers (PCIHSS)—Offset 2Ch" on page 2668
50	2	00F8	"VLW Bus:Device:Function (VBDF)—Offset 50h" on page 2668
52	2	00F8	"ERROR Bus:Device:Function (EBDF)—Offset 52h" on page 2669
54	4	0000C700	"Routing Configuration (RCFG)—Offset 54h" on page 2670
60	1	00	"High Performance Event Timer Configuration (HPTC)—Offset 60h" on page 2670
64	2	0000	"IOxAPIC Configuration (IOAC)—Offset 64h" on page 2671
6C	2	00F8	"IOxAPIC Bus:Device:Function (IBDF)—Offset 6Ch" on page 2671
70	2	00F8	"HPET Bus:Device:Function (HBDF)—Offset 70h" on page 2672
80	4	00000000	"Sideband Register posted 0 (SBREGPOSTED0)—Offset 80h" on page 2672
84	4	00000000	"Sideband Register posted 1 (SBREGPOSTED1)—Offset 84h" on page 2672
88	4	00000000	"Sideband Register posted 2 (SBREGPOSTED2)—Offset 88h" on page 2673
8C	4	00000000	"Sideband Register posted 3 (SBREGPOSTED3)—Offset 8Ch" on page 2673
90	4	00000000	"Sideband Register posted 4 (SBREGPOSTED4)—Offset 90h" on page 2673
94	4	00000000	"Sideband Register posted 5 (SBREGPOSTED5)—Offset 94h" on page 2673
98	4	00000000	"Sideband Register posted 6 (SBREGPOSTED6)—Offset 98h" on page 2674
9C	4	00000000	"Sideband Register posted 7 (SBREGPOSTED7)—Offset 9Ch" on page 2674
A0	4	00060010	"Display Bus:Device:Function (DISPBDF)—Offset A0h" on page 2674
A4	2	0000	"ICC Register Offsets (ICCOS)—Offset A4h" on page 2675
B0	4	00000000	"Endpoint Mask 0 (EPMASK0)—Offset B0h" on page 2675
B4	4	00000000	"Endpoint Mask 1 (EPMASK1)—Offset B4h" on page 2675
B8	4	00000000	"Endpoint Mask 2 (EPMASK2)—Offset B8h" on page 2676
BC	4	00000000	"Endpoint Mask 3 (EPMASK3)—Offset BCh" on page 2676
C0	4	00000000	"Endpoint Mask 4 (EPMASK4)—Offset C0h" on page 2676
C4	4	00000000	"Endpoint Mask 5 (EPMASK5)—Offset C4h" on page 2676
C8	4	00000000	"Endpoint Mask 6 (EPMASK6)—Offset C8h" on page 2677
CC	4	00000000	"Endpoint Mask 7 (EPMASK7)—Offset CCh" on page 2677
D0	4	00000000	"SBI Address (SBIADDR)—Offset D0h" on page 2677

Table 57-1. Summary of PCI Configuration Registers—0/31/1 (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
D4	4	00000000	"SBI Data (SBIDATA)—Offset D4h" on page 2678
D8	2	0000	"SBI Status (SBISTAT)—Offset D8h" on page 2678
DA	2	0000	"SBI Routing Identification (SBIRID)—Offset DAh" on page 2679
DC	4	00000000	"SBI Extended Address (SBIEXTADDR)—Offset DCh" on page 2679
E0	4	00000007	"P2SB Control (P2SBC)—Offset E0h" on page 2680
F0	4	00000000	"Unsupported Request Error Status (URES)—Offset F0h" on page 2681
F4	4	00000000	"Unsupported Request Error Control (UREC)—Offset F4h" on page 2681
F8	4	00000F00	"Manufacturer's ID (MANID)—Offset F8h" on page 2682

57.2 Registers in Configuration Space

57.2.1 PCI Identifier (PCIID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 0h

Default: 19DD8086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19dd RO/V	**Device Identification (DID):** The upper 8-bits of this field can be overridden by the SoC. **Power Well:** Core
15:0	0x8086 RO	**Vendor Identification (VID):** Indicates Intel **Power Well:** Core

57.2.2 PCI Command (PCICMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 4h

Default: 0004h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
10	0x0 RO	**Interrupt Disable (INTD):** P2SB does not issue any interrupts on its own behalf **Power Well:** Core
9	0x0 RO	**Fast Back to Back Enable (FB2BE):** Not applicable **Power Well:** Core
8	0x0 RW	**SERR# Enable (SEE):** This bit enables parity error reporting to the SoC Interrupt Error Handler (IEH) **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
6	0x0 RW	**Parity Error Response Enable (PEE):** This bit controls the device's response to parity error. **Power Well:** Core
5	0x0 RO	**VGA Palette Snoop (VGA):** Not applicable. **Power Well:** Core
4	0x0 RO	**Memory Write & Invalidate Enable (MWIE):** Not applicable. **Power Well:** Core
3	0x0 RO	**Special Cycle Enable (SCE):** Not applicable. **Power Well:** Core
2	0x1 RO	**Bus Master Enable (BME):** Bus mastering cannot be disabled as this device acts as a proxy for non-PCI devices. **Power Well:** Core
1	0x0 RW	**Memory Space Enable (MSE):** This bit controls the P2SB acceptance of PCI MMIO BARs only. Other legacy regions are unaffected by this bit. **Power Well:** Core
0	0x0 RW	**I/O Space Enable (IOSE):** Legacy regions are unaffected by this bit. **Power Well:** Core

57.2.3 PCI Status (PCISTS)—Offset 6h

The P2SB does not issue any interrupts, signal any errors, or provide any additional capability structures. This register has no functionality.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 6h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**Detected Parity Error (DPE):** This register bit is set when parity error is detected. **Power Well:** Core
14	0x0 RW/1C	**Signaled System Error (SSE):** This register sets when PCICMD.SE bit and PCISTS.DPE bit is set **Power Well:** Core
13:0	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core

57.2.4 Revision ID (PCIRID)—Offset 8h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:1] + 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO/V	**Revision ID (RID):** Indicates the part revision. This field resets to 0 and can be overridden by the SoC circuitry during the SoC power-up sequence **Power Well:** Core

57.2.5 Class Code (PCICC)—Offset 9h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 9h

Default: 00058000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**RSVD0:** Reserved
23:16	0x5 RO	**Base Class Code (BCC):** Indicates a Memory Controller device class. **Power Well:** Core
15:8	0x80 RO	**Sub-Class Code (SCC):** Indicates an unspecified sub-class other Memory Controller. **Power Well:** Core
7:0	0x0 RO	**Programming Interface (PI):** No programming interface. **Power Well:** Core

57.2.6 PCI Master Latency Timer (PCIMLT)—Offset Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:1] + Dh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core

57.2.7 PCI Header Type (PCIHTYPE)—Offset Eh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:1] + Eh

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Multi-Function Device (MFD):** Indicates that this is part of a multi-function device. **Power Well:** Core
6:0	0x0 RO	**Header Type (HTYPE):** Indicates a generic Type 0 PCI device header. **Power Well:** Core

57.2.8 Sideband Register Access BAR (SBREG_BAR)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW	**Register Base Address (RBA):** Lower DWORD of the base address for the sideband register access BAR. **Power Well:** Core
23:4	0x0 RO	**Hardwired to 0 to request a BAR of 16MB (HW202RB16MB):** Hardwired to 0 to request a BAR of 16MB **Power Well:** Core
3	0x0 RO	**Prefetchable (PREF):** Indicates this is not prefetchable. **Power Well:** Core
2:1	0x2 RO	**Address Type (ATYPE):** Indicates that the BAR can be defined to be located anywhere in 64-bit Host Root Memory Space. **Power Well:** Core
0	0x0 RO	**Space Type (STYPE):** Indicates Memory Space **Power Well:** Core

57.2.9 Sideband Register BAR High DWORD (SBREG_BARH)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Register Base Address (RBAH):** Upper DWORD of the base address for the sideband register access BAR. **Power Well:** Core

57.2.10 PCI Subsystem Identifiers (PCIHSS)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Written by BIOS. Not used by hardware. **Power Well:** Core
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Written by BIOS. Not used by hardware. **Power Well:** Core

57.2.11 VLW Bus:Device:Function (VBDF)—Offset 50h

This register specifies the bus:device:function ID that the VLW VDM will use for its Requester ID. This field is default to Bus 0: Device 31: Function 0 after reset. BIOS shall program this field accordingly if unique bus:device:function number is required for the VLW message.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 50h

Default: 00F8h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**Bus Number (BUS):** Reserved. **Power Well:** Core
7:3	0x1f RW	**Device Number (DEV):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Function Number (FUNC):** Reserved. **Power Well:** Core

57.2.12 ERROR Bus:Device:Function (EBDF)—Offset 52h

This register specifies the bus:device:function ID that the Error Signaling messages VDM will use for its Requester ID. This field is default to Bus 0: Device 31: Function 0 after reset. BIOS shall program this field accordingly if unique bus:device:function number is required for the VLW message.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 52h

Default: 00F8h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**Bus Number (BUS):** Reserved. **Power Well:** Core
7:3	0x1f RW	**Device Number (DEV):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Function Number (FUNC):** Reserved. **Power Well:** Core

57.2.13 Routing Configuration (RCFG)—Offset 54h

This register contains information used for routing transactions between primary and sideband interfaces.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 54h

Default: 0000C700h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:8	0xc7 RW	**Reserved Page Register Destination ID (RPRID):** Specifies the IOSF-SB destination ID for sending Reserved Page Register cycles (e.g. Port 80h). By default this will load to the ID of the LPC device depending on which has been strapped active in the system. **Power Well:** Core
7:1	0x0 RW	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
0	0x0 RW	**RTC Shadow Enable (RSE):** When set, all IO writes to the RTC will be also sent to the PMC. This allows cases where the battery-backed storage is in an external PMIC device. **Power Well:** Core

57.2.14 High Performance Event Timer Configuration (HPTC)—Offset 60h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:1] + 60h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Address Enable (AE):** When set, the P2SB will decode the High Performance Event Timer (HPET) Host Root memory-address range selected by bits 1:0 below. **Power Well:** Core
6:2	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
1:0	0x0 RW	**Address Select (AS):** This 2-bit field selects 1 of 4 possible memory address ranges for the High-Performance Event Timer (HPET) functionality. The encodings are: • 00: FED0_0000h - FED0_03FFFh • 01: FED0_1000h - FED0_13FFFh • 10: FED0_2000h - FED0_23FFFh • 11: FED0_3000h - FED0_33FFFh **Power Well:** Core

57.2.15 IOxAPIC Configuration (IOAC)—Offset 64h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 64h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RW	**Address Enable (AE):** When set, the P2SB will decode the IOxAPIC Host Root memory-address range selected by bits 7:0 below. **Power Well:** Core
7:0	0x0 RW	**APIC Range Select (ASEL):** These eight bits define the eight address bits 19:12 for the IOxAPIC range. The default value of 00h enables compatibility with prior Intel products as an initial value. This value must not be changed by software unless the IOxAPIC Address Enable (AE) bit is cleared. **Power Well:** Core

57.2.16 IOxAPIC Bus:Device:Function (IBDF)—Offset 6Ch

This register specifies the PCI Bus:Device:Function ID that the IOxAPIC will use in the following:

- As the Requester ID when initiating Interrupt Messages to the CPU.
- As the Completer ID when responding to the reads targeting the IOxAPIC Memory-Mapped I/O (MMIO) registers.

This field is default to Bus 0: Device 31: Function 0 after reset. BIOS shall program this field accordingly if a unique Bus:Device:Function number is required for the internal IOxAPIC.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 6Ch

Default: 00F8h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**Bus Number (BUS):** Reserved. **Power Well:** Core
7:3	0x1f RW	**Device Number (DEV):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Function Number (FUNC):** Reserved. **Power Well:** Core

57.2.17 HPET Bus:Device:Function (HBDF)—Offset 70h

This register specifies the PCI Bus:Device:Function ID that the integrated High-Performance Event Timer (HPET) device will use in the following:

- As the Requester ID when initiating Interrupt Messages to the CPU.
- As the Completer ID when responding to the reads targeting the corresponding HPET Memory-Mapped I/O (MMIO) registers.

This field is default to Bus 0: Device 31: Function 0 after reset. BIOS shall program this field accordingly if unique Bus:Device:Function number is required for the corresponding HPET.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 70h

Default: 00F8h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**Bus Number (BUS):** Reserved. **Power Well:** Core
7:3	0x1f RW	**Device Number (DEV):** Reserved. **Power Well:** Core
2:0	0x0 RW	**Function Number (FUNC):** Reserved. **Power Well:** Core

57.2.18 Sideband Register posted 0 (SBREGPOSTED0)—Offset 80h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 80h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 0 (SBREGPOSTED0):** One hot masks for setting SBREG to posted posted for IOSF-SB endpoint IDs 31-0. **Power Well:** Core

57.2.19 Sideband Register posted 1 (SBREGPOSTED1)—Offset 84h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 84h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 1 (SBREGPOSTED1):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 63-32. **Power Well:** Core

57.2.20 Sideband Register posted 2 (SBREGPOSTED2)—Offset 88h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 88h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 0 (SBREGPOSTED2):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 95-64. **Power Well:** Core

57.2.21 Sideband Register posted 3 (SBREGPOSTED3)—Offset 8Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 8Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 3 (SBREGPOSTED3):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 127-96. **Power Well:** Core

57.2.22 Sideband Register posted 4 (SBREGPOSTED4)—Offset 90h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 4 (SBREGPOSTED4):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 159-128. **Power Well:** Core

57.2.23 Sideband Register posted 5 (SBREGPOSTED5)—Offset 94h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 5 (SBREGPOSTED5):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 191-160. **Power Well:** Core

57.2.24 Sideband Register posted 6 (SBREGPOSTED6)—Offset 98h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 6 (SBREGPOSTED6):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 223-192. **Power Well:** Core

57.2.25 Sideband Register posted 7 (SBREGPOSTED7)—Offset 9Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Sideband Register posted 7 (SBREGPOSTED7):** One hot masks for setting SBREG to posted for IOSF-SB endpoint IDs 255-224. **Power Well:** Core

57.2.26 Display Bus:Device:Function (DISPBDF)—Offset A0h

This register specifies the PCI Bus:Device:Function ID that the Display initiated upstream RAVDMs will use for its Requester ID. This will also be used for the claiming these Route-by-ID RAVDMs downstream.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + A0h

Default: 00060010h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
18:16	0x6 RW	**Display Target Block (DTBLK):** This register contains the Target BLK field that will be used when sending RAVDM messages to the CPU Complex North Display. **Power Well:** Core
15:8	0x0 RW	**Bus Number (BUS):** The bus number of the Display in the CPU Complex. **Power Well:** Core
7:3	0x2 RW	**Device Number (DEV):** The bus number of the Display in the CPU Complex. **Power Well:** Core
2:0	0x0 RW	**Function Number (FUNC):** The function number of the Display in the CPU Complex **Power Well:** Core

57.2.27 ICC Register Offsets (ICCOS)—Offset A4h

This register contains the offsets to be used when sending RAVDMs to the Integrated Clock Controller. Each of the two spaces decoded for the ICC have a separate base address that will be used when sending those transactions on IOSF-SB to the ICC.

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + A4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**Modulator Control Address Offset (MODBASE):** This specifies the upper 8b for the 16b address that will be used for sending RAVDM access that target the Modulator Control range of the ICC (FFF00h - FFFFFh). **Power Well:** Core
7:0	0x0 RW	**Buffer Address Offset (BUFBASE):** This specifies the upper 8b for the 16b address that will be used for sending RAVDM access that target the Buffer range of the ICC (FFE00h - FFEFFh). **Power Well:** Core

57.2.28 Endpoint Mask 0 (EPMASK0)—Offset B0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 0 (EPMASK0):** One hot masks for disabling IOSF-SB endpoint IDs 31-0. **Power Well:** Core

57.2.29 Endpoint Mask 1 (EPMASK1)—Offset B4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + B4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 1 (EPMASK1):** One hot masks for disabling IOSF-SB endpoint IDs 63-32. **Power Well:** Core

57.2.30 Endpoint Mask 2 (EPMASK2)—Offset B8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + B8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 2 (EPMASK2):** One hot masks for disabling IOSF-SB endpoint IDs 95-64. **Power Well:** Core

57.2.31 Endpoint Mask 3 (EPMASK3)—Offset BCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + BCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 3 (EPMASK3):** One hot masks for disabling IOSF-SB endpoint IDs 127-96. **Power Well:** Core

57.2.32 Endpoint Mask 4 (EPMASK4)—Offset C0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 4 (EPMASK4):** One hot masks for disabling IOSF-SB endpoint IDs 128-159. **Power Well:** Core

57.2.33 Endpoint Mask 5 (EPMASK5)—Offset C4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 5 (EPMASK5):** One hot masks for disabling IOSF-SB endpoint IDs 191-160. **Power Well:** Core

57.2.34 Endpoint Mask 6 (EPMASK6)—Offset C8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 6 (EPMASK6):** One hot masks for disabling IOSF-SB endpoint IDs 223-192. **Power Well:** Core

57.2.35 Endpoint Mask 7 (EPMASK7)—Offset CCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V/L	**Endpoint Mask 7 (EPMASK7):** One hot masks for disabling IOSF-SB endpoint IDs 255-224. **Power Well:** Core

57.2.36 SBI Address (SBIADDR)—Offset D0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW	**Destination Port ID (DESTID):** The content of this register field is sent in the IOSF Sideband Message Register Access dest field. **Power Well:** Core
23:20	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
19:16	0x0 RW	**Root Space (RS):** Destination IOSF-SB Root Space. ***Note:*** This register may only be written during manufacturing test. P2SB will only accept writes to this register from transactions with a SAI equal to the SBI_RS_ACCESS_SAI parameter. This should be assigned to the SAI used by the functional test module (typically TAM) that will perform this register write on IOSF-P. **Power Well:** Core
15:0	0x0 RW	**Address Offset (OFFSET):** Register address offset. The content of this register field is sent in the IOSF Sideband Message Register Access address(15:0) field. **Power Well:** Core

57.2.37 SBI Data (SBIDATA)—Offset D4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + D4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Data (DATA):** The content of this register field is sent on the IOSF sideband Message Register Access data(31:0) field. **Power Well:** Core

57.2.38 SBI Status (SBISTAT)—Offset D8h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + D8h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:8	0x0 RW	**Opcode (OPCODE):** This is the Opcode sent in the IOSF sideband message. **Power Well:** Core
7	0x0 RW	**Posted (POSTED):** When set to 1, the message will be send as a posted message instead of non-posted. This should only be used if the receiver is known to support posted operations for the specified operation. **Power Well:** Core
6:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
2:1	0x0 RW/V	**Response Status (RESPONSE):** • 00 - Successful • 01 - Unsuccessful / Not Supported • 10 - Powered Down • 11 - Multi-cast Mixed This register reflects the response status for the previously completed transaction. The value of this register is only meaningful if SBISTAT.INITRDY is zero. **Power Well:** Core
0	0x0 RW/1S	**Initiate/ Ready# (INITRDY):** • 0: The IOSF sideband interface is ready for a new transaction • 1: The IOSF sideband interface is busy with the previous transaction. A write to set this register bit to 1 will trigger an IOSF sideband message on the private IOSF sideband interface. The message will be formed based on the values programmed in the Sideband Message Interface Register Access registers. Software needs to ensure that the interface is not busy (SBISTAT.INITRDY is clear) before writing to this register. **Power Well:** Core

57.2.39 SBI Routing Identification (SBIRID)—Offset DAh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + DAh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:12	0x0 RW	**First Byte Enable (FBE):** The content of this field is sent in the IOSF Sideband Register Access FBE field. **Power Well:** Core
11	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
10:8	0x0 RW	**Base Address Register (BAR):** The contents of this field are sent in the IOSF Sideband Register Access BAR field. This should be zero performing a Memory Mapped operation to a PCI compliant device. **Power Well:** Core
7:0	0x0 RW	**Function ID (FID):** The contents of this field are sent in the IOSF Sideband Register access FID field. This field should generally remain at zero unless specifically required by a particular application. **Power Well:** Core

57.2.40 SBI Extended Address (SBIEXTADDR)—Offset DCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + DCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Extended Address (ADDR):** The content of this register field is sent on the IOSF sideband Message Register Access address(48:32) field. This must be set to all 0 if 16b addressing is desired. **Power Well:** Core

57.2.41 P2SB Control (P2SBC)—Offset E0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + E0h

Default: 00000007h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RW	**Reserved (RSVD):** Reserved. **Power Well:** Core
26	0x0 RW	**Data Parity Error Enable (DPEE):** IOSFP data parity error handling (EP bit) enabling bit **Power Well:** Core
25	0x0 RW	**Command Parity Error Enable (CPEE):** IOSFP command parity error handling enabling bit **Power Well:** Core
24	0x0 RW	**Data Phase Parity Error Enable (DPPEE):** IOSFP data phase parity error handling enabling bit **Power Well:** Core
23:18	0x0 RW	**Reserved (RSVD_3):** Reserved. **Power Well:** Core
17	0x0 RW/O	**Endpoint Mask Lock (MASKLOCK):** Locks the value of the eight Endpoint Mask (EPMASK[0-7]) registers. Once this value is written to a one it may only be cleared by a reset. **Power Well:** Core
16	0x0 RW	**PGCB Clock Gating Enable (PGCBCGE):** When asserted, the P2SB can de-assert the clock request to disable the PGCB clock dynamically when it reaches the power-down idle state. **Power Well:** Core
15:9	0x0 RW	**Reserved: (RSVD_1):** Hardware will not allocate these bits for any purpose in the future so that BIOS can always write to the HIDE field with this byte enabled without having to remember any other field values since it will not be possible to do a read-modify-write when the device is hidden. **Power Well:** Core
8	0x0 RW	**Hide Device (HIDE):** When this bit is set, the P2SB will return 1s on any PCI Configuration Read on IOSF-P. All other transactions including PCI Configuration Writes are unaffected by this. This does not affect reads performed on the IOSF-SB interface. **Power Well:** Core
7:3	0x0 RW	**Reserved (RSVD_2):** Reserved. **Power Well:** Core
2:0	0x7 RW	**Max Writes Pending (MAXW):** This controls the maximum number of outstanding writes on IOSF-SB initiated by MMIO writes to the SBREG_BAR. Once the number of SBREG_BAR writes that are issued, but not completed, on IOSF-SB is equal to this value, no new requests will be forwarded until the completions are received. A value of zero will have the same behavior as the value of one (single write outstanding). **Power Well:** Core

57.2.42 Unsupported Request Error Status (URES)—Offset F0h

This register is only reset by a loss of core power

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + F0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RW/1C	**Unsupported Request Detected (URD):** Set to 1 by hardware upon detecting an Unsupported Request on IOSF Primary interface that is not considered Advisory Non-Fatal **Power Well:** Core
7:0	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core

57.2.43 Unsupported Request Error Control (UREC)—Offset F4h

This register is only reset by a loss of core power.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + F4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RW	**Unsupported Request Reporting Enable (URRE):** If set to 1 by software, it allows reporting of an Unsupported Request as a system error. **Power Well:** SUS
7:0	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core

57.2.44 Manufacturer's ID (MANID)—Offset F8h

This register is assigned during the boot flow using the SetID message based on values found in the fuse block. All fields except MID will be reset by hardware to zero and set only by the SetID message.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:1] + F8h

Default: 00000F00h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
27:24	0x0 RO/V	**Dot portion of Process ID (DOT):** Indicates the dot process **Power Well:** Core
23:16	0x0 RO/V	**Manufacturing Stepping Identifier (MSID):** This field is incremented for each stepping of the part. ***Note:*** This field can be used by software to differentiate steppings when the Stepping Revision ID may not change. **Power Well:** Core
15:8	0xf RO	**Manufacturing Identifier (MID):** 0Fh = Intel **Power Well:** Core
7:0	0x0 RO/V	**Process portion of process ID (PROC):** Indicates the process. The dot portion of the process is reflected in bits (27:24) **Power Well:** Core

§ §

58 Power Management Controller - B0, D31, F2

58.1 Introduction and Index

The host-accessible registers for the Power Management Controller (PMC) are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

58.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 31 (decimal), Function 2. The offset addresses are listed.

Table 58-1. Summary of PCI Configuration Registers—0/31/2

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19DE8086	"PCI Identifier (PCIID)—Offset 0h" on page 2689
40	4	00000001	"ACPI Base Address (ABASE)—Offset 40h" on page 2689
44	4	00000000	"ACPI Control (ACTL)—Offset 44h" on page 2690
A0	4	A0000000	"General PM Configuration A (GEN_PMCON_A)—Offset A0h" on page 2691
A4	4	00004007	"General PM Configuration B (GEN_PMCON_B)—Offset A4h" on page 2693
AC	4	00000000	"Extended Test Mode Register 3 (ETR3)—Offset ACh" on page 2695

58.1.2 Host Memory Space—PWRMBASE

Table 58-2. Summary of Memory Mapped I/O Registers—PWRMBASE

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	FFFFFFFF	"Wake Alarm Device Timer: AC (WADT_AC)—Offset 0h" on page 2696
4	4	FFFFFFFF	"Wake Alarm Device Timer: DC (WADT_DC)—Offset 4h" on page 2697
8	4	FFFFFFFF	"Wake Alarm Device Expired Timer: AC (WADT_EXP_AC)—Offset 8h" on page 2698
C	4	FFFFFFFF	"Wake Alarm Device Expired Timer: DC (WADT_EXP_DC)—Offset Ch" on page 2698
10	4	05000000	"Power and Reset Status (PRSTS)—Offset 10h" on page 2699
18	4	00000020	"Power Management Configuration Reg 1 (PM_CFG)—Offset 18h" on page 2700
1C	4	00000000	"PCH Power Management Status (PCH_PM_STS)—Offset 1Ch" on page 2704
24	4	00000000	"PCH Power Management Status (PCH_PM_STS2)—Offset 24h" on page 2705
F0	4	200F0DE4	"ADR Enable (ADR_EN)—Offset F0h" on page 2707
F8	4	00000000	"System Time Capture Trigger (SYSTIMCT)—Offset F8h" on page 2709
FC	4	00000000	"ACPI Timer Control (ACPI_TMR_CTL)—Offset FCh" on page 2709
120	4	00000432	"GPIO Configuration (GPIO_CFG)—Offset 120h" on page 2710
124	4	00000000	"Global Reset Causes (GBLRST_CAUSE0)—Offset 124h" on page 2711
128	4	00000000	"Global Reset Causes (GBLRST_CAUSE1)—Offset 128h" on page 2713
12C	4	00000000	"Host Partition Reset Causes (HPR_CAUSE0)—Offset 12Ch" on page 2714
200	4	0000FFFF	"modPHY Power Management Configuration Reg 1 (MODPHY_PM_CFG1)—Offset 200h" on page 2715
204	4	05000000	"modPHY Power Management Configuration Reg 2 (MODPHY_PM_CFG2)—Offset 204h" on page 2716
208	4	00000000	"modPHY Power Management Configuration Reg 3 (MODPHY_PM_CFG3)—Offset 208h" on page 2718
20C	4	00000000	"modPHY Power Management Configuration Reg 4 (MODPHY_PM_CFG4)—Offset 20Ch" on page 2719
3F0	4	00000000	"IE_STS (IE_STS)—Offset 3F0h" on page 2720
3F4	4	00000000	"ME_STS (ME_STS)—Offset 3F4h" on page 2722
620	4	00000000	"Static PG Related Function Disable Register 1 (ST_PG_FDIS_PMC_1)—Offset 620h" on page 2723
628	4	00000000	"Non-Static PG Related Function Disable Register 1 (NST_PG_FDIS_1)—Offset 628h" on page 2724
640	4	00000000	"Non-Static PG Fuse Disable Read 1 Register (N_STPG_FUSE_SS_DIS_RD_1)—Offset 640h" on page 2724
644	4	00000000	"Static PG Fuse and Soft Strap Disable Read Register 2 (STPG_FUSE_SS_DIS_RD_2)—Offset 644h" on page 2725

58.1.3 Host I/O Space—ABASE

An index of the registers that are accessible in Host I/O Space is shown here.

Table 58-3. Summary of I/O Registers—ABASE

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"Power Management 1 Enables and Status (PM1_EN_STS)—Offset 0h" on page 2726
4	4	00000000	"Power Management 1 Control —Offset 4h" on page 2728
8	4	00000000	"Power Management 1 Timer (PM1_TMR)—Offset 8h" on page 2729
30	4	00000002	"SMI Control and Enable (SMI_EN)—Offset 30h" on page 2730
34	4	00000000	"SMI Status Register (SMI_STS)—Offset 34h" on page 2732
40	4	00000000	"General Purpose Event Control (GPE_CTRL)—Offset 40h" on page 2735
44	4	00000000	"Device Trap Status Register (DEVTRAP_STS)—Offset 44h" on page 2736
50	4	00000000	"PM2a Control Block (PM2A_CNT_BLK)—Offset 50h" on page 2737
54	4	00002000	"Over-Clocking WDT Control (OC_WDT_CTL)—Offset 54h" on page 2737
80	4	00000000	"General Purpose Event 0 Status [31:0] (GPE0_STS_31_0)—Offset 80h" on page 2738
84	4	00000000	"General Purpose Event 0 Status [63:32] (GPE0_STS_63_32)—Offset 84h" on page 2739
88	4	00000000	"General Purpose Event 0 Status [95:64] (GPE0_STS_95_64)—Offset 88h" on page 2739
8C	4	00000000	"General Purpose Event 0 Status [127:96] (GPE0_STS_127_96)—Offset 8Ch" on page 2740
90	4	00000000	"General Purpose Event 0 Enable [31:0] (GPE0_EN_31_0)—Offset 90h" on page 2742
94	4	00000000	"General Purpose Event 0 Enable [63:32] (GPE0_EN_63_32)—Offset 94h" on page 2742
98	4	00000000	"General Purpose Event 0 Enable [95:64] (GPE0_EN_95_64)—Offset 98h" on page 2742
9C	4	00000000	"General Purpose Event 0 Enable [127:96] (GPE0_EN_127_96)—Offset 9Ch" on page 2743

58.1.4 Host I/O Space—Fixed Address

An index of the registers that are accessible in Host I/O Space is shown here.

Table 58-4. Summary of I/O Registers—Fixed Addresses

Address (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
CF9	1	0	"Reset Control Register (RST_CNT)" on page 2745

58.1.5 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 58-5. Summary of Sideband Registers—0x82

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
B0	00000000	"Advanced Power Management Status and Control Port (APM_STS_CNT)—Offset B0h" on page 2746
B4	00000000	"Misc SB Reg0 (MISC_SBR0)—Offset B4h" on page 2746

58.2 Registers in Configuration Space

58.2.1 PCI Identifier (PCIID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:2] + 0h

Default: 19DE8086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19DE RO/V	**Device Identification (DID):** These bits are assigned by Intel.
15:0	0x8086 RO	**Vendor Identification (VID):** Indicates Intel

58.2.2 ACPI Base Address (ABASE)—Offset 40h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:2] + 40h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW/L	**Base Address (BA):** Provides the 256 bytes of I/O space for ACPI logic. This field is locked by GEN_PMCON_B.ACPI_BASE_LOCK.
7:1	0x0 RO	**Reserved (RSVD_7_1):** Always 0.
0	0x1 RO	**Space Type (STYPE):** Always 1 to indicate I/O space.

58.2.3 ACPI Control (ACTL)—Offset 44h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:2] + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_31_9):** Reserved.
8	0x0 RW	**PWRM Enable (PWRM_EN):** When set, decode of the Host Memory Space range pointed by PWRMBASE is enabled.
7	0x0 RW	**ACPI Enable (EN):** When set, decode of the I/O range pointed to by the ACPI base register is enabled and the ACPI power management function is enabled.
6:3	0x0 RO	**Reserved (RSVD_6_3):** Reserved.
2:0	0x0 RW	**SCI IRQ Select (SCIS):** Specifies on which IRQ the SCI will internally appear. If not using the APIC, the SCI must be routed to IRQ[9-11], and that interrupt is not sharable with the SERIRQ stream, but is shareable with other PCI interrupts. If using the APIC, the SCI can also be mapped to IRQ20-23, and can be shared with other interrupts. Bits - SCI Map ---- - ------- • 000 - IRQ9 • 001 - IRQ10 • 010 - IRQ11 • 011 - Reserved • 100 - IRQ20 (only if APIC is enabled) • 101 - IRQ21 (only if APIC is enabled) • 110 - IRQ22 (only if APIC is enabled) • 111 - IRQ23 (only if APIC is enabled) When the interrupt is mapped to APIC interrupts 9, 10 or 11, the APIC should be programmed for active-high reception. When the interrupt is mapped to APIC interrupts 20 through 23, the APIC should be programmed for active-low reception.

58.2.4 General PM Configuration A (GEN_PMCON_A)—Offset A0h

Usage: ACPI and Legacy.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:2] + A0h

Default: A0000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW	**GBE Prep Non-fatal Timeout Enable (GBE_PREP_NFTO_EN):** When cleared, this bit causes the PMC to disable the GBE Prep non-fatal timeout, causing the PMC to wait indefinitely for the ACK STS (response) for Reset/Boot Prep message from the GBe MAC. When set, a non-fatal timeout will apply to the Reset/Boot Prep handshake.
30	0x0 RW	**RSVD:** Reserved
29	0x1 RW	**RSVD:** Reserved
28	0x0 RW	**After G3 PHY Power Enable (AG3_PP_EN):** This bit determines the Host software contribution to whether the LAN PHY is powered up after exiting G3.This bit is in the RTC power well.
27	0x0 RW	**Sx PHY Power Enable (SX_PP_EN):** This bit determines the Host software contribution to whether the LAN PHY remains powered in an Sx/MOFF state that was entered from S0 (rather than from G3).
26:24	0x0 RO	**Reserved (RSVD_26_24):** Reserved.
23	0x0 RW	**DRAM Initialization Scratchpad Bit (DISB):** This bit does not affect hardware functionality in any way. It is provided as a scratchpad bit that is maintained through main power well resets and CF9h-initiated resets. If the bit is 1, then the DRAM initialization was interrupted.
22	0x0 RO	**Reserved (RSVD_22):** Reserved.
21	0x0 RO/V	**Memory Placed in Self-Refresh (MEM_SR):** This bit will be set to 1 if DRAM should have remained powered and held in Self-Refresh through the last power state transition (i.e. the last time the system left S0). The scenarios where this should be the case are: • successful S3 entry and exit • successful Host partition reset without power cycle This indicates that memory was successfully placed into Self-Refresh. This bit will be cleared whenever the SoC begins a transition out of S0.
20:19	0x0 RO	**Reserved (RSVD_20_19):** Reserved.
18	0x0 RW/1C/V	**Minimum SLP_S4# Assertion Width Violation Status (MS4V):** Hardware sets this bit when the SLP_S4# assertion width is less than the time programmed in the SLP_S4# Minimum Assertion Width field in the GEN_PMCON_B register.
17	0x0 RO	**Reserved (RSVD_17):** Reserved.
16	0x0 RW/1C/V	**Global Reset Status (GBL_RST_STS):** This bit is set after a global reset (not G3 or DeepSx) occurs. See the GEN_PMCON_B.HOST_RST_STS bit for potential usage models.
15	0x0 RW	**Allow iCLK PLL Shutdown in C0 (ALLOW_ICLK_PLL_SD_INC0):** When this bit is left at '0' (default), PMC allows iCLK PLL Shutdown only when the CPU is in a non-C0 state.
14	0x0 RW	**Dynamic mPHY CRI Clock Gate Override (MPHY_CRICLK_GATE_OVR):** • 0: Enable CRI clock gating in the modPHY • 1: Disable CRI clock gating in the modPHY BIOS reading this register should always return the correct value.

Bit Range	Default & Access	Field Name (ID): Description
13	0x0 RW	**Allow OPI PLL Shutdown in C0 (ALLOW_OPI_PLL_SD_INC0):** When this bit is left at '0' (default), PMC allows OPI PLL Shutdown only when the CPU is in a non-C0 state. When set to '1', the OPI PLL can be shut down when the CPU is in C0 or Cx state assuming all other gating conditions are satisfied.
12	0x0 RW	**Allow SPXB Clock Gating in C0 (ALLOW_SPXB_CG_INC0):** When this bit is left at '0' (default), PMC allows SBXB Clock gating only when the CPU is in a non-C0 state.
11	0x0 RO	**Reserved (RSVD_11):** Reserved.
10	0x0 RW	**BIOS PCI Express Enable (BIOS_PCI_EXP_EN):** This bit acts as a global enable for the SCI associated with the PCI express ports. If this bit is not set, then the various PCI Express ports cannot cause the PCI_EXP_STS bit to go active.
9	0x0 RO/V	**Power Button Level (PWRBTN_LVL):** This read-only bit indicates the current state of the PMU_PWRBTN_N signal. • 1= High • 0 = Low
8	0x0 RO	**Reserved (RSVD_8):** Reserved.
7	0x0 RW	**Allow L1.LOW Entry During C0 (ALLOW_L1LOW_C0):** When this bit is 0, the PMC only allows L1.LOW entry if the CPU is in Cx (EA = 0). When set to 1, the PMC allows L1.LOW entry regardless of the value of EA.
6	0x0 RW	**Allow L1.LOW Entry with OPI Voltage On (ALLOW_L1LOW_OPI_ON):** When this bit is 0, the PMC only allows L1.LOW entry if the OPI voltage is off. When this bit is 1, the PMC allows L1.LOW entry regardless of whether the OPI voltage is on/off.
5	0x0 RW	**Allow L1.LOW Entry with CPU BCLK REQ Asserted (ALLOW_L1LOW_BCLKREQ_ON):** When this bit is 0, the PMC only allows L1.LOW entry if the CPUs BCLK request is de-asserted. When this bit is 1, the PMC allows L1.LOW entry regardless of whether the CPUs BCLK request is asserted/de-asserted.
4	0x0 RW/L	**SMI Lock (SMI_LOCK):** When this bit is set, writes to the GLB_SMI_EN bit will have no effect. Once the SMI_LOCK bit is set, writes of 0 to SMI_LOCK bit will have no effect (i.e. once set, this bit can only be cleared by host_prim_rst_b).
3	0x0 RW/L	**Reserved:** Reserved.
2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1:0	0x0 RW	**Period SMI Select (PER_SMI_SEL):** Software sets these bits to control the rate at which the periodic SMI# is generated: • 00 = 64 seconds (default) • 01 = 32 seconds • 10 = 16 seconds • 11 = 8 seconds Tolerance for the timer is ± 1 second.

58.2.5 General PM Configuration B (GEN_PMCON_B)—Offset A4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:2] + A4h

Default: 00004007h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Reserved (RSVD_31_19):** Reserved.
18	0x0 RW/L	**RSVD:** Reserved
17	0x0 RW/L	**ACPI Base Lock (ACPI_BASE_LOCK):** When set to 1, this bit locks down the ACPI Base Address Register (ABASE) located at offset 40h. The Base Address Field becomes read-only. This bit becomes locked when a value of 1b is written to it.
16	0x0 RW/L	**RSVD:** Reserved
15	0x0 RW	**PME B0 S5 Disable (PME_B0_S5_DIS):** When cleared (default), wake events from PME_B0_STS are allowed in S5 if PME_B0_EN = 1. When set to 1, this bit blocks wake events from PME_B0_STS in S5, regardless of the state of PME_B0_EN. The net effect of setting PME_B0_S5_DIS = 1 is described here: • When PME_B0_EN = 0 and WOL Enable Override = 0: Don't Wake when in S5. • When PME_B0_EN = 0 and WOL Enable Override = 1: Wake (LAN only) when in S5. • When PME_B0_EN = 1 and WOL Enable Override = 0: Don't Wake when in S5. • When PME_B0_EN = 1 and WOL Enable Override = 1: Wake (LAN only) when in S5. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
14	0x1 RW/1C	**SUS Well Power Failure (SUS_PWR_FLR):** This bit is set to '1' whenever SUS well power is lost, as indicated by pri_pwrgood_rst_b assertion.
13	0x0 RW	**WOL Enable Override (WOL_EN_OVRD):** When this bit is set to 1, the integrated LAN is enabled to wake the system from S5 regardless of the value in the PME_B0_EN bit in the GPE0_EN register.
12	0x0 RW/L	**Disable SLP_X Stretching After SUS Well Power Up (DIS_SLP_X_STRCH_SUS_UP):** When this bit is set to 1, all PMU_SLP_* pin stretching is disabled when powering up after a SUS well power loss. When this bit is left at 0, PMU_SLP_* stretching will be performed after SUS power failure as enabled in various other fields.
11:10	0x0 RW/L	**SLP_S3# Minimum Assertion Width (SLP_S3_MIN_ASST_WDTH):** This 2-bit value indicates the minimum assertion width of the PMU_SLP_S3_N signal to guarantee that the Main power supplies have been fully power-cycled. This value may be modified per platform depending on power supply capacitance, board capacitance, power failure detection circuits, etc. Settings are: • 00: 60 µsec • 01: 1 ms • 10: 50 ms • 11: 2 sec This field is not writable when the SLP_Sx# Stretching Policy Lock- Down bit is set. This bit is cleared by the pri_pwrgood_rst_b pin.
9	0x0 RW/1C/V	**Host Reset Status (HOST_RST_STS):** This bit is set by hardware when a host partition reset (not a global reset, DeepSx, or G3) occurs.
8	0x0 RO	**Reserved (RSVD_8):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RW	**SWSMI Rate Select (SWSMI_RATESEL):** This 2-bit value indicates when the SWSMI timer will time out. Valid values are: • 00 1.5ms ± 0.6ms • 01 16ms ± 4ms • 10 32ms ± 4ms • 11 64ms ± 4ms This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
5:4	0x0 RW/L	**SLP_S4# Minimum Assertion Width (S4MAW):** This 2-bit value indicates the minimum assertion width of the SLP_S4# signal to guarantee that the DRAMs have been safely power-cycled. This value may be modified per platform depending on DRAM types, power supply capacitance, etc. Valid values are: • 11: 1 second • 10: 2 seconds • 01: 3 seconds • 00: 4 seconds This value is used in two ways: • 1. If the PMU_SLP_S45_N assertion width is ever shorter than this time, the status bit MS4V of the GEN_PMCON_A register is set for BIOS to read when S0 is entered • 2. If enabled by bit 3 in this register, the hardware will prevent the PMU_SLP_S45_N signal from deasserting within this minimum time period after asserting.
3	0x0 RW/L	**SLP_S4# Assertion Stretch Enable (S4ASE):** When set to 1, the PMU_SLP_S45_N pin (which includes the ME override logic) will minimally assert for the time specified in bits 5:4 of this register. When 0, the minimum assertion time for PMU_SLP_S45_N is the same as the timing defined in the timing tables.
2	0x1 RW	**RTC_PWR_STS (RPS):** The SoC will set this bit to 1 to indicate a weak or missing battery. The bit will remain set until the software clears it by writing a 0 back to this bit position. This bit is in the RTC power well and is not cleared by any type of reset.
1	0x1 RW/1C	**PWR_FLR (PF):** • 0 = Indicates that the trickle current has not failed since the last time the bit was cleared. • 1 = Indicates that the trickle current (from the main battery or trickle supply) was removed or failed. Software writes a 1 to this bit to clear it.
0	0x1 RW/V	**AFTERG3_EN (AG3E):** Determines what state to go to when power is reapplied after a power failure (G3 state). • 0 = System will return to an S0 state (boot) after power is re-applied. • 1 = System will return to the S5 state. In the S5 state, the only enabled wake-up event is the Power Button or any enabled wake event that was preserved through the power failure. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.

58.2.6 Extended Test Mode Register 3 (ETR3)—Offset ACh

This register resides in the primary Core well. All bits except bit[23:16] are reset by host_deep_rst_b. Bit[23:16] are reset by pri_pwrgood_rst_b only.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:2] + ACh

Default: 80000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x1 RW/V/L	**CF9h Lockdown (CF9LOCK):** When set, this will lock the "CF9h Global Reset" bit. When set, this register locks itself. This register is reset by a CF9h reset. ***Note:*** In manufacturing/ debug environments this bit can be left as default 0b. In all other environments, BIOS must program this bit to 1b.
30:21	0x0 RO	**Reserved (RSVD_30_21):** These bits are reserved for Intel.
20	0x0 RW/L	**CF9h Global Reset (CF9GR):** When this bit is set, a CF9h write of 6h or Eh will cause a Global Reset of both the Host and the ME partitions. If this bit is cleared, a CF9h write of 6h or Eh will only reset the Host partition.
19:0	0x0 RO	**Reserved (RSVD_19_0):** These bits are reserved for Intel.

58.3 Registers in Memory Space—PWRMBASE

58.3.1 Wake Alarm Device Timer: AC (WADT_AC)—Offset 0h

Bits in this register only need to be valid for reading when the Main power well is up. However, since some of the events may initially be detected while the Main power well and SUS well are down, they are marked as DSW bits.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 0h

Default: FFFFFFFFh

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xFFFFFFFF RW/V	**Wake Alarm Device Timer Value for AC Mode (WADT_AC_VAL):** This field contains the 32-bit wake alarm device timer value (granularity 1s) for AC power. The timer begins decrementing when written to a value other than FFFFFFFFh (regardless of the power source when the write occurs). Upon counting down to 0: • If on AC power, GPE0b_STS.WADT_STS will be set. This status bit being set will generate a host wake if GPE0b_EN.WADT_EN is 1. • If the power source is DC at this time, the status bit is not set. However, if AC power subsequently returns to the platform, the AC Expired Timer begins running. See the WADT_EXP_AC register for details. • The timer returns to its default value of FFFFFFFFh.

58.3.2 Wake Alarm Device Timer: DC (WADT_DC)—Offset 4h

Bits in this register only need to be valid for reading when the Main power well is up. However, since some of the events may initially be detected while the Main power well and SUS well are down, they are marked as DSW bits.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 4h

Default: FFFFFFFFh

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xFFFFFFFF RW/V	**Wake Alarm Device Timer Value for DC Mode (WADT_DC_VAL):** This field contains the 32-bit wake alarm device timer value (granularity 1s) for DC power. The timer begins decrementing when written to a value other than FFFFFFFFh (regardless of the power source when the write occurs). Upon counting down to 0: • If on DC power, GPE0b_STS.WADT_STS will be set. This status bit being set will generate a host wake if GPE0b_EN.WADT_EN is 1. • If the power source is AC at this time, the status bit is not set. However, if DC power subsequently returns to the platform, the DC Expired Timer begins running. See the WADT_EXP_DC register for details. • The timer returns to its default value of FFFFFFFFh.

58.3.3 Wake Alarm Device Expired Timer: AC (WADT_EXP_AC)—Offset 8h

Bits in this register only need to be valid for reading when the Main power well is up. However, since some of the events may initially be detected while the Main power well and SUS well are down, they are marked as DSW bits.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 8h

Default: FFFFFFFFh

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xFFFFFFFF RW/V	**Wake Alarm Device Expired Timer Value for AC Mode (WADT_EXP_AC_VAL):** This field contains the 32-bit wake alarm device "Expired Timer" value (granularity 1s) for AC power. The timer begins decrementing after switching from DC to AC power, in the case where the WADT_AC timer has already expired while the platform was on DC power. This timer only decrements while operating on AC power. So if the power source switches back to DC power, the timer will stop (but not reset). When AC power returns, the timer will again begin decrementing. ***Note:*** This timer will only begin decrementing under the conditions described above if this field has been configured for something other than its default value of FFFFFFFFh (i.e. FFFFFFFFh = disabled). Upon expiration of this timer: • If on AC power, GPE0b_STS.WADT_STS will be set. This status bit being set will generate a host wake if GPE0b_EN.WADT_EN is 1. • BOTH the AC and DC Expired Timers return to their defaults value of FFFFFFFFh.

58.3.4 Wake Alarm Device Expired Timer: DC (WADT_EXP_DC)—Offset Ch

Bits in this register only need to be valid for reading when the Main power well is up. However, since some of the events may initially be detected while the Main power well and SUS well are down, they are marked as DSW bits.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + Ch

Default: FFFFFFFFh

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xFFFFFFFF RW/V	**Wake Alarm Device Expired Timer Value for DC Mode (WADT_EXP_DC_VAL):** This field contains the 32-bit wake alarm device "Expired Timer" value (granularity 1s) for DC power. The timer begins decrementing after switching from AC to DC power, in the case where the WADT_DC timer has already expired while the platform was on AC power. This timer only decrements while operating on DC power. So if the power source switches back to AC power, the timer will stop (but not reset). When DC power returns, the timer will again begin decrementing. ***Note:*** This timer will only begin decrementing under the conditions described above if this field has been configured for something other than its default value of FFFFFFFFh (i.e. FFFFFFFFh = disabled). Upon expiration of this timer: • If on DC power, GPE0b_STS.WADT_STS will be set. This status bit being set will generate a host wake if GPE0b_EN.WADT_EN is 1. • BOTH the AC and DC Expired Timers return to their defaults value of FFFFFFFFh.

58.3.5 Power and Reset Status (PRSTS)—Offset 10h

Bits in this register only need to be valid for reading when the Main power well is up. However, since some of the events may initially be detected while the Main power well is down, they are marked as suspend well bits. All suspend well bits in this register are reset by global_rst_b.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 10h

Default: 05000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x5 RO/V	**Power Management Controller Product ID (PMC_PRODID):** This field communicates the Product Family of the power management functionality.
23:16	0x0 RO/V	**Power Management Controller Revision ID (PMC_REVID):** This field communicates the implementation revision of the power management functionality.
15:12	0x0 RO	**Reserved (RSVD_15_12):** Reserved.
11	0x0 RW/1C/V	**Patch Copied Over Status (PATCH_COPIED_STS):** The SoC sets this bit when the Patch code is successfully authenticated and loaded into the SoC from the flash.
10	0x0 RO/V	**Patch Revision Not Compatible Status (PATCH_REV_NOT_COMP):** The SoC sets this bit when the Patch code is not compatible with the Power Management Controller Product and/or Revision. This bit remains valid after a PMC Patch load is attempted until the next global_rst_b.
9	0x0 RO/V	**Patch Load Timeout Status (PATCH_LOAD_TO):** The SoC sets this bit if the loading function fails to complete within a reasonable time limit.
8	0x0 RO/V	**PMC Operational Status (PMC_OP_STS):** The SoC sets this bit when the PMC becomes operational after completing the Patch Load, or, if no patch is needed. BIOS must wait for this bit to be set before performing resets or sleep events. This bit remains valid after a PMC Patch load until the next global_rst_b.
7	0x0 RW/1C/V	**VE Watch Dog Timer Status (VE_WDT_STS):** This bit will be set to '1' when the VE Watch Dog Timer triggers a reset. It will be cleared by a write of '1' by software.
6	0x0 RW/1C/V	**IE Host Wake Status (IE_HOST_WAKE_STS):** This bit is set when the IE generates a non-maskable wake event and is not affected by any other enable bit. When this bit is set, the host power management logic wakes to S0.
5	0x0 RW/1C/V	**Wake On LAN Override Wake Status (WOL_OVR_WK_STS):** This bit gets set when integrated LAN Signals a Power Management Event AND the system is in S5. BIOS can read this status bit to determine this wake source. Software clears this bit by writing a 1 to it.
4	0x0 RO	**Reserved (RSVD_4):** Reserved.
3	0x0 RO/V	**HR_SHAD_IE_EN_STS:** This register shadows the IE ROM Check in host space. • 0 = IE is disabled • 1 = IE is enabled
2:1	0x0 RO	**Reserved (RSVD_2_1):** Reserved.
0	0x0 RW/1C/V	**ME_HOST_WAKE_STS:** This bit is set when the ME generates a non-maskable wake event and is not affected by any other enable bit. When this bit is set, the host power management logic wakes to S0.

58.3.6 Power Management Configuration Reg 1 (PM_CFG)—Offset 18h

This register contains misc. fields used to configure the SoC power management behavior. This register is in multiple power wells and reset domains (see below).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 18h

Default: 00000020h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**SATA Interface Disable Indication (SATA_DIS_IND):** When set to 1, this bit indicates that the SATA interface on the SoC is completely disabled. Therefore, the mPhy lanes normally assigned to SATA will operate through the PCIe controller (or not be used at all). When cleared, it indicates that at least some of the SATA interface lanes may be used actively in the SoC by the SATA controller, so none of the four lanes assigned to SATA interface can operate through the PCIe controller.
30	0x0 RW	**Timing t591 (TIMING_T591):** This field configures t591 timing involved in the over-clocking flow (Wait times between writes from PMC to ICC registers when executing BCLK slow ramp flow) ***Note:*** Encodings are all min timings.
29	0x0 RW	**Allow 24MHz Crystal Oscillator Shutdown (ALLOW_24_OSC_SD):** When this bit is '0', the 24MHz crystal oscillator will always be running while in S0. When this bit is '1', the 24MHz crystal oscillator may be shut down in S0 (Cx only) if all other conditions allow.
28	0x0 RW	**Time Sync Maximum Attempts (TS_MAXTRY):** The value of this bit determines how many times the PMC will retry time synchronization before stopping and reporting failure to the initiator. Encoding: • 0 Maximum of 5 attempts • 1 Maximum of 10 attempts
27	0x0 RW/L	**Debug Mode Lock (DBG_MODE_LOCK):** When this bit is set to '1', the following bit is locked down • ETR3.SKIP_HOST_RST_HS • ETR3.RST_SX_TO_DBG • ETR3.PSMI_DGB_MODE_EN This bit becomes locked when a value of 1b is written to it. Writes to 0 to this bit are always ignored. Once locked, the only way the bit gets cleared is through a PLTRST# assertion.
26:24	0x0 RO	**Reserved (RSVD_26_24):** Reserved.
23	0x0 RW	**Enable Global Reset on Uncorrectable Parity Error on PMC SRAM Interface (EN_PMC_UNC_ERR):** If this bit is set to '1', a global reset is triggered when a parity error is detected on PMC's SRAM interfaces. No action is taken on such parity errors if this bit is '0'. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
22	0x0 RO	**Reserved (RSVD_22):** Reserved.
21	0x0 RW	**RTC Wake from DeepSx Disable (RTC_DSX_WAKE_DIS):** When set, this bit disables RTC wakes from waking the system from DeepSx. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
20	0x0 RO	**Reserved (RSVD_20):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
19:18	0x0 RW/L	**SLP_SUS# Minimum Assertion Width (SLP_SUS_MIN_ASST_WDTH):** This 2-bit value indicates the minimum assertion width of the SLP_SUS# signal to guarantee that the SUS well power supplies have been fully power-cycled. This value may be modified per platform depending on power supply capacitance, board capacitance, power failure detection circuits, etc. Settings are: • 00 = 0 ms (i.e. stretching disabled - default) • 01 = 500ms • 10 = 1s • 11 = 4s This field is not writable when the SLP_Sx# Stretching Policy Lock- Down bit is set. This field is ignored when exiting a G3 state if the "Disable SLP_X Stretching After SUS Power Failure" bit is set. Note that unlike with all other SLP_* pin stretching, this disable bit only impacts SLP_SUS# stretching during G3 exit rather than both G3 and DeepSx exit. SLP_SUS# stretching always applies to DeepSx regardless of the disable bit. **Programming Note:** For platforms that enable DeepSx, BIOS must program SLP_SUS# stretching to be greater than or equal to the largest stretching value on any other SLP_* pin (SLP_S3#, SLP_S4#, SLP_LAN#, or SLP_A#). This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
17:16	0x0 RW/L	**SLP_A# Minimum Assertion Width (SLP_A_MIN_ASST_WDTH):** This 2-bit value indicates the minimum assertion width of the SLP_A# signal to guarantee that the ASW power supplies have been fully power-cycled. This value may be modified per platform depending on power supply capacitance, board capacitance, power failure detection circuits, etc. Settings are: 00 = 0 ms (i.e. stretching disabled - default) 01 = 4 s 10 = 98 ms 11 = 2 s This field is not writable when the SLP_Sx# Stretching Policy Lock- Down bit is set. This field is ignored when exiting a G3 or DeepSx state if the "Disable SLP_X Stretching After SUS Power Failure" bit is set. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
15:14	0x0 RW/L	**SLP_LAN# Minimum Assertion Width (SLP_LAN_MIN_ASST_WDTH):** This 2-bit value indicates the minimum assertion width of the SLP_LAN# signal to guarantee that the power to the PHY has been fully power-cycled. This value may be modified per platform depending on power supply, capacitance, board capacitance, power failure detection circuits, etc. This field is not writable when the SLP_Sx# Stretching Policy Lock Down bit is set to '1'. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
13	0x0 RW	**After G3 Last State Enable (AG3_LS_EN):** When GEN_PMCON_B.AG3E is 0, AG3_LS_EN determines whether the SoC will consider the platforms previous state when determining whether to power-up after G3. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active. Encodings: • 0 (default): SoC power-up policies after G3 do not depend on the platforms state when the G3 occurred. • 1: SoC power-up policies after G3 depend on the platforms state when the G3 occurred. - If the power failure occurred while the platform was in S0 or while in the process of going to S0, the platform will power-up to S0 upon exiting G3. - If the power failure occurred while the platform was in Sx or while in the process of going to Sx, the platform will stay in S4/S5 upon exiting G3. ***Note:*** This bit applies only when GEN_PMCON_B.AG3E is 0. If AG3E is 1, the platform will always stay in S4/S5 after G3 regardless of the value of AG3_LS_EN. ***Note:*** The destination state is considered to be S0 during both host wake and throughout host partition resets with/without power cycle.

Bit Range	Default & Access	Field Name (ID): Description
12	0x0 RW	**After Type 8 Global Reset Last State Enable (A8GR_LS_EN):** AGR_LS_EN determines whether the SoC will consider the platforms previous state when determining whether to power-up after non-thermal and non-explicitly requested type 8 global resets. See the Reset Sources table for a list of impacted reset types. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active. Encodings: • 0 (default): SoC power-up policies after a global reset do not depend on the platforms state when the reset occurred. • 1: SoC power-up policies after a global reset depend on the platforms state when the reset occurred. - If the global reset occurred while the platform was in S0 or while in the process of going to S0, the platform will power-up to S0 after the reset. - If the global reset occurred while the platform was in Sx or while in the process of going to Sx, the platform will stay in S5 upon exiting G3. ***Note:*** The destination state is considered to be S0 during both host wake and throughout host partition resets with/without power cycle.
11	0x0 RW	**Global Reset Three Strike Counter Enable (GR_TSC_EN):** When set, GR_TSC_EN will cause the PMC to keep the platform in S5 after the third consecutive type 7 global reset occurs during the boot flow. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active. The three strike counter is reset in the following situations: • The system reaches S0 • A type 8 global reset occurs, including after the three strike counter causes the system to stay in S5. • RSMRST_N asserts (due to DeepSx entry or a G3 event occurring)
10	0x0 RW	**Power Button Debounce Mode (PB_DB_MODE):** This bit controls when interrupts (SMI#, SCI) are generated in response to assertion of the PMU_PWRBTN_N pin. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active. This bit's values cause the following behavior: • '0': The 16ms debounce period applies to all usages of the PMU_PWRBTN_N pin (legacy behavior). • '1': When a falling edge occurs on the PMU_PWRBTN_N pin, an interrupt is generated and the 16ms debounce timer starts. Subsequent interrupts are masked while the debounce timer is running. ***Note:*** Power button override logic always samples the post-debounce version of the pin.
9:8	0x0 RW/L	**Reset Power Cycle Duration (PWR_CYC_DUR):** The value in this register determines the minimum time a platform will stay in reset (SLP_S3#, SLP_S4#, SLP_S5# asserted and also SLP_A# and SLP_LAN# asserted if applicable) during a host partition reset with power cycle or a global reset. The duration programmed in this register takes precedence over the applicable SLP_# stretch timers in these reset scenarios. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active. This field is not writable when the SLP_Sx# Stretching Policy Lock-Down bit is set. Note that the duration programmed in this register should never be smaller than the stretch duration programmed in the following registers • GEN_PMCON_3.SLP_S3_MIN_ASST_WDTH • GEN_PMCON_3.S4MAW • PM_CFG.SLP_A_MIN_ASST_WDTH • PM_CFG.SLP_LAN_MIN_ASST_WDTH
7:6	0x0 RO	**Reserved (RSVD_7_6):** Reserved.
5	0x1 RW/V	**CPU OC Strap (COCS):** SW programs this pin with the value that should be reflected to the GPIO8_OCS pin, when the pin is in native mode. Hardware also sets this bit when the over-clocking watchdog timer expires.
4:2	0x0 RO	**Reserved (RSVD_4_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1:0	0x0 RW/V	**Timing t581 (TIMING_T581):** This field configures the t581 timing involved in the power down flow (CPUPWRGD inactive to ICC_ICLK_INIT inactive). Encodings (all min timings): • 00: 10 us (default) • 01: 100 us • 10: 1 ms • 11: 10 ms reset_type=host_deep_rst_b

58.3.7 PCH Power Management Status (PCH_PM_STS)—Offset 1Ch

This register contains misc. fields used to record events pertaining to SoC power management. Unless otherwise indicated, all RWC bits are cleared with a write of 1 by software. This register is in multiple power wells and reset domains (see below).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 1Ch

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved (RSVD_30_25):** Reserved.
16	0x0 RW/1C/V	**ADR Reset Status (ADR_RST_STS):** When set to '1', this bit indicates that the Asynchronous DRAM Refresh (ADR) flow was executed during a prior global reset entry.
15:13	0x0 RW	**BIOS Discovered DDR Speed (SPD_DDR_SPEED):** • 000=DDR 1600 • 001=DDR 1867 • 010=DDR 2133 • 011=DDR 2400 • 100=DDR 2666
12	0x0 RW	**Equal Speed Enable (EQUAL_SPEED_ENABLE):** • 0= Do not enable SSC PLL relock when SPD_DDR_SPEED = MAX_DDR_SKU • 1= enable SSC PLL relock when SPD_DDR_SPEED = MAX_DDR_SK
11	0x0 RW	**The triggered reset is an SPD reset (SPD_BIOS_RESET):** • 0= not SPD reset • 1= SPD Reset
10:7	0x0 RO	**Reserved (RSVD_10_7):** Reserved.
6	0x0 RW/1C/V	**IE uncorrectable Error Status (IE_UE_STS):** PMC FW Sets this bit as an indication that ME uncorrectable error as been forwarded to PMC FW
5:1	0x0 RO	**Reserved (RSVD_5_1):** Reserved.
0	0x0 RW/1C/V	**ME Uncorrectable Error Status (ME_UE_STS):** PMC FW sets this bit as an indication that a ME uncorrectable error has been forwarded to PMC FW.

58.3.8 PCH Power Management Status (PCH_PM_STS2)—Offset 24h

This register contains misc. fields used to record events pertaining to SoC power management. Unless otherwise indicated, all RWC bits are cleared with a write of '1' by software.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 24h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_31_21):** Reserved.
20:17	0x0 RO/V	**Current SPD SPEED (CURRENT_SPD_SPEED):** 0xxxx = undefined, use max DDR mem config (fuse) • 1000 = DDR1600 • 1001 = DDR1866 • 1010 = DDR2133 • 0000 = DDR2400 ***Note:*** The value of current SPD SPEED is only updated when the SPD reset is happened.
16	0x0 RO/V	**SPD_RESET_PCODE:** • 0 = PMC indicates to Pcode that this is not a SPD Reset. • 1 = PMC indicates to Pcode that this is a SPD Reset Set by PMC when SPD Reset is triggered
15	0x0 RW/1C/V	**IE Host Boot Prep Done Failure (IE_HBPD):** IE Host Boot Preparation did not complete.
14	0x0 RW/1C/V	**CPU Reset Done Failure (CRD):** CPU Reset Done message did not arrive from the CPU.
13	0x0 RW/1C/V	**ME Host Boot Prep Done Failure (ME_HBPD):** Intel® ME Host Boot Preparation did not complete.
12	0x0 RW/1C/V	**PINSTOP Acknowledge Failure (PINSTOP_ACK):** The GbE PHY did not respond to the PINSTOP message.
11	0x0 RW/1C/V	**PSCHS Acknowledge Failure (PSCHS_ACK):** The GbE MAC did not respond to the PSCHS message.
10	0x0 RW/1C/V	**SMT Reset Acknowledge Failure (SMT_RST_ACK):** One or more SMT controllers did not respond to the Intel® Management Engine bus reset warning.
9	0x0 RW/1C/V	**EXI State Transition Acknowledge Failure (EXI_STATE_TRANS_ACK):** EXI state transition ACK did not arrive.
8	0x0 RW/1C/V	**SPI Common Prep Handshake Failure (SPI_HRHS):** The SPI controller did not complete the host partition reset/Sx entry handshake.
7	0x0 RW/1C/V	**XCK Common Prep Handshake Failure (XCK_HRHS):** The integrated clocking unit did not complete the host partition reset/Sx entry handshake.
6	0x0 RW/1C/V	**CPU S345/Reset Warn Acknowledge Failure (CPU_S345RW_ACK):** The CPU did not respond to the GO_S345 or RESET_WARN message.
5	0x0 RW/1C/V	**CPU S1 Acknowledge Failure (CPU_S1_ACK):** The CPU did not respond to the GO_S1_XXX message.
4	0x0 RW/1C/V	**DMI L23 Entry Failure (DMI_L23):** The DMI interface did not respond to the request to entry L23.
3	0x0 RW/1C/V	**SMBus Host Reset Handshaking Failure (SMB_SRHS):** The host SMBus controller did not complete the host partition reset handshake.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/1C/V	**South Port L23 Entry Failure (SP_L23):** The SoC PCI Express ports did not complete the host partition reset/Sx entry handshake.
1	0x0 RW/1C/V	**XHCI Common Prep Handshake Failure (XHCI_HRHS):** The USB XHCI controller did not complete the host partition reset/Sx entry handshake.
0	0x0 RW/1C/V	**EVA L23 Entry Failure (EVA_L23):** The EVA did not complete the host partition reset/Sx entry handshake.

58.3.9 ADR Enable (ADR_EN)—Offset F0h

This register contains several enable bits related to the ”Automatic DIMM Self-Refresh” Asynchronous DRAM Refresh (ADR) feature. The default value of each bit is chosen based on the expected usage, but the values are programmable to retain flexibility. See the section on ADR later in chap. 16 for more information. This register is in the CORE power well and is reset by host_prim_rst_b.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + F0h

Default: 200F0DE4h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_31_30):** Reserved.
29	0x1 RW	**ADR GPIO Reset Enable (ADR_GPIO_RST_EN):** If this bit is set to '1', a Global Reset will be generated once the internal flush sequence is completed after: • Triggered by the ADR_TRIGGER signal pin (if available in the SoC product SKU). -OR- • Qualified internal events and the following are true: The ADR feature is part of the particular SoC product SKU, and ADR_FEAT_EN (bit 0) is a 1. If this bit is cleared, the active-high ADR_TRIGGER signal pin can still be enabled to affect the internal flush, but on its own, the signal does not trigger a Global Reset. ***Note:*** Unlike the other ADR_EN bits in this register, this enable bit is not required to be set to 1 for this source to trigger the warning to the SoC and CPU. This bit only impacts whether or not this source will actually trigger a Global Reset.
28:20	0x0 RO	**Reserved (RSVD_28_20):** Reserved.
19	0x1 RW/V	**IE Uncorrectable Error ADR Enable (IE_UERR_ADR_EN):** If this bit is set to '1', the IE uncorrectable SRAM error is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
18	0x1 RW/V	**IE Initiated Global Reset ADR Enable (IEGBL_ADR_EN):** If this bit is set to '1', the IE-initiated global reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
17	0x1 RW/V	**IE FW Watchdog Timer ADR Enable (IEWDT_ADR_EN):** If this bit is set to '1', the IE firmware watchdog timer global reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
16	0x1 RW/V	**IE Initiated Power Button Override ADR Enable (IEPBO_ADR_EN):** If this bit is set to '1', the IE-Initiated Power Button Override Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
15	0x0 RO	**Reserved (RSVD_15):** Reserved.
14	0x0 RW/V	**PMC Parity Error ADR Enable (PMC_PARERR_ADR_EN):** If this bit is set to '1', the PMC SUS RAM Parity Error Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '0' because this reset source is considered to be time-critical.
13	0x0 RO	**Reserved (RSVD_13):** Reserved.
12	0x0 RW/V	**SYS_PWROK Failure ADR Enable (SYSPWR_ADR_EN):** If this bit is set to '1', the SYS_PWROK Failure Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '0' because this reset source is considered to be time-critical.

Bit Range	Default & Access	Field Name (ID): Description
11	0x1 RW/V	**ME Uncorrectable Error ADR Enable (ME_UERR_ADR_EN):** If this bit is set to '1', the Intel® ME Uncorrectable SRAM error Global Reset source is included in the ADR feature. ***Note:*** Note: The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
10	0x1 RW/V	**PMC FW Watchdog Timer ADR Enable (PMCWDT_ADR_EN):** If this bit is set to '1', the PMC Firmware Watchdog Timer Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
9	0x0 RO	**Reserved (RSVD_9):** Reserved.
8	0x1 RW/V	**ME-Initiated Global Reset ADR Enable (MEGBL_ADR_EN):** If this bit is set to '1', the ME-initiated Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
7	0x1 RW/V	**ME FW Watchdog Timer ADR Enable (MEWDT_ADR_EN):** If this bit is set to '1', the ME Firmware Watchdog Timer Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
6	0x1 RW/V	**ME-Initiated Power Button Override ADR Enable (MEPBO_ADR_EN):** If this bit is set to '1', the ME-Initiated Power Button Override Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
5	0x1 RW/V	**Power Button Override ADR Enable (PBO_ADR_EN):** If this bit is set to '1', the Power Button Override Global Reset source is included in the ADR feature. ***Note:*** The default value for this bit was chosen to be '1' because this reset source is not considered to be time-critical.
4:3	0x0 RO	**Reserved (RSVD_4_3):** Reserved.
2	0x1 RW/V	**PMC FW-Initiated Global Reset ADR Enable (PMCGBL_ADR_EN):** If this bit is set to '1', all PMC firmware-initiated Global Reset sources are included in the ADR feature. The specific sources are: - SMBUS slave unconditional power down message • I/O space CF9h write or Shutdown Special-Cycle with the policy set for Global Reset. • Host partition reset entry timeout. • Sx entry timeout. • Any Host partition reset triggered with the "Promote Host Partition Reset to Global Reset" policy bit set to 1. ***Note:*** The default value for this bit was chosen to be '1' because any FW-handled global reset source is not considered to be time-critical.
1	0x0 RO	**Reserved (RSVD_1):** Reserved.
0	0x0 RW/V	**ADR Feature Enable (ADR_FEAT_EN):** If this bit is a '1' and the SoC product SKU supports ADR, SoC, support for Asynchronous DRAM Refresh is enabled. The other bits in this register determine which individual reset sources are included.

58.3.10 System Time Capture Trigger (SYSTIMCT)—Offset F8h

This register contains bits related to the "Audio Time Capture (ATC)" feature. This register is in the CORE power well and is reset by host_prim_rst_b.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + F8h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD_31_1):** Reserved.
0	0x0 RW/1S/V	**Capture Now (CAPTURE_NOW):** Write of '1' to this bit triggers time capture in all components supporting this feature. Hardware clears this register to indicate that time capture is complete. Once the bit is set to '1', subsequent writes of '0' or '1' have no effect until the bit is cleared by hardware. Please refer to the Audio Time Synchronization section for more details on Audio Synchronization and for a list of consumers of the "capture" signal from PMC. Implementation note: Once the bit is written to '1'. hardware should keep the "capture" signal asserted high for 16 PMC clocks, then keep the signal deasserted low for another 16 PMC clocks and then clear this register bit.

58.3.11 ACPI Timer Control (ACPI_TMR_CTL)—Offset FCh

This register allows software to disable the ACPI Timer, which could result in power savings for the SoC. This register is in the CORE power well and is reset by host_prim_rst_b.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + FCh

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Reserved (RSVD_31_2):** Reserved.
1	0x0 RW	**ACPI Timer Disable (ACPI_TIM_DIS):** This bit determines whether the ACPI Timer is enabled to run. Note that even when enabled, the timer only runs during S0. - 0: ACPI Timer is enabled (default) - 1: ACPI Timer is disabled (halted at the current value)
0	0x0 RW/1S/V	**ACPI Timer Clear (ACPI_TIM_CLR):** Writing a 1 to this bit will clear the ACPI Timer to all 0s. Hardware will automatically clear the bit back to '0' once the timer clear operation has completed. Writing a 0 to this bit has no effect. Implementation Note: The SoC must be capable of honoring this bit even while ACPI_TIM_DIS=1.

58.3.12 GPIO Configuration (GPIO_CFG)—Offset 120h

This register is in the PRIMARY power well and is reset by global_rst_b. reset_type=global_rst_b.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 120h

Default: 00000432h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:11	0x0 RO	**Reserved (RSVD_31_11):** Reserved.
10:8	0x4 RW	**GPIO Group to GPE_DW2 assignment encoding (GPE0_DW2):** This register assigns a specific GPIO Group to the ACPI GPE0[95:64]. • 0h = reserved[7:0] and GPP_A[23:0] • 1h = reserved[7:0] and GPP_B[23:0] • 2h = reserved[7:0] and GPP_C[23:0] • 3h = reserved[7:0] and GPP_D[23:0] • 4h = reserved[7:0] and GPP_E[23:0] • 5h = reserved[7:0] and GPP_F[23:0] • 6h = reserved[23:0] and GPP_G[7:0] • 7h = reserved[20:0] and GPD[11:0]
7	0x0 RO	**Reserved (RSVD_7):** Reserved.
6:4	0x3 RW	**GPIO Group to GPE_DW1 assignment encoding (GPE0_DW1):** This register assigns a specific GPIO Group to the ACPI GPE0[63:32]. • 0h = reserved[7:0] and GPP_A[23:0] • 1h = reserved[7:0] and GPP_B[23:0] • 2h = reserved[7:0] and GPP_C[23:0] • 3h = reserved[7:0] and GPP_D[23:0] • 4h = reserved[7:0] and GPP_E[23:0] • 5h = reserved[7:0] and GPP_F[23:0] • 6h = reserved[23:0] and GPP_G[7:0] • 7h = reserved[20:0] and GPD[11:0]
3	0x0 RO	**Reserved (RSVD_3):** Reserved.
2:0	0x2 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW0):** This register assigns a specific GPIO Group to the ACPI GPE0[31:0]. • 0h = reserved[7:0] and GPP_A[23:0] • 1h = reserved[7:0] and GPP_B[23:0] • 2h = reserved[7:0] and GPP_C[23:0] • 3h = reserved[7:0] and GPP_D[23:0] • 4h = reserved[7:0] and GPP_E[23:0] • 5h = reserved[7:0] and GPP_F[23:0] • 6h = reserved[23:0] and GPP_G[7:0] • 7h = reserved[20:0] and GPD[11:0]

58.3.13 Global Reset Causes (GBLRST_CAUSE0)—Offset 124h

This register logs causes of host partition resets.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 124h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:25	0x0 RO	**Reserved (RSVD_31_25):** Shadow additional HW initiated GBLRST causes once they're added.
24	0x0 RW/1C/V	**IE HW Uncorrectable Error (IE_UNCOR_ERR):** This bit is set to '1' by hardware when a global reset is triggered by IE hardware due to the detection of an uncorrectable ECC or parity error on a data read from one of its SRAMs.
23	0x0 RW/1C/V	**IE FW Watchdog Timer (IE_WDT):** This bit is set to '1' by hardware when a global reset is triggered by the second expiration of the IE firmware watchdog timer.
22	0x0 RW/1C/V	**IE-Initiated Global Reset (IE_GBL):** This bit is set to '1' by hardware when a global reset is triggered by an ME FW write of 1's to both GENCTL.'IE-Partition Reset' and GENCTL.'IE-Initiated Host Reset With Power Cycle' in the same write cycle (this is IE FW's method of requesting a global reset).
21	0x0 RW/1C/V	**IE-Initiated Power Button Override (IE_PBO):** This bit is set to '1' by hardware when a global reset is triggered by an IE FW write of '1' to GENCTL.'IE-Initiated Power Button Override
20	0x0 RW/1C/V	**Over-Clocking WDT Expiration In ICC Survivability Mode (OC_WDT_EXP_ICCSURV):** This bit is set to '1 by hardware when a global reset is triggered by the expiration of the over-clocking watchdog timer while running in a mode that has ICC survivability impact (OC_WDT_ICCSURV=1).
19	0x0 RW/1C/V	**Over-Clocking WDT Expiration In Non-ICC Survivability Mode (OC_WDT_EXP_NO_ICCSURV):** This bit is set to '1 by hardware when a global reset is triggered by the expiration of the over-clocking watchdog timer while running in a mode that does not have ICC survivability impact (OC_WDT_ICCSURV=0).
18	0x0 RW/1C/V	**ADR GPIO Reset (ADR_GPIO_RST):** This bit is set to '1' by hardware when a global reset is triggered by the assertion of the SoC ADR_TRIGGER signal pin.
17	0x0 RW/1C/V	**ME HW Uncorrectable Error (ME_UNCOR_ERR):** This bit is set to '1' by hardware when a global reset is triggered by ME hardware due to the detection of an uncorrectable ECC or parity error on a data read from one of its SRAM s.
16	0x0 RW/1C/V	**CPU Thermal Runaway Watchdog Timer (CPU_THRM_WDT):** This bit is set to '1' by hardware when a global reset is triggered by the expiration of the CPU Thermal Runaway Watchdog Timer.
15:14	0x0 RW/1C/V	**Reserved (RSVD_15_14):** Reserved.
13	0x0 RW/1C/V	**AS Well Power Failure (ASW_FLR):** This bit is set to '1' by hardware when a global reset is triggered by an unexpected loss of ASW power (i.e. a deassertion of APWROK at an unexpected time).
12	0x0 RW/1C/V	**SYS_PWROK Failure (SYSPWR_FLR):** This bit is set to '1' by hardware when a global reset is triggered by an unexpected loss of SYS_PWROK. FW arms this global reset source via GBLRST_CTL.EN_SYSPWR_FLR. This register bit is in the RTC power well and is retained if the system has a functioning RTC battery during the G3 Mechanical Off state.
11	0x0 RW/1C/V	**PCH_PWROK Failure (PCHPWR_FLR):** This bit is set to '1' by hardware when a global reset is triggered by an unexpected loss of PCH_PWROK. FW arms this global reset source via GBLRST_CTL.EN_PCHPWR_FLR. This register bit is in the RTC power well and is retained if the system has a functioning RTC battery during the G3 Mechanical Off state.
10	0x0 RW/1C/V	**PMC Firmware Global Reset (PMC_FW):** This bit is set to '1' by hardware when a global reset is triggered by a request from PMC firmware (i.e. a write of '1' to the GBLRST_CTL.TRIG_GBL bit).
9	0x0 RW/1C/V	**ME Firmware Watchdog Timer (ME_WDT):** This bit is set to '1' by hardware when a global reset is triggered by the second expiration of the ME firmware watchdog timer.
8	0x0 RW/1C/V	**PMC Firmware Watchdog Timer (PMC_WDT):** This bit is set to '1' by hardware when a global reset is triggered by the second expiration of the PMC firmware watchdog timer.

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1C/V	**LTRESET# With Policy 1 (LTRST_POL1):** This bit is set to '1' by hardware when a global reset is triggered by an LTRESET# assertion with LT_E2STS.LT_RESET_POLICY = 1.
6	0x0 RW/1C/V	**ME-Initiated Global Reset (ME_GBL):** This bit is set to '1' by hardware when a global reset is triggered by an ME FW write of 1's to both GENCTL."ME-Partition Reset" and GENCTL."ME-Initiated Host Reset With Power Cycle" in the same write cycle (this is ME FW's method of requesting a global reset).
5	0x0 RW/1C/V	**CPU Thermal Trip (CPU_TRIP):** This bit is set to '1' by hardware when a global reset is triggered by a CPU thermal trip event (i.e. an assertion of the THRMTRIP# pin).
4	0x0 RW/1C/V	**ME-Initiated Power Button Override (ME_PBO):** This bit is set to '1' by hardware when a global reset is triggered by an ME FW write of '1' to GENCTL."ME-Initiated Power Button Override."
3	0x0 RW/1C/V	**ICH Catastrophic Temperature Event (ICH_CAT_TMP):** This bit is set to '1' by hardware when a global reset is triggered by a catastrophic temperature event from the ICH internal thermal sensor.
2	0x0 RW/1C/V	**PMC SUS RAM Uncorrectable Error (PMC_UNC_ERR):** This bit is set to '1' by hardware when a global reset is triggered due to an uncorrectable parity error on a data read from one of the PMC SUS well register files.
1	0x0 RW/1C/V	**Power Button Override (PB_OVR):** This bit is set to '1' by hardware when a global reset is triggered by a power button override (i.e. an assertion of the PMU_PWRBTN_N pin for 5.1 seconds).
0	0x0 RO	**Reserved (RSVD_0):** Reserved.

58.3.14 Global Reset Causes (GBLRST_CAUSE1)—Offset 128h

This register logs causes of host partition resets.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 128h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved (RSVD_31_6):** Reserved.
5	0x0 RW/1C/V	**ME Set Power Button Status (ME_SET_PBO_STS):** If this bit is set, the cause of the previous global reset was ME FW setting the power button override status.
4	0x0 RO	**Reserved (RSVD_4):** Reserved.
3	0x0 RW/1C/V	**Host SMBus Message (HSMB_MSG):** If this bit is set, the cause of the previous global reset was a global reset request received over the host SMBus interface.
2	0x0 RW/1C/V	**Host Partition Reset Promotion (HOST_RST_PROM):** If this bit is set, the cause of the previous global reset was a host partition reset that was promoted to a global reset either due to ME or host policy.
1	0x0 RW/1C/V	**Sx Entry Timeout (SX_ENTRY_TIMEOUT):** If this bit is set, the cause of the previous global reset was an expiration of the timer that runs during Sx entry.
0	0x0 RW/1C/V	**Host Partition Reset Timeout (HOST_RESET_TIMEOUT):** If this bit is set, the cause of the previous global reset was an expiration of the timer that runs during host partition resets.

58.3.15 Host Partition Reset Causes (HPR_CAUSE0)—Offset 12Ch

This register logs causes of host partition resets.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 12Ch

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Reserved (RSVD_31_19):** Reserved.
18	0x0 RO/V	**IE Initiated Host Reset With Power Down (IE_HRPD):** IE initiated host reset with power down
17	0x0 RO/V	**IE Initiated Host Reset With Power Cycle (IE_HRPC):** IE initiated host reset with power cycle.
16	0x0 RO/V	**IE Initiated Host Rest Without Power Cycle (IE_HR):** IE initiated host reset without power cycle.
15	0x0 RO	**Reserved (RSVD_15):** Reserved.
14	0x0 RO/V	**LT Sleep Error (LT_SLPERR):** Sleep entry attempted while LT secrets were present in memory.
13	0x0 RO/V	**Host SMBUS Host Reset With Power Cycle (HSMB_HRPC):** SMBus initiated host partition reset with power cycle.
12	0x0 RO/V	**Host SMBUS Host Reset Without Power Cycle (HSMB_HR):** SMBus initiated host partition reset without power cycle.
11	0x0 RO	**Reserved (RSVD_11_11):** Reserved.
10	0x0 RO/V	**ME-Initiated Host Reset With Power Down (MI_HRPD):** Intel® ME initiated host reset with power down.
9	0x0 RO/V	**ME-Initiated Host Reset With Power Cycle (MI_HRPC):** Intel® ME initiated host reset with power cycle.
8	0x0 RO/V	**ME-Initiated Host Reset Without Power Cycle (MI_HR):** Intel® ME initiated host reset without power cycle.
7	0x0 RO	**Reserved (RSVD_7):** Reserved.
6	0x0 RO/V	**Host TCO Watchdog Timer Second Expiration (TCO_WDT):** Host TCO watchdog timer reached zero for the second time.
5:4	0x0 RO	**Reserved (RSVD_5_4):** Reserved.
3	0x0 RO/V	**LTRESET (LTRST):** LTRESET message received and the LT.RESET.POLICY bit = '0'.
2	0x0 RO/V	
1	0x0 RO/V	**Write to CF9 (CF9_ES):** This bit will be set when Host software writes a value of 6h or Eh to the CF9h register in Host I/O Space. ***Note:*** The "shutdown" special cycle from the CPU will also set this bit.
0	0x0 RO	**Reserved (RSVD_0):** Reserved.

58.3.16 modPHY Power Management Configuration Reg 1 (MODPHY_PM_CFG1)—Offset 200h

This register contains misc. fields used to configure the SoC power management behavior with respect to the modPHY.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 200h

Default: 0000FFFFh

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW	**ModPHY Lane S0 SUS Well Power Gating Policy [15:0] (MLS0SWPGP):** This is a bit per lane that controls SUS Well Power Gating for a ModPHY lane to be used for S0 and S0ix use models as described above in HAS. • Bit 0: Corresponds to ModPHY Lane 0 • Bit 1: Corresponds to ModPHY Lane 1 • Bit 2: Corresponds to ModPHY Lane 2 : : Bit 15: Corresponds to ModPHY Lane 15 For each lane: • 0: Lane power gating not permitted in S0. • 1: Lane power gating is permitted in S0. Note that strap information/PCIe Lane reversal information will be factored by BIOS when programming these bits in the configuration registers. Note that it is illegal SW programming to have a bit location to be 1 in this field and the corresponding bit position to be 0 in MLSXSWPGP
15:0	0xffff RW	• **ModPHY Lane Sx SUS Well Power Gating Policy [15:0] (MLSXSWPGP):** This is a bit per lane that controls SUS Well Power Gating for a ModPHY lane when system is in Sx. • Bit 0: Corresponds to ModPHY Lane 0 • Bit 1: Corresponds to ModPHY Lane 1 • Bit 2: Corresponds to ModPHY Lane 2 : : Bit 15: Corresponds to ModPHY Lane 15 For each lane: • 0: Lane power gating not permitted in Sx. • 1: Lane power gating is permitted in Sx. Note that strap information/PCIe Lane reversal information will be factored by BIOS when programming these bits in the configuration registers. For ease of PMC implementation, this field will be used to manage Sx policies even in S0. In other words, the earlier restriction that BIOS does not have to program this field if MLSPDDGE is 1 does not apply any more. BIOS shall set this field appropriately for all cases.

58.3.17 modPHY Power Management Configuration Reg 2 (MODPHY_PM_CFG2)—Offset 204h

This register contains misc. fields used to configure the SoC power management behavior with respect to the modPHY.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 204h

Default: 05000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Gen2PLL Request Control (G2PLLREQCTL):** This bit controls how PMC should treat Gen2PLL power request for ModPHY power gating flows. • 0 - PMC should treat Gen2PLL request as non restore power request • 1 - PMC should treat Gen2PLL request as restore power request
30	0x0 RW	**ModPHY Lane SUS Power Domain Dynamic Gating Enable (MLSPDDGE):** When this bit is set to 1, ModPHY Lane SUS Well Dynamic Gating is enabled. ModPHY lane SPD is managed using the variables defined by the PMC. When this bit is 0, ModPHY Lane SUS Well Gating can still be done at a more coarse level using MLSXSWPGP and MLS0SWPGP fields.
29	0x0 RW	**Enable ModPHY FET Control (EMFC):** This bit enables PMC dynamic control of ModPHY external FET. When this bit is 0 and MLSPDDGE is 1, PMC goes through all of the ModPHY power gating flows except that the external FET is not turned off. This bit is being provided primarily to prevent External FET gating during EXI debug
28:24	0x5 RW/L	**External FET Ramp Time (EFRT):** This field defines the ramp time of ModPHY FET. • 00000b: 00us • 00001b: 20us • 00010b: 40us • ... • 00101b: 100us • ... • 11111b: 620us This bit is locked while PM_SYNC_MISC_CFG.PM_SYNC_LOCK = '1'
23:20	0x0 RO	**Reserved (RSVD_23_20):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
19:0	0x0 RW	**ASL Over-rides [19:0] (ASLOR):** This field provides ASL code to take over SPD power gating control. If ASL code sets a bit corresponding to a controller, it implies that PMC shall ignore any other inputs from that controller and assume that the controller is ready for SPD power gating. 0 in a bit position: Use HW interfaces for the controller to manage SPD gating/wake-up. 1 in a bit position: Ignore HW interfaces for the controller, rely only on MSPDRTReq field thats managed by ASL code. • Bit 0: Corresponds to PCIe Controller A, Function 0 • Bit 1: Corresponds to PCIe Controller A, Function 1 • Bit 2: Corresponds to PCIe Controller A, Function 2 • Bit 3: Corresponds to PCIe Controller A, Function 3 • Bit 4: Corresponds to PCIe Controller B, Function 0 • Bit 5: Corresponds to PCIe Controller B, Function 1 • Bit 6: Corresponds to PCIe Controller B, Function 2 • Bit 7: Corresponds to PCIe Controller B, Function 3 • Bit 8: Corresponds to PCIe Controller C, Function 0 • Bit 9: Corresponds to PCIe Controller C, Function 1 • Bit 10: Corresponds to PCIe Controller C, Function 2 • Bit 11: Corresponds to PCIe Controller C, Function 3 • Bit 12: Corresponds to SATA Controller • Bit 13: Corresponds to Gbe Controller • Bit 14: Corresponds to xHCI Controller • Bit 15: Corresponds to xDCI Controller • Bit 16: Corresponds to UFS Controller • Bits[19:17]: Reserved This field is going to be used in conjunction with MSPDRTReq and MSPDRTRAck fields above. If ASL code intends to over-ride HW decisions, it will set the corresponding bit for a controller/function to 1 in ASLOR and use MSPDRTReq bits to power-up/power-down SPD.

58.3.18 modPHY Power Management Configuration Reg 3 (MODPHY_PM_CFG3)—Offset 208h

This register contains misc. fields used to configure the SoC power management behavior with respect to the modPHY.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 208h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**Reserved (RSVD_31_20):** Reserved.
19:0	0x0 RW	**Controller SPD RTD3 Request [19:0] (MSPDRTREQ):** This field represents ASL code trigger request for ModPHY SPD gating. If this bit is set (to 1) for a controller, it implies that ASL code provides consent for SPD to be gated for the corresponding controllers lanes. Note that this bit could also be more statically used by BIOS to set this to 1 for a controller where SPD will only be managed through other interfaces implying ASL code does not exist for a controller. This is not a POR mode of operation if a function is enabled ASL code will exist for all controllers that are enabled. However, the controllers that are not enabled (Function Disabled), this field will be statically set by BIOS to activate ASL component in SPD gating equations. • Bit 0: Corresponds to PCIe Controller A, Function 0 • Bit 1: Corresponds to PCIe Controller A, Function 1 • Bit 2: Corresponds to PCIe Controller A, Function 2 • Bit 3: Corresponds to PCIe Controller A, Function 3 • Bit 4: Corresponds to PCIe Controller B, Function 0 • Bit 5: Corresponds to PCIe Controller B, Function 1 • Bit 6: Corresponds to PCIe Controller B, Function 2 • Bit 7: Corresponds to PCIe Controller B, Function 3 • Bit 8: Corresponds to PCIe Controller C, Function 0 • Bit 9: Corresponds to PCIe Controller C, Function 1 • Bit 10: Corresponds to PCIe Controller C, Function 2 • Bit 11: Corresponds to PCIe Controller C, Function 3 • Bit 12: Corresponds to SATA Controller • Bit 13: Corresponds to Gbe Controller • Bit 14: Corresponds to xHCI Controller • Bit 15: Corresponds to xDCI Controller • Bit 16: Corresponds to UFS Controller • Bits[19:17]: Reserved

58.3.19 modPHY Power Management Configuration Reg 4 (MODPHY_PM_CFG4)—Offset 20Ch

This register contains misc. fields used to configure the SoC power management behavior with respect to the modPHY.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 20Ch

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RO	**Reserved (RSVD_31_20):** Reserved.
19:0	0x0 RO/V	**Controller SPD RTD3 Request Acknowledge [19:0] (MSPDRTRACK):** This field represents the acknowledge for ASL code trigger request for ModPHY SPD gating. PMC sets a bit in this field to 1 to acknowledge that it has registered the corresponding MSPDRTREQ. Note that the action of setting this bit to 1 is immediate no other gating conditions are involved in this. Actual SPD shutdown may happen later once other power gating conditions have been satisfied as well. PMC clears a bit to 0 in this field once the corresponding MSPTDRTREQ is cleared by the ASL code and SPD state has been fully restored. • Bit 0: Corresponds to PCIe Controller A, Function 0 • Bit 1: Corresponds to PCIe Controller A, Function 1 • Bit 2: Corresponds to PCIe Controller A, Function 2 • Bit 3: Corresponds to PCIe Controller A, Function 3 • Bit 4: Corresponds to PCIe Controller B, Function 0 • Bit 5: Corresponds to PCIe Controller B, Function 1 • Bit 6: Corresponds to PCIe Controller B, Function 2 • Bit 7: Corresponds to PCIe Controller B, Function 3 • Bit 8: Corresponds to PCIe Controller C, Function 0 • Bit 9: Corresponds to PCIe Controller C, Function 1 • Bit 10: Corresponds to PCIe Controller C, Function 2 • Bit 11: Corresponds to PCIe Controller C, Function 3 • Bit 12: Corresponds to SATA Controller • Bit 13: Corresponds to Gbe Controller • Bit 14: Corresponds to xHCI Controller • Bit 15: Corresponds to xDCI Controller • Bit 16: Corresponds to UFS Controller • Bits[19:17]: Reserved

58.3.20 IE_STS (IE_STS)—Offset 3F0h

This register contains misc fields used to record events pertaining to the Innovation Engine (IE) status. This is shadowed from PMC XRAM IEPMMISC register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 3F0h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO/V	**Shadowed IEPMMISC[31:24] (SHAD_IEPMMISC_31_24):** Shadowed from PMC_XRAM_IEPMMISC
23	0x0 RO/V	**Shadowed IEPMMISC[23] (SHAD_IEPMMISC):** Shadowed IEPMMISC[23]
22	0x0 RO/V	**Shadowed Bios Authentication Result (SHAD_IE_BIOS_AUTH):** Written by IE OEM FW after it attempts to authenticate BIOS image. • 0 = BIOS authentication failed • 1 = BIOS authentication succeeded ***Note:*** This field is made available to OEM FW for its use.
21	0x0 RO/V	**Shadowed FW Authentication Result (SHAD_IE_FW_AUTH):** • 0 = IE FW authentication failed • 1 = IE FW authentication succeeded
20	0x0 RO/V	**Shadowed IE Hash Valid Fuse (SHAD_IE_HASHVALID_FUSE):** Written by IE ROM. Shadows the IE_HASHVALID_FUSE (OEM IFP) pulled by IE. • 0 = use debug Hash • 1 = use OEM Hash FYI to ME FW and BIOS.
19	0x0 RO/V	**Shadowed IE Locked (SHAD_IE_LOCKED):** Written by IE ROM. Shadows the IE_EOM_FUSE (OEM IFP) pulled by IE. • 0 = OEM in manufacturing (default) • 1 = OEM End-of-Manufacturing FYI to ME FW and BIOS.
18	0x0 RO/V	**Shadowed IE Verified Policy Fuse (SHAD_IE_VBPOLICY_FUSE):** Shadowed from PCI MMR_IE_STS
17	0x0 RO/V	**Shadowed IE Disable Strap (SHAD_IE_DISABLE_STRAP):** Written by IE ROM. Shadows the IE_DISABLE_STRAP (soft strap) pulled by IE. FYI to ME FW and BIOS.
16	0x0 RO/V	**Shadowed IE Policy Done (SHAD_IE_POLICY_DONE):** Set by IE ROM after it has set IE_DIS_HOST_WAK_SUS. This bit is a handshake from IE ROM to PMC FW. • 1) PMC FW should treat IE_POLICY_DONE (IE) similar to PATCH_DONE (Intel® ME): both are used as handshakes; the reset sequence will pause until set. Also both conditions have (chicken-out) PMC timers that, upon expiration, will cause reset to proceed regardless of the handshake. • 2) PMC FW should use IE_POLICY_DONE handshake to comprehend IE_DIS_HOST_WAK_SUS, even if S0_COMMIT was already asserted. IE ROM must set IE_DIS_HOST_WAK_SUS (to prevent boot if VB fails). ***Note:*** See description of PPS.S0_COMMIT and GENCTL.DIS_HOST_WAK_SUS for more details.
15:9	0x0 RO/V	**Shadowed IE_STS[15:9] (SHAD_IE_STS_15_9):** Shadowed from PMC XRAM IEPMMISC
8	0x0 RO/V	**Shadowed IE_CIOFF_STS (SHAD_IE_CIOFF_STS):** Shadows IE_CIOFF_STS bit in XRAM space, which is controlled by PMC FW and set when CI0-)CIoff is completed. BIOS shall poll this bit, after requesting CI0-)Cioff (indicated by IE_CIOFF_REQ). Once set BIOS should re-enumerate to remove IE devices and handoff to O/S. O/S-discovered devices should be persistent.
7:2	0x0 RO/V	**Shadowed IE_STS[7:2] (SHAD_IE_STS_7_2):** Shadowed from PMC XRAM IEPMMISC

Bit Range	Default & Access	Field Name (ID): Description
1:0	0x0 RO/V	**Shadowed IE_STS[1:0] (SHAD_IE_STS_1_0):** Shadowed from PMC XRAM IEPMMISC

58.3.21 ME_STS (ME_STS)—Offset 3F4h

This register contains misc. fields used to record events pertaining to the Intel® Management Engine status. This is shadowed from PMC XRAM MEPMMISC register.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 3F4h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD_31_16):** Reserved.
15:9	0x0 RO/V	**Shadowed ME_STS[15:9] (SHAD_ME_STS_15_9):** Shadowed from PMC_XRAM MEPMMISC[15:9]
8	0x0 RO/V	**Shadowed ME_CMOFF_STS (SHAD_ME_CMOFF_STS):** Shadows ME_CMOFF_STS in XRAM space, which is controlled by PMC FW and set when CM0-)CMoff is completed. BIOS shall poll this bit, after requesting CM0-)CMoff (indicated by IE_CMOFF_REQ). Once set BIOS should re-enumerate to remove ME devices and handoff to O/S. Why? O/S-discovered devices should be persistent. Shadowed from PMC XRAM MEPMMISC[8]
7:0	0x0 RO/V	**Shadowed ME_STS[7:0] (SHAD_ME_STS_7_0):** Shadowed from PMC_XRAM MEPMMISC[7:0]

58.3.22 Static PG Related Function Disable Register 1 (ST_PG_FDIS_PMC_1)—Offset 620h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [PWRMBASE] + 620h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Static Function Disable Lock (ST_FDIS_LK):** Lock control for all ST_PG_FDIS_PMC_* and NST_PG_FDIS_* registers (also self-locks when written to 1).
30:13	0x0 RO	**Reserved (RSVD_30_13):** Reserved.
12	0x0 RW/L	**EXI Function Disable (PMC Version) (EXI_FDIS_PMC):** BIOS is required to set this bit when EXI function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
11	0x0 RW/L	**NPK Function Disable (PMC Version) (NPK_FDIS_PMC):** BIOS is required to set this bit when NPK function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
10	0x0 RW/L	**IE Function Disable (PMC Version) (IE_FDIS_PMC):** BIOS is required to set this bit when IE function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
9	0x0 RW/L	**ME Function Disable (PMC Version) (ME_FDIS_PMC):** BIOS is required to set this bit when ME function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
8	0x0 RW/L	**XHCI Function Disable (PMC Version) (XHCI_FDIS_PMC):** BIOS is required to set this bit when XHCI function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
7	0x0 RW/L	**eMMC (SCC) Function Disable (PMC Version) (EMMC_FDIS_PMC):** BIOS is required to set this bit when eMMC function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
6	0x0 RW/L	**nCPM Function Disable (PMC Version) (NCPM_FDIS_PMC):** BIOS is required to set this bit when Intel® QuickAssist Technology function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
5	0x0 RW/L	**PCIE1 Function Disable (PMC Version) (PCIE1_FDIS_PMC):** BIOS is required to set this bit when PCIE Ctrl 1 function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
4	0x0 RW/L	**PCIE0 Function Disable (PMC Version) (PCIE0_FDIS_PMC):** BIOS is required to set this bit when PCIE Ctrl 0 function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
3	0x0 RW/L	**SATA1 Function Disable (PMC Version) (SATA1_FDIS_PMC):** BIOS is required to set this bit when SATA Ctrl 1 function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
2	0x0 RW/L	**SATA0 Function Disable (PMC Version) (SATA0_FDIS_PMC):** BIOS is required to set this bit when SATA Ctrl 0 function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
1	0x0 RW/L	**GBE1 Function Disable (PMC Version) (GBE1_FDIS_PMC):** BIOS is required to set this bit when GBE Ctrl 1 function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
0	0x0 RW/L	**GBE0 Function Disable (PMC Version) (GBE0_FDIS_PMC):** BIOS is required to set this bit when GBE Ctrl 0 function is configured to be function disabled. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.

58.3.23 Non-Static PG Related Function Disable Register 1 (NST_PG_FDIS_1)—Offset 628h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 628h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3:0	0x0 RW	**LAN port disable control bits (LAN_PORT_DISABLE):** Host disable of the LAN ports, LAN_PORT_DISABLE[3:0] = Odem1[1:0] + Odem0[1:0]

58.3.24 Non-Static PG Fuse Disable Read 1 Register (N_STPG_FUSE_SS_DIS_RD_1)—Offset 640h

This register contains fuse disable based information - which is not used for static power gating (this information is provided only for host/BIOS read access).

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 640h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:4	0x0 RO	**Reserved (RSVD_31_4):** Reserved.
3:0	0x0 RO/V	**LAN port Disable status (LAN_PORT_DISABLE_STATUS):** Result of all fuses and straps and control bits of the LAN port disable, LAN_PORT_DISABLE_STATUS[3:0] = Odem1[1:0] + Odem0[1:0]

58.3.25 Static PG Fuse and Soft Strap Disable Read Register 2 (STPG_FUSE_SS_DIS_RD_2)—Offset 644h

This register contains fuse and soft strap disable based information - all of which is used for static power-gating (for example, if a bit is set in this register for a particular IP, PMC keeps that IP in a power-gated state - except as noted below.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [PWRMBASE] + 644h

Default: 00000000h

PWRMBASE Type: PCI Configuration Register (Size: 32 bits)
PWRMBASE Reference: [B:0, D:31, F:2] + 48h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD_31_16):** Reserved.
15	0x0 RO/V	**Intel® Management Engine (Intel® ME) Fuse or Soft Strap Disable (ME_FUSE_SS_DIS):** RO bit indicating if the Intel® Management Engine function is disabled through fuse/soft strap.
14	0x0 RO/V	**Innovation Engine Fuse or Soft Strap Disable (IE_FUSE_SS_DIS):** RO bit indicating if Innovation Engine function is disabled through fuse/soft strap.
13	0x0 RO/V	**USB2 Fuse or Soft Strap Disable (USB2_FUSE_SS_DIS):** RO bit indicating if USB2 function is disabled through fuse/soft strap.
12	0x0 RO/V	**LPC Fuse or Soft Strap Disable (LPC_FUSE_SS_DIS):** RO bit indicating if LPC function is disabled through fuse/soft strap.
11	0x0 RO/V	**ESPISPI Fuse or Soft Strap Disable (ESPISPI_FUSE_SS_DIS):** RO bit indicating if ESPISPI function is disabled through fuse/soft strap.
10	0x0 RO/V	**NPK Fuse or Soft Strap Disable (NPK_FUSE_SS_DIS):** RO bit indicating if NPK function is disabled through fuse/soft strap.
9	0x0 RO	**Reserved (RSVD_9):** Reserved.
8	0x0 RO/V	**eMMC Fuse or Soft Strap Disable (EMMC_FUSE_SS_DIS):** RO bit indicating if eMMC (SCC) function is disabled through fuse/soft strap.
7	0x0 RO/V	**XHCI Fuse or Soft Strap Disable (XHCI_FUSE_SS_DIS):** RO bit indicating if XHCI function is disabled through fuse/soft strap.
6	0x0 RO/V	**nCPM Fuse or Soft Strap Disable (NCPM_FUSE_SS_DIS):** RO bit indicating if Intel® QuickAssist Technology function is disabled through fuse/soft strap.
5	0x0 RO/V	**PCIE Ctrl 1 Fuse or Soft Strap Disable (PCIE1_FUSE_SS_DIS):** RO bit indicating if PCIE Ctrl 1 function is disabled through fuse or Soft strap.
4	0x0 RO/V	**PCIE Ctrl 0 Fuse or Soft Strap Disable (PCIE0_FUSE_SS_DIS):** RO bit indicating if PCIE Ctrl 0 function is disabled through fuse or Soft strap.
3	0x0 RO/V	**SATA Ctrl 1 Fuse or Soft Strap Disable (SATA1_FUSE_SS_DIS):** RO bit indicating if SATA Ctrl 1 function is disabled through fuse or Soft strap.
2	0x0 RO/V	**SATA Ctrl 0 Fuse or Soft Strap Disable (SATA0_FUSE_SS_DIS):** RO bit indicating if SATA Ctrl 0 function is disabled through fuse or Soft strap.
1	0x0 RO/V	**GBE Ctrl 1 Fuse or Soft Strap Disable (GBE1_FUSE_SS_DIS):** RO bit indicating if GBE Ctrl 1 function is disabled through fuse or Soft strap.
0	0x0 RO/V	**GBE Ctrl 0 Fuse or Soft Strap Disable (GBE0_FUSE_SS_DIS):** RO bit indicating if GBE Ctrl 0 function is disabled through fuse or Soft strap.

58.4 Registers in I/O Space—ABASE

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) ABASE described in Section 58.2.2, "ACPI Base Address (ABASE)—Offset 40h" on page 2689.

58.4.1 Power Management 1 Enables and Status (PM1_EN_STS)—Offset 0h

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 0h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD_31):** Reserved.
30	0x0 RW	**PCI Express Wake Disable (PCIEXP_WAKE_DIS):** This bit disables the inputs to the PCIEXP_WAKE_STS bit in the PM1 Status register from waking the system. Modification of this bit has no impact on the value of the PCIEXP_WAKE_STS bit.
29:27	0x0 RO	**Reserved (RSVD_29_27):** Reserved.
26	0x0 RW/V	**RTC Alarm Enable (RTC_EN):** This is the RTC alarm enable bit. It works in conjunction with the SCI_EN bit. When RTC_STS is set, one of the following happens: • When RTC_EN=0: No SMI# or SCI. If system was in S1-S5, no wake event occurs. • When RTC_EN=1 and SCI_EN = 1: SCI. If system was in S1-S5, then a wake event occurs before the SCI. • When RTC_EN=1 and SCI_EN = 0: SMI#. If system was in S1-S5, then a wake event occurs before the SMI#. This register bit is circuitry in the SoC RTC power well in order to allow an RTC event to wake after a power failure. It is reset only when the active-low SRTCRST_N input signal pin is asserted.
25	0x0 RO	**Reserved (RSVD_25):** Reserved.
24	0x0 RW/V	**Power Button Enable (PWRBTN_EN):** This bit is the power button enable. It works in conjunction with the SCI_EN bit. When PWRBTN_STS is set, one of the following happens: • When PWRBTN_EN=0: No SMI# or SCI. • When PWRBTN_EN=1 and SCI_EN = 1: SCI. • When PWRBTN_EN=1 and SCI_EN = 0: SMI#. ***Note:*** PWRBTN_EN has no effect on the PWRBTN_STS bit being set by the assertion of the power button. The Power Button is always enabled as a Wake event.
23:22	0x0 RO	**Reserved (RSVD_23_22):** Reserved.
21	0x0 RW	**Global Enable (GBL_EN):** The global enable bit. When both the GBL_EN and the GBL_STS are set, the SoC generates an SCI.
20:17	0x0 RO	**Reserved (RSVD_20_17):** Reserved.
16	0x0 RW	**Timer Overflow Interrupt Enable (TMROF_EN):** This is the timer overflow interrupt enable bit. It works in conjunction with the SCI_EN bit. When TMROF_STS is set, one of the following happens: • When TMROF_EN=0: No SMI# or SCI. • When TMROF_EN=1 and SCI_EN = 1: SCI. When TMROF_EN=1 and SCI_EN = 0: SMI#.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C/V	**Wake Status (WAK_STS):** This bit is set when the system is in one of the Sleep states (via the SLP_EN bit) and an enabled SoC Wake event occurs. Upon setting this bit, the SoC will transition the system to the ON state. This bit can only be set by hardware and can only be cleared by writing a one to this bit position. This bit is not affected by hard resets caused by a CF9 write, but is reset by the SoC-internal pri_pwrgood_rst_b signal.
14	0x0 RW/1C/V	**PCI Express Wake Status (PCIEXP_WAKE_STS):** This bit is set by hardware to indicate that the system woke due to a PCI Express wakeup event. This event can be caused by the PCI Express WAKE# pin being active, or one or more of the PCI Express ports being in beacon state, or receipt of a PCI Express PME message at root port.
13:12	0x0 RO	**Reserved (RSVD_13_12):** Reserved.
11	0x0 RW/1C/V	**Power Button Override (PWRBTNOR_STS):** This bit is set when any of these occur: • A Power Button Override Event occurs (i.e., the power button is pressed for at least four consecutive seconds) • The corresponding bit is received in the SMBus slave message • The Intel® ME-Initiated "Power Button Override" bit is set • The Intel® ME-Initiated "Host Reset with Power Down" is set • An internal thermal sensor catastrophic condition occurs These events cause an unconditional transition to the S5 state.
10	0x0 RW/1C/V	**RTC Status (RTC_STS):** This bit is set when the RTC generates an alarm (assertion of the IRQ8# signal), and is not affected by any other enable bit. See the RTC_EN bit in this register for the effect when RTC_STS goes active.
9	0x0 RO	**Reserved (RSVD_9):** Reserved.
8	0x0 RW/1C/V	**Power Button Status (PWRBTN_STS):** This bit is set when the PMU_PWRBTN_N input signal pin is asserted (low), independent of any other enable bit. See the PWRBTN_EN bit in this register for the effect when PWRBTN_STS goes active. PWRBTN_STS is always a wake event. This bit is only set by hardware and can be cleared by software writing a one to this bit position. This bit is not affected by hard resets caused by a CF9 write, but is reset by the SoC internal pwrgood_rst_b.
7:6	0x0 RO	**Reserved (RSVD_7_6):** Reserved.
5	0x0 RW/1C/V	**GBL Status (GBL_STS):** This bit is set when an SCI is generated due to the BIOS wanting the attention of the SCI handler. BIOS has a corresponding bit, BIOS_RLS, which will cause an SCI and set this bit. The SCI handler should then clear this bit by writing a 1 to it. This bit will not cause wake events or SMI#. This bit is not affected by SCI_EN.
4	0x0 RW/1C/V	**Bus Master Status (BM_STS):** This bit is set to 1 by the SoC when a SoC-visible bus master requests access to memory or the BM_BUSY# signal is active. This bit is cleared by the CPU writing a 1 to this bit position. This bit will not cause a wake event, SCI, or SMI.
3:1	0x0 RO	**Reserved (RSVD_3_1):** Reserved.
0	0x0 RW/1C/V	**Timer Overflow Status (TMROF_STS):** This is the timer overflow status bit.

58.4.2 Power Management 1 Control —Offset 4h

Usage: ACPI or Legacy. Not lockable. Bits 0-9, 13-31 = Primary Power Well. Bits 10-12 = RTC Power Well.

Type: I/O Register (Size: 32 bits)

BAR and Offset: [ABASE] + 4h

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved (RSVD_31_14):** Reserved.
13	0x0 WO	**Sleep Enable (SLP_EN):** This is a write-only bit and reads to it always return a zero. Setting this bit causes the system to sequence into the Sleep state defined by the SLP_TYP field.
12:10	0x0 RW	**Sleep Type (SLP_TYP):** This 3-bit field defines the type of Sleep the system should enter when the SLP_EN bit is set to 1. These bits are in the RTC power well and are cleared when the SoC input signal pin SRTCRST_N is active. • 000: Mode = ON, Typical Mapping = S0 • 001: Reserved • 010: Reserved • 011: Reserved • 100: Reserved • 101: Reserved • 110: Mode = Suspend-To-Disk, Typical Mapping = S4 • 111: Mode = Soft Off, Typical Mapping = S5
9:3	0x0 RO	**Reserved (RSVD_9_3):** Reserved.
2	0x0 WO	**GBL_RLS:** The Global Release bit is used by the ACPI software which writes a '1' to raise an event to the BIOS software. This bit always reads as 0.
1	0x0 RW	**BM_RLD:** This bit is treated as a scratchpad bit.
0	0x0 RW	**SCI Enable (SCI_EN):** Selects the SCI interrupt or the SMI# for various events. • 0 = These events will generate an SMI#. • 1 = These events will generate an SCI.

58.4.3 Power Management 1 Timer (PM1_TMR)—Offset 8h

Usage: ACPI. Not lockable. Primary Power Well.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 8h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD_31_24):** Reserved. Will always read 0.
23:0	0x0 RO/V	**Timer Value (TMR_VAL):** This read-only field returns the running count of the PM timer. This counter runs off a 3.579545 MHz clock (derived from 14.31818 MHz divided by 4). It is reset (to 0) during a PCI reset, and then continues counting as long as the system is in the S0 state. Anytime bit 22 of the timer goes HIGH to LOW (bits referenced from 0 to 23), the TMROF_STS bit is set. The High-to-Low transition will occur every 2.3435 seconds. Writes to this register have no effect.

58.4.4 SMI Control and Enable (SMI_EN)—Offset 30h

Usage: ACPI or Legacy. Not lockable. Primary Power Well.
This register is symmetrical to the SMI Status Register.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 30h

Default: 00000002h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**XHCI SMI Enable (XHCI_SMI_EN):** Software sets this bit to enable XHCI SMI events.
30	0x0 RW	**ME SMI Enable (ME_SMI_EN):** Software sets this bit to enable Intel® ME SMI# events.
29	0x0 RW	**LPSS SMI Enable (LPSS_SMI_EN):** Software sets this bit to enable LPSS SMII events.
28	0x0 RW/L	**Reserved:** Reserved.
27	0x0 RW/1S	**GPIO Unlock SMI Enable (GPIO_UNLOCK_SMI_EN):** Setting this bit will cause the SoC to generate an SMI# when the GPIO_UNLOCK_SMI_STS bit is set in the SMI_STS register. Once written to '1', this bit can only be cleared by host_prim_rst_b.
26	0x0 RO	**Reserved (RSVD_26):** Reserved.
25	0x0 RW	**SCC SMI Enable (SCC_SMI_EN):** Software sets this bit to enable SCC (eMMC) SMI events
24	0x0 RO	**Reserved (RSVD_24):** Reserved.
23	0x0 RW	**IE SMI Enable (IE_SMI_EN):** Software sets this bit to enable Innovation Engine (IE) SMI# events.
22:19	0x0 RO	**Reserved (Rsvd_22_19):** Reserved.
18	0x0 RW	**IEH (RAS Error Collector) SMI Enable (IEH_SMI_EN):** Software sets this bit to enable Internal Error Handler (IEH) SMI# events.
17	0x0 RW	**Legacy USB 2 Enable (LEGACY_USB2_EN):** Enables legacy USB 2.0 logic to cause SMI#.
16:15	0x0 RO	**Reserved (RSVD_16_15):** Reserved.
14	0x0 RW	**Periodic Enable (PERIODIC_EN):** Setting this bit will cause the SoC to generate an SMI# when the PERIODIC_STS bit is set in the SMI_STS register.
13	0x0 RW/L	**TCO Enable (TCO_EN):** • 0 = Disables TCO logic generating an SMI# • 1 = Enables the TCO logic to generate SMI# If the NMI2SMI_EN bit is set, then SMI's that are caused by NMI's (i.e. rerouted) will not be gated by the TCO_EN bit. Even if the TCO_EN bit is 0, the NMI's will still be routed to cause the SMI#. This bit can not be written once the TCO_LOCK bit (at offset 08h of TCO I/O Space) is set. This prevents unauthorized software from disabling the generation of TCO-based SMI's
12	0x0 RO	**Reserved (RSVD_12):** Reserved.
11	0x0 RW	**MCSMI Enable (MCSMI_EN):** Software sets this bit to 1 to enables the SoC to trap access to the microcontroller range (62h or 66h).

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RO	**Reserved (RSVD_10_8):** Reserved.
7	0x0 WO	**BIOS_RLS:** Enables the generation of an SCI interrupt for ACPI software when a '1' is written to this bit position by BIOS software. This bit always reads a zero. GBL_STS being set will cause an SCI, even if the SCI_EN bit is not set. Software must take great care not to set the BIOS_RLS bit (which causes GBL_STS to be set) if the SCI handler is not in place.
6	0x0 RW	**Software SMI Timer Enable (SWSMI_TMR_EN):** Software sets this bit to a '1' to start the Software SMI# Timer. When the timer expires (depending on the SWSMI_RATE_SEL bits), it will generate an SMI# and set the SWSMI_TMR_STS bit. The SWSMI_TMR_EN bit will remain at 1 until software sets it back to 0. Clearing the SWSMI_TMR_EN bit before the timer expires will reset the timer and the SMI# will not be generated. The default for this bit is 0.
5	0x0 RW	**APMC Enable (APMC_EN):** If set, this enables writes to the APM_CNT register to cause an SMI#
4	0x0 RW	**SMI On Sleep Enable (SMI_ON_SLP_EN):** If this bit is set, the SoC will generate an SMI# when a write access attempts to set the SLP_EN bit (in the PM1_CNT register). Furthermore, the SoC will not put the system to a sleep state. It is expected that the SMI# handler will turn off the SMI_ON_SLP_EN bit before actually setting the SLP_EN bit.
3	0x0 RW	**Legacy USB Enable (LEGACY_USB_EN):** Enables legacy USB circuit to cause SMI#.
2	0x0 RW	**BIOS Enable (BIOS_EN):** Enables the generation of SMI# when ACPI software writes a '1' to the GBL_RLS bit. ***Note:*** If the BIOS_STS bit, which gets set when software writes a 1 to GBL_RLS bit, is already a 1 at the time that BIOS_EN becomes 1, an SMI# will be generated when BIOS_EN gets set.
1	0x1 RW/1S/V	**End of SMI (EOS):** This bit controls the arbitration of the SMI signal to the processor. This bit must be set in order for the SoC to assert SMI# low to the processor after SMI# has been asserted previously.
0	0x0 RW/L	**Global SMI Enable (GBL_SMI_EN):** When set, this bit enables the generation of SMIs in the system upon any enabled SMI event. This bit is reset by a PCI reset event. If this bit is not set, no SMI# will be generated. When the SMI_LOCK bit is set, this bit cannot be changed.

58.4.5 SMI Status Register (SMI_STS)—Offset 34h

Usage: ACPI or Legacy. Not lockable. Primary Power Well.
If the corresponding _EN bit is set when the _STS bit is set, the SoC will cause an SMI# (except bits 8-10, which don't cause SMI#).

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 34h

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**XHCI SMI Status (XHCI_SMI_STS):** This bit will be set when any USB 3.0 (XHCI) Host Controller is requesting an SMI.
30	0x0 RO/V	**ME SMI Status (ME_SMI_STS):** This bit will be set when the Intel® ME is requesting an SMI#.
29	0x0 RW/1C/V	**LPSS SMI Status (LPSS_SMI_STS):** This bit gets set when LPSS agent is requesting SMI #. This bit is set by hardware and cleared by software writing a 1 to this bit position
28	0x0 RO/V	**Reserved:** Reserved.
27	0x0 RW/1C/V	**GPIO Unlock SMI Status (GPIO_UNLOCK_SMI_STS):** This bit will be set of the GPIO registers lock-down logic is requesting an SMI#. Writing a '1' to this bit position clears this bit to '0'.
26	0x0 RO/V	**SPI_SMI Status (SPI_SMI_STS):** This bit will be set when the SPI logic is requesting an SMI#. This bit is read only because the sticky status and enable bits associated with this function are located in the SPI registers.
25	0x0 RW/1C/V	**SCC SMI Status (SCC_SMI_STS):** This bit gets set when SCC agent is requesting SMI#. This bit is set by hardware and cleared by software writing a 1 to this bit position.
24	0x0 RO	**Reserved (RSVD_24):** Reserved.
23	0x0 RO/V	**IE SMI Status (IE_SMI_STS):** This bit will be set when the Innovation Engine (IE) is requesting an SMI#.
22	0x0 RO/V	**INTERNAL_TT Status (INTERNAL_TT_STS):** This bit will be set if the internal thermal throttle mechanism has changed state. This bit is read only because the sticky status and enable bit associated with this function is in the other unit.
21	0x0 RO/V	**Monitor Status (MONITOR_STS):** This bit will be set if the Trap/SMI logic has caused the SMI. This will occur when the CPU or a bus master accesses an assigned register (or a sequence of accesses).
20	0x0 RO/V	**PCI_EXP_SMI Status (PCI_EXP_SMI_STS):** 1- PCI Express SMI event occurred. This could be due to a PCI Express PME event or Hot Plug Event.
19	0x0 RO/V	**RTC Update-In-Progress SMI Status (RTC_UIP_SMI_STS):** This bit will be set when the RTC Update-In-Progress signal transitions either from low-to-high or high-to-low, depending on the enables in the I/O Trap register space.
18	0x0 RO/V	**IEH Status (IEH_STS) (IEH_SMI_STS):** This non-sticky read-only bit is a logical OR of each of the SMI status bits in the Internal Error Handler (IEH) Support register ANDed with the corresponding enable bits. This bit will not be active if the enable bits are not set.
17	0x0 RO/V	**Legacy USB 2 Status (LEGACY_USB2_STS):** This non-sticky read-only bit is a logical OR of each of the SMI status bits in the USB 2.0 Legacy Support Register ANDed with the corresponding enable bits. This bit will not be active if the enable bits are not set. Writes to this bit will have no effect.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW/1C/V	**SMBUS_SMI Status (SMBUS_SMI_STS):** The SoC sets this bit to '1' to indicate that the SMI# was caused by: • 1. The SMBus Slave receiving a message that an SMI# should be caused, or • 2. The SMBALERT# signal goes active and the SMB_SMI_EN bit is set and the SMBALERT_DIS bit is cleared. • 3. The SMBus Slave receiving a HOST_NOTIFY message and the HOST_NOTIFY_INTREN and the SMB_SMI_EN bits are set. • 4. The SMBus Slave receiving a "SMI in S0" message. This bit is sticky. It is cleared by writing a '1' to this bit position.
15	0x0 RO/V	**SERIRQ_SMI Status (SERIRQ_SMI_STS):** • 0 = SMI# not caused by SERIRQ decoder • 1 = Indicates the SMI# was caused by the SERIRQ decoder This bit is not sticky. Writes to this bit will have no effect.
14	0x0 RW/1C/V	**Periodic Status (PERIODIC_STS):** This bit will be set at the rate determined by the PER_SMI_SEL bits. If the PERIODIC_EN bit is also set, the SoC will generate an SMI#. This bit is cleared by writing a '1' to this bit position.
13	0x0 RW/1C/V	**TCO Status (TCO_STS):** • 0 = SMI not caused by TCO logic. • 1 = Indicates SMI was caused by the TCO logic ***Note:*** Will not cause wake event. This bit is cleared by writing a '1' to this bit position.
12	0x0 RO/V	**DEVMON Status (DEVMON_STS):** This read-only bit is set when bit 0 in the DEVTRAP_STS register is set. It is not sticky, so writes to this bit will have no effect.
11	0x0 RW/1C/V	**MCSMI Status (MCSMI_STS):** This bit is set if there is an access to the power management microcontroller range (62h or 66h). If this bit is set, and the MCSMI_EN bit is also set, the SoC will generate an SMI#. This bit is set by hardware and cleared by software writing a '1' to its bit position.
10	0x0 RO/V	**GPIO SMI Status (GPIO_SMI_STS):** This bit will be a 1 if any GPIO that is enabled to trigger SMI is asserted. GPIOs that are not routed to cause an SMI will have no effect on this bit. This bit is NOT sticky. Writes to this bit will have no effect.
9	0x0 RO/V	**GPE0 Status (GPE0_STS):** There are several status/enable bit pairs in GPE0_STS/EN_127_96 that are capable of triggering SMIs. This bit is a logical OR of all of those pairs (i.e. this bit is asserted whenever at least one of those pairs has both the status and enable bit asserted). This bit is NOT sticky. Writes to this bit will have no effect. ***Note:*** The setting of this bit does not cause the SMI#.
8	0x0 RO/V	**PM1 Status Register (PM1_STS_REG):** This is an OR of the bits (except for bits 5 and 4) in the ACPI PM1 Status Reg. (offset PMBASE+00h). Not sticky. Writes to this bit have no effect. ***Note:*** The setting of this bit does not cause the SMI#.
7	0x0 RO	**Reserved (RSVD_7):** Reserved.
6	0x0 RW/1C/V	**Software SMI Timer Status (SWSMI_TMR_STS):** This bit will be set to '1' by the hardware when the Software SMI# Timer expires. This bit will remain 1 until the software writes a '1' to this bit.
5	0x0 RW/1C/V	**APM Status (APM_STS):** SMI# was generated by a write access to the APM control register and if the APMC_EN bit is set. This bit is cleared by writing a one to its bit position.
4	0x0 RW/1C/V	**SMI_ON_SLP_EN Status (SMI_ON_SLP_EN_STS):** This bit will be set by the SoC when a write access attempts to set the SLP_EN bit. This bit is cleared by writing a '1' to this bit position
3	0x0 RO/V	**Legacy USB Status (LEGACY_USB_STS):** This non-sticky read-only bit is a logical OR of each of the SMI status bits in the USB Legacy Keybd Register ANDed with the corresponding enable bits. This bit will not be active if the enable bits are not set. Writes to this bit will have no effect.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/1C/V	**BIOS Status (BIOS_STS):** This bit gets set by hardware when a 1 is written by software to the GBL_RLS bit. When both BIOS_EN and the BIOS_STS bit are set, an SMI# will be generated. The BIOS_STS bit is cleared when software writes a '1' to this bit position.
1:0	0x0 RO	**Reserved (RSVD_1_0):** Reserved.

58.4.6 General Purpose Event Control (GPE_CTRL)—Offset 40h

Usage: ACPI or Legacy. Not lockable. Primary Power Well.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 40h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_31_18):** Reserved.
17	0x0 RW/V	**Software GPE Control (SWGPE_CTRL):** This bit allows software to control the assertion of SWGPE_STS bit. This bit is used by hardware as the level input signal for the SWGPE_STS bit in the GPE0_STS register. When SWGPE_CTRL is 1, SWGPE_STS will be set to 1, and writes to SWGPE_STS with a value of 1 to clear SWGPE_STS will result in SWGPE_STS being set back to 1 by hardware. When SWGPE_CTRL is 0, writes to SWGPE_STS with a value of '1' will clear SWGPE_STS to 0.
16:0	0x0 RO	**Reserved (RSVD_16_0):** Reserved.

58.4.7 Device Trap Status Register (DEVTRAP_STS)—Offset 44h

Usage: Legacy only. Not lockable. Primary Power Well.
Each bit indicates if an access has occurred to the corresponding device's trap range, or for bits 6:9 if the corresponding PCI interrupt is active. Write '1' to the same bit position to clear it. This register is used by APM power management software to see if there has been system activity. The periodic SMI# timer indicates if it is the right time to read the DEVTRAP_STS register.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 44h

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:13	0x0 RO	**Reserved (RSVD_31_13):** Reserved.
12	0x0 RW/1C/V	**D12 Trap Status (D12_TRP_STS):** KBC (60/64h). • 0 = Indicates that there has been no access to this device I/O range. • 1 = This device I/O range has been accessed. Clear this bit by writing a 1 to the bit location.
11:10	0x0 RO	**Reserved (RSVD_11_10):** Reserved.
9	0x0 RW/1C/V	**D9 Trap Status (D9_TRP_STS):** PIRQ[D or H]. • 0 = The corresponding PCI interrupts have not been active. • 1 = At least one of the corresponding PCI interrupts have been active. Clear this bit by writing a 1 to the bit location.
8	0x0 RW/1C/V	**D8 Trap Status (D8_TRP_STS):** PIRQ[C or G]. • 0 = The corresponding PCI interrupts have not been active. • 1 = At least one of the corresponding PCI interrupts have been active. Clear this bit by writing a 1 to the bit location.
7	0x0 RW/1C/V	**D7 Trap Status (D7_TRP_STS):** PIRQ[B or F]. • 0 = The corresponding PCI interrupts have not been active. • 1 = At least one of the corresponding PCI interrupts have been active. Clear this bit by writing a 1 to the bit location.
6	0x0 RW/1C/V	**D6 Trap Status (D6_TRP_STS):** PIRQ[A or E]. • 0 = The corresponding PCI interrupts have not been active. • 1 = At least one of the corresponding PCI interrupts have been active. Clear this bit by writing a 1 to the bit location.
5	0x0 RW/1C/V	**D5 Trap Status (D5_TRP_STS):** This will be set if any of the following are accessed (as determined by the I/O ranges in the LPC decoder (even if the LPC forwarding is not enabled): SP1, SP2, PP, FDC. Clear this bit by writing a 1 to the bit location.
4:1	0x0 RO	**Reserved (RSVD_4_1):** Reserved.
0	0x0 RW/1C/V	**D0 Trap Status (D0_TRP_STS):** The access/SMI was due to the SATA logic. There is no corresponding bit in the DEVTRAP_EN register because the enables are in the new SATA registers.

58.4.8 PM2a Control Block (PM2A_CNT_BLK)—Offset 50h

Usage: ACPI or Legacy. Not lockable. Primary Power Well.
BIOS must describe this register as 1 byte wide to the OS.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 50h

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD_31_1):** Reserved.
0	0x0 RW	**ARB_DIS:** This bit is a scratchpad bit for legacy software compatibility.

58.4.9 Over-Clocking WDT Control (OC_WDT_CTL)—Offset 54h

This register controls the operation of the SoCs Over-Clocking Watchdog Timer.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 54h

Default: 00002000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 WO	**Over-Clocking WDT Reload (OC_WDT_RLD):** Software can write a '1' to this bit to reload (“ping”) the SoC over-clocking watchdog timer while it is running. A write of '0' to this bit has no effect. A write of '1' to this bit while OC_WDT_EN=0, or with the clearing of OC_WDT_EN, does not start or reload the WDT (i.e. OC_WDT_EN takes precedence). The value in OC_WDT_TOV may be changed by software along with its setting of this bit. On a WDT reload, the current (potentially new) value in OC_WDT_TOV is loaded into the WDT as the new timeout value.
30:26	0x0 RO	**Reserved (RSVD_30_26):** Reserved.
25	0x0 RW/1C/V	**Over-Clocking WDT ICC Survivability Mode Timeout Status (OC_WDT_ICCSURV_STS):** This bit is set to '1' if the over-clocking WDT has timed out and triggered a global reset while running in a mode that has ICC survivability impact (OC_WDT_ICCSURV=1). It is cleared by a software write of '1' or by the pri_pwrgood_rst_b.
24	0x0 RW/1C/V	**Over-Clocking WDT Non-ICC Survivability Mode Timeout Status (OC_WDT_NO_ICCSURV_STS):** This bit is set to '1' if the over-clocking WDT has timed out and triggered a global reset while running in a mode that does not have ICC survivability impact (OC_WDT_ICCSURV=0). It is cleared by a software write of '1' or by the pri_pwrgood_rst_b.
23:16	0x0 RW	**Over-Clocking WDT Scratchpad (OC_WDT_SCRATCH):** This field is available as scratchpad space for software and has no effect on SoC hardware operation.
15	0x0 RW/L	**Over-Clocking WDT Force All (OC_WDT_FORCE_ALL):** GATE_BIT: OC_WDT_CTL.OC_WDT_CTL_LCK.HIGH When this bit is set to 1 and the OC_WDT is running, any included global reset source will behave as though the OC_WDT expired.
14	0x0 RW/V/L	**Over-Clocking WDT Enable (OC_WDT_EN):** Software sets this bit to '1' to enable the SoC over-clocking watchdog timer. While the counter is running, if it expires before being reloaded by software via the OC_WDT_RLD bit or halted by software clearing this bit, then one of the status bits will be set (which one depends on the WDT operating mode at the time - see the OC_WDT_ICCSURV bit description), and a global reset will be triggered. This bit is also set by the hardware when conditions allow the OC_WDT to self-start at power cycle reboot (effectively changes the default of this bit as seen by software).

Bit Range	Default & Access	Field Name (ID): Description
13	0x1 RW/L	**Over-Clocking WDT ICC Survivability Impact (OC_WDT_ICCSURV):** This bit determines whether OC_WDT expiration will have an impact on ICC (Integrated Clock Controller) bootstrap survivability. • 0 = Software should configure the OC_WDT to this mode if no ICC hardware auto-recovery actions are desired in the event of a timeout. A timeout in this mode will set OC_WDT_NO_ICCSURV_STS. • 1 (Default) = An OC_WDT timeout while operating in this mode causes certain ICC hardware auto-recovery actions to take place. A timeout in this mode will set OC_WDT_ICCSURV_STS.
12	0x0 RW/L	**OC_WDT_CTL Register Lock (OC_WDT_CTL_LCK):** This bit controls write-ability to this register. Encodings: • 0 = All fields of register OC_WDT_CTL operate as normal and can be updated by software. Reads to the register operate as normal. • 1 = All RW/L fields of register OC_WDT_CTL, including this lock control bit, are locked. Writes to these register fields have no effect and the register fields retain their current states. Reads to the register operate as normal. Once this bit is set, it can only be cleared by CORE well power loss.
11:10	0x0 RO	**Reserved (RSVD_11_10):** Reserved.
9:0	0x0 RW/V/L	**Over-Clocking WDT Timeout Value (OC_WDT_TOV):** Software programs the desired over-clocking WDT timeout value into this register. This timer is zero-based and has a granularity of 1 second. Example timeout values: • 000h: 1 second • 001h: 2 seconds • ... • 3FFh: ~17 minutes (1024 seconds) The value of OC_WDT_TOV may be changed by software along with its setting of the OC_WDT_RLD bit. On a WDT reload, the current (potentially new) value in OC_WDT_TOV is loaded into the WDT as the new timeout value. This field is also updated by the hardware when conditions allow the OC_WDT to self-start at power cycle reboot (effectively changes the default of this field as seen by software).

58.4.10 General Purpose Event 0 Status [31:0] (GPE0_STS_31_0)—Offset 80h

GPE0_STS bits 31:0 are assigned to certain SoC GPIO signals as GPE0_DW0. This register is symmetrical to the General Purpose Event 0 Enable [31:0] Register.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 80h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1C/V	**General Purpose Event 0 Status [31:0] (GPE0_STS_31_0):** These bits are mapped to the SoC General-Purpose I/O (GPIO) signals that can generate GPE0 when properly configured.

58.4.11 General Purpose Event 0 Status [63:32] (GPE0_STS_63_32)—Offset 84h

GPE0_STS bits 63:32 are assigned to certain SoC GPIO signals as GPE0_DW1. This register is symmetrical to the General Purpose Event 0 Enable [63:32] Register.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 84h

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1C/V	**General Purpose Event 0 Status [63:32] (GPE0_STS_63_32):** These bits are mapped to the SoC General-Purpose I/O (GPIO) signals that can generate GPE0 when properly configured.

58.4.12 General Purpose Event 0 Status [95:64] (GPE0_STS_95_64)—Offset 88h

GPE0_STS bits 95:64 are assigned to certain SoC GPIO signals as GPE0_DW2. This register is symmetrical to the General Purpose Event 0 Enable [95:64] Register.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 88h

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/1C/V	**General Purpose Event 0 Status [95:64] (GPE0_STS_95_64):** These bits are mapped to the SoC General-Purpose I/O (GPIO) signals that can generate GPE0 when properly configured.

58.4.13 General Purpose Event 0 Status [127:96] (GPE0_STS_127_96)—Offset 8Ch

This register is symmetrical to the General Purpose Event 0 Enable [127:96] Register. Unless indicated otherwise below, if the corresponding _EN bit is set, then when the STS bit get set, the SoC generates a Wake Event. Once back in an S0 state (or if already in an S0 state when the event occurs), the SoC also generates an SCI if the SCIEN bit is set, or an SMI# if the SCIEN bit is not set and GBL_SMI_EN is set.

Type: I/O Register
(Size: 32 bits)

BAR and Offset: [ABASE] + 8Ch

Default: 00000000h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Reserved (RSVD_31_19):** Reserved.
18	0x0 RW/1C/V	**Wake Alarm Device Timer Status (WADT_STS):** This bit is set whenever the any of the wake alarm device timers signal a timer expiration.
17	0x0 RW/1C/V	**USB Connection in/after DeepSx Status (USB_CON_DSX_STS):** This bit is set when a connection event occurs on any unmasked USB port while in DeepSx or while in Sx immediately after DeepSx. ***Note:*** This bit will be set regardless of the value of the DSX_CFG.USB_CON_DSX_MODE bit.
16	0x0 RW/1C/V	**GPIO[27] Status (GP27_STS):** This bit is set whenever GPIO[27] is seen asserted low. Note that unlike the GPI[n]_STS bits, GPIO[27] is always monitored as an input for the purpose of setting this bit, regardless of the actual GPIO configuration.
15	0x0 RW/1C/V	**GPIO Tier2 SCI Status (GPIO_TIER2_SCI_STS):** This bit is a logical OR of sci_wake from tier 2 GPIO's. reset_type = host_deep_rst_b
14	0x0 RW/1C/V	**Reserved:** Reserved.
13	0x0 RW/1C/V	**Power Management Event Bus 0 Status (PME_B0_STS):** This bit will be set to 1 by the SoC when any internal device with PCI Power Management capabilities on bus 0 asserts the equivalent of the PME# signal. Additionally, if the PME_B0_EN and SCI_EN bits are set, and the system is in an S0 state, then the setting of the PME_B0_STS bit will generate an SCI (or SMI# if SCI_EN is not set). If the PME_B0_EN bit is set, and the system is in an S1-S4 state (or S5 state due to SLP_TYP and SLP_EN), then the setting of the PME_B0_STS bit will generate a wake event. If the system is in an S5 state due to power button override, then the PME_B0_STS bit will not cause a wake event or SCI. This bit is cleared by a software write of '1'. Internal devices which can set this bit: • Integrated LAN • SATA • EHCI (USB 2.0) • XHCI (USB 3.0) • Intel® ME Maskable Host Wake
12	0x0 RW/1C/V	**ME SCI Status (ME_SCI_STS):** This bit will be set when the Intel® ME is requesting an SCI. Software must clear the ME source of the SCI before clearing this bit. ***Note:*** This source is not able to cause a wake event.
11	0x0 RW/1C/V	**Power Management Event Status (PME_STS):** This bit will be set to 1 by hardware when the PME# signal goes active. Additionally, if the PME_EN and SCI_EN bits are set, and system is in an S0 state, then the setting of the PME_STS bit will generate an SCI (or SMI# if SCI_EN is not set). If the PME_EN bit is set, and the system is in an S1-S4 state (or S5 state due to SLP_TYP and SLP_EN), then the setting of the PME_STS bit will generate a wake event. If the system is in an S5 state due to power button override, then PME_STS will not cause a wake event or SCI. This bit is cleared by writing a 1 to this bit position.
10	0x0 RO	**Reserved (RSVD_10):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
9	0x0 RW/1C/V	**PCI Express Status (PCI_EXP_STS):** This bit will be set to 1 by hardware to indicate that: • The PME event message was received on one or more of the PCI-Express Ports • An Assert PMEGPE message received from the MCH via DMI ***Note:*** The PCI WAKE# pin and the PCI-Express Beacons have no impact on this bit. Software attempts to clear this bit by writing a 1 to this bit position. If the PCI_EXP_STS bit went active due to an Assert PMEGPE message, then a Deassert PMEGPE message must be received prior to the software write in order for the bit to be cleared. If the bit is not cleared and the corresponding PCI_EXP_EN bit is set, the level-triggered SCI will remain active.
8	0x0 RW/1C/V	**RI Status (RI_STS):** This bit will be set to1 by hardware when the RI# input signal goes active. This bit can be reset by writing a 1 to this bit position.
7	0x0 RW/1C/V	**SMBus Wake Status (SMB_WAK_STS):** This bit is set to 1 by the hardware to indicate that the wake event was caused by the SoC's SMBus logic. This could be due to either the SMBus slave unit receiving a message or the SMBALERT# signal going active.
6	0x0 RW/1C/V	**TCOSCI Status (TCOSCI_STS):** This bit will be set to 1 by hardware when the TCO logic or Thermal Sensor logic causes an SCI. This bit can be reset by writing a one to this bit position.
5:4	0x0 RO	**Reserved (RSVD_5_4):** Reserved.
3	0x0 RW/1C/V	**IE SCI Status (IE_SCI_STS):** This bit will be set when the Innovative Engine (IE) is requesting an SCI. Software must clear the IE source of the SCI before clearing this bit. ***Note:*** This source is not able to cause a wake event.
2	0x0 RW/1C/V	**Software GPE Status (SWGPE_STS):** The SWGPE_CTRL bit (bit 1 of GPE_CTRL reg) acts as a level input to this bit.
1	0x0 RW/1C/V	**Hot Plug Status (HOT_PLUG_STS):** This bit is set to 1 by hardware when a PCI-Express hot-plug event occurs. This will cause an SCI if the HOT_PLUG_EN and SCI_EN bits are set. This bit is cleared by writing a '1' to this bit position. The following events cause this bit to set: • Assert_GPE message received from any of the PCI Express ports in the SoC • Assert_HPGPE message received from any of the PCI Express ports in the SoC
0	0x0 RO	**Reserved (RSVD_0):** Reserved.

58.4.14 General Purpose Event 0 Enable [31:0] (GPE0_EN_31_0)—Offset 90h

GPE0_EN bits 31:0 are assigned to certain SoC GPIO signals as GPE0_DW0. This register is symmetrical to the General Purpose Event 0 Status [31:0] Register.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 90h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**General Purpose Event 0 Enable [31:0] (GPE0_EN_31_0):** See Chapter 26, "Customer General-Purpose I/O (GPIO)."

58.4.15 General Purpose Event 0 Enable [63:32] (GPE0_EN_63_32)—Offset 94h

GPE0_EN bits 63:32 are assigned to certain SoC GPIO signals as GPE0_DW1. This register is symmetrical to the General Purpose Event 0 Status [63:32] Register.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 94h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**General Purpose Event 0 Enable [63:32] (GPE0_EN_63_32):** See Chapter 26, "Customer General-Purpose I/O (GPIO)."

58.4.16 General Purpose Event 0 Enable [95:64] (GPE0_EN_95_64)—Offset 98h

GPE0_EN bits 95:64 are assigned to certain SoC GPIO signals as GPE0_DW2. This register is symmetrical to the General Purpose Event 0 Status [95:64] Register.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 98h

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**General Purpose Event 0 Enable [95:64] (GPE0_EN_95_64):** See Chapter 26, "Customer General-Purpose I/O (GPIO)."

58.4.17 General Purpose Event 0 Enable [127:96] (GPE0_EN_127_96)—Offset 9Ch

This register is symmetrical to the General Purpose Event 0 Status [127:96] Register.

Type: I/O Register
(Size: 32 bits)

Default: 00000000h

BAR and Offset: [ABASE] + 9Ch

ABASE Type: PCI Configuration Register (Size: 32 bits)
ABASE Reference: [B:0, D:31, F:2] + 40h

Bit Range	Default & Access	Field Name (ID): Description
31:19	0x0 RO	**Reserved (RSVD_31_19):** Reserved.
18	0x0 RW	**Wake Alarm Device Timer Enable (WADT_EN):** Used to enable the setting of the WADT_STS bit to generate wake/SMI#/SCI.
17	0x0 RW	**USB Connection in/after DeepSx Enable (USB_CON_DSX_EN):** Used to enable the setting of the USB_CON_DSX_STS bit to generate wake/SMI#/SCI.
16	0x0 RW	**GPIO[27] Enable (GP27_EN):** Used to enable the setting of the GP27_STS bit to generate wake/SMI#/SCI. Host wake events from the PHY through GP27 cannot be disabled by clearing this bit. ***Note:*** GPIO[27] is a valid host wake event from Deep-Sx. But the wake enable configuration must persist even after a G3. To make this happen, this bit is in the SoC RTC power well.
15	0x0 RW/V	**GPIO Tier2 SCI EN (GPIO_TIER2_SCI_EN):** Used to enable the setting of GPIO_TIER2_SCI_STS to generate wake/SCI# reset_type =host_deep_rst_b
14	0x0 RW/V	**Reserved:** Reserved.
13	0x0 RW/V	**PME_B0 Enable (PME_B0_EN):** Enables the setting of the PME_B0_STS bit to generate a wake event and/or an SCI or SMI#. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
12	0x0 RW/V	**ME SCI Enable (ME_SCI_EN):** Used to enable the setting of the ME_SCI_STS bit to generate a SCI.
11	0x0 RW/V	**Power Management Event Enable (PME_EN):** Enables the setting of the PME_STS to generate a wake event and/or an SCI. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
10	0x0 RO	**Reserved (RSVD_10):** Reserved.
9	0x0 RW/V	**PCI Express Enable (PCI_EXP_EN):** Enables the SoC to cause an SCI when PCI_EXP_STS bit is set. This is used to allow the PCI Express ports to cause an SCI due to wake/PME events.
8	0x0 RW/V	**RI Enable (RI_EN):** When RI_EN and RI_STS are both set, a Wake event will occur. If RI_EN is not set, then when RI_STS is set, no Wake event will occur. This bit is in the RTC power well and is cleared when the SoC input signal pin SRTCRST_N is active.
7	0x0 RO	**Reserved (RSVD_7):** Reserved. ***Note:*** For the SoC, the SMBus slave will always be enabled as a wake event, as will the SMBALERT# signal.
6	0x0 RW/V	**TCOSCI Enable (TCOSCI_EN):** When TCOSCI_EN and TCOSCI_STS are both set, an SCI will be generated.
5:4	0x0 RO	**Reserved (RSVD_5_4):** Reserved.
3	0x0 RW/V	**IE SCI Enable (IE_SCI_EN):** Used to enable the setting of the IE_SCI_STS bit to generate a SCI.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW/V	**Software GPE Enable (SWGPE_EN):** This bit, when set to 1, enables the SW GPE function. • If SWGPE_CTRL is written to a 1, hardware will set SWGPE_STS (acts as a level input). • If SWGPE_STS, SWGPE_EN, and SCI_EN are all 1's, an SCI will be generated. • If SWGPE_STS = 1, SWGPE_EN = 1, SCI_EN = 0, and GBL_SMI_EN = 1, then an SMI# will be generated.
1	0x0 RW/V	**Hot Plug Enable (HOT_PLUG_EN):** Enables the SoC to cause an SCI when the HOT_PLUG_STS bit is set. This is used to allow the PCI Express ports to cause an SCI due to hot-plug events. The following events cause HOT_PLUG_STS bit to set: • Assert_GPE message received from any of the PCI Express ports in the SoC • Assert_HPGPE message received from any of the PCI Express ports in the SoC
0	0x0 RO	**Reserved (RSVD_0):** Reserved.

58.5 Registers in I/O Space—Fixed Addresses

This register is accessed in Host I/O Space through a fixed I/O address.

58.5.1 Reset Control Register (RST_CNT)

Type: I/O Register
(Size: 8 bits)

Fixed Address in Host I/O Space: CF9h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:4	0x0 RO	**Reserved (RSVD_7_4):** Reserved.
3	0x0 RW	**Full Reset (FULL_RST):** When this bit is set to 1 and bit 1 is set to 1 (indicating Hard Reset, not Soft Reset), and the RST_CPU bit (bit 2) is written from 0 to 1, the SoC performs a full reset, including driving signal pins PMU_SLP_S3_N and PMU_SLP_S45_N active (low) for at least 3, and no more than 5, seconds. When this bit is set, it also causes the full power cycle (PMU_SLP_S3_N and PMU_SLP_S45_N assertion) in response to PMU_RESETBUTTON_N, COREPWROK, and Watchdog Timer reset sources.
2	0x0 RW	**Reset CPU (RST_CPU):** This bit will cause either a hard or soft reset to the CPU depending on the state of the SYS_RST bit (bit 1 in this same register). The software will cause the reset by setting bit 2 from a 0 to a 1.
1	0x0 RW	**System Reset (SYS_RST):** This bit determines the type of reset caused via RST_CPU (bit 2 of this register). • If SYS_RST is 0 when RST_CPU goes from 0 to 1, then the SoC will force an internal Initialize (INIT#) signal to the CPU but system can hang due to the security concern with this internal initialize (INIT#) enabled. • If SYS_RST is 1 when RST_CPU goes from 0 to 1, then the SoC will force PCI Reset active for about 1 ms, however the PMU_SLP_S3_N and PMU_SLP_S45_N signals assertions are dependent on the value of the FULL_RST (bit 3 of this register).
0	0x0 RO	**Reserved (RSVD_0):** Reserved.

58.6 Sideband Registers

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

58.6.1 Advanced Power Management Status and Control Port (APM_STS_CNT)—Offset B0h

Usage: Legacy only. Not lockable. Primary Power Well.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x82] + B0h
Host Memory Space: SBREG_BAR + 0x820000 + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW	**APM Status Port (APM_STS):** Used to pass data between the OS and the SMI handler. Basically, this is a scratchpad register and is not effected by any other register or function (other than a PCI reset).
23:16	0x0 RW	**Advanced Power Management Control Port (APM_CNT):** Used to pass an APM command between the OS and the SMI handler. Writes to this port not only store data in the APMC register, but also generates an SMI# when the APMC_EN bit is set.
15:0	0x0 RO	**Reserved (RSVD_15_0):** Reserved.

58.6.2 Misc SB Reg0 (MISC_SBR0)—Offset B4h

Misc SB Reg0

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0x82] + B4h
Host Memory Space: SBREG_BAR + 0x820000 + B4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_31_9):** Reserved.
8	0x0 RW	**North Completed (NORTH_COMPLETED):** North Completed • 0: Punit has not completed north preparation for Asynchronous DRAM Refresh (ADR) • 1: Punit has completed north preparation for ADR Set by Pcode through CRWt once Pcode has put DIMM in Self-refresh.
7:5	0x0 RO	**Reserved (RSVD_7_5):** Reserved.
4:1	0x0 RO/V	**FINAL DDR SPEED set by PMC FW (FINAL_DDR_SPEED):** FINAL_DDR_SPEED set by PMC firmware (CURRENT_SPD_SPEED): • 0xxxx = undefined, use max DDR mem config (fuse) as IDI speed • 1000 = DDR1600, 400MHz IDI freq • 1001 = DDR1866, 466MHz IDI freq • 1010 = DDR2133, 533MHz IDI freq • 1011 = DDR2400, 600Mhz IDI freq • 1100 = DDR2666, 667MHz IDI freq

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RW/1C/V	**SPD_RESET_PCODE:** SPD_RESET_PCODE (SPD_RESET_PCODE) • 0= PMC indicates to Pcode that this is NOT a SPD Reset. • 1= PMC indicates to Pcode that this is a SPD ResetSet by PMC firmware during the SPD Reset clocking flow.

§ §

59 SMBus - Legacy - B0, D31, F4

59.1 Introduction and Index

The host-accessible registers for the SMBus are described here.

To determine the number of devices/functions available refer to the following:

- Table 1-1, “Features by product SKU - Server and Cloud Storage SKUs 0 through 4”
- Table 1-2, “Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10”
- Table 1-3, “Features by Product SKU - Extended Temperature SKUs 11 through 14”.

The legend for the register access codes are described in Chapter 43, “Introduction.”

59.1.1 Registers in Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 31 (decimal), Function 4. The offset addresses are listed.

Table 59-1. Summary of PCI Configuration Registers—0/31/4

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	8086	"Vendor ID (VID)—Offset 0h" on page 2755
2	2	19DF	"Device ID (DID)—Offset 2h" on page 2755
4	2	0000	"Command (CMD)—Offset 4h" on page 2756
6	2	0280	"Device Status (DS)—Offset 6h" on page 2757
8	1	00	"Revision ID (RID)—Offset 8h" on page 2758
9	1	00	"Programming Interface (PI)—Offset 9h" on page 2758
A	1	05	"Sub Class Code (SCC)—Offset Ah" on page 2758
B	1	0C	"Base Class Code (BCC)—Offset Bh" on page 2758
10	4	00000004	"SMBus Memory Base Address_31_0 (SMBMBAR_31_0)—Offset 10h" on page 2759
14	4	00000000	"SMBus Memory Base Address_63_32 (SMBMBAR_63_32)—Offset 14h" on page 2759
20	4	00000001	"SMB Base Address (SBA)—Offset 20h" on page 2760
2C	2	0000	"SVID—Offset 2Ch" on page 2760
2E	2	0000	"SID—Offset 2Eh" on page 2760
3C	1	00	"Interrupt Line (INTLN)—Offset 3Ch" on page 2761
3D	3	01	"Interrupt Pin (INTPN)—Offset 3Dh" on page 2761
40	1	00	"Host Configuration (HCFG)—Offset 40h" on page 2762
50	4	00000001	"TCO Base Address (TCOBASE)—Offset 50h" on page 2763
54	4	00000000	"TCO Control (TCOCTL)—Offset 54h" on page 2763
64	4	08080000	"Host_Timing (HTIM)—Offset 64h" on page 2764
F8	4	01000F1C	"Manufacturer's ID (MANID)—Offset F8h" on page 2765

59.1.2 Registers in Memory Space—SMBMBAR

An index of the registers that are accessible in Host Memory Space is shown here.

Table 59-2. Summary of Memory Mapped I/O Registers—SMBMBAR

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	00	"Host Status Register Address (HSTS)—Offset 0h" on page 2766
2	1	00	"Host Control Register (HCTL)—Offset 2h" on page 2767
3	1	00	"Host Command Register (HCMD)—Offset 3h" on page 2769
4	1	00	"Transmit Slave Address Register (TSA)—Offset 4h" on page 2769
5	1	00	"Data 0 Register (HD0)—Offset 5h" on page 2769
6	1	00	"Data 1 Register (HD1)—Offset 6h" on page 2770
7	1	00	"Host Block Data (HBD)—Offset 7h" on page 2770
8	1	00	"Packet Error Check Data Register (PEC)—Offset 8h" on page 2771
9	1	44	"Receive Slave Address Register (RSA)—Offset 9h" on page 2771
A	2	0000	"Slave Data Register (SD)—Offset Ah" on page 2772
C	1	00	"Auxiliary Status (AUXS)—Offset Ch" on page 2773
D	1	00	"Auxiliary Control (AUXC)—Offset Dh" on page 2774
E	1	04	"SMLINK_PIN_CTL Register (SMLC)—Offset Eh" on page 2775
F	1	04	"SMBUS_PIN_CTL Register (SMBC)—Offset Fh" on page 2776
10	1	00	"Slave Status Register (SSTS)—Offset 10h" on page 2777
11	3	00	"Slave Command Register (SCMD)—Offset 11h" on page 2778
14	2	00	"Notify Device Address Register (NDA)—Offset 14h" on page 2779
16	1	00	"Notify Data Low Byte Register (NDLB)—Offset 16h" on page 2779
17	1	00	"Notify Data High Byte Register (NDHB)—Offset 17h" on page 2779

59.1.3 Registers in I/O Space—SBA

An index of the registers that are accessible in Host I/O Space is shown here.

Table 59-3. Summary of I/O Registers—SBA

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	00	"Host Status Register Address (HSTS)—Offset 0h" on page 2780
2	1	00	"Host Control Register (HCTL)—Offset 2h" on page 2781
3	1	00	"Host Command Register (HCMD)—Offset 3h" on page 2783
4	1	00	"Transmit Slave Address Register (TSA)—Offset 4h" on page 2783
5	1	00	"Data 0 Register (HD0)—Offset 5h" on page 2783
6	1	00	"Data 1 Register (HD1)—Offset 6h" on page 2784
7	1	00	"Host Block Data (HBD)—Offset 7h" on page 2784
8	1	00	"Packet Error Check Data Register (PEC)—Offset 8h" on page 2785
9	1	44	"Receive Slave Address Register (RSA)—Offset 9h" on page 2785
A	2	0000	"Slave Data Register (SD)—Offset Ah" on page 2786
C	1	00	"Auxiliary Status (AUXS)—Offset Ch" on page 2787
D	1	00	"Auxiliary Control (AUXC)—Offset Dh" on page 2788
E	1	04	"SMLINK_PIN_CTL Register (SMLC)—Offset Eh" on page 2789
F	1	04	"SMBUS_PIN_CTL Register (SMBC)—Offset Fh" on page 2790
10	1	00	"Slave Status Register (SSTS)—Offset 10h" on page 2791
11	3	00	"Slave Command Register (SCMD)—Offset 11h" on page 2792
14	2	00	"Notify Device Address Register (NDA)—Offset 14h" on page 2793
16	1	00	"Notify Data Low Byte Register (NDLB)—Offset 16h" on page 2793
17	1	00	"Notify Data High Byte Register (NDHB)—Offset 17h" on page 2793

59.1.4 Registers in I/O Space—TCOBASE

An index of the registers that are accessible in Host I/O Space is shown here.

Table 59-4. Summary of I/O Registers—TCOBASE

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	2	0004	"TCO_RLD Register (TRLD)—Offset 0h" on page 2794
2	1	00	"TCO_DAT_IN Register (TDI)—Offset 2h" on page 2794
3	1	00	"TCO_DAT_OUT Register (TDO)—Offset 3h" on page 2795
4	2	0000	"TCO1_STS Register (TSTS1)—Offset 4h" on page 2795
6	2	0000	"TCO2_STS Register (TSTS2)—Offset 6h" on page 2797
8	2	0000	"TCO1_CNT Register (TCTL1)—Offset 8h" on page 2798
A	2	0008	"TCO2_CNT Register (TCTL2)—Offset Ah" on page 2799
10	1	03	"LEGACY_ELIM Register (LE)—Offset 10h" on page 2800
12	2	0004	"TCO_TMR Register (TTMR)—Offset 12h" on page 2800

59.1.5 Sideband Registers—Host SMBus Private Configuration

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 59-5. Summary of Sideband Registers—0xCF

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
0	00000000	"TCO Configuration (TCOCFG)—Offset 0h" on page 2801
C	00000000	"General Control (GC)—Offset Ch" on page 2802
10	00000009	"Power Control Enable (PCE)—Offset 10h" on page 2803

59.1.6 Sideband Registers—CLTT SMBus Configuration Control

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 59-6. Summary of Sideband Registers—0xCC

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
10	00000000	"Ch0 Dimm0 Cfg Status (C0D0CFGSTS)—Offset 10h" on page 2805
14	01000000	"Ch0 Dimm1 Cfg Status (C0D1CFGSTS)—Offset 14h" on page 2805
18	00000000	"Ch0 Dimm2 Cfg Status (C0D2CFGSTS)—Offset 18h" on page 2806
1C	00000000	"Ch0 Dimm3 Cfg Status (C0D3CFGSTS)—Offset 1Ch" on page 2806
20	02000000	"Ch1 Dimm0 Cfg Status (C1D0CFGSTS)—Offset 20h" on page 2807
24	03000000	"Ch1 Dimm1 Cfg Status (C1D1CFGSTS)—Offset 24h" on page 2807
28	00000000	"Ch1 Dimm2 Cfg Status (C1D2CFGSTS)—Offset 28h" on page 2808
2C	00000000	"Ch1 Dimm3 Cfg Status (C1D3CFGSTS)—Offset 2Ch" on page 2808
30	00000000	"Ch0 Dimm Temp Status (C0TEMPSTS0)—Offset 30h" on page 2809
34	00000000	"Ch0 Dimm Temp Status (C0TEMPSTS1)—Offset 34h" on page 2809
38	00000000	"Ch1 Dimm Temp Status (C1TEMPSTS0)—Offset 38h" on page 2809
3C	00000000	"Ch1 Dimm Temp Status (C1TEMPSTS1)—Offset 3Ch" on page 2810
40	00	"Host Configuration (HCFG)—Offset 40h" on page 2810

59.2 Registers in Configuration Space

59.2.1 Vendor ID (VID)—Offset 0h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:4] + 0h

Default: 8086h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x8086 RO	**Vendor ID (VID):** Value indicates Intel as the vendor. **Power Well:** Core

59.2.2 Device ID (DID)—Offset 2h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:4] + 2h

Default: 19DFh

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x19df RO/V	**Device ID (DID):** Indicates the device number assigned by the SIG. **Power Well:** Core

59.2.3 Command (CMD)—Offset 4h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:4] + 4h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:11	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
10	0x0 RW	**Interrupt Disable (INTD):** • 1 = Disables SMBus to assert its PIRQB# signal. Defaults to 0. **Power Well:** Core
9	0x0 RO	**Fast Back to Back Enable (FBE):** Reserved as 0. Read Only. **Power Well:** Core
8	0x0 RW	**SERR# Enable (SERRE):** • 1 = Enables SERR# generation. **Power Well:** Core
7	0x0 RO	**Wait Cycle Control (WCC):** Reserved as 0. Read Only. **Power Well:** Core
6	0x0 RW	**Parity Error Response (PER):** • 1 = Sets Detected Parity Error bit when parity error is detected. **Power Well:** Core
5	0x0 RO	**VGA Palette Snoop (VGAPS):** Reserved as 0. Read Only. **Power Well:** Core
4	0x0 RO	**Postable Memory Write Enable (PMWE):** Reserved as 0. Read Only. **Power Well:** Core
3	0x0 RO	**Special Cycle Enable (SCE):** Reserved as 0. Read Only. **Power Well:** Core
2	0x0 RO	**Bus Master Enable (BME):** Reserved as 0. Read Only. **Power Well:** Core
1	0x0 RW	**Memory Space Enable (MSE):** • 1= Enables memory mapped config space. **Power Well:** Core
0	0x0 RW	**I/O Space Enable (IOSE):** • 1= enables access to the SM Bus I/O space registers as defined by the Base Address Register. **Power Well:** Core

59.2.4 Device Status (DS)—Offset 6h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:4] + 6h

Default: 0280h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/1C	**Detected Parity Error (DPE):** Reserved. **Power Well:** Core
14	0x0 RW/1C	**Signaled System Error (SSE):** Reserved. **Power Well:** Core
13	0x0 RO	**Received Master Abort (RMA):** Reserved as 0. **Power Well:** Core
12	0x0 RO	**Received Target Abort (RTA):** Reserved as 0. **Power Well:** Core
11	0x0 RO	**Signaled Target-Abort Status (STA):** Reserved as 0. **Power Well:** Core
10:9	0x1 RO	**DEVSEL# Timing Status (DEVT):** This 2-bit field defines the timing for DEVSEL# assertion. **Power Well:** Core
8	0x0 RO	**Data Parity Error Detected (DPED):** Reserved as 0. **Power Well:** Core
7	0x1 RO	**Fast Back-to-Back Capable (FBC):** Reserved as 1. **Power Well:** Core
6	0x0 RO	**User Definable Features (UDF):** Reserved as 0. **Power Well:** Core
5	0x0 RO	**66 MHz Capable (C_66M):** Reserved as 0. **Power Well:** Core
4	0x0 RO	**Capabilities List Indicator (CLI):** Hardwired to 0 because there are no capability list structures in this function. **Power Well:** Core
3	0x0 RO	**Interrupt Status (INTS):** This bit indicates that an interrupt is pending. It is independent from the state of the Interrupt Enable bit in the command register. **Power Well:** Core
2:0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core

59.2.5 Revision ID (RID)—Offset 8h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Revision ID (RID):** The value reported in this register depends on the global revision ID. **Power Well:** Core

59.2.6 Programming Interface (PI)—Offset 9h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + 9h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**Programming Interface (PI):** Programming interface. **Power Well:** Core

59.2.7 Sub Class Code (SCC)—Offset Ah

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + Ah

Default: 05h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x5 RO	**Sub Class Code (SCC):** A value of 05h indicates that this device is a SM Bus serial controller. **Power Well:** Core

59.2.8 Base Class Code (BCC)—Offset Bh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + Bh

Default: 0Ch

Bit Range	Default & Access	Field Name (ID): Description
7:0	0xc RO	**Base Class Code (BCC):** A value of 0Ch indicates that this device is a serial controller. **Power Well:** Core

59.2.9 SMBus Memory Base Address_31_0 (SMBMBAR_31_0)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + 10h

Default: 00000004h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RW	**Base Address (BA):** Provides the 32 byte system memory base address. **Power Well:** Core
7:4	0x0 RO	**Hardwired_0:** Hardwired to 0. **Power Well:** Core
3	0x0 RO	**Prefetchable (PREF):** Hardwired to 0. Indicated that SMBMBAR is not prefetchable. **Power Well:** Core
2:1	0x2 RO	**Address Range (ADDRNG):** Indicates that this SMBMBAR can be located anywhere in 64 bit address space. **Power Well:** Core
0	0x0 RO	**Memory Space Indicator (MSI):** Indicates that the SMB logic is memory mapped. **Power Well:** Core

59.2.10 SMBus Memory Base Address_63_32 (SMBMBAR_63_32)—Offset 14h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + 14h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**Base Address (BA):** Bits 63-32 of SMBus Memory Base Address. **Power Well:** Core

59.2.11 SMB Base Address (SBA)—Offset 20h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + 20h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:5	0x0 RW	**Base Address (BA):** Provides the 32 byte t system I/O base address for the SMB logic. **Power Well:** Core
4:1	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
0	0x1 RO	**IO Space Indicator (IOSI):** This read-only bit always is 1, indicating that the SMB logic is I/O mapped. **Power Well:** Core

59.2.12 SVID—Offset 2Ch

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:4] + 2Ch

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/O	**SVID:** BIOS sets the value in this register to identify the Subsystem Vendor ID. The SMBus SVID register, in combination with the SMBus Subsystem ID register, enables the operating system to distinguish each subsystem from the others. ***Note:*** The software can write to this register only once per core well reset. Writes should be done as a single 16-bit cycle. **Power Well:** Core

59.2.13 SID—Offset 2Eh

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:4] + 2Eh

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RW/O	**SID:** BIOS can write to this register to identify the Subsystem ID. The SID register, in combination with the SVID, enable the operating system to distinguish each subsystem from other(s). ***Note:*** The software can write to this register only once per core well reset. Writes should be done as a single 16-bit cycle. **Power Well:** Core

59.2.14 Interrupt Line (INTLN)—Offset 3Ch

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + 3Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Line (INTLN):** This data is not used by the hardware. It is to communicate to software the interrupt line that the interrupt pin is connected to PIRQB#. **Power Well:** Core

59.2.15 Interrupt Pin (INTPN)—Offset 3Dh

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + 3Dh

Default: 01h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x1 RO	**Interrupt Pin (INTPN):** This defines the interrupt pin to be used by the SMBus controller. Bits: Pins • 0h: No Interrupt • 1h: INTA# • 2h: INTB# • 3h: INTC# • 4h: INTD# • 5h-Fh: Reserved BIOS **Power Well:** Core

59.2.16 Host Configuration (HCFG)—Offset 40h

Type: PCI Configuration Register (Size: 8 bits)

Offset: [B:0, D:31, F:4] + 40h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
4	0x0 RW/1L	**SPD Write Disable (SPDWD):** No SMB registers should be accessed while HSTS.HBSY bit is set, the same will apply to SPD write disable. **Power Well:** Core
3	0x0 RW	**SSRESET:** Soft SMBUS Reset: When this bit is 1, the SMBus state machine and logic is reset. The HW will reset this bit to 0 when reset operation is completed. **Power Well:** Core
2	0x0 RW	**I2C_EN (I2CEN):** When this bit is 1, the SMBus Host is enabled to communicate with I2C devices. This will change the formatting of some commands. When this bit is 0, behavior is for SMBus. **Power Well:** Core
1	0x0 RW	**SMB_SMI_EN (SSEN):** When this bit is set, any source of an SMB interrupt will instead be routed to generate an SMI#. Refer to Section 28.8, "Interrupts and SMI" on page 722 (Interrupts/SMI#) for details. **Power Well:** Core
0	0x0 RW	**HST_EN (HSTEN):** When set, the SMB Host Controller interface is enabled to execute commands. The HST_INT_EN bit needs to be enabled in order for the SMB Host Controller to interrupt or SMI#. Additionally, the SMB Host Controller will not respond to any new requests until all interrupt requests have been cleared. **Power Well:** Core

59.2.17 TCO Base Address (TCOBASE)—Offset 50h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + 50h

Default: 00000001h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:5	0x0 RW/L	**TCO Base Address (TCOBA):** Provides the 32 bytes of I/O space for TCO logic, mappable anywhere in the 64k I/O space on 32-byte boundaries. **Power Well:** Core
4:1	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
0	0x1 RO	**I/O Space (IOS):** Indicates an I/O Space. **Power Well:** Core

59.2.18 TCO Control (TCOCTL)—Offset 54h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + 54h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RW	**TCO Base Enable (TCO_BASE_EN):** When set, decode of the I/O range pointed to by the TCO base register is enabled. **Power Well:** Core
7:1	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
0	0x0 RW/O	**TCO Base Lock (TCO_BASE_LOCK):** When set to 1, this bit locks down the TCO Base Address Register (TCOBASE) at offset 50h. The Base Address Field becomes read-only. This bit becomes locked when a value of 1b is written to it. Writes of 0 to this bit are always ignored. Once locked by writing 1, the only way to clear this bit is to perform a platform reset. **Power Well:** Core

59.2.19 Host_Timing (HTIM)—Offset 64h

Setting these timing parameters will affect the SMBus host PHY layer. These values should only be changed when the SMBus is idle.

These timings are based off the 10MHz PHY clock. A higher frequency PHY clock will scale the timings accordingly. This register is in the suspend well.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + 64h

Default: 08080000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x8 RW	**Thigh:** The time value in this field will be added/subtracted to the Thigh timing parameter as defined in SMB 2.0 spec. • 00000000: -7 Clocks (-700ns) • 00000001: -6 Clocks (-600ns) • ---- • 00000111: -1 Clock (-100ns) • 00001000: +0 Clock (0ns) • 00001001: +1 Clock (+100ns) • ---- • 11111111: +247 Clocks (+24700ns) ***Note:*** These are offsets that control the range of the nominal Thigh value in the PHY layers **Power Well:** SUS
23:16	0x8 RW	**Tiow:** The time value in this field will be added/subtracted to the Tiow timing parameter as defined in SMB 2.0 spec. See Thigh field above **Power Well:** SUS
15:12	0x0 RW	**Thdsta:** The time value in this field will be added/subtracted to the Thdsta timing parameter as defined in SMB 2.0 spec. • 1111: -7 Clocks (-700ns) • 1110: -6 Clocks (-600ns) • ---- • x000: +0 Clock (0ns) • 0001: +1 Clock (+100ns) • ---- • 0111: +7 Clocks (+700ns) **Power Well:** SUS
11:8	0x0 RW	**Tsusta:** The time value in this field will be added/subtracted to the Tsusta timing parameter as defined in SMB 2.0 spec. See Thdsta field above. **Power Well:** SUS
7:4	0x0 RW	**Tbuf:** The time value in this field will be added/subtracted to the Tbuf timing parameter as defined in SMB 2.0 spec. See Thdsta field above. **Power Well:** SUS
3:0	0x0 RW	**Tsusto:** The time value in this field will be added/subtracted to the Tsusto timing parameter as defined in SMB 2.0 spec. See Thdsta field above. **Power Well:** SUS

59.2.20 Manufacturer's ID (MANID)—Offset F8h

This reflects the value of the Manufacturers ID which provides information on the details of the chip revision.

Note: A single Manufacturers ID is implemented based on information in the Fuse block and distributed to the devices via a message.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:4] + F8h

Default: 01000F1Ch

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
27:24	0x1 RO/V	**Dot Portion of Process ID (DPID):** Indicates the dot process as x.8. **Power Well:** Core
23:16	0x0 RO/V	**Stepping ID (SID):** This field is incremented for each stepping of the part. ***Note:*** This field can be used by software to differentiate steppings when the Revision ID may not change. **Power Well:** Core
15:8	0xf RO/V	**Manufacturer (MaFa):** 0Fh = Intel. **Power Well:** Core
7:0	0x1C RO/V	**Process/Dot (PD):** Indicates that the process base is 1271. **Power Well:** Core

59.3 Registers in Memory Space—SMBMBAR

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) SMBMBAR.

59.3.1 Host Status Register Address (HSTS)—Offset 0h

All status bits are set by hardware and cleared by the software writing a one to the particular bit position. Writing a zero to any bit position has no affect.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 0h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1C	**BYTE_DONE_STS (BDS):** This bit will be set to 1 when the host controller has received a byte (for Block Read commands) or if it has completed transmission of a byte (for Block Write commands) when the 32-byte buffer is not being used. **Power Well:** Core
6	0x0 RW/1C	**In Use Status (IUS):** After a full PCI reset, a read to this bit returns a 0. After the first read, subsequent reads will return a 1. A write of a 1 to this bit will reset the next read value to 0. Writing a 0 to this bit has no effect. **Power Well:** Core
5	0x0 RW/1C	**SMBALERT_STS (SMSTS):** SoC sets this bit to a 1 to indicates source of the interrupt or SMI# was the SMBAlert# signal. Software resets this bit by writing a 1 to this location. This bit should also be cleared by RSMRST# (but not PLTRST#). **Power Well:** Core
4	0x0 RW/1C	**Failed (FAIL):** When set, this indicates that the source of the interrupt or SMI# was a failed bus transaction. This is set in response to the KILL bit being set to terminate the host transaction. **Power Well:** Core
3	0x0 RW/1C	**Bus Error (BERR):** When set, this indicates the source of the interrupt or SMI# was a transaction collision. **Power Well:** Core
2	0x0 RW/1C	**Device Error (DERR):** When set, this indicates that the source of the interrupt or SMI# was due one of the following: • Illegal Command Field Unclaimed Cycle (host initiated) • Host Device Time-out Error. CRC Error **Power Well:** Core
1	0x0 RW/1C	**Interrupt (INTR):** When set, this indicates that the source of the interrupt or SMI# was the successful completion of its last command. **Power Well:** Core
0	0x0 RW/1C	**Host Busy (HBSY):** A 1 indicates that the SMBus Host is running a command from the host interface. No SMB registers should be accessed while this bit is set. **Power Well:** Core

59.3.2 Host Control Register (HCTL)—Offset 2h

Note: A read to this register will clear the pointer in the 32-byte buffer.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 2h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**PEC_EN:** When set to 1, this bit causes the host controller to perform the SMBus transaction with the Packet Error Checking phase appended. For writes, the value of the PEC byte is transferred from the PEC Register. For reads, the PEC byte is loaded in to the PEC Register. **Power Well:** Core
6	0x0 RW	**START:** This write-only bit is used to initiate the command described in the SMB_CMD field. All registers should be setup prior to writing a 1 to this bit position. This bit always reads zero. **Power Well:** Core
5	0x0 RW	**LAST_BYTE:** Used for I2C Read commands as an indication that the next byte will be the last one to be received for that block. **Power Well:** Core
4:2	0x0 RW	**SMB_CMD:** As shown by the bit encoding below, indicates which command the SMBus Host is to perform. If enabled, the SMBus Host will generate an interrupt or SMI# when the command has completed If the value is for a non-supported or reserved command, the SMBus Host will set the device error (DEV_ERR) status bit and generate an interrupt when the START bit is set. The SMBus Controller will perform no command, and will not operate until DEV_ERR is cleared. Val - Command Description: • 000 - Quick: The slave address and read/write value (bit 0) are stored in the tx slave address register. • 001 - Byte: This command uses the transmit slave address and command registers. Bit 0 of the slave address register determines if this is a read or write command. • 010 - Byte Data: This command uses the transmit slave address, command, and DATA0 registers. Bit 0 of the slave address register determines if this is a read or write command. If it is a read, the DATA0 register will contain the read data. • 011 - Word Data: This command uses the transmit slave address, command, DATA0 and DATA1 registers. Bit 0 of the slave address register determines if this is a read or write command. If it is a read, after the command completes the DATA0 and DATA1 registers will contain the read data. • 100 - Process Call: This command uses the transmit slave address, command, DATA0 and DATA1 registers. Bit 0 of the slave address register determines if this is a read or write command. After the command completes, the DATA0 and DATA1 registers will contain the read data. • 101 - Block: This command uses the transmit slave address, command, and DATA0 registers, and the Block Data Byte register. For block write, the count is stored in the DATA0 register and indicates how many bytes of data will be transferred. For block reads, the count is received and stored in the DATA0 register. Bit 0 of the slave address register selects if this is a read or write command. For writes, data is retrieved from the first n (where n is equal to the specified count) addresses of the SRAM array. For reads, the data is stored in the Block Data Byte register. • 110 - I2C Read: This command uses the transmit slave address, command, DATA0, DATA1 registers, and the Block Data Byte register. The read data is stored in the Block Data Byte register. The SoC will continue reading data until the NAK is received. • 111 - Block-Process: This command uses the transmit slave address, command, DATA0 and the Block Data Byte register. For block write, the count is stored in the DATA0 register and indicates how many bytes of data will be transferred. For block read, the count is received and stored in the DATA0 register. Bit 0 of the slave address register always indicate a write command. For writes, data is retrieved from the first m (where m is equal to the specified count) addresses of the SRAM array. For reads, the data is stored in the Block Data Byte register. ***Note:*** E32B bit in the Auxiliary Control Register must be set for this command to work. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW	**KILL:** When set, kills the current host transaction taking place, sets the FAILED status bit, and asserts the interrupt (or SMI#) selected by the SMB_INTRSEL field. This bit, once set, must be cleared to allow the SMB Host Controller to function normally. **Power Well:** Core
0	0x0 RW	**INTREN:** Enable the generation of an interrupt or SMI# upon the completion of the command. **Power Well:** Core

59.3.3 Host Command Register (HCMD)—Offset 3h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 3h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Host Command Register (HCMD):** This eight bit field is transmitted by the host controller in the command field of the SMB protocol during the execution of any command. **Power Well:** Core

59.3.4 Transmit Slave Address Register (TSA)—Offset 4h

This register is transmitted by the host controller in the slave address field of the SMB protocol. This is the address of the target.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 4h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RW	**ADDRESS (ADDR):** 7-bit address of the targeted slave. ***Note:*** Writes to TSA values of A0h - AEh are blocked depending on the setting of the SPD write disable bit in HCFG - HostConfiguration. **Power Well:** Core
0	0x0 RW	**RW:** Direction of the host transfer. • 1 = Read. • 0 = Write. **Power Well:** Core

59.3.5 Data 0 Register (HD0)—Offset 5h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 5h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**DATA0/COUNT (DATA0_COUNT):** This field contains the eight bit data sent in the DATA0 field of the SMB protocol. For block write commands, this register reflects the number of bytes to transfer. This register should be programmed to a value between 1 and 32 for block counts. A count of 0 or a count above 32 will result in unpredictable behavior. The host controller does not check or log illegal block counts. **Power Well:** Core

59.3.6 Data 1 Register (HD1)—Offset 6h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 6h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**DATA1:** This eight bit register is transmitted in the DATA1 field of the SMB protocol during the execution of any command. **Power Well:** Core

59.3.7 Host Block Data (HBD)—Offset 7h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 7h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Block Data (BDTA):** This is either a register, or a pointer into a 32- byte block array, depending upon whether the E32B bit is set in the Auxiliary Control register. When the E32B bit is cleared, this is a register containing a byte of data to be sent on a block write or read from on a block read, just as it behaved on the SoC. When the E32B bit is set, reads and writes to this register are used to access the 32-byte block data storage array. An internal index pointer is used to address the array, which is reset to 0 by reading the HCTL register (offset 02h). The index pointer then increments automatically upon each access to this register. The transfer of block data into (read) or out of (write) this storage array during an SMBus transaction always starts at index address 0. When the E2B bit is set, for writes, software will write up to 32-bytes to this register as part of the setup for the command. After the Host Controller has sent the Address, Command, and Byte Count fields, it will send the bytes in the SRAM pointed to by this register. When the E2B bit is cleared for writes, software will place a single byte in this register. After the host controller has sent the address, command, and byte count fields, it will send the byte in this register. If there is more data to send, software will write the next series of bytes to the SRAM pointed to by this register and clear the DONE_STS bit. The controller will then send the next byte. During the time between the last byte being transmitted to the next byte being transmitted, the controller will insert wait-states on the interface. When the E2B bit is set for reads, after receiving the byte count into the Data0 register, the first series of data bytes go into the SRAM pointed to by this register. If the byte count has been exhausted or the 32-byte SRAM has been filled, the controller will generate an SMI# or interrupt (depending on configuration) and set the DONE_STS bit. Software will then read the data. During the time between when the last byte is read from the SRAM to when the DONE_STS bit is cleared, the controller will insert wait states on the interface. **Power Well:** Core

59.3.8 Packet Error Check Data Register (PEC)—Offset 8h

Note: This register may reside in either the core well or the suspend well.

To simplify the implementation, this register will be in the suspend well with the suspend well version of PCI reset (URST33B). This register contains the 8-bit CRC value that is used as the Packet Error Check on SMBus.

For writes, this register is written by software prior to running the command.

For reads, this register is read by software after the read command is completed on SMBus.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [SMBMBAR] + 8h

Default: 00h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**PEC_DATA:** This 8-bit register is written with the SMBus PEC data prior to a write transaction. For read transactions, the PEC data is loaded from the SMBus into this register and is then read by software. Software must ensure that the INUSE_STS bit is properly maintained to avoid having this field over-written by a write transaction following a read transaction. **Power Well:** Core

59.3.9 Receive Slave Address Register (RSA)—Offset 9h

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [SMBMBAR] + 9h

Default: 44h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
6:0	0x44 RW	**SLAVE_ADDR[6:0] (SA_6_0):** This field is the slave address that the SoC decodes for read and write cycles. The default is not 0 so that it can respond even before the CPU comes up (or if the CPU is dead). This register is reset by RSMRST#, but not by PLTRST#. **Power Well:** Resume

59.3.10 Slave Data Register (SD)—Offset Ah

Type: Memory Mapped I/O Register (Size: 16 bits)

Default: 0000h

BAR and Offset: [SMBMBAR] + Ah

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO/V	**SLAVE_DATA[15:0] (SD_15_0):** This field is the 16-bit data value written by the external SMBus master. The CPU can then read the value from this register. This register is reset by RSMRST#, but not by PLTRST#. • SLAVE_DATA [15:8] corresponds to the Data Message Byte 1 at Slave Write Register 5 in the table. • SLAVE_DATA [7:0] corresponds to the Data Message Byte 0 at Slave Write Register 4 in the table. **Power Well:** Resume

59.3.11 Auxiliary Status (AUXS)—Offset Ch

All bits in this register are in the core well.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + Ch

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
4	0x0 RO/V	**SMT3EN:** Register value determines if SMT3 is enabled and connected on SMLink1. Disabled means the device is not connected to the pins. • 0: Disable. • 1: Enable. **Power Well:** Core
3	0x0 RO/V	**SMT2EN:** Register value determines if SMT2 is enabled and connected on SMLink0. Disabled means the device is not connected to the pins. • 0: Disable. • 1: Enable. **Power Well:** Core
2	0x0 RO/V	**SMT1EN:** Register value determines if SMT1 is enabled and connected on SMBus. Disabled means the device is not connected to the pins. • 0: Disables. • 1: Enable. **Power Well:** Core
1	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
0	0x0 RW/1C	**CRC Error (CRCE):** This bit is set if a received message contained a CRC error. When this bit is set, the DERR bit of the host status register will also be set. This bit will be set by the controller if a software abort occurs in the middle of the CRC portion of the cycle or an abort happens after the SMBus Controller has received the final data bit transmitted by the external slave. **Power Well:** Core

59.3.12 Auxiliary Control (AUXC)—Offset Dh

All bits in this register are in the resume well.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + Dh

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:2	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
1	0x0 RW	**Enable 32-byte Buffer (E32B):** When set, the Host Block Data register is a pointer into a 32-byte buffer, as opposed to a single register. This enables the block commands to transfer or receive up to 32-bytes before the controller generates an interrupt. **Power Well:** Resume
0	0x0 RW	**Automatically Append CRC (AAC):** When set, the SMBus Controller will automatically append the CRC. This bit must not be changed during SM Bus transactions, or undetermined behavior will result. It should be programmed only once during the lifetime of the function. **Power Well:** Resume

59.3.13 SMLINK_PIN_CTL Register (SMLC)—Offset Eh

Note: This register is in the resume well and is reset by RSMRST#.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [SMBMBAR] + Eh

Default: 04h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
2	0x1 RW	**SMLINK_CLK_CTL:** • 0 = SMBus Controller will drive the SMLINK[0] pin low, independent of what the other SMLINK logic would otherwise indicate for the SMLINK(0) pin. • 1 = The SMLINK[0] pin is Not overdriven low. The other SMLINK logic controls the state of the pin. **Power Well:** Resume
1	0x0 RO/V	**SMLINK[1]_CUR_STS (SMLINK1_CUR_STS):** This bit has a default value that is dependent on an external signal level. This returns the value on the SMLINK[1] pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Resume
0	0x0 RO/V	**SMLINK[0]_CUR_STS (SMLINK0_CUR_STS):** This bit has a default value that is dependent on an external signal level. This returns the value on the SMLINK[0] pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Core

59.3.14 SMBUS_PIN_CTL Register (SMBC)—Offset Fh

Note: This register is in the resume well and is reset by RSMRST#.

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 04h

BAR and Offset: [SMBMBAR] + Fh

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
2	0x1 RW	**SMBCLK_CTL:** • 0 = SMBus Controller will drive the SMBCLK pin low, independent of what the other SMB logic would otherwise indicate for the SMBCLK pin. • 1 = The SMBCLK pin is Not overdriven low. The other SMBus logic controls the state of the pin. **Power Well:** Resume
1	0x0 RO/V	**SMBDATA_CUR_STS:** This bit has a default value that is dependent on an external signal level. This returns the value on the SMBDATA pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Resume
0	0x0 RO/V	**SMBCLK_CUR_STS:** This bit has a default value that is dependent on an external signal level. This returns the value on the SMBCLK pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Resume

59.3.15 Slave Status Register (SSTS)—Offset 10h

All bits in this register are implemented in the 64 kHz clock domain. Therefore, software must poll the register until a write takes effect before assuming that a write has completed internally.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [SMBMBAR] + 10h

Default: 00h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
0	0x0 RW/1C	**HOST_NOTIFY_STS (HNS):** The SMBus Controller sets this bit to a 1 when it has completely received a successful Host Notify Command on the SMBus pins. Software reads this bit to determine that the source of the interrupt or SMI# was the reception of the Host Notify Command. Software clears this bit after reading any information needed from the Notify address and data registers by writing a 1 to this bit. ***Note:*** The controller will allow the Notify Address and Data registers to be over-written once this bit has been cleared. When this bit is 1, the SMBus Controller will NACK the first byte (host address) of any new Host Notify commands on the SMBus. Writing a 0 to this bit has no effect. **Power Well:** Resume

59.3.16 Slave Command Register (SCMD)—Offset 11h

All bits in this register are implemented in the 64 kHz clock domain. Therefore, software must poll the register until a write takes effect before assuming that a write has completed internally. Also, software must confirm the prior written value before writing to the register again.

Type: Memory Mapped I/O Register (Size: 8 bits)

BAR and Offset: [SMBMBAR] + 11h

Default: 00h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
2	0x0 RW	**SMBALERT_DIS (SMB_D):** Software sets this bit to 1 to block the generation of the interrupt or SMI# due to the SMBALERT# source. This bit is logically inverted and ANDed with the SMBALERT_STS bit. The resulting signal is distributed to the SMI# and/or interrupt generation logic. This bit does not effect the wake logic. **Power Well:** Resume
1	0x0 RW	**HOST_NOTIFY_WKEN (HNW):** Software sets this bit to 1 to enable the reception of a Host Notify command as a wake event. When enabled this event is ORed in with the other SMBus wake events and is reflected in the SMB_WAK_STS bit of the General Purpose Event 0 Status register. **Power Well:** Resume
0	0x0 RW	**HOST_NOTIFY_INTREN (HNI):** Software sets this bit to 1 to enable the generation of interrupt or SMI# when HOST_NOTIFY_STS is 1. This enable does not affect the setting of the HOST_NOTIFY_STS bit. When the interrupt is generated, either PIRQB or SMI# is generated, depending on the value of the SMB_SMI_EN bit (D31, F3, Off40h, B1). If the HOST_NOTIFY_STS bit is set when this bit is written to a 1, then the interrupt (or SMI#) will be generated. The interrupt (or SMI#) is logically generated by ANDing the STS and INTREN bits. **Power Well:** Resume

59.3.17 Notify Device Address Register (NDA)—Offset 14h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 14h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RO/V	**DEVICE_ADDRESS (Dev_Addr):** This field contains the 7-bit device address received during the Host Notify protocol of the SMBus 2.0 specification. Software should only consider this field valid when the HOST_NOTIFY_STS bit is set to 1. **Power Well:** Resume
0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume

59.3.18 Notify Data Low Byte Register (NDLB)—Offset 16h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 16h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**DATA_LOW_BYTE (DLB):** This field contains the first (low) byte of data received during the Host Notify protocol of the SMBus 2.0 specification. Software should only consider this field valid when the HOST_NOTIFY_STS bit is set to 1. **Power Well:** Resume

59.3.19 Notify Data High Byte Register (NDHB)—Offset 17h

Type: Memory Mapped I/O Register (Size: 8 bits)

Default: 00h

BAR and Offset: [SMBMBAR] + 17h

SMBMBAR Type: PCI Configuration Register (Size: 64 bits)
SMBMBAR Reference: [B:0, D:31, F:4] + 10h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**DATA_HIGH_BYTE (DHB):** This field contains the second (high) byte of data received during the Host Notify protocol of the SMBus 2.0 specification. Software should only consider this field valid when the HOST_NOTIFY_STS bit is set to 1. **Power Well:** Resume

59.4 Registers in I/O Space—SBA

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) SBA.

59.4.1 Host Status Register Address (HSTS)—Offset 0h

All status bits are set by hardware and cleared by the software writing a one to the particular bit position. Writing a zero to any bit position has no affect.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 0h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1C	**BYTE_DONE_STS (BDS):** This bit will be set to 1 when the host controller has received a byte (for Block Read commands) or if it has completed transmission of a byte (for Block Write commands) when the 32-byte buffer is not being used. **Power Well:** Core
6	0x0 RW/1C	**In Use Status (IUS):** After a full PCI reset, a read to this bit returns a 0. After the first read, subsequent reads will return a 1. A write of a 1 to this bit will reset the next read value to 0. Writing a 0 to this bit has no effect. **Power Well:** Core
5	0x0 RW/1C	**SMBALERT_STS (SMSTS):** The SoC sets this bit to a 1 to indicates source of the interrupt or SMI# was the SMBAlert# signal. Software resets this bit by writing a 1 to this location. This bit should also be cleared by RSMRST# (but not PLTRST#). **Power Well:** Core
4	0x0 RW/1C	**Failed (FAIL):** When set, this indicates that the source of the interrupt or SMI# was a failed bus transaction. This is set in response to the KILL bit being set to terminate the host transaction. **Power Well:** Core
3	0x0 RW/1C	**Bus Error (BERR):** When set, this indicates the source of the interrupt or SMI# was a transaction collision. **Power Well:** Core
2	0x0 RW/1C	**Device Error (DERR):** When set, this indicates that the source of the interrupt or SMI# was due one of the following: • Illegal Command Field Unclaimed Cycle (host initiated) • Host Device Time-out Error. CRC Error **Power Well:** Core
1	0x0 RW/1C	**Interrupt (INTR):** When set, this indicates that the source of the interrupt or SMI# was the successful completion of its last command. **Power Well:** Core
0	0x0 RW/1C	**Host Busy (HBSY):** A 1 indicates that the SMBus Host is running a command from the host interface. No SMB registers should be accessed while this bit is set. **Power Well:** Core

59.4.2 Host Control Register (HCTL)—Offset 2h

Note: A read to this register will clear the pointer in the 32-byte buffer.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 2h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**PEC_EN:** When set to 1, this bit causes the host controller to perform the SMBus transaction with the Packet Error Checking phase appended. For writes, the value of the PEC byte is transferred from the PEC Register. For reads, the PEC byte is loaded in to the PEC Register. When this bit is cleared to 0, the SMBus host controller does not perform the transaction with the PEC phase appended. This bit must be written prior to the write in which the START bit is set. **Power Well:** Core
6	0x0 RW	**START:** This write-only bit is used to initiate the command described in the SMB_CMD field. All registers should be setup prior to writing a 1 to this bit position. This bit always reads zero. The HOST_BUSY bit in the Host Status register (offset 00h) can be used to identify when the SMBus Controller has finished the command. **Power Well:** Core
5	0x0 RW	**LAST_BYTE:** Used for I2C Read commands as an indication that the next byte will be the last one to be received for that block. The algorithm and usage model for this bit will be as follows (assume a message of n bytes): • A. When the software sees the BYTE_DONE_STS bit set (bit 7 in the SMBus Host Status Register) for each of bytes 1 through n-2 of the message, the software should then read the Block Data Byte Register to get the byte that was just received. • B. After reading each of bytes 1 to n-2 of the message, the software will then clear the BYTE_DONE_STS bit. • C. After receiving byte n-1 of the message, the software will then set the LAST BYTE bit. The software will then clear the BYTE_DONE_STS bit. • D. The SoC will then receive the last byte of the message (byte n). However, the controller state machine will see the LAST BYTE bit set, and instead of sending an ACK after receiving the last byte, it will instead send a NAK. • E. After receiving the last byte (byte n), the software will still clear the BYTE_DONE_STS bit. However, the LAST_BYTE bit will be irrelevant at that point. ***Note:*** This bit may be set when the TCO timer causes the SECOND_TO_STS bit to be set. See the TCO2_STS Register in Volume 1, bit 1 for more details on that bit. The SMBus device driver should clear the LAST_BYTE bit (if it is set) before starting any new command. ***Note:*** In addition to I2C Read Commands, the LAST_BYTE bit will also cause Block Read/Write cycles to stop prematurely (at the end of the next byte). **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
4:2	0x0 RW	**SMB_CMD:** As shown by the bit encoding below, indicates which command the SMBus Host is to perform. If enabled, the SoC will generate an interrupt or SMI# when the command has completed If the value is for a non-supported or reserved command, the SoC will set the device error (DEV_ERR) status bit and generate an interrupt when the START bit is set. The controller will perform no command, and will not operate until DEV_ERR is cleared. Val - Command Description: • 000 - Quick: The slave address and read/write value (bit 0) are stored in the tx slave address register. • 001 - Byte: This command uses the transmit slave address and command registers. Bit 0 of the slave address register determines if this is a read or write command. • 010 - Byte Data: This command uses the transmit slave address, command, and DATA0 registers. Bit 0 of the slave address register determines if this is a read or write command. If it is a read, the DATA0 register will contain the read data. • 011 - Word Data: This command uses the transmit slave address, command, DATA0 and DATA1 registers. Bit 0 of the slave address register determines if this is a read or write command. If it is a read, after the command completes the DATA0 and DATA1 registers will contain the read data. • 100 - Process Call: This command uses the transmit slave address, command, DATA0 and DATA1 registers. Bit 0 of the slave address register determines if this is a read or write command. After the command completes, the DATA0 and DATA1 registers will contain the read data. • 101 - Block: This command uses the transmit slave address, command, and DATA0 registers, and the Block Data Byte register. For block write, the count is stored in the DATA0 register and indicates how many bytes of data will be transferred. For block reads, the count is received and stored in the DATA0 register. Bit 0 of the slave address register selects if this is a read or write command. For writes, data is retrieved from the first n (where n is equal to the specified count) addresses of the SRAM array. For reads, the data is stored in the Block Data Byte register. • 110 - I2C Read: This command uses the transmit slave address, command, DATA0, DATA1 registers, and the Block Data Byte register. The read data is stored in the Block Data Byte register. The SMBus Controller will continue reading data until the NAK is received. • 111 - Block-Process: This command uses the transmit slave address, command, DATA0 and the Block Data Byte register. For block write, the count is stored in the DATA0 register and indicates how many bytes of data will be transferred. For block read, the count is received and stored in the DATA0 register. Bit 0 of the slave address register always indicate a write command. For writes, data is retrieved from the first m (where m is equal to the specified count) addresses of the SRAM array. For reads, the data is stored in the Block Data Byte register. ***Note:*** E32B bit in the Auxiliary Control Register must be set for this command to work. **Power Well:** Core
1	0x0 RW	**KILL:** When set, kills the current host transaction taking place, sets the FAILED status bit, and asserts the interrupt (or SMI#) selected by the SMB_INTRSEL field. This bit, once set, must be cleared to allow the SMB Host Controller to function normally. **Power Well:** Core
0	0x0 RW	**INTREN:** Enable the generation of an interrupt or SMI# upon the completion of the command. **Power Well:** Core

59.4.3 Host Command Register (HCMD)—Offset 3h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 3h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Host Command Register (HCMD):** This eight bit field is transmitted by the host controller in the command field of the SMB protocol during the execution of any command. **Power Well:** Core

59.4.4 Transmit Slave Address Register (TSA)—Offset 4h

This register is transmitted by the host controller in the slave address field of the SMB protocol. This is the address of the target.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 4h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RW	**ADDRESS (ADDR):** 7-bit address of the targeted slave. ***Note:*** Writes to TSA values of A0h - AEh are blocked depending on the setting of the SPD write disable bit in HCFG - HostConfiguration. **Power Well:** Core
0	0x0 RW	**RW:** Direction of the host transfer. • 1 = Read. • 0 = Write. **Power Well:** Core

59.4.5 Data 0 Register (HD0)—Offset 5h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 5h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**DATA0/COUNT (DATA0_COUNT):** This field contains the eight bit data sent in the DATA0 field of the SMB protocol. For block write commands, this register reflects the number of bytes to transfer. This register should be programmed to a value between 1 and 32 for block counts. A count of 0 or a count above 32 will result in unpredictable behavior. The host controller does not check or log illegal block counts. **Power Well:** Core

59.4.6 Data 1 Register (HD1)—Offset 6h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 6h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**DATA1:** This eight bit register is transmitted in the DATA1 field of the SMB protocol during the execution of any command. **Power Well:** Core

59.4.7 Host Block Data (HBD)—Offset 7h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 7h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Block Data (BDTA):** This is either a register, or a pointer into a 32- byte block array, depending upon whether the E32B bit is set in the Auxiliary Control register. When the E32B bit is cleared, this is a register containing a byte of data to be sent on a block write or read from on a block read, just as it behaved on the SoC. When the E32B bit is set, reads and writes to this register are used to access the 32-byte block data storage array. An internal index pointer is used to address the array, which is reset to 0 by reading the HCTL register (offset 02h). The index pointer then increments automatically upon each access to this register. The transfer of block data into (read) or out of (write) this storage array during an SMBus transaction always starts at index address 0. When the E2B bit is set, for writes, software will write up to 32-bytes to this register as part of the setup for the command. After the Host Controller has sent the Address, Command, and Byte Count fields, it will send the bytes in the SRAM pointed to by this register. When the E2B bit is cleared for writes, software will place a single byte in this register. After the host controller has sent the address, command, and byte count fields, it will send the byte in this register. If there is more data to send, software will write the next series of bytes to the SRAM pointed to by this register and clear the DONE_STS bit. The controller will then send the next byte. During the time between the last byte being transmitted to the next byte being transmitted, the controller will insert wait-states on the interface. When the E2B bit is set for reads, after receiving the byte count into the Data0 register, the first series of data bytes go into the SRAM pointed to by this register. If the byte count has been exhausted or the 32-byte SRAM has been filled, the controller will generate an SMI# or interrupt (depending on configuration) and set the DONE_STS bit. Software will then read the data. During the time between when the last byte is read from the SRAM to when the DONE_STS bit is cleared, the controller will insert wait states on the interface. **Power Well:** Core

59.4.8 Packet Error Check Data Register (PEC)—Offset 8h

Note: This register may reside in either the core well or the suspend well.

To simplify the implementation, this register will be in the suspend well with the suspend well version of PCI reset (URST33B). This register contains the 8-bit CRC value that is used as the Packet Error Check on SMBus. For writes, this register is written by software prior to running the command. For reads, this register is read by software after the read command is completed on SMBus.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 8h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**PEC_DATA:** This 8-bit register is written with the SMBus PEC data prior to a write transaction. For read transactions, the PEC data is loaded from the SMBus into this register and is then read by software. Software must ensure that the INUSE_STS bit is properly maintained to avoid having this field over-written by a write transaction following a read transaction. **Power Well:** Core

59.4.9 Receive Slave Address Register (RSA)—Offset 9h

Type: I/O Register
(Size: 8 bits)

Default: 44h

BAR and Offset: [SBA] + 9h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
6:0	0x44 RW	**SLAVE_ADDR[6:0] (SA_6_0):** This field is the slave address that the SMBus Host decodes for read and write cycles. The default is not 0 so that it can respond even before the CPU comes up (or if the CPU is dead). This register is reset by RSMRST#, but not by PLTRST#. **Power Well:** Resume

59.4.10 Slave Data Register (SD)—Offset Ah

Type: I/O Register
(Size: 16 bits)

Default: 0000h

BAR and Offset: [SBA] + Ah

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
15:0	0x0 RO/V	**SLAVE_DATA[15:0] (SD_15_0):** This field is the 16-bit data value written by the external SMBus master. The CPU can then read the value from this register. This register is reset by RSMRST#, but not by PLTRST#. • SLAVE_DATA [15:8] corresponds to the Data Message Byte 1 at Slave Write Register 5 in the table. • SLAVE_DATA [7:0] corresponds to the Data Message Byte 0 at Slave Write Register 4 in the table. **Power Well:** Resume

59.4.11 Auxiliary Status (AUXS)—Offset Ch

All bits in this register are in the core well.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + Ch

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
4	0x0 RO/V	**SMT3EN:** Register value determines if SMT3 is enabled and connected on SMLink1. Disabled means the device is not connected to the pins. • 0: Disable. • 1: Enable. **Power Well:** Core
3	0x0 RO/V	**SMT2EN:** Register value determines if SMT2 is enabled and connected on SMLink0. Disabled means the device is not connected to the pins. • 0: Disable. • 1: Enable. **Power Well:** Core
2	0x0 RO/V	**SMT1EN:** Register value determines if SMT1 is enabled and connected on SMBus. Disabled means the device is not connected to the pins. • 0: Disables. • 1: Enable. **Power Well:** Core
1	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
0	0x0 RW/1C	**CRC Error (CRCE):** This bit is set if a received message contained a CRC error. When this bit is set, the DERR bit of the host status register will also be set. This bit will be set by the controller if a software abort occurs in the middle of the CRC portion of the cycle or an abort happens after SMBus Host has received the final data bit transmitted by external slave. **Power Well:** Core

59.4.12 Auxiliary Control (AUXC)—Offset Dh

All bits in this register are in the resume well.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + Dh

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:2	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
1	0x0 RW	**Enable 32-byte Buffer (E32B):** When set, the Host Block Data register is a pointer into a 32-byte buffer, as opposed to a single register. This enables the block commands to transfer or receive up to 32-bytes before the SoC generates an interrupt. **Power Well:** Resume
0	0x0 RW	**Automatically Append CRC (AAC):** When set, the SoC will automatically append the CRC. This bit must not be changed during SM Bus transactions, or undetermined behavior will result. It should be programmed only once during the lifetime of the function. **Power Well:** Resume

59.4.13 SMLINK_PIN_CTL Register (SMLC)—Offset Eh

Note: This register is in the resume well and is reset by RSMRST#.

Type: I/O Register
(Size: 8 bits)

Default: 04h

BAR and Offset: [SBA] + Eh

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
2	0x1 RW	**SMLINK_CLK_CTL:** • 0 = SMBus Controller will drive the SMLINK[0] pin low, independent of what the other SMLINK logic would otherwise indicate for the SMLINK(0) pin. • 1 = The SMLINK[0] pin is Not overdriven low. The other SMLINK logic controls the state of the pin. **Power Well:** Resume
1	0x0 RO/V	**SMLINK[1]_CUR_STS (SMLINK1_CUR_STS):** This bit has a default value that is dependent on an external signal level. This returns the value on the SMLINK[1] pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Resume
0	0x0 RO/V	**SMLINK[0]_CUR_STS (SMLINK0_CUR_STS):** This bit has a default value that is dependent on an external signal level. This returns the value on the SMLINK[0] pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Core

59.4.14 SMBUS_PIN_CTL Register (SMBC)—Offset Fh

Note: This register is in the resume well and is reset by RSMRST#.

Type: I/O Register
(Size: 8 bits)

Default: 04h

BAR and Offset: [SBA] + Fh

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
2	0x1 RW	**SMBCLK_CTL:** • 0 = SMBus Controller will drive the SMBCLK pin low, independent of what the other SMB logic would otherwise indicate for the SMBCLK pin. • 1 = The SMBCLK pin is Not overdriven low. The other SMBus logic controls the state of the pin. **Power Well:** Resume
1	0x0 RO/V	**SMBDATA_CUR_STS:** This bit has a default value that is dependent on an external signal level. This returns the value on the SMBDATA pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Resume
0	0x0 RO/V	**SMBCLK_CUR_STS:** This bit has a default value that is dependent on an external signal level. This returns the value on the SMBCLK pin. It will be 1 to indicate high, 0 to indicate low. This allows software to read the current state of the pin. **Power Well:** Resume

59.4.15 Slave Status Register (SSTS)—Offset 10h

All bits in this register are implemented in the 64 kHz clock domain. Therefore, software must poll the register until a write takes effect before assuming that a write has completed internally.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 10h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
0	0x0 RW/1C	**HOST_NOTIFY_STS (HNS):** The SMBus Controller sets this bit to a 1 when it has completely received a successful Host Notify Command on the SMBus pins. Software reads this bit to determine that the source of the interrupt or SMI# was the reception of the Host Notify Command. Software clears this bit after reading any information needed from the Notify address and data registers by writing a 1 to this bit. ***Note:*** The SMBus Controller will allow the Notify Address and Data registers to be over-written once this bit has been cleared. When this bit is 1, the SMBus Controller will NACK the first byte (host address) of any new Host Notify commands on the SMBus. Writing a 0 to this bit has no effect. **Power Well:** Resume

59.4.16 Slave Command Register (SCMD)—Offset 11h

All bits in this register are implemented in the 64 kHz clock domain. Therefore, software must poll the register until a write takes effect before assuming that a write has completed internally. Also, software must confirm the prior written value before writing to the register again.

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 11h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
2	0x0 RW	**SMBALERT_DIS (SMB_D):** Software sets this bit to 1 to block the generation of the interrupt or SMI# due to the SMBALERT# source. This bit is logically inverted and ANDed with the SMBALERT_STS bit. The resulting signal is distributed to the SMI# and/or interrupt generation logic. This bit does not effect the wake logic. **Power Well:** Resume
1	0x0 RW	**HOST_NOTIFY_WKEN (HNW):** Software sets this bit to 1 to enable the reception of a Host Notify command as a wake event. When enabled this event is ORed in with the other SMBus wake events and is reflected in the SMB_WAK_STS bit of the General Purpose Event 0 Status register. **Power Well:** Resume
0	0x0 RW	**HOST_NOTIFY_INTREN (HNI):** Software sets this bit to 1 to enable the generation of interrupt or SMI# when HOST_NOTIFY_STS is 1. This enable does not affect the setting of the HOST_NOTIFY_STS bit. When the interrupt is generated, either PIRQB or SMI# is generated, depending on the value of the SMB_SMI_EN bit (D31, F3, Off40h, B1). If the HOST_NOTIFY_STS bit is set when this bit is written to a 1, then the interrupt (or SMI#) will be generated. The interrupt (or SMI#) is logically generated by ANDing the STS and INTREN bits. **Power Well:** Resume

59.4.17 Notify Device Address Register (NDA)—Offset 14h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 14h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:1	0x0 RO/V	**DEVICE_ADDRESS (Dev_Addr):** This field contains the 7-bit device address received during the Host Notify protocol of the SMBus 2.0 specification. Software should only consider this field valid when the HOST_NOTIFY_STS bit is set to 1. **Power Well:** Resume
0	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume

59.4.18 Notify Data Low Byte Register (NDLB)—Offset 16h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 16h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**DATA_LOW_BYTE (DLB):** This field contains the first (low) byte of data received during the Host Notify protocol of the SMBus 2.0 specification. Software should only consider this field valid when the HOST_NOTIFY_STS bit is set to 1. **Power Well:** Resume

59.4.19 Notify Data High Byte Register (NDHB)—Offset 17h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [SBA] + 17h

SBA Type: PCI Configuration Register (Size: 32 bits)
SBA Reference: [B:0, D:31, F:4] + 20h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RO	**DATA_HIGH_BYTE (DHB):** This field contains the second (high) byte of data received during the Host Notify protocol of the SMBus 2.0 specification. Software should only consider this field valid when the HOST_NOTIFY_STS bit is set to 1. **Power Well:** Resume

59.5 Registers in I/O Space—TCOBASE

These registers are accessed in Host I/O Space starting at the relocatable I/O address defined by the Base Address Register (BAR) TCOBASE described in Section 59.2.17, "TCO Base Address (TCOBASE)—Offset 50h" on page 2763.

59.5.1 TCO_RLD Register (TRLD)—Offset 0h

Type: I/O Register
(Size: 16 bits)

Default: 0004h

BAR and Offset: [TCOBASE] + 0h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
15:10	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
9:0	0x4 RW	**TCORLD:** Reading this register will return the current count of the TCO timer. Writing any value to this register will reload the timer to prevent the timeout. **Power Well:** Core

59.5.2 TCO_DAT_IN Register (TDI)—Offset 2h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [TCOBASE] + 2h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**TCO_DAT_IN (TDI):** Data Register for passing commands from the OS to the SMI handler. Writes to this register will cause an SMI and set the OS_TCO_SMI bit in the TCO_STS register. **Power Well:** Core

59.5.3 TCO_DAT_OUT Register (TDO)—Offset 3h

Type: I/O Register
(Size: 8 bits)

Default: 00h

BAR and Offset: [TCOBASE] + 3h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**TCO_DAT_OUT (TDO):** Data Register for passing commands from the SMI handler to the OS. Writes to this register will set the TCO_INT_STS bit in the TCO_STS register. It also causes an interrupt, as selected by the TCO_IRQ_SEL bits. **Power Well:** Core

59.5.4 TCO1_STS Register (TSTS1)—Offset 4h

Unless otherwise indicated, these bits are sticky and are cleared by writing a 1 to the corresponding bit position.

Type: I/O Register
(Size: 16 bits)

Default: 0000h

BAR and Offset: [TCOBASE] + 4h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
15:14	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
13	0x0 RO	**TCO Slave Select (TCO_SLVSEL):** This register bit indicates the value of TCO Slave Select Soft Strap. Refer to the Section 19, "Serial Peripheral Interface (SPI)" on page 592 for details. **Power Well:** Core
12	0x0 RW/1C	**CPUSERR_STS:** Reserved **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
10	0x0 RW/1C	**CPUSMI_STS:** Reserved **Power Well:** Core
9	0x0 RW/1C	**CPUSCI_STS:** Reserved **Power Well:** Core
8	0x0 RW/1C	**BIOSWR_STS:** The SoC sets this bit to 1 and generates and SMI# to indicate an illegal attempt to write to the BIOS. (The BIOS write could be either to FirmwareHUB (FWH) or SPI Flash). This occurs when either: • a) The WP bit (10.1.7.4 bit 0) is changed from 0 to 1 and the LE bit (10.1.7.4 bit 1) is also set. • b) Any write is attempted to the BIOS and the WP bit is also set. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1C	**NEWCENTURY_STS:** This bit will be set when the year rolls over from 1999 to 2000. If the bit is already 1, it will remain 1. This bit can be cleared either by software writing a 1 back to the bit position, or by RTEST# going active. When this bit is set, an SMI# will be generated. However, this will not be a wake event. ***Note:*** This bit 7 is not valid when the RTC battery is first put in (or if the RTC battery does not provide sufficient power when the system is unplugged). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD_2):** Reserved. **Power Well:** Core
3	0x0 RW/1C	**TIMEOUT:** Bit set to 1 by the SoC to indicate that the SMI was caused by TCO timer reaching 0. ***Note:*** The SMI handler should clear this bit to prevent an immediate re-entry to the SMI handler. **Power Well:** Core
2	0x0 RW/1C	**TCO_INT_STS:** Bit set to 1 when SMI handler caused the interrupt by writing to the TCO_DAT_OUT register. **Power Well:** Core
1	0x0 RW/1C	**OS_TCO_SMI:** Bit set to 1 when OS code caused an SMI# by writing to the TCO_DAT_IN register. **Power Well:** Core
0	0x0 RO/V	**NMI2SMI_STS:** This bit is set when an SMI# occurs because an event occurred that would otherwise have caused an NMI. **Power Well:** Core

59.5.5 TCO2_STS Register (TSTS2)—Offset 6h

Type: I/O Register
(Size: 16 bits)

Default: 0000h

BAR and Offset: [TCOBASE] + 6h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
15:5	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
4	0x0 RW/1C	**SMLINK_SLAVE_SMI_STS:** Reserved **Power Well:** Resume
3:2	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Resume
1	0x0 RW/1C	**SECOND_TO_STS:** The SoC sets this bit to 1 to indicate that the TIMEOUT bit had been (or is currently) set and a second timeout occurred before the TCO_RLD register was written. If this bit is set and the NO_REBOOT config bit is 0, then the SoC will reboot the system after the second timeout. The reboot is done by asserting PLTRST#. This bit is only cleared by writing a 1 to this bit or by a RSMRST#. **Power Well:** Resume
0	0x0 RW/1C	**INTRD_DET:** Intruder Detect. Bit set to 1 by the SoC to indicate that an intrusion was detected. This is latched. This bit is cleared by writing a 1 to this bit or by RTEST#. This bit is backed in the RTC Well. ***Note:*** If the INTRUDER# signal is active when the software attempts to clear the INTRD_DET bit, the bit will remain as a 1, and the SMI# will be generated again immediately. **Power Well:** Resume

59.5.6 TCO1_CNT Register (TCTL1)—Offset 8h

Type: I/O Register
(Size: 16 bits)

Default: 0000h

BAR and Offset: [TCOBASE] + 8h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
15:13	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
12	0x0 RW	**TCO_LOCK:** When set to 1, this bit prevents writes from changing the TCO_EN bit (in offset 30h of Power Management I/O space). Once this bit is set to 1, it can not be cleared by software writing a 0 to this bit location. A core-well reset is required to change this bit from 1 to 0. This bit defaults to 0. **Power Well:** Core
11	0x0 RW	**TCO_TMR_HALT:** 1 = The TCO timer will halt. It will not count, and thus cannot reach a value that would cause an SMI# or to cause the SECOND_TO_STS bit to be set. This will also prevent rebooting. • 0 = The TCO timer is enabled to count. This is the default. **Power Well:** Core
10	0x0 RW	**SEND_NOW:** Reserved. **Power Well:** Core
9	0x0 RW	**NMI2SMI_EN:** Setting this bit "1" forces all NMIs to instead cause an SMI#, and will be reported in the TCO1_STS register. This bit is set and the NMI_EN# bit is set to "0", the NMI# will be routed to cause an SMI#. No NMI# will be caused. However, if the GL_SMI_EN bit is not set, then no SMI# will be generated either. If this bit is set but the NMI_EN# bit is set to "1", then no NMI nor SMI# will be generated. The following shows the possible combination: • NMI_EN#, GBL_SMI_EN 00: No SMI# based on NMI events (since no EMI# at all because SMI_EN =0) • NMI_EN#, GBL_SMI_EN 01: SMI# will be caused based on NMI events • NMI_EN#, GBL_SMI_EN 10: No SMI# at all because SMI_EN is 0 • NMI_EN#, GBL_SMI_EN 11: No SMI# based on NMI events because NMI_EN#=1 **Power Well:** Core
8	0x0 RW	**NMI_NOW:** Writing a 1 to this bit causes an NMI. this allows the BIOS or SMI handler to force entry to the NMI handler. The NMI handler is expected to clear this bit. Another NMI will not be generated until the bit is cleared by writing a 1 back to the same bit position. **Power Well:** Core
7:0	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core

59.5.7 TCO2_CNT Register (TCTL2)—Offset Ah

Type: I/O Register
(Size: 16 bits)

Default: 0008h

BAR and Offset: [TCOBASE] + Ah

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
15:6	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Resume
5:4	0x0 RW	**OS_POLICY:** OS-based software writes to these bits to select the policy that the BIOS will use after the platform resets due the WDT. The following convention is recommended for the BIOS and OS: • 00 Boot normally. • 01 Shut down. • 10 Don’t load OS. Hold in pre-boot state and use LAN to determine next step. • 11 Reserved Implementation. ***Note:*** These are just scratch pad bits. They should not be reset when the TCO logic resets the platform due to Watchdog Timer. **Power Well:** Resume
3	0x1 RW	**SMB_ALERT_DISABLE:** Disables GP/SMBALERT# as an alert source for the heartbeats and the SMBus slave. At reset (RSMRST# pin assertion only), this bit is set and the muxed GP/SMBALERT# are disabled. **Power Well:** Resume
2:1	0x0 RW	**INTRD_SEL:** Selects the action to take if the INTRUDER# signal goes active. • 11 Reserved. • 01 Interrupt. For IRQ routing see Section 59.6.1, “TCO Configuration (TCOCFG)—Offset 0h” on page 2801. • 10 SMI#. • 00 INTRUDER# doesn't cause SMI# or interrupt. **Power Well:** Resume
0	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Resume

59.5.8 LEGACY_ELIM Register (LE)—Offset 10h

Type: I/O Register
(Size: 8 bits)

Default: 03h

BAR and Offset: [TCOBASE] + 10h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
7:2	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
1	0x1 RW	**IRQ12_CAUSE:** When software sets the bit to 1, IRQ12 will be high (asserted). When software sets the bit to 0, IRQ12 will be low (not asserted). Default for this bit is 1. **Power Well:** Core
0	0x1 RW	**IRQ1_CAUSE:** When software sets the bit to 1, IRQ1 will be high (asserted). When software sets the bit to 0, IRQ1 will be low (not asserted). Default for this bit is 1. **Power Well:** Core

59.5.9 TCO_TMR Register (TTMR)—Offset 12h

Type: I/O Register
(Size: 16 bits)

Default: 0004h

BAR and Offset: [TCOBASE] + 12h

TCOBASE Type: PCI Configuration Register (Size: 32 bits)
TCOBASE Reference: [B:0, D:31, F:4] + 50h

Bit Range	Default & Access	Field Name (ID): Description
15:10	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
9:0	0x4 RW	**TCOTMR:** Value that is loaded into the timer each time the TCO_RLD register is written. Values of 0000h or 0001h will be ignored and should not be attempted. The timer is clocked at approximately 0.6 seconds, and thus allows timeouts ranging from 1.2 second to 613.8 seconds. ***Note:*** The timer has an error of +/- 1 tick (0.6s). **Power Well:** Core

59.6 Sideband Registers—Host SMBus Private Configuration

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

59.6.1 TCO Configuration (TCOCFG)—Offset 0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCF] + 0h
Host Memory Space: SBREG_BAR + 0xCF0000 + 0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
7	0x0 RW	**TCO IRQ Enable (IE):** When set, TCO IRQ is enabled, as selected by the TCO_IRQ_SEL field. When cleared, TCO IRQ is disabled. **Power Well:** Core
6:3	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
2:0	0x0 RW	**TCO IRQ Select (IS):** Specifies on which IRQ the TCO will internally appear. If not using the APIC, the TCO interrupt must be routed to IRQ9-11, and that interrupt is not sharable with the SERIRQ stream, but is shareable with other PCI interrupts. If using the APIC, the TCO interrupt can also be mapped to IRQ20-23, and can be shared with other interrupts. Bits TCO Map • 000 IRQ9 (maps to 8259 and APIC). • 001 IRQ10 (maps to 8259 and APIC). • 010 IRQ11 (maps to 8259 and APIC). • 011 Reserved 100 IRQ20 (maps to APIC). • 101 IRQ21 (maps to APIC). • 110 IRQ22 (maps to APIC). • 111 IRQ23 (maps to APIC). If the TCO IRQ is programmed to be routed to both the 8259 and the APIC, only one of these interrupt controllers should be enabled to service the interrupt. When setting the these bits, the TCO IRQ Enable (IE) bit must be cleared to prevent glitching. When the interrupt is mapped to APIC interrupts 9, 10 or 11, the APIC should be programmed for active-high reception. When the interrupt is mapped to APIC interrupts 20 through 23, the APIC should be programmed for active-low reception. **Power Well:** Core

59.6.2 General Control (GC)—Offset Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCF] + Ch
Host Memory Space: SBREG_BAR + 0xCF0000 + Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:3	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
2	0x0 RW	**SMB Static Clock Gating Enable (SMBSCGE):** SMB cluster static clock gating is enabled. ***Note:*** Setting this bit will also clock gate all the TCO logic functionality. **Power Well:** Core
1	0x0 RW	**No Reboot (NR):** This bit is set when the "No TCO Reboot Enable" SoC Hard Pin Strap pin (pin name GPIO[12]) is sampled high on the rising edge of the active-low RSMRST_N SoC signal pin. This bit may be set or cleared by software if the Hard Pin Strap is sampled low but may not override the strap when it indicates No TCO Reboot. When set, the TCO Watchdog Timer counts down and generates the SMI# on the first timeout, but will not reboot on the second timeout. **Power Well:** Core
0	0x0 RW	**Function Disable (FD):** When set to one, this disables the PCI configuration register space for the SMBus device. **Power Well:** Core

59.6.3 Power Control Enable (PCE)—Offset 10h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCF] + 10h
Host Memory Space: SBREG_BAR + 0xCF0000 + 10h

Default: 00000009h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
5	0x0 RW	**Hardware Autonomous Enable (HAE):** When set, the SMB will automatically engage power gating when it has reached its idle condition. **Power Well:** Core
4	0x0 RO	**Reserved (RSVD_1):** Reserved. **Power Well:** Core
3	0x1 RO	**Sleep Enable (SE):** When this bit is clear, the SMB will never assert Sleep to the retention flops. If set, then SMB may assert Sleep during power gating. **Power Well:** Core
2	0x0 RO	**D3-Hot Enable (D3HE):** No support for D3 Hot power gating. **Power Well:** Core
1	0x0 RO	**I3 Enable (I3E):** No support for S0i3 power gating. **Power Well:** Core
0	0x1 RW	**PMC Request Enable (PMCRE):** When set to 1, the SMB will engage power gating if it is idle and the power-gating request is granted by the PMC. **Power Well:** Core

59.7 Sideband Registers—CLTT SMBus Configuration Control

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

59.7.1 CLTT Status (CLTT_STS)—Offset 0h

CLTT Status

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 0h
Host Memory Space: SBREG_BAR + 0xCC0000 + 0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
1	0x0 RO/V	**Done (DONE):** Indicates that HW has completed the SMBusCmd. **Power Well:** Core
0	0x0 RO/V	**Busy (BUSY):** Indicates that HW is busy completing an SMBusCmd. **Power Well:** Core

59.7.2 Ch0 Dimm0 Cfg Status (C0D0CFGSTS)—Offset 10h

Memory Channel 0 DIMM 0 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 10h
Host Memory Space: SBREG_BAR + 0xCC0000 + 10h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x0 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.3 Ch0 Dimm1 Cfg Status (C0D1CFGSTS)—Offset 14h

Memory Channel 0 DIMM 1 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 14h
Host Memory Space: SBREG_BAR + 0xCC0000 + 14h

Default: 01000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x1 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.4 Ch0 Dimm2 Cfg Status (C0D2CFGSTS)—Offset 18h

Memory Channel 0 DIMM 2 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 18h
Host Memory Space: SBREG_BAR + 0xCC0000 + 18h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x0 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.5 Ch0 Dimm3 Cfg Status (C0D3CFGSTS)—Offset 1Ch

Memory Channel 0 DIMM 3 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 1Ch
Host Memory Space: SBREG_BAR + 0xCC0000 + 1Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x0 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.6 Ch1 Dimm0 Cfg Status (C1D0CFGSTS)—Offset 20h

Memory Channel 1 DIMM 0 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 20h
Host Memory Space: SBREG_BAR + 0xCC0000 + 20h

Default: 02000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x2 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.7 Ch1 Dimm1 Cfg Status (C1D1CFGSTS)—Offset 24h

Memory Channel 1 DIMM 1 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 24h
Host Memory Space: SBREG_BAR + 0xCC0000 + 24h

Default: 03000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x3 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.8 Ch1 Dimm2 Cfg Status (C1D2CFGSTS)—Offset 28h

Memory Channel 1 DIMM 2 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 28h
Host Memory Space: SBREG_BAR + 0xCC0000 + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x0 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.9 Ch1 Dimm3 Cfg Status (C1D3CFGSTS)—Offset 2Ch

Memory Channel 1 DIMM 3 Configuration and Status Register.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 2Ch
Host Memory Space: SBREG_BAR + 0xCC0000 + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Valid (VALID):** Channel DIMM is Populated. **Power Well:** Core
30:24	0x0 RW	**Slave ID (SLAVE_ID):** SMBus Slave ID. **Power Well:** Core
23:16	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
15:0	0x0 RO/V	**Read_Data (READ_DATA):** Data retrieved from SMBus. **Power Well:** Core

59.7.10 Ch0 Dimm Temp Status (C0TEMPSTS0)—Offset 30h

Memory Channel 0 DIMM TSOD Temperature Status Register. This register is protected by SAI WAC #1 and can be locked by CLTT_SMBUS_Mode (CSMBM) register Bit[1].

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 30h
Host Memory Space: SBREG_BAR + 0xCC0000 + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/V/L	**Read_Temp_Data1 (READ_TEMP_DATA1):** Read_Temp_Data1: Data retrieved from DIMM1. **Power Well:** Core
15:0	0x0 RW/V/L	**Read_Temp_Data0 (READ_TEMP_DATA0):** Read_Temp_Data0: Data retrieved from DIMM0. **Power Well:** Core

59.7.11 Ch0 Dimm Temp Status (C0TEMPSTS1)—Offset 34h

Memory Channel 0 DIMM TSOD Temperature Status Register. This register is protected by SAI WAC #1 and can be locked by CLTT_SMBUS_Mode (CSMBM) register Bit[1].

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 34h
Host Memory Space: SBREG_BAR + 0xCC0000 + 34h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/V/L	**Read_Temp_Data3 (READ_TEMP_DATA3):** Read_Temp_Data3: Data retrieved from DIMM3. **Power Well:** Core
15:0	0x0 RW/V/L	**Read_Temp_Data2 (READ_TEMP_DATA2):** Read_Temp_Data2: Data retrieved from DIMM2. **Power Well:** Core

59.7.12 Ch1 Dimm Temp Status (C1TEMPSTS0)—Offset 38h

Memory Channel 1 DIMM TSOD Temperature Status Register. This register is protected by SAI WAC #1 and can be locked by CLTT_SMBUS_Mode (CSMBM) register Bit[1].

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 38h
Host Memory Space: SBREG_BAR + 0xCC0000 + 38h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/V/L	**Read_Temp_Data1 (READ_TEMP_DATA1):** Read_Temp_Data1: Data retrieved from DIMM1. **Power Well:** Core
15:0	0x0 RW/V/L	**Read_Temp_Data0 (READ_TEMP_DATA0):** Read_Temp_Data0: Data retrieved from DIMM0. **Power Well:** Core

59.7.13 Ch1 Dimm Temp Status (C1TEMPSTS1)—Offset 3Ch

Memory Channel 1 DIMM TSOD Temperature Status Register. This register is protected by SAI WAC #1 and can be locked by CLTT_SMBUS_Mode (CSMBM) register Bit[1].

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xCC] + 3Ch
Host Memory Space: SBREG_BAR + 0xCC0000 + 3Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/V/L	**Read_Temp_Data3 (READ_TEMP_DATA3):** Read_Temp_Data3: Data retrieved from DIMM3. **Power Well:** Core
15:0	0x0 RW/V/L	**Read_Temp_Data2 (READ_TEMP_DATA2):** Read_Temp_Data2: Data retrieved from DIMM2. **Power Well:** Core

59.7.14 Host Configuration (HCFG)—Offset 40h

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xCC] + 40h
Host Memory Space: SBREG_BAR + 0xCC0000 + 40h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
4	0x0 RW/O	**SPD Write Disable (SPD_WRITE_DISABLE):** Reserved. **Power Well:** Core
3	0x0 RW/V	**SSRESET:** Soft SMBUS Reset: When this bit is 1, the SMBus state machine and logic is reset. The HW will reset this bit to 0 when reset operation is completed. **Power Well:** Core
2	0x0 RW	**I2C_EN:** When this bit is 1, the SMB Controller is enabled to communicate with I2C devices. This will change the formatting of some commands. When this bit is 0, behavior is for SMBus. **Power Well:** Core
1	0x0 RW	**SMB_SMI_EN:** When this bit is set, any source of an SMB interrupt will instead be routed to generate an SMI#. Refer to Section 6.7 (Interrupts/SMI#) for details. **Power Well:** Core
0	0x0 RW/V	**HST_EN:** When set, the SMB Host Controller interface is enabled to execute commands. The HST_INT_EN bit needs to be enabled in order for the SMB Host Controller to interrupt or SMI#. Additionally, the SMB Host Controller will not respond to any new requests until all interrupt requests have been cleared. **Power Well:** Core

§ §

60 SPI Controller - B0, D31, F5

60.1 Introduction and Index

The host-accessible registers for the SPI Controller are described here.

To determine the number of devices and functions available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

60.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 31 (decimal), Function 5. The offset addresses and default values are listed.

Table 60-1. Summary of PCI Configuration Registers—0/31/5

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	19E08086	"Device ID and Vendor ID (BIOS_SPI_DID_VID)—Offset 0h" on page 2815
4	4	00000400	"Status and Command (BIOS_SPI_STS_CMD)—Offset 4h" on page 2816
8	4	0C800000	"Revision ID (BIOS_SPI_CC_RID)—Offset 8h" on page 2818
C	4	00000000	"BIST, Header Type, Latency Timer, Cache Line Size (BIOS_SPI_BIST_HTYPE_LT_CLS)—Offset Ch" on page 2818
10	4	00000000	"SPI BAR0 MMIO (BIOS_SPI_BAR0)—Offset 10h" on page 2819
28	4	00000000	"Cardbus CIS Pointer (BIOS_SPI_CCP)—Offset 28h" on page 2819
2C	4	00000000	"Subsystem and Vendor ID (BIOS_SPI_SID_SVID)—Offset 2Ch" on page 2819
30	4	00000000	"Expansion ROM Base Address (BIOS_SPI_XRBAR)—Offset 30h" on page 2820
34	4	00000000	"Capabilities List Pointer (BIOS_SPI_CAPP)—Offset 34h" on page 2820
D0	4	00000000	"SPI Unsupported Request Status (BIOS_SPI_UR_STS_CTL)—Offset D0h" on page 2820
D8	4	0000FFCF	"BIOS Decode Enable (BIOS_SPI_BDE)—Offset D8h" on page 2821
DC	4	00000028	"BIOS Control (BIOS_SPI_BC)—Offset DCh" on page 2823

60.1.2 Host Memory Space—BIOS_SPI_BAR0

An index of the registers that are accessible in Host Memory Space is shown here.

Table 60-2. Summary of Memory Mapped I/O Registers—BIOS_SPI_BAR0

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	4	00000000	"SPI BIOS MMIO PRI (BIOS_BFPREG)—Offset 0h" on page 2825
4	4	00002000	"Hardware Sequencing Flash Status and Control (BIOS_HSFSTS_CTL)—Offset 4h" on page 2826
8	4	00000000	"Flash Address (BIOS_FADDR)—Offset 8h" on page 2828
C	4	00000000	"Discrete Lock Bits (BIOS_DLOCK)—Offset Ch" on page 2829
10	4	00000000	"Flash Data 0 (BIOS_FDATA0)—Offset 10h" on page 2830
14	4	00000000	"Flash Data 1 (BIOS_FDATA1)—Offset 14h" on page 2830
18	4	00000000	"Flash Data 2 (BIOS_FDATA2)—Offset 18h" on page 2830
1C	4	00000000	"Flash Data 3 (BIOS_FDATA3)—Offset 1Ch" on page 2831
20	4	00000000	"Flash Data 4 (BIOS_FDATA4)—Offset 20h" on page 2831
24	4	00000000	"Flash Data 5 (BIOS_FDATA5)—Offset 24h" on page 2831
28	4	00000000	"Flash Data 6 (BIOS_FDATA6)—Offset 28h" on page 2832
2C	4	00000000	"Flash Data 7 (BIOS_FDATA7)—Offset 2Ch" on page 2832
30	4	00000000	"Flash Data 8 (BIOS_FDATA8)—Offset 30h" on page 2832
34	4	00000000	"Flash Data 9 (BIOS_FDATA9)—Offset 34h" on page 2833
38	4	00000000	"Flash Data 10 (BIOS_FDATA10)—Offset 38h" on page 2833
3C	4	00000000	"Flash Data 11 (BIOS_FDATA11)—Offset 3Ch" on page 2833
40	4	00000000	"Flash Data 12 (BIOS_FDATA12)—Offset 40h" on page 2834
44	4	00000000	"Flash Data 13 (BIOS_FDATA13)—Offset 44h" on page 2834
48	4	00000000	"Flash Data 14 (BIOS_FDATA14)—Offset 48h" on page 2834
4C	4	00000000	"Flash Data 15 (BIOS_FDATA15)—Offset 4Ch" on page 2834
50	4	000042C2	"Flash Region Access Permissions (BIOS_FRACC)—Offset 50h" on page 2835
54	4	00007FFF	"Flash Region 0 (BIOS_FREG0)—Offset 54h" on page 2836
58	4	00007FFF	"Flash Region 1 (BIOS_FREG1)—Offset 58h" on page 2836
5C	4	00007FFF	"Flash Region 2 (BIOS_FREG2)—Offset 5Ch" on page 2837
60	4	00007FFF	"Flash Region 3 (BIOS_FREG3)—Offset 60h" on page 2837
64	4	00007FFF	"Flash Region 4 (BIOS_FREG4)—Offset 64h" on page 2838
68	4	00007FFF	"Flash Region 5 (BIOS_FREG5)—Offset 68h" on page 2838
6C	4	00007FFF	"Flash Region 6 (BIOS_FREG6)—Offset 6Ch" on page 2839
70	4	00007FFF	"Flash Region 7 (BIOS_FREG7)—Offset 70h" on page 2839
74	4	00007FFF	"Flash Region 8 (BIOS_FREG8)—Offset 74h" on page 2840
78	4	00007FFF	"Flash Region 9 (BIOS_FREG9)—Offset 78h" on page 2840
7C	4	00000000	"Flash Region 10 (BIOS_FREG10)—Offset 7Ch" on page 2841
80	4	00000000	"Flash Region 11 (BIOS_FREG11)—Offset 80h" on page 2841
84	4	00000000	"Flash Protected Range 0 (BIOS_FPR0)—Offset 84h" on page 2842
88	4	00000000	"Flash Protected Range 1 (BIOS_FPR1)—Offset 88h" on page 2843
8C	4	00000000	"Flash Protected Range 2 (BIOS_FPR2)—Offset 8Ch" on page 2844

Table 60-2. Summary of Memory Mapped I/O Registers—BIOS_SPI_BAR0 (Continued)

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
90	4	00000000	"Flash Protected Range 3 (BIOS_FPR3)—Offset 90h" on page 2845
94	4	00000000	"Flash Protected Range 4 (BIOS_FPR4)—Offset 94h" on page 2846
98	4	00000000	"Global Protected Range 0 (BIOS_GPR0)—Offset 98h" on page 2847
A0	4	FE000000	"Software Sequencing Flash Status and Control (BIOS_SSFSTS_CTL)—Offset A0h" on page 2848
A4	4	00000000	"Prefix Opcode and Opcode Type Configuration (BIOS_PREOP_OPTYPE)—Offset A4h" on page 2850
A8	4	00000000	"Opcode Menu0 Configuration (BIOS_OPMENU0)—Offset A8h" on page 2851
AC	4	00000000	"Opcode Menu1 Configuration (BIOS_OPMENU1)—Offset ACh" on page 2852
B0	4	00000000	"Secondary Flash Region Access Permissions (BIOS_SFRACC)—Offset B0h" on page 2852
B4	4	00000000	"Flash Descriptor Observability Control (BIOS_FDOC)—Offset B4h" on page 2853
B8	4	00000000	"Flash Descriptor Observability Data (BIOS_FDOD)—Offset B8h" on page 2854
C0	4	00000000	"Additional Flash Control (BIOS_AFC)—Offset C0h" on page 2854
C4	4	00002000	"Vendor Specific Component Capabilities for Component 0 (BIOS_SFDP0_VSCC0)—Offset C4h" on page 2855
C8	4	00002000	"Vendor Specific Component Capabilities for Component 1 (BIOS_SFDP1_VSCC1)—Offset C8h" on page 2858
CC	4	00000000	"Parameter Table Index (BIOS_PTINX)—Offset CCh" on page 2860
D0	4	00000000	"Parameter Table Data (BIOS_PTDATA)—Offset D0h" on page 2861
D4	4	00000000	"SPI Bus Requester Status (BIOS_SBRS)—Offset D4h" on page 2862
E0	4	00000000	"Flash Region 12 (BIOS_FREG12)—Offset E0h" on page 2863
E4	4	00000000	"Flash Region 13 (BIOS_FREG13)—Offset E4h" on page 2863
E8	4	00000000	"Flash Region 14 (BIOS_FREG14)—Offset E8h" on page 2864
EC	4	00000000	"Flash Region 15 (BIOS_FREG15)—Offset ECh" on page 2864
F0	4	00000000	"Set Strap Msg Lock (SSML)—Offset F0h" on page 2865
F4	4	00000000	"Set Strap Msg Control (SSMC)—Offset F4h" on page 2865
F8	4	00000000	"Set Strap Msg Data (SSMD)—Offset F8h" on page 2866
108	4	00000000	"RPMC SFDP Table (BIOS_RPMC0_D0)—Offset 108h" on page 2866
10C	4	00000000	"RPMC SFDP Table (BIOS_RPMC1_D0)—Offset 10Ch" on page 2867
110	4	00000000	"RPMC SFDP Table (BIOS_RPMC0_D1)—Offset 110h" on page 2867
114	4	00000000	"RPMC SFDP Table (BIOS_RPMC1_D1)—Offset 114h" on page 2867
118	4	000000C2	"BIOS Master Read Access Permissions (BIOS_BM_RAP)—Offset 118h" on page 2868
11C	4	00000042	"BIOS Master Write Access Permissions (BIOS_BM_WAP)—Offset 11Ch" on page 2868
1B0	4	00000000	"IE Flash Protected Range 0 (BIOS_IE_PR0)—Offset 1B0h" on page 2869
1B4	4	00000000	"IE Flash Protected Range 1 (BIOS_IE_PR1)—Offset 1B4h" on page 2870
1B8	4	00000000	"IE Flash Protected Range 2 (BIOS_IE_PR2)—Offset 1B8h" on page 2871
1BC	4	00000000	"IE Flash Protected Range 3 (BIOS_IE_PR3)—Offset 1BCh" on page 2872
1C0	4	00000000	"IE Flash Protected Range 4 (BIOS_IE_PR4)—Offset 1C0h" on page 2873

60.2 Registers in Configuration Space

60.2.1 Device ID and Vendor ID (BIOS_SPI_DID_VID)—Offset 0h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 0h

Default: 19E08086h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x19e0 RO/V	**Device Identification (DID):**
15:0	0x8086 RO	**Vendor Identification (VID):** This field identifies the manufacturer of the device. Valid vendor identifiers are allocated by the PCI SIG to ensure uniqueness. 0x8086 indicates Intel.

60.2.2 Status and Command (BIOS_SPI_STS_CMD)—Offset 4h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 4h

Default: 00000400h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C/V	**Detected Parity Error (DPE):** Detected Parity Error (DPE).
30	0x0 RW/1C/V	**Signaled System Error (SSE):** Signaled System Error (SSE).
29	0x0 RO	**Received Master Abort (RMA):** Received Master Abort (RMA).
28	0x0 RO	**Received Target Abort (RTA):** Received Target Abort (RTA).
27	0x0 RW/1C/V	**Signaled Target Abort (STA):** Signaled Target Abort (STA).
26:25	0x0 RO	**Devsel Timing (DEVT):** Devsel Timing (DEVT).
24	0x0 RO	**Master Data Parity Error (MDPE):** Master Data Parity Error (MDPE).
23	0x0 RO	**Fast Back to Back Capable (FBTBC):** Fast Back to Back Capable (FBTBC).
22	0x0 RO	**Reserved (RSVD0):** Reserved (RSVD).
21	0x0 RO	**66 MHz Capable (MCAP):** Not 66MHz Capable Device.
20	0x0 RO	**Capabilities List (CAPL):** Capabilities List.
19	0x0 RO	**Interrupt Status (INTS):** Interrupt Status.
18:11	0x0 RO	**Reserved (RSVD1):** Reserved.
10	0x1 RO	**Interrupt Disable (INTD):** Interrupt Disable.
9	0x0 RO	**Fast Back to Back Enable (FBTBEN):** Fast Back to Back Enable.
8	0x0 RW	**System Error Enable (SERREN):** System Error Enable.
7	0x0 RO	**Reserved (RSVD):** Reserved.
6	0x0 RW	**Parity Error Response (PERRR):** Parity Error Response.
5	0x0 RO	**VGA Palette Snoop (VGAPS):** VGA Palette Snoop.
4	0x0 RO	**Memory Write and Invalidate Enable (MWRIEN):** Memory Write and Invalidate Enable.
3	0x0 RO	**Special Cycles (SPCYC):** Special Cycles.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW	**Bus Master Enable (BME):** Bus Master Enable.
1	0x0 RW	**Memory Space Enable (MSE):** Memory Space Enable.
0	0x0 RO	**IO Space Enable (IOSE):** IO Space Enable.

60.2.3 Revision ID (BIOS_SPI_CC_RID)—Offset 8h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 8h

Default: 0C800000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0xc RO/V	**Base Class Code (BCC):** Base Class Code.
23:16	0x80 RO/V	**Sub-Class Code (SCC):** Sub-Class Code.
15:8	0x0 RO/V	**Programming Interface (PI):** Programming Interface.
7:0	0x0 RO/V	**Revision ID (RID):** Indicates the part revision.

60.2.4 BIST, Header Type, Latency Timer, Cache Line Size (BIOS_SPI_BIST_HTYPE_LT_CLS)—Offset Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved.
23	0x0 RO/V	**Multi-function Device (MFD):** Multi-function Device.
22:16	0x0 RO	**Header Type (HTYPE):** Header Type.
15:8	0x0 RO	**Latency Timer (LT):** Latency Timer.
7:0	0x0 RO	**Cacheline Size (CLSZ):** Cacheline Size.

60.2.5 SPI BAR0 MMIO (BIOS_SPI_BAR0)—Offset 10h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 10h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RW	**Memory BAR (MEMBAR):** Software programs this register with the base address of the device's memory region. The Host/BIOS MMIO registers in the flash controller are offset from this BAR.
11:4	0x0 RO	**Memory Size (MEMSIZE):** Hardwired to 0 to indicate 4KB of memory space.
3	0x0 RO	**Prefetchable (PREFETCH):** A device can mark a range as prefetchable if there are no side effects on reads, the device returns all bytes on reads regardless of the byte enables. Hardwired to 1 to indicate the device's memory space as prefetchable.
2:1	0x0 RO	**Type (TYP):** Hardwired to 0 to indicate that Base register is 32 bits wide and mapping can be done anywhere in the 32-bit Memory Space.
0	0x0 RO	**Memory Space Indicator (MEMSPACE):** Hardwired to 0 to identify a Memory BAR.

60.2.6 Cardbus CIS Pointer (BIOS_SPI_CCP)—Offset 28h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Reserved (RSVD):** Reserved.

60.2.7 Subsystem and Vendor ID (BIOS_SPI_SID_SVID)—Offset 2Ch

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RW/O	**Subsystem ID (SSID):** Subsystem ID.
15:0	0x0 RW/O	**Subsystem Vendor ID (SSVID):** Subsystem Vendor ID.

60.2.8 Expansion ROM Base Address (BIOS_SPI_XRBAR)—Offset 30h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO	**Reserved (RSVD):** Reserved.

60.2.9 Capabilities List Pointer (BIOS_SPI_CAPP)—Offset 34h

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + 34h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Reserved.
7:0	0x0 RO	**Capabilities Pointer (CAPP):** Indicates the pointer for the first entry in the capabilities list.

60.2.10 SPI Unsupported Request Status (BIOS_SPI_UR_STS_CTL)—Offset D0h

See the IOSF Specification for required behavior.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Reserved (RSVD):** Reserved.
1	0x0 RW/1C/V	**Unsupported Request Detected (URD):** Set to 1 by hardware upon detecting an Unsupported Request that is not considered an Advisory Non-Fatal error. Cleared to 0 when software writes a 1 to this register.
0	0x0 RW	**Unsupported Request Reporting Enabled (URRE):** If set to 1 by software, the flash controller generates a DoSERR sideband message when the URD bit transitions from 0 to 1.

60.2.11 BIOS Decode Enable (BIOS_SPI_BDE)—Offset D8h

This register only effects BIOS decode if BIOS is resident on SPI.

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + D8h

Default: 0000FFCFh

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):**
15	0x1 RO	**F8-FF Enable (EF8):** Enables decoding of 512K of the following BIOS range: • Data space: FFF80000h - FFFFFFFFh
14	0x1 RW	**F0-F8 Enable (EF0):** Enables decoding of 512K of the following BIOS range: • Data space: FFF00000h - FFF7FFFFh
13	0x1 RW	**E8-EF Enable (EE8):** Enables decoding of 512K of the following BIOS range: • Data space: FFE80000h - FFEFFFFFh
12	0x1 RW	**E0-E8 Enable (EE0):** Enables decoding of 512K of the following BIOS range: • Data space: FFE00000h - FFE7FFFFh
11	0x1 RW	**D8-DF Enable (ED8):** Enables decoding of 512K of the following BIOS range: • Data space: FFD80000h - FFDFFFFFh
10	0x1 RW	**D0-D7 Enable (ED0):** Enables decoding of 512K of the following BIOS range: • Data space: FFD00000h - FFD7FFFFh
9	0x1 RW	**C8-CF Enable (EC8):** Enables decoding of 512K of the following BIOS range: • Data space: FFC80000h - FFCFFFFFh
8	0x1 RW	**C0-C7 Enable (EC0):** Enables decoding of 512K of the following BIOS range: • Data space: FFC00000h - FFC7FFFFh
7	0x1 RW	**Legacy F Segment Enable (LFE):** This enables the decoding of the legacy 64KB range at F0000h - FFFFFh ***Note:*** Decode for the BIOS legacy F segment is enabled by the LFE bit only, it is not affected by the GEN_PMCON_1.iA64_EN bit.
6	0x1 RW	**Legacy E Segment Enable (LEE):** This enables the decoding of the legacy 64KB range at E0000h - EFFFFh ***Note:*** Decode for the BIOS legacy E segment is enabled by the LEE bit only, it is not affected by the GEN_PMCON_1.iA64_EN bit.
5:4	0x0 RO	**Reserved (RSVD_1):** Reserved.
3	0x1 RW	**70-7F Enable (E70):** Enables decoding of 1 MB of the following BIOS range: • Data space: FF700000h - FF7FFFFFh
2	0x1 RW	**60-6F Enable (E60):** Enables decoding of 1 MB of the following BIOS range: • Data space: FF600000h - FF6FFFFFh

Bit Range	Default & Access	Field Name (ID): Description
1	0x1 RW	**50-5F Enable (E50):** Enables decoding of 1 MB of the following BIOS range: • Data space: FF500000h - FF5FFFFFh
0	0x1 RW	**40-4F Enable (E40):** Enables decoding of 1 MB of the following BIOS range: • Data space: FF400000h - FF4FFFFFh

60.2.12 BIOS Control (BIOS_SPI_BC)—Offset DCh

Type: PCI Configuration Register (Size: 32 bits)

Offset: [B:0, D:31, F:5] + DCh

Default: 00000028h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**Reserved (RSVD):** Reserved.
11	0x0 RW/L	**Async SMI Enable for BIOS Write Protection (ASE_BWP):** When set to '1' the flash controller will generate an SMI when it blocks a BIOS write or erase due to WPD=0. The value in this field can be written by software as long as the BIOS Interface Lock-Down (BILD) is not set.
10	0x0 RO/V	**Asynchronous SMI Status (SPI_ASYNC_SS):** Status indication that the SPI Flash Controller has asserted an asynchronous SMI. Hardware clears the bit when it sends the De-assert SMI message. • 0 = Default state • 1 = SPI flash controller asserted asynchronous SMI
9	0x0 RW/L	Reserved.
8	0x0 RW/1C/V	**Synchronous SMI Status (SPI_SYNC_SS):** Status indication that the SPI Flash Controller has asserted a synchronous SMI. Hardware clears the bit when it sends the De-assert Synchronous SMI message. • 0 = Default state • 1 = SPI flash controller asserted Synchronous SMI
7	0x0 RW/L	**BIOS Interface Lock-Down (BILD):** When set, prevents TS and BBS from being changed. This bit can only be written from 0 to 1 once.
6	0x0 RW/V/L	**Boot BIOS Strap (BBS):** This field determines the destination of accesses to the BIOS memory range. For the default, “Functional Strap” section of Signal Description chapter for details. Bit Description • 0 = SPI • 1 = LPC The value in this field can be overwritten by software as long as the BIOS Interface Lock-Down (BILD) is not set
5	0x1 RW/L	**Enable InSMM.STS (EISS):** When this bit is set, the BIOS region is not writable until the CPU sets the InSMM.STS bit. If this bit [5] is set, then WPD must be a '1' and InSMM.STS must be '1' also in order to write to BIOS region of SPI Flash. If this bit [5] is clear, then the InSMM.STS is a don't care. This bit is locked by LE.
4	0x0 RO/V	**Top Swap Status (TSS):** This bit provides a read-only path to view the state of the Top Swap bit. It is duplicated here to be consistent with the LPC version of the BC register.

Bit Range	Default & Access	Field Name (ID): Description
3:2	0x2 RW	**SPI Read Configuration (SRC):** These bits are located in PCI Config space to allow them to be set early in the boot flow. This 2-bit field controls two policies related to BIOS reads on the SPI interface: Bit 3- Prefetch Enable Bit 2- Cache Disable Settings are summarized below: Bits 3:2 Description • 00 No prefetching, but caching enabled. Direct Memory reads load the read buffer cache with "valid" data, allowing repeated reads to the same range to complete quickly • 01 No prefetching and no caching. One-to-one correspondence of host BIOS reads to SPI cycles. This value can be used to invalidate the cache. • 10 Prefetching and Caching enabled. This mode is used for long sequences of short reads to consecutive addresses (i.e. shadowing). • 11 Illegal. Caching must be enabled when Prefetching is enabled. This eliminates the need for a complex prefetch-flushing mechanism.
1	0x0 RW/L	**Lock Enable (LE):** When set, setting the WPD bit will cause SMI. When cleared, setting the WPD bit will not cause SMI. Once set, this bit can only be cleared by a PLTRST#. When this bit is set, EISS - bit [5] of this register is locked down.
0	0x0 RW	**Write Protect Disable (WPD):** When set, access to the BIOS space is enabled for both read and write cycles to BIOS. When cleared, only read cycles are permitted to the FWH or SPI flash. When this bit is written from a '0' to a '1' and the LE bit is also set, an SMI# is generated. This ensures that only SMM code can update BIOS.

60.3 Registers in Memory Space—BIOS_SPI_BAR0

These registers are accessed in Host Memory Space starting at the relocatable memory address defined by the Base Address Register (BAR) BIOS_SPI_BAR0.

60.3.1 SPI BIOS MMIO PRI (BIOS_BFPREG)—Offset 0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 0h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Shadowed BIOS Region Select (SBRS):**
30:16	0x0 RO/V	**BIOS Flash Primary Region Limit (PRL):** This specifies address bits 26:12 for the Primary Region Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG1.Region Limit, or the Flash Descriptor.FLREG6.Region Limit depending on the BFPREG.SBRS bit.
15	0x0 RO	**Reserved (RSVD):** Reserved.
14:0	0x0 RO/V	**BIOS Flash Primary Region Base (PRB):** This specifies address bits 26:12 for the Primary Region Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG1.Region Base, or the Flash Descriptor.FLREG6.Region Base depending on the BFPREG.SBRS bit.

60.3.2 Hardware Sequencing Flash Status and Control (BIOS_HSFSTS_CTL)—Offset 4h

Note: If operating in Non-Descriptor mode, hardware sequencing is not allowed.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 4h

Default: 00002000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Flash SPI SMI# Enable (FSMIE):** When set to 1, the SPI asserts an SMI# request whenever the Flash Cycle Done but is 1.
30	0x0 RO	Reserved.
29:24	0x0 RW	**Flash Data Byte Count (FDBC):** The field specifies the number of bytes to shift in or out during the data portion of the SPI cycle. The contents of this register are 0s based with 0b representing 1 byte and 3Fh representing 64 bytes. The number of bytes transferred is the value of this field plus 1. The field is ignored for the Block Erase command.
23:22	0x1 RO	Reserved.
21	0x0 RW	**Write Enable Type (WET):** Write Enable Type (WET) • 0 - Use 06h as the write enable instruction • 1 - Use 50h as the write enable instruction
20:17	0x0 RW	**FLASH Cycle (FCYCLE):** This field defines the Flash SPI cycle type generated to the FLASH when the FGO but is set as defined below: • 0 - Read (1 up to 64 bytes by setting FDBC) • 1 - Reserved • 2 - Write (1 up to 64 bytes by setting FDBC) • 3 - 4k Block Erase • 4 - 64K Sector Erase • 5 - Read SFDP • 6 - Read JEDEC ID • 7 - Write Status • 8 - Read Status • 9 - RPMC Op1 • A - RPMC Op2 Flash controller hardware automatically inserts a write enable opcode prior to write and erase operations. Hardware automatically polls for device not-busy using read status after write and erase operations. Flash controller hardware automatically polls for device not-ready using read status and RPMC Op2 after RPMC Op1 operations. Read status is repeated until the device is not-busy, then RPMC Op2 is repeated until the device is not-busy. If the device does not support 64k erase size (or if it doesn't support SFDP) then only 4k is allowed. ***Note:*** If reserved 1 is programmed to this field, flash controller will handle it as if it is 0 (Read).
16	0x0 RW/1S/V	Flash Cycle Go (FGO): A write to this register with a 1 in this but initiates a request to the Flash SPI Arbiter to start a cycle. This register is cleared by hardware when the cycle is granted by the SPU arbiter to run the cycle on the SPI bus. When the cycle is complete, the FDONE bit is set. Software is forbidden to write to any register in the HSFLCTL register between the FGO bit getting set and the FDONE bit being cleared. Any attempt to violate this rule will be ignored by hardware. Hardware allows other bits in this register to be programmed for the same transaction when writing this bit to 1. This saves an additional memory write. This but always returns 0 on reads.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW/L	**Flash Configuration Lock-Down (FLOCKDN):** When set to 1, those Flash Program Registers that are locked down by this FLOCKDN but cannot be written. Once set to 1, this but can only be cleared by a hardware reset.
14	0x0 RO/V	**Flash Descriptor Valid (FDV):** This bit is set to a 1 if the Flash Controller read the correct Flash Descriptor Signature. If the Flash Descriptor Valid bit is not 1, software cannot use the Hardware Sequencing registers, but must use the software sequencing registers. Any attempt to use the Hardware Sequencing registers will result in the FCERR bit being set.
13	0x1 RO/V	**Flash Descriptor Override Pin-Strap Status (FDOPSS):** This register reflects the value the Flash Descriptor Override Pin-Strap. • 1 - No override • 0 - The Flash Descriptor Override strap is set
12	0x0 RW/L	**PRR3 PRR4 Lock-Down (PRR34_LOCKDN):** When set to 1, the BIOS PRR3 and PRR4 registers cannot be written. Once set to 1, this bit can only be cleared by a hardware reset.
11	0x0 RW/L	**Flash Configuration Lock-Down (WRSDIS):** • 0 - Write status operation may be used using Hardware Sequencing • 1 - Write status is not allowed as a Hardware Sequencing Operation. The flash controller will block the operation and set the FCERR but when software sets the “go” bit.
10:6	0x0 RO	Reserved.
5	0x0 RO/V	**SPI Cycle In Progress (H_SCIP):** hardware sets this bit when software sets the Flash Cycle Go (FGO) bit in the Hardware Sequencing Flash Control register. This bit remains set until the cycle completes on the SPI interface. Hardware automatically sets and clears this bit so that software can determine when read data is valid and/or when it is safe to begin programming the next command. Software must only program the next command when this bit is 0.
4:0	0x0 RO	Reserved.

60.3.3 Flash Address (BIOS_FADDR)—Offset 8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 8h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x0 RO	**Reserved (RSVD):** Reserved.
26:0	0x0 RW	**Flash Linear Address (FLA):** The FLA is the starting byte linear address of a SPI Read or Write cycle or an address within a Block for the Block Erase command. The Flash Linear Address must fall within a region for which BIOS has access permissions. Hardware must convert the FLA into a Flash Physical Address (FPA) before running this cycle on the SPI bus. When operating in non-descriptor mode bit [26:24] is ignored and the FLA [23:0] is the FPA.

60.3.4 Discrete Lock Bits (BIOS_DLOCK)—Offset Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RW	**Reserved (RSVD):** Whenever modifying BIOS_DLOCK read the value of bits 31:17 and write back the value read.
16	0x0 RW/L	**SSEQ Lock-Down (SSEQLOCKDN):** IA FW Software Sequencing registers are locked when the logical OR of this bit and FLOCKDN is true. The affected registers are BIOS_SSFSTS_CTL.SCF, BIOS_PREOP_OPTYPE, BIOS_OPMENU0, and BIOS_OPMENU1. Once set to 1 this register is only cleared by host partition reset.
15:13	0x0 RW	**Reserved (RSVD):** Whenever modifying BIOS_DLOCK read the value of bits 15:13 and write back the value read.
12	0x0 RW/L	**PR4 Lock-Down (PR4LOCKDN):** IA FW PR4 register is locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
11	0x0 RW/L	**PR3 Lock-Down (PR3LOCKDN):** IA FW PR3 register is locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
10	0x0 RW/L	**PR2 Lock-Down (PR2LOCKDN):** IA FW PR2 register is locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
9	0x0 RW/L	**PR1 Lock-Down (PR1LOCKDN):** IA FW PR1 register is locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
8	0x0 RW/L	**PR0 Lock-Down (PR0LOCKDN):** IA FW PR0 register is locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
7:4	0x0 RW	**Reserved (RSVD):** Whenever modifying BIOS_DLOCK read the value of bits 7:4 and write back the value read.
3	0x0 RW/L	**SBMRAG Lock-Down (SBMRAGLOCKDN):** IA FW SFRACC.BMRAG register bits are locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
2	0x0 RW/L	**SBMWAG Lock-Down (SBMWAGLOCKDN):** IA FW SFRACC.BMWAG register bits are locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
1	0x0 RW/L	**BMRAG Lock-Down (BMRAGLOCKDN):** IA FW FRACC.BMRAG register bits are locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.
0	0x0 RW/L	**BMWAG Lock-Down (BMWAGLOCKDN):** IA FW FRACC.BMWAG register bits are locked when the logical OR of this bit and FLOCKDN is true. Once set to 1 this register is only cleared by host partition reset.

60.3.5 Flash Data 0 (BIOS_FDATA0)—Offset 10h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 10h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 0 (FD0):** This field is shifted out as the SPI Data on the Master-Out Slave-In Data pin during the data portion of the SPI cycle. This register also shifts in the data from the Master-In Slave-Out pin into this register during the data portion of the SPI cycle. The data is always shifted starting with the least significant byte, msb to lsb, followed by the next least significant byte, msb to lsb, etc. Specifically, the shift order on SPI in terms of bits within this register is: 7-6-5-4-3-2-1-0-15-14-13-?8-23-22-?16-31?24 Bit 24 is the last bit shifted out/in. There are no alignment assumptions; byte 0 always represents the value specified by the cycle address. ***Note:*** The data in this register may be modified by the hardware during any programmed SPI transaction. Direct Memory Reads do not modify the contents of this register.

60.3.6 Flash Data 1 (BIOS_FDATA1)—Offset 14h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 14h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 1 (FD1):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD0 has completely shifted in/out.

60.3.7 Flash Data 2 (BIOS_FDATA2)—Offset 18h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 18h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 2 (FD2):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD1 has completely shifted in/out.

60.3.8 Flash Data 3 (BIOS_FDATA3)—Offset 1Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 1Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 3 (FD3):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD2 has completely shifted in/out.

60.3.9 Flash Data 4 (BIOS_FDATA4)—Offset 20h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 20h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 4 (FD4):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD3 has completely shifted in/out.

60.3.10 Flash Data 5 (BIOS_FDATA5)—Offset 24h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 24h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 5 (FD5):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD4 has completely shifted in/out.

60.3.11 Flash Data 6 (BIOS_FDATA6)—Offset 28h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 28h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 6 (FD6):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD5 has completely shifted in/out.

60.3.12 Flash Data 7 (BIOS_FDATA7)—Offset 2Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 2Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 7 (FD7):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD6 has completely shifted in/out.

60.3.13 Flash Data 8 (BIOS_FDATA8)—Offset 30h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 30h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 8 (FD8):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD7 has completely shifted in/out.

60.3.14 Flash Data 9 (BIOS_FDATA9)—Offset 34h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 34h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 9 (FD9):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD8 has completely shifted in/out.

60.3.15 Flash Data 10 (BIOS_FDATA10)—Offset 38h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 38h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 10 (FD10):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD9 has completely shifted in/out.

60.3.16 Flash Data 11 (BIOS_FDATA11)—Offset 3Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 3Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 11 (FD11):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD10 has completely shifted in/out.

60.3.17 Flash Data 12 (BIOS_FDATA12)—Offset 40h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 40h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 12 (FD12):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD11 has completely shifted in/out.

60.3.18 Flash Data 13 (BIOS_FDATA13)—Offset 44h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 44h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 13 (FD13):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD12 has completely shifted in/out.

60.3.19 Flash Data 14 (BIOS_FDATA14)—Offset 48h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 48h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 14 (FD14):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD13 has completely shifted in/out.

60.3.20 Flash Data 15 (BIOS_FDATA15)—Offset 4Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 4Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Flash Data 15 (FD15):** Similar definition as Flash Data 0. However, this register does not begin shifting until FD14 has completely shifted in/out.

60.3.21 Flash Region Access Permissions (BIOS_FRACC)—Offset 50h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 000042C2h

BAR and Offset: [BIOS_SPI_BAR0] + 50h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/L	**BIOS Master Write Access Grant (BMWAG):** Each bit [31:24] corresponds to Master [7:0]. BIOS can grant one or more masters write access to the BIOS region 1 overriding the permissions in the Flash Descriptor. The contents of this register are locked by the FLOCKDN bit.
23:16	0x0 RW/L	**BIOS Master Read Access Grant (BMRAG):** Each bit [23:16] corresponds to Master [7:0]. BIOS can grant one or more masters read access to the BIOS region 1 overriding the read permissions in the Flash Descriptor. The contents of this register are locked by the FLOCKDN bit.
15:8	0x42 RO/V	**BIOS Region Write Access (BRWA):** Each bit [15:8] corresponds to Regions [7:0]. If the bit is set, this master can erase and write that particular region through register accesses. The contents of this register are that of the Flash Descriptor.Flash Master 1.Master Region Write Access OR a particular master has granted BIOS write permissions in their Master Write Access Grant register OR the Flash Descriptor Security Override strap is set. BIOS always have the write access to its own Region 1 and Region 6 by default. Thus, the reset default of this field will be read as “42h”regardless of descriptor or non-descriptor mode.
7:0	0xc2 RO/V	**BIOS Region Read Access (BRRA):** Each bit [7:0] corresponds to Regions [7:0]. If the bit is set, this master can read that particular region through register accesses. The contents of this register are that of the Flash Descriptor.Flash Master 1.Master Region Write Access OR a particular master has granted BIOS read permissions in their Master Read Access Grant register OR the Flash Descriptor Security Override strap is set. BIOS always have the read access to its own Region 1 and Region 6 by default. Thus, the reset default of this field will be read as “42h” regardless of descriptor or non-descriptor mode.

60.3.22 Flash Region 0 (BIOS_FREG0)—Offset 54h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 54h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 0 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG0.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 0 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG0.Region Base.

60.3.23 Flash Region 1 (BIOS_FREG1)—Offset 58h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 58h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 1 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG1.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 1 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG1.Region Base.

60.3.24 Flash Region 2 (BIOS_FREG2)—Offset 5Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 5Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 2 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG2.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 2 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG2.Region Base.

60.3.25 Flash Region 3 (BIOS_FREG3)—Offset 60h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 60h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 3 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG3.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 3 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG3.Region Base.

60.3.26 Flash Region 4 (BIOS_FREG4)—Offset 64h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 64h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 4 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG4.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 4 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG4.Region Base.

60.3.27 Flash Region 5 (BIOS_FREG5)—Offset 68h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 68h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 5 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG5.Region Limit
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 5 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG5.Region Base

60.3.28 Flash Region 6 (BIOS_FREG6)—Offset 6Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 6Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 6 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG6.Region Limit if the Server Feature Disable Fuse 6 is '0'. If the Server Feature Disable Fuse 6 is a '1' then this field is loaded with all zeros.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 6 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG6.Region Base if the Server Feature Disable Fuse 6 is '0'. If the Server Feature Disable Fuse 6 is a '1' then this field is loaded with all ones.

60.3.29 Flash Region 7 (BIOS_FREG7)—Offset 70h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 70h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 7 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG7.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 7 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG7.Region Base.

60.3.30 Flash Region 8 (BIOS_FREG8)—Offset 74h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 74h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 8 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG8.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 8 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG8.Region Base.

60.3.31 Flash Region 9 (BIOS_FREG9)—Offset 78h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00007FFFh

BAR and Offset: [BIOS_SPI_BAR0] + 78h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 9 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG9.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x7fff RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 9 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG9.Region Base.

60.3.32 Flash Region 10 (BIOS_FREG10)—Offset 7Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 7Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 10 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG10.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x0 RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 10 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG10.Region Base.

60.3.33 Flash Region 11 (BIOS_FREG11)—Offset 80h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 80h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 11 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG11.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x0 RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 11 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG11.Region Base.

60.3.34 Flash Protected Range 0 (BIOS_FPR0)—Offset 84h

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 84h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RW/L	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RW/L	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RW/L	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.35 Flash Protected Range 1 (BIOS_FPR1)—Offset 88h

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 88h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RW/L	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RW/L	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RW/L	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.36 Flash Protected Range 2 (BIOS_FPR2)—Offset 8Ch

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 8Ch

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RW/L	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RW/L	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RW/L	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.37 Flash Protected Range 3 (BIOS_FPR3)—Offset 90h

This register can not be written when the PRR34_LOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 90h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RW/L	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RW/L	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RW/L	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.38 Flash Protected Range 4 (BIOS_FPR4)—Offset 94h

This register can not be written when the PRR34_LOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 94h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/L	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RW/L	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RW/L	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RW/L	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.39 Global Protected Range 0 (BIOS_GPR0)—Offset 98h

This register is initialized via softstraps. This protected range applies globally to all masters / flash requesters.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 98h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RO/V	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RO/V	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RO/V	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.40 Software Sequencing Flash Status and Control (BIOS_SSFSTS_CTL)—Offset A0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: FE000000h

BAR and Offset: [BIOS_SPI_BAR0] + A0h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:27	0x1f RO	**Reserved (RSVD):** This field is not programmable, it is fixed at 1Fh.
26:24	0x6 RW/L	**SPI Cycle Frequency (SCF):** The listed frequencies are approximate. • 010: 17MHz • 100: 30MHz • 110: 48MHz • All Others: Reserved This register sets frequency to use for all SPI Software Sequencing cycles (write, erase, fast read, read status,.etc) except for the Read cycle which always run at 20MHz. This register is locked when the SPI Configuration Lock-Down (FLOCKDN) bit is set.
23	0x0 RW	**SPI SMI# Enable (SME):** When set to 1, the SPI asserts an SMI# request whenever the Cycle Done Status bit is 1.
22	0x0 RW	**Data Cycle (DS):** When set to 1, there is data that corresponds to this transaction. When 0, no data is delivered for this cycle, and the DBC and data fields themselves are don't cares.
21:16	0x0 RW	**Data Byte Count (DBC):** This field specifies the number of bytes to shift in or out during the data portion of the SPI cycle. The valid settings (in decimal) are any value from 0 to 63. The number of bytes transferred is the value of this field plus 1. ***Note:*** When this field is 00_0000b, then there is 1 byte to transfer and that 11_1111b means there are 64 bytes to transfer.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:12	0x0 RW	**Cycle Opcode Pointer (COP):** This field selects one of the programmed opcodes in the Opcode Menu to be used as the SPI Command/Opcode. In the case of an Atomic Cycle Sequence, this determines the second command.
11	0x0 RW	**Sequence Prefix Opcode Pointer (SPOP):** This field selects one of the two programmed prefix opcodes for use when performing an Atomic Cycle Sequence. A value of 0 points to the opcode in the least significant byte of the Prefix Opcodes register. By making this programmable, the ICH supports flash devices that have different opcodes for enabling writes to the data space vs. status register.
10	0x0 RW	**Atomic Cycle Sequence (ACS):** When set to 1 along with the SCGO assertion, the SoC will execute a sequence of commands on the SPI interface without allowing another master to arbitrate and interleave cycles. The sequence is composed of: • Atomic Sequence Prefix Command (8-bit opcode only) • Primary Command specified below by software (can include address and data) • Polling the Flash Status Register (opcode 05h) until bit 0 becomes 0b. The SPI Cycle in Progress bit remains set and the Cycle Done Status bit remains unset until the Busy bit in the Flash Status Register returns 0.
9	0x0 RW/1S/V	**SPI Cycle Go (SCGO):** This bit always returns 0 on reads. However, a write to this register with a '1' in this bit starts the SPI cycle defined by the other bits of this register. The "SPI Cycle in Progress" (SCIP) bit gets set by this action. Hardware must ignore writes to this bit while the Cycle In Progress bit is set. Hardware allows other bits in this register to be programmed for the same transaction when writing this bit to 1. This saves an additional memory write.
8	0x0 RO	**Reserved (RSVD_2):** Reserved.



Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO/V	**Fast Read Supported (FAST_READ_SUPPORT):** This bit reflects the value of the Fast Read Support bit in the Flash Descriptor Component Section.
6	0x0 RO/V	**Dual Output Fast Read Supported (DUAL_FAST_READ_SUPPORT):** This bit reflects the value of the Dual Output Fast Read Support bit in the Flash Descriptor Component Section.
5	0x0 RO	**Reserved (RSVD_3):** Reserved.
4	0x0 RO/V	**Access Error Log (AEL):** This bit reflects the value of the Hardware Sequencing Status.AEL register.
3	0x0 RW/1C/V	**Flash Cycle Error (FCERR):** Hardware sets this bit to 1 when a programmed access is blocked from running on the SPI interface due to one of the protection policies or when any of the programmed cycle registers is written while a programmed access is already in progress. This bit remains asserted until cleared by software writing a 1 or hardware reset.
2	0x0 RW/1C/V	**Cycle Done Status (CYCLE_DONE_STS):** The SoC sets this bit to 1 when the SPI Cycle completes (i.e., SCIP bit is 0) after software sets the GO bit. This bit remains asserted until cleared by software writing a 1 or hardware reset. When this bit is set and the SPI SMI# Enable bit is set, an internal signal is asserted to the SMI# generation block. Software must make sure this bit is cleared prior to enabling the SPI SMI# assertion for a new programmed access.
1	0x0 RO	**Reserved (RSVD_4):** Reserved.
0	0x0 RO/V	**SPI Cycle In Progress (SCIP):** Hardware sets this bit when software sets the SPI Cycle Go bit in the Command register.

60.3.41 Prefix Opcode and Opcode Type Configuration (BIOS_PREOP_OPTYPE)—Offset A4h

This register is not writable when the Flash Configuration Lock-Down (FLOCKDN) bit is set. Entries in this register correspond to the entries in the Opcode Menu Configuration register.

Note that the definition below only provides write protection for opcodes that have addresses associated with them. Therefore, any erase or write opcodes that do not use an address should be avoided (for example, "Chip Erase" and "Auto-Address Increment Byte Program").

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + A4h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RW/L	**Opcode Type 7 (OPCODE_TYPE7):** See the description for bits 17:16.
29:28	0x0 RW/L	**Opcode Type 6 (OPCODE_TYPE6):** See the description for bits 17:16.
27:26	0x0 RW/L	**Opcode Type 5 (OPCODE_TYPE5):** See the description for bits 17:16.
25:24	0x0 RW/L	**Opcode Type 4 (OPCODE_TYPE4):** See the description for bits 17:16.
23:22	0x0 RW/L	**Opcode Type 3 (OPCODE_TYPE3):** See the description for bits 17:16.
21:20	0x0 RW/L	**Opcode Type 2 (OPCODE_TYPE2):** See the description for bits 17:16.
19:18	0x0 RW/L	**Opcode Type 1 (OPCODE_TYPE1):** See the description for bits 17:16.
17:16	0x0 RW/L	**Opcode Type 0 (OPCODE_TYPE0):** This field specifies information about the corresponding Opcode 0. This information allows the hardware to 1) know whether to use the address field and 2) provide BIOS and Shared Flash protection capabilities.The hardware implementation also uses the read vs. write information for modifying the behavior of the SPI interface logic. The encoding of the two bits is: • 00 = No Address associated with this Opcode and Read Cycle type • 01 = No Address associated with this Opcode and Write Cycle type • 10 = Address required; Read cycle type • 11 = Address required; Write cycle type
15:8	0x0 RW/L	**Prefix Opcode 1 (PREFIX_OPCODE1):** Software programs an SPI opcode into this field that is permitted to run as the first command in an atomic cycle sequence.
7:0	0x0 RW/L	**Prefix Opcode 0 (PREFIX_OPCODE0):** Software programs an SPI opcode into this field that is permitted to run as the first command in an atomic cycle sequence.

60.3.42 Opcode Menu0 Configuration (BIOS_OPMENU0)—Offset A8h

This register is not writable when the SPI Configuration Lock-Down bit (FLOCKDN) is set. Eight entries are available in this register to give BIOS a sufficient set of commands for communicating with the flash device, while also restricting what malicious software can do. This keeps the hardware flexible enough to operate with a wide variety of SPI devices.

It is recommended that BIOS avoid programming Write Enable opcodes in this menu. Malicious software could then perform writes and erases to the SPI flash without using the atomic cycle mechanism. This could cause functional failures in a shared flash environment. Write Enable opcodes should only be programmed in the Prefix Opcodes.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + A8h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/L	**Allowable Opcode 3 (OPCODE3):** See the description for bits 7:0.
23:16	0x0 RW/L	**Allowable Opcode 2 (OPCODE2):** See the description for bits 7:0.
15:8	0x0 RW/L	**Allowable Opcode 1 (OPCODE1):** See the description for bits 7:0.
7:0	0x0 RW/L	**Allowable Opcode 0 (OPCODE0):** Software programs an SPI opcode into this field for use when initiating SPI commands through the Control Register.

60.3.43 Opcode Menu1 Configuration (BIOS_OPMENU1)—Offset ACh

This register is not writable when the SPI Configuration Lock-Down bit (FLOCKDN) is set. Eight entries are available in this register to give BIOS a sufficient set of commands for communicating with the flash device, while also restricting what malicious software can do. This keeps the hardware flexible enough to operate with a wide variety of SPI devices.

It is recommended that BIOS avoid programming Write Enable opcodes in this menu. Malicious software could then perform writes and erases to the SPI flash without using the atomic cycle mechanism. This could cause functional failures in a shared flash environment. Write Enable opcodes should only be programmed in the Prefix Opcodes.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + ACh

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/L	**Allowable Opcode 7 (OPCODE7):** See the description for bits 7:0.
23:16	0x0 RW/L	**Allowable Opcode 6 (OPCODE6):** See the description for bits 7:0.
15:8	0x0 RW/L	**Allowable Opcode 5 (OPCODE5):** See the description for bits 7:0.
7:0	0x0 RW/L	**Allowable Opcode 4 (OPCODE4):** Software programs an SPI opcode into this field for use when initiating SPI commands through the Control Register.

60.3.44 Secondary Flash Region Access Permissions (BIOS_SFRACC)—Offset B0h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + B0h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RW/L	**Secondary BIOS Master Write Access Grant (SECONDARYBIOS_MWAG):** Each bit [31:29] corresponds to Master [7:0]. BIOS can grant one or more masters write access to the Secondary BIOS region 6 overriding the permissions in the Flash Descriptor. The contents of this register are locked by the FLOCKDN bit.
23:16	0x0 RW/L	**Secondary BIOS Master Read Access Grant (SECONDARYBIOS_MRAG):** Each bit [28:16] corresponds to Master [7:0]. BIOS can grant one or more masters read access to the Secondary BIOS region 6 overriding the read permissions in the Flash Descriptor. The contents of this register are locked by the FLOCKDN bit.
15:0	0x0 RO	**Reserved (RSVD):** Reserved.

60.3.45 Flash Descriptor Observability Control (BIOS_FDOC)—Offset B4h

This is a test mode only register that can be used to observe the contents of the Flash Descriptor that is stored internally in the SoC Flash Controller. The CPU Complex soft straps are not observable in SoC as these are forwarded to the CPU Complex and not stored.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + B4h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:15	0x0 RO	**Reserved (RSVD):** Reserved.
14:12	0x0 RW	**Flash Descriptor Section Select (FDSS):** Selects which section within the loaded Flash Descriptor to observe. • 000: Flash Signature and Descriptor Map • 001: Component • 010: Region • 011: Master • 100: Soft Straps • Other: Reserved
11:2	0x0 RW	**Flash Descriptor Section Index (FDSI):** Selects the DW offset within the Flash Descriptor Section to observe.
1:0	0x0 RO	**Reserved (RSVD_1):** Reserved.

60.3.46 Flash Descriptor Observability Data (BIOS_FDOD)—Offset B8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + B8h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Flash Descriptor Section Data (FDSD):** Returns the DW of data to observe as selected in the Flash Descriptor Observability Control.

60.3.47 Additional Flash Control (BIOS_AFC)—Offset C0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + C0h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD):** Reserved.
9:1	0x0 RW	**Reserved RW Scratch Pad (Reserved_SCRATCHPAD):** Scratch Pad bits that are R/W to be used
0	0x0 RW/V/P	**Stop Prefetch on Flush Pending (SPFP):** When set to '1', the in progress of a prefetch will be ended if subsequence access from the master of the same interface (SPXB or MBB) is detected to be a cache-miss and read cache will be flushed. When set to '0', the prefetch will be allowed to complete prior to flushing. This register is only reset on a Early boot reset of both the Host and the ME partitions.NOTE: This should change to reset on a host reset and a different SPFP bit used for the Intel® Management Engine cache. Future project fix? The reset value of this bit is determined by the SoC soft strap PCHSTRP0.SPI_SPFP.

60.3.48 Vendor Specific Component Capabilities for Component 0 (BIOS_SFDP0_VSCC0)—Offset C4h

Note: Intel is planning to deprecate support for non-SFDP capable flash devices.

VSCC registers were previously used to allow software to configure flash device-specific parameters. Since Serial Flash Discoverable Parameters were standardized in 2011 this capability is less important. For SPT, the VSCC registers will be renamed SFDP registers. If the flash controller discovers SFDP devices, then hardware will populate the appropriate register fields from the SFDP table and treat them as read-only by software. If SFDP is not discovered then the registers will remain writable by software. This change is intended to allow microarchitectural cleanup by having device parameters sourced from a single location. The SPI flash controller uses the Quad Enable Requirements (QER) data from the SFDP table to ensure that the flash device is enabled for Quad-mode prior to issuing any Quad-mode reads. If quad reads are disabled via softstraps then the flash controller may ignore QER. If the QE bit is in the flash status register, the controller reads the status register. If the QE bit is 0 then the controller sets it to 1 and writes the status register back to the flash device using a write_enable, write_status sequence.

The QER bits are used by software/firmware as follows:

1. Manufacturing time: FITC tool is used to initialize the set of vendor-specific VSCC entries in the FLUMAP portion of the descriptor, where each entry is a pair of (device ID, VSCC value).
2. Boot time: Intel® Management Engine firmware and BIOS perform the SoC register initialization.
   a. Read JEDEC ID from each flash device.
   b. Scan through VSCC tables pointed to by FLUMAP.
   c. Copy the entry from FLUMAP which matches device 0 into VSCC0, copy entry which matches device 1 into VSCC1.
3. In software sequencing, BIOS/Intel® Management Engine ensure QE bit is not cleared while doing status register write.

The flash controller uses the polling delays to set internal timers after initiating a write, erase, or RPMC operation. After the internal timer expires the flash controller begins polling the flash busy status in bit 0 of the status register. [OPEN: Move requirement to a standalone section] If the RPMC polling requirements bit is set to poll with RPMC Op2, then the flash controller issues an RPMC Op2 instead of a read status (05h). The RPMC Op2 operation uses “fast read” timing with 8 dummy bits between the address and valid data. Bit 0 of the first byte returned from RPMC Op2 is the busy bit.

The fields in this register pertain to cycles targeting addresses less than FLCOMP.C0DEN, i.e. within Component 0.

If the CPPTV bit is '0', software must configure the VSCC register appropriately. If the CPPTV bit is '1', the corresponding parameter values discovered via SFDP will be used. In most cases, software is not required to configure the VSCC register. However, if the SFDP table indicates an erase size other than 4k Byte, then software is required to program the VSCC.EO register with the correct erase opcode.

If the CPPTV bit is '0' and the VSCC register is not programmed and the Flash is operating in Flash Mode (as opposed to EEPROM mode), then software cannot use hardware sequencing. This requirement is not enforced by hardware, but is a requirement of the power-on usage model.

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00002000h

BAR and Offset: [BIOS_SPI_BAR0] + C4h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Component Property Parameter Table Valid (CPPTV):** This bit is set to a 1 if the Flash Controller detects a valid SFDP Component Property Parameter Table in Component 0. ***Note:*** If this bit is set software must not overwrite bits that were initialized by hardware via SFDP discovery.
30	0x0 RW/L	**Vendor Component Lock (VCL):** 0 = The lock bit is not set. 1 = The Vendor Component Lock bit is set. This register locks itself when set.
29	0x0 RW/V/L	**64k Erase Valid (EO_64k_VALID):** 0 = The EO_64k opcode is not valid. 1 = The EO_64k opcode is valid.
28	0x0 RW/V/L	**4k Erase Valid (EO_4k_VALID):** 0 = The EO_4k opcode is not valid. 1 = The EO_4k opcode is valid.
27	0x0 RW/L	**RPMC Supported (RPMC_SUPPORTED):** 0 = The device does not support RPMC. 1 = The device supports RPMC.
26	0x0 RW/V/L	**Deep Powerdown Supported (DEEP_PWRDN_SUPPORTED):** 0 = The device does not support Deep Powerdown. 1 = The device supports Deep Powerdown.
25	0x0 RW/V/L	**Suspend/Resume Supported (SUSPEND_RESUME_SUPPORTED):** 0 = The device does not support Suspend/Resume. 1 = The device supports Suspend/Resume.
24	0x0 RW/V/L	**Soft Reset Supported (SOFT_RST_SUPPORTED):** 0 = The device does not support Soft Reset. 1 = The device supports Soft Reset.
23:16	0x0 RW/V/L	**64k Erase Opcode (EO_64k):** This register is programmed with the Flash 64k sector erase instruction opcode for component 0. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit.
15:8	0x20 RW/V/L	**4k Erase Opcode (EO_4k):** This register is programmed with the Flash 4k subsector erase instruction opcode for component 0. Software must program this register if the SFDP table for this component does not show 4 k Byte erase capability. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit.
7:5	0x0 RW/V/L	**Quad Enable Requirements (QER):** • 000 Part does not require a Quad Enable bit to be set, either because Quad is not supported or because the manufacturer somehow permanently enables Quad capability. • 001 Part requires bit 9 in status register 2 to be set to enable quad IO. Writing one byte to status register clears all bits in register 2, therefore status register writes MUST be two bytes. • 010 Part requires bit 6 of status register 1 to be set to enable quad IO. • 011 Part requires bit 7 of the configuration register to be set to enable Quad. • 100 Part requires bit 9 in status register 2 to be set to enable quad IO. Writing one byte to the status register does not clear the second byte. This register is locked by the Vendor Component Lock (VCL) bit. If the SFDP table contains this information, the flash controller loads these bits from the table. The flash controller uses this information to prevent clearing the QE bit in the flash device's status register when WSR=1.
4	0x0 RW/V/L	**Write Enable on Write Status (WEWS):** 0 = 50h is the opcode to enable a status register write. 1 = 06h is the opcode to enable a status register write. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit. ***Note:*** Hardware ignores the state of this bit.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/V/L	**Write Status Required (WSR):** 0 = No requirement to write to the Write Status Register prior to a write 1 = A write is required to the Write Status Register prior to write and erase to remove any protection. This is required for SST components. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit. ***Note:*** Hardware ignores the state of this bit.
2	0x0 RW/V/L	**Write Granularity (WG):** 0 = Reserved. 1 = 64 Byte. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit. ***Note:*** Hardware ignores the state of this bit.
1:0	0x0 RW/L	**Reserved (RSVD):** Reserved.

60.3.49 Vendor Specific Component Capabilities for Component 1 (BIOS_SFDP1_VSCC1)—Offset C8h

Note: Intel is planning to deprecates support for non-SFDP capable flash devices.

See 31.1, Section 4)a). The fields in this register pertain to cycles targeting addresses greater than or equal to FLCOMP.C0DEN, i.e. outside of Component 0. The lockable bits in this register are locked when either CPPTV is set to '1' by hardware or when VCL is '1'.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + C8h

Default: 00002000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Component Property Parameter Table Valid (CPPTV):** This bit is set to a 1 if the Flash Controller detects a valid SFDP Component Property Parameter Table in Component 1. ***Note:*** If this bit is set software must not overwrite bits that were initialized by hardware via SFDP discovery.
30	0x0 RO	**Reserved (RSVD):** Reserved.
29	0x0 RW/V/L	**64k Erase Valid (EO_64k_VALID):** 0 = The EO_64k opcode is not valid. 1 = The EO_64k opcode is valid.
28	0x0 RW/V/L	**4k Erase Valid (EO_4k_VALID):** 0 = The EO_4k opcode is not valid. 1 = The EO_4k opcode is valid.
27	0x0 RW/L	**RPMC Supported (RPMC_SUPPORTED):** 0 = The device does not support RPMC. 1 = The device supports RPMC.
26	0x0 RW/V/L	**Deep Powerdown Supported (DEEP_PWRDN_SUPPORTED):** 0 = The device does not support Deep Powerdown. 1 = The device supports Deep Powerdown.
25	0x0 RW/V/L	**Suspend/Resume Supported (SUSPEND_RESUME_SUPPORTED):** 0 = The device does not support Suspend/Resume. 1 = The device supports Suspend/Resume.
24	0x0 RW/V/L	**Soft Reset Supported (SOFT_RST_SUPPORTED):** 0 = The device does not support Soft Reset. 1 = The device supports Soft Reset.
23:16	0x0 RW/V/L	**64k Erase Opcode (EO_64k):** This register is programmed with the Flash 64k sector erase instruction opcode for component 1. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit.
15:8	0x20 RW/V/L	**4k Erase Opcode (EO_4k):** This register is programmed with the Flash 4k subsector erase instruction opcode for component 1. Software must program this register if the SFDP table for this component does not show 4 k Byte erase capability. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit.

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 RW/V/L	**Quad Enable Requirements (QER):** • 000 Part does not require a Quad Enable bit to be set, either because Quad is not supported or because the manufacturer somehow permanently enables Quad capability. • 001 Part requires bit 9 in status register 2 to be set to enable quad IO. Writing one byte to status register clears all bits in register 2, therefore status register writes MUST be two bytes. • 010 Part requires bit 6 of status register 1 to be set to enable quad IO. • 011 Part requires bit 7 of the configuration register to be set to enable Quad. • 100 Part requires bit 9 in status register 2 to be set to enable quad IO. Writing one byte to the status register does not clear the second byte. This register is locked by the Vendor Component Lock (VCL) bit. If the SFDP table contains this information, the flash controller loads these bits from the table. The flash controller uses this information to prevent clearing the QE bit in the flash device's status register when WSR=1.
4	0x0 RW/V/L	**Write Enable on Write Status (WEWS):** 0 = 50h is the opcode to enable a status register write. 1 = 06h is the opcode to enable a status register write. Must be set to '1' for Intel's Blanshard Flash Component and for Atmel. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit. ***Note:*** Hardware ignores the state of this bit.
3	0x0 RW/V/L	**Write Status Required (WSR):** 0 = No requirement to write to the Write Status Register prior to a write. 1 = A write is required to the Write Status Register prior to write and erase to remove any protection. This is required for SST components. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit. ***Note:*** Hardware ignores the state of this bit.
2	0x0 RW/V/L	**Write Granularity (WG):** 0 = Reserved. 1 = 64 Byte. This register is locked by the Vendor Component Lock (VCL) bit or the CPPTV bit. ***Note:*** Hardware ignores the state of this bit.
1:0	0x0 RW/L	**Reserved (RSVD_1):** Reserved.

60.3.50 Parameter Table Index (BIOS_PTINX)—Offset CCh

Observability control for Component Property Tables.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + CCh

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15:14	0x0 RW	**Supported Parameter Table (SPT):** Selects which supported parameter table to observe. • 00: Component 0 Property Parameter Table. • 01: Component 1 Property Parameter Table. • 10: Reserved. • 11: Reserved.
13:12	0x0 RW	**Header or Data (HORD):** Select parameter table header DW vs Data DW. • 00: SFDP Header. • 01: Parameter Table Header. • 10: Data. • 11: Reserved.
11:2	0x0 RW	**Parameter Table DW Index (PTDWI):** Selects the DW offset within the parameter table to observe.
1:0	0x0 RO	**Reserved (RSVD_1):** Reserved.

60.3.51 Parameter Table Data (BIOS_PTDATA)—Offset D0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + D0h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RO/V	**Parameter Table DW Data (PTDWD):** Returns the DW of data to observe as selected in the Parameter Table Index register. ***Note:*** The returned value of reserved fields in the SFDP header or table must be ignored by software. The flash controller may return either 0 or 1 for these fields.

60.3.52 SPI Bus Requester Status (BIOS_SBRS)—Offset D4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + D4h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**TPM access ongoing (TPM_ACC_ONG):**
30:18	0x0 RO	**Reserved (RSVD):** Reserved.
17:15	0x0 RO/V	**Master 6 Status (M6STATUS):** See description under M1STATUS.
14:12	0x0 RO/V	**Master 5 Status (M5STATUS):** See description under M1STATUS.
11:9	0x0 RO/V	**Master 4 Status (M4STATUS):** See description under M1STATUS.
8:6	0x0 RO/V	**Master 3 Status (M3STATUS):** See description under M1STATUS.
5:3	0x0 RO/V	**Master 2 Status (M2STATUS):** See description under M1STATUS.
2:0	0x0 RO/V	**Master 1 Status (M1STATUS):** Indicates whether this master has an outstanding transaction enqueued or in flight and the transaction type. • 0xx: No transaction. • 100: Flash read transaction. • 101: Flash write transaction. • 110: Flash erase transaction. • 111: Flash RPMC transaction.

60.3.53 Flash Region 12 (BIOS_FREG12)—Offset E0h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + E0h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 12 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG12.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x0 RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 12 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG12.Region Base.

60.3.54 Flash Region 13 (BIOS_FREG13)—Offset E4h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + E4h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 13 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG13.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x0 RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 13 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG13.Region Base.

60.3.55 Flash Region 14 (BIOS_FREG14)—Offset E8h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + E8h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 14 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG14.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x0 RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 14 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG14.Region Base.

60.3.56 Flash Region 15 (BIOS_FREG15)—Offset ECh

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + ECh

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**Reserved (RSVD):** Reserved.
30:16	0x0 RO/V	**Region Limit (RL):** This specifies address bits 26:12 for the Region 15 Limit. The value in this register is loaded from the contents in the Flash Descriptor.FLREG15.Region Limit.
15	0x0 RO	**Reserved (RSVD_1):** Reserved.
14:0	0x0 RO/V	**Region Base (RB):** This specifies address bits 26:12 for the Region 15 Base. The value in this register is loaded from the contents in the Flash Descriptor.FLREG15.Region Base.

60.3.57 Set Strap Msg Lock (SSML)—Offset F0h

Lockable: Yes

Power Well: Resume

reset_type= wrsmrst#.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + F0h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Reserved.
0	0x0 RW/L	**Set_Strap Lock (SSL):** When set to '1', all of SSML, SSMC and SSMD is locked, including this Lock bit. Note that this bit is reset on CF9 resets. reset_type= wrsmrst#

60.3.58 Set Strap Msg Control (SSMC)—Offset F4h

Lockable: Yes

Power Well: DSW

reset_type= dsw_pok

The DSW bits are all cleared by dsw_pok, but must not be cleared by CF9h resets.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + F4h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved (RSVD):** Reserved.
0	0x0 RW/L	**Set_Strap Mux Select (SSMS):** When set to '1', the Set strap message bits [47:32] come from the Set_Strap Msg Data register. This bit is reset by the RSMRST# pin only. When '0', the Set-Strap data continues to come from the soft straps themselves. reset_type=dsw_pok This register field is locked by the Set Strap Lock (SSML.SSL) bit.

60.3.59 Set Strap Msg Data (SSMD)—Offset F8h

Lockable: Yes
Power Well: DSW
Reset Type: dsw_pok

This register is used to provide a BIOS programmable sticky register which contains data that will be used in the Set-Strap type 1 msg on subsequent resets. The bits in the message control certain CPU features, for which see the CPU spec. These bits are in the resume well, so only reset on G3.

The usage model is that on each reset BIOS will check the state of the CPU. If the state is correct, then BIOS continues. If not, then BIOS writes the SSMD and SSMC registers and does a CF9 reset. On the reset the value of what was written to SSMD takes effect. Note that some mobile platforms force G3 on S5 requests. For those platforms, if the user/BIOS wants to have these bits set, there will be 2 resets on every power-on. If the platform accepts the default of '0' for these controls, then there is only one reset. The bits are in DSW and not RTC well because this allows a user upgrade, assuming the user unplugged the system before doing the upgrade, to revert to a setting of 0. This should reduce any interoperability concerns regarding user upgrades. The DSW bits are all cleared dsw_pok, and must not be cleared by CF9h resets.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + F8h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15:0	0x0 RW/L	**Set_Strap Data (SSD):** When SSMS is '1', then this data is sent in the Set-Strap msg Type 1 upon reset. This data is sent in the 2nd DW of data, bits[15:0]. reset_type=int_sus_pok This register field is locked by the Set Strap Lock (SSML.SSL) bit.

60.3.60 RPMC SFDP Table (BIOS_RPMC0_D0)—Offset 108h

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 108h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RPMC SFDP Table dword 0 Device 0 (RPMC0_D0):**

60.3.61 RPMC SFDP Table (BIOS_RPMC1_D0)—Offset 10Ch

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 10Ch

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RPMC SFDP Table dword 1 Device 0 (RPMC1_D0):**

60.3.62 RPMC SFDP Table (BIOS_RPMC0_D1)—Offset 110h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 110h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RPMC SFDP Table dword 0 Device 1 (RPMC0_D1):**

60.3.63 RPMC SFDP Table (BIOS_RPMC1_D1)—Offset 114h

Type: Memory Mapped I/O Register (Size: 32 bits)

Default: 00000000h

BAR and Offset: [BIOS_SPI_BAR0] + 114h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**RPMC SFDP Table dword 0 Device 1 (RPMC1_D1):**

60.3.64 BIOS Master Read Access Permissions (BIOS_BM_RAP)—Offset 118h

This register is implemented in DNV, LBG and subsequent programs.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 118h

Default: 000000C2h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15:0	0xc2 RO/V	**BIOS Master Read Access Permissions (BMRAP) (BMRAP):** Each bit [15:0] corresponds to Regions [15:0]. If the bit is set, this master can read that particular region through register accesses. The contents of this register are that of the Flash Descriptor.Flash Master 1.Master Region Read Access OR a particular master has granted BIOS read permissions in their Master Read Access Grant register OR the Flash Descriptor Security Override strap is set. BIOS has read access to its own Region 1, 6 and 7 by default. Thus, the reset default of this field will be read as "C2h".

60.3.65 BIOS Master Write Access Permissions (BIOS_BM_WAP)—Offset 11Ch

This register is implemented in DNV, LBG and subsequent programs.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 11Ch

Default: 00000042h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD):** Reserved.
15:0	0x42 RO/V	**BIOS Master Write Access Permissions (BMWAP) (BMWAP):** Each bit [15:0] corresponds to Regions [15:0]. If the bit is set, this master can erase and write that particular region through register accesses. The contents of this register are that of the Flash Descriptor.Flash Master 1.Master Region Write Access OR a particular master has granted BIOS write permissions in their Master Write Access Grant register OR the Flash Descriptor Security Override strap is set. BIOS has write access to its own Region 1 and 6 by default. Thus, the reset default of this field will be read as "42h".

60.3.66 IE Flash Protected Range 0 (BIOS_IE_PR0)—Offset 1B0h

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 1B0h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RO/V	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RO/V	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RO/V	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.67 IE Flash Protected Range 1 (BIOS_IE_PR1)—Offset 1B4h

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 1B4h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RO/V	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RO/V	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RO/V	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.68 IE Flash Protected Range 2 (BIOS_IE_PR2)—Offset 1B8h

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 1B8h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RO/V	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RO/V	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RO/V	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.69 IE Flash Protected Range 3 (BIOS_IE_PR3)—Offset 1BCh

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 1BCh

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RO/V	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RO/V	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RO/V	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

60.3.70 IE Flash Protected Range 4 (BIOS_IE_PR4)—Offset 1C0h

This register can not be written when the FLOCKDN bit is set to 1.

Type: Memory Mapped I/O Register (Size: 32 bits)

BAR and Offset: [BIOS_SPI_BAR0] + 1C0h

Default: 00000000h

BIOS_SPI_BAR0 Type: PCI Configuration Register (Size: 32 bits)
BIOS_SPI_BAR0 Reference: [B:0, D:31, F:5] + 10h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO/V	**Write Protection Enable (WPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that writes and erases directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
30:16	0x0 RO/V	**Protected Range Limit (PRL):** This field corresponds to FLA address bits 26:12 and specifies the upper limit of the protected range. Address bits 11:0 are assumed to be FFFh for the limit comparison. Any address greater than the value programmed in this field is unaffected by this protected range.
15	0x0 RO/V	**Read Protection Enable (RPE):** When set, this bit indicates that the Base and Limit fields in this register are valid and that read directed to addresses between them (inclusive) must be blocked by hardware. The base and limit fields are ignored when this bit is cleared.
14:0	0x0 RO/V	**Protected Range Base (PRB):** This field corresponds to FLA address bits 26:12 and specifies the lower base of the protected range. Address bits 11:0 are assumed to be 000h for the base comparison. Any address less than the value programmed in this field is unaffected by this protected range.

§ §

61 Programmable Interval Timer - Legacy

61.1 Introduction and Index

The host-accessible registers for the Programmable Interval Timer (PIT) are described here.

The legend for the register access codes are described in Chapter 43, “Introduction.”

61.1.1 Host I/O Space—Fixed Address

An index of the registers that are accessible in Host I/O Space is shown here.

61.2 Registers in I/O Space—Fixed Addresses

Table 61-1. Summary of I/O Registers—Fixed I/O Ports

I/O Port (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
40	1	C4	"Counter 0 - Interval Timer Status Byte Format Register (C0_ITSBFR)—Offset 40h" on page 2876
42	1	C4	"Counter 2 - Interval Timer Status Byte Format Register (C2_ITSBFR)—Offset 42h" on page 2877
43	1	00	"Timer Control Word Register (TCW)—Offset 43h" on page 2878
42	1	00	"Counter 2 - Counter Access Ports Register (C2_CAPR)—Offset 42h" on page 2879
43	1	C0	"Read Back Command (RBC)—Offset 43h" on page 2880
43	1	00	"Counter Latch Command (CLC)—Offset 43h" on page 2881
61	1	00	"NMI Status and Control (NMI_STS_CNT)—Offset 61h" on page 2882

These registers are accessed in Host I/O Space through fixed I/O Port addresses.

61.2.1 Counter 0 - Interval Timer Status Byte Format Register (C0_ITSBFR)—Offset 40h

Each counter's status byte can be read following a Read Back Command. If latch status is chosen (bit 4=0, Read Back Command) as a read back option for a given counter, the next read from the counter's Counter Access Ports Register (I/O Port 40h for counter 0 and I/O Port 42h for counter 2) returns the status byte. The status byte returns the following:

Type: I/O Register
(Size: 8 bits)

I/O Port: 40h

Default: C4h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Counter OUT Pin State (COPS):** • When this bit is a 1, the OUT pin of the counter is also a 1. • When this bit is a 0, the OUT pin of the counter is also a 0. **Power Well:** Core
6	0x1 RO	**Count Register Status (CRSTS):** This bit indicates when the last count written to the Count Register (CR) has been loaded into the counting element (CE). The exact time this happens depends on the counter mode, but until the count is loaded into the counting element (CE), the count value will be incorrect. • 0 - Count has been transferred from CR to CE and is available for reading. • 1 - Null Count. Count has not been transferred from CR to CE and is not yet available for reading. **Power Well:** Core
5:4	0x0 RO	**Read/Write Selection Status (RW_SLT_STS):** These reflect the read/write selection made through bits[5:4] of the control register. The binary codes returned during the status read match the codes used to program the counter read/write selection. • 00 - Counter Latch Command • 01 - Read/Write Least Significant Byte (LSB) • 10 - Read/Write Most Significant Byte (MSB) • 11 - Read/Write LSB then MSB **Power Well:** Core
3:1	0x2 RO	**Mode Selection Status (MD_SLT_STS):** These bits return the counter mode programming. The binary code returned matches the code used to program the counter mode, as listed under the bit function above. • 000 - Out signal on end of count (=0) • 001 - Hardware retriggerable one-shot • x10 - Rate generator (divide by n counter) • x11 - Square wave output • 100 - Software triggered strobe • 101 - Hardware triggered strobe **Power Well:** Core
0	0x0 RO	**Countdown Type Status (CDT_STS):** This bit reflects the current countdown type, ether 0 for binary countdown or a 1 for binary coded decimal (BCD) countdown. **Power Well:** Core

61.2.2 Counter 2 - Interval Timer Status Byte Format Register (C2_ITSBFR)—Offset 42h

Each counter's status byte can be read following a Read Back Command. If latch status is chosen (bit 4=0, Read Back Command) as a read back option for a given counter, the next read from the counter's Counter Access Ports Register (I/O Port 40h for counter 0 and I/O Port 42h for counter 2) returns the status byte. The status byte returns the following:

Type: I/O Register
(Size: 8 bits)

I/O Port: 42h

Default: C4h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RO	**Counter OUT Pin State (COPS):** • When this bit is a 1, the OUT pin of the counter is also a 1. • When this bit is a 0, the OUT pin of the counter is also a 0. **Power Well:** Core
6	0x1 RO	**Count Register Status (CRSTS):** This bit indicates when the last count written to the Count Register (CR) has been loaded into the counting element (CE). The exact time this happens depends on the counter mode, but until the count is loaded into the counting element (CE), the count value will be incorrect. • 0 - Count has been transferred from CR to CE and is available for reading. • 1 - Null Count. Count has not been transferred from CR to CE and is not yet available for reading. **Power Well:** Core
5:4	0x0 RO	**Read/Write Selection Status (RW_SLT_STS):** These reflect the read/write selection made through bits[5:4] of the control register. The binary codes returned during the status read match the codes used to program the counter read/write selection. • 00 - Counter Latch Command • 01 - Read/Write Least Significant Byte (LSB) • 10 - Read/Write Most Significant Byte (MSB) • 11 - Read/Write LSB then MSB **Power Well:** Core
3:1	0x2 RO	**Mode Selection Status (MD_SLT_STS):** These bits return the counter mode programming. The binary code returned matches the code used to program the counter mode, as listed under the bit function above. • 000 - Out signal on end of count (=0) • 001 - Hardware retriggerable one-shot • x10 - Rate generator (divide by n counter) • x11 - Square wave output • 100 - Software triggered strobe • 101 - Hardware triggered strobe **Power Well:** Core
0	0x0 RO	**Countdown Type Status (CDT_STS):** This bit reflects the current countdown type, ether 0 for binary countdown or a 1 for binary coded decimal (BCD) countdown. **Power Well:** Core

61.2.3 Timer Control Word Register (TCW)—Offset 43h

This register is programmed prior to any counter being accessed to specify counter modes. Following reset, the control words for each register are undefined and each counter output is 0. Each timer must be programmed to bring it into a known state. There are two special commands that can be issued to the counters through this register, the Read Back Command and the Counter Latch Command. When these commands are chosen, several bits within this register are redefined.

Type: I/O Register (Size: 8 bits)

I/O Port: 43h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 WO	**Counter Select (CNT_SLT):** The Counter Selection bits select the counter the control word acts upon as shown below. The Read Back Command is selected when bits[7:6] are both 1. • 00 - Counter 0 select • 01 - Reserved • 10 - Counter 2 select • 11 - Read Back Command **Power Well:** Core
5:4	0x0 WO	**Read/Write Select: (RW_SLT):** These bits are the read/write control bits. The actual counter programming is done through the counter port (40h for counter 0 and 42h for counter 2). • 00 - Counter Latch Command • 01 - Read/Write Least Significant Byte (LSB) • 10 - Read/Write Most Significant Byte (MSB) • 11 - Read/Write LSB then MSB **Power Well:** Core
3:1	0x0 WO	**Counter Mode Selection (CNT_MD_SLTN):** These bits select one of six possible modes of operation for the selected counter. • 000 - Out signal on end of count (=0) • 001 - Hardware retriggerable one-shot • x10 - Rate generator (divide by n counter) • x11 - Square wave output • 100 - Software triggered strobe • 101 - Hardware triggered strobe **Power Well:** Core
0	0x0 WO	**Binary/BCD Countdown Select (B_BCD_CNTDWN_SLT):** • 0 - Binary countdown is used. The largest possible binary count is 2^{16} • 1 - Binary coded decimal (BCD) count is used.The largest possible BCD count is 10^4 **Power Well:** Core

61.2.4 Counter 2 - Counter Access Ports Register (C2_CAPR)—Offset 42h

Type: I/O Register
(Size: 8 bits)

I/O Port: 42h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW/V	**Counter Port (CP):** Each counter port address is used to program the 16-bit Count Register. The order of programming, either LSB only, MSB only, or LSB then MSB, is defined with the Interval Counter Control Register at I/O Port 43h. The counter port is also used to read the current count from the Count Register, and return the status of the counter programming following a Read Back Command. **Power Well:** Core

61.2.5 Read Back Command (RBC)—Offset 43h

The Read Back Command is used to determine the count value, programmed mode, and current states of the OUT pin and Null count flag of the selected counter or counters.

Type: I/O Register (Size: 8 bits)

I/O Port: 43h

Default: C0h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x3 WO	**Read Back Command (RBC):** Must be 11 to select the Read Back Command (RBC). Otherwise, see "Counter Latch Command (CLC)—Offset 43h" on page 2881. **Power Well:** Core
5	0x0 WO	**Latch Count of Selected Counters (LCSC):** • 0 - Current count value of the selected counters will be latched • 1 - Current count will not be latched **Power Well:** Core
4	0x0 WO	**Latch Status of Selected Counters (LSSC):** • 0 - Status of the selected counters will be latched • 1 - Status will not be latched **Power Well:** Core
3	0x0 WO	**Counter 2 Select (CNT_2_SLT):** When set to 1, Counter 2 count and/or status will be latched **Power Well:** Core
2	0x0 WO	**Reserved (RSVD):** Reserved **Power Well:** Core
1	0x0 WO	**Counter 0 Select (CNT_0_SLT):** When set to 1, Counter 0 count and/or status will be latched. **Power Well:** Core
0	0x0 WO	**Reserved (RSVD_1):** Must be 0. **Power Well:** Core

61.2.6 Counter Latch Command (CLC)—Offset 43h

The Counter Latch Command latches the current count value. This command is used to insure that the count read from the counter is accurate.

Type: I/O Register (Size: 8 bits)

I/O Port: 43h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 WO	**Counter Selection (CNT_SLT):** These bits select the counter for latching. • 00 - Counter 0 • 01 - Reserved • 10 - Counter 2 ***Note:*** If 11 is written, then the write is interpreted as a Read Back Command (RBC). See "Read Back Command (RBC)—Offset 43h" on page 2880. **Power Well:** Core
5:4	0x0 WO	**Counter Latch Command (CLC):** Write 00 to select the Counter Latch Command. **Power Well:** Core
3:0	0x0 WO	**Reserved (RSVD):** Must be 0. **Power Well:** Core

61.2.7 NMI Status and Control (NMI_STS_CNT)—Offset 61h

NMI Status and Control Register

Type: I/O Register
(Size: 8 bits)

I/O Port: 61h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**SERR# NMI Source Status (SERR_NMI_STS):** This bit is set by any of the sources of the internal SERR signal of the SoC. This includes SERR assertions forwarded from the secondary PCI bus, error from a PCIe port, or internal Bus 0 functions that generate SERR#. Bit 2 must be cleared in this register in order for this bit to be set. This interrupt source is enabled by setting bit 2 to 0. To reset the interrupt, set bit 2 to 1 and then set it to 0. This bit is read-only. When writing to port 61h, this bit must be 0. **Power Well:** Core
6	0x0 RO	**IOCHK# NMI Source Status (IOCHK_NMI_STS):** This bit is set if an ISA/LPC agent (via SERIRQ) asserts IOCHK# and bit 3 is cleared in this register. This interrupt source is enabled by setting bit 3 to 0. To reset the interrupt, set bit 3 to 1 and then set it to 0. This bit is read-only. When writing to port 61h, this bit must be a 0. **Power Well:** Core
5	0x0 RO	**Timer Counter 2 OUT Status (TMR2_OUT_STS):** This bit reflects the current state of the 8254 Counter 2 output. Counter 2 must be programmed following any PCI reset for this bit to have a determinate value. When writing to port 61h, this bit must be a 0. **Power Well:** Core
4	0x0 RO	**Reserved (RSVD):** Will return 0 when read. Writes to this bit will be ignored. **Power Well:** Core
3	0x0 RW	**IOCHK# NMI Enable (IOCHK_NMI_EN):** • When this bit is a 1, IOCHK# NMIs are disabled and cleared. • When this bit is a 0, IOCHK# NMIs are enabled. **Power Well:** Core
2	0x0 RW	**PCI SERR# Enable (PCI_SERR_EN):** • When this bit is a 1, the SERR# NMIs are disabled and cleared. • When this bit is a 0, SERR# NMIs are enabled. **Power Well:** Core
1	0x0 RW	**Reserved (RSVD):** Unused **Power Well:** Core
0	0x0 RW	**Timer Counter 2 Enable (TIM_CNT2_EN):** When this bit is a 0, Counter 2 counting is disabled. Counting is enabled when this bit is 1. **Power Well:** Core

§ §

62 Real Time Clock - Legacy

62.1 Introduction and Index

The host-accessible registers for the Real Time Clock are described here.

The legend for the register access codes are described in Chapter 43, "Introduction."

62.1.1 Host I/O Space—Fixed Address

An index of the registers that are accessible in Host I/O Space is shown here. For a description of the RTC Configuration (RC) register see "RTC Configuration (RC)—Offset 3400h" on page 2900.

Table 62-1. Summary of I/O Registers—Fixed Address

I/O Port (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
70 (also 74)	1	80	"NMI Enable (and Real Time Clock Index) (NMI_EN)—Port 70h" on page 2888
71 (also 75)	1	n/a	"Real Time Clock Data—Port 71h" on page 2889
If RTC Configuration (RC) bit 2 = 0			
72 (also 76)	1	80	(Alias) "NMI Enable (and Real Time Clock Index) (NMI_EN)—Port 70h" on page 2888
73 (also 77)	1	n/a	(Alias) "Real Time Clock Data—Port 71h" on page 2889
If RTC Configuration (RC) bit 2 = 1			
72 (also 76)	1	0	"Real Time Clock Index to Extended RAM—Port 72h" on page 2889
73 (also 77)	1	n/a	"Real Time Clock Data—Port 73h" on page 2889

62.1.2 Host I/O Space—RTC Standard Static RAM Bank (Indexed Data)

An index of the registers that are accessible in Host I/O Space is shown here. The Index Value is provided by the RTC Standard RAM Index Register. If the Upper 128 Byte Enable (UE) bit is = 0, the Index value is aliased to the RTC Extended RAM Index Register. For the UE bit of the RC register see "RTC Configuration (RC)—Offset 3400h" on page 2900.

Table 62-2. Summary of RTC Standard Static RAM Bank — Indexed Data

Index Value (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0	1	00	"Seconds (Sec)—Index 0h" on page 2890
1	1	00	"Seconds Alarm (Sec_Alarm)—Index 1h" on page 2890
2	1	00	"Minutes—Index 2h" on page 2890
3	1	00	"Minutes Alarm (Minutes_Alarm)—Index 3h" on page 2891
4	1	00	"Hours—Index 4h" on page 2891
5	1	00	"Hours Alarm (Hours_Alarm)—Index 5h" on page 2891
6	1	00	"Day of Week (Day_of_Week)—Index 6h" on page 2892
7	1	00	"Day of Month (Day_of_Month)—Index 7h" on page 2892
8	1	00	"Month—Index 8h" on page 2892
9	1	00	"Year—Index 9h" on page 2893
A	1	20	"Register A (Register_A)—Index Ah" on page 2894
B	1	80	"Register B - General Configuration (Register_B)—Index Bh" on page 2895
C	1	00	"Register C - Flag Register (Register_C)—Index Ch" on page 2897
D	1	80	"Register D - Flag Register (Register_D)—Index Dh" on page 2898
E through 7F	1 (each access)	n/a	"User RAM—Index Eh through 7Fh" on page 2898

62.1.3 Host I/O Space—RTC Extended Static RAM Bank (Indexed Data)

An index of the registers that are accessible in Host I/O Space is shown here. The Index Value is provided by the RTC Extended RAM Index Register if the Upper 128 Byte Enable (UE) bit is = 1. For the UE bit of the RC register see "RTC Configuration (RC)—Offset 3400h" on page 2900.

Table 62-3. Summary of RTC Extended Static RAM Bank — Indexed Data

Index Value (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
0 through 7F	1 (each access)	n/a	"User RAM—Index 0h through 7Fh" on page 2899

62.1.4 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 62-4. Summary of Sideband Registers—0xD1

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
3400	00000000	"RTC Configuration (RC)—Offset 3400h" on page 2900
3414	00	"Backed Up Control (BUC)—Offset 3414h" on page 2901
3F04	00000000	"RTC Update In Progress SMI Control (UIPSMI)—Offset 3F04h" on page 2902
3418	00000000	"RTC Dynamic Clock Gating Control (RTCDCG)—Offset 3418h" on page 2903

62.2 Registers in I/O Space—Fixed Addresses

These registers are accessed in Host I/O Space through fixed I/O addresses.

62.2.1 NMI Enable (and Real Time Clock Index) (NMI_EN)—Port 70h

This register is write-only for normal operation. In Alternate-Access mode, this register can be read to find the NMI Enable status and the RTC index value.

Alternate-Access Mode is enabled by setting Alternate Access Mode Enable (AME), bit 17 of the 32-bit General Interrupt Control (GIC) register in relocatable Memory Space at offset D0_31FCh from SBREG_BAR.

When the Upper 128 Byte Enable (UE) bit of the RTC Configuration (RC) Register = 0, The NMI_EN register is aliased to I/O Ports 72h and 76h. See "RTC Configuration (RC)—Offset 3400h" on page 2900.

I/O Writes to 72h, 74h, and 76h do not affect the NMI Enable bit (bit 7 of 70h).

Type: I/O Register (Size: 8 bits)

I/O Port: 70h (aliased 74h. If UE = 0, also aliased to 72h and 76h)

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW/V	**NMI_EN# (NMI_EN):** When this bit is a 1, all NMI sources are disabled. When this bit is a 0, NMI sources are enabled. I/O Writes to 72h, 74h, and 76h do not affect the state of NMI_EN.
6:0	0x0 RW/V	**Real Time Clock Index (Address) (RTC_INDX):** This data goes to the RTC to select which register or CMOS RAM address is being accessed. **Power Well:** RTC

62.2.2 Real Time Clock Data—Port 71h

RTC data located at index address defined by RTC_INDX.

When the Upper 128 Byte Enable (UE) bit of the RTC Configuration (RC) Register = 0, The NMI_EN register is aliased to I/O Ports 73h and 77h. See "RTC Configuration (RC)—Offset 3400h" on page 2900.

Type: I/O Register
(Size: 8 bits)

I/O Port: 71h (aliased 75h. If UE = 0, also aliased to 73h and 77h)

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Real Time Clock Data:** This is the data located at RTC_INDX. The data is either an RTC register or CMOS RAM. **Power Well:** RTC

62.2.3 Real Time Clock Index to Extended RAM—Port 72h

This register is accessible only when the Upper 128 Byte Enable (UE) bit of the RTC Configuration (RC) Register = 1. If UE = 0, see "NMI Enable (and Real Time Clock Index) (NMI_EN)—Port 70h" on page 2888. For the RC register see "RTC Configuration (RC)—Offset 3400h" on page 2900.

Type: I/O Register
(Size: 8 bits)

I/O Port: 72h (aliased 76h)

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved:** Reserved.
6:0	0x0 RW	**Real Time Clock Extended Index (Address)** This data goes to the RTC to select which Extended CMOS RAM address is being accessed. **Power Well:** RTC

62.2.4 Real Time Clock Data—Port 73h

RTC data located at index address defined by the Real Time Clock Extended Index register. This register is accessible only when the Upper 128 Byte Enable (UE) bit of the RTC Configuration (RC) Register = 1. If UE = 0, see "Real Time Clock Data—Port 71h" on page 2889. For the RC register see "RTC Configuration (RC)—Offset 3400h" on page 2900.

Type: I/O Register
(Size: 8 bits)

I/O Port: 73h (aliased 77h)

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Real Time Clock Data:** This is the data located at the Extended RAM address defined by the Real Time Clock Extended Index register. The data is Extended CMOS RAM. **Power Well:** RTC

62.3 Registers in Host I/O Space—RTC Standard Static RAM Bank (Indexed Data)

62.3.1 Seconds (Sec)—Index 0h

RTC Index: 00h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current time second.

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** 0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Seconds (Sec):** Time Seconds **Power Well:** RTC

62.3.2 Seconds Alarm (Sec_Alarm)—Index 1h

RTC Index: 01h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores Seconds Alarm.

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** 1h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Seconds Alarm (Sec_Alarm):** Sec_Alarm **Power Well:** RTC

62.3.3 Minutes—Index 2h

RTC Index: 02h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current time Minutes.

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** 2h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Minutes:** Time Minutes **Power Well:** RTC

62.3.4 Minutes Alarm (Minutes_Alarm)—Index 3h

RTC Index: 03h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores Alarm Minutes.

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** 3h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Minutes Alarm (Minutes_Alarm):** Alarm Minutes **Power Well:** RTC

62.3.5 Hours—Index 4h

RTC Index: 04h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current time Hours.

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** 4h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Hours:** Time Hours **Power Well:** RTC

62.3.6 Hours Alarm (Hours_Alarm)—Index 5h

RTC Index: 05h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores Alarm Hours.

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** 5h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Hours Alarm (Hours_Alarm):** Alarm Hours **Power Well:** RTC

62.3.7 Day of Week (Day_of_Week)—Index 6h

RTC Index: 06h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current Day of Week.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: 6h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Day of Week (Day_of_Week):** This field indicates current Day of Week **Power Well:** RTC

62.3.8 Day of Month (Day_of_Month)—Index 7h

RTC Index: 07h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current Day of Month.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: 7h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Day of Month (Day_of_Month):** This field indicates current Day of Month **Power Well:** RTC

62.3.9 Month—Index 8h

RTC Index: 08h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current Month.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: 8h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Month:** This field indicates current Month **Power Well:** RTC

62.3.10 Year—Index 9h

RTC Index: 09h. Attribute: Read/Write. Default Value: Undefined. Size: 8-bit. This register stores current Year.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: 9h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Year:** This field indicates current Year **Power Well:** RTC

62.3.11 Register A (Register_A)—Index Ah

RTC Index: 0Ah Attribute: Read/Write Default Value: Undefined Size: 8-bit Lockable: No Power Well: RTC This register is used for general configuration of the RTC functions. None of the bits are affected by RSMRST# or any other reset signal.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: Ah

Default: 20h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**UPDATE IN PROGRESS (UIP):** This bit may be monitored as a status flag. When asserted as a 1, the update is soon to occur or is in progress. If 0, the update cycle will not start for at least 488 s. The time, calendar, and alarm information in RAM is always available when the UIP bit is 0. The ICH provides the ability to generate SMI# based on either the 0-to-1 or 1-to-0 transition of this bit. This can be useful for work-arounds and debug in silicon. **Power Well:** RTC
6:4	0x2 RW	**Division Chain Select (DV_2_0):** These three bits control the divider chain for the oscillator, and are not affected by RSMRST# or any other reset signal. DV(2) corresponds to bit 6. • 010 Normal Operation • 11X Divider Reset • 101 Bypass 15 stages (test mode only) • 100 Bypass 10 stages (test mode only) • 011 Bypass 5 stages (test mode only) • 001 Invalid • 000 Invalid **Power Well:** RTC
3:0	0x0 RW	**Rate Select (RS_3_0):** Selects one of 13 taps of the 15 stage divider chain. The selected tap can generate a periodic interrupt if the PIE bit is set in Register B. Otherwise this tap will set the PF flag of Register C. If the periodic interrupt is not to be used, these bits should all be set to zero. RS3 corresponds to bit 3. The Periodic Rate is as follows: • 0000 Interrupt never toggles • 0001 3.90625 ms • 0010 7.8125 ms • 0011 122.070 s • 0100 244.141 s • 0101 488.281 s • 0110 976.5625 s • 0111 1.953125 ms • 1000 3.90625 ms • 1001 7.8125 ms • 1010 15.625 ms • 1011 31.25 ms • 1100 62.5 ms • 1101 125 ms • 1110 250 ms • 1111 500 ms **Power Well:** RTC

62.3.12 Register B - General Configuration (Register_B)—Index Bh

RTC Index: 0Bh Attribute: Read/Write Default Value: U0U00UUU Size: 8-bit Lockable: No Power Well: RTC

Type: RTC Standard Static RAM (Size: 8 bits) **Index:** Bh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Update Cycle Inhibit (SET):** Enables/Inhibits the update cycles. When SET is 0, update cycle occurs normally once each second. If set to one, a current update cycle will abort and subsequent update cycles will not occur until SET is returned to zero. When set is one, the BIOS may initialize time and calendar bytes safely. This bit is not affected by RSMRST# nor any other reset signal. ***Note:*** Software must ensure this bit is at least transitioned from '1' to '0' once whenever the RTC coin battery is inserted. This is to ensure that the internal RTC time updates occur properly. **Power Well:** RTC
6	0x0 RW	**Periodic Interrupt Enable (PIE):** If set to 1, the Periodic Interrupt Enable (PIE) bit allows an interrupt to occur with a time base set with the RS bits of register A. This bit is cleared by RSMRST#, but not on any other reset **Power Well:** RTC
5	0x0 RW	**Alarm Interrupt Enable (AIE):** If set to one, the Alarm Interrupt Enable (AIE) bit allows an interrupt to occur when the AF is one as set from an alarm match from the update cycle. An alarm can occur once a second, one an hour, once a day, or once a month. This bit is cleared by RTEST# #, but not on any other reset **Power Well:** RTC
4	0x0 RW	**Update-ended Interrupt Enable: (UIE):** If set to one, the Update-ended Interrupt Enable (UIE) bit allows an interrupt to occur when the update cycle ends. This bit is cleared by RSMRST#, but not on any other reset **Power Well:** RTC
3	0x0 RW	**Square Wave Enable (SQWE):** The Square Wave Enable bit serves no function in this device, yet is left in this register bank to provide compatibility with the Motorola 146818B. There is not SQW pin on this device. This bit is cleared by RSMRST#, but not on any other reset. **Power Well:** RTC
2	0x0 RW	**Data Mode (DM):** The Data Mode (DM) bit specifies either binary or BCD data representation. A one denotes binary, and zero denotes BCD. This bit is not affected by RSMRST# nor any other reset signal. **Power Well:** RTC
1	0x0 RW	**Hour Format (HOURFORM):** This bit indicates the hour byte format. If one, twenty-four hour mode is selected. If zero, twelve-hour mode is selected. In twelve hour mode, the seventh bit represents AM as zero and PM as one. This bit is not affected by RSMRST# nor any other reset signal. **Power Well:** RTC

Bit Range	Default & Access	Field Name (ID): Description
0	0x0 RW	**Daylight Savings Enable (DSE):** The Daylight Savings Enable bit triggers two special hour updates per year when set to one. One is on the first Sunday in April, where time increments from 1:59:59 AM to 3:00:00 AM. The other is the last Sunday in October when the time first reaches 1:59:59 AM, it is changed to 1:00:00 AM. The time must increment normally for at least two update cycles (seconds) previous to these conditions for the time change to occur properly. These special update conditions do not occur when the DSE bit is set to zero. The days for the hour adjustment are those specified in United States federal law as of 1987, which is different than previous years. This bit is not affected by RSMRST# nor any other reset signal. If BUC.DSO bit is set, the DSE bit continues to be a R/W bit, but Daylight Saving is disabled regardless of the DSE bit. **Power Well:** RTC

62.3.13 Register C - Flag Register (Register_C)—Index Ch

RTC Index: 0Ch Attribute: Read-Only (Writes have no effect). Default Value: 00U00000 Size: 8-bit Lockable: No Power Well: RTC

Type: RTC Standard Static RAM (Size: 8 bits)

Index: Ch

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Interrupt Request Flag (IRQF):** Interrupt Request Flag = PF * PIE + AF * AIE + UF * UFE. This also causes the RTC Interrupt to be asserted. This bit is cleared upon RSMRST# or a read of Register C. **Power Well:** RTC
6	0x0 RO	**Periodic Interrupt Flag (PF):** Periodic interrupt Flag will be one when the tap as specified by the RS bits of register A is one. If no taps are specified, this flag bit will remain at zero. This bit is cleared upon RSMRST# or a read of Register C. **Power Well:** RTC
5	0x0 RO	**Alarm Flag (AF):** Alarm Flag will be high after all Alarm values match the current time. This bit is cleared upon RTEST# or a read of Register C. **Power Well:** RTC
4	0x0 RO	**Update-ended Flag (UF):** Updated-ended flag will be high immediately following an update cycle for each second. The bit is cleared upon RSMRST# or a read of Register C. **Power Well:** RTC
3:0	0x0 RO	**Reserved (RSVD):** Will always report 0 **Power Well:** RTC

62.3.14 Register D - Flag Register (Register_D)—Index Dh

RTC Index: 0Dh Attribute: Read/Write Default Value: 10UUUUUU Size: 8-bit Lockable: No Power Well: RTC

Type: RTC Standard Static RAM (Size: 8 bits)

Index: Dh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Valid RAM and Time Bit (VRT):** This bit is hard-wired to 1 in the RTC power well. This bit should always be written as a 0 for write cycle, however it will return a 1 for read cycles. **Power Well:** RTC
6	0x0 RW	**Reserved (RSVD):** This bit always returns a 0 and should be set to 0 for write cycles. **Power Well:** RTC
5:0	0x0 RW	**Date Alarm (Date_Alarm):** These bits store the date of month alarm value. If set to 000000, then a dont care state is assumed. The host must configure the dates alarm for these bits to do anything, yet they can be written at any time. If the date alarm is not enabled, these bits will return zeros to mimic the functionality of the Motorola 146818B. These bits are not affected by any reset assertion. **Power Well:** RTC

62.3.15 User RAM—Index Eh through 7Fh

Access to 114 bytes of user Static RAM located in the RTC Power Well of the SoC.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: Dh through 7Fh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7:0	n/a RW	**User RAM Data:** **Power Well:** RTC

62.4 Registers in Host I/O Space—RTC Extended Static RAM Bank (Indexed Data)

62.4.1 User RAM—Index 0h through 7Fh

Access to 128 bytes of user Static RAM located in the RTC Power Well of the SoC.

Type: RTC Standard Static RAM (Size: 8 bits)

Index: 0h through 7Fh

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7:0	n/a RW	**User RAM Data:** **Power Well:** RTC

62.5 Sideband Registers

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

62.5.1 RTC Configuration (RC)—Offset 3400h

All bits in this register are in the Primary Well and cleared by host_side_rst_b.

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0xD1] + 3400h
Host Memory Space: SBREG_BAR + 0xD10000 + 3400h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1L	**Bios Interface Lock-Down (BILD):** When set, prevents RTC version of TS (BUC.TS) from being changed. This bit can only be written from 0 to 1 once. This BILD bit has different function compared to the LPC and SPI version but BIOS should set all the corresponding bits after reset in order to lock down the BIOS interface correctly. **Power Well:** Core
30:7	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
6	0x0 RW	**RTC High Power Mode HW Disable (HPM_HW_DIS):** When set to 1 the internal VRM that generates the rtc well supply voltage in SUS mode is disabled when SLP_S0# is asserted to '0'. (via irtcdswen pin to RTC EBB). When 0, HW control of the RTC internal VRM is disabled. **Power Well:** Core
5	0x0 RW	**RTC High Power Mode SW Disable (HPM_SW_DIS):** When set to 1 the internal VRM that generates the rtc well supply voltage in SUS mode is disabled (via irtcdswen pin to RTC EBB). When 0 the internal VRM powers the rtc well when RSMRST# is '1'. (default) **Power Well:** Core
4	0x0 RW/1L	**Upper 128 Byte Lock (UL):** When set, bytes 38h-3Fh in the upper 128 byte bank of RTC RAM are locked and cannot be accessed. Writes will be dropped and reads will not return any guaranteed data. Bit reset on system reset. **Power Well:** Core
3	0x0 RW/1L	**Lower 128 Byte Lock (LL):** When set, bytes 38h-3Fh in the lower 128 byte bank of RTC RAM are locked and cannot be accessed. Writes will be dropped and reads will not return any guaranteed data. Bit reset on system reset. **Power Well:** Core
2	0x0 RW	**Upper 128 Byte Enable (UE):** When set, the upper 128 byte bank of RTC RAM can be accessed. **Power Well:** Core
1:0	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core

62.5.2 Backed Up Control (BUC)—Offset 3414h

All bits in this register are in the RTC well and only cleared by RTEST.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD1] + 3414h
Host Memory Space: SBREG_BAR + 0xD10000 + 3414h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** RTC
6	0x0 RW	**Reserved (RSVD_2):** Reserved **Power Well:** RTC
5	0x0 RW	**LAN Disable (LanDisable):** • '0': LAN is Enabled '1': LAN is Disabled. It will not claim any configuration cycles on SPXB or MBB nor initiate any cycles on SPXB or MBB. When the RTC backup copy of the LAN Disable Fuse is set, this register is Read Only. • '1'. If the RTC backup copy of the LAN Disable Fuse is not set, this register is reset to 0 on RTEST#. If the Function Disable SUS Well Lockdown register is set, this bit can not be changed by software. **Power Well:** RTC
4	0x0 RW	**Daylight Savings Override (SDO):** • When this bit is a '1', the DSE bit in the RTC Register B bit(0) is a RW bit but has no effect where daylight savings is hard-disabled internally. • When this bit is a '0', the DSE bit in the RTC register B bit(0) is a RW bit that is configurable by software to enable the daylight savings. System BIOS shall configure this bit accordingly during the boot process before RTC time is initialized. **Power Well:** RTC
3	0x0 RW	**NetDetect Enable (NDE):** • If this bit is '1' and the South MLink Enable bit is '0' (ME PM RTCPMCFG.SMLEN), then the GPIO(14) input signal is muxed onto the South MLink MLCLK pin as a NetDetect Request signal to the wireless LAN component. • If the South MLink Enable bit is a '1', then the South MLink MLCLK pin is used as MLCLK, independent of the value of this register. • If both the South MLink Enable bit is '0' and this NetDetect Enable bit is '0', then the South MLink MLCLK pin is tri-stated. This register is in the RTC well instead of the SUS well to maintain state if the SUS well power is removed in S4. **Power Well:** RTC
2	0x0 RW	**Reserved (RSVD_3):** Reserved **Power Well:** RTC
1	0x0 RO	**Reserved (RSVD_4):** Reserved **Power Well:** RTC
0	0x0 RW	**Top Swap (TS):** This should be set by BIOS when the corresponding TS bit in the LPC controller is set in order to properly restore the state of that field after reset since they are not preserved in an RTC well bit in those devices. If SoC is strapped for Top-Swap (GNT(3)# is low at rising edge of PWROK), then this bit cannot be cleared by software. The strap jumper should be removed and the system rebooted. **Power Well:** RTC

62.5.3 RTC Update In Progress SMI Control (UIPSMI)—Offset 3F04h

This register exists in the RTC power well.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD1] + 3F04h
Host Memory Space: SBREG_BAR + 0xD10000 + 3F04h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
17	0x0 RW/1C	**RTC UIP Low-to-High (UIP_L2H):** This sticky status bit is set whenever the RTC Update-In-Progress signal transitions from low to high (i.e., at the start of an update). **Power Well:** Core
16	0x0 RW/1C	**RTC UIP High-to-Low (UIP_H2L):** This sticky status bit is set whenever the RTC Update-In-Progress signal transitions from high to low (i.e., at the start of an update). **Power Well:** Core
15:2	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
1	0x0 RW	**RTC UIP Low-to-High SMI Enable (UIP_L2H_SMI_en):** When this bit is set, a '1' in bit 17 will assert the internal SMI signal to the Power Management SMI logic **Power Well:** Core
0	0x0 RW	**RTC UIP High-to-Low SMI Enable (UIP_H2L_SMI_en):** When this bit is set, a '1' in bit 16 will assert the internal SMI signal to the Power Management SMI logic **Power Well:** Core

62.5.4 RTC Dynamic Clock Gating Control (RTCDCG)—Offset 3418h

All bits in this register are in the Primary Well and cleared by host_side_rst_b.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD1] + 3418h
Host Memory Space: SBREG_BAR + 0xD10000 + 3418h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** RTC
7:3	0x0 RW	**Reserved (RSVD_1):** Reserved for future use **Power Well:** Core
2	0x0 RW	**pgcb_clk (12MHz) Dynamic Clock Gate Enable (RTCPGCBDCGEN):** • 0 - Disable dynamic clock gate on pgcb_clk (Default) • 1 - Enable dynamic clock gate on pgcb_clk **Power Well:** Core
1	0x0 RW	**ipciclk_clk (24MHz) Dynamic Clock Gate Enable (RTCPCICLKDCGEN):** • 0 - Disable dynamic clock gate on ipci_clk (Default) • 1 - Enable dynamic clock gate on ipci_clk **Power Well:** Core
0	0x0 RW	**rosc_side_clk (120MHz) Dynamic Clock Gate Enable (RTCROSIDEDCGEN):** • 0 - Disable dynamic clock gate on rosc_side_clk (Default) • 1 - Enable dynamic clock gate on rosc_side_clk **Power Well:** Core

§ §

63 High Precision Event Timer - Legacy

63.1 Introduction and Index

The host-accessible registers for the High Precision Event Timer are described here.

The legend for the register access codes are described in Chapter 43, "Introduction."

63.1.1 Host Memory Space—Fixed Address

An index of the registers that are accessible in Host Memory Space is shown here.

Table 63-1. Summary of Memory Mapped I/O Registers—0xFED00000

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
10	8	0000000000000000	"General Config Register (GEN_CFG)—Offset 10h" on page 2906
20	8	0000000000000000	"General Interrupt Status Register (GEN_INT_STS)—Offset 20h" on page 2907

63.2 Registers in Memory Space—Fixed Addresses

These registers are accessed in Host Memory Space through fixed memory addresses.

63.2.1 General Config Register (GEN_CFG)—Offset 10h

Software can read the various bytes in this register using 32-bit or 64-bit accesses. 32-bit accesses may only be done to offset 010h or 014h. 64-bit accesses may only be done to 010h.

Type: Memory Mapped I/O Register (Size: 64 bits)

Address: [0xFED00000] + 10h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:2	0x0 RO	**Reserved (RSV_63_2):** These bits will return 0 when read. Writes will have no effect. **Power Well:** Core
1	0x0 RW	**Legacy Rout (LEG_RT_CNF)** If the LEG_RT_CNF bit is set, then the interrupts will be routed as follows: • **Timer 0** will be routed to IRQ0 in 8259 or IRQ2 in the I/O APIC • **Timer 1** will be routed to IRQ8 in 8259 or IRQ8 in the I/O APIC • **Timer 2-7** will be routed as per the routing in that timer config register. If the LEG_RT_CNF bit is set, the individual routing bits for timers 0 and 1 (APIC or FSB) will have no impact. Otherwise, if the LEG_RT_CNF bit is not set, the individual routing bits for each of the timers are used. **Power Well:** Core
0	0x0 RW	**Overall Enable (ENABLE_CNF):** This bit must be set to enable any of the timers to generate interrupts. If this bit is 0, then the main counter will halt (will not increment) and no interrupts will be caused by any of these timers. This bit will default to 0. BIOS can set it to 1 or 0. **Power Well:** Core

63.2.2 General Interrupt Status Register (GEN_INT_STS)—Offset 20h

Software can read the various bytes in this register using 32-bit or 64-bit accesses. 32-bit accesses may only be done to offset 020h or 024h. 64-bit accesses may only be done to 020h.

Type: Memory Mapped I/O Register (Size: 64 bits)

Address: [0xFED00000] + 20h

Default: 0000000000000000h

Bit Range	Default & Access	Field Name (ID): Description
63:8	0x0 RO	**Reserved (RSV):** These bits will return 0 when read. Writes will have no effect. **Power Well:** Core
7	0x0 RW/1C	**Timer 7 Interrupt Active (T07_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
6	0x0 RW/1C	**Timer 6 Interrupt Active (T06_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
5	0x0 RW/1C	**Timer 5 Interrupt Active (T05_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
4	0x0 RW/1C	**Timer 4 Interrupt Active (T04_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
3	0x0 RW/1C	T**imer 3 Interrupt Active (T03_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
2	0x0 RW/1C	**Timer 2 Interrupt Active (T02_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
1	0x0 RW/1C	**Timer 1 Interrupt Active (T01_INT_STS)** Same functionality as Timer 0 Interrupt Active (T00_INT_STS). **Power Well:** Core
0	0x0 RW/1C	**Timer 0 Interrupt Active (T00_INT_STS)** The functionality of this bit depends on whether the edge or level-triggered mode is used for this timer: • If set to edge triggered mode: This bit will always read as 0 and writes will have no effect. • If set to level-triggered mode: This bit will be set by hardware if the corresponding timer interrupt is active. Once the bit is set, it can be cleared by software writing a 1 to the same bit position. Writes of 0 to this bit will have no effect. For example if the bit is already set, a write of 0 will not clear the bit. This bit defaults to 0. **Power Well:** Core

§ §

64 PIC and I/O APIC Controllers

64.1 Introduction and Index

The host-accessible registers for the PIC and I/O APIC Controller are described here.

The legend for the register access codes are described in Chapter 43, "Introduction."

64.1.1 Host Configuration Space

These registers are discovered in Host Configuration Space starting at Bus 0, Device 31 (decimal), Function 1. The offset addresses are listed.

Table 64-1. Summary of PCI Configuration Registers—0/31/1

Offset (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
64	2	0000	"IOxAPIC Configuration (IOAC)—Offset 64h" on page 2913

64.1.2 Host Memory Space—Fixed Address

An index of the registers that are accessible in Host Memory Space is shown here.

The IOxAPIC Interrupt Message table is located in Host Memory Space starting at address FEE0_0000h. Construction of the address for a table entry is shown in Table 64-2.

Table 64-2. IOxAPIC Interrupt Message Address

Address Bit	Short Description	Description
31:20	FEEh	Hardwired as FEEh
19:12	Destination ID	Destination ID of the local APIC - from DID field of the interrupt RTE
11:4	Extended Destination ID	Extended destination ID of the local APIC - from EDID field of the interrupt RTE
3	Redirection Hint	Redirection Hint - '1" If the DLM field = “Lowest Priority” (001) for the interrupt RTE. Otherwise '0'
2	Destination Mode	Used by the Local APIC to determine whether it is the destination of the Interrupt Message
1:0	00	Hardwired as 00 - Interrupt Message data is written as a Double Word (32 bits)

For the description of an IOxAPIC Interrupt Message, see Section 64.3.3, “IOxAPIC Interrupt Messages for Local APIC—FEE0_0000h” on page 2914.

Also located in Host Memory Space are the 32-bit IOxAPIC Index (IDX), Window (WDW), and End-of-Interrupt (EOI) registers. See Table 64-3, “Summary of Memory-Mapped Registers—Fixed Addresses” on page 2910.

For the information accessible through the IOxAPIC Index/Window mechanism, see Table 64-4, “Summary of IOxAPIC Index/Window-Accessed Registers” on page 2911.

Table 64-3. Summary of Memory-Mapped Registers—Fixed Addresses

Address (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
FECO_0000	4	00000000	“Index Register (IDX)—FEC0_0000h” on page 2914
FECO_0010	4	00000000	“Window Register (WDW)—FEC0_0010h” on page 2914

Table 64-4. Summary of IOxAPIC Index/Window-Accessed Registers

Index (IDX) Value (hex)	Double-Word Accesses	Default Value (hex)	Contents of Window (WDW) Register Name (Register Symbol)
1	1	00770020	"Version (VS)—Offset 1h" on page 2917
2 through F	1	00000000	Reserved
10, 11	2	0000000000010000	"Redirection Table Entry 0 (RTE0)—Offset 10h" on page 2918
12, 13	2	0000000000010000	"Redirection Table Entry 1 (RTE1)—Offset 12h" on page 2920
14, 15	2	0000000000010000	"Redirection Table Entry 2 (RTE2)—Offset 14h" on page 2922
through	...	...	...
FC, FD	2	0000000000010000	"Redirection Table Entry 118 (RTE118)—Offset FCh" on page 2924
FE, FF	2	0000000000010000	"Redirection Table Entry 119 (RTE119)—Offset FEh" on page 2926

64.1.3 Host I/O Space—Fixed Address

An index of the registers that are accessible in Host I/O Space is shown here.

Table 64-5. Summary of I/O Registers—Fixed Location

I/O Port Address (hex)	Bytes	Default Value (hex)	Register Name (Register Symbol)
20	1	11	"Master Initialization Command Word 1 (MICW1)—I/O Port 20h" on page 2928
21	1	00	"Master Initialization Command Word 2 (MICW2)—I/O Port 21h" on page 2929
21	1	07	"Master Initialization Command Word 3 (MICW3)—I/O Port 21h" on page 2929
21	1	00	"Master Initialization Command Word 4 (MICW4)—I/O Port 21h" on page 2930
21	1	00	"Master Operational Control Word 1 (MOCW1)—I/O Port 21h" on page 2930
20	1	00	"Master Operational Control Word 2 (MOCW2)—I/O Port 20h" on page 2931
20	1	08	"Master Operational Control Word 3 (MOCW3)—I/O Port 20h" on page 2932
A0	1	11	"Slave Initialization Command Word 1 (SICW1)—I/O Port A0h" on page 2933
A1	1	00	"Slave Initialization Command Word 2 (SICW2)—I/O Port A1h" on page 2934
A1	1	07	"Slave Initialization Command Word 3 (SICW3)—I/O Port A1h" on page 2934
A1	1	00	"Slave Initialization Command Word 4 (SICW4)—I/O Port A1h" on page 2935
A1	1	00	"Slave Operational Control Word 1 (SOCW1)—I/O Port A1h" on page 2935
A0	1	00	"Slave Operational Control Word 2 (SOCW2)—I/O Port A0h" on page 2936
A0	1	08	"Slave Operational Control Word 3 (SOCW3)—I/O Port A0h" on page 2937
4D0	1	00	"Master Edge/Level Control (ELCR1)—I/O Port 4D0h" on page 2938
4D1	1	00	"Slave Edge/Level Control (ELCR2)—I/O Port 4D1h" on page 2938

64.2 Registers in Configuration Space

64.2.1 IOxAPIC Configuration (IOAC)—Offset 64h

Type: PCI Configuration Register (Size: 16 bits)

Offset: [B:0, D:31, F:1] + 64h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:9	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
8	0x0 RW	**Address Enable (AE):** When set, the P2SB will decode the IOxAPIC Host Root memory-address range selected by bits 7:0 below. **Power Well:** Core
7:0	0x0 RW	**APIC Range Select (ASEL):** These eight bits define the eight address bits 19:12 for the IOxAPIC range. The default value of 00h enables compatibility with prior Intel products as an initial value. This value must not be changed by software unless the IOxAPIC Address Enable (AE) bit is cleared. **Power Well:** Core

64.3 Registers in Memory Space—Fixed Addresses

These registers are accessed in Host Memory Space through fixed memory addresses.

64.3.1 Index Register (IDX)—FEC0_0000h

This 8-bit register selects which indirect register appears in the window register to be manipulated by software. Software will program this register to select the desired APIC internal register.

Type: Memory-Mapped I/O Register (Size: 32 bits)

Address: FEC0_0000h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:8	0x0 RO	**Reserved (RSVD):** Reserved. **Power Well:** Core
7:0	0x0 RW	**Index Register (IDX):** Index Register for APIC **Power Well:** Core

64.3.2 Window Register (WDW)—FEC0_0010h

This 32-bit register specifies the data to be read or written to the register pointed to by the IDX register. This register can be accessed only in DWord quantities.

Type: Memory-Mapped I/O Register (Size: 32 bits)

Address: FEC0_0010h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW/V	**Window Register (WDW):** Window Register for APIC **Power Well:** Core

64.3.3 IOxAPIC Interrupt Messages for Local APIC—FEE0_0000h

The 32-bit IOxAPIC Interrupt Messages sent to the Local APICs are written in Host Memory Space starting at address FEE0_0000h through address FEEF_FFFCh. Each message has the following data format.

Type: Memory-Mapped I/O Register (Size: 32 bits)

Address: FEE0_0000h through FEEF_FFCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved:** Reserved. Hardwired as 0.
15	0x0 RO	**Trigger Mode:** From the TM field of the Redirection Table Entry (RTE). • '0' indicates the interrupt is edge sensitive. • '1' indicates the interrupt is level sensitive.

Bit Range	Default & Access	Field Name (ID): Description
14	0x0 RO	**Delivery Status:** Is always '1' indicating an "Assert Message" cycle.
13:12	0x0 RO	**Reserved:** Reserved. Hardwired as 0.
11	0x0 RO	**Destination Mode:** From the DSM field of the RTE. Used by the Local APIC to determine whether it is the destination of the message.
10:8	0x0 RO	**Delivery Mode:** From the DLM field of the RTE. Establishes how the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode.
7:0	0x0 RO	**Vector:** From the VCT field of the RTE. Defines the Interrupt Vector for this interrupt. Values range between 10h and FEh.

64.4 Registers Accessed through IOxAPIC IDX and WDW

These registers are accessed through the IOxAPIC Index/Window mechanism. For each Index (IDX) value, one double-word is accessible in the Window (WDW) register.

64.4.1 Version (VS)—Offset 1h

Type: IOxAPIC IDX/WDW (Size: 32 bits)

IDX: 1h

Default: 00770020h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
23:16	0x77 RW/O	**Maximum Redirection Entries (MRE):** This is the entry number (0 being the lowest entry) of the highest entry in the redirection table. The default value is 77h to indicate a maximum of 120 (decimal) Redirection Table Entries. This field is Read-Write-Once. BIOS must write to this field after PLTRST# to lockdown the value. This allows BIOS to utilize some of the entries for its own purpose and thus advertising fewer IOxAPIC Redirection Table Entries to the Operating System. BIOS may to program this field up to 77h (maximum 120 entries). **Power Well:** Core
15	0x0 RO	**Pin Assertion Register Supported (PRQ):** The default value indicates that the IOxAPIC does not implement the Pin Assertion Register. **Power Well:** Core
14:8	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
7:0	0x20 RO	**Version (VS):** Identifies the implementation version as IOxAPIC. **Power Well:** Core

64.4.2 Redirection Table Entry 0 (RTE0)—Offset 10h

Type: IOxAPIC IDX/WDW (Size: 64 bits)

IDX: 10h, 11h

Default: 0000000000010000h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x0 RW	**Destination ID (DID):** Destination ID of the local APIC **Power Well:** Core
55:48	0x0 RW	**Extended Destination ID (EDID):** Extended destination ID of the local APIC. **Power Well:** Core
47:17	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
16	0x1 RW	**Mask (MSK):** When set, interrupts are not delivered nor held pending. When cleared, and edge or level on this interrupt results in the delivery of the interrupt. **Power Well:** Core
15	0x0 RW	**Trigger Mode (TM):** When cleared, the interrupt is edge sensitive. When set, the interrupt is level sensitive. **Power Well:** Core
14	0x0 RO/V	**Remote IRR (RIRR):** This is used for level triggered interrupts - its meaning is undefined for edge triggered interrupts. This bit is set when IOxAPIC sends the level interrupt message to the CPU. This bit is cleared when an EOI message is received that matches the VCT field. This bit is never set for SMI, NMI, INIT, or ExtINT delivery modes. **Power Well:** Core
13	0x0 RW	**Polarity (POL):** This specifies the polarity of each interrupt input. When cleared, the signal is active high. When set, the signal is active low. **Power Well:** Core
12	0x0 RO/V	**Delivery Status (DS):** This field contains the current status of the delivery of this interrupt. When set, an interrupt is pending and not yet delivered. When cleared, there is no activity for this entry **Power Well:** Core
11	0x0 RW	**Destination Mode (DSM):** This field is used by the local APIC to determine whether it is the destination of the message. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Delivery Mode (DLM):** This field specifies how the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode. These encodings are: • 000 - Fixed • 001 - Lowest Priority • 010 - SMI (Not supported) • 011 - Reserved • 100 - NMI (Not supported) • 101 - INIT (Not supported) • 110 - Reserved • 111 - ExtINT **Power Well:** Core
7:0	0x0 RW	**Vector (VCT):** This field contains the interrupt vector for this interrupt. Values range between 10h and FEh. **Power Well:** Core

64.4.3 Redirection Table Entry 1 (RTE1)—Offset 12h

Type: IOxAPIC IDX/WDW (Size: 64 bits)

IDX: 12h, 13h

Default: 0000000000010000h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x0 RW	**Destination ID (DID):** Destination ID of the local APIC **Power Well:** Core
55:48	0x0 RW	**Extended Destination ID (EDID):** Extended destination ID of the local APIC. **Power Well:** Core
47:17	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
16	0x1 RW	**Mask (MSK):** When set, interrupts are not delivered nor held pending. When cleared, and edge or level on this interrupt results in the delivery of the interrupt. **Power Well:** Core
15	0x0 RW	**Trigger Mode (TM):** When cleared, the interrupt is edge sensitive. When set, the interrupt is level sensitive. **Power Well:** Core
14	0x0 RO/V	**Remote IRR (RIRR):** This is used for level triggered interrupts - its meaning is undefined for edge triggered interrupts. This bit is set when IOxAPIC sends the level interrupt message to the CPU. This bit is cleared when an EOI message is received that matches the VCT field. This bit is never set for SMI, NMI, INIT, or ExtINT delivery modes. **Power Well:** Core
13	0x0 RW	**Polarity (POL):** This specifies the polarity of each interrupt input. When cleared, the signal is active high. When set, the signal is active low. **Power Well:** Core
12	0x0 RO/V	**Delivery Status (DS):** This field contains the current status of the delivery of this interrupt. When set, an interrupt is pending and not yet delivered. When cleared, there is no activity for this entry **Power Well:** Core
11	0x0 RW	**Destination Mode (DSM):** This field is used by the local APIC to determine whether it is the destination of the message. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Delivery Mode (DLM):** This field specifies how the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode. These encodings are: • 000 - Fixed • 001 - Lowest Priority • 010 - SMI (Not supported) • 011 - Reserved • 100 - NMI (Not supported) • 101 - INIT (Not supported) • 110 - Reserved • 111 - ExtINT **Power Well:** Core
7:0	0x0 RW	**Vector (VCT):** This field contains the interrupt vector for this interrupt. Values range between 10h and FEh. **Power Well:** Core

64.4.4 Redirection Table Entry 2 (RTE2)—Offset 14h

Type: IOxAPIC IDX/WDW (Size: 64 bits)

IDX: 14h, 15h

Default: 0000000000010000h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x0 RW	**Destination ID (DID):** Destination ID of the local APIC **Power Well:** Core
55:48	0x0 RW	**Extended Destination ID (EDID):** Extended destination ID of the local APIC. **Power Well:** Core
47:17	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
16	0x1 RW	**Mask (MSK):** When set, interrupts are not delivered nor held pending. When cleared, and edge or level on this interrupt results in the delivery of the interrupt. **Power Well:** Core
15	0x0 RW	**Trigger Mode (TM):** When cleared, the interrupt is edge sensitive. When set, the interrupt is level sensitive. **Power Well:** Core
14	0x0 RO/V	**Remote IRR (RIRR):** This is used for level triggered interrupts - its meaning is undefined for edge triggered interrupts. This bit is set when IOxAPIC sends the level interrupt message to the CPU. This bit is cleared when an EOI message is received that matches the VCT field. This bit is never set for SMI, NMI, INIT, or ExtINT delivery modes. **Power Well:** Core
13	0x0 RW	**Polarity (POL):** This specifies the polarity of each interrupt input. When cleared, the signal is active high. When set, the signal is active low. **Power Well:** Core
12	0x0 RO/V	**Delivery Status (DS):** This field contains the current status of the delivery of this interrupt. When set, an interrupt is pending and not yet delivered. When cleared, there is no activity for this entry **Power Well:** Core
11	0x0 RW	**Destination Mode (DSM):** This field is used by the local APIC to determine whether it is the destination of the message. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Delivery Mode (DLM):** This field specifies how the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode. These encodings are: • 000 - Fixed • 001 - Lowest Priority • 010 - SMI (Not supported) • 011 - Reserved • 100 - NMI (Not supported) • 101 - INIT (Not supported) • 110 - Reserved • 111 - ExtINT **Power Well:** Core
7:0	0x0 RW	**Vector (VCT):** This field contains the interrupt vector for this interrupt. Values range between 10h and FEh. **Power Well:** Core

64.4.5 Redirection Table Entry 118 (RTE118)—Offset FCh

Type: IOxAPIC IDX/WDW (Size: 64 bits)

IDX: FCh, FDh

Default: 0000000000010000h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x0 RW	**Destination ID (DID):** Destination ID of the local APIC **Power Well:** Core
55:48	0x0 RW	**Extended Destination ID (EDID):** Extended destination ID of the local APIC. **Power Well:** Core
47:17	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
16	0x1 RW	**Mask (MSK):** When set, interrupts are not delivered nor held pending. When cleared, and edge or level on this interrupt results in the delivery of the interrupt. **Power Well:** Core
15	0x0 RW	**Trigger Mode (TM):** When cleared, the interrupt is edge sensitive. When set, the interrupt is level sensitive. **Power Well:** Core
14	0x0 RO/V	**Remote IRR (RIRR):** This is used for level triggered interrupts - its meaning is undefined for edge triggered interrupts. This bit is set when IOxAPIC sends the level interrupt message to the CPU. This bit is cleared when an EOI message is received that matches the VCT field. This bit is never set for SMI, NMI, INIT, or ExtINT delivery modes. **Power Well:** Core
13	0x0 RW	**Polarity (POL):** This specifies the polarity of each interrupt input. When cleared, the signal is active high. When set, the signal is active low. **Power Well:** Core
12	0x0 RO/V	**Delivery Status (DS):** This field contains the current status of the delivery of this interrupt. When set, an interrupt is pending and not yet delivered. When cleared, there is no activity for this entry **Power Well:** Core
11	0x0 RW	**Destination Mode (DSM):** This field is used by the local APIC to determine whether it is the destination of the message. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Delivery Mode (DLM):** This field specifies how the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode. • These encodings are: • 000 - Fixed • 001 - Lowest Priority • 010 - SMI (Not supported) • 011 - Reserved • 100 - NMI (Not supported) • 101 - INIT (Not supported) • 110 - Reserved • 111 - ExtINT **Power Well:** Core
7:0	0x0 RW	**Vector (VCT):** This field contains the interrupt vector for this interrupt. Values range between 10h and FEh. **Power Well:** Core

64.4.6 Redirection Table Entry 119 (RTE119)—Offset FEh

Type: IOxAPIC IDX/WDW (Size: 64 bits)

IDX: FCh, FDh

Default: 0000000000010000h

Bit Range	Default & Access	Field Name (ID): Description
63:56	0x0 RW	**Destination ID (DID):** Destination ID of the local APIC **Power Well:** Core
55:48	0x0 RW	**Extended Destination ID (EDID):** Extended destination ID of the local APIC. **Power Well:** Core
47:17	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
16	0x1 RW	**Mask (MSK):** When set, interrupts are not delivered nor held pending. When cleared, and edge or level on this interrupt results in the delivery of the interrupt. **Power Well:** Core
15	0x0 RW	**Trigger Mode (TM):** When cleared, the interrupt is edge sensitive. When set, the interrupt is level sensitive. **Power Well:** Core
14	0x0 RO/V	**Remote IRR (RIRR):** This is used for level triggered interrupts - its meaning is undefined for edge triggered interrupts. This bit is set when IOxAPIC sends the level interrupt message to the CPU. This bit is cleared when an EOI message is received that matches the VCT field. This bit is never set for SMI, NMI, INIT, or ExtINT delivery modes. **Power Well:** Core
13	0x0 RW	**Polarity (POL):** This specifies the polarity of each interrupt input. When cleared, the signal is active high. When set, the signal is active low. **Power Well:** Core
12	0x0 RO/V	**Delivery Status (DS):** This field contains the current status of the delivery of this interrupt. When set, an interrupt is pending and not yet delivered. When cleared, there is no activity for this entry **Power Well:** Core
11	0x0 RW	**Destination Mode (DSM):** This field is used by the local APIC to determine whether it is the destination of the message. **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
10:8	0x0 RW	**Delivery Mode (DLM):** This field specifies how the APICs listed in the destination field should act upon reception of this signal. Certain Delivery Modes will only operate as intended when used in conjunction with a specific trigger mode. These encodings are: • 000 - Fixed • 001 - Lowest Priority • 010 - SMI (Not supported) • 011 - Reserved • 100 - NMI (Not supported) • 101 - INIT (Not supported) • 110 - Reserved • 111 - ExtINT **Power Well:** Core
7:0	0x0 RW	**Vector (VCT):** This field contains the interrupt vector for this interrupt. Values range between 10h and FEh. **Power Well:** Core

64.5 Registers in I/O Space—Fixed Addresses

These registers are accessed in Host I/O Space through fixed I/O Port addresses.

64.5.1 Master Initialization Command Word 1 (MICW1)—I/O Port 20h

A write to Initialization Command Word 1 (ICW1) starts the interrupt controller initialization sequence, during which the following occurs:

1. The Interrupt Mask register is cleared.
2. IRQ7 input is assigned priority 7.
3. The slave mode address is set to 7.
4. Special Mask Mode is cleared and Status Read is set to IRR.

Once this write occurs, the controller expects writes to ICW2, ICW3, and ICW4 to complete the initialization sequence.

Type: I/O Register (Size: 8 bits)

I/O Port Address: 20h

Default: 11h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 WO	**ICW/OCW select (ICW_OCW_SLT1):** These bits are MCS-85 specific, and not needed. Should be programmed to 000 **Power Well:** Core
4	0x1 WO	**ICW/OCW select (ICW_OCW_SLT2):** This bit must be a 1 to select ICW1 and enable the ICW2, ICW3, and ICW4 sequence. **Power Well:** Core
3	0x0 WO	**Edge/Level Bank Select (LTIM):** Disabled. Replaced by the edge/level triggered control registers (ELCR). **Power Well:** Core
2	0x0 WO	**ADI-IGNORED (ADI):** Ignored by the SoC. Should be programmed to 0. **Power Well:** Core
1	0x0 WO	**Single or Cascade (SNGL):** Must be programmed to a 0 to indicate two controllers operating in cascade mode. **Power Well:** Core
0	0x1 WO	**ICW4 Write Required (IC4):** This bit must be programmed to a 1 to indicate that ICW4 needs to be programmed. **Power Well:** Core

64.5.2 Master Initialization Command Word 2 (MICW2)—I/O Port 21h

ICW2 is used to initialize the interrupt controller with the five most significant bits of the interrupt vector address. The value programmed for bits[7:3] is used by the CPU to define the base address in the interrupt vector table for the interrupt routines associated with each IRQ on the controller. Typical ISA ICW2 values are 08h for the master controller and 70h for the slave controller.

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 21h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 WO	**Interrupt Vector Base Address (IVBA):** Bits [7:3] define the base address in the interrupt vector table for the interrupt routines associated with each interrupt request level input. **Power Well:** Core
2:0	0x0 WO	**Interrupt Request Level (IRL):** When writing ICW2, these bits should all be 0. During an interrupt acknowledge cycle, these bits are programmed by the interrupt controller with the interrupt to be serviced. This is combined with bits [7:3] to form the interrupt vector driven onto the data bus during the second INTA# cycle. The code is a three bit binary code: Code Master Interrupt Slave Interrupt • 000 IRQ0 IRQ8 • 001 IRQ1 IRQ9 • 010 IRQ2 IRQ10 • 011 IRQ3 IRQ11 • 100 IRQ4 IRQ12 • 101 IRQ5 IRQ13 • 110 IRQ6 IRQ14 • 111 IRQ7 IRQ15 **Power Well:** Core

64.5.3 Master Initialization Command Word 3 (MICW3)—I/O Port 21h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 21h

Default: 07h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 WO	**MICW3 [7:3] (MICW3_7_3):** These bits must be programmed to zero. **Power Well:** Core
2	0x1 WO	**Cascaded Controller Connection (CCC):** This bit must always be programmed to a 1 to indicate the slave controller for interrupts 8 - 15 is cascaded on IRQ2. **Power Well:** Core
1:0	0x3 WO	**MICW [1:0] (MICW3_1_0):** These bits must be programmed to zero. **Power Well:** Core

64.5.4 Master Initialization Command Word 4 (MICW4)—I/O Port 21h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 21h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 WO	**Reserved (RSVD):** Must be 0. **Power Well:** Core
4	0x0 WO	**Special Fully Nested Mode (SFNM):** Should normally be disabled by writing a 0 to this bit. If SFNM=1, the special fully nested mode is programmed. **Power Well:** Core
3	0x0 WO	**Buffered Mode (BUF):** Must be cleared for non-buffered mode. Writing 1 will result in undefined behavior. **Power Well:** Core
2	0x0 WO	**Master/Slave in Buffered Mode (MSBM):** Not used. Should always be programmed to 0. **Power Well:** Core
1	0x0 WO	**Automatic End of Interrupt (AEOI):** This bit should normally be programmed to 0. This is the normal end of interrupt. If this bit is 1, the automatic end of interrupt mode is programmed. AEOI is discussed in Section 13.1.7.2 **Power Well:** Core
0	0x0 WO	**Microprocessor Mode (MM):** This bit must be written to 1 to indicate that the controller is operating in an Intel Architecture-based system. Writing 0 will result in undefined behavior.1 **Power Well:** Core

64.5.5 Master Operational Control Word 1 (MOCW1)—I/O Port 21h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 21h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Request Mask (IRM):** When a 1 is written to any bit in this register, the corresponding IRQ line is masked. When a 0 is written to any bit in this register, the corresponding IRQ mask bit is cleared, and interrupt requests will again be accepted by the controller. Masking IRQ2 on the master controller will also mask the interrupt requests from the slave controller. **Power Well:** Core

64.5.6 Master Operational Control Word 2 (MOCW2)—I/O Port 20h

Following a part reset or ICW initialization, the controller enters the fully nested mode of operation. Non-specific EOI without rotation is the default. Both rotation mode and specific EOI mode are disabled following initialization.

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 20h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 WO	**Rotate and EOI Codes (REOI):** R, SL, EOI - These three bits control the Rotate and End of Interrupt modes and combinations of the two. A chart of these combinations is listed above under the bit definition. • 000 Rotate in Auto EOI Mode (Clear) • 001 Non-specific EOI command • 010 No Operation • 011 *Specific EOI Command • 100 Rotate in Auto EOI Mode (Set) • 101 Rotate on Non-Specific EOI Command • 110 *Set Priority Command • 111 *Rotate on Specific EOI Command • *L0 - L2 Are Used **Power Well:** Core
4:3	0x0 WO	**OCW2 Select (O2S):** When selecting OCW2, bits 4:3 = 00 **Power Well:** Core
2:0	0x0 WO	**Interrupt Level Select (L2, L1, L0) (ILSLT):** L2, L1, and L0 determine the interrupt level acted upon when the SL bit is active. A simple binary code, outlined above, selects the channel for the command to act upon. When the SL bit is inactive, these bits do not have a defined function, programming L2, L1 and L0 to 0 is sufficient in this case. **Power Well:** Core

64.5.7 Master Operational Control Word 3 (MOCW3)—I/O Port 20h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 20h

Default: 08h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD):** Must be 0. **Power Well:** Core
6	0x0 WO	**Special Mask Mode (SMM):** If this bit is set, the Special Mask Mode can be used by an interrupt service routine to dynamically alter the system priority structure while the routine is executing, through selective enabling/ disabling of the other channel's mask bits. Bit 6, the ESMM bit, must be set for this bit to have any meaning. **Power Well:** Core
5	0x0 WO	**Enable Special Mask Mode (ESMM):** **Power Well:** Core
4:3	0x1 WO	**OCW3 Select (O3S):** When selecting OCW3, bits 4:3 = 01 **Power Well:** Core
2	0x0 WO	**Poll Mode Command (PMC):** When cleared, poll command is not issued. When set, the next I/O read to the interrupt controller is treated as an interrupt acknowledge cycle. An encoded byte is driven onto the data bus, representing the highest priority level requesting service. **Power Well:** Core
1:0	0x0 WO	**Register Read Command (RRC):** . To retain the current selection (read ISR or read IRR), always write a 0 to bit 1 when programming this register. The selected register can be read repeatedly without reprogramming OCW3. To select a new status register, OCW3 must be reprogrammed prior to attempting the read. Value Command • 00 No Action • 01 No Action • 10 Read IRQ Register • 11 Read IS Register **Power Well:** Core

64.5.8 Slave Initialization Command Word 1 (SICW1)—I/O Port A0h

A write to Initialization Command Word 1 starts the interrupt controller initialization sequence, during which the following occurs: 1. The Interrupt Mask register is cleared. 2. IRQ7 input is assigned priority 7. 3. The slave mode address is set to 7. 4. Special Mask Mode is cleared and Status Read is set to IRR. Once this write occurs, the controller expects writes to ICW2, ICW3, and ICW4 to complete the initialization sequence.

Type: I/O Register (Size: 8 bits)

I/O Port Address: A0h

Default: 11h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 WO	**ICW/OCW select (ICW_OCW_SLT1):** These bits are MCS-85 specific, and not needed. Should be programmed to 000 **Power Well:** Core
4	0x1 WO	**ICW/OCW select (ICW_OCW_SLT2):** This bit must be a 1 to select ICW1 and enable the ICW2, ICW3, and ICW4 sequence. **Power Well:** Core
3	0x0 WO	**Edge/Level Bank Select (LTIM):** Disabled. Replaced by the edge/level triggered control registers (ELCR). **Power Well:** Core
2	0x0 WO	**ADI-IGNORED (ADI):** Ignored by the SoC. Should be programmed to 0. **Power Well:** Core
1	0x0 WO	**Single or Cascade (SNGL):** Must be programmed to a 0 to indicate two controllers operating in cascade mode. **Power Well:** Core
0	0x1 WO	**ICW4 Write Required (IC4):** This bit must be programmed to a 1 to indicate that ICW4 needs to be programmed. **Power Well:** Core

64.5.9 Slave Initialization Command Word 2 (SICW2)—I/O Port A1h

ICW2 is used to initialize the interrupt controller with the five most significant bits of the interrupt vector address. The value programmed for bits[7:3] is used by the CPU to define the base address in the interrupt vector table for the interrupt routines associated with each IRQ on the controller. Typical ISA ICW2 values are 08h for the master controller and 70h for the slave controller.

Type: I/O Register
(Size: 8 bits)

I/O Port Address: A1h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 WO	**Interrupt Vector Base Address (IVBA):** Bits [7:3] define the base address in the interrupt vector table for the interrupt routines associated with each interrupt request level input. **Power Well:** Core
2:0	0x0 WO	**Interrupt Request Level (IRL):** When writing ICW2, these bits should all be 0. During an interrupt acknowledge cycle, these bits are programmed by the interrupt controller with the interrupt to be serviced. This is combined with bits [7:3] to form the interrupt vector driven onto the data bus during the second INTA# cycle. The code is a three bit binary code: Code Master Interrupt Slave Interrupt • 000 IRQ0 IRQ8 • 001 IRQ1 IRQ9 • 010 IRQ2 IRQ10 • 011 IRQ3 IRQ11 • 100 IRQ4 IRQ12 • 101 IRQ5 IRQ13 • 110 IRQ6 IRQ14 • 111 IRQ7 IRQ15 **Power Well:** Core

64.5.10 Slave Initialization Command Word 3 (SICW3)—I/O Port A1h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: A1h

Default: 07h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 WO	**Reserved (RSVD):** Must be 0. **Power Well:** Core
2:0	0x7 WO	**Slave Identification Code (SIC):** This field must be programmed to 02h to match the code broadcast by the master controller during the INTA# sequence. **Power Well:** Core

64.5.11 Slave Initialization Command Word 4 (SICW4)—I/O Port A1h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: A1h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 WO	**Reserved (RSVD):** Must be 0. **Power Well:** Core
4	0x0 WO	**Special Fully Nested Mode (SFNM):** Should normally be disabled by writing a 0 to this bit. If SFNM=1, the special fully nested mode is programmed. **Power Well:** Core
3	0x0 WO	**Buffered Mode (BUF):** Must be cleared for non-buffered mode. Writing 1 will result in undefined behavior. **Power Well:** Core
2	0x0 WO	**Master/Slave in Buffered Mode (MSBM):** Not used. Should always be programmed to 0. **Power Well:** Core
1	0x0 WO	**Automatic End of Interrupt (AEOI):** This bit should normally be programmed to 0. This is the normal end of interrupt. If this bit is 1, the automatic end of interrupt mode is programmed. AEOI is discussed in Section 13.1.7.2 **Power Well:** Core
0	0x0 WO	**Microprocessor Mode (MM):** This bit must be written to 1 to indicate that the controller is operating in an Intel Architecture-based system. Writing 0 will result in undefined behavior.1 **Power Well:** Core

64.5.12 Slave Operational Control Word 1 (SOCW1)—I/O Port A1h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: A1h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:0	0x0 RW	**Interrupt Request Mask (IRM):** When a 1 is written to any bit in this register, the corresponding IRQ line is masked. When a 0 is written to any bit in this register, the corresponding IRQ mask bit is cleared, and interrupt requests will again be accepted by the controller. Masking IRQ2 on the master controller will also mask the interrupt requests from the slave controller. **Power Well:** Core

64.5.13 Slave Operational Control Word 2 (SOCW2)—I/O Port A0h

Following a part reset or ICW initialization, the controller enters the fully nested mode of operation. Non-specific EOI without rotation is the default. Both rotation mode and specific EOI mode are disabled following initialization.

Type: I/O Register
(Size: 8 bits)

I/O Port Address: A0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:5	0x0 WO	**Rotate and EOI Codes (REOI):** R, SL, EOI - These three bits control the Rotate and End of Interrupt modes and combinations of the two. A chart of these combinations is listed above under the bit definition. • 000 Rotate in Auto EOI Mode (Clear) • 001 Non-specific EOI command • 010 No Operation • 011 *Specific EOI Command • 100 Rotate in Auto EOI Mode (Set) • 101 Rotate on Non-Specific EOI Command • 110 *Set Priority Command • 111 *Rotate on Specific EOI Command *L0 - L2 Are Used **Power Well:** Core
4:3	0x0 WO	**OCW2 Select (O2S):** When selecting OCW2, bits 4:3 = 00 **Power Well:** Core
2:0	0x0 WO	**Interrupt Level Select (L2, L1, L0) (ILSLT):** L2, L1, and L0 determine the interrupt level acted upon when the SL bit is active. A simple binary code, outlined above, selects the channel for the command to act upon. When the SL bit is inactive, these bits do not have a defined function, programming L2, L1 and L0 to 0 is sufficient in this case. **Power Well:** Core

64.5.14 Slave Operational Control Word 3 (SOCW3)—I/O Port A0h

Type: I/O Register
(Size: 8 bits)

I/O Port Address: A0h

Default: 08h

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RO	**Reserved (RSVD):** Must be 0. **Power Well:** Core
6	0x0 WO	**Special Mask Mode (SMM):** If this bit is set, the Special Mask Mode can be used by an interrupt service routine to dynamically alter the system priority structure while the routine is executing, through selective enabling/ disabling of the other channel's mask bits. Bit 6, the ESMM bit, must be set for this bit to have any meaning. **Power Well:** Core
5	0x0 WO	**Enable Special Mask Mode (ESMM):** **Power Well:** Core
4:3	0x1 WO	**OCW3 Select (O3S):** When selecting OCW3, bits 4:3 = 01 **Power Well:** Core
2	0x0 WO	**Poll Mode Command (PMC):** When cleared, poll command is not issued. When set, the next I/O read to the interrupt controller is treated as an interrupt acknowledge cycle. An encoded byte is driven onto the data bus, representing the highest priority level requesting service. **Power Well:** Core
1:0	0x0 WO	**Register Read Command (RRC):** To retain the current selection (read ISR or read IRR), always write a 0 to bit 1 when programming this register. The selected register can be read repeatedly without reprogramming OCW3. To select a new status register, OCW3 must be reprogrammed prior to attempting the read. Value Command • 00 No Action • 01 No Action • 10 Read IRQ Register • 11 Read IS Register **Power Well:** Core

64.5.15 Master Edge/Level Control (ELCR1)—I/O Port 4D0h

Master Edge/Level Control Register

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 4D0h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:3	0x0 RW	**Edge Level Control (ELC_7_3):** In edge mode, (bit cleared), the interrupt is recognized by a low to high transition. In level mode (bit set), the interrupt is recognized by a high level. **Power Well:** Core
2:0	0x0 RO	**Reserved (RSVD):** The cascade channel(IRQ2), heart beat timer (IRQ0), and keyboard controller (IRQ1), cannot be put into level mode **Power Well:** Core

64.5.16 Slave Edge/Level Control (ELCR2)—I/O Port 4D1h

Slave Edge/Level Control Register

Type: I/O Register
(Size: 8 bits)

I/O Port Address: 4D1h

Default: 00h

Bit Range	Default & Access	Field Name (ID): Description
7:6	0x0 RW	**Edge Level Control (ELC_15_14):** In edge mode, (bit cleared), the interrupt is recognized by a low to high transition. In level mode (bit set), the interrupt is recognized by a high level. Bit 7 applies to IRQ15, and bit 6 to IRQ14. **Power Well:** Core
5	0x0 RW	**Edge Level Control (ELC_13):** In edge mode, (bit cleared), the interrupt is recognized by a low to high transition. In level mode (bit set), the interrupt is recognized by a high level. This bit applies to IRQ13. **Power Well:** Core
4:1	0x0 RW	**Edge Level Control (ELC_12_9):** In edge mode, (bit cleared), the interrupt is recognized by a low to high transition. In level mode (bit set), the interrupt is recognized by a high level. Bit 4 applies to IRQ12, bit 3 to IRQ11, bit 2 to IRQ10, and bit 1 to IRQ9. **Power Well:** Core
0	0x0 RO	**Reserved (RSVD):** The Real Time Clock (IRQ8#) cannot be programmed for level mode. **Power Well:** Core

§ §

65 Customer General-Purpose I/O Controller

65.1 Introduction and Index

The host-accessible registers for the Customer General-Purpose I/O Controller are described here. Also, the registers that allow the selection of one of a number of shared, signal functions are also described here.

Besides the Host, the customer general-purpose I/O controller are also accessible through Intel® ME Configuration Space and IE configuration Space using their own Bus, Device and Function Numbers.

The legend for the register access codes are described in Chapter 43, "Introduction."

Note: The following statement needs to be noted when referring to register Table 65-1 and Table 65-2:

The internal pull-up resistor option is not supported for 1.8V GPIOs.
The internal pull-down resistor option is not supported for 3.3V GPIOs.

65.1.1 Sideband Registers—Configurable I/O Signals

An index of the Sideband Registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method."

Table 65-1. Summary of Sideband Registers, Part 1 of 2—Sideband Port 0xC2 (Sheet 1 of 4)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
C	00000400	"Pad Base Address (PADBAR)—Offset Ch" on page 2953
10	00021000	"Miscellaneous Configuration (MISCCFG)—Offset 10h" on page 2954
20	00000000	"Pad Ownership (PAD_OWN_NORTH_ALL_0)—Offset 20h" on page 2955
24	00000000	"Pad Ownership (PAD_OWN_NORTH_ALL_1)—Offset 24h" on page 2957
28	00000000	"Pad Ownership (PAD_OWN_NORTH_ALL_2)—Offset 28h" on page 2959
2C	00000000	"Pad Ownership (PAD_OWN_NORTH_ALL_3)—Offset 2Ch" on page 2961
30	00000000	"Pad Ownership (PAD_OWN_NORTH_ALL_4)—Offset 30h" on page 2963
34	00000000	"Pad Ownership (PAD_OWN_NORTH_ALL_5)—Offset 34h" on page 2965
90	00000000	"Pad Configuration Lock (PADCFGLOCK_NORTH_ALL_0)—Offset 90h" on page 2966
94	00000000	"Pad Configuration Lock (PADCFGLOCKTX_NORTH_ALL_0)—Offset 94h" on page 2968
98	00000000	"Pad Configuration Lock (PADCFGLOCK_NORTH_ALL_1)—Offset 98h" on page 2970
9C	00000000	"Pad Configuration Lock (PADCFGLOCKTX_NORTH_ALL_1)—Offset 9Ch" on page 2971
C0	00000000	"Host Software Pad Ownership (HOSTSW_OWN_NORTH_ALL_0)—Offset C0h" on page 2972
C4	00000000	"Host Software Pad Ownership (HOSTSW_OWN_NORTH_ALL_1)—Offset C4h" on page 2974
100	00000000	"GPI Interrupt Status (GPI_IS_NORTH_ALL_0)—Offset 100h" on page 2975
104	00000000	"GPI Interrupt Status (GPI_IS_NORTH_ALL_1)—Offset 104h" on page 2977
120	00000000	"GPI Interrupt Enable (GPI_IE_NORTH_ALL_0)—Offset 120h" on page 2978
124	00000000	"GPI Interrupt Enable (GPI_IE_NORTH_ALL_1)—Offset 124h" on page 2980
140	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_NORTH_ALL_0)—Offset 140h" on page 2981
144	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_NORTH_ALL_1)—Offset 144h" on page 2983
160	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_NORTH_ALL_0)—Offset 160h" on page 2984
164	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_NORTH_ALL_1)—Offset 164h" on page 2986
180	00000000	"SMI Status (GPI_SMI_STS_NORTH_ALL_0)—Offset 180h" on page 2987
184	00000000	"SMI Status (GPI_SMI_STS_NORTH_ALL_1)—Offset 184h" on page 2989
1A0	00000000	"SMI Enable (GPI_SMI_EN_NORTH_ALL_0)—Offset 1A0h" on page 2990
1A4	00000000	"SMI Enable (GPI_SMI_EN_NORTH_ALL_1)—Offset 1A4h" on page 2992
1C0	00000000	"NMI Status (GPI_NMI_STS_NORTH_ALL_0)—Offset 1C0h" on page 2993
1C4	00000000	"NMI Status (GPI_NMI_STS_NORTH_ALL_1)—Offset 1C4h" on page 2995
1E0	00000000	"NMI Enable (GPI_NMI_EN_NORTH_ALL_0)—Offset 1E0h" on page 2996
1E4	00000000	"NMI Enable (GPI_NMI_EN_NORTH_ALL_1)—Offset 1E4h" on page 2998
400	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP0)—Offset 400h" on page 2999
404	00000018	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP0)—Offset 404h" on page 3002

Table 65-1. Summary of Sideband Registers, Part 1 of 2—Sideband Port 0xC2 (Sheet 2 of 4)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
408	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP0)—Offset 408h" on page 3003
40C	00000019	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP0)—Offset 40Ch" on page 3006
410	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP1)—Offset 410h" on page 3007
414	0000001A	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP1)—Offset 414h" on page 3010
418	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP1)—Offset 418h" on page 3011
41C	0000001B	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP1)—Offset 41Ch" on page 3014
420	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP2)—Offset 420h" on page 3015
424	0000001C	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP2)—Offset 424h" on page 3018
428	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP2)—Offset 428h" on page 3019
42C	0000001D	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP2)—Offset 42Ch" on page 3022
430	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP3)—Offset 430h" on page 3023
434	0000001E	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP3)—Offset 434h" on page 3026
438	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP3)—Offset 438h" on page 3027
43C	0000001F	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP3)—Offset 43Ch" on page 3030
440	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE2_LED0)—Offset 440h" on page 3031
444	00000020	"Pad Configuration DW1 (PAD_CFG_DW1_GBE2_LED0)—Offset 444h" on page 3034
448	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE2_LED1)—Offset 448h" on page 3035
44C	00000021	"Pad Configuration DW1 (PAD_CFG_DW1_GBE2_LED1)—Offset 44Ch" on page 3038
450	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_I2C_CLK)—Offset 450h" on page 3039
454	00002822	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_I2C_CLK)—Offset 454h" on page 3042
458	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_I2C_DATA)—Offset 458h" on page 3043
45C	00002823	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_I2C_DATA)—Offset 45Ch" on page 3046
460	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_I2C_CLK)—Offset 460h" on page 3047
464	00002824	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_I2C_CLK)—Offset 464h" on page 3050
468	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_I2C_DATA)—Offset 468h" on page 3051
46C	00002825	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_I2C_DATA)—Offset 46Ch" on page 3054
470	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_RXD0)—Offset 470h" on page 3055
474	00003026	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_RXD0)—Offset 474h" on page 3058
478	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_CLK_IN)—Offset 478h" on page 3059
47C	00003027	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_CLK_IN)—Offset 47Ch" on page 3062
480	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_RXD1)—Offset 480h" on page 3063
484	00003028	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_RXD1)—Offset 484h" on page 3066
488	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_CRS_DV)—Offset 488h" on page 3067
48C	00000029	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_CRS_DV)—Offset 48Ch" on page 3070
490	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_ARB_IN)—Offset 490h" on page 3071
494	0000102A	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_ARB_IN)—Offset 494h" on page 3074
498	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TX_EN)—Offset 498h" on page 3075
49C	0000002B	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TX_EN)—Offset 49Ch" on page 3078
4A0	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TXD0)—Offset 4A0h" on page 3079

Table 65-1. Summary of Sideband Registers, Part 1 of 2—Sideband Port 0xC2 (Sheet 3 of 4)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
4A4	0000002C	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TXD0)—Offset 4A4h" on page 3082
4A8	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TXD1)—Offset 4A8h" on page 3083
4AC	0000002D	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TXD1)—Offset 4ACh" on page 3086
4B0	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_NCSI_ARB_OUT)—Offset 4B0h" on page 3087
4B4	0000002E	"Pad Configuration DW1 (PAD_CFG_DW1_NCSI_ARB_OUT)—Offset 4B4h" on page 3090
4B8	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_LED0)—Offset 4B8h" on page 3091
4BC	0000002F	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_LED0)—Offset 4BCh" on page 3094
4C0	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE0_LED1)—Offset 4C0h" on page 3095
4C4	00000030	"Pad Configuration DW1 (PAD_CFG_DW1_GBE0_LED1)—Offset 4C4h" on page 3098
4C8	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_LED0)—Offset 4C8h" on page 3099
4CC	00000031	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_LED0)—Offset 4CCh" on page 3102
4D0	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_GBE1_LED1)—Offset 4D0h" on page 3103
4D4	00000032	"Pad Configuration DW1 (PAD_CFG_DW1_GBE1_LED1)—Offset 4D4h" on page 3106
4D8	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_0)—Offset 4D8h" on page 3107
4DC	00000033	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_0)—Offset 4DCh" on page 3110
4E0	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ0_N)—Offset 4E0h" on page 3111
4E4	00000034	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ0_N)—Offset 4E4h" on page 3114
4E8	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ1_N)—Offset 4E8h" on page 3115
4EC	00000035	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ1_N)—Offset 4ECh" on page 3118
4F0	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ2_N)—Offset 4F0h" on page 3119
4F4	00000036	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ2_N)—Offset 4F4h" on page 3122
4F8	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ3_N)—Offset 4F8h" on page 3123
4FC	00000037	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ3_N)—Offset 4FCh" on page 3126
500	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ4_N)—Offset 500h" on page 3127
504	00000038	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ4_N)—Offset 504h" on page 3130
508	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_1)—Offset 508h" on page 3131
50C	00000039	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_1)—Offset 50Ch" on page 3134
510	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_2)—Offset 510h" on page 3135
514	0000003A	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_2)—Offset 514h" on page 3138
518	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SVID_ALERT_N)—Offset 518h" on page 3139
51C	0000003B	"Pad Configuration DW1 (PAD_CFG_DW1_SVID_ALERT_N)—Offset 51Ch" on page 3142
520	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SVID_DATA)—Offset 520h" on page 3143
524	0000003C	"Pad Configuration DW1 (PAD_CFG_DW1_SVID_DATA)—Offset 524h" on page 3146
528	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SVID_CLK)—Offset 528h" on page 3147
52C	0000003D	"Pad Configuration DW1 (PAD_CFG_DW1_SVID_CLK)—Offset 52Ch" on page 3150
530	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_THERMTRIP_N)—Offset 530h" on page 3151
534	0000303E	"Pad Configuration DW1 (PAD_CFG_DW1_THERMTRIP_N)—Offset 534h" on page 3154
538	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_PROCHOT_N)—Offset 538h" on page 3155

Table 65-1. Summary of Sideband Registers, Part 1 of 2—Sideband Port 0xC2 (Sheet 4 of 4)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
53C	0000303F	"Pad Configuration DW1 (PAD_CFG_DW1_PROCHOT_N)—Offset 53Ch" on page 3158
540	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_MEMHOT_N)—Offset 540h" on page 3159
544	00003040	"Pad Configuration DW1 (PAD_CFG_DW1_MEMHOT_N)—Offset 544h" on page 3162

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 1 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
C	00000400	"Pad Base Address (PADBAR)—Offset 0Ch" on page 3163
10	00021000	"Miscellaneous Configuration (MISCCFG)—Offset 10h" on page 3164
20	00000000	"Pad Ownership (PAD_OWN_SOUTH_DFX_0)—Offset 20h" on page 3165
24	00000000	"Pad Ownership (PAD_OWN_SOUTH_DFX_1)—Offset 24h" on page 3167
28	00000000	"Pad Ownership (PAD_OWN_SOUTH_DFX_2)—Offset 28h" on page 3169
2C	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_0)—Offset 2Ch" on page 3170
30	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_1)—Offset 30h" on page 3172
34	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_2)—Offset 34h" on page 3174
38	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_3)—Offset 38h" on page 3176
3C	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_4)—Offset 3Ch" on page 3178
40	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_5)—Offset 40h" on page 3180
44	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP0_6)—Offset 44h" on page 3182
48	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP1_0)—Offset 48h" on page 3183
4C	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP1_1)—Offset 4Ch" on page 3185
50	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP1_2)—Offset 50h" on page 3187
54	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP1_3)—Offset 54h" on page 3189
58	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP1_4)—Offset 58h" on page 3191
5C	00000000	"Pad Ownership (PAD_OWN_SOUTH_GROUP1_5)—Offset 5Ch" on page 3193
90	00000000	"Pad Configuration Lock (PADCFGLOCK_SOUTH_DFX_0)—Offset 90h" on page 3194
94	00000000	"Pad Configuration Lock (PADCFGLOCKTX_SOUTH_DFX_0)—Offset 94h" on page 3196
98	00000000	"Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP0_0)—Offset 98h" on page 3198
9C	00000000	"Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP0_0)—Offset 9Ch" on page 3200
A0	00000000	"Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP0_1)—Offset A0h" on page 3202
A4	00000000	"Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP0_1)—Offset A4h" on page 3204
A8	00000000	"Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP1_0)—Offset A8h" on page 3206
AC	00000000	"Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP1_0)—Offset ACh" on page 3208
B0	00000000	"Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP1_1)—Offset B0h" on page 3210
B4	00000000	"Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP1_1)—Offset B4h" on page 3211
C0	00000000	"Host Software Pad Ownership (HOSTSW_OWN_SOUTH_DFX_0)—Offset C0h" on page 3212
C4	00000000	"Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP0_0)—Offset C4h" on page 3214
C8	00000000	"Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP0_1)—Offset C8h" on page 3216
CC	00000000	"Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP1_0)—Offset CCh" on page 3218
D0	00000000	"Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP1_1)—Offset D0h" on page 3220
100	00000000	"GPI Interrupt Status (GPI_IS_SOUTH_DFX_0)—Offset 100h" on page 3221
104	00000000	"GPI Interrupt Status (GPI_IS_SOUTH_GROUP0_0)—Offset 104h" on page 3223
108	00000000	"GPI Interrupt Status (GPI_IS_SOUTH_GROUP0_1)—Offset 108h" on page 3225

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 2 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
10C	00000000	"GPI Interrupt Status (GPI_IS_SOUTH_GROUP1_0)—Offset 10Ch" on page 3227
110	00000000	"GPI Interrupt Status (GPI_IS_SOUTH_GROUP1_1)—Offset 110h" on page 3229
120	00000000	"GPI Interrupt Enable (GPI_IE_SOUTH_DFX_0)—Offset 120h" on page 3230
124	00000000	"GPI Interrupt Enable (GPI_IE_SOUTH_GROUP0_0)—Offset 124h" on page 3232
128	00000000	"GPI Interrupt Enable (GPI_IE_SOUTH_GROUP0_1)—Offset 128h" on page 3234
12C	00000000	"GPI Interrupt Enable (GPI_IE_SOUTH_GROUP1_0)—Offset 12Ch" on page 3236
130	00000000	"GPI Interrupt Enable (GPI_IE_SOUTH_GROUP1_1)—Offset 130h" on page 3238
140	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_DFX_0)—Offset 140h" on page 3239
144	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP0_0)—Offset 144h" on page 3241
148	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP0_1)—Offset 148h" on page 3243
14C	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP1_0)—Offset 14Ch" on page 3245
150	00000000	"GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP1_1)—Offset 150h" on page 3247
160	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_DFX_0)—Offset 160h" on page 3248
164	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP0_0)—Offset 164h" on page 3250
168	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP0_1)—Offset 168h" on page 3252
16C	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP1_0)—Offset 16Ch" on page 3254
170	00000000	"GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP1_1)—Offset 170h" on page 3256
184	00000000	"SMI Status (GPI_SMI_STS_SOUTH_GROUP0_0)—Offset 184h" on page 3257
188	00000000	"SMI Status (GPI_SMI_STS_SOUTH_GROUP0_1)—Offset 188h" on page 3259
18C	00000000	"SMI Status (GPI_SMI_STS_SOUTH_GROUP1_0)—Offset 18Ch" on page 3261
190	00000000	"SMI Status (GPI_SMI_STS_SOUTH_GROUP1_1)—Offset 190h" on page 3263
1A4	00000000	"SMI Enable (GPI_SMI_EN_SOUTH_GROUP0_0)—Offset 1A4h" on page 3264
1A8	00000000	"SMI Enable (GPI_SMI_EN_SOUTH_GROUP0_1)—Offset 1A8h" on page 3266
1AC	00000000	"SMI Enable (GPI_SMI_EN_SOUTH_GROUP1_0)—Offset 1ACh" on page 3268
1B0	00000000	"SMI Enable (GPI_SMI_EN_SOUTH_GROUP1_1)—Offset 1B0h" on page 3270
1C4	00000000	"NMI Status (GPI_NMI_STS_SOUTH_GROUP0_0)—Offset 1C4h" on page 3271
1C8	00000000	"NMI Status (GPI_NMI_STS_SOUTH_GROUP0_1)—Offset 1C8h" on page 3273
1CC	00000000	"NMI Status (GPI_NMI_STS_SOUTH_GROUP1_0)—Offset 1CCh" on page 3275
1D0	00000000	"NMI Status (GPI_NMI_STS_SOUTH_GROUP1_1)—Offset 1D0h" on page 3277
1E4	00000000	"NMI Enable (GPI_NMI_EN_SOUTH_GROUP0_0)—Offset 1E4h" on page 3278
1E8	00000000	"NMI Enable (GPI_NMI_EN_SOUTH_GROUP0_1)—Offset 1E8h" on page 3280
1EC	00000000	"NMI Enable (GPI_NMI_EN_SOUTH_GROUP1_0)—Offset 1ECh" on page 3282
1F0	00000000	"NMI Enable (GPI_NMI_EN_SOUTH_GROUP1_1)—Offset 1F0h" on page 3284

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 3 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
400	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT_CLK0)—Offset 400h" on page 3285
404	00000041	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT_CLK0)—Offset 404h" on page 3288
408	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT_CLK1)—Offset 408h" on page 3289
40C	00000042	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT_CLK1)—Offset 40Ch" on page 3292
410	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT0)—Offset 410h" on page 3293
414	00000043	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT0)—Offset 414h" on page 3296
418	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT1)—Offset 418h" on page 3297
41C	00000044	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT1)—Offset 41Ch" on page 3300
420	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT2)—Offset 420h" on page 3301
424	00000045	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT2)—Offset 424h" on page 3304
428	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT3)—Offset 428h" on page 3305
42C	00000046	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT3)—Offset 42Ch" on page 3308
430	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT4)—Offset 430h" on page 3309
434	00000047	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT4)—Offset 434h" on page 3312
438	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT5)—Offset 438h" on page 3313
43C	00000048	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT5)—Offset 43Ch" on page 3316
440	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT6)—Offset 440h" on page 3317
444	00000049	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT6)—Offset 444h" on page 3320
448	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT7)—Offset 448h" on page 3321
44C	0000004A	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT7)—Offset 44Ch" on page 3324
450	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT8)—Offset 450h" on page 3325
454	0000004B	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT8)—Offset 454h" on page 3328
458	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT9)—Offset 458h" on page 3329
45C	0000004C	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT9)—Offset 45Ch" on page 3332
460	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT10)—Offset 460h" on page 3333
464	0000004D	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT10)—Offset 464h" on page 3336
468	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT11)—Offset 468h" on page 3337
46C	0000004E	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT11)—Offset 46Ch" on page 3340
470	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT12)—Offset 470h" on page 3341
474	0000004F	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT12)—Offset 474h" on page 3344
478	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT13)—Offset 478h" on page 3345
47C	00000050	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT13)—Offset 47Ch" on page 3348
480	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT14)—Offset 480h" on page 3349
484	00000051	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT14)—Offset 484h" on page 3352
488	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT15)—Offset 488h" on page 3353
48C	00000052	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT15)—Offset 48Ch" on page 3356
490	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_12)—Offset 490h" on page 3357
494	00000053	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_12)—Offset 494h" on page 3360

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 4 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
498	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_ALRT_N)—Offset 498h" on page 3361
49C	00000054	"Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_ALRT_N)—Offset 49Ch" on page 3364
4A0	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ5_N)—Offset 4A0h" on page 3365
4A4	00000055	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ5_N)—Offset 4A4h" on page 3368
4A8	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ6_N)—Offset 4A8h" on page 3369
4AC	00000056	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ6_N)—Offset 4ACh" on page 3372
4B0	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ7_N)—Offset 4B0h" on page 3373
4B4	00000057	"Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ7_N)—Offset 4B4h" on page 3376
4B8	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_UART0_RXD)—Offset 4B8h" on page 3377
4BC	00003058	"Pad Configuration DW1 (PAD_CFG_DW1_UART0_RXD)—Offset 4BCh" on page 3380
4C0	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_UART0_TXD)—Offset 4C0h" on page 3381
4C4	00000059	"Pad Configuration DW1 (PAD_CFG_DW1_UART0_TXD)—Offset 4C4h" on page 3384
4C8	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_CLK)—Offset 4C8h" on page 3385
4CC	0000305A	"Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_CLK)—Offset 4CCh" on page 3388
4D0	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_DATA)—Offset 4D0h" on page 3389
4D4	0000305B	"Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_DATA)—Offset 4D4h" on page 3392
4D8	45000601	"Pad Configuration DW0 (PAD_CFG_DW0_ERROR2_N)—Offset 4D8h" on page 3393
4DC	0000005C	"Pad Configuration DW1 (PAD_CFG_DW1_ERROR2_N)—Offset 4DCh" on page 3396
4E0	45000601	"Pad Configuration DW0 (PAD_CFG_DW0_ERROR1_N)—Offset 4E0h" on page 3397
4E4	0000005D	"Pad Configuration DW1 (PAD_CFG_DW1_ERROR1_N)—Offset 4E4h" on page 3400
4E8	45000601	"Pad Configuration DW0 (PAD_CFG_DW0_ERROR0_N)—Offset 4E8h" on page 3401
4EC	0000005E	"Pad Configuration DW1 (PAD_CFG_DW1_ERROR0_N)—Offset 4ECh" on page 3404
4F0	44000601	"Pad Configuration DW0 (PAD_CFG_DW0_IERR_N)—Offset 4F0h" on page 3405
4F4	0000005F	"Pad Configuration DW1 (PAD_CFG_DW1_IERR_N)—Offset 4F4h" on page 3408
4F8	44000601	"Pad Configuration DW0 (PAD_CFG_DW0_MCERR_N)—Offset 4F8h" on page 3409
4FC	00000060	"Pad Configuration DW1 (PAD_CFG_DW1_MCERR_N)—Offset 4FCh" on page 3412
500	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_CLK)—Offset 500h" on page 3413
504	00003061	"Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_CLK)—Offset 504h" on page 3416
508	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_DATA)—Offset 508h" on page 3417
50C	00003062	"Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_DATA)—Offset 50Ch" on page 3420
510	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_ALRT_N)—Offset 510h" on page 3421
514	00003063	"Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_ALRT_N)—Offset 514h" on page 3424
518	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB1_HOST_DATA)—Offset 518h" on page 3425
51C	00003064	"Pad Configuration DW1 (PAD_CFG_DW1_SMB1_HOST_DATA)—Offset 51Ch" on page 3428
520	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB1_HOST_CLK)—Offset 520h" on page 3429
524	00003065	"Pad Configuration DW1 (PAD_CFG_DW1_SMB1_HOST_CLK)—Offset 524h" on page 3432

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 5 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
528	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB2_PECI_DATA)—Offset 528h" on page 3433
52C	00003066	"Pad Configuration DW1 (PAD_CFG_DW1_SMB2_PECI_DATA)—Offset 52Ch" on page 3436
530	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB2_PECI_CLK)—Offset 530h" on page 3437
534	00003067	"Pad Configuration DW1 (PAD_CFG_DW1_SMB2_PECI_CLK)—Offset 534h" on page 3440
538	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_DATA)—Offset 538h" on page 3441
53C	00003068	"Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_DATA)—Offset 53Ch" on page 3444
540	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_CLK)—Offset 540h" on page 3445
544	00003069	"Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_CLK)—Offset 544h" on page 3448
548	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_ALRT_N)—Offset 548h" on page 3449
54C	0000306A	"Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_ALRT_N)—Offset 54Ch" on page 3452
550	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_USB_OC0_N)—Offset 550h" on page 3453
554	0000306B	"Pad Configuration DW1 (PAD_CFG_DW1_USB_OC0_N)—Offset 554h" on page 3456
558	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_FLEX_CLK_SE0)—Offset 558h" on page 3457
55C	0000006C	"Pad Configuration DW1 (PAD_CFG_DW1_FLEX_CLK_SE0)—Offset 55Ch" on page 3460
560	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_FLEX_CLK_SE1)—Offset 560h" on page 3461
564	0000006D	"Pad Configuration DW1 (PAD_CFG_DW1_FLEX_CLK_SE1)—Offset 564h" on page 3464
568	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_4)—Offset 568h" on page 3465
56C	0000006E	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_4)—Offset 56Ch" on page 3468
570	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_5)—Offset 570h" on page 3469
574	0000006F	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_5)—Offset 574h" on page 3472
578	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_6)—Offset 578h" on page 3473
57C	00000070	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_6)—Offset 57Ch" on page 3476
580	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_7)—Offset 580h" on page 3477
584	00000071	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_7)—Offset 584h" on page 3480
588	45000700	"Pad Configuration DW0 (PAD_CFG_DW0_SATA0_LED_N)—Offset 588h" on page 3481
58C	00000072	"Pad Configuration DW1 (PAD_CFG_DW1_SATA0_LED_N)—Offset 58Ch" on page 3484
590	45000700	"Pad Configuration DW0 (PAD_CFG_DW0_SATA1_LED_N)—Offset 590h" on page 3485
594	00000073	"Pad Configuration DW1 (PAD_CFG_DW1_SATA1_LED_N)—Offset 594h" on page 3488
598	45000700	"Pad Configuration DW0 (PAD_CFG_DW0_SATA_PDETECT0)—Offset 598h" on page 3489
59C	00000074	"Pad Configuration DW1 (PAD_CFG_DW1_SATA_PDETECT0)—Offset 59Ch" on page 3492
5A0	45000700	"Pad Configuration DW0 (PAD_CFG_DW0_SATA_PDETECT1)—Offset 5A0h" on page 3493
5A4	00000075	"Pad Configuration DW1 (PAD_CFG_DW1)—Offset 5A4h" on page 3496
5A8	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_SATA0_SDOUT)—Offset 5A8h" on page 3497
5AC	00000076	"Pad Configuration DW1 (PAD_CFG_DW1_SATA0_SDOUT)—Offset 5ACh" on page 3500
5B0	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_SATA1_SDOUT)—Offset 5B0h" on page 3501
5B4	00000018	"Pad Configuration DW1 (PAD_CFG_DW1_SATA1_SDOUT)—Offset 5B4h" on page 3504

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 6 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
5B8	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_UART1_RXD)—Offset 5B8h" on page 3505
5BC	00003019	"Pad Configuration DW1 (PAD_CFG_DW1_UART1_RXD)—Offset 5BCh" on page 3508
5C0	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_UART1_TXD)—Offset 5C0h" on page 3509
5C4	0000001A	"Pad Configuration DW1 (PAD_CFG_DW1_UART1_TXD)—Offset 5C4h" on page 3512
5C8	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_8)—Offset 5C8h" on page 3513
5CC	0000001B	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_8)—Offset 5CCh" on page 3516
5D0	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_9)—Offset 5D0h" on page 3517
5D4	0000001C	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_9)—Offset 5D4h" on page 3520
5D8	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_TCK)—Offset 5D8h" on page 3521
5DC	0400101D	"Pad Configuration DW1 (PAD_CFG_DW1_TCK)—Offset 5DCh" on page 3524
5E0	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_TRST_N)—Offset 5E0h" on page 3525
5E4	0400301E	"Pad Configuration DW1 (PAD_CFG_DW1_TRST_N)—Offset 5E4h" on page 3528
5E8	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_TMS)—Offset 5E8h" on page 3529
5EC	0400301F	"Pad Configuration DW1 (PAD_CFG_DW1_TMS)—Offset 5ECh" on page 3532
5F0	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_TDI)—Offset 5F0h" on page 3533
5F4	04003020	"Pad Configuration DW1 (PAD_CFG_DW1_TDI)—Offset 5F4h" on page 3536
5F8	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_TDO)—Offset 5F8h" on page 3537
5FC	00000021	"Pad Configuration DW1 (PAD_CFG_DW1_TDO)—Offset 5FCh" on page 3540
600	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_CX_PRDY_N)—Offset 600h" on page 3541
604	00003022	"Pad Configuration DW1 (PAD_CFG_DW1_CX_PRDY_N)—Offset 604h" on page 3544
608	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_CX_PREQ_N)—Offset 608h" on page 3545
60C	04003023	"Pad Configuration DW1 (PAD_CFG_DW1_CX_PREQ_N)—Offset 60Ch" on page 3548
610	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_CTBTRIGINOUT)—Offset 610h" on page 3549
614	04003024	"Pad Configuration DW1 (PAD_CFG_DW1_CTBTRIGINOUT)—Offset 614h" on page 3552
618	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_CTBTRIGOUT)—Offset 618h" on page 3553
61C	04000025	"Pad Configuration DW1 (PAD_CFG_DW1_CTBTRIGOUT)—Offset 61Ch" on page 3556
620	44000300	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE2)—Offset 620h" on page 3557
624	04000026	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE2)—Offset 624h" on page 3560
628	44000300	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE3)—Offset 628h" on page 3561
62C	04000027	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE3)—Offset 62Ch" on page 3564
630	44000300	"Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE4)—Offset 630h" on page 3565
634	00000028	"Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE4)—Offset 634h" on page 3568
638	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SUSPWRDNACK)—Offset 638h" on page 3569
63C	00000029	"Pad Configuration DW1 (PAD_CFG_DW1_SUSPWRDNACK)—Offset 63Ch" on page 3572
640	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_SUSCLK)—Offset 640h" on page 3573
644	0000002A	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_SUSCLK)—Offset 644h" on page 3576
648	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_ADR_TRIGGER)—Offset 648h" on page 3577
64C	0000002B	"Pad Configuration DW1 (PAD_CFG_DW1_ADR_TRIGGER)—Offset 64Ch" on page 3580
650	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_SLP_S45_N)—Offset 650h" on page 3581

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 7 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
654	0000002C	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_SLP_S45_N)—Offset 654h" on page 3584
658	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_SLP_S3_N)—Offset 658h" on page 3585
65C	0000002D	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_SLP_S3_N)—Offset 65Ch" on page 3588
660	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_WAKE_N)—Offset 660h" on page 3589
664	0000302E	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_WAKE_N)—Offset 664h" on page 3592
668	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_PWRBTN_N)—Offset 668h" on page 3593
66C	0000302F	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_PWRBTN_N)—Offset 66Ch" on page 3596
670	45000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_RESETBUTTON_N)—Offset 670h" on page 3597
674	00003030	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_RESETBUTTON_N)—Offset 674h" on page 3600
678	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_PMU_PLTRST_N)—Offset 678h" on page 3601
67C	00000031	"Pad Configuration DW1 (PAD_CFG_DW1_PMU_PLTRST_N)—Offset 67Ch" on page 3604
680	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SUS_STAT_N)—Offset 680h" on page 3605
684	00000032	"Pad Configuration DW1 (PAD_CFG_DW1_SUS_STAT_N)—Offset 684h" on page 3608
688	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SLP_S0IX_N)—Offset 688h" on page 3609
68C	00000033	"Pad Configuration DW1 (PAD_CFG_DW1_SLP_S0IX_N)—Offset 68Ch" on page 3612
690	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_CS0_N)—Offset 690h" on page 3613
694	00003C34	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_CS0_N)—Offset 694h" on page 3616
698	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_CS1_N)—Offset 698h" on page 3617
69C	00003C35	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_CS1_N)—Offset 69Ch" on page 3620
6A0	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_MOSI_IO0)—Offset 6A0h" on page 3621
6A4	00003C36	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_MOSI_IO0)—Offset 6A4h" on page 3624
6A8	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_MISO_IO1)—Offset 6A8h" on page 3625
6AC	00003C37	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_MISO_IO1)—Offset 6ACh" on page 3628
6B0	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_IO2)—Offset 6B0h" on page 3629
6B4	00003C38	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_IO2)—Offset 6B4h" on page 3632
6B8	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_IO3)—Offset 6B8h" on page 3633
6BC	00003C39	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_IO3)—Offset 6BCh" on page 3636
6C0	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_CLK)—Offset 6C0h" on page 3637
6C4	00003C3A	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_CLK)—Offset 6C4h" on page 3640
6C8	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_SPI_CLK_LOOPBK)—Offset 6C8h" on page 3641
6CC	00003C3B	"Pad Configuration DW1 (PAD_CFG_DW1_SPI_CLK_LOOPBK)—Offset 6CCh" on page 3644
6D0	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO0)—Offset 6D0h" on page 3645
6D4	00003C3C	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO0)—Offset 6D4h" on page 3648
6D8	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO1)—Offset 6D8h" on page 3649
6DC	00003C3D	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO1)—Offset 6DCh" on page 3652
6E0	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO2)—Offset 6E0h" on page 3653
6E4	00003C3E	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO2)—Offset 6E4h" on page 3656
6E8	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO3)—Offset 6E8h" on page 3657

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 8 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
6EC	00003C3F	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO3)—Offset 6ECh" on page 3660
6F0	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CS0_N)—Offset 6F0h" on page 3661
6F4	00000040	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CS0_N)—Offset 6F4h" on page 3664
6F8	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CLK)—Offset 6F8h" on page 3665
6FC	00001041	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CLK)—Offset 6FCh" on page 3668
700	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_RST_N)—Offset 700h" on page 3669
704	00001042	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_RST_N)—Offset 704h" on page 3672
708	45000A00	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_ALRT0_N)—Offset 708h" on page 3673
70C	00000043	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_ALRT0_N)—Offset 70Ch" on page 3676
710	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_10)—Offset 710h" on page 3677
714	00000044	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_10)—Offset 714h" on page 3680
718	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_11)—Offset 718h" on page 3681
71C	00000045	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_11)—Offset 71Ch" on page 3684
720	44000600	"Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CLK_LOOPBK)—Offset 720h" on page 3685
724	00000046	"Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CLK_LOOPBK)—Offset 724h" on page 3688
728	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_CMD)—Offset 728h" on page 3689
72C	00000047	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_CMD)—Offset 72Ch" on page 3692
730	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_STROBE)—Offset 730h" on page 3693
734	00000048	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_STROBE)—Offset 734h" on page 3696
738	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_CLK)—Offset 738h" on page 3697
73C	00000049	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_CLK)—Offset 73Ch" on page 3700
740	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D0)—Offset 740h" on page 3701
744	0000004A	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D0)—Offset 744h" on page 3704
748	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D1)—Offset 748h" on page 3705
74C	0000004B	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D1)—Offset 74Ch" on page 3708
750	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D2)—Offset 750h" on page 3709
754	0000004C	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D2)—Offset 754h" on page 3712
758	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D3)—Offset 758h" on page 3713
75C	0000004D	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D3)—Offset 75Ch" on page 3716
760	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D4)—Offset 760h" on page 3717
764	0000004E	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D4)—Offset 764h" on page 3720
768	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D5)—Offset 768h" on page 3721
76C	0000004F	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D5)—Offset 76Ch" on page 3724
770	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D6)—Offset 770h" on page 3725
774	00000050	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D6)—Offset 774h" on page 3728
778	45000300	"Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D7)—Offset 778h" on page 3729

Table 65-2. Summary of Sideband Registers, Part 2 of 2—Sideband Port 0xC5 (Sheet 9 of 9)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
77C	00000051	"Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D7)—Offset 77Ch" on page 3732
780	45000200	"Pad Configuration DW0 (PAD_CFG_DW0_GPIO_3)—Offset 780h" on page 3733
784	00000052	"Pad Configuration DW1 (PAD_CFG_DW1_GPIO_3)—Offset 784h" on page 3736

65.2 Sideband Registers, Part 1 of 2—Sideband Port 0xC2

65.2.1 Pad Base Address (PADBAR)—Offset Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + Ch
Host Memory Space: SBREG_BAR + 0xC20000 + Ch

Default: 00000400h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD_0):** Reserved.
15:0	0x400 RO	**Pad Base Address (PADBAR):** This field provides the starting byte-align address of Pad0 register sets within a Community. It is meant for software to discover from where the very first Pad register (i.e. Pad0 register) starts to compute the next Pad address offsets.

65.2.2 Miscellaneous Configuration (MISCCFG)—Offset 10h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 10h
Host Memory Space: SBREG_BAR + 0xC20000 + 10h

Default: 00021000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Reserved (Reserved1):** Reserved
19:16	0x2 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW2):** This register assigns a specific GPIO Group to the ACPI GPE0[95:64]. The setting is SoC specific.
15:12	0x1 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW1):** This register assigns a specific GPIO Group to the ACPI GPE0[63:32]. The setting is SoC specific.
11:8	0x0 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW0):** GPIO Group to GPE_DW0 assignment encoding (GPE0_DW0[3:0]): This register assigns a specific GPIO Group to the ACPI GPE0[31:0]. The setting is SoC specific.
7:5	0x0 RW	**Reserved (Reserved2):** Reserved
4	0x0 RW	**NCSI Outbound Signal Staging Control (NCSI_STAGE_EN):** NCSI Signal Staging Control: This register controls the bypass/staging logic for the GBE NCSI output signals - when 1, the signals will be staged with NCSI_ARB_CLK; when 0, the flops will be bypassed.
3	0x0 RW	**GPIO Driver IRQ Route (GPIO_DRIVER_IRQ_ROUTE):** GPIO Driver IRQ_ROUTE[1:0]: Specifies the APIC IRQ globally for all pads within the current community (GPI_IS with corresponding GPI_IE enable). • 0 = IRQ14 • 1 = IRQ15
2	0x0 RW	**GSX Static Local Clock Gating (GSXSLCGEN):** GSX Static Local Clock Gating (GSXSLCGEn) Specify whether the GSX controller should be statically clock gated for power saving if it is not enabled (even though the capability is available). • 0 = Disable dynamic local clock gating • 1 = Enable dynamic local clock gating
1	0x0 RW	**GPIO Dynamic Partition Clock Gating Enable (GPDPCGEN):** GPIO Dynamic Partition Clock Gating Enable (GPDPCGEn) Specify whether the GPIO Community should take part in partition clock gating • 0 = Disable participation in dynamic partition clock gating • 1 = Enable participation in dynamic partition clock gating
0	0x0 RW	**GPIO Dynamic Local Clock Gating Enable (GPDLCGEN):** GPIO Dynamic Local Clock Gating Enable (GPDLCGEn) Specify whether the GPIO Community should perform local clock gating • 0 = Disable dynamic local clock gating • 1 = Enable dynamic local clock gating

65.2.3 Pad Ownership (PAD_OWN_NORTH_ALL_0)—Offset 20h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 20h
Host Memory Space: SBREG_BAR + 0xC20000 + 20h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_SDP3):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_SDP3):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_SDP2):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_SDP2):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_SDP1):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_SDP1):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_SDP0):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_SDP0):** See Description for bits [29:28] of this register.

65.2.4 Pad Ownership (PAD_OWN_NORTH_ALL_1)—Offset 24h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 24h
Host Memory Space: SBREG_BAR + 0xC20000 + 24h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_CLK_IN):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_RXD0):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_I2C_DATA):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_I2C_CLK):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_I2C_DATA):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_I2C_CLK):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_GBE2_LED1):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_GBE2_LED0):** See Description for bits [29:28] of this register.

65.2.5 Pad Ownership (PAD_OWN_NORTH_ALL_2)—Offset 28h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 28h
Host Memory Space: SBREG_BAR + 0xC20000 + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_LED0):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_ARB_OUT):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_TXD1):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_TXD0):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_TX_EN):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_ARB_IN):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_CRS_DV):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_NCSI_RXD1):** See Description for bits [29:28] of this register.

65.2.6 Pad Ownership (PAD_OWN_NORTH_ALL_3)—Offset 2Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 2Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ3_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ2_N):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ1_N):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ0_N):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_0):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_LED1):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_GBE1_LED0):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_GBE0_LED1):** See Description for bits [29:28] of this register.

65.2.7 Pad Ownership (PAD_OWN_NORTH_ALL_4)—Offset 30h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 30h
Host Memory Space: SBREG_BAR + 0xC20000 + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_PROCHOT_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_THERMTRIP_N):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_SVID_CLK):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_SVID_DATA):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_SVID_ALERT_N):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_2):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_1):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ4_N):** See Description for bits [29:28] of this register.

65.2.8 Pad Ownership (PAD_OWN_NORTH_ALL_5)—Offset 34h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 34h
Host Memory Space: SBREG_BAR + 0xC20000 + 34h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:2	0x0 RO	**Reserved (RSVD_0):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_MEMHOT_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.

65.2.9 Pad Configuration Lock (PADCFGLOCK_NORTH_ALL_0)—Offset 90h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 90h
Host Memory Space: SBREG_BAR + 0xC20000 + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ3_N):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
30	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_ARB_IN):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RW	**Pad Config Lock (PADCFGLOCK_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.10 Pad Configuration Lock (PADCFGLOCKTX_NORTH_ALL_0)—Offset 94h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 94h
Host Memory Space: SBREG_BAR + 0xC20000 + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ3_N):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
30	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_ARB_IN):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.11 Pad Configuration Lock (PADCFGLOCK_NORTH_ALL_1)—Offset 98h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 98h
Host Memory Space: SBREG_BAR + 0xC20000 + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_MEMHOT_N):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.12 Pad Configuration Lock (PADCFGLOCKTX_NORTH_ALL_1)—Offset 9Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 9Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_MEMHOT_N):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.13 Host Software Pad Ownership (HOSTSW_OWN_NORTH_ALL_0)—Offset C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + C0h
Host Memory Space: SBREG_BAR + 0xC20000 + C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ3_N):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... Bit N-1= pad N-1
30	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_CLK_IN):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
14	0x0 RW	**HostSW_Own (HOSTSW_OWN_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.14 Host Software Pad Ownership (HOSTSW_OWN_NORTH_ALL_1)—Offset C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + C4h
Host Memory Space: SBREG_BAR + 0xC20000 + C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_MEMHOT_N):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... Bit N-1= pad N-1
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.15 GPI Interrupt Status (GPI_IS_NORTH_ALL_0)—Offset 100h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 100h
Host Memory Space: SBREG_BAR + 0xC20000 + 100h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ3_N):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... Bit N-1= pad N-1
30	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_CRS_DV):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.16 GPI Interrupt Status (GPI_IS_NORTH_ALL_1)—Offset 104h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 104h
Host Memory Space: SBREG_BAR + 0xC20000 + 104h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_MEMHOT_N):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... Bit N-1= pad N-1
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.17 GPI Interrupt Enable (GPI_IE_NORTH_ALL_0)—Offset 120h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 120h
Host Memory Space: SBREG_BAR + 0xC20000 + 120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ3_N):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... Bit N-1= pad N-1
30	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_CRS_DV):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.18 GPI Interrupt Enable (GPI_IE_NORTH_ALL_1)—Offset 124h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 124h
Host Memory Space: SBREG_BAR + 0xC20000 + 124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_MEMHOT_N):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... Bit N-1= pad N-1
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.19 Reserved[0-5] (RSVD6[0-5])—Offset 128h, Count 6, Stride 4h

65.2.20 GPI General Purpose Events Status (GPI_GPE_STS_NORTH_ALL_0)—Offset 140h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 140h
Host Memory Space: SBREG_BAR + 0xC20000 + 140h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ3_N):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... Bit N-1= Pad N-1
30	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_ARB_IN):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.21 GPI General Purpose Events Status (GPI_GPE_STS_NORTH_ALL_1)—Offset 144h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 144h
Host Memory Space: SBREG_BAR + 0xC20000 + 144h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_MEMHOT_N):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... Bit N-1= Pad N-1
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.22 GPI General Purpose Events Enable (GPI_GPE_EN_NORTH_ALL_0)—Offset 160h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 160h
Host Memory Space: SBREG_BAR + 0xC20000 + 160h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ3_N):** This bit is used to enable/disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i] bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
30	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_RXD1):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.23 GPI General Purpose Events Enable (GPI_GPE_EN_NORTH_ALL_1)—Offset 164h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 164h
Host Memory Space: SBREG_BAR + 0xC20000 + 164h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_MEMHOT_N):** This bit is used to enable/ disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.24 SMI Status (GPI_SMI_STS_NORTH_ALL_0)—Offset 180h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 180h
Host Memory Space: SBREG_BAR + 0xC20000 + 180h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ3_N):** This bit is set to '1' by hardware when a level event (See RxEdCfg, RxInv) is detected, and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding PAD_OWN[2:0] is '000' (i.e. ACPI GPIO Mode). If the following conditions are true, then an SMI will be generated if the GPI_SMI_STS bit is set: 1. The corresponding bit in the GPI_SMI_EN register is set 2. The corresponding pad's GPIROUTSMI is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no SMI event • 1 = There is an SMI event The state of GPI_SMI_EN[x] does not prevent the setting of GPI_SMI_STS[x]. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 Defaults for these bits are dependent on the state of the GPI pads.
30	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_ARB_IN):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RO	**GPI SMI Status (GPI_SMI_STS_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RO	**GPI SMI Status (GPI_SMI_STS_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.25 SMI Status (GPI_SMI_STS_NORTH_ALL_1)—Offset 184h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 184h
Host Memory Space: SBREG_BAR + 0xC20000 + 184h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RO	**GPI SMI Status (GPI_SMI_STS_MEMHOT_N):** This bit is set to '1' by hardware when a level event (See RxEdCfg, RxInv) is detected, and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding PAD_OWN[2:0] is '000' (i.e. ACPI GPIO Mode). If the following conditions are true, then an SMI will be generated if the GPI_SMI_STS bit is set: 1. The corresponding bit in the GPI_SMI_EN register is set 2. The corresponding pad's GPIROUTSMI is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no SMI event • 1 = There is an SMI event The state of GPI_SMI_EN[x] does not prevent the setting of GPI_SMI_STS[x]. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 Defaults for these bits are dependent on the state of the GPI pads.
7	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RO	**GPI SMI Status (GPI_SMI_STS_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_1):**See Description for bit [8] of this register.
0	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.26 SMI Enable (GPI_SMI_EN_NORTH_ALL_0)—Offset 1A0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 1A0h
Host Memory Space: SBREG_BAR + 0xC20000 + 1A0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ3_N):** This bit is used to enable/disable the generation of SMI when the corresponding GPI_SMI_STS bit is set. The pad must also be routed for SMI functionality in order for SMI to be generated, i.e. the corresponding GPIROUTSMI must be set to '1'. • 0 = disable SMI generation • 1 = enable SMI generation ***Note:*** Each of the bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1
30	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_RXD1):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.27 SMI Enable (GPI_SMI_EN_NORTH_ALL_1)—Offset 1A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 1A4h
Host Memory Space: SBREG_BAR + 0xC20000 + 1A4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_MEMHOT_N):** This bit is used to enable/disable the generation of SMI when the corresponding GPI_SMI_STS bit is set. The pad must also be routed for SMI functionality in order for SMI to be generated, i.e. the corresponding GPIROUTSMI must be set to '1'. • 0 = disable SMI generation • 1 = enable SMI generation ***Note:*** Each of the bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1
7	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.28 NMI Status (GPI_NMI_STS_NORTH_ALL_0)—Offset 1C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 1C0h
Host Memory Space: SBREG_BAR + 0xC20000 + 1C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ3_N):** This bit is set to '1' by hardware when an edge event is detected (See RxEdCfg, RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding GPIONMIRout is set to '1', i.e. programmed to route as NMI The corresponding GPIOOwn[2:0] is '000' (i.e. ACPI GPIO Mode). • The corresponding GPI_NMI_EN is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no NMI event • 1 = There is an NMI event Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
30	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_CRS_DV):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_RXD1):** See Description for bit [31] of this register.
15	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RO	**GPI NMI Status (GPI_NMI_STS_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RO	**GPI NMI Status (GPI_NMI_STS_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.29 NMI Status (GPI_NMI_STS_NORTH_ALL_1)—Offset 1C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 1C4h
Host Memory Space: SBREG_BAR + 0xC20000 + 1C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RO	**GPI NMI Status (GPI_NMI_STS_MEMHOT_N):** This bit is set to '1' by hardware when an edge event is detected (See RxEdCfg, RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding GPIONMIRout is set to '1', i.e. programmed to route as NMI The corresponding GPIOOwn[2:0] is '000' (i.e. ACPI GPIO Mode). • The corresponding GPI_NMI_EN is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no NMI event • 1 = There is an NMI event Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
7	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RO	**GPI NMI Status (GPI_NMI_STS_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.30 NMI Enable (GPI_NMI_EN_NORTH_ALL_0)—Offset 1E0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 1E0h
Host Memory Space: SBREG_BAR + 0xC20000 + 1E0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ3_N):** This bit is used to enable/disable the generation of NMI when the corresponding GPI_NMI_STS bit is set and its GPIROUTNMI is set. • 0 = disable NMI generation • 1 = enable NMI generation Each bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
30	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ2_N):** See Description for bit [31] of this register.
29	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ1_N):** See Description for bit [31] of this register.
28	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ0_N):** See Description for bit [31] of this register.
27	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_0):** See Description for bit [31] of this register.
26	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_LED1):** See Description for bit [31] of this register.
25	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_LED0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_LED1):** See Description for bit [31] of this register.
23	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_LED0):** See Description for bit [31] of this register.
22	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_ARB_OUT):** See Description for bit [31] of this register.
21	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_TXD1):** See Description for bit [31] of this register.
20	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_TXD0):** See Description for bit [31] of this register.
19	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_TX_EN):** See Description for bit [31] of this register.
18	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_ARB_IN):** See Description for bit [31] of this register.
17	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_CRS_DV):** See Description for bit [31] of this register.
16	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_RXD1):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_CLK_IN):** See Description for bit [31] of this register.
14	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_NCSI_RXD0):** See Description for bit [31] of this register.
13	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_I2C_DATA):** See Description for bit [31] of this register.
12	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_I2C_CLK):** See Description for bit [31] of this register.
11	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_I2C_DATA):** See Description for bit [31] of this register.
10	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_I2C_CLK):** See Description for bit [31] of this register.
9	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE2_LED1):** See Description for bit [31] of this register.
8	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE2_LED0):** See Description for bit [31] of this register.
7	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_SDP3):** See Description for bit [31] of this register.
6	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_SDP3):** See Description for bit [31] of this register.
5	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_SDP2):** See Description for bit [31] of this register.
4	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_SDP2):** See Description for bit [31] of this register.
3	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_SDP1):** See Description for bit [31] of this register.
2	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_SDP1):** See Description for bit [31] of this register.
1	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE1_SDP0):** See Description for bit [31] of this register.
0	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_GBE0_SDP0):** See Description for bit [31] of this register.

65.2.31 NMI Enable (GPI_NMI_EN_NORTH_ALL_1)—Offset 1E4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 1E4h
Host Memory Space: SBREG_BAR + 0xC20000 + 1E4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:9	0x0 RO	**Reserved (RSVD_0):** Reserved.
8	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_MEMHOT_N):** This bit is used to enable/disable the generation of NMI when the corresponding GPI_NMI_STS bit is set and its GPIROUTNMI is set. • 0 = disable NMI generation • 1 = enable NMI generation Each bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
7	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PROCHOT_N):** See Description for bit [8] of this register.
6	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_THERMTRIP_N):** See Description for bit [8] of this register.
5	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SVID_CLK):** See Description for bit [8] of this register.
4	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SVID_DATA):** See Description for bit [8] of this register.
3	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SVID_ALERT_N):** See Description for bit [8] of this register.
2	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_2):** See Description for bit [8] of this register.
1	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_1):** See Description for bit [8] of this register.
0	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ4_N):** See Description for bit [8] of this register.

65.2.32 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP0)—Offset 400h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 400h
Host Memory Space: SBREG_BAR + 0xC20000 + 400h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.33 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP0)—Offset 404h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 404h
Host Memory Space: SBREG_BAR + 0xC20000 + 404h

Default: 00000018h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x18 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.34 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP0)—Offset 408h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 408h
Host Memory Space: SBREG_BAR + 0xC20000 + 408h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.35 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP0)—Offset 40Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 40Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 40Ch

Default: 00000019h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x19 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.36 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP1)—Offset 410h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 410h
Host Memory Space: SBREG_BAR + 0xC20000 + 410h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.37 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP1)—Offset 414h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 414h
Host Memory Space: SBREG_BAR + 0xC20000 + 414h

Default: 0000001Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.38 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP1)—Offset 418h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 418h
Host Memory Space: SBREG_BAR + 0xC20000 + 418h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.39 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP1)—Offset 41Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 41Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 41Ch

Default: 0000001Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.40 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP2)—Offset 420h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 420h
Host Memory Space: SBREG_BAR + 0xC20000 + 420h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.41 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP2)—Offset 424h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 424h
Host Memory Space: SBREG_BAR + 0xC20000 + 424h

Default: 0000001Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.42 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP2)—Offset 428h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 428h
Host Memory Space: SBREG_BAR + 0xC20000 + 428h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.43 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP2)—Offset 42Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 42Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 42Ch

Default: 0000001Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.44 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_SDP3)—Offset 430h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 430h
Host Memory Space: SBREG_BAR + 0xC20000 + 430h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.45 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_SDP3)—Offset 434h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 434h
Host Memory Space: SBREG_BAR + 0xC20000 + 434h

Default: 0000001Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.46 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_SDP3)—Offset 438h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 438h
Host Memory Space: SBREG_BAR + 0xC20000 + 438h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.47 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_SDP3)—Offset 43Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 43Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 43Ch

Default: 0000001Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.48 Pad Configuration DW0 (PAD_CFG_DW0_GBE2_LED0)—Offset 440h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 440h
Host Memory Space: SBREG_BAR + 0xC20000 + 440h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.49 Pad Configuration DW1 (PAD_CFG_DW1_GBE2_LED0)—Offset 444h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 444h
Host Memory Space: SBREG_BAR + 0xC20000 + 444h

Default: 00000020h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x20 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.50 Pad Configuration DW0 (PAD_CFG_DW0_GBE2_LED1)—Offset 448h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 448h
Host Memory Space: SBREG_BAR + 0xC20000 + 448h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.51 Pad Configuration DW1 (PAD_CFG_DW1_GBE2_LED1)—Offset 44Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 44Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 44Ch

Default: 00000021h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x21 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.52 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_I2C_CLK)—Offset 450h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 450h
Host Memory Space: SBREG_BAR + 0xC20000 + 450h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.53 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_I2C_CLK)—Offset 454h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 454h
Host Memory Space: SBREG_BAR + 0xC20000 + 454h

Default: 00002822h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xa RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x22 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.54 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_I2C_DATA)—Offset 458h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 458h
Host Memory Space: SBREG_BAR + 0xC20000 + 458h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.55 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_I2C_DATA)—Offset 45Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 45Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 45Ch

Default: 00002823h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xa RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x23 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.56 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_I2C_CLK)—Offset 460h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 460h
Host Memory Space: SBREG_BAR + 0xC20000 + 460h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.



Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.57 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_I2C_CLK)—Offset 464h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 464h
Host Memory Space: SBREG_BAR + 0xC20000 + 464h

Default: 00002824h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xa RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x24 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.58 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_I2C_DATA)—Offset 468h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 468h
Host Memory Space: SBREG_BAR + 0xC20000 + 468h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.59 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_I2C_DATA)—Offset 46Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 46Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 46Ch

Default: 00002825h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xa RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x25 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.60 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_RXD0)—Offset 470h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 470h
Host Memory Space: SBREG_BAR + 0xC20000 + 470h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.61 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_RXD0)—Offset 474h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 474h
Host Memory Space: SBREG_BAR + 0xC20000 + 474h

Default: 00003026h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x26 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.62 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_CLK_IN)—Offset 478h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 478h
Host Memory Space: SBREG_BAR + 0xC20000 + 478h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.63 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_CLK_IN)—Offset 47Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 47Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 47Ch

Default: 00003027h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x27 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.64 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_RXD1)—Offset 480h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 480h
Host Memory Space: SBREG_BAR + 0xC20000 + 480h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.65 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_RXD1)—Offset 484h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 484h
Host Memory Space: SBREG_BAR + 0xC20000 + 484h

Default: 00003028h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x28 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.66 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_CRS_DV)—Offset 488h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 488h
Host Memory Space: SBREG_BAR + 0xC20000 + 488h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.67 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_CRS_DV)—Offset 48Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 48Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 48Ch

Default: 00000029h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x29 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.68 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_ARB_IN)—Offset 490h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 490h
Host Memory Space: SBREG_BAR + 0xC20000 + 490h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.69 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_ARB_IN)—Offset 494h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 494h
Host Memory Space: SBREG_BAR + 0xC20000 + 494h

Default: 0000102Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x4 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.70 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TX_EN)—Offset 498h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 498h
Host Memory Space: SBREG_BAR + 0xC20000 + 498h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.71 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TX_EN)—Offset 49Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 49Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 49Ch

Default: 0000002Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.72 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TXD0)—Offset 4A0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4A0h
Host Memory Space: SBREG_BAR + 0xC20000 + 4A0h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.73 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TXD0)—Offset 4A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4A4h
Host Memory Space: SBREG_BAR + 0xC20000 + 4A4h

Default: 0000002Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.74 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_TXD1)—Offset 4A8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4A8h
Host Memory Space: SBREG_BAR + 0xC20000 + 4A8h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.75 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_TXD1)—Offset 4ACh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4ACh
Host Memory Space: SBREG_BAR + 0xC20000 + 4ACh

Default: 0000002Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.76 Pad Configuration DW0 (PAD_CFG_DW0_NCSI_ARB_OUT)—Offset 4B0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4B0h
Host Memory Space: SBREG_BAR + 0xC20000 + 4B0h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.77 Pad Configuration DW1 (PAD_CFG_DW1_NCSI_ARB_OUT)—Offset 4B4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4B4h
Host Memory Space: SBREG_BAR + 0xC20000 + 4B4h

Default: 0000002Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.78 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_LED0)—Offset 4B8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4B8h
Host Memory Space: SBREG_BAR + 0xC20000 + 4B8h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.79 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_LED0)—Offset 4BCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4BCh
Host Memory Space: SBREG_BAR + 0xC20000 + 4BCh

Default: 0000002Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.80 Pad Configuration DW0 (PAD_CFG_DW0_GBE0_LED1)—Offset 4C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4C0h
Host Memory Space: SBREG_BAR + 0xC20000 + 4C0h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.81 Pad Configuration DW1 (PAD_CFG_DW1_GBE0_LED1)—Offset 4C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4C4h
Host Memory Space: SBREG_BAR + 0xC20000 + 4C4h

Default: 00000030h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x30 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.82 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_LED0)—Offset 4C8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4C8h
Host Memory Space: SBREG_BAR + 0xC20000 + 4C8h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.83 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_LED0)—Offset 4CCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4CCh
Host Memory Space: SBREG_BAR + 0xC20000 + 4CCh

Default: 00000031h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x31 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.84 Pad Configuration DW0 (PAD_CFG_DW0_GBE1_LED1)—Offset 4D0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4D0h
Host Memory Space: SBREG_BAR + 0xC20000 + 4D0h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.85 Pad Configuration DW1 (PAD_CFG_DW1_GBE1_LED1)—Offset 4D4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4D4h
Host Memory Space: SBREG_BAR + 0xC20000 + 4D4h

Default: 00000032h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x32 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.86 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_0)—Offset 4D8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4D8h
Host Memory Space: SBREG_BAR + 0xC20000 + 4D8h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.87 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_0)—Offset 4DCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4DCh
Host Memory Space: SBREG_BAR + 0xC20000 + 4DCh

Default: 00000033h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x33 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.88 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ0_N)—Offset 4E0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4E0h
Host Memory Space: SBREG_BAR + 0xC20000 + 4E0h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.89 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ0_N)—Offset 4E4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4E4h
Host Memory Space: SBREG_BAR + 0xC20000 + 4E4h

Default: 00000034h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x34 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.90 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ1_N)—Offset 4E8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4E8h
Host Memory Space: SBREG_BAR + 0xC20000 + 4E8h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.91 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ1_N)—Offset 4ECh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4ECh
Host Memory Space: SBREG_BAR + 0xC20000 + 4ECh

Default: 00000035h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x35 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.92 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ2_N)—Offset 4F0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4F0h
Host Memory Space: SBREG_BAR + 0xC20000 + 4F0h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.93 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ2_N)—Offset 4F4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4F4h
Host Memory Space: SBREG_BAR + 0xC20000 + 4F4h

Default: 00000036h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x36 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.94 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ3_N)—Offset 4F8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4F8h
Host Memory Space: SBREG_BAR + 0xC20000 + 4F8h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.95 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ3_N)—Offset 4FCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 4FCh
Host Memory Space: SBREG_BAR + 0xC20000 + 4FCh

Default: 00000037h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x37 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.96 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ4_N)—Offset 500h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 500h
Host Memory Space: SBREG_BAR + 0xC20000 + 500h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.97 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ4_N)—Offset 504h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 504h
Host Memory Space: SBREG_BAR + 0xC20000 + 504h

Default: 00000038h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x38 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.98 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_1)—Offset 508h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 508h
Host Memory Space: SBREG_BAR + 0xC20000 + 508h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Pre Glitch Filter Stage RX Pad State Select (PreGfRXSel) Determine if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. 0 = Select synchronized, non filtered RX pad state 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.99 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_1)—Offset 50Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 50Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 50Ch

Default: 00000039h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x39 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.100 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_2)—Offset 510h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 510h
Host Memory Space: SBREG_BAR + 0xC20000 + 510h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.101 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_2)—Offset 514h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 514h
Host Memory Space: SBREG_BAR + 0xC20000 + 514h

Default: 0000003Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.102 Pad Configuration DW0 (PAD_CFG_DW0_SVID_ALERT_N)—Offset 518h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 518h
Host Memory Space: SBREG_BAR + 0xC20000 + 518h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.103 Pad Configuration DW1 (PAD_CFG_DW1_SVID_ALERT_N)—Offset 51Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 51Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 51Ch

Default: 0000003Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.104 Pad Configuration DW0 (PAD_CFG_DW0_SVID_DATA)—Offset 520h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 520h
Host Memory Space: SBREG_BAR + 0xC20000 + 520h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.105 Pad Configuration DW1 (PAD_CFG_DW1_SVID_DATA)—Offset 524h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 524h
Host Memory Space: SBREG_BAR + 0xC20000 + 524h

Default: 0000003Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.106 Pad Configuration DW0 (PAD_CFG_DW0_SVID_CLK)—Offset 528h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 528h
Host Memory Space: SBREG_BAR + 0xC20000 + 528h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.107 Pad Configuration DW1 (PAD_CFG_DW1_SVID_CLK)—Offset 52Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 52Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 52Ch

Default: 0000003Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.108 Pad Configuration DW0 (PAD_CFG_DW0_THERMTRIP_N)—Offset 530h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 530h
Host Memory Space: SBREG_BAR + 0xC20000 + 530h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.109 Pad Configuration DW1 (PAD_CFG_DW1_THERMTRIP_N)—Offset 534h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 534h
Host Memory Space: SBREG_BAR + 0xC20000 + 534h

Default: 0000303Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.110 Pad Configuration DW0 (PAD_CFG_DW0_PROCHOT_N)—Offset 538h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 538h
Host Memory Space: SBREG_BAR + 0xC20000 + 538h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.111 Pad Configuration DW1 (PAD_CFG_DW1_PROCHOT_N)—Offset 53Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 53Ch
Host Memory Space: SBREG_BAR + 0xC20000 + 53Ch

Default: 0000303Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.2.112 Pad Configuration DW0 (PAD_CFG_DW0_MEMHOT_N)—Offset 540h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 540h
Host Memory Space: SBREG_BAR + 0xC20000 + 540h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.2.113 Pad Configuration DW1 (PAD_CFG_DW1_MEMHOT_N)—Offset 544h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC2] + 544h
Host Memory Space: SBREG_BAR + 0xC20000 + 544h

Default: 00003040h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x40 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3 Sideband Registers, Part 2 of 2—Sideband Port 0xC5

65.3.1 Pad Base Address (PADBAR)—Offset 0Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 0Ch

Default: 00000400h

Bit Range	Default & Access	Field Name (ID): Description
31:16	0x0 RO	**Reserved (RSVD_0):** Reserved
15:0	0x400 RO	**Pad Base Address (PADBAR):** This field provides the starting byte-align address of Pad0 register sets within a Community. It is meant for software to discover from where the very first Pad register (i.e. Pad0 register) starts to compute the next Pad address offsets.

65.3.2 Miscellaneous Configuration (MISCCFG)—Offset 10h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 10h
Host Memory Space: SBREG_BAR + 0xC50000 + 10h

Default: 00021000h

Bit Range	Default & Access	Field Name (ID): Description
31:20	0x0 RW	**Reserved (RSVD_1):** Reserved
19:16	0x2 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW2):** This register assigns a specific GPIO Group to the ACPI GPE0[95:64].
15:12	0x1 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW1):** GPIO Group to GPE_DW0 assignment encoding (GPE0_DW1[3:0]) : This register assigns a specific GPIO Group to the ACPI GPE0[63:32].
11:8	0x0 RW	**GPIO Group to GPE_DW0 assignment encoding (GPE0_DW0):** GPIO Group to GPE_DW0 assignment encoding (GPE0_DW0[3:0]) : This register assigns a specific GPIO Group to the ACPI GPE0[31:0].
7:5	0x0 RW	**Reserved (Re2):** Reserved
4	0x0 RW	**NCSI Inbound Signal Staging Control (NCSI_STAGE_EN):** This register controls the bypass/ staging logic for the GBE NCSI input signals - when 1, the signals will be staged with NCSI_ARB_CLK; when 0, the flops will be bypassed.
3	0x0 RW	**GPIO Driver IRQ Route (GPIO_DRIVER_IRQ_ROUTE):** GPIO Driver IRQ_ROUTE[1:0]: Specifies the APIC IRQ globally for all pads within the current community (GPI_IS with corresponding GPI_IE enable). • 0 = IRQ14 • 1 = IRQ15
2	0x0 RW	**GSX Static Local Clock Gating (GSXSLCGEN):** GSX Static Local Clock Gating (GSXSLCGEn) Specify whether the GSX controller should be statically clock gated for power saving if it is not enabled (even though the capability is available). • 0 = Disable dynamic local clock gating • 1 = Enable dynamic local clock gating
1	0x0 RW	**GPIO Dynamic Partition Clock Gating Enable (GPDPCGEN):** GPIO Dynamic Partition Clock Gating Enable (GPDPCGEn) Specify whether the GPIO Community should take part in partition clock gating • 0 = Disable participation in dynamic partition clock gating • 1 = Enable participation in dynamic partition clock gating
0	0x0 RW	**GPIO Dynamic Local Clock Gating Enable (GPDLCGEN):** GPIO Dynamic Local Clock Gating Enable (GPDLCGEn) Specify whether the GPIO Community should perform local clock gating. • 0 = Disable dynamic local clock gating • 1 = Enable dynamic local clock gating

65.3.3 Pad Ownership (PAD_OWN_SOUTH_DFX_0)—Offset 20h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 20h
Host Memory Space: SBREG_BAR + 0xC50000 + 20h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT5):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT4):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT3):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT2):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT1):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT0):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT_CLK1):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT_CLK0):** See Description for bits [29:28] of this register.

65.3.4 Pad Ownership (PAD_OWN_SOUTH_DFX_1)—Offset 24h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 24h
Host Memory Space: SBREG_BAR + 0xC50000 + 24h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT13):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT12):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT11):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT10):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT9):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT8):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT7):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT6):** See Description for bits [29:28] of this register.

65.3.5 Pad Ownership (PAD_OWN_SOUTH_DFX_2)—Offset 28h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 28h
Host Memory Space: SBREG_BAR + 0xC50000 + 28h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved (RSVD_0):** Reserved.
5:4	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT15):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
3:2	0x0 RO	**Reserved (RSVD_1):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_DFX_PORT14):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.

65.3.6 Pad Ownership (PAD_OWN_SOUTH_GROUP0_0)—Offset 2Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 2Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 2Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_SMB5_GBE_CLK):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_UART0_TXD):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_UART0_RXD):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ7_N):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ6_N):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_PCIE_CLKREQ5_N):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_SMB5_GBE_ALRT_N):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_12):** See Description for bits [29:28] of this register.

65.3.7 Pad Ownership (PAD_OWN_SOUTH_GROUP0_1)—Offset 30h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 30h
Host Memory Space: SBREG_BAR + 0xC50000 + 30h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_SMB0_LEG_DATA):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_SMB0_LEG_CLK):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_MCERR_N):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_IERR_N):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_ERROR0_N):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_ERROR1_N):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_ERROR2_N):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_SMB5_GBE_DATA):** See Description for bits [29:28] of this register.

65.3.8 Pad Ownership (PAD_OWN_SOUTH_GROUP0_2)—Offset 34h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 34h
Host Memory Space: SBREG_BAR + 0xC50000 + 34h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_SMB4_CSME0_ALRT_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_SMB4_CSME0_CLK):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_SMB4_CSME0_DATA):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_SMB2_PECI_CLK):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_SMB2_PECI_DATA):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_SMB1_HOST_CLK):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_SMB1_HOST_DATA):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_SMB0_LEG_ALRT_N):** See Description for bits [29:28] of this register.

65.3.9 Pad Ownership (PAD_OWN_SOUTH_GROUP0_3)—Offset 38h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 38h
Host Memory Space: SBREG_BAR + 0xC50000 + 38h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_SATA0_LED_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_7):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_6):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_5):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_4):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_FLEX_CLK_SE1):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_FLEX_CLK_SE0):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_USB_OC0_N):** See Description for bits [29:28] of this register.

65.3.10 Pad Ownership (PAD_OWN_SOUTH_GROUP0_4)—Offset 3Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 3Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 3Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_8):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_UART1_TXD):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_UART1_RXD):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_SATA1_SDOUT):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_SATA0_SDOUT):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_SATA_PDETECT1):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_SATA_PDETECT0):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_SATA1_LED_N):** See Description for bits [29:28] of this register.

65.3.11 Pad Ownership (PAD_OWN_SOUTH_GROUP0_5)—Offset 40h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 40h
Host Memory Space: SBREG_BAR + 0xC50000 + 40h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_CX_PREQ_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_CX_PRDY_N):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_TDO):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_TDI):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_TMS):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_TRST_N):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_TCK):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_9):** See Description for bits [29:28] of this register.

65.3.12 Pad Ownership (PAD_OWN_SOUTH_GROUP0_6)—Offset 44h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 44h
Host Memory Space: SBREG_BAR + 0xC50000 + 44h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_DFX_SPARE4):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
15:14	0x0 RO	**Reserved (RSVD_1):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_DFX_SPARE3):** See Description for bits [17:16] of this register.
11:10	0x0 RO	**Reserved (RSVD_2):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_DFX_SPARE2):** See Description for bits [17:16] of this register.
7:6	0x0 RO	**Reserved (RSVD_3):** Reserved.
5:4	0x0 RW	**Pad Ownership (PAD_OWN_CTBTRIGOUT):** See Description for bits [17:16] of this register.
3:2	0x0 RO	**Reserved (RSVD_4):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_CTBTRIGINOUT):** See Description for bits [17:16] of this register.

65.3.13 Pad Ownership (PAD_OWN_SOUTH_GROUP1_0)—Offset 48h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 48h
Host Memory Space: SBREG_BAR + 0xC50000 + 48h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_PMU_RESETBUTTON_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_PMU_PWRBTN_N):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_PMU_WAKE_N):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_PMU_SLP_S3_N):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_PMU_SLP_S45_N):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_ADR_TRIGGER):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_PMU_SUSCLK):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_SUSPWRDNACK):** See Description for bits [29:28] of this register.

65.3.14 Pad Ownership (PAD_OWN_SOUTH_GROUP1_1)—Offset 4Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 4Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_SPI_IO2):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_SPI_MISO_IO1):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_SPI_MOSI_IO0):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_SPI_CS1_N):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_SPI_CS0_N):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_SLP_S0IX_N):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_SUS_STAT_N):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_PMU_PLTRST_N):** See Description for bits [29:28] of this register.

65.3.15 Pad Ownership (PAD_OWN_SOUTH_GROUP1_2)—Offset 50h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 50h
Host Memory Space: SBREG_BAR + 0xC50000 + 50h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_CS0_N):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_IO3):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_IO2):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_IO1):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_IO0):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_SPI_CLK_LOOPBK):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_SPI_CLK):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_SPI_IO3):** See Description for bits [29:28] of this register.

65.3.16 Pad Ownership (PAD_OWN_SOUTH_GROUP1_3)—Offset 54h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 54h
Host Memory Space: SBREG_BAR + 0xC50000 + 54h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_STROBE):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_CMD):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_CLK_LOOPBK):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_11):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_10):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_ALRT0_N):** See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_RST_N):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_ESPI_CLK):** See Description for bits [29:28] of this register.

65.3.17 Pad Ownership (PAD_OWN_SOUTH_GROUP1_4)—Offset 58h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 58h
Host Memory Space: SBREG_BAR + 0xC50000 + 58h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved (RSVD_0):** Reserved.
29:28	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D6):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
27:26	0x0 RO	**Reserved (RSVD_1):** Reserved.
25:24	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D5):** See Description for bits [29:28] of this register.
23:22	0x0 RO	**Reserved (RSVD_2):** Reserved.
21:20	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D4):** See Description for bits [29:28] of this register.
19:18	0x0 RO	**Reserved (RSVD_3):** Reserved.
17:16	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D3):** See Description for bits [29:28] of this register.
15:14	0x0 RO	**Reserved (RSVD_4):** Reserved.
13:12	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D2):** See Description for bits [29:28] of this register.
11:10	0x0 RO	**Reserved (RSVD_5):** Reserved.
9:8	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D1):**See Description for bits [29:28] of this register.
7:6	0x0 RO	**Reserved (RSVD_6):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
5:4	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D0):** See Description for bits [29:28] of this register.
3:2	0x0 RO	**Reserved (RSVD_7):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_CLK):** See Description for bits [29:28] of this register.

65.3.18 Pad Ownership (PAD_OWN_SOUTH_GROUP1_5)—Offset 5Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 5Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved (RSVD_0):** Reserved.
5:4	0x0 RW	**Pad Ownership (PAD_OWN_GPIO_3):** This register can be written by the Intel® Management Engine (Intel® ME) GPIO Function only.** Write access without Intel® ME GPIO Function SAI shall be dropped. There is no SAI restriction on register read. Encoding: • 00 = Host GPIO ACPI Mode or GPIO Driver Mode. Host software (ACPI or GPIO Driver) has ownership of the pad. In Host GPIO Driver Mode (refer to HOSTSW_OWN), GPIO input event update is limited to GPI_INT_STS update only. Otherwise in Host ACPI Mode, updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. No read/write restriction to the Pad Configuration register set during host ownership. During host ownership, Intel® ME, IE and ISH do not own this pad and are not notified of the GPIO input event. • 01 = Intel® ME GPIO Mode. The Intel® ME has ownership of the pad. All accesses to Pad Configuration register set must be verified with Intel® ME GPIO Function SAI **. Non-posted cycle access without Intel® ME SAI shall result in Unsuccessful Completion status. Posted cycle access without Intel® ME SAI shall be dropped. In Intel® ME GPIO Mode, the host related status registers related to the pad (refer to host ownership above) are masked from being updated by GPIO input event. If IOSF-SB Virtual Wire message generation is enabled for this pad, GPIO hardware sends the Virtual Wire message to Intel® ME GPIO Function. Only the Intel® ME GPIO Function is notified of the GPIO input event. • 10 = ISH GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying ISH GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the ISH GPIO Function. • 11 = IE GPIO Mode. Same description as Intel® ME GPIO Mode above except verifying IE GPIO Function SAI for pad related register accesses and the Virtual Wire message is delivered to the IE GPIO Function. **During DFx mode, Secure DFx can write to the PAD_OWN.
3:2	0x0 RO	**Reserved (RSVD_1):** Reserved.
1:0	0x0 RW	**Pad Ownership (PAD_OWN_EMMC_D7):** See Description for bits [5:4] of this register.

65.3.19 Pad Configuration Lock (PADCFGLOCK_SOUTH_DFX_0)—Offset 90h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 90h
Host Memory Space: SBREG_BAR + 0xC50000 + 90h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT15):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
16	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT3):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT2):** See Description for bit [17] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT1):** See Description for bit [17] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT0):** See Description for bit [17] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.20 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_DFX_0)—Offset 94h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 94h
Host Memory Space: SBREG_BAR + 0xC50000 + 94h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT15):** Pad Configuration Lock GPIO TxState (PadCfgLockTx) PadCfgLockTx locks the GPIOTxState bit from being configured. The GPIOTxState register becomes Read-Only and software writes to the register have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1 = Locks the Pad Configuration GPIOTXState field as read-only (RO) Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1 = pad N-1 When PadCfgLockTx[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
16	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT3):** See Description for bit [17] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT2):** See Description for bit [17] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT1):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT0):** See Description for bit [17] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.21 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP0_0)—Offset 98h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 98h
Host Memory Space: SBREG_BAR + 0xC50000 + 98h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Pad Config Lock (PADCFGLOCK_SATA0_LED_N):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
30	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**Pad Config Lock (PADCFGLOCK_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**Pad Config Lock (PADCFGLOCK_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW	**Pad Config Lock (PADCFGLOCK_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB4_CSME0_CLK):**See Description for bit [31] of this register.
21	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB1_HOST_CLK):** See Description for bit [31] of this register.



Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW	**Pad Config Lock (PADCFGLOCK_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW	**Pad Config Lock (PADCFGLOCK_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW	**Pad Config Lock (PADCFGLOCK_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW	**Pad Config Lock (PADCFGLOCK_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW	**Pad Config Lock (PADCFGLOCK_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_12):** See Description for bit [31] of this register.

65.3.22 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP0_0)—Offset 9Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 9Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 9Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SATA0_LED_N):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
30	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB1_HOST_CLK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_12):** See Description for bit [31] of this register.

65.3.23 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP0_1)—Offset A0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + A0h
Host Memory Space: SBREG_BAR + 0xC50000 + A0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_SPARE4):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
19	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RW	**Pad Config Lock (PADCFGLOCK_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW	**Pad Config Lock (PADCFGLOCK_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW	**Pad Config Lock (PADCFGLOCK_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW	**Pad Config Lock (PADCFGLOCK_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW	**Pad Config Lock (PADCFGLOCK_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW	**Pad Config Lock (PADCFGLOCK_TDO):** See Description for bit [20] of this register.
12	0x0 RW	**Pad Config Lock (PADCFGLOCK_TDI):** See Description for bit [20] of this register.
11	0x0 RW	**Pad Config Lock (PADCFGLOCK_TMS):** See Description for bit [20] of this register.
10	0x0 RW	**Pad Config Lock (PADCFGLOCK_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW	**Pad Config Lock (PADCFGLOCK_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_9):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.24 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP0_1)—Offset A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + A4h
Host Memory Space: SBREG_BAR + 0xC50000 + A4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_SPARE4):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
19	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_TDO):** See Description for bit [20] of this register.
12	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_TDI):** See Description for bit [20] of this register.
11	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_TMS):** See Description for bit [20] of this register.
10	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_9):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.25 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP1_0)—Offset A8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + A8h
Host Memory Space: SBREG_BAR + 0xC50000 + A8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_STROBE):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
30	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW	**Pad Config Lock (PADCFGLOCK_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW	**Pad Config Lock (PADCFGLOCK_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW	**Pad Config Lock (PADCFGLOCK_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW	**Pad Config Lock (PADCFGLOCK_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.26 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP1_0)—Offset ACh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + ACh
Host Memory Space: SBREG_BAR + 0xC50000 + ACh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_STROBE):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
30	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.



Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.27 Pad Configuration Lock (PADCFGLOCK_SOUTH_GROUP1_1)—Offset B0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + B0h
Host Memory Space: SBREG_BAR + 0xC50000 + B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**Pad Config Lock (PADCFGLOCK_GPIO_3):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
8	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**Pad Config Lock (PADCFGLOCK_EMMC_CLK):** See Description for bit [9] of this register.

65.3.28 Pad Configuration Lock (PADCFGLOCKTX_SOUTH_GROUP1_1)—Offset B4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + B4h
Host Memory Space: SBREG_BAR + 0xC50000 + B4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_GPIO_3):** PadCfgLock locks specific register fields in the pad specific registers (in Community or Pad) from being configured. The registers affected become Read-Only and software writes to these registers have no effect. This field is meaningful and takes effect only if the pad is owned by host (refer to PAD_OWN register). Pads under other ownership are not affected by the PadCfgLock. 0 = Unlock 1= Lock the following register fields as read-only (RO): • Pad Configuration registers (exclude GPIOTXState) • GPI_NMI_EN Register (if implemented) • GPI_SMI_EN Register (if implemented) • GPI_GPE_EN Register (if implemented) • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 When PadCfgLock[n] is written from a '1' to a '0' (unlock), a synchronous SMI# is generated if enabled. This ensures that only SMM code can change the above GPIO registers after the lockdown.
8	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**Pad Config Lock TXState (PADCFGLOCKTX_EMMC_CLK):** See Description for bit [9] of this register.

65.3.29 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_DFX_0)—Offset C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + C0h
Host Memory Space: SBREG_BAR + 0xC50000 + C0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT15):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
16	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT3):** See Description for bit [17] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT2):** See Description for bit [17] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT1):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT0):** See Description for bit [17] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.30 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP0_0)—Offset C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + C4h
Host Memory Space: SBREG_BAR + 0xC50000 + C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**HostSW_Own (HOSTSW_OWN_SATA0_LED_N):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
30	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**HostSW_Own (HOSTSW_OWN_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**HostSW_Own (HOSTSW_OWN_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW	**HostSW_Own (HOSTSW_OWN_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.



Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW	**HostSW_Own (HOSTSW_OWN_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW	**HostSW_Own (HOSTSW_OWN_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW	**HostSW_Own (HOSTSW_OWN_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW	**HostSW_Own (HOSTSW_OWN_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW	**HostSW_Own (HOSTSW_OWN_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_12):** See Description for bit [31] of this register.

65.3.31 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP0_1)—Offset C8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + C8h
Host Memory Space: SBREG_BAR + 0xC50000 + C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_SPARE4):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
19	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RW	**HostSW_Own (HOSTSW_OWN_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW	**HostSW_Own (HOSTSW_OWN_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW	**HostSW_Own (HOSTSW_OWN_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW	**HostSW_Own (HOSTSW_OWN_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW	**HostSW_Own (HOSTSW_OWN_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW	**HostSW_Own (HOSTSW_OWN_TDO):** See Description for bit [20] of this register.
12	0x0 RW	**HostSW_Own (HOSTSW_OWN_TDI):** See Description for bit [20] of this register.
11	0x0 RW	**HostSW_Own (HOSTSW_OWN_TMS):** See Description for bit [20] of this register.
10	0x0 RW	**HostSW_Own (HOSTSW_OWN_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW	**HostSW_Own (HOSTSW_OWN_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_UART1_TXD):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.32 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP1_0)—Offset CCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + CCh
Host Memory Space: SBREG_BAR + 0xC50000 + CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_STROBE):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
30	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW	**HostSW_Own (HOSTSW_OWN_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_IO3):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW	**HostSW_Own (HOSTSW_OWN_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW	**HostSW_Own (HOSTSW_OWN_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW	**HostSW_Own (HOSTSW_OWN_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.33 Host Software Pad Ownership (HOSTSW_OWN_SOUTH_GROUP1_1)—Offset D0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + D0h
Host Memory Space: SBREG_BAR + 0xC50000 + D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**HostSW_Own (HOSTSW_OWN_GPIO_3):** This register determines the appropriate host status bit update when a pad is under host ownership (refer to PAD_OWN). 0 = ACPI Mode. GPIO input event updates are limited to GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS. GPI_INT_STS update is masked. 1 = GPIO Driver Mode. GPIO input event updates are limited to GPI_INT_STS. GPI_GPE_STS, GPI_NMI_STS and/or GPI_SMI_STS updates are masked. Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
8	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**HostSW_Own (HOSTSW_OWN_EMMC_CLK):** See Description for bit [9] of this register.

65.3.34 GPI Interrupt Status (GPI_IS_SOUTH_DFX_0)—Offset 100h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 100h
Host Memory Space: SBREG_BAR + 0xC50000 + 100h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT15):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
16	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT3):** See Description for bit [17] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT2):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT1):** See Description for bit [17] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT0):** See Description for bit [17] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.35 GPI Interrupt Status (GPI_IS_SOUTH_GROUP0_0)—Offset 104h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 104h
Host Memory Space: SBREG_BAR + 0xC50000 + 104h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SATA0_LED_N):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
30	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB1_HOST_DATA):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_12):** See Description for bit [31] of this register.

65.3.36 GPI Interrupt Status (GPI_IS_SOUTH_GROUP0_1)—Offset 108h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 108h
Host Memory Space: SBREG_BAR + 0xC50000 + 108h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RO	**GPI Interrupt Status (GPI_INT_STS_DFX_SPARE4):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
19	0x0 RO	**GPI Interrupt Status (GPI_INT_STS_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RO	**GPI Interrupt Status (GPI_INT_STS_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_TDO):** See Description for bit [20] of this register.
12	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_TDI):** See Description for bit [20] of this register.
11	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_TMS):** See Description for bit [20] of this register.
10	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_TCK):** See Description for bit [20] of this register.
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_8):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.37 GPI Interrupt Status (GPI_IS_SOUTH_GROUP1_0)—Offset 10Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 10Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 10Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_STROBE):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
30	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_CLK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.38 GPI Interrupt Status (GPI_IS_SOUTH_GROUP1_1)—Offset 110h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 110h
Host Memory Space: SBREG_BAR + 0xC50000 + 110h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_GPIO_3):** This bit is set to '1' by hardware when either an edge or a level event is detected (See RxEdCfg RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode • The corresponding PAD_OWN[1:0] is '00' and HOSTSW_OWN ='1' (i.e. Host GPIO Driver Mode). Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = No interrupt • 1 = Interrupt asserts The state of GPI_INT_EN[x] does not prevent the setting of GPI_INT_STS[x]. • Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
8	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW/1C	**GPI Interrupt Status (GPI_INT_STS_EMMC_CLK):** See Description for bit [9] of this register.

65.3.39 GPI Interrupt Enable (GPI_IE_SOUTH_DFX_0)—Offset 120h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 120h
Host Memory Space: SBREG_BAR + 0xC50000 + 120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT15):** This bit is used to enable/disable the generation of APIC interrupt when the corresponding GPI_INT_STS bit is set. • 0 = disable interrupt generation • 1 = enable interrupt generation Refer to GPIO_DRIVER_IRQ_ROUTE for host GPIO Driver Mode interrupt routing. Each bit position correspond to one pad: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
16	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT3):** See Description for bit [17] of this register.
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT2):** See Description for bit [17] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT1):** See Description for bit [17] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT0):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.40 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP0_0)—Offset 124h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 124h
Host Memory Space: SBREG_BAR + 0xC50000 + 124h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SATA0_LED_N):** This bit is used to enable/disable the generation of APIC interrupt when the corresponding GPI_INT_STS bit is set. • 0 = disable interrupt generation • 1 = enable interrupt generation Refer to GPIO_DRIVER_IRQ_ROUTE for host GPIO Driver Mode interrupt routing. Each bit position correspond to one pad: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
30	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB0_LEG_DATA):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
14	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_12):** See Description for bit [31] of this register.

65.3.41 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP0_1)—Offset 128h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 128h
Host Memory Space: SBREG_BAR + 0xC50000 + 128h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RO	**GPI Interrupt Enable (GPI_INT_EN_DFX_SPARE4):** This bit is used to enable/disable the generation of APIC interrupt when the corresponding GPI_INT_STS bit is set. • 0 = disable interrupt generation • 1 = enable interrupt generation Refer to GPIO_DRIVER_IRQ_ROUTE for host GPIO Driver Mode interrupt routing. Each bit position correspond to one pad: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
19	0x0 RO	**GPI Interrupt Enable (GPI_INT_EN_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RO	**GPI Interrupt Enable (GPI_INT_EN_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_TDO):** See Description for bit [20] of this register.
12	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_TDI):** See Description for bit [20] of this register.
11	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_TMS):** See Description for bit [20] of this register.
10	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_UART1_RXD):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.42 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP1_0)—Offset 12Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 12Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 12Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_STROBE):** This bit is used to enable/disable the generation of APIC interrupt when the corresponding GPI_INT_STS bit is set. • 0 = disable interrupt generation • 1 = enable interrupt generation Refer to GPIO_DRIVER_IRQ_ROUTE for host GPIO Driver Mode interrupt routing. Each bit position correspond to one pad: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
30	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_IO2):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
14	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.43 GPI Interrupt Enable (GPI_IE_SOUTH_GROUP1_1)—Offset 130h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 130h
Host Memory Space: SBREG_BAR + 0xC50000 + 130h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_GPIO_3):** This bit is used to enable/disable the generation of APIC interrupt when the corresponding GPI_INT_STS bit is set. • 0 = disable interrupt generation • 1 = enable interrupt generation Refer to GPIO_DRIVER_IRQ_ROUTE for host GPIO Driver Mode interrupt routing. Each bit position correspond to one pad: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1
8	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**GPI Interrupt Enable (GPI_INT_EN_EMMC_CLK):** See Description for bit [9] of this register.

65.3.44 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_DFX_0)—Offset 140h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 140h
Host Memory Space: SBREG_BAR + 0xC50000 + 140h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT15):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
16	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT3):** See Description for bit [17] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT2):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT1):** See Description for bit [17] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT0):** See Description for bit [17] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.45 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP0_0)—Offset 144h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 144h
Host Memory Space: SBREG_BAR + 0xC50000 + 144h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SATA0_LED_N):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
30	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB1_HOST_DATA):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_12):** See Description for bit [31] of this register.

65.3.46 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP0_1)—Offset 148h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 148h
Host Memory Space: SBREG_BAR + 0xC50000 + 148h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_SPARE4):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
19	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_TDO):** See Description for bit [20] of this register.
12	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_TDI):** See Description for bit [20] of this register.
11	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_TMS):** See Description for bit [20] of this register.
10	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_TCK):** See Description for bit [20] of this register.
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_8):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.47 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP1_0)—Offset 14Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 14Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 14Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_STROBE):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
30	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_CLK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.48 GPI General Purpose Events Status (GPI_GPE_STS_SOUTH_GROUP1_1)—Offset 150h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 150h
Host Memory Space: SBREG_BAR + 0xC50000 + 150h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_GPIO_3):** These bits are set any time the corresponding GPIO pad is set up as an input, under host ownership and the corresponding GPIO signal is high (or low if the corresponding RXINV bit is set). If the corresponding enable bit is set in the GPI_GPE_EN register, then when the GPI_GPE_STS[i] bit is set: • If the system is in an S3-S5 state, the event will also wake the system. • If the system is in an S0 state (or upon waking back to an S0 state), an SCI will be caused, depending on the GPIRoutSCI bit for the corresponding pad. These bits are sticky bits and are cleared by writing a 1 back to this bit position. The state of GPI_GPE_EN[i] does not prevent the setting of GPI_GPE_STS[i]. Each bit position correspond to 1 pad in the Community: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
8	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW/1C	**GPI General Purpose Events Status (GPI_GPE_STS_EMMC_CLK):** See Description for bit [9] of this register.

65.3.49 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_DFX_0)—Offset 160h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 160h
Host Memory Space: SBREG_BAR + 0xC50000 + 160h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:18	0x0 RO	**Reserved (RSVD_0):** Reserved.
17	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT15):** This bit is used to enable/ disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i] bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** Note: The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
16	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT14):** See Description for bit [17] of this register.
15	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT13):** See Description for bit [17] of this register.
14	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT12):** See Description for bit [17] of this register.
13	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT11):** See Description for bit [17] of this register.
12	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT10):** See Description for bit [17] of this register.
11	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT9):** See Description for bit [17] of this register.
10	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT8):** See Description for bit [17] of this register.
9	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT7):** See Description for bit [17] of this register.
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT6):** See Description for bit [17] of this register.
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT5):** See Description for bit [17] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT4):** See Description for bit [17] of this register.
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT3):** See Description for bit [17] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT2):** See Description for bit [17] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT1):** See Description for bit [17] of this register.

Bit Range	Default & Access	Field Name (ID): Description
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT0):** See Description for bit [17] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT_CLK1):** See Description for bit [17] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_PORT_CLK0):** See Description for bit [17] of this register.

65.3.50 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP0_0)—Offset 164h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 164h
Host Memory Space: SBREG_BAR + 0xC50000 + 164h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SATA0_LED_N):** This bit is used to enable/ disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i] bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** Note: The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
30	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_IERR_N):** See Description for bit [31] of this register.
11	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_12):** See Description for bit [31] of this register.

65.3.51 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP0_1)—Offset 168h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 168h
Host Memory Space: SBREG_BAR + 0xC50000 + 168h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_SPARE4):** This bit is used to enable/ disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i] bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** Note: The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
19	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_TDO):** See Description for bit [20] of this register.
12	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_TDI):** See Description for bit [20] of this register.
11	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_TMS):** See Description for bit [20] of this register.
10	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_TRST_N):** See Description for bit [20] of this register.
9	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_UART1_TXD):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.52 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP1_0)—Offset 16Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 16Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 16Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_STROBE):** This bit is used to enable/disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i] bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** Note: The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
30	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_IO3):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.53 GPI General Purpose Events Enable (GPI_GPE_EN_SOUTH_GROUP1_1)—Offset 170h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 170h
Host Memory Space: SBREG_BAR + 0xC50000 + 170h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_GPIO_3):** This bit is used to enable/disable the generation of GPE to cause SCI and/or wake when the corresponding GPI_GPE_STS[i] bit is set. • 0 = disable GPE generation • 1 = enable GPE generation ***Note:*** Note: The pad must also be routed for GPE functionality in order for GPE to be generated, i.e. the corresponding GPIRoutSCI must be set to '1'. Bit assignment: • Bit0 = Pad0 • Bit1 = Pad1 • Bit2 = Pad2 • ... • Bit N-1= Pad N-1
8	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**GPI General Purpose Events Enable (GPI_GPE_EN_EMMC_CLK):** See Description for bit [9] of this register.

65.3.54 SMI Status (GPI_SMI_STS_SOUTH_GROUP0_0)—Offset 184h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 184h
Host Memory Space: SBREG_BAR + 0xC50000 + 184h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SATA0_LED_N):** This bit is set to '1' by hardware when a level event (See RxEdCfg, RxInv) is detected, and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding PAD_OWN[2:0] is '000' (i.e. ACPI GPIO Mode). If the following conditions are true, then an SMI will be generated if the GPI_SMI_STS bit is set: 1. The corresponding bit in the GPI_SMI_EN register is set 2. The corresponding pad's GPIROUTSMI is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no SMI event • 1 = There is an SMI event The state of GPI_SMI_EN[x] does not prevent the setting of GPI_SMI_STS[x]. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 Defaults for these bits are dependent on the state of the GPI pads.
30	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI SMI Status (GPI_SMI_STS_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB1_HOST_CLK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RO	**GPI SMI Status (GPI_SMI_STS_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RO	**GPI SMI Status (GPI_SMI_STS_IERR_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_12):** See Description for bit [31] of this register.

65.3.55 SMI Status (GPI_SMI_STS_SOUTH_GROUP0_1)—Offset 188h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 188h
Host Memory Space: SBREG_BAR + 0xC50000 + 188h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RO	**GPI SMI Status (GPI_SMI_STS_DFX_SPARE4):** This bit is set to '1' by hardware when a level event (See RxEdCfg, RxInv) is detected, and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding PAD_OWN[2:0] is '000' (i.e. ACPI GPIO Mode). If the following conditions are true, then an SMI will be generated if the GPI_SMI_STS bit is set: 1. The corresponding bit in the GPI_SMI_EN register is set 2. The corresponding pad's GPIROUTSMI is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no SMI event • 1 = There is an SMI event The state of GPI_SMI_EN[x] does not prevent the setting of GPI_SMI_STS[x]. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 Defaults for these bits are dependent on the state of the GPI pads.
19	0x0 RO	**GPI SMI Status (GPI_SMI_STS_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RO	**GPI SMI Status (GPI_SMI_STS_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RO	**GPI SMI Status (GPI_SMI_STS_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RO	**GPI SMI Status (GPI_SMI_STS_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RO	**GPI SMI Status (GPI_SMI_STS_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RO	**GPI SMI Status (GPI_SMI_STS_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RO	**GPI SMI Status (GPI_SMI_STS_TDO):** See Description for bit [20] of this register.
12	0x0 RO	**GPI SMI Status (GPI_SMI_STS_TDI):** See Description for bit [20] of this register.
11	0x0 RO	**GPI SMI Status (GPI_SMI_STS_TMS):** See Description for bit [20] of this register.
10	0x0 RO	**GPI SMI Status (GPI_SMI_STS_TRST_N):** See Description for bit [20] of this register.
9	0x0 RO	**GPI SMI Status (GPI_SMI_STS_TCK):** See Description for bit [20] of this register.
8	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_9):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
7	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.56 SMI Status (GPI_SMI_STS_SOUTH_GROUP1_0)—Offset 18Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 18Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 18Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_STROBE):** This bit is set to '1' by hardware when a level event (See RxEdCfg, RxInv) is detected, and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding PAD_OWN[2:0] is '000' (i.e. ACPI GPIO Mode). If the following conditions are true, then an SMI will be generated if the GPI_SMI_STS bit is set: 1. The corresponding bit in the GPI_SMI_EN register is set 2. The corresponding pad's GPIROUTSMI is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no SMI event • 1 = There is an SMI event The state of GPI_SMI_EN[x] does not prevent the setting of GPI_SMI_STS[x]. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 Defaults for these bits are dependent on the state of the GPI pads.
30	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RO	**GPI SMI Status (GPI_SMI_STS_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
17	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RO	**GPI SMI Status (GPI_SMI_STS_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RO	**GPI SMI Status (GPI_SMI_STS_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.57 SMI Status (GPI_SMI_STS_SOUTH_GROUP1_1)—Offset 190h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 190h
Host Memory Space: SBREG_BAR + 0xC50000 + 190h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_GPIO_3):** This bit is set to '1' by hardware when a level event (See RxEdCfg, RxInv) is detected, and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding PAD_OWN[2:0] is '000' (i.e. ACPI GPIO Mode). If the following conditions are true, then an SMI will be generated if the GPI_SMI_STS bit is set: 1. The corresponding bit in the GPI_SMI_EN register is set 2. The corresponding pad's GPIROUTSMI is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no SMI event • 1 = There is an SMI event The state of GPI_SMI_EN[x] does not prevent the setting of GPI_SMI_STS[x]. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 Defaults for these bits are dependent on the state of the GPI pads.
8	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW/1C	**GPI SMI Status (GPI_SMI_STS_EMMC_CLK):** See Description for bit [9] of this register.

65.3.58 SMI Enable (GPI_SMI_EN_SOUTH_GROUP0_0)—Offset 1A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1A4h
Host Memory Space: SBREG_BAR + 0xC50000 + 1A4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SATA0_LED_N):** This bit is used to enable/disable the generation of SMI when the corresponding GPI_SMI_STS bit is set. The pad must also be routed for SMI functionality in order for SMI to be generated, i.e. the corresponding GPIROUTSMI must be set to '1'. • 0 = disable SMI generation • 1 = enable SMI generation ***Note:*** Each of the bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1
30	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_IERR_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_12):** See Description for bit [31] of this register.

65.3.59 SMI Enable (GPI_SMI_EN_SOUTH_GROUP0_1)—Offset 1A8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1A8h
Host Memory Space: SBREG_BAR + 0xC50000 + 1A8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_DFX_SPARE4):** This bit is used to enable/disable the generation of SMI when the corresponding GPI_SMI_STS bit is set. The pad must also be routed for SMI functionality in order for SMI to be generated, i.e. the corresponding GPIROUTSMI must be set to '1'. • 0 = disable SMI generation • 1 = enable SMI generation ***Note:*** Each of the bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1
19	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_TDO):** See Description for bit [20] of this register.
12	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_TDI):** See Description for bit [20] of this register.
11	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_TMS):** See Description for bit [20] of this register.
10	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_TRST_N):** See Description for bit [20] of this register.
9	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_UART1_TXD):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.60 SMI Enable (GPI_SMI_EN_SOUTH_GROUP1_0)—Offset 1ACh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1ACh
Host Memory Space: SBREG_BAR + 0xC50000 + 1ACh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_STROBE):** This bit is used to enable/disable the generation of SMI when the corresponding GPI_SMI_STS bit is set. The pad must also be routed for SMI functionality in order for SMI to be generated, i.e. the corresponding GPIROUTSMI must be set to '1'. • 0 = disable SMI generation • 1 = enable SMI generation ***Note:*** Each of the bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1
30	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_IO3):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_IO2):**See Description for bit [31] of this register.
14	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RO	**GPI SMI Enable (GPI_SMI_EN_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.61 SMI Enable (GPI_SMI_EN_SOUTH_GROUP1_1)—Offset 1B0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1B0h
Host Memory Space: SBREG_BAR + 0xC50000 + 1B0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_GPIO_3):** This bit is used to enable/disable the generation of SMI when the corresponding GPI_SMI_STS bit is set. The pad must also be routed for SMI functionality in order for SMI to be generated, i.e. the corresponding GPIROUTSMI must be set to '1'. • 0 = disable SMI generation • 1 = enable SMI generation ***Note:*** Each of the bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1
8	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**GPI SMI Enable (GPI_SMI_EN_EMMC_CLK):** See Description for bit [9] of this register.

65.3.62 NMI Status (GPI_NMI_STS_SOUTH_GROUP0_0)—Offset 1C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1C4h
Host Memory Space: SBREG_BAR + 0xC50000 + 1C4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SATA0_LED_N):** This bit is set to '1' by hardware when an edge event is detected (See RxEdCfg, RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding GPIONMIRout is set to '1', i.e. programmed to route as NMI The corresponding GPIOOwn[2:0] is '000' (i.e. ACPI GPIO Mode). • The corresponding GPI_NMI_EN is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no NMI event • 1 = There is an NMI event Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
30	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI NMI Status (GPI_NMI_STS_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB1_HOST_CLK):**See Description for bit [31] of this register.
17	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB1_HOST_DATA):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.
15	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RO	**GPI NMI Status (GPI_NMI_STS_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RO	**GPI NMI Status (GPI_NMI_STS_IERR_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_12):** See Description for bit [31] of this register.

65.3.63 NMI Status (GPI_NMI_STS_SOUTH_GROUP0_1)—Offset 1C8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1C8h
Host Memory Space: SBREG_BAR + 0xC50000 + 1C8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RO	**GPI NMI Status (GPI_NMI_STS_DFX_SPARE4):** This bit is set to '1' by hardware when an edge event is detected (See RxEdCfg, RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding GPIONMIRout is set to '1', i.e. programmed to route as NMI The corresponding GPIOOwn[2:0] is '000' (i.e. ACPI GPIO Mode). • The corresponding GPI_NMI_EN is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no NMI event • 1 = There is an NMI event Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
19	0x0 RO	**GPI NMI Status (GPI_NMI_STS_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RO	**GPI NMI Status (GPI_NMI_STS_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RO	**GPI NMI Status (GPI_NMI_STS_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RO	**GPI NMI Status (GPI_NMI_STS_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RO	**GPI NMI Status (GPI_NMI_STS_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RO	**GPI NMI Status (GPI_NMI_STS_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RO	**GPI NMI Status (GPI_NMI_STS_TDO):** See Description for bit [20] of this register.
12	0x0 RO	**GPI NMI Status (GPI_NMI_STS_TDI):** See Description for bit [20] of this register.
11	0x0 RO	**GPI NMI Status (GPI_NMI_STS_TMS):** See Description for bit [20] of this register.
10	0x0 RO	**GPI NMI Status (GPI_NMI_STS_TRST_N):** See Description for bit [20] of this register.
9	0x0 RO	**GPI NMI Status (GPI_NMI_STS_TCK):** See Description for bit [20] of this register.
8	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_8):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
6	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_UART1_TXD):** See Description for bit [20] of this register.
5	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.64 NMI Status (GPI_NMI_STS_SOUTH_GROUP1_0)—Offset 1CCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1CCh
Host Memory Space: SBREG_BAR + 0xC50000 + 1CCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_STROBE):** This bit is set to '1' by hardware when an edge event is detected (See RxEdCfg, RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding GPIONMIRout is set to '1', i.e. programmed to route as NMI The corresponding GPIOOwn[2:0] is '000' (i.e. ACPI GPIO Mode). • The corresponding GPI_NMI_EN is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no NMI event • 1 = There is an NMI event Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
30	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RO	**GPI NMI Status (GPI_NMI_STS_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_CLK):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
16	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_IO3):** See Description for bit [31] of this register.
15	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RO	**GPI NMI Status (GPI_NMI_STS_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RO	**GPI NMI Status (GPI_NMI_STS_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.65 NMI Status (GPI_NMI_STS_SOUTH_GROUP1_1)—Offset 1D0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1D0h
Host Memory Space: SBREG_BAR + 0xC50000 + 1D0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_GPIO_3):** This bit is set to '1' by hardware when an edge event is detected (See RxEdCfg, RxInv) on pad and all the following conditions are true: • The corresponding pad is used in GPIO input mode (PMode) • The corresponding GPIONMIRout is set to '1', i.e. programmed to route as NMI The corresponding GPIOOwn[2:0] is '000' (i.e. ACPI GPIO Mode). • The corresponding GPI_NMI_EN is set Writing a value of '1' will clear the bit while writing a value of '0' has no effect. • 0 = There is no NMI event • 1 = There is an NMI event Bit assignment: • Bit0 = pad 0 • Bit1 = pad 1 • Bit2 = pad 2 • ... • Bit N-1= pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
8	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW/1C	**GPI NMI Status (GPI_NMI_STS_EMMC_CLK):** See Description for bit [9] of this register.

65.3.66 NMI Enable (GPI_NMI_EN_SOUTH_GROUP0_0)—Offset 1E4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1E4h
Host Memory Space: SBREG_BAR + 0xC50000 + 1E4h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SATA0_LED_N):** This bit is used to enable/disable the generation of NMI when the corresponding GPI_NMI_STS bit is set and its GPIROUTNMI is set. • 0 = disable NMI generation • 1 = enable NMI generation Each bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
30	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_7):** See Description for bit [31] of this register.
29	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_6):** See Description for bit [31] of this register.
28	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_5):** See Description for bit [31] of this register.
27	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_4):** See Description for bit [31] of this register.
26	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_FLEX_CLK_SE1):** See Description for bit [31] of this register.
25	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_FLEX_CLK_SE0):** See Description for bit [31] of this register.
24	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_USB_OC0_N):** See Description for bit [31] of this register.
23	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB4_CSME0_ALRT_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB4_CSME0_CLK):** See Description for bit [31] of this register.
21	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB4_CSME0_DATA):** See Description for bit [31] of this register.
20	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB2_PECI_CLK):** See Description for bit [31] of this register.
19	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB2_PECI_DATA):** See Description for bit [31] of this register.
18	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB1_HOST_CLK):** See Description for bit [31] of this register.
17	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB1_HOST_DATA):** See Description for bit [31] of this register.
16	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB0_LEG_ALRT_N):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB0_LEG_DATA):** See Description for bit [31] of this register.
14	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SMB0_LEG_CLK):** See Description for bit [31] of this register.
13	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_MCERR_N):** See Description for bit [31] of this register.
12	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_IERR_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ERROR0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ERROR1_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ERROR2_N):** See Description for bit [31] of this register.
8	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SMB5_GBE_DATA):** See Description for bit [31] of this register.
7	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SMB5_GBE_CLK):** See Description for bit [31] of this register.
6	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_UART0_TXD):** See Description for bit [31] of this register.
5	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_UART0_RXD):** See Description for bit [31] of this register.
4	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ7_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ6_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_PCIE_CLKREQ5_N):** See Description for bit [31] of this register.
1	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SMB5_GBE_ALRT_N):** See Description for bit [31] of this register.
0	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_12):** See Description for bit [31] of this register.

65.3.67 NMI Enable (GPI_NMI_EN_SOUTH_GROUP0_1)—Offset 1E8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1E8h
Host Memory Space: SBREG_BAR + 0xC50000 + 1E8h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved (RSVD_0):** Reserved.
20	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_DFX_SPARE4):** This bit is used to enable/disable the generation of NMI when the corresponding GPI_NMI_STS bit is set and its GPIROUTNMI is set. • 0 = disable NMI generation • 1 = enable NMI generation Each bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
19	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_DFX_SPARE3):** See Description for bit [20] of this register.
18	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_DFX_SPARE2):** See Description for bit [20] of this register.
17	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_CTBTRIGOUT):** See Description for bit [20] of this register.
16	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_CTBTRIGINOUT):** See Description for bit [20] of this register.
15	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_CX_PREQ_N):** See Description for bit [20] of this register.
14	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_CX_PRDY_N):** See Description for bit [20] of this register.
13	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_TDO):** See Description for bit [20] of this register.
12	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_TDI):** See Description for bit [20] of this register.
11	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_TMS):** See Description for bit [20] of this register.
10	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_TRST_N):** See Description for bit [20] of this register.
9	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_TCK):** See Description for bit [20] of this register.
8	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_9):** See Description for bit [20] of this register.
7	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_8):** See Description for bit [20] of this register.
6	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_UART1_TXD):** See Description for bit [20] of this register.

Bit Range	Default & Access	Field Name (ID): Description
5	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_UART1_RXD):** See Description for bit [20] of this register.
4	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SATA1_SDOUT):** See Description for bit [20] of this register.
3	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SATA0_SDOUT):** See Description for bit [20] of this register.
2	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SATA_PDETECT1):** See Description for bit [20] of this register.
1	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SATA_PDETECT0):** See Description for bit [20] of this register.
0	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_SATA1_LED_N):** See Description for bit [20] of this register.

65.3.68 NMI Enable (GPI_NMI_EN_SOUTH_GROUP1_0)—Offset 1ECh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1ECh
Host Memory Space: SBREG_BAR + 0xC50000 + 1ECh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_STROBE):** This bit is used to enable/disable the generation of NMI when the corresponding GPI_NMI_STS bit is set and its GPIROUTNMI is set. • 0 = disable NMI generation • 1 = enable NMI generation Each bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
30	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_CMD):** See Description for bit [31] of this register.
29	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_CLK_LOOPBK):** See Description for bit [31] of this register.
28	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_11):** See Description for bit [31] of this register.
27	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_10):** See Description for bit [31] of this register.
26	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_ESPI_ALRT0_N):** See Description for bit [31] of this register.
25	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_RST_N):** See Description for bit [31] of this register.
24	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_CLK):** See Description for bit [31] of this register.
23	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_CS0_N):** See Description for bit [31] of this register.
22	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_IO3):** See Description for bit [31] of this register.
21	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_IO2):** See Description for bit [31] of this register.
20	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_IO1):** See Description for bit [31] of this register.
19	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_ESPI_IO0):** See Description for bit [31] of this register.
18	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_CLK_LOOPBK):** See Description for bit [31] of this register.
17	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_CLK):** See Description for bit [31] of this register.
16	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_IO3):** See Description for bit [31] of this register.

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_IO2):** See Description for bit [31] of this register.
14	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_MISO_IO1):** See Description for bit [31] of this register.
13	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_MOSI_IO0):** See Description for bit [31] of this register.
12	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_CS1_N):** See Description for bit [31] of this register.
11	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SPI_CS0_N):** See Description for bit [31] of this register.
10	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SLP_S0IX_N):** See Description for bit [31] of this register.
9	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SUS_STAT_N):** See Description for bit [31] of this register.
8	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_PLTRST_N):** See Description for bit [31] of this register.
7	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_RESETBUTTON_N):** See Description for bit [31] of this register.
6	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_PWRBTN_N):** See Description for bit [31] of this register.
5	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_WAKE_N):** See Description for bit [31] of this register.
4	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_SLP_S3_N):** See Description for bit [31] of this register.
3	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_SLP_S45_N):** See Description for bit [31] of this register.
2	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_ADR_TRIGGER):** See Description for bit [31] of this register.
1	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_PMU_SUSCLK):** See Description for bit [31] of this register.
0	0x0 RO	**GPI NMI Enable (GPI_NMI_EN_SUSPWRDNACK):** See Description for bit [31] of this register.

65.3.69 NMI Enable (GPI_NMI_EN_SOUTH_GROUP1_1)—Offset 1F0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 1F0h
Host Memory Space: SBREG_BAR + 0xC50000 + 1F0h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:10	0x0 RO	**Reserved (RSVD_0):** Reserved.
9	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_GPIO_3):** This bit is used to enable/disable the generation of NMI when the corresponding GPI_NMI_STS bit is set and its GPIROUTNMI is set. • 0 = disable NMI generation • 1 = enable NMI generation Each bit is lock-able dependent on the associated Pad Configuration register PadCfgLock setting. E.g. if the PadCfgLock of pad0 is '1', bit0 of this bit is locked down to read-only. Bit assignment: • Bit0 = Pad 0 • Bit1 = Pad 1 • Bit2 = Pad 2 • ... • Bit N-1 = Pad N-1 For pads which do not support NMI, the corresponding bit is read-only zero.
8	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D7):** See Description for bit [9] of this register.
7	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D6):** See Description for bit [9] of this register.
6	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D5):** See Description for bit [9] of this register.
5	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D4):** See Description for bit [9] of this register.
4	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D3):** See Description for bit [9] of this register.
3	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D2):** See Description for bit [9] of this register.
2	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D1):** See Description for bit [9] of this register.
1	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_D0):** See Description for bit [9] of this register.
0	0x0 RW	**GPI NMI Enable (GPI_NMI_EN_EMMC_CLK):** See Description for bit [9] of this register.

65.3.70 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT_CLK0)—Offset 400h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 400h
Host Memory Space: SBREG_BAR + 0xC50000 + 400h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b ***Note:*** The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.71 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT_CLK0)—Offset 404h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 404h
Host Memory Space: SBREG_BAR + 0xC50000 + 404h

Default: 00000041h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x41 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 • Up to the max IOxAPIC IRQ supported by the SoC.

65.3.72 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT_CLK1)—Offset 408h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 408h
Host Memory Space: SBREG_BAR + 0xC50000 + 408h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.73 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT_CLK1)—Offset 40Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 40Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 40Ch

Default: 00000042h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x42 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.74 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT0)—Offset 410h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 410h
Host Memory Space: SBREG_BAR + 0xC50000 + 410h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2 (PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1 (PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.75 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT0)—Offset 414h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 414h
Host Memory Space: SBREG_BAR + 0xC50000 + 414h

Default: 00000043h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x43 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.76 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT1)—Offset 418h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 418h
Host Memory Space: SBREG_BAR + 0xC50000 + 418h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.77 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT1)—Offset 41Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 41Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 41Ch

Default: 00000044h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x44 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.78 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT2)—Offset 420h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 420h
Host Memory Space: SBREG_BAR + 0xC50000 + 420h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.79 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT2)—Offset 424h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 424h
Host Memory Space: SBREG_BAR + 0xC50000 + 424h

Default: 00000045h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x45 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.80 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT3)—Offset 428h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 428h
Host Memory Space: SBREG_BAR + 0xC50000 + 428h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.81 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT3)—Offset 42Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 42Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 42Ch

Default: 00000046h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x46 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.82 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT4)—Offset 430h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 430h
Host Memory Space: SBREG_BAR + 0xC50000 + 430h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.83 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT4)—Offset 434h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 434h
Host Memory Space: SBREG_BAR + 0xC50000 + 434h

Default: 00000047h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x47 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.84 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT5)—Offset 438h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 438h
Host Memory Space: SBREG_BAR + 0xC50000 + 438h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.85 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT5)—Offset 43Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 43Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 43Ch

Default: 00000048h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x48 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.86 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT6)—Offset 440h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 440h
Host Memory Space: SBREG_BAR + 0xC50000 + 440h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.87 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT6)—Offset 444h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 444h
Host Memory Space: SBREG_BAR + 0xC50000 + 444h

Default: 00000049h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x49 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.88 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT7)—Offset 448h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 448h
Host Memory Space: SBREG_BAR + 0xC50000 + 448h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.89 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT7)—Offset 44Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 44Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 44Ch

Default: 0000004Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.90 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT8)—Offset 450h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 450h
Host Memory Space: SBREG_BAR + 0xC50000 + 450h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.91 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT8)—Offset 454h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 454h
Host Memory Space: SBREG_BAR + 0xC50000 + 454h

Default: 0000004Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.92 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT9)—Offset 458h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 458h
Host Memory Space: SBREG_BAR + 0xC50000 + 458h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.93 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT9)—Offset 45Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 45Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 45Ch

Default: 0000004Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.94 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT10)—Offset 460h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 460h
Host Memory Space: SBREG_BAR + 0xC50000 + 460h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.95 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT10)—Offset 464h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 464h
Host Memory Space: SBREG_BAR + 0xC50000 + 464h

Default: 0000004Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.96 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT11)—Offset 468h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 468h
Host Memory Space: SBREG_BAR + 0xC50000 + 468h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.97 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT11)—Offset 46Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 46Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 46Ch

Default: 0000004Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.98 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT12)—Offset 470h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 470h
Host Memory Space: SBREG_BAR + 0xC50000 + 470h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.99 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT12)—Offset 474h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 474h
Host Memory Space: SBREG_BAR + 0xC50000 + 474h

Default: 0000004Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.100 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT13)—Offset 478h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 478h
Host Memory Space: SBREG_BAR + 0xC50000 + 478h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.101 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT13)—Offset 47Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 47Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 47Ch

Default: 00000050h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x50 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.102 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT14)—Offset 480h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 480h
Host Memory Space: SBREG_BAR + 0xC50000 + 480h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.103 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT14)—Offset 484h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 484h
Host Memory Space: SBREG_BAR + 0xC50000 + 484h

Default: 00000051h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x51 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.104 Pad Configuration DW0 (PAD_CFG_DW0_DFX_PORT15)—Offset 488h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 488h
Host Memory Space: SBREG_BAR + 0xC50000 + 488h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12	0x0 RW	**Pad Mode bit 2(PMODE2):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
11	0x0 RW	**Pad Mode bit 1(PMODE1):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad

Bit Range	Default & Access	Field Name (ID): Description
10	0x1 RW	**Pad Mode bit 0 (PMODE0):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.105 Pad Configuration DW1 (PAD_CFG_DW1_DFX_PORT15)—Offset 48Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 48Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 48Ch

Default: 00000052h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x52 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.106 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_12)—Offset 490h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 490h
Host Memory Space: SBREG_BAR + 0xC50000 + 490h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.107 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_12)—Offset 494h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 494h
Host Memory Space: SBREG_BAR + 0xC50000 + 494h

Default: 00000053h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x53 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.108 Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_ALRT_N)—Offset 498h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 498h
Host Memory Space: SBREG_BAR + 0xC50000 + 498h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.109 Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_ALRT_N)—Offset 49Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 49Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 49Ch

Default: 00000054h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x54 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.110 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ5_N)—Offset 4A0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4A0h
Host Memory Space: SBREG_BAR + 0xC50000 + 4A0h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.111 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ5_N)—Offset 4A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4A4h
Host Memory Space: SBREG_BAR + 0xC50000 + 4A4h

Default: 00000055h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x55 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.112 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ6_N)—Offset 4A8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4A8h
Host Memory Space: SBREG_BAR + 0xC50000 + 4A8h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.113 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ6_N)—Offset 4ACh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4ACh
Host Memory Space: SBREG_BAR + 0xC50000 + 4ACh

Default: 00000056h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x56 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.114 Pad Configuration DW0 (PAD_CFG_DW0_PCIE_CLKREQ7_N)—Offset 4B0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4B0h
Host Memory Space: SBREG_BAR + 0xC50000 + 4B0h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.115 Pad Configuration DW1 (PAD_CFG_DW1_PCIE_CLKREQ7_N)—Offset 4B4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4B4h
Host Memory Space: SBREG_BAR + 0xC50000 + 4B4h

Default: 00000057h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x57 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.116 Pad Configuration DW0 (PAD_CFG_DW0_UART0_RXD)—Offset 4B8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4B8h
Host Memory Space: SBREG_BAR + 0xC50000 + 4B8h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.117 Pad Configuration DW1 (PAD_CFG_DW1_UART0_RXD)—Offset 4BCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4BCh
Host Memory Space: SBREG_BAR + 0xC50000 + 4BCh

Default: 00003058h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x58 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.118 Pad Configuration DW0 (PAD_CFG_DW0_UART0_TXD)—Offset 4C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4C0h
Host Memory Space: SBREG_BAR + 0xC50000 + 4C0h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.119 Pad Configuration DW1 (PAD_CFG_DW1_UART0_TXD)—Offset 4C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4C4h
Host Memory Space: SBREG_BAR + 0xC50000 + 4C4h

Default: 00000059h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x59 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.120 Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_CLK)—Offset 4C8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4C8h
Host Memory Space: SBREG_BAR + 0xC50000 + 4C8h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.121 Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_CLK)—Offset 4CCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4CCh
Host Memory Space: SBREG_BAR + 0xC50000 + 4CCh

Default: 0000305Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x5a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.122 Pad Configuration DW0 (PAD_CFG_DW0_SMB5_GBE_DATA)—Offset 4D0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4D0h
Host Memory Space: SBREG_BAR + 0xC50000 + 4D0h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.123 Pad Configuration DW1 (PAD_CFG_DW1_SMB5_GBE_DATA)—Offset 4D4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4D4h
Host Memory Space: SBREG_BAR + 0xC50000 + 4D4h

Default: 0000305Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x5b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.124 Pad Configuration DW0 (PAD_CFG_DW0_ERROR2_N)—Offset 4D8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4D8h
Host Memory Space: SBREG_BAR + 0xC50000 + 4D8h

Default: 45000601h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x1 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.125 Pad Configuration DW1 (PAD_CFG_DW1_ERROR2_N)—Offset 4DCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4DCh
Host Memory Space: SBREG_BAR + 0xC50000 + 4DCh

Default: 0000005Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x5c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.126 Pad Configuration DW0 (PAD_CFG_DW0_ERROR1_N)—Offset 4E0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4E0h
Host Memory Space: SBREG_BAR + 0xC50000 + 4E0h

Default: 45000601h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x1 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.127 Pad Configuration DW1 (PAD_CFG_DW1_ERROR1_N)—Offset 4E4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4E4h
Host Memory Space: SBREG_BAR + 0xC50000 + 4E4h

Default: 0000005Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x5d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.128 Pad Configuration DW0 (PAD_CFG_DW0_ERROR0_N)—Offset 4E8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4E8h
Host Memory Space: SBREG_BAR + 0xC50000 + 4E8h

Default: 45000601h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x1 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.129 Pad Configuration DW1 (PAD_CFG_DW1_ERROR0_N)—Offset 4ECh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4ECh
Host Memory Space: SBREG_BAR + 0xC50000 + 4ECh

Default: 0000005Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x5e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.130 Pad Configuration DW0 (PAD_CFG_DW0_IERR_N)—Offset 4F0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4F0h
Host Memory Space: SBREG_BAR + 0xC50000 + 4F0h

Default: 44000601h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x1 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.131 Pad Configuration DW1 (PAD_CFG_DW1_IERR_N)—Offset 4F4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4F4h
Host Memory Space: SBREG_BAR + 0xC50000 + 4F4h

Default: 0000005Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x5f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.132 Pad Configuration DW0 (PAD_CFG_DW0_MCERR_N)—Offset 4F8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4F8h
Host Memory Space: SBREG_BAR + 0xC50000 + 4F8h

Default: 44000601h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x1 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.133 Pad Configuration DW1 (PAD_CFG_DW1_MCERR_N)—Offset 4FCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 4FCh
Host Memory Space: SBREG_BAR + 0xC50000 + 4FCh

Default: 00000060h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x60 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.134 Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_CLK)—Offset 500h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 500h
Host Memory Space: SBREG_BAR + 0xC50000 + 500h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.135 Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_CLK)—Offset 504h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 504h
Host Memory Space: SBREG_BAR + 0xC50000 + 504h

Default: 00003061h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x61 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.136 Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_DATA)—Offset 508h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 508h
Host Memory Space: SBREG_BAR + 0xC50000 + 508h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.137 Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_DATA)—Offset 50Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 50Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 50Ch

Default: 00003062h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x62 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.138 Pad Configuration DW0 (PAD_CFG_DW0_SMB0_LEG_ALRT_N)—Offset 510h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 510h
Host Memory Space: SBREG_BAR + 0xC50000 + 510h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.139 Pad Configuration DW1 (PAD_CFG_DW1_SMB0_LEG_ALRT_N)—Offset 514h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 514h
Host Memory Space: SBREG_BAR + 0xC50000 + 514h

Default: 00003063h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x63 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.140 Pad Configuration DW0 (PAD_CFG_DW0_SMB1_HOST_DATA)—Offset 518h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 518h
Host Memory Space: SBREG_BAR + 0xC50000 + 518h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.141 Pad Configuration DW1 (PAD_CFG_DW1_SMB1_HOST_DATA)—Offset 51Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 51Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 51Ch

Default: 00003064h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x64 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.142 Pad Configuration DW0 (PAD_CFG_DW0_SMB1_HOST_CLK)—Offset 520h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 520h
Host Memory Space: SBREG_BAR + 0xC50000 + 520h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.143 Pad Configuration DW1 (PAD_CFG_DW1_SMB1_HOST_CLK)—Offset 524h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 524h
Host Memory Space: SBREG_BAR + 0xC50000 + 524h

Default: 00003065h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x65 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.144 Pad Configuration DW0 (PAD_CFG_DW0_SMB2_PECI_DATA)—Offset 528h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 528h
Host Memory Space: SBREG_BAR + 0xC50000 + 528h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.145 Pad Configuration DW1 (PAD_CFG_DW1_SMB2_PECI_DATA)—Offset 52Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 52Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 52Ch

Default: 00003066h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x66 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.146 Pad Configuration DW0 (PAD_CFG_DW0_SMB2_PECI_CLK)—Offset 530h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 530h
Host Memory Space: SBREG_BAR + 0xC50000 + 530h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.147 Pad Configuration DW1 (PAD_CFG_DW1_SMB2_PECI_CLK)—Offset 534h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 534h
Host Memory Space: SBREG_BAR + 0xC50000 + 534h

Default: 00003067h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x67 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.148 Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_DATA)—Offset 538h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 538h
Host Memory Space: SBREG_BAR + 0xC50000 + 538h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.149 Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_DATA)—Offset 53Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 53Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 53Ch

Default: 00003068h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x68 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.150 Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_CLK)—Offset 540h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 540h
Host Memory Space: SBREG_BAR + 0xC50000 + 540h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.151 Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_CLK)—Offset 544h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 544h
Host Memory Space: SBREG_BAR + 0xC50000 + 544h

Default: 00003069h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x69 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.152 Pad Configuration DW0 (PAD_CFG_DW0_SMB4_CSME0_ALRT_N)—Offset 548h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 548h
Host Memory Space: SBREG_BAR + 0xC50000 + 548h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.153 Pad Configuration DW1 (PAD_CFG_DW1_SMB4_CSME0_ALRT_N)—Offset 54Ch

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 54Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 54Ch

Default: 0000306Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x6a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.154 Pad Configuration DW0 (PAD_CFG_DW0_USB_OC0_N)—Offset 550h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 550h
Host Memory Space: SBREG_BAR + 0xC50000 + 550h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.155 Pad Configuration DW1 (PAD_CFG_DW1_USB_OC0_N)—Offset 554h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 554h
Host Memory Space: SBREG_BAR + 0xC50000 + 554h

Default: 0000306Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x6b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.156 Pad Configuration DW0 (PAD_CFG_DW0_FLEX_CLK_SE0)—Offset 558h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 558h
Host Memory Space: SBREG_BAR + 0xC50000 + 558h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.157 Pad Configuration DW1 (PAD_CFG_DW1_FLEX_CLK_SE0)—Offset 55Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 55Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 55Ch

Default: 0000006Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x6c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.158 Pad Configuration DW0 (PAD_CFG_DW0_FLEX_CLK_SE1)—Offset 560h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 560h
Host Memory Space: SBREG_BAR + 0xC50000 + 560h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.159 Pad Configuration DW1 (PAD_CFG_DW1_FLEX_CLK_SE1)—Offset 564h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 564h
Host Memory Space: SBREG_BAR + 0xC50000 + 564h

Default: 0000006Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x6d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.160 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_4)—Offset 568h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 568h
Host Memory Space: SBREG_BAR + 0xC50000 + 568h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.161 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_4)—Offset 56Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 56Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 56Ch

Default: 0000006Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x6e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.162 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_5)—Offset 570h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 570h
Host Memory Space: SBREG_BAR + 0xC50000 + 570h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.163 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_5)—Offset 574h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 574h
Host Memory Space: SBREG_BAR + 0xC50000 + 574h

Default: 0000006Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x6f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.164 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_6)—Offset 578h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 578h
Host Memory Space: SBREG_BAR + 0xC50000 + 578h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.165 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_6)—Offset 57Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 57Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 57Ch

Default: 00000070h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x70 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.166 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_7)—Offset 580h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 580h
Host Memory Space: SBREG_BAR + 0xC50000 + 580h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.167 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_7)—Offset 584h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 584h
Host Memory Space: SBREG_BAR + 0xC50000 + 584h

Default: 00000071h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x71 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.168 Pad Configuration DW0 (PAD_CFG_DW0_SATA0_LED_N)—Offset 588h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 588h
Host Memory Space: SBREG_BAR + 0xC50000 + 588h

Default: 45000700h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.169 Pad Configuration DW1 (PAD_CFG_DW1_SATA0_LED_N)—Offset 58Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 58Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 58Ch

Default: 00000072h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x72 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.170 Pad Configuration DW0 (PAD_CFG_DW0_SATA1_LED_N)—Offset 590h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 590h
Host Memory Space: SBREG_BAR + 0xC50000 + 590h

Default: 45000700h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.171 Pad Configuration DW1 (PAD_CFG_DW1_SATA1_LED_N)—Offset 594h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 594h
Host Memory Space: SBREG_BAR + 0xC50000 + 594h

Default: 00000073h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x73 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.172 Pad Configuration DW0 (PAD_CFG_DW0_SATA_PDETECT0)—Offset 598h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 598h
Host Memory Space: SBREG_BAR + 0xC50000 + 598h

Default: 45000700h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.173 Pad Configuration DW1 (PAD_CFG_DW1_SATA_PDETECT0)—Offset 59Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 59Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 59Ch

Default: 00000074h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x74 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.174 Pad Configuration DW0 (PAD_CFG_DW0_SATA_PDETECT1)—Offset 5A0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5A0h
Host Memory Space: SBREG_BAR + 0xC50000 + 5A0h

Default: 45000700h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.175 Pad Configuration DW1 (PAD_CFG_DW1)—Offset 5A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5A4h
Host Memory Space: SBREG_BAR + 0xC50000 + 5A4h

Default: 00000075h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x75 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.176 Pad Configuration DW0 (PAD_CFG_DW0_SATA0_SDOUT)—Offset 5A8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5A8h
Host Memory Space: SBREG_BAR + 0xC50000 + 5A8h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.177 Pad Configuration DW1 (PAD_CFG_DW1_SATA0_SDOUT)—Offset 5ACh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5ACh
Host Memory Space: SBREG_BAR + 0xC50000 + 5ACh

Default: 00000076h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x76 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.178 Pad Configuration DW0 (PAD_CFG_DW0_SATA1_SDOUT)—Offset 5B0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5B0h
Host Memory Space: SBREG_BAR + 0xC50000 + 5B0h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.179 Pad Configuration DW1 (PAD_CFG_DW1_SATA1_SDOUT)—Offset 5B4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5B4h
Host Memory Space: SBREG_BAR + 0xC50000 + 5B4h

Default: 00000018h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x18 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.180 Pad Configuration DW0 (PAD_CFG_DW0_UART1_RXD)—Offset 5B8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5B8h
Host Memory Space: SBREG_BAR + 0xC50000 + 5B8h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.181 Pad Configuration DW1 (PAD_CFG_DW1_UART1_RXD)—Offset 5BCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5BCh
Host Memory Space: SBREG_BAR + 0xC50000 + 5BCh

Default: 00003019h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x19 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.182 Pad Configuration DW0 (PAD_CFG_DW0_UART1_TXD)—Offset 5C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5C0h
Host Memory Space: SBREG_BAR + 0xC50000 + 5C0h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.183 Pad Configuration DW1 (PAD_CFG_DW1_UART1_TXD)—Offset 5C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5C4h
Host Memory Space: SBREG_BAR + 0xC50000 + 5C4h

Default: 0000001Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.184 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_8)—Offset 5C8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5C8h
Host Memory Space: SBREG_BAR + 0xC50000 + 5C8h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.185 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_8)—Offset 5CCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5CCh
Host Memory Space: SBREG_BAR + 0xC50000 + 5CCh

Default: 0000001Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.186 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_9)—Offset 5D0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5D0h
Host Memory Space: SBREG_BAR + 0xC50000 + 5D0h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.187 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_9)—Offset 5D4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5D4h
Host Memory Space: SBREG_BAR + 0xC50000 + 5D4h

Default: 0000001Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.188 Pad Configuration DW0 (PAD_CFG_DW0_TCK)—Offset 5D8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5D8h
Host Memory Space: SBREG_BAR + 0xC50000 + 5D8h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.189 Pad Configuration DW1 (PAD_CFG_DW1_TCK)—Offset 5DCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5DCh
Host Memory Space: SBREG_BAR + 0xC50000 + 5DCh

Default: 0400101Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x4 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.190 Pad Configuration DW0 (PAD_CFG_DW0_TRST_N)—Offset 5E0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5E0h
Host Memory Space: SBREG_BAR + 0xC50000 + 5E0h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.191 Pad Configuration DW1 (PAD_CFG_DW1_TRST_N)—Offset 5E4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5E4h
Host Memory Space: SBREG_BAR + 0xC50000 + 5E4h

Default: 0400301Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.192 Pad Configuration DW0 (PAD_CFG_DW0_TMS)—Offset 5E8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5E8h
Host Memory Space: SBREG_BAR + 0xC50000 + 5E8h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.193 Pad Configuration DW1 (PAD_CFG_DW1_TMS)—Offset 5ECh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5ECh
Host Memory Space: SBREG_BAR + 0xC50000 + 5ECh

Default: 0400301Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x1f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.194 Pad Configuration DW0 (PAD_CFG_DW0_TDI)—Offset 5F0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5F0h
Host Memory Space: SBREG_BAR + 0xC50000 + 5F0h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.195 Pad Configuration DW1 (PAD_CFG_DW1_TDI)—Offset 5F4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5F4h
Host Memory Space: SBREG_BAR + 0xC50000 + 5F4h

Default: 04003020h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x20 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.196 Pad Configuration DW0 (PAD_CFG_DW0_TDO)—Offset 5F8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5F8h
Host Memory Space: SBREG_BAR + 0xC50000 + 5F8h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.197 Pad Configuration DW1 (PAD_CFG_DW1_TDO)—Offset 5FCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 5FCh
Host Memory Space: SBREG_BAR + 0xC50000 + 5FCh

Default: 00000021h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x21 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.198 Pad Configuration DW0 (PAD_CFG_DW0_CX_PRDY_N)—Offset 600h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 600h
Host Memory Space: SBREG_BAR + 0xC50000 + 600h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.199 Pad Configuration DW1 (PAD_CFG_DW1_CX_PRDY_N)—Offset 604h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 604h
Host Memory Space: SBREG_BAR + 0xC50000 + 604h

Default: 00003022h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x22 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.200 Pad Configuration DW0 (PAD_CFG_DW0_CX_PREQ_N)—Offset 608h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 608h
Host Memory Space: SBREG_BAR + 0xC50000 + 608h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.201 Pad Configuration DW1 (PAD_CFG_DW1_CX_PREQ_N)—Offset 60Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 60Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 60Ch

Default: 04003023h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x23 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.202 Pad Configuration DW0 (PAD_CFG_DW0_CTBTRIGINOUT)—Offset 610h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 610h
Host Memory Space: SBREG_BAR + 0xC50000 + 610h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.203 Pad Configuration DW1 (PAD_CFG_DW1_CTBTRIGINOUT)—Offset 614h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 614h
Host Memory Space: SBREG_BAR + 0xC50000 + 614h

Default: 04003024h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x24 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.204 Pad Configuration DW0 (PAD_CFG_DW0_CTBTRIGOUT)—Offset 618h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 618h
Host Memory Space: SBREG_BAR + 0xC50000 + 618h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.205 Pad Configuration DW1 (PAD_CFG_DW1_CTBTRIGOUT)—Offset 61Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 61Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 61Ch

Default: 04000025h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x25 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.206 Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE2)—Offset 620h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 620h
Host Memory Space: SBREG_BAR + 0xC50000 + 620h

Default: 44000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.207 Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE2)—Offset 624h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 624h
Host Memory Space: SBREG_BAR + 0xC50000 + 624h

Default: 04000026h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x26 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.208 Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE3)—Offset 628h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 628h
Host Memory Space: SBREG_BAR + 0xC50000 + 628h

Default: 44000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.209 Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE3)—Offset 62Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 62Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 62Ch

Default: 04000027h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x27 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.210 Pad Configuration DW0 (PAD_CFG_DW0_DFX_SPARE4)—Offset 630h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 630h
Host Memory Space: SBREG_BAR + 0xC50000 + 630h

Default: 44000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.211 Pad Configuration DW1 (PAD_CFG_DW1_DFX_SPARE4)—Offset 634h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 634h
Host Memory Space: SBREG_BAR + 0xC50000 + 634h

Default: 00000028h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x28 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.212 Pad Configuration DW0 (PAD_CFG_DW0_SUSPWRDNACK)—Offset 638h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 638h
Host Memory Space: SBREG_BAR + 0xC50000 + 638h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.213 Pad Configuration DW1 (PAD_CFG_DW1_SUSPWRDNACK)—Offset 63Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 63Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 63Ch

Default: 00000029h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x29 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.214 Pad Configuration DW0 (PAD_CFG_DW0_PMU_SUSCLK)—Offset 640h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 640h
Host Memory Space: SBREG_BAR + 0xC50000 + 640h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.215 Pad Configuration DW1 (PAD_CFG_DW1_PMU_SUSCLK)—Offset 644h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 644h
Host Memory Space: SBREG_BAR + 0xC50000 + 644h

Default: 0000002Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.216 Pad Configuration DW0 (PAD_CFG_DW0_ADR_TRIGGER)—Offset 648h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 648h
Host Memory Space: SBREG_BAR + 0xC50000 + 648h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.217 Pad Configuration DW1 (PAD_CFG_DW1_ADR_TRIGGER)—Offset 64Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 64Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 64Ch

Default: 0000002Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.218 Pad Configuration DW0 (PAD_CFG_DW0_PMU_SLP_S45_N)—Offset 650h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 650h
Host Memory Space: SBREG_BAR + 0xC50000 + 650h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.219 Pad Configuration DW1 (PAD_CFG_DW1_PMU_SLP_S45_N)—Offset 654h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 654h
Host Memory Space: SBREG_BAR + 0xC50000 + 654h

Default: 0000002Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.220 Pad Configuration DW0 (PAD_CFG_DW0_PMU_SLP_S3_N)—Offset 658h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 658h
Host Memory Space: SBREG_BAR + 0xC50000 + 658h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.221 Pad Configuration DW1 (PAD_CFG_DW1_PMU_SLP_S3_N)—Offset 65Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 65Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 65Ch

Default: 0000002Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.222 Pad Configuration DW0 (PAD_CFG_DW0_PMU_WAKE_N)—Offset 660h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 660h
Host Memory Space: SBREG_BAR + 0xC50000 + 660h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.223 Pad Configuration DW1 (PAD_CFG_DW1_PMU_WAKE_N)—Offset 664h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 664h
Host Memory Space: SBREG_BAR + 0xC50000 + 664h

Default: 0000302Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.224 Pad Configuration DW0 (PAD_CFG_DW0_PMU_PWRBTN_N)—Offset 668h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 668h
Host Memory Space: SBREG_BAR + 0xC50000 + 668h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.225 Pad Configuration DW1 (PAD_CFG_DW1_PMU_PWRBTN_N)—Offset 66Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 66Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 66Ch

Default: 0000302Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x2f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.226 Pad Configuration DW0 (PAD_CFG_DW0_PMU_RESETBUTTON_N)—Offset 670h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 670h
Host Memory Space: SBREG_BAR + 0xC50000 + 670h

Default: 45000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.227 Pad Configuration DW1 (PAD_CFG_DW1_PMU_RESETBUTTON_N)—Offset 674h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 674h
Host Memory Space: SBREG_BAR + 0xC50000 + 674h

Default: 00003030h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xc RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x30 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.228 Pad Configuration DW0 (PAD_CFG_DW0_PMU_PLTRST_N)—Offset 678h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 678h
Host Memory Space: SBREG_BAR + 0xC50000 + 678h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.229 Pad Configuration DW1 (PAD_CFG_DW1_PMU_PLTRST_N)—Offset 67Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 67Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 67Ch

Default: 00000031h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x31 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.230 Pad Configuration DW0 (PAD_CFG_DW0_SUS_STAT_N)—Offset 680h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 680h
Host Memory Space: SBREG_BAR + 0xC50000 + 680h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.231 Pad Configuration DW1 (PAD_CFG_DW1_SUS_STAT_N)—Offset 684h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 684h
Host Memory Space: SBREG_BAR + 0xC50000 + 684h

Default: 00000032h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x32 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.232 Pad Configuration DW0 (PAD_CFG_DW0_SLP_S0IX_N)—Offset 688h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 688h
Host Memory Space: SBREG_BAR + 0xC50000 + 688h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.233 Pad Configuration DW1 (PAD_CFG_DW1_SLP_S0IX_N)—Offset 68Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 68Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 68Ch

Default: 00000033h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x33 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.234 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CS0_N)—Offset 690h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 690h
Host Memory Space: SBREG_BAR + 0xC50000 + 690h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.235 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CS0_N)—Offset 694h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 694h
Host Memory Space: SBREG_BAR + 0xC50000 + 694h

Default: 00003C34h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x34 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.236 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CS1_N)—Offset 698h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 698h
Host Memory Space: SBREG_BAR + 0xC50000 + 698h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.237 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CS1_N)—Offset 69Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 69Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 69Ch

Default: 00003C35h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x35 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.238 Pad Configuration DW0 (PAD_CFG_DW0_SPI_MOSI_IO0)—Offset 6A0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6A0h
Host Memory Space: SBREG_BAR + 0xC50000 + 6A0h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.239 Pad Configuration DW1 (PAD_CFG_DW1_SPI_MOSI_IO0)—Offset 6A4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6A4h
Host Memory Space: SBREG_BAR + 0xC50000 + 6A4h

Default: 00003C36h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x36 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.240 Pad Configuration DW0 (PAD_CFG_DW0_SPI_MISO_IO1)—Offset 6A8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6A8h
Host Memory Space: SBREG_BAR + 0xC50000 + 6A8h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.241 Pad Configuration DW1 (PAD_CFG_DW1_SPI_MISO_IO1)—Offset 6ACh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6ACh
Host Memory Space: SBREG_BAR + 0xC50000 + 6ACh

Default: 00003C37h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x37 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.242 Pad Configuration DW0 (PAD_CFG_DW0_SPI_IO2)—Offset 6B0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6B0h
Host Memory Space: SBREG_BAR + 0xC50000 + 6B0h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.243 Pad Configuration DW1 (PAD_CFG_DW1_SPI_IO2)—Offset 6B4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6B4h
Host Memory Space: SBREG_BAR + 0xC50000 + 6B4h

Default: 00003C38h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x38 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.244 Pad Configuration DW0 (PAD_CFG_DW0_SPI_IO3)—Offset 6B8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6B8h
Host Memory Space: SBREG_BAR + 0xC50000 + 6B8h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.245 Pad Configuration DW1 (PAD_CFG_DW1_SPI_IO3)—Offset 6BCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6BCh
Host Memory Space: SBREG_BAR + 0xC50000 + 6BCh

Default: 00003C39h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x39 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.246 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CLK)—Offset 6C0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6C0h
Host Memory Space: SBREG_BAR + 0xC50000 + 6C0h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.247 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CLK)—Offset 6C4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6C4h
Host Memory Space: SBREG_BAR + 0xC50000 + 6C4h

Default: 00003C3Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.248 Pad Configuration DW0 (PAD_CFG_DW0_SPI_CLK_LOOPBK)—Offset 6C8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6C8h
Host Memory Space: SBREG_BAR + 0xC50000 + 6C8h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RO	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.249 Pad Configuration DW1 (PAD_CFG_DW1_SPI_CLK_LOOPBK)—Offset 6CCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6CCh
Host Memory Space: SBREG_BAR + 0xC50000 + 6CCh

Default: 00003C3Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.250 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO0)—Offset 6D0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6D0h
Host Memory Space: SBREG_BAR + 0xC50000 + 6D0h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.251 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO0)—Offset 6D4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6D4h
Host Memory Space: SBREG_BAR + 0xC50000 + 6D4h

Default: 00003C3Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.252 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO1)—Offset 6D8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6D8h
Host Memory Space: SBREG_BAR + 0xC50000 + 6D8h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.253 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO1)—Offset 6DCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6DCh
Host Memory Space: SBREG_BAR + 0xC50000 + 6DCh

Default: 00003C3Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.254 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO2)—Offset 6E0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6E0h
Host Memory Space: SBREG_BAR + 0xC50000 + 6E0h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.255 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO2)—Offset 6E4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6E4h
Host Memory Space: SBREG_BAR + 0xC50000 + 6E4h

Default: 00003C3Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.256 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_IO3)—Offset 6E8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6E8h
Host Memory Space: SBREG_BAR + 0xC50000 + 6E8h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.257 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_IO3)—Offset 6ECh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6ECh
Host Memory Space: SBREG_BAR + 0xC50000 + 6ECh

Default: 00003C3Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0xf RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x3f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.258 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CS0_N)—Offset 6F0h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6F0h
Host Memory Space: SBREG_BAR + 0xC50000 + 6F0h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.259 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CS0_N)—Offset 6F4h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6F4h
Host Memory Space: SBREG_BAR + 0xC50000 + 6F4h

Default: 00000040h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x40 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.260 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CLK)—Offset 6F8h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6F8h
Host Memory Space: SBREG_BAR + 0xC50000 + 6F8h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.261 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CLK)—Offset 6FCh

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 6FCh
Host Memory Space: SBREG_BAR + 0xC50000 + 6FCh

Default: 00001041h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x4 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x41 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.262 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_RST_N)—Offset 700h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 700h
Host Memory Space: SBREG_BAR + 0xC50000 + 700h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.263 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_RST_N)—Offset 704h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 704h
Host Memory Space: SBREG_BAR + 0xC50000 + 704h

Default: 00001042h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x4 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x42 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.264 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_ALRT0_N)—Offset 708h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 708h
Host Memory Space: SBREG_BAR + 0xC50000 + 708h

Default: 45000A00h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.265 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_ALRT0_N)—Offset 70Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 70Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 70Ch

Default: 00000043h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x43 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.266 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_10)—Offset 710h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 710h
Host Memory Space: SBREG_BAR + 0xC50000 + 710h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.267 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_10)—Offset 714h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 714h
Host Memory Space: SBREG_BAR + 0xC50000 + 714h

Default: 00000044h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x44 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.268 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_11)—Offset 718h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 718h
Host Memory Space: SBREG_BAR + 0xC50000 + 718h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.269 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_11)—Offset 71Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 71Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 71Ch

Default: 00000045h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x45 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.270 Pad Configuration DW0 (PAD_CFG_DW0_ESPI_CLK_LOOPBK)—Offset 720h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 720h
Host Memory Space: SBREG_BAR + 0xC50000 + 720h

Default: 44000600h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x0 RO	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RO	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RO	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.271 Pad Configuration DW1 (PAD_CFG_DW1_ESPI_CLK_LOOPBK)—Offset 724h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 724h
Host Memory Space: SBREG_BAR + 0xC50000 + 724h

Default: 00000046h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x46 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.272 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_CMD)—Offset 728h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 728h
Host Memory Space: SBREG_BAR + 0xC50000 + 728h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.273 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_CMD)—Offset 72Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 72Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 72Ch

Default: 00000047h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x47 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.274 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_STROBE)—Offset 730h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 730h
Host Memory Space: SBREG_BAR + 0xC50000 + 730h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.275 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_STROBE)—Offset 734h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 734h
Host Memory Space: SBREG_BAR + 0xC50000 + 734h

Default: 00000048h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x48 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.276 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_CLK)—Offset 738h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 738h
Host Memory Space: SBREG_BAR + 0xC50000 + 738h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.277 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_CLK)—Offset 73Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 73Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 73Ch

Default: 00000049h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x49 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.278 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D0)—Offset 740h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 740h
Host Memory Space: SBREG_BAR + 0xC50000 + 740h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.279 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D0)—Offset 744h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 744h
Host Memory Space: SBREG_BAR + 0xC50000 + 744h

Default: 0000004Ah

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4a RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.280 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D1)—Offset 748h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 748h
Host Memory Space: SBREG_BAR + 0xC50000 + 748h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.281 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D1)—Offset 74Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 74Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 74Ch

Default: 0000004Bh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4b RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.282 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D2)—Offset 750h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 750h
Host Memory Space: SBREG_BAR + 0xC50000 + 750h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.283 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D2)—Offset 754h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 754h
Host Memory Space: SBREG_BAR + 0xC50000 + 754h

Default: 0000004Ch

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4c RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.284 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D3)—Offset 758h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 758h
Host Memory Space: SBREG_BAR + 0xC50000 + 758h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.285 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D3)—Offset 75Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 75Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 75Ch

Default: 0000004Dh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4d RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.286 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D4)—Offset 760h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 760h
Host Memory Space: SBREG_BAR + 0xC50000 + 760h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.287 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D4)—Offset 764h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 764h
Host Memory Space: SBREG_BAR + 0xC50000 + 764h

Default: 0000004Eh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4e RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.288 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D5)—Offset 768h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 768h
Host Memory Space: SBREG_BAR + 0xC50000 + 768h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.289 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D5)—Offset 76Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 76Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 76Ch

Default: 0000004Fh

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x4f RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.290 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D6)—Offset 770h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 770h
Host Memory Space: SBREG_BAR + 0xC50000 + 770h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.291 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D6)—Offset 774h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 774h
Host Memory Space: SBREG_BAR + 0xC50000 + 774h

Default: 00000050h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x50 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.292 Pad Configuration DW0 (PAD_CFG_DW0_EMMC_D7)—Offset 778h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 778h
Host Memory Space: SBREG_BAR + 0xC50000 + 778h

Default: 45000300h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x1 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.293 Pad Configuration DW1 (PAD_CFG_DW1_EMMC_D7)—Offset 77Ch

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 77Ch
Host Memory Space: SBREG_BAR + 0xC50000 + 77Ch

Default: 00000051h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x51 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

65.3.294 Pad Configuration DW0 (PAD_CFG_DW0_GPIO_3)—Offset 780h

Type: Sideband Register (Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 780h
Host Memory Space: SBREG_BAR + 0xC50000 + 780h

Default: 45000200h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x1 RW	**Pad Reset Config (PADRSTCFG):** This field controls which reset is used to reset the specified Pad Register fields. It is the SoC responsibilities to decide the number of configurable reset required with an example below: • 00 = Powergood (i.e. sticky reset) • 01 = Deep GPIO Reset (i.e. host deep reset: host_deep_rst_b) • 10 = GPIO Reset (i.e. host reset: host_rst_b) • 11 = Reserved; tied to inactive (i.e. '1' for active low reset) For DSW well pads, this register default to 00b. For Primary well GPIO pads, this register default to 01b The hardware must ensure that when this field is programmed, the muxed reset signal does not glitch to cause momentarily reset assertion.
29	0x0 RW	**RX Pad State Select (RXPADSTSEL):** Determines from which node the RX pad state for native function should be taken from. This field only affects the pad state value being fanned out to native function(s) and is not meaningful if the pad is in GPIO mode (i.e. Pad Mode = 0). • 0 = Raw RX pad state directly from CFIO RX buffer • 1 = Internal RX pad state (subject to RXINV and PreGfRXSel settings)
28	0x0 RW	**RX Raw Override to '1' (RXRAW1):** This bit determines if the selected pad state is being overridden to '1'. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The override takes place at the internal pad state directly from buffer and before the RXINV. • 0 = No Override • 1 = RX drive 1 internally
27	0x0 RO	**Reserved (RSVD_0):** Reserved.
26:25	0x2 RW	**RX Level/Edge Configuration (RXEVCFG):** Determines if the internal RX pad state (synchronized, filtered vs non-filtered version as determined by PreGfRXSel, and is further subject to RXInv) should be passed on to the next logic stage as is, as a pulse, or level signal. This field does not affect the received pad state (to GPIORXState or native functions) but how the interrupt or wake triggering events should be delivered to the GPIO Community Controller. • 0h = Level • 1h = Edge • 2h = Drive '0' • 3h = Reserved (implement as setting 0h)
24	0x1 RW	**Pre Glitch Filter Stage RX Pad State Select (PREGFRXSEL):** Determines if the synchronized version of the raw RX pad state should be subjected to glitch filter or not. This field only makes sense when the RX buffer is configured as an input and is not disabled. • 0 = Select synchronized, non filtered RX pad state • 1 = Select synchronized, filtered RX pad state The selected RX pad state can be further subjected to polarity inversion through RXINV
23	0x0 RW	**RX Invert (RXINV):** This bit determines if the selected pad state should go through the polarity inversion stage. This field only makes sense when the RX buffer is configured as an input in either GPIO Mode or native function mode. The polarity inversion takes place at the mux node of raw vs filtered or non-filtered RX pad state, as determined by PreGfRXsel and RXPadStSel. This bit does not affect GPIORXState. During host ownership GPIO Mode, when this bit is set to '1', then the RX pad state is inverted as it is sent to the GPIO-to-IOxAPIC, GPE/SCI, SMI, NMI logic or GPI_IS[n] that is using it. This is used to allow active-low and active-high inputs to cause IRQ, SMI#, SCI or NMI. • 0 = No inversion • 1 = Inversion

Bit Range	Default & Access	Field Name (ID): Description
22:21	0x0 RO	**RX/TX Enable Config (RXTXENCFG):** This controls the RX and TX buffer enables for the function selected by Pad Mode, but is not applicable when Pad Mode is 0 (i.e. GPIO mode). Hardware shall ensure GPIOTxDis and GPIORxDis are controlling the RX and TX buffers when this field is 0 and Pad Mode is 0. • 0 = Function defined in Pad Mode controls TX and RX Enables • 1 = Function controls TX Enable and RX Disabled with RX drive 0 internally • 2 = Function controls TX Enable and RX Disabled with RX drive 1 internally • 3 = Function controls TX Enabled and RX is always enabled
20	0x0 RW	**GPIO Input Route IOxAPIC (GPIROUTIOXAPIC):** Determines if the pad can be routed to cause peripheral IRQ when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause peripheral IRQ • 1 = Routing can cause peripheral IRQ ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the peripheral IRQ indication to the intended recipient(s).
19	0x0 RW	**GPIO Input Route SCI (GPIROUTSCI):** Determines if the pad can be routed to cause SCI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SCI • 1 = Routing can cause SCI ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the GPE indication to the intended recipient(s), e.g. PMU.
18	0x0 RW	**GPIO Input Route SMI (GPIROUTSMI):** Determines if the pad can be routed to cause SMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause SMI. • 1 = Routing can cause SMI. ***Note:*** This bit does not affect any interrupt status bit within GPIO, but is used as the last qualifier for the SMI indication to the intended recipient(s).
17	0x0 RW	**GPIO Input Route NMI (GPIROUTNMI):** Determines if the pad can be routed to cause NMI when configured in GPIO input mode. If the pad is not configured in GPIO input mode, this field has no effect. • 0 = Routing does not cause NMI. • 1 = Routing can cause NMI. ***Note:*** This bit also affects GPI_NMI_STS. If '0', GPI_NMI_STS is always clear. If '1', GPI_NMI_STS could be set (depending on GPIOOwn setting) when there is an event. Whether a NMI indication is generated and sent to the intended recipient(s) is also depending on the corresponding GPI_NMI_EN bit.
16:13	0x0 RO	**Reserved (RSVD_1):** Reserved.
12:10	0x0 RW	**Pad Mode bits (PMODE):** Bits [12:10] of this DW0 register determine whether the Pad is controlled by GPIO controller logic or one of the SoC native functions is assigned to the Pad. Bits [12:10] decode: • 0 = GPIO controls the Pad • 1 = Function 1, if applicable, controls the Pad • 2 = Function 2, if applicable, controls the Pad • ... • 7 = Function 7, if applicable, controls the Pad
9	0x1 RW	**GPIO RX Disable (GPIORXDIS):** • 0 = Enable the input buffer (active low enable) of the pad • 1 = Disable the input buffer of the pad. ***Note:*** When the input buffer is disabled, the internal pad state is always driven to '0' by CFIO HIP.
8	0x0 RW	**GPIO TX Disable (GPIOTXDIS):** • 0 = Enable the output buffer (active low enable) of the pad • 1 = Disable the output buffer of the pad; i.e. Hi-Z
7:2	0x0 RO	**Reserved (RSVD_2):** Reserved.

Bit Range	Default & Access	Field Name (ID): Description
1	0x0 RO	**GPIO RX State (GPIORXSTATE):** This is the current internal RX pad state after Glitch Filter logic stage and is not affected by PMode and RXINV settings.
0	0x0 RW	**GPIO TX State (GPIOTXSTATE):** • 0 = Drive a level '0' to the TX output pad • 1 = Drive a level '1' to the TX output pad

65.3.295 Pad Configuration DW1 (PAD_CFG_DW1_GPIO_3)—Offset 784h

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xC5] + 784h
Host Memory Space: SBREG_BAR + 0xC50000 + 784h

Default: 00000052h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**.
13:10	0x0 RW	**Termination (TERM):** The Pad Termination state defines the different weak Pull-Up and Pull-Down settings that are supported by the buffer. The settings for register bits [13:10] correspond to: • 0h = none • 2h = 5k weak Pull-Down • 4h = 20k weak Pull-Down • 8h = none • 9h = 1k weak Pull-Up • Ah = 5k weak Pull-Up • Bh = 2k weak Pull-Up • Ch = 20k weak Pull-Up • Dh = 1k and 2k weak Pull-Up • Fh = The TERM register does not define the termination. Instead, the SoC internal circuitry controls the type and value of the termination, if any, on this pad. • All others bit settings are reserved. If a reserved value is programmed, the pad may malfunction. The setting of this register field is applicable in all Pad Modes including GPIO. As each Pad Mode may require different termination and isolation, care must be taken by software and BIOS in the transition with appropriate register programming. The actual transition sequence requirement may vary on case-by-case basis depending on the native functions involved. For example, before changing the pad from the output to input direction, the weak Pull-Up/Pull-Down settings should be programmed first to ensure the input does not float momentarily.
9:8	0x0 RO	**Reserved**.
7:0	0x52 RO	**Interrupt Select (INTSEL):** The Interrupt Select defines which interrupt line driven from the GPIO Controller toggles when an interrupt is detected on this pad. • 0 = Interrupt Line 0 • 1 = Interrupt Line 1 Up to the max IOxAPIC IRQ supported by the SoC.

§ §

66 SMBus - PECI

66.1 Introduction and Index

Much of the programming-related information and register descriptions for the SMBus-PECI are in Section 30, "SMBus Controller - Platform Environment Control Interface" on page 795.

The legend for the register access codes are described in Chapter 43, "Introduction."

§ §

67 Interrupt Steering and Control

67.1 Introduction and Index

The host-accessible registers for Interrupt Steering and Control are described here. The legend for the register access codes are described in Chapter 43, “Introduction.”

67.1.1 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

Table 67-1. Summary of Sideband Registers—0xD0

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
3100	80	"PIRQA Routing Control (PARC)—Offset 3100h" on page 3741
3101	80	"PIRQB Routing Control (PBRC)—Offset 3101h" on page 3742
3102	80	"PIRQC Routing Control (PCRC)—Offset 3102h" on page 3743
3103	80	"PIRQD Routing Control (PDRC)—Offset 3103h" on page 3744
3104	80	"PIRQE Routing Control (PERC)—Offset 3104h" on page 3745
3105	80	"PIRQF Routing Control (PFRC)—Offset 3105h" on page 3746
3106	80	"PIRQG Routing Control (PGRC)—Offset 3106h" on page 3747
3107	80	"PIRQH Routing Control (PHRC)—Offset 3107h" on page 3748
3120	00000000	"Message Decoder Control (MSGDC)—Offset 3120h" on page 3749
3140	3210	"PCI Interrupt Route 0 (PIR0)—Offset 3140h" on page 3750
3142	3210	"PCI Interrupt Route 1 (PIR1)—Offset 3142h" on page 3751
3144	3210	"PCI Interrupt Route 2 (PIR2)—Offset 3144h" on page 3752
3146	3210	"PCI Interrupt Route 3 (PIR3)—Offset 3146h" on page 3753
3148	3210	"PCI Interrupt Route 4 (PIR4)—Offset 3148h" on page 3754
314A	3210	"PCI Interrupt Route 5 (PIR5)—Offset 314Ah" on page 3755
314C	3210	"PCI Interrupt Route 6 (PIR6)—Offset 314Ch" on page 3756
314E	3210	"PCI Interrupt Route 7 (PIR7)—Offset 314Eh" on page 3757
3150	3210	"PCI Interrupt Route 8 (PIR8)—Offset 3150h" on page 3758
3152	3210	"PCI Interrupt Route 9 (PIR9)—Offset 3152h" on page 3759
3154	3210	"PCI Interrupt Route 10 (PIR10)—Offset 3154h" on page 3760
3156	3210	"PCI Interrupt Route 11 (PIR11)—Offset 3156h" on page 3761
3158	3210	"PCI Interrupt Route 12 (PIR12)—Offset 3158h" on page 3762
31FC	00000000	"General Interrupt Control (GIC)—Offset 31FCh" on page 3763
3200	00FF0000	"Interrupt Polarity Control 0 (IPC0)—Offset 3200h" on page 3765
3204	00000000	"Interrupt Polarity Control 1 (IPC1)—Offset 3204h" on page 3765
3208	00000000	"Interrupt Polarity Control 2 (IPC2)—Offset 3208h" on page 3765
320C	00000000	"Interrupt Polarity Control 3 (IPC3)—Offset 320Ch" on page 3766
3220	00000000	"Interrupt Blocking Control (IBC)—Offset 3220h" on page 3766
3230	00000000	"Interrupt Edge-Trigger Extension 0 (IETE0)—Offset 3230h" on page 3766
3234	00000000	"Interrupt Edge-Trigger Extension 1 (IETE1)—Offset 3234h" on page 3767
3238	00000000	"Interrupt Edge-Trigger Extension 2 (IETE2)—Offset 3238h" on page 3767
323C	00000000	"Interrupt Edge-Trigger Extension 3 (IETE3)—Offset 323Ch" on page 3767
3300	00000000	"ITSS Power Reduction Control (ITSSPRC)—Offset 3300h" on page 3768
3304	0033	"SIDE Clock Timing (SIDECT)—Offset 3304h" on page 3769
3306	0033	"IPCI Clock Timing (IPCICT)—Offset 3306h" on page 3770
3308	0003	"PGCB Clock Timing (PGCBCT)—Offset 3308h" on page 3770

Table 67-1. Summary of Sideband Registers—0xD0 (Continued)

Offset (hex)	Default Value (hex)	Register Name (Register Symbol)
3320	00000000	"Uncorrectable Error Mask (UEM)—Offset 3320h" on page 3771
3324	00000000	"Uncorrectable Error Severity (UEV)—Offset 3324h" on page 3772
3328	00002000	"Correctable Error Mask (CEM)—Offset 3328h" on page 3773
3330	00000000	"NMI Control (NMI)—Offset 3330h" on page 3774
3334	0000	"Master Message Control (MMC)—Offset 3334h" on page 3775
3336	0001	"Master Message Status (MMSTS)—Offset 3336h" on page 3775
3400	00000000	"HPET Offload Scale Value (HOFFVAL)—Offset 3400h" on page 3776

67.2 Sideband Registers

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method" on page 187.

67.2.1 PIRQA Routing Control (PARC)—Offset 3100h

PIRQA Routing Control Register.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3100h
Host Memory Space: SBREG_BAR + 0xD00000 + 3100h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQA is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQA is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQA • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.2 PIRQB Routing Control (PBRC)—Offset 3101h

PIRQB Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3101h
Host Memory Space: SBREG_BAR + 0xD00000 + 3101h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQB is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQB is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQB • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.3 PIRQC Routing Control (PCRC)—Offset 3102h

PIRQC Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3102h
Host Memory Space: SBREG_BAR + 0xD00000 + 3102h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQC is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQC is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQC • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.4 PIRQD Routing Control (PDRC)—Offset 3103h

PIRQD Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3103h
Host Memory Space: SBREG_BAR + 0xD00000 + 3103h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQD is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQD is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQD • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.5 PIRQE Routing Control (PERC)—Offset 3104h

PIRQE Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3104h
Host Memory Space: SBREG_BAR + 0xD00000 + 3104h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQE is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQE is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQE • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.6 PIRQF Routing Control (PFRC)—Offset 3105h

PIRQF Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3105h
Host Memory Space: SBREG_BAR + 0xD00000 + 3105h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQF is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQF is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQF • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.7 PIRQG Routing Control (PGRC)—Offset 3106h

PIRQG Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3106h
Host Memory Space: SBREG_BAR + 0xD00000 + 3106h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQG is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQG is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQG • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.8 PIRQH Routing Control (PHRC)—Offset 3107h

PIRQH Routing Control Register. It has the same programming values as PARC.

Type: Sideband Register
(Size: 8 bits)

Sideband Port and Offset: [Port: 0xD0] + 3107h
Host Memory Space: SBREG_BAR + 0xD00000 + 3107h

Default: 80h

Bit Range	Default & Access	Field Name (ID): Description
7	0x1 RW	**Interrupt Routing Enable (REN):** When cleared, PIRQH is routed to one of the legacy interrupts specified in bits [3:0] of this register. When set, the PIRQH is not routed to the internal 8259 Programmable Interrupt Controller (PIC). **Power Well:** Core
6:4	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
3:0	0x0 RW	**IRQ Routing (IR):** IRQ destination for PIRQH • 0000 - Reserved • 0001 - Reserved • 0010 - Reserved • 0011 - IRQ3 • 0100 - IRQ4 • 0101 - IRQ5 • 0110 - IRQ6 • 0111 - IRQ7 • 1000 - Reserved • 1001 - IRQ9 • 1010 - IRQ10 • 1011 - IRQ11 • 1100 - IRQ12 • 1101 - Reserved • 1110 - IRQ14 • 1111 - IRQ15 **Power Well:** Core

67.2.9 Message Decoder Control (MSGDC)—Offset 3120h

Message Decoder Control Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3120h
Host Memory Space: SBREG_BAR + 0xD00000 + 3120h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:12	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core
11:8	0x0 RW	**INTA-D Default Decoder PIR Mapping (INTDDPIR):** Specifies the PIR register to use for the INTA-D Default Decoder state. PIR registers map INTA-D state to PRIQA-H. This value is only used when INTDDEN is set. ***Note:*** Acceptable values include any valid PIR register number (i.e. 0-12) or the value of 13. The value of 13, which behaves similar to the PIR direct connect source IDs, maps INTA to PIRQA, INTB maps to PIRQB, INTC maps to PIRQC and INTD maps to PIRQD and has no programmable option to change it. **Power Well:** Core
7:3	0x0 RO	**Reserved (RSVD2):** Reserved **Power Well:** Core
2	0x0 RW	**NMI Default Decoder Enable (NMIDDEN):** When set, the NMI decode logic will accept ASSERT_NMI/DEASSERT_NMI messages from unknown sources (sources not specified with the NMI_SRC_ID and (if OPC_ASRT/DSRTNMI == OPC_ASRT/DASRTIOCHK which is the default case) IOCHK_SRC_ID parameters). When cleared, NMI messages from unknown sources will be dropped. **Power Well:** Core
1	0x0 RW	**INTAD Default Decoder Enable (INTDDEN):** When set, the INTA-D decoder logic will accept ASSERT_INTA-D/DEASSERT_INTA-D messages from unknown sources (source not specified with the IPIR0-12_SRC_ID and PIRDC_SRC_ID parameters). When cleared, INTA-D messages from unknown sources will be dropped. **Power Well:** Core
0	0x0 RW	**IRQN Default Decoder Enable (IRQDDEN):** When set, the IRQN decoder logic will accept ASSERT_IRQN/DEASSERT_IRQN messages from unknown source (source not specified with the SIRQ_SINGLE_CAUSE_SRC_ID and SIRQ_MULTI_CAUSE_SRC_ID parameters). When cleared, IRQN messages from unknown sources will be dropped. **Power Well:** Core

67.2.10 PCI Interrupt Route 0 (PIR0)—Offset 3140h

PCI Interrupt Route 0 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3140h
Host Memory Space: SBREG_BAR + 0xD00000 + 3140h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.11 PCI Interrupt Route 1 (PIR1)—Offset 3142h

PCI Interrupt Route 1 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3142h
Host Memory Space: SBREG_BAR + 0xD00000 + 3142h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC# **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.12 PCI Interrupt Route 2 (PIR2)—Offset 3144h

PCI Interrupt Route 2 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3144h
Host Memory Space: SBREG_BAR + 0xD00000 + 3144h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.13 PCI Interrupt Route 3 (PIR3)—Offset 3146h

PCI Interrupt Route 3 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3146h
Host Memory Space: SBREG_BAR + 0xD00000 + 3146h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.14 PCI Interrupt Route 4 (PIR4)—Offset 3148h

PCI Interrupt Route 4 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3148h
Host Memory Space: SBREG_BAR + 0xD00000 + 3148h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.15 PCI Interrupt Route 5 (PIR5)—Offset 314Ah

PCI Interrupt Route 5 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 314Ah
Host Memory Space: SBREG_BAR + 0xD00000 + 314Ah

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.16 PCI Interrupt Route 6 (PIR6)—Offset 314Ch

PCI Interrupt Route 6 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 314Ch
Host Memory Space: SBREG_BAR + 0xD00000 + 314Ch

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.17 PCI Interrupt Route 7 (PIR7)—Offset 314Eh

PCI Interrupt Route 7 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 314Eh
Host Memory Space: SBREG_BAR + 0xD00000 + 314Eh

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.18 PCI Interrupt Route 8 (PIR8)—Offset 3150h

PCI Interrupt Route 8 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3150h
Host Memory Space: SBREG_BAR + 0xD00000 + 3150h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.19 PCI Interrupt Route 9 (PIR9)—Offset 3152h

PCI Interrupt Route 9 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3152h
Host Memory Space: SBREG_BAR + 0xD00000 + 3152h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.20 PCI Interrupt Route 10 (PIR10)—Offset 3154h

PCI Interrupt Route 10 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3154h
Host Memory Space: SBREG_BAR + 0xD00000 + 3154h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.21 PCI Interrupt Route 11 (PIR11)—Offset 3156h

PCI Interrupt Route 11 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3156h
Host Memory Space: SBREG_BAR + 0xD00000 + 3156h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.22 PCI Interrupt Route 12 (PIR12)—Offset 3158h

PCI Interrupt Route 12 Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3158h
Host Memory Space: SBREG_BAR + 0xD00000 + 3158h

Default: 3210h

Bit Range	Default & Access	Field Name (ID): Description
15	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
14:12	0x3 RW	**Interrupt D Pin Route (IDR):** Indicates which PIRQ internal to the SoC is connected to the INTD#. • 0h - PIRQA# • 1h - PIRQB# • 2h - PIRQC# • 3h - PIRQD# • 4h - PIRQE# • 5h - PIRQF# • 6h - PIRQG# • 7h - PIRQH# **Power Well:** Core
11	0x0 RO	**Reserved (RSVD_1):** Reserved **Power Well:** Core
10:8	0x2 RW	**Interrupt C Pin Route (ICR):** See the IDR description. This field applies to INTC#. **Power Well:** Core
7	0x0 RO	**Reserved (RSVD_2):** Reserved **Power Well:** Core
6:4	0x1 RW	**Interrupt B Pin Route (IBR):** See the IDR description. This field applies to INTB#. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD_3):** Reserved **Power Well:** Core
2:0	0x0 RW	**Interrupt A Pin Route (IAR):** See the IDR description. This field applies to INTA#. **Power Well:** Core

67.2.23 General Interrupt Control (GIC)—Offset 31FCh

FEC10000h - FEC3FFFFh is allocated to PCIe when Port I/OxAPIC Enable (PAE) bit is set.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 31FCh
Host Memory Space: SBREG_BAR + 0xD00000 + 31FCh

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
21	0x0 RW	**CF9 Completion Dependency Disable (CF9NODEP):** When set, the completion ordering between the Non-Posted IO Write causing CF9 Request to PMC and the GO_S1_SENT indication is disabled. In other words, the IO Write completion can be issued before PMC indicates the GO_S1_SENT indication. When cleared, the completion for the IO Write is only sent after the GO_S1_SENT indication asserts. **Power Well:** Core
20	0x0 RW	**INIT# VLW Message Completion Dependacy Disable (INITVMNODEP):** When sent, the completion ordering between the Non-Posted IO Write which causes an INIT and the Non-Posted VLW message which signals the INIT is broken. In other words, the IO Write completion can be sent out before the VLW completion is received. When cleared, the completion for the IO Write is only be sent AFTER the completion for the VLW is received. **Power Well:** Core
19	0x0 RW	**INIT# VLW Message Disable (INITVMDIS):** Disable INIT# VLW message. When set, if other type of VLW message to be sent, the VLWValue Bit[5] under VLW Vendor Defined Message should always be 0 - no active edge on INIT#. When clear, the INIT# information will be conveyed as normal. **Power Well:** Core
18	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
17	0x0 RW	**Alternate Access Mode Enable (AME):** When set, read only registers can be written, and write only registers can be read. **Power Well:** Core
16	0x0 RW	**Shutdown Policy Select (SDPS):** When cleared (default) the PCH will update INIT# in response to the shutdown Vendor Defined Message (VDM). When set to 1, PCH will treat the shutdown VDM similar to receiving a CF9h I/O write, and will drive PLTRST# active. See Section 16.13 Reset Behavior for variations on whether power is cycled due to this reset source depending on the programming of other bits. BIOS guide note: This register is reset any time PLTRST# asserts. **Power Well:** Core
15:9	0x0 RW	**MAX_IRQ_ENTRY_SIZE (MAXIRQSIZE):** This field indicates the size of the IOxAPIC entry. The default size is 120 entries. • 0000000: 120 entry size • 0000001: 24 entry size (Legacy mode) • 0000010 - 1111111: Reserved **Power Well:** Core

Bit Range	Default & Access	Field Name (ID): Description
8	0x0 RW	**Server Error Reporting Mode (SERM):** When set, the CPU Complex is the final target of all host space errors. In this mode, if the PCH detects a fatal, non-fatal, or correctable error on DMI or PSFs, it sends one of ERR_FATAL, ERR_NONFATAL, or ERR_CORR to CPU Complex. When cleared, the SoC is the final target of all host space errors. **Power Well:** Core
7:2	0x0 RW	**Reserved (RSVD2):** Scratch pad: These bits are reserved for future use. **Power Well:** Core
1	0x0 RW	**INIT# VLW Message Disable Mode (INITVMDISMODE):** This policy bit dictates the INIT# handling when INITVMDIS is configured to 1. When set to 1 and INITVMDIS = 1, the INIT# events will be dropped such that upon clearing the INITVMDIS = 0 later, no INIT# VLW Message is released. When set to 0 (default) and INITVMDIS = 1, the INIT# events will be masked such that upon clearing the INITVMDIS = 0 later, the INIT# VLW Message is released. **Power Well:** Core
0	0x0 RO/P	**CPU Shutdown Status (CPUSDSTS):** This bit is set to 1 if the CPU sends the Shutdown Special cycle message. The Shutdown Message is recognized as an INIT# event if the Shutdown Policy Select = 0. Otherwise the SoC treats the Shutdown Special cycle as a request for CF9 Hard Reset. This is a sticky Read Only bit that is only reset by a loss of core power. **Power Well:** Core

67.2.24 Interrupt Polarity Control 0 (IPC0)—Offset 3200h

Interrupt Polarity Control 0 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3200h
Host Memory Space: SBREG_BAR + 0xD00000 + 3200h

Default: 00FF0000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0xff0000 RW	**IRQ 31-0 Active High Polarity Disable (IPC0_IRQxAHPOLDIS):** IRQ 31-0 Active High Polarity Disable (IPC0.IRQxAHPOLDIS): When set to 1, the interrupt polarity associated with IRQ31 down to IRQ0 is inverted to appear as Active Low to IOxAPIC. When set to 0, the interrupt is appears as Active High to IOxAPIC. **Power Well:** Core

67.2.25 Interrupt Polarity Control 1 (IPC1)—Offset 3204h

Interrupt Polarity Control 1 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3204h
Host Memory Space: SBREG_BAR + 0xD00000 + 3204h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**IRQ 63-32 Active High Polarity Disable (IPC1_IRQAHPOLDIS):** IRQ 63-32 Active High Polarity Disable (IPC1.IRQAHPOLDIS): When set to 1, the interrupt polarity associated with IRQ63 down to IRQ32 is inverted to appear as Active Low to IOxAPIC. When set to 0, the interrupt is appears as Active High to IOxAPIC. **Power Well:** Core

67.2.26 Interrupt Polarity Control 2 (IPC2)—Offset 3208h

Interrupt Polarity Control 2 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3208h
Host Memory Space: SBREG_BAR + 0xD00000 + 3208h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**IRQ 95-64 Active High Polarity Disable (IPC2_IRQAHPOLDIS):** IRQ 95-64 Active High Polarity Disable (IPC2.IRQAHPOLDIS): When set to 1, the interrupt polarity associated with IRQ95 down to IRQ64 is inverted to appear as Active Low to IOxAPIC. When set to 0, the interrupt is appears as Active High to IOxAPIC. **Power Well:** Core

67.2.27 Interrupt Polarity Control 3 (IPC3)—Offset 320Ch

Interrupt Polarity Control 3 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 320Ch
Host Memory Space: SBREG_BAR + 0xD00000 + 320Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
23:0	0x0 RW	**IRQ 119-96 Active High Polarity Disable (IPC3_IRQAHPOLDIS):** IRQ 119-96 Active High Polarity Disable (IPC3.IRQAHPOLDIS): When set to 1, the interrupt polarity associated with IRQ119 down to IRQ96 is inverted to appear as Active Low to IOxAPIC. When set to 0, the interrupt is appears as Active High to IOxAPIC. **Power Well:** Core

67.2.28 Interrupt Blocking Control (IBC)—Offset 3220h

Interrupt Blocking Control Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3220h
Host Memory Space: SBREG_BAR + 0xD00000 + 3220h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**IRQ 23-0 IRQx Interrupt Disable (IRQxDIS):** When set to 1, any interrupts associated with IRQ23 down to IRQ0 originating from ASSERT_IRQn sideband messages are blocked from reaching the 8259 and IOxAPIC interrupt controllers. When set to 0, interrupts are allowed to pass to the interrupt controllers. SIRQ_NUM_OF_SHAREABLE parameter value will affect the bits function.bit SIRQ_NUM_OF_SHAREABLE-1:0] will act as IRQxDIS function, bit [31:SIRQ_NUM_OF_SHAREABLE] will be reserved. **Power Well:** Core

67.2.29 Interrupt Edge-Trigger Extension 0 (IETE0)—Offset 3230h

Interrupt Edge-Trigger Extension 0 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3230h
Host Memory Space: SBREG_BAR + 0xD00000 + 3230h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**IRQ 31-0 Disable Edge-Triggered Interrupt Extension (IETE31_0):** When set, DSn bits corresponding to Edge-triggered interrupts gets cleared if the interrupt source is de-asserted before interrupt gets serviced (this is backward compatible with previous architectures). When cleared, the IOxAPIC DSn bit corresponding to Edge-triggered interrupts stays asserted (i.e. extended) even when interrupt source is de-asserted before interrupt gets serviced. **Power Well:** Core

67.2.30 Interrupt Edge-Trigger Extension 1 (IETE1)—Offset 3234h

Interrupt Edge-Trigger Extension 1 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3234h
Host Memory Space: SBREG_BAR + 0xD00000 + 3234h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**IRQ 63-32 Disable Edge-Triggered Interrupt Extension (IETE63_32):** When set, DSn bits corresponding to Edge-triggered interrupts gets cleared if the interrupt source is de-asserted before interrupt gets serviced (this is backward compatible with previous architectures). When cleared, the IOxAPIC DSn bit corresponding to Edge-triggered interrupts stays asserted (i.e. extended) even when interrupt source is de-asserted before interrupt gets serviced. **Power Well:** Core

67.2.31 Interrupt Edge-Trigger Extension 2 (IETE2)—Offset 3238h

Interrupt Edge-Trigger Extension 2 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3238h
Host Memory Space: SBREG_BAR + 0xD00000 + 3238h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:0	0x0 RW	**IRQ 95-64 Disable Edge-Triggered Interrupt Extension (IETE95_64):** When set, DSn bits corresponding to Edge-triggered interrupts gets cleared if the interrupt source is de-asserted before interrupt gets serviced (this is backward compatible with previous architectures). When cleared the IOxAPIC DSn bit corresponding to Edge-triggered interrupts stays asserted (i.e. extended) even when interrupt source is de-asserted before interrupt gets serviced. **Power Well:** Core

67.2.32 Interrupt Edge-Trigger Extension 3 (IETE3)—Offset 323Ch

Interrupt Edge-Trigger Extension 3 Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 323Ch
Host Memory Space: SBREG_BAR + 0xD00000 + 323Ch

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:24	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core
23:0	0x0 RW	**IRQ 119-96 Disable Edge-Triggered Interrupt Extension (IETE119_96):** When set, DSn bits corresponding to Edge-triggered interrupts gets cleared if the interrupt source is de-asserted before interrupt gets serviced (this is backward compatible with previous architectures). When cleared the IOxAPIC DSn bit corresponding to Edge-triggered interrupts stays asserted (i.e. extended) even when interrupt source is de-asserted before interrupt gets serviced. **Power Well:** Core

67.2.33 ITSS Power Reduction Control (ITSSPRC)—Offset 3300h

Power controls for the entire interrupt and timer subsystem.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3300h
Host Memory Space: SBREG_BAR + 0xD00000 + 3300h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:5	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
4	0x0 RW	**PGCB Dynamic Clock Gating Enable (PGCBDCGE):** When set, the ITSS enables dynamic clock gating of the PGCB clock domain. BIOS is requested to program this field to 1. **Power Well:** Core
3	0x0 RW	**HPET Dynamic Clock Gating Enable (HPETDCGE):** When set, the HPET enables dynamic clock gating. BIOS is requested to program this field to 1. **Power Well:** Core
2	0x0 RW	**8254 Static Clock Gating Enable (CGE8254):** When set, the 8254 Programmable Interval Timer is disabled statically. This bit shall be set by BIOS if the 8254 feature is not needed in the system or before BIOS hands off the system that supports C11. Normal operation of 8254 requires this bit to 0. **Power Well:** Core
1	0x0 RW	**Sideband Dynamic Clock Gating Enable (SBDCGE):** Setting this bit will enable all dynamic clock gating of the Sideband Clock domain. BIOS is requested to program this field to 1. **Power Well:** Core
0	0x0 RW	**PCI Dynamic Clock Gating Enable (PCIDCGE):** Setting this bit will enable dynamic clock gating for the ITSS Core Logic that uses PCI Clock. BIOS is requested to program this field to 1. **Power Well:** Core

67.2.34 SIDE Clock Timing (SIDECT)—Offset 3304h

SIDE Clock Timing Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3304h
Host Memory Space: SBREG_BAR + 0xD00000 + 3304h

Default: 0033h

Bit Range	Default & Access	Field Name (ID): Description
15:7	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core
6:4	0x3 RW	**Clock Request Hold-Off (CLKREQHO):** Defines the amount of idle time required between locking for power gate preparation and deassertion of the prim_clkreq signal. This field defines the exponent such that the actual delay = 2^ CLKREQHO. **WARNING:** This value should not be updated unless the Sideband Interface Clock Gating Enable (ITSSPRC.SBDCGE) control register bit is set to 0. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD2):** Reserved **Power Well:** Core
2:0	0x3 RW	**Clock Gating Hold-Off (CLKGATEHO):** Defines the amount of idle time required before local clock gating will be engaged (if enabled). This field defines the exponent such that the actual delay = 2^ CLGATEHO. **WARNING:** This value should not be updated unless the Sideband Interface Clock Gating Enable (ITSSPRC.SBDCGE) control register bit is set to 0. **Power Well:** Core

67.2.35 IPCI Clock Timing (IPCICT)—Offset 3306h

IPCI Clock Timing Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3306h
Host Memory Space: SBREG_BAR + 0xD00000 + 3306h

Default: 0033h

Bit Range	Default & Access	Field Name (ID): Description
15:7	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core
6:4	0x3 RW	**Clock Request Hold-Off (CLKREQHO):** Defines the amount of idle time required between locking for power gate preparation and deassertion of the prim_clkreq signal. This field defines the exponent such that the actual delay = 2^ CLKREQHO. **WARNING:** This value should not be updated unless the PCI Dynamic Clock Gate Enable (ITSSPRC.PCIDCGE) control register bit is set to 0. **Power Well:** Core
3	0x0 RO	**Reserved (RSVD2):** Reserved **Power Well:** Core
2:0	0x3 RW	**Clock Gating Hold-Off (CLKGATEHO):** Defines the amount of idle time required before local clock gating will be engaged (if enabled). This field defines the exponent such that the actual delay = 2^ CLGATEHO. **WARNING:** This value should not be updated unless the PCI Dynamic Clock Gate Enable (ITSSPRC.PCIDCGE) control register bit is set to 0. **Power Well:** Core

67.2.36 PGCB Clock Timing (PGCBCT)—Offset 3308h

PGCB Clock Timing Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3308h
Host Memory Space: SBREG_BAR + 0xD00000 + 3308h

Default: 0003h

Bit Range	Default & Access	Field Name (ID): Description
15:4	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core
3:0	0x3 RW	**Clock Gating Hold-Off (CLKGATEHO):** Specifies the minimum number of delay clocks the PGCB clock gate sequencing should wait, before enabling the PGCB clock to be gated at the trunk-level. **WARNING:** This value should not be updated unless the PGCB Dynamic Clock Gate Enable (ITSSPRC.PGCBDCGE) control register bit is set to 0. **Power Well:** Core

67.2.37 Uncorrectable Error Mask (UEM)—Offset 3320h

When set, the corresponding error is masked, and the reported error will cause no action. When cleared, the corresponding error is enabled. This register is only reset by a loss of core power.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3320h
Host Memory Space: SBREG_BAR + 0xD00000 + 3320h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**Reserved (RSVD4):** Reserved **Power Well:** Core
22	0x0 RW/P	**Uncorrectable Internal Error Mask (UIE):** Mask for uncorrectable internal errors (to be used for parity errors). **Power Well:** Core
21	0x0 RO	**Reserved (RSVD3):** Reserved **Power Well:** Core
20	0x0 RW/P	**Unsupported Request Error Mask (URE):** Mask for uncorrectable errors **Power Well:** Core
19:17	0x0 RO	**Reserved (RSVD2):** Reserved **Power Well:** Core
16	0x0 RW/P	**Unexpected Completion Mask (UC):** Mask for unexpected completions. **Power Well:** Core
15:0	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core

67.2.38 Uncorrectable Error Severity (UEV)—Offset 3324h

This register gives the option to make an uncorrectable error fatal or non-fatal. An error is fatal if the bit is set. An error is non-fatal is the bit is cleared. This register is only reset by a loss of core power.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3324h
Host Memory Space: SBREG_BAR + 0xD00000 + 3324h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:23	0x0 RO	**Reserved (RSVD4):** Reserved **Power Well:** Core
22	0x0 RW/P	**Uncorrectable Internal Error Severity (UIE):** Severity for uncorrectable internal errors (to be used for parity errors). **Power Well:** Core
21	0x0 RO	**Reserved (RSVD3):** Reserved **Power Well:** Core
20	0x0 RW/P	**Unsupported Request Error Severity (URE):** Severity for uncorrectable errors **Power Well:** Core
19:17	0x0 RO	**Reserved (RSVD2):** Reserved **Power Well:** Core
16	0x0 RW/P	**Unexpected Completion Severity (UC):** Severity for unexpected completions. **Power Well:** Core
15:0	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core

67.2.39 Correctable Error Mask (CEM)—Offset 3328h

When set, the corresponding error is masked and the reported error will cause no action. When cleared, the corresponding error is enabled. This register is only reset by a loss of core power.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3328h
Host Memory Space: SBREG_BAR + 0xD00000 + 3328h

Default: 00002000h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved (RSVD2):** Reserved **Power Well:** Core
13	0x1 RW/P	**Advisory Non-Fatal Error Mask (ANFEM):** When set, masks Advisory Non-Fatal errors from signaling ERR_COR to the device control register. Set by default to enable compatibility with software that does not comprehend Role-Based Error Reporting. **Power Well:** Core
12:0	0x0 RO	**Reserved (RSVD1):** Reserved **Power Well:** Core

67.2.40 NMI Control (NMI)—Offset 3330h

NMI Control Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3330h
Host Memory Space: SBREG_BAR + 0xD00000 + 3330h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:6	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
5	0x0 RW/1C	**NMI VLW Delivery Status (NMI_VLW_STS):** A writable status bit which is set whenever a VLW message that assert NMI is successfully sent and the associated completion is received. Its intent is to enable a pooling mechanism for software to enforce NMI_NOW message ordering. Once set, writing the bit to1 will clear the status. Writing the bit to 0 has no effect. **Power Well:** Core
4	0x0 RO/V	**NMI Status (NMI_STS):** RO status bit indicating the current NMI status. The bit will be set to (1b1) if any NMI source is asserted and NMI2SMI_EN is set to (1b0). ***Note:*** In models *not* compiled with the USE_NMI_CTRL_REG, the value of NMI2SMI_EN will come from the mu1_smnmi2smi_en interface pin rather than the NMI2SMI_EN control register bit. **Power Well:** Core
3	0x0 RO/V	**NMI-to-SMI Status (NMI2SMI_STS):** RO status bit indicating the current NMI2SMI status. The bit will be set (1b1) if any NMI source is asserted and NMI2SMI_EN is set (1b1). ***Note:*** In models *not* compiled with the USE_NMI_CTRL_REG, the value of NMI2SMI_EN will come from the mu1_smnmi2smi_en interface pin rather than the NMI2SMI_EN control register bit. **Power Well:** Core
2	0x0 RW	**NMI-to-SMI Enable (NMI2SMI_EN):** Setting to 1b1 causes NMIs to be sent as ASSERT_SMI/ DEASSERT_SMI messages to PMC instead of the regular NMI messages. Setting to 1b0 maintains the regular NMI routing (as VLW and VM). Bits NMI_NOW and NMI2SMI_EN can't be configured on same cycle. **Power Well:** Core
1	0x0 RO/V	**NMI NOW Status (NMI_NOW_STS):** RO status bit indicating the current state of NMI_NOW. See NMI_NOW. **Power Well:** Core
0	0x0 WO	**NMI Now Command (NMI_NOW):** Writing 1b1 to NMI_NOW inverts the NMI NOW Status (NMI_NOW_STS) value. The first time NMI_NOW is written sets the NMI_NOW_STS and initiates an NMI. The next write clears the NMI_NOW_STS and allows initiating NMI by the next write to NMI_NOW. Writing 1b0 to NMI_NOW has no effect. Bits NMI_NOW and NMI2SMI_EN can't be configured on same cycle. **Power Well:** Core

67.2.41 Master Message Control (MMC)—Offset 3334h

Master Message Control Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3334h
Host Memory Space: SBREG_BAR + 0xD00000 + 3334h

Default: 0000h

Bit Range	Default & Access	Field Name (ID): Description
15:1	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
0	0x0 RW/V	**Master Message Enable (MSTRMSG_EN):** When set, allows ITSS to release any pending/in progress IOAPIC MWr, HPET MWr, VLW_EVT or the ERR Messages to the IOSF SB. When cleared, ITSS prevents these messages from being issued to the IOSF SB. The Master Message Enable sets to 1 when: • BIOS SW write to 1 • ITSS receives the IOSF SB MSTR_MSG_EN Message. The Master Message Enable clears to 0 when: • BIOS SW write to 0 • ITSS receives the IOSF SB MSTR_MSG_DIS Message • ITSS receives the RESET_PREP Message • ITSS receives the FORCEPWRGOK Message ***Note:*** This bit supersedes the INITVMDIS policy bit. For example, if MSTRMSGEN = 0 but INITVMDIS = 0, INIT# VLW message is disallowed. **Power Well:** Core

67.2.42 Master Message Status (MMSTS)—Offset 3336h

Master Message Status Register

Type: Sideband Register
(Size: 16 bits)

Sideband Port and Offset: [Port: 0xD0] + 3336h
Host Memory Space: SBREG_BAR + 0xD00000 + 3336h

Default: 0001h

Bit Range	Default & Access	Field Name (ID): Description
15:1	0x0 RO	**Reserved (RSVD):** Reserved Field **Power Well:** Core
0	0x1 RO/V	**Master Message Locked (MSTRMSGLOC_STS):** Sets when the Master Message Enable (MSTRMSG_EN) bit is set to 0 and all Sideband Message Mastering has stopped. Clears when MSTRMSG_EN==1. This bit has no direct effect on hardware and is used as a semaphore bit to indicate Message Mastering on IOSF SB is busy/not complete. **Power Well:** Core

67.2.43 HPET Offload Scale Value (HOFFVAL)—Offset 3400h

HPET Offload Scale Value Register

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: [Port: 0xD0] + 3400h
Host Memory Space: SBREG_BAR + 0xD00000 + 3400h

Default: 00000000h

Bit Range	Default & Access	Field Name (ID): Description
31:28	0x0 RO	**Reserved (RSVD):** Reserved **Power Well:** Core
27:0	0x0 RW/P	**Offload Scale Value (VAL):** Offload Scale Value (VAL): Indicates the lower 28 bits of the value that should be added to the slow clock counter during RTC offload of the HPET timers. **Power Well:** Core

§ §

68 PHY - High-Speed I/O

68.1 Introduction and Index

The host-accessible registers for the PHY circuitry for the High-Speed I/O (HSIO) interface. Only the registers associated with customer PHY Tuning are shown. The HSIO interface is comprised of the:

- PCI Express* HSIO Lanes
- SATA HSIO Lanes
- USB 3.0 HSIO Lanes

The SoC has 20 HSIO Lanes maximum and are configured as shown in the Chapter 10, "Flexible I/O Adapter (FIA) Overview."

To determine the number of HSIO lanes and interface types available refer to the following:

- Table 1-1, "Features by product SKU - Server and Cloud Storage SKUs 0 through 4"
- Table 1-2, "Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10"
- Table 1-3, "Features by Product SKU - Extended Temperature SKUs 11 through 14".

The legend for the register access codes are described in Chapter 43, "Introduction."

Please refer to the document #568853 for the detail about how to tune the registers for HSIO interfaces.

68.1.1 Sideband Registers

An index of the Sideband registers that are accessible to the Host are listed here. Each is accessible in Host Memory Space using the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method".

Table 68-1. Summary of Sideband Registers (Lane 0 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
28	BA_0028	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
94	BA_0094	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
98	BA_0098	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
9C	BA_009C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
CC	BA_00CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
150	BA_0150	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
154	BA_0154	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
164	BA_0164	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
168	BA_0168	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-2. Summary of Sideband Registers (Lane 1 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
228	BA_0228	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
294	BA_0294	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
298	BA_0298	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
29C	BA_029C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
2CC	BA_02CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
350	BA_0350	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
354	BA_0354	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
364	BA_0364	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
368	BA_0368	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-3. Summary of Sideband Registers (Lane 2 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
428	BA_0428	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
494	BA_0494	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
498	BA_0498	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
49C	BA_049C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
4CC	BA_04CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
550	BA_0550	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
554	BA_0554	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
564	BA_0564	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
568	BA_0568	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-4. Summary of Sideband Registers (Lane 3 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
628	BA_0628	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
694	BA_0694	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
698	BA_0698	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
69C	BA_069C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
6CC	BA_06CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
750	BA_0750	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
754	BA_0754	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
764	BA_0764	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
768	BA_0768	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-5. Summary of Sideband Registers (Lane 4 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
828	BA_0828	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
894	BA_0894	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
898	BA_0898	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
89C	BA_089C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
8CC	BA_08CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
950	BA_0950	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
954	BA_0954	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
964	BA_0964	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
968	BA_0968	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-6. Summary of Sideband Registers (Lane 5 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
A28	BA_0A28	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
A94	BA_0A94	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
A98	BA_0A98	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
A9C	BA_0A9C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
ACC	BA_0ACC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
B50	BA_0B50	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
B54	BA_0B54	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
B64	BA_0B64	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
B68	BA_0B68	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-7. Summary of Sideband Registers (Lane 6 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
C28	BA_0C28	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
C94	BA_0C94	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
C98	BA_0C98	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
C9C	BA_0C9C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
CCC	BA_0CCC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
D50	BA_0D50	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
D54	BA_0D54	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
D64	BA_0D64	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
D68	BA_0D68	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-8. Summary of Sideband Registers (Lane 7 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
E28	BA_0E28	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
E94	BA_0E94	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
E98	BA_0E98	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
E9C	BA_0E9C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
ECC	BA_0ECC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
F50	BA_0F50	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
F54	BA_0F54	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
F64	BA_0F64	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
F68	BA_0F68	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-9. Summary of Sideband Registers (Lane 8 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1028	BA_1028	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1094	BA_1094	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1098	BA_1098	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
109C	BA_109C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
10CC	BA_10CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1150	BA_1150	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1154	BA_1154	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1164	BA_1164	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1168	BA_1168	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-10. Summary of Sideband Registers (Lane 9 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1228	BA_1228	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1294	BA_1294	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1298	BA_1298	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
129C	BA_129C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
12CC	BA_12CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1350	BA_1350	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1354	BA_1354	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1364	BA_1364	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1368	BA_1368	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-11. Summary of Sideband Registers (Lane 10 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1428	BA_1428	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1494	BA_1494	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1498	BA_1498	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
149C	BA_149C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
14CC	BA_14CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1550	BA_1550	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1554	BA_1554	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1564	BA_1564	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1568	BA_1568	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-12. Summary of Sideband Registers (Lane 11 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1628	BA_1628	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1694	BA_1694	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1698	BA_1698	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
169C	BA_169C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
16CC	BA_16CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1750	BA_1750	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1754	BA_1754	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1764	BA_1764	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1768	BA_1768	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-13. Summary of Sideband Registers (Lane 12 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1828	BA_1828	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1894	BA_1894	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1898	BA_1898	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
189C	BA_189C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
18CC	BA_18CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1950	BA_1950	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1954	BA_1954	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1964	BA_1964	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1968	BA_1968	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-14. Summary of Sideband Registers (Lane 13 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1A28	BA_1A28	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1A94	BA_1A94	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1A98	BA_1A98	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
1A9C	BA_1A9C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
1ACC	BA_1ACC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1B50	BA_1B50	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1B54	BA_1B54	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1B64	BA_1B64	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1B68	BA_1B68	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-15. Summary of Sideband Registers (Lane 14 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1C28	BA_1C28	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1C94	BA_1C94	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1C98	BA_1C98	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
1C9C	BA_1C9C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
1CCC	BA_1CCC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1D50	BA_1D50	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1D54	BA_1D54	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1D64	BA_1D64	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1D68	BA_1D68	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-16. Summary of Sideband Registers (Lane 15 of 19) — 0xBA

Offset from Sideband Port BAh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
1E28	BA_1E28	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
1E94	BA_1E94	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
1E98	BA_1E98	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
1E9C	BA_1E9C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
1ECC	BA_1ECC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
1F50	BA_1F50	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
1F54	BA_1F54	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
1F64	BA_1F64	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
1F68	BA_1F68	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-17. Summary of Sideband Registers (Lane 16 of 19) — 0xBB

Offset from Sideband Port BBh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
2028	BB_2028	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
2094	BB_2094	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
2098	BB_2098	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
209C	BB_209C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
20CC	BB_20CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
2150	BB_2150	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
2154	BB_2154	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
2164	BB_2164	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
2168	BB_2168	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-18. Summary of Sideband Registers (Lane 17 of 19) — 0xBB

Offset from Sideband Port BBh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
2228	BB_2228	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
2294	BB_2294	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
2298	BB_2298	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
229C	BB_229C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
22CC	BB_22CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
2350	BB_2350	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
2354	BB_2354	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
2364	BB_2364	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
2368	BB_2368	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-19. Summary of Sideband Registers (Lane 18 of 19) — 0xBB

Offset from Sideband Port BBh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
2428	BB_2428	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
2494	BB_2494	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
2498	BB_2498	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
249C	BB_249C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
24CC	BB_24CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
2550	BB_2550	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
2554	BB_2554	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
2564	BB_2564	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
2568	BB_2568	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

Table 68-20. Summary of Sideband Registers (Lane 19 of 19) — 0xBB

Offset from Sideband Port BBh (hex)	Memory-Mapped I/O offset from SBREG_BAR (hex)	Default Value (hex)	Register Name (Register Symbol)
2628	BB_2628	01020180	"PCS_DWORD10 (pcs_dword10)—Offset 28h" on page 3788
2694	BB_2694	28292A00	"TX_DWORD5 (tx_dword5)—Offset 94h" on page 3789
2698	BB_2698	151F2020	"TX_DWORD6 (tx_dword6)—Offset 98h" on page 3790
269C	BB_269C	022A0000	"TX_DWORD7 (tx_dword7)—Offset 9Ch" on page 3791
26CC	BB_26CC	201F0000	"TX_DWORD19 (tx_dword19)—Offset CCh" on page 3792
2750	BB_2750	003F3F3F	"RX_DWORD20 (rx_dword20)—Offset 150h" on page 3792
2754	BB_2754	80C00000	"RX_DWORD21 (rx_dword21)—Offset 154h" on page 3793
2764	BB_2764	00005400	"RX_DWORD25 (rx_dword25)—Offset 164h" on page 3794
2768	BB_2768	B800822A	"RX_DWORD26 (rx_dword26)—Offset 168h" on page 3794

68.2 Sideband Registers

The Sideband registers accessible to the Host are described here. They are accessible in Host Memory Space starting at the Sideband Base Address Register (SBREG_BAR). See Section 3.4.1, "Using SBREG_BAR Method".

68.2.1 PCS_DWORD10 (pcs_dword10)—Offset 28h

PCS_DWORD10 for HSIO Lane 0 is shown here. This register description applies to the PCS_DWORD10 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 28h
Host Memory Space: SBREG_BAR + 0xBA0000 + 28h

Default: 01020180

Bit Range	Default & Access	Field Name (ID): Description
31:7	0x0 RO	**Reserved**
6:5	0x0 RW	**reg_cfg_data_dynclkgate_mode_1_0:** • 00 - Susclk gating and laneclkreq disabled • 01 - Reserved • 10 - Reserved • 11 - Susclk gating enabled and laneclkreq enabled
4:0	0x0 RO	**Reserved**

68.2.2 TX_DWORD5 (tx_dword5)—Offset 94h

TX_DWORD5 for HSIO Lane 0 is shown here. This register description applies to the TX_DWORD5 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 94h
Host Memory Space: SBREG_BAR + 0xBA0000 + 94h

Default: 28292A00h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RO	**Reserved**
21:16	0x29 RW	**ow2tapgen2deemph3p5_5_0:** Tx De-emphasis -3.5dB Setting for Rate1. When Tx is operating in 2-Tap mode, these bits define the 3.5dB de-emphasis setting, i.e. factor (X/64) of slices to use in main-R1. These bits are valid only when rate=2'b01 (typically gen2).
15:14	0x0 RO	**Reserved**
13:8	0x2a RW	**ow2tapgen1deemph3p5_5_0:** Tx De-emphasis -3.5dB Setting for Rate0. When Tx is operating in 2-Tap mode, these bits define the 3.5dB de-emphasis setting, i.e. factor (X/64) of slices to use in main-R1. These bits are valid only when rate=2'b00 (typically gen1).
7:0	0x0 RO	**Reserved**

68.2.3 TX_DWORD6 (tx_dword6)—Offset 98h

TX_DWORD6 for HSIO Lane 0 is shown here. This register description applies to the TX_DWORD6 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 98h
Host Memory Space: SBREG_BAR + 0xBA0000 + 98h

Default: 151F2020h

Bit Range	Default & Access	Field Name (ID): Description
31:22	0x0 RO	**Reserved**
21:16	0x1f RW	**ow2tapgen3deemph6p0_5_0:** Tx De-emphasis -6.0dB Setting for Rate2. When Tx is operating in 2-Tap mode, these bits define the 6.0dB de-emphasis setting, i.e. factor (X/64) of slices to use in main-R1. These bits are valid only when rate=2'b10 (typically gen3).
15:14	0x0 RO	**Reserved**
13:8	0x20 RW	**ow2tapgen2deemph6p0_5_0:** Tx De-emphasis -6.0dB Setting for Rate1. When Tx is operating in 2-Tap mode, these bits define the 6.0dB de-emphasis setting, i.e. factor (X/64) of slices to use in main-R1. These bits are valid only when rate=2'b01 (typically gen2).
7:0	0x0 RO	**Reserved**

68.2.4 TX_DWORD7 (tx_dword7)—Offset 9Ch

TX_DWORD7 for HSIO Lane 0 is shown here. This register description applies to the TX_DWORD7 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 9Ch
Host Memory Space: SBREG_BAR + 0xBA0000 + 9Ch

Default: 022A0000h

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved**
29:24	0x20	**Omargom011_5_0:** Tx Margin011 factor (X/64) of slices to use for full swing level.
23:22	0x0 RO	**Reserved**
21:16	0x2A	**Omargom010_5_0:** Tx Margin010 factor (X/64) of slices to use for full swing level.
15:14	0x0 RO	**Reserved**
13:8	0x0	**Omargom001_5_0:** Tx Margin001 factor (X/64) of slices to use for full swing level.
7:6	0x0 RO	**Reserved**
5:0	0x0	**Omargom000_5_0:** Tx Margin000 factor (x/64) of slices to use for full swing level.

68.2.5 TX_DWORD19 (tx_dword19)—Offset CCh

TX_DWORD19 for HSIO Lane 0 is shown here. This register description applies to the TX_DWORD19 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + CCh
Host Memory Space: SBREG_BAR + 0xBA0000 + CCh

Default: 201F0000h

Bit Range	Default & Access	Field Name (ID): Description
31:1	0x0 RO	**Reserved**
0	0x0 RW	**o_calccont:** initiate calculation of swing-control while '1' the calculation is done consecutively.

68.2.6 RX_DWORD20 (rx_dword20)—Offset 150h

RX_DWORD20 for HSIO Lane 0 is shown here. This register description applies to the RX_DWORD20 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 150h
Host Memory Space: SBREG_BAR + 0xBA0000 + 150h

Default: 003F3F3Fh

Bit Range	Default & Access	Field Name (ID): Description
31:30	0x0 RO	**Reserved**
29:24	0x0 RW	**icfgctledatatap_fullrate_5_0:** FULL rate CTLE Tap Co-efficients override in non-adaptive system.
23:0	0x0 RO	**Reserved**

68.2.7 RX_DWORD21 (rx_dword21)—Offset 154h

RX_DWORD21 for HSIO Lane 0 is shown here. This register description applies to the RX_DWORD21 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 154h
Host Memory Space: SBREG_BAR + 0xBA0000 + 154h

Default: 80C00000h

Bit Range	Default & Access	Field Name (ID): Description
31:14	0x0 RO	**Reserved**
13:8	0x0 RW	**icfgctledatatap_quatrate_5_0:** QUARTER rate CTLE Tap Co-efficients override in non-adaptive system.
7:4	0x0 RO	**Reserved**
5:0	0x0 RW	**icfgctledatatap_halfrate_5_0:** HALF rate CTLE Tap Co-efficients override in non-adaptive system.

68.2.8 RX_DWORD25 (rx_dword25)—Offset 164h

RX_DWORD25 for HSIO Lane 0 is shown here. This register description applies to the RX_DWORD25 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 164h
Host Memory Space: SBREG_BAR + 0xBA0000 + 164h

Default: 00005400h

Bit Range	Default & Access	Field Name (ID): Description
31:21	0x0 RO	**Reserved**
20:16	0x0 RW	**ctle_adapt_offset_cfg_4_0:** The 2s complement value to be added to the CTLE coefficient after its training.
15:0	0x0 RO	**Reserved**

68.2.9 RX_DWORD26 (rx_dword26)—Offset 168h

RX_DWORD26 for HSIO Lane 0 is shown here. This register description applies to the RX_DWORD26 for other 19 HSIO Lanes. See Table 68-2, "Summary of Sideband Registers (Lane 1 of 19) — 0xBA" through Table 68-20, "Summary of Sideband Registers (Lane 19 of 19) — 0xBB" for the applicable Sideband Ports and offset values.

Type: Sideband Register
(Size: 32 bits)

Sideband Port and Offset: 0xBA + 168h
Host Memory Space: SBREG_BAR + 0xBA0000 + 168h

Default: B800822Ah

Bit Range	Default & Access	Field Name (ID): Description
31:17	0x0 RO	**Reserved**
16	0x0 RW	**sata_eq_dis:** chicken bit disable SATA3 doing equation by default. • 1: disable eq • 0: run eq
15:0	0x0 RO	**Reserved**

§ §

69 Model-Specific Registers (MSR)

69.1 Introduction and Index

The host-accessible registers for the Model-Specific Registers (MSR) are described here.

To determine the number of processor cores, L2 Cache units, and Memory Controllers refer to the following:

- Table 1-1, “Features by product SKU - Server and Cloud Storage SKUs 0 through 4”
- Table 1-2, “Features by Product SKU - Network and Enterprise Storage SKUs 5 through 10”
- Table 1-3, “Features by Product SKU - Extended Temperature SKUs 11 through 14”

The legend for the register access codes are described in Chapter 43, “Introduction.”

Table 69-1. Model Specific Register (MSR) Index (Sheet 1 of 5)

MSR Address	MSR Name
006h	(006h) IA32_MONITOR_FILTER_SIZE on page 3801
017h	(017h) IA32_PLATFORM_ID on page 3802
01Bh	(01Bh) IA32_APIC_BASE on page 3802
02Eh	(02Eh) MSR_PIC_MSG_CONTROL on page 3803
033h	(033h) MSR_MEMORY_CONTROL on page 3803
034h	(034h) MSR_SMI_COUNT on page 3803
035h	(035h) CORE_THREAD_COUNT on page 3804
039h	(039h) MSR_THREAD_ID on page 3804
03Bh	(03Bh) IA32_TSC_ADJUST on page 3804
04Eh	(04Eh) MSR_PPIN_CTL on page 3805
04Fh	(04Fh) MSR_PPIN on page 3805
052h	(052h) SMM_MCA_CONTROL on page 3805
079h	(079h) IA32_BIOS_UPDT_TRIG on page 3806
07Ah	(07Ah) MSR_SGX_FEATURE_ACTIVATION on page 3806
08Bh	(08Bh) IA32_BIOS_SIGN_ID on page 3806
09Bh	(09Bh) IA32_SMM_MONITOR_CTL on page 3806
09Eh	(09Eh) IA32_SMBASE on page 3807
0C1h	(0C1h) IA32_PMC0 on page 3807
0C2h	(0C2h) IA32_PMC1 on page 3807
0C3h	(0C3h) IA32_PMC2 on page 3807
0C4h	(0C4h) IA32_PMC3 on page 3807
0CEh	(0CEh) MSR_PLATFORM_INFO on page 3808
0E2h	(0E2h) MSR_PKG_CST_CONFIG_CONTROL on page 3810
0E4h	(0E4h) MSR_PMG_IO_CAPTURE_BASE on page 3811
0E7h	(0E7h) IA32_MPERF on page 3811
0E8h	(0E8h) IA32_APERF on page 3811
0FEh	(0FEh) IA32_MTRRCAP on page 3812
120h	(120h) POWER_MISC on page 3812
121h	(121h) EMULATE_PM_TMR on page 3813
139h	(139h) INITIAL_BOOT_BLOCK_COMPLETE on page 3813
13Ch	(13Ch) FEATURE_CONFIG on page 3813
140h	(140h) FEATURE_ENABLES on page 3814
15Ch	(15Ch) PERMEM_CONFIG_INFO on page 3814
15Dh	(15Dh) PERMEM_CTRLR_INDEX on page 3814
15Eh	(15Eh) PERMEM_CTRLR_ID on page 3814
174h	(174h) IA32_SYSENTER_CS on page 3815
175h	(175h) IA32_SYSENTER_ESP on page 3815
176h	(176h) IA32_SYSENTER_EIP on page 3815
179h	(179h) IA32_MCG_CAP on page 3816

Table 69-1. Model Specific Register (MSR) Index (Sheet 2 of 5)

MSR Address	MSR Name
17Ah	(17Ah) IA32_MCG_STATUS on page 3816
17Dh	(17Dh) MSR_SMM_MCA_CAP on page 3817
17Fh	(17Fh) MSR_ERROR_CONTROL on page 3817
186h	(186h) IA32_PERFEVTSEL0 on page 3818
187h	(187h) IA32_PERFEVTSEL1 on page 3818
188h	(188h) IA32_PERFEVTSEL2 on page 3818
189h	(189h) IA32_PERFEVTSEL3 on page 3819
198h	(198h) IA32_PERF_STATUS on page 3819
199h	(199h) IA32_PERF_CTL on page 3819
19Ah	(19Ah) IA32_CLOCK_MODULATION on page 3820
19Bh	(19Bh) IA32_THERM_INTERRUPT on page 3820
19Ch	(19Ch) IA32_THERM_STATUS on page 3821
19Dh	(19Dh) MSR_THERM2_CTL on page 3822
1A0h	(1A0h) IA32_MISC_ENABLE on page 3823
1A1h	(1A1h) PACKAGE_THERM_MARGINBD on page 3824
1A2h	(1A2h) MSR_TEMPERATURE_TARGET on page 3824
1A4h	(1A4h) MSR_MISC_FEATURE_CONTROL on page 3824
1A6h	(1A6h) MSR_OFFCORE_RSP_0 on page 3825
1A7h	(1A7h) MSR_OFFCORE_RSP_1 on page 3825
1A8h	(1A8h) THREAD_SW_DEFEATURE on page 3825
1AAh	(1AAh) MSR_MISC_PWR_MGMT on page 3825
1ADh	(1ADh) MSR_TURBO_RATIO_LIMIT on page 3826
1AEh	(1AEh) MSR_TURBO_RATIO_LIMIT1 on page 3826
1B0h	(1B0h) IA32_ENERGY_PERF_BIAS on page 3826
1B1h	(1B1h) IA32_PACKAGE_THERM_STATUS on page 3827
1B2h	(1B2h) IA32_PACKAGE_THERM_INTERRUPT on page 3828
1C6h	(1C6h) DEBUG_RESOURCE_STATUS on page 3828
1C8h	(1C8h) MSR_LBR_SELECT on page 3829
1C9h	(1C9h) MSR_LASTBRANCH_TOS on page 3829
1D9h	(1D9h) IA32_DEBUGCTL on page 3830
1E3h	(1E3h) DEBUG_ERR_INJ_CTL on page 3830
1E4h	(1E4h) DEBUG_ERR_INJ_CTL2 on page 3831
1E6h	(1E6h) PIC_DEBUG_MODES on page 3832
1F0h	(1F0h) VLW_CAPABILITY on page 3834
1FCh	(1FCh) MSR_POWER_CTL on page 3835
281h	(281h) IA32_MC1_CTL2 (L2 Cache) on page 3836
282h	(282h) IA32_MC2_CTL2 (FEC) on page 3836
283h	(283h) IA32_MC3_CTL2 (MEC) on page 3836
284h	(284h) IA32_MC4_CTL2 (SA) on page 3836
285h	(285h) IA32_MC5_CTL2 (PMU) on page 3837

Table 69-1. Model Specific Register (MSR) Index (Sheet 3 of 5)

MSR Address	MSR Name
286h	(286h) IA32_MC6_CTL2 (SA) on page 3837
287h	(287h) IA32_MC7_CTL2 (MEM 0) on page 3837
288h	(288h) IA32_MC8_CTL2 (MEM 1) on page 3838
2E0h	(2E0h) NO_EVICT_MODE on page 3838
2FFh	(2FFh) IA32_MTRR_DEF_TYPE on page 3838
300h	(300h) MSR_SGXOWNER0 on page 3839
301h	(301h) MSR_SGXOWNER1 on page 3839
309h	(309h) IA32_FIXED_CTR0 on page 3839
30Ah	(30Ah) IA32_FIXED_CTR1 on page 3839
30Bh	(30Bh) IA32_FIXED_CTR2 on page 3839
345h	(345h) IA32_PERF_CAPABILITIES on page 3840
38Dh	(38Dh) IA32_FIXED_CTR_CTRL on page 3840
38Eh	(38Eh) IA32_PERF_GLOBAL_STATUS on page 3841
38Fh	(38Fh) IA32_PERF_GLOBAL_CTRL on page 3842
390h	(390h) IA32_PERF_GLOBAL_STATUS_RESET on page 3843
391h	(391h) IA32_PERF_GLOBAL_STATUS_SET on page 3844
392h	(392h) IA32_PERF_GLOBAL_INUSE on page 3844
3F1h	(3F1h) IA32_PEBS_ENABLE on page 3845
3F8h	(3F8h) MSR_PKG_C3_RESIDENCY on page 3845
3F9h	(3F9h) MSR_PKG_C6_RESIDENCY on page 3845
3FCh	(3FCh) MSR_CORE_C3_RESIDENCY on page 3845
3FDh	(3FDh) MSR_CORE_C6_RESIDENCY on page 3846
3FEh	(3FEh) MSR_CORE_C7_RESIDENCY on page 3846
400h	(400h) IA32_MC0_CTL (BIU) on page 3846
401h	(401h) IA32_MC0_STATUS on page 3847
402h	(402h) IA32_MC0_ADDR (BIU) on page 3848
404h	(404h) IA32_MC1_CTL (L2 Cache) on page 3848
405h	(405h) IA32_MC1_STATUS (L2 Cache) on page 3849
406h	(406h) IA32_MC1_ADDR (L2 Cache) on page 3851
408h	(408h) IA32_MC2_CTL (FEC) on page 3851
409h	(409h) IA32_MC2_STATUS (FEC) on page 3852
40Ah	(40Ah) IA32_MC2_ADDR (FEC) on page 3854
40Ch	(40Ch) IA32_MC3_CTL (MEC) on page 3854
40Dh	(40Dh) IA32_MC3_STATUS (MEC) on page 3855
40Eh	(40Eh) IA32_MC3_ADDR (MEC) on page 3855
410h	(410h) IA32_MC4_CTL (SA) on page 3856
411h	(411h) IA32_MC4_STATUS (SA) on page 3858
412h	(412h) IA32_MC4_ADDR (SA) on page 3860
413h	(413h) IA32_MC4_MISC (SA) on page 3860
414h	(414h) IA32_MC5_CTL (PMU) on page 3861

Table 69-1. Model Specific Register (MSR) Index (Sheet 4 of 5)

MSR Address	MSR Name
415h	(415h) IA32_MC5_STATUS (PMU) on page 3863
416h	(416h) IA32_MC5_ADDR (PMU) on page 3864
417h	(417h) IA32_MC5_MISC (PMU) on page 3864
418h	(418h) IA32_MC6_CTL (SA) on page 3865
419h	(419h) IA32_MC6_STATUS (SA) on page 3867
41Ah	(41Ah) IA32_MC6_ADDR (SA) on page 3867
41Ch	(41Ch) IA32_MC7_CTL (MEM 0) on page 3868
41Dh	(41Dh) IA32_MC7_STATUS (MEM 0) on page 3870
41Fh	(41Fh) IA32_MC7_MISC (MEM 0) on page 3871
420h	(420h) IA32_MC8_CTL (MEM 1) on page 3872
421h	(421h) IA32_MC8_STATUS (MEM 1) on page 3874
423h	(423h) IA32_MC8_MISC (MEM 1) on page 3874
4C1h	(4C1h) IA32_A_PMC0 on page 3874
4C2h	(4C2h) IA32_A_PMC1 on page 3875
4C3h	(4C3h) IA32_A_PMC2 on page 3875
4C4h	(4C4h) IA32_A_PMC3 on page 3875
4E0h	(4E0h) MSR_SMM_FEATURE_CONTROL on page 3875
4E2h	(4E2h) MSR_SMM_DELAYED on page 3876
4E3h	(4E3h) MSR_SMM_BLOCKED on page 3876
500h	(500h) IA32_SGX_SVN_STATUS on page 3876
503h	(503h) MSR_SGX_DEBUG_MODE on page 3877
560h	(560h) IA32_RTIT_OUTPUT_BASE on page 3877
561h	(561h) IA32_RTIT_OUTPUT_MASK_PTRS on page 3877
570h	(570h) IA32_RTIT_CTL on page 3878
571h	(571h) ARR_CR_RTIT_STATUSIA32_RTIT_STATUS on page 3878
572h	(572h) IA32_RTIT_CR3_MATCH on page 3878
580h	(580h) IA32_RTIT_ADDR0_A on page 3878
581h	(581h) IA32_RTIT_ADDR0_B on page 3879
582h	(582h) IA32_RTIT_ADDR1_A on page 3879
583h	(583h) IA32_RTIT_ADDR1_B on page 3879
600h	(600h) IA32_DS_AREA on page 3879
601h	(601h) MSR_VR_CURRENT_CONFIG on page 3880
603h	(603h) MSR_VR_MISC_CONFIG on page 3880
606h	(606h) MSR_RAPL_POWER_UNIT on page 3881
610h	(610h) MSR_PKG_POWER_LIMIT on page 3882
614h	(614h) MSR_PKG_POWER_INFO on page 3884
615h	(615h) PPL3_CONTROL on page 3884
618h	(618h) MSR_DRAM_POWER_LIMIT on page 3885
61Ch	(61Ch) MSR_DRAM_POWER_INFO on page 3886
633h	(633h) MSR_PKGC_IRTL3 on page 3887

Table 69-1. Model Specific Register (MSR) Index (Sheet 5 of 5)

MSR Address	MSR Name
634h	(634h) MSR_PKGC_IRTL4 on page 3887
635h	(635h) MSR_PKGC_IRTL5 on page 3888
639h	(639h) MSR_PP0_ENERGY_STATUS on page 3888
641h	(641h) MSR_PP1_ENERGY_STATUS on page 3889
64Ch	(64Ch) MSR_TURBO_ACTIVATION_RATIO on page 3889
64Fh	(64Fh) MSR_CORE_PERF_LIMIT_REASONS on page 3890
80Fh	(80Fh) IA32_X2APIC_SIVR on page 3891
828h	(828h) IA32_X2APIC_ESR on page 3891
82Fh	(82Fh) IA32_X2APIC_LVT_CMCI on page 3892
830h	(830h) IA32_X2APIC_ICR on page 3893
832h	(832h) IA32_X2APIC_LVT_TIMER on page 3894
833h	(833h) IA32_X2APIC_LVT_THERMAL on page 3895
834h	(834h) IA32_X2APIC_LVT_PMI on page 3895
835h	(835h) IA32_X2APIC_LVT_LINT0 on page 3896
836h	(836h) IA32_X2APIC_LVT_LINT1 on page 3897
837h	(837h) IA32_X2APIC_LVT_ERROR on page 3897
838h	(838h) IA32_X2APIC_INIT_COUNT on page 3898
839h	(839h) IA32_X2APIC_CUR_COUNT on page 3898
83Eh	(83Eh) IA32_X2APIC_DIV_CONF on page 3898
83Fh	(83Fh) IA32_X2APIC_SELF_IPI on page 3898
C80h	(C80h) IA32_DEBUG_FEATURE on page 3899
C8Fh	(C8Fh) IA32_PQR_ASSOC on page 3899
D10h	(D10h) IA32_L2_QOS_MASK_0 on page 3899
D11h	(D11h) IA32_L2_QOS_MASK_1 on page 3900
D12h	(D12h) IA32_L2_QOS_MASK_2 on page 3900
D13h	(D13h) IA32_L2_QOS_MASK_3 on page 3900
D90h	(D90h) IA32_BNDCFGS on page 3901
DA0h	(DA0h) IA32_XSS on page 3901
C0000080h	(C0000080h) IA32_EFER on page 3901
C0000081h	(C0000081h) IA32_STAR on page 3902
C0000082h	(C0000082h) IA32_LSTAR on page 3902
C0000083h	(C0000083h) IA32_CSTAR on page 3902
C0000084h	(C0000084h) IA32_FMASK on page 3902
C0000100h	(C0000100h) IA32_FS_BASE on page 3903
C0000101h	(C0000101h) IA32_GS_BASE on page 3903
C0000102h	(C0000102h) IA32_KERNEL_GS_BASE on page 3903
C0000103h	(C0000103h) IA32_TSC_AUX on page 3903

69.2 Model Specific Registers (MSRs)

69.2.1 (006h) IA32_MONITOR_FILTER_SIZE

OS or BIOS can program to the maximum line size in the system. CPUID will return the maximum line size of the processor and the system for the purposes of Monitor and MWait. Software can use this information to pad data appropriately to avoid cross-cluster hot-spots.

MSR Address: 006h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:16	Thread	0h	RW	Reserved.
15:0	Thread	0h	RW	**FILTER_MAXIMUM_LINE_SIZE —** OS or BIOS can program to the maximum line size in the system. CPUID will return the maximum line size of the processor and the system for the purposes of Monitor and MWait. Software can use this information to pad data appropriately to avoid cross-cluster hot-spots.

69.2.2 (017h) IA32_PLATFORM_ID

Used for selecting which patch to use. Indicates the platform that the processor is intended for. This MSR is used for microcode update loading purpose only. For all other device identification purposes it is recommended that System BIOS use PCI based Device Identification register.

MSR Address: 17h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:53	Package	0h	RSV	Reserved.
52:50	Package	0h	RW	**PLATFORM_ID —** This field is loaded from SoC fuses.
49:0	Package	0h	RSV	Reserved.

69.2.3 (01Bh) IA32_APIC_BASE

Register used to implement the APICBASE MSR. Contains the base address for all the APIC registers along with certain APIC control and state bits. The xAPIC Base Register holds the APIC base address, permitting the relocation of the APIC memory map.

MSR Address: 01Bh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:40	Thread	0h	Rsvd0	Reserved.
39:12	Thread	0h	RW	**APIC_BASE —** Bits 39:12 of the physical APIC register base address. WRMSR will GP fault on writes of 1 to 35:32 for PA32 parts.
11	Thread	0h	RW	**APEN —** APIC enable bit. If bit is 0, then the SoC APIC is disabled. If the bit is 1, then APIC is enabled.
10	Thread	0h	RW	**EXTENDED_MODE_ENABLE —** Enable/Disable for APIC Extensions.
9	Thread	0h	Rsvd0	Reserved.
8	Thread	0h	RW	**BSP —** Bit used to indicate that the processor is the Boot Strap Processor (BSP). BIOS must clear this bit if the processor is not going to be the System BSP (SBSP).
7:0	Thread	0h	Rsvd0	Reserved.

69.2.4 (02Eh) MSR_PIC_MSG_CONTROL

MSR used to enable/disable TPR messages. See NHM-B bug 2425138. Controls APIC TPR Update messages from the processor's Local APIC. By default at reset, TPR Update messages are disabled so they are not queued up while not being serviced. However, it is the BIOS' responsibility to enable TPR Update messages before any Local APIC mode transitions occur.

MSR Address: 02Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:11	-	-	-	Reserved.
10	Module	0h	RO	**TPR_MSG_OFF —** Prevents all TPR / IntPrioUpd messages from being generated, including those generated from APIC ID/LogID/DFR writes and Enable changes. WRMSR only allows clearing of this bit. Any attempt to set it (if already clear) will be ignored.
9:0	-	-	-	Reserved.

69.2.5 (033h) MSR_MEMORY_CONTROL

DCU_TEST_CTL MSR. Ucode mirrors the appropriate split lock disable bit and this entry is used only to generate the proper address defines. This register is used to disable split locks, which are locked instructions that split a cache line.

MSR Address: 033h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Thread	0h	RW	**SPLIT_LOCK_DISABLE —** If set to 1, disables split locks. If clear to 0, enables split locks. Setting this bit will cause split locks to be non-atomic, despite the lock attribute of the instruction.
30:0	-	-	-	Reserved.

69.2.6 (034h) MSR_SMI_COUNT

SLM PerfMon:Number of times SMISystem Management Mode (SMM) was entered.

MSR Address: 034h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	0h	RW	Reserved.
31:0	Thread	0h	RO	**SMM_ENTRY_COUNT —** Holds a running count of SMI events since the last reset.

69.2.7 (035h) CORE_THREAD_COUNT

This MSR is shared in the processor package and used to determine the current count of enabled Cores and Threads. This register reflects the actual number of enabled Cores and Threads based on the factory configurations and BIOS modifications. The Core Count and ThreadCount fields reflect the enabled cores and threads based on the factory-configured core.

MSR Address: 035h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:16	Package	-	RO	**CORE_COUNT —** The Core Count reflects the enabled cores based on the factory-configured core count and the value of the RESOLVED_CORES_MASK register at reset time.
15:0	Package	-	RO	**THREAD_COUNT —** The Thread Count reflects the enabled threads based on the factory-configured thread count and the value of the RESOLVED_CORES_MASK register at reset time.

69.2.8 (039h) MSR_THREAD_ID

On P4, external software is allowed to set bits 31:5 to an arbitrary value to support clustered systems.

MSR Address: 039h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:8	Thread	0h	Rsvd0	**RESERVED —** reserved
7:0	Thread	0h	RW	**APIC_ID —** From the local APIC ID. Read only unless PIC debug mode is enabled.

69.2.9 (03Bh) IA32_TSC_ADJUST

UTSC_THREAD_OFFSET is Used to read the thread specific offset to Time Stamp counter base value in RDTSC computation. This helps in synchronizing between the cores for TSC calibration. This feature is available only when CPUID.(EAX=7):EBX[1] is 1.

MSR Address: 03Bh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**THREAD_OFFSET —** A read from this MSR would return the thread's offset to TSC base value, that is used in computing RDTSC return value. A write to this MSR would write only the thread's offset to the TSC value and not update the actual counter value.

69.2.10 (04Eh) MSR_PPIN_CTL

Protected Processor Inventory Number (PPIN) Enable Control The reset value is 0. It will not survive warm reset.

MSR Address: 04Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Package	0h	RW	**ENABLE —** Indication to SW about presence of PPIN 0 - PPIN not present. Read of PPIN MSR results in a #GP. 1 - PPIN present. Read of PPIN MSR by SW is allowed.
0	Package	0h	RW	**LOCK —** Bit indicates if PPIN_CTL is locked 0 - Not locked (SW free to write to PPIN_CTL). 1 - Locked (SW can no longer write to PPIN_CTL).

69.2.11 (04Fh) MSR_PPIN

MSR for PPIN feature. Access to MSR_PPIN is permitted only if MSR_PPIN_CTL[1:0]='10b'

MSR Address: 4Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Package	0h	RO	**VALUE —** The 64 bit inventory number.

69.2.12 (052h) SMM_MCA_CONTROL

Allows System Management mode (SMM) firmware to intercept Corrected and UCNA (Uncorrected, No Action) errors.

MSR Address: 052h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:10	-	-	-	Reserved.
9	Thread	0h	RW	**PEND_SMI_ON_MCA —** Pend SMI on MCA
8:2	-	-	-	Reserved.
1	Thread	0h	rsvd0	**UCNA_RD_STATUS_IN_SMM_ONLY —** The SoC design has no UCNA errors.
0	Thread	0h	RW	**CERR_RD_STATUS_IN_SMM_ONLY —** Only read valid correctable errors status when in SMM. Otherwise read 0 if V=1 and UC=0.

69.2.13 (079h) IA32_BIOS_UPDT_TRIG

Used to trigger the loading of the Microcode Update to the processor. Refer to the 'Microcode Update' section of the BIOS Writer's Guide for further information on the Microcode Update loading. Attempts to read this MSR will result in a GP fault. The IA32_BIOS_UPDT_TRIG register is not shared across cores in the same physical processor. BIOS must load the microcode update for each thread in a processor package.

MSR Address: 079h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	0h	WO	**DATA —** Any data write will cause the microcode update loader to get triggered.

69.2.14 (07Ah) MSR_SGX_FEATURE_ACTIVATION

MSR Address: 07Ah				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:1	-	-	-	Reserved.
0	Core	0h	RW	**SE —** Secure Enclaves Feature Activation

69.2.15 (08Bh) IA32_BIOS_SIGN_ID

Microcode Update Signature.

MSR Address: 08Bh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	0h	RW	**PATCH_SIGN_ID —** Microcode Update Signature.
31:0	Thread	0h	Rsvd0	Reserved.

69.2.16 (09Bh) IA32_SMM_MONITOR_CTL

This MSR is writeable only in System Management Mode (SMM), else the SoC generates #GP.

MSR Address: 09Bh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	0h	RW	Reserved.
31:12	Thread	0h	RW	**MSEG_BASE_PAGE_FRAME_ADR —** VMX MSEG base page frame address
11:3	Thread	0h	RW	Reserved.
2	Thread	0h	RW	**VMXOFFCTRL —** VMX Off Control. When this bit is set, VMXOFF will unmask SMI events.
1	Thread	0h	RW	**CSTATE_SMI_OPTIN —** C-state SMI VMX opt in. Can only be set by WRMSR if IA32_FEATURE_CONTROL_MSR.C_STATE_SMI and LOCK
0	Thread	0h	RW	**VALID —** When set, this bit indicates that the MSR contents are valid.

69.2.17 (09Eh) IA32_SMBASE

Read only MSR. WRMSR will always #GP. RDMSR will GP if not in SMM mode.

MSR Address: 09Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	-	-	-	**Reserved (RSVD) —** Reserved.
31:0	Thread	0h	RO	**DATA —** Register which contains the current SMM base value for the processor. The RESET event handler should set it to 0x00030000, which is the default value. When RSM executes, it reads the SMM base slot value in SMM memory and loads it into this register.

69.2.18 (0C1h) IA32_PMC0

Performance Counter Register 0. This register is available only if CPUID (EAX=0Ah):EAX[15:8] > 0.

MSR Address: 0C1h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	-	-	**DATA** — Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.19 (0C2h) IA32_PMC1

Performance Counter Register 1. This register is available only if CPUID (EAX=0Ah):EAX[15:8] > 1.

MSR Address: 0C2h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	-	-	**DATA** — Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.20 (0C3h) IA32_PMC2

Performance Counter Register 2. This register is available only if CPUID (EAX=0Ah):EAX[15:8] > 2.

MSR Address: 0C3h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	-	-	**DATA** — Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.21 (0C4h) IA32_PMC3

Performance Counter Register 3. This register is available only if CPUID (EAX=0Ah):EAX[15:8] > 3.

MSR Address: 0C4h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	-	-	**DATA** — Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.22 (0CEh) MSR_PLATFORM_INFO

This contains information about platforms frequency capabilities that the CPU reports.

MSR Address: CEh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:56	Package	0h	RO	Reserved.
55:48	Package	1h	RW	**MIN_OPERATING_RATIO —** Min supported ratio in units of 100MHz Confirm with Jeff
47:40	Package	0h	RW	**MAX_EFFICIENCY_RATIO —** Maximum Efficiency Ratio. This is given in units of 100 MHz.
39:38	Package	0h	RO	Reserved.
37	Package	0h	RW	**TIMED_MWAIT_ENABLE —** Timed MWAIT enable
36	Package	0h	RO	Reserved.
35	Package	0h	RW	**PFAT_ENABLE —** Platform Firmware Armoring Technology (PFAT). 0 indicates the PFAT feature is not available. 1indicates the PFAT feature is available.
34:33	Package	0h	RW	**CONFIG_TDP_LEVELS —** Configurable TDP. Indicates the number of configurable TDP levels supported. 00 - Config TDP not supported 01 - One additional TDP level supported 10 - Two additional TDP levels supported
32	Package	0h	RW	**LPM_SUPPORT** — Low Power Mode Support. When set to 1, indicates that BIOS may program IA32_PERF_CTL to levels below the max efficiency ratio down to Minimum Ratio bits [55:48]. 0 - Low Power mode not supported 1 - Low Power mode supported Determined by fuse.
31	Package	1h	RW	**CPUID_FAULTING_EN —** CPUID Faulting Capability. When set to 1 indicates that the processor supports raising a #GP if CPUID is executed when not in SMM and the CPL > 0. When this bit is set, it indicates that MSR 140h FEATURE_ENABLES bit 0 can be written by a VMM.
30	Package	1h	RW	**PRG_TJ_OFFSET_EN —** Programmable TCC Activation Offset. When set to 1, indicates that the TCC Activation Offset field in MSR_TEMPERATURE_TARGET is valid and programmable. When set to 0, indicates it's not programmable. When this bit is 0, an attempt to write to MSR_TEMPERATURE_TARGET bits [27:24] will result in a GP fault.
29	Package	1h	RW	**PRG_TDP_LIMIT_EN —** Programmable TDP Limits for Turbo Mode. When set to 1, indicates that TDP Limits for Turbo mode are programmable, and when set to 0, indicates TDP Limits for Turbo mode are not programmable. When this bit is 0, an attempt to write to PP0_POWER_LIMIT, PP1_POWER_LIMIT and PACKAGE_POWER_LIMIT MSR will result in a GP fault.
28	Package	1h	RW	**PRG_TURBO_RATIO_EN —** Programmable Ratio Limits for Turbo Mode. When set to 1, indicates Programmable Ratio Limits for Turbo Mode are enabled, and when set to 0, indicates Programmable Ratio Limits for Turbo Mode are disabled.
27	Package	0h	RW	**SAMPLE_PART —** Sample. A value of 1 indicates the processor is a preproduction sample and a property of Intel, a value of 0 indicates the part is intended for production.
26	Package	0h	RW	**DCU_16K_MODE_AVAIL —** DCU Mode Select Support. When set to 1. indicates that DCU Mode Selection is supported, and when set to 0, indicates that DCU Mode Selection is not available and the processor will remain in the default DCU mode.
25	Package	0h	RO	Reserved.
24	Package	0h	RW	**OCVOLT_OVRD_EN —** When set to 1, indicates that this part supports Voltage override overclocking. When this bit is 0 the processor does not support overclocking Voltage overrides.
23	Package	0h	RW	**PPIN_CAP —** When set to 1, indicates that Protected Processor Inventory Number (PPIN) feature is supported.
22:17	Package	0h	RO	Reserved.

MSR Address: CEh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
16	Package	1h	RO	**SMM_SAVE_CAP —** SMM Save Capability. When set to 1 indicates this feature exists.
15:8	Package	0h	RW	**MAX_NON_TURBO_LIM_RATIO —** Maximum Non Turbo Ratio. Contains the max non-turbo ratio. This is the ratio of the frequency that invariant TSC runs at. Frequency = ratio * 100 MHz. ***Note:*** The Maximum Non-Turbo Ratio is adjusted to the flexible limit ratio (as specified in the FLEX_RATIO MSR 194h FLEX_RATIO field bits [15:8]) if flexible limit is enabled (by setting the FLEX_RATIO MSR 194h FLEX_EN field bit[16]=1. In case of Configurable TDP feature, the maximum of the available TDP levels is reported in this field.
7:0	Package	0h	RO	Reserved.

69.2.23 (0E2h) MSR_PKG_CST_CONFIG_CONTROL

Power Management - C-states configuration. Note the presence of the LOCK bit (15). When set, locks bits 15-0 of this register for further writes, until the next reset occurs.

MSR Address: 0E2h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Core	-	-	Reserved.
31	Core	0h	RW	**TIMED_MWAIT_ENABLE —** When set, enables Timed MWAIT feature. When this bit is cleared, all MWAIT timer configurations issued as a part of MWAIT will raise a #GP exception.
30	Core	0h	RW	**ENPKGCUNDEMOTION —** Enable Package Cstate Un-Demotion. Its the enable to consider cases where demotion was the incorrect decision in determining Cstate depth.
29	Core	0h	RW	**ENPKGCAUTODEMOTION —** Enable Package Cstate Auto-Demotion. It enables use of history of past pkg Cstate depth and residence, as a factor in determining Cstate depth.
28	Core	0h	RW	**ENC1UNDEMOTION —** Enable Un-Demotion from Demoted C1.
27	Core	0h	RW	**ENC3UNDEMOTION —** Enable Un-Demotion from Demoted C3.
26	Core	0h	RW	**C1_STATE_AUTO_DEMOTION_ENABLE —** When set, SoC will conditionally demote C3/C6/C7 requests to C1 based on uncore auto-demote information.
25	Core	0h	RW	**C3_STATE_AUTO_DEMOTION_ENABLE —** When set, SoC will conditionally demote C6/C7 requests to C3 based on uncore auto-demote information.
24:16	Core	-	-	Reserved.
15	Core	0h	RW-O	**CST_CFG_LOCK —** When set, locks bits [15:0] of this register for further writes, until the next reset occurs.
14:11	Core	-	-	Reserved.
10	Core	0h	RW-L	**IO_MWAIT_REDIRECTION —** When set, will map I/O_read instructions sent to I/O registers at MSR_PMG_IO_CAPTURE_BASE[15:0] to MWAIT instructions.
9:8	Core	-	-	Reserved.
7:4	Core	0h	RW	**MAX_CORE_C_STATE —** The possible values are: 0000 - Reserved 0001 - C1 0010 - C3 0011 - C6
3:0	Core	0h	RW-L	**PACK_LIM —** Limits the resolved package Cstate to be less than or equal to the encoded state: • 0x0 = No Pkg States [Self-Refresh] • 0x1 = No S0Ix [L2 Voltage Reduction] • 0x2 = No Limit [Default] This field will also indirectly impact the possible module Cstate. A limit of C1 means that the module cannot leave C0, as C1 is a core-only Cstate. C3 and C6, will restrict the possible module Cstate to that respective value. If the state is unlimited or C7 and deeper, then the module can enter C7. The states C8, C9, and C10 and synonyms for S0i1, S0i2, and S0i3, respectively.

69.2.24 (0E4h) MSR_PMG_IO_CAPTURE_BASE

Power Management I/O base address for I/O trapping to C-states.

See http://biosbits.org.

MSR Address: 0E4h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:19	Core	-	-	Reserved.
18:16	Core	0h	RW	**CST_RANGE —** The I/O-port block size in which I/O-redirection will be executed (0-7). Should be programmed based on the number of LVLx registers existing in the SoC.
15:0	Core	0h	RW	**LVL2B —** The SoC compares I/O-read zone to this base address to determine if an MWAIT(C2/3/4) needs to be issued instead of the I/O-read. Should be programmed to the SoC Plevel_2 I/O address.

69.2.25 (0E7h) IA32_MPERF

Maximum Performance Frequency Clock Count register. IA32_MPERF and IA32_APERF MSRs do not have any meaning by themselves separately. Only IA32_APERF/ IA32_MPERF ratio is architectural.

MSR Address: 0E7h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**C0_MCNT —** C0 maximum-frequency clock count: Increments at maximum clock frequency (as allowed by the Resolved Ratio) when core is in C0. Cleared by a write to this field.

69.2.26 (0E8h) IA32_APERF

Actual Performance Frequency Clock Count register. IA32_MPERF and IA32_APERF MSRs do not have any meaning by themselves separately. Only IA32_APERF/ IA32_MPERF ratio is architectural.

MSR Address: 0E8h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**C0_ACNT —** C0 actual-frequency clock count: Accumulates core clock counts at the coordinated clock frequency when core is in C0. Cleared by a write to this field.

69.2.27 (0FEh) IA32_MTRRCAP

Read-only register containing MTRR feature identification for the processor. Should be used in conjunction with the CPUID[EDX] bit 12 to determine MTRR capabilities. This MSR is read only. The SoC generates #GP on any write.

MSR Address: 0FEh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:13	Core	-	-	Reserved.
12	Core	0h	RO	**PRMRR —** PRMRRs are supported: Reports 1 if PRMRR is fuse enabled.
11	Core	0h	RO	**SMRR —** SMRR: 1 indicates supported.
10	Core	0h	RO	**WRITE —** Write-Combining memory type supported if set.
9	Core	-	-	Reserved.
8	Core	0h	RO	**FIX —** Fixed range registers supported if set.
7:0	Core	0h	RO	**VCNT —** Number of variable range registers.

69.2.28 (120h) POWER_MISC

Miscellaneous power controls used for eHALT enables.

MSR Address: 120h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:9	-	-	-	Reserved.
8	Thread	0h	RW	**WBINVAL_DL1 —** Used by BIOS to flush DL1->L2.
7	-	-	-	Reserved.
6	Thread	0h	RW	**ENABLE_IA_UNTRUSTED_MODE —** Post boot, BIOS will set this boot to clear the default IA_Boot mode and enter IA Untrusted Mode.
5:4	-	-	-	Reserved.
3	Thread	0h	RW	**ENABLE_INDP_AUTOCM —** Enable Independent Pstate Auto Clock Modulation: Writing 1 to this bit will allow automatic clock modulation based on it's core specific requested ratio if requested ratio is lower than the resolved module ratio. This setting does not apply if requested ratio is lower than minimum ratio supported by core PLL.
2	Thread	0h	RW	**ENABLE_ULFM_AUTOCM —** Enable UltraLowFreqMode Auto Clock Modulation: Writing 1 to this bit will allow automatic clock modulation based on it's core specific requested ratio if the resolved module ratio equals the minimum ratio supported by core PLL.
1:0	-	-	-	Reserved.

69.2.29 (121h) EMULATE_PM_TMR

Emulate PM_TMR.

MSR Address: 121h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	0h	RW	**MULTIPLIER —** Constant programmed by BIOS to translate CTC to target frequency (14.31818/4).
31:17	-	-	-	Reserved.
16	Thread	0h	RW	**PM_TMR_BLK_VALID —** Indicates that the MSR has been programmed by BIOS, and thus enables internal emulation of the PM_TMR.
15:0	Thread	0h	RW	**PM_TMR_BLK_BASE —** Base I/O port address of the PM_TMR.

69.2.30 (139h) INITIAL_BOOT_BLOCK_COMPLETE

Write-only MSR. WRMSR causes #GP if SECURE_BOOT_CAPABILITY_ENABLE == 0.

MSR Address: 139h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:1	-	-	-	Reserved.
0	Thread	0h	WO	**BIOS_RDY_FOR_MISC_EVENTS —** WMRSR ignores writes of 0. A write of 1 will set CPU_BIOS_RDY_FOR_MISC_INTERRUPTS in SEC.

69.2.31 (13Ch) FEATURE_CONFIG

This MSR is visible only if CPUID.(EAX=01h):ECX[25]=1, which indicates the processor was manufactured with AES-NI enabled. Note that when AES-NI is disabled, a #UD exception will be raised if software attempts to execute one of the AES-NI instructions.

MSR Address: 13Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Core	0h	RW	**AESNI_DISABLE —** This bit disables Advanced Encryption Standard feature on this processor core. To disable AES, System BIOS must write 11b to this MSR. Writes of 00b, 01b or 10b to this MSR will result in AES enable. WRMSR will GP if the lock bit is set.
0	Core	0h	RW	**AESNI_LOCK —** 1 = Locked. When set, locks this MSR from being written, writes o this bit will result in GP(0) until an S5 reset occurs. BIOS must ensure this lock bit is set before boot to OS.

69.2.32 (140h) FEATURE_ENABLES

Miscellaneous enables for thread-specific features.

MSR Address: 140h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:1	-	-	-	Reserved.
0	Thread	0h	RW	**CPUID_GP_ON_CPL_GT_0 —** Causes CPUID to #GP if current privilege level (CPL) is greater than 0 and not in SMM. BIOS should not set this bit. This bit should only be configured by a VMM.

69.2.33 (15Ch) PERMEM_CONFIG_INFO

Specifies the maximum number of memory controllers on the platform capable of supporting memory persistence.

MSR Address: 15Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:8	-	-	-	Reserved.
7:0	Thread	0h	RO	**NUMBER_OF_PCOMMIT_ADDRESSES —** Maximum number of different PCOMMIT addresses.

69.2.34 (15Dh) PERMEM_CTRLR_INDEX

Index into the list of persistent memory addresses which is accessed when the PERMEM_CTRLR_ID MSR is read/written.

MSR Address: 15Dh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Thread	0h	RW	**LOCK —** When set, WRMSR to PERMEM_CTRL_ID will #GP. WRMSR to clear this bit outside SMM will #GP. That means that once locked, it can be unlocked only from SMM. This bit is cleared on reset.
62:2	-	-	-	Reserved.
1:0	Thread	0h	RW	**INDEX —** Can be programmed to any value in the range 0 to N-1 where N is the value reported in 7:0 of PERMEM_CONFIG_INFO. For the SoC, N=4, and so this is a 2-bit field to allow the remaining fields to be checked by the MSR pla.

69.2.35 (15Eh) PERMEM_CTRLR_ID

Specifies the maximum number of memory controllers on the platform capable of supporting memory persistence.

MSR Address: 15Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:40	-	-	-	Reserved.
39:6	Thread	0h	RW	**IDENTIFIER —** Value written to this field uniquely identifies a persistent memory controller, whose index is in PERMEM_CTRLR_INDEX. Unused indices must be programmed with a reserved value of 0.
5:0	-	-	-	Reserved.

69.2.36 (174h) IA32_SYSENTER_CS

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 174h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	-	-	-	Reserved.
31:0	Thread	0h	RW	**DATA —** To be defined in the Intel® 64 and IA-32 Architectures Software Developer's Manual.

69.2.37 (175h) IA32_SYSENTER_ESP

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 175h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**DATA —** To be defined in the Intel® 64 and IA-32 Architectures Software Developer's Manual.

69.2.38 (176h) IA32_SYSENTER_EIP

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 176h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**DATA —** To be defined in the Intel® 64 and IA-32 Architectures Software Developer's Manual.

69.2.39 (179h) IA32_MCG_CAP

MCA Capability Control Register. This MSR is read only. The SoC generates #GP on any write.

MSR Address: 179h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:24	-	-	-	Reserved.
23:16	Thread	0h	RO	**NUMBER_OF_EXTENDED_MACHINE_CHECK_REGISTERS —** Indicates the number of extended machine check state registers present on this processor.
15:12	-	-	-	Reserved.
11	Thread	0h	RO	**MCG_YELLOW_GREEN —** Indicates that this processor implements "yellow/ green" health reporting.
10	Thread	0h	RO	**MCB_CMCI_P —** Correct MC Error counting / signaling is supported.
9	Thread	0h	RO	**EXTENDED_MACHINE_CHECK_MSRS_SUPPORTED —** Indicates that this processor implements the extended machine check state registers found starting at MSR address 180H. The SoC does not implement these extended registers.
8	Thread	0h	RO	**IMCG_CTL_IS_PRESENT —** Indicates that this processor implements the IA32_MCG_CTL MSR. The SoC does not implement this MSR.
7:0	Thread	0h	RO	**NUMBER_OF_HARDWARE_REPORTING_BANKS_AVAILABLE —** Indicates the number of error-reporting banks available on this processor.

69.2.40 (17Ah) IA32_MCG_STATUS

The Machine Check Status register is used to determine the current state of the machine check architecture of the processor after an error has occurred.

MSR Address: 17Ah				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:3	-	-	-	Reserved.
2	Thread	0h	RW	**MCIP —** Machine Check In Progress. When set, indicates that a machine check has been generated. If a second machine check is detected while this bit is still set, the processor will enter a shutdown state. Software can write this bit, and should write it to 0 after processing a machine check exception.
1	Thread	0h	RW	**EIPV —** Error IP valid. When set, indicates that the instruction pointed to by the instruction pointer pushed on the stack when the machine check was generated is directly associated with the error.
0	Thread	0h	RW	**RIPV —** Restart IP valid. When set, indicates that the program execution can be restarted reliably at the instruction pointed to by the instruction pointer pushed on the stack when the machine check was generated. When cleared, the program cannot be reliably restarted.

69.2.41 (17Dh) MSR_SMM_MCA_CAP

This register is only accessible while in SMM. Attempting to read or write this register outside of SMM will cause a #GP exception to be raised. This register indicates support for enhanced SMM features. It also reports which Machine-Check banks support enhanced MCA.

MSR Address: 17Dh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:60	-	-	-	Reserved.
59	Thread	0h	SMM-RO	**LONG_FLOW_INDICATION —** Set to indicate SMM long flow indicator support.
58	Thread	0h	SMM-RO	**SMM_CODE_ACCESS_CHK —** Set to 1 if the SMM code access check feature is supported and the SMM_FEATURE_CONTROL register (MSR 4E0h) is supported.
57	Thread	0h	SMM-RO	**SMM_CPU_SVRSTR —** 0 for the SoC. Set to 1 if the SAVE/RESTORE feature is supported and the SMM_FEATURE_CONTROL register (MSR 4E0h) is supported.
56	Thread	0h	SMM-RO	**TARGETED_SMI —** 0 for the SoC. Set to 1 if the thread supports targeted SMI and the SMM_ENABLE register (MSR 4E1h) is supported.
55	Thread	0h	SMM-RO	**ERROR_SPOOFING —** 0 for the SoC. Set if Error Spoofing and Enhanced MCA are supported.
54	Thread	0h	SMM-RO	**SMM_PROT_MODE —** 0 for the SoC. Set if SMM Protected Mode is supported.
53:32	-	-	-	Reserved.
31:0	Thread	0h	SMM-RO	**BANK_SUPPORT —** ENHANCED_MCA only, so 0 for the SoC. One bit per bank. If bit is set, then the corresponding bank supports enhanced MCA.

69.2.42 (17Fh) MSR_ERROR_CONTROL

Error Control Register. This register allows BIOS to control certain error logging features and their behaviors on the processor.

A #GP Fault will occur when doing a read of this MSR and the ERROR_CONTROL MSR is not available.A non-architectural, package-scoped MSR intended for use by BIOS. The bit will be saved and restored in C7+ states. The reset value for the bit is 0. It will not survive warm reset.

MSR Address: 17Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:5	-	-	-	Reserved.
4	Package	0h	RW	**CMCI_DISABLE —** When set to 1, disables corrected machine check interrupt entirely, cleared upon each reset. BIOS may use this bit to disable CMCI. Typically useful if OEM offers BIOS based PFA (Predicted Failure Analysis) or "Health Monitoring" capability. BIOS will require error polling, e.g., periodic SMI. Must be set during the BIOS initialization. Once it is set: • Any read to IA32_MCG_CAP[10] bit will result in 0. Indicating that processor does not support CMCI. Any read to IA32_MCi_CTL2[30] bit will result in 0. Indicating that CMCI signaling is not available in machine check bank 'i'.Any write to it will result in no change (read-only).
3:0	-	-	-	Reserved.

69.2.43 (186h) IA32_PERFEVTSEL0

Performance Event Selection Register 0. This register is available only if CPUID. (EAX=0Ah):EAX[15:8] > 0

MSR Address: 186h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	-	-	-	Reserved.
31:24	Thread	0h	RW	**COUNT_MASK —** When CMASK is not zero, the corresponding performance counter increments each cycle if the event count is greater than or equal to the CMASK.
23	Thread	0h	RW	**INVERT_FLAG —** Invert the CMASK.
22	Thread	0h	RW	**ENABLE_FLAG —** When set, performance counting is enabled in the performance-monitoring counter; when clear, the counter is disabled.
21	Thread	0h	RW	**MYTHREAD_ALLTHREAD —** 0 = Count events associated with this logical processor 1 = Count event on any logical processor in that core, or for uncore events, any logical processor in the module.
20	Thread	0h	RW	**INT_APIC_ENABLE_FLAG —** When set, the processor generates an exception through its local APIC on counter overflow for this counter's thread.
19	Thread	0h	RW	**PIN_CONTROL_FLAG —** Enables pin control.
18	Thread	0h	RW	**EDGE_DETECT_FLAG —** Enables edge detection if set.
17	Thread	0h	RW	**OS_MODE_FLAG —** Counts while in privilege level is ring 0.
16	Thread	0h	RW	**USER_MODE_FLAG —** Counts while in privilege level is not ring 0.
15:8	Thread	0h	RW	**EVENT_MASK —** Further qualifies the event selected in the event select field.of cache states
7:0	Thread	0h	RW	**EVENT_ID —** Selects the event to be monitored

69.2.44 (187h) IA32_PERFEVTSEL1

Performance Event Selection Register 0. This register is available only if CPUID. (EAX=0Ah):EAX[15:8] > 1

MSR Address: 187h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**DATA —** Refer to the description of IA32_PERFEVTSEL0.

69.2.45 (188h) IA32_PERFEVTSEL2

Performance Event Selection Register 0. This register is available only if CPUID. (EAX=0Ah):EAX[15:8] > 2

MSR Address: 188h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**DATA —** Refer to the description of IA32_PERFEVTSEL0.

69.2.46 (189h) IA32_PERFEVTSEL3

Performance Event Selection Register 0. This register is available only if CPUID. (EAX=0Ah):EAX[15:8] > 3

MSR Address: 189h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**DATA —** Refer to the description of IA32_PERFEVTSEL0.

69.2.47 (198h) IA32_PERF_STATUS

Performance Status MSR.

MSR Address: 198h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	-	-	-	Reserved.
47:32	Module	0h	RO	**CORE_VOLTAGE —** Voltage in 3.13 format.
31:16	-	-	-	Reserved.
15:8	Module	0h	RO	**PLLRATIO —** Current performance State Value bits 15:8.Ratio of the core pll.
7:0	-	-	-	Reserved.

69.2.48 (199h) IA32_PERF_CTL

Performance Control MSR. SW makes request for a new Performance state (P-State) by writing this MSR.

MSR Address: 199h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:33	-	-	-	Reserved.
32	Thread	0h	RW	**TURBO_DISABLE —** 1 = Turbo Mode disabled, 0=Turbo Mode enabled. Note: This Turbo Mode Disable exists on each logical processor. Turbo Mode setting of a core does not impact Turbo Mode of the package. BIOS should not use this Turbo Mode Disable since it does not change the Turbo Mode feature flag. This Turbo Mode Disable is intended for OS use only.
31:16	-	-	-	Reserved.
15:8	Thread	0h	RW	**P_REQ —** Requested P-state ratio value for this logical processor.
7:0	-	-	-	Reserved.

69.2.49 (19Ah) IA32_CLOCK_MODULATION

Thread T-State Request

MSR Address: 19Ah				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:5	-	-	-	**Reserved (RSVD) —** Reserved.
4	Thread	0h	RW	**THROTTLE_ACTIVE —** Enables ondemand software controlled clock modulation when set disables softwarecontrolled clock modulation when clear.
3:0	Thread	0h	RW	**T_STATE_REQ —** Selects the ondemand clock modulation duty cycle. This field is only active when the ondemand clock modulation enable flag is set.

69.2.50 (19Bh) IA32_THERM_INTERRUPT

Intel® Thermal Monitor Interrupt Control Register for the digital thermometer. When any of the interrupt enables are set, SW must configure the interrupt type to be delivered. SW writes the Thermal Local Vector Table (TLVT) entry of the local APIC to specify the interrupt type to be delivered.

MSR Address: 19Bh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:25	-	-	-	Reserved.
24	Core	0h	RW	**SPARE_PWR_LIMIT_ENABLE —** Reserved for Power Limit Notification Enable.
23	Core	0h	RW	**THRESHOLD_2_INT_ENABLE —** Threshold 2 Interrupt Enable R/W. This bit allows the BIOS to enable the generation of an interrupt on the transition of threshold 2 in any direction. A value 0 default disables interrupts and a value 1 enables interrupts..
22:16	Core	0h	RW	**THRESHOLD_2_REL_TEMP —** Specifies temperature Threshold 2 value as an offset below TJ_{MAX} temperature. Compares against temperature reported value in the status register IA32_CR_THERM_STATUSDIG_TEMP_READOUT value.
15	Core	0h	RW	**THRESHOLD_1_INT_ENABLE —** Threshold 1 Interrupt Enable R/W. This bit allows the BIOS to enable the generation of an interrupt on the transition of threshold 1 in any direction. A value 0 default disables interrupts and a value 1 enables interrupts.
14:8	Core	0h	RW	**THRESHOLD_1_REL_TEMP —** Specifies temperature Threshold 1 value as an offset below TJ_{MAX} temperature. Compares against temperature reported value in the status register IA32_CR_THERM_STATUSDIG_TEMP_READOUT value.
7:5	-	-	-	Reserved.
4	Core	0h	RW	**OUT_OF_SPEC_INT_ENABLE —** This bit allows the BIOS to enable the generation of an interrupt on the transition to the OutofSpec condition. The OutofSpec temperature is specified as an offset from TJ_{MAX} in CPU_THERM_CFG1OUT_OF_SPEC_THRESHOLD..If OVERHEAT_OFF_FUSE will ignore OOS condition.
3	-	-	-	Reserved.
2	Core	0h	RW	**PROCHOT_INT_ENABLE —** This bit allows the BIOS to enable the interrupt on the transition of the external PROCHOT pin. If set a thermal interrupt is generated on either the rising or falling edge of PROCHOT.0 disable interrupt. 1 enable interrupt.
1	Core	0h	RW	**LOW_TEMP_INT_ENABLE —** This bit allows the BIOS to enable the generation of an interrupt on the transition from hightemperature to a lowtemperature where high temperature is dictated by the thermal monitor trip threshold. 0 disable interrupt. 1 enable interrupt
0	Core	0h	RW	**HIGH_TEMP_INT_ENABLE —** This bit allows the BIOS to enable the generation of an interrupt on the transition from lowtemperature to a hightemperature threshold where high temperature is dictated by the thermal monitor trip threshold. 0 disable interrupt. 1 enable interrupt.

69.2.51 (19Ch) IA32_THERM_STATUS

Intel® Thermal Monitor CPU Core thermal status register.

MSR Address: 19Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Core	0h	RO	**VALID —** Set if temperature is within the valid thermal sensor range.
30:27	Core	1h	RO	**RESOLUTION —** Supported resolution in degrees C.
26:23	-	-	-	Reserved.
22:16	Core	0h	RO	**TEMPERATURE —** This is a temperature offset in degrees C from the TJ_{MAX} temperature. See the READING_VALID field in the thermal status register for further details on how to interpret this field. Note that behavior of this field is also affected by CPU_THERM_SENS_CFGGROUP_TEMP. The power controller will read sensor data from each CPU core and update this field.
15:12	-	-	-	Reserved.
11	Core	0h	RW_0C	**POWER_LIMITATION_LOG —** PWR_LIMIT Log. This bit is set by firmware and cleared by software.
10	Core	0h	RO	**POWER_LIMITATION_STATUS —** PWR_LIMIT Status.
9	Core	0h	RW_0C	**THRESHOLD2_LOG —** Sticky log bit that asserts on a 0 to 1 or a 1 to 0 transition of the THERMAL_THRESHOLD2_STATUS bit. This bit is set by firmware and cleared by SW.
8	Core	0h	RO	**THRESHOLD2_STATUS —** Indicates that the current temperature reported in DIG_TEMP_READOUT is higher than or equal to Threshold 2 temperature.
7	Core	0h	RW_0C	**THRESHOLD1_LOG —** Sticky log bit that asserts on a 0 to 1 or a 1 to 0 transition of the THERMAL_THRESHOLD1_STATUS bit. This bit is set by firmware and cleared by SW.
6	Core	0h	RO	**THRESHOLD1_STATUS —** Indicates that the current temperature reported in DIG_TEMP_READOUT is higher than or equal to Threshold 1 temperature.
5	Core	0h	RW_0C	**OUT_OF_SPEC_LOG —** Sticky log bit indicating that the processor operating out of its thermal specification since the last time this bit was cleared. This bit is set by firmware on a 0 to 1 transition of OUT_OF_SPEC_STATUS.
4	Core	0h	RO	**OUT_OF_SPEC_STATUS —** Status bit indicating that the processor is operating out of its thermal specification. Once set this bit will be cleared once the temperature decreases back to cold condition.
3	Core	0h	RW_0C	**PROCHOT_LOG —** Sticky log bit indicating that PROCHOT has been asserted since the last time this bit was cleared by SW. This bit is set by firmware on a 0 to 1 transition of PROCHOT_EVENT.
2	Core	0h	RO	**PROCHOT_STATUS —** Status bit indicating that PROCHOT is currently being asserted.
1	Core	0h	RW_0C	**THERMAL_MONITOR_LOG —** Sticky log bit indicating that the core has seen a thermal monitor event since the last time SW cleared this bit. This bit is set by Firmware on a 0 to 1 transition of THERMAL_MONITOR_STATUS.
0	Core	0h	RO	**THERMAL_MONITOR_STATUS —** Status bit indicating that the Thermal Monitor has tripped and is currently thermally throttling.

69.2.52 (19Dh) MSR_THERM2_CTL

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 19Dh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	-	-	-	Reserved.
31:0	Thread	0h	Rsvd0	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.53 (1A0h) IA32_MISC_ENABLE

Miscellaneous Enables Register holds enable bits for miscellaneous features.

MSR Address: 1A0h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:39	-	-	-	Reserved.
38	Package	0h	RW	**TURBO_DISABLE —** Disables turbo mode.
37:35	-	-	-	Reserved.
34	Thread	0h	RW	**NX_DISABLE —** When set to a 1, disables the Execute Disable Bit feature (XD Bit).
33:24	-	-	-	Reserved.
23	Thread	0h	RW	**DISABLE_ECHOING_TPR_MESSAGES —** This MSR field maps to PIC_CR_DEBUG_MODES.TPR_MSG_OFF
22	Thread	0h	RW	**BOOT_NT4 —** Setting this bit causes CPUID to pretend leaves 4 and 5 don't exist and that the max defined leaf is 3.
21:19	-	-	-	Reserved.
18	Thread	0h	RW	**ENABLE_MONITOR_FSM —** Reset sets this bit. SW Enables MONITOR/MWAIT FSM in BLS.
17	-	-	-	Reserved.
16	Package	0h	RW	**ENABLE_GV3 —** Setting this bit enables the Geyserville3 mechanism. The software can set the processor operating point by writing the proper VID and frequency ratio into the CLK_GEYSIII_CONTROL register. Default value is 0 (disabled). This bit is affected by fuse settings, and can be set to 1 only if FB_GV3_DISABLE_FUSE is '0 . This bit is write protected by the GV_SEL_LOCK bit.
15:13	-	-	-	Reserved.
12	Core	0h	RO	**PEBS_UNAVAILABLE —** Based Sampling debug feature. RDMSR ucode returns !EMON_AVAILABLE. Written value is ignored.
11	Core	0h	Rsvd0	**BTS_UNAVAILABLE —** If set the processor does not support Branch Trace Stores. WRMSR prevents setting this bit.
10:8	-	-	-	Reserved.
7	Core	0h	RW	**EMON_AVAILABLE —** RDMSR gets this bit from PM_CR_DEBUG_DEFEATURE.PERFMON_AVAIL. WRMSR masks writes to this bit. This bit prevents public software access to the emon / performance counter registers. When set, these regs are available and read/write. When clear, the registers.
6:4	-	-	-	Reserved.
3	Package	0h	RW	**THERMAL_MONITOR_ENABLE —** This value from PCU_CR_FIRM_CONFIG. Global TM EN. This is a union of bits 3, 13 (ENABLE_TT2) and 36 (ENABLE_EMTTM). A value = 0 (default) indicates disabled, and a value = 1 indicates enabled. Activation is possible only if FB_THERM_THROT_DIS_FUSE is '0'".
2	-	-	-	Reserved.
1	-	-	-	Reserved.
0	Thread	0h	RW	**FAST_STRINGS —** Enable fast strings.

69.2.54 (1A1h) PACKAGE_THERM_MARGINBD

This register can be read to get the average Thermal margin above Tspec.

MSR Address: 1A1h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:16	-	-	-	Reserved.
15:0	Package	0h	RO	**THERM_MARGIN —** Thermal margin in 8.8 format .

69.2.55 (1A2h) MSR_TEMPERATURE_TARGET

Legacy register holding temperature related constants for Platform use. This register is updated by FW based on fuse values.

MSR Address: 1A2h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	-	-	-	Reserved.
30:24	Package	0h	RW	**TJ_MAX_TCC_OFFSET —** This field allows platform SW to configure a Tjmax_offset such that thermal throttling is activated at fused_Tjmax Tjmax_TCC_offset. FW reads this field to control thermal throttling activation at temperature lower than fused Tjmax.
23:16	Package	5Ah	RO	**REF_TEMP —** Tjmax a.k.a. Throttle Temperature TCC activation temperature or Prochot Temperature or REF_TEMP This is the maximum junction temperature at which thermal throttling aka thermal monitor is activated. FW updates this register based on FUSE_TJMAX. This field is read only by all other SW.
15:8	Package	0h	RO	**FAN_TEMP_TARGET_OFFSET —** Fan Temperature Target Offset a.k.a. TControl indicates the relative offset from the Thermal Monitor Trip Temperature at which fans should be engaged. FUSE_TEMP_TARGET 1.
7:0	-	-	-	Reserved.

69.2.56 (1A4h) MSR_MISC_FEATURE_CONTROL

Miscellaneous Feature Control Register.

MSR Address: 1A4h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:3	-	-	-	Reserved.
2	Core	0h	RW	**DCU_STREAMER_PREFETCH_DISABLE —** WMRSR maps this to MEC_CR_MODES_AND_DEFEATURES.DISABLE_PREFETCHER.
1	-	-	-	Reserved.
0	Module	0h	RW	**MLC_STREAMER_PREFETCH_DISABLE —** WMRSR maps this to EBL_CR_DEBUG_CTL1_PREF_UCODE_DISABLE.

69.2.57 (1A6h) MSR_OFFCORE_RSP_0

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 1A6h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	-	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.58 (1A7h) MSR_OFFCORE_RSP_1

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 1A7h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	-	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

69.2.59 (1A8h) THREAD_SW_DEFEATURE

This MSR has no functionality and exists only for compatibility purposes. Returns 0s on reads, drops writes.

MSR Address: 1A8h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:0	Thread	0h	RW	**DATA —** Returns zeros for RDMSR. Writes are dropped for WRMSR.

69.2.60 (1AAh) MSR_MISC_PWR_MGMT

Legacy Miscellaneous Power Management Features.

MSR Address: 1AAh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:23	-	-	-	Reserved.
22	Package	0h	RW	**LOCK_THERM_INT —** Ties thermal interrupts from both cores. If set then thermal interrupt on one core is routed to all cores.
21:1	-	-	-	Reserved.
0	Package	0h	RW	**SINGLE_PCTL_EN —** When set (1) will cause PST commands (writes to IA32_PERF_CTL) from any cores to set the P-state target (no coordination). This means that the last that write the P-state request, is the dominant one. If not set this means that coordination between all the thread requests will be initiated and the resolved result will dominant. Default = 0 (disabled). Indicates the number of error-reporting banks available on this processor.

69.2.61 (1ADh) MSR_TURBO_RATIO_LIMIT

PUNIT_MSR: This register allows determines the ratio limits to be used to limit frequency based on cores being C6/C7. During reset the SoC initializes this register based on SoC fuses. The MSR values determine how many ratio ticks of turbo to allow based on the number of active cores.

MSR Address: 1ADh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:56	Package	0h	RW	**RATIO_LIMIT_7 —** Ratio limit 7
55:48	Package	0h	RW	**RATIO_LIMIT_6 —** Ratio limit 6
47:40	Package	0h	RW	**RATIO_LIMIT_5 —** Ratio limit 5
39:32	Package	0h	RW	**RATIO_LIMIT_4 —** Ratio limit 4
31:24	Package	0h	RW	**RATIO_LIMIT_3 —** Ratio limit 3
23:16	Package	0h	RW	**RATIO_LIMIT_2 —** Ratio limit 2
15:8	Package	0h	RW	**RATIO_LIMIT_1 —** Ratio limit 1
7:0	Package	0h	RW	**RATIO_LIMIT_0 —** Ratio limit 0

69.2.62 (1AEh) MSR_TURBO_RATIO_LIMIT1

PUNIT_MSR: This register allows determines the core counts to be used to limit frequency based on cores being C6/C7. During reset the SoC initializes this register based on SoC fuses. The MSR values determine how many ratio ticks of turbo to allow based on the number of active cores.

MSR Address: 1AEh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:56	Package	0h	RW	**CORE_COUNT_7 —** Core count 7
55:48	Package	0h	RW	**CORE_COUNT_6 —** Core count 6
47:40	Package	0h	RW	**CORE_COUNT_5 —** Core count 5
39:32	Package	0h	RW	**CORE_COUNT_4 —** Core count 4
31:24	Package	0h	RW	**CORE_COUNT_3 —** Core count 3
23:16	Package	0h	RW	**CORE_COUNT_2 —** Core count 2
15:8	Package	0h	RW	**CORE_COUNT_1 —** Core count 1
7:0	Package	0h	RW	**CORE_COUNT_0 —** Core count 0

69.2.63 (1B0h) IA32_ENERGY_PERF_BIAS

Not a real register. This define exists to create the MSR routine that will be used to control the energy-efficient P-State performance policy. The bits will be redirected to a corresponding field in THREAD_P_REQ. This register allows software to control the Energy efficiency Policy in the CPU. This MSR will #GP unless POWER_CTL1[PWR_PERF_PLTFRM_OVR] is set.

MSR Address: 1B0h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:4	-	-	-	Reserved.
3:0	Package	0h	RW	**ENERGY_POLICY —** If enabled via POWER_CTL1, overrides the energy-efficient P-State performance policy field in THREAD_P_REQ

69.2.64 (1B1h) IA32_PACKAGE_THERM_STATUS

Package Thermal Status Register for tracking package level temperature changes. This MSR is visible and accessible only when CPUID.(EAX=06h):EAX[6] is set to indicate this feature is available.

MSR Address: 1B1h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Package	0h	RW	**VALID —** Set if temperature is within the valid thermal sensor range.
30:27	Package	1h	RO	**RESOLUTION —** Supported resolution in degrees C.
26:23	-	-	-	Reserved.
22:16	Package	0h	RO	**TEMPERATURE —** Temperature in degrees C relative to the thermal monitor trip temperature fused.
15:12	-	-	-	Reserved.
11	Package	0h	RW_0C	**POWER_LIMITATION_LOG —** Sticky log bit that asserts when either IA is running at P-state below the max P-state offset or that GT is running at P-state below its P1 frequency. Set by HW on a 0 to 1 transition of Power Limitation Status. Cleared by SW.
10	Package	0h	RO	**POWER_LIMITATION_STATUS —** Status log bit that notifies that either IA is running at P-state below the max P-state offset or that GT is running at P-state below its P1 frequency.
9	Package	0h	RW_0C	**THRESHOLD2_LOG —** Sticky log bit that asserts on a 0 to 1 or 1 to 0 transition of the Threshold1_Status bit. HW controls this transition.
8	Package	0h	RO	**THRESHOLD2_STATUS —** Indicates that the current temperature bits 22:16 in this register is higher than or equal to the Threshold1 defined in the IA32_PACKAGE_THERM_INTERRUPT MSR. Note that because temperature and thresholds are defined as negative offsets a higher number means a lower temperature.
7	Package	0h	RW_0C	**THRESHOLD1_LOG —** Sticky log bit that asserts on a 0 to 1 or 1 to 0 transition of the Threshold1_Status bit. HW controls this transition.
6	Package	0h	RO	**THRESHOLD1_STATUS —** Indicates that the current temperature bits 22:16 in this register is higher than or equal to the Threshold1 defined in the IA32_PACKAGE_THERM_INTERRUPT MSR. Note that because temperature and thresholds are defined as negative offsets a higher number means a lower temperature.
5	Package	0h	RW_0C	**OUT_OF_SPEC_LOG —** Sticky log bit indicating that the processor operating out of its thermal specification since the last time this bit was cleared. Set by HW on a 0 to 1 transition of Out_of_Spec_Status
4	Package	0h	RO	**OUT_OF_SPEC_STATUS —** Status bit indicating that the processor is operating out of its thermal specification.
3	Package	0h	RW_0C	**PROCHOT_LOG —** Sticky log bit indicating that PROCHOT has been asserted since the last time this bit was cleared by SW. Set by HW on a 0 to 1 transition of Prochot_Status.
2	Package	0h	RO	**PROCHOT_STATUS —** Status bit indicating that PROCHOT is currently being asserted.
1	Package	0h	RW_0C	**THERMAL_MONITOR_LOG —** Sticky log bit indicating that the package has seen a thermal monitor event since the last time SW cleared this bit. Set by HW on a 0 to 1 transition of Thermal_Monitor_Status.
0	Package	0h	RO	**THERMAL_MONITOR_STATUS —** Status bit indicating that any of the package thermal monitor have tripped and the package is currently thermally throttling.

69.2.65 (1B2h) IA32_PACKAGE_THERM_INTERRUPT

Thermal Limitation Interrupt Control. PCODE will read this information before generating a thermal interrupt.

MSR Address: 1B2h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:25	-	-	-	Reserved.
24	Package	0h	RW	**POWER_INT_ENABLE —** When this bit is set a thermal interrupt will be sent upon throttling due to power limitations.
23	Package	0h	RW	**THRESHOLD_2_INT_ENABLE —** Controls the generation of a thermal interrupt whenever the Thermal Threshold 2 Temperature is crossed.
22:16	Package	0h	RW	**THRESHOLD_2_REL_TEMP —** This value indicates the offset in degrees below TJ Max Temperature that should trigger a Thermal Threshold 2 trip.
15	Package	0h	RW	**THRESHOLD_1_INT_ENABLE —** Controls the generation of a thermal interrupt whenever the Thermal Threshold 1 Temperature is crossed.
14:8	Package	0h	RW	**THRESHOLD_1_REL_TEMP —** This value indicates the offset in degrees below TJ Max Temperature that should trigger a Thermal Threshold 1 trip.
7:5	-	-	-	Reserved.
4	Package	0h	RW	**OUT_OF_SPEC_INT_ENABLE —** Thermal interrupt enable for the Out Of Spec condition which is stored in the Out Of Spec status bit in PACKAGE_THERM_STATUS.
3	-	-	-	Reserved.
2	Package	0h	RW	**PROCHOT_INT_ENABLE —** Bidirectional PROCHOT assertion interrupt enable. If set a thermal interrupt is delivered on the rising edge of PROCHOT.
1	Package	0h	RW	**LOW_TEMP_INT_ENABLE —** Enables a thermal interrupt to be generated on the transition from a hightemperature to a lowtemperature when set where high temperature is dicated by the thermal monitor trip temperature minus offset as defined in IA32_TEMPERATURE_TARGET.
0	Package	0h	RW	**HIGH_TEMP_INT_ENABLE —** Enables a thermal interrupt to be generated on the transition from a lowtemperature to a hightemperature when set where high temperature is dicated by the thermal monitor trip temperature minus offset as defined in IA32_TEMPERATURE_TARGET.

69.2.66 (1C6h) DEBUG_RESOURCE_STATUS

This MSR returns the status of debug resources.

MSR Address: 1C6h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Thread	0h	RO	**DEBUG_AVAILABLE —**
0	Thread	0h	RO	**DEBUG_DRX_AVAILABLE —**

69.2.67 (1C8h) MSR_LBR_SELECT

MSR_LBR_SELECT is cleared to zero at RESET, and LBR (Last Branch Record) filtering is disabled, i.e. all branches will be captured. MSR_LBR_SELECT provides bit fields to specify the conditions of subsets of branches that will not be captured in the LBR.

MSR Address: 1C8h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:10	-	-	-	Reserved.
9	Thread	0h	RW	**LBR_CALL_STACK_EN —** Enable LBR call stack.
8	Thread	0h	RW	**FAR_BRANCH —** Filter out far branches.
7	Thread	0h	RW	**NEAR_REL_JMP —** Filter out near unconditional relative branches.
6	Thread	0h	RW	**NEAR_INDIRECT_JMP —** Filter out near unconditional indirect jumps.
5	Thread	0h	RW	**NEAR_RET —** Filter out near returns.
4	Thread	0h	RW	**NEAR_INDIRECT_CALL —** Filter out near indirect calls.
3	Thread	0h	RW	**NEAR_REL_CALL —** Filter out near relative calls.
2	Thread	0h	RW	**JCC —** Filter out taken conditional branches.
1	Thread	0h	RW	**CPL_NEQ_0 —** Filter out non-ring 0 branches.
0	Thread	0h	RW	**CPL_EQ_0 —** Filter out ring 0 branches.

69.2.68 (1C9h) MSR_LASTBRANCH_TOS

Contains an index (bits 0-3) that points to the MSR containing the most recent branch record. See MSR_LASTBRANCH_0_FROM_IP (at 0x680).

MSR Address: 1C9h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:5	-	-	-	Reserved.
4:0	Thread	0h	RW	**TOS_POINTER —** LBR Top-of-stack.

69.2.69 (1D9h) IA32_DEBUGCTL

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: 1D9h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:15	-	-	-	Reserved.
14	Thread	0h	RW	**FREEZE_WHILE_SMM_EN —** When set, freezes perfmon and trace messages while in SMM. When set, freezes perfmon and trace messages while in SMM.
13	-	-	-	Reserved.
12	Thread	0h	RW	**FREEZE_PERFMON_ON_PMI —** When set, each ENABLE bit of the global counter control MSR are frozen (address 3BFH) on a PMI request.
11	Thread	0h	RW	**FREEZE_LBRS_ON_PMI —** When set, the LBR stack is frozen on a PMIrequest.
10	Thread	0h	RW	**BTS_OFF_USR —** When set, BTS or BTM is skipped if CPL > 0
9	Thread	0h	RW	**BTS_OFF_OS —** When set, BTS or BTM is skipped if CPL = 0.
8	Thread	0h	RW	**BTINT —** When clear, BTMs are logged in a BTS buffer in circular fashion. When this bit is set, an interrupt is generated by the BTS facility when the BTS buffer is full.
7	Thread	0h	RW	**BTS —** Setting this bit enables branch trace messages (BTMs) to be logged in a BTS buffer.
6	Thread	0h	RW	**TR —** Setting this bit to 1 enables branch trace messages to be sent.
5:2	-	-	-	Reserved.
1	Thread	0h	RW	**BTF —** Setting this bit to 1 enables the processor to treat EFLAGS.TF as single-step on branches instead of single-step on instructions.
0	Thread	0h	RW	**LBR —** Setting this bit to 1 enables the processor to record a running trace of the most recent branches taken by the processor in the LBR stack.

69.2.70 (1E3h) DEBUG_ERR_INJ_CTL

This MSR holds the capability of MCA error injection. Bit 1 for unlock MCA/ CMCI generation capability (allows event injection), bit 0 to unlock writing to MC banks. This register contains controls to enable/disable both the MB bank write capability and the MCA/CMCI signaling capability.

MSR Address: 1E3h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Thread	0h	RW	**MCBW_E —** CMCI/MCA signaling enable flag. If this bit is set, enables MCA and CMCI signaling through DEBUG_ERR_INJ_CTL2 register.
0	Thread	0h	RW	**MCA_CMCI_SE —** Machine check bank write capability enable flag - If this bit is set, non-zero value writes to the MCi_STATUS, MCi_MISC and MCi_ADDR registers are allowed (will not cause general-protection (#GP) exception) from SMM and ring0. If this bit is clear, regular MC bank access rules apply to the MCi_STATUS, MCi_MISC and MCi_ADDR registers (i.e, cause general-protection (#GP) exception on non-zero value writes).

69.2.71 (1E4h) DEBUG_ERR_INJ_CTL2

This register allows generating MCA or CMCI from ring0 code. This is write only (WO) register, it can be written only if DEBUG_ERR_INJ_CTL.MCA_CMCI_SE bit is set. Writing to this MSR without setting MCA_CMCI_SE bit will cause general-protection (#GP) exception. Reads to this MSR will cause general-protection (#GP) exception.

MSR Address: 1E4h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Thread	0h	WO	**MCA_G —** Setting this bit will cause MCA to be broadcast to all threads in the system.
0	Thread	0h	WO	**CMCI_G —** Setting this bit causes a CMCI to be generated on the both cores on the module when this MSR is written.

Note: Specifies the machine-check architecture defined error code for the machine check error condition detected. The machine-check architecture-defined error codes are guaranteed to be the same for all IA-32 processors that implement the machine-check architecture. Please refer to section 15.9 and chapter 16 of the document 325384 “Intel 64 and IA-32 Intel Architecture Software Developer's manual Volume 3: system programming guide” for the detail information.

69.2.72 (1E6h) PIC_DEBUG_MODES

MSR Address: 1E6h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Module	0h	RW	**SELF_IPI_OFF —** CB to disable the Self IPI feature and revert Self IPI interrupt behavior.
30	Module	0h	RW	**DISABLE_CTC_DL_SYNC —** CB to disable CTC sync with URT using the sync (Q) bit.
29	-	-	-	Reserved.
28	Module	0h	RW	**WATCHDOG_IGNORE_BUSQEMPTY —** Masks out bus queue empty from smc nuke logic.
27	Module	0h	RW	**WATCHDOG_QUICK —** Change all the above WATCHDOG setting to be on ROB Timeout[1] instead of ROB Timeout[2], cut timeout times in half to give a warning early to the other core.
26	Module	0h	RW	**DISABLE_ASYNC_MCKIND —** Disable Asynchronous MCKind from being signaled
25	Module	0h	RW	**DISABLE_ASYNC_MCERR —** Disable Asynchronous MCERR from being signaled
24	Module	0h	RW	**PSMI_ASSIST —** Prevents certain registers from changing and prevents side-effects for PSMI Modes
23	Module	0h	RW	**WATCHDOG_SMC_OTHER_REPEATED —** On ROB Timeout[2] = 1, SMC Nuke other core continuously
22	Module	0h	RW	**WATCHDOG_SMC_SAME_WAIT —** On ROB Timeout Cnt 011 to 100, SMC Nuke same core on TSC[8] Toggle
21	Module	0h	RW	**WATCHDOG_SMC_SAME_NOW —** On ROB Timeout Cnt 011 to 100, SMC Nuke same core now
20	Module	0h	RW	**WATCHDOG_SMC_OTHER_WAIT —** On ROB Timeout Cnt 011 to 100, SMC Nuke other core on TSC[8] Toggle
19	Module	0h	RW	**WATCHDOG_SMC_OTHER_NOW —** On ROB Timeout Cnt 011 to 100, SMC Nuke other core now
18:17	Module	0h	RW	**PERIODIC_SMC_TSC_SEL —** Selects Bit of TSC for Periodic SMC Nuke. 00:TSC[20]:1ms, 00:TSC[20]:1ms, 01:TSC[23]:10ms, 10:TSC[27]:100ms, 11:TSC[30]:1s
16	Module	0h	RW	**PERIODIC_SMC_EN —** Enables Periodic SMC Nukes if set
15	Module	0h	RW	**CMCI_FEATURE_DISABLE —** Setting this bit will disable the CMCI LVT
14	Module	0h	RW	**L2_CMCI_INTERNAL —** Setting this bit will not send the L2 CMCI event to Tunit and complete internally instead.
13	-	-	-	Reserved.
12	Module	0h	RW	**ID_IS_NOT_READONLY —** when set to '1 enables SW to write to ID register in APIC.
11	Module	0h	RW	**TSC_DEADLINE_CB —** CB for TSC Deadline
10	Module	0h	RW	**SV_SENTER_EN —** enables saving of internal data to SCPs during SENTER
9	Module	0h	RW	**SV_GLOBAL_ENABLE —** enables PATCH2 and PATCH3 special instructions in Unlocked units only.
8	Module	0h	RW	**DISABLE_INTPRIUPD_GENERATION —** >Disables TPR/IntPriUpd from being generated
7	Module	0h	RW	**EOI_NO_BDCST_ENABLE —** f
6	Module	0h	RW	**EOI_SUPPRESS_CB —**
5	Module	0h	RW	**ICR_MSG_OFF —**
4	Module	0h	RW	**TPR_MSG_OFF —** Disable new TPR Update message requests to the FSB TPR messages. Will be generated for changes to PIC HW/SW enables.

MSR Address: 1E6h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
3	Module	0h	RW	**PIC_REQ_OFF —** Disable new PICOMB requests to the EBC.
2	Module	0h	RW	**CCR_FREEZE_CORE1 —** When this bit is set the CCR of Core1 will be frozen
1	Module	0h	RW	**CCR_FREEZE_CORE0 —** When this bit is set the CCR of Core0 will be frozen
0	Module	0h	RW	**TSC_FREEZE —** When this bit is set its freezes the counting of the Time Stamp counter.)

69.2.73 (1F0h) VLW_CAPABILITY

This MSR reports information about the Legacy features and VLW messages that are supported.

MSR Address: 1F0h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:7	-	-	-	Reserved.
6	Core	0h	RO	**NMI —** 1 means NMI VLW message is supported 1 = Supported, 0= Not Supported.
5	Core	0h	RO	**INIT —** 1 means INIT VLW message is supported 1 = Supported, 0= Not Supported.
4	Core	0h	RO	**SMI —** 1 means SMI VLW message is supported. This will be 0 if SMM is fuse disabled
3	-	-	-	Reserved.
2	Core	0h	RO	**INTR —** Indicates whether INTR VLW message is supported. 1 = Supported, 0= Not Supported.
1:0	-	-	-	Reserved.

69.2.74 (1FCh) MSR_POWER_CTL

Power Control Register allows enable and disable of specific power and thermal management features.

MSR Address: 1FCh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	-	-	-	Reserved.
30	Package	0h	RW	**CSTATE_PREWAKE_DISABLE —** This bit can be used to disable core/pkg C-state Prewake timers.
29:25	-	-	-	Reserved.
24	Package	0h	RW	**VR_THERM_ALERT_DISABLE —** When set to 1, disables the VR_THERMAL_ALERT signaling.
23	Package	0h	RW	**PROCHOT_LOCK —** When set to 1, locks bits 0, 21, 22 and 23 of this MSR. Once set, a reset is required to clear this bit.
22	Package	0h	RW	**PROCHOT_RESPONSE —** Prochhot Configurable Response Enable.
21	Package	0h	RW	**PROCHOT_OUTPUT_MODE_DISABLE —** Prochot output disable.
20	-	-	-	Reserved.
19	Package	0h	RW	**EE_TURBO_DISABLE —** Energy Efficient Turbo Disable.
18	Package	0h	RW	**PWR_PERF_PLTFRM_OVR —** When set to 0 (default), will disable access to IA32_ENERGY_PERFORMANCE_BIAS MSR 1B0h (causing a GP# fault on access). CPUID.(EAX=6):ECX[3] will read 0.
17	Package	0h	RW	**PHOLD_SR_DISABLE —** If set to '1', CPU will also prevent the memory from going to SR during the CST_PREVENTION timeout;
16:6	Package	0h	RW	**PHOLD_CST_PREVENTION_INIT —** Init value for the PHOLD_CST_PREVENTION_Timer. Values are between 0 and 1023 in 2^21*10nS resolution (matching 0 - ~21sec).
5	-	-	-	Reserved.
4	Package	0h	RW	**FAST_BRK_INT_EN —** Controls the VID swing rate for Other_Intp_Wake events detected at the iMPH. Will override a "SLOW" sideband wake indication (for C7 or PCIe).
3	Package	0h	RW	**FAST_BRK_SNP_EN —** Controls the VID swing rate for Other_Snp_Wake events detected at the iMPH. Will override a "SLOW" sideband wake indication primarily for PCIe traffic.
2	Package	0h	RW	**SAPM_IMC_C2_POLICY —** Enables Self Refresh entry when the CPU is in package-C2 (popup) state. Should be disabled only if platform traffic cannot withstand even the SR exit latency while in C2.
1	Package	0h	RW	**C1E_ENABLE —** Used to enable C1E behavior on every C1 entry (even if MWAIT C1E substate bit was not set or when using HLT).When this package-visible bit is set, it will cause CPU to switch to minimum GV point when all cores have entered C1. Frequency will switch immediately, followed by gradual voltage switching (GV3 style). This is a package visible bit stored in PCU_CR_FIRM_CONFIG[C1E_ENABLE]
0	Package	0h	RW	**ENABLE_BIDIR_PROCHOT —** Used to enable or disable the response to PROCHOT# input. When set/enabled, platform can force CPU to throttle to a lower power condition such as Pn/Pm by asserting prochot#. When clear/disabled (default), CPU ignores the status of the prochot input signal.

69.2.75 (281h) IA32_MC1_CTL2 (L2 Cache)

Bank 1 MCA Control Register 2.

MSR Address: 281h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Module	-	RO	Reserved.
30	Module	0h	RW	**CMCI_EN —** CMCI Enable
29:15	Module	-	RO	Reserved.
14:0	Module	0h	RW	**CORRECTED_ERROR_COUNT_THRESHOLD —** Corrected Error Count Threshold.

69.2.76 (282h) IA32_MC2_CTL2 (FEC)

MCA Address Control Register for CMCI.

MSR Address: 282h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Core	-	RO	Reserved.
30	Core	0h	RW	**CMCI_EN —** CMCI Enable. Software sets this bit to enable the generation of corrected machine check interrupts.
29:15	Core	-	RO	Reserved.
14:0	Core	0h	RW	**CORRECTED_ERROR_COUNT_THRESHOLD —** The Threshold Value for Corrected Error Count.

69.2.77 (283h) IA32_MC3_CTL2 (MEC)

MSR Address: 283h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Module	-	RO	Reserved.
30	Module	0h	Rsvd0	**CMCI_EN —** Reserved.
29:15	Module	-	RO	Reserved.
14:0	Module	0h	Rsvd0	**CORRECTED_ERROR_COUNT_THRESHOLD —** Reserved.

69.2.78 (284h) IA32_MC4_CTL2 (SA)

MSR Address: 284h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:35	Package	-	RO	Reserved.
34	Package	0h	RW	**MCE_CTL —** Controls MCE Remapping 0 MCE 1 MSMI.
33	Package	-	RO	Reserved.
32	Package	0h	RW	**CMCI_CTL —** Controls CMCI Remapping 0 CMCI 1 CSMI.
31	Package	-	RO	Reserved.
30	Package	0h	RW	**CMCI_EN —** Reserved.
29:15	Package	-	RO	Reserved.
14:0	Package	0h	RW	**THRESHOLD —** Reserved.

69.2.79 (285h) IA32_MC5_CTL2 (PMU)

MSR Address: 285h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:35	Package	-	RO	Reserved.
34	Package	0h	RW	**MCE_CTL —** Controls MCE Remapping 0 MCE 1 MSMI.
33	Package	-	RO	Reserved.
32	Package	0h	RW	**CMCI_CTL —** Controls CMCI Remapping 0 CMCI 1 CSMI.
31	Package	-	RO	Reserved.
30	Package	0h	RW	**CMCI_EN —** Reserved.
29:15	Package	-	RO	Reserved.
14:0	Package	0h	RW	**THRESHOLD —** Reserved.

69.2.80 (286h) IA32_MC6_CTL2 (SA)

MSR Address: 286h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:35	Package	-	RO	Reserved.
34	Package	0h	RW	**MCE_CTL —** Controls MCE Remapping 0 MCE 1 MSMI.
33	Package	-	RO	Reserved.
32	Package	0h	RW	**CMCI_CTL —** Controls CMCI Remapping 0 CMCI 1 CSMI.
31	Package	-	RO	Reserved.
30	Package	0h	RW	**CMCI_EN —** Reserved.
29:15	Package	-	RO	Reserved.
14:0	Package	0h	RW	**THRESHOLD —** Reserved.

69.2.81 (287h) IA32_MC7_CTL2 (MEM 0)

MSR Address: 287h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:35	Package	-	RO	Reserved.
34	Package	0h	RW	**MCE_CTL —** Controls MCE Remapping 0 MCE 1 MSMI.
33	Package	-	RO	Reserved.
32	Package	0h	RW	**CMCI_CTL —** Controls CMCI Remapping 0 CMCI 1 CSMI.
31	Package	-	RO	Reserved.
30	Package	0h	RW	**CMCI_EN —** Reserved.
29:15	Package	-	RO	Reserved.
14:0	Package	0h	RW	**THRESHOLD —** Reserved.

69.2.82 (288h) IA32_MC8_CTL2 (MEM 1)

MSR Address: 288h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:35	Package	-	RO	Reserved.
34	Package	0h	RW	**MCE_CTL —** Controls MCE Remapping 0 MCE 1 MSMI.
33	Package	-	RO	Reserved.
32	Package	0h	RW	**CMCI_CTL —** Controls CMCI Remapping 0 CMCI 1 CSMI.
31	Package	-	RO	Reserved.
30	Package	0h	RW	**CMCI_EN —** Reserved.
29:15	Package	-	RO	Reserved.
14:0	Package	0h	RW	**THRESHOLD —** Reserved.

69.2.83 (2E0h) NO_EVICT_MODE

MSR Address: 2E0h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Thread	0h	RW	**NEM_RUN —** BIOS sets this bit when it's done filling the NEM region and ready for using cache as RAM.
0	Thread	0h	RW	**NEM_SETUP —** BIOS sets this when it is ready to fill the NEM region, and then executes the requests to fill the NEM.

69.2.84 (2FFh) IA32_MTRR_DEF_TYPE

The IA32_MTRR_DEF_TYPE MSR sets the default properties of the regions of physical memory that are not encompassed by MTRRs.

MSR Address: 2FFh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:12	-	-	-	Reserved.
11	Core	0h	RW	**MTRR_ENABLE —** When set, enables all MTRRs. A value = 0 disables, and a value = 1 enables all MTRRs. Note: Global MTRR Enable is often referred to as IA32_MTRR_DEF_TYPE.E or IA32_MTRR_DEF_TYPE.GE.
10	Core	0h	RW	**FIXED_RANGE_ENABLE —** When set, enables the fixed range MTRRs. A value = 0 disables, and a value = 1 enables the Fixed MTRRs. Note: Fixed MTRR Enable is often referred to as IA32_MTRR_DEF_TYPE.F or IA32_MTRR_DEF_TYPE.FE.
9:3	-	-	RO	Reserved.
2:0	Core	0h	RW	**TYPE —** Indicates the default memory type used for those memory ranges that do not have a memory type specified in an MTRR. Note: Default MTRR Memory Type is often referred to as IA32_MTRR_DEF_TYPE.

69.2.85 (300h) MSR_SGXOWNER0

Register shared by all threads.

MSR Address: 300h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Package	0h	RW	**DATA —** Data space allowed to be read/written by the SoC in byte granularity.

69.2.86 (301h) MSR_SGXOWNER1

Register shared by all threads.

MSR Address: 301h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Package	0h	RW	**DATA —** Data space allowed to be read/written by the SoC in byte granularity.

69.2.87 (309h) IA32_FIXED_CTR0

IA32_FIXED_CTR0 contains a 48-bit fixed rate counter.

MSR Address: 309h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	-	-	-	Reserved.
47:0	Thread	0h	RW	**FIXED_COUNTER0_VALUE —** 48-bit fixed rate counter 0.

69.2.88 (30Ah) IA32_FIXED_CTR1

IA32_FIXED_CTR1 contains a 48-bit fixed rate counter.

MSR Address: 30Ah				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	-	-	-	Reserved.
47:0	Thread	0h	RW	**FIXED_COUNTER1_VALUE —** 48-bit fixed rate counter 1.

69.2.89 (30Bh) IA32_FIXED_CTR2

IA32_FIXED_CTR2 contains a 48-bit fixed rate counter.

MSR Address: 30Bh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	-	-	-	Reserved.
47:0	Thread	0h	RW	**FIXED_COUNTER2_VALUE —** 48-bit fixed rate counter 2.

69.2.90 (345h) IA32_PERF_CAPABILITIES

This register enumerates the existence of certain debug features in PerfMon.

MSR Address: 345h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:14	-	-	-	Reserved.
13	Core	0h	RO	**FULLWIDTHCNTRS —** Full width of counter writable via IA32_A_PMCx.
12	Core	0h	RO	**SMMFREEZE —** Freeze while SMM is supported
11:8	Core	0h	RO	**PEBS_REC_FORMAT —** PEBS Record Format.
7	Core	0h	RO	**PEBS_SAVE_ARCH_REGS —** When set, PEBS will save architectural register and state information according to the encoded value of the PEBSRecordFormat field.
6	Core	0h	RO	**PEBS_TRAP —** PEBS Record Format.
5:0	Core	0h	RO	**LBR_FORMAT —** Last Branch Record Format. 0=32-bit, 1=64-bit LIP, 2=64-bit EIP.

69.2.91 (38Dh) IA32_FIXED_CTR_CTRL

This register provides enables for the fixed performance counters and enables for PMI. This register also provides the control for the counts to be for single thread or both threads in a core.

MSR Address: 38Dh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:12	-	-	-	Reserved.
11	Thread	0h	RW	**CTR_2_PMI_ENABLE —** When this bit is set fixed counter 0 will count instructions retired for both threads.
10	Thread	0h	RW	**CTR_2_BOTH_THREAD_ENABLE —** When this bit is set fixed counter 0 will count instructions retired for both threads.
9:8	Thread	0h	RW	**CTR_2_ENABLE —** This bit field is the local enable for the Fixed counter 2. Disabling these bits will cause the counters to halt. Counter is enabled by setting CPL Level: 00 - Disable 01 - Ring 0 (OS) 10 - Ring 1,2,3 (User) 11 - All ring levels (OS or User) when CPL changes to one of the above the counter gets enabled.
7	Thread	0h	RW	**CTR_1_PMI_ENABLE —** When this bit is set fixed counter 0 will count instructions retired for both threads.
6	Thread	0h	RW	**CTR_1_BOTH_THREAD_ENABLE —** When this bit is set fixed counter 0 will count instructions retired for both threads.
5:4	Thread	0h	RW	**CTR_1_ENABLE —** This bit field is the local enable for the Fixed counter 2. Disabling these bits will cause the counters to halt. Counter is enabled by setting CPL Level: 00 - Disable 01 - Ring 0 (OS) 10 - Ring 1,2,3 (User) 11 - All ring levels (OS or User) when CPL changes to one of the above the counter gets enabled.
3	Thread	0h	RW	**CTR_0_PMI_ENABLE —** When this bit is set fixed counter 0 will count instructions retired for both threads.
2	Thread	0h	RW	**CTR_0_BOTH_THREAD_ENABLE —** When this bit is set fixed counter 0 will count instructions retired for both threads.
1:0	Thread	0h	RW	**CTR_0_ENABLE —** This bit field is the local enable for the Fixed counter 2. Disabling these bits will cause the counters to halt. Counter is enabled by setting CPL Level: 00 - Disable 01 - Ring 0 (OS) 10 - Ring 1,2,3 (User) 11 - All ring levels (OS or User) when CPL changes to one of the above the counter gets enabled.

69.2.92 (38Eh) IA32_PERF_GLOBAL_STATUS

Global Performance Counter Status.

MSR Address: 38Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Thread	0h	RO	**COND_CHG —** Status bits of this register has changed.
62	Thread	0h	RO	**PEBS_BUFFER_OVERFLOW —** DS SAVE area Buffer overflow status.
61	-	-	-	Reserved.
60	Thread	0h	RO	**ASCI —** Set if any of the perfmon counters are suppressed.
59	Thread	0h	RO	**COUNTERS_FROZEN —**
58	Thread	0h	RO	**LBRS_FROZEN —**
57:56	-	-	-	Reserved.
55	Thread	0h	RO	**RTIT_TOPA_PMI —** RTIT Table of Physical Addresses PMI. Allows software to differentiate between legacy PMI sources.
54:35	-	-	-	Reserved.
34	Thread	0h	RO	**FIXED_PERFMON_COUNTER_2_OVERFLOW —** Overflow status of IA32_FIXED_CTR2
33	Thread	0h	RO	**FIXED_PERFMON_COUNTER_1_OVERFLOW —** Overflow status of IA32_FIXED_CTR1
32	Thread	0h	RO	**FIXED_PERFMON_COUNTER_0_OVERFLOW —** Overflow status of IA32_FIXED_CTR0
31:4	-	-	-	Reserved.
3	Thread	0h	RO	**GP_PERFMON_COUNTER_3_OVERFLOW —** Overflow status of IA32_PMC3.
2	Thread	0h	RO	**GP_PERFMON_COUNTER_2_OVERFLOW —** Overflow status of IA32_PMC2.
1	Thread	0h	RO	**GP_PERFMON_COUNTER_1_OVERFLOW —** Overflow status of IA32_PMC1.
0	Thread	0h	RO	**GP_PERFMON_COUNTER_0_OVERFLOW —** Overflow status of IA32_PMC0.

69.2.93 (38Fh) IA32_PERF_GLOBAL_CTRL

Counter increments while the result of ANDing respective enable bit in this MSR with the corresponding OS or USR bits in the general-purpose or fixed counter control MSR is true.

MSR Address: 38Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:35	-	-	-	Reserved.
34	Thread	0h	RW	**ENABLE_FIXED_PERFMON_COUNTER_2 —** Global Enable for Fixed Counter 2. Both this enable and the local enable for the fixed counter needs to be asserted for the fixed counter to be counting.
33	Thread	0h	RW	**ENABLE_FIXED_PERFMON_COUNTER_1 —** Global Enable for Fixed Counter 1. Both this enable and the local enable for the fixed counter needs to be asserted for the fixed counter to be counting.
32	Thread	0h	RW	**ENABLE_FIXED_PERFMON_COUNTER_0 —** Global Enable for Fixed Counter 0. Both this enable and the local enable for the fixed counter needs to be asserted for the fixed counter to be counting.
31:4	-	-	-	Reserved.
3	Thread	0h	RW	**ENABLE_GP_PERFMON_COUNTER_3 —** Global Enable for PerfMon Counter 3. If either the global or local enable are not asserted, the counter will be disabled. The global enable allows for simultaneous enabling or disabling of all or some of the Core PerfMon counters.
2	Thread	0h	RW	**ENABLE_GP_PERFMON_COUNTER_2 —** Global Enable for PerfMon Counter 2. If either the global or local enable are not asserted, the counter will be disabled. The global enable allows for simultaneous enabling or disabling of all or some of the Core PerfMon counters.
1	Thread	0h	RW	**ENABLE_GP_PERFMON_COUNTER_1 —** Global Enable for PerfMon Counter 1. If either the global or local enable are not asserted, the counter will be disabled. The global enable allows for simultaneous enabling or disabling of all or some of the Core PerfMon counters.
0	Thread	0h	RW	**ENABLE_GP_PERFMON_COUNTER_0 —** Global Enable for PerfMon Counter 0. If either the global or local enable are not asserted, the counter will be disabled. The global enable allows for simultaneous enabling or disabling of all or some of the Core PerfMon counters.

69.2.94 (390h) IA32_PERF_GLOBAL_STATUS_RESET

Global Perfmon Overflow clear register.

MSR Address: 390h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Thread	0h	WO	**CLR_CONDCHG —** If set, clears the conditions changed in the status register.
62	Thread	0h	WO	**CLEAR_PEBS_BUFFER_OVERFLOW —** Clears related bit in IA32_CR_PERF_GLOBAL_STATUS.
61	-	-	-	Reserved.
60	Thread	0h	WO	**CLEAR_ASCI —** Clear ASCI in status register.
59	Thread	0h	WO	**CLEAR_COUNTERS_FROZEN —** Clears IA32_PERF_GLOBAL_STATUS[59].
58	Thread	0h	WO	**CLEAR_LBRS_FROZEN —** Clears IA32_PERF_GLOBAL_STATUS[58].
57:56	-	-	-	Reserved.
55	Thread	0h	WO	**CLEAR_RTIT_TOPA_PMI —** RTIT Table of Physical Addresses PMI. Allows software to differentiate between legacy PMI sources.
54:35	-	-	-	Reserved.
34	Thread	0h	WO	**CLEAR_FIXED_PERFMON_COUNTER_2_OVERFLOW —** Set to 1 to Clear OVF_FIXED_CTR2 bit.
33	Thread	0h	WO	**CLEAR_FIXED_PERFMON_COUNTER_1_OVERFLOW —** Set to 1 to Clear OVF_FIXED_CTR1 bit.
32	Thread	0h	WO	**CLEAR_FIXED_PERFMON_COUNTER_0_OVERFLOW —** Set to 1 to Clear OVF_FIXED_CTR0 bit.
31:4	-	-	-	Reserved.
3	Thread	0h	WO	**CLEAR_PERFMON_COUNTER_3_OVERFLOW —** Set to 1 to Clear OVF_PMC3 bit.
2	Thread	0h	WO	**CLEAR_PERFMON_COUNTER_2_OVERFLOW —** Set to 1 to Clear OVF_PMC2 bit.
1	Thread	0h	WO	**CLEAR_PERFMON_COUNTER_1_OVERFLOW —** Set to 1 to Clear OVF_PMC1 bit.
0	Thread	0h	WO	**CLEAR_PERFMON_COUNTER_0_OVERFLOW —** Set to 1 to Clear OVF_PMC0 bit.

69.2.95 (391h) IA32_PERF_GLOBAL_STATUS_SET

This register is used to enumerate the availability of PerfMon resources for use.

MSR Address: 391h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Thread	0h	WO	**SET_COND_CHNGD —** Sets IA32_PERF_GLOBAL_STATUS[63].
62	Thread	0h	WO	**SET_PEBS_BUFFER_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[62].
61	-	-	-	Reserved.
60	Thread	0h	WO	**SET_ASCI —** Set the ASCI bit
59	Thread	0h	WO	**SET_COUNTERS_FROZEN —** Sets IA32_PERF_GLOBAL_STATUS[59].
58	Thread	0h	WO	**SET_LBRS_FROZEN —** Sets IA32_PERF_GLOBAL_STATUS[58].
57:56	-	-	-	Reserved.
55	Thread	0h	WO	**SET_RTIT_TOPA_PMI —** Sets IA32_PERF_GLOBAL_STATUS[55].
54:35	-	-	-	Reserved.
34	Thread	0h	WO	**SET_FIX2_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[34].
33	Thread	0h	WO	**SET_FIX1_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[33].
32	Thread	0h	WO	**SET_FIX0_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[32].
31:4	-	-	-	Reserved.
3	Thread	0h	WO	**SET_CNTR3_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[3].
2	Thread	0h	WO	**SET_CNTR2_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[2].
1	Thread	0h	WO	**SET_CNTR1_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[1].
0	Thread	0h	WO	**SET_CNTR0_OVFLW —** Sets IA32_PERF_GLOBAL_STATUS[0].

69.2.96 (392h) IA32_PERF_GLOBAL_INUSE

This register is used to enumerate the availability of PerfMon resources for use.

MSR Address: 392h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Thread	0h	RO	**PMI_PROGRAMMED —** Set if any of the Fixed or GP counters have PMI Enabled.
62	Thread	0h	RO	**PEBS_PROGRAMMED —** PEBS_ENABLE[0].
61:35	-	-	-	Reserved.
34	Thread	0h	RO	**IA32_FIXED_CTR2_PROGRAMMED —** BITWISE_OR(Fixed_Ctr_Ctrl[9:8]).
33	Thread	0h	RO	**IA32_FIXED_CTR1_PROGRAMMED —** BITWISE_OR(Fixed_Ctr_Ctrl[5:4]).
32	Thread	0h	RO	**IA32_FIXED_CTR0_PROGRAMMED —** BITWISE_OR(Fixed_Ctr_Ctrl[1:0]).
31:4	-	-	-	Reserved.
3	Thread	0h	RO	**IA32_PMC3_PROGRAMMED —** BITWISE_OR(Event_Select3[7:0]).
2	Thread	0h	RO	**IA32_PMC2_PROGRAMMED —** BITWISE_OR(Event_Select2[7:0]).
1	Thread	0h	RO	**IA32_PMC1_PROGRAMMED —** BITWISE_OR(Event_Select1[7:0]).
0	Thread	0h	RO	**IA32_PMC0_PROGRAMMED —** BITWISE_OR(Event_Select0[7:0]).

69.2.97 (3F1h) IA32_PEBS_ENABLE

Precise Event Based Sampling (PEBS) controlling MSR.

MSR Address: 3F1h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:1	-	-	-	Reserved.
0	Thread	0h	RW	**PEBS_ENABLE —** When set, enables Precise Event Based Sampling.

69.2.98 (3F8h) MSR_PKG_C3_RESIDENCY

Time spent in the Package C-State. It is given in units compatible to P1 clock frequency Guaranteed / Maximum Core Non-Turbo Frequency. This time will be updated by the SoC PCODE only after the C-State exit the update of this register has lower priority than actually ensuring that the C-State exit occurs.

MSR Address: 3F8h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:60	-	-	-	Reserved.
59:0	Package	0h	RW	**COUNTER —** Counter Value.

69.2.99 (3F9h) MSR_PKG_C6_RESIDENCY

Time spent in the Package C-State. It is given in units compatible to P1 clock frequency Guaranteed / Maximum Core Non-Turbo Frequency. This time will be updated by the SoC PCODE only after the C-State exit the update of this register has lower priority than actually ensuring that the C-State exit occurs.

MSR Address: 3F9h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:60	-	-	-	Reserved.
59:0	Package	0h	RW	**COUNTER —** Counter Value.

69.2.100 (3FCh) MSR_CORE_C3_RESIDENCY

The MSR_CORE_C3_RESIDENCY exists to assist in the debug of OEM platform power issues. This timer is not architectural which means it is not for use by OS or BIOS; and not guaranteed to be on future products or in the same MSR locations if it is available.

MSR Address: 3FCh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	0h	RW	**RESIDENCY —** This value will be accumulated by the SoC. This is in the CTC time-domain. A RDMSR will be required to convert this using "P" to get into the TSC time-domain.

69.2.101 (3FDh) MSR_CORE_C6_RESIDENCY

The MSR_CORE_C6_RESIDENCY exists to assist in the debug of OEM platform power issues. This timer is not architectural which means it is not for use by OS or BIOS; and not guaranteed to be on future products or in the same MSR locations if it is available.

MSR Address: 3FDh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	0h	RW	**RESIDENCY —** This value will be accumulated by the SoC. This is in the CTC time-domain. A RDMSR will be required to convert this using "P" to get into the TSC time-domain.

69.2.102 (3FEh) MSR_CORE_C7_RESIDENCY

The MSR_CORE_C7_RESIDENCY exists to assist in the debug of OEM platform power issues. This timer is not architectural which means it is not for use by OS or BIOS; and not guaranteed to be on future products or in the same MSR locations if it is available.

MSR Address: 3FEh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	-	-	**DATA —** Reserved for possible future use.

69.2.103 (400h) IA32_MC0_CTL (BIU)

MSR Address: 400h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Module	-	-	Reserved.
7:0	Core	0h	RW	**EN_IFU_ERR_SIGALING -** Enable IFU MCA error signaling. When bit is set, IFU errors will result in assertion of CATERR#. Otherwise, CATERR# is not asserted.

69.2.104 (401h) IA32_MC0_STATUS

MCA Status Register. WRMSR microcode

The SoC generates #GP on non-zero writes.

MSR Address: 401h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Module	0h	RW	**VALID —** Valid
62	Module	0h	RW	**OVERFLOW —** Overflow
61	Module	0h	RW	**MCERR —** MCERR
60	Module	0h	RW	**EN —** Reserved.
59	Module	-	-	Reserved.
58	Module	0h	RW	**ADDRV —** Addrv
57	Module	0h	RW	**PCC —** XQ_ERR
56:38	Module	-	-	Reserved.
37:32	Module	0h	RW	**BGF_ERROR —** Data driven sticky bit
31:30	Module	-	-	Reserved.
29	Module	0h	RW	**MCERR_INBOUND —** MCERR observed bit
28	Module	0h	RW	**MCERR_OUTBOUND —** MCERR driven sticky bit
27:25	Module	0h	RW	**ERROR_TYPE —** Error type is valid when ADDRV is set: • 001 - Inbound Data Error • 010 - Outbound Data Error • 011 - Transaction Error
24:18	Module	0h	RW	**IDI_OPCODE —** XQ error request
17:12	Module	-	-	Reserved.
11	Module	0h	RW	**MCACOD_IDI —** MCA COD bit1
10	Module	0h	RW	**MCACOD_ROB —** MCA COD ROB
9:6	Module	-	-	Reserved.
5:4	Module	0h	RW	**MCACOD_REQ —** MCA COD req bits
3:2	Module	-	-	Reserved.
1:0	Module	0h	RW	**MCACOD —** MCA COD bits

69.2.105 (402h) IA32_MC0_ADDR (BIU)

MCA Address Register. WRMSR microcode

The SoC generates #GP on non-zero writes.

MSR Address: 402h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:40	Module	-	-	Reserved.
39:0	Module	0h	RW	**BITS0TO35 —** Bits 0 to 39 for the MCA address register.

69.2.106 (404h) IA32_MC1_CTL (L2 Cache)

MSR Address: 404h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:2	Module	-	-	Reserved.
1	Module	0h	RW	**PIC —** Enables reporting of MCA errors to Hard Error.
0	Module	0h	RW	**DATA —** Enables reporting of MCA errors to Hard Error.

69.2.107 (405h) IA32_MC1_STATUS (L2 Cache)

L2 MCA Status Register. WRMSR microcode

The SoC generates #GP on non-zero writes.

MSR Address: 405h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Module	0h	RW	**MC_VALID_BIT —** MC is valid due to any ECC error detected.
62	Module	0h	RW	**MC_OVWR_BIT —** New ECC error overwriting old ECC error.
61	Module	0h	RW	**MC_UC_BIT —** Uncorrectable ECC error detected.
60	Module	0h	RW	**MC_EN_BIT —** Any ECC error detected.
59	Module	-	-	Reserved.
58	Module	0h	RW	**MC_ADDRV_BIT —** Address/State/LRU had ECC error.
57	Module	0h	RW	**MC_PCC_BIT —** Processor Context Corruption, always 1 with an uncorrectable error.
56:55	Module	-	-	Reserved.
54	Module	0h	RW	**MC_YELLOW_BIT —** Indicates parts health.
53	Module	0h	RW	**MC_GREEN_BIT —** Indicates parts health only when SINGLE_MCA_LOGGING_MODE_RANGE = 00.
52	Module	0h	RW	**MC_ERROR_COUNT_OVERFLOW_BIT —** Counting filtered correctable MCA errors.
51:38	Module	0h	RW	**MC_ERROR_COUNT —** Counting filtered correctable MCA errors.
37:36	Module	-	-	Reserved.
35	Module	0h	RW	**MCFH —** MCA Fast hit error.
34	Module	0h	RW	**MCAC —** MCA Core ID.
33:31	Module	-	-	Reserved.
30	Module	0h	RW	**MCSBF —** Fuse disable sbf pass through.
29:25	Module	-	-	Reserved.
24:23	Module	0h	RW	**MSCOD —** Model Specific error code, in addition to MCA code. Array with error: • 00 - Data • 01 - Tag • 10 - State

MSR Address: 405h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
22:20	Module	-	-	Reserved.
19:16	Module	0h	RW	**MCAW —** MCA Way.
15:0	Core	-	RWS-O	**MCACOD —** Machine Check Architecture Error Code Refer to Intel® 64 and IA-32 Architectures Software Developer Manual, Volume 3A: System Programming Guide, Part 1. Bit[15:11] can be any value between 0x0-0x1f. Bit [8] will set to 0x1 when Cache Hierarchy Error. For the lower 8 bits, the compound error code format: bRRRR TTLL RRRR: Cache Hierarchy Error RRRR. • b0000: Generic Error • b0001: Generic Read • b0010: Generic Write • b0011: Data Read • b0100: Data Write • b0101: Instruction Fetch • b0110: Prefetch • b0111: Eviction • b1000: Snoop • b1001-B1111: Reserved RRRR TT: Cache Hierarchy Error TT. • b00: Instruction • b01: Data • b10: Generic TT • b11: Reserved TT LL: Cache Hierarchy Error LL • b00: Level 0 (core L1 cache) • b01: Level 1 (core L2 cache) • b10: Level 2 (L3/LLC cache) • b11: Generic LL For Simple Error, bit[2:0]: • b000: No Error • b001: Unclassified Error • b010: Microcode ROM Parity Error • b011: External Error • b100: FRC Error • b101: Internal Parity Error • b110-b111: Simple Error Following are examples of supported codes: • 0x0174 - Eviction Error (e.g. WBINVD) • 0x0134 - L1 Data Read Error • 0x0144 - L1 Data Store Error • 0x0164 - L1 Data Prefetch Error • 0x0184 - L1 Data Snoop Error

69.2.108 (406h) IA32_MC1_ADDR (L2 Cache)

L2 MCA Address Register. WRMSR microcode

The SoC generates #GP on non-zero writes.

MSR Address: 406h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:40	Module	-	-	Reserved.
39:0	Module	0h	RW	**MCA_ADDR —** MCA Address MCA Control Register.

69.2.109 (408h) IA32_MC2_CTL (FEC)

Reserved for future use.

MSR Address: 408h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:4	-	-	-	**RSVD_63_4** - Reserved
3:1	Core	0h	RW	**EN_DTLB_ERR_SIGNALING** - Enable DTLB error reporting. When bit is set DTLB errors will result in assertion of CATERR#. Otherwise, CATERR# is not asserted.
0	Core	0h	RW	**EN_DCU_ERR_SIGNALING** - Enable DCU error reporting. When bit is set DCU errors will result in assertion of CATERR#. Otherwise, CATERR# is not asserted.

69.2.110 (409h) IA32_MC2_STATUS (FEC)

MCA Status Register.Only a write of all 0s is allowed by WRMSR microcode.

MSR Address: 409h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Core	0h	RW	**VAL —** Valid bit - Indicates the information in this register is for a valid error report.
62	Core	0h	RW	**OVER —** Machine check overflow - Indicates that there was another error already written to this register which is still in the handler (i.e., the VAL bit was already set when this error occurred).
61	Core	0h	RW	**UC —** Uncorrected Error - Signifies the error being reported went uncorrected.
60	Core	0h	RW	**EN —** MCI_CTL register has the associated Error Enable bit set.
59	Core	-	-	Reserved.
58	Core	0h	RW	**ADDRV —** MCI_ADDR register holds valid data.
57	Core	0h	RW	**PCC —** Processor Context Corrupt - Indicates that the processor state may have been corrupted by this MCA event.
56:53	Core	-	-	Reserved.
52:38	Core	0h	RW	**CORRECTED_ERROR_COUNT —** Indicates the number of corrected errors.

MSR Address: 409h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
37:32	Core	-	-	Reserved.
31:16	Core	0h	RW	**MSCOD** - Model Specific Error Code • 0x0000 - Tag Parity Error • 0x0001 - Data Parity Error • 0x0010 - Tag Parity Error • 0x0011 - Data Parity Error • 0x0004 - Internal Error
15:0	Core	-	RWS-O	**MCACOD** - Machine Check Architecture Code Refer to Intel® 64 and IA-32 Architectures Software Developer Manual, Volume 3A: System Programming Guide, Part 1. Bit[15:11] can be any value between 0x0-0x1f. Bit[8] will set to 0x1 when Cache Hierarchy Error. For the lower 8 bits, the compound error code Format: bRRRR TTLL RRRR: Cache Hierarchy Error RRRR. • b0000: Generic Error • b0001: Generic Read • b0010: Generic Write • b0011: Data Read • b0100: Data Write • b0101: Instruction Fetch • b0110: Prefetch • b0111: Eviction • b1000: Snoop • b1001-b1111: Reserved RRRR TT: Cache Hierarchy Error TT. • b00: Instruction • b01: Data • b10: Generic TT • b11: Reserved TT LL: Cache Hierarchy Error LL • b00: Level 0 (core L1 cache) • b01: Level 1 (core L2 cache) • b10: Level 2 (L3/LLC cache) • b11: Generic LL For Simple Error, bit[2:0]: • b000: No Error • b001: Unclassified Error • b010: Microcode ROM Parity Error • b011: External Error • b100: FRC Error • b101: Internal Parity Error • b110-b111: Simple Error Following are examples of supported codes: • 0x0174 - Eviction Error (e.g. WBINVD) • 0x0134 - L1 Data Read Error • 0x0144 - L1 Data Store Error • 0x0164 - L1 Data Prefetch Error • 0x0184 - L1 Data Snoop Error

69.2.111 (40Ah) IA32_MC2_ADDR (FEC)

MCA Address Register. Only a write of all 0s is allowed by WRMSR microcode.

MSR Address: 40Ah				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	Core	-	-	Reserved.
47:0	Core	0h	RW	**ADDRESS —** Linear Address[47:0] for I$ or ITAG and Physical Address [39:0] for SNOOP ITAG PARITY ERROR.

69.2.112 (40Ch) IA32_MC3_CTL (MEC)

MCA Control Register. MRM b1598713:Dont #GP on writing ones to the upper part of MCi_CTL because the software model always write one to the whole 64bit.

MSR Address: 40Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:2	Core	-	-	Reserved.
1	Core	0h	RW	**L1_TAG_PERR_UNCORR —** Enable uncorrectable data cache errors.
0	Core	0h	RW	**L1_DATA_PERR_UNCORR —** Enable uncorrectable tag array errors.

69.2.113 (40Dh) IA32_MC3_STATUS (MEC)

MCA Status Register. WRMSR microcode

The SoC generates #GP on non-zero writes.

MSR Address: 40Dh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Core	0h	RW	**VAL —** Valid bit for the bank.
62	Core	0h	RW	**OVER —** Bank overflowed (you missed one).
61	Core	0h	RW	**UC —** Error was uncorrectable.
60	Core	0h	RW	**EN —** Error was enabled.
59	Core	-	-	Reserved.
58	Core	0h	RW	**ADDRV —** Address is valid.
57	Core	0h	RW	**PCC —** Processor context corrupt.
56:21	Core	-	-	Reserved.
20:16	Core	0h	RW	**MODEL_SPECIFIC_ERROR_CODE —** Model specific error code.
15:0	Core	0h	RW	**MCA_ERROR_CODE —** Machine check error code.

69.2.114 (40Eh) IA32_MC3_ADDR (MEC)

MCA Address Register. WRMSR microcode

The SoC generates #GP on non-zero writes.

MSR Address: 40Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:40	Core	-	-	Reserved.
39:0	Core	0h	RW	**ADDRESS —** The address in the address register.

69.2.115 (410h) IA32_MC4_CTL (SA)

Machine Check Architecture Control MSR.

MSR Address: 410h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RO	**EE63** — Error Enable 63
62	Package	0h	RO	**EE62** — Error Enable 62
61	Package	0h	RO	**EE61** — Error Enable 61
60	Package	0h	RO	**EE60** — Error Enable 60
59	Package	0h	RO	**EE59** — Error Enable 59
58	Package	0h	RO	**EE58** — Error Enable 58
57	Package	0h	RO	**EE57** — Error Enable 57
56	Package	0h	RO	**EE56** — Error Enable 56
55	Package	0h	RO	**EE55** — Error Enable 55
54	Package	0h	RO	**EE54** — Error Enable 54
53	Package	0h	RO	**EE53** — Error Enable 53
52	Package	0h	RO	**EE52** — Error Enable 52
51	Package	0h	RO	**EE51** — Error Enable 51
50	Package	0h	RO	**EE50** — Error Enable 50
49	Package	0h	RO	**EE49** — Error Enable 49
48	Package	0h	RO	**EE48** — Error Enable 48
47	Package	0h	RO	**EE47** — Error Enable 47
46	Package	0h	RO	**EE46** — Error Enable 46
45	Package	0h	RO	**EE45** — Error Enable 45
44	Package	0h	RO	**EE44** — Error Enable 44
43	Package	0h	RO	**EE43** — Error Enable 43
42	Package	0h	RO	**EE42** — Error Enable 42
41	Package	0h	RO	**EE41** — Error Enable 41
40	Package	0h	RO	**EE40** — Error Enable 40
39	Package	0h	RO	**EE39** — Error Enable 39
38	Package	0h	RO	**EE38** — Error Enable 38
37	Package	0h	RO	**EE37** — Error Enable 37
36	Package	0h	RO	**EE36** — Error Enable 36
35	Package	0h	RO	**EE35** — Error Enable 35
34	Package	0h	RO	**EE34** — Error Enable 34
33	Package	0h	RO	**EE33** — Error Enable 33
32	Package	0h	RO	**EE32** — Error Enable 32
31	Package	0h	RO	**EE31** — Error Enable 31
30	Package	0h	RO	**EE30** — Error Enable 30
29	Package	0h	RO	**EE29** — Error Enable 29
28	Package	0h	RO	**EE28** — Error Enable 28
27	Package	0h	RO	**EE27** — Error Enable 27
26	Package	0h	RO	**EE26** — Error Enable 26

MSR Address: 410h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
25	Package	0h	RO	**EE25 —** Error Enable 25
24	Package	0h	RO	**EE24 —** Error Enable 24
23	Package	0h	RO	**EE23 —** Error Enable 23
22	Package	0h	RO	**EE22 —** Error Enable 22
21	Package	0h	RO	**EE21 —** Error Enable 21
20	Package	0h	RO	**EE20 —** Error Enable 20
19	Package	0h	RO	**EE19 —** Error Enable 19
18	Package	0h	RO	**EE18 —** Error Enable 18
17	Package	0h	RO	**EE17 —** Error Enable 17
16	Package	0h	RO	**EE16 —** Error Enable 16
15	Package	0h	RO	**EE15 —** Error Enable 15
14	Package	0h	RO	**EE14 —** Error Enable 14
13	Package	0h	RO	**EE13 —** Error Enable 13
12	Package	0h	RO	**EE12 —** Error Enable 12
11	Package	0h	RO	**EE11 —** Error Enable 11
10	Package	0h	RO	**EE10 —** Error Enable 10
9	Package	0h	RO	**EE09 —** Error Enable 09
8	Package	0h	RO	**EE08 —** Error Enable 08
7	Package	0h	RO	**EE07 —** Error Enable 07
6	Package	0h	RO	**XUCODE_ERR —** Error Enable 06
5	Package	0h	RO	**EE05 —** Error Enable 05
4	Package	0h	RO	**EE04 —** Error Enable 04
3	Package	0h	RO	**EE03 —** Error Enable 03
2	Package	0h	RO	**EE02 —** Error Enable 02
1	Package	0h	RO	**EE01 —** Error Enable 01
0	Package	0h	RO	**EE00 —** Error Enable 00

69.2.116 (411h) IA32_MC4_STATUS (SA)

Machine Check Architecture Status MSR.

MSR Address: 411h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Core	0h	RW	**VAL —** Valid bit - Indicates the information in this register is for a valid error report.
62	Core	0h	RW	**OVER —** Machine check overflow - Indicates that there was another error already written to this register which is still in the handler (i.e., the VAL bit was already set when this error occurred).
61	Core	0h	RW	**UC —** Uncorrected Error - Signifies the error being reported went uncorrected.
60	Core	0h	RW	**EN —** MCI_CTL register has the associated Error Enable bit set.
59	Core	-	-	Reserved.
58	Core	0h	RW	**ADDRV —** MCI_ADDR register holds valid data.
57	Core	0h	RW	**PCC —** Processor Context Corrupt - Indicates that the processor state may have been corrupted by this MCA event.
56:53	Core	-	-	Reserved.
52:38	Core	0h	RW	**CORRECTED_ERROR_COUNT —** Indicates the number of corrected errors.

MSR Address: 411h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
37:32	Core	-	-	Reserved.
31:16	Core	0h	RW	**MSCOD** - Model Specific Error Code • 0x0000 - Tag Parity Error • 0x0001 - Data Parity Error • 0x0010 - Tag Parity Error • 0x0011 - Data Parity Error • 0x0004 - Internal Error
15:0	Core	-	RWS-O	**MCACOD** - Machine Check Architecture Code Refer to Intel® 64 and IA-32 Architectures Software Developer Manual, Volume 3A: System Programming Guide, Part 1. Bit[15:11] can be any value between 0x0-0x1f. Bit[8] will set to 0x1 when Cache Hierarchy Error. For the lower 8 bits, the compound error code Format: bRRRR TTLL RRRR: Cache Hierarchy Error RRRR. • b0000: Generic Error • b0001: Generic Read • b0010: Generic Write • b0011: Data Read • b0100: Data Write • b0101: Instruction Fetch • b0110: Prefetch • b0111: Eviction • b1000: Snoop • b1001-b1111: Reserved RRRR TT: Cache Hierarchy Error TT. • b00: Instruction • b01: Data • b10: Generic TT • b11: Reserved TT LL: Cache Hierarchy Error LL • b00: Level 0 (core L1 cache) • b01: Level 1 (core L2 cache) • b10: Level 2 (L3/LLC cache) • b11: Generic LL For Simple Error, bit[2:0]: • b000: No Error • b001: Unclassified Error • b010: Microcode ROM Parity Error • b011: External Error • b100: FRC Error • b101: Internal Parity Error • b110-b111: Simple Error Following are examples of supported codes: • 0x0174 - Eviction Error (e.g. WBINVD) • 0x0134 - L1 Data Read Error • 0x0144 - L1 Data Store Error • 0x0164 - L1 Data Prefetch Error • 0x0184 - L1 Data Snoop Error

69.2.117 (412h) IA32_MC4_ADDR (SA)

Machine Check Architecture Address MSR.

MSR Address: 412h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Package	0h	RW	**ENH_MCA_AVAIL —** Available when enhanced MCA is in use.

69.2.118 (413h) IA32_MC4_MISC (SA)

PCU Machine Check Architecture Misc MSR.

MSR Address: 413h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:9	Package	0h	RW	**MODEL_SPECIFIC_INFO —** Available when enhanced MCA is in use.
8:6	Package	0h	RW	**ADDRESS_MODE —** This field contains the address mode for the recorded address. The options are: • 000 -> Segment Offset • 001 -> Linear Address • 010 -> Physical Address
5:0	Package	0h	RW	**RECOVERABLE_ADDRESS_LSB —** This field contains the LSB of the recoverable error address.

69.2.119 (414h) IA32_MC5_CTL (PMU)

Machine Check Architecture Control MSR.

MSR Address: 414h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RO	**EE63** — Error Enable 63
62	Package	0h	RO	**EE62** — Error Enable 62
61	Package	0h	RO	**EE61** — Error Enable 61
60	Package	0h	RO	**EE60** — Error Enable 60
59	Package	0h	RO	**EE59** — Error Enable 59
58	Package	0h	RO	**EE58** — Error Enable 58
57	Package	0h	RO	**EE57** — Error Enable 57
56	Package	0h	RO	**EE56** — Error Enable 56
55	Package	0h	RO	**EE55** — Error Enable 55
54	Package	0h	RO	**EE54** — Error Enable 54
53	Package	0h	RO	**EE53** — Error Enable 53
52	Package	0h	RO	**EE52** — Error Enable 52
51	Package	0h	RO	**EE51** — Error Enable 51
50	Package	0h	RO	**EE50** — Error Enable 50
49	Package	0h	RO	**EE49** — Error Enable 49
48	Package	0h	RO	**EE48** — Error Enable 48
47	Package	0h	RO	**EE47** — Error Enable 47
46	Package	0h	RO	**EE46** — Error Enable 46
45	Package	0h	RO	**EE45** — Error Enable 45
44	Package	0h	RO	**EE44** — Error Enable 44
43	Package	0h	RO	**EE43** — Error Enable 43
42	Package	0h	RO	**EE42** — Error Enable 42
41	Package	0h	RO	**EE41** — Error Enable 41
40	Package	0h	RO	**EE40** — Error Enable 40
39	Package	0h	RO	**EE39** — Error Enable 39
38	Package	0h	RO	**EE38** — Error Enable 38
37	Package	0h	RO	**EE37** — Error Enable 37
36	Package	0h	RO	**EE36** — Error Enable 36
35	Package	0h	RO	**EE35** — Error Enable 35
34	Package	0h	RO	**EE34** — Error Enable 34
33	Package	0h	RO	**EE33** — Error Enable 33
32	Package	0h	RO	**EE32** — Error Enable 32
31	Package	0h	RO	**EE31** — Error Enable 31
30	Package	0h	RO	**EE30** — Error Enable 30
29	Package	0h	RO	**EE29** — Error Enable 29
28	Package	0h	RO	**EE28** — Error Enable 28
27	Package	0h	RO	**EE27** — Error Enable 27
26	Package	0h	RO	**EE26** — Error Enable 26

MSR Address: 414h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
25	Package	0h	RO	**EE25 —** Error Enable 25
24	Package	0h	RO	**EE24 —** Error Enable 24
23	Package	0h	RO	**EE23 —** Error Enable 23
22	Package	0h	RO	**EE22 —** Error Enable 22
21	Package	0h	RO	**EE21 —** Error Enable 21
20	Package	0h	RO	**EE20 —** Error Enable 20
19	Package	0h	RO	**EE19 —** Error Enable 19
18	Package	0h	RO	**EE18 —** Error Enable 18
17	Package	0h	RO	**EE17 —** Error Enable 17
16	Package	0h	RO	**EE16 —** Error Enable 16
15	Package	0h	RO	**EE15 —** Error Enable 15
14	Package	0h	RO	**EE14 —** Error Enable 14
13	Package	0h	RO	**EE13 —** Error Enable 13
12	Package	0h	RO	**EE12 —** Error Enable 12
11	Package	0h	RO	**EE11 —** Error Enable 11
10	Package	0h	RO	**EE10 —** Error Enable 10
9	Package	0h	RO	**EE09 —** Error Enable 09
8	Package	0h	RO	**EE08 —** Error Enable 08
7	Package	0h	RO	**EE07 —** Error Enable 07
6	Package	0h	RO	**EE06 —** Error Enable 06
5	Package	0h	RO	**EE05 —** Error Enable 05
4	Package	0h	RO	**EE04 —** Error Enable 04
3	Package	0h	RO	**EE03 —** Error Enable 03
2	Package	0h	RO	**EN_PCU_FW_ERR —** Error Enable 02
1	Package	0h	RO	**EN_PCU_UC_ERR —** Error Enable 01
0	Package	0h	RO	**EN_PCU_HW_ERR —** Error Enable 00

69.2.120 (415h) IA32_MC5_STATUS (PMU)

Machine Check Architecture Status MSR.

MSR Address: 415h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW	**VAL —** MCi_STATUS Register Valid.
62	Package	0h	RW	**OVER —** Error Overflow.
61	Package	0h	RW	**UC —** Uncorrected Error.
60	Package	0h	RW	**EN —** Error Reporting Enabled.
59	Package	0h	RW	**MISCV —** MCi_MISC Register Valid.
58	Package	0h	RW	**ADDRV —** MCi_ADDR Register Valid.
57	Package	0h	RW	**PCC —** Processor Context Corrupted.
56	Package	0h	RW	**S —** Signaling an uncorrected recoverable (UCR) error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
55	Package	0h	RW	**AR —** Recovery Action Required for UCR Error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
54:53	Package	0h	RW	**TES —** Threshold-Based Error Status - When MCG_CAP11 is not set, these bits are model specific.
52:38	Package	0h	RW	**CORRECTED_ERROR_COUNT —** Corrected error count.
37:32	Package	0h	RW	**OTHER_INFO —** Other information.
31:16	Package	0h	RW	**MSCOD —** Model specific Error Code.
15:0	Package	0h	RW	**MCACOD —** MCA Error Code.

69.2.121 (416h) IA32_MC5_ADDR (PMU)

Machine Check Architecture Address MSR.

MSR Address: 416h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Package	0h	RW	**ENH_MCA_AVAIL —** Available when enhanced MCA is in use.

69.2.122 (417h) IA32_MC5_MISC (PMU)

PCU Machine Check Architecture Misc MSR.

MSR Address: 417h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:9	Package	0h	RW	**MODEL_SPECIFIC_INFO —** Available when enhanced MCA is in use.
8:6	Package	0h	RW	**ADDRESS_MODE —** This field contains the address mode for the recorded address. The options are: • 000 -> Segment Offset • 001 -> Linear Address • 010 -> Physical Address
5:0	Package	0h	RW	**RECOVERABLE_ADDRESS_LSB —** This field contains the LSB of the recoverable error address.

69.2.123 (418h) IA32_MC6_CTL (SA)

Machine Check Architecture Control MSR.

MSR Address: 418h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RO	**EE63** — Error Enable 63
62	Package	0h	RO	**EE62** — Error Enable 62
61	Package	0h	RO	**EE61** — Error Enable 61
60	Package	0h	RO	**EE60** — Error Enable 60
59	Package	0h	RO	**EE59** — Error Enable 59
58	Package	0h	RO	**EE58** — Error Enable 58
57	Package	0h	RO	**EE57** — Error Enable 57
56	Package	0h	RO	**EE56** — Error Enable 56
55	Package	0h	RO	**EE55** — Error Enable 55
54	Package	0h	RO	**EE54** — Error Enable 54
53	Package	0h	RO	**EE53** — Error Enable 53
52	Package	0h	RO	**EE52** — Error Enable 52
51	Package	0h	RO	**EE51** — Error Enable 51
50	Package	0h	RO	**EE50** — Error Enable 50
49	Package	0h	RO	**EE49** — Error Enable 49
48	Package	0h	RO	**EE48** — Error Enable 48
47	Package	0h	RO	**EE47** — Error Enable 47
46	Package	0h	RO	**EE46** — Error Enable 46
45	Package	0h	RO	**EE45** — Error Enable 45
44	Package	0h	RO	**EE44** — Error Enable 44
43	Package	0h	RO	**EE43** — Error Enable 43
42	Package	0h	RO	**EE42** — Error Enable 42
41	Package	0h	RO	**EE41** — Error Enable 41
40	Package	0h	RO	**EE40** — Error Enable 40
39	Package	0h	RO	**EE39** — Error Enable 39
38	Package	0h	RO	**EE38** — Error Enable 38
37	Package	0h	RO	**EE37** — Error Enable 37
36	Package	0h	RO	**EE36** — Error Enable 36
35	Package	0h	RO	**EE35** — Error Enable 35
34	Package	0h	RO	**EE34** — Error Enable 34
33	Package	0h	RO	**EE33** — Error Enable 33
32	Package	0h	RO	**EE32** — Error Enable 32
31	Package	0h	RO	**EE31** — Error Enable 31
30	Package	0h	RO	**EE30** — Error Enable 30
29	Package	0h	RO	**EE29** — Error Enable 29
28	Package	0h	RO	**EE28** — Error Enable 28
27	Package	0h	RO	**EE27** — Error Enable 27
26	Package	0h	RO	**EE26** — Error Enable 26

MSR Address: 418h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
25	Package	0h	RO	**EE25 —** Error Enable 25
24	Package	0h	RO	**EE24 —** Error Enable 24
23	Package	0h	RO	**EE23 —** Error Enable 23
22	Package	0h	RO	**EE22 —** Error Enable 22
21	Package	0h	RO	**EE21 —** Error Enable 21
20	Package	0h	RO	**EE20 —** Error Enable 20
19	Package	0h	RO	**EE19 —** Error Enable 19
18	Package	0h	RO	**EE18 —** Error Enable 18
17	Package	0h	RO	**EE17 —** Error Enable 17
16	Package	0h	RO	**EE16 —** Error Enable 16
15	Package	0h	RO	**EE15 —** Error Enable 15
14	Package	0h	RO	**EE14 —** Error Enable 14
13	Package	0h	RO	**EE13 —** Error Enable 13
12	Package	0h	RO	**EE12 —** Error Enable 12
11	Package	0h	RO	**EE11 —** Error Enable 11
10	Package	0h	RO	**EE10 —** Error Enable 10
9	Package	0h	RO	**EE09 —** Error Enable 09
8	Package	0h	RO	**EE08 —** Error Enable 08
7	Package	0h	RO	**EE07 —** Error Enable 07
6	Package	0h	RO	**EE06 —** Error Enable 06
5	Package	0h	RO	**EE05 —** Error Enable 05
4	Package	0h	RO	**EE04 —** Error Enable 04
3	Package	0h	RO	**EE03 —** Error Enable 03
2	Package	0h	RO	**EE02 —** Error Enable 02
1	Package	0h	RO	**EE01 —** Error Enable 01
0	Package	0h	RO	**EE00 —** Error Enable 00

69.2.124 (419h) IA32_MC6_STATUS (SA)

Machine Check Architecture Status MSR.

MSR Address: 419h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW	**VAL —** MCi_STATUS Register Valid.
62	Package	0h	RW	**OVER —** Error Overflow.
61	Package	0h	RW	**UC —** Uncorrected Error.
60	Package	0h	RW	**EN —** Error Reporting Enabled.
59	Package	0h	RW	**MISCV —** MCi_MISC Register Valid.
58	Package	0h	RW	**ADDRV —** MCi_ADDR Register Valid.
57	Package	0h	RW	**PCC —** Processor Context Corrupted.
56	Package	0h	RW	**S —** Signaling an uncorrected recoverable (UCR) error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
55	Package	0h	RW	**AR —** Recovery Action Required for UCR Error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
54:53	Package	0h	RW	**TES —** Threshold-Based Error Status - When MCG_CAP11 is not set, these bits are model specific.
52:38	Package	0h	RW	**CORRECTED_ERROR_COUNT —** Corrected error count.
37:32	Package	0h	RW	**OTHER_INFO —** Other information.
31:16	Package	0h	RW	**MSCOD —** Model specific Error Code.
15:0	Package	0h	RW	**MCACOD —** MCA Error Code.

69.2.125 (41Ah) IA32_MC6_ADDR (SA)

Machine Check Architecture Address MSR.

MSR Address: 41Ah				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Package	0h	RW	**ENH_MCA_AVAIL —** Available when enhanced MCA is in use.

69.2.126 (41Ch) IA32_MC7_CTL (MEM 0)

Machine Check Architecture Control MSR.

MSR Address: 41Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RO	**EE63** — Error Enable 63
62	Package	0h	RO	**EE62** — Error Enable 62
61	Package	0h	RO	**EE61** — Error Enable 61
60	Package	0h	RO	**EE60** — Error Enable 60
59	Package	0h	RO	**EE59** — Error Enable 59
58	Package	0h	RO	**EE58** — Error Enable 58
57	Package	0h	RO	**EE57** — Error Enable 57
56	Package	0h	RO	**EE56** — Error Enable 56
55	Package	0h	RO	**EE55** — Error Enable 55
54	Package	0h	RO	**EE54** — Error Enable 54
53	Package	0h	RO	**EE53** — Error Enable 53
52	Package	0h	RO	**EE52** — Error Enable 52
51	Package	0h	RO	**EE51** — Error Enable 51
50	Package	0h	RO	**EE50** — Error Enable 50
49	Package	0h	RO	**EE49** — Error Enable 49
48	Package	0h	RO	**EE48** — Error Enable 48
47	Package	0h	RO	**EE47** — Error Enable 47
46	Package	0h	RO	**EE46** — Error Enable 46
45	Package	0h	RO	**EE45** — Error Enable 45
44	Package	0h	RO	**EE44** — Error Enable 44
43	Package	0h	RO	**EE43** — Error Enable 43
42	Package	0h	RO	**EE42** — Error Enable 42
41	Package	0h	RO	**EE41** — Error Enable 41
40	Package	0h	RO	**EE40** — Error Enable 40
39	Package	0h	RO	**EE39** — Error Enable 39
38	Package	0h	RO	**EE38** — Error Enable 38
37	Package	0h	RO	**EE37** — Error Enable 37
36	Package	0h	RO	**EE36** — Error Enable 36
35	Package	0h	RO	**EE35** — Error Enable 35
34	Package	0h	RO	**EE34** — Error Enable 34
33	Package	0h	RO	**EE33** — Error Enable 33
32	Package	0h	RO	**EE32** — Error Enable 32
31	Package	0h	RO	**EE31** — Error Enable 31
30	Package	0h	RO	**EE30** — Error Enable 30
29	Package	0h	RO	**EE29** — Error Enable 29
28	Package	0h	RO	**EE28** — Error Enable 28
27	Package	0h	RO	**EE27** — Error Enable 27
26	Package	0h	RO	**EE26** — Error Enable 26

MSR Address: 41Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
25	Package	0h	RO	**EE25 —** Error Enable 25
24	Package	0h	RO	**EE24 —** Error Enable 24
23	Package	0h	RO	**EE23 —** Error Enable 23
22	Package	0h	RO	**EE22 —** Error Enable 22
21	Package	0h	RO	**EE21 —** Error Enable 21
20	Package	0h	RO	**EE20 —** Error Enable 20
19	Package	0h	RO	**EE19 —** Error Enable 19
18	Package	0h	RO	**EE18 —** Error Enable 18
17	Package	0h	RO	**EE17 —** Error Enable 17
16	Package	0h	RO	**EE16 —** Error Enable 16
15	Package	0h	RO	**EE15 —** Error Enable 15
14	Package	0h	RO	**EE14 —** Error Enable 14
13	Package	0h	RO	**EE13 —** Error Enable 13
12	Package	0h	RO	**EE12 —** Error Enable 12
11	Package	0h	RO	**EE11 —** Error Enable 11
10	Package	0h	RO	**EE10 —** Error Enable 10
9	Package	0h	RO	**EE09 —** Error Enable 09
8	Package	0h	RO	**EE08 —** Error Enable 08
7	Package	0h	RO	**EE07 —** Error Enable 07
6	Package	0h	RO	**EE06 —** Error Enable 06
5	Package	0h	RO	**EE05 —** Error Enable 05
4	Package	0h	RO	**EE04 —** Error Enable 04
3	Package	0h	RO	**EE03 —** Error Enable 03
2	Package	0h	RO	**EE02 —** Error Enable 02
1	Package	0h	RO	**EE01 —** Error Enable 01
0	Package	0h	RO	**EE00 —** Error Enable 00

69.2.127 (41Dh) IA32_MC7_STATUS (MEM 0)

Machine Check Architecture Status MSR.

MSR Address: 41Dh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW	**VAL —** MCi_STATUS Register Valid.
62	Package	0h	RW	**OVER —** Error Overflow.
61	Package	0h	RW	**UC —** Uncorrected Error.
60	Package	0h	RW	**EN —** Error Reporting Enabled.
59	Package	0h	RW	**MISCV —** MCi_MISC Register Valid.
58	Package	0h	RW	**ADDRV —** MCi_ADDR Register Valid.
57	Package	0h	RW	**PCC —** Processor Context Corrupted.
56	Package	0h	RW	**S —** Signaling an uncorrected recoverable (UCR) error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
55	Package	0h	RW	**AR —** Recovery Action Required for UCR Error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
54:53	Package	0h	RW	**TES —** Threshold-Based Error Status - When MCG_CAP11 is not set, these bits are model specific.
52:38	Package	0h	RW	**CORRECTED_ERROR_COUNT —** Corrected error count.
37:32	Package	0h	RW	**OTHER_INFO —** Other information.
31:16	Package	0h	RW-O	**MSCOD —** Model specific Error Code. • 0x0200 - BT Timeout Error • 0x0100 - Internal Parity • 0x0080 - Internal Parity • 0x0040 - Internal Parity • 0x0020 - Internal Parity • 0x0010 - RTID Error • 0x0008 - Internal Error • 0x0004 - Partial Write Error • 0x0002 - Data Buffer Parity Error • 0x0001 - Memory Read Error • All others reserved.
15:0	Package	0h	-	**MCCOD —** Specifies the machine check architecture defined error code for the machine check error condition detected. Data Read Error: 0000 0000 1001 CCCC; Generic Error: 0000 0000 1000 CCCC; (HADB Parity, RTID out Range, BGF, etc.) Write Error: 0000 0000 1010 CCCC; (Partial Write, etc.) Replace CCCC with channel number. • Ch 0 = 0000b • Ch 1 = 0001b • Ch 2 = 0010b • Ch 3 = 0011b If the channel number can not be specified, such as request from Cbo and RTID out of range, use encode 1111.

69.2.128 (41Fh) IA32_MC7_MISC (MEM 0)

PCU Machine Check Architecture Misc MSR.

MSR Address: 41Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:9	Package	0h	RW	**MODEL_SPECIFIC_INFO —** Available when enhanced MCA is in use.
8:6	Package	0h	RW	**ADDRESS_MODE —** This field contains the address mode for the recorded address. The options are: • 000 -> Segment Offset • 001 -> Linear Address • 010 -> Physical Address
5:0	Package	0h	RW	**RECOVERABLE_ADDRESS_LSB —** This field contains the LSB of the recoverable error address.

69.2.129 (420h) IA32_MC8_CTL (MEM 1)

Machine Check Architecture Control MSR.

MSR Address: 420h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RO	**EE63** — Error Enable 63
62	Package	0h	RO	**EE62** — Error Enable 62
61	Package	0h	RO	**EE61** — Error Enable 61
60	Package	0h	RO	**EE60** — Error Enable 60
59	Package	0h	RO	**EE59** — Error Enable 59
58	Package	0h	RO	**EE58** — Error Enable 58
57	Package	0h	RO	**EE57** — Error Enable 57
56	Package	0h	RO	**EE56** — Error Enable 56
55	Package	0h	RO	**EE55** — Error Enable 55
54	Package	0h	RO	**EE54** — Error Enable 54
53	Package	0h	RO	**EE53** — Error Enable 53
52	Package	0h	RO	**EE52** — Error Enable 52
51	Package	0h	RO	**EE51** — Error Enable 51
50	Package	0h	RO	**EE50** — Error Enable 50
49	Package	0h	RO	**EE49** — Error Enable 49
48	Package	0h	RO	**EE48** — Error Enable 48
47	Package	0h	RO	**EE47** — Error Enable 47
46	Package	0h	RO	**EE46** — Error Enable 46
45	Package	0h	RO	**EE45** — Error Enable 45
44	Package	0h	RO	**EE44** — Error Enable 44
43	Package	0h	RO	**EE43** — Error Enable 43
42	Package	0h	RO	**EE42** — Error Enable 42
41	Package	0h	RO	**EE41** — Error Enable 41
40	Package	0h	RO	**EE40** — Error Enable 40
39	Package	0h	RO	**EE39** — Error Enable 39
38	Package	0h	RO	**EE38** — Error Enable 38
37	Package	0h	RO	**EE37** — Error Enable 37
36	Package	0h	RO	**EE36** — Error Enable 36
35	Package	0h	RO	**EE35** — Error Enable 35
34	Package	0h	RO	**EE34** — Error Enable 34
33	Package	0h	RO	**EE33** — Error Enable 33
32	Package	0h	RO	**EE32** — Error Enable 32
31	Package	0h	RO	**EE31** — Error Enable 31
30	Package	0h	RO	**EE30** — Error Enable 30
29	Package	0h	RO	**EE29** — Error Enable 29
28	Package	0h	RO	**EE28** — Error Enable 28
27	Package	0h	RO	**EE27** — Error Enable 27
26	Package	0h	RO	**EE26** — Error Enable 26

MSR Address: 420h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
25	Package	0h	RO	**EE25 —** Error Enable 25
24	Package	0h	RO	**EE24 —** Error Enable 24
23	Package	0h	RO	**EE23 —** Error Enable 23
22	Package	0h	RO	**EE22 —** Error Enable 22
21	Package	0h	RO	**EE21 —** Error Enable 21
20	Package	0h	RO	**EE20 —** Error Enable 20
19	Package	0h	RO	**EE19 —** Error Enable 19
18	Package	0h	RO	**EE18 —** Error Enable 18
17	Package	0h	RO	**EE17 —** Error Enable 17
16	Package	0h	RO	**EE16 —** Error Enable 16
15	Package	0h	RO	**EE15 —** Error Enable 15
14	Package	0h	RO	**EE14 —** Error Enable 14
13	Package	0h	RO	**EE13 —** Error Enable 13
12	Package	0h	RO	**EE12 —** Error Enable 12
11	Package	0h	RO	**EE11 —** Error Enable 11
10	Package	0h	RO	**EE10 —** Error Enable 10
9	Package	0h	RO	**EE09 —** Error Enable 09
8	Package	0h	RO	**EE08 —** Error Enable 08
7	Package	0h	RO	**EE07 —** Error Enable 07
6	Package	0h	RO	**EE06 —** Error Enable 06
5	Package	0h	RO	**EE05 —** Error Enable 05
4	Package	0h	RO	**EE04 —** Error Enable 04
3	Package	0h	RO	**EE03 —** Error Enable 03
2	Package	0h	RO	**EE02 —** Error Enable 02
1	Package	0h	RO	**EE01 —** Error Enable 01
0	Package	0h	RO	**EE00 —** Error Enable 00

69.2.130 (421h) IA32_MC8_STATUS (MEM 1)

Machine Check Architecture Status MSR.

MSR Address: 421h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW	**VAL —** MCi_STATUS Register Valid.
62	Package	0h	RW	**OVER —** Error Overflow.
61	Package	0h	RW	**UC —** Uncorrected Error.
60	Package	0h	RW	**EN —** Error Reporting Enabled.
59	Package	0h	RW	**MISCV —** MCi_MISC Register Valid.
58	Package	0h	RW	**ADDRV —** MCi_ADDR Register Valid.
57	Package	0h	RW	**PCC —** Processor Context Corrupted.
56	Package	0h	RW	**S —** Signaling an uncorrected recoverable (UCR) error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
55	Package	0h	RW	**AR —** Recovery Action Required for UCR Error - When MCG_CAP11 or MCG_CAP24 are not set, these bits are reserved or model specific.
54:53	Package	0h	RW	**TES —** Threshold-Based Error Status - When MCG_CAP11 is not set, these bits are model specific.
52:38	Package	0h	RW	**CORRECTED_ERROR_COUNT —** Corrected error count.
37:32	Package	0h	RW	**OTHER_INFO —** Other information.
31:16	Package	0h	RW	**MSCOD —** Model specific Error Code.
15:0	Package	0h	RW	**MCACOD —** MCA Error Code.

69.2.131 (423h) IA32_MC8_MISC (MEM 1)

PCU Machine Check Architecture Misc MSR.

MSR Address: 423h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:9	Package	0h	RW	**MODEL_SPECIFIC_INFO —** Available when enhanced MCA is in use.
8:6	Package	0h	RW	**ADDRESS_MODE —** This field contains the address mode for the recorded address. The options are: • 000 -> Segment Offset • 001 -> Linear Address • 010 -> Physical Address
5:0	Package	0h	RW	**RECOVERABLE_ADDRESS_LSB —** This field contains the LSB of the recoverable error address.

69.2.132 (4C1h) IA32_A_PMC0

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

MSR Address: 4C1h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

69.2.133 (4C2h) IA32_A_PMC1

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

MSR Address: 4C2h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

69.2.134 (4C3h) IA32_A_PMC2

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

MSR Address: 4C3h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

69.2.135 (4C4h) IA32_A_PMC3

Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for complete details on MSRs related to Performance Monitoring.

MSR Address: 4C4h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a complete details on MSRs related to Performance Monitoring.

69.2.136 (4E0h) MSR_SMM_FEATURE_CONTROL

This MSR holds enable bits for on-chip storage of SMM and Code Access Check Violation features. This MSR can be written only from within SMM but can be read by SMM and non SMM code. This MSR is cleared only on cold reset.

MSR Address: 4E0h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:3	Package	-	-	Reserved.
2	Package	0h	RW	**SMM_CODE_CHK_EN —** If 1, generate unrecoverable MCHK on code fetch outside SMRR. If 0, do not report any errors for code fetch outside SMRR.
1	Package	-	-	Reserved.
0	Package	0h	RW	**LOCK —** If Lock = 1, CPU will drop writes to the MSR If Lock = 0, CPU will allow update to b[2:0].

69.2.137 (4E2h) MSR_SMM_DELAYED

This MSR contains bit per logical processor indicating whether the logical processor is in the middle of long flow and hence will delay servicing of SMI. SMI will be serviced after the long flow completes execution.

MSR Address: 4E2h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:16	Package	-	-	Reserved.
15:0	Package	0h	SMM-RO	**LOG_PROC_STATE —** Each bit represents a logical processor of its state in a long flow of internal operation which delays servicing an interrupt. The corresponding bit will be set at the start of long events such as: - Microcode Update Load - C6 - WBINVD - Ratio Change - Throttle The bit is automatically cleared at the end of each long event. The reset value of this field is 0. Only bit positions below N = CPUID.(EAX=0BH, ECX=PKG_LVL):EBX[15:0] can be updated.

69.2.138 (4E3h) MSR_SMM_BLOCKED

This MSR contains bit per logical processor indicating whether the logical processor is in state where SMIs are blocked and hence will not be able to service SMI. SMI can be serviced after the logical processor exits the state in which SMIs are blocked.

MSR Address: 4E3h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:16	Package	-	-	Reserved.
15:0	Package	FFFFh	SMM-RO	**LOG_PROC —** Each bit represents a logical processor of its blocked state to service an SMI. The corresponding bit will be set if the logical processor is in one of the following states: - Wait For SIPI - SENTER Sleep The reset value of this field is 0FFFH. Only bit positions below N = CPUID.(EAX=0BH, ECX=PKG_LVL):EBX[15:0] can be updated.

69.2.139 (500h) IA32_SGX_SVN_STATUS

MSR Address: 500h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:24	-	-	-	Reserved.
23:16	Package	0h	RO	**SINIT_SE_SVN —** Since the SoC does not support SINIT, this bit field is always 0. 0
15:1	-	-	-	Reserved.
0	Package	0h	RO	**LOCK —** If 1, indicates that a non-faulting Intel® SGX instruction has been executed. If 0, indicates that the processor will allow a properly signed Authenticated Code Modules (ACMs) to launch.

69.2.140 (503h) MSR_SGX_DEBUG_MODE

This MSR does not survive warm reset.

MSR Address: 503h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:2	-	-	-	Reserved.
1	Package	0h	RO	**NPK_ACTIVE —** This read-only field indicates that the Intel® Trace Hub is active.
0	Package	0h	RW	**NPK_REQUEST —** When software sets this bit, a request is triggered to the Intel® Trace Hub to clear the Intel® Software Guard Extensions (Intel® SGX) keys.

69.2.141 (560h) IA32_RTIT_OUTPUT_BASE

This MSR is used to configure the output region of internally-buffered packets. The size of the address field is determined by the maximum physical address width (MAXPHYADDR), as reported by CPUID.80000008H:EAX[7:0].

The processor updates this MSR while when packet generation is enabled, and those updates are asynchronous to instruction execution. Therefore, the values in this MSR should be considered unreliable unless packet generation is disabled (IA32_RTIT_CTL.TraceEn = 0).

This MSR can be written only when IA32_RTIT_CTL.TraceEn is 0; otherwise WRMSR causes a general-protection fault (#GP).

MSR Address: 560h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for details on this register, including supported fields.

69.2.142 (561h) IA32_RTIT_OUTPUT_MASK_PTRS

This MSR holds the pointers that indicate the ToPA entry that is currently in use and the offset into that entry's output region to which packets are being written.

The processor updates this MSR while when packet generation is enabled, and those updates are asynchronous to instruction execution. Therefore, the values in this MSR should be considered unreliable unless packet generation is disabled (IA32_RTIT_CTL.TraceEn = 0).

This MSR can be written only when IA32_RTIT_CTL.TraceEn is 0; otherwise WRMSR causes a general-protection fault (#GP).

MSR Address: 561h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for details on this register, including supported fields.

69.2.143 (570h) IA32_RTIT_CTL

The primary enable and control MSR for trace packet generation.

MSR Address: 570h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for details on this register, including supported fields.

69.2.144 (571h) ARR_CR_RTIT_STATUSIA32_RTIT_STATUS

The IA32_RTIT_STATUS MSR is readable and writable by software, but some bits (ContextEn, TriggerEn) are read-only and cannot be directly modified. The WRMSR instruction ignores these bits in the source operand (attempts to modify these bits are ignored and do not cause WRMSR to fault).

This MSR can only be written when IA32_RTIT_CTL.TraceEn is 0; otherwise WRMSR causes a general-protection fault (#GP). The processor does not modify the value of this MSR while TraceEn is 0 (software can modify it with WRMSR).

MSR Address: 571h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for details on this register, including supported fields.

69.2.145 (572h) IA32_RTIT_CR3_MATCH

CR3 matches IA32_RTIT_CR3_MATCH if the two registers are identical for bits 63:5; the lower 5 bits of CR3 and IA32_RTIT_CR3_MATCH are not compared.

This MSR can be written only when IA32_RTIT_CTL.TraceEn is 0; otherwise WRMSR causes a general-protection fault (#GP). IA32_RTIT_CR3_MATCH[4:0] are reserved and must be 0; an attempt to set those bits using WRMSR causes a #GP.

MSR Address: 572h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Core	-	-	**DATA —** Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for details on this register, including supported fields.

69.2.146 (580h) IA32_RTIT_ADDR0_A

Region ADDR0 start address. MSR used to support EIP filtering.

MSR Address: 580h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	Thread	0h	RO	**IP0_SIGN_EXT —** On a creg read, bit 47 is sign extended into bits 63:48. This state is not stored.
47:0	Thread	0h	RW	**IP0_ADDR —** Holds the base Linear Instruction Pointer (address) for the region defined as ADDR0.

69.2.147 (581h) IA32_RTIT_ADDR0_B

Region ADDR0 end address. MSR used to support EIP filtering.

MSR Address: 581h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	Thread	0h	RO	**IP0_SIGN_EXT —** On a read, bit 47 is sign extended into bits 63:48. This state is not stored.
47:0	Thread	0h	RW	**IP0_ADDR —** Holds the limit Linear Instruction Pointer (address) for the region defined as ADDR0.

69.2.148 (582h) IA32_RTIT_ADDR1_A

Region ADDR1 start address. MSR used to support EIP filtering.

MSR Address: 582h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	Thread	0h	RO	**IP1_SIGN_EXT —** On a read, bit 47 is sign extended into bits 63:48. This state is not stored.
47:0	Thread	0h	RW	**IP1_ADDR —** Holds the base Linear Instruction Pointer (address) for the region defined as ADDR1.

69.2.149 (583h) IA32_RTIT_ADDR1_B

Region ADDR1 end address. MSR used to support EIP filtering.

MSR Address: 583h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	Thread	0h	RO	**IP1_SIGN_EXT —** On a read, bit 47 is sign extended into bits 63:48. This state is not stored.
47:0	Thread	0h	RW	**IP1_ADDR —** Holds the limit Linear Instruction Pointer (address) for the region defined as ADDR1.

69.2.150 (600h) IA32_DS_AREA

Points to the linear address of the first byte of the DS buffer management area, which is used to manage the BTS and PEBS buffers. Refer to the IA-32 Intel® Architecture Software Developer's Manual for a detailed description and usage of this MSR and the Debug Store (DS) Mechanism.

MSR Address: 600h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**DATA —** The linear address of the first byte of the DS buffer management area. Useful bits in this field depend on the address methodology in use when the register state is saved.

69.2.151 (601h) MSR_VR_CURRENT_CONFIG

This register is used to limit the current consumption of the Primary power Plane. Primary Plane refers to the Vccin power rail. The processor will read this value during Reset Phase 4. On each slow loop, the maximum current possible will be calculated and the processor will send the appropriate PS Code according to the thresholds in this register. Set power state amp thresholds to 0A in order to disable that power state.

MSR Address: 601h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:56	-	-	-	Reserved.
55:48	Package	0h	RW	**IUNIT_LL_RES —** Load line resistance in 1/2 mOhm steps for the IUNIT domain. IUNIT IccMax current will be multiplied by IUNIT_LL_RES resistance to calculate the voltage guardband necessary to manage for an IUNIT didt droop.
47:40	Package	0h	RW	**GT_LL_RES —** Load line resistance in 1/2 mOhm steps for the GT domain. GT IccMax current will be multiplied by GT_LL_RES resistance to calculate the voltage guardband necessary to manage for GT didt droop.
39:32	Package	0h	RW	**GLM_LL_RES —** Load line resistance in 1/2 mOhm steps for the GLM domain. GLM IccMax current will be multiplied by GLM_LL_RES resistance to calculate the voltage guardband necessary to manage for GLM didt droop.
31:26	-	-	-	Reserved.
25:13	Package	0h	RW	**VCCGI_PS1_ICCMAX —** Peak current supported by the VR on the VGI rail when in PS1 mode. A value of 0 indicates VR support 0A of current in PS1 which will effectively disable PS1 use. Units given in PACKAGE_POWER_SKU_UNIT.CURRENT_UNIT.
12:0	Package	0h	RW	**VCCGI_PS0_ICCMAX —** Peak current supported by the VR on the VGI rail. Assumes VR is in the highest power state possible (PS0). Units given in PACKAGE_POWER_SKU_UNIT.CURRENT_UNIT.

69.2.152 (603h) MSR_VR_MISC_CONFIG

Input voltage regulator configuration parameters.

MSR Address: 603h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:2	-	-	-	Reserved.
1	Package	1h	RW	**IDLE_ENTRY_RAMP_RATE —** Controls the VR ramp rate on package Cstate entry events. 1 fast 0 slow. If Decay is set it has priority.
0	Package	1h	RW	**IDLE_EXIT_RAMP_RATE —** Controls the VR ramp rate on package Cstate wake events. 1 fast 0 slow.

69.2.153 (606h) MSR_RAPL_POWER_UNIT

Defines units for calculating SKU power and timing parameters. PCODE will update the contents of this register.

MSR Address: 606h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:28	Package	3h	RW	**RESISTANCE_UNIT —** Specifies the number of decimal bits in which current units in this register are specified. 0: steps of 1 Ohm 1: steps of 0.5 Ohms 2: steps of 0.25 Ohms etc...
27:24	Package	3h	RW	**CURRENT_UNIT —** Specifies the number of decimal bits in which current units in this register are specified. 0: steps of 1 A 1: steps of 0.5 Amps 2: steps of 0.25 A etc...
23:20	Package	-	-	Reserved.
19:16	Package	Ah	RW	**TIME_UNIT —** Time Units used for power control registers. The actual unit value is calculated by 1 s / 2^(TIME_UNIT). The default value of Ah corresponds to 976 µs.
15:13	Package	-	-	Reserved.
12:8	Package	Eh	RW	**ENERGY_UNIT —** Energy Units used for power control registers. The actual unit value is calculated by 1 J / 2^(ENERGY_UNIT). The default value of 14 decimal corresponds to Ux.14 number.
7:4	Package	-	-	Reserved.
3:0	Package	8h	RW	**PWR_UNIT —** Power Units used for power control registers. The actual unit value is calculated by 1 W / 2^(PWR_UNIT). The default value of 0110b corresponds to 1/64 W.

69.2.154 (610h) MSR_PKG_POWER_LIMIT

The Package Power Limit Register allows platform BIOS to limit the power consumption of the processor to the specified values. POWER_LIMIT_1 and POWER_LIMIT_1_TIME are used to specify sustained long duration power limits and are around the TDP value of the processor. POWER_LIMIT_2 is used to specify the short duration power limit. The specified Power Limits are programmable only if bit 29 in PLATFORM_INFO (MSR CEh) is set. If this bit is not set then writes to this MSR will result in a GP fault.The Integrated Graphics driver CPM driver BIOS and OS can balance the power budget between the Primary Power Plane IA and the Secondary Power Plane GT via PRIMARY_PLANE_TURBO_POWER_LIMIT_MSR and SECONDARY_PLANE_TURBO_POWER_LIMIT_MSR.

MSR Address: 610h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW_L	**PKG_PWR_LIM_LOCK —** When set all settings in this register are locked and are treated as Read Only. This bit will typically set by BIOS during boot time or resume from Sx.
62:56	Package	-	-	Reserved.
55:49	Package	0h	RW_L	**PKG_PWR_LIM_2_TIME** — This indicates the short duration time window over which Power_Limit_2 value should be maintained. This field is made up of two numbers from the following equation. The processor power consumption will be controlled to the Power_Limit_2 value over an exponential weighted moving average of the time window. Time Window = (float) ((1+(X/4)) * (2 ^ Y)) Where: X = POWER_LIMIT_2_TIME[55:54] Y = POWER_LIMIT_2_TIME[53:49] The unit of measurement for this field is available from PACKAGE_POWER_SKU_UNIT (MSR 606h). It is recommended that system BIOS not update this value during runtime.
48	Package	0h	RW_L	**PKG_CLMP_LIM_2 —** When set, allows processor to go below the OS requested P States in order to maintain the power below Power_Limit_2 value specified below. Both RAPL clamp bits CRITICAL_POWER_CLAMP_[2-1] are set to 1.
47	Package	0h	RW_L	**PKG_PWR_LIM_2_EN —** When set, enables processor to apply control policies such that the package power does not exceed Power_Limit_2 value. BIOS must set Power_Limit_2_EN for proper turbo mode operation and set Power_Limit_2 field of this MSR to an appropriate value.
46:32	Package	0h	RW_L	**PKG_PWR_LIM_2 —** Short Duration Power limit value which the package must not exceed. This field is specified in the units as identified by the PACKAGE_POWER_SKU_UNIT (MSR 606h). Note: BIOS must enable Power_Limit_2 to enable Short Duration Power Limit for the processor. Recommended default value is 1.2 times the Long Duration Power Limit value (Power_Limit_1).
31:24	Package	-	-	Reserved.
23:17	Package	0h	RW_L	**PKG_PWR_LIM_1_TIME —** This indicates the time window over which Power_Limit_1 value should be maintained. This field is made up of two numbers from the following equation. The processor power consumption will be controlled to the Power_Limit_1 value over an exponential weighted moving average of the time window. Time Window = (float) ((1+(X/4)) * (2 ^ Y)) Where: X = POWER_LIMIT_1_TIME[23:22] Y = POWER_LIMIT_1_TIME[21:17] The unit of measurement for this field is available from PACKAGE_POWER_SKU_UNIT (MSR 606h). The maximum allowed value in this field is defined in PACKAGE_POWER_SKU (MSR 614h) PACKAGE_MAX_TIME field. It is recommended that system BIOS not update this value during runtime.

MSR Address: 610h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
16	Package	0h	RW_L	**PKG_CLMP_LIM_1 —** When set, allows processor to go below the OS requested P States in order to maintain the power below Power_Limit_1 value specified below. Both RAPL clamp bits CRITICAL_POWER_CLAMP_[2-1] are set to 1.
15	Package	0h	RW_L	**PKG_PWR_LIM_1_EN —** When set, enables processor to apply control policies such that the package average power does not exceed Power_Limit_1 value over over an exponential weighted moving average of the time window. This bit is always enabled indicating Power_Limit_1 is always active. Because the processor must maintain the power consumption to the TDP value, Power_Limit_1 is always enabled.
14:0	Package	0h	RW_L	**PKG_PWR_LIM_1 —** Average Power limit value which the package must not exceed over a time window as specified by Power_Limit_1_TIME field above. The processor power consumption will be controlled to the Power_Limit_1 value over an exponential weighted moving average of the time window. This field is specified in the units as identified by the PACKAGE_POWER_SKU_UNIT (MSR 606h). Initial value varies based on the SKU. It is recommended that system BIOS not update this value during runtime.

69.2.155 (614h) MSR_PKG_POWER_INFO

Defines allowed SKU power and timing parameters. PCODE will update the contents of this register.

MSR Address: 614h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:55	Package	-	-	Reserved.
54:48	Package	12h	RW	**PKG_MAX_WIN —** The maximal time window allowed for the SoC product SKU. Higher values will be clamped to this value. The unit of measurement is defined in PACKAGE_POWER_SKU_UNIT_MSRTIME_UNIT.
47	Package	-	-	Reserved.
46:32	Package	240h	RW	**PKG_MAX_PWR —** The maximal package power setting allowed for the SoC product SKU. Higher values will be clamped to this value. The maximum setting is typical not guaranteed. The default value for this field is determined by the SoC product SKU. The units for this value are defined in PACKAGE_POWER_SKU_MSRPWR_UNIT.
31	Package	-	-	Reserved.
30:16	Package	60h	RW	**PKG_MIN_PWR —** The minimal package power setting allowed for the SoC product SKU. Lower values will be clamped to this value. The minimum setting is typical not guaranteed. The default value for this field is determined by the SoC product SKU. The units for this value are defined in PACKAGE_POWER_SKU_MSRPWR_UNIT.
15	Package	-	-	Reserved.
14:0	Package	118h	RW	**PKG_TDP —** The package's Thermal Design Power (TDP) allowed for this part. The value is in the units identified in POWER_UNIT field in PACKAGE_POWER_SKU_UNIT (MSR 606h).

69.2.156 (615h) PPL3_CONTROL

PL3 Control MSR.

MSR Address: 615h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW_L	**LOCK —** Lock this MSR until next reset: 0 - unlocked 1 - locked
62:48	-	-	-	Reserved.
47	Package	0h	RW_L	**PL4_ENABLE —** Power Limit 4 Enable: 0 => Algorithm disabled 1 => Algorithm enabled
46:32	Package	0h	RW_L	**PMAX —** Power Limit 'PL4' or Pmax power limit in the units as described PACAKGE_POWER_SKU_UNIT MSR.
31	-	-	-	Reserved.
30:24	Package	0h	RW_L	**DUTY_CYCLE —** Expressed in percentage (%). Clipped to a max value of 100%.
23:17	Package	0h	RW_L	**TIME_WINDOW —** Duration over which duty cycle control will be maintained. (xxYYYY format)
16	-	-	-	Reserved.
15	Package	0h	RW_L	**PL3_ENABLE —** Power Limit 3 Enable: 0 => Algorithm disabled 1 => Algorithm enabled
14:0	Package	0h	RW_L	**POWER_LIMIT —** PL3 or PAppMax power level. A power reading above this will be interpreted as a violation (in increments of 1/8th Watt).

69.2.157 (618h) MSR_DRAM_POWER_LIMIT

RAPL power limit for the DDR domain. This register is written by platform software and read by the SoC once per 1 ms. There are actually two instances of this register: one with MSR access and one with MMIO access. There is a separate PECI command which is also analogous.

MSR Address: 618h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RW	**LOCKED —** When set this entire register becomes Read-Only. This bit will typically be set by BIOS during boot.
62:24	-	-	-	Reserved.
23:22	Package	0h	RW	**LIMIT1_TIME_WINDOW_X —** Power Limit0 time window X value for DDR domain. Actual time_window for RAPL is: 1/1024 seconds 1x/4 2y.
21:17	Package	0h	RW	**LIMIT1_TIME_WINDOW_Y —** Power Limit0 time window Y value for DDR domain. Actual time_window for RAPL is: 1/1024 seconds 1x/4 2y.
16	Package	-	-	Reserved.
15	Package	0h	RW	**LIMIT1_ENABLE —** Power Limit0 enable bit for DDR domain.
14:0	Package	0h	RW	**LIMIT1_POWER —** Power Limit0 for DDR domain. Units Watts Format11.3 Resolution0.125W Range02047.875W.

69.2.158 (61Ch) MSR_DRAM_POWER_INFO

This register defines allowed DRAM power and timing parameters, and provides DRAM power range information for RAPL usage. It is recommended to program "DRAM_POWER_INFO" CSR and leave MSR_DRAM_POWER_INFO unlocked for OS software to modify.

MSR Address: 61Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63	Package	0h	RO	**LOCK —** Lock bit to lock the Register.
62:55	-	-	-	Reserved.
54:48	Package	28h	RO	**DRAM_MAX_WIN —** The maximal time window allowed for the DRAM. Higher values will be clamped to this value. x = PKG_MAX_WIN[54:53] y = PKG_MAX_WIN[52:48] The timing interval window is Floating Point number given by 1.x*power(2,y). The unit of measurement is defined in DRAM_POWER_INFO_UNIT_MSR[TIME_UNIT].
47	-	-	-	Reserved.
46:32	Package	258h	RO	**DRAM_MAX_PWR —** The maximal power setting allowed for DRAM. Higher values will be clamped to this value. The maximum setting is typical (not guaranteed). The units for this value are defined in DRAM_POWER_INFO_UNIT_MSR[PWR_UNIT].
31	-	-	-	Reserved.
30:16	Package	78h	RO	**DRAM_MIN_PWR —** The minimal power setting allowed for DRAM. Lower values will be clamped to this value. The minimum setting is typical (not guaranteed). The units for this value are defined in DRAM_POWER_INFO_UNIT_MSR[PWR_UNIT].
15	-	-	-	Reserved.
14:0	Package	118h	RO	**DRAM_TDP —** The Spec power allowed for DRAM The TDP setting is typical (not guaranteed). The units for this value are defined in DRAM_POWER_INFO_UNIT_MSR[PWR_UNIT].

69.2.159 (633h) MSR_PKGC_IRTL3

The coordinated PackageAdditive above the core Interrupt Response Time is used for BIOS runtime control. This setting affects the selected package state. It is reflected to the IOS as part of the PM_REQ message for PMC usage as well. This register may be changed dynamically due to platform events AC/DC etc.The coordinated PackageAdditive above the core Interrupt Response Time is used for BIOS runtime control. This setting affects the selected package state. It is reflected to the IOS as part of the PM_REQ message for PMC usage as well. This register may be changed dynamically due to platform events AC/DC etc.

MSR Address: 633h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:16	Package	-	-	Reserved.
15	Package	0h	RW	**VALID —** This field qualifies the validity of the Value field in this register.
14:13	Package	-	-	Reserved.
12:10	Package	0h	RW	**MULTIPLIER —** This field indicates the unit of measurement that is defined for the Value field in this register.
9:0	Package	0h	RW	**VALUE —** The Interrupt Response Time Limit is given in units defined in the Multiplier field of this register.

69.2.160 (634h) MSR_PKGC_IRTL4

The coordinated PackageAdditive above the core Interrupt Response Time is used for BIOS runtime control. This setting affects the selected package state. It is reflected to the IOS as part of the PM_REQ message for PMC usage as well. This register may be changed dynamically due to platform events AC/DC etc.

MSR Address: 634h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:16	Package	-	-	Reserved.
15	Package	0h	RW	**VALID —** This field qualifies the validity of the Value field in this register.
14:13	Package	-	-	Reserved.
12:10	Package	0h	RW	**MULTIPLIER —** This field indicates the unit of measurement that is defined for the Value field in this register.
9:0	Package	0h	RW	**VALUE —** The Interrupt Response Time Limit is given in units defined in the Multiplier field of this register.

69.2.161 (635h) MSR_PKGC_IRTL5

The coordinated PackageAdditive above the core Interrupt Response Time is used for BIOS runtime control. This setting affects the selected package state. It is reflected to the IOS as part of the PM_REQ message for PMC usage as well. This register may be changed dynamically due to platform events AC/DC etc.

MSR Address: 635h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:16	Package	-	-	Reserved.
15	Package	0h	RW	**VALID —** This field qualifies the validity of the Value field in this register.
14:13	Package	-	-	Reserved.
12:10	Package	0h	RW	**MULTIPLIER —** This field indicates the unit of measurement that is defined for the Value field in this register.
9:0	Package	0h	RW	**VALUE —** The Interrupt Response Time Limit is given in units defined in the Multiplier field of this register.

69.2.162 (639h) MSR_PP0_ENERGY_STATUS

Reports total energy consumed. The counter will wrap around and continue counting when it reaches its limit. The energy status is reported in units which are defined in the ENERGY_UNIT field of MSR_RAPL_POWER_UNIT. Software will read this value and subtract the difference from last value read. The value of this register is updated every 1 ms.

MSR Address: 639h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Package	-	-	Reserved.
31:0	Package	0h	RO	**Total Energy Consumed —** The unsigned integer value represents the total amount of energy consumed since the last time this register was cleared. The unit of this field is specified by the ENERGY_UNIT field of MSR_RAPL_POWER_UNIT.

69.2.163 (641h) MSR_PP1_ENERGY_STATUS

Reports total energy consumed. The counter will wrap around and continue counting when it reaches its limit. The energy status is reported in units which are defined in the ENERGY_UNIT field of MSR_RAPL_POWER_UNIT. Software will read this value and subtract the difference from last value read. The value of this register is updated every 1 ms.

MSR Address: 641h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Package	-	-	Reserved.
31:0	Package	0h	RO	**Total Energy Consumed —** The unsigned integer value represents the total amount of energy consumed since the last time this register was cleared. The unit of this field is specified by the ENERGY_UNIT field of MSR_RAPL_POWER_UNIT.

69.2.164 (64Ch) MSR_TURBO_ACTIVATION_RATIO

This register is programmed by System BIOS to indicate the new maximum non-turbo ratio to be used by the processor. Attempts to write to this MSR when the PLATFORM_INFO[34:33] == 0 may result in a #GP fault.

MSR Address: 64Ch				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Package	-	-	Reserved.
31	Package	0h	RW_L	**TURBO_ACTIVATION_RATIO_LOCK —** When this bit is set it indicates that the contents of this register are locked. This bit is cleared only on a reset.
30:8	Package	-	-	Reserved.
7:0	Package	0h	RW_L	**MAX_NON_TURBO_RATIO —** System BIOS can program this field to indicate the new Max non turbo ratio (in units of 100 MHz). All P state requests above this ratio are considered as Max Turbo ratio request. Note: A value of 0 indicates that the feature is disabled.

69.2.165 (64Fh) MSR_CORE_PERF_LIMIT_REASONS

Interface to allow software to determine what is causing resolved frequency to be clamped below the requested frequency.

MSR Address: 64Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31	Package	0h	RW_0C	**QOS_LOG —** Set by the SoC and cleared by software.
30	Package	0h	RW_0C	**MAX_EFFICIENCY_FREQ_LOG —** Set by the SoC and cleared by software.
29	Package	0h	RW_0C	**MCT_LOG —** Set by the SoC and cleared by software.
28	Package	0h	RW_0C	**EDP_LOG —** Set by the SoC and cleared by software.
27	Package	0h	RW_0C	**MULTI_CORE_TURBO_LOG —** Set by the SoC and cleared by software.
26	Package	0h	RW_0C	**VR_THERMALERT_LOG —** Set by the SoC and cleared by software.
25	Package	0h	RW_0C	**IA_UTILIZATION_LOG —** Set by the SoC and cleared by software.
24	Package	0h	RW_0C	**DEV3_LOG —** Set by the SoC and cleared by software.
23	Package	0h	RW_0C	**DEV2_LOG —** Set by the SoC and cleared by software.
22:20	Package	-	-	Reserved.
19	Package	0h	RW_0C	**PL2_LOG —** Set by the SoC and cleared by software.
18	Package	0h	RW_0C	**PL1_LOG —** Set by the SoC and cleared by software.
17	Package	0h	RW_0C	**THERMAL_LOG —** Set by the SoC and cleared by software.
16	Package	0h	RW_0C	**PROCHOT_LOG —** Set by the SoC and cleared by software.
15	Package	0h	RO	**QOS_STATUS —** Frequency is limited below the operating system or driver Quality-of-Service floor.
14	Package	0h	RO	**MAX_EFFICIENCY_FREQ_STATUS —** Frequency is limited below the maximum efficiency frequency.
13	Package	0h	RO	**MCT_STATUS —** Frequency is limited due to ratio change transition attenuation (MCT, prevents frequent ratio changes due to core C-state entry/exit).
12	Package	0h	RO	**EDP_STATUS —** Frequency is limited due to a package-level EDP constraint.
11	Package	0h	RO	**MULTI_CORE_TURBO_STATUS —** Frequency is limited due to effective multi-core turbo constraints, if applicable.
10	Package	0h	RO	**VR_THERMALERT_STATUS — F**requency is limited due to a VR thermal excursion.
9	Package	0h	RO	**IA_UTILIZATION_STATUS —** Frequency is limited due to autonomous utilization-based P-state control, if supported.
8	Package	0h	RO	**DEV3_STATUS —** Frequency is limited due to Dev3 driver override.
7	Package	0h	RO	**DEV2_STATUS —** Frequency is limited due to Dev2 driver override.
6:4	Package	-	-	Reserved.
3	Package	0h	RO	**PL2_STATUS —** Frequency is limited due to a package-level PL2 excursion.
2	Package	0h	RO	**PL1_STATUS —** Frequency is limited due to a package-level PL1 excursion.
1	Package	0h	RO	**THERMAL_STATUS —** Frequency is limited due to thermal excursion.
0	Package	0h	RO	**PROCHOT_STATUS —** Frequency is limited due to external PROCHOT assertion, if supported.

69.2.166 (80Fh) IA32_X2APIC_SIVR

The spurious interrupt vector register has been extended for both legacy and extended xAPIC mode with a mechanism that enables software to perform directed EOIs to specific IOxAPICs in the system. Bit 12 of the spurious interrupt vector register controls the generation of the EOI broadcast. When this bit is set, broadcast EOIs will not be generated. Support for this feature can be detected by means of bit 24 in the Local xAPIC Version register. The feature is supported if this bit is set to 1.

MSR Address: 80Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:13	Thread	-	-	Reserved.
12	Thread	0h	RW	**DIRECTED_EOI_EN —** This bit controls the generation of the EOI broadcast. When this bit is set, broadcast EOIs will not be generated.
11:9	Thread	-	-	Reserved.
8	Thread	0h	RW	**SOFTWARE_ENABLE —** • 1 = enabled • 0 = disabled
7:0	Thread	0h	RW	**SPURIOUS_VECTOR —** Vector number of the spurious vector.

69.2.167 (828h) IA32_X2APIC_ESR

Extended xAPIC Error Status Register.

MSR Address: 828h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Thread	-	-	Reserved.
7	Thread	0h	RW	**ILLEGAL_REGISTER_ADDRESS —** APIC register access detected with an illegal address.
6	Thread	0h	RW	**RECEIVE_ILLEGAL_VECTOR —** Interrupt received with an illegal vector.
5	Thread	0h	RW	**SEND_ILLEGAL_VECTOR —** IPI with illegal vector attempted from ICR write.
4	Thread	0h	Rsvd0	**REDIRECTABLE_IPI —** IPI with illegal Low Priority delivery mode attempted from ICR write.
3	Thread	0h	Rsvd0	**RECEIVE_ACCEPT_ERROR —** Set when the local APIC detects that the message it received was not accepted by any APIC on the APIC bus, including itself.
2	Thread	0h	Rsvd0	**SEND_ACCEPT_ERROR —** Set when the local APIC detects that a message it sent was not accepted by any APIC on the APIC bus.
1	Thread	0h	Rsvd0	**RECEIVE_CHECKSUM_ERROR —** Set when the local APIC detects a checksum error for a message that it received on the APIC bus.
0	Thread	0h	Rsvd0	**SEND_CHECKSUM_ERROR —** Set when the local APIC detects a checksum error for a message that it sent on the APIC bus.

69.2.168 (82Fh) IA32_X2APIC_LVT_CMCI

The Corrected Machine Check Interrupt LVT Register is an extension of the xAPIC in both legacy and extended xAPIC modes.

MSR Address: 82Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:17	Thread	-	-	Reserved.
16	Thread	0h	RW	**MASK —** A value of 1 indicates that the interrupt is masked.
15:13	Thread	-	-	Reserved.
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11	Thread	-	-	Reserved.
10:8	Thread	0h	RW	**DELIVERY_MODE —** Delivery Mode: • 000b - Fixed priority • 001b - Lowest Priority • 010b - SMI • 011b - Reserved • 100b - NMI • 101b - INIT • 110b - Startup • 111b - Reserved
7:0	Thread	0h	RW	**VECTOR —** PIC Correctable MCA Interrupt Vector.

69.2.169 (830h) IA32_X2APIC_ICR

Extended xAPIC Interrupt Command Register.

MSR Address: 830h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	0h	RW	**DESTINATION_FIELD —** 32-bit destination ID of the IPI.
31:20	Thread	-	-	Reserved.
19:18	Thread	0h	RW	**DESTINATION_SHORTHAND —** Destination Shorthand: • 00b - No shorthand • 01b - Self • 10b - All including self • 11b - All excluding self
17:13	Thread	-	-	Reserved.
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11	Thread	0h	RW	**DESTINATION_MODE —** Destination Mode: • 0b - Physical • 1b - Logical
10:8	Thread	0h	RW	**DELIVERY_MODE —** Delivery Mode: • 000b - Fixed priority • 001b - Lowest Priority • 010b - SMI • 011b - Reserved • 100b - NMI • 101b - INIT • 110b - Startup • 111b - Reserved
7:0	Thread	0h	RW	**VECTOR —** 4-K aligned interrupt vector address.

69.2.170 (832h) IA32_X2APIC_LVT_TIMER

Extended xAPIC LVT Entry for the xAPIC Timer.

MSR Address: 832h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:19	Thread	-	-	Reserved.
18:17	Thread	0h	RW	**TIMER_MODE —** Timer mode: • 00b - One shot • 01b - Periodic • 10b - TSC Deadline • 11b - Reserved
16	Thread	0h	RW	**MASK —** Mask” • 0b - Not masked • 1b - Masked
15:13	Thread	-	-	Reserved.
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11:8	Thread	-	-	Reserved.
7:0	Thread	0h	RW	**VECTOR —** PIC Timer Interrupt Vector.

69.2.171 (833h) IA32_X2APIC_LVT_THERMAL

Extended xAPIC LVT Entry for the Thermal Interrupt.

MSR Address: 833h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:17	Thread	-	-	Reserved.
16	Thread	0h	RW	**MASK —** Mask” • 0b - Not masked • 1b - Masked
15:13	Thread	-	-	Reserved.
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11	Thread	-	-	Reserved.
10:8	Thread	0h	RW	**DELIVERY_MODE —** Delivery Mode: • 000b - Fixed priority • 001b - Lowest Priority • 010b - SMI • 011b - Reserved • 100b - NMI • 101b - INIT • 110b - Startup • 111b - Reserved
7:0	Thread	0h	RW	**VECTOR —** PIC Thermal Interrupt Vector.

69.2.172 (834h) IA32_X2APIC_LVT_PMI

Extended xAPIC LVT Entry for PerfMon Interrupt.

MSR Address: 834h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:17	Thread	-	-	Reserved.
16	Thread	0h	RW	**MASK —** Mask” • 0b - Not masked • 1b - Masked
15:13	Thread	-	-	Reserved.
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11	Thread	-	-	Reserved.
10:8	Thread	0h	RW	**DELIVERY_MODE —** Delivery Mode: • 000b - Fixed priority • 001b - Lowest Priority • 010b - SMI • 011b - Reserved • 100b - NMI • 101b - INIT • 110b - Startup • 111b - Reserved
7:0	Thread	0h	RW	**VECTOR —** PIC PerfMon Interrupt Vector.

69.2.173 (835h) IA32_X2APIC_LVT_LINT0

Extended xAPIC LVT Entry for Lint Pin 0 Interrupt.

MSR Address: 835h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:17	Thread	-	-	Reserved.
16	Thread	0h	RW	**MASK —** Mask” • 0b - Not masked • 1b - Masked
15	Thread	0h	RW	**TRIGGER_MODE —** Trigger Mode: • 0b - Edge • 1b - Level
14	Thread	0h	RO	**REMOTE_IRR —** For fixed mode, level-triggered interrupts this flag is set when the local APIC accepts the interrupt for servicing and is reset when an EOI command is received from the processor. The meaning of this flag is undefined for edge-triggered interrupts and other delivery modes.
13	Thread	0h	RW	**POLARITY —** 0: active high, 1: active low
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11	Thread	-	-	Reserved.
10:8	Thread	0h	RW	**DELIVERY_MODE —** Delivery Mode: • 000b - Fixed priority • 001b - Lowest Priority • 010b - SMI • 011b - Reserved • 100b - NMI • 101b - INIT • 110b - Startup • 111b - Reserved
7:0	Thread	0h	RW	**VECTOR —** PIC Lint Pin 0 Interrupt Vector.

69.2.174 (836h) IA32_X2APIC_LVT_LINT1

Extended xAPIC LVT Entry for Lint Pin 0 Interrupt.

MSR Address: 836h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:17	Thread	-	-	Reserved.
18:17	Thread	0h	Rsvd0	**TIMER_MODE —** fill description here
16	Thread	0h	RW	**MASK —** Mask” • 0b - Not masked • 1b - Masked
15	Thread	0h	RW	**TRIGGER_MODE —** Trigger Mode: • 0b - Edge • 1b - Level
14	Thread	0h	RO	**REMOTE_IRR —** For fixed mode, level-triggered interrupts this flag is set when the local APIC accepts the interrupt for servicing and is reset when an EOI command is received from the processor. The meaning of this flag is undefined for edge-triggered interrupts and other delivery modes.
13	Thread	0h	RW	**POLARITY —** 0: active high, 1: active low
12	Thread	0h	RO	**DELIVERY_STATUS —** Delivery Status: • 0b - Idle • 1b - Pending
11	Thread	-	-	Reserved.
10:8	Thread	0h	RW	**DELIVERY_MODE —** Delivery Mode: • 000b - Fixed priority • 001b - Lowest Priority • 010b - SMI • 011b - Reserved • 100b - NMI • 101b - INIT • 110b - Startup • 111b - Reserved
7:0	Thread	0h	RW	**VECTOR —** PIC Lint Pin 1 Interrupt Vector.

69.2.175 (837h) IA32_X2APIC_LVT_ERROR

Extended xAPIC LVT Entry for Error Interrupt.

MSR Address: 837h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:17	Thread	-	-	Reserved.
16	Thread	0h	RW	**MASK —** Mask” • 0b - Not masked • 1b - Masked
15:13	Thread	-	-	Reserved.
12	Thread	0h	RO	**DELIVERY_STATUS —** fill description here
11:8	Thread	-	-	Reserved.
7:0	Thread	0h	RW	**VECTOR —** PIC Error Interrupt Vector.

69.2.176 (838h) IA32_X2APIC_INIT_COUNT

Extended xAPIC Timer Initial Count register.

MSR Address: 838h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	-	-	Reserved.
31:0	Thread	0h	RW	**INIT_COUNT_REGISTER_VALUE —** APIC LVT Interrupt Timer Initial Count.

69.2.177 (839h) IA32_X2APIC_CUR_COUNT

Extended xAPIC Timer Current Count register.

MSR Address: 839h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	-	-	Reserved.
31:0	Thread	0h	RW	**CURRENT_COUNT_REGISTER_VALUE —** APIC LVT Interrupt Timer Current Count.

69.2.178 (83Eh) IA32_X2APIC_DIV_CONF

Extended xAPIC Timer Divide Config register.

MSR Address: 83Eh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:4	Thread	-	-	Reserved.
3	Thread	0h	RW	**CFGCNT_HI —** This corresponds to the value in the Divide Config Register in the APIC.
2	Thread	-	-	Reserved.
1:0	Thread	0h	RW	**CFGCNT_LO —** This corresponds to the value in the Divide Config Register in the APIC.

69.2.179 (83Fh) IA32_X2APIC_SELF_IPI

Extended xAPIC mode provides a new fast self IPI interface. System software only specifies the vector associated with the interrupt.

MSR Address: 83Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Thread	-	-	Reserved.
7:0	Thread	0h	RW	**VECTOR —** Self IPI Vector.

69.2.180 (C80h) IA32_DEBUG_FEATURE

Silicon Debug Feature Control.

MSR Address: C80h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Package	-	-	Reserved.
31	Package	0h	RO	**DEBUG_OCCURRED —** This "sticky bit" is set by hardware to indicate the status of bit 0. Default is 0.
30	Package	0h	RW	**LOCK —** If 1, locks any further change to the MSR. The lock bit is set automatically on the first SMI assertion even if not explicitly set by BIOS. Default is 0. Once set, the lock remains until a cold reset.
29:1	-	-	-	Reserved.
0	Package	0h	RW	**ENABLE —** BIOS sets this bit to 1 to enable Silicon Debug Features. Default is 0.

69.2.181 (C8Fh) IA32_PQR_ASSOC

Resource Association Register.

MSR Address: C8Fh				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:34	Core	-	-	Reserved.
33:32	Core	0h	RW	**COS —** COS Selector - core 0; It is programmed to specify which L2_QOS mask should apply to this logical processor.
31:0	Core	-	-	Reserved.

69.2.182 (D10h) IA32_L2_QOS_MASK_0

L2 Class Of Service Mask - COS 0.

MSR Address: D10h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Module	-	-	Reserved.
7:0	Module	0h	RW	**WAY_MASK —** Bit vector of available L2 ways for COS 0 enforcement. For a 512KB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 1 way. For a 1 MB and 2 MB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 2 way. So bit 0 corresponds to ways 0, 1. Bit 1 corresponds to ways 2, 3. And so on.

69.2.183 (D11h) IA32_L2_QOS_MASK_1

L2 Class Of Service Mask - COS 1.

MSR Address: D11h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Module	-	-	Reserved.
7:0	Module	0h	RW	**WAY_MASK —** Bit vector of available L2 ways for COS 1 enforcement. For a 512KB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 1 way. For a 1 MB and 2 MB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 2 way. So bit 0 corresponds to ways 0, 1. Bit 1 corresponds to ways 2, 3. And so on.

69.2.184 (D12h) IA32_L2_QOS_MASK_2

L2 Class Of Service Mask - COS 2.

MSR Address: D12h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Module	-	-	Reserved.
7:0	Module	0h	RW	**WAY_MASK —** Bit vector of available L2 ways for COS 2 enforcement. For a 512KB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 1 way. For a 1 MB and 2 MB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 2 way. So bit 0 corresponds to ways 0, 1. Bit 1 corresponds to ways 2, 3. And so on.

69.2.185 (D13h) IA32_L2_QOS_MASK_3

L2 Class Of Service Mask - COS 3.

MSR Address: D13h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:8	Module	-	-	Reserved.
7:0	Module	0h	RW	**WAY_MASK —** Bit vector of available L2 ways for COS 3 enforcement. For a 512KB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 1 way. For a 1 MB and 2 MB L2 cache, each bit in IA32_L2_QOS_MASK_*[7:0] corresponds to 2 way. So bit 0 corresponds to ways 0, 1. Bit 1 corresponds to ways 2, 3. And so on.

69.2.186 (D90h) IA32_BNDCFGS

Bound Configuration Supervisor State of Intel® Memory Protection Extensions (Intel® MPX) configuration.

MSR Address: D90h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:12	Thread	0h	RW	**ADDRESS_BD —** Base Address of Bound Directory.
11:2	Thread	-	-	Reserved.
1	Thread	0h	RW	**BNDPRESERVE —** Preserve the bounds registers for near branch instructions in the absence of the BND prefix.
0	Thread	0h	RW	**ENABLE —** Enable Intel® MPX in supervisor mode.

69.2.187 (DA0h) IA32_XSS

Extended Supervisor State Mask.

MSR Address: DA0h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:9	-	-	-	Reserved.
8	Thread	0h	RW	**RTIT —** Trace Packet Configuration State. This bit controls whether XSAVES/ XRSTORS can save/load RTIT state.
7:0	-	-	-	Reserved.

69.2.188 (C0000080h) IA32_EFER

Extended Feature Enable Register (EFER). This MSR may only be accessed when CPUID.(EAX=80000001h):EDX[20] or EDX[29] is set. Features of this register are to be enabled by the OS. BIOS may examine this register, but should not modify the contents of this register.

MSR Address: C0000080h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
31:12	Thread	-	-	Reserved.
11	Thread	0h	RW	**NXE —** Execute Disable Bit Enable. When set enables the Execute Disable Bit capability. This feature is only usable when the Physical Address Extension paging mechanism is engaged. The OS will control this bit, BIOS must not modify this bit.
10	Thread	0h	RW	**LMA —** IA-32e Mode Active (Long Mode Active). When set, the processor is in IA-32e mode (Long Mode) and is either running in compatibility mode or 64- bit mode. If LMA = 0 (Default), the processor is running in legacy mode and behaves like a standard 32-bit IA-32 processor.
9	Thread	-	-	Reserved.
8	Thread	0h	RW	**LME —** IA-32e Mode Enable (Long Mode Enable). When set enables the processor IA-32e mode operation. IA-32e mode is not activated until PAE mode paging is enabled. The OS will control this bit, BIOS must not modify this bit.
7:1	Thread	-	-	Reserved.
0	Thread	0h	RW	**SCE —** SYSCALL Enable. Enables SYSCALL/SYSRET instructions in 64-bit mode. It is the responsibility of the OS to enable SYSCALL/SYSRET for 64-bit operation. The OS will control this bit, BIOS must not modify this bit.

69.2.189 (C0000081h) IA32_STAR

System-Call Target Address Register (STAR). Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: C0000081h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:48	Thread	0h	RW	**SYSRET_CS_SS —** SYSRET CS and SS Selector.
47:32	Thread	0h	RW	**SYSCALL_CS_SS —** SYSCALL CS and SS Selector.
31:0	Thread	0h	RW	**SYSCALL_LEGACY_EIP —** SYSCALL legacy EIP Selector.

69.2.190 (C0000082h) IA32_LSTAR

IA-32e Mode System-Call Target Address Register. Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: C0000082h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**TARGET_RIP —** Target RIP for 64-bit Mode Calling Program.

69.2.191 (C0000083h) IA32_CSTAR

IA-32e Mode System-Call Target Address. Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: C0000083h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**SYSCALL_TARGET_ADDR —** IA-32e Mode System Call Target Address.

69.2.192 (C0000084h) IA32_FMASK

System-Call Flag Mask. Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: C0000084h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	-	-	Reserved.
31:0	Thread	0h	RW	**SYSCALL_FLAG_MASK —** System Call Flag Mask. If CPUID (EAX=80000001h):EDX[29] is set.

69.2.193 (C0000100h) IA32_FS_BASE

FS base MSR. Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: C0000100h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**FS_BASE —** Map of BASE Address of FS. If CPUID (EAX=80000001h):EDX[29] is set.

69.2.194 (C0000101h) IA32_GS_BASE

GS base MSR. Refer to the Intel® 64 and IA-32 Architectures Software Developer's Manual for a detailed description and usage of this MSR.

MSR Address: C0000101h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**GS_BASE —** Map of BASE Address of GS. If CPUID (EAX=80000001h):EDX[29] is set.

69.2.195 (C0000102h) IA32_KERNEL_GS_BASE

Swap Target of BASE Address of GS.

MSR Address: C0000102h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:0	Thread	0h	RW	**GS_BASE_SWAP_TARGET —** Swap Target of BASE Address of GS.

69.2.196 (C0000103h) IA32_TSC_AUX

Auxiliary Time-Stamp Counter (TSC).

MSR Address: C0000103h				
Bit	**Scope**	**Default**	**Attribute**	**Description**
63:32	Thread	-	-	Reserved.
31:0	Thread	0h	RW	**AUX —** Auxiliary signature of Time-Stamp Counter.

§ §

Mouser Electronics

Authorized Distributor

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

Intel:

HW8076502444202S R381 HW8076502444301S R3L7 HW8076502639302S R388 HW8076502639402S R389 HW8076502639602S R38B HW8076502639802S R38D HW8076503693501S R3JX

OCEAN CHIPS
Океан Электроники
Поставка электронных компонентов

Компания «Океан Электроники» предлагает заключение долгосрочных отношений при поставках импортных электронных компонентов на взаимовыгодных условиях!

Наши преимущества:

- Поставка оригинальных импортных электронных компонентов напрямую с производств Америки, Европы и Азии, а так же с крупнейших складов мира;
- Широкая линейка поставок активных и пассивных импортных электронных компонентов (более 30 млн. наименований);
- Поставка сложных, дефицитных, либо снятых с производства позиций;
- Оперативные сроки поставки под заказ (от 5 рабочих дней);
- Экспресс доставка в любую точку России;
- Помощь Конструкторского Отдела и консультации квалифицированных инженеров;
- Техническая поддержка проекта, помощь в подборе аналогов, поставка прототипов;
- Поставка электронных компонентов под контролем ВП;
- Система менеджмента качества сертифицирована по Международному стандарту ISO 9001;
- При необходимости вся продукция военного и аэрокосмического назначения проходит испытания и сертификацию в лаборатории (по согласованию с заказчиком);
- Поставка специализированных компонентов военного и аэрокосмического уровня качества (Xilinx, Altera, Analog Devices, Intersil, Interpoint, Microsemi, Actel, Aeroflex, Peregrine, VPT, Syfer, Eurofarad, Texas Instruments, MS Kennedy, Miteq, Cobham, E2V, MA-COM, Hittite, Mini-Circuits, General Dynamics и др.);

Компания «Океан Электроники» является официальным дистрибьютором и эксклюзивным представителем в России одного из крупнейших производителей разъемов военного и аэрокосмического назначения «**JONHON**», а так же официальным дистрибьютором и эксклюзивным представителем в России производителя высокотехнологичных и надежных решений для передачи СВЧ сигналов «**FORSTAR**».

AVIC JONHON

«JONHON» (основан в 1970 г.)

Разъемы специального, военного и аэрокосмического назначения:

(Применяются в военной, авиационной, аэрокосмической, морской, железнодорожной, горно- и нефтедобывающей отраслях промышленности)

«FORSTAR» (основан в 1998 г.)

ВЧ соединители, коаксиальные кабели, кабельные сборки и микроволновые компоненты:

(Применяются в телекоммуникациях гражданского и специального назначения, в средствах связи, РЛС, а так же военной, авиационной и аэрокосмической отраслях промышленности).

FORSTAR®

Телефон: 8 (812) 309-75-97 (многоканальный)
Факс: 8 (812) 320-03-32
Электронная почта: ocean@oceanchips.ru
Web: http://oceanchips.ru/
Адрес: 198099, г. Санкт-Петербург, ул. Калинина, д. 2, корп. 4, лит. А