# INTEGRATED CIRCUITS

# DATA SHEET



# **PCA9560**

Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

Product data sheet Supersedes data of 2003 Jun 27





# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

**PCA9560** 



#### **FEATURES**

- 5-bit 3-to-1 multiplexer, 1-bit latch DIP switch
- 5-bit external hardware pins
- Two 6-bit internal non-volatile registers, fully pin-to-pin compatible with PCA9559
- Selection between the two non-volatile registers
- Selection between non-volatile registers and external hardware pins
- I<sup>2</sup>C/SMBus interface logic
- Internal pull-up resistors on input pin and control signals
- Active high write protect on input controls the ability to write to the non-volatile registers
- 2 address pins, allowing up to 4 devices on the I<sup>2</sup>C-bus
- 5 open drain multiplexed outputs
- Open drain non-multiplexed output
- Internal 6-bit non-volatile registers programmable and readable via I<sup>2</sup>C-bus
- External hardware 5-bit value readable via I<sup>2</sup>C-bus
- Multiplexer selection can be overridden by I<sup>2</sup>C-bus
- Operating power supply voltage 3.0 V to 3.6 V
- 5 V and 2.5 V tolerant inputs/outputs
- 0 to 400 kHz clock frequency
- ESD protection exceeds 2000 V HBM per JESD22-A114, 200 V MM per JESD22-A115, and 1000 V CDM per JESD22-C101
- Latch-up testing is done to JESDEC Standard JESD78 which exceeds 100 mA.
- Package offering: SO20, TSSOP20

### **DESCRIPTION**

The PCA9560 is a 20-pin CMOS device consisting of two 6-bit non-volatile EEPROM registers, 5 hardware pin inputs and a 5-bit multiplexed output with one latched EEPROM bit. It is used for DIP switch-free or jumper-less system configuration and supports Mobile and Desktop VID Configuration, where 3 preset values (2 sets of internal non-volatile registers and 1 set of external hardware pins) set processor voltage for operation in either performance, deep sleep or deeper sleep modes. The PCA9560 is also useful in server and telecom/networking applications when used to replace DIP switches or jumpers, since the settings can be easily changed via I<sup>2</sup>C/SMBus without having to power down the equipment to open the cabinet. The non-volatile memory retains the most current setting selected before the power is turned off.

The PCA9560 typically resides between the CPU and Voltage Regulator Module (VRM) when used for CPU VID (Voltage

IDentification code) configuration. It is used to bypass the CPU-defined VID values and provide a different set of VID values to the VRM, if an increase in the CPU voltage is desired. An increase in CPU voltage combined with an increase in CPU frequency leads to a performance boost of up to 7.5%. Lower CPU voltage reduces power consumption. The main advantage of the PCA9560 over the older PCA9559 device in this application is that it contains two internal non-volatile EEPROM registers instead of just one, allowing three independent settings (performance operation, deep sleep mode and deeper sleep mode) instead of only two (performance operation and deep sleep mode). The PCA9560 is footprint compatible and a drop-in replacement for the PCA9559, without any software modifications required.

The PCA9560 has 2 address pins allow up to 4 devices to be placed on the same  $I^2C$  bus or SMBus.

### **PIN CONFIGURATION**




Figure 1. Pin configuration

### **PIN DESCRIPTION**

PIN	SYMBOL	FUNCTION
1	SCL	Serial I <sup>2</sup> C-bus clock
2	SDA	Serial bi-directional I <sup>2</sup> C-bus data
3	A1	Programmable LSBs of I <sup>2</sup> C
4	A0	address
5–9	MUX_IN A-E	External inputs to multiplexer
10	GND	Ground
11	MUX_ SELECT_0	Selects MUX_IN inputs or register contents for MUX_OUT outputs
12–16	MUX_OUT E-A	Open drain multiplexed outputs
17	NON-MUXED_ OUTPUT	Open drain output from non-volatile memory
18	MUX_ SELECT_1	Selects between the two non-volatile registers
19	WP	Active high non-volatile register write-protect input
20	$V_{DD}$	Power supply: +3.0 to +3.6 V

### ORDERING INFORMATION

PACKAGES	TEMPERATURE RANGE	ORDER CODE	TOPSIDE MARK	DRAWING NUMBER
20-Pin Plastic SO	−40 to +85 °C	PCA9560D	PCA9560D	SOT163-1
20-Pin Plastic TSSOP	–40 to +85 °C	PCA9560PW	PCA9560	SOT360-1

Standard packing quantities and other packaging data are available at www.philipslogic.com/packaging.

### **BLOCK DIAGRAM**




Figure 2. Block diagram

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

### **DEVICE ADDRESS**

Following a START condition the bus master must output the address of the slave it is accessing. The address of the PCA9560 is shown in Figure 3. To conserve power, no internal pull-up resistors are incorporated on the hardware selectable address pins and they must be pulled HIGH or LOW.

The last bit of the slave address byte defines the operation to be performed. When set to logic 1 a read is selected while a logic 0 selects a write operation.




Figure 3. Slave address

### **CONTROL REGISTER**

Following the successful acknowledgement of the slave address, the bus master will send a byte to the PCA9560, which will be stored in the control register. This register can be written and read via the  $I^2C$ -bus.




Figure 4. Control Register

### **CONTROL REGISTER DEFINITION**

Following the address and acknowledge bit with logic 0 in the read/write bit, the first byte written is the command byte. If the command byte is reserved and therefore not valid, it will not be acknowledged. Only valid command bytes will be acknowledged.

Table 1. Register Addresses

D7	D6	D5	D4	D3	D2	D1	D0	REGISTER NAME	TYPE	REGISTER FUNCTION
0	0	0	0	0	0	0	0	EEPROM 0	Read/Write	EEPROM byte 0 register
0	0	0	0	0	0	0	1	EEPROM 1	Read/Write	EEPROM byte 1 register
1	1	1	1	1	1	1	1	MUX_IN	Read	MUX_IN values register

Table 2. Commands

D7	D6	D5	D4	D3	D2	D1	D0	COMMAND
1	1	1	1	1	0	0	0	MUX_OUT from EEPROM byte 0
1	1	1	1	1	1	0	0	MUX_OUT from EEPROM byte 1
1	1	1	1	1	Х	1	0	MUX_OUT from MUX_IN
1	1	1	1	1	Х	Х	1	MUX_OUT from MUX_SELECT <sup>2</sup>

### NOTE:

- 1. All other combinations are reserved.
- 2. MUX\_SELECT pins select between MUX\_IN and EEPROM to MUX\_OUT.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

#### REGISTER DESCRIPTION

If the command byte is an EEPROM address, the next byte sent will be programmed into that EEPROM address on the following STOP condition, if the WP is logic 0. If more than one byte is sent sequentially, the second byte will be written in the other-volatile register, on the following STOP condition. If any more data bytes are sent after the second byte, they will not be acknowledged and no bytes will be written to the non-volatile registers. After a byte is read from or written to the EEPROM, the part automatically points to the next non-volatile register. If the command code was FFH, the MUX\_IN values are sent with the three MSBs padded with zeroes as shown below. If the command codes was 00H, then the non-volatile register 1 is sent, and if the command code was 01H, then the non-volatile register 1 is sent.

### **EEPROM Byte 0 Register**

	D7	D6	D5	D4	D3	D2	D1	D0
Write	Х	Х	Non-Muxed Data	EEPROM 0 Data E	EEPROM 0 Data D	EEPROM 0 Data C	EEPROM 0 Data B	EEPROM 0 Data A
Read	0	0	Non-Muxed Data	EEPROM 0 Data E	EEPROM 0 Data D	EEPROM 0 Data C	EEPROM 0 Data B	EEPROM 0 Data A
Default	0	0	0	0	0	0	0	0

### **EEPROM Byte 1 Register**

	D7	D6	D5	D4	D3	D2	D1	D0
Write	Х	Х	Non-Muxed Data	EEPROM 1 Data E	EEPROM 1 Data D	EEPROM 1 Data C	EEPROM 1 Data B	EEPROM 1 Data A
Read	0	0	Non-Muxed Data	EEPROM 1 Data E	EEPROM 1 Data D	EEPROM 1 Data C	EEPROM 1 Data B	EEPROM 1 Data A
Default	0	0	0	0	0	0	0	0

### MUX\_IN Register

	D7	D6	D5	D4	D3	D2	D1	D0
Read	0	0	0	MUX_IN Data E	MUX_IN Data D	MUX_IN Data C	MUX_IN Data B	MUX_IN Data A

If the command byte is a MUX command byte, any additional data bytes sent after the MUX command code will not be acknowledged. If the read/write bit in the address is a logic 1, then a read operation follows and the data sent out depends on the previously stored command code.

The MUX\_SELECT\_1 pin can function as the over-ride pin as on the PCA9559 if the non-volatile register 1 is left at all 0s.

The NON\_MUXED\_OUT pin is a latched output. It is latched when MUX\_SELECT\_0 = 1. It is transparent when the MUX\_SELECT\_0 = 0. The data sent out on the NON\_MUXED\_OUT output is the 6th most significant bit of the non-volatile register. Whether this comes from the non-volatile register 0 or non-volatile register 1 depends on the command code or the external mux-select pins.

After a valid  $I^2C$  write operation to the EEPROM, the part cannot be addressed via the  $I^2C$  for 3.6 ms. If the part is addressed prior to this time, the part will not acknowledge its address.

### NOTE:

To ensure data integrity, the non-volatile register must be internally write protected when V<sub>DD</sub> to the I<sup>2</sup>C bus is powered down or V<sub>DD</sub> to the component is dropped below normal operating levels.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C FEPROM DIP switch

PCA9560

### **CONVERSION FROM THE PCA9559 TO THE PCA9560**

The PCA9560 is a drop in replacement to the PCA9559 with no software modifications. The PCA9559 has only one MUX\_SELECT pin to choose between the MUX\_IN values and the single non-volatile register. Since the PCA9560 has two internal non-volatile registers, if Register 1 is left to all 0's (default condition) then the MUX\_SELECT\_1 pin can function the same as the PCA9559 OVERRIDE # pin and MUX\_SELECT\_0 pin can function the same as the PCA9559 MUX\_IN pin.

The PCA9560 can read the MUX\_IN\_X values via I<sup>2</sup>C that the PACA9559 cannot do. Another difference is that the MUX\_SELECT\_X control pins can be overridden by I<sup>2</sup>C. To replace the PCA9559 with the PCA9560, the function table for the MUX\_OUT outputs and the NON\_MUXED\_OUT output must stay the same and the MUX\_SELECT pin functions should not be overridden by I<sup>2</sup>C.

### **EXTERNAL CONTROL SIGNALS**

The Write Protect (WP) input is used to control the ability to write the content of the non-volatile registers. If the WP signal is logic 0, the I<sup>2</sup>C bus will be able to write the contents of the non-volatile registers. If the WP signal is logic 1, data will not be allowed to be written into the non-volatile registers. In this case, the slave address and the command code will be acknowledged but the following data bytes will not be acknowledged and the EEPROM is not updated.

The factory default for the contents of the non-volatile register are all logic 0. These stored values can be read or written using the I<sup>2</sup>C-bus (described in the next section).

The WP, MUX\_IN\*, MUX\_SELECT\_0, and MUX\_SELECT\_1 signals have internal pull-up resistors. See the DC and AC Characteristics for hysteresis and signal spike suppression figures.

### Function Table<sup>1</sup>

WP	MUX_SELECT_0	MUX_SELECT_1	COMMANDS
0	Х	Х	Write to the non-volatile registers through I <sup>2</sup> C bus allowed
1	Х	Х	Write to the non-volatile registers through I <sup>2</sup> C bus not allowed
×	0	1	MUX_OUT and NON_MUXED_OUT (transparent) from EEPROM byte 0
×	0	0	MUX_OUT and NON_MUXED_OUT (transparent) from EEPROM byte 1
×	1	1	MUX_OUT from MUX_IN inputs and NON_MUXED_OUT latched (from EEPROM 0)
Х	1	0	MUX_OUT from MUX_IN inputs and NON_MUXED_OUT latched (from EEPROM 1)

### NOTE:

### POWER-ON RESET (POR)

When power is applied to  $V_{DD}$ , an internal power-on reset holds the PCA9560 in a reset state until  $V_{DD}$  has reached  $V_{POR}$ . At that point, the reset condition is released and the PCA9560 volatile registers and I<sup>2</sup>C/SMBus state machine will initialize to their default states.

The MUX\_OUT and NON\_MUXED\_OUT pin values depend on:

- the MUX\_SELECT\_0 and MUX\_SELECT\_1 logic levels, selecting either the MUX\_IN input pins or one of the two 6-bit EEPROMs
- the previously stored values in the EEPROM registers/current MUX\_IN pin values as shown in the Function Table

<sup>1.</sup> This table is valid when not overridden by I<sup>2</sup>C control register.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

### CHARACTERISTICS OF THE I<sup>2</sup>C-BUS

The I<sup>2</sup>C-bus is for 2-way, 2-line communication between different ICs or modules. The two lines are a serial data line (SDA) and a serial clock line (SCL). Both lines must be connected to a positive supply via a pull-up resistor when connected to the output stages of a device. Data transfer may be initiated only when the bus is not busy.

### Bit transfer

One data bit is transferred during each clock pulse. The data on the SDA line must remain stable during the HIGH period of the clock pulse as changes in the data line at this time will be interpreted as control signals (see Figure 5).




Figure 5. Bit transfer

### Start and stop conditions

Both data and clock lines remain HIGH when the bus is not busy. A HIGH-to-LOW transition of the data line, while the clock is HIGH is defined as the start condition (S). A LOW-to-HIGH transition of the data line while the clock is HIGH is defined as the stop condition (P) (see Figure 6).

### System configuration

A device generating a message is a 'transmitter', a device receiving is the 'receiver'. The device initiates a transfer is the 'master' and the devices which are controlled by the master are the 'slaves' (see Figure 7).




Figure 6. Definition of start and stop conditions




Figure 7. System configuration

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

### **Acknowledge**

The number of data bytes transferred between the start and the stop conditions from transmitter to receiver is not limited. Each byte of eight bits is followed by one acknowledge bit. The acknowledge bit is a HIGH-level put on the bus by the transmitter whereas the master generates an extra acknowledge related clock pulse.

A slave receiver which is addressed must generate an acknowledge after the reception of each byte. Also a master must generate an acknowledge after the reception of each byte that has been clocked out of the slave transmitter. The device that acknowledges has to pull down the SDA line during the acknowledge clock pulse, so that the SDA line is stable LOW during the HIGH period of the acknowledge related clock pulse, set-up and hold times must be taken into account.

A receiver must signal an end of data to the transmitter by not generating an acknowledge on the last byte that has been clocked out of the slave. In this event, the transmitter must leave the data line HIGH to enable the master to generate a stop condition.




Figure 8. Acknowledgement on the I<sup>2</sup>C-bus

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

#### **Bus Transactions**

Data is transmitted to the PCA9560 registers using Write Byte transfers (see Figures 9 and 10). Data is read from the PCA9560 registers using Read and Receive Byte transfers (see Figure 11).




Figure 9. WRITE on 1 EEPROM — assuming WP = 0




Figure 10. WRITE on 2 EEPROMs — assuming WP = 0




Figure 11. READ MUX\_IN register

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

## ABSOLUTE MAXIMUM RATINGS1, 2

In accordance with the Absolute Maximum Rating System (IEC 134)

Voltages are referenced to GND (ground = 0 V)

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
$V_{DD}$	DC supply voltage		-0.5 to +4.0	V
V <sub>IN</sub>	DC input voltage	Note 3	-0.5 to +5.5	V
V <sub>OUT</sub>	DC output voltage	Note 3	-0.5 to +5.5	V
T <sub>stg</sub>	Storage temperature range		-60 to +150	°C

- 1. Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.
- 2. The performance capability of a high-performance integrated circuit in conjunction with its thermal environment can create junction temperatures which are detrimental to reliability. The maximum junction temperature of this integrated circuit should not exceed 150°C.

  3. The maximum input or output voltage is the lesser of 5.5 V or V<sub>DD</sub> + 4.0 V, except for very short (e.g., system start-up or shut-down)

### RECOMMENDED OPERATING CONDITIONS

CVMDOL	DADAMETE	in.	CONDITIONS	LIM	ITS	UNIT
SYMBOL	PARAMETE	:K	CONDITIONS	MIN	MAX	UNII
V <sub>DD</sub>	DC supply voltage		_	3.0	3.6	V
V <sub>IL</sub>	LOW-level input voltage	SCL, SDA	I <sub>OL</sub> = 3 mA	-0.5	0.9	V
V <sub>IH</sub>	HIGH-level input voltage	SCL, SDA	I <sub>OL</sub> = 3 mA	2.7	5.5 <sup>1</sup>	V
V	LOWI and advisor as to a t		I <sub>OL</sub> = 3 mA	_	0.4	V
V <sub>OL</sub>	LOW-level output voltage	SCL, SDA	I <sub>OL</sub> = 6 mA	_	0.6	V
V <sub>IL</sub>	LOW-level input voltage	MUX_IN, MUX_SELECT_0, MUX_SELECT_1	_	-0.5	0.8	V
V <sub>IH</sub>	HIGH-level input voltage	MUX_IN, MUX_SELECT_0, MUX_SELECT_1	_	2.0	5.5 <sup>1</sup>	V
l <sub>OL</sub>	LOW-level output current	MUX_OUT, NON_MUXED_OUT	_	_	8	mA
Іон	HIGH-level output current	MUX_OUT, NON_MUXED_OUT			100	μΑ
dt/dv	Input transition rise or fall time	dt/dv	_	0	10	ns/V
T <sub>amb</sub>	Operating ambient temperature	T <sub>amb</sub>	_	-40	85	°C

<sup>1.</sup> The maximum input voltage is the lesser of 5.5 V or V<sub>DD</sub> + 4.0 V, except for very short (e.g., system start-up or shut-down) durations.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

### **DC CHARACTERISTICS**

SYMBOL	PARAMETER	TEST CONDITION		UNIT		
STWBUL	PARAMETER	TEST CONDITION	MIN.	TYP.	MAX.	וואט
Supply				•	•	
V <sub>DD</sub>	Supply voltage		3	_	3.6	V
I <sub>DDL</sub>	Supply current	Operating mode ALL inputs = 0 V	<u> </u>	_	1	mA
I <sub>DDH</sub>	Supply current	Operating mode ALL inputs = V <sub>DD</sub>	<u> </u>	_	600	μА
V <sub>POR</sub>	Power-on reset voltage	No load; V <sub>I</sub> = V <sub>DD</sub> or GND	-	2.3	2.7	V
Input SCL:	Input/Output SDA					
V <sub>IL</sub>	LOW-level input voltage		-0.5	_	0.8	V
V <sub>IH</sub>	HIGH-level input voltage		2	_	5.5 <sup>1</sup>	V
I <sub>OL</sub>	LOW-level output current	V <sub>OL</sub> = 0.4 V	3	_	_	mA
I <sub>OL</sub>	LOW-level output current	V <sub>OL</sub> = 0.6 V	6	_	_	mA
I <sub>IH</sub>	Leakage current HIGH	$V_I = V_{DD}$	-1	_	1	μΑ
I <sub>IL</sub>	Input current LOW	V <sub>I</sub> = GND	-1	_	1	μΑ
C <sub>I</sub>	Input capacitance		_	3	6	pF
WP, MUX_S	SELECT_0, MUX_SELECT_1					
I <sub>IH</sub>	Leakage current HIGH	$V_I = V_{DD}$	-1	<u> </u>	1	μΑ
I <sub>IL</sub>	Input current LOW	V <sub>DD</sub> = 3.6 V; V <sub>I</sub> = GND	-20	_	-50	μА
C <sub>I</sub>	Input capacitance		<u> </u>	2.5	5	pF
MUX_IN A	→ E					
I <sub>IH</sub>	Leakage current HIGH	$V_I = V_{DD}$	-1	_	1	μΑ
I <sub>IL</sub>	Input current LOW	V <sub>DD</sub> = 3.6 V; V <sub>I</sub> = GND	-20	_	-50	μΑ
Cl	Input capacitance		_	2.5	5	pF
A0, A1 Inpu	ıts					•
I <sub>IH</sub>	Leakage current HIGH	$V_I = V_{DD}$	-1	_	1	μА
I <sub>IL</sub>	Input current LOW	V <sub>DD</sub> = 3.6 V; V <sub>I</sub> = GND	-20	_	-50	μΑ
C <sub>I</sub>	Input capacitance		_	2	4	pF
MUX_OUT				_		
V <sub>OL</sub>	LOW-level output voltage	I <sub>OL</sub> = 100 μA	<u> </u>	_	0.4	V
V <sub>OL</sub>	LOW-level output voltage	I <sub>OL</sub> = 4 mA	-	_	0.7	V
I <sub>OH</sub>	HIGH-level output current	$V_{OH} = V_{DD}$	1 –	_	100	μΑ
NON-MUXE	D_OUT		•	•	•	•
V <sub>OL</sub>	LOW-level output voltage	I <sub>OL</sub> = 100 μA	T -	_	0.4	V
V <sub>OL</sub>	LOW-level output voltage	I <sub>OL</sub> = 2 mA	1 –		0.7	V

### NOTE:

## **NON-VOLATILE STORAGE SPECIFICATIONS**

PARAMETER	SPECIFICATION		
Memory cell data retention	10 years min		
Number of memory cell write cycles	100,000 cycles min		

Application Note AN250 I2C DIP Switch provides additional information on memory cell data retention and the minimum number of write cycles.

<sup>1.</sup> The maximum input voltage is the lesser of 5.5 V or  $V_{DD}$  + 4.0 V, except for very short (e.g., system start-up or shut-down) durations.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

### **SAC CHARACTERISTICS**

SYMBOL	PARAMETER		LINUT		
STWBUL	PARAMETER	MIN.	TYP.	MAX.	UNIT
MUX_IN ⇒ MUX	OUT				
t <sub>PLH</sub>	LOW-to-HIGH transition time	_	28	40	ns
t <sub>PHL</sub>	HIGH-to-LOW transition time	_	8	15	ns
$\textbf{Select} \Rightarrow \textbf{MUX\_C}$	DUT				
t <sub>PLH</sub>	LOW-to-HIGH transition time	_	30	43	ns
t <sub>PHL</sub>	HIGH-to-LOW transition time	_	10	15	ns
t <sub>R</sub>	Output rise time	1.0	_	3	ns/V
t <sub>F</sub>	Output fall time	1.0	_	3	ns/V
C <sub>L</sub>	Test load capacitance on outputs	_	_	50	pF
Select ⇒ NON-N	IUXED_OUT				
t <sub>PLH</sub>	LOW-to-HIGH transition time	_	30	40	ns
t <sub>PHL</sub>	HIGH-to-LOW transition time	_	9	15	ns

## **AC SPECIFICATIONS**

SYMBOL	PARAMETER	STANDAF I <sup>2</sup> C-l		FAST MO	UNITS	
		MIN	MAX	MIN	MAX	
f <sub>SCL</sub>	Operating frequency	0	100	0	400	kHz
t <sub>BUF</sub>	Bus free time between STOP and START conditions	4.7	_	1.3	_	μs
t <sub>HD;STA</sub>	Hold time after (repeated) START condition	4.0	_	0.6	_	μs
t <sub>SU;STA</sub>	Repeated START condition setup time	4.7	_	0.6	_	μs
tsu;sto	Set-up time for STOP condition	4.0	_	0.6	_	μs
t <sub>HD;DAT</sub>	Data in hold time	0	_	0	_	ns
t <sub>VD;ACK</sub>	Valid time for ACK condition <sup>2</sup>	0.3	3.45	0.1	0.9	μs
t <sub>VD;DAT</sub>	Data out valid time <sup>3</sup>	300	_	50	_	ns
t <sub>SU;DAT</sub>	Data set-up time	250	_	100	_	ns
t <sub>LOW</sub>	Clock LOW period	4.7	_	1.3	_	μs
tHIGH	Clock HIGH period	4.0	_	0.6	_	μs
t <sub>F</sub>	Clock/Data fall time	_	300	20 + 0.1 C <sub>b</sub> <sup>1</sup>	300	ns
t <sub>R</sub>	Clock/Data rise time	_	1000	20 + 0.1 C <sub>b</sub> <sup>1</sup>	300	ns
t <sub>SP</sub>	Pulse width of spikes that must be suppressed by the input filters	_	50	_	50	ns

## NOTES:

C<sub>b</sub> = total capacitance of one bus line in pF.
 t<sub>VD;ACK</sub> = time for Acknowledgement signal from SCL LOW to SDA (out) LOW.
 t<sub>VD;DAT</sub> = minimum time for SDA data out to be valid following SCL LOW.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560




Figure 12. Definition of timing




Figure 13. Open drain output enable and disable times





Figure 14. Test circuit

# SO20: plastic small outline package; 20 leads; body width 7.5 mm

SOT163-1



# DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	А3	bp	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	v	w	у	z <sup>(1)</sup>	θ
mm	2.65	0.3 0.1	2.45 2.25	0.25	0.49 0.36	0.32 0.23	13.0 12.6	7.6 7.4	1.27	10.65 10.00	1.4	1.1 0.4	1.1 1.0	0.25	0.25	0.1	0.9 0.4	8°
inches	0.1	0.012 0.004	0.096 0.089	0.01	0.019 0.014	0.013 0.009	0.51 0.49	0.30 0.29	0.05	0.419 0.394	0.055		0.043 0.039	0.01	0.01	0.004	0.035 0.016	0°


### Note


1. Plastic or metal protrusions of 0.15 mm (0.006 inch) maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE			
VERSION	IEC	JEDEC	JEITA		PROJECTION	1550E DATE	
SOT163-1	075E04	MS-013				<del>-99-12-27</del> 03-02-19	

TSSOP20: plastic thin shrink small outline package; 20 leads; body width 4.4 mm

SOT360-1





detail X

## DIMENSIONS (mm are the original dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	1.1	0.15 0.05	0.95 0.80	0.25	0.30 0.19	0.2 0.1	6.6 6.4	4.5 4.3	0.65	6.6 6.2	1	0.75 0.50	0.4 0.3	0.2	0.13	0.1	0.5 0.2	8° 0°

### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ICCUE DATE			
VERSION	IEC	JEDEC	JEITA		PROJECTION	ISSUE DATE	
SOT360-1		MO-153				<del>-99-12-27</del> 03-02-19	

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560

# **REVISION HISTORY**

Rev	Date	Description
_4	20040519	Product data sheet (9397 750 13154). Supersedes data of 2003 Jun 27 (9397 750 11676).
		Modifications:
		● Features section, 16 <sup>th</sup> bullet: from "inputs" to "inputs/outputs"
		<ul> <li>Absolute maximum ratings table: V<sub>DD</sub>, V<sub>IN</sub>, and V<sub>OUT</sub> limits modified. Note 3 re-written.</li> </ul>
		Recommended operating conditions
		<ul> <li>V<sub>IH</sub> max. (on SCL, SDA) changed from 4.0 V to 5.5 V (with Note 1 added).</li> </ul>
		<ul> <li>V<sub>IH</sub> max. (on MUX_IN, MUX_SELECT_0, MUX_SELECT_1) changed from 4.0 V to 5.5 V (with Note 1 added).</li> </ul>
		• DC characteristics table: Input SCL: Input/Output SDA; VIH parameter max. limit modified, and Note 1 added.
_3	20030627	Product data (9397 750 11676); ECN 853-2286 29936 dated 19 May 2003. Supersedes data of 2002 May 24 (9397 750 09892).
_2	20020524	Product data (9397 750 09892); ECN 853-2286 28310 of 24 May 2002.

# Dual 5-bit multiplexed 1-bit latched I<sup>2</sup>C EEPROM DIP switch

PCA9560



Purchase of Philips  $I^2C$  components conveys a license under the Philips'  $I^2C$  patent to use the components in the  $I^2C$  system provided the system conforms to the  $I^2C$  specifications defined by Philips. This specification can be ordered using the code 9398 393 40011.

#### Data sheet status

Level	Data sheet status [1]	Product status <sup>[2] [3]</sup>	Definitions
I	Objective data sheet	Development	This data sheet contains data from the objective specification for product development.  Philips Semiconductors reserves the right to change the specification in any manner without notice.
II	Preliminary data sheet	Qualification	This data sheet contains data from the preliminary specification. Supplementary data will be published at a later date. Philips Semiconductors reserves the right to change the specification without notice, in order to improve the design and supply the best possible product.
III	Product data sheet	Production	This data sheet contains data from the product specification. Philips Semiconductors reserves the right to make changes at any time in order to improve the design, manufacturing and supply. Relevant changes will be communicated via a Customer Product/Process Change Notification (CPCN).

- [1] Please consult the most recently issued data sheet before initiating or completing a design.
- [2] The product status of the device(s) described in this data sheet may have changed since this data sheet was published. The latest information is available on the Internet at URL http://www.semiconductors.philips.com.
- [3] For data sheets describing multiple type numbers, the highest-level product status determines the data sheet status.

### **Definitions**

**Short-form specification** — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

Limiting values definition — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 60134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

Application information — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

### **Disclaimers**

Life support — These products are not designed for use in life support appliances, devices, or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes in the products—including circuits, standard cells, and/or software—described or contained herein in order to improve design and/or performance. When the product is in full production (status 'Production'), relevant changes will be communicated via a Customer Product/Process Change Notification (CPCN). Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

### **Contact information**

For additional information please visit

http://www.semiconductors.philips.com. Fax: +31 40 27 24825

For sales offices addresses send e-mail to: sales.addresses@www.semiconductors.philips.com

© Koninklijke Philips Electronics N.V. 2004 All rights reserved. Printed in U.S.A.

Date of release: 05-04

Document order number: 9397 750 13154

Let's make things better.

Philips Semiconductors







Компания «Океан Электроники» предлагает заключение долгосрочных отношений при поставках импортных электронных компонентов на взаимовыгодных условиях!

### Наши преимущества:

- Поставка оригинальных импортных электронных компонентов напрямую с производств Америки, Европы и Азии, а так же с крупнейших складов мира;
- Широкая линейка поставок активных и пассивных импортных электронных компонентов (более 30 млн. наименований);
- Поставка сложных, дефицитных, либо снятых с производства позиций;
- Оперативные сроки поставки под заказ (от 5 рабочих дней);
- Экспресс доставка в любую точку России;
- Помощь Конструкторского Отдела и консультации квалифицированных инженеров;
- Техническая поддержка проекта, помощь в подборе аналогов, поставка прототипов;
- Поставка электронных компонентов под контролем ВП;
- Система менеджмента качества сертифицирована по Международному стандарту ISO 9001;
- При необходимости вся продукция военного и аэрокосмического назначения проходит испытания и сертификацию в лаборатории (по согласованию с заказчиком);
- Поставка специализированных компонентов военного и аэрокосмического уровня качества (Xilinx, Altera, Analog Devices, Intersil, Interpoint, Microsemi, Actel, Aeroflex, Peregrine, VPT, Syfer, Eurofarad, Texas Instruments, MS Kennedy, Miteq, Cobham, E2V, MA-COM, Hittite, Mini-Circuits, General Dynamics и др.);

Компания «Океан Электроники» является официальным дистрибьютором и эксклюзивным представителем в России одного из крупнейших производителей разъемов военного и аэрокосмического назначения «JONHON», а так же официальным дистрибьютором и эксклюзивным представителем в России производителя высокотехнологичных и надежных решений для передачи СВЧ сигналов «FORSTAR».



**«JONHON»** (основан в 1970 г.)

Разъемы специального, военного и аэрокосмического назначения:

(Применяются в военной, авиационной, аэрокосмической, морской, железнодорожной, горно- и нефтедобывающей отраслях промышленности)

«**FORSTAR**» (основан в 1998 г.)

ВЧ соединители, коаксиальные кабели, кабельные сборки и микроволновые компоненты:

(Применяются в телекоммуникациях гражданского и специального назначения, в средствах связи, РЛС, а так же военной, авиационной и аэрокосмической отраслях промышленности).



Телефон: 8 (812) 309-75-97 (многоканальный)

Факс: 8 (812) 320-03-32

Электронная почта: ocean@oceanchips.ru

Web: http://oceanchips.ru/

Адрес: 198099, г. Санкт-Петербург, ул. Калинина, д. 2, корп. 4, лит. А